

## 12.0 Drainage

The Contractor shall evaluate all existing cross drains, storm drains, and seep lines within the Project that will receive new heat tape for condition and performance and submit a list of facilities to be cleaned to CDOT for Approval. All impacted seep and drainage facilities shall be cleaned prior to Final Acceptance. Any cleaning prior to Final Acceptance shall be compensated in accordance with Book 1, Section 13.7 Time and Materials Change. The Contractor shall notify CDOT prior to performing any required culvert cleaning to allow CDOT personnel to observe and document all work and equipment associated with the culvert cleaning.