

Colorado Department Of Transportation
Notice To Contractors

Printed On: 01/10/2020

Read Order No. 006
Letting Date: January 23, 2020 10:00 AM
Region: 5
Counties: MINERAL,
RIO GRANDE

Contract ID: C22422
Contract UDBE Goal: 7.00 %
Guaranty: 5% of Total Bid
For Plans and Specs go to <http://cdot.dbesystem.com>
Work Days: 54
Res. 5111 Arthur Forrest Miller 719-587-6501

Projects: NHPP1602-169

Contract Description:

THIS PROJECT IS LOCATED ON US HIGHWAY 160 IN MINERAL AND RIO GRANDE COUNTIES BETWEEN MILEPOSTS 174.38 AND 185. THE WORK CONSISTS OF A 1" HMA LEVELING COURSE, 1.5" HMA OVERLAY, GUARDRAIL REPLACEMENT, CONCRETE CURBING, AGGREGATE BASE COURSE SHOULDERING, REPLACING FADED SIGN PANELS, INLAID STRIPING, TRAFFIC CONTROL, AND EROSION CONTROL.

Please register at cdot.dbesystem.com where plans and specs can be found in the "my bid solicitations" menu. 12/5/2019

One Publication: 12/5/2019

It is estimated that the total cost of all items in the bid will be:

- Between \$0 and \$1,000,000
- Between \$1,000,000 and \$5,000,000
- Between \$5,000,000 and \$20,000,000
- Greater than \$20,000,000

Item No.	Description	Quantity	Units
	Major Items		
202-00240	Removal of Asphalt Mat (Planing)	3,001.000	SY
202-01130	Removal of Guardrail Type 3	8,366.000	LF
212-00006	Seeding (Native)	0.500	ACRE
304-09014	Aggregate Base Course (Special)	4,043.000	TON
403-00720	Hot Mix Asphalt (Patching) (Asphalt)	337.000	TON
403-00721	Hot Mix Asphalt (Patching) (Asphalt)	100.000	SY
403-34731	Hot Mix Asphalt (Grading SX) (75) (PG 58-34)	21,004.000	TON
403-36721	Hot Mix Asphalt (Grading ST)(75)(PG 58-28)	15,009.000	TON
411-10255	Emulsified Asphalt (Slow-Setting)	23,741.000	GAL
606-00302	Guardrail Type 3 (31 Inch Midwest Guardrail System)	7,557.000	LF
606-01385	Transition Type 3J	2.000	EACH
606-01390	End Anchorage Type 3K	1.000	EACH
606-01460	Median Terminal	4.000	EACH
606-02003	End Anchorage (Nonflared)	26.000	EACH

Item No.	Description	Quantity	Units
	Major Items		
614-80385	Rumble Strip	900.000	LF
620-00002	Field Office (Class 2)	1.000	EACH
620-00012	Field Laboratory (Class 2)	1.000	EACH
626-00000	Mobilization	1.000	L S
627-00013	Pavement Marking Paint (High Build)	2,710.000	GAL
627-00019	Pavement Marking Paint (High Build)(Inlaid)	1,485.000	GAL
627-30105	Pavement Marking Paint (Word-Symbol)	1,307.000	SF
627-30410	Preformed Thermoplastic Pavement Marking (Xwalk- Stop Line)	760.000	SF
630-00000	Flagging	3,000.000	HOUR
630-00012	Traffic Control Management	54.000	DAY