

Colorado Department of Transportation

Standard Specifications
for
Road and Bridge
Construction



COLORADO

Department of Transportation

2019

Colorado Department of Transportation

**Standard Specifications
for
Road and Bridge Construction**



2019

PREFACE

These standard specifications are to be used on contract work awarded by the Colorado Department of Transportation (CDOT). They may be supplemented or modified to suit specific contracts.

These specifications are expressed in United States Standard Measure (English units). The international System of Units (SI, Modernized Metric) is used only where standardized testing requires metric units. For clarity, aggregate sieve sizes appear in both SI and English Units. The dimensions, measurements, and requirements stated in English units are the specification requirements. All Contractor submittals shall be prepared in English Units. Pay item quantities will be measured in English units.

Unless otherwise identified, forms herein referred to (e.g. Form 605) are CDOT forms. Forms from other organizations or agencies are clearly identified (e.g. FHWA Form 1273).

Use of these specifications by any other organization or individual will be at the user's risk. Organizations or individuals citing these specifications by reference in their contract work will be responsible for furnishing prospective bidders copies of the specifications along with any addenda that may affect their contract.

Addenda to these specifications may be issued by the Department to suit its needs. Addenda may be accessed on the CDOT website.

TABLE OF CONTENTS

	Page
Division 100 General Provisions	1-1
Section 101 Definitions and Terms	1-1
Section 102 Bidding Requirements and Conditions	1-9
102.01 Prequalification of Bidders.....	1-9
102.02 Contents of Proposal Forms.	1-9
102.03 Interpretation of Quantities in Proposal Form.....	1-9
102.04 Interpretation of Plans and Specifications.....	1-9
102.05 Examination of Plans, Specifications, Special Provisions, and Site of Work.....	1-9
102.06 Preparation of Proposal.	1-10
102.07 Irregular Proposals.	1-10
102.08 Combination or Conditional Proposals.	1-10
102.09 Anti-Collusion Affidavit.	1-10
102.10 Material Guaranty.....	1-10
Section 103 Award and Execution of Contract	1-11
103.01 Consideration of Proposals.....	1-11
103.02 Award of Contract.	1-11
103.03 Requirement of Contract Bonds.....	1-11
103.04 Execution and Approval of Contract.....	1-11
Section 104 Scope of Work.....	1-12
104.01 Intent of Contract.	1-12
104.02 Differing Site Conditions, Suspensions of Work, and Significant Changes in the Character of Work.....	1-12
104.03 Extra Work.	1-13
104.04 Maintaining Traffic.	1-13
104.05 Rights in and Use of Materials Found on the Work.	1-13
104.06 Final Cleaning Up.	1-13
104.07 Value Engineering Change Proposals by the Contractor.	1-14
Section 105 Control of Work	1-18
105.01 Authority of the Engineer.....	1-18
105.02 Plans, Shop Drawings, Working Drawings, Other submittals, and Construction Drawings.....	1-18
105.03 Conformity to the Contract.	1-20
105.04 Conformity to the Contract of Superpave Performance Graded Binders.....	1-25
105.05 Conformity to the Contract of Hot Mix Asphalt.	1-25
105.06 Conformity to the Contract of Portland Cement Concrete Pavement.....	1-29
105.07 Conformity to Roadway Smoothness Criteria.....	1-33
105.09 Coordination of Plans, Specifications, Supplemental Specifications, and Special Provisions.....	1-38
105.10 Cooperation by Contractor.	1-38
105.11 Cooperation with Utilities.	1-39
105.12 Cooperation Between Contractors.....	1-39
105.13 Construction Stakes, Lines and Grades.	1-39
105.14 Authority and Duties of the Project Engineer.....	1-40
105.15 Duties of the Inspector.	1-40
105.16 Inspection and Testing of Work.....	1-40
105.17 Removal of Unacceptable Work and Unauthorized Work.....	1-41
105.18 Load Restrictions.	1-41
105.19 Maintenance During Construction.	1-42
105.20 Failure to Maintain Roadway or Structure.	1-42
105.21 Acceptance.	1-42
105.22 Dispute Resolution.	1-42
105.23 Dispute Review Board.	1-45
105.24 Claims for Unresolved Disputes.....	1-51

Section 106 Control of Material.....	1-70
106.01 Source of Supply and Quality Requirements.	1-70
106.02 Material Sources.....	1-70
106.03 Samples, Tests, Cited Specifications.	1-71
106.04 Qualification of Testing Personnel and Laboratories.	1-71
106.05 Sampling and Testing of Hot Mix Asphalt.	1-71
106.06 Sampling and Testing of Portland Cement Concrete Paving.....	1-77
106.07 Material Inspection at Plant.....	1-81
106.08 Storage of Materials.	1-82
106.09 Handling Materials.	1-82
106.10 Department Furnished Materials.	1-82
106.11 Buy America Requirements.....	1-82
106.12 Certificates of Compliance.	1-83
106.13 Certified Test Report.	1-83
Section 107 Legal Relations and Responsibility to Public.....	1-85
107.01 Laws to be Observed.	1-85
107.02 Permits, Licenses, and Taxes.	1-85
107.03 Patented Devices, Materials, and Processes.	1-85
107.04 Restoration of Surfaces Opened by Permit.....	1-85
107.05 Federal Aid Provisions.	1-85
107.06 Safety, Health, and Sanitation Provisions.	1-85
107.07 Public Convenience and Safety.	1-88
107.08 Railroad-Highway Provisions.	1-88
107.09 Construction Over and Adjacent to Navigable Waters.	1-88
107.10 Barricades and Signs.	1-88
107.11 Use of Explosives.....	1-88
107.12 Protection and Restoration of Property and Landscape.....	1-89
107.13 Forest Protection.	1-89
107.14 Interruption of Irrigation Water Flow.	1-89
107.15 Responsibility for Damage Claims, Insurance Types and Coverage Limits.....	1-89
107.16 Opening Sections of Project to Traffic.	1-90
107.17 Contractor's Responsibility for Work.....	1-90
107.19 Furnishing Right of Way.....	1-91
107.20 Personal Liability of Public Employees.	1-91
107.21 No Waiver of Legal Rights.....	1-92
107.22 Third Party Beneficiary.	1-92
107.23 Archaeological and Paleontological Discoveries.	1-92
107.24 Air Quality Control.	1-92
107.25 Water Quality Control.	1-92
Section 108 Prosecution and Progress.....	1-98
108.01 Subletting of Contract.	1-98
108.02 Notice to Proceed.	1-98
108.03 Project Schedule.	1-98
108.04 Payment Schedule.	1-102
108.05 Limitation of Operations.	1-103
108.06 Character of Workers; Methods and Equipment.....	1-103
108.07 Workplace Violence.....	1-103
108.08 Determination and Extension of Contract Time.	1-103
108.09 Failure to Complete Work on Time.	1-105
108.10 Default of Contract.....	1-106
108.11 Termination of Contract.	1-107
Section 109 Measurement and Payment.....	1-108
109.01 Measurement of Quantities.	1-108
109.02 Scope of Payment.....	1-110
109.03 Compensation for Altered Quantities.	1-110
109.04 Compensation for Changes and Force Account Work.....	1-111
109.05 Eliminated Items.	1-113
109.06 Partial Payments.....	1-113

109.07	Payment for Material on Hand (Stockpiled Material)	1-118
109.08	Reserved.....	1-119
109.09	Acceptance and Final Payment.	1-119
109.10	Compensation for Compensable Delays.	1-119

Divisions 200 through 600 Construction Detail

Division 200	Earthwork.....	2-1
201	Clearing and Grubbing.....	2-1
202	Removal of Structures and Obstructions.....	2-3
203	Excavation and Embankment.....	2-7
206	Excavation and Backfill for Structures	2-16
207	Topsoil.....	2-24
208	Erosion Control	2-26
209	Watering and Dust Palliatives	2-49
210	Reset Structures.....	2-51
212	Seeding, Fertilizer, Soil Conditioner, and Sodding	2-54
213	Mulching	2-59
214	Planting	2-65
215	Transplanting.....	2-70
216	Soil Retention Covering	2-73
217	Herbicide Treatment.....	2-78
250	Environmental, Health and Safety Management.....	2-79
Division 300	Bases	3-1
304	Aggregate Base Course	3-1
306	Reconditioning	3-3
307	Lime Treated Subgrade	3-4
Division 400	Pavements	4-1
401	Plant Mix Pavements – General	4-1
403	Hot Mix Asphalt.....	4-11
405	Heating and Scarifying Treatment.....	4-12
406	Cold Asphalt Pavement (Recycle).....	4-14
407	Prime Coat, Tack Coat, and Rejuvenating Agent	4-17
408	Joint and Crack Sealant.....	4-19
409	Chip Seal.....	4-20
411	Asphalt Materials	4-22
412	Portland Cement Concrete Pavement.....	4-24
420	Geosynthetics	4-38
Division 500	Structures.....	5-1
501	Steel Sheet Piling	5-1
502	Piling	5-2
503	Drilled Shafts	5-9
504	Walls.....	5-20
506	Riprap.....	5-30
507	Slope and Ditch Paving	5-34
508	Timber Structures.....	5-37
509	Steel Structures	5-39
510	Structural Plate Structures.....	5-56
512	Bearing Device.....	5-58
514	Pedestrian and Bikeway Railing	5-63
515	Waterproofing Membrane	5-65
516	Dampproofing	5-68
517	Waterproofing	5-69
518	Waterstops and Expansion Joints	5-71
Division 600	Miscellaneous Construction	6-1
601	Structural Concrete.....	6-1
602	Reinforcing Steel.....	6-36

603	Culverts and Sewers	6-39
604	Manholes, Inlets, and Meter Vaults	6-43
605	Subsurface Drains	6-45
606	Guardrail	6-47
607	Fences.....	6-50
608	Sidewalks and Bikeways	6-52
609	Curb and Gutter.....	6-54
610	Median Cover Material	6-56
611	Cattle Guards.....	6-57
612	Delineators and Reflectors	6-58
613	Lighting	6-61
614	Traffic Control Devices	6-67
615	Water Control Devices	6-90
616	Siphons.....	6-91
617	Reserved.....	6-92
618	Prestressed Concrete	6-93
619	Water Lines	6-116
620	Field Facilities	6-118
622	Rest Areas and Buildings	6-120
623	Irrigation System	6-129
624	Drainage Pipe	6-137
625	Construction Surveying.....	6-140
626	Mobilization	6-143
627	Pavement Marking	6-144
629	Survey Monumentation	6-152
630	Construction Zone Traffic Control	6-157
641	Shotcrete.....	6-170
Division 700	Materials Details.....	7-1
701	Hydraulic Cement	7-1
702	Bituminous Materials	7-3
703	Aggregates.....	7-12
704	Masonry Units	7-22
705	Joint, Waterproofing, and Bearing Material	7-23
706	Concrete and Clay Pipe	7-29
707	Metal Pipe	7-30
708	Paints	7-32
709	Reinforcing Steel and Wire Rope	7-38
710	Fence and Guardrail	7-39
711	Concrete Curing Materials and Admixtures	7-41
712	Miscellaneous.....	7-42
712.01	Water.....	7-42
712.02	Calcium Chloride	7-42
712.03	Hydrated Lime.....	7-42
712.05	Precast Concrete Units	7-42
712.06	Frames, Grates, Covers, and Steps	7-42
712.07	Geosynthetics	7-43
712.08	Geotextiles.....	7-44
712.09	Gabions and Slope Mattresses.....	7-45
712.10	Epoxy.....	7-46
712.11	Plastic Pipe for Underdrains	7-47
712.12	Geocomposite Drains	7-47
712.13	Plastic Pipe	7-47
713	Traffic Control Materials.....	7-49
714	Prestressed Unit Materials.....	7-58
715	Lighting and Electrical Materials	7-59
716	Water Line Materials	7-65
717	Rest Area and Building Materials.....	7-67