

Date Issued 12.23.24

**Page 601-46, subsection 601.16 (e), the fourth paragraph under the subsection, an**

601.16 (e), fourth paragraph

“. . . shall monitor the air temperature within the enclosure at intervals acceptable to the Engineer. The Contractor shall monitor and maintain the structural integrity of the enclosure. Heating of the enclosure may be stopped after 72 hours if the **concrete air** achieved 0.80f'c. For every day that the internal temperature of the concrete is below 50 °F during the curing period,