Chapter 600

Concrete & Item 600 - 18

This chapter is not part of the Project's specifications, but is a guide for project personnel in interpreting CDOT specifications, understanding ASTM, AASHTO, and Colorado test procedures, and for completing CDOT forms.

ITEM 601, STRUCTURAL CONCRETE

CONCRETE DESIGN MIXES

All concrete placed on the project shall conform to a design mix, which has been approved according to CP 62. The design mix is defined by the proportions and sources of all ingredients in the concrete.

The Contractor (or Supplier) will establish and is responsible for the concrete design mix proportions and source of all ingredients for each class of concrete used. The Region Materials Engineer (RME) or the Concrete & Physical Properties (CPP) Unit may verify any or all properties of the submitted mix design prior to approval. When a trial mix check is requested, aggregate sources will be sampled by the Contractor and the samples submitted to the CPP Unit.

The concrete Table 601-1 in Section 601 of the Standard Specification or in the Special Provisions for the project gives the data for each class of concrete. The column "Concrete Class" lists each class of concrete and the required field compressive strength. The cement content for each class of concrete is the minimum amount or range that will be used for designing the concrete mix.

For all classes of concrete, except Class H and HT, the compressive strength of the laboratory trial mix shall be at least 15% greater than the required field compressive strengths.

When a concrete mix design is approved, a CDOT Form #1373 will be issued for the project.

Standard approved mix designs will be placed on the Pre-Approved Concrete Mix Designs list:

www.codot.gov/business/apl

Mix designs are approved for two years from the date the mix was trialed or when the aggregate were sampled, whichever occurs first.

REFERENCING PRE-APPROVED MIX DESIGNS

Projects may choose to reference existing pre-approved concrete mix designs. The concrete mix designs used on CDOT projects are to be referenced in the following manner:

- Cross-reference the contractor's mix design number with the CDOT mix design number on the Pre-Approved Concrete Mix Design list.
- Document the Concrete Mix Design on a CDOT Form #1188, listing the CDOT mix number.
- 3. Mixes must be reviewed and approved by the RME or CPP Unit prior to use.

Upon approval of the concrete mix design, a CDOT Form #1373 will be issued for the project.

REVIEW OF CONTRACTOR'S MIX DESIGN

Mix approval is required before concrete placement begins following the procedures of CP 62.

AGGREGATES

A minimum of three 60 lb. sacks of the coarse (1-1/2 in. to 3/4 in.); three 60 lb. sacks of intermediate (3/4 in. to plus #4); and three 60 lb. sacks of sand (minus #4) per class of concrete are required when mix design checks are performed.

One additional sack of each aggregate will be required for Class H, HT S50, and P mixes.

Aggregate Tests Required for Design Mixes

The following test will be performed by the Contractor:

- (1) specific gravity
- (2) absorption
- (3) organic impurities in sand
- (4) sieve analysis
- (5) sand equivalent
- (6) L.A. abrasion
- (7) percent passing the No. 200 sieve
- (8) fineness modulus
- (9) unit weight and voids in aggregate
- (10) potential alkali reactivity
- (11) soundness by the sodium sulfate method.

COMPRESSIVE STRENGTH TESTING

Determination of compressive strength of concrete shall be done in accordance with ASTM C 39. This method consists of applying a compressive axial load to molded cylinders or cores at a rate within the prescribed range until failure occurs. The compressive strength of the specimen is calculated by dividing the maximum load attained during the test by the cross-sectional area of the specimen. The following details, from the test procedure, are noted:

- 1. Initial cure of specimens is in accordance with AASHTO T 23 as modified.
- 2. Testing machine. Calibration of the testing machine shall be performed at least annually, but not to exceed 13 months. Recalibration is required upon installation or relocation of the machine, or whenever there is reason to doubt the accuracy of test results. The diameter of the sphere of the top loading head on the machine shall be at least 75% of the diameter of the specimen to be tested.

- Concrete specimens shall not be tested if any individual cylinder diameter differs from other diameters of the same cylinder by more than 2%. No cylinder shall depart from perpendicularity to the axis by more than 0.5°; top of cylinder may not deviate by more than 1/16 inch in 12 inches. When neoprene caps are used, each end of the cylinder shall be planed within 0.125 inches across any diameter and no depression in the concrete surface deeper than 0.125 inches is tolerated. diameter used for calculating the cross-sectional area of cylinder shall be determined to the nearest 0.01 inches by averaging two diameters measured at right angles about mid-height of the specimen. Core length shall be measured to the nearest 0.05 inch when length-to-diameter ratio is less than 1.8, or more than 2.2.
- 4. Procedure. Test the cylinders as molded in the field. The loading rate shall be within the range of 20 to 50 psi/second. During the first half of the anticipated load, a higher rate of loading is allowed. When using neoprene caps an additional three to five seconds of load is applied to ensure completion of the test and avoidance of premature breaks.
- 5. Neoprene Pads. Only one side of the pad shall be used when testing the cylinders. Each pad shall not be used to test more than 100 cylinders. Record the number of tests for each pad. The neoprene pad's shore hardness shall be the following for the specified compressive strengths:
 - 50 for 1500 6000 psi
 - 60 for 2500 7000 psi
 - 70 for 4000 7000 psi

A 60 durometer pad is recommended for testing all classes of concrete except for Class S50 which requires sulfur capping.

The neoprene pads shall be removed from the retaining rings and inspected after each test.

QUALITY ASSURANCE PROGRAM FOR CDOT CONCRETE CYLINDER TESTING

Introduction

This defines a quality assurance program for testing of concrete cylinders. This program assures the conformance of CDOT equipment and procedures to ASTM Standards by the following:

- 1. Equipment checks using a standard checklist.
- 2. Procedure checks using a standard checklist.
- Inter-Lab (Round Robin) testing with all labs testing replicate specimens at the same time.
- 4. Training offered by the Concrete Unit of Staff Materials & Geotechnical Branch.
- 5. ACI certification of CDOT employees.

Cylinders shall be tested with equipment that has been checked and found to be in conformance with ASTM criteria. Testing shall be conducted by an employee who is certified as an ACI Concrete Laboratory Testing Tech I or ACI Concrete Strength Testing Technician.

Equipment

The cylinder testing equipment will be examined, using the equipment checklist, a minimum of once a year or when the equipment is moved. The person checking the equipment must meet one of the following criteria:

- 1. Examined by CCRL (Cement and Concrete Reference Laboratory) for procedures and equipment.
- 2. Trained by the Concrete Unit of Staff Materials & Geotechnical Branch.

Procedures

The person will be observed conducting the test by a proctor using the procedures checklist a minimum of once a year. The proctor checking the procedures must meet one of the following criteria:

1. Examined by CCRL for procedures and equipment.

- Trained by the Concrete Unit of Staff Materials & Geotechnical Branch.
- 3. Certified as an ACI Concrete Laboratory Testing Tech I or ACI Concrete Strength Testing Technician.

Inter-Lab Testing (Round Robin)

The Concrete Unit will mold replicate cylinders and distribute these to each Region. All cylinders will be tested at approximately the same time. The Concrete Unit will compile the results and distribute a brief report. Excessive deviations will be investigated by the Region.

Training

The Concrete Unit will conduct training for Region personnel who perform concrete cylinder testing. Classes will be approximately 4 hours and will normally have four trainees per class. The training will be conducted by an employee that has been examined by CCRL.

ACI Certification

American Concrete Institute (ACI) offers one-day certifications. These certifications include testing of concrete cylinders and a complete battery of tests conducted on concrete aggregate and concrete. ACI Certifications are offered through the Colorado Ready Mixed Concrete Association. CRMCA may be contacted at 303-290-0303 or http://www.crmca.org/.

Documentation

Region Materials Laboratories will maintain documentation on equipment calibration, equipment checks, procedure checks, employee training, employee ACI certification, and Inter-Lab results.

The Concrete Unit of the Central Laboratory will maintain documentation of equipment and procedure checks conducted by the Concrete Unit and Inter-Lab results.

Equipment and Documentation Checklist for Compression Testing of Concrete Cylinders

Date	Location
Inspection	Team
Compress	ion Machine
Mfg. & Mod	del
Capacity	
Installation	Date
Calibration	Date
	Calibration interval did not exceed 13 months or calibrated since moved.
	Loading head free moving (4° in any direction).
	Head diameter: [A minimum dimension of at least 3% greater than the diameter of the specimen, to be tested.
	Head radius > radius of sphere.
Other Equ	ipment Noted and Available
	Condition of neoprene pads and extrusion controllers.
	Water temperature of cylinder storage area (73.4°F ± 3°).
	Temperature recording device operating.
	Water saturated with lime.
Document	ation / Records on File
	Compression machine calibration documentation immediately available.
	Water temperature, neoprene pad durometer, and neoprene pad usage recorded (100 uses per pad maximum).
	Diameter, load, and psi of cylinders recorded.
	2015 FMM

Procedure Checklist for Compression Testing of Concrete Cylinders Location _____ Proctor Proctor Credentials Employee Observed Employee Training and Certification **Procedure** Remove specimen from moist storage, maintain moisture. Measure diameter to nearest 0.01 in by averaging two diameters measured at right angles to each other, using calipers, at mid-height of specimen. Wipe clean bearing surfaces of upper and lower blocks. Center the cylinder to the spherical head. Bring top block to bear gently and uniformly on specimen while rotating the movable portion by hand. Load the cylinder (20 to 50 psi/sec. for hydraulically operated machines). Take cylinders to failure (additional 3-5 seconds may be required to ensure completion of break). Record maximum load. Calculate the compressive strength and report to the required precision (nearest 10 psi) Comments:

2015 FMM

UNIT WEIGHT, YIELD, AND GRAVIMETRIC AIR CONTENT OF CONCRETE

AASHTO T 121

The unit weight of the concrete is determined by AASHTO T 121.

Refer to AASHTO T 121 for full details of the test procedure and calculations for determining the following: Unit weight (pounds per cubic foot), yield (volume of concrete produced per batch), relative yield (ratio of the actual volume to the volume as designed for the batch), and air content (percentage of voids in the concrete).

EXCESSIVE WATER DEMAND

Water-cement ratios, which exceed the specified maximum may result from one of the following:

- Incorrect batch weights, due to mathematical errors or scales out of adjustment.
- 2. Stockpiles of aggregate drying to less than a saturated surface-dry condition, requiring more water than the design. Water added to the batch to bring the aggregates to SSD shall not be included in the w/cm ratio calculation.

It is the Contractor's responsibility to maintain water-cement ratios at or below the specified maximum.

MAKING AND CURING CONCRETE CYLINDERS IN THE FIELD

Acceptance (QA) Cylinders

Test cylinders made for determination of compliance with strength specifications are referred to as "acceptance cylinders". These cylinders are tested at 28 days after casting for all classes of concrete except H and HT which are tested at 56 days.

Acceptance cylinders made at the job site shall be made and cured in accordance with AASHTO T 23 except that initial cure shall be in a water tank with a temperature of $73.4^{\circ}F \pm 3^{\circ}$.

Information Cylinders

Test cylinders made for determining form removal time or when a structure may be put into service are referred to as "information cylinders". Information cylinders shall be cured, in the same manner as the structure. Do not expose these cylinders to direct sunlight or do not store where they may be disturbed by Contractor personnel. They shall remain in the molds until they are tested. Information cylinders are for the purpose of determining relative structure strength and are not to replace acceptance cylinders.

Numbering and Marking Cylinders

See the instructions and examples of CDOT Form #82 in this chapter for the correct method of numbering cylinders. Mark the identifying number and information on the cylinders with a water-proof marking. Do not scratch numbers on the end of the cylinders as it will affect test results.

DOCUMENTATION AND TRANSFER OF CONCRETE TEST CYLINDERS

Field sheet Numbering System

The CDOT Form #82, Concrete Cylinder Transmittal, is used to document and provide information for concrete cylinders submitted for compressive strength testing. Each Form #82 is assigned a field sheet control number. The Reproduction Branch is responsible for assigning the established numbers prior to printing.

Concrete Cylinder Transport

Concrete specimens being transported prior to 48 hours after molding are left in the molds. Upon arrival at the designated testing facility, cylinders are removed from the molds and stored in a suitable curing area. Specimens to be transported after 48 hour age are removed from the molds in 24 ± 8 hours. Curing shall be in saturated limewater @ 73.4°F + 3° until the time of transport. During transportation, the specimens must be protected and kept moist with cushioning material in padded boxes or suitable protective containers. Moisture loss shall be prevented by wrapping the specimens in plastic, wet sand or burlap. The project tester or designated project representative will be responsible for proper transfer of the specimens.

The cylinders shall be removed from the molds and marked with the project number, cylinder set number, and break date.

For concrete mix designs with 15% or more Class F fly ash, it is recommended that the cast cylinders remain in the initial curing condition for the majority of the allowed 48 hour time. Concrete with 15% or more Class F fly ash can develop strength slower and transporting them sooner can lead to low break strengths.

Reporting Test Results

The cylinder test information is entered in a reporting program from the CDOT Form #82, Concrete Cylinder Transmittal Report. Compressive test results and cylinder measurements are performed on the specified break dates with compressive strength test results reported on CDOT Form #192, Report of Concrete Tests. Reports are obtained through CARS. It is the responsibility of the Engineer in charge of the laboratory to ensure the proper testing and reporting of compressive strength test results.

TECHNICAL COMPLAINTS

Questions or problems should be directed to the Concrete / Physical Properties Unit Program Manager at 303-398-6542. The evaluation process will include an investigation ensuring that correct procedures were adhered to in the following areas:

- 1. Paperwork
- 2. Testing procedures
- 3. Machine Calibration and settings

A verbal reply will be issued, written replies upon request.

AIR ENTRAINMENT

Definition

Air entrainment is the introduction of air that causes the development of a system of microscopic air bubbles in concrete during mixing.

Measurement

Determination of air content at the job site shall be made in accordance with AASHTO T 152 and the apparent air content reported. Do not correct the air meter reading for air in the aggregate, but report total percent air.

The following may affect the quantity and quality of entrained air in concrete.

1. Fly Ash

Fly Ash may substantially change the amount of air entraining admixture required to produce the required air content. Fly ash with a high loss of ignition (LOI) has a high content of carbon and it usually causes the greatest air reduction.

2. Temperature

Rising temperatures generally require increased amounts of air entraining agents.

3. Water

An increase in the water-cement ratio may increase the air content of the concrete. Contaminants present in many water sources, especially streams, can cause highly variable air content in the water.

4. Mixina

A normal dosage of A.E.A. that does not produce adequate air entrainment may indicate inadequate mixing. Trucks with worn blades will not entrain satisfactory amounts of air within the specified number of mixing revolutions. However, prolonged mixing may increase concrete temperature and further reduce air content. The addition of more air-entraining agent to a truck on the job site is allowed.

5. Cement

The ability of the mortar to entrain air will decrease with the increase of the fineness of the cement, and with an increase in the cement content of the mortar.

6. Fine Aggregate

Changes in the sand may alter the volume of air entrainment in the mortar. An increase in quantity of very fine particles (minus No. 30 plus No. 100

sieve) will tend to increase the volume of air in the mortar.

7. Pumping Concrete

Pumping concrete may reduce the air content of the concrete. Several factors in the pump configuration may influence the quantity of air loss. It is the responsibility of the Contractor to ensure that the air content leaving the pump be within the specified limits.

ADMIXTURES

Pre-Approved Acceptance. Admixtures are required to conform to applicable AASHTO or ASTM specifications. When using an admixture, attention should be given to the instruction provided by the manufacturer. The amount shown on the laboratory design mix is merely a guide and may require adjustment.

Check the Approved Products List at www.codot.gov/business/apl for approved admixtures.

Surface Retarders

To produce exposed aggregate textures, surface retarders may be used. Sample panels may be constructed on the job site using the design mix and surface retarder, if required by contract documents. This will not only provide a measure of the effectiveness of the retarder but will give a preview of the color and texture of the final result. It is important, as with other admixtures, to follow manufacturer's instruction. Sample panels, if required, should be a minimum of 2' X 2' for 3/4" exposed coarse aggregate. If larger sized coarse aggregate is required, the panel dimensions should be increased. Most surface retarders require an initial curing period prior to removal of the matrix.

Workability Agents and Pumping Aids

Improved workability is important for concrete placed in heavily reinforced members or placed by pumping or tremie methods. Frequently, increasing the cement content or the amount of fine aggregate will give the desired workability. One of the best workability agents is entrained air. It acts as a "lubricant" and is especially effective in improving workability and preventing segregation.

Finely divided materials are also used as admixtures to improve workability of mixes deficient in material passing the No. 50 and No. 100 sieves. These materials may be chemically inert or pozzolanic. Inert materials include ground quartz, ground limestone, hydrated lime, and talc. Pozzolans include fly ash, volcanic glass, silica fume, diatomaceous earths, and some clays and shales heat-treated or raw.

Fly ash from an approved source may be used as a cement replacement in all classes of concretes, provided a design mix has been run using the substitution. Class C Fly Ash shall not be used in concrete that may be subjected to sulfate exposure in soil or water.

Monomolecular Film Coatings / Water Fog Sprays

Monomolecular Film Coatings may be applied to concrete slabs or other flatwork as a method to effectively retard surface evaporation. When placing bridge deck concrete or roadway concrete pavement, a film coating shall only be used ahead of the finishing machine during emergency situations, such as a breakdown of the finishing machine. Under these conditions, this type of application is considered to be equivalent to water fog spray.

Accordingly, its usage shall be subject to the established construction guidelines, per approval of the Engineer. A monomolecular film coating may be used after the finishing operation to prevent evaporation until the wet curing material is in place. The film shall be applied as a fine mist in small quantities.

Preformed Expansion Joint Material

Damage may occur during shipping, handling, and/or storage on the project. Therefore, immediately prior to use, project personnel shall inspect the material for physical damage, dryness, bleaching, etc. Any portion of a shipment may be rejected prior to use at the direction of project personnel.

ITEM 602, REINFORCING STEEL (EPOXY COATED)

NOTE: Only producers of epoxy-coated reinforcing steel, in accordance with CP 11, that are on CDOT's Qualified Manufacturers List can be used: www.codot.gov/business/apl.

COC Acceptance. Bars shall meet the requirements of Subsection 709.01 prior to coating. Epoxy coated bars shall meet the requirements of the latest edition of AASHTO M 284.

Coated bars shall be tied with coated tie wires and placed on plastic supports or fully coated steel supports.

Field-inspect epoxy-coated steel carefully. Document field inspection and attach mill test reports to the CDOT Form #157. Retain all copies in the field Project Files.

ITEM 602, REINFORCING STEEL

NOTE: Only Reinforcing Steel Mills, in accordance with CP 11, that are on CDOT's Qualified Manufacturers List can be used: www.codot.gov/business/apl

Field inspections, by the Engineer, should indicate that the reinforcing steel is clean and if Epoxy-Coated, that the coating is not chipped, cracked, or scratched. The steel should also be checked for proper size and grade using information listed below.

The CDOT Staff Bridge Branch uses several different strengths of reinforcing steel for design purposes. It is necessary to watch the bar list on the bridge plans for higher strength grades, find their exact locations on the bridge plans, and be sure the correct steel is being used in that location.

Grade 60 has a yield strength of 60,000 psi and has either a "60" on the bar or a single continuous longitudinal line through at least five spaces offset from the center of the barside. This grade may be substituted on an equal basis for Grade 40 without prior approval. However, make note of this in the project records if substitution is made.

The metric equivalent to Grade 60 is Grade 420. It has either a "4" on the bar or a single continuous longitudinal line through at least five spaces offset from the center of the barside.

Grade 75 has a yield strength of 75,000 psi and has either a "75" on the base or two continuous longitudinal line through at least five spaces offset each direction from the center of the bar.

The metric equivalent to Grade 75 is Grade 520. It has either a "5" on the base or two continuous longitudinal line through at least five spaces offset each direction from the center of the bar.

Metric markings are being phased out by the Concrete Reinforcing Steel Institute (CRSI) to reduce confusion and the chance of errors/delays from the construction supply chain.

Information on bar markings at CRSI website: http://www.crsi.org/index.cfm/steel/identification

CSRI Plant Identification Guide for Concrete Reinforcing Bars available at CRSI website or http://internal.dot.state.co.us/MAC/Resources.cfm.

An effort should be made to note in the project diary and on appropriate CDOT forms the grades of reinforcing steel used and especially note when different grades were used in special locations.

Concrete blocks or chairs for support of reinforcing steel need not be tested or documented unless there is reason to believe they lack conformance with CRSI recommended practices.

Certain items contain reinforcing steel, which is not included in the quantities of Item 602. These include precast, concrete bridge caissons, drop inlets, manholes, sign footings, slope and ditch pavements, and dowels in concrete pavement. When totaling up the pay quantity for these items, be sure the steel for these items is not included in reporting Item 602.

WIRE MESH

Wire mesh: Field-inspect. Document in the Project Files.

The term "gage" is used by the metal industry to denote a nominal dimension. This table defines those dimensions. Galvanized sheet steel is, or course, thicker than bare sheet steel. This difference is caused by the application of a double surface coating of zinc representing 2 to 2.5 oz. per sq. ft.

Wire gage is the diameter of the finished product whether galvanized or bare. The galvanizing on wire may vary from a thin film to as much as 2 oz. per sq. ft. of area. In the case

of chain link fence wire, a 2 oz. coating may contribute as much as 0.007 in. to the diameter.

The figures in the Table 600-1 pertain to actual thicknesses and diameters, but may vary because of manufacturer's tolerances. For example, culvert sheets may be 0.006 to 0.009

in. undersize. Multi-plate sheets may be as much as 0.012 in. undersize. Wire can vary as much as ± 0.005 in. from the given diameter. To determine spelter thickness, consider 1 oz. per sq. ft. of zinc coating to be 0.0017 in. thick.

TABLE OF GAGE MEASUREMENTS

SHEE	T STEEL	WIRE	GAGE	SHEET	STEEL	WIF	RE GAGE
Bare	Galv	Dian	neter	Bare	Galv		Diam.
<u>Inches</u>	<u>Inches</u>	<u>Inc</u>	<u>hes</u>	<u>mm</u>	<u>mm</u>	<u>_ mr</u>	<u>m</u>
.2758	.280	1	.283	7.005	7.112	1	7.188
.2451	.249	3	.244	6.225	6.325	3	6.197
.2145	.218	5	.207	5.448	5.537	5	5.258
		6	.192			6	4.877
.1838	.188	7	.177	4.668	4.775	7	4.496
.1793		7	.170	4.554		7	4.318
.1644	.168	8	.162	4.176	4.267	8	4.115
		9	.148			9	3.759
.1345	.138	10	.135	3.416	3.505	10	3.429
		11	.120			11	3.048
.1046	.109	12	.105	2.657	2.769	12	2.667
		12	.099			12	2.515
.0747	.079	14	.080	1.897	2.007	14	2.032
		14	.076			14	1.930
.0598	.064	16	.0625	1.152	1.626	16	1.588
.0478	.052	18	.0475	1.214	1.321	18	1.207
.0359	.040	20	.0348	0.912	1.016	20	0.884
.0299	.034	22	.0286	0.760	0.864	22	0.726

TABLE 600-1

ITEM 603 Culverts & Sewers

604 Manholes, Inlets, Meter Vaults

624 Drainage Pipe

CORRUGATED METAL PIPE

Final acceptance is based on field inspection by Project Personnel.

SPELTER DAMAGE REPAIR

Zinc rich paint conforming to Department of Defense DOD-P-21035A should be used for repainting damaged spelter. A Certificate of Compliance is required that indicates that the zinc rich paint meets the above referenced specification.

CONCRETE CULVERT PIPE

NOTE: Only Precast Concrete Manufacturers, in accordance with CP 11, that are on CDOT's Qualified Manufacturers List can be used: www.coloradodot.info/business/apl

Inspection of the individual pieces of the lot is left to the supplier and the field personnel. The field inspection is to be done in accordance with AASHTO M 170.

After final pay quantities are known, document them on a CDOT Form #157.

VITRIFIED CLAY PIPE

The project field personnel should field-inspect the pipe and document information in the Project Files.

PIPE JOINT SEALING COMPOUND

Most joints will require some type of sealing material. The choice is limited to either performed plastic sealing compound or bituminous mastic. Both must meet AASHTO M 198 specification. Portland cement grout is not allowed. Rubber gaskets are required for siphon and sanitary sewers and also may be used without further approval on storm sewers and culverts.

The performed plastic sealing compound is supplied with removable paper strips between layers. A primer is required. Instructions require the primer to dry hard before applying the joint sealer. It is strongly recommended that the primer be applied by the contractor at the jobsite rather than by the pipe manufacturer in his plant. This helps keep dirt off the primer surface and coats any chipped surfaces. Cold and wet weather require special installation procedures.

On the CDOT Form #157 that accompanies the sample list trade name, manufacturer, and any analysis or specification data found on the label.

ITEM 604, MANHOLES

Manholes will have stamped on each section the date of manufacture and name or trademark of the fabricator. Inspect these sections for the same characteristics listed and explained under Concrete Culvert Pipe. Document in the Project Files that the material was field-inspected and is acceptable, and add a statement to the effect that the material was in good condition when installed.

ITEM 606, GUARDRAIL

Treated Timber Posts & Galvanized Steel Posts

Project personnel will inspect all posts upon arrival on the project regardless of their source. This inspection will be documented on CDOT Form #157, an example of which appears at the end of this chapter. See Special Notice to Contractors for additional information.

Final acceptance is based on field-inspection by project personnel.

Type 3 W-Beam Guard Rail

When either the weathering steel or galvanized steel arrives on the job, it must be stored in such a way that water will not get in between the stacked rails. Water in a confined area, as it would be between these rails, causes a rapid loss of galvanizing in the form of white rust and definite kind of rusting in the weathering steel that leads to flaking and pitting, as well as an uneven rust pattern. The acceptance documentation can be done on the same CDOT Form #157 as used for acceptance of the posts. See example at the end of this Chapter.

ITEM 606, END ANCHORAGE

For individual components of end anchors, and types, refer to the M & S Standards for description of parts on each type. Further details are shown in the Standard Specifications, Section 710 and Subsection 710.09. The acceptance documentation can be done on the same CDOT Form #157 as used for acceptance / verification of the posts. List the above information on the CDOT Form #157.

ITEM 607, FENCES

Treated Timber Posts

Project personnel will inspect posts and note the source, field-inspect for compliance, and document on CDOT Form #157

ITEM 613, LIGHTING*

Luminaires

Many manufacturers of luminaires that comply with our specification are "nationally known brands". It must be understood that they also manufacture luminaires that do not meet our specification and therefore, it is necessary to check the ratings of the luminaires furnished against the requirements of the plans and specifications. Document this inspection on a CDOT Form #157. See Special Notice to Contractors for additional information.

Metal Light Standards (pole and arms)*

Many suppliers are capable of providing approved standards. Because the standards received on the job were made by a company

previously approved, does not imply that they meet the requirements of the plans and specifications, since they also supply poles and arms in other sizes and to other specifications. It is necessary to check all features against the requirements of the plans and specifications. Document this inspection on a CDOT Form #157. See Special Notice to Contractors.

* See the Schedule for Item 613

ITEM 614, TRAFFIC CONTROL DEVICES

Sign Posts

Structural Steel: These posts have the break-away feature which requires the bolts to be torqued. The upper, or fuse plate bolts, are normally shop tightened. Therefore, field checking of these fuse plate bolts should be necessary. The lower or break-away bolts are tightened more than the required torque so that during shipment and erection, the two parts stay attached. Therefore, it is necessary after erection, for the contractor to loosen these break-away bolts and retighten them with torque wrench to the torque values shown on the plans (Standard Drawing S-614-5). Be careful not to over-tighten them. It is very important to burr the threads of the break-away bolts to prevent the nuts from loosening. Be sure to check the torque of all bolts because if they are not tightened properly, the sign will not function as designed. Document in Project Files.

Flashing Yellow Beacons

Be sure that all features required by the standard drawing and the specifications are met by the models supplied.

Anchor Bolts for Sign Bridge Structure

The anchor bolts for wide flange posts and sign structures that go into these footings are part of the sign structure but are shipped ahead of them. Small structure anchor bolts and

regular bolts should be field inspected and documented in Project Files. See Special Notice to Contractors.

ITEM 615, WATER CONTROL DEVICES

Drawing M-615-A requires the use of a joint sealer meeting Federal Specification SS-S-168 or approved equivalent to make the adjustable elbows watertight.

ITEM 618, POST TENSIONING GROUT

Each project will collect a sample and send it to the Central Lab prior to use. The Chemical Lab will test the 1st sample from particular grout and send that result to each project that sends a sample for that grout until the test results are greater than 6 months old. Then the next sample submitted after the 6 months would be tested. The grout submittal shall comply with Section 618.09.

ITEM 624, DRAINAGE PIPE

There are several different types of drainage pipe materials available, each with different abrasion and corrosive resistant characteristics. To take economic advantage of this, ten different classes have been defined and the available drainage pipe materials designated as useable or not useable for each class, so the contractor can select the most economical material.

Most projects will have no corrosive problems. However, when they are encountered, they should be recognized during the soil survey. The decision on what Class of pipe to use is detailed in the CDOT Pipe Material Selection. The Soils Survey portion of Chapter 200 gives details on what to look for and when to suspect the existence of a corrosive condition.

CDOT Forms - Applicable for the Concrete Chapter, Examples and Instructions

Form	Title	Page
# 1188	Concrete Mix Submittal [preceded by Contractor's supplemental documentation]	15-20
# 1373	Concrete Mix Design Report – [computer output]	21
# 157	Field Report for Sample Identification or Materials Documentation	22-32
# 46	Concrete Truck Mixer Inspection Certification	33
# 82	Concrete Specimen Transmittal	34-36
# 156	Concrete Test Results Summary	37
# 192	Report of Concrete Tests – [computer output]	38-39
# 193	Inspection- Quality Assurance Acceptance Report – [computer output]	40
# 196-A	Physical Test Report – [computer output]	41
# 199	Concrete Core Tests – [computer output]	42
# 276	Report of Concrete Placed	43
# 281	Concrete Batched and Placed	44
# 389	Field Report for Joint Sealant Testing	45
# 626	Field Laboratory Test Results	46
# 1372	Reinforcing Bar Physical Test Report – [computer output]	47-49
# 1375	Concrete Field Tests Report – [computer output]	50

ATTENTION!

All of the referenced CDOT Materials Forms above, except those indicated as "computer output", have been revised in 2014. All of these forms state: *Previous editions are obsolete and may not be used*. The use of Materials Forms older than what is indicated in Appendix O of the FMM is not authorized!

The examples of completed forms will be revised as necessary and as time permits in future FMM's.

Instructions for *Manually Developing the Field Sheet Numbers for CDOT Forms* is presented in Appendix O. In Chapter 600 the forms that utilize a Field Sheet are bolded above.

to tenter visio appear the tenter of a least order	es sates a mon proportional mon o	- 500 Sept 1750 Sept 500 Sept	Contract ID	Table and Plant advantages.	Region	Date Submitted
CONCRETE MAIN		TATION		C18180	1	02/15/2017
CONCRETE MIX	X SUBMITTAL		Project No.		FBR 0404-0	50
The issue of the late of the l			Proj. Locatio	n L	JS 40 Over Sar	nd Creek
This submittal form shall mix design for review by	the Concrete Unit of C	DOT	Contractor		Hamon Contra	ctors
Central Laboratory. CDC	OT Form #157 not requ	ired.	Concrete su	pplier Martin M	Marietta Materia	als-Riverbend Plant
Project contact	(print name)			Phone # (303) {	555-1545	
Information	Jesse Str	ebelinski		Email strebelins	ski@rocksol.com	<u> </u>
☐ New mix	004705				☐ Non S	tandard
☐ APL mix-CDC	T mix# 201705	0			Optimi	ized
Sulfate Class from Project Plans		ass 2		□ Not Sr	posified: De	sfault Class 2
Class 0	_	ass 2 ass 3		□ Mor St	becilied. De	efault Class 2
Concrete Class:						
☐ B; 601.02.01	1.00	✓ D):	601.02.03.0	0	
☐ BZ: 601.02.02		_		601.02.03.0		
☐ G: 601.02.17			or opeoidi OT	601.02.04.0		
	3.00 (see note)			601.02.	Ŭ	
	5.00 (see note)	_	OTHER	001.02		
	,		ZITILIN			
	ment Class P and Class teria: Compressive		exural			
	projects, check all mat	erial code	es from the C	Owner Acceptanc	e Sampling Ch	ecklist that this
mix will be utilized for:	: omitted will be used for	Class D :	and Class R	on this project (Sheck Class D	and Class B hoves
Example: Class D suc	offlitted will be ased for	Class D	and Class D	on this project. C	DIECK Class D	and Class B boxes
Contractor is require	ed to submit the follo	wing info	ormation for	r New mixes.		
Per CP 62 and 601	1.05: Mix properties, su	ipporting t	test data, an	d trial mix data		
For Project specific with CDOT Form 118	submittal, the follow	ing docu	ments are r	equired to be su	ıbmitted	
✓ Project Special Pro						
Applicable Project	Special Provisions					
✓ Standard Special F						
Special Instructions: Explain	any missing required data or	test results.				
Mix design includes trial			ensile streng	th results.		
Mix will be used as the 0	Class D mix also.					
☐ Original - Project Files☐ CDOT Central Laboratory, C			are obsolete and	d may not be used.		CDOT Form #1188 2/1

Page 14 of 50

			18 :	1-1-1
COLORADO DEPARTMENT OF TRANSPORTATION	Contract ID	C18180	Region 1	Date Submitted 02/01/2017
CONCRETE MIX SUBMITTAL	Project No.		FBR 0404-0	50
	Proj. Locatio	n (JS 40 Over Sar	nd Creek
This submittal form shall be used to submit a concrete mix design for review by the Concrete Unit of CDOT	Contractor		Hamon Contra	ctors
Central Laboratory. CDOT Form #157 not required.	Concrete su	pplier Martin	Marietta Materia	als-Riverbend Plant
Project contact (print name)	• 1	Phone # (303)	555 15/5	
Information Jesse Strebelinski		1,23	ski@rocksol.com	A
✓ New mix	,		☐ Non S	tandard
☐ APL mix-CDOT mix#			Optimi	ized
Sulfate Class from Project Plans				
Class 0		☐ Not S	pecified: De	efault Class 2
☐ Class 1 ☐ Class 3				
Concrete Class:				
☑ B: 601.02.01.00 ☑ D:		601.02.03.0	00	
☐ BZ: 601.02.02.00 ☐ D:	Special	601.02.03.0	01	
☐ G: 601.02.17.00 ☐ D ⁻	Γ	601.02.04.0	00	
☑ P: 601.02.08.00 (see note) ☐ S()	601.02.		
	, THER			
	I I ILIX			
Note: Concrete Pavement Class P and Class E Acceptance Criteria: Compressive ☐ Flex	kural			
Note: For SMM/LIMS projects, check all material codes	from the C	Owner Acceptan	ce Sampling Ch	ecklist that this
mix will be utilized for:				
Example: Class D submitted will be used for Class D ar	nd Class B	on this project.	Check Class D	and Class B boxes
Contractor is required to submit the following infor	mation fo	New mixes.		
Per CP 62 and 601.05: Mix properties, supporting te	st data, an	d trial mix data		
For Project execific cubwritted the following decume	anta ara r	aguired to be a	uhmittad	
For Project specific submittal, the following docum with CDOT Form 1188.	ients are r	equired to be s	ubmittea	
✓ Project Special Provisions Index				
✓ Applicable Project Special Provisions				
Standard Special Provisions Index				
Special Instructions: Explain any missing required data or test results.				
Mix will be used as the Class D, Class P, and Class B mix	(also.			
☐ Original - Project Files Previous editions at ☐ CDOT Central Laboratory, Concrete Program - with attachments	re obsolete an	d may not be used.		CDOT Form #1188 2/1



Mulligan Testing Laboratories

1301 South Birch Street, Denver, CO 80222

Freddy's Ready Mix Concrete Co. ID No.: 42352

Trial Date: 02-10-2003 CDOT Concrete Class D

MIX DESIGN MATERIALS:

<u>Material</u>	Per Cubic Yard
Sand	1152 lbs.
Cement (I/II)	512 lbs.
Fly Ash (Class F)	128 lbs.
Aggregate Size # 67	1802 lbs.
Water	261.5 lbs. (33.0 gal.)
Mateu Daalualisas Assaut	05.0 `

Water Reducing Agent 25.8 oz.

Air Entrainment Agent 2.7 oz.

The above weights are based upon aggregates in a saturated, surface dry condition. Batch plant corrections must be made for moisture in aggregates.

PHYSICAL PROPERTIES:

Unit Weight: 141.1 pcf Yield: 1.01 Water/Cement Ratio: 0.41 Air Content: 6.2 % Slump: 3.50 in.

COMPRESSIVE STRENGTH RESULTS:

(From laboratory trial)

Cylinder Number

				<u>,</u>		unib C 1	•	
Cylinder Break Time	1	2	3	4	5	6	7	Average Strength (psi)
3-Day	4040	4220	-	-	-	-	-	4130
7-Day	-	-	4720	4680	-	-	-	4700
28-Day	-	-	-	-	5730	5300	5380	5470



Material Suppliers and Sources:

<u>Material</u>	Company	<u>Source</u>
Fine Aggregate:	Blarney Sand & Gravel	Shamrock Pit East
Coarse Aggregate:	Blarney Sand & Gravel	Shamrock Pit West
Cement (Type I/II):	Celtic Cement Co.	Guffey, Colorado
Fly Ash (Class F):	Finnegan Fly Ash Co.	McClure, Colorado
Water Reducing Agent:	Antrim Admixtures Co.	Antrim H2O
Air Entrainment Agent:	Antrim Admixtures Co.	Antrim Super Air

Coarse Aggregate

Sieve Analysis

Sieve	% Passing	<u>Spec</u>
1"	100	100
3/4"	92	90-100
1/2"	54	
3/8"	41	20-55
#4	6	0-10
#8	3	0-5
#200	0.8	0-1.5

Specific Gravity: 2.64 L.A. Abrasion: 42 % loss

Absorption: 0.9 % Voids & Unit Weight: 38%; 103 pcf Sodium Soundness: 1 % loss ASTM C1260: 0.182 % expansion

Fine Aggregate

Sieve Analysis

Sieve	% Passing	<u>Spec</u>
3/8"	100	100
#4	99	95 – 100
#8	94	80 –100
#16	70	50 – 85
#30	50	25 – 60
#50	22	10 – 60
#100	8	2 – 10
#200	2.4	0 - 3.0

Specific Gravity: 2.65 Absorption: 0.7 %

Sodium Soundness: 1 % loss

Fineness Modulus: 2.61

Sand Equivalent: 83

Organic Impurities: Plate # 1 ASTM C1260: 0.071 % expansion





Mulligan Testing Laboratories

1301 South Birch Street, Denver, CO 80222

March 24, 2003

Freddy's Ready Mix Concrete Company Attention: Frederick Fletcher 52 Wesley Avenue Bailey, CO 80421

Dear Mr. Fletcher,

This letter reports the results of the potential reactivity tests (mortar bar method), which our lab performed for you. The materials were received at our facility in March 2003. The aggregates were defined as "Shamrock Pit Aggregates." The mix was compiled of 63.4% coarse aggregates and 36.6% fine aggregates. Along with the aggregates, Celtic cement Type I/II and Finnegan Class F fly ash were submitted.

The aggregate samples were prepared and tested in conformance with ASTM C 1260, "Potential Alkali Reactivity of Aggregates (Mortar Bar Method)". Since the coarse aggregate did not meet the CDOT requirement for expanding no more than 0.10% after 16 days, the aggregates, cement and fly ash were combined in proportion to the mix design and tested according to CPL 4202 "Determining the Potential Alkali Reactivity of Cementitious Materials and Aggregate (Accelerated Mortar Bar Method). The 16-day expansion for the mix was 0.056%. These results are presented in Tables 1, 2 and 3 and graphed in Figure One.

This data signifies that the potential for deleterious behavior of this concrete mix is low. Please feel free to contact me with any questions you may have regarding this report.


Sincerely,

Patrick Mulligan Laboratory Manager Mulligan Testing Laboratories

Enclosures



		Tat	Table 1 - AS	- ASR Sand Test	, ,				
Zero (48	(48 hr)	3-Day Reading		7-Day Reading		10-Day Reading		14-Day Reading	
	0	3	% Change	7	% Change		% Change		% Change
0.229	596	0.2311	0.015	0.2336	0.040	0.2355	0.059	0.2398	0.102
0.231	314 276	0.2336	0.022	0.2351	0.037	0.2364	0.050	0.2377	0.063
	<u> </u>	•	0.020		0.036	•	0.050	•	0.071
		Tab	le 2 - ASI	3 Gravel Tes	St				
		Table	le 2 - ASI	2 - ASR Gravel Test	st		-		
Zero (48 hr)	18 hr)	3-Day Reading		7-Day Reading		10-Day Reading		14-Day Reading	
0		3	% Change	7	% Change	10	% Change	14	% Change
0.3604	2 S	0.3657	0.053	0.3694	0.090	0.3738	0.134	0.3789	0.185
0.364	1 8	0.3694	0.046	0.3733	0.085	0.3797	0.149	0.3848	0.200
Ľ		•	0.039	•	0.073	•	0.130	_	0.182
		-		:	·			\	
		Та	ble 3 - A	Table 3 - ASR Mix Test					
Zero (48 hr)	18 hr)	3-Day Reading		7-Day Reading		10-Day Reading		14-Day Reading	
% Change 0		3	% Change	7	% Change	10	% Change	14	% Change
0.218	185	0.2201	0.016	0.2213	0.028	0.2230	0.045	0.2253	990:0
0.1764	.64	0.1778	0.014	0.1787	0.023	0.1800	0.036	0.1811	0.047
0.200	93	0.2112	0.019	0.2122	0.029	0.2136	0.043	0.2145	0.052
<u>'</u>			0.016	•	0.027	•	0.041	•	0.056



COLOBAL	O DED	ADTRE	NT OF TRANS	PODTATION	Project No.		REGION	Contract ID
COLONAL	O DEP	ANTINE	NI OF IRANS	PORTATION	MR 2854-012		1	12345
Conc	roto	RAis	Dooign	Donort	Location			
Conc	Hele	IVIIX	Design I	neport	West of Bailey			
Concrete Supplier	• Freddy'	's Ready Mix	/	CDOT Mix Nu	ımber : 20030	00		
	777	S Heady Wil						
Supplier Mix ID:		4500 -		Item 601		ncrete		
ield Compressive	e Strengtn:	4500 p	OSI		e Resistance and low			
					e resistance requires		io ≤0.40	
		Concret		is (SSD Batch We	eights for 1 Cubic	Yard)		
Cement:	512	Pounds	Celtic (Guffey)					
			Type I/II Ceme	nt				
Fly Ash:	128	Pounds	Finnegan (McClure)					
		· oundo	Class F Fly Ash					
Silica Fume		Pounds						
Onica i unie		rounds						
Coarse	1802	Pounds	Blarney, Shamrock F	Pit; Size 57/67				
Aggregate 1 Coarse								
Aggregate 2		Pounds						
Coarse		Pounds						
Aggregate 3		rounds						
Fine Aggregate	1152	Pounds	Blarney, Shamrock F	Pit				
Admixture	2.7	Ounces	Antrim. Super-Air					
Admixture	25.8	Ounces	Antim, H2O					
Admixture		Ounces						
Admixture		Ounces						
Water	262	Pounds						
water	202	rounus						
		de la	Tria	al Batch Propertion				i i i
				7-Day Compressive	The state of the s	0 psi		
Unit Weight:	141.1	PCF		14-Day Compressive	e Strength :	psi		
W / Cm Ratio:	0.41			28-Day Compressive	e Strength: 547	0 psi		
Slump :	3.50	Inches		56-Day Compressive	e Strength:	psi		
Air Content :	6.20	%		7-Day Flexural Stren	ngth:	psi		
Relative Yield :	1.01			28-Day Flexural Stre	ength:	psi		
			Agg	regate Test Resu	ılts			
		Specific	c Gravity (SSD)	Absorption				
Coarse Aggregate	1:		2.64	0.9 %				
Coarse Aggregate	2:			%				
Coarse Aggregate				%				
Fine Aggregate :	70.5		2.65	0.7 %				
mo Aggregate .			2.00	0.7 76				
				Comments:				
Reviewed by:	Miranda R	oskop			Review date: 3/2	26/2003		
			OT Concrete and Phys					

CICL D DEDORT COD CALL	ISPORTATION	Field sheet N	lo. L20227	Date 11/28/02
FIELD REPORT FOR SAMI		A I ION Project No.		et location
OR MATERIALS DOCUMI	ENTATION	IM0253		25, SH 7 to WCR 16
Metric units ☐ yes	s 🖄 no	Project code		
		119	25	3200 4 P
Sample submitted: e.: Soil, ABC, Hydrated lime, HMA,			Fie	eld office phone number 303 - 828 - 0386
concrete cores, steel, etc.)	S		Fig	eld office FAX number 303-828-0430
tem Class	Grading		S	pecial provisions
412 PFA	M	ix #98034	ар	oplicable: 🛛 yes 🔲 no
Previously used on Project No.: Air 7.1/Slump 5.5		DOT Form #157 F/S No ed on 10/25/0		CDOT Form #633 (sack) CDOT Form #634 (can)
Sample Identification: Quantity & Unit of ma Materials Documentation: Field inspected (or				moved from (stationing), etc.
Submitting (3) cores	for Compressive	Strength.		
Time cored was 3 PM	. Date 11/28/02	<u>•</u>		
Please call head test	ter @ 303-555-2	1525		
A) 93+780				
B) 93+785				
C) 93+775				
Cored at 35 days				
ADI /OMI Acceptance: ADI Pef No.	advat name:			Date checked:
APL/QML Acceptance: APL Ref. No. Pr	oduct name:			Date checked:
2	oduct name: oduct name:			Date checked:
APL/QML Acceptance: APL Ref. No. Pr	oduct name:	ergency.		Date checked:
	oduct name:	ergency		DESSUES ROOM BARONS
APL/QML Acceptance: APL Ref. No. Pr Preliminary Construction	oduct name: Maintenance Eme		rge	Date checked:
Preliminary Construction Contractor Kraemer and Sons Exampled from Pt. roadway Roadway	oduct name: Maintenance Eme	Gupplier	rge	Date checked:
Preliminary Construction Contractor Kraemer and Sons Exampled from Pt. roadway, windrow, tock, etc.)	oduct name: Maintenance Eme	Gupplier LaFa		Date checked:
Preliminary Construction Preliminary Construction Contractor Kraemer and Sons Sampled from Pit, roadway, windrow, Roadway Quantity represented	oduct name: Maintenance Eme	Supplier LaFa		Date checked: Date needed ASAP antity to date
Preliminary Construction Preliminary Construction Contractor Kraemer and Sons Sampled from Roadway, windrow, tock, etc.) Quantity represented	Maintenance Eme	Supplier LaFa Pit name or owner		Date checked: Date needed ASAP
Preliminary Construction Preliminary Construction Contractor Kraemer and Sons Sampled from Pit, roadway, windrow, atock, etc.) Quantity represented Sample submitted: X Yes No Central Sampled or inspected by (Name)	oduct name: Maintenance Eme S F Previous quantity	Supplier LaFa Pit name or owner	Total qu Geocal Lab phone num	Date checked: Date needed ASAP antityto date Date 11/29/02
Preliminary Construction Preliminary Construction Contractor Kraemer and Sons Sampled from Prt. roadway, windrow, tock, etc.) Quantity represented Sample submitted: Shipped to:	Maintenance Eme	Supplier LaFa Pit name or owner Via Tech	Total qu Geocal Lab phone num	Date checked: Date needed ASAP antity to date Date 11/29/02

Note: Within Date needed, ASAP is not a date.

COLORADO DEPARTMENT OF			Field sheet N		Da		
FIELD REPORT FOR S	AMPLE IDEN		Project No.	0227	Project location	11/28	702
OR MATERIALS DOC	JMENTATIC	N	IM0253	3-151	I-25, SH	7 to W	CR 16
Metric units 0	⊒yes ⊠	no	Project code	(,	Function	Region	Part.
			11625		3200	4	Р
Sample submitted:					Field office pho	ne number 8 - 0386	
ie.: Soil, ABC, Hydrated lime, HMA, oncrete cores, steel, etc.)	res				Field office FA	X number	
tem Class		Grading			Special provisi	2 8-043 0 ons	,
412	В		mn A		applicable:	yes	no no
Previously used on Project No.: Air 7.1/Slump 5.5		Previous CDOT Forn Mix #20		.(s):		Form #633 (Form #634 (
Sample Identification: Quantity & Unit Materials Documentation: Field inspe					ple removed from	(stationing),	etc.
Submitting (3) c	ores for Com	pressive Stre	nath				
Time cored 5:00							
1) 832+88.10	rm Date 37.	12/01					
2) 832+90							
3) 833+00							
Cored at 33 Do							
cored at 33 De	173						
APL/QML Acceptance: APL Ref. No.	Product name:				Dat	e checked:	
ADL/ONL Assentance, ADL Def. No.	Droduct name:				Det	بالمعالمة والما	
APL/QML Acceptance: APL Ref. No.	Product name:				Dat	e checked:	
Preliminary Construc	tion Maintenan	ce Emergency			Da	te needed	7
Contractor	<u> </u>	Supplier				ASAF	
Kraemer and So	ns	Сарриот	Ready M	۸ix			
Sampled from Pit, roadway, windrow, Roadway stock, etc.)		Pit name o	owner				
Quantity represented Placed 2/7/01	Previous	quantity Removed 3	/12/02	Te	otal quantity to date		
Sample submitted: Shipped			Via		Dat		
		Region lab	6	eocal		3/12/	01
Sampled or inspected by (Name) D. Elsbernd	(Title)	Q.A. Tech		Lab phone	e number 303-828	3-2644	
Supervisor (Pro./Res./Matts. Engr./Maint. Supt.)	Title			Address		ee Hill	Rd.
Corey Stewart		P.E. I			Boulder		
istribution: White copy - Staff Materials Br		had to Ctoff M-ti-l-				CDOT For	m #157 9
(submit white copy only if sam Canary copy - Region Materials	Engineer		2 300	***			
Pink copy - Resident Engineer	Prev	vious editions may be u	sed until supplie	s are exha	usted		

Note: Within Date needed, ASAP is not a date.

COLORADO DEPARTMENT OF TRANSPORT FIELD REPORT FOR SAMPLE ID OR MATERIALS DOCUMENTA	DENTIFIC	ATION	Region 4 Contract ID C18180		Id sheet # 251674 te Submitted 04/13/2015
Metric units yes	√ no		Project Locatio		
Address			US 40 Over		
Material Type REINFORCING STEEL				-555-2525	Cell Phone 719-555-5353
Material Code (LIMS) Item 503/601/602	Class		Grading	Sp	pecial Provisions yes
Previously used on Project No.:	Previous	CDOT Form #	157 F/S No.(s):		_
Sample Identification: Quantity & Unit of material subm Materials Documentation: Field inspected (describe ap	pearance, weigl	ht/dimensions	, model/serial nu	imber), COC 8	CDOT Form #634 (can) ved from (stationing), etc. Wor CTR provided , etc.
SUBMITTING 3	STICKS OF	REBAR, 4	FEET LONG	6, #5 BAR	
MANUF	ACTURER A	APPEARS (ON THE QMI		
	TEST AS F	PER A370			
154D154709	R: 0825, 0930), 0830, 09	30, 0365,	Sample ID (
				,	,
APL/QML Acceptance: APL Ref. No. Product name BLACK BA					Date checked: 04/06/2015
APL/QML Acceptance: APL Ref. No. Product name					Date checked:
Preliminary Construction Mainte	_	mergency			Date needed
Contractor HAMON CONTRACTORS, INC.		Supplier EVPAZ P	OCKY MOUI	ITAIN OTE	
Pit, roadway, windrow, STOCKPILE tock, etc.)		Pit name or		NIAIN STE	EL
65,000 LBS	revious quantity	0		Total qua	antity to date 65,000 LBS.
Sample submitted: Shipped specified quantity Yes No Central lab	•		Via TODD MAYH	IFW	Date 04/13/2015
Sampled or inspected by (print name) LESLIE KOCHIS	Title EPST III	-gion iau	E-	mail	②state.co.us
Supervisor (Pro./Res./Matls. Engr./Maint. Supt.) (print name) KARL LARSON	Title CEPM I			esidency MON	
	OLI IVI I		L	IVIOIV	

COLORADO DEPARTMENT OF				Region 4 Contract ID		Field sh	251675
OR MATERIALS DO				C18180		Date S	04/13/2015
				Project No.	FBR 0404	I-050	
Metric units	yes	V	/ no	Project Locat			
				US 40 Ove		reek	
Material Type TIE BAR, EPOXY	COATED	-		Field Lab pho	ne 9-555-25	25	Cell Phone 719-555-5353
Material Code (LIMS)	Item		Class	Grading	9-555-25		Provisions ves
709.03.02.00	412		CLASS P				
Previously used on Project No.:			Previous CDOT Form	#157 F/S No.(s):		CDOT Form #633 (sack) CDOT Form #634 (can)
 Sample Identification: Quantity & L Materials Documentation: Field ins 	pected (describ	oe appear	describe tests required ance, weight/dimension	s, model/serial	on sample re number), CO	emoved	from (stationing) etc.
	MAN	NUFAC	TURER APPEARS	ON THE QN	1 L		
		TE	EST AS PER A370				
MANUFACTURER: GERDAL	AMERISTE	EEL, KA	NSAS CITY				
EPOXY COATING: ABC COA	TING CO. (OF OKL	AHOMA		V V		
LINE ITEMS COVERED BY		IED 00					
LINE ITEMS COVERED BY	HIS SUPPL	JER: 03	30				
Jser ID KOCHISL							
Sample ID (#1)		Sample	D (#2)		Sample	ID (#3)	
154D15592301		Sample	D (#2)		Sample	10 (#3)	
Sample ID (#4)		Sample	ID (#5)		Sample	ID (#6)	
						, ,	
APL/QML Acceptance: APL Ref. No.	Product						Date checked:
QML APL/QML Acceptance: APL Ref. No.	TIE BA						04/06/2015
APLIQUIL Acceptance. APL Rei. No.	Product	name:					Date checked:
Preliminary Const		aintenai	nce Emergency				Date needed
Contractor			Supplier				
HAMON CONTRACTORS, IN	C.	20700		J AMERISTE	EL, KC		
Sampled from (Pit, roadway, windrow, STOCK stock, etc.)	PILE		Pit name o	rowner			
Quantity represented	None of the second seco	Previo	us quantity		Tota	I quantit	y to date
605,000 LBS			0				605,000 LBS.
Sample submitted: Shipp Yes No	ped specified qu Centra	,		Via TODD MAY	/HEW		Date 04/13/2015
Gampled or inspected by (print name) LESLIE KOCHIS		Title			E-mail leslie.koch	nis@st	
Supervisor (Pro./Res./Matls. Engr./Maint. Sup	t.) (print name)	Title			Residency		
KARL LARSON		CE	PMI		LIMON		
stribution: White copy - CDOT Centra (submit white copy only if Canary copy - Region Mate	sample or informa	ation is dire	cted to Staff Materials)				CDOT Form #157 4/1

COLORADO DEPARTMENT O				Region 1	Field shee	251676
FIELD REPORT FOR			ATION	Contract ID C18180	Date Sub	mitted 04/23/2015
OR MATERIALS DO	CUMENTA	ATION		Project No.		0 1/23/2010
Metric units	yes	√ no			BR 0404-050	
				Project Location US 40 Over	Sand Creek	
Material Type REINFORCED CC	NCRETE PIPE			Field Lab phone	e C	ell Phone 719-555-5353
Material Code (LIMS) 706.02.01.00	Item 624	Class CLASS	7	Grading		Provisions yes
Previously used on Project No.:		Previous	CDOT Form #	\$157 F/S No.(s):		DOT Form #633 (sack) DOT Form #634 (can)
Sample Identification: Quantity & L Materials Documentation: Field ins		ppearance, weig	ht/dimensions	, model/serial n	sample removed fro	m (stationing), etc.
18" 19 L. FT.	1 END SECTION	ON LINE IT	TEM 0295 8	0310		
24" 120 L. FT.	1 END SECTI	ON LINE I	TEM 0300 8	k 0315		
30" 212 L. FT.	1 END SECT	ION LINE IT	ΓΕΜ 0305 8	0320		
KOCHISL Sample ID (#1) 154N083546 Sample ID (#4)		mple ID (#2)			Sample ID (#3) Sample ID (#6)	
APL/QML Acceptance: APL Ref. No.	Product nam	ie.				Date checked:
QML	RCP					04/06/2015
APL/QML Acceptance: APL Ref. No.	Product nam	ne:				Date checked:
Preliminary Const	_	tenance E □	mergency			Date needed
Contractor HAMON CONTRACTORS, IN	IC.		Supplier OLD CAS	TLE PRECA	ST PLATTEVILL	E
Sampled from (Pit, roadway, windrow, stock, etc.)			Pit name or	owner		
Quantity represented SEE ABOVE		Previous quantity	/		Total quantity	o date
	ped specified quanti Central Ia	,	Region lab	Via		Date
Sampled or inspected by (print name) LESLIE KOCHIS		Title EPST III			-mail eslie.kochis@sta	e.co.us
Supervisor (Pro./Res./Matls, Engr./Maint, Sup KARL LARSON	ot.) (print name)	Title CEPM I			lesidency IMON	
	al Laboratory					CDOT Form #157 4/

COLORADO DEPARTMENT OF TRA FIELD REPORT FOR SAM OR MATERIALS DOCUM	IPLE IDE	NTIFIC	ATION	Region 1 Contract ID C18180		Field sheet # 251677 Date Submitted 04/25/2015
				Project No.	FBR 0404-	
Metric unitsy	/es	√ no		Project Locat US 40 Ove		reek
Material Type PIPE , CORRUGATED S	STEEL			Field Lab pho	ne 19-555-252	Cell Phone 25 719-555-5353
Material Code (LIMS) Item 707.02.01.00 603		Class		Grading		Special Provisions yes
Previously used on Project No.:		Previous (CDOT Form #	157 F/S No.(s	s):	CDOT Form #633 (sack) CDOT Form #634 (can)
Sample Identification: Quantity & Unit of m. Materials Documentation: Field inspected ((describe appe	arance, weigh	nt/dimensions	, model/serial	number), CO	emoved from (stationing), etc. DC &/or CTR provided , etc.
15" 297 L. FT. LINE ITEM 0)595					
18" 1502 L. FT. LINE ITEM 0	600					
24" 186 L. FT. 2-END SECTIO	ONS LINE I	TEM 0605				
30" 157 L. FT. 2-END SECTION	ONS LINE I	TEM 0610				
User ID		e ID (#2)			Sample	
Sample ID (#4)	Sampl	e ID (#5)			Sample	ID (#6)
APL/QML Acceptance: APL Ref. No.	Product name:					Date checked:
APL/QML Acceptance: APL Ref. No.	Product name:					Date checked:
Preliminary Construction	Mainten	ance En	nergency			Date needed
Contractor HAMON CONTRACTORS, INC. Sampled from (Pit, roadway, windrow, stock, etc.)			Supplier CONTEC Pit name or	H ENGINE	ERED SOL	LUTIONS
Quantity represented SEE ABOVE	Prev	ious quantity			Total	Il quantity to date
	cified quantity to		egion lab	Via		Date
Sampled or inspected by (print name) LESLIE KOCHIS	Т	itle EPST III	3		E-mail leslie.koch	nis@state.co.us
Supervisor (Pro./Res./Matls. Engr./Maint. Supt.) (print na		itle CEPM I			Residency LIMON	
KARL LARSON	10	JEI IVI I				

COLORADO DEPARTMENT OF TR FIELD REPORT FOR SAN			ATION	Region 1 Contract ID		Field sheet # 210358 Date Submitted
OR MATERIALS DOCU	MENTA	ΓΙΟΝ		C18180		04/17/2015
				Project No.	BR 0404	4 050
Metric units	yes	√ no		Project Location	on	
				US 40 Ove	r Sand C	reek
Material Type Guard Rail, End Treatme	ents, Posts	and Blocks		Field Lab phor	e 9-555-25	Cell Phone 719-555-5353
Material Code (LIMS) Item See Below 606		Class		Grading	000 20	Special Provisions yes
Previously used on Project No.:		Previous (CDOT Form #	157 F/S No.(s)	:	CDOT Form #633 (sack) CDOT Form #634 (can)
 Sample Identification: Quantity & Unit of m Materials Documentation: Field inspected Guardrail and End Treatments of the control of	(describe appe	earance, weigh	nt/dimensions	, model/serial r	umber), C	OC &/or CTR provided , etc.
1) Type 3 (6-3Post Spacing) 71	0.05.01.00	Line Ite	m: 0430			
2) End Anchorage Type 3D, Transi	tion Type 30	G, Transitio	n 3H, Medi	an Terminal	, End An	chorage (Nonflared)
All above items-Materia	I Code 606.	.02.03.00	Line Items	s: 0435, 044	10, 0445,	, 0450, & 0455
3) Guardrail Hardware, End Anchor	Rods 710.	.09.01.00	_ine Item: ()435	9	
4) Traffic Control, Reflective Sheeti	ng 713.04	1.01.00 Lin	e Item: 04	55		
User ID KOCHISL						
Sample ID (#1)	Samp	ole ID (#2)			Sample	e ID (#3)
154H223815	154F	1224229			154H2	224801
Sample ID (#4) 154H225206	Samp	ole ID (#5)			Sample	e ID (#6)
APL/QML Acceptance: APL Ref. No.	Product name:					Date checked:
APL/QML Acceptance: APL Ref. No.	Product name:					Date checked:
Preliminary Construction	n Maintei	nance Er	mergency			Date needed
Contractor HAMON CONTRACTORS			Supplier Adarand-	Nucor Steel	Kinamar	n A7
Sampled from (Pit, roadway, windrow, STOCKPILE ON PF stock, etc.)	ROJECT		Pit name or		Tungman	1, 7, 10-
Quantity represented	Pre	vious quantity			Tota	al quantity to date
Sample submitted: Shipped spe	cified quantity	to:		Via		Date
		D R	egion lab	V.IG		Duic
Sampled or inspected by (print name) LESLIE KOCHIS		Title EPST III		1	E-mail eslie.koc	his@state.co.us
Supervisor (Pro./Res./Matls, Engr./Maint, Supt.) (print in KARL LARSON		Title CEPM I			Residency IMON	
		∪ E1 1V1 I				
Distribution: White copy - CDOT Central Labora (submit white copy only if sample of						CDOT Form #157 4/1

COLORADO DEPARTMENT OF T				Region 1		Field sheet	[#] 210362
FIELD REPORT FOR SA OR MATERIALS DOCU			ATION	Contract ID C18180		Date Subr	04/28/2015
) IVI I V I /	111011		Project No.	BR 040	4.050	
Metric units	yes	√ no		Project Locati		4 030	
				US 40 Ove		Creek	
Material Type Light Standards and L	uminaires,	Foundation H	ardware	Field Lab phor	ne 9-555-25		Il Phone 719-555-5353
Material Code (LIMS)	em 06	Class		Grading	3 000 20	Special Pr	
Previously used on Project No.:		Previous (CDOT Form a	#157 F/S No.(s):		OOT Form #633 (sack) OOT Form #634 (can)
 Sample Identification: Quantity & Unit of Materials Documentation: Field inspect 	ed (describe a	ppearance, weigh	nt/dimensions	s, model/serial	number), C	OC &/or CT	R provided , etc.
The following items have be	en inspecte	d, COC's and	Buy Amei	rican on reco	ord. See	Attachme	ent icon in SMM
1) Light Standard and Luminaire	[Decorative]	715.04.02.0	00 Line I	tem: 0540 2	Each		
2) Light Standard Steel (35 Foot)		715.03.01.0)1 Line If	tem: 0545 6	Each		
3) Light Standard Foundation(Mis	c. Hardwar	e) 509.10.01.0	00 Line I	tem 0550 6	Each		
4) Luminaire HP Sodium (250 Wa	att)	715.04.01.0	01 Line I	tem 0560 1	2 Each		
5) Luminaire HP Sodium (Wall) (150 Watt)	715.04.01.0	02 Line I	tem: 0880 &	0985 2	Each	
User ID KOCHISL	60						
Sample ID (#1) 154S213915		mple ID (#2) 4S214209			1 '	e ID (#3) 244601	
Sample ID (#4)		imple ID (#5)			Sampl	e ID (#6)	
154S215315	15	4S215823					
APL/QML Acceptance: APL Ref. No.	Product nan	ne:					Date checked:
APL/QML Acceptance: APL Ref. No.	Product nan	ne:					Date checked:
Preliminary Construct		tenance Er □	mergency	STATE OF THE STATE			Date needed
Contractor HAMON CONTRACTORS			Supplier	MILLS PROI	NICTS		
Sampled from (Pit, roadway, windrow, STOCKPILE ON stock, etc.)	PROJECT		Pit name or		20010		
Quantity represented	F	Previous quantity			To	tal quantity to	o date
Sample submitted: Shipped	specified quant	tity to:		Via			Date
	-	b 🗆 R	egion lab				
Sampled or inspected by (print name) LESLIE KOCHIS		Title EPST III			E-mail leslie.ko	chis@stat	e.co.us
Supervisor (Pro./Res./Matls. Engr./Maint. Supt.) (pro./Res./Matls. Engr./Maint. Supt.)	int name)	Title CEPM I		1	Residency LIMON		
Distribution: White copy - CDOT Central Lab	oratory		************		LIIVIOIN		CDOT Form #157 4/1
(submit white copy only if same	le or information Engineer	is directed to Staff	Materials)				

COLORADO DEPARTMENT OF T	MPLE IDE	ENTIFICA		Region 1 Contract ID		Field s	210373 Submitted
OR MATERIALS DOCU	JMENTAT	TON		C18180 Project No.	FBR 0404	050	05/01/2015
Metric units	yes	√ no		Project Locat US 40 Ove	ion		
Material Type Prestressed Material,	Steel Wire Str	rand		Field Lab pho			Cell Phone
Material Code (LIMS)	em 18	Class		Grading	9-555-25		719-555-5353 al Provisions yes
Previously used on Project No.:	10	Previous C	DOT Form #	157 F/S No.(s	s):		CDOT Form #633 (sack) CDOT Form #634 (can)
 Sample Identification: Quantity & Unit o Materials Documentation: Field inspected 		earance, weight	t/dimensions				I from (stationing), etc.
See Attachment icon	in SMM for co	py of the CT	ΓR and Bu	y American	Letter		
1) One strand, 5-1/2 ft. Heat # 6	18922						
2) One strand, 5-1/2 ft. Heat #6	318919						
User ID KOCHISL							
Sample ID (#1) 155S221056	Samp	le ID (#2)	S221809		Sample	e ID (#3)	1
Sample ID (#4)	Samp	ole ID (#5)			Sample	e ID (#6)
APL/QML Acceptance: APL Ref. No.	Product name:						Date checked:
APL/QML Acceptance: APL Ref. No.	Product name:						Date checked:
Preliminary Constructi ☐ ☑	ion Mainter	nance Em	nergency				Date needed
Contractor HAMON CONTRACTORS Sampled from			Supplier Insted Wi Pit name or	re Products	;		
(Pit, roadway, windrow, STOCKPILE ON stock, etc.)		·			Tot	-1 augnt	On the shake
Quantity represented 25 coils		vious quantity	0		Tot	al quam	25 Coils
	Specified quantity to Central lab		egion lab	Via CDOT			Date 05/03/2015
Sampled or inspected by (print name) LESLIE KOCHIS		Title EPST III				:his@s	state.co.us
Supervisor (Pro./Res./Matls, Engr./Maint, Supt.) (pr KARL LARSON		Title CEPM I			Residency LIMON		
	oratory						CDOT Form #157 4/1

COLORADO DEPARTMENT FIELD REPORT FOR	SAMPL	E IDENTIFIC	MOLTA	Region 1 Contract ID C18180		Field sheet # 21037 Date Submitted	75 5/05/2015
OR MATERIALS DO				Project No.	FBR 0404		5.00,2010
Metric units	yes	√ no		Project Locat US 40 Ove		reek	
Material Type Prestressed Mate	rial, Steel B	 ar		Field Lab pho	one 19-555-25	Cell Phone	555-5353
Material Code (LIMS) 714.01.02.00	Item 618	Class		Grading	19-333-23	Special Provisions	yes
Previously used on Project No.:		Previous	CDOT Form #	157 F/S No.(s	s):	CDOT Form #	[‡] 633 (sack)
 Sample Identification: Quantity & Materials Documentation: Field in See Attachment 	spected (descr Submit	ibe appearance, weig ting 1 bar, 42" lor	ght/dimensions, ng	model/serial	number), Co		
				,			
				11 -			
					9		
User ID KOCHISL							
Sample ID (#1)		Sample ID (#2)			Sample	e ID (#3)	
1555124523							
Sample ID (#4)		Sample ID (#5)			Sample	e ID (#6)	
APL/QML Acceptance: APL Ref. No	. Produc	t name:				Date che	cked:
APL/QML Acceptance: APL Ref. No	. Produc	t name:				Date che	cked:
	truction M	Maintenance E	Emergency			Date need	ded
Contractor HAMON CONTRACTORS			Supplier Insted Wir	e Products	3	·	
Sampled from (Pit, roadway, windrow, STOCKPILE stock, etc.)	ON PROJE	СТ	Pit name or o				
Quantity represented 5 Ton		Previous quantity	0		Tota	al quantity to date 5 T	on
Sample submitted: Shi	pped specified Centr	quantity to: al lab		_{Via} CDOT		Date 05/08/2	015
√ Yes □ No 1		Title			E-mail leslie.koc	:his@state.co.us	
√ Yes □ No 1		EPST III					
Yes No 1 Sampled or inspected by (print name) LESLIE KOCHIS	upt.) (print name)	Title CEPM I			Residency LIMON		
Yes No 1 Sampled or inspected by (print name) LESLIE KOCHIS Supervisor (Pro.Res./Matls. Engr./Maint. S	ral Laboratory	Title CEPM I	ff Materials)		20 000 000000000	CD	OT Form #157 4/14

COLORADO DEPARTMENT OF THE FIELD REPORT FOR SA	MPLE I	DENTIFICA	ATION	Region 1 Contract ID C18180		Date Submitted 08/05/2015
OR MATERIALS DOCU	,			Project No.	BR 0404	
Metric units	yes	√ no		Project Location US 40 Ove		eek
Material Type Pavement Marking Ma	terial			Field Lab phor	ne 9-555-252	Cell Phone 719-555-5353
Material Code (LIMS) Ite See Below 62	m	Class		Grading		Special Provisions yes
Previously used on Project No.:		Previous (CDOT Form #	‡157 F/S No.(s)):	CDOT Form #633 (sack) CDOT Form #634 (can)
 Sample Identification: Quantity & Unit of Materials Documentation: Field inspecte Pavement Mark 	d (describe a	ppearance, weigh	nt/dimensions	, model/serial r	number), CO	C &/or CTR provided , etc.
See the	Attachmen	t Icon In SMM	I to view C	OC's and C	TR's	
1) Traffic Control, Glass Beads, E	poxy Mark	713.08.02.00	Line Iter	m: 0630		
2) Traffic Control, Epoxy Marking,	Yellow	713.17.01.0	1 Line Iter	n: 0630		
3) Traffic Control, Epoxy Marking,	White	713.17.01.0	2 Line Ite	m: 0630		
4) Traffic Control, Beads 713.0	8.04.00 Lir	ne Item: 0635	5) Pair	t, Pavement	Marking	708.05.01.00 Line Item: 0635
User ID KOCHISL						
Sample ID (#1) 1585154589		mple ID (#2) 85155513			Sample I	
Sample ID (#4) 1585161018		mple ID (#5) 85162239			Sample I	ID (#6)
APL/QML Acceptance: APL Ref. No. 2424	Product nam Epoplex L	ne: .S50, Yellow				Date checked: 08/01/2015
APL/QML Acceptance: APL Ref. No. 2423	Product nan Epoplex L	ne: .S50, White				Date checked: 08/01/2015
Preliminary Constructi		tenance Er □	nergency			Date needed
Contractor HAMON CONTRACTORS			Supplier Epoplex-	Epoxy Paint	t, Beads-P	Potters
Sampled from (Pit, roadway, windrow, stock, etc.)			Pit name or	owner		
Quantity represented		Previous quantity			Total	I quantity to date
	pecified quant Central la	b 🗆 R	egion lab	Via		Date
Sampled or inspected by (print name) LESLIE KOCHIS		Title EPST III			E-mail leslie.koch	nis@state.co.us
	nt name)	Title			Residency	
Supervisor (Pro./Res./Matls. Engr./Maint. Supt.) (print KARL LARSON		CEPM I			LIMON	

Note: Within Date needed, ASAP is not a date.

CONCRETE		F TRANSPOR	TATION		18180	Date Submitted	04/01/2015
INSPECTIO			N	Project locati	BR 0404-050 on Over Sand Cre	eek	
				Concrete con	Ready M	/lixed	
Unit number	252	251	250	247	248	245	239
Rated mixing capacity (1)	10 yds	10 yds	10 yds	10 yds	10 yds	10 yds	10 yds
Blade wear (2)	ОК	ОК	ОК	ОК	ОК	ОК	ОК
Free of Hardened concrete (3)	YES	YES	YES	YES	YES	YES	YES
Revolution counter	YES	YES	YES	YES	YES	YES	YES
Nater gauges	YES	YES	YES	YES	YES	YES	YES
Meets operating speed requirements	YES	YES	YES	YES	YES	YES	YES
			04/01/15	04/01/15	04/04/45		
Date inspected	04/01/15	04/01/15	04/01/15	04/01/13	04/01/15	04/01/15	04/01/15
(1) Rated mix (2) Blade wea configurat Mixer blade types:	GREG M. ing capacity of ar cannot excions see "x" of a cannot excions see "x" of a cannot excions see "x" of a cannot excite the cannot e	GREG M. cannot exceed eed more than limensions belo	GREG M. 63% of gross 25 mm (one in ow.	GREG M. volume of dru nch) of the orig "Straight"	GREG M.	GREG M.	GREG M.
(1) Rated mix (2) Blade wea configurat Mixer blade types:	gred M. ing capacity of ar cannot excions see "x" of a cannot have a mixers liste of specificat er penalty.	gred M. cannot exceed eed more than limensions belief an appreciable ed above were ions.	GREG M. 63% of gross 25 mm (one in ow.	"Straight" of hardened ond met the recond DEGRE	green M. m ginal height. For the concrete inside the quirements for the concrete inside the concrete inside the quirements for the concrete inside the conc	GREG M. or typical blade typical blade or conformance	GREG M.
(2) Blade wear configurat Mixer blade types: (3) The drum I certify the truck the AASHTO M15	gred M. ing capacity of ar cannot excions see "x" of a cannot have a mixers listed of specificat green and the cannot have a mixer serious to the cannot ha	gred M. cannot exceed eed more than limensions bel an appreciable ed above were ions. Y OF PERJUR LAWS, THAT ST OF MY KN	GREG M. 63% of gross 25 mm (one in ow.) e accumulation inspected ar Y IN THE SECUTION THE SEC	"Straight" of hardened ond met the recond DEGRE	green M. m ginal height. For the concrete inside the quirements for the concrete inside the concrete inside the quirements for the concrete inside the conc	GREG M. or typical blade typical blade or conformance	GREG M.
(2) Blade wear configurat Mixer blade types: (3) The drum I certify the truck the AASHTO M15 I DECLARE UNDICABLE STATE O AND COMPLETE	cannot have mixers lister of specificat ER PENALTY R FEDERAL TO THE BE cipal executive, s	gred M. cannot exceed eed more than limensions belong an appreciable ed above were ions. Y OF PERJUR LAWS, THAT ST OF MY KN signature and title	GREG M. 63% of gross 25 mm (one in ow.) e accumulation inspected and inspected are i	"Straight" of hardened ond met the recond DEGRE	green M. m ginal height. For the concrete inside the quirements for the concrete inside the concrete inside the quirements for the concrete inside the conc	GREG M. or typical blade typical blade or conformance	GREG M.
(1) Rated mix (2) Blade wea configurat Mixer blade types: (3) The drum I certify the truck the AASHTO M15 I DECLARE UNDICABLE STATE O AND COMPLETE Concrete company's prin	cannot have mixers listed for the BE cipal executive, secked by CI tion (Certifiers na	eed more than limensions belong an appreciable ed above were ions. Y OF PERJUR LAWS, THAT ST OF MY KN signature and title	GREG M. 63% of gross 25 mm (one in ow.) e accumulation inspected and are inspected and inspected a	"Straight" of hardened of met the recond DEGREMENTS MADE	green M. m ginal height. For the concrete inside the quirements for the concrete inside the concrete inside the quirements for the concrete inside the conc	GREG M. or typical blade or conformance OTHER APPL CUMENT ARE	GREG M.
(1) Rated mix (2) Blade wear configurat Mixer blade types: (3) The drum I certify the truck the AASHTO M15 I DECLARE UNDICABLE STATE OF AND COMPLETE Concrete company's print Completed and chestoche plant scale certifica	cannot have mixers listed for the BE cipal executive, secked by CI tion (Certifiers na	eed more than limensions belong an appreciable ed above were ions. Y OF PERJUR LAWS, THAT ST OF MY KN signature and title	GREG M. 63% of gross 25 mm (one in ow.) e accumulation inspected ar Y IN THE SECUTION THE STATEM IOWLEDGE.	"Straight" of hardened of met the recond DEGREMENTS MADE	green M. m ginal height. For the concrete inside the concrete in	GREG M. or typical blade or conformance OTHER APPL CUMENT ARE	GREG M.

INSTRUCTIONS FOR CDOT FORM #82, CONCRETE SPECIMEN TRANSMITTAL

- ♦ Under Item # list the Item for which this concrete was placed.
- ♦ List the 281 ticket number of the load or suppliers ticket no. from which cylinders were made.
- ♦ Design cylinder set numbers for each project and class of concrete will be numbered consecutively beginning with No. 1.
- ♦ Fill in the areas for; Concrete class (A, B, D, etc.), Days cured, Break dates, and No. of cylinders.

Example, Design

Mark Cylinders as indicated	Set no.	Conc. class	Days cured	Break date	No. of cylinders	
Mix Design Cylinders marked	1	Α	7	8/16/99	2	
Mix Design Cylinders marked	1	Α	28	9/6/99	3	
Mix Design Cylinders marked						
				Total	5	
	Set no./class	Field Cylinder	Days cured	Break date	No. of cylinders	
Information Cylinders marked		X				
		X				
Information Cylinders marked		X				

Example, Information

Mark Cylinders as indicated	Set no.	Conc. class	Days cured	Break date	No. of cylinders
Mix Design Cylinders marked					
Mix Design Cylinders marked					
Mix Design Cylinders marked					
				Total	
	Set no./class	Field Cylinder	Days cured	Break date	No. of cylinders
Information Cylinders marked	Set no./class	Field Cylinder	Days cured	8/19/99	No. of cylinders
Information Cylinders marked Information Cylinders marked	4 .				No. of cylinders 1 1

Structural strength "Information" cylinders will be marked with the same set number as the Design cylinders from the same batch; Set No/Concrete class, Days cured, and Break date. Normally "X" cylinders will be cast at the same time as design cylinders and cured under the same conditions as the structure. In the column under "Days Cured" indicate the test data desired (7, 11, 14, 21, etc days cured) with the appropriate break date entered in the next column, and number of cylinders.

Note: Use separate Form #82s for Design and Information cylinders.

Under **QUANTITIES REPRESENTED** list the measurement applicable to the Pay Item. Report the previous placement quantity of the item under "To Date". Under "This Placement" list the quantity represented by the current Form #82 including any small quantity that did not require cylinders, and then list the total quantity of this class of concrete to date. Enter the specification for Compressive Strength Required.

COLORADO DEPARTMENT OF TRANSPORTATION	OF TRANSPOR	TATION	Project No.	o. IM 0253-151		Project code (SA#) 11925	Proj. location	I-25 SH 7 to WCR 16	WCR 16
CONCRETE OF COMMENT IN AN DIMINISTRATION OF ENGLISH OF Metric	MEN I HAIN etric	SMITTAL	Date 11	11/05/03	Region Res	Resident Engineer D. Forsyth	CDOT Mix#	2007004	
Zead	ked	Applicable CDOT F OR Suppliers ticket	Applicable CDOT Form #281 Field Sheet # OR Suppliers ticket #:	135789	Station	Wall Cap	Item & Description	ption 601 Structural	ıctural
Slump 3.00 inches (mm)	n) Entrainedair	6.1	% Unitweight 14	143.4 lbs/ft³ (kg/m³)	kg/m³) Yield	1.01	Col	Concrete temperature	78 °F (°C)
Cylinders for design adequacy		Date molded 11/5/03	Time 10	10:45 am	Curedhrs.	Days in Days in molds 1	n 🚨 Damp sand 🔀 Water		at Temp.
Cylinders for structural strength information	th information	Date molded	Time		Cured hrs.	Days in Days at molds site	Days at structure Ship site to	Shipped Cen	Central lab
Mark Cylinders as indicated	Set no.	Conc. class	Days cured	Break date	No. of cylinders	lers	Laboratory test results	test results	
Specimen Identification	1	۵	7	11/12/03	2	Specimenage	Diameter (beam - H x W)	Totalload	PSI/MPa
Specimen Identification	1	Δ	28	12/3/03	ო	7	3.99	96089	
Specimen Identification						7	4.00	62031	
Specified strength (PSI/MPa) 4500	0	QA/QC specification (broke	(6)	28 days)	□ yes □ r	no 28	3.99	76840	
Specimen type: X 4 x 8 cylinder		Beam 🗅 S	Splitting C	Cube		28	4.00	76514	
						28	4.00	78456	
	Previous	This pl	This placement	To date					
Quantity represented cubic yards/meters	0		100 ¢U YD	100 (100 CU YD		9		
Field Comments:					Lat	Lab comments:			
I.A.T./Remarks:									
Cast by:	Transport	Transported by:(Name/Title/Company)	Company)	100	Pho	Phone number		FAX number	100
		-	Tones P/PST			303-555	234	303-555-A	42.

COLORADO DEPARTMENT OF TRANSPORTATION	NT OF TRANSP(ORTATION	_			Contract ID	J	C18180		Region 1	Date Su	Date Submitted 03/12/2015	12/2015
CONCRETE TEST RESULTS SUMMARY	TRESULT	SSUM	MARY			Project No.	Project No. FBR 0404-050	050					
Note: Field tester to fill out form		Metric units	À	yes 🖾 no		Project location	tion US 40	US 40 Over Sand Creek	1 Creek				
Item 601	Class	Design mix no.	.or 2013048	48		Batch pla	Batch plant Ready Mixed-Denver	Mixed-Den	Iver	Specifications:	ons: 601 CL.	D-Bridge	
User ID KOCHISL	Slump	5.25"	i	ches/mm	inches/mm maximum	% total air	air 5.0	To 8.0		Compress	Compressive strength	4500	Psi/MPa
SMM/LIMS Sample ID (or Test #)	Date Placed	Ticket no.	Cu. yd Batched	Cu. yd./Cu. m	Temp.	Slump	% total air	Unit mass	Yield	Calculated w/c ratio	Cylinders casted F.S. no.	Set No.	S. E.
1535110136	03/06/2015	000312	10	10	64	3.75	7.1	140.0	660	.40			
1535111025	03/06/2015	000313	10	0	89	7.5	7.6	140.8	1.00	.41			
1535112505	03/06/2015	000314	10	10	99	5.9	4.5	141.9	1.01	.40			
1535114513	03/06/2015	000315	10	10	99	5.6	4.25	142.0	1.01	.39	22589	2-D	
1535120505	03/06/2015	000316	10	10	68	5.8	4.0	141.2	1.00	.40			
1535123056	03/06/2015	000319	10	10	29	6.4	4.5	141.1	1.00	.39			
Action taken to document deviations from specifications (including quantities with price reduction calculations attached) Ticket # 00313 rejected due to out of specification slump.	ons from specification to out of specif	l ns (including c ication slun	yuantities wi	th price red	uction calcu	ulations attacl	hed).						
Fester (print name) Leslie Kochis		Title	ritle CEPM I		Project Karl L	Project Engineer (print name) Karl Larson	int name)		Signature	0		Title	ritle CEPM I
Distribution: original - Project file		-			-							TOGO	CDOT Form #156 4/14

COLORADO DEPARTMENT OF TRANSPORTATION		ORTATION	7			Contract ID		C18180		Region 1	Date St	Date Submitted 03/12/2015	12/2015
CONCRETE TEST RESU		LTS SUMMARY	MARY	ı		Project No.	Project No. FBR 0404-050	.050					
Note: Field tester to fill out form		Metric units		□ yes ☑ no		Project location	tion US 40	US 40 Over Sand Creek	d Creek				
Item 601	Class	Design mix no.	no. 2013048	148		Batch pla	Batch plant Ready Mixed-Denver	Mixed-Der	lver	Specificat	Specifications: 601 CL. D-Bridge	. D-Bridge	
User ID KOCHISL	Slump	5.25"	.⊑	ches/mm	inches/mm maximum	% total air	air 5.0	To 8.0		Compress	Compressive strength	4500 F	Psi/MPa
SMM/LIMS Sample ID (or Test #)	Date Placed	Ticket no.	Cu. yd Batched	Cu. yd./Cu. m	Temp.	Slump	% total air	Unit mass	Yield	Calculated w/c ratio	Cylinders casted F.S. no.	Set No.	S. E.
1535110136	03/06/2015	000312	10	10	64	3.75	7.1	140.0	660	.40			
1535111025	03/06/2015	000313	10	0	89	7.5	7.6	140.8	1.00	.41			
1535112505	03/06/2015	000314	10	10	99	5.9	4.5	141.9	1.01	.40			
1535114513	03/06/2015	000315	10	10	99	5.6	4.25	142.0	1.01	.39	22589	2-D	
1535120505	03/06/2015	000316	10	10	89	5.8	4.0	141.2	1.00	.40			8
1535123056	03/06/2015	000319	10	10	29	6.4	4.5	141.1	1.00	.39			
Action taken to document deviations from specifications (including quantities with price reduction calculations attached). Ticket # 00313 rejected due to out of specification slump.	ons from specificati e to out of spec	ons (including iffication slui	quantities wii	th price red	uction calcu	lations attack	hed).						
												$\ \cdot\ $	
Fester (print name)		Title			Project	Project Engineer (print name)	nt name)		Signature	ā		Title	Title
Leslie Kochis			CHDM		Karlarson	arson							

STATE OF COLORADO

DEPARTMENT OF TRANSPORTATION

DATE TRANSMITTED: 6/06/2007 (final)

PROJECT NO: STA 145A-037 PROJECT CODE: 15201

LOCATION: Keystone Hill

REGION: 5

FIELD SHEET: 116216 SUPPLIER: Contractor on Site

Placed at: Sta. 602+54

Portion: Micropiles

REPORT OF CONCRETE TESTS

Item No.: 503

Concrete Class: Grout Micropiles

Date Molded: 5/8/2007

Slump: N/A

Air: N/A Unit Weight: N/A

Cylinder Set No.: 11G

				Cross -	Maximum	Compressive
Specimen	Date	Age		Sectional	Load	Strength
Number	Tested	(Days)	Cubes	Area	(Lbs)	(PSI)
11G	05/11/07	3	2"x 2"	4 sq. in.	16238	4060
11G	05/11/07	3	2"x 2"	4 sq. in.	18521	4630
11G	05/11/07	3	2"x 2"	4 sq. in.	16438	4110
11G	06/06/07	28	2"x 2"	4 sq. in.	20587	5147
11G	06/06/07	28	2"x 2"	4 sq. in.	22620	5655
11G	06/06/07	28	2"x 2"	4 sq. in.	18186	4547**

Average Break Strength:

3-day: 4270 psi 28-day: 5400 psi**

Remarks: Cubes tested in accordance with AASHTO T - 106.

**NOTE: Last cube out of allowable tolerance, average calculated off 2 cubes.

COMPRESSIVE STRENGTH REQUIRED: 3 day: 2500 psi, 28 day: 4000psi

MICHAEL COGGINS

Tested By: Robin S. DiFerdinando (3-day)

Patrick R. Murphy (28-day)

REGION MATERIALS ENGINEER

Cc: Project Engineer

Region Materials Engineer

Resident Engineer

Contractor Project File CDOT Form 192 Revised 11/06

STATE OF COLORADO

PROJECT NO: STA 062A-011

DEPARTMENT OF TRANSPORTATION

PROJECT CODE: 14556 LOCATION: Amelia Street

DATE TRANSMITTED: 6/6/2007

REGION: 5

FIELD SHEET: 108064 SUPPLIER: United Companies

REPORT OF CONCRETE TESTS

Item No.: 601

Placed at: 11+79 55' Rt.

Portion:

Concrete Class: B

Date Molded: 5/10/2007

Air: 5.0 %

Unit Weight: 137.6

Slump: 3.5" Cylinder Set No.: 1B

				Cross -	Maximum	Compressive
Specimen	Date	Age		Sectional	Load	Strength
Number	Tested	(Days)	Diameter	Area	(Lbs)	(PSI)
1B	5/17/07	7	4"	12.57 sq. in.	40801	3246
1B	5/17/07	7	4"	12.57 sq. in.	38683	3077
1B	6/6/07	28	4"	12.57 sq. in.	54445	4331
1B	6/6/07	28	4"	12.57 sq. in.	52892	4208
1B	6/6/07	28	4"	12.57 sq. in.	52045	4140

Average Break Strength:

7-day: 3160 psi 28-day: 4230 psi

Remarks: Cylinders tested in accordance with ASTM C-39.

COMPRESSIVE STRENGTH REQUIRED: 3000 psi

MICHAEL COGGINS

Tested By: Robin S. DiFerdinando (7-day)

Patrick R. Murphy (28-day)

REGION MATERIALS ENGINEER

Cc: Project Engineer

Region Materials Engineer

Resident Engineer Project File CDOT Form 192 Revised 11/06

COLORADO DEPARTMENT OF TRANSPORTATION	Project No.: IM 0253-151
	Project Code: 11925
INSPECTION - QUALITY ASSURANCE	Proj. Location: SH 7 to WCR 16
ACCEPTANCE REPORT	Date: 1/19/03
	Report No.: 12

Colorado Department of Transportation Staff Bridge Design Branch 4201 E. Arkansas Avenue, Room 330 Denver, Colorado 80222

Pay Item Number	618
Pay Item Description	Prestressed Conc. Box/ 32" - 48" Depth
Pay Item Units	Square Foot (SF)
Number of Units QA Inspected	8080 SF
Contract Unit Price	35 \$ Per SF
Structure Number & Construction Phase	D-17-CT
Fabricator	Rocky Mountain Prestress
Prime Contractor	Kraemer and Sons

The above referenced Items were inspected, tested, and accepted by the Contractors Quality Control Unit (QC). CDOT Staff Bridge Design performed random Quality Assurance Inspections and Testing (QA) to the extent necessary to verify that an acceptable product is furnished in accordance with the Contract. The Items were found by QA to be in reasonable conformance with the plans and specifications.

Mark A. Leonard CDOT Staff Bridge Design Engineer

Dana E. Christensen Professional Engineer II

Distribution:
Leonard
Inspection File
Quarterly Report File

By: _____Quality Assurance Inspector

CDOT Form #193 04/04

COLORADO DEPARTMENT OF TRANSPORTATION UNCOATED SEVEN-WIRE STEEL STRAND PHYSICAL TEST REPORT

 Field Sheet No.
 176767
 Project Code
 13579

 Sample Number
 2008001
 Project Number
 C 2706-033

 Sample Date
 1/4/2008
 Project Location
 I-270 Phase VI

 Region
 6

Reel Number	Size	Yield Strength (lbf)	Breaking Strength (lbf)	Modulus of Elasticity (psi)	Elongation in 24" (%)	Nominal Steel Area of Strand (sq. in.)	Nominal Weight of Strand (lb/100 ft.)
4465	15	54,600	61,024	3.059E+07	>3.5	0.217	752
4465	15	54,995	61,330	2.825E+07	>3.5	0.217	755

	AASHTO N	1 203 Spec	ifications	
Strand Designation Number	Nominal Diameter (in)	Minimum Yield Strength (lbf)	Minimum Breaking Strength (lbf)	Minimum Elongation in 24"
9	3/8"	20700	23000	3.5%
13	1/2"	37170	41300	3.5%
13a	0.520"	40500	45000	3.5%
15	0.600"	52740	58600	3.5%

Remarks: Tested in accordance with AASHTO T244

Tested By: Kelvin Jiron Report Date: 1/8/2008 Glenn Frieler

Concrete Physical Properties Engineer
CDOT FORM 196-A

Rev. 1/2008

Project ID: 12183 STATE OF COLORADO

Colorado Department of Transportation Field Sheet #: 99986

Project: IMD 0704-183(B) Location: I 70 WASH TO BRIGHTON Report Date: 5/1/2001 PHASEIII

CONCRETE CORE TEST

Item: 412 Date Placed: 11/28/2000 Class: PFA Date Removed: 11/29/2000 Portion: PAVEMENT ate Size: N/G Date Tested: 12/1/2000

Aggregate Size: N/G Cure Time: 35 Moisture Condition: DRY

Age: 35

CORE ID	TRIM LENGTH (in.)	CAP LENGTH (in.)	DIAMETER (IN.)	MAX LOAD (lbs.)	STRENGTH (PSI)	FRACTUR TYPE	UNIT WEIGHT	CORRECT. FACTOR
01	10.90	11.08	5.55	88400	3654	CONE/SHEAR	10.90	1.00
02	10.87	11.10	5.55	87800	3629	SHEAR	10.87	1.00
03	11.12	11.23	5.62	96900	3906	SHEAR	11.12	1.00

Remarks: Cores were tested in accordance with CP 65-91.

Tested by:

Central Laboratory Regional Materials Engineer Glenn Frieler Concrete/ Physical Properties Program Manager

> CDOT FORM 199 Rev. 04/01

COLORADO DEPARTMENT OF TRANSPORTATION REPORT OF CONCRETE PLACED Sheet #: 1 of ₁ Note: Inspector/Field tester to fill out form Date of Placement 3/10/15 Contract ID C18180 Weather Partly Cloudy Project No. FBR 0404-050 Temperature 54 Superintendent Rita Pryszinski Min. 38 Mix Design No. 2013048 Concrete class D Concrete supplier (plant) Ready Mixed - Denver Added Quality control tests Location Cubic yards Ticket # Sta. Portion On Waste Rej. Ticket # % Air Slump Temp. mix Cyl. # (gals.) 1527+07 Deck 000312 10 000312 7.1 3.75 64 0 000313 7.5 _____ Deck 000313 0 7.6 68 0 000314 4.5 0 5.9 69 1527+19 Deck 000314 10 0 No 5 000315 4.25 5-D 5.6 66 1527+33 Deck 000315 10 0 No 0 000316 4.0 1527+45 5.8 68 0 Deck 000316 10 0 0 000319 6.4 0 1527+58 Deck 000317 3 4.5 67 0 No 1527+74 Deck 000318 10 0 No 5 1527+88 Deck 000319 10 0 No 5 1527+98 000320 Concrete yield Deck 1 No 3 Ticket #000315 (Cyl Set 5-D) Actual Yield = 1.01Cure check Membrane Forming Curing Compound (WR Meadows-White 1610) used along with insulated blankets. Product applied at: (36'x 98')/18 gallons = 196 SF/Gal Thickness check 1527+02 12 ft Right 1527+29 23 ft Right 1527+65 7 ft Right 1527+94 34 ft Right 1/8 Inch Inch 1/4 Inch 1/4 Inch Load represented with Ticket 000313 was rejected due to excessive slump. Maximum allowable is 5.25". Theoretical Volume = 76.1 CY Actual Volume Placed = 76.0 CY Print Name Dennis Bolton Signed Title EPST-I Previous editions are obsolete and may not be used CDOT Form #276 04/14

CONCRE AND PLA	TE BA			Projec	ct code (SA#	٤١	92!		
	(OLD			Date Contra		5, SI 4/02		to W	_
Supplier Ready	Mix	ruck # 02	99 Cu.	Yds. 10.(Kr Des	<u>aem</u> 0001		Class.	Spec
esign weights and	l total batch v			oisture)					Opec
1 CU. YD. Design Wt.	1 type 633 lb	Fly ash 3 type 70 lb	500 lb	Medium 1485	881	26		1 18.0 oz	<u>5</u>
Total adjusted batch Wt.	6485 _{1b}	740 _{lb}	lb	1516C	9140	189	96 gal	180.0 oz	848 _{oz}
Moisture in coarse agg.	4.0	%	re in medium a)g.	%	Moisture in		2.5	
Time charged	11:10	Discha time	rged	12:40		Truck wate	r meter	reading at plar	t
	Field	mixing					E	Batch water	
Mixing revolutions	on job	20				In agg	. 8	6.43	gals.
Gallons of water a	idded	0				At pla	nt 2	27.19	gals.
Cubic yds. in truck		10				Total Max a	oatch	<u>313.62</u>	
Equivalent batch of	gallons	<u>313.62</u>		-		per ba		<u>381.4</u>	3 gals.
Equivalent batch (ch cu. yds. ls. in Truck	— X gals.	water adde	d	Total	allowe	ed 67.86	gals.
Water permitted: _	7225			.44	Χ.	12 = 3	81	.48	gals.
	(Batch Wt. Cement - Ibs.)	·	* '	nximum water	· ·	-		(Maximum	allowed
When % total air	5.2	Slump	3.0	Mix temp	erature 7	n f	Cyl. s		
taken Yield 1	04		(Nomogra	RPM ran	ge 10	12	RPM		
1. Placed at Bric	lge Dec	kF1		Portion	Sna	- <u>- </u>	l	46	
2. Air temp maximum	55 f			Minimum	Spa	<u>n C</u>	Weath	ner Clas	
Lines 1 & 2 repres				l Thr	45 _		<u> </u>	<u>Clea</u>	<u> </u>
Remarks		·		**!!					
Plant inspector	in mempuakima anaddi amuu amu		Harriston, es de espés municipalitation de la constantina de la constantina de la constantina de la constantin	Job inspector			***************************************		
						,	21.3	CDOT Form	

COLORADO DEPA FIELD REPO			Pro	ject No. I	M 0253-151	4/8/U
TESTING		OINT SEAL	Pro	ect code (S. 1925	A#) Proj. location I-25, SH 7	to WCR 16
Project specific loca	ation of test					
4 lane highway WB or SB	WB or SB	EB or NB	EB or NB		2 lane highway	EB or NB
×				OR		
\ \ \ \ \ \ \ \ \ \ \ \ \ \ \ \ \ \ \	(
12		et .				
178+00 Test method		rning 890 S	Self Level		Placement date 3/8/03	Temp 75 °
	CP 67-02 M	ethod A	CP 67	-02 Metho	od B	
Test number 1		Pass	Fail			-
Project specific loca	ation of test					
4 lane highway					2 lane highway	
WB or SB	WB or SB	EB or NB	EB or NB		WB or SB	EB or NB
				OR		
	X					
X						
12.5	12	eet			 	
Station	Sealant material				Placement date	Temp
185+50 Test method		rning 890 s	Self Leve	ling	3/8/03	75 °
rootmonou	CP 67-02 M	ethod A	⊠ CP 67-	-02 Metho	od B	
Test number 1		∑ Pass	Fail	***************************************		
Project specific loca	ition of test			·		
4 lane highway					2 lane highway	
WB or SB	WB or SB	EB or NB	EB or NB			EB or NB
				OB		
	X			OR		
	×					
 12 	12 "	 				
Station	Sealant material	eet		I	feet Placement date	Temp
202+25	Dow Co	rning 890 <i>S</i>	ielf Level	ing	3/8/03	76 °
Test method	☐ CP 67-02 M	ethod A	⊠ CP 67-	02 Metho	od B	
Test number 1		X Pass	Fail			
<u> </u>						
Tester						

		MENT OF T		RTATION	Project No. FBR 0404 Project Location US 40 Ove		C18180
Contractor/Sup		Contractors	q		Item	Class	Lot
Attention: Larr	y Jones		,		601	D	
TEST NO.	Set 1-D	Set 2-D	Set 3-D	Set 4-D	TK#100238	Item Descript	ion
DATE	04/05/2015	04/15/2015	04/23/2015	4/25/2015	4/28/2015	Class D #30	45400
STATION	1003+56	1005+10	1004+00	1004+56	1003.56	Class D #20	15106
LOCATION	Abut #1	Abut #4	Pier Cap#2	Pier Cap#3	NE-Wall	0	E-95- v T4-4
QUANTITY	100 CY	100 CY	100 CY	100 CY	9.0 CY	Specs	Failing Test #
Sieve							
Sieve							
Sieve							
Sieve							
Sieve							
Sieve							
Sieve							
Sieve				140			
Sieve							
Sieve							
Sieve							
L.L.							
P.I.							
% Bitumen							
Max SpG							
Voids							
VMA							
% Rel. Comp.							
% Moisture							
Slump	3-3/4"	4"	3-1/2"	3-3/4"	5-1/4"	2" to 6"	
% Air	6.1	6.8	5.5	5.7	9.2	5.0-8.0%	TK#100238
Flex/Cyl PSI	4870	4650	5210	5350		>4500	
Other:							
	content on TK #1	ponding Sample ID (n the high end.		Remarks (below)		Time
Leslie Kochis	i .		CDOT (sign na			Date 04/28/2015	Time 9:15 am
Contractor's Rep	resentative (print	name)	Contractor's Ke	epresentative (sig	in name)	Date 4/29/2015	8:10 am

COLORADO DEPARTMENT OF TRANSPORTATION REINFORCING BAR PHYSICAL TEST REPORT

Field Sheet No.: 1234 Sample Number: 1234 9/18/2007 Sample Date:

Project Code: 1 Project No.:

SCM

Project Location: Colorado School of Mines

Region:

Manufacturer: Ameristeel Plant:

Heat Number:

Charlotte

60 Bar Grade: S Bar Type:

3 Bar Size:

Bar	Yield Strength (psi)	Tensile Strength (psi)	Elongation (%)	Reduction of Area (%)	Unit Weight (Ibs/ft)	Bar Diameter (Inches)
1	59,102	81,342	14.78	46.77	0.366	0.392
2	57,962	80,426	16.19	45.55	0.366	0.393
ASTM A 615 SPECS	Minimum	Minimum	Minimum			
Grade 40	40,000	60,000	*A	N/A	N/A	N/A
Grade 60	60,000	90,000	*B	N/A	N/A	N/A

^{*}A: 11 for bar size #3; 12 for bar sizes #4 to #6

Remarks: Tested in accordance with ASTM A 370

Glenn Frieler

Concrete _Physical Properties Engineer CDOT FORM 1372

Rev. 1/2007

Tested by: Kelvin Jiron Report Date: 9/19/2007

^{*}B: 9 for bar sizes #3 to #6; 8 for bar sizes #7 to #8; 7 for bar sizes #9 to #18

COLORADO DEPAR	TMENT OF TRANSPO	RTATION
REINFORCING	BAR PHYSICA	L TEST REPORT

 Field Sheet No.:
 1234

 Sample Number:
 1234

 Sample Date:
 9/18/2007

Project Code: 1
Project No.: S0

SCM

Project Location: Colorado School of Mines

Region:

Manufacturer: Ameristeel

Plant: Charlotte
Heat Number:

Bar Grade: 60
Bar Type: S
Bar Size: 3

Bar	Yield Strength (psi)	Tensile Strength (psi)	Elongation (%)	Reduction of Area (%)	Unit Weight (lbs/ft)	Bar Diameter (Inches)
1	59,102	81,342	14.78	46.77	0.366	0.392
2	57,962	80,426	16.19	45.55	0.366	0.393
ASTM A 706 SPECS	Range	Minimum	Minimum			
	60,000 - 78,000	80,000	*A	N/A	N/A	N/A

*A: 14 for bar sizes #3 to #6; 12 for bar sizes #7 to #11; 10 for bar sizes #14 and #18

Remarks: Tested in accordance with ASTM A 370

Glenn Frieler Concrete _Physical Properties Engineer CDOT FORM 1372

Rev. 1/2007

Tested by: Kelvin Jiron Report Date: 9/19/2007

COLORADO DEPARTMENT OF TRANSPORTATION REINFORCING BAR PHYSICAL TEST REPORT

Field Sheet No.: 1234 Sample Number: 1234 9/18/2007 Sample Date:

Project No.:

1 SCM

Project Location: Colorado School of Mines

Region:

Project Code:

Manufacturer: Ameristeel

Charlotte Heat Number:

Bar Grade: 60 S Bar Type: 3 Bar Size:

Bar	Yield Strength (psi)	Tensile Strength (psi)	Elongation (%)	Reduction of Area (%)	Unit Weight (lbs/ft)	Bar Diameter (Inches)
1	59,102	81,342	14.78	46.77	0.366	0.392
2	57,962	80,426	16.19	45.55	0.366	0.393
ASTM A 722 SPECS	Minimum	Minimum	Minimum			
	120,000	150,000	7.0	N/A	N/A	N/A

Remarks: Tested in accordance with ASTM A 370

Glenn Frieler Concrete Physical Properties Engineer

CDOT FORM 1372

Rev. 1/2007

Tested by: Kelvin Jiron Report Date: 9/19/2007

CONCRETE FIELD TESTS REPORT					Project code (SA#) 11925 Project location I-25, SH 7 to WCR 16 Field sheet no. 120227 Date 2/23/03			
em no.	601			Structure	E-12-B			
oncrete cl	lass O			Station placed	Station placed 240+00 Field cured 24 hrs 2 days in molds and then			
ate molde	d 3/27/0	4		Field cured				
3.25			28	days in	Cure Tan	k		
otal air 6.1% Unit weight			or da	ays at structure. Ther				
ylinder Se	et no.							
pecimen o.	Date tested	Age (days)	Diameter/ or cubes	Cross-sectional area	Maximum load (lbs)	Compressive strength (psi)	Sand Equivalent	
1	4/24/04	28	4.01	12.598	64280	5100	83	
2	4/24/04	28	4.01	12.598	63920	5070		
3	4/24/04	28	4.00	12.566	64320	5120		
				A	verage break strength:	5100	psi	