

IA FREQUENCY GUIDE SCHEDULE for Evaluation of OA Sampling & Testing

ITEM	DESCRIPTION	TYPE OF TEST REQUIRED	MINIMUM SAMPLING FREQUENCY	FORM #	REMARKS
203	EMBANKMENT	% Compaction	1 per 100,000 cu. yds. (75,000 m ³), or a fraction thereof greater than 25,000 cu. yds. None required if plan quantity is less than 25,000 cu. yds. (20,000 m ³).	212	Use the same location for % Compaction. Verify curve selection.
206	STRUCTURE BACKFILL (Class I)	Gradation % Compaction	1 per 10,000 cu. yds. (7,500 m ³), or a fraction thereof greater than 1,000 cu. yds. None required if plan quantity is less than 1,000 cu. yds. (750 m ³).	6	Split the gradation sample. Use the same location for % Compaction. Verify curve selection.
206	STRUCTURE BACKFILL (Class II)	% Compaction	1 per 10,000 cu. yds. (7,500 m ³), or a fraction thereof greater than 1,000 cu. yds. None required if plan quantity is less than 1,000 cu. yds. (750 m ³).	212	Use the same location for % Compaction. Verify curve selection.
206	FILTER MATERIAL	Gradation	1 per 2,000 cu. yds. (1,500 m ³), or a fraction thereof greater than 200 cu. yds. None required if plan quantity is less than 1,000 cu. yds. (750 m ³).	6	Split the gradation sample.
304	AGGREGATE BASE COURSE	Gradation % Compaction	1 per 20,000 tons (20,000 t), (10,000 cu. yds.) or a fraction thereof greater than 2,000 tons (2,000 t), (1,000 cu. yds.). None required if plan quantity is less than 10,000 tons (10,000 t), (5,000 cu. yds.).	6	Split the gradation sample. Use the same location for % Compaction. Verify curve selection.
306	RECONDITIONING	% Compaction	1 per 50,000 sq. yds. (40,000 m ²), or a fraction thereof greater than 5,000 sq. yds. (4,000 m ²). None required if plan quantity is less than 25,000 sq. yds. (20,000 m ²).	212	Use the same location for % Compaction. Verify curve selection.

IA FREQUENCY GUIDE SCHEDULE for Evaluation of OA Sampling & Testing

ITEM	DESCRIPTION	TYPE OF TEST REQUIRED	MINIMUM SAMPLING FREQUENCY	FORM #	REMARKS
307	LIME TREATED SUB-GRADE	% Compaction	1 per 50,000 sq. yds. (42,000 m ²), or a fraction thereof greater than 5,000 sq. yds. (4,200 m ²). None required if plan quantity is less than 25,000 sq. yds. (20,000 m ²).	212	Use the same location for % Compaction. Verify curve selection.
308	PORTLAND CEMENT or FLYASH TREATED BASE [Project Special]	Gradation % Compaction	1 per 50,000 tons (50,000 t) or a fraction thereof greater than 5,000 tons (5,000 t). None required if plan quantity is less than 5,000 tons (5,000 t).	6	Split the gradation sample. Use the same location for % Compaction. Verify curve selection.
310	FULL DEPTH RECLAMATION [Project Special]	% Compaction	1 per Project or as determined by the RME.	69	Use the same location for % Compaction. Verify curve selection.
403	HOT MIX ASPHALT (HMA) - VOIDS ACCEPTANCE PROJECT Basis	% Asphalt Maximum Specific Gravity Hveem Stability Air Voids Voids in Mineral Aggregate	1 per 10,000 tons (10,000 t), or a fraction thereof greater than 2,500 tons (2,500 t). None required if plan quantity is less than 2,500 tons (2,500 t).	360 &/or 58	Split the sample.
				69	Use the same location for % Compaction. Take an adjacent core for joint density.
403	HOT MIX ASPHALT (HMA) - VOIDS ACCEPTANCE SYSTEM Basis	% Asphalt Maximum Specific Gravity Hveem Stability Air Voids Voids in Mineral Aggregate	1 per 25,000 tons (25,000 t), or a fraction thereof greater than 2,500 tons (2,500 t), and perform at a minimum one IA every two months on each HMA project tester and their equipment. None required if plan quantity is less than 2,500 tons (2,500 t).	360 &/or 58	Split the sample.
				69	Use the same location for % Compaction. Take an adjacent core for joint density.

IA FREQUENCY GUIDE SCHEDULE for Evaluation of OA Sampling & Testing

ITEM	DESCRIPTION	TYPE OF TEST REQUIRED	MINIMUM SAMPLING FREQUENCY	FORM #	REMARKS
403	HOT MIX ASPHALT (HMA) - GRADATION ACCEPTANCE	% Asphalt Maximum Specific Gravity Gradation	1 per 10,000 tons (10,000 t), or a fraction thereof greater than 2,500 tons (2,500 t). None required if plan quantity is less than 2,500 tons (2,500 t).	360 &/or 58 and 6	Split the sample.
	PROJECT Basis	% Compaction Joint Density		69	Use the same location for % Compaction. Take an adjacent core for joint density.
403	HOT MIX ASPHALT (HMA) - GRADATION ACCEPTANCE	% Asphalt Maximum Specific Gravity Gradation	1 per 25,000 tons (25,000 t), or a fraction thereof greater than 2,500 tons (2,500 t), and perform at a minimum one IA every two months on each HMA project tester and their equipment. None required if plan quantity is less than 2,500 tons (2,500 t).	360 &/or 58 and 6	Split the sample.
	SYSTEM Basis	% Compaction Joint Density		69	Use the same location for % Compaction. Take an adjacent core for joint density.
405	HOT-IN-PLACE RECYCLE	% Compaction Maximum Specific Gravity	1 per 50,000 sq. yds. (40,000 m ²), or a fraction thereof greater than 5,000 sq. yds. (4,000 m ²). None required if plan quantity is less than 25,000 sq. yds. (20,000 m ²).	69	Use the same location for % Compaction. Split the HMA sample.
406	COLD ASPHALT PAVEMENT (RECYCLE)	% Compaction	1 per 50,000 sq. yds. (40,000 m ²), or a fraction thereof greater than 5,000 sq. yds. (4,000 m ²). None required if plan quantity is less than 25,000 sq. yds. (20,000 m ²).	69	Use the same location for % Compaction.

IA FREQUENCY GUIDE SCHEDULE for Evaluation of OA Sampling & Testing

ITEM	DESCRIPTION	TYPE OF TEST REQUIRED	MINIMUM SAMPLING FREQUENCY	FORM #	REMARKS
409	CHIP SEAL COAT MATERIAL - AGGREGATE	Gradation	1 per 5,000 tons (5,000 t), or a fraction thereof greater than 500 tons (500 t). None required if plan quantity is less than 1,200 tons (1,200 t). 1 per 285,000 sq. yds. (230,000 m ²). None required if plan quantity is less than 62,500 sq. yds. (50,000 m ²).	6	Split the gradation sample.
403-411	ASPHALT MATERIALS	Determined by Central Laboratory	<p>Asphalt Cement / Performance Graded Binder & Emulsion for Chip Seal Coat and Cold-In-Place Recycling: Project acceptance sampling will be witnessed by the Region IA Tester, and documented on CDOT Form #411.</p> <p>Project Basis: 1 per 20,000 tons (20,000 t), or a fraction thereof greater than 2,500 tons (2,500 t) per binder type. None required if plan quantity is less than 2,500 tons (2,500 t).</p> <p>System Basis: A minimum of one per two months per tester or one per binder grade. None required if plan quantity is less than 2,500 tons (2,500 t).</p>	67 &/or 411	

IA FREQUENCY GUIDE SCHEDULE for Evaluation of OA Sampling & Testing

ITEM	DESCRIPTION	TYPE OF TEST REQUIRED	MINIMUM SAMPLING FREQUENCY	FORM #	REMARKS
412	PORTLAND CEMENT CONCRETE PAVEMENT (PCCP) (Compressive Strength Alternative)	Air Content Slump Compressive Strength Sand Equivalent	1 set of cylinders per 50,000 sq. yds. (40,000 m ²), or a fraction thereof greater than 5,000 sq. yds. (4,000 m ²) for all thicknesses. None required if total plan quantity for all thicknesses is less than 5,000 sq. yds. (4,000 m ²).	82 &/or 192	May use the same sampling container or a split sample. Split the sand equivalent sample.
	(Flexural Strength Alternative)	Flexural Strength	1 set of beams per 50,000 sq. yds. (40,000 m ²), or a fraction thereof greater than 5,000 sq. yds. (4,000 m ²) for all thicknesses. None required if total plan quantity for all thicknesses is less than 5,000 sq. yds. (4,000 m ²).	157, 82 &/or 192	May use the same sampling container or a split sample.
503	DRILLED CAISSONS	Air Content Slump Compressive Strength Unit Weight Temperature	1 set of cylinders per 2,000 cu. yds. (1,500 m ³), or a fraction thereof greater than 200 cu. yds. (150 m ³). None required if plan quantity is less than 500 cu. yds. (380 m ³). When specified.	82 &/or 192	May use the same sampling container or a split sample.
601	STRUCTURAL CONCRETE	Air Content Slump Compressive Strength	1 per 2,000 cu. yds. (1,500 m ³), or fraction thereof greater than 500 cu. yds. for each Class. No tests required if the quantity is less than 500 cu. yds. for each class. <u>Exception</u> : 1 test minimum if the total quantity of all classes is greater than 500 cu. yds. (380 m ³).	82 &/or 192	May use the same sampling container or a split sample.

IA FREQUENCY GUIDE SCHEDULE for Evaluation of OA Sampling & Testing

ITEM	DESCRIPTION	TYPE OF TEST REQUIRED	MINIMUM SAMPLING FREQUENCY	REMARKS
606	GUARDRAIL (Cast In-Place)	Compressive Strength Air Content Slump	1 per 10,000 linear feet (3,000 m) or a fraction thereof greater than 1,000 linear feet (300 m). None required if plan quantity for all classes is less than 3,000 linear feet (900 m).	May use the same sampling container or a split sample.
608	SIDEWALKS & BIKEWAYS (PCCP)	Air Content Slump Compressive Strength	1 per 10,000 sq. yds. (8,000 m ²), or a fraction thereof greater than 1,000 sq. yds. (800 m ²). None required if total plan quantity for all classes and for all thicknesses is less than 3,000 sq. yds. (2,500 m ²)	May use the same sampling container or a split sample.
	(HMA)	AC Content Gradation	1 per project. None required if total plan quantity is less than 2,500 tons (2,500 t).	Split the HMA sample.
609	CURB AND GUTTER (PCCP)	Air Content Slump Compressive Strength	1 per project. None required if plan quantity is less than 10,000 linear ft. (3,000 m).	May use the same sampling container or a split sample.
	(HMA)	AC Content Gradation	1 per project. None required if total plan quantity is less than 2,500 linear ft. (40 t).	Split the HMA sample.
618	PRESTRESSED CONCRETE (STRUCTURES) (Cast In-Place)	Air Content Slump Compressive Strength	1 per 2,000 cu. yds. (1,500 m ³), or a fraction thereof greater than 200 cu. yds. (150 m ³). None required if plan quantity is less than 500 cu. yds. (380 m ³).	May use the same sampling container or a split sample.

IA FREQUENCY GUIDE SCHEDULE for Evaluation of OA Sampling & Testing

- NOTE 1** - When all Items subject to Independent Assurance Sampling on a particular project have quantities less than the minimums set forth in the OA Frequency Guide Schedule for Minimum Materials Sampling, Testing, and Inspection, no IA Samples are required. However, on such projects the Region Materials Engineer will fill in the heading on a CDOT Form #379 and write across the face of this form a statement to the effect that “*No Independent Assurance samples were taken because of the small quantities involved.*” This will fulfill Independent Assurance requirements on this project.
- NOTE 2** - Independent Assurance testing should be accomplished by the same method used for Owner Acceptance (OA) at the Point of Verification or Acceptance listed for each Item in the OA Frequency Guide Schedule for Minimum Materials Sampling, Testing, and Inspection in the Field Materials Manual. Sampling shall be accomplished using CDOT approved sampling methods outlined in the FMM. All samples shall be split with the field tester (OA) and run independently by personnel who have no direct responsibility for Quality Assurance or Verification sampling and testing for the project.
- NOTE 3** - For Item 403 – 411: Local Agency (LA) projects on Colorado State Highways as well as the National Highway System (NHS) shall have the IA's performed by CDOT. The binder and emulsion samples shall be sent to the Central Lab.
- NOTE 4** - Refer to the CDOT Independent Assurance Manual for specific item testing information and techniques.

IA FREQUENCY GUIDE SCHEDULE for Evaluation of OA Sampling & Testing

TABLE IA – 1, Comparison Precision Guide

Element	Type of Test	Minor Difference	Significant Difference
Gradation	Sieve Analysis per CP 31		
	Nominal Maximum	≤ 1%	> 1%
	1-1/2" to # 8	≤ 5%	> 5%
	#16 to #50	≤ 4%	> 4%
	#100	≤ 3%	> 3%
Sieve Analysis per CP 31	#200	≤ 3%	> 3%
	NOTE: # 200 (Item 409 per CP 31)	≤ 0.5%	> 0.5%
Asphalt Content	Asphalt Content Gauge per CP 85 Ignition Method per CP-L 5120	≤ 0.20%	> 0.20%
		≤ 0.35%	> 0.35%
Maximum Specific Gravity	Flask per CP 51	≤ 0.019	> 0.019
Asphalt Compaction	M/D Gauge per CP 81 Cores per CP 44	≤ 2.0%	> 2.0%
		≤ 2.0%	> 2.0%
Asphalt Compaction at Longitudinal Joints	M/D Gauge per CP 81 Cores per CP 44	≤ 2.0%	> 2.0%
		≤ 2.0%	> 2.0%
Air Voids	Per CP-L 5115	≤ 1.2%	> 1.2%
Voids in Mineral Aggregate	Per CP 48	≤ 1.2%	> 1.2%
Hveem Stability	Per CP-L 5106	≤ 7	> 7

IA FREQUENCY GUIDE SCHEDULE for Evaluation of OA Sampling & Testing

TABLE IA – 1, Comparison Precision Guide (continued)

Element	Type of Test	Minor Difference	Significant Difference
Sand Equivalent	Sand Equivalent per CP 37	≤ 5 points	> 5 points
Slump	Cone per AASHTO T 119	≤ 1/2"	> 1/2"
Air Content	Air Meter per AASHTO T 152	≤ 0.5%	> 0.5%
Compressive Strength	Compressive Strength per ASTM C 39	Average QA within ±10% of average IA	Average QA test result >10% of average IA test result
Flexural Strength	Flexural Strength per AASHTO T 97	Average QA within ±10% of average IA	Average QA test result >10% of average IA test result
Soil Compaction	M/D Gauge per CP 80	≤ 2.0%	> 2.0%
Aggregate Base Compaction	M/D Gauge per CP 80	≤ 2.0%	> 2.0%

NOTE: Data based on Empirical Bayesian Statistics and is subject to change as the database increases. Table 1 was revised for the 2007 FMM based on data from the 2003, 2004, and 2005 construction season.

IA FREQUENCY GUIDE SCHEDULE for Evaluation of OA Sampling & Testing

{This page was intentionally left blank.}