

2019

COST DATA

January – June



Compiled By
Engineering Estimates and Market Analysis Unit
of the
Contracts and Market Analysis Branch

August 7, 2019

COLORADO COST DATA

FOREWORD

The Colorado Department of Transportation's Engineering Estimates and Market Analysis (EEMA) Unit, of the Contracts and Market Analysis Branch, publishes the Cost Data Book annually. A joint effort has been made between the Department's sections and the EEMA Unit to gather and record cost data for this publication.

The following data includes weighted average prices for items on highway construction projects that were bid during the 2019 calendar year. Caution should be used in applying these historical averages to specific projects. Allowances for varying geographic, climatic, social, economic conditions and type of project should be made.

Changes and improvements are continually being made to update and increase the usefulness for future issues. Comments and suggestions for improvements for users of this publication are welcome.

2019 COST DATA
CONSTRUCTION
TABLE OF CONTENTS

	<u># OF PAGES</u>
LIST OF 2019 BID PROJECTS	5
BRIDGE COST PER SQUARE FEET	1
ITEM UNIT COSTS BY PROJECTS	357

Colorado Department of Transportation
 2019 Cost Data
 PROJECTS BID FROM 01/01/19 THROUGH 06/30/19

13:38 Wednesday, August 7, 2019 1

BID LETTING	CONTRACTOR/ PROJECT NUMBER	LOCATION	DIST	TERRAIN	BIDS	AWARDED BID	INDEX
20190103	ZAK DIRT, INC. ERI119A-065	PR SH 119A BOULDER CANYON	4	M	8	\$30,306,322.04	97.57
20190103	ZAK DIRT, INC. STA119A-069	SH 119: NEDERLAND - EAST	4	M	8	\$30,306,322.04	97.57
20190103	Bixby Electric, Inc. NHPPR500-173	US 160_550 DURANGO SIGNALS OPS	5	M	2	\$1,203,248.00	91.75
20190103	MARTIN MARIETTA MATERIALS IM0251-351	I-25 South of Pueblo MP 79.6 t	2	P	4	\$7,699,264.78	102.66
20190103	STRUCTURES, INC. STAR200-242	R2 NORTH PROGRAM WALL REPAIRS	2	U	2	\$2,656,524.00	106.26
20190103	JALISCO INTERNATIONAL, INC. SHER100-289	INTERSECTIONS @ SH83 & LONGS W	1	R	5	\$1,254,593.50	80.21
20190103	AB Underground FSA0142-068	SH 14 & WCR 33 INTERSECTION IM	4	P	4	\$166,650.95	83.79
20190110	STRUCTURES, INC. FBR0341-087	US 34 OVER NORTH FORK CO RIVER	3	R	6	\$3,822,565.87	87.86
20190110	Kilgore Companies, LLC dba Elam Construc STR0132-021	SH 13-MOFFAT COUNTY-CR 3 SOUTH	3	R	5	\$10,888,031.90	94.88
20190110	RDP BARRICADE CO., LLC MTCER300-247	MTCE R3 FY19 REGION ROUNDABOUT	3	M	5	\$292,337.50	71.06
20190117	OLDCASTLE SW GROUP, INC. STR141A-047	SH 141 MP 120-143 MESA COUNTY	3	M	4	\$6,640,287.15	81.95
20190117	LAWSON CONSTRUCTION COMPANY NHPP0701-241	I-70 TRUCK PARKING GARFIELD CO	3	M	5	\$3,285,824.15	120.68
20190117	ROADSAFE TRAFFIC SYSTEMS, INC MTCER400-368	REGION 4 FY 19 STENCIL NW	4	R	4	\$810,557.00	100.45
20190124	AMERICAN CIVIL CONSTRUCTORS, LLC dba A STR0241-062	US 24 143.4 - 148	3	M	3	\$6,766,336.00	124.94
20190124	ABCO CONTRACTING, INC. NHPPR100-250	PACKAGE A (I-25 / I-70 / I-76)	1	U	5	\$2,634,897.00	96.85
20190131	M. A. MORTENSON COMPANY ER072A-040 NHPP072A-041	PR SH72A FLOOD PERMANENT REPAI PR SH72A FLOOD PERMANENT REPAI	1 1	M M	12	\$8,825,893.42	85.80
20190131	ARROW ELECTRIC SERVICE, INC. STAM086-075	SH96A ABRIENDO - ORMAN SAFETY	2	U	3	\$1,652,620.50	110.17

Colorado Department of Transportation
2019 Cost Data
PROJECTS BID FROM 01/01/19 THROUGH 06/30/19

13:38 Wednesday, August 7, 2019 2

BID LETTING	CONTRACTOR/ PROJECT NUMBER	LOCATION	DIST	TERRAIN	BIDS	AWARDED BID	INDEX
20190131	KIEWIT INFRASTRUCTURE CO. STA067A-038	SH 67 SEDALIA RESURFACING	1	R	3	\$1,122,309.00	85.44
20190207	CASTLE ROCK CONST. CO. OF COLO, LLC NH2871-035	US 287 PASSING LANES SOUTH OF	2	P	4	\$3,826,381.89	109.33
20190207	PAONIA, INC ITSSW01-638	ETHERNET PHASE III (PRIMARYLY	2	P	2	\$2,207,222.50	100.33
20190207	GRAND RIVER CONSTRUCTION NHPP0821-107	SH 82 GLENWOOD SPRINGS TO CAR	3	M	2	\$7,296,532.86	93.31
20190207	INNOVATIVE MARKING SYSTEMS, INC. MTCER500-206	R5 FY19 STRIPING	5	M	3	\$1,528,025.00	93.03
20190214	OLDCASTLE SW GROUP, INC. NHPP145A-065	SH 145 PASSING LANES AT DEEP C	5	M	5	\$5,394,676.05	94.32
20190214	APC CONSTRUCTION CO., LLC NHPP0741-022	SH 74: I-70 TO CR 65 RESURFACI	1	M	4	\$2,948,790.02	79.83
20190220	GEOSTABILIZATION INTERNATIONAL, LLC NHPP0702-379	I-70 VAIL PASS VARIOUS WALL RE	3	M	1	\$2,116,515.00	100.00
20190221	OLDCASTLE SW GROUP, INC. NHPP1601-076	US 160 MANCOS HILL (MP 40.000)	5	R	3	\$2,620,142.20	85.71
20190221	SEMA CONSTRUCTION, INC. NHPP070A-028	FALL RIVER ROAD BRIDGE	1	M	5	\$2,544,166.60	93.23
20190221	W.L. CONTRACTORS, INC. SHER100-284	FY19 NORTH SIGNAL PKG	1	U	3	\$1,223,678.00	96.66
20190307	OLDCASTLE SW GROUP, INC. NHPP1601-073	US 160 PASSING LANE NORTH OF T	5	R	2	\$9,086,930.60	102.08
20190307	APC SOUTHERN CONSTRUCTION COMPANY, LLC NHPP006A-058	US 6 LOVELAND PASS - I-70 (FY1	1	M	2	\$4,627,901.98	102.08
20190307	ZAK DIRT, INC. FBR0253-247	I25 AT VINE DRIVE BRIDGE REPLA	4	R	11	\$4,931,805.85	90.31
20190307	K.E.C.I. COLORADO, INC. SHE2254-090	Colfax & I-225, Colfax & Chamb	1	U	2	\$2,455,668.00	105.84
20190307	ROADSAFE TRAFFIC SYSTEMS, INC MPR200-253	R2 FY19 STENCIL PVMT MKG PROJE	2	R	3	\$459,964.65	76.66
20190307	NORAA CONCRETE CONSTRUCTION CORPORATION C R100-315	R1 ADA CURB RAMPS - PH 5	1	U	2	\$1,179,971.00	115.88

Colorado Department of Transportation
2019 Cost Data
PROJECTS BID FROM 01/01/19 THROUGH 06/30/19

13:38 Wednesday, August 7, 2019 3

BID LETTING	CONTRACTOR/ PROJECT NUMBER	LOCATION	DIST	TERRAIN	BIDS	AWARDED BID	INDEX
20190314	APC SOUTHERN CONSTRUCTION COMPANY, LLC NHPP0702-378	I-70 OFFICERS GULCH TO FRISCO	3	M	3	\$5,631,566.28	104.90
20190314	Kilgore Companies, LLC dba Elam NHPP050A-033	Construc US50 West of Delta EB Lanes Re	3	R	3	\$5,568,270.57	96.99
20190321	A and S CONSTRUCTION CO. NHPP0503-087	US 50 PASSING LANES EAST OF SA	5	M	2	\$4,173,000.00	117.72
20190321	BRANNAN SAND AND GRAVEL, LLC NHPP2254-089	I-225 RESURFACING FROM I-25 TO	1	R	3	\$9,692,868.95	109.57
20190321	W.L. CONTRACTORS, INC. SHER100-308	MIDPOINT - SIGNAL CONST PACKAG	1	U	2	\$2,699,567.00	118.63
20190321	STURGEON ELECTRIC COMPANY, INC SHE 0252-481	I-25 RAMP METER INSTALLATION	1	U	3	\$3,866,299.75	111.55
20190328	HAMILTON CONSTRUCTION CO. STM0242-077	US24 - 8TH ST TO WEST OF MANIT	2	M	3	\$9,699,261.40	96.99
20190328	SCOTT CONTRACTING INC. STA0131-070 HMA ALT STA0131-070 PCCP ALT	SH 13 CR 5 NORTH AND SOUTH SH 13 CR 5 NORTH AND SOUTH	3 3	M M	6	\$16,872,998.84	87.18
20190404	HAMON INFRASTRUCTURE, INC. NHPP030A-035	US 285/SH30	1	U	1	\$7,599,000.00	103.13
20190404	OLDCASTLE SW GROUP, INC. STRR300-236	SH 92 and SH 133	3	R	1	\$2,765,365.50	101.86
20190404	KIRKLAND CONSTRUCTION, LLLP IM0252-472	I-25 CABLE BARRIER PHASE III	2	R	2	\$2,606,409.00	130.32
20190404	KOLBE STRIPING INC. MT CER300-252	MTCE R3 FY19/20 REGION WIDE EP	3	M	3	\$2,483,355.70	101.25
20190418	Lobato Construction, LLC BR071A-020	REPLACEMENT OF STRUCTURE L-22-	2	R	3	\$1,176,279.10	106.93
20190418	INTERFACE COMMUNICATIONS COMPANY FSA0252-468	I-25 AND PLUM CREEK IMPROVEMEN	1	R	4	\$1,250,558.84	110.57
20190418	INNOVATIVE MARKING SYSTEMS, INC. MTCE0702-387	MTCE R3 FY19 I-70 TAPE	3	M	3	\$528,630.00	105.74
20190418	ROADSAFE TRAFFIC SYSTEMS, INC MT CER300-253	MTCE R3 FY19/20 REGION WIDE ST	3	M	2	\$446,398.85	98.25
20190425	GRAHAM CONTRACTING LTD NHPP0703-445	I-70 WESTBOUND PEAK PERIOD SHO	1	M	3	\$61,648,291.79	112.79

Colorado Department of Transportation
2019 Cost Data
PROJECTS BID FROM 01/01/19 THROUGH 06/30/19

13:38 Wednesday, August 7, 2019 4

BID LETTING	CONTRACTOR/ PROJECT NUMBER	LOCATION	DIST	TERRAIN	BIDS	AWARDED BID	INDEX
20190502	INTERMOUNTAIN SLURRY SEAL, INC. NHPP2851-012	US 285 Antonito to Estrella Ch	5	P	3	\$2,087,647.10	115.09
20190502	STURGEON ELECTRIC COMPANY, INC FSA2873-190	US 287 AND FOOTHILLS PARKWAY	4	U	2	\$525,469.00	119.44
20190502	SURFACE PREPARATION TECHNOLOGIES FSA0061-090	SH 6: CENTER LINE RUMBLE STRIP	4	P	1	\$297,699.70	115.39
20190502	KSK, LLC MTCE0641-103	MTCE R3 FY20 SH 64 RANGELY PED	3	M	2	\$490,000.00	98.11
20190502	CAN DO CONCRETE CONSTRUCTION, INC C2571-013	SH257 & 392:WINDSOR CURB RAMPS	4	U	3	\$572,176.50	93.32
20190509	ROADSAFE TRAFFIC SYSTEMS, INC FSAR100-327	REGION 1 6 INCH LANE LINE MARK	1	R	1	\$7,896,410.44	102.41
20190516	MAIN ELECTRIC LTD IMO252-456	I-25 COLORADO SPRINGS RAMP MET	2	U	3	\$2,357,641.59	107.17
20190516	KSK, LLC SHE0701-243	I-70 EXIT 26 DDI MODIFICATIONS	3	U	4	\$864,000.00	101.47
20190516	HAMON INFRASTRUCTURE, INC. FSA0703-454	EB I-70 AUX LANE WARD TO KIPLI	1	U	3	\$2,128,000.00	98.25
20190516	KSK, LLC CR300-248	CRAIG RESIDENCY ADA RAMPS	3	U	3	\$1,030,000.00	84.24
20190523	AVERY ASPHALT STMC430-020	ADA RAMPS DIVIDE ESB	2	M	1	\$359,777.96	109.02
20190530	OLDCASTLE SW GROUP, INC. FBR0063-057	US-6 F-09-K BRIDGE OVER CASTLE	3	M	2	\$3,273,447.70	90.64
20190530	MORTON ELECTRIC, INC. STRR200-257	ROAD CLOSURE GATES ON VARIOUS	2	R	2	\$343,793.45	71.62
20190606	HARVEY CONTRACTORS INC MPR200-255	FY20 R2 PAVEMENT MARKING PROJE	2	R	3	\$3,505,808.20	100.17
20190607	WILLIAMS CONSTRUCTION CONTRACTORS ERI45A-081	SH 145 MP 21 EMERGENCY ROCKFAL	5	M	2	\$589,326.00	117.29
20190610	RLW/SEMA, A Joint Venture 0253-277	I-25 EXPRESS LANES SEGMENT 5 &	4	U	1	\$2,282,301.00	101.27
20190613	Lobato Construction, LLC NHPP0703-442	I-70 SILVERPLUME SOUNDWALL AND	1	M	8	\$3,086,000.00	103.33

Colorado Department of Transportation
 2019 Cost Data
 PROJECTS BID FROM 01/01/19 THROUGH 06/30/19

13:38 Wednesday, August 7, 2019 5

BID LETTING	CONTRACTOR/ PROJECT NUMBER	LOCATION	DIST	TERRAIN	BIDS	AWARDED BID	INDEX
20190613	SURFACE PREPARATION TECHNOLOGIES FSA0142-067	SH 14 RUMBLESTRIPS: AULT TO SH	4	R	1	\$260,707.75	103.25
20190613	KIEWIT INFRASTRUCTURE CO. NHPP030A-036	SH 30 & TOWER RD IMPROVEMENTS	1	U	1	\$681,630.50	112.49
20190613	GONZALES CONSTRUCTION COMPANY, INC. CR500-205	R5 GUARDRAIL END TREATMENT EAS	5	R	1	\$528,219.95	105.85
20190620	AMERICAN CIVIL CONSTRUCTORS, LLC dba A STR 141A-040	R5 YEAR 4 BRDG PREV MAINT RAMP	5	R	2	\$2,647,688.00	135.00
20190620	AMERICAN WEST CONSTRUCTION, LLC NHPP160A-030	US160 MM 43.2, 150.4, 156.3, 1	5	M	2	\$985,023.00	87.01
20190627	MIDWEST ROCKFALL, INC. C0502-085	US 50 MM 201.8 MONARCH AVALANC	5	M	2	\$366,397.75	96.52
					=====	=====	=====
TOTALS					234	\$320,343,922.12	101.03

Colorado Department of Transportation
 2019 Cost Data
 BRIDGE COST PER SQUARE FOOT
 (01/01/19 THROUGH 06/30/19)

13:38 Wednesday, August 7, 2019 1

DATE LET	PROJECT NUMBER/ PROJECT LOCATION	TERR/ BRIDGE ID	LENGTH	WIDTH	TOTAL SQUARE FT	TOTAL COST	COST PER SQUARE FOOT
BRIDGE REPAIR							
190314	NHPP0702-378 I-70 OFFICERS GULCH TO FRISCO	M 0300	131.0000	108.0000	14148.0	\$35,564	\$2.51
		0301	144.0000	42.0000	6048.0	\$167,255	\$27.65
		0302	144.0000	42.0000	6048.0	\$176,494	\$29.18
		0303	297.6000	40.0000	11904.0	\$42,107	\$3.54
190620	STR 141A-040 R5 YEAR 4 BRDG PREV MAINT RAMP	R O-05-H	92.0000	34.0000	3128.0	\$119,080	\$38.07
		P-05-S	502.0000	86.0000	43172.0	\$320,740	\$7.43
		P-05-AI	151.0000	55.0000	8305.0	\$387,689	\$46.68
		P-05-AH	57.0000	51.0000	2907.0	\$185,538	\$63.82
		P-07-D	364.0000	32.0000	11648.0	\$196,370	\$16.86
		O-08-A	189.0000	38.0000	7182.0	\$216,540	\$30.15
			WEIGHTED AVERAGE COST:				
			NEW STRUCTURES		114490.0	\$1,847,377	\$16.14
PRESTRES GIRDER (BOX SECTION)							
190221	NHPP070A-028 FALL RIVER ROAD BRIDGE	M CLR312-1.10	64.0000	41.0000	2624.0	\$1,064,241	\$405.58
			WEIGHTED AVERAGE COST:				
			NEW STRUCTURES		2624.0	\$1,064,241	\$405.58
PRESTRES GIRDER (I-SECTION G-54)							
190110	FBR0341-087 US 34 OVER NORTH FORK CO RIVER	R D-13-Y	117.0000	44.0000	5148.0	\$1,942,312	\$377.29
			WEIGHTED AVERAGE COST:				
			NEW STRUCTURES		5148.0	\$1,942,312	\$377.29

PROJECT NUMBER	ITEM NUMBER/ PROJECT LOCATION	ITEM DESCRIPTION/ PROJECT LOCATION	DATE LET	UNIT/ QUANTITY	ENGR. EST.	AVERAGE BID	AWARDED BID
===== 201-00000		Clear and Grub		LUMP SUM	=====		
STAR200-242		R2 NORTH PROGRAM WALL REPAIRS	01/03/19	1.00	15000.00	5857.16	5762.00
FSA0142-068		SH 14 & WCR 33 INTERSECTION I	01/03/19	1.00	8000.00	4819.50	4500.00
ER119A-065		PR SH 119A BOULDER CANYON	01/03/19	1.00	100000.00	92080.72	148000.00
STAL19A-069		SH 119: NEDERLAND - EAST					
STR0132-021		SH 13-MOFFAT COUNTY-CR 3 SOUT	01/10/19	1.00	50000.00	73226.40	33500.00
FBR0341-087		US 34 OVER NORTH FORK CO RIVE	01/10/19	1.00	20000.00	26179.33	28600.00
STR141A-047		SH 141 MP 120-143 MESA COUNTY	01/17/19	1.00	15000.00	28990.34	25000.00
NHPP0701-241		I-70 TRUCK PARKING GARFIELD C	01/17/19	1.00	8000.00	16832.62	35000.00
STR0241-062		US 24 143.4 - 148	01/24/19	1.00	30000.00	67608.33	50000.00
ER072A-040		PR SH72A FLOOD PERMANENT REPA	01/31/19	1.00	7000.00	86134.60	20000.00
NHPP072A-041		PR SH72A FLOOD PERMANENT REPA					
STAM086-075		SH96A ABRIENDO - ORMAN SAFETY	01/31/19	1.00	10000.00	9833.33	1000.00
NHPP145A-065		SH 145 PASSING LANES AT DEEP	02/14/19	1.00	85000.00	138485.28	148000.00
NHPP070A-028		FALL RIVER ROAD BRIDGE	02/21/19	1.00	5000.00	34113.06	72500.00
NHPP1601-073		US 160 PASSING LANE NORTH OF	03/07/19	1.00	15000.00	24415.00	27330.00
FBR0253-247		I25 AT VINE DRIVE BRIDGE REPL	03/07/19	1.00	25000.00	23521.13	18500.00
SHE2254-090		Colfax & I-225, Colfax & Cham	03/07/19	1.00	2000.00	73250.00	16500.00
NHPP0503-087		US 50 PASSING LANES EAST OF S	03/21/19	1.00	30000.00	82000.00	54000.00
SHE 0252-481		I-25 RAMP METER INSTALLATION	03/21/19	1.00	5000.00	8133.33	13150.00
STA0131-070 HMA ALT		SH 13 CR 5 NORTH AND SOUTH	03/28/19	1.00	45000.00	133795.00	14150.00
STA0131-070 PCCP ALT		SH 13 CR 5 NORTH AND SOUTH					
		WEIGHTED AVERAGE FOR THE FIRST QUARTER		18.00	27368.42	57558.35	39749.56
IM0252-472		I-25 CABLE BARRIER PHASE III	04/04/19	1.00	20000.00	55000.00	60000.00
BR071A-020		REPLACEMENT OF STRUCTURE L-22	04/18/19	1.00	4250.00	30166.67	30000.00
FSA0252-468		I-25 AND PLUM CREEK IMPROVEME	04/18/19	1.00	1500.00	7231.50	1770.00
NHPP0703-445		I-70 WESTBOUND PEAK PERIOD SH	04/25/19	1.00	78000.00	267898.33	77695.00
MTCE0641-103		MTCE R3 FY20 SH 64 RANGELY PE	05/02/19	1.00	2000.00	14552.50	9000.00
FSA2873-190		US 287 AND FOOTHILLS PARKWAY	05/02/19	1.00	5000.00	4385.00	7000.00
FSA0703-454		EB I-70 AUX LANE WARD TO KIPL	05/16/19	1.00	13425.57	53333.33	45000.00
FBR0063-057		US-6 F-09-K BRIDGE OVER CASTL	05/30/19	1.00	35000.00	35050.00	10100.00
STRR200-257		ROAD CLOSURE GATES ON VARIOUS	05/30/19	1.00	10000.00	2576.00	1000.00
ER145A-081		SH 145 MP 21 EMERGENCY ROCKFA	06/07/19	1.00	15000.00	11944.72	14437.00
NHPP0703-442		I-70 SILVERPLUME SOUNDWALL AN	06/13/19	1.00	3000.00	46212.13	49900.00
NHPP160A-030		US160 MM 43.2, 150.4, 156.3,	06/20/19	1.00	40000.00	84375.00	125000.00
C0502-085		US 50 MM 201.8 MONARCH AVALAN	06/27/19	1.00	15000.00	20731.00	5000.00
		WEIGHTED AVERAGE FOR THE SECOND QUARTER		13.00	18628.89	51622.88	33530.92
		WEIGHTED AVERAGE FOR THE YEAR		31.00	23817.99	55801.45	37141.74
===== 201-00001		Clear and Grub		Acre	=====		
ER119A-065		PR SH 119A BOULDER CANYON	01/03/19	6.74	3250.00	7877.43	6500.00

COLORADO DEPARTMENT OF TRANSPORTATION
ITEM UNIT COSTS BY PROJECTS -- 2019 COST DATA

13:44 Wednesday, August 7, 2019 2

PROJECT NUMBER	ITEM NUMBER/ PROJECT LOCATION	ITEM DESCRIPTION/ PROJECT LOCATION	DATE LET	UNIT/ QUANTITY	ENGR. EST.	AVERAGE BID	AWARDED BID
=====	201-00001	Clear and Grub		Acre	=====		
STA119A-069		SH 119: NEDERLAND - EAST					
NH2871-035		US 287 PASSING LANES SOUTH OF	02/07/19	10.00	10000.00	5389.42	8500.01
STM0242-077		US24 - 8TH ST TO WEST OF MANI	03/28/19	0.80	19800.00	29666.67	14000.00
	WEIGHTED AVERAGE FOR THE FIRST QUARTER			17.54	7853.19	7387.12	7982.33
	WEIGHTED AVERAGE FOR THE YEAR			17.54	7853.19	7387.12	7982.33
=====	201-00005	Rem of Debris		LUMP SUM	=====		
ER119A-065		PR SH 119A BOULDER CANYON	01/03/19	1.00	5000.00	23963.70	2500.00
STA119A-069		SH 119: NEDERLAND - EAST					
STR0241-062		US 24 143.4 - 148	01/24/19	1.00	5000.00	8788.33	10000.00
	WEIGHTED AVERAGE FOR THE FIRST QUARTER			2.00	5000.00	19824.96	6250.00
	WEIGHTED AVERAGE FOR THE YEAR			2.00	5000.00	19824.96	6250.00
=====	202-00000	Rem Str and Obstructions		LUMP SUM	=====		
STR0241-062		US 24 143.4 - 148	01/24/19	1.00	20000.00	34000.00	15000.00
NHPP006A-058		US 6 LOVELAND PASS - I-70 (FY	03/07/19	1.00	2000.00	12085.76	15171.51
	WEIGHTED AVERAGE FOR THE FIRST QUARTER			2.00	11000.00	25234.30	15085.76
MTCE0641-103		MTCE R3 FY20 SH 64 RANGELY PE	05/02/19	1.00	2000.00	1265.00	2100.00
	WEIGHTED AVERAGE FOR THE SECOND QUARTER			1.00	2000.00	1265.00	2100.00
	WEIGHTED AVERAGE FOR THE YEAR			3.00	8000.00	18385.93	10757.17
=====	202-00001	Rem Structure		Each	=====		
STA0131-070 HMA ALT		SH 13 CR 5 NORTH AND SOUTH	03/28/19	2.00	2000.00	6060.71	5020.00
STA0131-070 PCCP ALT		SH 13 CR 5 NORTH AND SOUTH					
	WEIGHTED AVERAGE FOR THE FIRST QUARTER			2.00	2000.00	6060.71	5020.00
NHPP0703-445		I-70 WESTBOUND PEAK PERIOD SH	04/25/19	1.00	3000.00	1900.45	733.00
	WEIGHTED AVERAGE FOR THE SECOND QUARTER			1.00	3000.00	1900.45	733.00
	WEIGHTED AVERAGE FOR THE YEAR			3.00	2333.33	4673.96	2876.50

PROJECT NUMBER	ITEM NUMBER/ PROJECT LOCATION	ITEM DESCRIPTION/ PROJECT LOCATION	DATE LET	UNIT/ QUANTITY	ENGR. EST.	AVERAGE BID	AWARDED BID
=====	202-00008	Tree Trimming		Hour	=====	=====	=====
NHPP0703-442		I-70 SILVERPLUME SOUNDWALL AN	06/13/19	10.00	350.00	226.52	170.00
		WEIGHTED AVERAGE FOR THE SECOND QUARTER		10.00	350.00	226.52	170.00
		WEIGHTED AVERAGE FOR THE YEAR		10.00	350.00	226.52	170.00
=====	202-00010	Rem Tree		Each	=====	=====	=====
ER119A-065		PR SH 119A BOULDER CANYON	01/03/19	428.00	300.00	410.26	300.00
STA119A-069		SH 119: NEDERLAND - EAST					
FBR0341-087		US 34 OVER NORTH FORK CO RIVE	01/10/19	38.00	500.00	419.65	404.34
STR0241-062		US 24 143.4 - 148	01/24/19	15.00	500.00	636.67	300.00
ER072A-040		PR SH72A FLOOD PERMANENT REPA	01/31/19	92.00	350.00	501.04	230.00
NHPP072A-041		PR SH72A FLOOD PERMANENT REPA					
NHPP070A-028		FALL RIVER ROAD BRIDGE	02/21/19	11.00	325.00	431.42	510.00
NHPP1601-073		US 160 PASSING LANE NORTH OF	03/07/19	8.00	500.00	753.50	507.00
STM0242-077		US24 - 8TH ST TO WEST OF MANI	03/28/19	29.00	262.00	281.67	175.00
		WEIGHTED AVERAGE FOR THE FIRST QUARTER		621.00	325.72	432.04	296.56
NHPP0703-445		I-70 WESTBOUND PEAK PERIOD SH	04/25/19	32.00	330.00	515.49	291.00
MTCE0641-103		MTCE R3 FY20 SH 64 RANGELY PE	05/02/19	8.00	400.00	380.00	400.00
CR300-248		CRAIG RESIDENCY ADA RAMPS	05/16/19	2.00	300.00	1303.33	500.00
NHPP160A-030		US160 MM 43.2, 150.4, 156.3,	06/20/19	4.00	2000.00	635.00	770.00
C0502-085		US 50 MM 201.8 MONARCH AVALAN	06/27/19	30.00	300.00	577.50	185.00
		WEIGHTED AVERAGE FOR THE SECOND QUARTER		76.00	412.63	554.39	291.34
		WEIGHTED AVERAGE FOR THE YEAR		697.00	335.20	436.46	295.99
=====	202-00015	Rem Headwall		Each	=====	=====	=====
ER119A-065		PR SH 119A BOULDER CANYON	01/03/19	8.00	800.00	1341.19	650.00
STA119A-069		SH 119: NEDERLAND - EAST					
STR0132-021		SH 13-MOFFAT COUNTY-CR 3 SOUT	01/10/19	18.00	1000.00	640.00	355.00
STR0241-062		US 24 143.4 - 148	01/24/19	2.00	300.00	1466.67	1000.00
ER072A-040		PR SH72A FLOOD PERMANENT REPA	01/31/19	1.00	2500.00	2783.33	1700.00
NHPP072A-041		PR SH72A FLOOD PERMANENT REPA					
NHPP145A-065		SH 145 PASSING LANES AT DEEP	02/14/19	1.00	2000.00	2124.23	675.00

COLORADO DEPARTMENT OF TRANSPORTATION
ITEM UNIT COSTS BY PROJECTS -- 2019 COST DATA

13:44 Wednesday, August 7, 2019 4

PROJECT NUMBER	ITEM NUMBER/ PROJECT LOCATION	ITEM DESCRIPTION/ PROJECT LOCATION	DATE LET	UNIT/ QUANTITY	ENGR. EST.	AVERAGE BID	AWARDED BID
===== 202-00015		Rem Headwall		Each =====			
NHPP0503-087		US 50 PASSING LANES EAST OF S	03/21/19	4.00	500.00	2150.00	300.00
	WEIGHTED AVERAGE FOR THE FIRST QUARTER			34.00	926.47	1153.82	504.85
	WEIGHTED AVERAGE FOR THE YEAR			34.00	926.47	1153.82	504.85
===== 202-00019		Rem Inlet		Each =====			
SHER100-289		INTERSECTIONS @ SH83 & LONGS	01/03/19	1.00	1500.00	1206.20	1650.00
ER119A-065		PR SH 119A BOULDER CANYON	01/03/19	6.00	600.00	1433.07	600.00
STA119A-069		SH 119: NEDERLAND - EAST					
NHPP0701-241		I-70 TRUCK PARKING GARFIELD C	01/17/19	2.00	760.00	1477.07	575.00
STR0241-062		US 24 143.4 - 148	01/24/19	10.00	1200.00	1838.33	500.00
ER072A-040		PR SH72A FLOOD PERMANENT REPA	01/31/19	4.00	1500.00	1520.46	1700.00
NHPP072A-041		PR SH72A FLOOD PERMANENT REPA					
STAM086-075		SH96A ABRIENDO - ORMAN SAFETY	01/31/19	3.00	1000.00	5159.00	2932.00
SHE2254-090		Colfax & I-225, Colfax & Cham	03/07/19	1.00	1500.00	3300.00	2600.00
NHPP050A-033		US50 West of Delta EB Lanes R	03/14/19	1.00	1000.00	2030.00	790.00
SHER100-308		MIDPOINT - SIGNAL CONST PACKA	03/21/19	1.00	1000.00	3025.00	3200.00
	WEIGHTED AVERAGE FOR THE FIRST QUARTER			29.00	1073.10	1801.86	1158.14
IM0252-472		I-25 CABLE BARRIER PHASE III	04/04/19	2.00	1000.00	3550.00	5000.00
NHPP0703-445		I-70 WESTBOUND PEAK PERIOD SH	04/25/19	16.00	1500.00	893.70	630.00
MTCE0641-103		MTCE R3 FY20 SH 64 RANGELY PE	05/02/19	3.00	1000.00	1027.50	1250.00
	WEIGHTED AVERAGE FOR THE SECOND QUARTER			21.00	1380.95	1090.73	1134.76
	WEIGHTED AVERAGE FOR THE YEAR			50.00	1202.40	1610.02	1148.32
===== 202-00020		Rem CBC		Each =====			
ER119A-065		PR SH 119A BOULDER CANYON	01/03/19	1.00	20000.00	17126.68	12000.00
STA119A-069		SH 119: NEDERLAND - EAST					
STR0132-021		SH 13-MOFFAT COUNTY-CR 3 SOUT	01/10/19	1.00	15000.00	31032.00	36710.00
ER072A-040		PR SH72A FLOOD PERMANENT REPA	01/31/19	4.00	20000.00	20695.86	14000.00
NHPP072A-041		PR SH72A FLOOD PERMANENT REPA					
	WEIGHTED AVERAGE FOR THE FIRST QUARTER			6.00	19166.67	21074.99	17451.67
	WEIGHTED AVERAGE FOR THE YEAR			6.00	19166.67	21074.99	17451.67

COLORADO DEPARTMENT OF TRANSPORTATION
 ITEM UNIT COSTS BY PROJECTS -- 2019 COST DATA

13:44 Wednesday, August 7, 2019 5

PROJECT NUMBER	ITEM NUMBER/ PROJECT LOCATION	ITEM DESCRIPTION/ PROJECT LOCATION	DATE LET	UNIT/ QUANTITY	ENGR. EST.	AVERAGE BID	AWARDED BID
=====	202-00021	Rem Manhole		Each	=====		
SHER100-289		INTERSECTIONS @ SH83 & LONGS	01/03/19	2.00	2000.00	1283.40	2200.00
STAM086-075		SH96A ABRIENDO - ORMAN SAFETY	01/31/19	1.00	1200.00	5159.00	2932.00
		WEIGHTED AVERAGE FOR THE FIRST QUARTER		3.00	1733.33	2177.77	2444.00
NHPP0703-445		I-70 WESTBOUND PEAK PERIOD SH	04/25/19	23.00	1000.00	2987.74	838.00
		WEIGHTED AVERAGE FOR THE SECOND QUARTER		23.00	1000.00	2987.74	838.00
		WEIGHTED AVERAGE FOR THE YEAR		26.00	1084.62	2859.33	1023.31
=====	202-00024	Rem Emb Prot Ty 5		Each	=====		
STM0242-077		US24 - 8TH ST TO WEST OF MANI	03/28/19	1.00	2500.00	790.00	800.00
		WEIGHTED AVERAGE FOR THE FIRST QUARTER		1.00	2500.00	790.00	800.00
		WEIGHTED AVERAGE FOR THE YEAR		1.00	2500.00	790.00	800.00
=====	202-00026	Rem S and D Pave		Sq Yard	=====		
SHE2254-090		Colfax & I-225, Colfax & Cham	03/07/19	142.00	17.00	40.50	26.00
		WEIGHTED AVERAGE FOR THE FIRST QUARTER		142.00	17.00	40.50	26.00
NHPP0703-445		I-70 WESTBOUND PEAK PERIOD SH	04/25/19	167.00	17.00	32.78	25.00
		WEIGHTED AVERAGE FOR THE SECOND QUARTER		167.00	17.00	32.78	25.00
		WEIGHTED AVERAGE FOR THE YEAR		309.00	17.00	35.57	25.46
=====	202-00027	Rem Riprap		Sq Yard	=====		
FBR0341-087		US 34 OVER NORTH FORK CO RIVE	01/10/19	22.00	30.00	23.20	20.34

PROJECT NUMBER	ITEM NUMBER/ PROJECT LOCATION	ITEM DESCRIPTION/ PROJECT LOCATION	DATE LET	UNIT/ QUANTITY	ENGR. EST.	AVERAGE BID	AWARDED BID
=====	202-00027	Rem Riprap		Sq Yard	=====	=====	=====
NHPP050A-033		US50 West of Delta EB Lanes R	03/14/19	11.00	70.00	68.33	55.00
STM0242-077		US24 - 8TH ST TO WEST OF MANI	03/28/19	300.00	75.00	46.00	25.00
		WEIGHTED AVERAGE FOR THE FIRST QUARTER		333.00	71.86	43.87	25.68
		WEIGHTED AVERAGE FOR THE YEAR		333.00	71.86	43.87	25.68
=====	202-00032	Rem Valve		Each	=====	=====	=====
STR0241-062		US 24 143.4 - 148	01/24/19	1.00	1200.00	2648.33	750.00
		WEIGHTED AVERAGE FOR THE FIRST QUARTER		1.00	1200.00	2648.33	750.00
		WEIGHTED AVERAGE FOR THE YEAR		1.00	1200.00	2648.33	750.00
=====	202-00033	Rem Pipe		Each	=====	=====	=====
ER119A-065		PR SH 119A BOULDER CANYON	01/03/19	15.00	1500.00	2411.30	560.00
STA119A-069		SH 119: NEDERLAND - EAST					
STR0132-021		SH 13-MOFFAT COUNTY-CR 3 SOUT	01/10/19	12.00	2000.00	2528.00	2620.00
NHPP145A-065		SH 145 PASSING LANES AT DEEP	02/14/19	13.00	1500.00	3593.26	1750.00
NHPP1601-073		US 160 PASSING LANE NORTH OF	03/07/19	12.00	4000.00	1460.00	1320.00
NHPP006A-058		US 6 LOVELAND PASS - I-70 (FY	03/07/19	3.00	2000.00	3249.17	2498.33
STA0131-070 HMA ALT		SH 13 CR 5 NORTH AND SOUTH	03/28/19	60.00	1200.00	3648.67	3310.00
STA0131-070 PCCP ALT		SH 13 CR 5 NORTH AND SOUTH					
		WEIGHTED AVERAGE FOR THE FIRST QUARTER		115.00	1669.57	3045.92	2179.12
		WEIGHTED AVERAGE FOR THE YEAR		115.00	1669.57	3045.92	2179.12
=====	202-00035	Rem Pipe		Lin Foot	=====	=====	=====
SHER100-289		INTERSECTIONS @ SH83 & LONGS	01/03/19	738.00	27.00	25.80	28.00
ER119A-065		PR SH 119A BOULDER CANYON	01/03/19	182.00	60.00	46.73	20.00
STA119A-069		SH 119: NEDERLAND - EAST					
STR0241-062		US 24 143.4 - 148	01/24/19	151.00	40.00	60.67	34.00
ER072A-040		PR SH72A FLOOD PERMANENT REPA	01/31/19	470.00	40.00	53.37	16.00
NHPP072A-041		PR SH72A FLOOD PERMANENT REPA					
STAM086-075		SH96A ABRIENDO - ORMAN SAFETY	01/31/19	290.00	27.00	58.17	39.50
FBR0253-247		I25 AT VINE DRIVE BRIDGE REPL	03/07/19	269.00	25.00	20.26	14.00
SHE2254-090		Colfax & I-225, Colfax & Cham	03/07/19	9.00	27.00	289.50	64.00
NHPP0503-087		US 50 PASSING LANES EAST OF S	03/21/19	769.00	50.00	57.50	70.00

PROJECT NUMBER	ITEM NUMBER/ PROJECT LOCATION	ITEM DESCRIPTION/ PROJECT LOCATION	DATE LET	UNIT/ QUANTITY	ENGR. EST.	AVERAGE BID	AWARDED BID
=====	202-00035	Rem Pipe		Lin Foot	=====	=====	=====
SHER100-308		MIDPOINT - SIGNAL CONST PACKA	03/21/19	32.00	30.00	70.25	64.00
		WEIGHTED AVERAGE FOR THE FIRST QUARTER		2,910.00	37.76	41.97	37.33
NHPP0703-445		I-70 WESTBOUND PEAK PERIOD SH	04/25/19	1,082.00	28.00	35.96	32.00
MTCE0641-103		MTCE R3 FY20 SH 64 RANGELY PE	05/02/19	35.00	25.00	51.75	62.00
NHPP160A-030		US160 MM 43.2, 150.4, 156.3,	06/20/19	78.00	80.00	81.75	63.50
		WEIGHTED AVERAGE FOR THE SECOND QUARTER		1,195.00	31.31	38.34	34.93
		WEIGHTED AVERAGE FOR THE YEAR		4,105.00	35.88	41.35	36.63
=====	202-00037	Rem of End Section		Each	=====	=====	=====
SHER100-289		INTERSECTIONS @ SH83 & LONGS	01/03/19	2.00	300.00	322.10	330.00
ER119A-065		PR SH 119A BOULDER CANYON	01/03/19	1.00	340.00	697.50	250.00
STA119A-069		SH 119: NEDERLAND - EAST					
ER072A-040		PR SH72A FLOOD PERMANENT REPA	01/31/19	6.00	550.00	985.74	125.00
NHPP072A-041		PR SH72A FLOOD PERMANENT REPA					
NH2871-035		US 287 PASSING LANES SOUTH OF	02/07/19	1.00	500.00	577.52	353.00
NHPP145A-065		SH 145 PASSING LANES AT DEEP	02/14/19	2.00	800.00	1483.14	375.00
FBR0253-247		I25 AT VINE DRIVE BRIDGE REPL	03/07/19	1.00	500.00	457.97	400.00
SHE2254-090		Colfax & I-225, Colfax & Cham	03/07/19	1.00	300.00	875.00	850.00
		WEIGHTED AVERAGE FOR THE FIRST QUARTER		14.00	510.00	886.35	286.64
NHPP0703-445		I-70 WESTBOUND PEAK PERIOD SH	04/25/19	9.00	300.00	481.01	385.00
FBR0063-057		US-6 F-09-K BRIDGE OVER CASTL	05/30/19	1.00	500.00	1107.50	715.00
		WEIGHTED AVERAGE FOR THE SECOND QUARTER		10.00	320.00	524.21	418.00
		WEIGHTED AVERAGE FOR THE YEAR		24.00	430.83	814.42	341.38
=====	202-00039	Rem of Bollard		Each	=====	=====	=====
STR0241-062		US 24 143.4 - 148	01/24/19	6.00	120.00	245.00	200.00
		WEIGHTED AVERAGE FOR THE FIRST QUARTER		6.00	120.00	245.00	200.00

PROJECT NUMBER	ITEM NUMBER/ PROJECT LOCATION	ITEM DESCRIPTION/ PROJECT LOCATION	DATE LET	UNIT/ QUANTITY	ENGR. EST.	AVERAGE BID	AWARDED BID
=====	202-00039	Rem of Bollard		Each	=====		
NHPP0703-445		I-70 WESTBOUND PEAK PERIOD SH	04/25/19	8.00	1000.00	403.03	618.00
		WEIGHTED AVERAGE FOR THE SECOND QUARTER		8.00	1000.00	403.03	618.00
		WEIGHTED AVERAGE FOR THE YEAR		14.00	622.86	335.30	438.86
=====	202-00040	Rem Elec Conduit		Lin Foot	=====		
NHPP0703-445		I-70 WESTBOUND PEAK PERIOD SH	04/25/19	2,760.00	19.00	28.56	30.00
SHE0701-243		I-70 EXIT 26 DDI MODIFICATION	05/16/19	528.00	10.00	5.30	5.00
		WEIGHTED AVERAGE FOR THE SECOND QUARTER		3,288.00	17.55	23.84	25.99
		WEIGHTED AVERAGE FOR THE YEAR		3,288.00	17.55	23.84	25.99
=====	202-00070	Rem Barricade		Each	=====		
STA067A-038		SH 67 SEDALIA RESURFACING	01/31/19	1.00	500.00	877.61	500.00
		WEIGHTED AVERAGE FOR THE FIRST QUARTER		1.00	500.00	877.61	500.00
		WEIGHTED AVERAGE FOR THE YEAR		1.00	500.00	877.61	500.00
=====	202-00080	Rem Guard Post		Each	=====		
NHPP030A-035		US 285/SH30	04/04/19	4.00	200.00	200.00	200.00
		WEIGHTED AVERAGE FOR THE SECOND QUARTER		4.00	200.00	200.00	200.00
		WEIGHTED AVERAGE FOR THE YEAR		4.00	200.00	200.00	200.00
=====	202-00090	Rem Delineator		Each	=====		
IM0251-351		I-25 South of Pueblo MP 79.6	01/03/19	415.00	9.00	3.99	4.46
SHER100-289		INTERSECTIONS @ SH83 & LONGS	01/03/19	38.00	35.00	14.30	10.50
ER119A-065		PR SH 119A BOULDER CANYON	01/03/19	825.00	7.00	8.57	4.00

PROJECT NUMBER	ITEM NUMBER/ PROJECT LOCATION	ITEM DESCRIPTION/ PROJECT LOCATION	DATE LET	UNIT/ QUANTITY	ENGR. EST.	AVERAGE BID	AWARDED BID
===== 202-00090							
		Rem Delineator		Each			
STA119A-069		SH 119: NEDERLAND - EAST					
STR0132-021		SH 13-MOFFAT COUNTY-CR 3 SOUT	01/10/19	92.00	6.00	11.90	12.10
FBR0341-087		US 34 OVER NORTH FORK CO RIVE	01/10/19	9.00	15.00	9.36	6.03
STR141A-047		SH 141 MP 120-143 MESA COUNTY	01/17/19	485.00	10.00	5.73	5.25
STR0241-062		US 24 143.4 - 148	01/24/19	23.00	8.00	10.67	13.00
STA067A-038		SH 67 SEDALIA RESURFACING	01/31/19	5.00	80.00	63.98	20.00
NH2871-035		US 287 PASSING LANES SOUTH OF	02/07/19	95.00	10.00	5.50	5.25
NHPP145A-065		SH 145 PASSING LANES AT DEEP	02/14/19	20.00	10.00	11.05	10.00
NHPP0741-022		SH 74: I-70 TO CR 65 RESURFAC	02/14/19	10.00	13.00	8.22	7.60
NHPP070A-028		FALL RIVER ROAD BRIDGE	02/21/19	12.00	20.00	35.06	12.00
NHPP1601-073		US 160 PASSING LANE NORTH OF	03/07/19	60.00	8.00	7.90	7.80
C R100-315		R1 ADA CURB RAMPS - PH 5	03/07/19	50.00	14.00	135.00	85.00
NHPP050A-033		US50 West of Delta EB Lanes R	03/14/19	170.00	6.00	5.17	5.00
NHPP0503-087		US 50 PASSING LANES EAST OF S	03/21/19	35.00	10.00	4.00	5.00
SHE 0252-481		I-25 RAMP METER INSTALLATION	03/21/19	32.00	13.00	33.33	72.00
NHPP2254-089		I-225 RESURFACING FROM I-25 T	03/21/19	160.00	7.00	13.11	20.00
STM0242-077		US24 - 8TH ST TO WEST OF MANI	03/28/19	303.00	8.05	5.40	7.00
STA0131-070 HMA ALT		SH 13 CR 5 NORTH AND SOUTH	03/28/19	146.00	8.00	11.23	6.05
STA0131-070 PCCP ALT		SH 13 CR 5 NORTH AND SOUTH					
		WEIGHTED AVERAGE FOR THE FIRST QUARTER		2,985.00	8.77	8.88	8.38
BR071A-020		REPLACEMENT OF STRUCTURE L-22	04/18/19	16.00	6.50	30.50	21.00
NHPP0703-445		I-70 WESTBOUND PEAK PERIOD SH	04/25/19	200.00	10.00	14.79	20.00
FBR0063-057		US-6 F-09-K BRIDGE OVER CASTL	05/30/19	6.00	5.00	28.75	55.00
STRR200-257		ROAD CLOSURE GATES ON VARIOUS	05/30/19	3.00	20.00	58.50	50.00
NHPP030A-036		SH 30 & TOWER RD IMPROVEMENTS	06/13/19	6.00	16.00	7.00	7.00
CR500-205		R5 GUARDRAIL END TREATMENT EA	06/13/19	53.00	10.00	7.60	7.60
		WEIGHTED AVERAGE FOR THE SECOND QUARTER		284.00	9.93	15.83	18.52
		WEIGHTED AVERAGE FOR THE YEAR		3,269.00	8.87	9.22	9.28
===== 202-00150							
		Rem Wall		Each			
ER119A-065		PR SH 119A BOULDER CANYON	01/03/19	15.00	850.00	717.61	95.00
STA119A-069		SH 119: NEDERLAND - EAST					
		WEIGHTED AVERAGE FOR THE FIRST QUARTER		15.00	850.00	717.61	95.00
		WEIGHTED AVERAGE FOR THE YEAR		15.00	850.00	717.61	95.00
===== 202-00155							
		Rem Wall		Lin Foot			
ER119A-065		PR SH 119A BOULDER CANYON	01/03/19	246.00	40.00	60.34	17.50

COLORADO DEPARTMENT OF TRANSPORTATION
 ITEM UNIT COSTS BY PROJECTS -- 2019 COST DATA

13:44 Wednesday, August 7, 2019 10

PROJECT NUMBER	ITEM NUMBER/ PROJECT LOCATION	ITEM DESCRIPTION/ PROJECT LOCATION	DATE LET	UNIT/ QUANTITY	ENGR. EST.	AVERAGE BID	AWARDED BID
=====	202-00155	Rem Wall		Lin Foot	=====		
STA119A-069		SH 119: NEDERLAND - EAST					
STR0241-062		US 24 143.4 - 148	01/24/19	201.00	70.00	28.33	25.00
		WEIGHTED AVERAGE FOR THE FIRST QUARTER		447.00	53.49	52.83	20.87
MTCE0641-103		MTCE R3 FY20 SH 64 RANGELY PE	05/02/19	430.00	30.00	12.38	14.00
		WEIGHTED AVERAGE FOR THE SECOND QUARTER		430.00	30.00	12.38	14.00
		WEIGHTED AVERAGE FOR THE YEAR		877.00	41.97	42.69	17.50
=====	202-00165	Rem Wall		LUMP SUM	=====		
NHPP0703-442		I-70 SILVERPLUME SOUNDWALL AN	06/13/19	1.00	100000.00	271131.55	212800.00
		WEIGHTED AVERAGE FOR THE SECOND QUARTER		1.00	100000.00	271131.55	212800.00
		WEIGHTED AVERAGE FOR THE YEAR		1.00	100000.00	271131.55	212800.00
=====	202-00170	Grinding And Texturing Conc Pvmt		Sq Yard	=====		
NHPP0703-445		I-70 WESTBOUND PEAK PERIOD SH	04/25/19	1,662.00	10.00	25.29	42.00
STMC430-020		ADA RAMPS DIVIDE ESB	05/23/19	10.00	8.90	272.88	272.88
		WEIGHTED AVERAGE FOR THE SECOND QUARTER		1,672.00	9.99	25.78	43.38
		WEIGHTED AVERAGE FOR THE YEAR		1,672.00	9.99	25.78	43.38
=====	202-00175	Rem Concrete		LUMP SUM	=====		
NHPP0503-087		US 50 PASSING LANES EAST OF S	03/21/19	1.00	4000.00	24000.00	18000.00
		WEIGHTED AVERAGE FOR THE FIRST QUARTER		1.00	4000.00	24000.00	18000.00
MTCE0641-103		MTCE R3 FY20 SH 64 RANGELY PE	05/02/19	1.00	1500.00	2185.00	1200.00
		WEIGHTED AVERAGE FOR THE SECOND QUARTER		1.00	1500.00	2185.00	1200.00
		WEIGHTED AVERAGE FOR THE YEAR		2.00	2750.00	13092.50	9600.00

PROJECT NUMBER	ITEM NUMBER/ PROJECT LOCATION	ITEM DESCRIPTION/ PROJECT LOCATION	DATE LET	UNIT/ QUANTITY	ENGR. EST.	AVERAGE BID	AWARDED BID
===== 202-00190		Rem of Conc Median Cover Matl		Sq Yard	=====		
SHER100-289		INTERSECTIONS @ SH83 & LONGS	01/03/19	886.00	20.00	12.00	10.00
NHPP0741-022		SH 74: I-70 TO CR 65 RESURFAC	02/14/19	396.00	25.00	28.07	35.80
SHER100-284		FY19 NORTH SIGNAL PKG	02/21/19	57.00	29.00	38.00	35.00
SHE2254-090		Colfax & I-225, Colfax & Cham	03/07/19	812.00	20.00	29.50	24.00
SHER100-308		MIDPOINT - SIGNAL CONST PACKA	03/21/19	337.00	7.50	34.50	35.00
NHPP2254-089		I-225 RESURFACING FROM I-25 T	03/21/19	186.00	40.00	46.15	52.00
		WEIGHTED AVERAGE FOR THE FIRST QUARTER		2,674.00	20.75	22.24	24.68
FSA0252-468		I-25 AND PLUM CREEK IMPROVEME	04/18/19	641.00	16.00	24.00	36.00
C2571-013		SH257 & 392:WINDSOR CURB RAMP	05/02/19	28.00	40.00	32.00	30.00
FSA2873-190		US 287 AND FOOTHILLS PARKWAY	05/02/19	31.00	22.00	53.50	60.00
STMC430-020		ADA RAMPS DIVIDE ESB	05/23/19	83.00	16.00	102.83	102.83
		WEIGHTED AVERAGE FOR THE SECOND QUARTER		783.00	17.10	27.24	43.82
		WEIGHTED AVERAGE FOR THE YEAR		3,457.00	19.92	23.42	29.01
===== 202-00195		Rem of Median Cover		Sq Yard	=====		
C R100-315		R1 ADA CURB RAMPS - PH 5	03/07/19	123.00	26.00	32.50	25.00
STM0242-077		US24 - 8TH ST TO WEST OF MANI	03/28/19	1,245.00	20.00	5.83	3.00
		WEIGHTED AVERAGE FOR THE FIRST QUARTER		1,368.00	20.54	7.48	4.98
NHPP030A-035		US 285/SH30	04/04/19	859.00	5.00	20.00	20.00
FSA2873-190		US 287 AND FOOTHILLS PARKWAY	05/02/19	22.00	25.00	54.50	60.00
SHE0701-243		I-70 EXIT 26 DDI MODIFICATION	05/16/19	1,442.00	10.00	4.06	5.00
		WEIGHTED AVERAGE FOR THE SECOND QUARTER		2,323.00	8.29	6.45	11.07
		WEIGHTED AVERAGE FOR THE YEAR		3,691.00	12.83	6.83	8.81
===== 202-00200		Rem Sidewalk		Sq Yard	=====		
SHER100-289		INTERSECTIONS @ SH83 & LONGS	01/03/19	56.00	30.00	17.30	12.50

PROJECT NUMBER	ITEM NUMBER/ PROJECT LOCATION	ITEM DESCRIPTION/ PROJECT LOCATION	DATE LET	UNIT/ QUANTITY	ENGR. EST.	AVERAGE BID	AWARDED BID
=====	202-00200	Rem Sidewalk		Sq Yard	=====	=====	=====
ER119A-065		PR SH 119A BOULDER CANYON	01/03/19	896.00	18.00	14.76	5.00
STA119A-069		SH 119: NEDERLAND - EAST					
NHPP0701-241		I-70 TRUCK PARKING GARFIELD C	01/17/19	479.00	17.00	16.35	16.00
STR0241-062		US 24 143.4 - 148	01/24/19	462.00	17.00	27.33	10.00
STAM086-075		SH96A ABRIENDO - ORMAN SAFETY	01/31/19	149.00	26.00	55.83	41.50
NHPP0821-107		SH 82 GLENWOOD SPRINGS TO CA	02/07/19	228.00	25.00	47.00	34.00
SHER100-284		FY19 NORTH SIGNAL PKG	02/21/19	1.00	30.00	314.67	126.00
C R100-315		R1 ADA CURB RAMPS - PH 5	03/07/19	1,320.00	28.00	34.00	28.00
SHE2254-090		Colfax & I-225, Colfax & Cham	03/07/19	408.00	25.00	45.50	26.00
NHPP0702-378		I-70 OFFICERS GULCH TO FRISCO	03/14/19	47.00	400.00	142.92	358.75
SHER100-308		MIDPOINT - SIGNAL CONST PACKA	03/21/19	205.00	30.00	35.00	36.00
NHPP2254-089		I-225 RESURFACING FROM I-25 T	03/21/19	73.00	25.00	83.65	93.00
STM0242-077		US24 - 8TH ST TO WEST OF MANI	03/28/19	214.00	17.00	9.67	6.00
		WEIGHTED AVERAGE FOR THE FIRST QUARTER		4,538.00	26.66	24.76	24.55
				-----	-----	-----	-----
NHPP030A-035		US 285/SH30	04/04/19	217.50	25.00	90.00	90.00
FSA0252-468		I-25 AND PLUM CREEK IMPROVEME	04/18/19	31.00	30.00	35.25	59.00
NHPP0703-445		I-70 WESTBOUND PEAK PERIOD SH	04/25/19	261.00	25.00	20.55	18.00
C2571-013		SH257 & 392:WINDSOR CURB RAMP	05/02/19	274.00	30.00	27.67	25.00
MTCE0641-103		MTCE R3 FY20 SH 64 RANGELY PE	05/02/19	457.00	25.00	25.50	21.00
CR300-248		CRAIG RESIDENCY ADA RAMPS	05/16/19	1,974.00	45.00	42.00	22.00
STMC430-020		ADA RAMPS DIVIDE ESB	05/23/19	171.00	20.00	58.58	58.58
STR 141A-040		R5 YEAR 4 BRDG PREV MAINT RAM	06/20/19	5.00	50.00	105.00	50.00
		WEIGHTED AVERAGE FOR THE SECOND QUARTER		3,390.50	36.88	38.59	28.39
				=====	=====	=====	=====
		WEIGHTED AVERAGE FOR THE YEAR		7,928.50	31.03	29.53	26.19
=====	202-00201	Rem Curb		Lin Foot	=====	=====	=====
ER119A-065		PR SH 119A BOULDER CANYON	01/03/19	807.00	5.00	12.63	12.00
STA119A-069		SH 119: NEDERLAND - EAST					
STA067A-038		SH 67 SEDALIA RESURFACING	01/31/19	370.00	12.00	13.49	12.00
SHE2254-090		Colfax & I-225, Colfax & Cham	03/07/19	533.00	10.00	10.00	5.00
STM0242-077		US24 - 8TH ST TO WEST OF MANI	03/28/19	3,467.00	10.00	4.13	5.00
		WEIGHTED AVERAGE FOR THE FIRST QUARTER		5,177.00	9.36	7.89	6.59
				-----	-----	-----	-----
NHPP030A-035		US 285/SH30	04/04/19	41.30	10.00	70.00	70.00

COLORADO DEPARTMENT OF TRANSPORTATION
 ITEM UNIT COSTS BY PROJECTS -- 2019 COST DATA

13:44 Wednesday, August 7, 2019 13

PROJECT NUMBER	ITEM NUMBER/ PROJECT LOCATION	ITEM DESCRIPTION/ PROJECT LOCATION	DATE LET	UNIT/ QUANTITY	ENGR. EST.	AVERAGE BID	AWARDED BID
=====	202-00201	Rem Curb		Lin Foot	=====		
FSA2873-190		US 287 AND FOOTHILLS PARKWAY	05/02/19	75.00	20.00	17.50	24.00
SHE0701-243		I-70 EXIT 26 DDI MODIFICATION	05/16/19	504.00	10.00	5.56	5.00
		WEIGHTED AVERAGE FOR THE SECOND QUARTER		620.30	11.21	7.58	11.63
		WEIGHTED AVERAGE FOR THE YEAR		5,797.30	9.56	7.86	7.13
=====	202-00202	Rem Gutter		Lin Foot	=====		
ER119A-065		PR SH 119A BOULDER CANYON	01/03/19	18.00	15.00	38.64	17.00
STA119A-069		SH 119: NEDERLAND - EAST					
		WEIGHTED AVERAGE FOR THE FIRST QUARTER		18.00	15.00	38.64	17.00
		WEIGHTED AVERAGE FOR THE YEAR		18.00	15.00	38.64	17.00
=====	202-00203	Rem Curb and Gutter		Lin Foot	=====		
SHER100-289		INTERSECTIONS @ SH83 & LONGS	01/03/19	1,606.00	14.00	10.30	11.50
ER119A-065		PR SH 119A BOULDER CANYON	01/03/19	522.00	8.00	12.85	6.00
STA119A-069		SH 119: NEDERLAND - EAST					
NHPP0701-241		I-70 TRUCK PARKING GARFIELD C	01/17/19	896.00	8.00	9.88	12.00
STR0241-062		US 24 143.4 - 148	01/24/19	479.00	25.00	12.67	7.00
STAM086-075		SH96A ABRIENDO - ORMAN SAFETY	01/31/19	841.00	9.00	26.00	16.00
NHPP0821-107		SH 82 GLENWOOD SPRINGS TO CA	02/07/19	340.00	10.00	21.50	8.00
NHPP0741-022		SH 74: I-70 TO CR 65 RESURFAC	02/14/19	843.00	12.00	14.60	10.85
SHER100-284		FY19 NORTH SIGNAL PKG	02/21/19	229.00	15.00	13.33	14.00
FBR0253-247		I25 AT VINE DRIVE BRIDGE REPL	03/07/19	410.00	10.00	6.92	5.50
C R100-315		R1 ADA CURB RAMPS - PH 5	03/07/19	2,373.00	14.00	26.50	15.00
SHE2254-090		Colfax & I-225, Colfax & Cham	03/07/19	1,321.00	15.00	20.50	10.00
NHPP0702-378		I-70 OFFICERS GULCH TO FRISCO	03/14/19	78.00	30.00	30.29	35.87
SHER100-308		MIDPOINT - SIGNAL CONST PACKA	03/21/19	972.00	10.00	12.88	12.00
NHPP2254-089		I-225 RESURFACING FROM I-25 T	03/21/19	312.00	11.00	20.21	22.00
STM0242-077		US24 - 8TH ST TO WEST OF MANI	03/28/19	2,606.00	10.00	5.80	2.50
		WEIGHTED AVERAGE FOR THE FIRST QUARTER		13,828.00	12.22	13.38	10.35
NHPP030A-035		US 285/SH30	04/04/19	957.50	14.00	24.00	24.00
FSA0252-468		I-25 AND PLUM CREEK IMPROVEME	04/18/19	553.00	15.00	18.50	19.00
NHPP0703-445		I-70 WESTBOUND PEAK PERIOD SH	04/25/19	443.00	14.00	9.35	9.00
C2571-013		SH257 & 392:WINDSOR CURB RAMP	05/02/19	850.00	20.00	13.17	12.00

PROJECT NUMBER	ITEM NUMBER/ PROJECT LOCATION	ITEM DESCRIPTION/ PROJECT LOCATION	DATE LET	UNIT/ QUANTITY	ENGR. EST.	AVERAGE BID	AWARDED BID
===== 202-00203							
	Rem Curb and Gutter			Lin Foot			
MTCE0641-103	MTCE R3 FY20 SH 64 RANGELY PE		05/02/19	828.00	15.00	10.25	10.00
FSA2873-190	US 287 AND FOOTHILLS PARKWAY		05/02/19	136.00	20.00	17.50	20.00
CR300-248	CRAIG RESIDENCY ADA RAMPS		05/16/19	4,237.00	20.00	20.00	9.00
SHE0701-243	I-70 EXIT 26 DDI MODIFICATION		05/16/19	815.00	10.00	6.19	8.00
STMC430-020	ADA RAMPS DIVIDE ESB		05/23/19	394.00	14.50	17.13	17.13
STR 141A-040	R5 YEAR 4 BRDG PREV MAINT RAM		06/20/19	12.00	15.00	56.00	50.00
	WEIGHTED AVERAGE FOR THE SECOND QUARTER			9,225.50	17.22	16.33	12.00
	WEIGHTED AVERAGE FOR THE YEAR			23,053.50	14.22	14.39	11.01
===== 202-00204							
	Rem C, G and Sidewalk			Lin Foot			
ER119A-065	PR SH 119A BOULDER CANYON		01/03/19	125.00	8.00	39.13	11.00
STA119A-069	SH 119: NEDERLAND - EAST						
STAM086-075	SH96A ABRIENDO - ORMAN SAFETY		01/31/19	538.00	20.00	34.00	18.00
	WEIGHTED AVERAGE FOR THE FIRST QUARTER			663.00	17.74	35.96	16.68
	WEIGHTED AVERAGE FOR THE YEAR			663.00	17.74	35.96	16.68
===== 202-00206							
	Rem Conc Curb Ramp			Sq Yard			
SHER100-289	INTERSECTIONS @ SH83 & LONGS		01/03/19	148.00	38.00	24.60	33.00
ER119A-065	PR SH 119A BOULDER CANYON		01/03/19	117.00	27.00	37.79	10.00
STA119A-069	SH 119: NEDERLAND - EAST						
NHPP0741-022	SH 74: I-70 TO CR 65 RESURFAC		02/14/19	139.00	36.00	28.56	36.90
SHER100-284	FY19 NORTH SIGNAL PKG		02/21/19	199.00	40.00	29.33	36.00
SHE2254-090	Colfax & I-225, Colfax & Cham		03/07/19	393.00	38.00	57.00	34.00
NHPP0702-378	I-70 OFFICERS GULCH TO FRISCO		03/14/19	25.00	450.00	163.33	410.00
SHER100-308	MIDPOINT - SIGNAL CONST PACKA		03/21/19	131.00	43.00	39.50	38.50
NHPP2254-089	I-225 RESURFACING FROM I-25 T		03/21/19	118.00	36.00	61.76	75.00
STM0242-077	US24 - 8TH ST TO WEST OF MANI		03/28/19	61.00	46.20	25.00	12.00
	WEIGHTED AVERAGE FOR THE FIRST QUARTER			1,331.00	45.55	40.28	42.51
===== 202-00207							
NHPP030A-035	US 285/SH30		04/04/19	730.20	30.00	80.00	80.00
NHPP0703-445	I-70 WESTBOUND PEAK PERIOD SH		04/25/19	119.00	40.00	30.63	39.00
C2571-013	SH257 & 392:WINDSOR CURB RAMP		05/02/19	826.00	28.00	28.00	20.00
FSA2873-190	US 287 AND FOOTHILLS PARKWAY		05/02/19	90.00	45.00	49.00	61.00
STMC430-020	ADA RAMPS DIVIDE ESB		05/23/19	189.00	32.57	77.80	77.80
	WEIGHTED AVERAGE FOR THE SECOND QUARTER			1,954.20	30.70	41.24	51.05
	WEIGHTED AVERAGE FOR THE YEAR			3,285.20	36.72	40.73	47.59

COLORADO DEPARTMENT OF TRANSPORTATION
ITEM UNIT COSTS BY PROJECTS -- 2019 COST DATA

13:44 Wednesday, August 7, 2019 15

PROJECT NUMBER	ITEM NUMBER/ PROJECT LOCATION	ITEM DESCRIPTION/ PROJECT LOCATION	DATE LET	UNIT/ QUANTITY	ENGR. EST.	AVERAGE BID	AWARDED BID
=====	202-00207	Rem of Brick Pavers		Sq Yard	=====		
ER119A-065	PR SH 119A BOULDER CANYON	PR SH 119A BOULDER CANYON	01/03/19	70.00	25.00	33.96	16.00
STA119A-069	SH 119: NEDERLAND - EAST	SH 119: NEDERLAND - EAST					
STR0241-062	US 24 143.4 - 148	US 24 143.4 - 148	01/24/19	144.00	30.00	27.17	9.00
	WEIGHTED AVERAGE FOR THE FIRST QUARTER			214.00	28.36	31.00	11.29
	WEIGHTED AVERAGE FOR THE YEAR			214.00	28.36	31.00	11.29
=====	202-00210	Rem Conc Pavement		Sq Yard	=====		
SHER100-289	INTERSECTIONS @ SH83 & LONGS	INTERSECTIONS @ SH83 & LONGS	01/03/19	59.00	35.00	30.40	21.00
ER119A-065	PR SH 119A BOULDER CANYON	PR SH 119A BOULDER CANYON	01/03/19	474.00	30.00	18.97	8.50
STA119A-069	SH 119: NEDERLAND - EAST	SH 119: NEDERLAND - EAST					
STR0241-062	US 24 143.4 - 148	US 24 143.4 - 148	01/24/19	238.00	25.00	44.67	14.00
NHPPR100-250	PACKAGE A (I-25 / I-70 / I-76	PACKAGE A (I-25 / I-70 / I-76	01/24/19	160.00	27.00	179.12	75.00
ER072A-040	PR SH72A FLOOD PERMANENT REPA	PR SH72A FLOOD PERMANENT REPA	01/31/19	118.00	45.00	78.28	20.00
NHPP072A-041	PR SH72A FLOOD PERMANENT REPA	PR SH72A FLOOD PERMANENT REPA					
STAM086-075	SH96A ABRIENDO - ORMAN SAFETY	SH96A ABRIENDO - ORMAN SAFETY	01/31/19	150.00	55.00	96.00	63.00
NHPP0821-107	SH 82 GLENWOOD SPRINGS TO CA	SH 82 GLENWOOD SPRINGS TO CA	02/07/19	88.00	35.00	68.50	67.00
C R100-315	R1 ADA CURB RAMPS - PH 5	R1 ADA CURB RAMPS - PH 5	03/07/19	29.00	37.00	60.00	45.00
SHE 0252-481	I-25 RAMP METER INSTALLATION	I-25 RAMP METER INSTALLATION	03/21/19	326.00	37.00	189.00	165.00
	WEIGHTED AVERAGE FOR THE FIRST QUARTER			1,642.00	34.31	70.34	56.88
NHPP030A-035	US 285/SH30	US 285/SH30	04/04/19	75.30	37.00	200.00	200.00
FSA0252-468	I-25 AND PLUM CREEK IMPROVEME	I-25 AND PLUM CREEK IMPROVEME	04/18/19	605.00	47.00	44.88	36.00
NHPP0703-445	I-70 WESTBOUND PEAK PERIOD SH	I-70 WESTBOUND PEAK PERIOD SH	04/25/19	3,878.00	35.00	16.03	14.00
C2571-013	SH257 & 392:WINDSOR CURB RAMP	SH257 & 392:WINDSOR CURB RAMP	05/02/19	163.00	35.00	42.00	30.00
MTCE0641-103	MTCE R3 FY20 SH 64 RANGELY PE	MTCE R3 FY20 SH 64 RANGELY PE	05/02/19	272.00	30.00	33.50	28.00
FSA2873-190	US 287 AND FOOTHILLS PARKWAY	US 287 AND FOOTHILLS PARKWAY	05/02/19	18.00	25.00	98.50	160.00
CR300-248	CRAIG RESIDENCY ADA RAMPS	CRAIG RESIDENCY ADA RAMPS	05/16/19	275.00	45.00	60.00	32.00
SHE0701-243	I-70 EXIT 26 DDI MODIFICATION	I-70 EXIT 26 DDI MODIFICATION	05/16/19	357.00	30.00	11.69	25.00
STMC430-020	ADA RAMPS DIVIDE ESB	ADA RAMPS DIVIDE ESB	05/23/19	121.00	65.00	41.72	41.72
STR 141A-040	R5 YEAR 4 BRDG PREV MAINT RAM	R5 YEAR 4 BRDG PREV MAINT RAM	06/20/19	846.00	40.00	75.50	16.00
	WEIGHTED AVERAGE FOR THE SECOND QUARTER			6,610.30	37.22	28.62	21.61
	WEIGHTED AVERAGE FOR THE YEAR			8,252.30	36.64	41.58	28.63
=====	202-00212	Rem Conc Pavement (Spec)		Sq Yard	=====		
NH2871-035	US 287 PASSING LANES SOUTH OF	US 287 PASSING LANES SOUTH OF	02/07/19	13,726.00	10.00	22.17	12.39
	WEIGHTED AVERAGE FOR THE FIRST QUARTER			13,726.00	10.00	22.17	12.39
	WEIGHTED AVERAGE FOR THE YEAR			13,726.00	10.00	22.17	12.39

PROJECT NUMBER	ITEM NUMBER/ PROJECT LOCATION	ITEM DESCRIPTION/ PROJECT LOCATION	DATE LET	UNIT/ QUANTITY	ENGR. EST.	AVERAGE BID	AWARDED BID
=====	202-00217	Rem Conc Pvmt (Planing) (Spec)		Sq Yard	=====		
NHPPR100-250		PACKAGE A (I-25 / I-70 / I-76	01/24/19	2,225.00	35.00	38.25	33.00
		WEIGHTED AVERAGE FOR THE FIRST QUARTER		2,225.00	35.00	38.25	33.00
STR 141A-040		R5 YEAR 4 BRDG PREV MAINT RAM	06/20/19	865.00	45.00	52.50	20.00
		WEIGHTED AVERAGE FOR THE SECOND QUARTER		865.00	45.00	52.50	20.00
		WEIGHTED AVERAGE FOR THE YEAR		3,090.00	37.80	40.17	29.36
=====	202-00220	Rem Asphalt Mat		Sq Yard	=====		
FSA0142-068		SH 14 & WCR 33 INTERSECTION I	01/03/19	25.00	60.00	130.25	30.00
SHER100-289		INTERSECTIONS @ SH83 & LONGS	01/03/19	1,817.00	12.00	16.50	12.50
ER119A-065		PR SH 119A BOULDER CANYON	01/03/19	35,625.00	5.00	6.54	5.50
STA119A-069		SH 119: NEDERLAND - EAST					
FBR0341-087		US 34 OVER NORTH FORK CO RIVE	01/10/19	1,610.00	11.00	8.68	6.64
STR141A-047		SH 141 MP 120-143 MESA COUNTY	01/17/19	16,205.00	25.00	4.42	4.15
NHPP0701-241		I-70 TRUCK PARKING GARFIELD C	01/17/19	7,489.00	7.00	5.69	7.50
STR0241-062		US 24 143.4 - 148	01/24/19	4,307.00	9.00	12.90	8.00
ER072A-040		PR SH72A FLOOD PERMANENT REPA	01/31/19	13,690.00	14.00	13.18	7.00
NHPP072A-041		PR SH72A FLOOD PERMANENT REPA					
STAM086-075		SH96A ABRIENDO - ORMAN SAFETY	01/31/19	265.00	7.44	33.00	45.00
NHPP0821-107		SH 82 GLENWOOD SPRINGS TO CA	02/07/19	58.00	25.00	86.50	48.00
NH2871-035		US 287 PASSING LANES SOUTH OF	02/07/19	557.00	10.00	5.80	3.29
NHPP145A-065		SH 145 PASSING LANES AT DEEP	02/14/19	51.00	25.00	37.01	20.00
NHPP0741-022		SH 74: I-70 TO CR 65 RESURFAC	02/14/19	228.00	13.00	28.11	30.50
NHPP070A-028		FALL RIVER ROAD BRIDGE	02/21/19	3,260.00	15.00	8.46	8.50
SHER100-284		FY19 NORTH SIGNAL PKG	02/21/19	28.00	14.00	60.33	57.00
NHPP1601-073		US 160 PASSING LANE NORTH OF	03/07/19	8,161.00	12.00	6.50	4.00
FBR0253-247		I25 AT VINE DRIVE BRIDGE REPL	03/07/19	10,104.00	6.00	4.18	3.10
NHPP006A-058		US 6 LOVELAND PASS - I-70 (FY	03/07/19	60.00	5.00	46.93	58.85
C R100-315		R1 ADA CURB RAMPS - PH 5	03/07/19	466.00	22.00	34.00	30.00
NHPP0702-378		I-70 OFFICERS GULCH TO FRISCO	03/14/19	21.00	50.00	48.58	30.75
NHPP0503-087		US 50 PASSING LANES EAST OF S	03/21/19	10,149.00	2.00	7.50	8.00
SHE 0252-481		I-25 RAMP METER INSTALLATION	03/21/19	25.00	21.00	111.33	170.00
SHER100-308		MIDPOINT - SIGNAL CONST PACKA	03/21/19	600.00	10.00	37.50	41.00
STM0242-077		US24 - 8TH ST TO WEST OF MANI	03/28/19	2,764.00	15.38	13.00	15.00
		WEIGHTED AVERAGE FOR THE FIRST QUARTER		117,565.00	10.28	7.99	6.56
NHPP030A-035		US 285/SH30	04/04/19	5,380.00	16.00	15.00	15.00

PROJECT NUMBER	ITEM NUMBER/ PROJECT LOCATION	ITEM DESCRIPTION/ PROJECT LOCATION	DATE LET	UNIT/ QUANTITY	ENGR. EST.	AVERAGE BID	AWARDED BID
=====	202-00220	Rem Asphalt Mat		Sq Yard	=====	=====	=====
IM0252-472		I-25 CABLE BARRIER PHASE III	04/04/19	374.00	15.00	15.00	20.00
NHPP0703-445		I-70 WESTBOUND PEAK PERIOD SH	04/25/19	33,852.00	14.00	12.99	11.00
C2571-013		SH257 & 392:WINDSOR CURB RAMP	05/02/19	135.00	30.00	33.67	20.00
MTCE0641-103		MTCE R3 FY20 SH 64 RANGELY PE	05/02/19	297.00	30.00	24.25	20.00
FSA2873-190		US 287 AND FOOTHILLS PARKWAY	05/02/19	80.00	60.00	80.00	110.00
FSA0703-454		EB I-70 AUX LANE WARD TO KIPL	05/16/19	5,707.00	10.00	13.34	7.00
CR300-248		CRAIG RESIDENCY ADA RAMP	05/16/19	109.00	30.00	54.67	30.00
SHE0701-243		I-70 EXIT 26 DDI MODIFICATION	05/16/19	99.00	50.00	12.38	16.00
STMC430-020		ADA RAMP DIVIDE ESB	05/23/19	56.00	35.30	60.45	60.45
FBR0063-057		US-6 F-09-K BRIDGE OVER CASTL	05/30/19	1,461.00	6.00	11.25	13.00
NHPP0703-442		I-70 SILVERPLUME SOUNDWALL AN	06/13/19	356.00	12.00	34.96	28.00
NHPP030A-036		SH 30 & TOWER RD IMPROVEMENTS	06/13/19	1,134.00	12.00	15.00	15.00
		WEIGHTED AVERAGE FOR THE SECOND QUARTER		49,040.00	13.81	13.89	11.67
		WEIGHTED AVERAGE FOR THE YEAR		166,605.00	11.32	8.87	8.06
=====	202-00222	Removal of Detour Pavement		Sq Yard	=====	=====	=====
NHPP050A-033		US50 West of Delta EB Lanes R	03/14/19	2,030.00	20.00	18.27	14.80
		WEIGHTED AVERAGE FOR THE FIRST QUARTER		2,030.00	20.00	18.27	14.80
		WEIGHTED AVERAGE FOR THE YEAR		2,030.00	20.00	18.27	14.80
=====	202-00226	Rem of Asph Mat (Special)		Sq Yard	=====	=====	=====
STAM086-075		SH96A ABRIENDO - ORMAN SAFETY	01/31/19	457.00	5.80	43.67	45.00
SHE2254-090		Colfax & I-225, Colfax & Cham	03/07/19	2,258.00	20.00	27.50	24.00
		WEIGHTED AVERAGE FOR THE FIRST QUARTER		2,715.00	17.61	31.26	27.53
		WEIGHTED AVERAGE FOR THE YEAR		2,715.00	17.61	31.26	27.53
=====	202-00240	Rem Asphalt Mat (Planing)		Sq Yard	=====	=====	=====
IM0251-351		I-25 South of Pueblo MP 79.6	01/03/19	282,404.00	1.50	1.81	1.32
FSA0142-068		SH 14 & WCR 33 INTERSECTION I	01/03/19	1,788.00	7.50	5.88	4.50
ER119A-065		PR SH 119A BOULDER CANYON	01/03/19	17,019.00	3.50	3.22	4.00
STA119A-069		SH 119: NEDERLAND - EAST					
STR0132-021		SH 13-MOFFAT COUNTY-CR 3 SOUT	01/10/19	970.00	10.00	9.60	18.00
FBR0341-087		US 34 OVER NORTH FORK CO RIVE	01/10/19	1,865.00	5.50	4.94	4.88

PROJECT NUMBER	ITEM NUMBER/ PROJECT LOCATION	ITEM DESCRIPTION/ PROJECT LOCATION	DATE LET	UNIT/ QUANTITY	ENGR. EST.	AVERAGE BID	AWARDED BID
===== 202-00240		Rem Asphalt Mat (Planing)		Sq Yard	=====	=====	=====
STR141A-047		SH 141 MP 120-143 MESA COUNTY	01/17/19	858.00	3.00	12.12	7.15
STR0241-062		US 24 143.4 - 148	01/24/19	80,947.00	3.00	4.78	3.00
STAM086-075		SH96A ABRIENDO - ORMAN SAFETY	01/31/19	229.00	4.00	103.25	34.75
STA067A-038		SH 67 SEDALIA RESURFACING	01/31/19	31,926.00	2.00	1.85	1.50
NHPP0821-107		SH 82 GLENWOOD SPRINGS TO CA	02/07/19	263,797.00	2.40	1.45	1.25
NHPP145A-065		SH 145 PASSING LANES AT DEEP	02/14/19	12,492.00	15.00	3.20	3.00
NHPP0741-022		SH 74: I-70 TO CR 65 RESURFAC	02/14/19	113,445.00	4.00	2.76	1.54
NHPP070A-028		FALL RIVER ROAD BRIDGE	02/21/19	1,004.00	4.00	5.81	4.40
NHPP1601-073		US 160 PASSING LANE NORTH OF	03/07/19	414.00	5.00	21.70	21.40
NHPP006A-058		US 6 LOVELAND PASS - I-70 (FY	03/07/19	213,002.00	4.00	2.18	1.56
NHPP0702-378		I-70 OFFICERS GULCH TO FRISCO	03/14/19	196,965.00	2.50	3.14	1.82
NHPP050A-033		US50 West of Delta EB Lanes R	03/14/19	120,424.00	1.50	2.30	2.05
NHPP0503-087		US 50 PASSING LANES EAST OF S	03/21/19	11,923.00	3.00	4.25	5.00
SHER100-308		MIDPOINT - SIGNAL CONST PACKA	03/21/19	1,087.00	30.00	7.50	10.00
NHPP2254-089		I-225 RESURFACING FROM I-25 T	03/21/19	344,279.00	2.50	2.57	3.00
STM0242-077		US24 - 8TH ST TO WEST OF MANI	03/28/19	270,620.00	1.80	2.93	2.00
STA0131-070 HMA ALT		SH 13 CR 5 NORTH AND SOUTH	03/28/19	2,400.00	3.00	8.97	7.30
STA0131-070 PCCP ALT		SH 13 CR 5 NORTH AND SOUTH					
		WEIGHTED AVERAGE FOR THE FIRST QUARTER		1,969,858.00	2.57	2.56	1.99
NHPP030A-035		US 285/SH30	04/04/19	215,242.20	3.00	1.60	1.60
BR071A-020		REPLACEMENT OF STRUCTURE L-22	04/18/19	2,241.00	4.00	12.12	6.60
NHPP0703-445		I-70 WESTBOUND PEAK PERIOD SH	04/25/19	284,570.00	3.50	2.50	3.00
FBR0063-057		US-6 F-09-K BRIDGE OVER CASTL	05/30/19	50.00	3.00	50.20	72.00
ER145A-081		SH 145 MP 21 EMERGENCY ROCKFA	06/07/19	1,368.00	5.00	20.96	26.00
NHPP030A-036		SH 30 & TOWER RD IMPROVEMENTS	06/13/19	499.00	16.00	10.00	10.00
STR 141A-040		R5 YEAR 4 BRDG PREV MAINT RAM	06/20/19	206.00	15.00	47.50	50.00
		WEIGHTED AVERAGE FOR THE SECOND QUARTER		504,176.20	3.31	2.45	2.51
				=====	=====	=====	=====
		WEIGHTED AVERAGE FOR THE YEAR		2,474,034.20	2.72	2.54	2.10
===== 202-00246		Rem Asphalt Mat (Planing) (Special)		Sq Yard	=====	=====	=====
IM0251-351		I-25 South of Pueblo MP 79.6	01/03/19	345.00	18.00	25.87	25.09
ER119A-065		PR SH 119A BOULDER CANYON	01/03/19	778.00	5.00	31.53	45.00
STA119A-069		SH 119: NEDERLAND - EAST					
NHPPR100-250		PACKAGE A (I-25 / I-70 / I-76	01/24/19	3,509.00	15.00	19.89	17.00
STA067A-038		SH 67 SEDALIA RESURFACING	01/31/19	1,198.00	15.00	8.64	13.00
NHPP0741-022		SH 74: I-70 TO CR 65 RESURFAC	02/14/19	1,162.00	20.00	13.26	16.00
NHPP0702-378		I-70 OFFICERS GULCH TO FRISCO	03/14/19	59.00	40.00	109.20	82.61
NHPP2254-089		I-225 RESURFACING FROM I-25 T	03/21/19	4,148.00	20.00	10.66	10.00

COLORADO DEPARTMENT OF TRANSPORTATION
 ITEM UNIT COSTS BY PROJECTS -- 2019 COST DATA

13:44 Wednesday, August 7, 2019 19

PROJECT NUMBER	ITEM NUMBER/ PROJECT LOCATION	ITEM DESCRIPTION/ PROJECT LOCATION	DATE LET	UNIT/ QUANTITY	ENGR. EST.	AVERAGE BID	AWARDED BID
=====	202-00246	Rem Asphalt Mat (Planing) (Special)		Sq Yard	=====	=====	=====
STM0242-077		US24 - 8TH ST TO WEST OF MANI	03/28/19	6,126.00	21.75	12.00	12.00
		WEIGHTED AVERAGE FOR THE FIRST QUARTER		17,325.00	18.61	16.25	14.85
NHPP2851-012		US 285 Antonito to Estrella C	05/02/19	40,550.00	5.00	2.15	1.76
STR 141A-040		R5 YEAR 4 BRDG PREV MAINT RAM	06/20/19	2,475.00	20.00	21.50	20.00
		WEIGHTED AVERAGE FOR THE SECOND QUARTER		43,025.00	5.86	2.91	2.81
		WEIGHTED AVERAGE FOR THE YEAR		60,350.00	9.52	7.41	6.27
=====	202-00250	Rem Pavement Marking		Sq Foot	=====	=====	=====
IM0251-351		I-25 South of Pueblo MP 79.6	01/03/19	5,000.00	1.00	1.50	1.63
NHPPR500-173		US 160_550 DURANGO SIGNALS OP	01/03/19	172.00	5.00	5.00	4.00
SHER100-289		INTERSECTIONS @ SH83 & LONGS	01/03/19	2,100.00	1.50	1.50	1.30
STR0132-021		SH 13-MOFFAT COUNTY-CR 3 SOUT	01/10/19	35,472.00	1.75	1.03	0.80
FBR0341-087		US 34 OVER NORTH FORK CO RIVE	01/10/19	2,160.00	3.00	2.59	2.08
MTCER300-247		MTCE R3 FY19 REGION ROUNDABOU	01/10/19	17,200.00	5.00	3.71	2.25
NHPP0701-241		I-70 TRUCK PARKING GARFIELD C	01/17/19	4,499.00	0.58	2.89	3.25
STR0241-062		US 24 143.4 - 148	01/24/19	29,089.00	1.50	0.83	1.00
ER072A-040		PR SH72A FLOOD PERMANENT REPA	01/31/19	11,000.00	1.00	1.88	2.00
NHPP072A-041		PR SH72A FLOOD PERMANENT REPA					
STAM086-075		SH96A ABRIENDO - ORMAN SAFETY	01/31/19	1,360.00	0.66	2.67	2.52
STA067A-038		SH 67 SEDALIA RESURFACING	01/31/19	11,000.00	1.00	1.03	0.44
NHPP0821-107		SH 82 GLENWOOD SPRINGS TO CA	02/07/19	187,601.00	0.58	0.64	0.53
NH2871-035		US 287 PASSING LANES SOUTH OF	02/07/19	14,295.00	2.00	1.43	1.00
NHPP145A-065		SH 145 PASSING LANES AT DEEP	02/14/19	17,068.00	2.00	1.69	1.75
NHPP0741-022		SH 74: I-70 TO CR 65 RESURFAC	02/14/19	100.00	2.50	2.35	2.20
NHPP1601-076		US 160 MANCOS HILL (MP 40.000	02/21/19	92.00	5.00	5.89	6.00
NHPP070A-028		FALL RIVER ROAD BRIDGE	02/21/19	50.00	10.00	5.51	5.50
MPR200-253		R2 FY19 STENCIL PVMT MKG PROJ	03/07/19	500.00	2.50	4.92	2.75
C R100-315		R1 ADA CURB RAMPS - PH 5	03/07/19	74.00	2.50	6.50	5.00
SHE2254-090		Colfax & I-225, Colfax & Cham	03/07/19	6,852.00	1.50	2.25	2.50
NHPP0702-378		I-70 OFFICERS GULCH TO FRISCO	03/14/19	34,581.00	1.00	0.99	0.61
NHPP050A-033		US50 West of Delta EB Lanes R	03/14/19	30,463.00	1.50	0.68	0.60
SHE 0252-481		I-25 RAMP METER INSTALLATION	03/21/19	1,355.00	1.00	4.05	4.50
SHER100-308		MIDPOINT - SIGNAL CONST PACKA	03/21/19	3,245.00	2.00	3.00	3.50
NHPP2254-089		I-225 RESURFACING FROM I-25 T	03/21/19	52,500.00	1.00	0.61	0.55
STM0242-077		US24 - 8TH ST TO WEST OF MANI	03/28/19	176,929.00	0.56	0.56	0.52
STA0131-070 HMA ALT		SH 13 CR 5 NORTH AND SOUTH	03/28/19	88,340.00	1.00	0.89	0.85
STA0131-070 PCCP ALT		SH 13 CR 5 NORTH AND SOUTH					
		WEIGHTED AVERAGE FOR THE FIRST QUARTER		733,097.00	1.02	1.03	0.78

PROJECT NUMBER	ITEM NUMBER/ PROJECT LOCATION	ITEM DESCRIPTION/ PROJECT LOCATION	DATE LET	UNIT/ QUANTITY	ENGR. EST.	AVERAGE BID	AWARDED BID
===== 202-00250		Rem Pavement Marking		Sq Foot	=====		
NHPP030A-035		US 285/SH30	04/04/19	10,000.00	0.76	0.95	0.95
STRR300-236		SH 92 and SH 133	04/04/19	231,960.00	0.75	0.60	0.60
MTCER300-252		MTCE R3 FY19/20 REGION WIDE E	04/04/19	919,483.00	0.42	0.46	0.50
BR071A-020		REPLACEMENT OF STRUCTURE L-22	04/18/19	599.00	1.00	2.93	2.20
FSA0252-468		I-25 AND PLUM CREEK IMPROVEME	04/18/19	6,600.00	1.00	1.75	1.48
MTCER300-253		MTCE R3 FY19/20 REGION WIDE S	04/18/19	1,497.00	1.00	2.38	2.75
NHPP0703-445		I-70 WESTBOUND PEAK PERIOD SH	04/25/19	48,000.00	1.00	0.98	1.10
NHPP2851-012		US 285 Antonito to Estrella C	05/02/19	1,558.00	0.75	4.25	6.00
C2571-013		SH257 & 392:WINDSOR CURB RAMP	05/02/19	851.00	5.00	3.67	3.00
MTCE0641-103		MTCE R3 FY20 SH 64 RANGELY PE	05/02/19	1,160.00	4.00	3.88	5.00
FSA2873-190		US 287 AND FOOTHILLS PARKWAY	05/02/19	324.00	6.00	4.50	5.00
FSA0703-454		EB I-70 AUX LANE WARD TO KIPL	05/16/19	5,325.00	0.80	2.99	1.85
CR300-248		CRAIG RESIDENCY ADA RAMPS	05/16/19	308.00	4.50	3.17	3.00
SHE0701-243		I-70 EXIT 26 DDI MODIFICATION	05/16/19	994.00	6.00	3.90	4.00
STMC430-020		ADA RAMPS DIVIDE ESB	05/23/19	53.00	50.00	37.76	37.76
FBR0063-057		US-6 F-09-K BRIDGE OVER CASTL	05/30/19	1,316.00	1.00	2.88	3.00
MPR200-255		FY20 R2 PAVEMENT MARKING PROJ	06/06/19	5,857.00	0.50	0.88	0.60
NHPP0703-442		I-70 SILVERPLUME SOUNDWALL AN	06/13/19	210.00	1.50	6.21	5.80
NHPP030A-036		SH 30 & TOWER RD IMPROVEMENTS	06/13/19	2,630.00	1.50	2.00	2.00
STR 141A-040		R5 YEAR 4 BRDG PREV MAINT RAM	06/20/19	3,510.00	2.50	3.00	3.00
		WEIGHTED AVERAGE FOR THE SECOND QUARTER		1,242,235.00	0.54	0.55	0.59
		WEIGHTED AVERAGE FOR THE YEAR		1,975,332.00	0.72	0.75	0.66
===== 202-00251		Rem Pvmt Marking (Asph Grooving)		Sq Foot	=====		
MPR200-255		FY20 R2 PAVEMENT MARKING PROJ	06/06/19	583,853.00	0.80	0.57	0.60
		WEIGHTED AVERAGE FOR THE SECOND QUARTER		583,853.00	0.80	0.57	0.60
		WEIGHTED AVERAGE FOR THE YEAR		583,853.00	0.80	0.57	0.60
===== 202-00252		Rem Pvmt Marking (Conc Grooving)		Sq Foot	=====		
MPR200-255		FY20 R2 PAVEMENT MARKING PROJ	06/06/19	789,347.00	0.90	0.70	0.60
		WEIGHTED AVERAGE FOR THE SECOND QUARTER		789,347.00	0.90	0.70	0.60
		WEIGHTED AVERAGE FOR THE YEAR		789,347.00	0.90	0.70	0.60

COLORADO DEPARTMENT OF TRANSPORTATION
ITEM UNIT COSTS BY PROJECTS -- 2019 COST DATA

13:44 Wednesday, August 7, 2019 21

PROJECT NUMBER	ITEM NUMBER/ PROJECT LOCATION	ITEM DESCRIPTION/ PROJECT LOCATION	DATE LET	UNIT/ QUANTITY	ENGR. EST.	AVERAGE BID	AWARDED BID
=====	202-00254	Rem of Pvmt Mkg (12 In)		Sq Foot	=====		
SHER100-289		INTERSECTIONS @ SH83 & LONGS	01/03/19	2,000.00	1.00	1.50	1.30
	WEIGHTED	AVERAGE FOR THE FIRST QUARTER		2,000.00	1.00	1.50	1.30
		WEIGHTED AVERAGE FOR THE YEAR		2,000.00	1.00	1.50	1.30
=====	202-00256	Rem of Pvmt Mkg (15 In)		Sq Foot	=====		
NHPP2254-089		I-225 RESURFACING FROM I-25 T	03/21/19	3,500.00	1.50	0.61	0.55
	WEIGHTED	AVERAGE FOR THE FIRST QUARTER		3,500.00	1.50	0.61	0.55
		WEIGHTED AVERAGE FOR THE YEAR		3,500.00	1.50	0.61	0.55
=====	202-00260	Rem of Pvmt Mkg (On-Call)		Sq Foot	=====		
NHPP030A-035		US 285/SH30	04/04/19	730.20	1.00	0.95	0.95
MTCER300-252		MTCE R3 FY19/20 REGION WIDE E	04/04/19	74,000.00	0.42	0.63	0.65
	WEIGHTED	AVERAGE FOR THE SECOND QUARTER		74,730.20	0.43	0.63	0.65
		WEIGHTED AVERAGE FOR THE YEAR		74,730.20	0.43	0.63	0.65
=====	202-00400	Rem Bridge		Each	=====		
FBR0341-087		US 34 OVER NORTH FORK CO RIVE	01/10/19	1.00	50000.00	132068.64	133311.84
FBR0253-247		I25 AT VINE DRIVE BRIDGE REPL	03/07/19	1.00	70000.00	133001.93	200000.00
	WEIGHTED	AVERAGE FOR THE FIRST QUARTER		2.00	60000.00	132672.53	166655.92
BR071A-020		REPLACEMENT OF STRUCTURE L-22	04/18/19	1.00	30000.00	78166.67	46000.00
FBR0063-057		US-6 F-09-K BRIDGE OVER CASTL	05/30/19	1.00	60000.00	43500.00	41000.00
	WEIGHTED	AVERAGE FOR THE SECOND QUARTER		2.00	45000.00	64300.00	43500.00
		WEIGHTED AVERAGE FOR THE YEAR		4.00	52500.00	117133.32	105077.96
=====	202-00410	Rem Mat From Br		Sq Yard	=====		
SHE2254-090		Colfax & I-225, Colfax & Cham	03/07/19	184.00	25.00	30.00	25.00
	WEIGHTED	AVERAGE FOR THE FIRST QUARTER		184.00	25.00	30.00	25.00
		WEIGHTED AVERAGE FOR THE YEAR		184.00	25.00	30.00	25.00

COLORADO DEPARTMENT OF TRANSPORTATION
ITEM UNIT COSTS BY PROJECTS -- 2019 COST DATA

13:44 Wednesday, August 7, 2019 22

PROJECT NUMBER	ITEM NUMBER/ PROJECT LOCATION	ITEM DESCRIPTION/ PROJECT LOCATION	DATE LET	UNIT/ QUANTITY	ENGR. EST.	AVERAGE BID	AWARDED BID
===== 202-00425		Rem Bridge Railing		Lin Foot	=====		
STR141A-047		SH 141 MP 120-143 MESA COUNTY	01/17/19	380.00	45.00	26.83	28.35
NHPPR100-250		PACKAGE A (I-25 / I-70 / I-76	01/24/19	16.00	50.00	177.51	180.00
STA067A-038		SH 67 SEDALIA RESURFACING	01/31/19	142.00	65.00	39.28	20.00
NHPP0702-378		I-70 OFFICERS GULCH TO FRISCO	03/14/19	627.00	50.00	26.40	20.19
STM0242-077		US24 - 8TH ST TO WEST OF MANI	03/28/19	2,626.00	48.81	25.67	8.00
		WEIGHTED AVERAGE FOR THE FIRST QUARTER		3,791.00	49.24	27.46	13.23
		WEIGHTED AVERAGE FOR THE YEAR		3,791.00	49.24	27.46	13.23
===== 202-00450		Rem Port Present Str (1)		Sq Yard	=====		
NHPPR100-250		PACKAGE A (I-25 / I-70 / I-76	01/24/19	321.00	80.00	137.62	110.00
		WEIGHTED AVERAGE FOR THE FIRST QUARTER		321.00	80.00	137.62	110.00
STR 141A-040		R5 YEAR 4 BRDG PREV MAINT RAM	06/20/19	118.00	120.00	215.00	200.00
		WEIGHTED AVERAGE FOR THE SECOND QUARTER		118.00	120.00	215.00	200.00
		WEIGHTED AVERAGE FOR THE YEAR		439.00	90.75	147.54	134.19
===== 202-00453		Rem Port Present Str (2)		Sq Yard	=====		
IM0251-351		I-25 South of Pueblo MP 79.6	01/03/19	17.00	300.00	412.82	394.21
ER119A-065		PR SH 119A BOULDER CANYON	01/03/19	16.00	300.00	1465.70	250.00
STA119A-069		SH 119: NEDERLAND - EAST					
NHPPR100-250		PACKAGE A (I-25 / I-70 / I-76	01/24/19	133.00	300.00	259.69	175.00
STA067A-038		SH 67 SEDALIA RESURFACING	01/31/19	139.00	350.00	260.34	320.00
NHPP0741-022		SH 74: I-70 TO CR 65 RESURFAC	02/14/19	59.00	350.00	273.57	260.00
NHPP0702-378		I-70 OFFICERS GULCH TO FRISCO	03/14/19	3.00	280.00	663.33	1025.00
NHPP2254-089		I-225 RESURFACING FROM I-25 T	03/21/19	209.00	280.00	315.63	295.00
STM0242-077		US24 - 8TH ST TO WEST OF MANI	03/28/19	461.00	227.60	263.33	350.00
		WEIGHTED AVERAGE FOR THE FIRST QUARTER		1,037.00	273.27	319.72	308.46
STR 141A-040		R5 YEAR 4 BRDG PREV MAINT RAM	06/20/19	37.00	300.00	500.00	650.00
		WEIGHTED AVERAGE FOR THE SECOND QUARTER		37.00	300.00	500.00	650.00
		WEIGHTED AVERAGE FOR THE YEAR		1,074.00	274.19	323.42	320.23

COLORADO DEPARTMENT OF TRANSPORTATION
ITEM UNIT COSTS BY PROJECTS -- 2019 COST DATA

13:44 Wednesday, August 7, 2019 23

PROJECT NUMBER	ITEM NUMBER/ PROJECT LOCATION	ITEM DESCRIPTION/ PROJECT LOCATION	DATE LET	UNIT/ QUANTITY	ENGR. EST.	AVERAGE BID	AWARDED BID
===== 202-00460		Rem Port Present Str (3)		Sq Yard	=====		
IM0251-351		I-25 South of Pueblo MP 79.6	01/03/19	2.00	600.00	1645.77	1407.88
ER119A-065		PR SH 119A BOULDER CANYON	01/03/19	4.00	400.00	2433.80	1000.00
STA119A-069		SH 119: NEDERLAND - EAST					
NHPPR100-250		PACKAGE A (I-25 / I-70 / I-76	01/24/19	18.00	600.00	627.95	325.00
STA067A-038		SH 67 SEDALIA RESURFACING	01/31/19	69.00	600.00	411.13	500.00
NHPP0741-022		SH 74: I-70 TO CR 65 RESURFAC	02/14/19	12.00	700.00	574.22	435.00
NHPP0702-378		I-70 OFFICERS GULCH TO FRISCO	03/14/19	14.00	475.00	736.67	1025.00
NHPP2254-089		I-225 RESURFACING FROM I-25 T	03/21/19	22.00	500.00	570.93	480.00
STM0242-077		US24 - 8TH ST TO WEST OF MANI	03/28/19	30.00	479.17	753.33	1000.00
		WEIGHTED AVERAGE FOR THE FIRST QUARTER		171.00	558.04	680.36	627.46
STR 141A-040		R5 YEAR 4 BRDG PREV MAINT RAM	06/20/19	8.00	500.00	1025.00	1400.00
		WEIGHTED AVERAGE FOR THE SECOND QUARTER		8.00	500.00	1025.00	1400.00
		WEIGHTED AVERAGE FOR THE YEAR		179.00	555.45	689.57	661.99
===== 202-00495		Rem Port Present Str		LUMP SUM	=====		
NHPP0703-445		I-70 WESTBOUND PEAK PERIOD SH	04/25/19	1.00	5000.00	10503.79	11155.00
STR 141A-040		R5 YEAR 4 BRDG PREV MAINT RAM	06/20/19	1.00	30000.00	39500.00	15000.00
		WEIGHTED AVERAGE FOR THE SECOND QUARTER		2.00	17500.00	22102.27	13077.50
		WEIGHTED AVERAGE FOR THE YEAR		2.00	17500.00	22102.27	13077.50
===== 202-00500		Rem Port Present Str		Each	=====		
ER119A-065		PR SH 119A BOULDER CANYON	01/03/19	1.00	10000.00	12703.78	9000.00
STA119A-069		SH 119: NEDERLAND - EAST					
		WEIGHTED AVERAGE FOR THE FIRST QUARTER		1.00	10000.00	12703.78	9000.00
NHPP0703-445		I-70 WESTBOUND PEAK PERIOD SH	04/25/19	1.00	1000.00	5872.44	6475.00
		WEIGHTED AVERAGE FOR THE SECOND QUARTER		1.00	1000.00	5872.44	6475.00
		WEIGHTED AVERAGE FOR THE YEAR		2.00	5500.00	10840.69	7737.50

COLORADO DEPARTMENT OF TRANSPORTATION
 ITEM UNIT COSTS BY PROJECTS -- 2019 COST DATA

13:44 Wednesday, August 7, 2019 24

PROJECT NUMBER	ITEM NUMBER/ PROJECT LOCATION	ITEM DESCRIPTION/ PROJECT LOCATION	DATE LET	UNIT/ QUANTITY	ENGR. EST.	AVERAGE BID	AWARDED BID
===== 202-00502		Rem Port Present Str		Cubic Yard	=====		
STM0242-077		US24 - 8TH ST TO WEST OF MANI	03/28/19	23.00	1500.00	1183.33	950.00
		WEIGHTED AVERAGE FOR THE FIRST QUARTER		23.00	1500.00	1183.33	950.00
STR 141A-040		R5 YEAR 4 BRDG PREV MAINT RAM	06/20/19	1.00	2500.00	26500.00	15000.00
		WEIGHTED AVERAGE FOR THE SECOND QUARTER		1.00	2500.00	26500.00	15000.00
		WEIGHTED AVERAGE FOR THE YEAR		24.00	1541.67	1896.48	1535.42
===== 202-00503		Rem Port Present Str		Sq Yard	=====		
NHPPR100-250		PACKAGE A (I-25 / I-70 / I-76	01/24/19	66.00	900.00	945.98	1270.00
NHPP0702-378		I-70 OFFICERS GULCH TO FRISCO	03/14/19	77.00	500.00	370.83	512.50
		WEIGHTED AVERAGE FOR THE FIRST QUARTER		143.00	684.62	709.15	862.12
NHPP160A-030		US160 MM 43.2, 150.4, 156.3,	06/20/19	6.00	800.00	1875.00	1500.00
		WEIGHTED AVERAGE FOR THE SECOND QUARTER		6.00	800.00	1875.00	1500.00
		WEIGHTED AVERAGE FOR THE YEAR		149.00	689.26	733.57	887.80
===== 202-00504		Rem Exp Device		Lin Foot	=====		
NHPPR100-250		PACKAGE A (I-25 / I-70 / I-76	01/24/19	203.00	280.00	258.11	222.00
NHPP0741-022		SH 74: I-70 TO CR 65 RESURFAC	02/14/19	228.00	300.00	227.65	195.50
		WEIGHTED AVERAGE FOR THE FIRST QUARTER		431.00	290.58	243.69	207.98
NHPP030A-035		US 285/SH30	04/04/19	328.00	250.00	100.00	100.00
STR 141A-040		R5 YEAR 4 BRDG PREV MAINT RAM	06/20/19	174.00	250.00	290.00	170.00
		WEIGHTED AVERAGE FOR THE SECOND QUARTER		502.00	250.00	197.81	124.26
		WEIGHTED AVERAGE FOR THE YEAR		933.00	268.75	231.78	162.94

COLORADO DEPARTMENT OF TRANSPORTATION
 ITEM UNIT COSTS BY PROJECTS -- 2019 COST DATA

13:44 Wednesday, August 7, 2019 25

PROJECT NUMBER	ITEM NUMBER/ PROJECT LOCATION	ITEM DESCRIPTION/ PROJECT LOCATION	DATE LET	UNIT/ QUANTITY	ENGR. EST.	AVERAGE BID	AWARDED BID
===== 202-00505		Rem Port of Present Structure		Sq Foot	=====		
IM0251-351		I-25 South of Pueblo MP 79.6	01/03/19	292.00	45.00	260.92	259.05
NHPP0741-022		SH 74: I-70 TO CR 65 RESURFAC	02/14/19	100.00	60.00	261.86	230.00
	WEIGHTED AVERAGE FOR THE FIRST QUARTER			392.00	48.83	261.16	251.64
	WEIGHTED AVERAGE FOR THE YEAR			392.00	48.83	261.16	251.64
===== 202-00520		Rem of Exp Joint Matl		Lin Foot	=====		
NHPP0702-378		I-70 OFFICERS GULCH TO FRISCO	03/14/19	168.00	12.50	28.50	20.50
	WEIGHTED AVERAGE FOR THE FIRST QUARTER			168.00	12.50	28.50	20.50
	WEIGHTED AVERAGE FOR THE YEAR			168.00	12.50	28.50	20.50
===== 202-00700		Rem Light Standard		Each	=====		
ITSSW01-638		ETHERNET PHASE III (PRIMARYLY	02/07/19	1.00	600.00	600.00	500.00
NHPP070A-028		FALL RIVER ROAD BRIDGE	02/21/19	1.00	210.00	1641.60	1100.00
	WEIGHTED AVERAGE FOR THE FIRST QUARTER			2.00	405.00	1344.00	800.00
FSA0252-468		I-25 AND PLUM CREEK IMPROVEME	04/18/19	2.00	600.00	339.25	621.00
	WEIGHTED AVERAGE FOR THE SECOND QUARTER			2.00	600.00	339.25	621.00
	WEIGHTED AVERAGE FOR THE YEAR			4.00	502.50	808.13	710.50
===== 202-00705		Rem Light Standard Foundation		Each	=====		
ITSSW01-638		ETHERNET PHASE III (PRIMARYLY	02/07/19	1.00	600.00	750.00	500.00
NHPP070A-028		FALL RIVER ROAD BRIDGE	02/21/19	1.00	1000.00	1251.00	1100.00
	WEIGHTED AVERAGE FOR THE FIRST QUARTER			2.00	800.00	1107.86	800.00
FSA0252-468		I-25 AND PLUM CREEK IMPROVEME	04/18/19	3.00	850.00	569.25	582.00

COLORADO DEPARTMENT OF TRANSPORTATION
 ITEM UNIT COSTS BY PROJECTS -- 2019 COST DATA

13:44 Wednesday, August 7, 2019 26

PROJECT NUMBER	ITEM NUMBER/ PROJECT LOCATION	ITEM DESCRIPTION/ PROJECT LOCATION	DATE LET	UNIT/ QUANTITY	ENGR. EST.	AVERAGE BID	AWARDED BID
=====	202-00705	Rem Light Standard Foundation		Each =====			
NHPP0703-445		I-70 WESTBOUND PEAK PERIOD SH	04/25/19	13.00	750.00	980.29	1032.00
FSA0703-454		EB I-70 AUX LANE WARD TO KIPL	05/16/19	3.00	900.00	1016.48	750.00
SHE0701-243		I-70 EXIT 26 DDI MODIFICATION	05/16/19	4.00	700.00	575.00	500.00
	WEIGHTED AVERAGE FOR THE SECOND QUARTER			23.00	773.91	834.35	844.00
	WEIGHTED AVERAGE FOR THE YEAR			25.00	776.00	857.42	840.48
=====	202-00715	Rem CCTV Pole		Each =====			
ITSSW01-638		ETHERNET PHASE III (PRIMARYLY	02/07/19	12.00	600.00	1560.00	500.00
	WEIGHTED AVERAGE FOR THE FIRST QUARTER			12.00	600.00	1560.00	500.00
NHPP0703-445		I-70 WESTBOUND PEAK PERIOD SH	04/25/19	2.00	500.00	2727.40	2865.00
	WEIGHTED AVERAGE FOR THE SECOND QUARTER			2.00	500.00	2727.40	2865.00
	WEIGHTED AVERAGE FOR THE YEAR			14.00	585.71	1793.48	837.86
=====	202-00720	Rem CCTV Camera		Each =====			
ITSSW01-638		ETHERNET PHASE III (PRIMARYLY	02/07/19	22.00	650.00	447.50	500.00
	WEIGHTED AVERAGE FOR THE FIRST QUARTER			22.00	650.00	447.50	500.00
	WEIGHTED AVERAGE FOR THE YEAR			22.00	650.00	447.50	500.00
=====	202-00750	Rem Luminaire		Each =====			
STR0241-062		US 24 143.4 - 148	01/24/19	1.00	100.00	648.33	240.00
NHPP2254-089		I-225 RESURFACING FROM I-25 T	03/21/19	6.00	200.00	278.77	150.00
	WEIGHTED AVERAGE FOR THE FIRST QUARTER			7.00	185.71	331.56	162.86
	WEIGHTED AVERAGE FOR THE YEAR			7.00	185.71	331.56	162.86
=====	202-00805	Rem Overhead Sign Str		Each =====			
NHPP0703-445		I-70 WESTBOUND PEAK PERIOD SH	04/25/19	1.00	5500.00	5229.57	2373.00

PROJECT NUMBER	ITEM NUMBER/ PROJECT LOCATION	ITEM DESCRIPTION/ PROJECT LOCATION	DATE LET	UNIT/ QUANTITY	ENGR. EST.	AVERAGE BID	AWARDED BID
===== 202-00805	Rem Overhead Sign Str			Each =====			
SHE0701-243	I-70 EXIT 26 DDI MODIFICATION	05/16/19		1.00	5000.00	5712.50	6350.00
	WEIGHTED AVERAGE FOR THE SECOND QUARTER			2.00	5250.00	5505.53	4361.50
	WEIGHTED AVERAGE FOR THE YEAR			2.00	5250.00	5505.53	4361.50
===== 202-00806	Rem Walkway			Lin Foot =====			
NHPP2254-089	I-225 RESURFACING FROM I-25 T	03/21/19		72.00	7.00	84.36	105.00
	WEIGHTED AVERAGE FOR THE FIRST QUARTER			72.00	7.00	84.36	105.00
	WEIGHTED AVERAGE FOR THE YEAR			72.00	7.00	84.36	105.00
===== 202-00810	Rem Ground Sign			Each =====			
NHPPR500-173	US 160_550 DURANGO SIGNALS OP	01/03/19		2.00	200.00	321.00	367.00
FSA0142-068	SH 14 & WCR 33 INTERSECTION I	01/03/19		2.00	200.00	127.50	60.00
SHER100-289	INTERSECTIONS @ SH83 & LONGS	01/03/19		13.00	150.00	145.60	130.00
ER119A-065	PR SH 119A BOULDER CANYON	01/03/19		339.00	45.00	86.18	56.00
STA119A-069	SH 119: NEDERLAND - EAST						
STR0132-021	SH 13-MOFFAT COUNTY-CR 3 SOUT	01/10/19		6.00	100.00	161.80	152.00
FBR0341-087	US 34 OVER NORTH FORK CO RIVE	01/10/19		6.00	60.00	103.31	78.45
NHPP0701-241	I-70 TRUCK PARKING GARFIELD C	01/17/19		1.00	150.00	177.46	235.00
STR0241-062	US 24 143.4 - 148	01/24/19		3.00	100.00	135.67	140.00
ER072A-040	PR SH72A FLOOD PERMANENT REPA	01/31/19		8.00	150.00	89.38	57.00
NHPP072A-041	PR SH72A FLOOD PERMANENT REPA						
STA067A-038	SH 67 SEDALIA RESURFACING	01/31/19		4.00	160.00	267.51	100.00
NHPP0821-107	SH 82 GLENWOOD SPRINGS TO CA	02/07/19		6.00	150.00	102.00	79.00
NH2871-035	US 287 PASSING LANES SOUTH OF	02/07/19		2.00	100.00	114.04	78.75
NHPP145A-065	SH 145 PASSING LANES AT DEEP	02/14/19		2.00	60.00	174.25	150.00
NHPP0741-022	SH 74: I-70 TO CR 65 RESURFAC	02/14/19		3.00	150.00	166.97	162.80
NHPP070A-028	FALL RIVER ROAD BRIDGE	02/21/19		6.00	150.00	147.64	160.00
NHPP1601-073	US 160 PASSING LANE NORTH OF	03/07/19		2.00	400.00	225.00	300.00
FBR0253-247	I25 AT VINE DRIVE BRIDGE REPL	03/07/19		8.00	100.00	65.77	55.00
SHE2254-090	Colfax & I-225, Colfax & Cham	03/07/19		2.00	125.00	112.50	130.00
NHPP0503-087	US 50 PASSING LANES EAST OF S	03/21/19		17.00	70.00	87.50	100.00
STM0242-077	US24 - 8TH ST TO WEST OF MANI	03/28/19		15.00	93.36	78.33	65.00
STA0131-070 HMA ALT	SH 13 CR 5 NORTH AND SOUTH	03/28/19		40.00	120.00	106.94	90.90
STA0131-070 PCCP ALT	SH 13 CR 5 NORTH AND SOUTH						
	WEIGHTED AVERAGE FOR THE FIRST QUARTER			487.00	67.90	91.13	69.80
NHPP030A-035	US 285/SH30	04/04/19		10.00	100.00	65.00	65.00

COLORADO DEPARTMENT OF TRANSPORTATION
 ITEM UNIT COSTS BY PROJECTS -- 2019 COST DATA

13:44 Wednesday, August 7, 2019 28

PROJECT NUMBER	ITEM NUMBER/ PROJECT LOCATION	ITEM DESCRIPTION/ PROJECT LOCATION	DATE LET	UNIT/ QUANTITY	ENGR. EST.	AVERAGE BID	AWARDED BID
===== 202-00810		Rem Ground Sign		Each =====			
FSA0252-468		I-25 AND PLUM CREEK IMPROVEME	04/18/19	6.00	175.00	178.75	237.00
NHPP0703-445		I-70 WESTBOUND PEAK PERIOD SH	04/25/19	50.00	120.00	225.60	148.00
NHPP2851-012		US 285 Antonito to Estrella C	05/02/19	32.00	82.00	138.33	200.00
MTCE0641-103		MTCE R3 FY20 SH 64 RANGELY PE	05/02/19	2.00	125.00	397.50	500.00
NHPP030A-036		SH 30 & TOWER RD IMPROVEMENTS	06/13/19	10.00	150.00	155.00	155.00
	WEIGHTED AVERAGE FOR THE SECOND QUARTER			110.00	112.95	187.76	167.47
	WEIGHTED AVERAGE FOR THE YEAR			597.00	76.20	98.94	88.42
===== 202-00815		Rem of Sign (Special)		Each =====			
SHER100-284		FY19 NORTH SIGNAL PKG	02/21/19	11.00	50.00	296.33	605.00
	WEIGHTED AVERAGE FOR THE FIRST QUARTER			11.00	50.00	296.33	605.00
	WEIGHTED AVERAGE FOR THE YEAR			11.00	50.00	296.33	605.00
===== 202-00821		Rem Sign Panel		Each =====			
NHPPR500-173		US 160_550 DURANGO SIGNALS OP	01/03/19	67.00	50.00	84.50	54.00
ER119A-065		PR SH 119A BOULDER CANYON	01/03/19	2.00	70.00	82.08	56.00
STAL19A-069		SH 119: NEDERLAND - EAST					
STAM086-075		SH96A ABRIENDO - ORMAN SAFETY	01/31/19	9.00	31.81	39.17	37.50
NHPP0821-107		SH 82 GLENWOOD SPRINGS TO CA	02/07/19	6.00	100.00	89.00	53.00
NHPP145A-065		SH 145 PASSING LANES AT DEEP	02/14/19	2.00	80.00	84.58	100.00
NHPP0741-022		SH 74: I-70 TO CR 65 RESURFAC	02/14/19	7.00	60.00	33.39	32.55
MPR200-253		R2 FY19 STENCIL PVMT MKG PROJ	03/07/19	6.00	45.00	128.33	75.00
NHPP006A-058		US 6 LOVELAND PASS - I-70 (FY	03/07/19	23.00	80.00	140.82	81.64
NHPP2254-089		I-225 RESURFACING FROM I-25 T	03/21/19	6.00	45.00	264.23	160.00
STM0242-077		US24 - 8TH ST TO WEST OF MANI	03/28/19	8.00	51.64	65.00	65.00
	WEIGHTED AVERAGE FOR THE FIRST QUARTER			136.00	56.98	95.03	63.39
NHPP030A-035		US 285/SH30	04/04/19	20.00	60.00	65.00	65.00
FSA0252-468		I-25 AND PLUM CREEK IMPROVEME	04/18/19	3.00	100.00	62.50	45.00
NHPP2851-012		US 285 Antonito to Estrella C	05/02/19	62.00	30.00	57.00	26.00
FSA0703-454		EB I-70 AUX LANE WARD TO KIPL	05/16/19	2.00	300.00	190.40	170.00
SHE0701-243		I-70 EXIT 26 DDI MODIFICATION	05/16/19	3.00	50.00	450.00	400.00
	WEIGHTED AVERAGE FOR THE SECOND QUARTER			90.00	45.67	81.33	50.97
	WEIGHTED AVERAGE FOR THE YEAR			226.00	52.48	89.35	58.44

COLORADO DEPARTMENT OF TRANSPORTATION
 ITEM UNIT COSTS BY PROJECTS -- 2019 COST DATA

13:44 Wednesday, August 7, 2019 29

PROJECT NUMBER	ITEM NUMBER/ PROJECT LOCATION	ITEM DESCRIPTION/ PROJECT LOCATION	DATE LET	UNIT/ QUANTITY	ENGR. EST.	AVERAGE BID	AWARDED BID
===== 202-00825		Rem Flashing Beacon		Each	=====	=====	=====
STA067A-038		SH 67 SEDALIA RESURFACING	01/31/19	2.00	160.00	860.12	2000.00
	WEIGHTED AVERAGE FOR THE FIRST QUARTER			2.00	160.00	860.12	2000.00
	WEIGHTED AVERAGE FOR THE YEAR			2.00	160.00	860.12	2000.00
===== 202-00827		Rem of Pull Box		Each	=====	=====	=====
ITSSW01-638		ETHERNET PHASE III (PRIMARYLY	02/07/19	5.00	250.00	488.50	500.00
NHPP0741-022		SH 74: I-70 TO CR 65 RESURFAC	02/14/19	4.00	350.00	238.99	235.00
C R100-315		R1 ADA CURB RAMPS - PH 5	03/07/19	14.00	325.00	770.00	590.00
STM0242-077		US24 - 8TH ST TO WEST OF MANI	03/28/19	4.00	202.00	1340.00	250.00
	WEIGHTED AVERAGE FOR THE FIRST QUARTER			27.00	296.59	702.25	470.37
FSA0252-468		I-25 AND PLUM CREEK IMPROVEME	04/18/19	4.00	325.00	203.25	178.00
NHPP0703-445		I-70 WESTBOUND PEAK PERIOD SH	04/25/19	23.00	320.00	4531.02	4770.00
FSA2873-190		US 287 AND FOOTHILLS PARKWAY	05/02/19	3.00	250.00	812.50	475.00
CR300-248		CRAIG RESIDENCY ADA RAMPS	05/16/19	5.00	300.00	527.33	300.00
STRR200-257		ROAD CLOSURE GATES ON VARIOUS	05/30/19	2.00	275.00	327.50	250.00
	WEIGHTED AVERAGE FOR THE SECOND QUARTER			37.00	309.73	2999.89	3076.95
	WEIGHTED AVERAGE FOR THE YEAR			64.00	304.19	2138.27	1977.30
===== 202-00828		Rem Traf Sig Equipment		LUMP SUM	=====	=====	=====
SHER100-289		INTERSECTIONS @ SH83 & LONGS	01/03/19	1.00	20000.00	7877.00	7375.00
STAM086-075		SH96A ABRIENDO - ORMAN SAFETY	01/31/19	1.00	3500.00	27833.33	13500.00
SHER100-284		FY19 NORTH SIGNAL PKG	02/21/19	1.00	40000.00	22512.33	18900.00
SHE2254-090		Colfax & I-225, Colfax & Cham	03/07/19	1.00	15000.00	24985.00	25000.00
SHER100-308		MIDPOINT - SIGNAL CONST PACKA	03/21/19	1.00	30000.00	72369.00	94738.00
STM0242-077		US24 - 8TH ST TO WEST OF MANI	03/28/19	1.00	70000.00	6133.33	4500.00
	WEIGHTED AVERAGE FOR THE FIRST QUARTER			6.00	29750.00	22418.33	27335.50
NHPP030A-035		US 285/SH30	04/04/19	1.00	15000.00	4400.00	4400.00

COLORADO DEPARTMENT OF TRANSPORTATION
ITEM UNIT COSTS BY PROJECTS -- 2019 COST DATA

13:44 Wednesday, August 7, 2019 30

PROJECT NUMBER	ITEM NUMBER/ PROJECT LOCATION	ITEM DESCRIPTION/ PROJECT LOCATION	DATE LET	UNIT/ QUANTITY	ENGR. EST.	AVERAGE BID	AWARDED BID
===== 202-00828		Rem Traf Sig Equipment		LUMP SUM	=====	=====	=====
FSA0252-468		I-25 AND PLUM CREEK IMPROVEME	04/18/19	1.00	14000.00	5692.00	4174.00
MTCE0641-103		MTCE R3 FY20 SH 64 RANGELY PE	05/02/19	1.00	2500.00	5280.00	4800.00
FSA2873-190		US 287 AND FOOTHILLS PARKWAY	05/02/19	1.00	15000.00	8585.00	11000.00
	WEIGHTED AVERAGE FOR THE SECOND QUARTER			4.00	11625.00	6099.78	6093.50
	WEIGHTED AVERAGE FOR THE YEAR			10.00	22500.00	16978.81	18838.70
===== 202-00831		Rem Traf Sig Head		Each	=====	=====	=====
NHPPR500-173		US 160_550 DURANGO SIGNALS OP	01/03/19	10.00	150.00	175.50	76.00
	WEIGHTED AVERAGE FOR THE FIRST QUARTER			10.00	150.00	175.50	76.00
FSA0252-468		I-25 AND PLUM CREEK IMPROVEME	04/18/19	1.00	175.00	83.00	77.00
	WEIGHTED AVERAGE FOR THE SECOND QUARTER			1.00	175.00	83.00	77.00
	WEIGHTED AVERAGE FOR THE YEAR			11.00	152.27	160.08	76.09
===== 202-00840		Rem Traf Sig Pole		Each	=====	=====	=====
NHPP2254-089		I-225 RESURFACING FROM I-25 T	03/21/19	1.00	2500.00	1614.89	800.00
	WEIGHTED AVERAGE FOR THE FIRST QUARTER			1.00	2500.00	1614.89	800.00
	WEIGHTED AVERAGE FOR THE YEAR			1.00	2500.00	1614.89	800.00
===== 202-00855		Rem Traf Sig Control Cab		Each	=====	=====	=====
ITSSW01-638		ETHERNET PHASE III (PRIMARYLY	02/07/19	2.00	1500.00	2147.50	3000.00
	WEIGHTED AVERAGE FOR THE FIRST QUARTER			2.00	1500.00	2147.50	3000.00
NHPP0703-445		I-70 WESTBOUND PEAK PERIOD SH	04/25/19	4.00	1300.00	2777.45	2942.00
	WEIGHTED AVERAGE FOR THE SECOND QUARTER			4.00	1300.00	2777.45	2942.00
	WEIGHTED AVERAGE FOR THE YEAR			6.00	1366.67	2619.96	2961.33

COLORADO DEPARTMENT OF TRANSPORTATION
 ITEM UNIT COSTS BY PROJECTS -- 2019 COST DATA

13:44 Wednesday, August 7, 2019 31

PROJECT NUMBER	ITEM NUMBER/ PROJECT LOCATION	ITEM DESCRIPTION/ PROJECT LOCATION	DATE LET	UNIT/ QUANTITY	ENGR. EST.	AVERAGE BID	AWARDED BID
===== 202-00858		Rem Pedestal Pole		Each	=====	=====	=====
NHPPR500-173		US 160_550 DURANGO SIGNALS OP	01/03/19	1.00	1000.00	542.00	219.00
	WEIGHTED	AVERAGE FOR THE FIRST QUARTER		1.00	1000.00	542.00	219.00
		WEIGHTED AVERAGE FOR THE YEAR		1.00	1000.00	542.00	219.00
===== 202-00860		Rem Ped Push Button		Each	=====	=====	=====
NHPP0741-022		SH 74: I-70 TO CR 65 RESURFAC	02/14/19	12.00	50.00	66.76	65.00
C R100-315		R1 ADA CURB RAMPS - PH 5	03/07/19	15.00	120.00	172.50	60.00
	WEIGHTED	AVERAGE FOR THE FIRST QUARTER		27.00	88.89	107.43	62.22
FSA0252-468		I-25 AND PLUM CREEK IMPROVEME	04/18/19	8.00	65.00	22.25	18.00
	WEIGHTED	AVERAGE FOR THE SECOND QUARTER		8.00	65.00	22.25	18.00
		WEIGHTED AVERAGE FOR THE YEAR		35.00	83.43	82.65	52.11
===== 202-00889		Rem of Detect Warning		Each	=====	=====	=====
STR0241-062		US 24 143.4 - 148	01/24/19	1.00	200.00	541.67	320.00
	WEIGHTED	AVERAGE FOR THE FIRST QUARTER		1.00	200.00	541.67	320.00
		WEIGHTED AVERAGE FOR THE YEAR		1.00	200.00	541.67	320.00
===== 202-00895		Rem of Impact Attenuator		Each	=====	=====	=====
NHPP0821-107		SH 82 GLENWOOD SPRINGS TO CA	02/07/19	3.00	1500.00	1750.00	1500.00
SHE2254-090		Colfax & I-225, Colfax & Cham	03/07/19	2.00	1200.00	2900.00	4000.00
	WEIGHTED	AVERAGE FOR THE FIRST QUARTER		5.00	1380.00	2210.00	2500.00
NHPP0703-445		I-70 WESTBOUND PEAK PERIOD SH	04/25/19	2.00	3000.00	1580.43	2076.00
	WEIGHTED	AVERAGE FOR THE SECOND QUARTER		2.00	3000.00	1580.43	2076.00
		WEIGHTED AVERAGE FOR THE YEAR		7.00	1842.86	1973.91	2378.86

COLORADO DEPARTMENT OF TRANSPORTATION
 ITEM UNIT COSTS BY PROJECTS -- 2019 COST DATA

13:44 Wednesday, August 7, 2019 32

PROJECT NUMBER	ITEM NUMBER/ PROJECT LOCATION	ITEM DESCRIPTION/ PROJECT LOCATION	DATE LET	UNIT/ QUANTITY	ENGR. EST.	AVERAGE BID	AWARDED BID
===== 202-01000		Rem Fence		Lin Foot	=====		
ER119A-065		PR SH 119A BOULDER CANYON	01/03/19	98.00	5.00	6.52	5.00
STA119A-069		SH 119: NEDERLAND - EAST					
STR0132-021		SH 13-MOFFAT COUNTY-CR 3 SOUT	01/10/19	49,160.00	1.00	0.91	0.78
FBR0341-087		US 34 OVER NORTH FORK CO RIVE	01/10/19	297.00	2.00	4.82	4.22
STR0241-062		US 24 143.4 - 148	01/24/19	252.00	3.00	11.17	15.00
ER072A-040		PR SH72A FLOOD PERMANENT REPA	01/31/19	149.00	3.00	6.40	6.00
NHPP072A-041		PR SH72A FLOOD PERMANENT REPA					
NHPP1601-073		US 160 PASSING LANE NORTH OF	03/07/19	3,813.00	1.50	1.45	0.90
FBR0253-247		I25 AT VINE DRIVE BRIDGE REPL	03/07/19	513.00	5.00	2.94	2.00
NHPP0503-087		US 50 PASSING LANES EAST OF S	03/21/19	7,286.00	1.20	1.08	1.00
SHE 0252-481		I-25 RAMP METER INSTALLATION	03/21/19	745.00	3.00	2.17	2.00
STA0131-070 HMA ALT		SH 13 CR 5 NORTH AND SOUTH	03/28/19	105,060.00	1.20	1.13	0.85
STA0131-070 PCCP ALT		SH 13 CR 5 NORTH AND SOUTH					
		WEIGHTED AVERAGE FOR THE FIRST QUARTER		167,373.00	1.18	1.11	0.89
NHPP030A-035		US 285/SH30	04/04/19	69.00	3.00	12.00	12.00
NHPP0703-445		I-70 WESTBOUND PEAK PERIOD SH	04/25/19	2,456.00	3.00	6.52	7.00
FBR0063-057		US-6 F-09-K BRIDGE OVER CASTL	05/30/19	218.00	3.00	2.63	2.50
ER145A-081		SH 145 MP 21 EMERGENCY ROCKFA	06/07/19	100.00	1.50	4.47	8.00
		WEIGHTED AVERAGE FOR THE SECOND QUARTER		2,843.00	2.95	6.31	6.81
		WEIGHTED AVERAGE FOR THE YEAR		170,216.00	1.21	1.18	1.04
===== 202-01035		Rem of Gate		Each	=====		
STR0132-021		SH 13-MOFFAT COUNTY-CR 3 SOUT	01/10/19	12.00	150.00	122.00	104.00
NHPP1601-073		US 160 PASSING LANE NORTH OF	03/07/19	1.00	210.00	270.00	390.00
NHPP0503-087		US 50 PASSING LANES EAST OF S	03/21/19	7.00	270.00	155.50	200.00
STA0131-070 HMA ALT		SH 13 CR 5 NORTH AND SOUTH	03/28/19	66.00	325.00	181.50	121.00
STA0131-070 PCCP ALT		SH 13 CR 5 NORTH AND SOUTH					
		WEIGHTED AVERAGE FOR THE FIRST QUARTER		86.00	294.77	167.79	132.66
FBR0063-057		US-6 F-09-K BRIDGE OVER CASTL	05/30/19	1.00	200.00	200.00	100.00
		WEIGHTED AVERAGE FOR THE SECOND QUARTER		1.00	200.00	200.00	100.00
		WEIGHTED AVERAGE FOR THE YEAR		87.00	293.68	168.02	132.06

PROJECT NUMBER	ITEM NUMBER/ PROJECT LOCATION	ITEM DESCRIPTION/ PROJECT LOCATION	DATE LET	UNIT/ QUANTITY	ENGR. EST.	AVERAGE BID	AWARDED BID
===== 202-01130		Rem Gdrail Ty 3		Lin Foot	=====		
IM0251-351		I-25 South of Pueblo MP 79.6	01/03/19	16,600.00	4.50	3.15	3.37
ER119A-065		PR SH 119A BOULDER CANYON	01/03/19	14,780.00	4.00	2.85	2.50
STA119A-069		SH 119: NEDERLAND - EAST					
FBR0341-087		US 34 OVER NORTH FORK CO RIVE	01/10/19	367.00	5.00	7.50	8.45
STR141A-047		SH 141 MP 120-143 MESA COUNTY	01/17/19	4,500.00	5.00	3.27	3.00
NHPP0701-241		I-70 TRUCK PARKING GARFIELD C	01/17/19	1,135.00	4.00	6.63	5.70
STR0241-062		US 24 143.4 - 148	01/24/19	3,711.00	5.00	6.92	8.00
ER072A-040		PR SH72A FLOOD PERMANENT REPA	01/31/19	2,916.00	4.00	6.44	6.00
NHPP072A-041		PR SH72A FLOOD PERMANENT REPA					
STA067A-038		SH 67 SEDALIA RESURFACING	01/31/19	96.00	4.50	11.28	10.00
NHPP0821-107		SH 82 GLENWOOD SPRINGS TO CA	02/07/19	39,380.00	4.00	2.30	2.10
NH2871-035		US 287 PASSING LANES SOUTH OF	02/07/19	500.00	5.00	4.44	3.94
NHPP0741-022		SH 74: I-70 TO CR 65 RESURFAC	02/14/19	363.00	5.00	7.45	7.30
NHPP070A-028		FALL RIVER ROAD BRIDGE	02/21/19	260.00	4.50	8.55	9.50
NHPP1601-073		US 160 PASSING LANE NORTH OF	03/07/19	237.00	10.00	6.38	5.75
FBR0253-247		I25 AT VINE DRIVE BRIDGE REPL	03/07/19	1,150.00	4.00	5.10	10.00
NHPP006A-058		US 6 LOVELAND PASS - I-70 (FY	03/07/19	4,216.00	5.00	3.74	3.48
SHE2254-090		Colfax & I-225, Colfax & Cham	03/07/19	67.00	5.00	20.98	24.00
NHPP0702-378		I-70 OFFICERS GULCH TO FRISCO	03/14/19	2,141.00	5.00	6.96	5.89
NHPP050A-033		US50 West of Delta EB Lanes R	03/14/19	6,872.00	4.00	3.55	3.15
NHPP0503-087		US 50 PASSING LANES EAST OF S	03/21/19	564.00	4.00	5.80	6.00
SHE 0252-481		I-25 RAMP METER INSTALLATION	03/21/19	303.00	5.00	9.50	9.50
NHPP2254-089		I-225 RESURFACING FROM I-25 T	03/21/19	1,391.00	6.00	6.34	6.00
STM0242-077		US24 - 8TH ST TO WEST OF MANI	03/28/19	7,505.00	4.58	2.92	2.75
STA0131-070 HMA ALT		SH 13 CR 5 NORTH AND SOUTH	03/28/19	3,822.00	4.00	5.68	5.40
STA0131-070 PCCP ALT		SH 13 CR 5 NORTH AND SOUTH					
		WEIGHTED AVERAGE FOR THE FIRST QUARTER		112,876.00	4.29	3.65	3.27
BR071A-020		REPLACEMENT OF STRUCTURE L-22	04/18/19	265.00	6.00	17.17	16.50
FSA0252-468		I-25 AND PLUM CREEK IMPROVEME	04/18/19	216.00	8.00	14.20	13.28
NHPP0703-445		I-70 WESTBOUND PEAK PERIOD SH	04/25/19	44,221.00	4.00	2.93	2.50
FSA0703-454		EB I-70 AUX LANE WARD TO KIPL	05/16/19	57.00	7.00	66.78	20.00
NHPP0703-442		I-70 SILVERPLUME SOUNDWALL AN	06/13/19	50.00	30.00	20.58	46.00
CR500-205		R5 GUARDRAIL END TREATMENT EA	06/13/19	1,105.00	10.00	6.50	6.50
		WEIGHTED AVERAGE FOR THE SECOND QUARTER		45,914.00	4.21	3.25	2.80
		WEIGHTED AVERAGE FOR THE YEAR		158,790.00	4.27	3.56	3.13

===== 202-01135		Rem Gdrail Thrie Beam		Lin Foot	=====		
ER119A-065		PR SH 119A BOULDER CANYON	01/03/19	413.00	5.00	6.20	6.00

COLORADO DEPARTMENT OF TRANSPORTATION
ITEM UNIT COSTS BY PROJECTS -- 2019 COST DATA

13:44 Wednesday, August 7, 2019 34

PROJECT NUMBER	ITEM NUMBER/ PROJECT LOCATION	ITEM DESCRIPTION/ PROJECT LOCATION	DATE LET	UNIT/ QUANTITY	ENGR. EST.	AVERAGE BID	AWARDED BID
===== 202-01135	Rem Gdrail Thrie Beam			Lin Foot			
STA119A-069	SH 119: NEDERLAND - EAST						
	WEIGHTED AVERAGE FOR THE FIRST QUARTER			413.00	5.00	6.20	6.00
	WEIGHTED AVERAGE FOR THE YEAR			413.00	5.00	6.20	6.00
===== 202-01140	Rem Gdrail Ty 4			Lin Foot			
ER119A-065	PR SH 119A BOULDER CANYON		01/03/19	9,081.00	12.00	14.44	11.00
STA119A-069	SH 119: NEDERLAND - EAST						
NHPPR100-250	PACKAGE A (I-25 / I-70 / I-76		01/24/19	77.00	50.00	200.79	156.00
	WEIGHTED AVERAGE FOR THE FIRST QUARTER			9,158.00	12.32	15.42	12.22
NHPP0703-445	I-70 WESTBOUND PEAK PERIOD SH		04/25/19	13,642.00	25.00	25.33	15.00
NHPP0703-442	I-70 SILVERPLUME SOUNDWALL AN		06/13/19	1,294.00	30.00	30.20	28.00
	WEIGHTED AVERAGE FOR THE SECOND QUARTER			14,936.00	25.43	26.32	16.13
	WEIGHTED AVERAGE FOR THE YEAR			24,094.00	20.45	19.92	14.64
===== 202-01170	Rem Gdrail Ty 7			Lin Foot			
STR0241-062	US 24 143.4 - 148		01/24/19	100.00	10.00	23.33	9.00
NHPP070A-028	FALL RIVER ROAD BRIDGE		02/21/19	19.00	90.00	118.15	28.00
SHE2254-090	Colfax & I-225, Colfax & Cham		03/07/19	33.00	120.00	300.00	300.00
	WEIGHTED AVERAGE FOR THE FIRST QUARTER			152.00	43.88	82.48	74.55
NHPP0703-445	I-70 WESTBOUND PEAK PERIOD SH		04/25/19	1,104.00	100.00	30.67	17.00
	WEIGHTED AVERAGE FOR THE SECOND QUARTER			1,104.00	100.00	30.67	17.00
	WEIGHTED AVERAGE FOR THE YEAR			1,256.00	93.21	37.00	23.96
===== 202-01180	Rem Median Barrier			Lin Foot			
STR 141A-040	R5 YEAR 4 BRDG PREV MAINT RAM		06/20/19	238.00	25.00	145.00	50.00
	WEIGHTED AVERAGE FOR THE SECOND QUARTER			238.00	25.00	145.00	50.00
	WEIGHTED AVERAGE FOR THE YEAR			238.00	25.00	145.00	50.00

PROJECT NUMBER	ITEM NUMBER/ PROJECT LOCATION	ITEM DESCRIPTION/ PROJECT LOCATION	DATE LET	UNIT/ QUANTITY	ENGR. EST.	AVERAGE BID	AWARDED BID
===== 202-01200		Rem Tensioned Cable Barrier		Lin Foot	=====		
IM0252-472		I-25 CABLE BARRIER PHASE III	04/04/19	16,083.00	5.00	6.00	7.00
		WEIGHTED AVERAGE FOR THE SECOND QUARTER		16,083.00	5.00	6.00	7.00
		WEIGHTED AVERAGE FOR THE YEAR		16,083.00	5.00	6.00	7.00
===== 202-01300		Rem End Anchorage		Each	=====		
IM0251-351		I-25 South of Pueblo MP 79.6	01/03/19	40.00	290.00	309.41	336.89
ER119A-065		PR SH 119A BOULDER CANYON	01/03/19	67.00	225.37	250.86	215.00
STA119A-069		SH 119: NEDERLAND - EAST					
FBR0341-087		US 34 OVER NORTH FORK CO RIVE	01/10/19	4.00	275.00	367.73	392.27
STR141A-047		SH 141 MP 120-143 MESA COUNTY	01/17/19	10.00	300.00	334.45	310.00
NHPP0701-241		I-70 TRUCK PARKING GARFIELD C	01/17/19	4.00	300.00	439.09	375.00
STR0241-062		US 24 143.4 - 148	01/24/19	26.00	300.00	323.33	340.00
ER072A-040		PR SH72A FLOOD PERMANENT REPA	01/31/19	17.00	250.00	375.01	375.00
NHPP072A-041		PR SH72A FLOOD PERMANENT REPA					
STA067A-038		SH 67 SEDALIA RESURFACING	01/31/19	3.00	400.00	433.89	500.00
NHPP0821-107		SH 82 GLENWOOD SPRINGS TO CA	02/07/19	50.00	300.00	183.00	166.00
NH2871-035		US 287 PASSING LANES SOUTH OF	02/07/19	4.00	500.00	389.38	325.50
NHPP145A-065		SH 145 PASSING LANES AT DEEP	02/14/19	1.00	200.00	337.85	300.00
NHPP0741-022		SH 74: I-70 TO CR 65 RESURFAC	02/14/19	4.00	400.00	335.55	325.50
NHPP1601-073		US 160 PASSING LANE NORTH OF	03/07/19	4.00	200.00	370.00	340.00
NHPP006A-058		US 6 LOVELAND PASS - I-70 (FY	03/07/19	26.00	300.00	307.85	315.69
SHE2254-090		Colfax & I-225, Colfax & Cham	03/07/19	1.00	300.00	1050.00	1500.00
NHPP0702-378		I-70 OFFICERS GULCH TO FRISCO	03/14/19	10.00	250.00	496.67	410.00
NHPP050A-033		US50 West of Delta EB Lanes R	03/14/19	20.00	325.00	331.67	285.00
NHPP0503-087		US 50 PASSING LANES EAST OF S	03/21/19	4.00	200.00	400.00	400.00
NHPP2254-089		I-225 RESURFACING FROM I-25 T	03/21/19	64.00	200.00	307.57	275.00
STM0242-077		US24 - 8TH ST TO WEST OF MANI	03/28/19	15.00	292.67	253.33	220.00
STA0131-070 HMA ALT		SH 13 CR 5 NORTH AND SOUTH	03/28/19	14.00	300.00	482.86	431.00
STA0131-070 PCCP ALT		SH 13 CR 5 NORTH AND SOUTH					
		WEIGHTED AVERAGE FOR THE FIRST QUARTER		388.00	268.40	304.78	284.39
IM0252-472		I-25 CABLE BARRIER PHASE III	04/04/19	20.00	300.00	2500.00	2000.00
BR071A-020		REPLACEMENT OF STRUCTURE L-22	04/18/19	6.00	300.00	823.33	790.00
FSA0252-468		I-25 AND PLUM CREEK IMPROVEME	04/18/19	1.00	3500.00	514.50	478.00
NHPP0703-445		I-70 WESTBOUND PEAK PERIOD SH	04/25/19	52.00	250.00	344.02	356.00
NHPP0703-442		I-70 SILVERPLUME SOUNDWALL AN	06/13/19	2.00	350.00	709.33	1430.00
CR500-205		R5 GUARDRAIL END TREATMENT EA	06/13/19	40.00	500.00	325.00	325.00
		WEIGHTED AVERAGE FOR THE SECOND QUARTER		121.00	371.90	711.30	657.77
		WEIGHTED AVERAGE FOR THE YEAR		509.00	293.01	362.76	374.39

PROJECT NUMBER	ITEM NUMBER/ PROJECT LOCATION	ITEM DESCRIPTION/ PROJECT LOCATION	DATE LET	UNIT/ QUANTITY	ENGR. EST.	AVERAGE BID	AWARDED BID
===== 202-01400		Removal of Cattle Guard		Each	=====	=====	=====
STR0132-021		SH 13-MOFFAT COUNTY-CR 3 SOUT	01/10/19	1.00	4000.00	2596.00	1640.00
STA0131-070 HMA ALT		SH 13 CR 5 NORTH AND SOUTH	03/28/19	2.00	3000.00	2038.73	606.00
STA0131-070 PCCP ALT		SH 13 CR 5 NORTH AND SOUTH					
		WEIGHTED AVERAGE FOR THE FIRST QUARTER		3.00	3333.33	2292.03	1123.00
		WEIGHTED AVERAGE FOR THE YEAR		3.00	3333.33	2292.03	1123.00
===== 202-04001		Plug Culvert		Each	=====	=====	=====
NHPP145A-065		SH 145 PASSING LANES AT DEEP	02/14/19	1.00	5000.00	28378.26	13000.00
NHPP1601-073		US 160 PASSING LANE NORTH OF	03/07/19	3.00	5000.00	6500.00	10000.00
NHPP006A-058		US 6 LOVELAND PASS - I-70 (FY	03/07/19	3.00	1500.00	5191.98	7383.96
NHPP0503-087		US 50 PASSING LANES EAST OF S	03/21/19	2.00	1800.00	3100.00	700.00
		WEIGHTED AVERAGE FOR THE FIRST QUARTER		9.00	3122.22	10687.77	7394.65
NHPP0703-445		I-70 WESTBOUND PEAK PERIOD SH	04/25/19	11.00	2500.00	3692.81	1392.00
		WEIGHTED AVERAGE FOR THE SECOND QUARTER		11.00	2500.00	3692.81	1392.00
		WEIGHTED AVERAGE FOR THE YEAR		20.00	2780.00	6413.07	4093.19
===== 202-04002		Clean Culvert		Each	=====	=====	=====
SHER100-289		INTERSECTIONS @ SH83 & LONGS	01/03/19	1.00	2500.00	1374.20	1600.00
ER119A-065		PR SH 119A BOULDER CANYON	01/03/19	176.00	1350.00	1324.48	850.00
STA119A-069		SH 119: NEDERLAND - EAST					
ER072A-040		PR SH72A FLOOD PERMANENT REPA	01/31/19	2.00	2500.00	2499.56	1600.00
NHPP072A-041		PR SH72A FLOOD PERMANENT REPA					
STA067A-038		SH 67 SEDALIA RESURFACING	01/31/19	12.00	2500.00	999.95	250.00
NHPP070A-028		FALL RIVER ROAD BRIDGE	02/21/19	4.00	2500.00	1976.22	1400.00
NHPP006A-058		US 6 LOVELAND PASS - I-70 (FY	03/07/19	10.00	2500.00	3655.05	3810.09
SHE2254-090		Colfax & I-225, Colfax & Cham	03/07/19	2.00	2300.00	2375.00	750.00
NHPP050A-033		US50 West of Delta EB Lanes R	03/14/19	2.00	2500.00	5180.00	1540.00
NHPP0503-087		US 50 PASSING LANES EAST OF S	03/21/19	2.00	2000.00	4150.00	4000.00
SHER100-308		MIDPOINT - SIGNAL CONST PACKA	03/21/19	3.00	1500.00	1625.00	1050.00
NHPP2254-089		I-225 RESURFACING FROM I-25 T	03/21/19	1.00	1500.00	2685.17	4000.00
		WEIGHTED AVERAGE FOR THE FIRST QUARTER		215.00	1533.49	1403.21	1027.12

COLORADO DEPARTMENT OF TRANSPORTATION
ITEM UNIT COSTS BY PROJECTS -- 2019 COST DATA

13:44 Wednesday, August 7, 2019 37

PROJECT NUMBER	ITEM NUMBER/ PROJECT LOCATION	ITEM DESCRIPTION/ PROJECT LOCATION	DATE LET	UNIT/ QUANTITY	ENGR. EST.	AVERAGE BID	AWARDED BID
=====	202-04002	Clean Culvert		Each	=====	=====	=====
IM0252-472		I-25 CABLE BARRIER PHASE III	04/04/19	10.00	2500.00	2900.00	2000.00
NHPP0703-445		I-70 WESTBOUND PEAK PERIOD SH	04/25/19	77.00	2500.00	1831.75	1516.00
FSA0703-454		EB I-70 AUX LANE WARD TO KIPL	05/16/19	3.00	2500.00	2095.71	2000.00
NHPP0703-442		I-70 SILVERPLUME SOUNDWALL AN	06/13/19	1.00	3000.00	2729.34	2830.00
NHPP030A-036		SH 30 & TOWER RD IMPROVEMENTS	06/13/19	2.00	2200.00	2400.00	2400.00
STR 141A-040		R5 YEAR 4 BRDG PREV MAINT RAM	06/20/19	1.00	1000.00	5000.00	5000.00
NHPP160A-030		US160 MM 43.2, 150.4, 156.3,	06/20/19	4.00	3000.00	5150.00	5300.00
		WEIGHTED AVERAGE FOR THE SECOND QUARTER		98.00	2504.08	2063.68	1801.65
		WEIGHTED AVERAGE FOR THE YEAR		313.00	1837.38	1505.05	1269.63
=====	202-04003	Clean Culvert (Spec)		Each	=====	=====	=====
SHER100-284		FY19 NORTH SIGNAL PKG	02/21/19	1.00	1500.00	1610.67	2182.00
		WEIGHTED AVERAGE FOR THE FIRST QUARTER		1.00	1500.00	1610.67	2182.00
		WEIGHTED AVERAGE FOR THE YEAR		1.00	1500.00	1610.67	2182.00
=====	202-04005	Clean Valve Box		Each	=====	=====	=====
SHE2254-090		Colfax & I-225, Colfax & Cham	03/07/19	3.00	300.00	600.00	200.00
		WEIGHTED AVERAGE FOR THE FIRST QUARTER		3.00	300.00	600.00	200.00
NHPP030A-035		US 285/SH30	04/04/19	80.00	250.00	400.00	400.00
NHPP030A-036		SH 30 & TOWER RD IMPROVEMENTS	06/13/19	2.00	300.00	245.00	245.00
		WEIGHTED AVERAGE FOR THE SECOND QUARTER		82.00	251.22	396.22	396.22
		WEIGHTED AVERAGE FOR THE YEAR		85.00	252.94	410.11	389.29
=====	202-04006	Clean Culvert		Hour	=====	=====	=====
SHE2254-090		Colfax & I-225, Colfax & Cham	03/07/19	10.00	350.00	400.00	300.00

PROJECT NUMBER	ITEM NUMBER/ PROJECT LOCATION	ITEM DESCRIPTION/ PROJECT LOCATION	DATE LET	UNIT/ QUANTITY	ENGR. EST.	AVERAGE BID	AWARDED BID
===== 202-04006		Clean Culvert		Hour =====			
SHER100-308		MIDPOINT - SIGNAL CONST PACKA	03/21/19	5.00	350.00	1272.50	345.00
	WEIGHTED AVERAGE FOR THE FIRST QUARTER			15.00	350.00	690.83	315.00
	WEIGHTED AVERAGE FOR THE YEAR			15.00	350.00	690.83	315.00
===== 202-04010		Clean Inlet		Each =====			
NHPP0701-241		I-70 TRUCK PARKING GARFIELD C	01/17/19	1.00	520.00	1768.96	800.00
STA067A-038		SH 67 SEDALIA RESURFACING	01/31/19	8.00	450.00	329.67	250.00
NHPP0821-107		SH 82 GLENWOOD SPRINGS TO CA	02/07/19	3.00	450.00	2040.00	1580.00
NHPP0741-022		SH 74: I-70 TO CR 65 RESURFAC	02/14/19	18.00	800.00	1205.71	1625.00
NHPP006A-058		US 6 LOVELAND PASS - I-70 (FY	03/07/19	10.00	700.00	1255.19	1110.37
SHER100-308		MIDPOINT - SIGNAL CONST PACKA	03/21/19	1.00	400.00	1177.50	1725.00
NHPP2254-089		I-225 RESURFACING FROM I-25 T	03/21/19	27.00	375.00	540.78	200.00
	WEIGHTED AVERAGE FOR THE FIRST QUARTER			68.00	549.93	890.81	809.10
NHPP030A-035		US 285/SH30	04/04/19	61.00	400.00	1300.00	1300.00
NHPP0703-445		I-70 WESTBOUND PEAK PERIOD SH	04/25/19	35.00	400.00	655.85	640.00
FSA0703-454		EB I-70 AUX LANE WARD TO KIPL	05/16/19	1.00	500.00	948.39	1100.00
	WEIGHTED AVERAGE FOR THE SECOND QUARTER			97.00	401.03	893.55	1059.79
	WEIGHTED AVERAGE FOR THE YEAR			165.00	462.39	892.03	956.48
===== 202-04050		Clean Exp Joint		Lin Foot =====			
STR 141A-040		R5 YEAR 4 BRDG PREV MAINT RAM	06/20/19	212.00	20.00	53.50	25.00
	WEIGHTED AVERAGE FOR THE SECOND QUARTER			212.00	20.00	53.50	25.00
	WEIGHTED AVERAGE FOR THE YEAR			212.00	20.00	53.50	25.00
===== 202-05010		Sawing Concrete (10 In)		Lin Foot =====			
SHER100-289		INTERSECTIONS @ SH83 & LONGS	01/03/19	133.00	10.00	6.50	6.00
	WEIGHTED AVERAGE FOR THE FIRST QUARTER			133.00	10.00	6.50	6.00
	WEIGHTED AVERAGE FOR THE YEAR			133.00	10.00	6.50	6.00

COLORADO DEPARTMENT OF TRANSPORTATION
 ITEM UNIT COSTS BY PROJECTS -- 2019 COST DATA

13:44 Wednesday, August 7, 2019 39

PROJECT NUMBER	ITEM NUMBER/ PROJECT LOCATION	ITEM DESCRIPTION/ PROJECT LOCATION	DATE LET	UNIT/ QUANTITY	ENGR. EST.	AVERAGE BID	AWARDED BID
===== 202-05011		Sawing Concrete (10.5 In)		Lin Foot	=====		
NHPP030A-035	US 285/SH30		04/04/19	152.80	15.00	30.00	30.00
	WEIGHTED AVERAGE FOR THE SECOND QUARTER			152.80	15.00	30.00	30.00
	WEIGHTED AVERAGE FOR THE YEAR			152.80	15.00	30.00	30.00
===== 202-05026		Sawing Asphalt Mat (6 In)		Lin Foot	=====		
NHPP0701-241	I-70 TRUCK PARKING GARFIELD C		01/17/19	1,518.00	4.00	3.77	2.35
STA067A-038	SH 67 SEDALIA RESURFACING		01/31/19	506.00	10.00	24.72	8.00
STA0131-070 HMA ALT	SH 13 CR 5 NORTH AND SOUTH		03/28/19	1,480.00	7.00	5.40	8.55
STA0131-070 PCCP ALT	SH 13 CR 5 NORTH AND SOUTH						
	WEIGHTED AVERAGE FOR THE FIRST QUARTER			3,504.00	6.13	6.65	5.04
STMC430-020	ADA RAMPS DIVIDE ESB		05/23/19	263.00	5.50	8.06	8.06
NHPP0703-442	I-70 SILVERPLUME SOUNDWALL AN		06/13/19	1,668.00	4.00	3.32	5.20
	WEIGHTED AVERAGE FOR THE SECOND QUARTER			1,931.00	4.20	3.41	5.59
	WEIGHTED AVERAGE FOR THE YEAR			5,435.00	5.45	5.03	5.27
===== 202-05030		Sawing Asphalt Mat (10 In)		Lin Foot	=====		
SHER100-289	INTERSECTIONS @ SH83 & LONGS		01/03/19	2,676.00	4.00	4.04	4.00
	WEIGHTED AVERAGE FOR THE FIRST QUARTER			2,676.00	4.00	4.04	4.00
NHPP030A-035	US 285/SH30		04/04/19	8,359.20	4.00	5.00	5.00
	WEIGHTED AVERAGE FOR THE SECOND QUARTER			8,359.20	4.00	5.00	5.00
	WEIGHTED AVERAGE FOR THE YEAR			11,035.20	4.00	4.41	4.76
===== 202-05150		Sandblasting		Sq Foot	=====		
STAR200-242	R2 NORTH PROGRAM WALL REPAIRS		01/03/19	406,360.00	1.00	1.95	1.10
	WEIGHTED AVERAGE FOR THE FIRST QUARTER			406,360.00	1.00	1.95	1.10
	WEIGHTED AVERAGE FOR THE YEAR			406,360.00	1.00	1.95	1.10

COLORADO DEPARTMENT OF TRANSPORTATION
 ITEM UNIT COSTS BY PROJECTS -- 2019 COST DATA

13:44 Wednesday, August 7, 2019 40

PROJECT NUMBER	ITEM NUMBER/ PROJECT LOCATION	ITEM DESCRIPTION/ PROJECT LOCATION	DATE LET	UNIT/ QUANTITY	ENGR. EST.	AVERAGE BID	AWARDED BID
=====	202-06000	Rem Detour		LUMP SUM	=====		
STM0242-077		US24 - 8TH ST TO WEST OF MANI	03/28/19	1.00	5000.00	4233.33	1000.00
		WEIGHTED AVERAGE FOR THE FIRST QUARTER		1.00	5000.00	4233.33	1000.00
		WEIGHTED AVERAGE FOR THE YEAR		1.00	5000.00	4233.33	1000.00
=====	202-07000	Oblit Old Road		LUMP SUM	=====		
NHPP1601-073		US 160 PASSING LANE NORTH OF	03/07/19	1.00	45000.00	9000.00	11000.00
		WEIGHTED AVERAGE FOR THE FIRST QUARTER		1.00	45000.00	9000.00	11000.00
		WEIGHTED AVERAGE FOR THE YEAR		1.00	45000.00	9000.00	11000.00
=====	203-00000	Uncl Excav		Cubic Yard	=====		
NHPP0701-241		I-70 TRUCK PARKING GARFIELD C	01/17/19	2,315.00	40.00	21.45	12.75
STAM086-075		SH96A ABRRIENDO - ORMAN SAFETY	01/31/19	376.00	75.00	98.67	35.00
NHPP070A-028		FALL RIVER ROAD BRIDGE	02/21/19	696.00	24.00	36.35	37.00
SHE 0252-481		I-25 RAMP METER INSTALLATION	03/21/19	2,024.00	45.00	28.17	38.00
STM0242-077		US24 - 8TH ST TO WEST OF MANI	03/28/19	1,596.00	25.00	41.67	50.00
		WEIGHTED AVERAGE FOR THE FIRST QUARTER		7,007.00	38.32	31.68	32.13
		WEIGHTED AVERAGE FOR THE YEAR		7,007.00	38.32	31.68	32.13
=====	203-00010	Uncl Excav (CIP)		Cubic Yard	=====		
FSA0142-068		SH 14 & WCR 33 INTERSECTION I	01/03/19	118.00	65.00	83.75	42.00
SHER100-289		INTERSECTIONS @ SH83 & LONGS	01/03/19	745.00	15.00	66.20	34.00
ER119A-065		PR SH 119A BOULDER CANYON	01/03/19	47,766.00	30.00	28.24	21.00
STA119A-069		SH 119: NEDERLAND - EAST					
STR141A-047		SH 141 MP 120-143 MESA COUNTY	01/17/19	7,280.00	40.00	37.67	21.50
ER072A-040		PR SH72A FLOOD PERMANENT REPA	01/31/19	5,514.00	20.00	31.51	14.00
NHPP072A-041		PR SH72A FLOOD PERMANENT REPA					
NHPP0821-107		SH 82 GLENWOOD SPRINGS TO CA	02/07/19	37.00	45.00	80.93	36.85
SHE2254-090		Colfax & I-225, Colfax & Cham	03/07/19	666.00	20.00	59.00	68.00
SHER100-308		MIDPOINT - SIGNAL CONST PACKA	03/21/19	203.00	18.00	122.50	50.00
NHPP2254-089		I-225 RESURFACING FROM I-25 T	03/21/19	105.00	50.00	76.13	75.00
		WEIGHTED AVERAGE FOR THE FIRST QUARTER		62,434.00	30.07	29.80	21.33

COLORADO DEPARTMENT OF TRANSPORTATION
 ITEM UNIT COSTS BY PROJECTS -- 2019 COST DATA

13:44 Wednesday, August 7, 2019 41

PROJECT NUMBER	ITEM NUMBER/ PROJECT LOCATION	ITEM DESCRIPTION/ PROJECT LOCATION	DATE LET	UNIT/ QUANTITY	ENGR. EST.	AVERAGE BID	AWARDED BID
===== 203-00010		Uncl Excav (CIP)		Cubic Yard	=====		
BR071A-020		REPLACEMENT OF STRUCTURE L-22	04/18/19	2,270.00	20.00	27.83	24.50
FSA0252-468		I-25 AND PLUM CREEK IMPROVEME	04/18/19	962.00	25.00	65.82	70.80
NHPP0703-445		I-70 WESTBOUND PEAK PERIOD SH	04/25/19	17,871.00	20.00	31.67	21.00
FSA0703-454		EB I-70 AUX LANE WARD TO KIPL	05/16/19	3,344.00	17.00	43.90	25.00
SHE0701-243		I-70 EXIT 26 DDI MODIFICATION	05/16/19	1,205.00	25.00	18.50	17.00
NHPP030A-036		SH 30 & TOWER RD IMPROVEMENTS	06/13/19	1,115.00	20.00	22.00	22.00
		WEIGHTED AVERAGE FOR THE SECOND QUARTER		26,767.00	20.03	33.58	23.45
		WEIGHTED AVERAGE FOR THE YEAR		89,201.00	27.06	30.34	21.97
===== 203-00012		Uncl Excav (CIP) (Spec)		Cubic Yard	=====		
STR0241-062		US 24 143.4 - 148	01/24/19	67.00	100.00	56.67	25.00
		WEIGHTED AVERAGE FOR THE FIRST QUARTER		67.00	100.00	56.67	25.00
		WEIGHTED AVERAGE FOR THE YEAR		67.00	100.00	56.67	25.00
===== 203-00040		Uncl Excav (Spec)		Cubic Yard	=====		
ER119A-065		PR SH 119A BOULDER CANYON	01/03/19	2,554.00	20.00	32.72	23.00
STA119A-069		SH 119: NEDERLAND - EAST					
		WEIGHTED AVERAGE FOR THE FIRST QUARTER		2,554.00	20.00	32.72	23.00
		WEIGHTED AVERAGE FOR THE YEAR		2,554.00	20.00	32.72	23.00
===== 203-00050		Unsuitable Material		Cubic Yard	=====		
ER119A-065		PR SH 119A BOULDER CANYON	01/03/19	100.00	28.00	61.45	47.50
STA119A-069		SH 119: NEDERLAND - EAST					
STR0132-021		SH 13-MOFFAT COUNTY-CR 3 SOUT	01/10/19	10,000.00	20.00	7.85	10.60
STR0241-062		US 24 143.4 - 148	01/24/19	100.00	40.00	57.00	25.00
ER072A-040		PR SH72A FLOOD PERMANENT REPA	01/31/19	500.00	40.00	42.18	35.00
NHPP072A-041		PR SH72A FLOOD PERMANENT REPA					
NHPP070A-028		FALL RIVER ROAD BRIDGE	02/21/19	50.00	45.00	28.94	18.00
STA0131-070 HMA ALT		SH 13 CR 5 NORTH AND SOUTH	03/28/19	24,000.00	12.00	12.37	7.10

PROJECT NUMBER	ITEM NUMBER/ PROJECT LOCATION	ITEM DESCRIPTION/ PROJECT LOCATION	DATE LET	UNIT/ QUANTITY	ENGR. EST.	AVERAGE BID	AWARDED BID
===== 203-00050							
STA0131-070 PCCP ALT		Unsuitable Material SH 13 CR 5 NORTH AND SOUTH		Cubic Yard			
		WEIGHTED AVERAGE FOR THE FIRST QUARTER		34,750.00	14.88	12.44	9.53
NHPP0703-445		I-70 WESTBOUND PEAK PERIOD SH 04/25/19		250.00	400.00	58.48	40.00
C2571-013		SH257 & 392:WINDSOR CURB RAMP 05/02/19		52.00	60.00	84.33	75.00
FSA0703-454		EB I-70 AUX LANE WARD TO KIPL 05/16/19		100.00	25.00	63.33	25.00
		WEIGHTED AVERAGE FOR THE SECOND QUARTER		402.00	262.74	63.03	40.80
		WEIGHTED AVERAGE FOR THE YEAR		35,152.00	17.71	12.91	10.07
===== 203-00060							
		Emb Matl (CIP)		Cubic Yard			
IM0251-351		I-25 South of Pueblo MP 79.6 01/03/19		1,401.00	60.00	48.02	37.62
STR0132-021		SH 13-MOFFAT COUNTY-CR 3 SOUT 01/10/19		93,297.00	17.00	14.70	12.20
FBR0341-087		US 34 OVER NORTH FORK CO RIVE 01/10/19		1,349.00	200.00	46.56	41.04
NHPP0701-241		I-70 TRUCK PARKING GARFIELD C 01/17/19		4,477.00	22.00	47.63	65.00
STR0241-062		US 24 143.4 - 148 01/24/19		776.00	35.00	90.67	94.00
STA067A-038		SH 67 SEDALIA RESURFACING 01/31/19		293.00	45.00	45.82	45.00
NH2871-035		US 287 PASSING LANES SOUTH OF 02/07/19		17,067.00	12.00	24.71	17.75
NHPP145A-065		SH 145 PASSING LANES AT DEEP 02/14/19		13,627.00	25.00	44.41	40.00
NHPP1601-073		US 160 PASSING LANE NORTH OF 03/07/19		14,799.00	12.00	16.50	17.00
FBR0253-247		I25 AT VINE DRIVE BRIDGE REPL 03/07/19		25,053.00	17.50	24.64	17.00
NHPP006A-058		US 6 LOVELAND PASS - I-70 (FY 03/07/19		77.00	30.00	78.82	81.64
NHPP0503-087		US 50 PASSING LANES EAST OF S 03/21/19		19,921.00	14.00	28.50	25.00
SHE 0252-481		I-25 RAMP METER INSTALLATION 03/21/19		560.00	22.00	50.33	72.00
STM0242-077		US24 - 8TH ST TO WEST OF MANI 03/28/19		329.00	15.00	44.33	55.00
STA0131-070 HMA ALT		SH 13 CR 5 NORTH AND SOUTH 03/28/19		504,419.00	10.00	9.84	5.65
STA0131-070 PCCP ALT		SH 13 CR 5 NORTH AND SOUTH					
		WEIGHTED AVERAGE FOR THE FIRST QUARTER		697,445.00	12.31	14.77	11.58
IM0252-472		I-25 CABLE BARRIER PHASE III 04/04/19		18,782.00	11.00	31.50	23.00
FBR0063-057		US-6 F-09-K BRIDGE OVER CASTL 05/30/19		9,284.00	25.00	60.25	49.00
STRR200-257		ROAD CLOSURE GATES ON VARIOUS 05/30/19		16.00	55.00	87.00	100.00
ER145A-081		SH 145 MP 21 EMERGENCY ROCKFA 06/07/19		304.00	12.00	64.19	51.00
NHPP0703-442		I-70 SILVERPLUME SOUNDWALL AN 06/13/19		80.00	40.00	71.13	87.00
NHPP030A-036		SH 30 & TOWER RD IMPROVEMENTS 06/13/19		6.00	50.00	80.00	80.00
CR500-205		R5 GUARDRAIL END TREATMENT EA 06/13/19		90.00	80.00	255.00	255.00

COLORADO DEPARTMENT OF TRANSPORTATION
ITEM UNIT COSTS BY PROJECTS -- 2019 COST DATA

13:44 Wednesday, August 7, 2019 43

PROJECT NUMBER	ITEM NUMBER/ PROJECT LOCATION	ITEM DESCRIPTION/ PROJECT LOCATION	DATE LET	UNIT/ QUANTITY	ENGR. EST.	AVERAGE BID	AWARDED BID
===== 203-00060		Emb Matl (CIP)		Cubic Yard			
NHPP160A-030		US160 MM 43.2, 150.4, 156.3,	06/20/19	145.00	50.00	77.50	105.00
	WEIGHTED AVERAGE FOR THE SECOND QUARTER			28,707.00	16.07	42.13	33.08
	WEIGHTED AVERAGE FOR THE YEAR			726,152.00	12.45	15.39	12.89
===== 203-00062		Emb Matl (CIP) (Spec)		Cubic Yard			
SHE 0252-481		I-25 RAMP METER INSTALLATION	03/21/19	412.00	20.00	59.67	90.00
	WEIGHTED AVERAGE FOR THE FIRST QUARTER			412.00	20.00	59.67	90.00
FSA0252-468		I-25 AND PLUM CREEK IMPROVEME	04/18/19	809.00	20.00	75.65	82.60
FSA0703-454		EB I-70 AUX LANE WARD TO KIPL	05/16/19	921.00	20.00	47.21	10.00
	WEIGHTED AVERAGE FOR THE SECOND QUARTER			1,730.00	20.00	62.55	43.95
	WEIGHTED AVERAGE FOR THE YEAR			2,142.00	20.00	62.06	52.81
===== 203-00066		Emb Matl (CIP) (R40)		Cubic Yard			
FSA0142-068		SH 14 & WCR 33 INTERSECTION I	01/03/19	41.00	75.00	248.50	115.00
FBR0253-247		I25 AT VINE DRIVE BRIDGE REPL	03/07/19	9,114.00	20.00	27.65	23.00
SHE 0252-481		I-25 RAMP METER INSTALLATION	03/21/19	488.00	20.00	63.67	90.00
	WEIGHTED AVERAGE FOR THE FIRST QUARTER			9,643.00	20.23	28.52	26.78
	WEIGHTED AVERAGE FOR THE YEAR			9,643.00	20.23	28.52	26.78
===== 203-00100		Muck Excav		Cubic Yard			
ER119A-065		PR SH 119A BOULDER CANYON	01/03/19	3,736.00	40.00	51.07	45.00
STA119A-069		SH 119: NEDERLAND - EAST					
FBR0341-087		US 34 OVER NORTH FORK CO RIVE	01/10/19	300.00	37.00	17.18	12.74
NHPP145A-065		SH 145 PASSING LANES AT DEEP	02/14/19	50.00	50.00	85.17	130.00
NHPP1601-073		US 160 PASSING LANE NORTH OF	03/07/19	500.00	36.00	44.00	28.00
FBR0253-247		I25 AT VINE DRIVE BRIDGE REPL	03/07/19	200.00	35.00	26.05	40.00
C R100-315		R1 ADA CURB RAMPS - PH 5	03/07/19	900.00	35.00	53.00	48.00
	WEIGHTED AVERAGE FOR THE FIRST QUARTER			5,686.00	38.61	48.06	42.85

PROJECT NUMBER	ITEM NUMBER/ PROJECT LOCATION	ITEM DESCRIPTION/ PROJECT LOCATION	DATE LET	UNIT/ QUANTITY	ENGR. EST.	AVERAGE BID	AWARDED BID
=====	203-00100	Muck Excav		Cubic Yard	=====		
	STMC430-020	ADA RAMPS DIVIDE ESB	05/23/19	5.00	200.00	50.00	50.00
	FBR0063-057	US-6 F-09-K BRIDGE OVER CASTL	05/30/19	50.00	25.00	34.38	44.75
	NHPP030A-036	SH 30 & TOWER RD IMPROVEMENTS	06/13/19	200.00	50.00	74.00	74.00
		WEIGHTED AVERAGE FOR THE SECOND QUARTER		255.00	48.04	60.61	67.79
		WEIGHTED AVERAGE FOR THE YEAR		5,941.00	39.02	48.17	43.92
=====	203-00400	Rock Excav		Cubic Yard	=====		
	ER119A-065	PR SH 119A BOULDER CANYON	01/03/19	46,620.00	65.00	71.65	48.00
	STA119A-069	SH 119: NEDERLAND - EAST					
	STR0241-062	US 24 143.4 - 148	01/24/19	170.00	90.00	75.17	60.00
	ER072A-040	PR SH72A FLOOD PERMANENT REPA	01/31/19	451.00	45.00	91.83	48.00
	NHPP072A-041	PR SH72A FLOOD PERMANENT REPA					
	NHPP145A-065	SH 145 PASSING LANES AT DEEP	02/14/19	200.00	50.00	103.94	96.00
		WEIGHTED AVERAGE FOR THE FIRST QUARTER		47,441.00	64.84	72.03	48.25
		WEIGHTED AVERAGE FOR THE YEAR		47,441.00	64.84	72.03	48.25
=====	203-00440	Rock Excav (Spec)		Cubic Yard	=====		
	NHPP0703-445	I-70 WESTBOUND PEAK PERIOD SH	04/25/19	20.00	800.00	418.08	404.00
		WEIGHTED AVERAGE FOR THE SECOND QUARTER		20.00	800.00	418.08	404.00
		WEIGHTED AVERAGE FOR THE YEAR		20.00	800.00	418.08	404.00
=====	203-00598	Rock Scaling		Hour	=====		
	ER119A-065	PR SH 119A BOULDER CANYON	01/03/19	375.00	250.00	174.63	115.00
	STA119A-069	SH 119: NEDERLAND - EAST					
	STR0241-062	US 24 143.4 - 148	01/24/19	100.00	85.00	208.33	230.00
		WEIGHTED AVERAGE FOR THE FIRST QUARTER		475.00	215.26	177.69	139.21
	NHPP0703-445	I-70 WESTBOUND PEAK PERIOD SH	04/25/19	320.00	250.00	180.19	198.00
		WEIGHTED AVERAGE FOR THE SECOND QUARTER		320.00	250.00	180.19	198.00
		WEIGHTED AVERAGE FOR THE YEAR		795.00	229.25	178.25	162.87

COLORADO DEPARTMENT OF TRANSPORTATION
 ITEM UNIT COSTS BY PROJECTS -- 2019 COST DATA

13:44 Wednesday, August 7, 2019 45

PROJECT NUMBER	ITEM NUMBER/ PROJECT LOCATION	ITEM DESCRIPTION/ PROJECT LOCATION	DATE LET	UNIT/ QUANTITY	ENGR. EST.	AVERAGE BID	AWARDED BID
=====	203-01020	Compaction (AASHTO T 99)		Cubic Yard	=====		
NHPP030A-036		SH 30 & TOWER RD IMPROVEMENTS	06/13/19	1,562.00	15.00	40.00	40.00
		WEIGHTED AVERAGE FOR THE SECOND QUARTER		1,562.00	15.00	40.00	40.00
		WEIGHTED AVERAGE FOR THE YEAR		1,562.00	15.00	40.00	40.00
=====	203-01100	Proof Rolling		Hour	=====		
ER119A-065		PR SH 119A BOULDER CANYON	01/03/19	40.00	105.00	120.83	85.00
STA119A-069		SH 119: NEDERLAND - EAST					
STR0132-021		SH 13-MOFFAT COUNTY-CR 3 SOUT	01/10/19	40.00	90.00	165.80	182.00
NH2871-035		US 287 PASSING LANES SOUTH OF	02/07/19	10.00	100.00	109.27	117.15
NHPP145A-065		SH 145 PASSING LANES AT DEEP	02/14/19	20.00	200.00	130.09	81.00
NHPP070A-028		FALL RIVER ROAD BRIDGE	02/21/19	10.00	130.00	100.89	100.00
NHPP0503-087		US 50 PASSING LANES EAST OF S	03/21/19	40.00	140.00	80.00	110.00
NHPP2254-089		I-225 RESURFACING FROM I-25 T	03/21/19	20.00	175.00	83.02	90.00
STA0131-070 HMA ALT		SH 13 CR 5 NORTH AND SOUTH	03/28/19	360.00	120.00	129.04	100.00
STA0131-070 PCCP ALT		SH 13 CR 5 NORTH AND SOUTH					
		WEIGHTED AVERAGE FOR THE FIRST QUARTER		540.00	122.96	126.94	107.42
		WEIGHTED AVERAGE FOR THE YEAR		540.00	122.96	126.94	107.42
=====	203-01140	Rolling		Hour	=====		
STR0241-062		US 24 143.4 - 148	01/24/19	20.00	120.00	100.00	100.00
NHPP1601-073		US 160 PASSING LANE NORTH OF	03/07/19	20.00	150.00	115.00	130.00
NHPP0503-087		US 50 PASSING LANES EAST OF S	03/21/19	20.00	120.00	70.00	90.00
		WEIGHTED AVERAGE FOR THE FIRST QUARTER		60.00	130.00	95.71	106.67
SHE0701-243		I-70 EXIT 26 DDI MODIFICATION	05/16/19	10.00	100.00	86.75	50.00
		WEIGHTED AVERAGE FOR THE SECOND QUARTER		10.00	100.00	86.75	50.00
		WEIGHTED AVERAGE FOR THE YEAR		70.00	125.71	93.72	98.57
=====	203-01500	Blading		Hour	=====		
STAR200-242		R2 NORTH PROGRAM WALL REPAIRS	01/03/19	40.00	130.00	184.14	200.00

PROJECT NUMBER	ITEM NUMBER/ PROJECT LOCATION	ITEM DESCRIPTION/ PROJECT LOCATION	DATE LET	UNIT/ QUANTITY	ENGR. EST.	AVERAGE BID	AWARDED BID
===== 203-01500 Blading Hour =====							
STR0132-021		SH 13-MOFFAT COUNTY-CR 3 SOUT	01/10/19	200.00	150.00	163.80	180.00
FBR0341-087		US 34 OVER NORTH FORK CO RIVE	01/10/19	40.00	150.00	136.73	125.84
STR141A-047		SH 141 MP 120-143 MESA COUNTY	01/17/19	150.00	140.00	125.38	90.00
NHPP0701-241		I-70 TRUCK PARKING GARFIELD C	01/17/19	20.00	145.00	163.39	185.00
STR0241-062		US 24 143.4 - 148	01/24/19	60.00	160.00	129.33	150.00
ER072A-040		PR SH72A FLOOD PERMANENT REPA	01/31/19	200.00	180.00	160.46	220.00
NHPP072A-041		PR SH72A FLOOD PERMANENT REPA					
STA067A-038		SH 67 SEDALIA RESURFACING	01/31/19	10.00	180.00	199.06	150.00
NHPP0821-107		SH 82 GLENWOOD SPRINGS TO CA	02/07/19	20.00	150.00	107.50	125.00
NH2871-035		US 287 PASSING LANES SOUTH OF	02/07/19	50.00	150.00	162.85	132.15
NHPP145A-065		SH 145 PASSING LANES AT DEEP	02/14/19	40.00	200.00	135.21	92.00
NHPP070A-028		FALL RIVER ROAD BRIDGE	02/21/19	20.00	180.00	160.46	180.00
NHPP1601-073		US 160 PASSING LANE NORTH OF	03/07/19	20.00	160.00	126.50	113.00
FBR0253-247		I25 AT VINE DRIVE BRIDGE REPL	03/07/19	20.00	140.00	139.60	115.00
NHPP006A-058		US 6 LOVELAND PASS - I-70 (FY	03/07/19	60.00	150.00	170.25	190.50
NHPP0702-378		I-70 OFFICERS GULCH TO FRISCO	03/14/19	40.00	150.00	124.58	153.75
NHPP050A-033		US50 West of Delta EB Lanes R	03/14/19	125.00	150.00	117.67	123.00
NHPP0503-087		US 50 PASSING LANES EAST OF S	03/21/19	60.00	150.00	95.00	140.00
NHPP2254-089		I-225 RESURFACING FROM I-25 T	03/21/19	20.00	200.00	167.26	150.00
STM0242-077		US24 - 8TH ST TO WEST OF MANI	03/28/19	20.00	150.00	161.67	135.00
STA0131-070 HMA ALT		SH 13 CR 5 NORTH AND SOUTH	03/28/19	320.00	140.00	196.36	215.00
STA0131-070 PCCP ALT		SH 13 CR 5 NORTH AND SOUTH					
WEIGHTED AVERAGE FOR THE FIRST QUARTER				1,535.00	153.19	156.27	162.28
=====							
IM0252-472		I-25 CABLE BARRIER PHASE III	04/04/19	160.00	100.00	125.00	100.00
BR071A-020		REPLACEMENT OF STRUCTURE L-22	04/18/19	40.00	134.00	146.67	100.00
SHE0701-243		I-70 EXIT 26 DDI MODIFICATION	05/16/19	10.00	150.00	103.00	50.00
FBR0063-057		US-6 F-09-K BRIDGE OVER CASTL	05/30/19	40.00	150.00	112.75	101.50
NHPP160A-030		US160 MM 43.2, 150.4, 156.3,	06/20/19	10.00	140.00	142.50	160.00
WEIGHTED AVERAGE FOR THE SECOND QUARTER				260.00	116.38	126.88	100.62
=====							
WEIGHTED AVERAGE FOR THE YEAR				1,795.00	147.86	154.09	152.47
=====							
===== 203-01510 Backhoe Hour =====							
STAR200-242		R2 NORTH PROGRAM WALL REPAIRS	01/03/19	40.00	130.00	116.50	104.00
ER119A-065		PR SH 119A BOULDER CANYON	01/03/19	960.00	120.00	134.16	110.00
STA119A-069		SH 119: NEDERLAND - EAST					
STR0132-021		SH 13-MOFFAT COUNTY-CR 3 SOUT	01/10/19	40.00	90.00	120.20	125.00
FBR0341-087		US 34 OVER NORTH FORK CO RIVE	01/10/19	20.00	170.00	140.52	125.84
STR141A-047		SH 141 MP 120-143 MESA COUNTY	01/17/19	15.00	140.00	101.67	75.00

PROJECT NUMBER	ITEM NUMBER/ PROJECT LOCATION	ITEM DESCRIPTION/ PROJECT LOCATION	DATE LET	UNIT/ QUANTITY	ENGR. EST.	AVERAGE BID	AWARDED BID
===== 203-01510 Backhoe Hour =====							
NHPP0701-241		I-70 TRUCK PARKING GARFIELD C	01/17/19	20.00	150.00	126.07	180.00
STR0241-062		US 24 143.4 - 148	01/24/19	60.00	150.00	138.00	200.00
ER072A-040		PR SH72A FLOOD PERMANENT REPA	01/31/19	200.00	170.00	124.93	88.00
NHPP072A-041		PR SH72A FLOOD PERMANENT REPA					
NHPP0741-022		SH 74: I-70 TO CR 65 RESURFAC	02/14/19	10.00	200.00	147.94	140.00
NHPP1601-073		US 160 PASSING LANE NORTH OF	03/07/19	40.00	200.00	145.00	130.00
FBR0253-247		I25 AT VINE DRIVE BRIDGE REPL	03/07/19	20.00	125.00	128.90	75.00
NHPP006A-058		US 6 LOVELAND PASS - I-70 (FY	03/07/19	10.00	175.00	148.04	136.07
NHPP0503-087		US 50 PASSING LANES EAST OF S	03/21/19	40.00	130.00	100.00	150.00
STA0131-070 HMA ALT		SH 13 CR 5 NORTH AND SOUTH	03/28/19	360.00	140.00	160.33	123.00
STA0131-070 PCCP ALT		SH 13 CR 5 NORTH AND SOUTH					
		WEIGHTED AVERAGE FOR THE FIRST QUARTER		1,835.00	133.71	134.03	114.32
IM0252-472		I-25 CABLE BARRIER PHASE III	04/04/19	160.00	50.00	125.00	50.00
BR071A-020		REPLACEMENT OF STRUCTURE L-22	04/18/19	40.00	163.00	145.00	100.00
NHPP0703-445		I-70 WESTBOUND PEAK PERIOD SH	04/25/19	200.00	180.00	150.21	75.00
FBR0063-057		US-6 F-09-K BRIDGE OVER CASTL	05/30/19	30.00	150.00	126.00	85.00
ER145A-081		SH 145 MP 21 EMERGENCY ROCKFA	06/07/19	20.00	200.00	131.04	98.00
		WEIGHTED AVERAGE FOR THE SECOND QUARTER		450.00	131.16	140.64	70.02
		WEIGHTED AVERAGE FOR THE YEAR		2,285.00	133.20	134.59	104.85
===== 203-01515 Backhoe (Landscaping) Hour =====							
FBR0341-087		US 34 OVER NORTH FORK CO RIVE	01/10/19	2.00	185.00	175.07	125.84
		WEIGHTED AVERAGE FOR THE FIRST QUARTER		2.00	185.00	175.07	125.84
STR 141A-040		R5 YEAR 4 BRDG PREV MAINT RAM	06/20/19	7.00	180.00	270.00	90.00
		WEIGHTED AVERAGE FOR THE SECOND QUARTER		7.00	180.00	270.00	90.00
		WEIGHTED AVERAGE FOR THE YEAR		9.00	181.11	226.19	97.96
===== 203-01550 Dozing Hour =====							
STAR200-242		R2 NORTH PROGRAM WALL REPAIRS	01/03/19	40.00	155.00	202.14	236.00

PROJECT NUMBER	ITEM NUMBER/ PROJECT LOCATION	ITEM DESCRIPTION/ PROJECT LOCATION	DATE LET	UNIT/ QUANTITY	ENGR. EST.	AVERAGE BID	AWARDED BID
===== 203-01550 Dozing Hour =====							
STR0132-021		SH 13-MOFFAT COUNTY-CR 3 SOUT	01/10/19	40.00	150.00	185.40	210.00
FBR0341-087		US 34 OVER NORTH FORK CO RIVE	01/10/19	40.00	165.00	148.99	125.84
STR0241-062		US 24 143.4 - 148	01/24/19	60.00	180.00	208.33	200.00
ER072A-040		PR SH72A FLOOD PERMANENT REPA	01/31/19	200.00	150.00	159.50	130.00
NHPP072A-041		PR SH72A FLOOD PERMANENT REPA					
NHPP1601-073		US 160 PASSING LANE NORTH OF	03/07/19	40.00	180.00	180.00	190.00
FBR0253-247		I25 AT VINE DRIVE BRIDGE REPL	03/07/19	20.00	150.00	154.12	120.00
NHPP0503-087		US 50 PASSING LANES EAST OF S	03/21/19	40.00	150.00	115.00	180.00
STA0131-070 HMA ALT		SH 13 CR 5 NORTH AND SOUTH	03/28/19	320.00	150.00	219.75	196.00
STA0131-070 PCCP ALT		SH 13 CR 5 NORTH AND SOUTH					
WEIGHTED AVERAGE FOR THE FIRST QUARTER				800.00	154.75	175.17	170.99
=====							
IM0252-472		I-25 CABLE BARRIER PHASE III	04/04/19	60.00	100.00	150.00	100.00
BR071A-020		REPLACEMENT OF STRUCTURE L-22	04/18/19	40.00	193.00	170.00	100.00
NHPP0703-445		I-70 WESTBOUND PEAK PERIOD SH	04/25/19	720.00	150.00	163.39	98.00
FBR0063-057		US-6 F-09-K BRIDGE OVER CASTL	05/30/19	20.00	200.00	177.25	212.50
ER145A-081		SH 145 MP 21 EMERGENCY ROCKFA	06/07/19	20.00	180.00	160.49	151.00
WEIGHTED AVERAGE FOR THE SECOND QUARTER				860.00	150.37	163.24	102.13
WEIGHTED AVERAGE FOR THE YEAR				1,660.00	152.48	170.90	131.51
=====							
===== 203-01555 Dozing (Landscaping) Hour =====							
FBR0341-087		US 34 OVER NORTH FORK CO RIVE	01/10/19	2.00	190.00	221.61	150.80
WEIGHTED AVERAGE FOR THE FIRST QUARTER				2.00	190.00	221.61	150.80
=====							
STR 141A-040		R5 YEAR 4 BRDG PREV MAINT RAM	06/20/19	7.00	150.00	325.00	200.00
WEIGHTED AVERAGE FOR THE SECOND QUARTER				7.00	150.00	325.00	200.00
WEIGHTED AVERAGE FOR THE YEAR				9.00	158.89	277.28	189.07
=====							
===== 203-01565 Hydraulic Excavator Hour =====							
STR0132-021		SH 13-MOFFAT COUNTY-CR 3 SOUT	01/10/19	40.00	175.00	185.60	210.00

COLORADO DEPARTMENT OF TRANSPORTATION
ITEM UNIT COSTS BY PROJECTS -- 2019 COST DATA

13:44 Wednesday, August 7, 2019 49

PROJECT NUMBER	ITEM NUMBER/ PROJECT LOCATION	ITEM DESCRIPTION/ PROJECT LOCATION	DATE LET	UNIT/ QUANTITY	ENGR. EST.	AVERAGE BID	AWARDED BID
===== 203-01565		Hydraulic Excavator		Hour =====			
ER072A-040		PR SH72A FLOOD PERMANENT REPA	01/31/19	200.00	135.00	167.19	140.00
NHPP072A-041		PR SH72A FLOOD PERMANENT REPA					
NHPP145A-065		SH 145 PASSING LANES AT DEEP	02/14/19	40.00	200.00	155.12	103.00
		WEIGHTED AVERAGE FOR THE FIRST QUARTER		280.00	150.00	167.64	144.71
ER145A-081		SH 145 MP 21 EMERGENCY ROCKFA	06/07/19	150.00	150.00	223.41	177.00
NHPP160A-030		US160 MM 43.2, 150.4, 156.3,	06/20/19	40.00	190.00	145.00	165.00
		WEIGHTED AVERAGE FOR THE SECOND QUARTER		190.00	158.42	206.90	174.47
		WEIGHTED AVERAGE FOR THE YEAR		470.00	153.40	172.34	156.74
===== 203-01580		Truck		Hour =====			
NHPP0702-378		I-70 OFFICERS GULCH TO FRISCO	03/14/19	40.00	125.00	97.42	92.25
		WEIGHTED AVERAGE FOR THE FIRST QUARTER		40.00	125.00	97.42	92.25
		WEIGHTED AVERAGE FOR THE YEAR		40.00	125.00	97.42	92.25
===== 203-01582		Truck (Dump)		Hour =====			
STR0132-021		SH 13-MOFFAT COUNTY-CR 3 SOUT	01/10/19	40.00	100.00	100.62	117.00
STR0241-062		US 24 143.4 - 148	01/24/19	60.00	110.00	107.00	100.00
ER072A-040		PR SH72A FLOOD PERMANENT REPA	01/31/19	200.00	125.00	119.38	160.00
NHPP072A-041		PR SH72A FLOOD PERMANENT REPA					
NHPP0821-107		SH 82 GLENWOOD SPRINGS TO CA	02/07/19	20.00	120.00	90.00	95.00
		WEIGHTED AVERAGE FOR THE FIRST QUARTER		320.00	118.75	116.84	139.31
NHPP0703-445		I-70 WESTBOUND PEAK PERIOD SH	04/25/19	500.00	300.00	144.30	116.00
SHE0701-243		I-70 EXIT 26 DDI MODIFICATION	05/16/19	10.00	100.00	86.25	50.00
ER145A-081		SH 145 MP 21 EMERGENCY ROCKFA	06/07/19	20.00	115.00	142.80	144.00
NHPP160A-030		US160 MM 43.2, 150.4, 156.3,	06/20/19	30.00	120.00	116.88	115.00
		WEIGHTED AVERAGE FOR THE SECOND QUARTER		560.00	280.18	141.85	115.77
		WEIGHTED AVERAGE FOR THE YEAR		880.00	221.48	126.04	124.33

COLORADO DEPARTMENT OF TRANSPORTATION
 ITEM UNIT COSTS BY PROJECTS -- 2019 COST DATA

13:44 Wednesday, August 7, 2019 50

PROJECT NUMBER	ITEM NUMBER/ PROJECT LOCATION	ITEM DESCRIPTION/ PROJECT LOCATION	DATE LET	UNIT/ QUANTITY	ENGR. EST.	AVERAGE BID	AWARDED BID
=====	203-01590	Front End Loader (Rubber)		Hour	=====		
STR0132-021		SH 13-MOFFAT COUNTY-CR 3 SOUT	01/10/19	40.00	150.00	162.20	200.00
STR0241-062		US 24 143.4 - 148	01/24/19	30.00	140.00	138.33	130.00
C R100-315		R1 ADA CURB RAMPS - PH 5	03/07/19	20.00	130.00	142.50	100.00
		WEIGHTED AVERAGE FOR THE FIRST QUARTER		90.00	142.22	153.30	154.44
NHPP0703-445		I-70 WESTBOUND PEAK PERIOD SH	04/25/19	500.00	175.00	127.11	90.00
SHE0701-243		I-70 EXIT 26 DDI MODIFICATION	05/16/19	10.00	150.00	102.00	50.00
ER145A-081		SH 145 MP 21 EMERGENCY ROCKFA	06/07/19	20.00	125.00	159.68	141.00
		WEIGHTED AVERAGE FOR THE SECOND QUARTER		530.00	172.64	127.30	91.17
		WEIGHTED AVERAGE FOR THE YEAR		620.00	168.23	131.79	100.35
=====	203-01594	Combination Loader		Hour	=====		
ER119A-065		PR SH 119A BOULDER CANYON	01/03/19	60.00	125.00	124.15	65.00
STA119A-069		SH 119: NEDERLAND - EAST					
FBR0341-087		US 34 OVER NORTH FORK CO RIVE	01/10/19	20.00	120.00	111.33	125.84
ER072A-040		PR SH72A FLOOD PERMANENT REPA	01/31/19	200.00	175.00	127.15	190.00
NHPP072A-041		PR SH72A FLOOD PERMANENT REPA					
NHPP0821-107		SH 82 GLENWOOD SPRINGS TO CA	02/07/19	20.00	120.00	130.00	115.00
NHPP145A-065		SH 145 PASSING LANES AT DEEP	02/14/19	40.00	150.00	123.65	98.00
NHPP070A-028		FALL RIVER ROAD BRIDGE	02/21/19	60.00	175.00	120.02	110.00
NHPP1601-073		US 160 PASSING LANE NORTH OF	03/07/19	100.00	150.00	113.00	96.00
FBR0253-247		I25 AT VINE DRIVE BRIDGE REPL	03/07/19	20.00	120.00	105.22	75.00
SHE2254-090		Colfax & I-225, Colfax & Cham	03/07/19	8.00	180.00	125.00	120.00
NHPP0702-378		I-70 OFFICERS GULCH TO FRISCO	03/14/19	40.00	125.00	111.00	123.00
NHPP0503-087		US 50 PASSING LANES EAST OF S	03/21/19	40.00	120.00	80.00	110.00
STM0242-077		US24 - 8TH ST TO WEST OF MANI	03/28/19	20.00	120.00	111.67	75.00
STA0131-070 HMA ALT		SH 13 CR 5 NORTH AND SOUTH	03/28/19	360.00	120.00	148.95	164.00
STA0131-070 PCCP ALT		SH 13 CR 5 NORTH AND SOUTH					
		WEIGHTED AVERAGE FOR THE FIRST QUARTER		988.00	139.72	127.74	135.69
IM0252-472		I-25 CABLE BARRIER PHASE III	04/04/19	60.00	75.00	112.50	100.00
BR071A-020		REPLACEMENT OF STRUCTURE L-22	04/18/19	40.00	120.00	124.00	100.00
CR300-248		CRAIG RESIDENCY ADA RAMPS	05/16/19	10.00	125.00	101.67	25.00

PROJECT NUMBER	ITEM NUMBER/ PROJECT LOCATION	ITEM DESCRIPTION/ PROJECT LOCATION	DATE LET	UNIT/ QUANTITY	ENGR. EST.	AVERAGE BID	AWARDED BID
===== 203-01594							
		Combination Loader		Hour			
SHE0701-243		I-70 EXIT 26 DDI MODIFICATION	05/16/19	10.00	100.00	94.50	50.00
FBR0063-057		US-6 F-09-K BRIDGE OVER CASTL	05/30/19	50.00	120.00	108.75	108.50
ER145A-081		SH 145 MP 21 EMERGENCY ROCKFA	06/07/19	20.00	150.00	159.68	141.00
NHPP0703-442		I-70 SILVERPLUME SOUNDWALL AN	06/13/19	40.00	180.00	125.73	204.00
CR500-205		R5 GUARDRAIL END TREATMENT EA	06/13/19	20.00	120.00	95.00	95.00
STR 141A-040		R5 YEAR 4 BRDG PREV MAINT RAM	06/20/19	30.00	150.00	230.00	130.00
NHPP160A-030		US160 MM 43.2, 150.4, 156.3,	06/20/19	30.00	120.00	120.00	115.00
		WEIGHTED AVERAGE FOR THE SECOND QUARTER		310.00	123.39	127.04	117.44
		WEIGHTED AVERAGE FOR THE YEAR		1,298.00	135.82	127.64	130.63
===== 203-01597							
		Potholing		Hour			
STAR200-242		R2 NORTH PROGRAM WALL REPAIRS	01/03/19	16.00	200.00	258.61	248.00
NHPPR500-173		US 160_550 DURANGO SIGNALS OP	01/03/19	8.00	300.00	499.50	494.00
SHER100-289		INTERSECTIONS @ SH83 & LONGS	01/03/19	80.00	200.00	226.40	175.00
ER119A-065		PR SH 119A BOULDER CANYON	01/03/19	80.00	162.50	243.91	250.00
STA119A-069		SH 119: NEDERLAND - EAST					
STR0132-021		SH 13-MOFFAT COUNTY-CR 3 SOUT	01/10/19	10.00	300.00	264.60	290.00
FBR0341-087		US 34 OVER NORTH FORK CO RIVE	01/10/19	60.00	240.00	273.38	286.00
STR141A-047		SH 141 MP 120-143 MESA COUNTY	01/17/19	15.00	250.00	256.38	220.00
STR0241-062		US 24 143.4 - 148	01/24/19	80.00	240.00	296.67	280.00
ER072A-040		PR SH72A FLOOD PERMANENT REPA	01/31/19	160.00	265.00	254.19	255.00
NHPP072A-041		PR SH72A FLOOD PERMANENT REPA					
STAM086-075		SH96A ABRIENDO - ORMAN SAFETY	01/31/19	135.00	100.00	285.00	155.00
STA067A-038		SH 67 SEDALIA RESURFACING	01/31/19	20.00	200.00	270.93	300.00
NHPP0821-107		SH 82 GLENWOOD SPRINGS TO CA	02/07/19	120.00	240.00	435.00	445.00
NH2871-035		US 287 PASSING LANES SOUTH OF	02/07/19	10.00	200.00	276.09	367.50
ITSSW01-638		ETHERNET PHASE III (PRIMARYLY	02/07/19	200.00	220.00	115.00	10.00
NHPP145A-065		SH 145 PASSING LANES AT DEEP	02/14/19	40.00	400.00	294.21	385.00
NHPP0741-022		SH 74: I-70 TO CR 65 RESURFAC	02/14/19	20.00	200.00	278.99	265.00
NHPP1601-076		US 160 MANCOS HILL (MP 40.000	02/21/19	8.00	300.00	385.67	550.00
NHPP070A-028		FALL RIVER ROAD BRIDGE	02/21/19	40.00	270.00	275.83	200.00
SHER100-284		FY19 NORTH SIGNAL PKG	02/21/19	75.00	200.00	241.00	180.00
NHPP1601-073		US 160 PASSING LANE NORTH OF	03/07/19	80.00	350.00	367.50	335.00
FBR0253-247		I25 AT VINE DRIVE BRIDGE REPL	03/07/19	20.00	225.00	256.08	245.00
NHPP006A-058		US 6 LOVELAND PASS - I-70 (FY	03/07/19	40.00	250.00	233.86	217.72
C R100-315		R1 ADA CURB RAMPS - PH 5	03/07/19	15.00	200.00	332.50	300.00
SHE2254-090		Colfax & I-225, Colfax & Cham	03/07/19	120.00	200.00	202.50	225.00
NHPP0702-378		I-70 OFFICERS GULCH TO FRISCO	03/14/19	25.00	300.00	261.67	205.00
NHPP050A-033		US50 West of Delta EB Lanes R	03/14/19	20.00	225.00	320.00	220.00
NHPP0503-087		US 50 PASSING LANES EAST OF S	03/21/19	40.00	200.00	245.00	240.00
SHE 0252-481		I-25 RAMP METER INSTALLATION	03/21/19	100.00	200.00	213.00	285.00
SHER100-308		MIDPOINT - SIGNAL CONST PACKA	03/21/19	100.00	260.00	262.50	175.00
NHPP2254-089		I-225 RESURFACING FROM I-25 T	03/21/19	75.00	200.00	287.39	375.00

COLORADO DEPARTMENT OF TRANSPORTATION
 ITEM UNIT COSTS BY PROJECTS -- 2019 COST DATA

13:44 Wednesday, August 7, 2019 52

PROJECT NUMBER	ITEM NUMBER/ PROJECT LOCATION	ITEM DESCRIPTION/ PROJECT LOCATION	DATE LET	UNIT/ QUANTITY	ENGR. EST.	AVERAGE BID	AWARDED BID
===== 203-01597 Potholing Hour =====							
STM0242-077		US24 - 8TH ST TO WEST OF MANI	03/28/19	160.00	215.00	258.00	204.00
STA0131-070 HMA ALT		SH 13 CR 5 NORTH AND SOUTH	03/28/19	100.00	240.00	305.98	262.00
STA0131-070 PCCP ALT		SH 13 CR 5 NORTH AND SOUTH					
WEIGHTED AVERAGE FOR THE FIRST QUARTER				2,072.00	225.27	259.85	233.42
NHPP030A-035		US 285/SH30	04/04/19	100.00	200.00	180.00	180.00
IM0252-472		I-25 CABLE BARRIER PHASE III	04/04/19	120.00	250.00	230.00	260.00
BR071A-020		REPLACEMENT OF STRUCTURE L-22	04/18/19	40.00	230.00	285.00	245.00
FSA0252-468		I-25 AND PLUM CREEK IMPROVEME	04/18/19	40.00	225.00	208.25	219.00
NHPP0703-445		I-70 WESTBOUND PEAK PERIOD SH	04/25/19	500.00	200.00	347.18	219.00
NHPP2851-012		US 285 Antonito to Estrella C	05/02/19	2.00	400.00	450.00	100.00
C2571-013		SH257 & 392:WINDSOR CURB RAMP	05/02/19	20.00	230.00	265.33	200.00
MTCE0641-103		MTCE R3 FY20 SH 64 RANGELY PE	05/02/19	20.00	250.00	357.50	350.00
FSA2873-190		US 287 AND FOOTHILLS PARKWAY	05/02/19	40.00	200.00	360.00	420.00
IM0252-456		I-25 COLORADO SPRINGS RAMP ME	05/16/19	180.00	250.00	224.67	159.00
FSA0703-454		EB I-70 AUX LANE WARD TO KIPL	05/16/19	40.00	200.00	319.29	250.00
CR300-248		CRAIG RESIDENCY ADA RAMPS	05/16/19	10.00	220.00	266.67	150.00
SHE0701-243		I-70 EXIT 26 DDI MODIFICATION	05/16/19	30.00	500.00	288.75	250.00
STMC430-020		ADA RAMPS DIVIDE ESB	05/23/19	40.00	180.00	10.00	10.00
FBR0063-057		US-6 F-09-K BRIDGE OVER CASTL	05/30/19	20.00	250.00	272.50	330.00
ER145A-081		SH 145 MP 21 EMERGENCY ROCKFA	06/07/19	20.00	350.00	347.00	222.00
NHPP0703-442		I-70 SILVERPLUME SOUNDWALL AN	06/13/19	20.00	220.00	260.44	425.00
NHPP030A-036		SH 30 & TOWER RD IMPROVEMENTS	06/13/19	30.00	225.00	250.00	250.00
CR500-205		R5 GUARDRAIL END TREATMENT EA	06/13/19	50.00	400.00	380.00	380.00
STR 141A-040		R5 YEAR 4 BRDG PREV MAINT RAM	06/20/19	20.00	225.00	250.00	170.00
NHPP160A-030		US160 MM 43.2, 150.4, 156.3,	06/20/19	16.00	300.00	337.50	300.00
WEIGHTED AVERAGE FOR THE SECOND QUARTER				1,358.00	233.03	293.02	226.45
WEIGHTED AVERAGE FOR THE YEAR				3,430.00	228.34	270.00	230.62
===== 203-01620 Sweeping Hour =====							
FBR0341-087		US 34 OVER NORTH FORK CO RIVE	01/10/19	50.00	220.00	163.99	101.62
WEIGHTED AVERAGE FOR THE FIRST QUARTER				50.00	220.00	163.99	101.62
FBR0063-057		US-6 F-09-K BRIDGE OVER CASTL	05/30/19	50.00	130.00	145.00	130.00
NHPP160A-030		US160 MM 43.2, 150.4, 156.3,	06/20/19	44.00	150.00	116.25	120.00
WEIGHTED AVERAGE FOR THE SECOND QUARTER				94.00	139.36	131.54	125.32
WEIGHTED AVERAGE FOR THE YEAR				144.00	167.36	151.49	117.09

COLORADO DEPARTMENT OF TRANSPORTATION
 ITEM UNIT COSTS BY PROJECTS -- 2019 COST DATA

13:44 Wednesday, August 7, 2019 53

PROJECT NUMBER	ITEM NUMBER/ PROJECT LOCATION	ITEM DESCRIPTION/ PROJECT LOCATION	DATE LET	UNIT/ QUANTITY	ENGR. EST.	AVERAGE BID	AWARDED BID
=====	203-01622	Sweeping (With Pickup Broom)		Hour	=====	=====	=====
SHER100-284		FY19 NORTH SIGNAL PKG	02/21/19	40.00	175.00	121.33	170.00
NHPP0503-087		US 50 PASSING LANES EAST OF S	03/21/19	20.00	200.00	110.00	170.00
		WEIGHTED AVERAGE FOR THE FIRST QUARTER		60.00	183.33	118.50	170.00
		WEIGHTED AVERAGE FOR THE YEAR		60.00	183.33	118.50	170.00
=====	203-02300	Rock Scaler		Hour	=====	=====	=====
C0502-085		US 50 MM 201.8 MONARCH AVALAN	06/27/19	20.00	250.00	731.50	276.00
		WEIGHTED AVERAGE FOR THE SECOND QUARTER		20.00	250.00	731.50	276.00
		WEIGHTED AVERAGE FOR THE YEAR		20.00	250.00	731.50	276.00
=====	203-02324	Blast Vibration Monitoring		LUMP SUM	=====	=====	=====
ER119A-065		PR SH 119A BOULDER CANYON	01/03/19	1.00	50000.00	103693.79	180000.00
STA119A-069		SH 119: NEDERLAND - EAST					
		WEIGHTED AVERAGE FOR THE FIRST QUARTER		1.00	50000.00	103693.79	180000.00
		WEIGHTED AVERAGE FOR THE YEAR		1.00	50000.00	103693.79	180000.00
=====	203-02330	Laborer		Hour	=====	=====	=====
STAR200-242		R2 NORTH PROGRAM WALL REPAIRS	01/03/19	60.00	40.00	49.67	50.00
ER119A-065		PR SH 119A BOULDER CANYON	01/03/19	60.00	50.00	49.11	35.00
STA119A-069		SH 119: NEDERLAND - EAST					
STR0132-021		SH 13-MOFFAT COUNTY-CR 3 SOUT	01/10/19	100.00	44.00	39.70	45.00
FBR0341-087		US 34 OVER NORTH FORK CO RIVE	01/10/19	120.00	55.00	43.44	39.10
STR141A-047		SH 141 MP 120-143 MESA COUNTY	01/17/19	15.00	45.00	50.97	32.00
NHPP0701-241		I-70 TRUCK PARKING GARFIELD C	01/17/19	60.00	45.00	48.95	50.00
STR0241-062		US 24 143.4 - 148	01/24/19	80.00	50.00	48.17	47.00
ER072A-040		PR SH72A FLOOD PERMANENT REPA	01/31/19	80.00	75.00	50.53	45.00
NHPP072A-041		PR SH72A FLOOD PERMANENT REPA					
NHPP0821-107		SH 82 GLENWOOD SPRINGS TO CA	02/07/19	40.00	48.00	33.50	35.00
NHPP145A-065		SH 145 PASSING LANES AT DEEP	02/14/19	40.00	50.00	49.21	32.00
NHPP0741-022		SH 74: I-70 TO CR 65 RESURFAC	02/14/19	10.00	75.00	57.98	45.00
NHPP070A-028		FALL RIVER ROAD BRIDGE	02/21/19	30.00	75.00	39.36	42.00

PROJECT NUMBER	ITEM NUMBER/ PROJECT LOCATION	ITEM DESCRIPTION/ PROJECT LOCATION	DATE LET	UNIT/ QUANTITY	ENGR. EST.	AVERAGE BID	AWARDED BID
===== 203-02330 Laborer Hour =====							
NHPP1601-073		US 160 PASSING LANE NORTH OF	03/07/19	80.00	60.00	53.00	46.00
FBR0253-247		I25 AT VINE DRIVE BRIDGE REPL	03/07/19	20.00	50.00	42.13	35.00
SHE2254-090		Colfax & I-225, Colfax & Cham	03/07/19	62.00	70.00	49.00	28.00
NHPP0702-378		I-70 OFFICERS GULCH TO FRISCO	03/14/19	40.00	60.00	50.42	51.25
NHPP0503-087		US 50 PASSING LANES EAST OF S	03/21/19	40.00	45.00	42.50	60.00
WEIGHTED AVERAGE FOR THE FIRST QUARTER				937.00	54.47	46.66	42.78
NHPP030A-035		US 285/SH30	04/04/19	50.00	65.00	50.00	50.00
BR071A-020		REPLACEMENT OF STRUCTURE L-22	04/18/19	40.00	40.00	41.67	32.00
NHPP0703-445		I-70 WESTBOUND PEAK PERIOD SH	04/25/19	1,540.00	75.00	51.30	43.00
CR300-248		CRAIG RESIDENCY ADA RAMPS	05/16/19	10.00	50.00	51.67	45.00
FBR0063-057		US-6 F-09-K BRIDGE OVER CASTL	05/30/19	120.00	42.00	33.50	35.00
ER145A-081		SH 145 MP 21 EMERGENCY ROCKFA	06/07/19	60.00	60.00	65.50	53.00
NHPP0703-442		I-70 SILVERPLUME SOUNDWALL AN	06/13/19	40.00	80.00	39.76	36.00
CR500-205		R5 GUARDRAIL END TREATMENT EA	06/13/19	20.00	55.00	69.60	69.60
STR 141A-040		R5 YEAR 4 BRDG PREV MAINT RAM	06/20/19	60.00	50.00	57.50	50.00
NHPP160A-030		US160 MM 43.2, 150.4, 156.3,	06/20/19	24.00	50.00	46.88	50.00
WEIGHTED AVERAGE FOR THE SECOND QUARTER				1,964.00	70.26	50.15	43.21
WEIGHTED AVERAGE FOR THE YEAR				2,901.00	65.16	48.60	43.07
===== 206-00000 Str Excav Cubic Yard =====							
STAR200-242		R2 NORTH PROGRAM WALL REPAIRS	01/03/19	278.00	50.00	48.28	59.00
ER119A-065		PR SH 119A BOULDER CANYON	01/03/19	3,256.00	30.00	43.40	28.00
STA119A-069		SH 119: NEDERLAND - EAST					
FBR0341-087		US 34 OVER NORTH FORK CO RIVE	01/10/19	1,053.00	20.00	18.12	16.29
STR0241-062		US 24 143.4 - 148	01/24/19	75.00	40.00	58.33	65.00
ER072A-040		PR SH72A FLOOD PERMANENT REPA	01/31/19	5,566.00	17.00	30.95	15.00
NHPP072A-041		PR SH72A FLOOD PERMANENT REPA					
STAM086-075		SH96A ABRIENDO - ORMAN SAFETY	01/31/19	215.00	32.00	129.83	94.50
NHPP0821-107		SH 82 GLENWOOD SPRINGS TO CA	02/07/19	300.00	29.00	122.50	190.00
NHPP145A-065		SH 145 PASSING LANES AT DEEP	02/14/19	1,517.00	35.00	32.24	18.00
NHPP070A-028		FALL RIVER ROAD BRIDGE	02/21/19	589.00	34.00	25.37	14.00
NHPP1601-073		US 160 PASSING LANE NORTH OF	03/07/19	1,012.00	27.00	23.50	23.00
FBR0253-247		I25 AT VINE DRIVE BRIDGE REPL	03/07/19	4,390.00	20.00	11.66	8.00
NHPP006A-058		US 6 LOVELAND PASS - I-70 (FY	03/07/19	106.00	35.00	48.32	46.64
NHPP0503-087		US 50 PASSING LANES EAST OF S	03/21/19	323.00	30.00	45.00	40.00
STM0242-077		US24 - 8TH ST TO WEST OF MANI	03/28/19	410.00	40.00	43.67	55.00
WEIGHTED AVERAGE FOR THE FIRST QUARTER				19,090.00	24.30	27.62	22.25

PROJECT NUMBER	ITEM NUMBER/ PROJECT LOCATION	ITEM DESCRIPTION/ PROJECT LOCATION	DATE LET	UNIT/ QUANTITY	ENGR. EST.	AVERAGE BID	AWARDED BID
===== 206-00000		Str Excav		Cubic Yard	=====		
BR071A-020		REPLACEMENT OF STRUCTURE L-22	04/18/19	407.00	30.00	26.00	29.00
NHPP0703-445		I-70 WESTBOUND PEAK PERIOD SH	04/25/19	37,161.00	17.00	24.92	23.00
FBR0063-057		US-6 F-09-K BRIDGE OVER CASTL	05/30/19	5,856.00	20.00	35.44	13.50
ER145A-081		SH 145 MP 21 EMERGENCY ROCKFA	06/07/19	1,005.00	40.00	37.47	33.00
NHPP0703-442		I-70 SILVERPLUME SOUNDWALL AN	06/13/19	844.00	20.00	29.86	33.00
NHPP160A-030		US160 MM 43.2, 150.4, 156.3,	06/20/19	101.00	22.00	49.88	31.00
		WEIGHTED AVERAGE FOR THE SECOND QUARTER		45,374.00	18.08	26.33	22.25
		WEIGHTED AVERAGE FOR THE YEAR		64,464.00	19.92	27.04	22.25
===== 206-00050		Str Bkfl (Spec)		Cubic Yard	=====		
NHPP145A-065		SH 145 PASSING LANES AT DEEP	02/14/19	320.00	130.00	73.19	60.00
		WEIGHTED AVERAGE FOR THE FIRST QUARTER		320.00	130.00	73.19	60.00
NHPP0703-445		I-70 WESTBOUND PEAK PERIOD SH	04/25/19	29,581.00	26.00	73.04	72.00
		WEIGHTED AVERAGE FOR THE SECOND QUARTER		29,581.00	26.00	73.04	72.00
		WEIGHTED AVERAGE FOR THE YEAR		29,901.00	27.11	73.04	71.87
===== 206-00065		Str Bkfl (Flow-Fill)		Cubic Yard	=====		
IM0251-351		I-25 South of Pueblo MP 79.6	01/03/19	5.00	275.00	947.23	991.15
ER119A-065		PR SH 119A BOULDER CANYON	01/03/19	965.00	300.00	188.18	170.00
STA119A-069		SH 119: NEDERLAND - EAST					
STR0132-021		SH 13-MOFFAT COUNTY-CR 3 SOUT	01/10/19	50.20	300.00	300.40	268.00
STR0241-062		US 24 143.4 - 148	01/24/19	569.00	190.00	317.00	400.00
NHPP0741-022		SH 74: I-70 TO CR 65 RESURFAC	02/14/19	0.50	400.00	5042.16	4350.00
SHE 0252-481		I-25 RAMP METER INSTALLATION	03/21/19	6.00	400.00	258.33	190.00
STM0242-077		US24 - 8TH ST TO WEST OF MANI	03/28/19	14.00	200.00	890.00	1750.00
		WEIGHTED AVERAGE FOR THE FIRST QUARTER		1,609.70	260.57	219.30	272.02
NHPP0703-445		I-70 WESTBOUND PEAK PERIOD SH	04/25/19	100.00	200.00	274.14	279.00

PROJECT NUMBER	ITEM NUMBER/ PROJECT LOCATION	ITEM DESCRIPTION/ PROJECT LOCATION	DATE LET	UNIT/ QUANTITY	ENGR. EST.	AVERAGE BID	AWARDED BID
===== 206-00065	STR 141A-040	Str Bkfl (Flow-Fill) R5 YEAR 4 BRDG PREV MAINT RAM	06/20/19	Cubic Yard 64.00	250.00	580.00	600.00
		WEIGHTED AVERAGE FOR THE SECOND QUARTER		164.00	219.51	365.61	404.27
		WEIGHTED AVERAGE FOR THE YEAR		1,773.70	256.78	225.44	284.25
===== 206-00100		Str Bkfl (CL 1)		Cubic Yard			
ER119A-065		PR SH 119A BOULDER CANYON	01/03/19	1,310.00	45.00	53.93	51.00
STA119A-069		SH 119: NEDERLAND - EAST					
FBR0341-087		US 34 OVER NORTH FORK CO RIVE	01/10/19	757.00	45.00	49.65	44.54
ER072A-040		PR SH72A FLOOD PERMANENT REPA	01/31/19	2,110.00	45.00	50.94	34.00
NHPP072A-041		PR SH72A FLOOD PERMANENT REPA					
NHPP070A-028		FALL RIVER ROAD BRIDGE	02/21/19	597.00	34.00	40.43	24.00
NHPP1601-073		US 160 PASSING LANE NORTH OF	03/07/19	134.00	80.00	57.50	63.00
FBR0253-247		I25 AT VINE DRIVE BRIDGE REPL	03/07/19	2,652.00	40.00	39.25	46.00
NHPP006A-058		US 6 LOVELAND PASS - I-70 (FY	03/07/19	80.00	17.00	70.54	61.07
NHPP0503-087		US 50 PASSING LANES EAST OF S	03/21/19	259.00	50.00	62.50	65.00
STM0242-077		US24 - 8TH ST TO WEST OF MANI	03/28/19	229.00	40.00	60.33	70.00
		WEIGHTED AVERAGE FOR THE FIRST QUARTER		8,128.00	42.88	46.49	43.65
BR071A-020		REPLACEMENT OF STRUCTURE L-22	04/18/19	152.00	50.00	116.33	49.00
NHPP0703-445		I-70 WESTBOUND PEAK PERIOD SH	04/25/19	3,907.00	25.00	42.68	42.00
FBR0063-057		US-6 F-09-K BRIDGE OVER CASTL	05/30/19	5,700.00	50.00	71.78	57.00
STR 141A-040		R5 YEAR 4 BRDG PREV MAINT RAM	06/20/19	13.00	60.00	1100.00	200.00
NHPP160A-030		US160 MM 43.2, 150.4, 156.3,	06/20/19	64.00	70.00	170.00	240.00
		WEIGHTED AVERAGE FOR THE SECOND QUARTER		9,836.00	40.21	59.92	52.30
		WEIGHTED AVERAGE FOR THE YEAR		17,964.00	41.42	49.75	48.38
===== 206-00200		Str Bkfl (CL 2)		Cubic Yard			
FBR0341-087		US 34 OVER NORTH FORK CO RIVE	01/10/19	163.00	25.00	32.79	49.49
STR0241-062		US 24 143.4 - 148	01/24/19	110.00	50.00	74.83	50.00
ER072A-040		PR SH72A FLOOD PERMANENT REPA	01/31/19	332.00	20.00	70.65	36.00
NHPP072A-041		PR SH72A FLOOD PERMANENT REPA					
NHPP0821-107		SH 82 GLENWOOD SPRINGS TO CA	02/07/19	76.00	40.00	177.50	195.00
NHPP145A-065		SH 145 PASSING LANES AT DEEP	02/14/19	5,859.00	40.00	43.34	20.00
NHPP070A-028		FALL RIVER ROAD BRIDGE	02/21/19	47.00	40.00	50.46	86.00

COLORADO DEPARTMENT OF TRANSPORTATION
 ITEM UNIT COSTS BY PROJECTS -- 2019 COST DATA

13:44 Wednesday, August 7, 2019 57

PROJECT NUMBER	ITEM NUMBER/ PROJECT LOCATION	ITEM DESCRIPTION/ PROJECT LOCATION	DATE LET	UNIT/ QUANTITY	ENGR. EST.	AVERAGE BID	AWARDED BID
=====	206-00200	Str Bkfl (CL 2)		Cubic Yard	=====		
FBR0253-247		I25 AT VINE DRIVE BRIDGE REPL	03/07/19	17.00	30.00	33.92	20.00
		WEIGHTED AVERAGE FOR THE FIRST QUARTER		6,604.00	38.77	47.01	24.52
BR071A-020		REPLACEMENT OF STRUCTURE L-22	04/18/19	70.00	40.00	34.67	26.00
NHPP0703-445		I-70 WESTBOUND PEAK PERIOD SH	04/25/19	852.00	35.00	56.41	15.00
NHPP0703-442		I-70 SILVERPLUME SOUNDWALL AN	06/13/19	729.00	45.00	33.18	21.00
		WEIGHTED AVERAGE FOR THE SECOND QUARTER		1,651.00	39.63	40.12	18.12
		WEIGHTED AVERAGE FOR THE YEAR		8,255.00	38.94	45.66	23.24
=====	206-00360	Mechanical Reinforcement of Soil		Cubic Yard	=====		
FBR0341-087		US 34 OVER NORTH FORK CO RIVE	01/10/19	656.00	45.00	26.34	18.71
NHPP070A-028		FALL RIVER ROAD BRIDGE	02/21/19	534.00	35.00	27.96	18.00
FBR0253-247		I25 AT VINE DRIVE BRIDGE REPL	03/07/19	1,796.00	28.00	32.71	18.00
		WEIGHTED AVERAGE FOR THE FIRST QUARTER		2,986.00	32.99	31.28	18.16
BR071A-020		REPLACEMENT OF STRUCTURE L-22	04/18/19	152.00	40.00	58.67	45.00
NHPP0703-445		I-70 WESTBOUND PEAK PERIOD SH	04/25/19	16,526.00	30.00	20.69	35.00
FBR0063-057		US-6 F-09-K BRIDGE OVER CASTL	05/30/19	3,060.00	35.00	14.55	15.00
		WEIGHTED AVERAGE FOR THE SECOND QUARTER		19,738.00	30.85	20.33	31.98
		WEIGHTED AVERAGE FOR THE YEAR		22,724.00	31.13	23.82	30.16
=====	206-00510	Filter Matl (CL A)		Cubic Yard	=====		
ER119A-065		PR SH 119A BOULDER CANYON	01/03/19	302.00	60.00	100.29	108.00
STA119A-069		SH 119: NEDERLAND - EAST					
ER072A-040		PR SH72A FLOOD PERMANENT REPA	01/31/19	2,545.00	90.00	73.22	68.00
NHPP072A-041		PR SH72A FLOOD PERMANENT REPA					
		WEIGHTED AVERAGE FOR THE FIRST QUARTER		2,847.00	86.82	75.20	72.24
		WEIGHTED AVERAGE FOR THE YEAR		2,847.00	86.82	75.20	72.24

COLORADO DEPARTMENT OF TRANSPORTATION
 ITEM UNIT COSTS BY PROJECTS -- 2019 COST DATA

13:44 Wednesday, August 7, 2019 58

PROJECT NUMBER	ITEM NUMBER/ PROJECT LOCATION	ITEM DESCRIPTION/ PROJECT LOCATION	DATE LET	UNIT/ QUANTITY	ENGR. EST.	AVERAGE BID	AWARDED BID
=====	206-00520	Filter Matl (CL B)		Cubic Yard	=====		
NHPP070A-028		FALL RIVER ROAD BRIDGE	02/21/19	149.00	125.00	81.37	88.00
NHPP0503-087		US 50 PASSING LANES EAST OF S	03/21/19	12.00	120.00	150.00	140.00
		WEIGHTED AVERAGE FOR THE FIRST QUARTER		161.00	124.63	83.51	91.88
NHPP0703-442		I-70 SILVERPLUME SOUNDWALL AN	06/13/19	411.00	125.00	93.77	110.00
		WEIGHTED AVERAGE FOR THE SECOND QUARTER		411.00	125.00	93.77	110.00
		WEIGHTED AVERAGE FOR THE YEAR		572.00	124.90	91.82	104.90
=====	206-01000	Bed Course Matl		Cubic Yard	=====		
NHPP1601-073		US 160 PASSING LANE NORTH OF	03/07/19	325.00	80.00	74.50	59.00
NHPP006A-058		US 6 LOVELAND PASS - I-70 (FY	03/07/19	4.00	40.00	219.37	238.73
		WEIGHTED AVERAGE FOR THE FIRST QUARTER		329.00	79.51	76.26	61.19
		WEIGHTED AVERAGE FOR THE YEAR		329.00	79.51	76.26	61.19
=====	206-01750	Shoring		LUMP SUM	=====		
STR0241-062		US 24 143.4 - 148	01/24/19	1.00	10000.00	88666.67	6300.00
NHPP070A-028		FALL RIVER ROAD BRIDGE	02/21/19	1.00	34000.00	42342.30	99500.00
		WEIGHTED AVERAGE FOR THE FIRST QUARTER		2.00	22000.00	59713.94	52900.00
		WEIGHTED AVERAGE FOR THE YEAR		2.00	22000.00	59713.94	52900.00
=====	206-01781	Shoring (A 1)		LUMP SUM	=====		
ER119A-065		PR SH 119A BOULDER CANYON	01/03/19	1.00	20000.00	31474.34	18800.00
STA119A-069		SH 119: NEDERLAND - EAST					
ER072A-040		PR SH72A FLOOD PERMANENT REPA	01/31/19	1.00	56000.00	51513.88	20000.00
NHPP072A-041		PR SH72A FLOOD PERMANENT REPA					
NHPP145A-065		SH 145 PASSING LANES AT DEEP	02/14/19	1.00	20000.00	25476.26	25000.00
STM0242-077		US24 - 8TH ST TO WEST OF MANI	03/28/19	1.00	5000.00	16166.67	0.01
		WEIGHTED AVERAGE FOR THE FIRST QUARTER		4.00	24200.00	36045.48	16520.00

PROJECT NUMBER	ITEM NUMBER/ PROJECT LOCATION	ITEM DESCRIPTION/ PROJECT LOCATION	DATE LET	UNIT/ QUANTITY	ENGR. EST.	AVERAGE BID	AWARDED BID
===== 206-01781		Shoring (A 1)		LUMP SUM	=====		
NHPP0703-445		I-70 WESTBOUND PEAK PERIOD SH	04/25/19	1.00	25000.00	181152.00	163456.00
FBR0063-057		US-6 F-09-K BRIDGE OVER CASTL	05/30/19	1.00	45000.00	78412.50	94825.00
NHPP160A-030		US160 MM 43.2, 150.4, 156.3,	06/20/19	1.00	10000.00	5350.00	7700.00
		WEIGHTED AVERAGE FOR THE SECOND QUARTER		3.00	26666.67	101568.71	88660.33
		WEIGHTED AVERAGE FOR THE YEAR		7.00	25125.00	46712.06	43572.63
===== 206-01782		Shoring (A 2)		LUMP SUM	=====		
ER119A-065		PR SH 119A BOULDER CANYON	01/03/19	1.00	20000.00	35602.20	19800.00
STA119A-069		SH 119: NEDERLAND - EAST					
ER072A-040		PR SH72A FLOOD PERMANENT REPA	01/31/19	1.00	49000.00	56765.27	67000.00
NHPP072A-041		PR SH72A FLOOD PERMANENT REPA					
NHPP145A-065		SH 145 PASSING LANES AT DEEP	02/14/19	1.00	20000.00	16380.12	10000.00
STM0242-077		US24 - 8TH ST TO WEST OF MANI	03/28/19	1.00	5000.00	16166.67	0.01
		WEIGHTED AVERAGE FOR THE FIRST QUARTER		4.00	22800.00	38367.20	23320.00
NHPP0703-445		I-70 WESTBOUND PEAK PERIOD SH	04/25/19	1.00	35000.00	334228.00	305684.00
FBR0063-057		US-6 F-09-K BRIDGE OVER CASTL	05/30/19	1.00	40000.00	48092.50	43185.00
NHPP160A-030		US160 MM 43.2, 150.4, 156.3,	06/20/19	1.00	10000.00	4350.00	5700.00
		WEIGHTED AVERAGE FOR THE SECOND QUARTER		3.00	28333.33	158224.14	118189.67
		WEIGHTED AVERAGE FOR THE YEAR		7.00	24875.00	57878.79	58896.13
===== 206-01783		Shoring (A 3)		LUMP SUM	=====		
ER119A-065		PR SH 119A BOULDER CANYON	01/03/19	1.00	20000.00	54445.26	27800.00
STA119A-069		SH 119: NEDERLAND - EAST					
ER072A-040		PR SH72A FLOOD PERMANENT REPA	01/31/19	1.00	58500.00	42047.15	48000.00
NHPP072A-041		PR SH72A FLOOD PERMANENT REPA					
		WEIGHTED AVERAGE FOR THE FIRST QUARTER		2.00	32833.33	49131.78	34533.33
NHPP160A-030		US160 MM 43.2, 150.4, 156.3,	06/20/19	1.00	10000.00	4350.00	5700.00
		WEIGHTED AVERAGE FOR THE SECOND QUARTER		1.00	10000.00	4350.00	5700.00
		WEIGHTED AVERAGE FOR THE YEAR		3.00	27125.00	46146.33	27325.00

COLORADO DEPARTMENT OF TRANSPORTATION
 ITEM UNIT COSTS BY PROJECTS -- 2019 COST DATA

13:44 Wednesday, August 7, 2019 60

PROJECT NUMBER	ITEM NUMBER/ PROJECT LOCATION	ITEM DESCRIPTION/ PROJECT LOCATION	DATE LET	UNIT/ QUANTITY	ENGR. EST.	AVERAGE BID	AWARDED BID
===== 206-01784		Shoring (A 4)		LUMP SUM	=====		
ER119A-065		PR SH 119A BOULDER CANYON	01/03/19	1.00	20000.00	61964.76	43500.00
STA119A-069		SH 119: NEDERLAND - EAST					
ER072A-040		PR SH72A FLOOD PERMANENT REPA	01/31/19	1.00	45500.00	55010.83	88000.00
NHPP072A-041		PR SH72A FLOOD PERMANENT REPA					
		WEIGHTED AVERAGE FOR THE FIRST QUARTER		2.00	28500.00	58984.50	58333.33
NHPP160A-030		US160 MM 43.2, 150.4, 156.3,	06/20/19	1.00	10000.00	4350.00	5700.00
		WEIGHTED AVERAGE FOR THE SECOND QUARTER		1.00	10000.00	4350.00	5700.00
		WEIGHTED AVERAGE FOR THE YEAR		3.00	23875.00	55342.20	45175.00
===== 206-01785		Shoring (A 5)		LUMP SUM	=====		
ER119A-065		PR SH 119A BOULDER CANYON	01/03/19	1.00	20000.00	40079.71	25700.00
STA119A-069		SH 119: NEDERLAND - EAST					
ER072A-040		PR SH72A FLOOD PERMANENT REPA	01/31/19	1.00	10000.00	37299.98	37000.00
NHPP072A-041		PR SH72A FLOOD PERMANENT REPA					
		WEIGHTED AVERAGE FOR THE FIRST QUARTER		2.00	16666.67	38888.40	29466.67
		WEIGHTED AVERAGE FOR THE YEAR		2.00	16666.67	38888.40	29466.67
===== 206-01786		Shoring (A 6)		LUMP SUM	=====		
ER119A-065		PR SH 119A BOULDER CANYON	01/03/19	1.00	20000.00	23268.83	14900.00
STA119A-069		SH 119: NEDERLAND - EAST					
		WEIGHTED AVERAGE FOR THE FIRST QUARTER		1.00	20000.00	23268.83	14900.00
		WEIGHTED AVERAGE FOR THE YEAR		1.00	20000.00	23268.83	14900.00
===== 207-00205		Topsoil		Cubic Yard	=====		
ER119A-065		PR SH 119A BOULDER CANYON	01/03/19	9,646.00	15.00	31.84	35.00
STA119A-069		SH 119: NEDERLAND - EAST					

PROJECT NUMBER	ITEM NUMBER/ PROJECT LOCATION	ITEM DESCRIPTION/ PROJECT LOCATION	DATE LET	UNIT/ QUANTITY	ENGR. EST.	AVERAGE BID	AWARDED BID
===== 207-00205 Topsoil Cubic Yard =====							
STR0132-021		SH 13-MOFFAT COUNTY-CR 3 SOUT	01/10/19	24,200.00	4.00	3.99	5.25
FBR0341-087		US 34 OVER NORTH FORK CO RIVE	01/10/19	216.00	10.00	28.51	18.71
NHPP0701-241		I-70 TRUCK PARKING GARFIELD C	01/17/19	425.00	16.00	41.71	5.00
STR0241-062		US 24 143.4 - 148	01/24/19	219.00	20.00	76.67	65.00
ER072A-040		PR SH72A FLOOD PERMANENT REPA	01/31/19	4,840.00	30.00	27.64	20.00
NHPP072A-041		PR SH72A FLOOD PERMANENT REPA					
NH2871-035		US 287 PASSING LANES SOUTH OF	02/07/19	3,557.00	15.00	5.24	3.20
NHPP145A-065		SH 145 PASSING LANES AT DEEP	02/14/19	2,570.00	35.00	19.16	21.00
NHPP070A-028		FALL RIVER ROAD BRIDGE	02/21/19	37.00	50.00	65.14	46.00
FBR0253-247		I25 AT VINE DRIVE BRIDGE REPL	03/07/19	1,850.00	10.00	14.90	7.00
SHE2254-090		Colfax & I-225, Colfax & Cham	03/07/19	61.00	30.00	74.50	65.00
NHPP0503-087		US 50 PASSING LANES EAST OF S	03/21/19	3,362.00	10.00	8.50	5.00
SHE 0252-481		I-25 RAMP METER INSTALLATION	03/21/19	2,256.00	25.00	28.00	45.00
STM0242-077		US24 - 8TH ST TO WEST OF MANI	03/28/19	544.00	10.15	41.17	31.50
STA0131-070 HMA ALT		SH 13 CR 5 NORTH AND SOUTH	03/28/19	68,298.00	8.00	5.53	3.60
STA0131-070 PCCP ALT		SH 13 CR 5 NORTH AND SOUTH					
WEIGHTED AVERAGE FOR THE FIRST QUARTER				122,081.00	9.89	12.90	10.51
IM0252-472		I-25 CABLE BARRIER PHASE III	04/04/19	11,700.00	8.00	8.50	10.00
BR071A-020		REPLACEMENT OF STRUCTURE L-22	04/18/19	140.00	20.00	21.33	16.00
NHPP0703-445		I-70 WESTBOUND PEAK PERIOD SH	04/25/19	6,722.00	20.00	16.30	13.00
FSA0703-454		EB I-70 AUX LANE WARD TO KIPL	05/16/19	1,742.00	10.00	30.02	18.00
FBR0063-057		US-6 F-09-K BRIDGE OVER CASTL	05/30/19	752.00	10.00	45.50	73.00
NHPP0703-442		I-70 SILVERPLUME SOUNDWALL AN	06/13/19	296.00	40.00	25.83	21.00
NHPP160A-030		US160 MM 43.2, 150.4, 156.3,	06/20/19	790.00	25.00	17.50	10.00
WEIGHTED AVERAGE FOR THE SECOND QUARTER				22,142.00	12.98	15.56	13.86
WEIGHTED AVERAGE FOR THE YEAR				144,223.00	10.36	13.15	11.19
===== 207-00210 Stockpile Topsoil Cubic Yard =====							
ER119A-065		PR SH 119A BOULDER CANYON	01/03/19	1,000.00	7.00	17.29	6.90
STA119A-069		SH 119: NEDERLAND - EAST					
STR0132-021		SH 13-MOFFAT COUNTY-CR 3 SOUT	01/10/19	24,200.00	5.00	4.15	7.00
NHPP145A-065		SH 145 PASSING LANES AT DEEP	02/14/19	2,570.00	15.00	20.01	18.00
NHPP1601-073		US 160 PASSING LANE NORTH OF	03/07/19	5,750.00	10.00	6.15	4.30
SHE2254-090		Colfax & I-225, Colfax & Cham	03/07/19	61.00	12.00	34.50	27.00
NHPP0503-087		US 50 PASSING LANES EAST OF S	03/21/19	3,362.00	10.00	8.00	4.00
SHE 0252-481		I-25 RAMP METER INSTALLATION	03/21/19	2,256.00	12.00	18.33	25.00
STA0131-070 HMA ALT		SH 13 CR 5 NORTH AND SOUTH	03/28/19	68,298.00	4.00	6.06	4.15
STA0131-070 PCCP ALT		SH 13 CR 5 NORTH AND SOUTH					
WEIGHTED AVERAGE FOR THE FIRST QUARTER				107,497.00	5.20	6.43	6.28

COLORADO DEPARTMENT OF TRANSPORTATION
ITEM UNIT COSTS BY PROJECTS -- 2019 COST DATA

13:44 Wednesday, August 7, 2019 62

PROJECT NUMBER	ITEM NUMBER/ PROJECT LOCATION	ITEM DESCRIPTION/ PROJECT LOCATION	DATE LET	UNIT/ QUANTITY	ENGR. EST.	AVERAGE BID	AWARDED BID
===== 207-00210		Stockpile Topsoil		Cubic Yard	=====		
FSA0252-468		I-25 AND PLUM CREEK IMPROVEME	04/18/19	13.00	12.00	94.50	108.00
NHPP0703-445		I-70 WESTBOUND PEAK PERIOD SH	04/25/19	6,722.00	10.00	10.94	8.00
FSA0703-454		EB I-70 AUX LANE WARD TO KIPL	05/16/19	1,742.00	3.50	20.15	5.00
NHPP0703-442		I-70 SILVERPLUME SOUNDWALL AN	06/13/19	296.00	10.00	15.90	14.00
NHPP160A-030		US160 MM 43.2, 150.4, 156.3,	06/20/19	790.00	15.00	15.00	5.00
	WEIGHTED AVERAGE FOR THE SECOND QUARTER			9,563.00	9.23	13.34	7.53
	WEIGHTED AVERAGE FOR THE YEAR			117,060.00	5.53	6.94	6.42
===== 207-00305		Wetland Topsoil		Cubic Yard	=====		
STA0131-070 HMA ALT		SH 13 CR 5 NORTH AND SOUTH	03/28/19	1,516.00	40.00	17.41	7.55
STA0131-070 PCCP ALT		SH 13 CR 5 NORTH AND SOUTH					
	WEIGHTED AVERAGE FOR THE FIRST QUARTER			1,516.00	40.00	17.41	7.55
NHPP160A-030		US160 MM 43.2, 150.4, 156.3,	06/20/19	45.00	40.00	40.00	30.00
	WEIGHTED AVERAGE FOR THE SECOND QUARTER			45.00	40.00	40.00	30.00
	WEIGHTED AVERAGE FOR THE YEAR			1,561.00	40.00	17.84	8.81
===== 207-00310		Stockpile Wetland Topsoil		Cubic Yard	=====		
ER119A-065		PR SH 119A BOULDER CANYON	01/03/19	3.00	15.00	258.11	150.00
STA119A-069		SH 119: NEDERLAND - EAST					
STA0131-070 HMA ALT		SH 13 CR 5 NORTH AND SOUTH	03/28/19	1,492.00	20.00	9.65	7.00
STA0131-070 PCCP ALT		SH 13 CR 5 NORTH AND SOUTH					
	WEIGHTED AVERAGE FOR THE FIRST QUARTER			1,495.00	19.99	10.98	7.57
NHPP160A-030		US160 MM 43.2, 150.4, 156.3,	06/20/19	45.00	115.00	35.00	20.00
	WEIGHTED AVERAGE FOR THE SECOND QUARTER			45.00	115.00	35.00	20.00
	WEIGHTED AVERAGE FOR THE YEAR			1,540.00	22.77	11.45	8.28

PROJECT NUMBER	ITEM NUMBER/ PROJECT LOCATION	ITEM DESCRIPTION/ PROJECT LOCATION	DATE LET	UNIT/ QUANTITY	ENGR. EST.	AVERAGE BID	AWARDED BID
===== 208-00002		Erosion Log Type 1 (12 In)		Lin Foot	=====		
STAR200-242		R2 NORTH PROGRAM WALL REPAIRS	01/03/19	300.00	5.00	12.67	13.00
FSA0142-068		SH 14 & WCR 33 INTERSECTION I	01/03/19	435.00	10.00	5.49	3.95
ER119A-065		PR SH 119A BOULDER CANYON	01/03/19	3,330.00	4.00	5.78	4.25
STA119A-069		SH 119: NEDERLAND - EAST					
STR0132-021		SH 13-MOFFAT COUNTY-CR 3 SOUT	01/10/19	15,500.00	4.00	4.49	4.15
FBR0341-087		US 34 OVER NORTH FORK CO RIVE	01/10/19	1,400.00	5.00	5.83	7.13
STR141A-047		SH 141 MP 120-143 MESA COUNTY	01/17/19	800.00	6.00	6.43	5.50
NHPP0701-241		I-70 TRUCK PARKING GARFIELD C	01/17/19	1,650.00	5.50	5.51	5.25
STR0241-062		US 24 143.4 - 148	01/24/19	1,080.00	5.00	5.00	4.00
ER072A-040		PR SH72A FLOOD PERMANENT REPA	01/31/19	34,850.00	5.00	4.97	4.00
NHPP072A-041		PR SH72A FLOOD PERMANENT REPA					
NHPP0821-107		SH 82 GLENWOOD SPRINGS TO CA	02/07/19	220.00	5.50	5.05	4.60
NHPP145A-065		SH 145 PASSING LANES AT DEEP	02/14/19	1,130.00	5.00	5.03	5.50
NHPP0741-022		SH 74: I-70 TO CR 65 RESURFAC	02/14/19	421.00	7.00	6.60	7.00
NHPP1601-076		US 160 MANCOS HILL (MP 40.000	02/21/19	50.00	5.00	5.37	4.75
NHPP070A-028		FALL RIVER ROAD BRIDGE	02/21/19	4,129.00	7.00	4.87	4.30
SHER100-284		FY19 NORTH SIGNAL PKG	02/21/19	90.00	6.00	7.83	6.50
NHPP1601-073		US 160 PASSING LANE NORTH OF	03/07/19	2,060.00	15.00	4.93	4.85
FBR0253-247		I25 AT VINE DRIVE BRIDGE REPL	03/07/19	5,360.00	6.00	4.26	4.50
NHPP006A-058		US 6 LOVELAND PASS - I-70 (FY	03/07/19	280.00	5.00	12.51	5.02
SHE2254-090		Colfax & I-225, Colfax & Cham	03/07/19	234.00	7.00	10.00	5.00
NHPP0702-378		I-70 OFFICERS GULCH TO FRISCO	03/14/19	500.00	10.00	8.16	4.73
NHPP050A-033		US50 West of Delta EB Lanes R	03/14/19	1,000.00	7.00	5.32	5.45
NHPP0503-087		US 50 PASSING LANES EAST OF S	03/21/19	1,100.00	5.50	5.00	5.00
SHER100-308		MIDPOINT - SIGNAL CONST PACKA	03/21/19	680.00	5.00	8.25	7.50
STM0242-077		US24 - 8TH ST TO WEST OF MANI	03/28/19	925.00	5.50	4.13	4.50
STA0131-070 HMA ALT		SH 13 CR 5 NORTH AND SOUTH	03/28/19	43,920.00	5.00	4.52	4.75
STA0131-070 PCCP ALT		SH 13 CR 5 NORTH AND SOUTH					
		WEIGHTED AVERAGE FOR THE FIRST QUARTER		121,444.00	5.22	4.87	4.45
IM0252-472		I-25 CABLE BARRIER PHASE III	04/04/19	4,110.00	6.00	4.00	4.00
BR071A-020		REPLACEMENT OF STRUCTURE L-22	04/18/19	3,000.00	5.00	5.13	3.00
FSA0252-468		I-25 AND PLUM CREEK IMPROVEME	04/18/19	675.00	7.00	5.84	5.84
FSA0703-454		EB I-70 AUX LANE WARD TO KIPL	05/16/19	900.00	6.00	8.14	8.00
SHE0701-243		I-70 EXIT 26 DDI MODIFICATION	05/16/19	20.00	10.00	10.75	10.00
FBR0063-057		US-6 F-09-K BRIDGE OVER CASTL	05/30/19	1,500.00	5.00	4.87	4.75
STRR200-257		ROAD CLOSURE GATES ON VARIOUS	05/30/19	1,000.00	7.55	5.95	5.00
ER145A-081		SH 145 MP 21 EMERGENCY ROCKFA	06/07/19	200.00	15.00	5.86	6.00
NHPP0703-442		I-70 SILVERPLUME SOUNDWALL AN	06/13/19	230.00	6.00	10.36	5.80
CR500-205		R5 GUARDRAIL END TREATMENT EA	06/13/19	1,500.00	4.50	5.55	5.55
STR 141A-040		R5 YEAR 4 BRDG PREV MAINT RAM	06/20/19	480.00	5.00	6.00	6.00
NHPP160A-030		US160 MM 43.2, 150.4, 156.3,	06/20/19	1,919.00	6.00	7.50	5.00

PROJECT NUMBER	ITEM NUMBER/ PROJECT LOCATION	ITEM DESCRIPTION/ PROJECT LOCATION	DATE LET	UNIT/ QUANTITY	ENGR. EST.	AVERAGE BID	AWARDED BID
===== 208-00002		Erosion Log Type 1 (12 In)		Lin Foot	=====		
C0502-085		US 50 MM 201.8 MONARCH AVALAN	06/27/19	40.00	15.00	14.25	19.00
	WEIGHTED AVERAGE FOR THE SECOND QUARTER			15,574.00	5.82	5.77	4.69
	WEIGHTED AVERAGE FOR THE YEAR			137,018.00	5.28	4.91	4.49
===== 208-00008		Erosion Log Type 2 (12 In)		Lin Foot	=====		
IM0251-351		I-25 South of Pueblo MP 79.6	01/03/19	1,600.00	5.50	8.16	7.67
ER119A-065		PR SH 119A BOULDER CANYON	01/03/19	20,000.00	5.00	7.32	6.25
STA119A-069		SH 119: NEDERLAND - EAST					
ITSSW01-638		ETHERNET PHASE III (PRIMARYLY	02/07/19	400.00	8.00	4.50	1.00
STM0242-077		US24 - 8TH ST TO WEST OF MANI	03/28/19	6,650.00	7.00	6.17	7.50
	WEIGHTED AVERAGE FOR THE FIRST QUARTER			28,650.00	5.53	7.21	6.55
NHPP0703-445		I-70 WESTBOUND PEAK PERIOD SH	04/25/19	29,150.00	6.00	7.08	8.00
NHPP030A-036		SH 30 & TOWER RD IMPROVEMENTS	06/13/19	100.00	10.00	5.50	5.50
	WEIGHTED AVERAGE FOR THE SECOND QUARTER			29,250.00	6.01	7.08	7.99
	WEIGHTED AVERAGE FOR THE YEAR			57,900.00	5.78	7.17	7.28
===== 208-00009		Erosion Log Type 2 (18 In)		Lin Foot	=====		
NH2871-035		US 287 PASSING LANES SOUTH OF	02/07/19	2,000.00	7.00	11.68	10.45
	WEIGHTED AVERAGE FOR THE FIRST QUARTER			2,000.00	7.00	11.68	10.45
	WEIGHTED AVERAGE FOR THE YEAR			2,000.00	7.00	11.68	10.45
===== 208-00012		Erosion Log Type 1 (9 In)		Lin Foot	=====		
STA067A-038		SH 67 SEDALIA RESURFACING	01/31/19	1,400.00	15.00	4.24	4.00
SHE2254-090		Colfax & I-225, Colfax & Cham	03/07/19	92.00	10.00	14.50	4.00
SHE 0252-481		I-25 RAMP METER INSTALLATION	03/21/19	7,152.00	10.00	6.67	8.00
	WEIGHTED AVERAGE FOR THE FIRST QUARTER			8,644.00	10.81	6.33	7.31
IM0252-456		I-25 COLORADO SPRINGS RAMP ME	05/16/19	8,660.00	8.00	4.50	4.00
	WEIGHTED AVERAGE FOR THE SECOND QUARTER			8,660.00	8.00	4.50	4.00
	WEIGHTED AVERAGE FOR THE YEAR			17,304.00	9.40	5.41	5.65

COLORADO DEPARTMENT OF TRANSPORTATION
 ITEM UNIT COSTS BY PROJECTS -- 2019 COST DATA

13:44 Wednesday, August 7, 2019 65

PROJECT NUMBER	ITEM NUMBER/ PROJECT LOCATION	ITEM DESCRIPTION/ PROJECT LOCATION	DATE LET	UNIT/ QUANTITY	ENGR. EST.	AVERAGE BID	AWARDED BID
===== 208-00013		Erosion Log Type 1 (20 In)		Lin Foot	=====		
STR0132-021		SH 13-MOFFAT COUNTY-CR 3 SOUT	01/10/19	400.00	7.00	8.08	6.60
STA067A-038		SH 67 SEDALIA RESURFACING	01/31/19	750.00	10.00	5.34	4.50
		WEIGHTED AVERAGE FOR THE FIRST QUARTER		1,150.00	8.96	6.63	5.23
		WEIGHTED AVERAGE FOR THE YEAR		1,150.00	8.96	6.63	5.23
===== 208-00020		Silt Fence		Lin Foot	=====		
NH2871-035		US 287 PASSING LANES SOUTH OF	02/07/19	13,200.00	2.00	1.65	1.42
NHPP145A-065		SH 145 PASSING LANES AT DEEP	02/14/19	3,926.00	5.00	2.00	1.50
NHPP1601-076		US 160 MANCOS HILL (MP 40.000	02/21/19	1,000.00	2.00	2.60	1.80
NHPP1601-073		US 160 PASSING LANE NORTH OF	03/07/19	1,100.00	5.00	2.00	2.00
FBR0253-247		I25 AT VINE DRIVE BRIDGE REPL	03/07/19	432.00	2.00	2.31	1.50
NHPP0503-087		US 50 PASSING LANES EAST OF S	03/21/19	1,900.00	1.50	2.00	2.00
STM0242-077		US24 - 8TH ST TO WEST OF MANI	03/28/19	980.00	3.50	1.82	2.75
		WEIGHTED AVERAGE FOR THE FIRST QUARTER		22,538.00	2.69	1.82	1.59
FSA0252-468		I-25 AND PLUM CREEK IMPROVEME	04/18/19	398.00	2.00	2.40	1.60
NHPP2851-012		US 285 Antonito to Estrella C	05/02/19	500.00	1.00	2.75	2.00
FSA0703-454		EB I-70 AUX LANE WARD TO KIPL	05/16/19	100.00	2.00	7.04	10.00
ER145A-081		SH 145 MP 21 EMERGENCY ROCKFA	06/07/19	300.00	5.00	2.59	3.00
NHPP0703-442		I-70 SILVERPLUME SOUNDWALL AN	06/13/19	1,300.00	3.00	5.01	1.40
STR 141A-040		R5 YEAR 4 BRDG PREV MAINT RAM	06/20/19	100.00	3.50	2.75	3.00
		WEIGHTED AVERAGE FOR THE SECOND QUARTER		2,698.00	2.69	4.40	2.10
		WEIGHTED AVERAGE FOR THE YEAR		25,236.00	2.69	2.18	1.64
===== 208-00021		Silt Fence (Reinf)		Lin Foot	=====		
IM0251-351		I-25 South of Pueblo MP 79.6	01/03/19	500.00	6.50	4.43	4.31
		WEIGHTED AVERAGE FOR THE FIRST QUARTER		500.00	6.50	4.43	4.31
		WEIGHTED AVERAGE FOR THE YEAR		500.00	6.50	4.43	4.31
===== 208-00023		Erosion Log (Type 3) (12 In)		Lin Foot	=====		
ER119A-065		PR SH 119A BOULDER CANYON	01/03/19	4,000.00	6.00	7.02	5.90

PROJECT NUMBER	ITEM NUMBER/ PROJECT LOCATION	ITEM DESCRIPTION/ PROJECT LOCATION	DATE LET	UNIT/ QUANTITY	ENGR. EST.	AVERAGE BID	AWARDED BID
=====	208-00023	Erosion Log (Type 3) (12 In)		Lin Foot	=====		
STA119A-069		SH 119: NEDERLAND - EAST					
	WEIGHTED AVERAGE FOR THE FIRST QUARTER			4,000.00	6.00	7.02	5.90
	WEIGHTED AVERAGE FOR THE YEAR			4,000.00	6.00	7.02	5.90
=====	208-00025	Plastic Sheeting		Sq Yard	=====		
FSA2873-190		US 287 AND FOOTHILLS PARKWAY	05/02/19	250.00	10.00	10.50	13.00
	WEIGHTED AVERAGE FOR THE SECOND QUARTER			250.00	10.00	10.50	13.00
	WEIGHTED AVERAGE FOR THE YEAR			250.00	10.00	10.50	13.00
=====	208-00035	Aggregate Bag		Lin Foot	=====		
NHPPR500-173		US 160_550 DURANGO SIGNALS OP	01/03/19	100.00	15.00	14.50	9.00
SHER100-289		INTERSECTIONS @ SH83 & LONGS	01/03/19	400.00	12.00	8.35	4.75
ER119A-065		PR SH 119A BOULDER CANYON	01/03/19	764.00	10.00	9.69	5.60
STA119A-069		SH 119: NEDERLAND - EAST					
STR0132-021		SH 13-MOFFAT COUNTY-CR 3 SOUT	01/10/19	100.00	5.00	10.27	7.45
STR141A-047		SH 141 MP 120-143 MESA COUNTY	01/17/19	250.00	10.00	8.63	6.00
NHPP0701-241		I-70 TRUCK PARKING GARFIELD C	01/17/19	200.00	8.00	11.52	17.00
STR0241-062		US 24 143.4 - 148	01/24/19	2,288.00	7.00	12.67	11.00
NHPPR100-250		PACKAGE A (I-25 / I-70 / I-76	01/24/19	150.00	12.00	10.93	7.00
STAM086-075		SH96A ABRIENDO - ORMAN SAFETY	01/31/19	128.00	9.50	13.00	15.00
STA067A-038		SH 67 SEDALIA RESURFACING	01/31/19	48.00	12.00	8.40	10.00
NHPP0821-107		SH 82 GLENWOOD SPRINGS TO CA	02/07/19	400.00	5.00	9.45	14.20
ITSSW01-638		ETHERNET PHASE III (PRIMARILY	02/07/19	300.00	8.00	5.00	1.00
NHPP0741-022		SH 74: I-70 TO CR 65 RESURFAC	02/14/19	100.00	12.00	8.77	10.30
NHPP070A-028		FALL RIVER ROAD BRIDGE	02/21/19	32.00	12.00	7.79	5.50
SHER100-284		FY19 NORTH SIGNAL PKG	02/21/19	240.00	12.00	9.00	7.00
FBR0253-247		I25 AT VINE DRIVE BRIDGE REPL	03/07/19	320.00	8.00	6.63	6.55
NHPP006A-058		US 6 LOVELAND PASS - I-70 (FY	03/07/19	40.00	20.00	19.39	13.78
SHE2254-090		Colfax & I-225, Colfax & Cham	03/07/19	350.00	12.00	11.00	7.00
NHPP0702-378		I-70 OFFICERS GULCH TO FRISCO	03/14/19	500.00	15.00	14.35	11.56
NHPP050A-033		US50 West of Delta EB Lanes R	03/14/19	100.00	10.00	6.15	5.45
SHE 0252-481		I-25 RAMP METER INSTALLATION	03/21/19	240.00	12.00	7.33	7.50
SHER100-308		MIDPOINT - SIGNAL CONST PACKA	03/21/19	436.00	10.00	8.00	7.00
NHPP2254-089		I-225 RESURFACING FROM I-25 T	03/21/19	2,442.00	11.00	6.10	5.50
STM0242-077		US24 - 8TH ST TO WEST OF MANI	03/28/19	65.00	9.00	5.75	6.75
	WEIGHTED AVERAGE FOR THE FIRST QUARTER			9,993.00	9.78	9.26	8.04
NHPP030A-035		US 285/SH30	04/04/19	500.00	12.00	10.00	10.00

PROJECT NUMBER	ITEM NUMBER/ PROJECT LOCATION	ITEM DESCRIPTION/ PROJECT LOCATION	DATE LET	UNIT/ QUANTITY	ENGR. EST.	AVERAGE BID	AWARDED BID
===== 208-00035		Aggregate Bag		Lin Foot			
STRR300-236		SH 92 and SH 133	04/04/19	400.00	10.00	5.00	5.00
NHPP0703-445		I-70 WESTBOUND PEAK PERIOD SH	04/25/19	14,980.00	12.00	10.90	11.00
MTCE0641-103		MTCE R3 FY20 SH 64 RANGELY PE	05/02/19	85.00	20.00	17.38	20.00
FSA2873-190		US 287 AND FOOTHILLS PARKWAY	05/02/19	100.00	10.00	17.50	21.00
IM0252-456		I-25 COLORADO SPRINGS RAMP ME	05/16/19	24.00	8.00	12.00	7.00
FSA0703-454		EB I-70 AUX LANE WARD TO KIPL	05/16/19	50.00	12.00	26.89	15.00
SHE0701-243		I-70 EXIT 26 DDI MODIFICATION	05/16/19	130.00	9.00	7.56	1.00
NHPP030A-036		SH 30 & TOWER RD IMPROVEMENTS	06/13/19	100.00	12.00	10.00	10.00
CR500-205		R5 GUARDRAIL END TREATMENT EA	06/13/19	200.00	10.00	9.95	9.95
STR 141A-040		R5 YEAR 4 BRDG PREV MAINT RAM	06/20/19	430.00	8.00	14.50	15.00
C0502-085		US 50 MM 201.8 MONARCH AVALAN	06/27/19	40.00	16.00	20.25	25.00
		WEIGHTED AVERAGE FOR THE SECOND QUARTER		17,039.00	11.84	10.98	10.98
		WEIGHTED AVERAGE FOR THE YEAR		27,032.00	11.08	10.23	9.89
===== 208-00041		Rock Check Dam		Each			
ER119A-065		PR SH 119A BOULDER CANYON	01/03/19	100.00	400.00	687.18	285.00
STA119A-069		SH 119: NEDERLAND - EAST					
NHPP0821-107		SH 82 GLENWOOD SPRINGS TO CA	02/07/19	1.00	800.00	3275.00	1050.00
NH2871-035		US 287 PASSING LANES SOUTH OF	02/07/19	6.00	500.00	1205.85	1800.00
		WEIGHTED AVERAGE FOR THE FIRST QUARTER		107.00	409.35	708.52	377.10
		WEIGHTED AVERAGE FOR THE YEAR		107.00	409.35	708.52	377.10
===== 208-00045		Conc Washout Str		Each			
STAR200-242		R2 NORTH PROGRAM WALL REPAIRS	01/03/19	1.00	1500.00	1866.83	2051.00
IM0251-351		I-25 South of Pueblo MP 79.6	01/03/19	1.00	2000.00	1984.88	1999.19
ER119A-065		PR SH 119A BOULDER CANYON	01/03/19	12.00	1566.67	2495.15	4400.00
STA119A-069		SH 119: NEDERLAND - EAST					
FBR0341-087		US 34 OVER NORTH FORK CO RIVE	01/10/19	2.00	2000.00	1640.33	1680.91
NHPPR100-250		PACKAGE A (I-25 / I-70 / I-76	01/24/19	2.00	1500.00	2490.08	1500.00
ER072A-040		PR SH72A FLOOD PERMANENT REPA	01/31/19	8.00	1500.00	1658.02	1000.00
NHPP072A-041		PR SH72A FLOOD PERMANENT REPA					
STAM086-075		SH96A ABRIENDO - ORMAN SAFETY	01/31/19	2.00	2000.00	2141.67	625.00
STA067A-038		SH 67 SEDALIA RESURFACING	01/31/19	1.00	1500.00	1480.02	1500.00
NH2871-035		US 287 PASSING LANES SOUTH OF	02/07/19	2.00	1000.00	2784.22	3675.00
ITSSW01-638		ETHERNET PHASE III (PRIMARYLY	02/07/19	3.00	1400.00	650.00	500.00
NHPP145A-065		SH 145 PASSING LANES AT DEEP	02/14/19	1.00	1500.00	2034.67	1650.00
NHPP0741-022		SH 74: I-70 TO CR 65 RESURFAC	02/14/19	1.00	1500.00	2242.02	2200.00
NHPP070A-028		FALL RIVER ROAD BRIDGE	02/21/19	2.00	1500.00	1375.37	570.00

PROJECT NUMBER	ITEM NUMBER/ PROJECT LOCATION	ITEM DESCRIPTION/ PROJECT LOCATION	DATE LET	UNIT/ QUANTITY	ENGR. EST.	AVERAGE BID	AWARDED BID
===== 208-00045 Conc Washout Str Each =====							
SHER100-284	FY19 NORTH SIGNAL PKG		02/21/19	3.00	1400.00	1374.00	1576.00
NHPP1601-073	US 160 PASSING LANE NORTH OF		03/07/19	2.00	1500.00	1850.00	1700.00
FBR0253-247	I25 AT VINE DRIVE BRIDGE REPL		03/07/19	2.00	1500.00	1195.39	850.00
SHE2254-090	Colfax & I-225, Colfax & Cham		03/07/19	1.00	1500.00	2575.00	1150.00
NHPP050A-033	US50 West of Delta EB Lanes R		03/14/19	1.00	1500.00	1916.67	2500.00
NHPP0503-087	US 50 PASSING LANES EAST OF S		03/21/19	2.00	1200.00	3250.00	1500.00
SHE 0252-481	I-25 RAMP METER INSTALLATION		03/21/19	16.00	1500.00	1291.67	1550.00
STM0242-077	US24 - 8TH ST TO WEST OF MANI		03/28/19	3.00	1930.00	1666.67	2000.00
WEIGHTED AVERAGE FOR THE FIRST QUARTER				68.00	1535.15	1868.56	1986.47
=====							
NHPP030A-035	US 285/SH30		04/04/19	1.00	1500.00	5000.00	5000.00
IM0252-472	I-25 CABLE BARRIER PHASE III		04/04/19	3.00	1200.00	2000.00	3000.00
FSA0252-468	I-25 AND PLUM CREEK IMPROVEME		04/18/19	1.00	2000.00	1330.00	1416.00
NHPP0703-445	I-70 WESTBOUND PEAK PERIOD SH		04/25/19	14.00	1500.00	5900.98	1779.00
FSA2873-190	US 287 AND FOOTHILLS PARKWAY		05/02/19	1.00	1500.00	2037.50	2600.00
STRR200-257	ROAD CLOSURE GATES ON VARIOUS		05/30/19	3.00	739.25	596.50	350.00
WEIGHTED AVERAGE FOR THE SECOND QUARTER				23.00	1383.38	4554.35	1911.83
WEIGHTED AVERAGE FOR THE YEAR				91.00	1496.79	2254.96	1967.60
=====							
===== 208-00046 Pre-fab Conc Washout Str (Type 1) Each =====							
NHPPR500-173	US 160_550 DURANGO SIGNALS OP		01/03/19	1.00	1000.00	1450.00	650.00
SHER100-289	INTERSECTIONS @ SH83 & LONGS		01/03/19	2.00	1500.00	1416.00	2350.00
STR0132-021	SH 13-MOFFAT COUNTY-CR 3 SOUT		01/10/19	1.00	1800.00	2670.00	1380.00
NHPP0701-241	I-70 TRUCK PARKING GARFIELD C		01/17/19	1.00	1700.00	4187.62	4500.00
STR0241-062	US 24 143.4 - 148		01/24/19	3.00	2100.00	1286.67	560.00
NHPP0821-107	SH 82 GLENWOOD SPRINGS TO CA		02/07/19	2.00	1500.00	2800.00	2600.00
SHE2254-090	Colfax & I-225, Colfax & Cham		03/07/19	2.00	1300.00	2925.00	350.00
NHPP0702-378	I-70 OFFICERS GULCH TO FRISCO		03/14/19	1.00	1000.00	2254.17	2562.50
SHER100-308	MIDPOINT - SIGNAL CONST PACKA		03/21/19	3.00	1450.00	1550.00	1300.00
NHPP2254-089	I-225 RESURFACING FROM I-25 T		03/21/19	2.00	2000.00	2337.44	2250.00
STA0131-070 HMA ALT	SH 13 CR 5 NORTH AND SOUTH		03/28/19	6.00	1500.00	2591.00	1820.00
STA0131-070 PCCP ALT	SH 13 CR 5 NORTH AND SOUTH						
WEIGHTED AVERAGE FOR THE FIRST QUARTER				24.00	1572.92	2257.68	1677.74
=====							
NHPP030A-035	US 285/SH30		04/04/19	5.00	2000.00	4000.00	4000.00

PROJECT NUMBER	ITEM NUMBER/ PROJECT LOCATION	ITEM DESCRIPTION/ PROJECT LOCATION	DATE LET	UNIT/ QUANTITY	ENGR. EST.	AVERAGE BID	AWARDED BID
===== 208-00046		Pre-fab Conc Washout Str (Type 1)		Each			
BR071A-020		REPLACEMENT OF STRUCTURE L-22	04/18/19	2.00	2000.00	943.33	700.00
MTCE0641-103		MTCE R3 FY20 SH 64 RANGELY PE	05/02/19	1.00	2000.00	1590.00	2000.00
IM0252-456		I-25 COLORADO SPRINGS RAMP ME	05/16/19	3.00	1600.00	910.00	880.00
FSA0703-454		EB I-70 AUX LANE WARD TO KIPL	05/16/19	2.00	2000.00	3922.07	6000.00
SHE0701-243		I-70 EXIT 26 DDI MODIFICATION	05/16/19	1.00	2000.00	1875.00	2000.00
FBR0063-057		US-6 F-09-K BRIDGE OVER CASTL	05/30/19	1.00	1500.00	1532.69	970.00
NHPP0703-442		I-70 SILVERPLUME SOUNDWALL AN	06/13/19	1.00	2000.00	2718.27	2680.00
STR 141A-040		R5 YEAR 4 BRDG PREV MAINT RAM	06/20/19	2.00	2400.00	375.00	500.00
NHPP160A-030		US160 MM 43.2, 150.4, 156.3,	06/20/19	4.00	3000.00	1615.00	980.00
C0502-085		US 50 MM 201.8 MONARCH AVALAN	06/27/19	1.00	2000.00	5391.50	4730.00
		WEIGHTED AVERAGE FOR THE SECOND QUARTER		23.00	2134.78	2108.52	2319.13
		WEIGHTED AVERAGE FOR THE YEAR		47.00	1847.87	2192.42	2013.01
===== 208-00051		Storm Drain Inlet Protection (Type I)		Lin Foot			
NHPPR500-173		US 160_550 DURANGO SIGNALS OP	01/03/19	100.00	20.00	60.00	20.00
SHER100-289		INTERSECTIONS @ SH83 & LONGS	01/03/19	100.00	10.00	11.10	7.50
STR0241-062		US 24 143.4 - 148	01/24/19	14.00	20.00	13.67	12.00
NHPPR100-250		PACKAGE A (I-25 / I-70 / I-76	01/24/19	175.00	15.00	12.67	12.00
STAM086-075		SH96A ABRIENDO - ORMAN SAFETY	01/31/19	5.00	14.00	24.67	22.00
ITSSW01-638		ETHERNET PHASE III (PRIMARILY	02/07/19	100.00	15.00	9.00	1.00
NHPP0741-022		SH 74: I-70 TO CR 65 RESURFAC	02/14/19	206.00	20.00	15.78	10.30
SHER100-284		FY19 NORTH SIGNAL PKG	02/21/19	4.00	200.00	50.33	51.00
FBR0253-247		I25 AT VINE DRIVE BRIDGE REPL	03/07/19	22.00	100.00	11.85	7.00
SHER100-308		MIDPOINT - SIGNAL CONST PACKA	03/21/19	26.00	14.00	62.50	58.00
NHPP2254-089		I-225 RESURFACING FROM I-25 T	03/21/19	24.00	12.00	18.90	20.00
		WEIGHTED AVERAGE FOR THE FIRST QUARTER		776.00	19.65	17.29	12.49
MTCE0641-103		MTCE R3 FY20 SH 64 RANGELY PE	05/02/19	26.00	20.00	110.60	200.00
STR 141A-040		R5 YEAR 4 BRDG PREV MAINT RAM	06/20/19	92.00	15.00	14.50	15.00
		WEIGHTED AVERAGE FOR THE SECOND QUARTER		118.00	16.10	35.67	55.76
		WEIGHTED AVERAGE FOR THE YEAR		894.00	19.18	18.62	18.21
===== 208-00052		Storm Drain Inlet Protection (Type II)		Lin Foot			
ER119A-065		PR SH 119A BOULDER CANYON	01/03/19	1.00	100.00	190.66	235.00

COLORADO DEPARTMENT OF TRANSPORTATION
 ITEM UNIT COSTS BY PROJECTS -- 2019 COST DATA

13:44 Wednesday, August 7, 2019 70

PROJECT NUMBER	ITEM NUMBER/ PROJECT LOCATION	ITEM DESCRIPTION/ PROJECT LOCATION	DATE LET	UNIT/ QUANTITY	ENGR. EST.	AVERAGE BID	AWARDED BID
===== 208-00052		Storm Drain Inlet Protection (Type II)		Lin Foot	=====		
STA119A-069		SH 119: NEDERLAND - EAST					
STR0241-062		US 24 143.4 - 148	01/24/19	28.00	50.00	74.33	72.00
STAM086-075		SH96A ABRIENDO - ORMAN SAFETY	01/31/19	3.00	55.00	62.67	48.00
NHPP070A-028		FALL RIVER ROAD BRIDGE	02/21/19	20.00	55.00	35.02	21.00
	WEIGHTED AVERAGE FOR THE FIRST QUARTER			52.00	53.17	58.88	54.13
	WEIGHTED AVERAGE FOR THE YEAR			52.00	53.17	58.88	54.13
===== 208-00053		Storm Drain Inlet Protect (Ty I) (84 In)		Each	=====		
ER119A-065		PR SH 119A BOULDER CANYON	01/03/19	6.00	400.00	232.31	73.00
STA119A-069		SH 119: NEDERLAND - EAST					
NHPP0503-087		US 50 PASSING LANES EAST OF S	03/21/19	15.00	300.00	177.50	200.00
SHE 0252-481		I-25 RAMP METER INSTALLATION	03/21/19	9.00	130.00	215.00	215.00
	WEIGHTED AVERAGE FOR THE FIRST QUARTER			30.00	269.00	212.20	179.10
FSA0252-468		I-25 AND PLUM CREEK IMPROVEME	04/18/19	2.00	150.00	214.75	195.00
	WEIGHTED AVERAGE FOR THE SECOND QUARTER			2.00	150.00	214.75	195.00
	WEIGHTED AVERAGE FOR THE YEAR			32.00	261.56	212.38	180.09
===== 208-00054		Storm Drain Inlet Protection (Type II)		Each	=====		
SHE 0252-481		I-25 RAMP METER INSTALLATION	03/21/19	9.00	150.00	320.67	315.00
NHPP2254-089		I-225 RESURFACING FROM I-25 T	03/21/19	3.00	250.00	327.76	400.00
	WEIGHTED AVERAGE FOR THE FIRST QUARTER			12.00	175.00	322.44	336.25
NHPP030A-035		US 285/SH30	04/04/19	67.00	300.00	200.00	200.00
SHE0701-243		I-70 EXIT 26 DDI MODIFICATION	05/16/19	11.00	300.00	218.75	150.00
	WEIGHTED AVERAGE FOR THE SECOND QUARTER			78.00	300.00	207.43	192.95
	WEIGHTED AVERAGE FOR THE YEAR			90.00	283.33	235.60	212.06
===== 208-00056		Storm Drain Inlet Protection (Type III)		Each	=====		
ER119A-065		PR SH 119A BOULDER CANYON	01/03/19	2.00	50.00	264.35	240.00

PROJECT NUMBER	ITEM NUMBER/ PROJECT LOCATION	ITEM DESCRIPTION/ PROJECT LOCATION	DATE LET	UNIT/ QUANTITY	ENGR. EST.	AVERAGE BID	AWARDED BID
=====	208-00056	Storm Drain Inlet Protection (Type III)		Each	=====	=====	=====
STA119A-069		SH 119: NEDERLAND - EAST					
STR0241-062		US 24 143.4 - 148	01/24/19	12.00	300.00	158.33	205.00
FBR0253-247		I25 AT VINE DRIVE BRIDGE REPL	03/07/19	8.00	15.00	313.34	265.00
		WEIGHTED AVERAGE FOR THE FIRST QUARTER		22.00	173.64	267.88	230.00
MTCE0641-103		MTCE R3 FY20 SH 64 RANGELY PE	05/02/19	1.00	500.00	385.00	200.00
STR 141A-040		R5 YEAR 4 BRDG PREV MAINT RAM	06/20/19	2.00	300.00	150.00	150.00
		WEIGHTED AVERAGE FOR THE SECOND QUARTER		3.00	366.67	228.33	166.67
		WEIGHTED AVERAGE FOR THE YEAR		25.00	196.80	266.25	222.40
=====	208-00070	Vehicle Tracking Pad		Each	=====	=====	=====
STAR200-242		R2 NORTH PROGRAM WALL REPAIRS	01/03/19	1.00	1500.00	3324.06	3395.00
IM0251-351		I-25 South of Pueblo MP 79.6	01/03/19	2.00	2000.00	2081.65	3345.46
ER119A-065		PR SH 119A BOULDER CANYON	01/03/19	18.00	2066.67	3196.57	3100.00
STA119A-069		SH 119: NEDERLAND - EAST					
STR0132-021		SH 13-MOFFAT COUNTY-CR 3 SOUT	01/10/19	1.00	2000.00	3382.00	3790.00
FBR0341-087		US 34 OVER NORTH FORK CO RIVE	01/10/19	4.00	2500.00	2077.94	1552.26
ER072A-040		PR SH72A FLOOD PERMANENT REPA	01/31/19	16.00	2200.00	2218.57	830.00
NHPP072A-041		PR SH72A FLOOD PERMANENT REPA					
NHPP0821-107		SH 82 GLENWOOD SPRINGS TO CA	02/07/19	2.00	2000.00	2250.00	2400.00
NHPP145A-065		SH 145 PASSING LANES AT DEEP	02/14/19	1.00	3000.00	3096.93	3750.00
NHPP1601-073		US 160 PASSING LANE NORTH OF	03/07/19	2.00	3500.00	1550.00	1700.00
FBR0253-247		I25 AT VINE DRIVE BRIDGE REPL	03/07/19	2.00	2000.00	2674.28	4000.00
NHPP050A-033		US50 West of Delta EB Lanes R	03/14/19	1.00	2900.00	2633.33	4500.00
NHPP0503-087		US 50 PASSING LANES EAST OF S	03/21/19	2.00	1800.00	1750.00	900.00
SHE 0252-481		I-25 RAMP METER INSTALLATION	03/21/19	3.00	2500.00	2490.00	2500.00
SHER100-308		MIDPOINT - SIGNAL CONST PACKA	03/21/19	1.00	2000.00	1875.00	2550.00
STM0242-077		US24 - 8TH ST TO WEST OF MANI	03/28/19	5.00	2318.00	2950.00	3750.00
STA0131-070 HMA ALT		SH 13 CR 5 NORTH AND SOUTH	03/28/19	8.00	2500.00	3023.92	2180.00
STA0131-070 PCCP ALT		SH 13 CR 5 NORTH AND SOUTH					
		WEIGHTED AVERAGE FOR THE FIRST QUARTER		69.00	2253.48	2620.46	2352.85
NHPP030A-035		US 285/SH30	04/04/19	1.00	2500.00	4000.00	4000.00
IM0252-472		I-25 CABLE BARRIER PHASE III	04/04/19	5.00	1500.00	2200.00	2000.00
FSA0252-468		I-25 AND PLUM CREEK IMPROVEME	04/18/19	2.00	2200.00	2493.25	2773.00

COLORADO DEPARTMENT OF TRANSPORTATION
 ITEM UNIT COSTS BY PROJECTS -- 2019 COST DATA

13:44 Wednesday, August 7, 2019 72

PROJECT NUMBER	ITEM NUMBER/ PROJECT LOCATION	ITEM DESCRIPTION/ PROJECT LOCATION	DATE LET	UNIT/ QUANTITY	ENGR. EST.	AVERAGE BID	AWARDED BID
===== 208-00070 Vehicle Tracking Pad Each =====							
NHPP0703-445		I-70 WESTBOUND PEAK PERIOD SH	04/25/19	14.00	2500.00	3921.20	2373.00
FSA0703-454		EB I-70 AUX LANE WARD TO KIPL	05/16/19	3.00	2500.00	2610.81	2000.00
FBR0063-057		US-6 F-09-K BRIDGE OVER CASTL	05/30/19	2.00	2000.00	2738.49	2965.00
STRR200-257		ROAD CLOSURE GATES ON VARIOUS	05/30/19	4.00	1550.00	1420.25	517.50
NHPP0703-442		I-70 SILVERPLUME SOUNDWALL AN	06/13/19	1.00	3000.00	2015.70	1700.00
STR 141A-040		R5 YEAR 4 BRDG PREV MAINT RAM	06/20/19	3.00	2500.00	2750.00	3000.00
	WEIGHTED AVERAGE FOR THE SECOND QUARTER			35.00	2217.14	3011.20	2213.37
	WEIGHTED AVERAGE FOR THE YEAR			104.00	2241.25	2687.09	2304.03
===== 208-00071 Maint Aggregate (Veh Track Pad) Cubic Yard =====							
ER072A-040		PR SH72A FLOOD PERMANENT REPA	01/31/19	200.00	80.00	69.88	53.00
NHPP072A-041		PR SH72A FLOOD PERMANENT REPA					
	WEIGHTED AVERAGE FOR THE FIRST QUARTER			200.00	80.00	69.88	53.00
FSA0703-454		EB I-70 AUX LANE WARD TO KIPL	05/16/19	75.00	50.00	71.67	55.00
NHPP0703-442		I-70 SILVERPLUME SOUNDWALL AN	06/13/19	20.00	100.00	118.61	57.00
	WEIGHTED AVERAGE FOR THE SECOND QUARTER			95.00	60.53	91.17	55.42
	WEIGHTED AVERAGE FOR THE YEAR			295.00	73.73	72.83	53.78
===== 208-00075 Pre-fab Vehicle Track Pad Each =====							
NH2871-035		US 287 PASSING LANES SOUTH OF	02/07/19	4.00	1000.00	4857.87	3675.00
SHE2254-090		Colfax & I-225, Colfax & Cham	03/07/19	2.00	1500.00	3500.00	500.00
	WEIGHTED AVERAGE FOR THE FIRST QUARTER			6.00	1166.67	4586.29	2616.67
BR071A-020		REPLACEMENT OF STRUCTURE L-22	04/18/19	4.00	3000.00	6116.67	6000.00
NHPP160A-030		US160 MM 43.2, 150.4, 156.3,	06/20/19	8.00	2000.00	1325.00	1400.00
	WEIGHTED AVERAGE FOR THE SECOND QUARTER			12.00	2333.33	3378.57	2933.33
	WEIGHTED AVERAGE FOR THE YEAR			18.00	1944.44	3881.79	2827.78

PROJECT NUMBER	ITEM NUMBER/ PROJECT LOCATION	ITEM DESCRIPTION/ PROJECT LOCATION	DATE LET	UNIT/ QUANTITY	ENGR. EST.	AVERAGE BID	AWARDED BID
===== 208-00082 Construction Mat Sq Foot =====							
NHPP160A-030		US160 MM 43.2, 150.4, 156.3,	06/20/19	100.00	200.00	656.00	62.00
	WEIGHTED AVERAGE FOR THE SECOND QUARTER			100.00	200.00	656.00	62.00
	WEIGHTED AVERAGE FOR THE YEAR			100.00	200.00	656.00	62.00
===== 208-00090 Erosion Control (Curb Ramp) Each =====							
C R100-315		R1 ADA CURB RAMPS - PH 5	03/07/19	118.00	450.00	625.00	650.00
	WEIGHTED AVERAGE FOR THE FIRST QUARTER			118.00	450.00	625.00	650.00
C2571-013		SH257 & 392:WINDSOR CURB RAMP	05/02/19	60.00	500.00	362.00	300.00
CR300-248		CRAIG RESIDENCY ADA RAMPS	05/16/19	197.00	300.00	285.00	10.00
STMC430-020		ADA RAMPS DIVIDE ESB	05/23/19	23.00	58.00	350.00	350.00
	WEIGHTED AVERAGE FOR THE SECOND QUARTER			280.00	322.98	304.34	100.07
	WEIGHTED AVERAGE FOR THE YEAR			398.00	360.64	377.81	263.12
===== 208-00103 Removal and Disposal of Sediment (Labor) Hour =====							
STAR200-242		R2 NORTH PROGRAM WALL REPAIRS	01/03/19	20.00	50.00	105.64	43.00
IM0251-351		I-25 South of Pueblo MP 79.6	01/03/19	80.00	60.00	70.59	61.33
NHPPR500-173		US 160_550 DURANGO SIGNALS OP	01/03/19	5.00	50.00	158.50	217.00
FSA0142-068		SH 14 & WCR 33 INTERSECTION I	01/03/19	40.00	50.00	54.55	35.00
SHER100-289		INTERSECTIONS @ SH83 & LONGS	01/03/19	200.00	75.00	53.60	38.00
ER119A-065		PR SH 119A BOULDER CANYON	01/03/19	660.00	45.91	59.44	35.00
STA119A-069		SH 119: NEDERLAND - EAST					
STR0132-021		SH 13-MOFFAT COUNTY-CR 3 SOUT	01/10/19	40.00	45.00	42.60	45.00
FBR0341-087		US 34 OVER NORTH FORK CO RIVE	01/10/19	80.00	40.00	52.77	42.46
STR141A-047		SH 141 MP 120-143 MESA COUNTY	01/17/19	60.00	50.00	51.72	35.00
NHPP0701-241		I-70 TRUCK PARKING GARFIELD C	01/17/19	30.00	60.00	81.48	75.00
STR0241-062		US 24 143.4 - 148	01/24/19	30.00	60.00	59.00	47.00
ER072A-040		PR SH72A FLOOD PERMANENT REPA	01/31/19	120.00	100.00	59.52	45.00
NHPP072A-041		PR SH72A FLOOD PERMANENT REPA					
NHPP0821-107		SH 82 GLENWOOD SPRINGS TO CA	02/07/19	20.00	50.00	66.00	68.00
ITSSW01-638		ETHERNET PHASE III (PRIMARILY	02/07/19	40.00	60.00	15.00	10.00
NHPP145A-065		SH 145 PASSING LANES AT DEEP	02/14/19	20.00	70.00	67.87	32.00

PROJECT NUMBER	ITEM NUMBER/ PROJECT LOCATION	ITEM DESCRIPTION/ PROJECT LOCATION	DATE LET	UNIT/ QUANTITY	ENGR. EST.	AVERAGE BID	AWARDED BID
===== 208-00103		Removal and Disposal of Sediment (Labor)		Hour =====			
NHPP0741-022		SH 74: I-70 TO CR 65 RESURFAC	02/14/19	20.00	61.00	68.87	75.00
NHPP1601-076		US 160 MANCOS HILL (MP 40.000	02/21/19	8.00	60.00	153.10	50.00
NHPP070A-028		FALL RIVER ROAD BRIDGE	02/21/19	30.00	100.00	36.89	37.00
SHER100-284		FY19 NORTH SIGNAL PKG	02/21/19	40.00	75.00	63.00	70.00
NHPP1601-073		US 160 PASSING LANE NORTH OF	03/07/19	80.00	60.00	63.25	61.50
FBR0253-247		I25 AT VINE DRIVE BRIDGE REPL	03/07/19	40.00	60.00	50.21	35.00
NHPP006A-058		US 6 LOVELAND PASS - I-70 (FY	03/07/19	80.00	85.00	57.22	54.43
SHE2254-090		Colfax & I-225, Colfax & Cham	03/07/19	5.00	70.00	77.50	55.00
NHPP0702-378		I-70 OFFICERS GULCH TO FRISCO	03/14/19	40.00	70.00	47.08	51.25
NHPP050A-033		US50 West of Delta EB Lanes R	03/14/19	40.00	55.00	51.33	39.00
NHPP0503-087		US 50 PASSING LANES EAST OF S	03/21/19	80.00	50.00	40.00	55.00
SHE 0252-481		I-25 RAMP METER INSTALLATION	03/21/19	85.00	75.00	53.33	70.00
SHER100-308		MIDPOINT - SIGNAL CONST PACKA	03/21/19	20.00	60.00	68.50	60.00
STM0242-077		US24 - 8TH ST TO WEST OF MANI	03/28/19	540.00	56.85	47.67	50.00
STA0131-070 HMA ALT		SH 13 CR 5 NORTH AND SOUTH	03/28/19	640.00	55.00	47.22	48.50
STA0131-070 PCCP ALT		SH 13 CR 5 NORTH AND SOUTH					
		WEIGHTED AVERAGE FOR THE FIRST QUARTER		3,193.00	58.34	55.40	46.00
NHPP030A-035		US 285/SH30	04/04/19	15.00	65.00	80.00	80.00
STRR300-236		SH 92 and SH 133	04/04/19	20.00	50.00	30.00	30.00
IM0252-472		I-25 CABLE BARRIER PHASE III	04/04/19	60.00	29.00	36.00	40.00
BR071A-020		REPLACEMENT OF STRUCTURE L-22	04/18/19	20.00	54.00	38.00	32.00
FSA0252-468		I-25 AND PLUM CREEK IMPROVEME	04/18/19	24.00	60.00	51.50	47.00
NHPP0703-445		I-70 WESTBOUND PEAK PERIOD SH	04/25/19	180.00	75.00	75.97	86.00
NHPP2851-012		US 285 Antonito to Estrella C	05/02/19	8.00	55.00	56.67	50.00
MTCE0641-103		MTCE R3 FY20 SH 64 RANGELY PE	05/02/19	10.00	60.00	69.25	100.00
FSA2873-190		US 287 AND FOOTHILLS PARKWAY	05/02/19	10.00	75.00	105.00	100.00
IM0252-456		I-25 COLORADO SPRINGS RAMP ME	05/16/19	48.00	55.00	62.42	87.25
FSA0703-454		EB I-70 AUX LANE WARD TO KIPL	05/16/19	16.00	65.00	64.65	50.00
SHE0701-243		I-70 EXIT 26 DDI MODIFICATION	05/16/19	20.00	70.00	51.50	45.00
FBR0063-057		US-6 F-09-K BRIDGE OVER CASTL	05/30/19	40.00	50.00	50.00	35.00
STRR200-257		ROAD CLOSURE GATES ON VARIOUS	05/30/19	40.00	95.24	63.00	20.00
ER145A-081		SH 145 MP 21 EMERGENCY ROCKFA	06/07/19	20.00	60.00	93.86	124.00
NHPP0703-442		I-70 SILVERPLUME SOUNDWALL AN	06/13/19	10.00	90.00	51.16	36.00
NHPP030A-036		SH 30 & TOWER RD IMPROVEMENTS	06/13/19	3.00	70.00	50.00	50.00
CR500-205		R5 GUARDRAIL END TREATMENT EA	06/13/19	10.00	45.00	91.10	91.10
STR 141A-040		R5 YEAR 4 BRDG PREV MAINT RAM	06/20/19	20.00	60.00	55.00	40.00
NHPP160A-030		US160 MM 43.2, 150.4, 156.3,	06/20/19	80.00	55.00	49.38	55.00
C0502-085		US 50 MM 201.8 MONARCH AVALAN	06/27/19	10.00	90.00	117.50	85.00
		WEIGHTED AVERAGE FOR THE SECOND QUARTER		664.00	62.76	62.25	63.08
		WEIGHTED AVERAGE FOR THE YEAR		3,857.00	59.10	56.10	49.20
===== 208-00105		Removal and Disposal of Sediment (Equip)		Hour =====			
STAR200-242		R2 NORTH PROGRAM WALL REPAIRS	01/03/19	20.00	100.00	188.22	96.00

PROJECT NUMBER	ITEM NUMBER/ PROJECT LOCATION	ITEM DESCRIPTION/ PROJECT LOCATION	DATE LET	UNIT/ QUANTITY	ENGR. EST.	AVERAGE BID	AWARDED BID
=====	208-00105	Removal and Disposal of Sediment (Equip)		Hour =====			
IM0251-351		I-25 South of Pueblo MP 79.6	01/03/19	80.00	120.00	123.67	122.67
SHER100-289		INTERSECTIONS @ SH83 & LONGS	01/03/19	100.00	150.00	113.00	75.00
ER119A-065		PR SH 119A BOULDER CANYON	01/03/19	650.00	96.54	143.54	90.00
STA119A-069		SH 119: NEDERLAND - EAST					
STR0132-021		SH 13-MOFFAT COUNTY-CR 3 SOUT	01/10/19	40.00	125.00	116.80	90.00
FBR0341-087		US 34 OVER NORTH FORK CO RIVE	01/10/19	40.00	120.00	109.97	98.45
STR141A-047		SH 141 MP 120-143 MESA COUNTY	01/17/19	30.00	140.00	126.67	165.00
NHPP0701-241		I-70 TRUCK PARKING GARFIELD C	01/17/19	30.00	115.00	127.39	150.00
STR0241-062		US 24 143.4 - 148	01/24/19	30.00	120.00	120.00	100.00
ER072A-040		PR SH72A FLOOD PERMANENT REPA	01/31/19	120.00	165.00	118.34	82.00
NHPP072A-041		PR SH72A FLOOD PERMANENT REPA					
NHPP0821-107		SH 82 GLENWOOD SPRINGS TO CA	02/07/19	20.00	115.00	147.50	145.00
ITSSW01-638		ETHERNET PHASE III (PRIMARYLY	02/07/19	40.00	110.00	15.00	10.00
NHPP145A-065		SH 145 PASSING LANES AT DEEP	02/14/19	20.00	75.00	146.03	166.00
NHPP0741-022		SH 74: I-70 TO CR 65 RESURFAC	02/14/19	20.00	118.00	105.51	95.00
NHPP1601-076		US 160 MANCOS HILL (MP 40.000	02/21/19	8.00	130.00	128.33	85.00
NHPP070A-028		FALL RIVER ROAD BRIDGE	02/21/19	30.00	150.00	74.08	110.00
SHER100-284		FY19 NORTH SIGNAL PKG	02/21/19	40.00	150.00	114.67	130.00
NHPP1601-073		US 160 PASSING LANE NORTH OF	03/07/19	80.00	150.00	141.50	153.00
FBR0253-247		I25 AT VINE DRIVE BRIDGE REPL	03/07/19	40.00	120.00	97.76	90.00
NHPP006A-058		US 6 LOVELAND PASS - I-70 (FY	03/07/19	10.00	150.00	124.43	108.86
SHE2254-090		Colfax & I-225, Colfax & Cham	03/07/19	5.00	140.00	127.50	105.00
NHPP0702-378		I-70 OFFICERS GULCH TO FRISCO	03/14/19	40.00	150.00	97.50	102.50
NHPP050A-033		US50 West of Delta EB Lanes R	03/14/19	40.00	145.00	117.33	122.00
NHPP0503-087		US 50 PASSING LANES EAST OF S	03/21/19	80.00	100.00	90.00	130.00
SHE 0252-481		I-25 RAMP METER INSTALLATION	03/21/19	85.00	125.00	79.67	94.00
SHER100-308		MIDPOINT - SIGNAL CONST PACKA	03/21/19	15.00	115.00	112.50	100.00
STM0242-077		US24 - 8TH ST TO WEST OF MANI	03/28/19	640.00	109.69	131.67	105.00
STA0131-070 HMA ALT		SH 13 CR 5 NORTH AND SOUTH	03/28/19	100.00	110.00	97.48	60.60
STA0131-070 PCCP ALT		SH 13 CR 5 NORTH AND SOUTH					
		WEIGHTED AVERAGE FOR THE FIRST QUARTER		2,453.00	116.04	127.82	100.63
NHPP030A-035		US 285/SH30	04/04/19	10.00	150.00	140.00	140.00
IM0252-472		I-25 CABLE BARRIER PHASE III	04/04/19	14.00	75.00	94.00	100.00
BR071A-020		REPLACEMENT OF STRUCTURE L-22	04/18/19	40.00	150.00	115.00	100.00
FSA0252-468		I-25 AND PLUM CREEK IMPROVEME	04/18/19	24.00	100.00	102.00	72.00
NHPP0703-445		I-70 WESTBOUND PEAK PERIOD SH	04/25/19	90.00	150.00	156.32	103.00
NHPP2851-012		US 285 Antonito to Estrella C	05/02/19	8.00	135.00	203.33	75.00
FSA2873-190		US 287 AND FOOTHILLS PARKWAY	05/02/19	20.00	150.00	155.00	150.00
IM0252-456		I-25 COLORADO SPRINGS RAMP ME	05/16/19	48.00	120.00	53.97	31.90
FSA0703-454		EB I-70 AUX LANE WARD TO KIPL	05/16/19	16.00	120.00	155.50	200.00
FBR0063-057		US-6 F-09-K BRIDGE OVER CASTL	05/30/19	20.00	100.00	143.71	175.00
STRR200-257		ROAD CLOSURE GATES ON VARIOUS	05/30/19	40.00	123.00	94.50	20.00
ER145A-081		SH 145 MP 21 EMERGENCY ROCKFA	06/07/19	20.00	150.00	192.71	224.00

PROJECT NUMBER	ITEM NUMBER/ PROJECT LOCATION	ITEM DESCRIPTION/ PROJECT LOCATION	DATE LET	UNIT/ QUANTITY	ENGR. EST.	AVERAGE BID	AWARDED BID
===== 208-00105		Removal and Disposal of Sediment (Equip)		Hour =====			
NHPP0703-442		I-70 SILVERPLUME SOUNDWALL AN	06/13/19	10.00	150.00	121.05	118.00
STR 141A-040		R5 YEAR 4 BRDG PREV MAINT RAM	06/20/19	20.00	140.00	152.50	125.00
NHPP160A-030		US160 MM 43.2, 150.4, 156.3,	06/20/19	40.00	115.00	113.75	115.00
	WEIGHTED AVERAGE FOR THE SECOND QUARTER			420.00	131.02	124.60	102.83
	WEIGHTED AVERAGE FOR THE YEAR			2,873.00	118.23	127.55	100.96
===== 208-00106		Sweeping (Sediment Removal)		Hour =====			
IM0251-351		I-25 South of Pueblo MP 79.6	01/03/19	40.00	160.00	176.74	178.42
NHPPR500-173		US 160_550 DURANGO SIGNALS OP	01/03/19	5.00	120.00	170.50	76.00
FSA0142-068		SH 14 & WCR 33 INTERSECTION I	01/03/19	32.00	140.00	118.25	75.00
SHER100-289		INTERSECTIONS @ SH83 & LONGS	01/03/19	60.00	150.00	140.40	160.00
ER119A-065		PR SH 119A BOULDER CANYON	01/03/19	720.00	107.78	165.21	125.00
STA119A-069		SH 119: NEDERLAND - EAST					
STR0132-021		SH 13-MOFFAT COUNTY-CR 3 SOUT	01/10/19	40.00	150.00	235.20	350.00
FBR0341-087		US 34 OVER NORTH FORK CO RIVE	01/10/19	50.00	150.00	160.13	98.45
STR141A-047		SH 141 MP 120-143 MESA COUNTY	01/17/19	20.00	150.00	162.76	110.00
NHPP0701-241		I-70 TRUCK PARKING GARFIELD C	01/17/19	10.00	150.00	245.33	300.00
STR0241-062		US 24 143.4 - 148	01/24/19	30.00	150.00	191.67	140.00
NHPPR100-250		PACKAGE A (I-25 / I-70 / I-76	01/24/19	110.00	170.00	157.34	145.00
ER072A-040		PR SH72A FLOOD PERMANENT REPA	01/31/19	120.00	155.00	136.68	86.00
NHPP072A-041		PR SH72A FLOOD PERMANENT REPA					
STAM086-075		SH96A ABRIENDO - ORMAN SAFETY	01/31/19	28.00	140.00	170.33	161.00
STA067A-038		SH 67 SEDALIA RESURFACING	01/31/19	8.00	150.00	271.58	200.00
ITSSW01-638		ETHERNET PHASE III (PRIMARILY	02/07/19	40.00	150.00	15.00	10.00
NHPP145A-065		SH 145 PASSING LANES AT DEEP	02/14/19	20.00	250.00	231.56	396.00
NHPP0741-022		SH 74: I-70 TO CR 65 RESURFAC	02/14/19	40.00	150.00	178.77	220.00
NHPP1601-076		US 160 MANCOS HILL (MP 40.000	02/21/19	40.00	150.00	237.33	370.00
NHPP070A-028		FALL RIVER ROAD BRIDGE	02/21/19	15.00	150.00	122.49	170.00
SHER100-284		FY19 NORTH SIGNAL PKG	02/21/19	36.00	150.00	102.00	32.00
FBR0253-247		I25 AT VINE DRIVE BRIDGE REPL	03/07/19	20.00	150.00	128.99	95.00
NHPP006A-058		US 6 LOVELAND PASS - I-70 (FY	03/07/19	30.00	195.00	195.25	190.50
SHE2254-090		Colfax & I-225, Colfax & Cham	03/07/19	15.00	150.00	120.00	105.00
NHPP0702-378		I-70 OFFICERS GULCH TO FRISCO	03/14/19	40.00	180.00	173.54	230.62
NHPP050A-033		US50 West of Delta EB Lanes R	03/14/19	20.00	150.00	146.30	68.90
SHE 0252-481		I-25 RAMP METER INSTALLATION	03/21/19	66.00	165.00	115.33	135.00
SHER100-308		MIDPOINT - SIGNAL CONST PACKA	03/21/19	60.00	140.00	147.50	150.00
NHPP2254-089		I-225 RESURFACING FROM I-25 T	03/21/19	16.00	150.00	186.54	160.00
STM0242-077		US24 - 8TH ST TO WEST OF MANI	03/28/19	360.00	150.83	186.67	150.00
STA0131-070 HMA ALT		SH 13 CR 5 NORTH AND SOUTH	03/28/19	320.00	150.00	198.89	182.00
STA0131-070 PCCP ALT		SH 13 CR 5 NORTH AND SOUTH					
	WEIGHTED AVERAGE FOR THE FIRST QUARTER			2,411.00	140.58	164.97	146.26
NHPP030A-035		US 285/SH30	04/04/19	75.00	160.00	135.00	135.00

PROJECT NUMBER	ITEM NUMBER/ PROJECT LOCATION	ITEM DESCRIPTION/ PROJECT LOCATION	DATE LET	UNIT/ QUANTITY	ENGR. EST.	AVERAGE BID	AWARDED BID
===== 208-00106		Sweeping (Sediment Removal)		Hour =====			
BR071A-020		REPLACEMENT OF STRUCTURE L-22	04/18/19	30.00	140.00	156.67	120.00
FSA0252-468		I-25 AND PLUM CREEK IMPROVEME	04/18/19	24.00	150.00	110.75	72.00
NHPP0703-445		I-70 WESTBOUND PEAK PERIOD SH	04/25/19	90.00	150.00	218.34	220.00
MTCE0641-103		MTCE R3 FY20 SH 64 RANGELY PE	05/02/19	20.00	160.00	115.00	100.00
FSA2873-190		US 287 AND FOOTHILLS PARKWAY	05/02/19	20.00	140.00	215.00	215.00
IM0252-456		I-25 COLORADO SPRINGS RAMP ME	05/16/19	80.00	160.00	165.00	170.00
FSA0703-454		EB I-70 AUX LANE WARD TO KIPL	05/16/19	20.00	150.00	149.96	200.00
SHE0701-243		I-70 EXIT 26 DDI MODIFICATION	05/16/19	40.00	160.00	116.25	75.00
FBR0063-057		US-6 F-09-K BRIDGE OVER CASTL	05/30/19	20.00	150.00	202.50	230.00
STRR200-257		ROAD CLOSURE GATES ON VARIOUS	05/30/19	40.00	217.98	105.50	20.00
NHPP0703-442		I-70 SILVERPLUME SOUNDWALL AN	06/13/19	40.00	375.00	188.56	298.00
NHPP030A-036		SH 30 & TOWER RD IMPROVEMENTS	06/13/19	40.00	150.00	150.00	150.00
CR500-205		R5 GUARDRAIL END TREATMENT EA	06/13/19	40.00	175.00	182.00	182.00
STR 141A-040		R5 YEAR 4 BRDG PREV MAINT RAM	06/20/19	60.00	150.00	182.00	200.00
		WEIGHTED AVERAGE FOR THE SECOND QUARTER		639.00	172.49	167.27	163.93
		WEIGHTED AVERAGE FOR THE YEAR		3,050.00	147.27	165.24	150.16
===== 208-00107		Rem Trash		Hour =====			
IM0251-351		I-25 South of Pueblo MP 79.6	01/03/19	20.00	125.00	139.16	250.13
FSA0142-068		SH 14 & WCR 33 INTERSECTION I	01/03/19	2.00	60.00	161.75	35.00
SHER100-289		INTERSECTIONS @ SH83 & LONGS	01/03/19	10.00	125.00	108.70	160.00
ER119A-065		PR SH 119A BOULDER CANYON	01/03/19	30.00	70.00	161.87	35.00
STA119A-069		SH 119: NEDERLAND - EAST					
STR0132-021		SH 13-MOFFAT COUNTY-CR 3 SOUT	01/10/19	80.00	50.00	121.80	80.00
FBR0341-087		US 34 OVER NORTH FORK CO RIVE	01/10/19	10.00	125.00	97.46	39.10
STR141A-047		SH 141 MP 120-143 MESA COUNTY	01/17/19	10.00	80.00	179.25	180.00
NHPP0701-241		I-70 TRUCK PARKING GARFIELD C	01/17/19	10.00	100.00	177.05	50.00
STR0241-062		US 24 143.4 - 148	01/24/19	30.00	115.00	150.67	47.00
NHPPR100-250		PACKAGE A (I-25 / I-70 / I-76	01/24/19	22.00	125.00	69.91	40.00
ER072A-040		PR SH72A FLOOD PERMANENT REPA	01/31/19	80.00	120.00	101.48	91.00
NHPP072A-041		PR SH72A FLOOD PERMANENT REPA					
STAM086-075		SH96A ABRIENDO - ORMAN SAFETY	01/31/19	24.00	90.00	76.33	14.00
STA067A-038		SH 67 SEDALIA RESURFACING	01/31/19	6.00	125.00	184.74	225.00
NHPP0821-107		SH 82 GLENWOOD SPRINGS TO CA	02/07/19	8.00	100.00	113.50	37.00
ITSSW01-638		ETHERNET PHASE III (PRIMARYLY	02/07/19	10.00	100.00	15.00	10.00
NHPP0741-022		SH 74: I-70 TO CR 65 RESURFAC	02/14/19	10.00	100.00	97.36	165.00
FBR0253-247		I25 AT VINE DRIVE BRIDGE REPL	03/07/19	20.00	50.00	80.45	35.00
NHPP006A-058		US 6 LOVELAND PASS - I-70 (FY	03/07/19	10.00	125.00	75.82	81.64
SHE2254-090		Colfax & I-225, Colfax & Cham	03/07/19	30.00	135.00	195.00	40.00
NHPP0702-378		I-70 OFFICERS GULCH TO FRISCO	03/14/19	40.00	80.00	73.96	76.87
NHPP050A-033		US50 West of Delta EB Lanes R	03/14/19	20.00	50.00	81.93	80.80
SHE 0252-481		I-25 RAMP METER INSTALLATION	03/21/19	20.00	125.00	51.33	64.00
SHER100-308		MIDPOINT - SIGNAL CONST PACKA	03/21/19	10.00	115.00	73.50	70.00

PROJECT NUMBER	ITEM NUMBER/ PROJECT LOCATION	ITEM DESCRIPTION/ PROJECT LOCATION	DATE LET	UNIT/ QUANTITY	ENGR. EST.	AVERAGE BID	AWARDED BID
===== 208-00107							
		Rem Trash		Hour			
NHPP2254-089		I-225 RESURFACING FROM I-25 T	03/21/19	8.00	125.00	132.49	75.00
STM0242-077		US24 - 8TH ST TO WEST OF MANI	03/28/19	60.00	125.00	197.00	100.00
STA0131-070 HMA ALT		SH 13 CR 5 NORTH AND SOUTH	03/28/19	120.00	90.00	95.46	203.00
STA0131-070 PCCP ALT		SH 13 CR 5 NORTH AND SOUTH					
	WEIGHTED AVERAGE FOR THE FIRST QUARTER			700.00	97.11	113.40	91.07
=====							
NHPP030A-035		US 285/SH30	04/04/19	10.00	135.00	200.00	200.00
BR071A-020		REPLACEMENT OF STRUCTURE L-22	04/18/19	30.00	87.00	60.00	32.00
NHPP0703-445		I-70 WESTBOUND PEAK PERIOD SH	04/25/19	90.00	135.00	177.78	161.00
MTCE0641-103		MTCE R3 FY20 SH 64 RANGELY PE	05/02/19	5.00	125.00	130.00	100.00
FSA0703-454		EB I-70 AUX LANE WARD TO KIPL	05/16/19	10.00	100.00	140.09	225.00
SHE0701-243		I-70 EXIT 26 DDI MODIFICATION	05/16/19	20.00	120.00	61.50	75.00
FBR0063-057		US-6 F-09-K BRIDGE OVER CASTL	05/30/19	20.00	50.00	76.22	70.00
STRR200-257		ROAD CLOSURE GATES ON VARIOUS	05/30/19	16.00	64.00	44.50	20.00
NHPP0703-442		I-70 SILVERPLUME SOUNDWALL AN	06/13/19	10.00	125.00	102.26	36.00
NHPP030A-036		SH 30 & TOWER RD IMPROVEMENTS	06/13/19	10.00	90.00	260.00	260.00
STR 141A-040		R5 YEAR 4 BRDG PREV MAINT RAM	06/20/19	60.00	60.00	73.00	100.00
C0502-085		US 50 MM 201.8 MONARCH AVALAN	06/27/19	10.00	250.00	142.50	135.00
	WEIGHTED AVERAGE FOR THE SECOND QUARTER			291.00	104.50	117.03	115.91
	WEIGHTED AVERAGE FOR THE YEAR			991.00	99.28	114.09	98.83
=====							
===== 208-00200							
		Erosion Control Management		LUMP SUM			
SHE2254-090		Colfax & I-225, Colfax & Cham	03/07/19	1.00	6000.00	12500.00	5000.00
	WEIGHTED AVERAGE FOR THE FIRST QUARTER			1.00	6000.00	12500.00	5000.00
=====							
STRR200-257		ROAD CLOSURE GATES ON VARIOUS	05/30/19	1.00	3400.00	10620.50	2500.00
	WEIGHTED AVERAGE FOR THE SECOND QUARTER			1.00	3400.00	10620.50	2500.00
	WEIGHTED AVERAGE FOR THE YEAR			2.00	4700.00	11560.25	3750.00
=====							
===== 208-00207							
		Erosion Control Management		Day			
STAR200-242		R2 NORTH PROGRAM WALL REPAIRS	01/03/19	20.00	300.00	350.10	308.00

PROJECT NUMBER	ITEM NUMBER/ PROJECT LOCATION	ITEM DESCRIPTION/ PROJECT LOCATION	DATE LET	UNIT/ QUANTITY	ENGR. EST.	AVERAGE BID	AWARDED BID
===== 208-00207		Erosion Control Management		Day =====			
FSA0142-068	SH 14 & WCR 33 INTERSECTION I	SH 14 & WCR 33 INTERSECTION I	01/03/19	15.00	210.00	192.50	110.00
ER119A-065	PR SH 119A BOULDER CANYON	PR SH 119A BOULDER CANYON	01/03/19	380.00	190.00	210.42	135.00
STA119A-069	SH 119: NEDERLAND - EAST	SH 119: NEDERLAND - EAST					
STR0132-021	SH 13-MOFFAT COUNTY-CR 3 SOUT	SH 13-MOFFAT COUNTY-CR 3 SOUT	01/10/19	120.00	150.00	389.00	940.00
FBR0341-087	US 34 OVER NORTH FORK CO RIVE	US 34 OVER NORTH FORK CO RIVE	01/10/19	226.00	200.00	140.00	99.80
STR141A-047	SH 141 MP 120-143 MESA COUNTY	SH 141 MP 120-143 MESA COUNTY	01/17/19	45.00	210.00	264.51	150.00
NHPP0701-241	I-70 TRUCK PARKING GARFIELD C	I-70 TRUCK PARKING GARFIELD C	01/17/19	80.00	240.00	349.89	575.00
STR0241-062	US 24 143.4 - 148	US 24 143.4 - 148	01/24/19	140.00	220.00	536.67	180.00
ER072A-040	PR SH72A FLOOD PERMANENT REPA	PR SH72A FLOOD PERMANENT REPA	01/31/19	195.00	300.00	169.07	105.00
NHPP072A-041	PR SH72A FLOOD PERMANENT REPA	PR SH72A FLOOD PERMANENT REPA					
STAM086-075	SH96A ABRIENDO - ORMAN SAFETY	SH96A ABRIENDO - ORMAN SAFETY	01/31/19	30.00	215.00	316.67	200.00
STA067A-038	SH 67 SEDALIA RESURFACING	SH 67 SEDALIA RESURFACING	01/31/19	5.00	250.00	305.89	100.00
NH2871-035	US 287 PASSING LANES SOUTH OF	US 287 PASSING LANES SOUTH OF	02/07/19	29.00	250.00	406.01	420.00
NHPP145A-065	SH 145 PASSING LANES AT DEEP	SH 145 PASSING LANES AT DEEP	02/14/19	75.00	400.00	326.44	300.00
NHPP070A-028	FALL RIVER ROAD BRIDGE	FALL RIVER ROAD BRIDGE	02/21/19	35.00	250.00	152.94	48.00
SHER100-284	FY19 NORTH SIGNAL PKG	FY19 NORTH SIGNAL PKG	02/21/19	12.00	250.00	159.67	140.00
NHPP1601-073	US 160 PASSING LANE NORTH OF	US 160 PASSING LANE NORTH OF	03/07/19	90.00	300.00	528.50	557.00
FBR0253-247	I25 AT VINE DRIVE BRIDGE REPL	I25 AT VINE DRIVE BRIDGE REPL	03/07/19	150.00	210.00	102.95	85.00
NHPP050A-033	US50 West of Delta EB Lanes R	US50 West of Delta EB Lanes R	03/14/19	30.00	250.00	360.00	255.00
NHPP0503-087	US 50 PASSING LANES EAST OF S	US 50 PASSING LANES EAST OF S	03/21/19	90.00	150.00	450.00	400.00
SHE 0252-481	I-25 RAMP METER INSTALLATION	I-25 RAMP METER INSTALLATION	03/21/19	132.00	250.00	140.00	140.00
STM0242-077	US24 - 8TH ST TO WEST OF MANI	US24 - 8TH ST TO WEST OF MANI	03/28/19	135.00	260.00	49.67	50.00
STA0131-070 HMA ALT	SH 13 CR 5 NORTH AND SOUTH	SH 13 CR 5 NORTH AND SOUTH	03/28/19	600.00	250.00	344.36	182.00
STA0131-070 PCCP ALT	SH 13 CR 5 NORTH AND SOUTH	SH 13 CR 5 NORTH AND SOUTH					
	WEIGHTED AVERAGE FOR THE FIRST QUARTER			2,634.00	234.17	229.92	224.42
NHPP030A-035	US 285/SH30	US 285/SH30	04/04/19	50.00	250.00	200.00	200.00
IM0252-472	I-25 CABLE BARRIER PHASE III	I-25 CABLE BARRIER PHASE III	04/04/19	60.00	100.00	360.00	400.00
BR071A-020	REPLACEMENT OF STRUCTURE L-22	REPLACEMENT OF STRUCTURE L-22	04/18/19	15.00	300.00	155.67	50.00
FSA0252-468	I-25 AND PLUM CREEK IMPROVEME	I-25 AND PLUM CREEK IMPROVEME	04/18/19	60.00	250.00	238.50	136.00
NHPP0703-445	I-70 WESTBOUND PEAK PERIOD SH	I-70 WESTBOUND PEAK PERIOD SH	04/25/19	720.00	275.00	222.55	113.00
FSA0703-454	EB I-70 AUX LANE WARD TO KIPL	EB I-70 AUX LANE WARD TO KIPL	05/16/19	45.00	250.00	355.49	100.00
FBR0063-057	US-6 F-09-K BRIDGE OVER CASTL	US-6 F-09-K BRIDGE OVER CASTL	05/30/19	127.00	205.00	404.29	635.00
NHPP0703-442	I-70 SILVERPLUME SOUNDWALL AN	I-70 SILVERPLUME SOUNDWALL AN	06/13/19	50.00	250.00	216.19	39.00
	WEIGHTED AVERAGE FOR THE SECOND QUARTER			1,127.00	253.58	245.39	187.55
	WEIGHTED AVERAGE FOR THE YEAR			3,761.00	239.99	232.95	212.41
===== 208-00300		Temporary Berms		Lin Foot =====			
ER119A-065	PR SH 119A BOULDER CANYON	PR SH 119A BOULDER CANYON	01/03/19	300.00	15.00	15.82	8.65

PROJECT NUMBER	ITEM NUMBER/ PROJECT LOCATION	ITEM DESCRIPTION/ PROJECT LOCATION	DATE LET	UNIT/ QUANTITY	ENGR. EST.	AVERAGE BID	AWARDED BID
===== 208-00300		Temporary Berms		Lin Foot			
STA119A-069		SH 119: NEDERLAND - EAST					
ER072A-040		PR SH72A FLOOD PERMANENT REPA	01/31/19	1,746.00	3.00	12.56	2.00
NHPP072A-041		PR SH72A FLOOD PERMANENT REPA					
NHPP145A-065		SH 145 PASSING LANES AT DEEP	02/14/19	1,309.00	10.00	4.22	3.00
STM0242-077		US24 - 8TH ST TO WEST OF MANI	03/28/19	200.00	1.00	15.33	20.00
	WEIGHTED AVERAGE FOR THE FIRST QUARTER			3,555.00	6.48	11.08	3.94
	WEIGHTED AVERAGE FOR THE YEAR			3,555.00	6.48	11.08	3.94
===== 208-00301		Temporary Diversion		Lin Foot			
ER119A-065		PR SH 119A BOULDER CANYON	01/03/19	2,700.00	155.00	62.50	55.00
STA119A-069		SH 119: NEDERLAND - EAST					
	WEIGHTED AVERAGE FOR THE FIRST QUARTER			2,700.00	155.00	62.50	55.00
	WEIGHTED AVERAGE FOR THE YEAR			2,700.00	155.00	62.50	55.00
===== 208-00400		Water Control		LUMP SUM			
ER119A-065		PR SH 119A BOULDER CANYON	01/03/19	1.00	30000.00	124660.74	150000.00
STA119A-069		SH 119: NEDERLAND - EAST					
FBR0341-087		US 34 OVER NORTH FORK CO RIVE	01/10/19	1.00	75000.00	46903.04	37918.23
STM0242-077		US24 - 8TH ST TO WEST OF MANI	03/28/19	1.00	50000.00	82000.00	45000.00
	WEIGHTED AVERAGE FOR THE FIRST QUARTER			3.00	51666.67	89688.48	77639.41
NHPP160A-030		US160 MM 43.2, 150.4, 156.3,	06/20/19	1.00	60000.00	37250.00	27000.00
	WEIGHTED AVERAGE FOR THE SECOND QUARTER			1.00	60000.00	37250.00	27000.00
	WEIGHTED AVERAGE FOR THE YEAR			4.00	53750.00	84168.64	64979.56
===== 208-00520		Temp Stream Crossing		LUMP SUM			
ER119A-065		PR SH 119A BOULDER CANYON	01/03/19	1.00	10000.00	96489.59	30000.00
STA119A-069		SH 119: NEDERLAND - EAST					
	WEIGHTED AVERAGE FOR THE FIRST QUARTER			1.00	10000.00	96489.59	30000.00
	WEIGHTED AVERAGE FOR THE YEAR			1.00	10000.00	96489.59	30000.00

COLORADO DEPARTMENT OF TRANSPORTATION
 ITEM UNIT COSTS BY PROJECTS -- 2019 COST DATA

13:44 Wednesday, August 7, 2019 81

PROJECT NUMBER	ITEM NUMBER/ PROJECT LOCATION	ITEM DESCRIPTION/ PROJECT LOCATION	DATE LET	UNIT/ QUANTITY	ENGR. EST.	AVERAGE BID	AWARDED BID
===== 209-00600		Dust Palliative (Mg Cl)		Gallon			
STR0132-021		SH 13-MOFFAT COUNTY-CR 3 SOUT	01/10/19	100,000.00	1.00	0.85	0.76
NHPP070A-028		FALL RIVER ROAD BRIDGE	02/21/19	900.00	2.50	4.38	0.80
NHPP1601-073		US 160 PASSING LANE NORTH OF	03/07/19	35,000.00	2.50	1.88	1.75
STA0131-070 HMA ALT		SH 13 CR 5 NORTH AND SOUTH	03/28/19	60,000.00	1.15	1.44	1.50
STA0131-070 PCCP ALT		SH 13 CR 5 NORTH AND SOUTH					
	WEIGHTED AVERAGE FOR THE FIRST QUARTER			195,900.00	1.32	1.11	1.10
	WEIGHTED AVERAGE FOR THE YEAR			195,900.00	1.32	1.11	1.10
===== 210-00001		Res Structure		Each			
NHPP0703-445		I-70 WESTBOUND PEAK PERIOD SH	04/25/19	1.00	15000.00	9314.69	9490.00
	WEIGHTED AVERAGE FOR THE SECOND QUARTER			1.00	15000.00	9314.69	9490.00
	WEIGHTED AVERAGE FOR THE YEAR			1.00	15000.00	9314.69	9490.00
===== 210-00002		Reset Structure		LUMP SUM			
STAR200-242		R2 NORTH PROGRAM WALL REPAIRS	01/03/19	1.00	508732.00	518246.60	654792.00
	WEIGHTED AVERAGE FOR THE FIRST QUARTER			1.00	508732.00	518246.60	654792.00
	WEIGHTED AVERAGE FOR THE YEAR			1.00	508732.00	518246.60	654792.00
===== 210-00010		Res Mailbox Str		Each			
ER072A-040		PR SH72A FLOOD PERMANENT REPA	01/31/19	1.00	450.00	331.19	400.00
NHPP072A-041		PR SH72A FLOOD PERMANENT REPA					
STA0131-070 HMA ALT		SH 13 CR 5 NORTH AND SOUTH	03/28/19	24.00	500.00	365.53	424.00
STA0131-070 PCCP ALT		SH 13 CR 5 NORTH AND SOUTH					
	WEIGHTED AVERAGE FOR THE FIRST QUARTER			25.00	498.00	360.63	422.15
	WEIGHTED AVERAGE FOR THE YEAR			25.00	498.00	360.63	422.15
===== 210-00011		Res Mailbox Str (Ty 1)		Each			
ER119A-065		PR SH 119A BOULDER CANYON	01/03/19	42.00	150.00	309.22	270.00

COLORADO DEPARTMENT OF TRANSPORTATION
 ITEM UNIT COSTS BY PROJECTS -- 2019 COST DATA

13:44 Wednesday, August 7, 2019 82

PROJECT NUMBER	ITEM NUMBER/ PROJECT LOCATION	ITEM DESCRIPTION/ PROJECT LOCATION	DATE LET	UNIT/ QUANTITY	ENGR. EST.	AVERAGE BID	AWARDED BID
=====	210-00011	Res Mailbox Str (Ty 1)		Each	=====	=====	=====
STA119A-069		SH 119: NEDERLAND - EAST					
NHPP1601-073		US 160 PASSING LANE NORTH OF	03/07/19	5.00	500.00	500.00	500.00
NHPP0503-087		US 50 PASSING LANES EAST OF S	03/21/19	11.00	300.00	325.00	250.00
	WEIGHTED AVERAGE FOR THE FIRST QUARTER			58.00	208.62	315.34	286.03
	WEIGHTED AVERAGE FOR THE YEAR			58.00	208.62	315.34	286.03
=====	210-00012	Res Mailbox Str (Ty 2)		Each	=====	=====	=====
ER119A-065		PR SH 119A BOULDER CANYON	01/03/19	11.00	190.00	341.21	280.00
STA119A-069		SH 119: NEDERLAND - EAST					
NHPP0503-087		US 50 PASSING LANES EAST OF S	03/21/19	1.00	360.00	387.50	300.00
	WEIGHTED AVERAGE FOR THE FIRST QUARTER			12.00	204.17	342.24	281.67
	WEIGHTED AVERAGE FOR THE YEAR			12.00	204.17	342.24	281.67
=====	210-00013	Res Mailbox Str (Ty 3)		Each	=====	=====	=====
ER119A-065		PR SH 119A BOULDER CANYON	01/03/19	6.00	300.00	442.90	380.00
STA119A-069		SH 119: NEDERLAND - EAST					
NHPP0503-087		US 50 PASSING LANES EAST OF S	03/21/19	2.00	500.00	480.00	400.00
	WEIGHTED AVERAGE FOR THE FIRST QUARTER			8.00	350.00	445.75	385.00
	WEIGHTED AVERAGE FOR THE YEAR			8.00	350.00	445.75	385.00
=====	210-00015	Res End Section		Each	=====	=====	=====
NH2871-035		US 287 PASSING LANES SOUTH OF	02/07/19	1.00	1000.00	1419.40	3000.00
	WEIGHTED AVERAGE FOR THE FIRST QUARTER			1.00	1000.00	1419.40	3000.00
	WEIGHTED AVERAGE FOR THE YEAR			1.00	1000.00	1419.40	3000.00
=====	210-00050	Res Fire Hydrant		Each	=====	=====	=====
ER119A-065		PR SH 119A BOULDER CANYON	01/03/19	1.00	1500.00	5149.71	6400.00
STA119A-069		SH 119: NEDERLAND - EAST					

COLORADO DEPARTMENT OF TRANSPORTATION
 ITEM UNIT COSTS BY PROJECTS -- 2019 COST DATA

13:44 Wednesday, August 7, 2019 83

PROJECT NUMBER	ITEM NUMBER/ PROJECT LOCATION	ITEM DESCRIPTION/ PROJECT LOCATION	DATE LET	UNIT/ QUANTITY	ENGR. EST.	AVERAGE BID	AWARDED BID
===== 210-00050	Res Fire Hydrant			Each =====			
STR0241-062	US 24 143.4 - 148		01/24/19	6.00	3200.00	7863.33	11000.00
	WEIGHTED AVERAGE FOR THE FIRST QUARTER			7.00	2957.14	7028.37	10342.86
MTCE0641-103	MTCE R3 FY20 SH 64 RANGELY PE		05/02/19	1.00	6000.00	6100.00	4700.00
	WEIGHTED AVERAGE FOR THE SECOND QUARTER			1.00	6000.00	6100.00	4700.00
	WEIGHTED AVERAGE FOR THE YEAR			8.00	3337.50	6962.06	9637.50
===== 210-00090	Res Delineator			Each =====			
ER119A-065 STA119A-069	PR SH 119A BOULDER CANYON SH 119: NEDERLAND - EAST		01/03/19	1.00	120.00	40.92	25.00
	WEIGHTED AVERAGE FOR THE FIRST QUARTER			1.00	120.00	40.92	25.00
NHPP030A-035 IM0252-472 NHPP0703-442	US 285/SH30 I-25 CABLE BARRIER PHASE III I-70 SILVERPLUME SOUNDWALL AN		04/04/19 04/04/19 06/13/19	1.00 3.00 2.00	135.00 50.00 140.00	120.00 161.50 73.17	120.00 300.00 57.00
	WEIGHTED AVERAGE FOR THE SECOND QUARTER			6.00	94.17	98.25	189.00
	WEIGHTED AVERAGE FOR THE YEAR			7.00	97.86	83.45	165.57
===== 210-00425	Res Bridge Railing			Lin Foot =====			
STR 141A-040	R5 YEAR 4 BRDG PREV MAINT RAM		06/20/19	40.00	60.00	175.00	150.00
	WEIGHTED AVERAGE FOR THE SECOND QUARTER			40.00	60.00	175.00	150.00
	WEIGHTED AVERAGE FOR THE YEAR			40.00	60.00	175.00	150.00
===== 210-00473	Res TV Cameras			Each =====			
ITSSW01-638	ETHERNET PHASE III (PRIMARYLY		02/07/19	4.00	1000.00	1284.50	1000.00

COLORADO DEPARTMENT OF TRANSPORTATION
ITEM UNIT COSTS BY PROJECTS -- 2019 COST DATA

13:44 Wednesday, August 7, 2019 84

PROJECT NUMBER	ITEM NUMBER/ PROJECT LOCATION	ITEM DESCRIPTION/ PROJECT LOCATION	DATE LET	UNIT/ QUANTITY	ENGR. EST.	AVERAGE BID	AWARDED BID
=====	210-00473	Res TV Cameras		Each =====			
SHE2254-090		Colfax & I-225, Colfax & Cham	03/07/19	1.00	1500.00	685.00	700.00
		WEIGHTED AVERAGE FOR THE FIRST QUARTER		5.00	1100.00	1164.60	940.00
FSA0252-468		I-25 AND PLUM CREEK IMPROVEME	04/18/19	1.00	1200.00	1140.25	607.00
NHPP0703-445		I-70 WESTBOUND PEAK PERIOD SH	04/25/19	1.00	1500.00	3161.34	3328.00
		WEIGHTED AVERAGE FOR THE SECOND QUARTER		2.00	1350.00	2006.43	1967.50
		WEIGHTED AVERAGE FOR THE YEAR		7.00	1171.43	1511.24	1233.57
=====	210-00475	Res CCTV Pole		Each =====			
NHPP0703-445		I-70 WESTBOUND PEAK PERIOD SH	04/25/19	1.00	2000.00	6152.05	6496.00
		WEIGHTED AVERAGE FOR THE SECOND QUARTER		1.00	2000.00	6152.05	6496.00
		WEIGHTED AVERAGE FOR THE YEAR		1.00	2000.00	6152.05	6496.00
=====	210-00476	Reset MVRD		Each =====			
ITSSW01-638		ETHERNET PHASE III (PRIMARYLY	02/07/19	1.00	1200.00	2284.50	3000.00
		WEIGHTED AVERAGE FOR THE FIRST QUARTER		1.00	1200.00	2284.50	3000.00
NHPP0703-445		I-70 WESTBOUND PEAK PERIOD SH	04/25/19	2.00	1200.00	1799.41	1898.00
		WEIGHTED AVERAGE FOR THE SECOND QUARTER		2.00	1200.00	1799.41	1898.00
		WEIGHTED AVERAGE FOR THE YEAR		3.00	1200.00	1920.68	2265.33
=====	210-00479	Res Radio Com Antenna		Each =====			
STAM086-075		SH96A ABRIENDO - ORMAN SAFETY	01/31/19	3.00	760.50	1523.33	1075.00
SHE2254-090		Colfax & I-225, Colfax & Cham	03/07/19	3.00	750.00	540.00	550.00
NHPP2254-089		I-225 RESURFACING FROM I-25 T	03/21/19	1.00	375.00	1088.28	800.00
		WEIGHTED AVERAGE FOR THE FIRST QUARTER		7.00	700.93	1123.05	810.71
		WEIGHTED AVERAGE FOR THE YEAR		7.00	700.93	1123.05	810.71

COLORADO DEPARTMENT OF TRANSPORTATION
 ITEM UNIT COSTS BY PROJECTS -- 2019 COST DATA

13:44 Wednesday, August 7, 2019 85

PROJECT NUMBER	ITEM NUMBER/ PROJECT LOCATION	ITEM DESCRIPTION/ PROJECT LOCATION	DATE LET	UNIT/ QUANTITY	ENGR. EST.	AVERAGE BID	AWARDED BID
=====	210-00481	Reset DSRC (Roadside Unit)		Each	=====		
NHPP0703-445		I-70 WESTBOUND PEAK PERIOD SH 04/25/19		1.00	1500.00	1799.41	1898.00
		WEIGHTED AVERAGE FOR THE SECOND QUARTER		1.00	1500.00	1799.41	1898.00
		WEIGHTED AVERAGE FOR THE YEAR		1.00	1500.00	1799.41	1898.00
=====	210-00510	Reb Port Present Str		LUMP SUM	=====		
NHPP0703-445		I-70 WESTBOUND PEAK PERIOD SH 04/25/19		1.00	350000.00	138437.38	111546.00
		WEIGHTED AVERAGE FOR THE SECOND QUARTER		1.00	350000.00	138437.38	111546.00
		WEIGHTED AVERAGE FOR THE YEAR		1.00	350000.00	138437.38	111546.00
=====	210-00530	Rebuild Port of Present Str		Sq Foot	=====		
ER119A-065		PR SH 119A BOULDER CANYON	01/03/19	100.00	250.00	226.30	300.00
STA119A-069		SH 119: NEDERLAND - EAST					
STA067A-038		SH 67 SEDALIA RESURFACING	01/31/19	97.00	650.00	330.50	300.00
		WEIGHTED AVERAGE FOR THE FIRST QUARTER		197.00	446.95	254.09	300.00
		WEIGHTED AVERAGE FOR THE YEAR		197.00	446.95	254.09	300.00
=====	210-00750	Res Light Standard		Each	=====		
FBR0253-247		I25 AT VINE DRIVE BRIDGE REPL	03/07/19	2.00	2000.00	3449.75	3300.00
SHE 0252-481		I-25 RAMP METER INSTALLATION	03/21/19	3.00	2300.00	1718.15	1825.00
		WEIGHTED AVERAGE FOR THE FIRST QUARTER		5.00	2180.00	2947.03	2415.00
NHPP0703-445		I-70 WESTBOUND PEAK PERIOD SH 04/25/19		14.00	2000.00	2053.42	2135.00
MTCE0641-103		MTCE R3 FY20 SH 64 RANGELY PE 05/02/19		2.00	1500.00	4235.00	3850.00
		WEIGHTED AVERAGE FOR THE SECOND QUARTER		16.00	1937.50	2243.12	2349.38
		WEIGHTED AVERAGE FOR THE YEAR		21.00	1995.24	2526.51	2365.00

PROJECT NUMBER	ITEM NUMBER/ PROJECT LOCATION	ITEM DESCRIPTION/ PROJECT LOCATION	DATE LET	UNIT/ QUANTITY	ENGR. EST.	AVERAGE BID	AWARDED BID
===== 210-00809		Res Blank Sign (Fib Opt)		Each	=====	=====	=====
MTCE0641-103		MTCE R3 FY20 SH 64 RANGELY PE	05/02/19	1.00	200.00	4520.00	4110.00
		WEIGHTED AVERAGE FOR THE SECOND QUARTER		1.00	200.00	4520.00	4110.00
		WEIGHTED AVERAGE FOR THE YEAR		1.00	200.00	4520.00	4110.00
===== 210-00810		Res Ground Sign		Each	=====	=====	=====
ER119A-065		PR SH 119A BOULDER CANYON	01/03/19	2.00	300.00	178.05	350.00
STA119A-069		SH 119: NEDERLAND - EAST					
STR0132-021		SH 13-MOFFAT COUNTY-CR 3 SOUT	01/10/19	13.00	400.00	331.60	300.00
STR141A-047		SH 141 MP 120-143 MESA COUNTY	01/17/19	32.00	300.00	235.63	260.00
NHPP0701-241		I-70 TRUCK PARKING GARFIELD C	01/17/19	4.00	300.00	438.82	400.00
STR0241-062		US 24 143.4 - 148	01/24/19	24.00	250.00	376.67	340.00
ER072A-040		PR SH72A FLOOD PERMANENT REPA	01/31/19	24.00	300.00	253.78	400.00
NHPP072A-041		PR SH72A FLOOD PERMANENT REPA					
STA067A-038		SH 67 SEDALIA RESURFACING	01/31/19	4.00	250.00	315.30	55.00
NH2871-035		US 287 PASSING LANES SOUTH OF	02/07/19	13.00	250.00	329.92	315.00
NHPP145A-065		SH 145 PASSING LANES AT DEEP	02/14/19	6.00	250.00	319.22	360.00
NHPP1601-073		US 160 PASSING LANE NORTH OF	03/07/19	12.00	400.00	315.00	280.00
FBR0253-247		I25 AT VINE DRIVE BRIDGE REPL	03/07/19	13.00	250.00	491.50	1500.00
C R100-315		R1 ADA CURB RAMPS - PH 5	03/07/19	6.00	300.00	265.00	250.00
SHE2254-090		Colfax & I-225, Colfax & Cham	03/07/19	8.00	250.00	210.00	325.00
NHPP050A-033		US50 West of Delta EB Lanes R	03/14/19	10.00	300.00	258.33	275.00
NHPP0503-087		US 50 PASSING LANES EAST OF S	03/21/19	1.00	280.00	500.00	400.00
SHE 0252-481		I-25 RAMP METER INSTALLATION	03/21/19	1.00	300.00	333.33	340.00
SHER100-308		MIDPOINT - SIGNAL CONST PACKA	03/21/19	3.00	260.00	710.00	770.00
STA0131-070 HMA ALT		SH 13 CR 5 NORTH AND SOUTH	03/28/19	40.00	300.00	274.54	273.00
STA0131-070 PCCP ALT		SH 13 CR 5 NORTH AND SOUTH					
		WEIGHTED AVERAGE FOR THE FIRST QUARTER		216.00	295.19	313.19	392.73
NHPP030A-035		US 285/SH30	04/04/19	11.00	250.00	398.00	398.00
IM0252-472		I-25 CABLE BARRIER PHASE III	04/04/19	2.00	300.00	400.00	500.00
FSA0252-468		I-25 AND PLUM CREEK IMPROVEME	04/18/19	4.00	250.00	685.25	830.00
NHPP0703-445		I-70 WESTBOUND PEAK PERIOD SH	04/25/19	11.00	300.00	863.86	445.00
C2571-013		SH257 & 392:WINDSOR CURB RAMP	05/02/19	4.00	325.00	658.67	200.00
MTCE0641-103		MTCE R3 FY20 SH 64 RANGELY PE	05/02/19	3.00	250.00	925.00	650.00
FSA2873-190		US 287 AND FOOTHILLS PARKWAY	05/02/19	1.00	250.00	510.00	750.00
IM0252-456		I-25 COLORADO SPRINGS RAMP ME	05/16/19	20.00	250.00	389.00	382.00
FSA0703-454		EB I-70 AUX LANE WARD TO KIPL	05/16/19	5.00	250.00	335.93	270.00

PROJECT NUMBER	ITEM NUMBER/ PROJECT LOCATION	ITEM DESCRIPTION/ PROJECT LOCATION	DATE LET	UNIT/ QUANTITY	ENGR. EST.	AVERAGE BID	AWARDED BID
===== 210-00810		Res Ground Sign		Each =====			
CR300-248		CRAIG RESIDENCY ADA RAMPS	05/16/19	39.00	400.00	231.00	150.00
SHE0701-243		I-70 EXIT 26 DDI MODIFICATION	05/16/19	5.00	250.00	326.25	500.00
	WEIGHTED AVERAGE FOR THE SECOND QUARTER			105.00	314.76	411.67	327.93
	WEIGHTED AVERAGE FOR THE YEAR			321.00	301.59	335.03	370.13
===== 210-00815		Res Sign Panel		Each =====			
NHPPR500-173		US 160_550 DURANGO SIGNALS OP	01/03/19	6.00	200.00	421.00	242.00
SHER100-289		INTERSECTIONS @ SH83 & LONGS	01/03/19	4.00	150.00	584.00	555.00
ER119A-065		PR SH 119A BOULDER CANYON	01/03/19	1.00	300.00	120.16	110.00
STA119A-069		SH 119: NEDERLAND - EAST					
STAM086-075		SH96A ABRIENDO - ORMAN SAFETY	01/31/19	22.00	174.70	140.00	30.00
STA067A-038		SH 67 SEDALIA RESURFACING	01/31/19	2.00	150.00	417.64	65.00
SHER100-284		FY19 NORTH SIGNAL PKG	02/21/19	11.00	200.00	581.67	540.00
FBR0253-247		I25 AT VINE DRIVE BRIDGE REPL	03/07/19	2.00	391.40	134.24	150.00
NHPP006A-058		US 6 LOVELAND PASS - I-70 (FY	03/07/19	2.00	65.00	256.65	163.29
SHE2254-090		Colfax & I-225, Colfax & Cham	03/07/19	4.00	200.00	147.50	175.00
SHER100-308		MIDPOINT - SIGNAL CONST PACKA	03/21/19	7.00	160.00	95.00	90.00
NHPP2254-089		I-225 RESURFACING FROM I-25 T	03/21/19	11.00	250.00	81.64	170.00
STM0242-077		US24 - 8TH ST TO WEST OF MANI	03/28/19	1.00	215.87	201.67	250.00
	WEIGHTED AVERAGE FOR THE FIRST QUARTER			73.00	195.10	255.12	199.84
NHPP030A-035		US 285/SH30	04/04/19	1.00	350.00	100.00	100.00
FSA0252-468		I-25 AND PLUM CREEK IMPROVEME	04/18/19	4.00	400.00	168.75	171.00
FSA2873-190		US 287 AND FOOTHILLS PARKWAY	05/02/19	1.00	150.00	347.50	475.00
NHPP030A-036		SH 30 & TOWER RD IMPROVEMENTS	06/13/19	4.00	450.00	33.00	33.00
	WEIGHTED AVERAGE FOR THE SECOND QUARTER			10.00	390.00	157.70	139.10
	WEIGHTED AVERAGE FOR THE YEAR			83.00	218.58	246.23	192.53
===== 210-00816		Res Sign Panel (Spec)		Each =====			
MTCE0641-103		MTCE R3 FY20 SH 64 RANGELY PE	05/02/19	1.00	3000.00	680.00	1000.00
	WEIGHTED AVERAGE FOR THE SECOND QUARTER			1.00	3000.00	680.00	1000.00
	WEIGHTED AVERAGE FOR THE YEAR			1.00	3000.00	680.00	1000.00

PROJECT NUMBER	ITEM NUMBER/ PROJECT LOCATION	ITEM DESCRIPTION/ PROJECT LOCATION	DATE LET	UNIT/ QUANTITY	ENGR. EST.	AVERAGE BID	AWARDED BID
===== 210-00820		Res Var Mesg Sign		Each			
NHPP0503-087		US 50 PASSING LANES EAST OF S	03/21/19	1.00	7000.00	3500.00	5000.00
		WEIGHTED AVERAGE FOR THE FIRST QUARTER		1.00	7000.00	3500.00	5000.00
NHPP0703-445		I-70 WESTBOUND PEAK PERIOD SH	04/25/19	1.00	5000.00	19123.06	20208.00
		WEIGHTED AVERAGE FOR THE SECOND QUARTER		1.00	5000.00	19123.06	20208.00
		WEIGHTED AVERAGE FOR THE YEAR		2.00	6000.00	12873.83	12604.00
===== 210-00827		Res Pull Box		Each			
NHPP0741-022		SH 74: I-70 TO CR 65 RESURFAC	02/14/19	4.00	579.00	244.20	240.00
C R100-315		R1 ADA CURB RAMPS - PH 5	03/07/19	10.00	265.00	742.50	385.00
		WEIGHTED AVERAGE FOR THE FIRST QUARTER		14.00	354.71	521.03	343.57
NHPP030A-035		US 285/SH30	04/04/19	9.00	365.00	825.00	825.00
C2571-013		SH257 & 392:WINDSOR CURB RAMP	05/02/19	4.00	325.00	2336.67	350.00
MTCE0641-103		MTCE R3 FY20 SH 64 RANGELY PE	05/02/19	1.00	500.00	1210.00	1100.00
STMC430-020		ADA RAMPS DIVIDE ESB	05/23/19	2.00	400.00	1000.00	1000.00
		WEIGHTED AVERAGE FOR THE SECOND QUARTER		16.00	367.81	1595.40	745.31
		WEIGHTED AVERAGE FOR THE YEAR		30.00	361.70	961.35	557.83
===== 210-00831		Res Traf Sig Head		Each			
NHPPR500-173		US 160_550 DURANGO SIGNALS OP	01/03/19	3.00	400.00	504.50	234.00
		WEIGHTED AVERAGE FOR THE FIRST QUARTER		3.00	400.00	504.50	234.00
FSA0252-468		I-25 AND PLUM CREEK IMPROVEME	04/18/19	7.00	300.00	333.75	325.00
		WEIGHTED AVERAGE FOR THE SECOND QUARTER		7.00	300.00	333.75	325.00
		WEIGHTED AVERAGE FOR THE YEAR		10.00	330.00	363.88	297.70

COLORADO DEPARTMENT OF TRANSPORTATION
ITEM UNIT COSTS BY PROJECTS -- 2019 COST DATA

13:44 Wednesday, August 7, 2019 89

PROJECT NUMBER	ITEM NUMBER/ PROJECT LOCATION	ITEM DESCRIPTION/ PROJECT LOCATION	DATE LET	UNIT/ QUANTITY	ENGR. EST.	AVERAGE BID	AWARDED BID
===== 210-00840		Res Traf Sig Pole		Each	=====	=====	=====
FSA0252-468		I-25 AND PLUM CREEK IMPROVEME	04/18/19	1.00	3500.00	3165.50	4493.00
	WEIGHTED	AVERAGE FOR THE SECOND QUARTER		1.00	3500.00	3165.50	4493.00
		WEIGHTED AVERAGE FOR THE YEAR		1.00	3500.00	3165.50	4493.00
===== 210-00845		Res Traf Sig Cntrlr		Each	=====	=====	=====
STAM086-075		SH96A ABRIENDO - ORMAN SAFETY	01/31/19	3.00	1024.66	1125.00	1325.00
	WEIGHTED	AVERAGE FOR THE FIRST QUARTER		3.00	1024.66	1125.00	1325.00
NHPP0703-445		I-70 WESTBOUND PEAK PERIOD SH	04/25/19	4.00	1500.00	455.56	481.00
	WEIGHTED	AVERAGE FOR THE SECOND QUARTER		4.00	1500.00	455.56	481.00
		WEIGHTED AVERAGE FOR THE YEAR		7.00	1296.28	742.46	842.71
===== 210-00847		Res Trav Time Ind		Each	=====	=====	=====
ITSSW01-638		ETHERNET PHASE III (PRIMARYLY	02/07/19	4.00	650.00	1784.50	2000.00
	WEIGHTED	AVERAGE FOR THE FIRST QUARTER		4.00	650.00	1784.50	2000.00
NHPP0703-445		I-70 WESTBOUND PEAK PERIOD SH	04/25/19	2.00	1100.00	4311.80	6740.00
	WEIGHTED	AVERAGE FOR THE SECOND QUARTER		2.00	1100.00	4311.80	6740.00
		WEIGHTED AVERAGE FOR THE YEAR		6.00	800.00	2867.63	3580.00
===== 210-00848		Res Traf Sig Control+Cab		Each	=====	=====	=====
NHPP0821-107		SH 82 GLENWOOD SPRINGS TO CA	02/07/19	3.00	3000.00	6100.00	6000.00
	WEIGHTED	AVERAGE FOR THE FIRST QUARTER		3.00	3000.00	6100.00	6000.00
		WEIGHTED AVERAGE FOR THE YEAR		3.00	3000.00	6100.00	6000.00

COLORADO DEPARTMENT OF TRANSPORTATION
ITEM UNIT COSTS BY PROJECTS -- 2019 COST DATA

13:44 Wednesday, August 7, 2019 90

PROJECT NUMBER	ITEM NUMBER/ PROJECT LOCATION	ITEM DESCRIPTION/ PROJECT LOCATION	DATE LET	UNIT/ QUANTITY	ENGR. EST.	AVERAGE BID	AWARDED BID
===== 210-00855		Res Traf Sig Control Cab		Each	=====	=====	=====
NHPP0703-445		I-70 WESTBOUND PEAK PERIOD SH	04/25/19	1.00	4000.00	9678.98	10597.00
	WEIGHTED	AVERAGE FOR THE SECOND QUARTER		1.00	4000.00	9678.98	10597.00
		WEIGHTED AVERAGE FOR THE YEAR		1.00	4000.00	9678.98	10597.00
===== 210-00858		Res Pedestal Pole		Each	=====	=====	=====
NHPP030A-035		US 285/SH30	04/04/19	1.00	450.00	2350.00	2350.00
CR300-248		CRAIG RESIDENCY ADA RAMPS	05/16/19	1.00	700.00	1200.00	1600.00
	WEIGHTED	AVERAGE FOR THE SECOND QUARTER		2.00	575.00	1487.50	1975.00
		WEIGHTED AVERAGE FOR THE YEAR		2.00	575.00	1487.50	1975.00
===== 210-00859		Mod Ped Push Button		Each	=====	=====	=====
C R100-315		R1 ADA CURB RAMPS - PH 5	03/07/19	12.00	250.00	697.50	445.00
	WEIGHTED	AVERAGE FOR THE FIRST QUARTER		12.00	250.00	697.50	445.00
		WEIGHTED AVERAGE FOR THE YEAR		12.00	250.00	697.50	445.00
===== 210-00860		Res Ped Push Button		Each	=====	=====	=====
NHPP0741-022		SH 74: I-70 TO CR 65 RESURFAC	02/14/19	1.00	1500.00	80.43	80.00
C R100-315		R1 ADA CURB RAMPS - PH 5	03/07/19	28.00	180.00	827.50	655.00
	WEIGHTED	AVERAGE FOR THE FIRST QUARTER		29.00	225.52	777.70	635.17
C2571-013		SH257 & 392:WINDSOR CURB RAMP	05/02/19	14.00	71.00	1592.67	1430.00
CR300-248		CRAIG RESIDENCY ADA RAMPS	05/16/19	1.00	200.00	397.33	420.00
	WEIGHTED	AVERAGE FOR THE SECOND QUARTER		15.00	79.60	1512.98	1362.67
		WEIGHTED AVERAGE FOR THE YEAR		44.00	175.77	1092.82	883.18
===== 210-00865		Res Ped Sig Head		Each	=====	=====	=====
FSA0252-468		I-25 AND PLUM CREEK IMPROVEME	04/18/19	2.00	100.00	242.50	325.00
	WEIGHTED	AVERAGE FOR THE SECOND QUARTER		2.00	100.00	242.50	325.00
		WEIGHTED AVERAGE FOR THE YEAR		2.00	100.00	242.50	325.00

COLORADO DEPARTMENT OF TRANSPORTATION
 ITEM UNIT COSTS BY PROJECTS -- 2019 COST DATA

13:44 Wednesday, August 7, 2019 91

PROJECT NUMBER	ITEM NUMBER/ PROJECT LOCATION	ITEM DESCRIPTION/ PROJECT LOCATION	DATE LET	UNIT/ QUANTITY	ENGR. EST.	AVERAGE BID	AWARDED BID
===== 210-00867		Res Fire Preempt Unit		Each	=====		
SHER100-289		INTERSECTIONS @ SH83 & LONGS	01/03/19	2.00	500.00	522.80	500.00
SHER100-284		FY19 NORTH SIGNAL PKG	02/21/19	5.00	500.00	520.33	425.00
SHER100-308		MIDPOINT - SIGNAL CONST PACKA	03/21/19	9.00	475.00	810.00	410.00
		WEIGHTED AVERAGE FOR THE FIRST QUARTER		16.00	485.94	642.16	425.94
FSA2873-190		US 287 AND FOOTHILLS PARKWAY	05/02/19	1.00	800.00	862.50	935.00
		WEIGHTED AVERAGE FOR THE SECOND QUARTER		1.00	800.00	862.50	935.00
		WEIGHTED AVERAGE FOR THE YEAR		17.00	504.41	651.96	455.88
===== 210-00875		Res Surface Cond Analyser		Each	=====		
ITSSW01-638		ETHERNET PHASE III (PRIMARYLY	02/07/19	1.00	800.00	3250.00	3000.00
		WEIGHTED AVERAGE FOR THE FIRST QUARTER		1.00	800.00	3250.00	3000.00
		WEIGHTED AVERAGE FOR THE YEAR		1.00	800.00	3250.00	3000.00
===== 210-00882		Res Detector		Each	=====		
SHE2254-090		Colfax & I-225, Colfax & Cham	03/07/19	6.00	2000.00	990.00	1250.00
		WEIGHTED AVERAGE FOR THE FIRST QUARTER		6.00	2000.00	990.00	1250.00
		WEIGHTED AVERAGE FOR THE YEAR		6.00	2000.00	990.00	1250.00
===== 210-00890		Res Int Detect Sys (Camera)		Each	=====		
STAM086-075		SH96A ABRIENDO - ORMAN SAFETY	01/31/19	8.00	8000.00	1625.00	975.00
NHPP2254-089		I-225 RESURFACING FROM I-25 T	03/21/19	1.00	1300.00	1151.52	850.00
		WEIGHTED AVERAGE FOR THE FIRST QUARTER		9.00	7255.56	1572.39	961.11
FSA2873-190		US 287 AND FOOTHILLS PARKWAY	05/02/19	4.00	950.00	1475.00	1250.00
		WEIGHTED AVERAGE FOR THE SECOND QUARTER		4.00	950.00	1475.00	1250.00
		WEIGHTED AVERAGE FOR THE YEAR		13.00	5315.38	1550.13	1050.00

PROJECT NUMBER	ITEM NUMBER/ PROJECT LOCATION	ITEM DESCRIPTION/ PROJECT LOCATION	DATE LET	UNIT/ QUANTITY	ENGR. EST.	AVERAGE BID	AWARDED BID
=====	210-01000	Res Fence		Lin Foot	=====		
STR0241-062		US 24 143.4 - 148	01/24/19	426.00	15.00	45.17	60.00
NHPPR100-250		PACKAGE A (I-25 / I-70 / I-76	01/24/19	20.00	25.00	69.64	75.00
NHPP0821-107		SH 82 GLENWOOD SPRINGS TO CA	02/07/19	226.00	18.00	22.00	33.00
STM0242-077		US24 - 8TH ST TO WEST OF MANI	03/28/19	570.00	22.00	27.83	25.50
		WEIGHTED AVERAGE FOR THE FIRST QUARTER		1,242.00	18.92	34.53	39.50
FSA0703-454		EB I-70 AUX LANE WARD TO KIPL	05/16/19	200.00	80.00	27.23	38.50
CR300-248		CRAIG RESIDENCY ADA RAMPS	05/16/19	22.00	25.00	46.33	20.00
STR 141A-040		R5 YEAR 4 BRDG PREV MAINT RAM	06/20/19	30.00	40.00	68.00	50.00
NHPP160A-030		US160 MM 43.2, 150.4, 156.3,	06/20/19	30.00	15.00	19.25	16.00
		WEIGHTED AVERAGE FOR THE SECOND QUARTER		282.00	64.54	31.34	35.89
		WEIGHTED AVERAGE FOR THE YEAR		1,524.00	27.36	33.95	38.83
=====	210-01011	Res Gate		Each	=====		
NHPP1601-073		US 160 PASSING LANE NORTH OF	03/07/19	3.00	700.00	265.00	300.00
		WEIGHTED AVERAGE FOR THE FIRST QUARTER		3.00	700.00	265.00	300.00
		WEIGHTED AVERAGE FOR THE YEAR		3.00	700.00	265.00	300.00
=====	210-01050	Res C L Fence		Lin Foot	=====		
ITSSW01-638		ETHERNET PHASE III (PRIMARYLY	02/07/19	35.00	23.00	18.50	10.00
		WEIGHTED AVERAGE FOR THE FIRST QUARTER		35.00	23.00	18.50	10.00
		WEIGHTED AVERAGE FOR THE YEAR		35.00	23.00	18.50	10.00
=====	210-01130	Res Gdrail Ty 3		Lin Foot	=====		
NHPP0821-107		SH 82 GLENWOOD SPRINGS TO CA	02/07/19	50.00	145.00	31.00	22.00
		WEIGHTED AVERAGE FOR THE FIRST QUARTER		50.00	145.00	31.00	22.00

COLORADO DEPARTMENT OF TRANSPORTATION
 ITEM UNIT COSTS BY PROJECTS -- 2019 COST DATA

13:44 Wednesday, August 7, 2019 93

PROJECT NUMBER	ITEM NUMBER/ PROJECT LOCATION	ITEM DESCRIPTION/ PROJECT LOCATION	DATE LET	UNIT/ QUANTITY	ENGR. EST.	AVERAGE BID	AWARDED BID
===== 210-01130		Res Gdrail Ty 3		Lin Foot	=====		
STR 141A-040		R5 YEAR 4 BRDG PREV MAINT RAM	06/20/19	37.50	50.00	97.60	110.00
		WEIGHTED AVERAGE FOR THE SECOND QUARTER		37.50	50.00	97.60	110.00
		WEIGHTED AVERAGE FOR THE YEAR		87.50	104.29	59.54	59.71
===== 210-01180		Reset Guardrail (Special)		Lin Foot	=====		
STR 141A-040		R5 YEAR 4 BRDG PREV MAINT RAM	06/20/19	50.00	60.00	182.50	180.00
		WEIGHTED AVERAGE FOR THE SECOND QUARTER		50.00	60.00	182.50	180.00
		WEIGHTED AVERAGE FOR THE YEAR		50.00	60.00	182.50	180.00
===== 210-01190		Reset Tensioned Cable Barrier		Lin Foot	=====		
IM0252-472		I-25 CABLE BARRIER PHASE III	04/04/19	14,903.00	18.00	23.50	25.00
		WEIGHTED AVERAGE FOR THE SECOND QUARTER		14,903.00	18.00	23.50	25.00
		WEIGHTED AVERAGE FOR THE YEAR		14,903.00	18.00	23.50	25.00
===== 210-01700		Res Sprinkler Head		Each	=====		
C R100-315		R1 ADA CURB RAMPS - PH 5	03/07/19	15.00	75.00	78.00	58.00
		WEIGHTED AVERAGE FOR THE FIRST QUARTER		15.00	75.00	78.00	58.00
CR300-248		CRAIG RESIDENCY ADA RAMPS	05/16/19	33.00	70.00	196.67	100.00
		WEIGHTED AVERAGE FOR THE SECOND QUARTER		33.00	70.00	196.67	100.00
		WEIGHTED AVERAGE FOR THE YEAR		48.00	71.56	169.07	86.88
===== 210-01710		Res Valve		Each	=====		
STR0241-062		US 24 143.4 - 148	01/24/19	3.00	1700.00	3933.33	4900.00
		WEIGHTED AVERAGE FOR THE FIRST QUARTER		3.00	1700.00	3933.33	4900.00
		WEIGHTED AVERAGE FOR THE YEAR		3.00	1700.00	3933.33	4900.00

COLORADO DEPARTMENT OF TRANSPORTATION
 ITEM UNIT COSTS BY PROJECTS -- 2019 COST DATA

13:44 Wednesday, August 7, 2019 94

PROJECT NUMBER	ITEM NUMBER/ PROJECT LOCATION	ITEM DESCRIPTION/ PROJECT LOCATION	DATE LET	UNIT/ QUANTITY	ENGR. EST.	AVERAGE BID	AWARDED BID
=====	210-02510	Relay Sprinkler System		LUMP SUM	=====		
ER119A-065 STA119A-069		PR SH 119A BOULDER CANYON SH 119: NEDERLAND - EAST	01/03/19	1.00	6000.00	29293.92	26000.00
		WEIGHTED AVERAGE FOR THE FIRST QUARTER		1.00	6000.00	29293.92	26000.00
		WEIGHTED AVERAGE FOR THE YEAR		1.00	6000.00	29293.92	26000.00
=====	210-02804	Grinding: Sidwlk and/or Curb Ramp Repair		Lin Foot	=====		
C2571-013 CR300-248		SH257 & 392:WINDSOR CURB RAMP CRAIG RESIDENCY ADA RAMPS	05/02/19 05/16/19	25.00 99.00	42.00 30.00	53.33 76.00	40.00 15.00
		WEIGHTED AVERAGE FOR THE SECOND QUARTER		124.00	32.42	71.43	20.04
		WEIGHTED AVERAGE FOR THE YEAR		124.00	32.42	71.43	20.04
=====	210-02806	Grinding: Slope Correction		Sq Foot	=====		
C2571-013		SH257 & 392:WINDSOR CURB RAMP	05/02/19	400.00	70.00	44.17	10.00
		WEIGHTED AVERAGE FOR THE SECOND QUARTER		400.00	70.00	44.17	10.00
		WEIGHTED AVERAGE FOR THE YEAR		400.00	70.00	44.17	10.00
=====	210-04010	Adj Manhole		Each	=====		
SHER100-289 FBR0341-087 STR0241-062 NHPP0821-107 NHPP0741-022 C R100-315 SHE2254-090 NHPP2254-089		INTERSECTIONS @ SH83 & LONGS US 34 OVER NORTH FORK CO RIVE US 24 143.4 - 148 SH 82 GLENWOOD SPRINGS TO CA SH 74: I-70 TO CR 65 RESURFAC R1 ADA CURB RAMPS - PH 5 Colfax & I-225, Colfax & Cham I-225 RESURFACING FROM I-25 T	01/03/19 01/10/19 01/24/19 02/07/19 02/14/19 03/07/19 03/07/19 03/21/19	1.00 2.00 23.00 2.00 2.00 1.00 7.00 68.00	750.00 820.00 1000.00 900.00 900.00 600.00 700.00 650.00	565.00 2159.50 1145.00 675.00 1200.00 970.00 425.00 815.93	475.00 1448.39 800.00 100.00 650.00 950.00 500.00 750.00
		WEIGHTED AVERAGE FOR THE FIRST QUARTER		106.00	742.36	925.74	742.66
NHPP030A-035		US 285/SH30	04/04/19	90.00	650.00	700.00	700.00

COLORADO DEPARTMENT OF TRANSPORTATION
 ITEM UNIT COSTS BY PROJECTS -- 2019 COST DATA

13:44 Wednesday, August 7, 2019 95

PROJECT NUMBER	ITEM NUMBER/ PROJECT LOCATION	ITEM DESCRIPTION/ PROJECT LOCATION	DATE LET	UNIT/ QUANTITY	ENGR. EST.	AVERAGE BID	AWARDED BID
=====	210-04010	Adj Manhole		Each =====			
STMC430-020		ADA RAMPS DIVIDE ESB	05/23/19	1.00	700.00	3000.00	3000.00
NHPP030A-036		SH 30 & TOWER RD IMPROVEMENTS	06/13/19	1.00	700.00	700.00	700.00
	WEIGHTED AVERAGE FOR THE SECOND QUARTER			92.00	651.09	725.00	725.00
	WEIGHTED AVERAGE FOR THE YEAR			198.00	699.95	880.69	734.45
=====	210-04015	Modify Manhole		Each =====			
STR0241-062		US 24 143.4 - 148	01/24/19	16.00	10000.00	4233.33	4800.00
	WEIGHTED AVERAGE FOR THE FIRST QUARTER			16.00	10000.00	4233.33	4800.00
	WEIGHTED AVERAGE FOR THE YEAR			16.00	10000.00	4233.33	4800.00
=====	210-04020	Modify Inlet		Each =====			
ER119A-065		PR SH 119A BOULDER CANYON	01/03/19	4.00	2500.00	3848.13	3200.00
STA119A-069		SH 119: NEDERLAND - EAST					
	WEIGHTED AVERAGE FOR THE FIRST QUARTER			4.00	2500.00	3848.13	3200.00
IM0252-472		I-25 CABLE BARRIER PHASE III	04/04/19	2.00	2000.00	2500.00	3000.00
FSA0703-454		EB I-70 AUX LANE WARD TO KIPL	05/16/19	1.00	3500.00	5735.16	2500.00
	WEIGHTED AVERAGE FOR THE SECOND QUARTER			3.00	2500.00	3886.50	2833.33
	WEIGHTED AVERAGE FOR THE YEAR			7.00	2500.00	3855.02	3042.86
=====	210-04025	Modify Structure		Each =====			
STR 141A-040		R5 YEAR 4 BRDG PREV MAINT RAM	06/20/19	1.00	6000.00	12250.00	5000.00
	WEIGHTED AVERAGE FOR THE SECOND QUARTER			1.00	6000.00	12250.00	5000.00
	WEIGHTED AVERAGE FOR THE YEAR			1.00	6000.00	12250.00	5000.00
=====	210-04030	Modify Guardrail		Lin Foot =====			
IM0251-351		I-25 South of Pueblo MP 79.6	01/03/19	4,388.00	12.00	9.18	9.52
	WEIGHTED AVERAGE FOR THE FIRST QUARTER			4,388.00	12.00	9.18	9.52
	WEIGHTED AVERAGE FOR THE YEAR			4,388.00	12.00	9.18	9.52

COLORADO DEPARTMENT OF TRANSPORTATION
 ITEM UNIT COSTS BY PROJECTS -- 2019 COST DATA

13:44 Wednesday, August 7, 2019 96

PROJECT NUMBER	ITEM NUMBER/ PROJECT LOCATION	ITEM DESCRIPTION/ PROJECT LOCATION	DATE LET	UNIT/ QUANTITY	ENGR. EST.	AVERAGE BID	AWARDED BID
===== 210-04050		Adj Valve Box		Each	=====		
FBR0341-087		US 34 OVER NORTH FORK CO RIVE	01/10/19	1.00	540.00	1178.44	245.62
STR0241-062		US 24 143.4 - 148	01/24/19	57.00	500.00	921.67	430.00
NHPP0821-107		SH 82 GLENWOOD SPRINGS TO CA	02/07/19	2.00	610.00	250.00	75.00
C R100-315		R1 ADA CURB RAMPS - PH 5	03/07/19	10.00	400.00	497.50	500.00
SHE2254-090		Colfax & I-225, Colfax & Cham	03/07/19	6.00	300.00	325.00	300.00
		WEIGHTED AVERAGE FOR THE FIRST QUARTER		76.00	474.47	842.84	417.18
NHPP030A-035		US 285/SH30	04/04/19	160.00	350.00	525.00	525.00
MTCE0641-103		MTCE R3 FY20 SH 64 RANGELY PE	05/02/19	4.00	1500.00	407.50	700.00
CR300-248		CRAIG RESIDENCY ADA RAMPS	05/16/19	2.00	350.00	661.00	450.00
NHPP030A-036		SH 30 & TOWER RD IMPROVEMENTS	06/13/19	2.00	400.00	425.00	425.00
		WEIGHTED AVERAGE FOR THE SECOND QUARTER		168.00	377.98	523.16	527.08
		WEIGHTED AVERAGE FOR THE YEAR		244.00	408.03	698.20	492.85
===== 210-04200		Adj Gdrail		Lin Foot	=====		
STM0242-077		US24 - 8TH ST TO WEST OF MANI	03/28/19	655.00	150.00	17.00	16.00
		WEIGHTED AVERAGE FOR THE FIRST QUARTER		655.00	150.00	17.00	16.00
NHPP0703-445		I-70 WESTBOUND PEAK PERIOD SH	04/25/19	2,640.00	22.00	20.58	21.00
		WEIGHTED AVERAGE FOR THE SECOND QUARTER		2,640.00	22.00	20.58	21.00
		WEIGHTED AVERAGE FOR THE YEAR		3,295.00	47.44	19.87	20.01
===== 211-00220		2 In Cored Drilled Hole		Each	=====		
ER119A-065		PR SH 119A BOULDER CANYON	01/03/19	20.00	93.00	2168.72	4900.00
STA119A-069		SH 119: NEDERLAND - EAST					
		WEIGHTED AVERAGE FOR THE FIRST QUARTER		20.00	93.00	2168.72	4900.00
		WEIGHTED AVERAGE FOR THE YEAR		20.00	93.00	2168.72	4900.00

PROJECT NUMBER	ITEM NUMBER/ PROJECT LOCATION	ITEM DESCRIPTION/ PROJECT LOCATION	DATE LET	UNIT/ QUANTITY	ENGR. EST.	AVERAGE BID	AWARDED BID
=====	211-01111	Rock Reinf (Dowels)		Lin Foot	=====		
NHPP0703-445		I-70 WESTBOUND PEAK PERIOD SH	04/25/19	300.00	115.00	85.69	91.00
	WEIGHTED	AVERAGE FOR THE SECOND QUARTER		300.00	115.00	85.69	91.00
		WEIGHTED AVERAGE FOR THE YEAR		300.00	115.00	85.69	91.00
=====	211-01115	Rock Reinf (No.10)		Lin Foot	=====		
ER119A-065 STA119A-069		PR SH 119A BOULDER CANYON SH 119: NEDERLAND - EAST	01/03/19	15,225.00	90.00	98.80	98.00
	WEIGHTED	AVERAGE FOR THE FIRST QUARTER		15,225.00	90.00	98.80	98.00
NHPP0703-445		I-70 WESTBOUND PEAK PERIOD SH	04/25/19	400.00	170.00	87.74	92.00
	WEIGHTED	AVERAGE FOR THE SECOND QUARTER		400.00	170.00	87.74	92.00
		WEIGHTED AVERAGE FOR THE YEAR		15,625.00	92.05	98.69	97.85
=====	211-01300	Rock Anchor		Each	=====		
C0502-085		US 50 MM 201.8 MONARCH AVALAN	06/27/19	12.00	2500.00	5649.50	3470.00
	WEIGHTED	AVERAGE FOR THE SECOND QUARTER		12.00	2500.00	5649.50	3470.00
		WEIGHTED AVERAGE FOR THE YEAR		12.00	2500.00	5649.50	3470.00
=====	211-03005	Dewatering		LUMP SUM	=====		
SHER100-289		INTERSECTIONS @ SH83 & LONGS	01/03/19	1.00	5000.00	4613.20	4800.00
ER119A-065 STA119A-069		PR SH 119A BOULDER CANYON SH 119: NEDERLAND - EAST	01/03/19	1.00	30000.00	122791.58	185000.00
STR0241-062		US 24 143.4 - 148	01/24/19	1.00	5000.00	34058.33	20000.00
NHPP0821-107		SH 82 GLENWOOD SPRINGS TO CA	02/07/19	1.00	40000.00	54600.00	84200.00
STM0242-077		US24 - 8TH ST TO WEST OF MANI	03/28/19	1.00	25000.00	29066.67	15000.00
	WEIGHTED	AVERAGE FOR THE FIRST QUARTER		5.00	21000.00	62093.98	61800.00
		WEIGHTED AVERAGE FOR THE YEAR		5.00	21000.00	62093.98	61800.00

COLORADO DEPARTMENT OF TRANSPORTATION
 ITEM UNIT COSTS BY PROJECTS -- 2019 COST DATA

13:44 Wednesday, August 7, 2019 98

PROJECT NUMBER	ITEM NUMBER/ PROJECT LOCATION	ITEM DESCRIPTION/ PROJECT LOCATION	DATE LET	UNIT/ QUANTITY	ENGR. EST.	AVERAGE BID	AWARDED BID
===== 212-00005		Seeding (Native)		Pound	=====	=====	=====
NH2871-035		US 287 PASSING LANES SOUTH OF	02/07/19	10.00	500.00	892.49	446.25
		WEIGHTED AVERAGE FOR THE FIRST QUARTER		10.00	500.00	892.49	446.25
		WEIGHTED AVERAGE FOR THE YEAR		10.00	500.00	892.49	446.25
===== 212-00006		Seeding (Native)		Acre	=====	=====	=====
IM0251-351		I-25 South of Pueblo MP 79.6	01/03/19	1.00	1500.00	1695.06	1458.73
FSA0142-068		SH 14 & WCR 33 INTERSECTION I	01/03/19	0.13	5000.00	3411.00	6215.00
ER119A-065		PR SH 119A BOULDER CANYON	01/03/19	11.17	1000.00	834.88	450.00
STA119A-069		SH 119: NEDERLAND - EAST					
STR0132-021		SH 13-MOFFAT COUNTY-CR 3 SOUT	01/10/19	45.00	1000.00	507.80	428.00
FBR0341-087		US 34 OVER NORTH FORK CO RIVE	01/10/19	0.46	3000.00	2182.32	1452.16
STR141A-047		SH 141 MP 120-143 MESA COUNTY	01/17/19	3.00	3000.00	1421.47	1350.00
NHPP0701-241		I-70 TRUCK PARKING GARFIELD C	01/17/19	0.95	1025.00	1960.13	1300.00
STR0241-062		US 24 143.4 - 148	01/24/19	0.40	1200.00	3413.33	5200.00
ER072A-040		PR SH72A FLOOD PERMANENT REPA	01/31/19	9.00	750.00	839.38	575.00
NHPP072A-041		PR SH72A FLOOD PERMANENT REPA					
STA067A-038		SH 67 SEDALIA RESURFACING	01/31/19	0.10	2500.00	5793.28	9000.00
NHPP0821-107		SH 82 GLENWOOD SPRINGS TO CA	02/07/19	0.37	1025.00	2200.00	1400.00
ITSSW01-638		ETHERNET PHASE III (PRIMARYLY	02/07/19	1.21	800.00	725.00	250.00
NHPP145A-065		SH 145 PASSING LANES AT DEEP	02/14/19	6.60	2000.00	1307.70	675.00
NHPP0741-022		SH 74: I-70 TO CR 65 RESURFAC	02/14/19	0.30	2000.00	1755.65	1955.00
NHPP1601-076		US 160 MANCOS HILL (MP 40.000	02/21/19	0.10	3000.00	2713.33	2500.00
NHPP070A-028		FALL RIVER ROAD BRIDGE	02/21/19	0.10	8333.00	7981.29	4012.00
SHER100-284		FY19 NORTH SIGNAL PKG	02/21/19	0.05	10000.00	9966.67	7600.00
NHPP1601-073		US 160 PASSING LANE NORTH OF	03/07/19	10.70	1500.00	490.00	630.00
FBR0253-247		I25 AT VINE DRIVE BRIDGE REPL	03/07/19	7.80	800.00	899.21	650.00
NHPP006A-058		US 6 LOVELAND PASS - I-70 (FY	03/07/19	0.20	5000.00	2365.44	1730.87
SHE2254-090		Colfax & I-225, Colfax & Cham	03/07/19	0.13	3500.00	2079.96	3000.00
NHPP050A-033		US50 West of Delta EB Lanes R	03/14/19	3.00	1000.00	526.67	580.00
NHPP0503-087		US 50 PASSING LANES EAST OF S	03/21/19	6.24	800.00	725.00	700.00
SHE 0252-481		I-25 RAMP METER INSTALLATION	03/21/19	3.30	800.00	785.67	770.00
SHER100-308		MIDPOINT - SIGNAL CONST PACKA	03/21/19	0.42	825.00	1307.50	1215.00
NHPP2254-089		I-225 RESURFACING FROM I-25 T	03/21/19	0.10	5000.00	3971.35	3500.00
STM0242-077		US24 - 8TH ST TO WEST OF MANI	03/28/19	1.20	796.67	1361.50	884.50
STA0131-070 HMA ALT		SH 13 CR 5 NORTH AND SOUTH	03/28/19	128.00	750.00	383.06	315.00
STA0131-070 PCCP ALT		SH 13 CR 5 NORTH AND SOUTH					
		WEIGHTED AVERAGE FOR THE FIRST QUARTER		241.03	938.11	637.18	513.09
NHPP030A-035		US 285/SH30	04/04/19	0.10	1000.00	680.00	680.00

PROJECT NUMBER	ITEM NUMBER/ PROJECT LOCATION	ITEM DESCRIPTION/ PROJECT LOCATION	DATE LET	UNIT/ QUANTITY	ENGR. EST.	AVERAGE BID	AWARDED BID
===== 212-00006 Seeding (Native) Acre =====							
IM0252-472		I-25 CABLE BARRIER PHASE III	04/04/19	17.30	500.00	585.00	370.00
BR071A-020		REPLACEMENT OF STRUCTURE L-22	04/18/19	1.00	730.00	1853.33	1660.00
FSA0252-468		I-25 AND PLUM CREEK IMPROVEME	04/18/19	0.03	2000.00	15160.75	27743.00
NHPP0703-445		I-70 WESTBOUND PEAK PERIOD SH	04/25/19	23.00	1000.00	1007.70	1000.00
IM0252-456		I-25 COLORADO SPRINGS RAMP ME	05/16/19	0.90	2600.00	1345.33	1335.00
FSA0703-454		EB I-70 AUX LANE WARD TO KIPL	05/16/19	2.00	1500.00	729.30	575.00
FBR0063-057		US-6 F-09-K BRIDGE OVER CASTL	05/30/19	1.40	800.00	1197.50	1045.00
STRR200-257		ROAD CLOSURE GATES ON VARIOUS	05/30/19	0.60	5858.00	1315.00	750.00
ER145A-081		SH 145 MP 21 EMERGENCY ROCKFA	06/07/19	1.00	1500.00	1690.21	1824.00
NHPP0703-442		I-70 SILVERPLUME SOUNDWALL AN	06/13/19	0.70	2000.00	3341.38	1740.00
NHPP030A-036		SH 30 & TOWER RD IMPROVEMENTS	06/13/19	0.10	2000.00	800.00	800.00
CR500-205		R5 GUARDRAIL END TREATMENT EA	06/13/19	0.15	15000.00	1950.00	1950.00
STR 141A-040		R5 YEAR 4 BRDG PREV MAINT RAM	06/20/19	0.30	3000.00	6300.00	10000.00
NHPP160A-030		US160 MM 43.2, 150.4, 156.3,	06/20/19	1.70	2000.00	968.41	1100.00
C0502-085		US 50 MM 201.8 MONARCH AVALAN	06/27/19	0.20	4000.00	2475.00	3000.00
	WEIGHTED AVERAGE FOR THE SECOND QUARTER			50.48	1049.22	1067.67	893.63
	WEIGHTED AVERAGE FOR THE YEAR			291.51	957.36	686.68	597.52
===== 212-00007 Seeding (Native) (Hydraulic) Acre =====							
ER119A-065		PR SH 119A BOULDER CANYON	01/03/19	1.00	1000.00	1659.16	1000.00
STA119A-069		SH 119: NEDERLAND - EAST					
	WEIGHTED AVERAGE FOR THE FIRST QUARTER			1.00	1000.00	1659.16	1000.00
	WEIGHTED AVERAGE FOR THE YEAR			1.00	1000.00	1659.16	1000.00
===== 212-00009 Seeding (Temporary) Acre =====							
ER119A-065		PR SH 119A BOULDER CANYON	01/03/19	0.53	1000.00	1428.91	800.00
STA119A-069		SH 119: NEDERLAND - EAST					
FBR0341-087		US 34 OVER NORTH FORK CO RIVE	01/10/19	0.11	4000.00	2718.94	1160.69
	WEIGHTED AVERAGE FOR THE FIRST QUARTER			0.64	1515.63	1602.67	861.99
FBR0063-057		US-6 F-09-K BRIDGE OVER CASTL	05/30/19	0.30	600.00	2175.00	1760.00
	WEIGHTED AVERAGE FOR THE SECOND QUARTER			0.30	600.00	2175.00	1760.00
	WEIGHTED AVERAGE FOR THE YEAR			0.94	1223.40	1665.11	1148.59

PROJECT NUMBER	ITEM NUMBER/ PROJECT LOCATION	ITEM DESCRIPTION/ PROJECT LOCATION	DATE LET	UNIT/ QUANTITY	ENGR. EST.	AVERAGE BID	AWARDED BID
=====	212-00022	Seeding (Riparian)		Acre	=====		
ER119A-065		PR SH 119A BOULDER CANYON	01/03/19	0.20	2500.00	3268.29	3500.00
STA119A-069		SH 119: NEDERLAND - EAST					
ER072A-040		PR SH72A FLOOD PERMANENT REPA	01/31/19	1.01	500.00	1348.25	1100.00
NHPP072A-041		PR SH72A FLOOD PERMANENT REPA					
		WEIGHTED AVERAGE FOR THE FIRST QUARTER		1.21	830.58	1572.16	1496.69
		WEIGHTED AVERAGE FOR THE YEAR		1.21	830.58	1572.16	1496.69
=====	212-00028	Seeding (Wetlands)		Acre	=====		
FBR0341-087		US 34 OVER NORTH FORK CO RIVE	01/10/19	0.05	5000.00	7852.58	6983.15
ER072A-040		PR SH72A FLOOD PERMANENT REPA	01/31/19	0.12	10000.00	3375.63	1800.00
NHPP072A-041		PR SH72A FLOOD PERMANENT REPA					
NHPP0821-107		SH 82 GLENWOOD SPRINGS TO CA	02/07/19	0.03	12000.00	29000.00	28000.00
NHPP145A-065		SH 145 PASSING LANES AT DEEP	02/14/19	0.10	5000.00	4943.44	6340.00
STA0131-070 HMA ALT		SH 13 CR 5 NORTH AND SOUTH	03/28/19	0.94	20000.00	2358.43	3120.00
STA0131-070 PCCP ALT		SH 13 CR 5 NORTH AND SOUTH					
		WEIGHTED AVERAGE FOR THE FIRST QUARTER		1.24	17024.19	3531.09	4552.67
NHPP160A-030		US160 MM 43.2, 150.4, 156.3,	06/20/19	0.09	25000.00	1612.50	2100.00
		WEIGHTED AVERAGE FOR THE SECOND QUARTER		0.09	25000.00	1612.50	2100.00
		WEIGHTED AVERAGE FOR THE YEAR		1.33	17563.91	3465.93	4296.00
=====	212-00032	Soil Conditioning		Acre	=====		
FSA0142-068		SH 14 & WCR 33 INTERSECTION I	01/03/19	0.13	5000.00	6043.75	7600.00
ER119A-065		PR SH 119A BOULDER CANYON	01/03/19	10.50	3250.00	3502.89	3400.00
STA119A-069		SH 119: NEDERLAND - EAST					
STR0132-021		SH 13-MOFFAT COUNTY-CR 3 SOUT	01/10/19	45.00	4000.00	371.20	335.00
FBR0341-087		US 34 OVER NORTH FORK CO RIVE	01/10/19	0.46	3300.00	6213.11	7601.33
STR141A-047		SH 141 MP 120-143 MESA COUNTY	01/17/19	3.00	5000.00	4487.47	3750.00
NHPP0701-241		I-70 TRUCK PARKING GARFIELD C	01/17/19	0.95	3200.00	2941.88	925.00
STR0241-062		US 24 143.4 - 148	01/24/19	0.40	3000.00	6853.33	7700.00
ER072A-040		PR SH72A FLOOD PERMANENT REPA	01/31/19	9.00	4200.00	3130.32	2900.00
NHPP072A-041		PR SH72A FLOOD PERMANENT REPA					

PROJECT NUMBER	ITEM NUMBER/ PROJECT LOCATION	ITEM DESCRIPTION/ PROJECT LOCATION	DATE LET	UNIT/ QUANTITY	ENGR. EST.	AVERAGE BID	AWARDED BID
===== 212-00032 Soil Conditioning Acre =====							
STA067A-038	SH 67 SEDALIA RESURFACING	SH 67 SEDALIA RESURFACING	01/31/19	0.10	2500.00	7772.93	10000.00
NHPP0821-107	SH 82 GLENWOOD SPRINGS TO CA	SH 82 GLENWOOD SPRINGS TO CA	02/07/19	0.40	3200.00	3407.50	6515.00
NH2871-035	US 287 PASSING LANES SOUTH OF	US 287 PASSING LANES SOUTH OF	02/07/19	10.00	3000.00	2814.44	2602.95
ITSSW01-638	ETHERNET PHASE III (PRIMARYLY	ETHERNET PHASE III (PRIMARYLY	02/07/19	1.21	2700.00	1025.00	250.00
NHPP145A-065	SH 145 PASSING LANES AT DEEP	SH 145 PASSING LANES AT DEEP	02/14/19	6.60	2000.00	3353.95	3200.00
NHPP0741-022	SH 74: I-70 TO CR 65 RESURFAC	SH 74: I-70 TO CR 65 RESURFAC	02/14/19	0.30	3000.00	4128.08	4125.00
NHPP070A-028	FALL RIVER ROAD BRIDGE	FALL RIVER ROAD BRIDGE	02/21/19	0.10	8333.00	9016.24	3111.60
SHER100-284	FY19 NORTH SIGNAL PKG	FY19 NORTH SIGNAL PKG	02/21/19	0.05	10000.00	16100.00	14400.00
NHPP1601-073	US 160 PASSING LANE NORTH OF	US 160 PASSING LANE NORTH OF	03/07/19	10.70	3500.00	6600.00	4200.00
FBR0253-247	I25 AT VINE DRIVE BRIDGE REPL	I25 AT VINE DRIVE BRIDGE REPL	03/07/19	5.20	1750.00	2380.99	3800.00
NHPP006A-058	US 6 LOVELAND PASS - I-70 (FY	US 6 LOVELAND PASS - I-70 (FY	03/07/19	0.20	5000.00	8223.01	7446.01
SHE2254-090	Colfax & I-225, Colfax & Cham	Colfax & I-225, Colfax & Cham	03/07/19	0.13	3500.00	6445.50	9000.00
NHPP050A-033	US50 West of Delta EB Lanes R	US50 West of Delta EB Lanes R	03/14/19	3.00	2500.00	3933.33	3600.00
NHPP0503-087	US 50 PASSING LANES EAST OF S	US 50 PASSING LANES EAST OF S	03/21/19	6.24	2500.00	3000.00	3000.00
SHE 0252-481	I-25 RAMP METER INSTALLATION	I-25 RAMP METER INSTALLATION	03/21/19	3.30	3000.00	4616.67	4350.00
SHER100-308	MIDPOINT - SIGNAL CONST PACKA	MIDPOINT - SIGNAL CONST PACKA	03/21/19	0.42	3300.00	3925.00	4100.00
STM0242-077	US24 - 8TH ST TO WEST OF MANI	US24 - 8TH ST TO WEST OF MANI	03/28/19	1.20	2946.67	3008.33	2325.00
STA0131-070 HMA ALT	SH 13 CR 5 NORTH AND SOUTH	SH 13 CR 5 NORTH AND SOUTH	03/28/19	128.00	3000.00	1443.22	1320.00
STA0131-070 PCCP ALT	SH 13 CR 5 NORTH AND SOUTH	SH 13 CR 5 NORTH AND SOUTH					
WEIGHTED AVERAGE FOR THE FIRST QUARTER				246.59	3217.85	1993.04	1917.53
=====							
NHPP030A-035	US 285/SH30	US 285/SH30	04/04/19	0.10	2000.00	2500.00	2500.00
IM0252-472	I-25 CABLE BARRIER PHASE III	I-25 CABLE BARRIER PHASE III	04/04/19	17.30	2000.00	2900.00	2800.00
BR071A-020	REPLACEMENT OF STRUCTURE L-22	REPLACEMENT OF STRUCTURE L-22	04/18/19	1.00	2700.00	4246.67	3490.00
FSA0252-468	I-25 AND PLUM CREEK IMPROVEME	I-25 AND PLUM CREEK IMPROVEME	04/18/19	0.03	2000.00	17532.75	38031.00
NHPP0703-445	I-70 WESTBOUND PEAK PERIOD SH	I-70 WESTBOUND PEAK PERIOD SH	04/25/19	23.00	3000.00	3258.36	3400.00
IM0252-456	I-25 COLORADO SPRINGS RAMP ME	I-25 COLORADO SPRINGS RAMP ME	05/16/19	0.90	3800.00	5134.67	3869.00
FSA0703-454	EB I-70 AUX LANE WARD TO KIPL	EB I-70 AUX LANE WARD TO KIPL	05/16/19	2.00	2500.00	3594.86	2800.00
FBR0063-057	US-6 F-09-K BRIDGE OVER CASTL	US-6 F-09-K BRIDGE OVER CASTL	05/30/19	1.40	2500.00	4382.50	5015.00
STRR200-257	ROAD CLOSURE GATES ON VARIOUS	ROAD CLOSURE GATES ON VARIOUS	05/30/19	0.60	10858.00	4884.17	3500.00
ER145A-081	SH 145 MP 21 EMERGENCY ROCKFA	SH 145 MP 21 EMERGENCY ROCKFA	06/07/19	1.00	3500.00	7040.37	8956.00
NHPP0703-442	I-70 SILVERPLUME SOUNDWALL AN	I-70 SILVERPLUME SOUNDWALL AN	06/13/19	0.70	2500.00	7004.74	5520.00
NHPP030A-036	SH 30 & TOWER RD IMPROVEMENTS	SH 30 & TOWER RD IMPROVEMENTS	06/13/19	0.10	2000.00	3000.00	3000.00
CR500-205	R5 GUARDRAIL END TREATMENT EA	R5 GUARDRAIL END TREATMENT EA	06/13/19	0.15	15000.00	6765.00	6765.00
STR 141A-040	R5 YEAR 4 BRDG PREV MAINT RAM	R5 YEAR 4 BRDG PREV MAINT RAM	06/20/19	0.30	6000.00	8150.00	9000.00
NHPP160A-030	US160 MM 43.2, 150.4, 156.3,	US160 MM 43.2, 150.4, 156.3,	06/20/19	1.70	4000.00	3691.67	4800.00
WEIGHTED AVERAGE FOR THE SECOND QUARTER				50.28	2810.16	3546.39	3474.92
WEIGHTED AVERAGE FOR THE YEAR				296.87	3148.80	2170.94	2253.79
=====							
===== 212-00040 Soil Preparation (Lawn) Acre =====							
NHPP030A-035	US 285/SH30	US 285/SH30	04/04/19	0.03	3000.00	1000.00	1000.00
WEIGHTED AVERAGE FOR THE SECOND QUARTER				0.03	3000.00	1000.00	1000.00
WEIGHTED AVERAGE FOR THE YEAR				0.03	3000.00	1000.00	1000.00

COLORADO DEPARTMENT OF TRANSPORTATION
 ITEM UNIT COSTS BY PROJECTS -- 2019 COST DATA

13:44 Wednesday, August 7, 2019 102

PROJECT NUMBER	ITEM NUMBER/ PROJECT LOCATION	ITEM DESCRIPTION/ PROJECT LOCATION	DATE LET	UNIT/ QUANTITY	ENGR. EST.	AVERAGE BID	AWARDED BID
===== 212-00050 Sod Sq Foot =====							
STR0241-062		US 24 143.4 - 148	01/24/19	610.00	5.00	3.08	2.00
		WEIGHTED AVERAGE FOR THE FIRST QUARTER		610.00	5.00	3.08	2.00
FSA2873-190 CR300-248		US 287 AND FOOTHILLS PARKWAY CRAIG RESIDENCY ADA RAMPS	05/02/19 05/16/19	436.00 310.00	2.00 3.00	12.50 12.33	14.00 5.00
		WEIGHTED AVERAGE FOR THE SECOND QUARTER		746.00	2.42	12.41	10.26
		WEIGHTED AVERAGE FOR THE YEAR		1,356.00	3.58	7.71	6.54
===== 212-00100 Tree Retention and Protection LUMP SUM =====							
STR0241-062		US 24 143.4 - 148	01/24/19	1.00	15000.00	3743.33	4000.00
		WEIGHTED AVERAGE FOR THE FIRST QUARTER		1.00	15000.00	3743.33	4000.00
		WEIGHTED AVERAGE FOR THE YEAR		1.00	15000.00	3743.33	4000.00
===== 212-00900 Compost Cubic Yard =====							
NHPP030A-036		SH 30 & TOWER RD IMPROVEMENTS	06/13/19	65.00	250.00	26.00	26.00
		WEIGHTED AVERAGE FOR THE SECOND QUARTER		65.00	250.00	26.00	26.00
		WEIGHTED AVERAGE FOR THE YEAR		65.00	250.00	26.00	26.00
===== 212-01200 Landscape Restoration LUMP SUM =====							
SHER100-284		FY19 NORTH SIGNAL PKG	02/21/19	1.00	2500.00	9200.00	4600.00
		WEIGHTED AVERAGE FOR THE FIRST QUARTER		1.00	2500.00	9200.00	4600.00
NHPP030A-035		US 285/SH30	04/04/19	1.00	10000.00	15000.00	15000.00
		WEIGHTED AVERAGE FOR THE SECOND QUARTER		1.00	10000.00	15000.00	15000.00
		WEIGHTED AVERAGE FOR THE YEAR		2.00	6250.00	10650.00	9800.00

COLORADO DEPARTMENT OF TRANSPORTATION
 ITEM UNIT COSTS BY PROJECTS -- 2019 COST DATA

13:44 Wednesday, August 7, 2019 103

PROJECT NUMBER	ITEM NUMBER/ PROJECT LOCATION	ITEM DESCRIPTION/ PROJECT LOCATION	DATE LET	UNIT/ QUANTITY	ENGR. EST.	AVERAGE BID	AWARDED BID
===== 213-00002		Mulching (Weed Free Hay)		Acre =====			
ER119A-065	PR SH 119A BOULDER CANYON	01/03/19	1.15	1250.00	1294.59	680.00	
STA119A-069	SH 119: NEDERLAND - EAST						
STA067A-038	SH 67 SEDALIA RESURFACING	01/31/19	0.10	2500.00	2288.87	3000.00	
NH2871-035	US 287 PASSING LANES SOUTH OF	02/07/19	10.00	1000.00	880.73	769.65	
NHPP0741-022	SH 74: I-70 TO CR 65 RESURFAC	02/14/19	0.30	2000.00	4689.43	5680.00	
NHPP006A-058	US 6 LOVELAND PASS - I-70 (FY	03/07/19	0.20	2000.00	5099.91	4199.81	
STM0242-077	US24 - 8TH ST TO WEST OF MANI	03/28/19	0.80	900.00	1950.00	3250.00	
	WEIGHTED AVERAGE FOR THE FIRST QUARTER		12.55	1068.33	1124.73	1109.36	
IM0252-472	I-25 CABLE BARRIER PHASE III	04/04/19	17.30	450.00	990.00	480.00	
STRR200-257	ROAD CLOSURE GATES ON VARIOUS	05/30/19	0.60	10858.00	1653.50	800.00	
NHPP030A-036	SH 30 & TOWER RD IMPROVEMENTS	06/13/19	0.10	2000.00	3500.00	3500.00	
	WEIGHTED AVERAGE FOR THE SECOND QUARTER		18.00	805.54	1019.17	507.44	
	WEIGHTED AVERAGE FOR THE YEAR		30.55	913.50	1082.34	754.71	
===== 213-00003		Mulching (Weed Free)		Acre =====			
STR0132-021	SH 13-MOFFAT COUNTY-CR 3 SOUT	01/10/19	45.00	800.00	658.40	525.00	
ITSSW01-638	ETHERNET PHASE III (PRIMARYLY	02/07/19	1.21	1000.00	725.00	250.00	
NHPP1601-076	US 160 MANCOS HILL (MP 40.000	02/21/19	0.10	3500.00	5206.67	5000.00	
FBR0253-247	I25 AT VINE DRIVE BRIDGE REPL	03/07/19	7.80	1000.00	753.57	650.00	
SHE 0252-481	I-25 RAMP METER INSTALLATION	03/21/19	3.30	1000.00	2066.67	1965.00	
SHER100-308	MIDPOINT - SIGNAL CONST PACKA	03/21/19	0.42	1100.00	4795.06	5065.12	
NHPP2254-089	I-225 RESURFACING FROM I-25 T	03/21/19	0.10	5000.00	4340.26	3500.00	
STA0131-070 HMA ALT	SH 13 CR 5 NORTH AND SOUTH	03/28/19	96.00	1000.00	894.16	746.00	
STA0131-070 PCCP ALT	SH 13 CR 5 NORTH AND SOUTH						
	WEIGHTED AVERAGE FOR THE FIRST QUARTER		153.93	946.03	815.30	701.10	
NHPP030A-035	US 285/SH30	04/04/19	0.10	1200.00	2000.00	2000.00	
NHPP0703-445	I-70 WESTBOUND PEAK PERIOD SH	04/25/19	23.00	1500.00	922.93	1000.00	
IM0252-456	I-25 COLORADO SPRINGS RAMP ME	05/16/19	0.90	1800.00	2185.33	2259.00	
FSA0703-454	EB I-70 AUX LANE WARD TO KIPL	05/16/19	2.00	1500.00	2231.35	820.00	
NHPP0703-442	I-70 SILVERPLUME SOUNDWALL AN	06/13/19	0.70	2500.00	5757.09	1400.00	
CR500-205	R5 GUARDRAIL END TREATMENT EA	06/13/19	0.15	15000.00	6030.00	6030.00	

COLORADO DEPARTMENT OF TRANSPORTATION
 ITEM UNIT COSTS BY PROJECTS -- 2019 COST DATA

13:44 Wednesday, August 7, 2019 104

PROJECT NUMBER	ITEM NUMBER/ PROJECT LOCATION	ITEM DESCRIPTION/ PROJECT LOCATION	DATE LET	UNIT/ QUANTITY	ENGR. EST.	AVERAGE BID	AWARDED BID
===== 213-00003		Mulching (Weed Free)		Acre =====			
STR 141A-040		R5 YEAR 4 BRDG PREV MAINT RAM	06/20/19	0.30	3000.00	5850.00	6000.00
	WEIGHTED AVERAGE FOR THE SECOND QUARTER			27.15	1625.78	1423.95	1125.51
	WEIGHTED AVERAGE FOR THE YEAR			181.08	1047.95	888.81	787.68
===== 213-00004		Mulching (Weed Free Straw)		Acre =====			
ER119A-065		PR SH 119A BOULDER CANYON	01/03/19	9.40	1250.00	1170.12	630.00
STAL19A-069		SH 119: NEDERLAND - EAST					
NHPP070A-028		FALL RIVER ROAD BRIDGE	02/21/19	0.10	8333.00	9540.31	3276.80
NHPP1601-073		US 160 PASSING LANE NORTH OF	03/07/19	10.70	1500.00	1100.00	1100.00
NHPP050A-033		US50 West of Delta EB Lanes R	03/14/19	3.00	1000.00	1320.00	1160.00
NHPP0503-087		US 50 PASSING LANES EAST OF S	03/21/19	6.24	700.00	650.00	600.00
STM0242-077		US24 - 8TH ST TO WEST OF MANI	03/28/19	0.40	1000.00	1566.67	2800.00
	WEIGHTED AVERAGE FOR THE FIRST QUARTER			29.84	1219.88	1153.58	883.50
NHPP160A-030		US160 MM 43.2, 150.4, 156.3,	06/20/19	1.70	1600.00	1857.36	3200.00
	WEIGHTED AVERAGE FOR THE SECOND QUARTER			1.70	1600.00	1857.36	3200.00
	WEIGHTED AVERAGE FOR THE YEAR			31.54	1240.37	1173.00	1008.36
===== 213-00007		Mulching (Wood Strand)		Acre =====			
C0502-085		US 50 MM 201.8 MONARCH AVALAN	06/27/19	0.20	15000.00	37389.00	15000.00
	WEIGHTED AVERAGE FOR THE SECOND QUARTER			0.20	15000.00	37389.00	15000.00
	WEIGHTED AVERAGE FOR THE YEAR			0.20	15000.00	37389.00	15000.00
===== 213-00008		Mulching (Wood Chip)		Cubic Foot =====			
ER072A-040		PR SH72A FLOOD PERMANENT REPA	01/31/19	9,800.00	3.00	2.19	0.35
NHPP072A-041		PR SH72A FLOOD PERMANENT REPA					
	WEIGHTED AVERAGE FOR THE FIRST QUARTER			9,800.00	3.00	2.19	0.35
	WEIGHTED AVERAGE FOR THE YEAR			9,800.00	3.00	2.19	0.35

PROJECT NUMBER	ITEM NUMBER/ PROJECT LOCATION	ITEM DESCRIPTION/ PROJECT LOCATION	DATE LET	UNIT/ QUANTITY	ENGR. EST.	AVERAGE BID	AWARDED BID
=====	213-00011	Mulching (Hydraulic)		Acre	=====	=====	=====
STR0132-021		SH 13-MOFFAT COUNTY-CR 3 SOUT	01/10/19	35.00	1500.00	1402.00	1150.00
		WEIGHTED AVERAGE FOR THE FIRST QUARTER		35.00	1500.00	1402.00	1150.00
		WEIGHTED AVERAGE FOR THE YEAR		35.00	1500.00	1402.00	1150.00
=====	213-00012	Spray-on Mulch Blanket		Acre	=====	=====	=====
ER119A-065		PR SH 119A BOULDER CANYON	01/03/19	1.50	2500.00	4563.87	3500.00
STA119A-069		SH 119: NEDERLAND - EAST					
FBR0341-087		US 34 OVER NORTH FORK CO RIVE	01/10/19	0.37	4500.00	4750.23	8306.14
STR141A-047		SH 141 MP 120-143 MESA COUNTY	01/17/19	3.00	4000.00	4525.73	4400.00
NHPP0701-241		I-70 TRUCK PARKING GARFIELD C	01/17/19	0.95	3200.00	5968.83	5500.00
STR0241-062		US 24 143.4 - 148	01/24/19	0.40	3500.00	7190.00	7600.00
ER072A-040		PR SH72A FLOOD PERMANENT REPA	01/31/19	9.00	3500.00	4275.01	3300.00
NHPP072A-041		PR SH72A FLOOD PERMANENT REPA					
NHPP0821-107		SH 82 GLENWOOD SPRINGS TO CA	02/07/19	0.37	3200.00	6525.00	5250.00
NHPP145A-065		SH 145 PASSING LANES AT DEEP	02/14/19	6.60	2500.00	4196.54	3600.00
STA0131-070 HMA ALT		SH 13 CR 5 NORTH AND SOUTH		6.00	4000.00	3156.67	
STA0131-070 PCCP ALT		SH 13 CR 5 NORTH AND SOUTH					
		WEIGHTED AVERAGE FOR THE FIRST QUARTER		28.19	3371.37	4264.69	3839.15
FBR0063-057		US-6 F-09-K BRIDGE OVER CASTL	05/30/19	1.20	6000.00	4005.00	4585.00
ER145A-081		SH 145 MP 21 EMERGENCY ROCKFA	06/07/19	1.00	1500.00	5994.97	6169.00
NHPP160A-030		US160 MM 43.2, 150.4, 156.3,	06/20/19	0.16	4000.00	2875.00	4500.00
		WEIGHTED AVERAGE FOR THE SECOND QUARTER		2.36	3957.63	4771.60	5250.42
		WEIGHTED AVERAGE FOR THE YEAR		30.55	3416.66	4276.85	3974.82
=====	213-00013	Spray-on Mulch Blanket		Pound	=====	=====	=====
STA0131-070 HMA ALT		SH 13 CR 5 NORTH AND SOUTH	03/28/19	6.00	4000.00	3139.13	3090.00
STA0131-070 PCCP ALT		SH 13 CR 5 NORTH AND SOUTH					
		WEIGHTED AVERAGE FOR THE FIRST QUARTER		6.00	4000.00	3139.13	3090.00
BR071A-020		REPLACEMENT OF STRUCTURE L-22	04/18/19	3,000.00	1.70	2.02	1.55
		WEIGHTED AVERAGE FOR THE SECOND QUARTER		3,000.00	1.70	2.02	1.55
		WEIGHTED AVERAGE FOR THE YEAR		3,006.00	9.68	8.28	7.71

PROJECT NUMBER	ITEM NUMBER/ PROJECT LOCATION	ITEM DESCRIPTION/ PROJECT LOCATION	DATE LET	UNIT/ QUANTITY	ENGR. EST.	AVERAGE BID	AWARDED BID
===== 213-00061		Mulch Tackifier		Pound	=====		
ER119A-065		PR SH 119A BOULDER CANYON	01/03/19	2,110.00	5.00	3.01	2.75
STA119A-069		SH 119: NEDERLAND - EAST					
STR0132-021		SH 13-MOFFAT COUNTY-CR 3 SOUT	01/10/19	9,000.00	4.00	2.12	1.85
ER072A-040		PR SH72A FLOOD PERMANENT REPA	01/31/19	1,800.00	3.00	2.43	2.50
NHPP072A-041		PR SH72A FLOOD PERMANENT REPA					
STA067A-038		SH 67 SEDALIA RESURFACING	01/31/19	20.00	3.00	23.40	40.00
NH2871-035		US 287 PASSING LANES SOUTH OF	02/07/19	1,880.00	5.00	2.66	2.36
NHPP0741-022		SH 74: I-70 TO CR 65 RESURFAC	02/14/19	60.00	5.00	5.12	5.00
NHPP1601-076		US 160 MANCOS HILL (MP 40.000	02/21/19	10.00	20.00	28.53	26.00
NHPP070A-028		FALL RIVER ROAD BRIDGE	02/21/19	8.00	3.00	33.14	34.00
NHPP1601-073		US 160 PASSING LANE NORTH OF	03/07/19	1,071.00	4.00	4.85	3.70
FBR0253-247		I25 AT VINE DRIVE BRIDGE REPL	03/07/19	780.00	4.00	2.90	3.00
NHPP006A-058		US 6 LOVELAND PASS - I-70 (FY	03/07/19	40.00	10.00	12.38	10.76
NHPP050A-033		US50 West of Delta EB Lanes R	03/14/19	600.00	3.00	2.97	2.80
NHPP0503-087		US 50 PASSING LANES EAST OF S	03/21/19	1,248.00	3.00	3.00	3.00
SHER100-308		MIDPOINT - SIGNAL CONST PACKA	03/21/19	59.00	2.60	5.25	3.25
NHPP2254-089		I-225 RESURFACING FROM I-25 T	03/21/19	200.00	6.00	3.89	3.35
STM0242-077		US24 - 8TH ST TO WEST OF MANI	03/28/19	240.00	2.67	2.58	2.75
STA0131-070 HMA ALT		SH 13 CR 5 NORTH AND SOUTH	03/28/19	19,256.00	4.00	2.35	2.60
STA0131-070 PCCP ALT		SH 13 CR 5 NORTH AND SOUTH					
		WEIGHTED AVERAGE FOR THE FIRST QUARTER		38,382.00	4.02	2.49	2.49
NHPP030A-035		US 285/SH30	04/04/19	20.00	25.00	2.59	2.59
IM0252-472		I-25 CABLE BARRIER PHASE III	04/04/19	1,730.00	2.00	2.00	1.00
NHPP0703-445		I-70 WESTBOUND PEAK PERIOD SH	04/25/19	4,600.00	3.00	2.69	3.00
IM0252-456		I-25 COLORADO SPRINGS RAMP ME	05/16/19	270.00	5.00	10.31	2.93
STRR200-257		ROAD CLOSURE GATES ON VARIOUS	05/30/19	150.00	13.25	4.15	2.00
NHPP0703-442		I-70 SILVERPLUME SOUNDWALL AN	06/13/19	210.00	5.00	11.31	5.50
NHPP030A-036		SH 30 & TOWER RD IMPROVEMENTS	06/13/19	100.00	3.00	5.00	5.00
CR500-205		R5 GUARDRAIL END TREATMENT EA	06/13/19	30.00	20.00	10.00	10.00
STR 141A-040		R5 YEAR 4 BRDG PREV MAINT RAM	06/20/19	60.00	4.00	8.50	10.00
NHPP160A-030		US160 MM 43.2, 150.4, 156.3,	06/20/19	340.00	5.00	3.25	4.00
		WEIGHTED AVERAGE FOR THE SECOND QUARTER		7,510.00	3.33	3.65	2.74
		WEIGHTED AVERAGE FOR THE YEAR		45,892.00	3.91	2.62	2.55
===== 213-00067		Rock Mulch (Weed Free)		Sq Foot	=====		
C R100-315		R1 ADA CURB RAMPS - PH 5	03/07/19	100.00	30.00	20.00	12.00
		WEIGHTED AVERAGE FOR THE FIRST QUARTER		100.00	30.00	20.00	12.00

PROJECT NUMBER	ITEM NUMBER/ PROJECT LOCATION	ITEM DESCRIPTION/ PROJECT LOCATION	DATE LET	UNIT/ QUANTITY	ENGR. EST.	AVERAGE BID	AWARDED BID
=====	213-00067	Rock Mulch (Weed Free)		Sq Foot	=====		
CR300-248		CRAIG RESIDENCY ADA RAMPS	05/16/19	30.00	15.00	24.67	5.00
		WEIGHTED AVERAGE FOR THE SECOND QUARTER		30.00	15.00	24.67	5.00
		WEIGHTED AVERAGE FOR THE YEAR		130.00	26.54	21.45	10.38
=====	213-00150	Bonded Fiber Matrix		Acre	=====		
STR0132-021		SH 13-MOFFAT COUNTY-CR 3 SOUT	01/10/19	10.00	3000.00	3173.00	2930.00
FBR0341-087		US 34 OVER NORTH FORK CO RIVE	01/10/19	0.11	5000.00	7658.24	8724.23
STA0131-070 HMA ALT		SH 13 CR 5 NORTH AND SOUTH	03/28/19	128.00	3000.00	2907.19	2910.00
STA0131-070 PCCP ALT		SH 13 CR 5 NORTH AND SOUTH					
		WEIGHTED AVERAGE FOR THE FIRST QUARTER		138.11	3001.59	2944.98	2921.33
NHPP0703-445		I-70 WESTBOUND PEAK PERIOD SH	04/25/19	20.00	3500.00	3469.62	3800.00
		WEIGHTED AVERAGE FOR THE SECOND QUARTER		20.00	3500.00	3469.62	3800.00
		WEIGHTED AVERAGE FOR THE YEAR		158.11	3064.64	3008.62	3108.06
=====	213-00700	Landscape Boulder		Each	=====		
ER072A-040		PR SH72A FLOOD PERMANENT REPA	01/31/19	529.00	250.00	533.31	285.00
NHPP072A-041		PR SH72A FLOOD PERMANENT REPA					
		WEIGHTED AVERAGE FOR THE FIRST QUARTER		529.00	250.00	533.31	285.00
NHPP0703-445		I-70 WESTBOUND PEAK PERIOD SH	04/25/19	107.00	300.00	491.35	356.00
		WEIGHTED AVERAGE FOR THE SECOND QUARTER		107.00	300.00	491.35	356.00
		WEIGHTED AVERAGE FOR THE YEAR		636.00	258.41	531.29	296.94
=====	214-00000	Landscape Maintenance		LUMP SUM	=====		
ER119A-065		PR SH 119A BOULDER CANYON	01/03/19	1.00	7500.00	24160.50	11000.00

COLORADO DEPARTMENT OF TRANSPORTATION
 ITEM UNIT COSTS BY PROJECTS -- 2019 COST DATA

13:44 Wednesday, August 7, 2019 108

PROJECT NUMBER	ITEM NUMBER/ PROJECT LOCATION	ITEM DESCRIPTION/ PROJECT LOCATION	DATE LET	UNIT/ QUANTITY	ENGR. EST.	AVERAGE BID	AWARDED BID
=====	214-00000	Landscape Maintenance		LUMP SUM	=====	=====	=====
STA119A-069		SH 119: NEDERLAND - EAST					
ER072A-040		PR SH72A FLOOD PERMANENT REPA	01/31/19	1.00	75000.00	51469.28	80000.00
NHPP072A-041		PR SH72A FLOOD PERMANENT REPA					
		WEIGHTED AVERAGE FOR THE FIRST QUARTER		2.00	41250.00	40545.77	45500.00
NHPP030A-035		US 285/SH30	04/04/19	1.00	10000.00	32528.00	32528.00
NHPP0703-445		I-70 WESTBOUND PEAK PERIOD SH	04/25/19	1.00	100000.00	40399.66	18986.00
		WEIGHTED AVERAGE FOR THE SECOND QUARTER		2.00	55000.00	38431.75	25757.00
		WEIGHTED AVERAGE FOR THE YEAR		4.00	48125.00	40193.43	35628.50
=====	214-00145	Plant Protect Fence		Lin Foot	=====	=====	=====
ER119A-065		PR SH 119A BOULDER CANYON	01/03/19	1,730.00	3.00	4.94	6.00
STA119A-069		SH 119: NEDERLAND - EAST					
		WEIGHTED AVERAGE FOR THE FIRST QUARTER		1,730.00	3.00	4.94	6.00
NHPP030A-035		US 285/SH30	04/04/19	125.00	4.00	3.80	3.80
		WEIGHTED AVERAGE FOR THE SECOND QUARTER		125.00	4.00	3.80	3.80
		WEIGHTED AVERAGE FOR THE YEAR		1,855.00	3.07	4.93	5.85
=====	214-00205	Deciduous Tree (5 Gal)		Each	=====	=====	=====
FBR0341-087		US 34 OVER NORTH FORK CO RIVE	01/10/19	5.00	350.00	240.65	162.94
ER072A-040		PR SH72A FLOOD PERMANENT REPA	01/31/19	140.00	85.00	89.35	59.00
NHPP072A-041		PR SH72A FLOOD PERMANENT REPA					
STM0242-077		US24 - 8TH ST TO WEST OF MANI	03/28/19	29.00	500.00	88.33	110.00
		WEIGHTED AVERAGE FOR THE FIRST QUARTER		174.00	161.78	91.82	70.49
		WEIGHTED AVERAGE FOR THE YEAR		174.00	161.78	91.82	70.49
=====	214-00220	Deciduous Tree (2 In C)		Each	=====	=====	=====
ER119A-065		PR SH 119A BOULDER CANYON	01/03/19	24.00	600.00	674.32	650.00

COLORADO DEPARTMENT OF TRANSPORTATION
 ITEM UNIT COSTS BY PROJECTS -- 2019 COST DATA

13:44 Wednesday, August 7, 2019 109

PROJECT NUMBER	ITEM NUMBER/ PROJECT LOCATION	ITEM DESCRIPTION/ PROJECT LOCATION	DATE LET	UNIT/ QUANTITY	ENGR. EST.	AVERAGE BID	AWARDED BID
===== 214-00220	214-00220	Deciduous Tree (2 In C)		Each			
STA119A-069		SH 119: NEDERLAND - EAST					
	WEIGHTED AVERAGE FOR THE FIRST QUARTER			24.00	600.00	674.32	650.00
	WEIGHTED AVERAGE FOR THE YEAR			24.00	600.00	674.32	650.00
===== 214-00222	214-00222	Decid Tree (2 In Cal) (Furnish)		Each			
NHPP070A-028		FALL RIVER ROAD BRIDGE	02/21/19	3.00	350.00	505.39	420.00
	WEIGHTED AVERAGE FOR THE FIRST QUARTER			3.00	350.00	505.39	420.00
NHPP0703-445		I-70 WESTBOUND PEAK PERIOD SH	04/25/19	22.00	450.00	505.76	480.00
	WEIGHTED AVERAGE FOR THE SECOND QUARTER			22.00	450.00	505.76	480.00
	WEIGHTED AVERAGE FOR THE YEAR			25.00	438.00	505.69	472.80
===== 214-00330	214-00330	Deciduous Shrub (3 Gal)		Each			
ER119A-065		PR SH 119A BOULDER CANYON	01/03/19	95.00	30.00	70.70	60.00
STA119A-069		SH 119: NEDERLAND - EAST					
	WEIGHTED AVERAGE FOR THE FIRST QUARTER			95.00	30.00	70.70	60.00
	WEIGHTED AVERAGE FOR THE YEAR			95.00	30.00	70.70	60.00
===== 214-00350	214-00350	Deciduous Shrub (5 Gal)		Each			
STR0241-062		US 24 143.4 - 148	01/24/19	5.00	350.00	103.00	55.00
ER072A-040		PR SH72A FLOOD PERMANENT REPA	01/31/19	419.00	86.00	43.11	35.00
NHPP072A-041		PR SH72A FLOOD PERMANENT REPA					
STM0242-077		US24 - 8TH ST TO WEST OF MANI	03/28/19	34.00	65.00	51.00	55.00
	WEIGHTED AVERAGE FOR THE FIRST QUARTER			458.00	87.32	43.45	36.70
	WEIGHTED AVERAGE FOR THE YEAR			458.00	87.32	43.45	36.70
===== 214-00450	214-00450	Evergreen Tree (5 Gal)		Each			
ER072A-040		PR SH72A FLOOD PERMANENT REPA	01/31/19	23.00	200.00	160.55	81.00

COLORADO DEPARTMENT OF TRANSPORTATION
 ITEM UNIT COSTS BY PROJECTS -- 2019 COST DATA

13:44 Wednesday, August 7, 2019 110

PROJECT NUMBER	ITEM NUMBER/ PROJECT LOCATION	ITEM DESCRIPTION/ PROJECT LOCATION	DATE LET	UNIT/ QUANTITY	ENGR. EST.	AVERAGE BID	AWARDED BID
===== 214-00450 NHPP072A-041		Evergreen Tree (5 Gal) PR SH72A FLOOD PERMANENT REPA		Each =====			
	WEIGHTED AVERAGE FOR THE FIRST QUARTER			23.00	200.00	160.55	81.00
	WEIGHTED AVERAGE FOR THE YEAR			23.00	200.00	160.55	81.00
===== 214-00507		Furn Evergreen Tree (6 Ft) (B-B)		Each =====			
NHPP070A-028		FALL RIVER ROAD BRIDGE	02/21/19	8.00	500.00	386.05	350.00
	WEIGHTED AVERAGE FOR THE FIRST QUARTER			8.00	500.00	386.05	350.00
NHPP0703-445		I-70 WESTBOUND PEAK PERIOD SH	04/25/19	10.00	400.00	591.72	575.00
	WEIGHTED AVERAGE FOR THE SECOND QUARTER			10.00	400.00	591.72	575.00
	WEIGHTED AVERAGE FOR THE YEAR			18.00	444.44	474.19	475.00
===== 214-00510		Evergreen Tree (10 Ft) (B-B)		Each =====			
NHPP160A-030		US160 MM 43.2, 150.4, 156.3,	06/20/19	4.00	1000.00	1600.00	1700.00
	WEIGHTED AVERAGE FOR THE SECOND QUARTER			4.00	1000.00	1600.00	1700.00
	WEIGHTED AVERAGE FOR THE YEAR			4.00	1000.00	1600.00	1700.00
===== 214-01010		Brush Layer Cutting		Each =====			
NHPP145A-065 NHPP1601-073		SH 145 PASSING LANES AT DEEP	02/14/19	600.00	8.00	8.36	8.00
		US 160 PASSING LANE NORTH OF	03/07/19	15.00	15.00	14.50	19.00
	WEIGHTED AVERAGE FOR THE FIRST QUARTER			615.00	8.17	8.42	8.27
NHPP160A-030		US160 MM 43.2, 150.4, 156.3,	06/20/19	100.00	6.00	11.03	16.50
	WEIGHTED AVERAGE FOR THE SECOND QUARTER			100.00	6.00	11.03	16.50
	WEIGHTED AVERAGE FOR THE YEAR			715.00	7.87	8.58	9.42

COLORADO DEPARTMENT OF TRANSPORTATION
 ITEM UNIT COSTS BY PROJECTS -- 2019 COST DATA

13:44 Wednesday, August 7, 2019 111

PROJECT NUMBER	ITEM NUMBER/ PROJECT LOCATION	ITEM DESCRIPTION/ PROJECT LOCATION	DATE LET	UNIT/ QUANTITY	ENGR. EST.	AVERAGE BID	AWARDED BID
=====	214-01013	Live Willow Stakes		Each	=====	=====	=====
ER119A-065 STA119A-069		PR SH 119A BOULDER CANYON SH 119: NEDERLAND - EAST	01/03/19	100.00	25.00	6.02	3.25
	WEIGHTED	AVERAGE FOR THE FIRST QUARTER		100.00	25.00	6.02	3.25
		WEIGHTED AVERAGE FOR THE YEAR		100.00	25.00	6.02	3.25
=====	214-01015	Willow Cuttings		Each	=====	=====	=====
FBR0341-087 ER072A-040 NHPP072A-041		US 34 OVER NORTH FORK CO RIVE PR SH72A FLOOD PERMANENT REPA PR SH72A FLOOD PERMANENT REPA	01/10/19 01/31/19	205.00 2,904.00	7.40 6.00	11.03 5.62	5.87 4.00
	WEIGHTED	AVERAGE FOR THE FIRST QUARTER		3,109.00	6.09	5.80	4.12
STR 141A-040		R5 YEAR 4 BRDG PREV MAINT RAM	06/20/19	15.00	4.00	22.00	30.00
	WEIGHTED	AVERAGE FOR THE SECOND QUARTER		15.00	4.00	22.00	30.00
		WEIGHTED AVERAGE FOR THE YEAR		3,124.00	6.08	5.81	4.25
=====	214-01025	Dormant Log Cutting		Each	=====	=====	=====
NHPP145A-065		SH 145 PASSING LANES AT DEEP	02/14/19	15.00	50.00	132.86	100.00
	WEIGHTED	AVERAGE FOR THE FIRST QUARTER		15.00	50.00	132.86	100.00
		WEIGHTED AVERAGE FOR THE YEAR		15.00	50.00	132.86	100.00
=====	214-01228	Riprap Planting Pocket		Each	=====	=====	=====
ER072A-040 NHPP072A-041		PR SH72A FLOOD PERMANENT REPA PR SH72A FLOOD PERMANENT REPA	01/31/19	183.00	400.00	160.56	140.00
	WEIGHTED	AVERAGE FOR THE FIRST QUARTER		183.00	400.00	160.56	140.00
		WEIGHTED AVERAGE FOR THE YEAR		183.00	400.00	160.56	140.00

COLORADO DEPARTMENT OF TRANSPORTATION
 ITEM UNIT COSTS BY PROJECTS -- 2019 COST DATA

13:44 Wednesday, August 7, 2019 112

PROJECT NUMBER	ITEM NUMBER/ PROJECT LOCATION	ITEM DESCRIPTION/ PROJECT LOCATION	DATE LET	UNIT/ QUANTITY	ENGR. EST.	AVERAGE BID	AWARDED BID
===== 215-00000		Transplant Shrub		Each			
NHPP145A-065		SH 145 PASSING LANES AT DEEP	02/14/19	30.00	80.00	64.27	45.00
	WEIGHTED AVERAGE FOR THE FIRST QUARTER			30.00	80.00	64.27	45.00
	WEIGHTED AVERAGE FOR THE YEAR			30.00	80.00	64.27	45.00
===== 216-00041		Soil Reten Blanket (S/C)		Sq Yard			
NHPP1601-073		US 160 PASSING LANE NORTH OF	03/07/19	1,136.00	5.00	3.75	3.50
	WEIGHTED AVERAGE FOR THE FIRST QUARTER			1,136.00	5.00	3.75	3.50
STRR200-257		ROAD CLOSURE GATES ON VARIOUS	05/30/19	2,420.00	6.63	3.29	2.50
	WEIGHTED AVERAGE FOR THE SECOND QUARTER			2,420.00	6.63	3.29	2.50
	WEIGHTED AVERAGE FOR THE YEAR			3,556.00	6.11	3.44	2.82
===== 216-00042		Soil Retent Blanket (BioD S/C)		Sq Yard			
ER119A-065		PR SH 119A BOULDER CANYON	01/03/19	4,000.00	2.50	3.77	2.30
STAl19A-069		SH 119: NEDERLAND - EAST					
NH2871-035		US 287 PASSING LANES SOUTH OF	02/07/19	50.00	10.00	5.60	5.25
	WEIGHTED AVERAGE FOR THE FIRST QUARTER			4,050.00	2.59	3.78	2.34
NHPP160A-030		US160 MM 43.2, 150.4, 156.3,	06/20/19	1,415.00	7.00	4.50	4.00
	WEIGHTED AVERAGE FOR THE SECOND QUARTER			1,415.00	7.00	4.50	4.00
	WEIGHTED AVERAGE FOR THE YEAR			5,465.00	3.73	3.83	2.77
===== 216-00101		Soil Reten Blanket (S-C) (PhotoD Cl 1)		Sq Yard			
SHER100-284		FY19 NORTH SIGNAL PKG	02/21/19	60.00	10.00	11.57	7.70

COLORADO DEPARTMENT OF TRANSPORTATION
 ITEM UNIT COSTS BY PROJECTS -- 2019 COST DATA

13:44 Wednesday, August 7, 2019 113

PROJECT NUMBER	ITEM NUMBER/ PROJECT LOCATION	ITEM DESCRIPTION/ PROJECT LOCATION	DATE LET	UNIT/ QUANTITY	ENGR. EST.	AVERAGE BID	AWARDED BID
===== 216-00101		Soil Reten Blanket (S-C) (PhotoD Cl 1)		Sq Yard	=====	=====	=====
SHE2254-090		Colfax & I-225, Colfax & Cham	03/07/19	594.00	10.00	3.47	3.00
	WEIGHTED AVERAGE FOR THE FIRST QUARTER			654.00	10.00	4.54	3.43
STR 141A-040		R5 YEAR 4 BRDG PREV MAINT RAM	06/20/19	100.00	25.00	7.00	10.00
	WEIGHTED AVERAGE FOR THE SECOND QUARTER			100.00	25.00	7.00	10.00
	WEIGHTED AVERAGE FOR THE YEAR			754.00	11.99	4.85	4.30
===== 216-00201		Soil Reten Blanket (S-C) (BioD Cl 1)		Sq Yard	=====	=====	=====
IM0251-351		I-25 South of Pueblo MP 79.6	01/03/19	900.00	4.00	4.22	3.87
FSA0142-068		SH 14 & WCR 33 INTERSECTION I	01/03/19	600.00	4.50	3.93	2.35
ER119A-065		PR SH 119A BOULDER CANYON	01/03/19	300.00	3.00	3.22	2.30
STA119A-069		SH 119: NEDERLAND - EAST					
STR0132-021		SH 13-MOFFAT COUNTY-CR 3 SOUT	01/10/19	28,000.00	2.00	2.42	2.15
FBR0341-087		US 34 OVER NORTH FORK CO RIVE	01/10/19	500.00	3.50	3.91	4.38
STR0241-062		US 24 143.4 - 148	01/24/19	300.00	8.00	4.50	4.00
ER072A-040		PR SH72A FLOOD PERMANENT REPA	01/31/19	17,000.00	3.00	2.86	3.00
NHPP072A-041		PR SH72A FLOOD PERMANENT REPA					
NHPP0821-107		SH 82 GLENWOOD SPRINGS TO CA	02/07/19	145.00	3.00	6.38	8.50
NHPP145A-065		SH 145 PASSING LANES AT DEEP	02/14/19	9,546.00	3.00	3.17	3.50
FBR0253-247		I25 AT VINE DRIVE BRIDGE REPL	03/07/19	13,375.00	3.00	2.48	2.30
NHPP0503-087		US 50 PASSING LANES EAST OF S	03/21/19	1,000.00	2.20	3.50	4.00
STM0242-077		US24 - 8TH ST TO WEST OF MANI	03/28/19	100.00	2.50	2.42	2.75
STA0131-070 HMA ALT		SH 13 CR 5 NORTH AND SOUTH	03/28/19	160,272.00	2.00	2.70	2.70
STA0131-070 PCCP ALT		SH 13 CR 5 NORTH AND SOUTH					
	WEIGHTED AVERAGE FOR THE FIRST QUARTER			232,038.00	2.20	2.70	2.67
NHPP0703-445		I-70 WESTBOUND PEAK PERIOD SH	04/25/19	63,001.00	3.00	2.94	3.80
FSA0703-454		EB I-70 AUX LANE WARD TO KIPL	05/16/19	5,324.00	3.50	5.06	2.50
FBR0063-057		US-6 F-09-K BRIDGE OVER CASTL	05/30/19	4,000.00	3.50	2.65	3.25
	WEIGHTED AVERAGE FOR THE SECOND QUARTER			72,325.00	3.06	3.09	3.67
	WEIGHTED AVERAGE FOR THE YEAR			304,363.00	2.41	2.77	3.00
===== 216-00221		Soil Reten Blanket (C) (BioD Cl 1)		Sq Yard	=====	=====	=====
ER119A-065		PR SH 119A BOULDER CANYON	01/03/19	2,570.00	5.50	3.77	3.00

PROJECT NUMBER	ITEM NUMBER/ PROJECT LOCATION	ITEM DESCRIPTION/ PROJECT LOCATION	DATE LET	UNIT/ QUANTITY	ENGR. EST.	AVERAGE BID	AWARDED BID
=====	216-00221	Soil Reten Blanket (C) (BioD Cl 1)		Sq Yard	=====		
STA119A-069		SH 119: NEDERLAND - EAST					
	WEIGHTED AVERAGE FOR THE FIRST QUARTER			2,570.00	5.50	3.77	3.00
	WEIGHTED AVERAGE FOR THE YEAR			2,570.00	5.50	3.77	3.00
=====	216-00301	Turf Reinf Mat (Cl 1)		Sq Yard	=====		
ER119A-065		PR SH 119A BOULDER CANYON	01/03/19	1,700.00	5.00	6.32	5.00
STA119A-069		SH 119: NEDERLAND - EAST					
STM0242-077		US24 - 8TH ST TO WEST OF MANI	03/28/19	10.00	6.00	7.83	13.00
	WEIGHTED AVERAGE FOR THE FIRST QUARTER			1,710.00	5.01	6.32	5.05
	WEIGHTED AVERAGE FOR THE YEAR			1,710.00	5.01	6.32	5.05
=====	216-00302	Turf Reinf Mat (Cl 2)		Sq Yard	=====		
FBR0253-247		I25 AT VINE DRIVE BRIDGE REPL	03/07/19	1,373.00	6.00	6.59	5.40
STA0131-070 HMA ALT		SH 13 CR 5 NORTH AND SOUTH	03/28/19	11,590.00	6.00	5.45	5.60
STA0131-070 PCCP ALT		SH 13 CR 5 NORTH AND SOUTH					
	WEIGHTED AVERAGE FOR THE FIRST QUARTER			12,963.00	6.00	5.80	5.56
NHPP0703-445		I-70 WESTBOUND PEAK PERIOD SH	04/25/19	24,415.00	5.00	6.35	7.00
	WEIGHTED AVERAGE FOR THE SECOND QUARTER			24,415.00	5.00	6.35	7.00
	WEIGHTED AVERAGE FOR THE YEAR			37,378.00	5.35	6.12	6.67
=====	217-00000	Herbicide Treatment		Sq Yard	=====		
IM0252-472		I-25 CABLE BARRIER PHASE III	04/04/19	3,500.00	0.30	0.65	0.30
	WEIGHTED AVERAGE FOR THE SECOND QUARTER			3,500.00	0.30	0.65	0.30
	WEIGHTED AVERAGE FOR THE YEAR			3,500.00	0.30	0.65	0.30
=====	217-00015	Noxious Weed Management		Sq Yard	=====		
ER119A-065		PR SH 119A BOULDER CANYON	01/03/19	900.00	5.00	3.92	5.00

PROJECT NUMBER	ITEM NUMBER/ PROJECT LOCATION	ITEM DESCRIPTION/ PROJECT LOCATION	DATE LET	UNIT/ QUANTITY	ENGR. EST.	AVERAGE BID	AWARDED BID
===== 217-00015		Noxious Weed Management		Sq Yard			
STA119A-069		SH 119: NEDERLAND - EAST					
	WEIGHTED AVERAGE FOR THE FIRST QUARTER			900.00	5.00	3.92	5.00
	WEIGHTED AVERAGE FOR THE YEAR			900.00	5.00	3.92	5.00
===== 217-00020		Herbicide Treatment		Hour			
FBR0341-087		US 34 OVER NORTH FORK CO RIVE	01/10/19	10.00	175.00	186.45	76.65
ER072A-040		PR SH72A FLOOD PERMANENT REPA	01/31/19	48.00	120.00	186.43	170.00
NHPP072A-041		PR SH72A FLOOD PERMANENT REPA					
NHPP0821-107		SH 82 GLENWOOD SPRINGS TO CA	02/07/19	10.00	130.00	151.00	122.00
NHPP070A-028		FALL RIVER ROAD BRIDGE	02/21/19	20.00	200.00	187.82	230.00
FBR0253-247		I25 AT VINE DRIVE BRIDGE REPL	03/07/19	40.00	130.00	133.54	95.00
SHE 0252-481		I-25 RAMP METER INSTALLATION	03/21/19	10.00	150.00	104.50	110.00
	WEIGHTED AVERAGE FOR THE FIRST QUARTER			138.00	141.38	164.98	142.37
NHPP0703-445		I-70 WESTBOUND PEAK PERIOD SH	04/25/19	160.00	150.00	93.52	118.00
	WEIGHTED AVERAGE FOR THE SECOND QUARTER			160.00	150.00	93.52	118.00
	WEIGHTED AVERAGE FOR THE YEAR			298.00	146.01	144.87	129.28
===== 240-00000		Wildlife Biologist		Hour			
ER119A-065		PR SH 119A BOULDER CANYON	01/03/19	16.00	150.00	94.51	125.00
STA119A-069		SH 119: NEDERLAND - EAST					
STR0132-021		SH 13-MOFFAT COUNTY-CR 3 SOUT	01/10/19	24.00	120.00	147.60	115.00
FBR0341-087		US 34 OVER NORTH FORK CO RIVE	01/10/19	40.00	135.00	124.75	117.44
STR141A-047		SH 141 MP 120-143 MESA COUNTY	01/17/19	80.00	125.00	159.13	80.00
NHPP0701-241		I-70 TRUCK PARKING GARFIELD C	01/17/19	10.00	115.00	199.23	135.00
STR0241-062		US 24 143.4 - 148	01/24/19	40.00	125.00	155.33	120.00
NHPPR100-250		PACKAGE A (I-25 / I-70 / I-76	01/24/19	150.00	125.00	83.36	40.00
ER072A-040		PR SH72A FLOOD PERMANENT REPA	01/31/19	92.00	125.00	115.59	135.00
NHPP072A-041		PR SH72A FLOOD PERMANENT REPA					
STA067A-038		SH 67 SEDALIA RESURFACING	01/31/19	40.00	125.00	113.13	110.00
NHPP0821-107		SH 82 GLENWOOD SPRINGS TO CA	02/07/19	8.00	150.00	102.00	114.00
ITSSW01-638		ETHERNET PHASE III (PRIMARYLY	02/07/19	30.00	120.00	80.00	10.00
NHPP145A-065		SH 145 PASSING LANES AT DEEP	02/14/19	60.00	100.00	139.37	135.00
NHPP0741-022		SH 74: I-70 TO CR 65 RESURFAC	02/14/19	40.00	120.00	64.46	48.85

PROJECT NUMBER	ITEM NUMBER/ PROJECT LOCATION	ITEM DESCRIPTION/ PROJECT LOCATION	DATE LET	UNIT/ QUANTITY	ENGR. EST.	AVERAGE BID	AWARDED BID
===== 240-00000 Wildlife Biologist Hour =====							
NHPP070A-028		FALL RIVER ROAD BRIDGE	02/21/19	10.00	200.00	121.74	100.00
NHPP1601-073		US 160 PASSING LANE NORTH OF	03/07/19	20.00	140.00	178.50	107.00
SHE2254-090		Colfax & I-225, Colfax & Cham	03/07/19	20.00	120.00	100.50	106.00
NHPP0702-378		I-70 OFFICERS GULCH TO FRISCO	03/14/19	40.00	130.00	161.68	125.05
NHPP0503-087		US 50 PASSING LANES EAST OF S	03/21/19	30.00	100.00	140.00	130.00
NHPP2254-089		I-225 RESURFACING FROM I-25 T	03/21/19	40.00	120.00	104.53	95.00
WEIGHTED AVERAGE FOR THE FIRST QUARTER				790.00	123.90	117.18	93.74
=====							
NHPP030A-035		US 285/SH30	04/04/19	80.00	125.00	75.00	75.00
NHPP0703-445		I-70 WESTBOUND PEAK PERIOD SH	04/25/19	120.00	125.00	118.38	118.00
FSA0703-454		EB I-70 AUX LANE WARD TO KIPL	05/16/19	8.00	100.00	222.20	110.00
FBR0063-057		US-6 F-09-K BRIDGE OVER CASTL	05/30/19	40.00	100.00	129.25	126.50
NHPP0703-442		I-70 SILVERPLUME SOUNDWALL AN	06/13/19	10.00	105.00	113.31	109.00
CR500-205		R5 GUARDRAIL END TREATMENT EA	06/13/19	30.00	120.00	145.00	145.00
STR 141A-040		R5 YEAR 4 BRDG PREV MAINT RAM	06/20/19	45.00	120.00	140.00	135.00
NHPP160A-030		US160 MM 43.2, 150.4, 156.3,	06/20/19	100.00	120.00	75.00	100.00
C0502-085		US 50 MM 201.8 MONARCH AVALAN	06/27/19	40.00	150.00	129.00	135.00
WEIGHTED AVERAGE FOR THE SECOND QUARTER				473.00	122.30	112.91	112.08
=====							
WEIGHTED AVERAGE FOR THE YEAR				1,263.00	123.30	116.30	100.61
=====							
===== 240-00001 Wildlife Biologist Day =====							
STA0131-070 HMA ALT		SH 13 CR 5 NORTH AND SOUTH	03/28/19	90.00	800.00	935.09	1520.00
STA0131-070 PCCP ALT		SH 13 CR 5 NORTH AND SOUTH					
WEIGHTED AVERAGE FOR THE FIRST QUARTER				90.00	800.00	935.09	1520.00
=====							
WEIGHTED AVERAGE FOR THE YEAR				90.00	800.00	935.09	1520.00
=====							
===== 240-00010 Rem of Nests Hour =====							
STAR200-242		R2 NORTH PROGRAM WALL REPAIRS	01/03/19	10.00	130.00	83.59	55.00
IM0251-351		I-25 South of Pueblo MP 79.6	01/03/19	60.00	106.00	78.81	134.03
ER119A-065		PR SH 119A BOULDER CANYON	01/03/19	80.00	120.00	108.67	90.00
STA119A-069		SH 119: NEDERLAND - EAST					
STR0132-021		SH 13-MOFFAT COUNTY-CR 3 SOUT	01/10/19	40.00	100.00	92.00	90.00
FBR0341-087		US 34 OVER NORTH FORK CO RIVE	01/10/19	10.00	130.00	98.51	149.92
STR141A-047		SH 141 MP 120-143 MESA COUNTY	01/17/19	5.00	115.00	126.41	160.00

PROJECT NUMBER	ITEM NUMBER/ PROJECT LOCATION	ITEM DESCRIPTION/ PROJECT LOCATION	DATE LET	UNIT/ QUANTITY	ENGR. EST.	AVERAGE BID	AWARDED BID
===== 240-00010							
		Rem of Nests		Hour			
STR0241-062		US 24 143.4 - 148	01/24/19	40.00	115.00	102.00	120.00
NHPPR100-250		PACKAGE A (I-25 / I-70 / I-76	01/24/19	150.00	125.00	108.19	72.00
ER072A-040		PR SH72A FLOOD PERMANENT REPA	01/31/19	80.00	165.00	110.84	135.00
NHPP072A-041		PR SH72A FLOOD PERMANENT REPA					
STA067A-038		SH 67 SEDALIA RESURFACING	01/31/19	40.00	145.00	102.85	100.00
NHPP0821-107		SH 82 GLENWOOD SPRINGS TO CA	02/07/19	8.00	150.00	102.00	114.00
ITSSW01-638		ETHERNET PHASE III (PRIMARILY	02/07/19	10.00	105.00	105.00	10.00
NHPP145A-065		SH 145 PASSING LANES AT DEEP	02/14/19	10.00	120.00	114.22	135.00
NHPP0741-022		SH 74: I-70 TO CR 65 RESURFAC	02/14/19	40.00	150.00	66.27	54.30
NHPP070A-028		FALL RIVER ROAD BRIDGE	02/21/19	10.00	200.00	80.04	79.00
NHPP1601-073		US 160 PASSING LANE NORTH OF	03/07/19	10.00	150.00	76.00	62.00
SHE2254-090		Colfax & I-225, Colfax & Cham	03/07/19	20.00	150.00	85.00	80.00
NHPP0702-378		I-70 OFFICERS GULCH TO FRISCO	03/14/19	40.00	130.00	115.02	125.05
NHPP0503-087		US 50 PASSING LANES EAST OF S	03/21/19	10.00	80.00	85.00	70.00
NHPP2254-089		I-225 RESURFACING FROM I-25 T	03/21/19	40.00	95.00	100.67	90.00
STM0242-077		US24 - 8TH ST TO WEST OF MANI	03/28/19	45.00	102.33	151.50	104.50
STA0131-070 HMA ALT		SH 13 CR 5 NORTH AND SOUTH	03/28/19	60.00	150.00	100.99	170.00
STA0131-070 PCCP ALT		SH 13 CR 5 NORTH AND SOUTH					
WEIGHTED AVERAGE FOR THE FIRST QUARTER				818.00	128.17	104.48	99.92
=====							
NHPP030A-035		US 285/SH30	04/04/19	80.00	150.00	70.00	70.00
NHPP0703-445		I-70 WESTBOUND PEAK PERIOD SH	04/25/19	120.00	150.00	106.85	112.00
FBR0063-057		US-6 F-09-K BRIDGE OVER CASTL	05/30/19	10.00	130.00	166.75	126.50
STRR200-257		ROAD CLOSURE GATES ON VARIOUS	05/30/19	8.00	120.00	216.00	150.00
NHPP0703-442		I-70 SILVERPLUME SOUNDWALL AN	06/13/19	10.00	90.00	134.41	95.00
STR 141A-040		R5 YEAR 4 BRDG PREV MAINT RAM	06/20/19	56.00	85.00	219.00	120.00
WEIGHTED AVERAGE FOR THE SECOND QUARTER				284.00	133.52	128.95	102.73
=====							
WEIGHTED AVERAGE FOR THE YEAR				1,102.00	129.55	107.94	100.67
=====							
===== 240-00020							
		Netting		Sq Yard			
STAR200-242		R2 NORTH PROGRAM WALL REPAIRS	01/03/19	100.00	10.00	19.22	16.00
IM0251-351		I-25 South of Pueblo MP 79.6	01/03/19	2,100.00	10.00	7.67	11.26
ER119A-065		PR SH 119A BOULDER CANYON	01/03/19	1,400.00	11.00	13.48	9.00
STA119A-069		SH 119: NEDERLAND - EAST					
STR0132-021		SH 13-MOFFAT COUNTY-CR 3 SOUT	01/10/19	40.00	20.00	23.09	15.40
FBR0341-087		US 34 OVER NORTH FORK CO RIVE	01/10/19	400.00	18.00	9.72	8.57
ER072A-040		PR SH72A FLOOD PERMANENT REPA	01/31/19	114.00	20.00	13.69	3.00
NHPP072A-041		PR SH72A FLOOD PERMANENT REPA					
NHPP0702-378		I-70 OFFICERS GULCH TO FRISCO	03/14/19	100.00	20.00	16.59	9.78

COLORADO DEPARTMENT OF TRANSPORTATION
 ITEM UNIT COSTS BY PROJECTS -- 2019 COST DATA

13:44 Wednesday, August 7, 2019 118

PROJECT NUMBER	ITEM NUMBER/ PROJECT LOCATION	ITEM DESCRIPTION/ PROJECT LOCATION	DATE LET	UNIT/ QUANTITY	ENGR. EST.	AVERAGE BID	AWARDED BID
===== 240-00020	Netting			Sq Yard			
STM0242-077		US24 - 8TH ST TO WEST OF MANI	03/28/19	5,892.00	12.83	5.00	3.00
	WEIGHTED AVERAGE FOR THE FIRST QUARTER			10,146.00	12.35	8.61	6.00
FBR0063-057		US-6 F-09-K BRIDGE OVER CASTL	05/30/19	400.00	10.00	13.75	10.50
	WEIGHTED AVERAGE FOR THE SECOND QUARTER			400.00	10.00	13.75	10.50
	WEIGHTED AVERAGE FOR THE YEAR			10,546.00	12.26	8.70	6.17
===== 240-00100	Prairie Dog Mgmt			LUMP SUM			
NHPP030A-036		SH 30 & TOWER RD IMPROVEMENTS	06/13/19	1.00	15000.00	1000.00	1000.00
	WEIGHTED AVERAGE FOR THE SECOND QUARTER			1.00	15000.00	1000.00	1000.00
	WEIGHTED AVERAGE FOR THE YEAR			1.00	15000.00	1000.00	1000.00
===== 250-00010	Envir Health/Safety Mngmt			LUMP SUM			
NHPPR500-173		US 160_550 DURANGO SIGNALS OP	01/03/19	1.00	5000.00	5000.00	5200.00
FBR0341-087		US 34 OVER NORTH FORK CO RIVE	01/10/19	1.00	4500.00	5371.67	7020.00
ER072A-040		PR SH72A FLOOD PERMANENT REPA	01/31/19	1.00	5000.00	4580.93	8100.00
NHPP072A-041		PR SH72A FLOOD PERMANENT REPA					
NHPP070A-028		FALL RIVER ROAD BRIDGE	02/21/19	1.00	6000.00	3937.80	2400.00
	WEIGHTED AVERAGE FOR THE FIRST QUARTER			4.00	5125.00	4675.61	5680.00
FBR0063-057		US-6 F-09-K BRIDGE OVER CASTL	05/30/19	1.00	5000.00	2875.00	3000.00
	WEIGHTED AVERAGE FOR THE SECOND QUARTER			1.00	5000.00	2875.00	3000.00
	WEIGHTED AVERAGE FOR THE YEAR			5.00	5100.00	4542.23	5144.00
===== 250-00050	Monitoring Technician			Hour			
NHPPR500-173		US 160_550 DURANGO SIGNALS OP	01/03/19	80.00	250.00	100.00	100.00

PROJECT NUMBER	ITEM NUMBER/ PROJECT LOCATION	ITEM DESCRIPTION/ PROJECT LOCATION	DATE LET	UNIT/ QUANTITY	ENGR. EST.	AVERAGE BID	AWARDED BID
=====	250-00050	Monitoring Technician		Hour =====			
FBR0341-087		US 34 OVER NORTH FORK CO RIVE	01/10/19	10.00	135.00	87.90	78.00
ER072A-040		PR SH72A FLOOD PERMANENT REPA	01/31/19	43.00	100.00	98.57	120.00
NHPP072A-041		PR SH72A FLOOD PERMANENT REPA					
NHPP070A-028		FALL RIVER ROAD BRIDGE	02/21/19	64.00	125.00	84.87	90.00
		WEIGHTED AVERAGE FOR THE FIRST QUARTER		197.00	170.81	94.03	100.00
FBR0063-057		US-6 F-09-K BRIDGE OVER CASTL	05/30/19	10.00	80.00	113.50	117.00
		WEIGHTED AVERAGE FOR THE SECOND QUARTER		10.00	80.00	113.50	117.00
		WEIGHTED AVERAGE FOR THE YEAR		207.00	166.43	94.39	100.82
=====	250-00110	Health and Safety Officer		Hour =====			
NHPPR500-173		US 160_550 DURANGO SIGNALS OP	01/03/19	8.00	200.00	171.00	142.00
FBR0341-087		US 34 OVER NORTH FORK CO RIVE	01/10/19	10.00	150.00	104.32	78.00
ER072A-040		PR SH72A FLOOD PERMANENT REPA	01/31/19	43.00	100.00	116.14	135.00
NHPP072A-041		PR SH72A FLOOD PERMANENT REPA					
NHPP070A-028		FALL RIVER ROAD BRIDGE	02/21/19	24.00	125.00	98.19	110.00
		WEIGHTED AVERAGE FOR THE FIRST QUARTER		85.00	122.35	113.35	121.89
FBR0063-057		US-6 F-09-K BRIDGE OVER CASTL	05/30/19	15.00	100.00	125.50	130.00
STR 141A-040		R5 YEAR 4 BRDG PREV MAINT RAM	06/20/19	60.00	110.00	100.00	100.00
		WEIGHTED AVERAGE FOR THE SECOND QUARTER		75.00	108.00	105.10	106.00
		WEIGHTED AVERAGE FOR THE YEAR		160.00	115.63	111.92	114.44
=====	250-00120	Material Sampling and Delivery		Each =====			
FBR0341-087		US 34 OVER NORTH FORK CO RIVE	01/10/19	1.00	1000.00	290.31	476.32
		WEIGHTED AVERAGE FOR THE FIRST QUARTER		1.00	1000.00	290.31	476.32
FBR0063-057		US-6 F-09-K BRIDGE OVER CASTL	05/30/19	1.00	400.00	520.50	275.00
		WEIGHTED AVERAGE FOR THE SECOND QUARTER		1.00	400.00	520.50	275.00
		WEIGHTED AVERAGE FOR THE YEAR		2.00	700.00	347.86	375.66

COLORADO DEPARTMENT OF TRANSPORTATION
 ITEM UNIT COSTS BY PROJECTS -- 2019 COST DATA

13:44 Wednesday, August 7, 2019 120

PROJECT NUMBER	ITEM NUMBER/ PROJECT LOCATION	ITEM DESCRIPTION/ PROJECT LOCATION	DATE LET	UNIT/ QUANTITY	ENGR. EST.	AVERAGE BID	AWARDED BID
=====	250-00200	Material Handling (Stockpile)		Cubic Yard	=====		
NHPPR500-173		US 160_550 DURANGO SIGNALS OP	01/03/19	5.00	300.00	1741.50	2883.00
	WEIGHTED AVERAGE FOR THE FIRST QUARTER			5.00	300.00	1741.50	2883.00
	WEIGHTED AVERAGE FOR THE YEAR			5.00	300.00	1741.50	2883.00
=====	304-01000	ABC (CL 1)		Ton	=====		
STR0132-021		SH 13-MOFFAT COUNTY-CR 3 SOUT	01/10/19	59,888.00	16.00	19.67	17.60
STA0131-070 HMA ALT		SH 13 CR 5 NORTH AND SOUTH	03/28/19	134,792.00	20.00	23.32	17.85
STA0131-070 PCCP ALT		SH 13 CR 5 NORTH AND SOUTH					
	WEIGHTED AVERAGE FOR THE FIRST QUARTER			194,680.00	18.77	21.77	17.67
	WEIGHTED AVERAGE FOR THE YEAR			194,680.00	18.77	21.77	17.67
=====	304-01005	ABC (CL 1)		Cubic Yard	=====		
FBR0341-087		US 34 OVER NORTH FORK CO RIVE	01/10/19	300.00	50.00	52.49	39.83
	WEIGHTED AVERAGE FOR THE FIRST QUARTER			300.00	50.00	52.49	39.83
	WEIGHTED AVERAGE FOR THE YEAR			300.00	50.00	52.49	39.83
=====	304-02000	ABC (CL 2)		Ton	=====		
NHPP145A-065		SH 145 PASSING LANES AT DEEP	02/14/19	10,766.00	21.00	33.89	25.00
NHPP1601-073		US 160 PASSING LANE NORTH OF	03/07/19	31,868.00	23.00	25.00	18.00
	WEIGHTED AVERAGE FOR THE FIRST QUARTER			42,634.00	22.49	29.07	19.77
ER145A-081		SH 145 MP 21 EMERGENCY ROCKFA	06/07/19	1,387.00	23.00	31.95	28.00
	WEIGHTED AVERAGE FOR THE SECOND QUARTER			1,387.00	23.00	31.95	28.00
	WEIGHTED AVERAGE FOR THE YEAR			44,021.00	22.51	29.14	20.03
=====	304-03000	ABC (CL 3)		Ton	=====		
SHE0701-243		I-70 EXIT 26 DDI MODIFICATION	05/16/19	548.00	25.00	30.25	31.00
	WEIGHTED AVERAGE FOR THE SECOND QUARTER			548.00	25.00	30.25	31.00
	WEIGHTED AVERAGE FOR THE YEAR			548.00	25.00	30.25	31.00

COLORADO DEPARTMENT OF TRANSPORTATION
ITEM UNIT COSTS BY PROJECTS -- 2019 COST DATA

13:44 Wednesday, August 7, 2019 121

PROJECT NUMBER	ITEM NUMBER/ PROJECT LOCATION	ITEM DESCRIPTION/ PROJECT LOCATION	DATE LET	UNIT/ QUANTITY	ENGR. EST.	AVERAGE BID	AWARDED BID
=====	304-03005	ABC (CL 3)		Cubic Yard	=====		
FBR0063-057		US-6 F-09-K BRIDGE OVER CASTL	05/30/19	50.00	60.00	66.77	53.00
		WEIGHTED AVERAGE FOR THE SECOND QUARTER		50.00	60.00	66.77	53.00
		WEIGHTED AVERAGE FOR THE YEAR		50.00	60.00	66.77	53.00
=====	304-06000	ABC (CL 6)		Ton	=====		
FSA0142-068		SH 14 & WCR 33 INTERSECTION I	01/03/19	91.00	75.00	81.20	40.00
ER119A-065		PR SH 119A BOULDER CANYON	01/03/19	3,563.00	25.00	35.82	42.00
STA119A-069		SH 119: NEDERLAND - EAST					
STR0132-021		SH 13-MOFFAT COUNTY-CR 3 SOUT	01/10/19	40,976.00	17.00	21.73	19.20
FBR0341-087		US 34 OVER NORTH FORK CO RIVE	01/10/19	1,075.00	30.00	35.46	27.10
NHPP0701-241		I-70 TRUCK PARKING GARFIELD C	01/17/19	7,076.00	30.00	35.68	32.00
STAM086-075		SH96A ABRIENDO - ORMAN SAFETY	01/31/19	377.00	25.00	80.83	44.50
NHPP145A-065		SH 145 PASSING LANES AT DEEP	02/14/19	4,835.00	25.00	39.99	29.00
NHPP0741-022		SH 74: I-70 TO CR 65 RESURFAC	02/14/19	26.00	52.00	110.97	55.85
SHER100-284		FY19 NORTH SIGNAL PKG	02/21/19	5.00	50.00	144.00	170.00
NHPP1601-073		US 160 PASSING LANE NORTH OF	03/07/19	21,001.00	27.00	26.00	18.00
C R100-315		R1 ADA CURB RAMPS - PH 5	03/07/19	900.00	40.00	77.50	65.00
NHPP050A-033		US50 West of Delta EB Lanes R	03/14/19	137.30	50.00	50.97	69.90
NHPP0503-087		US 50 PASSING LANES EAST OF S	03/21/19	11,908.00	21.00	26.50	23.00
SHER100-308		MIDPOINT - SIGNAL CONST PACKA	03/21/19	489.00	50.00	72.50	45.00
STM0242-077		US24 - 8TH ST TO WEST OF MANI	03/28/19	1,735.00	35.00	40.67	60.00
STA0131-070 HMA ALT		SH 13 CR 5 NORTH AND SOUTH	03/28/19	113,756.00	22.00	25.85	21.65
STA0131-070 PCCP ALT		SH 13 CR 5 NORTH AND SOUTH					
		WEIGHTED AVERAGE FOR THE FIRST QUARTER		207,950.30	22.20	26.59	22.69
NHPP030A-035		US 285/SH30	04/04/19	1,737.00	35.00	40.00	40.00
IM0252-472		I-25 CABLE BARRIER PHASE III	04/04/19	4,345.00	35.00	32.00	29.00
NHPP0703-445		I-70 WESTBOUND PEAK PERIOD SH	04/25/19	18,783.00	35.00	31.73	22.00
CR300-248		CRAIG RESIDENCY ADA RAMPS	05/16/19	415.00	40.00	67.00	43.00
SHE0701-243		I-70 EXIT 26 DDI MODIFICATION	05/16/19	522.00	30.00	35.63	33.00
FBR0063-057		US-6 F-09-K BRIDGE OVER CASTL	05/30/19	925.00	40.00	43.46	38.00
ER145A-081		SH 145 MP 21 EMERGENCY ROCKFA	06/07/19	394.00	27.00	51.09	52.00
		WEIGHTED AVERAGE FOR THE SECOND QUARTER		27,121.00	35.03	33.19	25.79
		WEIGHTED AVERAGE FOR THE YEAR		235,071.30	23.68	27.20	23.15
=====	304-06007	ABC (CL 6)		Cubic Yard	=====		
SHER100-289		INTERSECTIONS @ SH83 & LONGS	01/03/19	518.00	40.00	51.60	48.00

PROJECT NUMBER	ITEM NUMBER/ PROJECT LOCATION	ITEM DESCRIPTION/ PROJECT LOCATION	DATE LET	UNIT/ QUANTITY	ENGR. EST.	AVERAGE BID	AWARDED BID
===== 304-06007	ABC (CL 6)			Cubic Yard			
ER119A-065	PR SH 119A BOULDER CANYON		01/03/19	6,619.00	35.00	54.58	49.50
STA119A-069	SH 119: NEDERLAND - EAST						
STR141A-047	SH 141 MP 120-143 MESA COUNTY		01/17/19	6,716.00	40.00	56.90	47.00
STR0241-062	US 24 143.4 - 148		01/24/19	1,465.00	55.00	110.00	80.00
ER072A-040	PR SH72A FLOOD PERMANENT REPA		01/31/19	59.00	45.00	84.57	57.00
NHPP072A-041	PR SH72A FLOOD PERMANENT REPA						
STA067A-038	SH 67 SEDALIA RESURFACING		01/31/19	58.00	35.00	120.70	90.00
NH2871-035	US 287 PASSING LANES SOUTH OF		02/07/19	4,671.00	50.00	55.73	42.25
NHPP070A-028	FALL RIVER ROAD BRIDGE		02/21/19	987.00	35.00	45.43	39.00
FBR0253-247	I25 AT VINE DRIVE BRIDGE REPL		03/07/19	2,282.00	45.00	50.82	45.00
SHE2254-090	Colfax & I-225, Colfax & Cham		03/07/19	614.00	50.00	86.50	93.00
SHER100-308	MIDPOINT - SIGNAL CONST PACKA		03/21/19	133.00	90.00	96.00	77.00
STM0242-077	US24 - 8TH ST TO WEST OF MANI		03/28/19	401.00	55.00	70.67	100.00
	WEIGHTED AVERAGE FOR THE FIRST QUARTER			24,523.00	42.48	56.61	50.56
BR071A-020	REPLACEMENT OF STRUCTURE L-22		04/18/19	603.00	30.00	56.67	46.00
C2571-013	SH257 & 392:WINDSOR CURB RAMP		05/02/19	181.00	65.00	70.00	60.00
MTCE0641-103	MTCE R3 FY20 SH 64 RANGELY PE		05/02/19	77.00	65.00	227.50	105.00
FSA2873-190	US 287 AND FOOTHILLS PARKWAY		05/02/19	14.00	200.00	150.00	180.00
FSA0703-454	EB I-70 AUX LANE WARD TO KIPL		05/16/19	2,232.00	54.00	54.15	45.00
STMC430-020	ADA RAMPS DIVIDE ESB		05/23/19	42.00	42.00	141.29	141.29
NHPP0703-442	I-70 SILVERPLUME SOUNDWALL AN		06/13/19	146.00	60.00	83.98	76.00
NHPP030A-036	SH 30 & TOWER RD IMPROVEMENTS		06/13/19	500.00	50.00	100.00	100.00
	WEIGHTED AVERAGE FOR THE SECOND QUARTER			3,795.00	51.04	63.65	57.09
	WEIGHTED AVERAGE FOR THE YEAR			28,318.00	43.63	57.13	51.44
===== 304-06008	ABC (CL 6) (Spec)			Cubic Yard			
ER119A-065	PR SH 119A BOULDER CANYON		01/03/19	48.00	40.00	92.03	125.00
STA119A-069	SH 119: NEDERLAND - EAST						
FBR0253-247	I25 AT VINE DRIVE BRIDGE REPL		03/07/19	386.00	60.00	63.25	55.00
	WEIGHTED AVERAGE FOR THE FIRST QUARTER			434.00	57.79	65.63	62.74
	WEIGHTED AVERAGE FOR THE YEAR			434.00	57.79	65.63	62.74
===== 304-06009	ABC (CL 6) (Spec)			Ton			
NHPP1601-073	US 160 PASSING LANE NORTH OF		03/07/19	4,460.00	40.00	30.00	30.00
	WEIGHTED AVERAGE FOR THE FIRST QUARTER			4,460.00	40.00	30.00	30.00
	WEIGHTED AVERAGE FOR THE YEAR			4,460.00	40.00	30.00	30.00

COLORADO DEPARTMENT OF TRANSPORTATION
ITEM UNIT COSTS BY PROJECTS -- 2019 COST DATA

13:44 Wednesday, August 7, 2019 123

PROJECT NUMBER	ITEM NUMBER/ PROJECT LOCATION	ITEM DESCRIPTION/ PROJECT LOCATION	DATE LET	UNIT/ QUANTITY	ENGR. EST.	AVERAGE BID	AWARDED BID
=====	304-07000	ABC (CL 7)		Ton	=====	=====	=====
	STR141A-047	SH 141 MP 120-143 MESA COUNTY	01/17/19	8,453.62	30.00	27.59	20.00
	NHPP0821-107	SH 82 GLENWOOD SPRINGS TO CA	02/07/19	100.00	25.00	86.00	22.00
	NHPP050A-033	US50 West of Delta EB Lanes R	03/14/19	1,493.61	24.00	35.20	41.60
		WEIGHTED AVERAGE FOR THE FIRST QUARTER		10,047.23	29.06	28.78	23.23
		WEIGHTED AVERAGE FOR THE YEAR		10,047.23	29.06	28.78	23.23
=====	304-07005	ABC (CL 7)		Cubic Yard	=====	=====	=====
	STR0241-062	US 24 143.4 - 148	01/24/19	1,831.00	75.00	73.33	80.00
		WEIGHTED AVERAGE FOR THE FIRST QUARTER		1,831.00	75.00	73.33	80.00
		WEIGHTED AVERAGE FOR THE YEAR		1,831.00	75.00	73.33	80.00
=====	304-08002	ABC (Shoulder Material)		Cubic Yard	=====	=====	=====
	IM0251-351	I-25 South of Pueblo MP 79.6	01/03/19	504.00	42.00	52.13	42.90
	STM0242-077	US24 - 8TH ST TO WEST OF MANI	03/28/19	665.00	40.00	85.00	95.00
		WEIGHTED AVERAGE FOR THE FIRST QUARTER		1,169.00	40.86	68.48	72.54
		WEIGHTED AVERAGE FOR THE YEAR		1,169.00	40.86	68.48	72.54
=====	304-09001	ABC (Spec) (Install Only)		Cubic Yard	=====	=====	=====
	CR500-205	R5 GUARDRAIL END TREATMENT EA	06/13/19	27.00	100.00	355.00	355.00
		WEIGHTED AVERAGE FOR THE SECOND QUARTER		27.00	100.00	355.00	355.00
		WEIGHTED AVERAGE FOR THE YEAR		27.00	100.00	355.00	355.00
=====	304-09014	ABC (Spec)		Ton	=====	=====	=====
	ER119A-065	PR SH 119A BOULDER CANYON	01/03/19	333.00	50.00	81.12	44.00
	STA119A-069	SH 119: NEDERLAND - EAST					
	NHPP145A-065	SH 145 PASSING LANES AT DEEP	02/14/19	117.00	40.00	74.84	48.00

COLORADO DEPARTMENT OF TRANSPORTATION
 ITEM UNIT COSTS BY PROJECTS -- 2019 COST DATA

13:44 Wednesday, August 7, 2019 124

PROJECT NUMBER	ITEM NUMBER/ PROJECT LOCATION	ITEM DESCRIPTION/ PROJECT LOCATION	DATE LET	UNIT/ QUANTITY	ENGR. EST.	AVERAGE BID	AWARDED BID
===== 304-09014 NHPP0503-087	ABC (Spec) US 50 PASSING LANES EAST OF S		03/21/19	Ton 1,560.00	20.00	42.50	54.00
	WEIGHTED AVERAGE FOR THE FIRST QUARTER			2,010.00	26.13	61.62	51.99
	WEIGHTED AVERAGE FOR THE YEAR			2,010.00	26.13	61.62	51.99
===== 304-09100 NHPP2254-089	ABC (RAP) I-225 RESURFACING FROM I-25 T		03/21/19	Ton 436.30	50.00	25.45	30.00
	WEIGHTED AVERAGE FOR THE FIRST QUARTER			436.30	50.00	25.45	30.00
	WEIGHTED AVERAGE FOR THE YEAR			436.30	50.00	25.45	30.00
===== 307-00212 SHE 0252-481	Lime Tr Subgrade (12 In) I-25 RAMP METER INSTALLATION		03/21/19	Sq Yard 760.00	12.00	34.67	20.00
	WEIGHTED AVERAGE FOR THE FIRST QUARTER			760.00	12.00	34.67	20.00
	WEIGHTED AVERAGE FOR THE YEAR			760.00	12.00	34.67	20.00
===== 310-00500 NHPP050A-033	Full Depth Reclam of Hot Mix Asph Pvmt US50 West of Delta EB Lanes R		03/14/19	Sq Yard 18,993.00	0.80	2.18	2.90
	WEIGHTED AVERAGE FOR THE FIRST QUARTER			18,993.00	0.80	2.18	2.90
	WEIGHTED AVERAGE FOR THE YEAR			18,993.00	0.80	2.18	2.90
===== 310-00608 STA0131-070 HMA ALT STA0131-070 PCCP ALT	Full Depth Reclam. of HMA Pvmt (0-8 in.) SH 13 CR 5 NORTH AND SOUTH		03/28/19	Sq Yard 130,193.00	2.60	2.42	2.75
	WEIGHTED AVERAGE FOR THE FIRST QUARTER			130,193.00	2.60	2.42	2.75
	WEIGHTED AVERAGE FOR THE YEAR			130,193.00	2.60	2.42	2.75
===== 310-00610 STR0132-021	Full Depth Reclam. of HMA Pvmt (8-12 in.) SH 13-MOFFAT COUNTY-CR 3 SOUT		01/10/19	Sq Yard 66,711.00	2.50	2.07	0.95

COLORADO DEPARTMENT OF TRANSPORTATION
ITEM UNIT COSTS BY PROJECTS -- 2019 COST DATA

13:44 Wednesday, August 7, 2019 125

PROJECT NUMBER	ITEM NUMBER/ PROJECT LOCATION	ITEM DESCRIPTION/ PROJECT LOCATION	DATE LET	UNIT/ QUANTITY	ENGR. EST.	AVERAGE BID	AWARDED BID
===== 310-00610		Full Depth Reclam. of HMA Pvmt (8-12 in)		Sq Yard	=====	=====	=====
NHPP1601-073		US 160 PASSING LANE NORTH OF	03/07/19	38,140.00	5.00	4.25	2.50
STA0131-070 HMA ALT		SH 13 CR 5 NORTH AND SOUTH	03/28/19	32,549.00	2.80	2.48	2.80
STA0131-070 PCCP ALT		SH 13 CR 5 NORTH AND SOUTH					
	WEIGHTED AVERAGE FOR THE FIRST QUARTER			137,400.00	3.27	2.48	1.69
	WEIGHTED AVERAGE FOR THE YEAR			137,400.00	3.27	2.48	1.69
===== 310-00614		Full Depth Reclam of HMA Pvmt (12-16 in)		Sq Yard	=====	=====	=====
NHPP050A-033		US50 West of Delta EB Lanes R	03/14/19	45,525.00	6.00	5.07	3.95
	WEIGHTED AVERAGE FOR THE FIRST QUARTER			45,525.00	6.00	5.07	3.95
	WEIGHTED AVERAGE FOR THE YEAR			45,525.00	6.00	5.07	3.95
===== 403-00720		HMA (Patching) (Asph)		Ton	=====	=====	=====
IM0251-351		I-25 South of Pueblo MP 79.6	01/03/19	616.00	135.00	156.17	135.49
FSA0142-068		SH 14 & WCR 33 INTERSECTION I	01/03/19	50.00	210.00	242.00	300.00
SHER100-289		INTERSECTIONS @ SH83 & LONGS	01/03/19	157.00	200.00	183.20	250.00
ER119A-065		PR SH 119A BOULDER CANYON	01/03/19	957.00	185.00	167.15	145.00
STA119A-069		SH 119: NEDERLAND - EAST					
STR0132-021		SH 13-MOFFAT COUNTY-CR 3 SOUT	01/10/19	120.00	300.00	187.60	165.00
FBR0341-087		US 34 OVER NORTH FORK CO RIVE	01/10/19	122.00	260.00	300.49	286.20
NHPP0701-241		I-70 TRUCK PARKING GARFIELD C	01/17/19	6.00	400.00	597.81	450.00
STR0241-062		US 24 143.4 - 148	01/24/19	215.00	175.00	240.00	230.00
ER072A-040		PR SH72A FLOOD PERMANENT REPA	01/31/19	10,300.00	150.00	135.59	105.00
NHPP072A-041		PR SH72A FLOOD PERMANENT REPA					
STAM086-075		SH96A ABRIENDO - ORMAN SAFETY	01/31/19	115.00	150.00	251.33	162.00
STA067A-038		SH 67 SEDALIA RESURFACING	01/31/19	112.00	200.00	262.27	170.00
NHPP0821-107		SH 82 GLENWOOD SPRINGS TO CA	02/07/19	100.00	230.00	152.50	125.00
NHPP145A-065		SH 145 PASSING LANES AT DEEP	02/14/19	540.00	350.00	221.95	155.00
NHPP0741-022		SH 74: I-70 TO CR 65 RESURFAC	02/14/19	572.00	200.00	171.25	170.00
NHPP070A-028		FALL RIVER ROAD BRIDGE	02/21/19	50.00	225.00	191.61	160.00
SHER100-284		FY19 NORTH SIGNAL PKG	02/21/19	15.00	250.00	310.00	310.00
NHPP1601-073		US 160 PASSING LANE NORTH OF	03/07/19	204.00	175.00	202.50	205.00
NHPP006A-058		US 6 LOVELAND PASS - I-70 (FY	03/07/19	1,000.00	350.00	146.07	162.14
C R100-315		R1 ADA CURB RAMPS - PH 5	03/07/19	213.00	170.00	412.50	325.00
SHE2254-090		Colfax & I-225, Colfax & Cham	03/07/19	33.00	125.00	237.50	300.00
NHPP050A-033		US50 West of Delta EB Lanes R	03/14/19	7,798.70	90.00	103.33	80.00
NHPP0503-087		US 50 PASSING LANES EAST OF S	03/21/19	559.00	175.00	135.00	120.00
SHER100-308		MIDPOINT - SIGNAL CONST PACKA	03/21/19	575.00	185.00	325.00	260.00
NHPP2254-089		I-225 RESURFACING FROM I-25 T	03/21/19	298.11	200.00	286.61	325.00

COLORADO DEPARTMENT OF TRANSPORTATION
ITEM UNIT COSTS BY PROJECTS -- 2019 COST DATA

13:44 Wednesday, August 7, 2019 126

PROJECT NUMBER	ITEM NUMBER/ PROJECT LOCATION	ITEM DESCRIPTION/ PROJECT LOCATION	DATE LET	UNIT/ QUANTITY	ENGR. EST.	AVERAGE BID	AWARDED BID	
===== 403-00720								
STM0242-077		HMA (Patching) (Asph) US24 - 8TH ST TO WEST OF MANI	03/28/19	Ton 535.00	175.98	178.58	155.75	
STA0131-070 HMA ALT		SH 13 CR 5 NORTH AND SOUTH	03/28/19	700.00	200.00	210.45	193.00	
STA0131-070 PCCP ALT		SH 13 CR 5 NORTH AND SOUTH						
WEIGHTED AVERAGE FOR THE FIRST QUARTER				25,962.81	152.59	141.29	120.25	
NHPP030A-035		US 285/SH30	04/04/19	50.00	225.00	435.00	435.00	
BR071A-020		REPLACEMENT OF STRUCTURE L-22	04/18/19	40.00	175.00	290.00	260.00	
NHPP0703-445		I-70 WESTBOUND PEAK PERIOD SH	04/25/19	5,592.00	200.00	170.08	157.00	
C2571-013		SH257 & 392:WINDSOR CURB RAMP	05/02/19	46.00	300.00	351.33	300.00	
FSA2873-190		US 287 AND FOOTHILLS PARKWAY	05/02/19	8.00	325.00	523.50	430.00	
STMC430-020		ADA RAMPS DIVIDE ESB	05/23/19	41.00	210.00	282.22	282.22	
FBR0063-057		US-6 F-09-K BRIDGE OVER CASTL	05/30/19	103.00	130.00	245.32	235.00	
ER145A-081		SH 145 MP 21 EMERGENCY ROCKFA	06/07/19	443.00	175.00	218.96	236.00	
NHPP0703-442		I-70 SILVERPLUME SOUNDWALL AN	06/13/19	335.00	250.00	230.17	170.00	
STR 141A-040		R5 YEAR 4 BRDG PREV MAINT RAM	06/20/19	360.00	300.00	512.50	550.00	
WEIGHTED AVERAGE FOR THE SECOND QUARTER				7,018.00	205.80	194.55	188.46	
WEIGHTED AVERAGE FOR THE YEAR				32,980.81	163.92	147.12	134.92	
===== 403-00721								
				Sq Yard				
STAR200-242		R2 NORTH PROGRAM WALL REPAIRS	01/03/19	11.00	50.00	485.53	298.00	
NHPPR100-250		PACKAGE A (I-25 / I-70 / I-76	01/24/19	723.00	290.00	54.16	25.00	
NHPP0821-107		SH 82 GLENWOOD SPRINGS TO CA	02/07/19	47.00	38.00	187.50	50.00	
NHPP0702-378		I-70 OFFICERS GULCH TO FRISCO	03/14/19	710.00	45.00	55.88	34.65	
SHE 0252-481		I-25 RAMP METER INSTALLATION	03/21/19	406.00	300.00	141.00	58.00	
WEIGHTED AVERAGE FOR THE FIRST QUARTER				1,897.00	192.81	72.73	37.88	
STRR300-236		SH 92 and SH 133	04/04/19	50.00	250.00	150.00	150.00	
MTCE0641-103		MTCE R3 FY20 SH 64 RANGELY PE	05/02/19	328.00	49.00	83.00	100.00	
CR300-248		CRAIG RESIDENCY ADA RAMPS	05/16/19	50.00	150.00	134.00	95.00	
WEIGHTED AVERAGE FOR THE SECOND QUARTER				428.00	84.28	95.85	105.26	
WEIGHTED AVERAGE FOR THE YEAR				2,325.00	172.83	75.22	50.28	
===== 403-00800								
				Ton				
STA067A-038		Emerg Pothole Rep SH 67 SEDALIA RESURFACING	01/31/19	10.00	600.00	632.64	600.00	

COLORADO DEPARTMENT OF TRANSPORTATION
ITEM UNIT COSTS BY PROJECTS -- 2019 COST DATA

13:44 Wednesday, August 7, 2019 127

PROJECT NUMBER	ITEM NUMBER/ PROJECT LOCATION	ITEM DESCRIPTION/ PROJECT LOCATION	DATE LET	UNIT/ QUANTITY	ENGR. EST.	AVERAGE BID	AWARDED BID
===== 403-00800		Emerg Pothole Rep		Ton =====			
NHPP0741-022		SH 74: I-70 TO CR 65 RESURFAC	02/14/19	50.00	750.00	658.75	700.00
NHPP2254-089		I-225 RESURFACING FROM I-25 T	03/21/19	50.00	500.00	651.54	875.00
		WEIGHTED AVERAGE FOR THE FIRST QUARTER		110.00	622.73	653.84	770.45
NHPP030A-035		US 285/SH30	04/04/19	50.00	500.00	1000.00	1000.00
		WEIGHTED AVERAGE FOR THE SECOND QUARTER		50.00	500.00	1000.00	1000.00
		WEIGHTED AVERAGE FOR THE YEAR		160.00	584.38	694.09	842.19
===== 403-09210		SMA		Ton =====			
ER119A-065		PR SH 119A BOULDER CANYON	01/03/19	42,231.00	135.00	115.14	111.00
STA119A-069		SH 119: NEDERLAND - EAST					
		WEIGHTED AVERAGE FOR THE FIRST QUARTER		42,231.00	135.00	115.14	111.00
		WEIGHTED AVERAGE FOR THE YEAR		42,231.00	135.00	115.14	111.00
===== 403-09221		SMA (Fibers) (Asph)		Ton =====			
NHPP1601-073		US 160 PASSING LANE NORTH OF	03/07/19	7,646.00	120.00	144.50	149.00
NHPP2254-089		I-225 RESURFACING FROM I-25 T	03/21/19	50,328.08	100.00	127.82	115.00
		WEIGHTED AVERAGE FOR THE FIRST QUARTER		57,974.08	102.64	129.36	119.48
NHPP030A-035		US 285/SH30	04/04/19	23,676.60	115.00	115.00	115.00
FSA0703-454		EB I-70 AUX LANE WARD TO KIPL	05/16/19	1,346.00	125.00	133.83	126.20
		WEIGHTED AVERAGE FOR THE SECOND QUARTER		25,022.60	115.54	117.74	115.60
		WEIGHTED AVERAGE FOR THE YEAR		82,996.68	106.53	127.70	118.31
===== 403-09500		Furnish HMA		Ton =====			
STR141A-047		SH 141 MP 120-143 MESA COUNTY	01/17/19	6,897.41	50.00	89.82	90.00

COLORADO DEPARTMENT OF TRANSPORTATION
ITEM UNIT COSTS BY PROJECTS -- 2019 COST DATA

13:44 Wednesday, August 7, 2019 128

PROJECT NUMBER	ITEM NUMBER/ PROJECT LOCATION	ITEM DESCRIPTION/ PROJECT LOCATION	DATE LET	UNIT/ QUANTITY	ENGR. EST.	AVERAGE BID	AWARDED BID
===== 403-09500		Furnish HMA		Ton =====			
NHPP1601-073	US 160 PASSING LANE NORTH OF		03/07/19	800.00	70.00	90.75	91.50
	WEIGHTED AVERAGE FOR THE FIRST QUARTER			7,697.41	52.08	89.87	90.16
	WEIGHTED AVERAGE FOR THE YEAR			7,697.41	52.08	89.87	90.16
===== 403-33741		HMA (Gr S) (75) (PG 64-22)		Ton =====			
NHPP030A-036	SH 30 & TOWER RD IMPROVEMENTS		06/13/19	1,501.00	80.00	102.00	102.00
	WEIGHTED AVERAGE FOR THE SECOND QUARTER			1,501.00	80.00	102.00	102.00
	WEIGHTED AVERAGE FOR THE YEAR			1,501.00	80.00	102.00	102.00
===== 403-34701		HMA (Gr SX) (75)		Ton =====			
STR0132-021	SH 13-MOFFAT COUNTY-CR 3 SOUT		01/10/19	38,824.00	50.00	57.54	59.30
FBR0341-087	US 34 OVER NORTH FORK CO RIVE		01/10/19	975.00	125.00	195.93	197.28
STR141A-047	SH 141 MP 120-143 MESA COUNTY		01/17/19	30,946.82	55.00	67.85	55.00
STR0241-062	US 24 143.4 - 148		01/24/19	11,178.00	67.00	104.33	120.00
NHPP0821-107	SH 82 GLENWOOD SPRINGS TO CA		02/07/19	30,182.00	62.00	52.50	50.00
NHPP0702-378	I-70 OFFICERS GULCH TO FRISCO		03/14/19	26,007.00	75.00	79.85	90.54
	WEIGHTED AVERAGE FOR THE FIRST QUARTER			138,112.82	60.36	67.81	68.07
FBR0063-057	US-6 F-09-K BRIDGE OVER CASTL		05/30/19	1,135.00	180.00	105.22	100.00
	WEIGHTED AVERAGE FOR THE SECOND QUARTER			1,135.00	180.00	105.22	100.00
	WEIGHTED AVERAGE FOR THE YEAR			139,247.82	61.33	67.98	68.33
===== 403-34721		HMA (Gr SX) (75) (PG 58-28)		Ton =====			
ER119A-065	PR SH 119A BOULDER CANYON		01/03/19	26,681.00	87.25	87.57	82.00
STA119A-069	SH 119: NEDERLAND - EAST						
NHPP145A-065	SH 145 PASSING LANES AT DEEP		02/14/19	6,815.00	125.00	130.76	125.00
NHPP0741-022	SH 74: I-70 TO CR 65 RESURFAC		02/14/19	15,855.00	95.00	82.35	73.40
NHPP070A-028	FALL RIVER ROAD BRIDGE		02/21/19	1,088.00	110.00	117.70	97.00
NHPP0503-087	US 50 PASSING LANES EAST OF S		03/21/19	13,599.00	82.00	92.50	87.00

COLORADO DEPARTMENT OF TRANSPORTATION
 ITEM UNIT COSTS BY PROJECTS -- 2019 COST DATA

13:44 Wednesday, August 7, 2019 129

PROJECT NUMBER	ITEM NUMBER/ PROJECT LOCATION	ITEM DESCRIPTION/ PROJECT LOCATION	DATE LET	UNIT/ QUANTITY	ENGR. EST.	AVERAGE BID	AWARDED BID
===== 403-34721		HMA (Gr SX) (75) (PG 58-28)		Ton =====			
STM0242-077		US24 - 8TH ST TO WEST OF MANI	03/28/19	1,271.80	70.00	97.50	95.50
		WEIGHTED AVERAGE FOR THE FIRST QUARTER		65,309.80	92.02	91.82	85.95
IM0252-472		I-25 CABLE BARRIER PHASE III	04/04/19	1,195.00	130.00	152.50	170.00
		WEIGHTED AVERAGE FOR THE SECOND QUARTER		1,195.00	130.00	152.50	170.00
		WEIGHTED AVERAGE FOR THE YEAR		66,504.80	92.70	92.23	87.46
===== 403-34723		HMA (Gr SX) (75) (PG 58-28) (3 In)		Sq Yard =====			
STA0131-070 HMA ALT		SH 13 CR 5 NORTH AND SOUTH	03/28/19	7,362.00	16.00	21.08	22.10
STA0131-070 PCCP ALT		SH 13 CR 5 NORTH AND SOUTH					
		WEIGHTED AVERAGE FOR THE FIRST QUARTER		7,362.00	16.00	21.08	22.10
		WEIGHTED AVERAGE FOR THE YEAR		7,362.00	16.00	21.08	22.10
===== 403-34725		HMA (Gr SX) (75) (PG 58-28) (4.5 In)		Sq Yard =====			
STA0131-070 HMA ALT		SH 13 CR 5 NORTH AND SOUTH	03/28/19	145,072.00	19.01	20.09	31.70
STA0131-070 PCCP ALT		SH 13 CR 5 NORTH AND SOUTH					
		WEIGHTED AVERAGE FOR THE FIRST QUARTER		145,072.00	19.01	20.09	31.70
		WEIGHTED AVERAGE FOR THE YEAR		145,072.00	19.01	20.09	31.70
===== 403-34731		HMA (Gr SX) (75) (PG 58-34)		Ton =====			
NHPP006A-058		US 6 LOVELAND PASS - I-70 (FY 03/07/19)		21,911.00	95.00	116.29	118.57
		WEIGHTED AVERAGE FOR THE FIRST QUARTER		21,911.00	95.00	116.29	118.57
		WEIGHTED AVERAGE FOR THE YEAR		21,911.00	95.00	116.29	118.57
===== 403-34733		HMA (Gr SX) (75) (PG 58-34) (2 In)		Sq Yard =====			
STA0131-070 HMA ALT		SH 13 CR 5 NORTH AND SOUTH	03/28/19	162,662.00	9.06	11.32	14.40

COLORADO DEPARTMENT OF TRANSPORTATION
 ITEM UNIT COSTS BY PROJECTS -- 2019 COST DATA

13:44 Wednesday, August 7, 2019 130

PROJECT NUMBER	ITEM NUMBER/ PROJECT LOCATION	ITEM DESCRIPTION/ PROJECT LOCATION	DATE LET	UNIT/ QUANTITY	ENGR. EST.	AVERAGE BID	AWARDED BID
===== 403-34733	STA0131-070 PCCP ALT	HMA (Gr SX) (75) (PG 58-34) (2 In) SH 13 CR 5 NORTH AND SOUTH		Sq Yard			
		WEIGHTED AVERAGE FOR THE FIRST QUARTER		162,662.00	9.06	11.32	14.40
		WEIGHTED AVERAGE FOR THE YEAR		162,662.00	9.06	11.32	14.40
===== 403-34751	FSA0142-068 SHER100-289	HMA (Gr SX) (75) (PG 64-28) SH 14 & WCR 33 INTERSECTION I INTERSECTIONS @ SH83 & LONGS	01/03/19 01/03/19	310.00 997.00	167.50 200.00	158.75 119.00	154.00 104.00
		WEIGHTED AVERAGE FOR THE FIRST QUARTER		1,307.00	192.29	126.92	115.86
		WEIGHTED AVERAGE FOR THE YEAR		1,307.00	192.29	126.92	115.86
===== 403-34771	IM0251-351 STA067A-038	HMA (Gr SX) (75) (PG 76-28) I-25 South of Pueblo MP 79.6 SH 67 SEDALIA RESURFACING	01/03/19 01/31/19	38,311.00 3,798.00	80.00 90.00	82.52 97.27	72.20 89.00
		WEIGHTED AVERAGE FOR THE FIRST QUARTER		42,109.00	80.90	83.54	73.72
NHPP030A-036		SH 30 & TOWER RD IMPROVEMENTS	06/13/19	551.00	90.00	125.00	125.00
		WEIGHTED AVERAGE FOR THE SECOND QUARTER		551.00	90.00	125.00	125.00
		WEIGHTED AVERAGE FOR THE YEAR		42,660.00	81.02	83.68	74.38
===== 403-34801	NHPP050A-033	HMA (Gr SX) (100) US50 West of Delta EB Lanes R	03/14/19	32,072.53	52.00	54.92	58.25
		WEIGHTED AVERAGE FOR THE FIRST QUARTER		32,072.53	52.00	54.92	58.25
		WEIGHTED AVERAGE FOR THE YEAR		32,072.53	52.00	54.92	58.25
===== 403-34821	STAM086-075	HMA (Gr SX) (100) (PG 58-28) SH96A ABRIENDO - ORMAN SAFETY	01/31/19	178.00	100.00	228.33	160.00
		WEIGHTED AVERAGE FOR THE FIRST QUARTER		178.00	100.00	228.33	160.00

COLORADO DEPARTMENT OF TRANSPORTATION
ITEM UNIT COSTS BY PROJECTS -- 2019 COST DATA

13:44 Wednesday, August 7, 2019 131

PROJECT NUMBER	ITEM NUMBER/ PROJECT LOCATION	ITEM DESCRIPTION/ PROJECT LOCATION	DATE LET	UNIT/ QUANTITY	ENGR. EST.	AVERAGE BID	AWARDED BID
===== 403-34821		HMA (Gr SX) (100) (PG 58-28)		Ton	=====	=====	=====
NHPP0703-445		I-70 WESTBOUND PEAK PERIOD SH	04/25/19	22,057.00	85.00	97.17	92.00
	WEIGHTED AVERAGE FOR THE SECOND QUARTER			22,057.00	85.00	97.17	92.00
	WEIGHTED AVERAGE FOR THE YEAR			22,235.00	85.12	98.22	92.54
===== 403-34841		HMA (Gr SX) (100) (PG 64-22)		Ton	=====	=====	=====
NHPP1601-073		US 160 PASSING LANE NORTH OF	03/07/19	17,313.00	85.00	109.25	108.50
SHER100-308		MIDPOINT - SIGNAL CONST PACKA	03/21/19	151.00	125.00	310.00	395.00
	WEIGHTED AVERAGE FOR THE FIRST QUARTER			17,464.00	85.35	110.99	110.98
FSA0703-454		EB I-70 AUX LANE WARD TO KIPL	05/16/19	1,423.00	95.00	95.58	85.32
	WEIGHTED AVERAGE FOR THE SECOND QUARTER			1,423.00	95.00	95.58	85.32
	WEIGHTED AVERAGE FOR THE YEAR			18,887.00	86.07	109.31	109.04
===== 403-34851		HMA (Gr SX) (100) (PG 64-28)		Ton	=====	=====	=====
BR071A-020		REPLACEMENT OF STRUCTURE L-22	04/18/19	1,171.79	110.00	110.00	100.00
NHPP0703-445		I-70 WESTBOUND PEAK PERIOD SH	04/25/19	53,286.00	90.00	103.33	98.00
	WEIGHTED AVERAGE FOR THE SECOND QUARTER			54,457.79	90.43	103.48	98.04
	WEIGHTED AVERAGE FOR THE YEAR			54,457.79	90.43	103.48	98.04
===== 403-34871		HMA (Gr SX) (100) (PG 76-28)		Ton	=====	=====	=====
NHPPR100-250		PACKAGE A (I-25 / I-70 / I-76	01/24/19	112.00	120.00	272.66	265.00
STAM086-075		SH96A ABRIENDO - ORMAN SAFETY	01/31/19	94.00	300.00	329.00	175.00
FBR0253-247		I25 AT VINE DRIVE BRIDGE REPL	03/07/19	5,482.00	120.00	90.88	90.00
SHE2254-090		Colfax & I-225, Colfax & Cham	03/07/19	1,559.00	120.00	138.00	175.00
SHER100-308		MIDPOINT - SIGNAL CONST PACKA	03/21/19	151.00	125.00	389.00	398.00

COLORADO DEPARTMENT OF TRANSPORTATION
 ITEM UNIT COSTS BY PROJECTS -- 2019 COST DATA

13:44 Wednesday, August 7, 2019 132

PROJECT NUMBER	ITEM NUMBER/ PROJECT LOCATION	ITEM DESCRIPTION/ PROJECT LOCATION	DATE LET	UNIT/ QUANTITY	ENGR. EST.	AVERAGE BID	AWARDED BID
===== 403-34871		HMA (Gr SX) (100) (PG 76-28)		Ton =====			
STM0242-077		US24 - 8TH ST TO WEST OF MANI	03/28/19	38,463.00	85.00	90.42	84.25
	WEIGHTED AVERAGE FOR THE FIRST QUARTER			45,861.00	91.03	92.84	89.68
SHE0701-243		I-70 EXIT 26 DDI MODIFICATION	05/16/19	138.00	400.00	308.25	300.00
	WEIGHTED AVERAGE FOR THE SECOND QUARTER			138.00	400.00	308.25	300.00
	WEIGHTED AVERAGE FOR THE YEAR			45,999.00	91.96	93.50	90.31
===== 403-40000		HMA Safety Edge		Lin Foot =====			
STA0131-070 HMA ALT		SH 13 CR 5 NORTH AND SOUTH	03/28/19	51,407.00	1.20	1.26	4.05
STA0131-070 PCCP ALT		SH 13 CR 5 NORTH AND SOUTH					
	WEIGHTED AVERAGE FOR THE FIRST QUARTER			51,407.00	1.20	1.26	4.05
	WEIGHTED AVERAGE FOR THE YEAR			51,407.00	1.20	1.26	4.05
===== 405-00100		Heating and Remixing Treatment		Sq Yard =====			
STR141A-047		SH 141 MP 120-143 MESA COUNTY	01/17/19	359,548.00	4.80	4.14	3.25
	WEIGHTED AVERAGE FOR THE FIRST QUARTER			359,548.00	4.80	4.14	3.25
	WEIGHTED AVERAGE FOR THE YEAR			359,548.00	4.80	4.14	3.25
===== 408-01100		Joint Sealant		Lin Foot =====			
NHPPR100-250		PACKAGE A (I-25 / I-70 / I-76	01/24/19	122.00	18.00	20.79	23.00
STA067A-038		SH 67 SEDALIA RESURFACING	01/31/19	130.00	20.00	25.80	25.00
	WEIGHTED AVERAGE FOR THE FIRST QUARTER			252.00	19.03	22.74	24.03
STR 141A-040		R5 YEAR 4 BRDG PREV MAINT RAM	06/20/19	113.00	30.00	63.50	100.00
	WEIGHTED AVERAGE FOR THE SECOND QUARTER			113.00	30.00	63.50	100.00
	WEIGHTED AVERAGE FOR THE YEAR			365.00	22.43	30.26	47.55

COLORADO DEPARTMENT OF TRANSPORTATION
 ITEM UNIT COSTS BY PROJECTS -- 2019 COST DATA

13:44 Wednesday, August 7, 2019 133

PROJECT NUMBER	ITEM NUMBER/ PROJECT LOCATION	ITEM DESCRIPTION/ PROJECT LOCATION	DATE LET	UNIT/ QUANTITY	ENGR. EST.	AVERAGE BID	AWARDED BID
=====	409-01015	CC Matl (Ty I)		Sq Yard	=====		
NHPP0821-107		SH 82 GLENWOOD SPRINGS TO CA	02/07/19	237,901.00	1.00	1.35	1.55
NHPP1601-076		US 160 MANCOS HILL (MP 40.000	02/21/19	762,614.00	1.20	0.88	0.80
		WEIGHTED AVERAGE FOR THE FIRST QUARTER		1,000,515.00	1.15	0.96	0.98
STRR300-236		SH 92 and SH 133	04/04/19	786,105.00	0.90	0.88	0.88
		WEIGHTED AVERAGE FOR THE SECOND QUARTER		786,105.00	0.90	0.88	0.88
		WEIGHTED AVERAGE FOR THE YEAR		1,786,620.00	1.04	0.95	0.94
=====	409-02015	CC Matl (Ty II)		Sq Yard	=====		
NHPP1601-076		US 160 MANCOS HILL (MP 40.000	02/21/19	35,501.00	1.25	1.50	1.25
		WEIGHTED AVERAGE FOR THE FIRST QUARTER		35,501.00	1.25	1.50	1.25
STRR300-236		SH 92 and SH 133	04/04/19	111,653.00	1.15	1.25	1.25
NHPP2851-012		US 285 Antonito to Estrella C	05/02/19	588,166.00	0.95	1.38	1.10
		WEIGHTED AVERAGE FOR THE SECOND QUARTER		699,819.00	0.98	1.37	1.12
		WEIGHTED AVERAGE FOR THE YEAR		735,320.00	0.99	1.38	1.13
=====	409-09000	Micro-Surfacing Seal Coat		Ton	=====		
IM0251-351		I-25 South of Pueblo MP 79.6	01/03/19	8,425.00	200.00	233.55	234.18
NHPP1601-076		US 160 MANCOS HILL (MP 40.000	02/21/19	852.00	225.00	369.67	445.00
		WEIGHTED AVERAGE FOR THE FIRST QUARTER		9,277.00	202.30	243.14	253.54
		WEIGHTED AVERAGE FOR THE YEAR		9,277.00	202.30	243.14	253.54
=====	411-03342	Asph Cem (PG 64-28)		Ton	=====		
NHPP0821-107		SH 82 GLENWOOD SPRINGS TO CA	02/07/19	1,811.00	440.00	465.00	580.00

COLORADO DEPARTMENT OF TRANSPORTATION
 ITEM UNIT COSTS BY PROJECTS -- 2019 COST DATA

13:44 Wednesday, August 7, 2019 134

PROJECT NUMBER	ITEM NUMBER/ PROJECT LOCATION	ITEM DESCRIPTION/ PROJECT LOCATION	DATE LET	UNIT/ QUANTITY	ENGR. EST.	AVERAGE BID	AWARDED BID
===== 411-03342		Asph Cem (PG 64-28)		Ton =====			
NHPP050A-033		US50 West of Delta EB Lanes R	03/14/19	1,307.52	480.00	585.00	600.00
	WEIGHTED AVERAGE FOR THE FIRST QUARTER			3,118.52	456.77	527.39	588.39
	WEIGHTED AVERAGE FOR THE YEAR			3,118.52	456.77	527.39	588.39
===== 411-03352		Asph Cem (PG 58-28)		Ton =====			
STR0132-021		SH 13-MOFFAT COUNTY-CR 3 SOUT	01/10/19	1,533.00	400.00	449.20	405.00
FBR0341-087		US 34 OVER NORTH FORK CO RIVE	01/10/19	60.00	650.00	718.83	760.40
NHPP0702-378		I-70 OFFICERS GULCH TO FRISCO	03/14/19	1,820.00	420.00	459.64	518.92
NHPP050A-033		US50 West of Delta EB Lanes R	03/14/19	616.83	380.00	428.33	430.00
	WEIGHTED AVERAGE FOR THE FIRST QUARTER			4,029.83	409.69	456.73	465.57
	WEIGHTED AVERAGE FOR THE YEAR			4,029.83	409.69	456.73	465.57
===== 411-03354		Asph Cem (PG 64-22)		Ton =====			
STR141A-047		SH 141 MP 120-143 MESA COUNTY	01/17/19	2,250.95	400.00	354.82	265.00
	WEIGHTED AVERAGE FOR THE FIRST QUARTER			2,250.95	400.00	354.82	265.00
	WEIGHTED AVERAGE FOR THE YEAR			2,250.95	400.00	354.82	265.00
===== 411-03355		Asph Cem (PG 58-34)		Ton =====			
STR0132-021		SH 13-MOFFAT COUNTY-CR 3 SOUT	01/10/19	795.00	500.00	528.20	475.00
STR0241-062		US 24 143.4 - 148	01/24/19	673.00	400.00	556.67	720.00
	WEIGHTED AVERAGE FOR THE FIRST QUARTER			1,468.00	454.16	537.79	587.32
FBR0063-057		US-6 F-09-K BRIDGE OVER CASTL	05/30/19	68.00	700.00	778.97	745.00
	WEIGHTED AVERAGE FOR THE SECOND QUARTER			68.00	700.00	778.97	745.00
	WEIGHTED AVERAGE FOR THE YEAR			1,536.00	465.04	543.14	594.30
===== 411-10216		Emul Asph (CRS-2P)		Gallon =====			
NHPP1601-076		US 160 MANCOS HILL (MP 40.000	02/21/19	315,323.00	2.40	2.07	2.00
	WEIGHTED AVERAGE FOR THE FIRST QUARTER			315,323.00	2.40	2.07	2.00

COLORADO DEPARTMENT OF TRANSPORTATION
 ITEM UNIT COSTS BY PROJECTS -- 2019 COST DATA

13:44 Wednesday, August 7, 2019 135

PROJECT NUMBER	ITEM NUMBER/ PROJECT LOCATION	ITEM DESCRIPTION/ PROJECT LOCATION	DATE LET	UNIT/ QUANTITY	ENGR. EST.	AVERAGE BID	AWARDED BID
=====	411-10216	Emul Asph (CRS-2P)		Gallon	=====	=====	=====
STRR300-236		SH 92 and SH 133	04/04/19	415,429.00	1.80	2.15	2.15
NHPP2851-012		US 285 Antonito to Estrella C	05/02/19	228,711.00	1.90	3.23	3.50
		WEIGHTED AVERAGE FOR THE SECOND QUARTER		644,140.00	1.84	2.82	2.63
		WEIGHTED AVERAGE FOR THE YEAR		959,463.00	2.02	2.47	2.42
=====	411-10217	Emulsified Asphalt (CRS-2P)		Ton	=====	=====	=====
NHPP0821-107		SH 82 GLENWOOD SPRINGS TO CA	02/07/19	508.00	440.00	460.50	521.00
		WEIGHTED AVERAGE FOR THE FIRST QUARTER		508.00	440.00	460.50	521.00
		WEIGHTED AVERAGE FOR THE YEAR		508.00	440.00	460.50	521.00
=====	411-10251	Emul Asph (CSS-1)		Gallon	=====	=====	=====
ER072A-040		PR SH72A FLOOD PERMANENT REPA	01/31/19	1,950.00	3.50	4.81	6.00
NHPP072A-041		PR SH72A FLOOD PERMANENT REPA					
		WEIGHTED AVERAGE FOR THE FIRST QUARTER		1,950.00	3.50	4.81	6.00
		WEIGHTED AVERAGE FOR THE YEAR		1,950.00	3.50	4.81	6.00
=====	411-10253	Emul Asph (CSS-1H)		Gallon	=====	=====	=====
NHPP1601-076		US 160 MANCOS HILL (MP 40.000	02/21/19	47,954.00	2.50	2.45	2.00
		WEIGHTED AVERAGE FOR THE FIRST QUARTER		47,954.00	2.50	2.45	2.00
		WEIGHTED AVERAGE FOR THE YEAR		47,954.00	2.50	2.45	2.00
=====	411-10255	Emul Asph (SS)		Gallon	=====	=====	=====
IM0251-351		I-25 South of Pueblo MP 79.6	01/03/19	44,984.00	3.00	3.11	3.78
SHER100-289		INTERSECTIONS @ SH83 & LONGS	01/03/19	1,076.00	3.45	3.18	2.25

PROJECT NUMBER	ITEM NUMBER/ PROJECT LOCATION	ITEM DESCRIPTION/ PROJECT LOCATION	DATE LET	UNIT/ QUANTITY	ENGR. EST.	AVERAGE BID	AWARDED BID
===== 411-10255		Emul Asph (SS)		Gallon			
STR0132-021		SH 13-MOFFAT COUNTY-CR 3 SOUT	01/10/19	17,589.00	2.75	2.69	2.25
FBR0341-087		US 34 OVER NORTH FORK CO RIVE	01/10/19	193.00	4.00	24.94	30.17
STR141A-047		SH 141 MP 120-143 MESA COUNTY	01/17/19	17,863.00	4.00	2.72	2.00
STR0241-062		US 24 143.4 - 148	01/24/19	5,750.00	5.00	4.92	7.00
STA067A-038		SH 67 SEDALIA RESURFACING	01/31/19	1,608.00	4.00	3.86	3.00
NHPP0821-107		SH 82 GLENWOOD SPRINGS TO CA	02/07/19	13,190.00	5.50	2.75	3.00
NHPP145A-065		SH 145 PASSING LANES AT DEEP	02/14/19	1,535.00	4.00	5.31	4.00
NHPP0741-022		SH 74: I-70 TO CR 65 RESURFAC	02/14/19	5,827.00	4.50	3.45	5.80
NHPP1601-073		US 160 PASSING LANE NORTH OF	03/07/19	3,486.00	4.00	3.93	4.85
NHPP006A-058		US 6 LOVELAND PASS - I-70 (FY	03/07/19	11,761.00	4.50	2.00	2.99
NHPP0702-378		I-70 OFFICERS GULCH TO FRISCO	03/14/19	22,991.00	4.00	2.19	3.07
NHPP050A-033		US50 West of Delta EB Lanes R	03/14/19	16,614.00	4.00	2.75	2.50
NHPP0503-087		US 50 PASSING LANES EAST OF S	03/21/19	3,939.00	4.00	2.50	1.00
NHPP2254-089		I-225 RESURFACING FROM I-25 T	03/21/19	17,414.00	4.50	2.91	3.50
STM0242-077		US24 - 8TH ST TO WEST OF MANI	03/28/19	14,140.00	3.00	2.83	3.00
STA0131-070 HMA ALT		SH 13 CR 5 NORTH AND SOUTH	03/28/19	15,482.00	3.00	3.51	7.25
STA0131-070 PCCP ALT		SH 13 CR 5 NORTH AND SOUTH					
		WEIGHTED AVERAGE FOR THE FIRST QUARTER		215,442.00	3.75	2.97	3.26
NHPP030A-035		US 285/SH30	04/04/19	10,762.10	3.50	3.00	3.00
BR071A-020		REPLACEMENT OF STRUCTURE L-22	04/18/19	360.00	3.60	7.04	7.80
NHPP0703-445		I-70 WESTBOUND PEAK PERIOD SH	04/25/19	40,895.00	4.00	3.11	3.00
NHPP2851-012		US 285 Antonito to Estrella C	05/02/19	38,282.00	2.15	3.08	3.50
FSA0703-454		EB I-70 AUX LANE WARD TO KIPL	05/16/19	1,961.00	5.00	6.45	3.10
SHE0701-243		I-70 EXIT 26 DDI MODIFICATION	05/16/19	84.00	10.00	9.19	6.00
FBR0063-057		US-6 F-09-K BRIDGE OVER CASTL	05/30/19	266.00	4.00	17.12	16.35
ER145A-081		SH 145 MP 21 EMERGENCY ROCKFA	06/07/19	150.00	4.00	13.04	12.00
NHPP0703-442		I-70 SILVERPLUME SOUNDWALL AN	06/13/19	44.00	4.50	5.08	5.70
NHPP030A-036		SH 30 & TOWER RD IMPROVEMENTS	06/13/19	1,201.00	5.50	2.50	2.50
		WEIGHTED AVERAGE FOR THE SECOND QUARTER		94,005.10	3.23	3.23	3.27
		WEIGHTED AVERAGE FOR THE YEAR		309,447.10	3.59	3.04	3.27
===== 411-90010		Asph Rejuvenating Agent		Gallon			
STR141A-047		SH 141 MP 120-143 MESA COUNTY	01/17/19	22,651.00	3.00	3.33	3.30
		WEIGHTED AVERAGE FOR THE FIRST QUARTER		22,651.00	3.00	3.33	3.30
		WEIGHTED AVERAGE FOR THE YEAR		22,651.00	3.00	3.33	3.30
===== 412-00600		Conc Pvmt (6 In)		Sq Yard			
STR0241-062		US 24 143.4 - 148	01/24/19	471.00	80.00	104.00	95.00

COLORADO DEPARTMENT OF TRANSPORTATION
 ITEM UNIT COSTS BY PROJECTS -- 2019 COST DATA

13:44 Wednesday, August 7, 2019 137

PROJECT NUMBER	ITEM NUMBER/ PROJECT LOCATION	ITEM DESCRIPTION/ PROJECT LOCATION	DATE LET	UNIT/ QUANTITY	ENGR. EST.	AVERAGE BID	AWARDED BID
===== 412-00600	Conc Pvmt (6 In)			Sq Yard	=====	=====	=====
STAM086-075	SH96A ABRIENDO - ORMAN SAFETY		01/31/19	150.00	200.00	127.75	88.25
NH2871-035	US 287 PASSING LANES SOUTH OF		02/07/19	693.00	80.00	70.83	80.83
	WEIGHTED AVERAGE FOR THE FIRST QUARTER			1,314.00	93.70	86.47	86.76
NHPP0703-445	I-70 WESTBOUND PEAK PERIOD SH		04/25/19	48.00	150.00	98.27	107.00
C2571-013	SH257 & 392:WINDSOR CURB RAMP		05/02/19	160.00	100.00	126.00	80.00
MTCE0641-103	MTCE R3 FY20 SH 64 RANGELY PE		05/02/19	112.00	85.00	152.50	95.00
FSA2873-190	US 287 AND FOOTHILLS PARKWAY		05/02/19	13.00	120.00	156.00	165.00
CR300-248	CRAIG RESIDENCY ADA RAMPS		05/16/19	240.00	55.00	145.00	85.00
STMC430-020	ADA RAMPS DIVIDE ESB		05/23/19	121.00	100.00	104.57	104.57
	WEIGHTED AVERAGE FOR THE SECOND QUARTER			694.00	85.85	134.05	91.89
	WEIGHTED AVERAGE FOR THE YEAR			2,008.00	90.99	99.32	88.53
===== 412-00605	Conc Pvmt (6 In) (Fast Track)			Sq Yard	=====	=====	=====
STR0241-062	US 24 143.4 - 148		01/24/19	1,412.00	120.00	104.83	94.00
	WEIGHTED AVERAGE FOR THE FIRST QUARTER			1,412.00	120.00	104.83	94.00
	WEIGHTED AVERAGE FOR THE YEAR			1,412.00	120.00	104.83	94.00
===== 412-00800	Conc Pvmt (8 In)			Sq Yard	=====	=====	=====
NHPP0821-107	SH 82 GLENWOOD SPRINGS TO CA		02/07/19	87.00	220.00	133.50	142.00
SHE 0252-481	I-25 RAMP METER INSTALLATION		03/21/19	525.00	135.00	201.83	135.00
	WEIGHTED AVERAGE FOR THE FIRST QUARTER			612.00	147.08	195.04	136.00
FSA0703-454	EB I-70 AUX LANE WARD TO KIPL		05/16/19	9,791.00	70.00	84.17	67.50
	WEIGHTED AVERAGE FOR THE SECOND QUARTER			9,791.00	70.00	84.17	67.50
	WEIGHTED AVERAGE FOR THE YEAR			10,403.00	74.53	90.40	71.53
===== 412-00900	Conc Pvmt (9 In)			Sq Yard	=====	=====	=====
NHPP0701-241	I-70 TRUCK PARKING GARFIELD C		01/17/19	23,479.00	62.00	87.80	76.00

COLORADO DEPARTMENT OF TRANSPORTATION
 ITEM UNIT COSTS BY PROJECTS -- 2019 COST DATA

13:44 Wednesday, August 7, 2019 138

PROJECT NUMBER	ITEM NUMBER/ PROJECT LOCATION	ITEM DESCRIPTION/ PROJECT LOCATION	DATE LET	UNIT/ QUANTITY	ENGR. EST.	AVERAGE BID	AWARDED BID
===== 412-00900		Conc Pvmt (9 In)		Sq Yard	=====	=====	=====
STA0131-070 HMA ALT		SH 13 CR 5 NORTH AND SOUTH	03/28/19	142,064.00	48.00	54.04	48.86
STA0131-070 PCCP ALT		SH 13 CR 5 NORTH AND SOUTH					
	WEIGHTED AVERAGE FOR THE FIRST QUARTER			165,543.00	49.99	61.33	52.71
SHE0701-243		I-70 EXIT 26 DDI MODIFICATION	05/16/19	1,506.00	71.00	98.00	80.00
	WEIGHTED AVERAGE FOR THE SECOND QUARTER			1,506.00	71.00	98.00	80.00
	WEIGHTED AVERAGE FOR THE YEAR			167,049.00	50.18	61.73	52.96
===== 412-00950		Conc Pvmt (9-1/2 In)		Sq Yard	=====	=====	=====
NHPP2254-089		I-225 RESURFACING FROM I-25 T	03/21/19	200.00	100.00	258.88	290.00
	WEIGHTED AVERAGE FOR THE FIRST QUARTER			200.00	100.00	258.88	290.00
	WEIGHTED AVERAGE FOR THE YEAR			200.00	100.00	258.88	290.00
===== 412-00952		Conc Pvmt (9 1/2 In) (Fast Track)		Sq Yard	=====	=====	=====
SHER100-289		INTERSECTIONS @ SH83 & LONGS	01/03/19	49.00	200.00	145.80	130.00
	WEIGHTED AVERAGE FOR THE FIRST QUARTER			49.00	200.00	145.80	130.00
NHPP0703-445		I-70 WESTBOUND PEAK PERIOD SH	04/25/19	3,223.00	170.00	104.46	93.00
	WEIGHTED AVERAGE FOR THE SECOND QUARTER			3,223.00	170.00	104.46	93.00
	WEIGHTED AVERAGE FOR THE YEAR			3,272.00	170.45	105.48	93.55
===== 412-01000		Conc Pvmt (10 In)		Sq Yard	=====	=====	=====
C R100-315		R1 ADA CURB RAMPS - PH 5	03/07/19	29.00	140.00	200.00	200.00
SHE 0252-481		I-25 RAMP METER INSTALLATION	03/21/19	1,236.00	150.00	210.00	140.00
	WEIGHTED AVERAGE FOR THE FIRST QUARTER			1,265.00	149.77	209.85	141.38

COLORADO DEPARTMENT OF TRANSPORTATION
 ITEM UNIT COSTS BY PROJECTS -- 2019 COST DATA

13:44 Wednesday, August 7, 2019 139

PROJECT NUMBER	ITEM NUMBER/ PROJECT LOCATION	ITEM DESCRIPTION/ PROJECT LOCATION	DATE LET	UNIT/ QUANTITY	ENGR. EST.	AVERAGE BID	AWARDED BID
===== 412-01000		Conc Pvmt (10 In)		Sq Yard	=====		
NHPP030A-035		US 285/SH30	04/04/19	46.00	100.00	500.00	500.00
		WEIGHTED AVERAGE FOR THE SECOND QUARTER		46.00	100.00	500.00	500.00
		WEIGHTED AVERAGE FOR THE YEAR		1,311.00	148.02	213.35	153.96
===== 412-01020		Conc Pvmt (10 In) (Fast Track)		Sq Yard	=====		
STR 141A-040		R5 YEAR 4 BRDG PREV MAINT RAM	06/20/19	628.00	90.00	267.00	200.00
		WEIGHTED AVERAGE FOR THE SECOND QUARTER		628.00	90.00	267.00	200.00
		WEIGHTED AVERAGE FOR THE YEAR		628.00	90.00	267.00	200.00
===== 412-01050		Conc Pvmt (10-1/2 In)		Sq Yard	=====		
FSA0252-468		I-25 AND PLUM CREEK IMPROVEME	04/18/19	1,118.00	100.00	158.75	177.00
		WEIGHTED AVERAGE FOR THE SECOND QUARTER		1,118.00	100.00	158.75	177.00
		WEIGHTED AVERAGE FOR THE YEAR		1,118.00	100.00	158.75	177.00
===== 412-01100		Conc Pvmt (11 In)		Sq Yard	=====		
NH2871-035		US 287 PASSING LANES SOUTH OF	02/07/19	26,014.00	55.00	74.35	68.97
		WEIGHTED AVERAGE FOR THE FIRST QUARTER		26,014.00	55.00	74.35	68.97
		WEIGHTED AVERAGE FOR THE YEAR		26,014.00	55.00	74.35	68.97
===== 412-01120		Conc Pvmt (11 In) (Fast Track)		Sq Yard	=====		
NHPP030A-035		US 285/SH30	04/04/19	84.30	200.00	575.00	575.00
		WEIGHTED AVERAGE FOR THE SECOND QUARTER		84.30	200.00	575.00	575.00
		WEIGHTED AVERAGE FOR THE YEAR		84.30	200.00	575.00	575.00

COLORADO DEPARTMENT OF TRANSPORTATION
 ITEM UNIT COSTS BY PROJECTS -- 2019 COST DATA

13:44 Wednesday, August 7, 2019 140

PROJECT NUMBER	ITEM NUMBER/ PROJECT LOCATION	ITEM DESCRIPTION/ PROJECT LOCATION	DATE LET	UNIT/ QUANTITY	ENGR. EST.	AVERAGE BID	AWARDED BID
=====	412-01255	Conc Pvmt (12 In) (Spec)		Sq Yard	=====		
NHPPR100-250		PACKAGE A (I-25 / I-70 / I-76	01/24/19	160.00	600.00	472.24	207.00
		WEIGHTED AVERAGE FOR THE FIRST QUARTER		160.00	600.00	472.24	207.00
NHPP030A-035		US 285/SH30	04/04/19	69.00	750.00	350.00	350.00
		WEIGHTED AVERAGE FOR THE SECOND QUARTER		69.00	750.00	350.00	350.00
		WEIGHTED AVERAGE FOR THE YEAR		229.00	645.20	462.53	250.09
=====	412-02000	Conc Safety Edge		Lin Foot	=====		
NH2871-035		US 287 PASSING LANES SOUTH OF	02/07/19	12,011.00	5.00	4.58	3.82
STA0131-070 HMA ALT		SH 13 CR 5 NORTH AND SOUTH	03/28/19	49,249.00	2.00	3.80	3.45
STA0131-070 PCCP ALT		SH 13 CR 5 NORTH AND SOUTH					
		WEIGHTED AVERAGE FOR THE FIRST QUARTER		61,260.00	2.59	3.99	3.52
		WEIGHTED AVERAGE FOR THE YEAR		61,260.00	2.59	3.99	3.52
=====	412-05100	Poly Slab Jacking		Pound	=====		
NHPPR100-250		PACKAGE A (I-25 / I-70 / I-76	01/24/19	11,583.00	8.00	6.67	6.00
		WEIGHTED AVERAGE FOR THE FIRST QUARTER		11,583.00	8.00	6.67	6.00
		WEIGHTED AVERAGE FOR THE YEAR		11,583.00	8.00	6.67	6.00
=====	412-15000	Routing and Sealing Cracks		Lin Foot	=====		
NHPPR100-250		PACKAGE A (I-25 / I-70 / I-76	01/24/19	160.00	20.00	39.67	15.00
		WEIGHTED AVERAGE FOR THE FIRST QUARTER		160.00	20.00	39.67	15.00
		WEIGHTED AVERAGE FOR THE YEAR		160.00	20.00	39.67	15.00
=====	420-00000	Geomembrane		Sq Yard	=====		
FBR0341-087		US 34 OVER NORTH FORK CO RIVE	01/10/19	170.00	25.00	10.87	14.69

COLORADO DEPARTMENT OF TRANSPORTATION
ITEM UNIT COSTS BY PROJECTS -- 2019 COST DATA

13:44 Wednesday, August 7, 2019 141

PROJECT NUMBER	ITEM NUMBER/ PROJECT LOCATION	ITEM DESCRIPTION/ PROJECT LOCATION	DATE LET	UNIT/ QUANTITY	ENGR. EST.	AVERAGE BID	AWARDED BID
=====	420-00000	Geomembrane		Sq Yard	=====	=====	=====
NHPP145A-065		SH 145 PASSING LANES AT DEEP	02/14/19	124.00	25.00	28.68	11.00
NHPP1601-073		US 160 PASSING LANE NORTH OF	03/07/19	152.00	12.00	10.50	15.00
		WEIGHTED AVERAGE FOR THE FIRST QUARTER		446.00	20.57	16.49	13.77
NHPP0703-445		I-70 WESTBOUND PEAK PERIOD SH	04/25/19	19,250.00	12.00	12.04	12.00
FBR0063-057		US-6 F-09-K BRIDGE OVER CASTL	05/30/19	1,534.00	20.00	10.91	11.30
		WEIGHTED AVERAGE FOR THE SECOND QUARTER		20,784.00	12.59	11.99	11.95
		WEIGHTED AVERAGE FOR THE YEAR		21,230.00	12.76	12.13	11.99
=====	420-00102	Geotextile (Er Cont) (CL 1)		Sq Yard	=====	=====	=====
STAR200-242		R2 NORTH PROGRAM WALL REPAIRS	01/03/19	30.00	4.00	6.06	6.50
FBR0341-087		US 34 OVER NORTH FORK CO RIVE	01/10/19	181.00	4.00	7.02	9.54
NHPP0821-107		SH 82 GLENWOOD SPRINGS TO CA	02/07/19	97.00	6.00	12.43	16.85
FBR0253-247		I25 AT VINE DRIVE BRIDGE REPL	03/07/19	762.00	6.00	3.19	2.50
		WEIGHTED AVERAGE FOR THE FIRST QUARTER		1,070.00	5.61	3.82	5.10
NHPP0703-442		I-70 SILVERPLUME SOUNDWALL AN	06/13/19	120.00	15.00	15.79	5.70
STR 141A-040		R5 YEAR 4 BRDG PREV MAINT RAM	06/20/19	60.00	8.00	12.00	5.00
		WEIGHTED AVERAGE FOR THE SECOND QUARTER		180.00	12.67	15.37	5.47
		WEIGHTED AVERAGE FOR THE YEAR		1,250.00	6.62	4.97	5.16
=====	420-00112	Geotextile (Drain) (CL 1)		Sq Yard	=====	=====	=====
FBR0341-087		US 34 OVER NORTH FORK CO RIVE	01/10/19	781.00	3.00	3.80	3.77
ER072A-040		PR SH72A FLOOD PERMANENT REPA	01/31/19	245.00	80.00	10.58	3.00
NHPP072A-041		PR SH72A FLOOD PERMANENT REPA					
NHPP1601-073		US 160 PASSING LANE NORTH OF	03/07/19	1,283.00	4.50	4.18	3.35
NHPP0503-087		US 50 PASSING LANES EAST OF S	03/21/19	230.00	6.00	10.00	3.00
STM0242-077		US24 - 8TH ST TO WEST OF MANI	03/28/19	1,308.00	3.50	3.50	3.00
		WEIGHTED AVERAGE FOR THE FIRST QUARTER		3,847.00	8.75	5.35	3.27
		WEIGHTED AVERAGE FOR THE YEAR		3,847.00	8.75	5.35	3.27

COLORADO DEPARTMENT OF TRANSPORTATION
 ITEM UNIT COSTS BY PROJECTS -- 2019 COST DATA

13:44 Wednesday, August 7, 2019 142

PROJECT NUMBER	ITEM NUMBER/ PROJECT LOCATION	ITEM DESCRIPTION/ PROJECT LOCATION	DATE LET	UNIT/ QUANTITY	ENGR. EST.	AVERAGE BID	AWARDED BID
=====	420-00113	Geotextile (Drain) (CL 2)		Sq Yard	=====		
ER119A-065		PR SH 119A BOULDER CANYON	01/03/19	22,329.00	2.41	2.67	1.80
STA119A-069		SH 119: NEDERLAND - EAST					
NHPP0503-087		US 50 PASSING LANES EAST OF S	03/21/19	116.00	6.00	14.50	3.00
		WEIGHTED AVERAGE FOR THE FIRST QUARTER		22,445.00	2.43	2.68	1.81
NHPP0703-445		I-70 WESTBOUND PEAK PERIOD SH	04/25/19	641.00	2.00	3.78	4.00
		WEIGHTED AVERAGE FOR THE SECOND QUARTER		641.00	2.00	3.78	4.00
		WEIGHTED AVERAGE FOR THE YEAR		23,086.00	2.41	2.70	1.87
=====	420-00114	Geotextile (Drain) (CL 3)		Sq Yard	=====		
ER119A-065		PR SH 119A BOULDER CANYON	01/03/19	35.00	7.00	13.58	25.00
STA119A-069		SH 119: NEDERLAND - EAST					
		WEIGHTED AVERAGE FOR THE FIRST QUARTER		35.00	7.00	13.58	25.00
		WEIGHTED AVERAGE FOR THE YEAR		35.00	7.00	13.58	25.00
=====	420-00132	Geotextile (Separator) (CL 1)		Sq Yard	=====		
STR0132-021		SH 13-MOFFAT COUNTY-CR 3 SOUT	01/10/19	20,192.00	2.50	1.69	1.95
STR0241-062		US 24 143.4 - 148	01/24/19	23.00	20.00	30.67	10.00
STA0131-070 HMA ALT		SH 13 CR 5 NORTH AND SOUTH	03/28/19	68,000.00	2.00	1.80	1.50
STA0131-070 PCCP ALT		SH 13 CR 5 NORTH AND SOUTH					
		WEIGHTED AVERAGE FOR THE FIRST QUARTER		88,215.00	2.12	1.77	1.67
		WEIGHTED AVERAGE FOR THE YEAR		88,215.00	2.12	1.77	1.67
=====	420-00510	Geotextile (Cr Reduc) (H D)		Sq Yard	=====		
ER119A-065		PR SH 119A BOULDER CANYON	01/03/19	580.00	20.00	12.89	18.00
STA119A-069		SH 119: NEDERLAND - EAST					
		WEIGHTED AVERAGE FOR THE FIRST QUARTER		580.00	20.00	12.89	18.00

COLORADO DEPARTMENT OF TRANSPORTATION
 ITEM UNIT COSTS BY PROJECTS -- 2019 COST DATA

13:44 Wednesday, August 7, 2019 143

PROJECT NUMBER	ITEM NUMBER/ PROJECT LOCATION	ITEM DESCRIPTION/ PROJECT LOCATION	DATE LET	UNIT/ QUANTITY	ENGR. EST.	AVERAGE BID	AWARDED BID
=====	420-00510	Geotextile (Cr Reduc) (H D)		Sq Yard	=====		
STR 141A-040		R5 YEAR 4 BRDG PREV MAINT RAM	06/20/19	285.00	20.00	12.50	10.00
		WEIGHTED AVERAGE FOR THE SECOND QUARTER		285.00	20.00	12.50	10.00
		WEIGHTED AVERAGE FOR THE YEAR		865.00	20.00	12.84	15.36
=====	420-00526	Cellular Geogrid		Sq Yard	=====		
NHPP050A-033		US50 West of Delta EB Lanes R	03/14/19	2,000.00	45.00	4.13	2.25
		WEIGHTED AVERAGE FOR THE FIRST QUARTER		2,000.00	45.00	4.13	2.25
		WEIGHTED AVERAGE FOR THE YEAR		2,000.00	45.00	4.13	2.25
=====	502-00100	Drill Hole Fac Pile Driving		Lin Foot	=====		
FBR0341-087		US 34 OVER NORTH FORK CO RIVE	01/10/19	444.00	350.00	604.86	611.87
		WEIGHTED AVERAGE FOR THE FIRST QUARTER		444.00	350.00	604.86	611.87
		WEIGHTED AVERAGE FOR THE YEAR		444.00	350.00	604.86	611.87
=====	502-00460	Pile Tip		Each	=====		
FBR0341-087		US 34 OVER NORTH FORK CO RIVE	01/10/19	16.00	200.00	214.03	240.75
FBR0253-247		I25 AT VINE DRIVE BRIDGE REPL	03/07/19	18.00	200.00	183.47	215.00
		WEIGHTED AVERAGE FOR THE FIRST QUARTER		34.00	200.00	193.45	227.12
BR071A-020		REPLACEMENT OF STRUCTURE L-22	04/18/19	12.00	150.00	156.67	100.00
NHPP0703-442		I-70 SILVERPLUME SOUNDWALL AN	06/13/19	82.00	200.00	186.06	159.00
		WEIGHTED AVERAGE FOR THE SECOND QUARTER		94.00	193.62	184.53	151.47
		WEIGHTED AVERAGE FOR THE YEAR		128.00	195.31	187.19	171.56

COLORADO DEPARTMENT OF TRANSPORTATION
 ITEM UNIT COSTS BY PROJECTS -- 2019 COST DATA

13:44 Wednesday, August 7, 2019 144

PROJECT NUMBER	ITEM NUMBER/ PROJECT LOCATION	ITEM DESCRIPTION/ PROJECT LOCATION	DATE LET	UNIT/ QUANTITY	ENGR. EST.	AVERAGE BID	AWARDED BID
=====	502-00500	CJP Splice		Each	=====		
FBR0253-247		I25 AT VINE DRIVE BRIDGE REPL	03/07/19	36.00	725.00	450.66	1.00
		WEIGHTED AVERAGE FOR THE FIRST QUARTER		36.00	725.00	450.66	1.00
BR071A-020		REPLACEMENT OF STRUCTURE L-22	04/18/19	12.00	200.00	789.00	1.00
		WEIGHTED AVERAGE FOR THE SECOND QUARTER		12.00	200.00	789.00	1.00
		WEIGHTED AVERAGE FOR THE YEAR		48.00	593.75	478.86	1.00
=====	502-02010	Dynamic Pile Test		Each	=====		
BR071A-020		REPLACEMENT OF STRUCTURE L-22	04/18/19	2.00	7500.00	3233.33	3500.00
		WEIGHTED AVERAGE FOR THE SECOND QUARTER		2.00	7500.00	3233.33	3500.00
		WEIGHTED AVERAGE FOR THE YEAR		2.00	7500.00	3233.33	3500.00
=====	502-11274	Steel Pile (HP 12x74)		Lin Foot	=====		
FBR0253-247		I25 AT VINE DRIVE BRIDGE REPL	03/07/19	977.00	75.00	86.83	95.00
STM0242-077		US24 - 8TH ST TO WEST OF MANI	03/28/19	213.00	100.00	298.33	225.00
		WEIGHTED AVERAGE FOR THE FIRST QUARTER		1,190.00	79.47	98.70	118.27
BR071A-020		REPLACEMENT OF STRUCTURE L-22	04/18/19	498.00	120.00	126.33	90.00
		WEIGHTED AVERAGE FOR THE SECOND QUARTER		498.00	120.00	126.33	90.00
		WEIGHTED AVERAGE FOR THE YEAR		1,688.00	91.43	101.91	109.93
=====	502-11489	Steel Pile (HP 14x89)		Lin Foot	=====		
FBR0341-087		US 34 OVER NORTH FORK CO RIVE	01/10/19	492.00	100.00	114.32	76.20
		WEIGHTED AVERAGE FOR THE FIRST QUARTER		492.00	100.00	114.32	76.20
		WEIGHTED AVERAGE FOR THE YEAR		492.00	100.00	114.32	76.20

COLORADO DEPARTMENT OF TRANSPORTATION
ITEM UNIT COSTS BY PROJECTS -- 2019 COST DATA

13:44 Wednesday, August 7, 2019 145

PROJECT NUMBER	ITEM NUMBER/ PROJECT LOCATION	ITEM DESCRIPTION/ PROJECT LOCATION	DATE LET	UNIT/ QUANTITY	ENGR. EST.	AVERAGE BID	AWARDED BID
=====	502-14102	Steel Pile (HP 14x102)		Lin Foot	=====		
NHPP0703-442		I-70 SILVERPLUME SOUNDWALL AN	06/13/19	2,214.00	80.00	106.72	135.00
		WEIGHTED AVERAGE FOR THE SECOND QUARTER		2,214.00	80.00	106.72	135.00
		WEIGHTED AVERAGE FOR THE YEAR		2,214.00	80.00	106.72	135.00
=====	503-00018	Drilled Shaft (18 In)		Lin Foot	=====		
STAM086-075		SH96A ABRIENDO - ORMAN SAFETY	01/31/19	70.00	150.00	224.00	162.00
ITSSW01-638		ETHERNET PHASE III (PRIMARYLY	02/07/19	20.00	400.00	253.00	400.00
SHER100-284		FY19 NORTH SIGNAL PKG	02/21/19	5.00	150.00	211.00	210.00
SHE 0252-481		I-25 RAMP METER INSTALLATION	03/21/19	105.00	250.00	226.42	290.00
SHER100-308		MIDPOINT - SIGNAL CONST PACKA	03/21/19	35.00	145.00	180.00	145.00
NHPP2254-089		I-225 RESURFACING FROM I-25 T	03/21/19	8.00	165.00	284.26	230.00
STM0242-077		US24 - 8TH ST TO WEST OF MANI	03/28/19	10.00	225.00	328.33	295.00
		WEIGHTED AVERAGE FOR THE FIRST QUARTER		253.00	214.01	228.58	239.94
FSA0252-468		I-25 AND PLUM CREEK IMPROVEME	04/18/19	10.00	250.00	216.50	188.00
IM0252-456		I-25 COLORADO SPRINGS RAMP ME	05/16/19	63.00	200.00	316.33	384.00
SHE0701-243		I-70 EXIT 26 DDI MODIFICATION	05/16/19	4.00	225.00	280.00	250.00
		WEIGHTED AVERAGE FOR THE SECOND QUARTER		77.00	207.79	297.66	351.58
		WEIGHTED AVERAGE FOR THE YEAR		330.00	212.56	246.41	265.99
=====	503-00024	Drilled Shaft (24 In)		Lin Foot	=====		
ITSSW01-638		ETHERNET PHASE III (PRIMARYLY	02/07/19	72.00	450.00	390.00	500.00
SHER100-308		MIDPOINT - SIGNAL CONST PACKA	03/21/19	7.00	200.00	257.50	235.00
		WEIGHTED AVERAGE FOR THE FIRST QUARTER		79.00	427.85	378.26	476.52
NHPP0703-445		I-70 WESTBOUND PEAK PERIOD SH	04/25/19	1,216.00	300.00	570.14	510.00
IM0252-456		I-25 COLORADO SPRINGS RAMP ME	05/16/19	121.00	350.00	441.00	418.00
STR200-257		ROAD CLOSURE GATES ON VARIOUS	05/30/19	56.00	500.00	194.50	122.00
		WEIGHTED AVERAGE FOR THE SECOND QUARTER		1,393.00	312.38	548.56	486.41
		WEIGHTED AVERAGE FOR THE YEAR		1,472.00	318.58	542.28	485.88

COLORADO DEPARTMENT OF TRANSPORTATION
ITEM UNIT COSTS BY PROJECTS -- 2019 COST DATA

13:44 Wednesday, August 7, 2019 146

PROJECT NUMBER	ITEM NUMBER/ PROJECT LOCATION	ITEM DESCRIPTION/ PROJECT LOCATION	DATE LET	UNIT/ QUANTITY	ENGR. EST.	AVERAGE BID	AWARDED BID
=====	503-00030	Drilled Shaft (30 In)		Lin Foot	=====		
SHE2254-090		Colfax & I-225, Colfax & Cham	03/07/19	24.00	250.00	322.50	365.00
	WEIGHTED AVERAGE FOR THE FIRST QUARTER			24.00	250.00	322.50	365.00
	WEIGHTED AVERAGE FOR THE YEAR			24.00	250.00	322.50	365.00
=====	503-00036	Drilled Shaft (36 In)		Lin Foot	=====		
SHER100-289		INTERSECTIONS @ SH83 & LONGS	01/03/19	57.00	300.00	330.80	315.00
STAM086-075		SH96A ABRIENDO - ORMAN SAFETY	01/31/19	209.00	600.00	508.33	475.00
ITSSW01-638		ETHERNET PHASE III (PRIMARILY	02/07/19	90.00	500.00	491.50	600.00
NHPP070A-028		FALL RIVER ROAD BRIDGE	02/21/19	576.00	350.00	827.04	600.00
SHER100-284		FY19 NORTH SIGNAL PKG	02/21/19	133.00	350.00	346.67	285.00
SHE2254-090		Colfax & I-225, Colfax & Cham	03/07/19	48.00	350.00	330.00	375.00
SHE 0252-481		I-25 RAMP METER INSTALLATION	03/21/19	76.00	450.00	425.00	500.00
SHER100-308		MIDPOINT - SIGNAL CONST PACKA	03/21/19	342.00	350.00	437.50	385.00
NHPP2254-089		I-225 RESURFACING FROM I-25 T	03/21/19	16.00	350.00	420.87	290.00
STM0242-077		US24 - 8TH ST TO WEST OF MANI	03/28/19	15.00	950.00	468.33	395.00
	WEIGHTED AVERAGE FOR THE FIRST QUARTER			1,562.00	400.90	637.93	482.06
FSA0252-468		I-25 AND PLUM CREEK IMPROVEME	04/18/19	53.00	500.00	376.75	413.00
NHPP0703-445		I-70 WESTBOUND PEAK PERIOD SH	04/25/19	36.00	400.00	993.74	900.00
FSA2873-190		US 287 AND FOOTHILLS PARKWAY	05/02/19	57.00	400.00	417.50	485.00
IM0252-456		I-25 COLORADO SPRINGS RAMP ME	05/16/19	38.00	500.00	541.00	473.00
	WEIGHTED AVERAGE FOR THE SECOND QUARTER			184.00	449.46	540.99	542.98
	WEIGHTED AVERAGE FOR THE YEAR			1,746.00	406.01	629.11	488.48
=====	503-00042	Drilled Shaft (42 In)		Lin Foot	=====		
ITSSW01-638		ETHERNET PHASE III (PRIMARILY	02/07/19	42.00	600.00	645.00	900.00
SHE2254-090		Colfax & I-225, Colfax & Cham	03/07/19	152.00	550.00	382.50	400.00
STM0242-077		US24 - 8TH ST TO WEST OF MANI	03/28/19	17.00	525.00	498.33	425.00
	WEIGHTED AVERAGE FOR THE FIRST QUARTER			211.00	557.94	446.18	501.54
FSA0703-454		EB I-70 AUX LANE WARD TO KIPL	05/16/19	18.00	650.00	629.51	300.00
	WEIGHTED AVERAGE FOR THE SECOND QUARTER			18.00	650.00	629.51	300.00
	WEIGHTED AVERAGE FOR THE YEAR			229.00	565.17	466.27	485.70

COLORADO DEPARTMENT OF TRANSPORTATION
ITEM UNIT COSTS BY PROJECTS -- 2019 COST DATA

13:44 Wednesday, August 7, 2019 147

PROJECT NUMBER	ITEM NUMBER/ PROJECT LOCATION	ITEM DESCRIPTION/ PROJECT LOCATION	DATE LET	UNIT/ QUANTITY	ENGR. EST.	AVERAGE BID	AWARDED BID
===== 503-00048		Drilled Shaft (48 In)		Lin Foot	=====		
STAM086-075		SH96A ABRIENDO - ORMAN SAFETY	01/31/19	21.00	800.00	576.67	525.00
ITSSW01-638		ETHERNET PHASE III (PRIMARYLY	02/07/19	120.00	700.00	722.50	1000.00
SHER100-308		MIDPOINT - SIGNAL CONST PACKA	03/21/19	21.00	540.00	542.50	495.00
STM0242-077		US24 - 8TH ST TO WEST OF MANI	03/28/19	21.00	560.00	561.67	475.00
		WEIGHTED AVERAGE FOR THE FIRST QUARTER		183.00	677.05	656.62	827.30
NHPP0703-445		I-70 WESTBOUND PEAK PERIOD SH	04/25/19	472.00	500.00	1165.83	1150.00
FSA2873-190		US 287 AND FOOTHILLS PARKWAY	05/02/19	21.00	550.00	590.00	610.00
		WEIGHTED AVERAGE FOR THE SECOND QUARTER		493.00	502.13	1149.24	1127.00
		WEIGHTED AVERAGE FOR THE YEAR		676.00	549.48	1041.53	1045.87
===== 503-00054		Drilled Shaft (54 In)		Lin Foot	=====		
SHER100-289		INTERSECTIONS @ SH83 & LONGS	01/03/19	21.00	650.00	643.00	610.00
SHER100-284		FY19 NORTH SIGNAL PKG	02/21/19	84.00	650.00	509.33	500.00
SHER100-308		MIDPOINT - SIGNAL CONST PACKA	03/21/19	42.00	550.00	592.50	585.00
STM0242-077		US24 - 8TH ST TO WEST OF MANI	03/28/19	21.00	700.00	618.33	535.00
		WEIGHTED AVERAGE FOR THE FIRST QUARTER		168.00	631.25	564.67	539.38
FSA0252-468		I-25 AND PLUM CREEK IMPROVEME	04/18/19	49.00	850.00	649.75	601.00
NHPP0703-445		I-70 WESTBOUND PEAK PERIOD SH	04/25/19	45.00	750.00	1501.33	1526.00
SHE0701-243		I-70 EXIT 26 DDI MODIFICATION	05/16/19	48.00	700.00	733.25	1260.00
		WEIGHTED AVERAGE FOR THE SECOND QUARTER		142.00	767.61	900.22	1116.89
		WEIGHTED AVERAGE FOR THE YEAR		310.00	693.71	735.55	803.92
===== 503-00060		Drilled Shaft (60 In)		Lin Foot	=====		
FBR0253-247		I25 AT VINE DRIVE BRIDGE REPL	03/07/19	143.00	900.00	964.80	1050.00
		WEIGHTED AVERAGE FOR THE FIRST QUARTER		143.00	900.00	964.80	1050.00
		WEIGHTED AVERAGE FOR THE YEAR		143.00	900.00	964.80	1050.00

COLORADO DEPARTMENT OF TRANSPORTATION
 ITEM UNIT COSTS BY PROJECTS -- 2019 COST DATA

13:44 Wednesday, August 7, 2019 148

PROJECT NUMBER	ITEM NUMBER/ PROJECT LOCATION	ITEM DESCRIPTION/ PROJECT LOCATION	DATE LET	UNIT/ QUANTITY	ENGR. EST.	AVERAGE BID	AWARDED BID
=====	503-00310	CSL Testing		Each	=====	=====	=====
FBR0253-247		I25 AT VINE DRIVE BRIDGE REPL	03/07/19	3.00	1950.00	2730.17	1100.00
	WEIGHTED AVERAGE FOR THE FIRST QUARTER			3.00	1950.00	2730.17	1100.00
	WEIGHTED AVERAGE FOR THE YEAR			3.00	1950.00	2730.17	1100.00
=====	504-03411	Retaining Wall (Boulder)		Sq Foot	=====	=====	=====
NHPP145A-065		SH 145 PASSING LANES AT DEEP	02/14/19	7,645.00	40.00	38.40	19.00
	WEIGHTED AVERAGE FOR THE FIRST QUARTER			7,645.00	40.00	38.40	19.00
	WEIGHTED AVERAGE FOR THE YEAR			7,645.00	40.00	38.40	19.00
=====	504-04410	Block Facing		Sq Foot	=====	=====	=====
FBR0341-087		US 34 OVER NORTH FORK CO RIVE	01/10/19	586.00	50.00	38.57	32.12
	WEIGHTED AVERAGE FOR THE FIRST QUARTER			586.00	50.00	38.57	32.12
	WEIGHTED AVERAGE FOR THE YEAR			586.00	50.00	38.57	32.12
=====	504-04420	Precast Panel Facing		Sq Foot	=====	=====	=====
FBR0253-247		I25 AT VINE DRIVE BRIDGE REPL	03/07/19	340.00	50.00	288.59	50.00
	WEIGHTED AVERAGE FOR THE FIRST QUARTER			340.00	50.00	288.59	50.00
NHPP0703-445		I-70 WESTBOUND PEAK PERIOD SH	04/25/19	67,224.00	25.00	30.67	22.00
FSA0703-454		EB I-70 AUX LANE WARD TO KIPL	05/16/19	45.00	45.00	217.76	250.00
FBR0063-057		US-6 F-09-K BRIDGE OVER CASTL	05/30/19	6,941.00	40.00	28.75	34.50
	WEIGHTED AVERAGE FOR THE SECOND QUARTER			74,210.00	26.42	30.66	23.31
	WEIGHTED AVERAGE FOR THE YEAR			74,550.00	26.52	35.06	23.43
=====	504-04430	Reinforced Concrete Facing		Sq Foot	=====	=====	=====
ER119A-065		PR SH 119A BOULDER CANYON	01/03/19	495.00	60.00	57.03	42.00

COLORADO DEPARTMENT OF TRANSPORTATION
ITEM UNIT COSTS BY PROJECTS -- 2019 COST DATA

13:44 Wednesday, August 7, 2019 149

PROJECT NUMBER	ITEM NUMBER/ PROJECT LOCATION	ITEM DESCRIPTION/ PROJECT LOCATION	DATE LET	UNIT/ QUANTITY	ENGR. EST.	AVERAGE BID	AWARDED BID
=====	504-04430	Reinforced Concrete Facing		Sq Foot	=====		
STA119A-069		SH 119: NEDERLAND - EAST					
NHPP0741-022		SH 74: I-70 TO CR 65 RESURFAC	02/14/19	100.00	40.00	368.58	325.00
	WEIGHTED AVERAGE FOR THE FIRST QUARTER			595.00	56.64	85.61	89.56
	WEIGHTED AVERAGE FOR THE YEAR			595.00	56.64	85.61	89.56
=====	504-05000	Wire Mesh Facing		Sq Foot	=====		
NHPP145A-065		SH 145 PASSING LANES AT DEEP	02/14/19	14,850.00	25.00	33.19	27.75
	WEIGHTED AVERAGE FOR THE FIRST QUARTER			14,850.00	25.00	33.19	27.75
	WEIGHTED AVERAGE FOR THE YEAR			14,850.00	25.00	33.19	27.75
=====	504-06100	Ground Nailed Wall		Sq Foot	=====		
ER119A-065		PR SH 119A BOULDER CANYON	01/03/19	1,474.00	20.00	28.43	16.00
STA119A-069		SH 119: NEDERLAND - EAST					
	WEIGHTED AVERAGE FOR THE FIRST QUARTER			1,474.00	20.00	28.43	16.00
	WEIGHTED AVERAGE FOR THE YEAR			1,474.00	20.00	28.43	16.00
=====	504-06400	Soil Nail Wall		Sq Foot	=====		
ER119A-065		PR SH 119A BOULDER CANYON	01/03/19	1,756.00	27.00	86.92	120.00
STA119A-069		SH 119: NEDERLAND - EAST					
	WEIGHTED AVERAGE FOR THE FIRST QUARTER			1,756.00	27.00	86.92	120.00
	WEIGHTED AVERAGE FOR THE YEAR			1,756.00	27.00	86.92	120.00
=====	504-06406	Soil Nail		Lin Foot	=====		
STAR200-242		R2 NORTH PROGRAM WALL REPAIRS	01/03/19	2,800.00	96.00	46.56	41.00
ER119A-065		PR SH 119A BOULDER CANYON	01/03/19	8,245.00	60.00	37.20	38.00
STA119A-069		SH 119: NEDERLAND - EAST					
	WEIGHTED AVERAGE FOR THE FIRST QUARTER			11,045.00	69.13	37.93	38.76
	WEIGHTED AVERAGE FOR THE YEAR			11,045.00	69.13	37.93	38.76

PROJECT NUMBER	ITEM NUMBER/ PROJECT LOCATION	ITEM DESCRIPTION/ PROJECT LOCATION	DATE LET	UNIT/ QUANTITY	ENGR. EST.	AVERAGE BID	AWARDED BID
=====	504-06410	Verification Testing		Each	=====		
STAR200-242		R2 NORTH PROGRAM WALL REPAIRS	01/03/19	2.00	5000.00	3942.86	1716.00
ER119A-065		PR SH 119A BOULDER CANYON	01/03/19	5.00	2500.00	2986.08	3500.00
STA119A-069		SH 119: NEDERLAND - EAST					
		WEIGHTED AVERAGE FOR THE FIRST QUARTER		7.00	3214.29	3073.06	2990.29
		WEIGHTED AVERAGE FOR THE YEAR		7.00	3214.29	3073.06	2990.29
=====	504-08255	Masonry Landscape Wall (Dry Stack)		Sq Foot	=====		
ER119A-065		PR SH 119A BOULDER CANYON	01/03/19	813.00	30.00	59.08	59.00
STA119A-069		SH 119: NEDERLAND - EAST					
		WEIGHTED AVERAGE FOR THE FIRST QUARTER		813.00	30.00	59.08	59.00
		WEIGHTED AVERAGE FOR THE YEAR		813.00	30.00	59.08	59.00
=====	506-00020	Place Riprap		Cubic Yard	=====		
ER119A-065		PR SH 119A BOULDER CANYON	01/03/19	1,505.00	75.00	49.24	30.00
STA119A-069		SH 119: NEDERLAND - EAST					
		WEIGHTED AVERAGE FOR THE FIRST QUARTER		1,505.00	75.00	49.24	30.00
ER145A-081		SH 145 MP 21 EMERGENCY ROCKFA	06/07/19	404.00	25.00	162.28	66.00
		WEIGHTED AVERAGE FOR THE SECOND QUARTER		404.00	25.00	162.28	66.00
		WEIGHTED AVERAGE FOR THE YEAR		1,909.00	64.42	56.35	37.62
=====	506-00030	Grouted Riprap		Cubic Yard	=====		
NHPP1601-073		US 160 PASSING LANE NORTH OF	03/07/19	2.00	1500.00	1200.00	1200.00
		WEIGHTED AVERAGE FOR THE FIRST QUARTER		2.00	1500.00	1200.00	1200.00
		WEIGHTED AVERAGE FOR THE YEAR		2.00	1500.00	1200.00	1200.00

COLORADO DEPARTMENT OF TRANSPORTATION
 ITEM UNIT COSTS BY PROJECTS -- 2019 COST DATA

13:44 Wednesday, August 7, 2019 151

PROJECT NUMBER	ITEM NUMBER/ PROJECT LOCATION	ITEM DESCRIPTION/ PROJECT LOCATION	DATE LET	UNIT/ QUANTITY	ENGR. EST.	AVERAGE BID	AWARDED BID
=====	506-00100	Riprap (Gabions)		Cubic Yard	=====		
NHPP0703-445		I-70 WESTBOUND PEAK PERIOD SH	04/25/19	64.00	150.00	268.54	166.00
	WEIGHTED AVERAGE FOR THE SECOND QUARTER			64.00	150.00	268.54	166.00
	WEIGHTED AVERAGE FOR THE YEAR			64.00	150.00	268.54	166.00
=====	506-00206	Riprap (6 In)		Cubic Yard	=====		
STAR200-242		R2 NORTH PROGRAM WALL REPAIRS	01/03/19	1.00	300.00	307.87	491.00
ER119A-065		PR SH 119A BOULDER CANYON	01/03/19	777.00	100.00	94.08	78.00
STA119A-069		SH 119: NEDERLAND - EAST					
FBR0341-087		US 34 OVER NORTH FORK CO RIVE	01/10/19	8.00	150.00	108.89	60.35
NHPP0701-241		I-70 TRUCK PARKING GARFIELD C	01/17/19	58.00	115.00	163.86	215.00
STR0241-062		US 24 143.4 - 148	01/24/19	9.00	180.00	275.00	210.00
NHPP070A-028		FALL RIVER ROAD BRIDGE	02/21/19	32.00	75.00	104.65	65.00
NHPP1601-073		US 160 PASSING LANE NORTH OF	03/07/19	314.00	180.00	211.50	183.00
FBR0253-247		I25 AT VINE DRIVE BRIDGE REPL	03/07/19	254.00	90.00	102.74	80.00
NHPP0503-087		US 50 PASSING LANES EAST OF S	03/21/19	12.00	200.00	285.00	200.00
	WEIGHTED AVERAGE FOR THE FIRST QUARTER			1,465.00	117.18	106.89	107.99
BR071A-020		REPLACEMENT OF STRUCTURE L-22	04/18/19	161.00	120.00	141.67	120.00
NHPP0703-445		I-70 WESTBOUND PEAK PERIOD SH	04/25/19	86.00	65.00	103.61	87.00
STR 141A-040		R5 YEAR 4 BRDG PREV MAINT RAM	06/20/19	56.00	150.00	540.00	150.00
	WEIGHTED AVERAGE FOR THE SECOND QUARTER			303.00	109.93	182.46	116.18
	WEIGHTED AVERAGE FOR THE YEAR			1,768.00	115.94	112.73	109.39
=====	506-00209	Riprap (9 In)		Cubic Yard	=====		
STR0132-021		SH 13-MOFFAT COUNTY-CR 3 SOUT	01/10/19	67.00	140.00	119.45	70.00
FBR0341-087		US 34 OVER NORTH FORK CO RIVE	01/10/19	352.00	150.00	122.27	131.48
ER072A-040		PR SH72A FLOOD PERMANENT REPA	01/31/19	243.00	125.00	112.65	68.00
NHPP072A-041		PR SH72A FLOOD PERMANENT REPA					
NHPP1601-073		US 160 PASSING LANE NORTH OF	03/07/19	16.00	150.00	252.50	235.00
FBR0253-247		I25 AT VINE DRIVE BRIDGE REPL	03/07/19	12.00	120.00	155.47	150.00
NHPP0503-087		US 50 PASSING LANES EAST OF S	03/21/19	52.00	130.00	180.00	220.00
	WEIGHTED AVERAGE FOR THE FIRST QUARTER			742.00	139.02	119.70	113.87

PROJECT NUMBER	ITEM NUMBER/ PROJECT LOCATION	ITEM DESCRIPTION/ PROJECT LOCATION	DATE LET	UNIT/ QUANTITY	ENGR. EST.	AVERAGE BID	AWARDED BID
=====	506-00209	Riprap (9 In)		Cubic Yard	=====		
NHPP0703-445		I-70 WESTBOUND PEAK PERIOD SH	04/25/19	103.00	75.00	102.90	86.00
		WEIGHTED AVERAGE FOR THE SECOND QUARTER		103.00	75.00	102.90	86.00
		WEIGHTED AVERAGE FOR THE YEAR		845.00	131.22	118.83	110.48
=====	506-00212	Riprap (12 In)		Cubic Yard	=====		
ER119A-065		PR SH 119A BOULDER CANYON	01/03/19	124.00	120.00	114.93	125.00
STA119A-069		SH 119: NEDERLAND - EAST					
STR0132-021		SH 13-MOFFAT COUNTY-CR 3 SOUT	01/10/19	56.00	150.00	135.95	80.00
ER072A-040		PR SH72A FLOOD PERMANENT REPA	01/31/19	118.00	177.00	113.05	68.00
NHPP072A-041		PR SH72A FLOOD PERMANENT REPA					
NHPP145A-065		SH 145 PASSING LANES AT DEEP	02/14/19	275.00	200.00	209.07	225.00
NHPP1601-073		US 160 PASSING LANE NORTH OF	03/07/19	58.00	250.00	242.50	200.00
NHPP050A-033		US50 West of Delta EB Lanes R	03/14/19	40.00	160.00	183.00	134.00
STA0131-070 HMA ALT		SH 13 CR 5 NORTH AND SOUTH	03/28/19	954.00	120.00	141.01	115.00
STA0131-070 PCCP ALT		SH 13 CR 5 NORTH AND SOUTH					
		WEIGHTED AVERAGE FOR THE FIRST QUARTER		1,625.00	144.34	147.09	140.85
NHPP0703-445		I-70 WESTBOUND PEAK PERIOD SH	04/25/19	105.00	140.00	117.20	120.00
		WEIGHTED AVERAGE FOR THE SECOND QUARTER		105.00	140.00	117.20	120.00
		WEIGHTED AVERAGE FOR THE YEAR		1,730.00	144.07	145.83	139.10
=====	506-00218	Riprap (18 In)		Cubic Yard	=====		
ER119A-065		PR SH 119A BOULDER CANYON	01/03/19	7,888.00	95.00	88.97	80.00
STA119A-069		SH 119: NEDERLAND - EAST					
ER072A-040		PR SH72A FLOOD PERMANENT REPA	01/31/19	1,963.00	130.00	117.16	72.00
NHPP072A-041		PR SH72A FLOOD PERMANENT REPA					
NHPP1601-073		US 160 PASSING LANE NORTH OF	03/07/19	91.00	100.00	255.00	200.00
NHPP006A-058		US 6 LOVELAND PASS - I-70 (FY	03/07/19	20.00	350.00	255.47	260.94
NHPP0503-087		US 50 PASSING LANES EAST OF S	03/21/19	18.00	130.00	197.50	250.00
		WEIGHTED AVERAGE FOR THE FIRST QUARTER		9,980.00	102.50	97.08	80.19
		WEIGHTED AVERAGE FOR THE YEAR		9,980.00	102.50	97.08	80.19

COLORADO DEPARTMENT OF TRANSPORTATION
 ITEM UNIT COSTS BY PROJECTS -- 2019 COST DATA

13:44 Wednesday, August 7, 2019 153

PROJECT NUMBER	ITEM NUMBER/ PROJECT LOCATION	ITEM DESCRIPTION/ PROJECT LOCATION	DATE LET	UNIT/ QUANTITY	ENGR. EST.	AVERAGE BID	AWARDED BID
=====	506-00224	Riprap (24 In)		Cubic Yard	=====		
ER119A-065		PR SH 119A BOULDER CANYON	01/03/19	1,590.00	135.00	102.47	130.00
STA119A-069		SH 119: NEDERLAND - EAST					
NHPP0821-107		SH 82 GLENWOOD SPRINGS TO CA	02/07/19	116.00	180.00	196.25	147.50
NHPP070A-028		FALL RIVER ROAD BRIDGE	02/21/19	411.00	120.00	114.51	79.00
STM0242-077		US24 - 8TH ST TO WEST OF MANI	03/28/19	1,012.00	140.00	107.00	100.00
		WEIGHTED AVERAGE FOR THE FIRST QUARTER		3,129.00	136.32	105.81	114.25
NHPP160A-030		US160 MM 43.2, 150.4, 156.3,	06/20/19	19.00	150.00	204.59	280.00
		WEIGHTED AVERAGE FOR THE SECOND QUARTER		19.00	150.00	204.59	280.00
		WEIGHTED AVERAGE FOR THE YEAR		3,148.00	136.40	106.02	115.25
=====	506-00406	Soil Riprap (6 In)		Cubic Yard	=====		
NHPP0703-445		I-70 WESTBOUND PEAK PERIOD SH	04/25/19	91.00	80.00	123.50	115.00
		WEIGHTED AVERAGE FOR THE SECOND QUARTER		91.00	80.00	123.50	115.00
		WEIGHTED AVERAGE FOR THE YEAR		91.00	80.00	123.50	115.00
=====	506-00418	Soil Riprap (18 In)		Cubic Yard	=====		
ER072A-040		PR SH72A FLOOD PERMANENT REPA	01/31/19	5,178.00	110.00	104.74	58.00
NHPP072A-041		PR SH72A FLOOD PERMANENT REPA					
		WEIGHTED AVERAGE FOR THE FIRST QUARTER		5,178.00	110.00	104.74	58.00
NHPP160A-030		US160 MM 43.2, 150.4, 156.3,	06/20/19	12.00	40.00	216.39	280.00
		WEIGHTED AVERAGE FOR THE SECOND QUARTER		12.00	40.00	216.39	280.00
		WEIGHTED AVERAGE FOR THE YEAR		5,190.00	109.84	104.78	58.51
=====	506-00424	Soil Riprap (24 In)		Cubic Yard	=====		
NHPP0821-107		SH 82 GLENWOOD SPRINGS TO CA	02/07/19	52.00	120.00	161.50	158.00
		WEIGHTED AVERAGE FOR THE FIRST QUARTER		52.00	120.00	161.50	158.00
		WEIGHTED AVERAGE FOR THE YEAR		52.00	120.00	161.50	158.00

PROJECT NUMBER	ITEM NUMBER/ PROJECT LOCATION	ITEM DESCRIPTION/ PROJECT LOCATION	DATE LET	UNIT/ QUANTITY	ENGR. EST.	AVERAGE BID	AWARDED BID
=====	506-00612	Matrix Riprap (12 In)		Cubic Yard	=====		
ER119A-065	PR SH 119A BOULDER CANYON	PR SH 119A BOULDER CANYON	01/03/19	4,751.00	160.00	142.44	125.00
STA119A-069	SH 119: NEDERLAND - EAST	SH 119: NEDERLAND - EAST					
STM0242-077	US24 - 8TH ST TO WEST OF MANI	US24 - 8TH ST TO WEST OF MANI	03/28/19	120.00	225.00	356.67	300.00
	WEIGHTED AVERAGE FOR THE FIRST QUARTER			4,871.00	161.60	144.45	129.31
	WEIGHTED AVERAGE FOR THE YEAR			4,871.00	161.60	144.45	129.31
=====	506-01020	Geogrid Reinforce		Sq Yard	=====		
STR0132-021	SH 13-MOFFAT COUNTY-CR 3 SOUT	SH 13-MOFFAT COUNTY-CR 3 SOUT	01/10/19	40,000.00	3.00	1.81	1.65
FBR0341-087	US 34 OVER NORTH FORK CO RIVE	US 34 OVER NORTH FORK CO RIVE	01/10/19	900.00	4.00	5.41	4.65
NHPP1601-073	US 160 PASSING LANE NORTH OF	US 160 PASSING LANE NORTH OF	03/07/19	300.00	7.00	7.00	11.00
STM0242-077	US24 - 8TH ST TO WEST OF MANI	US24 - 8TH ST TO WEST OF MANI	03/28/19	1,115.00	3.00	4.00	5.00
STA0131-070 HMA ALT	SH 13 CR 5 NORTH AND SOUTH	SH 13 CR 5 NORTH AND SOUTH	03/28/19	136,000.00	4.00	2.14	2.85
STA0131-070 PCCP ALT	SH 13 CR 5 NORTH AND SOUTH	SH 13 CR 5 NORTH AND SOUTH					
	WEIGHTED AVERAGE FOR THE FIRST QUARTER			178,315.00	3.77	2.07	2.47
FBR0063-057	US-6 F-09-K BRIDGE OVER CASTL	US-6 F-09-K BRIDGE OVER CASTL	05/30/19	33.00	5.00	37.47	24.15
	WEIGHTED AVERAGE FOR THE SECOND QUARTER			33.00	5.00	37.47	24.15
	WEIGHTED AVERAGE FOR THE YEAR			178,348.00	3.77	2.08	2.48
=====	507-00000	Conc S and D Pave		Cubic Yard	=====		
STAR200-242	R2 NORTH PROGRAM WALL REPAIRS	R2 NORTH PROGRAM WALL REPAIRS	01/03/19	60.00	452.01	827.34	758.00
ER072A-040	PR SH72A FLOOD PERMANENT REPA	PR SH72A FLOOD PERMANENT REPA	01/31/19	3.30	1000.00	989.73	770.00
NHPP072A-041	PR SH72A FLOOD PERMANENT REPA	PR SH72A FLOOD PERMANENT REPA					
NH2871-035	US 287 PASSING LANES SOUTH OF	US 287 PASSING LANES SOUTH OF	02/07/19	10.00	1000.00	637.47	618.10
SHE2254-090	Colfax & I-225, Colfax & Cham	Colfax & I-225, Colfax & Cham	03/07/19	24.00	900.00	862.50	725.00
STA0131-070 HMA ALT	SH 13 CR 5 NORTH AND SOUTH	SH 13 CR 5 NORTH AND SOUTH	03/28/19	34.00	700.00	1504.33	1970.00
STA0131-070 PCCP ALT	SH 13 CR 5 NORTH AND SOUTH	SH 13 CR 5 NORTH AND SOUTH					
	WEIGHTED AVERAGE FOR THE FIRST QUARTER			131.30	653.62	1026.36	919.44
NHPP0703-445	I-70 WESTBOUND PEAK PERIOD SH	I-70 WESTBOUND PEAK PERIOD SH	04/25/19	10.00	1000.00	844.55	320.00

COLORADO DEPARTMENT OF TRANSPORTATION
 ITEM UNIT COSTS BY PROJECTS -- 2019 COST DATA

13:44 Wednesday, August 7, 2019 155

PROJECT NUMBER	ITEM NUMBER/ PROJECT LOCATION	ITEM DESCRIPTION/ PROJECT LOCATION	DATE LET	UNIT/ QUANTITY	ENGR. EST.	AVERAGE BID	AWARDED BID
=====	507-00000	Conc S and D Pave		Cubic Yard	=====		
NHPP0703-442		I-70 SILVERPLUME SOUNDWALL AN	06/13/19	49.00	600.00	697.26	604.00
	WEIGHTED AVERAGE FOR THE SECOND QUARTER			59.00	667.80	707.73	555.86
	WEIGHTED AVERAGE FOR THE YEAR			190.30	658.02	852.09	795.66
=====	507-00100	Conc S and D Pave (Reinf)		Cubic Yard	=====		
ER119A-065		PR SH 119A BOULDER CANYON	01/03/19	149.00	400.00	832.76	650.00
ST119A-069		SH 119: NEDERLAND - EAST					
SHE 0252-481		I-25 RAMP METER INSTALLATION	03/21/19	1.00	500.00	3855.00	2450.00
	WEIGHTED AVERAGE FOR THE FIRST QUARTER			150.00	400.67	840.34	662.00
	WEIGHTED AVERAGE FOR THE YEAR			150.00	400.67	840.34	662.00
=====	507-00350	Gr Riprap S and D Pave		Cubic Yard	=====		
STAR200-242		R2 NORTH PROGRAM WALL REPAIRS	01/03/19	8.00	500.00	451.26	458.00
	WEIGHTED AVERAGE FOR THE FIRST QUARTER			8.00	500.00	451.26	458.00
	WEIGHTED AVERAGE FOR THE YEAR			8.00	500.00	451.26	458.00
=====	507-00400	Bitum S and D Pave (Asph)		Ton	=====		
FBR0341-087		US 34 OVER NORTH FORK CO RIVE	01/10/19	9.00	380.00	459.65	457.60
	WEIGHTED AVERAGE FOR THE FIRST QUARTER			9.00	380.00	459.65	457.60
BR071A-020		REPLACEMENT OF STRUCTURE L-22	04/18/19	12.00	250.00	423.33	510.00
NHPP0703-445		I-70 WESTBOUND PEAK PERIOD SH	04/25/19	3.00	450.00	2056.96	2243.00
	WEIGHTED AVERAGE FOR THE SECOND QUARTER			15.00	290.00	750.06	856.60
	WEIGHTED AVERAGE FOR THE YEAR			24.00	323.75	591.65	706.98
=====	509-00000	Str Steel		Pound	=====		
NHPPRI00-250		PACKAGE A (I-25 / I-70 / I-76	01/24/19	4,087.00	12.50	10.63	9.00
	WEIGHTED AVERAGE FOR THE FIRST QUARTER			4,087.00	12.50	10.63	9.00

COLORADO DEPARTMENT OF TRANSPORTATION
 ITEM UNIT COSTS BY PROJECTS -- 2019 COST DATA

13:44 Wednesday, August 7, 2019 156

PROJECT NUMBER	ITEM NUMBER/ PROJECT LOCATION	ITEM DESCRIPTION/ PROJECT LOCATION	DATE LET	UNIT/ QUANTITY	ENGR. EST.	AVERAGE BID	AWARDED BID
=====	509-00000	Str Steel		Pound	=====		
NHPP0703-442		I-70 SILVERPLUME SOUNDWALL AN	06/13/19	91,859.00	2.50	3.17	2.80
		WEIGHTED AVERAGE FOR THE SECOND QUARTER		91,859.00	2.50	3.17	2.80
		WEIGHTED AVERAGE FOR THE YEAR		95,946.00	2.93	3.37	3.06
=====	509-00001	Str Steel (Galv)		Pound	=====		
STR 141A-040		R5 YEAR 4 BRDG PREV MAINT RAM	06/20/19	720.00	10.00	21.50	8.00
		WEIGHTED AVERAGE FOR THE SECOND QUARTER		720.00	10.00	21.50	8.00
		WEIGHTED AVERAGE FOR THE YEAR		720.00	10.00	21.50	8.00
=====	509-08121	Temp Bridge Deck		Lin Foot	=====		
NHPPR100-250		PACKAGE A (I-25 / I-70 / I-76	01/24/19	103.00	900.00	1726.03	800.00
		WEIGHTED AVERAGE FOR THE FIRST QUARTER		103.00	900.00	1726.03	800.00
		WEIGHTED AVERAGE FOR THE YEAR		103.00	900.00	1726.03	800.00
=====	509-90003	Paint Structural Steel		LUMP SUM	=====		
STAR200-242		R2 NORTH PROGRAM WALL REPAIRS	01/03/19	1.00	25000.00	81086.85	83650.00
		WEIGHTED AVERAGE FOR THE FIRST QUARTER		1.00	25000.00	81086.85	83650.00
		WEIGHTED AVERAGE FOR THE YEAR		1.00	25000.00	81086.85	83650.00
=====	514-00000	Pipe Railing		Lin Foot	=====		
STR0241-062		US 24 143.4 - 148	01/24/19	247.00	200.00	221.67	240.00
		WEIGHTED AVERAGE FOR THE FIRST QUARTER		247.00	200.00	221.67	240.00
		WEIGHTED AVERAGE FOR THE YEAR		247.00	200.00	221.67	240.00

COLORADO DEPARTMENT OF TRANSPORTATION
 ITEM UNIT COSTS BY PROJECTS -- 2019 COST DATA

13:44 Wednesday, August 7, 2019 157

PROJECT NUMBER	ITEM NUMBER/ PROJECT LOCATION	ITEM DESCRIPTION/ PROJECT LOCATION	DATE LET	UNIT/ QUANTITY	ENGR. EST.	AVERAGE BID	AWARDED BID
=====	514-00048	Ped Railing (48 In)		Lin Foot	=====		
ER119A-065 STA119A-069		PR SH 119A BOULDER CANYON SH 119: NEDERLAND - EAST	01/03/19	238.00	225.00	293.08	225.00
		WEIGHTED AVERAGE FOR THE FIRST QUARTER		238.00	225.00	293.08	225.00
		WEIGHTED AVERAGE FOR THE YEAR		238.00	225.00	293.08	225.00
=====	514-00100	Hand Rail		Lin Foot	=====		
CR300-248		CRAIG RESIDENCY ADA RAMPS	05/16/19	14.00	120.00	173.67	50.00
		WEIGHTED AVERAGE FOR THE SECOND QUARTER		14.00	120.00	173.67	50.00
		WEIGHTED AVERAGE FOR THE YEAR		14.00	120.00	173.67	50.00
=====	514-00200	Pedestrian Railing (Steel)		Lin Foot	=====		
ER119A-065 STA119A-069		PR SH 119A BOULDER CANYON SH 119: NEDERLAND - EAST	01/03/19	722.00	175.00	255.97	265.00
		WEIGHTED AVERAGE FOR THE FIRST QUARTER		722.00	175.00	255.97	265.00
		WEIGHTED AVERAGE FOR THE YEAR		722.00	175.00	255.97	265.00
=====	514-00201	Ped Railing (Steel) (Spec)		Lin Foot	=====		
NHPP070A-028		FALL RIVER ROAD BRIDGE	02/21/19	130.00	150.00	473.87	540.00
		WEIGHTED AVERAGE FOR THE FIRST QUARTER		130.00	150.00	473.87	540.00
NHPP0703-445		I-70 WESTBOUND PEAK PERIOD SH	04/25/19	399.00	450.00	285.27	367.00
		WEIGHTED AVERAGE FOR THE SECOND QUARTER		399.00	450.00	285.27	367.00
		WEIGHTED AVERAGE FOR THE YEAR		529.00	376.28	351.64	409.51
=====	515-00120	Waterproofing (Membrane)		Sq Yard	=====		
IM0251-351		I-25 South of Pueblo MP 79.6	01/03/19	345.00	20.00	25.48	22.53

PROJECT NUMBER	ITEM NUMBER/ PROJECT LOCATION	ITEM DESCRIPTION/ PROJECT LOCATION	DATE LET	UNIT/ QUANTITY	ENGR. EST.	AVERAGE BID	AWARDED BID
=====	515-00120	Waterproofing (Membrane)		Sq Yard	=====	=====	=====
ER119A-065	PR SH 119A BOULDER CANYON		01/03/19	1,266.00	20.00	25.84	22.00
STA119A-069	SH 119: NEDERLAND - EAST						
FBR0341-087	US 34 OVER NORTH FORK CO RIVE		01/10/19	568.00	22.00	23.94	24.09
NHPPR100-250	PACKAGE A (I-25 / I-70 / I-76		01/24/19	987.00	20.00	18.24	14.00
ER072A-040	PR SH72A FLOOD PERMANENT REPA		01/31/19	1,047.00	20.00	22.01	18.00
NHPP072A-041	PR SH72A FLOOD PERMANENT REPA						
STA067A-038	SH 67 SEDALIA RESURFACING		01/31/19	1,198.00	20.00	17.14	20.00
NHPP0741-022	SH 74: I-70 TO CR 65 RESURFAC		02/14/19	1,415.00	20.00	17.94	16.25
NHPP070A-028	FALL RIVER ROAD BRIDGE		02/21/19	359.00	20.00	24.04	24.00
FBR0253-247	I25 AT VINE DRIVE BRIDGE REPL		03/07/19	1,453.00	21.00	17.34	16.00
NHPP0702-378	I-70 OFFICERS GULCH TO FRISCO		03/14/19	61.00	250.00	70.96	76.87
NHPP2254-089	I-225 RESURFACING FROM I-25 T		03/21/19	4,148.00	20.00	25.28	24.00
STM0242-077	US24 - 8TH ST TO WEST OF MANI		03/28/19	5,917.00	18.20	20.08	19.25
	WEIGHTED AVERAGE FOR THE FIRST QUARTER			18,764.00	20.32	21.29	20.19
BR071A-020	REPLACEMENT OF STRUCTURE L-22		04/18/19	449.00	20.00	25.67	25.00
NHPP0703-445	I-70 WESTBOUND PEAK PERIOD SH		04/25/19	75.00	18.00	32.30	46.00
FBR0063-057	US-6 F-09-K BRIDGE OVER CASTL		05/30/19	184.00	30.00	36.38	42.75
STR 141A-040	R5 YEAR 4 BRDG PREV MAINT RAM		06/20/19	2,229.00	17.00	26.00	35.00
	WEIGHTED AVERAGE FOR THE SECOND QUARTER			2,937.00	18.30	26.75	34.24
	WEIGHTED AVERAGE FOR THE YEAR			21,701.00	20.04	21.65	22.10
=====	515-00122	Waterproofing (Membrane) (Spec)		Sq Yard	=====	=====	=====
NHPP0703-445	I-70 WESTBOUND PEAK PERIOD SH		04/25/19	1.00	150.00	1286.21	824.00
	WEIGHTED AVERAGE FOR THE SECOND QUARTER			1.00	150.00	1286.21	824.00
	WEIGHTED AVERAGE FOR THE YEAR			1.00	150.00	1286.21	824.00
=====	515-00400	Concrete Sealer		Sq Yard	=====	=====	=====
STAR200-242	R2 NORTH PROGRAM WALL REPAIRS		01/03/19	46,468.00	11.44	17.47	14.75
FBR0253-247	I25 AT VINE DRIVE BRIDGE REPL		03/07/19	406.00	16.00	11.30	11.00
STM0242-077	US24 - 8TH ST TO WEST OF MANI		03/28/19	52.00	15.00	27.58	55.75
	WEIGHTED AVERAGE FOR THE FIRST QUARTER			46,926.00	11.48	17.20	14.76
STR 141A-040	R5 YEAR 4 BRDG PREV MAINT RAM		06/20/19	556.00	20.00	22.50	30.00
	WEIGHTED AVERAGE FOR THE SECOND QUARTER			556.00	20.00	22.50	30.00
	WEIGHTED AVERAGE FOR THE YEAR			47,482.00	11.58	17.26	14.94

COLORADO DEPARTMENT OF TRANSPORTATION
 ITEM UNIT COSTS BY PROJECTS -- 2019 COST DATA

13:44 Wednesday, August 7, 2019 159

PROJECT NUMBER	ITEM NUMBER/ PROJECT LOCATION	ITEM DESCRIPTION/ PROJECT LOCATION	DATE LET	UNIT/ QUANTITY	ENGR. EST.	AVERAGE BID	AWARDED BID
=====	518-00000	Brdg Compress Joint Sealer		Lin Foot	=====		
NHPP030A-035		US 285/SH30	04/04/19	328.00	165.00	145.00	145.00
STR 141A-040		R5 YEAR 4 BRDG PREV MAINT RAM	06/20/19	48.00	200.00	250.00	150.00
		WEIGHTED AVERAGE FOR THE SECOND QUARTER		376.00	169.47	168.77	145.64
		WEIGHTED AVERAGE FOR THE YEAR		376.00	169.47	168.77	145.64
=====	518-00100	Waterstop		Lin Foot	=====		
ER072A-040		PR SH72A FLOOD PERMANENT REPA	01/31/19	36.00	45.00	26.97	7.00
NHPP072A-041		PR SH72A FLOOD PERMANENT REPA					
		WEIGHTED AVERAGE FOR THE FIRST QUARTER		36.00	45.00	26.97	7.00
		WEIGHTED AVERAGE FOR THE YEAR		36.00	45.00	26.97	7.00
=====	518-01001	Br Expan Joint (Asphaltic Plug)		Lin Foot	=====		
IM0251-351		I-25 South of Pueblo MP 79.6	01/03/19	804.00	170.00	176.55	155.43
NHPP0702-378		I-70 OFFICERS GULCH TO FRISCO	03/14/19	168.00	154.00	185.77	217.30
STM0242-077		US24 - 8TH ST TO WEST OF MANI	03/28/19	789.00	220.00	230.67	192.00
		WEIGHTED AVERAGE FOR THE FIRST QUARTER		1,761.00	190.88	198.36	177.72
		WEIGHTED AVERAGE FOR THE YEAR		1,761.00	190.88	198.36	177.72
=====	518-01004	Br Expan Device (0-4 In)		Lin Foot	=====		
NHPPR100-250		PACKAGE A (I-25 / I-70 / I-76	01/24/19	100.00	375.00	312.36	260.00
NHPP0741-022		SH 74: I-70 TO CR 65 RESURFAC	02/14/19	228.00	350.00	440.89	445.00
FBR0253-247		I25 AT VINE DRIVE BRIDGE REPL	03/07/19	130.00	210.00	271.27	200.00
		WEIGHTED AVERAGE FOR THE FIRST QUARTER		458.00	315.72	332.93	335.07
STR 141A-040		R5 YEAR 4 BRDG PREV MAINT RAM	06/20/19	126.00	300.00	430.00	400.00
		WEIGHTED AVERAGE FOR THE SECOND QUARTER		126.00	300.00	430.00	400.00
		WEIGHTED AVERAGE FOR THE YEAR		584.00	312.33	340.83	349.08

COLORADO DEPARTMENT OF TRANSPORTATION
 ITEM UNIT COSTS BY PROJECTS -- 2019 COST DATA

13:44 Wednesday, August 7, 2019 160

PROJECT NUMBER	ITEM NUMBER/ PROJECT LOCATION	ITEM DESCRIPTION/ PROJECT LOCATION	DATE LET	UNIT/ QUANTITY	ENGR. EST.	AVERAGE BID	AWARDED BID
=====	518-01050	Br Expan Device (Special)		Lin Foot	=====		
STR 141A-040		R5 YEAR 4 BRDG PREV MAINT RAM	06/20/19	128.00	400.00	410.00	450.00
	WEIGHTED AVERAGE FOR THE SECOND QUARTER			128.00	400.00	410.00	450.00
	WEIGHTED AVERAGE FOR THE YEAR			128.00	400.00	410.00	450.00
=====	518-01060	Br Expan Device (Gland) (0-4 In)		Lin Foot	=====		
NHPPR100-250		PACKAGE A (I-25 / I-70 / I-76)	01/24/19	56.00	200.00	132.10	75.00
	WEIGHTED AVERAGE FOR THE FIRST QUARTER			56.00	200.00	132.10	75.00
	WEIGHTED AVERAGE FOR THE YEAR			56.00	200.00	132.10	75.00
=====	518-01109	Inst Br Expan Device (Greater Than 4 In)		Lin Foot	=====		
NHPPR100-250		PACKAGE A (I-25 / I-70 / I-76)	01/24/19	103.00	220.00	637.17	435.00
	WEIGHTED AVERAGE FOR THE FIRST QUARTER			103.00	220.00	637.17	435.00
	WEIGHTED AVERAGE FOR THE YEAR			103.00	220.00	637.17	435.00
=====	518-03000	Saw and Seal Br Joint		Lin Foot	=====		
IM0251-351		I-25 South of Pueblo MP 79.6	01/03/19	90.00	31.00	27.92	28.16
ER119A-065		PR SH 119A BOULDER CANYON	01/03/19	715.00	25.00	20.51	28.00
STA119A-069		SH 119: NEDERLAND - EAST					
STR141A-047		SH 141 MP 120-143 MESA COUNTY	01/17/19	219.00	25.00	27.45	23.00
NHPPR100-250		PACKAGE A (I-25 / I-70 / I-76)	01/24/19	1,531.00	22.00	15.94	10.00
NHPP0702-378		I-70 OFFICERS GULCH TO FRISCO	03/14/19	1,320.00	26.00	28.87	25.62
NHPP2254-089		I-225 RESURFACING FROM I-25 T	03/21/19	1,480.00	35.00	14.27	16.00
	WEIGHTED AVERAGE FOR THE FIRST QUARTER			5,355.00	27.25	19.60	18.75
STR 141A-040		R5 YEAR 4 BRDG PREV MAINT RAM	06/20/19	212.00	25.00	46.00	80.00
	WEIGHTED AVERAGE FOR THE SECOND QUARTER			212.00	25.00	46.00	80.00
	WEIGHTED AVERAGE FOR THE YEAR			5,567.00	27.17	20.08	21.08

COLORADO DEPARTMENT OF TRANSPORTATION
 ITEM UNIT COSTS BY PROJECTS -- 2019 COST DATA

13:44 Wednesday, August 7, 2019 161

PROJECT NUMBER	ITEM NUMBER/ PROJECT LOCATION	ITEM DESCRIPTION/ PROJECT LOCATION	DATE LET	UNIT/ QUANTITY	ENGR. EST.	AVERAGE BID	AWARDED BID
=====	518-03100	Rapid Cure Silicone Jt Seal		Lin Foot	=====		
NHPP160A-030		US160 MM 43.2, 150.4, 156.3,	06/20/19	20.00	40.00	155.63	270.00
	WEIGHTED AVERAGE FOR THE SECOND QUARTER			20.00	40.00	155.63	270.00
	WEIGHTED AVERAGE FOR THE YEAR			20.00	40.00	155.63	270.00
=====	519-01000	Epoxy Resin (Injection)		Lin Foot	=====		
IM0251-351		I-25 South of Pueblo MP 79.6	01/03/19	61.00	150.00	319.40	366.05
	WEIGHTED AVERAGE FOR THE FIRST QUARTER			61.00	150.00	319.40	366.05
NHPP160A-030		US160 MM 43.2, 150.4, 156.3,	06/20/19	25.00	140.00	187.50	250.00
	WEIGHTED AVERAGE FOR THE SECOND QUARTER			25.00	140.00	187.50	250.00
	WEIGHTED AVERAGE FOR THE YEAR			86.00	147.09	296.97	332.31
=====	519-03035	Place Thin Bond Overlay (Poly Conc)		Sq Yard	=====		
NHPPR100-250		PACKAGE A (I-25 / I-70 / I-76	01/24/19	7,302.00	25.00	44.56	50.50
	WEIGHTED AVERAGE FOR THE FIRST QUARTER			7,302.00	25.00	44.56	50.50
STR 141A-040		R5 YEAR 4 BRDG PREV MAINT RAM	06/20/19	1,631.00	70.00	129.50	175.00
	WEIGHTED AVERAGE FOR THE SECOND QUARTER			1,631.00	70.00	129.50	175.00
	WEIGHTED AVERAGE FOR THE YEAR			8,933.00	33.22	51.52	73.23
=====	519-03055	Furnish Thin Bond Overlay (Poly Conc)		Cubic Foot	=====		
NHPPR100-250		PACKAGE A (I-25 / I-70 / I-76	01/24/19	6,354.00	100.00	116.76	99.00
	WEIGHTED AVERAGE FOR THE FIRST QUARTER			6,354.00	100.00	116.76	99.00

PROJECT NUMBER	ITEM NUMBER/ PROJECT LOCATION	ITEM DESCRIPTION/ PROJECT LOCATION	DATE LET	UNIT/ QUANTITY	ENGR. EST.	AVERAGE BID	AWARDED BID
=====	519-03055	Furnish Thin Bond Overlay (Poly Conc)		Cubic Foot	=====		
STR 141A-040		R5 YEAR 4 BRDG PREV MAINT RAM	06/20/19	1,156.00	130.00	160.00	197.00
		WEIGHTED AVERAGE FOR THE SECOND QUARTER		1,156.00	130.00	160.00	197.00
		WEIGHTED AVERAGE FOR THE YEAR		7,510.00	104.62	119.69	114.08
=====	601-01000	Conc CL B		Cubic Yard	=====		
STAR200-242		R2 NORTH PROGRAM WALL REPAIRS	01/03/19	3.00	700.00	1192.08	1322.00
ER119A-065		PR SH 119A BOULDER CANYON	01/03/19	53.00	1200.00	1071.01	697.00
STA119A-069		SH 119: NEDERLAND - EAST					
STR0132-021		SH 13-MOFFAT COUNTY-CR 3 SOUT	01/10/19	61.10	1000.00	894.00	690.00
STA0131-070 HMA ALT		SH 13 CR 5 NORTH AND SOUTH	03/28/19	390.00	800.00	1113.00	963.00
STA0131-070 PCCP ALT		SH 13 CR 5 NORTH AND SOUTH					
		WEIGHTED AVERAGE FOR THE FIRST QUARTER		507.10	865.31	1068.79	867.83
NHPP160A-030		US160 MM 43.2, 150.4, 156.3,	06/20/19	25.00	3500.00	2437.50	3000.00
		WEIGHTED AVERAGE FOR THE SECOND QUARTER		25.00	3500.00	2437.50	3000.00
		WEIGHTED AVERAGE FOR THE YEAR		532.10	989.10	1103.79	1025.96
=====	601-01050	Conc CL B (Wall)		Cubic Yard	=====		
ER119A-065		PR SH 119A BOULDER CANYON	01/03/19	18.00	1200.00	1202.47	800.00
STA119A-069		SH 119: NEDERLAND - EAST					
STR0241-062		US 24 143.4 - 148	01/24/19	3.00	2000.00	1328.33	1400.00
NHPP0503-087		US 50 PASSING LANES EAST OF S	03/21/19	17.00	1500.00	1750.00	1300.00
		WEIGHTED AVERAGE FOR THE FIRST QUARTER		38.00	1397.37	1308.08	1071.05
NHPP0703-445		I-70 WESTBOUND PEAK PERIOD SH	04/25/19	18.00	520.00	1197.67	593.00
		WEIGHTED AVERAGE FOR THE SECOND QUARTER		18.00	520.00	1197.67	593.00
		WEIGHTED AVERAGE FOR THE YEAR		56.00	1115.36	1283.34	917.39

COLORADO DEPARTMENT OF TRANSPORTATION
 ITEM UNIT COSTS BY PROJECTS -- 2019 COST DATA

13:44 Wednesday, August 7, 2019 163

PROJECT NUMBER	ITEM NUMBER/ PROJECT LOCATION	ITEM DESCRIPTION/ PROJECT LOCATION	DATE LET	UNIT/ QUANTITY	ENGR. EST.	AVERAGE BID	AWARDED BID
===== 601-03000		Conc CL D		Cubic Yard	=====		
ER119A-065		PR SH 119A BOULDER CANYON	01/03/19	53.00	1400.00	1124.82	330.00
STA119A-069		SH 119: NEDERLAND - EAST					
STR0241-062		US 24 143.4 - 148	01/24/19	10.00	2500.00	1110.00	1200.00
NHPP0821-107		SH 82 GLENWOOD SPRINGS TO CA	02/07/19	28.00	600.00	824.00	1158.00
NHPP145A-065		SH 145 PASSING LANES AT DEEP	02/14/19	44.40	1000.00	1625.95	1825.00
NHPP070A-028		FALL RIVER ROAD BRIDGE	02/21/19	289.00	800.00	724.33	520.00
NHPP1601-073		US 160 PASSING LANE NORTH OF	03/07/19	50.00	1000.00	1525.00	1050.00
NHPP0702-378		I-70 OFFICERS GULCH TO FRISCO	03/14/19	26.00	1500.00	923.75	1281.25
		WEIGHTED AVERAGE FOR THE FIRST QUARTER		500.40	960.43	929.31	757.47
FBR0063-057		US-6 F-09-K BRIDGE OVER CASTL	05/30/19	8.00	1800.00	1635.00	1320.00
C0502-085		US 50 MM 201.8 MONARCH AVALAN	06/27/19	8.60	4000.00	7183.50	6000.00
		WEIGHTED AVERAGE FOR THE SECOND QUARTER		16.60	2939.76	4509.52	3744.58
		WEIGHTED AVERAGE FOR THE YEAR		517.00	1023.98	979.08	853.38
===== 601-03030		Conc CL D (Box)		Cubic Yard	=====		
ER119A-065		PR SH 119A BOULDER CANYON	01/03/19	37.00	800.00	1097.65	700.00
STA119A-069		SH 119: NEDERLAND - EAST					
STR0132-021		SH 13-MOFFAT COUNTY-CR 3 SOUT	01/10/19	94.90	1200.00	997.00	900.00
ER072A-040		PR SH72A FLOOD PERMANENT REPA	01/31/19	1,500.00	750.00	721.47	840.00
NHPP072A-041		PR SH72A FLOOD PERMANENT REPA					
NHPP0503-087		US 50 PASSING LANES EAST OF S	03/21/19	155.00	800.00	1250.00	1100.00
		WEIGHTED AVERAGE FOR THE FIRST QUARTER		1,786.90	779.27	742.74	862.84
		WEIGHTED AVERAGE FOR THE YEAR		1,786.90	779.27	742.74	862.84
===== 601-03040		Conc CL D (Bridge)		Cubic Yard	=====		
ER119A-065		PR SH 119A BOULDER CANYON	01/03/19	35.00	1000.00	1736.21	890.00
STA119A-069		SH 119: NEDERLAND - EAST					
FBR0341-087		US 34 OVER NORTH FORK CO RIVE	01/10/19	107.00	1300.00	884.55	726.02
NHPP070A-028		FALL RIVER ROAD BRIDGE	02/21/19	315.00	850.00	963.06	670.00
STM0242-077		US24 - 8TH ST TO WEST OF MANI	03/28/19	145.00	1071.38	1433.33	1600.00
		WEIGHTED AVERAGE FOR THE FIRST QUARTER		602.00	992.03	1089.47	916.75

COLORADO DEPARTMENT OF TRANSPORTATION
 ITEM UNIT COSTS BY PROJECTS -- 2019 COST DATA

13:44 Wednesday, August 7, 2019 164

PROJECT NUMBER	ITEM NUMBER/ PROJECT LOCATION	ITEM DESCRIPTION/ PROJECT LOCATION	DATE LET	UNIT/ QUANTITY	ENGR. EST.	AVERAGE BID	AWARDED BID
=====	601-03040	Conc CL D (Bridge)		Cubic Yard	=====		
BR071A-020		REPLACEMENT OF STRUCTURE L-22	04/18/19	163.00	800.00	950.00	510.00
STR 141A-040		R5 YEAR 4 BRDG PREV MAINT RAM	06/20/19	102.00	1000.00	1150.00	1500.00
		WEIGHTED AVERAGE FOR THE SECOND QUARTER		265.00	876.98	1008.87	891.06
		WEIGHTED AVERAGE FOR THE YEAR		867.00	956.86	1074.06	908.90
=====	601-03050	Conc CL D (Wall)		Cubic Yard	=====		
ER119A-065		PR SH 119A BOULDER CANYON	01/03/19	656.00	790.00	893.95	905.00
STA119A-069		SH 119: NEDERLAND - EAST					
FBR0341-087		US 34 OVER NORTH FORK CO RIVE	01/10/19	12.00	1500.00	1430.24	1882.85
STR0241-062		US 24 143.4 - 148	01/24/19	134.00	1200.00	993.33	1000.00
ER072A-040		PR SH72A FLOOD PERMANENT REPA	01/31/19	152.00	800.00	717.79	805.00
NHPP072A-041		PR SH72A FLOOD PERMANENT REPA					
FBR0253-247		I25 AT VINE DRIVE BRIDGE REPL	03/07/19	12.00	900.00	585.93	700.00
		WEIGHTED AVERAGE FOR THE FIRST QUARTER		966.00	858.63	857.04	912.04
NHPP0703-445		I-70 WESTBOUND PEAK PERIOD SH	04/25/19	7,997.00	600.00	733.33	450.00
FBR0063-057		US-6 F-09-K BRIDGE OVER CASTL	05/30/19	79.00	1600.00	1460.00	1320.00
NHPP0703-442		I-70 SILVERPLUME SOUNDWALL AN	06/13/19	82.00	650.00	893.31	901.00
		WEIGHTED AVERAGE FOR THE SECOND QUARTER		8,158.00	610.19	742.19	462.96
		WEIGHTED AVERAGE FOR THE YEAR		9,124.00	636.49	769.34	510.50
=====	601-03057	Conc CL DR		Cubic Yard	=====		
IM0251-351		I-25 South of Pueblo MP 79.6	01/03/19	2.00	3500.00	2307.39	2534.18
NHPPR100-250		PACKAGE A (I-25 / I-70 / I-76	01/24/19	55.00	1050.00	2466.56	1500.00
STA067A-038		SH 67 SEDALIA RESURFACING	01/31/19	31.00	3000.00	2416.10	1800.00
NHPP0741-022		SH 74: I-70 TO CR 65 RESURFAC	02/14/19	24.90	3000.00	3023.68	2985.00
NHPP0702-378		I-70 OFFICERS GULCH TO FRISCO	03/14/19	5.00	3600.00	1324.17	2562.50
STM0242-077		US24 - 8TH ST TO WEST OF MANI	03/28/19	59.00	1600.00	2150.00	2250.00
		WEIGHTED AVERAGE FOR THE FIRST QUARTER		176.90	1949.41	2431.14	2053.46

COLORADO DEPARTMENT OF TRANSPORTATION
 ITEM UNIT COSTS BY PROJECTS -- 2019 COST DATA

13:44 Wednesday, August 7, 2019 165

PROJECT NUMBER	ITEM NUMBER/ PROJECT LOCATION	ITEM DESCRIPTION/ PROJECT LOCATION	DATE LET	UNIT/ QUANTITY	ENGR. EST.	AVERAGE BID	AWARDED BID
=====	601-03057	Conc CL DR		Cubic Yard	=====		
STR 141A-040		R5 YEAR 4 BRDG PREV MAINT RAM	06/20/19	22.00	4000.00	2875.00	1500.00
		WEIGHTED AVERAGE FOR THE SECOND QUARTER		22.00	4000.00	2875.00	1500.00
		WEIGHTED AVERAGE FOR THE YEAR		198.90	2176.22	2458.59	1992.24
=====	601-03540	Conc CL DT (Deck Topping)		Cubic Yard	=====		
ER119A-065 STA119A-069		PR SH 119A BOULDER CANYON SH 119: NEDERLAND - EAST	01/03/19	39.00	1000.00	964.20	1100.00
		WEIGHTED AVERAGE FOR THE FIRST QUARTER		39.00	1000.00	964.20	1100.00
		WEIGHTED AVERAGE FOR THE YEAR		39.00	1000.00	964.20	1100.00
=====	601-04550	Conc CL G		Cubic Yard	=====		
FBR0253-247		I25 AT VINE DRIVE BRIDGE REPL	03/07/19	952.00	750.00	752.44	635.00
		WEIGHTED AVERAGE FOR THE FIRST QUARTER		952.00	750.00	752.44	635.00
		WEIGHTED AVERAGE FOR THE YEAR		952.00	750.00	752.44	635.00
=====	601-06100	Conc (Patching)		Cubic Yard	=====		
ER119A-065 STA119A-069 NHPPR100-250 NHPP2254-089 STM0242-077		PR SH 119A BOULDER CANYON SH 119: NEDERLAND - EAST PACKAGE A (I-25 / I-70 / I-76 I-225 RESURFACING FROM I-25 T US24 - 8TH ST TO WEST OF MANI	01/03/19 01/24/19 03/21/19 03/28/19	10.00 3.00 27.00 4.00	100.00 1900.00 2250.00 2700.00	3234.87 3620.79 2983.17 2600.00	2800.00 3200.00 2700.00 3000.00
		WEIGHTED AVERAGE FOR THE FIRST QUARTER		44.00	1778.41	3116.69	2784.09
		WEIGHTED AVERAGE FOR THE YEAR		44.00	1778.41	3116.69	2784.09
=====	601-06102	Concrete (Patching)		Cubic Foot	=====		
IM0251-351		I-25 South of Pueblo MP 79.6	01/03/19	77.00	110.00	236.29	270.31
		WEIGHTED AVERAGE FOR THE FIRST QUARTER		77.00	110.00	236.29	270.31
		WEIGHTED AVERAGE FOR THE YEAR		77.00	110.00	236.29	270.31

COLORADO DEPARTMENT OF TRANSPORTATION
ITEM UNIT COSTS BY PROJECTS -- 2019 COST DATA

13:44 Wednesday, August 7, 2019 166

PROJECT NUMBER	ITEM NUMBER/ PROJECT LOCATION	ITEM DESCRIPTION/ PROJECT LOCATION	DATE LET	UNIT/ QUANTITY	ENGR. EST.	AVERAGE BID	AWARDED BID
=====	601-06150	Conc (Patching)		Sq Foot	=====		
STAR200-242		R2 NORTH PROGRAM WALL REPAIRS	01/03/19	72.00	200.00	195.07	311.00
NHPP0503-087		US 50 PASSING LANES EAST OF S	03/21/19	50.00	120.00	143.00	120.00
		WEIGHTED AVERAGE FOR THE FIRST QUARTER		122.00	167.21	173.73	232.72
		WEIGHTED AVERAGE FOR THE YEAR		122.00	167.21	173.73	232.72
=====	601-06164	Conc (Patching) (Fast Curing)		Cubic Yard	=====		
NHPP160A-030		US160 MM 43.2, 150.4, 156.3,	06/20/19	1.00	7000.00	9750.00	17000.00
		WEIGHTED AVERAGE FOR THE SECOND QUARTER		1.00	7000.00	9750.00	17000.00
		WEIGHTED AVERAGE FOR THE YEAR		1.00	7000.00	9750.00	17000.00
=====	601-06404	Concrete (UHPC)		Cubic Foot	=====		
FBR0341-087		US 34 OVER NORTH FORK CO RIVE	01/10/19	920.00	380.00	309.75	390.94
		WEIGHTED AVERAGE FOR THE FIRST QUARTER		920.00	380.00	309.75	390.94
		WEIGHTED AVERAGE FOR THE YEAR		920.00	380.00	309.75	390.94
=====	601-10310	Fly Ash Slurry		Cubic Yard	=====		
ER072A-040		PR SH72A FLOOD PERMANENT REPA	01/31/19	40.00	300.00	237.83	120.00
NHPP072A-041		PR SH72A FLOOD PERMANENT REPA					
		WEIGHTED AVERAGE FOR THE FIRST QUARTER		40.00	300.00	237.83	120.00
		WEIGHTED AVERAGE FOR THE YEAR		40.00	300.00	237.83	120.00
=====	601-40005	Cut Stone Veneer		Sq Foot	=====		
ER119A-065		PR SH 119A BOULDER CANYON	01/03/19	4,092.00	62.00	65.17	60.00
STA119A-069		SH 119: NEDERLAND - EAST					
		WEIGHTED AVERAGE FOR THE FIRST QUARTER		4,092.00	62.00	65.17	60.00
		WEIGHTED AVERAGE FOR THE YEAR		4,092.00	62.00	65.17	60.00

COLORADO DEPARTMENT OF TRANSPORTATION
 ITEM UNIT COSTS BY PROJECTS -- 2019 COST DATA

13:44 Wednesday, August 7, 2019 167

PROJECT NUMBER	ITEM NUMBER/ PROJECT LOCATION	ITEM DESCRIPTION/ PROJECT LOCATION	DATE LET	UNIT/ QUANTITY	ENGR. EST.	AVERAGE BID	AWARDED BID
=====	601-40300	Struct Conc Coating		Sq Yard	=====		
ER119A-065		PR SH 119A BOULDER CANYON	01/03/19	52.00	30.00	39.11	10.00
STA119A-069		SH 119: NEDERLAND - EAST					
NHPPR100-250		PACKAGE A (I-25 / I-70 / I-76	01/24/19	88.00	10.00	35.02	30.00
NHPP070A-028		FALL RIVER ROAD BRIDGE	02/21/19	1,067.00	20.00	15.59	13.00
		WEIGHTED AVERAGE FOR THE FIRST QUARTER		1,207.00	19.70	18.55	14.11
NHPP0703-445		I-70 WESTBOUND PEAK PERIOD SH	04/25/19	45,065.00	16.00	11.50	13.00
FBR0063-057		US-6 F-09-K BRIDGE OVER CASTL	05/30/19	834.00	30.00	26.88	13.75
		WEIGHTED AVERAGE FOR THE SECOND QUARTER		45,899.00	16.25	11.69	13.01
		WEIGHTED AVERAGE FOR THE YEAR		47,106.00	16.34	11.98	13.04
=====	601-40400	Struct Conc Stain		Sq Yard	=====		
ER119A-065		PR SH 119A BOULDER CANYON	01/03/19	5.00	18.00	83.72	90.00
STA119A-069		SH 119: NEDERLAND - EAST					
FBR0341-087		US 34 OVER NORTH FORK CO RIVE	01/10/19	442.00	25.00	26.49	32.59
FBR0253-247		I25 AT VINE DRIVE BRIDGE REPL	03/07/19	1,574.00	10.00	14.14	14.70
		WEIGHTED AVERAGE FOR THE FIRST QUARTER		2,021.00	13.30	15.91	18.80
NHPP0703-442		I-70 SILVERPLUME SOUNDWALL AN	06/13/19	5,460.00	20.00	11.15	10.00
		WEIGHTED AVERAGE FOR THE SECOND QUARTER		5,460.00	20.00	11.15	10.00
		WEIGHTED AVERAGE FOR THE YEAR		7,481.00	18.19	12.64	12.38
=====	601-40401	Struct Conc Stain		Sq Foot	=====		
ER119A-065		PR SH 119A BOULDER CANYON	01/03/19	7,750.00	2.00	8.06	10.00
STA119A-069		SH 119: NEDERLAND - EAST					
		WEIGHTED AVERAGE FOR THE FIRST QUARTER		7,750.00	2.00	8.06	10.00
		WEIGHTED AVERAGE FOR THE YEAR		7,750.00	2.00	8.06	10.00

PROJECT NUMBER	ITEM NUMBER/ PROJECT LOCATION	ITEM DESCRIPTION/ PROJECT LOCATION	DATE LET	UNIT/ QUANTITY	ENGR. EST.	AVERAGE BID	AWARDED BID
=====	601-51005	Galvanic Anodes		Each	=====		
ER119A-065	PR SH 119A BOULDER CANYON	01/03/19	100.00	40.00	37.59	30.00	
STA119A-069	SH 119: NEDERLAND - EAST						
STA067A-038	SH 67 SEDALIA RESURFACING	01/31/19	1,040.00	25.00	22.46	15.00	
NHPP0741-022	SH 74: I-70 TO CR 65 RESURFAC	02/14/19	355.00	27.00	26.07	27.10	
NHPP0702-378	I-70 OFFICERS GULCH TO FRISCO	03/14/19	85.00	25.00	44.75	51.25	
NHPP2254-089	I-225 RESURFACING FROM I-25 T	03/21/19	1,155.00	30.00	36.07	35.00	
STM0242-077	US24 - 8TH ST TO WEST OF MANI	03/28/19	2,455.00	26.18	21.17	16.50	
	WEIGHTED AVERAGE FOR THE FIRST QUARTER		5,190.00	27.10	26.15	21.87	
STR 141A-040	R5 YEAR 4 BRDG PREV MAINT RAM	06/20/19	225.00	45.00	28.00	25.00	
	WEIGHTED AVERAGE FOR THE SECOND QUARTER		225.00	45.00	28.00	25.00	
	WEIGHTED AVERAGE FOR THE YEAR		5,415.00	27.84	26.20	22.00	
=====	601-51007	Galvanic Anodes (Install Only)		Each	=====		
IM0251-351	I-25 South of Pueblo MP 79.6	01/03/19	95.00	40.00	22.59	18.02	
	WEIGHTED AVERAGE FOR THE FIRST QUARTER		95.00	40.00	22.59	18.02	
	WEIGHTED AVERAGE FOR THE YEAR		95.00	40.00	22.59	18.02	
=====	602-00000	Reinf Steel		Pound	=====		
STAR200-242	R2 NORTH PROGRAM WALL REPAIRS	01/03/19	229.00	3.00	2.54	3.00	
IM0251-351	I-25 South of Pueblo MP 79.6	01/03/19	200.00	5.00	13.30	16.89	
ER119A-065	PR SH 119A BOULDER CANYON	01/03/19	69,930.00	1.10	1.27	1.05	
STA119A-069	SH 119: NEDERLAND - EAST						
STR0241-062	US 24 143.4 - 148	01/24/19	1,550.00	2.00	2.00	2.00	
ER072A-040	PR SH72A FLOOD PERMANENT REPA	01/31/19	15,128.00	2.00	1.12	1.60	
NHPP072A-041	PR SH72A FLOOD PERMANENT REPA						
STA067A-038	SH 67 SEDALIA RESURFACING	01/31/19	1,385.00	2.00	2.77	2.00	
NHPP0741-022	SH 74: I-70 TO CR 65 RESURFAC	02/14/19	415.00	2.50	2.84	3.26	
NHPP2254-089	I-225 RESURFACING FROM I-25 T	03/21/19	1,265.00	1.50	2.56	2.10	
STM0242-077	US24 - 8TH ST TO WEST OF MANI	03/28/19	7,490.00	1.37	2.58	3.75	
STA0131-070 HMA ALT	SH 13 CR 5 NORTH AND SOUTH	03/28/19	20,808.00	1.40	2.07	1.50	
STA0131-070 PCCP ALT	SH 13 CR 5 NORTH AND SOUTH						
	WEIGHTED AVERAGE FOR THE FIRST QUARTER		118,400.00	1.33	1.36	1.44	

PROJECT NUMBER	ITEM NUMBER/ PROJECT LOCATION	ITEM DESCRIPTION/ PROJECT LOCATION	DATE LET	UNIT/ QUANTITY	ENGR. EST.	AVERAGE BID	AWARDED BID
=====	602-00000	Reinf Steel		Pound	=====		
NHPP0703-445		I-70 WESTBOUND PEAK PERIOD SH	04/25/19	53,815.00	1.00	0.99	0.95
STR 141A-040		R5 YEAR 4 BRDG PREV MAINT RAM	06/20/19	265.00	4.00	3.00	2.00
NHPP160A-030		US160 MM 43.2, 150.4, 156.3,	06/20/19	60.00	2.00	16.25	30.00
C0502-085		US 50 MM 201.8 MONARCH AVALAN	06/27/19	809.00	6.00	25.50	22.75
		WEIGHTED AVERAGE FOR THE SECOND QUARTER		54,949.00	1.09	1.25	1.31
		WEIGHTED AVERAGE FOR THE YEAR		173,349.00	1.25	1.34	1.39
=====	602-00020	Reinf Steel (Epoxy)		Pound	=====		
ER119A-065		PR SH 119A BOULDER CANYON	01/03/19	70,350.00	1.10	1.62	1.10
STA119A-069		SH 119: NEDERLAND - EAST					
STR0132-021		SH 13-MOFFAT COUNTY-CR 3 SOUT	01/10/19	6,326.00	3.00	4.41	5.50
FBR0341-087		US 34 OVER NORTH FORK CO RIVE	01/10/19	18,970.00	1.30	1.52	1.48
STR0241-062		US 24 143.4 - 148	01/24/19	11,020.00	2.00	2.72	2.50
NHPPR100-250		PACKAGE A (I-25 / I-70 / I-76	01/24/19	4,508.00	2.00	2.05	2.00
ER072A-040		PR SH72A FLOOD PERMANENT REPA	01/31/19	350,682.00	2.50	1.25	1.60
NHPP072A-041		PR SH72A FLOOD PERMANENT REPA					
NHPP0821-107		SH 82 GLENWOOD SPRINGS TO CA	02/07/19	2,930.00	1.80	3.45	3.15
NHPP145A-065		SH 145 PASSING LANES AT DEEP	02/14/19	2,168.00	7.00	2.73	1.85
NHPP0741-022		SH 74: I-70 TO CR 65 RESURFAC	02/14/19	1,888.00	2.50	3.39	3.80
NHPP070A-028		FALL RIVER ROAD BRIDGE	02/21/19	77,905.00	1.65	1.31	1.00
NHPP1601-073		US 160 PASSING LANE NORTH OF	03/07/19	3,651.00	2.00	4.25	6.50
FBR0253-247		I25 AT VINE DRIVE BRIDGE REPL	03/07/19	183,239.00	1.10	1.11	1.05
NHPP0702-378		I-70 OFFICERS GULCH TO FRISCO	03/14/19	6,930.00	6.00	3.87	5.12
NHPP0503-087		US 50 PASSING LANES EAST OF S	03/21/19	24,749.00	1.50	2.25	2.00
STM0242-077		US24 - 8TH ST TO WEST OF MANI	03/28/19	15,175.00	1.20	2.30	1.50
		WEIGHTED AVERAGE FOR THE FIRST QUARTER		780,491.00	1.91	1.30	1.49
BR071A-020		REPLACEMENT OF STRUCTURE L-22	04/18/19	28,600.00	2.00	1.22	1.15
NHPP0703-445		I-70 WESTBOUND PEAK PERIOD SH	04/25/19	1,101,795.00	1.50	1.16	1.02
FBR0063-057		US-6 F-09-K BRIDGE OVER CASTL	05/30/19	9,513.00	3.00	2.45	2.40
NHPP0703-442		I-70 SILVERPLUME SOUNDWALL AN	06/13/19	17,794.00	1.25	1.63	1.30
STR 141A-040		R5 YEAR 4 BRDG PREV MAINT RAM	06/20/19	19,190.00	2.50	2.75	2.00
NHPP160A-030		US160 MM 43.2, 150.4, 156.3,	06/20/19	50.00	2.15	31.40	60.00
		WEIGHTED AVERAGE FOR THE SECOND QUARTER		1,176,942.00	1.54	1.20	1.06
		WEIGHTED AVERAGE FOR THE YEAR		1,957,433.00	1.68	1.27	1.23

COLORADO DEPARTMENT OF TRANSPORTATION
 ITEM UNIT COSTS BY PROJECTS -- 2019 COST DATA

13:44 Wednesday, August 7, 2019 170

PROJECT NUMBER	ITEM NUMBER/ PROJECT LOCATION	ITEM DESCRIPTION/ PROJECT LOCATION	DATE LET	UNIT/ QUANTITY	ENGR. EST.	AVERAGE BID	AWARDED BID
=====	602-00210	Welded Wire Fabric		Sq Yard	=====		
NHPP145A-065		SH 145 PASSING LANES AT DEEP	02/14/19	11,432.00	22.00	14.94	3.50
SHE2254-090		Colfax & I-225, Colfax & Cham	03/07/19	145.00	13.00	26.50	8.00
		WEIGHTED AVERAGE FOR THE FIRST QUARTER		11,577.00	21.89	15.00	3.56
C0502-085		US 50 MM 201.8 MONARCH AVALAN	06/27/19	51.00	50.00	427.71	140.71
		WEIGHTED AVERAGE FOR THE SECOND QUARTER		51.00	50.00	427.71	140.71
		WEIGHTED AVERAGE FOR THE YEAR		11,628.00	22.01	15.73	4.16
=====	603-00001	Annular Space Grouting		Cubic Yard	=====		
NHPP1601-073		US 160 PASSING LANE NORTH OF	03/07/19	114.00	300.00	420.00	390.00
		WEIGHTED AVERAGE FOR THE FIRST QUARTER		114.00	300.00	420.00	390.00
NHPP160A-030		US160 MM 43.2, 150.4, 156.3,	06/20/19	117.00	700.00	376.46	425.00
		WEIGHTED AVERAGE FOR THE SECOND QUARTER		117.00	700.00	376.46	425.00
		WEIGHTED AVERAGE FOR THE YEAR		231.00	502.60	397.94	407.73
=====	603-00024	Prep Culvert Pipe (24 In)		Lin Foot	=====		
FBR0341-087		US 34 OVER NORTH FORK CO RIVE	01/10/19	86.00	100.00	80.51	57.20
		WEIGHTED AVERAGE FOR THE FIRST QUARTER		86.00	100.00	80.51	57.20
		WEIGHTED AVERAGE FOR THE YEAR		86.00	100.00	80.51	57.20
=====	603-00025	Culvert Lining (24 Inch) (Special)		Lin Foot	=====		
FBR0341-087		US 34 OVER NORTH FORK CO RIVE	01/10/19	86.00	500.00	504.05	191.36
		WEIGHTED AVERAGE FOR THE FIRST QUARTER		86.00	500.00	504.05	191.36
		WEIGHTED AVERAGE FOR THE YEAR		86.00	500.00	504.05	191.36

COLORADO DEPARTMENT OF TRANSPORTATION
 ITEM UNIT COSTS BY PROJECTS -- 2019 COST DATA

13:44 Wednesday, August 7, 2019 171

PROJECT NUMBER	ITEM NUMBER/ PROJECT LOCATION	ITEM DESCRIPTION/ PROJECT LOCATION	DATE LET	UNIT/ QUANTITY	ENGR. EST.	AVERAGE BID	AWARDED BID
=====	603-00036	Culvert Lining (36 In)		Lin Foot	=====		
NHPP160A-030		US160 MM 43.2, 150.4, 156.3,	06/20/19	112.00	500.00	392.37	390.00
	WEIGHTED AVERAGE FOR THE SECOND QUARTER			112.00	500.00	392.37	390.00
	WEIGHTED AVERAGE FOR THE YEAR			112.00	500.00	392.37	390.00
=====	603-00048	Culvert Lining (48 In)		Lin Foot	=====		
NHPP160A-030		US160 MM 43.2, 150.4, 156.3,	06/20/19	374.00	600.00	498.34	450.00
	WEIGHTED AVERAGE FOR THE SECOND QUARTER			374.00	600.00	498.34	450.00
	WEIGHTED AVERAGE FOR THE YEAR			374.00	600.00	498.34	450.00
=====	603-00051	Culvert Lining (48 In) (Slip)		Lin Foot	=====		
NHPP1601-073		US 160 PASSING LANE NORTH OF	03/07/19	334.00	500.00	873.50	647.00
	WEIGHTED AVERAGE FOR THE FIRST QUARTER			334.00	500.00	873.50	647.00
	WEIGHTED AVERAGE FOR THE YEAR			334.00	500.00	873.50	647.00
=====	603-01125	12 In RCP (CIP)		Lin Foot	=====		
SHER100-289		INTERSECTIONS @ SH83 & LONGS	01/03/19	147.00	100.00	73.40	105.00
STR0241-062		US 24 143.4 - 148	01/24/19	23.00	135.00	143.00	80.00
NHPP1601-073		US 160 PASSING LANE NORTH OF	03/07/19	100.00	175.00	167.00	194.00
	WEIGHTED AVERAGE FOR THE FIRST QUARTER			270.00	130.76	96.83	135.83
	WEIGHTED AVERAGE FOR THE YEAR			270.00	130.76	96.83	135.83
=====	603-01150	15 In RCP		Lin Foot	=====		
MTCE0641-103		MTCE R3 FY20 SH 64 RANGELY PE	05/02/19	31.00	200.00	101.00	77.00
	WEIGHTED AVERAGE FOR THE SECOND QUARTER			31.00	200.00	101.00	77.00
	WEIGHTED AVERAGE FOR THE YEAR			31.00	200.00	101.00	77.00

COLORADO DEPARTMENT OF TRANSPORTATION
 ITEM UNIT COSTS BY PROJECTS -- 2019 COST DATA

13:44 Wednesday, August 7, 2019 172

PROJECT NUMBER	ITEM NUMBER/ PROJECT LOCATION	ITEM DESCRIPTION/ PROJECT LOCATION	DATE LET	UNIT/ QUANTITY	ENGR. EST.	AVERAGE BID	AWARDED BID
=====	603-01155	15 In RCP (CIP)		Lin Foot	=====		
STR0241-062		US 24 143.4 - 148	01/24/19	45.00	145.00	154.67	85.00
STAM086-075		SH96A ABRIENDO - ORMAN SAFETY	01/31/19	27.00	200.00	591.50	417.00
		WEIGHTED AVERAGE FOR THE FIRST QUARTER		72.00	165.63	318.48	209.50
NHPP0703-445		I-70 WESTBOUND PEAK PERIOD SH	04/25/19	179.00	86.00	118.67	107.00
STR 141A-040		R5 YEAR 4 BRDG PREV MAINT RAM	06/20/19	200.00	100.00	205.00	150.00
		WEIGHTED AVERAGE FOR THE SECOND QUARTER		379.00	93.39	155.52	129.69
		WEIGHTED AVERAGE FOR THE YEAR		451.00	104.92	186.05	142.43
=====	603-01180	18 In RCP		Lin Foot	=====		
STAR200-242		R2 NORTH PROGRAM WALL REPAIRS	01/03/19	30.00	150.00	163.63	204.00
FBR0253-247		I25 AT VINE DRIVE BRIDGE REPL	03/07/19	865.00	100.00	78.90	57.00
NHPP0503-087		US 50 PASSING LANES EAST OF S	03/21/19	185.00	100.00	115.00	120.00
		WEIGHTED AVERAGE FOR THE FIRST QUARTER		1,080.00	101.39	80.75	71.88
MTCE0641-103		MTCE R3 FY20 SH 64 RANGELY PE	05/02/19	30.00	250.00	108.50	82.00
		WEIGHTED AVERAGE FOR THE SECOND QUARTER		30.00	250.00	108.50	82.00
		WEIGHTED AVERAGE FOR THE YEAR		1,110.00	105.41	80.92	72.15
=====	603-01185	18 In RCP (CIP)		Lin Foot	=====		
SHER100-289		INTERSECTIONS @ SH83 & LONGS	01/03/19	724.00	130.00	71.50	85.00
ER119A-065		PR SH 119A BOULDER CANYON	01/03/19	362.00	100.00	172.74	100.00
STA119A-069		SH 119: NEDERLAND - EAST					
STR0241-062		US 24 143.4 - 148	01/24/19	39.00	155.00	161.67	105.00
ER072A-040		PR SH72A FLOOD PERMANENT REPA	01/31/19	239.00	95.00	150.66	94.00
NHPP072A-041		PR SH72A FLOOD PERMANENT REPA					
NHPP1601-073		US 160 PASSING LANE NORTH OF	03/07/19	116.00	250.00	180.00	200.00
NHPP050A-033		US50 West of Delta EB Lanes R	03/14/19	192.00	80.00	173.33	185.00

COLORADO DEPARTMENT OF TRANSPORTATION
 ITEM UNIT COSTS BY PROJECTS -- 2019 COST DATA

13:44 Wednesday, August 7, 2019 173

PROJECT NUMBER	ITEM NUMBER/ PROJECT LOCATION	ITEM DESCRIPTION/ PROJECT LOCATION	DATE LET	UNIT/ QUANTITY	ENGR. EST.	AVERAGE BID	AWARDED BID
=====	603-01185	18 In RCP (CIP)		Lin Foot	=====	=====	=====
SHER100-308		MIDPOINT - SIGNAL CONST PACKA	03/21/19	20.00	100.00	246.50	193.00
		WEIGHTED AVERAGE FOR THE FIRST QUARTER		1,692.00	121.41	131.56	110.45
NHPP0703-445		I-70 WESTBOUND PEAK PERIOD SH	04/25/19	5,495.00	93.00	133.00	105.00
		WEIGHTED AVERAGE FOR THE SECOND QUARTER		5,495.00	93.00	133.00	105.00
		WEIGHTED AVERAGE FOR THE YEAR		7,187.00	99.69	132.45	106.28
=====	603-01240	24 In RCP		Lin Foot	=====	=====	=====
SHE2254-090		Colfax & I-225, Colfax & Cham	03/07/19	14.00	100.00	1012.50	475.00
NHPP0503-087		US 50 PASSING LANES EAST OF S	03/21/19	97.00	120.00	123.00	126.00
		WEIGHTED AVERAGE FOR THE FIRST QUARTER		111.00	117.48	235.19	170.02
MTCE0641-103		MTCE R3 FY20 SH 64 RANGELY PE	05/02/19	24.00	300.00	131.00	92.00
NHPP0703-442		I-70 SILVERPLUME SOUNDWALL AN	06/13/19	139.00	150.00	139.59	169.00
		WEIGHTED AVERAGE FOR THE SECOND QUARTER		163.00	172.09	139.23	157.66
		WEIGHTED AVERAGE FOR THE YEAR		274.00	149.96	154.65	162.67
=====	603-01245	24 In RCP (CIP)		Lin Foot	=====	=====	=====
ER119A-065		PR SH 119A BOULDER CANYON	01/03/19	96.00	125.00	222.02	160.00
STA119A-069		SH 119: NEDERLAND - EAST					
STR0241-062		US 24 143.4 - 148	01/24/19	1,002.00	165.00	179.00	115.00
		WEIGHTED AVERAGE FOR THE FIRST QUARTER		1,098.00	161.50	187.75	118.93
NHPP0703-445		I-70 WESTBOUND PEAK PERIOD SH	04/25/19	433.00	100.00	211.67	197.00
		WEIGHTED AVERAGE FOR THE SECOND QUARTER		433.00	100.00	211.67	197.00
		WEIGHTED AVERAGE FOR THE YEAR		1,531.00	144.11	193.88	141.01

COLORADO DEPARTMENT OF TRANSPORTATION
 ITEM UNIT COSTS BY PROJECTS -- 2019 COST DATA

13:44 Wednesday, August 7, 2019 174

PROJECT NUMBER	ITEM NUMBER/ PROJECT LOCATION	ITEM DESCRIPTION/ PROJECT LOCATION	DATE LET	UNIT/ QUANTITY	ENGR. EST.	AVERAGE BID	AWARDED BID
=====	603-01305	30 In RCP (CIP)		Lin Foot	=====		
STAM086-075		SH96A ABRIENDO - ORMAN SAFETY	01/31/19	37.00	400.00	630.67	602.00
		WEIGHTED AVERAGE FOR THE FIRST QUARTER		37.00	400.00	630.67	602.00
		WEIGHTED AVERAGE FOR THE YEAR		37.00	400.00	630.67	602.00
=====	603-01360	36 In RCP		Lin Foot	=====		
NHPP0503-087		US 50 PASSING LANES EAST OF S	03/21/19	389.00	160.00	214.00	250.00
		WEIGHTED AVERAGE FOR THE FIRST QUARTER		389.00	160.00	214.00	250.00
		WEIGHTED AVERAGE FOR THE YEAR		389.00	160.00	214.00	250.00
=====	603-01365	36 In RCP (CIP)		Lin Foot	=====		
ER119A-065		PR SH 119A BOULDER CANYON	01/03/19	41.00	150.00	335.71	210.00
STAL19A-069		SH 119: NEDERLAND - EAST					
ER072A-040		PR SH72A FLOOD PERMANENT REPA	01/31/19	910.00	135.00	255.04	255.00
NHPP072A-041		PR SH72A FLOOD PERMANENT REPA					
NHPP145A-065		SH 145 PASSING LANES AT DEEP	02/14/19	860.00	274.00	256.23	170.00
NHPP1601-073		US 160 PASSING LANE NORTH OF	03/07/19	536.00	190.00	338.00	396.00
		WEIGHTED AVERAGE FOR THE FIRST QUARTER		2,347.00	198.76	262.29	255.27
		WEIGHTED AVERAGE FOR THE YEAR		2,347.00	198.76	262.29	255.27
=====	603-01425	42 In RCP (CIP)		Lin Foot	=====		
ER119A-065		PR SH 119A BOULDER CANYON	01/03/19	32.00	250.00	295.47	170.00
STAL19A-069		SH 119: NEDERLAND - EAST					
STAM086-075		SH96A ABRIENDO - ORMAN SAFETY	01/31/19	84.00	500.00	743.67	702.00
		WEIGHTED AVERAGE FOR THE FIRST QUARTER		116.00	431.03	517.80	555.24
		WEIGHTED AVERAGE FOR THE YEAR		116.00	431.03	517.80	555.24
=====	603-01485	48 In RCP (CIP)		Lin Foot	=====		
ER119A-065		PR SH 119A BOULDER CANYON	01/03/19	247.00	275.00	355.17	320.00

COLORADO DEPARTMENT OF TRANSPORTATION
 ITEM UNIT COSTS BY PROJECTS -- 2019 COST DATA

13:44 Wednesday, August 7, 2019 175

PROJECT NUMBER	ITEM NUMBER/ PROJECT LOCATION	ITEM DESCRIPTION/ PROJECT LOCATION	DATE LET	UNIT/ QUANTITY	ENGR. EST.	AVERAGE BID	AWARDED BID
=====	603-01485	48 In RCP (CIP)		Lin Foot	=====		
STA119A-069		SH 119: NEDERLAND - EAST					
ER072A-040		PR SH72A FLOOD PERMANENT REPA	01/31/19	154.00	165.00	310.22	230.00
NHPP072A-041		PR SH72A FLOOD PERMANENT REPA					
	WEIGHTED	AVERAGE FOR THE FIRST QUARTER		401.00	232.76	333.45	285.44
		WEIGHTED AVERAGE FOR THE YEAR		401.00	232.76	333.45	285.44
=====	603-01605	60 In RCP (CIP)		Lin Foot	=====		
STAM086-075		SH96A ABRIENDO - ORMAN SAFETY	01/31/19	112.00	600.00	984.67	1045.00
	WEIGHTED	AVERAGE FOR THE FIRST QUARTER		112.00	600.00	984.67	1045.00
		WEIGHTED AVERAGE FOR THE YEAR		112.00	600.00	984.67	1045.00
=====	603-01720	72 In RCP		Lin Foot	=====		
NHPP0503-087		US 50 PASSING LANES EAST OF S	03/21/19	88.00	1000.00	533.00	600.00
	WEIGHTED	AVERAGE FOR THE FIRST QUARTER		88.00	1000.00	533.00	600.00
		WEIGHTED AVERAGE FOR THE YEAR		88.00	1000.00	533.00	600.00
=====	603-01845	84 In RCP (CIP)		Lin Foot	=====		
NH2871-035		US 287 PASSING LANES SOUTH OF	02/07/19	8.00	1000.00	926.12	1100.01
	WEIGHTED	AVERAGE FOR THE FIRST QUARTER		8.00	1000.00	926.12	1100.01
		WEIGHTED AVERAGE FOR THE YEAR		8.00	1000.00	926.12	1100.01
=====	603-02185	23x14 In RCP (CIP)		Lin Foot	=====		
STR0241-062		US 24 143.4 - 148	01/24/19	264.00	200.00	245.00	125.00
NHPP1601-073		US 160 PASSING LANE NORTH OF	03/07/19	372.00	120.00	218.00	196.00
	WEIGHTED	AVERAGE FOR THE FIRST QUARTER		636.00	153.21	231.92	166.53
		WEIGHTED AVERAGE FOR THE YEAR		636.00	153.21	231.92	166.53

COLORADO DEPARTMENT OF TRANSPORTATION
 ITEM UNIT COSTS BY PROJECTS -- 2019 COST DATA

13:44 Wednesday, August 7, 2019 176

PROJECT NUMBER	ITEM NUMBER/ PROJECT LOCATION	ITEM DESCRIPTION/ PROJECT LOCATION	DATE LET	UNIT/ QUANTITY	ENGR. EST.	AVERAGE BID	AWARDED BID
=====	603-02240	30x19 In RCP		Lin Foot	=====		
NHPP0503-087		US 50 PASSING LANES EAST OF S	03/21/19	77.00	150.00	168.00	170.00
		WEIGHTED AVERAGE FOR THE FIRST QUARTER		77.00	150.00	168.00	170.00
NHPP0703-442		I-70 SILVERPLUME SOUNDWALL AN	06/13/19	72.00	150.00	235.92	198.00
		WEIGHTED AVERAGE FOR THE SECOND QUARTER		72.00	150.00	235.92	198.00
		WEIGHTED AVERAGE FOR THE YEAR		149.00	150.00	221.59	183.53
=====	603-02360	45x29 In RCP		Lin Foot	=====		
NHPP0503-087		US 50 PASSING LANES EAST OF S	03/21/19	70.00	300.00	325.00	320.00
		WEIGHTED AVERAGE FOR THE FIRST QUARTER		70.00	300.00	325.00	320.00
		WEIGHTED AVERAGE FOR THE YEAR		70.00	300.00	325.00	320.00
=====	603-02365	45x29 In RCP (CIP)		Lin Foot	=====		
NHPP1601-073		US 160 PASSING LANE NORTH OF	03/07/19	88.00	200.00	375.00	400.00
		WEIGHTED AVERAGE FOR THE FIRST QUARTER		88.00	200.00	375.00	400.00
		WEIGHTED AVERAGE FOR THE YEAR		88.00	200.00	375.00	400.00
=====	603-02425	53x34 In RCP (CIP)		Lin Foot	=====		
NHPP1601-073		US 160 PASSING LANE NORTH OF	03/07/19	84.00	200.00	470.00	500.00
		WEIGHTED AVERAGE FOR THE FIRST QUARTER		84.00	200.00	470.00	500.00
		WEIGHTED AVERAGE FOR THE YEAR		84.00	200.00	470.00	500.00
=====	603-05015	15 In RCES		Each	=====		
NHPP0703-445		I-70 WESTBOUND PEAK PERIOD SH	04/25/19	2.00	1200.00	1303.67	1961.00
		WEIGHTED AVERAGE FOR THE SECOND QUARTER		2.00	1200.00	1303.67	1961.00
		WEIGHTED AVERAGE FOR THE YEAR		2.00	1200.00	1303.67	1961.00

COLORADO DEPARTMENT OF TRANSPORTATION
 ITEM UNIT COSTS BY PROJECTS -- 2019 COST DATA

13:44 Wednesday, August 7, 2019 177

PROJECT NUMBER	ITEM NUMBER/ PROJECT LOCATION	ITEM DESCRIPTION/ PROJECT LOCATION	DATE LET	UNIT/ QUANTITY	ENGR. EST.	AVERAGE BID	AWARDED BID
=====	603-05018	18 In RCES		Each =====			
ER119A-065		PR SH 119A BOULDER CANYON	01/03/19	3.00	1300.00	1865.18	950.00
STA119A-069		SH 119: NEDERLAND - EAST					
ER072A-040		PR SH72A FLOOD PERMANENT REPA	01/31/19	1.00	900.00	1850.49	1800.00
NHPP072A-041		PR SH72A FLOOD PERMANENT REPA					
NHPP1601-073		US 160 PASSING LANE NORTH OF	03/07/19	2.00	1500.00	1550.00	1500.00
FBR0253-247		I25 AT VINE DRIVE BRIDGE REPL	03/07/19	5.00	1250.00	1203.02	1050.00
NHPP0503-087		US 50 PASSING LANES EAST OF S	03/21/19	10.00	1000.00	2150.00	1800.00
		WEIGHTED AVERAGE FOR THE FIRST QUARTER		21.00	1145.24	1585.53	1471.43
NHPP0703-445		I-70 WESTBOUND PEAK PERIOD SH	04/25/19	3.00	1200.00	1370.33	1901.00
		WEIGHTED AVERAGE FOR THE SECOND QUARTER		3.00	1200.00	1370.33	1901.00
		WEIGHTED AVERAGE FOR THE YEAR		24.00	1152.08	1569.91	1525.13
=====	603-05024	24 In RCES		Each =====			
ER119A-065		PR SH 119A BOULDER CANYON	01/03/19	1.00	1400.00	2071.92	1100.00
STA119A-069		SH 119: NEDERLAND - EAST					
STR0241-062		US 24 143.4 - 148	01/24/19	1.00	2200.00	1510.00	1800.00
SHE2254-090		Colfax & I-225, Colfax & Cham	03/07/19	1.00	2000.00	1650.00	1100.00
NHPP0503-087		US 50 PASSING LANES EAST OF S	03/21/19	2.00	1500.00	2350.00	2000.00
		WEIGHTED AVERAGE FOR THE FIRST QUARTER		5.00	1720.00	1988.55	1600.00
NHPP0703-445		I-70 WESTBOUND PEAK PERIOD SH	04/25/19	2.00	1500.00	1505.33	1927.00
NHPP0703-442		I-70 SILVERPLUME SOUNDWALL AN	06/13/19	1.00	900.00	2461.47	2330.00
		WEIGHTED AVERAGE FOR THE SECOND QUARTER		3.00	1300.00	2051.70	2061.33
		WEIGHTED AVERAGE FOR THE YEAR		8.00	1562.50	2017.07	1773.00
=====	603-05036	36 In RCES		Each =====			
ER119A-065		PR SH 119A BOULDER CANYON	01/03/19	2.00	1600.00	5305.39	5300.00

COLORADO DEPARTMENT OF TRANSPORTATION
ITEM UNIT COSTS BY PROJECTS -- 2019 COST DATA

13:44 Wednesday, August 7, 2019 178

PROJECT NUMBER	ITEM NUMBER/ PROJECT LOCATION	ITEM DESCRIPTION/ PROJECT LOCATION	DATE LET	UNIT/ QUANTITY	ENGR. EST.	AVERAGE BID	AWARDED BID
=====	603-05036	36 In RCES		Each =====			
STA119A-069		SH 119: NEDERLAND - EAST					
ER072A-040		PR SH72A FLOOD PERMANENT REPA	01/31/19	19.00	2100.00	2675.64	2400.00
NHPP072A-041		PR SH72A FLOOD PERMANENT REPA					
NHPP145A-065		SH 145 PASSING LANES AT DEEP	02/14/19	8.00	3000.00	3397.40	3000.00
NHPP1601-073		US 160 PASSING LANE NORTH OF	03/07/19	8.00	2000.00	2575.00	2150.00
NHPP0503-087		US 50 PASSING LANES EAST OF S	03/21/19	6.00	2200.00	3450.00	3000.00
		WEIGHTED AVERAGE FOR THE FIRST QUARTER		43.00	2239.53	2927.65	2683.72
		WEIGHTED AVERAGE FOR THE YEAR		43.00	2239.53	2927.65	2683.72
=====	603-05042	42 In RCES		Each =====			
ER119A-065		PR SH 119A BOULDER CANYON	01/03/19	2.00	1700.00	7879.74	6800.00
STA119A-069		SH 119: NEDERLAND - EAST					
		WEIGHTED AVERAGE FOR THE FIRST QUARTER		2.00	1700.00	7879.74	6800.00
		WEIGHTED AVERAGE FOR THE YEAR		2.00	1700.00	7879.74	6800.00
=====	603-05048	48 In RCES		Each =====			
ER119A-065		PR SH 119A BOULDER CANYON	01/03/19	1.00	1900.00	6728.79	8000.00
STA119A-069		SH 119: NEDERLAND - EAST					
ER072A-040		PR SH72A FLOOD PERMANENT REPA	01/31/19	3.00	2300.00	3127.34	2600.00
NHPP072A-041		PR SH72A FLOOD PERMANENT REPA					
		WEIGHTED AVERAGE FOR THE FIRST QUARTER		4.00	2200.00	3782.15	3950.00
		WEIGHTED AVERAGE FOR THE YEAR		4.00	2200.00	3782.15	3950.00
=====	603-05118	23x14 In RCES		Each =====			
STR0241-062		US 24 143.4 - 148	01/24/19	4.00	1500.00	1613.33	1850.00
NHPP1601-073		US 160 PASSING LANE NORTH OF	03/07/19	22.00	1800.00	2300.00	2800.00
		WEIGHTED AVERAGE FOR THE FIRST QUARTER		26.00	1753.85	2152.86	2653.85
		WEIGHTED AVERAGE FOR THE YEAR		26.00	1753.85	2152.86	2653.85
=====	603-05124	30x19 In RCES		Each =====			
NHPP0503-087		US 50 PASSING LANES EAST OF S	03/21/19	2.00	2500.00	2750.00	2500.00
		WEIGHTED AVERAGE FOR THE FIRST QUARTER		2.00	2500.00	2750.00	2500.00

COLORADO DEPARTMENT OF TRANSPORTATION
 ITEM UNIT COSTS BY PROJECTS -- 2019 COST DATA

13:44 Wednesday, August 7, 2019 179

PROJECT NUMBER	ITEM NUMBER/ PROJECT LOCATION	ITEM DESCRIPTION/ PROJECT LOCATION	DATE LET	UNIT/ QUANTITY	ENGR. EST.	AVERAGE BID	AWARDED BID
=====	603-05124	30x19 In RCES		Each	=====		
NHPP0703-442		I-70 SILVERPLUME SOUNDWALL AN	06/13/19	1.00	2000.00	2641.93	2790.00
		WEIGHTED AVERAGE FOR THE SECOND QUARTER		1.00	2000.00	2641.93	2790.00
		WEIGHTED AVERAGE FOR THE YEAR		3.00	2333.33	2677.95	2596.67
=====	603-05136	45x29 In RCES		Each	=====		
NHPP1601-073		US 160 PASSING LANE NORTH OF	03/07/19	1.00	1700.00	2687.50	2375.00
NHPP0503-087		US 50 PASSING LANES EAST OF S	03/21/19	1.00	5000.00	4750.00	4000.00
		WEIGHTED AVERAGE FOR THE FIRST QUARTER		2.00	3350.00	3718.75	3187.50
		WEIGHTED AVERAGE FOR THE YEAR		2.00	3350.00	3718.75	3187.50
=====	603-05142	53x34 In RCES		Each	=====		
NHPP1601-073		US 160 PASSING LANE NORTH OF	03/07/19	1.00	3000.00	4700.00	5400.00
		WEIGHTED AVERAGE FOR THE FIRST QUARTER		1.00	3000.00	4700.00	5400.00
		WEIGHTED AVERAGE FOR THE YEAR		1.00	3000.00	4700.00	5400.00
=====	603-10180	18 In CSP		Lin Foot	=====		
NHPP0701-241		I-70 TRUCK PARKING GARFIELD C	01/17/19	40.00	190.00	148.88	175.00
		WEIGHTED AVERAGE FOR THE FIRST QUARTER		40.00	190.00	148.88	175.00
NHPP0703-445		I-70 WESTBOUND PEAK PERIOD SH	04/25/19	81.00	80.00	141.67	237.00
		WEIGHTED AVERAGE FOR THE SECOND QUARTER		81.00	80.00	141.67	237.00
		WEIGHTED AVERAGE FOR THE YEAR		121.00	116.36	144.92	216.50
=====	603-10240	24 In CSP		Lin Foot	=====		
ER119A-065		PR SH 119A BOULDER CANYON	01/03/19	15.00	110.00	224.86	98.00

COLORADO DEPARTMENT OF TRANSPORTATION
 ITEM UNIT COSTS BY PROJECTS -- 2019 COST DATA

13:44 Wednesday, August 7, 2019 180

PROJECT NUMBER	ITEM NUMBER/ PROJECT LOCATION	ITEM DESCRIPTION/ PROJECT LOCATION	DATE LET	UNIT/ QUANTITY	ENGR. EST.	AVERAGE BID	AWARDED BID
===== 603-10240	24 In CSP			Lin Foot			
STA119A-069	SH 119: NEDERLAND - EAST						
FBR0253-247	I25 AT VINE DRIVE BRIDGE REPL	03/07/19		21.00	90.00	94.57	82.00
	WEIGHTED AVERAGE FOR THE FIRST QUARTER			36.00	98.33	139.11	88.67
NHPP0703-445	I-70 WESTBOUND PEAK PERIOD SH	04/25/19		69.00	100.00	129.00	92.00
FBR0063-057	US-6 F-09-K BRIDGE OVER CASTL	05/30/19		25.00	150.00	220.88	91.75
	WEIGHTED AVERAGE FOR THE SECOND QUARTER			94.00	113.30	146.87	91.93
	WEIGHTED AVERAGE FOR THE YEAR			130.00	109.15	142.39	91.03
===== 603-10300	30 In CSP			Lin Foot			
NHPP0703-445	I-70 WESTBOUND PEAK PERIOD SH	04/25/19		19.00	150.00	139.33	99.00
	WEIGHTED AVERAGE FOR THE SECOND QUARTER			19.00	150.00	139.33	99.00
	WEIGHTED AVERAGE FOR THE YEAR			19.00	150.00	139.33	99.00
===== 603-10360	36 In CSP			Lin Foot			
STR0241-062	US 24 143.4 - 148	01/24/19		7.00	180.00	284.67	150.00
NH2871-035	US 287 PASSING LANES SOUTH OF	02/07/19		8.00	500.00	293.03	510.21
	WEIGHTED AVERAGE FOR THE FIRST QUARTER			15.00	350.67	289.72	342.11
NHPP0703-445	I-70 WESTBOUND PEAK PERIOD SH	04/25/19		46.00	175.00	139.00	117.00
	WEIGHTED AVERAGE FOR THE SECOND QUARTER			46.00	175.00	139.00	117.00
	WEIGHTED AVERAGE FOR THE YEAR			61.00	218.20	180.82	172.36
===== 603-30018	18 In SES			Each			
SHER100-289	INTERSECTIONS @ SH83 & LONGS	01/03/19		1.00	200.00	588.40	660.00
	WEIGHTED AVERAGE FOR THE FIRST QUARTER			1.00	200.00	588.40	660.00

COLORADO DEPARTMENT OF TRANSPORTATION
 ITEM UNIT COSTS BY PROJECTS -- 2019 COST DATA

13:44 Wednesday, August 7, 2019 181

PROJECT NUMBER	ITEM NUMBER/ PROJECT LOCATION	ITEM DESCRIPTION/ PROJECT LOCATION	DATE LET	UNIT/ QUANTITY	ENGR. EST.	AVERAGE BID	AWARDED BID
=====	603-30018	18 In SES		Each	=====		
NHPP0703-445		I-70 WESTBOUND PEAK PERIOD SH	04/25/19	2.00	700.00	459.00	392.00
	WEIGHTED AVERAGE FOR THE SECOND QUARTER			2.00	700.00	459.00	392.00
	WEIGHTED AVERAGE FOR THE YEAR			3.00	533.33	517.82	481.33
=====	603-30024	24 In SES		Each	=====		
ER119A-065		PR SH 119A BOULDER CANYON	01/03/19	3.00	690.00	1133.87	650.00
STA119A-069		SH 119: NEDERLAND - EAST					
ER072A-040		PR SH72A FLOOD PERMANENT REPA	01/31/19	1.00	500.00	1528.47	2010.00
NHPP072A-041		PR SH72A FLOOD PERMANENT REPA					
FBR0253-247		I25 AT VINE DRIVE BRIDGE REPL	03/07/19	1.00	500.00	788.09	800.00
	WEIGHTED AVERAGE FOR THE FIRST QUARTER			5.00	614.00	1153.69	952.00
NHPP0703-445		I-70 WESTBOUND PEAK PERIOD SH	04/25/19	4.00	800.00	537.67	478.00
FBR0063-057		US-6 F-09-K BRIDGE OVER CASTL	05/30/19	1.00	2000.00	2180.00	360.00
	WEIGHTED AVERAGE FOR THE SECOND QUARTER			5.00	1040.00	772.29	454.40
	WEIGHTED AVERAGE FOR THE YEAR			10.00	827.00	1066.15	703.20
=====	603-30036	36 In SES		Each	=====		
NHPP0703-445		I-70 WESTBOUND PEAK PERIOD SH	04/25/19	2.00	1000.00	821.67	655.00
	WEIGHTED AVERAGE FOR THE SECOND QUARTER			2.00	1000.00	821.67	655.00
	WEIGHTED AVERAGE FOR THE YEAR			2.00	1000.00	821.67	655.00
=====	603-33036	36 In Pipe Safety End Treat		Each	=====		
NH2871-035		US 287 PASSING LANES SOUTH OF	02/07/19	1.00	3000.00	1605.16	1200.01
	WEIGHTED AVERAGE FOR THE FIRST QUARTER			1.00	3000.00	1605.16	1200.01
	WEIGHTED AVERAGE FOR THE YEAR			1.00	3000.00	1605.16	1200.01

COLORADO DEPARTMENT OF TRANSPORTATION
 ITEM UNIT COSTS BY PROJECTS -- 2019 COST DATA

13:44 Wednesday, August 7, 2019 182

PROJECT NUMBER	ITEM NUMBER/ PROJECT LOCATION	ITEM DESCRIPTION/ PROJECT LOCATION	DATE LET	UNIT/ QUANTITY	ENGR. EST.	AVERAGE BID	AWARDED BID
=====	603-50006	6 In Plastic Pipe		Lin Foot	=====		
ER119A-065 STA119A-069		PR SH 119A BOULDER CANYON SH 119: NEDERLAND - EAST	01/03/19	159.00	40.00	58.09	28.00
	WEIGHTED AVERAGE FOR THE FIRST QUARTER			159.00	40.00	58.09	28.00
	WEIGHTED AVERAGE FOR THE YEAR			159.00	40.00	58.09	28.00
=====	603-50012	12 In Plastic Pipe		Lin Foot	=====		
STAR200-242		R2 NORTH PROGRAM WALL REPAIRS	01/03/19	28.00	70.00	96.87	128.00
	WEIGHTED AVERAGE FOR THE FIRST QUARTER			28.00	70.00	96.87	128.00
	WEIGHTED AVERAGE FOR THE YEAR			28.00	70.00	96.87	128.00
=====	603-70808	8x8 Ft CBC (Precast)		Lin Foot	=====		
STR0132-021 STA0131-070 HMA ALT STA0131-070 PCCP ALT		SH 13-MOFFAT COUNTY-CR 3 SOUT SH 13 CR 5 NORTH AND SOUTH SH 13 CR 5 NORTH AND SOUTH	01/10/19 03/28/19	206.00 594.00	1200.00 1200.00	1407.00 1331.85	1590.00 1320.00
	WEIGHTED AVERAGE FOR THE FIRST QUARTER			800.00	1200.00	1359.38	1430.58
	WEIGHTED AVERAGE FOR THE YEAR			800.00	1200.00	1359.38	1430.58
=====	603-70905	9x5 Ft CBC (Precast)		Lin Foot	=====		
NHPP1601-073		US 160 PASSING LANE NORTH OF	03/07/19	130.00	1400.00	1490.00	1580.00
	WEIGHTED AVERAGE FOR THE FIRST QUARTER			130.00	1400.00	1490.00	1580.00
	WEIGHTED AVERAGE FOR THE YEAR			130.00	1400.00	1490.00	1580.00
=====	603-71006	10x6 Ft CBC (Precast)		Lin Foot	=====		
NHPP145A-065		SH 145 PASSING LANES AT DEEP	02/14/19	96.00	1200.00	2463.13	2300.00
	WEIGHTED AVERAGE FOR THE FIRST QUARTER			96.00	1200.00	2463.13	2300.00
	WEIGHTED AVERAGE FOR THE YEAR			96.00	1200.00	2463.13	2300.00

COLORADO DEPARTMENT OF TRANSPORTATION
ITEM UNIT COSTS BY PROJECTS -- 2019 COST DATA

13:44 Wednesday, August 7, 2019 183

PROJECT NUMBER	ITEM NUMBER/ PROJECT LOCATION	ITEM DESCRIPTION/ PROJECT LOCATION	DATE LET	UNIT/ QUANTITY	ENGR. EST.	AVERAGE BID	AWARDED BID
=====	603-71609	16x8 Ft CBC (Precast)		Lin Foot	=====		
ER119A-065 STA119A-069		PR SH 119A BOULDER CANYON SH 119: NEDERLAND - EAST	01/03/19	72.00	3850.00	2158.97	1680.00
		WEIGHTED AVERAGE FOR THE FIRST QUARTER		72.00	3850.00	2158.97	1680.00
		WEIGHTED AVERAGE FOR THE YEAR		72.00	3850.00	2158.97	1680.00
=====	603-71610	16x10 Ft CBC (Precast)		Lin Foot	=====		
ER119A-065 STA119A-069		PR SH 119A BOULDER CANYON SH 119: NEDERLAND - EAST	01/03/19	120.00	4250.00	2167.39	1700.00
		WEIGHTED AVERAGE FOR THE FIRST QUARTER		120.00	4250.00	2167.39	1700.00
		WEIGHTED AVERAGE FOR THE YEAR		120.00	4250.00	2167.39	1700.00
=====	603-72011	20x10 Ft CBC (Precast)		Lin Foot	=====		
FBR0063-057		US-6 F-09-K BRIDGE OVER CASTL	05/30/19	67.00	9000.00	3700.00	3900.00
		WEIGHTED AVERAGE FOR THE SECOND QUARTER		67.00	9000.00	3700.00	3900.00
		WEIGHTED AVERAGE FOR THE YEAR		67.00	9000.00	3700.00	3900.00
=====	603-72100	CBC Wingwall (Precast)		Each	=====		
FBR0063-057		US-6 F-09-K BRIDGE OVER CASTL	05/30/19	4.00	20000.00	27112.50	29225.00
		WEIGHTED AVERAGE FOR THE SECOND QUARTER		4.00	20000.00	27112.50	29225.00
		WEIGHTED AVERAGE FOR THE YEAR		4.00	20000.00	27112.50	29225.00
=====	603-83009	8 In Sewer Pipe (Spec)		Lin Foot	=====		
NHPP0703-445		I-70 WESTBOUND PEAK PERIOD SH	04/25/19	1,363.00	120.00	163.33	11.00
		WEIGHTED AVERAGE FOR THE SECOND QUARTER		1,363.00	120.00	163.33	11.00
		WEIGHTED AVERAGE FOR THE YEAR		1,363.00	120.00	163.33	11.00

COLORADO DEPARTMENT OF TRANSPORTATION
 ITEM UNIT COSTS BY PROJECTS -- 2019 COST DATA

13:44 Wednesday, August 7, 2019 184

PROJECT NUMBER	ITEM NUMBER/ PROJECT LOCATION	ITEM DESCRIPTION/ PROJECT LOCATION	DATE LET	UNIT/ QUANTITY	ENGR. EST.	AVERAGE BID	AWARDED BID
===== 604-00305		Inlet Ty C (5 Ft)		Each =====			
ER119A-065		PR SH 119A BOULDER CANYON	01/03/19	10.00	3900.00	4519.99	3800.00
STA119A-069		SH 119: NEDERLAND - EAST					
ER072A-040		PR SH72A FLOOD PERMANENT REPA	01/31/19	1.00	3500.00	4573.01	8500.00
NHPP072A-041		PR SH72A FLOOD PERMANENT REPA					
NHPP050A-033		US50 West of Delta EB Lanes R	03/14/19	2.00	4000.00	3693.33	2480.00
NHPP0503-087		US 50 PASSING LANES EAST OF S	03/21/19	1.00	4000.00	5000.00	4000.00
STA0131-070 HMA ALT		SH 13 CR 5 NORTH AND SOUTH	03/28/19	2.00	4000.00	4015.82	5230.00
STA0131-070 PCCP ALT		SH 13 CR 5 NORTH AND SOUTH					
		WEIGHTED AVERAGE FOR THE FIRST QUARTER		16.00	3906.25	4459.72	4046.00
NHPP0703-445		I-70 WESTBOUND PEAK PERIOD SH	04/25/19	6.00	5000.00	4815.67	4587.00
		WEIGHTED AVERAGE FOR THE SECOND QUARTER		6.00	5000.00	4815.67	4587.00
		WEIGHTED AVERAGE FOR THE YEAR		22.00	4204.55	4511.39	4200.57
===== 604-00310		Inlet Ty C (10 Ft)		Each =====			
ER119A-065		PR SH 119A BOULDER CANYON	01/03/19	1.00	8500.00	6172.12	4500.00
STA119A-069		SH 119: NEDERLAND - EAST					
		WEIGHTED AVERAGE FOR THE FIRST QUARTER		1.00	8500.00	6172.12	4500.00
IM0252-472		I-25 CABLE BARRIER PHASE III	04/04/19	2.00	5000.00	9250.00	13000.00
		WEIGHTED AVERAGE FOR THE SECOND QUARTER		2.00	5000.00	9250.00	13000.00
		WEIGHTED AVERAGE FOR THE YEAR		3.00	6166.67	7198.08	10166.67
===== 604-00350		Inlet Ty C (Spec)		Each =====			
ER119A-065		PR SH 119A BOULDER CANYON	01/03/19	2.00	5000.00	5816.59	4700.00
STA119A-069		SH 119: NEDERLAND - EAST					
STR0241-062		US 24 143.4 - 148	01/24/19	1.00	5000.00	4246.67	5400.00
		WEIGHTED AVERAGE FOR THE FIRST QUARTER		3.00	5000.00	5568.71	4933.33
		WEIGHTED AVERAGE FOR THE YEAR		3.00	5000.00	5568.71	4933.33

COLORADO DEPARTMENT OF TRANSPORTATION
 ITEM UNIT COSTS BY PROJECTS -- 2019 COST DATA

13:44 Wednesday, August 7, 2019 185

PROJECT NUMBER	ITEM NUMBER/ PROJECT LOCATION	ITEM DESCRIPTION/ PROJECT LOCATION	DATE LET	UNIT/ QUANTITY	ENGR. EST.	AVERAGE BID	AWARDED BID
===== 604-00505		Inlet Ty D (5 Ft)		Each =====			
ER119A-065		PR SH 119A BOULDER CANYON	01/03/19	1.00	5000.00	5101.40	4800.00
STA119A-069		SH 119: NEDERLAND - EAST					
ER072A-040		PR SH72A FLOOD PERMANENT REPA	01/31/19	14.00	4500.00	5016.47	7800.00
NHPP072A-041		PR SH72A FLOOD PERMANENT REPA					
NHPP006A-058		US 6 LOVELAND PASS - I-70 (FY	03/07/19	1.00	5200.00	5178.27	6856.54
NHPP0503-087		US 50 PASSING LANES EAST OF S	03/21/19	4.00	4500.00	6000.00	5000.00
		WEIGHTED AVERAGE FOR THE FIRST QUARTER		20.00	4560.00	5064.17	7042.83
NHPP0703-445		I-70 WESTBOUND PEAK PERIOD SH	04/25/19	5.00	5000.00	7555.00	8005.00
		WEIGHTED AVERAGE FOR THE SECOND QUARTER		5.00	5000.00	7555.00	8005.00
		WEIGHTED AVERAGE FOR THE YEAR		25.00	4648.00	5250.05	7235.26
===== 604-00510		Inlet Ty D (10 Ft)		Each =====			
ER119A-065		PR SH 119A BOULDER CANYON	01/03/19	1.00	8500.00	7117.75	5500.00
STA119A-069		SH 119: NEDERLAND - EAST					
ER072A-040		PR SH72A FLOOD PERMANENT REPA	01/31/19	2.00	700.00	6440.12	5500.00
NHPP072A-041		PR SH72A FLOOD PERMANENT REPA					
NHPP145A-065		SH 145 PASSING LANES AT DEEP	02/14/19	9.00	8000.00	5638.67	4250.00
NHPP006A-058		US 6 LOVELAND PASS - I-70 (FY	03/07/19	3.00	5500.00	7136.46	7272.92
		WEIGHTED AVERAGE FOR THE FIRST QUARTER		15.00	6560.00	6121.25	5104.58
NHPP0703-445		I-70 WESTBOUND PEAK PERIOD SH	04/25/19	2.00	5500.00	10753.33	14860.00
		WEIGHTED AVERAGE FOR THE SECOND QUARTER		2.00	5500.00	10753.33	14860.00
		WEIGHTED AVERAGE FOR THE YEAR		17.00	6435.29	6433.53	6252.28
===== 604-00511		Inlet Ty D (Spec) (10 Ft)		Each =====			
ER072A-040		PR SH72A FLOOD PERMANENT REPA	01/31/19	1.00	5000.00	9144.73	8400.00
NHPP072A-041		PR SH72A FLOOD PERMANENT REPA					
		WEIGHTED AVERAGE FOR THE FIRST QUARTER		1.00	5000.00	9144.73	8400.00
		WEIGHTED AVERAGE FOR THE YEAR		1.00	5000.00	9144.73	8400.00

COLORADO DEPARTMENT OF TRANSPORTATION
ITEM UNIT COSTS BY PROJECTS -- 2019 COST DATA

13:44 Wednesday, August 7, 2019 186

PROJECT NUMBER	ITEM NUMBER/ PROJECT LOCATION	ITEM DESCRIPTION/ PROJECT LOCATION	DATE LET	UNIT/ QUANTITY	ENGR. EST.	AVERAGE BID	AWARDED BID
===== 604-13005		Inlet Ty 13 (5 Ft)		Each =====			
ER119A-065		PR SH 119A BOULDER CANYON	01/03/19	3.00	3500.00	5996.50	4500.00
STA119A-069		SH 119: NEDERLAND - EAST					
STR0241-062		US 24 143.4 - 148	01/24/19	5.00	4000.00	4516.67	4700.00
		WEIGHTED AVERAGE FOR THE FIRST QUARTER		8.00	3812.50	5427.33	4625.00
MTCE0641-103		MTCE R3 FY20 SH 64 RANGELY PE	05/02/19	1.00	3200.00	5325.00	5800.00
		WEIGHTED AVERAGE FOR THE SECOND QUARTER		1.00	3200.00	5325.00	5800.00
		WEIGHTED AVERAGE FOR THE YEAR		9.00	3744.44	5422.34	4755.56
===== 604-13006		Inlet Ty 13 (5 Ft) (Spec)		Each =====			
STR0241-062		US 24 143.4 - 148	01/24/19	11.00	4750.00	4625.00	4700.00
		WEIGHTED AVERAGE FOR THE FIRST QUARTER		11.00	4750.00	4625.00	4700.00
		WEIGHTED AVERAGE FOR THE YEAR		11.00	4750.00	4625.00	4700.00
===== 604-16005		Inlet Ty 16 (5 Ft)		Each =====			
SHER100-289		INTERSECTIONS @ SH83 & LONGS	01/03/19	1.00	2500.00	5117.60	6500.00
ER119A-065		PR SH 119A BOULDER CANYON	01/03/19	1.00	4500.00	7630.90	7000.00
STA119A-069		SH 119: NEDERLAND - EAST					
		WEIGHTED AVERAGE FOR THE FIRST QUARTER		2.00	3500.00	6664.25	6750.00
		WEIGHTED AVERAGE FOR THE YEAR		2.00	3500.00	6664.25	6750.00
===== 604-16010		Inlet Ty 16 (10 Ft)		Each =====			
STAM086-075		SH96A ABRIENDO - ORMAN SAFETY	01/31/19	1.00	10000.00	13129.33	6275.00
		WEIGHTED AVERAGE FOR THE FIRST QUARTER		1.00	10000.00	13129.33	6275.00
		WEIGHTED AVERAGE FOR THE YEAR		1.00	10000.00	13129.33	6275.00

COLORADO DEPARTMENT OF TRANSPORTATION
 ITEM UNIT COSTS BY PROJECTS -- 2019 COST DATA

13:44 Wednesday, August 7, 2019 187

PROJECT NUMBER	ITEM NUMBER/ PROJECT LOCATION	ITEM DESCRIPTION/ PROJECT LOCATION	DATE LET	UNIT/ QUANTITY	ENGR. EST.	AVERAGE BID	AWARDED BID
===== 604-16505		Inlet Ty 16 (D) (5 Ft)		Each	=====	=====	=====
NHPP0703-445		I-70 WESTBOUND PEAK PERIOD SH	04/25/19	3.00	5000.00	9569.67	8959.00
	WEIGHTED	AVERAGE FOR THE SECOND QUARTER		3.00	5000.00	9569.67	8959.00
		WEIGHTED AVERAGE FOR THE YEAR		3.00	5000.00	9569.67	8959.00
===== 604-16515		Inlet Ty 16 (D) (15 Ft)		Each	=====	=====	=====
STAM086-075		SH96A ABRIENDO - ORMAN SAFETY	01/31/19	1.00	15000.00	18851.67	8425.00
	WEIGHTED	AVERAGE FOR THE FIRST QUARTER		1.00	15000.00	18851.67	8425.00
		WEIGHTED AVERAGE FOR THE YEAR		1.00	15000.00	18851.67	8425.00
===== 604-16550		Inlet Ty 16 (D) (Spec)		Each	=====	=====	=====
STAM086-075		SH96A ABRIENDO - ORMAN SAFETY	01/31/19	1.00	18000.00	24360.67	7524.00
	WEIGHTED	AVERAGE FOR THE FIRST QUARTER		1.00	18000.00	24360.67	7524.00
		WEIGHTED AVERAGE FOR THE YEAR		1.00	18000.00	24360.67	7524.00
===== 604-16605		Inlet Ty 16 (T) (5 Ft)		Each	=====	=====	=====
NHPP0703-445		I-70 WESTBOUND PEAK PERIOD SH	04/25/19	9.00	6000.00	11045.00	10435.00
	WEIGHTED	AVERAGE FOR THE SECOND QUARTER		9.00	6000.00	11045.00	10435.00
		WEIGHTED AVERAGE FOR THE YEAR		9.00	6000.00	11045.00	10435.00
===== 604-16610		Inlet Ty 16 (T) (10 Ft)		Each	=====	=====	=====
NHPP0703-445		I-70 WESTBOUND PEAK PERIOD SH	04/25/19	3.00	7000.00	11360.33	12131.00
	WEIGHTED	AVERAGE FOR THE SECOND QUARTER		3.00	7000.00	11360.33	12131.00
		WEIGHTED AVERAGE FOR THE YEAR		3.00	7000.00	11360.33	12131.00
===== 604-19000		Inlet Spec		Each	=====	=====	=====
STR0241-062		US 24 143.4 - 148	01/24/19	1.00	5000.00	5363.33	4700.00
	WEIGHTED	AVERAGE FOR THE FIRST QUARTER		1.00	5000.00	5363.33	4700.00

COLORADO DEPARTMENT OF TRANSPORTATION
 ITEM UNIT COSTS BY PROJECTS -- 2019 COST DATA

13:44 Wednesday, August 7, 2019 188

PROJECT NUMBER	ITEM NUMBER/ PROJECT LOCATION	ITEM DESCRIPTION/ PROJECT LOCATION	DATE LET	UNIT/ QUANTITY	ENGR. EST.	AVERAGE BID	AWARDED BID
=====	604-19000	Inlet Spec		Each	=====	=====	=====
NHPP0703-445		I-70 WESTBOUND PEAK PERIOD SH	04/25/19	282.00	150.00	265.33	256.00
		WEIGHTED AVERAGE FOR THE SECOND QUARTER		282.00	150.00	265.33	256.00
		WEIGHTED AVERAGE FOR THE YEAR		283.00	167.14	283.35	271.70
=====	604-19005	Inlet Spec (5 Ft)		Each	=====	=====	=====
STR0241-062		US 24 143.4 - 148	01/24/19	1.00	5000.00	5721.67	4700.00
		WEIGHTED AVERAGE FOR THE FIRST QUARTER		1.00	5000.00	5721.67	4700.00
		WEIGHTED AVERAGE FOR THE YEAR		1.00	5000.00	5721.67	4700.00
=====	604-19025	Inlet Spec (25 Ft)		Each	=====	=====	=====
STAM086-075		SH96A ABRIENDO - ORMAN SAFETY	01/31/19	1.00	25000.00	35171.67	16710.00
		WEIGHTED AVERAGE FOR THE FIRST QUARTER		1.00	25000.00	35171.67	16710.00
		WEIGHTED AVERAGE FOR THE YEAR		1.00	25000.00	35171.67	16710.00
=====	604-19105	Inlet Ty R L5 (5 Ft)		Each	=====	=====	=====
FBR0253-247		I25 AT VINE DRIVE BRIDGE REPL	03/07/19	5.00	4750.00	5401.45	4600.00
SHER100-308		MIDPOINT - SIGNAL CONST PACKA	03/21/19	1.00	5500.00	8890.00	9000.00
		WEIGHTED AVERAGE FOR THE FIRST QUARTER		6.00	4875.00	5523.85	5333.33
MTCE0641-103		MTCE R3 FY20 SH 64 RANGELY PE	05/02/19	2.00	4500.00	6767.50	7700.00
		WEIGHTED AVERAGE FOR THE SECOND QUARTER		2.00	4500.00	6767.50	7700.00
		WEIGHTED AVERAGE FOR THE YEAR		8.00	4781.25	5605.40	5925.00
=====	604-19110	Inlet Ty R L5 (10 Ft)		Each	=====	=====	=====
FBR0253-247		I25 AT VINE DRIVE BRIDGE REPL	03/07/19	4.00	6500.00	7285.68	7250.00
		WEIGHTED AVERAGE FOR THE FIRST QUARTER		4.00	6500.00	7285.68	7250.00
		WEIGHTED AVERAGE FOR THE YEAR		4.00	6500.00	7285.68	7250.00

COLORADO DEPARTMENT OF TRANSPORTATION
 ITEM UNIT COSTS BY PROJECTS -- 2019 COST DATA

13:44 Wednesday, August 7, 2019 189

PROJECT NUMBER	ITEM NUMBER/ PROJECT LOCATION	ITEM DESCRIPTION/ PROJECT LOCATION	DATE LET	UNIT/ QUANTITY	ENGR. EST.	AVERAGE BID	AWARDED BID
===== 604-19115		Inlet Ty R L5 (15 Ft)		Each			
FBR0253-247		I25 AT VINE DRIVE BRIDGE REPL	03/07/19	2.00	8000.00	9805.46	9700.00
	WEIGHTED AVERAGE FOR THE FIRST QUARTER			2.00	8000.00	9805.46	9700.00
	WEIGHTED AVERAGE FOR THE YEAR			2.00	8000.00	9805.46	9700.00
===== 604-19210		Inlet Ty R L10 (10 Ft)		Each			
SHE2254-090		Colfax & I-225, Colfax & Cham	03/07/19	1.00	7500.00	10500.00	8000.00
	WEIGHTED AVERAGE FOR THE FIRST QUARTER			1.00	7500.00	10500.00	8000.00
MTCE0641-103		MTCE R3 FY20 SH 64 RANGELY PE	05/02/19	1.00	6500.00	10392.50	11000.00
	WEIGHTED AVERAGE FOR THE SECOND QUARTER			1.00	6500.00	10392.50	11000.00
	WEIGHTED AVERAGE FOR THE YEAR			2.00	7000.00	10446.25	9500.00
===== 604-19405		Inlet Ty R Spec (5 Ft)		Each			
STR0241-062		US 24 143.4 - 148	01/24/19	1.00	7500.00	6473.33	6000.00
	WEIGHTED AVERAGE FOR THE FIRST QUARTER			1.00	7500.00	6473.33	6000.00
	WEIGHTED AVERAGE FOR THE YEAR			1.00	7500.00	6473.33	6000.00
===== 604-20000		Outlet Structure		Each			
NHPP0703-445		I-70 WESTBOUND PEAK PERIOD SH	04/25/19	1.00	12000.00	11783.33	11350.00
	WEIGHTED AVERAGE FOR THE SECOND QUARTER			1.00	12000.00	11783.33	11350.00
	WEIGHTED AVERAGE FOR THE YEAR			1.00	12000.00	11783.33	11350.00
===== 604-25000		Vane Grate Inlet Spec		Each			
FBR0253-247		I25 AT VINE DRIVE BRIDGE REPL	03/07/19	4.00	7500.00	7790.68	4650.00
	WEIGHTED AVERAGE FOR THE FIRST QUARTER			4.00	7500.00	7790.68	4650.00
	WEIGHTED AVERAGE FOR THE YEAR			4.00	7500.00	7790.68	4650.00

COLORADO DEPARTMENT OF TRANSPORTATION
 ITEM UNIT COSTS BY PROJECTS -- 2019 COST DATA

13:44 Wednesday, August 7, 2019 190

PROJECT NUMBER	ITEM NUMBER/ PROJECT LOCATION	ITEM DESCRIPTION/ PROJECT LOCATION	DATE LET	UNIT/ QUANTITY	ENGR. EST.	AVERAGE BID	AWARDED BID
===== 604-25005		Vane Gate Inlet (5 Ft)		Each	=====	=====	=====
ER119A-065 STA119A-069		PR SH 119A BOULDER CANYON SH 119: NEDERLAND - EAST	01/03/19	1.00	4000.00	6140.97	4800.00
		WEIGHTED AVERAGE FOR THE FIRST QUARTER		1.00	4000.00	6140.97	4800.00
NHPP0703-445 STR 141A-040		I-70 WESTBOUND PEAK PERIOD SH R5 YEAR 4 BRDG PREV MAINT RAM	04/25/19 06/20/19	45.00 1.00	5000.00 5000.00	5933.33 10000.00	4000.00 10000.00
		WEIGHTED AVERAGE FOR THE SECOND QUARTER		46.00	5000.00	5992.70	4130.43
		WEIGHTED AVERAGE FOR THE YEAR		47.00	4978.72	6000.88	4144.68
===== 604-25010		Vane Gate Inlet (10 Ft)		Each	=====	=====	=====
ER119A-065 STA119A-069		PR SH 119A BOULDER CANYON SH 119: NEDERLAND - EAST	01/03/19	1.00	4750.00	8427.84	5700.00
		WEIGHTED AVERAGE FOR THE FIRST QUARTER		1.00	4750.00	8427.84	5700.00
NHPP0703-445		I-70 WESTBOUND PEAK PERIOD SH	04/25/19	17.00	6000.00	7191.33	5374.00
		WEIGHTED AVERAGE FOR THE SECOND QUARTER		17.00	6000.00	7191.33	5374.00
		WEIGHTED AVERAGE FOR THE YEAR		18.00	5930.56	7359.00	5392.11
===== 604-25015		Vane Gate Inlet (15 Ft)		Each	=====	=====	=====
NHPP0703-445		I-70 WESTBOUND PEAK PERIOD SH	04/25/19	1.00	7000.00	10567.67	7803.00
		WEIGHTED AVERAGE FOR THE SECOND QUARTER		1.00	7000.00	10567.67	7803.00
		WEIGHTED AVERAGE FOR THE YEAR		1.00	7000.00	10567.67	7803.00
===== 604-26005		Vane Gate Inlet (D) (5 Ft)		Each	=====	=====	=====
NHPP0703-445		I-70 WESTBOUND PEAK PERIOD SH	04/25/19	1.00	5500.00	9166.00	7723.00
		WEIGHTED AVERAGE FOR THE SECOND QUARTER		1.00	5500.00	9166.00	7723.00
		WEIGHTED AVERAGE FOR THE YEAR		1.00	5500.00	9166.00	7723.00

COLORADO DEPARTMENT OF TRANSPORTATION
 ITEM UNIT COSTS BY PROJECTS -- 2019 COST DATA

13:44 Wednesday, August 7, 2019 191

PROJECT NUMBER	ITEM NUMBER/ PROJECT LOCATION	ITEM DESCRIPTION/ PROJECT LOCATION	DATE LET	UNIT/ QUANTITY	ENGR. EST.	AVERAGE BID	AWARDED BID
===== 604-26015		Vane Grate Inlet (D) (15 Ft)		Each	=====	=====	=====
NHPP0703-445		I-70 WESTBOUND PEAK PERIOD SH	04/25/19	1.00	10000.00	14804.00	13612.00
	WEIGHTED AVERAGE FOR THE SECOND QUARTER			1.00	10000.00	14804.00	13612.00
	WEIGHTED AVERAGE FOR THE YEAR			1.00	10000.00	14804.00	13612.00
===== 604-30005		MH Slab Base (5 Ft)		Each	=====	=====	=====
SHER100-289		INTERSECTIONS @ SH83 & LONGS	01/03/19	6.00	3200.00	4144.80	3500.00
STR0241-062		US 24 143.4 - 148	01/24/19	3.00	7500.00	4956.67	4100.00
ER072A-040		PR SH72A FLOOD PERMANENT REPA	01/31/19	2.00	4000.00	5777.36	9800.00
NHPP072A-041		PR SH72A FLOOD PERMANENT REPA					
	WEIGHTED AVERAGE FOR THE FIRST QUARTER			11.00	4518.18	4882.71	4809.09
NHPP0703-445		I-70 WESTBOUND PEAK PERIOD SH	04/25/19	2.00	3500.00	4015.00	2645.00
NHPP0703-442		I-70 SILVERPLUME SOUNDWALL AN	06/13/19	1.00	4000.00	5880.09	4650.00
	WEIGHTED AVERAGE FOR THE SECOND QUARTER			3.00	3666.67	5080.76	3313.33
	WEIGHTED AVERAGE FOR THE YEAR			14.00	4335.71	4918.72	4488.57
===== 604-30010		MH Slab Base (10 Ft)		Each	=====	=====	=====
ER119A-065		PR SH 119A BOULDER CANYON	01/03/19	2.00	5000.00	7506.96	6000.00
STA119A-069		SH 119: NEDERLAND - EAST					
SHER100-308		MIDPOINT - SIGNAL CONST PACKA	03/21/19	1.00	5000.00	10375.00	12850.00
	WEIGHTED AVERAGE FOR THE FIRST QUARTER			3.00	5000.00	7825.63	8283.33
NHPP0703-445		I-70 WESTBOUND PEAK PERIOD SH	04/25/19	18.00	3500.00	5442.00	3626.00
	WEIGHTED AVERAGE FOR THE SECOND QUARTER			18.00	3500.00	5442.00	3626.00
	WEIGHTED AVERAGE FOR THE YEAR			21.00	3714.29	6037.91	4291.33
===== 604-30015		MH Slab Base (15 Ft)		Each	=====	=====	=====
ER119A-065		PR SH 119A BOULDER CANYON	01/03/19	3.00	6500.00	10051.52	8500.00

COLORADO DEPARTMENT OF TRANSPORTATION
 ITEM UNIT COSTS BY PROJECTS -- 2019 COST DATA

13:44 Wednesday, August 7, 2019 192

PROJECT NUMBER	ITEM NUMBER/ PROJECT LOCATION	ITEM DESCRIPTION/ PROJECT LOCATION	DATE LET	UNIT/ QUANTITY	ENGR. EST.	AVERAGE BID	AWARDED BID
===== 604-30015		MH Slab Base (15 Ft)		Each =====			
STA119A-069		SH 119: NEDERLAND - EAST					
	WEIGHTED AVERAGE FOR THE FIRST QUARTER			3.00	6500.00	10051.52	8500.00
NHPP0703-445		I-70 WESTBOUND PEAK PERIOD SH 04/25/19		6.00	7000.00	7129.00	5437.00
	WEIGHTED AVERAGE FOR THE SECOND QUARTER			6.00	7000.00	7129.00	5437.00
	WEIGHTED AVERAGE FOR THE YEAR			9.00	6833.33	8799.01	6458.00
===== 604-31010		MH Box Base (10 Ft)		Each =====			
FBR0253-247		I25 AT VINE DRIVE BRIDGE REPL 03/07/19		1.00	10000.00	5989.33	5000.00
	WEIGHTED AVERAGE FOR THE FIRST QUARTER			1.00	10000.00	5989.33	5000.00
MTCE0641-103		MTCE R3 FY20 SH 64 RANGELY PE 05/02/19		1.00	7500.00	9812.50	12200.00
	WEIGHTED AVERAGE FOR THE SECOND QUARTER			1.00	7500.00	9812.50	12200.00
	WEIGHTED AVERAGE FOR THE YEAR			2.00	8750.00	6577.51	8600.00
===== 604-31015		MH Box Base (15 Ft)		Each =====			
STAM086-075		SH96A ABRIENDO - ORMAN SAFETY 01/31/19		2.00	16000.00	19763.33	14675.00
	WEIGHTED AVERAGE FOR THE FIRST QUARTER			2.00	16000.00	19763.33	14675.00
	WEIGHTED AVERAGE FOR THE YEAR			2.00	16000.00	19763.33	14675.00
===== 604-39005		MH Spec (5 Ft)		Each =====			
STR0241-062		US 24 143.4 - 148	01/24/19	1.00	7500.00	4783.33	4100.00
	WEIGHTED AVERAGE FOR THE FIRST QUARTER			1.00	7500.00	4783.33	4100.00
	WEIGHTED AVERAGE FOR THE YEAR			1.00	7500.00	4783.33	4100.00

COLORADO DEPARTMENT OF TRANSPORTATION
 ITEM UNIT COSTS BY PROJECTS -- 2019 COST DATA

13:44 Wednesday, August 7, 2019 193

PROJECT NUMBER	ITEM NUMBER/ PROJECT LOCATION	ITEM DESCRIPTION/ PROJECT LOCATION	DATE LET	UNIT/ QUANTITY	ENGR. EST.	AVERAGE BID	AWARDED BID
===== 604-39010		MH Spec (10 Ft)		Each			
STR0241-062		US 24 143.4 - 148	01/24/19	3.00	6000.00	7195.00	5100.00
		WEIGHTED AVERAGE FOR THE FIRST QUARTER		3.00	6000.00	7195.00	5100.00
MTCE0641-103		MTCE R3 FY20 SH 64 RANGELY PE	05/02/19	1.00	8000.00	9812.50	12200.00
		WEIGHTED AVERAGE FOR THE SECOND QUARTER		1.00	8000.00	9812.50	12200.00
		WEIGHTED AVERAGE FOR THE YEAR		4.00	6500.00	7670.91	6875.00
===== 604-39050		MH (TMS)		Each			
NHPP0703-445		I-70 WESTBOUND PEAK PERIOD SH	04/25/19	27.00	5000.00	27401.67	29505.00
		WEIGHTED AVERAGE FOR THE SECOND QUARTER		27.00	5000.00	27401.67	29505.00
		WEIGHTED AVERAGE FOR THE YEAR		27.00	5000.00	27401.67	29505.00
===== 604-50003		IG and F Ty C		Each			
FBR0253-247		I25 AT VINE DRIVE BRIDGE REPL	03/07/19	1.00	2000.00	2580.78	850.00
		WEIGHTED AVERAGE FOR THE FIRST QUARTER		1.00	2000.00	2580.78	850.00
		WEIGHTED AVERAGE FOR THE YEAR		1.00	2000.00	2580.78	850.00
===== 604-50200		MH R and C		Each			
MTCE0641-103		MTCE R3 FY20 SH 64 RANGELY PE	05/02/19	2.00	500.00	580.00	500.00
		WEIGHTED AVERAGE FOR THE SECOND QUARTER		2.00	500.00	580.00	500.00
		WEIGHTED AVERAGE FOR THE YEAR		2.00	500.00	580.00	500.00
===== 604-50800		San Sewer Vault		Each			
NHPP0703-445		I-70 WESTBOUND PEAK PERIOD SH	04/25/19	1.00	8000.00	27015.00	30945.00
		WEIGHTED AVERAGE FOR THE SECOND QUARTER		1.00	8000.00	27015.00	30945.00
		WEIGHTED AVERAGE FOR THE YEAR		1.00	8000.00	27015.00	30945.00

COLORADO DEPARTMENT OF TRANSPORTATION
 ITEM UNIT COSTS BY PROJECTS -- 2019 COST DATA

13:44 Wednesday, August 7, 2019 194

PROJECT NUMBER	ITEM NUMBER/ PROJECT LOCATION	ITEM DESCRIPTION/ PROJECT LOCATION	DATE LET	UNIT/ QUANTITY	ENGR. EST.	AVERAGE BID	AWARDED BID
=====	605-00040	4 In PP Underdrain		Lin Foot	=====		
ER119A-065 STA119A-069		PR SH 119A BOULDER CANYON SH 119: NEDERLAND - EAST	01/03/19	292.00	20.00	33.96	40.00
		WEIGHTED AVERAGE FOR THE FIRST QUARTER		292.00	20.00	33.96	40.00
		WEIGHTED AVERAGE FOR THE YEAR		292.00	20.00	33.96	40.00
=====	605-00060	6 In PP Underdrain		Lin Foot	=====		
NHPP050A-033 NHPP0503-087		US50 West of Delta EB Lanes R US 50 PASSING LANES EAST OF S	03/14/19 03/21/19	1,935.00 140.00	30.00 25.00	46.70 55.00	24.10 80.00
		WEIGHTED AVERAGE FOR THE FIRST QUARTER		2,075.00	29.66	47.08	27.87
		WEIGHTED AVERAGE FOR THE YEAR		2,075.00	29.66	47.08	27.87
=====	605-00061	6 In PP Underdrain (Special)		Lin Foot	=====		
ER119A-065 STA119A-069		PR SH 119A BOULDER CANYON SH 119: NEDERLAND - EAST	01/03/19	850.00	40.00	37.52	60.00
		WEIGHTED AVERAGE FOR THE FIRST QUARTER		850.00	40.00	37.52	60.00
		WEIGHTED AVERAGE FOR THE YEAR		850.00	40.00	37.52	60.00
=====	605-00080	8 In PP Underdrain		Lin Foot	=====		
ER119A-065 STA119A-069		PR SH 119A BOULDER CANYON SH 119: NEDERLAND - EAST	01/03/19	60.00	50.00	85.27	110.00
		WEIGHTED AVERAGE FOR THE FIRST QUARTER		60.00	50.00	85.27	110.00
		WEIGHTED AVERAGE FOR THE YEAR		60.00	50.00	85.27	110.00
=====	605-00120	12 In PP Underdrain		Lin Foot	=====		
STAR200-242		R2 NORTH PROGRAM WALL REPAIRS	01/03/19	147.00	59.75	112.87	160.00
		WEIGHTED AVERAGE FOR THE FIRST QUARTER		147.00	59.75	112.87	160.00
		WEIGHTED AVERAGE FOR THE YEAR		147.00	59.75	112.87	160.00

PROJECT NUMBER	ITEM NUMBER/ PROJECT LOCATION	ITEM DESCRIPTION/ PROJECT LOCATION	DATE LET	UNIT/ QUANTITY	ENGR. EST.	AVERAGE BID	AWARDED BID
=====	605-83002	Geocomp Drain (w/ Pipe)		Sq Yard	=====		
ER119A-065 STA119A-069		PR SH 119A BOULDER CANYON SH 119: NEDERLAND - EAST	01/03/19	445.00	50.00	34.02	88.00
		WEIGHTED AVERAGE FOR THE FIRST QUARTER		445.00	50.00	34.02	88.00
		WEIGHTED AVERAGE FOR THE YEAR		445.00	50.00	34.02	88.00
=====	605-84000	Subsurface Drain Outlet		Lin Foot	=====		
ER119A-065 STA119A-069		PR SH 119A BOULDER CANYON SH 119: NEDERLAND - EAST	01/03/19	99.00	50.00	55.78	62.00
		WEIGHTED AVERAGE FOR THE FIRST QUARTER		99.00	50.00	55.78	62.00
		WEIGHTED AVERAGE FOR THE YEAR		99.00	50.00	55.78	62.00
=====	606-00301	Gdrail Ty 3 (6-3)		Lin Foot	=====		
IM0251-351		I-25 South of Pueblo MP 79.6	01/03/19	16,600.00	22.00	23.39	23.37
ER119A-065 STA119A-069		PR SH 119A BOULDER CANYON SH 119: NEDERLAND - EAST	01/03/19	13,882.00	26.00	47.60	47.00
STR0132-021		SH 13-MOFFAT COUNTY-CR 3 SOUT	01/10/19	950.00	38.00	43.48	38.40
FBR0341-087		US 34 OVER NORTH FORK CO RIVE	01/10/19	125.00	40.00	50.72	52.26
STR141A-047		SH 141 MP 120-143 MESA COUNTY	01/17/19	5,400.00	36.00	26.02	24.75
NHPP0701-241		I-70 TRUCK PARKING GARFIELD C	01/17/19	1,135.00	32.00	29.82	28.00
STR0241-062		US 24 143.4 - 148	01/24/19	4,219.00	36.00	47.50	49.00
ER072A-040		PR SH72A FLOOD PERMANENT REPA	01/31/19	7,337.50	31.00	45.04	48.00
NHPP072A-041		PR SH72A FLOOD PERMANENT REPA					
STA067A-038		SH 67 SEDALIA RESURFACING	01/31/19	612.50	35.00	40.70	44.00
NHPP0821-107		SH 82 GLENWOOD SPRINGS TO CA	02/07/19	39,318.00	32.00	22.23	22.45
NH2871-035		US 287 PASSING LANES SOUTH OF	02/07/19	538.00	25.00	28.66	26.51
NHPP145A-065		SH 145 PASSING LANES AT DEEP	02/14/19	2,887.50	25.00	39.24	35.00
NHPP0741-022		SH 74: I-70 TO CR 65 RESURFAC	02/14/19	114.00	45.00	75.43	75.00
NHPP070A-028		FALL RIVER ROAD BRIDGE	02/21/19	806.00	50.00	46.40	45.00
NHPP1601-073		US 160 PASSING LANE NORTH OF	03/07/19	1,988.00	25.00	27.25	26.50
FBR0253-247		I25 AT VINE DRIVE BRIDGE REPL	03/07/19	3,679.00	35.00	40.15	50.00
NHPP006A-058		US 6 LOVELAND PASS - I-70 (FY	03/07/19	4,216.00	45.00	42.39	40.77
NHPP0702-378		I-70 OFFICERS GULCH TO FRISCO	03/14/19	1,904.00	48.00	54.93	48.28
NHPP050A-033		US50 West of Delta EB Lanes R	03/14/19	6,900.00	28.00	23.03	20.60
NHPP0503-087		US 50 PASSING LANES EAST OF S	03/21/19	1,025.00	30.00	41.00	41.00
SHE 0252-481		I-25 RAMP METER INSTALLATION	03/21/19	733.00	35.00	42.67	40.00
NHPP2254-089		I-225 RESURFACING FROM I-25 T	03/21/19	3,800.00	25.00	52.10	47.00

COLORADO DEPARTMENT OF TRANSPORTATION
 ITEM UNIT COSTS BY PROJECTS -- 2019 COST DATA

13:44 Wednesday, August 7, 2019 196

PROJECT NUMBER	ITEM NUMBER/ PROJECT LOCATION	ITEM DESCRIPTION/ PROJECT LOCATION	DATE LET	UNIT/ QUANTITY	ENGR. EST.	AVERAGE BID	AWARDED BID
=====	606-00301	Gdrail Ty 3 (6-3)		Lin Foot	=====		
STM0242-077		US24 - 8TH ST TO WEST OF MANI	03/28/19	6,262.50	25.92	24.70	23.00
STA0131-070 HMA ALT		SH 13 CR 5 NORTH AND SOUTH	03/28/19	3,822.00	30.00	33.14	39.30
STA0131-070 PCCP ALT		SH 13 CR 5 NORTH AND SOUTH					
	WEIGHTED AVERAGE FOR THE FIRST QUARTER			128,254.00	30.17	36.36	31.57
BR071A-020		REPLACEMENT OF STRUCTURE L-22	04/18/19	150.00	28.00	84.83	82.00
FSA0252-468		I-25 AND PLUM CREEK IMPROVEME	04/18/19	332.00	35.00	49.51	45.55
SHE0701-243		I-70 EXIT 26 DDI MODIFICATION	05/16/19	38.00	30.00	53.50	45.00
FBR0063-057		US-6 F-09-K BRIDGE OVER CASTL	05/30/19	788.00	45.00	38.00	39.00
ER145A-081		SH 145 MP 21 EMERGENCY ROCKFA	06/07/19	237.50	30.00	45.10	46.00
CR500-205		R5 GUARDRAIL END TREATMENT EA	06/13/19	1,156.25	40.00	32.80	32.80
	WEIGHTED AVERAGE FOR THE SECOND QUARTER			2,701.75	39.16	45.02	40.24
	WEIGHTED AVERAGE FOR THE YEAR			130,955.75	30.35	36.44	31.76
=====	606-00305	Gdrail Ty 3 (Spec)		Lin Foot	=====		
NHPP0703-445		I-70 WESTBOUND PEAK PERIOD SH	04/25/19	30,221.00	50.00	44.00	43.00
	WEIGHTED AVERAGE FOR THE SECOND QUARTER			30,221.00	50.00	44.00	43.00
	WEIGHTED AVERAGE FOR THE YEAR			30,221.00	50.00	44.00	43.00
=====	606-00350	Gdrail Ty 3 (D) (6-3)		Lin Foot	=====		
NHPP0821-107		SH 82 GLENWOOD SPRINGS TO CA	02/07/19	62.00	45.00	48.25	46.50
	WEIGHTED AVERAGE FOR THE FIRST QUARTER			62.00	45.00	48.25	46.50
	WEIGHTED AVERAGE FOR THE YEAR			62.00	45.00	48.25	46.50
=====	606-00710	Gdrail Ty 7 (Sty CA)		Lin Foot	=====		
NHPP0702-378		I-70 OFFICERS GULCH TO FRISCO	03/14/19	25.00	90.00	318.17	512.50
	WEIGHTED AVERAGE FOR THE FIRST QUARTER			25.00	90.00	318.17	512.50
FSA0252-468		I-25 AND PLUM CREEK IMPROVEME	04/18/19	34.00	200.00	261.00	472.00

COLORADO DEPARTMENT OF TRANSPORTATION
 ITEM UNIT COSTS BY PROJECTS -- 2019 COST DATA

13:44 Wednesday, August 7, 2019 197

PROJECT NUMBER	ITEM NUMBER/ PROJECT LOCATION	ITEM DESCRIPTION/ PROJECT LOCATION	DATE LET	UNIT/ QUANTITY	ENGR. EST.	AVERAGE BID	AWARDED BID
===== 606-00710 NHPP0703-445	Gdrail Ty 7 (Sty CA) I-70 WESTBOUND PEAK PERIOD SH		04/25/19	Lin Foot 15.00	200.00	368.33	355.00
	WEIGHTED AVERAGE FOR THE SECOND QUARTER			49.00	200.00	287.69	436.18
	WEIGHTED AVERAGE FOR THE YEAR			74.00	162.84	296.62	461.97
===== 606-00745 NHPP0703-445	Gdrail Ty 7 (Sty CE) (Conc Glare Screen) I-70 WESTBOUND PEAK PERIOD SH		04/25/19	Lin Foot 36.00	175.00	471.33	474.00
	WEIGHTED AVERAGE FOR THE SECOND QUARTER			36.00	175.00	471.33	474.00
	WEIGHTED AVERAGE FOR THE YEAR			36.00	175.00	471.33	474.00
===== 606-00900 NHPPR100-250	Gdrail (Spec) PACKAGE A (I-25 / I-70 / I-76		01/24/19	Lin Foot 77.00	310.00	325.26	245.00
	WEIGHTED AVERAGE FOR THE FIRST QUARTER			77.00	310.00	325.26	245.00
	WEIGHTED AVERAGE FOR THE YEAR			77.00	310.00	325.26	245.00
===== 606-00910 ER119A-065 STA119A-069 STR0241-062 SHE2254-090	Guardrail Type 9 (Style CA) PR SH 119A BOULDER CANYON SH 119: NEDERLAND - EAST US 24 143.4 - 148 Colfax & I-225, Colfax & Cham		01/03/19 01/24/19 03/07/19	Lin Foot 8,074.00 250.00 24.00	82.00 96.00 220.00	99.03 169.33 550.00	79.00 170.00 450.00
	WEIGHTED AVERAGE FOR THE FIRST QUARTER			8,348.00	82.82	100.17	82.79
NHPP0703-445 SHE0701-243 NHPP0703-442 STR 141A-040	I-70 WESTBOUND PEAK PERIOD SH I-70 EXIT 26 DDI MODIFICATION I-70 SILVERPLUME SOUNDWALL AN R5 YEAR 4 BRDG PREV MAINT RAM		04/25/19 05/16/19 06/13/19 06/20/19	2,300.00 78.00 1,239.00 238.00	85.00 200.00 130.00 170.00	157.67 154.75 120.99 320.00	148.00 145.00 99.00 200.00
	WEIGHTED AVERAGE FOR THE SECOND QUARTER			3,855.00	107.04	141.35	135.40
	WEIGHTED AVERAGE FOR THE YEAR			12,203.00	90.47	108.90	99.41

COLORADO DEPARTMENT OF TRANSPORTATION
 ITEM UNIT COSTS BY PROJECTS -- 2019 COST DATA

13:44 Wednesday, August 7, 2019 198

PROJECT NUMBER	ITEM NUMBER/ PROJECT LOCATION	ITEM DESCRIPTION/ PROJECT LOCATION	DATE LET	UNIT/ QUANTITY	ENGR. EST.	AVERAGE BID	AWARDED BID
=====	606-00915	Guardrail Type 9 (Style CG)		Lin Foot	=====		
NHPP0703-445		I-70 WESTBOUND PEAK PERIOD SH	04/25/19	10,937.00	95.00	144.00	120.00
	WEIGHTED AVERAGE FOR THE SECOND QUARTER			10,937.00	95.00	144.00	120.00
	WEIGHTED AVERAGE FOR THE YEAR			10,937.00	95.00	144.00	120.00
=====	606-00917	Guardrail Type 9 (Style CG) (Special)		Lin Foot	=====		
NHPP0703-445		I-70 WESTBOUND PEAK PERIOD SH	04/25/19	2,724.00	100.00	173.33	150.00
	WEIGHTED AVERAGE FOR THE SECOND QUARTER			2,724.00	100.00	173.33	150.00
	WEIGHTED AVERAGE FOR THE YEAR			2,724.00	100.00	173.33	150.00
=====	606-00931	Guardrail Type 9 (Style CD) (Special)		Lin Foot	=====		
NHPP0703-445		I-70 WESTBOUND PEAK PERIOD SH	04/25/19	368.00	136.00	360.00	330.00
	WEIGHTED AVERAGE FOR THE SECOND QUARTER			368.00	136.00	360.00	330.00
	WEIGHTED AVERAGE FOR THE YEAR			368.00	136.00	360.00	330.00
=====	606-00940	Guardrail Type 9 (Style CE)		Lin Foot	=====		
ER119A-065 ST119A-069		PR SH 119A BOULDER CANYON SH 119: NEDERLAND - EAST	01/03/19	1,474.00	85.00	178.22	160.00
	WEIGHTED AVERAGE FOR THE FIRST QUARTER			1,474.00	85.00	178.22	160.00
NHPP0703-445		I-70 WESTBOUND PEAK PERIOD SH	04/25/19	29.00	220.00	626.00	575.00
	WEIGHTED AVERAGE FOR THE SECOND QUARTER			29.00	220.00	626.00	575.00
	WEIGHTED AVERAGE FOR THE YEAR			1,503.00	87.60	181.50	168.01
=====	606-00941	Guardrail Type 9 (Style CE) (Special)		Lin Foot	=====		
ER119A-065		PR SH 119A BOULDER CANYON	01/03/19	446.00	90.00	239.69	285.00

COLORADO DEPARTMENT OF TRANSPORTATION
 ITEM UNIT COSTS BY PROJECTS -- 2019 COST DATA

13:44 Wednesday, August 7, 2019 199

PROJECT NUMBER	ITEM NUMBER/ PROJECT LOCATION	ITEM DESCRIPTION/ PROJECT LOCATION	DATE LET	UNIT/ QUANTITY	ENGR. EST.	AVERAGE BID	AWARDED BID
=====	606-00941	Guardrail Type 9 (Style CE) (Special)		Lin Foot	=====		
STA119A-069		SH 119: NEDERLAND - EAST					
	WEIGHTED AVERAGE FOR THE FIRST QUARTER			446.00	90.00	239.69	285.00
	WEIGHTED AVERAGE FOR THE YEAR			446.00	90.00	239.69	285.00
=====	606-00942	Guardrail Type 9 (Style CGE)		Lin Foot	=====		
NHPP0703-445		I-70 WESTBOUND PEAK PERIOD SH 04/25/19		2,668.00	162.00	243.67	231.00
	WEIGHTED AVERAGE FOR THE SECOND QUARTER			2,668.00	162.00	243.67	231.00
	WEIGHTED AVERAGE FOR THE YEAR			2,668.00	162.00	243.67	231.00
=====	606-00943	Guardrail Type 9 (Style CGE) (Special)		Lin Foot	=====		
STA0131-070 HMA ALT		SH 13 CR 5 NORTH AND SOUTH	03/28/19	1,370.00	90.00	276.97	76.60
STA0131-070 PCCP ALT		SH 13 CR 5 NORTH AND SOUTH					
	WEIGHTED AVERAGE FOR THE FIRST QUARTER			1,370.00	90.00	276.97	76.60
	WEIGHTED AVERAGE FOR THE YEAR			1,370.00	90.00	276.97	76.60
=====	606-00944	Guardrail Type 9 (Style CGD) (Special)		Lin Foot	=====		
NHPP0703-445		I-70 WESTBOUND PEAK PERIOD SH 04/25/19		80.00	100.00	531.00	528.00
	WEIGHTED AVERAGE FOR THE SECOND QUARTER			80.00	100.00	531.00	528.00
	WEIGHTED AVERAGE FOR THE YEAR			80.00	100.00	531.00	528.00
=====	606-01320	End Anchor Ty 3B		Each	=====		
ER072A-040		PR SH72A FLOOD PERMANENT REPA	01/31/19	2.00	1500.00	4645.18	5300.00
NHPP072A-041		PR SH72A FLOOD PERMANENT REPA					
	WEIGHTED AVERAGE FOR THE FIRST QUARTER			2.00	1500.00	4645.18	5300.00
	WEIGHTED AVERAGE FOR THE YEAR			2.00	1500.00	4645.18	5300.00
=====	606-01340	End Anchor Ty 3D		Each	=====		
IM0251-351		I-25 South of Pueblo MP 79.6	01/03/19	15.00	1500.00	1073.03	1122.96

PROJECT NUMBER	ITEM NUMBER/ PROJECT LOCATION	ITEM DESCRIPTION/ PROJECT LOCATION	DATE LET	UNIT/ QUANTITY	ENGR. EST.	AVERAGE BID	AWARDED BID
===== 606-01340							
		End Anchor Ty 3D		Each			
NHPP0701-241		I-70 TRUCK PARKING GARFIELD C	01/17/19	2.00	1900.00	3119.38	2900.00
ER072A-040		PR SH72A FLOOD PERMANENT REPA	01/31/19	2.00	1500.00	1109.00	1100.00
NHPP072A-041		PR SH72A FLOOD PERMANENT REPA					
SHE2254-090		Colfax & I-225, Colfax & Cham	03/07/19	1.00	1500.00	2220.00	2375.00
NHPP0702-378		I-70 OFFICERS GULCH TO FRISCO	03/14/19	5.00	1200.00	3216.12	2598.37
NHPP050A-033		US50 West of Delta EB Lanes R	03/14/19	9.00	1500.00	1876.67	1680.00
SHE 0252-481		I-25 RAMP METER INSTALLATION	03/21/19	1.00	1500.00	4036.67	3810.00
NHPP2254-089		I-225 RESURFACING FROM I-25 T	03/21/19	10.00	1500.00	1446.00	1300.00
STM0242-077		US24 - 8TH ST TO WEST OF MANI	03/28/19	6.00	1610.00	870.00	800.00
		WEIGHTED AVERAGE FOR THE FIRST QUARTER		51.00	1499.22	1569.81	1508.65
===== 606-01340							
FSA0252-468		I-25 AND PLUM CREEK IMPROVEME	04/18/19	1.00	1400.00	2096.25	1947.00
NHPP0703-445		I-70 WESTBOUND PEAK PERIOD SH	04/25/19	31.00	1500.00	2140.27	2228.00
SHE0701-243		I-70 EXIT 26 DDI MODIFICATION	05/16/19	1.00	2000.00	4525.00	1420.00
		WEIGHTED AVERAGE FOR THE SECOND QUARTER		33.00	1512.12	2232.97	2195.00
		WEIGHTED AVERAGE FOR THE YEAR		84.00	1504.29	1800.77	1778.29
===== 606-01370							
		Transition Ty 3G		Each			
ER119A-065		PR SH 119A BOULDER CANYON	01/03/19	25.00	1980.00	4678.48	4790.00
STA119A-069		SH 119: NEDERLAND - EAST					
FBR0341-087		US 34 OVER NORTH FORK CO RIVE	01/10/19	4.00	2400.00	3030.82	3301.11
STR141A-047		SH 141 MP 120-143 MESA COUNTY	01/17/19	8.00	2500.00	2077.36	2085.00
STR0241-062		US 24 143.4 - 148	01/24/19	6.00	2200.00	4128.33	4000.00
STA067A-038		SH 67 SEDALIA RESURFACING	01/31/19	7.00	3000.00	3060.43	2400.00
NHPP0741-022		SH 74: I-70 TO CR 65 RESURFAC	02/14/19	4.00	3000.00	3680.02	3595.00
NHPP070A-028		FALL RIVER ROAD BRIDGE	02/21/19	5.00	3000.00	4378.22	3800.00
FBR0253-247		I25 AT VINE DRIVE BRIDGE REPL	03/07/19	4.00	2000.00	3632.71	3700.00
NHPP006A-058		US 6 LOVELAND PASS - I-70 (FY	03/07/19	2.00	3000.00	3894.16	3788.32
NHPP0702-378		I-70 OFFICERS GULCH TO FRISCO	03/14/19	6.00	3500.00	4265.83	3587.50
NHPP2254-089		I-225 RESURFACING FROM I-25 T	03/21/19	30.00	2500.00	3817.53	3300.00
STM0242-077		US24 - 8TH ST TO WEST OF MANI	03/28/19	11.00	2554.55	3233.33	3100.00
		WEIGHTED AVERAGE FOR THE FIRST QUARTER		112.00	2485.71	3970.10	3578.72
===== 606-01370							
BR071A-020		REPLACEMENT OF STRUCTURE L-22	04/18/19	4.00	2000.00	4823.62	4710.00
FSA0252-468		I-25 AND PLUM CREEK IMPROVEME	04/18/19	1.00	3000.00	4247.50	3965.00

COLORADO DEPARTMENT OF TRANSPORTATION
 ITEM UNIT COSTS BY PROJECTS -- 2019 COST DATA

13:44 Wednesday, August 7, 2019 201

PROJECT NUMBER	ITEM NUMBER/ PROJECT LOCATION	ITEM DESCRIPTION/ PROJECT LOCATION	DATE LET	UNIT/ QUANTITY	ENGR. EST.	AVERAGE BID	AWARDED BID
=====	606-01370	Transition Ty 3G		Each =====			
NHPP0703-445		I-70 WESTBOUND PEAK PERIOD SH	04/25/19	29.00	2500.00	5112.64	5000.00
NHPP0703-442		I-70 SILVERPLUME SOUNDWALL AN	06/13/19	1.00	3500.00	6471.39	5920.00
	WEIGHTED AVERAGE FOR THE SECOND QUARTER			35.00	2485.71	5148.14	4963.57
	WEIGHTED AVERAGE FOR THE YEAR			147.00	2485.71	4175.71	3908.44
=====	606-01371	Transition Ty 3G (Spec)		Each =====			
BR071A-020		REPLACEMENT OF STRUCTURE L-22	04/18/19	2.00	3500.00	5245.00	5120.00
	WEIGHTED AVERAGE FOR THE SECOND QUARTER			2.00	3500.00	5245.00	5120.00
	WEIGHTED AVERAGE FOR THE YEAR			2.00	3500.00	5245.00	5120.00
=====	606-01380	Transition Ty 3H		Each =====			
IM0251-351		I-25 South of Pueblo MP 79.6	01/03/19	2.00	1700.00	2093.53	2186.81
NHPP070A-028		FALL RIVER ROAD BRIDGE	02/21/19	1.00	2000.00	2289.74	2000.00
NHPP0702-378		I-70 OFFICERS GULCH TO FRISCO	03/14/19	1.00	2300.00	2478.25	2039.75
STM0242-077		US24 - 8TH ST TO WEST OF MANI	03/28/19	12.00	1500.00	1733.33	1600.00
	WEIGHTED AVERAGE FOR THE FIRST QUARTER			16.00	1606.25	1885.22	1725.84
NHPP0703-445		I-70 WESTBOUND PEAK PERIOD SH	04/25/19	21.00	2000.00	2219.57	2313.00
	WEIGHTED AVERAGE FOR THE SECOND QUARTER			21.00	2000.00	2219.57	2313.00
	WEIGHTED AVERAGE FOR THE YEAR			37.00	1829.73	2068.39	2059.09
=====	606-01385	Transition Ty 3J		Each =====			
ER119A-065		PR SH 119A BOULDER CANYON	01/03/19	2.00	1250.00	1654.20	1600.00
STA119A-069		SH 119: NEDERLAND - EAST					
STR0241-062		US 24 143.4 - 148	01/24/19	3.00	2000.00	3126.67	3200.00
ER072A-040		PR SH72A FLOOD PERMANENT REPA	01/31/19	6.00	1500.00	1699.42	1600.00
NHPP072A-041		PR SH72A FLOOD PERMANENT REPA					
NHPP0821-107		SH 82 GLENWOOD SPRINGS TO CA	02/07/19	1.00	1350.00	2012.50	1525.00
FBR0253-247		I25 AT VINE DRIVE BRIDGE REPL	03/07/19	1.00	1800.00	1318.95	1300.00

COLORADO DEPARTMENT OF TRANSPORTATION
 ITEM UNIT COSTS BY PROJECTS -- 2019 COST DATA

13:44 Wednesday, August 7, 2019 202

PROJECT NUMBER	ITEM NUMBER/ PROJECT LOCATION	ITEM DESCRIPTION/ PROJECT LOCATION	DATE LET	UNIT/ QUANTITY	ENGR. EST.	AVERAGE BID	AWARDED BID
=====	606-01385	Transition Ty 3J		Each =====			
NHPP2254-089		I-225 RESURFACING FROM I-25 T	03/21/19	2.00	1500.00	2991.90	3000.00
	WEIGHTED AVERAGE FOR THE FIRST QUARTER			15.00	1576.67	1840.09	2081.67
BR071A-020		REPLACEMENT OF STRUCTURE L-22	04/18/19	2.00	2000.00	3250.00	3170.00
CR500-205		R5 GUARDRAIL END TREATMENT EA	06/13/19	5.00	1700.00	2370.00	2370.00
	WEIGHTED AVERAGE FOR THE SECOND QUARTER			7.00	1785.71	2850.00	2598.57
	WEIGHTED AVERAGE FOR THE YEAR			22.00	1643.18	1927.56	2246.14
=====	606-01390	End Anchor Ty 3K		Each =====			
ER119A-065		PR SH 119A BOULDER CANYON	01/03/19	2.00	1800.00	2209.95	2180.00
STA119A-069		SH 119: NEDERLAND - EAST					
STR0241-062		US 24 143.4 - 148	01/24/19	3.00	2200.00	2711.67	2900.00
ER072A-040		PR SH72A FLOOD PERMANENT REPA	01/31/19	6.00	3000.00	1763.23	1600.00
NHPP072A-041		PR SH72A FLOOD PERMANENT REPA					
NHPP0821-107		SH 82 GLENWOOD SPRINGS TO CA	02/07/19	1.00	1850.00	1762.50	1525.00
FBR0253-247		I25 AT VINE DRIVE BRIDGE REPL	03/07/19	1.00	2000.00	2061.84	2100.00
NHPP2254-089		I-225 RESURFACING FROM I-25 T	03/21/19	1.00	1000.00	2901.02	2500.00
	WEIGHTED AVERAGE FOR THE FIRST QUARTER			14.00	2360.71	1961.28	2056.07
BR071A-020		REPLACEMENT OF STRUCTURE L-22	04/18/19	4.00	2000.00	2943.33	2830.00
CR500-205		R5 GUARDRAIL END TREATMENT EA	06/13/19	15.00	1900.00	1630.00	1630.00
	WEIGHTED AVERAGE FOR THE SECOND QUARTER			19.00	1921.05	2213.70	1882.63
	WEIGHTED AVERAGE FOR THE YEAR			33.00	2107.58	2009.96	1956.21
=====	606-01392	Interrupted Structure Approach		Lin Foot =====			
CR500-205		R5 GUARDRAIL END TREATMENT EA	06/13/19	284.00	80.00	68.00	68.00
	WEIGHTED AVERAGE FOR THE SECOND QUARTER			284.00	80.00	68.00	68.00
	WEIGHTED AVERAGE FOR THE YEAR			284.00	80.00	68.00	68.00

COLORADO DEPARTMENT OF TRANSPORTATION
 ITEM UNIT COSTS BY PROJECTS -- 2019 COST DATA

13:44 Wednesday, August 7, 2019 203

PROJECT NUMBER	ITEM NUMBER/ PROJECT LOCATION	ITEM DESCRIPTION/ PROJECT LOCATION	DATE LET	UNIT/ QUANTITY	ENGR. EST.	AVERAGE BID	AWARDED BID
=====	606-01395	Transition Ty 3L		Each	=====	=====	=====
NHPP0703-445		I-70 WESTBOUND PEAK PERIOD SH	04/25/19	9.00	2000.00	2103.62	2100.00
	WEIGHTED AVERAGE FOR THE SECOND QUARTER			9.00	2000.00	2103.62	2100.00
	WEIGHTED AVERAGE FOR THE YEAR			9.00	2000.00	2103.62	2100.00
=====	606-01460	Median Terminal		Each	=====	=====	=====
IM0251-351		I-25 South of Pueblo MP 79.6	01/03/19	2.00	4600.00	5600.26	5851.20
NHPP0821-107		SH 82 GLENWOOD SPRINGS TO CA	02/07/19	3.00	4500.00	6100.00	7000.00
	WEIGHTED AVERAGE FOR THE FIRST QUARTER			5.00	4540.00	5814.43	6540.48
	WEIGHTED AVERAGE FOR THE YEAR			5.00	4540.00	5814.43	6540.48
=====	606-02003	End Anchor (Nonflared)		Each	=====	=====	=====
IM0251-351		I-25 South of Pueblo MP 79.6	01/03/19	16.00	2700.00	3398.87	2896.05
ER119A-065		PR SH 119A BOULDER CANYON	01/03/19	47.00	2600.00	4981.53	5100.00
STA119A-069		SH 119: NEDERLAND - EAST					
FBR0341-087		US 34 OVER NORTH FORK CO RIVE	01/10/19	4.00	3500.00	4020.13	4242.56
STR141A-047		SH 141 MP 120-143 MESA COUNTY	01/17/19	1.00	3000.00	3444.45	3100.00
NHPP0701-241		I-70 TRUCK PARKING GARFIELD C	01/17/19	2.00	2500.00	3680.87	3400.00
STR0241-062		US 24 143.4 - 148	01/24/19	27.00	2500.00	5016.67	4700.00
ER072A-040		PR SH72A FLOOD PERMANENT REPA	01/31/19	13.00	4500.00	3370.14	3400.00
NHPP072A-041		PR SH72A FLOOD PERMANENT REPA					
STA067A-038		SH 67 SEDALIA RESURFACING	01/31/19	2.00	3000.00	3552.63	3400.00
NHPP0821-107		SH 82 GLENWOOD SPRINGS TO CA	02/07/19	31.00	2800.00	2770.00	2640.00
NH2871-035		US 287 PASSING LANES SOUTH OF	02/07/19	1.00	2250.00	3718.08	3207.75
NHPP145A-065		SH 145 PASSING LANES AT DEEP	02/14/19	3.00	2700.00	4360.76	4365.00
NHPP0741-022		SH 74: I-70 TO CR 65 RESURFAC	02/14/19	2.00	3000.00	3936.66	3850.00
NHPP070A-028		FALL RIVER ROAD BRIDGE	02/21/19	4.00	3500.00	5086.10	4600.00
NHPP1601-073		US 160 PASSING LANE NORTH OF	03/07/19	8.00	4000.00	3800.00	3200.00
FBR0253-247		I25 AT VINE DRIVE BRIDGE REPL	03/07/19	9.00	3000.00	3355.09	3400.00
NHPP006A-058		US 6 LOVELAND PASS - I-70 (FY	03/07/19	4.00	2500.00	4636.38	4272.75
SHE2254-090		Colfax & I-225, Colfax & Cham	03/07/19	1.00	3000.00	3895.00	4200.00
NHPP0702-378		I-70 OFFICERS GULCH TO FRISCO	03/14/19	1.00	4400.00	5458.83	4776.50
NHPP050A-033		US50 West of Delta EB Lanes R	03/14/19	2.00	2800.00	3190.00	2570.00
SHE 0252-481		I-25 RAMP METER INSTALLATION	03/21/19	2.00	3500.00	4881.67	4600.00
NHPP2254-089		I-225 RESURFACING FROM I-25 T	03/21/19	11.00	3000.00	3857.65	3300.00
	WEIGHTED AVERAGE FOR THE FIRST QUARTER			191.00	2924.35	4193.66	3916.01

PROJECT NUMBER	ITEM NUMBER/ PROJECT LOCATION	ITEM DESCRIPTION/ PROJECT LOCATION	DATE LET	UNIT/ QUANTITY	ENGR. EST.	AVERAGE BID	AWARDED BID
===== 606-02003		End Anchor (Nonflared)		Each	=====	=====	=====
NHPP0703-445		I-70 WESTBOUND PEAK PERIOD SH	04/25/19	7.00	3700.00	4476.55	4400.00
SHE0701-243		I-70 EXIT 26 DDI MODIFICATION	05/16/19	1.00	3000.00	4740.00	3160.00
FBR0063-057		US-6 F-09-K BRIDGE OVER CASTL	05/30/19	2.00	4000.00	3607.50	3860.00
ER145A-081		SH 145 MP 21 EMERGENCY ROCKFA	06/07/19	2.00	4000.00	4812.35	5005.00
NHPP0703-442		I-70 SILVERPLUME SOUNDWALL AN	06/13/19	1.00	4300.00	7120.47	6270.00
CR500-205		R5 GUARDRAIL END TREATMENT EA	06/13/19	35.00	3000.00	2970.00	2970.00
		WEIGHTED AVERAGE FOR THE SECOND QUARTER		48.00	3212.50	4046.85	3373.13
		WEIGHTED AVERAGE FOR THE YEAR		239.00	2982.22	4183.32	3806.98
===== 606-02005		End Anchor (Flared)		Each	=====	=====	=====
IM0251-351		I-25 South of Pueblo MP 79.6	01/03/19	7.00	3200.00	3210.96	4348.45
ER119A-065		PR SH 119A BOULDER CANYON	01/03/19	19.00	2500.00	3947.70	3900.00
STA119A-069		SH 119: NEDERLAND - EAST					
STR0132-021		SH 13-MOFFAT COUNTY-CR 3 SOUT	01/10/19	6.00	3000.00	3258.00	2840.00
STR141A-047		SH 141 MP 120-143 MESA COUNTY	01/17/19	19.00	3000.00	4348.41	4150.00
ER072A-040		PR SH72A FLOOD PERMANENT REPA	01/31/19	13.00	4000.00	2852.26	2900.00
NHPP072A-041		PR SH72A FLOOD PERMANENT REPA					
STA067A-038		SH 67 SEDALIA RESURFACING	01/31/19	5.00	2500.00	3836.54	4500.00
NHPP0821-107		SH 82 GLENWOOD SPRINGS TO CA	02/07/19	19.00	3400.00	3150.00	3000.00
NH2871-035		US 287 PASSING LANES SOUTH OF	02/07/19	3.00	2500.00	3096.39	2661.75
NHPP0741-022		SH 74: I-70 TO CR 65 RESURFAC	02/14/19	2.00	2500.00	3310.62	3195.00
NHPP006A-058		US 6 LOVELAND PASS - I-70 (FY	03/07/19	22.00	3000.00	4296.88	3793.76
NHPP0702-378		I-70 OFFICERS GULCH TO FRISCO	03/14/19	9.00	4000.00	5058.07	4314.22
NHPP050A-033		US50 West of Delta EB Lanes R	03/14/19	9.00	2600.00	2850.00	2250.00
NHPP0503-087		US 50 PASSING LANES EAST OF S	03/21/19	6.00	2200.00	4650.00	5000.00
NHPP2254-089		I-225 RESURFACING FROM I-25 T	03/21/19	16.00	3000.00	3105.68	2700.00
STM0242-077		US24 - 8TH ST TO WEST OF MANI	03/28/19	9.00	2977.78	2533.33	2300.00
STA0131-070 HMA ALT		SH 13 CR 5 NORTH AND SOUTH	03/28/19	22.00	2500.00	3439.66	3900.00
STA0131-070 PCCP ALT		SH 13 CR 5 NORTH AND SOUTH					
		WEIGHTED AVERAGE FOR THE FIRST QUARTER		186.00	2983.33	3533.80	3493.40
BR071A-020		REPLACEMENT OF STRUCTURE L-22	04/18/19	2.00	2500.00	4425.00	4330.00
FSA0252-468		I-25 AND PLUM CREEK IMPROVEME	04/18/19	1.00	3000.00	3775.75	3493.00
NHPP0703-445		I-70 WESTBOUND PEAK PERIOD SH	04/25/19	27.00	2500.00	4027.05	4202.00
		WEIGHTED AVERAGE FOR THE SECOND QUARTER		30.00	2516.67	4042.24	4186.90
		WEIGHTED AVERAGE FOR THE YEAR		216.00	2918.52	3587.79	3594.89

COLORADO DEPARTMENT OF TRANSPORTATION
 ITEM UNIT COSTS BY PROJECTS -- 2019 COST DATA

13:44 Wednesday, August 7, 2019 205

PROJECT NUMBER	ITEM NUMBER/ PROJECT LOCATION	ITEM DESCRIPTION/ PROJECT LOCATION	DATE LET	UNIT/ QUANTITY	ENGR. EST.	AVERAGE BID	AWARDED BID
=====	606-10405	Brdg Rail Ty 4 (Spec)		Lin Foot	=====		
NHPPR100-250		PACKAGE A (I-25 / I-70 / I-76	01/24/19	12.00	300.00	698.15	405.00
	WEIGHTED AVERAGE FOR THE FIRST QUARTER			12.00	300.00	698.15	405.00
	WEIGHTED AVERAGE FOR THE YEAR			12.00	300.00	698.15	405.00
=====	606-10700	Brdg Rail Ty 7		Lin Foot	=====		
NHPP070A-028		FALL RIVER ROAD BRIDGE	02/21/19	149.00	150.00	175.89	220.00
FBR0253-247		I25 AT VINE DRIVE BRIDGE REPL	03/07/19	505.00	150.00	132.60	130.00
	WEIGHTED AVERAGE FOR THE FIRST QUARTER			654.00	150.00	137.72	150.50
NHPP0703-445		I-70 WESTBOUND PEAK PERIOD SH	04/25/19	15,824.00	165.00	125.00	95.00
	WEIGHTED AVERAGE FOR THE SECOND QUARTER			15,824.00	165.00	125.00	95.00
	WEIGHTED AVERAGE FOR THE YEAR			16,478.00	164.40	126.49	97.20
=====	606-10705	Brdg Rail Ty 7 (Spec)		Lin Foot	=====		
NHPP070A-028		FALL RIVER ROAD BRIDGE	02/21/19	82.00	95.00	213.76	190.00
	WEIGHTED AVERAGE FOR THE FIRST QUARTER			82.00	95.00	213.76	190.00
NHPP0703-445		I-70 WESTBOUND PEAK PERIOD SH	04/25/19	2,101.00	140.00	191.00	170.00
	WEIGHTED AVERAGE FOR THE SECOND QUARTER			2,101.00	140.00	191.00	170.00
	WEIGHTED AVERAGE FOR THE YEAR			2,183.00	138.31	192.39	170.75
=====	606-11000	Brdg Rail Ty 10		Lin Foot	=====		
NHPP0702-378		I-70 OFFICERS GULCH TO FRISCO	03/14/19	7.00	187.00	665.04	620.12
	WEIGHTED AVERAGE FOR THE FIRST QUARTER			7.00	187.00	665.04	620.12
	WEIGHTED AVERAGE FOR THE YEAR			7.00	187.00	665.04	620.12

COLORADO DEPARTMENT OF TRANSPORTATION
 ITEM UNIT COSTS BY PROJECTS -- 2019 COST DATA

13:44 Wednesday, August 7, 2019 206

PROJECT NUMBER	ITEM NUMBER/ PROJECT LOCATION	ITEM DESCRIPTION/ PROJECT LOCATION	DATE LET	UNIT/ QUANTITY	ENGR. EST.	AVERAGE BID	AWARDED BID
=====	606-11010	Brdg Rail Ty 10R		Lin Foot	=====		
	ER119A-065	PR SH 119A BOULDER CANYON	01/03/19	36.00	200.00	335.80	475.00
	STA119A-069	SH 119: NEDERLAND - EAST					
	STR141A-047	SH 141 MP 120-143 MESA COUNTY	01/17/19	381.00	180.00	215.53	235.00
	STA067A-038	SH 67 SEDALIA RESURFACING	01/31/19	142.00	250.00	286.50	250.00
	NHPP0702-378	I-70 OFFICERS GULCH TO FRISCO	03/14/19	718.00	133.00	220.85	227.55
	STM0242-077	US24 - 8TH ST TO WEST OF MANI	03/28/19	2,470.00	323.05	211.67	175.00
		WEIGHTED AVERAGE FOR THE FIRST QUARTER		3,747.00	268.14	219.57	196.90
		WEIGHTED AVERAGE FOR THE YEAR		3,747.00	268.14	219.57	196.90
=====	606-11030	Brdg Rail Ty 10M		Lin Foot	=====		
	FBR0341-087	US 34 OVER NORTH FORK CO RIVE	01/10/19	237.00	220.00	235.07	216.60
	NHPP070A-028	FALL RIVER ROAD BRIDGE	02/21/19	416.00	175.00	242.83	160.00
		WEIGHTED AVERAGE FOR THE FIRST QUARTER		653.00	191.33	239.68	180.54
	BR071A-020	REPLACEMENT OF STRUCTURE L-22	04/18/19	202.00	180.00	243.33	170.00
		WEIGHTED AVERAGE FOR THE SECOND QUARTER		202.00	180.00	243.33	170.00
		WEIGHTED AVERAGE FOR THE YEAR		855.00	188.65	240.22	178.05
=====	606-21010	End Anchor (Tens Cab Bar)		Each	=====		
	IM0252-472	I-25 CABLE BARRIER PHASE III	04/04/19	10.00	8000.00	8750.00	8000.00
		WEIGHTED AVERAGE FOR THE SECOND QUARTER		10.00	8000.00	8750.00	8000.00
		WEIGHTED AVERAGE FOR THE YEAR		10.00	8000.00	8750.00	8000.00
=====	606-99999	Gdrail Ty 7 (Precast)		Lin Foot	=====		
	NHPPR100-250	PACKAGE A (I-25 / I-70 / I-76)	01/24/19	100.00	120.00	94.50	114.00
		WEIGHTED AVERAGE FOR THE FIRST QUARTER		100.00	120.00	94.50	114.00
		WEIGHTED AVERAGE FOR THE YEAR		100.00	120.00	94.50	114.00

COLORADO DEPARTMENT OF TRANSPORTATION
 ITEM UNIT COSTS BY PROJECTS -- 2019 COST DATA

13:44 Wednesday, August 7, 2019 207

PROJECT NUMBER	ITEM NUMBER/ PROJECT LOCATION	ITEM DESCRIPTION/ PROJECT LOCATION	DATE LET	UNIT/ QUANTITY	ENGR. EST.	AVERAGE BID	AWARDED BID
===== 607-00005 End Post Each =====							
	STR0132-021	SH 13-MOFFAT COUNTY-CR 3 SOUT	01/10/19	34.00	250.00	170.80	156.00
	FBR0341-087	US 34 OVER NORTH FORK CO RIVE	01/10/19	6.00	530.00	333.05	325.89
	NHPP1601-073	US 160 PASSING LANE NORTH OF	03/07/19	11.00	350.00	222.50	225.00
	NHPP0503-087	US 50 PASSING LANES EAST OF S	03/21/19	38.00	250.00	222.50	220.00
	STA0131-070 HMA ALT	SH 13 CR 5 NORTH AND SOUTH	03/28/19	50.00	300.00	237.65	261.00
	STA0131-070 PCCP ALT	SH 13 CR 5 NORTH AND SOUTH					
	WEIGHTED AVERAGE FOR THE FIRST QUARTER			139.00	287.99	216.91	215.96
	FBR0063-057	US-6 F-09-K BRIDGE OVER CASTL	05/30/19	10.00	250.00	189.13	375.00
	ER145A-081	SH 145 MP 21 EMERGENCY ROCKFA	06/07/19	4.00	350.00	133.25	60.00
	WEIGHTED AVERAGE FOR THE SECOND QUARTER			14.00	278.57	173.16	285.00
	WEIGHTED AVERAGE FOR THE YEAR			153.00	287.12	214.37	223.51
===== 607-00010 Corner and Line Br Post Each =====							
	STR0132-021	SH 13-MOFFAT COUNTY-CR 3 SOUT	01/10/19	77.00	320.00	230.20	208.00
	FBR0341-087	US 34 OVER NORTH FORK CO RIVE	01/10/19	2.00	600.00	386.75	380.20
	NHPP1601-073	US 160 PASSING LANE NORTH OF	03/07/19	25.00	250.00	315.00	330.00
	NHPP0503-087	US 50 PASSING LANES EAST OF S	03/21/19	22.00	380.00	280.00	280.00
	STA0131-070 HMA ALT	SH 13 CR 5 NORTH AND SOUTH	03/28/19	54.00	400.00	264.81	297.00
	STA0131-070 PCCP ALT	SH 13 CR 5 NORTH AND SOUTH					
	WEIGHTED AVERAGE FOR THE FIRST QUARTER			180.00	344.72	251.51	256.24
	FBR0063-057	US-6 F-09-K BRIDGE OVER CASTL	05/30/19	6.00	300.00	417.50	485.00
	WEIGHTED AVERAGE FOR THE SECOND QUARTER			6.00	300.00	417.50	485.00
	WEIGHTED AVERAGE FOR THE YEAR			186.00	343.28	254.51	264.88
===== 607-00015 End Post (Spec) Each =====							
	STA0131-070 HMA ALT	SH 13 CR 5 NORTH AND SOUTH	03/28/19	156.00	500.00	309.96	352.00

COLORADO DEPARTMENT OF TRANSPORTATION
 ITEM UNIT COSTS BY PROJECTS -- 2019 COST DATA

13:44 Wednesday, August 7, 2019 208

PROJECT NUMBER	ITEM NUMBER/ PROJECT LOCATION	ITEM DESCRIPTION/ PROJECT LOCATION	DATE LET	UNIT/ QUANTITY	ENGR. EST.	AVERAGE BID	AWARDED BID
===== 607-00015							
STA0131-070 PCCP ALT		End Post (Spec) SH 13 CR 5 NORTH AND SOUTH		Each			
		WEIGHTED AVERAGE FOR THE FIRST QUARTER		156.00	500.00	309.96	352.00
		WEIGHTED AVERAGE FOR THE YEAR		156.00	500.00	309.96	352.00
===== 607-00020							
		Corner and Line Br Post (Spec)		Each			
STA0131-070 HMA ALT		SH 13 CR 5 NORTH AND SOUTH	03/28/19	180.00	700.00	358.49	121.00
STA0131-070 PCCP ALT		SH 13 CR 5 NORTH AND SOUTH					
		WEIGHTED AVERAGE FOR THE FIRST QUARTER		180.00	700.00	358.49	121.00
		WEIGHTED AVERAGE FOR THE YEAR		180.00	700.00	358.49	121.00
===== 607-01000							
		Fence BW MP		Lin Foot			
ER072A-040		PR SH72A FLOOD PERMANENT REPA	01/31/19	85.00	8.00	18.70	45.00
NHPP072A-041		PR SH72A FLOOD PERMANENT REPA					
NHPP1601-073		US 160 PASSING LANE NORTH OF	03/07/19	2,601.00	3.00	5.13	4.25
FBR0253-247		I25 AT VINE DRIVE BRIDGE REPL	03/07/19	513.00	5.00	7.51	5.00
SHE 0252-481		I-25 RAMP METER INSTALLATION	03/21/19	740.00	8.00	11.08	5.50
		WEIGHTED AVERAGE FOR THE FIRST QUARTER		3,939.00	4.31	8.00	5.46
===== 607-01050							
		Fence Wire MP		Lin Foot			
ER145A-081		SH 145 MP 21 EMERGENCY ROCKFA	06/07/19	300.00	3.00	9.97	10.00
		WEIGHTED AVERAGE FOR THE SECOND QUARTER		300.00	3.00	9.97	10.00
		WEIGHTED AVERAGE FOR THE YEAR		4,239.00	4.22	8.08	5.78
===== 607-01050							
		Fence Wire MP		Lin Foot			
ER072A-040		PR SH72A FLOOD PERMANENT REPA	01/31/19	887.00	2.00	125.93	12.00
NHPP072A-041		PR SH72A FLOOD PERMANENT REPA					
SHER100-308		MIDPOINT - SIGNAL CONST PACKA	03/21/19	50.00	10.00	108.00	160.00
		WEIGHTED AVERAGE FOR THE FIRST QUARTER		937.00	2.43	125.76	19.90
		WEIGHTED AVERAGE FOR THE YEAR		937.00	2.43	125.76	19.90

COLORADO DEPARTMENT OF TRANSPORTATION
 ITEM UNIT COSTS BY PROJECTS -- 2019 COST DATA

13:44 Wednesday, August 7, 2019 209

PROJECT NUMBER	ITEM NUMBER/ PROJECT LOCATION	ITEM DESCRIPTION/ PROJECT LOCATION	DATE LET	UNIT/ QUANTITY	ENGR. EST.	AVERAGE BID	AWARDED BID
=====	607-01055	Fence Wire TWP		Lin Foot	=====		
FBR0341-087		US 34 OVER NORTH FORK CO RIVE	01/10/19	319.00	5.00	11.57	10.38
	WEIGHTED AVERAGE FOR THE FIRST QUARTER			319.00	5.00	11.57	10.38
	WEIGHTED AVERAGE FOR THE YEAR			319.00	5.00	11.57	10.38
=====	607-01100	Fence BW TWP		Lin Foot	=====		
NHPP0503-087		US 50 PASSING LANES EAST OF S	03/21/19	7,129.00	10.00	3.80	4.00
	WEIGHTED AVERAGE FOR THE FIRST QUARTER			7,129.00	10.00	3.80	4.00
FBR0063-057		US-6 F-09-K BRIDGE OVER CASTL	05/30/19	100.00	5.00	11.63	20.00
	WEIGHTED AVERAGE FOR THE SECOND QUARTER			100.00	5.00	11.63	20.00
	WEIGHTED AVERAGE FOR THE YEAR			7,229.00	9.93	3.91	4.22
=====	607-01110	Fence BW TWP (Spec)		Lin Foot	=====		
STA0131-070 HMA ALT		SH 13 CR 5 NORTH AND SOUTH	03/28/19	69,946.00	6.00	6.59	5.70
STA0131-070 PCCP ALT		SH 13 CR 5 NORTH AND SOUTH					
	WEIGHTED AVERAGE FOR THE FIRST QUARTER			69,946.00	6.00	6.59	5.70
	WEIGHTED AVERAGE FOR THE YEAR			69,946.00	6.00	6.59	5.70
=====	607-11200	Fence CW MP		Lin Foot	=====		
NHPP1601-073		US 160 PASSING LANE NORTH OF	03/07/19	612.00	4.00	6.00	5.00
	WEIGHTED AVERAGE FOR THE FIRST QUARTER			612.00	4.00	6.00	5.00
	WEIGHTED AVERAGE FOR THE YEAR			612.00	4.00	6.00	5.00
=====	607-11300	Fence CW TWP		Lin Foot	=====		
FBR0063-057		US-6 F-09-K BRIDGE OVER CASTL	05/30/19	50.00	8.00	21.63	40.00
	WEIGHTED AVERAGE FOR THE SECOND QUARTER			50.00	8.00	21.63	40.00
	WEIGHTED AVERAGE FOR THE YEAR			50.00	8.00	21.63	40.00

PROJECT NUMBER	ITEM NUMBER/ PROJECT LOCATION	ITEM DESCRIPTION/ PROJECT LOCATION	DATE LET	UNIT/ QUANTITY	ENGR. EST.	AVERAGE BID	AWARDED BID
=====	607-11310	Fence CW TWP (Spec)		Lin Foot	=====		
STR0132-021		SH 13-MOFFAT COUNTY-CR 3 SOUT	01/10/19	44,120.00	4.00	3.85	3.45
STA0131-070 HMA ALT		SH 13 CR 5 NORTH AND SOUTH	03/28/19	33,556.00	5.00	5.95	6.15
STA0131-070 PCCP ALT		SH 13 CR 5 NORTH AND SOUTH					
		WEIGHTED AVERAGE FOR THE FIRST QUARTER		77,676.00	4.43	4.51	4.19
		WEIGHTED AVERAGE FOR THE YEAR		77,676.00	4.43	4.51	4.19
=====	607-11455	Fence Wood		Lin Foot	=====		
ER119A-065		PR SH 119A BOULDER CANYON	01/03/19	326.00	18.00	25.35	20.00
STA119A-069		SH 119: NEDERLAND - EAST					
STR0241-062		US 24 143.4 - 148	01/24/19	213.00	50.00	74.33	98.00
		WEIGHTED AVERAGE FOR THE FIRST QUARTER		539.00	30.65	34.99	50.82
		WEIGHTED AVERAGE FOR THE YEAR		539.00	30.65	34.99	50.82
=====	607-11525	Fence (Plastic)		Lin Foot	=====		
STAR200-242		R2 NORTH PROGRAM WALL REPAIRS	01/03/19	200.00	3.20	4.19	5.00
IM0251-351		I-25 South of Pueblo MP 79.6	01/03/19	400.00	4.00	2.79	3.10
NHPPR500-173		US 160_550 DURANGO SIGNALS OP	01/03/19	200.00	15.00	9.00	8.00
SHER100-289		INTERSECTIONS @ SH83 & LONGS	01/03/19	500.00	4.50	4.95	3.00
ER119A-065		PR SH 119A BOULDER CANYON	01/03/19	2,500.00	3.60	4.65	2.00
STA119A-069		SH 119: NEDERLAND - EAST					
STR0132-021		SH 13-MOFFAT COUNTY-CR 3 SOUT	01/10/19	500.00	7.00	2.71	2.65
FBR0341-087		US 34 OVER NORTH FORK CO RIVE	01/10/19	765.00	5.00	3.90	2.46
STR141A-047		SH 141 MP 120-143 MESA COUNTY	01/17/19	350.00	8.00	4.45	5.00
NHPP0701-241		I-70 TRUCK PARKING GARFIELD C	01/17/19	1,000.00	4.50	4.18	3.25
STR0241-062		US 24 143.4 - 148	01/24/19	625.00	5.00	8.50	4.00
ER072A-040		PR SH72A FLOOD PERMANENT REPA	01/31/19	300.00	5.00	4.28	3.00
NHPP072A-041		PR SH72A FLOOD PERMANENT REPA					
STAM086-075		SH96A ABRIENDO - ORMAN SAFETY	01/31/19	500.00	4.30	4.15	1.45
NHPP0821-107		SH 82 GLENWOOD SPRINGS TO CA	02/07/19	880.00	5.00	2.18	2.85
ITSSW01-638		ETHERNET PHASE III (PRIMARYLY	02/07/19	40.00	4.00	6.00	2.00
NHPP145A-065		SH 145 PASSING LANES AT DEEP	02/14/19	151.00	5.00	3.19	1.50
NHPP070A-028		FALL RIVER ROAD BRIDGE	02/21/19	2,896.00	5.00	2.58	2.10
NHPP1601-073		US 160 PASSING LANE NORTH OF	03/07/19	1,000.00	3.00	3.30	2.60
C R100-315		R1 ADA CURB RAMPS - PH 5	03/07/19	500.00	5.00	7.50	8.00
SHE2254-090		Colfax & I-225, Colfax & Cham	03/07/19	20.00	4.00	22.50	15.00
NHPP050A-033		US50 West of Delta EB Lanes R	03/14/19	500.00	5.00	2.92	2.35

COLORADO DEPARTMENT OF TRANSPORTATION
 ITEM UNIT COSTS BY PROJECTS -- 2019 COST DATA

13:44 Wednesday, August 7, 2019 211

PROJECT NUMBER	ITEM NUMBER/ PROJECT LOCATION	ITEM DESCRIPTION/ PROJECT LOCATION	DATE LET	UNIT/ QUANTITY	ENGR. EST.	AVERAGE BID	AWARDED BID
===== 607-11525		Fence (Plastic)		Lin Foot	=====		
NHPP0503-087		US 50 PASSING LANES EAST OF S	03/21/19	500.00	4.00	3.50	3.00
SHE 0252-481		I-25 RAMP METER INSTALLATION	03/21/19	2,260.00	4.00	4.67	4.00
SHER100-308		MIDPOINT - SIGNAL CONST PACKA	03/21/19	290.00	5.00	4.75	3.50
NHPP2254-089		I-225 RESURFACING FROM I-25 T	03/21/19	500.00	4.50	5.42	5.00
STM0242-077		US24 - 8TH ST TO WEST OF MANI	03/28/19	500.00	8.00	3.33	3.50
STA0131-070 HMA ALT		SH 13 CR 5 NORTH AND SOUTH	03/28/19	1,000.00	4.00	3.27	1.20
STA0131-070 PCCP ALT		SH 13 CR 5 NORTH AND SOUTH					
		WEIGHTED AVERAGE FOR THE FIRST QUARTER		18,877.00	4.69	4.04	3.05
NHPP030A-035		US 285/SH30	04/04/19	100.00	5.00	15.00	15.00
BR071A-020		REPLACEMENT OF STRUCTURE L-22	04/18/19	2,000.00	3.50	3.57	2.90
NHPP0703-445		I-70 WESTBOUND PEAK PERIOD SH	04/25/19	1,118.00	4.00	3.49	2.00
NHPP2851-012		US 285 Antonito to Estrella C	05/02/19	100.00	4.00	11.62	8.00
IM0252-456		I-25 COLORADO SPRINGS RAMP ME	05/16/19	1,000.00	4.00	3.64	1.92
CR300-248		CRAIG RESIDENCY ADA RAMPS	05/16/19	500.00	7.00	2.00	0.50
FBR0063-057		US-6 F-09-K BRIDGE OVER CASTL	05/30/19	200.00	4.00	3.25	3.00
NHPP0703-442		I-70 SILVERPLUME SOUNDWALL AN	06/13/19	2,050.00	4.00	3.22	2.00
NHPP030A-036		SH 30 & TOWER RD IMPROVEMENTS	06/13/19	500.00	4.00	5.00	5.00
STR 141A-040		R5 YEAR 4 BRDG PREV MAINT RAM	06/20/19	470.00	3.00	7.00	10.00
NHPP160A-030		US160 MM 43.2, 150.4, 156.3,	06/20/19	2,657.00	5.00	3.68	3.50
		WEIGHTED AVERAGE FOR THE SECOND QUARTER		10,695.00	4.26	3.56	3.15
		WEIGHTED AVERAGE FOR THE YEAR		29,572.00	4.53	3.89	3.09
===== 607-11530		Fence (Spec)		Lin Foot	=====		
ER119A-065		PR SH 119A BOULDER CANYON	01/03/19	74.00	25.00	26.85	18.00
STA119A-069		SH 119: NEDERLAND - EAST					
STA0131-070 HMA ALT		SH 13 CR 5 NORTH AND SOUTH	03/28/19	438.00	60.00	30.45	31.50
STA0131-070 PCCP ALT		SH 13 CR 5 NORTH AND SOUTH					
		WEIGHTED AVERAGE FOR THE FIRST QUARTER		512.00	54.94	29.33	28.09
		WEIGHTED AVERAGE FOR THE YEAR		512.00	54.94	29.33	28.09
===== 607-11580		Fence (Temp)		Lin Foot	=====		
NHPP006A-058		US 6 LOVELAND PASS - I-70 (FY	03/07/19	100.00	10.00	6.95	10.89
		WEIGHTED AVERAGE FOR THE FIRST QUARTER		100.00	10.00	6.95	10.89

COLORADO DEPARTMENT OF TRANSPORTATION
 ITEM UNIT COSTS BY PROJECTS -- 2019 COST DATA

13:44 Wednesday, August 7, 2019 212

PROJECT NUMBER	ITEM NUMBER/ PROJECT LOCATION	ITEM DESCRIPTION/ PROJECT LOCATION	DATE LET	UNIT/ QUANTITY	ENGR. EST.	AVERAGE BID	AWARDED BID
=====	607-11580	Fence (Temp)		Lin Foot	=====		
NHPP160A-030		US160 MM 43.2, 150.4, 156.3,	06/20/19	267.00	10.00	6.50	5.50
		WEIGHTED AVERAGE FOR THE SECOND QUARTER		267.00	10.00	6.50	5.50
		WEIGHTED AVERAGE FOR THE YEAR		367.00	10.00	6.62	6.97
=====	607-15000	Fence Conc (Sound)		Sq Foot	=====		
NHPP0703-442		I-70 SILVERPLUME SOUNDWALL AN	06/13/19	19,170.00	60.00	112.56	54.00
		WEIGHTED AVERAGE FOR THE SECOND QUARTER		19,170.00	60.00	112.56	54.00
		WEIGHTED AVERAGE FOR THE YEAR		19,170.00	60.00	112.56	54.00
=====	607-32208	Wood Snow Fence (8 Ft)		Each	=====		
STR0132-021		SH 13-MOFFAT COUNTY-CR 3 SOUT	01/10/19	590.00	565.00	452.40	416.00
		WEIGHTED AVERAGE FOR THE FIRST QUARTER		590.00	565.00	452.40	416.00
		WEIGHTED AVERAGE FOR THE YEAR		590.00	565.00	452.40	416.00
=====	607-53005	Fence CL (Spec)		Lin Foot	=====		
FBR0253-247		I25 AT VINE DRIVE BRIDGE REPL	03/07/19	505.00	135.00	279.82	275.00
		WEIGHTED AVERAGE FOR THE FIRST QUARTER		505.00	135.00	279.82	275.00
		WEIGHTED AVERAGE FOR THE YEAR		505.00	135.00	279.82	275.00
=====	607-53136	Fence CL (36 In)		Lin Foot	=====		
NHPP0703-445		I-70 WESTBOUND PEAK PERIOD SH	04/25/19	1,280.00	15.00	19.91	20.00
FBR0063-057		US-6 F-09-K BRIDGE OVER CASTL	05/30/19	824.00	70.00	32.50	30.00
		WEIGHTED AVERAGE FOR THE SECOND QUARTER		2,104.00	36.54	23.69	23.92
		WEIGHTED AVERAGE FOR THE YEAR		2,104.00	36.54	23.69	23.92

COLORADO DEPARTMENT OF TRANSPORTATION
 ITEM UNIT COSTS BY PROJECTS -- 2019 COST DATA

13:44 Wednesday, August 7, 2019 213

PROJECT NUMBER	ITEM NUMBER/ PROJECT LOCATION	ITEM DESCRIPTION/ PROJECT LOCATION	DATE LET	UNIT/ QUANTITY	ENGR. EST.	AVERAGE BID	AWARDED BID
=====	607-53148	Fence CL (48 In)		Lin Foot	=====		
STR0241-062		US 24 143.4 - 148	01/24/19	53.00	50.00	90.33	100.00
		WEIGHTED AVERAGE FOR THE FIRST QUARTER		53.00	50.00	90.33	100.00
		WEIGHTED AVERAGE FOR THE YEAR		53.00	50.00	90.33	100.00
=====	607-53161	Fence CL (Spec) (60 In)		Lin Foot	=====		
NHPP030A-035		US 285/SH30	04/04/19	69.00	120.00	83.00	83.00
		WEIGHTED AVERAGE FOR THE SECOND QUARTER		69.00	120.00	83.00	83.00
		WEIGHTED AVERAGE FOR THE YEAR		69.00	120.00	83.00	83.00
=====	607-55040	Mesh Anchor		Each	=====		
ER119A-065 STA119A-069		PR SH 119A BOULDER CANYON SH 119: NEDERLAND - EAST	01/03/19	50.00	500.00	965.46	840.00
		WEIGHTED AVERAGE FOR THE FIRST QUARTER		50.00	500.00	965.46	840.00
NHPP0703-445		I-70 WESTBOUND PEAK PERIOD SH 04/25/19		855.00	550.00	522.05	500.00
		WEIGHTED AVERAGE FOR THE SECOND QUARTER		855.00	550.00	522.05	500.00
		WEIGHTED AVERAGE FOR THE YEAR		905.00	547.24	581.87	518.78
=====	607-55050	Mesh Anchor (Spec)		Each	=====		
NHPP0703-445		I-70 WESTBOUND PEAK PERIOD SH 04/25/19		85.00	2000.00	1197.07	1500.00
		WEIGHTED AVERAGE FOR THE SECOND QUARTER		85.00	2000.00	1197.07	1500.00
		WEIGHTED AVERAGE FOR THE YEAR		85.00	2000.00	1197.07	1500.00
=====	607-55060	Mesh Pin		Each	=====		
NHPP0703-445		I-70 WESTBOUND PEAK PERIOD SH 04/25/19		50.00	260.00	177.62	170.00
		WEIGHTED AVERAGE FOR THE SECOND QUARTER		50.00	260.00	177.62	170.00
		WEIGHTED AVERAGE FOR THE YEAR		50.00	260.00	177.62	170.00

COLORADO DEPARTMENT OF TRANSPORTATION
 ITEM UNIT COSTS BY PROJECTS -- 2019 COST DATA

13:44 Wednesday, August 7, 2019 214

PROJECT NUMBER	ITEM NUMBER/ PROJECT LOCATION	ITEM DESCRIPTION/ PROJECT LOCATION	DATE LET	UNIT/ QUANTITY	ENGR. EST.	AVERAGE BID	AWARDED BID
=====	607-55100	Wire Mesh (Draped)		Sq Foot	=====		
ER119A-065 STA119A-069		PR SH 119A BOULDER CANYON SH 119: NEDERLAND - EAST	01/03/19	68,700.00	4.00	2.77	3.15
		WEIGHTED AVERAGE FOR THE FIRST QUARTER		68,700.00	4.00	2.77	3.15
NHPP0703-445		I-70 WESTBOUND PEAK PERIOD SH	04/25/19	117,295.00	6.00	2.45	2.40
		WEIGHTED AVERAGE FOR THE SECOND QUARTER		117,295.00	6.00	2.45	2.40
		WEIGHTED AVERAGE FOR THE YEAR		185,995.00	5.26	2.65	2.68
=====	607-55104	Wire Mesh (Special)		Sq Foot	=====		
NHPP0703-445		I-70 WESTBOUND PEAK PERIOD SH	04/25/19	54,445.00	14.00	8.38	8.50
		WEIGHTED AVERAGE FOR THE SECOND QUARTER		54,445.00	14.00	8.38	8.50
		WEIGHTED AVERAGE FOR THE YEAR		54,445.00	14.00	8.38	8.50
=====	607-56001	Fence (Animal Protect)		Lin Foot	=====		
FBR0341-087		US 34 OVER NORTH FORK CO RIVE	01/10/19	50.00	13.00	21.55	13.33
		WEIGHTED AVERAGE FOR THE FIRST QUARTER		50.00	13.00	21.55	13.33
		WEIGHTED AVERAGE FOR THE YEAR		50.00	13.00	21.55	13.33
=====	607-60108	8 Ft Gate		Each	=====		
FBR0063-057		US-6 F-09-K BRIDGE OVER CASTL	05/30/19	1.00	1000.00	392.50	385.00
		WEIGHTED AVERAGE FOR THE SECOND QUARTER		1.00	1000.00	392.50	385.00
		WEIGHTED AVERAGE FOR THE YEAR		1.00	1000.00	392.50	385.00
=====	607-60110	10 Ft Gate		Each	=====		
NHPP1601-073		US 160 PASSING LANE NORTH OF	03/07/19	4.00	700.00	720.00	640.00
		WEIGHTED AVERAGE FOR THE FIRST QUARTER		4.00	700.00	720.00	640.00

COLORADO DEPARTMENT OF TRANSPORTATION
 ITEM UNIT COSTS BY PROJECTS -- 2019 COST DATA

13:44 Wednesday, August 7, 2019 215

PROJECT NUMBER	ITEM NUMBER/ PROJECT LOCATION	ITEM DESCRIPTION/ PROJECT LOCATION	DATE LET	UNIT/ QUANTITY	ENGR. EST.	AVERAGE BID	AWARDED BID
=====	607-60110	10 Ft Gate		Each	=====		
ER145A-081		SH 145 MP 21 EMERGENCY ROCKFA	06/07/19	1.00	700.00	297.50	300.00
		WEIGHTED AVERAGE FOR THE SECOND QUARTER		1.00	700.00	297.50	300.00
		WEIGHTED AVERAGE FOR THE YEAR		5.00	700.00	635.50	572.00
=====	607-60116	16 Ft Gate		Each	=====		
NHPP0503-087		US 50 PASSING LANES EAST OF S	03/21/19	5.00	800.00	490.00	480.00
STA0131-070 HMA ALT		SH 13 CR 5 NORTH AND SOUTH	03/28/19	16.00	1500.00	397.57	242.00
STA0131-070 PCCP ALT		SH 13 CR 5 NORTH AND SOUTH					
		WEIGHTED AVERAGE FOR THE FIRST QUARTER		21.00	1333.33	413.51	333.54
		WEIGHTED AVERAGE FOR THE YEAR		21.00	1333.33	413.51	333.54
=====	607-60117	16 Ft Gate (Spec)		Each	=====		
STR0132-021		SH 13-MOFFAT COUNTY-CR 3 SOUT	01/10/19	18.00	700.00	289.40	260.00
STA0131-070 HMA ALT		SH 13 CR 5 NORTH AND SOUTH	03/28/19	28.00	1500.00	434.71	242.00
STA0131-070 PCCP ALT		SH 13 CR 5 NORTH AND SOUTH					
		WEIGHTED AVERAGE FOR THE FIRST QUARTER		46.00	1186.96	359.55	252.13
		WEIGHTED AVERAGE FOR THE YEAR		46.00	1186.96	359.55	252.13
=====	607-60120	20 Ft Gate		Each	=====		
FBR0341-087		US 34 OVER NORTH FORK CO RIVE	01/10/19	1.00	980.00	1047.26	905.24
NHPP0503-087		US 50 PASSING LANES EAST OF S	03/21/19	2.00	1600.00	540.00	530.00
STA0131-070 HMA ALT		SH 13 CR 5 NORTH AND SOUTH	03/28/19	6.00	1900.00	528.56	364.00
STA0131-070 PCCP ALT		SH 13 CR 5 NORTH AND SOUTH					
		WEIGHTED AVERAGE FOR THE FIRST QUARTER		9.00	1731.11	641.34	509.54
		WEIGHTED AVERAGE FOR THE YEAR		9.00	1731.11	641.34	509.54
=====	607-60121	20 Ft Gate (Spec)		Each	=====		
STA0131-070 HMA ALT		SH 13 CR 5 NORTH AND SOUTH	03/28/19	16.00	1900.00	616.20	667.00

COLORADO DEPARTMENT OF TRANSPORTATION
 ITEM UNIT COSTS BY PROJECTS -- 2019 COST DATA

13:44 Wednesday, August 7, 2019 216

PROJECT NUMBER	ITEM NUMBER/ PROJECT LOCATION	ITEM DESCRIPTION/ PROJECT LOCATION	DATE LET	UNIT/ QUANTITY	ENGR. EST.	AVERAGE BID	AWARDED BID
=====	607-60121	20 Ft Gate (Spec)		Each			
STA0131-070	PCCP ALT	SH 13 CR 5 NORTH AND SOUTH					
	WEIGHTED AVERAGE FOR THE FIRST QUARTER			16.00	1900.00	616.20	667.00
	WEIGHTED AVERAGE FOR THE YEAR			16.00	1900.00	616.20	667.00
=====	607-60620	Road Closure Gate		Each			
NHPP070A-028		FALL RIVER ROAD BRIDGE	02/21/19	1.00	15000.00	20896.00	10700.00
	WEIGHTED AVERAGE FOR THE FIRST QUARTER			1.00	15000.00	20896.00	10700.00
STRR200-257		ROAD CLOSURE GATES ON VARIOUS	05/30/19	8.00	15000.00	10879.00	10500.00
	WEIGHTED AVERAGE FOR THE SECOND QUARTER			8.00	15000.00	10879.00	10500.00
	WEIGHTED AVERAGE FOR THE YEAR			9.00	15000.00	13264.00	10522.22
=====	608-00000	Conc Sidewalk		Sq Yard			
SHER100-289		INTERSECTIONS @ SH83 & LONGS	01/03/19	40.00	75.00	71.60	77.00
ER119A-065		PR SH 119A BOULDER CANYON	01/03/19	125.00	60.00	65.33	56.00
STA119A-069		SH 119: NEDERLAND - EAST					
STR0241-062		US 24 143.4 - 148	01/24/19	2,173.00	50.00	89.83	85.00
STAM086-075		SH96A ABRIENDO - ORMAN SAFETY	01/31/19	35.00	75.00	96.05	68.15
SHER100-284		FY19 NORTH SIGNAL PKG	02/21/19	20.00	75.00	115.33	130.00
C R100-315		R1 ADA CURB RAMPS - PH 5	03/07/19	466.00	85.00	116.50	105.00
SHE2254-090		Colfax & I-225, Colfax & Cham	03/07/19	350.00	75.00	82.50	65.00
NHPP0702-378		I-70 OFFICERS GULCH TO FRISCO	03/14/19	18.00	300.00	185.58	358.75
SHER100-308		MIDPOINT - SIGNAL CONST PACKA	03/21/19	231.00	50.00	90.00	104.00
NHPP2254-089		I-225 RESURFACING FROM I-25 T	03/21/19	54.00	80.00	182.65	200.00
STM0242-077		US24 - 8TH ST TO WEST OF MANI	03/28/19	231.00	67.00	51.67	50.00
	WEIGHTED AVERAGE FOR THE FIRST QUARTER			3,743.00	60.35	88.69	86.64
NHPP030A-035		US 285/SH30	04/04/19	83.30	75.00	110.00	110.00
MTCE0641-103		MTCE R3 FY20 SH 64 RANGELY PE	05/02/19	382.00	125.00	106.00	72.00
CR300-248		CRAIG RESIDENCY ADA RAMPS	05/16/19	439.00	70.00	123.00	56.00

COLORADO DEPARTMENT OF TRANSPORTATION
 ITEM UNIT COSTS BY PROJECTS -- 2019 COST DATA

13:44 Wednesday, August 7, 2019 217

PROJECT NUMBER	ITEM NUMBER/ PROJECT LOCATION	ITEM DESCRIPTION/ PROJECT LOCATION	DATE LET	UNIT/ QUANTITY	ENGR. EST.	AVERAGE BID	AWARDED BID
=====	608-00000	Conc Sidewalk		Sq Yard	=====	=====	=====
STMC430-020		ADA RAMPS DIVIDE ESB	05/23/19	59.00	102.00	114.56	114.56
STR 141A-040		R5 YEAR 4 BRDG PREV MAINT RAM	06/20/19	5.00	130.00	245.00	150.00
		WEIGHTED AVERAGE FOR THE SECOND QUARTER		968.30	94.39	117.02	71.01
		WEIGHTED AVERAGE FOR THE YEAR		4,711.30	67.34	93.51	83.43
=====	608-00005	Conc Sidewalk (Spec)		Sq Yard	=====	=====	=====
SHER100-308		MIDPOINT - SIGNAL CONST PACKA	03/21/19	87.00	150.00	172.00	254.00
		WEIGHTED AVERAGE FOR THE FIRST QUARTER		87.00	150.00	172.00	254.00
NHPP0703-445		I-70 WESTBOUND PEAK PERIOD SH	04/25/19	95.00	100.00	133.06	145.00
		WEIGHTED AVERAGE FOR THE SECOND QUARTER		95.00	100.00	133.06	145.00
		WEIGHTED AVERAGE FOR THE YEAR		182.00	123.90	147.82	197.10
=====	608-00006	Conc Sidewalk (6 In)		Sq Yard	=====	=====	=====
ER119A-065		PR SH 119A BOULDER CANYON	01/03/19	1,524.00	55.00	65.78	59.00
STA119A-069		SH 119: NEDERLAND - EAST					
NHPP0821-107		SH 82 GLENWOOD SPRINGS TO CA	02/07/19	7.00	150.00	197.50	120.00
		WEIGHTED AVERAGE FOR THE FIRST QUARTER		1,531.00	55.43	65.93	59.28
NHPP030A-035		US 285/SH30	04/04/19	98.00	85.00	135.00	135.00
FSA0252-468		I-25 AND PLUM CREEK IMPROVEME	04/18/19	23.00	80.00	94.63	96.00
NHPP0703-445		I-70 WESTBOUND PEAK PERIOD SH	04/25/19	307.00	65.00	89.91	105.00
C2571-013		SH257 & 392:WINDSOR CURB RAMP	05/02/19	140.00	95.00	119.00	70.00
		WEIGHTED AVERAGE FOR THE SECOND QUARTER		568.00	76.45	101.06	101.18
		WEIGHTED AVERAGE FOR THE YEAR		2,099.00	61.12	69.85	70.62
=====	608-00010	Conc Curb Ramp		Sq Yard	=====	=====	=====
SHER100-289		INTERSECTIONS @ SH83 & LONGS	01/03/19	140.00	150.00	152.80	180.00

PROJECT NUMBER	ITEM NUMBER/ PROJECT LOCATION	ITEM DESCRIPTION/ PROJECT LOCATION	DATE LET	UNIT/ QUANTITY	ENGR. EST.	AVERAGE BID	AWARDED BID
===== 608-00010							
		Conc Curb Ramp		Sq Yard			
ER119A-065		PR SH 119A BOULDER CANYON	01/03/19	106.00	147.00	171.47	120.00
STA119A-069		SH 119: NEDERLAND - EAST					
STR0241-062		US 24 143.4 - 148	01/24/19	581.00	150.00	195.00	180.00
STAM086-075		SH96A ABRIENDO - ORMAN SAFETY	01/31/19	429.00	60.00	139.00	126.50
NHPP0821-107		SH 82 GLENWOOD SPRINGS TO CA	02/07/19	302.00	160.00	190.75	156.50
NHPP0741-022		SH 74: I-70 TO CR 65 RESURFAC	02/14/19	133.00	200.00	155.95	146.55
SHER100-284		FY19 NORTH SIGNAL PKG	02/21/19	202.00	175.00	149.00	185.00
C R100-315		R1 ADA CURB RAMPS - PH 5	03/07/19	1,437.00	162.00	197.50	175.00
SHE2254-090		Colfax & I-225, Colfax & Cham	03/07/19	447.00	155.00	264.00	238.00
NHPP0702-378		I-70 OFFICERS GULCH TO FRISCO	03/14/19	46.00	200.00	277.75	461.25
SHER100-308		MIDPOINT - SIGNAL CONST PACKA	03/21/19	220.00	185.00	160.50	196.00
NHPP2254-089		I-225 RESURFACING FROM I-25 T	03/21/19	129.00	165.00	384.70	425.00
STM0242-077		US24 - 8TH ST TO WEST OF MANI	03/28/19	114.00	146.05	216.67	190.00
		WEIGHTED AVERAGE FOR THE FIRST QUARTER		4,286.00	151.58	192.64	186.56
NHPP030A-035		US 285/SH30	04/04/19	884.40	155.00	250.00	250.00
FSA0252-468		I-25 AND PLUM CREEK IMPROVEME	04/18/19	12.00	200.00	185.38	213.00
NHPP0703-445		I-70 WESTBOUND PEAK PERIOD SH	04/25/19	81.00	155.00	188.75	175.00
C2571-013		SH257 & 392:WINDSOR CURB RAMP	05/02/19	1,178.00	170.00	175.33	180.00
MTCE0641-103		MTCE R3 FY20 SH 64 RANGELY PE	05/02/19	179.00	180.00	203.50	132.00
FSA2873-190		US 287 AND FOOTHILLS PARKWAY	05/02/19	106.00	185.00	202.50	180.00
CR300-248		CRAIG RESIDENCY ADA RAMPS	05/16/19	3,085.00	150.00	201.33	126.00
STMC430-020		ADA RAMPS DIVIDE ESB	05/23/19	340.00	250.00	180.27	180.27
		WEIGHTED AVERAGE FOR THE SECOND QUARTER		5,865.40	162.29	197.38	160.70
		WEIGHTED AVERAGE FOR THE YEAR		10,151.40	157.76	195.33	171.62
===== 608-00015							
		Detectable Warnings		Sq Foot			
STR0241-062		US 24 143.4 - 148	01/24/19	18.00	100.00	62.50	64.00
STAM086-075		SH96A ABRIENDO - ORMAN SAFETY	01/31/19	70.00	118.83	90.92	72.75
C R100-315		R1 ADA CURB RAMPS - PH 5	03/07/19	105.00	90.00	111.50	125.00
NHPP0702-378		I-70 OFFICERS GULCH TO FRISCO	03/14/19	16.00	125.00	170.08	256.25
		WEIGHTED AVERAGE FOR THE FIRST QUARTER		209.00	103.20	103.54	112.29
NHPP030A-035		US 285/SH30	04/04/19	13.40	100.00	100.00	100.00
C2571-013		SH257 & 392:WINDSOR CURB RAMP	05/02/19	13.00	125.00	122.67	150.00

COLORADO DEPARTMENT OF TRANSPORTATION
ITEM UNIT COSTS BY PROJECTS -- 2019 COST DATA

13:44 Wednesday, August 7, 2019 219

PROJECT NUMBER	ITEM NUMBER/ PROJECT LOCATION	ITEM DESCRIPTION/ PROJECT LOCATION	DATE LET	UNIT/ QUANTITY	ENGR. EST.	AVERAGE BID	AWARDED BID
===== CR300-248	608-00015	Detectable Warnings CRAIG RESIDENCY ADA RAMP	05/16/19	Sq Foot 189.00	100.00	49.33	50.00
		WEIGHTED AVERAGE FOR THE SECOND QUARTER		215.40	101.51	55.05	59.15
		WEIGHTED AVERAGE FOR THE YEAR		424.40	102.34	77.22	85.32
===== NHPP0821-107	608-00018	Curb Ramp (Temp Parallel) (Single) SH 82 GLENWOOD SPRINGS TO CA	02/07/19	Each 4.00	1500.00	1190.00	380.00
		WEIGHTED AVERAGE FOR THE FIRST QUARTER		4.00	1500.00	1190.00	380.00
		WEIGHTED AVERAGE FOR THE YEAR		4.00	1500.00	1190.00	380.00
===== ER119A-065 STA119A-069	608-00026	Conc Bikeway (6 In) PR SH 119A BOULDER CANYON SH 119: NEDERLAND - EAST	01/03/19	Sq Yard 2,386.00	45.00	70.68	65.00
		WEIGHTED AVERAGE FOR THE FIRST QUARTER		2,386.00	45.00	70.68	65.00
		WEIGHTED AVERAGE FOR THE YEAR		2,386.00	45.00	70.68	65.00
===== ER119A-065 STA119A-069	608-00028	Conc Bikeway (8 In) PR SH 119A BOULDER CANYON SH 119: NEDERLAND - EAST	01/03/19	Sq Yard 429.00	50.00	90.41	75.00
		WEIGHTED AVERAGE FOR THE FIRST QUARTER		429.00	50.00	90.41	75.00
		WEIGHTED AVERAGE FOR THE YEAR		429.00	50.00	90.41	75.00
===== NHPP0703-445	608-00040	Conc Bikeway (Spec) I-70 WESTBOUND PEAK PERIOD SH	04/25/19	Sq Yard 153.00	100.00	143.51	150.00
		WEIGHTED AVERAGE FOR THE SECOND QUARTER		153.00	100.00	143.51	150.00
		WEIGHTED AVERAGE FOR THE YEAR		153.00	100.00	143.51	150.00
===== STR0241-062	608-10010	Sidewalk Drain US 24 143.4 - 148	01/24/19	Each 7.00	3000.00	2576.67	2700.00
		WEIGHTED AVERAGE FOR THE FIRST QUARTER		7.00	3000.00	2576.67	2700.00
		WEIGHTED AVERAGE FOR THE YEAR		7.00	3000.00	2576.67	2700.00

COLORADO DEPARTMENT OF TRANSPORTATION
ITEM UNIT COSTS BY PROJECTS -- 2019 COST DATA

13:44 Wednesday, August 7, 2019 220

PROJECT NUMBER	ITEM NUMBER/ PROJECT LOCATION	ITEM DESCRIPTION/ PROJECT LOCATION	DATE LET	UNIT/ QUANTITY	ENGR. EST.	AVERAGE BID	AWARDED BID
===== 609-20010		Curb Ty 2 B		Lin Foot	=====		
STR0241-062		US 24 143.4 - 148	01/24/19	27.00	30.00	76.50	72.00
C R100-315		R1 ADA CURB RAMPS - PH 5	03/07/19	10.00	80.00	68.00	80.00
SHE2254-090		Colfax & I-225, Colfax & Cham	03/07/19	311.00	70.00	44.00	23.00
		WEIGHTED AVERAGE FOR THE FIRST QUARTER		348.00	67.18	48.30	28.44
NHPP030A-035		US 285/SH30	04/04/19	20.00	65.00	65.00	65.00
FSA2873-190		US 287 AND FOOTHILLS PARKWAY	05/02/19	11.00	100.00	75.00	80.00
		WEIGHTED AVERAGE FOR THE SECOND QUARTER		31.00	77.42	70.24	70.32
		WEIGHTED AVERAGE FOR THE YEAR		379.00	68.02	49.51	31.87
===== 609-21010		C and G Ty 2 I-B		Lin Foot	=====		
SHER100-289		INTERSECTIONS @ SH83 & LONGS	01/03/19	250.00	17.00	29.20	30.00
ER119A-065		PR SH 119A BOULDER CANYON	01/03/19	282.00	25.00	33.33	34.00
STA119A-069		SH 119: NEDERLAND - EAST					
STAM086-075		SH96A ABRIENDO - ORMAN SAFETY	01/31/19	213.00	24.00	37.08	28.25
NHPP0741-022		SH 74: I-70 TO CR 65 RESURFAC	02/14/19	843.00	22.00	32.35	40.15
C R100-315		R1 ADA CURB RAMPS - PH 5	03/07/19	379.00	35.00	49.50	45.00
SHE2254-090		Colfax & I-225, Colfax & Cham	03/07/19	696.00	20.00	40.00	30.00
SHER100-308		MIDPOINT - SIGNAL CONST PACKA	03/21/19	382.00	35.00	36.25	33.50
NHPP2254-089		I-225 RESURFACING FROM I-25 T	03/21/19	179.00	17.00	59.24	47.50
		WEIGHTED AVERAGE FOR THE FIRST QUARTER		3,224.00	24.37	36.21	36.04
NHPP030A-035		US 285/SH30	04/04/19	8,558.40	20.00	40.00	40.00
FSA0252-468		I-25 AND PLUM CREEK IMPROVEME	04/18/19	458.00	25.00	35.50	30.00
NHPP0703-445		I-70 WESTBOUND PEAK PERIOD SH	04/25/19	487.00	20.00	34.16	32.00
C2571-013		SH257 & 392:WINDSOR CURB RAMP	05/02/19	41.00	50.00	43.67	45.00
FSA2873-190		US 287 AND FOOTHILLS PARKWAY	05/02/19	157.00	40.00	37.50	30.00
STMC430-020		ADA RAMPS DIVIDE ESB	05/23/19	94.00	50.00	46.98	46.98
		WEIGHTED AVERAGE FOR THE SECOND QUARTER		9,795.40	20.97	38.67	39.06
		WEIGHTED AVERAGE FOR THE YEAR		13,019.40	21.81	37.52	38.31
===== 609-21011		C and G Ty 2 I-M		Lin Foot	=====		
SHER100-289		INTERSECTIONS @ SH83 & LONGS	01/03/19	1,800.00	22.00	26.40	27.00

COLORADO DEPARTMENT OF TRANSPORTATION
 ITEM UNIT COSTS BY PROJECTS -- 2019 COST DATA

13:44 Wednesday, August 7, 2019 221

PROJECT NUMBER	ITEM NUMBER/ PROJECT LOCATION	ITEM DESCRIPTION/ PROJECT LOCATION	DATE LET	UNIT/ QUANTITY	ENGR. EST.	AVERAGE BID	AWARDED BID
===== 609-21011		C and G Ty 2 I-M		Lin Foot	=====	=====	=====
NHPP0701-241		I-70 TRUCK PARKING GARFIELD C	01/17/19	1,636.00	30.00	32.74	26.00
STM0242-077		US24 - 8TH ST TO WEST OF MANI	03/28/19	2,499.00	35.00	21.42	16.25
		WEIGHTED AVERAGE FOR THE FIRST QUARTER		5,935.00	29.68	26.99	22.20
NHPP0703-445		I-70 WESTBOUND PEAK PERIOD SH	04/25/19	307.00	26.00	34.82	33.00
		WEIGHTED AVERAGE FOR THE SECOND QUARTER		307.00	26.00	34.82	33.00
		WEIGHTED AVERAGE FOR THE YEAR		6,242.00	29.50	27.27	22.73
===== 609-21013		C and G Ty 2 I-M (Spec)		Lin Foot	=====	=====	=====
STM0242-077		US24 - 8TH ST TO WEST OF MANI	03/28/19	361.00	35.00	33.33	28.00
		WEIGHTED AVERAGE FOR THE FIRST QUARTER		361.00	35.00	33.33	28.00
		WEIGHTED AVERAGE FOR THE YEAR		361.00	35.00	33.33	28.00
===== 609-21020		C and G Ty 2 II-B		Lin Foot	=====	=====	=====
SHER100-289		INTERSECTIONS @ SH83 & LONGS	01/03/19	12.00	45.00	43.80	50.00
ER119A-065		PR SH 119A BOULDER CANYON	01/03/19	1,603.00	34.26	34.29	36.00
ST119A-069		SH 119: NEDERLAND - EAST					
STR0241-062		US 24 143.4 - 148	01/24/19	5,153.00	35.00	42.33	35.00
STAM086-075		SH96A ABRIENDO - ORMAN SAFETY	01/31/19	600.00	30.00	45.78	32.35
NHPP0821-107		SH 82 GLENWOOD SPRINGS TO CA	02/07/19	84.00	40.00	48.00	48.00
SHER100-284		FY19 NORTH SIGNAL PKG	02/21/19	214.00	45.00	39.67	45.00
FBR0253-247		I25 AT VINE DRIVE BRIDGE REPL	03/07/19	4,344.00	28.00	26.14	30.00
C R100-315		R1 ADA CURB RAMPS - PH 5	03/07/19	315.00	40.00	49.50	45.00
SHE2254-090		Colfax & I-225, Colfax & Cham	03/07/19	854.00	32.00	50.00	35.00
NHPP0702-378		I-70 OFFICERS GULCH TO FRISCO	03/14/19	18.00	60.00	81.17	102.50
SHER100-308		MIDPOINT - SIGNAL CONST PACKA	03/21/19	803.00	37.00	40.50	36.00
STM0242-077		US24 - 8TH ST TO WEST OF MANI	03/28/19	81.00	40.00	35.67	28.00
		WEIGHTED AVERAGE FOR THE FIRST QUARTER		14,081.00	32.84	32.01	34.03
NHPP030A-035		US 285/SH30	04/04/19	459.50	35.00	43.00	43.00

COLORADO DEPARTMENT OF TRANSPORTATION
 ITEM UNIT COSTS BY PROJECTS -- 2019 COST DATA

13:44 Wednesday, August 7, 2019 222

PROJECT NUMBER	ITEM NUMBER/ PROJECT LOCATION	ITEM DESCRIPTION/ PROJECT LOCATION	DATE LET	UNIT/ QUANTITY	ENGR. EST.	AVERAGE BID	AWARDED BID
===== 609-21020		C and G Ty 2 II-B		Lin Foot	=====	=====	=====
FSA0252-468		I-25 AND PLUM CREEK IMPROVEME	04/18/19	75.00	35.00	43.00	38.00
NHPP0703-445		I-70 WESTBOUND PEAK PERIOD SH	04/25/19	326.00	35.00	38.27	37.00
C2571-013		SH257 & 392:WINDSOR CURB RAMP	05/02/19	142.00	50.00	42.00	40.00
MTCE0641-103		MTCE R3 FY20 SH 64 RANGELY PE	05/02/19	583.00	40.00	52.00	34.00
FSA2873-190		US 287 AND FOOTHILLS PARKWAY	05/02/19	18.00	60.00	81.00	75.00
CR300-248		CRAIG RESIDENCY ADA RAMPS	05/16/19	633.00	40.00	89.00	37.00
SHE0701-243		I-70 EXIT 26 DDI MODIFICATION	05/16/19	731.00	35.00	33.63	27.00
STMC430-020		ADA RAMPS DIVIDE ESB	05/23/19	145.00	36.50	42.64	42.64
	WEIGHTED AVERAGE FOR THE SECOND QUARTER			3,112.50	37.85	51.00	35.62
	WEIGHTED AVERAGE FOR THE YEAR			17,193.50	33.75	33.75	34.32
===== 609-21021		C and G Ty 2 II-M		Lin Foot	=====	=====	=====
SHER100-289		INTERSECTIONS @ SH83 & LONGS	01/03/19	580.00	30.00	32.40	32.00
ER072A-040		PR SH72A FLOOD PERMANENT REPA	01/31/19	39.00	35.00	54.95	50.00
NHPP072A-041		PR SH72A FLOOD PERMANENT REPA					
STM0242-077		US24 - 8TH ST TO WEST OF MANI	03/28/19	1,070.00	40.00	26.00	21.00
	WEIGHTED AVERAGE FOR THE FIRST QUARTER			1,689.00	36.45	30.88	25.45
NHPP030A-035		US 285/SH30	04/04/19	2.80	40.00	200.00	200.00
NHPP0703-445		I-70 WESTBOUND PEAK PERIOD SH	04/25/19	312.00	35.00	38.61	38.00
	WEIGHTED AVERAGE FOR THE SECOND QUARTER			314.80	35.04	39.09	39.44
	WEIGHTED AVERAGE FOR THE YEAR			2,003.80	36.23	31.91	27.65
===== 609-21023		C and G Ty 2 II-B (Spec)		Lin Foot	=====	=====	=====
STAM086-075		SH96A ABRIENDO - ORMAN SAFETY	01/31/19	267.00	33.87	55.45	34.15
	WEIGHTED AVERAGE FOR THE FIRST QUARTER			267.00	33.87	55.45	34.15
	WEIGHTED AVERAGE FOR THE YEAR			267.00	33.87	55.45	34.15
===== 609-21900		C and G Ty 2 (Spec)		Lin Foot	=====	=====	=====
SHER100-308		MIDPOINT - SIGNAL CONST PACKA	03/21/19	96.00	50.00	107.00	135.00
	WEIGHTED AVERAGE FOR THE FIRST QUARTER			96.00	50.00	107.00	135.00

COLORADO DEPARTMENT OF TRANSPORTATION
 ITEM UNIT COSTS BY PROJECTS -- 2019 COST DATA

13:44 Wednesday, August 7, 2019 223

PROJECT NUMBER	ITEM NUMBER/ PROJECT LOCATION	ITEM DESCRIPTION/ PROJECT LOCATION	DATE LET	UNIT/ QUANTITY	ENGR. EST.	AVERAGE BID	AWARDED BID
=====	609-21900	C and G Ty 2 (Spec)		Lin Foot	=====		
STR 141A-040		R5 YEAR 4 BRDG PREV MAINT RAM	06/20/19	12.00	50.00	90.00	60.00
		WEIGHTED AVERAGE FOR THE SECOND QUARTER		12.00	50.00	90.00	60.00
		WEIGHTED AVERAGE FOR THE YEAR		108.00	50.00	105.11	126.67
=====	609-22021	CGS Ty 2 MS		Lin Foot	=====		
STR0241-062		US 24 143.4 - 148	01/24/19	16.00	60.00	143.33	115.00
		WEIGHTED AVERAGE FOR THE FIRST QUARTER		16.00	60.00	143.33	115.00
		WEIGHTED AVERAGE FOR THE YEAR		16.00	60.00	143.33	115.00
=====	609-24002	Gutter Ty 2 (2 Ft)		Lin Foot	=====		
ER119A-065		PR SH 119A BOULDER CANYON	01/03/19	129.00	30.00	37.44	27.00
STA119A-069		SH 119: NEDERLAND - EAST					
FBR0341-087		US 34 OVER NORTH FORK CO RIVE	01/10/19	350.00	75.00	28.39	42.24
		WEIGHTED AVERAGE FOR THE FIRST QUARTER		479.00	62.88	31.37	38.14
		WEIGHTED AVERAGE FOR THE YEAR		479.00	62.88	31.37	38.14
=====	609-24004	Gutter Ty 2 (4 Ft)		Lin Foot	=====		
STR0241-062		US 24 143.4 - 148	01/24/19	125.00	50.00	63.00	53.00
STAM086-075		SH96A ABRIENDO - ORMAN SAFETY	01/31/19	107.00	44.90	59.25	38.25
		WEIGHTED AVERAGE FOR THE FIRST QUARTER		232.00	47.65	61.27	46.20
NHPP0703-445		I-70 WESTBOUND PEAK PERIOD SH	04/25/19	423.00	50.00	36.57	34.00
		WEIGHTED AVERAGE FOR THE SECOND QUARTER		423.00	50.00	36.57	34.00
		WEIGHTED AVERAGE FOR THE YEAR		655.00	49.17	45.32	38.32

COLORADO DEPARTMENT OF TRANSPORTATION
ITEM UNIT COSTS BY PROJECTS -- 2019 COST DATA

13:44 Wednesday, August 7, 2019 224

PROJECT NUMBER	ITEM NUMBER/ PROJECT LOCATION	ITEM DESCRIPTION/ PROJECT LOCATION	DATE LET	UNIT/ QUANTITY	ENGR. EST.	AVERAGE BID	AWARDED BID
=====	609-24010	Gutter Ty 2 (10 Ft)		Lin Foot	=====		
ER072A-040		PR SH72A FLOOD PERMANENT REPA	01/31/19	187.00	20.00	108.89	105.00
NHPP072A-041		PR SH72A FLOOD PERMANENT REPA					
		WEIGHTED AVERAGE FOR THE FIRST QUARTER		187.00	20.00	108.89	105.00
		WEIGHTED AVERAGE FOR THE YEAR		187.00	20.00	108.89	105.00
=====	609-40010	Curb Ty 4 B		Lin Foot	=====		
NHPPR100-250		PACKAGE A (I-25 / I-70 / I-76	01/24/19	61.00	25.00	54.60	37.00
SHE2254-090		Colfax & I-225, Colfax & Cham	03/07/19	221.00	53.00	37.50	20.00
		WEIGHTED AVERAGE FOR THE FIRST QUARTER		282.00	46.94	44.48	23.68
		WEIGHTED AVERAGE FOR THE YEAR		282.00	46.94	44.48	23.68
=====	609-40031	Curb Ty 4 B (Key-Way)		Lin Foot	=====		
SHER100-289		INTERSECTIONS @ SH83 & LONGS	01/03/19	332.00	8.00	21.80	30.00
		WEIGHTED AVERAGE FOR THE FIRST QUARTER		332.00	8.00	21.80	30.00
		WEIGHTED AVERAGE FOR THE YEAR		332.00	8.00	21.80	30.00
=====	609-40120	Curb Median Special		Sq Yard	=====		
SHER100-289		INTERSECTIONS @ SH83 & LONGS	01/03/19	22.00	175.00	115.20	115.00
		WEIGHTED AVERAGE FOR THE FIRST QUARTER		22.00	175.00	115.20	115.00
		WEIGHTED AVERAGE FOR THE YEAR		22.00	175.00	115.20	115.00
=====	609-60011	Curb Ty 6 M		Lin Foot	=====		
FBR0341-087		US 34 OVER NORTH FORK CO RIVE	01/10/19	341.00	17.00	25.67	36.21
ER072A-040		PR SH72A FLOOD PERMANENT REPA	01/31/19	635.00	12.00	21.58	19.00
NHPP072A-041		PR SH72A FLOOD PERMANENT REPA					
SHE 0252-481		I-25 RAMP METER INSTALLATION	03/21/19	303.00	18.00	53.17	61.00

COLORADO DEPARTMENT OF TRANSPORTATION
 ITEM UNIT COSTS BY PROJECTS -- 2019 COST DATA

13:44 Wednesday, August 7, 2019 225

PROJECT NUMBER	ITEM NUMBER/ PROJECT LOCATION	ITEM DESCRIPTION/ PROJECT LOCATION	DATE LET	UNIT/ QUANTITY	ENGR. EST.	AVERAGE BID	AWARDED BID
===== 609-60011		Curb Ty 6 M		Lin Foot			
STM0242-077		US24 - 8TH ST TO WEST OF MANI	03/28/19	3,497.00	16.00	11.00	8.50
		WEIGHTED AVERAGE FOR THE FIRST QUARTER		4,776.00	15.67	18.07	15.21
BR071A-020		REPLACEMENT OF STRUCTURE L-22	04/18/19	50.00	20.00	33.67	16.00
NHPP0703-445		I-70 WESTBOUND PEAK PERIOD SH	04/25/19	46.00	65.00	85.23	15.00
		WEIGHTED AVERAGE FOR THE SECOND QUARTER		96.00	41.56	58.38	15.52
		WEIGHTED AVERAGE FOR THE YEAR		4,872.00	16.18	18.61	15.21
===== 609-71000		Curb (Special)		Lin Foot			
SHE2254-090		Colfax & I-225, Colfax & Cham	03/07/19	85.00	40.00	75.00	50.00
		WEIGHTED AVERAGE FOR THE FIRST QUARTER		85.00	40.00	75.00	50.00
NHPP030A-035		US 285/SH30	04/04/19	48.00	36.00	66.00	66.00
		WEIGHTED AVERAGE FOR THE SECOND QUARTER		48.00	36.00	66.00	66.00
		WEIGHTED AVERAGE FOR THE YEAR		133.00	38.56	73.02	55.77
===== 610-00010		Median Cover Matl (Dec)		Sq Foot			
SHER100-308		MIDPOINT - SIGNAL CONST PACKA	03/21/19	422.00	20.00	46.00	67.00
		WEIGHTED AVERAGE FOR THE FIRST QUARTER		422.00	20.00	46.00	67.00
		WEIGHTED AVERAGE FOR THE YEAR		422.00	20.00	46.00	67.00
===== 610-00020		Median Cover (Pattern Conc)		Sq Foot			
NHPP0701-241		I-70 TRUCK PARKING GARFIELD C	01/17/19	1,600.00	15.00	11.72	10.85
STAM086-075		SH96A ABRIENDO - ORMAN SAFETY	01/31/19	2,963.00	15.00	33.33	17.75
		WEIGHTED AVERAGE FOR THE FIRST QUARTER		4,563.00	15.00	23.09	15.33

COLORADO DEPARTMENT OF TRANSPORTATION
 ITEM UNIT COSTS BY PROJECTS -- 2019 COST DATA

13:44 Wednesday, August 7, 2019 226

PROJECT NUMBER	ITEM NUMBER/ PROJECT LOCATION	ITEM DESCRIPTION/ PROJECT LOCATION	DATE LET	UNIT/ QUANTITY	ENGR. EST.	AVERAGE BID	AWARDED BID
=====	610-00020	Median Cover (Pattern Conc)		Sq Foot	=====		
NHPP030A-035		US 285/SH30	04/04/19	43,858.00	12.00	12.00	12.00
FSA0252-468		I-25 AND PLUM CREEK IMPROVEME	04/18/19	3,780.00	15.00	16.80	17.70
		WEIGHTED AVERAGE FOR THE SECOND QUARTER		47,638.00	12.24	13.23	12.45
		WEIGHTED AVERAGE FOR THE YEAR		52,201.00	12.48	15.43	12.70
=====	610-00024	Median Cover (4 In Pattern Conc)		Sq Foot	=====		
SHE2254-090		Colfax & I-225, Colfax & Cham	03/07/19	3,979.00	7.00	16.00	10.00
		WEIGHTED AVERAGE FOR THE FIRST QUARTER		3,979.00	7.00	16.00	10.00
		WEIGHTED AVERAGE FOR THE YEAR		3,979.00	7.00	16.00	10.00
=====	610-00026	Median Cover (6 In Pattern Conc)		Sq Foot	=====		
SHER100-289		INTERSECTIONS @ SH83 & LONGS	01/03/19	1,269.00	15.00	12.40	11.00
STM0242-077		US24 - 8TH ST TO WEST OF MANI	03/28/19	7,031.00	10.00	14.67	11.00
		WEIGHTED AVERAGE FOR THE FIRST QUARTER		8,300.00	10.76	14.14	11.00
		WEIGHTED AVERAGE FOR THE YEAR		8,300.00	10.76	14.14	11.00
=====	610-00030	Median Cover Matl (Conc)		Sq Foot	=====		
SHER100-289		INTERSECTIONS @ SH83 & LONGS	01/03/19	7,266.00	6.00	8.60	7.00
NHPP0741-022		SH 74: I-70 TO CR 65 RESURFAC	02/14/19	3,555.00	6.00	12.92	16.25
C R100-315		R1 ADA CURB RAMPS - PH 5	03/07/19	1,082.00	10.00	27.75	17.50
SHER100-308		MIDPOINT - SIGNAL CONST PACKA	03/21/19	450.00	10.00	14.75	15.50
NHPP2254-089		I-225 RESURFACING FROM I-25 T	03/21/19	248.00	6.00	18.81	19.00
		WEIGHTED AVERAGE FOR THE FIRST QUARTER		12,601.00	6.49	10.73	11.05
NHPP0703-445		I-70 WESTBOUND PEAK PERIOD SH	04/25/19	6,568.00	10.00	9.13	8.00

COLORADO DEPARTMENT OF TRANSPORTATION
 ITEM UNIT COSTS BY PROJECTS -- 2019 COST DATA

13:44 Wednesday, August 7, 2019 227

PROJECT NUMBER	ITEM NUMBER/ PROJECT LOCATION	ITEM DESCRIPTION/ PROJECT LOCATION	DATE LET	UNIT/ QUANTITY	ENGR. EST.	AVERAGE BID	AWARDED BID
===== 610-00030		Median Cover Matl (Conc)		Sq Foot			
C2571-013		SH257 & 392:WINDSOR CURB RAMP	05/02/19	149.00	25.00	34.00	15.00
FSA2873-190		US 287 AND FOOTHILLS PARKWAY	05/02/19	359.00	25.00	37.00	55.00
STMC430-020		ADA RAMPS DIVIDE ESB	05/23/19	92.00	12.75	47.08	47.08
	WEIGHTED AVERAGE FOR THE SECOND QUARTER			7,168.00	11.10	10.78	11.00
	WEIGHTED AVERAGE FOR THE YEAR			19,769.00	8.16	10.75	11.03
===== 611-00016		16 Ft Cattle Gd		Each			
STA0131-070 HMA ALT		SH 13 CR 5 NORTH AND SOUTH	03/28/19	2.00	16000.00	18508.66	3030.00
STA0131-070 PCCP ALT		SH 13 CR 5 NORTH AND SOUTH					
	WEIGHTED AVERAGE FOR THE FIRST QUARTER			2.00	16000.00	18508.66	3030.00
	WEIGHTED AVERAGE FOR THE YEAR			2.00	16000.00	18508.66	3030.00
===== 611-00020		20 Ft Cattle Gd		Each			
STR0132-021		SH 13-MOFFAT COUNTY-CR 3 SOUT	01/10/19	1.00	20000.00	21180.00	19500.00
	WEIGHTED AVERAGE FOR THE FIRST QUARTER			1.00	20000.00	21180.00	19500.00
	WEIGHTED AVERAGE FOR THE YEAR			1.00	20000.00	21180.00	19500.00
===== 612-00001		Delin (Ty I)		Each			
STR0132-021		SH 13-MOFFAT COUNTY-CR 3 SOUT	01/10/19	117.00	40.00	25.94	23.20
FBR0341-087		US 34 OVER NORTH FORK CO RIVE	01/10/19	9.00	25.00	24.95	24.14
STR141A-047		SH 141 MP 120-143 MESA COUNTY	01/17/19	827.00	24.00	22.15	21.00
NHPP0701-241		I-70 TRUCK PARKING GARFIELD C	01/17/19	4.00	12.00	49.58	38.50
STR0241-062		US 24 143.4 - 148	01/24/19	50.00	25.00	25.33	30.00
ER072A-040		PR SH72A FLOOD PERMANENT REPA	01/31/19	15.00	25.00	67.64	275.00
NHPP072A-041		PR SH72A FLOOD PERMANENT REPA					
STA067A-038		SH 67 SEDALIA RESURFACING	01/31/19	8.00	75.00	62.27	22.00
NHPP0821-107		SH 82 GLENWOOD SPRINGS TO CA	02/07/19	300.00	30.00	22.50	21.00
NHPP145A-065		SH 145 PASSING LANES AT DEEP	02/14/19	10.00	20.00	27.15	28.00
NHPP0741-022		SH 74: I-70 TO CR 65 RESURFAC	02/14/19	362.00	65.00	31.40	30.40
NHPP070A-028		FALL RIVER ROAD BRIDGE	02/21/19	2.00	35.00	38.06	30.00
NHPP1601-073		US 160 PASSING LANE NORTH OF	03/07/19	30.00	40.00	23.75	23.50
NHPP050A-033		US50 West of Delta EB Lanes R	03/14/19	180.00	25.00	22.67	22.00
NHPP0503-087		US 50 PASSING LANES EAST OF S	03/21/19	47.00	22.00	21.00	22.00

COLORADO DEPARTMENT OF TRANSPORTATION
 ITEM UNIT COSTS BY PROJECTS -- 2019 COST DATA

13:44 Wednesday, August 7, 2019 228

PROJECT NUMBER	ITEM NUMBER/ PROJECT LOCATION	ITEM DESCRIPTION/ PROJECT LOCATION	DATE LET	UNIT/ QUANTITY	ENGR. EST.	AVERAGE BID	AWARDED BID
===== 612-00001 Delin (Ty I) Each =====							
NHPP2254-089	I-225	RESURFACING FROM I-25 T	03/21/19	150.00	25.00	53.31	85.00
STM0242-077	US24 - 8TH ST TO WEST OF MANI		03/28/19	430.00	26.05	18.00	16.00
STA0131-070 HMA ALT	SH 13 CR 5 NORTH AND SOUTH		03/28/19	146.00	24.00	23.71	26.70
STA0131-070 PCCP ALT	SH 13 CR 5 NORTH AND SOUTH						
WEIGHTED AVERAGE FOR THE FIRST QUARTER				2,687.00	31.64	26.04	27.23
=====							
FSA0252-468	I-25 AND PLUM CREEK IMPROVEME		04/18/19	5.00	35.00	69.75	29.00
NHPP0703-445	I-70 WESTBOUND PEAK PERIOD SH		04/25/19	100.00	47.00	44.20	34.00
FSA0703-454	EB I-70 AUX LANE WARD TO KIPL		05/16/19	10.00	35.00	90.20	85.00
FBR0063-057	US-6 F-09-K BRIDGE OVER CASTL		05/30/19	3.00	25.00	22.75	27.50
ER145A-081	SH 145 MP 21 EMERGENCY ROCKFA		06/07/19	6.00	40.00	29.39	34.00
CR500-205	R5 GUARDRAIL END TREATMENT EA		06/13/19	26.00	30.00	31.65	31.65
WEIGHTED AVERAGE FOR THE SECOND QUARTER				150.00	42.13	47.40	36.70
WEIGHTED AVERAGE FOR THE YEAR				2,837.00	32.19	26.91	27.74
=====							
===== 612-00002 Delin (Ty II) Each =====							
SHER100-289	INTERSECTIONS @ SH83 & LONGS		01/03/19	34.00	65.00	45.30	28.50
STR0241-062	US 24 143.4 - 148		01/24/19	50.00	35.00	26.33	30.00
STA067A-038	SH 67 SEDALIA RESURFACING		01/31/19	4.00	74.00	64.33	24.00
NHPP0821-107	SH 82 GLENWOOD SPRINGS TO CA		02/07/19	50.00	32.00	24.05	22.10
NHPP145A-065	SH 145 PASSING LANES AT DEEP		02/14/19	25.00	25.00	31.52	32.00
NHPP1601-073	US 160 PASSING LANE NORTH OF		03/07/19	17.00	30.00	26.95	27.90
NHPP050A-033	US50 West of Delta EB Lanes R		03/14/19	40.00	27.00	24.33	23.00
NHPP2254-089	I-225 RESURFACING FROM I-25 T		03/21/19	10.00	35.00	57.08	90.00
STM0242-077	US24 - 8TH ST TO WEST OF MANI		03/28/19	222.00	26.41	19.75	17.25
STA0131-070 HMA ALT	SH 13 CR 5 NORTH AND SOUTH		03/28/19	32.00	26.00	25.84	29.10
STA0131-070 PCCP ALT	SH 13 CR 5 NORTH AND SOUTH						
WEIGHTED AVERAGE FOR THE FIRST QUARTER				484.00	31.23	26.58	23.63
=====							
NHPP030A-035	US 285/SH30		04/04/19	25.00	50.00	18.50	18.50
FSA0252-468	I-25 AND PLUM CREEK IMPROVEME		04/18/19	11.00	40.00	72.25	31.00
NHPP0703-445	I-70 WESTBOUND PEAK PERIOD SH		04/25/19	100.00	60.00	45.96	35.00
NHPP030A-036	SH 30 & TOWER RD IMPROVEMENTS		06/13/19	12.00	35.00	55.00	55.00
WEIGHTED AVERAGE FOR THE SECOND QUARTER				148.00	54.80	47.48	33.54
WEIGHTED AVERAGE FOR THE YEAR				632.00	36.75	30.81	26.01

PROJECT NUMBER	ITEM NUMBER/ PROJECT LOCATION	ITEM DESCRIPTION/ PROJECT LOCATION	DATE LET	UNIT/ QUANTITY	ENGR. EST.	AVERAGE BID	AWARDED BID
===== 612-00003		Delin (Ty III)		Each =====			
SHER100-289		INTERSECTIONS @ SH83 & LONGS	01/03/19	4.00	75.00	47.30	30.50
STR0132-021		SH 13-MOFFAT COUNTY-CR 3 SOUT	01/10/19	3.00	50.00	27.10	27.30
FBR0341-087		US 34 OVER NORTH FORK CO RIVE	01/10/19	2.00	30.00	28.25	26.55
STR141A-047		SH 141 MP 120-143 MESA COUNTY	01/17/19	360.00	28.00	24.95	23.00
NHPP0701-241		I-70 TRUCK PARKING GARFIELD C	01/17/19	2.00	15.00	62.29	43.80
STR0241-062		US 24 143.4 - 148	01/24/19	25.00	45.00	29.00	33.00
ER072A-040		PR SH72A FLOOD PERMANENT REPA	01/31/19	55.00	35.00	52.71	31.00
NHPP072A-041		PR SH72A FLOOD PERMANENT REPA					
STA067A-038		SH 67 SEDALIA RESURFACING	01/31/19	4.00	85.00	65.67	26.00
NHPP0821-107		SH 82 GLENWOOD SPRINGS TO CA	02/07/19	20.00	34.00	25.58	23.15
NHPP145A-065		SH 145 PASSING LANES AT DEEP	02/14/19	30.00	30.00	35.23	33.00
NHPP070A-028		FALL RIVER ROAD BRIDGE	02/21/19	2.00	85.00	46.22	33.00
NHPP1601-073		US 160 PASSING LANE NORTH OF	03/07/19	8.00	35.00	30.25	32.50
C R100-315		R1 ADA CURB RAMPS - PH 5	03/07/19	100.00	60.00	145.00	90.00
NHPP050A-033		US50 West of Delta EB Lanes R	03/14/19	15.00	29.00	26.67	24.00
NHPP0503-087		US 50 PASSING LANES EAST OF S	03/21/19	25.00	30.00	25.00	23.00
STM0242-077		US24 - 8TH ST TO WEST OF MANI	03/28/19	89.00	24.87	20.67	18.00
STA0131-070 HMA ALT		SH 13 CR 5 NORTH AND SOUTH	03/28/19	226.00	28.00	28.00	31.50
STA0131-070 PCCP ALT		SH 13 CR 5 NORTH AND SOUTH					
		WEIGHTED AVERAGE FOR THE FIRST QUARTER		970.00	32.75	37.62	32.83
NHPP0703-445		I-70 WESTBOUND PEAK PERIOD SH	04/25/19	20.00	75.00	46.99	36.00
FSA0703-454		EB I-70 AUX LANE WARD TO KIPL	05/16/19	10.00	50.00	90.20	85.00
FBR0063-057		US-6 F-09-K BRIDGE OVER CASTL	05/30/19	3.00	35.00	27.50	31.00
ER145A-081		SH 145 MP 21 EMERGENCY ROCKFA	06/07/19	2.00	35.00	41.11	48.00
CR500-205		R5 GUARDRAIL END TREATMENT EA	06/13/19	27.00	33.00	38.00	38.00
NHPP160A-030		US160 MM 43.2, 150.4, 156.3,	06/20/19	8.00	27.00	84.45	80.00
		WEIGHTED AVERAGE FOR THE SECOND QUARTER		70.00	46.89	57.57	48.93
		WEIGHTED AVERAGE FOR THE YEAR		1,040.00	33.70	38.36	34.04
===== 612-00021		Delin (Ty I) (Barrier)		Each =====			
ER072A-040		PR SH72A FLOOD PERMANENT REPA	01/31/19	33.00	40.00	58.13	75.00
NHPP072A-041		PR SH72A FLOOD PERMANENT REPA					
STM0242-077		US24 - 8TH ST TO WEST OF MANI	03/28/19	76.00	40.00	57.00	55.00
		WEIGHTED AVERAGE FOR THE FIRST QUARTER		109.00	40.00	57.72	61.06
NHPP0703-445		I-70 WESTBOUND PEAK PERIOD SH	04/25/19	40.00	50.00	41.71	52.00

COLORADO DEPARTMENT OF TRANSPORTATION
 ITEM UNIT COSTS BY PROJECTS -- 2019 COST DATA

13:44 Wednesday, August 7, 2019 230

PROJECT NUMBER	ITEM NUMBER/ PROJECT LOCATION	ITEM DESCRIPTION/ PROJECT LOCATION	DATE LET	UNIT/ QUANTITY	ENGR. EST.	AVERAGE BID	AWARDED BID
===== 612-00021		Delin (Ty I) (Barrier)		Each =====			
SHE0701-243		I-70 EXIT 26 DDI MODIFICATION	05/16/19	3.00	70.00	69.00	60.00
	WEIGHTED AVERAGE FOR THE SECOND QUARTER			43.00	51.40	44.19	52.56
	WEIGHTED AVERAGE FOR THE YEAR			152.00	43.22	55.35	58.65
===== 612-00022		Delin (Ty II) (Barrier)		Each =====			
NHPP0703-445		I-70 WESTBOUND PEAK PERIOD SH	04/25/19	40.00	48.00	42.04	53.00
	WEIGHTED AVERAGE FOR THE SECOND QUARTER			40.00	48.00	42.04	53.00
	WEIGHTED AVERAGE FOR THE YEAR			40.00	48.00	42.04	53.00
===== 612-00031		Delin (Ty I) (Extra Ht)		Each =====			
NHPP006A-058		US 6 LOVELAND PASS - I-70 (FY	03/07/19	50.00	450.00	43.77	43.54
NHPP0702-378		I-70 OFFICERS GULCH TO FRISCO	03/14/19	10.00	45.00	53.37	46.12
	WEIGHTED AVERAGE FOR THE FIRST QUARTER			60.00	382.50	45.99	43.97
	WEIGHTED AVERAGE FOR THE YEAR			60.00	382.50	45.99	43.97
===== 612-00032		Delin (Ty II) (Extra Ht)		Each =====			
C0502-085		US 50 MM 201.8 MONARCH AVALAN	06/27/19	3.00	50.00	262.50	225.00
	WEIGHTED AVERAGE FOR THE SECOND QUARTER			3.00	50.00	262.50	225.00
	WEIGHTED AVERAGE FOR THE YEAR			3.00	50.00	262.50	225.00
===== 612-00033		Delin (Ty III) (Extra Ht)		Each =====			
NHPP0702-378		I-70 OFFICERS GULCH TO FRISCO	03/14/19	16.00	50.00	60.42	51.25
	WEIGHTED AVERAGE FOR THE FIRST QUARTER			16.00	50.00	60.42	51.25
	WEIGHTED AVERAGE FOR THE YEAR			16.00	50.00	60.42	51.25
===== 612-00037		Delin (Flex) (Flat Mount)		Each =====			
NH2871-035		US 287 PASSING LANES SOUTH OF	02/07/19	18.00	60.00	66.23	63.00
	WEIGHTED AVERAGE FOR THE FIRST QUARTER			18.00	60.00	66.23	63.00
	WEIGHTED AVERAGE FOR THE YEAR			18.00	60.00	66.23	63.00

COLORADO DEPARTMENT OF TRANSPORTATION
 ITEM UNIT COSTS BY PROJECTS -- 2019 COST DATA

13:44 Wednesday, August 7, 2019 231

PROJECT NUMBER	ITEM NUMBER/ PROJECT LOCATION	ITEM DESCRIPTION/ PROJECT LOCATION	DATE LET	UNIT/ QUANTITY	ENGR. EST.	AVERAGE BID	AWARDED BID
===== 612-00041		Delin (Flex) (Ty I)		Each	=====		
IM0251-351		I-25 South of Pueblo MP 79.6	01/03/19	290.00	60.00	70.96	64.68
ER119A-065		PR SH 119A BOULDER CANYON	01/03/19	600.00	50.00	72.82	68.00
STA119A-069		SH 119: NEDERLAND - EAST					
NHPP0701-241		I-70 TRUCK PARKING GARFIELD C	01/17/19	18.00	72.00	115.13	105.00
FBR0253-247		I25 AT VINE DRIVE BRIDGE REPL	03/07/19	5.00	64.00	81.09	125.00
STM0242-077		US24 - 8TH ST TO WEST OF MANI	03/28/19	6.00	55.00	60.33	55.00
		WEIGHTED AVERAGE FOR THE FIRST QUARTER		919.00	53.70	73.13	67.90
BR071A-020		REPLACEMENT OF STRUCTURE L-22	04/18/19	13.00	30.00	64.33	63.00
		WEIGHTED AVERAGE FOR THE SECOND QUARTER		13.00	30.00	64.33	63.00
		WEIGHTED AVERAGE FOR THE YEAR		932.00	53.36	73.07	67.83
===== 612-00042		Delin (Flex) (Ty II)		Each	=====		
IM0251-351		I-25 South of Pueblo MP 79.6	01/03/19	24.00	65.00	74.53	66.91
ER119A-065		PR SH 119A BOULDER CANYON	01/03/19	40.00	50.00	77.58	68.00
STA119A-069		SH 119: NEDERLAND - EAST					
FBR0253-247		I25 AT VINE DRIVE BRIDGE REPL	03/07/19	5.00	64.00	107.54	175.00
STM0242-077		US24 - 8TH ST TO WEST OF MANI	03/28/19	5.00	60.00	65.33	60.00
		WEIGHTED AVERAGE FOR THE FIRST QUARTER		74.00	56.49	79.99	74.34
		WEIGHTED AVERAGE FOR THE YEAR		74.00	56.49	79.99	74.34
===== 612-00043		Delin (Flex) (Ty III)		Each	=====		
IM0251-351		I-25 South of Pueblo MP 79.6	01/03/19	101.00	65.00	78.85	69.14
ER119A-065		PR SH 119A BOULDER CANYON	01/03/19	70.00	50.00	79.72	75.00
STA119A-069		SH 119: NEDERLAND - EAST					
FBR0253-247		I25 AT VINE DRIVE BRIDGE REPL	03/07/19	4.00	64.00	134.25	225.00
		WEIGHTED AVERAGE FOR THE FIRST QUARTER		175.00	58.98	81.75	75.05
BR071A-020		REPLACEMENT OF STRUCTURE L-22	04/18/19	5.00	40.00	68.00	65.00
		WEIGHTED AVERAGE FOR THE SECOND QUARTER		5.00	40.00	68.00	65.00
		WEIGHTED AVERAGE FOR THE YEAR		180.00	58.45	81.55	74.77

COLORADO DEPARTMENT OF TRANSPORTATION
 ITEM UNIT COSTS BY PROJECTS -- 2019 COST DATA

13:44 Wednesday, August 7, 2019 232

PROJECT NUMBER	ITEM NUMBER/ PROJECT LOCATION	ITEM DESCRIPTION/ PROJECT LOCATION	DATE LET	UNIT/ QUANTITY	ENGR. EST.	AVERAGE BID	AWARDED BID
=====	612-00052	Reflector		Each	=====		
STR0241-062	US 24 143.4 - 148		01/24/19	434.00	4.00	12.33	8.00
	WEIGHTED AVERAGE FOR THE FIRST QUARTER			434.00	4.00	12.33	8.00
	WEIGHTED AVERAGE FOR THE YEAR			434.00	4.00	12.33	8.00
=====	612-00070	Reflector Strip (4 In)		Each	=====		
STR0241-062	US 24 143.4 - 148		01/24/19	90.00	30.00	61.00	60.00
	WEIGHTED AVERAGE FOR THE FIRST QUARTER			90.00	30.00	61.00	60.00
	WEIGHTED AVERAGE FOR THE YEAR			90.00	30.00	61.00	60.00
=====	612-00101	Delin (Drv Conc Inst) (Ty I)		Each	=====		
FSA0142-068	SH 14 & WCR 33 INTERSECTION I		01/03/19	8.00	150.00	138.00	110.00
ER119A-065	PR SH 119A BOULDER CANYON		01/03/19	156.00	130.00	129.06	115.00
STA119A-069	SH 119: NEDERLAND - EAST						
SHE 0252-481	I-25 RAMP METER INSTALLATION		03/21/19	17.00	110.00	146.00	150.00
	WEIGHTED AVERAGE FOR THE FIRST QUARTER			181.00	129.01	129.93	118.07
	WEIGHTED AVERAGE FOR THE YEAR			181.00	129.01	129.93	118.07
=====	612-00102	Delin (Drv Conc Inst) (Ty II)		Each	=====		
ER119A-065	PR SH 119A BOULDER CANYON		01/03/19	1.00	180.00	133.64	120.00
STA119A-069	SH 119: NEDERLAND - EAST						
SHE 0252-481	I-25 RAMP METER INSTALLATION		03/21/19	12.00	125.00	149.33	150.00
	WEIGHTED AVERAGE FOR THE FIRST QUARTER			13.00	129.23	146.48	147.69
	WEIGHTED AVERAGE FOR THE YEAR			13.00	129.23	146.48	147.69
=====	612-00103	Delin (Drv Conc Inst) (Ty III)		Each	=====		
ER119A-065	PR SH 119A BOULDER CANYON		01/03/19	28.00	150.00	139.36	125.00

COLORADO DEPARTMENT OF TRANSPORTATION
 ITEM UNIT COSTS BY PROJECTS -- 2019 COST DATA

13:44 Wednesday, August 7, 2019 233

PROJECT NUMBER	ITEM NUMBER/ PROJECT LOCATION	ITEM DESCRIPTION/ PROJECT LOCATION	DATE LET	UNIT/ QUANTITY	ENGR. EST.	AVERAGE BID	AWARDED BID
===== 612-00103 STA119A-069		Delin (Drv Conc Inst) (Ty III) SH 119: NEDERLAND - EAST		Each =====			
	WEIGHTED AVERAGE FOR THE FIRST QUARTER			28.00	150.00	139.36	125.00
	WEIGHTED AVERAGE FOR THE YEAR			28.00	150.00	139.36	125.00
===== 612-00111		Delin (Drv) (Ty I)		Each =====			
NH2871-035		US 287 PASSING LANES SOUTH OF 02/07/19		64.00	90.00	65.59	60.90
	WEIGHTED AVERAGE FOR THE FIRST QUARTER			64.00	90.00	65.59	60.90
	WEIGHTED AVERAGE FOR THE YEAR			64.00	90.00	65.59	60.90
===== 612-00112		Delin (Drv) (Ty II)		Each =====			
NH2871-035		US 287 PASSING LANES SOUTH OF 02/07/19		30.00	90.00	68.73	63.00
	WEIGHTED AVERAGE FOR THE FIRST QUARTER			30.00	90.00	68.73	63.00
	WEIGHTED AVERAGE FOR THE YEAR			30.00	90.00	68.73	63.00
===== 612-00113		Delin (Drv) (Ty III)		Each =====			
NH2871-035		US 287 PASSING LANES SOUTH OF 02/07/19		10.00	90.00	70.88	65.10
	WEIGHTED AVERAGE FOR THE FIRST QUARTER			10.00	90.00	70.88	65.10
	WEIGHTED AVERAGE FOR THE YEAR			10.00	90.00	70.88	65.10
===== 612-00260		Loc Mark (Fib Opt) (Dome)		Each =====			
ITSSW01-638 SHE 0252-481		ETHERNET PHASE III (PRIMARILY 02/07/19 I-25 RAMP METER INSTALLATION 03/21/19		20.00 29.00	120.00 76.00	100.00 77.67	100.00 125.00
	WEIGHTED AVERAGE FOR THE FIRST QUARTER			49.00	93.96	84.70	114.80
NHPP0703-445		I-70 WESTBOUND PEAK PERIOD SH 04/25/19		86.00	100.00	614.69	614.00

COLORADO DEPARTMENT OF TRANSPORTATION
 ITEM UNIT COSTS BY PROJECTS -- 2019 COST DATA

13:44 Wednesday, August 7, 2019 234

PROJECT NUMBER	ITEM NUMBER/ PROJECT LOCATION	ITEM DESCRIPTION/ PROJECT LOCATION	DATE LET	UNIT/ QUANTITY	ENGR. EST.	AVERAGE BID	AWARDED BID
===== 612-00260		Loc Mark (Fib Opt) (Dome)		Each =====			
IM0252-456		I-25 COLORADO SPRINGS RAMP ME	05/16/19	26.00	125.00	123.67	98.00
	WEIGHTED AVERAGE FOR THE SECOND QUARTER			112.00	105.80	500.71	494.21
	WEIGHTED AVERAGE FOR THE YEAR			161.00	102.20	386.60	378.74
===== 612-00270		Loc Mark (Util) (Flat Slat)		Each =====			
ITSSW01-638		ETHERNET PHASE III (PRIMARYLY	02/07/19	16.00	85.00	87.50	100.00
SHE 0252-481		I-25 RAMP METER INSTALLATION	03/21/19	83.00	80.00	53.67	90.00
	WEIGHTED AVERAGE FOR THE FIRST QUARTER			99.00	80.81	57.52	91.62
NHPP0703-445		I-70 WESTBOUND PEAK PERIOD SH	04/25/19	87.00	125.00	471.27	470.00
	WEIGHTED AVERAGE FOR THE SECOND QUARTER			87.00	125.00	471.27	470.00
	WEIGHTED AVERAGE FOR THE YEAR			186.00	101.48	256.76	268.60
===== 612-00300		Steel Guard Post		Each =====			
NHPP030A-035		US 285/SH30	04/04/19	8.00	750.00	500.00	500.00
	WEIGHTED AVERAGE FOR THE SECOND QUARTER			8.00	750.00	500.00	500.00
	WEIGHTED AVERAGE FOR THE YEAR			8.00	750.00	500.00	500.00
===== 613-00102		1 In Elec Cond (GRC) (Special)		Lin Foot =====			
NHPP0703-445		I-70 WESTBOUND PEAK PERIOD SH	04/25/19	300.00	18.00	61.43	61.00
	WEIGHTED AVERAGE FOR THE SECOND QUARTER			300.00	18.00	61.43	61.00
	WEIGHTED AVERAGE FOR THE YEAR			300.00	18.00	61.43	61.00
===== 613-00125		1-1/4 In Elec Cond		Lin Foot =====			
ER145A-081		SH 145 MP 21 EMERGENCY ROCKFA	06/07/19	650.00	24.00	14.79	14.00
	WEIGHTED AVERAGE FOR THE SECOND QUARTER			650.00	24.00	14.79	14.00
	WEIGHTED AVERAGE FOR THE YEAR			650.00	24.00	14.79	14.00

COLORADO DEPARTMENT OF TRANSPORTATION
 ITEM UNIT COSTS BY PROJECTS -- 2019 COST DATA

13:44 Wednesday, August 7, 2019 235

PROJECT NUMBER	ITEM NUMBER/ PROJECT LOCATION	ITEM DESCRIPTION/ PROJECT LOCATION	DATE LET	UNIT/ QUANTITY	ENGR. EST.	AVERAGE BID	AWARDED BID
=====	613-00200	2 In Elec Cond		Lin Foot	=====		
NHPPR500-173		US 160_550 DURANGO SIGNALS OP	01/03/19	15.00	80.00	28.50	29.00
FBR0341-087		US 34 OVER NORTH FORK CO RIVE	01/10/19	253.00	30.00	11.38	8.46
STR0241-062		US 24 143.4 - 148	01/24/19	175.00	15.00	116.67	35.00
NHPP145A-065		SH 145 PASSING LANES AT DEEP	02/14/19	5,400.00	15.00	16.85	12.07
NHPP070A-028		FALL RIVER ROAD BRIDGE	02/21/19	368.00	15.00	9.07	16.00
NHPP1601-073		US 160 PASSING LANE NORTH OF	03/07/19	10,560.00	8.00	10.80	10.60
FBR0253-247		I25 AT VINE DRIVE BRIDGE REPL	03/07/19	530.00	12.00	13.77	20.00
		WEIGHTED AVERAGE FOR THE FIRST QUARTER		17,301.00	10.91	14.85	11.69
FSA0252-468		I-25 AND PLUM CREEK IMPROVEME	04/18/19	530.00	25.00	13.13	9.00
FSA2873-190		US 287 AND FOOTHILLS PARKWAY	05/02/19	190.00	25.00	22.50	23.00
SHE0701-243		I-70 EXIT 26 DDI MODIFICATION	05/16/19	528.00	20.00	14.03	13.00
		WEIGHTED AVERAGE FOR THE SECOND QUARTER		1,248.00	22.88	14.31	12.82
		WEIGHTED AVERAGE FOR THE YEAR		18,549.00	11.72	14.81	11.77
=====	613-00206	2 In Elec Cond (Bored)		Lin Foot	=====		
SHER100-289		INTERSECTIONS @ SH83 & LONGS	01/03/19	500.00	15.00	15.80	15.00
STAM086-075		SH96A ABRIENDO - ORMAN SAFETY	01/31/19	739.00	10.00	19.40	16.10
NHPP0821-107		SH 82 GLENWOOD SPRINGS TO CA	02/07/19	2,833.00	20.00	59.38	58.00
ITSSW01-638		ETHERNET PHASE III (PRIMARILY	02/07/19	1,280.00	20.00	30.25	35.00
NHPP0741-022		SH 74: I-70 TO CR 65 RESURFAC	02/14/19	1,170.00	15.00	42.03	41.25
SHER100-284		FY19 NORTH SIGNAL PKG	02/21/19	960.00	15.00	18.00	13.00
SHE2254-090		Colfax & I-225, Colfax & Cham	03/07/19	795.00	12.00	25.00	33.00
SHE 0252-481		I-25 RAMP METER INSTALLATION	03/21/19	37,350.00	13.00	13.20	15.50
SHER100-308		MIDPOINT - SIGNAL CONST PACKA	03/21/19	2,335.00	16.00	14.70	14.00
NHPP2254-089		I-225 RESURFACING FROM I-25 T	03/21/19	380.00	14.00	33.76	30.00
STM0242-077		US24 - 8TH ST TO WEST OF MANI	03/28/19	540.00	17.00	27.83	18.50
		WEIGHTED AVERAGE FOR THE FIRST QUARTER		48,882.00	13.83	17.06	19.40
NHPP0703-445		I-70 WESTBOUND PEAK PERIOD SH	04/25/19	9,305.00	35.00	152.51	150.00
IM0252-456		I-25 COLORADO SPRINGS RAMP ME	05/16/19	25,565.00	12.00	17.11	16.33
STRR200-257		ROAD CLOSURE GATES ON VARIOUS	05/30/19	675.00	30.00	23.23	26.40
		WEIGHTED AVERAGE FOR THE SECOND QUARTER		35,545.00	18.36	52.86	51.51
		WEIGHTED AVERAGE FOR THE YEAR		84,427.00	15.74	32.39	32.92

COLORADO DEPARTMENT OF TRANSPORTATION
ITEM UNIT COSTS BY PROJECTS -- 2019 COST DATA

13:44 Wednesday, August 7, 2019 236

PROJECT NUMBER	ITEM NUMBER/ PROJECT LOCATION	ITEM DESCRIPTION/ PROJECT LOCATION	DATE LET	UNIT/ QUANTITY	ENGR. EST.	AVERAGE BID	AWARDED BID
=====	613-00300	3 In Elec Cond		Lin Foot	=====		
FSA0252-468		I-25 AND PLUM CREEK IMPROVEME	04/18/19	774.00	40.00	18.00	22.00
FSA2873-190		US 287 AND FOOTHILLS PARKWAY	05/02/19	140.00	35.00	25.50	25.00
		WEIGHTED AVERAGE FOR THE SECOND QUARTER		914.00	39.23	18.62	22.46
		WEIGHTED AVERAGE FOR THE YEAR		914.00	39.23	18.62	22.46
=====	613-00306	3 In Elec Cond (Bored)		Lin Foot	=====		
SHER100-289		INTERSECTIONS @ SH83 & LONGS	01/03/19	850.00	17.00	17.70	16.50
STAM086-075		SH96A ABRIENDO - ORMAN SAFETY	01/31/19	1,478.00	20.00	22.73	18.25
NHPP0821-107		SH 82 GLENWOOD SPRINGS TO CA	02/07/19	5,138.00	30.00	64.82	63.15
SHER100-284		FY19 NORTH SIGNAL PKG	02/21/19	1,920.00	15.00	19.17	14.50
SHE2254-090		Colfax & I-225, Colfax & Cham	03/07/19	1,590.00	15.00	27.09	36.00
SHE 0252-481		I-25 RAMP METER INSTALLATION	03/21/19	12,525.00	15.00	15.33	18.50
SHER100-308		MIDPOINT - SIGNAL CONST PACKA	03/21/19	3,800.00	24.00	16.10	15.50
NHPP2254-089		I-225 RESURFACING FROM I-25 T	03/21/19	160.00	17.00	31.75	33.00
STM0242-077		US24 - 8TH ST TO WEST OF MANI	03/28/19	1,000.00	25.00	28.67	19.00
		WEIGHTED AVERAGE FOR THE FIRST QUARTER		28,461.00	19.59	24.01	26.89
NHPP030A-035		US 285/SH30	04/04/19	660.00	20.00	66.00	66.00
NHPP0703-445		I-70 WESTBOUND PEAK PERIOD SH	04/25/19	685.00	40.00	152.51	150.00
IM0252-456		I-25 COLORADO SPRINGS RAMP ME	05/16/19	1,400.00	25.00	19.80	19.91
SHE0701-243		I-70 EXIT 26 DDI MODIFICATION	05/16/19	81.00	81.00	55.75	52.00
		WEIGHTED AVERAGE FOR THE SECOND QUARTER		2,826.00	29.07	63.30	63.13
		WEIGHTED AVERAGE FOR THE YEAR		31,287.00	20.45	27.41	30.17
=====	613-01100	1 In Elec Cond (P)		Lin Foot	=====		
SHER100-308		MIDPOINT - SIGNAL CONST PACKA	03/21/19	250.00	20.00	9.40	8.00
		WEIGHTED AVERAGE FOR THE FIRST QUARTER		250.00	20.00	9.40	8.00
NHPP0703-445		I-70 WESTBOUND PEAK PERIOD SH	04/25/19	1,070.00	18.00	40.64	40.00
		WEIGHTED AVERAGE FOR THE SECOND QUARTER		1,070.00	18.00	40.64	40.00
		WEIGHTED AVERAGE FOR THE YEAR		1,320.00	18.38	36.43	33.94

COLORADO DEPARTMENT OF TRANSPORTATION
 ITEM UNIT COSTS BY PROJECTS -- 2019 COST DATA

13:44 Wednesday, August 7, 2019 237

PROJECT NUMBER	ITEM NUMBER/ PROJECT LOCATION	ITEM DESCRIPTION/ PROJECT LOCATION	DATE LET	UNIT/ QUANTITY	ENGR. EST.	AVERAGE BID	AWARDED BID
=====	613-01200	2 In Elec Cond (P)		Lin Foot	=====		
SHER100-289		INTERSECTIONS @ SH83 & LONGS	01/03/19	50.00	7.00	11.20	10.50
STAM086-075		SH96A ABRIENDO - ORMAN SAFETY	01/31/19	339.00	14.00	16.42	9.25
STA067A-038		SH 67 SEDALIA RESURFACING	01/31/19	50.00	10.00	48.59	17.00
NHPP0821-107		SH 82 GLENWOOD SPRINGS TO CA	02/07/19	276.00	15.00	21.00	20.00
ITSSW01-638		ETHERNET PHASE III (PRIMARYLY	02/07/19	4,770.00	14.00	16.00	20.00
NHPP070A-028		FALL RIVER ROAD BRIDGE	02/21/19	400.00	15.00	22.40	16.00
SHER100-284		FY19 NORTH SIGNAL PKG	02/21/19	480.00	10.00	16.67	14.00
SHE2254-090		Colfax & I-225, Colfax & Cham	03/07/19	185.00	10.00	15.50	21.00
SHE 0252-481		I-25 RAMP METER INSTALLATION	03/21/19	1,450.00	12.00	13.33	12.00
SHER100-308		MIDPOINT - SIGNAL CONST PACKA	03/21/19	805.00	11.00	12.55	12.50
NHPP2254-089		I-225 RESURFACING FROM I-25 T	03/21/19	120.00	10.00	20.65	19.00
		WEIGHTED AVERAGE FOR THE FIRST QUARTER		8,925.00	13.07	16.23	17.05
BR071A-020		REPLACEMENT OF STRUCTURE L-22	04/18/19	218.00	7.00	12.80	3.40
NHPP0703-445		I-70 WESTBOUND PEAK PERIOD SH	04/25/19	31,638.00	20.00	44.96	35.00
IM0252-456		I-25 COLORADO SPRINGS RAMP ME	05/16/19	4,560.00	20.00	12.87	13.61
FSAO703-454		EB I-70 AUX LANE WARD TO KIPL	05/16/19	600.00	12.00	33.01	31.00
STRR200-257		ROAD CLOSURE GATES ON VARIOUS	05/30/19	355.00	16.00	19.54	17.39
		WEIGHTED AVERAGE FOR THE SECOND QUARTER		37,371.00	19.76	40.49	31.97
		WEIGHTED AVERAGE FOR THE YEAR		46,296.00	18.47	36.55	29.10
=====	613-01201	2 In Elec Cond (P) (Spec)		Lin Foot	=====		
IM0252-456		I-25 COLORADO SPRINGS RAMP ME	05/16/19	1,490.00	50.00	27.00	10.00
		WEIGHTED AVERAGE FOR THE SECOND QUARTER		1,490.00	50.00	27.00	10.00
		WEIGHTED AVERAGE FOR THE YEAR		1,490.00	50.00	27.00	10.00
=====	613-01300	3 In Elec Cond (P)		Lin Foot	=====		
SHER100-289		INTERSECTIONS @ SH83 & LONGS	01/03/19	100.00	13.00	13.60	12.50
STAM086-075		SH96A ABRIENDO - ORMAN SAFETY	01/31/19	139.00	16.00	17.42	10.25
NHPP0821-107		SH 82 GLENWOOD SPRINGS TO CA	02/07/19	263.00	19.00	22.00	21.00
SHER100-284		FY19 NORTH SIGNAL PKG	02/21/19	480.00	12.00	17.67	16.00
SHE2254-090		Colfax & I-225, Colfax & Cham	03/07/19	235.00	15.00	26.00	37.00

COLORADO DEPARTMENT OF TRANSPORTATION
ITEM UNIT COSTS BY PROJECTS -- 2019 COST DATA

13:44 Wednesday, August 7, 2019 238

PROJECT NUMBER	ITEM NUMBER/ PROJECT LOCATION	ITEM DESCRIPTION/ PROJECT LOCATION	DATE LET	UNIT/ QUANTITY	ENGR. EST.	AVERAGE BID	AWARDED BID
===== 613-01300		3 In Elec Cond (P)		Lin Foot	=====	=====	=====
SHE 0252-481		I-25 RAMP METER INSTALLATION	03/21/19	335.00	12.00	14.67	13.00
SHER100-308		MIDPOINT - SIGNAL CONST PACKA	03/21/19	960.00	13.00	16.15	18.50
NHPP2254-089		I-225 RESURFACING FROM I-25 T	03/21/19	240.00	12.00	38.76	20.00
		WEIGHTED AVERAGE FOR THE FIRST QUARTER		2,752.00	13.51	19.57	18.71
NHPP030A-035		US 285/SH30	04/04/19	270.00	15.00	56.00	56.00
NHPP0703-445		I-70 WESTBOUND PEAK PERIOD SH	04/25/19	990.00	22.00	92.17	92.00
		WEIGHTED AVERAGE FOR THE SECOND QUARTER		1,260.00	20.50	89.16	84.29
		WEIGHTED AVERAGE FOR THE YEAR		4,012.00	15.71	41.59	39.30
===== 613-03491		Elec Cond (P) (Mult)		Lin Foot	=====	=====	=====
NHPP0703-445		I-70 WESTBOUND PEAK PERIOD SH	04/25/19	27,200.00	30.00	80.82	63.00
		WEIGHTED AVERAGE FOR THE SECOND QUARTER		27,200.00	30.00	80.82	63.00
		WEIGHTED AVERAGE FOR THE YEAR		27,200.00	30.00	80.82	63.00
===== 613-03492		Elec Cond (P) (Mult) (Bored)		Lin Foot	=====	=====	=====
NHPP0703-445		I-70 WESTBOUND PEAK PERIOD SH	04/25/19	5,475.00	49.00	242.51	245.00
		WEIGHTED AVERAGE FOR THE SECOND QUARTER		5,475.00	49.00	242.51	245.00
		WEIGHTED AVERAGE FOR THE YEAR		5,475.00	49.00	242.51	245.00
===== 613-03500		Elec Cond (P) (Mult) (Spec)		Lin Foot	=====	=====	=====
NHPP0703-445		I-70 WESTBOUND PEAK PERIOD SH	04/25/19	1,250.00	49.00	231.22	243.00
		WEIGHTED AVERAGE FOR THE SECOND QUARTER		1,250.00	49.00	231.22	243.00
		WEIGHTED AVERAGE FOR THE YEAR		1,250.00	49.00	231.22	243.00
===== 613-04100		Elect System Mods		LUMP SUM	=====	=====	=====
SHE 0252-481		I-25 RAMP METER INSTALLATION	03/21/19	1.00	10000.00	10371.67	9345.00
		WEIGHTED AVERAGE FOR THE FIRST QUARTER		1.00	10000.00	10371.67	9345.00

COLORADO DEPARTMENT OF TRANSPORTATION
ITEM UNIT COSTS BY PROJECTS -- 2019 COST DATA

13:44 Wednesday, August 7, 2019 239

PROJECT NUMBER	ITEM NUMBER/ PROJECT LOCATION	ITEM DESCRIPTION/ PROJECT LOCATION	DATE LET	UNIT/ QUANTITY	ENGR. EST.	AVERAGE BID	AWARDED BID
===== 613-04100		Elect System Mods		LUMP SUM	=====		
NHPP0703-445		I-70 WESTBOUND PEAK PERIOD SH	04/25/19	1.00	25000.00	225427.54	220000.00
	WEIGHTED AVERAGE FOR THE SECOND QUARTER			1.00	25000.00	225427.54	220000.00
	WEIGHTED AVERAGE FOR THE YEAR			2.00	17500.00	117899.61	114672.50
===== 613-07000		Pull Box (Spec)		Each	=====		
STA067A-038		SH 67 SEDALIA RESURFACING	01/31/19	2.00	600.00	680.79	1200.00
NHPP0821-107		SH 82 GLENWOOD SPRINGS TO CA	02/07/19	15.00	900.00	1270.00	1250.00
NHPP0741-022		SH 74: I-70 TO CR 65 RESURFAC	02/14/19	12.00	500.00	440.26	430.00
SHE 0252-481		I-25 RAMP METER INSTALLATION	03/21/19	36.00	400.00	1169.67	845.00
NHPP2254-089		I-225 RESURFACING FROM I-25 T	03/21/19	18.00	450.00	538.59	400.00
	WEIGHTED AVERAGE FOR THE FIRST QUARTER			83.00	520.48	889.13	770.24
NHPP030A-035		US 285/SH30	04/04/19	4.00	600.00	2777.00	2777.00
NHPP0703-445		I-70 WESTBOUND PEAK PERIOD SH	04/25/19	5.00	600.00	866.45	913.00
IM0252-456		I-25 COLORADO SPRINGS RAMP ME	05/16/19	56.00	600.00	1046.67	1140.00
	WEIGHTED AVERAGE FOR THE SECOND QUARTER			65.00	600.00	1069.22	1223.28
	WEIGHTED AVERAGE FOR THE YEAR			148.00	555.41	966.91	969.21
===== 613-07001		Type One Pull Box		Each	=====		
STR0241-062		US 24 143.4 - 148	01/24/19	4.00	1000.00	1220.00	860.00
STAM086-075		SH96A ABRIENDO - ORMAN SAFETY	01/31/19	11.00	750.00	1126.67	515.00
NHPP0741-022		SH 74: I-70 TO CR 65 RESURFAC	02/14/19	4.00	900.00	635.36	620.00
C R100-315		R1 ADA CURB RAMPS - PH 5	03/07/19	4.00	900.00	2007.50	1125.00
SHER100-308		MIDPOINT - SIGNAL CONST PACKA	03/21/19	1.00	500.00	830.00	630.00
NHPP2254-089		I-225 RESURFACING FROM I-25 T	03/21/19	1.00	700.00	849.05	650.00
	WEIGHTED AVERAGE FOR THE FIRST QUARTER			25.00	826.00	1111.53	694.60
C2571-013		SH257 & 392:WINDSOR CURB RAMP	05/02/19	1.00	1300.00	832.00	805.00

COLORADO DEPARTMENT OF TRANSPORTATION
 ITEM UNIT COSTS BY PROJECTS -- 2019 COST DATA

13:44 Wednesday, August 7, 2019 240

PROJECT NUMBER	ITEM NUMBER/ PROJECT LOCATION	ITEM DESCRIPTION/ PROJECT LOCATION	DATE LET	UNIT/ QUANTITY	ENGR. EST.	AVERAGE BID	AWARDED BID
===== 613-07001		Type One Pull Box		Each =====			
IM0252-456		I-25 COLORADO SPRINGS RAMP ME	05/16/19	59.00	800.00	833.67	658.00
CR300-248		CRAIG RESIDENCY ADA RAMPS	05/16/19	4.00	950.00	829.00	700.00
		WEIGHTED AVERAGE FOR THE SECOND QUARTER		64.00	817.19	833.35	662.92
		WEIGHTED AVERAGE FOR THE YEAR		89.00	819.66	910.74	671.82
===== 613-07002		Type Two Pull Box		Each =====			
NHPP0821-107		SH 82 GLENWOOD SPRINGS TO CA	02/07/19	10.00	1000.00	1422.50	1395.00
C R100-315		R1 ADA CURB RAMPS - PH 5	03/07/19	4.00	950.00	2420.00	1390.00
SHER100-308		MIDPOINT - SIGNAL CONST PACKA	03/21/19	4.00	580.00	1075.00	880.00
NHPP2254-089		I-225 RESURFACING FROM I-25 T	03/21/19	1.00	800.00	1111.28	900.00
		WEIGHTED AVERAGE FOR THE FIRST QUARTER		19.00	890.53	1531.89	1259.47
C2571-013		SH257 & 392:WINDSOR CURB RAMP	05/02/19	1.00	1600.00	1171.33	1104.00
IM0252-456		I-25 COLORADO SPRINGS RAMP ME	05/16/19	22.00	950.00	1360.33	1081.00
SHE0701-243		I-70 EXIT 26 DDI MODIFICATION	05/16/19	1.00	1000.00	1058.75	960.00
		WEIGHTED AVERAGE FOR THE SECOND QUARTER		24.00	979.17	1336.04	1076.92
		WEIGHTED AVERAGE FOR THE YEAR		43.00	940.00	1404.24	1157.58
===== 613-07003		Type Three Pull Box		Each =====			
SHER100-289		INTERSECTIONS @ SH83 & LONGS	01/03/19	5.00	1000.00	954.20	900.00
STAM086-075		SH96A ABRIENDO - ORMAN SAFETY	01/31/19	3.00	800.00	1421.67	565.00
C R100-315		R1 ADA CURB RAMPS - PH 5	03/07/19	5.00	1400.00	2800.00	1950.00
SHE2254-090		Colfax & I-225, Colfax & Cham	03/07/19	2.00	1200.00	492.50	500.00
		WEIGHTED AVERAGE FOR THE FIRST QUARTER		15.00	1120.00	1387.92	1129.67
C2571-013		SH257 & 392:WINDSOR CURB RAMP	05/02/19	1.00	2250.00	1524.00	1415.00
		WEIGHTED AVERAGE FOR THE SECOND QUARTER		1.00	2250.00	1524.00	1415.00
		WEIGHTED AVERAGE FOR THE YEAR		16.00	1190.63	1395.92	1147.50

PROJECT NUMBER	ITEM NUMBER/ PROJECT LOCATION	ITEM DESCRIPTION/ PROJECT LOCATION	DATE LET	UNIT/ QUANTITY	ENGR. EST.	AVERAGE BID	AWARDED BID
===== 613-07004		Type Four Pull Box		Each =====			
SHER100-289		INTERSECTIONS @ SH83 & LONGS	01/03/19	3.00	1250.00	1106.00	1050.00
FBR0341-087		US 34 OVER NORTH FORK CO RIVE	01/10/19	2.00	1500.00	1204.78	1298.68
NHPP0821-107		SH 82 GLENWOOD SPRINGS TO CA	02/07/19	10.00	1600.00	1802.50	1765.00
NHPP145A-065		SH 145 PASSING LANES AT DEEP	02/14/19	6.00	4000.00	2400.99	1450.00
SHER100-284		FY19 NORTH SIGNAL PKG	02/21/19	12.00	1300.00	1237.67	1100.00
NHPP1601-073		US 160 PASSING LANE NORTH OF	03/07/19	8.00	1525.00	2725.00	3350.00
C R100-315		R1 ADA CURB RAMPS - PH 5	03/07/19	1.00	1800.00	3190.00	2595.00
SHE2254-090		Colfax & I-225, Colfax & Cham	03/07/19	15.00	1250.00	727.50	725.00
SHER100-308		MIDPOINT - SIGNAL CONST PACKA	03/21/19	23.00	1225.00	1755.00	1555.00
		WEIGHTED AVERAGE FOR THE FIRST QUARTER		80.00	1540.94	1624.24	1516.65
C2571-013		SH257 & 392:WINDSOR CURB RAMP	05/02/19	1.00	2750.00	1715.33	1584.00
IM0252-456		I-25 COLORADO SPRINGS RAMP ME	05/16/19	14.00	1600.00	2055.00	1827.00
		WEIGHTED AVERAGE FOR THE SECOND QUARTER		15.00	1676.67	2032.36	1810.80
		WEIGHTED AVERAGE FOR THE YEAR		95.00	1562.37	1697.12	1563.10
===== 613-07005		Type Five Pull Box		Each =====			
SHER100-289		INTERSECTIONS @ SH83 & LONGS	01/03/19	2.00	1750.00	1446.40	1350.00
NHPP0821-107		SH 82 GLENWOOD SPRINGS TO CA	02/07/19	4.00	1800.00	2127.50	2080.00
SHER100-284		FY19 NORTH SIGNAL PKG	02/21/19	3.00	1750.00	1526.67	1321.00
SHE2254-090		Colfax & I-225, Colfax & Cham	03/07/19	4.00	1700.00	983.50	950.00
SHER100-308		MIDPOINT - SIGNAL CONST PACKA	03/21/19	6.00	1500.00	2255.00	2150.00
STM0242-077		US24 - 8TH ST TO WEST OF MANI	03/28/19	5.00	1250.00	1537.33	1112.00
		WEIGHTED AVERAGE FOR THE FIRST QUARTER		24.00	1583.33	1664.71	1551.79
C2571-013		SH257 & 392:WINDSOR CURB RAMP	05/02/19	1.00	3250.00	2178.67	1993.00
FSA2873-190		US 287 AND FOOTHILLS PARKWAY	05/02/19	4.00	1700.00	2247.50	1825.00
IM0252-456		I-25 COLORADO SPRINGS RAMP ME	05/16/19	12.00	1800.00	2425.00	2250.00
		WEIGHTED AVERAGE FOR THE SECOND QUARTER		17.00	1861.76	2379.06	2134.88
		WEIGHTED AVERAGE FOR THE YEAR		41.00	1698.78	1972.73	1793.56
===== 613-07010		Pull Box (Surf Mtd)		Each =====			
NHPP0703-445		I-70 WESTBOUND PEAK PERIOD SH	04/25/19	3.00	1500.00	1936.13	1900.00
		WEIGHTED AVERAGE FOR THE SECOND QUARTER		3.00	1500.00	1936.13	1900.00
		WEIGHTED AVERAGE FOR THE YEAR		3.00	1500.00	1936.13	1900.00

COLORADO DEPARTMENT OF TRANSPORTATION
 ITEM UNIT COSTS BY PROJECTS -- 2019 COST DATA

13:44 Wednesday, August 7, 2019 242

PROJECT NUMBER	ITEM NUMBER/ PROJECT LOCATION	ITEM DESCRIPTION/ PROJECT LOCATION	DATE LET	UNIT/ QUANTITY	ENGR. EST.	AVERAGE BID	AWARDED BID
===== 613-07011		Pull Box (11"x18"x12")		Each =====			
SHE 0252-481		I-25 RAMP METER INSTALLATION	03/21/19	83.00	500.00	834.33	990.00
		WEIGHTED AVERAGE FOR THE FIRST QUARTER		83.00	500.00	834.33	990.00
NHPP030A-035		US 285/SH30	04/04/19	8.00	750.00	1200.00	1200.00
FSA0252-468		I-25 AND PLUM CREEK IMPROVEME	04/18/19	8.00	900.00	778.25	473.00
NHPP0703-445		I-70 WESTBOUND PEAK PERIOD SH	04/25/19	82.00	625.00	1831.95	1800.00
		WEIGHTED AVERAGE FOR THE SECOND QUARTER		98.00	657.65	1696.38	1642.69
		WEIGHTED AVERAGE FOR THE YEAR		181.00	585.36	1295.17	1343.39
===== 613-07016		Pull Box (16"x16"x6")		Each =====			
BR071A-020		REPLACEMENT OF STRUCTURE L-22	04/18/19	4.00	700.00	976.67	670.00
		WEIGHTED AVERAGE FOR THE SECOND QUARTER		4.00	700.00	976.67	670.00
		WEIGHTED AVERAGE FOR THE YEAR		4.00	700.00	976.67	670.00
===== 613-07023		Pull Box (24"x36"x24")		Each =====			
ITSSW01-638		ETHERNET PHASE III (PRIMARYLY	02/07/19	35.00	2600.00	1467.00	1200.00
SHE 0252-481		I-25 RAMP METER INSTALLATION	03/21/19	14.00	1500.00	1846.00	2010.00
		WEIGHTED AVERAGE FOR THE FIRST QUARTER		49.00	2285.71	1609.13	1431.43
NHPP0703-445		I-70 WESTBOUND PEAK PERIOD SH	04/25/19	70.00	1400.00	3362.65	3300.00
		WEIGHTED AVERAGE FOR THE SECOND QUARTER		70.00	1400.00	3362.65	3300.00
		WEIGHTED AVERAGE FOR THE YEAR		119.00	1764.71	2752.73	2530.59
===== 613-07025		Pull Box (24"x24"x14")		Each =====			
NHPP070A-028		FALL RIVER ROAD BRIDGE	02/21/19	2.00	1500.00	2112.00	1600.00
		WEIGHTED AVERAGE FOR THE FIRST QUARTER		2.00	1500.00	2112.00	1600.00
		WEIGHTED AVERAGE FOR THE YEAR		2.00	1500.00	2112.00	1600.00

COLORADO DEPARTMENT OF TRANSPORTATION
 ITEM UNIT COSTS BY PROJECTS -- 2019 COST DATA

13:44 Wednesday, August 7, 2019 243

PROJECT NUMBER	ITEM NUMBER/ PROJECT LOCATION	ITEM DESCRIPTION/ PROJECT LOCATION	DATE LET	UNIT/ QUANTITY	ENGR. EST.	AVERAGE BID	AWARDED BID
=====	613-07034	Pull Box (24"x36"x18")		Each	=====	=====	=====
STRR200-257		ROAD CLOSURE GATES ON VARIOUS	05/30/19	16.00	1250.00	1064.00	865.00
	WEIGHTED	AVERAGE FOR THE SECOND QUARTER		16.00	1250.00	1064.00	865.00
		WEIGHTED AVERAGE FOR THE YEAR		16.00	1250.00	1064.00	865.00
=====	613-07040	Pull Box (30"x48"x24")		Each	=====	=====	=====
ITSSW01-638		ETHERNET PHASE III (PRIMARYLY	02/07/19	3.00	2000.00	2544.00	3000.00
SHE 0252-481		I-25 RAMP METER INSTALLATION	03/21/19	15.00	2000.00	2224.33	2570.00
	WEIGHTED	AVERAGE FOR THE FIRST QUARTER		18.00	2000.00	2261.94	2641.67
NHPP0703-445		I-70 WESTBOUND PEAK PERIOD SH	04/25/19	7.00	2000.00	4153.31	4000.00
	WEIGHTED	AVERAGE FOR THE SECOND QUARTER		7.00	2000.00	4153.31	4000.00
		WEIGHTED AVERAGE FOR THE YEAR		25.00	2000.00	2813.59	3022.00
=====	613-07195	Proof Conduit		Lin Foot	=====	=====	=====
IM0252-456		I-25 COLORADO SPRINGS RAMP ME	05/16/19	1,370.00	3.00	2.49	2.47
	WEIGHTED	AVERAGE FOR THE SECOND QUARTER		1,370.00	3.00	2.49	2.47
		WEIGHTED AVERAGE FOR THE YEAR		1,370.00	3.00	2.49	2.47
=====	613-10000	Wiring		LUMP SUM	=====	=====	=====
NHPPR500-173		US 160_550 DURANGO SIGNALS OP	01/03/19	1.00	50000.00	37600.00	46200.00
SHER100-289		INTERSECTIONS @ SH83 & LONGS	01/03/19	1.00	6500.00	7539.60	4400.00
STAM086-075		SH96A ABRIENDO - ORMAN SAFETY	01/31/19	1.00	15000.00	39333.33	24000.00
NHPP0821-107		SH 82 GLENWOOD SPRINGS TO CA	02/07/19	1.00	10000.00	38250.00	26500.00
ITSSW01-638		ETHERNET PHASE III (PRIMARYLY	02/07/19	1.00	30000.00	22500.00	30000.00
NHPP070A-028		FALL RIVER ROAD BRIDGE	02/21/19	1.00	25000.00	8164.00	10700.00
SHER100-284		FY19 NORTH SIGNAL PKG	02/21/19	1.00	6000.00	28841.00	21067.00
SHE2254-090		Colfax & I-225, Colfax & Cham	03/07/19	1.00	10000.00	27303.00	35000.00

COLORADO DEPARTMENT OF TRANSPORTATION
ITEM UNIT COSTS BY PROJECTS -- 2019 COST DATA

13:44 Wednesday, August 7, 2019 244

PROJECT NUMBER	ITEM NUMBER/ PROJECT LOCATION	ITEM DESCRIPTION/ PROJECT LOCATION	DATE LET	UNIT/ QUANTITY	ENGR. EST.	AVERAGE BID	AWARDED BID
===== 613-10000 Wiring LUMP SUM =====							
SHE 0252-481		I-25 RAMP METER INSTALLATION	03/21/19	1.00	155000.00	227255.00	265600.00
SHER100-308		MIDPOINT - SIGNAL CONST PACKA	03/21/19	1.00	30000.00	54000.00	33000.00
NHPP2254-089		I-225 RESURFACING FROM I-25 T	03/21/19	1.00	10000.00	8293.73	6500.00
STM0242-077		US24 - 8TH ST TO WEST OF MANI	03/28/19	1.00	30000.00	18833.33	6500.00
	WEIGHTED AVERAGE FOR THE FIRST QUARTER			12.00	31458.33	40156.95	42455.58
===== 613-10015 Breakaway Wiring System Each =====							
NHPP0703-445		I-70 WESTBOUND PEAK PERIOD SH	04/25/19	36.00	1200.00	1337.35	1300.00
IM0252-456		I-25 COLORADO SPRINGS RAMP ME	05/16/19	12.00	1000.00	1267.33	1337.00
	WEIGHTED AVERAGE FOR THE SECOND QUARTER			48.00	1150.00	1319.85	1309.25
	WEIGHTED AVERAGE FOR THE YEAR			48.00	1150.00	1319.85	1309.25
===== 613-13000 Luminaire (LED) Each =====							
FSA0252-468		I-25 AND PLUM CREEK IMPROVEME	04/18/19	3.00	1000.00	849.50	708.00
NHPP0703-445		I-70 WESTBOUND PEAK PERIOD SH	04/25/19	10.00	1000.00	2426.98	2400.00
FSA2873-190		US 287 AND FOOTHILLS PARKWAY	05/02/19	4.00	1100.00	1030.00	790.00
STRR200-257		ROAD CLOSURE GATES ON VARIOUS	05/30/19	8.00	750.00	1094.50	1000.00
	WEIGHTED AVERAGE FOR THE SECOND QUARTER			25.00	936.00	1647.81	1491.36
	WEIGHTED AVERAGE FOR THE YEAR			25.00	936.00	1647.81	1491.36
===== 613-13006 Lumin (LED) (8500 Lumens) Each =====							
SHER100-289		INTERSECTIONS @ SH83 & LONGS	01/03/19	4.00	850.00	1010.60	950.00

COLORADO DEPARTMENT OF TRANSPORTATION
 ITEM UNIT COSTS BY PROJECTS -- 2019 COST DATA

13:44 Wednesday, August 7, 2019 245

PROJECT NUMBER	ITEM NUMBER/ PROJECT LOCATION	ITEM DESCRIPTION/ PROJECT LOCATION	DATE LET	UNIT/ QUANTITY	ENGR. EST.	AVERAGE BID	AWARDED BID
=====	613-13006	Lumin (LED) (8500 Lumens)		Each =====			
SHER100-284		FY19 NORTH SIGNAL PKG	02/21/19	11.00	1200.00	697.33	782.00
SHE2254-090		Colfax & I-225, Colfax & Cham	03/07/19	6.00	750.00	808.50	800.00
SHER100-308		MIDPOINT - SIGNAL CONST PACKA	03/21/19	17.00	835.00	627.50	515.00
STM0242-077		US24 - 8TH ST TO WEST OF MANI	03/28/19	4.00	835.00	1015.00	885.00
		WEIGHTED AVERAGE FOR THE FIRST QUARTER		42.00	919.88	778.75	702.31
		WEIGHTED AVERAGE FOR THE YEAR		42.00	919.88	778.75	702.31
=====	613-16000	Luminaire (Spec)		Each =====			
STAM086-075		SH96A ABRIENDO - ORMAN SAFETY	01/31/19	12.00	4000.00	945.67	992.00
SHE2254-090		Colfax & I-225, Colfax & Cham	03/07/19	7.00	1850.00	808.50	800.00
		WEIGHTED AVERAGE FOR THE FIRST QUARTER		19.00	3207.89	907.26	921.26
NHPP0703-445		I-70 WESTBOUND PEAK PERIOD SH	04/25/19	10.00	2000.00	3372.02	3300.00
		WEIGHTED AVERAGE FOR THE SECOND QUARTER		10.00	2000.00	3372.02	3300.00
		WEIGHTED AVERAGE FOR THE YEAR		29.00	2791.38	1831.55	1741.52
=====	613-20200	Inst Lumin		Each =====			
NHPP070A-028		FALL RIVER ROAD BRIDGE	02/21/19	5.00	1000.00	318.64	530.00
SHER100-308		MIDPOINT - SIGNAL CONST PACKA	03/21/19	4.00	240.00	200.00	150.00
		WEIGHTED AVERAGE FOR THE FIRST QUARTER		9.00	662.22	289.88	361.11
		WEIGHTED AVERAGE FOR THE YEAR		9.00	662.22	289.88	361.11
=====	613-32300	Light Std Steel (30 Ft)		Each =====			
STRR200-257		ROAD CLOSURE GATES ON VARIOUS	05/30/19	8.00	1550.00	4787.50	2970.00
		WEIGHTED AVERAGE FOR THE SECOND QUARTER		8.00	1550.00	4787.50	2970.00
		WEIGHTED AVERAGE FOR THE YEAR		8.00	1550.00	4787.50	2970.00
=====	613-32350	Light Std Steel (35 Ft)		Each =====			
SHE 0252-481		I-25 RAMP METER INSTALLATION	03/21/19	17.00	3000.00	2948.00	2240.00
		WEIGHTED AVERAGE FOR THE FIRST QUARTER		17.00	3000.00	2948.00	2240.00
		WEIGHTED AVERAGE FOR THE YEAR		17.00	3000.00	2948.00	2240.00

COLORADO DEPARTMENT OF TRANSPORTATION
ITEM UNIT COSTS BY PROJECTS -- 2019 COST DATA

13:44 Wednesday, August 7, 2019 246

PROJECT NUMBER	ITEM NUMBER/ PROJECT LOCATION	ITEM DESCRIPTION/ PROJECT LOCATION	DATE LET	UNIT/ QUANTITY	ENGR. EST.	AVERAGE BID	AWARDED BID
=====	613-32400	Light Std Steel (40 Ft)		Each	=====	=====	=====
NHPP070A-028		FALL RIVER ROAD BRIDGE	02/21/19	5.00	3300.00	6790.40	5300.00
	WEIGHTED AVERAGE FOR THE FIRST QUARTER			5.00	3300.00	6790.40	5300.00
	WEIGHTED AVERAGE FOR THE YEAR			5.00	3300.00	6790.40	5300.00
=====	613-34351	Light Std Metal (35 Ft) (Spec) (1)		Each	=====	=====	=====
NHPP0703-445		I-70 WESTBOUND PEAK PERIOD SH	04/25/19	1.00	4100.00	6664.02	6500.00
	WEIGHTED AVERAGE FOR THE SECOND QUARTER			1.00	4100.00	6664.02	6500.00
	WEIGHTED AVERAGE FOR THE YEAR			1.00	4100.00	6664.02	6500.00
=====	613-40000	Conc Foundation Pad		Each	=====	=====	=====
IM0252-456		I-25 COLORADO SPRINGS RAMP ME	05/16/19	12.00	1500.00	1545.00	560.00
	WEIGHTED AVERAGE FOR THE SECOND QUARTER			12.00	1500.00	1545.00	560.00
	WEIGHTED AVERAGE FOR THE YEAR			12.00	1500.00	1545.00	560.00
=====	613-40010	Light Std Foundation		Each	=====	=====	=====
NHPP070A-028		FALL RIVER ROAD BRIDGE	02/21/19	5.00	2500.00	1976.60	1600.00
FBR0253-247		I25 AT VINE DRIVE BRIDGE REPL	03/07/19	2.00	1000.00	1956.70	1750.00
SHE 0252-481		I-25 RAMP METER INSTALLATION	03/21/19	17.00	1250.00	1320.12	1480.00
	WEIGHTED AVERAGE FOR THE FIRST QUARTER			24.00	1489.58	1630.49	1527.50
NHPP0703-445		I-70 WESTBOUND PEAK PERIOD SH	04/25/19	14.00	1300.00	3918.02	2500.00
FSA0703-454		EB I-70 AUX LANE WARD TO KIPL	05/16/19	3.00	1500.00	910.69	790.00
SHE0701-243		I-70 EXIT 26 DDI MODIFICATION	05/16/19	4.00	1400.00	1801.25	1680.00
	WEIGHTED AVERAGE FOR THE SECOND QUARTER			21.00	1347.62	3008.56	2099.52
	WEIGHTED AVERAGE FOR THE YEAR			45.00	1423.33	2190.07	1794.44

COLORADO DEPARTMENT OF TRANSPORTATION
ITEM UNIT COSTS BY PROJECTS -- 2019 COST DATA

13:44 Wednesday, August 7, 2019 247

PROJECT NUMBER	ITEM NUMBER/ PROJECT LOCATION	ITEM DESCRIPTION/ PROJECT LOCATION	DATE LET	UNIT/ QUANTITY	ENGR. EST.	AVERAGE BID	AWARDED BID
=====	613-40012	Light Std Foundation Spec		Each	=====	=====	=====
NHPP0703-445		I-70 WESTBOUND PEAK PERIOD SH	04/25/19	1.00	2100.00	4169.92	2900.00
	WEIGHTED AVERAGE FOR THE SECOND QUARTER			1.00	2100.00	4169.92	2900.00
	WEIGHTED AVERAGE FOR THE YEAR			1.00	2100.00	4169.92	2900.00
=====	613-50355	Power Transformer		Each	=====	=====	=====
NHPP0703-445		I-70 WESTBOUND PEAK PERIOD SH	04/25/19	2.00	4000.00	3425.98	3300.00
	WEIGHTED AVERAGE FOR THE SECOND QUARTER			2.00	4000.00	3425.98	3300.00
	WEIGHTED AVERAGE FOR THE YEAR			2.00	4000.00	3425.98	3300.00
=====	613-80124	Load Center (120/240V,1-Ph, 60A,16 Circ)		Each	=====	=====	=====
NHPP0703-445		I-70 WESTBOUND PEAK PERIOD SH	04/25/19	17.00	2900.00	2447.60	2400.00
	WEIGHTED AVERAGE FOR THE SECOND QUARTER			17.00	2900.00	2447.60	2400.00
	WEIGHTED AVERAGE FOR THE YEAR			17.00	2900.00	2447.60	2400.00
=====	613-80130	Service Meter Cabinet		Each	=====	=====	=====
SHER100-289		INTERSECTIONS @ SH83 & LONGS	01/03/19	1.00	5000.00	5218.00	5000.00
ITSSW01-638		ETHERNET PHASE III (PRIMARYLY	02/07/19	2.00	6000.00	6250.00	7500.00
SHER100-284		FY19 NORTH SIGNAL PKG	02/21/19	3.00	5000.00	6147.67	7015.00
SHE2254-090		Colfax & I-225, Colfax & Cham	03/07/19	4.00	5000.00	4905.00	5000.00
SHE 0252-481		I-25 RAMP METER INSTALLATION	03/21/19	3.00	5000.00	5155.00	5915.00
SHER100-308		MIDPOINT - SIGNAL CONST PACKA	03/21/19	4.00	4250.00	4815.00	3915.00
	WEIGHTED AVERAGE FOR THE FIRST QUARTER			17.00	4941.18	5362.19	5555.88
NHPP0703-445		I-70 WESTBOUND PEAK PERIOD SH	04/25/19	14.00	5300.00	8220.78	8000.00
IM0252-456		I-25 COLORADO SPRINGS RAMP ME	05/16/19	12.00	5000.00	5298.33	3420.00
STRR200-257		ROAD CLOSURE GATES ON VARIOUS	05/30/19	6.00	6000.00	5442.50	3500.00
	WEIGHTED AVERAGE FOR THE SECOND QUARTER			32.00	5318.75	6681.36	5438.75
	WEIGHTED AVERAGE FOR THE YEAR			49.00	5187.76	6254.86	5479.39

COLORADO DEPARTMENT OF TRANSPORTATION
 ITEM UNIT COSTS BY PROJECTS -- 2019 COST DATA

13:44 Wednesday, August 7, 2019 248

PROJECT NUMBER	ITEM NUMBER/ PROJECT LOCATION	ITEM DESCRIPTION/ PROJECT LOCATION	DATE LET	UNIT/ QUANTITY	ENGR. EST.	AVERAGE BID	AWARDED BID
=====	613-80274	Struct Mount Disc Switch		Each	=====		
SHE 0252-481		I-25 RAMP METER INSTALLATION	03/21/19	13.00	20.00	498.33	685.00
	WEIGHTED AVERAGE FOR THE FIRST QUARTER			13.00	20.00	498.33	685.00
	WEIGHTED AVERAGE FOR THE YEAR			13.00	20.00	498.33	685.00
=====	613-81699	Safe Switch NEMA 3R, 30A, 2-pole, 240 V		Each	=====		
NHPP0703-445		I-70 WESTBOUND PEAK PERIOD SH	04/25/19	50.00	370.00	1538.19	1500.00
	WEIGHTED AVERAGE FOR THE SECOND QUARTER			50.00	370.00	1538.19	1500.00
	WEIGHTED AVERAGE FOR THE YEAR			50.00	370.00	1538.19	1500.00
=====	613-81700	Safe Switch NEMA 3R 60A 2 Pole 240V		Each	=====		
NHPP0703-445		I-70 WESTBOUND PEAK PERIOD SH	04/25/19	21.00	1000.00	1677.57	1700.00
	WEIGHTED AVERAGE FOR THE SECOND QUARTER			21.00	1000.00	1677.57	1700.00
	WEIGHTED AVERAGE FOR THE YEAR			21.00	1000.00	1677.57	1700.00
=====	613-81900	Mobile Light Tower		Each	=====		
STR0132-021		SH 13-MOFFAT COUNTY-CR 3 SOUT	01/10/19	3.00	7500.00	6566.00	5050.00
	WEIGHTED AVERAGE FOR THE FIRST QUARTER			3.00	7500.00	6566.00	5050.00
	WEIGHTED AVERAGE FOR THE YEAR			3.00	7500.00	6566.00	5050.00
=====	614-00011	Sign Panel (CL I)		Sq Foot	=====		
IM0251-351		I-25 South of Pueblo MP 79.6	01/03/19	9.25	18.00	21.68	22.30
SHER100-289		INTERSECTIONS @ SH83 & LONGS	01/03/19	256.00	27.00	30.20	20.00
ER119A-065		PR SH 119A BOULDER CANYON	01/03/19	497.00	21.80	23.58	21.00
STA119A-069		SH 119: NEDERLAND - EAST					
FBR0341-087		US 34 OVER NORTH FORK CO RIVE	01/10/19	7.00	21.00	17.36	16.90
NHPP0701-241		I-70 TRUCK PARKING GARFIELD C	01/17/19	33.00	25.00	22.61	21.00

PROJECT NUMBER	ITEM NUMBER/ PROJECT LOCATION	ITEM DESCRIPTION/ PROJECT LOCATION	DATE LET	UNIT/ QUANTITY	ENGR. EST.	AVERAGE BID	AWARDED BID
=====	614-00011	Sign Panel (CL I)		Sq Foot	=====	=====	=====
STR0241-062		US 24 143.4 - 148	01/24/19	168.00	25.00	26.67	30.00
ER072A-040		PR SH72A FLOOD PERMANENT REPA	01/31/19	48.50	30.00	28.66	21.00
NHPP072A-041		PR SH72A FLOOD PERMANENT REPA					
STAM086-075		SH96A ABRIENDO - ORMAN SAFETY	01/31/19	197.00	20.67	41.58	17.75
STA067A-038		SH 67 SEDALIA RESURFACING	01/31/19	7.00	30.00	28.91	20.00
NHPP0821-107		SH 82 GLENWOOD SPRINGS TO CA	02/07/19	25.00	25.00	19.88	14.75
NHPP145A-065		SH 145 PASSING LANES AT DEEP	02/14/19	14.75	37.00	21.08	25.00
NHPP0741-022		SH 74: I-70 TO CR 65 RESURFAC	02/14/19	2.00	35.00	21.21	20.65
NHPP070A-028		FALL RIVER ROAD BRIDGE	02/21/19	79.00	27.00	20.05	26.00
NHPP1601-073		US 160 PASSING LANE NORTH OF	03/07/19	6.25	32.00	20.00	20.00
FBR0253-247		I25 AT VINE DRIVE BRIDGE REPL	03/07/19	35.00	22.00	25.40	28.00
MPR200-253		R2 FY19 STENCIL PVMT MKG PROJ	03/07/19	30.00	20.00	53.33	25.00
NHPP006A-058		US 6 LOVELAND PASS - I-70 (FY	03/07/19	149.00	25.00	21.89	21.77
SHE2254-090		Colfax & I-225, Colfax & Cham	03/07/19	193.00	25.00	26.00	20.00
NHPP0503-087		US 50 PASSING LANES EAST OF S	03/21/19	77.00	17.00	21.00	20.00
SHE 0252-481		I-25 RAMP METER INSTALLATION	03/21/19	290.00	25.00	25.32	32.00
SHER100-308		MIDPOINT - SIGNAL CONST PACKA	03/21/19	311.50	20.00	25.50	26.00
NHPP2254-089		I-225 RESURFACING FROM I-25 T	03/21/19	38.00	27.00	24.32	35.00
STM0242-077		US24 - 8TH ST TO WEST OF MANI	03/28/19	139.00	23.02	30.00	50.00
STA0131-070 HMA ALT		SH 13 CR 5 NORTH AND SOUTH	03/28/19	132.26	24.00	17.27	24.20
STA0131-070 PCCP ALT		SH 13 CR 5 NORTH AND SOUTH					
		WEIGHTED AVERAGE FOR THE FIRST QUARTER		2,744.51	23.50	26.00	24.96
NHPP030A-035		US 285/SH30	04/04/19	137.00	25.00	18.00	18.00
FSA0252-468		I-25 AND PLUM CREEK IMPROVEME	04/18/19	86.00	27.00	27.50	27.00
NHPP0703-445		I-70 WESTBOUND PEAK PERIOD SH	04/25/19	118.00	25.00	29.29	20.00
NHPP2851-012		US 285 Antonito to Estrella C	05/02/19	294.00	20.00	22.33	20.00
MTCE0641-103		MTCE R3 FY20 SH 64 RANGELY PE	05/02/19	50.00	25.00	51.00	25.00
FSA2873-190		US 287 AND FOOTHILLS PARKWAY	05/02/19	60.00	20.00	35.50	36.00
IM0252-456		I-25 COLORADO SPRINGS RAMP ME	05/16/19	251.00	20.00	24.33	18.00
NHPP030A-036		SH 30 & TOWER RD IMPROVEMENTS	06/13/19	26.00	30.00	21.00	21.00
		WEIGHTED AVERAGE FOR THE SECOND QUARTER		1,022.00	22.34	25.85	21.04
		WEIGHTED AVERAGE FOR THE YEAR		3,766.51	23.19	25.97	23.88
=====	614-00012	Sign Panel (CL II)		Sq Foot	=====	=====	=====
NHPPR500-173		US 160_550 DURANGO SIGNALS OP	01/03/19	452.00	30.00	56.88	63.00
FSA0142-068		SH 14 & WCR 33 INTERSECTION I	01/03/19	18.00	25.00	29.63	27.50
SHER100-289		INTERSECTIONS @ SH83 & LONGS	01/03/19	34.00	32.00	34.60	28.00
ER119A-065		PR SH 119A BOULDER CANYON	01/03/19	1,555.00	16.00	28.16	26.00

PROJECT NUMBER	ITEM NUMBER/ PROJECT LOCATION	ITEM DESCRIPTION/ PROJECT LOCATION	DATE LET	UNIT/ QUANTITY	ENGR. EST.	AVERAGE BID	AWARDED BID
===== 614-00012 Sign Panel (CL II) Sq Foot =====							
STA119A-069		SH 119: NEDERLAND - EAST					
FBR0341-087		US 34 OVER NORTH FORK CO RIVE	01/10/19	73.00	23.00	21.49	21.73
STAM086-075		SH96A ABRIENDO - ORMAN SAFETY	01/31/19	27.00	23.08	19.92	20.25
STA067A-038		SH 67 SEDALIA RESURFACING	01/31/19	89.00	31.00	35.03	30.00
NHPP0821-107		SH 82 GLENWOOD SPRINGS TO CA	02/07/19	36.00	27.00	23.00	19.00
NHPP145A-065		SH 145 PASSING LANES AT DEEP	02/14/19	78.00	25.00	26.65	32.00
NHPP0741-022		SH 74: I-70 TO CR 65 RESURFAC	02/14/19	70.00	35.00	20.13	19.50
NHPP070A-028		FALL RIVER ROAD BRIDGE	02/21/19	94.00	30.00	24.95	34.00
NHPP1601-073		US 160 PASSING LANE NORTH OF	03/07/19	126.50	20.00	27.50	25.00
FBR0253-247		I25 AT VINE DRIVE BRIDGE REPL	03/07/19	20.00	25.00	33.61	38.00
NHPP006A-058		US 6 LOVELAND PASS - I-70 (FY	03/07/19	108.00	30.00	24.57	26.13
SHE2254-090		Colfax & I-225, Colfax & Cham	03/07/19	32.00	27.00	29.00	25.00
NHPP0503-087		US 50 PASSING LANES EAST OF S	03/21/19	215.00	20.00	22.50	22.00
SHE 0252-481		I-25 RAMP METER INSTALLATION	03/21/19	67.00	25.00	36.32	51.00
SHER100-308		MIDPOINT - SIGNAL CONST PACKA	03/21/19	157.00	25.00	26.00	27.00
NHPP2254-089		I-225 RESURFACING FROM I-25 T	03/21/19	138.00	25.00	27.54	40.00
STM0242-077		US24 - 8TH ST TO WEST OF MANI	03/28/19	173.00	25.99	21.17	19.50
STA0131-070 HMA ALT		SH 13 CR 5 NORTH AND SOUTH	03/28/19	118.00	26.00	22.31	30.30
STA0131-070 PCCP ALT		SH 13 CR 5 NORTH AND SOUTH					
WEIGHTED AVERAGE FOR THE FIRST QUARTER				3,680.50	22.08	28.89	31.34
NHPP030A-035		US 285/SH30	04/04/19	358.00	25.00	21.00	21.00
FSA0252-468		I-25 AND PLUM CREEK IMPROVEME	04/18/19	77.00	29.00	33.00	29.00
NHPP0703-445		I-70 WESTBOUND PEAK PERIOD SH	04/25/19	601.00	26.00	27.83	22.00
NHPP2851-012		US 285 Antonito to Estrella C	05/02/19	383.00	22.00	28.33	25.00
IM0252-456		I-25 COLORADO SPRINGS RAMP ME	05/16/19	153.00	25.00	31.67	20.00
SHE0701-243		I-70 EXIT 26 DDI MODIFICATION	05/16/19	11.00	25.00	29.00	30.00
NHPP030A-036		SH 30 & TOWER RD IMPROVEMENTS	06/13/19	20.00	30.00	22.00	22.00
WEIGHTED AVERAGE FOR THE SECOND QUARTER				1,603.00	24.91	28.17	22.69
WEIGHTED AVERAGE FOR THE YEAR				5,283.50	22.94	28.76	28.69
===== 614-00013 Sign Panel (CL III) Sq Foot =====							
SHER100-289		INTERSECTIONS @ SH83 & LONGS	01/03/19	48.00	35.00	37.90	31.50
STA067A-038		SH 67 SEDALIA RESURFACING	01/31/19	20.00	35.00	35.75	28.00
NHPP0741-022		SH 74: I-70 TO CR 65 RESURFAC	02/14/19	24.00	40.00	37.90	36.90
NHPP006A-058		US 6 LOVELAND PASS - I-70 (FY	03/07/19	60.00	30.00	28.83	32.66
NHPP2254-089		I-225 RESURFACING FROM I-25 T	03/21/19	606.00	32.00	35.53	33.00
STA0131-070 HMA ALT		SH 13 CR 5 NORTH AND SOUTH	03/28/19	311.00	28.00	25.49	36.40
STA0131-070 PCCP ALT		SH 13 CR 5 NORTH AND SOUTH					
WEIGHTED AVERAGE FOR THE FIRST QUARTER				1,069.00	31.09	32.67	33.47

COLORADO DEPARTMENT OF TRANSPORTATION
 ITEM UNIT COSTS BY PROJECTS -- 2019 COST DATA

13:44 Wednesday, August 7, 2019 251

PROJECT NUMBER	ITEM NUMBER/ PROJECT LOCATION	ITEM DESCRIPTION/ PROJECT LOCATION	DATE LET	UNIT/ QUANTITY	ENGR. EST.	AVERAGE BID	AWARDED BID
===== 614-00013		Sign Panel (CL III)		Sq Foot	=====		
FSA0252-468		I-25 AND PLUM CREEK IMPROVEME	04/18/19	836.00	30.00	39.25	25.00
NHPP0703-445		I-70 WESTBOUND PEAK PERIOD SH	04/25/19	1,683.00	30.00	37.12	34.00
SHE0701-243		I-70 EXIT 26 DDI MODIFICATION	05/16/19	504.00	30.00	38.50	30.00
		WEIGHTED AVERAGE FOR THE SECOND QUARTER		3,023.00	30.00	38.07	30.84
		WEIGHTED AVERAGE FOR THE YEAR		4,092.00	30.29	36.78	31.45
===== 614-00014		Lighted Street Name Sign (Inst Only)		Each	=====		
STM0242-077		US24 - 8TH ST TO WEST OF MANI	03/28/19	4.00	2000.00	900.00	950.00
		WEIGHTED AVERAGE FOR THE FIRST QUARTER		4.00	2000.00	900.00	950.00
		WEIGHTED AVERAGE FOR THE YEAR		4.00	2000.00	900.00	950.00
===== 614-00026		Inst Sign Panel (CL I)		Each	=====		
STR0132-021		SH 13-MOFFAT COUNTY-CR 3 SOUT	01/10/19	2.00	200.00	305.40	303.00
		WEIGHTED AVERAGE FOR THE FIRST QUARTER		2.00	200.00	305.40	303.00
FSA2873-190		US 287 AND FOOTHILLS PARKWAY	05/02/19	4.00	200.00	246.00	215.00
		WEIGHTED AVERAGE FOR THE SECOND QUARTER		4.00	200.00	246.00	215.00
		WEIGHTED AVERAGE FOR THE YEAR		6.00	200.00	279.00	244.33
===== 614-00027		Inst Sign Panel (CL II)		Sq Foot	=====		
FSA0703-454		EB I-70 AUX LANE WARD TO KIPL	05/16/19	16.00	10.00	33.19	24.00
		WEIGHTED AVERAGE FOR THE SECOND QUARTER		16.00	10.00	33.19	24.00
		WEIGHTED AVERAGE FOR THE YEAR		16.00	10.00	33.19	24.00

PROJECT NUMBER	ITEM NUMBER/ PROJECT LOCATION	ITEM DESCRIPTION/ PROJECT LOCATION	DATE LET	UNIT/ QUANTITY	ENGR. EST.	AVERAGE BID	AWARDED BID
===== 614-00028		Inst Sign Panel (CL III)		Sq Foot	=====		
FSA0703-454		EB I-70 AUX LANE WARD TO KIPL	05/16/19	298.00	30.00	42.15	37.00
	WEIGHTED	AVERAGE FOR THE SECOND QUARTER		298.00	30.00	42.15	37.00
		WEIGHTED AVERAGE FOR THE YEAR		298.00	30.00	42.15	37.00
===== 614-00035		Sign Panel (Spec)		Sq Foot	=====		
NHPP0701-241		I-70 TRUCK PARKING GARFIELD C	01/17/19	70.00	52.00	26.96	24.00
ER072A-040		PR SH72A FLOOD PERMANENT REPA	01/31/19	4.34	30.00	47.14	38.00
NHPP072A-041		PR SH72A FLOOD PERMANENT REPA					
	WEIGHTED	AVERAGE FOR THE FIRST QUARTER		74.34	50.72	29.57	24.82
		WEIGHTED AVERAGE FOR THE YEAR		74.34	50.72	29.57	24.82
===== 614-00037		Sign Panel (Spec)		Each	=====		
FSA0142-068		SH 14 & WCR 33 INTERSECTION I	01/03/19	2.00	1000.00	3453.75	3250.00
	WEIGHTED	AVERAGE FOR THE FIRST QUARTER		2.00	1000.00	3453.75	3250.00
		WEIGHTED AVERAGE FOR THE YEAR		2.00	1000.00	3453.75	3250.00
===== 614-00041		Sign Post (Spec)		Each	=====		
NHPP0741-022		SH 74: I-70 TO CR 65 RESURFAC	02/14/19	1.00	900.00	1217.74	1500.00
	WEIGHTED	AVERAGE FOR THE FIRST QUARTER		1.00	900.00	1217.74	1500.00
		WEIGHTED AVERAGE FOR THE YEAR		1.00	900.00	1217.74	1500.00
===== 614-00200		Steel Sign Post (U-2)		Lin Foot	=====		
ER072A-040		PR SH72A FLOOD PERMANENT REPA	01/31/19	7.00	21.00	18.59	31.00
NHPP072A-041		PR SH72A FLOOD PERMANENT REPA					
	WEIGHTED	AVERAGE FOR THE FIRST QUARTER		7.00	21.00	18.59	31.00

COLORADO DEPARTMENT OF TRANSPORTATION
 ITEM UNIT COSTS BY PROJECTS -- 2019 COST DATA

13:44 Wednesday, August 7, 2019 253

PROJECT NUMBER	ITEM NUMBER/ PROJECT LOCATION	ITEM DESCRIPTION/ PROJECT LOCATION	DATE LET	UNIT/ QUANTITY	ENGR. EST.	AVERAGE BID	AWARDED BID
=====	614-00200	Steel Sign Post (U-2)		Lin Foot	=====		
NHPP030A-036		SH 30 & TOWER RD IMPROVEMENTS	06/13/19	14.00	30.00	11.00	11.00
	WEIGHTED AVERAGE FOR THE SECOND QUARTER			14.00	30.00	11.00	11.00
	WEIGHTED AVERAGE FOR THE YEAR			21.00	27.00	17.50	17.67
=====	614-00216	Steel Sign Post (2x2 In T)		Lin Foot	=====		
ER119A-065 STA119A-069		PR SH 119A BOULDER CANYON SH 119: NEDERLAND - EAST	01/03/19	150.00	13.00	16.37	8.50
	WEIGHTED AVERAGE FOR THE FIRST QUARTER			150.00	13.00	16.37	8.50
	WEIGHTED AVERAGE FOR THE YEAR			150.00	13.00	16.37	8.50
=====	614-00218	Steel Sign Post (2.25x2.25 In T)		Lin Foot	=====		
ER119A-065 STA119A-069		PR SH 119A BOULDER CANYON SH 119: NEDERLAND - EAST	01/03/19	45.00	25.00	20.23	10.50
	WEIGHTED AVERAGE FOR THE FIRST QUARTER			45.00	25.00	20.23	10.50
	WEIGHTED AVERAGE FOR THE YEAR			45.00	25.00	20.23	10.50
=====	614-00818	Steel Sign Post (W 8x18)		Lin Foot	=====		
NHPP0703-445		I-70 WESTBOUND PEAK PERIOD SH	04/25/19	112.00	75.00	104.16	128.00
	WEIGHTED AVERAGE FOR THE SECOND QUARTER			112.00	75.00	104.16	128.00
	WEIGHTED AVERAGE FOR THE YEAR			112.00	75.00	104.16	128.00
=====	614-00821	Steel Sign Post (W 8x21)		Lin Foot	=====		
FSA0703-454		EB I-70 AUX LANE WARD TO KIPL	05/16/19	40.00	85.00	81.54	70.00
	WEIGHTED AVERAGE FOR THE SECOND QUARTER			40.00	85.00	81.54	70.00
	WEIGHTED AVERAGE FOR THE YEAR			40.00	85.00	81.54	70.00

COLORADO DEPARTMENT OF TRANSPORTATION
 ITEM UNIT COSTS BY PROJECTS -- 2019 COST DATA

13:44 Wednesday, August 7, 2019 254

PROJECT NUMBER	ITEM NUMBER/ PROJECT LOCATION	ITEM DESCRIPTION/ PROJECT LOCATION	DATE LET	UNIT/ QUANTITY	ENGR. EST.	AVERAGE BID	AWARDED BID
===== 614-01502		Steel Sign Supp (2-In Rd) (Po&Sock)		Lin Foot	=====		
STA0131-070 HMA ALT		SH 13 CR 5 NORTH AND SOUTH	03/28/19	183.00	25.00	27.60	40.00
STA0131-070 PCCP ALT		SH 13 CR 5 NORTH AND SOUTH					
	WEIGHTED AVERAGE FOR THE FIRST QUARTER			183.00	25.00	27.60	40.00
	WEIGHTED AVERAGE FOR THE YEAR			183.00	25.00	27.60	40.00
===== 614-01503		Steel Sign Supp (2-In Rd) (Po&Sock)		Each	=====		
ER119A-065		PR SH 119A BOULDER CANYON	01/03/19	86.00	200.00	193.45	150.00
STA119A-069		SH 119: NEDERLAND - EAST					
STR0132-021		SH 13-MOFFAT COUNTY-CR 3 SOUT	01/10/19	1.00	300.00	524.80	505.00
FBR0253-247		I25 AT VINE DRIVE BRIDGE REPL	03/07/19	6.00	205.00	296.20	275.00
SHER100-308		MIDPOINT - SIGNAL CONST PACKA	03/21/19	1.00	210.00	460.00	450.00
STM0242-077		US24 - 8TH ST TO WEST OF MANI	03/28/19	9.00	220.00	213.33	200.00
	WEIGHTED AVERAGE FOR THE FIRST QUARTER			103.00	203.11	205.52	168.01
FSA2873-190		US 287 AND FOOTHILLS PARKWAY	05/02/19	2.00	180.00	365.00	475.00
	WEIGHTED AVERAGE FOR THE SECOND QUARTER			2.00	180.00	365.00	475.00
	WEIGHTED AVERAGE FOR THE YEAR			105.00	202.67	206.32	173.86
===== 614-01512		Steel Sign Supp (2-In Rd) (Post)		Lin Foot	=====		
ER119A-065		PR SH 119A BOULDER CANYON	01/03/19	1,035.00	9.06	10.77	9.00
STA119A-069		SH 119: NEDERLAND - EAST					
FBR0341-087		US 34 OVER NORTH FORK CO RIVE	01/10/19	10.00	11.60	13.14	12.07
NHPP145A-065		SH 145 PASSING LANES AT DEEP	02/14/19	24.00	27.00	15.04	8.00
NHPP1601-073		US 160 PASSING LANE NORTH OF	03/07/19	36.00	10.00	17.33	16.65
NHPP0503-087		US 50 PASSING LANES EAST OF S	03/21/19	146.00	15.00	13.00	14.00
	WEIGHTED AVERAGE FOR THE FIRST QUARTER			1,251.00	10.14	10.97	9.81
NHPP2851-012		US 285 Antonito to Estrella C	05/02/19	384.00	22.00	12.67	17.00
	WEIGHTED AVERAGE FOR THE SECOND QUARTER			384.00	22.00	12.67	17.00
	WEIGHTED AVERAGE FOR THE YEAR			1,635.00	12.93	11.16	11.50

COLORADO DEPARTMENT OF TRANSPORTATION
ITEM UNIT COSTS BY PROJECTS -- 2019 COST DATA

13:44 Wednesday, August 7, 2019 255

PROJECT NUMBER	ITEM NUMBER/ PROJECT LOCATION	ITEM DESCRIPTION/ PROJECT LOCATION	DATE LET	UNIT/ QUANTITY	ENGR. EST.	AVERAGE BID	AWARDED BID
===== 614-01522		Steel Sign Supp (2-In Rd) (Sock)		Each			
ER119A-065	PR SH 119A BOULDER CANYON	01/03/19	198.00	50.25	135.12	120.00	
STA119A-069	SH 119: NEDERLAND - EAST						
FBR0341-087	US 34 OVER NORTH FORK CO RIVE	01/10/19	1.00	130.00	193.98	181.05	
NHPP145A-065	SH 145 PASSING LANES AT DEEP	02/14/19	5.00	75.00	96.83	100.00	
NHPP1601-073	US 160 PASSING LANE NORTH OF	03/07/19	11.00	60.00	112.50	105.00	
NHPP0503-087	US 50 PASSING LANES EAST OF S	03/21/19	13.00	110.00	143.50	120.00	
	WEIGHTED AVERAGE FOR THE FIRST QUARTER		228.00	55.02	134.59	119.11	
NHPP2851-012	US 285 Antonito to Estrella C	05/02/19	32.00	100.00	186.67	160.00	
SHE0701-243	I-70 EXIT 26 DDI MODIFICATION	05/16/19	3.00	92.00	115.00	200.00	
	WEIGHTED AVERAGE FOR THE SECOND QUARTER		35.00	99.31	178.70	163.43	
	WEIGHTED AVERAGE FOR THE YEAR		263.00	60.92	137.28	125.00	
===== 614-01572		Steel Sign Supp (2-1/2 Rd NP40) (Po&Slip)		Lin Foot			
FBR0341-087	US 34 OVER NORTH FORK CO RIVE	01/10/19	58.00	36.00	19.20	19.31	
STA0131-070 HMA ALT	SH 13 CR 5 NORTH AND SOUTH	03/28/19	887.00	48.00	41.84	30.30	
STA0131-070 PCCP ALT	SH 13 CR 5 NORTH AND SOUTH						
	WEIGHTED AVERAGE FOR THE FIRST QUARTER		945.00	47.26	39.22	29.03	
NHPP030A-036	SH 30 & TOWER RD IMPROVEMENTS	06/13/19	7.00	50.00	80.00	80.00	
	WEIGHTED AVERAGE FOR THE SECOND QUARTER		7.00	50.00	80.00	80.00	
	WEIGHTED AVERAGE FOR THE YEAR		952.00	47.28	39.31	29.73	
===== 614-01573		Steel Sign Supp (2-1/2 Rd NP40) (Po&Slip)		Each			
IM0251-351	I-25 South of Pueblo MP 79.6	01/03/19	3.00	350.00	321.84	390.30	
ER119A-065	PR SH 119A BOULDER CANYON	01/03/19	27.00	360.00	413.30	355.00	
STA119A-069	SH 119: NEDERLAND - EAST						
STR0241-062	US 24 143.4 - 148	01/24/19	12.00	360.00	476.67	500.00	

COLORADO DEPARTMENT OF TRANSPORTATION
ITEM UNIT COSTS BY PROJECTS -- 2019 COST DATA

13:44 Wednesday, August 7, 2019 256

PROJECT NUMBER	ITEM NUMBER/ PROJECT LOCATION	ITEM DESCRIPTION/ PROJECT LOCATION	DATE LET	UNIT/ QUANTITY	ENGR. EST.	AVERAGE BID	AWARDED BID
===== 614-01573		Steel Sign Supp (2-1/2 Rd NP40) (Po&Slip)		Each =====			
NH2871-035		US 287 PASSING LANES SOUTH OF	02/07/19	10.00	350.00	418.96	393.75
STM0242-077		US24 - 8TH ST TO WEST OF MANI	03/28/19	15.00	420.00	410.00	400.00
		WEIGHTED AVERAGE FOR THE FIRST QUARTER		67.00	371.49	416.91	398.41
MTCE0641-103		MTCE R3 FY20 SH 64 RANGELY PE	05/02/19	6.00	380.00	970.00	500.00
		WEIGHTED AVERAGE FOR THE SECOND QUARTER		6.00	380.00	970.00	500.00
		WEIGHTED AVERAGE FOR THE YEAR		73.00	372.19	435.30	406.76
===== 614-01575		Steel Sign Supp (2-1/2 In Rd NP40) (Po)		Lin Foot =====			
NHPPR500-173		US 160_550 DURANGO SIGNALS OP	01/03/19	52.00	20.00	76.50	13.00
FSA0142-068		SH 14 & WCR 33 INTERSECTION I	01/03/19	44.00	18.00	20.38	10.50
ER119A-065		PR SH 119A BOULDER CANYON	01/03/19	507.00	19.00	25.48	22.00
STA119A-069		SH 119: NEDERLAND - EAST					
NHPP1601-073		US 160 PASSING LANE NORTH OF	03/07/19	120.00	20.00	16.43	17.85
NHPP0503-087		US 50 PASSING LANES EAST OF S	03/21/19	268.00	16.00	21.00	19.00
		WEIGHTED AVERAGE FOR THE FIRST QUARTER		991.00	18.32	25.45	19.70
		WEIGHTED AVERAGE FOR THE YEAR		991.00	18.32	25.45	19.70
===== 614-01578		Steel Sign Supp (2-1/2 In Rd NP40) (Slip)		Each =====			
NHPPR500-173		US 160_550 DURANGO SIGNALS OP	01/03/19	5.00	400.00	368.50	367.00
FSA0142-068		SH 14 & WCR 33 INTERSECTION I	01/03/19	4.00	300.00	187.50	105.00
ER119A-065		PR SH 119A BOULDER CANYON	01/03/19	62.00	200.00	279.66	275.00
STA119A-069		SH 119: NEDERLAND - EAST					
FBR0341-087		US 34 OVER NORTH FORK CO RIVE	01/10/19	5.00	225.00	274.42	295.71
NHPP1601-073		US 160 PASSING LANE NORTH OF	03/07/19	14.00	250.00	275.00	260.00
NHPP0503-087		US 50 PASSING LANES EAST OF S	03/21/19	22.00	250.00	203.50	240.00
		WEIGHTED AVERAGE FOR THE FIRST QUARTER		112.00	229.69	272.89	265.21
SHE0701-243		I-70 EXIT 26 DDI MODIFICATION	05/16/19	2.00	212.00	347.00	500.00
		WEIGHTED AVERAGE FOR THE SECOND QUARTER		2.00	212.00	347.00	500.00
		WEIGHTED AVERAGE FOR THE YEAR		114.00	229.38	273.83	269.33

COLORADO DEPARTMENT OF TRANSPORTATION
 ITEM UNIT COSTS BY PROJECTS -- 2019 COST DATA

13:44 Wednesday, August 7, 2019 257

PROJECT NUMBER	ITEM NUMBER/ PROJECT LOCATION	ITEM DESCRIPTION/ PROJECT LOCATION	DATE LET	UNIT/ QUANTITY	ENGR. EST.	AVERAGE BID	AWARDED BID
===== 614-01582		Steel Sign Supp (2-1/2 In Rd) (Po&Slip)		Lin Foot	=====		
NHPP0703-445		I-70 WESTBOUND PEAK PERIOD SH	04/25/19	74.00	40.00	368.62	51.00
	WEIGHTED AVERAGE FOR THE SECOND QUARTER			74.00	40.00	368.62	51.00
	WEIGHTED AVERAGE FOR THE YEAR			74.00	40.00	368.62	51.00
===== 614-01583		Stl Sign Supp (2-1/2 In Rd 80) (Po&Slip)		Each	=====		
SHER100-289		INTERSECTIONS @ SH83 & LONGS	01/03/19	28.00	500.00	413.40	450.00
NHPP0701-241		I-70 TRUCK PARKING GARFIELD C	01/17/19	18.00	600.00	504.45	470.00
ER072A-040		PR SH72A FLOOD PERMANENT REPA	01/31/19	27.00	500.00	494.38	450.00
NHPP072A-041		PR SH72A FLOOD PERMANENT REPA					
STAM086-075		SH96A ABRIENDO - ORMAN SAFETY	01/31/19	2.00	542.63	471.67	415.00
STA067A-038		SH 67 SEDALIA RESURFACING	01/31/19	10.00	500.00	530.91	500.00
NH2871-035		US 287 PASSING LANES SOUTH OF	02/07/19	3.00	550.00	473.74	446.25
FBR0253-247		I25 AT VINE DRIVE BRIDGE REPL	03/07/19	2.00	420.00	616.31	710.00
SHE2254-090		Colfax & I-225, Colfax & Cham	03/07/19	3.00	500.00	570.00	690.00
SHE 0252-481		I-25 RAMP METER INSTALLATION	03/21/19	2.00	500.00	576.67	525.00
SHER100-308		MIDPOINT - SIGNAL CONST PACKA	03/21/19	8.00	425.00	780.00	770.00
NHPP2254-089		I-225 RESURFACING FROM I-25 T	03/21/19	15.00	400.00	638.40	500.00
	WEIGHTED AVERAGE FOR THE FIRST QUARTER			118.00	498.10	501.50	496.43
NHPP030A-035		US 285/SH30	04/04/19	85.00	400.00	405.00	405.00
FSA0703-454		EB I-70 AUX LANE WARD TO KIPL	05/16/19	5.00	500.00	639.91	542.00
	WEIGHTED AVERAGE FOR THE SECOND QUARTER			90.00	405.56	440.24	412.61
	WEIGHTED AVERAGE FOR THE YEAR			208.00	458.05	493.81	460.16
===== 614-01585		Steel Sign Supp (2-1/2 In Rd 80) (Post)		Lin Foot	=====		
NHPP0821-107		SH 82 GLENWOOD SPRINGS TO CA	02/07/19	78.00	24.00	27.50	21.00
NHPP145A-065		SH 145 PASSING LANES AT DEEP	02/14/19	60.00	25.00	26.15	32.00
NHPP0741-022		SH 74: I-70 TO CR 65 RESURFAC	02/14/19	24.00	25.00	30.70	29.30
NHPP070A-028		FALL RIVER ROAD BRIDGE	02/21/19	190.00	25.00	24.92	30.00
NHPP006A-058		US 6 LOVELAND PASS - I-70 (FY	03/07/19	40.00	30.00	30.33	32.66
	WEIGHTED AVERAGE FOR THE FIRST QUARTER			392.00	25.31	26.03	28.74

COLORADO DEPARTMENT OF TRANSPORTATION
ITEM UNIT COSTS BY PROJECTS -- 2019 COST DATA

13:44 Wednesday, August 7, 2019 258

PROJECT NUMBER	ITEM NUMBER/ PROJECT LOCATION	ITEM DESCRIPTION/ PROJECT LOCATION	DATE LET	UNIT/ QUANTITY	ENGR. EST.	AVERAGE BID	AWARDED BID
=====	614-01585	Steel Sign Supp (2-1/2 In Rd 80) (Post)		Lin Foot	=====		
FSA0252-468		I-25 AND PLUM CREEK IMPROVEME	04/18/19	156.00	30.00	30.25	25.00
NHPP0703-445		I-70 WESTBOUND PEAK PERIOD SH	04/25/19	954.00	20.00	31.95	28.00
		WEIGHTED AVERAGE FOR THE SECOND QUARTER		1,110.00	21.41	31.65	27.58
		WEIGHTED AVERAGE FOR THE YEAR		1,502.00	22.42	29.90	27.88
=====	614-01588	Steel Sign Supp (2-1/2 In Rd 80) (Slip)		Each	=====		
NHPP0821-107		SH 82 GLENWOOD SPRINGS TO CA	02/07/19	8.00	320.00	325.00	260.00
NHPP145A-065		SH 145 PASSING LANES AT DEEP	02/14/19	9.00	240.00	268.84	400.00
NHPP0741-022		SH 74: I-70 TO CR 65 RESURFAC	02/14/19	2.00	400.00	310.24	300.00
NHPP070A-028		FALL RIVER ROAD BRIDGE	02/21/19	16.00	400.00	308.62	420.00
NHPP006A-058		US 6 LOVELAND PASS - I-70 (FY	03/07/19	3.00	250.00	404.11	408.22
		WEIGHTED AVERAGE FOR THE FIRST QUARTER		38.00	333.42	302.54	374.33
FSA0252-468		I-25 AND PLUM CREEK IMPROVEME	04/18/19	14.00	300.00	350.50	372.00
NHPP0703-445		I-70 WESTBOUND PEAK PERIOD SH	04/25/19	73.00	320.00	422.70	296.00
		WEIGHTED AVERAGE FOR THE SECOND QUARTER		87.00	316.78	408.00	308.23
		WEIGHTED AVERAGE FOR THE YEAR		125.00	321.84	369.99	328.33
=====	614-03001	Conc Footing (Ty 1)		Each	=====		
NHPP0821-107		SH 82 GLENWOOD SPRINGS TO CA	02/07/19	6.00	1800.00	607.50	215.00
		WEIGHTED AVERAGE FOR THE FIRST QUARTER		6.00	1800.00	607.50	215.00
		WEIGHTED AVERAGE FOR THE YEAR		6.00	1800.00	607.50	215.00
=====	614-03003	Conc Footing (Ty 3)		Each	=====		
NHPP0703-445		I-70 WESTBOUND PEAK PERIOD SH	04/25/19	8.00	1500.00	2497.25	984.00
		WEIGHTED AVERAGE FOR THE SECOND QUARTER		8.00	1500.00	2497.25	984.00
		WEIGHTED AVERAGE FOR THE YEAR		8.00	1500.00	2497.25	984.00

COLORADO DEPARTMENT OF TRANSPORTATION
 ITEM UNIT COSTS BY PROJECTS -- 2019 COST DATA

13:44 Wednesday, August 7, 2019 259

PROJECT NUMBER	ITEM NUMBER/ PROJECT LOCATION	ITEM DESCRIPTION/ PROJECT LOCATION	DATE LET	UNIT/ QUANTITY	ENGR. EST.	AVERAGE BID	AWARDED BID
=====	614-03004	Conc Footing (Ty 4)		Each	=====	=====	=====
FSA0703-454		EB I-70 AUX LANE WARD TO KIPL	05/16/19	2.00	1500.00	1575.67	1320.00
	WEIGHTED	AVERAGE FOR THE SECOND QUARTER		2.00	1500.00	1575.67	1320.00
		WEIGHTED AVERAGE FOR THE YEAR		2.00	1500.00	1575.67	1320.00
=====	614-07105	Mod Sign Legend		Each	=====	=====	=====
NHPP2254-089		I-225 RESURFACING FROM I-25 T	03/21/19	2.00	1200.00	3052.48	4000.00
	WEIGHTED	AVERAGE FOR THE FIRST QUARTER		2.00	1200.00	3052.48	4000.00
		WEIGHTED AVERAGE FOR THE YEAR		2.00	1200.00	3052.48	4000.00
=====	614-10050	Mod Overhead Sign Str		Each	=====	=====	=====
NHPP2254-089		I-225 RESURFACING FROM I-25 T	03/21/19	1.00	5000.00	13379.54	4500.00
	WEIGHTED	AVERAGE FOR THE FIRST QUARTER		1.00	5000.00	13379.54	4500.00
FSA0703-454		EB I-70 AUX LANE WARD TO KIPL	05/16/19	1.00	1000.00	6186.32	8000.00
	WEIGHTED	AVERAGE FOR THE SECOND QUARTER		1.00	1000.00	6186.32	8000.00
		WEIGHTED AVERAGE FOR THE YEAR		2.00	3000.00	9782.93	6250.00
=====	614-10115	Dyn Mesg Sign (Color LED) (O/H)		Each	=====	=====	=====
NHPP0703-445		I-70 WESTBOUND PEAK PERIOD SH	04/25/19	7.00	100000.00	105784.87	151000.00
	WEIGHTED	AVERAGE FOR THE SECOND QUARTER		7.00	100000.00	105784.87	151000.00
		WEIGHTED AVERAGE FOR THE YEAR		7.00	100000.00	105784.87	151000.00
=====	614-10116	Dyn Msg Sign Ctrl		Each	=====	=====	=====
ITSSW01-638		ETHERNET PHASE III (PRIMARYLY	02/07/19	2.00	12500.00	22810.00	25000.00
	WEIGHTED	AVERAGE FOR THE FIRST QUARTER		2.00	12500.00	22810.00	25000.00
		WEIGHTED AVERAGE FOR THE YEAR		2.00	12500.00	22810.00	25000.00

PROJECT NUMBER	ITEM NUMBER/ PROJECT LOCATION	ITEM DESCRIPTION/ PROJECT LOCATION	DATE LET	UNIT/ QUANTITY	ENGR. EST.	AVERAGE BID	AWARDED BID
=====	614-10119	Scroll Sign		Each	=====	=====	=====
NHPP0703-445		I-70 WESTBOUND PEAK PERIOD SH	04/25/19	6.00	20000.00	20166.22	2373.00
	WEIGHTED AVERAGE FOR THE SECOND QUARTER			6.00	20000.00	20166.22	2373.00
	WEIGHTED AVERAGE FOR THE YEAR			6.00	20000.00	20166.22	2373.00
=====	614-10120	Var Mesg Sign		Each	=====	=====	=====
NHPP0703-445		I-70 WESTBOUND PEAK PERIOD SH	04/25/19	4.00	75000.00	45903.88	45000.00
	WEIGHTED AVERAGE FOR THE SECOND QUARTER			4.00	75000.00	45903.88	45000.00
	WEIGHTED AVERAGE FOR THE YEAR			4.00	75000.00	45903.88	45000.00
=====	614-10127	Var Speed Limit Sign		Each	=====	=====	=====
NHPP0703-445		I-70 WESTBOUND PEAK PERIOD SH	04/25/19	12.00	30000.00	20578.79	21000.00
	WEIGHTED AVERAGE FOR THE SECOND QUARTER			12.00	30000.00	20578.79	21000.00
	WEIGHTED AVERAGE FOR THE YEAR			12.00	30000.00	20578.79	21000.00
=====	614-10139	Radar Speed Disp Sgn (LED)		Each	=====	=====	=====
STAM086-075		SH96A ABRIENDO - ORMAN SAFETY	01/31/19	2.00	10000.00	15728.33	22185.00
	WEIGHTED AVERAGE FOR THE FIRST QUARTER			2.00	10000.00	15728.33	22185.00
	WEIGHTED AVERAGE FOR THE YEAR			2.00	10000.00	15728.33	22185.00
=====	614-10147	VMS LED (Overhead)		Each	=====	=====	=====
NHPP0703-445		I-70 WESTBOUND PEAK PERIOD SH	04/25/19	3.00	15000.00	24410.43	24000.00
	WEIGHTED AVERAGE FOR THE SECOND QUARTER			3.00	15000.00	24410.43	24000.00
	WEIGHTED AVERAGE FOR THE YEAR			3.00	15000.00	24410.43	24000.00
=====	614-10160	Sig Head B-Plates		Each	=====	=====	=====
NHPPR500-173		US 160_550 DURANGO SIGNALS OP	01/03/19	164.00	343.29	180.78	146.32

COLORADO DEPARTMENT OF TRANSPORTATION
ITEM UNIT COSTS BY PROJECTS -- 2019 COST DATA

13:44 Wednesday, August 7, 2019 261

PROJECT NUMBER	ITEM NUMBER/ PROJECT LOCATION	ITEM DESCRIPTION/ PROJECT LOCATION	DATE LET	UNIT/ QUANTITY	ENGR. EST.	AVERAGE BID	AWARDED BID
===== 614-10160 NHPP0821-107		Sig Head B-Plates SH 82 GLENWOOD SPRINGS TO CA	02/07/19	Each 39.00	220.00	296.50	290.00
	WEIGHTED AVERAGE FOR THE FIRST QUARTER			203.00	319.61	203.01	173.92
FSA0252-468		I-25 AND PLUM CREEK IMPROVEME	04/18/19	12.00	450.00	99.00	55.00
	WEIGHTED AVERAGE FOR THE SECOND QUARTER			12.00	450.00	99.00	55.00
	WEIGHTED AVERAGE FOR THE YEAR			215.00	326.88	192.02	167.28
===== 614-10245		LUS LED (Single Faced)		Each			
NHPP0703-445		I-70 WESTBOUND PEAK PERIOD SH	04/25/19	7.00	50000.00	33742.04	35500.00
	WEIGHTED AVERAGE FOR THE SECOND QUARTER			7.00	50000.00	33742.04	35500.00
	WEIGHTED AVERAGE FOR THE YEAR			7.00	50000.00	33742.04	35500.00
===== 614-31800		Monotube Overhead Sign Cant (18 In Dia)		Each			
FSA0703-454		EB I-70 AUX LANE WARD TO KIPL	05/16/19	1.00	37000.00	57195.50	45000.00
	WEIGHTED AVERAGE FOR THE SECOND QUARTER			1.00	37000.00	57195.50	45000.00
	WEIGHTED AVERAGE FOR THE YEAR			1.00	37000.00	57195.50	45000.00
===== 614-32000		Monotube Overhead Sign Cant (20 In Dia)		Each			
NHPP0703-445		I-70 WESTBOUND PEAK PERIOD SH	04/25/19	1.00	42000.00	48196.08	42680.00
	WEIGHTED AVERAGE FOR THE SECOND QUARTER			1.00	42000.00	48196.08	42680.00
	WEIGHTED AVERAGE FOR THE YEAR			1.00	42000.00	48196.08	42680.00
===== 614-32400		Monotube Overhead Sign Cant (24 In Dia)		Each			
NHPP0703-445		I-70 WESTBOUND PEAK PERIOD SH	04/25/19	21.00	46000.00	58327.02	43417.00
	WEIGHTED AVERAGE FOR THE SECOND QUARTER			21.00	46000.00	58327.02	43417.00
	WEIGHTED AVERAGE FOR THE YEAR			21.00	46000.00	58327.02	43417.00

COLORADO DEPARTMENT OF TRANSPORTATION
 ITEM UNIT COSTS BY PROJECTS -- 2019 COST DATA

13:44 Wednesday, August 7, 2019 262

PROJECT NUMBER	ITEM NUMBER/ PROJECT LOCATION	ITEM DESCRIPTION/ PROJECT LOCATION	DATE LET	UNIT/ QUANTITY	ENGR. EST.	AVERAGE BID	AWARDED BID
===== 614-42000		Monotube Overhead Sign Brdg (20 In Dia)		Each			
FSA0252-468		I-25 AND PLUM CREEK IMPROVEME	04/18/19	1.00	70000.00	114141.00	88285.00
	WEIGHTED AVERAGE FOR THE SECOND QUARTER			1.00	70000.00	114141.00	88285.00
	WEIGHTED AVERAGE FOR THE YEAR			1.00	70000.00	114141.00	88285.00
===== 614-42400		Monotube Overhead Sign Brdg (24 In Dia)		Each			
SHE0701-243		I-70 EXIT 26 DDI MODIFICATION	05/16/19	1.00	100000.00	158037.50	120000.00
	WEIGHTED AVERAGE FOR THE SECOND QUARTER			1.00	100000.00	158037.50	120000.00
	WEIGHTED AVERAGE FOR THE YEAR			1.00	100000.00	158037.50	120000.00
===== 614-70000		Prog Traf Sig Face		Each			
NHPP2254-089		I-225 RESURFACING FROM I-25 T	03/21/19	5.00	5300.00	5464.77	5400.00
	WEIGHTED AVERAGE FOR THE FIRST QUARTER			5.00	5300.00	5464.77	5400.00
	WEIGHTED AVERAGE FOR THE YEAR			5.00	5300.00	5464.77	5400.00
===== 614-70010		Mod Sig Face		Each			
SHE2254-090		Colfax & I-225, Colfax & Cham	03/07/19	3.00	500.00	455.00	620.00
	WEIGHTED AVERAGE FOR THE FIRST QUARTER			3.00	500.00	455.00	620.00
	WEIGHTED AVERAGE FOR THE YEAR			3.00	500.00	455.00	620.00
===== 614-70024		1310nm SFP Optic Module		Each			
SHER100-289		INTERSECTIONS @ SH83 & LONGS	01/03/19	2.00	650.00	333.60	312.00
ITSSW01-638		ETHERNET PHASE III (PRIMARYLY	02/07/19	60.00	400.00	687.50	1000.00
SHER100-284		FY19 NORTH SIGNAL PKG	02/21/19	3.00	2000.00	421.33	601.00
SHE 0252-481		I-25 RAMP METER INSTALLATION	03/21/19	26.00	300.00	275.00	265.00
SHER100-308		MIDPOINT - SIGNAL CONST PACKA	03/21/19	6.00	575.00	577.50	610.00
	WEIGHTED AVERAGE FOR THE FIRST QUARTER			97.00	438.66	515.32	752.34

COLORADO DEPARTMENT OF TRANSPORTATION
 ITEM UNIT COSTS BY PROJECTS -- 2019 COST DATA

13:44 Wednesday, August 7, 2019 263

PROJECT NUMBER	ITEM NUMBER/ PROJECT LOCATION	ITEM DESCRIPTION/ PROJECT LOCATION	DATE LET	UNIT/ QUANTITY	ENGR. EST.	AVERAGE BID	AWARDED BID
=====	614-70024	1310nm SFP Optic Module		Each	=====	=====	=====
NHPP0703-445		I-70 WESTBOUND PEAK PERIOD SH	04/25/19	16.00	500.00	473.52	498.00
IM0252-456		I-25 COLORADO SPRINGS RAMP ME	05/16/19	28.00	400.00	544.33	468.00
		WEIGHTED AVERAGE FOR THE SECOND QUARTER		44.00	436.36	518.58	478.91
		WEIGHTED AVERAGE FOR THE YEAR		141.00	437.94	516.51	667.01
=====	614-70026	CWDM Multiplexor Demultiplexor Module		Each	=====	=====	=====
ITSSW01-638		ETHERNET PHASE III (PRIMARYLY	02/07/19	4.00	7500.00	9528.50	10000.00
		WEIGHTED AVERAGE FOR THE FIRST QUARTER		4.00	7500.00	9528.50	10000.00
		WEIGHTED AVERAGE FOR THE YEAR		4.00	7500.00	9528.50	10000.00
=====	614-70028	CWDM SFP Optic Module		Each	=====	=====	=====
ITSSW01-638		ETHERNET PHASE III (PRIMARYLY	02/07/19	66.00	900.00	859.50	700.00
SHE 0252-481		I-25 RAMP METER INSTALLATION	03/21/19	2.00	1000.00	852.33	830.00
		WEIGHTED AVERAGE FOR THE FIRST QUARTER		68.00	902.94	859.19	703.82
NHPP0703-445		I-70 WESTBOUND PEAK PERIOD SH	04/25/19	25.00	1600.00	1272.30	1323.00
		WEIGHTED AVERAGE FOR THE SECOND QUARTER		25.00	1600.00	1272.30	1323.00
		WEIGHTED AVERAGE FOR THE YEAR		93.00	1090.32	1004.65	870.27
=====	614-70030	Optical Attenuator		Each	=====	=====	=====
SHER100-289		INTERSECTIONS @ SH83 & LONGS	01/03/19	2.00	200.00	106.40	99.00
ITSSW01-638		ETHERNET PHASE III (PRIMARYLY	02/07/19	126.00	100.00	62.50	50.00
SHER100-284		FY19 NORTH SIGNAL PKG	02/21/19	3.00	2000.00	334.33	335.00
SHE 0252-481		I-25 RAMP METER INSTALLATION	03/21/19	28.00	85.00	91.33	100.00
SHER100-308		MIDPOINT - SIGNAL CONST PACKA	03/21/19	3.00	175.00	267.50	155.00
		WEIGHTED AVERAGE FOR THE FIRST QUARTER		162.00	135.22	80.61	66.47

COLORADO DEPARTMENT OF TRANSPORTATION
 ITEM UNIT COSTS BY PROJECTS -- 2019 COST DATA

13:44 Wednesday, August 7, 2019 264

PROJECT NUMBER	ITEM NUMBER/ PROJECT LOCATION	ITEM DESCRIPTION/ PROJECT LOCATION	DATE LET	UNIT/ QUANTITY	ENGR. EST.	AVERAGE BID	AWARDED BID
=====	614-70030	Optical Attenuator		Each	=====	=====	=====
NHPP0703-445		I-70 WESTBOUND PEAK PERIOD SH	04/25/19	41.00	150.00	168.92	178.00
IM0252-456		I-25 COLORADO SPRINGS RAMP ME	05/16/19	28.00	150.00	140.67	193.00
		WEIGHTED AVERAGE FOR THE SECOND QUARTER		69.00	150.00	157.46	184.09
		WEIGHTED AVERAGE FOR THE YEAR		231.00	139.63	108.62	101.60
=====	614-70032	Optical Filter		Each	=====	=====	=====
ITSSW01-638		ETHERNET PHASE III (PRIMARYLY	02/07/19	76.00	450.00	477.50	500.00
		WEIGHTED AVERAGE FOR THE FIRST QUARTER		76.00	450.00	477.50	500.00
NHPP0703-445		I-70 WESTBOUND PEAK PERIOD SH	04/25/19	66.00	1000.00	535.02	565.00
		WEIGHTED AVERAGE FOR THE SECOND QUARTER		66.00	1000.00	535.02	565.00
		WEIGHTED AVERAGE FOR THE YEAR		142.00	705.63	510.04	530.21
=====	614-70112	Traf Sig Face (12)		Each	=====	=====	=====
NHPPR500-173		US 160_550 DURANGO SIGNALS OP	01/03/19	2.00	600.00	552.00	494.00
		WEIGHTED AVERAGE FOR THE FIRST QUARTER		2.00	600.00	552.00	494.00
		WEIGHTED AVERAGE FOR THE YEAR		2.00	600.00	552.00	494.00
=====	614-70150	Ped Sig Face (16) (Countdown)		Each	=====	=====	=====
SHER100-289		INTERSECTIONS @ SH83 & LONGS	01/03/19	6.00	650.00	555.00	525.00
STAM086-075		SH96A ABRIENDO - ORMAN SAFETY	01/31/19	24.00	800.00	680.67	560.00
SHER100-284		FY19 NORTH SIGNAL PKG	02/21/19	18.00	800.00	553.33	485.00
SHE2254-090		Colfax & I-225, Colfax & Cham	03/07/19	14.00	550.00	695.00	720.00
SHER100-308		MIDPOINT - SIGNAL CONST PACKA	03/21/19	40.00	525.00	625.00	550.00
NHPP2254-089		I-225 RESURFACING FROM I-25 T	03/21/19	2.00	750.00	809.44	700.00

COLORADO DEPARTMENT OF TRANSPORTATION
 ITEM UNIT COSTS BY PROJECTS -- 2019 COST DATA

13:44 Wednesday, August 7, 2019 265

PROJECT NUMBER	ITEM NUMBER/ PROJECT LOCATION	ITEM DESCRIPTION/ PROJECT LOCATION	DATE LET	UNIT/ QUANTITY	ENGR. EST.	AVERAGE BID	AWARDED BID
===== 614-70150		Ped Sig Face (16) (Countdown)		Each =====			
STM0242-077		US24 - 8TH ST TO WEST OF MANI	03/28/19	8.00	720.00	695.00	615.00
		WEIGHTED AVERAGE FOR THE FIRST QUARTER		112.00	655.89	634.47	568.93
NHPP030A-035		US 285/SH30	04/04/19	40.00	600.00	840.00	840.00
FSA0252-468		I-25 AND PLUM CREEK IMPROVEME	04/18/19	2.00	600.00	594.25	485.00
FSA2873-190		US 287 AND FOOTHILLS PARKWAY	05/02/19	8.00	700.00	710.00	750.00
		WEIGHTED AVERAGE FOR THE SECOND QUARTER		50.00	616.00	776.78	811.40
		WEIGHTED AVERAGE FOR THE YEAR		162.00	643.58	659.91	643.77
===== 614-70200		Access Ped Sig		Each =====			
STAM086-075		SH96A ABRIENDO - ORMAN SAFETY	01/31/19	8.00	1280.65	1416.00	890.00
		WEIGHTED AVERAGE FOR THE FIRST QUARTER		8.00	1280.65	1416.00	890.00
FSA0252-468		I-25 AND PLUM CREEK IMPROVEME	04/18/19	10.00	1300.00	1691.25	1435.00
		WEIGHTED AVERAGE FOR THE SECOND QUARTER		10.00	1300.00	1691.25	1435.00
		WEIGHTED AVERAGE FOR THE YEAR		18.00	1291.40	1588.03	1192.78
===== 614-70225		Traf Sig Face (12-12)		Each =====			
SHE 0252-481		I-25 RAMP METER INSTALLATION	03/21/19	32.00	650.00	565.67	590.00
		WEIGHTED AVERAGE FOR THE FIRST QUARTER		32.00	650.00	565.67	590.00
IM0252-456		I-25 COLORADO SPRINGS RAMP ME	05/16/19	23.00	700.00	605.67	640.00
		WEIGHTED AVERAGE FOR THE SECOND QUARTER		23.00	700.00	605.67	640.00
		WEIGHTED AVERAGE FOR THE YEAR		55.00	670.91	582.39	610.91

COLORADO DEPARTMENT OF TRANSPORTATION
 ITEM UNIT COSTS BY PROJECTS -- 2019 COST DATA

13:44 Wednesday, August 7, 2019 266

PROJECT NUMBER	ITEM NUMBER/ PROJECT LOCATION	ITEM DESCRIPTION/ PROJECT LOCATION	DATE LET	UNIT/ QUANTITY	ENGR. EST.	AVERAGE BID	AWARDED BID
===== 614-70336		Traf Sig Face (12-12-12)		Each	=====		
NHPPR500-173		US 160_550 DURANGO SIGNALS OP	01/03/19	5.00	1200.00	929.00	783.00
SHER100-289		INTERSECTIONS @ SH83 & LONGS	01/03/19	19.00	750.00	770.80	725.00
STAM086-075		SH96A ABRIENDO - ORMAN SAFETY	01/31/19	46.00	1200.00	898.33	720.00
NHPP0821-107		SH 82 GLENWOOD SPRINGS TO CA	02/07/19	17.00	1200.00	1292.50	1265.00
SHER100-284		FY19 NORTH SIGNAL PKG	02/21/19	39.00	750.00	716.67	635.00
SHE2254-090		Colfax & I-225, Colfax & Cham	03/07/19	51.00	700.00	1178.00	1200.00
SHE 0252-481		I-25 RAMP METER INSTALLATION	03/21/19	40.00	700.00	871.73	1020.00
SHER100-308		MIDPOINT - SIGNAL CONST PACKA	03/21/19	89.00	700.00	745.00	625.00
STM0242-077		US24 - 8TH ST TO WEST OF MANI	03/28/19	16.00	850.00	946.67	760.00
		WEIGHTED AVERAGE FOR THE FIRST QUARTER		322.00	822.05	875.41	828.77
NHPP030A-035		US 285/SH30	04/04/19	29.00	750.00	1000.00	1000.00
FSA0252-468		I-25 AND PLUM CREEK IMPROVEME	04/18/19	14.00	800.00	786.25	574.00
FSA2873-190		US 287 AND FOOTHILLS PARKWAY	05/02/19	14.00	750.00	970.00	950.00
IM0252-456		I-25 COLORADO SPRINGS RAMP ME	05/16/19	25.00	900.00	911.67	780.00
SHE0701-243		I-70 EXIT 26 DDI MODIFICATION	05/16/19	2.00	1100.00	1587.50	1500.00
		WEIGHTED AVERAGE FOR THE SECOND QUARTER		84.00	811.31	924.82	867.10
		WEIGHTED AVERAGE FOR THE YEAR		406.00	819.83	884.74	836.70
===== 614-70448		Traf Sig Face (12-12-12-12)		Each	=====		
NHPPR500-173		US 160_550 DURANGO SIGNALS OP	01/03/19	7.00	1300.00	1079.00	933.00
STAM086-075		SH96A ABRIENDO - ORMAN SAFETY	01/31/19	9.00	1000.00	1085.67	795.00
SHER100-284		FY19 NORTH SIGNAL PKG	02/21/19	8.00	1200.00	955.67	897.00
SHE2254-090		Colfax & I-225, Colfax & Cham	03/07/19	12.00	1000.00	1511.50	1500.00
STM0242-077		US24 - 8TH ST TO WEST OF MANI	03/28/19	6.00	1200.00	1106.67	900.00
		WEIGHTED AVERAGE FOR THE FIRST QUARTER		42.00	1116.67	1154.68	1053.86
NHPP030A-035		US 285/SH30	04/04/19	6.00	1200.00	1200.00	1200.00
FSA0252-468		I-25 AND PLUM CREEK IMPROVEME	04/18/19	2.00	1000.00	990.00	722.00
FSA2873-190		US 287 AND FOOTHILLS PARKWAY	05/02/19	8.00	1100.00	1272.50	1175.00
		WEIGHTED AVERAGE FOR THE SECOND QUARTER		16.00	1125.00	1182.67	1127.75
		WEIGHTED AVERAGE FOR THE YEAR		58.00	1118.97	1160.81	1074.24

COLORADO DEPARTMENT OF TRANSPORTATION
 ITEM UNIT COSTS BY PROJECTS -- 2019 COST DATA

13:44 Wednesday, August 7, 2019 267

PROJECT NUMBER	ITEM NUMBER/ PROJECT LOCATION	ITEM DESCRIPTION/ PROJECT LOCATION	DATE LET	UNIT/ QUANTITY	ENGR. EST.	AVERAGE BID	AWARDED BID
=====	614-70560	Traf Sig Face (12-12-12-12-12)		Each	=====	=====	=====
SHER100-308		MIDPOINT - SIGNAL CONST PACKA	03/21/19	4.00	1400.00	1390.00	1480.00
		WEIGHTED AVERAGE FOR THE FIRST QUARTER		4.00	1400.00	1390.00	1480.00
		WEIGHTED AVERAGE FOR THE YEAR		4.00	1400.00	1390.00	1480.00
=====	614-72830	Communications Cabinet		Each	=====	=====	=====
SHE 0252-481		I-25 RAMP METER INSTALLATION	03/21/19	16.00	12000.00	12537.00	14775.00
		WEIGHTED AVERAGE FOR THE FIRST QUARTER		16.00	12000.00	12537.00	14775.00
NHPP0703-445		I-70 WESTBOUND PEAK PERIOD SH	04/25/19	20.00	2500.00	24099.22	25304.00
		WEIGHTED AVERAGE FOR THE SECOND QUARTER		20.00	2500.00	24099.22	25304.00
		WEIGHTED AVERAGE FOR THE YEAR		36.00	6722.22	18960.45	20624.44
=====	614-72832	Comm Cabinet (Type 2)		Each	=====	=====	=====
ITSSW01-638		ETHERNET PHASE III (PRIMARYLY	02/07/19	16.00	15000.00	11625.00	14000.00
		WEIGHTED AVERAGE FOR THE FIRST QUARTER		16.00	15000.00	11625.00	14000.00
NHPP0703-445		I-70 WESTBOUND PEAK PERIOD SH	04/25/19	4.00	10000.00	19489.61	21032.00
		WEIGHTED AVERAGE FOR THE SECOND QUARTER		4.00	10000.00	19489.61	21032.00
		WEIGHTED AVERAGE FOR THE YEAR		20.00	14000.00	13769.89	15406.40
=====	614-72836	Conflict Monitor		Each	=====	=====	=====
SHER100-289		INTERSECTIONS @ SH83 & LONGS	01/03/19	1.00	1000.00	1106.00	1050.00
SHER100-284		FY19 NORTH SIGNAL PKG	02/21/19	3.00	1000.00	898.33	961.00

PROJECT NUMBER	ITEM NUMBER/ PROJECT LOCATION	ITEM DESCRIPTION/ PROJECT LOCATION	DATE LET	UNIT/ QUANTITY	ENGR. EST.	AVERAGE BID	AWARDED BID
===== 614-72836		Conflict Monitor		Each =====			
SHE2254-090		Colfax & I-225, Colfax & Cham	03/07/19	4.00	900.00	1420.00	1500.00
SHER100-308		MIDPOINT - SIGNAL CONST PACKA	03/21/19	3.00	920.00	802.50	820.00
	WEIGHTED AVERAGE FOR THE FIRST QUARTER			11.00	941.82	1063.93	1126.64
	WEIGHTED AVERAGE FOR THE YEAR			11.00	941.82	1063.93	1126.64
===== 614-72855		Traf Sig Ctrl Cabinet		Each =====			
SHER100-289		INTERSECTIONS @ SH83 & LONGS	01/03/19	1.00	25000.00	19398.00	16000.00
STAM086-075		SH96A ABRIENDO - ORMAN SAFETY	01/31/19	3.00	15000.00	22926.67	19780.00
SHER100-284		FY19 NORTH SIGNAL PKG	02/21/19	3.00	20000.00	16450.00	16100.00
SHE2254-090		Colfax & I-225, Colfax & Cham	03/07/19	4.00	15000.00	20780.50	21000.00
SHER100-308		MIDPOINT - SIGNAL CONST PACKA	03/21/19	3.00	15000.00	16900.00	16500.00
STM0242-077		US24 - 8TH ST TO WEST OF MANI	03/28/19	1.00	23100.00	22283.33	21150.00
	WEIGHTED AVERAGE FOR THE FIRST QUARTER			15.00	17206.67	19646.85	18552.67
FSA2873-190		US 287 AND FOOTHILLS PARKWAY	05/02/19	1.00	20000.00	23550.00	21400.00
	WEIGHTED AVERAGE FOR THE SECOND QUARTER			1.00	20000.00	23550.00	21400.00
	WEIGHTED AVERAGE FOR THE YEAR			16.00	17381.25	19832.71	18730.63
===== 614-72858		Ped Pole (3.5 In)		Each =====			
SHE2254-090		Colfax & I-225, Colfax & Cham	03/07/19	9.00	1750.00	1180.00	1050.00
	WEIGHTED AVERAGE FOR THE FIRST QUARTER			9.00	1750.00	1180.00	1050.00
	WEIGHTED AVERAGE FOR THE YEAR			9.00	1750.00	1180.00	1050.00
===== 614-72860		Ped Push Button		Each =====			
STAM086-075		SH96A ABRIENDO - ORMAN SAFETY	01/31/19	16.00	430.00	1528.33	1375.00
SHER100-284		FY19 NORTH SIGNAL PKG	02/21/19	16.00	700.00	243.67	182.00
C R100-315		R1 ADA CURB RAMPS - PH 5	03/07/19	5.00	750.00	3227.50	1770.00
SHE2254-090		Colfax & I-225, Colfax & Cham	03/07/19	14.00	600.00	260.00	330.00
SHER100-308		MIDPOINT - SIGNAL CONST PACKA	03/21/19	42.00	600.00	297.50	220.00

COLORADO DEPARTMENT OF TRANSPORTATION
ITEM UNIT COSTS BY PROJECTS -- 2019 COST DATA

13:44 Wednesday, August 7, 2019 269

PROJECT NUMBER	ITEM NUMBER/ PROJECT LOCATION	ITEM DESCRIPTION/ PROJECT LOCATION	DATE LET	UNIT/ QUANTITY	ENGR. EST.	AVERAGE BID	AWARDED BID
===== 614-72860		Ped Push Button		Each =====			
STM0242-077		US24 - 8TH ST TO WEST OF MANI	03/28/19	3.00	700.00	396.67	400.00
		WEIGHTED AVERAGE FOR THE FIRST QUARTER		96.00	599.27	674.76	508.56
NHPP030A-035		US 285/SH30	04/04/19	6.00	700.00	420.00	420.00
FSA2873-190		US 287 AND FOOTHILLS PARKWAY	05/02/19	8.00	500.00	402.50	435.00
		WEIGHTED AVERAGE FOR THE SECOND QUARTER		14.00	585.71	407.27	428.57
		WEIGHTED AVERAGE FOR THE YEAR		110.00	597.55	651.13	498.38
===== 614-72863		Ped Push Button Post Assem		Each =====			
SHER100-289		INTERSECTIONS @ SH83 & LONGS	01/03/19	6.00	2500.00	1395.20	1325.00
NHPP0741-022		SH 74: I-70 TO CR 65 RESURFAC	02/14/19	9.00	3000.00	3318.04	3215.00
SHER100-284		FY19 NORTH SIGNAL PKG	02/21/19	3.00	2000.00	1192.00	1416.00
C R100-315		R1 ADA CURB RAMPS - PH 5	03/07/19	27.00	2300.00	2150.50	2301.00
SHE2254-090		Colfax & I-225, Colfax & Cham	03/07/19	6.00	3000.00	1219.50	1000.00
SHER100-308		MIDPOINT - SIGNAL CONST PACKA	03/21/19	15.00	3000.00	1170.00	740.00
NHPP2254-089		I-225 RESURFACING FROM I-25 T	03/21/19	2.00	2000.00	2733.53	3000.00
STM0242-077		US24 - 8TH ST TO WEST OF MANI	03/28/19	5.00	1500.00	1368.33	1105.00
		WEIGHTED AVERAGE FOR THE FIRST QUARTER		73.00	2528.77	1952.19	1806.64
NHPP030A-035		US 285/SH30	04/04/19	20.00	2500.00	2400.00	2400.00
FSA2873-190		US 287 AND FOOTHILLS PARKWAY	05/02/19	7.00	1700.00	1897.50	1525.00
CR300-248		CRAIG RESIDENCY ADA RAMPS	05/16/19	2.00	3000.00	2299.67	1600.00
STMC430-020		ADA RAMPS DIVIDE ESB	05/23/19	2.00	950.00	2000.00	2000.00
		WEIGHTED AVERAGE FOR THE SECOND QUARTER		31.00	2251.61	2199.12	2125.00
		WEIGHTED AVERAGE FOR THE YEAR		104.00	2446.15	1996.51	1901.54
===== 614-72864		Fire Preempt Unit		Each =====			
SHE2254-090		Colfax & I-225, Colfax & Cham	03/07/19	6.00	6000.00	2419.00	2500.00
		WEIGHTED AVERAGE FOR THE FIRST QUARTER		6.00	6000.00	2419.00	2500.00
		WEIGHTED AVERAGE FOR THE YEAR		6.00	6000.00	2419.00	2500.00

COLORADO DEPARTMENT OF TRANSPORTATION
 ITEM UNIT COSTS BY PROJECTS -- 2019 COST DATA

13:44 Wednesday, August 7, 2019 270

PROJECT NUMBER	ITEM NUMBER/ PROJECT LOCATION	ITEM DESCRIPTION/ PROJECT LOCATION	DATE LET	UNIT/ QUANTITY	ENGR. EST.	AVERAGE BID	AWARDED BID
===== 614-72866		Fire Preempt Unit + Timer		Each			
FSA0252-468		I-25 AND PLUM CREEK IMPROVEME	04/18/19	2.00	6000.00	3993.75	2155.00
FSA2873-190		US 287 AND FOOTHILLS PARKWAY	05/02/19	1.00	4000.00	5625.00	5550.00
		WEIGHTED AVERAGE FOR THE SECOND QUARTER		3.00	5333.33	4320.00	3286.67
		WEIGHTED AVERAGE FOR THE YEAR		3.00	5333.33	4320.00	3286.67
===== 614-72871		Loop Detect Wire (Prefab) Spec		Lin Foot			
NHPP2254-089		I-225 RESURFACING FROM I-25 T	03/21/19	232.00	5.00	16.55	13.00
		WEIGHTED AVERAGE FOR THE FIRST QUARTER		232.00	5.00	16.55	13.00
		WEIGHTED AVERAGE FOR THE YEAR		232.00	5.00	16.55	13.00
===== 614-72875		Loop Detect Wire		Lin Foot			
STA067A-038		SH 67 SEDALIA RESURFACING	01/31/19	464.00	4.00	5.94	6.50
NHPP0821-107		SH 82 GLENWOOD SPRINGS TO CA	02/07/19	4,624.00	4.80	11.80	11.60
NHPP0741-022		SH 74: I-70 TO CR 65 RESURFAC	02/14/19	6,336.00	5.00	6.08	5.92
NHPP006A-058		US 6 LOVELAND PASS - I-70 (FY	03/07/19	750.00	10.00	9.31	7.62
SHE 0252-481		I-25 RAMP METER INSTALLATION	03/21/19	12,320.00	4.25	4.83	4.00
NHPP2254-089		I-225 RESURFACING FROM I-25 T	03/21/19	5,200.00	4.50	7.06	6.00
		WEIGHTED AVERAGE FOR THE FIRST QUARTER		29,694.00	4.68	6.38	6.07
NHPP0703-445		I-70 WESTBOUND PEAK PERIOD SH	04/25/19	3,180.00	4.00	8.15	8.00
IM0252-456		I-25 COLORADO SPRINGS RAMP ME	05/16/19	18,928.00	4.00	7.29	4.88
		WEIGHTED AVERAGE FOR THE SECOND QUARTER		22,108.00	4.00	7.42	5.33
		WEIGHTED AVERAGE FOR THE YEAR		51,802.00	4.39	6.82	5.76
===== 614-72878		Detect Amp (Loop) (4)		Each			
SHE 0252-481		I-25 RAMP METER INSTALLATION	03/21/19	20.00	1000.00	951.67	900.00
		WEIGHTED AVERAGE FOR THE FIRST QUARTER		20.00	1000.00	951.67	900.00
		WEIGHTED AVERAGE FOR THE YEAR		20.00	1000.00	951.67	900.00

COLORADO DEPARTMENT OF TRANSPORTATION
 ITEM UNIT COSTS BY PROJECTS -- 2019 COST DATA

13:44 Wednesday, August 7, 2019 271

PROJECT NUMBER	ITEM NUMBER/ PROJECT LOCATION	ITEM DESCRIPTION/ PROJECT LOCATION	DATE LET	UNIT/ QUANTITY	ENGR. EST.	AVERAGE BID	AWARDED BID
===== 614-72884		Detect (Micro Wave)		Each			
SHE 0252-481		I-25 RAMP METER INSTALLATION	03/21/19	1.00	10000.00	10392.00	9785.00
		WEIGHTED AVERAGE FOR THE FIRST QUARTER		1.00	10000.00	10392.00	9785.00
FSA0252-468		I-25 AND PLUM CREEK IMPROVEME	04/18/19	11.00	9000.00	9437.75	7651.00
		WEIGHTED AVERAGE FOR THE SECOND QUARTER		11.00	9000.00	9437.75	7651.00
		WEIGHTED AVERAGE FOR THE YEAR		12.00	9083.33	9498.66	7828.83
===== 614-72885		Detect (Spec)		Each			
NHPPR500-173		US 160_550 DURANGO SIGNALS OP	01/03/19	90.00	9000.00	8096.60	8203.20
SHER100-289		INTERSECTIONS @ SH83 & LONGS	01/03/19	6.00	12000.00	6080.20	5800.00
SHER100-284		FY19 NORTH SIGNAL PKG	02/21/19	17.00	12000.00	7315.33	7733.00
SHE2254-090		Colfax & I-225, Colfax & Cham	03/07/19	6.00	12000.00	11267.50	12000.00
SHER100-308		MIDPOINT - SIGNAL CONST PACKA	03/21/19	35.00	11500.00	7675.00	7900.00
		WEIGHTED AVERAGE FOR THE FIRST QUARTER		154.00	10133.12	7828.97	8136.68
		WEIGHTED AVERAGE FOR THE YEAR		154.00	10133.12	7828.97	8136.68
===== 614-72886		Intersection Detect Sys (Camera)		Each			
STM0242-077		US24 - 8TH ST TO WEST OF MANI	03/28/19	4.00	6000.00	6766.67	6300.00
		WEIGHTED AVERAGE FOR THE FIRST QUARTER		4.00	6000.00	6766.67	6300.00
NHPP030A-035		US 285/SH30	04/04/19	5.00	12000.00	12100.00	12100.00
		WEIGHTED AVERAGE FOR THE SECOND QUARTER		5.00	12000.00	12100.00	12100.00
		WEIGHTED AVERAGE FOR THE YEAR		9.00	9333.33	8335.29	9522.22
===== 614-72887		Detect (Microwave Veh)		Each			
ITSSW01-638		ETHERNET PHASE III (PRIMARYLY	02/07/19	2.00	10800.00	9500.00	10000.00

COLORADO DEPARTMENT OF TRANSPORTATION
 ITEM UNIT COSTS BY PROJECTS -- 2019 COST DATA

13:44 Wednesday, August 7, 2019 272

PROJECT NUMBER	ITEM NUMBER/ PROJECT LOCATION	ITEM DESCRIPTION/ PROJECT LOCATION	DATE LET	UNIT/ QUANTITY	ENGR. EST.	AVERAGE BID	AWARDED BID
===== 614-72887 SHE 0252-481		Detect (Microwave Veh) I-25 RAMP METER INSTALLATION	03/21/19	Each 16.00	10500.00	11705.82	11135.00
		WEIGHTED AVERAGE FOR THE FIRST QUARTER		18.00	10533.33	11536.14	11008.89
IM0252-456		I-25 COLORADO SPRINGS RAMP ME	05/16/19	12.00	10000.00	11247.67	11043.00
		WEIGHTED AVERAGE FOR THE SECOND QUARTER		12.00	10000.00	11247.67	11043.00
		WEIGHTED AVERAGE FOR THE YEAR		30.00	10320.00	11418.13	11022.53
===== 614-72895 SHE2254-090		Vehicle Detect Sys (Single Camera) Colfax & I-225, Colfax & Cham	03/07/19	Each 1.00	9000.00	11650.00	12500.00
		WEIGHTED AVERAGE FOR THE FIRST QUARTER		1.00	9000.00	11650.00	12500.00
		WEIGHTED AVERAGE FOR THE YEAR		1.00	9000.00	11650.00	12500.00
===== 614-73005 NHPP0703-445		Piezo (Elec) (CL II) I-70 WESTBOUND PEAK PERIOD SH	04/25/19	Each 5.00	3500.00	8134.05	8573.00
		WEIGHTED AVERAGE FOR THE SECOND QUARTER		5.00	3500.00	8134.05	8573.00
		WEIGHTED AVERAGE FOR THE YEAR		5.00	3500.00	8134.05	8573.00
===== 614-75855 NHPP0821-107		Inst Traf Sig Ctrler Cab SH 82 GLENWOOD SPRINGS TO CA	02/07/19	Each 3.00	2400.00	6060.00	5920.00
		WEIGHTED AVERAGE FOR THE FIRST QUARTER		3.00	2400.00	6060.00	5920.00
		WEIGHTED AVERAGE FOR THE YEAR		3.00	2400.00	6060.00	5920.00
===== 614-80000 ER119A-065		Flash Beacon PR SH 119A BOULDER CANYON	01/03/19	Each 12.00	2000.00	2249.43	1960.00

COLORADO DEPARTMENT OF TRANSPORTATION
 ITEM UNIT COSTS BY PROJECTS -- 2019 COST DATA

13:44 Wednesday, August 7, 2019 273

PROJECT NUMBER	ITEM NUMBER/ PROJECT LOCATION	ITEM DESCRIPTION/ PROJECT LOCATION	DATE LET	UNIT/ QUANTITY	ENGR. EST.	AVERAGE BID	AWARDED BID
=====	614-80000	Flash Beacon		Each	=====		
STA119A-069		SH 119: NEDERLAND - EAST					
STA067A-038		SH 67 SEDALIA RESURFACING	01/31/19	2.00	3000.00	3901.29	2800.00
NHPP0821-107		SH 82 GLENWOOD SPRINGS TO CA	02/07/19	4.00	3600.00	6850.00	6700.00
NHPP0741-022		SH 74: I-70 TO CR 65 RESURFAC	02/14/19	3.00	3000.00	5330.81	5215.00
SHE 0252-481		I-25 RAMP METER INSTALLATION	03/21/19	32.00	3000.00	3303.67	3020.00
		WEIGHTED AVERAGE FOR THE FIRST QUARTER		53.00	2818.87	3097.59	3173.68
IM0252-456		I-25 COLORADO SPRINGS RAMP ME	05/16/19	24.00	2500.00	2511.33	1831.00
		WEIGHTED AVERAGE FOR THE SECOND QUARTER		24.00	2500.00	2511.33	1831.00
		WEIGHTED AVERAGE FOR THE YEAR		77.00	2719.48	2952.04	2755.18
=====	614-80010	Travel Time Indicator		Each	=====		
NHPP0703-445		I-70 WESTBOUND PEAK PERIOD SH	04/25/19	1.00	20000.00	34964.97	36903.00
		WEIGHTED AVERAGE FOR THE SECOND QUARTER		1.00	20000.00	34964.97	36903.00
		WEIGHTED AVERAGE FOR THE YEAR		1.00	20000.00	34964.97	36903.00
=====	614-80311	Barricade (Ty 3 F-A)		Each	=====		
FSA0142-068		SH 14 & WCR 33 INTERSECTION I	01/03/19	6.00	1000.00	308.88	10.50
		WEIGHTED AVERAGE FOR THE FIRST QUARTER		6.00	1000.00	308.88	10.50
		WEIGHTED AVERAGE FOR THE YEAR		6.00	1000.00	308.88	10.50
=====	614-80312	Barricade (Ty 3 F-B)		Each	=====		
STA067A-038		SH 67 SEDALIA RESURFACING	01/31/19	1.00	1000.00	3938.62	3400.00
		WEIGHTED AVERAGE FOR THE FIRST QUARTER		1.00	1000.00	3938.62	3400.00
		WEIGHTED AVERAGE FOR THE YEAR		1.00	1000.00	3938.62	3400.00
=====	614-80385	Rumble Strip		Lin Foot	=====		
ER119A-065		PR SH 119A BOULDER CANYON	01/03/19	78,978.00	0.22	0.27	0.18

COLORADO DEPARTMENT OF TRANSPORTATION
 ITEM UNIT COSTS BY PROJECTS -- 2019 COST DATA

13:44 Wednesday, August 7, 2019 274

PROJECT NUMBER	ITEM NUMBER/ PROJECT LOCATION	ITEM DESCRIPTION/ PROJECT LOCATION	DATE LET	UNIT/ QUANTITY	ENGR. EST.	AVERAGE BID	AWARDED BID
===== 614-80385		Rumble Strip		Lin Foot	=====		
STA119A-069		SH 119: NEDERLAND - EAST					
STR0132-021		SH 13-MOFFAT COUNTY-CR 3 SOUT	01/10/19	35,600.00	0.25	0.28	0.44
NHPP1601-076		US 160 MANCOS HILL (MP 40.000	02/21/19	11,290.00	0.80	0.33	0.35
NHPP006A-058		US 6 LOVELAND PASS - I-70 (FY	03/07/19	18,850.00	0.30	0.18	0.16
NHPP050A-033		US50 West of Delta EB Lanes R	03/14/19	37,049.00	0.20	0.31	0.40
STA0131-070 HMA ALT		SH 13 CR 5 NORTH AND SOUTH	03/28/19	65,835.00	0.25	0.41	0.30
STA0131-070 PCCP ALT		SH 13 CR 5 NORTH AND SOUTH					
	WEIGHTED AVERAGE FOR THE FIRST QUARTER			247,602.00	0.26	0.30	0.29
NHPP0703-445		I-70 WESTBOUND PEAK PERIOD SH	04/25/19	55,977.00	0.30	0.19	0.20
FBR0063-057		US-6 F-09-K BRIDGE OVER CASTL	05/30/19	719.00	1.00	2.85	3.00
	WEIGHTED AVERAGE FOR THE SECOND QUARTER			56,696.00	0.31	0.21	0.24
	WEIGHTED AVERAGE FOR THE YEAR			304,298.00	0.27	0.29	0.28
===== 614-80391		Rumble Strip (Grind) (Asphalt)		Lin Foot	=====		
IM0251-351		I-25 South of Pueblo MP 79.6	01/03/19	189,615.00	0.01	0.12	0.13
NHPP0821-107		SH 82 GLENWOOD SPRINGS TO CA	02/07/19	61,293.00	0.35	0.24	0.11
NHPP1601-073		US 160 PASSING LANE NORTH OF	03/07/19	14,750.00	0.50	0.33	0.35
NHPP0702-378		I-70 OFFICERS GULCH TO FRISCO	03/14/19	77,941.00	0.10	0.13	0.09
	WEIGHTED AVERAGE FOR THE FIRST QUARTER			343,599.00	0.11	0.14	0.13
FSA0061-090		SH 6: CENTER LINE RUMBLE STRI	05/02/19	162,024.00	0.20	0.25	0.25
FSA0142-067		SH 14 RUMBLESTRIPS: AULT TO S	06/13/19	259,683.00	0.26	0.25	0.25
	WEIGHTED AVERAGE FOR THE SECOND QUARTER			421,707.00	0.24	0.25	0.25
	WEIGHTED AVERAGE FOR THE YEAR			765,306.00	0.18	0.17	0.19
===== 614-80392		Rumble Strip (Grind) (Conc)		Lin Foot	=====		
FSA0061-090		SH 6: CENTER LINE RUMBLE STRI	05/02/19	115,630.00	0.65	0.69	0.69
	WEIGHTED AVERAGE FOR THE SECOND QUARTER			115,630.00	0.65	0.69	0.69
	WEIGHTED AVERAGE FOR THE YEAR			115,630.00	0.65	0.69	0.69

COLORADO DEPARTMENT OF TRANSPORTATION
ITEM UNIT COSTS BY PROJECTS -- 2019 COST DATA

13:44 Wednesday, August 7, 2019 275

PROJECT NUMBER	ITEM NUMBER/ PROJECT LOCATION	ITEM DESCRIPTION/ PROJECT LOCATION	DATE LET	UNIT/ QUANTITY	ENGR. EST.	AVERAGE BID	AWARDED BID
=====	614-81000	Sig-Light Pole Steel		Each	=====	=====	=====
SHER100-308		MIDPOINT - SIGNAL CONST PACKA	03/21/19	1.00	8000.00	10175.00	7900.00
		WEIGHTED AVERAGE FOR THE FIRST QUARTER		1.00	8000.00	10175.00	7900.00
		WEIGHTED AVERAGE FOR THE YEAR		1.00	8000.00	10175.00	7900.00
=====	614-81125	Sig-Light Pole Steel (1-25 Ft)		Each	=====	=====	=====
SHER100-308		MIDPOINT - SIGNAL CONST PACKA	03/21/19	1.00	11000.00	13777.50	11855.00
		WEIGHTED AVERAGE FOR THE FIRST QUARTER		1.00	11000.00	13777.50	11855.00
		WEIGHTED AVERAGE FOR THE YEAR		1.00	11000.00	13777.50	11855.00
=====	614-81130	Sig-Light Pole Steel (1-30 Ft)		Each	=====	=====	=====
SHER100-289		INTERSECTIONS @ SH83 & LONGS	01/03/19	1.00	17000.00	18510.00	17600.00
SHER100-284		FY19 NORTH SIGNAL PKG	02/21/19	1.00	16000.00	16970.00	16000.00
SHE2254-090		Colfax & I-225, Colfax & Cham	03/07/19	1.00	14000.00	9675.00	12000.00
SHER100-308		MIDPOINT - SIGNAL CONST PACKA	03/21/19	3.00	15000.00	15642.50	14885.00
		WEIGHTED AVERAGE FOR THE FIRST QUARTER		6.00	15333.33	16041.56	15042.50
		WEIGHTED AVERAGE FOR THE YEAR		6.00	15333.33	16041.56	15042.50
=====	614-81135	Sig-Light Pole Steel (1-35 Ft)		Each	=====	=====	=====
STAM086-075		SH96A ABRIENDO - ORMAN SAFETY	01/31/19	2.00	14000.00	19820.67	18900.00
SHE2254-090		Colfax & I-225, Colfax & Cham	03/07/19	1.00	15000.00	10247.50	12500.00
SHE 0252-481		I-25 RAMP METER INSTALLATION	03/21/19	2.00	13000.00	17687.17	16630.00
SHER100-308		MIDPOINT - SIGNAL CONST PACKA	03/21/19	1.00	13000.00	16300.00	16100.00
		WEIGHTED AVERAGE FOR THE FIRST QUARTER		6.00	13666.67	17383.88	16610.00
FSA0252-468		I-25 AND PLUM CREEK IMPROVEME	04/18/19	1.00	16000.00	19671.00	19481.00
IM0252-456		I-25 COLORADO SPRINGS RAMP ME	05/16/19	2.00	16000.00	20046.00	20138.00
		WEIGHTED AVERAGE FOR THE SECOND QUARTER		3.00	16000.00	19896.00	19919.00
		WEIGHTED AVERAGE FOR THE YEAR		9.00	14444.44	18350.08	17713.00

COLORADO DEPARTMENT OF TRANSPORTATION
ITEM UNIT COSTS BY PROJECTS -- 2019 COST DATA

13:44 Wednesday, August 7, 2019 276

PROJECT NUMBER	ITEM NUMBER/ PROJECT LOCATION	ITEM DESCRIPTION/ PROJECT LOCATION	DATE LET	UNIT/ QUANTITY	ENGR. EST.	AVERAGE BID	AWARDED BID
===== 614-81140		Sig-Light Pole Steel (1-40 Ft)		Each	=====		
SHER100-289		INTERSECTIONS @ SH83 & LONGS	01/03/19	1.00	18000.00	20114.00	19150.00
STAM086-075		SH96A ABRIENDO - ORMAN SAFETY	01/31/19	4.00	14000.00	21750.00	20250.00
SHE2254-090		Colfax & I-225, Colfax & Cham	03/07/19	1.00	16000.00	10792.50	13000.00
SHER100-308		MIDPOINT - SIGNAL CONST PACKA	03/21/19	1.00	13750.00	17462.50	16725.00
STM0242-077		US24 - 8TH ST TO WEST OF MANI	03/28/19	1.00	16000.00	20666.67	19200.00
	WEIGHTED AVERAGE FOR THE FIRST QUARTER			8.00	14968.75	20003.33	18634.38
	WEIGHTED AVERAGE FOR THE YEAR			8.00	14968.75	20003.33	18634.38
===== 614-81145		Sig-Light Pole Steel (1-45 Ft)		Each	=====		
STAM086-075		SH96A ABRIENDO - ORMAN SAFETY	01/31/19	2.00	15000.00	22083.33	20750.00
SHER100-284		FY19 NORTH SIGNAL PKG	02/21/19	1.00	17500.00	18494.33	18000.00
SHE 0252-481		I-25 RAMP METER INSTALLATION	03/21/19	2.00	17000.00	18855.33	18305.00
SHER100-308		MIDPOINT - SIGNAL CONST PACKA	03/21/19	1.00	15800.00	17707.50	17000.00
	WEIGHTED AVERAGE FOR THE FIRST QUARTER			6.00	16216.67	19795.88	18851.67
FSA2873-190		US 287 AND FOOTHILLS PARKWAY	05/02/19	1.00	18000.00	22500.00	21000.00
	WEIGHTED AVERAGE FOR THE SECOND QUARTER			1.00	18000.00	22500.00	21000.00
	WEIGHTED AVERAGE FOR THE YEAR			7.00	16471.43	20080.53	19158.57
===== 614-81150		Sig-Light Pole Steel (1-50 Ft)		Each	=====		
STAM086-075		SH96A ABRIENDO - ORMAN SAFETY	01/31/19	2.00	15500.00	23000.00	22375.00
SHER100-284		FY19 NORTH SIGNAL PKG	02/21/19	3.00	17000.00	18992.00	18190.00
SHE2254-090		Colfax & I-225, Colfax & Cham	03/07/19	1.00	17000.00	13550.00	16000.00
SHER100-308		MIDPOINT - SIGNAL CONST PACKA	03/21/19	4.00	15900.00	17950.00	17350.00
STM0242-077		US24 - 8TH ST TO WEST OF MANI	03/28/19	1.00	14900.00	21516.67	19950.00
	WEIGHTED AVERAGE FOR THE FIRST QUARTER			11.00	16136.36	19434.93	18606.36
FSA2873-190		US 287 AND FOOTHILLS PARKWAY	05/02/19	1.00	19000.00	23000.00	21000.00
	WEIGHTED AVERAGE FOR THE SECOND QUARTER			1.00	19000.00	23000.00	21000.00
	WEIGHTED AVERAGE FOR THE YEAR			12.00	16375.00	19672.60	18805.83

COLORADO DEPARTMENT OF TRANSPORTATION
ITEM UNIT COSTS BY PROJECTS -- 2019 COST DATA

13:44 Wednesday, August 7, 2019 277

PROJECT NUMBER	ITEM NUMBER/ PROJECT LOCATION	ITEM DESCRIPTION/ PROJECT LOCATION	DATE LET	UNIT/ QUANTITY	ENGR. EST.	AVERAGE BID	AWARDED BID
===== 614-81155		Sig-Light Pole Steel (1-55 Ft)		Each	=====		
SHER100-289		INTERSECTIONS @ SH83 & LONGS	01/03/19	1.00	19000.00	22954.00	21800.00
STAM086-075		SH96A ABRIENDO - ORMAN SAFETY	01/31/19	1.00	16000.00	23841.67	22875.00
SHER100-284		FY19 NORTH SIGNAL PKG	02/21/19	2.00	22000.00	19578.67	19000.00
SHE2254-090		Colfax & I-225, Colfax & Cham	03/07/19	2.00	17500.00	14876.00	17500.00
SHER100-308		MIDPOINT - SIGNAL CONST PACKA	03/21/19	7.00	15500.00	18120.00	17500.00
NHPP2254-089		I-225 RESURFACING FROM I-25 T	03/21/19	1.00	17000.00	24660.48	25000.00
STM0242-077		US24 - 8TH ST TO WEST OF MANI	03/28/19	1.00	14900.00	21716.67	20250.00
		WEIGHTED AVERAGE FOR THE FIRST QUARTER		15.00	16960.00	19896.91	19028.33
FSA2873-190		US 287 AND FOOTHILLS PARKWAY	05/02/19	1.00	20000.00	24235.00	21700.00
		WEIGHTED AVERAGE FOR THE SECOND QUARTER		1.00	20000.00	24235.00	21700.00
		WEIGHTED AVERAGE FOR THE YEAR		16.00	17150.00	20113.81	19195.31
===== 614-81160		Sig-Light Pole Steel (1-60 Ft)		Each	=====		
SHER100-308		MIDPOINT - SIGNAL CONST PACKA	03/21/19	1.00	22000.00	27272.50	26950.00
		WEIGHTED AVERAGE FOR THE FIRST QUARTER		1.00	22000.00	27272.50	26950.00
FSA2873-190		US 287 AND FOOTHILLS PARKWAY	05/02/19	1.00	23500.00	31900.00	31100.00
		WEIGHTED AVERAGE FOR THE SECOND QUARTER		1.00	23500.00	31900.00	31100.00
		WEIGHTED AVERAGE FOR THE YEAR		2.00	22750.00	29586.25	29025.00
===== 614-81165		Sig-Light Pole Steel (1-65 Ft)		Each	=====		
STAM086-075		SH96A ABRIENDO - ORMAN SAFETY	01/31/19	1.00	18500.00	30383.33	31150.00
SHE2254-090		Colfax & I-225, Colfax & Cham	03/07/19	4.00	21000.00	18858.50	22000.00
		WEIGHTED AVERAGE FOR THE FIRST QUARTER		5.00	20500.00	22001.64	23830.00
		WEIGHTED AVERAGE FOR THE YEAR		5.00	20500.00	22001.64	23830.00

COLORADO DEPARTMENT OF TRANSPORTATION
ITEM UNIT COSTS BY PROJECTS -- 2019 COST DATA

13:44 Wednesday, August 7, 2019 278

PROJECT NUMBER	ITEM NUMBER/ PROJECT LOCATION	ITEM DESCRIPTION/ PROJECT LOCATION	DATE LET	UNIT/ QUANTITY	ENGR. EST.	AVERAGE BID	AWARDED BID
===== 614-81170		Sig-Light Pole Steel (1-70 Ft)		Each	=====		
SHER100-289		INTERSECTIONS @ SH83 & LONGS	01/03/19	1.00	22000.00	33651.00	32000.00
SHE2254-090		Colfax & I-225, Colfax & Cham	03/07/19	1.00	25000.00	20616.00	23500.00
SHER100-308		MIDPOINT - SIGNAL CONST PACKA	03/21/19	1.00	23800.00	30952.50	28350.00
		WEIGHTED AVERAGE FOR THE FIRST QUARTER		3.00	23600.00	30154.67	27950.00
		WEIGHTED AVERAGE FOR THE YEAR		3.00	23600.00	30154.67	27950.00
===== 614-81175		Sig-Light Pole Steel (1-75 Ft)		Each	=====		
SHER100-284		FY19 NORTH SIGNAL PKG	02/21/19	4.00	30000.00	33120.67	35000.00
SHE2254-090		Colfax & I-225, Colfax & Cham	03/07/19	2.00	29000.00	20871.00	24000.00
SHER100-308		MIDPOINT - SIGNAL CONST PACKA	03/21/19	1.00	24500.00	31252.50	28555.00
		WEIGHTED AVERAGE FOR THE FIRST QUARTER		7.00	28928.57	30190.94	30936.43
		WEIGHTED AVERAGE FOR THE YEAR		7.00	28928.57	30190.94	30936.43
===== 614-81525		Sig-Light Pole Steel (2-25&50 Ft)		Each	=====		
STM0242-077		US24 - 8TH ST TO WEST OF MANI	03/28/19	1.00	32000.00	32100.00	30000.00
		WEIGHTED AVERAGE FOR THE FIRST QUARTER		1.00	32000.00	32100.00	30000.00
		WEIGHTED AVERAGE FOR THE YEAR		1.00	32000.00	32100.00	30000.00
===== 614-81535		Sig-Light Pole Steel (2-35&40 Ft)		Each	=====		
FSA0252-468		I-25 AND PLUM CREEK IMPROVEME	04/18/19	1.00	23000.00	34461.25	30138.00
		WEIGHTED AVERAGE FOR THE SECOND QUARTER		1.00	23000.00	34461.25	30138.00
		WEIGHTED AVERAGE FOR THE YEAR		1.00	23000.00	34461.25	30138.00
===== 614-84000		Traf Sig Ped Pole Steel		Each	=====		
NHPPR500-173		US 160_550 DURANGO SIGNALS OP	01/03/19	1.00	3000.00	4146.50	4093.00
ITSSW01-638		ETHERNET PHASE III (PRIMARYLY	02/07/19	4.00	2500.00	2000.00	1500.00

COLORADO DEPARTMENT OF TRANSPORTATION
 ITEM UNIT COSTS BY PROJECTS -- 2019 COST DATA

13:44 Wednesday, August 7, 2019 279

PROJECT NUMBER	ITEM NUMBER/ PROJECT LOCATION	ITEM DESCRIPTION/ PROJECT LOCATION	DATE LET	UNIT/ QUANTITY	ENGR. EST.	AVERAGE BID	AWARDED BID
===== 614-84000 Traf Sig Ped Pole Steel Each =====							
SHER100-284		FY19 NORTH SIGNAL PKG	02/21/19	1.00	1500.00	2641.33	2645.00
SHE2254-090		Colfax & I-225, Colfax & Cham	03/07/19	4.00	200.00	2431.00	1500.00
SHER100-308		MIDPOINT - SIGNAL CONST PACKA	03/21/19	6.00	2100.00	2550.00	2025.00
STM0242-077		US24 - 8TH ST TO WEST OF MANI	03/28/19	2.00	3100.00	3200.00	3000.00
	WEIGHTED AVERAGE FOR THE FIRST QUARTER			18.00	1894.44	2601.67	2049.33
===== 614-84100 Traf Sig Ped Pole Alum Each =====							
FSA0252-468		I-25 AND PLUM CREEK IMPROVEME	04/18/19	2.00	2500.00	3219.50	2868.00
IM0252-456		I-25 COLORADO SPRINGS RAMP ME	05/16/19	17.00	1800.00	2430.00	2775.00
SHE0701-243		I-70 EXIT 26 DDI MODIFICATION	05/16/19	1.00	2400.00	4376.25	4050.00
	WEIGHTED AVERAGE FOR THE SECOND QUARTER			20.00	1900.00	2653.83	2848.05
	WEIGHTED AVERAGE FOR THE YEAR			38.00	1897.37	2633.88	2469.71
===== 614-85001 Impact Atten Each =====							
STAM086-075		SH96A ABRIENDO - ORMAN SAFETY	01/31/19	14.00	2000.00	1825.83	1625.00
SHE 0252-481		I-25 RAMP METER INSTALLATION	03/21/19	32.00	1500.00	1899.00	1945.00
	WEIGHTED AVERAGE FOR THE FIRST QUARTER			46.00	1652.17	1876.73	1847.61
	WEIGHTED AVERAGE FOR THE YEAR			46.00	1652.17	1876.73	1847.61
===== 614-85001 Impact Atten Each =====							
ER119A-065		PR SH 119A BOULDER CANYON	01/03/19	1.00	30000.00	22201.12	16900.00
STA119A-069		SH 119: NEDERLAND - EAST					
NHPP0821-107		SH 82 GLENWOOD SPRINGS TO CA	02/07/19	3.00	30000.00	19842.50	13685.00
SHE2254-090		Colfax & I-225, Colfax & Cham	03/07/19	2.00	2000.00	29000.00	28000.00
	WEIGHTED AVERAGE FOR THE FIRST QUARTER			6.00	20666.67	22925.78	18992.50
FSA0703-454		EB I-70 AUX LANE WARD TO KIPL	05/16/19	1.00	25000.00	21123.88	24987.19
SHE0701-243		I-70 EXIT 26 DDI MODIFICATION	05/16/19	1.00	25000.00	17762.50	24000.00
	WEIGHTED AVERAGE FOR THE SECOND QUARTER			2.00	25000.00	19203.09	24493.60
	WEIGHTED AVERAGE FOR THE YEAR			8.00	21750.00	21883.43	20367.77

COLORADO DEPARTMENT OF TRANSPORTATION
ITEM UNIT COSTS BY PROJECTS -- 2019 COST DATA

13:44 Wednesday, August 7, 2019 280

PROJECT NUMBER	ITEM NUMBER/ PROJECT LOCATION	ITEM DESCRIPTION/ PROJECT LOCATION	DATE LET	UNIT/ QUANTITY	ENGR. EST.	AVERAGE BID	AWARDED BID
=====	614-85005	Impact Atten (Sand Barrel Array)		Each	=====	=====	=====
STA067A-038		SH 67 SEDALIA RESURFACING	01/31/19	1.00	5500.00	5342.24	5600.00
	WEIGHTED AVERAGE FOR THE FIRST QUARTER			1.00	5500.00	5342.24	5600.00
	WEIGHTED AVERAGE FOR THE YEAR			1.00	5500.00	5342.24	5600.00
=====	614-86006	Telemetry (Master)		Each	=====	=====	=====
NHPP0703-445		I-70 WESTBOUND PEAK PERIOD SH	04/25/19	8.00	3000.00	8209.68	8638.00
	WEIGHTED AVERAGE FOR THE SECOND QUARTER			8.00	3000.00	8209.68	8638.00
	WEIGHTED AVERAGE FOR THE YEAR			8.00	3000.00	8209.68	8638.00
=====	614-86007	Serial to IP Converter		Each	=====	=====	=====
ITSSW01-638		ETHERNET PHASE III (PRIMARYLY	02/07/19	6.00	1750.00	2000.00	1000.00
SHE 0252-481		I-25 RAMP METER INSTALLATION	03/21/19	16.00	1150.00	885.00	1095.00
	WEIGHTED AVERAGE FOR THE FIRST QUARTER			22.00	1313.64	1108.00	1069.09
	WEIGHTED AVERAGE FOR THE YEAR			22.00	1313.64	1108.00	1069.09
=====	614-86105	Telemetry (Field)		Each	=====	=====	=====
NHPPR500-173		US 160_550 DURANGO SIGNALS OP	01/03/19	9.00	7000.00	4805.00	3110.00
	WEIGHTED AVERAGE FOR THE FIRST QUARTER			9.00	7000.00	4805.00	3110.00
NHPP0703-445		I-70 WESTBOUND PEAK PERIOD SH	04/25/19	2.00	2500.00	10047.84	10596.00
	WEIGHTED AVERAGE FOR THE SECOND QUARTER			2.00	2500.00	10047.84	10596.00
	WEIGHTED AVERAGE FOR THE YEAR			11.00	6181.82	6115.71	4471.09
=====	614-86238	Ctrlrler (S-S) (F-A) (8)		Each	=====	=====	=====
SHE2254-090		Colfax & I-225, Colfax & Cham	03/07/19	2.00	7000.00	4839.00	5100.00
	WEIGHTED AVERAGE FOR THE FIRST QUARTER			2.00	7000.00	4839.00	5100.00
	WEIGHTED AVERAGE FOR THE YEAR			2.00	7000.00	4839.00	5100.00

COLORADO DEPARTMENT OF TRANSPORTATION
 ITEM UNIT COSTS BY PROJECTS -- 2019 COST DATA

13:44 Wednesday, August 7, 2019 281

PROJECT NUMBER	ITEM NUMBER/ PROJECT LOCATION	ITEM DESCRIPTION/ PROJECT LOCATION	DATE LET	UNIT/ QUANTITY	ENGR. EST.	AVERAGE BID	AWARDED BID
=====	614-86248	Traf Ctrler (Type 2070LC)		Each	=====	=====	=====
SHER100-289		INTERSECTIONS @ SH83 & LONGS	01/03/19	1.00	10000.00	7752.00	7400.00
SHER100-284		FY19 NORTH SIGNAL PKG	02/21/19	3.00	7000.00	5698.67	7170.00
SHER100-308		MIDPOINT - SIGNAL CONST PACKA	03/21/19	3.00	5100.00	6137.50	5925.00
		WEIGHTED AVERAGE FOR THE FIRST QUARTER		7.00	6614.29	6343.65	6669.29
		WEIGHTED AVERAGE FOR THE YEAR		7.00	6614.29	6343.65	6669.29
=====	614-86250	Ctrler (Ramp Metering)		Each	=====	=====	=====
SHE 0252-481		I-25 RAMP METER INSTALLATION	03/21/19	16.00	2300.00	1588.33	1615.00
		WEIGHTED AVERAGE FOR THE FIRST QUARTER		16.00	2300.00	1588.33	1615.00
IM0252-456		I-25 COLORADO SPRINGS RAMP ME	05/16/19	12.00	15000.00	12225.67	12000.00
		WEIGHTED AVERAGE FOR THE SECOND QUARTER		12.00	15000.00	12225.67	12000.00
		WEIGHTED AVERAGE FOR THE YEAR		28.00	7742.86	6147.19	6065.71
=====	614-86734	WIM Station (Ty III)		Each	=====	=====	=====
NHPP0703-445		I-70 WESTBOUND PEAK PERIOD SH	04/25/19	1.00	50000.00	139752.78	148475.00
		WEIGHTED AVERAGE FOR THE SECOND QUARTER		1.00	50000.00	139752.78	148475.00
		WEIGHTED AVERAGE FOR THE YEAR		1.00	50000.00	139752.78	148475.00
=====	614-86748	Ctrler (Ty 2070)		Each	=====	=====	=====
FSA2873-190		US 287 AND FOOTHILLS PARKWAY	05/02/19	1.00	5000.00	5485.00	5600.00
		WEIGHTED AVERAGE FOR THE SECOND QUARTER		1.00	5000.00	5485.00	5600.00
		WEIGHTED AVERAGE FOR THE YEAR		1.00	5000.00	5485.00	5600.00
=====	614-86754	Maint of ITS Equip		LUMP SUM	=====	=====	=====
NHPP0703-445		I-70 WESTBOUND PEAK PERIOD SH	04/25/19	1.00	125000.00	1374479.40	1382413.00
		WEIGHTED AVERAGE FOR THE SECOND QUARTER		1.00	125000.00	1374479.40	1382413.00
		WEIGHTED AVERAGE FOR THE YEAR		1.00	125000.00	1374479.40	1382413.00

COLORADO DEPARTMENT OF TRANSPORTATION
 ITEM UNIT COSTS BY PROJECTS -- 2019 COST DATA

13:44 Wednesday, August 7, 2019 282

PROJECT NUMBER	ITEM NUMBER/ PROJECT LOCATION	ITEM DESCRIPTION/ PROJECT LOCATION	DATE LET	UNIT/ QUANTITY	ENGR. EST.	AVERAGE BID	AWARDED BID
===== 614-86800		Uninterrupted Power Supply		Each			
SHER100-289		INTERSECTIONS @ SH83 & LONGS	01/03/19	1.00	10000.00	9641.20	9200.00
SHER100-284		FY19 NORTH SIGNAL PKG	02/21/19	3.00	10000.00	6728.00	7400.00
SHE2254-090		Colfax & I-225, Colfax & Cham	03/07/19	3.00	8000.00	8952.00	9500.00
SHER100-308		MIDPOINT - SIGNAL CONST PACKA	03/21/19	3.00	9900.00	7072.50	7525.00
STM0242-077		US24 - 8TH ST TO WEST OF MANI	03/28/19	1.00	11000.00	6333.33	6000.00
		WEIGHTED AVERAGE FOR THE FIRST QUARTER		11.00	9518.18	7720.86	8043.18
NHPP0703-445		I-70 WESTBOUND PEAK PERIOD SH	04/25/19	17.00	10000.00	17049.92	18042.00
		WEIGHTED AVERAGE FOR THE SECOND QUARTER		17.00	10000.00	17049.92	18042.00
		WEIGHTED AVERAGE FOR THE YEAR		28.00	9810.71	13668.14	14113.89
===== 614-86920		Mod Traf Sig Ctrler Cab		Each			
ITSSW01-638		ETHERNET PHASE III (PRIMARYLY	02/07/19	16.00	2500.00	3250.00	1500.00
		WEIGHTED AVERAGE FOR THE FIRST QUARTER		16.00	2500.00	3250.00	1500.00
		WEIGHTED AVERAGE FOR THE YEAR		16.00	2500.00	3250.00	1500.00
===== 614-87010		Fiber Optic Cable (S Mode) (12 Fiber)		Lin Foot			
NHPPR500-173		US 160_550 DURANGO SIGNALS OP	01/03/19	5,200.00	4.00	4.35	3.04
SHER100-289		INTERSECTIONS @ SH83 & LONGS	01/03/19	500.00	7.50	3.14	3.00
ITSSW01-638		ETHERNET PHASE III (PRIMARYLY	02/07/19	16,145.00	4.50	9.05	5.00
SHER100-284		FY19 NORTH SIGNAL PKG	02/21/19	75.00	8.00	36.67	13.00
SHE 0252-481		I-25 RAMP METER INSTALLATION	03/21/19	11,845.00	3.00	2.13	2.15
SHER100-308		MIDPOINT - SIGNAL CONST PACKA	03/21/19	480.00	10.00	5.38	7.25
		WEIGHTED AVERAGE FOR THE FIRST QUARTER		34,245.00	4.03	5.30	3.74
NHPP0703-445		I-70 WESTBOUND PEAK PERIOD SH	04/25/19	18,450.00	7.00	22.17	23.00
IM0252-456		I-25 COLORADO SPRINGS RAMP ME	05/16/19	9,245.00	5.00	4.70	3.60
		WEIGHTED AVERAGE FOR THE SECOND QUARTER		27,695.00	6.33	16.34	16.52
		WEIGHTED AVERAGE FOR THE YEAR		61,940.00	5.06	10.86	9.45

COLORADO DEPARTMENT OF TRANSPORTATION
 ITEM UNIT COSTS BY PROJECTS -- 2019 COST DATA

13:44 Wednesday, August 7, 2019 283

PROJECT NUMBER	ITEM NUMBER/ PROJECT LOCATION	ITEM DESCRIPTION/ PROJECT LOCATION	DATE LET	UNIT/ QUANTITY	ENGR. EST.	AVERAGE BID	AWARDED BID
===== 614-87012		Fiber Optic Term Panel (12 Fiber)		Each =====			
SHER100-289		INTERSECTIONS @ SH83 & LONGS	01/03/19	1.00	1000.00	904.60	860.00
SHER100-284		FY19 NORTH SIGNAL PKG	02/21/19	3.00	3000.00	1514.33	645.00
SHE 0252-481		I-25 RAMP METER INSTALLATION	03/21/19	12.00	1250.00	1314.00	1330.00
SHER100-308		MIDPOINT - SIGNAL CONST PACKA	03/21/19	3.00	575.00	1092.50	655.00
		WEIGHTED AVERAGE FOR THE FIRST QUARTER		19.00	1406.58	1285.91	1090.53
NHPP0703-445		I-70 WESTBOUND PEAK PERIOD SH	04/25/19	15.00	600.00	501.23	528.00
		WEIGHTED AVERAGE FOR THE SECOND QUARTER		15.00	600.00	501.23	528.00
		WEIGHTED AVERAGE FOR THE YEAR		34.00	1050.74	936.30	842.35
===== 614-87015		Buffer Tube Fan Out Kit		Each =====			
NHPPR500-173		US 160_550 DURANGO SIGNALS OP	01/03/19	3.00	600.00	1125.00	250.00
SHER100-289		INTERSECTIONS @ SH83 & LONGS	01/03/19	1.00	650.00	343.40	325.00
ITSSW01-638		ETHERNET PHASE III (PRIMARYLY	02/07/19	18.00	400.00	151.50	200.00
SHER100-284		FY19 NORTH SIGNAL PKG	02/21/19	3.00	1000.00	710.00	80.00
SHE 0252-481		I-25 RAMP METER INSTALLATION	03/21/19	12.00	230.00	70.33	80.00
SHER100-308		MIDPOINT - SIGNAL CONST PACKA	03/21/19	3.00	500.00	179.00	78.00
		WEIGHTED AVERAGE FOR THE FIRST QUARTER		40.00	422.75	244.05	152.73
NHPP0703-445		I-70 WESTBOUND PEAK PERIOD SH	04/25/19	22.00	1200.00	528.60	557.00
		WEIGHTED AVERAGE FOR THE SECOND QUARTER		22.00	1200.00	528.60	557.00
		WEIGHTED AVERAGE FOR THE YEAR		62.00	698.55	358.57	296.18
===== 614-87024		Fiber Optic Term Panel (24 Fiber)		Each =====			
NHPPR500-173		US 160_550 DURANGO SIGNALS OP	01/03/19	3.00	1000.00	2109.50	1419.00
ITSSW01-638		ETHERNET PHASE III (PRIMARYLY	02/07/19	13.00	1250.00	1151.00	1800.00
		WEIGHTED AVERAGE FOR THE FIRST QUARTER		16.00	1203.13	1330.72	1728.56
		WEIGHTED AVERAGE FOR THE YEAR		16.00	1203.13	1330.72	1728.56

COLORADO DEPARTMENT OF TRANSPORTATION
ITEM UNIT COSTS BY PROJECTS -- 2019 COST DATA

13:44 Wednesday, August 7, 2019 284

PROJECT NUMBER	ITEM NUMBER/ PROJECT LOCATION	ITEM DESCRIPTION/ PROJECT LOCATION	DATE LET	UNIT/ QUANTITY	ENGR. EST.	AVERAGE BID	AWARDED BID
===== 614-87100		Auto Traf Rec Sta		Each	=====	=====	=====
NHPP0703-445		I-70 WESTBOUND PEAK PERIOD SH	04/25/19	1.00	12000.00	28800.17	30490.00
	WEIGHTED	AVERAGE FOR THE SECOND QUARTER		1.00	12000.00	28800.17	30490.00
		WEIGHTED AVERAGE FOR THE YEAR		1.00	12000.00	28800.17	30490.00
===== 614-87320		CCTV		Each	=====	=====	=====
ITSSW01-638		ETHERNET PHASE III (PRIMARYLY	02/07/19	33.00	3500.00	4910.00	5500.00
SHER100-284		FY19 NORTH SIGNAL PKG	02/21/19	3.00	2500.00	4504.00	4670.00
SHER100-308		MIDPOINT - SIGNAL CONST PACKA	03/21/19	3.00	5000.00	4900.00	4400.00
	WEIGHTED	AVERAGE FOR THE FIRST QUARTER		39.00	3538.46	4864.15	5351.54
NHPP0703-445		I-70 WESTBOUND PEAK PERIOD SH	04/25/19	4.00	5000.00	6536.06	6882.36
	WEIGHTED	AVERAGE FOR THE SECOND QUARTER		4.00	5000.00	6536.06	6882.36
		WEIGHTED AVERAGE FOR THE YEAR		43.00	3674.42	5079.88	5493.94
===== 614-87321		CCTV (Inst)		Each	=====	=====	=====
ITSSW01-638		ETHERNET PHASE III (PRIMARYLY	02/07/19	3.00	500.00	1379.50	1500.00
	WEIGHTED	AVERAGE FOR THE FIRST QUARTER		3.00	500.00	1379.50	1500.00
		WEIGHTED AVERAGE FOR THE YEAR		3.00	500.00	1379.50	1500.00
===== 614-87333		CCTV Camera (Traf Surveil)		Each	=====	=====	=====
NHPPR500-173		US 160_550 DURANGO SIGNALS OP	01/03/19	3.00	7000.00	12440.00	17380.00
	WEIGHTED	AVERAGE FOR THE FIRST QUARTER		3.00	7000.00	12440.00	17380.00
		WEIGHTED AVERAGE FOR THE YEAR		3.00	7000.00	12440.00	17380.00
===== 614-87350		Test Fiber Optic Cable		LUMP SUM	=====	=====	=====
NHPPR500-173		US 160_550 DURANGO SIGNALS OP	01/03/19	1.00	5000.00	7428.50	1857.00

COLORADO DEPARTMENT OF TRANSPORTATION
 ITEM UNIT COSTS BY PROJECTS -- 2019 COST DATA

13:44 Wednesday, August 7, 2019 285

PROJECT NUMBER	ITEM NUMBER/ PROJECT LOCATION	ITEM DESCRIPTION/ PROJECT LOCATION	DATE LET	UNIT/ QUANTITY	ENGR. EST.	AVERAGE BID	AWARDED BID
=====	614-87350	Test Fiber Optic Cable		LUMP SUM	=====	=====	=====
SHER100-289		INTERSECTIONS @ SH83 & LONGS	01/03/19	1.00	10000.00	1517.00	1440.00
ITSSW01-638		ETHERNET PHASE III (PRIMARYLY	02/07/19	1.00	15000.00	23817.50	20000.00
SHER100-284		FY19 NORTH SIGNAL PKG	02/21/19	1.00	5000.00	9348.00	4700.00
SHE 0252-481		I-25 RAMP METER INSTALLATION	03/21/19	1.00	6000.00	6388.33	8265.00
SHER100-308		MIDPOINT - SIGNAL CONST PACKA	03/21/19	1.00	6000.00	6015.00	4100.00
		WEIGHTED AVERAGE FOR THE FIRST QUARTER		6.00	7833.33	7606.82	6727.00
NHPP0703-445		I-70 WESTBOUND PEAK PERIOD SH	04/25/19	1.00	75000.00	167098.51	176212.00
IM0252-456		I-25 COLORADO SPRINGS RAMP ME	05/16/19	1.00	40000.00	9564.00	12100.00
		WEIGHTED AVERAGE FOR THE SECOND QUARTER		2.00	57500.00	88331.26	94156.00
		WEIGHTED AVERAGE FOR THE YEAR		8.00	20250.00	28665.37	28584.25
=====	614-87364	CCTV Pole w Low Dev (50 Ft)		Each	=====	=====	=====
ITSSW01-638		ETHERNET PHASE III (PRIMARYLY	02/07/19	5.00	23000.00	22363.00	20000.00
		WEIGHTED AVERAGE FOR THE FIRST QUARTER		5.00	23000.00	22363.00	20000.00
NHPP0703-445		I-70 WESTBOUND PEAK PERIOD SH	04/25/19	1.00	22000.00	41203.39	43430.00
		WEIGHTED AVERAGE FOR THE SECOND QUARTER		1.00	22000.00	41203.39	43430.00
		WEIGHTED AVERAGE FOR THE YEAR		6.00	22833.33	26710.78	23905.00
=====	614-87366	CCTV Pole w Low Dev (60 Ft)		Each	=====	=====	=====
ITSSW01-638		ETHERNET PHASE III (PRIMARYLY	02/07/19	2.00	26000.00	28312.00	25000.00
		WEIGHTED AVERAGE FOR THE FIRST QUARTER		2.00	26000.00	28312.00	25000.00
		WEIGHTED AVERAGE FOR THE YEAR		2.00	26000.00	28312.00	25000.00
=====	614-87368	CCTV Pole w Low Dev (70 Ft)		Each	=====	=====	=====
ITSSW01-638		ETHERNET PHASE III (PRIMARYLY	02/07/19	5.00	30000.00	35035.00	30000.00
		WEIGHTED AVERAGE FOR THE FIRST QUARTER		5.00	30000.00	35035.00	30000.00
		WEIGHTED AVERAGE FOR THE YEAR		5.00	30000.00	35035.00	30000.00

COLORADO DEPARTMENT OF TRANSPORTATION
 ITEM UNIT COSTS BY PROJECTS -- 2019 COST DATA

13:44 Wednesday, August 7, 2019 286

PROJECT NUMBER	ITEM NUMBER/ PROJECT LOCATION	ITEM DESCRIPTION/ PROJECT LOCATION	DATE LET	UNIT/ QUANTITY	ENGR. EST.	AVERAGE BID	AWARDED BID
===== 614-87400		Brkaway Taper ITS Pole Steel (30 Ft)		Each			
IM0252-456		I-25 COLORADO SPRINGS RAMP ME	05/16/19	11.00	8000.00	5866.67	5100.00
	WEIGHTED AVERAGE FOR THE SECOND QUARTER			11.00	8000.00	5866.67	5100.00
	WEIGHTED AVERAGE FOR THE YEAR			11.00	8000.00	5866.67	5100.00
===== 614-87402		Brkaway Taper ITS Pole Steel (40 Ft)		Each			
ITSSW01-638		ETHERNET PHASE III (PRIMARYLY	02/07/19	6.00	6500.00	9000.00	12500.00
	WEIGHTED AVERAGE FOR THE FIRST QUARTER			6.00	6500.00	9000.00	12500.00
NHPP0703-445		I-70 WESTBOUND PEAK PERIOD SH	04/25/19	3.00	4500.00	6034.13	6366.00
	WEIGHTED AVERAGE FOR THE SECOND QUARTER			3.00	4500.00	6034.13	6366.00
	WEIGHTED AVERAGE FOR THE YEAR			9.00	5833.33	7728.91	10455.33
===== 614-87412		Fiber Optic Cable (S Mode) (12 S) (Inst)		Lin Foot			
STM0242-077		US24 - 8TH ST TO WEST OF MANI	03/28/19	25.00	5.00	18.00	20.00
	WEIGHTED AVERAGE FOR THE FIRST QUARTER			25.00	5.00	18.00	20.00
	WEIGHTED AVERAGE FOR THE YEAR			25.00	5.00	18.00	20.00
===== 614-87501		Splice FO Cable (1 S)		Each			
ITSSW01-638		ETHERNET PHASE III (PRIMARYLY	02/07/19	100.00	120.00	272.50	500.00
	WEIGHTED AVERAGE FOR THE FIRST QUARTER			100.00	120.00	272.50	500.00
	WEIGHTED AVERAGE FOR THE YEAR			100.00	120.00	272.50	500.00
===== 614-87512		Splice FO Cable (12 S)		Each			
SHER100-289		INTERSECTIONS @ SH83 & LONGS	01/03/19	1.00	1650.00	1656.00	1575.00

COLORADO DEPARTMENT OF TRANSPORTATION
 ITEM UNIT COSTS BY PROJECTS -- 2019 COST DATA

13:44 Wednesday, August 7, 2019 287

PROJECT NUMBER	ITEM NUMBER/ PROJECT LOCATION	ITEM DESCRIPTION/ PROJECT LOCATION	DATE LET	UNIT/ QUANTITY	ENGR. EST.	AVERAGE BID	AWARDED BID
=====	614-87512	Splice FO Cable (12 S)		Each =====			
SHER100-284		FY19 NORTH SIGNAL PKG	02/21/19	3.00	1650.00	1187.00	2600.00
SHER100-308		MIDPOINT - SIGNAL CONST PACKA	03/21/19	3.00	125.00	2000.00	2100.00
	WEIGHTED AVERAGE FOR THE FIRST QUARTER			7.00	996.43	1548.15	2239.29
	WEIGHTED AVERAGE FOR THE YEAR			7.00	996.43	1548.15	2239.29
=====	614-87650	Fiber Optic Cable (S Mode) (216 S)		Lin Foot =====			
NHPP0703-445		I-70 WESTBOUND PEAK PERIOD SH	04/25/19	58,660.00	4.00	8.83	9.00
	WEIGHTED AVERAGE FOR THE SECOND QUARTER			58,660.00	4.00	8.83	9.00
	WEIGHTED AVERAGE FOR THE YEAR			58,660.00	4.00	8.83	9.00
=====	614-87691	Ethernet Switch Type I		Each =====			
ITSSW01-638		ETHERNET PHASE III (PRIMARYLY	02/07/19	25.00	3500.00	3515.00	3000.00
	WEIGHTED AVERAGE FOR THE FIRST QUARTER			25.00	3500.00	3515.00	3000.00
	WEIGHTED AVERAGE FOR THE YEAR			25.00	3500.00	3515.00	3000.00
=====	614-87692	Ethernet Switch Type II		Each =====			
SHER100-289		INTERSECTIONS @ SH83 & LONGS	01/03/19	1.00	5000.00	5282.00	5035.00
ITSSW01-638		ETHERNET PHASE III (PRIMARYLY	02/07/19	22.00	3800.00	3221.50	3000.00
SHER100-284		FY19 NORTH SIGNAL PKG	02/21/19	3.00	5000.00	4193.33	4200.00
SHE 0252-481		I-25 RAMP METER INSTALLATION	03/21/19	12.00	3500.00	3047.33	2865.00
SHER100-308		MIDPOINT - SIGNAL CONST PACKA	03/21/19	3.00	3580.00	3912.50	4025.00
	WEIGHTED AVERAGE FOR THE FIRST QUARTER			41.00	3813.17	3390.75	3172.93
NHPP0703-445		I-70 WESTBOUND PEAK PERIOD SH	04/25/19	14.00	5000.00	4854.45	5114.00
IM0252-456		I-25 COLORADO SPRINGS RAMP ME	05/16/19	12.00	4500.00	3656.67	3702.00
	WEIGHTED AVERAGE FOR THE SECOND QUARTER			26.00	4769.23	4301.63	4462.31
	WEIGHTED AVERAGE FOR THE YEAR			67.00	4184.18	3789.90	3673.28

COLORADO DEPARTMENT OF TRANSPORTATION
 ITEM UNIT COSTS BY PROJECTS -- 2019 COST DATA

13:44 Wednesday, August 7, 2019 288

PROJECT NUMBER	ITEM NUMBER/ PROJECT LOCATION	ITEM DESCRIPTION/ PROJECT LOCATION	DATE LET	UNIT/ QUANTITY	ENGR. EST.	AVERAGE BID	AWARDED BID
===== 614-87698		Ethernet Agg Switch Type II		Each			
NHPP0703-445		I-70 WESTBOUND PEAK PERIOD SH	04/25/19	2.00	25000.00	55411.62	58636.00
	WEIGHTED	AVERAGE FOR THE SECOND QUARTER		2.00	25000.00	55411.62	58636.00
		WEIGHTED AVERAGE FOR THE YEAR		2.00	25000.00	55411.62	58636.00
===== 615-00030		Emb Prot Ty 3		Each			
NHPP006A-058		US 6 LOVELAND PASS - I-70 (FY	03/07/19	1.00	3000.00	5121.50	5442.99
	WEIGHTED	AVERAGE FOR THE FIRST QUARTER		1.00	3000.00	5121.50	5442.99
		WEIGHTED AVERAGE FOR THE YEAR		1.00	3000.00	5121.50	5442.99
===== 615-00050		Emb Prot Ty 5		Each			
ER119A-065		PR SH 119A BOULDER CANYON	01/03/19	3.00	2000.00	6419.86	4400.00
STA119A-069		SH 119: NEDERLAND - EAST					
FBR0341-087		US 34 OVER NORTH FORK CO RIVE	01/10/19	4.00	3200.00	1427.46	3017.47
ER072A-040		PR SH72A FLOOD PERMANENT REPA	01/31/19	1.00	4000.00	4694.39	2700.00
NHPP072A-041		PR SH72A FLOOD PERMANENT REPA					
SHER100-308		MIDPOINT - SIGNAL CONST PACKA	03/21/19	1.00	3000.00	8350.00	13000.00
	WEIGHTED	AVERAGE FOR THE FIRST QUARTER		9.00	2866.67	4215.62	4552.21
BR071A-020		REPLACEMENT OF STRUCTURE L-22	04/18/19	2.00	3000.00	3410.00	1580.00
	WEIGHTED	AVERAGE FOR THE SECOND QUARTER		2.00	3000.00	3410.00	1580.00
		WEIGHTED AVERAGE FOR THE YEAR		11.00	2890.91	4144.53	4011.81
===== 615-00150		Emb Prot (Spec)		Each			
STM0242-077		US24 - 8TH ST TO WEST OF MANI	03/28/19	1.00	1850.00	1483.33	2000.00
	WEIGHTED	AVERAGE FOR THE FIRST QUARTER		1.00	1850.00	1483.33	2000.00
NHPP0703-445		I-70 WESTBOUND PEAK PERIOD SH	04/25/19	2.00	1600.00	4408.02	7119.00
	WEIGHTED	AVERAGE FOR THE SECOND QUARTER		2.00	1600.00	4408.02	7119.00
		WEIGHTED AVERAGE FOR THE YEAR		3.00	1683.33	3433.13	5412.67

COLORADO DEPARTMENT OF TRANSPORTATION
 ITEM UNIT COSTS BY PROJECTS -- 2019 COST DATA

13:44 Wednesday, August 7, 2019 289

PROJECT NUMBER	ITEM NUMBER/ PROJECT LOCATION	ITEM DESCRIPTION/ PROJECT LOCATION	DATE LET	UNIT/ QUANTITY	ENGR. EST.	AVERAGE BID	AWARDED BID
=====	618-00142	Prestress Conc I (BT42)		Lin Foot	=====		
FBR0253-247		I25 AT VINE DRIVE BRIDGE REPL	03/07/19	2,307.00	255.00	247.87	228.00
	WEIGHTED AVERAGE FOR THE FIRST QUARTER			2,307.00	255.00	247.87	228.00
	WEIGHTED AVERAGE FOR THE YEAR			2,307.00	255.00	247.87	228.00
=====	618-00154	Prestress Conc I (BT54)		Lin Foot	=====		
FBR0341-087		US 34 OVER NORTH FORK CO RIVE	01/10/19	818.00	350.00	371.38	414.74
	WEIGHTED AVERAGE FOR THE FIRST QUARTER			818.00	350.00	371.38	414.74
	WEIGHTED AVERAGE FOR THE YEAR			818.00	350.00	371.38	414.74
=====	618-01992	Prestress Conc Box (Depth Less Than 32")		Sq Foot	=====		
NHPP070A-028		FALL RIVER ROAD BRIDGE	02/21/19	2,381.00	100.00	85.74	76.00
	WEIGHTED AVERAGE FOR THE FIRST QUARTER			2,381.00	100.00	85.74	76.00
BR071A-020		REPLACEMENT OF STRUCTURE L-22	04/18/19	2,975.00	60.00	74.33	75.00
	WEIGHTED AVERAGE FOR THE SECOND QUARTER			2,975.00	60.00	74.33	75.00
	WEIGHTED AVERAGE FOR THE YEAR			5,356.00	77.78	80.85	75.44
=====	618-06034	Prestress Conc Slab (Depth 6" Thru 13")		Sq Foot	=====		
FBR0341-087		US 34 OVER NORTH FORK CO RIVE	01/10/19	5,216.00	50.00	108.25	93.29
	WEIGHTED AVERAGE FOR THE FIRST QUARTER			5,216.00	50.00	108.25	93.29
	WEIGHTED AVERAGE FOR THE YEAR			5,216.00	50.00	108.25	93.29
=====	619-00005	Water Line		LUMP SUM	=====		
STR0241-062		US 24 143.4 - 148	01/24/19	1.00	5000.00	18566.67	30000.00
	WEIGHTED AVERAGE FOR THE FIRST QUARTER			1.00	5000.00	18566.67	30000.00
	WEIGHTED AVERAGE FOR THE YEAR			1.00	5000.00	18566.67	30000.00

COLORADO DEPARTMENT OF TRANSPORTATION
ITEM UNIT COSTS BY PROJECTS -- 2019 COST DATA

13:44 Wednesday, August 7, 2019 290

PROJECT NUMBER	ITEM NUMBER/ PROJECT LOCATION	ITEM DESCRIPTION/ PROJECT LOCATION	DATE LET	UNIT/ QUANTITY	ENGR. EST.	AVERAGE BID	AWARDED BID
===== 619-06240		24 In Duct Iron Pipe		Lin Foot	=====		
NHPP1601-073		US 160 PASSING LANE NORTH OF	03/07/19	250.00	180.00	182.50	185.00
	WEIGHTED	AVERAGE FOR THE FIRST QUARTER		250.00	180.00	182.50	185.00
		WEIGHTED AVERAGE FOR THE YEAR		250.00	180.00	182.50	185.00
===== 619-06440		42 In Duct Iron Pipe (Restrained) (Furn)		Lin Foot	=====		
0253-277		I-25 EXPRESS LANES SEGMENT 5	06/10/19	2,960.00	578.00	585.99	585.99
	WEIGHTED	AVERAGE FOR THE SECOND QUARTER		2,960.00	578.00	585.99	585.99
		WEIGHTED AVERAGE FOR THE YEAR		2,960.00	578.00	585.99	585.99
===== 619-06450		42 In Duct Iron Pipe (NonRestrained) (Furn)		Lin Foot	=====		
0253-277		I-25 EXPRESS LANES SEGMENT 5	06/10/19	1,170.00	464.00	468.18	468.18
	WEIGHTED	AVERAGE FOR THE SECOND QUARTER		1,170.00	464.00	468.18	468.18
		WEIGHTED AVERAGE FOR THE YEAR		1,170.00	464.00	468.18	468.18
===== 619-10160		16 In Weld Steel Pipe		Lin Foot	=====		
NHPP0703-445		I-70 WESTBOUND PEAK PERIOD SH	04/25/19	348.00	300.00	616.14	365.00
	WEIGHTED	AVERAGE FOR THE SECOND QUARTER		348.00	300.00	616.14	365.00
		WEIGHTED AVERAGE FOR THE YEAR		348.00	300.00	616.14	365.00
===== 619-30320		4 In Galv Pipe		Lin Foot	=====		
ER119A-065 STA119A-069		PR SH 119A BOULDER CANYON SH 119: NEDERLAND - EAST	01/03/19	14.00	50.00	209.22	550.00
	WEIGHTED	AVERAGE FOR THE FIRST QUARTER		14.00	50.00	209.22	550.00
		WEIGHTED AVERAGE FOR THE YEAR		14.00	50.00	209.22	550.00

COLORADO DEPARTMENT OF TRANSPORTATION
 ITEM UNIT COSTS BY PROJECTS -- 2019 COST DATA

13:44 Wednesday, August 7, 2019 291

PROJECT NUMBER	ITEM NUMBER/ PROJECT LOCATION	ITEM DESCRIPTION/ PROJECT LOCATION	DATE LET	UNIT/ QUANTITY	ENGR. EST.	AVERAGE BID	AWARDED BID
=====	619-50100	1-1/4 In Plastic Pipe		Lin Foot	=====		
C0502-085		US 50 MM 201.8 MONARCH AVALAN	06/27/19	4,020.00	22.00	24.38	7.50
	WEIGHTED AVERAGE FOR THE SECOND QUARTER			4,020.00	22.00	24.38	7.50
	WEIGHTED AVERAGE FOR THE YEAR			4,020.00	22.00	24.38	7.50
=====	619-50640	8 In Plastic Pipe		Lin Foot	=====		
NHPP1601-073		US 160 PASSING LANE NORTH OF	03/07/19	285.00	97.00	52.00	49.00
	WEIGHTED AVERAGE FOR THE FIRST QUARTER			285.00	97.00	52.00	49.00
	WEIGHTED AVERAGE FOR THE YEAR			285.00	97.00	52.00	49.00
=====	619-51280	16 In Plastic Pipe		Lin Foot	=====		
NHPP1601-073		US 160 PASSING LANE NORTH OF	03/07/19	10,462.00	105.00	120.00	113.70
	WEIGHTED AVERAGE FOR THE FIRST QUARTER			10,462.00	105.00	120.00	113.70
	WEIGHTED AVERAGE FOR THE YEAR			10,462.00	105.00	120.00	113.70
=====	619-51290	18 In Plastic Pipe		Lin Foot	=====		
C0502-085		US 50 MM 201.8 MONARCH AVALAN	06/27/19	6.00	100.00	715.38	475.00
	WEIGHTED AVERAGE FOR THE SECOND QUARTER			6.00	100.00	715.38	475.00
	WEIGHTED AVERAGE FOR THE YEAR			6.00	100.00	715.38	475.00
=====	619-71000	Place Valve		Each	=====		
NHPP1601-073		US 160 PASSING LANE NORTH OF	03/07/19	5.00	7600.00	14718.00	15636.00
	WEIGHTED AVERAGE FOR THE FIRST QUARTER			5.00	7600.00	14718.00	15636.00
	WEIGHTED AVERAGE FOR THE YEAR			5.00	7600.00	14718.00	15636.00
=====	619-71516	2 In Air and Vacuum Valve		Each	=====		
NHPP1601-073		US 160 PASSING LANE NORTH OF	03/07/19	14.00	8500.00	4900.00	4800.00
	WEIGHTED AVERAGE FOR THE FIRST QUARTER			14.00	8500.00	4900.00	4800.00
	WEIGHTED AVERAGE FOR THE YEAR			14.00	8500.00	4900.00	4800.00

COLORADO DEPARTMENT OF TRANSPORTATION
 ITEM UNIT COSTS BY PROJECTS -- 2019 COST DATA

13:44 Wednesday, August 7, 2019 292

PROJECT NUMBER	ITEM NUMBER/ PROJECT LOCATION	ITEM DESCRIPTION/ PROJECT LOCATION	DATE LET	UNIT/ QUANTITY	ENGR. EST.	AVERAGE BID	AWARDED BID
=====	619-77210	Restrained Plug (Spec)		Each	=====	=====	=====
STR0241-062	US 24 143.4 - 148		01/24/19	1.00	1500.00	2730.00	4300.00
	WEIGHTED AVERAGE FOR THE FIRST QUARTER			1.00	1500.00	2730.00	4300.00
	WEIGHTED AVERAGE FOR THE YEAR			1.00	1500.00	2730.00	4300.00
=====	619-77400	Curb Stop and Box		Each	=====	=====	=====
STR0241-062	US 24 143.4 - 148		01/24/19	1.00	500.00	3116.67	3300.00
	WEIGHTED AVERAGE FOR THE FIRST QUARTER			1.00	500.00	3116.67	3300.00
	WEIGHTED AVERAGE FOR THE YEAR			1.00	500.00	3116.67	3300.00
=====	619-78042	5-1/4 In Fire Hydrant		Each	=====	=====	=====
STR0241-062	US 24 143.4 - 148		01/24/19	3.00	10750.00	13256.67	9800.00
	WEIGHTED AVERAGE FOR THE FIRST QUARTER			3.00	10750.00	13256.67	9800.00
	WEIGHTED AVERAGE FOR THE YEAR			3.00	10750.00	13256.67	9800.00
=====	620-00001	Field Office (CL 1)		Each	=====	=====	=====
NHPP1601-076	US 160 MANCOS HILL (MP 40.000		02/21/19	1.00	20000.00	26580.00	25000.00
	WEIGHTED AVERAGE FOR THE FIRST QUARTER			1.00	20000.00	26580.00	25000.00
IM0252-472	I-25 CABLE BARRIER PHASE III		04/04/19	1.00	15000.00	16750.00	20000.00
FSA0252-468	I-25 AND PLUM CREEK IMPROVEME		04/18/19	1.00	14000.00	14821.50	16161.00
MTCE0641-103	MTCE R3 FY20 SH 64 RANGELY PE		05/02/19	1.00	20000.00	15750.00	5000.00
FSA0703-454	EB I-70 AUX LANE WARD TO KIPL		05/16/19	1.00	15000.00	39000.00	40000.00
NHPP160A-030	US160 MM 43.2, 150.4, 156.3,		06/20/19	1.00	20000.00	17750.00	13000.00
	WEIGHTED AVERAGE FOR THE SECOND QUARTER			5.00	16800.00	21291.23	18832.20
	WEIGHTED AVERAGE FOR THE YEAR			6.00	17333.33	22282.88	19860.17

PROJECT NUMBER	ITEM NUMBER/ PROJECT LOCATION	ITEM DESCRIPTION/ PROJECT LOCATION	DATE LET	UNIT/ QUANTITY	ENGR. EST.	AVERAGE BID	AWARDED BID
===== 620-00002		Field Office (CL 2)		Each =====			
STAR200-242		R2 NORTH PROGRAM WALL REPAIRS	01/03/19	1.00	25000.00	26271.52	35380.00
IM0251-351		I-25 South of Pueblo MP 79.6	01/03/19	1.00	30000.00	19043.01	12768.72
STR0132-021		SH 13-MOFFAT COUNTY-CR 3 SOUT	01/10/19	1.00	36000.00	37976.00	37630.00
STR141A-047		SH 141 MP 120-143 MESA COUNTY	01/17/19	1.00	24000.00	23850.51	30000.00
NHPP0701-241		I-70 TRUCK PARKING GARFIELD C	01/17/19	1.00	30000.00	27203.94	19250.00
ER072A-040		PR SH72A FLOOD PERMANENT REPA	01/31/19	1.00	100000.00	37504.74	18000.00
NHPP072A-041		PR SH72A FLOOD PERMANENT REPA					
NH2871-035		US 287 PASSING LANES SOUTH OF	02/07/19	1.00	25000.00	29206.46	36750.00
NHPP145A-065		SH 145 PASSING LANES AT DEEP	02/14/19	1.00	40000.00	30740.19	35000.00
NHPP0741-022		SH 74: I-70 TO CR 65 RESURFAC	02/14/19	1.00	24705.00	42750.00	42000.00
NHPP070A-028		FALL RIVER ROAD BRIDGE	02/21/19	1.00	75000.00	22158.13	23800.00
NHPP1601-073		US 160 PASSING LANE NORTH OF	03/07/19	1.00	25000.00	25450.00	31900.00
FBR0253-247		I25 AT VINE DRIVE BRIDGE REPL	03/07/19	1.00	20000.00	28507.39	30000.00
NHPP006A-058		US 6 LOVELAND PASS - I-70 (FY	03/07/19	1.00	30000.00	19205.61	20411.21
NHPP0702-378		I-70 OFFICERS GULCH TO FRISCO	03/14/19	1.00	25000.00	28825.00	19475.00
NHPP050A-033		US50 West of Delta EB Lanes R	03/14/19	1.00	28000.00	25343.33	20030.00
NHPP0503-087		US 50 PASSING LANES EAST OF S	03/21/19	1.00	25000.00	23000.00	16000.00
STM0242-077		US24 - 8TH ST TO WEST OF MANI	03/28/19	1.00	22000.00	34166.67	17500.00
STA0131-070 HMA ALT		SH 13 CR 5 NORTH AND SOUTH	03/28/19	2.00	50000.00	68333.33	64250.00
STA0131-070 PCCP ALT		SH 13 CR 5 NORTH AND SOUTH					
		WEIGHTED AVERAGE FOR THE FIRST QUARTER		19.00	36037.11	32637.67	28341.38
NHPP030A-035		US 285/SH30	04/04/19	1.00	40000.00	55000.00	55000.00
BR071A-020		REPLACEMENT OF STRUCTURE L-22	04/18/19	1.00	10000.00	28267.00	1.00
SHE0701-243		I-70 EXIT 26 DDI MODIFICATION	05/16/19	1.00	25000.00	22250.00	20000.00
NHPP0703-442		I-70 SILVERPLUME SOUNDWALL AN	06/13/19	1.00	25000.00	30928.02	41400.00
C0502-085		US 50 MM 201.8 MONARCH AVALAN	06/27/19	1.00	18000.00	18850.00	16700.00
		WEIGHTED AVERAGE FOR THE SECOND QUARTER		5.00	23600.00	28551.40	26620.20
		WEIGHTED AVERAGE FOR THE YEAR		24.00	33446.04	31902.14	27967.21
===== 620-00005		Field Office (Spec)		Each =====			
ER119A-065		PR SH 119A BOULDER CANYON	01/03/19	1.00	37500.00	155004.52	165000.00
STA119A-069		SH 119: NEDERLAND - EAST					
FBR0341-087		US 34 OVER NORTH FORK CO RIVE	01/10/19	1.00	35000.00	35222.93	21396.30
STR0241-062		US 24 143.4 - 148	01/24/19	1.00	28000.00	27333.33	23000.00
STA067A-038		SH 67 SEDALIA RESURFACING	01/31/19	1.00	25000.00	14687.82	16000.00
NHPP0702-379		I-70 VAIL PASS VARIOUS WALL R	02/20/19	1.00	15900.00	15900.00	15900.00

COLORADO DEPARTMENT OF TRANSPORTATION
 ITEM UNIT COSTS BY PROJECTS -- 2019 COST DATA

13:44 Wednesday, August 7, 2019 294

PROJECT NUMBER	ITEM NUMBER/ PROJECT LOCATION	ITEM DESCRIPTION/ PROJECT LOCATION	DATE LET	UNIT/ QUANTITY	ENGR. EST.	AVERAGE BID	AWARDED BID
===== 620-00005		Field Office (Spec)		Each =====			
NHPP2254-089		I-225 RESURFACING FROM I-25 T	03/21/19	1.00	22000.00	45128.40	70000.00
	WEIGHTED AVERAGE FOR THE FIRST QUARTER			6.00	27233.33	72030.10	51882.72
NHPP0703-445		I-70 WESTBOUND PEAK PERIOD SH	04/25/19	1.00	50000.00	367603.00	252809.00
FBR0063-057		US-6 F-09-K BRIDGE OVER CASTL	05/30/19	1.00	20000.00	28500.00	27000.00
	WEIGHTED AVERAGE FOR THE SECOND QUARTER			2.00	35000.00	231961.80	139904.50
	WEIGHTED AVERAGE FOR THE YEAR			8.00	29175.00	99604.53	73888.16
===== 620-00011		Field Lab (CL 1)		Each =====			
IM0252-472		I-25 CABLE BARRIER PHASE III	04/04/19	1.00	15000.00	16500.00	20000.00
FBR0063-057		US-6 F-09-K BRIDGE OVER CASTL	05/30/19	1.00	20000.00	25000.00	30000.00
	WEIGHTED AVERAGE FOR THE SECOND QUARTER			2.00	17500.00	20750.00	25000.00
	WEIGHTED AVERAGE FOR THE YEAR			2.00	17500.00	20750.00	25000.00
===== 620-00012		Field Lab (CL 2)		Each =====			
IM0251-351		I-25 South of Pueblo MP 79.6	01/03/19	1.00	20000.00	16979.12	12553.49
ER119A-065		PR SH 119A BOULDER CANYON	01/03/19	1.00	30000.00	47355.04	85000.00
STA119A-069		SH 119: NEDERLAND - EAST					
STR0132-021		SH 13-MOFFAT COUNTY-CR 3 SOUT	01/10/19	1.00	34000.00	34752.00	30710.00
FBR0341-087		US 34 OVER NORTH FORK CO RIVE	01/10/19	1.00	23000.00	26929.48	20921.93
STR141A-047		SH 141 MP 120-143 MESA COUNTY	01/17/19	1.00	22000.00	21274.17	28000.00
NHPP0701-241		I-70 TRUCK PARKING GARFIELD C	01/17/19	1.00	25000.00	26109.63	17000.00
STR0241-062		US 24 143.4 - 148	01/24/19	1.00	26000.00	25666.67	23000.00
ER072A-040		PR SH72A FLOOD PERMANENT REPA	01/31/19	1.00	35000.00	26849.64	18000.00
NHPP072A-041		PR SH72A FLOOD PERMANENT REPA					
STA067A-038		SH 67 SEDALIA RESURFACING	01/31/19	1.00	25000.00	11132.65	9000.00
NH2871-035		US 287 PASSING LANES SOUTH OF	02/07/19	1.00	20000.00	16563.36	15750.00
NHPP145A-065		SH 145 PASSING LANES AT DEEP	02/14/19	1.00	40000.00	30266.29	33000.00
NHPP0741-022		SH 74: I-70 TO CR 65 RESURFAC	02/14/19	1.00	55000.00	29125.00	41500.00
NHPP070A-028		FALL RIVER ROAD BRIDGE	02/21/19	1.00	45000.00	15762.45	12600.00
NHPP1601-073		US 160 PASSING LANE NORTH OF	03/07/19	1.00	25000.00	29800.00	41600.00
FBR0253-247		I25 AT VINE DRIVE BRIDGE REPL	03/07/19	1.00	18000.00	19067.04	30000.00
NHPP006A-058		US 6 LOVELAND PASS - I-70 (FY	03/07/19	1.00	13000.00	15783.48	15566.95
NHPP0702-378		I-70 OFFICERS GULCH TO FRISCO	03/14/19	1.00	28000.00	25808.33	17425.00

PROJECT NUMBER	ITEM NUMBER/ PROJECT LOCATION	ITEM DESCRIPTION/ PROJECT LOCATION	DATE LET	UNIT/ QUANTITY	ENGR. EST.	AVERAGE BID	AWARDED BID
===== 620-00012							
		Field Lab (CL 2)		Each			
NHPP050A-033		US50 West of Delta EB Lanes R	03/14/19	1.00	24000.00	23000.00	18000.00
NHPP0503-087		US 50 PASSING LANES EAST OF S	03/21/19	1.00	20000.00	22000.00	14000.00
NHPP2254-089		I-225 RESURFACING FROM I-25 T	03/21/19	1.00	10000.00	33132.33	40000.00
STM0242-077		US24 - 8TH ST TO WEST OF MANI	03/28/19	1.00	18000.00	22000.00	11000.00
STA0131-070 HMA ALT		SH 13 CR 5 NORTH AND SOUTH	03/28/19	2.00	50000.00	62058.33	63050.00
STA0131-070 PCCP ALT		SH 13 CR 5 NORTH AND SOUTH					
WEIGHTED AVERAGE FOR THE FIRST QUARTER				23.00	28521.74	27886.46	27167.15
=====							
NHPP030A-035		US 285/SH30	04/04/19	1.00	20000.00	30000.00	30000.00
STRR300-236		SH 92 and SH 133	04/04/19	1.00	23000.00	15000.00	15000.00
BR071A-020		REPLACEMENT OF STRUCTURE L-22	04/18/19	1.00	10000.00	20033.67	1.00
NHPP0703-445		I-70 WESTBOUND PEAK PERIOD SH	04/25/19	1.00	200000.00	115230.68	55717.00
FSA0703-454		EB I-70 AUX LANE WARD TO KIPL	05/16/19	1.00	25000.00	21500.00	17500.00
WEIGHTED AVERAGE FOR THE SECOND QUARTER				5.00	55600.00	46844.82	23643.60
WEIGHTED AVERAGE FOR THE YEAR				28.00	33357.14	29715.78	26514.64
=====							
===== 620-00020							
		Sanitary Facility		Each			
STAR200-242		R2 NORTH PROGRAM WALL REPAIRS	01/03/19	2.00	2000.00	1238.39	1355.00
IM0251-351		I-25 South of Pueblo MP 79.6	01/03/19	1.00	2700.00	5090.85	5018.19
FSA0142-068		SH 14 & WCR 33 INTERSECTION I	01/03/19	1.00	1500.00	401.25	275.00
SHER100-289		INTERSECTIONS @ SH83 & LONGS	01/03/19	2.00	1500.00	969.00	650.00
ER119A-065		PR SH 119A BOULDER CANYON	01/03/19	3.00	1750.00	6244.50	5800.00
STA119A-069		SH 119: NEDERLAND - EAST					
STR0132-021		SH 13-MOFFAT COUNTY-CR 3 SOUT	01/10/19	2.00	2500.00	5413.26	3750.00
FBR0341-087		US 34 OVER NORTH FORK CO RIVE	01/10/19	1.00	1000.00	2260.24	3228.69
STR141A-047		SH 141 MP 120-143 MESA COUNTY	01/17/19	1.00	2000.00	8242.68	12500.00
NHPP0701-241		I-70 TRUCK PARKING GARFIELD C	01/17/19	1.00	2500.00	1845.69	1750.00
MTCER400-368		REGION 4 FY 19 STENCIL NW	01/17/19	2.00	1500.00	1625.00	500.00
STR0241-062		US 24 143.4 - 148	01/24/19	1.00	2500.00	7383.33	3500.00
NHPPR100-250		PACKAGE A (I-25 / I-70 / I-76	01/24/19	2.00	3000.00	1634.88	1200.00
ER072A-040		PR SH72A FLOOD PERMANENT REPA	01/31/19	2.00	3500.00	2798.10	1000.00
NHPP072A-041		PR SH72A FLOOD PERMANENT REPA					
STA067A-038		SH 67 SEDALIA RESURFACING	01/31/19	1.00	2500.00	1005.53	500.00
NHPP0821-107		SH 82 GLENWOOD SPRINGS TO CA	02/07/19	2.00	2000.00	1500.00	2500.00
NH2871-035		US 287 PASSING LANES SOUTH OF	02/07/19	1.00	3000.00	4401.29	5250.00
ITSSW01-638		ETHERNET PHASE III (PRIMARYLY	02/07/19	1.00	2000.00	500.00	500.00
NHPP145A-065		SH 145 PASSING LANES AT DEEP	02/14/19	2.00	4000.00	3468.74	2160.00
NHPP0741-022		SH 74: I-70 TO CR 65 RESURFAC	02/14/19	2.00	3500.00	1825.15	3550.00
NHPP0702-379		I-70 VAIL PASS VARIOUS WALL R	02/20/19	1.00	2500.00	2500.00	2500.00

PROJECT NUMBER	ITEM NUMBER/ PROJECT LOCATION	ITEM DESCRIPTION/ PROJECT LOCATION	DATE LET	UNIT/ QUANTITY	ENGR. EST.	AVERAGE BID	AWARDED BID
=====	620-00020	Sanitary Facility		Each =====			
NHPP1601-076		US 160 MANCOS HILL (MP 40.000	02/21/19	1.00	1700.00	3676.67	1500.00
NHPP070A-028		FALL RIVER ROAD BRIDGE	02/21/19	1.00	4000.00	2748.95	1100.00
SHER100-284		FY19 NORTH SIGNAL PKG	02/21/19	2.00	3000.00	879.33	500.00
NHPP1601-073		US 160 PASSING LANE NORTH OF	03/07/19	1.00	3000.00	4950.00	3900.00
FBR0253-247		I25 AT VINE DRIVE BRIDGE REPL	03/07/19	2.00	1500.00	2996.66	3000.00
NHPP006A-058		US 6 LOVELAND PASS - I-70 (FY	03/07/19	2.00	1500.00	5643.33	6286.65
C R100-315		R1 ADA CURB RAMPS - PH 5	03/07/19	3.00	1500.00	1625.00	1500.00
SHE2254-090		Colfax & I-225, Colfax & Cham	03/07/19	1.00	1500.00	2500.00	1500.00
NHPP0702-378		I-70 OFFICERS GULCH TO FRISCO	03/14/19	1.00	1500.00	6041.67	5125.00
NHPP050A-033		US50 West of Delta EB Lanes R	03/14/19	1.00	1800.00	5266.67	6600.00
NHPP0503-087		US 50 PASSING LANES EAST OF S	03/21/19	2.00	2500.00	2900.00	4000.00
SHE 0252-481		I-25 RAMP METER INSTALLATION	03/21/19	1.00	2500.00	2663.33	2915.00
SHER100-308		MIDPOINT - SIGNAL CONST PACKA	03/21/19	1.00	1900.00	1750.00	1700.00
NHPP2254-089		I-225 RESURFACING FROM I-25 T	03/21/19	1.00	2500.00	2258.81	4000.00
STM0242-077		US24 - 8TH ST TO WEST OF MANI	03/28/19	2.00	2300.00	1716.67	2750.00
STA0131-070 HMA ALT		SH 13 CR 5 NORTH AND SOUTH	03/28/19	4.00	3500.00	7797.26	9700.00
STA0131-070 PCCP ALT		SH 13 CR 5 NORTH AND SOUTH					
		WEIGHTED AVERAGE FOR THE FIRST QUARTER		57.00	2367.54	3441.43	3110.28
NHPP030A-035		US 285/SH30	04/04/19	1.00	2000.00	4075.19	4075.19
STRR300-236		SH 92 and SH 133	04/04/19	1.00	2000.00	750.00	750.00
IM0252-472		I-25 CABLE BARRIER PHASE III	04/04/19	2.00	1000.00	2250.00	2500.00
BR071A-020		REPLACEMENT OF STRUCTURE L-22	04/18/19	2.00	1500.00	1108.33	525.00
FSA0252-468		I-25 AND PLUM CREEK IMPROVEME	04/18/19	1.00	2250.00	1165.50	862.00
NHPP0703-445		I-70 WESTBOUND PEAK PERIOD SH	04/25/19	4.00	7500.00	5118.25	5339.00
NHPP2851-012		US 285 Antonito to Estrella C	05/02/19	1.00	2000.00	2500.00	1000.00
C2571-013		SH257 & 392:WINDSOR CURB RAMP	05/02/19	2.00	1500.00	1125.00	1000.00
MTCE0641-103		MTCE R3 FY20 SH 64 RANGELY PE	05/02/19	1.00	2500.00	4725.00	1500.00
FSA2873-190		US 287 AND FOOTHILLS PARKWAY	05/02/19	1.00	1000.00	875.00	980.00
FSA0061-090		SH 6: CENTER LINE RUMBLE STRI	05/02/19	1.00	3000.00	1500.00	1500.00
FSAR100-327		REGION 1 6 INCH LANE LINE MAR	05/09/19	2.00	2500.00	5000.00	5000.00
IM0252-456		I-25 COLORADO SPRINGS RAMP ME	05/16/19	1.00	1500.00	3680.00	2440.00
FSA0703-454		EB I-70 AUX LANE WARD TO KIPL	05/16/19	1.00	3500.00	2666.67	2500.00
CR300-248		CRAIG RESIDENCY ADA RAMPS	05/16/19	1.00	1800.00	3478.33	3500.00
SHE0701-243		I-70 EXIT 26 DDI MODIFICATION	05/16/19	1.00	1500.00	2106.25	5000.00
STMC430-020		ADA RAMPS DIVIDE ESB	05/23/19	1.00	2000.00	2500.00	2500.00
FBR0063-057		US-6 F-09-K BRIDGE OVER CASTL	05/30/19	1.00	2500.00	4537.50	7725.00
STRR200-257		ROAD CLOSURE GATES ON VARIOUS	05/30/19	4.00	1000.00	475.50	400.00
ER145A-081		SH 145 MP 21 EMERGENCY ROCKFA	06/07/19	1.00	3000.00	770.50	361.00
NHPP0703-442		I-70 SILVERPLUME SOUNDWALL AN	06/13/19	1.00	2000.00	1989.48	2550.00
NHPP030A-036		SH 30 & TOWER RD IMPROVEMENTS	06/13/19	1.00	3000.00	2200.00	2200.00
CR500-205		R5 GUARDRAIL END TREATMENT EA	06/13/19	1.00	3500.00	3035.00	3035.00
FSA0142-067		SH 14 RUMBLESTRIPS: AULT TO S	06/13/19	1.00	2000.00	1500.00	1500.00
STR 141A-040		R5 YEAR 4 BRDG PREV MAINT RAM	06/20/19	2.00	2500.00	2625.00	2000.00

COLORADO DEPARTMENT OF TRANSPORTATION
 ITEM UNIT COSTS BY PROJECTS -- 2019 COST DATA

13:44 Wednesday, August 7, 2019 297

PROJECT NUMBER	ITEM NUMBER/ PROJECT LOCATION	ITEM DESCRIPTION/ PROJECT LOCATION	DATE LET	UNIT/ QUANTITY	ENGR. EST.	AVERAGE BID	AWARDED BID
=====	620-00020	Sanitary Facility		Each			
NHPP160A-030		US160 MM 43.2, 150.4, 156.3	06/20/19	4.00	2500.00	1355.00	210.00
C0502-085		US 50 MM 201.8 MONARCH AVALAN	06/27/19	1.00	2500.00	2900.00	2000.00
	WEIGHTED AVERAGE FOR THE SECOND QUARTER			41.00	2574.39	2401.23	2239.61
	WEIGHTED AVERAGE FOR THE YEAR			98.00	2454.08	3141.07	2738.43
=====	621-00425	Detour		LUMP SUM			
ER119A-065		PR SH 119A BOULDER CANYON	01/03/19	1.00	90000.00	107804.46	85000.00
STA119A-069		SH 119: NEDERLAND - EAST					
	WEIGHTED AVERAGE FOR THE FIRST QUARTER			1.00	90000.00	107804.46	85000.00
ER145A-081		SH 145 MP 21 EMERGENCY ROCKFA	06/07/19	1.00	43000.00	36163.00	29244.00
	WEIGHTED AVERAGE FOR THE SECOND QUARTER			1.00	43000.00	36163.00	29244.00
	WEIGHTED AVERAGE FOR THE YEAR			2.00	66500.00	93476.17	57122.00
=====	621-00450	Detour Pvmt		Sq Yard			
ER119A-065		PR SH 119A BOULDER CANYON	01/03/19	500.00	100.00	70.24	55.00
STA119A-069		SH 119: NEDERLAND - EAST					
FBR0341-087		US 34 OVER NORTH FORK CO RIVE	01/10/19	1,653.00	120.00	60.27	65.42
ER072A-040		PR SH72A FLOOD PERMANENT REPA	01/31/19	1,370.00	125.00	86.74	45.00
NHPP072A-041		PR SH72A FLOOD PERMANENT REPA					
NHPP070A-028		FALL RIVER ROAD BRIDGE	02/21/19	107.00	110.00	96.92	100.00
NHPP050A-033		US50 West of Delta EB Lanes R	03/14/19	2,030.00	55.00	47.80	50.40
NHPP0503-087		US 50 PASSING LANES EAST OF S	03/21/19	200.00	65.00	73.00	56.00
	WEIGHTED AVERAGE FOR THE FIRST QUARTER			5,860.00	94.89	71.61	54.86
NHPP0703-445		I-70 WESTBOUND PEAK PERIOD SH	04/25/19	1,100.00	75.00	126.00	83.00
FBR0063-057		US-6 F-09-K BRIDGE OVER CASTL	05/30/19	2,800.00	80.00	59.00	43.00
	WEIGHTED AVERAGE FOR THE SECOND QUARTER			3,900.00	78.59	83.84	54.28
	WEIGHTED AVERAGE FOR THE YEAR			9,760.00	88.37	73.96	54.63

COLORADO DEPARTMENT OF TRANSPORTATION
ITEM UNIT COSTS BY PROJECTS -- 2019 COST DATA

13:44 Wednesday, August 7, 2019 298

PROJECT NUMBER	ITEM NUMBER/ PROJECT LOCATION	ITEM DESCRIPTION/ PROJECT LOCATION	DATE LET	UNIT/ QUANTITY	ENGR. EST.	AVERAGE BID	AWARDED BID
=====	621-00500	Temp Brdg		LUMP SUM	=====		
FBR0341-087		US 34 OVER NORTH FORK CO RIVE	01/10/19	1.00	420000.00	396404.28	302425.65
		WEIGHTED AVERAGE FOR THE FIRST QUARTER		1.00	420000.00	396404.28	302425.65
		WEIGHTED AVERAGE FOR THE YEAR		1.00	420000.00	396404.28	302425.65
=====	622-00270	Bollard		Each	=====		
ER119A-065 STA119A-069		PR SH 119A BOULDER CANYON SH 119: NEDERLAND - EAST	01/03/19	1.00	1000.00	1157.19	1000.00
		WEIGHTED AVERAGE FOR THE FIRST QUARTER		1.00	1000.00	1157.19	1000.00
NHPP0703-445 CR300-248		I-70 WESTBOUND PEAK PERIOD SH CRAIG RESIDENCY ADA RAMPS	04/25/19 05/16/19	3.00 2.00	1500.00 1000.00	1460.90 1281.67	1423.00 500.00
		WEIGHTED AVERAGE FOR THE SECOND QUARTER		5.00	1300.00	1389.21	1053.80
		WEIGHTED AVERAGE FOR THE YEAR		6.00	1250.00	1308.50	1044.83
=====	622-00352	Trash Receptacle (Bear Resist) (Special)		Each	=====		
NHPP0701-241		I-70 TRUCK PARKING GARFIELD C	01/17/19	6.00	1200.00	2147.45	1500.00
		WEIGHTED AVERAGE FOR THE FIRST QUARTER		6.00	1200.00	2147.45	1500.00
		WEIGHTED AVERAGE FOR THE YEAR		6.00	1200.00	2147.45	1500.00
=====	622-00715	Monitor Wells		Lin Foot	=====		
STR0241-062		US 24 143.4 - 148	01/24/19	26.00	200.00	251.33	120.00
		WEIGHTED AVERAGE FOR THE FIRST QUARTER		26.00	200.00	251.33	120.00
		WEIGHTED AVERAGE FOR THE YEAR		26.00	200.00	251.33	120.00
=====	622-03262	Sani Vault Restroom (Special)		LUMP SUM	=====		
NHPP0701-241		I-70 TRUCK PARKING GARFIELD C	01/17/19	1.00	45000.00	69062.39	65000.00
		WEIGHTED AVERAGE FOR THE FIRST QUARTER		1.00	45000.00	69062.39	65000.00
		WEIGHTED AVERAGE FOR THE YEAR		1.00	45000.00	69062.39	65000.00

COLORADO DEPARTMENT OF TRANSPORTATION
 ITEM UNIT COSTS BY PROJECTS -- 2019 COST DATA

13:44 Wednesday, August 7, 2019 299

PROJECT NUMBER	ITEM NUMBER/ PROJECT LOCATION	ITEM DESCRIPTION/ PROJECT LOCATION	DATE LET	UNIT/ QUANTITY	ENGR. EST.	AVERAGE BID	AWARDED BID
=====	624-20019	18 In Drainage Pipe (CL 0) (CIP)		Lin Foot	=====		
STR0132-021		SH 13-MOFFAT COUNTY-CR 3 SOUT	01/10/19	260.00	100.00	122.60	129.00
	WEIGHTED AVERAGE FOR THE FIRST QUARTER			260.00	100.00	122.60	129.00
	WEIGHTED AVERAGE FOR THE YEAR			260.00	100.00	122.60	129.00
=====	624-20025	24 In Drainage Pipe (CL 0) (CIP)		Lin Foot	=====		
STR0132-021		SH 13-MOFFAT COUNTY-CR 3 SOUT	01/10/19	255.00	110.00	144.00	156.00
	WEIGHTED AVERAGE FOR THE FIRST QUARTER			255.00	110.00	144.00	156.00
	WEIGHTED AVERAGE FOR THE YEAR			255.00	110.00	144.00	156.00
=====	624-20031	30 In Drainage Pipe (CL 0) (CIP)		Lin Foot	=====		
STR0132-021		SH 13-MOFFAT COUNTY-CR 3 SOUT	01/10/19	493.00	120.00	156.20	163.00
	WEIGHTED AVERAGE FOR THE FIRST QUARTER			493.00	120.00	156.20	163.00
	WEIGHTED AVERAGE FOR THE YEAR			493.00	120.00	156.20	163.00
=====	624-20037	36 In Drainage Pipe (CL 0) (CIP)		Lin Foot	=====		
STR0132-021		SH 13-MOFFAT COUNTY-CR 3 SOUT	01/10/19	418.00	140.00	166.20	173.00
	WEIGHTED AVERAGE FOR THE FIRST QUARTER			418.00	140.00	166.20	173.00
	WEIGHTED AVERAGE FOR THE YEAR			418.00	140.00	166.20	173.00
=====	624-20049	48 In Drainage Pipe (CL 0) (CIP)		Lin Foot	=====		
STR0132-021		SH 13-MOFFAT COUNTY-CR 3 SOUT	01/10/19	130.00	160.00	241.20	231.00
	WEIGHTED AVERAGE FOR THE FIRST QUARTER			130.00	160.00	241.20	231.00
	WEIGHTED AVERAGE FOR THE YEAR			130.00	160.00	241.20	231.00
=====	624-20061	60 In Drainage Pipe (CL 0) (CIP)		Lin Foot	=====		
STR0132-021		SH 13-MOFFAT COUNTY-CR 3 SOUT	01/10/19	214.00	200.00	302.00	296.00
	WEIGHTED AVERAGE FOR THE FIRST QUARTER			214.00	200.00	302.00	296.00
	WEIGHTED AVERAGE FOR THE YEAR			214.00	200.00	302.00	296.00

COLORADO DEPARTMENT OF TRANSPORTATION
ITEM UNIT COSTS BY PROJECTS -- 2019 COST DATA

13:44 Wednesday, August 7, 2019 300

PROJECT NUMBER	ITEM NUMBER/ PROJECT LOCATION	ITEM DESCRIPTION/ PROJECT LOCATION	DATE LET	UNIT/ QUANTITY	ENGR. EST.	AVERAGE BID	AWARDED BID
===== 624-20300		Detour Drainage Pipe (CL 0)		Lin Foot	=====		
FBR0341-087		US 34 OVER NORTH FORK CO RIVE	01/10/19	100.00	70.00	74.55	54.31
NHPP050A-033		US50 West of Delta EB Lanes R	03/14/19	600.00	80.00	52.17	44.50
		WEIGHTED AVERAGE FOR THE FIRST QUARTER		700.00	78.57	57.76	45.90
FBR0063-057		US-6 F-09-K BRIDGE OVER CASTL	05/30/19	300.00	50.00	102.00	19.00
		WEIGHTED AVERAGE FOR THE SECOND QUARTER		300.00	50.00	102.00	19.00
		WEIGHTED AVERAGE FOR THE YEAR		1,000.00	70.00	66.61	37.83
===== 624-20301		Detour Drainage Pipe (CL 0)		LUMP SUM	=====		
ER072A-040		PR SH72A FLOOD PERMANENT REPA	01/31/19	1.00	16000.00	133627.66	140000.00
NHPP072A-041		PR SH72A FLOOD PERMANENT REPA					
NHPP145A-065		SH 145 PASSING LANES AT DEEP	02/14/19	1.00	20000.00	44906.66	19500.00
		WEIGHTED AVERAGE FOR THE FIRST QUARTER		2.00	18000.00	107533.25	79750.00
		WEIGHTED AVERAGE FOR THE YEAR		2.00	18000.00	107533.25	79750.00
===== 624-21013		12 In Drainage Pipe (CL 1) (CIP)		Lin Foot	=====		
ER119A-065		PR SH 119A BOULDER CANYON	01/03/19	255.00	65.00	138.56	68.50
ST119A-069		SH 119: NEDERLAND - EAST					
		WEIGHTED AVERAGE FOR THE FIRST QUARTER		255.00	65.00	138.56	68.50
		WEIGHTED AVERAGE FOR THE YEAR		255.00	65.00	138.56	68.50
===== 624-27024		24 In Drainage Pipe (CL 7)		Lin Foot	=====		
NHPP006A-058		US 6 LOVELAND PASS - I-70 (FY	03/07/19	139.00	100.00	153.85	127.69
		WEIGHTED AVERAGE FOR THE FIRST QUARTER		139.00	100.00	153.85	127.69
		WEIGHTED AVERAGE FOR THE YEAR		139.00	100.00	153.85	127.69

COLORADO DEPARTMENT OF TRANSPORTATION
 ITEM UNIT COSTS BY PROJECTS -- 2019 COST DATA

13:44 Wednesday, August 7, 2019 301

PROJECT NUMBER	ITEM NUMBER/ PROJECT LOCATION	ITEM DESCRIPTION/ PROJECT LOCATION	DATE LET	UNIT/ QUANTITY	ENGR. EST.	AVERAGE BID	AWARDED BID
===== 624-27025		24 In Drainage Pipe (CL 7) (CIP)		Lin Foot	=====		
ER119A-065 STA119A-069		PR SH 119A BOULDER CANYON SH 119: NEDERLAND - EAST	01/03/19	34.00	75.00	212.90	90.00
	WEIGHTED AVERAGE FOR THE FIRST QUARTER			34.00	75.00	212.90	90.00
	WEIGHTED AVERAGE FOR THE YEAR			34.00	75.00	212.90	90.00
===== 624-27031		30 In Drainage Pipe (CL 7) (CIP)		Lin Foot	=====		
ER119A-065 STA119A-069		PR SH 119A BOULDER CANYON SH 119: NEDERLAND - EAST	01/03/19	62.00	100.00	255.93	165.00
	WEIGHTED AVERAGE FOR THE FIRST QUARTER			62.00	100.00	255.93	165.00
	WEIGHTED AVERAGE FOR THE YEAR			62.00	100.00	255.93	165.00
===== 624-27037		36 In Drainage Pipe (CL 7) (CIP)		Lin Foot	=====		
ER119A-065 STA119A-069		PR SH 119A BOULDER CANYON SH 119: NEDERLAND - EAST	01/03/19	530.00	105.00	249.91	150.00
	WEIGHTED AVERAGE FOR THE FIRST QUARTER			530.00	105.00	249.91	150.00
	WEIGHTED AVERAGE FOR THE YEAR			530.00	105.00	249.91	150.00
===== 624-27049		48 In Drainage Pipe (CL 7) (CIP)		Lin Foot	=====		
ER119A-065 STA119A-069		PR SH 119A BOULDER CANYON SH 119: NEDERLAND - EAST	01/03/19	76.00	150.00	328.52	210.00
	WEIGHTED AVERAGE FOR THE FIRST QUARTER			76.00	150.00	328.52	210.00
	WEIGHTED AVERAGE FOR THE YEAR			76.00	150.00	328.52	210.00
===== 624-30019		18 In Drainage Pipe (CL 10) (CIP)		Lin Foot	=====		
STA0131-070 HMA ALT STA0131-070 PCCP ALT		SH 13 CR 5 NORTH AND SOUTH SH 13 CR 5 NORTH AND SOUTH	03/28/19	548.00	100.00	88.01	87.20
	WEIGHTED AVERAGE FOR THE FIRST QUARTER			548.00	100.00	88.01	87.20
	WEIGHTED AVERAGE FOR THE YEAR			548.00	100.00	88.01	87.20

PROJECT NUMBER	ITEM NUMBER/ PROJECT LOCATION	ITEM DESCRIPTION/ PROJECT LOCATION	DATE LET	UNIT/ QUANTITY	ENGR. EST.	AVERAGE BID	AWARDED BID
=====	624-30025	24 In Drainage Pipe (CL 10) (CIP)		Lin Foot	=====		
STA0131-070 HMA ALT		SH 13 CR 5 NORTH AND SOUTH	03/28/19	3,258.00	140.00	107.79	93.90
STA0131-070 PCCP ALT		SH 13 CR 5 NORTH AND SOUTH					
	WEIGHTED	AVERAGE FOR THE FIRST QUARTER		3,258.00	140.00	107.79	93.90
		WEIGHTED AVERAGE FOR THE YEAR		3,258.00	140.00	107.79	93.90
=====	624-30031	30 In Drainage Pipe (CL 10) (CIP)		Lin Foot	=====		
STA0131-070 HMA ALT		SH 13 CR 5 NORTH AND SOUTH	03/28/19	318.00	180.00	138.24	116.00
STA0131-070 PCCP ALT		SH 13 CR 5 NORTH AND SOUTH					
	WEIGHTED	AVERAGE FOR THE FIRST QUARTER		318.00	180.00	138.24	116.00
		WEIGHTED AVERAGE FOR THE YEAR		318.00	180.00	138.24	116.00
=====	624-30037	36 In Drainage Pipe (CL 10) (CIP)		Lin Foot	=====		
STA0131-070 HMA ALT		SH 13 CR 5 NORTH AND SOUTH	03/28/19	688.00	280.00	159.95	134.00
STA0131-070 PCCP ALT		SH 13 CR 5 NORTH AND SOUTH					
	WEIGHTED	AVERAGE FOR THE FIRST QUARTER		688.00	280.00	159.95	134.00
		WEIGHTED AVERAGE FOR THE YEAR		688.00	280.00	159.95	134.00
=====	624-30049	48 In Drainage Pipe (CL 10) (CIP)		Lin Foot	=====		
STA0131-070 HMA ALT		SH 13 CR 5 NORTH AND SOUTH	03/28/19	612.00	480.00	231.97	184.00
STA0131-070 PCCP ALT		SH 13 CR 5 NORTH AND SOUTH					
	WEIGHTED	AVERAGE FOR THE FIRST QUARTER		612.00	480.00	231.97	184.00
		WEIGHTED AVERAGE FOR THE YEAR		612.00	480.00	231.97	184.00
=====	624-30061	60 In Drainage Pipe (CL 10) (CIP)		Lin Foot	=====		
STA0131-070 HMA ALT		SH 13 CR 5 NORTH AND SOUTH	03/28/19	816.00	680.00	330.98	252.00
STA0131-070 PCCP ALT		SH 13 CR 5 NORTH AND SOUTH					
	WEIGHTED	AVERAGE FOR THE FIRST QUARTER		816.00	680.00	330.98	252.00
		WEIGHTED AVERAGE FOR THE YEAR		816.00	680.00	330.98	252.00

PROJECT NUMBER	ITEM NUMBER/ PROJECT LOCATION	ITEM DESCRIPTION/ PROJECT LOCATION	DATE LET	UNIT/ QUANTITY	ENGR. EST.	AVERAGE BID	AWARDED BID
===== 624-50025		24 In Equip Drain Pipe E (CL 10) (CIP)		Lin Foot	=====		
STA0131-070 HMA ALT		SH 13 CR 5 NORTH AND SOUTH	03/28/19	1,108.00	300.00	186.84	181.00
STA0131-070 PCCP ALT		SH 13 CR 5 NORTH AND SOUTH					
	WEIGHTED AVERAGE FOR THE FIRST QUARTER			1,108.00	300.00	186.84	181.00
	WEIGHTED AVERAGE FOR THE YEAR			1,108.00	300.00	186.84	181.00
===== 624-50049		48 In Equip Drain Pipe E (CL 10) (CIP)		Lin Foot	=====		
STA0131-070 HMA ALT		SH 13 CR 5 NORTH AND SOUTH	03/28/19	232.00	600.00	355.86	366.00
STA0131-070 PCCP ALT		SH 13 CR 5 NORTH AND SOUTH					
	WEIGHTED AVERAGE FOR THE FIRST QUARTER			232.00	600.00	355.86	366.00
	WEIGHTED AVERAGE FOR THE YEAR			232.00	600.00	355.86	366.00
===== 625-00000		Const Surveying		LUMP SUM	=====		
STAR200-242		R2 NORTH PROGRAM WALL REPAIRS	01/03/19	1.00	10000.00	21208.84	31200.00
IM0251-351		I-25 South of Pueblo MP 79.6	01/03/19	1.00	15000.00	14828.96	14173.59
FSA0142-068		SH 14 & WCR 33 INTERSECTION I	01/03/19	1.00	6000.00	6388.75	5355.00
SHER100-289		INTERSECTIONS @ SH83 & LONGS	01/03/19	1.00	20000.00	16300.00	20000.00
ER119A-065		PR SH 119A BOULDER CANYON	01/03/19	1.00	165000.00	360584.24	250000.00
STA119A-069		SH 119: NEDERLAND - EAST					
STR0132-021		SH 13-MOFFAT COUNTY-CR 3 SOUT	01/10/19	1.00	80000.00	131276.00	103380.00
FBR0341-087		US 34 OVER NORTH FORK CO RIVE	01/10/19	1.00	60000.00	37684.59	32382.52
NHPP0701-241		I-70 TRUCK PARKING GARFIELD C	01/17/19	1.00	25000.00	40974.92	27500.00
STR0241-062		US 24 143.4 - 148	01/24/19	1.00	50000.00	99000.00	75000.00
NHPPR100-250		PACKAGE A (I-25 / I-70 / I-76	01/24/19	1.00	5000.00	26723.49	10000.00
ER072A-040		PR SH72A FLOOD PERMANENT REPA	01/31/19	1.00	90000.00	87827.32	99000.00
NHPP072A-041		PR SH72A FLOOD PERMANENT REPA					
STAM086-075		SH96A ABRIENDO - ORMAN SAFETY	01/31/19	1.00	15000.00	30583.33	15250.00
STA067A-038		SH 67 SEDALIA RESURFACING	01/31/19	1.00	7500.00	11829.70	10000.00
NHPP0821-107		SH 82 GLENWOOD SPRINGS TO CA	02/07/19	1.00	20000.00	23400.00	11800.00
NH2871-035		US 287 PASSING LANES SOUTH OF	02/07/19	1.00	50000.00	28383.84	21399.00
NHPP145A-065		SH 145 PASSING LANES AT DEEP	02/14/19	1.00	70000.00	64758.36	68000.00
NHPP0741-022		SH 74: I-70 TO CR 65 RESURFAC	02/14/19	1.00	15000.00	24459.94	29500.00
NHPP070A-028		FALL RIVER ROAD BRIDGE	02/21/19	1.00	24000.00	40880.00	37200.00
SHER100-284		FY19 NORTH SIGNAL PKG	02/21/19	1.00	5000.00	12966.67	16700.00
NHPP1601-073		US 160 PASSING LANE NORTH OF	03/07/19	1.00	100000.00	78188.43	76376.85
FBR0253-247		I25 AT VINE DRIVE BRIDGE REPL	03/07/19	1.00	45000.00	44126.92	40500.00
NHPP006A-058		US 6 LOVELAND PASS - I-70 (FY	03/07/19	1.00	25000.00	13531.59	13063.18

PROJECT NUMBER	ITEM NUMBER/ PROJECT LOCATION	ITEM DESCRIPTION/ PROJECT LOCATION	DATE LET	UNIT/ QUANTITY	ENGR. EST.	AVERAGE BID	AWARDED BID
===== 625-00000				Const Surveying			
				LUMP SUM	=====		
SHE2254-090		Colfax & I-225, Colfax & Cham	03/07/19	1.00	15000.00	32500.00	25000.00
NHPP050A-033		US50 West of Delta EB Lanes R	03/14/19	1.00	12000.00	54666.67	44000.00
NHPP0503-087		US 50 PASSING LANES EAST OF S	03/21/19	1.00	50000.00	57500.00	65000.00
SHE 0252-481		I-25 RAMP METER INSTALLATION	03/21/19	1.00	20000.00	17190.00	14080.00
SHER100-308		MIDPOINT - SIGNAL CONST PACKA	03/21/19	1.00	10000.00	24600.00	30000.00
NHPP2254-089		I-225 RESURFACING FROM I-25 T	03/21/19	1.00	80000.00	16236.76	15000.00
STM0242-077		US24 - 8TH ST TO WEST OF MANI	03/28/19	1.00	45000.00	64233.33	42700.00
STA0131-070 HMA ALT		SH 13 CR 5 NORTH AND SOUTH	03/28/19	1.00	100000.00	166816.67	124900.00
STA0131-070 PCCP ALT		SH 13 CR 5 NORTH AND SOUTH					
WEIGHTED AVERAGE FOR THE FIRST QUARTER				30.00	43048.39	70659.78	45615.34
NHPP030A-035		US 285/SH30	04/04/19	1.00	65000.00	120000.00	120000.00
IM0252-472		I-25 CABLE BARRIER PHASE III	04/04/19	1.00	20000.00	23500.00	17000.00
BR071A-020		REPLACEMENT OF STRUCTURE L-22	04/18/19	1.00	10000.00	17000.00	12000.00
FSA0252-468		I-25 AND PLUM CREEK IMPROVEME	04/18/19	1.00	20000.00	15616.50	11446.00
NHPP0703-445		I-70 WESTBOUND PEAK PERIOD SH	04/25/19	1.00	275000.00	765253.00	495759.00
MTCE0641-103		MTCE R3 FY20 SH 64 RANGELY PE	05/02/19	1.00	25000.00	19750.00	20000.00
FSA0703-454		EB I-70 AUX LANE WARD TO KIPL	05/16/19	1.00	25000.00	50000.00	35000.00
CR300-248		CRAIG RESIDENCY ADA RAMP	05/16/19	1.00	3600.00	6144.33	7500.00
SHE0701-243		I-70 EXIT 26 DDI MODIFICATION	05/16/19	1.00	20000.00	22625.00	25000.00
STMC430-020		ADA RAMP DIVIDE ESB	05/23/19	1.00	12000.00	35000.00	35000.00
FBR0063-057		US-6 F-09-K BRIDGE OVER CASTL	05/30/19	1.00	40000.00	35925.00	51850.00
NHPP0703-442		I-70 SILVERPLUME SOUNDWALL AN	06/13/19	1.00	25000.00	32639.82	22700.00
NHPP030A-036		SH 30 & TOWER RD IMPROVEMENTS	06/13/19	1.00	10000.00	12000.00	12000.00
STR 141A-040		R5 YEAR 4 BRDG PREV MAINT RAM	06/20/19	1.00	30000.00	40000.00	40000.00
NHPP160A-030		US160 MM 43.2, 150.4, 156.3,	06/20/19	1.00	25000.00	9483.34	9500.00
WEIGHTED AVERAGE FOR THE SECOND QUARTER				15.00	40373.33	81794.96	60983.67
WEIGHTED AVERAGE FOR THE YEAR				45.00	42176.09	73377.29	50738.11
===== 625-00001				Const Surveying (Hour)			
				Hour	=====		
STR0241-062		US 24 143.4 - 148	01/24/19	40.00	200.00	175.33	160.00
ER072A-040		PR SH72A FLOOD PERMANENT REPA	01/31/19	200.00	200.00	161.11	155.00
NHPP072A-041		PR SH72A FLOOD PERMANENT REPA					
STA067A-038		SH 67 SEDALIA RESURFACING	01/31/19	10.00	200.00	235.48	200.00
C R100-315		R1 ADA CURB RAMPS - PH 5	03/07/19	25.00	300.00	232.50	180.00
NHPP050A-033		US50 West of Delta EB Lanes R	03/14/19	20.00	175.00	138.33	125.00
NHPP2254-089		I-225 RESURFACING FROM I-25 T	03/21/19	40.00	250.00	187.55	165.00
WEIGHTED AVERAGE FOR THE FIRST QUARTER				335.00	211.94	164.46	158.21

PROJECT NUMBER	ITEM NUMBER/ PROJECT LOCATION	ITEM DESCRIPTION/ PROJECT LOCATION	DATE LET	UNIT/ QUANTITY	ENGR. EST.	AVERAGE BID	AWARDED BID
=====	625-00001	Const Surveying (Hour)		Hour	=====	=====	=====
C2571-013		SH257 & 392:WINDSOR CURB RAMP	05/02/19	100.00	200.00	227.33	185.00
FSA2873-190		US 287 AND FOOTHILLS PARKWAY	05/02/19	50.00	200.00	237.50	255.00
		WEIGHTED AVERAGE FOR THE SECOND QUARTER		150.00	200.00	229.88	208.33
		WEIGHTED AVERAGE FOR THE YEAR		485.00	208.25	172.69	173.71
=====	626-00000	Mobilization		LUMP SUM	=====	=====	=====
STAR200-242		R2 NORTH PROGRAM WALL REPAIRS	01/03/19	1.00	363403.23	208828.65	231792.00
IM0251-351		I-25 South of Pueblo MP 79.6	01/03/19	1.00	328193.35	668258.43	295562.71
NHPPR500-173		US 160_550 DURANGO SIGNALS OP	01/03/19	1.00	110000.00	104615.00	119230.00
FSA0142-068		SH 14 & WCR 33 INTERSECTION I	01/03/19	1.00	18000.00	25437.50	16750.00
SHER100-289		INTERSECTIONS @ SH83 & LONGS	01/03/19	1.00	150000.00	99534.00	75000.00
ER119A-065		PR SH 119A BOULDER CANYON	01/03/19	1.00	2750000.00	2810186.27	3480000.00
STA119A-069		SH 119: NEDERLAND - EAST					
STR0132-021		SH 13-MOFFAT COUNTY-CR 3 SOUT	01/10/19	1.00	900000.00	869676.00	717980.00
FBR0341-087		US 34 OVER NORTH FORK CO RIVE	01/10/19	1.00	500000.00	425528.09	298668.54
MTCER300-247		MTCE R3 FY19 REGION ROUNDABOU	01/10/19	1.00	25000.00	43400.00	21500.00
STR141A-047		SH 141 MP 120-143 MESA COUNTY	01/17/19	1.00	600000.00	557124.20	405000.00
NHPP0701-241		I-70 TRUCK PARKING GARFIELD C	01/17/19	1.00	250000.00	262472.51	275000.00
MTCER400-368		REGION 4 FY 19 STENCIL NW	01/17/19	1.00	25000.00	42250.00	15000.00
STR0241-062		US 24 143.4 - 148	01/24/19	1.00	600000.00	727333.33	670000.00
NHPPR100-250		PACKAGE A (I-25 / I-70 / I-76	01/24/19	1.00	280000.00	277077.96	209000.00
ER072A-040		PR SH72A FLOOD PERMANENT REPA	01/31/19	1.00	840000.00	844173.09	614000.00
NHPP072A-041		PR SH72A FLOOD PERMANENT REPA					
STAM086-075		SH96A ABRIENDO - ORMAN SAFETY	01/31/19	1.00	37319.78	254166.67	62500.00
STA067A-038		SH 67 SEDALIA RESURFACING	01/31/19	1.00	95000.00	149610.66	112000.00
NHPP0821-107		SH 82 GLENWOOD SPRINGS TO CA	02/07/19	1.00	620000.00	530500.00	380000.00
NH2871-035		US 287 PASSING LANES SOUTH OF	02/07/19	1.00	313616.00	361883.73	320381.19
ITSSW01-638		ETHERNET PHASE III (PRIMARILY	02/07/19	1.00	206257.50	192500.00	100000.00
MTCER500-206		R5 FY19 STRIPING	02/07/19	1.00	15000.00	45666.67	12000.00
NHPP145A-065		SH 145 PASSING LANES AT DEEP	02/14/19	1.00	450000.00	598138.35	535000.00
NHPP0741-022		SH 74: I-70 TO CR 65 RESURFAC	02/14/19	1.00	300000.00	215748.71	156500.00
NHPP1601-076		US 160 MANCOS HILL (MP 40.000	02/21/19	1.00	300000.00	327666.67	278000.00
NHPP070A-028		FALL RIVER ROAD BRIDGE	02/21/19	1.00	300000.00	265565.61	254416.66
SHER100-284		FY19 NORTH SIGNAL PKG	02/21/19	1.00	24000.00	88333.33	61000.00
NHPP1601-073		US 160 PASSING LANE NORTH OF	03/07/19	1.00	850000.00	674500.00	579000.00
FBR0253-247		I25 AT VINE DRIVE BRIDGE REPL	03/07/19	1.00	450000.00	404805.50	215000.00
MPR200-253		R2 FY19 STENCIL PVMT MKG PROJ	03/07/19	1.00	40714.16	17500.00	12500.00
NHPP006A-058		US 6 LOVELAND PASS - I-70 (FY	03/07/19	1.00	270000.00	412751.54	456503.08
C R100-315		R1 ADA CURB RAMPS - PH 5	03/07/19	1.00	150000.00	159648.00	154296.00

PROJECT NUMBER	ITEM NUMBER/ PROJECT LOCATION	ITEM DESCRIPTION/ PROJECT LOCATION	DATE LET	UNIT/ QUANTITY	ENGR. EST.	AVERAGE BID	AWARDED BID
===== 626-00000 Mobilization LUMP SUM =====							
SHE2254-090		Colfax & I-225, Colfax & Cham	03/07/19	1.00	495000.00	257500.00	290000.00
NHPP0702-378		I-70 OFFICERS GULCH TO FRISCO	03/14/19	1.00	550000.00	660500.00	451500.00
NHPP050A-033		US50 West of Delta EB Lanes R	03/14/19	1.00	520000.00	443333.33	275000.00
NHPP0503-087		US 50 PASSING LANES EAST OF S	03/21/19	1.00	350000.00	412896.00	355792.00
SHE 0252-481		I-25 RAMP METER INSTALLATION	03/21/19	1.00	170000.00	401250.00	130000.00
SHER100-308		MIDPOINT - SIGNAL CONST PACKA	03/21/19	1.00	250000.00	177500.00	218000.00
NHPP2254-089		I-225 RESURFACING FROM I-25 T	03/21/19	1.00	800000.00	749441.99	412300.00
STM0242-077		US24 - 8TH ST TO WEST OF MANI	03/28/19	1.00	574114.62	919000.00	960000.00
STA0131-070 HMA ALT		SH 13 CR 5 NORTH AND SOUTH	03/28/19	1.00	1600000.00	1672776.12	694344.00
STA0131-070 PCCP ALT		SH 13 CR 5 NORTH AND SOUTH					
WEIGHTED AVERAGE FOR THE FIRST QUARTER				40.00	459649.24	568546.02	373012.90
NHPP030A-035		US 285/SH30	04/04/19	1.00	650000.00	690000.00	690000.00
STRR300-236		SH 92 and SH 133	04/04/19	1.00	210000.00	270000.00	270000.00
IM0252-472		I-25 CABLE BARRIER PHASE III	04/04/19	1.00	279038.00	280000.00	260000.00
MTCE300-252		MTCE R3 FY19/20 REGION WIDE E	04/04/19	1.00	5000.00	16500.00	15000.00
BR071A-020		REPLACEMENT OF STRUCTURE L-22	04/18/19	1.00	31605.10	178278.94	120000.00
FSA0252-468		I-25 AND PLUM CREEK IMPROVEME	04/18/19	1.00	80000.00	113087.75	76801.00
MTCE0702-387		MTCE R3 FY19 I-70 TAPE	04/18/19	1.00	8000.00	14833.33	12000.00
MTCE300-253		MTCE R3 FY19/20 REGION WIDE S	04/18/19	1.00	15000.00	31250.00	12500.00
NHPP0703-445		I-70 WESTBOUND PEAK PERIOD SH	04/25/19	1.00	6000000.00	6721624.67	6164874.00
NHPP2851-012		US 285 Antonito to Estrella C	05/02/19	1.00	180000.00	138663.33	100000.00
C2571-013		SH257 & 392:WINDSOR CURB RAMP	05/02/19	1.00	60000.00	125000.00	75000.00
MTCE0641-103		MTCE R3 FY20 SH 64 RANGELY PE	05/02/19	1.00	50000.00	102326.50	98593.00
FSA2873-190		US 287 AND FOOTHILLS PARKWAY	05/02/19	1.00	32500.00	46100.00	40200.00
FSA0061-090		SH 6: CENTER LINE RUMBLE STRI	05/02/19	1.00	43460.70	85000.00	85000.00
FSAR100-327		REGION 1 6 INCH LANE LINE MAR	05/09/19	1.00	50000.00	32500.00	32500.00
IM0252-456		I-25 COLORADO SPRINGS RAMP ME	05/16/19	1.00	128501.00	227052.33	125462.00
FSA0703-454		EB I-70 AUX LANE WARD TO KIPL	05/16/19	1.00	225000.00	205333.33	186000.00
CR300-248		CRAIG RESIDENCY ADA RAMPS	05/16/19	1.00	150000.00	153349.67	125374.00
SHE0701-243		I-70 EXIT 26 DDI MODIFICATION	05/16/19	1.00	100000.00	114395.75	138583.00
STMC430-020		ADA RAMPS DIVIDE ESB	05/23/19	1.00	51289.67	37000.00	37000.00
FBR0063-057		US-6 F-09-K BRIDGE OVER CASTL	05/30/19	1.00	370300.00	262394.07	283000.00
STRR200-257		ROAD CLOSURE GATES ON VARIOUS	05/30/19	1.00	68922.95	73120.00	45471.00
MPR200-255		FY20 R2 PAVEMENT MARKING PROJ	06/06/19	1.00	41407.80	67500.00	25000.00
ER145A-081		SH 145 MP 21 EMERGENCY ROCKFA	06/07/19	1.00	50000.00	85005.11	49875.00
NHPP0703-442		I-70 SILVERPLUME SOUNDWALL AN	06/13/19	1.00	250000.00	419843.56	304892.20
NHPP030A-036		SH 30 & TOWER RD IMPROVEMENTS	06/13/19	1.00	50000.00	111000.00	111000.00
CR500-205		R5 GUARDRAIL END TREATMENT EA	06/13/19	1.00	60000.00	110825.00	110825.00
FSA0142-067		SH 14 RUMBLESTRIPS: AULT TO S	06/13/19	1.00	54907.42	65000.00	65000.00
STR 141A-040		R5 YEAR 4 BRDG PREV MAINT RAM	06/20/19	1.00	200000.00	534000.00	250000.00
NHPP160A-030		US160 MM 43.2, 150.4, 156.3,	06/20/19	1.00	110000.00	121704.68	120000.00
C0502-085		US 50 MM 201.8 MONARCH AVALAN	06/27/19	1.00	40000.00	59250.00	45500.00
WEIGHTED AVERAGE FOR THE SECOND QUARTER				31.00	311126.86	437901.57	325014.52
=====							
WEIGHTED AVERAGE FOR THE YEAR				71.00	395702.10	526874.95	352055.86

PROJECT NUMBER	ITEM NUMBER/ PROJECT LOCATION	ITEM DESCRIPTION/ PROJECT LOCATION	DATE LET	UNIT/ QUANTITY	ENGR. EST.	AVERAGE BID	AWARDED BID
===== 626-01102		Public Info Services (Tier II)		LUMP SUM	=====		
ER119A-065 STA119A-069		PR SH 119A BOULDER CANYON SH 119: NEDERLAND - EAST	01/03/19	1.00	30000.00	50323.47	65000.00
		WEIGHTED AVERAGE FOR THE FIRST QUARTER		1.00	30000.00	50323.47	65000.00
NHPP0703-445		I-70 WESTBOUND PEAK PERIOD SH	04/25/19	1.00	150000.00	105339.68	116501.00
		WEIGHTED AVERAGE FOR THE SECOND QUARTER		1.00	150000.00	105339.68	116501.00
		WEIGHTED AVERAGE FOR THE YEAR		2.00	90000.00	65327.89	90750.50
===== 626-01103		Public Info Services (Tier III)		LUMP SUM	=====		
STAR200-242		R2 NORTH PROGRAM WALL REPAIRS	01/03/19	1.00	25000.00	11989.43	8835.00
IM0251-351		I-25 South of Pueblo MP 79.6	01/03/19	1.00	28000.00	11056.73	19515.17
STR0132-021		SH 13-MOFFAT COUNTY-CR 3 SOUT	01/10/19	1.00	15000.00	13372.00	8080.00
FBR0341-087		US 34 OVER NORTH FORK CO RIVE	01/10/19	1.00	10000.00	12269.99	5719.92
NHPP0701-241		I-70 TRUCK PARKING GARFIELD C	01/17/19	1.00	15000.00	6103.23	4000.00
STR0241-062		US 24 143.4 - 148	01/24/19	1.00	20000.00	11336.67	19000.00
NHPPR100-250		PACKAGE A (I-25 / I-70 / I-76	01/24/19	1.00	75000.00	14728.16	8000.00
ER072A-040		PR SH72A FLOOD PERMANENT REPA	01/31/19	1.00	35000.00	19168.50	20000.00
NHPP072A-041		PR SH72A FLOOD PERMANENT REPA					
NHPP0821-107		SH 82 GLENWOOD SPRINGS TO CA	02/07/19	1.00	15000.00	22800.00	10600.00
NHPP145A-065		SH 145 PASSING LANES AT DEEP	02/14/19	1.00	20000.00	7716.83	6500.00
NHPP0741-022		SH 74: I-70 TO CR 65 RESURFAC	02/14/19	1.00	6500.00	11451.89	11775.00
NHPP070A-028		FALL RIVER ROAD BRIDGE	02/21/19	1.00	6500.00	11567.00	8000.00
FBR0253-247		I25 AT VINE DRIVE BRIDGE REPL	03/07/19	1.00	10000.00	13538.73	13000.00
NHPP006A-058		US 6 LOVELAND PASS - I-70 (FY	03/07/19	1.00	15000.00	10201.29	13063.18
C R100-315		R1 ADA CURB RAMPS - PH 5	03/07/19	1.00	10000.00	9000.00	8500.00
NHPP0702-378		I-70 OFFICERS GULCH TO FRISCO	03/14/19	1.00	15000.00	25458.33	15375.00
NHPP050A-033		US50 West of Delta EB Lanes R	03/14/19	1.00	20000.00	5666.67	4000.00
NHPP0503-087		US 50 PASSING LANES EAST OF S	03/21/19	1.00	15000.00	10500.00	14000.00
NHPP2254-089		I-225 RESURFACING FROM I-25 T	03/21/19	1.00	25000.00	9406.06	10000.00
STA0131-070 HMA ALT		SH 13 CR 5 NORTH AND SOUTH	03/28/19	1.00	75000.00	11391.38	7440.00
STA0131-070 PCCP ALT		SH 13 CR 5 NORTH AND SOUTH					
		WEIGHTED AVERAGE FOR THE FIRST QUARTER		20.00	25285.71	12921.90	10770.16
NHPP030A-035		US 285/SH30	04/04/19	1.00	15000.00	8400.00	8400.00

PROJECT NUMBER	ITEM NUMBER/ PROJECT LOCATION	ITEM DESCRIPTION/ PROJECT LOCATION	DATE LET	UNIT/ QUANTITY	ENGR. EST.	AVERAGE BID	AWARDED BID
===== 626-01103 Public Info Services (Tier III) LUMP SUM =====							
BR071A-020		REPLACEMENT OF STRUCTURE L-22	04/18/19	1.00	2000.00	9233.33	7500.00
IM0252-456		I-25 COLORADO SPRINGS RAMP ME	05/16/19	1.00	25000.00	8098.00	4594.00
FSA0703-454		EB I-70 AUX LANE WARD TO KIPL	05/16/19	1.00	7000.00	11532.02	4000.00
SHE0701-243		I-70 EXIT 26 DDI MODIFICATION	05/16/19	1.00	10000.00	10072.50	18490.00
FBR0063-057		US-6 F-09-K BRIDGE OVER CASTL	05/30/19	1.00	15000.00	16581.00	17370.00
NHPP0703-442		I-70 SILVERPLUME SOUNDWALL AN	06/13/19	1.00	15000.00	8623.91	7480.00
NHPP030A-036		SH 30 & TOWER RD IMPROVEMENTS	06/13/19	1.00	5000.00	5000.00	5000.00
	WEIGHTED AVERAGE FOR THE SECOND QUARTER			8.00	11750.00	9697.33	9104.25
	WEIGHTED AVERAGE FOR THE YEAR			28.00	21551.72	12220.91	10294.19
===== 626-01104 Public Info Services (Tier IV) LUMP SUM =====							
NHPPR500-173		US 160_550 DURANGO SIGNALS OP	01/03/19	1.00	5000.00	8790.00	8080.00
FSA0142-068		SH 14 & WCR 33 INTERSECTION I	01/03/19	1.00	2500.00	3095.00	2380.00
SHER100-289		INTERSECTIONS @ SH83 & LONGS	01/03/19	1.00	10000.00	6270.00	4500.00
STR141A-047		SH 141 MP 120-143 MESA COUNTY	01/17/19	1.00	12000.00	6135.15	10000.00
MTCER400-368		REGION 4 FY 19 STENCIL NW	01/17/19	1.00	7500.00	6625.00	2500.00
STAM086-075		SH96A ABRIENDO - ORMAN SAFETY	01/31/19	1.00	10000.00	8876.67	9745.00
STA067A-038		SH 67 SEDALIA RESURFACING	01/31/19	1.00	7500.00	3385.34	2500.00
NH2871-035		US 287 PASSING LANES SOUTH OF	02/07/19	1.00	15000.00	6843.70	6678.00
MTCER500-206		R5 FY19 STRIPING	02/07/19	1.00	5000.00	3966.67	4400.00
NHPP1601-076		US 160 MANCOS HILL (MP 40.000	02/21/19	1.00	3000.00	9220.00	8500.00
SHER100-284		FY19 NORTH SIGNAL PKG	02/21/19	1.00	3500.00	7347.00	6700.00
NHPP1601-073		US 160 PASSING LANE NORTH OF	03/07/19	1.00	20000.00	4500.00	4000.00
MPR200-253		R2 FY19 STENCIL PVMT MKG PROJ	03/07/19	1.00	2500.00	7333.33	2500.00
SHE2254-090		Colfax & I-225, Colfax & Cham	03/07/19	1.00	5000.00	12612.09	18000.00
SHE 0252-481		I-25 RAMP METER INSTALLATION	03/21/19	1.00	10000.00	11379.33	10040.00
SHER100-308		MIDPOINT - SIGNAL CONST PACKA	03/21/19	1.00	5000.00	6387.50	6825.00
	WEIGHTED AVERAGE FOR THE FIRST QUARTER			16.00	7718.75	6824.99	6709.25
STRR300-236		SH 92 and SH 133	04/04/19	1.00	9000.00	7500.00	7500.00
FSA0252-468		I-25 AND PLUM CREEK IMPROVEME	04/18/19	1.00	8000.00	7465.50	4012.00
NHPP2851-012		US 285 Antonito to Estrella C	05/02/19	1.00	5000.00	9333.33	3000.00
C2571-013		SH257 & 392:WINDSOR CURB RAMP	05/02/19	1.00	5500.00	7210.33	5000.00
MTCE0641-103		MTCE R3 FY20 SH 64 RANGELY PE	05/02/19	1.00	5000.00	12700.00	16500.00
FSA2873-190		US 287 AND FOOTHILLS PARKWAY	05/02/19	1.00	6000.00	4950.00	5000.00
FSA0061-090		SH 6: CENTER LINE RUMBLE STRI	05/02/19	1.00	6000.00	10000.00	10000.00
CR300-248		CRAIG RESIDENCY ADA RAMPS	05/16/19	1.00	10000.00	8228.67	18000.00
STM430-020		ADA RAMPS DIVIDE ESB	05/23/19	1.00	8200.00	5000.00	5000.00
STRR200-257		ROAD CLOSURE GATES ON VARIOUS	05/30/19	1.00	3000.00	3191.00	4000.00

COLORADO DEPARTMENT OF TRANSPORTATION
 ITEM UNIT COSTS BY PROJECTS -- 2019 COST DATA

13:44 Wednesday, August 7, 2019 309

PROJECT NUMBER	ITEM NUMBER/ PROJECT LOCATION	ITEM DESCRIPTION/ PROJECT LOCATION	DATE LET	UNIT/ QUANTITY	ENGR. EST.	AVERAGE BID	AWARDED BID
===== 626-01104 Public Info Services (Tier IV) LUMP SUM =====							
MPR200-255	FY20 R2 PAVEMENT MARKING PROJ		06/06/19	1.00	2500.00	26666.67	45000.00
CR500-205	R5 GUARDRAIL END TREATMENT EA		06/13/19	1.00	12000.00	9500.00	9500.00
FSA0142-067	SH 14 RUMBLESTRIPS: AULT TO S		06/13/19	1.00	8000.00	7500.00	7500.00
STR 141A-040	R5 YEAR 4 BRDG PREV MAINT RAM		06/20/19	1.00	12000.00	18500.00	20000.00
NHPP160A-030	US160 MM 43.2, 150.4, 156.3,		06/20/19	1.00	7500.00	6325.00	6400.00
C0502-085	US 50 MM 201.8 MONARCH AVALAN		06/27/19	1.00	2000.00	4522.50	6000.00
	WEIGHTED AVERAGE FOR THE SECOND QUARTER			16.00	6856.25	9819.88	10775.75
	WEIGHTED AVERAGE FOR THE YEAR			32.00	7287.50	8015.73	8742.50
===== 627-00001 Pvmt Mkg Paint Gallon =====							
IM0251-351	I-25 South of Pueblo MP 79.6		01/03/19	698.00	35.00	38.81	45.53
ER119A-065	PR SH 119A BOULDER CANYON		01/03/19	116.00	65.00	67.49	65.00
STA119A-069	SH 119: NEDERLAND - EAST						
	WEIGHTED AVERAGE FOR THE FIRST QUARTER			814.00	39.28	45.96	48.30
	WEIGHTED AVERAGE FOR THE YEAR			814.00	39.28	45.96	48.30
===== 627-00002 Thermoplastic Pvmt Mkg Sq Foot =====							
STMC430-020	ADA RAMPS DIVIDE ESB		05/23/19	100.00	83.30	25.00	25.00
	WEIGHTED AVERAGE FOR THE SECOND QUARTER			100.00	83.30	25.00	25.00
	WEIGHTED AVERAGE FOR THE YEAR			100.00	83.30	25.00	25.00
===== 627-00005 Epoxy Pvmt Mkg Gallon =====							
NHPP1601-073	US 160 PASSING LANE NORTH OF		03/07/19	264.00	50.00	100.25	100.50
	WEIGHTED AVERAGE FOR THE FIRST QUARTER			264.00	50.00	100.25	100.50
	WEIGHTED AVERAGE FOR THE YEAR			264.00	50.00	100.25	100.50
===== 627-00006 Mod Epoxy Pvmt Mkg (On-Call) Gallon =====							
MTCER300-252	MTCE R3 FY19/20 REGION WIDE E		04/04/19	1,100.00	60.00	80.50	62.00
	WEIGHTED AVERAGE FOR THE SECOND QUARTER			1,100.00	60.00	80.50	62.00
	WEIGHTED AVERAGE FOR THE YEAR			1,100.00	60.00	80.50	62.00

PROJECT NUMBER	ITEM NUMBER/ PROJECT LOCATION	ITEM DESCRIPTION/ PROJECT LOCATION	DATE LET	UNIT/ QUANTITY	ENGR. EST.	AVERAGE BID	AWARDED BID
=====	627-00008	Mod Epoxy Pvmt Mkg		Gallon	=====	=====	=====
FSA0142-068		SH 14 & WCR 33 INTERSECTION I	01/03/19	11.00	250.00	481.00	340.00
SHER100-289		INTERSECTIONS @ SH83 & LONGS	01/03/19	24.00	100.00	118.60	91.00
ER119A-065		PR SH 119A BOULDER CANYON	01/03/19	1,044.84	80.00	91.11	85.00
STA119A-069		SH 119: NEDERLAND - EAST					
STR0132-021		SH 13-MOFFAT COUNTY-CR 3 SOUT	01/10/19	286.00	250.00	101.40	95.00
FBR0341-087		US 34 OVER NORTH FORK CO RIVE	01/10/19	11.00	250.00	367.61	338.00
MTCER300-247		MTCE R3 FY19 REGION ROUNDABOU	01/10/19	220.00	350.00	274.60	175.00
NHPP0701-241		I-70 TRUCK PARKING GARFIELD C	01/17/19	48.00	75.00	273.91	435.00
STR0241-062		US 24 143.4 - 148	01/24/19	330.00	75.00	93.92	100.00
NHPPR100-250		PACKAGE A (I-25 / I-70 / I-76	01/24/19	20.00	80.00	448.80	295.00
STA067A-038		SH 67 SEDALIA RESURFACING	01/31/19	129.00	100.00	77.79	75.00
NHPP0821-107		SH 82 GLENWOOD SPRINGS TO CA	02/07/19	2,612.00	72.00	77.90	75.80
NHPP0741-022		SH 74: I-70 TO CR 65 RESURFAC	02/14/19	214.00	90.00	93.01	92.30
NHPP070A-028		FALL RIVER ROAD BRIDGE	02/21/19	18.00	100.00	195.40	160.00
FBR0253-247		I25 AT VINE DRIVE BRIDGE REPL	03/07/19	56.00	200.00	118.65	90.00
NHPP006A-058		US 6 LOVELAND PASS - I-70 (FY	03/07/19	906.00	65.00	67.38	70.76
SHE2254-090		Colfax & I-225, Colfax & Cham	03/07/19	73.00	90.00	151.00	167.00
NHPP0702-378		I-70 OFFICERS GULCH TO FRISCO	03/14/19	403.00	92.00	90.62	76.87
SHE 0252-481		I-25 RAMP METER INSTALLATION	03/21/19	29.00	40.00	378.33	360.00
SHER100-308		MIDPOINT - SIGNAL CONST PACKA	03/21/19	11.00	100.00	461.50	488.00
NHPP2254-089		I-225 RESURFACING FROM I-25 T	03/21/19	432.00	75.00	69.76	60.00
STA0131-070 HMA ALT		SH 13 CR 5 NORTH AND SOUTH	03/28/19	1,044.00	78.00	84.78	106.00
STA0131-070 PCCP ALT		SH 13 CR 5 NORTH AND SOUTH					
		WEIGHTED AVERAGE FOR THE FIRST QUARTER		7,921.84	91.11	99.97	89.67
NHPP030A-035		US 285/SH30	04/04/19	202.00	90.00	70.00	70.00
STRR300-236		SH 92 and SH 133	04/04/19	3,863.00	75.00	63.00	63.00
MTCER300-252		MTCE R3 FY19/20 REGION WIDE E	04/04/19	32,739.00	60.00	60.58	57.80
FSA0252-468		I-25 AND PLUM CREEK IMPROVEME	04/18/19	54.00	90.00	181.28	171.10
NHPP0703-445		I-70 WESTBOUND PEAK PERIOD SH	04/25/19	926.00	75.00	82.81	78.00
FSA0061-090		SH 6: CENTER LINE RUMBLE STRI	05/02/19	621.00	110.00	110.00	110.00
IM0252-456		I-25 COLORADO SPRINGS RAMP ME	05/16/19	10.00	500.00	829.33	375.00
FSA0703-454		EB I-70 AUX LANE WARD TO KIPL	05/16/19	43.00	90.00	96.31	98.00
SHE0701-243		I-70 EXIT 26 DDI MODIFICATION	05/16/19	9.00	300.00	172.50	145.00
FBR0063-057		US-6 F-09-K BRIDGE OVER CASTL	05/30/19	17.00	75.00	152.50	160.00
MPR200-255		FY20 R2 PAVEMENT MARKING PROJ	06/06/19	24,071.00	54.00	66.42	65.00
NHPP0703-442		I-70 SILVERPLUME SOUNDWALL AN	06/13/19	12.00	75.00	588.90	578.00
NHPP030A-036		SH 30 & TOWER RD IMPROVEMENTS	06/13/19	49.00	90.00	175.00	175.00
FSA0142-067		SH 14 RUMBLESTRIPS: AULT TO S	06/13/19	1,000.00	96.00	110.00	110.00
		WEIGHTED AVERAGE FOR THE SECOND QUARTER		63,616.00	60.19	64.44	62.90
		WEIGHTED AVERAGE FOR THE YEAR		71,537.84	63.61	69.13	65.69

COLORADO DEPARTMENT OF TRANSPORTATION
ITEM UNIT COSTS BY PROJECTS -- 2019 COST DATA

13:44 Wednesday, August 7, 2019 311

PROJECT NUMBER	ITEM NUMBER/ PROJECT LOCATION	ITEM DESCRIPTION/ PROJECT LOCATION	DATE LET	UNIT/ QUANTITY	ENGR. EST.	AVERAGE BID	AWARDED BID
=====	627-00009	Mod Epoxy (Inlaid)		Gallon	=====		
IM0251-351		I-25 South of Pueblo MP 79.6	01/03/19	1,197.00	105.00	120.54	143.10
STR141A-047		SH 141 MP 120-143 MESA COUNTY	01/17/19	1,559.00	140.00	103.73	102.00
STAM086-075		SH96A ABRIENDO - ORMAN SAFETY	01/31/19	20.00	150.00	395.67	335.00
NH2871-035		US 287 PASSING LANES SOUTH OF	02/07/19	166.00	150.00	160.06	131.25
NHPP050A-033		US50 West of Delta EB Lanes R	03/14/19	351.00	140.00	105.00	85.00
STM0242-077		US24 - 8TH ST TO WEST OF MANI	03/28/19	494.00	182.00	63.00	60.00
		WEIGHTED AVERAGE FOR THE FIRST QUARTER		3,787.00	134.91	109.08	110.45
MTCE0641-103		MTCE R3 FY20 SH 64 RANGELY PE	05/02/19	7.00	350.00	452.50	425.00
		WEIGHTED AVERAGE FOR THE SECOND QUARTER		7.00	350.00	452.50	425.00
		WEIGHTED AVERAGE FOR THE YEAR		3,794.00	135.30	109.41	111.03
=====	627-00011	Pvmt Mkg Paint (Waterborne)		Gallon	=====		
ER119A-065		PR SH 119A BOULDER CANYON	01/03/19	15.00	200.00	92.36	65.00
STA119A-069		SH 119: NEDERLAND - EAST					
STAM086-075		SH96A ABRIENDO - ORMAN SAFETY	01/31/19	16.00	50.00	69.17	62.50
STM0242-077		US24 - 8TH ST TO WEST OF MANI	03/28/19	1,823.00	64.00	33.67	31.00
		WEIGHTED AVERAGE FOR THE FIRST QUARTER		1,854.00	64.98	35.22	31.55
BR071A-020		REPLACEMENT OF STRUCTURE L-22	04/18/19	18.00	60.00	55.00	54.00
		WEIGHTED AVERAGE FOR THE SECOND QUARTER		18.00	60.00	55.00	54.00
		WEIGHTED AVERAGE FOR THE YEAR		1,872.00	64.93	35.41	31.76
=====	627-00012	Pvmt Mkg Paint (Low VOC Solvent Base)		Gallon	=====		
FBR0341-087		US 34 OVER NORTH FORK CO RIVE	01/10/19	28.00	80.00	145.30	135.82
C R100-315		R1 ADA CURB RAMPS - PH 5	03/07/19	10.00	100.00	192.50	200.00
STM0242-077		US24 - 8TH ST TO WEST OF MANI	03/28/19	148.00	33.33	43.33	40.00
		WEIGHTED AVERAGE FOR THE FIRST QUARTER		186.00	43.94	75.16	63.03
		WEIGHTED AVERAGE FOR THE YEAR		186.00	43.94	75.16	63.03

PROJECT NUMBER	ITEM NUMBER/ PROJECT LOCATION	ITEM DESCRIPTION/ PROJECT LOCATION	DATE LET	UNIT/ QUANTITY	ENGR. EST.	AVERAGE BID	AWARDED BID
===== 627-00013		Pvmt Mkg Paint (High Build)		Gallon	=====		
STAR200-242		R2 NORTH PROGRAM WALL REPAIRS	01/03/19	2.00	100.00	243.20	234.00
SHER100-289		INTERSECTIONS @ SH83 & LONGS	01/03/19	104.00	35.00	52.20	45.00
STR0132-021		SH 13-MOFFAT COUNTY-CR 3 SOUT	01/10/19	1,048.00	40.00	47.70	48.50
STR141A-047		SH 141 MP 120-143 MESA COUNTY	01/17/19	3,989.00	35.00	39.70	40.50
NHPP0701-241		I-70 TRUCK PARKING GARFIELD C	01/17/19	62.00	27.00	95.25	132.00
STR0241-062		US 24 143.4 - 148	01/24/19	674.00	55.00	52.58	56.00
ER072A-040		PR SH72A FLOOD PERMANENT REPA	01/31/19	428.00	67.00	50.86	46.00
NHPP072A-041		PR SH72A FLOOD PERMANENT REPA					
STA067A-038		SH 67 SEDALIA RESURFACING	01/31/19	314.00	45.00	34.24	36.00
NHPP0821-107		SH 82 GLENWOOD SPRINGS TO CA	02/07/19	3,865.00	36.00	34.80	31.60
NH2871-035		US 287 PASSING LANES SOUTH OF	02/07/19	255.00	50.00	104.84	99.75
MTCER500-206		R5 FY19 STRIPING	02/07/19	64,500.00	25.00	25.80	23.25
NHPP145A-065		SH 145 PASSING LANES AT DEEP	02/14/19	475.00	140.00	60.04	63.37
NHPP1601-076		US 160 MANCOS HILL (MP 40.000	02/21/19	8,405.00	30.00	28.53	27.00
NHPP1601-073		US 160 PASSING LANE NORTH OF	03/07/19	528.00	60.00	46.50	48.00
SHE2254-090		Colfax & I-225, Colfax & Cham	03/07/19	15.00	45.00	82.75	110.00
NHPP0702-378		I-70 OFFICERS GULCH TO FRISCO	03/14/19	1,208.00	75.00	45.25	30.75
NHPP050A-033		US50 West of Delta EB Lanes R	03/14/19	1,089.00	36.00	35.33	33.00
NHPP0503-087		US 50 PASSING LANES EAST OF S	03/21/19	418.00	40.00	78.33	74.02
SHE 0252-481		I-25 RAMP METER INSTALLATION	03/21/19	15.00	45.00	147.33	145.00
SHER100-308		MIDPOINT - SIGNAL CONST PACKA	03/21/19	2.00	35.00	366.50	238.00
NHPP2254-089		I-225 RESURFACING FROM I-25 T	03/21/19	1,614.00	37.00	34.99	31.00
STA0131-070 HMA ALT		SH 13 CR 5 NORTH AND SOUTH	03/28/19	2,853.00	39.00	42.50	48.70
STA0131-070 PCCP ALT		SH 13 CR 5 NORTH AND SOUTH					
		WEIGHTED AVERAGE FOR THE FIRST QUARTER		91,863.00	29.40	30.15	27.00
NHPP030A-035		US 285/SH30	04/04/19	1,267.00	40.00	30.00	30.00
STRR300-236		SH 92 and SH 133	04/04/19	2,189.00	32.00	36.00	36.00
BR071A-020		REPLACEMENT OF STRUCTURE L-22	04/18/19	9.00	70.00	136.67	130.00
NHPP2851-012		US 285 Antonito to Estrella C	05/02/19	4,061.00	35.00	35.55	38.00
FSA0703-454		EB I-70 AUX LANE WARD TO KIPL	05/16/19	162.00	36.00	53.66	58.00
FBR0063-057		US-6 F-09-K BRIDGE OVER CASTL	05/30/19	64.00	40.00	84.00	88.00
STR 141A-040		R5 YEAR 4 BRDG PREV MAINT RAM	06/20/19	129.00	110.00	41.00	50.00
		WEIGHTED AVERAGE FOR THE SECOND QUARTER		7,881.00	36.30	36.34	37.28
		WEIGHTED AVERAGE FOR THE YEAR		99,744.00	29.94	30.49	27.83
===== 627-00014		Pvmt Mkg Paint (Low Temp)		Gallon	=====		
ER072A-040		PR SH72A FLOOD PERMANENT REPA	01/31/19	105.00	75.00	49.93	45.00

COLORADO DEPARTMENT OF TRANSPORTATION
 ITEM UNIT COSTS BY PROJECTS -- 2019 COST DATA

13:44 Wednesday, August 7, 2019 313

PROJECT NUMBER	ITEM NUMBER/ PROJECT LOCATION	ITEM DESCRIPTION/ PROJECT LOCATION	DATE LET	UNIT/ QUANTITY	ENGR. EST.	AVERAGE BID	AWARDED BID
=====	627-00014	Pvmt Mkg Paint (Low Temp)		Gallon	=====		
NHPP072A-041		PR SH72A FLOOD PERMANENT REPA					
NHPP0741-022		SH 74: I-70 TO CR 65 RESURFAC	02/14/19	888.00	110.00	33.81	32.55
NHPP006A-058		US 6 LOVELAND PASS - I-70 (FY 03/07/19		3,438.00	35.00	33.24	30.48
	WEIGHTED AVERAGE FOR THE FIRST QUARTER			4,431.00	50.98	35.21	31.24
NHPP0703-445		I-70 WESTBOUND PEAK PERIOD SH	04/25/19	4,267.00	85.00	44.11	50.00
	WEIGHTED AVERAGE FOR THE SECOND QUARTER			4,267.00	85.00	44.11	50.00
	WEIGHTED AVERAGE FOR THE YEAR			8,698.00	67.67	39.86	40.44
=====	627-00019	Pvmt Mkg Paint (High Build) (Inlaid)		Gallon	=====		
ER119A-065		PR SH 119A BOULDER CANYON	01/03/19	2,772.00	50.00	81.72	73.00
STAl19A-069		SH 119: NEDERLAND - EAST					
	WEIGHTED AVERAGE FOR THE FIRST QUARTER			2,772.00	50.00	81.72	73.00
	WEIGHTED AVERAGE FOR THE YEAR			2,772.00	50.00	81.72	73.00
=====	627-00032	Raised Flex Pvmt Marker (Temp)		Each	=====		
NHPP2851-012		US 285 Antonito to Estrella C	05/02/19	8,220.00	2.00	1.55	0.65
STR 141A-040		R5 YEAR 4 BRDG PREV MAINT RAM	06/20/19	65.00	20.00	8.50	10.00
	WEIGHTED AVERAGE FOR THE SECOND QUARTER			8,285.00	2.14	1.59	0.72
	WEIGHTED AVERAGE FOR THE YEAR			8,285.00	2.14	1.59	0.72
=====	627-00070	Preform Thermoplastic Pvmt Mkg		Sq Foot	=====		
NHPP0821-107		SH 82 GLENWOOD SPRINGS TO CA	02/07/19	409.00	19.00	13.95	13.65
	WEIGHTED AVERAGE FOR THE FIRST QUARTER			409.00	19.00	13.95	13.65
	WEIGHTED AVERAGE FOR THE YEAR			409.00	19.00	13.95	13.65
=====	627-01001	Preform Plastic Pvmt Mkg (Ty I)		Sq Foot	=====		
FSA0252-468		I-25 AND PLUM CREEK IMPROVEME	04/18/19	72.00	14.00	17.38	16.52
	WEIGHTED AVERAGE FOR THE SECOND QUARTER			72.00	14.00	17.38	16.52
	WEIGHTED AVERAGE FOR THE YEAR			72.00	14.00	17.38	16.52

PROJECT NUMBER	ITEM NUMBER/ PROJECT LOCATION	ITEM DESCRIPTION/ PROJECT LOCATION	DATE LET	UNIT/ QUANTITY	ENGR. EST.	AVERAGE BID	AWARDED BID
===== 627-01010		Preform Plastic Pvmt Mkg (TY I) (Inlaid)		Sq Foot	=====		
	IM0251-351	I-25 South of Pueblo MP 79.6	01/03/19	128.00	14.00	18.52	32.52
	NHPPR500-173	US 160_550 DURANGO SIGNALS OP	01/03/19	150.00	16.00	22.10	23.00
	SHER100-289	INTERSECTIONS @ SH83 & LONGS	01/03/19	3,304.00	14.00	12.80	11.50
	ER119A-065	PR SH 119A BOULDER CANYON	01/03/19	307.00	16.03	26.78	25.00
	STA119A-069	SH 119: NEDERLAND - EAST					
	STRO241-062	US 24 143.4 - 148	01/24/19	66.00	15.00	26.42	23.00
	NHPP0741-022	SH 74: I-70 TO CR 65 RESURFAC	02/14/19	1,915.00	15.00	13.47	13.00
	NHPP1601-073	US 160 PASSING LANE NORTH OF	03/07/19	457.40	18.00	26.75	23.50
	NHPP006A-058	US 6 LOVELAND PASS - I-70 (FY	03/07/19	325.00	12.00	27.07	26.13
	NHPP0702-378	I-70 OFFICERS GULCH TO FRISCO	03/14/19	5,197.00	15.00	14.10	12.30
	SHER100-308	MIDPOINT - SIGNAL CONST PACKA	03/21/19	221.00	12.50	20.25	20.50
	NHPP2254-089	I-225 RESURFACING FROM I-25 T	03/21/19	16,408.00	13.00	13.09	11.50
	STM0242-077	US24 - 8TH ST TO WEST OF MANI	03/28/19	21,782.00	13.00	11.67	11.00
		WEIGHTED AVERAGE FOR THE FIRST QUARTER		50,260.40	13.42	13.01	11.85
	NHPP030A-035	US 285/SH30	04/04/19	27,221.00	13.00	10.00	10.00
	MTCE0702-387	MTCE R3 FY19 I-70 TAPE	04/18/19	30,200.00	10.00	10.93	10.25
	NHPP0703-445	I-70 WESTBOUND PEAK PERIOD SH	04/25/19	8,395.00	12.00	13.61	13.00
	FSAR100-327	REGION 1 6 INCH LANE LINE MAR	05/09/19	551,705.00	9.30	9.64	9.64
	FSA0703-454	EB I-70 AUX LANE WARD TO KIPL	05/16/19	1,498.00	12.00	12.84	12.80
	MPR200-255	FY20 R2 PAVEMENT MARKING PROJ	06/06/19	28,889.00	10.00	11.15	11.00
	NHPP030A-036	SH 30 & TOWER RD IMPROVEMENTS	06/13/19	634.00	13.00	17.00	17.00
		WEIGHTED AVERAGE FOR THE SECOND QUARTER		648,542.00	9.56	10.12	9.80
		WEIGHTED AVERAGE FOR THE YEAR		698,802.40	9.84	10.61	9.95
===== 627-01011		Preform Plastic Pvmt Mkg (Contr) (Inlaid)		Sq Foot	=====		
	FSAR100-327	REGION 1 6 INCH LANE LINE MAR	05/09/19	263,016.00	9.60	9.64	9.64
		WEIGHTED AVERAGE FOR THE SECOND QUARTER		263,016.00	9.60	9.64	9.64
		WEIGHTED AVERAGE FOR THE YEAR		263,016.00	9.60	9.64	9.64
===== 627-02001		Preform Plastic Pvmt Mkg (Ty II)		Sq Foot	=====		
	NHPPRI00-250	PACKAGE A (I-25 / I-70 / I-76	01/24/19	286.00	15.00	26.37	24.00
		WEIGHTED AVERAGE FOR THE FIRST QUARTER		286.00	15.00	26.37	24.00
		WEIGHTED AVERAGE FOR THE YEAR		286.00	15.00	26.37	24.00

COLORADO DEPARTMENT OF TRANSPORTATION
ITEM UNIT COSTS BY PROJECTS -- 2019 COST DATA

13:44 Wednesday, August 7, 2019 315

PROJECT NUMBER	ITEM NUMBER/ PROJECT LOCATION	ITEM DESCRIPTION/ PROJECT LOCATION	DATE LET	UNIT/ QUANTITY	ENGR. EST.	AVERAGE BID	AWARDED BID
=====	627-02010	Preform Plastic Pvmt Mkg (Ty II) (Inlaid)		Sq Foot	=====		
SHER100-289		INTERSECTIONS @ SH83 & LONGS	01/03/19	1,865.00	13.00	15.00	14.00
NH2871-035		US 287 PASSING LANES SOUTH OF	02/07/19	2,618.00	10.00	19.68	16.59
SHE 0252-481		I-25 RAMP METER INSTALLATION	03/21/19	265.00	12.00	25.67	24.00
NHPP2254-089		I-225 RESURFACING FROM I-25 T	03/21/19	3,336.00	12.00	15.32	13.50
		WEIGHTED AVERAGE FOR THE FIRST QUARTER		8,084.00	11.58	16.99	14.96
FSA0252-468		I-25 AND PLUM CREEK IMPROVEME	04/18/19	282.00	12.00	18.49	17.46
MTCE0702-387		MTCE R3 FY19 I-70 TAPE	04/18/19	16,100.00	11.00	11.95	11.50
NHPP0703-445		I-70 WESTBOUND PEAK PERIOD SH	04/25/19	1,263.00	12.00	14.89	14.00
MPR200-255		FY20 R2 PAVEMENT MARKING PROJ	06/06/19	54,690.00	10.50	12.15	12.00
		WEIGHTED AVERAGE FOR THE SECOND QUARTER		72,335.00	10.64	12.19	11.94
		WEIGHTED AVERAGE FOR THE YEAR		80,419.00	10.74	12.78	12.25
=====	627-30210	Thermoplastic Pvmt Mkg (XS)		Sq Foot	=====		
SHE 0252-481		I-25 RAMP METER INSTALLATION	03/21/19	552.00	18.00	17.67	17.00
		WEIGHTED AVERAGE FOR THE FIRST QUARTER		552.00	18.00	17.67	17.00
NHPP030A-035		US 285/SH30	04/04/19	1,230.00	18.00	8.50	8.50
		WEIGHTED AVERAGE FOR THE SECOND QUARTER		1,230.00	18.00	8.50	8.50
		WEIGHTED AVERAGE FOR THE YEAR		1,782.00	18.00	13.76	11.13
=====	627-30323	Preform Plastic Pvmt Mkg (WS) (Typ I) (In)		Sq Foot	=====		
NHPP030A-036		SH 30 & TOWER RD IMPROVEMENTS	06/13/19	32.00	25.00	22.00	22.00
		WEIGHTED AVERAGE FOR THE SECOND QUARTER		32.00	25.00	22.00	22.00
		WEIGHTED AVERAGE FOR THE YEAR		32.00	25.00	22.00	22.00
=====	627-30324	Preform Plastic Pvmt Mkg (WS) (TY I)		Sq Foot	=====		
ER119A-065		PR SH 119A BOULDER CANYON	01/03/19	53.50	13.00	21.07	20.00

COLORADO DEPARTMENT OF TRANSPORTATION
ITEM UNIT COSTS BY PROJECTS -- 2019 COST DATA

13:44 Wednesday, August 7, 2019 316

PROJECT NUMBER	ITEM NUMBER/ PROJECT LOCATION	ITEM DESCRIPTION/ PROJECT LOCATION	DATE LET	UNIT/ QUANTITY	ENGR. EST.	AVERAGE BID	AWARDED BID
=====	627-30324	Preform Plastic Pvmt Mkg (WS) (TY I)		Sq Foot	=====	=====	=====
STA119A-069		SH 119: NEDERLAND - EAST					
SHER100-284		FY19 NORTH SIGNAL PKG	02/21/19	88.00	26.00	36.33	38.00
		WEIGHTED AVERAGE FOR THE FIRST QUARTER		141.50	21.08	26.89	31.19
		WEIGHTED AVERAGE FOR THE YEAR		141.50	21.08	26.89	31.19
=====	627-30328	Pre Plastic Pvmt Mkg (XWalk) (Typ1) (In)		Sq Foot	=====	=====	=====
IM0252-456		I-25 COLORADO SPRINGS RAMP ME	05/16/19	604.00	25.00	25.67	20.00
		WEIGHTED AVERAGE FOR THE SECOND QUARTER		604.00	25.00	25.67	20.00
		WEIGHTED AVERAGE FOR THE YEAR		604.00	25.00	25.67	20.00
=====	627-30329	Preform Plastic Pvmt Mkg (XS) (TY I)		Sq Foot	=====	=====	=====
ER119A-065		PR SH 119A BOULDER CANYON	01/03/19	826.00	15.00	12.87	12.00
STA119A-069		SH 119: NEDERLAND - EAST					
SHER100-284		FY19 NORTH SIGNAL PKG	02/21/19	96.00	14.00	28.00	29.00
		WEIGHTED AVERAGE FOR THE FIRST QUARTER		922.00	14.90	13.50	13.77
NHPP030A-036		SH 30 & TOWER RD IMPROVEMENTS	06/13/19	110.00	13.00	17.00	17.00
		WEIGHTED AVERAGE FOR THE SECOND QUARTER		110.00	13.00	17.00	17.00
		WEIGHTED AVERAGE FOR THE YEAR		1,032.00	14.69	13.55	14.11
=====	627-30405	Preform Thermoplastic Pvmt Mkg (WS)		Sq Foot	=====	=====	=====
NHPPR500-173		US 160_550 DURANGO SIGNALS OP	01/03/19	239.00	17.00	25.00	26.00
SHER100-289		INTERSECTIONS @ SH83 & LONGS	01/03/19	427.00	16.00	19.00	18.00
ER119A-065		PR SH 119A BOULDER CANYON	01/03/19	54.00	19.00	20.49	20.00
STA119A-069		SH 119: NEDERLAND - EAST					
MTCER400-368		REGION 4 FY 19 STENCIL NW	01/17/19	23,954.00	11.50	13.74	13.50
STAM086-075		SH96A ABRIENDO - ORMAN SAFETY	01/31/19	247.00	18.00	17.50	16.50
STA067A-038		SH 67 SEDALIA RESURFACING	01/31/19	17.00	15.00	20.86	18.00
NH2871-035		US 287 PASSING LANES SOUTH OF	02/07/19	348.00	20.00	19.30	14.39

PROJECT NUMBER	ITEM NUMBER/ PROJECT LOCATION	ITEM DESCRIPTION/ PROJECT LOCATION	DATE LET	UNIT/ QUANTITY	ENGR. EST.	AVERAGE BID	AWARDED BID
===== 627-30405		Preform Thermoplastic Pvmt Mkg (WS)		Sq Foot	=====	=====	=====
NHPP145A-065	SH 145 PASSING LANES AT DEEP	SH 145 PASSING LANES AT DEEP	02/14/19	229.00	30.00	23.10	22.00
NHPP0741-022	SH 74: I-70 TO CR 65 RESURFAC	SH 74: I-70 TO CR 65 RESURFAC	02/14/19	338.00	20.00	15.28	14.10
NHPP070A-028	FALL RIVER ROAD BRIDGE	FALL RIVER ROAD BRIDGE	02/21/19	76.00	25.00	16.98	17.00
FBR0253-247	I25 AT VINE DRIVE BRIDGE REPL	I25 AT VINE DRIVE BRIDGE REPL	03/07/19	178.00	15.00	19.49	17.50
MPR200-253	R2 FY19 STENCIL PVMT MKG PROJ	R2 FY19 STENCIL PVMT MKG PROJ	03/07/19	10,168.00	12.88	15.50	13.00
NHPP006A-058	US 6 LOVELAND PASS - I-70 (FY	US 6 LOVELAND PASS - I-70 (FY	03/07/19	64.00	25.00	30.57	26.13
SHE2254-090	Colfax & I-225, Colfax & Cham	Colfax & I-225, Colfax & Cham	03/07/19	193.00	15.00	19.00	18.00
NHPP0503-087	US 50 PASSING LANES EAST OF S	US 50 PASSING LANES EAST OF S	03/21/19	348.00	20.00	24.00	22.00
SHER100-308	MIDPOINT - SIGNAL CONST PACKA	MIDPOINT - SIGNAL CONST PACKA	03/21/19	357.00	20.00	18.00	18.00
NHPP2254-089	I-225 RESURFACING FROM I-25 T	I-225 RESURFACING FROM I-25 T	03/21/19	2,279.00	15.00	19.50	17.00
STM0242-077	US24 - 8TH ST TO WEST OF MANI	US24 - 8TH ST TO WEST OF MANI	03/28/19	1,671.00	16.64	17.00	16.00
	WEIGHTED AVERAGE FOR THE FIRST QUARTER			41,187.00	12.84	14.93	14.05
NHPP030A-035	US 285/SH30	US 285/SH30	04/04/19	689.00	13.00	13.00	13.00
FSA0252-468	I-25 AND PLUM CREEK IMPROVEME	I-25 AND PLUM CREEK IMPROVEME	04/18/19	550.00	14.00	17.14	16.05
STR 141A-040	R5 YEAR 4 BRDG PREV MAINT RAM	R5 YEAR 4 BRDG PREV MAINT RAM	06/20/19	45.00	25.00	30.50	35.00
	WEIGHTED AVERAGE FOR THE SECOND QUARTER			1,284.00	13.85	16.58	15.08
	WEIGHTED AVERAGE FOR THE YEAR			42,471.00	12.87	14.97	14.09
===== 627-30407		Preform Thermoplastic Pvmt Mkg (WS) (Sp)		Sq Foot	=====	=====	=====
MTCER300-247	MTCE R3 FY19 REGION ROUNDABOU	MTCE R3 FY19 REGION ROUNDABOU	01/10/19	5,755.00	22.00	23.80	20.50
NHPP0701-241	I-70 TRUCK PARKING GARFIELD C	I-70 TRUCK PARKING GARFIELD C	01/17/19	163.00	24.00	24.30	27.00
STR0241-062	US 24 143.4 - 148	US 24 143.4 - 148	01/24/19	17.00	20.00	21.17	16.00
NHPP0821-107	SH 82 GLENWOOD SPRINGS TO CA	SH 82 GLENWOOD SPRINGS TO CA	02/07/19	18.00	17.00	22.00	19.00
MPR200-253	R2 FY19 STENCIL PVMT MKG PROJ	R2 FY19 STENCIL PVMT MKG PROJ	03/07/19	120.00	17.00	16.17	13.00
NHPP050A-033	US50 West of Delta EB Lanes R	US50 West of Delta EB Lanes R	03/14/19	193.00	30.00	23.33	17.00
STA0131-070 HMA ALT	SH 13 CR 5 NORTH AND SOUTH	SH 13 CR 5 NORTH AND SOUTH	03/28/19	1,292.00	20.00	21.94	25.20
STA0131-070 PCCP ALT	SH 13 CR 5 NORTH AND SOUTH	SH 13 CR 5 NORTH AND SOUTH					
	WEIGHTED AVERAGE FOR THE FIRST QUARTER			7,558.00	21.81	23.51	20.85
STRR300-236	SH 92 and SH 133	SH 92 and SH 133	04/04/19	1,751.00	14.00	18.00	18.00
MTCER300-253	MTCE R3 FY19/20 REGION WIDE S	MTCE R3 FY19/20 REGION WIDE S	04/18/19	6,020.00	13.00	14.50	13.00
SHE0701-243	I-70 EXIT 26 DDI MODIFICATION	I-70 EXIT 26 DDI MODIFICATION	05/16/19	53.00	30.00	21.75	17.00
	WEIGHTED AVERAGE FOR THE SECOND QUARTER			7,824.00	13.34	15.05	14.15
	WEIGHTED AVERAGE FOR THE YEAR			15,382.00	17.50	21.07	17.29

PROJECT NUMBER	ITEM NUMBER/ PROJECT LOCATION	ITEM DESCRIPTION/ PROJECT LOCATION	DATE LET	UNIT/ QUANTITY	ENGR. EST.	AVERAGE BID	AWARDED BID
=====	627-30408	Pre Thermo Pvmt Mkg (Shield)		Sq Foot	=====		
MPR200-253		R2 FY19 STENCIL PVMT MKG PROJ	03/07/19	564.00	30.00	25.00	26.00
		WEIGHTED AVERAGE FOR THE FIRST QUARTER		564.00	30.00	25.00	26.00
		WEIGHTED AVERAGE FOR THE YEAR		564.00	30.00	25.00	26.00
=====	627-30410	Preform Thermoplastic Pvmt Mkg (XS)		Sq Foot	=====		
NHPPR500-173		US 160_550 DURANGO SIGNALS OP	01/03/19	40.00	17.00	23.50	19.40
FSA0142-068		SH 14 & WCR 33 INTERSECTION I	01/03/19	49.00	18.00	37.31	26.25
SHER100-289		INTERSECTIONS @ SH83 & LONGS	01/03/19	2,548.00	12.00	12.40	11.50
MTCER400-368		REGION 4 FY 19 STENCIL NW	01/17/19	40,756.00	10.20	11.04	10.50
STAM086-075		SH96A ABRIENDO - ORMAN SAFETY	01/31/19	2,661.00	16.00	11.87	11.60
STA067A-038		SH 67 SEDALIA RESURFACING	01/31/19	40.00	12.00	17.19	15.00
NHPP0741-022		SH 74: I-70 TO CR 65 RESURFAC	02/14/19	3,126.00	12.00	11.60	10.85
NHPP070A-028		FALL RIVER ROAD BRIDGE	02/21/19	150.00	25.00	13.63	13.00
FBR0253-247		I25 AT VINE DRIVE BRIDGE REPL	03/07/19	178.00	15.00	14.58	12.50
C R100-315		R1 ADA CURB RAMPS - PH 5	03/07/19	180.00	40.00	27.00	25.00
SHE2254-090		Colfax & I-225, Colfax & Cham	03/07/19	4,325.00	12.00	10.25	11.00
SHER100-308		MIDPOINT - SIGNAL CONST PACKA	03/21/19	4,351.00	12.50	12.00	13.00
NHPP2254-089		I-225 RESURFACING FROM I-25 T	03/21/19	3,005.00	12.00	13.59	12.00
STM0242-077		US24 - 8TH ST TO WEST OF MANI	03/28/19	4,990.00	13.00	11.67	11.00
		WEIGHTED AVERAGE FOR THE FIRST QUARTER		66,399.00	11.28	11.40	10.97
NHPP030A-035		US 285/SH30	04/04/19	23,950.00	12.00	8.50	8.50
FSA0252-468		I-25 AND PLUM CREEK IMPROVEME	04/18/19	1,678.00	13.00	12.25	11.51
NHPP0703-445		I-70 WESTBOUND PEAK PERIOD SH	04/25/19	583.00	12.00	11.19	10.00
C2571-013		SH257 & 392:WINDSOR CURB RAMP	05/02/19	855.00	20.00	16.50	12.50
FSA2873-190		US 287 AND FOOTHILLS PARKWAY	05/02/19	558.00	20.00	15.00	15.00
STR 141A-040		R5 YEAR 4 BRDG PREV MAINT RAM	06/20/19	126.00	20.00	27.00	30.00
		WEIGHTED AVERAGE FOR THE SECOND QUARTER		27,750.00	12.50	10.22	9.07
		WEIGHTED AVERAGE FOR THE YEAR		94,149.00	11.64	11.24	10.41
=====	627-30411	Preform Thermoplastic Pvmt Mkg (XS) (Sp)		Sq Foot	=====		
MTCER300-247		MTCE R3 FY19 REGION ROUNDABOU	01/10/19	3,000.00	20.00	17.50	16.50

COLORADO DEPARTMENT OF TRANSPORTATION
ITEM UNIT COSTS BY PROJECTS -- 2019 COST DATA

13:44 Wednesday, August 7, 2019 319

PROJECT NUMBER	ITEM NUMBER/ PROJECT LOCATION	ITEM DESCRIPTION/ PROJECT LOCATION	DATE LET	UNIT/ QUANTITY	ENGR. EST.	AVERAGE BID	AWARDED BID
=====	627-30411	Preform Thermoplastic Pvmt Mkg (XS) (Sp)		Sq Foot	=====		
STR0241-062	US 24 143.4 - 148		01/24/19	994.00	19.00	14.50	13.00
NHPP0821-107	SH 82 GLENWOOD SPRINGS TO CA		02/07/19	1,608.00	12.00	10.25	10.00
MPR200-253	R2 FY19 STENCIL PVMT MKG PROJ		03/07/19	26,211.00	12.00	12.05	10.15
NHPP0702-378	I-70 OFFICERS GULCH TO FRISCO		03/14/19	520.00	20.00	17.52	22.55
NHPP050A-033	US50 West of Delta EB Lanes R		03/14/19	283.00	30.00	19.00	12.00
STM0242-077	US24 - 8TH ST TO WEST OF MANI		03/28/19	1,600.00	11.00	13.00	12.00
	WEIGHTED AVERAGE FOR THE FIRST QUARTER			34,216.00	13.13	13.01	11.07
STRR300-236	SH 92 and SH 133		04/04/19	90.00	16.00	13.75	13.75
MT CER300-253	MTCE R3 FY19/20 REGION WIDE S		04/18/19	32,814.00	10.25	10.58	10.15
MTCE0641-103	MTCE R3 FY20 SH 64 RANGELY PE		05/02/19	360.00	30.00	15.75	14.00
CR300-248	CRAIG RESIDENCY ADA RAMPS		05/16/19	462.00	17.00	15.67	13.00
SHE0701-243	I-70 EXIT 26 DDI MODIFICATION		05/16/19	43.00	30.00	20.25	15.00
	WEIGHTED AVERAGE FOR THE SECOND QUARTER			33,769.00	10.59	10.76	10.25
	WEIGHTED AVERAGE FOR THE YEAR			67,985.00	11.87	12.13	10.66
=====	627-40012	Methyl Methac Pvmt Mkg (WS) (In)		Sq Foot	=====		
NHPP1601-076	US 160 MANCOS HILL (MP 40.000		02/21/19	5,863.00	33.00	16.57	14.00
	WEIGHTED AVERAGE FOR THE FIRST QUARTER			5,863.00	33.00	16.57	14.00
NHPP2851-012	US 285 Antonito to Estrella C		05/02/19	1,558.00	30.00	18.75	19.00
	WEIGHTED AVERAGE FOR THE SECOND QUARTER			1,558.00	30.00	18.75	19.00
	WEIGHTED AVERAGE FOR THE YEAR			7,421.00	32.37	17.03	15.05
=====	627-40013	Methyl Methac Pvmt Mkg (XS) (In)		Sq Foot	=====		
NHPP1601-076	US 160 MANCOS HILL (MP 40.000		02/21/19	1,960.00	33.00	12.80	11.00
	WEIGHTED AVERAGE FOR THE FIRST QUARTER			1,960.00	33.00	12.80	11.00
	WEIGHTED AVERAGE FOR THE YEAR			1,960.00	33.00	12.80	11.00

COLORADO DEPARTMENT OF TRANSPORTATION
 ITEM UNIT COSTS BY PROJECTS -- 2019 COST DATA

13:44 Wednesday, August 7, 2019 320

PROJECT NUMBER	ITEM NUMBER/ PROJECT LOCATION	ITEM DESCRIPTION/ PROJECT LOCATION	DATE LET	UNIT/ QUANTITY	ENGR. EST.	AVERAGE BID	AWARDED BID
=====	629-01001	Survey Monument (Ty 1)		Each	=====		
FBR0341-087		US 34 OVER NORTH FORK CO RIVE	01/10/19	2.00	500.00	420.89	212.91
ER072A-040		PR SH72A FLOOD PERMANENT REPA	01/31/19	20.00	155.00	244.52	240.00
NHPP072A-041		PR SH72A FLOOD PERMANENT REPA					
STAM086-075		SH96A ABRIENDO - ORMAN SAFETY	01/31/19	1.00	6000.00	1358.33	975.00
NHPP145A-065		SH 145 PASSING LANES AT DEEP	02/14/19	6.00	200.00	715.89	450.00
		WEIGHTED AVERAGE FOR THE FIRST QUARTER		29.00	389.66	313.29	306.92
		WEIGHTED AVERAGE FOR THE YEAR		29.00	389.66	313.29	306.92
=====	629-01003	Survey Monument (Ty 3)		Each	=====		
ER119A-065		PR SH 119A BOULDER CANYON	01/03/19	3.00	500.00	1400.87	1500.00
STA119A-069		SH 119: NEDERLAND - EAST					
ER072A-040		PR SH72A FLOOD PERMANENT REPA	01/31/19	3.00	850.00	416.45	360.00
NHPP072A-041		PR SH72A FLOOD PERMANENT REPA					
		WEIGHTED AVERAGE FOR THE FIRST QUARTER		6.00	675.00	810.22	930.00
		WEIGHTED AVERAGE FOR THE YEAR		6.00	675.00	810.22	930.00
=====	629-01005	Survey Monument (Ty 5)		Each	=====		
ER072A-040		PR SH72A FLOOD PERMANENT REPA	01/31/19	40.00	250.00	227.12	240.00
NHPP072A-041		PR SH72A FLOOD PERMANENT REPA					
		WEIGHTED AVERAGE FOR THE FIRST QUARTER		40.00	250.00	227.12	240.00
		WEIGHTED AVERAGE FOR THE YEAR		40.00	250.00	227.12	240.00
=====	629-01031	Survey Monument (Ty 3A)		Each	=====		
ER072A-040		PR SH72A FLOOD PERMANENT REPA	01/31/19	3.00	500.00	664.15	605.00
NHPP072A-041		PR SH72A FLOOD PERMANENT REPA					
FBR0253-247		I25 AT VINE DRIVE BRIDGE REPL	03/07/19	1.00	500.00	843.95	750.00
		WEIGHTED AVERAGE FOR THE FIRST QUARTER		4.00	500.00	706.23	641.25
		WEIGHTED AVERAGE FOR THE YEAR		4.00	500.00	706.23	641.25
=====	629-01050	Monument Box		Each	=====		
NHPP0821-107		SH 82 GLENWOOD SPRINGS TO CA	02/07/19	1.00	500.00	180.00	160.00
		WEIGHTED AVERAGE FOR THE FIRST QUARTER		1.00	500.00	180.00	160.00
		WEIGHTED AVERAGE FOR THE YEAR		1.00	500.00	180.00	160.00

PROJECT NUMBER	ITEM NUMBER/ PROJECT LOCATION	ITEM DESCRIPTION/ PROJECT LOCATION	DATE LET	UNIT/ QUANTITY	ENGR. EST.	AVERAGE BID	AWARDED BID
=====	629-01065	Survey Monument (Ty 5S)		Each	=====	=====	=====
CR300-248		CRAIG RESIDENCY ADA RAMPS	05/16/19	14.00	750.00	849.67	965.00
		WEIGHTED AVERAGE FOR THE SECOND QUARTER		14.00	750.00	849.67	965.00
		WEIGHTED AVERAGE FOR THE YEAR		14.00	750.00	849.67	965.00
=====	629-01110	Locate Monuments		Hour	=====	=====	=====
NHPP0821-107		SH 82 GLENWOOD SPRINGS TO CA	02/07/19	4.00	200.00	180.00	160.00
SHE2254-090		Colfax & I-225, Colfax & Cham	03/07/19	8.00	180.00	182.50	190.00
		WEIGHTED AVERAGE FOR THE FIRST QUARTER		12.00	186.67	181.67	180.00
		WEIGHTED AVERAGE FOR THE YEAR		12.00	186.67	181.67	180.00
=====	630-00000	Flagging		Hour	=====	=====	=====
STAR200-242		R2 NORTH PROGRAM WALL REPAIRS	01/03/19	400.00	28.00	27.59	26.00
IM0251-351		I-25 South of Pueblo MP 79.6	01/03/19	14,000.00	20.00	16.49	25.02
NHPPR500-173		US 160_550 DURANGO SIGNALS OP	01/03/19	100.00	30.00	31.25	26.00
FSA0142-068		SH 14 & WCR 33 INTERSECTION I	01/03/19	280.00	28.00	49.81	57.75
SHER100-289		INTERSECTIONS @ SH83 & LONGS	01/03/19	500.00	35.00	29.20	29.00
ER119A-065		PR SH 119A BOULDER CANYON	01/03/19	10,570.00	28.50	29.65	27.00
STA119A-069		SH 119: NEDERLAND - EAST					
STR0132-021		SH 13-MOFFAT COUNTY-CR 3 SOUT	01/10/19	12,000.00	28.00	24.66	21.20
FBR0341-087		US 34 OVER NORTH FORK CO RIVE	01/10/19	4,000.00	28.00	27.65	28.08
MTCER300-247		MTCE R3 FY19 REGION ROUNDABOU	01/10/19	320.00	25.00	26.60	25.00
STR141A-047		SH 141 MP 120-143 MESA COUNTY	01/17/19	6,600.00	28.00	24.81	25.00
NHPP0701-241		I-70 TRUCK PARKING GARFIELD C	01/17/19	1,908.00	25.00	29.12	22.00
MTCER400-368		REGION 4 FY 19 STENCIL NW	01/17/19	1,100.00	20.00	24.75	12.00
STR0241-062		US 24 143.4 - 148	01/24/19	10,000.00	26.00	29.17	30.00
NHPPR100-250		PACKAGE A (I-25 / I-70 / I-76	01/24/19	300.00	35.00	34.41	35.00
ER072A-040		PR SH72A FLOOD PERMANENT REPA	01/31/19	6,700.00	30.00	29.42	28.00
NHPP072A-041		PR SH72A FLOOD PERMANENT REPA					
STAM086-075		SH96A ABRIENDO - ORMAN SAFETY	01/31/19	200.00	22.00	26.50	25.50
STA067A-038		SH 67 SEDALIA RESURFACING	01/31/19	1,200.00	30.00	28.77	30.00
NHPP0821-107		SH 82 GLENWOOD SPRINGS TO CA	02/07/19	3,749.00	30.00	27.25	29.50
NH2871-035		US 287 PASSING LANES SOUTH OF	02/07/19	500.00	24.00	26.03	24.68
ITSSW01-638		ETHERNET PHASE III (PRIMARYLY	02/07/19	80.00	25.00	26.25	25.00
NHPP145A-065		SH 145 PASSING LANES AT DEEP	02/14/19	5,800.00	28.00	27.52	23.00
NHPP0741-022		SH 74: I-70 TO CR 65 RESURFAC	02/14/19	3,180.00	35.00	27.40	27.15
NHPP1601-076		US 160 MANCOS HILL (MP 40.000	02/21/19	2,300.00	24.00	20.90	23.50

PROJECT NUMBER	ITEM NUMBER/ PROJECT LOCATION	ITEM DESCRIPTION/ PROJECT LOCATION	DATE LET	UNIT/ QUANTITY	ENGR. EST.	AVERAGE BID	AWARDED BID
=====	630-00000	Flagging		Hour =====			
NHPP070A-028		FALL RIVER ROAD BRIDGE	02/21/19	400.00	30.00	27.06	32.00
SHER100-284		FY19 NORTH SIGNAL PKG	02/21/19	600.00	30.00	30.67	35.00
NHPP1601-073		US 160 PASSING LANE NORTH OF	03/07/19	5,580.00	25.00	24.28	24.55
FBR0253-247		I25 AT VINE DRIVE BRIDGE REPL	03/07/19	1,000.00	30.00	24.50	21.00
MPR200-253		R2 FY19 STENCIL PVMT MKG PROJ	03/07/19	750.00	25.00	21.67	12.00
NHPP006A-058		US 6 LOVELAND PASS - I-70 (FY	03/07/19	2,500.00	25.00	34.60	39.19
C R100-315		R1 ADA CURB RAMPS - PH 5	03/07/19	2,200.00	26.00	30.50	25.00
SHE2254-090		Colfax & I-225, Colfax & Cham	03/07/19	1,350.00	30.00	28.50	27.00
NHPP0702-378		I-70 OFFICERS GULCH TO FRISCO	03/14/19	4,150.00	30.00	32.27	32.80
NHPP050A-033		US50 West of Delta EB Lanes R	03/14/19	6,000.00	28.00	24.00	25.00
NHPP0503-087		US 50 PASSING LANES EAST OF S	03/21/19	2,400.00	25.00	24.00	21.00
SHE 0252-481		I-25 RAMP METER INSTALLATION	03/21/19	880.00	30.00	30.00	28.00
SHER100-308		MIDPOINT - SIGNAL CONST PACKA	03/21/19	1,000.00	25.00	30.50	32.00
NHPP2254-089		I-225 RESURFACING FROM I-25 T	03/21/19	3,000.00	30.00	32.56	36.00
STM0242-077		US24 - 8TH ST TO WEST OF MANI	03/28/19	700.00	28.57	29.67	32.00
STA0131-070 HMA ALT		SH 13 CR 5 NORTH AND SOUTH	03/28/19	16,000.00	28.00	30.85	31.50
STA0131-070 PCCP ALT		SH 13 CR 5 NORTH AND SOUTH					
		WEIGHTED AVERAGE FOR THE FIRST QUARTER		134,297.00	27.10	26.99	26.75
NHPP030A-035		US 285/SH30	04/04/19	750.00	32.00	30.00	30.00
STRR300-236		SH 92 and SH 133	04/04/19	3,500.00	28.00	27.00	27.00
BR071A-020		REPLACEMENT OF STRUCTURE L-22	04/18/19	100.00	26.00	30.67	26.00
FSA0252-468		I-25 AND PLUM CREEK IMPROVEME	04/18/19	32.00	30.00	34.25	29.50
MTCE0702-387		MTCE R3 FY19 I-70 TAPE	04/18/19	200.00	14.00	17.33	24.00
MTCER300-253		MTCE R3 FY19/20 REGION WIDE S	04/18/19	300.00	14.00	18.50	12.00
NHPP0703-445		I-70 WESTBOUND PEAK PERIOD SH	04/25/19	2,500.00	30.00	45.26	71.00
NHPP2851-012		US 285 Antonito to Estrella C	05/02/19	1,920.00	26.00	21.00	18.00
C2571-013		SH257 & 392:WINDSOR CURB RAMP	05/02/19	220.00	28.00	36.00	45.50
MTCE0641-103		MTCE R3 FY20 SH 64 RANGELY PE	05/02/19	500.00	30.00	20.25	8.00
FSA2873-190		US 287 AND FOOTHILLS PARKWAY	05/02/19	240.00	30.00	33.35	33.00
FSA0061-090		SH 6: CENTER LINE RUMBLE STRI	05/02/19	480.00	25.00	0.10	0.10
IM0252-456		I-25 COLORADO SPRINGS RAMP ME	05/16/19	120.00	30.00	31.17	31.00
FSA0703-454		EB I-70 AUX LANE WARD TO KIPL	05/16/19	640.00	30.00	29.95	30.00
CR300-248		CRAIG RESIDENCY ADA RAMPS	05/16/19	500.00	28.00	29.00	20.00
SHE0701-243		I-70 EXIT 26 DDI MODIFICATION	05/16/19	1,600.00	25.00	19.88	8.00
STMC430-020		ADA RAMPS DIVIDE ESB	05/23/19	512.00	12.00	30.00	30.00
FBR0063-057		US-6 F-09-K BRIDGE OVER CASTL	05/30/19	2,160.00	30.00	30.50	33.00
STRR200-257		ROAD CLOSURE GATES ON VARIOUS	05/30/19	400.00	20.00	29.42	27.50
ER145A-081		SH 145 MP 21 EMERGENCY ROCKFA	06/07/19	480.00	25.00	28.57	30.00
NHPP030A-036		SH 30 & TOWER RD IMPROVEMENTS	06/13/19	960.00	30.00	26.00	26.00
CR500-205		R5 GUARDRAIL END TREATMENT EA	06/13/19	1,500.00	25.00	29.10	29.10
FSA0142-067		SH 14 RUMBLESTRIPS: AULT TO S	06/13/19	390.00	20.00	0.10	0.10
STR 141A-040		R5 YEAR 4 BRDG PREV MAINT RAM	06/20/19	3,776.00	27.00	30.00	30.00
NHPP160A-030		US160 MM 43.2, 150.4, 156.3,	06/20/19	400.00	23.00	26.89	26.00

COLORADO DEPARTMENT OF TRANSPORTATION
 ITEM UNIT COSTS BY PROJECTS -- 2019 COST DATA

13:44 Wednesday, August 7, 2019 323

PROJECT NUMBER	ITEM NUMBER/ PROJECT LOCATION	ITEM DESCRIPTION/ PROJECT LOCATION	DATE LET	UNIT/ QUANTITY	ENGR. EST.	AVERAGE BID	AWARDED BID
=====	630-00000	Flagging		Hour =====			
C0502-085		US 50 MM 201.8 MONARCH AVALAN	06/27/19	100.00	33.00	37.50	38.50
		WEIGHTED AVERAGE FOR THE SECOND QUARTER		24,280.00	26.94	28.72	29.53
		WEIGHTED AVERAGE FOR THE YEAR		158,577.00	27.07	27.13	27.19
=====	630-00001	Pilot Car Operation		Hour =====			
ER119A-065		PR SH 119A BOULDER CANYON	01/03/19	800.00	50.00	64.49	65.00
STA119A-069		SH 119: NEDERLAND - EAST					
STR0132-021		SH 13-MOFFAT COUNTY-CR 3 SOUT	01/10/19	3,000.00	60.00	33.86	45.50
STR141A-047		SH 141 MP 120-143 MESA COUNTY	01/17/19	1,920.00	60.00	50.38	50.00
NHPP0821-107		SH 82 GLENWOOD SPRINGS TO CA	02/07/19	150.00	50.00	61.75	63.00
NHPP1601-076		US 160 MANCOS HILL (MP 40.000	02/21/19	800.00	40.00	37.30	43.00
NHPP0503-087		US 50 PASSING LANES EAST OF S	03/21/19	160.00	50.00	96.51	60.00
STA0131-070 HMA ALT		SH 13 CR 5 NORTH AND SOUTH	03/28/19	6,400.00	60.00	56.25	72.70
STA0131-070 PCCP ALT		SH 13 CR 5 NORTH AND SOUTH					
		WEIGHTED AVERAGE FOR THE FIRST QUARTER		13,230.00	57.95	49.25	56.89
STRR300-236		SH 92 and SH 133	04/04/19	720.00	60.00	60.00	60.00
NHPP2851-012		US 285 Antonito to Estrella C	05/02/19	360.00	46.00	43.33	50.00
		WEIGHTED AVERAGE FOR THE SECOND QUARTER		1,080.00	55.33	50.00	56.67
		WEIGHTED AVERAGE FOR THE YEAR		14,310.00	57.75	49.27	56.87
=====	630-00003	Uniformed Traf Ctrl		Hour =====			
NHPPR100-250		PACKAGE A (I-25 / I-70 / I-76	01/24/19	1,500.00	100.00	99.82	105.00
ER072A-040		PR SH72A FLOOD PERMANENT REPA	01/31/19	2,400.00	110.00	106.53	125.00
NHPP072A-041		PR SH72A FLOOD PERMANENT REPA					
NHPP0741-022		SH 74: I-70 TO CR 65 RESURFAC	02/14/19	408.00	100.00	129.34	141.15
SHER100-284		FY19 NORTH SIGNAL PKG	02/21/19	48.00	100.00	121.00	135.00
SHE2254-090		Colfax & I-225, Colfax & Cham	03/07/19	64.00	100.00	100.00	100.00
SHER100-308		MIDPOINT - SIGNAL CONST PACKA	03/21/19	96.00	100.00	140.00	145.00
		WEIGHTED AVERAGE FOR THE FIRST QUARTER		4,516.00	105.31	106.39	119.99
NHPP030A-035		US 285/SH30	04/04/19	2,000.00	102.00	75.00	75.00

PROJECT NUMBER	ITEM NUMBER/ PROJECT LOCATION	ITEM DESCRIPTION/ PROJECT LOCATION	DATE LET	UNIT/ QUANTITY	ENGR. EST.	AVERAGE BID	AWARDED BID
===== 630-00003 Uniformed Traf Ctrl Hour =====							
IM0252-472	I-25 CABLE BARRIER PHASE III	04/04/19	1,000.00	100.00	95.50	91.00	
FSA0252-468	I-25 AND PLUM CREEK IMPROVEME	04/18/19	16.00	120.00	124.40	141.60	
NHPP0703-445	I-70 WESTBOUND PEAK PERIOD SH	04/25/19	1,000.00	100.00	138.67	100.00	
FSA0703-454	EB I-70 AUX LANE WARD TO KIPL	05/16/19	200.00	90.00	97.09	90.00	
NHPP0703-442	I-70 SILVERPLUME SOUNDWALL AN	06/13/19	100.00	100.00	110.03	113.00	
NHPP030A-036	SH 30 & TOWER RD IMPROVEMENTS	06/13/19	8.00	100.00	150.00	150.00	
	WEIGHTED AVERAGE FOR THE SECOND QUARTER		4,324.00	100.54	107.70	86.44	
	WEIGHTED AVERAGE FOR THE YEAR		8,840.00	102.98	106.62	103.58	
===== 630-00004 Traf Ctrl Vehicle Each =====							
SHER100-284	FY19 NORTH SIGNAL PKG	02/21/19	2.00	5000.00	1160.00	1250.00	
	WEIGHTED AVERAGE FOR THE FIRST QUARTER		2.00	5000.00	1160.00	1250.00	
NHPP030A-035	US 285/SH30	04/04/19	2.00	6500.00	4000.00	4000.00	
	WEIGHTED AVERAGE FOR THE SECOND QUARTER		2.00	6500.00	4000.00	4000.00	
	WEIGHTED AVERAGE FOR THE YEAR		4.00	5750.00	1870.00	2625.00	
===== 630-00007 Traf Ctrl Inspection Day =====							
STAR200-242	R2 NORTH PROGRAM WALL REPAIRS	01/03/19	28.00	175.00	216.18	208.00	
IM0251-351	I-25 South of Pueblo MP 79.6	01/03/19	72.00	150.00	136.90	174.56	
FSA0142-068	SH 14 & WCR 33 INTERSECTION I	01/03/19	18.00	200.00	159.00	105.00	
SHER100-289	INTERSECTIONS @ SH83 & LONGS	01/03/19	26.00	200.00	127.00	125.00	
ER119A-065	PR SH 119A BOULDER CANYON	01/03/19	195.00	187.18	370.13	450.00	
STA119A-069	SH 119: NEDERLAND - EAST						
STR0132-021	SH 13-MOFFAT COUNTY-CR 3 SOUT	01/10/19	150.00	250.00	239.20	247.00	
FBR0341-087	US 34 OVER NORTH FORK CO RIVE	01/10/19	70.00	250.00	209.48	130.00	
STR141A-047	SH 141 MP 120-143 MESA COUNTY	01/17/19	32.00	300.00	303.51	260.00	
NHPP0701-241	I-70 TRUCK PARKING GARFIELD C	01/17/19	25.00	225.00	411.72	525.00	
STR0241-062	US 24 143.4 - 148	01/24/19	60.00	300.00	403.33	420.00	
ER072A-040	PR SH72A FLOOD PERMANENT REPA	01/31/19	120.00	250.00	201.22	220.00	
NHPP072A-041	PR SH72A FLOOD PERMANENT REPA						
STAM086-075	SH96A ABRIENDO - ORMAN SAFETY	01/31/19	56.00	50.00	55.67	51.00	
STA067A-038	SH 67 SEDALIA RESURFACING	01/31/19	10.00	175.00	173.60	150.00	
NHPP0821-107	SH 82 GLENWOOD SPRINGS TO CA	02/07/19	70.00	250.00	165.25	116.00	

PROJECT NUMBER	ITEM NUMBER/ PROJECT LOCATION	ITEM DESCRIPTION/ PROJECT LOCATION	DATE LET	UNIT/ QUANTITY	ENGR. EST.	AVERAGE BID	AWARDED BID
=====	630-00007	Traf Ctrl Inspection		Day =====			
NH2871-035		US 287 PASSING LANES SOUTH OF	02/07/19	48.00	180.00	238.57	220.50
ITSSW01-638		ETHERNET PHASE III (PRIMARYLY	02/07/19	20.00	190.00	85.00	5.00
NHPP145A-065		SH 145 PASSING LANES AT DEEP	02/14/19	85.00	150.00	150.98	90.00
NHPP0741-022		SH 74: I-70 TO CR 65 RESURFAC	02/14/19	40.00	200.00	226.83	195.40
NHPP1601-076		US 160 MANCOS HILL (MP 40.000	02/21/19	48.00	100.00	97.50	107.50
NHPP070A-028		FALL RIVER ROAD BRIDGE	02/21/19	60.00	250.00	259.23	420.00
SHER100-284		FY19 NORTH SIGNAL PKG	02/21/19	60.00	200.00	204.67	250.00
NHPP1601-073		US 160 PASSING LANE NORTH OF	03/07/19	78.00	200.00	106.00	112.00
FBR0253-247		I25 AT VINE DRIVE BRIDGE REPL	03/07/19	90.00	200.00	331.50	460.00
NHPP006A-058		US 6 LOVELAND PASS - I-70 (FY	03/07/19	45.00	200.00	304.11	408.22
C R100-315		R1 ADA CURB RAMPS - PH 5	03/07/19	24.00	220.00	275.00	150.00
SHE2254-090		Colfax & I-225, Colfax & Cham	03/07/19	40.00	175.00	125.00	150.00
NHPP0702-378		I-70 OFFICERS GULCH TO FRISCO	03/14/19	85.00	400.00	403.33	410.00
NHPP050A-033		US50 West of Delta EB Lanes R	03/14/19	55.00	300.00	285.00	300.00
NHPP0503-087		US 50 PASSING LANES EAST OF S	03/21/19	50.00	170.00	205.00	110.00
SHE 0252-481		I-25 RAMP METER INSTALLATION	03/21/19	40.00	150.00	239.33	225.00
SHER100-308		MIDPOINT - SIGNAL CONST PACKA	03/21/19	56.00	185.00	187.50	255.00
NHPP2254-089		I-225 RESURFACING FROM I-25 T	03/21/19	40.00	175.00	226.16	250.00
STM0242-077		US24 - 8TH ST TO WEST OF MANI	03/28/19	60.00	190.00	210.67	312.00
STA0131-070 HMA ALT		SH 13 CR 5 NORTH AND SOUTH	03/28/19	252.00	300.00	365.55	424.00
STA0131-070 PCCP ALT		SH 13 CR 5 NORTH AND SOUTH					
		WEIGHTED AVERAGE FOR THE FIRST QUARTER		2,208.00	222.15	262.35	266.72
NHPP030A-035		US 285/SH30	04/04/19	73.00	175.00	250.00	250.00
STRR300-236		SH 92 and SH 133	04/04/19	25.00	300.00	350.00	350.00
IM0252-472		I-25 CABLE BARRIER PHASE III	04/04/19	75.00	130.00	233.50	167.00
BR071A-020		REPLACEMENT OF STRUCTURE L-22	04/18/19	60.00	250.00	306.67	200.00
FSA0252-468		I-25 AND PLUM CREEK IMPROVEME	04/18/19	16.00	185.00	166.75	236.00
NHPP0703-445		I-70 WESTBOUND PEAK PERIOD SH	04/25/19	110.00	175.00	411.67	500.00
NHPP2851-012		US 285 Antonito to Estrella C	05/02/19	18.00	125.00	125.00	75.00
C2571-013		SH257 & 392:WINDSOR CURB RAMP	05/02/19	35.00	170.00	314.67	411.00
MTCE0641-103		MTCE R3 FY20 SH 64 RANGELY PE	05/02/19	20.00	200.00	162.50	30.00
FSA2873-190		US 287 AND FOOTHILLS PARKWAY	05/02/19	14.00	200.00	307.50	225.00
FSA0061-090		SH 6: CENTER LINE RUMBLE STRI	05/02/19	6.00	150.00	250.00	250.00
IM0252-456		I-25 COLORADO SPRINGS RAMP ME	05/16/19	69.00	180.00	173.83	159.00
FSA0703-454		EB I-70 AUX LANE WARD TO KIPL	05/16/19	40.00	190.00	243.74	100.00
CR300-248		CRAIG RESIDENCY ADA RAMPS	05/16/19	48.00	175.00	280.33	300.00
SHE0701-243		I-70 EXIT 26 DDI MODIFICATION	05/16/19	20.00	200.00	247.50	300.00
FTMC430-020		ADA RAMPS DIVIDE ESB	05/23/19	21.00	122.00	215.00	215.00
FBR0063-057		US-6 F-09-K BRIDGE OVER CASTL	05/30/19	37.00	300.00	320.00	415.00
ER145A-081		SH 145 MP 21 EMERGENCY ROCKFA	06/07/19	12.00	200.00	77.35	78.00
NHPP0703-442		I-70 SILVERPLUME SOUNDWALL AN	06/13/19	36.00	200.00	322.82	226.00
NHPP030A-036		SH 30 & TOWER RD IMPROVEMENTS	06/13/19	40.00	200.00	100.00	100.00
CR500-205		R5 GUARDRAIL END TREATMENT EA	06/13/19	12.00	220.00	250.00	250.00

PROJECT NUMBER	ITEM NUMBER/ PROJECT LOCATION	ITEM DESCRIPTION/ PROJECT LOCATION	DATE LET	UNIT/ QUANTITY	ENGR. EST.	AVERAGE BID	AWARDED BID
===== 630-00007 Traf Ctrl Inspection Day =====							
FSA0142-067	SH 14 RUMBLESTRIPS: AULT TO S	06/13/19	4.00	200.00	250.00	250.00	250.00
STR 141A-040	R5 YEAR 4 BRDG PREV MAINT RAM	06/20/19	65.00	160.00	107.50	150.00	150.00
NHPP160A-030	US160 MM 43.2, 150.4, 156.3,	06/20/19	30.00	300.00	218.34	220.00	220.00
C0502-085	US 50 MM 201.8 MONARCH AVALAN	06/27/19	4.00	700.00	381.50	478.00	478.00
WEIGHTED AVERAGE FOR THE SECOND QUARTER				890.00	193.77	267.62	249.28
WEIGHTED AVERAGE FOR THE YEAR				3,098.00	214.00	263.32	261.50
===== 630-00012 Traf Ctrl Mgmt Day =====							
STAR200-242	R2 NORTH PROGRAM WALL REPAIRS	01/03/19	111.00	700.00	815.21	733.00	733.00
IM0251-351	I-25 South of Pueblo MP 79.6	01/03/19	122.00	700.00	1157.46	1454.64	1454.64
NHPPR500-173	US 160_550 DURANGO SIGNALS OP	01/03/19	40.00	850.00	733.00	806.00	806.00
FSA0142-068	SH 14 & WCR 33 INTERSECTION I	01/03/19	15.00	700.00	710.00	420.00	420.00
SHER100-289	INTERSECTIONS @ SH83 & LONGS	01/03/19	69.00	850.00	588.80	575.00	575.00
ER119A-065	PR SH 119A BOULDER CANYON	01/03/19	380.00	765.00	1096.99	1000.00	1000.00
STA119A-069	SH 119: NEDERLAND - EAST						
STR0132-021	SH 13-MOFFAT COUNTY-CR 3 SOUT	01/10/19	250.00	750.00	764.20	904.00	904.00
FBR0341-087	US 34 OVER NORTH FORK CO RIVE	01/10/19	156.00	1800.00	654.15	676.00	676.00
MTCER300-247	MTCE R3 FY19 REGION ROUNDABOU	01/10/19	35.00	800.00	580.00	500.00	500.00
STR141A-047	SH 141 MP 120-143 MESA COUNTY	01/17/19	110.00	900.00	864.90	850.00	850.00
NHPP0701-241	I-70 TRUCK PARKING GARFIELD C	01/17/19	53.00	1000.00	904.81	715.00	715.00
MTCER400-368	REGION 4 FY 19 STENCIL NW	01/17/19	150.00	135.00	450.00	150.00	150.00
STR0241-062	US 24 143.4 - 148	01/24/19	140.00	900.00	1246.67	1200.00	1200.00
NHPPR100-250	PACKAGE A (I-25 / I-70 / I-76	01/24/19	121.00	850.00	1034.72	1127.00	1127.00
ER072A-040	PR SH72A FLOOD PERMANENT REPA	01/31/19	240.00	850.00	891.94	790.00	790.00
NHPP072A-041	PR SH72A FLOOD PERMANENT REPA						
STAM086-075	SH96A ABRIENDO - ORMAN SAFETY	01/31/19	126.00	400.00	620.67	590.00	590.00
STA067A-038	SH 67 SEDALIA RESURFACING	01/31/19	25.00	800.00	1113.00	1100.00	1100.00
NHPP0821-107	SH 82 GLENWOOD SPRINGS TO CA	02/07/19	170.00	1000.00	1000.00	1050.00	1050.00
NH2871-035	US 287 PASSING LANES SOUTH OF	02/07/19	120.00	950.00	722.12	682.50	682.50
ITSSW01-638	ETHERNET PHASE III (PRIMARILY	02/07/19	200.00	550.00	690.00	500.00	500.00
NHPP145A-065	SH 145 PASSING LANES AT DEEP	02/14/19	160.00	800.00	943.84	650.00	650.00
NHPP0741-022	SH 74: I-70 TO CR 65 RESURFAC	02/14/19	106.00	850.00	1013.82	640.50	640.50
NHPP1601-076	US 160 MANCOS HILL (MP 40.000	02/21/19	52.00	750.00	675.33	780.00	780.00
NHPP070A-028	FALL RIVER ROAD BRIDGE	02/21/19	135.00	1000.00	1162.10	980.00	980.00
SHER100-284	FY19 NORTH SIGNAL PKG	02/21/19	75.00	750.00	908.67	900.00	900.00
NHPP1601-073	US 160 PASSING LANE NORTH OF	03/07/19	193.00	800.00	754.50	809.00	809.00
FBR0253-247	I25 AT VINE DRIVE BRIDGE REPL	03/07/19	150.00	725.00	674.22	510.00	510.00
MPR200-253	R2 FY19 STENCIL PVMT MKG PROJ	03/07/19	40.00	600.00	415.00	150.00	150.00
NHPP006A-058	US 6 LOVELAND PASS - I-70 (FY	03/07/19	105.00	680.00	1144.30	1088.60	1088.60
C R100-315	R1 ADA CURB RAMPS - PH 5	03/07/19	60.00	650.00	1017.50	650.00	650.00
SHE2254-090	Colfax & I-225, Colfax & Cham	03/07/19	120.00	850.00	785.00	770.00	770.00
NHPP0702-378	I-70 OFFICERS GULCH TO FRISCO	03/14/19	99.00	1400.00	1008.33	1025.00	1025.00
NHPP050A-033	US50 West of Delta EB Lanes R	03/14/19	115.00	900.00	965.00	950.00	950.00

PROJECT NUMBER	ITEM NUMBER/ PROJECT LOCATION	ITEM DESCRIPTION/ PROJECT LOCATION	DATE LET	UNIT/ QUANTITY	ENGR. EST.	AVERAGE BID	AWARDED BID
===== 630-00012							
		Traf Ctrl Mgmt		Day			
NHPP0503-087		US 50 PASSING LANES EAST OF S	03/21/19	90.00	600.00	1050.00	1300.00
SHE 0252-481		I-25 RAMP METER INSTALLATION	03/21/19	110.00	850.00	1365.33	1475.00
SHER100-308		MIDPOINT - SIGNAL CONST PACKA	03/21/19	140.00	750.00	900.00	900.00
NHPP2254-089		I-225 RESURFACING FROM I-25 T	03/21/19	100.00	750.00	1218.35	900.00
STM0242-077		US24 - 8TH ST TO WEST OF MANI	03/28/19	154.00	815.00	1203.33	1310.00
STA0131-070 HMA ALT		SH 13 CR 5 NORTH AND SOUTH	03/28/19	558.00	900.00	1089.63	1180.00
STA0131-070 PCCP ALT		SH 13 CR 5 NORTH AND SOUTH					
		WEIGHTED AVERAGE FOR THE FIRST QUARTER		5,195.00	821.55	916.94	877.09
NHPP030A-035		US 285/SH30	04/04/19	145.00	850.00	1250.00	1250.00
STRR300-236		SH 92 and SH 133	04/04/19	40.00	900.00	1000.00	1000.00
IM0252-472		I-25 CABLE BARRIER PHASE III	04/04/19	177.00	1100.00	1200.00	1400.00
BR071A-020		REPLACEMENT OF STRUCTURE L-22	04/18/19	30.00	750.00	986.67	560.00
FSA0252-468		I-25 AND PLUM CREEK IMPROVEME	04/18/19	60.00	850.00	939.03	702.10
MTCE0702-387		MTCE R3 FY19 I-70 TAPE	04/18/19	20.00	200.00	416.67	450.00
MTCE0702-387		MTCE R3 FY19/20 REGION WIDE S	04/18/19	90.00	200.00	735.00	150.00
NHPP0703-445		I-70 WESTBOUND PEAK PERIOD SH	04/25/19	500.00	750.00	2300.00	1200.00
NHPP2851-012		US 285 Antonito to Estrella C	05/02/19	35.00	750.00	708.33	800.00
C2571-013		SH257 & 392:WINDSOR CURB RAMP	05/02/19	60.00	700.00	1106.00	700.00
MTCE0641-103		MTCE R3 FY20 SH 64 RANGELY PE	05/02/19	45.00	900.00	567.50	300.00
FSA2873-190		US 287 AND FOOTHILLS PARKWAY	05/02/19	34.00	850.00	1271.00	745.00
FSA0061-090		SH 6: CENTER LINE RUMBLE STRI	05/02/19	16.00	250.00	100.00	100.00
IM0252-456		I-25 COLORADO SPRINGS RAMP ME	05/16/19	172.00	700.00	1275.33	1276.00
FSA0703-454		EB I-70 AUX LANE WARD TO KIPL	05/16/19	80.00	900.00	1164.74	875.00
CR300-248		CRAIG RESIDENCY ADA RAMP	05/16/19	136.00	750.00	1056.00	1400.00
SHE0701-243		I-70 EXIT 26 DDI MODIFICATION	05/16/19	50.00	1000.00	827.50	1000.00
FTMC430-020		ADA RAMP DIVIDE ESB	05/23/19	32.00	733.00	600.00	600.00
FBR0063-057		US-6 F-09-K BRIDGE OVER CASTL	05/30/19	90.00	1010.00	1000.00	1075.00
STRR200-257		ROAD CLOSURE GATES ON VARIOUS	05/30/19	35.00	500.00	914.00	825.00
MPR200-255		FY20 R2 PAVEMENT MARKING PROJ	06/06/19	20.00	100.00	716.67	400.00
ER145A-081		SH 145 MP 21 EMERGENCY ROCKFA	06/07/19	30.00	800.00	831.42	969.00
NHPP0703-442		I-70 SILVERPLUME SOUNDWALL AN	06/13/19	88.00	850.00	819.84	793.00
NHPP030A-036		SH 30 & TOWER RD IMPROVEMENTS	06/13/19	40.00	900.00	300.00	300.00
CR500-205		R5 GUARDRAIL END TREATMENT EA	06/13/19	55.00	1100.00	750.00	750.00
FSA0142-067		SH 14 RUMBLESTRIPS: AULT TO S	06/13/19	13.00	150.00	100.00	100.00
STR 141A-040		R5 YEAR 4 BRDG PREV MAINT RAM	06/20/19	155.00	800.00	882.50	1000.00
NHPP160A-030		US160 MM 43.2, 150.4, 156.3,	06/20/19	72.00	800.00	560.00	570.00
C0502-085		US 50 MM 201.8 MONARCH AVALAN	06/27/19	5.00	1100.00	882.50	985.00
		WEIGHTED AVERAGE FOR THE SECOND QUARTER		2,325.00	786.54	1287.21	988.38
		WEIGHTED AVERAGE FOR THE YEAR		7,520.00	810.73	996.43	912.78
===== 630-00015							
		Uniformed Traf Ctrl Coordination		Hour			
SHER100-289		INTERSECTIONS @ SH83 & LONGS	01/03/19	10.00	87.00	45.60	16.00

COLORADO DEPARTMENT OF TRANSPORTATION
ITEM UNIT COSTS BY PROJECTS -- 2019 COST DATA

13:44 Wednesday, August 7, 2019 328

PROJECT NUMBER	ITEM NUMBER/ PROJECT LOCATION	ITEM DESCRIPTION/ PROJECT LOCATION	DATE LET	UNIT/ QUANTITY	ENGR. EST.	AVERAGE BID	AWARDED BID
=====	630-00015	Uniformed Traf Ctrl Coordination		Hour =====			
SHE 0252-481		I-25 RAMP METER INSTALLATION	03/21/19	30.00	75.00	34.17	15.00
	WEIGHTED AVERAGE FOR THE FIRST QUARTER			40.00	78.00	38.25	15.25
FSA2873-190		US 287 AND FOOTHILLS PARKWAY	05/02/19	8.00	125.00	62.50	115.00
IM0252-456		I-25 COLORADO SPRINGS RAMP ME	05/16/19	50.00	125.00	109.50	82.00
MPR200-255		FY20 R2 PAVEMENT MARKING PROJ	06/06/19	840.00	120.00	98.33	20.00
	WEIGHTED AVERAGE FOR THE SECOND QUARTER			898.00	120.32	98.74	24.30
	WEIGHTED AVERAGE FOR THE YEAR			938.00	118.52	95.75	23.91
=====	630-00017	Traffic Control Management (Special)		Day =====			
ER119A-065		PR SH 119A BOULDER CANYON	01/03/19	50.00	100.00	1111.47	1000.00
STA119A-069		SH 119: NEDERLAND - EAST					
	WEIGHTED AVERAGE FOR THE FIRST QUARTER			50.00	100.00	1111.47	1000.00
	WEIGHTED AVERAGE FOR THE YEAR			50.00	100.00	1111.47	1000.00
=====	630-00031	Courtesy Patrol		Hour =====			
STM0242-077		US24 - 8TH ST TO WEST OF MANI	03/28/19	600.00	75.00	141.67	125.00
	WEIGHTED AVERAGE FOR THE FIRST QUARTER			600.00	75.00	141.67	125.00
	WEIGHTED AVERAGE FOR THE YEAR			600.00	75.00	141.67	125.00
=====	630-00040	Develop Traf Incident Mgmt Plan		LUMP SUM =====			
STM0242-077		US24 - 8TH ST TO WEST OF MANI	03/28/19	1.00	1200.00	3100.00	500.00
	WEIGHTED AVERAGE FOR THE FIRST QUARTER			1.00	1200.00	3100.00	500.00
	WEIGHTED AVERAGE FOR THE YEAR			1.00	1200.00	3100.00	500.00
=====	630-00041	Implement Traf Incident Mgmt Plan		Month =====			
STM0242-077		US24 - 8TH ST TO WEST OF MANI	03/28/19	6.00	300.00	2766.67	300.00
	WEIGHTED AVERAGE FOR THE FIRST QUARTER			6.00	300.00	2766.67	300.00
	WEIGHTED AVERAGE FOR THE YEAR			6.00	300.00	2766.67	300.00

COLORADO DEPARTMENT OF TRANSPORTATION
ITEM UNIT COSTS BY PROJECTS -- 2019 COST DATA

13:44 Wednesday, August 7, 2019 329

PROJECT NUMBER	ITEM NUMBER/ PROJECT LOCATION	ITEM DESCRIPTION/ PROJECT LOCATION	DATE LET	UNIT/ QUANTITY	ENGR. EST.	AVERAGE BID	AWARDED BID
===== 630-80001		Flash Beacon (Port)		Each	=====		
STR0132-021		SH 13-MOFFAT COUNTY-CR 3 SOUT	01/10/19	4.00	1000.00	1688.00	2530.00
FBR0341-087		US 34 OVER NORTH FORK CO RIVE	01/10/19	4.00	550.00	672.20	120.70
NHPPR100-250		PACKAGE A (I-25 / I-70 / I-76	01/24/19	6.00	900.00	577.77	590.00
NH2871-035		US 287 PASSING LANES SOUTH OF	02/07/19	8.00	650.00	1286.37	1155.00
FBR0253-247		I25 AT VINE DRIVE BRIDGE REPL	03/07/19	16.00	1000.00	372.20	110.00
NHPP0702-378		I-70 OFFICERS GULCH TO FRISCO	03/14/19	4.00	775.00	1410.00	1230.00
NHPP0503-087		US 50 PASSING LANES EAST OF S	03/21/19	4.00	850.00	865.00	900.00
STM0242-077		US24 - 8TH ST TO WEST OF MANI	03/28/19	10.00	650.00	1033.33	300.00
STA0131-070 HMA ALT		SH 13 CR 5 NORTH AND SOUTH	03/28/19	12.00	1200.00	770.87	1450.00
STA0131-070 PCCP ALT		SH 13 CR 5 NORTH AND SOUTH					
		WEIGHTED AVERAGE FOR THE FIRST QUARTER		68.00	885.29	696.98	731.66
NHPP030A-035		US 285/SH30	04/04/19	12.00	1000.00	1100.00	1100.00
IM0252-472		I-25 CABLE BARRIER PHASE III	04/04/19	11.00	100.00	1200.00	900.00
NHPP0703-445		I-70 WESTBOUND PEAK PERIOD SH	04/25/19	25.00	1250.00	1376.06	118.00
MTCE0641-103		MTCE R3 FY20 SH 64 RANGELY PE	05/02/19	2.00	700.00	525.00	150.00
		WEIGHTED AVERAGE FOR THE SECOND QUARTER		50.00	915.00	1282.34	527.00
		WEIGHTED AVERAGE FOR THE YEAR		118.00	897.88	834.50	640.29
===== 630-80002		Flash Beacon (Solar)		Each	=====		
IM0251-351		I-25 South of Pueblo MP 79.6	01/03/19	20.00	850.00	389.19	232.74
ER119A-065		PR SH 119A BOULDER CANYON	01/03/19	2.00	2000.00	1256.54	1500.00
STA119A-069		SH 119: NEDERLAND - EAST					
ER072A-040		PR SH72A FLOOD PERMANENT REPA	01/31/19	6.00	1100.00	968.68	1100.00
NHPP072A-041		PR SH72A FLOOD PERMANENT REPA					
		WEIGHTED AVERAGE FOR THE FIRST QUARTER		28.00	985.71	720.15	509.10
BR071A-020		REPLACEMENT OF STRUCTURE L-22	04/18/19	16.00	725.00	473.33	200.00
FSA0252-468		I-25 AND PLUM CREEK IMPROVEME	04/18/19	4.00	1300.00	870.75	1180.00
		WEIGHTED AVERAGE FOR THE SECOND QUARTER		20.00	840.00	572.69	396.00
		WEIGHTED AVERAGE FOR THE YEAR		48.00	925.00	679.47	461.98

PROJECT NUMBER	ITEM NUMBER/ PROJECT LOCATION	ITEM DESCRIPTION/ PROJECT LOCATION	DATE LET	UNIT/ QUANTITY	ENGR. EST.	AVERAGE BID	AWARDED BID
===== 630-80305		Flagging Station Light		Each			
STR141A-047		SH 141 MP 120-143 MESA COUNTY	01/17/19	2.00	1200.00	3613.84	3500.00
MTCER400-368		REGION 4 FY 19 STENCIL NW	01/17/19	4.00	110.00	693.75	500.00
ER072A-040		PR SH72A FLOOD PERMANENT REPA	01/31/19	6.00	1500.00	2622.58	1100.00
NHPP072A-041		PR SH72A FLOOD PERMANENT REPA					
MPR200-253		R2 FY19 STENCIL PVMT MKG PROJ	03/07/19	4.00	1290.00	1083.33	500.00
		WEIGHTED AVERAGE FOR THE FIRST QUARTER		16.00	1062.50	2239.22	1100.00
SHE0701-243		I-70 EXIT 26 DDI MODIFICATION	05/16/19	2.00	2200.00	1040.00	1500.00
		WEIGHTED AVERAGE FOR THE SECOND QUARTER		2.00	2200.00	1040.00	1500.00
		WEIGHTED AVERAGE FOR THE YEAR		18.00	1188.89	2156.52	1144.44
===== 630-80335		Barricade (3 M-A) (Temp)		Each			
STAR200-242		R2 NORTH PROGRAM WALL REPAIRS	01/03/19	2.00	125.00	210.57	208.00
ER119A-065		PR SH 119A BOULDER CANYON	01/03/19	12.00	160.00	295.49	300.00
STA119A-069		SH 119: NEDERLAND - EAST					
STR0132-021		SH 13-MOFFAT COUNTY-CR 3 SOUT	01/10/19	4.00	240.00	237.94	152.00
STR0241-062		US 24 143.4 - 148	01/24/19	12.00	185.00	258.33	360.00
NHPPR100-250		PACKAGE A (I-25 / I-70 / I-76	01/24/19	20.00	125.00	95.92	95.00
STA067A-038		SH 67 SEDALIA RESURFACING	01/31/19	4.00	150.00	111.71	250.00
ITSSW01-638		ETHERNET PHASE III (PRIMARYLY	02/07/19	3.00	220.00	160.00	100.00
NHPP145A-065		SH 145 PASSING LANES AT DEEP	02/14/19	2.00	175.00	321.41	275.00
C R100-315		R1 ADA CURB RAMPS - PH 5	03/07/19	8.00	250.00	167.50	100.00
SHE2254-090		Colfax & I-225, Colfax & Cham	03/07/19	14.00	145.00	140.00	250.00
NHPP0702-378		I-70 OFFICERS GULCH TO FRISCO	03/14/19	2.00	150.00	268.75	256.25
SHE 0252-481		I-25 RAMP METER INSTALLATION	03/21/19	6.00	150.00	63.50	60.00
SHER100-308		MIDPOINT - SIGNAL CONST PACKA	03/21/19	10.00	185.00	120.50	195.00
NHPP2254-089		I-225 RESURFACING FROM I-25 T	03/21/19	4.00	135.00	120.21	250.00
STM0242-077		US24 - 8TH ST TO WEST OF MANI	03/28/19	8.00	150.00	175.00	55.00
STA0131-070 HMA ALT		SH 13 CR 5 NORTH AND SOUTH	03/28/19	4.00	250.00	372.25	424.00
STA0131-070 PCCP ALT		SH 13 CR 5 NORTH AND SOUTH					
		WEIGHTED AVERAGE FOR THE FIRST QUARTER		115.00	167.65	191.07	195.62
NHPP030A-035		US 285/SH30	04/04/19	20.00	130.00	210.00	210.00

PROJECT NUMBER	ITEM NUMBER/ PROJECT LOCATION	ITEM DESCRIPTION/ PROJECT LOCATION	DATE LET	UNIT/ QUANTITY	ENGR. EST.	AVERAGE BID	AWARDED BID
===== 630-80335							
		Barricade (3 M-A) (Temp)		Each			
IM0252-472		I-25 CABLE BARRIER PHASE III	04/04/19	3.00	80.00	167.50	85.00
FSA0252-468		I-25 AND PLUM CREEK IMPROVEME	04/18/19	12.00	125.00	158.50	118.00
NHPP0703-445		I-70 WESTBOUND PEAK PERIOD SH	04/25/19	10.00	200.00	269.92	118.00
C2571-013		SH257 & 392:WINDSOR CURB RAMP	05/02/19	9.00	150.00	149.00	110.00
MTCE0641-103		MTCE R3 FY20 SH 64 RANGELY PE	05/02/19	20.00	160.00	27.50	1.00
CR300-248		CRAIG RESIDENCY ADA RAMPS	05/16/19	8.00	170.00	152.00	5.00
STMC430-020		ADA RAMPS DIVIDE ESB	05/23/19	8.00	78.00	120.00	120.00
STR 141A-040		R5 YEAR 4 BRDG PREV MAINT RAM	06/20/19	12.00	360.00	82.50	100.00
		WEIGHTED AVERAGE FOR THE SECOND QUARTER		102.00	168.57	143.71	100.60
		WEIGHTED AVERAGE FOR THE YEAR		217.00	168.08	174.45	150.54
===== 630-80336							
		Barricade (3 M-B) (Temp)		Each			
NH2871-035		US 287 PASSING LANES SOUTH OF	02/07/19	16.00	250.00	232.86	210.00
NHPP070A-028		FALL RIVER ROAD BRIDGE	02/21/19	6.00	170.00	163.45	580.00
SHER100-284		FY19 NORTH SIGNAL PKG	02/21/19	4.00	250.00	293.33	320.00
FBR0253-247		I25 AT VINE DRIVE BRIDGE REPL	03/07/19	7.00	200.00	132.21	110.00
STM0242-077		US24 - 8TH ST TO WEST OF MANI	03/28/19	8.00	255.00	250.00	80.00
		WEIGHTED AVERAGE FOR THE FIRST QUARTER		41.00	230.73	190.85	232.44
NHPP030A-036		SH 30 & TOWER RD IMPROVEMENTS	06/13/19	4.00	250.00	60.00	60.00
		WEIGHTED AVERAGE FOR THE SECOND QUARTER		4.00	250.00	60.00	60.00
		WEIGHTED AVERAGE FOR THE YEAR		45.00	232.44	188.37	217.11
===== 630-80337							
		Barricade (3 M-C) (Temp)		Each			
STAR200-242		R2 NORTH PROGRAM WALL REPAIRS	01/03/19	5.00	100.00	317.14	208.00
FBR0341-087		US 34 OVER NORTH FORK CO RIVE	01/10/19	4.00	180.00	185.28	90.52
		WEIGHTED AVERAGE FOR THE FIRST QUARTER		9.00	135.56	224.06	155.79
FBR0063-057		US-6 F-09-K BRIDGE OVER CASTL	05/30/19	4.00	100.00	487.50	825.00
NHPP0703-442		I-70 SILVERPLUME SOUNDWALL AN	06/13/19	1.00	150.00	710.79	231.00
		WEIGHTED AVERAGE FOR THE SECOND QUARTER		5.00	110.00	599.15	706.20
		WEIGHTED AVERAGE FOR THE YEAR		14.00	126.43	344.09	352.36

PROJECT NUMBER	ITEM NUMBER/ PROJECT LOCATION	ITEM DESCRIPTION/ PROJECT LOCATION	DATE LET	UNIT/ QUANTITY	ENGR. EST.	AVERAGE BID	AWARDED BID
===== 630-80338 Barricade (3 M-D) (Temp) Each =====							
IM0251-351		I-25 South of Pueblo MP 79.6	01/03/19	8.00	550.00	328.99	290.93
NHPP050A-033		US50 West of Delta EB Lanes R	03/14/19	9.00	450.00	275.00	250.00
		WEIGHTED AVERAGE FOR THE FIRST QUARTER		17.00	497.06	304.28	269.26
BR071A-020							
		REPLACEMENT OF STRUCTURE L-22	04/18/19	28.00	365.00	156.33	25.00
		WEIGHTED AVERAGE FOR THE SECOND QUARTER		28.00	365.00	156.33	25.00
		WEIGHTED AVERAGE FOR THE YEAR		45.00	414.89	217.38	117.28
===== 630-80340 Pedestrian Barricade (ADA) Lin Foot =====							
STR0241-062		US 24 143.4 - 148	01/24/19	100.00	45.00	59.00	75.00
C R100-315		R1 ADA CURB RAMPS - PH 5	03/07/19	400.00	45.00	50.00	30.00
		WEIGHTED AVERAGE FOR THE FIRST QUARTER		500.00	45.00	52.45	39.00
C2571-013							
MTCE0641-103		SH257 & 392:WINDSOR CURB RAMP	05/02/19	300.00	32.00	18.43	10.30
FSA2873-190		MTCE R3 FY20 SH 64 RANGELY PE	05/02/19	50.00	50.00	51.00	60.00
CR300-248		US 287 AND FOOTHILLS PARKWAY	05/02/19	16.00	50.00	320.00	600.00
STMC430-020		CRAIG RESIDENCY ADA RAMPS	05/16/19	400.00	50.00	47.33	30.00
		ADA RAMPS DIVIDE ESB	05/23/19	125.00	16.00	15.00	15.00
		WEIGHTED AVERAGE FOR THE SECOND QUARTER		891.00	39.17	38.44	33.18
		WEIGHTED AVERAGE FOR THE YEAR		1,391.00	41.27	42.90	35.27
===== 630-80341 Const Traf Sign (A) Each =====							
STAR200-242		R2 NORTH PROGRAM WALL REPAIRS	01/03/19	20.00	50.00	62.16	57.00
IM0251-351		I-25 South of Pueblo MP 79.6	01/03/19	42.00	55.00	40.07	52.37
NHPPR500-173		US 160_550 DURANGO SIGNALS OP	01/03/19	84.00	35.00	33.50	33.00
FSA0142-068		SH 14 & WCR 33 INTERSECTION I	01/03/19	44.00	50.00	33.38	10.50
SHER100-289		INTERSECTIONS @ SH83 & LONGS	01/03/19	38.00	55.00	38.00	70.00
ER119A-065		PR SH 119A BOULDER CANYON	01/03/19	72.00	50.00	85.76	75.00

PROJECT NUMBER	ITEM NUMBER/ PROJECT LOCATION	ITEM DESCRIPTION/ PROJECT LOCATION	DATE LET	UNIT/ QUANTITY	ENGR. EST.	AVERAGE BID	AWARDED BID
=====	630-80341	Const Traf Sign (A)		Each =====			
STA119A-069		SH 119: NEDERLAND - EAST					
STR0132-021		SH 13-MOFFAT COUNTY-CR 3 SOUT	01/10/19	26.00	35.00	27.46	20.20
FBR0341-087		US 34 OVER NORTH FORK CO RIVE	01/10/19	46.00	55.00	24.87	12.07
MTCER300-247		MTCE R3 FY19 REGION ROUNDABOU	01/10/19	8.00	15.00	15.00	10.00
STR141A-047		SH 141 MP 120-143 MESA COUNTY	01/17/19	50.00	45.00	30.83	36.75
NHPP0701-241		I-70 TRUCK PARKING GARFIELD C	01/17/19	18.00	50.00	16.50	23.50
MTCER400-368		REGION 4 FY 19 STENCIL NW	01/17/19	80.00	11.00	32.50	10.00
STR0241-062		US 24 143.4 - 148	01/24/19	135.00	50.00	48.00	60.00
NHPPR100-250		PACKAGE A (I-25 / I-70 / I-76	01/24/19	60.00	60.00	92.38	95.00
ER072A-040		PR SH72A FLOOD PERMANENT REPA	01/31/19	50.00	65.00	80.82	60.70
NHPP072A-041		PR SH72A FLOOD PERMANENT REPA					
STAM086-075		SH96A ABRRIENDO - ORMAN SAFETY	01/31/19	32.00	54.55	55.67	51.00
STA067A-038		SH 67 SEDALIA RESURFACING	01/31/19	10.00	65.00	37.38	60.00
NHPP0821-107		SH 82 GLENWOOD SPRINGS TO CA	02/07/19	114.00	35.00	13.25	21.00
NH2871-035		US 287 PASSING LANES SOUTH OF	02/07/19	28.00	35.00	34.12	31.50
ITSSW01-638		ETHERNET PHASE III (PRIMARYLY	02/07/19	14.00	45.00	160.25	260.00
NHPP145A-065		SH 145 PASSING LANES AT DEEP	02/14/19	4.00	60.00	43.20	35.00
NHPP0741-022		SH 74: I-70 TO CR 65 RESURFAC	02/14/19	8.00	65.00	39.15	41.00
NHPP1601-076		US 160 MANCOS HILL (MP 40.000	02/21/19	20.00	30.00	40.38	37.75
NHPP070A-028		FALL RIVER ROAD BRIDGE	02/21/19	41.00	65.00	32.10	53.00
SHER100-284		FY19 NORTH SIGNAL PKG	02/21/19	29.00	65.00	44.00	50.00
NHPP1601-073		US 160 PASSING LANE NORTH OF	03/07/19	8.00	35.00	34.50	39.00
FBR0253-247		I25 AT VINE DRIVE BRIDGE REPL	03/07/19	157.00	55.00	49.29	11.00
MPR200-253		R2 FY19 STENCIL PVMT MKG PROJ	03/07/19	24.00	40.00	36.67	15.00
NHPP006A-058		US 6 LOVELAND PASS - I-70 (FY	03/07/19	6.00	75.00	45.66	65.32
C R100-315		R1 ADA CURB RAMPS - PH 5	03/07/19	91.00	60.00	60.00	40.00
SHE2254-090		Colfax & I-225, Colfax & Cham	03/07/19	33.00	55.00	37.50	65.00
NHPP0702-378		I-70 OFFICERS GULCH TO FRISCO	03/14/19	12.00	80.00	60.50	61.50
NHPP050A-033		US50 West of Delta EB Lanes R	03/14/19	47.00	50.00	36.33	45.00
NHPP0503-087		US 50 PASSING LANES EAST OF S	03/21/19	22.00	40.00	30.00	10.00
SHE 0252-481		I-25 RAMP METER INSTALLATION	03/21/19	32.00	45.00	34.67	33.00
SHER100-308		MIDPOINT - SIGNAL CONST PACKA	03/21/19	44.00	45.00	43.75	51.50
NHPP2254-089		I-225 RESURFACING FROM I-25 T	03/21/19	8.00	50.00	44.81	60.00
STM0242-077		US24 - 8TH ST TO WEST OF MANI	03/28/19	48.00	51.54	76.00	30.00
STA0131-070 HMA ALT		SH 13 CR 5 NORTH AND SOUTH	03/28/19	94.00	55.00	35.04	72.70
STA0131-070 PCCP ALT		SH 13 CR 5 NORTH AND SOUTH					
		WEIGHTED AVERAGE FOR THE FIRST QUARTER		1,699.00	48.55	50.01	42.29
NHPP030A-035		US 285/SH30	04/04/19	48.00	45.00	65.00	65.00
STRR300-236		SH 92 and SH 133	04/04/19	82.00	45.00	45.00	45.00
IM0252-472		I-25 CABLE BARRIER PHASE III	04/04/19	31.00	30.00	71.50	43.00
BR071A-020		REPLACEMENT OF STRUCTURE L-22	04/18/19	180.00	55.00	39.00	30.00
FSA0252-468		I-25 AND PLUM CREEK IMPROVEME	04/18/19	18.00	75.00	60.23	64.90
MTCE0702-387		MTCE R3 FY19 I-70 TAPE	04/18/19	8.00	10.00	26.67	45.00

PROJECT NUMBER	ITEM NUMBER/ PROJECT LOCATION	ITEM DESCRIPTION/ PROJECT LOCATION	DATE LET	UNIT/ QUANTITY	ENGR. EST.	AVERAGE BID	AWARDED BID
=====	630-80341	Const Traf Sign (A)		Each	=====	=====	=====
MTCER300-253		MTCE R3 FY19/20 REGION WIDE S	04/18/19	21.00	10.00	10.00	10.00
NHPP0703-445		I-70 WESTBOUND PEAK PERIOD SH	04/25/19	70.00	60.00	81.44	118.00
NHPP2851-012		US 285 Antonito to Estrella C	05/02/19	87.00	32.00	31.00	13.00
C2571-013		SH257 & 392:WINDSOR CURB RAMP	05/02/19	50.00	40.00	45.67	12.00
MTCE0641-103		MTCE R3 FY20 SH 64 RANGELY PE	05/02/19	25.00	85.00	8.50	5.00
FSA2873-190		US 287 AND FOOTHILLS PARKWAY	05/02/19	36.00	25.00	58.50	80.00
FSA0061-090		SH 6: CENTER LINE RUMBLE STRI	05/02/19	16.00	50.00	100.00	100.00
IM0252-456		I-25 COLORADO SPRINGS RAMP ME	05/16/19	56.00	45.00	74.50	82.00
FSA0703-454		EB I-70 AUX LANE WARD TO KIPL	05/16/19	14.00	75.00	68.42	20.00
CR300-248		CRAIG RESIDENCY ADA RAMPS	05/16/19	84.00	50.00	32.33	5.00
SHE0701-243		I-70 EXIT 26 DDI MODIFICATION	05/16/19	51.00	50.00	36.25	5.00
STMC430-020		ADA RAMPS DIVIDE ESB	05/23/19	170.00	58.79	60.00	60.00
FBR0063-057		US-6 F-09-K BRIDGE OVER CASTL	05/30/19	33.00	50.00	50.75	71.50
STRR200-257		ROAD CLOSURE GATES ON VARIOUS	05/30/19	24.00	40.00	50.75	38.50
MPR200-255		FY20 R2 PAVEMENT MARKING PROJ	06/06/19	16.00	10.00	28.33	10.00
ER145A-081		SH 145 MP 21 EMERGENCY ROCKFA	06/07/19	8.00	35.00	11.90	12.00
NHPP0703-442		I-70 SILVERPLUME SOUNDWALL AN	06/13/19	31.00	70.00	52.76	35.00
NHPP030A-036		SH 30 & TOWER RD IMPROVEMENTS	06/13/19	29.00	75.00	55.00	55.00
CR500-205		R5 GUARDRAIL END TREATMENT EA	06/13/19	10.00	50.00	25.00	25.00
FSA0142-067		SH 14 RUMBLESTRIPS: AULT TO S	06/13/19	16.00	100.00	100.00	100.00
STR 141A-040		R5 YEAR 4 BRDG PREV MAINT RAM	06/20/19	25.00	50.00	31.50	50.00
NHPP160A-030		US160 MM 43.2, 150.4, 156.3,	06/20/19	90.00	33.00	34.17	35.00
C0502-085		US 50 MM 201.8 MONARCH AVALAN	06/27/19	4.00	60.00	65.50	66.00
		WEIGHTED AVERAGE FOR THE SECOND QUARTER		1,333.00	49.06	46.87	43.78
		WEIGHTED AVERAGE FOR THE YEAR		3,032.00	48.78	49.07	42.96
=====	630-80342	Const Traf Sign (B)		Each	=====	=====	=====
STAR200-242		R2 NORTH PROGRAM WALL REPAIRS	01/03/19	30.00	60.00	145.76	213.00
IM0251-351		I-25 South of Pueblo MP 79.6	01/03/19	27.00	65.00	48.03	64.00
NHPPR500-173		US 160_550 DURANGO SIGNALS OP	01/03/19	24.00	40.00	41.00	33.00
FSA0142-068		SH 14 & WCR 33 INTERSECTION I	01/03/19	53.00	60.00	39.13	10.50
SHER100-289		INTERSECTIONS @ SH83 & LONGS	01/03/19	58.00	105.00	99.40	125.00
ER119A-065		PR SH 119A BOULDER CANYON	01/03/19	204.00	55.00	97.18	80.00
STA119A-069		SH 119: NEDERLAND - EAST					
STR0132-021		SH 13-MOFFAT COUNTY-CR 3 SOUT	01/10/19	96.00	40.00	37.24	30.30
FBR0341-087		US 34 OVER NORTH FORK CO RIVE	01/10/19	12.00	80.00	35.54	12.07
MTCER300-247		MTCE R3 FY19 REGION ROUNDABOU	01/10/19	18.00	15.00	12.60	10.00
STR141A-047		SH 141 MP 120-143 MESA COUNTY	01/17/19	8.00	55.00	50.05	70.00
NHPP0701-241		I-70 TRUCK PARKING GARFIELD C	01/17/19	30.00	65.00	25.80	17.00
MTCER400-368		REGION 4 FY 19 STENCIL NW	01/17/19	24.00	11.00	35.00	10.00
STR0241-062		US 24 143.4 - 148	01/24/19	2.00	60.00	90.67	120.00
NHPPR100-250		PACKAGE A (I-25 / I-70 / I-76	01/24/19	41.00	100.00	93.20	95.00
ER072A-040		PR SH72A FLOOD PERMANENT REPA	01/31/19	70.00	100.00	140.01	225.00

PROJECT NUMBER	ITEM NUMBER/ PROJECT LOCATION	ITEM DESCRIPTION/ PROJECT LOCATION	DATE LET	UNIT/ QUANTITY	ENGR. EST.	AVERAGE BID	AWARDED BID
=====	630-80342	Const Traf Sign (B)		Each =====			
NHPP072A-041		PR SH72A FLOOD PERMANENT REPA					
STAM086-075		SH96A ABRIENDO - ORMAN SAFETY	01/31/19	41.00	79.19	66.67	61.00
STA067A-038		SH 67 SEDALIA RESURFACING	01/31/19	41.00	100.00	58.09	70.00
NHPP0821-107		SH 82 GLENWOOD SPRINGS TO CA	02/07/19	154.00	40.00	13.25	21.00
NH2871-035		US 287 PASSING LANES SOUTH OF	02/07/19	90.00	40.00	39.47	36.75
ITSSW01-638		ETHERNET PHASE III (PRIMARILY	02/07/19	38.00	60.00	130.75	190.00
NHPP145A-065		SH 145 PASSING LANES AT DEEP	02/14/19	48.00	60.00	43.60	35.00
NHPP0741-022		SH 74: I-70 TO CR 65 RESURFAC	02/14/19	48.00	110.00	48.38	52.00
NHPP1601-076		US 160 MANCOS HILL (MP 40.000	02/21/19	91.00	35.00	40.38	37.75
NHPP070A-028		FALL RIVER ROAD BRIDGE	02/21/19	22.00	110.00	38.48	63.00
SHER100-284		FY19 NORTH SIGNAL PKG	02/21/19	29.00	120.00	54.67	60.00
NHPP1601-073		US 160 PASSING LANE NORTH OF	03/07/19	40.00	50.00	39.50	39.00
FBR0253-247		I25 AT VINE DRIVE BRIDGE REPL	03/07/19	19.00	60.00	581.91	1200.00
MPR200-253		R2 FY19 STENCIL PVMT MKG PROJ	03/07/19	48.00	50.00	36.67	15.00
NHPP006A-058		US 6 LOVELAND PASS - I-70 (FY	03/07/19	38.00	125.00	50.38	70.76
C R100-315		R1 ADA CURB RAMPS - PH 5	03/07/19	33.00	100.00	91.50	48.00
SHE2254-090		Colfax & I-225, Colfax & Cham	03/07/19	38.00	110.00	47.50	75.00
NHPP0702-378		I-70 OFFICERS GULCH TO FRISCO	03/14/19	64.00	85.00	67.21	66.62
NHPP050A-033		US50 West of Delta EB Lanes R	03/14/19	71.00	60.00	42.67	50.00
NHPP0503-087		US 50 PASSING LANES EAST OF S	03/21/19	58.00	55.00	36.00	12.00
SHE 0252-481		I-25 RAMP METER INSTALLATION	03/21/19	18.00	85.00	40.50	38.00
SHER100-308		MIDPOINT - SIGNAL CONST PACKA	03/21/19	66.00	60.00	150.00	264.00
NHPP2254-089		I-225 RESURFACING FROM I-25 T	03/21/19	62.00	90.00	52.38	70.00
STM0242-077		US24 - 8TH ST TO WEST OF MANI	03/28/19	149.00	55.00	86.67	35.00
STA0131-070 HMA ALT		SH 13 CR 5 NORTH AND SOUTH	03/28/19	184.00	65.00	36.05	78.80
STA0131-070 PCCP ALT		SH 13 CR 5 NORTH AND SOUTH					
		WEIGHTED AVERAGE FOR THE FIRST QUARTER		2,187.00	65.14	82.54	77.79
NHPP030A-035		US 285/SH30	04/04/19	84.00	90.00	75.00	75.00
STRR300-236		SH 92 and SH 133	04/04/19	102.00	50.00	50.00	50.00
IM0252-472		I-25 CABLE BARRIER PHASE III	04/04/19	23.00	40.00	91.50	73.00
BR071A-020		REPLACEMENT OF STRUCTURE L-22	04/18/19	17.00	62.00	64.00	70.00
FSA0252-468		I-25 AND PLUM CREEK IMPROVEME	04/18/19	31.00	110.00	111.63	206.50
MTCE0702-387		MTCE R3 FY19 I-70 TAPE	04/18/19	48.00	10.00	26.67	45.00
MTCE0702-387		MTCE R3 FY19/20 REGION WIDE S	04/18/19	15.00	10.00	10.00	10.00
NHPP0703-445		I-70 WESTBOUND PEAK PERIOD SH	04/25/19	80.00	120.00	196.40	118.00
NHPP2851-012		US 285 Antonito to Estrella C	05/02/19	30.00	42.00	38.33	25.00
C2571-013		SH257 & 392:WINDSOR CURB RAMP	05/02/19	36.00	60.00	73.33	12.50
MTCE0641-103		MTCE R3 FY20 SH 64 RANGELY PE	05/02/19	24.00	85.00	14.50	5.00
FSA2873-190		US 287 AND FOOTHILLS PARKWAY	05/02/19	34.00	35.00	68.50	90.00
FSA0061-090		SH 6: CENTER LINE RUMBLE STRI	05/02/19	28.00	65.00	100.00	100.00
IM0252-456		I-25 COLORADO SPRINGS RAMP ME	05/16/19	20.00	50.00	92.17	108.00
FSA0703-454		EB I-70 AUX LANE WARD TO KIPL	05/16/19	22.00	100.00	99.08	50.00
CR300-248		CRAIG RESIDENCY ADA RAMPS	05/16/19	24.00	70.00	42.67	5.00

PROJECT NUMBER	ITEM NUMBER/ PROJECT LOCATION	ITEM DESCRIPTION/ PROJECT LOCATION	DATE LET	UNIT/ QUANTITY	ENGR. EST.	AVERAGE BID	AWARDED BID
===== 630-80342							
		Const Traf Sign (B)		Each			
STMC430-020		ADA RAMPS DIVIDE ESB	05/23/19	45.00	25.00	66.00	66.00
FBR0063-057		US-6 F-09-K BRIDGE OVER CASTL	05/30/19	27.00	65.00	53.50	77.00
STRR200-257		ROAD CLOSURE GATES ON VARIOUS	05/30/19	100.00	50.00	71.75	49.50
MPR200-255		FY20 R2 PAVEMENT MARKING PROJ	06/06/19	26.00	10.00	28.33	10.00
ER145A-081		SH 145 MP 21 EMERGENCY ROCKFA	06/07/19	29.00	50.00	11.90	12.00
NHPP0703-442		I-70 SILVERPLUME SOUNDWALL AN	06/13/19	27.00	100.00	57.11	40.00
NHPP030A-036		SH 30 & TOWER RD IMPROVEMENTS	06/13/19	29.00	100.00	65.00	65.00
CR500-205		R5 GUARDRAIL END TREATMENT EA	06/13/19	78.00	60.00	38.00	38.00
FSA0142-067		SH 14 RUMBLESTRIPS: AULT TO S	06/13/19	28.00	100.00	100.00	100.00
STR 141A-040		R5 YEAR 4 BRDG PREV MAINT RAM	06/20/19	102.00	60.00	31.50	50.00
NHPP160A-030		US160 MM 43.2, 150.4, 156.3,	06/20/19	32.00	36.00	44.72	45.00
C0502-085		US 50 MM 201.8 MONARCH AVALAN	06/27/19	6.00	70.00	172.50	110.00
		WEIGHTED AVERAGE FOR THE SECOND QUARTER		1,147.00	62.76	71.33	60.61
		WEIGHTED AVERAGE FOR THE YEAR		3,334.00	64.32	80.10	71.71
===== 630-80343							
		Const Traf Sign (C)		Each			
IM0251-351		I-25 South of Pueblo MP 79.6	01/03/19	53.00	85.00	57.24	75.64
SHER100-289		INTERSECTIONS @ SH83 & LONGS	01/03/19	4.00	120.00	117.40	165.00
ER119A-065		PR SH 119A BOULDER CANYON	01/03/19	2.00	70.00	126.89	200.00
STA119A-069		SH 119: NEDERLAND - EAST					
STR0132-021		SH 13-MOFFAT COUNTY-CR 3 SOUT	01/10/19	4.00	45.00	39.26	40.40
NHPPR100-250		PACKAGE A (I-25 / I-70 / I-76	01/24/19	4.00	100.00	95.92	95.00
STAM086-075		SH96A ABRIENDO - ORMAN SAFETY	01/31/19	4.00	76.89	68.33	62.00
STA067A-038		SH 67 SEDALIA RESURFACING	01/31/19	6.00	115.00	74.76	120.00
NHPP0821-107		SH 82 GLENWOOD SPRINGS TO CA	02/07/19	16.00	45.00	18.75	21.00
ITSSW01-638		ETHERNET PHASE III (PRIMARILY	02/07/19	4.00	80.00	291.25	500.00
NHPP145A-065		SH 145 PASSING LANES AT DEEP	02/14/19	2.00	60.00	47.69	40.00
NHPP070A-028		FALL RIVER ROAD BRIDGE	02/21/19	9.00	100.00	45.06	74.00
SHER100-284		FY19 NORTH SIGNAL PKG	02/21/19	4.00	140.00	65.00	70.00
NHPP1601-073		US 160 PASSING LANE NORTH OF	03/07/19	2.00	60.00	42.50	45.00
MPR200-253		R2 FY19 STENCIL PVMT MKG PROJ	03/07/19	24.00	60.00	36.67	15.00
SHE2254-090		Colfax & I-225, Colfax & Cham	03/07/19	4.00	125.00	65.00	100.00
NHPP0702-378		I-70 OFFICERS GULCH TO FRISCO	03/14/19	48.00	90.00	72.25	71.75
NHPP0503-087		US 50 PASSING LANES EAST OF S	03/21/19	2.00	70.00	61.00	50.00
SHER100-308		MIDPOINT - SIGNAL CONST PACKA	03/21/19	11.00	75.00	155.00	264.00
NHPP2254-089		I-225 RESURFACING FROM I-25 T	03/21/19	14.00	100.00	59.63	80.00
STA0131-070 HMA ALT		SH 13 CR 5 NORTH AND SOUTH	03/28/19	12.00	75.00	37.07	84.90
STA0131-070 PCCP ALT		SH 13 CR 5 NORTH AND SOUTH					
		WEIGHTED AVERAGE FOR THE FIRST QUARTER		229.00	82.83	64.50	84.61
NHPP030A-035		US 285/SH30	04/04/19	10.00	120.00	85.00	85.00

PROJECT NUMBER	ITEM NUMBER/ PROJECT LOCATION	ITEM DESCRIPTION/ PROJECT LOCATION	DATE LET	UNIT/ QUANTITY	ENGR. EST.	AVERAGE BID	AWARDED BID
===== 630-80343							
		Const Traf Sign (C)		Each			
STRR300-236		SH 92 and SH 133	04/04/19	12.00	55.00	60.00	60.00
IM0252-472		I-25 CABLE BARRIER PHASE III	04/04/19	10.00	50.00	102.50	90.00
MTCE0702-387		MTCE R3 FY19 I-70 TAPE	04/18/19	8.00	10.00	26.67	45.00
NHPP0703-445		I-70 WESTBOUND PEAK PERIOD SH	04/25/19	55.00	130.00	196.40	118.00
IM0252-456		I-25 COLORADO SPRINGS RAMP ME	05/16/19	4.00	65.00	95.50	108.00
FSA0703-454		EB I-70 AUX LANE WARD TO KIPL	05/16/19	2.00	120.00	104.19	60.00
STRR200-257		ROAD CLOSURE GATES ON VARIOUS	05/30/19	4.00	55.00	71.75	49.50
MPR200-255		FY20 R2 PAVEMENT MARKING PROJ	06/06/19	8.00	10.00	28.33	10.00
NHPP0703-442		I-70 SILVERPLUME SOUNDWALL AN	06/13/19	12.00	110.00	63.88	43.00
NHPP030A-036		SH 30 & TOWER RD IMPROVEMENTS	06/13/19	4.00	120.00	75.00	75.00
STR 141A-040		R5 YEAR 4 BRDG PREV MAINT RAM	06/20/19	10.00	65.00	40.00	60.00
C0502-085		US 50 MM 201.8 MONARCH AVALAN	06/27/19	4.00	150.00	194.50	154.00
		WEIGHTED AVERAGE FOR THE SECOND QUARTER		143.00	93.99	118.53	85.19
		WEIGHTED AVERAGE FOR THE YEAR		372.00	87.12	83.45	84.84
===== 630-80344							
		Const Traf Sign (Spec)		Sq Foot			
ER119A-065		PR SH 119A BOULDER CANYON	01/03/19	210.00	30.00	26.91	30.00
STA119A-069		SH 119: NEDERLAND - EAST					
STR0132-021		SH 13-MOFFAT COUNTY-CR 3 SOUT	01/10/19	132.00	22.00	37.96	30.30
ER072A-040		PR SH72A FLOOD PERMANENT REPA	01/31/19	320.00	30.00	15.61	22.10
NHPP072A-041		PR SH72A FLOOD PERMANENT REPA					
NHPP0821-107		SH 82 GLENWOOD SPRINGS TO CA	02/07/19	128.00	15.00	18.75	21.00
NH2871-035		US 287 PASSING LANES SOUTH OF	02/07/19	64.00	20.00	21.34	19.95
NHPP070A-028		FALL RIVER ROAD BRIDGE	02/21/19	24.00	30.00	21.28	24.00
SHER100-284		FY19 NORTH SIGNAL PKG	02/21/19	32.00	30.00	27.67	30.00
FBR0253-247		I25 AT VINE DRIVE BRIDGE REPL	03/07/19	55.00	20.00	36.83	60.00
NHPP0702-378		I-70 OFFICERS GULCH TO FRISCO	03/14/19	96.00	85.00	26.87	25.62
STA0131-070 HMA ALT		SH 13 CR 5 NORTH AND SOUTH	03/28/19	80.00	25.00	24.13	24.20
STA0131-070 PCCP ALT		SH 13 CR 5 NORTH AND SOUTH					
		WEIGHTED AVERAGE FOR THE FIRST QUARTER		1,141.00	30.63	22.57	26.88
===== 630-80343							
STRR300-236		SH 92 and SH 133	04/04/19	192.00	25.00	20.00	20.00
BR071A-020		REPLACEMENT OF STRUCTURE L-22	04/18/19	64.00	25.00	25.00	15.00
NHPP0703-445		I-70 WESTBOUND PEAK PERIOD SH	04/25/19	200.00	30.00	54.71	118.00
FBR0063-057		US-6 F-09-K BRIDGE OVER CASTL	05/30/19	60.00	30.00	21.00	22.00
STR 141A-040		R5 YEAR 4 BRDG PREV MAINT RAM	06/20/19	72.00	30.00	40.00	60.00
		WEIGHTED AVERAGE FOR THE SECOND QUARTER		588.00	27.82	39.86	57.89
		WEIGHTED AVERAGE FOR THE YEAR		1,729.00	29.67	24.89	37.68

PROJECT NUMBER	ITEM NUMBER/ PROJECT LOCATION	ITEM DESCRIPTION/ PROJECT LOCATION	DATE LET	UNIT/ QUANTITY	ENGR. EST.	AVERAGE BID	AWARDED BID
===== 630-80348		Const Info Sign		Each	=====	=====	=====
STM0242-077	US24 - 8TH ST TO WEST OF MANI	03/28/19		2.00	250.00	223.33	220.00
	WEIGHTED AVERAGE FOR THE FIRST QUARTER			2.00	250.00	223.33	220.00
	WEIGHTED AVERAGE FOR THE YEAR			2.00	250.00	223.33	220.00
===== 630-80350		Vert Panel		Each	=====	=====	=====
IM0251-351	I-25 South of Pueblo MP 79.6	01/03/19		75.00	40.00	36.63	34.91
FSA0142-068	SH 14 & WCR 33 INTERSECTION I	01/03/19		10.00	30.00	15.63	10.50
ER119A-065	PR SH 119A BOULDER CANYON	01/03/19		150.00	20.00	22.42	20.00
STA119A-069	SH 119: NEDERLAND - EAST						
NH2871-035	US 287 PASSING LANES SOUTH OF	02/07/19		30.00	30.00	39.97	36.75
NHPP145A-065	SH 145 PASSING LANES AT DEEP	02/14/19		200.00	10.00	24.38	25.00
NHPP1601-076	US 160 MANCOS HILL (MP 40.000)	02/21/19		30.00	5.00	29.80	27.00
SHER100-284	FY19 NORTH SIGNAL PKG	02/21/19		24.00	45.00	37.00	40.00
NHPP1601-073	US 160 PASSING LANE NORTH OF	03/07/19		100.00	50.00	26.00	28.00
NHPP050A-033	US50 West of Delta EB Lanes R	03/14/19		300.00	25.00	15.88	20.00
NHPP2254-089	I-225 RESURFACING FROM I-25 T	03/21/19		100.00	40.00	26.07	40.00
	WEIGHTED AVERAGE FOR THE FIRST QUARTER			1,019.00	26.43	23.77	25.90
FSA2873-190	US 287 AND FOOTHILLS PARKWAY	05/02/19		50.00	25.00	42.50	60.00
CR500-205	R5 GUARDRAIL END TREATMENT EA	06/13/19		20.00	45.00	25.00	25.00
STR 141A-040	R5 YEAR 4 BRDG PREV MAINT RAM	06/20/19		75.00	30.00	31.50	50.00
	WEIGHTED AVERAGE FOR THE SECOND QUARTER			145.00	30.34	35.09	50.00
	WEIGHTED AVERAGE FOR THE YEAR			1,164.00	26.92	24.45	28.91
===== 630-80353		Vert Panel (Light) (F)		Each	=====	=====	=====
NHPP050A-033	US50 West of Delta EB Lanes R	03/14/19		25.00	35.00	21.83	20.00
	WEIGHTED AVERAGE FOR THE FIRST QUARTER			25.00	35.00	21.83	20.00
	WEIGHTED AVERAGE FOR THE YEAR			25.00	35.00	21.83	20.00
===== 630-80354		Vert Panel (Light) (SB)		Each	=====	=====	=====
IM0251-351	I-25 South of Pueblo MP 79.6	01/03/19		75.00	75.00	42.86	40.73

COLORADO DEPARTMENT OF TRANSPORTATION
 ITEM UNIT COSTS BY PROJECTS -- 2019 COST DATA

13:44 Wednesday, August 7, 2019 339

PROJECT NUMBER	ITEM NUMBER/ PROJECT LOCATION	ITEM DESCRIPTION/ PROJECT LOCATION	DATE LET	UNIT/ QUANTITY	ENGR. EST.	AVERAGE BID	AWARDED BID
===== 630-80354		Vert Panel (Light) (SB)		Each =====			
NHPP050A-033		US50 West of Delta EB Lanes R	03/14/19	25.00	35.00	21.83	20.00
	WEIGHTED AVERAGE FOR THE FIRST QUARTER			100.00	65.00	38.65	35.55
	WEIGHTED AVERAGE FOR THE YEAR			100.00	65.00	38.65	35.55
===== 630-80355		Port Mesg Panel		Each =====			
STAR200-242		R2 NORTH PROGRAM WALL REPAIRS	01/03/19	4.00	5000.00	5185.30	3640.00
IM0251-351		I-25 South of Pueblo MP 79.6	01/03/19	6.00	5000.00	6752.84	6400.43
NHPPR500-173		US 160_550 DURANGO SIGNALS OP	01/03/19	4.00	2500.00	2096.50	1468.00
FSA0142-068		SH 14 & WCR 33 INTERSECTION I	01/03/19	4.00	1000.00	1181.25	525.00
SHER100-289		INTERSECTIONS @ SH83 & LONGS	01/03/19	3.00	7500.00	2035.00	2200.00
ER119A-065		PR SH 119A BOULDER CANYON	01/03/19	16.00	3500.00	8277.33	6000.00
STA119A-069		SH 119: NEDERLAND - EAST					
FBR0341-087		US 34 OVER NORTH FORK CO RIVE	01/10/19	2.00	13000.00	3740.37	1206.99
STR0241-062		US 24 143.4 - 148	01/24/19	4.00	6000.00	7201.67	8000.00
NHPPR100-250		PACKAGE A (I-25 / I-70 / I-76	01/24/19	5.00	5000.00	3443.04	3500.00
ER072A-040		PR SH72A FLOOD PERMANENT REPA	01/31/19	6.00	6000.00	8527.86	11000.00
NHPP072A-041		PR SH72A FLOOD PERMANENT REPA					
STAM086-075		SH96A ABRIENDO - ORMAN SAFETY	01/31/19	2.00	4000.00	6758.33	6375.00
STA067A-038		SH 67 SEDALIA RESURFACING	01/31/19	5.00	6000.00	910.18	1700.00
NH2871-035		US 287 PASSING LANES SOUTH OF	02/07/19	4.00	5500.00	12036.84	11466.00
NHPP145A-065		SH 145 PASSING LANES AT DEEP	02/14/19	2.00	5000.00	4828.10	3000.00
NHPP0741-022		SH 74: I-70 TO CR 65 RESURFAC	02/14/19	2.00	6500.00	4374.48	2985.00
NHPP1601-076		US 160 MANCOS HILL (MP 40.000	02/21/19	3.00	2000.00	1976.67	2000.00
NHPP070A-028		FALL RIVER ROAD BRIDGE	02/21/19	4.00	7000.00	3945.80	3700.00
SHER100-284		FY19 NORTH SIGNAL PKG	02/21/19	4.00	7000.00	5883.33	6500.00
NHPP1601-073		US 160 PASSING LANE NORTH OF	03/07/19	2.00	4000.00	2925.00	3350.00
FBR0253-247		I25 AT VINE DRIVE BRIDGE REPL	03/07/19	6.00	6500.00	3505.88	550.00
NHPP006A-058		US 6 LOVELAND PASS - I-70 (FY	03/07/19	2.00	6000.00	7037.95	7075.89
SHE2254-090		Colfax & I-225, Colfax & Cham	03/07/19	2.00	6000.00	4250.00	7500.00
NHPP0702-378		I-70 OFFICERS GULCH TO FRISCO	03/14/19	2.00	5000.00	7375.00	5125.00
NHPP050A-033		US50 West of Delta EB Lanes R	03/14/19	3.00	5500.00	6000.00	4000.00
NHPP0503-087		US 50 PASSING LANES EAST OF S	03/21/19	4.00	5000.00	6000.00	9000.00
SHE 0252-481		I-25 RAMP METER INSTALLATION	03/21/19	4.00	4500.00	3999.33	3745.00
SHER100-308		MIDPOINT - SIGNAL CONST PACKA	03/21/19	2.00	5000.00	3612.53	4500.05
NHPP2254-089		I-225 RESURFACING FROM I-25 T	03/21/19	4.00	4000.00	6296.87	10000.00
STM0242-077		US24 - 8TH ST TO WEST OF MANI	03/28/19	6.00	3233.33	10606.67	3720.00
STA0131-070 HMA ALT		SH 13 CR 5 NORTH AND SOUTH	03/28/19	6.00	7000.00	4405.16	8180.00
STA0131-070 PCCP ALT		SH 13 CR 5 NORTH AND SOUTH					
	WEIGHTED AVERAGE FOR THE FIRST QUARTER			123.00	5052.03	6025.32	5129.79
NHPP030A-035		US 285/SH30	04/04/19	6.00	4200.00	6500.00	6500.00

PROJECT NUMBER	ITEM NUMBER/ PROJECT LOCATION	ITEM DESCRIPTION/ PROJECT LOCATION	DATE LET	UNIT/ QUANTITY	ENGR. EST.	AVERAGE BID	AWARDED BID
===== 630-80355							
		Port Mesq Panel		Each			
STRR300-236		SH 92 and SH 133	04/04/19	6.00	8000.00	2750.00	2750.00
IM0252-472		I-25 CABLE BARRIER PHASE III	04/04/19	2.00	4500.00	10000.00	7000.00
BR071A-020		REPLACEMENT OF STRUCTURE L-22	04/18/19	5.00	2000.00	5000.00	3000.00
FSA0252-468		I-25 AND PLUM CREEK IMPROVEME	04/18/19	4.00	6000.00	4340.00	4130.00
NHPP0703-445		I-70 WESTBOUND PEAK PERIOD SH	04/25/19	5.00	5500.00	15143.98	5933.00
C2571-013		SH257 & 392:WINDSOR CURB RAMP	05/02/19	4.00	3400.00	2691.67	525.00
FSA02873-190		US 287 AND FOOTHILLS PARKWAY	05/02/19	2.00	3500.00	2160.00	2350.00
FSA0061-090		SH 6: CENTER LINE RUMBLE STRI	05/02/19	2.00	3000.00	2500.00	2500.00
IM0252-456		I-25 COLORADO SPRINGS RAMP ME	05/16/19	4.00	5000.00	10149.67	13399.00
FSA0703-454		EB I-70 AUX LANE WARD TO KIPL	05/16/19	2.00	6000.00	5087.90	2000.00
CR300-248		CRAIG RESIDENCY ADA RAMPS	05/16/19	3.00	3000.00	4603.00	4000.00
SHE0701-243		I-70 EXIT 26 DDI MODIFICATION	05/16/19	2.00	10.00	3825.00	4000.00
STMC430-020		ADA RAMPS DIVIDE ESB	05/23/19	4.00	5000.00	5000.00	5000.00
FBR0063-057		US-6 F-09-K BRIDGE OVER CASTL	05/30/19	2.00	5000.00	3862.50	5225.00
ER145A-081		SH 145 MP 21 EMERGENCY ROCKFA	06/07/19	2.00	4000.00	1012.50	1022.00
NHPP0703-442		I-70 SILVERPLUME SOUNDWALL AN	06/13/19	2.00	7000.00	7786.15	9320.00
NHPP030A-036		SH 30 & TOWER RD IMPROVEMENTS	06/13/19	2.00	6000.00	2500.00	2500.00
CR500-205		R5 GUARDRAIL END TREATMENT EA	06/13/19	2.00	2000.00	4430.00	4430.00
FSA0142-067		SH 14 RUMBLESTRIPS: AULT TO S	06/13/19	2.00	2500.00	2500.00	2500.00
STR 141A-040		R5 YEAR 4 BRDG PREV MAINT RAM	06/20/19	2.00	11000.00	6550.00	10000.00
NHPP160A-030		US160 MM 43.2, 150.4, 156.3,	06/20/19	8.00	3600.00	1000.00	1000.00
C0502-085		US 50 MM 201.8 MONARCH AVALAN	06/27/19	2.00	3600.00	3082.50	4950.00
		WEIGHTED AVERAGE FOR THE SECOND QUARTER		75.00	4564.27	5635.02	4373.00
		WEIGHTED AVERAGE FOR THE YEAR		198.00	4867.27	5935.77	4838.72
===== 630-80356							
		Flash Arrow Panel (A Ty)		Each			
STAR200-242		R2 NORTH PROGRAM WALL REPAIRS	01/03/19	1.00	1000.00	1810.03	1040.00
FBR0253-247		I25 AT VINE DRIVE BRIDGE REPL	03/07/19	4.00	1250.00	672.88	10.00
SHER100-308		MIDPOINT - SIGNAL CONST PACKA	03/21/19	6.00	1000.00	962.50	1300.00
		WEIGHTED AVERAGE FOR THE FIRST QUARTER		11.00	1090.91	772.01	807.27
		WEIGHTED AVERAGE FOR THE YEAR		11.00	1090.91	772.01	807.27
===== 630-80357							
		Flash Arrow Panel (B Ty)		Each			
NHPPR500-173		US 160_550 DURANGO SIGNALS OP	01/03/19	4.00	1700.00	637.00	649.00
NHPP1601-076		US 160 MANCOS HILL (MP 40.000	02/21/19	2.00	550.00	804.33	700.00
NHPP1601-073		US 160 PASSING LANE NORTH OF	03/07/19	2.00	1000.00	1375.00	750.00
C R100-315		R1 ADA CURB RAMPS - PH 5	03/07/19	6.00	950.00	1600.00	900.00
SHE2254-090		Colfax & I-225, Colfax & Cham	03/07/19	3.00	1000.00	550.00	1000.00

COLORADO DEPARTMENT OF TRANSPORTATION
 ITEM UNIT COSTS BY PROJECTS -- 2019 COST DATA

13:44 Wednesday, August 7, 2019 341

PROJECT NUMBER	ITEM NUMBER/ PROJECT LOCATION	ITEM DESCRIPTION/ PROJECT LOCATION	DATE LET	UNIT/ QUANTITY	ENGR. EST.	AVERAGE BID	AWARDED BID
===== 630-80357 Flash Arrow Panel (B Ty) Each =====							
NHPP0503-087		US 50 PASSING LANES EAST OF S	03/21/19	2.00	1500.00	800.00	600.00
STM0242-077		US24 - 8TH ST TO WEST OF MANI	03/28/19	3.00	1000.00	1593.33	1580.00
		WEIGHTED AVERAGE FOR THE FIRST QUARTER		22.00	1118.18	1131.88	901.64
C2571-013 SH257 & 392:WINDSOR CURB RAMP 05/02/19 6.00 1000.00 1196.67 115.00							
FSA2873-190		US 287 AND FOOTHILLS PARKWAY	05/02/19	2.00	1500.00	985.00	1000.00
IM0252-456		I-25 COLORADO SPRINGS RAMP ME	05/16/19	2.00	1500.00	1683.67	1531.00
CR300-248		CRAIG RESIDENCY ADA RAMPS	05/16/19	3.00	1250.00	766.33	250.00
SHE0701-243		I-70 EXIT 26 DDI MODIFICATION	05/16/19	2.00	5000.00	892.50	1000.00
STMC430-020		ADA RAMPS DIVIDE ESB	05/23/19	2.00	560.00	1500.00	1500.00
STR 141A-040		R5 YEAR 4 BRDG PREV MAINT RAM	06/20/19	6.00	1500.00	2325.00	4000.00
		WEIGHTED AVERAGE FOR THE SECOND QUARTER		23.00	1559.57	1364.73	1543.57
		WEIGHTED AVERAGE FOR THE YEAR		45.00	1343.78	1259.08	1229.73
===== 630-80358 Flash Arrow Panel (C Ty) Each =====							
IM0251-351		I-25 South of Pueblo MP 79.6	01/03/19	4.00	1500.00	1031.46	1745.57
SHER100-289		INTERSECTIONS @ SH83 & LONGS	01/03/19	2.00	2000.00	932.00	1260.00
NHPP0701-241		I-70 TRUCK PARKING GARFIELD C	01/17/19	2.00	1500.00	502.16	275.00
MTCER400-368		REGION 4 FY 19 STENCIL NW	01/17/19	2.00	110.00	637.50	250.00
STR0241-062		US 24 143.4 - 148	01/24/19	4.00	2000.00	1830.00	2100.00
NHPPR100-250		PACKAGE A (I-25 / I-70 / I-76	01/24/19	4.00	1500.00	1140.21	1200.00
STAM086-075		SH96A ABRIENDO - ORMAN SAFETY	01/31/19	4.00	800.00	626.67	725.00
STA067A-038		SH 67 SEDALIA RESURFACING	01/31/19	2.00	1500.00	537.12	850.00
NHPP0821-107		SH 82 GLENWOOD SPRINGS TO CA	02/07/19	2.00	1500.00	1625.00	1600.00
ITSSW01-638		ETHERNET PHASE III (PRIMARYLY	02/07/19	2.00	1500.00	1800.00	2500.00
NHPP0741-022		SH 74: I-70 TO CR 65 RESURFAC	02/14/19	1.00	1600.00	2030.30	1630.00
NHPP070A-028		FALL RIVER ROAD BRIDGE	02/21/19	4.00	1750.00	1564.10	1800.00
SHER100-284		FY19 NORTH SIGNAL PKG	02/21/19	2.00	1650.00	1790.00	2000.00
NHPP006A-058		US 6 LOVELAND PASS - I-70 (FY	03/07/19	1.00	3000.00	1925.31	1850.62
NHPP0702-378		I-70 OFFICERS GULCH TO FRISCO	03/14/19	2.00	3000.00	2112.50	1537.50
NHPP050A-033		US50 West of Delta EB Lanes R	03/14/19	3.00	1500.00	1481.04	1250.00
SHE 0252-481		I-25 RAMP METER INSTALLATION	03/21/19	3.00	1500.00	1363.00	1280.00
NHPP2254-089		I-225 RESURFACING FROM I-25 T	03/21/19	4.00	1000.00	1669.65	2000.00
STM0242-077		US24 - 8TH ST TO WEST OF MANI	03/28/19	4.00	1600.00	1593.33	1580.00
		WEIGHTED AVERAGE FOR THE FIRST QUARTER		52.00	1533.08	1299.85	1465.73
NHPP030A-035		US 285/SH30	04/04/19	6.00	1500.00	1600.00	1600.00

PROJECT NUMBER	ITEM NUMBER/ PROJECT LOCATION	ITEM DESCRIPTION/ PROJECT LOCATION	DATE LET	UNIT/ QUANTITY	ENGR. EST.	AVERAGE BID	AWARDED BID
===== 630-80358		Flash Arrow Panel (C Ty)		Each =====			
STRR300-236		SH 92 and SH 133	04/04/19	1.00	2000.00	850.00	850.00
IM0252-472		I-25 CABLE BARRIER PHASE III	04/04/19	1.00	2200.00	2750.00	2500.00
BR071A-020		REPLACEMENT OF STRUCTURE L-22	04/18/19	2.00	1500.00	1543.33	50.00
FSA0252-468		I-25 AND PLUM CREEK IMPROVEME	04/18/19	4.00	1500.00	1487.85	1274.40
MTCE0702-387		MTCE R3 FY19 I-70 TAPE	04/18/19	2.00	200.00	383.33	525.00
MTCE0702-387		MTCE R3 FY19 I-70 TAPE	04/18/19	2.00	100.00	250.00	250.00
NHPP0703-445		I-70 WESTBOUND PEAK PERIOD SH	04/25/19	10.00	1600.00	3272.09	593.00
FSA0703-454		EB I-70 AUX LANE WARD TO KIPL	05/16/19	2.00	1500.00	2043.95	500.00
STRR200-257		ROAD CLOSURE GATES ON VARIOUS	05/30/19	4.00	800.00	235.50	220.00
MPR200-255		FY20 R2 PAVEMENT MARKING PROJ	06/06/19	2.00	100.00	933.33	100.00
NHPP0703-442		I-70 SILVERPLUME SOUNDWALL AN	06/13/19	1.00	1500.00	1831.09	2150.00
NHPP030A-036		SH 30 & TOWER RD IMPROVEMENTS	06/13/19	2.00	600.00	1000.00	1000.00
		WEIGHTED AVERAGE FOR THE SECOND QUARTER		39.00	1228.21	1850.25	816.86
		WEIGHTED AVERAGE FOR THE YEAR		91.00	1402.42	1496.28	1187.64
===== 630-80359		Port Mesg Panel		Day =====			
STR0132-021		SH 13-MOFFAT COUNTY-CR 3 SOUT	01/10/19	630.00	60.00	70.56	80.80
STR141A-047		SH 141 MP 120-143 MESA COUNTY	01/17/19	220.00	100.00	49.56	25.00
NHPP0701-241		I-70 TRUCK PARKING GARFIELD C	01/17/19	92.00	80.00	118.91	110.00
NHPP0821-107		SH 82 GLENWOOD SPRINGS TO CA	02/07/19	416.00	80.00	93.50	132.00
		WEIGHTED AVERAGE FOR THE FIRST QUARTER		1,358.00	73.96	74.85	89.42
NHPP2851-012		US 285 Antonito to Estrella C	05/02/19	76.00	65.00	100.00	60.00
MTCE0641-103		MTCE R3 FY20 SH 64 RANGELY PE	05/02/19	100.00	85.00	86.00	100.00
		WEIGHTED AVERAGE FOR THE SECOND QUARTER		176.00	76.36	93.46	82.73
		WEIGHTED AVERAGE FOR THE YEAR		1,534.00	74.24	76.24	88.65
===== 630-80360		Drum Channel Dev		Each =====			
STAR200-242		R2 NORTH PROGRAM WALL REPAIRS	01/03/19	200.00	40.00	45.33	57.00
IM0251-351		I-25 South of Pueblo MP 79.6	01/03/19	25.00	32.00	42.55	58.19
NHPPR500-173		US 160_550 DURANGO SIGNALS OP	01/03/19	150.00	22.00	15.00	19.00
FSA0142-068		SH 14 & WCR 33 INTERSECTION I	01/03/19	40.00	40.00	16.50	11.00
SHER100-289		INTERSECTIONS @ SH83 & LONGS	01/03/19	100.00	35.00	33.40	45.00
ER119A-065		PR SH 119A BOULDER CANYON	01/03/19	250.00	40.00	28.34	20.00

PROJECT NUMBER	ITEM NUMBER/ PROJECT LOCATION	ITEM DESCRIPTION/ PROJECT LOCATION	DATE LET	UNIT/ QUANTITY	ENGR. EST.	AVERAGE BID	AWARDED BID
=====	630-80360	Drum Channel Dev		Each =====			
STA119A-069		SH 119: NEDERLAND - EAST					
STR0132-021		SH 13-MOFFAT COUNTY-CR 3 SOUT	01/10/19	500.00	30.00	28.72	10.10
FBR0341-087		US 34 OVER NORTH FORK CO RIVE	01/10/19	50.00	55.00	20.87	12.07
STR141A-047		SH 141 MP 120-143 MESA COUNTY	01/17/19	50.00	30.00	13.83	10.00
NHPP0701-241		I-70 TRUCK PARKING GARFIELD C	01/17/19	20.00	40.00	10.58	5.50
STR0241-062		US 24 143.4 - 148	01/24/19	200.00	35.00	19.17	18.00
NHPPR100-250		PACKAGE A (I-25 / I-70 / I-76	01/24/19	50.00	35.00	33.81	35.00
STAM086-075		SH96A ABRIENDO - ORMAN SAFETY	01/31/19	75.00	6.00	45.00	42.00
STA067A-038		SH 67 SEDALIA RESURFACING	01/31/19	50.00	35.00	39.33	45.00
NHPP0821-107		SH 82 GLENWOOD SPRINGS TO CA	02/07/19	40.00	40.00	27.15	15.80
NH2871-035		US 287 PASSING LANES SOUTH OF	02/07/19	200.00	20.00	39.97	36.75
ITSSW01-638		ETHERNET PHASE III (PRIMARYLY	02/07/19	60.00	35.00	65.00	75.00
NHPP145A-065		SH 145 PASSING LANES AT DEEP	02/14/19	100.00	25.00	23.98	25.00
NHPP0741-022		SH 74: I-70 TO CR 65 RESURFAC	02/14/19	100.00	35.00	30.35	21.70
NHPP1601-076		US 160 MANCOS HILL (MP 40.000	02/21/19	50.00	8.00	29.13	27.00
NHPP070A-028		FALL RIVER ROAD BRIDGE	02/21/19	50.00	45.00	23.52	32.00
SHER100-284		FY19 NORTH SIGNAL PKG	02/21/19	50.00	37.00	36.33	38.00
NHPP1601-073		US 160 PASSING LANE NORTH OF	03/07/19	50.00	12.00	34.00	28.00
FBR0253-247		I25 AT VINE DRIVE BRIDGE REPL	03/07/19	50.00	40.00	76.16	125.00
NHPP006A-058		US 6 LOVELAND PASS - I-70 (FY	03/07/19	50.00	40.00	21.17	16.33
C R100-315		R1 ADA CURB RAMPS - PH 5	03/07/19	200.00	40.00	60.00	30.00
SHE2254-090		Colfax & I-225, Colfax & Cham	03/07/19	75.00	37.00	40.00	70.00
NHPP0702-378		I-70 OFFICERS GULCH TO FRISCO	03/14/19	500.00	15.00	15.46	15.37
NHPP050A-033		US50 West of Delta EB Lanes R	03/14/19	500.00	30.00	12.38	15.00
NHPP0503-087		US 50 PASSING LANES EAST OF S	03/21/19	400.00	30.00	12.50	14.00
SHER100-308		MIDPOINT - SIGNAL CONST PACKA	03/21/19	70.00	35.00	63.00	90.00
NHPP2254-089		I-225 RESURFACING FROM I-25 T	03/21/19	200.00	35.00	23.40	30.00
STM0242-077		US24 - 8TH ST TO WEST OF MANI	03/28/19	179.00	27.07	49.00	17.00
STA0131-070 HMA ALT		SH 13 CR 5 NORTH AND SOUTH	03/28/19	600.00	30.00	30.34	18.20
STA0131-070 PCCP ALT		SH 13 CR 5 NORTH AND SOUTH					
		WEIGHTED AVERAGE FOR THE FIRST QUARTER		5,284.00	30.01	29.08	25.27
NHPP030A-035		US 285/SH30	04/04/19	100.00	35.00	37.00	37.00
STRR300-236		SH 92 and SH 133	04/04/19	70.00	40.00	15.00	15.00
BR071A-020		REPLACEMENT OF STRUCTURE L-22	04/18/19	50.00	35.00	44.33	35.00
FSA0252-468		I-25 AND PLUM CREEK IMPROVEME	04/18/19	100.00	40.00	35.88	29.50
NHPP0703-445		I-70 WESTBOUND PEAK PERIOD SH	04/25/19	500.00	40.00	61.14	11.00
NHPP2851-012		US 285 Antonito to Estrella C	05/02/19	48.00	25.00	20.00	10.00
C2571-013		SH257 & 392:WINDSOR CURB RAMP	05/02/19	50.00	40.00	68.33	102.00
MTCE0641-103		MTCE R3 FY20 SH 64 RANGELY PE	05/02/19	50.00	35.00	37.00	50.00
FSA2873-190		US 287 AND FOOTHILLS PARKWAY	05/02/19	50.00	30.00	42.00	57.00
FSA0061-090		SH 6: CENTER LINE RUMBLE STRI	05/02/19	35.00	27.00	1.00	1.00
IM0252-456		I-25 COLORADO SPRINGS RAMP ME	05/16/19	50.00	30.00	52.67	63.00
FSA0703-454		EB I-70 AUX LANE WARD TO KIPL	05/16/19	150.00	40.00	34.10	25.00

PROJECT NUMBER	ITEM NUMBER/ PROJECT LOCATION	ITEM DESCRIPTION/ PROJECT LOCATION	DATE LET	UNIT/ QUANTITY	ENGR. EST.	AVERAGE BID	AWARDED BID
===== 630-80360							
		Drum Channel Dev		Each			
SHE0701-243		I-70 EXIT 26 DDI MODIFICATION	05/16/19	85.00	25.00	19.25	40.00
STMC430-020		ADA RAMP DIVIDE ESB	05/23/19	300.00	35.00	30.00	30.00
FBR0063-057		US-6 F-09-K BRIDGE OVER CASTL	05/30/19	25.00	40.00	13.00	11.00
STRR200-257		ROAD CLOSURE GATES ON VARIOUS	05/30/19	100.00	50.00	44.50	33.00
MFR200-255		FY20 R2 PAVEMENT MARKING PROJ	06/06/19	120.00	5.00	16.67	5.00
ER145A-081		SH 145 MP 21 EMERGENCY ROCKFA	06/07/19	20.00	40.00	28.72	48.00
NHPP0703-442		I-70 SILVERPLUME SOUNDWALL AN	06/13/19	100.00	37.00	22.62	35.00
NHPP030A-036		SH 30 & TOWER RD IMPROVEMENTS	06/13/19	25.00	35.00	30.00	30.00
CR500-205		R5 GUARDRAIL END TREATMENT EA	06/13/19	25.00	40.00	25.00	25.00
FSA0142-067		SH 14 RUMBLESTRIPS: AULT TO S	06/13/19	35.00	25.00	1.00	1.00
STR 141A-040		R5 YEAR 4 BRDG PREV MAINT RAM	06/20/19	60.00	24.00	31.50	50.00
NHPP160A-030		US160 MM 43.2, 150.4, 156.3,	06/20/19	150.00	22.00	11.31	11.50
C0502-085		US 50 MM 201.8 MONARCH AVALAN	06/27/19	20.00	5.00	27.75	22.00
		WEIGHTED AVERAGE FOR THE SECOND QUARTER		2,318.00	33.76	37.07	26.07
		WEIGHTED AVERAGE FOR THE YEAR		7,602.00	31.15	31.04	25.53
===== 630-80363							
		Drum Channel Dev (Light) (F)		Each			
STAR200-242		R2 NORTH PROGRAM WALL REPAIRS	01/03/19	100.00	40.00	70.57	57.00
ER119A-065		PR SH 119A BOULDER CANYON	01/03/19	20.00	50.00	78.65	150.00
STA119A-069		SH 119: NEDERLAND - EAST					
STR0132-021		SH 13-MOFFAT COUNTY-CR 3 SOUT	01/10/19	40.00	40.00	36.04	25.30
STR141A-047		SH 141 MP 120-143 MESA COUNTY	01/17/19	15.00	35.00	22.74	15.00
NHPP0701-241		I-70 TRUCK PARKING GARFIELD C	01/17/19	5.00	45.00	12.11	9.00
STR0241-062		US 24 143.4 - 148	01/24/19	100.00	45.00	19.83	18.00
ER072A-040		PR SH72A FLOOD PERMANENT REPA	01/31/19	45.00	60.00	104.89	77.00
NHPP072A-041		PR SH72A FLOOD PERMANENT REPA					
NHPP0821-107		SH 82 GLENWOOD SPRINGS TO CA	02/07/19	10.00	45.00	35.40	15.80
NHPP145A-065		SH 145 PASSING LANES AT DEEP	02/14/19	50.00	50.00	40.35	40.00
SHER100-284		FY19 NORTH SIGNAL PKG	02/21/19	10.00	80.00	59.67	65.00
NHPP1601-073		US 160 PASSING LANE NORTH OF	03/07/19	25.00	26.00	44.50	45.00
C R100-315		R1 ADA CURB RAMPS - PH 5	03/07/19	8.00	60.00	69.00	38.00
NHPP0702-378		I-70 OFFICERS GULCH TO FRISCO	03/14/19	20.00	20.00	23.50	20.50
NHPP050A-033		US50 West of Delta EB Lanes R	03/14/19	50.00	35.00	22.17	20.00
STA0131-070 HMA ALT		SH 13 CR 5 NORTH AND SOUTH	03/28/19	60.00	35.00	30.34	18.20
STA0131-070 PCCP ALT		SH 13 CR 5 NORTH AND SOUTH					
		WEIGHTED AVERAGE FOR THE FIRST QUARTER		558.00	42.44	55.45	40.61
IM0252-472		I-25 CABLE BARRIER PHASE III	04/04/19	212.00	33.00	77.50	50.00
BR071A-020		REPLACEMENT OF STRUCTURE L-22	04/18/19	25.00	45.00	50.33	40.00

PROJECT NUMBER	ITEM NUMBER/ PROJECT LOCATION	ITEM DESCRIPTION/ PROJECT LOCATION	DATE LET	UNIT/ QUANTITY	ENGR. EST.	AVERAGE BID	AWARDED BID
===== 630-80363		Drum Channel Dev (Light) (F)		Each =====			
NHPP0703-445	I-70 WESTBOUND PEAK PERIOD SH	04/25/19	10.00	50.00	100.49	118.00	
C2571-013	SH257 & 392:WINDSOR CURB RAMP	05/02/19	6.00	50.00	82.33	115.00	
MTCE0641-103	MTCE R3 FY20 SH 64 RANGELY PE	05/02/19	25.00	40.00	52.00	50.00	
FSA0703-454	EB I-70 AUX LANE WARD TO KIPL	05/16/19	15.00	65.00	73.31	50.00	
SHE0701-243	I-70 EXIT 26 DDI MODIFICATION	05/16/19	12.00	35.00	19.25	40.00	
FBR0063-057	US-6 F-09-K BRIDGE OVER CASTL	05/30/19	10.00	40.00	11.00	11.00	
NHPP030A-036	SH 30 & TOWER RD IMPROVEMENTS	06/13/19	10.00	60.00	35.00	35.00	
CR500-205	R5 GUARDRAIL END TREATMENT EA	06/13/19	9.00	50.00	50.00	50.00	
	WEIGHTED AVERAGE FOR THE SECOND QUARTER		334.00	38.22	67.24	50.48	
	WEIGHTED AVERAGE FOR THE YEAR		892.00	40.86	58.35	44.43	
===== 630-80364		Drum Channel Dev (Light) (SB)		Each =====			
IM0251-351	I-25 South of Pueblo MP 79.6	01/03/19	75.00	55.00	46.53	64.00	
NHPPR500-173	US 160_550 DURANGO SIGNALS OP	01/03/19	25.00	30.00	26.50	25.00	
STR0132-021	SH 13-MOFFAT COUNTY-CR 3 SOUT	01/10/19	40.00	40.00	36.04	25.30	
STR141A-047	SH 141 MP 120-143 MESA COUNTY	01/17/19	15.00	35.00	22.74	15.00	
NHPP0701-241	I-70 TRUCK PARKING GARFIELD C	01/17/19	5.00	45.00	12.71	12.00	
STR0241-062	US 24 143.4 - 148	01/24/19	50.00	53.00	20.50	18.00	
NHPP0821-107	SH 82 GLENWOOD SPRINGS TO CA	02/07/19	15.00	45.00	35.40	15.80	
NHPP1601-073	US 160 PASSING LANE NORTH OF	03/07/19	25.00	40.00	44.50	45.00	
NHPP0702-378	I-70 OFFICERS GULCH TO FRISCO	03/14/19	40.00	20.00	33.50	20.50	
NHPP050A-033	US50 West of Delta EB Lanes R	03/14/19	50.00	35.00	22.17	20.00	
STM0242-077	US24 - 8TH ST TO WEST OF MANI	03/28/19	40.00	34.00	55.33	20.00	
STA0131-070 HMA ALT	SH 13 CR 5 NORTH AND SOUTH	03/28/19	60.00	35.00	30.34	18.20	
STA0131-070 PCCP ALT	SH 13 CR 5 NORTH AND SOUTH						
	WEIGHTED AVERAGE FOR THE FIRST QUARTER		440.00	39.91	34.83	29.63	
IM0252-456	I-25 COLORADO SPRINGS RAMP ME	05/16/19	25.00	35.00	69.00	76.00	
SHE0701-243	I-70 EXIT 26 DDI MODIFICATION	05/16/19	10.00	40.00	19.25	40.00	
STMC430-020	ADA RAMPS DIVIDE ESB	05/23/19	30.00	2.25	34.00	34.00	
MPR200-255	FY20 R2 PAVEMENT MARKING PROJ	06/06/19	120.00	5.00	30.00	5.00	
ER145A-081	SH 145 MP 21 EMERGENCY ROCKFA	06/07/19	20.00	40.00	23.80	24.00	
STR 141A-040	R5 YEAR 4 BRDG PREV MAINT RAM	06/20/19	20.00	30.00	37.50	55.00	
NHPP160A-030	US160 MM 43.2, 150.4, 156.3,	06/20/19	32.00	34.00	34.17	35.00	
	WEIGHTED AVERAGE FOR THE SECOND QUARTER		257.00	17.24	34.52	25.76	
	WEIGHTED AVERAGE FOR THE YEAR		697.00	31.55	34.73	28.14	
===== 630-80367		Port Traf Speed Monitor		Each =====			
STR0241-062	US 24 143.4 - 148	01/24/19	1.00	4000.00	3675.00	3100.00	

PROJECT NUMBER	ITEM NUMBER/ PROJECT LOCATION	ITEM DESCRIPTION/ PROJECT LOCATION	DATE LET	UNIT/ QUANTITY	ENGR. EST.	AVERAGE BID	AWARDED BID
===== 630-80367 Port Traf Speed Monitor Each =====							
NHPP0702-378		I-70 OFFICERS GULCH TO FRISCO	03/14/19	2.00	3000.00	5033.33	4100.00
NHPP050A-033		US50 West of Delta EB Lanes R	03/14/19	4.00	3000.00	4233.33	4500.00
		WEIGHTED AVERAGE FOR THE FIRST QUARTER		7.00	3142.86	4382.14	4185.71
===== 630-80368 Port Traf Speed Monitor Day =====							
STR0132-021		SH 13-MOFFAT COUNTY-CR 3 SOUT	01/10/19	630.00	50.00	17.88	20.20
STA0131-070 HMA ALT		SH 13 CR 5 NORTH AND SOUTH	03/28/19	1,260.00	50.00	119.04	18.20
STA0131-070 PCCP ALT		SH 13 CR 5 NORTH AND SOUTH					
		WEIGHTED AVERAGE FOR THE FIRST QUARTER		1,890.00	50.00	73.06	19.20
		WEIGHTED AVERAGE FOR THE YEAR		1,890.00	50.00	73.06	19.20
===== 630-80370 Conc Barrier (Temp) Lin Foot =====							
ER119A-065		PR SH 119A BOULDER CANYON	01/03/19	11,100.00	40.00	32.76	20.00
STA119A-069		SH 119: NEDERLAND - EAST					
STR0132-021		SH 13-MOFFAT COUNTY-CR 3 SOUT	01/10/19	1,000.00	50.00	62.98	32.90
FBR0341-087		US 34 OVER NORTH FORK CO RIVE	01/10/19	788.00	40.00	29.85	49.12
STR0241-062		US 24 143.4 - 148	01/24/19	1,000.00	60.00	59.00	45.00
ER072A-040		PR SH72A FLOOD PERMANENT REPA	01/31/19	2,040.00	40.00	51.73	35.00
NHPP072A-041		PR SH72A FLOOD PERMANENT REPA					
NH2871-035		US 287 PASSING LANES SOUTH OF	02/07/19	6,808.00	45.00	45.42	35.85
NHPP145A-065		SH 145 PASSING LANES AT DEEP	02/14/19	4,500.00	30.00	70.32	69.00
NHPP070A-028		FALL RIVER ROAD BRIDGE	02/21/19	1,000.00	40.00	35.44	20.00
NHPP1601-073		US 160 PASSING LANE NORTH OF	03/07/19	500.00	70.00	81.00	82.00
FBR0253-247		I25 AT VINE DRIVE BRIDGE REPL	03/07/19	1,500.00	30.00	33.92	31.00
NHPP0702-378		I-70 OFFICERS GULCH TO FRISCO	03/14/19	660.00	75.00	87.25	71.75
NHPP050A-033		US50 West of Delta EB Lanes R	03/14/19	1,250.00	45.00	52.07	41.20
NHPP0503-087		US 50 PASSING LANES EAST OF S	03/21/19	1,000.00	50.00	60.00	70.00
SHE 0252-481		I-25 RAMP METER INSTALLATION	03/21/19	3,516.00	45.00	44.17	10.00
NHPP2254-089		I-225 RESURFACING FROM I-25 T	03/21/19	600.00	45.00	63.30	50.00
STM0242-077		US24 - 8TH ST TO WEST OF MANI	03/28/19	4,418.00	40.00	37.00	50.00

COLORADO DEPARTMENT OF TRANSPORTATION
 ITEM UNIT COSTS BY PROJECTS -- 2019 COST DATA

13:44 Wednesday, August 7, 2019 347

PROJECT NUMBER	ITEM NUMBER/ PROJECT LOCATION	ITEM DESCRIPTION/ PROJECT LOCATION	DATE LET	UNIT/ QUANTITY	ENGR. EST.	AVERAGE BID	AWARDED BID
===== 630-80370		Conc Barrier (Temp)		Lin Foot	=====	=====	=====
STA0131-070 HMA ALT	SH 13 CR 5 NORTH AND SOUTH	SH 13 CR 5 NORTH AND SOUTH	03/28/19	4,000.00	40.00	50.89	58.60
STA0131-070 PCCP ALT	SH 13 CR 5 NORTH AND SOUTH	SH 13 CR 5 NORTH AND SOUTH					
	WEIGHTED AVERAGE FOR THE FIRST QUARTER			45,680.00	41.73	43.58	37.64
NHPP0703-445		I-70 WESTBOUND PEAK PERIOD SH	04/25/19	24,000.00	45.00	61.67	27.00
FSA0703-454		EB I-70 AUX LANE WARD TO KIPL	05/16/19	4,800.00	35.00	23.94	30.00
FBR0063-057		US-6 F-09-K BRIDGE OVER CASTL	05/30/19	900.00	30.00	47.00	49.00
ER145A-081		SH 145 MP 21 EMERGENCY ROCKFA	06/07/19	500.00	70.00	119.12	105.00
NHPP0703-442		I-70 SILVERPLUME SOUNDWALL AN	06/13/19	1,400.00	70.00	49.87	35.00
STR 141A-040		R5 YEAR 4 BRDG PREV MAINT RAM	06/20/19	1,390.00	40.00	105.00	100.00
	WEIGHTED AVERAGE FOR THE SECOND QUARTER			32,990.00	44.36	56.59	32.63
	WEIGHTED AVERAGE FOR THE YEAR			78,670.00	42.83	47.45	35.49
===== 630-80371		Reset Concrete Barrier (Temp)		Lin Foot	=====	=====	=====
STM0242-077	US24 - 8TH ST TO WEST OF MANI	US24 - 8TH ST TO WEST OF MANI	03/28/19	6,076.00	15.00	9.33	12.00
	WEIGHTED AVERAGE FOR THE FIRST QUARTER			6,076.00	15.00	9.33	12.00
	WEIGHTED AVERAGE FOR THE YEAR			6,076.00	15.00	9.33	12.00
===== 630-80372		Conc Barrier (Temp) (Furnish & Install)		Lin Foot	=====	=====	=====
NHPP030A-036	SH 30 & TOWER RD IMPROVEMENTS	SH 30 & TOWER RD IMPROVEMENTS	06/13/19	700.00	45.00	20.00	20.00
	WEIGHTED AVERAGE FOR THE SECOND QUARTER			700.00	45.00	20.00	20.00
	WEIGHTED AVERAGE FOR THE YEAR			700.00	45.00	20.00	20.00
===== 630-80377		Port Water Filled Barrier (Temp)		Lin Foot	=====	=====	=====
CR500-205	R5 GUARDRAIL END TREATMENT EA	R5 GUARDRAIL END TREATMENT EA	06/13/19	120.00	40.00	25.00	25.00
	WEIGHTED AVERAGE FOR THE SECOND QUARTER			120.00	40.00	25.00	25.00
	WEIGHTED AVERAGE FOR THE YEAR			120.00	40.00	25.00	25.00

PROJECT NUMBER	ITEM NUMBER/ PROJECT LOCATION	ITEM DESCRIPTION/ PROJECT LOCATION	DATE LET	UNIT/ QUANTITY	ENGR. EST.	AVERAGE BID	AWARDED BID
===== 630-80380		Traffic Cone		Each =====			
STAR200-242		R2 NORTH PROGRAM WALL REPAIRS	01/03/19	200.00	25.00	10.43	13.00
IM0251-351		I-25 South of Pueblo MP 79.6	01/03/19	150.00	8.00	12.94	17.46
NHPPR500-173		US 160_550 DURANGO SIGNALS OP	01/03/19	250.00	5.00	4.00	2.50
FSA0142-068		SH 14 & WCR 33 INTERSECTION I	01/03/19	100.00	10.00	4.78	1.10
SHER100-289		INTERSECTIONS @ SH83 & LONGS	01/03/19	200.00	12.00	11.40	13.00
ER119A-065		PR SH 119A BOULDER CANYON	01/03/19	380.00	8.03	12.78	11.00
STA119A-069		SH 119: NEDERLAND - EAST					
STR0132-021		SH 13-MOFFAT COUNTY-CR 3 SOUT	01/10/19	250.00	5.00	3.58	1.05
FBR0341-087		US 34 OVER NORTH FORK CO RIVE	01/10/19	50.00	10.00	8.29	6.03
MTCER300-247		MTCE R3 FY19 REGION ROUNDABOU	01/10/19	80.00	5.00	6.00	5.00
STR141A-047		SH 141 MP 120-143 MESA COUNTY	01/17/19	175.00	8.00	4.41	5.00
NHPP0701-241		I-70 TRUCK PARKING GARFIELD C	01/17/19	200.00	15.00	4.48	2.50
MTCER400-368		REGION 4 FY 19 STENCIL NW	01/17/19	150.00	6.00	7.50	5.00
STR0241-062		US 24 143.4 - 148	01/24/19	600.00	8.00	11.23	12.00
NHPPR100-250		PACKAGE A (I-25 / I-70 / I-76	01/24/19	500.00	10.00	10.18	11.00
ER072A-040		PR SH72A FLOOD PERMANENT REPA	01/31/19	45.00	12.00	14.68	14.00
NHPP072A-041		PR SH72A FLOOD PERMANENT REPA					
STAM086-075		SH96A ABRIENDO - ORMAN SAFETY	01/31/19	250.00	5.00	9.33	9.00
STA067A-038		SH 67 SEDALIA RESURFACING	01/31/19	250.00	12.00	8.35	7.00
NHPP0821-107		SH 82 GLENWOOD SPRINGS TO CA	02/07/19	700.00	6.00	5.80	10.50
NH2871-035		US 287 PASSING LANES SOUTH OF	02/07/19	200.00	10.00	11.65	3.15
ITSSW01-638		ETHERNET PHASE III (PRIMARILY	02/07/19	200.00	10.00	15.25	14.00
NHPP145A-065		SH 145 PASSING LANES AT DEEP	02/14/19	50.00	10.00	2.13	2.00
NHPP0741-022		SH 74: I-70 TO CR 65 RESURFAC	02/14/19	100.00	12.00	12.42	10.85
NHPP1601-076		US 160 MANCOS HILL (MP 40.000	02/21/19	350.00	2.00	2.12	2.15
SHER100-284		FY19 NORTH SIGNAL PKG	02/21/19	50.00	12.00	12.00	13.00
NHPP1601-073		US 160 PASSING LANE NORTH OF	03/07/19	100.00	10.00	1.75	2.50
FBR0253-247		I25 AT VINE DRIVE BRIDGE REPL	03/07/19	200.00	7.50	4.69	1.00
MPR200-253		R2 FY19 STENCIL PVMT MKG PROJ	03/07/19	300.00	5.00	7.33	5.00
NHPP006A-058		US 6 LOVELAND PASS - I-70 (FY	03/07/19	100.00	15.00	11.45	10.89
C R100-315		R1 ADA CURB RAMPS - PH 5	03/07/19	200.00	13.50	13.50	5.00
SHE2254-090		Colfax & I-225, Colfax & Cham	03/07/19	120.00	12.00	4.00	7.00
NHPP0702-378		I-70 OFFICERS GULCH TO FRISCO	03/14/19	1,000.00	10.00	8.42	10.25
NHPP050A-033		US50 West of Delta EB Lanes R	03/14/19	150.00	8.00	4.42	5.00
NHPP0503-087		US 50 PASSING LANES EAST OF S	03/21/19	300.00	10.00	4.50	1.00
NHPP2254-089		I-225 RESURFACING FROM I-25 T	03/21/19	400.00	10.00	12.03	20.00
STM0242-077		US24 - 8TH ST TO WEST OF MANI	03/28/19	600.00	7.00	16.67	10.00
STA0131-070 HMA ALT		SH 13 CR 5 NORTH AND SOUTH	03/28/19	300.00	8.00	15.16	6.05
STA0131-070 PCCP ALT		SH 13 CR 5 NORTH AND SOUTH					
		WEIGHTED AVERAGE FOR THE FIRST QUARTER		9,250.00	8.82	9.11	8.53
NHPP030A-035		US 285/SH30	04/04/19	400.00	10.00	11.00	11.00

PROJECT NUMBER	ITEM NUMBER/ PROJECT LOCATION	ITEM DESCRIPTION/ PROJECT LOCATION	DATE LET	UNIT/ QUANTITY	ENGR. EST.	AVERAGE BID	AWARDED BID
===== 630-80380		Traffic Cone		Each =====			
STRR300-236		SH 92 and SH 133	04/04/19	1,000.00	10.00	1.00	1.00
IM0252-472		I-25 CABLE BARRIER PHASE III	04/04/19	200.00	10.00	15.00	10.00
BR071A-020		REPLACEMENT OF STRUCTURE L-22	04/18/19	100.00	9.00	10.83	10.00
MTCE0702-387		MTCE R3 FY19 I-70 TAPE	04/18/19	600.00	5.00	3.67	3.00
MTCE0702-387		MTCE R3 FY19/20 REGION WIDE S	04/18/19	100.00	5.00	5.00	5.00
NHPP0703-445		I-70 WESTBOUND PEAK PERIOD SH	04/25/19	400.00	12.00	13.36	11.00
NHPP2851-012		US 285 Antonito to Estrella C	05/02/19	264.00	5.00	5.00	1.00
C2571-013		SH257 & 392:WINDSOR CURB RAMP	05/02/19	100.00	7.00	7.67	2.00
MTCE0641-103		MTCE R3 FY20 SH 64 RANGELY PE	05/02/19	80.00	10.00	1.60	2.00
FSA2873-190		US 287 AND FOOTHILLS PARKWAY	05/02/19	100.00	10.00	15.35	17.00
IM0252-456		I-25 COLORADO SPRINGS RAMP ME	05/16/19	100.00	10.00	20.17	19.00
FSA0703-454		EB I-70 AUX LANE WARD TO KIPL	05/16/19	150.00	12.00	9.20	5.00
CR300-248		CRAIG RESIDENCY ADA RAMPS	05/16/19	150.00	8.00	5.33	1.00
STMC430-020		ADA RAMPS DIVIDE ESB	05/23/19	100.00	7.02	10.00	10.00
FBR0063-057		US-6 F-09-K BRIDGE OVER CASTL	05/30/19	50.00	10.00	5.25	5.50
STRR200-257		ROAD CLOSURE GATES ON VARIOUS	05/30/19	200.00	10.00	9.77	7.00
MPR200-255		FY20 R2 PAVEMENT MARKING PROJ	06/06/19	200.00	5.00	5.48	5.00
ER145A-081		SH 145 MP 21 EMERGENCY ROCKFA	06/07/19	40.00	10.00	4.86	5.00
NHPP0703-442		I-70 SILVERPLUME SOUNDWALL AN	06/13/19	100.00	12.00	9.71	3.50
NHPP030A-036		SH 30 & TOWER RD IMPROVEMENTS	06/13/19	50.00	12.00	11.00	11.00
CR500-205		R5 GUARDRAIL END TREATMENT EA	06/13/19	150.00	12.00	1.30	1.30
STR 141A-040		R5 YEAR 4 BRDG PREV MAINT RAM	06/20/19	40.00	7.00	12.00	20.00
NHPP160A-030		US160 MM 43.2, 150.4, 156.3,	06/20/19	80.00	4.00	1.13	1.15
C0502-085		US 50 MM 201.8 MONARCH AVALAN	06/27/19	50.00	10.00	8.05	1.10
		WEIGHTED AVERAGE FOR THE SECOND QUARTER		4,804.00	8.81	7.57	5.44
		WEIGHTED AVERAGE FOR THE YEAR		14,054.00	8.82	8.74	7.46
===== 630-80384		Tubular Marker		Each =====			
STA067A-038		SH 67 SEDALIA RESURFACING	01/31/19	25.00	15.00	32.38	45.00
		WEIGHTED AVERAGE FOR THE FIRST QUARTER		25.00	15.00	32.38	45.00
		WEIGHTED AVERAGE FOR THE YEAR		25.00	15.00	32.38	45.00
===== 630-80391		Channel Dev (Fixed)		Each =====			
NHPP2254-089		I-225 RESURFACING FROM I-25 T	03/21/19	50.00	45.00	60.79	55.00
		WEIGHTED AVERAGE FOR THE FIRST QUARTER		50.00	45.00	60.79	55.00
		WEIGHTED AVERAGE FOR THE YEAR		50.00	45.00	60.79	55.00

PROJECT NUMBER	ITEM NUMBER/ PROJECT LOCATION	ITEM DESCRIPTION/ PROJECT LOCATION	DATE LET	UNIT/ QUANTITY	ENGR. EST.	AVERAGE BID	AWARDED BID
===== 630-80393		Stackable Vertical Panels		Each			
SHER100-289		INTERSECTIONS @ SH83 & LONGS	01/03/19	50.00	30.00	33.60	45.00
MTCER400-368		REGION 4 FY 19 STENCIL NW	01/17/19	50.00	6.00	21.88	5.00
NHPPR100-250		PACKAGE A (I-25 / I-70 / I-76	01/24/19	80.00	45.00	23.00	25.00
STAM086-075		SH96A ABRIENDO - ORMAN SAFETY	01/31/19	50.00	24.10	45.00	42.00
NHPP0741-022		SH 74: I-70 TO CR 65 RESURFAC	02/14/19	50.00	30.00	34.71	40.70
SHER100-284		FY19 NORTH SIGNAL PKG	02/21/19	20.00	50.00	37.00	40.00
NHPP006A-058		US 6 LOVELAND PASS - I-70 (FY	03/07/19	25.00	30.00	21.89	21.77
C R100-315		R1 ADA CURB RAMPS - PH 5	03/07/19	40.00	35.00	25.00	20.00
SHE 0252-481		I-25 RAMP METER INSTALLATION	03/21/19	50.00	25.00	21.00	20.00
SHER100-308		MIDPOINT - SIGNAL CONST PACKA	03/21/19	155.00	17.50	35.25	38.50
		WEIGHTED AVERAGE FOR THE FIRST QUARTER		570.00	26.70	29.76	31.13
IM0252-472		I-25 CABLE BARRIER PHASE III	04/04/19	25.00	15.00	57.50	35.00
C2571-013		SH257 & 392:WINDSOR CURB RAMP	05/02/19	50.00	22.00	49.83	102.00
CR300-248		CRAIG RESIDENCY ADA RAMPS	05/16/19	60.00	20.00	22.00	30.00
STMC430-020		ADA RAMPS DIVIDE ESB	05/23/19	75.00	22.00	34.00	34.00
NHPP0703-442		I-70 SILVERPLUME SOUNDWALL AN	06/13/19	50.00	30.00	23.85	40.00
NHPP030A-036		SH 30 & TOWER RD IMPROVEMENTS	06/13/19	20.00	30.00	50.00	50.00
		WEIGHTED AVERAGE FOR THE SECOND QUARTER		280.00	22.95	31.31	47.59
		WEIGHTED AVERAGE FOR THE YEAR		850.00	25.46	30.26	36.56
===== 630-80401		Delin (Ty I) (Temp)		Each			
FBR0063-057		US-6 F-09-K BRIDGE OVER CASTL	05/30/19	24.00	5.00	28.00	31.00
		WEIGHTED AVERAGE FOR THE SECOND QUARTER		24.00	5.00	28.00	31.00
		WEIGHTED AVERAGE FOR THE YEAR		24.00	5.00	28.00	31.00
===== 630-80415		Adv Warn Flash or Seq Panel (C Type)		Day			
MPR200-253		R2 FY19 STENCIL PVMT MKG PROJ	03/07/19	100.00	120.00	31.67	20.00
		WEIGHTED AVERAGE FOR THE FIRST QUARTER		100.00	120.00	31.67	20.00
		WEIGHTED AVERAGE FOR THE YEAR		100.00	120.00	31.67	20.00

COLORADO DEPARTMENT OF TRANSPORTATION
 ITEM UNIT COSTS BY PROJECTS -- 2019 COST DATA

13:44 Wednesday, August 7, 2019 351

PROJECT NUMBER	ITEM NUMBER/ PROJECT LOCATION	ITEM DESCRIPTION/ PROJECT LOCATION	DATE LET	UNIT/ QUANTITY	ENGR. EST.	AVERAGE BID	AWARDED BID
===== 630-80430 Rumble Strip (Port) Each =====							
STR0132-021		SH 13-MOFFAT COUNTY-CR 3 SOUT	01/10/19	2.00	1500.00	5014.00	3030.00
NHPP0821-107		SH 82 GLENWOOD SPRINGS TO CA	02/07/19	12.00	1500.00	1955.00	1160.00
	WEIGHTED AVERAGE FOR THE FIRST QUARTER			14.00	1500.00	2854.71	1427.14
	WEIGHTED AVERAGE FOR THE YEAR			14.00	1500.00	2854.71	1427.14
===== 630-80440 Port Rumble Strips (Temp) Each =====							
NHPP145A-065		SH 145 PASSING LANES AT DEEP	02/14/19	12.00	1200.00	1258.96	850.00
NHPP1601-073		US 160 PASSING LANE NORTH OF	03/07/19	12.00	1000.00	1525.00	2050.00
NHPP050A-033		US50 West of Delta EB Lanes R	03/14/19	12.00	800.00	2533.54	1600.00
	WEIGHTED AVERAGE FOR THE FIRST QUARTER			36.00	1000.00	1694.54	1500.00
STRR300-236		SH 92 and SH 133	04/04/19	24.00	1800.00	800.00	800.00
	WEIGHTED AVERAGE FOR THE SECOND QUARTER			24.00	1800.00	800.00	800.00
	WEIGHTED AVERAGE FOR THE YEAR			60.00	1320.00	1545.45	1220.00
===== 630-80511 Mobile Pvmt Marking Zone LUMP SUM =====							
ER119A-065		PR SH 119A BOULDER CANYON	01/03/19	1.00	10000.00	14027.87	8500.00
STAl19A-069		SH 119: NEDERLAND - EAST					
STR0132-021		SH 13-MOFFAT COUNTY-CR 3 SOUT	01/10/19	1.00	4000.00	16318.00	8590.00
STR0241-062		US 24 143.4 - 148	01/24/19	1.00	12000.00	6450.00	8200.00
NHPP0821-107		SH 82 GLENWOOD SPRINGS TO CA	02/07/19	1.00	6000.00	9150.00	8950.00
MTCER500-206		R5 FY19 STRIPING	02/07/19	1.00	10000.00	35666.67	12000.00
NHPP1601-076		US 160 MANCOS HILL (MP 40.000	02/21/19	1.00	10000.00	11830.00	10000.00
NHPP0702-378		I-70 OFFICERS GULCH TO FRISCO	03/14/19	1.00	10000.00	10486.67	2460.00
STM0242-077		US24 - 8TH ST TO WEST OF MANI	03/28/19	1.00	10000.00	10866.67	3500.00
	WEIGHTED AVERAGE FOR THE FIRST QUARTER			8.00	9000.00	14600.43	7775.00
STRR300-236		SH 92 and SH 133	04/04/19	1.00	5000.00	5000.00	5000.00

COLORADO DEPARTMENT OF TRANSPORTATION
ITEM UNIT COSTS BY PROJECTS -- 2019 COST DATA

13:44 Wednesday, August 7, 2019 352

PROJECT NUMBER	ITEM NUMBER/ PROJECT LOCATION	ITEM DESCRIPTION/ PROJECT LOCATION	DATE LET	UNIT/ QUANTITY	ENGR. EST.	AVERAGE BID	AWARDED BID
===== 630-80511							
NHPP2851-012		Mobile Pvmt Marking Zone US 285 Antonito to Estrella C	05/02/19	LUMP SUM 1.00	2000.00	7500.00	5000.00
		WEIGHTED AVERAGE FOR THE SECOND QUARTER		2.00	3500.00	6875.00	5000.00
		WEIGHTED AVERAGE FOR THE YEAR		10.00	7900.00	13691.56	7220.00
===== 630-80520							
		Mobile Pvmt Mkg Zone		Day			
FSA0061-090		SH 6: CENTER LINE RUMBLE STRI	05/02/19	16.00	200.00	1.00	1.00
MPR200-255		FY20 R2 PAVEMENT MARKING PROJ	06/06/19	100.00	50.00	383.33	400.00
FSA0142-067		SH 14 RUMBLESTRIPS: AULT TO S	06/13/19	13.00	250.00	1.00	1.00
		WEIGHTED AVERAGE FOR THE SECOND QUARTER		129.00	88.76	349.63	310.30
		WEIGHTED AVERAGE FOR THE YEAR		129.00	88.76	349.63	310.30
===== 630-85006							
		Impact Atten (Sand Fill) (Temp)		Each			
FBR0341-087		US 34 OVER NORTH FORK CO RIVE	01/10/19	4.00	3500.00	3142.23	2172.58
SHE 0252-481		I-25 RAMP METER INSTALLATION	03/21/19	4.00	4500.00	4508.33	3765.00
		WEIGHTED AVERAGE FOR THE FIRST QUARTER		8.00	4000.00	3597.60	2968.79
===== 630-85010							
		Impact Atten (Temp)		Each			
ER119A-065		PR SH 119A BOULDER CANYON	01/03/19	18.00	3500.00	6837.07	5600.00
STA119A-069		SH 119: NEDERLAND - EAST					
STR141A-047		SH 141 MP 120-143 MESA COUNTY	01/17/19	2.00	5500.00	2777.58	3200.00
STR0241-062		US 24 143.4 - 148	01/24/19	1.00	5000.00	4098.33	4200.00
NH2871-035		US 287 PASSING LANES SOUTH OF	02/07/19	4.00	3000.00	3996.99	3675.00
NHPP145A-065		SH 145 PASSING LANES AT DEEP	02/14/19	4.00	4000.00	5420.93	4000.00
NHPP070A-028		FALL RIVER ROAD BRIDGE	02/21/19	3.00	3500.00	6789.66	4700.00

COLORADO DEPARTMENT OF TRANSPORTATION
 ITEM UNIT COSTS BY PROJECTS -- 2019 COST DATA

13:44 Wednesday, August 7, 2019 353

PROJECT NUMBER	ITEM NUMBER/ PROJECT LOCATION	ITEM DESCRIPTION/ PROJECT LOCATION	DATE LET	UNIT/ QUANTITY	ENGR. EST.	AVERAGE BID	AWARDED BID
===== 630-85010 Impact Atten (Temp) Each =====							
NHPP1601-073		US 160 PASSING LANE NORTH OF	03/07/19	2.00	6000.00	4050.00	4100.00
NHPP0702-378		I-70 OFFICERS GULCH TO FRISCO	03/14/19	2.00	5000.00	4700.00	4100.00
NHPP0503-087		US 50 PASSING LANES EAST OF S	03/21/19	2.00	600.00	4250.00	4000.00
NHPP2254-089		I-225 RESURFACING FROM I-25 T	03/21/19	2.00	5000.00	3673.64	5000.00
STM0242-077		US24 - 8TH ST TO WEST OF MANI	03/28/19	6.00	3600.00	9550.00	5750.00
STA0131-070 HMA ALT		SH 13 CR 5 NORTH AND SOUTH	03/28/19	8.00	5000.00	2311.24	5460.00
STA0131-070 PCCP ALT		SH 13 CR 5 NORTH AND SOUTH					
	WEIGHTED AVERAGE FOR THE FIRST QUARTER			54.00	3931.48	5985.37	4938.80
===== 630-85011 Imp Atten (Temp) Day =====							
NHPP0703-445		I-70 WESTBOUND PEAK PERIOD SH	04/25/19	15.00	5200.00	11762.49	4153.00
FBR0063-057		US-6 F-09-K BRIDGE OVER CASTL	05/30/19	2.00	4000.00	2525.00	3850.00
ER145A-081		SH 145 MP 21 EMERGENCY ROCKFA	06/07/19	2.00	6000.00	3306.75	3221.00
	WEIGHTED AVERAGE FOR THE SECOND QUARTER			19.00	5157.89	10427.15	4023.00
	WEIGHTED AVERAGE FOR THE YEAR			73.00	4250.68	6718.75	4686.62
===== 630-85011 Imp Atten (Temp) Day =====							
STR0132-021		SH 13-MOFFAT COUNTY-CR 3 SOUT	01/10/19	160.00	40.00	54.58	101.00
ER072A-040		PR SH72A FLOOD PERMANENT REPA	01/31/19	1,180.00	100.00	55.62	33.00
NHPP072A-041		PR SH72A FLOOD PERMANENT REPA					
NHPP0821-107		SH 82 GLENWOOD SPRINGS TO CA	02/07/19	20.00	72.00	125.00	85.00
	WEIGHTED AVERAGE FOR THE FIRST QUARTER			1,360.00	92.53	55.75	41.76
FSA0252-468		I-25 AND PLUM CREEK IMPROVEME	04/18/19	60.00	100.00	125.88	147.50
IM0252-456		I-25 COLORADO SPRINGS RAMP ME	05/16/19	100.00	100.00	696.00	638.00
FSA0703-454		EB I-70 AUX LANE WARD TO KIPL	05/16/19	80.00	40.00	153.33	100.00
	WEIGHTED AVERAGE FOR THE SECOND QUARTER			240.00	80.00	353.60	336.04
	WEIGHTED AVERAGE FOR THE YEAR			1,600.00	90.65	70.47	85.91
===== 630-85020 Mobile Attenuator Each =====							
ER119A-065		PR SH 119A BOULDER CANYON	01/03/19	2.00	14000.00	37514.76	30000.00

PROJECT NUMBER	ITEM NUMBER/ PROJECT LOCATION	ITEM DESCRIPTION/ PROJECT LOCATION	DATE LET	UNIT/ QUANTITY	ENGR. EST.	AVERAGE BID	AWARDED BID
===== 630-85020		Mobile Attenuator		Each =====			
STA119A-069		SH 119: NEDERLAND - EAST					
STR141A-047		SH 141 MP 120-143 MESA COUNTY	01/17/19	2.00	12000.00	16235.38	15000.00
STR0241-062		US 24 143.4 - 148	01/24/19	1.00	20000.00	38700.00	36000.00
NHPPR100-250		PACKAGE A (I-25 / I-70 / I-76	01/24/19	2.00	550.00	49720.00	53000.00
NHPP0741-022		SH 74: I-70 TO CR 65 RESURFAC	02/14/19	1.00	500.00	54423.81	19550.00
FBR0253-247		I25 AT VINE DRIVE BRIDGE REPL	03/07/19	2.00	25000.00	10652.68	5500.00
NHPP0702-378		I-70 OFFICERS GULCH TO FRISCO	03/14/19	1.00	25000.00	23816.67	18450.00
STA0131-070 HMA ALT		SH 13 CR 5 NORTH AND SOUTH	03/28/19	4.00	25000.00	4373.63	14550.00
STA0131-070 PCCP ALT		SH 13 CR 5 NORTH AND SOUTH					
		WEIGHTED AVERAGE FOR THE FIRST QUARTER		15.00	16573.33	24607.78	23853.85
IM0252-472		I-25 CABLE BARRIER PHASE III	04/04/19	2.00	8000.00	26500.00	19000.00
NHPP0703-445		I-70 WESTBOUND PEAK PERIOD SH	04/25/19	4.00	10000.00	63551.77	29665.00
STRR200-257		ROAD CLOSURE GATES ON VARIOUS	05/30/19	4.00	1000.00	7649.00	7150.00
		WEIGHTED AVERAGE FOR THE SECOND QUARTER		10.00	6000.00	38742.22	18526.00
		WEIGHTED AVERAGE FOR THE YEAR		25.00	12344.00	27933.53	21537.39
===== 630-85040		Impact Atten (I-M-A) (Temp)		Each =====			
IM0251-351		I-25 South of Pueblo MP 79.6	01/03/19	2.00	25000.00	20097.61	15128.29
MTCER400-368		REGION 4 FY 19 STENCIL NW	01/17/19	2.00	17500.00	15175.00	250.00
		WEIGHTED AVERAGE FOR THE FIRST QUARTER		4.00	21250.00	17636.31	7689.15
MTCE0702-387		MTCE R3 FY19 I-70 TAPE	04/18/19	2.00	1000.00	9400.00	1200.00
		WEIGHTED AVERAGE FOR THE SECOND QUARTER		2.00	1000.00	9400.00	1200.00
		WEIGHTED AVERAGE FOR THE YEAR		6.00	14500.00	15390.04	5526.10
===== 630-85041		Mobile Attenuator		Day =====			
SHER100-289		INTERSECTIONS @ SH83 & LONGS	01/03/19	20.00	350.00	384.60	360.00
NHPP0701-241		I-70 TRUCK PARKING GARFIELD C	01/17/19	53.00	350.00	309.99	400.00
ER072A-040		PR SH72A FLOOD PERMANENT REPA	01/31/19	210.00	350.00	549.39	550.00

PROJECT NUMBER	ITEM NUMBER/ PROJECT LOCATION	ITEM DESCRIPTION/ PROJECT LOCATION	DATE LET	UNIT/ QUANTITY	ENGR. EST.	AVERAGE BID	AWARDED BID
===== 630-85041							
		Mobile Attenuator		Day			
NHPP072A-041		PR SH72A FLOOD PERMANENT REPA					
STA067A-038		SH 67 SEDALIA RESURFACING	01/31/19	5.00	500.00	738.01	650.00
NHPP0821-107		SH 82 GLENWOOD SPRINGS TO CA	02/07/19	180.00	350.00	468.50	552.00
ITSSW01-638		ETHERNET PHASE III (PRIMARYLY	02/07/19	90.00	500.00	450.00	350.00
NHPP1601-076		US 160 MANCOS HILL (MP 40.000	02/21/19	46.00	400.00	636.33	650.00
SHER100-284		FY19 NORTH SIGNAL PKG	02/21/19	75.00	125.00	465.67	500.00
MPR200-253		R2 FY19 STENCIL PVMT MKG PROJ	03/07/19	80.00	300.00	241.67	75.00
NHPP050A-033		US50 West of Delta EB Lanes R	03/14/19	5.00	400.00	650.00	450.00
SHE 0252-481		I-25 RAMP METER INSTALLATION	03/21/19	60.00	450.00	367.33	345.00
NHPP2254-089		I-225 RESURFACING FROM I-25 T	03/21/19	150.00	350.00	734.22	550.00
STM0242-077		US24 - 8TH ST TO WEST OF MANI	03/28/19	70.00	331.43	510.00	440.00
		WEIGHTED AVERAGE FOR THE FIRST QUARTER		1,044.00	350.60	516.49	467.11
===== 630-85041							
NHPP030A-035		US 285/SH30	04/04/19	80.00	450.00	315.00	315.00
FSA0252-468		I-25 AND PLUM CREEK IMPROVEME	04/18/19	60.00	650.00	464.25	472.00
FSA0703-454		EB I-70 AUX LANE WARD TO KIPL	05/16/19	25.00	382.87	563.19	350.00
MPR200-255		FY20 R2 PAVEMENT MARKING PROJ	06/06/19	20.00	100.00	433.33	100.00
NHPP0703-442		I-70 SILVERPLUME SOUNDWALL AN	06/13/19	10.00	550.00	547.63	521.00
NHPP030A-036		SH 30 & TOWER RD IMPROVEMENTS	06/13/19	80.00	450.00	200.00	200.00
		WEIGHTED AVERAGE FOR THE SECOND QUARTER		275.00	465.72	430.36	310.84
		WEIGHTED AVERAGE FOR THE YEAR		1,319.00	374.60	506.88	434.53
===== 630-86801							
		Traffic Signal (Temp)		LUMP SUM			
STR0132-021		SH 13-MOFFAT COUNTY-CR 3 SOUT	01/10/19	1.00	10000.00	71172.00	35360.00
STR141A-047		SH 141 MP 120-143 MESA COUNTY	01/17/19	1.00	22000.00	11991.44	10000.00
NHPP070A-028		FALL RIVER ROAD BRIDGE	02/21/19	1.00	30000.00	25686.80	19000.00
STA0131-070 HMA ALT		SH 13 CR 5 NORTH AND SOUTH	03/28/19	1.00	25000.00	26965.00	31500.00
STA0131-070 PCCP ALT		SH 13 CR 5 NORTH AND SOUTH					
		WEIGHTED AVERAGE FOR THE FIRST QUARTER		4.00	22400.00	34702.49	23965.00
===== 630-86801							
ER145A-081		SH 145 MP 21 EMERGENCY ROCKFA	06/07/19	1.00	15000.00	2978.00	3006.00
		WEIGHTED AVERAGE FOR THE SECOND QUARTER		1.00	15000.00	2978.00	3006.00
		WEIGHTED AVERAGE FOR THE YEAR		5.00	21166.67	31818.44	19773.20

PROJECT NUMBER	ITEM NUMBER/ PROJECT LOCATION	ITEM DESCRIPTION/ PROJECT LOCATION	DATE LET	UNIT/ QUANTITY	ENGR. EST.	AVERAGE BID	AWARDED BID
===== 630-86810		Traffic Signal (Temp)		Each	=====		
ER119A-065	PR SH 119A BOULDER CANYON	01/03/19	8.00	23125.00	22528.25	25000.00	
STA119A-069	SH 119: NEDERLAND - EAST						
ER072A-040	PR SH72A FLOOD PERMANENT REPA	01/31/19	3.00	5000.00	34049.19	44000.00	
NHPP072A-041	PR SH72A FLOOD PERMANENT REPA						
NHPP145A-065	SH 145 PASSING LANES AT DEEP	02/14/19	1.00	20000.00	17847.47	12000.00	
NHPP0741-022	SH 74: I-70 TO CR 65 RESURFAC	02/14/19	2.00	18000.00	17072.08	7925.00	
	WEIGHTED AVERAGE FOR THE FIRST QUARTER		14.00	18285.71	25605.25	25703.57	
STR 141A-040	R5 YEAR 4 BRDG PREV MAINT RAM	06/20/19	3.00	16000.00	5500.00	6000.00	
	WEIGHTED AVERAGE FOR THE SECOND QUARTER		3.00	16000.00	5500.00	6000.00	
	WEIGHTED AVERAGE FOR THE YEAR		17.00	17882.35	24591.54	22226.47	
===== 632-00000		Night Work Lighting		LUMP SUM	=====		
NHPPR500-173	US 160_550 DURANGO SIGNALS OP	01/03/19	1.00	10000.00	19400.00	8800.00	
ER119A-065	PR SH 119A BOULDER CANYON	01/03/19	1.00	50000.00	52271.61	1.00	
STA119A-069	SH 119: NEDERLAND - EAST						
STR0132-021	SH 13-MOFFAT COUNTY-CR 3 SOUT	01/10/19	1.00	10000.00	18510.00	2500.00	
NHPPR100-250	PACKAGE A (I-25 / I-70 / I-76	01/24/19	1.00	10000.00	105728.85	23000.00	
NHPP070A-028	FALL RIVER ROAD BRIDGE	02/21/19	1.00	15000.00	22938.01	29900.00	
NHPP0702-378	I-70 OFFICERS GULCH TO FRISCO	03/14/19	1.00	50000.00	108791.66	56374.99	
STM0242-077	US24 - 8TH ST TO WEST OF MANI	03/28/19	1.00	10000.00	140000.00	40000.00	
	WEIGHTED AVERAGE FOR THE FIRST QUARTER		7.00	22142.86	62555.88	22939.43	
NHPP030A-035	US 285/SH30	04/04/19	1.00	15000.00	48000.00	48000.00	
IM0252-472	I-25 CABLE BARRIER PHASE III	04/04/19	1.00	50000.00	70000.00	40000.00	
	WEIGHTED AVERAGE FOR THE SECOND QUARTER		2.00	32500.00	62666.67	44000.00	
	WEIGHTED AVERAGE FOR THE YEAR		9.00	24444.44	62565.65	27619.55	
===== 641-10000		Shotcrete		Sq Yard	=====		
STAR200-242	R2 NORTH PROGRAM WALL REPAIRS	01/03/19	218.00	250.00	172.92	136.00	

COLORADO DEPARTMENT OF TRANSPORTATION
ITEM UNIT COSTS BY PROJECTS -- 2019 COST DATA

13:44 Wednesday, August 7, 2019 357

PROJECT NUMBER	ITEM NUMBER/ PROJECT LOCATION	ITEM DESCRIPTION/ PROJECT LOCATION	DATE LET	UNIT/ QUANTITY	ENGR. EST.	AVERAGE BID	AWARDED BID
=====	641-10000	Shotcrete		Sq Yard	=====	=====	=====
ER119A-065	PR SH 119A BOULDER CANYON	PR SH 119A BOULDER CANYON	01/03/19	164.00	500.00	206.54	215.00
STA119A-069	SH 119: NEDERLAND - EAST	SH 119: NEDERLAND - EAST					
	WEIGHTED AVERAGE FOR THE FIRST QUARTER			382.00	357.33	198.15	169.92
NHPP0703-445	I-70 WESTBOUND PEAK PERIOD SH 04/25/19			80.00	120.00	663.51	652.00
	WEIGHTED AVERAGE FOR THE SECOND QUARTER			80.00	120.00	663.51	652.00
	WEIGHTED AVERAGE FOR THE YEAR			462.00	316.23	254.33	253.39
=====	641-10010	Initial Shotcrete Facing		Sq Foot	=====	=====	=====
ER119A-065	PR SH 119A BOULDER CANYON	PR SH 119A BOULDER CANYON	01/03/19	6,153.00	60.00	25.57	20.00
STA119A-069	SH 119: NEDERLAND - EAST	SH 119: NEDERLAND - EAST					
	WEIGHTED AVERAGE FOR THE FIRST QUARTER			6,153.00	60.00	25.57	20.00
	WEIGHTED AVERAGE FOR THE YEAR			6,153.00	60.00	25.57	20.00
=====	641-10070	Shotcrete Sculpting		Sq Yard	=====	=====	=====
NHPP0703-445	I-70 WESTBOUND PEAK PERIOD SH 04/25/19			80.00	300.00	116.52	118.00
	WEIGHTED AVERAGE FOR THE SECOND QUARTER			80.00	300.00	116.52	118.00
	WEIGHTED AVERAGE FOR THE YEAR			80.00	300.00	116.52	118.00
=====	642-00010	Exploder (Ty 1) (Install)		Each	=====	=====	=====
C0502-085	US 50 MM 201.8 MONARCH AVALAN	US 50 MM 201.8 MONARCH AVALAN	06/27/19	3.00	25000.00	31503.00	20590.00
	WEIGHTED AVERAGE FOR THE SECOND QUARTER			3.00	25000.00	31503.00	20590.00
	WEIGHTED AVERAGE FOR THE YEAR			3.00	25000.00	31503.00	20590.00
=====	642-00030	Cntrl Shelter (Ty 1) (Install)		Each	=====	=====	=====
C0502-085	US 50 MM 201.8 MONARCH AVALAN	US 50 MM 201.8 MONARCH AVALAN	06/27/19	1.00	15000.00	36983.00	25550.00
	WEIGHTED AVERAGE FOR THE SECOND QUARTER			1.00	15000.00	36983.00	25550.00
	WEIGHTED AVERAGE FOR THE YEAR			1.00	15000.00	36983.00	25550.00