

2020

COST DATA

January – June



Compiled By
Engineering Estimates and Market Analysis Unit
of the
Contracts and Market Analysis Branch

October 2, 2020

COLORADO COST DATA

FOREWORD

The Colorado Department of Transportation's Engineering Estimates and Market Analysis (EEMA) Unit, of the Contracts and Market Analysis Branch, publishes the Cost Data Book annually. A joint effort has been made between the Department's sections and the EEMA Unit to gather and record cost data for this publication.

The following data includes weighted average prices for items on highway construction projects that were bid during the 2020 calendar year. Caution should be used in applying these historical averages to specific projects. Allowances for varying geographic, climatic, social, economic conditions and type of project should be made.

Changes and improvements are continually being made to update and increase the usefulness for future issues. Comments and suggestions for improvements for users of this publication are welcome.

2020 COST DATA
CONSTRUCTION
TABLE OF CONTENTS

	<u># OF PAGES</u>
LIST OF 2020 BID PROJECTS	5
BRIDGE COST PER SQUARE FEET	1
ITEM UNIT COSTS BY PROJECTS	355

Colorado Department of Transportation
 2020 Cost Data
 PROJECTS BID FROM 01/01/20 THROUGH 06/30/20

10:52 Friday, October 2, 2020 1

BID LETTING	CONTRACTOR/ PROJECT NUMBER	LOCATION	DIST	TERRAIN	BIDS	AWARDED BID	INDEX
20200109	SIMON CONTRACTORS STA0142-066	SH 14 New Raymer West	4	R	4	\$5,477,794.00	99.11
20200109	MARTIN MARIETTA MATERIALS NHPP0343-041	I-76 & US 34 FT. MORGAN AREA R	4	P	3	\$19,964,032.84	114.09
20200109	MOUNTAIN CONSTRUCTORS, INC. FSA0341-097	US 34 & MACGREGOR INTERSECTION	4	M	1	\$1,871,822.50	122.04
20200109	HAMON INFRASTRUCTURE, INC. FSA0253-262	I-25 SB BOTTLENECK I-76 TO I-7	1	U	3	\$1,356,000.00	108.39
20200109	STURGEON ELECTRIC COMPANY, INC NHPP0253-265	I-25 AT ERIE PARKWAY ON AND OF	4	R	3	\$756,000.00	96.02
20200109	SURFACE PREPARATION TECHNOLOGIES SHER500-210	R5 FY19 CENTER LINE RUMBLE STR	5	R	2	\$887,234.48	113.49
20200116	ZAK DIRT, INC. BR0343-040 FBR0343-043	US 34 REPUBLICAN RIVER BRIDGES US 34 D-28-P STRUCTURE REPLACE	4 4	P P	6	\$5,310,755.65	101.62
20200116	Kilgore Companies, LLC dba Elam STR131A-038	Construc SH 131 MP 51.95-55.73, ROUTE C	3	M	2	\$1,359,498.00	90.33
20200116	MCATEE CONSTRUCTION CO. STA006A-067	SH 6 Merino to Atwood	4	R	2	\$3,766,927.45	96.38
20200123	APC SOUTHERN CONSTRUCTION COMPANY, LLC NH 0503-093	US50 WEST OF TEXAS CREEK MP 25	2	M	2	\$7,035,527.04	111.68
20200123	REDLINE PIPELINE, LLC PWQM240-172	El Paso County, north Colorado	2	R	2	\$7,664,700.70	116.13
20200130	OLDCASTLE SW GROUP, INC. STR141A-044	SH 141 AND SH 145, FROM SLICKR	5	R	5	\$10,688,093.10	92.40
20200130	AMERICAN WEST CONSTRUCTION, LLC STR012A-050	CULVERT REPAIR I-25 AND US 350	2	P	1	\$547,985.00	110.70
20200206	MCATEE CONSTRUCTION CO. STA059A-036	SH 59 SEIBERT TO COPE	4	P	2	\$12,072,994.45	114.74
20200206	BRANNAN SAND AND GRAVEL, LLC STA0703-443	I-70 EJMT TUNNELS PAVING	1	M	2	\$5,223,224.95	108.53
20200206	DILLIE AND KUHN, INC. ITS0761-231	ITS FIBER AND CAMERAS ON I-76	00	P	5	\$3,179,048.10	72.30
20200206	AMERICAN CIVIL CONSTRUCTORS, LLC dba A NHPP 0852-116	US85:HAMPDEN TO FLORIDA-RESURF	1	U	2	\$7,686,500.00	119.92

Colorado Department of Transportation
 2020 Cost Data
 PROJECTS BID FROM 01/01/20 THROUGH 06/30/20

10:52 Friday, October 2, 2020 2

BID LETTING	CONTRACTOR/ PROJECT NUMBER	LOCATION	DIST	TERRAIN	BIDS	AWARDED BID	INDEX
20200206	ROADSAFE TRAFFIC SYSTEMS, INC MTCER300-257	R3 FY 20/21 Region Wide Epoxy	3	M	2	\$3,474,413.60	106.39
20200206	HAMILTON CONSTRUCTION CO. NHPP4701-134	C-470 NOISE WALL WEST OF LUCEN	1	U	5	\$3,357,952.85	84.13
20200213	A and S CONSTRUCTION CO. STA069A-033	SH69 MP 58.7 TO 71.58	2	M	2	\$5,376,000.00	114.38
20200213	DURAN EXCAVATING, INC. FSA2873-194	US 287 Longmont Intersection I	4	U	6	\$1,160,406.20	106.49
20200213	A and S CONSTRUCTION CO. STR116A-001	SH 116 A Surface Treatment Pro	2	P	3	\$8,883,000.00	92.53
20200213	Straight Stripe Painting, Inc. MTCER500-213	R5 FY 20 / FY 21 STRIPING	5	M	4	\$2,068,435.00	116.92
20200227	Casper Electric, Inc. NHPP0702-359	I-70 No Name Tunnel Lighting	3	M	4	\$3,425,884.84	88.90
20200227	Casper Electric, Inc. C0402-094	US 40 GRAND COUNTY SIGNAL REPL	3	R	2	\$1,081,340.90	97.02
20200227	MARTIN MARIETTA MATERIALS NH0242-085	US 24 M.P. 291.38 to M.P. 296.	2	R	3	\$5,351,155.83	113.85
20200227	A and S CONSTRUCTION CO. STR0101-027	SH 10 Overlay La Junta West	2	P	3	\$6,758,000.00	96.46
20200305	APC SOUTHERN CONSTRUCTION COMPANY, LLC NHPP0171-105	SH 17 MP 84.5 to US 285 & SH 1	5	P	3	\$21,320,469.84	95.83
20200305	SEMA CONSTRUCTION, INC. NHPP0091-044	SH 9 FRISCO MAIN ST TO IRON SP	3	M	3	\$14,138,928.75	119.86
20200305	OLDCASTLE SW GROUP, INC. NHPP0502-082	US 50 MONTROSE RE CHIP SEAL	3	R	4	\$3,758,750.22	94.53
20200305	KSK, LLC STRR300-249	Grand and Jackson Counties ADA	3	M	3	\$1,400,000.00	110.27
20200305	TEZAK HEAVY EQUIPMENT CO., INC. BR025A-046	K-18-U ON I-25 AT MP112 BRIDGE	2	R	7	\$2,071,985.91	94.18
20200305	CASTLE ROCK CONST. CO. OF COLO, LLC STR2871-038	US 287 Passing Lanes Springfie	2	P	2	\$4,519,619.33	100.44
20200305	OLDCASTLE SW GROUP, INC. NHPP145A-080	SH 145 Keystone-Placerville Re	5	M	1	\$4,469,722.20	91.55

Colorado Department of Transportation
 2020 Cost Data
 PROJECTS BID FROM 01/01/20 THROUGH 06/30/20

10:52 Friday, October 2, 2020 3

BID LETTING	CONTRACTOR/ PROJECT NUMBER	LOCATION	DIST	TERRAIN	BIDS	AWARDED BID	INDEX
20200305	KSK, LLC CC080-037	VARIOUS ADA RAMPS ALONG NORTH	3	U	4	\$300,000.00	70.28
20200305	OLDCASTLE SW GROUP, INC. C0641-106	SH 64 Meeker West Rural Resurf	3	R	2	\$4,422,918.00	70.62
20200326	MOUNTAIN VALLEY CONTRACTING, INC. HPP 0501-067	US 50 AND SH 92 DELTA INTERSEC	3	U	2	\$2,761,591.15	110.11
20200326	KIRKLAND CONSTRUCTION, LLLP NH050A-034	US50A PUEBLO WEST PURCELL INTE	2	R	8	\$32,992,239.13	103.10
20200326	DURAN EXCAVATING, INC. SHE 0703-461	I-70 and Kipling North Phase	1	U	5	\$2,391,211.25	96.23
20200402	CASTLE ROCK CONST. CO. OF COLO, LLC IM0761-226	I76/SH52 Interchange	4	R	7	\$11,765,116.33	89.67
20200402	KSK, LLC STA340A-021	SH340 MP 6-6.76 MESA COUNTY	3	R	3	\$1,235,000.00	107.36
20200402	OLDCASTLE SW GROUP, INC. NHPP1602-169	US 160 WC TUNNEL EAST RESURFAC	5	M	3	\$6,333,543.94	100.47
20200402	Kilgore Companies, LLC dba Elam STR0341-101	Construc SH 34 North of Grandby Resurfa	3	M	4	\$7,604,366.80	97.23
20200402	OLDCASTLE SW GROUP, INC. STR092A-030	SH92 MP 31.748-48.5, DELTA AND	3	M	2	\$5,574,468.91	97.49
20200402	ROADSAFE TRAFFIC SYSTEMS, INC MTCER300-259	MTCE R3 FY20/21 Region Wide St	3	M	2	\$753,924.25	110.04
20200409	INTERMOUNTAIN SLURRY SEAL, INC. NHPP1601-077	US 160 MP 29.750 - MP 34.891	5	R	3	\$1,303,347.00	83.16
20200409	ABCO CONTRACTING, INC. SFTY2254-091	225 Ramp Improvements	1	U	2	\$3,226,884.00	76.19
20200409	TRICON 2, LLC IM0252-473	I-25 CABLE BARRIER PHASE IV	2	R	2	\$2,277,000.00	103.50
20200409	CC ENTRPRS TRAFFIC CONTROL SPECIALISTS SHER100-339	WWD TRAFFIC CONTROL ENHANCEMEN	1	R	1	\$2,165,914.00	114.25
20200423	CASTLE ROCK CONST. CO. OF COLO, LLC CC0852-106 FBR0852-108	US-85 LOUVIERS TO MP 191.75 US-85 BETWEEN LOUVIERS AND MP	1 1	R R	8	\$23,753,931.10	86.61
20200423	W.L. CONTRACTORS, INC. C1211-090	SH-121 & 29th Ave / SH-121 & S	1	U	3	\$1,679,401.00	95.54

Colorado Department of Transportation
2020 Cost Data
PROJECTS BID FROM 01/01/20 THROUGH 06/30/20

10:52 Friday, October 2, 2020 4

BID LETTING	CONTRACTOR/ PROJECT NUMBER	LOCATION	DIST	TERRAIN	BIDS	AWARDED BID	INDEX
20200430	CONCRETE WORKS OF COLORADO INC. FSA1602-159	US 160 AND SH 17 INTERSECTION	5	U	3	\$5,247,258.00	160.28
20200430	OLDCASTLE SW GROUP, INC. C1601-082	Hawkins Signal and Curb Ramps	5	U	3	\$1,827,783.00	126.03
20200507	W.L. CONTRACTORS, INC. NHPPR100-303	LONG MAST ARM SIGNALS PROJECT	1	U	3	\$1,762,713.21	93.97
20200507	ZAK DIRT, INC. C0853-112	US85 & WCR98 INTERSECTION IMPR	4	R	8	\$1,913,218.60	79.71
20200507	ZAK DIRT, INC. FBR0343-042	US 34 D-27-G STRUCTURE REPLACE	4	P	9	\$2,466,070.75	88.17
20200514	INTERFACE COMMUNICATIONS COMPANY ITS SW02-304	ITS FIBER TO STATE BUILDINGS I	00	M	4	\$2,136,538.00	58.90
20200514	OLDCASTLE SW GROUP, INC. NHPP0402-098	US 40 CHIP SEAL MP 126 TO MP 1	3	M	3	\$1,038,174.50	102.50
20200515	RLW/SEMA, A Joint Venture NHPP0253-276	I-25 EXPRESS LANES SEGMENT 5 &	4	R	1	\$8,274,649.78	100.59
20200521	ROADSAFE TRAFFIC SYSTEMS, INC MTCE R100-341	Various Highways in Region 1	1	U	2	\$12,348,544.30	107.77
20200528	KIRKLAND CONSTRUCTION, LLLP NH050A-035 NH050A-037	US 50A Pueblo Regional Pond US 50A Pueblo Regional Pond	2 2	R R	8	\$1,975,485.70	89.79
20200528	STURGEON ELECTRIC COMPANY, INC SHER400-373	R4 Signal Head Backplate Insta	4	R	2	\$995,960.00	73.40
20200528	PAONIA, INC ITS SW02-303	R1: US 285, SH 83 R2: SH 83, S	00	R	5	\$2,221,563.29	57.59
20200528	TLM CONSTRUCTORS, INC. IM025A-048	Northbound I-25 bridge at Exit	2	M	3	\$610,899.00	81.45
20200528	HARVEY CONTRACTORS INC MTCER200-265	Pueblo	2	R	4	\$3,254,518.92	95.72
20200611	PAONIA, INC ITSSW01-719	FY 20 ITS CAPITAL REPLACEMENT	00	P	2	\$1,488,325.00	60.77
20200611	W.L. CONTRACTORS, INC. FSAR400-356	FY 20 SIGNAL POLE REPLACEMENTS	4	U	3	\$630,460.00	91.28
20200618	MAIN ELECTRIC LTD SHE016A-043	SH 21 & 16 SIGNALS PROJECT	2	U	5	\$1,409,599.14	78.31

Colorado Department of Transportation
 2020 Cost Data
 PROJECTS BID FROM 01/01/20 THROUGH 06/30/20

10:52 Friday, October 2, 2020 5

BID LETTING	CONTRACTOR/ PROJECT NUMBER	LOCATION	DIST	TERRAIN	BIDS	AWARDED BID	INDEX	
20200623	LAWRENCE CONSTRUCTION CO. NHPP5501-029	US 550/160 CONNECTION SOUTH DB	5	M	1	\$77,748,000.00	100.00	
20200625	RALPH L. WADSWORTH CONSTRUCTION CO., LLC NHPPR100-251	SH 2/ Vasquez	1	U	2	\$919,658.19	103.51	
					=====	=====	=====	
					TOTALS	236	\$426,274,479.97	99.15

Colorado Department of Transportation
 2020 Cost Data
 BRIDGE COST PER SQUARE FOOT
 (01/01/20 THROUGH 06/30/20)

10:52 Friday, October 2, 2020 1

DATE LET	PROJECT NUMBER/ PROJECT LOCATION	TERR/ BRIDGE ID	LENGTH	WIDTH	TOTAL SQUARE FT	TOTAL COST	COST PER SQUARE FOOT
BRIDGE REPAIR							
200123	NH 0503-093 US50 WEST OF TEXAS CREEK MP 25	M 0300	63.0000	66.6600	4199.6	\$64,349	\$15.32
		0301	84.3300	34.0000	2867.2	\$45,164	\$15.75
		0302	141.0000	73.5000	10363.5	\$72,793	\$7.02
200206	NHPP 0852-116 US85:HAMPDEN TO FLORIDA-RESURF	U 0300	200.0000	120.0000	24000.0	\$1,909,206	\$79.55
200213	STA069A-033 SH69 MP 58.7 TO 71.58	M 0300	123.3000	25.0000	3082.5	\$36,358	\$11.79
			WEIGHTED AVERAGE COST: NEW STRUCTURES		44512.8	\$2,127,869	\$47.80
CONCRETE SLAB AND GIRDER							
200206	STA059A-036 SH 59 SEIBERT TO COPE	P 0300	120.0000	34.0000	4080.0	\$530,047	\$129.91
200507	FBR0343-042 US 34 D-27-G STRUCTURE REPLACE	P 0300	82.5000	48.0000	3960.0	\$842,133	\$212.66
			WEIGHTED AVERAGE COST: NEW STRUCTURES		8040.0	\$1,372,179	\$170.67
CONCRETE SLAB BRIDGE							
200227	STR0101-027 SH 10 Overlay La Junta West	P 0300	32.0000	41.0000	1312.0	\$43,017	\$32.79
			WEIGHTED AVERAGE COST: NEW STRUCTURES		1312.0	\$43,017	\$32.79
PRESTRES GIRDER (BOX SECTION)							
200116	BR0343-040 US 34 REPUBLICAN RIVER BRIDGES	P 0300	115.5000	43.0000	4966.5	\$1,026,755	\$206.74
200116	FBR0343-043 US 34 D-28-P STRUCTURE REPLACE	P 0300	128.5000	43.0000	5525.5	\$1,230,872	\$222.76
			WEIGHTED AVERAGE COST: NEW STRUCTURES		10492.0	\$2,257,627	\$215.18

PROJECT NUMBER	ITEM NUMBER/ PROJECT LOCATION	ITEM DESCRIPTION/ PROJECT LOCATION	DATE LET	UNIT/ QUANTITY	ENGR. EST.	AVERAGE BID	AWARDED BID
===== 201-00000		Clear and Grub		LUMP SUM	=====		
FSA0253-262	I-25 SB BOTTLENECK I-76 TO I-	01/09/20	1.00	15000.00	30509.00	20000.00	
FSA0341-097	US 34 & MACGREGOR INTERSECTIO	01/09/20	1.00	7500.00	30000.00	30000.00	
NHPP0343-041	I-76 & US 34 FT. MORGAN AREA	01/09/20	1.00	12500.00	55801.76	13596.00	
NHPP4701-134	C-470 NOISE WALL WEST OF LUCE	02/06/20	1.00	5000.00	33000.00	15000.00	
FSA2873-194	US 287 Longmont Intersection	02/13/20	1.00	10000.00	24614.17	5200.00	
NHPP0091-044	SH 9 FRISCO MAIN ST TO IRON S	03/05/20	1.00	26000.00	55750.00	75000.00	
NH050A-034	US50A PUEBLO WEST PURCELL INT	03/26/20	1.00	320000.00	319725.00	115000.00	
HPP 0501-067	US 50 AND SH 92 DELTA INTERSE	03/26/20	1.00	5000.00	18160.00	22320.00	
SHE 0703-461	I-70 and Kipling North Phase	03/26/20	1.00	9000.00	17463.60	4818.00	
	WEIGHTED AVERAGE FOR THE FIRST QUARTER		9.00	45555.56	95841.81	33437.11	
IM0761-226	I76/SH52 Interchange	04/02/20	1.00	50000.00	144432.86	29999.99	
STA340A-021	SH340 MP 6-6.76 MESA COUNTY	04/02/20	1.00	25000.00	9670.00	18100.00	
IM0252-473	I-25 CABLE BARRIER PHASE IV	04/09/20	1.00	60000.00	37500.00	25000.00	
SFTY2254-091	225 Ramp Improvements	04/09/20	1.00	20000.00	33000.00	59000.00	
CC0852-106	US-85 LOUVIERS TO MP 191.75	04/23/20	1.00	37500.00	240540.56	166399.60	
FBR0852-108	US-85 BETWEEN LOUVIERS AND MP						
FSA1602-159	US 160 AND SH 17 INTERSECTION	04/30/20	1.00	10000.00	83700.00	146100.00	
C0853-112	US85 & WCR98 INTERSECTION IMP	05/07/20	1.00	18000.00	22367.50	15100.00	
NHPPR100-303	LONG MAST ARM SIGNALS PROJECT	05/07/20	1.00	8000.00	11290.31	870.00	
NHPP0253-276	I-25 EXPRESS LANES SEGMENT 5	05/15/20	1.00	142000.00	159773.52	159773.52	
NH050A-035	US 50A Pueblo Regional Pond	05/28/20	1.00	40000.00	36097.25	35000.00	
NH050A-037	US 50A Pueblo Regional Pond						
SHE016A-043	SH 21 & 16 SIGNALS PROJECT	06/18/20	1.00	21000.00	5248.20	2541.00	
	WEIGHTED AVERAGE FOR THE SECOND QUARTER		11.00	39227.27	80881.36	59807.65	
	WEIGHTED AVERAGE FOR THE YEAR		20.00	42075.00	87143.87	47940.91	
===== 201-00001		Clear and Grub		Acre	=====		
PWQM240-172	El Paso County, north Colorad	01/23/20	4.00	6250.00	21150.00	18300.00	
NHPP0171-105	SH 17 MP 84.5 to US 285 & SH	03/05/20	157.00	1000.00	820.85	957.54	
STR2871-038	US 287 Passing Lanes Springfi	03/05/20	13.00	8000.00	1602.61	1010.53	
BR025A-046	K-18-U ON I-25 AT MP112 BRIDG	03/05/20	1.00	10000.00	26161.56	3106.92	
	WEIGHTED AVERAGE FOR THE FIRST QUARTER		175.00	1691.43	1524.64	1370.16	
	WEIGHTED AVERAGE FOR THE YEAR		175.00	1691.43	1524.64	1370.16	
===== 201-00005		Rem of Debris		LUMP SUM	=====		
NHPP0343-041	I-76 & US 34 FT. MORGAN AREA	01/09/20	1.00	5000.00	13834.15	23656.00	

PROJECT NUMBER	ITEM NUMBER/ PROJECT LOCATION	ITEM DESCRIPTION/ PROJECT LOCATION	DATE LET	UNIT/ QUANTITY	ENGR. EST.	AVERAGE BID	AWARDED BID
=====	201-00005	Rem of Debris		LUMP SUM	=====	=====	=====
NHPP 0852-116		US85:HAMPDEN TO FLORIDA-RESUR	02/06/20	1.00	15000.00	27500.00	25000.00
	WEIGHTED AVERAGE FOR THE FIRST QUARTER			2.00	10000.00	19300.49	24328.00
	WEIGHTED AVERAGE FOR THE YEAR			2.00	10000.00	19300.49	24328.00
=====	202-00000	Rem Str and Obstructions		LUMP SUM	=====	=====	=====
PWQM240-172		El Paso County, north Colorad	01/23/20	1.00	5000.00	10250.00	7500.00
	WEIGHTED AVERAGE FOR THE FIRST QUARTER			1.00	5000.00	10250.00	7500.00
	WEIGHTED AVERAGE FOR THE YEAR			1.00	5000.00	10250.00	7500.00
=====	202-00001	Rem Structure		Each	=====	=====	=====
NHPP0253-276		I-25 EXPRESS LANES SEGMENT 5	05/15/20	2.00	2000.00	2623.57	2623.57
	WEIGHTED AVERAGE FOR THE SECOND QUARTER			2.00	2000.00	2623.57	2623.57
	WEIGHTED AVERAGE FOR THE YEAR			2.00	2000.00	2623.57	2623.57
=====	202-00002	Rem of Structure (Spec)		Each	=====	=====	=====
CC0852-106		US-85 LOUVIERS TO MP 191.75	04/23/20	1.00	5000.00	5017.45	950.30
FBR0852-108		US-85 BETWEEN LOUVIERS AND MP					
	WEIGHTED AVERAGE FOR THE SECOND QUARTER			1.00	5000.00	5017.45	950.30
	WEIGHTED AVERAGE FOR THE YEAR			1.00	5000.00	5017.45	950.30
=====	202-00003	Rem of Structure (Spec)		LUMP SUM	=====	=====	=====
NHPP0253-276		I-25 EXPRESS LANES SEGMENT 5	05/15/20	1.00	39000.00	37614.04	37614.04
	WEIGHTED AVERAGE FOR THE SECOND QUARTER			1.00	39000.00	37614.04	37614.04
	WEIGHTED AVERAGE FOR THE YEAR			1.00	39000.00	37614.04	37614.04
=====	202-00008	Tree Trimming		Hour	=====	=====	=====
NHPP0702-359		I-70 No Name Tunnel Lighting	02/27/20	8.00	300.00	90.73	150.00
	WEIGHTED AVERAGE FOR THE FIRST QUARTER			8.00	300.00	90.73	150.00
	WEIGHTED AVERAGE FOR THE YEAR			8.00	300.00	90.73	150.00

PROJECT NUMBER	ITEM NUMBER/ PROJECT LOCATION	ITEM DESCRIPTION/ PROJECT LOCATION	DATE LET	UNIT/ QUANTITY	ENGR. EST.	AVERAGE BID	AWARDED BID
===== 202-00009		Tree Trimming		LUMP SUM	=====		
NHPP145A-080	SH 145 Keystone-Placerville R		03/05/20	1.00	3000.00	5975.00	5975.00
	WEIGHTED AVERAGE FOR THE FIRST QUARTER			1.00	3000.00	5975.00	5975.00
	WEIGHTED AVERAGE FOR THE YEAR			1.00	3000.00	5975.00	5975.00
===== 202-00010		Rem Tree		Each	=====		
FSA0341-097	US 34 & MACGREGOR INTERSECTIO		01/09/20	4.00	300.00	750.00	750.00
BR0343-040	US 34 REPUBLICAN RIVER BRIDGE		01/16/20	9.00	750.00	779.03	1060.00
FBR0343-043	US 34 D-28-P STRUCTURE REPLAC						
ITS0761-231	ITS FIBER AND CAMERAS ON I-76		02/06/20	1.00	500.00	1192.00	150.00
C0402-094	US 40 GRAND COUNTY SIGNAL REP		02/27/20	1.00	1000.00	2050.00	2500.00
NH050A-034	US50A PUEBLO WEST PURCELL INT		03/26/20	3.00	250.00	759.50	1000.00
SHE 0703-461	I-70 and Kipling North Phase		03/26/20	1.00	350.00	2122.00	1700.00
	WEIGHTED AVERAGE FOR THE FIRST QUARTER			19.00	555.26	893.25	1046.84
IM0761-226	I76/SH52 Interchange		04/02/20	9.00	500.00	457.00	540.00
CC0852-106	US-85 LOUVIERS TO MP 191.75		04/23/20	71.00	320.00	760.94	445.00
FBR0852-108	US-85 BETWEEN LOUVIERS AND MP						
FSA1602-159	US 160 AND SH 17 INTERSECTION		04/30/20	1.00	800.00	2515.67	537.00
FBR0343-042	US 34 D-27-G STRUCTURE REPLAC		05/07/20	1.00	350.00	833.23	1200.00
	WEIGHTED AVERAGE FOR THE SECOND QUARTER			82.00	345.98	740.36	465.76
	WEIGHTED AVERAGE FOR THE YEAR			101.00	385.35	759.86	575.07
===== 202-00015		Rem Headwall		Each	=====		
NHPP145A-080	SH 145 Keystone-Placerville R		03/05/20	1.00	1400.00	750.00	750.00
HPP 0501-067	US 50 AND SH 92 DELTA INTERSE		03/26/20	2.00	1500.00	3027.48	1586.00
	WEIGHTED AVERAGE FOR THE FIRST QUARTER			3.00	1466.67	2571.98	1307.33
CC0852-106	US-85 LOUVIERS TO MP 191.75		04/23/20	17.00	2500.00	824.69	401.50

COLORADO DEPARTMENT OF TRANSPORTATION
 ITEM UNIT COSTS BY PROJECTS -- 2020 COST DATA

10:58 Friday, October 2, 2020 4

PROJECT NUMBER	ITEM NUMBER/ PROJECT LOCATION	ITEM DESCRIPTION/ PROJECT LOCATION	DATE LET	UNIT/ QUANTITY	ENGR. EST.	AVERAGE BID	AWARDED BID
===== 202-00015		Rem Headwall		Each =====			
FBR0852-108		US-85 BETWEEN LOUVIERS AND MP					
NHPP0253-276		I-25 EXPRESS LANES SEGMENT 5	05/15/20	3.00	2000.00	2259.07	2259.07
	WEIGHTED AVERAGE FOR THE SECOND QUARTER			20.00	2425.00	855.65	680.14
	WEIGHTED AVERAGE FOR THE YEAR			23.00	2300.00	915.25	761.94
===== 202-00019		Rem Inlet		Each =====			
FSA0341-097		US 34 & MACGREGOR INTERSECTIO	01/09/20	2.00	800.00	1300.00	1300.00
NHPP0091-044		SH 9 FRISCO MAIN ST TO IRON S	03/05/20	4.00	2000.00	1558.33	2000.00
NH050A-034		US50A PUEBLO WEST PURCELL INT	03/26/20	8.00	1000.00	1082.67	1600.00
HPP 0501-067		US 50 AND SH 92 DELTA INTERSE	03/26/20	3.00	1100.00	1777.00	1121.00
SHE 0703-461		I-70 and Kipling North Phase	03/26/20	1.00	1245.00	2008.00	1028.00
	WEIGHTED AVERAGE FOR THE FIRST QUARTER			18.00	1230.28	1250.48	1543.94
IM0761-226		I76/SH52 Interchange	04/02/20	5.00	1200.00	1121.16	938.00
CC0852-106		US-85 LOUVIERS TO MP 191.75	04/23/20	2.00	1000.00	1379.24	2750.00
FBR0852-108		US-85 BETWEEN LOUVIERS AND MP					
	WEIGHTED AVERAGE FOR THE SECOND QUARTER			7.00	1142.86	1202.13	1455.71
	WEIGHTED AVERAGE FOR THE YEAR			25.00	1205.80	1232.87	1519.24
===== 202-00020		Rem CBC		Each =====			
CC0852-106		US-85 LOUVIERS TO MP 191.75	04/23/20	9.00	10000.00	6883.54	1782.00
FBR0852-108		US-85 BETWEEN LOUVIERS AND MP					
	WEIGHTED AVERAGE FOR THE SECOND QUARTER			9.00	10000.00	6883.54	1782.00
	WEIGHTED AVERAGE FOR THE YEAR			9.00	10000.00	6883.54	1782.00
===== 202-00021		Rem Manhole		Each =====			
PWQM240-172		El Paso County, north Colorad	01/23/20	1.00	2500.00	1291.50	1283.00
NHPP0091-044		SH 9 FRISCO MAIN ST TO IRON S	03/05/20	1.00	1500.00	1920.00	1500.00
NH050A-034		US50A PUEBLO WEST PURCELL INT	03/26/20	4.00	1200.00	1400.01	1500.00

COLORADO DEPARTMENT OF TRANSPORTATION
 ITEM UNIT COSTS BY PROJECTS -- 2020 COST DATA

10:58 Friday, October 2, 2020 5

PROJECT NUMBER	ITEM NUMBER/ PROJECT LOCATION	ITEM DESCRIPTION/ PROJECT LOCATION	DATE LET	UNIT/ QUANTITY	ENGR. EST.	AVERAGE BID	AWARDED BID
===== 202-00021		Rem Manhole		Each =====			
HPP 0501-067		US 50 AND SH 92 DELTA INTERSE	03/26/20	1.00	1200.00	3280.43	740.00
	WEIGHTED AVERAGE FOR THE FIRST QUARTER			7.00	1428.57	1530.87	1360.43
IM0761-226		I76/SH52 Interchange	04/02/20	1.00	1000.00	1209.13	1177.00
	WEIGHTED AVERAGE FOR THE SECOND QUARTER			1.00	1000.00	1209.13	1177.00
	WEIGHTED AVERAGE FOR THE YEAR			8.00	1375.00	1481.91	1337.50
===== 202-00023		Rem Emb Prot Ty 3		Each =====			
NHPP0253-276		I-25 EXPRESS LANES SEGMENT 5	05/15/20	2.00	1000.00	801.99	801.99
	WEIGHTED AVERAGE FOR THE SECOND QUARTER			2.00	1000.00	801.99	801.99
	WEIGHTED AVERAGE FOR THE YEAR			2.00	1000.00	801.99	801.99
===== 202-00024		Rem Emb Prot Ty 5		Each =====			
IM0761-226		I76/SH52 Interchange	04/02/20	4.00	500.00	521.32	489.00
	WEIGHTED AVERAGE FOR THE SECOND QUARTER			4.00	500.00	521.32	489.00
	WEIGHTED AVERAGE FOR THE YEAR			4.00	500.00	521.32	489.00
===== 202-00026		Rem S and D Pave		Sq Yard =====			
FSA0253-262		I-25 SB BOTTLENECK I-76 TO I-	01/09/20	402.00	25.00	27.42	25.00
STR012A-050		CULVERT REPAIR I-25 AND US 35	01/30/20	45.50	40.00	130.00	130.00
NH050A-034		US50A PUEBLO WEST PURCELL INT	03/26/20	109.00	18.50	16.63	36.00
	WEIGHTED AVERAGE FOR THE FIRST QUARTER			556.50	24.95	25.18	35.74
SFTY2254-091		225 Ramp Improvements	04/09/20	2,141.00	40.00	25.50	33.00
	WEIGHTED AVERAGE FOR THE SECOND QUARTER			2,141.00	40.00	25.50	33.00
	WEIGHTED AVERAGE FOR THE YEAR			2,697.50	36.90	25.39	33.57

PROJECT NUMBER	ITEM NUMBER/ PROJECT LOCATION	ITEM DESCRIPTION/ PROJECT LOCATION	DATE LET	UNIT/ QUANTITY	ENGR. EST.	AVERAGE BID	AWARDED BID
===== 202-00027		Rem Riprap		Sq Yard			
FSA0341-097		US 34 & MACGREGOR INTERSECTIO	01/09/20	43.00	20.00	32.00	32.00
PWQM240-172		El Paso County, north Colorad	01/23/20	121.00	25.00	40.50	59.00
NHPP0171-105		SH 17 MP 84.5 to US 285 & SH	03/05/20	3.00	250.00	727.70	1818.10
NHPP0091-044		SH 9 FRISCO MAIN ST TO IRON S	03/05/20	12.00	100.00	74.67	140.00
		WEIGHTED AVERAGE FOR THE FIRST QUARTER		179.00	32.60	61.86	87.43
SFTY2254-091		225 Ramp Improvements	04/09/20	26.00	75.00	57.50	89.00
		WEIGHTED AVERAGE FOR THE SECOND QUARTER		26.00	75.00	57.50	89.00
		WEIGHTED AVERAGE FOR THE YEAR		205.00	37.98	61.27	87.63
===== 202-00029		Rem Gabion		Cubic Yard			
STA059A-036		SH 59 SEIBERT TO COPE	02/06/20	78.00	50.00	68.00	61.00
		WEIGHTED AVERAGE FOR THE FIRST QUARTER		78.00	50.00	68.00	61.00
		WEIGHTED AVERAGE FOR THE YEAR		78.00	50.00	68.00	61.00
===== 202-00030		Rem Water Service		Each			
CC0852-106		US-85 LOUVIERS TO MP 191.75	04/23/20	1.00	2000.00	2207.42	3217.50
FBR0852-108		US-85 BETWEEN LOUVIERS AND MP					
NHPP0253-276		I-25 EXPRESS LANES SEGMENT 5	05/15/20	1.00	7000.00	2136.54	2136.54
		WEIGHTED AVERAGE FOR THE SECOND QUARTER		2.00	4500.00	2199.55	2677.02
		WEIGHTED AVERAGE FOR THE YEAR		2.00	4500.00	2199.55	2677.02
===== 202-00031		Rem of Fire Hydrant		Each			
IM0761-226		I76/SH52 Interchange	04/02/20	1.00	2000.00	1436.01	1611.00
		WEIGHTED AVERAGE FOR THE SECOND QUARTER		1.00	2000.00	1436.01	1611.00
		WEIGHTED AVERAGE FOR THE YEAR		1.00	2000.00	1436.01	1611.00

PROJECT NUMBER	ITEM NUMBER/ PROJECT LOCATION	ITEM DESCRIPTION/ PROJECT LOCATION	DATE LET	UNIT/ QUANTITY	ENGR. EST.	AVERAGE BID	AWARDED BID
===== 202-00033		Rem Pipe		Each	=====		
NHPP145A-080		SH 145 Keystone-Placerville R	03/05/20	2.00	2000.00	1500.00	1500.00
NHPP0091-044		SH 9 FRISCO MAIN ST TO IRON S	03/05/20	9.00	2000.00	3236.67	7000.00
NH050A-034		US50A PUEBLO WEST PURCELL INT	03/26/20	11.00	2500.00	4249.25	2300.00
		WEIGHTED AVERAGE FOR THE FIRST QUARTER		22.00	2250.00	3968.58	4150.00
		WEIGHTED AVERAGE FOR THE YEAR		22.00	2250.00	3968.58	4150.00
===== 202-00035		Rem Pipe		Lin Foot	=====		
FSA0341-097		US 34 & MACGREGOR INTERSECTIO	01/09/20	420.00	20.00	21.00	21.00
NHPP0343-041		I-76 & US 34 FT. MORGAN AREA	01/09/20	620.00	20.00	22.41	13.00
PWQM240-172		El Paso County, north Colorad	01/23/20	377.00	35.00	29.50	27.00
STR012A-050		CULVERT REPAIR I-25 AND US 35	01/30/20	42.00	50.00	120.00	120.00
NHPP0171-105		SH 17 MP 84.5 to US 285 & SH	03/05/20	76.00	30.00	82.83	48.48
NHPP0091-044		SH 9 FRISCO MAIN ST TO IRON S	03/05/20	20.00	30.00	122.17	190.00
NH050A-034		US50A PUEBLO WEST PURCELL INT	03/26/20	1,014.00	22.00	40.45	56.00
HPP 0501-067		US 50 AND SH 92 DELTA INTERSE	03/26/20	375.00	30.00	83.70	17.60
SHE 0703-461		I-70 and Kipling North Phase	03/26/20	61.00	35.00	55.00	42.00
		WEIGHTED AVERAGE FOR THE FIRST QUARTER		3,005.00	24.85	40.83	35.12
IM0761-226		I76/SH52 Interchange	04/02/20	776.00	28.00	25.58	18.99
STA340A-021		SH340 MP 6-6.76 MESA COUNTY	04/02/20	134.00	25.00	27.13	37.00
SFTY2254-091		225 Ramp Improvements	04/09/20	3.00	50.00	297.50	295.00
CC0852-106		US-85 LOUVIERS TO MP 191.75	04/23/20	656.00	25.00	42.95	13.20
FBR0852-108		US-85 BETWEEN LOUVIERS AND MP					
NHPP0253-276		I-25 EXPRESS LANES SEGMENT 5	05/15/20	2,953.00	30.48	33.48	33.48
		WEIGHTED AVERAGE FOR THE SECOND QUARTER		4,522.00	29.11	33.90	28.33
		WEIGHTED AVERAGE FOR THE YEAR		7,527.00	27.41	37.17	31.04
===== 202-00036		Rem of Pipe (Spec)		Lin Foot	=====		
NHPP0091-044		SH 9 FRISCO MAIN ST TO IRON S	03/05/20	183.00	5.00	19.83	35.00
		WEIGHTED AVERAGE FOR THE FIRST QUARTER		183.00	5.00	19.83	35.00
		WEIGHTED AVERAGE FOR THE YEAR		183.00	5.00	19.83	35.00

PROJECT NUMBER	ITEM NUMBER/ PROJECT LOCATION	ITEM DESCRIPTION/ PROJECT LOCATION	DATE LET	UNIT/ QUANTITY	ENGR. EST.	AVERAGE BID	AWARDED BID
===== 202-00037		Rem of End Section		Each	=====		
STR012A-050		CULVERT REPAIR I-25 AND US 35	01/30/20	1.00	650.00	2200.00	2200.00
STR2871-038		US 287 Passing Lanes Springfi	03/05/20	1.00	300.00	405.77	480.00
NHPP0091-044		SH 9 FRISCO MAIN ST TO IRON S	03/05/20	7.00	200.00	493.33	580.00
NH050A-034		US50A PUEBLO WEST PURCELL INT	03/26/20	20.00	280.00	317.50	550.00
		WEIGHTED AVERAGE FOR THE FIRST QUARTER		29.00	274.14	348.76	611.72
IM0761-226		I76/SH52 Interchange	04/02/20	15.00	300.00	347.32	231.01
CC0852-106		US-85 LOUVIERS TO MP 191.75	04/23/20	14.00	590.00	359.36	198.00
FBR0852-108		US-85 BETWEEN LOUVIERS AND MP					
NHPP0253-276		I-25 EXPRESS LANES SEGMENT 5	05/15/20	4.00	568.00	878.16	878.16
		WEIGHTED AVERAGE FOR THE SECOND QUARTER		33.00	455.52	363.03	295.45
		WEIGHTED AVERAGE FOR THE YEAR		62.00	370.68	356.54	443.38
===== 202-00039		Rem of Bollard		Each	=====		
STRR300-249		Grand and Jackson Counties AD	03/05/20	1.00	700.00	776.67	180.00
NHPP0091-044		SH 9 FRISCO MAIN ST TO IRON S	03/05/20	2.00	100.00	441.67	270.00
		WEIGHTED AVERAGE FOR THE FIRST QUARTER		3.00	300.00	553.33	240.00
C1601-082		Hawkins Signal and Curb Ramps	04/30/20	1.00	300.00	1095.00	1800.00
		WEIGHTED AVERAGE FOR THE SECOND QUARTER		1.00	300.00	1095.00	1800.00
		WEIGHTED AVERAGE FOR THE YEAR		4.00	300.00	688.75	630.00
===== 202-00047		Rem Elec Equipment		LUMP SUM	=====		
FSA0253-262		I-25 SB BOTTLENECK I-76 TO I-	01/09/20	1.00	5750.00	12600.00	1500.00
NHPP0702-359		I-70 No Name Tunnel Lighting	02/27/20	1.00	5000.00	6204.75	2500.00
		WEIGHTED AVERAGE FOR THE FIRST QUARTER		2.00	5375.00	8945.57	2000.00
CC0852-106		US-85 LOUVIERS TO MP 191.75	04/23/20	1.00	2000.00	5638.05	5500.00

COLORADO DEPARTMENT OF TRANSPORTATION
ITEM UNIT COSTS BY PROJECTS -- 2020 COST DATA

10:58 Friday, October 2, 2020 9

PROJECT NUMBER	ITEM NUMBER/ PROJECT LOCATION	ITEM DESCRIPTION/ PROJECT LOCATION	DATE LET	UNIT/ QUANTITY	ENGR. EST.	AVERAGE BID	AWARDED BID
=====	202-00047	Rem Elec Equipment		LUMP SUM	=====		
FBR0852-108		US-85 BETWEEN LOUVIERS AND MP					
	WEIGHTED AVERAGE FOR THE SECOND QUARTER			1.00	2000.00	5638.05	5500.00
	WEIGHTED AVERAGE FOR THE YEAR			3.00	4250.00	7181.56	3166.67
=====	202-00055	Rem of FO Cable		Lin Foot	=====		
IM0761-226		I76/SH52 Interchange	04/02/20	5,450.00	1.00	2.10	1.29
	WEIGHTED AVERAGE FOR THE SECOND QUARTER			5,450.00	1.00	2.10	1.29
	WEIGHTED AVERAGE FOR THE YEAR			5,450.00	1.00	2.10	1.29
=====	202-00070	Rem Barricade		Each	=====		
CC0852-106		US-85 LOUVIERS TO MP 191.75	04/23/20	2.00	900.00	691.95	605.00
FBR0852-108		US-85 BETWEEN LOUVIERS AND MP					
	WEIGHTED AVERAGE FOR THE SECOND QUARTER			2.00	900.00	691.95	605.00
	WEIGHTED AVERAGE FOR THE YEAR			2.00	900.00	691.95	605.00
=====	202-00090	Rem Delineator		Each	=====		
NHPP0343-041		I-76 & US 34 FT. MORGAN AREA	01/09/20	100.00	6.00	5.23	5.50
BR0343-040		US 34 REPUBLICAN RIVER BRIDGE	01/16/20	21.00	10.00	27.62	8.60
FBR0343-043		US 34 D-28-P STRUCTURE REPLAC					
STR131A-038		SH 131 MP 51.95-55.73, ROUTT	01/16/20	100.00	15.00	5.25	5.00
NH 0503-093		US50 WEST OF TEXAS CREEK MP 2	01/23/20	300.00	10.00	3.58	3.15
STA0703-443		I-70 EJMT TUNNELS PAVING	02/06/20	5.00	5.00	15.78	13.25
STA059A-036		SH 59 SEIBERT TO COPE	02/06/20	176.00	10.00	5.50	5.00
STR116A-001		SH 116 A Surface Treatment Pr	02/13/20	650.00	7.00	8.89	9.90
FSA2873-194		US 287 Longmont Intersection	02/13/20	6.00	10.00	29.50	22.00
STA069A-033		SH69 MP 58.7 TO 71.58	02/13/20	396.00	8.00	4.59	6.00
STR0101-027		SH 10 Overlay La Junta West	02/27/20	450.00	7.00	6.22	5.00
NH0242-085		US 24 M.P. 291.38 to M.P. 296	02/27/20	272.00	9.50	5.36	5.70
NHPP0171-105		SH 17 MP 84.5 to US 285 & SH	03/05/20	861.00	4.00	6.79	6.06
NHPP145A-080		SH 145 Keystone-Placerville R	03/05/20	565.00	10.00	8.00	8.00
STR2871-038		US 287 Passing Lanes Springfi	03/05/20	44.00	10.00	8.43	10.00
BR025A-046		K-18-U ON I-25 AT MP112 BRIDG	03/05/20	9.00	8.77	35.88	17.19
NHPP0091-044		SH 9 FRISCO MAIN ST TO IRON S	03/05/20	150.00	10.00	8.10	12.00

COLORADO DEPARTMENT OF TRANSPORTATION
ITEM UNIT COSTS BY PROJECTS -- 2020 COST DATA

10:58 Friday, October 2, 2020 10

PROJECT NUMBER	ITEM NUMBER/ PROJECT LOCATION	ITEM DESCRIPTION/ PROJECT LOCATION	DATE LET	UNIT/ QUANTITY	ENGR. EST.	AVERAGE BID	AWARDED BID
===== 202-00090		Rem Delineator		Each			
NH050A-034		US50A PUEBLO WEST PURCELL INT	03/26/20	200.00	7.00	6.05	2.25
SHE 0703-461		I-70 and Kipling North Phase	03/26/20	15.00	28.00	34.00	35.00
		WEIGHTED AVERAGE FOR THE FIRST QUARTER		4,320.00	7.76	7.20	6.71
NHPP1602-169		US 160 WC TUNNEL EAST RESURFA	04/02/20	586.00	7.50	4.88	7.58
STR092A-030		SH92 MP 31.748-48.5, DELTA AND	04/02/20	550.00	7.00	7.45	9.00
STA340A-021		SH340 MP 6-6.76 MESA COUNTY	04/02/20	17.00	10.00	5.25	5.00
SFTY2254-091		225 Ramp Improvements	04/09/20	26.00	10.00	31.50	31.00
CC0852-106		US-85 LOUVIERS TO MP 191.75	04/23/20	160.00	25.00	7.12	4.40
FBR0852-108		US-85 BETWEEN LOUVIERS AND MP					
FSA1602-159		US 160 AND SH 17 INTERSECTION	04/30/20	20.00	20.00	23.33	27.00
C0853-112		US85 & WCR98 INTERSECTION IMP	05/07/20	24.00	20.00	34.19	30.00
NHPPR100-303		LONG MAST ARM SIGNALS PROJECT	05/07/20	18.00	15.00	67.00	60.00
NHPP0253-276		I-25 EXPRESS LANES SEGMENT 5	05/15/20	90.00	16.00	16.21	16.21
SHE016A-043		SH 21 & 16 SIGNALS PROJECT	06/18/20	12.00	10.00	29.02	22.58
		WEIGHTED AVERAGE FOR THE SECOND QUARTER		1,503.00	10.24	9.07	10.02
		WEIGHTED AVERAGE FOR THE YEAR		5,823.00	8.40	7.73	7.56
===== 202-00155		Rem Wall		Lin Foot			
FSA0341-097		US 34 & MACGREGOR INTERSECTIO	01/09/20	25.00	200.00	16.00	16.00
BR0343-040		US 34 REPUBLICAN RIVER BRIDGE	01/16/20	56.00	60.00	97.54	100.00
FBR0343-043		US 34 D-28-P STRUCTURE REPLAC					
PWQM240-172		El Paso County, north Colorad	01/23/20	81.00	50.00	110.50	190.00
NHPP0091-044		SH 9 FRISCO MAIN ST TO IRON S	03/05/20	20.00	100.00	69.58	140.00
SHE 0703-461		I-70 and Kipling North Phase	03/26/20	157.00	200.00	100.20	104.00
		WEIGHTED AVERAGE FOR THE FIRST QUARTER		339.00	135.13	97.89	119.52
		WEIGHTED AVERAGE FOR THE YEAR		339.00	135.13	97.89	119.52
===== 202-00160		Rem Wall		Sq Foot			
C0402-094		US 40 GRAND COUNTY SIGNAL REP	02/27/20	66.00	60.00	71.50	25.00
		WEIGHTED AVERAGE FOR THE FIRST QUARTER		66.00	60.00	71.50	25.00
		WEIGHTED AVERAGE FOR THE YEAR		66.00	60.00	71.50	25.00

PROJECT NUMBER	ITEM NUMBER/ PROJECT LOCATION	ITEM DESCRIPTION/ PROJECT LOCATION	DATE LET	UNIT/ QUANTITY	ENGR. EST.	AVERAGE BID	AWARDED BID
=====	202-00170	Grinding And Texturing Conc Pvmt		Sq Yard	=====		
NHPP0343-041		I-76 & US 34 FT. MORGAN AREA	01/09/20	85.00	42.00	167.33	258.00
NHPP 0852-116		US85:HAMPDEN TO FLORIDA-RESUR	02/06/20	72,316.00	9.00	5.50	5.00
		WEIGHTED AVERAGE FOR THE FIRST QUARTER		72,401.00	9.04	5.78	5.30
		WEIGHTED AVERAGE FOR THE YEAR		72,401.00	9.04	5.78	5.30
=====	202-00190	Rem of Conc Median Cover Matl		Sq Yard	=====		
FSA0341-097		US 34 & MACGREGOR INTERSECTIO	01/09/20	55.00	21.00	22.00	22.00
NHPP0343-041		I-76 & US 34 FT. MORGAN AREA	01/09/20	44.50	24.00	41.23	47.00
NH0242-085		US 24 M.P. 291.38 to M.P. 296	02/27/20	88.00	30.00	25.12	34.20
NH050A-034		US50A PUEBLO WEST PURCELL INT	03/26/20	1,519.00	20.00	9.75	14.00
HPP 0501-067		US 50 AND SH 92 DELTA INTERSE	03/26/20	723.00	14.00	19.23	14.90
		WEIGHTED AVERAGE FOR THE FIRST QUARTER		2,429.50	18.67	11.36	15.79
IM0761-226		I76/SH52 Interchange	04/02/20	327.00	20.00	9.79	2.01
CC0852-106		US-85 LOUVIERS TO MP 191.75	04/23/20	34.00	22.00	348.18	40.00
FBR0852-108		US-85 BETWEEN LOUVIERS AND MP					
C1211-090		SH-121 & 29th Ave / SH-121 &	04/23/20	50.00	22.00	31.53	40.00
C1601-082		Hawkins Signal and Curb Ramps	04/30/20	46.00	25.00	78.00	108.00
NHPPR100-303		LONG MAST ARM SIGNALS PROJECT	05/07/20	12.00	40.00	66.33	45.00
		WEIGHTED AVERAGE FOR THE SECOND QUARTER		469.00	21.36	46.79	20.31
		WEIGHTED AVERAGE FOR THE YEAR		2,898.50	19.11	17.40	16.52
=====	202-00195	Rem of Median Cover		Sq Yard	=====		
NHPP0253-265		I-25 AT ERIE PARKWAY ON AND O	01/09/20	48.00	60.00	67.33	55.00
NHPP0091-044		SH 9 FRISCO MAIN ST TO IRON S	03/05/20	1,540.00	10.00	9.48	15.10
SHE 0703-461		I-70 and Kipling North Phase	03/26/20	65.00	25.00	34.00	56.00
		WEIGHTED AVERAGE FOR THE FIRST QUARTER		1,653.00	12.04	12.69	17.87
FSA1602-159		US 160 AND SH 17 INTERSECTION	04/30/20	83.00	25.00	45.00	16.00

PROJECT NUMBER	ITEM NUMBER/ PROJECT LOCATION	ITEM DESCRIPTION/ PROJECT LOCATION	DATE LET	UNIT/ QUANTITY	ENGR. EST.	AVERAGE BID	AWARDED BID
=====	202-00195	Rem of Median Cover		Sq Yard	=====	=====	=====
FSAR400-356		FY 20 SIGNAL POLE REPLACEMENT	06/11/20	24.00	60.00	67.17	58.00
SHE016A-043		SH 21 & 16 SIGNALS PROJECT	06/18/20	108.00	50.00	35.76	20.79
		WEIGHTED AVERAGE FOR THE SECOND QUARTER		215.00	41.47	41.06	23.09
		WEIGHTED AVERAGE FOR THE YEAR		1,868.00	15.43	16.79	18.47
=====	202-00200	Rem Sidewalk		Sq Yard	=====	=====	=====
FSA0341-097		US 34 & MACGREGOR INTERSECTIO	01/09/20	161.00	26.00	22.00	22.00
NHPP0343-041		I-76 & US 34 FT. MORGAN AREA	01/09/20	758.50	23.00	27.40	28.00
BR0343-040		US 34 REPUBLICAN RIVER BRIDGE	01/16/20	520.00	23.00	18.57	20.00
FBR0343-043		US 34 D-28-P STRUCTURE REPLAC					
NHPP 0852-116		US85:HAMPDEN TO FLORIDA-RESUR	02/06/20	21.40	60.00	80.00	30.00
ITS0761-231		ITS FIBER AND CAMERAS ON I-76	02/06/20	2.00	100.00	227.00	75.00
NHPP4701-134		C-470 NOISE WALL WEST OF LUCE	02/06/20	31.00	30.00	44.60	101.00
FSA2873-194		US 287 Longmont Intersection	02/13/20	42.00	30.00	41.99	24.00
C0402-094		US 40 GRAND COUNTY SIGNAL REP	02/27/20	202.00	25.00	39.00	47.00
STRR300-249		Grand and Jackson Counties AD	03/05/20	1,228.00	40.00	53.00	39.00
CC080-037		VARIOUS ADA RAMPS ALONG NORTH	03/05/20	443.00	40.00	41.17	23.00
NHPP0091-044		SH 9 FRISCO MAIN ST TO IRON S	03/05/20	490.00	40.00	10.00	10.50
NH050A-034		US50A PUEBLO WEST PURCELL INT	03/26/20	301.00	32.00	12.94	22.00
HPP 0501-067		US 50 AND SH 92 DELTA INTERSE	03/26/20	457.00	19.00	23.10	15.20
SHE 0703-461		I-70 and Kipling North Phase	03/26/20	222.00	35.00	26.60	17.00
		WEIGHTED AVERAGE FOR THE FIRST QUARTER		4,878.90	31.74	29.67	26.68
IM0761-226		I76/SH52 Interchange	04/02/20	278.00	40.00	12.74	5.50
C1211-090		SH-121 & 29th Ave / SH-121 &	04/23/20	110.00	18.00	32.20	43.00
C1601-082		Hawkins Signal and Curb Ramps	04/30/20	663.00	35.00	61.00	55.00
NHPPR100-303		LONG MAST ARM SIGNALS PROJECT	05/07/20	124.00	35.00	45.33	41.00
ITS SW02-304		ITS FIBER TO STATE BUILDINGS	05/14/20	10.00	100.00	138.25	183.00
NHPP0402-098		US 40 CHIP SEAL MP 126 TO MP	05/14/20	25.00	22.00	45.27	100.00
ITS SW02-303		R1: US 285, SH 83 R2: SH 83,	05/28/20	2.00	25.00	576.70	250.00
FSAR400-356		FY 20 SIGNAL POLE REPLACEMENT	06/11/20	77.00	50.00	49.00	47.00
SHE016A-043		SH 21 & 16 SIGNALS PROJECT	06/18/20	13.00	50.00	41.35	20.77
		WEIGHTED AVERAGE FOR THE SECOND QUARTER		1,302.00	35.90	40.00	43.42
		WEIGHTED AVERAGE FOR THE YEAR		6,180.90	32.61	31.96	30.21
=====	202-00201	Rem Curb		Lin Foot	=====	=====	=====
FSA0341-097		US 34 & MACGREGOR INTERSECTIO	01/09/20	206.00	7.00	7.00	7.00

COLORADO DEPARTMENT OF TRANSPORTATION
ITEM UNIT COSTS BY PROJECTS -- 2020 COST DATA

10:58 Friday, October 2, 2020 13

PROJECT NUMBER	ITEM NUMBER/ PROJECT LOCATION	ITEM DESCRIPTION/ PROJECT LOCATION	DATE LET	UNIT/ QUANTITY	ENGR. EST.	AVERAGE BID	AWARDED BID
===== 202-00201							
		Rem Curb		Lin Foot			
NH0242-085		US 24 M.P. 291.38 to M.P. 296	02/27/20	925.00	8.00	7.26	11.50
SRR300-249		Grand and Jackson Counties AD	03/05/20	106.00	25.00	45.33	15.00
HPP 0501-067		US 50 AND SH 92 DELTA INTERSE	03/26/20	946.00	15.00	6.10	7.35
		WEIGHTED AVERAGE FOR THE FIRST QUARTER		2,183.00	11.76	9.16	9.45
NHPP1602-169		US 160 WC TUNNEL EAST RESURFA	04/02/20	220.00	11.00	8.78	11.00
NHPPR100-303		LONG MAST ARM SIGNALS PROJECT	05/07/20	88.00	10.00	20.00	13.00
		WEIGHTED AVERAGE FOR THE SECOND QUARTER		308.00	10.71	11.99	11.57
		WEIGHTED AVERAGE FOR THE YEAR		2,491.00	11.63	9.59	9.71
===== 202-00202							
		Rem Gutter		Lin Foot			
SRR300-249		Grand and Jackson Counties AD	03/05/20	21.00	20.00	61.00	31.00
NHPP0091-044		SH 9 FRISCO MAIN ST TO IRON S	03/05/20	688.00	10.00	6.52	9.25
HPP 0501-067		US 50 AND SH 92 DELTA INTERSE	03/26/20	54.00	16.00	20.73	5.90
		WEIGHTED AVERAGE FOR THE FIRST QUARTER		763.00	10.70	8.74	9.61
IM0761-226		I76/SH52 Interchange	04/02/20	134.00	15.00	9.61	10.50
C1601-082		Hawkins Signal and Curb Ramps	04/30/20	113.00	30.00	53.00	44.00
		WEIGHTED AVERAGE FOR THE SECOND QUARTER		247.00	21.86	21.13	25.83
		WEIGHTED AVERAGE FOR THE YEAR		1,010.00	13.43	13.24	13.58
===== 202-00203							
		Rem Curb and Gutter		Lin Foot			
NHPP0253-265		I-25 AT ERIE PARKWAY ON AND O	01/09/20	355.00	30.00	19.67	14.00
FSA0341-097		US 34 & MACGREGOR INTERSECTIO	01/09/20	271.00	9.00	9.00	9.00
NHPP0343-041		I-76 & US 34 FT. MORGAN AREA	01/09/20	2,062.00	17.00	11.60	12.00
BR0343-040		US 34 REPUBLICAN RIVER BRIDGE	01/16/20	538.00	15.00	12.22	9.00
FBR0343-043		US 34 D-28-P STRUCTURE REPLAC					
NHPP 0852-116		US85:HAMPDEN TO FLORIDA-RESUR	02/06/20	63.90	20.00	20.00	10.00
FSA2873-194		US 287 Longmont Intersection	02/13/20	141.00	20.00	18.16	10.00
C0402-094		US 40 GRAND COUNTY SIGNAL REP	02/27/20	159.00	20.00	21.00	15.00

PROJECT NUMBER	ITEM NUMBER/ PROJECT LOCATION	ITEM DESCRIPTION/ PROJECT LOCATION	DATE LET	UNIT/ QUANTITY	ENGR. EST.	AVERAGE BID	AWARDED BID
===== 202-00203							
		Rem Curb and Gutter		Lin Foot			
NH0242-085		US 24 M.P. 291.38 to M.P. 296	02/27/20	901.00	11.00	9.89	12.00
STRR300-249		Grand and Jackson Counties AD	03/05/20	2,512.00	20.00	23.67	15.00
CC080-037		VARIOUS ADA RAMPS ALONG NORTH	03/05/20	843.00	35.00	20.77	15.00
NHPP0091-044		SH 9 FRISCO MAIN ST TO IRON S	03/05/20	6,287.00	10.00	5.35	7.25
NH050A-034		US50A PUEBLO WEST PURCELL INT	03/26/20	3,930.00	9.00	5.88	6.00
HPP 0501-067		US 50 AND SH 92 DELTA INTERSE	03/26/20	3,126.00	8.00	5.65	6.50
SHE 0703-461		I-70 and Kipling North Phase	03/26/20	743.00	17.00	16.50	10.50
WEIGHTED AVERAGE FOR THE FIRST QUARTER				21,931.90	13.18	9.50	9.11
IM0761-226		I76/SH52 Interchange	04/02/20	2,737.00	10.00	4.53	1.70
CC0852-106		US-85 LOUVIERS TO MP 191.75	04/23/20	145.00	15.00	11.70	14.00
FBR0852-108		US-85 BETWEEN LOUVIERS AND MP					
C1211-090		SH-121 & 29th Ave / SH-121 &	04/23/20	651.00	10.00	12.37	15.00
C1601-082		Hawkins Signal and Curb Ramps	04/30/20	828.00	15.00	50.33	44.00
FSA1602-159		US 160 AND SH 17 INTERSECTION	04/30/20	163.00	20.00	23.00	7.00
NHPPR100-303		LONG MAST ARM SIGNALS PROJECT	05/07/20	200.00	14.00	21.83	15.50
NHPP0402-098		US 40 CHIP SEAL MP 126 TO MP	05/14/20	100.00	15.00	49.17	30.00
NHPP0253-276		I-25 EXPRESS LANES SEGMENT 5	05/15/20	569.00	5.00	7.52	7.52
FSAR400-356		FY 20 SIGNAL POLE REPLACEMENT	06/11/20	35.00	40.00	31.33	21.00
SHE016A-043		SH 21 & 16 SIGNALS PROJECT	06/18/20	272.00	15.00	14.71	11.55
WEIGHTED AVERAGE FOR THE SECOND QUARTER				5,700.00	11.29	11.22	11.98
WEIGHTED AVERAGE FOR THE YEAR				27,631.90	12.79	9.93	9.70
===== 202-00205							
		Rem Wheel Stop		Each			
FSA1602-159		US 160 AND SH 17 INTERSECTION	04/30/20	1.00	150.00	760.00	92.00
WEIGHTED AVERAGE FOR THE SECOND QUARTER				1.00	150.00	760.00	92.00
WEIGHTED AVERAGE FOR THE YEAR				1.00	150.00	760.00	92.00
===== 202-00206							
		Rem Conc Curb Ramp		Sq Yard			
NHPP0253-265		I-25 AT ERIE PARKWAY ON AND O	01/09/20	216.00	50.00	58.67	33.00
FSA0341-097		US 34 & MACGREGOR INTERSECTIO	01/09/20	94.00	45.00	32.00	32.00
NHPP0343-041		I-76 & US 34 FT. MORGAN AREA	01/09/20	814.00	41.00	35.00	29.00
BR0343-040		US 34 REPUBLICAN RIVER BRIDGE	01/16/20	91.00	45.00	34.32	25.00
FBR0343-043		US 34 D-28-P STRUCTURE REPLAC					

PROJECT NUMBER	ITEM NUMBER/ PROJECT LOCATION	ITEM DESCRIPTION/ PROJECT LOCATION	DATE LET	UNIT/ QUANTITY	ENGR. EST.	AVERAGE BID	AWARDED BID
=====	202-00206	Rem Conc Curb Ramp		Sq Yard	=====	=====	=====
NHPP 0852-116		US85:HAMPDEN TO FLORIDA-RESUR	02/06/20	78.00	40.00	28.00	16.00
FSA2873-194		US 287 Longmont Intersection	02/13/20	28.00	40.00	57.48	28.00
NH0242-085		US 24 M.P. 291.38 to M.P. 296	02/27/20	50.00	48.00	29.83	34.95
NHPP0091-044		SH 9 FRISCO MAIN ST TO IRON S	03/05/20	76.00	40.00	35.17	58.50
SHE 0703-461		I-70 and Kipling North Phase	03/26/20	85.00	40.00	34.00	26.00
		WEIGHTED AVERAGE FOR THE FIRST QUARTER		1,532.00	42.81	38.34	30.32
IM0761-226		I76/SH52 Interchange	04/02/20	43.00	50.00	27.57	15.99
C1211-090		SH-121 & 29th Ave / SH-121 &	04/23/20	102.00	24.00	35.20	40.00
C1601-082		Hawkins Signal and Curb Ramps	04/30/20	440.00	50.00	56.67	42.00
NHPPR100-303		LONG MAST ARM SIGNALS PROJECT	05/07/20	83.00	40.00	42.00	41.00
FSAR400-356		FY 20 SIGNAL POLE REPLACEMENT	06/11/20	51.00	50.00	49.50	44.00
SHE016A-043		SH 21 & 16 SIGNALS PROJECT	06/18/20	111.00	35.00	41.96	20.79
		WEIGHTED AVERAGE FOR THE SECOND QUARTER		830.00	43.80	46.88	37.59
		WEIGHTED AVERAGE FOR THE YEAR		2,362.00	43.15	41.52	32.88
=====	202-00207	Rem of Brick Pavers		Sq Yard	=====	=====	=====
STRR300-249		Grand and Jackson Counties AD	03/05/20	659.00	35.00	14.67	17.00
NHPP0091-044		SH 9 FRISCO MAIN ST TO IRON S	03/05/20	47.00	50.00	53.67	28.00
		WEIGHTED AVERAGE FOR THE FIRST QUARTER		706.00	36.00	17.26	17.73
SHE016A-043		SH 21 & 16 SIGNALS PROJECT	06/18/20	3.00	50.00	91.40	29.00
		WEIGHTED AVERAGE FOR THE SECOND QUARTER		3.00	50.00	91.40	29.00
		WEIGHTED AVERAGE FOR THE YEAR		709.00	36.06	17.78	17.78
=====	202-00210	Rem Conc Pavement		Sq Yard	=====	=====	=====
FSA0253-262		I-25 SB BOTTLENECK I-76 TO I-	01/09/20	100.00	40.00	99.33	85.00
NHPP0343-041		I-76 & US 34 FT. MORGAN AREA	01/09/20	599.00	17.50	30.17	32.00
BR0343-040		US 34 REPUBLICAN RIVER BRIDGE	01/16/20	59.00	40.00	93.93	55.00
FBR0343-043		US 34 D-28-P STRUCTURE REPLAC					

COLORADO DEPARTMENT OF TRANSPORTATION
ITEM UNIT COSTS BY PROJECTS -- 2020 COST DATA

10:58 Friday, October 2, 2020 16

PROJECT NUMBER	ITEM NUMBER/ PROJECT LOCATION	ITEM DESCRIPTION/ PROJECT LOCATION	DATE LET	UNIT/ QUANTITY	ENGR. EST.	AVERAGE BID	AWARDED BID
===== 202-00210							
		Rem Conc Pavement		Sq Yard			
NHPP 0852-116		US85:HAMPDEN TO FLORIDA-RESUR	02/06/20	6,227.00	40.00	55.00	55.00
NHPP4701-134		C-470 NOISE WALL WEST OF LUCE	02/06/20	737.00	40.00	30.60	30.00
FSA2873-194		US 287 Longmont Intersection	02/13/20	1,285.00	22.00	27.47	22.00
C0402-094		US 40 GRAND COUNTY SIGNAL REP	02/27/20	38.00	60.00	75.00	105.00
STR2871-038		US 287 Passing Lanes Springfi	03/05/20	7,708.00	12.00	9.58	10.31
STRR300-249		Grand and Jackson Counties AD	03/05/20	389.00	40.00	68.33	41.00
CC080-037		VARIOUS ADA RAMP ALONG NORTH	03/05/20	53.00	35.00	38.26	27.00
NH050A-034		US50A PUEBLO WEST PURCELL INT	03/26/20	52.00	30.00	43.46	80.00
HPP 0501-067		US 50 AND SH 92 DELTA INTERSE	03/26/20	2,316.00	20.00	24.25	34.40
SHE 0703-461		I-70 and Kipling North Phase	03/26/20	339.00	40.00	64.00	32.00
	WEIGHTED AVERAGE FOR THE FIRST QUARTER			19,902.00	24.99	32.19	31.12
		I76/SH52 Interchange	04/02/20	12,213.00	18.00	11.26	9.20
IM0761-226		225 Ramp Improvements	04/09/20	1,184.00	35.00	49.00	46.00
SFTY2254-091		US-85 LOUVIERS TO MP 191.75	04/23/20	27,207.00	12.00	6.80	4.61
CC0852-106		US-85 BETWEEN LOUVIERS AND MP					
FBR0852-108		Hawkins Signal and Curb Ramps	04/30/20	417.00	40.00	68.67	45.00
C1601-082		LONG MAST ARM SIGNALS PROJECT	05/07/20	24.00	100.00	69.67	55.00
NHPPR100-303							
	WEIGHTED AVERAGE FOR THE SECOND QUARTER			41,045.00	14.78	8.64	7.61
	WEIGHTED AVERAGE FOR THE YEAR			60,947.00	18.12	11.93	15.29
===== 202-00212							
		Rem Conc Pavement (Spec)		Sq Yard			
STR2871-038		US 287 Passing Lanes Springfi	03/05/20	7,389.00	15.00	16.39	17.29
	WEIGHTED AVERAGE FOR THE FIRST QUARTER			7,389.00	15.00	16.39	17.29
	WEIGHTED AVERAGE FOR THE YEAR			7,389.00	15.00	16.39	17.29
===== 202-00215							
		Rem Conc Pvmt (Planing)		Sq Yard			
NHPP1602-169		US 160 WC TUNNEL EAST RESURFA	04/02/20	450.00	28.00	19.43	21.38
	WEIGHTED AVERAGE FOR THE SECOND QUARTER			450.00	28.00	19.43	21.38
	WEIGHTED AVERAGE FOR THE YEAR			450.00	28.00	19.43	21.38
===== 202-00220							
		Rem Asphalt Mat		Sq Yard			
FSA0253-262		I-25 SB BOTTLENECK I-76 TO I-	01/09/20	950.00	12.00	25.44	15.00

PROJECT NUMBER	ITEM NUMBER/ PROJECT LOCATION	ITEM DESCRIPTION/ PROJECT LOCATION	DATE LET	UNIT/ QUANTITY	ENGR. EST.	AVERAGE BID	AWARDED BID
=====	202-00220	Rem Asphalt Mat		Sq Yard	=====	=====	=====
FSA0341-097		US 34 & MACGREGOR INTERSECTIO	01/09/20	3,027.00	10.00	8.00	8.00
NHPP0343-041		I-76 & US 34 FT. MORGAN AREA	01/09/20	10,697.00	5.00	16.83	5.50
BR0343-040		US 34 REPUBLICAN RIVER BRIDGE	01/16/20	5,774.00	7.00	6.30	4.75
FBR0343-043		US 34 D-28-P STRUCTURE REPLAC					
STA006A-067		SH 6 Merino to Atwood	01/16/20	1,000.00	8.00	4.30	3.00
NHPP4701-134		C-470 NOISE WALL WEST OF LUCE	02/06/20	3,474.00	10.00	9.00	10.00
STA059A-036		SH 59 SEIBERT TO COPE	02/06/20	2,219.00	6.00	36.00	35.00
FSA2873-194		US 287 Longmont Intersection	02/13/20	1,043.00	8.00	22.86	11.00
STA069A-033		SH69 MP 58.7 TO 71.58	02/13/20	2,427.00	8.00	9.06	9.00
C0402-094		US 40 GRAND COUNTY SIGNAL REP	02/27/20	213.00	25.00	34.00	37.00
NHPP145A-080		SH 145 Keystone-Placerville R	03/05/20	244.00	25.00	59.00	59.00
STRR300-249		Grand and Jackson Counties AD	03/05/20	757.00	50.00	46.00	20.00
CC080-037		VARIOUS ADA RAMPS ALONG NORTH	03/05/20	28.00	50.00	27.03	8.00
NHPP0091-044		SH 9 FRISCO MAIN ST TO IRON S	03/05/20	3,226.00	4.00	11.75	17.00
NH050A-034		US50A PUEBLO WEST PURCELL INT	03/26/20	1,482.00	7.00	27.03	26.00
HPP 0501-067		US 50 AND SH 92 DELTA INTERSE	03/26/20	3,568.00	7.00	14.30	14.90
SHE 0703-461		I-70 and Kipling North Phase	03/26/20	741.00	12.00	40.50	21.50
		WEIGHTED AVERAGE FOR THE FIRST QUARTER		40,870.00	8.01	15.32	11.59
STR092A-030		SH92 MP 31.748-48.5, DELTA AND	04/02/20	3,733.00	8.00	6.43	3.25
IM0761-226		I76/SH52 Interchange	04/02/20	22,279.00	7.00	5.33	3.70
STA340A-021		SH340 MP 6-6.76 MESA COUNTY	04/02/20	210.00	10.00	21.62	21.00
SFTY2254-091		225 Ramp Improvements	04/09/20	669.00	25.00	25.50	19.00
CC0852-106		US-85 LOUVIERS TO MP 191.75	04/23/20	51,570.00	8.00	4.73	7.19
FBR0852-108		US-85 BETWEEN LOUVIERS AND MP					
C1601-082		Hawkins Signal and Curb Ramps	04/30/20	48.00	30.00	128.67	310.00
FSA1602-159		US 160 AND SH 17 INTERSECTION	04/30/20	10,648.00	6.00	18.17	14.00
C0853-112		US85 & WCR98 INTERSECTION IMP	05/07/20	9,048.00	7.00	5.40	5.00
NHPPR100-303		LONG MAST ARM SIGNALS PROJECT	05/07/20	125.00	50.00	48.00	55.00
FBR0343-042		US 34 D-27-G STRUCTURE REPLAC	05/07/20	2,267.00	6.50	7.02	8.00
NHPP0402-098		US 40 CHIP SEAL MP 126 TO MP	05/14/20	170.00	9.00	20.27	25.00
NHPP0253-276		I-25 EXPRESS LANES SEGMENT 5	05/15/20	15,851.00	3.70	3.23	3.23
FSAR400-356		FY 20 SIGNAL POLE REPLACEMENT	06/11/20	27.00	65.00	51.50	60.00
SHE016A-043		SH 21 & 16 SIGNALS PROJECT	06/18/20	233.00	25.00	42.64	31.19
		WEIGHTED AVERAGE FOR THE SECOND QUARTER		116,878.00	7.14	5.75	6.68
		WEIGHTED AVERAGE FOR THE YEAR		157,748.00	7.37	7.33	7.95
=====	202-00240	Rem Asphalt Mat (Planing)		Sq Yard	=====	=====	=====
STA0142-066		SH 14 New Raymer West	01/09/20	177,200.00	1.60	1.26	0.75

COLORADO DEPARTMENT OF TRANSPORTATION
 ITEM UNIT COSTS BY PROJECTS -- 2020 COST DATA

10:58 Friday, October 2, 2020 18

PROJECT NUMBER	ITEM NUMBER/ PROJECT LOCATION	ITEM DESCRIPTION/ PROJECT LOCATION	DATE LET	UNIT/ QUANTITY	ENGR. EST.	AVERAGE BID	AWARDED BID
===== 202-00240							
		Rem Asphalt Mat (Planing)		Sq Yard	=====		
FSA0341-097		US 34 & MACGREGOR INTERSECTIO	01/09/20	1,650.00	7.00	4.50	4.50
NHPP0343-041		I-76 & US 34 FT. MORGAN AREA	01/09/20	480,255.00	1.75	2.72	2.00
STA006A-067		SH 6 Merino to Atwood	01/16/20	136,413.00	2.25	1.25	0.60
STR131A-038		SH 131 MP 51.95-55.73, ROUTT	01/16/20	847.00	15.00	14.25	18.00
NH 0503-093		US50 WEST OF TEXAS CREEK MP 2	01/23/20	246,781.00	2.00	2.02	1.54
STR141A-044		SH 141 AND SH 145, FROM SLICK	01/30/20	108,716.00	2.50	2.21	1.40
STA0703-443		I-70 EJMT TUNNELS PAVING	02/06/20	91,710.00	3.75	7.93	6.91
NHPP4701-134		C-470 NOISE WALL WEST OF LUCE	02/06/20	2,609.00	5.00	6.82	6.00
STA059A-036		SH 59 SEIBERT TO COPE	02/06/20	5,437.00	3.00	6.13	5.25
STR116A-001		SH 116 A Surface Treatment Pr	02/13/20	15,500.00	10.00	3.53	5.00
STA069A-033		SH69 MP 58.7 TO 71.58	02/13/20	13,561.00	2.50	3.89	4.00
STR0101-027		SH 10 Overlay La Junta West	02/27/20	14,831.00	10.00	3.42	4.00
NH0242-085		US 24 M.P. 291.38 to M.P. 296	02/27/20	235,201.00	1.85	2.95	1.85
NHPP0171-105		SH 17 MP 84.5 to US 285 & SH	03/05/20	2,051.00	5.00	6.75	7.80
C0641-106		SH 64 Meeker West Rural Resur	03/05/20	6,694.00	15.00	6.40	4.65
NHPP145A-080		SH 145 Keystone-Placerville R	03/05/20	951.00	31165.00	6.50	6.50
BR025A-046		K-18-U ON I-25 AT MP112 BRIDG	03/05/20	929.00	5.00	6.98	5.93
NHPP0091-044		SH 9 FRISCO MAIN ST TO IRON S	03/05/20	11,974.00	2.00	3.55	3.00
NH050A-034		US50A PUEBLO WEST PURCELL INT	03/26/20	110,832.00	2.25	5.11	4.20
WEIGHTED AVERAGE FOR THE FIRST QUARTER				1,664,142.00	20.07	3.00	2.16
NHPP1602-169		US 160 WC TUNNEL EAST RESURFA	04/02/20	3,001.00	10.00	8.81	9.11
STR092A-030		SH92 MP 31.748-48.5, DELTA AND	04/02/20	6,717.00	5.00	4.95	4.00
IM0761-226		I76/SH52 Interchange	04/02/20	1,181.00	7.00	8.83	7.71
STA340A-021		SH340 MP 6-6.76 MESA COUNTY	04/02/20	537.00	8.00	12.37	9.00
STR0341-101		SH 34 North of Grandby Resurf	04/02/20	2,377.00	2.50	19.93	23.80
C1211-090		SH-121 & 29th Ave / SH-121 &	04/23/20	1,551.00	3.00	7.34	5.00
FSA1602-159		US 160 AND SH 17 INTERSECTION	04/30/20	255.00	7.00	24.33	6.00
C0853-112		US85 & WCR98 INTERSECTION IMP	05/07/20	7,543.00	3.00	3.42	3.10
FBR0343-042		US 34 D-27-G STRUCTURE REPLAC	05/07/20	5,687.00	4.50	4.33	3.75
WEIGHTED AVERAGE FOR THE SECOND QUARTER				28,849.00	4.74	5.73	6.19
=====							
WEIGHTED AVERAGE FOR THE YEAR				1,692,991.00	19.80	3.08	2.23
===== 202-00246							
		Rem Asphalt Mat (Planing) (Special)		Sq Yard	=====		
NHPP0343-041		I-76 & US 34 FT. MORGAN AREA	01/09/20	13,504.00	6.00	11.12	8.50
NH 0503-093		US50 WEST OF TEXAS CREEK MP 2	01/23/20	1,898.00	2.25	16.93	11.86
NHPP 0852-116		US85:HAMPDEN TO FLORIDA-RESUR	02/06/20	7,815.00	10.00	12.00	15.00
STA059A-036		SH 59 SEIBERT TO COPE	02/06/20	2,318.00	6.00	20.25	16.50
STA069A-033		SH69 MP 58.7 TO 71.58	02/13/20	282.00	20.00	28.08	24.00

COLORADO DEPARTMENT OF TRANSPORTATION
ITEM UNIT COSTS BY PROJECTS -- 2020 COST DATA

10:58 Friday, October 2, 2020 19

PROJECT NUMBER	ITEM NUMBER/ PROJECT LOCATION	ITEM DESCRIPTION/ PROJECT LOCATION	DATE LET	UNIT/ QUANTITY	ENGR. EST.	AVERAGE BID	AWARDED BID
=====	202-00246	Rem Asphalt Mat (Planing) (Special)		Sq Yard	=====	=====	=====
STR0101-027		SH 10 Overlay La Junta West	02/27/20	136.00	30.00	65.21	60.00
		WEIGHTED AVERAGE FOR THE FIRST QUARTER		25,953.00	7.21	12.80	11.86
IM0761-226		I76/SH52 Interchange	04/02/20	1,287.00	10.00	16.39	9.01
		WEIGHTED AVERAGE FOR THE SECOND QUARTER		1,287.00	10.00	16.39	9.01
		WEIGHTED AVERAGE FOR THE YEAR		27,240.00	7.34	13.23	11.72
=====	202-00248	Rem Rumble Strips		Lin Foot	=====	=====	=====
C0853-112		US85 & WCR98 INTERSECTION IMP	05/07/20	7,150.00	4.00	2.94	3.00
		WEIGHTED AVERAGE FOR THE SECOND QUARTER		7,150.00	4.00	2.94	3.00
		WEIGHTED AVERAGE FOR THE YEAR		7,150.00	4.00	2.94	3.00
=====	202-00250	Rem Pavement Marking		Sq Foot	=====	=====	=====
FSA0253-262		I-25 SB BOTTLENECK I-76 TO I-	01/09/20	8,837.00	1.00	1.81	1.60
NHPP0253-265		I-25 AT ERIE PARKWAY ON AND O	01/09/20	716.00	5.00	5.58	6.25
FSA0341-097		US 34 & MACGREGOR INTERSECTIO	01/09/20	455.00	3.00	4.00	4.00
NHPP0343-041		I-76 & US 34 FT. MORGAN AREA	01/09/20	72,250.00	0.90	0.82	0.90
BR0343-040		US 34 REPUBLICAN RIVER BRIDGE	01/16/20	1,400.00	2.00	3.36	3.00
FBR0343-043		US 34 D-28-P STRUCTURE REPLAC					
STR131A-038		SH 131 MP 51.95-55.73, ROUTT	01/16/20	41,460.00	1.00	0.73	0.65
NHPP 0852-116		US85:HAMPDEN TO FLORIDA-RESUR	02/06/20	20,000.00	1.00	1.50	2.00
MTCER300-257		R3 FY 20/21 Region Wide Epoxy	02/06/20	1,438,746.00	0.52	0.53	0.30
FSA2873-194		US 287 Longmont Intersection	02/13/20	1,648.00	2.00	3.51	3.10
C0402-094		US 40 GRAND COUNTY SIGNAL REP	02/27/20	1,700.00	4.00	2.25	2.50
C0641-106		SH 64 Meeker West Rural Resur	03/05/20	92,491.00	0.85	0.65	0.70
NHPP145A-080		SH 145 Keystone-Placerville R	03/05/20	2,750.00	7.00	3.20	3.20
STR2871-038		US 287 Passing Lanes Springfi	03/05/20	23,162.00	2.00	1.32	1.23
NHPP0502-082		US 50 MONTROSE RE CHIP SEAL	03/05/20	269,231.00	0.80	0.65	0.60
BR025A-046		K-18-U ON I-25 AT MP112 BRIDG	03/05/20	350.00	4.50	5.82	5.69
STRR300-249		Grand and Jackson Counties AD	03/05/20	1,116.00	3.50	9.33	3.00
NHPP0091-044		SH 9 FRISCO MAIN ST TO IRON S	03/05/20	27,458.00	2.00	2.42	2.00
NH050A-034		US50A PUEBLO WEST PURCELL INT	03/26/20	57,618.00	0.75	0.88	0.90
HPP 0501-067		US 50 AND SH 92 DELTA INTERSE	03/26/20	14,458.00	0.66	3.23	3.40
SHE 0703-461		I-70 and Kipling North Phase	03/26/20	4,500.00	1.00	3.03	3.10
		WEIGHTED AVERAGE FOR THE FIRST QUARTER		2,080,346.00	0.66	0.70	0.50

PROJECT NUMBER	ITEM NUMBER/ PROJECT LOCATION	ITEM DESCRIPTION/ PROJECT LOCATION	DATE LET	UNIT/ QUANTITY	ENGR. EST.	AVERAGE BID	AWARDED BID
===== 202-00250		Rem Pavement Marking		Sq Foot	=====		
STR092A-030		SH92 MP 31.748-48.5, DELTA AND	04/02/20	124,203.00	0.75	0.73	0.75
IM0761-226		I76/SH52 Interchange	04/02/20	32,300.00	1.00	1.25	1.06
STA340A-021		SH340 MP 6-6.76 MESA COUNTY	04/02/20	17.00	1.00	3.63	4.00
MTCER300-259		MTCE R3 FY20/21 Region Wide S	04/02/20	1,500.00	2.00	2.75	2.75
STR0341-101		SH 34 North of Grandby Resurf	04/02/20	120,754.00	1.00	0.99	0.75
SFTY2254-091		225 Ramp Improvements	04/09/20	5,550.00	3.00	2.50	3.00
CC0852-106		US-85 LOUVIERS TO MP 191.75	04/23/20	20,000.00	0.70	1.35	1.10
FBR0852-108		US-85 BETWEEN LOUVIERS AND MP					
C1211-090		SH-121 & 29th Ave / SH-121 &	04/23/20	3,000.00	1.00	2.53	2.00
C1601-082		Hawkins Signal and Curb Ramps	04/30/20	444.00	5.00	6.25	4.25
FSA1602-159		US 160 AND SH 17 INTERSECTION	04/30/20	3,900.00	2.50	2.53	2.00
C0853-112		US85 & WCR98 INTERSECTION IMP	05/07/20	23,986.00	1.20	1.18	0.80
NHPPR100-303		LONG MAST ARM SIGNALS PROJECT	05/07/20	4,165.00	2.80	2.27	2.00
FBR0343-042		US 34 D-27-G STRUCTURE REPLAC	05/07/20	862.00	3.25	6.89	6.25
NHPP0402-098		US 40 CHIP SEAL MP 126 TO MP	05/14/20	67,537.00	0.70	0.83	0.80
MTCE R100-341		Various Highways in Region 1	05/21/20	4,536,595.00	0.43	0.49	0.33
MTCER200-265		Pueblo	05/28/20	1,489,089.00	0.55	0.45	0.28
SHE016A-043		SH 21 & 16 SIGNALS PROJECT	06/18/20	10,467.00	3.00	2.66	2.20
		WEIGHTED AVERAGE FOR THE SECOND QUARTER		6,444,369.00	0.49	0.54	0.36
		WEIGHTED AVERAGE FOR THE YEAR		8,524,715.00	0.54	0.58	0.39
===== 202-00251		Rem Pvmt Marking (Asph Grooving)		Sq Foot	=====		
NH 0503-093		US50 WEST OF TEXAS CREEK MP 2	01/23/20	121,350.00	0.45	0.69	0.67
NH0242-085		US 24 M.P. 291.38 to M.P. 296	02/27/20	57,463.00	0.75	0.68	0.65
BR025A-046		K-18-U ON I-25 AT MP112 BRIDG	03/05/20	250.00	0.50	6.31	7.77
		WEIGHTED AVERAGE FOR THE FIRST QUARTER		179,063.00	0.55	0.71	0.67
		WEIGHTED AVERAGE FOR THE YEAR		179,063.00	0.55	0.71	0.67
===== 202-00254		Rem of Pvmt Mkg (12 In)		Sq Foot	=====		
NHPP 0852-116		US85:HAMPDEN TO FLORIDA-RESUR	02/06/20	2,000.00	1.25	1.50	2.00
		WEIGHTED AVERAGE FOR THE FIRST QUARTER		2,000.00	1.25	1.50	2.00
CC0852-106		US-85 LOUVIERS TO MP 191.75	04/23/20	5,000.00	1.00	1.35	1.10

COLORADO DEPARTMENT OF TRANSPORTATION
 ITEM UNIT COSTS BY PROJECTS -- 2020 COST DATA

10:58 Friday, October 2, 2020 21

PROJECT NUMBER	ITEM NUMBER/ PROJECT LOCATION	ITEM DESCRIPTION/ PROJECT LOCATION	DATE LET	UNIT/ QUANTITY	ENGR. EST.	AVERAGE BID	AWARDED BID
===== 202-00254 FBR0852-108		Rem of Pvmt Mkg (12 In) US-85 BETWEEN LOUVIERS AND MP		Sq Foot =====			
	WEIGHTED AVERAGE FOR THE SECOND QUARTER			5,000.00	1.00	1.35	1.10
	WEIGHTED AVERAGE FOR THE YEAR			7,000.00	1.07	1.36	1.36
===== 202-00256		Rem of Pvmt Mkg (15 In)		Sq Foot =====			
NHPP 0852-116		US85:HAMPDEN TO FLORIDA-RESUR	02/06/20	1,000.00	1.25	1.50	2.00
	WEIGHTED AVERAGE FOR THE FIRST QUARTER			1,000.00	1.25	1.50	2.00
CC0852-106 FBR0852-108		US-85 LOUVIERS TO MP 191.75 US-85 BETWEEN LOUVIERS AND MP	04/23/20	2,500.00	1.25	1.35	1.10
	WEIGHTED AVERAGE FOR THE SECOND QUARTER			2,500.00	1.25	1.35	1.10
	WEIGHTED AVERAGE FOR THE YEAR			3,500.00	1.25	1.36	1.36
===== 202-00260		Rem of Pvmt Mkg (On-Call)		Sq Foot =====			
MTCER300-257		R3 FY 20/21 Region Wide Epoxy	02/06/20	74,000.00	0.65	0.66	0.42
	WEIGHTED AVERAGE FOR THE FIRST QUARTER			74,000.00	0.65	0.66	0.42
	WEIGHTED AVERAGE FOR THE YEAR			74,000.00	0.65	0.66	0.42
===== 202-00400		Rem Bridge		Each =====			
BR0343-040 FBR0343-043 BR025A-046		US 34 REPUBLICAN RIVER BRIDGE US 34 D-28-P STRUCTURE REPLAC K-18-U ON I-25 AT MP112 BRIDG	01/16/20 03/05/20	2.00 1.00	28000.00 150000.00	58166.67 72894.59	75000.00 36379.49
	WEIGHTED AVERAGE FOR THE FIRST QUARTER			3.00	68666.67	63592.74	62126.50
CC0852-106		US-85 LOUVIERS TO MP 191.75	04/23/20	1.00	175000.00	72605.83	76998.50

COLORADO DEPARTMENT OF TRANSPORTATION
ITEM UNIT COSTS BY PROJECTS -- 2020 COST DATA

10:58 Friday, October 2, 2020 22

PROJECT NUMBER	ITEM NUMBER/ PROJECT LOCATION	ITEM DESCRIPTION/ PROJECT LOCATION	DATE LET	UNIT/ QUANTITY	ENGR. EST.	AVERAGE BID	AWARDED BID
===== 202-00400							
		Rem Bridge		Each			
FBR0852-108		US-85 BETWEEN LOUVIERS AND MP					
FBR0343-042		US 34 D-27-G STRUCTURE REPLAC	05/07/20	1.00	50000.00	71122.78	75000.00
	WEIGHTED AVERAGE FOR THE SECOND QUARTER			2.00	112500.00	71820.68	75999.25
	WEIGHTED AVERAGE FOR THE YEAR			5.00	86200.00	67478.16	67675.60
===== 202-00425							
		Rem Bridge Railing		Lin Foot			
NHPP0343-041		I-76 & US 34 FT. MORGAN AREA	01/09/20	5,109.00	20.00	23.27	22.00
STA059A-036		SH 59 SEIBERT TO COPE	02/06/20	1,215.00	27.00	35.50	31.00
STR0101-027		SH 10 Overlay La Junta West	02/27/20	583.00	25.00	25.46	20.00
NHPP0171-105		SH 17 MP 84.5 to US 285 & SH	03/05/20	136.00	30.00	26.81	37.42
SHE 0703-461		I-70 and Kipling North Phase	03/26/20	157.00	55.00	55.00	41.00
	WEIGHTED AVERAGE FOR THE FIRST QUARTER			7,200.00	22.54	26.16	24.06
	WEIGHTED AVERAGE FOR THE YEAR			7,200.00	22.54	26.16	24.06
===== 202-00450							
		Rem Port Present Str (1)		Sq Yard			
IM0761-226		I76/SH52 Interchange	04/02/20	53.00	215.00	386.71	225.00
	WEIGHTED AVERAGE FOR THE SECOND QUARTER			53.00	215.00	386.71	225.00
	WEIGHTED AVERAGE FOR THE YEAR			53.00	215.00	386.71	225.00
===== 202-00453							
		Rem Port Present Str (2)		Sq Yard			
NHPP0343-041		I-76 & US 34 FT. MORGAN AREA	01/09/20	220.00	291.00	384.76	352.00
NH 0503-093		US50 WEST OF TEXAS CREEK MP 2	01/23/20	33.00	350.00	583.53	567.06
NHPP 0852-116		US85:HAMPDEN TO FLORIDA-RESUR	02/06/20	483.00	350.00	357.50	350.00
STA059A-036		SH 59 SEIBERT TO COPE	02/06/20	188.00	300.00	345.00	340.00
STA069A-033		SH69 MP 58.7 TO 71.58	02/13/20	5.00	300.00	392.22	400.00
	WEIGHTED AVERAGE FOR THE FIRST QUARTER			929.00	325.64	371.24	356.43
IM0761-226		I76/SH52 Interchange	04/02/20	104.00	250.00	680.44	530.00
NHPPRI00-251		SH 2/ Vasquez	06/25/20	35.00	280.00	622.50	985.00
	WEIGHTED AVERAGE FOR THE SECOND QUARTER			139.00	257.55	675.35	644.57
	WEIGHTED AVERAGE FOR THE YEAR			1,068.00	316.78	455.62	393.93

COLORADO DEPARTMENT OF TRANSPORTATION
ITEM UNIT COSTS BY PROJECTS -- 2020 COST DATA

10:58 Friday, October 2, 2020 23

PROJECT NUMBER	ITEM NUMBER/ PROJECT LOCATION	ITEM DESCRIPTION/ PROJECT LOCATION	DATE LET	UNIT/ QUANTITY	ENGR. EST.	AVERAGE BID	AWARDED BID
===== 202-00460		Rem Port Present Str (3)		Sq Yard	=====		
NHPP0343-041		I-76 & US 34 FT. MORGAN AREA	01/09/20	6.00	498.00	1251.82	1111.00
NH 0503-093		US50 WEST OF TEXAS CREEK MP 2	01/23/20	3.00	500.00	1356.32	1312.63
NHPP 0852-116		US85:HAMPDEN TO FLORIDA-RESUR	02/06/20	33.00	550.00	850.00	1000.00
STA059A-036		SH 59 SEIBERT TO COPE	02/06/20	37.00	475.00	890.00	880.00
		WEIGHTED AVERAGE FOR THE FIRST QUARTER		79.00	509.03	930.67	964.10
NHPPR100-251		SH 2/ Vasquez	06/25/20	2.00	480.00	1348.35	2139.70
		WEIGHTED AVERAGE FOR THE SECOND QUARTER		2.00	480.00	1348.35	2139.70
		WEIGHTED AVERAGE FOR THE YEAR		81.00	508.31	940.62	993.13
===== 202-00495		Rem Port Present Str		LUMP SUM	=====		
NHPP0702-359		I-70 No Name Tunnel Lighting	02/27/20	1.00	15000.00	12807.36	5750.00
NH050A-034		US50A PUEBLO WEST PURCELL INT	03/26/20	1.00	10000.00	17412.50	11000.00
		WEIGHTED AVERAGE FOR THE FIRST QUARTER		2.00	12500.00	15877.45	8375.00
IM0761-226		I76/SH52 Interchange	04/02/20	1.00	120000.00	257771.43	130000.00
		WEIGHTED AVERAGE FOR THE SECOND QUARTER		1.00	120000.00	257771.43	130000.00
		WEIGHTED AVERAGE FOR THE YEAR		3.00	48333.33	104996.29	48916.67
===== 202-00500		Rem Port Present Str		Each	=====		
STA059A-036		SH 59 SEIBERT TO COPE	02/06/20	4.00	2300.00	5950.00	5900.00
		WEIGHTED AVERAGE FOR THE FIRST QUARTER		4.00	2300.00	5950.00	5900.00
SFTY2254-091		225 Ramp Improvements	04/09/20	1.00	5000.00	3200.00	4900.00
		WEIGHTED AVERAGE FOR THE SECOND QUARTER		1.00	5000.00	3200.00	4900.00
		WEIGHTED AVERAGE FOR THE YEAR		5.00	2840.00	5400.00	5700.00

COLORADO DEPARTMENT OF TRANSPORTATION
ITEM UNIT COSTS BY PROJECTS -- 2020 COST DATA

10:58 Friday, October 2, 2020 24

PROJECT NUMBER	ITEM NUMBER/ PROJECT LOCATION	ITEM DESCRIPTION/ PROJECT LOCATION	DATE LET	UNIT/ QUANTITY	ENGR. EST.	AVERAGE BID	AWARDED BID
===== 202-00502		Rem Port Present Str		Cubic Yard	=====		
NHPP0343-041		I-76 & US 34 FT. MORGAN AREA	01/09/20	8.00	1350.00	1239.71	1805.00
	WEIGHTED	AVERAGE FOR THE FIRST QUARTER		8.00	1350.00	1239.71	1805.00
		WEIGHTED AVERAGE FOR THE YEAR		8.00	1350.00	1239.71	1805.00
===== 202-00504		Rem Exp Device		Lin Foot	=====		
NHPP0343-041		I-76 & US 34 FT. MORGAN AREA	01/09/20	88.00	170.00	128.21	73.00
NHPP 0852-116		US85:HAMPDEN TO FLORIDA-RESUR	02/06/20	618.00	250.00	327.50	490.00
STA059A-036		SH 59 SEIBERT TO COPE	02/06/20	141.00	175.00	143.50	127.00
	WEIGHTED	AVERAGE FOR THE FIRST QUARTER		847.00	229.20	268.86	386.25
NHPPR100-251		SH 2/ Vasquez	06/25/20	648.00	200.00	149.15	125.30
	WEIGHTED	AVERAGE FOR THE SECOND QUARTER		648.00	200.00	149.15	125.30
		WEIGHTED AVERAGE FOR THE YEAR		1,495.00	216.55	218.45	273.14
===== 202-00505		Rem Port of Present Structure		Sq Foot	=====		
NHPP0343-041		I-76 & US 34 FT. MORGAN AREA	01/09/20	22.00	150.00	282.43	367.00
STA0703-443		I-70 EJMT TUNNELS PAVING	02/06/20	2,869.00	175.00	48.35	50.34
STA059A-036		SH 59 SEIBERT TO COPE	02/06/20	40.00	230.00	284.50	269.00
	WEIGHTED	AVERAGE FOR THE FIRST QUARTER		2,931.00	175.56	54.18	55.70
		WEIGHTED AVERAGE FOR THE YEAR		2,931.00	175.56	54.18	55.70
===== 202-00700		Rem Light Standard		Each	=====		
FSA0341-097		US 34 & MACGREGOR INTERSECTIO	01/09/20	2.00	500.00	750.00	750.00
NHPP0091-044		SH 9 FRISCO MAIN ST TO IRON S	03/05/20	15.00	500.00	510.00	490.00
HPP 0501-067		US 50 AND SH 92 DELTA INTERSE	03/26/20	1.00	580.00	888.00	896.00
	WEIGHTED	AVERAGE FOR THE FIRST QUARTER		18.00	504.44	535.22	541.44

COLORADO DEPARTMENT OF TRANSPORTATION
 ITEM UNIT COSTS BY PROJECTS -- 2020 COST DATA

10:58 Friday, October 2, 2020 25

PROJECT NUMBER	ITEM NUMBER/ PROJECT LOCATION	ITEM DESCRIPTION/ PROJECT LOCATION	DATE LET	UNIT/ QUANTITY	ENGR. EST.	AVERAGE BID	AWARDED BID
===== 202-00700		Rem Light Standard		Each	=====	=====	=====
IM0761-226		I76/SH52 Interchange	04/02/20	14.00	375.00	694.70	699.60
CC0852-106		US-85 LOUVIERS TO MP 191.75	04/23/20	1.00	800.00	287.06	275.00
FBR0852-108		US-85 BETWEEN LOUVIERS AND MP					
NHPP0253-276		I-25 EXPRESS LANES SEGMENT 5	05/15/20	2.00	2000.00	2140.00	2140.00
SHE016A-043		SH 21 & 16 SIGNALS PROJECT	06/18/20	1.00	800.00	1130.40	835.00
	WEIGHTED AVERAGE FOR THE SECOND QUARTER			18.00	602.78	710.70	843.58
	WEIGHTED AVERAGE FOR THE YEAR			36.00	553.61	657.62	692.51
===== 202-00705		Rem Light Standard Foundation		Each	=====	=====	=====
FSA0341-097		US 34 & MACGREGOR INTERSECTIO	01/09/20	2.00	550.00	650.00	650.00
NHPP0091-044		SH 9 FRISCO MAIN ST TO IRON S	03/05/20	15.00	700.00	913.33	880.00
HPP 0501-067		US 50 AND SH 92 DELTA INTERSE	03/26/20	1.00	610.00	1067.00	1100.00
	WEIGHTED AVERAGE FOR THE FIRST QUARTER			18.00	678.33	908.86	866.67
SFTY2254-091		225 Ramp Improvements	04/09/20	3.00	1000.00	710.00	700.00
CC0852-106		US-85 LOUVIERS TO MP 191.75	04/23/20	1.00	900.00	654.29	533.50
FBR0852-108		US-85 BETWEEN LOUVIERS AND MP					
	WEIGHTED AVERAGE FOR THE SECOND QUARTER			4.00	975.00	678.17	658.38
	WEIGHTED AVERAGE FOR THE YEAR			22.00	732.27	857.59	828.80
===== 202-00710		Rem Power Pole		Each	=====	=====	=====
NHPP0343-041		I-76 & US 34 FT. MORGAN AREA	01/09/20	1.00	1500.00	7473.33	3910.00
	WEIGHTED AVERAGE FOR THE FIRST QUARTER			1.00	1500.00	7473.33	3910.00
IM0761-226		I76/SH52 Interchange	04/02/20	2.00	2000.00	564.70	657.20
	WEIGHTED AVERAGE FOR THE SECOND QUARTER			2.00	2000.00	564.70	657.20
	WEIGHTED AVERAGE FOR THE YEAR			3.00	1833.33	1783.87	1741.47

COLORADO DEPARTMENT OF TRANSPORTATION
ITEM UNIT COSTS BY PROJECTS -- 2020 COST DATA

10:58 Friday, October 2, 2020 26

PROJECT NUMBER	ITEM NUMBER/ PROJECT LOCATION	ITEM DESCRIPTION/ PROJECT LOCATION	DATE LET	UNIT/ QUANTITY	ENGR. EST.	AVERAGE BID	AWARDED BID
===== 202-00725		Rem Ex Lighting Sys		LUMP SUM	=====		
NHPP0091-044		SH 9 FRISCO MAIN ST TO IRON S	03/05/20	1.00	15000.00	2875.00	2800.00
	WEIGHTED AVERAGE FOR THE FIRST QUARTER			1.00	15000.00	2875.00	2800.00
	WEIGHTED AVERAGE FOR THE YEAR			1.00	15000.00	2875.00	2800.00
===== 202-00750		Rem Luminaire		Each	=====		
NHPP0253-265		I-25 AT ERIE PARKWAY ON AND O	01/09/20	3.00	100.00	543.33	740.00
NHPP0702-359		I-70 No Name Tunnel Lighting	02/27/20	614.00	130.00	81.87	125.00
	WEIGHTED AVERAGE FOR THE FIRST QUARTER			617.00	129.85	83.55	127.99
	WEIGHTED AVERAGE FOR THE YEAR			617.00	129.85	83.55	127.99
===== 202-00805		Rem Overhead Sign Str		Each	=====		
HPP 0501-067		US 50 AND SH 92 DELTA INTERSE	03/26/20	2.00	5000.00	5937.50	7635.00
	WEIGHTED AVERAGE FOR THE FIRST QUARTER			2.00	5000.00	5937.50	7635.00
SFTY2254-091		225 Ramp Improvements	04/09/20	1.00	10000.00	6825.00	6650.00
	WEIGHTED AVERAGE FOR THE SECOND QUARTER			1.00	10000.00	6825.00	6650.00
	WEIGHTED AVERAGE FOR THE YEAR			3.00	6666.67	6233.33	7306.67
===== 202-00810		Rem Ground Sign		Each	=====		
FSA0253-262		I-25 SB BOTTLENECK I-76 TO I-	01/09/20	2.00	200.00	161.79	155.00
FSA0341-097		US 34 & MACGREGOR INTERSECTIO	01/09/20	7.00	80.00	200.00	200.00
NHPP0343-041		I-76 & US 34 FT. MORGAN AREA	01/09/20	73.00	60.00	79.51	85.00
BR0343-040		US 34 REPUBLICAN RIVER BRIDGE	01/16/20	6.00	68.00	121.34	125.00
FBR0343-043		US 34 D-28-P STRUCTURE REPLAC					
NH 0503-093		US50 WEST OF TEXAS CREEK MP 2	01/23/20	22.00	100.00	102.51	105.01
NHPP 0852-116		US85:HAMPDEN TO FLORIDA-RESUR	02/06/20	4.00	200.00	200.00	200.00
STA0703-443		I-70 EJMT TUNNELS PAVING	02/06/20	15.00	60.00	143.74	132.48

PROJECT NUMBER	ITEM NUMBER/ PROJECT LOCATION	ITEM DESCRIPTION/ PROJECT LOCATION	DATE LET	UNIT/ QUANTITY	ENGR. EST.	AVERAGE BID	AWARDED BID
===== 202-00810		Rem Ground Sign		Each =====			
STA059A-036		SH 59 SEIBERT TO COPE	02/06/20	20.00	125.00	126.00	102.00
STR116A-001		SH 116 A Surface Treatment Pr	02/13/20	109.00	85.00	154.58	150.00
FSA2873-194		US 287 Longmont Intersection	02/13/20	1.00	400.00	168.33	165.00
STA069A-033		SH69 MP 58.7 TO 71.58	02/13/20	156.00	65.00	84.31	100.00
STR0101-027		SH 10 Overlay La Junta West	02/27/20	98.00	75.00	111.01	100.00
C0402-094		US 40 GRAND COUNTY SIGNAL REP	02/27/20	1.00	150.00	375.00	500.00
NH0242-085		US 24 M.P. 291.38 to M.P. 296	02/27/20	180.00	88.50	102.29	114.00
NHPP0171-105		SH 17 MP 84.5 to US 285 & SH	03/05/20	13.00	200.00	151.67	153.01
NHPP145A-080		SH 145 Keystone-Placerville R	03/05/20	5.00	150.00	150.00	150.00
STR2871-038		US 287 Passing Lanes Springfi	03/05/20	3.00	100.00	156.28	175.50
NHPP0091-044		SH 9 FRISCO MAIN ST TO IRON S	03/05/20	14.00	200.00	100.00	91.00
NH050A-034		US50A PUEBLO WEST PURCELL INT	03/26/20	57.00	80.00	69.27	76.00
SHE 0703-461		I-70 and Kipling North Phase	03/26/20	9.00	200.00	147.00	20.00
		WEIGHTED AVERAGE FOR THE FIRST QUARTER		795.00	85.78	103.94	110.43
NHPP1602-169		US 160 WC TUNNEL EAST RESURFA	04/02/20	1.00	175.00	175.40	167.84
IM0761-226		I76/SH52 Interchange	04/02/20	79.00	70.00	135.43	159.00
STA340A-021		SH340 MP 6-6.76 MESA COUNTY	04/02/20	1.00	100.00	402.00	1000.00
SHER100-339		WWD TRAFFIC CONTROL ENHANCEME	04/09/20	495.00	150.00	100.00	100.00
SFTY2254-091		225 Ramp Improvements	04/09/20	4.00	150.00	222.50	215.00
CC0852-106		US-85 LOUVIERS TO MP 191.75	04/23/20	30.00	200.00	121.92	110.00
FBR0852-108		US-85 BETWEEN LOUVIERS AND MP					
C1211-090		SH-121 & 29th Ave / SH-121 &	04/23/20	5.00	70.00	192.67	125.00
C1601-082		Hawkins Signal and Curb Ramps	04/30/20	3.00	150.00	413.33	815.00
FSA1602-159		US 160 AND SH 17 INTERSECTION	04/30/20	21.00	50.00	226.67	215.00
C0853-112		US85 & WCR98 INTERSECTION IMP	05/07/20	5.00	100.00	110.38	113.00
NHPP0402-098		US 40 CHIP SEAL MP 126 TO MP	05/14/20	1.00	100.00	253.33	350.00
NHPP0253-276		I-25 EXPRESS LANES SEGMENT 5	05/15/20	13.00	468.00	259.49	259.49
ITSSW01-719		FY 20 ITS CAPITAL REPLACEMENT	06/11/20	9.00	200.00	2000.00	2500.00
SHE016A-043		SH 21 & 16 SIGNALS PROJECT	06/18/20	6.00	110.00	141.23	98.17
		WEIGHTED AVERAGE FOR THE SECOND QUARTER		673.00	145.10	151.94	152.08
		WEIGHTED AVERAGE FOR THE YEAR		1,468.00	112.97	122.05	129.52
===== 202-00815		Rem of Sign (Special)		Each =====			
NHPP0091-044		SH 9 FRISCO MAIN ST TO IRON S	03/05/20	5.00	1000.00	1001.67	530.00
		WEIGHTED AVERAGE FOR THE FIRST QUARTER		5.00	1000.00	1001.67	530.00
FSA1602-159		US 160 AND SH 17 INTERSECTION	04/30/20	1.00	1000.00	7139.33	8440.00
		WEIGHTED AVERAGE FOR THE SECOND QUARTER		1.00	1000.00	7139.33	8440.00
		WEIGHTED AVERAGE FOR THE YEAR		6.00	1000.00	2024.61	1848.33

PROJECT NUMBER	ITEM NUMBER/ PROJECT LOCATION	ITEM DESCRIPTION/ PROJECT LOCATION	DATE LET	UNIT/ QUANTITY	ENGR. EST.	AVERAGE BID	AWARDED BID
===== 202-00821		Rem Sign Panel		Each =====			
	STA0142-066	SH 14 New Raymer West	01/09/20	38.00	80.00	39.00	26.00
	FSA0253-262	I-25 SB BOTTLENECK I-76 TO I-	01/09/20	6.00	40.00	657.23	510.00
	NHPP0253-265	I-25 AT ERIE PARKWAY ON AND O	01/09/20	60.00	50.00	84.00	90.00
	FSA0341-097	US 34 & MACGREGOR INTERSECTIO	01/09/20	2.00	30.00	110.00	110.00
	NH 0503-093	US50 WEST OF TEXAS CREEK MP 2	01/23/20	223.00	30.00	69.13	68.26
	NHPP 0852-116	US85:HAMPDEN TO FLORIDA-RESUR	02/06/20	8.00	100.00	135.00	120.00
	STA0703-443	I-70 EJMT TUNNELS PAVING	02/06/20	17.00	60.00	102.18	99.36
	STR116A-001	SH 116 A Surface Treatment Pr	02/13/20	37.00	39.20	150.32	200.00
	FSA2873-194	US 287 Longmont Intersection	02/13/20	1.00	60.00	181.67	275.00
	STA069A-033	SH69 MP 58.7 TO 71.58	02/13/20	4.00	30.00	84.31	100.00
	STR0101-027	SH 10 Overlay La Junta West	02/27/20	55.00	75.00	46.59	65.00
	NH0242-085	US 24 M.P. 291.38 to M.P. 296	02/27/20	88.00	60.00	61.46	51.35
	NHPP0171-105	SH 17 MP 84.5 to US 285 & SH	03/05/20	58.00	30.00	47.93	40.80
	NHPP145A-080	SH 145 Keystone-Placerville R	03/05/20	63.00	80.00	66.00	66.00
	HPP 0501-067	US 50 AND SH 92 DELTA INTERSE	03/26/20	4.00	40.00	93.00	90.00
	SHE 0703-461	I-70 and Kipling North Phase	03/26/20	17.00	70.00	234.40	110.00
		WEIGHTED AVERAGE FOR THE FIRST QUARTER		681.00	49.95	83.77	77.04
	NHPP1602-169	US 160 WC TUNNEL EAST RESURFA	04/02/20	85.00	110.00	82.58	108.29
	SHER100-339	WWD TRAFFIC CONTROL ENHANCEME	04/09/20	366.00	65.00	50.00	50.00
	C1211-090	SH-121 & 29th Ave / SH-121 &	04/23/20	1.00	53.00	140.33	70.00
	NHPPR100-303	LONG MAST ARM SIGNALS PROJECT	05/07/20	2.00	50.00	71.00	70.00
		WEIGHTED AVERAGE FOR THE SECOND QUARTER		454.00	73.33	63.82	61.05
		WEIGHTED AVERAGE FOR THE YEAR		1,135.00	59.30	78.45	70.64
===== 202-00825		Rem Flashing Beacon		Each =====			
	NH050A-034	US50A PUEBLO WEST PURCELL INT	03/26/20	4.00	50.00	416.01	402.00
		WEIGHTED AVERAGE FOR THE FIRST QUARTER		4.00	50.00	416.01	402.00
		WEIGHTED AVERAGE FOR THE YEAR		4.00	50.00	416.01	402.00
===== 202-00827		Rem of Pull Box		Each =====			
	FSA0341-097	US 34 & MACGREGOR INTERSECTIO	01/09/20	2.00	200.00	350.00	350.00

PROJECT NUMBER	ITEM NUMBER/ PROJECT LOCATION	ITEM DESCRIPTION/ PROJECT LOCATION	DATE LET	UNIT/ QUANTITY	ENGR. EST.	AVERAGE BID	AWARDED BID
===== 202-00827							
		Rem of Pull Box		Each			
STRR300-249		Grand and Jackson Counties AD	03/05/20	8.00	300.00	431.00	300.00
CC080-037		VARIOUS ADA RAMPS ALONG NORTH	03/05/20	4.00	300.00	451.37	200.00
NHPP0091-044		SH 9 FRISCO MAIN ST TO IRON S	03/05/20	12.00	200.00	685.00	660.00
NH050A-034		US50A PUEBLO WEST PURCELL INT	03/26/20	1.00	350.00	249.17	260.00
		WEIGHTED AVERAGE FOR THE FIRST QUARTER		27.00	250.00	522.32	447.41
IM0761-226		I76/SH52 Interchange	04/02/20	4.00	1000.00	138.69	104.94
C1601-082		Hawkins Signal and Curb Ramps	04/30/20	18.00	350.00	326.67	195.00
FSA1602-159		US 160 AND SH 17 INTERSECTION	04/30/20	5.00	150.00	247.00	220.00
NHPPR100-303		LONG MAST ARM SIGNALS PROJECT	05/07/20	2.00	180.00	277.67	600.00
NHPP0253-276		I-25 EXPRESS LANES SEGMENT 5	05/15/20	10.00	482.00	481.50	481.50
		WEIGHTED AVERAGE FOR THE SECOND QUARTER		39.00	416.15	280.61	283.20
		WEIGHTED AVERAGE FOR THE YEAR		66.00	348.18	385.07	350.38
===== 202-00828							
		Rem Traf Sig Equipment		LUMP SUM			
C0402-094		US 40 GRAND COUNTY SIGNAL REP	02/27/20	1.00	15000.00	15000.00	10000.00
NHPP0091-044		SH 9 FRISCO MAIN ST TO IRON S	03/05/20	1.00	30000.00	20783.33	20000.00
NH050A-034		US50A PUEBLO WEST PURCELL INT	03/26/20	1.00	6000.00	12621.25	11000.00
HPP 0501-067		US 50 AND SH 92 DELTA INTERSE	03/26/20	1.00	8000.00	5014.00	5152.00
SHE 0703-461		I-70 and Kipling North Phase	03/26/20	1.00	12000.00	24136.00	22200.00
		WEIGHTED AVERAGE FOR THE FIRST QUARTER		5.00	14200.00	16201.40	13670.40
CC0852-106		US-85 LOUVIERS TO MP 191.75	04/23/20	1.00	12000.00	6241.34	6077.50
FBR0852-108		US-85 BETWEEN LOUVIERS AND MP					
C1211-090		SH-121 & 29th Ave / SH-121 &	04/23/20	1.00	15000.00	24954.12	20585.00
NHPPR100-303		LONG MAST ARM SIGNALS PROJECT	05/07/20	1.00	27500.00	34698.33	45295.00
FSAR400-356		FY 20 SIGNAL POLE REPLACEMENT	06/11/20	1.00	10000.00	19395.00	8885.00
SHE016A-043		SH 21 & 16 SIGNALS PROJECT	06/18/20	1.00	15000.00	17626.00	21656.00
		WEIGHTED AVERAGE FOR THE SECOND QUARTER		5.00	15900.00	17054.68	20499.70
		WEIGHTED AVERAGE FOR THE YEAR		10.00	15050.00	16648.36	17085.05
===== 202-00831							
		Rem Traf Sig Head		Each			
FSA2873-194		US 287 Longmont Intersection	02/13/20	2.00	125.00	259.17	95.00

COLORADO DEPARTMENT OF TRANSPORTATION
 ITEM UNIT COSTS BY PROJECTS -- 2020 COST DATA

10:58 Friday, October 2, 2020 30

PROJECT NUMBER	ITEM NUMBER/ PROJECT LOCATION	ITEM DESCRIPTION/ PROJECT LOCATION	DATE LET	UNIT/ QUANTITY	ENGR. EST.	AVERAGE BID	AWARDED BID
===== 202-00831	HPP 0501-067	Rem Traf Sig Head US 50 AND SH 92 DELTA INTERSE	03/26/20	Each 3.00	115.00	244.50	247.00
		WEIGHTED AVERAGE FOR THE FIRST QUARTER		5.00	119.00	254.28	186.20
		WEIGHTED AVERAGE FOR THE YEAR		5.00	119.00	254.28	186.20
===== 202-00832	SFTY2254-091	Rem of Sign Panel (Spec) 225 Ramp Improvements	04/09/20	Each 3.00	3500.00	597.50	580.00
		WEIGHTED AVERAGE FOR THE SECOND QUARTER		3.00	3500.00	597.50	580.00
		WEIGHTED AVERAGE FOR THE YEAR		3.00	3500.00	597.50	580.00
===== 202-00840	NHPP0091-044	Rem Traf Sig Pole SH 9 FRISCO MAIN ST TO IRON S	03/05/20	Each 2.00	1000.00	2550.00	2500.00
		WEIGHTED AVERAGE FOR THE FIRST QUARTER		2.00	1000.00	2550.00	2500.00
		WEIGHTED AVERAGE FOR THE YEAR		2.00	1000.00	2550.00	2500.00
===== 202-00858	SHE016A-043	Rem Pedestal Pole SH 21 & 16 SIGNALS PROJECT	06/18/20	Each 3.00	1100.00	570.13	495.67
		WEIGHTED AVERAGE FOR THE SECOND QUARTER		3.00	1100.00	570.13	495.67
		WEIGHTED AVERAGE FOR THE YEAR		3.00	1100.00	570.13	495.67
===== 202-00860	C1601-082	Rem Ped Push Button Hawkins Signal and Curb Ramps	04/30/20	Each 32.00	75.00	566.67	100.00
		WEIGHTED AVERAGE FOR THE SECOND QUARTER		32.00	75.00	566.67	100.00
		WEIGHTED AVERAGE FOR THE YEAR		32.00	75.00	566.67	100.00
===== 202-00889	NHPP0343-041	Rem of Detect Warning I-76 & US 34 FT. MORGAN AREA	01/09/20	Each 30.00	400.00	351.00	288.00
		WEIGHTED AVERAGE FOR THE FIRST QUARTER		30.00	400.00	351.00	288.00
		WEIGHTED AVERAGE FOR THE YEAR		30.00	400.00	351.00	288.00

COLORADO DEPARTMENT OF TRANSPORTATION
ITEM UNIT COSTS BY PROJECTS -- 2020 COST DATA

10:58 Friday, October 2, 2020 31

PROJECT NUMBER	ITEM NUMBER/ PROJECT LOCATION	ITEM DESCRIPTION/ PROJECT LOCATION	DATE LET	UNIT/ QUANTITY	ENGR. EST.	AVERAGE BID	AWARDED BID
=====	202-00890	Rem Span Wire Cable		Lin Foot	=====		
NHPP0091-044		SH 9 FRISCO MAIN ST TO IRON S	03/05/20	64.00	5.00	11.33	11.00
		WEIGHTED AVERAGE FOR THE FIRST QUARTER		64.00	5.00	11.33	11.00
		WEIGHTED AVERAGE FOR THE YEAR		64.00	5.00	11.33	11.00
=====	202-00895	Rem of Impact Attenuator		Each	=====		
NHPP0343-041		I-76 & US 34 FT. MORGAN AREA	01/09/20	2.00	1101.00	2902.67	6238.00
STA0703-443		I-70 EJMT TUNNELS PAVING	02/06/20	1.00	2500.00	1667.59	1720.18
		WEIGHTED AVERAGE FOR THE FIRST QUARTER		3.00	1567.33	2593.90	4732.06
		WEIGHTED AVERAGE FOR THE YEAR		3.00	1567.33	2593.90	4732.06
=====	202-00900	Rem Conc Footing		Each	=====		
FSA0341-097		US 34 & MACGREGOR INTERSECTIO	01/09/20	2.00	500.00	1500.00	1500.00
		WEIGHTED AVERAGE FOR THE FIRST QUARTER		2.00	500.00	1500.00	1500.00
		WEIGHTED AVERAGE FOR THE YEAR		2.00	500.00	1500.00	1500.00
=====	202-01000	Rem Fence		Lin Foot	=====		
BR0343-040		US 34 REPUBLICAN RIVER BRIDGE	01/16/20	268.00	3.00	3.66	4.00
FBR0343-043		US 34 D-28-P STRUCTURE REPLAC					
NHPP0091-044		SH 9 FRISCO MAIN ST TO IRON S	03/05/20	790.00	2.00	2.65	2.60
NH050A-034		US50A PUEBLO WEST PURCELL INT	03/26/20	2,219.00	1.75	2.72	0.90
		WEIGHTED AVERAGE FOR THE FIRST QUARTER		3,277.00	1.91	2.78	1.56
IM0761-226		I76/SH52 Interchange	04/02/20	76.00	2.00	3.39	3.07
STA340A-021		SH340 MP 6-6.76 MESA COUNTY	04/02/20	806.00	3.00	4.35	5.00
CC0852-106		US-85 LOUVIERS TO MP 191.75	04/23/20	11,365.00	2.00	0.67	0.77
FBR0852-108		US-85 BETWEEN LOUVIERS AND MP					
FSA1602-159		US 160 AND SH 17 INTERSECTION	04/30/20	332.00	6.00	8.67	3.00

PROJECT NUMBER	ITEM NUMBER/ PROJECT LOCATION	ITEM DESCRIPTION/ PROJECT LOCATION	DATE LET	UNIT/ QUANTITY	ENGR. EST.	AVERAGE BID	AWARDED BID
=====	202-01000	Rem Fence		Lin Foot	=====		
NHPP0253-276		I-25 EXPRESS LANES SEGMENT 5	05/15/20	4,142.00	1.00	0.92	0.92
NH050A-035		US 50A Pueblo Regional Pond	05/28/20	200.00	2.00	8.59	1.25
NH050A-037		US 50A Pueblo Regional Pond					
	WEIGHTED AVERAGE FOR THE SECOND QUARTER			16,921.00	1.88	0.99	1.07
	WEIGHTED AVERAGE FOR THE YEAR			20,198.00	1.89	1.31	1.15
=====	202-01035	Rem of Gate		Each	=====		
NH050A-034		US50A PUEBLO WEST PURCELL INT	03/26/20	1.00	200.00	301.02	200.00
	WEIGHTED AVERAGE FOR THE FIRST QUARTER			1.00	200.00	301.02	200.00
NHPP0253-276		I-25 EXPRESS LANES SEGMENT 5	05/15/20	2.00	128.00	130.36	130.36
	WEIGHTED AVERAGE FOR THE SECOND QUARTER			2.00	128.00	130.36	130.36
	WEIGHTED AVERAGE FOR THE YEAR			3.00	152.00	266.89	153.57
=====	202-01130	Rem Gdrail Ty 3		Lin Foot	=====		
NHPP0343-041		I-76 & US 34 FT. MORGAN AREA	01/09/20	22,112.00	5.00	4.80	4.50
BR0343-040		US 34 REPUBLICAN RIVER BRIDGE	01/16/20	753.00	5.00	6.29	4.85
FBR0343-043		US 34 D-28-P STRUCTURE REPLAC					
STR131A-038		SH 131 MP 51.95-55.73, ROUTT	01/16/20	4,965.00	6.00	3.48	3.30
NH 0503-093		US50 WEST OF TEXAS CREEK MP 2	01/23/20	23,906.00	10.00	5.55	7.09
STR141A-044		SH 141 AND SH 145, FROM SLICK	01/30/20	5,743.00	4.00	3.94	3.80
STA0703-443		I-70 EJMT TUNNELS PAVING	02/06/20	505.00	12.00	6.30	6.49
STA059A-036		SH 59 SEIBERT TO COPE	02/06/20	675.00	10.00	9.00	8.00
STR116A-001		SH 116 A Surface Treatment Pr	02/13/20	1,900.00	6.00	6.99	9.00
STA069A-033		SH69 MP 58.7 TO 71.58	02/13/20	5,575.00	4.50	7.99	8.00
STR0101-027		SH 10 Overlay La Junta West	02/27/20	1,163.00	10.00	8.38	5.00
NH0242-085		US 24 M.P. 291.38 to M.P. 296	02/27/20	3,134.00	3.20	3.98	4.00
NHPP0171-105		SH 17 MP 84.5 to US 285 & SH	03/05/20	988.00	8.00	6.23	9.49
C0641-106		SH 64 Meeker West Rural Resur	03/05/20	1,862.50	6.00	3.20	3.30
NHPP145A-080		SH 145 Keystone-Placerville R	03/05/20	50.00	15.00	11.50	11.50
BR025A-046		K-18-U ON I-25 AT MP112 BRIDG	03/05/20	344.00	4.50	8.69	5.18
NH050A-034		US50A PUEBLO WEST PURCELL INT	03/26/20	470.00	4.50	3.36	2.25
HPP 0501-067		US 50 AND SH 92 DELTA INTERSE	03/26/20	69.00	10.00	23.28	9.00
	WEIGHTED AVERAGE FOR THE FIRST QUARTER			74,214.50	6.75	5.14	5.65

PROJECT NUMBER	ITEM NUMBER/ PROJECT LOCATION	ITEM DESCRIPTION/ PROJECT LOCATION	DATE LET	UNIT/ QUANTITY	ENGR. EST.	AVERAGE BID	AWARDED BID
===== 202-01130		Rem Gdrail Ty 3		Lin Foot	=====		
NHPP1602-169		US 160 WC TUNNEL EAST RESURFA	04/02/20	8,366.00	6.00	7.77	7.04
STR092A-030		SH92 MP 31.748-48.5, DELTA AND	04/02/20	4,871.00	5.00	4.93	4.25
IM0761-226		I76/SH52 Interchange	04/02/20	906.00	7.00	2.82	2.70
STR0341-101		SH 34 North of Grandby Resurf	04/02/20	3,538.00	5.00	4.29	2.65
IM0252-473		I-25 CABLE BARRIER PHASE IV	04/09/20	1,103.00	5.00	4.09	3.17
SFTY2254-091		225 Ramp Improvements	04/09/20	1,152.00	20.00	3.75	3.50
CC0852-106		US-85 LOUVIERS TO MP 191.75	04/23/20	2,899.00	3.50	3.53	3.52
FBR0852-108		US-85 BETWEEN LOUVIERS AND MP					
FSA1602-159		US 160 AND SH 17 INTERSECTION	04/30/20	172.00	10.00	24.17	27.00
FBR0343-042		US 34 D-27-G STRUCTURE REPLAC	05/07/20	676.00	5.00	5.91	8.00
NHPP0253-276		I-25 EXPRESS LANES SEGMENT 5	05/15/20	375.00	3.00	3.37	3.37
ITSSW01-719		FY 20 ITS CAPITAL REPLACEMENT	06/11/20	775.00	14.00	10.75	11.50
		WEIGHTED AVERAGE FOR THE SECOND QUARTER		24,833.00	6.22	5.32	5.21
		WEIGHTED AVERAGE FOR THE YEAR		99,047.50	6.62	5.20	5.54
===== 202-01170		Rem Gdrail Ty 7		Lin Foot	=====		
NH 0503-093		US50 WEST OF TEXAS CREEK MP 2	01/23/20	300.00	10.00	36.91	33.82
NHPP0091-044		SH 9 FRISCO MAIN ST TO IRON S	03/05/20	347.00	50.00	16.50	18.00
SHE 0703-461		I-70 and Kipling North Phase	03/26/20	165.00	65.00	70.40	37.00
		WEIGHTED AVERAGE FOR THE FIRST QUARTER		812.00	38.27	39.50	27.71
STR092A-030		SH92 MP 31.748-48.5, DELTA AND	04/02/20	50.00	30.00	90.00	28.00
IM0761-226		I76/SH52 Interchange	04/02/20	350.00	11.00	25.54	18.99
SFTY2254-091		225 Ramp Improvements	04/09/20	1,068.00	70.00	24.50	25.00
		WEIGHTED AVERAGE FOR THE SECOND QUARTER		1,468.00	54.57	26.44	23.67
		WEIGHTED AVERAGE FOR THE YEAR		2,280.00	48.77	30.94	25.11
===== 202-01175		Rem of Guardrail (Spec)		Lin Foot	=====		
NHPP 0852-116		US85:HAMPDEN TO FLORIDA-RESUR	02/06/20	50.00	27.00	67.50	100.00
		WEIGHTED AVERAGE FOR THE FIRST QUARTER		50.00	27.00	67.50	100.00
		WEIGHTED AVERAGE FOR THE YEAR		50.00	27.00	67.50	100.00

PROJECT NUMBER	ITEM NUMBER/ PROJECT LOCATION	ITEM DESCRIPTION/ PROJECT LOCATION	DATE LET	UNIT/ QUANTITY	ENGR. EST.	AVERAGE BID	AWARDED BID
=====	202-01180	Rem Median Barrier		Lin Foot	=====		
NHPP 0852-116		US85:HAMPDEN TO FLORIDA-RESUR	02/06/20	112.00	75.00	75.00	90.00
		WEIGHTED AVERAGE FOR THE FIRST QUARTER		112.00	75.00	75.00	90.00
SFTY2254-091		225 Ramp Improvements	04/09/20	32.00	50.00	59.50	85.00
		WEIGHTED AVERAGE FOR THE SECOND QUARTER		32.00	50.00	59.50	85.00
		WEIGHTED AVERAGE FOR THE YEAR		144.00	69.44	71.56	88.89
=====	202-01200	Rem Tensioned Cable Barrier		Lin Foot	=====		
IM0252-473		I-25 CABLE BARRIER PHASE IV	04/09/20	1,262.00	5.00	5.09	3.17
		WEIGHTED AVERAGE FOR THE SECOND QUARTER		1,262.00	5.00	5.09	3.17
		WEIGHTED AVERAGE FOR THE YEAR		1,262.00	5.00	5.09	3.17
=====	202-01300	Rem End Anchorage		Each	=====		
NHPP0343-041		I-76 & US 34 FT. MORGAN AREA	01/09/20	52.00	324.00	311.00	380.00
BR0343-040		US 34 REPUBLICAN RIVER BRIDGE	01/16/20	8.00	400.00	446.06	300.00
FBR0343-043		US 34 D-28-P STRUCTURE REPLAC					
STR131A-038		SH 131 MP 51.95-55.73, ROUTT	01/16/20	12.00	300.00	347.50	330.00
NH 0503-093		US50 WEST OF TEXAS CREEK MP 2	01/23/20	72.00	400.00	151.98	103.96
STR141A-044		SH 141 AND SH 145, FROM SLICK	01/30/20	22.00	350.00	381.93	395.00
STA059A-036		SH 59 SEIBERT TO COPE	02/06/20	4.00	300.00	427.00	354.00
STA069A-033		SH69 MP 58.7 TO 71.58	02/13/20	51.00	300.00	380.67	400.00
NH0242-085		US 24 M.P. 291.38 to M.P. 296	02/27/20	6.00	375.00	284.91	210.00
C0641-106		SH 64 Meeker West Rural Resur	03/05/20	10.00	300.00	622.50	1025.00
NHPP145A-080		SH 145 Keystone-Placerville R	03/05/20	2.00	400.00	550.00	550.00
BR025A-046		K-18-U ON I-25 AT MP112 BRIDG	03/05/20	1.00	300.00	654.97	625.21
NH050A-034		US50A PUEBLO WEST PURCELL INT	03/26/20	5.00	300.00	404.22	340.00
		WEIGHTED AVERAGE FOR THE FIRST QUARTER		245.00	344.89	329.66	322.64
NHPP1602-169		US 160 WC TUNNEL EAST RESURFA	04/02/20	29.00	350.00	463.08	308.62

PROJECT NUMBER	ITEM NUMBER/ PROJECT LOCATION	ITEM DESCRIPTION/ PROJECT LOCATION	DATE LET	UNIT/ QUANTITY	ENGR. EST.	AVERAGE BID	AWARDED BID
=====	202-01300	Rem End Anchorage		Each	=====	=====	=====
STR092A-030		SH92 MP 31.748-48.5, DELTA AND	04/02/20	24.00	200.00	332.50	400.00
IM0761-226		I76/SH52 Interchange	04/02/20	9.00	250.00	239.55	233.20
STR0341-101		SH 34 North of Grandby Resurf	04/02/20	22.00	400.00	412.38	220.00
IM0252-473		I-25 CABLE BARRIER PHASE IV	04/09/20	11.00	300.00	444.45	388.89
SFTY2254-091		225 Ramp Improvements	04/09/20	3.00	300.00	277.50	270.00
CC0852-106		US-85 LOUVIERS TO MP 191.75	04/23/20	12.00	350.00	286.53	242.00
FBR0852-108		US-85 BETWEEN LOUVIERS AND MP					
FSA1602-159		US 160 AND SH 17 INTERSECTION	04/30/20	4.00	350.00	1002.67	893.00
FBR0343-042		US 34 D-27-G STRUCTURE REPLAC	05/07/20	4.00	400.00	379.20	500.00
NHPP0253-276		I-25 EXPRESS LANES SEGMENT 5	05/15/20	2.00	241.00	244.42	244.42
		WEIGHTED AVERAGE FOR THE SECOND QUARTER		120.00	315.68	375.54	329.51
		WEIGHTED AVERAGE FOR THE YEAR		365.00	335.29	348.19	324.90
=====	202-04001	Plug Culvert		Each	=====	=====	=====
NH050A-034		US50A PUEBLO WEST PURCELL INT	03/26/20	16.00	4000.00	2788.59	4300.00
		WEIGHTED AVERAGE FOR THE FIRST QUARTER		16.00	4000.00	2788.59	4300.00
IM0761-226		I76/SH52 Interchange	04/02/20	2.00	3000.00	1220.30	472.00
		WEIGHTED AVERAGE FOR THE SECOND QUARTER		2.00	3000.00	1220.30	472.00
		WEIGHTED AVERAGE FOR THE YEAR		18.00	3888.89	2633.97	3874.67
=====	202-04002	Clean Culvert		Each	=====	=====	=====
FSA0341-097		US 34 & MACGREGOR INTERSECTIO	01/09/20	8.00	1500.00	3000.00	3000.00
NHPP0343-041		I-76 & US 34 FT. MORGAN AREA	01/09/20	82.00	1650.00	2132.98	2668.00
BR0343-040		US 34 REPUBLICAN RIVER BRIDGE	01/16/20	2.00	1750.00	2221.53	2000.00
FBR0343-043		US 34 D-28-P STRUCTURE REPLAC					
NH 0503-093		US50 WEST OF TEXAS CREEK MP 2	01/23/20	75.00	364.00	930.86	595.06
NHPP4701-134		C-470 NOISE WALL WEST OF LUCE	02/06/20	2.00	1000.00	2280.00	950.00
NHPP0171-105		SH 17 MP 84.5 to US 285 & SH	03/05/20	14.00	3000.00	2813.08	3939.23
NH050A-034		US50A PUEBLO WEST PURCELL INT	03/26/20	1.00	2400.00	3083.13	2700.00
HPP 0501-067		US 50 AND SH 92 DELTA INTERSE	03/26/20	1.00	1500.00	2519.43	3622.00
SHE 0703-461		I-70 and Kipling North Phase	03/26/20	16.00	3000.00	1636.00	1350.00
		WEIGHTED AVERAGE FOR THE FIRST QUARTER		201.00	1363.18	1821.74	1872.52

PROJECT NUMBER	ITEM NUMBER/ PROJECT LOCATION	ITEM DESCRIPTION/ PROJECT LOCATION	DATE LET	UNIT/ QUANTITY	ENGR. EST.	AVERAGE BID	AWARDED BID
===== 202-04002		Clean Culvert		Each	=====		
IM0761-226		I76/SH52 Interchange	04/02/20	9.00	2000.00	2098.88	582.00
IM0252-473		I-25 CABLE BARRIER PHASE IV	04/09/20	13.00	1500.00	2287.50	1875.00
C1601-082		Hawkins Signal and Curb Ramps	04/30/20	1.00	3000.00	6050.00	2200.00
FSA1602-159		US 160 AND SH 17 INTERSECTION	04/30/20	2.00	3500.00	2558.00	1190.00
C0853-112		US85 & WCR98 INTERSECTION IMP	05/07/20	1.00	2000.00	1934.25	690.00
	WEIGHTED AVERAGE FOR THE SECOND QUARTER			26.00	1903.85	2270.53	1341.65
	WEIGHTED AVERAGE FOR THE YEAR			227.00	1425.11	1893.39	1811.72
===== 202-04004		Plug Culvert (Spec)		Each	=====		
NHPP145A-080		SH 145 Keystone-Placerville R	03/05/20	2.00	3000.00	4400.00	4400.00
	WEIGHTED AVERAGE FOR THE FIRST QUARTER			2.00	3000.00	4400.00	4400.00
	WEIGHTED AVERAGE FOR THE YEAR			2.00	3000.00	4400.00	4400.00
===== 202-04005		Clean Valve Box		Each	=====		
NHPP0343-041		I-76 & US 34 FT. MORGAN AREA	01/09/20	45.00	277.00	625.09	400.00
NHPP 0852-116		US85:HAMPDEN TO FLORIDA-RESUR	02/06/20	2.00	300.00	900.00	900.00
SHE 0703-461		I-70 and Kipling North Phase	03/26/20	2.00	150.00	510.00	250.00
	WEIGHTED AVERAGE FOR THE FIRST QUARTER			49.00	272.76	624.74	414.29
	WEIGHTED AVERAGE FOR THE YEAR			49.00	272.76	624.74	414.29
===== 202-04006		Clean Culvert		Hour	=====		
NHPP0253-276		I-25 EXPRESS LANES SEGMENT 5	05/15/20	10.00	300.00	475.50	475.50
	WEIGHTED AVERAGE FOR THE SECOND QUARTER			10.00	300.00	475.50	475.50
	WEIGHTED AVERAGE FOR THE YEAR			10.00	300.00	475.50	475.50
===== 202-04008		Clean Culvert		Lin Foot	=====		
STR012A-050		CULVERT REPAIR I-25 AND US 35	01/30/20	645.00	26.00	65.00	65.00
	WEIGHTED AVERAGE FOR THE FIRST QUARTER			645.00	26.00	65.00	65.00
	WEIGHTED AVERAGE FOR THE YEAR			645.00	26.00	65.00	65.00

PROJECT NUMBER	ITEM NUMBER/ PROJECT LOCATION	ITEM DESCRIPTION/ PROJECT LOCATION	DATE LET	UNIT/ QUANTITY	ENGR. EST.	AVERAGE BID	AWARDED BID
===== 202-04010		Clean Inlet		Each =====			
FSA0253-262		I-25 SB BOTTLENECK I-76 TO I-	01/09/20	7.00	900.00	847.18	205.00
NHPP0343-041		I-76 & US 34 FT. MORGAN AREA	01/09/20	4.00	328.00	1302.28	1112.00
NHPP 0852-116		US85:HAMPDEN TO FLORIDA-RESUR	02/06/20	77.00	600.00	900.00	800.00
STA0703-443		I-70 EJMT TUNNELS PAVING	02/06/20	18.00	850.00	2588.01	3346.01
NHPP4701-134		C-470 NOISE WALL WEST OF LUCE	02/06/20	5.00	300.00	1074.00	950.00
		WEIGHTED AVERAGE FOR THE FIRST QUARTER		111.00	636.14	1177.57	1193.34
IM0761-226		I76/SH52 Interchange	04/02/20	6.00	1500.00	608.44	770.00
SFTY2254-091		225 Ramp Improvements	04/09/20	14.00	1250.00	1117.50	1125.00
CC0852-106		US-85 LOUVIERS TO MP 191.75	04/23/20	8.00	2000.00	1792.57	412.50
FBR0852-108		US-85 BETWEEN LOUVIERS AND MP					
C1211-090		SH-121 & 29th Ave / SH-121 &	04/23/20	3.00	550.00	1292.00	800.00
C1601-082		Hawkins Signal and Curb Ramps	04/30/20	4.00	1500.00	2080.00	1240.00
FSA1602-159		US 160 AND SH 17 INTERSECTION	04/30/20	1.00	1500.00	1647.67	368.00
FSAR400-356		FY 20 SIGNAL POLE REPLACEMENT	06/11/20	10.00	1200.00	991.67	800.00
NHPPR100-251		SH 2/ Vasquez	06/25/20	1.00	1000.00	1798.85	1748.70
		WEIGHTED AVERAGE FOR THE SECOND QUARTER		47.00	1375.53	1297.09	875.46
		WEIGHTED AVERAGE FOR THE YEAR		158.00	856.09	1229.41	1098.78
===== 202-04100		Abandon Well		Each =====			
NHPP0091-044		SH 9 FRISCO MAIN ST TO IRON S	03/05/20	2.00	2000.00	2198.33	3000.00
		WEIGHTED AVERAGE FOR THE FIRST QUARTER		2.00	2000.00	2198.33	3000.00
CC0852-106		US-85 LOUVIERS TO MP 191.75	04/23/20	1.00	3000.00	4509.34	2750.00
FBR0852-108		US-85 BETWEEN LOUVIERS AND MP					
		WEIGHTED AVERAGE FOR THE SECOND QUARTER		1.00	3000.00	4509.34	2750.00
		WEIGHTED AVERAGE FOR THE YEAR		3.00	2333.33	3518.91	2916.67
===== 202-05010		Sawing Concrete (10 In)		Lin Foot =====			
CC0852-106		US-85 LOUVIERS TO MP 191.75	04/23/20	200.00	6.50	10.15	5.21

PROJECT NUMBER	ITEM NUMBER/ PROJECT LOCATION	ITEM DESCRIPTION/ PROJECT LOCATION	DATE LET	UNIT/ QUANTITY	ENGR. EST.	AVERAGE BID	AWARDED BID
===== 202-05010 FBR0852-108		Sawing Concrete (10 In) US-85 BETWEEN LOUVIERS AND MP		Lin Foot			
	WEIGHTED AVERAGE FOR THE SECOND QUARTER			200.00	6.50	10.15	5.21
	WEIGHTED AVERAGE FOR THE YEAR			200.00	6.50	10.15	5.21
===== 202-05026		Sawing Asphalt Mat (6 In)		Lin Foot			
SHE016A-043		SH 21 & 16 SIGNALS PROJECT	06/18/20	682.00	6.00	6.25	3.47
	WEIGHTED AVERAGE FOR THE SECOND QUARTER			682.00	6.00	6.25	3.47
	WEIGHTED AVERAGE FOR THE YEAR			682.00	6.00	6.25	3.47
===== 202-05030		Sawing Asphalt Mat (10 In)		Lin Foot			
BR025A-046		K-18-U ON I-25 AT MP112 BRIDG	03/05/20	676.00	4.00	7.41	6.32
	WEIGHTED AVERAGE FOR THE FIRST QUARTER			676.00	4.00	7.41	6.32
	WEIGHTED AVERAGE FOR THE YEAR			676.00	4.00	7.41	6.32
===== 202-05100		Sandblasting Reinf Steel		Sq Yard			
STA0703-443		I-70 EJMT TUNNELS PAVING	02/06/20	158.00	75.00	47.07	49.02
	WEIGHTED AVERAGE FOR THE FIRST QUARTER			158.00	75.00	47.07	49.02
	WEIGHTED AVERAGE FOR THE YEAR			158.00	75.00	47.07	49.02
===== 202-06530		Clean Drain Pipe (Spec)		Each			
STR092A-030		SH92 MP 31.748-48.5, DELTA AND	04/02/20	16.00	125.00	409.50	113.00
	WEIGHTED AVERAGE FOR THE SECOND QUARTER			16.00	125.00	409.50	113.00
	WEIGHTED AVERAGE FOR THE YEAR			16.00	125.00	409.50	113.00
===== 202-07000		Oblit Old Road		LUMP SUM			
NHPP0091-044		SH 9 FRISCO MAIN ST TO IRON S	03/05/20	1.00	10000.00	10958.33	10800.00
	WEIGHTED AVERAGE FOR THE FIRST QUARTER			1.00	10000.00	10958.33	10800.00
	WEIGHTED AVERAGE FOR THE YEAR			1.00	10000.00	10958.33	10800.00

PROJECT NUMBER	ITEM NUMBER/ PROJECT LOCATION	ITEM DESCRIPTION/ PROJECT LOCATION	DATE LET	UNIT/ QUANTITY	ENGR. EST.	AVERAGE BID	AWARDED BID
===== 203-00000		Uncl Excav		Cubic Yard	=====		
STA059A-036	SH 59 SEIBERT TO COPE	SH 59 SEIBERT TO COPE	02/06/20	2,260.00	18.00	23.50	22.00
STA069A-033	SH69 MP 58.7 TO 71.58	SH69 MP 58.7 TO 71.58	02/13/20	657.00	9.00	26.79	26.00
STR0101-027	SH 10 Overlay La Junta West	SH 10 Overlay La Junta West	02/27/20	2,523.00	50.00	39.54	40.00
NHPP0702-359	I-70 No Name Tunnel Lighting	I-70 No Name Tunnel Lighting	02/27/20	15.00	250.00	153.35	175.00
NHPP145A-080	SH 145 Keystone-Placerville R	SH 145 Keystone-Placerville R	03/05/20	131.00	100.00	23.00	23.00
NH050A-034	US50A PUEBLO WEST PURCELL INT	US50A PUEBLO WEST PURCELL INT	03/26/20	9,971.00	15.00	15.67	14.00
HPP 0501-067	US 50 AND SH 92 DELTA INTERSE	US 50 AND SH 92 DELTA INTERSE	03/26/20	1,430.00	25.00	33.93	27.50
	WEIGHTED AVERAGE FOR THE FIRST QUARTER			16,987.00	22.07	18.70	20.74
NHPP0402-098	US 40 CHIP SEAL MP 126 TO MP	US 40 CHIP SEAL MP 126 TO MP	05/14/20	100.00	20.00	62.50	70.00
	WEIGHTED AVERAGE FOR THE SECOND QUARTER			100.00	20.00	62.50	70.00
	WEIGHTED AVERAGE FOR THE YEAR			17,087.00	22.06	18.84	21.03
===== 203-00010		Uncl Excav (CIP)		Cubic Yard	=====		
FSA0253-262	I-25 SB BOTTLENECK I-76 TO I-	I-25 SB BOTTLENECK I-76 TO I-	01/09/20	725.00	25.00	41.80	30.00
FSA0341-097	US 34 & MACGREGOR INTERSECTIO	US 34 & MACGREGOR INTERSECTIO	01/09/20	625.00	50.00	36.00	36.00
PWQM240-172	El Paso County, north Colorad	El Paso County, north Colorad	01/23/20	1,297.00	20.00	53.75	98.00
STR116A-001	SH 116 A Surface Treatment Pr	SH 116 A Surface Treatment Pr	02/13/20	674.00	88.00	42.15	36.00
FSA2873-194	US 287 Longmont Intersection	US 287 Longmont Intersection	02/13/20	2,282.00	27.00	34.09	24.20
STR2871-038	US 287 Passing Lanes Springfi	US 287 Passing Lanes Springfi	03/05/20	14,547.00	20.00	13.34	9.75
BR025A-046	K-18-U ON I-25 AT MP112 BRIDG	K-18-U ON I-25 AT MP112 BRIDG	03/05/20	643.00	30.00	24.82	15.64
NHPP0091-044	SH 9 FRISCO MAIN ST TO IRON S	SH 9 FRISCO MAIN ST TO IRON S	03/05/20	7,292.00	25.00	33.05	33.00
	WEIGHTED AVERAGE FOR THE FIRST QUARTER			28,085.00	24.52	26.48	22.91
STA340A-021	SH340 MP 6-6.76 MESA COUNTY	SH340 MP 6-6.76 MESA COUNTY	04/02/20	1,656.00	22.00	25.37	31.00
IM0252-473	I-25 CABLE BARRIER PHASE IV	I-25 CABLE BARRIER PHASE IV	04/09/20	6,877.00	23.00	39.38	43.75
SFTY2254-091	225 Ramp Improvements	225 Ramp Improvements	04/09/20	6,310.00	45.00	43.00	47.00
CC0852-106	US-85 LOUVIERS TO MP 191.75	US-85 LOUVIERS TO MP 191.75	04/23/20	623,574.00	10.00	9.55	8.05
FBR0852-108	US-85 BETWEEN LOUVIERS AND MP	US-85 BETWEEN LOUVIERS AND MP					
C1601-082	Hawkins Signal and Curb Ramps	Hawkins Signal and Curb Ramps	04/30/20	336.00	50.00	96.33	192.00
FSA1602-159	US 160 AND SH 17 INTERSECTION	US 160 AND SH 17 INTERSECTION	04/30/20	2,722.00	30.00	59.33	40.00
FBR0343-042	US 34 D-27-G STRUCTURE REPLAC	US 34 D-27-G STRUCTURE REPLAC	05/07/20	1,547.00	30.00	30.77	35.00
NHPP0253-276	I-25 EXPRESS LANES SEGMENT 5	I-25 EXPRESS LANES SEGMENT 5	05/15/20	148,836.00	7.00	8.34	8.34

COLORADO DEPARTMENT OF TRANSPORTATION
ITEM UNIT COSTS BY PROJECTS -- 2020 COST DATA

10:58 Friday, October 2, 2020 40

PROJECT NUMBER	ITEM NUMBER/ PROJECT LOCATION	ITEM DESCRIPTION/ PROJECT LOCATION	DATE LET	UNIT/ QUANTITY	ENGR. EST.	AVERAGE BID	AWARDED BID
=====	203-00010	Uncl Excav (CIP)		Cubic Yard	=====		
NH050A-035	US 50A Pueblo Regional Pond	US 50A Pueblo Regional Pond	05/28/20	51,984.00	12.00	16.66	8.30
NH050A-037	US 50A Pueblo Regional Pond	US 50A Pueblo Regional Pond					
	WEIGHTED AVERAGE FOR THE SECOND QUARTER			843,842.00	10.10	10.34	8.97
	WEIGHTED AVERAGE FOR THE YEAR			871,927.00	10.57	10.56	9.42
=====	203-00040	Uncl Excav (Spec)		Cubic Yard	=====		
C0853-112	US85 & WCR98 INTERSECTION IMP	US85 & WCR98 INTERSECTION IMP	05/07/20	273.00	75.00	33.97	11.50
	WEIGHTED AVERAGE FOR THE SECOND QUARTER			273.00	75.00	33.97	11.50
	WEIGHTED AVERAGE FOR THE YEAR			273.00	75.00	33.97	11.50
=====	203-00050	Unsuitable Material		Cubic Yard	=====		
NHPP0343-041	I-76 & US 34 FT. MORGAN AREA	I-76 & US 34 FT. MORGAN AREA	01/09/20	1,419.00	30.00	28.00	35.00
BR0343-040	US 34 REPUBLICAN RIVER BRIDGE	US 34 REPUBLICAN RIVER BRIDGE	01/16/20	50.00	55.00	91.38	100.00
FBR0343-043	US 34 D-28-P STRUCTURE REPLAC	US 34 D-28-P STRUCTURE REPLAC					
PWQM240-172	El Paso County, north Colorad	El Paso County, north Colorad	01/23/20	260.00	40.00	49.50	48.00
STA059A-036	SH 59 SEIBERT TO COPE	SH 59 SEIBERT TO COPE	02/06/20	1,479.00	20.00	26.75	15.50
NHPP0171-105	SH 17 MP 84.5 to US 285 & SH	SH 17 MP 84.5 to US 285 & SH	03/05/20	100.00	50.00	73.26	79.79
NHPP145A-080	SH 145 Keystone-Placerville R	SH 145 Keystone-Placerville R	03/05/20	35.00	100.00	96.00	96.00
SHE 0703-461	I-70 and Kipling North Phase	I-70 and Kipling North Phase	03/26/20	200.00	40.00	72.60	60.00
	WEIGHTED AVERAGE FOR THE FIRST QUARTER			3,543.00	28.73	37.29	32.01
IM0761-226	I76/SH52 Interchange	I76/SH52 Interchange	04/02/20	1,000.00	35.00	24.90	40.00
FSA1602-159	US 160 AND SH 17 INTERSECTION	US 160 AND SH 17 INTERSECTION	04/30/20	545.00	35.00	108.00	84.00
C0853-112	US85 & WCR98 INTERSECTION IMP	US85 & WCR98 INTERSECTION IMP	05/07/20	20.00	65.00	77.25	13.00
FBR0343-042	US 34 D-27-G STRUCTURE REPLAC	US 34 D-27-G STRUCTURE REPLAC	05/07/20	100.00	80.00	49.42	25.00
NHPP0253-276	I-25 EXPRESS LANES SEGMENT 5	I-25 EXPRESS LANES SEGMENT 5	05/15/20	50.00	64.00	64.50	64.50
	WEIGHTED AVERAGE FOR THE SECOND QUARTER			1,715.00	38.82	42.17	53.51
	WEIGHTED AVERAGE FOR THE YEAR			5,258.00	32.02	39.78	39.02
=====	203-00060	Emb Matl (CIP)		Cubic Yard	=====		
NHPP0343-041	I-76 & US 34 FT. MORGAN AREA	I-76 & US 34 FT. MORGAN AREA	01/09/20	4,704.00	18.00	69.07	39.00

PROJECT NUMBER	ITEM NUMBER/ PROJECT LOCATION	ITEM DESCRIPTION/ PROJECT LOCATION	DATE LET	UNIT/ QUANTITY	ENGR. EST.	AVERAGE BID	AWARDED BID
=====	203-00060	Emb Matl (CIP)		Cubic Yard	=====	=====	=====
BR0343-040		US 34 REPUBLICAN RIVER BRIDGE	01/16/20	1,840.00	27.00	68.67	55.00
FBR0343-043		US 34 D-28-P STRUCTURE REPLAC					
NHPP4701-134		C-470 NOISE WALL WEST OF LUCE	02/06/20	250.00	50.00	58.80	51.00
STA059A-036		SH 59 SEIBERT TO COPE	02/06/20	8,647.00	40.00	49.00	48.00
STR116A-001		SH 116 A Surface Treatment Pr	02/13/20	497.00	80.00	36.77	40.00
STA069A-033		SH69 MP 58.7 TO 71.58	02/13/20	2,181.00	14.00	36.29	45.00
NHPP0171-105		SH 17 MP 84.5 to US 285 & SH	03/05/20	153,686.00	20.00	24.36	20.84
BR025A-046		K-18-U ON I-25 AT MP112 BRIDG	03/05/20	592.00	20.00	49.11	60.29
NHPP0091-044		SH 9 FRISCO MAIN ST TO IRON S	03/05/20	13,669.00	15.00	32.62	30.00
NH050A-034		US50A PUEBLO WEST PURCELL INT	03/26/20	192,375.00	15.00	19.28	17.50
SHE 0703-461		I-70 and Kipling North Phase	03/26/20	1,732.00	35.00	78.60	56.00
		WEIGHTED AVERAGE FOR THE FIRST QUARTER		380,173.00	17.89	21.87	20.89
STR092A-030		SH92 MP 31.748-48.5, DELTA AND	04/02/20	585.00	25.00	72.35	58.00
IM0761-226		I76/SH52 Interchange	04/02/20	58,002.00	17.00	22.55	17.35
C0853-112		US85 & WCR98 INTERSECTION IMP	05/07/20	9,589.00	22.00	28.47	18.50
ITSSW01-719		FY 20 ITS CAPITAL REPLACEMENT	06/11/20	16.00	75.00	137.50	25.00
		WEIGHTED AVERAGE FOR THE SECOND QUARTER		68,192.00	17.79	23.62	17.86
		WEIGHTED AVERAGE FOR THE YEAR		448,365.00	17.87	22.19	20.43
=====	203-00062	Emb Matl (CIP) (Spec)		Cubic Yard	=====	=====	=====
NHPP0343-041		I-76 & US 34 FT. MORGAN AREA	01/09/20	1,419.00	30.00	39.63	39.00
		WEIGHTED AVERAGE FOR THE FIRST QUARTER		1,419.00	30.00	39.63	39.00
		WEIGHTED AVERAGE FOR THE YEAR		1,419.00	30.00	39.63	39.00
=====	203-00066	Emb Matl (CIP) (R40)		Cubic Yard	=====	=====	=====
FSA2873-194		US 287 Longmont Intersection	02/13/20	761.00	50.00	64.37	87.00
NH050A-034		US50A PUEBLO WEST PURCELL INT	03/26/20	27,336.00	20.00	24.56	18.50
		WEIGHTED AVERAGE FOR THE FIRST QUARTER		28,097.00	20.81	25.38	20.36
		WEIGHTED AVERAGE FOR THE YEAR		28,097.00	20.81	25.38	20.36
=====	203-00100	Muck Excav		Cubic Yard	=====	=====	=====
NHPP0091-044		SH 9 FRISCO MAIN ST TO IRON S	03/05/20	100.00	35.00	40.50	49.00
		WEIGHTED AVERAGE FOR THE FIRST QUARTER		100.00	35.00	40.50	49.00

COLORADO DEPARTMENT OF TRANSPORTATION
 ITEM UNIT COSTS BY PROJECTS -- 2020 COST DATA

10:58 Friday, October 2, 2020 42

PROJECT NUMBER	ITEM NUMBER/ PROJECT LOCATION	ITEM DESCRIPTION/ PROJECT LOCATION	DATE LET	UNIT/ QUANTITY	ENGR. EST.	AVERAGE BID	AWARDED BID
=====	203-00100	Muck Excav		Cubic Yard	=====		
CC0852-106		US-85 LOUVIERS TO MP 191.75	04/23/20	200.00	30.00	38.19	40.00
FBR0852-108		US-85 BETWEEN LOUVIERS AND MP					
		WEIGHTED AVERAGE FOR THE SECOND QUARTER		200.00	30.00	38.19	40.00
		WEIGHTED AVERAGE FOR THE YEAR		300.00	31.67	38.56	43.00
=====	203-00400	Rock Excav		Cubic Yard	=====		
NHPP0702-359		I-70 No Name Tunnel Lighting	02/27/20	15.00	100.00	293.70	275.00
		WEIGHTED AVERAGE FOR THE FIRST QUARTER		15.00	100.00	293.70	275.00
CC0852-106		US-85 LOUVIERS TO MP 191.75	04/23/20	3,500.00	60.00	40.74	20.00
FBR0852-108		US-85 BETWEEN LOUVIERS AND MP					
		WEIGHTED AVERAGE FOR THE SECOND QUARTER		3,500.00	60.00	40.74	20.00
		WEIGHTED AVERAGE FOR THE YEAR		3,515.00	60.17	41.28	21.09
=====	203-00450	Rem Rock		Each	=====		
IM0761-226		I76/SH52 Interchange	04/02/20	7.00	12.00	262.69	115.00
		WEIGHTED AVERAGE FOR THE SECOND QUARTER		7.00	12.00	262.69	115.00
		WEIGHTED AVERAGE FOR THE YEAR		7.00	12.00	262.69	115.00
=====	203-01100	Proof Rolling		Hour	=====		
NHPP0343-041		I-76 & US 34 FT. MORGAN AREA	01/09/20	90.00	128.00	104.67	89.00
STR2871-038		US 287 Passing Lanes Springfi	03/05/20	10.00	100.00	73.88	90.00
SHE 0703-461		I-70 and Kipling North Phase	03/26/20	5.00	100.00	163.00	140.00
		WEIGHTED AVERAGE FOR THE FIRST QUARTER		105.00	124.00	107.34	91.52

PROJECT NUMBER	ITEM NUMBER/ PROJECT LOCATION	ITEM DESCRIPTION/ PROJECT LOCATION	DATE LET	UNIT/ QUANTITY	ENGR. EST.	AVERAGE BID	AWARDED BID
===== 203-01100		Proof Rolling		Hour	=====		
CC0852-106		US-85 LOUVIERS TO MP 191.75	04/23/20	30.00	100.00	191.94	110.00
FBR0852-108		US-85 BETWEEN LOUVIERS AND MP					
FSA1602-159		US 160 AND SH 17 INTERSECTION	04/30/20	12.00	150.00	119.67	112.00
NHPP0253-276		I-25 EXPRESS LANES SEGMENT 5	05/15/20	20.00	127.00	136.10	136.10
		WEIGHTED AVERAGE FOR THE SECOND QUARTER		62.00	118.39	179.37	118.81
		WEIGHTED AVERAGE FOR THE YEAR		167.00	121.92	142.24	101.65
===== 203-01140		Rolling		Hour	=====		
NHPP0171-105		SH 17 MP 84.5 to US 285 & SH	03/05/20	70.00	100.00	106.67	100.01
NHPP145A-080		SH 145 Keystone-Placerville R	03/05/20	20.00	125.00	82.00	82.00
		WEIGHTED AVERAGE FOR THE FIRST QUARTER		90.00	105.56	104.52	96.01
NHPP1602-169		US 160 WC TUNNEL EAST RESURFA	04/02/20	40.00	150.00	100.30	123.28
SFTY2254-091		225 Ramp Improvements	04/09/20	10.00	200.00	137.50	155.00
FSA1602-159		US 160 AND SH 17 INTERSECTION	04/30/20	16.00	90.00	126.67	119.00
		WEIGHTED AVERAGE FOR THE SECOND QUARTER		66.00	143.03	110.99	127.05
		WEIGHTED AVERAGE FOR THE YEAR		156.00	121.41	107.43	109.14
===== 203-01500		Blading		Hour	=====		
STA0142-066		SH 14 New Raymer West	01/09/20	100.00	143.00	153.75	105.00
FSA0341-097		US 34 & MACGREGOR INTERSECTIO	01/09/20	10.00	150.00	110.00	110.00
NHPP0343-041		I-76 & US 34 FT. MORGAN AREA	01/09/20	90.00	140.00	191.10	190.00
BR0343-040		US 34 REPUBLICAN RIVER BRIDGE	01/16/20	50.00	150.00	144.41	130.00
FBR0343-043		US 34 D-28-P STRUCTURE REPLAC					
STA006A-067		SH 6 Merino to Atwood	01/16/20	200.00	160.00	120.01	100.00
PWQM240-172		El Paso County, north Colorad	01/23/20	8.00	150.00	271.50	333.00
NHPP4701-134		C-470 NOISE WALL WEST OF LUCE	02/06/20	10.00	150.00	159.60	108.00
STR116A-001		SH 116 A Surface Treatment Pr	02/13/20	110.00	150.00	144.19	140.00
STA069A-033		SH69 MP 58.7 TO 71.58	02/13/20	40.00	145.00	152.70	135.00
STR0101-027		SH 10 Overlay La Junta West	02/27/20	100.00	150.00	109.29	125.00

PROJECT NUMBER	ITEM NUMBER/ PROJECT LOCATION	ITEM DESCRIPTION/ PROJECT LOCATION	DATE LET	UNIT/ QUANTITY	ENGR. EST.	AVERAGE BID	AWARDED BID
===== 203-01500 Blading Hour =====							
NHPP0171-105		SH 17 MP 84.5 to US 285 & SH	03/05/20	90.00	150.00	115.00	110.01
C0641-106		SH 64 Meeker West Rural Resur	03/05/20	20.00	180.00	107.00	95.00
NHPP145A-080		SH 145 Keystone-Placerville R	03/05/20	20.00	125.00	93.00	93.00
STR2871-038		US 287 Passing Lanes Springfi	03/05/20	50.00	150.00	77.33	90.00
BR025A-046		K-18-U ON I-25 AT MP112 BRIDG	03/05/20	20.00	155.00	155.62	154.34
NHPP0091-044		SH 9 FRISCO MAIN ST TO IRON S	03/05/20	40.00	150.00	168.33	230.00
NH050A-034		US50A PUEBLO WEST PURCELL INT	03/26/20	104.00	150.00	165.63	150.00
WEIGHTED AVERAGE FOR THE FIRST QUARTER				1,062.00	150.38	145.50	130.22
NHPP1602-169		US 160 WC TUNNEL EAST RESURFA	04/02/20	40.00	150.00	117.12	117.87
STR092A-030		SH92 MP 31.748-48.5,DELTA AND	04/02/20	20.00	140.00	130.50	120.00
IM0761-226		I76/SH52 Interchange	04/02/20	40.00	150.00	144.20	105.00
STA340A-021		SH340 MP 6-6.76 MESA COUNTY	04/02/20	20.00	150.00	96.67	30.00
STR0341-101		SH 34 North of Grandby Resurf	04/02/20	40.00	150.00	134.37	119.00
IM0252-473		I-25 CABLE BARRIER PHASE IV	04/09/20	30.00	100.00	90.00	100.00
SFTY2254-091		225 Ramp Improvements	04/09/20	30.00	200.00	172.50	175.00
CC0852-106		US-85 LOUVIERS TO MP 191.75	04/23/20	100.00	175.00	176.96	130.00
FBR0852-108		US-85 BETWEEN LOUVIERS AND MP					
FSA1602-159		US 160 AND SH 17 INTERSECTION	04/30/20	16.00	180.00	169.00	159.00
C0853-112		US85 & WCR98 INTERSECTION IMP	05/07/20	40.00	150.00	149.75	115.00
FBR0343-042		US 34 D-27-G STRUCTURE REPLAC	05/07/20	25.00	150.00	136.19	110.00
NHPP0253-276		I-25 EXPRESS LANES SEGMENT 5	05/15/20	40.00	214.00	237.53	237.53
NH050A-035		US 50A Pueblo Regional Pond	05/28/20	50.00	160.00	137.38	150.00
NH050A-037		US 50A Pueblo Regional Pond					
WEIGHTED AVERAGE FOR THE SECOND QUARTER				491.00	161.89	151.32	132.02
WEIGHTED AVERAGE FOR THE YEAR				1,553.00	154.02	147.92	130.79
===== 203-01510 Backhoe Hour =====							
PWQM240-172		El Paso County, north Colorad	01/23/20	8.00	125.00	211.50	183.00
STR012A-050		CULVERT REPAIR I-25 AND US 35	01/30/20	40.00	135.00	210.00	210.00
STA0703-443		I-70 EJMT TUNNELS PAVING	02/06/20	4.00	150.00	254.55	339.60
NHPP0702-359		I-70 No Name Tunnel Lighting	02/27/20	50.00	150.00	123.50	115.00
C0641-106		SH 64 Meeker West Rural Resur	03/05/20	20.00	220.00	94.00	78.00
BR025A-046		K-18-U ON I-25 AT MP112 BRIDG	03/05/20	20.00	125.00	125.85	120.94
NHPP0091-044		SH 9 FRISCO MAIN ST TO IRON S	03/05/20	40.00	150.00	144.83	240.00
WEIGHTED AVERAGE FOR THE FIRST QUARTER				182.00	150.55	137.02	167.86
STR092A-030		SH92 MP 31.748-48.5,DELTA AND	04/02/20	10.00	150.00	87.50	81.00

PROJECT NUMBER	ITEM NUMBER/ PROJECT LOCATION	ITEM DESCRIPTION/ PROJECT LOCATION	DATE LET	UNIT/ QUANTITY	ENGR. EST.	AVERAGE BID	AWARDED BID
===== 203-01510 Backhoe Hour =====							
IM0252-473		I-25 CABLE BARRIER PHASE IV	04/09/20	10.00	50.00	75.00	100.00
SFTY2254-091		225 Ramp Improvements	04/09/20	30.00	200.00	192.50	160.00
NHPP0253-276		I-25 EXPRESS LANES SEGMENT 5	05/15/20	40.00	219.00	231.52	231.52
NH050A-035		US 50A Pueblo Regional Pond	05/28/20	50.00	125.00	110.81	75.00
NH050A-037		US 50A Pueblo Regional Pond					
IM025A-048		Northbound I-25 bridge at Exi	05/28/20	10.00	140.00	174.53	130.00
	WEIGHTED AVERAGE FOR THE SECOND QUARTER			150.00	162.73	129.16	139.47
	WEIGHTED AVERAGE FOR THE YEAR			332.00	156.05	133.07	155.04
===== 203-01550 Dozing Hour =====							
FSA0341-097		US 34 & MACGREGOR INTERSECTIO	01/09/20	10.00	175.00	150.00	150.00
NHPP0343-041		I-76 & US 34 FT. MORGAN AREA	01/09/20	90.00	150.00	197.99	210.00
BR0343-040		US 34 REPUBLICAN RIVER BRIDGE	01/16/20	20.00	160.00	162.97	140.00
FBR0343-043		US 34 D-28-P STRUCTURE REPLAC					
PWQM240-172		El Paso County, north Colorad	01/23/20	8.00	150.00	320.00	350.00
NH050A-034		US50A PUEBLO WEST PURCELL INT	03/26/20	104.00	150.00	175.00	150.00
	WEIGHTED AVERAGE FOR THE FIRST QUARTER			232.00	151.94	180.48	179.31
IM0761-226		I76/SH52 Interchange	04/02/20	40.00	160.00	157.17	105.00
IM0252-473		I-25 CABLE BARRIER PHASE IV	04/09/20	10.00	100.00	90.00	100.00
SFTY2254-091		225 Ramp Improvements	04/09/20	30.00	200.00	202.50	180.00
CC0852-106		US-85 LOUVIERS TO MP 191.75	04/23/20	100.00	160.00	193.14	175.00
FBR0852-108		US-85 BETWEEN LOUVIERS AND MP					
FBR0343-042		US 34 D-27-G STRUCTURE REPLAC	05/07/20	10.00	160.00	156.42	110.00
NHPP0253-276		I-25 EXPRESS LANES SEGMENT 5	05/15/20	40.00	154.00	283.66	283.66
NH050A-035		US 50A Pueblo Regional Pond	05/28/20	50.00	180.00	160.94	150.00
NH050A-037		US 50A Pueblo Regional Pond					
	WEIGHTED AVERAGE FOR THE SECOND QUARTER			280.00	164.86	178.86	171.59
	WEIGHTED AVERAGE FOR THE YEAR			512.00	159.00	179.54	175.09
===== 203-01565 Hydraulic Excavator Hour =====							
FSA1602-159		US 160 AND SH 17 INTERSECTION	04/30/20	10.00	180.00	166.33	179.00
	WEIGHTED AVERAGE FOR THE SECOND QUARTER			10.00	180.00	166.33	179.00
	WEIGHTED AVERAGE FOR THE YEAR			10.00	180.00	166.33	179.00

PROJECT NUMBER	ITEM NUMBER/ PROJECT LOCATION	ITEM DESCRIPTION/ PROJECT LOCATION	DATE LET	UNIT/ QUANTITY	ENGR. EST.	AVERAGE BID	AWARDED BID
===== 203-01580		Truck		Hour =====			
STR0341-101		SH 34 North of Grandby Resurf	04/02/20	40.00	125.00	125.75	123.00
		WEIGHTED AVERAGE FOR THE SECOND QUARTER		40.00	125.00	125.75	123.00
		WEIGHTED AVERAGE FOR THE YEAR		40.00	125.00	125.75	123.00
===== 203-01582		Truck (Dump)		Hour =====			
STR131A-038		SH 131 MP 51.95-55.73, ROUTT	01/16/20	20.00	155.00	104.00	123.00
NH 0503-093		US50 WEST OF TEXAS CREEK MP 2	01/23/20	10.00	120.00	128.76	157.52
C0641-106		SH 64 Meeker West Rural Resur	03/05/20	20.00	200.00	104.00	85.00
NHPP145A-080		SH 145 Keystone-Placerville R	03/05/20	10.00	150.00	90.00	90.00
		WEIGHTED AVERAGE FOR THE FIRST QUARTER		60.00	163.33	107.23	110.59
SFTY2254-091		225 Ramp Improvements	04/09/20	20.00	200.00	130.00	150.00
		WEIGHTED AVERAGE FOR THE SECOND QUARTER		20.00	200.00	130.00	150.00
		WEIGHTED AVERAGE FOR THE YEAR		80.00	172.50	113.30	120.44
===== 203-01590		Front End Loader (Rubber)		Hour =====			
NH 0503-093		US50 WEST OF TEXAS CREEK MP 2	01/23/20	25.00	120.00	190.01	210.02
		WEIGHTED AVERAGE FOR THE FIRST QUARTER		25.00	120.00	190.01	210.02
NHPP0402-098		US 40 CHIP SEAL MP 126 TO MP	05/14/20	10.00	160.00	105.00	120.00
		WEIGHTED AVERAGE FOR THE SECOND QUARTER		10.00	160.00	105.00	120.00
		WEIGHTED AVERAGE FOR THE YEAR		35.00	131.43	158.13	184.30
===== 203-01594		Combination Loader		Hour =====			
FSA0341-097		US 34 & MACGREGOR INTERSECTIO	01/09/20	10.00	130.00	100.00	100.00

PROJECT NUMBER	ITEM NUMBER/ PROJECT LOCATION	ITEM DESCRIPTION/ PROJECT LOCATION	DATE LET	UNIT/ QUANTITY	ENGR. EST.	AVERAGE BID	AWARDED BID
===== 203-01594							
		Combination Loader		Hour			
NHPP0343-041		I-76 & US 34 FT. MORGAN AREA	01/09/20	10.00	120.00	176.11	185.00
PWQM240-172		El Paso County, north Colorad	01/23/20	8.00	150.00	140.00	110.00
STR141A-044		SH 141 AND SH 145, FROM SLICK	01/30/20	10.00	200.00	133.06	80.00
NHPP145A-080		SH 145 Keystone-Placerville R	03/05/20	20.00	122.00	99.00	99.00
NHPP0091-044		SH 9 FRISCO MAIN ST TO IRON S	03/05/20	40.00	150.00	131.67	110.00
SHE 0703-461		I-70 and Kipling North Phase	03/26/20	20.00	125.00	141.00	150.00
WEIGHTED AVERAGE FOR THE FIRST QUARTER				118.00	141.02	136.00	117.88
IM0761-226		I76/SH52 Interchange	04/02/20	40.00	120.00	109.94	105.00
STA340A-021		SH340 MP 6-6.76 MESA COUNTY	04/02/20	22.00	130.00	83.33	30.00
STR0341-101		SH 34 North of Grandby Resurf	04/02/20	40.00	125.00	120.51	78.80
IM0252-473		I-25 CABLE BARRIER PHASE IV	04/09/20	10.00	100.00	75.00	100.00
FSA1602-159		US 160 AND SH 17 INTERSECTION	04/30/20	16.00	120.00	134.33	112.00
NHPP0402-098		US 40 CHIP SEAL MP 126 TO MP	05/14/20	10.00	105.00	98.33	100.00
NHPP0253-276		I-25 EXPRESS LANES SEGMENT 5	05/15/20	40.00	176.00	183.00	183.00
WEIGHTED AVERAGE FOR THE SECOND QUARTER				178.00	132.98	114.57	107.44
WEIGHTED AVERAGE FOR THE YEAR				296.00	136.18	122.06	111.60
===== 203-01597							
		Potholing		Hour			
FSA0253-262		I-25 SB BOTTLENECK I-76 TO I-	01/09/20	50.00	250.00	204.04	190.00
NHPP0253-265		I-25 AT ERIE PARKWAY ON AND O	01/09/20	16.00	300.00	281.67	300.00
NHPP0343-041		I-76 & US 34 FT. MORGAN AREA	01/09/20	50.00	250.00	226.33	264.00
BR0343-040		US 34 REPUBLICAN RIVER BRIDGE	01/16/20	20.00	250.00	277.95	250.00
FBR0343-043		US 34 D-28-P STRUCTURE REPLAC					
STR131A-038		SH 131 MP 51.95-55.73, ROUTT	01/16/20	40.00	400.00	310.00	260.00
NH 0503-093		US50 WEST OF TEXAS CREEK MP 2	01/23/20	20.00	250.00	307.52	315.03
PWQM240-172		El Paso County, north Colorad	01/23/20	40.00	250.00	310.00	290.00
STR012A-050		CULVERT REPAIR I-25 AND US 35	01/30/20	10.00	300.00	670.00	670.00
STR141A-044		SH 141 AND SH 145, FROM SLICK	01/30/20	8.00	500.00	389.20	500.00
ITS0761-231		ITS FIBER AND CAMERAS ON I-76	02/06/20	200.00	250.00	169.00	170.00
NHPP4701-134		C-470 NOISE WALL WEST OF LUCE	02/06/20	20.00	250.00	255.60	238.00
FSA2873-194		US 287 Longmont Intersection	02/13/20	60.00	210.00	336.67	300.00
STA069A-033		SH69 MP 58.7 TO 71.58	02/13/20	20.00	260.00	293.00	300.00
STR0101-027		SH 10 Overlay La Junta West	02/27/20	10.00	200.00	256.83	240.00
NHPP0702-359		I-70 No Name Tunnel Lighting	02/27/20	60.00	460.00	266.36	275.00
C0402-094		US 40 GRAND COUNTY SIGNAL REP	02/27/20	100.00	300.00	212.50	325.00
NH0242-085		US 24 M.P. 291.38 to M.P. 296	02/27/20	40.00	235.00	304.69	275.00
NHPP0171-105		SH 17 MP 84.5 to US 285 & SH	03/05/20	120.00	175.00	120.00	120.01
C0641-106		SH 64 Meeker West Rural Resur	03/05/20	80.00	400.00	287.50	300.00

PROJECT NUMBER	ITEM NUMBER/ PROJECT LOCATION	ITEM DESCRIPTION/ PROJECT LOCATION	DATE LET	UNIT/ QUANTITY	ENGR. EST.	AVERAGE BID	AWARDED BID
===== 203-01597 Potholing Hour =====							
NHPP145A-080	SH 145 Keystone-Placerville R	SH 145 Keystone-Placerville R	03/05/20	40.00	400.00	385.00	385.00
STR2871-038	US 287 Passing Lanes Springfi	US 287 Passing Lanes Springfi	03/05/20	10.00	200.00	406.08	462.15
STRR300-249	Grand and Jackson Counties AD	Grand and Jackson Counties AD	03/05/20	40.00	250.00	410.00	380.00
NHPP0091-044	SH 9 FRISCO MAIN ST TO IRON S	SH 9 FRISCO MAIN ST TO IRON S	03/05/20	80.00	250.00	393.33	270.00
NH050A-034	US50A PUEBLO WEST PURCELL INT	US50A PUEBLO WEST PURCELL INT	03/26/20	100.00	260.00	313.75	300.00
HPP 0501-067	US 50 AND SH 92 DELTA INTERSE	US 50 AND SH 92 DELTA INTERSE	03/26/20	80.00	250.00	292.60	279.00
SHE 0703-461	I-70 and Kipling North Phase	I-70 and Kipling North Phase	03/26/20	40.00	250.00	344.20	350.00
WEIGHTED AVERAGE FOR THE FIRST QUARTER				1,354.00	274.45	268.29	264.55
NHPP1602-169	US 160 WC TUNNEL EAST RESURFA	US 160 WC TUNNEL EAST RESURFA	04/02/20	40.00	400.00	380.80	676.79
STR092A-030	SH92 MP 31.748-48.5,DELTA AND	SH92 MP 31.748-48.5,DELTA AND	04/02/20	100.00	300.00	414.50	450.00
IM0761-226	I76/SH52 Interchange	I76/SH52 Interchange	04/02/20	200.00	250.00	264.84	196.10
STA340A-021	SH340 MP 6-6.76 MESA COUNTY	SH340 MP 6-6.76 MESA COUNTY	04/02/20	40.00	310.00	325.00	310.00
STR0341-101	SH 34 North of Grandby Resurf	SH 34 North of Grandby Resurf	04/02/20	40.00	300.00	293.56	314.00
IM0252-473	I-25 CABLE BARRIER PHASE IV	I-25 CABLE BARRIER PHASE IV	04/09/20	10.00	260.00	231.25	312.50
SHER100-339	WWD TRAFFIC CONTROL ENHANCEME	WWD TRAFFIC CONTROL ENHANCEME	04/09/20	150.00	300.00	275.00	275.00
SFTY2254-091	225 Ramp Improvements	225 Ramp Improvements	04/09/20	60.00	300.00	295.00	240.00
CC0852-106	US-85 LOUVIERS TO MP 191.75	US-85 LOUVIERS TO MP 191.75	04/23/20	275.00	270.00	260.47	203.50
FBR0852-108	US-85 BETWEEN LOUVIERS AND MP	US-85 BETWEEN LOUVIERS AND MP					
C1211-090	SH-121 & 29th Ave / SH-121 &	SH-121 & 29th Ave / SH-121 &	04/23/20	80.00	240.00	256.67	185.00
C1601-082	Hawkins Signal and Curb Ramps	Hawkins Signal and Curb Ramps	04/30/20	40.00	300.00	395.00	500.00
FSA1602-159	US 160 AND SH 17 INTERSECTION	US 160 AND SH 17 INTERSECTION	04/30/20	60.00	300.00	352.67	286.00
C0853-112	US85 & WCR98 INTERSECTION IMP	US85 & WCR98 INTERSECTION IMP	05/07/20	20.00	230.00	254.38	235.00
NHPPR100-303	LONG MAST ARM SIGNALS PROJECT	LONG MAST ARM SIGNALS PROJECT	05/07/20	260.00	230.00	223.33	175.00
FBR0343-042	US 34 D-27-G STRUCTURE REPLAC	US 34 D-27-G STRUCTURE REPLAC	05/07/20	8.00	275.00	355.53	275.00
ITS SW02-304	ITS FIBER TO STATE BUILDINGS	ITS FIBER TO STATE BUILDINGS	05/14/20	250.00	200.00	214.75	212.00
NHPP0402-098	US 40 CHIP SEAL MP 126 TO MP	US 40 CHIP SEAL MP 126 TO MP	05/14/20	30.00	230.00	158.33	250.00
NHPP0253-276	I-25 EXPRESS LANES SEGMENT 5	I-25 EXPRESS LANES SEGMENT 5	05/15/20	80.00	360.00	368.59	368.59
ITS SW02-303	R1: US 285, SH 83 R2: SH 83,	R1: US 285, SH 83 R2: SH 83,	05/28/20	250.00	200.00	155.70	1.00
ITSSW01-719	FY 20 ITS CAPITAL REPLACEMENT	FY 20 ITS CAPITAL REPLACEMENT	06/11/20	80.00	275.00	125.00	50.00
FSAR400-356	FY 20 SIGNAL POLE REPLACEMENT	FY 20 SIGNAL POLE REPLACEMENT	06/11/20	20.00	350.00	261.67	225.00
SHE016A-043	SH 21 & 16 SIGNALS PROJECT	SH 21 & 16 SIGNALS PROJECT	06/18/20	175.00	250.00	173.60	175.00
WEIGHTED AVERAGE FOR THE SECOND QUARTER				2,268.00	257.72	239.96	213.72
WEIGHTED AVERAGE FOR THE YEAR				3,622.00	263.97	249.57	232.72
===== 203-01620 Sweeping Hour =====							
STR2871-038	US 287 Passing Lanes Springfi	US 287 Passing Lanes Springfi	03/05/20	10.00	100.00	129.25	58.50
WEIGHTED AVERAGE FOR THE FIRST QUARTER				10.00	100.00	129.25	58.50

PROJECT NUMBER	ITEM NUMBER/ PROJECT LOCATION	ITEM DESCRIPTION/ PROJECT LOCATION	DATE LET	UNIT/ QUANTITY	ENGR. EST.	AVERAGE BID	AWARDED BID
=====	203-01620	Sweeping		Hour	=====		
MTCER200-265		Pueblo	05/28/20	100.00	150.00	143.75	50.00
		WEIGHTED AVERAGE FOR THE SECOND QUARTER		100.00	150.00	143.75	50.00
		WEIGHTED AVERAGE FOR THE YEAR		110.00	145.45	143.06	50.77
=====	203-01622	Sweeping (With Pickup Broom)		Hour	=====		
NH0242-085		US 24 M.P. 291.38 to M.P. 296	02/27/20	40.00	170.00	242.10	350.00
		WEIGHTED AVERAGE FOR THE FIRST QUARTER		40.00	170.00	242.10	350.00
		WEIGHTED AVERAGE FOR THE YEAR		40.00	170.00	242.10	350.00
=====	203-02330	Laborer		Hour	=====		
STR131A-038		SH 131 MP 51.95-55.73, ROUTT	01/16/20	40.00	45.00	36.75	38.50
NH 0503-093		US50 WEST OF TEXAS CREEK MP 2	01/23/20	30.00	50.00	56.26	52.51
PWQM240-172		El Paso County, north Colorad	01/23/20	24.00	55.00	42.00	44.00
STR012A-050		CULVERT REPAIR I-25 AND US 35	01/30/20	20.00	45.00	60.00	60.00
STR141A-044		SH 141 AND SH 145, FROM SLICK	01/30/20	20.00	75.00	58.53	35.00
STA0703-443		I-70 EJMT TUNNELS PAVING	02/06/20	6.00	80.00	129.94	194.88
NHPP0702-359		I-70 No Name Tunnel Lighting	02/27/20	50.00	60.00	85.84	60.00
NHPP0171-105		SH 17 MP 84.5 to US 285 & SH	03/05/20	20.00	50.00	51.00	50.00
C0641-106		SH 64 Meeker West Rural Resur	03/05/20	10.00	40.00	36.00	37.00
NHPP145A-080		SH 145 Keystone-Placerville R	03/05/20	40.00	50.00	32.00	32.00
BR025A-046		K-18-U ON I-25 AT MP112 BRIDG	03/05/20	40.00	55.00	45.10	62.71
NHPP0091-044		SH 9 FRISCO MAIN ST TO IRON S	03/05/20	40.00	80.00	48.78	62.00
		WEIGHTED AVERAGE FOR THE FIRST QUARTER		340.00	56.76	55.44	52.59
NHPP1602-169		US 160 WC TUNNEL EAST RESURFA	04/02/20	24.00	80.00	67.31	90.17
STA340A-021		SH340 MP 6-6.76 MESA COUNTY	04/02/20	60.00	50.00	33.33	20.00
STR0341-101		SH 34 North of Grandby Resurf	04/02/20	40.00	60.00	57.06	35.00
IM0252-473		I-25 CABLE BARRIER PHASE IV	04/09/20	60.00	50.00	41.88	43.75
SFTY2254-091		225 Ramp Improvements	04/09/20	40.00	65.00	62.00	60.00
CC0852-106		US-85 LOUVIERS TO MP 191.75	04/23/20	80.00	55.00	52.80	55.00

PROJECT NUMBER	ITEM NUMBER/ PROJECT LOCATION	ITEM DESCRIPTION/ PROJECT LOCATION	DATE LET	UNIT/ QUANTITY	ENGR. EST.	AVERAGE BID	AWARDED BID
===== 203-02330		Laborer		Hour =====			
FBR0852-108		US-85 BETWEEN LOUVIERS AND MP					
C1601-082		Hawkins Signal and Curb Ramps	04/30/20	20.00	50.00	56.33	71.00
FSA1602-159		US 160 AND SH 17 INTERSECTION	04/30/20	24.00	30.00	57.67	79.00
NHPP0253-276		I-25 EXPRESS LANES SEGMENT 5	05/15/20	40.00	46.00	45.53	45.53
IM025A-048		Northbound I-25 bridge at Exi	05/28/20	75.00	52.00	66.98	45.00
		WEIGHTED AVERAGE FOR THE SECOND QUARTER		463.00	53.52	53.47	49.03
		WEIGHTED AVERAGE FOR THE YEAR		803.00	54.89	54.23	50.54
===== 206-00000		Str Excav		Cubic Yard =====			
NHPP0343-041		I-76 & US 34 FT. MORGAN AREA	01/09/20	10.00	50.00	299.94	599.00
BR0343-040		US 34 REPUBLICAN RIVER BRIDGE	01/16/20	1,585.00	20.00	19.56	15.00
FBR0343-043		US 34 D-28-P STRUCTURE REPLAC					
NHPP4701-134		C-470 NOISE WALL WEST OF LUCE	02/06/20	429.00	60.00	33.70	20.00
NHPP145A-080		SH 145 Keystone-Placerville R	03/05/20	338.00	40.00	58.00	58.00
BR025A-046		K-18-U ON I-25 AT MP112 BRIDG	03/05/20	968.00	30.00	22.84	16.23
NHPP0091-044		SH 9 FRISCO MAIN ST TO IRON S	03/05/20	2,942.00	30.00	24.92	30.00
NH050A-034		US50A PUEBLO WEST PURCELL INT	03/26/20	636.00	30.00	23.88	25.00
		WEIGHTED AVERAGE FOR THE FIRST QUARTER		6,908.00	30.09	23.94	25.74
IM0761-226		I76/SH52 Interchange	04/02/20	335.00	25.00	31.44	14.00
STA340A-021		SH340 MP 6-6.76 MESA COUNTY	04/02/20	153.00	30.00	66.33	58.00
SFTY2254-091		225 Ramp Improvements	04/09/20	461.00	30.00	57.50	74.00
CC0852-106		US-85 LOUVIERS TO MP 191.75	04/23/20	20,532.00	20.00	12.16	8.13
FBR0852-108		US-85 BETWEEN LOUVIERS AND MP					
FBR0343-042		US 34 D-27-G STRUCTURE REPLAC	05/07/20	1,040.00	22.00	21.30	30.00
NHPP0253-276		I-25 EXPRESS LANES SEGMENT 5	05/15/20	1,220.00	36.00	42.41	42.41
		WEIGHTED AVERAGE FOR THE SECOND QUARTER		23,741.00	21.24	13.47	12.53
		WEIGHTED AVERAGE FOR THE YEAR		30,649.00	23.23	15.09	15.51
===== 206-00050		Str Bkfl (Spec)		Cubic Yard =====			
NHPP145A-080		SH 145 Keystone-Placerville R	03/05/20	4.00	80.00	240.00	240.00
		WEIGHTED AVERAGE FOR THE FIRST QUARTER		4.00	80.00	240.00	240.00
		WEIGHTED AVERAGE FOR THE YEAR		4.00	80.00	240.00	240.00

PROJECT NUMBER	ITEM NUMBER/ PROJECT LOCATION	ITEM DESCRIPTION/ PROJECT LOCATION	DATE LET	UNIT/ QUANTITY	ENGR. EST.	AVERAGE BID	AWARDED BID
=====	206-00060	Str Bkfl (Spec) (Flow-Fill)		Cubic Yard	=====		
NHPP0343-041		I-76 & US 34 FT. MORGAN AREA	01/09/20	2.00	417.00	1566.20	2539.00
NH050A-034		US50A PUEBLO WEST PURCELL INT	03/26/20	445.00	180.00	238.64	160.00
		WEIGHTED AVERAGE FOR THE FIRST QUARTER		447.00	181.06	240.87	170.64
		WEIGHTED AVERAGE FOR THE YEAR		447.00	181.06	240.87	170.64
=====	206-00065	Str Bkfl (Flow-Fill)		Cubic Yard	=====		
NHPP0343-041		I-76 & US 34 FT. MORGAN AREA	01/09/20	1,357.00	200.00	220.38	212.00
STA059A-036		SH 59 SEIBERT TO COPE	02/06/20	2.00	500.00	715.00	730.00
NHPP145A-080		SH 145 Keystone-Placerville R	03/05/20	46.00	250.00	236.50	236.50
NHPP0091-044		SH 9 FRISCO MAIN ST TO IRON S	03/05/20	35.00	350.00	311.67	270.00
		WEIGHTED AVERAGE FOR THE FIRST QUARTER		1,440.00	205.66	223.29	214.91
IM0761-226		I76/SH52 Interchange	04/02/20	170.00	200.00	213.60	131.00
STA340A-021		SH340 MP 6-6.76 MESA COUNTY	04/02/20	163.00	40.00	124.00	90.00
ITSSW01-719		FY 20 ITS CAPITAL REPLACEMENT	06/11/20	75.00	400.00	200.00	150.00
		WEIGHTED AVERAGE FOR THE SECOND QUARTER		408.00	172.84	188.53	118.11
		WEIGHTED AVERAGE FOR THE YEAR		1,848.00	198.41	212.79	193.54
=====	206-00066	Str Bkfl (FF Ash)		Cubic Yard	=====		
NHPP 0852-116		US85:HAMPDEN TO FLORIDA-RESUR	02/06/20	727.00	125.00	325.00	300.00
		WEIGHTED AVERAGE FOR THE FIRST QUARTER		727.00	125.00	325.00	300.00
		WEIGHTED AVERAGE FOR THE YEAR		727.00	125.00	325.00	300.00
=====	206-00100	Str Bkfl (CL 1)		Cubic Yard	=====		
BR0343-040		US 34 REPUBLICAN RIVER BRIDGE	01/16/20	1,220.00	40.00	82.59	64.00
FBR0343-043		US 34 D-28-P STRUCTURE REPLAC					
NHPP4701-134		C-470 NOISE WALL WEST OF LUCE	02/06/20	302.00	60.00	73.40	63.00

PROJECT NUMBER	ITEM NUMBER/ PROJECT LOCATION	ITEM DESCRIPTION/ PROJECT LOCATION	DATE LET	UNIT/ QUANTITY	ENGR. EST.	AVERAGE BID	AWARDED BID
===== 206-00100		Str Bkfl (CL 1)		Cubic Yard	=====	=====	=====
STR116A-001		SH 116 A Surface Treatment Pr	02/13/20	40.00	123.00	78.52	50.00
NHPP0702-359		I-70 No Name Tunnel Lighting	02/27/20	10.00	100.00	485.73	310.00
NHPP145A-080		SH 145 Keystone-Placerville R	03/05/20	78.00	60.00	83.00	83.00
NHPP0091-044		SH 9 FRISCO MAIN ST TO IRON S	03/05/20	2,208.00	60.00	61.72	60.00
NH050A-034		US50A PUEBLO WEST PURCELL INT	03/26/20	15,652.00	45.00	27.70	23.00
		WEIGHTED AVERAGE FOR THE FIRST QUARTER		19,510.00	46.87	32.84	30.81
IM0761-226		I76/SH52 Interchange	04/02/20	70.00	225.00	71.86	68.90
SFTY2254-091		225 Ramp Improvements	04/09/20	301.00	50.00	104.00	135.00
CC0852-106		US-85 LOUVIERS TO MP 191.75	04/23/20	3,100.00	30.00	40.86	45.00
FBR0852-108		US-85 BETWEEN LOUVIERS AND MP					
FBR0343-042		US 34 D-27-G STRUCTURE REPLAC	05/07/20	555.00	80.00	82.69	63.00
NHPP0253-276		I-25 EXPRESS LANES SEGMENT 5	05/15/20	1,802.00	67.00	70.57	70.57
		WEIGHTED AVERAGE FOR THE SECOND QUARTER		5,828.00	49.58	50.51	59.56
		WEIGHTED AVERAGE FOR THE YEAR		25,338.00	47.49	36.17	37.42
===== 206-00200		Str Bkfl (CL 2)		Cubic Yard	=====	=====	=====
NHPP0343-041		I-76 & US 34 FT. MORGAN AREA	01/09/20	2.00	41.00	493.95	846.00
BR0343-040		US 34 REPUBLICAN RIVER BRIDGE	01/16/20	240.00	25.00	32.88	9.00
BR0343-043		US 34 D-28-P STRUCTURE REPLAC					
NHPP4701-134		C-470 NOISE WALL WEST OF LUCE	02/06/20	192.00	75.00	50.00	40.00
BR025A-046		K-18-U ON I-25 AT MP112 BRIDG	03/05/20	400.00	40.00	38.98	17.90
NH050A-034		US50A PUEBLO WEST PURCELL INT	03/26/20	433.00	55.00	29.35	22.00
		WEIGHTED AVERAGE FOR THE FIRST QUARTER		1,267.00	47.59	35.65	22.27
IM0761-226		I76/SH52 Interchange	04/02/20	138.00	25.00	48.65	10.00
CC0852-106		US-85 LOUVIERS TO MP 191.75	04/23/20	16,435.00	35.00	19.70	22.25
FBR0852-108		US-85 BETWEEN LOUVIERS AND MP					
FBR0343-042		US 34 D-27-G STRUCTURE REPLAC	05/07/20	60.00	30.00	27.35	7.50
NHPP0253-276		I-25 EXPRESS LANES SEGMENT 5	05/15/20	207.00	66.00	38.37	38.37
		WEIGHTED AVERAGE FOR THE SECOND QUARTER		16,840.00	35.28	19.97	22.30
		WEIGHTED AVERAGE FOR THE YEAR		18,107.00	36.14	20.92	22.29
===== 206-00360		Mechanical Reinforcement of Soil		Cubic Yard	=====	=====	=====
BR0343-040		US 34 REPUBLICAN RIVER BRIDGE	01/16/20	1,220.00	27.00	20.67	13.00

PROJECT NUMBER	ITEM NUMBER/ PROJECT LOCATION	ITEM DESCRIPTION/ PROJECT LOCATION	DATE LET	UNIT/ QUANTITY	ENGR. EST.	AVERAGE BID	AWARDED BID
=====	206-00360	Mechanical Reinforcement of Soil		Cubic Yard	=====		
FBR0343-043		US 34 D-28-P STRUCTURE REPLAC					
NHPP0091-044		SH 9 FRISCO MAIN ST TO IRON S	03/05/20	290.00	50.00	65.05	120.00
NH050A-034		US50A PUEBLO WEST PURCELL INT	03/26/20	8,935.00	26.00	17.59	12.00
	WEIGHTED AVERAGE FOR THE FIRST QUARTER			10,445.00	26.78	18.39	15.12
IM0761-226		I76/SH52 Interchange	04/02/20	70.00	20.00	43.36	21.20
CC0852-106		US-85 LOUVIERS TO MP 191.75	04/23/20	13,003.00	19.00	18.23	18.99
FBR0852-108		US-85 BETWEEN LOUVIERS AND MP					
FBR0343-042		US 34 D-27-G STRUCTURE REPLAC	05/07/20	555.00	28.00	26.20	7.50
NHPP0253-276		I-25 EXPRESS LANES SEGMENT 5	05/15/20	342.00	19.00	27.49	27.49
	WEIGHTED AVERAGE FOR THE SECOND QUARTER			13,970.00	19.36	18.73	18.75
	WEIGHTED AVERAGE FOR THE YEAR			24,415.00	22.54	18.59	17.20
=====	206-00505	Filter Matl (Spec)		Cubic Yard	=====		
NH050A-034		US50A PUEBLO WEST PURCELL INT	03/26/20	21,112.00	16.00	48.19	47.00
	WEIGHTED AVERAGE FOR THE FIRST QUARTER			21,112.00	16.00	48.19	47.00
	WEIGHTED AVERAGE FOR THE YEAR			21,112.00	16.00	48.19	47.00
=====	206-00510	Filter Matl (CL A)		Cubic Yard	=====		
NH050A-034		US50A PUEBLO WEST PURCELL INT	03/26/20	103.00	75.00	84.14	89.00
	WEIGHTED AVERAGE FOR THE FIRST QUARTER			103.00	75.00	84.14	89.00
IM0761-226		I76/SH52 Interchange	04/02/20	6.00	90.00	158.73	197.72
C0853-112		US85 & WCR98 INTERSECTION IMP	05/07/20	4.00	300.00	217.88	260.00
NHPP0253-276		I-25 EXPRESS LANES SEGMENT 5	05/15/20	58.00	259.00	134.83	134.83
	WEIGHTED AVERAGE FOR THE SECOND QUARTER			68.00	246.50	162.57	147.74
	WEIGHTED AVERAGE FOR THE YEAR			171.00	143.20	94.96	112.36
=====	206-00520	Filter Matl (CL B)		Cubic Yard	=====		
NHPP4701-134		C-470 NOISE WALL WEST OF LUCE	02/06/20	63.00	80.00	132.80	144.00

PROJECT NUMBER	ITEM NUMBER/ PROJECT LOCATION	ITEM DESCRIPTION/ PROJECT LOCATION	DATE LET	UNIT/ QUANTITY	ENGR. EST.	AVERAGE BID	AWARDED BID
===== 206-00520		Filter Matl (CL B)		Cubic Yard			
NH050A-034		US50A PUEBLO WEST PURCELL INT	03/26/20	30.00	55.00	120.47	128.00
	WEIGHTED AVERAGE FOR THE FIRST QUARTER			93.00	71.94	127.47	138.84
	WEIGHTED AVERAGE FOR THE YEAR			93.00	71.94	127.47	138.84
===== 206-00530		Filter Matl (CL C)		Cubic Yard			
SFTY2254-091		225 Ramp Improvements	04/09/20	96.00	150.00	152.50	165.00
	WEIGHTED AVERAGE FOR THE SECOND QUARTER			96.00	150.00	152.50	165.00
	WEIGHTED AVERAGE FOR THE YEAR			96.00	150.00	152.50	165.00
===== 206-01750		Shoring		LUMP SUM			
STA340A-021		SH340 MP 6-6.76 MESA COUNTY	04/02/20	1.00	15000.00	16033.33	24200.00
	WEIGHTED AVERAGE FOR THE SECOND QUARTER			1.00	15000.00	16033.33	24200.00
	WEIGHTED AVERAGE FOR THE YEAR			1.00	15000.00	16033.33	24200.00
===== 206-01781		Shoring (A 1)		LUMP SUM			
BR0343-040		US 34 REPUBLICAN RIVER BRIDGE	01/16/20	1.00	20000.00	42083.33	25000.00
FBR0343-043		US 34 D-28-P STRUCTURE REPLAC					
	WEIGHTED AVERAGE FOR THE FIRST QUARTER			1.00	20000.00	42083.33	25000.00
IM0761-226		I76/SH52 Interchange	04/02/20	1.00	16000.00	16323.53	14499.70
NHPP0253-276		I-25 EXPRESS LANES SEGMENT 5	05/15/20	1.00	26000.00	22978.46	22978.46
	WEIGHTED AVERAGE FOR THE SECOND QUARTER			2.00	21000.00	17155.40	18739.08
	WEIGHTED AVERAGE FOR THE YEAR			3.00	20666.67	27838.80	20826.05
===== 206-01782		Shoring (A 2)		LUMP SUM			
BR0343-040		US 34 REPUBLICAN RIVER BRIDGE	01/16/20	1.00	20000.00	46416.67	28000.00

PROJECT NUMBER	ITEM NUMBER/ PROJECT LOCATION	ITEM DESCRIPTION/ PROJECT LOCATION	DATE LET	UNIT/ QUANTITY	ENGR. EST.	AVERAGE BID	AWARDED BID
===== 206-01782		Shoring (A 2)		LUMP SUM	=====		
FBR0343-043		US 34 D-28-P STRUCTURE REPLAC					
	WEIGHTED AVERAGE FOR THE FIRST QUARTER			1.00	20000.00	46416.67	28000.00
IM0761-226		I76/SH52 Interchange	04/02/20	1.00	16000.00	15689.24	14499.70
NHPP0253-276		I-25 EXPRESS LANES SEGMENT 5	05/15/20	1.00	26000.00	22978.46	22978.46
	WEIGHTED AVERAGE FOR THE SECOND QUARTER			2.00	21000.00	16600.40	18739.08
	WEIGHTED AVERAGE FOR THE YEAR			3.00	20666.67	29378.80	21826.05
===== 206-01783		Shoring (A 3)		LUMP SUM	=====		
IM0761-226		I76/SH52 Interchange	04/02/20	1.00	6000.00	10991.43	6200.00
NHPP0253-276		I-25 EXPRESS LANES SEGMENT 5	05/15/20	1.00	22000.00	19348.96	19348.96
	WEIGHTED AVERAGE FOR THE SECOND QUARTER			2.00	14000.00	12036.12	12774.48
	WEIGHTED AVERAGE FOR THE YEAR			2.00	14000.00	12036.12	12774.48
===== 207-00205		Topsoil		Cubic Yard	=====		
FSA0341-097		US 34 & MACGREGOR INTERSECTIO	01/09/20	1,612.00	17.00	20.00	20.00
BR0343-040		US 34 REPUBLICAN RIVER BRIDGE	01/16/20	905.00	15.00	14.29	8.00
FBR0343-043		US 34 D-28-P STRUCTURE REPLAC					
PWQM240-172		El Paso County, north Colorad	01/23/20	3,765.00	20.00	54.50	62.00
STR116A-001		SH 116 A Surface Treatment Pr	02/13/20	135.00	92.00	47.67	33.00
STA069A-033		SH69 MP 58.7 TO 71.58	02/13/20	2,243.00	40.00	52.18	59.48
STR0101-027		SH 10 Overlay La Junta West	02/27/20	160.00	25.00	48.06	52.00
NHPP0171-105		SH 17 MP 84.5 to US 285 & SH	03/05/20	61,063.00	25.00	25.32	18.70
NHPP145A-080		SH 145 Keystone-Placerville R	03/05/20	46.00	150.00	140.00	140.00
STR2871-038		US 287 Passing Lanes Springfi	03/05/20	3,058.00	5.00	9.07	8.35
BR025A-046		K-18-U ON I-25 AT MP112 BRIDG	03/05/20	731.00	13.00	18.41	8.97
NHPP0091-044		SH 9 FRISCO MAIN ST TO IRON S	03/05/20	3,120.00	10.00	43.33	12.00
NH050A-034		US50A PUEBLO WEST PURCELL INT	03/26/20	13,982.00	8.00	27.62	16.00
	WEIGHTED AVERAGE FOR THE FIRST QUARTER			90,820.00	21.18	27.07	20.49
STA340A-021		SH340 MP 6-6.76 MESA COUNTY	04/02/20	451.00	30.00	28.67	45.00

PROJECT NUMBER	ITEM NUMBER/ PROJECT LOCATION	ITEM DESCRIPTION/ PROJECT LOCATION	DATE LET	UNIT/ QUANTITY	ENGR. EST.	AVERAGE BID	AWARDED BID
===== 207-00205 Topsoil Cubic Yard =====							
IM0252-473		I-25 CABLE BARRIER PHASE IV	04/09/20	1,838.00	10.00	15.00	12.50
SFTY2254-091		225 Ramp Improvements	04/09/20	915.00	25.00	51.50	51.00
CC0852-106		US-85 LOUVIERS TO MP 191.75	04/23/20	835.00	15.00	31.39	15.00
FBR0852-108		US-85 BETWEEN LOUVIERS AND MP					
C1211-090		SH-121 & 29th Ave / SH-121 &	04/23/20	50.00	12.00	91.33	126.00
C1601-082		Hawkins Signal and Curb Ramps	04/30/20	10.00	50.00	262.33	640.00
C0853-112		US85 & WCR98 INTERSECTION IMP	05/07/20	3,150.00	12.00	7.15	4.00
NHPP0253-276		I-25 EXPRESS LANES SEGMENT 5	05/15/20	13,750.00	8.20	8.55	8.55
NH050A-035		US 50A Pueblo Regional Pond	05/28/20	15,060.00	10.00	15.31	10.00
NH050A-037		US 50A Pueblo Regional Pond					
	WEIGHTED AVERAGE FOR THE SECOND QUARTER			36,059.00	10.25	14.80	10.98
	WEIGHTED AVERAGE FOR THE YEAR			126,879.00	18.07	22.89	17.79
===== 207-00210 Stockpile Topsoil Cubic Yard =====							
FSA0253-262		I-25 SB BOTTLENECK I-76 TO I-	01/09/20	560.00	6.00	23.13	22.00
FSA0341-097		US 34 & MACGREGOR INTERSECTIO	01/09/20	1,612.00	8.00	15.00	15.00
BR0343-040		US 34 REPUBLICAN RIVER BRIDGE	01/16/20	905.00	8.00	10.24	5.00
FBR0343-043		US 34 D-28-P STRUCTURE REPLAC					
BR025A-046		K-18-U ON I-25 AT MP112 BRIDG	03/05/20	573.00	6.00	9.35	7.31
	WEIGHTED AVERAGE FOR THE FIRST QUARTER			3,650.00	7.38	12.26	12.39
STA340A-021		SH340 MP 6-6.76 MESA COUNTY	04/02/20	451.00	7.50	19.33	28.00
CC0852-106		US-85 LOUVIERS TO MP 191.75	04/23/20	835.00	10.00	7.81	2.55
FBR0852-108		US-85 BETWEEN LOUVIERS AND MP					
C0853-112		US85 & WCR98 INTERSECTION IMP	05/07/20	3,150.00	7.00	5.08	3.00
NHPP0253-276		I-25 EXPRESS LANES SEGMENT 5	05/15/20	19,835.00	5.70	5.97	5.97
	WEIGHTED AVERAGE FOR THE SECOND QUARTER			24,271.00	6.05	6.12	5.88
	WEIGHTED AVERAGE FOR THE YEAR			27,921.00	6.22	7.31	6.73
===== 207-00305 Wetland Topsoil Cubic Yard =====							
BR0343-040		US 34 REPUBLICAN RIVER BRIDGE	01/16/20	55.00	30.00	28.81	20.00
FBR0343-043		US 34 D-28-P STRUCTURE REPLAC					
	WEIGHTED AVERAGE FOR THE FIRST QUARTER			55.00	30.00	28.81	20.00

PROJECT NUMBER	ITEM NUMBER/ PROJECT LOCATION	ITEM DESCRIPTION/ PROJECT LOCATION	DATE LET	UNIT/ QUANTITY	ENGR. EST.	AVERAGE BID	AWARDED BID
===== 207-00305		Wetland Topsoil		Cubic Yard	=====		
IM0761-226		I76/SH52 Interchange	04/02/20	820.00	18.00	15.46	11.00
	WEIGHTED AVERAGE FOR THE SECOND QUARTER			820.00	18.00	15.46	11.00
	WEIGHTED AVERAGE FOR THE YEAR			875.00	18.75	16.19	11.57
===== 207-00310		Stockpile Wetland Topsoil		Cubic Yard	=====		
BR0343-040 FBR0343-043		US 34 REPUBLICAN RIVER BRIDGE	01/16/20	55.00	20.00	23.74	16.00
		US 34 D-28-P STRUCTURE REPLAC					
	WEIGHTED AVERAGE FOR THE FIRST QUARTER			55.00	20.00	23.74	16.00
IM0761-226		I76/SH52 Interchange	04/02/20	820.00	19.00	14.96	11.99
	WEIGHTED AVERAGE FOR THE SECOND QUARTER			820.00	19.00	14.96	11.99
	WEIGHTED AVERAGE FOR THE YEAR			875.00	19.06	15.44	12.24
===== 207-00700		Topsoil (Onsite)		Cubic Yard	=====		
SHE 0703-461		I-70 and Kipling North Phase	03/26/20	303.00	28.00	33.00	21.00
	WEIGHTED AVERAGE FOR THE FIRST QUARTER			303.00	28.00	33.00	21.00
FBR0343-042		US 34 D-27-G STRUCTURE REPLAC	05/07/20	1,220.00	10.00	17.35	10.00
	WEIGHTED AVERAGE FOR THE SECOND QUARTER			1,220.00	10.00	17.35	10.00
	WEIGHTED AVERAGE FOR THE YEAR			1,523.00	13.58	19.25	12.19
===== 207-00703		Topsoil (Wetlnd)		Cubic Yard	=====		
FBR0343-042		US 34 D-27-G STRUCTURE REPLAC	05/07/20	201.00	20.00	28.27	20.00
	WEIGHTED AVERAGE FOR THE SECOND QUARTER			201.00	20.00	28.27	20.00
	WEIGHTED AVERAGE FOR THE YEAR			201.00	20.00	28.27	20.00

COLORADO DEPARTMENT OF TRANSPORTATION
 ITEM UNIT COSTS BY PROJECTS -- 2020 COST DATA

10:58 Friday, October 2, 2020 58

PROJECT NUMBER	ITEM NUMBER/ PROJECT LOCATION	ITEM DESCRIPTION/ PROJECT LOCATION	DATE LET	UNIT/ QUANTITY	ENGR. EST.	AVERAGE BID	AWARDED BID
=====	207-00704	Sub Soil Prep		Sq Yard	=====		
SHE 0703-461		I-70 and Kipling North Phase	03/26/20	2,015.00	1.00	5.44	7.00
		WEIGHTED AVERAGE FOR THE FIRST QUARTER		2,015.00	1.00	5.44	7.00
FBR0343-042		US 34 D-27-G STRUCTURE REPLAC	05/07/20	7,930.00	1.00	2.05	0.30
		WEIGHTED AVERAGE FOR THE SECOND QUARTER		7,930.00	1.00	2.05	0.30
		WEIGHTED AVERAGE FOR THE YEAR		9,945.00	1.00	2.47	1.66
=====	208-00002	Erosion Log Type 1 (12 In)		Lin Foot	=====		
STA0142-066		SH 14 New Raymer West	01/09/20	100.00	5.00	5.63	6.00
FSA0341-097		US 34 & MACGREGOR INTERSECTIO	01/09/20	800.00	5.00	9.00	9.00
NHPP0343-041		I-76 & US 34 FT. MORGAN AREA	01/09/20	10,041.00	6.00	6.60	5.00
BR0343-040		US 34 REPUBLICAN RIVER BRIDGE	01/16/20	1,913.00	6.00	6.07	6.50
FBR0343-043		US 34 D-28-P STRUCTURE REPLAC					
STA006A-067		SH 6 Merino to Atwood	01/16/20	300.00	5.00	10.36	11.75
STR131A-038		SH 131 MP 51.95-55.73, ROUTT	01/16/20	200.00	6.00	5.00	4.75
PWQM240-172		El Paso County, north Colorad	01/23/20	3,697.00	6.00	5.50	6.00
NHPP 0852-116		US85:HAMPDEN TO FLORIDA-RESUR	02/06/20	100.00	6.00	13.50	5.00
ITS0761-231		ITS FIBER AND CAMERAS ON I-76	02/06/20	15,510.00	7.00	5.50	5.00
STA059A-036		SH 59 SEIBERT TO COPE	02/06/20	800.00	7.00	5.50	5.00
STR116A-001		SH 116 A Surface Treatment Pr	02/13/20	2,500.00	5.00	4.80	6.00
FSA2873-194		US 287 Longmont Intersection	02/13/20	1,200.00	8.00	6.54	6.75
STR0101-027		SH 10 Overlay La Junta West	02/27/20	2,000.00	5.00	4.61	5.00
NHPP0702-359		I-70 No Name Tunnel Lighting	02/27/20	2,742.00	5.00	6.96	4.50
C0402-094		US 40 GRAND COUNTY SIGNAL REP	02/27/20	200.00	5.00	7.50	5.00
NHPP0171-105		SH 17 MP 84.5 to US 285 & SH	03/05/20	1,025.00	5.00	4.79	4.13
C0641-106		SH 64 Meeker West Rural Resur	03/05/20	450.00	6.00	4.83	5.25
NHPP145A-080		SH 145 Keystone-Placerville R	03/05/20	560.00	6.00	4.50	4.50
BR025A-046		K-18-U ON I-25 AT MP112 BRIDG	03/05/20	4,000.00	4.50	4.46	3.65
NHPP0091-044		SH 9 FRISCO MAIN ST TO IRON S	03/05/20	2,150.00	7.00	6.95	5.50
NH050A-034		US50A PUEBLO WEST PURCELL INT	03/26/20	57,920.00	5.00	5.39	4.30
HPP 0501-067		US 50 AND SH 92 DELTA INTERSE	03/26/20	1,760.00	5.00	5.48	5.25
SHE 0703-461		I-70 and Kipling North Phase	03/26/20	510.00	5.50	6.40	8.00
		WEIGHTED AVERAGE FOR THE FIRST QUARTER		110,478.00	5.50	5.48	4.74
NHPP1602-169		US 160 WC TUNNEL EAST RESURFA	04/02/20	200.00	5.00	6.21	4.93

PROJECT NUMBER	ITEM NUMBER/ PROJECT LOCATION	ITEM DESCRIPTION/ PROJECT LOCATION	DATE LET	UNIT/ QUANTITY	ENGR. EST.	AVERAGE BID	AWARDED BID
===== 208-00002		Erosion Log Type 1 (12 In)		Lin Foot	=====	=====	=====
STR092A-030		SH92 MP 31.748-48.5, DELTA AND	04/02/20	1,000.00	5.00	5.98	6.85
IM0761-226		I76/SH52 Interchange	04/02/20	11,860.00	6.00	4.95	3.91
STA340A-021		SH340 MP 6-6.76 MESA COUNTY	04/02/20	3,380.00	4.50	4.72	4.00
STR0341-101		SH 34 North of Grandby Resurf	04/02/20	500.00	10.00	10.24	17.50
NHPP1601-077		US 160 MP 29.750 - MP 34.891	04/09/20	200.00	5.00	8.12	5.00
SFTY2254-091		225 Ramp Improvements	04/09/20	3,903.00	5.00	5.00	4.00
CC0852-106		US-85 LOUVIERS TO MP 191.75	04/23/20	15,980.00	5.50	4.94	3.72
FBR0852-108		US-85 BETWEEN LOUVIERS AND MP					
C1211-090		SH-121 & 29th Ave / SH-121 &	04/23/20	80.00	6.00	10.23	7.00
C1601-082		Hawkins Signal and Curb Ramps	04/30/20	86.00	10.00	8.75	11.75
FSA1602-159		US 160 AND SH 17 INTERSECTION	04/30/20	1,310.00	6.00	6.00	5.00
C0853-112		US85 & WCR98 INTERSECTION IMP	05/07/20	1,634.00	5.00	4.57	4.25
NHPPR100-303		LONG MAST ARM SIGNALS PROJECT	05/07/20	1,655.00	8.00	7.12	6.00
FBR0343-042		US 34 D-27-G STRUCTURE REPLAC	05/07/20	3,500.00	6.00	4.84	4.75
ITS SW02-304		ITS FIBER TO STATE BUILDINGS	05/14/20	14,600.00	7.00	7.13	7.47
NHPP0253-276		I-25 EXPRESS LANES SEGMENT 5	05/15/20	27,340.00	4.30	4.32	4.32
ITS SW02-303		R1: US 285, SH 83 R2: SH 83,	05/28/20	5,130.00	5.50	5.56	5.25
ITSSW01-719		FY 20 ITS CAPITAL REPLACEMENT	06/11/20	1,000.00	5.00	4.00	2.50
FSAR400-356		FY 20 SIGNAL POLE REPLACEMENT	06/11/20	80.00	5.00	10.33	7.00
SHE016A-043		SH 21 & 16 SIGNALS PROJECT	06/18/20	250.00	8.00	7.00	5.01
		WEIGHTED AVERAGE FOR THE SECOND QUARTER		93,688.00	5.47	5.32	4.83
		WEIGHTED AVERAGE FOR THE YEAR		204,166.00	5.49	5.42	4.78
===== 208-00007		Erosion Log Type 2 (8 In)		Lin Foot	=====	=====	=====
NH050A-035		US 50A Pueblo Regional Pond	05/28/20	16,600.00	6.20	4.48	3.70
NH050A-037		US 50A Pueblo Regional Pond					
		WEIGHTED AVERAGE FOR THE SECOND QUARTER		16,600.00	6.20	4.48	3.70
		WEIGHTED AVERAGE FOR THE YEAR		16,600.00	6.20	4.48	3.70
===== 208-00008		Erosion Log Type 2 (12 In)		Lin Foot	=====	=====	=====
NHPP0253-265		I-25 AT ERIE PARKWAY ON AND O	01/09/20	350.00	10.00	8.35	10.00
STR012A-050		CULVERT REPAIR I-25 AND US 35	01/30/20	950.00	5.00	8.00	8.00
		WEIGHTED AVERAGE FOR THE FIRST QUARTER		1,300.00	6.35	8.18	8.54
		WEIGHTED AVERAGE FOR THE YEAR		1,300.00	6.35	8.18	8.54
===== 208-00009		Erosion Log Type 2 (18 In)		Lin Foot	=====	=====	=====
STR012A-050		CULVERT REPAIR I-25 AND US 35	01/30/20	280.00	12.00	14.00	14.00
		WEIGHTED AVERAGE FOR THE FIRST QUARTER		280.00	12.00	14.00	14.00
		WEIGHTED AVERAGE FOR THE YEAR		280.00	12.00	14.00	14.00

COLORADO DEPARTMENT OF TRANSPORTATION
ITEM UNIT COSTS BY PROJECTS -- 2020 COST DATA

10:58 Friday, October 2, 2020 60

PROJECT NUMBER	ITEM NUMBER/ PROJECT LOCATION	ITEM DESCRIPTION/ PROJECT LOCATION	DATE LET	UNIT/ QUANTITY	ENGR. EST.	AVERAGE BID	AWARDED BID
=====	208-00011	Erosion Bales (Weed Free)		Each	=====		
NH050A-034		US50A PUEBLO WEST PURCELL INT	03/26/20	160.00	26.00	33.14	31.00
		WEIGHTED AVERAGE FOR THE FIRST QUARTER		160.00	26.00	33.14	31.00
		WEIGHTED AVERAGE FOR THE YEAR		160.00	26.00	33.14	31.00
=====	208-00012	Erosion Log Type 1 (9 In)		Lin Foot	=====		
FSA0253-262		I-25 SB BOTTLENECK I-76 TO I-	01/09/20	200.00	7.00	8.31	12.00
NHPP4701-134		C-470 NOISE WALL WEST OF LUCE	02/06/20	3,165.00	5.00	4.72	4.50
		WEIGHTED AVERAGE FOR THE FIRST QUARTER		3,365.00	5.12	4.85	4.95
		WEIGHTED AVERAGE FOR THE YEAR		3,365.00	5.12	4.85	4.95
=====	208-00013	Erosion Log Type 1 (20 In)		Lin Foot	=====		
STR2871-038		US 287 Passing Lanes Springfi	03/05/20	2,000.00	10.00	6.46	7.28
		WEIGHTED AVERAGE FOR THE FIRST QUARTER		2,000.00	10.00	6.46	7.28
CC0852-106		US-85 LOUVIERS TO MP 191.75	04/23/20	1,840.00	7.00	8.82	7.92
FBR0852-108		US-85 BETWEEN LOUVIERS AND MP					
NHPP0253-276		I-25 EXPRESS LANES SEGMENT 5	05/15/20	500.00	7.00	10.70	10.70
		WEIGHTED AVERAGE FOR THE SECOND QUARTER		2,340.00	7.00	8.88	8.51
		WEIGHTED AVERAGE FOR THE YEAR		4,340.00	8.38	8.38	7.95
=====	208-00020	Silt Fence		Lin Foot	=====		
FSA0253-262		I-25 SB BOTTLENECK I-76 TO I-	01/09/20	100.00	2.00	8.63	7.00
FSA0341-097		US 34 & MACGREGOR INTERSECTIO	01/09/20	100.00	3.25	3.00	3.00
NHPP0343-041		I-76 & US 34 FT. MORGAN AREA	01/09/20	4,591.00	1.50	2.71	1.50
PWQM240-172		El Paso County, north Colorad	01/23/20	232.00	4.00	2.00	2.00
NHPP4701-134		C-470 NOISE WALL WEST OF LUCE	02/06/20	13,472.00	2.00	2.10	2.00
STA069A-033		SH69 MP 58.7 TO 71.58	02/13/20	1,560.00	3.25	2.47	3.00

PROJECT NUMBER	ITEM NUMBER/ PROJECT LOCATION	ITEM DESCRIPTION/ PROJECT LOCATION	DATE LET	UNIT/ QUANTITY	ENGR. EST.	AVERAGE BID	AWARDED BID
=====	208-00020	Silt Fence		Lin Foot	=====	=====	=====
NHPP0171-105		SH 17 MP 84.5 to US 285 & SH	03/05/20	1,000.00	2.00	1.94	1.38
NHPP145A-080		SH 145 Keystone-Placerville R	03/05/20	710.00	4.00	2.15	2.15
NH050A-034		US50A PUEBLO WEST PURCELL INT	03/26/20	18,259.00	3.00	2.23	1.40
	WEIGHTED AVERAGE FOR THE FIRST QUARTER			40,024.00	2.50	2.23	1.71
NHPP1602-169		US 160 WC TUNNEL EAST RESURFA	04/02/20	200.00	2.00	2.69	2.08
CC0852-106		US-85 LOUVIERS TO MP 191.75	04/23/20	5,500.00	2.25	2.05	1.10
FBR0852-108		US-85 BETWEEN LOUVIERS AND MP					
NHPP0253-276		I-25 EXPRESS LANES SEGMENT 5	05/15/20	390.00	1.00	1.47	1.47
NH050A-035		US 50A Pueblo Regional Pond	05/28/20	2,300.00	2.00	2.29	1.40
NH050A-037		US 50A Pueblo Regional Pond					
	WEIGHTED AVERAGE FOR THE SECOND QUARTER			8,390.00	2.12	2.12	1.22
	WEIGHTED AVERAGE FOR THE YEAR			48,414.00	2.43	2.21	1.63
=====	208-00021	Silt Fence (Reinf)		Lin Foot	=====	=====	=====
NH 0503-093		US50 WEST OF TEXAS CREEK MP 2	01/23/20	1,500.00	5.00	3.95	2.89
	WEIGHTED AVERAGE FOR THE FIRST QUARTER			1,500.00	5.00	3.95	2.89
IM0252-473		I-25 CABLE BARRIER PHASE IV	04/09/20	208.00	3.00	8.00	10.00
NHPP0253-276		I-25 EXPRESS LANES SEGMENT 5	05/15/20	930.00	3.00	2.94	2.94
	WEIGHTED AVERAGE FOR THE SECOND QUARTER			1,138.00	3.00	4.50	4.23
	WEIGHTED AVERAGE FOR THE YEAR			2,638.00	4.14	4.12	3.47
=====	208-00023	Erosion Log (Type 3) (12 In)		Lin Foot	=====	=====	=====
NHPP0343-041		I-76 & US 34 FT. MORGAN AREA	01/09/20	1,350.00	6.00	8.08	6.00
BR0343-040		US 34 REPUBLICAN RIVER BRIDGE	01/16/20	1,719.00	6.50	7.06	8.00
FBR0343-043		US 34 D-28-P STRUCTURE REPLAC					
	WEIGHTED AVERAGE FOR THE FIRST QUARTER			3,069.00	6.28	7.35	7.12
IM025A-048		Northbound I-25 bridge at Exi	05/28/20	60.00	7.00	15.30	18.00
	WEIGHTED AVERAGE FOR THE SECOND QUARTER			60.00	7.00	15.30	18.00
	WEIGHTED AVERAGE FOR THE YEAR			3,129.00	6.29	7.45	7.33

PROJECT NUMBER	ITEM NUMBER/ PROJECT LOCATION	ITEM DESCRIPTION/ PROJECT LOCATION	DATE LET	UNIT/ QUANTITY	ENGR. EST.	AVERAGE BID	AWARDED BID
===== 208-00025		Plastic Sheeting		Sq Yard	=====	=====	=====
FSA2873-194		US 287 Longmont Intersection	02/13/20	1,200.00	10.00	3.25	2.50
	WEIGHTED AVERAGE FOR THE FIRST QUARTER			1,200.00	10.00	3.25	2.50
	WEIGHTED AVERAGE FOR THE YEAR			1,200.00	10.00	3.25	2.50
===== 208-00033		Sediment Trap		Each	=====	=====	=====
NH 0503-093		US50 WEST OF TEXAS CREEK MP 2	01/23/20	1.00	2000.00	3875.27	5250.53
PWQM240-172		El Paso County, north Colorad	01/23/20	1.00	3000.00	7255.00	8110.00
	WEIGHTED AVERAGE FOR THE FIRST QUARTER			2.00	2500.00	5565.13	6680.27
NHPP0253-276		I-25 EXPRESS LANES SEGMENT 5	05/15/20	1.00	10000.00	10898.88	10898.88
	WEIGHTED AVERAGE FOR THE SECOND QUARTER			1.00	10000.00	10898.88	10898.88
	WEIGHTED AVERAGE FOR THE YEAR			3.00	5000.00	6631.88	8086.47
===== 208-00035		Aggregate Bag		Lin Foot	=====	=====	=====
STA0142-066		SH 14 New Raymer West	01/09/20	800.00	23.00	7.50	6.00
FSA0253-262		I-25 SB BOTTLENECK I-76 TO I-	01/09/20	25.00	12.00	18.51	22.00
NHPP0253-265		I-25 AT ERIE PARKWAY ON AND O	01/09/20	120.00	10.00	12.32	11.00
FSA0341-097		US 34 & MACGREGOR INTERSECTIO	01/09/20	120.00	10.00	13.00	13.00
NHPP0343-041		I-76 & US 34 FT. MORGAN AREA	01/09/20	3,040.00	5.00	7.48	6.50
BR0343-040		US 34 REPUBLICAN RIVER BRIDGE	01/16/20	120.00	6.50	11.14	8.00
FBR0343-043		US 34 D-28-P STRUCTURE REPLAC					
STA006A-067		SH 6 Merino to Atwood	01/16/20	500.00	23.00	9.85	8.50
STR131A-038		SH 131 MP 51.95-55.73, ROUTT	01/16/20	200.00	8.00	8.50	11.00
NH 0503-093		US50 WEST OF TEXAS CREEK MP 2	01/23/20	1,500.00	6.00	6.97	6.93
PWQM240-172		El Paso County, north Colorad	01/23/20	1,080.00	12.00	6.50	5.00
NHPP 0852-116		US85:HAMPDEN TO FLORIDA-RESUR	02/06/20	100.00	12.00	15.00	12.00
STA0703-443		I-70 EJMT TUNNELS PAVING	02/06/20	65.00	12.00	30.75	16.50
ITS0761-231		ITS FIBER AND CAMERAS ON I-76	02/06/20	500.00	8.00	8.35	7.20
STA059A-036		SH 59 SEIBERT TO COPE	02/06/20	700.00	8.00	9.00	8.00
FSA2873-194		US 287 Longmont Intersection	02/13/20	400.00	10.00	9.89	6.60
STA069A-033		SH69 MP 58.7 TO 71.58	02/13/20	8.00	8.00	11.84	12.00
NHPP0702-359		I-70 No Name Tunnel Lighting	02/27/20	100.00	10.00	19.95	11.50

PROJECT NUMBER	ITEM NUMBER/ PROJECT LOCATION	ITEM DESCRIPTION/ PROJECT LOCATION	DATE LET	UNIT/ QUANTITY	ENGR. EST.	AVERAGE BID	AWARDED BID
===== 208-00035		Aggregate Bag		Lin Foot	=====	=====	=====
C0402-094		US 40 GRAND COUNTY SIGNAL REP	02/27/20	200.00	10.00	10.50	11.00
NH0242-085		US 24 M.P. 291.38 to M.P. 296	02/27/20	210.00	10.00	16.96	34.25
C0641-106		SH 64 Meeker West Rural Resur	03/05/20	100.00	10.00	9.60	8.00
NHPP0502-082		US 50 MONTROSE RE CHIP SEAL	03/05/20	1,000.00	10.00	7.94	5.00
NHPP0091-044		SH 9 FRISCO MAIN ST TO IRON S	03/05/20	212.00	10.00	8.45	7.50
NH050A-034		US50A PUEBLO WEST PURCELL INT	03/26/20	25,200.00	8.00	6.63	5.80
HPP 0501-067		US 50 AND SH 92 DELTA INTERSE	03/26/20	425.00	10.00	6.90	6.75
SHE 0703-461		I-70 and Kipling North Phase	03/26/20	100.00	12.00	9.40	8.00
		WEIGHTED AVERAGE FOR THE FIRST QUARTER		36,825.00	8.50	6.90	6.33
NHPP1602-169		US 160 WC TUNNEL EAST RESURFA	04/02/20	200.00	9.00	11.99	12.77
STR092A-030		SH92 MP 31.748-48.5, DELTA AND	04/02/20	500.00	10.00	10.80	8.50
IM0761-226		I76/SH52 Interchange	04/02/20	384.00	10.00	9.86	6.36
STA340A-021		SH340 MP 6-6.76 MESA COUNTY	04/02/20	100.00	9.00	18.57	20.00
STR0341-101		SH 34 North of Grandby Resurf	04/02/20	500.00	15.00	12.81	17.50
SHER100-339		WWD TRAFFIC CONTROL ENHANCEME	04/09/20	1,000.00	12.00	5.00	5.00
C1211-090		SH-121 & 29th Ave / SH-121 &	04/23/20	200.00	6.00	12.60	14.00
C1601-082		Hawkins Signal and Curb Ramps	04/30/20	1,220.00	10.00	13.00	12.00
FSA1602-159		US 160 AND SH 17 INTERSECTION	04/30/20	40.00	10.00	15.00	12.00
NHPPR100-303		LONG MAST ARM SIGNALS PROJECT	05/07/20	145.00	10.00	12.67	15.00
FBR0343-042		US 34 D-27-G STRUCTURE REPLAC	05/07/20	1,500.00	8.00	7.33	8.00
ITS SW02-304		ITS FIBER TO STATE BUILDINGS	05/14/20	200.00	20.00	10.73	10.24
NHPP0402-098		US 40 CHIP SEAL MP 126 TO MP	05/14/20	100.00	5.00	14.67	24.00
NHPP0253-276		I-25 EXPRESS LANES SEGMENT 5	05/15/20	100.00	11.00	10.86	10.86
ITS SW02-303		R1: US 285, SH 83 R2: SH 83,	05/28/20	635.00	12.00	7.82	0.10
NH050A-035		US 50A Pueblo Regional Pond	05/28/20	800.00	10.00	8.58	8.00
NH050A-037		US 50A Pueblo Regional Pond					
ITSSW01-719		FY 20 ITS CAPITAL REPLACEMENT	06/11/20	220.00	14.00	9.75	7.50
FSAR400-356		FY 20 SIGNAL POLE REPLACEMENT	06/11/20	120.00	8.00	8.83	7.50
SHE016A-043		SH 21 & 16 SIGNALS PROJECT	06/18/20	60.00	10.00	11.96	11.78
NHPPR100-251		SH 2/ Vasquez	06/25/20	200.00	10.00	20.28	32.55
		WEIGHTED AVERAGE FOR THE SECOND QUARTER		8,224.00	10.48	9.30	9.59
		WEIGHTED AVERAGE FOR THE YEAR		45,049.00	8.86	7.23	6.93
===== 208-00041		Rock Check Dam		Each	=====	=====	=====
PWQM240-172		El Paso County, north Colorad	01/23/20	13.00	700.00	2541.00	2482.00
		WEIGHTED AVERAGE FOR THE FIRST QUARTER		13.00	700.00	2541.00	2482.00
CC0852-106		US-85 LOUVIERS TO MP 191.75	04/23/20	71.00	700.00	992.77	440.00

PROJECT NUMBER	ITEM NUMBER/ PROJECT LOCATION	ITEM DESCRIPTION/ PROJECT LOCATION	DATE LET	UNIT/ QUANTITY	ENGR. EST.	AVERAGE BID	AWARDED BID
===== 208-00041		Rock Check Dam		Each			
FBR0852-108		US-85 BETWEEN LOUVIERS AND MP					
NHPP0253-276		I-25 EXPRESS LANES SEGMENT 5	05/15/20	50.00	540.00	609.05	609.05
	WEIGHTED AVERAGE FOR THE SECOND QUARTER			121.00	633.88	961.73	509.86
	WEIGHTED AVERAGE FOR THE YEAR			134.00	640.30	1025.49	701.18
===== 208-00045		Conc Washout Str		Each			
FSA0341-097		US 34 & MACGREGOR INTERSECTIO	01/09/20	1.00	1500.00	4000.00	4000.00
NHPP0343-041		I-76 & US 34 FT. MORGAN AREA	01/09/20	6.00	1500.00	2204.98	2384.00
PWQM240-172		El Paso County, north Colorad	01/23/20	14.00	3000.00	898.50	817.00
NHPP4701-134		C-470 NOISE WALL WEST OF LUCE	02/06/20	2.00	2000.00	2824.20	2721.00
STA069A-033		SH69 MP 58.7 TO 71.58	02/13/20	1.00	3000.00	2562.97	2500.00
NH0242-085		US 24 M.P. 291.38 to M.P. 296	02/27/20	2.00	1970.00	2360.65	2500.00
STR2871-038		US 287 Passing Lanes Springfi	03/05/20	2.00	2000.00	1280.51	2340.00
BR025A-046		K-18-U ON I-25 AT MP112 BRIDG	03/05/20	2.00	1500.00	1632.32	698.62
NH050A-034		US50A PUEBLO WEST PURCELL INT	03/26/20	2.00	2500.00	4619.03	2500.00
	WEIGHTED AVERAGE FOR THE FIRST QUARTER			32.00	2357.50	2204.63	1680.04
NHPP1602-169		US 160 WC TUNNEL EAST RESURFA	04/02/20	1.00	800.00	1358.80	541.43
IM0761-226		I76/SH52 Interchange	04/02/20	3.00	1500.00	5367.23	2915.00
IM0252-473		I-25 CABLE BARRIER PHASE IV	04/09/20	4.00	1500.00	2562.50	1125.00
SFTY2254-091		225 Ramp Improvements	04/09/20	3.00	1500.00	3282.50	1665.00
CC0852-106		US-85 LOUVIERS TO MP 191.75	04/23/20	6.00	2500.00	2732.18	550.00
FBR0852-108		US-85 BETWEEN LOUVIERS AND MP					
C1211-090		SH-121 & 29th Ave / SH-121 &	04/23/20	3.00	2040.00	1290.00	685.00
NHPP0253-276		I-25 EXPRESS LANES SEGMENT 5	05/15/20	3.00	2597.00	1612.52	1612.52
NH050A-035		US 50A Pueblo Regional Pond	05/28/20	8.00	1500.00	833.50	500.00
NH050A-037		US 50A Pueblo Regional Pond					
SHE016A-043		SH 21 & 16 SIGNALS PROJECT	06/18/20	1.00	2000.00	1320.60	223.00
	WEIGHTED AVERAGE FOR THE SECOND QUARTER			32.00	1834.72	2182.77	1037.41
	WEIGHTED AVERAGE FOR THE YEAR			64.00	2096.11	2190.91	1358.72
===== 208-00046		Pre-fab Conc Washout Str (Type 1)		Each			
FSA0253-262		I-25 SB BOTTLENECK I-76 TO I-	01/09/20	1.00	2500.00	2676.38	3200.00
NHPP0253-265		I-25 AT ERIE PARKWAY ON AND O	01/09/20	2.00	640.00	1186.67	710.00

PROJECT NUMBER	ITEM NUMBER/ PROJECT LOCATION	ITEM DESCRIPTION/ PROJECT LOCATION	DATE LET	UNIT/ QUANTITY	ENGR. EST.	AVERAGE BID	AWARDED BID
===== 208-00046		Pre-fab Conc Washout Str (Type 1)		Each =====			
BR0343-040	US 34 REPUBLICAN RIVER BRIDGE	US 34 REPUBLICAN RIVER BRIDGE	01/16/20	3.00	1810.00	1795.49	1180.00
FBR0343-043	US 34 D-28-P STRUCTURE REPLAC	US 34 D-28-P STRUCTURE REPLAC					
NH 0503-093	US50 WEST OF TEXAS CREEK MP 2	US50 WEST OF TEXAS CREEK MP 2	01/23/20	1.00	2000.00	4125.27	5250.53
NHPP 0852-116	US85:HAMPDEN TO FLORIDA-RESUR	US85:HAMPDEN TO FLORIDA-RESUR	02/06/20	1.00	2500.00	9000.00	5000.00
STA0703-443	I-70 EJMT TUNNELS PAVING	I-70 EJMT TUNNELS PAVING	02/06/20	2.00	2000.00	2898.35	2596.70
ITS0761-231	ITS FIBER AND CAMERAS ON I-76	ITS FIBER AND CAMERAS ON I-76	02/06/20	4.00	1750.00	535.05	400.00
STA059A-036	SH 59 SEIBERT TO COPE	SH 59 SEIBERT TO COPE	02/06/20	2.00	1600.00	2025.00	2050.00
FSA2873-194	US 287 Longmont Intersection	US 287 Longmont Intersection	02/13/20	10.00	1500.00	808.33	600.00
C0402-094	US 40 GRAND COUNTY SIGNAL REP	US 40 GRAND COUNTY SIGNAL REP	02/27/20	2.00	2000.00	1750.00	500.00
NHPP145A-080	SH 145 Keystone-Placerville R	SH 145 Keystone-Placerville R	03/05/20	1.00	2000.00	200.00	200.00
NHPP0091-044	SH 9 FRISCO MAIN ST TO IRON S	SH 9 FRISCO MAIN ST TO IRON S	03/05/20	1.00	1000.00	13146.67	10000.00
HPP 0501-067	US 50 AND SH 92 DELTA INTERSE	US 50 AND SH 92 DELTA INTERSE	03/26/20	2.00	3000.00	2432.50	2885.00
SHE 0703-461	I-70 and Kipling North Phase	I-70 and Kipling North Phase	03/26/20	2.00	2500.00	1348.00	1450.00
	WEIGHTED AVERAGE FOR THE FIRST QUARTER			34.00	1791.47	1577.75	1622.76
STA340A-021	SH340 MP 6-6.76 MESA COUNTY	SH340 MP 6-6.76 MESA COUNTY	04/02/20	2.00	2000.00	1008.33	1200.00
SHER100-339	WWD TRAFFIC CONTROL ENHANCEME	WWD TRAFFIC CONTROL ENHANCEME	04/09/20	3.00	2500.00	1800.00	1800.00
CC0852-106	US-85 LOUVIERS TO MP 191.75	US-85 LOUVIERS TO MP 191.75	04/23/20	2.00	2200.00	2685.30	3300.00
FBR0852-108	US-85 BETWEEN LOUVIERS AND MP	US-85 BETWEEN LOUVIERS AND MP					
C1601-082	Hawkins Signal and Curb Ramps	Hawkins Signal and Curb Ramps	04/30/20	3.00	1500.00	666.67	400.00
FSA1602-159	US 160 AND SH 17 INTERSECTION	US 160 AND SH 17 INTERSECTION	04/30/20	2.00	1600.00	3377.33	207.00
NHPPR100-303	LONG MAST ARM SIGNALS PROJECT	LONG MAST ARM SIGNALS PROJECT	05/07/20	4.00	2000.00	611.67	685.00
ITS SW02-304	ITS FIBER TO STATE BUILDINGS	ITS FIBER TO STATE BUILDINGS	05/14/20	34.00	500.00	259.75	91.00
NHPP0253-276	I-25 EXPRESS LANES SEGMENT 5	I-25 EXPRESS LANES SEGMENT 5	05/15/20	2.00	8000.00	4963.60	4963.60
ITS SW02-303	R1: US 285, SH 83 R2: SH 83,	R1: US 285, SH 83 R2: SH 83,	05/28/20	2.00	500.00	982.20	350.00
ITSSW01-719	FY 20 ITS CAPITAL REPLACEMENT	FY 20 ITS CAPITAL REPLACEMENT	06/11/20	9.00	750.00	250.00	250.00
FSAR400-356	FY 20 SIGNAL POLE REPLACEMENT	FY 20 SIGNAL POLE REPLACEMENT	06/11/20	2.00	2200.00	595.00	725.00
NHPPR100-251	SH 2/ Vasquez	SH 2/ Vasquez	06/25/20	4.00	1500.00	1398.55	1256.10
	WEIGHTED AVERAGE FOR THE SECOND QUARTER			69.00	1199.28	699.79	597.10
	WEIGHTED AVERAGE FOR THE YEAR			103.00	1394.76	1031.68	935.67
===== 208-00051		Storm Drain Inlet Protection (Type I)		Lin Foot =====			
BR0343-040	US 34 REPUBLICAN RIVER BRIDGE	US 34 REPUBLICAN RIVER BRIDGE	01/16/20	9.00	20.00	26.80	15.00
FBR0343-043	US 34 D-28-P STRUCTURE REPLAC	US 34 D-28-P STRUCTURE REPLAC					
PWQM240-172	El Paso County, north Colorad	El Paso County, north Colorad	01/23/20	18.00	20.00	6.50	5.00
STA0703-443	I-70 EJMT TUNNELS PAVING	I-70 EJMT TUNNELS PAVING	02/06/20	65.00	20.00	31.22	17.44
NHPP0091-044	SH 9 FRISCO MAIN ST TO IRON S	SH 9 FRISCO MAIN ST TO IRON S	03/05/20	159.00	25.00	9.63	10.00
HPP 0501-067	US 50 AND SH 92 DELTA INTERSE	US 50 AND SH 92 DELTA INTERSE	03/26/20	49.00	15.00	21.68	6.75
SHE 0703-461	I-70 and Kipling North Phase	I-70 and Kipling North Phase	03/26/20	78.00	15.00	17.80	10.00
	WEIGHTED AVERAGE FOR THE FIRST QUARTER			378.00	20.42	16.37	10.74

COLORADO DEPARTMENT OF TRANSPORTATION
ITEM UNIT COSTS BY PROJECTS -- 2020 COST DATA

10:58 Friday, October 2, 2020 66

PROJECT NUMBER	ITEM NUMBER/ PROJECT LOCATION	ITEM DESCRIPTION/ PROJECT LOCATION	DATE LET	UNIT/ QUANTITY	ENGR. EST.	AVERAGE BID	AWARDED BID
===== 208-00051		Storm Drain Inlet Protection (Type I)		Lin Foot	=====		
IM0761-226		I76/SH52 Interchange	04/02/20	197.00	18.00	12.45	6.68
CC0852-106		US-85 LOUVIERS TO MP 191.75	04/23/20	1,584.00	19.00	12.44	11.77
FBR0852-108		US-85 BETWEEN LOUVIERS AND MP					
FSA1602-159		US 160 AND SH 17 INTERSECTION	04/30/20	7.00	25.00	48.00	14.00
ITS SW02-303		R1: US 285, SH 83 R2: SH 83,	05/28/20	325.00	25.00	27.79	0.10
NH050A-035		US 50A Pueblo Regional Pond	05/28/20	40.00	20.00	17.00	8.50
NH050A-037		US 50A Pueblo Regional Pond					
SHE016A-043		SH 21 & 16 SIGNALS PROJECT	06/18/20	160.00	35.00	11.84	10.20
	WEIGHTED AVERAGE FOR THE SECOND QUARTER			2,313.00	20.90	14.02	9.54
	WEIGHTED AVERAGE FOR THE YEAR			2,691.00	20.83	14.18	9.71
===== 208-00052		Storm Drain Inlet Protection (Type II)		Lin Foot	=====		
C0402-094		US 40 GRAND COUNTY SIGNAL REP	02/27/20	10.00	70.00	25.00	35.00
	WEIGHTED AVERAGE FOR THE FIRST QUARTER			10.00	70.00	25.00	35.00
IM0761-226		I76/SH52 Interchange	04/02/20	10.00	330.00	96.57	117.66
FSA1602-159		US 160 AND SH 17 INTERSECTION	04/30/20	10.00	50.00	67.33	39.00
ITS SW02-303		R1: US 285, SH 83 R2: SH 83,	05/28/20	325.00	65.00	48.34	0.10
	WEIGHTED AVERAGE FOR THE SECOND QUARTER			345.00	72.25	50.63	4.64
	WEIGHTED AVERAGE FOR THE YEAR			355.00	72.18	50.34	5.49
===== 208-00053		Storm Drain Inlet Protect (Ty I) (84 In)		Each	=====		
FSA0341-097		US 34 & MACGREGOR INTERSECTIO	01/09/20	15.00	208.00	200.00	200.00
NHPP 0852-116		US85:HAMPDEN TO FLORIDA-RESUR	02/06/20	3.00	200.00	425.00	200.00
FSA2873-194		US 287 Longmont Intersection	02/13/20	1.00	200.00	293.17	124.00
NH050A-034		US50A PUEBLO WEST PURCELL INT	03/26/20	8.00	180.00	325.55	140.00
	WEIGHTED AVERAGE FOR THE FIRST QUARTER			27.00	198.52	309.28	179.41
NH050A-035		US 50A Pueblo Regional Pond	05/28/20	2.00	55.00	231.19	72.00

COLORADO DEPARTMENT OF TRANSPORTATION
ITEM UNIT COSTS BY PROJECTS -- 2020 COST DATA

10:58 Friday, October 2, 2020 67

PROJECT NUMBER	ITEM NUMBER/ PROJECT LOCATION	ITEM DESCRIPTION/ PROJECT LOCATION	DATE LET	UNIT/ QUANTITY	ENGR. EST.	AVERAGE BID	AWARDED BID
===== 208-00053 Storm Drain Inlet Protect (Ty I) (84 In) Each =====							
NH050A-037		US 50A Pueblo Regional Pond					
FSAR400-356		FY 20 SIGNAL POLE REPLACEMENT	06/11/20	1.00	200.00	171.67	190.00
NHPPR100-251		SH 2/ Vasquez	06/25/20	1.00	200.00	1274.15	2355.30
	WEIGHTED AVERAGE FOR THE SECOND QUARTER			4.00	127.50	322.01	672.33
	WEIGHTED AVERAGE FOR THE YEAR			31.00	189.35	311.66	243.01
===== 208-00054 Storm Drain Inlet Protection (Type II) Each =====							
NHPP 0852-116		US85:HAMPDEN TO FLORIDA-RESUR	02/06/20	69.00	250.00	387.50	300.00
NHPP4701-134		C-470 NOISE WALL WEST OF LUCE	02/06/20	5.00	200.00	267.00	200.00
FSA2873-194		US 287 Longmont Intersection	02/13/20	6.00	300.00	286.67	360.00
NHPP0091-044		SH 9 FRISCO MAIN ST TO IRON S	03/05/20	6.00	100.00	546.67	210.00
HPP 0501-067		US 50 AND SH 92 DELTA INTERSE	03/26/20	15.00	50.00	369.55	345.00
SHE 0703-461		I-70 and Kipling North Phase	03/26/20	34.00	250.00	257.00	250.00
	WEIGHTED AVERAGE FOR THE FIRST QUARTER			135.00	221.48	323.95	287.37
C1601-082		Hawkins Signal and Curb Ramps	04/30/20	6.00	250.00	276.67	295.00
FSAR400-356		FY 20 SIGNAL POLE REPLACEMENT	06/11/20	3.00	250.00	200.67	177.00
	WEIGHTED AVERAGE FOR THE SECOND QUARTER			9.00	250.00	251.33	255.67
	WEIGHTED AVERAGE FOR THE YEAR			144.00	223.26	319.53	285.39
===== 208-00055 Rigid Inlet Prot Device Each =====							
STA0703-443		I-70 EJMT TUNNELS PAVING	02/06/20	220.00	25.00	79.66	80.06
	WEIGHTED AVERAGE FOR THE FIRST QUARTER			220.00	25.00	79.66	80.06
FSA1602-159		US 160 AND SH 17 INTERSECTION	04/30/20	3.00	50.00	367.00	177.00
	WEIGHTED AVERAGE FOR THE SECOND QUARTER			3.00	50.00	367.00	177.00
	WEIGHTED AVERAGE FOR THE YEAR			223.00	25.34	85.41	81.36
===== 208-00056 Storm Drain Inlet Protection (Type III) Each =====							
FSA0341-097		US 34 & MACGREGOR INTERSECTIO	01/09/20	1.00	400.00	65.00	65.00

COLORADO DEPARTMENT OF TRANSPORTATION
ITEM UNIT COSTS BY PROJECTS -- 2020 COST DATA

10:58 Friday, October 2, 2020 68

PROJECT NUMBER	ITEM NUMBER/ PROJECT LOCATION	ITEM DESCRIPTION/ PROJECT LOCATION	DATE LET	UNIT/ QUANTITY	ENGR. EST.	AVERAGE BID	AWARDED BID
=====	208-00056	Storm Drain Inlet Protection (Type III)		Each	=====	=====	=====
NHPP 0852-116		US85:HAMPDEN TO FLORIDA-RESUR	02/06/20	3.00	500.00	650.00	300.00
HPP 0501-067		US 50 AND SH 92 DELTA INTERSE	03/26/20	9.00	80.00	354.03	290.00
		WEIGHTED AVERAGE FOR THE FIRST QUARTER		13.00	201.54	413.50	275.00
IM0761-226		I76/SH52 Interchange	04/02/20	10.00	350.00	307.02	295.74
SFTY2254-091		225 Ramp Improvements	04/09/20	8.00	300.00	307.50	265.00
NHPP0253-276		I-25 EXPRESS LANES SEGMENT 5	05/15/20	6.00	350.00	352.83	352.83
FSAR400-356		FY 20 SIGNAL POLE REPLACEMENT	06/11/20	5.00	250.00	254.33	200.00
NHPPR100-251		SH 2/ Vasquez	06/25/20	7.00	350.00	405.63	43.25
		WEIGHTED AVERAGE FOR THE SECOND QUARTER		36.00	325.00	314.23	236.03
		WEIGHTED AVERAGE FOR THE YEAR		49.00	292.24	331.23	246.37
=====	208-00057	Storm Drain Inlet Protect (Ty I) (144 In)		Each	=====	=====	=====
FSA2873-194		US 287 Longmont Intersection	02/13/20	1.00	250.00	384.83	211.00
NH050A-034		US50A PUEBLO WEST PURCELL INT	03/26/20	3.00	300.00	409.34	240.00
		WEIGHTED AVERAGE FOR THE FIRST QUARTER		4.00	287.50	404.44	232.75
FSAR400-356		FY 20 SIGNAL POLE REPLACEMENT	06/11/20	1.00	300.00	223.33	268.00
		WEIGHTED AVERAGE FOR THE SECOND QUARTER		1.00	300.00	223.33	268.00
		WEIGHTED AVERAGE FOR THE YEAR		5.00	290.00	387.97	239.80
=====	208-00058	Storm Drain Inlet Protect (Ty I) (204 In)		Each	=====	=====	=====
NH050A-034		US50A PUEBLO WEST PURCELL INT	03/26/20	2.00	430.00	467.67	300.00
		WEIGHTED AVERAGE FOR THE FIRST QUARTER		2.00	430.00	467.67	300.00
		WEIGHTED AVERAGE FOR THE YEAR		2.00	430.00	467.67	300.00
=====	208-00070	Vehicle Tracking Pad		Each	=====	=====	=====
FSA0253-262		I-25 SB BOTTLENECK I-76 TO I-	01/09/20	2.00	2500.00	3378.95	2600.00

PROJECT NUMBER	ITEM NUMBER/ PROJECT LOCATION	ITEM DESCRIPTION/ PROJECT LOCATION	DATE LET	UNIT/ QUANTITY	ENGR. EST.	AVERAGE BID	AWARDED BID
===== 208-00070		Vehicle Tracking Pad		Each =====			
FSA0341-097		US 34 & MACGREGOR INTERSECTIO	01/09/20	1.00	3000.00	2500.00	2500.00
NHPP0343-041		I-76 & US 34 FT. MORGAN AREA	01/09/20	2.00	2000.00	4019.81	3476.00
NH 0503-093		US50 WEST OF TEXAS CREEK MP 2	01/23/20	2.00	2000.00	2337.69	3675.37
PWQM240-172		El Paso County, north Colorad	01/23/20	14.00	3000.00	3547.00	5294.00
NHPP 0852-116		US85:HAMPDEN TO FLORIDA-RESUR	02/06/20	1.00	3000.00	3750.00	2500.00
NHPP4701-134		C-470 NOISE WALL WEST OF LUCE	02/06/20	3.00	2000.00	2840.00	2500.00
STA069A-033		SH69 MP 58.7 TO 71.58	02/13/20	2.00	2600.00	1899.97	1200.00
NHPP0171-105		SH 17 MP 84.5 to US 285 & SH	03/05/20	4.00	1500.00	2213.75	3641.26
BR025A-046		K-18-U ON I-25 AT MP112 BRIDG	03/05/20	3.00	2500.00	2425.27	1294.25
NHPP0091-044		SH 9 FRISCO MAIN ST TO IRON S	03/05/20	1.00	1000.00	6573.33	12000.00
NH050A-034		US50A PUEBLO WEST PURCELL INT	03/26/20	4.00	2600.00	4703.46	2100.00
SHE 0703-461		I-70 and Kipling North Phase	03/26/20	1.00	3000.00	2415.00	3025.00
		WEIGHTED AVERAGE FOR THE FIRST QUARTER		40.00	2502.50	3403.31	3759.79
NHPP1602-169		US 160 WC TUNNEL EAST RESURFA	04/02/20	1.00	3500.00	2533.11	3954.46
IM0252-473		I-25 CABLE BARRIER PHASE IV	04/09/20	4.00	2000.00	2812.50	3125.00
SFTY2254-091		225 Ramp Improvements	04/09/20	2.00	2500.00	4387.50	3775.00
CC0852-106		US-85 LOUVIERS TO MP 191.75	04/23/20	6.00	3000.00	2933.94	2145.00
FBR0852-108		US-85 BETWEEN LOUVIERS AND MP					
FSA1602-159		US 160 AND SH 17 INTERSECTION	04/30/20	2.00	2000.00	3438.33	3010.00
NHPP0253-276		I-25 EXPRESS LANES SEGMENT 5	05/15/20	4.00	4000.00	3468.06	3468.06
NH050A-035		US 50A Pueblo Regional Pond	05/28/20	5.00	2500.00	2227.25	1000.00
NH050A-037		US 50A Pueblo Regional Pond					
		WEIGHTED AVERAGE FOR THE SECOND QUARTER		24.00	2791.67	2761.69	2573.61
		WEIGHTED AVERAGE FOR THE YEAR		64.00	2610.94	3115.60	3314.97
===== 208-00071		Maint Aggregate (Veh Track Pad)		Cubic Yard =====			
NHPP0091-044		SH 9 FRISCO MAIN ST TO IRON S	03/05/20	10.00	50.00	143.33	200.00
		WEIGHTED AVERAGE FOR THE FIRST QUARTER		10.00	50.00	143.33	200.00
NHPP1602-169		US 160 WC TUNNEL EAST RESURFA	04/02/20	50.00	100.00	64.16	124.57
CC0852-106		US-85 LOUVIERS TO MP 191.75	04/23/20	50.00	75.00	114.68	68.26
FBR0852-108		US-85 BETWEEN LOUVIERS AND MP					
NHPP0253-276		I-25 EXPRESS LANES SEGMENT 5	05/15/20	150.00	100.00	111.69	111.69
		WEIGHTED AVERAGE FOR THE SECOND QUARTER		250.00	95.00	103.21	105.58
		WEIGHTED AVERAGE FOR THE YEAR		260.00	93.27	104.86	109.21

PROJECT NUMBER	ITEM NUMBER/ PROJECT LOCATION	ITEM DESCRIPTION/ PROJECT LOCATION	DATE LET	UNIT/ QUANTITY	ENGR. EST.	AVERAGE BID	AWARDED BID
===== 208-00075		Pre-fab Vehicle Track Pad		Each	=====		
STA0142-066		SH 14 New Raymer West	01/09/20	1.00	4750.00	2218.25	2800.00
FSA0341-097		US 34 & MACGREGOR INTERSECTIO	01/09/20	1.00	1800.00	3750.00	3750.00
BR0343-040		US 34 REPUBLICAN RIVER BRIDGE	01/16/20	2.00	3000.00	4647.95	5740.00
FBR0343-043		US 34 D-28-P STRUCTURE REPLAC					
STA006A-067		SH 6 Merino to Atwood	01/16/20	1.00	2500.00	2750.08	2700.00
STR012A-050		CULVERT REPAIR I-25 AND US 35	01/30/20	9.00	3500.00	900.00	900.00
STA059A-036		SH 59 SEIBERT TO COPE	02/06/20	1.00	2000.00	2650.00	2800.00
STR116A-001		SH 116 A Surface Treatment Pr	02/13/20	2.00	1000.00	5199.97	1000.00
FSA2873-194		US 287 Longmont Intersection	02/13/20	2.00	2000.00	3075.00	2500.00
STR0101-027		SH 10 Overlay La Junta West	02/27/20	2.00	5000.00	2633.27	1000.00
STR2871-038		US 287 Passing Lanes Springfi	03/05/20	4.00	5000.00	8612.75	11700.00
SHE 0703-461		I-70 and Kipling North Phase	03/26/20	2.00	1500.00	5258.00	2750.00
		WEIGHTED AVERAGE FOR THE FIRST QUARTER		27.00	3242.59	4065.00	3441.85
IM0761-226		I76/SH52 Interchange	04/02/20	3.00	4000.00	8189.67	1959.00
STA340A-021		SH340 MP 6-6.76 MESA COUNTY	04/02/20	2.00	2500.00	5133.33	250.00
C1601-082		Hawkins Signal and Curb Ramps	04/30/20	2.00	1200.00	4833.33	3600.00
C0853-112		US85 & WCR98 INTERSECTION IMP	05/07/20	2.00	2000.00	7615.63	4200.00
FBR0343-042		US 34 D-27-G STRUCTURE REPLAC	05/07/20	2.00	3000.00	3197.51	3900.00
IM025A-048		Northbound I-25 bridge at Exi	05/28/20	1.00	5475.00	5816.33	5000.00
		WEIGHTED AVERAGE FOR THE SECOND QUARTER		12.00	2906.25	6123.39	2898.08
		WEIGHTED AVERAGE FOR THE YEAR		39.00	3139.10	5079.70	3274.54
===== 208-00090		Erosion Control (Curb Ramp)		Each	=====		
STRR300-249		Grand and Jackson Counties AD	03/05/20	148.00	300.00	361.00	290.00
CC080-037		VARIOUS ADA RAMPS ALONG NORTH	03/05/20	36.00	300.00	172.57	200.00
		WEIGHTED AVERAGE FOR THE FIRST QUARTER		184.00	300.00	314.85	272.39
		WEIGHTED AVERAGE FOR THE YEAR		184.00	300.00	314.85	272.39
===== 208-00103		Removal and Disposal of Sediment (Labor)		Hour	=====		
STA0142-066		SH 14 New Raymer West	01/09/20	50.00	45.00	52.75	40.00
FSA0253-262		I-25 SB BOTTLENECK I-76 TO I-	01/09/20	16.00	65.00	83.03	60.00

PROJECT NUMBER	ITEM NUMBER/ PROJECT LOCATION	ITEM DESCRIPTION/ PROJECT LOCATION	DATE LET	UNIT/ QUANTITY	ENGR. EST.	AVERAGE BID	AWARDED BID
=====	208-00103	Removal and Disposal of Sediment (Labor)		Hour =====			
NHPP0253-265		I-25 AT ERIE PARKWAY ON AND O	01/09/20	8.00	75.00	73.33	70.00
FSA0341-097		US 34 & MACGREGOR INTERSECTIO	01/09/20	20.00	54.00	75.00	75.00
NHPP0343-041		I-76 & US 34 FT. MORGAN AREA	01/09/20	204.50	50.00	82.36	44.00
BR0343-040		US 34 REPUBLICAN RIVER BRIDGE	01/16/20	50.00	55.00	53.41	35.00
FBR0343-043		US 34 D-28-P STRUCTURE REPLAC					
STA006A-067		SH 6 Merino to Atwood	01/16/20	50.00	45.00	91.00	126.00
STR131A-038		SH 131 MP 51.95-55.73, ROUTT	01/16/20	40.00	40.00	36.75	38.50
NH 0503-093		US50 WEST OF TEXAS CREEK MP 2	01/23/20	40.00	50.00	56.26	52.51
PWQM240-172		El Paso County, north Colorad	01/23/20	16.00	75.00	125.50	219.00
NHPP 0852-116		US85:HAMPDEN TO FLORIDA-RESUR	02/06/20	30.00	65.00	62.50	60.00
STA0703-443		I-70 EJMT TUNNELS PAVING	02/06/20	24.00	70.00	224.49	203.97
NHPP4701-134		C-470 NOISE WALL WEST OF LUCE	02/06/20	20.00	50.00	60.60	50.00
STA059A-036		SH 59 SEIBERT TO COPE	02/06/20	40.00	50.00	53.00	46.00
FSA2873-194		US 287 Longmont Intersection	02/13/20	70.00	60.00	88.83	50.00
STA069A-033		SH69 MP 58.7 TO 71.58	02/13/20	50.00	52.00	58.50	65.00
NHPP0702-359		I-70 No Name Tunnel Lighting	02/27/20	16.00	60.00	120.64	60.00
C0402-094		US 40 GRAND COUNTY SIGNAL REP	02/27/20	50.00	60.00	40.00	60.00
NH0242-085		US 24 M.P. 291.38 to M.P. 296	02/27/20	40.00	50.00	106.23	170.00
NHPP0171-105		SH 17 MP 84.5 to US 285 & SH	03/05/20	80.00	60.00	51.00	50.00
C0641-106		SH 64 Meeker West Rural Resur	03/05/20	30.00	40.00	36.00	37.00
NHPP145A-080		SH 145 Keystone-Placerville R	03/05/20	20.00	55.00	54.00	54.00
STR2871-038		US 287 Passing Lanes Springfi	03/05/20	50.00	50.00	59.25	58.50
NHPP0502-082		US 50 MONTROSE RE CHIP SEAL	03/05/20	20.00	50.00	43.50	35.00
BR025A-046		K-18-U ON I-25 AT MP112 BRIDG	03/05/20	40.00	55.00	57.24	62.71
NHPP0091-044		SH 9 FRISCO MAIN ST TO IRON S	03/05/20	100.00	60.00	51.12	51.00
HPP 0501-067		US 50 AND SH 92 DELTA INTERSE	03/26/20	108.00	60.00	46.75	43.70
SHE 0703-461		I-70 and Kipling North Phase	03/26/20	20.00	65.00	51.00	50.00
		WEIGHTED AVERAGE FOR THE FIRST QUARTER		1,302.50	54.48	67.45	60.96
NHPP1602-169		US 160 WC TUNNEL EAST RESURFA	04/02/20	80.00	60.00	60.66	62.37
STR092A-030		SH92 MP 31.748-48.5,DELTA AND	04/02/20	40.00	50.00	30.65	32.50
IM0761-226		I76/SH52 Interchange	04/02/20	60.00	55.00	52.38	53.00
STA340A-021		SH340 MP 6-6.76 MESA COUNTY	04/02/20	16.00	55.00	32.67	20.00
STR0341-101		SH 34 North of Grandby Resurf	04/02/20	40.00	70.00	48.00	35.00
IM0252-473		I-25 CABLE BARRIER PHASE IV	04/09/20	60.00	40.00	70.00	100.00
NHPP1601-077		US 160 MP 29.750 - MP 34.891	04/09/20	8.00	50.00	54.67	50.00
SFTY2254-091		225 Ramp Improvements	04/09/20	48.00	65.00	53.50	45.00
CC0852-106		US-85 LOUVIERS TO MP 191.75	04/23/20	300.00	60.00	78.91	110.00
FBR0852-108		US-85 BETWEEN LOUVIERS AND MP					
C1211-090		SH-121 & 29th Ave / SH-121 &	04/23/20	30.00	60.00	73.08	58.00
C1601-082		Hawkins Signal and Curb Ramps	04/30/20	30.00	50.00	66.67	78.00
FSA1602-159		US 160 AND SH 17 INTERSECTION	04/30/20	10.00	60.00	88.33	96.00
C0853-112		US85 & WCR98 INTERSECTION IMP	05/07/20	24.00	50.00	47.00	35.00
NHPPR100-303		LONG MAST ARM SIGNALS PROJECT	05/07/20	8.00	70.00	56.67	42.00

PROJECT NUMBER	ITEM NUMBER/ PROJECT LOCATION	ITEM DESCRIPTION/ PROJECT LOCATION	DATE LET	UNIT/ QUANTITY	ENGR. EST.	AVERAGE BID	AWARDED BID
===== 208-00103							
		Removal and Disposal of Sediment (Labor)		Hour			
FBR0343-042		US 34 D-27-G STRUCTURE REPLAC	05/07/20	216.00	50.00	44.39	25.00
ITS SW02-304		ITS FIBER TO STATE BUILDINGS	05/14/20	100.00	60.00	54.25	19.00
NHPP0402-098		US 40 CHIP SEAL MP 126 TO MP	05/14/20	15.00	50.00	41.67	35.00
NHPP0253-276		I-25 EXPRESS LANES SEGMENT 5	05/15/20	40.00	60.00	50.99	50.99
ITS SW02-303		R1: US 285, SH 83 R2: SH 83,	05/28/20	40.00	70.00	85.96	1.00
NH050A-035		US 50A Pueblo Regional Pond	05/28/20	200.00	50.00	51.35	45.00
NH050A-037		US 50A Pueblo Regional Pond					
ITSSW01-719		FY 20 ITS CAPITAL REPLACEMENT	06/11/20	50.00	60.00	42.50	10.00
FSAR400-356		FY 20 SIGNAL POLE REPLACEMENT	06/11/20	8.00	100.00	71.67	60.00
NHPPR100-251		SH 2/ Vasquez	06/25/20	10.00	75.00	87.68	113.35
	WEIGHTED AVERAGE FOR THE SECOND QUARTER			1,433.00	56.29	59.27	55.82
	WEIGHTED AVERAGE FOR THE YEAR			2,735.50	55.43	61.90	58.27
===== 208-00105							
		Removal and Disposal of Sediment (Equip)		Hour			
STA0142-066		SH 14 New Raymer West	01/09/20	50.00	85.00	95.75	80.00
FSA0253-262		I-25 SB BOTTLENECK I-76 TO I-	01/09/20	16.00	100.00	235.64	250.00
NHPP0253-265		I-25 AT ERIE PARKWAY ON AND O	01/09/20	8.00	150.00	132.33	92.00
NHPP0343-041		I-76 & US 34 FT. MORGAN AREA	01/09/20	205.00	100.00	164.67	185.00
BR0343-040		US 34 REPUBLICAN RIVER BRIDGE	01/16/20	100.00	110.00	113.50	105.00
FBR0343-043		US 34 D-28-P STRUCTURE REPLAC					
STA006A-067		SH 6 Merino to Atwood	01/16/20	50.00	85.00	153.51	195.00
STR131A-038		SH 131 MP 51.95-55.73, ROUTT	01/16/20	40.00	150.00	88.65	82.30
NH 0503-093		US50 WEST OF TEXAS CREEK MP 2	01/23/20	40.00	150.00	96.88	78.76
PWQM240-172		El Paso County, north Colorad	01/23/20	16.00	135.00	392.00	454.00
NHPP 0852-116		US85:HAMPDEN TO FLORIDA-RESUR	02/06/20	30.00	110.00	130.00	100.00
STA0703-443		I-70 EJMT TUNNELS PAVING	02/06/20	12.00	120.00	424.42	358.84
NHPP4701-134		C-470 NOISE WALL WEST OF LUCE	02/06/20	20.00	120.00	134.40	85.00
STA059A-036		SH 59 SEIBERT TO COPE	02/06/20	8.00	150.00	107.50	85.00
FSA2873-194		US 287 Longmont Intersection	02/13/20	20.00	130.00	143.00	150.00
STA069A-033		SH69 MP 58.7 TO 71.58	02/13/20	50.00	105.00	99.00	120.00
NHPP0702-359		I-70 No Name Tunnel Lighting	02/27/20	16.00	120.00	222.55	100.00
C0402-094		US 40 GRAND COUNTY SIGNAL REP	02/27/20	50.00	150.00	72.50	125.00
NH0242-085		US 24 M.P. 291.38 to M.P. 296	02/27/20	40.00	100.00	211.27	340.00
NHPP0171-105		SH 17 MP 84.5 to US 285 & SH	03/05/20	80.00	100.00	111.67	100.01
C0641-106		SH 64 Meeker West Rural Resur	03/05/20	30.00	150.00	90.00	100.00
NHPP145A-080		SH 145 Keystone-Placerville R	03/05/20	20.00	150.00	137.00	137.00
STR2871-038		US 287 Passing Lanes Springfi	03/05/20	50.00	150.00	152.75	175.50
BR025A-046		K-18-U ON I-25 AT MP112 BRIDG	03/05/20	40.00	120.00	123.20	117.43
NHPP0091-044		SH 9 FRISCO MAIN ST TO IRON S	03/05/20	100.00	150.00	103.33	130.00
SHE 0703-461		I-70 and Kipling North Phase	03/26/20	20.00	100.00	130.80	150.00
	WEIGHTED AVERAGE FOR THE FIRST QUARTER			1,111.00	118.24	134.41	147.58
NHPP1602-169		US 160 WC TUNNEL EAST RESURFA	04/02/20	80.00	150.00	139.91	148.14

PROJECT NUMBER	ITEM NUMBER/ PROJECT LOCATION	ITEM DESCRIPTION/ PROJECT LOCATION	DATE LET	UNIT/ QUANTITY	ENGR. EST.	AVERAGE BID	AWARDED BID
===== 208-00105		Removal and Disposal of Sediment (Equip)		Hour =====			
IM0761-226		I76/SH52 Interchange	04/02/20	60.00	110.00	111.97	212.00
STA340A-021		SH340 MP 6-6.76 MESA COUNTY	04/02/20	12.00	100.00	96.00	20.00
STR0341-101		SH 34 North of Grandby Resurf	04/02/20	40.00	150.00	100.01	78.80
IM0252-473		I-25 CABLE BARRIER PHASE IV	04/09/20	30.00	100.00	175.00	100.00
SFTY2254-091		225 Ramp Improvements	04/09/20	48.00	150.00	112.50	105.00
CC0852-106		US-85 LOUVIERS TO MP 191.75	04/23/20	150.00	130.00	161.29	275.00
FBR0852-108		US-85 BETWEEN LOUVIERS AND MP					
C1211-090		SH-121 & 29th Ave / SH-121 &	04/23/20	30.00	120.00	131.02	125.00
C1601-082		Hawkins Signal and Curb Ramps	04/30/20	30.00	125.00	169.67	169.00
FSA1602-159		US 160 AND SH 17 INTERSECTION	04/30/20	10.00	100.00	99.67	56.00
C0853-112		US85 & WCR98 INTERSECTION IMP	05/07/20	24.00	125.00	109.38	65.00
NHPPR100-303		LONG MAST ARM SIGNALS PROJECT	05/07/20	24.00	125.00	159.67	125.00
FBR0343-042		US 34 D-27-G STRUCTURE REPLAC	05/07/20	20.00	115.00	111.91	90.00
ITS SW02-304		ITS FIBER TO STATE BUILDINGS	05/14/20	100.00	120.00	101.50	50.00
NHPP0253-276		I-25 EXPRESS LANES SEGMENT 5	05/15/20	40.00	130.00	204.98	204.98
ITS SW02-303		R1: US 285, SH 83 R2: SH 83,	05/28/20	40.00	120.00	124.17	1.00
NH050A-035		US 50A Pueblo Regional Pond	05/28/20	200.00	50.00	123.81	75.00
NH050A-037		US 50A Pueblo Regional Pond					
ITSSW01-719		FY 20 ITS CAPITAL REPLACEMENT	06/11/20	50.00	135.00	42.50	10.00
FSAR400-356		FY 20 SIGNAL POLE REPLACEMENT	06/11/20	8.00	150.00	131.67	195.00
		WEIGHTED AVERAGE FOR THE SECOND QUARTER		996.00	112.55	129.40	123.79
		WEIGHTED AVERAGE FOR THE YEAR		2,107.00	115.55	131.43	136.34
===== 208-00106		Sweeping (Sediment Removal)		Hour =====			
STA0142-066		SH 14 New Raymer West	01/09/20	20.00	135.00	155.75	121.00
FSA0253-262		I-25 SB BOTTLENECK I-76 TO I-	01/09/20	12.00	160.00	206.24	130.00
NHPP0253-265		I-25 AT ERIE PARKWAY ON AND O	01/09/20	6.00	200.00	215.00	170.00
FSA0341-097		US 34 & MACGREGOR INTERSECTIO	01/09/20	80.00	150.00	120.00	120.00
NHPP0343-041		I-76 & US 34 FT. MORGAN AREA	01/09/20	750.00	125.00	169.21	153.00
BR0343-040		US 34 REPUBLICAN RIVER BRIDGE	01/16/20	100.00	130.00	159.17	90.00
FBR0343-043		US 34 D-28-P STRUCTURE REPLAC					
STA006A-067		SH 6 Merino to Atwood	01/16/20	20.00	135.00	265.71	285.00
STR131A-038		SH 131 MP 51.95-55.73, ROUTT	01/16/20	40.00	125.00	165.00	220.00
NH 0503-093		US50 WEST OF TEXAS CREEK MP 2	01/23/20	40.00	150.00	211.27	262.53
PWQM240-172		El Paso County, north Colorad	01/23/20	24.00	175.00	176.50	93.00
NHPP 0852-116		US85:HAMPDEN TO FLORIDA-RESUR	02/06/20	30.00	150.00	225.00	250.00
STA0703-443		I-70 EJMT TUNNELS PAVING	02/06/20	24.00	175.00	365.88	181.76
ITS0761-231		ITS FIBER AND CAMERAS ON I-76	02/06/20	20.00	150.00	99.48	75.00
NHPP4701-134		C-470 NOISE WALL WEST OF LUCE	02/06/20	40.00	150.00	176.60	148.00
STA059A-036		SH 59 SEIBERT TO COPE	02/06/20	144.00	140.00	148.50	127.00
FSA2873-194		US 287 Longmont Intersection	02/13/20	270.00	140.00	223.83	138.00
STA069A-033		SH69 MP 58.7 TO 71.58	02/13/20	20.00	155.00	191.00	200.00
NHPP0702-359		I-70 No Name Tunnel Lighting	02/27/20	20.00	125.00	176.74	150.00

PROJECT NUMBER	ITEM NUMBER/ PROJECT LOCATION	ITEM DESCRIPTION/ PROJECT LOCATION	DATE LET	UNIT/ QUANTITY	ENGR. EST.	AVERAGE BID	AWARDED BID
=====	208-00106	Sweeping (Sediment Removal)		Hour =====			
C0402-094		US 40 GRAND COUNTY SIGNAL REP	02/27/20	10.00	180.00	110.00	200.00
NH0242-085		US 24 M.P. 291.38 to M.P. 296	02/27/20	50.00	150.00	213.09	340.00
NHPP0171-105		SH 17 MP 84.5 to US 285 & SH	03/05/20	80.00	140.00	139.00	150.01
C0641-106		SH 64 Meeker West Rural Resur	03/05/20	20.00	125.00	161.50	110.00
NHPP145A-080		SH 145 Keystone-Placerville R	03/05/20	10.00	160.00	400.00	400.00
BR025A-046		K-18-U ON I-25 AT MP112 BRIDG	03/05/20	40.00	145.00	172.56	102.93
NHPP0091-044		SH 9 FRISCO MAIN ST TO IRON S	03/05/20	40.00	150.00	281.92	420.00
HPP 0501-067		US 50 AND SH 92 DELTA INTERSE	03/26/20	180.00	150.00	60.93	45.00
SHE 0703-461		I-70 and Kipling North Phase	03/26/20	40.00	150.00	169.40	225.00
		WEIGHTED AVERAGE FOR THE FIRST QUARTER		2,130.00	137.62	178.32	151.47
NHPP1602-169		US 160 WC TUNNEL EAST RESURFA	04/02/20	24.00	200.00	158.59	166.41
STR092A-030		SH92 MP 31.748-48.5, DELTA AND	04/02/20	40.00	150.00	139.50	132.00
IM0761-226		I76/SH52 Interchange	04/02/20	60.00	155.00	177.14	159.00
STA340A-021		SH340 MP 6-6.76 MESA COUNTY	04/02/20	30.00	110.00	123.67	20.00
STR0341-101		SH 34 North of Grandby Resurf	04/02/20	40.00	180.00	182.94	213.00
IM0252-473		I-25 CABLE BARRIER PHASE IV	04/09/20	30.00	155.00	125.00	100.00
SHER100-339		WWD TRAFFIC CONTROL ENHANCEME	04/09/20	60.00	165.00	20.00	20.00
NHPP1601-077		US 160 MP 29.750 - MP 34.891	04/09/20	8.00	350.00	170.00	150.00
SFTY2254-091		225 Ramp Improvements	04/09/20	60.00	175.00	212.50	125.00
CC0852-106		US-85 LOUVIERS TO MP 191.75	04/23/20	150.00	170.00	173.63	55.00
FBR0852-108		US-85 BETWEEN LOUVIERS AND MP					
C1211-090		SH-121 & 29th Ave / SH-121 &	04/23/20	38.00	160.00	214.00	186.00
FSA1602-159		US 160 AND SH 17 INTERSECTION	04/30/20	30.00	150.00	175.00	145.00
C0853-112		US85 & WCR98 INTERSECTION IMP	05/07/20	100.00	140.00	151.88	140.00
NHPPR100-303		LONG MAST ARM SIGNALS PROJECT	05/07/20	20.00	120.00	174.33	185.00
FBR0343-042		US 34 D-27-G STRUCTURE REPLAC	05/07/20	360.00	130.00	127.15	50.00
ITS SW02-304		ITS FIBER TO STATE BUILDINGS	05/14/20	150.00	150.00	101.50	79.00
NHPP0253-276		I-25 EXPRESS LANES SEGMENT 5	05/15/20	50.00	150.00	160.50	160.50
ITS SW02-303		R1: US 285, SH 83 R2: SH 83,	05/28/20	20.00	165.00	142.28	1.00
NH050A-035		US 50A Pueblo Regional Pond	05/28/20	200.00	50.00	136.69	75.00
NH050A-037		US 50A Pueblo Regional Pond					
IM025A-048		Northbound I-25 bridge at Exi	05/28/20	60.00	170.00	147.90	120.00
ITSSW01-719		FY 20 ITS CAPITAL REPLACEMENT	06/11/20	50.00	185.00	40.00	5.00
FSAR400-356		FY 20 SIGNAL POLE REPLACEMENT	06/11/20	6.00	200.00	195.00	195.00
SHE016A-043		SH 21 & 16 SIGNALS PROJECT	06/18/20	40.00	150.00	161.82	104.10
NHPPR100-251		SH 2/ Vasquez	06/25/20	100.00	150.00	147.08	128.15
		WEIGHTED AVERAGE FOR THE SECOND QUARTER		1,726.00	140.60	141.71	90.79
		WEIGHTED AVERAGE FOR THE YEAR		3,856.00	138.95	157.33	124.31
=====	208-00107	Rem Trash		Hour =====			
STA0142-066		SH 14 New Raymer West	01/09/20	20.00	45.00	81.25	45.00

PROJECT NUMBER	ITEM NUMBER/ PROJECT LOCATION	ITEM DESCRIPTION/ PROJECT LOCATION	DATE LET	UNIT/ QUANTITY	ENGR. EST.	AVERAGE BID	AWARDED BID
===== 208-00107							
		Rem Trash		Hour			
FSA0253-262		I-25 SB BOTTLENECK I-76 TO I-	01/09/20	10.00	100.00	185.12	250.00
FSA0341-097		US 34 & MACGREGOR INTERSECTIO	01/09/20	80.00	70.00	80.00	80.00
NHPP0343-041		I-76 & US 34 FT. MORGAN AREA	01/09/20	20.00	50.00	137.70	60.00
STA006A-067		SH 6 Merino to Atwood	01/16/20	20.00	45.00	99.50	115.00
STR131A-038		SH 131 MP 51.95-55.73, ROUTT	01/16/20	40.00	200.00	59.45	83.90
NH 0503-093		US50 WEST OF TEXAS CREEK MP 2	01/23/20	40.00	100.00	76.88	78.76
PWQM240-172		El Paso County, north Colorad	01/23/20	8.00	200.00	355.00	220.00
STR012A-050		CULVERT REPAIR I-25 AND US 35	01/30/20	20.00	110.00	69.00	69.00
NHPP 0852-116		US85:HAMPDEN TO FLORIDA-RESUR	02/06/20	30.00	100.00	180.00	60.00
STA0703-443		I-70 EJMT TUNNELS PAVING	02/06/20	12.00	100.00	234.94	194.88
NHPP4701-134		C-470 NOISE WALL WEST OF LUCE	02/06/20	35.00	120.00	134.20	54.00
STA059A-036		SH 59 SEIBERT TO COPE	02/06/20	40.00	60.00	68.00	61.00
STA069A-033		SH69 MP 58.7 TO 71.58	02/13/20	40.00	125.00	69.45	75.00
NHPP0702-359		I-70 No Name Tunnel Lighting	02/27/20	20.00	150.00	138.88	135.00
NH0242-085		US 24 M.P. 291.38 to M.P. 296	02/27/20	40.00	100.00	100.85	85.00
C0641-106		SH 64 Meeker West Rural Resur	03/05/20	15.00	200.00	58.70	37.00
BR025A-046		K-18-U ON I-25 AT MP112 BRIDG	03/05/20	40.00	100.00	82.02	71.17
NHPP0091-044		SH 9 FRISCO MAIN ST TO IRON S	03/05/20	40.00	100.00	190.00	170.00
NH050A-034		US50A PUEBLO WEST PURCELL INT	03/26/20	208.00	120.00	112.61	87.00
HPP 0501-067		US 50 AND SH 92 DELTA INTERSE	03/26/20	72.00	110.00	84.33	43.70
SHE 0703-461		I-70 and Kipling North Phase	03/26/20	10.00	112.00	106.40	210.00
WEIGHTED AVERAGE FOR THE FIRST QUARTER				860.00	108.14	110.57	86.12
NHPP1602-169		US 160 WC TUNNEL EAST RESURFA	04/02/20	12.00	185.00	144.54	234.82
STR092A-030		SH92 MP 31.748-48.5,DELTA AND	04/02/20	40.00	100.00	126.60	161.50
STA340A-021		SH340 MP 6-6.76 MESA COUNTY	04/02/20	28.00	70.00	56.50	10.00
STR0341-101		SH 34 North of Grandby Resurf	04/02/20	40.00	80.00	72.16	80.40
IM0252-473		I-25 CABLE BARRIER PHASE IV	04/09/20	20.00	110.00	41.88	43.75
SHER100-339		WWD TRAFFIC CONTROL ENHANCEME	04/09/20	30.00	150.00	50.00	50.00
CC0852-106		US-85 LOUVIERS TO MP 191.75	04/23/20	80.00	115.00	170.02	110.00
FBR0852-108		US-85 BETWEEN LOUVIERS AND MP					
FSA1602-159		US 160 AND SH 17 INTERSECTION	04/30/20	10.00	100.00	296.67	300.00
C0853-112		US85 & WCR98 INTERSECTION IMP	05/07/20	24.00	40.00	106.88	100.00
NHPPR100-303		LONG MAST ARM SIGNALS PROJECT	05/07/20	4.00	80.00	112.67	60.00
FBR0343-042		US 34 D-27-G STRUCTURE REPLAC	05/07/20	30.00	50.00	63.59	30.00
ITS SW02-304		ITS FIBER TO STATE BUILDINGS	05/14/20	100.00	90.00	46.25	19.00
ITS SW02-303		R1: US 285, SH 83 R2: SH 83,	05/28/20	20.00	120.00	104.18	1.00
NH050A-035		US 50A Pueblo Regional Pond	05/28/20	200.00	75.00	62.44	45.00
NH050A-037		US 50A Pueblo Regional Pond					
IM025A-048		Northbound I-25 bridge at Exi	05/28/20	60.00	120.00	108.33	110.00
NHPPR100-251		SH 2/ Vasquez	06/25/20	20.00	85.00	60.85	66.70
WEIGHTED AVERAGE FOR THE SECOND QUARTER				718.00	92.42	87.91	68.72
WEIGHTED AVERAGE FOR THE YEAR				1,578.00	100.99	98.46	78.20

PROJECT NUMBER	ITEM NUMBER/ PROJECT LOCATION	ITEM DESCRIPTION/ PROJECT LOCATION	DATE LET	UNIT/ QUANTITY	ENGR. EST.	AVERAGE BID	AWARDED BID
===== 208-00146		Pre-fab Conc Washout Str (Type 2)		Each			
FBR0343-042		US 34 D-27-G STRUCTURE REPLAC	05/07/20	4.00	2250.00	1908.29	750.00
		WEIGHTED AVERAGE FOR THE SECOND QUARTER		4.00	2250.00	1908.29	750.00
		WEIGHTED AVERAGE FOR THE YEAR		4.00	2250.00	1908.29	750.00
===== 208-00207		Erosion Control Management		Day			
FSA0341-097		US 34 & MACGREGOR INTERSECTIO	01/09/20	32.00	150.00	305.00	305.00
NHPP0343-041		I-76 & US 34 FT. MORGAN AREA	01/09/20	102.00	175.00	384.58	596.00
BR0343-040		US 34 REPUBLICAN RIVER BRIDGE	01/16/20	120.00	250.00	251.64	140.00
FBR0343-043		US 34 D-28-P STRUCTURE REPLAC					
NH 0503-093		US50 WEST OF TEXAS CREEK MP 2	01/23/20	60.00	200.00	252.51	105.01
PWQM240-172		El Paso County, north Colorad	01/23/20	90.00	200.00	626.00	922.00
ITS0761-231		ITS FIBER AND CAMERAS ON I-76	02/06/20	75.00	200.00	515.11	380.00
NHPP4701-134		C-470 NOISE WALL WEST OF LUCE	02/06/20	100.00	200.00	144.60	50.00
STR116A-001		SH 116 A Surface Treatment Pr	02/13/20	25.00	500.00	415.00	400.00
FSA2873-194		US 287 Longmont Intersection	02/13/20	36.00	200.00	334.17	165.00
NHPP0702-359		I-70 No Name Tunnel Lighting	02/27/20	35.00	600.00	630.65	435.00
NH0242-085		US 24 M.P. 291.38 to M.P. 296	02/27/20	90.00	215.00	206.01	400.00
NHPP0171-105		SH 17 MP 84.5 to US 285 & SH	03/05/20	80.00	250.00	521.68	600.03
STR2871-038		US 287 Passing Lanes Springfi	03/05/20	29.00	500.00	375.50	351.00
BR025A-046		K-18-U ON I-25 AT MP112 BRIDG	03/05/20	90.00	230.00	175.88	139.16
NHPP0091-044		SH 9 FRISCO MAIN ST TO IRON S	03/05/20	75.00	200.00	598.33	540.00
NH050A-034		US50A PUEBLO WEST PURCELL INT	03/26/20	131.00	210.00	281.04	427.00
HPP 0501-067		US 50 AND SH 92 DELTA INTERSE	03/26/20	36.00	280.00	262.55	280.00
SHE 0703-461		I-70 and Kipling North Phase	03/26/20	58.00	250.00	261.00	275.00
		WEIGHTED AVERAGE FOR THE FIRST QUARTER		1,264.00	237.33	317.60	372.21
IM0761-226		I76/SH52 Interchange	04/02/20	275.00	160.00	188.33	106.00
STA340A-021		SH340 MP 6-6.76 MESA COUNTY	04/02/20	24.00	150.00	470.67	1000.00
IM0252-473		I-25 CABLE BARRIER PHASE IV	04/09/20	30.00	230.00	218.75	62.50
SFTY2254-091		225 Ramp Improvements	04/09/20	40.00	250.00	209.00	238.00
CC0852-106		US-85 LOUVIERS TO MP 191.75	04/23/20	150.00	250.00	287.70	275.00
FBR0852-108		US-85 BETWEEN LOUVIERS AND MP					
FSA1602-159		US 160 AND SH 17 INTERSECTION	04/30/20	110.00	240.00	474.33	634.00
C0853-112		US85 & WCR98 INTERSECTION IMP	05/07/20	60.00	150.00	186.63	145.00
FBR0343-042		US 34 D-27-G STRUCTURE REPLAC	05/07/20	36.00	250.00	209.70	150.00
ITS SW02-303		R1: US 285, SH 83 R2: SH 83,	05/28/20	35.00	250.00	472.77	125.00
NH050A-035		US 50A Pueblo Regional Pond	05/28/20	108.00	350.00	192.69	50.00

PROJECT NUMBER	ITEM NUMBER/ PROJECT LOCATION	ITEM DESCRIPTION/ PROJECT LOCATION	DATE LET	UNIT/ QUANTITY	ENGR. EST.	AVERAGE BID	AWARDED BID
=====	208-00207	Erosion Control Management		Day	=====	=====	=====
NH050A-037		US 50A Pueblo Regional Pond					
	WEIGHTED AVERAGE FOR THE SECOND QUARTER			868.00	222.29	242.25	229.74
	WEIGHTED AVERAGE FOR THE YEAR			2,132.00	231.21	279.88	314.20
=====	208-00300	Temporary Berms		Lin Foot	=====	=====	=====
PWQM240-172		El Paso County, north Colorad	01/23/20	250.00	8.00	11.50	10.00
STA069A-033		SH69 MP 58.7 TO 71.58	02/13/20	100.00	1.00	25.98	20.00
NHPP0171-105		SH 17 MP 84.5 to US 285 & SH	03/05/20	75,000.00	1.00	1.76	3.03
	WEIGHTED AVERAGE FOR THE FIRST QUARTER			75,350.00	1.02	1.80	3.08
	WEIGHTED AVERAGE FOR THE YEAR			75,350.00	1.02	1.80	3.08
=====	208-00301	Temporary Diversion		Lin Foot	=====	=====	=====
HPP 0501-067		US 50 AND SH 92 DELTA INTERSE	03/26/20	123.00	276.00	100.30	180.00
	WEIGHTED AVERAGE FOR THE FIRST QUARTER			123.00	276.00	100.30	180.00
	WEIGHTED AVERAGE FOR THE YEAR			123.00	276.00	100.30	180.00
=====	208-00400	Water Control		LUMP SUM	=====	=====	=====
NHPP0091-044		SH 9 FRISCO MAIN ST TO IRON S	03/05/20	1.00	30000.00	95613.33	150000.00
NH050A-034		US50A PUEBLO WEST PURCELL INT	03/26/20	1.00	60000.00	116225.25	43000.00
	WEIGHTED AVERAGE FOR THE FIRST QUARTER			2.00	45000.00	110603.82	96500.00
NHPP0253-276		I-25 EXPRESS LANES SEGMENT 5	05/15/20	1.00	72000.00	65446.23	65446.23
	WEIGHTED AVERAGE FOR THE SECOND QUARTER			1.00	72000.00	65446.23	65446.23
	WEIGHTED AVERAGE FOR THE YEAR			3.00	54000.00	106840.69	86148.74
=====	210-00001	Res Structure		Each	=====	=====	=====
C1601-082		Hawkins Signal and Curb Ramps	04/30/20	1.00	1000.00	1098.33	2300.00
	WEIGHTED AVERAGE FOR THE SECOND QUARTER			1.00	1000.00	1098.33	2300.00
	WEIGHTED AVERAGE FOR THE YEAR			1.00	1000.00	1098.33	2300.00

COLORADO DEPARTMENT OF TRANSPORTATION
ITEM UNIT COSTS BY PROJECTS -- 2020 COST DATA

10:58 Friday, October 2, 2020 78

PROJECT NUMBER	ITEM NUMBER/ PROJECT LOCATION	ITEM DESCRIPTION/ PROJECT LOCATION	DATE LET	UNIT/ QUANTITY	ENGR. EST.	AVERAGE BID	AWARDED BID
===== 210-00002		Reset Structure		LUMP SUM	=====		
SHE 0703-461		I-70 and Kipling North Phase	03/26/20	1.00	10000.00	7318.80	9064.00
	WEIGHTED AVERAGE FOR THE FIRST QUARTER			1.00	10000.00	7318.80	9064.00
	WEIGHTED AVERAGE FOR THE YEAR			1.00	10000.00	7318.80	9064.00
===== 210-00010		Res Mailbox Str		Each	=====		
STA340A-021		SH340 MP 6-6.76 MESA COUNTY	04/02/20	1.00	500.00	476.67	1000.00
CC0852-106		US-85 LOUVIERS TO MP 191.75	04/23/20	7.00	375.00	427.37	423.50
FBR0852-108		US-85 BETWEEN LOUVIERS AND MP					
	WEIGHTED AVERAGE FOR THE SECOND QUARTER			8.00	390.63	429.87	495.56
	WEIGHTED AVERAGE FOR THE YEAR			8.00	390.63	429.87	495.56
===== 210-00011		Res Mailbox Str (Ty 1)		Each	=====		
NHPP0343-041		I-76 & US 34 FT. MORGAN AREA	01/09/20	81.00	241.00	169.76	181.00
STA006A-067		SH 6 Merino to Atwood	01/16/20	7.00	300.00	399.02	350.00
STA059A-036		SH 59 SEIBERT TO COPE	02/06/20	10.00	250.00	328.00	306.00
STR0101-027		SH 10 Overlay La Junta West	02/27/20	17.00	500.00	426.70	400.00
	WEIGHTED AVERAGE FOR THE FIRST QUARTER			115.00	283.66	229.14	234.53
STR092A-030		SH92 MP 31.748-48.5, DELTA AND	04/02/20	1.00	300.00	456.00	500.00
	WEIGHTED AVERAGE FOR THE SECOND QUARTER			1.00	300.00	456.00	500.00
	WEIGHTED AVERAGE FOR THE YEAR			116.00	283.80	230.52	236.82
===== 210-00012		Res Mailbox Str (Ty 2)		Each	=====		
NHPP0343-041		I-76 & US 34 FT. MORGAN AREA	01/09/20	14.00	333.00	190.89	204.00
STA059A-036		SH 59 SEIBERT TO COPE	02/06/20	3.00	500.00	400.50	381.00
	WEIGHTED AVERAGE FOR THE FIRST QUARTER			17.00	362.47	217.09	235.24
	WEIGHTED AVERAGE FOR THE YEAR			17.00	362.47	217.09	235.24

COLORADO DEPARTMENT OF TRANSPORTATION
 ITEM UNIT COSTS BY PROJECTS -- 2020 COST DATA

10:58 Friday, October 2, 2020 79

PROJECT NUMBER	ITEM NUMBER/ PROJECT LOCATION	ITEM DESCRIPTION/ PROJECT LOCATION	DATE LET	UNIT/ QUANTITY	ENGR. EST.	AVERAGE BID	AWARDED BID
===== 210-00013		Res Mailbox Str (Ty 3)		Each			
NHPP0343-041		I-76 & US 34 FT. MORGAN AREA	01/09/20	9.00	483.00	369.71	397.00
STR116A-001		SH 116 A Surface Treatment Pr	02/13/20	2.00	500.00	788.06	900.00
		WEIGHTED AVERAGE FOR THE FIRST QUARTER		11.00	486.09	445.78	488.45
STR092A-030		SH92 MP 31.748-48.5, DELTA AND	04/02/20	1.00	375.00	485.50	500.00
		WEIGHTED AVERAGE FOR THE SECOND QUARTER		1.00	375.00	485.50	500.00
		WEIGHTED AVERAGE FOR THE YEAR		12.00	476.83	448.05	489.42
===== 210-00015		Res End Section		Each			
STR2871-038		US 287 Passing Lanes Springfi	03/05/20	3.00	1000.00	1267.17	530.01
		WEIGHTED AVERAGE FOR THE FIRST QUARTER		3.00	1000.00	1267.17	530.01
		WEIGHTED AVERAGE FOR THE YEAR		3.00	1000.00	1267.17	530.01
===== 210-00060		Res Marker		Each			
SHE 0703-461		I-70 and Kipling North Phase	03/26/20	1.00	225.00	8320.00	11700.00
		WEIGHTED AVERAGE FOR THE FIRST QUARTER		1.00	225.00	8320.00	11700.00
		WEIGHTED AVERAGE FOR THE YEAR		1.00	225.00	8320.00	11700.00
===== 210-00090		Res Delineator		Each			
STA059A-036		SH 59 SEIBERT TO COPE	02/06/20	356.00	25.00	16.50	15.00
		WEIGHTED AVERAGE FOR THE FIRST QUARTER		356.00	25.00	16.50	15.00
IM0252-473		I-25 CABLE BARRIER PHASE IV	04/09/20	100.00	2.00	45.63	31.25
		WEIGHTED AVERAGE FOR THE SECOND QUARTER		100.00	2.00	45.63	31.25
		WEIGHTED AVERAGE FOR THE YEAR		456.00	19.96	22.89	18.56

COLORADO DEPARTMENT OF TRANSPORTATION
ITEM UNIT COSTS BY PROJECTS -- 2020 COST DATA

10:58 Friday, October 2, 2020 80

PROJECT NUMBER	ITEM NUMBER/ PROJECT LOCATION	ITEM DESCRIPTION/ PROJECT LOCATION	DATE LET	UNIT/ QUANTITY	ENGR. EST.	AVERAGE BID	AWARDED BID
=====	210-00200	Reset Flagpole		Each	=====	=====	=====
CC0852-106		US-85 LOUVIERS TO MP 191.75	04/23/20	1.00	650.00	1176.71	1650.00
FBR0852-108		US-85 BETWEEN LOUVIERS AND MP					
		WEIGHTED AVERAGE FOR THE SECOND QUARTER		1.00	650.00	1176.71	1650.00
		WEIGHTED AVERAGE FOR THE YEAR		1.00	650.00	1176.71	1650.00
=====	210-00300	Res Brick Pavers		Sq Yard	=====	=====	=====
STRR300-249		Grand and Jackson Counties AD	03/05/20	15.00	100.00	169.17	150.00
NHPP0091-044		SH 9 FRISCO MAIN ST TO IRON S	03/05/20	21.00	200.00	123.33	110.00
		WEIGHTED AVERAGE FOR THE FIRST QUARTER		36.00	158.33	142.43	126.67
		WEIGHTED AVERAGE FOR THE YEAR		36.00	158.33	142.43	126.67
=====	210-00425	Res Bridge Railing		Lin Foot	=====	=====	=====
NHPPR100-251		SH 2/ Vasquez	06/25/20	40.00	80.00	106.23	91.45
		WEIGHTED AVERAGE FOR THE SECOND QUARTER		40.00	80.00	106.23	91.45
		WEIGHTED AVERAGE FOR THE YEAR		40.00	80.00	106.23	91.45
=====	210-00427	Res Pipe Handrailing		Lin Foot	=====	=====	=====
HPP 0501-067		US 50 AND SH 92 DELTA INTERSE	03/26/20	29.00	30.00	42.90	43.50
		WEIGHTED AVERAGE FOR THE FIRST QUARTER		29.00	30.00	42.90	43.50
		WEIGHTED AVERAGE FOR THE YEAR		29.00	30.00	42.90	43.50
=====	210-00473	Res TV Cameras		Each	=====	=====	=====
NHPP0091-044		SH 9 FRISCO MAIN ST TO IRON S	03/05/20	1.00	1200.00	1223.33	1200.00
		WEIGHTED AVERAGE FOR THE FIRST QUARTER		1.00	1200.00	1223.33	1200.00
IM0761-226		I76/SH52 Interchange	04/02/20	1.00	1500.00	646.57	700.66

PROJECT NUMBER	ITEM NUMBER/ PROJECT LOCATION	ITEM DESCRIPTION/ PROJECT LOCATION	DATE LET	UNIT/ QUANTITY	ENGR. EST.	AVERAGE BID	AWARDED BID
===== 210-00473		Res TV Cameras		Each =====			
NHPPR100-303		LONG MAST ARM SIGNALS PROJECT	05/07/20	1.00	2500.00	679.33	460.00
	WEIGHTED AVERAGE FOR THE SECOND QUARTER			2.00	2000.00	656.40	580.33
	WEIGHTED AVERAGE FOR THE YEAR			3.00	1733.33	787.23	786.89
===== 210-00475		Res CCTV Pole		Each =====			
IM0761-226		I76/SH52 Interchange	04/02/20	1.00	1500.00	3175.71	3962.28
	WEIGHTED AVERAGE FOR THE SECOND QUARTER			1.00	1500.00	3175.71	3962.28
	WEIGHTED AVERAGE FOR THE YEAR			1.00	1500.00	3175.71	3962.28
===== 210-00476		Reset MVRD		Each =====			
SHE016A-043		SH 21 & 16 SIGNALS PROJECT	06/18/20	8.00	16000.00	714.20	350.00
	WEIGHTED AVERAGE FOR THE SECOND QUARTER			8.00	16000.00	714.20	350.00
	WEIGHTED AVERAGE FOR THE YEAR			8.00	16000.00	714.20	350.00
===== 210-00479		Res Radio Com Antenna		Each =====			
FSAR400-356		FY 20 SIGNAL POLE REPLACEMENT	06/11/20	3.00	850.00	796.67	950.00
SHE016A-043		SH 21 & 16 SIGNALS PROJECT	06/18/20	2.00	1000.00	574.10	338.50
	WEIGHTED AVERAGE FOR THE SECOND QUARTER			5.00	910.00	679.53	705.40
	WEIGHTED AVERAGE FOR THE YEAR			5.00	910.00	679.53	705.40
===== 210-00530		Rebuild Port of Present Str		Sq Foot =====			
NHPP 0852-116		US85:HAMPDEN TO FLORIDA-RESUR	02/06/20	16.00	550.00	760.00	420.00
STA059A-036		SH 59 SEIBERT TO COPE	02/06/20	40.00	125.00	229.00	218.00
	WEIGHTED AVERAGE FOR THE FIRST QUARTER			56.00	246.43	380.71	275.71
	WEIGHTED AVERAGE FOR THE YEAR			56.00	246.43	380.71	275.71
===== 210-00750		Res Light Standard		Each =====			
IM0761-226		I76/SH52 Interchange	04/02/20	10.00	1400.00	1550.30	1189.32
	WEIGHTED AVERAGE FOR THE SECOND QUARTER			10.00	1400.00	1550.30	1189.32
	WEIGHTED AVERAGE FOR THE YEAR			10.00	1400.00	1550.30	1189.32

PROJECT NUMBER	ITEM NUMBER/ PROJECT LOCATION	ITEM DESCRIPTION/ PROJECT LOCATION	DATE LET	UNIT/ QUANTITY	ENGR. EST.	AVERAGE BID	AWARDED BID
===== 210-00760		Res Luminaire		Each	=====	=====	=====
NHPP0091-044		SH 9 FRISCO MAIN ST TO IRON S	03/05/20	6.00	400.00	395.00	380.00
HPP 0501-067		US 50 AND SH 92 DELTA INTERSE	03/26/20	2.00	380.00	244.50	247.00
		WEIGHTED AVERAGE FOR THE FIRST QUARTER		8.00	395.00	367.64	346.75
		WEIGHTED AVERAGE FOR THE YEAR		8.00	395.00	367.64	346.75
===== 210-00810		Res Ground Sign		Each	=====	=====	=====
FSA0253-262		I-25 SB BOTTLENECK I-76 TO I-	01/09/20	1.00	400.00	1689.59	255.00
FSA0341-097		US 34 & MACGREGOR INTERSECTIO	01/09/20	3.00	230.00	325.00	325.00
NHPP0343-041		I-76 & US 34 FT. MORGAN AREA	01/09/20	5.00	295.00	317.04	340.00
BR0343-040		US 34 REPUBLICAN RIVER BRIDGE	01/16/20	12.00	300.00	348.67	500.00
FBR0343-043		US 34 D-28-P STRUCTURE REPLAC					
NHPP4701-134		C-470 NOISE WALL WEST OF LUCE	02/06/20	1.00	300.00	462.00	650.00
FSA2873-194		US 287 Longmont Intersection	02/13/20	5.00	300.00	366.67	275.00
NHPP0171-105		SH 17 MP 84.5 to US 285 & SH	03/05/20	138.00	175.00	224.60	193.81
BR025A-046		K-18-U ON I-25 AT MP112 BRIDG	03/05/20	4.00	300.00	301.86	290.92
STRR300-249		Grand and Jackson Counties AD	03/05/20	30.00	400.00	540.00	500.00
CC080-037		VARIOUS ADA RAMPS ALONG NORTH	03/05/20	7.00	400.00	224.38	50.00
NHPP0091-044		SH 9 FRISCO MAIN ST TO IRON S	03/05/20	36.00	400.00	440.00	500.00
NH050A-034		US50A PUEBLO WEST PURCELL INT	03/26/20	10.00	260.00	350.97	388.00
HPP 0501-067		US 50 AND SH 92 DELTA INTERSE	03/26/20	10.00	200.00	388.50	392.00
SHE 0703-461		I-70 and Kipling North Phase	03/26/20	4.00	400.00	351.00	165.00
		WEIGHTED AVERAGE FOR THE FIRST QUARTER		266.00	258.33	323.06	303.29
STR092A-030		SH92 MP 31.748-48.5, DELTA AND	04/02/20	5.00	250.00	490.00	450.00
IM0761-226		I76/SH52 Interchange	04/02/20	5.00	300.00	292.29	424.00
STA340A-021		SH340 MP 6-6.76 MESA COUNTY	04/02/20	7.00	280.00	562.50	1000.00
IM0252-473		I-25 CABLE BARRIER PHASE IV	04/09/20	10.00	300.00	456.25	437.50
SFTY2254-091		225 Ramp Improvements	04/09/20	4.00	400.00	720.00	700.00
C1601-082		Hawkins Signal and Curb Ramps	04/30/20	7.00	300.00	358.33	375.00
FSA1602-159		US 160 AND SH 17 INTERSECTION	04/30/20	2.00	300.00	628.67	322.00
C0853-112		US85 & WCR98 INTERSECTION IMP	05/07/20	2.00	250.00	180.88	150.00
NHPPR100-303		LONG MAST ARM SIGNALS PROJECT	05/07/20	2.00	255.00	367.67	120.00
FBR0343-042		US 34 D-27-G STRUCTURE REPLAC	05/07/20	8.00	300.00	266.72	500.00
NHPP0253-276		I-25 EXPRESS LANES SEGMENT 5	05/15/20	2.00	300.00	270.21	270.21
SHE016A-043		SH 21 & 16 SIGNALS PROJECT	06/18/20	8.00	320.00	453.00	593.00
		WEIGHTED AVERAGE FOR THE SECOND QUARTER		62.00	299.68	373.89	510.30
		WEIGHTED AVERAGE FOR THE YEAR		328.00	266.14	334.19	342.42

PROJECT NUMBER	ITEM NUMBER/ PROJECT LOCATION	ITEM DESCRIPTION/ PROJECT LOCATION	DATE LET	UNIT/ QUANTITY	ENGR. EST.	AVERAGE BID	AWARDED BID
===== 210-00815		Res Sign Panel		Each	=====		
FSA0253-262		I-25 SB BOTTLENECK I-76 TO I-	01/09/20	4.00	100.00	1083.97	26.00
NHPP0343-041		I-76 & US 34 FT. MORGAN AREA	01/09/20	8.00	150.00	212.03	227.00
NHPP 0852-116		US85:HAMPDEN TO FLORIDA-RESUR	02/06/20	1.00	350.00	100.00	100.00
FSA2873-194		US 287 Longmont Intersection	02/13/20	1.00	200.00	256.00	176.00
STA069A-033		SH69 MP 58.7 TO 71.58	02/13/20	7.00	120.00	138.34	150.00
NH0242-085		US 24 M.P. 291.38 to M.P. 296	02/27/20	5.00	195.00	291.02	370.00
NHPP0091-044		SH 9 FRISCO MAIN ST TO IRON S	03/05/20	5.00	50.00	204.67	270.00
NH050A-034		US50A PUEBLO WEST PURCELL INT	03/26/20	4.00	200.00	61.16	72.00
SHE 0703-461		I-70 and Kipling North Phase	03/26/20	29.00	450.00	232.00	140.00
		WEIGHTED AVERAGE FOR THE FIRST QUARTER		64.00	282.27	244.53	168.66
CC0852-106		US-85 LOUVIERS TO MP 191.75	04/23/20	23.00	400.00	99.06	93.50
FBR0852-108		US-85 BETWEEN LOUVIERS AND MP					
C1211-090		SH-121 & 29th Ave / SH-121 &	04/23/20	6.00	90.00	375.00	160.00
NHPPR100-303		LONG MAST ARM SIGNALS PROJECT	05/07/20	15.00	200.00	211.67	150.00
NHPP0402-098		US 40 CHIP SEAL MP 126 TO MP	05/14/20	3.00	165.00	341.67	500.00
SHE016A-043		SH 21 & 16 SIGNALS PROJECT	06/18/20	8.00	180.00	170.25	173.25
		WEIGHTED AVERAGE FOR THE SECOND QUARTER		55.00	266.82	149.96	149.94
		WEIGHTED AVERAGE FOR THE YEAR		119.00	275.13	194.63	160.00
===== 210-00816		Res Sign Panel (Spec)		Each	=====		
HPP 0501-067		US 50 AND SH 92 DELTA INTERSE	03/26/20	3.00	1000.00	442.50	225.00
		WEIGHTED AVERAGE FOR THE FIRST QUARTER		3.00	1000.00	442.50	225.00
SFTY2254-091		225 Ramp Improvements	04/09/20	2.00	4000.00	1500.00	1500.00
		WEIGHTED AVERAGE FOR THE SECOND QUARTER		2.00	4000.00	1500.00	1500.00
		WEIGHTED AVERAGE FOR THE YEAR		5.00	2200.00	865.50	735.00
===== 210-00825		Res Flashing Beacon		Each	=====		
FSA0341-097		US 34 & MACGREGOR INTERSECTIO	01/09/20	2.00	2000.00	2500.00	2500.00

PROJECT NUMBER	ITEM NUMBER/ PROJECT LOCATION	ITEM DESCRIPTION/ PROJECT LOCATION	DATE LET	UNIT/ QUANTITY	ENGR. EST.	AVERAGE BID	AWARDED BID
===== 210-00825		Res Flashing Beacon		Each =====			
FSA2873-194		US 287 Longmont Intersection	02/13/20	1.00	2500.00	4689.17	3000.00
	WEIGHTED AVERAGE FOR THE FIRST QUARTER			3.00	2166.67	4141.88	2666.67
	WEIGHTED AVERAGE FOR THE YEAR			3.00	2166.67	4141.88	2666.67
===== 210-00827		Res Pull Box		Each =====			
NHPP0343-041		I-76 & US 34 FT. MORGAN AREA	01/09/20	4.00	700.00	1249.33	1843.00
NHPP 0852-116		US85:HAMPDEN TO FLORIDA-RESUR	02/06/20	1.00	550.00	1591.00	1600.00
FSA2873-194		US 287 Longmont Intersection	02/13/20	1.00	800.00	1448.17	1400.00
NHPP0091-044		SH 9 FRISCO MAIN ST TO IRON S	03/05/20	13.00	1000.00	691.67	660.00
NH050A-034		US50A PUEBLO WEST PURCELL INT	03/26/20	2.00	1000.00	324.58	316.00
HPP 0501-067		US 50 AND SH 92 DELTA INTERSE	03/26/20	2.00	270.00	888.00	896.00
	WEIGHTED AVERAGE FOR THE FIRST QUARTER			23.00	856.09	792.19	929.39
IM0761-226		I76/SH52 Interchange	04/02/20	2.00	750.00	546.75	709.14
FSA1602-159		US 160 AND SH 17 INTERSECTION	04/30/20	1.00	350.00	1176.67	1050.00
	WEIGHTED AVERAGE FOR THE SECOND QUARTER			3.00	616.67	657.91	822.76
	WEIGHTED AVERAGE FOR THE YEAR			26.00	828.46	768.41	917.09
===== 210-00831		Res Traf Sig Head		Each =====			
FSA2873-194		US 287 Longmont Intersection	02/13/20	2.00	700.00	907.50	330.00
	WEIGHTED AVERAGE FOR THE FIRST QUARTER			2.00	700.00	907.50	330.00
NHPP0402-098		US 40 CHIP SEAL MP 126 TO MP	05/14/20	3.00	350.00	2826.67	5000.00
	WEIGHTED AVERAGE FOR THE SECOND QUARTER			3.00	350.00	2826.67	5000.00
	WEIGHTED AVERAGE FOR THE YEAR			5.00	490.00	1730.00	3132.00
===== 210-00840		Res Traf Sig Pole		Each =====			
NHPP0091-044		SH 9 FRISCO MAIN ST TO IRON S	03/05/20	1.00	4200.00	5366.67	5200.00
	WEIGHTED AVERAGE FOR THE FIRST QUARTER			1.00	4200.00	5366.67	5200.00
	WEIGHTED AVERAGE FOR THE YEAR			1.00	4200.00	5366.67	5200.00

COLORADO DEPARTMENT OF TRANSPORTATION
ITEM UNIT COSTS BY PROJECTS -- 2020 COST DATA

10:58 Friday, October 2, 2020 85

PROJECT NUMBER	ITEM NUMBER/ PROJECT LOCATION	ITEM DESCRIPTION/ PROJECT LOCATION	DATE LET	UNIT/ QUANTITY	ENGR. EST.	AVERAGE BID	AWARDED BID
=====	210-00855	Res Traf Sig Control Cab		Each	=====		
NHPPR100-303		LONG MAST ARM SIGNALS PROJECT	05/07/20	1.00	5000.00	3909.33	2365.00
FSAR400-356		FY 20 SIGNAL POLE REPLACEMENT	06/11/20	1.00	2500.00	6660.00	3650.00
SHE016A-043		SH 21 & 16 SIGNALS PROJECT	06/18/20	2.00	2000.00	2653.20	266.00
		WEIGHTED AVERAGE FOR THE SECOND QUARTER		4.00	2875.00	3640.00	1636.75
		WEIGHTED AVERAGE FOR THE YEAR		4.00	2875.00	3640.00	1636.75
=====	210-00858	Res Pedestal Pole		Each	=====		
HPP 0501-067		US 50 AND SH 92 DELTA INTERSE	03/26/20	1.00	800.00	999.00	1008.00
		WEIGHTED AVERAGE FOR THE FIRST QUARTER		1.00	800.00	999.00	1008.00
STA340A-021		SH340 MP 6-6.76 MESA COUNTY	04/02/20	6.00	700.00	1236.00	250.00
		WEIGHTED AVERAGE FOR THE SECOND QUARTER		6.00	700.00	1236.00	250.00
		WEIGHTED AVERAGE FOR THE YEAR		7.00	714.29	1212.30	358.29
=====	210-00860	Res Ped Push Button		Each	=====		
HPP 0501-067		US 50 AND SH 92 DELTA INTERSE	03/26/20	5.00	450.00	277.50	280.00
		WEIGHTED AVERAGE FOR THE FIRST QUARTER		5.00	450.00	277.50	280.00
		WEIGHTED AVERAGE FOR THE YEAR		5.00	450.00	277.50	280.00
=====	210-00865	Res Ped Sig Head		Each	=====		
NH050A-034		US50A PUEBLO WEST PURCELL INT	03/26/20	4.00	200.00	550.45	603.00
		WEIGHTED AVERAGE FOR THE FIRST QUARTER		4.00	200.00	550.45	603.00
		WEIGHTED AVERAGE FOR THE YEAR		4.00	200.00	550.45	603.00
=====	210-00867	Res Fire Preempt Unit		Each	=====		
FSA2873-194		US 287 Longmont Intersection	02/13/20	1.00	1000.00	1001.83	635.00

COLORADO DEPARTMENT OF TRANSPORTATION
 ITEM UNIT COSTS BY PROJECTS -- 2020 COST DATA

10:58 Friday, October 2, 2020 86

PROJECT NUMBER	ITEM NUMBER/ PROJECT LOCATION	ITEM DESCRIPTION/ PROJECT LOCATION	DATE LET	UNIT/ QUANTITY	ENGR. EST.	AVERAGE BID	AWARDED BID
===== 210-00867		Res Fire Preempt Unit		Each =====			
NHPP0091-044		SH 9 FRISCO MAIN ST TO IRON S	03/05/20	2.00	900.00	1848.33	1800.00
	WEIGHTED AVERAGE FOR THE FIRST QUARTER			3.00	933.33	1425.08	1411.67
C1211-090		SH-121 & 29th Ave / SH-121 &	04/23/20	3.00	1000.00	854.83	800.00
NHPPR100-303		LONG MAST ARM SIGNALS PROJECT	05/07/20	3.00	500.00	927.33	1090.00
	WEIGHTED AVERAGE FOR THE SECOND QUARTER			6.00	750.00	891.08	945.00
	WEIGHTED AVERAGE FOR THE YEAR			9.00	811.11	1104.68	1100.56
===== 210-00870		Res Coordination Unit		Each =====			
NHPP0091-044		SH 9 FRISCO MAIN ST TO IRON S	03/05/20	2.00	1000.00	880.00	850.00
HPP 0501-067		US 50 AND SH 92 DELTA INTERSE	03/26/20	1.00	500.00	666.00	672.00
	WEIGHTED AVERAGE FOR THE FIRST QUARTER			3.00	833.33	826.50	790.67
	WEIGHTED AVERAGE FOR THE YEAR			3.00	833.33	826.50	790.67
===== 210-00890		Res Int Detect Sys (Camera)		Each =====			
FSA2873-194		US 287 Longmont Intersection	02/13/20	1.00	1400.00	1495.50	1050.00
NH050A-034		US50A PUEBLO WEST PURCELL INT	03/26/20	1.00	1000.00	1641.21	1625.00
	WEIGHTED AVERAGE FOR THE FIRST QUARTER			2.00	1200.00	1578.76	1337.50
	WEIGHTED AVERAGE FOR THE YEAR			2.00	1200.00	1578.76	1337.50
===== 210-01000		Res Fence		Lin Foot =====			
NHPP0343-041		I-76 & US 34 FT. MORGAN AREA	01/09/20	24.00	25.00	28.44	34.00
NHPP0091-044		SH 9 FRISCO MAIN ST TO IRON S	03/05/20	315.00	15.00	12.43	12.00
	WEIGHTED AVERAGE FOR THE FIRST QUARTER			339.00	15.71	13.57	13.56
IM0761-226		I76/SH52 Interchange	04/02/20	302.00	30.00	11.00	10.39

COLORADO DEPARTMENT OF TRANSPORTATION
 ITEM UNIT COSTS BY PROJECTS -- 2020 COST DATA

10:58 Friday, October 2, 2020 87

PROJECT NUMBER	ITEM NUMBER/ PROJECT LOCATION	ITEM DESCRIPTION/ PROJECT LOCATION	DATE LET	UNIT/ QUANTITY	ENGR. EST.	AVERAGE BID	AWARDED BID
=====	210-01000	Res Fence		Lin Foot	=====		
CC0852-106		US-85 LOUVIERS TO MP 191.75	04/23/20	165.00	75.00	16.51	27.50
FBR0852-108		US-85 BETWEEN LOUVIERS AND MP					
FBR0343-042		US 34 D-27-G STRUCTURE REPLAC	05/07/20	100.00	40.00	19.10	22.00
NH050A-035		US 50A Pueblo Regional Pond	05/28/20	1,117.00	6.00	6.78	3.00
NH050A-037		US 50A Pueblo Regional Pond					
		WEIGHTED AVERAGE FOR THE SECOND QUARTER		1,684.00	19.08	9.26	7.85
		WEIGHTED AVERAGE FOR THE YEAR		2,023.00	18.52	9.56	8.81
=====	210-01010	Res Gate Post		Each	=====		
NHPP0091-044		SH 9 FRISCO MAIN ST TO IRON S	03/05/20	2.00	1000.00	473.33	460.00
		WEIGHTED AVERAGE FOR THE FIRST QUARTER		2.00	1000.00	473.33	460.00
		WEIGHTED AVERAGE FOR THE YEAR		2.00	1000.00	473.33	460.00
=====	210-01011	Res Gate		Each	=====		
NHPP0091-044		SH 9 FRISCO MAIN ST TO IRON S	03/05/20	1.00	500.00	490.00	470.00
		WEIGHTED AVERAGE FOR THE FIRST QUARTER		1.00	500.00	490.00	470.00
CC0852-106		US-85 LOUVIERS TO MP 191.75	04/23/20	3.00	450.00	367.57	440.00
FBR0852-108		US-85 BETWEEN LOUVIERS AND MP					
		WEIGHTED AVERAGE FOR THE SECOND QUARTER		3.00	450.00	367.57	440.00
		WEIGHTED AVERAGE FOR THE YEAR		4.00	462.50	381.17	447.50
=====	210-01050	Res C L Fence		Lin Foot	=====		
SHE 0703-461		I-70 and Kipling North Phase	03/26/20	400.00	20.00	17.00	13.00
		WEIGHTED AVERAGE FOR THE FIRST QUARTER		400.00	20.00	17.00	13.00
ITS SW02-303		R1: US 285, SH 83 R2: SH 83,	05/28/20	225.00	20.00	42.79	15.00
		WEIGHTED AVERAGE FOR THE SECOND QUARTER		225.00	20.00	42.79	15.00
		WEIGHTED AVERAGE FOR THE YEAR		625.00	20.00	26.29	13.72

COLORADO DEPARTMENT OF TRANSPORTATION
ITEM UNIT COSTS BY PROJECTS -- 2020 COST DATA

10:58 Friday, October 2, 2020 88

PROJECT NUMBER	ITEM NUMBER/ PROJECT LOCATION	ITEM DESCRIPTION/ PROJECT LOCATION	DATE LET	UNIT/ QUANTITY	ENGR. EST.	AVERAGE BID	AWARDED BID
===== 210-01130		Res Gdrail Ty 3		Lin Foot	=====		
IM0252-473		I-25 CABLE BARRIER PHASE IV	04/09/20	871.00	35.00	24.72	24.44
NHPPR100-251		SH 2/ Vasquez	06/25/20	25.00	40.00	118.35	60.70
		WEIGHTED AVERAGE FOR THE SECOND QUARTER		896.00	35.14	27.33	25.45
		WEIGHTED AVERAGE FOR THE YEAR		896.00	35.14	27.33	25.45
===== 210-01170		Res Gdrail Ty 7		Lin Foot	=====		
NHPP1602-169		US 160 WC TUNNEL EAST RESURFA	04/02/20	43.00	40.00	34.46	32.16
		WEIGHTED AVERAGE FOR THE SECOND QUARTER		43.00	40.00	34.46	32.16
		WEIGHTED AVERAGE FOR THE YEAR		43.00	40.00	34.46	32.16
===== 210-01190		Reset Tensioned Cable Barrier		Lin Foot	=====		
NH050A-034		US50A PUEBLO WEST PURCELL INT	03/26/20	7,040.00	20.00	17.70	17.60
		WEIGHTED AVERAGE FOR THE FIRST QUARTER		7,040.00	20.00	17.70	17.60
		WEIGHTED AVERAGE FOR THE YEAR		7,040.00	20.00	17.70	17.60
===== 210-01200		Res End Anchorage		Each	=====		
IM0252-473		I-25 CABLE BARRIER PHASE IV	04/09/20	3.00	1800.00	3472.22	3444.44
		WEIGHTED AVERAGE FOR THE SECOND QUARTER		3.00	1800.00	3472.22	3444.44
		WEIGHTED AVERAGE FOR THE YEAR		3.00	1800.00	3472.22	3444.44
===== 210-01710		Res Valve		Each	=====		
STA069A-033		SH69 MP 58.7 TO 71.58	02/13/20	9.00	500.00	1516.24	2500.00
		WEIGHTED AVERAGE FOR THE FIRST QUARTER		9.00	500.00	1516.24	2500.00
		WEIGHTED AVERAGE FOR THE YEAR		9.00	500.00	1516.24	2500.00

COLORADO DEPARTMENT OF TRANSPORTATION
 ITEM UNIT COSTS BY PROJECTS -- 2020 COST DATA

10:58 Friday, October 2, 2020 89

PROJECT NUMBER	ITEM NUMBER/ PROJECT LOCATION	ITEM DESCRIPTION/ PROJECT LOCATION	DATE LET	UNIT/ QUANTITY	ENGR. EST.	AVERAGE BID	AWARDED BID
=====	210-02003	Relay Pipe (3 In)		Lin Foot	=====		
FSA0253-262		I-25 SB BOTTLENECK I-76 TO I-	01/09/20	400.00	15.00	38.91	50.00
	WEIGHTED	AVERAGE FOR THE FIRST QUARTER		400.00	15.00	38.91	50.00
		WEIGHTED AVERAGE FOR THE YEAR		400.00	15.00	38.91	50.00
=====	210-02004	Relay Pipe (4 In)		Lin Foot	=====		
SFTY2254-091		225 Ramp Improvements	04/09/20	35.00	100.00	39.50	54.00
	WEIGHTED	AVERAGE FOR THE SECOND QUARTER		35.00	100.00	39.50	54.00
		WEIGHTED AVERAGE FOR THE YEAR		35.00	100.00	39.50	54.00
=====	210-02042	Relay Pipe (42 In)		Lin Foot	=====		
NHPP0253-276		I-25 EXPRESS LANES SEGMENT 5	05/15/20	60.00	320.00	417.44	417.44
	WEIGHTED	AVERAGE FOR THE SECOND QUARTER		60.00	320.00	417.44	417.44
		WEIGHTED AVERAGE FOR THE YEAR		60.00	320.00	417.44	417.44
=====	210-02510	Relay Sprinkler System		LUMP SUM	=====		
NHPP0091-044		SH 9 FRISCO MAIN ST TO IRON S	03/05/20	1.00	10000.00	15166.67	29600.00
	WEIGHTED	AVERAGE FOR THE FIRST QUARTER		1.00	10000.00	15166.67	29600.00
C1601-082		Hawkins Signal and Curb Ramps	04/30/20	1.00	8000.00	3783.33	2350.00
	WEIGHTED	AVERAGE FOR THE SECOND QUARTER		1.00	8000.00	3783.33	2350.00
		WEIGHTED AVERAGE FOR THE YEAR		2.00	9000.00	9475.00	15975.00
=====	210-02804	Grinding: Sidwlk and/or Curb Ramp Repair		Lin Foot	=====		
STRR300-249		Grand and Jackson Counties AD	03/05/20	137.00	30.00	59.83	34.00

PROJECT NUMBER	ITEM NUMBER/ PROJECT LOCATION	ITEM DESCRIPTION/ PROJECT LOCATION	DATE LET	UNIT/ QUANTITY	ENGR. EST.	AVERAGE BID	AWARDED BID
===== 210-02804 CC080-037		Grinding: Sidwlk and/or Curb Ramp Repair VARIOUS ADA RAMPS ALONG NORTH	03/05/20	Lin Foot 66.00	30.00	34.26	41.00
	WEIGHTED AVERAGE FOR THE FIRST QUARTER			203.00	30.00	49.83	36.28
	WEIGHTED AVERAGE FOR THE YEAR			203.00	30.00	49.83	36.28
===== 210-04010		Adj Manhole		Each			
FSA0341-097		US 34 & MACGREGOR INTERSECTIO	01/09/20	4.00	750.00	875.00	875.00
NHPP0343-041		I-76 & US 34 FT. MORGAN AREA	01/09/20	49.00	750.00	1287.60	1259.00
NHPP 0852-116		US85:HAMPDEN TO FLORIDA-RESUR	02/06/20	8.00	700.00	750.00	600.00
STA0703-443		I-70 EJMT TUNNELS PAVING	02/06/20	92.00	800.00	2131.88	2778.75
NHPP4701-134		C-470 NOISE WALL WEST OF LUCE	02/06/20	1.00	1000.00	941.80	729.00
STRR300-249		Grand and Jackson Counties AD	03/05/20	2.00	750.00	730.67	480.00
CC080-037		VARIOUS ADA RAMPS ALONG NORTH	03/05/20	2.00	750.00	561.25	310.00
NHPP0091-044		SH 9 FRISCO MAIN ST TO IRON S	03/05/20	18.00	1000.00	1661.67	1300.00
NH050A-034		US50A PUEBLO WEST PURCELL INT	03/26/20	4.00	2000.00	1183.96	2500.00
SHE 0703-461		I-70 and Kipling North Phase	03/26/20	1.00	700.00	1303.20	1166.00
	WEIGHTED AVERAGE FOR THE FIRST QUARTER			181.00	826.80	1615.53	2002.82
NHPP1602-169		US 160 WC TUNNEL EAST RESURFA	04/02/20	10.00	1700.00	2107.65	2480.98
STR092A-030		SH92 MP 31.748-48.5,DELTA AND	04/02/20	3.00	1500.00	964.50	1000.00
IM0761-226		I76/SH52 Interchange	04/02/20	7.00	1000.00	910.30	530.00
STR0341-101		SH 34 North of Grandby Resurf	04/02/20	2.00	750.00	1552.99	227.00
SFTY2254-091		225 Ramp Improvements	04/09/20	1.00	850.00	1337.50	1685.00
FSA1602-159		US 160 AND SH 17 INTERSECTION	04/30/20	3.00	1000.00	2103.33	755.00
	WEIGHTED AVERAGE FOR THE SECOND QUARTER			26.00	1301.92	1419.71	1381.68
	WEIGHTED AVERAGE FOR THE YEAR			207.00	886.47	1579.48	1924.81
===== 210-04015		Modify Manhole		Each			
NHPP0091-044		SH 9 FRISCO MAIN ST TO IRON S	03/05/20	1.00	5000.00	2440.00	3200.00
NH050A-034		US50A PUEBLO WEST PURCELL INT	03/26/20	1.00	2800.00	3251.50	6700.00
	WEIGHTED AVERAGE FOR THE FIRST QUARTER			2.00	3900.00	3030.18	4950.00
	WEIGHTED AVERAGE FOR THE YEAR			2.00	3900.00	3030.18	4950.00
===== 210-04016		Modify Manhole (Spec)		Each			
SHE 0703-461		I-70 and Kipling North Phase	03/26/20	1.00	1500.00	2575.00	4125.00
	WEIGHTED AVERAGE FOR THE FIRST QUARTER			1.00	1500.00	2575.00	4125.00
	WEIGHTED AVERAGE FOR THE YEAR			1.00	1500.00	2575.00	4125.00

COLORADO DEPARTMENT OF TRANSPORTATION
 ITEM UNIT COSTS BY PROJECTS -- 2020 COST DATA

10:58 Friday, October 2, 2020 91

PROJECT NUMBER	ITEM NUMBER/ PROJECT LOCATION	ITEM DESCRIPTION/ PROJECT LOCATION	DATE LET	UNIT/ QUANTITY	ENGR. EST.	AVERAGE BID	AWARDED BID
=====	210-04020	Modify Inlet		Each	=====		
NHPP0343-041		I-76 & US 34 FT. MORGAN AREA	01/09/20	18.00	2250.00	4185.00	4005.00
		WEIGHTED AVERAGE FOR THE FIRST QUARTER		18.00	2250.00	4185.00	4005.00
IM0761-226		I76/SH52 Interchange	04/02/20	1.00	2700.00	2955.06	2100.00
SFTY2254-091		225 Ramp Improvements	04/09/20	1.00	3500.00	4745.00	4890.00
		WEIGHTED AVERAGE FOR THE SECOND QUARTER		2.00	3100.00	3352.83	3495.00
		WEIGHTED AVERAGE FOR THE YEAR		20.00	2335.00	4066.12	3954.00
=====	210-04025	Modify Structure		Each	=====		
STRR300-249		Grand and Jackson Counties AD	03/05/20	3.00	7000.00	1259.67	870.00
		WEIGHTED AVERAGE FOR THE FIRST QUARTER		3.00	7000.00	1259.67	870.00
NHPPR100-251		SH 2/ Vasquez	06/25/20	1.00	5000.00	3375.15	3169.30
		WEIGHTED AVERAGE FOR THE SECOND QUARTER		1.00	5000.00	3375.15	3169.30
		WEIGHTED AVERAGE FOR THE YEAR		4.00	6500.00	1644.30	1444.83
=====	210-04050	Adj Valve Box		Each	=====		
NHPP0343-041		I-76 & US 34 FT. MORGAN AREA	01/09/20	45.00	393.00	676.45	824.00
NHPP 0852-116		US85:HAMPDEN TO FLORIDA-RESUR	02/06/20	4.00	450.00	425.00	250.00
STRR300-249		Grand and Jackson Counties AD	03/05/20	3.00	400.00	695.00	1000.00
CC080-037		VARIOUS ADA RAMPS ALONG NORTH	03/05/20	2.00	400.00	461.25	800.00
NHPP0091-044		SH 9 FRISCO MAIN ST TO IRON S	03/05/20	11.00	750.00	591.67	950.00
NH050A-034		US50A PUEBLO WEST PURCELL INT	03/26/20	1.00	800.00	698.61	1400.00
SHE 0703-461		I-70 and Kipling North Phase	03/26/20	2.00	300.00	714.20	583.00
		WEIGHTED AVERAGE FOR THE FIRST QUARTER		68.00	457.87	648.92	819.06
STR092A-030		SH92 MP 31.748-48.5, DELTA AND	04/02/20	6.00	1500.00	242.00	275.00

COLORADO DEPARTMENT OF TRANSPORTATION
ITEM UNIT COSTS BY PROJECTS -- 2020 COST DATA

10:58 Friday, October 2, 2020 92

PROJECT NUMBER	ITEM NUMBER/ PROJECT LOCATION	ITEM DESCRIPTION/ PROJECT LOCATION	DATE LET	UNIT/ QUANTITY	ENGR. EST.	AVERAGE BID	AWARDED BID
=====	210-04050	Adj Valve Box		Each =====			
IM0761-226		I76/SH52 Interchange	04/02/20	11.00	600.00	617.30	530.00
STA340A-021		SH340 MP 6-6.76 MESA COUNTY	04/02/20	9.00	350.00	443.33	350.00
C1601-082		Hawkins Signal and Curb Ramps	04/30/20	4.00	400.00	441.67	450.00
FSA1602-159		US 160 AND SH 17 INTERSECTION	04/30/20	1.00	300.00	1619.00	493.00
		WEIGHTED AVERAGE FOR THE SECOND QUARTER		31.00	666.13	553.91	416.87
		WEIGHTED AVERAGE FOR THE YEAR		99.00	523.08	612.53	693.12
=====	210-04060	Adj Water Meter		Each =====			
SHE 0703-461		I-70 and Kipling North Phase	03/26/20	1.00	300.00	2226.00	1090.00
		WEIGHTED AVERAGE FOR THE FIRST QUARTER		1.00	300.00	2226.00	1090.00
		WEIGHTED AVERAGE FOR THE YEAR		1.00	300.00	2226.00	1090.00
=====	210-04200	Adj Gdrail		Lin Foot =====			
NH 0503-093		US50 WEST OF TEXAS CREEK MP 2	01/23/20	12,941.00	10.00	6.94	5.88
NHPP145A-080		SH 145 Keystone-Placerville R	03/05/20	9,237.50	78472.50	7.30	7.30
		WEIGHTED AVERAGE FOR THE FIRST QUARTER		22,178.50	32690.18	7.03	6.47
		WEIGHTED AVERAGE FOR THE YEAR		22,178.50	32690.18	7.03	6.47
=====	211-02277	Cement Grout (Voids)		Cubic Yard =====			
STR012A-050		CULVERT REPAIR I-25 AND US 35	01/30/20	18.00	2000.00	1500.00	1500.00
		WEIGHTED AVERAGE FOR THE FIRST QUARTER		18.00	2000.00	1500.00	1500.00
		WEIGHTED AVERAGE FOR THE YEAR		18.00	2000.00	1500.00	1500.00
=====	211-03005	Dewatering		LUMP SUM =====			
BR0343-040		US 34 REPUBLICAN RIVER BRIDGE	01/16/20	1.00	15000.00	77422.50	96000.00
FBR0343-043		US 34 D-28-P STRUCTURE REPLAC					
PWQM240-172		El Paso County, north Colorad	01/23/20	1.00	250000.00	345000.00	400000.00
NH050A-034		US50A PUEBLO WEST PURCELL INT	03/26/20	1.00	15000.00	137125.60	50000.00

PROJECT NUMBER	ITEM NUMBER/ PROJECT LOCATION	ITEM DESCRIPTION/ PROJECT LOCATION	DATE LET	UNIT/ QUANTITY	ENGR. EST.	AVERAGE BID	AWARDED BID
=====	211-03005	Dewatering		LUMP SUM	=====	=====	=====
HPP 0501-067		US 50 AND SH 92 DELTA INTERSE	03/26/20	1.00	10000.00	7538.50	5855.00
		WEIGHTED AVERAGE FOR THE FIRST QUARTER		4.00	72500.00	125923.16	137963.75
FBR0343-042		US 34 D-27-G STRUCTURE REPLAC	05/07/20	1.00	25000.00	26949.12	15000.00
		WEIGHTED AVERAGE FOR THE SECOND QUARTER		1.00	25000.00	26949.12	15000.00
		WEIGHTED AVERAGE FOR THE YEAR		5.00	63000.00	92931.81	113371.00
=====	212-00006	Seeding (Native)		Acre	=====	=====	=====
STA0142-066		SH 14 New Raymer West	01/09/20	0.50	2500.00	3767.25	800.00
FSA0253-262		I-25 SB BOTTLENECK I-76 TO I-	01/09/20	0.60	850.00	1313.89	1210.00
NHPP0253-265		I-25 AT ERIE PARKWAY ON AND O	01/09/20	0.10	10000.00	8398.33	2720.00
FSA0341-097		US 34 & MACGREGOR INTERSECTIO	01/09/20	0.90	1500.00	825.00	825.00
NHPP0343-041		I-76 & US 34 FT. MORGAN AREA	01/09/20	3.20	950.00	970.96	1159.00
BR0343-040		US 34 REPUBLICAN RIVER BRIDGE	01/16/20	1.90	1200.00	1290.84	1050.00
FBR0343-043		US 34 D-28-P STRUCTURE REPLAC					
STR131A-038		SH 131 MP 51.95-55.73, ROUTT	01/16/20	0.30	3500.00	2005.00	1510.00
NH 0503-093		US50 WEST OF TEXAS CREEK MP 2	01/23/20	0.90	1000.00	1200.78	1101.56
PWQM240-172		El Paso County, north Colorad	01/23/20	11.10	1000.00	2987.50	875.00
STR012A-050		CULVERT REPAIR I-25 AND US 35	01/30/20	0.95	675.00	1600.00	1600.00
ITS0761-231		ITS FIBER AND CAMERAS ON I-76	02/06/20	36.30	1000.00	1182.65	540.00
NHPP4701-134		C-470 NOISE WALL WEST OF LUCE	02/06/20	6.10	1000.00	630.40	452.00
STA059A-036		SH 59 SEIBERT TO COPE	02/06/20	0.20	3000.00	1350.00	1200.00
STR116A-001		SH 116 A Surface Treatment Pr	02/13/20	0.30	2000.00	4897.00	9000.00
FSA2873-194		US 287 Longmont Intersection	02/13/20	0.50	2000.00	3060.89	4700.00
STA069A-033		SH69 MP 58.7 TO 71.58	02/13/20	0.50	1000.00	21369.21	40000.00
STR0101-027		SH 10 Overlay La Junta West	02/27/20	0.30	550.00	3847.17	6000.00
NHPP0702-359		I-70 No Name Tunnel Lighting	02/27/20	0.65	4000.00	1654.17	1200.00
C0402-094		US 40 GRAND COUNTY SIGNAL REP	02/27/20	0.10	3000.00	1100.00	1200.00
NHPP0171-105		SH 17 MP 84.5 to US 285 & SH	03/05/20	120.00	500.00	405.18	390.55
C0641-106		SH 64 Meeker West Rural Resur	03/05/20	0.20	2000.00	4550.00	8000.00
NHPP145A-080		SH 145 Keystone-Placerville R	03/05/20	0.49	5000.00	1250.00	1250.00
STR2871-038		US 287 Passing Lanes Springfi	03/05/20	10.00	500.00	1523.81	1037.79
BR025A-046		K-18-U ON I-25 AT MP112 BRIDG	03/05/20	1.00	800.00	2322.26	1621.19
NHPP0091-044		SH 9 FRISCO MAIN ST TO IRON S	03/05/20	5.80	2000.00	1296.67	1300.00
NH050A-034		US50A PUEBLO WEST PURCELL INT	03/26/20	39.00	1000.00	759.76	840.00
HPP 0501-067		US 50 AND SH 92 DELTA INTERSE	03/26/20	0.15	5000.00	4033.15	6820.00
		WEIGHTED AVERAGE FOR THE FIRST QUARTER		242.04	790.31	850.00	715.88
NHPP1602-169		US 160 WC TUNNEL EAST RESURFA	04/02/20	0.50	2500.00	2367.27	2097.29

PROJECT NUMBER	ITEM NUMBER/ PROJECT LOCATION	ITEM DESCRIPTION/ PROJECT LOCATION	DATE LET	UNIT/ QUANTITY	ENGR. EST.	AVERAGE BID	AWARDED BID
===== 212-00006		Seeding (Native)		Acre =====			
STR092A-030		SH92 MP 31.748-48.5, DELTA AND	04/02/20	0.50	2000.00	1690.00	1700.00
IM0761-226		I76/SH52 Interchange	04/02/20	21.30	630.00	591.03	500.11
STA340A-021		SH340 MP 6-6.76 MESA COUNTY	04/02/20	2.70	2000.00	1681.67	2500.00
IM0252-473		I-25 CABLE BARRIER PHASE IV	04/09/20	23.80	370.00	788.87	727.74
SHER100-339		WWD TRAFFIC CONTROL ENHANCEME	04/09/20	0.25	1000.00	500.00	500.00
SFTY2254-091		225 Ramp Improvements	04/09/20	1.70	1200.00	1420.00	840.00
CC0852-106		US-85 LOUVIERS TO MP 191.75	04/23/20	15.40	1000.00	577.35	473.00
FBR0852-108		US-85 BETWEEN LOUVIERS AND MP					
C1211-090		SH-121 & 29th Ave / SH-121 &	04/23/20	0.10	1000.00	15570.17	20240.00
C1601-082		Hawkins Signal and Curb Ramps	04/30/20	0.03	2000.00	8970.00	21000.00
FSA1602-159		US 160 AND SH 17 INTERSECTION	04/30/20	0.15	2000.00	2608.33	1870.00
C0853-112		US85 & WCR98 INTERSECTION IMP	05/07/20	3.90	1000.00	691.25	500.00
NHPPR100-303		LONG MAST ARM SIGNALS PROJECT	05/07/20	0.16	5000.00	6907.33	3472.00
ITS SW02-304		ITS FIBER TO STATE BUILDINGS	05/14/20	2.20	3000.00	3109.56	844.00
NHPP0253-276		I-25 EXPRESS LANES SEGMENT 5	05/15/20	17.00	600.00	624.24	624.24
ITS SW02-303		R1: US 285, SH 83 R2: SH 83,	05/28/20	13.40	1000.00	1758.10	0.10
NH050A-035		US 50A Pueblo Regional Pond	05/28/20	28.00	1000.00	744.34	400.00
NH050A-037		US 50A Pueblo Regional Pond					
ITSSW01-719		FY 20 ITS CAPITAL REPLACEMENT	06/11/20	1.60	3000.00	3023.75	1562.50
FSAR400-356		FY 20 SIGNAL POLE REPLACEMENT	06/11/20	0.04	15000.00	4144.67	4550.00
SHE016A-043		SH 21 & 16 SIGNALS PROJECT	06/18/20	0.42	5000.00	3444.49	1371.43
		WEIGHTED AVERAGE FOR THE SECOND QUARTER		133.15	889.41	859.44	584.50
		WEIGHTED AVERAGE FOR THE YEAR		375.19	825.48	853.87	669.25
===== 212-00007		Seeding (Native) (Hydraulic)		Acre =====			
CC0852-106		US-85 LOUVIERS TO MP 191.75	04/23/20	26.80	2000.00	892.70	731.50
FBR0852-108		US-85 BETWEEN LOUVIERS AND MP					
		WEIGHTED AVERAGE FOR THE SECOND QUARTER		26.80	2000.00	892.70	731.50
		WEIGHTED AVERAGE FOR THE YEAR		26.80	2000.00	892.70	731.50
===== 212-00009		Seeding (Temporary)		Acre =====			
NHPP0253-276		I-25 EXPRESS LANES SEGMENT 5	05/15/20	10.00	500.00	374.50	374.50
		WEIGHTED AVERAGE FOR THE SECOND QUARTER		10.00	500.00	374.50	374.50
		WEIGHTED AVERAGE FOR THE YEAR		10.00	500.00	374.50	374.50
===== 212-00028		Seeding (Wetlands)		Acre =====			
BR0343-040		US 34 REPUBLICAN RIVER BRIDGE	01/16/20	0.20	7500.00	5280.59	4500.00

PROJECT NUMBER	ITEM NUMBER/ PROJECT LOCATION	ITEM DESCRIPTION/ PROJECT LOCATION	DATE LET	UNIT/ QUANTITY	ENGR. EST.	AVERAGE BID	AWARDED BID
===== 212-00028		Seeding (Wetlands)		Acres			
FBR0343-043		US 34 D-28-P STRUCTURE REPLAC					
	WEIGHTED AVERAGE FOR THE FIRST QUARTER			0.20	7500.00	5280.59	4500.00
IM0761-226		I76/SH52 Interchange	04/02/20	0.50	3000.00	2770.45	3084.60
	WEIGHTED AVERAGE FOR THE SECOND QUARTER			0.50	3000.00	2770.45	3084.60
	WEIGHTED AVERAGE FOR THE YEAR			0.70	4285.71	3411.34	3489.00
===== 212-00032		Soil Conditioning		Acres			
FSA0253-262		I-25 SB BOTTLENECK I-76 TO I-	01/09/20	0.60	2800.00	3826.34	3510.00
NHPP0253-265		I-25 AT ERIE PARKWAY ON AND O	01/09/20	0.10	15000.00	28648.33	12700.00
FSA0341-097		US 34 & MACGREGOR INTERSECTIO	01/09/20	0.90	3000.00	5250.00	5250.00
NHPP0343-041		I-76 & US 34 FT. MORGAN AREA	01/09/20	3.20	1750.00	2584.50	2812.00
BR0343-040		US 34 REPUBLICAN RIVER BRIDGE	01/16/20	1.90	3500.00	3261.74	3300.00
FBR0343-043		US 34 D-28-P STRUCTURE REPLAC					
STR131A-038		SH 131 MP 51.95-55.73, ROUTT	01/16/20	0.30	3500.00	3175.00	1350.00
NH 0503-093		US50 WEST OF TEXAS CREEK MP 2	01/23/20	0.90	3000.00	2808.25	2616.49
PWQM240-172		El Paso County, north Colorad	01/23/20	7.10	3000.00	3552.50	3105.00
ITS0761-231		ITS FIBER AND CAMERAS ON I-76	02/06/20	36.30	3000.00	2777.94	2640.00
NHPP4701-134		C-470 NOISE WALL WEST OF LUCE	02/06/20	6.10	3000.00	3072.00	2850.00
STA059A-036		SH 59 SEIBERT TO COPE	02/06/20	0.20	5000.00	4500.00	3000.00
STR116A-001		SH 116 A Surface Treatment Pr	02/13/20	0.30	6000.00	6539.75	10000.00
FSA2873-194		US 287 Longmont Intersection	02/13/20	0.50	2500.00	4778.75	8500.00
STA069A-033		SH69 MP 58.7 TO 71.58	02/13/20	0.50	3100.00	32354.45	60000.00
STR0101-027		SH 10 Overlay La Junta West	02/27/20	0.30	2500.00	6497.86	7000.00
NHPP0702-359		I-70 No Name Tunnel Lighting	02/27/20	0.65	5000.00	4407.39	4725.00
C0402-094		US 40 GRAND COUNTY SIGNAL REP	02/27/20	0.10	5000.00	2746.00	4492.00
C0641-106		SH 64 Meeker West Rural Resur	03/05/20	0.20	4000.00	10150.00	15000.00
NHPP145A-080		SH 145 Keystone-Placerville R	03/05/20	0.49	8000.00	4500.00	4500.00
STR2871-038		US 287 Passing Lanes Springfi	03/05/20	10.00	3000.00	3349.32	3714.75
BR025A-046		K-18-U ON I-25 AT MP112 BRIDG	03/05/20	1.00	3000.00	3332.75	3048.97
NHPP0091-044		SH 9 FRISCO MAIN ST TO IRON S	03/05/20	5.80	4000.00	3183.33	3100.00
HPP 0501-067		US 50 AND SH 92 DELTA INTERSE	03/26/20	0.15	4000.00	13461.80	12320.00
	WEIGHTED AVERAGE FOR THE FIRST QUARTER			77.59	3118.96	3143.79	3481.01
NHPP1602-169		US 160 WC TUNNEL EAST RESURFA	04/02/20	0.50	5000.00	6183.96	5395.25

PROJECT NUMBER	ITEM NUMBER/ PROJECT LOCATION	ITEM DESCRIPTION/ PROJECT LOCATION	DATE LET	UNIT/ QUANTITY	ENGR. EST.	AVERAGE BID	AWARDED BID
===== 212-00032 Soil Conditioning Acre =====							
STR092A-030		SH92 MP 31.748-48.5, DELTA AND	04/02/20	0.50	3000.00	6510.00	6500.00
IM0761-226		I76/SH52 Interchange	04/02/20	21.80	2500.00	2071.61	2305.50
STA340A-021		SH340 MP 6-6.76 MESA COUNTY	04/02/20	2.70	5000.00	4378.33	5000.00
IM0252-473		I-25 CABLE BARRIER PHASE IV	04/09/20	23.80	2000.00	3227.72	3655.43
SHER100-339		WWD TRAFFIC CONTROL ENHANCEME	04/09/20	0.25	1000.00	500.00	500.00
CC0852-106		US-85 LOUVIERS TO MP 191.75	04/23/20	42.20	2700.00	3242.54	2849.00
FBR0852-108		US-85 BETWEEN LOUVIERS AND MP					
C1211-090		SH-121 & 29th Ave / SH-121 &	04/23/20	0.10	2700.00	12298.95	16185.00
C1601-082		Hawkins Signal and Curb Ramps	04/30/20	0.03	5000.00	25490.00	37000.00
FSA1602-159		US 160 AND SH 17 INTERSECTION	04/30/20	0.15	3000.00	7777.33	5700.00
C0853-112		US85 & WCR98 INTERSECTION IMP	05/07/20	3.90	2800.00	2517.63	2400.00
NHPPR100-303		LONG MAST ARM SIGNALS PROJECT	05/07/20	0.16	6000.00	9969.17	3720.00
ITS SW02-304		ITS FIBER TO STATE BUILDINGS	05/14/20	2.20	3000.00	6764.29	5905.00
NHPP0253-276		I-25 EXPRESS LANES SEGMENT 5	05/15/20	17.00	3100.00	3104.92	3104.92
ITS SW02-303		R1: US 285, SH 83 R2: SH 83,	05/28/20	13.40	3200.00	2948.75	10.00
ITSSW01-719		FY 20 ITS CAPITAL REPLACEMENT	06/11/20	1.60	5000.00	3739.25	1562.50
FSAR400-356		FY 20 SIGNAL POLE REPLACEMENT	06/11/20	0.05	20000.00	16319.67	18000.00
SHE016A-043		SH 21 & 16 SIGNALS PROJECT	06/18/20	0.42	10000.00	5959.87	5433.33
		WEIGHTED AVERAGE FOR THE SECOND QUARTER		130.76	2767.82	3010.58	2769.88
		WEIGHTED AVERAGE FOR THE YEAR		208.35	2898.58	3052.06	3034.70
===== 212-00050 Sod Sq Foot =====							
HPP 0501-067		US 50 AND SH 92 DELTA INTERSE	03/26/20	2,125.00	3.00	2.13	2.25
SHE 0703-461		I-70 and Kipling North Phase	03/26/20	1,577.00	5.00	3.05	2.75
		WEIGHTED AVERAGE FOR THE FIRST QUARTER		3,702.00	3.85	2.73	2.46
FSAR400-356		FY 20 SIGNAL POLE REPLACEMENT	06/11/20	270.00	5.00	5.50	8.00
		WEIGHTED AVERAGE FOR THE SECOND QUARTER		270.00	5.00	5.50	8.00
		WEIGHTED AVERAGE FOR THE YEAR		3,972.00	3.93	2.90	2.84
===== 212-00700 Organic Fertilizer Pound =====							
FBR0343-042		US 34 D-27-G STRUCTURE REPLAC	05/07/20	510.00	3.00	0.72	1.50
		WEIGHTED AVERAGE FOR THE SECOND QUARTER		510.00	3.00	0.72	1.50
		WEIGHTED AVERAGE FOR THE YEAR		510.00	3.00	0.72	1.50

COLORADO DEPARTMENT OF TRANSPORTATION
ITEM UNIT COSTS BY PROJECTS -- 2020 COST DATA

10:58 Friday, October 2, 2020 97

PROJECT NUMBER	ITEM NUMBER/ PROJECT LOCATION	ITEM DESCRIPTION/ PROJECT LOCATION	DATE LET	UNIT/ QUANTITY	ENGR. EST.	AVERAGE BID	AWARDED BID
===== 212-00701 Compost (Mech App) Cubic Yard =====							
SHE 0703-461		I-70 and Kipling North Phase	03/26/20	70.00	60.00	99.60	132.00
		WEIGHTED AVERAGE FOR THE FIRST QUARTER		70.00	60.00	99.60	132.00
FBR0343-042		US 34 D-27-G STRUCTURE REPLAC	05/07/20	69.00	40.00	46.93	78.00
		WEIGHTED AVERAGE FOR THE SECOND QUARTER		69.00	40.00	46.93	78.00
		WEIGHTED AVERAGE FOR THE YEAR		139.00	50.07	65.91	105.19
===== 212-00703 Humate Pound =====							
SHE 0703-461		I-70 and Kipling North Phase	03/26/20	80.00	10.00	3.90	5.00
		WEIGHTED AVERAGE FOR THE FIRST QUARTER		80.00	10.00	3.90	5.00
FBR0343-042		US 34 D-27-G STRUCTURE REPLAC	05/07/20	324.00	2.00	1.36	1.50
		WEIGHTED AVERAGE FOR THE SECOND QUARTER		324.00	2.00	1.36	1.50
		WEIGHTED AVERAGE FOR THE YEAR		404.00	3.58	1.67	2.19
===== 212-00704 Mycorrhizae Pound =====							
SHE 0703-461		I-70 and Kipling North Phase	03/26/20	20.00	20.00	25.20	27.00
		WEIGHTED AVERAGE FOR THE FIRST QUARTER		20.00	20.00	25.20	27.00
FBR0343-042		US 34 D-27-G STRUCTURE REPLAC	05/07/20	33.00	15.00	9.53	10.00
		WEIGHTED AVERAGE FOR THE SECOND QUARTER		33.00	15.00	9.53	10.00
		WEIGHTED AVERAGE FOR THE YEAR		53.00	16.89	13.47	16.42

COLORADO DEPARTMENT OF TRANSPORTATION
ITEM UNIT COSTS BY PROJECTS -- 2020 COST DATA

10:58 Friday, October 2, 2020 98

PROJECT NUMBER	ITEM NUMBER/ PROJECT LOCATION	ITEM DESCRIPTION/ PROJECT LOCATION	DATE LET	UNIT/ QUANTITY	ENGR. EST.	AVERAGE BID	AWARDED BID
=====	212-00705	Elemental Sulfur		Pound	=====	=====	=====
SHE 0703-461		I-70 and Kipling North Phase	03/26/20	24.00	5.00	11.20	17.00
	WEIGHTED AVERAGE FOR THE FIRST QUARTER			24.00	5.00	11.20	17.00
	WEIGHTED AVERAGE FOR THE YEAR			24.00	5.00	11.20	17.00
=====	212-00706	Seed (Native) Drill		Acre	=====	=====	=====
SHE 0703-461		I-70 and Kipling North Phase	03/26/20	0.10	1000.00	6218.00	8250.00
	WEIGHTED AVERAGE FOR THE FIRST QUARTER			0.10	1000.00	6218.00	8250.00
FBR0343-042		US 34 D-27-G STRUCTURE REPLAC	05/07/20	1.30	1500.00	825.99	475.00
	WEIGHTED AVERAGE FOR THE SECOND QUARTER			1.30	1500.00	825.99	475.00
	WEIGHTED AVERAGE FOR THE YEAR			1.40	1464.29	1046.98	1030.36
=====	212-00708	Seed (Native) Brdcast		Acre	=====	=====	=====
SHE 0703-461		I-70 and Kipling North Phase	03/26/20	0.30	1000.00	3792.00	5500.00
	WEIGHTED AVERAGE FOR THE FIRST QUARTER			0.30	1000.00	3792.00	5500.00
FBR0343-042		US 34 D-27-G STRUCTURE REPLAC	05/07/20	0.40	4000.00	1513.88	750.00
	WEIGHTED AVERAGE FOR THE SECOND QUARTER			0.40	4000.00	1513.88	750.00
	WEIGHTED AVERAGE FOR THE YEAR			0.70	2714.29	2183.92	2785.71
=====	212-00711	Seeding (Wetland) Broadcast		Acre	=====	=====	=====
FBR0343-042		US 34 D-27-G STRUCTURE REPLAC	05/07/20	0.20	7000.00	1798.18	1500.00
	WEIGHTED AVERAGE FOR THE SECOND QUARTER			0.20	7000.00	1798.18	1500.00
	WEIGHTED AVERAGE FOR THE YEAR			0.20	7000.00	1798.18	1500.00

COLORADO DEPARTMENT OF TRANSPORTATION
ITEM UNIT COSTS BY PROJECTS -- 2020 COST DATA

10:58 Friday, October 2, 2020 99

PROJECT NUMBER	ITEM NUMBER/ PROJECT LOCATION	ITEM DESCRIPTION/ PROJECT LOCATION	DATE LET	UNIT/ QUANTITY	ENGR. EST.	AVERAGE BID	AWARDED BID
===== 212-01200 Landscape Restoration LUMP SUM =====							
C0402-094		US 40 GRAND COUNTY SIGNAL REP	02/27/20	1.00	10000.00	4000.00	5000.00
NHPP0091-044		SH 9 FRISCO MAIN ST TO IRON S	03/05/20	1.00	6000.00	6000.00	11800.00
HPP 0501-067		US 50 AND SH 92 DELTA INTERSE	03/26/20	1.00	1000.00	7764.25	11200.00
		WEIGHTED AVERAGE FOR THE FIRST QUARTER		3.00	5666.67	5932.64	9333.33

C1211-090		SH-121 & 29th Ave / SH-121 &	04/23/20	1.00	2500.00	6343.33	2030.00
		WEIGHTED AVERAGE FOR THE SECOND QUARTER		1.00	2500.00	6343.33	2030.00
		WEIGHTED AVERAGE FOR THE YEAR		4.00	4875.00	6055.85	7507.50
=====							
===== 213-00000 Mulching Acre =====							
FSA0253-262		I-25 SB BOTTLENECK I-76 TO I-	01/09/20	0.60	2000.00	1096.57	1010.00
		WEIGHTED AVERAGE FOR THE FIRST QUARTER		0.60	2000.00	1096.57	1010.00
		WEIGHTED AVERAGE FOR THE YEAR		0.60	2000.00	1096.57	1010.00
=====							
===== 213-00002 Mulching (Weed Free Hay) Acre =====							
STR012A-050		CULVERT REPAIR I-25 AND US 35	01/30/20	0.95	1200.00	2500.00	2500.00
ITS0761-231		ITS FIBER AND CAMERAS ON I-76	02/06/20	36.30	800.00	879.34	660.00
NHPP4701-134		C-470 NOISE WALL WEST OF LUCE	02/06/20	6.10	2000.00	700.30	559.00
STR116A-001		SH 116 A Surface Treatment Pr	02/13/20	0.30	2000.00	3397.90	6000.00
STA069A-033		SH69 MP 58.7 TO 71.58	02/13/20	0.50	7700.00	6722.33	12000.00
STR0101-027		SH 10 Overlay La Junta West	02/27/20	0.30	750.00	3676.21	6000.00
STR2871-038		US 287 Passing Lanes Springfi	03/05/20	10.00	1000.00	906.94	1082.25
NHPP0091-044		SH 9 FRISCO MAIN ST TO IRON S	03/05/20	5.30	4000.00	1438.33	1500.00
		WEIGHTED AVERAGE FOR THE FIRST QUARTER		59.75	1309.71	943.50	972.64

SFTY2254-091		225 Ramp Improvements	04/09/20	1.70	1000.00	1495.00	1190.00
CC0852-106		US-85 LOUVIERS TO MP 191.75	04/23/20	14.70	750.00	938.89	880.00
FBR0852-108		US-85 BETWEEN LOUVIERS AND MP					

PROJECT NUMBER	ITEM NUMBER/ PROJECT LOCATION	ITEM DESCRIPTION/ PROJECT LOCATION	DATE LET	UNIT/ QUANTITY	ENGR. EST.	AVERAGE BID	AWARDED BID
===== 213-00002 Mulching (Weed Free Hay) Acre =====							
C1601-082		Hawkins Signal and Curb Ramps	04/30/20	0.03	4000.00	12663.33	24000.00
NH050A-035		US 50A Pueblo Regional Pond	05/28/20	28.00	650.00	930.13	600.00
NH050A-037		US 50A Pueblo Regional Pond					
FSAR400-356		FY 20 SIGNAL POLE REPLACEMENT	06/11/20	0.04	5000.00	6432.00	7075.00
	WEIGHTED AVERAGE FOR THE SECOND QUARTER			44.47	702.61	943.65	736.72
	WEIGHTED AVERAGE FOR THE YEAR			104.22	1050.66	943.58	871.98
===== 213-00003 Mulching (Weed Free) Acre =====							
NHPP0343-041		I-76 & US 34 FT. MORGAN AREA	01/09/20	0.20	5000.00	1618.73	2103.00
BR0343-040		US 34 REPUBLICAN RIVER BRIDGE	01/16/20	2.10	900.00	925.34	675.00
FBR0343-043		US 34 D-28-P STRUCTURE REPLAC					
PWQM240-172		El Paso County, north Colorad	01/23/20	11.10	700.00	859.00	948.00
NHPP145A-080		SH 145 Keystone-Placerville R	03/05/20	0.49	1500.00	2110.00	2110.00
BR025A-046		K-18-U ON I-25 AT MP112 BRIDG	03/05/20	1.00	1000.00	1148.87	967.03
NH050A-034		US50A PUEBLO WEST PURCELL INT	03/26/20	39.00	650.00	706.99	635.00
	WEIGHTED AVERAGE FOR THE FIRST QUARTER			53.89	700.41	736.45	726.05
NHPP1602-169		US 160 WC TUNNEL EAST RESURFA	04/02/20	0.50	3500.00	4218.74	3403.37
IM0761-226		I76/SH52 Interchange	04/02/20	18.40	650.00	1189.32	548.55
STA340A-021		SH340 MP 6-6.76 MESA COUNTY	04/02/20	2.70	2000.00	1389.67	2500.00
FSA1602-159		US 160 AND SH 17 INTERSECTION	04/30/20	0.15	1000.00	4347.67	1960.00
C0853-112		US85 & WCR98 INTERSECTION IMP	05/07/20	3.90	1000.00	1130.50	1100.00
ITS SW02-304		ITS FIBER TO STATE BUILDINGS	05/14/20	0.10	600.00	11681.43	1446.00
NHPP0253-276		I-25 EXPRESS LANES SEGMENT 5	05/15/20	13.00	800.00	792.52	792.52
ITS SW02-303		R1: US 285, SH 83 R2: SH 83,	05/28/20	13.40	1200.00	1907.84	10.00
	WEIGHTED AVERAGE FOR THE SECOND QUARTER			52.15	953.02	1400.67	646.41
	WEIGHTED AVERAGE FOR THE YEAR			106.04	824.64	1011.26	686.88
===== 213-00004 Mulching (Weed Free Straw) Acre =====							
NHPP0171-105		SH 17 MP 84.5 to US 285 & SH	03/05/20	120.00	500.00	624.20	602.61
	WEIGHTED AVERAGE FOR THE FIRST QUARTER			120.00	500.00	624.20	602.61
NHPPR100-303		LONG MAST ARM SIGNALS PROJECT	05/07/20	0.16	5000.00	4979.67	4464.00
	WEIGHTED AVERAGE FOR THE SECOND QUARTER			0.16	5000.00	4979.67	4464.00
	WEIGHTED AVERAGE FOR THE YEAR			120.16	505.99	630.00	607.75

COLORADO DEPARTMENT OF TRANSPORTATION
 ITEM UNIT COSTS BY PROJECTS -- 2020 COST DATA

10:58 Friday, October 2, 2020 101

PROJECT NUMBER	ITEM NUMBER/ PROJECT LOCATION	ITEM DESCRIPTION/ PROJECT LOCATION	DATE LET	UNIT/ QUANTITY	ENGR. EST.	AVERAGE BID	AWARDED BID
===== 213-00011		Mulching (Hydraulic)		Acre	=====	=====	=====
IM0252-473		I-25 CABLE BARRIER PHASE IV	04/09/20	23.80	480.00	1328.95	1157.89
		WEIGHTED AVERAGE FOR THE SECOND QUARTER		23.80	480.00	1328.95	1157.89
		WEIGHTED AVERAGE FOR THE YEAR		23.80	480.00	1328.95	1157.89
===== 213-00012		Spray-on Mulch Blanket		Acre	=====	=====	=====
NH 0503-093		US50 WEST OF TEXAS CREEK MP 2	01/23/20	0.90	4500.00	4268.96	4037.92
PWQM240-172		El Paso County, north Colorad	01/23/20	4.00	3500.00	3450.00	3400.00
FSA2873-194		US 287 Longmont Intersection	02/13/20	0.50	3500.00	5834.49	9400.00
NHPP0702-359		I-70 No Name Tunnel Lighting	02/27/20	0.65	6000.00	4565.16	4445.00
C0402-094		US 40 GRAND COUNTY SIGNAL REP	02/27/20	0.10	2000.00	2610.50	4221.00
BR025A-046		K-18-U ON I-25 AT MP112 BRIDG	03/05/20	1.00	3500.00	4091.49	4141.14
HPP 0501-067		US 50 AND SH 92 DELTA INTERSE	03/26/20	0.15	4000.00	9231.90	11030.00
		WEIGHTED AVERAGE FOR THE FIRST QUARTER		7.30	3835.62	4217.86	4252.21
STR092A-030		SH92 MP 31.748-48.5, DELTA AND	04/02/20	0.50	3000.00	7125.00	7000.00
IM0761-226		I76/SH52 Interchange	04/02/20	0.25	4700.00	4964.72	4380.45
STA340A-021		SH340 MP 6-6.76 MESA COUNTY	04/02/20	1.50	3000.00	3825.00	2500.00
FBR0343-042		US 34 D-27-G STRUCTURE REPLAC	05/07/20	1.60	3500.00	2988.57	3000.00
NHPP0253-276		I-25 EXPRESS LANES SEGMENT 5	05/15/20	10.00	3700.00	3797.55	3797.55
SHE016A-043		SH 21 & 16 SIGNALS PROJECT	06/18/20	0.42	5200.00	5895.63	6807.14
		WEIGHTED AVERAGE FOR THE SECOND QUARTER		14.27	3641.14	3745.70	3782.73
		WEIGHTED AVERAGE FOR THE YEAR		21.57	3706.95	3936.57	3941.62
===== 213-00061		Mulch Tackifier		Pound	=====	=====	=====
FSA0253-262		I-25 SB BOTTLENECK I-76 TO I-	01/09/20	120.00	3.00	3.83	3.60
NHPP0343-041		I-76 & US 34 FT. MORGAN AREA	01/09/20	160.00	6.00	1.75	0.90
BR0343-040		US 34 REPUBLICAN RIVER BRIDGE	01/16/20	400.00	3.50	3.14	2.85
FBR0343-043		US 34 D-28-P STRUCTURE REPLAC					
PWQM240-172		El Paso County, north Colorad	01/23/20	2,420.00	3.10	2.78	3.05
ITS0761-231		ITS FIBER AND CAMERAS ON I-76	02/06/20	7,260.00	5.00	6.01	2.88
NHPP4701-134		C-470 NOISE WALL WEST OF LUCE	02/06/20	1,300.00	2.50	1.89	1.60
STR116A-001		SH 116 A Surface Treatment Pr	02/13/20	56.00	5.00	14.93	10.00

PROJECT NUMBER	ITEM NUMBER/ PROJECT LOCATION	ITEM DESCRIPTION/ PROJECT LOCATION	DATE LET	UNIT/ QUANTITY	ENGR. EST.	AVERAGE BID	AWARDED BID
=====	213-00061	Mulch Tackifier		Pound	=====	=====	=====
STA069A-033		SH69 MP 58.7 TO 71.58	02/13/20	100.00	5.00	17.28	30.00
STR0101-027		SH 10 Overlay La Junta West	02/27/20	60.00	3.00	12.54	24.00
NHPP0171-105		SH 17 MP 84.5 to US 285 & SH	03/05/20	24,000.00	4.00	2.05	1.95
NHPP145A-080		SH 145 Keystone-Placerville R	03/05/20	98.00	100.00	4.50	4.50
STR2871-038		US 287 Passing Lanes Springfi	03/05/20	2,000.00	5.00	2.83	3.04
NHPP0091-044		SH 9 FRISCO MAIN ST TO IRON S	03/05/20	1,060.00	6.00	1.67	1.15
NH050A-034		US50A PUEBLO WEST PURCELL INT	03/26/20	5,200.00	2.75	2.48	2.75
		WEIGHTED AVERAGE FOR THE FIRST QUARTER		44,234.00	4.23	3.07	2.39
NHPP1602-169		US 160 WC TUNNEL EAST RESURFA	04/02/20	100.00	10.00	8.16	9.45
IM0761-226		I76/SH52 Interchange	04/02/20	3,680.00	2.40	2.49	2.35
STA340A-021		SH340 MP 6-6.76 MESA COUNTY	04/02/20	540.00	3.00	2.83	2.00
SHER100-339		WWD TRAFFIC CONTROL ENHANCEME	04/09/20	40.00	3.00	20.00	20.00
SFTY2254-091		225 Ramp Improvements	04/09/20	340.00	5.00	2.30	0.60
CC0852-106		US-85 LOUVIERS TO MP 191.75	04/23/20	7,156.00	3.00	2.11	2.22
FBR0852-108		US-85 BETWEEN LOUVIERS AND MP					
C1601-082		Hawkins Signal and Curb Ramps	04/30/20	6.00	15.00	56.33	115.00
FSA1602-159		US 160 AND SH 17 INTERSECTION	04/30/20	30.00	10.00	16.42	7.00
NHPPR100-303		LONG MAST ARM SIGNALS PROJECT	05/07/20	34.00	4.00	19.00	24.00
ITS SW02-304		ITS FIBER TO STATE BUILDINGS	05/14/20	20.00	5.00	63.70	8.00
NHPP0253-276		I-25 EXPRESS LANES SEGMENT 5	05/15/20	8,280.00	2.40	2.44	2.44
ITS SW02-303		R1: US 285, SH 83 R2: SH 83,	05/28/20	2,680.00	3.00	2.17	0.10
NH050A-035		US 50A Pueblo Regional Pond	05/28/20	5,600.00	3.00	2.14	1.00
NH050A-037		US 50A Pueblo Regional Pond					
ITSSW01-719		FY 20 ITS CAPITAL REPLACEMENT	06/11/20	320.00	5.00	11.75	11.00
FSAR400-356		FY 20 SIGNAL POLE REPLACEMENT	06/11/20	4.00	25.00	74.17	72.50
		WEIGHTED AVERAGE FOR THE SECOND QUARTER		28,830.00	2.84	2.33	2.06
		WEIGHTED AVERAGE FOR THE YEAR		73,064.00	3.68	2.73	2.26
=====	213-00067	Rock Mulch (Weed Free)		Sq Foot	=====	=====	=====
STRR300-249		Grand and Jackson Counties AD	03/05/20	363.00	15.00	15.33	25.00
CC080-037		VARIOUS ADA RAMPS ALONG NORTH	03/05/20	37.00	15.00	20.23	20.00
		WEIGHTED AVERAGE FOR THE FIRST QUARTER		400.00	15.00	15.92	24.54
		WEIGHTED AVERAGE FOR THE YEAR		400.00	15.00	15.92	24.54
=====	213-00070	Landscape Weed Barr Fabric		Sq Yard	=====	=====	=====
C1601-082		Hawkins Signal and Curb Ramps	04/30/20	2.00	20.00	162.33	330.00
		WEIGHTED AVERAGE FOR THE SECOND QUARTER		2.00	20.00	162.33	330.00
		WEIGHTED AVERAGE FOR THE YEAR		2.00	20.00	162.33	330.00

PROJECT NUMBER	ITEM NUMBER/ PROJECT LOCATION	ITEM DESCRIPTION/ PROJECT LOCATION	DATE LET	UNIT/ QUANTITY	ENGR. EST.	AVERAGE BID	AWARDED BID
===== 213-00150		Bonded Fiber Matrix		Acre			
PWQM240-172		El Paso County, north Colorad	01/23/20	5.00	3300.00	3450.00	3400.00
BR025A-046		K-18-U ON I-25 AT MP112 BRIDG	03/05/20	1.00	3000.00	4116.49	4141.14
NHPP0091-044		SH 9 FRISCO MAIN ST TO IRON S	03/05/20	5.80	3000.00	2460.00	2700.00
		WEIGHTED AVERAGE FOR THE FIRST QUARTER		11.80	3127.12	3084.87	3118.74
STA340A-021		SH340 MP 6-6.76 MESA COUNTY	04/02/20	1.50	3500.00	3937.33	2500.00
CC0852-106		US-85 LOUVIERS TO MP 191.75	04/23/20	27.50	3100.00	2533.85	2409.00
FBR0852-108		US-85 BETWEEN LOUVIERS AND MP					
FBR0343-042		US 34 D-27-G STRUCTURE REPLAC	05/07/20	1.50	3200.00	2922.46	3000.00
NHPP0253-276		I-25 EXPRESS LANES SEGMENT 5	05/15/20	10.00	3700.00	3754.12	3754.12
		WEIGHTED AVERAGE FOR THE SECOND QUARTER		40.50	3266.67	2629.68	2766.39
		WEIGHTED AVERAGE FOR THE YEAR		52.30	3235.18	2685.12	2845.89
===== 213-00700		Landscape Boulder		Each			
NHPP0091-044		SH 9 FRISCO MAIN ST TO IRON S	03/05/20	55.00	500.00	185.00	290.00
		WEIGHTED AVERAGE FOR THE FIRST QUARTER		55.00	500.00	185.00	290.00
		WEIGHTED AVERAGE FOR THE YEAR		55.00	500.00	185.00	290.00
===== 214-00000		Landscape Maintenance		LUMP SUM			
FSA0253-262		I-25 SB BOTTLENECK I-76 TO I-	01/09/20	1.00	25000.00	1906.67	1050.00
SHE 0703-461		I-70 and Kipling North Phase	03/26/20	1.00	17000.00	7896.00	8250.00
		WEIGHTED AVERAGE FOR THE FIRST QUARTER		2.00	21000.00	5650.00	4650.00
SFTY2254-091		225 Ramp Improvements	04/09/20	1.00	25000.00	5750.00	1500.00
		WEIGHTED AVERAGE FOR THE SECOND QUARTER		1.00	25000.00	5750.00	1500.00
		WEIGHTED AVERAGE FOR THE YEAR		3.00	22333.33	5670.00	3600.00

PROJECT NUMBER	ITEM NUMBER/ PROJECT LOCATION	ITEM DESCRIPTION/ PROJECT LOCATION	DATE LET	UNIT/ QUANTITY	ENGR. EST.	AVERAGE BID	AWARDED BID
=====	214-00005	Landscape Maintenance (24 Month)		LUMP SUM	=====		
NHPP4701-134		C-470 NOISE WALL WEST OF LUCE	02/06/20	1.00	7500.00	22218.00	14590.00
		WEIGHTED AVERAGE FOR THE FIRST QUARTER		1.00	7500.00	22218.00	14590.00
CC0852-106		US-85 LOUVIERS TO MP 191.75	04/23/20	1.00	25000.00	31557.22	29150.00
FBR0852-108		US-85 BETWEEN LOUVIERS AND MP					
NHPP0253-276		I-25 EXPRESS LANES SEGMENT 5	05/15/20	1.00	28400.00	28769.28	28769.28
		WEIGHTED AVERAGE FOR THE SECOND QUARTER		2.00	26700.00	31247.45	28959.64
		WEIGHTED AVERAGE FOR THE YEAR		3.00	20300.00	28022.65	24169.76
=====	214-00222	Decid Tree (2 In Cal) (Furnish)		Each	=====		
SHE 0703-461		I-70 and Kipling North Phase	03/26/20	1.00	400.00	1213.40	1375.00
		WEIGHTED AVERAGE FOR THE FIRST QUARTER		1.00	400.00	1213.40	1375.00
		WEIGHTED AVERAGE FOR THE YEAR		1.00	400.00	1213.40	1375.00
=====	214-01032	Large Woody Material		Each	=====		
FBR0343-042		US 34 D-27-G STRUCTURE REPLAC	05/07/20	1.00	2500.00	1790.63	500.00
		WEIGHTED AVERAGE FOR THE SECOND QUARTER		1.00	2500.00	1790.63	500.00
		WEIGHTED AVERAGE FOR THE YEAR		1.00	2500.00	1790.63	500.00
=====	216-00041	Soil Reten Blanket (S/C)		Sq Yard	=====		
CC0852-106		US-85 LOUVIERS TO MP 191.75	04/23/20	2,300.00	2.50	2.85	2.60
FBR0852-108		US-85 BETWEEN LOUVIERS AND MP					
		WEIGHTED AVERAGE FOR THE SECOND QUARTER		2,300.00	2.50	2.85	2.60
		WEIGHTED AVERAGE FOR THE YEAR		2,300.00	2.50	2.85	2.60
=====	216-00070	Geocell Confinement Sys		Sq Yard	=====		
CC0852-106		US-85 LOUVIERS TO MP 191.75	04/23/20	2,990.00	60.00	29.36	16.34

PROJECT NUMBER	ITEM NUMBER/ PROJECT LOCATION	ITEM DESCRIPTION/ PROJECT LOCATION	DATE LET	UNIT/ QUANTITY	ENGR. EST.	AVERAGE BID	AWARDED BID
===== 216-00070 FBR0852-108		Geocell Confinement Sys US-85 BETWEEN LOUVIERS AND MP		Sq Yard			
	WEIGHTED AVERAGE FOR THE SECOND QUARTER			2,990.00	60.00	29.36	16.34
	WEIGHTED AVERAGE FOR THE YEAR			2,990.00	60.00	29.36	16.34
===== 216-00101		Soil Reten Blanket (S-C) (PhotoD Cl 1)		Sq Yard			
FSA0341-097 NHPP4701-134		US 34 & MACGREGOR INTERSECTIO C-470 NOISE WALL WEST OF LUCE	01/09/20 02/06/20	4,340.00 21,580.00	5.00 3.00	3.75 2.10	3.75 1.70
	WEIGHTED AVERAGE FOR THE FIRST QUARTER			25,920.00	3.33	2.16	2.04
C1211-090		SH-121 & 29th Ave / SH-121 &	04/23/20	968.00	4.00	4.80	4.25
	WEIGHTED AVERAGE FOR THE SECOND QUARTER			968.00	4.00	4.80	4.25
	WEIGHTED AVERAGE FOR THE YEAR			26,888.00	3.36	2.23	2.12
===== 216-00111		Soil Reten Blanket (Excel) (PhotoD Cl 1)		Sq Yard			
STR012A-050		CULVERT REPAIR I-25 AND US 35	01/30/20	2,250.00	3.00	5.00	5.00
	WEIGHTED AVERAGE FOR THE FIRST QUARTER			2,250.00	3.00	5.00	5.00
	WEIGHTED AVERAGE FOR THE YEAR			2,250.00	3.00	5.00	5.00
===== 216-00201		Soil Reten Blanket (S-C) (BioD Cl 1)		Sq Yard			
NHPP0253-265		I-25 AT ERIE PARKWAY ON AND O	01/09/20	100.00	11.00	60.50	96.00
NHPP0343-041		I-76 & US 34 FT. MORGAN AREA	01/09/20	14,470.00	2.40	4.38	5.00
STR131A-038		SH 131 MP 51.95-55.73, ROUTT	01/16/20	1,000.00	4.00	3.40	3.55
PWQM240-172		El Paso County, north Colorad	01/23/20	14,808.00	2.50	2.65	2.80
ITS0761-231		ITS FIBER AND CAMERAS ON I-76	02/06/20	100.00	2.50	5.56	5.82
STA059A-036		SH 59 SEIBERT TO COPE	02/06/20	1,000.00	3.50	3.78	3.55
C0641-106		SH 64 Meeker West Rural Resur	03/05/20	968.00	3.00	3.18	3.00
NHPP145A-080		SH 145 Keystone-Placerville R	03/05/20	105.00	4.00	4.15	4.15
BR025A-046		K-18-U ON I-25 AT MP112 BRIDG	03/05/20	8,000.00	2.50	2.71	2.19
NHPP0091-044		SH 9 FRISCO MAIN ST TO IRON S	03/05/20	2,717.00	4.00	4.78	5.50

PROJECT NUMBER	ITEM NUMBER/ PROJECT LOCATION	ITEM DESCRIPTION/ PROJECT LOCATION	DATE LET	UNIT/ QUANTITY	ENGR. EST.	AVERAGE BID	AWARDED BID
===== 216-00201		Soil Reten Blanket (S-C) (BioD Cl 1)		Sq Yard	=====	=====	=====
NH050A-034		US50A PUEBLO WEST PURCELL INT	03/26/20	19,079.00	2.40	2.50	2.50
SHE 0703-461		I-70 and Kipling North Phase	03/26/20	1,813.00	3.00	3.40	3.00
		WEIGHTED AVERAGE FOR THE FIRST QUARTER		64,160.00	2.59	2.99	3.43
IM0761-226		I76/SH52 Interchange	04/02/20	16,633.00	2.00	2.74	2.44
SFTY2254-091		225 Ramp Improvements	04/09/20	1,166.00	4.00	3.25	2.50
CC0852-106		US-85 LOUVIERS TO MP 191.75	04/23/20	18,449.00	7.00	3.23	2.98
FBR0852-108		US-85 BETWEEN LOUVIERS AND MP					
FBR0343-042		US 34 D-27-G STRUCTURE REPLAC	05/07/20	800.00	4.00	2.78	2.60
ITS SW02-304		ITS FIBER TO STATE BUILDINGS	05/14/20	10,600.00	7.00	3.84	3.19
NHPP0253-276		I-25 EXPRESS LANES SEGMENT 5	05/15/20	15,960.00	2.60	2.66	2.66
NH050A-035		US 50A Pueblo Regional Pond	05/28/20	54,300.00	2.50	2.73	2.40
NH050A-037		US 50A Pueblo Regional Pond					
		WEIGHTED AVERAGE FOR THE SECOND QUARTER		117,908.00	3.58	2.89	2.60
		WEIGHTED AVERAGE FOR THE YEAR		182,068.00	3.23	2.92	2.90
===== 216-00211		Soil Reten Blanket (Exc) (BioD Cl 1)		Sq Yard	=====	=====	=====
ITS SW02-303		R1: US 285, SH 83 R2: SH 83,	05/28/20	50.00	6.00	25.84	10.00
		WEIGHTED AVERAGE FOR THE SECOND QUARTER		50.00	6.00	25.84	10.00
		WEIGHTED AVERAGE FOR THE YEAR		50.00	6.00	25.84	10.00
===== 216-00221		Soil Reten Blanket (C) (BioD Cl 1)		Sq Yard	=====	=====	=====
FBR0343-042		US 34 D-27-G STRUCTURE REPLAC	05/07/20	604.00	3.50	3.25	3.00
		WEIGHTED AVERAGE FOR THE SECOND QUARTER		604.00	3.50	3.25	3.00
		WEIGHTED AVERAGE FOR THE YEAR		604.00	3.50	3.25	3.00
===== 216-00301		Turf Reinf Mat (Cl 1)		Sq Yard	=====	=====	=====
NH050A-034		US50A PUEBLO WEST PURCELL INT	03/26/20	12,649.00	6.50	4.96	4.65
		WEIGHTED AVERAGE FOR THE FIRST QUARTER		12,649.00	6.50	4.96	4.65
		WEIGHTED AVERAGE FOR THE YEAR		12,649.00	6.50	4.96	4.65

PROJECT NUMBER	ITEM NUMBER/ PROJECT LOCATION	ITEM DESCRIPTION/ PROJECT LOCATION	DATE LET	UNIT/ QUANTITY	ENGR. EST.	AVERAGE BID	AWARDED BID
===== 216-00302		Turf Reinf Mat (Cl 2)		Sq Yard	=====		
NH050A-034		US50A PUEBLO WEST PURCELL INT	03/26/20	19,079.00	8.00	5.77	5.30
	WEIGHTED AVERAGE FOR THE FIRST QUARTER			19,079.00	8.00	5.77	5.30
	WEIGHTED AVERAGE FOR THE YEAR			19,079.00	8.00	5.77	5.30
===== 216-00303		Turf Reinf Mat (Cl 3)		Sq Yard	=====		
NHPP0091-044		SH 9 FRISCO MAIN ST TO IRON S	03/05/20	113.00	10.00	7.63	8.50
	WEIGHTED AVERAGE FOR THE FIRST QUARTER			113.00	10.00	7.63	8.50
	WEIGHTED AVERAGE FOR THE YEAR			113.00	10.00	7.63	8.50
===== 217-00000		Herbicide Treatment		Sq Yard	=====		
FSA0253-262		I-25 SB BOTTLENECK I-76 TO I-	01/09/20	3,000.00	3.50	0.57	0.55
NHPP0343-041		I-76 & US 34 FT. MORGAN AREA	01/09/20	5,982.00	0.42	0.35	0.30
NH 0503-093		US50 WEST OF TEXAS CREEK MP 2	01/23/20	200.00	10.00	5.63	5.25
NH050A-034		US50A PUEBLO WEST PURCELL INT	03/26/20	500.00	120.00	3.17	1.85
	WEIGHTED AVERAGE FOR THE FIRST QUARTER			9,682.00	7.75	0.84	0.56
SHE016A-043		SH 21 & 16 SIGNALS PROJECT	06/18/20	199.00	6.00	3.83	6.63
	WEIGHTED AVERAGE FOR THE SECOND QUARTER			199.00	6.00	3.83	6.63
	WEIGHTED AVERAGE FOR THE YEAR			9,881.00	7.71	0.93	0.68
===== 217-00020		Herbicide Treatment		Hour	=====		
PWQM240-172		El Paso County, north Colorad	01/23/20	8.00	200.00	246.00	202.00
ITS0761-231		ITS FIBER AND CAMERAS ON I-76	02/06/20	20.00	150.00	163.42	80.00
SHE 0703-461		I-70 and Kipling North Phase	03/26/20	8.00	125.00	214.20	165.00
	WEIGHTED AVERAGE FOR THE FIRST QUARTER			36.00	155.56	184.91	126.00
IM0761-226		I76/SH52 Interchange	04/02/20	20.00	165.00	230.62	265.00

PROJECT NUMBER	ITEM NUMBER/ PROJECT LOCATION	ITEM DESCRIPTION/ PROJECT LOCATION	DATE LET	UNIT/ QUANTITY	ENGR. EST.	AVERAGE BID	AWARDED BID
=====	217-00020	Herbicide Treatment		Hour =====			
SFTY2254-091	225 Ramp Improvements		04/09/20	8.00	150.00	215.00	300.00
CC0852-106	US-85 LOUVIERS TO MP 191.75		04/23/20	10.00	145.00	179.05	203.50
FBR0852-108	US-85 BETWEEN LOUVIERS AND MP						
C0853-112	US85 & WCR98 INTERSECTION IMP		05/07/20	8.00	85.00	311.63	350.00
FBR0343-042	US 34 D-27-G STRUCTURE REPLAC		05/07/20	20.00	150.00	178.36	100.00
ITS SW02-304	ITS FIBER TO STATE BUILDINGS		05/14/20	20.00	150.00	161.75	181.00
NHPP0253-276	I-25 EXPRESS LANES SEGMENT 5		05/15/20	40.00	200.00	193.04	193.04
ITS SW02-303	R1: US 285, SH 83 R2: SH 83,		05/28/20	20.00	125.00	192.04	0.10
	WEIGHTED AVERAGE FOR THE SECOND QUARTER			146.00	158.42	202.81	177.25
	WEIGHTED AVERAGE FOR THE YEAR			182.00	157.86	199.55	167.11
=====	218-00000	Noxious Weed Management		LUMP SUM =====			
NHPP0253-276	I-25 EXPRESS LANES SEGMENT 5		05/15/20	1.00	5400.00	5350.00	5350.00
	WEIGHTED AVERAGE FOR THE SECOND QUARTER			1.00	5400.00	5350.00	5350.00
	WEIGHTED AVERAGE FOR THE YEAR			1.00	5400.00	5350.00	5350.00
=====	240-00000	Wildlife Biologist		Hour =====			
FSA0253-262	I-25 SB BOTTLENECK I-76 TO I-		01/09/20	4.00	100.00	82.74	77.00
SHER500-210	R5 FY19 CENTER LINE RUMBLE ST		01/09/20	20.00	120.00	1012.50	275.00
STR141A-044	SH 141 AND SH 145, FROM SLICK		01/30/20	20.00	100.00	150.61	80.00
NHPP 0852-116	US85:HAMPDEN TO FLORIDA-RESUR		02/06/20	80.00	110.00	87.50	100.00
NHPP0702-359	I-70 No Name Tunnel Lighting		02/27/20	20.00	130.00	147.75	130.00
C0641-106	SH 64 Meeker West Rural Resur		03/05/20	20.00	150.00	103.50	95.00
NHPP145A-080	SH 145 Keystone-Placerville R		03/05/20	20.00	150.00	125.00	125.00
NHPP0091-044	SH 9 FRISCO MAIN ST TO IRON S		03/05/20	40.00	130.00	126.67	110.00
SHE 0703-461	I-70 and Kipling North Phase		03/26/20	8.00	100.00	163.00	220.00
	WEIGHTED AVERAGE FOR THE FIRST QUARTER			232.00	121.55	180.94	123.14
NHPP1602-169	US 160 WC TUNNEL EAST RESURFA		04/02/20	15.00	120.00	145.73	121.28
STA340A-021	SH340 MP 6-6.76 MESA COUNTY		04/02/20	20.00	130.00	126.67	130.00
STR0341-101	SH 34 North of Grandby Resurf		04/02/20	40.00	150.00	154.56	90.00
SFTY2254-091	225 Ramp Improvements		04/09/20	16.00	25.00	128.00	101.00
CC0852-106	US-85 LOUVIERS TO MP 191.75		04/23/20	80.00	100.00	105.62	82.50
FBR0852-108	US-85 BETWEEN LOUVIERS AND MP						

PROJECT NUMBER	ITEM NUMBER/ PROJECT LOCATION	ITEM DESCRIPTION/ PROJECT LOCATION	DATE LET	UNIT/ QUANTITY	ENGR. EST.	AVERAGE BID	AWARDED BID
===== 240-00000 Wildlife Biologist Hour =====							
C1601-082		Hawkins Signal and Curb Ramps	04/30/20	20.00	150.00	126.00	138.00
FSA1602-159		US 160 AND SH 17 INTERSECTION	04/30/20	20.00	110.00	199.00	215.00
NHPP0253-276		I-25 EXPRESS LANES SEGMENT 5	05/15/20	20.00	100.00	112.99	112.99
ITSSW01-719		FY 20 ITS CAPITAL REPLACEMENT	06/11/20	40.00	125.00	141.50	66.00
	WEIGHTED AVERAGE FOR THE SECOND QUARTER			271.00	114.39	124.16	104.04
	WEIGHTED AVERAGE FOR THE YEAR			503.00	117.69	143.81	112.85
===== 240-00010 Rem of Nests Hour =====							
BR0343-040		US 34 REPUBLICAN RIVER BRIDGE	01/16/20	80.00	95.00	119.65	85.00
FBR0343-043		US 34 D-28-P STRUCTURE REPLAC					
NH 0503-093		US50 WEST OF TEXAS CREEK MP 2	01/23/20	50.00	100.00	87.51	105.01
NHPP 0852-116		US85:HAMPDEN TO FLORIDA-RESUR	02/06/20	80.00	110.00	75.00	80.00
STA069A-033		SH69 MP 58.7 TO 71.58	02/13/20	40.00	102.00	87.28	60.00
STR0101-027		SH 10 Overlay La Junta West	02/27/20	100.00	100.00	96.92	60.00
NHPP0702-359		I-70 No Name Tunnel Lighting	02/27/20	40.00	130.00	98.48	120.00
NH0242-085		US 24 M.P. 291.38 to M.P. 296	02/27/20	30.00	100.00	128.51	150.00
C0641-106		SH 64 Meeker West Rural Resur	03/05/20	10.00	150.00	91.25	95.00
BR025A-046		K-18-U ON I-25 AT MP112 BRIDG	03/05/20	20.00	125.00	217.99	62.71
NH050A-034		US50A PUEBLO WEST PURCELL INT	03/26/20	8.00	100.00	199.34	225.00
	WEIGHTED AVERAGE FOR THE FIRST QUARTER			458.00	105.85	117.10	87.67
STR092A-030		SH92 MP 31.748-48.5,DELTA AND	04/02/20	8.00	100.00	298.50	285.00
IM0761-226		I76/SH52 Interchange	04/02/20	20.00	100.00	176.57	115.39
STA340A-021		SH340 MP 6-6.76 MESA COUNTY	04/02/20	20.00	140.00	117.67	130.00
CC0852-106		US-85 LOUVIERS TO MP 191.75	04/23/20	80.00	100.00	124.49	82.50
FBR0852-108		US-85 BETWEEN LOUVIERS AND MP					
IM025A-048		Northbound I-25 bridge at Exi	05/28/20	20.00	110.00	179.56	105.00
	WEIGHTED AVERAGE FOR THE SECOND QUARTER			148.00	106.76	138.65	107.35
	WEIGHTED AVERAGE FOR THE YEAR			606.00	106.07	124.97	92.48
===== 240-00015 Protect Migratory Birds Hour =====							
NH 0503-093		US50 WEST OF TEXAS CREEK MP 2	01/23/20	50.00	100.00	53.51	105.01
	WEIGHTED AVERAGE FOR THE FIRST QUARTER			50.00	100.00	53.51	105.01

PROJECT NUMBER	ITEM NUMBER/ PROJECT LOCATION	ITEM DESCRIPTION/ PROJECT LOCATION	DATE LET	UNIT/ QUANTITY	ENGR. EST.	AVERAGE BID	AWARDED BID
===== 240-00015		Protect Migratory Birds		Hour	=====		
SFTY2254-091		225 Ramp Improvements	04/09/20	16.00	80.00	128.00	101.00
	WEIGHTED AVERAGE FOR THE SECOND QUARTER			16.00	80.00	128.00	101.00
	WEIGHTED AVERAGE FOR THE YEAR			66.00	95.15	71.56	104.04
===== 240-00017		Protect Migratory Birds		LUMP SUM	=====		
SFTY2254-091		225 Ramp Improvements	04/09/20	1.00	5000.00	5690.00	8900.00
	WEIGHTED AVERAGE FOR THE SECOND QUARTER			1.00	5000.00	5690.00	8900.00
	WEIGHTED AVERAGE FOR THE YEAR			1.00	5000.00	5690.00	8900.00
===== 240-00020		Netting		Sq Yard	=====		
BR0343-040		US 34 REPUBLICAN RIVER BRIDGE	01/16/20	2,200.00	15.00	9.24	6.00
FBR0343-043		US 34 D-28-P STRUCTURE REPLAC					
NH 0503-093		US50 WEST OF TEXAS CREEK MP 2	01/23/20	500.00	10.00	14.45	18.90
STA069A-033		SH69 MP 58.7 TO 71.58	02/13/20	584.00	11.00	12.21	14.00
STR0101-027		SH 10 Overlay La Junta West	02/27/20	800.00	10.00	11.46	9.00
NHPP0702-359		I-70 No Name Tunnel Lighting	02/27/20	560.00	15.00	11.15	10.00
NH0242-085		US 24 M.P. 291.38 to M.P. 296	02/27/20	257.00	6.50	12.38	11.40
NH050A-034		US50A PUEBLO WEST PURCELL INT	03/26/20	1,000.00	10.00	9.88	12.00
	WEIGHTED AVERAGE FOR THE FIRST QUARTER			5,901.00	12.29	10.14	9.92
CC0852-106		US-85 LOUVIERS TO MP 191.75	04/23/20	200.00	6.00	30.17	31.57
FBR0852-108		US-85 BETWEEN LOUVIERS AND MP					
IM025A-048		Northbound I-25 bridge at Exi	05/28/20	400.00	10.00	19.53	8.00
	WEIGHTED AVERAGE FOR THE SECOND QUARTER			600.00	8.67	25.61	15.86
	WEIGHTED AVERAGE FOR THE YEAR			6,501.00	11.95	11.51	10.47
===== 240-00100		Prairie Dog Mgmt		LUMP SUM	=====		
SFTY2254-091		225 Ramp Improvements	04/09/20	1.00	1000.00	6750.00	8900.00

COLORADO DEPARTMENT OF TRANSPORTATION
ITEM UNIT COSTS BY PROJECTS -- 2020 COST DATA

10:58 Friday, October 2, 2020 111

PROJECT NUMBER	ITEM NUMBER/ PROJECT LOCATION	ITEM DESCRIPTION/ PROJECT LOCATION	DATE LET	UNIT/ QUANTITY	ENGR. EST.	AVERAGE BID	AWARDED BID
=====	240-00100	Prairie Dog Mgmt		LUMP SUM	=====	=====	=====
CC0852-106		US-85 LOUVIERS TO MP 191.75	04/23/20	1.00	20000.00	32069.11	24838.00
FBR0852-108		US-85 BETWEEN LOUVIERS AND MP					
	WEIGHTED AVERAGE FOR THE SECOND QUARTER			2.00	10500.00	27005.29	16869.00
	WEIGHTED AVERAGE FOR THE YEAR			2.00	10500.00	27005.29	16869.00
=====	240-00200	Bat House		Each	=====	=====	=====
BR0343-040		US 34 REPUBLICAN RIVER BRIDGE	01/16/20	2.00	500.00	742.89	350.00
FBR0343-043		US 34 D-28-P STRUCTURE REPLAC					
	WEIGHTED AVERAGE FOR THE FIRST QUARTER			2.00	500.00	742.89	350.00
	WEIGHTED AVERAGE FOR THE YEAR			2.00	500.00	742.89	350.00
=====	250-00010	Envir Health/Safety Mngmt		LUMP SUM	=====	=====	=====
NHPP0702-359		I-70 No Name Tunnel Lighting	02/27/20	1.00	6000.00	3270.75	2845.00
CC080-037		VARIOUS ADA RAMPS ALONG NORTH	03/05/20	1.00	12000.00	9140.44	15000.00
	WEIGHTED AVERAGE FOR THE FIRST QUARTER			2.00	9000.00	6205.60	8922.50
IM0761-226		I76/SH52 Interchange	04/02/20	1.00	10000.00	3082.35	2984.96
STA340A-021		SH340 MP 6-6.76 MESA COUNTY	04/02/20	1.00	8000.00	9671.67	20000.00
C1601-082		Hawkins Signal and Curb Ramps	04/30/20	1.00	5000.00	8233.33	3850.00
NHPP0253-276		I-25 EXPRESS LANES SEGMENT 5	05/15/20	1.00	3000.00	3204.65	3204.65
	WEIGHTED AVERAGE FOR THE SECOND QUARTER			4.00	6500.00	5606.87	7509.90
	WEIGHTED AVERAGE FOR THE YEAR			6.00	7333.33	5824.59	7980.77
=====	250-00050	Monitoring Technician		Hour	=====	=====	=====
CC080-037		VARIOUS ADA RAMPS ALONG NORTH	03/05/20	40.00	140.00	137.83	40.00
	WEIGHTED AVERAGE FOR THE FIRST QUARTER			40.00	140.00	137.83	40.00
STA340A-021		SH340 MP 6-6.76 MESA COUNTY	04/02/20	40.00	200.00	127.33	150.00

PROJECT NUMBER	ITEM NUMBER/ PROJECT LOCATION	ITEM DESCRIPTION/ PROJECT LOCATION	DATE LET	UNIT/ QUANTITY	ENGR. EST.	AVERAGE BID	AWARDED BID
===== 250-00050		Monitoring Technician		Hour =====			
FSA1602-159		US 160 AND SH 17 INTERSECTION	04/30/20	80.00	170.00	173.33	161.00
	WEIGHTED AVERAGE FOR THE SECOND QUARTER			120.00	180.00	158.00	157.33
	WEIGHTED AVERAGE FOR THE YEAR			160.00	170.00	151.79	128.00
===== 250-00100		Environmental Health and Safety		LUMP SUM =====			
FSA1602-159		US 160 AND SH 17 INTERSECTION	04/30/20	1.00	10000.00	8526.67	5790.00
ITS SW02-304		ITS FIBER TO STATE BUILDINGS	05/14/20	1.00	1000.00	7060.50	5485.00
	WEIGHTED AVERAGE FOR THE SECOND QUARTER			2.00	5500.00	7688.86	5637.50
	WEIGHTED AVERAGE FOR THE YEAR			2.00	5500.00	7688.86	5637.50
===== 250-00110		Health and Safety Officer		Hour =====			
NHPP0702-359		I-70 No Name Tunnel Lighting	02/27/20	10.00	120.00	155.53	125.00
CC080-037		VARIOUS ADA RAMPS ALONG NORTH	03/05/20	40.00	120.00	158.01	40.00
	WEIGHTED AVERAGE FOR THE FIRST QUARTER			50.00	120.00	157.51	57.00
STA340A-021		SH340 MP 6-6.76 MESA COUNTY	04/02/20	40.00	200.00	135.00	150.00
FSA1602-159		US 160 AND SH 17 INTERSECTION	04/30/20	20.00	150.00	210.33	264.00
	WEIGHTED AVERAGE FOR THE SECOND QUARTER			60.00	183.33	160.11	188.00
	WEIGHTED AVERAGE FOR THE YEAR			110.00	154.55	158.74	128.45
===== 250-00120		Material Sampling and Delivery		Each =====			
FSA1602-159		US 160 AND SH 17 INTERSECTION	04/30/20	10.00	350.00	407.00	306.00
	WEIGHTED AVERAGE FOR THE SECOND QUARTER			10.00	350.00	407.00	306.00
	WEIGHTED AVERAGE FOR THE YEAR			10.00	350.00	407.00	306.00
===== 250-00200		Material Handling (Stockpile)		Cubic Yard =====			
STA340A-021		SH340 MP 6-6.76 MESA COUNTY	04/02/20	200.00	25.00	17.08	3.00

COLORADO DEPARTMENT OF TRANSPORTATION
 ITEM UNIT COSTS BY PROJECTS -- 2020 COST DATA

10:58 Friday, October 2, 2020 113

PROJECT NUMBER	ITEM NUMBER/ PROJECT LOCATION	ITEM DESCRIPTION/ PROJECT LOCATION	DATE LET	UNIT/ QUANTITY	ENGR. EST.	AVERAGE BID	AWARDED BID
===== 250-00200		Material Handling (Stockpile)		Cubic Yard			
FSA1602-159		US 160 AND SH 17 INTERSECTION	04/30/20	20.00	200.00	223.00	314.00
	WEIGHTED AVERAGE FOR THE SECOND QUARTER			220.00	40.91	35.80	31.27
	WEIGHTED AVERAGE FOR THE YEAR			220.00	40.91	35.80	31.27
===== 250-00204		Materials Management Plan		LUMP SUM			
NHPP0253-276		I-25 EXPRESS LANES SEGMENT 5	05/15/20	1.00	3000.00	1284.00	1284.00
	WEIGHTED AVERAGE FOR THE SECOND QUARTER			1.00	3000.00	1284.00	1284.00
	WEIGHTED AVERAGE FOR THE YEAR			1.00	3000.00	1284.00	1284.00
===== 250-00210		Solid Waste Disposal		Cubic Yard			
FSA1602-159		US 160 AND SH 17 INTERSECTION	04/30/20	20.00	250.00	237.00	336.00
	WEIGHTED AVERAGE FOR THE SECOND QUARTER			20.00	250.00	237.00	336.00
	WEIGHTED AVERAGE FOR THE YEAR			20.00	250.00	237.00	336.00
===== 250-00220		Hazardous Waste Disposal		Cubic Yard			
NHPP0702-359		I-70 No Name Tunnel Lighting	02/27/20	1.00	600.00	585.00	520.00
	WEIGHTED AVERAGE FOR THE FIRST QUARTER			1.00	600.00	585.00	520.00
STA340A-021		SH340 MP 6-6.76 MESA COUNTY	04/02/20	200.00	20.00	61.50	3.00
FSA1602-159		US 160 AND SH 17 INTERSECTION	04/30/20	5.00	1000.00	676.33	709.00
	WEIGHTED AVERAGE FOR THE SECOND QUARTER			205.00	43.90	76.50	20.22
	WEIGHTED AVERAGE FOR THE YEAR			206.00	46.60	79.78	22.65
===== 304-01005		ABC (CL 1)		Cubic Yard			
NHPP0091-044		SH 9 FRISCO MAIN ST TO IRON S	03/05/20	100.00	40.00	86.42	81.00
	WEIGHTED AVERAGE FOR THE FIRST QUARTER			100.00	40.00	86.42	81.00

PROJECT NUMBER	ITEM NUMBER/ PROJECT LOCATION	ITEM DESCRIPTION/ PROJECT LOCATION	DATE LET	UNIT/ QUANTITY	ENGR. EST.	AVERAGE BID	AWARDED BID
=====	304-01005	ABC (CL 1)		Cubic Yard	=====		
STA340A-021		SH340 MP 6-6.76 MESA COUNTY	04/02/20	818.00	65.00	56.33	63.00
		WEIGHTED AVERAGE FOR THE SECOND QUARTER		818.00	65.00	56.33	63.00
		WEIGHTED AVERAGE FOR THE YEAR		918.00	62.28	59.61	64.96
=====	304-02000	ABC (CL 2)		Ton	=====		
NHPP145A-080		SH 145 Keystone-Placerville R	03/05/20	157.00	35.00	47.00	47.00
		WEIGHTED AVERAGE FOR THE FIRST QUARTER		157.00	35.00	47.00	47.00
		WEIGHTED AVERAGE FOR THE YEAR		157.00	35.00	47.00	47.00
=====	304-05000	ABC (CL 5)		Ton	=====		
NHPP 0852-116		US85:HAMPDEN TO FLORIDA-RESUR	02/06/20	1,557.00	40.00	46.00	70.00
		WEIGHTED AVERAGE FOR THE FIRST QUARTER		1,557.00	40.00	46.00	70.00
		WEIGHTED AVERAGE FOR THE YEAR		1,557.00	40.00	46.00	70.00
=====	304-06000	ABC (CL 6)		Ton	=====		
FSA0341-097		US 34 & MACGREGOR INTERSECTIO	01/09/20	719.00	55.00	56.00	56.00
NHPP0343-041		I-76 & US 34 FT. MORGAN AREA	01/09/20	4,459.00	35.00	44.79	44.00
BR0343-040		US 34 REPUBLICAN RIVER BRIDGE	01/16/20	1,727.00	42.00	50.04	42.00
FBR0343-043		US 34 D-28-P STRUCTURE REPLAC					
STR131A-038		SH 131 MP 51.95-55.73, ROUTT	01/16/20	1,085.00	50.00	51.50	53.00
PWQM240-172		El Paso County, north Colorad	01/23/20	1,547.00	45.00	48.00	63.00
STR141A-044		SH 141 AND SH 145, FROM SLICK	01/30/20	5,318.00	25.00	29.55	24.00
C0402-094		US 40 GRAND COUNTY SIGNAL REP	02/27/20	120.00	80.00	80.50	79.00
NHPP0171-105		SH 17 MP 84.5 to US 285 & SH	03/05/20	69,190.00	22.00	27.58	28.73
C0641-106		SH 64 Meeker West Rural Resur	03/05/20	5,145.00	50.00	38.50	32.00
NHPP145A-080		SH 145 Keystone-Placerville R	03/05/20	148.00	60.00	58.00	58.00
NH050A-034		US50A PUEBLO WEST PURCELL INT	03/26/20	70,563.00	24.00	23.00	17.00
SHE 0703-461		I-70 and Kipling North Phase	03/26/20	687.00	70.00	64.40	47.00
		WEIGHTED AVERAGE FOR THE FIRST QUARTER		160,708.00	25.29	25.59	24.85

PROJECT NUMBER	ITEM NUMBER/ PROJECT LOCATION	ITEM DESCRIPTION/ PROJECT LOCATION	DATE LET	UNIT/ QUANTITY	ENGR. EST.	AVERAGE BID	AWARDED BID
===== 304-06000	ABC (CL 6)			Ton	=====	=====	=====
STR092A-030		SH92 MP 31.748-48.5, DELTA AND	04/02/20	1,228.92	38.00	38.25	41.00
IM0252-473		I-25 CABLE BARRIER PHASE IV	04/09/20	6,269.00	25.00	34.59	34.17
SFTY2254-091		225 Ramp Improvements	04/09/20	1,947.00	50.00	67.50	59.00
CC0852-106		US-85 LOUVIERS TO MP 191.75	04/23/20	596.41	35.00	55.99	45.00
FBR0852-108		US-85 BETWEEN LOUVIERS AND MP					
C1601-082		Hawkins Signal and Curb Ramps	04/30/20	533.00	40.00	59.33	56.00
FSA1602-159		US 160 AND SH 17 INTERSECTION	04/30/20	3,633.00	45.00	49.33	58.00
C0853-112		US85 & WCR98 INTERSECTION IMP	05/07/20	12,110.00	30.00	29.15	20.00
NHPP0402-098		US 40 CHIP SEAL MP 126 TO MP	05/14/20	14.00	26.00	193.33	345.00
NH050A-035		US 50A Pueblo Regional Pond	05/28/20	358.00	30.00	41.53	29.00
NH050A-037		US 50A Pueblo Regional Pond					
	WEIGHTED AVERAGE FOR THE SECOND QUARTER			26,689.33	33.00	34.14	33.88
	WEIGHTED AVERAGE FOR THE YEAR			187,397.33	26.39	26.78	26.14
===== 304-06007	ABC (CL 6)			Cubic Yard	=====	=====	=====
FSA0253-262		I-25 SB BOTTLENECK I-76 TO I-	01/09/20	389.00	50.00	74.68	70.00
STA059A-036		SH 59 SEIBERT TO COPE	02/06/20	493.00	75.00	109.00	134.00
STR116A-001		SH 116 A Surface Treatment Pr	02/13/20	309.00	70.00	101.67	92.00
FSA2873-194		US 287 Longmont Intersection	02/13/20	619.00	60.00	85.00	75.00
STA069A-033		SH69 MP 58.7 TO 71.58	02/13/20	774.00	55.00	58.20	64.00
STR0101-027		SH 10 Overlay La Junta West	02/27/20	1,266.00	45.00	55.45	40.00
STR2871-038		US 287 Passing Lanes Springfi	03/05/20	11,490.00	50.00	63.53	55.00
BR025A-046		K-18-U ON I-25 AT MP112 BRIDG	03/05/20	230.00	45.00	58.97	55.34
STRR300-249		Grand and Jackson Counties AD	03/05/20	315.00	78.67	131.00	75.00
CC080-037		VARIOUS ADA RAMPS ALONG NORTH	03/05/20	83.00	100.00	91.78	86.00
NHPP0091-044		SH 9 FRISCO MAIN ST TO IRON S	03/05/20	11,054.00	25.00	66.42	58.00
HPP 0501-067		US 50 AND SH 92 DELTA INTERSE	03/26/20	1,867.00	45.00	99.15	65.10
	WEIGHTED AVERAGE FOR THE FIRST QUARTER			28,889.00	41.30	69.25	59.07
IM0761-226		I76/SH52 Interchange	04/02/20	11,240.00	55.00	50.82	49.70
STA340A-021		SH340 MP 6-6.76 MESA COUNTY	04/02/20	540.00	67.00	68.17	76.00
NHPPR100-303		LONG MAST ARM SIGNALS PROJECT	05/07/20	124.00	80.00	123.33	155.00
FBR0343-042		US 34 D-27-G STRUCTURE REPLAC	05/07/20	503.00	50.00	111.26	102.00
NHPP0253-276		I-25 EXPRESS LANES SEGMENT 5	05/15/20	2,426.00	47.00	54.24	54.24
	WEIGHTED AVERAGE FOR THE SECOND QUARTER			14,833.00	54.17	54.67	54.05
	WEIGHTED AVERAGE FOR THE YEAR			43,722.00	45.66	61.39	57.37

COLORADO DEPARTMENT OF TRANSPORTATION
ITEM UNIT COSTS BY PROJECTS -- 2020 COST DATA

10:58 Friday, October 2, 2020 116

PROJECT NUMBER	ITEM NUMBER/ PROJECT LOCATION	ITEM DESCRIPTION/ PROJECT LOCATION	DATE LET	UNIT/ QUANTITY	ENGR. EST.	AVERAGE BID	AWARDED BID
===== 304-06008		ABC (CL 6) (Spec)		Cubic Yard	=====		
IM0761-226		I76/SH52 Interchange	04/02/20	270.00	65.00	95.54	71.00
	WEIGHTED	AVERAGE FOR THE SECOND QUARTER		270.00	65.00	95.54	71.00
		WEIGHTED AVERAGE FOR THE YEAR		270.00	65.00	95.54	71.00
===== 304-07000		ABC (CL 7)		Ton	=====		
STR092A-030		SH92 MP 31.748-48.5, DELTA AND	04/02/20	12,248.40	30.00	32.00	24.00
	WEIGHTED	AVERAGE FOR THE SECOND QUARTER		12,248.40	30.00	32.00	24.00
		WEIGHTED AVERAGE FOR THE YEAR		12,248.40	30.00	32.00	24.00
===== 304-07009		ABC (CL 7) (Spec)		Ton	=====		
STA0142-066		SH 14 New Raymer West	01/09/20	8,284.00	22.50	21.25	22.00
STA006A-067		SH 6 Merino to Atwood	01/16/20	2,879.00	22.50	28.38	23.50
	WEIGHTED	AVERAGE FOR THE FIRST QUARTER		11,163.00	22.50	22.31	22.39
		WEIGHTED AVERAGE FOR THE YEAR		11,163.00	22.50	22.31	22.39
===== 304-07010		ABC (CL 7) (Spec)		Cubic Yard	=====		
FSA2873-194		US 287 Longmont Intersection	02/13/20	61.00	45.00	117.67	92.00
	WEIGHTED	AVERAGE FOR THE FIRST QUARTER		61.00	45.00	117.67	92.00
		WEIGHTED AVERAGE FOR THE YEAR		61.00	45.00	117.67	92.00
===== 304-08000		ABC (Shoulder Material)		Ton	=====		
NHPP0343-041		I-76 & US 34 FT. MORGAN AREA	01/09/20	1,423.00	30.00	41.67	31.00
	WEIGHTED	AVERAGE FOR THE FIRST QUARTER		1,423.00	30.00	41.67	31.00
		WEIGHTED AVERAGE FOR THE YEAR		1,423.00	30.00	41.67	31.00

COLORADO DEPARTMENT OF TRANSPORTATION
ITEM UNIT COSTS BY PROJECTS -- 2020 COST DATA

10:58 Friday, October 2, 2020 117

PROJECT NUMBER	ITEM NUMBER/ PROJECT LOCATION	ITEM DESCRIPTION/ PROJECT LOCATION	DATE LET	UNIT/ QUANTITY	ENGR. EST.	AVERAGE BID	AWARDED BID
===== 304-08002		ABC (Shoulder Material)		Cubic Yard	=====		
STR116A-001		SH 116 A Surface Treatment Pr	02/13/20	3,952.00	50.00	72.45	80.00
STR0101-027		SH 10 Overlay La Junta West	02/27/20	5,958.00	45.00	31.88	24.00
NH0242-085		US 24 M.P. 291.38 to M.P. 296	02/27/20	613.00	45.00	99.28	95.00
		WEIGHTED AVERAGE FOR THE FIRST QUARTER		10,523.00	46.88	51.04	49.17
STR0341-101		SH 34 North of Grandby Resurf	04/02/20	1,504.00	50.00	75.87	90.30
NHPP0253-276		I-25 EXPRESS LANES SEGMENT 5	05/15/20	98.00	300.00	382.66	382.66
		WEIGHTED AVERAGE FOR THE SECOND QUARTER		1,602.00	65.29	80.79	108.18
		WEIGHTED AVERAGE FOR THE YEAR		12,125.00	49.31	55.87	56.96
===== 304-09000		ABC (Spec)		Cubic Yard	=====		
C1601-082		Hawkins Signal and Curb Ramps	04/30/20	1.00	70.00	690.00	1100.00
		WEIGHTED AVERAGE FOR THE SECOND QUARTER		1.00	70.00	690.00	1100.00
		WEIGHTED AVERAGE FOR THE YEAR		1.00	70.00	690.00	1100.00
===== 304-09014		ABC (Spec)		Ton	=====		
STR141A-044		SH 141 AND SH 145, FROM SLICK	01/30/20	13,038.00	27.00	31.78	26.75
NHPP0171-105		SH 17 MP 84.5 to US 285 & SH	03/05/20	17,797.00	25.00	25.74	21.67
NHPP145A-080		SH 145 Keystone-Placerville R	03/05/20	2,079.00	84200.00	45.00	45.00
		WEIGHTED AVERAGE FOR THE FIRST QUARTER		32,914.00	5342.67	29.33	25.16
NHPP1602-169		US 160 WC TUNNEL EAST RESURFA	04/02/20	4,043.00	40.00	38.57	40.22
FSA1602-159		US 160 AND SH 17 INTERSECTION	04/30/20	201.00	45.00	65.00	54.00
		WEIGHTED AVERAGE FOR THE SECOND QUARTER		4,244.00	40.24	39.82	40.87
		WEIGHTED AVERAGE FOR THE YEAR		37,158.00	4737.06	30.33	26.95
===== 304-09100		ABC (RAP)		Ton	=====		
NHPP0253-276		I-25 EXPRESS LANES SEGMENT 5	05/15/20	1,777.00	10.00	22.08	22.08
		WEIGHTED AVERAGE FOR THE SECOND QUARTER		1,777.00	10.00	22.08	22.08
		WEIGHTED AVERAGE FOR THE YEAR		1,777.00	10.00	22.08	22.08

COLORADO DEPARTMENT OF TRANSPORTATION
 ITEM UNIT COSTS BY PROJECTS -- 2020 COST DATA

10:58 Friday, October 2, 2020 118

PROJECT NUMBER	ITEM NUMBER/ PROJECT LOCATION	ITEM DESCRIPTION/ PROJECT LOCATION	DATE LET	UNIT/ QUANTITY	ENGR. EST.	AVERAGE BID	AWARDED BID
===== 310-00608		Full Depth Reclam. of HMA Pvmt (0-8 in.)		Sq Yard	=====		
IM0761-226		I76/SH52 Interchange	04/02/20	10,341.00	4.50	3.43	3.50
STA340A-021		SH340 MP 6-6.76 MESA COUNTY	04/02/20	7,967.00	3.00	5.55	4.00
		WEIGHTED AVERAGE FOR THE SECOND QUARTER		18,308.00	3.85	3.95	3.72
		WEIGHTED AVERAGE FOR THE YEAR		18,308.00	3.85	3.95	3.72
===== 310-00610		Full Depth Reclam. of HMA Pvmt (8-12 in)		Sq Yard	=====		
STR141A-044		SH 141 AND SH 145, FROM SLICK	01/30/20	53,310.00	2.50	3.52	2.10
NHPP0091-044		SH 9 FRISCO MAIN ST TO IRON S	03/05/20	40,950.00	3.00	4.45	4.80
		WEIGHTED AVERAGE FOR THE FIRST QUARTER		94,260.00	2.72	3.81	3.27
IM0761-226		I76/SH52 Interchange	04/02/20	5,170.00	6.00	4.44	5.00
		WEIGHTED AVERAGE FOR THE SECOND QUARTER		5,170.00	6.00	4.44	5.00
		WEIGHTED AVERAGE FOR THE YEAR		99,430.00	2.89	3.87	3.36
===== 310-00614		Full Depth Reclam of HMA Pvmt (12-16 in)		Sq Yard	=====		
IM0761-226		I76/SH52 Interchange	04/02/20	3,103.00	7.00	6.41	8.50
		WEIGHTED AVERAGE FOR THE SECOND QUARTER		3,103.00	7.00	6.41	8.50
		WEIGHTED AVERAGE FOR THE YEAR		3,103.00	7.00	6.41	8.50
===== 403-00720		HMA (Patching) (Asph)		Ton	=====		
STA0142-066		SH 14 New Raymer West	01/09/20	400.00	180.00	210.63	188.50
FSA0253-262		I-25 SB BOTTLENECK I-76 TO I-	01/09/20	21.00	150.00	380.14	480.00
FSA0341-097		US 34 & MACGREGOR INTERSECTIO	01/09/20	161.00	220.00	210.00	210.00
NHPP0343-041		I-76 & US 34 FT. MORGAN AREA	01/09/20	2,343.00	165.00	181.20	220.00
BR0343-040		US 34 REPUBLICAN RIVER BRIDGE	01/16/20	167.00	335.00	333.64	330.00
FBR0343-043		US 34 D-28-P STRUCTURE REPLAC					
STA006A-067		SH 6 Merino to Atwood	01/16/20	600.00	180.00	158.26	175.00

PROJECT NUMBER	ITEM NUMBER/ PROJECT LOCATION	ITEM DESCRIPTION/ PROJECT LOCATION	DATE LET	UNIT/ QUANTITY	ENGR. EST.	AVERAGE BID	AWARDED BID
===== 403-00720				HMA (Patching) (Asph) Ton =====			
STR131A-038		SH 131 MP 51.95-55.73, ROUTT	01/16/20	50.00	200.00	253.50	207.00
NH 0503-093		US50 WEST OF TEXAS CREEK MP 2	01/23/20	481.00	120.00	149.56	159.11
NHPP 0852-116		US85:HAMPDEN TO FLORIDA-RESUR	02/06/20	50.00	130.00	252.50	300.00
STA0703-443		I-70 EJMT TUNNELS PAVING	02/06/20	132.00	300.00	382.26	339.51
STA059A-036		SH 59 SEIBERT TO COPE	02/06/20	1,294.00	185.00	193.00	176.00
STR116A-001		SH 116 A Surface Treatment Pr	02/13/20	100.00	200.00	161.59	150.00
STA069A-033		SH69 MP 58.7 TO 71.58	02/13/20	500.00	175.00	145.76	128.00
STR0101-027		SH 10 Overlay La Junta West	02/27/20	2,499.00	125.00	144.42	108.00
NH0242-085		US 24 M.P. 291.38 to M.P. 296	02/27/20	500.00	135.00	186.50	150.00
NHPP145A-080		SH 145 Keystone-Placerville R	03/05/20	40.00	300.00	260.00	260.00
BR025A-046		K-18-U ON I-25 AT MP112 BRIDG	03/05/20	10.00	150.00	552.67	642.79
NHPP0091-044		SH 9 FRISCO MAIN ST TO IRON S	03/05/20	22.00	300.00	463.33	540.00
NH050A-034		US50A PUEBLO WEST PURCELL INT	03/26/20	500.00	175.00	183.08	170.00
HPP 0501-067		US 50 AND SH 92 DELTA INTERSE	03/26/20	163.00	200.00	246.70	196.00
SHE 0703-461		I-70 and Kipling North Phase	03/26/20	184.00	300.00	196.40	120.00
WEIGHTED AVERAGE FOR THE FIRST QUARTER				10,217.00	166.11	182.45	172.35
NHPP1602-169		US 160 WC TUNNEL EAST RESURFA	04/02/20	337.00	220.00	208.43	248.18
STR092A-030		SH92 MP 31.748-48.5,DELTA AND	04/02/20	693.00	175.00	203.50	200.00
IM0761-226		I76/SH52 Interchange	04/02/20	212.00	220.00	164.24	145.75
IM0252-473		I-25 CABLE BARRIER PHASE IV	04/09/20	320.00	150.00	164.72	164.44
CC0852-106		US-85 LOUVIERS TO MP 191.75	04/23/20	155.40	130.00	179.55	110.00
FBR0852-108		US-85 BETWEEN LOUVIERS AND MP					
C1211-090		SH-121 & 29th Ave / SH-121 &	04/23/20	25.00	190.00	225.50	398.00
C1601-082		Hawkins Signal and Curb Ramps	04/30/20	100.00	250.00	334.50	203.50
FSA1602-159		US 160 AND SH 17 INTERSECTION	04/30/20	1,540.00	120.00	260.33	263.00
C0853-112		US85 & WCR98 INTERSECTION IMP	05/07/20	700.00	180.00	139.89	140.00
NHPPR100-303		LONG MAST ARM SIGNALS PROJECT	05/07/20	20.00	250.00	336.67	405.00
FBR0343-042		US 34 D-27-G STRUCTURE REPLAC	05/07/20	48.00	335.00	362.03	360.00
NHPP0402-098		US 40 CHIP SEAL MP 126 TO MP	05/14/20	10.00	230.00	404.33	395.00
NHPP0253-276		I-25 EXPRESS LANES SEGMENT 5	05/15/20	30.00	200.00	226.97	226.97
SHE016A-043		SH 21 & 16 SIGNALS PROJECT	06/18/20	15.10	500.00	435.80	346.49
WEIGHTED AVERAGE FOR THE SECOND QUARTER				4,205.50	163.53	199.98	213.42
WEIGHTED AVERAGE FOR THE YEAR				14,422.50	165.35	188.68	184.33
===== 403-00721				HMA (Patching) (Asph) Sq Yard =====			
FSA2873-194		US 287 Longmont Intersection	02/13/20	20.00	250.00	275.83	285.00
C0402-094		US 40 GRAND COUNTY SIGNAL REP	02/27/20	157.00	75.00	204.50	268.00
NHPP0171-105		SH 17 MP 84.5 to US 285 & SH	03/05/20	100.00	100.00	123.03	79.08

COLORADO DEPARTMENT OF TRANSPORTATION
ITEM UNIT COSTS BY PROJECTS -- 2020 COST DATA

10:58 Friday, October 2, 2020 120

PROJECT NUMBER	ITEM NUMBER/ PROJECT LOCATION	ITEM DESCRIPTION/ PROJECT LOCATION	DATE LET	UNIT/ QUANTITY	ENGR. EST.	AVERAGE BID	AWARDED BID
=====	403-00721	HMA (Patching) (Asph)		Sq Yard	=====	=====	=====
NHPP0502-082		US 50 MONTROSE RE CHIP SEAL	03/05/20	100.00	250.00	162.50	200.00
STRR300-249		Grand and Jackson Counties AD	03/05/20	737.00	75.00	144.67	141.00
CC080-037		VARIOUS ADA RAMP ALONG NORTH	03/05/20	11.00	150.00	130.88	120.00
		WEIGHTED AVERAGE FOR THE FIRST QUARTER		1,125.00	96.62	154.87	160.82
NHPP1602-169		US 160 WC TUNNEL EAST RESURFA	04/02/20	100.00	165.00	136.54	162.22
STR0341-101		SH 34 North of Grandby Resurf	04/02/20	1,540.00	50.00	32.13	31.40
ITS SW02-304		ITS FIBER TO STATE BUILDINGS	05/14/20	500.00	100.00	99.25	149.00
ITSSW01-719		FY 20 ITS CAPITAL REPLACEMENT	06/11/20	396.00	175.00	157.50	65.00
FSAR400-356		FY 20 SIGNAL POLE REPLACEMENT	06/11/20	28.00	450.00	290.00	305.00
		WEIGHTED AVERAGE FOR THE SECOND QUARTER		2,564.00	87.91	62.82	67.61
		WEIGHTED AVERAGE FOR THE YEAR		3,689.00	90.57	87.33	96.04
=====	403-00800	Emerg Pothole Rep		Ton	=====	=====	=====
CC0852-106		US-85 LOUVIERS TO MP 191.75	04/23/20	30.00	400.00	280.79	143.00
FBR0852-108		US-85 BETWEEN LOUVIERS AND MP					
		WEIGHTED AVERAGE FOR THE SECOND QUARTER		30.00	400.00	280.79	143.00
		WEIGHTED AVERAGE FOR THE YEAR		30.00	400.00	280.79	143.00
=====	403-05000	HMA (RCI)		Ton	=====	=====	=====
STA0142-066		SH 14 New Raymer West	01/09/20	11,208.00	183.00	185.00	170.00
		WEIGHTED AVERAGE FOR THE FIRST QUARTER		11,208.00	183.00	185.00	170.00
		WEIGHTED AVERAGE FOR THE YEAR		11,208.00	183.00	185.00	170.00
=====	403-09221	SMA (Fibers) (Asph)		Ton	=====	=====	=====
STA0703-443		I-70 EJMT TUNNELS PAVING	02/06/20	16,176.00	140.00	146.10	132.24
NHPP4701-134		C-470 NOISE WALL WEST OF LUCE	02/06/20	287.00	250.00	230.60	281.00
		WEIGHTED AVERAGE FOR THE FIRST QUARTER		16,463.00	141.92	149.68	134.83
		WEIGHTED AVERAGE FOR THE YEAR		16,463.00	141.92	149.68	134.83

COLORADO DEPARTMENT OF TRANSPORTATION
 ITEM UNIT COSTS BY PROJECTS -- 2020 COST DATA

10:58 Friday, October 2, 2020 121

PROJECT NUMBER	ITEM NUMBER/ PROJECT LOCATION	ITEM DESCRIPTION/ PROJECT LOCATION	DATE LET	UNIT/ QUANTITY	ENGR. EST.	AVERAGE BID	AWARDED BID
=====	403-33721	HMA (Gr S) (75) (PG 58-28)		Ton	=====	=====	=====
NH050A-034		US50A PUEBLO WEST PURCELL INT	03/26/20	45,523.00	85.00	87.85	80.50
		WEIGHTED AVERAGE FOR THE FIRST QUARTER		45,523.00	85.00	87.85	80.50
		WEIGHTED AVERAGE FOR THE YEAR		45,523.00	85.00	87.85	80.50
=====	403-33731	HMA (Gr S) (75) (PG 58-34)		Ton	=====	=====	=====
FSA0341-097		US 34 & MACGREGOR INTERSECTIO	01/09/20	239.00	140.00	175.00	175.00
		WEIGHTED AVERAGE FOR THE FIRST QUARTER		239.00	140.00	175.00	175.00
		WEIGHTED AVERAGE FOR THE YEAR		239.00	140.00	175.00	175.00
=====	403-33841	HMA (Gr S) (100) (PG 64-22)		Ton	=====	=====	=====
SHE 0703-461		I-70 and Kipling North Phase	03/26/20	193.00	200.00	146.80	114.00
		WEIGHTED AVERAGE FOR THE FIRST QUARTER		193.00	200.00	146.80	114.00
IM0761-226		I76/SH52 Interchange	04/02/20	618.00	123.00	108.21	122.96
CC0852-106		US-85 LOUVIERS TO MP 191.75	04/23/20	667.14	100.00	101.84	88.00
FBR0852-108		US-85 BETWEEN LOUVIERS AND MP					
		WEIGHTED AVERAGE FOR THE SECOND QUARTER		1,285.14	111.06	104.69	104.81
		WEIGHTED AVERAGE FOR THE YEAR		1,478.14	122.67	108.51	106.01
=====	403-34701	HMA (Gr SX) (75)		Ton	=====	=====	=====
STR131A-038		SH 131 MP 51.95-55.73, ROUTT	01/16/20	5,205.00	72.00	85.90	76.80
C0641-106		SH 64 Meeker West Rural Resur	03/05/20	22,811.00	70.00	53.25	49.00
NHPP0091-044		SH 9 FRISCO MAIN ST TO IRON S	03/05/20	18,248.00	85.00	121.67	130.00
		WEIGHTED AVERAGE FOR THE FIRST QUARTER		46,264.00	76.14	90.13	84.08
STR092A-030		SH92 MP 31.748-48.5, DELTA AND	04/02/20	22,842.57	55.00	73.10	55.50

COLORADO DEPARTMENT OF TRANSPORTATION
 ITEM UNIT COSTS BY PROJECTS -- 2020 COST DATA

10:58 Friday, October 2, 2020 122

PROJECT NUMBER	ITEM NUMBER/ PROJECT LOCATION	ITEM DESCRIPTION/ PROJECT LOCATION	DATE LET	UNIT/ QUANTITY	ENGR. EST.	AVERAGE BID	AWARDED BID
===== 403-34701		HMA (Gr SX) (75)		Ton =====			
STA340A-021	SH340 MP 6-6.76 MESA COUNTY	SH340 MP 6-6.76 MESA COUNTY	04/02/20	4,036.00	80.00	81.23	75.00
STR0341-101	SH 34 North of Grandby Resurf	SH 34 North of Grandby Resurf	04/02/20	35,472.00	60.00	67.83	65.90
	WEIGHTED AVERAGE FOR THE SECOND QUARTER			62,350.57	59.46	69.85	62.68
	WEIGHTED AVERAGE FOR THE YEAR			108,614.57	66.57	77.08	71.79
===== 403-34721		HMA (Gr SX) (75) (PG 58-28)		Ton =====			
NH 0503-093	US50 WEST OF TEXAS CREEK MP 2	US50 WEST OF TEXAS CREEK MP 2	01/23/20	37,383.00	80.00	82.82	88.64
STR116A-001	SH 116 A Surface Treatment Pr	SH 116 A Surface Treatment Pr	02/13/20	43,041.00	95.00	93.33	89.00
STA069A-033	SH69 MP 58.7 TO 71.58	SH69 MP 58.7 TO 71.58	02/13/20	21,860.70	80.00	87.50	86.00
STR0101-027	SH 10 Overlay La Junta West	SH 10 Overlay La Junta West	02/27/20	33,015.00	85.00	84.62	79.00
NHPP0171-105	SH 17 MP 84.5 to US 285 & SH	SH 17 MP 84.5 to US 285 & SH	03/05/20	24,478.00	75.00	80.77	62.30
NHPP145A-080	SH 145 Keystone-Placerville R	SH 145 Keystone-Placerville R	03/05/20	17,480.00	1821625.00	103.00	103.00
BR025A-046	K-18-U ON I-25 AT MP112 BRIDG	K-18-U ON I-25 AT MP112 BRIDG	03/05/20	345.00	85.00	193.10	187.72
	WEIGHTED AVERAGE FOR THE FIRST QUARTER			177,602.70	179363.85	87.84	84.59
IM0252-473	I-25 CABLE BARRIER PHASE IV	I-25 CABLE BARRIER PHASE IV	04/09/20	3,152.00	95.00	133.61	112.22
	WEIGHTED AVERAGE FOR THE SECOND QUARTER			3,152.00	95.00	133.61	112.22
	WEIGHTED AVERAGE FOR THE YEAR			180,754.70	176237.76	88.49	85.07
===== 403-34731		HMA (Gr SX) (75) (PG 58-34)		Ton =====			
NHPP0171-105	SH 17 MP 84.5 to US 285 & SH	SH 17 MP 84.5 to US 285 & SH	03/05/20	87,233.00	82.00	88.92	83.27
	WEIGHTED AVERAGE FOR THE FIRST QUARTER			87,233.00	82.00	88.92	83.27
NHPP1602-169	US 160 WC TUNNEL EAST RESURFA	US 160 WC TUNNEL EAST RESURFA	04/02/20	21,004.00	109.00	110.21	109.00
	WEIGHTED AVERAGE FOR THE SECOND QUARTER			21,004.00	109.00	110.21	109.00
	WEIGHTED AVERAGE FOR THE YEAR			108,237.00	87.24	93.05	88.26
===== 403-34741		HMA (Gr SX) (75) (PG 64-22)		Ton =====			
STR141A-044	SH 141 AND SH 145, FROM SLICK	SH 141 AND SH 145, FROM SLICK	01/30/20	78,571.00	78.00	88.96	76.50
	WEIGHTED AVERAGE FOR THE FIRST QUARTER			78,571.00	78.00	88.96	76.50

COLORADO DEPARTMENT OF TRANSPORTATION
 ITEM UNIT COSTS BY PROJECTS -- 2020 COST DATA

10:58 Friday, October 2, 2020 123

PROJECT NUMBER	ITEM NUMBER/ PROJECT LOCATION	ITEM DESCRIPTION/ PROJECT LOCATION	DATE LET	UNIT/ QUANTITY	ENGR. EST.	AVERAGE BID	AWARDED BID
===== 403-34741	HMA (Gr SX) (75) (PG 64-22)			Ton			
C0853-112		US85 & WCR98 INTERSECTION IMP	05/07/20	4,251.00	97.00	95.38	90.00
NHPPR100-303		LONG MAST ARM SIGNALS PROJECT	05/07/20	65.16	200.00	303.67	350.00
NHPP0253-276		I-25 EXPRESS LANES SEGMENT 5	05/15/20	3,517.00	92.00	92.95	92.95
	WEIGHTED AVERAGE FOR THE SECOND QUARTER			7,833.16	95.61	96.23	93.49
	WEIGHTED AVERAGE FOR THE YEAR			86,404.16	79.60	89.60	78.04
===== 403-34751	HMA (Gr SX) (75) (PG 64-28)			Ton			
STA0142-066		SH 14 New Raymer West	01/09/20	25,496.00	83.00	93.40	88.60
NHPP0343-041		I-76 & US 34 FT. MORGAN AREA	01/09/20	52,375.00	82.00	110.58	97.00
BR0343-040		US 34 REPUBLICAN RIVER BRIDGE	01/16/20	1,734.00	160.00	151.32	136.00
FBR0343-043		US 34 D-28-P STRUCTURE REPLAC					
STA006A-067		SH 6 Merino to Atwood	01/16/20	32,095.00	84.50	106.48	88.00
STA059A-036		SH 59 SEIBERT TO COPE	02/06/20	86,105.00	84.00	99.13	98.25
NH050A-034		US50A PUEBLO WEST PURCELL INT	03/26/20	20,982.00	80.00	100.39	91.50
	WEIGHTED AVERAGE FOR THE FIRST QUARTER			218,787.00	83.70	102.75	94.97
C1211-090		SH-121 & 29th Ave / SH-121 &	04/23/20	171.00	95.00	169.45	205.00
C0853-112		US85 & WCR98 INTERSECTION IMP	05/07/20	3,358.00	115.00	99.73	93.00
FBR0343-042		US 34 D-27-G STRUCTURE REPLAC	05/07/20	1,627.00	160.00	154.76	142.00
NHPP0253-276		I-25 EXPRESS LANES SEGMENT 5	05/15/20	1,115.00	95.00	96.19	96.19
	WEIGHTED AVERAGE FOR THE SECOND QUARTER			6,271.00	122.57	119.15	109.33
	WEIGHTED AVERAGE FOR THE YEAR			225,058.00	84.78	103.74	95.37
===== 403-34801	HMA (Gr SX) (100)			Ton			
HPP 0501-067		US 50 AND SH 92 DELTA INTERSE	03/26/20	665.00	150.00	114.83	84.00
	WEIGHTED AVERAGE FOR THE FIRST QUARTER			665.00	150.00	114.83	84.00
	WEIGHTED AVERAGE FOR THE YEAR			665.00	150.00	114.83	84.00
===== 403-34851	HMA (Gr SX) (100) (PG 64-28)			Ton			
NHPP0343-041		I-76 & US 34 FT. MORGAN AREA	01/09/20	36,086.00	90.00	108.94	97.00
	WEIGHTED AVERAGE FOR THE FIRST QUARTER			36,086.00	90.00	108.94	97.00
	WEIGHTED AVERAGE FOR THE YEAR			36,086.00	90.00	108.94	97.00

COLORADO DEPARTMENT OF TRANSPORTATION
 ITEM UNIT COSTS BY PROJECTS -- 2020 COST DATA

10:58 Friday, October 2, 2020 124

PROJECT NUMBER	ITEM NUMBER/ PROJECT LOCATION	ITEM DESCRIPTION/ PROJECT LOCATION	DATE LET	UNIT/ QUANTITY	ENGR. EST.	AVERAGE BID	AWARDED BID
===== 403-34871		HMA (Gr SX) (100) (PG 76-28)		Ton	=====	=====	=====
NHPP 0852-116		US85:HAMPDEN TO FLORIDA-RESUR	02/06/20	1,008.00	200.00	123.50	140.00
NH0242-085		US 24 M.P. 291.38 to M.P. 296	02/27/20	31,730.00	80.00	93.75	80.25
SHE 0703-461		I-70 and Kipling North Phase	03/26/20	56.00	200.00	219.80	235.00
		WEIGHTED AVERAGE FOR THE FIRST QUARTER		32,794.00	83.89	94.73	82.35
IM0761-226		I76/SH52 Interchange	04/02/20	1,251.00	150.00	132.46	137.48
SFTY2254-091		225 Ramp Improvements	04/09/20	185.00	175.00	240.00	180.00
CC0852-106		US-85 LOUVIERS TO MP 191.75	04/23/20	251.00	110.00	153.08	143.00
FBR0852-108		US-85 BETWEEN LOUVIERS AND MP					
		WEIGHTED AVERAGE FOR THE SECOND QUARTER		1,687.00	146.79	139.75	142.96
		WEIGHTED AVERAGE FOR THE YEAR		34,481.00	86.97	99.34	85.32
===== 403-36621		HMA (Gr ST) (50) (PG 58-28)		Ton	=====	=====	=====
STR116A-001		SH 116 A Surface Treatment Pr	02/13/20	30,279.00	109.00	98.00	96.00
STA069A-033		SH69 MP 58.7 TO 71.58	02/13/20	12,473.20	85.00	99.50	93.00
STR0101-027		SH 10 Overlay La Junta West	02/27/20	20,768.00	85.00	88.33	85.00
		WEIGHTED AVERAGE FOR THE FIRST QUARTER		63,520.20	96.44	94.83	91.81
		WEIGHTED AVERAGE FOR THE YEAR		63,520.20	96.44	94.83	91.81
===== 403-36701		HMA (Gr ST) (75)		Ton	=====	=====	=====
C0641-106		SH 64 Meeker West Rural Resur	03/05/20	16,390.00	72.00	60.05	53.00
		WEIGHTED AVERAGE FOR THE FIRST QUARTER		16,390.00	72.00	60.05	53.00
STR092A-030		SH92 MP 31.748-48.5, DELTA AND	04/02/20	13,933.50	70.00	85.75	63.50
STR0341-101		SH 34 North of Grandby Resurf	04/02/20	23,733.00	65.00	72.71	70.30
		WEIGHTED AVERAGE FOR THE SECOND QUARTER		37,666.50	66.85	75.67	67.78
		WEIGHTED AVERAGE FOR THE YEAR		54,056.50	68.41	72.38	63.30

COLORADO DEPARTMENT OF TRANSPORTATION
ITEM UNIT COSTS BY PROJECTS -- 2020 COST DATA

10:58 Friday, October 2, 2020 125

PROJECT NUMBER	ITEM NUMBER/ PROJECT LOCATION	ITEM DESCRIPTION/ PROJECT LOCATION	DATE LET	UNIT/ QUANTITY	ENGR. EST.	AVERAGE BID	AWARDED BID
=====	403-36721	HMA (Gr ST) (75) (PG 58-28)		Ton	=====	=====	=====
STR141A-044		SH 141 AND SH 145, FROM SLICK	01/30/20	23,663.00	85.00	105.47	86.00
NHPP145A-080		SH 145 Keystone-Placerville R	03/05/20	9,865.00	811155.00	105.00	105.00
		WEIGHTED AVERAGE FOR THE FIRST QUARTER		33,528.00	238727.49	105.44	91.59
NHPP1602-169		US 160 WC TUNNEL EAST RESURFA	04/02/20	15,009.00	110.00	113.93	108.50
		WEIGHTED AVERAGE FOR THE SECOND QUARTER		15,009.00	110.00	113.93	108.50
		WEIGHTED AVERAGE FOR THE YEAR		48,537.00	164940.28	107.64	96.82
=====	405-00100	Heating and Remixing Treatment		Sq Yard	=====	=====	=====
NHPP0171-105		SH 17 MP 84.5 to US 285 & SH	03/05/20	673,117.00	4.20	3.58	3.23
		WEIGHTED AVERAGE FOR THE FIRST QUARTER		673,117.00	4.20	3.58	3.23
		WEIGHTED AVERAGE FOR THE YEAR		673,117.00	4.20	3.58	3.23
=====	408-01000	Hot Joint-Crack Sealant		Ton	=====	=====	=====
NHPP0502-082		US 50 MONTROSE RE CHIP SEAL	03/05/20	45.00	4000.00	5275.00	3600.00
		WEIGHTED AVERAGE FOR THE FIRST QUARTER		45.00	4000.00	5275.00	3600.00
		WEIGHTED AVERAGE FOR THE YEAR		45.00	4000.00	5275.00	3600.00
=====	408-01100	Joint Sealant		Lin Foot	=====	=====	=====
NHPP0343-041		I-76 & US 34 FT. MORGAN AREA	01/09/20	3,206.00	13.00	26.76	27.00
BR0343-040		US 34 REPUBLICAN RIVER BRIDGE	01/16/20	386.00	20.00	19.02	25.00
FBR0343-043		US 34 D-28-P STRUCTURE REPLAC					
NHPP 0852-116		US85:HAMPDEN TO FLORIDA-RESUR	02/06/20	241.00	25.00	20.00	25.00
STA059A-036		SH 59 SEIBERT TO COPE	02/06/20	429.00	28.00	30.50	28.00
		WEIGHTED AVERAGE FOR THE FIRST QUARTER		4,262.00	15.82	25.41	26.81
FBR0343-042		US 34 D-27-G STRUCTURE REPLAC	05/07/20	192.00	25.00	31.32	11.00
		WEIGHTED AVERAGE FOR THE SECOND QUARTER		192.00	25.00	31.32	11.00
		WEIGHTED AVERAGE FOR THE YEAR		4,454.00	16.22	26.09	26.13

COLORADO DEPARTMENT OF TRANSPORTATION
 ITEM UNIT COSTS BY PROJECTS -- 2020 COST DATA

10:58 Friday, October 2, 2020 126

PROJECT NUMBER	ITEM NUMBER/ PROJECT LOCATION	ITEM DESCRIPTION/ PROJECT LOCATION	DATE LET	UNIT/ QUANTITY	ENGR. EST.	AVERAGE BID	AWARDED BID
===== 409-01015		CC Matl (Ty I)		Sq Yard			
NHPP0502-082		US 50 MONTROSE RE CHIP SEAL	03/05/20	1,107,884.00	0.88	1.31	0.85
		WEIGHTED AVERAGE FOR THE FIRST QUARTER		1,107,884.00	0.88	1.31	0.85
NHPP1601-077		US 160 MP 29.750 - MP 34.891	04/09/20	130,383.00	1.10	0.93	0.75
NHPP0402-098		US 40 CHIP SEAL MP 126 TO MP	05/14/20	191,375.00	1.25	1.37	1.20
		WEIGHTED AVERAGE FOR THE SECOND QUARTER		321,758.00	1.19	1.19	1.02
		WEIGHTED AVERAGE FOR THE YEAR		1,429,642.00	0.95	1.29	0.89
===== 409-02015		CC Matl (Ty II)		Sq Yard			
NHPP1601-077		US 160 MP 29.750 - MP 34.891	04/09/20	130,383.00	1.25	0.97	0.75
		WEIGHTED AVERAGE FOR THE SECOND QUARTER		130,383.00	1.25	0.97	0.75
		WEIGHTED AVERAGE FOR THE YEAR		130,383.00	1.25	0.97	0.75
===== 409-09000		Micro-Surfacing Seal Coat		Ton			
NHPP1601-077		US 160 MP 29.750 - MP 34.891	04/09/20	2,054.00	350.00	241.67	210.00
		WEIGHTED AVERAGE FOR THE SECOND QUARTER		2,054.00	350.00	241.67	210.00
		WEIGHTED AVERAGE FOR THE YEAR		2,054.00	350.00	241.67	210.00
===== 411-03352		Asph Cem (PG 58-28)		Ton			
C0641-106		SH 64 Meeker West Rural Resur	03/05/20	1,108.00	550.00	360.00	300.00
NHPP0091-044		SH 9 FRISCO MAIN ST TO IRON S	03/05/20	710.00	600.00	533.33	580.00
		WEIGHTED AVERAGE FOR THE FIRST QUARTER		1,818.00	569.53	444.95	409.35
STR092A-030		SH92 MP 31.748-48.5, DELTA AND	04/02/20	982.27	500.00	427.50	410.00

COLORADO DEPARTMENT OF TRANSPORTATION
ITEM UNIT COSTS BY PROJECTS -- 2020 COST DATA

10:58 Friday, October 2, 2020 127

PROJECT NUMBER	ITEM NUMBER/ PROJECT LOCATION	ITEM DESCRIPTION/ PROJECT LOCATION	DATE LET	UNIT/ QUANTITY	ENGR. EST.	AVERAGE BID	AWARDED BID
===== 411-03352	Asph Cem (PG 58-28)			Ton =====			
STR0341-101	SH 34 North of Grandby Resurf	04/02/20		1,403.00	450.00	424.92	405.00
	WEIGHTED AVERAGE FOR THE SECOND QUARTER			2,385.27	470.59	425.59	407.06
	WEIGHTED AVERAGE FOR THE YEAR			4,203.27	513.38	432.64	408.05
===== 411-03354	Asph Cem (PG 64-22)			Ton =====			
HPP 0501-067	US 50 AND SH 92 DELTA INTERSE	03/26/20		41.00	550.00	554.55	645.00
	WEIGHTED AVERAGE FOR THE FIRST QUARTER			41.00	550.00	554.55	645.00
STA340A-021	SH340 MP 6-6.76 MESA COUNTY	04/02/20		244.00	325.00	472.83	475.00
	WEIGHTED AVERAGE FOR THE SECOND QUARTER			244.00	325.00	472.83	475.00
	WEIGHTED AVERAGE FOR THE YEAR			285.00	357.37	481.07	499.46
===== 411-03355	Asph Cem (PG 58-34)			Ton =====			
STR131A-038	SH 131 MP 51.95-55.73, ROUTE	01/16/20		312.00	700.00	512.50	625.00
C0641-106	SH 64 Meeker West Rural Resur	03/05/20		1,371.00	650.00	460.00	400.00
NHPP0091-044	SH 9 FRISCO MAIN ST TO IRON S	03/05/20		383.00	700.00	636.67	690.00
	WEIGHTED AVERAGE FOR THE FIRST QUARTER			2,066.00	666.82	512.21	487.74
STR092A-030	SH92 MP 31.748-48.5, DELTA AND	04/02/20		1,337.26	440.00	507.50	500.00
STR0341-101	SH 34 North of Grandby Resurf	04/02/20		1,937.00	550.00	508.32	485.00
	WEIGHTED AVERAGE FOR THE SECOND QUARTER			3,274.26	505.07	508.11	491.13
	WEIGHTED AVERAGE FOR THE YEAR			5,340.26	567.65	509.35	489.82
===== 411-10216	Emul Asph (CRS-2P)			Gallon =====			
NHPP0502-082	US 50 MONTROSE RE CHIP SEAL	03/05/20		432,075.00	2.25	2.63	2.05
	WEIGHTED AVERAGE FOR THE FIRST QUARTER			432,075.00	2.25	2.63	2.05

COLORADO DEPARTMENT OF TRANSPORTATION
ITEM UNIT COSTS BY PROJECTS -- 2020 COST DATA

10:58 Friday, October 2, 2020 128

PROJECT NUMBER	ITEM NUMBER/ PROJECT LOCATION	ITEM DESCRIPTION/ PROJECT LOCATION	DATE LET	UNIT/ QUANTITY	ENGR. EST.	AVERAGE BID	AWARDED BID
=====	411-10216	Emul Asph (CRS-2P)		Gallon	=====	=====	=====
NHPP1601-077		US 160 MP 29.750 - MP 34.891	04/09/20	86,053.00	2.50	3.29	3.75
NHPP0402-098		US 40 CHIP SEAL MP 126 TO MP	05/14/20	69,263.00	2.75	2.40	1.70
		WEIGHTED AVERAGE FOR THE SECOND QUARTER		155,316.00	2.61	2.89	2.84
		WEIGHTED AVERAGE FOR THE YEAR		587,391.00	2.35	2.68	2.26
=====	411-10253	Emul Asph (CSS-1H)		Gallon	=====	=====	=====
NHPP0502-082		US 50 MONTROSE RE CHIP SEAL	03/05/20	121,867.24	2.25	2.13	1.35
		WEIGHTED AVERAGE FOR THE FIRST QUARTER		121,867.24	2.25	2.13	1.35
NHPP0402-098		US 40 CHIP SEAL MP 126 TO MP	05/14/20	19,536.00	3.50	1.57	0.80
		WEIGHTED AVERAGE FOR THE SECOND QUARTER		19,536.00	3.50	1.57	0.80
		WEIGHTED AVERAGE FOR THE YEAR		141,403.24	2.42	2.07	1.27
=====	411-10255	Emul Asph (SS)		Gallon	=====	=====	=====
SHER500-210		R5 FY19 CENTER LINE RUMBLE ST	01/09/20	6,077.00	3.00	12.88	17.50
STR131A-038		SH 131 MP 51.95-55.73, ROUTT	01/16/20	3,112.00	2.75	2.75	3.00
NH 0503-093		US50 WEST OF TEXAS CREEK MP 2	01/23/20	24,679.00	3.00	1.95	3.40
STR141A-044		SH 141 AND SH 145, FROM SLICK	01/30/20	56,560.00	3.50	3.25	3.00
STA0703-443		I-70 EJMT TUNNELS PAVING	02/06/20	4,851.00	5.00	7.49	3.48
STA059A-036		SH 59 SEIBERT TO COPE	02/06/20	41,988.00	2.80	1.45	1.90
STR116A-001		SH 116 A Surface Treatment Pr	02/13/20	48,362.00	4.00	2.38	3.00
STA069A-033		SH69 MP 58.7 TO 71.58	02/13/20	21,601.00	3.00	3.50	4.00
STR0101-027		SH 10 Overlay La Junta West	02/27/20	35,946.00	4.00	2.07	3.00
NH0242-085		US 24 M.P. 291.38 to M.P. 296	02/27/20	11,694.00	3.50	4.76	4.70
NHPP0171-105		SH 17 MP 84.5 to US 285 & SH	03/05/20	34,770.00	4.00	3.42	2.50
C0641-106		SH 64 Meeker West Rural Resur	03/05/20	18,854.00	3.00	4.00	5.00
NHPP145A-080		SH 145 Keystone-Placerville R	03/05/20	10,016.00	24606.00	4.50	4.50
BR025A-046		K-18-U ON I-25 AT MP112 BRIDG	03/05/20	105.00	4.00	17.86	19.00
NHPP0091-044		SH 9 FRISCO MAIN ST TO IRON S	03/05/20	13,667.00	7.00	5.42	5.50
NH050A-034		US50A PUEBLO WEST PURCELL INT	03/26/20	19,408.00	3.50	8.08	3.00

PROJECT NUMBER	ITEM NUMBER/ PROJECT LOCATION	ITEM DESCRIPTION/ PROJECT LOCATION	DATE LET	UNIT/ QUANTITY	ENGR. EST.	AVERAGE BID	AWARDED BID
=====	411-10255	Emul Asph (SS)		Gallon	=====	=====	=====
HPP 0501-067		US 50 AND SH 92 DELTA INTERSE	03/26/20	100.00	6.00	8.30	4.50
SHE 0703-461		I-70 and Kipling North Phase	03/26/20	111.00	4.00	7.40	8.00
		WEIGHTED AVERAGE FOR THE FIRST QUARTER		351,901.00	703.89	3.84	3.48
NHPP1602-169		US 160 WC TUNNEL EAST RESURFA	04/02/20	23,741.00	3.00	3.08	2.17
STR092A-030		SH92 MP 31.748-48.5, DELTA AND	04/02/20	26,216.00	4.00	2.50	2.00
STA340A-021		SH340 MP 6-6.76 MESA COUNTY	04/02/20	1,892.00	4.10	3.62	3.00
STR0341-101		SH 34 North of Grandby Resurf	04/02/20	77,645.00	3.00	2.55	2.00
CC0852-106		US-85 LOUVIERS TO MP 191.75	04/23/20	1,105.00	4.50	3.24	3.30
FBR0852-108		US-85 BETWEEN LOUVIERS AND MP					
C1211-090		SH-121 & 29th Ave / SH-121 &	04/23/20	155.00	4.00	22.05	4.50
FSA1602-159		US 160 AND SH 17 INTERSECTION	04/30/20	391.00	7.00	5.00	5.00
C0853-112		US85 & WCR98 INTERSECTION IMP	05/07/20	2,247.00	5.00	3.57	3.50
		WEIGHTED AVERAGE FOR THE SECOND QUARTER		133,392.00	3.27	2.71	2.09
		WEIGHTED AVERAGE FOR THE YEAR		485,293.00	511.31	3.51	3.10
=====	411-90010	Asph Rejuvenating Agent		Gallon	=====	=====	=====
NHPP0171-105		SH 17 MP 84.5 to US 285 & SH	03/05/20	29,526.00	3.50	2.76	3.03
		WEIGHTED AVERAGE FOR THE FIRST QUARTER		29,526.00	3.50	2.76	3.03
		WEIGHTED AVERAGE FOR THE YEAR		29,526.00	3.50	2.76	3.03
=====	412-00190	Conc Pvmnt (Patching)		Sq Yard	=====	=====	=====
FSA0253-262		I-25 SB BOTTLENECK I-76 TO I-	01/09/20	100.00	200.00	300.33	300.00
NHPP 0852-116		US85-HAMPDEN TO FLORIDA-RESUR	02/06/20	6,227.00	135.00	345.50	250.00
FSA2873-194		US 287 Longmont Intersection	02/13/20	117.00	150.00	315.00	105.00
SHE 0703-461		I-70 and Kipling North Phase	03/26/20	5.00	300.00	583.60	842.00
		WEIGHTED AVERAGE FOR THE FIRST QUARTER		6,449.00	136.41	343.35	248.60
IM0761-226		I76/SH52 Interchange	04/02/20	174.00	250.00	263.27	130.48
NHPPR100-303		LONG MAST ARM SIGNALS PROJECT	05/07/20	19.00	310.00	282.00	225.00

COLORADO DEPARTMENT OF TRANSPORTATION
ITEM UNIT COSTS BY PROJECTS -- 2020 COST DATA

10:58 Friday, October 2, 2020 130

PROJECT NUMBER	ITEM NUMBER/ PROJECT LOCATION	ITEM DESCRIPTION/ PROJECT LOCATION	DATE LET	UNIT/ QUANTITY	ENGR. EST.	AVERAGE BID	AWARDED BID
===== 412-00190		Conc Pvmt (Patching)		Sq Yard			
FSAR400-356		FY 20 SIGNAL POLE REPLACEMENT	06/11/20	12.00	300.00	337.83	161.00
	WEIGHTED AVERAGE FOR THE SECOND QUARTER			205.00	258.49	266.13	141.03
	WEIGHTED AVERAGE FOR THE YEAR			6,654.00	140.17	336.50	245.29
===== 412-00600		Conc Pvmt (6 In)		Sq Yard			
BR0343-040		US 34 REPUBLICAN RIVER BRIDGE	01/16/20	56.00	77.00	131.19	260.00
FBR0343-043		US 34 D-28-P STRUCTURE REPLAC					
ITS0761-231		ITS FIBER AND CAMERAS ON I-76	02/06/20	150.00	100.00	162.13	115.00
STR2871-038		US 287 Passing Lanes Springfi	03/05/20	265.00	80.00	83.71	81.11
STRR300-249		Grand and Jackson Counties AD	03/05/20	329.00	150.00	135.00	98.00
SHE 0703-461		I-70 and Kipling North Phase	03/26/20	31.00	150.00	154.20	114.00
	WEIGHTED AVERAGE FOR THE FIRST QUARTER			831.00	113.73	133.14	107.20
IM0761-226		I76/SH52 Interchange	04/02/20	38.00	130.00	100.83	52.88
FSA1602-159		US 160 AND SH 17 INTERSECTION	04/30/20	88.00	120.00	184.33	99.00
	WEIGHTED AVERAGE FOR THE SECOND QUARTER			126.00	123.02	142.42	85.09
	WEIGHTED AVERAGE FOR THE YEAR			957.00	114.96	134.63	104.29
===== 412-00605		Conc Pvmt (6 In) (Fast Track)		Sq Yard			
CC080-037		VARIOUS ADA RAMPS ALONG NORTH	03/05/20	42.00	200.00	122.41	122.00
	WEIGHTED AVERAGE FOR THE FIRST QUARTER			42.00	200.00	122.41	122.00
	WEIGHTED AVERAGE FOR THE YEAR			42.00	200.00	122.41	122.00
===== 412-00800		Conc Pvmt (8 In)		Sq Yard			
FSA0341-097		US 34 & MACGREGOR INTERSECTIO	01/09/20	1,385.00	100.00	80.00	80.00
NHPP0343-041		I-76 & US 34 FT. MORGAN AREA	01/09/20	309.00	130.00	134.33	147.00
	WEIGHTED AVERAGE FOR THE FIRST QUARTER			1,694.00	105.47	101.79	92.22
	WEIGHTED AVERAGE FOR THE YEAR			1,694.00	105.47	101.79	92.22

COLORADO DEPARTMENT OF TRANSPORTATION
 ITEM UNIT COSTS BY PROJECTS -- 2020 COST DATA

10:58 Friday, October 2, 2020 131

PROJECT NUMBER	ITEM NUMBER/ PROJECT LOCATION	ITEM DESCRIPTION/ PROJECT LOCATION	DATE LET	UNIT/ QUANTITY	ENGR. EST.	AVERAGE BID	AWARDED BID
=====	412-00801	Conc Pvmt (8 In) (Spec)		Sq Yard	=====		
FSA0341-097		US 34 & MACGREGOR INTERSECTIO	01/09/20	456.00	160.00	110.00	110.00
		WEIGHTED AVERAGE FOR THE FIRST QUARTER		456.00	160.00	110.00	110.00
IM0761-226		I76/SH52 Interchange	04/02/20	2,232.00	105.00	109.54	110.64
		WEIGHTED AVERAGE FOR THE SECOND QUARTER		2,232.00	105.00	109.54	110.64
		WEIGHTED AVERAGE FOR THE YEAR		2,688.00	114.33	109.55	110.53
=====	412-00805	Conc Pvmt (8 In) (Fast Track)		Sq Yard	=====		
C1601-082		Hawkins Signal and Curb Ramps	04/30/20	316.00	150.00	197.67	168.00
		WEIGHTED AVERAGE FOR THE SECOND QUARTER		316.00	150.00	197.67	168.00
		WEIGHTED AVERAGE FOR THE YEAR		316.00	150.00	197.67	168.00
=====	412-00815	Conc Pvmt (8 In) (R)		Sq Yard	=====		
NHPP0091-044		SH 9 FRISCO MAIN ST TO IRON S	03/05/20	1,074.00	200.00	125.00	120.00
		WEIGHTED AVERAGE FOR THE FIRST QUARTER		1,074.00	200.00	125.00	120.00
		WEIGHTED AVERAGE FOR THE YEAR		1,074.00	200.00	125.00	120.00
=====	412-00850	Conc Pvmt (8-1/2 In)		Sq Yard	=====		
FSA2873-194		US 287 Longmont Intersection	02/13/20	1,979.00	88.00	135.83	91.00
		WEIGHTED AVERAGE FOR THE FIRST QUARTER		1,979.00	88.00	135.83	91.00
		WEIGHTED AVERAGE FOR THE YEAR		1,979.00	88.00	135.83	91.00
=====	412-00870	Conc Pvmt (8-1/2 In) (Fast Track)		Sq Yard	=====		
FSA2873-194		US 287 Longmont Intersection	02/13/20	89.00	125.00	298.17	104.00
		WEIGHTED AVERAGE FOR THE FIRST QUARTER		89.00	125.00	298.17	104.00
		WEIGHTED AVERAGE FOR THE YEAR		89.00	125.00	298.17	104.00

COLORADO DEPARTMENT OF TRANSPORTATION
ITEM UNIT COSTS BY PROJECTS -- 2020 COST DATA

10:58 Friday, October 2, 2020 132

PROJECT NUMBER	ITEM NUMBER/ PROJECT LOCATION	ITEM DESCRIPTION/ PROJECT LOCATION	DATE LET	UNIT/ QUANTITY	ENGR. EST.	AVERAGE BID	AWARDED BID
=====	412-00900	Conc Pvmt (9 In)		Sq Yard	=====		
NHPP0343-041		I-76 & US 34 FT. MORGAN AREA	01/09/20	8,664.00	82.00	84.43	95.00
HPP 0501-067		US 50 AND SH 92 DELTA INTERSE	03/26/20	692.00	90.00	142.85	147.40
		WEIGHTED AVERAGE FOR THE FIRST QUARTER		9,356.00	82.59	87.39	98.88
IM0761-226		I76/SH52 Interchange	04/02/20	36,648.00	72.00	74.38	60.25
CC0852-106		US-85 LOUVIERS TO MP 191.75	04/23/20	118,410.00	35.00	57.04	40.46
FBR0852-108		US-85 BETWEEN LOUVIERS AND MP					
		WEIGHTED AVERAGE FOR THE SECOND QUARTER		155,058.00	43.74	60.74	45.14
		WEIGHTED AVERAGE FOR THE YEAR		164,414.00	45.96	61.33	48.20
=====	412-00920	Conc Pvmt (9 In) (Fast Track)		Sq Yard	=====		
HPP 0501-067		US 50 AND SH 92 DELTA INTERSE	03/26/20	1,796.00	120.00	145.70	150.05
		WEIGHTED AVERAGE FOR THE FIRST QUARTER		1,796.00	120.00	145.70	150.05
		WEIGHTED AVERAGE FOR THE YEAR		1,796.00	120.00	145.70	150.05
=====	412-01000	Conc Pvmt (10 In)		Sq Yard	=====		
C0402-094		US 40 GRAND COUNTY SIGNAL REP	02/27/20	27.00	200.00	161.50	158.00
		WEIGHTED AVERAGE FOR THE FIRST QUARTER		27.00	200.00	161.50	158.00
FSA1602-159		US 160 AND SH 17 INTERSECTION	04/30/20	7,555.00	125.00	130.67	132.00
NHPP0402-098		US 40 CHIP SEAL MP 126 TO MP	05/14/20	130.00	175.00	166.67	180.00
		WEIGHTED AVERAGE FOR THE SECOND QUARTER		7,685.00	125.85	131.28	132.81
		WEIGHTED AVERAGE FOR THE YEAR		7,712.00	126.11	131.35	132.90
=====	412-01001	Conc Pvmt (10 In) (Spec)		Sq Yard	=====		
FSA1602-159		US 160 AND SH 17 INTERSECTION	04/30/20	123.00	160.00	177.67	178.00
		WEIGHTED AVERAGE FOR THE SECOND QUARTER		123.00	160.00	177.67	178.00
		WEIGHTED AVERAGE FOR THE YEAR		123.00	160.00	177.67	178.00

COLORADO DEPARTMENT OF TRANSPORTATION
 ITEM UNIT COSTS BY PROJECTS -- 2020 COST DATA

10:58 Friday, October 2, 2020 133

PROJECT NUMBER	ITEM NUMBER/ PROJECT LOCATION	ITEM DESCRIPTION/ PROJECT LOCATION	DATE LET	UNIT/ QUANTITY	ENGR. EST.	AVERAGE BID	AWARDED BID
=====	412-01020	Conc Pvmt (10 In) (Fast Track)		Sq Yard	=====		
C1601-082		Hawkins Signal and Curb Ramps	04/30/20	81.00	160.00	241.67	200.00
	WEIGHTED AVERAGE FOR THE SECOND QUARTER			81.00	160.00	241.67	200.00
	WEIGHTED AVERAGE FOR THE YEAR			81.00	160.00	241.67	200.00
=====	412-01050	Conc Pvmt (10-1/2 In)		Sq Yard	=====		
SHE 0703-461		I-70 and Kipling North Phase	03/26/20	661.00	175.00	170.20	151.00
	WEIGHTED AVERAGE FOR THE FIRST QUARTER			661.00	175.00	170.20	151.00
	WEIGHTED AVERAGE FOR THE YEAR			661.00	175.00	170.20	151.00
=====	412-01100	Conc Pvmt (11 In)		Sq Yard	=====		
STR2871-038		US 287 Passing Lanes Springfi	03/05/20	31,992.00	65.00	63.65	61.37
	WEIGHTED AVERAGE FOR THE FIRST QUARTER			31,992.00	65.00	63.65	61.37
	WEIGHTED AVERAGE FOR THE YEAR			31,992.00	65.00	63.65	61.37
=====	412-01120	Conc Pvmt (11 In) (Fast Track)		Sq Yard	=====		
SHE 0703-461		I-70 and Kipling North Phase	03/26/20	168.00	200.00	249.80	142.00
	WEIGHTED AVERAGE FOR THE FIRST QUARTER			168.00	200.00	249.80	142.00
	WEIGHTED AVERAGE FOR THE YEAR			168.00	200.00	249.80	142.00
=====	412-01200	Conc Pvmt (12 In)		Sq Yard	=====		
FSA0253-262		I-25 SB BOTTLENECK I-76 TO I-	01/09/20	1,694.00	62.00	118.28	130.00
	WEIGHTED AVERAGE FOR THE FIRST QUARTER			1,694.00	62.00	118.28	130.00
IM0761-226		I76/SH52 Interchange	04/02/20	2,465.00	110.00	93.33	66.51
	WEIGHTED AVERAGE FOR THE SECOND QUARTER			2,465.00	110.00	93.33	66.51
	WEIGHTED AVERAGE FOR THE YEAR			4,159.00	90.45	99.00	92.37

COLORADO DEPARTMENT OF TRANSPORTATION
ITEM UNIT COSTS BY PROJECTS -- 2020 COST DATA

10:58 Friday, October 2, 2020 134

PROJECT NUMBER	ITEM NUMBER/ PROJECT LOCATION	ITEM DESCRIPTION/ PROJECT LOCATION	DATE LET	UNIT/ QUANTITY	ENGR. EST.	AVERAGE BID	AWARDED BID
=====	412-01250	Conc Pvmt (12-1/2 In)		Sq Yard	=====		
SFTY2254-091		225 Ramp Improvements	04/09/20	5,987.00	120.00	146.00	112.00
	WEIGHTED AVERAGE FOR THE SECOND QUARTER			5,987.00	120.00	146.00	112.00
	WEIGHTED AVERAGE FOR THE YEAR			5,987.00	120.00	146.00	112.00
=====	412-02000	Conc Safety Edge		Lin Foot	=====		
STR2871-038		US 287 Passing Lanes Springfi	03/05/20	13,315.00	4.00	3.11	3.52
	WEIGHTED AVERAGE FOR THE FIRST QUARTER			13,315.00	4.00	3.11	3.52
CC0852-106 FBR0852-108		US-85 LOUVIERS TO MP 191.75 US-85 BETWEEN LOUVIERS AND MP	04/23/20	23,634.00	5.00	3.18	2.72
	WEIGHTED AVERAGE FOR THE SECOND QUARTER			23,634.00	5.00	3.18	2.72
	WEIGHTED AVERAGE FOR THE YEAR			36,949.00	4.64	3.17	3.01
=====	412-11000	Conc Pave Dowel Bar Retro		Each	=====		
FSA0253-262 NHPP 0852-116		I-25 SB BOTTLENECK I-76 TO I- US85:HAMPDEN TO FLORIDA-RESUR	01/09/20 02/06/20	1,032.00 3,138.00	110.00 120.00	90.68 135.00	130.00 150.00
	WEIGHTED AVERAGE FOR THE FIRST QUARTER			4,170.00	117.53	120.36	145.05
	WEIGHTED AVERAGE FOR THE YEAR			4,170.00	117.53	120.36	145.05
=====	412-15000	Routing and Sealing Cracks		Lin Foot	=====		
NHPP 0852-116		US85:HAMPDEN TO FLORIDA-RESUR	02/06/20	1,099.00	45.00	16.00	25.00
	WEIGHTED AVERAGE FOR THE FIRST QUARTER			1,099.00	45.00	16.00	25.00
	WEIGHTED AVERAGE FOR THE YEAR			1,099.00	45.00	16.00	25.00
=====	412-16000	Cleaning + Sealing Joints		Lin Foot	=====		
NHPP 0852-116		US85:HAMPDEN TO FLORIDA-RESUR	02/06/20	117,066.00	3.50	2.08	3.00
	WEIGHTED AVERAGE FOR THE FIRST QUARTER			117,066.00	3.50	2.08	3.00
	WEIGHTED AVERAGE FOR THE YEAR			117,066.00	3.50	2.08	3.00

COLORADO DEPARTMENT OF TRANSPORTATION
ITEM UNIT COSTS BY PROJECTS -- 2020 COST DATA

10:58 Friday, October 2, 2020 135

PROJECT NUMBER	ITEM NUMBER/ PROJECT LOCATION	ITEM DESCRIPTION/ PROJECT LOCATION	DATE LET	UNIT/ QUANTITY	ENGR. EST.	AVERAGE BID	AWARDED BID
=====	420-00000	Geomembrane		Sq Yard	=====		
NHPP0091-044		SH 9 FRISCO MAIN ST TO IRON S	03/05/20	840.00	30.00	27.23	13.00
NH050A-034		US50A PUEBLO WEST PURCELL INT	03/26/20	2,483.00	40.00	12.82	13.40
		WEIGHTED AVERAGE FOR THE FIRST QUARTER		3,323.00	37.47	14.44	13.30
IM0761-226		I76/SH52 Interchange	04/02/20	225.00	15.00	19.56	5.30
		WEIGHTED AVERAGE FOR THE SECOND QUARTER		225.00	15.00	19.56	5.30
		WEIGHTED AVERAGE FOR THE YEAR		3,548.00	36.05	14.78	12.79
=====	420-00102	Geotextile (Er Cont) (CL 1)		Sq Yard	=====		
STA059A-036		SH 59 SEIBERT TO COPE	02/06/20	1,692.00	4.00	2.50	2.00
BR025A-046		K-18-U ON I-25 AT MP112 BRIDG	03/05/20	350.00	8.00	5.40	2.77
		WEIGHTED AVERAGE FOR THE FIRST QUARTER		2,042.00	4.69	3.72	2.13
CC0852-106		US-85 LOUVIERS TO MP 191.75	04/23/20	4,630.00	6.00	4.54	5.68
FBR0852-108		US-85 BETWEEN LOUVIERS AND MP					
NHPP0253-276		I-25 EXPRESS LANES SEGMENT 5	05/15/20	850.00	2.00	4.32	4.32
		WEIGHTED AVERAGE FOR THE SECOND QUARTER		5,480.00	5.38	4.54	5.47
		WEIGHTED AVERAGE FOR THE YEAR		7,522.00	5.19	4.43	4.56
=====	420-00103	Geotextile (Er Cont) (CL 2)		Sq Yard	=====		
NHPP0343-041		I-76 & US 34 FT. MORGAN AREA	01/09/20	378.00	6.00	7.17	5.28
		WEIGHTED AVERAGE FOR THE FIRST QUARTER		378.00	6.00	7.17	5.28
STA340A-021		SH340 MP 6-6.76 MESA COUNTY	04/02/20	19.00	15.00	21.33	25.00
		WEIGHTED AVERAGE FOR THE SECOND QUARTER		19.00	15.00	21.33	25.00
		WEIGHTED AVERAGE FOR THE YEAR		397.00	6.43	7.85	6.22

COLORADO DEPARTMENT OF TRANSPORTATION
 ITEM UNIT COSTS BY PROJECTS -- 2020 COST DATA

10:58 Friday, October 2, 2020 136

PROJECT NUMBER	ITEM NUMBER/ PROJECT LOCATION	ITEM DESCRIPTION/ PROJECT LOCATION	DATE LET	UNIT/ QUANTITY	ENGR. EST.	AVERAGE BID	AWARDED BID
===== 420-00112		Geotextile (Drain) (CL 1)		Sq Yard	=====		
NHPP0343-041		I-76 & US 34 FT. MORGAN AREA	01/09/20	57.00	6.00	14.15	11.00
BR0343-040		US 34 REPUBLICAN RIVER BRIDGE	01/16/20	1,969.00	5.50	4.38	4.00
FBR0343-043		US 34 D-28-P STRUCTURE REPLAC					
NHPP145A-080		SH 145 Keystone-Placerville R	03/05/20	233.00	4.00	5.25	5.25
NH050A-034		US50A PUEBLO WEST PURCELL INT	03/26/20	181.00	8.00	8.19	5.00
		WEIGHTED AVERAGE FOR THE FIRST QUARTER		2,440.00	5.55	4.92	4.36
IM0761-226		I76/SH52 Interchange	04/02/20	679.00	4.00	7.12	1.52
FBR0343-042		US 34 D-27-G STRUCTURE REPLAC	05/07/20	850.00	6.00	3.35	2.65
		WEIGHTED AVERAGE FOR THE SECOND QUARTER		1,529.00	5.11	4.79	2.15
		WEIGHTED AVERAGE FOR THE YEAR		3,969.00	5.38	4.86	3.51
===== 420-00113		Geotextile (Drain) (CL 2)		Sq Yard	=====		
NH050A-034		US50A PUEBLO WEST PURCELL INT	03/26/20	927.00	8.00	4.86	6.00
HPP 0501-067		US 50 AND SH 92 DELTA INTERSE	03/26/20	48.00	6.00	49.28	5.35
		WEIGHTED AVERAGE FOR THE FIRST QUARTER		975.00	7.90	5.43	5.97
FSA1602-159		US 160 AND SH 17 INTERSECTION	04/30/20	4.00	70.00	98.33	45.00
		WEIGHTED AVERAGE FOR THE SECOND QUARTER		4.00	70.00	98.33	45.00
		WEIGHTED AVERAGE FOR THE YEAR		979.00	8.16	5.57	6.13
===== 420-00114		Geotextile (Drain) (CL 3)		Sq Yard	=====		
FSA0341-097		US 34 & MACGREGOR INTERSECTIO	01/09/20	1,036.00	8.00	7.00	7.00
		WEIGHTED AVERAGE FOR THE FIRST QUARTER		1,036.00	8.00	7.00	7.00
		WEIGHTED AVERAGE FOR THE YEAR		1,036.00	8.00	7.00	7.00
===== 420-00132		Geotextile (Separator) (CL 1)		Sq Yard	=====		
NH050A-034		US50A PUEBLO WEST PURCELL INT	03/26/20	84,446.00	2.00	2.94	2.30
		WEIGHTED AVERAGE FOR THE FIRST QUARTER		84,446.00	2.00	2.94	2.30

COLORADO DEPARTMENT OF TRANSPORTATION
 ITEM UNIT COSTS BY PROJECTS -- 2020 COST DATA

10:58 Friday, October 2, 2020 137

PROJECT NUMBER	ITEM NUMBER/ PROJECT LOCATION	ITEM DESCRIPTION/ PROJECT LOCATION	DATE LET	UNIT/ QUANTITY	ENGR. EST.	AVERAGE BID	AWARDED BID
=====	420-00132	Geotextile (Separator) (CL 1)		Sq Yard	=====		
FSA1602-159		US 160 AND SH 17 INTERSECTION	04/30/20	10,332.00	5.00	5.17	5.00
		WEIGHTED AVERAGE FOR THE SECOND QUARTER		10,332.00	5.00	5.17	5.00
		WEIGHTED AVERAGE FOR THE YEAR		94,778.00	2.33	3.03	2.59
=====	420-00300	Geotextile (Reinforcement)		Sq Yard	=====		
C0853-112		US85 & WCR98 INTERSECTION IMP	05/07/20	2,298.00	6.00	7.07	5.25
		WEIGHTED AVERAGE FOR THE SECOND QUARTER		2,298.00	6.00	7.07	5.25
		WEIGHTED AVERAGE FOR THE YEAR		2,298.00	6.00	7.07	5.25
=====	420-00520	Geogrid Pvmt Reinf		Sq Yard	=====		
NHPP0343-041		I-76 & US 34 FT. MORGAN AREA	01/09/20	4,257.00	13.00	3.88	4.00
		WEIGHTED AVERAGE FOR THE FIRST QUARTER		4,257.00	13.00	3.88	4.00
		WEIGHTED AVERAGE FOR THE YEAR		4,257.00	13.00	3.88	4.00
=====	502-00100	Drill Hole Fac Pile Driving		Lin Foot	=====		
NH050A-034		US50A PUEBLO WEST PURCELL INT	03/26/20	640.00	50.00	42.36	47.60
		WEIGHTED AVERAGE FOR THE FIRST QUARTER		640.00	50.00	42.36	47.60
		WEIGHTED AVERAGE FOR THE YEAR		640.00	50.00	42.36	47.60
=====	502-00460	Pile Tip		Each	=====		
BR0343-040		US 34 REPUBLICAN RIVER BRIDGE	01/16/20	28.00	175.00	220.83	250.00
FBR0343-043		US 34 D-28-P STRUCTURE REPLAC					
NH050A-034		US50A PUEBLO WEST PURCELL INT	03/26/20	32.00	180.00	189.33	133.00
		WEIGHTED AVERAGE FOR THE FIRST QUARTER		60.00	177.67	201.81	187.60

PROJECT NUMBER	ITEM NUMBER/ PROJECT LOCATION	ITEM DESCRIPTION/ PROJECT LOCATION	DATE LET	UNIT/ QUANTITY	ENGR. EST.	AVERAGE BID	AWARDED BID
=====	502-00460	File Tip		Each	=====		
CC0852-106		US-85 LOUVIERS TO MP 191.75	04/23/20	14.00	200.00	216.67	357.50
FBR0852-108		US-85 BETWEEN LOUVIERS AND MP					
FBR0343-042		US 34 D-27-G STRUCTURE REPLAC	05/07/20	16.00	200.00	292.66	250.00
NHPP0253-276		I-25 EXPRESS LANES SEGMENT 5	05/15/20	52.00	161.00	186.74	186.74
		WEIGHTED AVERAGE FOR THE SECOND QUARTER		82.00	175.27	247.14	228.24
		WEIGHTED AVERAGE FOR THE YEAR		142.00	176.28	220.89	211.07
=====	502-00500	CJP Splice		Each	=====		
BR0343-040		US 34 REPUBLICAN RIVER BRIDGE	01/16/20	28.00	600.00	584.47	1.00
FBR0343-043		US 34 D-28-P STRUCTURE REPLAC					
NH050A-034		US50A PUEBLO WEST PURCELL INT	03/26/20	32.00	300.00	887.77	1.10
		WEIGHTED AVERAGE FOR THE FIRST QUARTER		60.00	440.00	767.59	1.05
CC0852-106		US-85 LOUVIERS TO MP 191.75	04/23/20	14.00	1000.00	771.24	467.50
FBR0852-108		US-85 BETWEEN LOUVIERS AND MP					
FBR0343-042		US 34 D-27-G STRUCTURE REPLAC	05/07/20	16.00	600.00	659.18	1.00
NHPP0253-276		I-25 EXPRESS LANES SEGMENT 5	05/15/20	2.00	700.00	1321.47	1321.47
		WEIGHTED AVERAGE FOR THE SECOND QUARTER		32.00	781.25	712.96	287.62
		WEIGHTED AVERAGE FOR THE YEAR		92.00	558.70	746.93	100.73
=====	502-02010	Dynamic File Test		Each	=====		
NH050A-034		US50A PUEBLO WEST PURCELL INT	03/26/20	2.00	3504.00	3798.49	3700.00
		WEIGHTED AVERAGE FOR THE FIRST QUARTER		2.00	3504.00	3798.49	3700.00
NHPP0253-276		I-25 EXPRESS LANES SEGMENT 5	05/15/20	4.00	2700.00	2675.00	2675.00
		WEIGHTED AVERAGE FOR THE SECOND QUARTER		4.00	2700.00	2675.00	2675.00
		WEIGHTED AVERAGE FOR THE YEAR		6.00	2968.00	3573.79	3016.67

COLORADO DEPARTMENT OF TRANSPORTATION
 ITEM UNIT COSTS BY PROJECTS -- 2020 COST DATA

10:58 Friday, October 2, 2020 139

PROJECT NUMBER	ITEM NUMBER/ PROJECT LOCATION	ITEM DESCRIPTION/ PROJECT LOCATION	DATE LET	UNIT/ QUANTITY	ENGR. EST.	AVERAGE BID	AWARDED BID
=====	502-11253	Steel Pile (HP 12x53)		Lin Foot	=====		
IM0761-226		I76/SH52 Interchange	04/02/20	732.00	95.00	86.42	130.00
	WEIGHTED	AVERAGE FOR THE SECOND QUARTER		732.00	95.00	86.42	130.00
		WEIGHTED AVERAGE FOR THE YEAR		732.00	95.00	86.42	130.00
=====	502-11274	Steel Pile (HP 12x74)		Lin Foot	=====		
BR0343-040		US 34 REPUBLICAN RIVER BRIDGE	01/16/20	1,407.00	90.00	83.08	90.00
FBR0343-043		US 34 D-28-P STRUCTURE REPLAC					
NH050A-034		US50A PUEBLO WEST PURCELL INT	03/26/20	1,168.00	80.00	88.74	79.25
	WEIGHTED	AVERAGE FOR THE FIRST QUARTER		2,575.00	85.46	86.05	85.12
FBR0343-042		US 34 D-27-G STRUCTURE REPLAC	05/07/20	584.00	95.00	91.16	95.00
	WEIGHTED	AVERAGE FOR THE SECOND QUARTER		584.00	95.00	91.16	95.00
		WEIGHTED AVERAGE FOR THE YEAR		3,159.00	87.23	87.22	86.95
=====	502-11284	Steel Pile (HP 12x84)		Lin Foot	=====		
CC0852-106		US-85 LOUVIERS TO MP 191.75	04/23/20	530.00	85.00	125.91	137.50
FBR0852-108		US-85 BETWEEN LOUVIERS AND MP					
	WEIGHTED	AVERAGE FOR THE SECOND QUARTER		530.00	85.00	125.91	137.50
		WEIGHTED AVERAGE FOR THE YEAR		530.00	85.00	125.91	137.50
=====	502-11473	Steel Pile (HP 14x73)		Lin Foot	=====		
IM0761-226		I76/SH52 Interchange	04/02/20	97.00	110.00	144.64	185.00
	WEIGHTED	AVERAGE FOR THE SECOND QUARTER		97.00	110.00	144.64	185.00
		WEIGHTED AVERAGE FOR THE YEAR		97.00	110.00	144.64	185.00
=====	502-11489	Steel Pile (HP 14x89)		Lin Foot	=====		
NHPP0253-276		I-25 EXPRESS LANES SEGMENT 5	05/15/20	1,284.00	102.00	103.38	103.38
	WEIGHTED	AVERAGE FOR THE SECOND QUARTER		1,284.00	102.00	103.38	103.38
		WEIGHTED AVERAGE FOR THE YEAR		1,284.00	102.00	103.38	103.38

COLORADO DEPARTMENT OF TRANSPORTATION
ITEM UNIT COSTS BY PROJECTS -- 2020 COST DATA

10:58 Friday, October 2, 2020 140

PROJECT NUMBER	ITEM NUMBER/ PROJECT LOCATION	ITEM DESCRIPTION/ PROJECT LOCATION	DATE LET	UNIT/ QUANTITY	ENGR. EST.	AVERAGE BID	AWARDED BID
=====	503-00012	Drilled Shaft (12 In)		Lin Foot	=====		
NHPPR100-303		LONG MAST ARM SIGNALS PROJECT	05/07/20	40.00	150.00	186.33	113.00
		WEIGHTED AVERAGE FOR THE SECOND QUARTER		40.00	150.00	186.33	113.00
		WEIGHTED AVERAGE FOR THE YEAR		40.00	150.00	186.33	113.00
=====	503-00018	Drilled Shaft (18 In)		Lin Foot	=====		
FSA0253-262		I-25 SB BOTTLENECK I-76 TO I-	01/09/20	16.00	240.00	399.13	365.00
NHPP0253-265		I-25 AT ERIE PARKWAY ON AND O	01/09/20	25.00	225.00	255.67	275.00
FSA0341-097		US 34 & MACGREGOR INTERSECTIO	01/09/20	18.00	200.00	250.00	250.00
NHPP0091-044		SH 9 FRISCO MAIN ST TO IRON S	03/05/20	1,640.00	200.00	220.67	155.00
NH050A-034		US50A PUEBLO WEST PURCELL INT	03/26/20	35.00	220.00	620.61	579.00
HPP 0501-067		US 50 AND SH 92 DELTA INTERSE	03/26/20	10.00	250.00	333.00	336.00
SHE 0703-461		I-70 and Kipling North Phase	03/26/20	20.00	275.00	208.20	193.00
		WEIGHTED AVERAGE FOR THE FIRST QUARTER		1,764.00	202.25	243.50	169.44
FSA1602-159		US 160 AND SH 17 INTERSECTION	04/30/20	5.00	200.00	499.00	445.00
FSAR400-356		FY 20 SIGNAL POLE REPLACEMENT	06/11/20	20.00	275.00	269.33	133.00
		WEIGHTED AVERAGE FOR THE SECOND QUARTER		25.00	260.00	315.27	195.40
		WEIGHTED AVERAGE FOR THE YEAR		1,789.00	203.05	244.47	169.81
=====	503-00024	Drilled Shaft (24 In)		Lin Foot	=====		
IM0761-226		I76/SH52 Interchange	04/02/20	12.00	300.00	310.78	349.80
SHE016A-043		SH 21 & 16 SIGNALS PROJECT	06/18/20	60.00	300.00	328.30	275.50
		WEIGHTED AVERAGE FOR THE SECOND QUARTER		72.00	300.00	324.47	287.88
		WEIGHTED AVERAGE FOR THE YEAR		72.00	300.00	324.47	287.88
=====	503-00036	Drilled Shaft (36 In)		Lin Foot	=====		
FSA0253-262		I-25 SB BOTTLENECK I-76 TO I-	01/09/20	19.00	550.00	573.10	510.00

PROJECT NUMBER	ITEM NUMBER/ PROJECT LOCATION	ITEM DESCRIPTION/ PROJECT LOCATION	DATE LET	UNIT/ QUANTITY	ENGR. EST.	AVERAGE BID	AWARDED BID
=====	503-00036	Drilled Shaft (36 In)		Lin Foot	=====	=====	=====
NHPP0253-265		I-25 AT ERIE PARKWAY ON AND O	01/09/20	30.00	415.00	402.67	445.00
ITS0761-231		ITS FIBER AND CAMERAS ON I-76	02/06/20	68.00	500.00	483.74	625.00
NHPP4701-134		C-470 NOISE WALL WEST OF LUCE	02/06/20	1,458.00	400.00	205.00	125.00
C0402-094		US 40 GRAND COUNTY SIGNAL REP	02/27/20	114.00	600.00	930.00	360.00
NHPP0091-044		SH 9 FRISCO MAIN ST TO IRON S	03/05/20	95.00	550.00	575.67	390.00
NH050A-034		US50A PUEBLO WEST PURCELL INT	03/26/20	53.00	800.00	650.18	715.00
HPP 0501-067		US 50 AND SH 92 DELTA INTERSE	03/26/20	57.00	500.00	909.50	952.00
SHE 0703-461		I-70 and Kipling North Phase	03/26/20	152.00	550.00	388.80	360.00
		WEIGHTED AVERAGE FOR THE FIRST QUARTER		2,046.00	447.34	289.82	231.07
IM0761-226		I76/SH52 Interchange	04/02/20	57.00	400.00	372.85	367.82
CC0852-106		US-85 LOUVIERS TO MP 191.75	04/23/20	57.00	600.00	411.43	401.50
FBR0852-108		US-85 BETWEEN LOUVIERS AND MP					
C1211-090		SH-121 & 29th Ave / SH-121 &	04/23/20	152.00	360.00	426.87	300.00
C1601-082		Hawkins Signal and Curb Ramps	04/30/20	76.00	800.00	1115.33	507.00
NHPPR100-303		LONG MAST ARM SIGNALS PROJECT	05/07/20	95.00	350.00	397.33	342.00
FSAR400-356		FY 20 SIGNAL POLE REPLACEMENT	06/11/20	75.00	400.00	561.67	385.00
		WEIGHTED AVERAGE FOR THE SECOND QUARTER		512.00	460.49	500.22	369.82
		WEIGHTED AVERAGE FOR THE YEAR		2,558.00	449.97	326.86	258.84
=====	503-00042	Drilled Shaft (42 In)		Lin Foot	=====	=====	=====
ITSSW01-719		FY 20 ITS CAPITAL REPLACEMENT	06/11/20	136.00	1200.00	813.50	750.00
FSAR400-356		FY 20 SIGNAL POLE REPLACEMENT	06/11/20	17.00	550.00	654.00	467.00
		WEIGHTED AVERAGE FOR THE SECOND QUARTER		153.00	1127.78	788.32	718.56
		WEIGHTED AVERAGE FOR THE YEAR		153.00	1127.78	788.32	718.56
=====	503-00048	Drilled Shaft (48 In)		Lin Foot	=====	=====	=====
NHPP0253-265		I-25 AT ERIE PARKWAY ON AND O	01/09/20	42.00	575.00	506.67	495.00
C0402-094		US 40 GRAND COUNTY SIGNAL REP	02/27/20	42.00	700.00	1295.00	590.00
NHPP0091-044		SH 9 FRISCO MAIN ST TO IRON S	03/05/20	21.00	650.00	1013.33	1400.00
NH050A-034		US50A PUEBLO WEST PURCELL INT	03/26/20	36.00	900.00	886.34	901.00
		WEIGHTED AVERAGE FOR THE FIRST QUARTER		141.00	706.38	876.52	761.74
CC0852-106		US-85 LOUVIERS TO MP 191.75	04/23/20	154.00	850.00	587.95	535.07

PROJECT NUMBER	ITEM NUMBER/ PROJECT LOCATION	ITEM DESCRIPTION/ PROJECT LOCATION	DATE LET	UNIT/ QUANTITY	ENGR. EST.	AVERAGE BID	AWARDED BID
===== 503-00048		Drilled Shaft (48 In)		Lin Foot	=====		
FBR0852-108		US-85 BETWEEN LOUVIERS AND MP					
C1211-090		SH-121 & 29th Ave / SH-121 &	04/23/20	21.00	580.00	618.90	555.00
NHPPR100-303		LONG MAST ARM SIGNALS PROJECT	05/07/20	105.00	525.00	557.67	562.00
ITSSW01-719		FY 20 ITS CAPITAL REPLACEMENT	06/11/20	31.00	1500.00	1006.00	995.00
FSAR400-356		FY 20 SIGNAL POLE REPLACEMENT	06/11/20	21.00	575.00	701.67	510.00
SHE016A-043		SH 21 & 16 SIGNALS PROJECT	06/18/20	126.00	650.00	641.65	310.23
	WEIGHTED AVERAGE FOR THE SECOND QUARTER			458.00	739.48	613.04	510.28
	WEIGHTED AVERAGE FOR THE YEAR			599.00	731.69	663.55	569.48
===== 503-00054		Drilled Shaft (54 In)		Lin Foot	=====		
BR0343-040		US 34 REPUBLICAN RIVER BRIDGE	01/16/20	219.00	600.00	629.43	750.00
FBR0343-043		US 34 D-28-P STRUCTURE REPLAC					
NH050A-034		US50A PUEBLO WEST PURCELL INT	03/26/20	21.00	1000.00	865.68	941.00
	WEIGHTED AVERAGE FOR THE FIRST QUARTER			240.00	635.00	656.21	766.71
SFTY2254-091		225 Ramp Improvements	04/09/20	57.00	60.00	682.50	670.00
C1211-090		SH-121 & 29th Ave / SH-121 &	04/23/20	91.00	700.00	937.97	895.00
NHPPR100-303		LONG MAST ARM SIGNALS PROJECT	05/07/20	112.00	550.00	753.33	850.00
SHE016A-043		SH 21 & 16 SIGNALS PROJECT	06/18/20	126.00	700.00	732.97	396.85
	WEIGHTED AVERAGE FOR THE SECOND QUARTER			386.00	561.97	775.14	686.11
	WEIGHTED AVERAGE FOR THE YEAR			626.00	589.97	712.97	717.01
===== 503-00060		Drilled Shaft (60 In)		Lin Foot	=====		
NH050A-034		US50A PUEBLO WEST PURCELL INT	03/26/20	528.00	1200.00	889.68	900.00
	WEIGHTED AVERAGE FOR THE FIRST QUARTER			528.00	1200.00	889.68	900.00
	WEIGHTED AVERAGE FOR THE YEAR			528.00	1200.00	889.68	900.00
===== 503-00200		Caisson (Special)		Lin Foot	=====		
FSA1602-159		US 160 AND SH 17 INTERSECTION	04/30/20	120.00	520.00	1641.00	1400.00
	WEIGHTED AVERAGE FOR THE SECOND QUARTER			120.00	520.00	1641.00	1400.00
	WEIGHTED AVERAGE FOR THE YEAR			120.00	520.00	1641.00	1400.00

PROJECT NUMBER	ITEM NUMBER/ PROJECT LOCATION	ITEM DESCRIPTION/ PROJECT LOCATION	DATE LET	UNIT/ QUANTITY	ENGR. EST.	AVERAGE BID	AWARDED BID
=====	503-00211	Agg Column Ground Improvement		Lin Foot	=====		
NH050A-034		US50A PUEBLO WEST PURCELL INT	03/26/20	4,461.00	38.00	52.08	59.00
		WEIGHTED AVERAGE FOR THE FIRST QUARTER		4,461.00	38.00	52.08	59.00
		WEIGHTED AVERAGE FOR THE YEAR		4,461.00	38.00	52.08	59.00
=====	503-00310	CSL Testing		Each	=====		
BR0343-040 FBR0343-043		US 34 REPUBLICAN RIVER BRIDGE	01/16/20	5.00	2750.00	2057.49	1300.00
		US 34 D-28-P STRUCTURE REPLAC					
		WEIGHTED AVERAGE FOR THE FIRST QUARTER		5.00	2750.00	2057.49	1300.00
CC0852-106 FBR0852-108		US-85 LOUVIERS TO MP 191.75	04/23/20	4.00	1500.00	3232.84	3630.00
		US-85 BETWEEN LOUVIERS AND MP					
		WEIGHTED AVERAGE FOR THE SECOND QUARTER		4.00	1500.00	3232.84	3630.00
		WEIGHTED AVERAGE FOR THE YEAR		9.00	2194.44	2664.13	2335.56
=====	504-04410	Block Facing		Sq Foot	=====		
IM0761-226		I76/SH52 Interchange	04/02/20	225.00	90.00	74.24	83.21
		WEIGHTED AVERAGE FOR THE SECOND QUARTER		225.00	90.00	74.24	83.21
		WEIGHTED AVERAGE FOR THE YEAR		225.00	90.00	74.24	83.21
=====	504-04420	Precast Panel Facing		Sq Foot	=====		
NH050A-034		US50A PUEBLO WEST PURCELL INT	03/26/20	11,301.00	36.00	46.21	46.50
		WEIGHTED AVERAGE FOR THE FIRST QUARTER		11,301.00	36.00	46.21	46.50
		WEIGHTED AVERAGE FOR THE YEAR		11,301.00	36.00	46.21	46.50
=====	504-05000	Wire Mesh Facing		Sq Foot	=====		
NH050A-034		US50A PUEBLO WEST PURCELL INT	03/26/20	11,301.00	30.00	22.34	25.00
		WEIGHTED AVERAGE FOR THE FIRST QUARTER		11,301.00	30.00	22.34	25.00
		WEIGHTED AVERAGE FOR THE YEAR		11,301.00	30.00	22.34	25.00

COLORADO DEPARTMENT OF TRANSPORTATION
 ITEM UNIT COSTS BY PROJECTS -- 2020 COST DATA

10:58 Friday, October 2, 2020 144

PROJECT NUMBER	ITEM NUMBER/ PROJECT LOCATION	ITEM DESCRIPTION/ PROJECT LOCATION	DATE LET	UNIT/ QUANTITY	ENGR. EST.	AVERAGE BID	AWARDED BID
=====	504-08050	Stone Landscape Wall		Sq Foot	=====		
NHPP0091-044		SH 9 FRISCO MAIN ST TO IRON S	03/05/20	372.00	75.00	81.72	71.00
	WEIGHTED AVERAGE FOR THE FIRST QUARTER			372.00	75.00	81.72	71.00
	WEIGHTED AVERAGE FOR THE YEAR			372.00	75.00	81.72	71.00
=====	504-08255	Masonry Landscape Wall (Dry Stack)		Sq Foot	=====		
C0402-094		US 40 GRAND COUNTY SIGNAL REP	02/27/20	44.00	100.00	75.00	35.00
	WEIGHTED AVERAGE FOR THE FIRST QUARTER			44.00	100.00	75.00	35.00
	WEIGHTED AVERAGE FOR THE YEAR			44.00	100.00	75.00	35.00
=====	506-00005	Riprap		Sq Yard	=====		
BR025A-046		K-18-U ON I-25 AT MP112 BRIDG	03/05/20	279.00	250.00	88.01	51.24
	WEIGHTED AVERAGE FOR THE FIRST QUARTER			279.00	250.00	88.01	51.24
	WEIGHTED AVERAGE FOR THE YEAR			279.00	250.00	88.01	51.24
=====	506-00030	Grouted Riprap		Cubic Yard	=====		
PWQM240-172		El Paso County, north Colorad	01/23/20	7.00	175.00	655.00	800.00
	WEIGHTED AVERAGE FOR THE FIRST QUARTER			7.00	175.00	655.00	800.00
SFTY2254-091		225 Ramp Improvements	04/09/20	11.00	1500.00	465.00	650.00
	WEIGHTED AVERAGE FOR THE SECOND QUARTER			11.00	1500.00	465.00	650.00
	WEIGHTED AVERAGE FOR THE YEAR			18.00	984.72	538.89	708.33
=====	506-00036	Grouted Riprap (36 In) (Special)		Cubic Yard	=====		
NHPP0091-044		SH 9 FRISCO MAIN ST TO IRON S	03/05/20	9.00	500.00	805.00	880.00
	WEIGHTED AVERAGE FOR THE FIRST QUARTER			9.00	500.00	805.00	880.00
	WEIGHTED AVERAGE FOR THE YEAR			9.00	500.00	805.00	880.00

COLORADO DEPARTMENT OF TRANSPORTATION
ITEM UNIT COSTS BY PROJECTS -- 2020 COST DATA

10:58 Friday, October 2, 2020 145

PROJECT NUMBER	ITEM NUMBER/ PROJECT LOCATION	ITEM DESCRIPTION/ PROJECT LOCATION	DATE LET	UNIT/ QUANTITY	ENGR. EST.	AVERAGE BID	AWARDED BID
=====	506-00100	Riprap (Gabions)		Cubic Yard	=====		
NHPP0091-044		SH 9 FRISCO MAIN ST TO IRON S	03/05/20	90.00	300.00	490.00	500.00
		WEIGHTED AVERAGE FOR THE FIRST QUARTER		90.00	300.00	490.00	500.00
		WEIGHTED AVERAGE FOR THE YEAR		90.00	300.00	490.00	500.00
=====	506-00206	Riprap (6 In)		Cubic Yard	=====		
NH050A-034		US50A PUEBLO WEST PURCELL INT	03/26/20	110.00	160.00	122.94	82.00
		WEIGHTED AVERAGE FOR THE FIRST QUARTER		110.00	160.00	122.94	82.00
IM0761-226		I76/SH52 Interchange	04/02/20	79.00	108.00	125.03	137.01
CC0852-106		US-85 LOUVIERS TO MP 191.75	04/23/20	554.00	110.00	108.02	85.00
FBR0852-108		US-85 BETWEEN LOUVIERS AND MP					
		WEIGHTED AVERAGE FOR THE SECOND QUARTER		633.00	109.75	109.91	91.49
		WEIGHTED AVERAGE FOR THE YEAR		743.00	117.19	111.86	90.09
=====	506-00209	Riprap (9 In)		Cubic Yard	=====		
FSA0341-097		US 34 & MACGREGOR INTERSECTIO	01/09/20	401.00	140.00	150.00	150.00
NHPP0343-041		I-76 & US 34 FT. MORGAN AREA	01/09/20	18.00	212.00	214.42	137.00
BR0343-040		US 34 REPUBLICAN RIVER BRIDGE	01/16/20	16.00	135.00	191.60	205.00
FBR0343-043		US 34 D-28-P STRUCTURE REPLAC					
STR0101-027		SH 10 Overlay La Junta West	02/27/20	3.00	450.00	810.41	900.00
NH050A-034		US50A PUEBLO WEST PURCELL INT	03/26/20	248.00	150.00	98.16	85.00
HPP 0501-067		US 50 AND SH 92 DELTA INTERSE	03/26/20	24.00	120.00	322.93	161.00
		WEIGHTED AVERAGE FOR THE FIRST QUARTER		710.00	145.84	118.70	131.75
CC0852-106		US-85 LOUVIERS TO MP 191.75	04/23/20	1,913.00	115.00	91.78	80.00
FBR0852-108		US-85 BETWEEN LOUVIERS AND MP					
FSA1602-159		US 160 AND SH 17 INTERSECTION	04/30/20	2.00	500.00	351.00	343.00
FBR0343-042		US 34 D-27-G STRUCTURE REPLAC	05/07/20	6.00	150.00	209.10	240.00
		WEIGHTED AVERAGE FOR THE SECOND QUARTER		1,921.00	115.51	92.29	80.77
		WEIGHTED AVERAGE FOR THE YEAR		2,631.00	123.69	96.10	94.53

COLORADO DEPARTMENT OF TRANSPORTATION
 ITEM UNIT COSTS BY PROJECTS -- 2020 COST DATA

10:58 Friday, October 2, 2020 146

PROJECT NUMBER	ITEM NUMBER/ PROJECT LOCATION	ITEM DESCRIPTION/ PROJECT LOCATION	DATE LET	UNIT/ QUANTITY	ENGR. EST.	AVERAGE BID	AWARDED BID
=====	506-00212	Riprap (12 In)		Cubic Yard	=====		
NHPP0343-041		I-76 & US 34 FT. MORGAN AREA	01/09/20	115.00	125.00	195.98	137.00
BR0343-040		US 34 REPUBLICAN RIVER BRIDGE	01/16/20	963.00	140.00	151.91	140.00
FBR0343-043		US 34 D-28-P STRUCTURE REPLAC					
NHPP145A-080		SH 145 Keystone-Placerville R	03/05/20	9.00	400.00	225.00	225.00
NH050A-034		US50A PUEBLO WEST PURCELL INT	03/26/20	228.00	140.00	99.71	86.00
		WEIGHTED AVERAGE FOR THE FIRST QUARTER		1,315.00	140.47	141.93	130.96
STA340A-021		SH340 MP 6-6.76 MESA COUNTY	04/02/20	16.00	200.00	192.33	196.00
CC0852-106		US-85 LOUVIERS TO MP 191.75	04/23/20	1,299.00	125.00	96.32	80.00
FBR0852-108		US-85 BETWEEN LOUVIERS AND MP					
NH050A-035		US 50A Pueblo Regional Pond	05/28/20	668.00	115.00	108.23	80.00
NH050A-037		US 50A Pueblo Regional Pond					
		WEIGHTED AVERAGE FOR THE SECOND QUARTER		1,983.00	122.24	100.64	80.94
		WEIGHTED AVERAGE FOR THE YEAR		3,298.00	129.51	114.48	100.88
=====	506-00218	Riprap (18 In)		Cubic Yard	=====		
NH050A-034		US50A PUEBLO WEST PURCELL INT	03/26/20	101.00	170.00	102.96	87.00
		WEIGHTED AVERAGE FOR THE FIRST QUARTER		101.00	170.00	102.96	87.00
CC0852-106		US-85 LOUVIERS TO MP 191.75	04/23/20	210.00	100.00	109.57	83.60
FBR0852-108		US-85 BETWEEN LOUVIERS AND MP					
FBR0343-042		US 34 D-27-G STRUCTURE REPLAC	05/07/20	800.00	150.00	150.77	120.00
		WEIGHTED AVERAGE FOR THE SECOND QUARTER		1,010.00	139.60	142.97	112.43
		WEIGHTED AVERAGE FOR THE YEAR		1,111.00	142.37	139.64	110.12
=====	506-00224	Riprap (24 In)		Cubic Yard	=====		
STA059A-036		SH 59 SEIBERT TO COPE	02/06/20	2,255.00	140.00	156.50	143.00
NHPP145A-080		SH 145 Keystone-Placerville R	03/05/20	259.00	200.00	250.00	250.00
		WEIGHTED AVERAGE FOR THE FIRST QUARTER		2,514.00	146.18	161.58	154.02

COLORADO DEPARTMENT OF TRANSPORTATION
 ITEM UNIT COSTS BY PROJECTS -- 2020 COST DATA

10:58 Friday, October 2, 2020 147

PROJECT NUMBER	ITEM NUMBER/ PROJECT LOCATION	ITEM DESCRIPTION/ PROJECT LOCATION	DATE LET	UNIT/ QUANTITY	ENGR. EST.	AVERAGE BID	AWARDED BID
=====	506-00224	Riprap (24 In)		Cubic Yard	=====		
CC0852-106 FBR0852-108		US-85 LOUVIERS TO MP 191.75 US-85 BETWEEN LOUVIERS AND MP	04/23/20	407.00	110.00	142.84	121.00
		WEIGHTED AVERAGE FOR THE SECOND QUARTER		407.00	110.00	142.84	121.00
		WEIGHTED AVERAGE FOR THE YEAR		2,921.00	141.14	153.97	149.42
=====	506-00409	Soil Riprap (9 In)		Cubic Yard	=====		
PWQM240-172		El Paso County, north Colorad	01/23/20	6.00	90.00	170.50	211.00
		WEIGHTED AVERAGE FOR THE FIRST QUARTER		6.00	90.00	170.50	211.00
IM0761-226 NHPP0253-276		I76/SH52 Interchange I-25 EXPRESS LANES SEGMENT 5	04/02/20 05/15/20	148.00 288.00	95.00 191.00	108.19 135.60	103.00 135.60
		WEIGHTED AVERAGE FOR THE SECOND QUARTER		436.00	158.41	114.15	124.53
		WEIGHTED AVERAGE FOR THE YEAR		442.00	157.48	114.66	125.71
=====	506-00412	Soil Riprap (12 In)		Cubic Yard	=====		
BR0343-040 FBR0343-043 PWQM240-172		US 34 REPUBLICAN RIVER BRIDGE US 34 D-28-P STRUCTURE REPLAC El Paso County, north Colorad	01/16/20 01/23/20	104.00 118.00	150.00 130.00	147.83 109.50	120.00 119.00
		WEIGHTED AVERAGE FOR THE FIRST QUARTER		222.00	139.37	137.31	119.47
C0853-112 NHPP0253-276		US85 & WCR98 INTERSECTION IMP I-25 EXPRESS LANES SEGMENT 5	05/07/20 05/15/20	15.00 195.00	150.00 180.00	170.88 99.54	200.00 99.54
		WEIGHTED AVERAGE FOR THE SECOND QUARTER		210.00	177.86	126.72	106.72
		WEIGHTED AVERAGE FOR THE YEAR		432.00	158.08	134.47	113.27

PROJECT NUMBER	ITEM NUMBER/ PROJECT LOCATION	ITEM DESCRIPTION/ PROJECT LOCATION	DATE LET	UNIT/ QUANTITY	ENGR. EST.	AVERAGE BID	AWARDED BID
=====	506-00418	Soil Riprap (18 In)		Cubic Yard	=====		
PWQM240-172		El Paso County, north Colorad	01/23/20	2,733.00	150.00	111.50	113.00
	WEIGHTED AVERAGE FOR THE FIRST QUARTER			2,733.00	150.00	111.50	113.00
	WEIGHTED AVERAGE FOR THE YEAR			2,733.00	150.00	111.50	113.00
=====	506-01020	Geogrid Reinforce		Sq Yard	=====		
NHPP0091-044		SH 9 FRISCO MAIN ST TO IRON S	03/05/20	150.00	10.00	15.55	5.50
NH050A-034		US50A PUEBLO WEST PURCELL INT	03/26/20	4,599.00	4.00	5.23	4.25
	WEIGHTED AVERAGE FOR THE FIRST QUARTER			4,749.00	4.19	5.35	4.29
	WEIGHTED AVERAGE FOR THE YEAR			4,749.00	4.19	5.35	4.29
=====	507-00000	Conc S and D Pave		Cubic Yard	=====		
NHPP4701-134		C-470 NOISE WALL WEST OF LUCE	02/06/20	101.00	250.00	629.80	539.00
NHPP145A-080		SH 145 Keystone-Placerville R	03/05/20	8.60	1900.00	1255.00	1255.00
NHPP0091-044		SH 9 FRISCO MAIN ST TO IRON S	03/05/20	4.00	800.00	940.67	1200.00
NH050A-034		US50A PUEBLO WEST PURCELL INT	03/26/20	95.00	570.00	855.52	881.00
	WEIGHTED AVERAGE FOR THE FIRST QUARTER			208.60	474.30	770.32	736.95
SFTY2254-091		225 Ramp Improvements	04/09/20	178.00	1200.00	1042.00	934.00
CC0852-106		US-85 LOUVIERS TO MP 191.75	04/23/20	12.00	850.00	1190.22	77.00
FBR0852-108		US-85 BETWEEN LOUVIERS AND MP					
	WEIGHTED AVERAGE FOR THE SECOND QUARTER			190.00	1177.89	1073.48	879.87
	WEIGHTED AVERAGE FOR THE YEAR			398.60	809.68	849.18	805.08
=====	507-00100	Conc S and D Pave (Reinf)		Cubic Yard	=====		
FSA0253-262		I-25 SB BOTTLENECK I-76 TO I-	01/09/20	19.00	850.00	859.70	1000.00
PWQM240-172		El Paso County, north Colorad	01/23/20	45.00	850.00	1245.50	1091.00
NH050A-034		US50A PUEBLO WEST PURCELL INT	03/26/20	164.00	600.00	910.56	840.00
	WEIGHTED AVERAGE FOR THE FIRST QUARTER			228.00	670.18	929.23	902.87

COLORADO DEPARTMENT OF TRANSPORTATION
 ITEM UNIT COSTS BY PROJECTS -- 2020 COST DATA

10:58 Friday, October 2, 2020 149

PROJECT NUMBER	ITEM NUMBER/ PROJECT LOCATION	ITEM DESCRIPTION/ PROJECT LOCATION	DATE LET	UNIT/ QUANTITY	ENGR. EST.	AVERAGE BID	AWARDED BID
=====	507-00100	Conc S and D Pave (Reinf)		Cubic Yard	=====		
IM0761-226		I76/SH52 Interchange	04/02/20	21.10	750.00	948.39	675.00
		WEIGHTED AVERAGE FOR THE SECOND QUARTER		21.10	750.00	948.39	675.00
		WEIGHTED AVERAGE FOR THE YEAR		249.10	676.94	930.99	883.57
=====	507-00400	Bitum S and D Pave (Asph)		Ton	=====		
NHPP0343-041		I-76 & US 34 FT. MORGAN AREA	01/09/20	24.00	320.00	405.38	351.00
BR0343-040		US 34 REPUBLICAN RIVER BRIDGE	01/16/20	6.00	400.00	340.10	310.00
FBR0343-043		US 34 D-28-P STRUCTURE REPLAC					
STA059A-036		SH 59 SEIBERT TO COPE	02/06/20	27.00	400.00	382.50	385.00
		WEIGHTED AVERAGE FOR THE FIRST QUARTER		57.00	366.32	383.25	362.79
IM0761-226		I76/SH52 Interchange	04/02/20	14.00	450.00	463.88	424.00
		WEIGHTED AVERAGE FOR THE SECOND QUARTER		14.00	450.00	463.88	424.00
		WEIGHTED AVERAGE FOR THE YEAR		71.00	382.82	413.64	374.86
=====	507-00550	Concrete Lined Ditch		Lin Foot	=====		
CC0852-106		US-85 LOUVIERS TO MP 191.75	04/23/20	228.00	50.00	128.90	176.66
FBR0852-108		US-85 BETWEEN LOUVIERS AND MP					
		WEIGHTED AVERAGE FOR THE SECOND QUARTER		228.00	50.00	128.90	176.66
		WEIGHTED AVERAGE FOR THE YEAR		228.00	50.00	128.90	176.66
=====	508-00520	Insulation Material (2 In)		Sq Foot	=====		
NHPP0091-044		SH 9 FRISCO MAIN ST TO IRON S	03/05/20	800.00	7.50	5.53	9.00
		WEIGHTED AVERAGE FOR THE FIRST QUARTER		800.00	7.50	5.53	9.00
		WEIGHTED AVERAGE FOR THE YEAR		800.00	7.50	5.53	9.00

COLORADO DEPARTMENT OF TRANSPORTATION
ITEM UNIT COSTS BY PROJECTS -- 2020 COST DATA

10:58 Friday, October 2, 2020 150

PROJECT NUMBER	ITEM NUMBER/ PROJECT LOCATION	ITEM DESCRIPTION/ PROJECT LOCATION	DATE LET	UNIT/ QUANTITY	ENGR. EST.	AVERAGE BID	AWARDED BID
=====	509-00000	Str Steel		Pound	=====		
NHPP0091-044		SH 9 FRISCO MAIN ST TO IRON S	03/05/20	105,842.00	3.00	8.97	4.15
	WEIGHTED	AVERAGE FOR THE FIRST QUARTER		105,842.00	3.00	8.97	4.15
		WEIGHTED AVERAGE FOR THE YEAR		105,842.00	3.00	8.97	4.15
=====	509-00001	Str Steel (Galv)		Pound	=====		
NHPP0343-041		I-76 & US 34 FT. MORGAN AREA	01/09/20	127.00	11.00	36.50	51.00
	WEIGHTED	AVERAGE FOR THE FIRST QUARTER		127.00	11.00	36.50	51.00
		WEIGHTED AVERAGE FOR THE YEAR		127.00	11.00	36.50	51.00
=====	509-08100	Provide Temporary Support		LUMP SUM	=====		
NHPP 0852-116		US85:HAMPDEN TO FLORIDA-RESUR	02/06/20	1.00	50000.00	92500.00	135000.00
	WEIGHTED	AVERAGE FOR THE FIRST QUARTER		1.00	50000.00	92500.00	135000.00
		WEIGHTED AVERAGE FOR THE YEAR		1.00	50000.00	92500.00	135000.00
=====	509-08121	Temp Bridge Deck		Lin Foot	=====		
NHPPR100-251		SH 2/ Vasquez	06/25/20	40.00	850.00	637.93	802.85
	WEIGHTED	AVERAGE FOR THE SECOND QUARTER		40.00	850.00	637.93	802.85
		WEIGHTED AVERAGE FOR THE YEAR		40.00	850.00	637.93	802.85
=====	510-20100	Str PA(Spec)		Lin Foot	=====		
NHPP0091-044		SH 9 FRISCO MAIN ST TO IRON S	03/05/20	109.00	1500.00	3025.00	2500.00
	WEIGHTED	AVERAGE FOR THE FIRST QUARTER		109.00	1500.00	3025.00	2500.00
		WEIGHTED AVERAGE FOR THE YEAR		109.00	1500.00	3025.00	2500.00
=====	513-00690	Bridge Drain (Spec)		Each	=====		
CC0852-106		US-85 LOUVIERS TO MP 191.75	04/23/20	3.00	5000.00	4584.11	7150.00

COLORADO DEPARTMENT OF TRANSPORTATION
 ITEM UNIT COSTS BY PROJECTS -- 2020 COST DATA

10:58 Friday, October 2, 2020 151

PROJECT NUMBER	ITEM NUMBER/ PROJECT LOCATION	ITEM DESCRIPTION/ PROJECT LOCATION	DATE LET	UNIT/ QUANTITY	ENGR. EST.	AVERAGE BID	AWARDED BID
===== 513-00690 FBR0852-108		Bridge Drain (Spec) US-85 BETWEEN LOUVIERS AND MP		Each =====			
	WEIGHTED AVERAGE FOR THE SECOND QUARTER			3.00	5000.00	4584.11	7150.00
	WEIGHTED AVERAGE FOR THE YEAR			3.00	5000.00	4584.11	7150.00
===== 514-00042		Ped Railing (42 In)		Lin Foot =====			
NHPP0343-041		I-76 & US 34 FT. MORGAN AREA	01/09/20	16.00	304.00	179.33	88.00
	WEIGHTED AVERAGE FOR THE FIRST QUARTER			16.00	304.00	179.33	88.00
IM0761-226		I76/SH52 Interchange	04/02/20	165.00	200.00	303.87	271.47
	WEIGHTED AVERAGE FOR THE SECOND QUARTER			165.00	200.00	303.87	271.47
	WEIGHTED AVERAGE FOR THE YEAR			181.00	209.19	298.90	255.25
===== 514-00054		Ped Railing (54 In)		Lin Foot =====			
NHPP4701-134		C-470 NOISE WALL WEST OF LUCE	02/06/20	36.00	250.00	439.78	200.00
	WEIGHTED AVERAGE FOR THE FIRST QUARTER			36.00	250.00	439.78	200.00
	WEIGHTED AVERAGE FOR THE YEAR			36.00	250.00	439.78	200.00
===== 514-00201		Ped Railing (Steel) (Spec)		Lin Foot =====			
FSA0341-097		US 34 & MACGREGOR INTERSECTIO	01/09/20	484.00	250.00	190.00	190.00
	WEIGHTED AVERAGE FOR THE FIRST QUARTER			484.00	250.00	190.00	190.00
	WEIGHTED AVERAGE FOR THE YEAR			484.00	250.00	190.00	190.00
===== 515-00120		Waterproofing (Membrane)		Sq Yard =====			
NHPP0343-041		I-76 & US 34 FT. MORGAN AREA	01/09/20	3,084.00	21.00	17.39	19.00

PROJECT NUMBER	ITEM NUMBER/ PROJECT LOCATION	ITEM DESCRIPTION/ PROJECT LOCATION	DATE LET	UNIT/ QUANTITY	ENGR. EST.	AVERAGE BID	AWARDED BID
=====	515-00120	Waterproofing (Membrane)		Sq Yard	=====		
BR0343-040	US 34 REPUBLICAN RIVER BRIDGE	US 34 REPUBLICAN RIVER BRIDGE	01/16/20	1,441.00	22.00	19.41	16.00
FBR0343-043	US 34 D-28-P STRUCTURE REPLAC	US 34 D-28-P STRUCTURE REPLAC					
NH 0503-093	US50 WEST OF TEXAS CREEK MP 2	US50 WEST OF TEXAS CREEK MP 2	01/23/20	1,898.00	20.00	18.03	17.06
NHPP 0852-116	US85:HAMPDEN TO FLORIDA-RESUR	US85:HAMPDEN TO FLORIDA-RESUR	02/06/20	7,815.00	20.00	17.50	20.00
STA059A-036	SH 59 SEIBERT TO COPE	SH 59 SEIBERT TO COPE	02/06/20	2,318.00	18.00	19.75	17.50
STA069A-033	SH69 MP 58.7 TO 71.58	SH69 MP 58.7 TO 71.58	02/13/20	282.00	20.00	23.01	25.00
STR0101-027	SH 10 Overlay La Junta West	SH 10 Overlay La Junta West	02/27/20	136.00	20.00	40.46	40.00
NH050A-034	US50A PUEBLO WEST PURCELL INT	US50A PUEBLO WEST PURCELL INT	03/26/20	3,580.00	20.00	17.49	17.00
	WEIGHTED AVERAGE FOR THE FIRST QUARTER			20,554.00	20.06	18.06	18.69
IM0761-226	I76/SH52 Interchange	I76/SH52 Interchange	04/02/20	1,384.00	20.00	19.64	17.00
CC0852-106	US-85 LOUVIERS TO MP 191.75	US-85 LOUVIERS TO MP 191.75	04/23/20	1,538.00	20.00	18.97	22.00
FBR0852-108	US-85 BETWEEN LOUVIERS AND MP	US-85 BETWEEN LOUVIERS AND MP					
FBR0343-042	US 34 D-27-G STRUCTURE REPLAC	US 34 D-27-G STRUCTURE REPLAC	05/07/20	667.00	20.00	19.75	17.00
NHPP0253-276	I-25 EXPRESS LANES SEGMENT 5	I-25 EXPRESS LANES SEGMENT 5	05/15/20	247.00	21.00	21.03	21.03
	WEIGHTED AVERAGE FOR THE SECOND QUARTER			3,836.00	20.06	19.38	19.26
	WEIGHTED AVERAGE FOR THE YEAR			24,390.00	20.06	18.43	18.78
=====	515-00400	Concrete Sealer		Sq Yard	=====		
NHPP0343-041	I-76 & US 34 FT. MORGAN AREA	I-76 & US 34 FT. MORGAN AREA	01/09/20	592.00	19.00	20.38	34.00
BR0343-040	US 34 REPUBLICAN RIVER BRIDGE	US 34 REPUBLICAN RIVER BRIDGE	01/16/20	365.00	20.00	17.39	16.00
FBR0343-043	US 34 D-28-P STRUCTURE REPLAC	US 34 D-28-P STRUCTURE REPLAC					
STA059A-036	SH 59 SEIBERT TO COPE	SH 59 SEIBERT TO COPE	02/06/20	267.00	12.50	14.38	13.75
	WEIGHTED AVERAGE FOR THE FIRST QUARTER			1,224.00	17.88	18.22	24.22
IM0761-226	I76/SH52 Interchange	I76/SH52 Interchange	04/02/20	537.00	17.00	18.52	15.00
	WEIGHTED AVERAGE FOR THE SECOND QUARTER			537.00	17.00	18.52	15.00
	WEIGHTED AVERAGE FOR THE YEAR			1,761.00	17.61	18.35	21.41
=====	518-00000	Brdg Compress Joint Sealer		Lin Foot	=====		
NH 0503-093	US50 WEST OF TEXAS CREEK MP 2	US50 WEST OF TEXAS CREEK MP 2	01/23/20	64.00	90.00	112.51	105.01
	WEIGHTED AVERAGE FOR THE FIRST QUARTER			64.00	90.00	112.51	105.01
	WEIGHTED AVERAGE FOR THE YEAR			64.00	90.00	112.51	105.01

COLORADO DEPARTMENT OF TRANSPORTATION
ITEM UNIT COSTS BY PROJECTS -- 2020 COST DATA

10:58 Friday, October 2, 2020 153

PROJECT NUMBER	ITEM NUMBER/ PROJECT LOCATION	ITEM DESCRIPTION/ PROJECT LOCATION	DATE LET	UNIT/ QUANTITY	ENGR. EST.	AVERAGE BID	AWARDED BID
=====	518-01001	Br Expan Joint (Asphaltic Plug)		Lin Foot	=====		
NHPP0343-041		I-76 & US 34 FT. MORGAN AREA	01/09/20	379.00	160.00	271.78	181.00
NH 0503-093		US50 WEST OF TEXAS CREEK MP 2	01/23/20	102.00	150.00	163.76	157.52
STA069A-033		SH69 MP 58.7 TO 71.58	02/13/20	24.00	200.00	442.75	500.00
		WEIGHTED AVERAGE FOR THE FIRST QUARTER		505.00	159.88	261.82	191.42
		WEIGHTED AVERAGE FOR THE YEAR		505.00	159.88	261.82	191.42
=====	518-01004	Br Expan Device (0-4 In)		Lin Foot	=====		
NHPP 0852-116		US85:HAMPDEN TO FLORIDA-RESUR	02/06/20	618.00	425.00	275.00	400.00
NH050A-034		US50A PUEBLO WEST PURCELL INT	03/26/20	244.00	310.00	307.59	228.00
		WEIGHTED AVERAGE FOR THE FIRST QUARTER		862.00	392.45	294.96	351.31
IM0761-226		I76/SH52 Interchange	04/02/20	142.00	310.00	317.72	275.00
CC0852-106		US-85 LOUVIERS TO MP 191.75	04/23/20	173.00	415.00	253.63	264.00
FBR0852-108		US-85 BETWEEN LOUVIERS AND MP					
NHPPR100-251		SH 2/ Vasquez	06/25/20	608.00	300.00	251.00	250.00
		WEIGHTED AVERAGE FOR THE SECOND QUARTER		923.00	323.09	270.47	256.47
		WEIGHTED AVERAGE FOR THE YEAR		1,785.00	356.59	281.98	302.27
=====	518-01050	Br Expan Device (Special)		Lin Foot	=====		
NHPP0343-041		I-76 & US 34 FT. MORGAN AREA	01/09/20	58.00	150.00	329.09	310.00
		WEIGHTED AVERAGE FOR THE FIRST QUARTER		58.00	150.00	329.09	310.00
		WEIGHTED AVERAGE FOR THE YEAR		58.00	150.00	329.09	310.00
=====	518-01109	Inst Br Expan Device (Greater Than 4 In)		Lin Foot	=====		
NHPPR100-251		SH 2/ Vasquez	06/25/20	40.00	700.00	451.50	400.00
		WEIGHTED AVERAGE FOR THE SECOND QUARTER		40.00	700.00	451.50	400.00
		WEIGHTED AVERAGE FOR THE YEAR		40.00	700.00	451.50	400.00

COLORADO DEPARTMENT OF TRANSPORTATION
ITEM UNIT COSTS BY PROJECTS -- 2020 COST DATA

10:58 Friday, October 2, 2020 154

PROJECT NUMBER	ITEM NUMBER/ PROJECT LOCATION	ITEM DESCRIPTION/ PROJECT LOCATION	DATE LET	UNIT/ QUANTITY	ENGR. EST.	AVERAGE BID	AWARDED BID
===== 518-03000		Saw and Seal Br Joint		Lin Foot	=====		
NH 0503-093		US50 WEST OF TEXAS CREEK MP 2	01/23/20	102.00	30.00	36.80	33.60
STA069A-033		SH69 MP 58.7 TO 71.58	02/13/20	96.00	25.00	35.76	40.00
		WEIGHTED AVERAGE FOR THE FIRST QUARTER		198.00	27.58	36.29	36.70
STR092A-030		SH92 MP 31.748-48.5, DELTA AND	04/02/20	116.00	26.00	55.15	22.00
STR0341-101		SH 34 North of Grandby Resurf	04/02/20	173.00	30.00	24.78	22.50
		WEIGHTED AVERAGE FOR THE SECOND QUARTER		289.00	28.39	32.41	22.30
		WEIGHTED AVERAGE FOR THE YEAR		487.00	28.06	33.57	28.16
===== 518-03100		Rapid Cure Silicone Jt Seal		Lin Foot	=====		
NHPP 0852-116		US85:HAMPDEN TO FLORIDA-RESUR	02/06/20	1,120.00	70.00	21.00	15.00
		WEIGHTED AVERAGE FOR THE FIRST QUARTER		1,120.00	70.00	21.00	15.00
		WEIGHTED AVERAGE FOR THE YEAR		1,120.00	70.00	21.00	15.00
===== 519-01000		Epoxy Resin (Injection)		Lin Foot	=====		
NHPP0343-041		I-76 & US 34 FT. MORGAN AREA	01/09/20	21.00	207.00	323.06	641.00
STR0101-027		SH 10 Overlay La Junta West	02/27/20	217.00	125.00	188.76	200.00
		WEIGHTED AVERAGE FOR THE FIRST QUARTER		238.00	132.24	200.61	238.91
IM025A-048		Northbound I-25 bridge at Exi	05/28/20	782.00	400.00	124.69	52.00
		WEIGHTED AVERAGE FOR THE SECOND QUARTER		782.00	400.00	124.69	52.00
		WEIGHTED AVERAGE FOR THE YEAR		1,020.00	337.52	142.41	95.61
===== 601-01000		Conc CL B		Cubic Yard	=====		
NHPP0091-044		SH 9 FRISCO MAIN ST TO IRON S	03/05/20	3.00	1000.00	1707.83	2000.00

COLORADO DEPARTMENT OF TRANSPORTATION
 ITEM UNIT COSTS BY PROJECTS -- 2020 COST DATA

10:58 Friday, October 2, 2020 155

PROJECT NUMBER	ITEM NUMBER/ PROJECT LOCATION	ITEM DESCRIPTION/ PROJECT LOCATION	DATE LET	UNIT/ QUANTITY	ENGR. EST.	AVERAGE BID	AWARDED BID
=====	601-01000	Conc CL B		Cubic Yard	=====		
NH050A-034		US50A PUEBLO WEST PURCELL INT	03/26/20	140.00	800.00	1179.69	1041.00
	WEIGHTED AVERAGE FOR THE FIRST QUARTER			143.00	804.20	1183.90	1061.12
IM0761-226		I76/SH52 Interchange	04/02/20	23.00	1400.00	1145.10	318.00
STA340A-021		SH340 MP 6-6.76 MESA COUNTY	04/02/20	14.00	800.00	1148.33	1210.00
CC0852-106		US-85 LOUVIERS TO MP 191.75	04/23/20	153.00	550.00	1121.52	979.00
FBR0852-108		US-85 BETWEEN LOUVIERS AND MP					
NH050A-035		US 50A Pueblo Regional Pond	05/28/20	334.00	800.00	815.56	700.00
NH050A-037		US 50A Pueblo Regional Pond					
	WEIGHTED AVERAGE FOR THE SECOND QUARTER			524.00	753.34	923.28	778.32
	WEIGHTED AVERAGE FOR THE YEAR			667.00	764.24	979.56	838.95
=====	601-01025	Conc CL B (Misc)		Cubic Yard	=====		
IM0761-226		I76/SH52 Interchange	04/02/20	1.00	1000.00	1604.44	318.00
	WEIGHTED AVERAGE FOR THE SECOND QUARTER			1.00	1000.00	1604.44	318.00
	WEIGHTED AVERAGE FOR THE YEAR			1.00	1000.00	1604.44	318.00
=====	601-01050	Conc CL B (Wall)		Cubic Yard	=====		
HPP 0501-067		US 50 AND SH 92 DELTA INTERSE	03/26/20	4.00	1000.00	1310.00	1840.00
	WEIGHTED AVERAGE FOR THE FIRST QUARTER			4.00	1000.00	1310.00	1840.00
	WEIGHTED AVERAGE FOR THE YEAR			4.00	1000.00	1310.00	1840.00
=====	601-03000	Conc CL D		Cubic Yard	=====		
NHPP0702-359		I-70 No Name Tunnel Lighting	02/27/20	7.00	2000.00	1301.46	715.00
NHPP145A-080		SH 145 Keystone-Placerville R	03/05/20	29.00	1900.00	1965.00	1965.00
NHPP0091-044		SH 9 FRISCO MAIN ST TO IRON S	03/05/20	95.00	1000.00	988.33	1000.00
	WEIGHTED AVERAGE FOR THE FIRST QUARTER			131.00	1252.67	1096.79	1198.40
IM0761-226		I76/SH52 Interchange	04/02/20	7.00	1500.00	2088.57	1351.50
	WEIGHTED AVERAGE FOR THE SECOND QUARTER			7.00	1500.00	2088.57	1351.50
	WEIGHTED AVERAGE FOR THE YEAR			138.00	1265.22	1221.08	1206.16

COLORADO DEPARTMENT OF TRANSPORTATION
ITEM UNIT COSTS BY PROJECTS -- 2020 COST DATA

10:58 Friday, October 2, 2020 156

PROJECT NUMBER	ITEM NUMBER/ PROJECT LOCATION	ITEM DESCRIPTION/ PROJECT LOCATION	DATE LET	UNIT/ QUANTITY	ENGR. EST.	AVERAGE BID	AWARDED BID
=====	601-03030	Conc CL D (Box)		Cubic Yard	=====		
BR025A-046		K-18-U ON I-25 AT MP112 BRIDG	03/05/20	388.00	800.00	644.71	544.95
NH050A-034		US50A PUEBLO WEST PURCELL INT	03/26/20	146.00	800.00	1241.63	1058.00
		WEIGHTED AVERAGE FOR THE FIRST QUARTER		534.00	800.00	824.21	685.22
NHPP0253-276		I-25 EXPRESS LANES SEGMENT 5	05/15/20	194.00	935.00	1068.72	1068.72
		WEIGHTED AVERAGE FOR THE SECOND QUARTER		194.00	935.00	1068.72	1068.72
		WEIGHTED AVERAGE FOR THE YEAR		728.00	835.98	835.84	787.42
=====	601-03040	Conc CL D (Bridge)		Cubic Yard	=====		
NHPP0343-041		I-76 & US 34 FT. MORGAN AREA	01/09/20	5.70	1200.00	1776.14	2087.00
BR0343-040		US 34 REPUBLICAN RIVER BRIDGE	01/16/20	763.00	750.00	810.17	850.00
FBR0343-043		US 34 D-28-P STRUCTURE REPLAC					
NH050A-034		US50A PUEBLO WEST PURCELL INT	03/26/20	1,818.00	650.00	773.50	708.00
		WEIGHTED AVERAGE FOR THE FIRST QUARTER		2,586.70	680.71	783.17	752.92
IM0761-226		I76/SH52 Interchange	04/02/20	56.10	1500.00	1463.36	1275.00
CC0852-106		US-85 LOUVIERS TO MP 191.75	04/23/20	768.00	800.00	846.37	715.00
FBR0852-108		US-85 BETWEEN LOUVIERS AND MP					
FBR0343-042		US 34 D-27-G STRUCTURE REPLAC	05/07/20	293.00	875.00	827.43	750.00
		WEIGHTED AVERAGE FOR THE SECOND QUARTER		1,117.10	854.82	867.34	752.30
		WEIGHTED AVERAGE FOR THE YEAR		3,703.80	733.22	810.44	752.74
=====	601-03050	Conc CL D (Wall)		Cubic Yard	=====		
PWQM240-172		El Paso County, north Colorad	01/23/20	458.00	800.00	1303.00	1206.00
NHPP4701-134		C-470 NOISE WALL WEST OF LUCE	02/06/20	381.00	800.00	940.00	785.00
NH050A-034		US50A PUEBLO WEST PURCELL INT	03/26/20	72.00	1100.00	1580.36	1275.00
		WEIGHTED AVERAGE FOR THE FIRST QUARTER		911.00	823.71	1146.46	1035.38

COLORADO DEPARTMENT OF TRANSPORTATION
ITEM UNIT COSTS BY PROJECTS -- 2020 COST DATA

10:58 Friday, October 2, 2020 157

PROJECT NUMBER	ITEM NUMBER/ PROJECT LOCATION	ITEM DESCRIPTION/ PROJECT LOCATION	DATE LET	UNIT/ QUANTITY	ENGR. EST.	AVERAGE BID	AWARDED BID
=====	601-03050	Conc CL D (Wall)		Cubic Yard	=====		
SFTY2254-091		225 Ramp Improvements	04/09/20	85.00	100.00	772.50	625.00
CC0852-106		US-85 LOUVIERS TO MP 191.75	04/23/20	238.00	750.00	1011.73	759.00
FBR0852-108		US-85 BETWEEN LOUVIERS AND MP					
NHPP0253-276		I-25 EXPRESS LANES SEGMENT 5	05/15/20	427.00	1064.00	965.77	965.77
		WEIGHTED AVERAGE FOR THE SECOND QUARTER		750.00	855.10	987.62	861.53
		WEIGHTED AVERAGE FOR THE YEAR		1,661.00	837.89	1079.11	956.88
=====	601-03057	Conc CL DR		Cubic Yard	=====		
NHPP0343-041		I-76 & US 34 FT. MORGAN AREA	01/09/20	25.50	2250.00	2689.01	2764.00
NH 0503-093		US50 WEST OF TEXAS CREEK MP 2	01/23/20	5.00	2500.00	2728.39	2656.77
NHPP 0852-116		US85:HAMPDEN TO FLORIDA-RESUR	02/06/20	129.00	2500.00	3250.00	3000.00
STA059A-036		SH 59 SEIBERT TO COPE	02/06/20	47.00	2000.00	2030.00	1960.00
STA069A-033		SH69 MP 58.7 TO 71.58	02/13/20	1.00	2000.00	3204.77	3500.00
		WEIGHTED AVERAGE FOR THE FIRST QUARTER		207.50	2353.61	2880.19	2729.57
NHPPR100-251		SH 2/ Vasquez	06/25/20	71.90	1700.00	1543.95	1317.90
		WEIGHTED AVERAGE FOR THE SECOND QUARTER		71.90	1700.00	1543.95	1317.90
		WEIGHTED AVERAGE FOR THE YEAR		279.40	2185.42	2551.33	2366.30
=====	601-04550	Conc CL G		Cubic Yard	=====		
IM0761-226		I76/SH52 Interchange	04/02/20	292.90	1150.00	980.88	1000.00
NHPP0253-276		I-25 EXPRESS LANES SEGMENT 5	05/15/20	214.00	1153.00	989.58	989.58
		WEIGHTED AVERAGE FOR THE SECOND QUARTER		506.90	1151.27	981.70	995.60
		WEIGHTED AVERAGE FOR THE YEAR		506.90	1151.27	981.70	995.60
=====	601-06102	Concrete (Patching)		Cubic Foot	=====		
NHPP0343-041		I-76 & US 34 FT. MORGAN AREA	01/09/20	11.00	79.00	317.99	406.00
		WEIGHTED AVERAGE FOR THE FIRST QUARTER		11.00	79.00	317.99	406.00
		WEIGHTED AVERAGE FOR THE YEAR		11.00	79.00	317.99	406.00

COLORADO DEPARTMENT OF TRANSPORTATION
 ITEM UNIT COSTS BY PROJECTS -- 2020 COST DATA

10:58 Friday, October 2, 2020 158

PROJECT NUMBER	ITEM NUMBER/ PROJECT LOCATION	ITEM DESCRIPTION/ PROJECT LOCATION	DATE LET	UNIT/ QUANTITY	ENGR. EST.	AVERAGE BID	AWARDED BID
=====	601-06150	Conc (Patching)		Sq Foot	=====		
STA0703-443		I-70 EJMT TUNNELS PAVING	02/06/20	2,869.00	80.00	68.34	70.82
		WEIGHTED AVERAGE FOR THE FIRST QUARTER		2,869.00	80.00	68.34	70.82
		WEIGHTED AVERAGE FOR THE YEAR		2,869.00	80.00	68.34	70.82
=====	601-40300	Struct Conc Coating		Sq Yard	=====		
STA0703-443		I-70 EJMT TUNNELS PAVING	02/06/20	7,083.00	15.00	20.38	21.20
NHPP4701-134		C-470 NOISE WALL WEST OF LUCE	02/06/20	5,808.00	10.00	10.10	7.00
		WEIGHTED AVERAGE FOR THE FIRST QUARTER		12,891.00	12.75	13.47	14.80
CC0852-106		US-85 LOUVIERS TO MP 191.75	04/23/20	1,141.00	12.00	13.62	13.00
FBR0852-108		US-85 BETWEEN LOUVIERS AND MP					
NHPP0253-276		I-25 EXPRESS LANES SEGMENT 5	05/15/20	1,362.00	11.00	10.70	10.70
		WEIGHTED AVERAGE FOR THE SECOND QUARTER		2,503.00	11.46	13.24	11.75
		WEIGHTED AVERAGE FOR THE YEAR		15,394.00	12.54	13.42	14.31
=====	601-40400	Struct Conc Stain		Sq Yard	=====		
NH050A-034		US50A PUEBLO WEST PURCELL INT	03/26/20	3,908.00	20.00	14.42	25.40
		WEIGHTED AVERAGE FOR THE FIRST QUARTER		3,908.00	20.00	14.42	25.40
		WEIGHTED AVERAGE FOR THE YEAR		3,908.00	20.00	14.42	25.40
=====	601-40401	Struct Conc Stain		Sq Foot	=====		
NHPP0091-044		SH 9 FRISCO MAIN ST TO IRON S	03/05/20	35,024.00	4.00	2.32	2.40
		WEIGHTED AVERAGE FOR THE FIRST QUARTER		35,024.00	4.00	2.32	2.40
		WEIGHTED AVERAGE FOR THE YEAR		35,024.00	4.00	2.32	2.40
=====	601-51005	Galvanic Anodes		Each	=====		
NHPP0343-041		I-76 & US 34 FT. MORGAN AREA	01/09/20	263.00	28.00	37.79	43.00

PROJECT NUMBER	ITEM NUMBER/ PROJECT LOCATION	ITEM DESCRIPTION/ PROJECT LOCATION	DATE LET	UNIT/ QUANTITY	ENGR. EST.	AVERAGE BID	AWARDED BID
===== 601-51005 Galvanic Anodes Each =====							
NH 0503-093	US50 WEST OF TEXAS CREEK MP 2	01/23/20	180.00	60.00	29.18	28.35	
NHPP 0852-116	US85:HAMPDEN TO FLORIDA-RESUR	02/06/20	2,570.00	27.00	30.50	26.00	
STA059A-036	SH 59 SEIBERT TO COPE	02/06/20	629.00	31.00	39.50	39.00	
STA069A-033	SH69 MP 58.7 TO 71.58	02/13/20	25.00	27.00	39.96	40.00	
WEIGHTED AVERAGE FOR THE FIRST QUARTER				3,667.00	29.38	32.75	29.66
WEIGHTED AVERAGE FOR THE YEAR				3,667.00	29.38	32.75	29.66
===== 602-00000 Reinf Steel Pound =====							
NHPP0343-041	I-76 & US 34 FT. MORGAN AREA	01/09/20	360.00	2.00	3.34	4.50	
NH 0503-093	US50 WEST OF TEXAS CREEK MP 2	01/23/20	180.00	2.00	6.65	6.30	
STA0703-443	I-70 EJMT TUNNELS PAVING	02/06/20	7,738.00	2.50	5.10	5.30	
STA059A-036	SH 59 SEIBERT TO COPE	02/06/20	2,408.00	2.00	2.38	2.25	
STA069A-033	SH69 MP 58.7 TO 71.58	02/13/20	25.00	5.00	6.10	8.00	
NHPP0091-044	SH 9 FRISCO MAIN ST TO IRON S	03/05/20	9,861.00	5.00	2.52	2.10	
NH050A-034	US50A PUEBLO WEST PURCELL INT	03/26/20	45,295.00	1.00	1.09	1.06	
HPP 0501-067	US 50 AND SH 92 DELTA INTERSE	03/26/20	400.00	1.60	4.30	6.45	
WEIGHTED AVERAGE FOR THE FIRST QUARTER				66,267.00	1.82	1.38	1.82
IM0761-226	I76/SH52 Interchange	04/02/20	3,956.00	1.10	1.74	1.05	
STA340A-021	SH340 MP 6-6.76 MESA COUNTY	04/02/20	1,588.00	1.70	3.25	2.00	
SFTY2254-091	225 Ramp Improvements	04/09/20	12,500.00	2.00	1.98	2.30	
NHPP0253-276	I-25 EXPRESS LANES SEGMENT 5	05/15/20	104,272.00	1.10	1.10	1.10	
NHPPR100-251	SH 2/ Vasquez	06/25/20	3,615.00	1.50	2.27	2.53	
WEIGHTED AVERAGE FOR THE SECOND QUARTER				125,931.00	1.21	1.45	1.27
WEIGHTED AVERAGE FOR THE YEAR				192,198.00	1.42	1.40	1.46
===== 602-00020 Reinf Steel (Epoxy) Pound =====							
NHPP0343-041	I-76 & US 34 FT. MORGAN AREA	01/09/20	2,460.00	2.00	2.85	3.00	
BR0343-040	US 34 REPUBLICAN RIVER BRIDGE	01/16/20	157,025.00	1.20	1.14	1.10	
FBR0343-043	US 34 D-28-P STRUCTURE REPLAC						
NHPP 0852-116	US85:HAMPDEN TO FLORIDA-RESUR	02/06/20	17,833.00	1.25	2.25	2.00	
NHPP4701-134	C-470 NOISE WALL WEST OF LUCE	02/06/20	73,481.00	1.90	1.17	1.05	
NHPP0702-359	I-70 No Name Tunnel Lighting	02/27/20	800.00	2.00	6.57	4.00	
NHPP145A-080	SH 145 Keystone-Placerville R	03/05/20	1,566.00	3.00	2.30	2.30	

COLORADO DEPARTMENT OF TRANSPORTATION
ITEM UNIT COSTS BY PROJECTS -- 2020 COST DATA

10:58 Friday, October 2, 2020 160

PROJECT NUMBER	ITEM NUMBER/ PROJECT LOCATION	ITEM DESCRIPTION/ PROJECT LOCATION	DATE LET	UNIT/ QUANTITY	ENGR. EST.	AVERAGE BID	AWARDED BID
=====	602-00020	Reinf Steel (Epoxy)		Pound	=====	=====	=====
BR025A-046		K-18-U ON I-25 AT MP112 BRIDG	03/05/20	80,805.00	2.00	1.32	1.60
NH050A-034		US50A PUEBLO WEST PURCELL INT	03/26/20	429,722.00	1.25	1.12	1.16
		WEIGHTED AVERAGE FOR THE FIRST QUARTER		763,692.00	1.39	1.16	1.21
IM0761-226		I76/SH52 Interchange	04/02/20	65,025.00	1.50	1.48	1.15
CC0852-106		US-85 LOUVIERS TO MP 191.75	04/23/20	232,223.00	1.20	1.15	1.43
FBR0852-108		US-85 BETWEEN LOUVIERS AND MP					
FBR0343-042		US 34 D-27-G STRUCTURE REPLAC	05/07/20	41,940.00	1.20	1.52	1.40
NHPP0253-276		I-25 EXPRESS LANES SEGMENT 5	05/15/20	79,936.00	1.26	1.23	1.23
NHPPR100-251		SH 2/ Vasquez	06/25/20	2,890.00	2.00	3.36	2.72
		WEIGHTED AVERAGE FOR THE SECOND QUARTER		422,014.00	1.26	1.26	1.35
		WEIGHTED AVERAGE FOR THE YEAR		1,185,706.00	1.34	1.20	1.26
=====	602-00030	Reinf (FRP) (Surface)		M Kip Foot	=====	=====	=====
IM025A-048		Northbound I-25 bridge at Exi	05/28/20	75.00	1900.00	4258.59	4900.00
		WEIGHTED AVERAGE FOR THE SECOND QUARTER		75.00	1900.00	4258.59	4900.00
		WEIGHTED AVERAGE FOR THE YEAR		75.00	1900.00	4258.59	4900.00
=====	602-00060	Reinf Steel Splice		Each	=====	=====	=====
STA0703-443		I-70 EJMT TUNNELS PAVING	02/06/20	696.00	20.00	95.41	99.36
		WEIGHTED AVERAGE FOR THE FIRST QUARTER		696.00	20.00	95.41	99.36
		WEIGHTED AVERAGE FOR THE YEAR		696.00	20.00	95.41	99.36
=====	603-00001	Annular Space Grouting		Cubic Yard	=====	=====	=====
NHPP0091-044		SH 9 FRISCO MAIN ST TO IRON S	03/05/20	10.00	600.00	821.67	900.00
		WEIGHTED AVERAGE FOR THE FIRST QUARTER		10.00	600.00	821.67	900.00
		WEIGHTED AVERAGE FOR THE YEAR		10.00	600.00	821.67	900.00

COLORADO DEPARTMENT OF TRANSPORTATION
 ITEM UNIT COSTS BY PROJECTS -- 2020 COST DATA

10:58 Friday, October 2, 2020 161

PROJECT NUMBER	ITEM NUMBER/ PROJECT LOCATION	ITEM DESCRIPTION/ PROJECT LOCATION	DATE LET	UNIT/ QUANTITY	ENGR. EST.	AVERAGE BID	AWARDED BID
=====	603-00047	Prepare Culvert Pipe (48 In)		Lin Foot	=====		
NHPP0091-044		SH 9 FRISCO MAIN ST TO IRON S	03/05/20	108.00	110.00	130.00	200.00
	WEIGHTED AVERAGE FOR THE FIRST QUARTER			108.00	110.00	130.00	200.00
	WEIGHTED AVERAGE FOR THE YEAR			108.00	110.00	130.00	200.00
=====	603-00048	Culvert Lining (48 In)		Lin Foot	=====		
NHPP0091-044		SH 9 FRISCO MAIN ST TO IRON S	03/05/20	120.00	400.00	653.33	680.00
	WEIGHTED AVERAGE FOR THE FIRST QUARTER			120.00	400.00	653.33	680.00
	WEIGHTED AVERAGE FOR THE YEAR			120.00	400.00	653.33	680.00
=====	603-00052	Culvert Lining (48 In) (Spray App)		Lin Foot	=====		
STR012A-050		CULVERT REPAIR I-25 AND US 35	01/30/20	403.00	520.00	330.00	330.00
	WEIGHTED AVERAGE FOR THE FIRST QUARTER			403.00	520.00	330.00	330.00
	WEIGHTED AVERAGE FOR THE YEAR			403.00	520.00	330.00	330.00
=====	603-00060	Culvert Lining (60 In)		Lin Foot	=====		
NHPP0091-044		SH 9 FRISCO MAIN ST TO IRON S	03/05/20	119.00	600.00	1045.00	1400.00
	WEIGHTED AVERAGE FOR THE FIRST QUARTER			119.00	600.00	1045.00	1400.00
	WEIGHTED AVERAGE FOR THE YEAR			119.00	600.00	1045.00	1400.00
=====	603-00061	Prep Culvert Pipe (60 In)		Lin Foot	=====		
NHPP0091-044		SH 9 FRISCO MAIN ST TO IRON S	03/05/20	109.00	110.00	98.75	170.00
	WEIGHTED AVERAGE FOR THE FIRST QUARTER			109.00	110.00	98.75	170.00
	WEIGHTED AVERAGE FOR THE YEAR			109.00	110.00	98.75	170.00
=====	603-01155	15 In RCP (CIP)		Lin Foot	=====		
PWQM240-172		El Paso County, north Colorad	01/23/20	583.00	145.00	137.50	115.00
	WEIGHTED AVERAGE FOR THE FIRST QUARTER			583.00	145.00	137.50	115.00

COLORADO DEPARTMENT OF TRANSPORTATION
 ITEM UNIT COSTS BY PROJECTS -- 2020 COST DATA

10:58 Friday, October 2, 2020 162

PROJECT NUMBER	ITEM NUMBER/ PROJECT LOCATION	ITEM DESCRIPTION/ PROJECT LOCATION	DATE LET	UNIT/ QUANTITY	ENGR. EST.	AVERAGE BID	AWARDED BID
=====	603-01155	15 In RCP (CIP)		Lin Foot	=====		
IM0761-226		I76/SH52 Interchange	04/02/20	132.00	105.00	88.79	83.00
STA340A-021		SH340 MP 6-6.76 MESA COUNTY	04/02/20	42.00	120.00	129.00	109.00
		WEIGHTED AVERAGE FOR THE SECOND QUARTER		174.00	108.62	93.62	89.28
		WEIGHTED AVERAGE FOR THE YEAR		757.00	136.64	116.71	109.09
=====	603-01180	18 In RCP		Lin Foot	=====		
CC0852-106		US-85 LOUVIERS TO MP 191.75	04/23/20	9,380.00	70.00	83.79	56.10
FBR0852-108		US-85 BETWEEN LOUVIERS AND MP					
		WEIGHTED AVERAGE FOR THE SECOND QUARTER		9,380.00	70.00	83.79	56.10
		WEIGHTED AVERAGE FOR THE YEAR		9,380.00	70.00	83.79	56.10
=====	603-01185	18 In RCP (CIP)		Lin Foot	=====		
FSA0341-097		US 34 & MACGREGOR INTERSECTIO	01/09/20	23.00	120.00	140.00	140.00
PWQM240-172		El Paso County, north Colorad	01/23/20	1,060.00	155.00	134.00	98.00
NHPP0091-044		SH 9 FRISCO MAIN ST TO IRON S	03/05/20	132.00	150.00	120.23	115.00
NH050A-034		US50A PUEBLO WEST PURCELL INT	03/26/20	2,571.00	110.00	102.55	85.00
HPP 0501-067		US 50 AND SH 92 DELTA INTERSE	03/26/20	367.00	120.00	158.08	159.20
SHE 0703-461		I-70 and Kipling North Phase	03/26/20	70.00	125.00	169.20	121.00
		WEIGHTED AVERAGE FOR THE FIRST QUARTER		4,223.00	123.72	108.28	96.55
IM0761-226		I76/SH52 Interchange	04/02/20	4.00	200.00	222.26	470.00
		WEIGHTED AVERAGE FOR THE SECOND QUARTER		4.00	200.00	222.26	470.00
		WEIGHTED AVERAGE FOR THE YEAR		4,227.00	123.79	108.42	96.90
=====	603-01240	24 In RCP		Lin Foot	=====		
CC0852-106		US-85 LOUVIERS TO MP 191.75	04/23/20	433.00	100.00	112.37	67.10

COLORADO DEPARTMENT OF TRANSPORTATION
 ITEM UNIT COSTS BY PROJECTS -- 2020 COST DATA

10:58 Friday, October 2, 2020 163

PROJECT NUMBER	ITEM NUMBER/ PROJECT LOCATION	ITEM DESCRIPTION/ PROJECT LOCATION	DATE LET	UNIT/ QUANTITY	ENGR. EST.	AVERAGE BID	AWARDED BID
===== 603-01240	24 In RCP			Lin Foot	=====		
FBR0852-108		US-85 BETWEEN LOUVIERS AND MP					
	WEIGHTED AVERAGE FOR THE SECOND QUARTER			433.00	100.00	112.37	67.10
	WEIGHTED AVERAGE FOR THE YEAR			433.00	100.00	112.37	67.10
===== 603-01245	24 In RCP (CIP)			Lin Foot	=====		
FSA0341-097		US 34 & MACGREGOR INTERSECTIO	01/09/20	89.00	140.00	120.00	120.00
PWQM240-172		El Paso County, north Colorad	01/23/20	630.00	170.00	197.50	195.00
NHPP0091-044		SH 9 FRISCO MAIN ST TO IRON S	03/05/20	1,507.00	120.00	147.33	150.00
NH050A-034		US50A PUEBLO WEST PURCELL INT	03/26/20	1,450.00	150.00	154.62	104.00
HPP 0501-067		US 50 AND SH 92 DELTA INTERSE	03/26/20	115.00	140.00	175.78	140.00
	WEIGHTED AVERAGE FOR THE FIRST QUARTER			3,791.00	140.86	155.91	138.88
IM0761-226		I76/SH52 Interchange	04/02/20	34.00	120.00	170.66	231.99
NH050A-035		US 50A Pueblo Regional Pond	05/28/20	2,245.00	100.00	132.58	140.00
NH050A-037		US 50A Pueblo Regional Pond					
	WEIGHTED AVERAGE FOR THE SECOND QUARTER			2,279.00	100.30	133.07	141.37
	WEIGHTED AVERAGE FOR THE YEAR			6,070.00	125.63	144.33	139.81
===== 603-01305	30 In RCP (CIP)			Lin Foot	=====		
FSA0341-097		US 34 & MACGREGOR INTERSECTIO	01/09/20	406.00	185.00	175.00	175.00
PWQM240-172		El Paso County, north Colorad	01/23/20	491.00	175.00	199.50	159.00
NH050A-034		US50A PUEBLO WEST PURCELL INT	03/26/20	893.00	170.00	172.16	129.00
	WEIGHTED AVERAGE FOR THE FIRST QUARTER			1,790.00	174.77	175.44	147.66
	WEIGHTED AVERAGE FOR THE YEAR			1,790.00	174.77	175.44	147.66
===== 603-01360	36 In RCP			Lin Foot	=====		
NHPP145A-080		SH 145 Keystone-Placerville R	03/05/20	48.00	400.00	390.00	390.00
	WEIGHTED AVERAGE FOR THE FIRST QUARTER			48.00	400.00	390.00	390.00

COLORADO DEPARTMENT OF TRANSPORTATION
 ITEM UNIT COSTS BY PROJECTS -- 2020 COST DATA

10:58 Friday, October 2, 2020 164

PROJECT NUMBER	ITEM NUMBER/ PROJECT LOCATION	ITEM DESCRIPTION/ PROJECT LOCATION	DATE LET	UNIT/ QUANTITY	ENGR. EST.	AVERAGE BID	AWARDED BID
=====	603-01360	36 In RCP		Lin Foot	=====		
CC0852-106		US-85 LOUVIERS TO MP 191.75	04/23/20	831.00	150.00	180.34	130.90
FBR0852-108		US-85 BETWEEN LOUVIERS AND MP					
		WEIGHTED AVERAGE FOR THE SECOND QUARTER		831.00	150.00	180.34	130.90
		WEIGHTED AVERAGE FOR THE YEAR		879.00	163.65	181.85	145.05
=====	603-01365	36 In RCP (CIP)		Lin Foot	=====		
PWQM240-172		El Paso County, north Colorad	01/23/20	995.00	205.00	251.00	222.00
NH050A-034		US50A PUEBLO WEST PURCELL INT	03/26/20	2,700.00	300.00	191.49	194.00
		WEIGHTED AVERAGE FOR THE FIRST QUARTER		3,695.00	274.42	196.51	201.54
		WEIGHTED AVERAGE FOR THE YEAR		3,695.00	274.42	196.51	201.54
=====	603-01420	42 In RCP		Lin Foot	=====		
CC0852-106		US-85 LOUVIERS TO MP 191.75	04/23/20	987.00	175.00	206.44	165.00
FBR0852-108		US-85 BETWEEN LOUVIERS AND MP					
		WEIGHTED AVERAGE FOR THE SECOND QUARTER		987.00	175.00	206.44	165.00
		WEIGHTED AVERAGE FOR THE YEAR		987.00	175.00	206.44	165.00
=====	603-01425	42 In RCP (CIP)		Lin Foot	=====		
PWQM240-172		El Paso County, north Colorad	01/23/20	555.00	200.00	305.00	250.00
		WEIGHTED AVERAGE FOR THE FIRST QUARTER		555.00	200.00	305.00	250.00
		WEIGHTED AVERAGE FOR THE YEAR		555.00	200.00	305.00	250.00
=====	603-01480	48 In RCP		Lin Foot	=====		
NHPP145A-080		SH 145 Keystone-Placerville R	03/05/20	50.00	400.00	590.00	590.00
		WEIGHTED AVERAGE FOR THE FIRST QUARTER		50.00	400.00	590.00	590.00

COLORADO DEPARTMENT OF TRANSPORTATION
 ITEM UNIT COSTS BY PROJECTS -- 2020 COST DATA

10:58 Friday, October 2, 2020 165

PROJECT NUMBER	ITEM NUMBER/ PROJECT LOCATION	ITEM DESCRIPTION/ PROJECT LOCATION	DATE LET	UNIT/ QUANTITY	ENGR. EST.	AVERAGE BID	AWARDED BID
=====	603-01480	48 In RCP		Lin Foot	=====		
CC0852-106		US-85 LOUVIERS TO MP 191.75	04/23/20	289.00	220.00	264.42	192.50
FBR0852-108		US-85 BETWEEN LOUVIERS AND MP					
		WEIGHTED AVERAGE FOR THE SECOND QUARTER		289.00	220.00	264.42	192.50
		WEIGHTED AVERAGE FOR THE YEAR		339.00	246.55	271.31	251.13
=====	603-01485	48 In RCP (CIP)		Lin Foot	=====		
PWQM240-172		El Paso County, north Colorad	01/23/20	5,989.00	240.00	400.00	320.00
		WEIGHTED AVERAGE FOR THE FIRST QUARTER		5,989.00	240.00	400.00	320.00
IM0761-226		I76/SH52 Interchange	04/02/20	11.00	325.00	627.25	870.00
		WEIGHTED AVERAGE FOR THE SECOND QUARTER		11.00	325.00	627.25	870.00
		WEIGHTED AVERAGE FOR THE YEAR		6,000.00	240.16	401.45	321.01
=====	603-01545	54 In RCP (CIP)		Lin Foot	=====		
PWQM240-172		El Paso County, north Colorad	01/23/20	553.00	300.00	449.50	379.00
		WEIGHTED AVERAGE FOR THE FIRST QUARTER		553.00	300.00	449.50	379.00
		WEIGHTED AVERAGE FOR THE YEAR		553.00	300.00	449.50	379.00
=====	603-01600	60 In RCP		Lin Foot	=====		
NHPP145A-080		SH 145 Keystone-Placerville R	03/05/20	56.00	500.00	750.00	750.00
		WEIGHTED AVERAGE FOR THE FIRST QUARTER		56.00	500.00	750.00	750.00
		WEIGHTED AVERAGE FOR THE YEAR		56.00	500.00	750.00	750.00
=====	603-01605	60 In RCP (CIP)		Lin Foot	=====		
PWQM240-172		El Paso County, north Colorad	01/23/20	605.00	550.00	588.50	557.00
		WEIGHTED AVERAGE FOR THE FIRST QUARTER		605.00	550.00	588.50	557.00
		WEIGHTED AVERAGE FOR THE YEAR		605.00	550.00	588.50	557.00

COLORADO DEPARTMENT OF TRANSPORTATION
ITEM UNIT COSTS BY PROJECTS -- 2020 COST DATA

10:58 Friday, October 2, 2020 166

PROJECT NUMBER	ITEM NUMBER/ PROJECT LOCATION	ITEM DESCRIPTION/ PROJECT LOCATION	DATE LET	UNIT/ QUANTITY	ENGR. EST.	AVERAGE BID	AWARDED BID
=====	603-01665	66 In RCP (CIP)		Lin Foot	=====		
PWQM240-172		El Paso County, north Colorad	01/23/20	1,180.00	600.00	667.50	545.00
	WEIGHTED AVERAGE FOR THE FIRST QUARTER			1,180.00	600.00	667.50	545.00
	WEIGHTED AVERAGE FOR THE YEAR			1,180.00	600.00	667.50	545.00
=====	603-02180	23x14 In RCP		Lin Foot	=====		
CC0852-106		US-85 LOUVIERS TO MP 191.75	04/23/20	152.00	175.00	133.38	171.60
FBR0852-108		US-85 BETWEEN LOUVIERS AND MP					
	WEIGHTED AVERAGE FOR THE SECOND QUARTER			152.00	175.00	133.38	171.60
	WEIGHTED AVERAGE FOR THE YEAR			152.00	175.00	133.38	171.60
=====	603-02185	23x14 In RCP (CIP)		Lin Foot	=====		
NHPP0343-041		I-76 & US 34 FT. MORGAN AREA	01/09/20	62.00	150.00	154.88	113.00
	WEIGHTED AVERAGE FOR THE FIRST QUARTER			62.00	150.00	154.88	113.00
	WEIGHTED AVERAGE FOR THE YEAR			62.00	150.00	154.88	113.00
=====	603-02245	30x19 In RCP (CIP)		Lin Foot	=====		
PWQM240-172		El Paso County, north Colorad	01/23/20	29.00	220.00	181.00	152.00
NH050A-034		US50A PUEBLO WEST PURCELL INT	03/26/20	67.00	160.00	193.15	188.00
	WEIGHTED AVERAGE FOR THE FIRST QUARTER			96.00	178.13	191.97	177.13
C0853-112		US85 & WCR98 INTERSECTION IMP	05/07/20	114.00	200.00	154.25	150.00
	WEIGHTED AVERAGE FOR THE SECOND QUARTER			114.00	200.00	154.25	150.00
	WEIGHTED AVERAGE FOR THE YEAR			210.00	190.00	169.13	162.40
=====	603-02305	38x24 In RCP (CIP)		Lin Foot	=====		
FSA0341-097		US 34 & MACGREGOR INTERSECTIO	01/09/20	85.00	185.00	180.00	180.00

COLORADO DEPARTMENT OF TRANSPORTATION
 ITEM UNIT COSTS BY PROJECTS -- 2020 COST DATA

10:58 Friday, October 2, 2020 167

PROJECT NUMBER	ITEM NUMBER/ PROJECT LOCATION	ITEM DESCRIPTION/ PROJECT LOCATION	DATE LET	UNIT/ QUANTITY	ENGR. EST.	AVERAGE BID	AWARDED BID
=====	603-02305	38x24 In RCP (CIP)		Lin Foot	=====	=====	=====
NH050A-034		US50A PUEBLO WEST PURCELL INT	03/26/20	43.00	180.00	216.91	215.00
		WEIGHTED AVERAGE FOR THE FIRST QUARTER		128.00	183.32	209.59	191.76
		WEIGHTED AVERAGE FOR THE YEAR		128.00	183.32	209.59	191.76
=====	603-02545	68x43 In RCP (CIP)		Lin Foot	=====	=====	=====
PWQM240-172		El Paso County, north Colorad	01/23/20	37.00	600.00	580.00	390.00
		WEIGHTED AVERAGE FOR THE FIRST QUARTER		37.00	600.00	580.00	390.00
		WEIGHTED AVERAGE FOR THE YEAR		37.00	600.00	580.00	390.00
=====	603-03360	36 In RCP Spec		Lin Foot	=====	=====	=====
HPP 0501-067		US 50 AND SH 92 DELTA INTERSE	03/26/20	112.00	705.00	363.30	348.00
		WEIGHTED AVERAGE FOR THE FIRST QUARTER		112.00	705.00	363.30	348.00
		WEIGHTED AVERAGE FOR THE YEAR		112.00	705.00	363.30	348.00
=====	603-05018	18 In RCES		Each	=====	=====	=====
NH050A-034		US50A PUEBLO WEST PURCELL INT	03/26/20	11.00	1150.00	1627.55	3000.00
		WEIGHTED AVERAGE FOR THE FIRST QUARTER		11.00	1150.00	1627.55	3000.00
CC0852-106 FBR0852-108		US-85 LOUVIERS TO MP 191.75	04/23/20	22.00	1500.00	1250.37	1204.50
		US-85 BETWEEN LOUVIERS AND MP					
		WEIGHTED AVERAGE FOR THE SECOND QUARTER		22.00	1500.00	1250.37	1204.50
		WEIGHTED AVERAGE FOR THE YEAR		33.00	1383.33	1376.09	1803.00
=====	603-05024	24 In RCES		Each	=====	=====	=====
FSA0341-097		US 34 & MACGREGOR INTERSECTIO	01/09/20	2.00	1300.00	1300.00	1300.00

COLORADO DEPARTMENT OF TRANSPORTATION
ITEM UNIT COSTS BY PROJECTS -- 2020 COST DATA

10:58 Friday, October 2, 2020 168

PROJECT NUMBER	ITEM NUMBER/ PROJECT LOCATION	ITEM DESCRIPTION/ PROJECT LOCATION	DATE LET	UNIT/ QUANTITY	ENGR. EST.	AVERAGE BID	AWARDED BID
=====	603-05024	24 In RCES		Each =====			
NHPP0091-044		SH 9 FRISCO MAIN ST TO IRON S	03/05/20	8.00	3000.00	1340.00	1200.00
NH050A-034		US50A PUEBLO WEST PURCELL INT	03/26/20	8.00	1250.00	1829.13	3200.00
		WEIGHTED AVERAGE FOR THE FIRST QUARTER		18.00	2033.33	1686.94	2100.00
CC0852-106		US-85 LOUVIERS TO MP 191.75	04/23/20	12.00	1700.00	1433.55	1490.50
FBR0852-108		US-85 BETWEEN LOUVIERS AND MP					
NH050A-035		US 50A Pueblo Regional Pond	05/28/20	2.00	1000.00	2701.75	5000.00
NH050A-037		US 50A Pueblo Regional Pond					
		WEIGHTED AVERAGE FOR THE SECOND QUARTER		14.00	1600.00	1614.72	1991.86
		WEIGHTED AVERAGE FOR THE YEAR		32.00	1843.75	1646.90	2052.69
=====	603-05030	30 In RCES		Each =====			
FSA0341-097		US 34 & MACGREGOR INTERSECTIO	01/09/20	7.00	1500.00	1700.00	1700.00
NH050A-034		US50A PUEBLO WEST PURCELL INT	03/26/20	8.00	1500.00	2237.73	3600.00
		WEIGHTED AVERAGE FOR THE FIRST QUARTER		15.00	1500.00	2184.71	2713.33
		WEIGHTED AVERAGE FOR THE YEAR		15.00	1500.00	2184.71	2713.33
=====	603-05036	36 In RCES		Each =====			
NHPP145A-080		SH 145 Keystone-Placerville R	03/05/20	1.00	3000.00	3250.00	3250.00
NH050A-034		US50A PUEBLO WEST PURCELL INT	03/26/20	6.00	1700.00	2764.05	4700.00
		WEIGHTED AVERAGE FOR THE FIRST QUARTER		7.00	1885.71	2773.96	4492.86
CC0852-106		US-85 LOUVIERS TO MP 191.75	04/23/20	9.00	3500.00	2244.18	2403.50
FBR0852-108		US-85 BETWEEN LOUVIERS AND MP					
		WEIGHTED AVERAGE FOR THE SECOND QUARTER		9.00	3500.00	2244.18	2403.50
		WEIGHTED AVERAGE FOR THE YEAR		16.00	2793.75	2458.72	3317.59
=====	603-05042	42 In RCES		Each =====			
CC0852-106		US-85 LOUVIERS TO MP 191.75	04/23/20	8.00	3750.00	2443.23	2596.00

COLORADO DEPARTMENT OF TRANSPORTATION
 ITEM UNIT COSTS BY PROJECTS -- 2020 COST DATA

10:58 Friday, October 2, 2020 169

PROJECT NUMBER	ITEM NUMBER/ PROJECT LOCATION	ITEM DESCRIPTION/ PROJECT LOCATION	DATE LET	UNIT/ QUANTITY	ENGR. EST.	AVERAGE BID	AWARDED BID
=====	603-05042	42 In RCES		Each	=====		
FBR0852-108		US-85 BETWEEN LOUVIERS AND MP					
	WEIGHTED AVERAGE FOR THE SECOND QUARTER			8.00	3750.00	2443.23	2596.00
	WEIGHTED AVERAGE FOR THE YEAR			8.00	3750.00	2443.23	2596.00
=====	603-05048	48 In RCES		Each	=====		
IM0761-226		I76/SH52 Interchange	04/02/20	3.00	4000.00	2795.46	3218.00
CC0852-106		US-85 LOUVIERS TO MP 191.75	04/23/20	4.00	4000.00	2815.46	2843.50
FBR0852-108		US-85 BETWEEN LOUVIERS AND MP					
	WEIGHTED AVERAGE FOR THE SECOND QUARTER			7.00	4000.00	2807.53	3004.00
	WEIGHTED AVERAGE FOR THE YEAR			7.00	4000.00	2807.53	3004.00
=====	603-05118	23x14 In RCES		Each	=====		
NHPP0343-041		I-76 & US 34 FT. MORGAN AREA	01/09/20	4.00	1350.00	1885.38	1918.00
	WEIGHTED AVERAGE FOR THE FIRST QUARTER			4.00	1350.00	1885.38	1918.00
	WEIGHTED AVERAGE FOR THE YEAR			4.00	1350.00	1885.38	1918.00
=====	603-05124	30x19 In RCES		Each	=====		
NH050A-034		US50A PUEBLO WEST PURCELL INT	03/26/20	2.00	1500.00	2346.44	3500.00
	WEIGHTED AVERAGE FOR THE FIRST QUARTER			2.00	1500.00	2346.44	3500.00
C0853-112		US85 & WCR98 INTERSECTION IMP	05/07/20	2.00	1700.00	2641.88	4000.00
	WEIGHTED AVERAGE FOR THE SECOND QUARTER			2.00	1700.00	2641.88	4000.00
	WEIGHTED AVERAGE FOR THE YEAR			4.00	1600.00	2494.16	3750.00
=====	603-05130	38x24 In RCES		Each	=====		
FSA0341-097		US 34 & MACGREGOR INTERSECTIO	01/09/20	2.00	1800.00	2200.00	2200.00
	WEIGHTED AVERAGE FOR THE FIRST QUARTER			2.00	1800.00	2200.00	2200.00
	WEIGHTED AVERAGE FOR THE YEAR			2.00	1800.00	2200.00	2200.00

COLORADO DEPARTMENT OF TRANSPORTATION
 ITEM UNIT COSTS BY PROJECTS -- 2020 COST DATA

10:58 Friday, October 2, 2020 170

PROJECT NUMBER	ITEM NUMBER/ PROJECT LOCATION	ITEM DESCRIPTION/ PROJECT LOCATION	DATE LET	UNIT/ QUANTITY	ENGR. EST.	AVERAGE BID	AWARDED BID
=====	603-10120	12 In CSP		Lin Foot	=====		
PWQM240-172		El Paso County, north Colorad	01/23/20	61.00	100.00	148.50	137.00
HPP 0501-067		US 50 AND SH 92 DELTA INTERSE	03/26/20	389.00	50.00	118.98	101.00
	WEIGHTED AVERAGE FOR THE FIRST QUARTER			450.00	56.78	122.98	105.88
	WEIGHTED AVERAGE FOR THE YEAR			450.00	56.78	122.98	105.88
=====	603-10180	18 In CSP		Lin Foot	=====		
STA059A-036		SH 59 SEIBERT TO COPE	02/06/20	16.00	125.00	149.00	138.00
NHPP0171-105		SH 17 MP 84.5 to US 285 & SH	03/05/20	160.00	75.00	147.34	102.02
NHPP0091-044		SH 9 FRISCO MAIN ST TO IRON S	03/05/20	28.00	100.00	135.17	150.00
	WEIGHTED AVERAGE FOR THE FIRST QUARTER			204.00	82.35	145.71	111.43
	WEIGHTED AVERAGE FOR THE YEAR			204.00	82.35	145.71	111.43
=====	603-10240	24 In CSP		Lin Foot	=====		
STR012A-050		CULVERT REPAIR I-25 AND US 35	01/30/20	20.00	20.00	190.00	190.00
NHPP0171-105		SH 17 MP 84.5 to US 285 & SH	03/05/20	64.00	90.00	195.03	110.10
NHPP0091-044		SH 9 FRISCO MAIN ST TO IRON S	03/05/20	34.00	200.00	136.00	130.00
	WEIGHTED AVERAGE FOR THE FIRST QUARTER			118.00	109.83	175.54	129.38
IM0761-226		I76/SH52 Interchange	04/02/20	8.00	100.00	170.88	213.01
	WEIGHTED AVERAGE FOR THE SECOND QUARTER			8.00	100.00	170.88	213.01
	WEIGHTED AVERAGE FOR THE YEAR			126.00	109.21	174.83	134.69
=====	603-10300	30 In CSP		Lin Foot	=====		
STR116A-001		SH 116 A Surface Treatment Pr	02/13/20	90.00	135.00	123.40	160.00
NHPP0171-105		SH 17 MP 84.5 to US 285 & SH	03/05/20	38.00	120.00	212.12	136.36
NH050A-034		US50A PUEBLO WEST PURCELL INT	03/26/20	320.00	190.00	93.08	80.00
	WEIGHTED AVERAGE FOR THE FIRST QUARTER			448.00	173.01	100.47	100.85
	WEIGHTED AVERAGE FOR THE YEAR			448.00	173.01	100.47	100.85

COLORADO DEPARTMENT OF TRANSPORTATION
 ITEM UNIT COSTS BY PROJECTS -- 2020 COST DATA

10:58 Friday, October 2, 2020 171

PROJECT NUMBER	ITEM NUMBER/ PROJECT LOCATION	ITEM DESCRIPTION/ PROJECT LOCATION	DATE LET	UNIT/ QUANTITY	ENGR. EST.	AVERAGE BID	AWARDED BID
=====	603-10360	36 In CSP		Lin Foot	=====		
STR2871-038		US 287 Passing Lanes Springfi	03/05/20	24.00	300.00	127.61	145.00
		WEIGHTED AVERAGE FOR THE FIRST QUARTER		24.00	300.00	127.61	145.00
IM0761-226		I76/SH52 Interchange	04/02/20	39.00	220.00	163.00	151.00
		WEIGHTED AVERAGE FOR THE SECOND QUARTER		39.00	220.00	163.00	151.00
		WEIGHTED AVERAGE FOR THE YEAR		63.00	250.48	157.71	148.71
=====	603-10480	48 In CSP		Lin Foot	=====		
STR012A-050 NHPP0091-044		CULVERT REPAIR I-25 AND US 35	01/30/20	22.00	150.00	320.00	320.00
		SH 9 FRISCO MAIN ST TO IRON S	03/05/20	22.00	175.00	221.67	200.00
		WEIGHTED AVERAGE FOR THE FIRST QUARTER		44.00	162.50	246.25	260.00
NHPP0253-276		I-25 EXPRESS LANES SEGMENT 5	05/15/20	72.00	200.00	215.68	215.68
		WEIGHTED AVERAGE FOR THE SECOND QUARTER		72.00	200.00	215.68	215.68
		WEIGHTED AVERAGE FOR THE YEAR		116.00	185.78	232.49	232.49
=====	603-15030	30 In Equiv CSPA		Lin Foot	=====		
STR2871-038		US 287 Passing Lanes Springfi	03/05/20	18.00	350.00	109.13	89.99
		WEIGHTED AVERAGE FOR THE FIRST QUARTER		18.00	350.00	109.13	89.99
		WEIGHTED AVERAGE FOR THE YEAR		18.00	350.00	109.13	89.99
=====	603-15054	54 In Equiv CSPA		Lin Foot	=====		
STR012A-050		CULVERT REPAIR I-25 AND US 35	01/30/20	12.00	200.00	460.00	460.00
		WEIGHTED AVERAGE FOR THE FIRST QUARTER		12.00	200.00	460.00	460.00
		WEIGHTED AVERAGE FOR THE YEAR		12.00	200.00	460.00	460.00

COLORADO DEPARTMENT OF TRANSPORTATION
 ITEM UNIT COSTS BY PROJECTS -- 2020 COST DATA

10:58 Friday, October 2, 2020 172

PROJECT NUMBER	ITEM NUMBER/ PROJECT LOCATION	ITEM DESCRIPTION/ PROJECT LOCATION	DATE LET	UNIT/ QUANTITY	ENGR. EST.	AVERAGE BID	AWARDED BID
=====	603-30018	18 In SES		Each	=====	=====	=====
NHPP0171-105		SH 17 MP 84.5 to US 285 & SH	03/05/20	13.00	500.00	1021.44	1539.33
NHPP0091-044		SH 9 FRISCO MAIN ST TO IRON S	03/05/20	1.00	400.00	905.00	490.00
		WEIGHTED AVERAGE FOR THE FIRST QUARTER		14.00	492.86	1013.13	1464.38
		WEIGHTED AVERAGE FOR THE YEAR		14.00	492.86	1013.13	1464.38
=====	603-30024	24 In SES		Each	=====	=====	=====
STR012A-050		CULVERT REPAIR I-25 AND US 35	01/30/20	1.00	1100.00	2300.00	2300.00
NHPP0171-105		SH 17 MP 84.5 to US 285 & SH	03/05/20	7.00	650.00	1117.55	1672.66
NHPP0091-044		SH 9 FRISCO MAIN ST TO IRON S	03/05/20	2.00	500.00	881.67	360.00
		WEIGHTED AVERAGE FOR THE FIRST QUARTER		10.00	665.00	1109.24	1472.86
IM0761-226		I76/SH52 Interchange	04/02/20	1.00	1000.00	849.58	616.00
		WEIGHTED AVERAGE FOR THE SECOND QUARTER		1.00	1000.00	849.58	616.00
		WEIGHTED AVERAGE FOR THE YEAR		11.00	695.45	1057.31	1394.97
=====	603-30030	30 In SES		Each	=====	=====	=====
STR116A-001		SH 116 A Surface Treatment Pr	02/13/20	2.00	1200.00	971.90	1500.00
NHPP0171-105		SH 17 MP 84.5 to US 285 & SH	03/05/20	4.00	750.00	1325.73	1927.19
		WEIGHTED AVERAGE FOR THE FIRST QUARTER		6.00	900.00	1207.79	1784.79
		WEIGHTED AVERAGE FOR THE YEAR		6.00	900.00	1207.79	1784.79
=====	603-30036	36 In SES		Each	=====	=====	=====
IM0761-226		I76/SH52 Interchange	04/02/20	3.00	1050.00	1292.30	1129.00
		WEIGHTED AVERAGE FOR THE SECOND QUARTER		3.00	1050.00	1292.30	1129.00
		WEIGHTED AVERAGE FOR THE YEAR		3.00	1050.00	1292.30	1129.00

COLORADO DEPARTMENT OF TRANSPORTATION
ITEM UNIT COSTS BY PROJECTS -- 2020 COST DATA

10:58 Friday, October 2, 2020 173

PROJECT NUMBER	ITEM NUMBER/ PROJECT LOCATION	ITEM DESCRIPTION/ PROJECT LOCATION	DATE LET	UNIT/ QUANTITY	ENGR. EST.	AVERAGE BID	AWARDED BID
=====	603-30048	48 In SES		Each	=====	=====	=====
STR012A-050		CULVERT REPAIR I-25 AND US 35	01/30/20	1.00	1750.00	7000.00	7000.00
NHPP0091-044		SH 9 FRISCO MAIN ST TO IRON S	03/05/20	1.00	1000.00	1791.67	1700.00
		WEIGHTED AVERAGE FOR THE FIRST QUARTER		2.00	1375.00	3093.75	4350.00
		WEIGHTED AVERAGE FOR THE YEAR		2.00	1375.00	3093.75	4350.00
=====	603-31330	30 In Equiv Arch SES		Each	=====	=====	=====
STR2871-038		US 287 Passing Lanes Springfi	03/05/20	1.00	1000.00	979.22	1016.00
		WEIGHTED AVERAGE FOR THE FIRST QUARTER		1.00	1000.00	979.22	1016.00
		WEIGHTED AVERAGE FOR THE YEAR		1.00	1000.00	979.22	1016.00
=====	603-31354	54 In Equiv Arch SES		Each	=====	=====	=====
STR012A-050		CULVERT REPAIR I-25 AND US 35	01/30/20	1.00	200.00	8000.00	8000.00
		WEIGHTED AVERAGE FOR THE FIRST QUARTER		1.00	200.00	8000.00	8000.00
		WEIGHTED AVERAGE FOR THE YEAR		1.00	200.00	8000.00	8000.00
=====	603-31454	54 In Traversable Equiv Arch SES		Each	=====	=====	=====
STR012A-050		CULVERT REPAIR I-25 AND US 35	01/30/20	2.00	1200.00	10000.00	10000.00
		WEIGHTED AVERAGE FOR THE FIRST QUARTER		2.00	1200.00	10000.00	10000.00
		WEIGHTED AVERAGE FOR THE YEAR		2.00	1200.00	10000.00	10000.00
=====	603-33024	24 In Pipe Safety End Treat		Each	=====	=====	=====
STR012A-050		CULVERT REPAIR I-25 AND US 35	01/30/20	1.00	1000.00	2000.00	2000.00
		WEIGHTED AVERAGE FOR THE FIRST QUARTER		1.00	1000.00	2000.00	2000.00
		WEIGHTED AVERAGE FOR THE YEAR		1.00	1000.00	2000.00	2000.00

COLORADO DEPARTMENT OF TRANSPORTATION
 ITEM UNIT COSTS BY PROJECTS -- 2020 COST DATA

10:58 Friday, October 2, 2020 174

PROJECT NUMBER	ITEM NUMBER/ PROJECT LOCATION	ITEM DESCRIPTION/ PROJECT LOCATION	DATE LET	UNIT/ QUANTITY	ENGR. EST.	AVERAGE BID	AWARDED BID
=====	603-33048	48 In Pipe Safety End Treat		Each	=====	=====	=====
STR012A-050		CULVERT REPAIR I-25 AND US 35	01/30/20	2.00	1000.00	3200.00	3200.00
	WEIGHTED	AVERAGE FOR THE FIRST QUARTER		2.00	1000.00	3200.00	3200.00
		WEIGHTED AVERAGE FOR THE YEAR		2.00	1000.00	3200.00	3200.00
=====	603-50003	3 In Plastic Pipe		Lin Foot	=====	=====	=====
FSA0341-097		US 34 & MACGREGOR INTERSECTIO	01/09/20	160.00	20.00	30.00	30.00
	WEIGHTED	AVERAGE FOR THE FIRST QUARTER		160.00	20.00	30.00	30.00
		WEIGHTED AVERAGE FOR THE YEAR		160.00	20.00	30.00	30.00
=====	603-50004	4 In Plastic Pipe		Lin Foot	=====	=====	=====
NHPP0253-276		I-25 EXPRESS LANES SEGMENT 5	05/15/20	158.00	85.00	49.38	49.38
	WEIGHTED	AVERAGE FOR THE SECOND QUARTER		158.00	85.00	49.38	49.38
		WEIGHTED AVERAGE FOR THE YEAR		158.00	85.00	49.38	49.38
=====	603-50012	12 In Plastic Pipe		Lin Foot	=====	=====	=====
IM0761-226		I76/SH52 Interchange	04/02/20	10.00	100.00	207.76	155.01
	WEIGHTED	AVERAGE FOR THE SECOND QUARTER		10.00	100.00	207.76	155.01
		WEIGHTED AVERAGE FOR THE YEAR		10.00	100.00	207.76	155.01
=====	603-50015	15 In Plastic Pipe		Lin Foot	=====	=====	=====
NHPP0253-276		I-25 EXPRESS LANES SEGMENT 5	05/15/20	196.00	109.00	82.97	82.97
	WEIGHTED	AVERAGE FOR THE SECOND QUARTER		196.00	109.00	82.97	82.97
		WEIGHTED AVERAGE FOR THE YEAR		196.00	109.00	82.97	82.97
=====	603-50036	36 In Plastic Pipe		Lin Foot	=====	=====	=====
PWQM240-172		El Paso County, north Colorad	01/23/20	6.00	500.00	474.50	269.00
	WEIGHTED	AVERAGE FOR THE FIRST QUARTER		6.00	500.00	474.50	269.00
		WEIGHTED AVERAGE FOR THE YEAR		6.00	500.00	474.50	269.00

COLORADO DEPARTMENT OF TRANSPORTATION
ITEM UNIT COSTS BY PROJECTS -- 2020 COST DATA

10:58 Friday, October 2, 2020 175

PROJECT NUMBER	ITEM NUMBER/ PROJECT LOCATION	ITEM DESCRIPTION/ PROJECT LOCATION	DATE LET	UNIT/ QUANTITY	ENGR. EST.	AVERAGE BID	AWARDED BID
=====	603-70504	5x4 Ft CBC (Precast)		Lin Foot	=====		
NHPP145A-080		SH 145 Keystone-Placerville R	03/05/20	64.00	1000.00	1350.00	1350.00
	WEIGHTED AVERAGE FOR THE FIRST QUARTER			64.00	1000.00	1350.00	1350.00
	WEIGHTED AVERAGE FOR THE YEAR			64.00	1000.00	1350.00	1350.00
=====	603-70605	6x5 Ft CBC (Precast)		Lin Foot	=====		
NH050A-034		US50A PUEBLO WEST PURCELL INT	03/26/20	460.00	800.00	1093.67	875.00
	WEIGHTED AVERAGE FOR THE FIRST QUARTER			460.00	800.00	1093.67	875.00
	WEIGHTED AVERAGE FOR THE YEAR			460.00	800.00	1093.67	875.00
=====	603-70606	6x6 Ft CBC (Precast)		Lin Foot	=====		
CC0852-106 FBR0852-108		US-85 LOUVIERS TO MP 191.75 US-85 BETWEEN LOUVIERS AND MP	04/23/20	180.00	1400.00	948.56	781.00
	WEIGHTED AVERAGE FOR THE SECOND QUARTER			180.00	1400.00	948.56	781.00
	WEIGHTED AVERAGE FOR THE YEAR			180.00	1400.00	948.56	781.00
=====	603-70607	6x7 Ft CBC (Precast)		Lin Foot	=====		
CC0852-106 FBR0852-108		US-85 LOUVIERS TO MP 191.75 US-85 BETWEEN LOUVIERS AND MP	04/23/20	144.00	1800.00	1039.72	918.50
	WEIGHTED AVERAGE FOR THE SECOND QUARTER			144.00	1800.00	1039.72	918.50
	WEIGHTED AVERAGE FOR THE YEAR			144.00	1800.00	1039.72	918.50
=====	603-71006	10x6 Ft CBC (Precast)		Lin Foot	=====		
CC0852-106 FBR0852-108		US-85 LOUVIERS TO MP 191.75 US-85 BETWEEN LOUVIERS AND MP	04/23/20	179.00	2300.00	1319.48	1320.00
	WEIGHTED AVERAGE FOR THE SECOND QUARTER			179.00	2300.00	1319.48	1320.00
	WEIGHTED AVERAGE FOR THE YEAR			179.00	2300.00	1319.48	1320.00

COLORADO DEPARTMENT OF TRANSPORTATION
ITEM UNIT COSTS BY PROJECTS -- 2020 COST DATA

10:58 Friday, October 2, 2020 176

PROJECT NUMBER	ITEM NUMBER/ PROJECT LOCATION	ITEM DESCRIPTION/ PROJECT LOCATION	DATE LET	UNIT/ QUANTITY	ENGR. EST.	AVERAGE BID	AWARDED BID
=====	603-71408	14x8 Ft CBC (Precast)		Lin Foot	=====		
CC0852-106		US-85 LOUVIERS TO MP 191.75	04/23/20	132.00	2800.00	2331.78	2640.00
FBR0852-108		US-85 BETWEEN LOUVIERS AND MP					
		WEIGHTED AVERAGE FOR THE SECOND QUARTER		132.00	2800.00	2331.78	2640.00
		WEIGHTED AVERAGE FOR THE YEAR		132.00	2800.00	2331.78	2640.00
=====	603-72100	CBC Wingwall (Precast)		Each	=====		
NH050A-034		US50A PUEBLO WEST PURCELL INT	03/26/20	2.00	6500.00	16116.73	16000.00
		WEIGHTED AVERAGE FOR THE FIRST QUARTER		2.00	6500.00	16116.73	16000.00
		WEIGHTED AVERAGE FOR THE YEAR		2.00	6500.00	16116.73	16000.00
=====	604-00305	Inlet Ty C (5 Ft)		Each	=====		
PWQM240-172		El Paso County, north Colorad	01/23/20	1.00	6000.00	5536.00	4672.00
NHPP0091-044		SH 9 FRISCO MAIN ST TO IRON S	03/05/20	3.00	5000.00	4858.33	6400.00
NH050A-034		US50A PUEBLO WEST PURCELL INT	03/26/20	3.00	4500.00	4902.79	5700.00
		WEIGHTED AVERAGE FOR THE FIRST QUARTER		7.00	4928.57	4927.54	5853.14
IM0761-226		I76/SH52 Interchange	04/02/20	2.00	5000.00	4550.77	5713.00
SFTY2254-091		225 Ramp Improvements	04/09/20	1.00	5000.00	5780.00	7360.00
CC0852-106		US-85 LOUVIERS TO MP 191.75	04/23/20	1.00	4000.00	4583.19	2216.50
FBR0852-108		US-85 BETWEEN LOUVIERS AND MP					
		WEIGHTED AVERAGE FOR THE SECOND QUARTER		4.00	4750.00	4664.01	5250.63
		WEIGHTED AVERAGE FOR THE YEAR		11.00	4863.64	4820.34	5634.05
=====	604-00310	Inlet Ty C (10 Ft)		Each	=====		
PWQM240-172		El Paso County, north Colorad	01/23/20	11.00	7500.00	8848.50	6697.00
		WEIGHTED AVERAGE FOR THE FIRST QUARTER		11.00	7500.00	8848.50	6697.00
		WEIGHTED AVERAGE FOR THE YEAR		11.00	7500.00	8848.50	6697.00

COLORADO DEPARTMENT OF TRANSPORTATION
ITEM UNIT COSTS BY PROJECTS -- 2020 COST DATA

10:58 Friday, October 2, 2020 177

PROJECT NUMBER	ITEM NUMBER/ PROJECT LOCATION	ITEM DESCRIPTION/ PROJECT LOCATION	DATE LET	UNIT/ QUANTITY	ENGR. EST.	AVERAGE BID	AWARDED BID
=====	604-00315	Inlet Ty C (15 Ft)		Each	=====	=====	=====
PWQM240-172		El Paso County, north Colorad	01/23/20	3.00	10500.00	11343.50	8687.00
	WEIGHTED AVERAGE FOR THE FIRST QUARTER			3.00	10500.00	11343.50	8687.00
	WEIGHTED AVERAGE FOR THE YEAR			3.00	10500.00	11343.50	8687.00
=====	604-00350	Inlet Ty C (Spec)		Each	=====	=====	=====
NH050A-035		US 50A Pueblo Regional Pond	05/28/20	2.00	3500.00	10058.50	10000.00
NH050A-037		US 50A Pueblo Regional Pond					
	WEIGHTED AVERAGE FOR THE SECOND QUARTER			2.00	3500.00	10058.50	10000.00
	WEIGHTED AVERAGE FOR THE YEAR			2.00	3500.00	10058.50	10000.00
=====	604-00505	Inlet Ty D (5 Ft)		Each	=====	=====	=====
FSA0341-097		US 34 & MACGREGOR INTERSECTIO	01/09/20	1.00	5000.00	5800.00	5800.00
PWQM240-172		El Paso County, north Colorad	01/23/20	1.00	6500.00	6560.50	5921.00
	WEIGHTED AVERAGE FOR THE FIRST QUARTER			2.00	5750.00	6307.00	5860.50
IM0761-226		I76/SH52 Interchange	04/02/20	2.00	7000.00	5435.64	10015.00
CC0852-106		US-85 LOUVIERS TO MP 191.75	04/23/20	1.00	5400.00	5897.04	3300.00
FBR0852-108		US-85 BETWEEN LOUVIERS AND MP					
	WEIGHTED AVERAGE FOR THE SECOND QUARTER			3.00	6466.67	5603.42	7776.67
	WEIGHTED AVERAGE FOR THE YEAR			5.00	6180.00	5687.85	7010.20
=====	604-00506	Inlet Ty D (Spec) (5 Ft)		Each	=====	=====	=====
NH050A-034		US50A PUEBLO WEST PURCELL INT	03/26/20	12.00	7000.00	7918.75	8000.00
	WEIGHTED AVERAGE FOR THE FIRST QUARTER			12.00	7000.00	7918.75	8000.00
	WEIGHTED AVERAGE FOR THE YEAR			12.00	7000.00	7918.75	8000.00

COLORADO DEPARTMENT OF TRANSPORTATION
ITEM UNIT COSTS BY PROJECTS -- 2020 COST DATA

10:58 Friday, October 2, 2020 178

PROJECT NUMBER	ITEM NUMBER/ PROJECT LOCATION	ITEM DESCRIPTION/ PROJECT LOCATION	DATE LET	UNIT/ QUANTITY	ENGR. EST.	AVERAGE BID	AWARDED BID
=====	604-00510	Inlet Ty D (10 Ft)		Each	=====	=====	=====
PWQM240-172		El Paso County, north Colorad	01/23/20	12.00	8500.00	9930.00	7860.00
NHPP145A-080		SH 145 Keystone-Placerville R	03/05/20	1.00	6000.00	8250.00	8250.00
		WEIGHTED AVERAGE FOR THE FIRST QUARTER		13.00	8307.69	9862.80	7890.00
		WEIGHTED AVERAGE FOR THE YEAR		13.00	8307.69	9862.80	7890.00
=====	604-00511	Inlet Ty D (Spec) (10 Ft)		Each	=====	=====	=====
PWQM240-172		El Paso County, north Colorad	01/23/20	2.00	25000.00	50431.50	24863.00
NHPP0091-044		SH 9 FRISCO MAIN ST TO IRON S	03/05/20	3.00	7000.00	9863.33	13100.00
		WEIGHTED AVERAGE FOR THE FIRST QUARTER		5.00	14200.00	22345.85	17805.20
		WEIGHTED AVERAGE FOR THE YEAR		5.00	14200.00	22345.85	17805.20
=====	604-00515	Inlet Ty D (15 Ft)		Each	=====	=====	=====
PWQM240-172		El Paso County, north Colorad	01/23/20	3.00	11500.00	13108.50	10217.00
		WEIGHTED AVERAGE FOR THE FIRST QUARTER		3.00	11500.00	13108.50	10217.00
		WEIGHTED AVERAGE FOR THE YEAR		3.00	11500.00	13108.50	10217.00
=====	604-00520	Inlet Ty D (20 Ft)		Each	=====	=====	=====
PWQM240-172		El Paso County, north Colorad	01/23/20	2.00	13500.00	17870.00	12740.00
		WEIGHTED AVERAGE FOR THE FIRST QUARTER		2.00	13500.00	17870.00	12740.00
		WEIGHTED AVERAGE FOR THE YEAR		2.00	13500.00	17870.00	12740.00
=====	604-00610	Inlet Ty D (D) (10 Ft)		Each	=====	=====	=====
NHPP0253-276		I-25 EXPRESS LANES SEGMENT 5	05/15/20	1.00	9100.00	9015.61	9015.61
		WEIGHTED AVERAGE FOR THE SECOND QUARTER		1.00	9100.00	9015.61	9015.61
		WEIGHTED AVERAGE FOR THE YEAR		1.00	9100.00	9015.61	9015.61

PROJECT NUMBER	ITEM NUMBER/ PROJECT LOCATION	ITEM DESCRIPTION/ PROJECT LOCATION	DATE LET	UNIT/ QUANTITY	ENGR. EST.	AVERAGE BID	AWARDED BID
===== 604-13005		Inlet Ty 13 (5 Ft)		Each	=====	=====	=====
NH050A-034		US50A PUEBLO WEST PURCELL INT	03/26/20	1.00	4800.00	4771.28	5800.00
		WEIGHTED AVERAGE FOR THE FIRST QUARTER		1.00	4800.00	4771.28	5800.00
IM0761-226		I76/SH52 Interchange	04/02/20	1.00	5000.00	4874.60	5751.00
FSA1602-159		US 160 AND SH 17 INTERSECTION	04/30/20	3.00	3500.00	5931.67	3430.00
		WEIGHTED AVERAGE FOR THE SECOND QUARTER		4.00	3875.00	5469.20	4010.25
		WEIGHTED AVERAGE FOR THE YEAR		5.00	4060.00	5236.56	4368.20
===== 604-13015		Inlet Ty 13 (15 Ft)		Each	=====	=====	=====
NH050A-034		US50A PUEBLO WEST PURCELL INT	03/26/20	1.00	7000.00	7930.62	12500.00
		WEIGHTED AVERAGE FOR THE FIRST QUARTER		1.00	7000.00	7930.62	12500.00
		WEIGHTED AVERAGE FOR THE YEAR		1.00	7000.00	7930.62	12500.00
===== 604-16005		Inlet Ty 16 (5 Ft)		Each	=====	=====	=====
IM0761-226		I76/SH52 Interchange	04/02/20	1.00	6000.00	6260.06	5422.00
FSA1602-159		US 160 AND SH 17 INTERSECTION	04/30/20	2.00	4500.00	6178.67	3760.00
		WEIGHTED AVERAGE FOR THE SECOND QUARTER		3.00	5000.00	6222.49	4314.00
		WEIGHTED AVERAGE FOR THE YEAR		3.00	5000.00	6222.49	4314.00
===== 604-16010		Inlet Ty 16 (10 Ft)		Each	=====	=====	=====
IM0761-226		I76/SH52 Interchange	04/02/20	1.00	7000.00	7142.93	6914.01
		WEIGHTED AVERAGE FOR THE SECOND QUARTER		1.00	7000.00	7142.93	6914.01
		WEIGHTED AVERAGE FOR THE YEAR		1.00	7000.00	7142.93	6914.01
===== 604-16050		Inlet Ty 16 (S) (Spec)		Each	=====	=====	=====
HPP 0501-067		US 50 AND SH 92 DELTA INTERSE	03/26/20	6.00	5000.00	3221.13	2889.00
		WEIGHTED AVERAGE FOR THE FIRST QUARTER		6.00	5000.00	3221.13	2889.00
		WEIGHTED AVERAGE FOR THE YEAR		6.00	5000.00	3221.13	2889.00

COLORADO DEPARTMENT OF TRANSPORTATION
 ITEM UNIT COSTS BY PROJECTS -- 2020 COST DATA

10:58 Friday, October 2, 2020 180

PROJECT NUMBER	ITEM NUMBER/ PROJECT LOCATION	ITEM DESCRIPTION/ PROJECT LOCATION	DATE LET	UNIT/ QUANTITY	ENGR. EST.	AVERAGE BID	AWARDED BID
===== 604-19105		Inlet Ty R L5 (5 Ft)		Each			
FSA0341-097		US 34 & MACGREGOR INTERSECTIO	01/09/20	1.00	6000.00	7250.00	7250.00
NHPP0091-044		SH 9 FRISCO MAIN ST TO IRON S	03/05/20	8.00	5000.00	9073.33	10600.00
NH050A-034		US50A PUEBLO WEST PURCELL INT	03/26/20	1.00	5000.00	6237.39	7000.00
HPP 0501-067		US 50 AND SH 92 DELTA INTERSE	03/26/20	1.00	5000.00	5795.75	4679.00
SHE 0703-461		I-70 and Kipling North Phase	03/26/20	1.00	3000.00	7284.00	8660.00
		WEIGHTED AVERAGE FOR THE FIRST QUARTER		12.00	4916.67	8073.02	9365.75
IM0761-226		I76/SH52 Interchange	04/02/20	3.00	5000.00	7462.23	7069.00
CC0852-106		US-85 LOUVIERS TO MP 191.75	04/23/20	33.00	4500.00	6616.40	5747.50
FBR0852-108		US-85 BETWEEN LOUVIERS AND MP					
		WEIGHTED AVERAGE FOR THE SECOND QUARTER		36.00	4541.67	6678.72	5857.63
		WEIGHTED AVERAGE FOR THE YEAR		48.00	4635.42	6850.33	6734.66
===== 604-19110		Inlet Ty R L5 (10 Ft)		Each			
PWQM240-172		El Paso County, north Colorad	01/23/20	1.00	10500.00	11609.50	10219.00
NHPP0091-044		SH 9 FRISCO MAIN ST TO IRON S	03/05/20	10.00	7000.00	11490.00	13300.00
		WEIGHTED AVERAGE FOR THE FIRST QUARTER		11.00	7318.18	11497.47	13019.91
IM0761-226		I76/SH52 Interchange	04/02/20	3.00	6500.00	8482.00	8974.69
CC0852-106		US-85 LOUVIERS TO MP 191.75	04/23/20	9.00	7000.00	7398.19	5775.00
FBR0852-108		US-85 BETWEEN LOUVIERS AND MP					
FSA1602-159		US 160 AND SH 17 INTERSECTION	04/30/20	1.00	6000.00	8671.67	7180.00
		WEIGHTED AVERAGE FOR THE SECOND QUARTER		13.00	6807.69	7675.07	6621.47
		WEIGHTED AVERAGE FOR THE YEAR		24.00	7041.67	8630.67	9554.09
===== 604-19115		Inlet Ty R L5 (15 Ft)		Each			
IM0761-226		I76/SH52 Interchange	04/02/20	1.00	9000.00	9942.52	12301.00
CC0852-106		US-85 LOUVIERS TO MP 191.75	04/23/20	2.00	7500.00	9678.15	6149.00

COLORADO DEPARTMENT OF TRANSPORTATION
 ITEM UNIT COSTS BY PROJECTS -- 2020 COST DATA

10:58 Friday, October 2, 2020 181

PROJECT NUMBER	ITEM NUMBER/ PROJECT LOCATION	ITEM DESCRIPTION/ PROJECT LOCATION	DATE LET	UNIT/ QUANTITY	ENGR. EST.	AVERAGE BID	AWARDED BID
===== 604-19115 FBR0852-108		Inlet Ty R L5 (15 Ft) US-85 BETWEEN LOUVIERS AND MP		Each =====			
	WEIGHTED AVERAGE FOR THE SECOND QUARTER			3.00	8000.00	9758.61	8199.67
	WEIGHTED AVERAGE FOR THE YEAR			3.00	8000.00	9758.61	8199.67
===== 604-19205 NH050A-034		Inlet Ty R L10 (5 Ft) US50A PUEBLO WEST PURCELL INT 03/26/20		Each =====			
	WEIGHTED AVERAGE FOR THE FIRST QUARTER			2.00	6500.00	8954.22	9500.00
	WEIGHTED AVERAGE FOR THE YEAR			2.00	6500.00	8954.22	9500.00
IM0761-226		I76/SH52 Interchange 04/02/20		3.00	6500.00	10025.53	10724.99
	WEIGHTED AVERAGE FOR THE SECOND QUARTER			3.00	6500.00	10025.53	10724.99
	WEIGHTED AVERAGE FOR THE YEAR			5.00	6500.00	9562.26	10234.99
===== 604-19210 PWQM240-172 NHPP0091-044 NH050A-034		Inlet Ty R L10 (10 Ft) El Paso County, north Colorad 01/23/20 SH 9 FRISCO MAIN ST TO IRON S 03/05/20 US50A PUEBLO WEST PURCELL INT 03/26/20		Each =====			
	WEIGHTED AVERAGE FOR THE FIRST QUARTER			3.00	10666.67	13166.13	14984.00
IM0761-226		I76/SH52 Interchange 04/02/20		1.00	7000.00	11514.56	13152.97
	WEIGHTED AVERAGE FOR THE SECOND QUARTER			1.00	7000.00	11514.56	13152.97
	WEIGHTED AVERAGE FOR THE YEAR			4.00	9750.00	12588.08	14526.24
===== 604-19305 NH050A-034		Inlet Ty R L15 (5 Ft) US50A PUEBLO WEST PURCELL INT 03/26/20		Each =====			
	WEIGHTED AVERAGE FOR THE FIRST QUARTER			1.00	12500.00	11588.62	10000.00
	WEIGHTED AVERAGE FOR THE YEAR			1.00	12500.00	11588.62	10000.00

COLORADO DEPARTMENT OF TRANSPORTATION
ITEM UNIT COSTS BY PROJECTS -- 2020 COST DATA

10:58 Friday, October 2, 2020 182

PROJECT NUMBER	ITEM NUMBER/ PROJECT LOCATION	ITEM DESCRIPTION/ PROJECT LOCATION	DATE LET	UNIT/ QUANTITY	ENGR. EST.	AVERAGE BID	AWARDED BID
===== 604-19310		Inlet Ty R L15 (10 Ft)		Each	=====	=====	=====
NH050A-034		US50A PUEBLO WEST PURCELL INT	03/26/20	1.00	15000.00	14617.11	16000.00
	WEIGHTED	AVERAGE FOR THE FIRST QUARTER		1.00	15000.00	14617.11	16000.00
		WEIGHTED AVERAGE FOR THE YEAR		1.00	15000.00	14617.11	16000.00
===== 604-19405		Inlet Ty R Spec (5 Ft)		Each	=====	=====	=====
FSA0341-097		US 34 & MACGREGOR INTERSECTIO	01/09/20	11.00	7000.00	7500.00	7500.00
HPP 0501-067		US 50 AND SH 92 DELTA INTERSE	03/26/20	1.00	8000.00	8677.40	7625.00
	WEIGHTED	AVERAGE FOR THE FIRST QUARTER		12.00	7083.33	7681.14	7510.42
CC0852-106		US-85 LOUVIERS TO MP 191.75	04/23/20	30.00	5000.00	7784.50	8717.50
FBR0852-108		US-85 BETWEEN LOUVIERS AND MP					
	WEIGHTED	AVERAGE FOR THE SECOND QUARTER		30.00	5000.00	7784.50	8717.50
		WEIGHTED AVERAGE FOR THE YEAR		42.00	5595.24	7779.18	8372.62
===== 604-19410		Inlet Ty R Spec (10 Ft)		Each	=====	=====	=====
CC0852-106		US-85 LOUVIERS TO MP 191.75	04/23/20	15.00	6000.00	8949.72	8800.00
FBR0852-108		US-85 BETWEEN LOUVIERS AND MP					
	WEIGHTED	AVERAGE FOR THE SECOND QUARTER		15.00	6000.00	8949.72	8800.00
		WEIGHTED AVERAGE FOR THE YEAR		15.00	6000.00	8949.72	8800.00
===== 604-19415		Inlet Ty R Spec (15 Ft)		Each	=====	=====	=====
CC0852-106		US-85 LOUVIERS TO MP 191.75	04/23/20	1.00	8000.00	12546.07	9130.00
FBR0852-108		US-85 BETWEEN LOUVIERS AND MP					
	WEIGHTED	AVERAGE FOR THE SECOND QUARTER		1.00	8000.00	12546.07	9130.00
		WEIGHTED AVERAGE FOR THE YEAR		1.00	8000.00	12546.07	9130.00

COLORADO DEPARTMENT OF TRANSPORTATION
ITEM UNIT COSTS BY PROJECTS -- 2020 COST DATA

10:58 Friday, October 2, 2020 183

PROJECT NUMBER	ITEM NUMBER/ PROJECT LOCATION	ITEM DESCRIPTION/ PROJECT LOCATION	DATE LET	UNIT/ QUANTITY	ENGR. EST.	AVERAGE BID	AWARDED BID
=====	604-19724	Inlet Spec (Trench) (24 Inch)		Lin Foot	=====		
FSA0341-097		US 34 & MACGREGOR INTERSECTIO	01/09/20	22.00	500.00	1800.00	1800.00
	WEIGHTED AVERAGE FOR THE FIRST QUARTER			22.00	500.00	1800.00	1800.00
	WEIGHTED AVERAGE FOR THE YEAR			22.00	500.00	1800.00	1800.00
=====	604-25000	Vane Gate Inlet Spec		Each	=====		
NH050A-034		US50A PUEBLO WEST PURCELL INT	03/26/20	2.00	8000.00	8800.56	5000.00
	WEIGHTED AVERAGE FOR THE FIRST QUARTER			2.00	8000.00	8800.56	5000.00
IM0761-226		I76/SH52 Interchange	04/02/20	2.00	6000.00	7330.08	8910.00
CC0852-106		US-85 LOUVIERS TO MP 191.75	04/23/20	2.00	10000.00	8818.90	6484.50
FBR0852-108		US-85 BETWEEN LOUVIERS AND MP					
	WEIGHTED AVERAGE FOR THE SECOND QUARTER			4.00	8000.00	8124.12	7697.25
	WEIGHTED AVERAGE FOR THE YEAR			6.00	8000.00	8359.40	6798.17
=====	604-25005	Vane Gate Inlet (5 Ft)		Each	=====		
SFTY2254-091		225 Ramp Improvements	04/09/20	1.00	5000.00	6900.00	7800.00
	WEIGHTED AVERAGE FOR THE SECOND QUARTER			1.00	5000.00	6900.00	7800.00
	WEIGHTED AVERAGE FOR THE YEAR			1.00	5000.00	6900.00	7800.00
=====	604-26005	Vane Gate Inlet (D) (5 Ft)		Each	=====		
NH050A-034		US50A PUEBLO WEST PURCELL INT	03/26/20	8.00	6000.00	7071.02	7500.00
	WEIGHTED AVERAGE FOR THE FIRST QUARTER			8.00	6000.00	7071.02	7500.00
	WEIGHTED AVERAGE FOR THE YEAR			8.00	6000.00	7071.02	7500.00
=====	604-26010	Vane Gate Inlet (D) (10 Ft)		Each	=====		
NH050A-034		US50A PUEBLO WEST PURCELL INT	03/26/20	2.00	8000.00	8349.50	10500.00
	WEIGHTED AVERAGE FOR THE FIRST QUARTER			2.00	8000.00	8349.50	10500.00
	WEIGHTED AVERAGE FOR THE YEAR			2.00	8000.00	8349.50	10500.00

COLORADO DEPARTMENT OF TRANSPORTATION
ITEM UNIT COSTS BY PROJECTS -- 2020 COST DATA

10:58 Friday, October 2, 2020 184

PROJECT NUMBER	ITEM NUMBER/ PROJECT LOCATION	ITEM DESCRIPTION/ PROJECT LOCATION	DATE LET	UNIT/ QUANTITY	ENGR. EST.	AVERAGE BID	AWARDED BID
=====	604-30000	MH Slab Base (Spec)		Each	=====		
NHPP0091-044		SH 9 FRISCO MAIN ST TO IRON S	03/05/20	10.00	5000.00	12426.67	11800.00
		WEIGHTED AVERAGE FOR THE FIRST QUARTER		10.00	5000.00	12426.67	11800.00
		WEIGHTED AVERAGE FOR THE YEAR		10.00	5000.00	12426.67	11800.00
=====	604-30005	MH Slab Base (5 Ft)		Each	=====		
FSA0341-097		US 34 & MACGREGOR INTERSECTIO	01/09/20	2.00	4500.00	13000.00	13000.00
HPP 0501-067		US 50 AND SH 92 DELTA INTERSE	03/26/20	1.00	4000.00	4205.28	2250.00
		WEIGHTED AVERAGE FOR THE FIRST QUARTER		3.00	4333.33	8602.64	9416.67
IM0761-226		I76/SH52 Interchange	04/02/20	2.00	4000.00	5812.06	5606.01
CC0852-106		US-85 LOUVIERS TO MP 191.75	04/23/20	1.00	5100.00	5922.60	4730.00
FBR0852-108		US-85 BETWEEN LOUVIERS AND MP					
FSA1602-159		US 160 AND SH 17 INTERSECTION	04/30/20	1.00	4500.00	6585.67	3890.00
NHPP0253-276		I-25 EXPRESS LANES SEGMENT 5	05/15/20	1.00	4500.00	4656.01	4656.01
		WEIGHTED AVERAGE FOR THE SECOND QUARTER		5.00	4420.00	5890.87	4897.61
		WEIGHTED AVERAGE FOR THE YEAR		8.00	4387.50	6252.44	6592.25
=====	604-30010	MH Slab Base (10 Ft)		Each	=====		
PWQM240-172		El Paso County, north Colorad	01/23/20	3.00	7500.00	10076.00	8152.00
NHPP0091-044		SH 9 FRISCO MAIN ST TO IRON S	03/05/20	7.00	6000.00	5733.33	7000.00
NH050A-034		US50A PUEBLO WEST PURCELL INT	03/26/20	10.00	7500.00	6216.99	8000.00
HPP 0501-067		US 50 AND SH 92 DELTA INTERSE	03/26/20	4.00	5000.00	5453.55	3050.00
		WEIGHTED AVERAGE FOR THE FIRST QUARTER		24.00	6645.83	6276.90	6902.33
IM0761-226		I76/SH52 Interchange	04/02/20	5.00	5500.00	5859.78	5973.00
CC0852-106		US-85 LOUVIERS TO MP 191.75	04/23/20	2.00	5000.00	6484.90	5280.00
FBR0852-108		US-85 BETWEEN LOUVIERS AND MP					
FSA1602-159		US 160 AND SH 17 INTERSECTION	04/30/20	1.00	6000.00	8017.33	4160.00

COLORADO DEPARTMENT OF TRANSPORTATION
ITEM UNIT COSTS BY PROJECTS -- 2020 COST DATA

10:58 Friday, October 2, 2020 185

PROJECT NUMBER	ITEM NUMBER/ PROJECT LOCATION	ITEM DESCRIPTION/ PROJECT LOCATION	DATE LET	UNIT/ QUANTITY	ENGR. EST.	AVERAGE BID	AWARDED BID
=====	604-30010	MH Slab Base (10 Ft)		Each =====			
NH050A-035		US 50A Pueblo Regional Pond	05/28/20	8.00	8500.00	6269.00	5000.00
NH050A-037		US 50A Pueblo Regional Pond					
	WEIGHTED AVERAGE FOR THE SECOND QUARTER			16.00	6968.75	6221.34	5286.56
	WEIGHTED AVERAGE FOR THE YEAR			40.00	6775.00	6248.76	6256.03
=====	604-30015	MH Slab Base (15 Ft)		Each =====			
PWQM240-172		El Paso County, north Colorad	01/23/20	14.00	9500.00	12010.50	11021.00
NH050A-034		US50A PUEBLO WEST PURCELL INT	03/26/20	4.00	8000.00	9142.65	10500.00
	WEIGHTED AVERAGE FOR THE FIRST QUARTER			18.00	9166.67	10480.98	10905.22
IM0761-226		I76/SH52 Interchange	04/02/20	1.00	6600.00	7435.50	5628.01
CC0852-106		US-85 LOUVIERS TO MP 191.75	04/23/20	2.00	7200.00	7976.34	6561.50
FBR0852-108		US-85 BETWEEN LOUVIERS AND MP					
NHPP0253-276		I-25 EXPRESS LANES SEGMENT 5	05/15/20	1.00	7500.00	8655.43	8655.43
	WEIGHTED AVERAGE FOR THE SECOND QUARTER			4.00	7125.00	7846.89	6851.61
	WEIGHTED AVERAGE FOR THE YEAR			22.00	8795.45	9728.38	10168.20
=====	604-30020	MH Slab Base (20 Ft)		Each =====			
PWQM240-172		El Paso County, north Colorad	01/23/20	5.00	12000.00	14603.00	13206.00
	WEIGHTED AVERAGE FOR THE FIRST QUARTER			5.00	12000.00	14603.00	13206.00
	WEIGHTED AVERAGE FOR THE YEAR			5.00	12000.00	14603.00	13206.00
=====	604-30025	MH Slab Base (25 Ft)		Each =====			
PWQM240-172		El Paso County, north Colorad	01/23/20	4.00	13500.00	18280.00	18560.00
	WEIGHTED AVERAGE FOR THE FIRST QUARTER			4.00	13500.00	18280.00	18560.00
	WEIGHTED AVERAGE FOR THE YEAR			4.00	13500.00	18280.00	18560.00
=====	604-30030	MH Slab Base (30 Ft)		Each =====			
PWQM240-172		El Paso County, north Colorad	01/23/20	1.00	20000.00	19601.50	17203.00
	WEIGHTED AVERAGE FOR THE FIRST QUARTER			1.00	20000.00	19601.50	17203.00
	WEIGHTED AVERAGE FOR THE YEAR			1.00	20000.00	19601.50	17203.00

COLORADO DEPARTMENT OF TRANSPORTATION
ITEM UNIT COSTS BY PROJECTS -- 2020 COST DATA

10:58 Friday, October 2, 2020 186

PROJECT NUMBER	ITEM NUMBER/ PROJECT LOCATION	ITEM DESCRIPTION/ PROJECT LOCATION	DATE LET	UNIT/ QUANTITY	ENGR. EST.	AVERAGE BID	AWARDED BID
=====	604-31010	MH Box Base (10 Ft)		Each	=====	=====	=====
PWQM240-172		El Paso County, north Colorad	01/23/20	5.00	8500.00	19401.50	17803.00
SHE 0703-461		I-70 and Kipling North Phase	03/26/20	1.00	10000.00	15167.80	9339.00
	WEIGHTED AVERAGE FOR THE FIRST QUARTER			6.00	8750.00	17990.27	16392.33
CC0852-106		US-85 LOUVIERS TO MP 191.75	04/23/20	4.00	10000.00	12786.36	9025.50
FBR0852-108		US-85 BETWEEN LOUVIERS AND MP					
	WEIGHTED AVERAGE FOR THE SECOND QUARTER			4.00	10000.00	12786.36	9025.50
	WEIGHTED AVERAGE FOR THE YEAR			10.00	9250.00	14447.18	13445.60
=====	604-31015	MH Box Base (15 Ft)		Each	=====	=====	=====
PWQM240-172		El Paso County, north Colorad	01/23/20	8.00	10500.00	20994.50	19989.00
NH050A-034		US50A PUEBLO WEST PURCELL INT	03/26/20	1.00	10000.00	15942.37	16000.00
	WEIGHTED AVERAGE FOR THE FIRST QUARTER			9.00	10444.44	19310.46	19545.78
	WEIGHTED AVERAGE FOR THE YEAR			9.00	10444.44	19310.46	19545.78
=====	604-31020	MH Box Base (20 Ft)		Each	=====	=====	=====
PWQM240-172		El Paso County, north Colorad	01/23/20	6.00	12500.00	25177.00	25354.00
	WEIGHTED AVERAGE FOR THE FIRST QUARTER			6.00	12500.00	25177.00	25354.00
	WEIGHTED AVERAGE FOR THE YEAR			6.00	12500.00	25177.00	25354.00
=====	604-31030	MH Box Base (30 Ft)		Each	=====	=====	=====
PWQM240-172		El Paso County, north Colorad	01/23/20	3.00	20000.00	29384.50	26769.00
	WEIGHTED AVERAGE FOR THE FIRST QUARTER			3.00	20000.00	29384.50	26769.00
	WEIGHTED AVERAGE FOR THE YEAR			3.00	20000.00	29384.50	26769.00
=====	604-39000	MH Spec		Each	=====	=====	=====
ITS0761-231		ITS FIBER AND CAMERAS ON I-76	02/06/20	1.00	18000.00	4073.20	2200.00
	WEIGHTED AVERAGE FOR THE FIRST QUARTER			1.00	18000.00	4073.20	2200.00
	WEIGHTED AVERAGE FOR THE YEAR			1.00	18000.00	4073.20	2200.00

COLORADO DEPARTMENT OF TRANSPORTATION
ITEM UNIT COSTS BY PROJECTS -- 2020 COST DATA

10:58 Friday, October 2, 2020 187

PROJECT NUMBER	ITEM NUMBER/ PROJECT LOCATION	ITEM DESCRIPTION/ PROJECT LOCATION	DATE LET	UNIT/ QUANTITY	ENGR. EST.	AVERAGE BID	AWARDED BID
=====	604-39050	MH (TMS)		Each	=====		
ITS0761-231		ITS FIBER AND CAMERAS ON I-76	02/06/20	13.00	7000.00	7225.00	7427.70
NH050A-034		US50A PUEBLO WEST PURCELL INT	03/26/20	1.00	5000.00	12513.22	13500.00
		WEIGHTED AVERAGE FOR THE FIRST QUARTER		14.00	6857.14	7804.53	7861.44
IM0761-226		I76/SH52 Interchange	04/02/20	3.00	7000.00	7152.44	6857.14
CC0852-106		US-85 LOUVIERS TO MP 191.75	04/23/20	7.00	20000.00	6485.41	6853.00
FBR0852-108		US-85 BETWEEN LOUVIERS AND MP					
NHPP0253-276		I-25 EXPRESS LANES SEGMENT 5	05/15/20	2.00	7300.00	7308.10	7308.10
ITS SW02-303		R1: US 285, SH 83 R2: SH 83,	05/28/20	3.00	9000.00	11416.08	7500.00
		WEIGHTED AVERAGE FOR THE SECOND QUARTER		15.00	13506.67	7438.74	7043.91
		WEIGHTED AVERAGE FOR THE YEAR		29.00	10296.55	7598.64	7438.58
=====	604-51012	12 In Slot Pipe Inlet		Lin Foot	=====		
HPP 0501-067		US 50 AND SH 92 DELTA INTERSE	03/26/20	100.00	50.00	304.18	290.00
		WEIGHTED AVERAGE FOR THE FIRST QUARTER		100.00	50.00	304.18	290.00
		WEIGHTED AVERAGE FOR THE YEAR		100.00	50.00	304.18	290.00
=====	604-51015	15 In Slot Pipe Inlet		Lin Foot	=====		
NHPP0702-359		I-70 No Name Tunnel Lighting	02/27/20	27.00	8900.00	707.85	400.00
		WEIGHTED AVERAGE FOR THE FIRST QUARTER		27.00	8900.00	707.85	400.00
		WEIGHTED AVERAGE FOR THE YEAR		27.00	8900.00	707.85	400.00
=====	605-00040	4 In PP Underdrain		Lin Foot	=====		
NHPP0091-044		SH 9 FRISCO MAIN ST TO IRON S	03/05/20	318.00	50.00	29.83	19.00
		WEIGHTED AVERAGE FOR THE FIRST QUARTER		318.00	50.00	29.83	19.00
		WEIGHTED AVERAGE FOR THE YEAR		318.00	50.00	29.83	19.00

COLORADO DEPARTMENT OF TRANSPORTATION
 ITEM UNIT COSTS BY PROJECTS -- 2020 COST DATA

10:58 Friday, October 2, 2020 188

PROJECT NUMBER	ITEM NUMBER/ PROJECT LOCATION	ITEM DESCRIPTION/ PROJECT LOCATION	DATE LET	UNIT/ QUANTITY	ENGR. EST.	AVERAGE BID	AWARDED BID
=====	605-00060	6 In PP Underdrain		Lin Foot	=====		
NH050A-034		US50A PUEBLO WEST PURCELL INT	03/26/20	208.00	40.00	45.99	52.00
		WEIGHTED AVERAGE FOR THE FIRST QUARTER		208.00	40.00	45.99	52.00
		WEIGHTED AVERAGE FOR THE YEAR		208.00	40.00	45.99	52.00
=====	605-17000	Vert Drain Wick		Lin Foot	=====		
NH050A-034		US50A PUEBLO WEST PURCELL INT	03/26/20	254,536.00	1.15	0.77	0.73
		WEIGHTED AVERAGE FOR THE FIRST QUARTER		254,536.00	1.15	0.77	0.73
		WEIGHTED AVERAGE FOR THE YEAR		254,536.00	1.15	0.77	0.73
=====	605-83001	Geocomp Drain (w/o Pipe)		Sq Yard	=====		
CC0852-106 FBR0852-108		US-85 LOUVIERS TO MP 191.75 US-85 BETWEEN LOUVIERS AND MP	04/23/20	216.00	40.00	21.35	30.20
		WEIGHTED AVERAGE FOR THE SECOND QUARTER		216.00	40.00	21.35	30.20
		WEIGHTED AVERAGE FOR THE YEAR		216.00	40.00	21.35	30.20
=====	605-83500	Geocomp Underdrain		Lin Foot	=====		
CC0852-106 FBR0852-108		US-85 LOUVIERS TO MP 191.75 US-85 BETWEEN LOUVIERS AND MP	04/23/20	866.00	45.00	49.67	13.20
		WEIGHTED AVERAGE FOR THE SECOND QUARTER		866.00	45.00	49.67	13.20
		WEIGHTED AVERAGE FOR THE YEAR		866.00	45.00	49.67	13.20
=====	606-00301	Gdrail Ty 3 (6-3)		Lin Foot	=====		
FSA0253-262 STR131A-038 STR141A-044 STA059A-036		I-25 SB BOTTLENECK I-76 TO I- SH 131 MP 51.95-55.73, ROUTT SH 141 AND SH 145, FROM SLICK SH 59 SEIBERT TO COPE	01/09/20 01/16/20 01/30/20 02/06/20	575.00 5,000.00 5,800.00 1,000.00	45.00 40.00 27.00 35.00	32.10 22.50 23.09 31.00	30.00 21.00 21.00 28.00

PROJECT NUMBER	ITEM NUMBER/ PROJECT LOCATION	ITEM DESCRIPTION/ PROJECT LOCATION	DATE LET	UNIT/ QUANTITY	ENGR. EST.	AVERAGE BID	AWARDED BID
===== 606-00301 Gdrail Ty 3 (6-3) Lin Foot =====							
STR116A-001		SH 116 A Surface Treatment Pr	02/13/20	1,100.00	32.00	33.90	37.00
STR0101-027		SH 10 Overlay La Junta West	02/27/20	650.00	32.00	34.14	37.00
NHPP0171-105		SH 17 MP 84.5 to US 285 & SH	03/05/20	864.00	40.00	30.71	32.88
C0641-106		SH 64 Meeker West Rural Resur	03/05/20	2,472.00	50.00	30.40	32.50
NHPP145A-080		SH 145 Keystone-Placerville R	03/05/20	50.00	10950.00	60.00	60.00
BR025A-046		K-18-U ON I-25 AT MP112 BRIDG	03/05/20	100.00	30.00	73.05	62.01
SHE 0703-461		I-70 and Kipling North Phase	03/26/20	290.00	45.00	29.50	32.00
WEIGHTED AVERAGE FOR THE FIRST QUARTER				17,901.00	66.77	26.29	25.92
=====							
STR092A-030		SH92 MP 31.748-48.5, DELTA AND	04/02/20	5,350.00	30.00	27.65	24.50
STR0341-101		SH 34 North of Grandby Resurf	04/02/20	3,246.00	40.00	41.99	38.60
CC0852-106		US-85 LOUVIERS TO MP 191.75	04/23/20	3,125.00	45.00	25.09	22.00
FBR0852-108		US-85 BETWEEN LOUVIERS AND MP					
ITSSW01-719		FY 20 ITS CAPITAL REPLACEMENT	06/11/20	1,287.50	70.00	42.00	45.00
WEIGHTED AVERAGE FOR THE SECOND QUARTER				13,008.50	40.06	30.75	29.45
WEIGHTED AVERAGE FOR THE YEAR				30,909.50	55.53	28.39	27.41
=====							
===== 606-00302 Gdrail Ty 3 (31 In MGS) Lin Foot =====							
NHPP0343-041		I-76 & US 34 FT. MORGAN AREA	01/09/20	22,924.00	32.00	21.35	22.00
BR0343-040		US 34 REPUBLICAN RIVER BRIDGE	01/16/20	388.00	40.00	36.21	31.00
FBR0343-043		US 34 D-28-P STRUCTURE REPLAC					
NH 0503-093		US50 WEST OF TEXAS CREEK MP 2	01/23/20	21,232.00	22.00	39.96	36.91
STA0703-443		I-70 EJMT TUNNELS PAVING	02/06/20	256.00	60.00	71.75	74.00
STA069A-033		SH69 MP 58.7 TO 71.58	02/13/20	6,887.50	25.00	29.45	32.00
NH0242-085		US 24 M.P. 291.38 to M.P. 296	02/27/20	3,087.50	32.00	28.70	27.35
NHPP0091-044		SH 9 FRISCO MAIN ST TO IRON S	03/05/20	363.00	50.00	54.33	55.00
NH050A-034		US50A PUEBLO WEST PURCELL INT	03/26/20	7,663.00	24.00	22.09	22.30
WEIGHTED AVERAGE FOR THE FIRST QUARTER				62,801.00	27.14	26.92	28.90
=====							
NHPP1602-169		US 160 WC TUNNEL EAST RESURFA	04/02/20	7,557.00	42.00	60.14	46.02
IM0761-226		I76/SH52 Interchange	04/02/20	587.50	25.00	31.92	30.69
IM0252-473		I-25 CABLE BARRIER PHASE IV	04/09/20	2,069.00	30.00	29.45	28.89
SFTY2254-091		225 Ramp Improvements	04/09/20	1,935.00	50.00	29.50	29.00
FSA1602-159		US 160 AND SH 17 INTERSECTION	04/30/20	12.50	50.00	134.67	147.00
FBR0343-042		US 34 D-27-G STRUCTURE REPLAC	05/07/20	525.00	40.00	34.95	31.00
WEIGHTED AVERAGE FOR THE SECOND QUARTER				12,686.00	40.40	48.06	39.40
WEIGHTED AVERAGE FOR THE YEAR				75,487.00	29.37	30.42	30.66

COLORADO DEPARTMENT OF TRANSPORTATION
 ITEM UNIT COSTS BY PROJECTS -- 2020 COST DATA

10:58 Friday, October 2, 2020 190

PROJECT NUMBER	ITEM NUMBER/ PROJECT LOCATION	ITEM DESCRIPTION/ PROJECT LOCATION	DATE LET	UNIT/ QUANTITY	ENGR. EST.	AVERAGE BID	AWARDED BID
=====	606-00710	Gd rail Ty 7 (Sty CA)		Lin Foot	=====		
NHPP4701-134		C-470 NOISE WALL WEST OF LUCE	02/06/20	400.00	130.00	134.00	140.00
	WEIGHTED AVERAGE FOR THE FIRST QUARTER			400.00	130.00	134.00	140.00
	WEIGHTED AVERAGE FOR THE YEAR			400.00	130.00	134.00	140.00
=====	606-00900	Gd rail (Spec)		Lin Foot	=====		
NHPP4701-134		C-470 NOISE WALL WEST OF LUCE	02/06/20	575.00	250.00	145.00	150.00
	WEIGHTED AVERAGE FOR THE FIRST QUARTER			575.00	250.00	145.00	150.00
IM0761-226		I76/SH52 Interchange	04/02/20	490.00	300.00	511.49	375.00
	WEIGHTED AVERAGE FOR THE SECOND QUARTER			490.00	300.00	511.49	375.00
	WEIGHTED AVERAGE FOR THE YEAR			1,065.00	273.00	344.37	253.52
=====	606-00910	Guardrail Type 9 (Style CA)		Lin Foot	=====		
NHPP 0852-116		US85:HAMPDEN TO FLORIDA-RESUR	02/06/20	24.00	150.00	210.00	120.00
NHPP0091-044		SH 9 FRISCO MAIN ST TO IRON S	03/05/20	1,487.00	130.00	164.67	150.00
NH050A-034		US50A PUEBLO WEST PURCELL INT	03/26/20	1,542.00	125.00	118.35	100.40
	WEIGHTED AVERAGE FOR THE FIRST QUARTER			3,053.00	127.63	130.88	124.71
	WEIGHTED AVERAGE FOR THE YEAR			3,053.00	127.63	130.88	124.71
=====	606-00920	Guardrail Type 9 (Style CC)		Lin Foot	=====		
NH050A-034		US50A PUEBLO WEST PURCELL INT	03/26/20	271.00	125.00	122.73	100.40
	WEIGHTED AVERAGE FOR THE FIRST QUARTER			271.00	125.00	122.73	100.40
SFTY2254-091		225 Ramp Improvements	04/09/20	1,128.00	250.00	146.25	92.50
	WEIGHTED AVERAGE FOR THE SECOND QUARTER			1,128.00	250.00	146.25	92.50
	WEIGHTED AVERAGE FOR THE YEAR			1,399.00	225.79	134.72	94.03

COLORADO DEPARTMENT OF TRANSPORTATION
 ITEM UNIT COSTS BY PROJECTS -- 2020 COST DATA

10:58 Friday, October 2, 2020 191

PROJECT NUMBER	ITEM NUMBER/ PROJECT LOCATION	ITEM DESCRIPTION/ PROJECT LOCATION	DATE LET	UNIT/ QUANTITY	ENGR. EST.	AVERAGE BID	AWARDED BID
=====	606-01320	End Anchor Ty 3B		Each	=====	=====	=====
STR092A-030		SH92 MP 31.748-48.5, DELTA AND	04/02/20	2.00	2000.00	2662.50	2775.00
		WEIGHTED AVERAGE FOR THE SECOND QUARTER		2.00	2000.00	2662.50	2775.00
		WEIGHTED AVERAGE FOR THE YEAR		2.00	2000.00	2662.50	2775.00
=====	606-01340	End Anchor Ty 3D		Each	=====	=====	=====
FSA0253-262		I-25 SB BOTTLENECK I-76 TO I-	01/09/20	1.00	1350.00	1434.58	1320.00
NHPP0343-041		I-76 & US 34 FT. MORGAN AREA	01/09/20	24.00	1500.00	1416.67	2370.00
NH 0503-093		US50 WEST OF TEXAS CREEK MP 2	01/23/20	1.00	1500.00	2221.27	2442.54
NH0242-085		US 24 M.P. 291.38 to M.P. 296	02/27/20	2.00	1520.00	1324.43	915.00
BR025A-046		K-18-U ON I-25 AT MP112 BRIDG	03/05/20	1.00	1500.00	2887.59	3128.61
NHPP0091-044		SH 9 FRISCO MAIN ST TO IRON S	03/05/20	2.00	1500.00	2196.67	2100.00
NH050A-034		US50A PUEBLO WEST PURCELL INT	03/26/20	9.00	1600.00	1659.87	1700.00
SHE 0703-461		I-70 and Kipling North Phase	03/26/20	1.00	2200.00	1372.60	1260.00
		WEIGHTED AVERAGE FOR THE FIRST QUARTER		41.00	1536.34	1609.59	2106.37
IM0761-226		I76/SH52 Interchange	04/02/20	4.00	1000.00	1073.48	1054.70
IM0252-473		I-25 CABLE BARRIER PHASE IV	04/09/20	3.00	1500.00	1683.34	1666.67
SFTY2254-091		225 Ramp Improvements	04/09/20	2.00	1750.00	1375.00	1350.00
CC0852-106		US-85 LOUVIERS TO MP 191.75	04/23/20	5.00	2100.00	1429.13	1094.50
FBR0852-108		US-85 BETWEEN LOUVIERS AND MP					
FSA1602-159		US 160 AND SH 17 INTERSECTION	04/30/20	1.00	3000.00	3094.67	2750.00
		WEIGHTED AVERAGE FOR THE SECOND QUARTER		15.00	1700.00	1384.03	1342.75
		WEIGHTED AVERAGE FOR THE YEAR		56.00	1580.18	1537.66	1901.83
=====	606-01370	Transition Ty 3G		Each	=====	=====	=====
NHPP0343-041		I-76 & US 34 FT. MORGAN AREA	01/09/20	36.00	2500.00	2308.00	2619.00
BR0343-040		US 34 REPUBLICAN RIVER BRIDGE	01/16/20	8.00	2500.00	2628.06	2300.00
FBR0343-043		US 34 D-28-P STRUCTURE REPLAC					
NH 0503-093		US50 WEST OF TEXAS CREEK MP 2	01/23/20	7.00	2100.00	4048.31	3596.61
STA0703-443		I-70 EJMT TUNNELS PAVING	02/06/20	1.00	4000.00	7175.02	7400.03
STA059A-036		SH 59 SEIBERT TO COPE	02/06/20	16.00	2500.00	2400.00	2200.00
STA069A-033		SH69 MP 58.7 TO 71.58	02/13/20	11.00	2500.00	2393.97	2600.00

PROJECT NUMBER	ITEM NUMBER/ PROJECT LOCATION	ITEM DESCRIPTION/ PROJECT LOCATION	DATE LET	UNIT/ QUANTITY	ENGR. EST.	AVERAGE BID	AWARDED BID
=====	606-01370	Transition Ty 3G		Each =====			
STR0101-027		SH 10 Overlay La Junta West	02/27/20	8.00	2000.00	2630.59	2700.00
NHPP0091-044		SH 9 FRISCO MAIN ST TO IRON S	03/05/20	2.00	5000.00	4633.33	4500.00
NH050A-034		US50A PUEBLO WEST PURCELL INT	03/26/20	4.00	2500.00	2443.52	2500.00
		WEIGHTED AVERAGE FOR THE FIRST QUARTER		93.00	2496.77	2586.91	2684.52
NHPP1602-169		US 160 WC TUNNEL EAST RESURFA	04/02/20	9.00	2800.00	5449.85	3790.01
IM0761-226		I76/SH52 Interchange	04/02/20	5.00	2000.00	2502.04	2453.90
STR0341-101		SH 34 North of Grandby Resurf	04/02/20	4.00	3500.00	3243.10	2880.00
IM0252-473		I-25 CABLE BARRIER PHASE IV	04/09/20	5.00	3500.00	2836.11	2772.22
SFTY2254-091		225 Ramp Improvements	04/09/20	1.00	3500.00	3430.00	3360.00
CC0852-106		US-85 LOUVIERS TO MP 191.75	04/23/20	2.00	4500.00	2628.20	2629.00
FBR0852-108		US-85 BETWEEN LOUVIERS AND MP					
FBR0343-042		US 34 D-27-G STRUCTURE REPLAC	05/07/20	4.00	2500.00	3049.10	2900.00
		WEIGHTED AVERAGE FOR THE SECOND QUARTER		30.00	2973.33	3335.54	3065.96
		WEIGHTED AVERAGE FOR THE YEAR		123.00	2613.01	2834.13	2777.55
=====	606-01371	Transition Ty 3G (Spec)		Each =====			
NH 0503-093		US50 WEST OF TEXAS CREEK MP 2	01/23/20	1.00	2500.00	4504.58	4509.15
		WEIGHTED AVERAGE FOR THE FIRST QUARTER		1.00	2500.00	4504.58	4509.15
		WEIGHTED AVERAGE FOR THE YEAR		1.00	2500.00	4504.58	4509.15
=====	606-01380	Transition Ty 3H		Each =====			
NHPP0343-041		I-76 & US 34 FT. MORGAN AREA	01/09/20	20.00	2000.00	867.00	924.00
STA0703-443		I-70 EJMT TUNNELS PAVING	02/06/20	1.00	2000.00	5161.41	5322.82
NHPP0091-044		SH 9 FRISCO MAIN ST TO IRON S	03/05/20	2.00	2000.00	2443.33	2400.00
NH050A-034		US50A PUEBLO WEST PURCELL INT	03/26/20	2.00	1500.00	1503.26	1525.00
SHE 0703-461		I-70 and Kipling North Phase	03/26/20	1.00	2500.00	1296.00	1210.00
		WEIGHTED AVERAGE FOR THE FIRST QUARTER		26.00	1980.77	1208.26	1263.95
IM0761-226		I76/SH52 Interchange	04/02/20	4.00	1300.00	1113.37	1086.50

COLORADO DEPARTMENT OF TRANSPORTATION
 ITEM UNIT COSTS BY PROJECTS -- 2020 COST DATA

10:58 Friday, October 2, 2020 193

PROJECT NUMBER	ITEM NUMBER/ PROJECT LOCATION	ITEM DESCRIPTION/ PROJECT LOCATION	DATE LET	UNIT/ QUANTITY	ENGR. EST.	AVERAGE BID	AWARDED BID
=====	606-01380	Transition Ty 3H		Each =====			
STR0341-101	SH 34 North of Grandby Resurf	SH 34 North of Grandby Resurf	04/02/20	4.00	2300.00	2078.73	1530.00
IM0252-473	I-25 CABLE BARRIER PHASE IV	I-25 CABLE BARRIER PHASE IV	04/09/20	4.00	1900.00	2077.78	2055.56
SFTY2254-091	225 Ramp Improvements	225 Ramp Improvements	04/09/20	1.00	3500.00	1400.00	1400.00
CC0852-106	US-85 LOUVIERS TO MP 191.75	US-85 LOUVIERS TO MP 191.75	04/23/20	2.00	2000.00	1328.69	1072.50
FBR0852-108	US-85 BETWEEN LOUVIERS AND MP	US-85 BETWEEN LOUVIERS AND MP					
	WEIGHTED AVERAGE FOR THE SECOND QUARTER			15.00	1966.67	1501.65	1482.22
	WEIGHTED AVERAGE FOR THE YEAR			41.00	1975.61	1337.42	1343.81
=====	606-01385	Transition Ty 3J		Each =====			
NHPP0343-041	I-76 & US 34 FT. MORGAN AREA	I-76 & US 34 FT. MORGAN AREA	01/09/20	3.00	2000.00	2105.33	2370.00
BR0343-040	US 34 REPUBLICAN RIVER BRIDGE	US 34 REPUBLICAN RIVER BRIDGE	01/16/20	1.00	1775.00	2072.56	1500.00
FBR0343-043	US 34 D-28-P STRUCTURE REPLAC	US 34 D-28-P STRUCTURE REPLAC					
STA069A-033	SH69 MP 58.7 TO 71.58	SH69 MP 58.7 TO 71.58	02/13/20	6.00	1600.00	953.24	1000.00
STR0101-027	SH 10 Overlay La Junta West	SH 10 Overlay La Junta West	02/27/20	6.00	2000.00	1377.13	2200.00
NH0242-085	US 24 M.P. 291.38 to M.P. 296	US 24 M.P. 291.38 to M.P. 296	02/27/20	1.00	2250.00	2585.52	3540.00
C0641-106	SH 64 Meeker West Rural Resur	SH 64 Meeker West Rural Resur	03/05/20	2.00	1700.00	1287.50	1325.00
	WEIGHTED AVERAGE FOR THE FIRST QUARTER			19.00	1843.42	1548.41	1789.47
NHPP1602-169	US 160 WC TUNNEL EAST RESURFA	US 160 WC TUNNEL EAST RESURFA	04/02/20	2.00	2200.00	3414.71	1732.58
STR0341-101	SH 34 North of Grandby Resurf	SH 34 North of Grandby Resurf	04/02/20	2.00	3000.00	3050.60	2955.00
FBR0343-042	US 34 D-27-G STRUCTURE REPLAC	US 34 D-27-G STRUCTURE REPLAC	05/07/20	1.00	2000.00	1982.91	2100.00
ITSSW01-719	FY 20 ITS CAPITAL REPLACEMENT	FY 20 ITS CAPITAL REPLACEMENT	06/11/20	2.00	2750.00	1245.50	1380.00
	WEIGHTED AVERAGE FOR THE SECOND QUARTER			7.00	2557.14	2508.19	2033.59
	WEIGHTED AVERAGE FOR THE YEAR			26.00	2035.58	1876.44	1855.20
=====	606-01390	End Anchor Ty 3K		Each =====			
NHPP0343-041	I-76 & US 34 FT. MORGAN AREA	I-76 & US 34 FT. MORGAN AREA	01/09/20	1.00	2000.00	2443.00	4280.00
BR0343-040	US 34 REPUBLICAN RIVER BRIDGE	US 34 REPUBLICAN RIVER BRIDGE	01/16/20	1.00	2070.00	1796.21	1500.00
FBR0343-043	US 34 D-28-P STRUCTURE REPLAC	US 34 D-28-P STRUCTURE REPLAC					
STA069A-033	SH69 MP 58.7 TO 71.58	SH69 MP 58.7 TO 71.58	02/13/20	6.00	1850.00	1464.41	1515.00
STR0101-027	SH 10 Overlay La Junta West	SH 10 Overlay La Junta West	02/27/20	6.00	2500.00	2328.45	3800.00
NH0242-085	US 24 M.P. 291.38 to M.P. 296	US 24 M.P. 291.38 to M.P. 296	02/27/20	1.00	2060.00	3141.95	1825.00
C0641-106	SH 64 Meeker West Rural Resur	SH 64 Meeker West Rural Resur	03/05/20	2.00	2000.00	1975.00	2030.00
	WEIGHTED AVERAGE FOR THE FIRST QUARTER			17.00	2131.18	2063.42	2562.06

PROJECT NUMBER	ITEM NUMBER/ PROJECT LOCATION	ITEM DESCRIPTION/ PROJECT LOCATION	DATE LET	UNIT/ QUANTITY	ENGR. EST.	AVERAGE BID	AWARDED BID
=====	606-01390	End Anchor Ty 3K		Each	=====	=====	=====
NHPP1602-169		US 160 WC TUNNEL EAST RESURFA	04/02/20	1.00	1800.00	3654.06	2382.29
STR0341-101		SH 34 North of Grandby Resurf	04/02/20	1.00	2500.00	2986.21	2365.00
FBR0343-042		US 34 D-27-G STRUCTURE REPLAC	05/07/20	1.00	2300.00	2114.77	2100.00
ITSSW01-719		FY 20 ITS CAPITAL REPLACEMENT	06/11/20	2.00	2100.00	1852.50	2000.00
		WEIGHTED AVERAGE FOR THE SECOND QUARTER		5.00	2160.00	2467.50	2169.46
		WEIGHTED AVERAGE FOR THE YEAR		22.00	2137.73	2185.86	2472.83
=====	606-01395	Transition Ty 3L		Each	=====	=====	=====
NHPP0171-105		SH 17 MP 84.5 to US 285 & SH	03/05/20	8.00	2000.00	1230.91	977.74
		WEIGHTED AVERAGE FOR THE FIRST QUARTER		8.00	2000.00	1230.91	977.74
		WEIGHTED AVERAGE FOR THE YEAR		8.00	2000.00	1230.91	977.74
=====	606-01400	Transition Type BR10M-GR3		Each	=====	=====	=====
FBR0343-042		US 34 D-27-G STRUCTURE REPLAC	05/07/20	4.00	3500.00	4524.86	3700.00
		WEIGHTED AVERAGE FOR THE SECOND QUARTER		4.00	3500.00	4524.86	3700.00
		WEIGHTED AVERAGE FOR THE YEAR		4.00	3500.00	4524.86	3700.00
=====	606-01460	Median Terminal		Each	=====	=====	=====
STA0703-443		I-70 EJMT TUNNELS PAVING	02/06/20	1.00	7000.00	18062.45	18629.89
NH050A-034		US50A PUEBLO WEST PURCELL INT	03/26/20	2.00	4500.00	8844.85	8910.00
		WEIGHTED AVERAGE FOR THE FIRST QUARTER		3.00	5333.33	9869.02	12149.96
NHPP1602-169		US 160 WC TUNNEL EAST RESURFA	04/02/20	8.00	9300.00	13248.46	8121.46
SFTY2254-091		225 Ramp Improvements	04/09/20	1.00	6000.00	10700.00	10400.00
		WEIGHTED AVERAGE FOR THE SECOND QUARTER		9.00	8933.33	13052.43	8374.63
		WEIGHTED AVERAGE FOR THE YEAR		12.00	8033.33	11750.13	9318.46

PROJECT NUMBER	ITEM NUMBER/ PROJECT LOCATION	ITEM DESCRIPTION/ PROJECT LOCATION	DATE LET	UNIT/ QUANTITY	ENGR. EST.	AVERAGE BID	AWARDED BID
===== 606-02003		End Anchor (Nonflared)		Each	=====		
FSA0253-262		I-25 SB BOTTLENECK I-76 TO I-	01/09/20	1.00	4000.00	3550.34	3250.00
NHPP0343-041		I-76 & US 34 FT. MORGAN AREA	01/09/20	23.00	3217.00	2921.33	3095.00
NH 0503-093		US50 WEST OF TEXAS CREEK MP 2	01/23/20	51.00	3000.00	4653.24	4306.48
STR141A-044		SH 141 AND SH 145, FROM SLICK	01/30/20	22.00	2500.00	4167.63	3500.00
STR116A-001		SH 116 A Surface Treatment Pr	02/13/20	16.00	2250.00	3428.29	4200.00
STA069A-033		SH69 MP 58.7 TO 71.58	02/13/20	4.00	2800.00	2927.57	3100.00
STR0101-027		SH 10 Overlay La Junta West	02/27/20	10.00	2500.00	3341.66	4100.00
NH0242-085		US 24 M.P. 291.38 to M.P. 296	02/27/20	3.00	3810.00	3733.09	3700.00
NHPP145A-080		SH 145 Keystone-Placerville R	03/05/20	2.00	12000.00	4800.00	4800.00
		WEIGHTED AVERAGE FOR THE FIRST QUARTER		132.00	2981.98	3875.90	3881.56
NHPP1602-169		US 160 WC TUNNEL EAST RESURFA	04/02/20	20.00	4000.00	5961.29	3627.58
IM0761-226		I76/SH52 Interchange	04/02/20	3.00	3000.00	3399.78	3317.80
IM0252-473		I-25 CABLE BARRIER PHASE IV	04/09/20	7.00	3500.00	3233.34	3166.67
FSA1602-159		US 160 AND SH 17 INTERSECTION	04/30/20	1.00	2000.00	8305.67	8890.00
ITSSW01-719		FY 20 ITS CAPITAL REPLACEMENT	06/11/20	6.00	6000.00	3380.00	3500.00
		WEIGHTED AVERAGE FOR THE SECOND QUARTER		37.00	4094.59	4907.42	3636.80
		WEIGHTED AVERAGE FOR THE YEAR		169.00	3225.57	4107.00	3827.97
===== 606-02005		End Anchor (Flared)		Each	=====		
NHPP0343-041		I-76 & US 34 FT. MORGAN AREA	01/09/20	20.00	2575.00	2535.67	2750.00
BR0343-040		US 34 REPUBLICAN RIVER BRIDGE	01/16/20	7.00	3250.00	3018.15	2900.00
FBR0343-043		US 34 D-28-P STRUCTURE REPLAC					
STR131A-038		SH 131 MP 51.95-55.73, ROUTT	01/16/20	12.00	3000.00	3150.00	3000.00
NH 0503-093		US50 WEST OF TEXAS CREEK MP 2	01/23/20	12.00	3000.00	4647.83	3995.65
NHPP4701-134		C-470 NOISE WALL WEST OF LUCE	02/06/20	1.00	2800.00	3250.00	2975.00
STA059A-036		SH 59 SEIBERT TO COPE	02/06/20	16.00	3000.00	2520.00	2240.00
STA069A-033		SH69 MP 58.7 TO 71.58	02/13/20	41.00	3600.00	2930.09	3000.00
C0641-106		SH 64 Meeker West Rural Resur	03/05/20	12.00	3000.00	4255.00	6200.00
NHPP0091-044		SH 9 FRISCO MAIN ST TO IRON S	03/05/20	2.00	4000.00	4476.67	4300.00
NH050A-034		US50A PUEBLO WEST PURCELL INT	03/26/20	10.00	3200.00	2443.52	2500.00
		WEIGHTED AVERAGE FOR THE FIRST QUARTER		133.00	3162.78	2975.38	3226.04
STR092A-030		SH92 MP 31.748-48.5, DELTA AND	04/02/20	27.00	3000.00	3507.50	3275.00

COLORADO DEPARTMENT OF TRANSPORTATION
 ITEM UNIT COSTS BY PROJECTS -- 2020 COST DATA

10:58 Friday, October 2, 2020 196

PROJECT NUMBER	ITEM NUMBER/ PROJECT LOCATION	ITEM DESCRIPTION/ PROJECT LOCATION	DATE LET	UNIT/ QUANTITY	ENGR. EST.	AVERAGE BID	AWARDED BID
=====	606-02005	End Anchor (Flared)		Each =====			
IM0761-226	I76/SH52 Interchange		04/02/20	2.00	3000.00	3654.58	3572.20
STR0341-101	SH 34 North of Grandby Resurf		04/02/20	21.00	4000.00	5242.47	4325.00
SFTY2254-091	225 Ramp Improvements		04/09/20	3.00	4000.00	3010.00	2920.00
CC0852-106	US-85 LOUVIERS TO MP 191.75		04/23/20	5.00	3500.00	2538.86	2469.78
FBR0852-108	US-85 BETWEEN LOUVIERS AND MP						
FBR0343-042	US 34 D-27-G STRUCTURE REPLAC		05/07/20	3.00	3250.00	3476.04	3400.00
ITSSW01-719	FY 20 ITS CAPITAL REPLACEMENT		06/11/20	6.00	5000.00	3395.50	3500.00
	WEIGHTED AVERAGE FOR THE SECOND QUARTER			67.00	3585.82	3945.78	3562.74
	WEIGHTED AVERAGE FOR THE YEAR			200.00	3304.50	3348.73	3338.83
=====	606-10300	Brdg Rail Ty 3		Lin Foot =====			
NHPP0171-105	SH 17 MP 84.5 to US 285 & SH		03/05/20	136.00	200.00	269.05	417.15
	WEIGHTED AVERAGE FOR THE FIRST QUARTER			136.00	200.00	269.05	417.15
	WEIGHTED AVERAGE FOR THE YEAR			136.00	200.00	269.05	417.15
=====	606-10405	Brdg Rail Ty 4 (Spec)		Lin Foot =====			
NHPP 0852-116	US85:HAMPDEN TO FLORIDA-RESUR		02/06/20	79.00	750.00	425.00	300.00
	WEIGHTED AVERAGE FOR THE FIRST QUARTER			79.00	750.00	425.00	300.00
	WEIGHTED AVERAGE FOR THE YEAR			79.00	750.00	425.00	300.00
=====	606-10700	Brdg Rail Ty 7		Lin Foot =====			
NHPP4701-134	C-470 NOISE WALL WEST OF LUCE		02/06/20	664.00	250.00	133.60	128.00
NH050A-034	US50A PUEBLO WEST PURCELL INT		03/26/20	587.00	100.00	119.21	148.00
SHE 0703-461	I-70 and Kipling North Phase		03/26/20	13.00	130.00	670.60	550.00
	WEIGHTED AVERAGE FOR THE FIRST QUARTER			1,264.00	179.11	129.56	141.63
	WEIGHTED AVERAGE FOR THE YEAR			1,264.00	179.11	129.56	141.63
=====	606-11010	Brdg Rail Ty 10R		Lin Foot =====			
NHPP0343-041	I-76 & US 34 FT. MORGAN AREA		01/09/20	5,118.00	185.00	156.90	157.00

COLORADO DEPARTMENT OF TRANSPORTATION
 ITEM UNIT COSTS BY PROJECTS -- 2020 COST DATA

10:58 Friday, October 2, 2020 197

PROJECT NUMBER	ITEM NUMBER/ PROJECT LOCATION	ITEM DESCRIPTION/ PROJECT LOCATION	DATE LET	UNIT/ QUANTITY	ENGR. EST.	AVERAGE BID	AWARDED BID
=====	606-11010	Brdg Rail Ty 10R		Lin Foot	=====	=====	=====
NH 0503-093		US50 WEST OF TEXAS CREEK MP 2	01/23/20	127.00	150.00	253.29	266.57
STA059A-036		SH 59 SEIBERT TO COPE	02/06/20	1,215.00	210.00	146.00	132.00
STR0101-027		SH 10 Overlay La Junta West	02/27/20	501.00	150.00	168.68	180.00
	WEIGHTED AVERAGE FOR THE FIRST QUARTER			6,961.00	186.21	157.70	156.29
	WEIGHTED AVERAGE FOR THE YEAR			6,961.00	186.21	157.70	156.29
=====	606-11030	Brdg Rail Ty 10M		Lin Foot	=====	=====	=====
BR0343-040		US 34 REPUBLICAN RIVER BRIDGE	01/16/20	648.00	180.00	172.62	165.00
FBR0343-043		US 34 D-28-P STRUCTURE REPLAC					
	WEIGHTED AVERAGE FOR THE FIRST QUARTER			648.00	180.00	172.62	165.00
IM0761-226		I76/SH52 Interchange	04/02/20	232.00	210.00	271.98	195.00
CC0852-106		US-85 LOUVIERS TO MP 191.75	04/23/20	380.00	220.00	215.25	112.04
FBR0852-108		US-85 BETWEEN LOUVIERS AND MP					
	WEIGHTED AVERAGE FOR THE SECOND QUARTER			612.00	216.21	235.00	143.49
	WEIGHTED AVERAGE FOR THE YEAR			1,260.00	197.59	206.64	154.55
=====	606-11032	Brdg Rail Ty 10M (Spec)		Lin Foot	=====	=====	=====
IM0761-226		I76/SH52 Interchange	04/02/20	231.00	220.00	308.73	225.00
	WEIGHTED AVERAGE FOR THE SECOND QUARTER			231.00	220.00	308.73	225.00
	WEIGHTED AVERAGE FOR THE YEAR			231.00	220.00	308.73	225.00
=====	606-11035	Brdg Rail Ty 10 MASH		Lin Foot	=====	=====	=====
FBR0343-042		US 34 D-27-G STRUCTURE REPLAC	05/07/20	250.00	250.00	259.21	205.00
	WEIGHTED AVERAGE FOR THE SECOND QUARTER			250.00	250.00	259.21	205.00
	WEIGHTED AVERAGE FOR THE YEAR			250.00	250.00	259.21	205.00
=====	606-20010	Tensioned Cable Barrier		Lin Foot	=====	=====	=====
NH050A-034		US50A PUEBLO WEST PURCELL INT	03/26/20	825.00	15.00	40.79	41.00
	WEIGHTED AVERAGE FOR THE FIRST QUARTER			825.00	15.00	40.79	41.00
	WEIGHTED AVERAGE FOR THE YEAR			825.00	15.00	40.79	41.00

COLORADO DEPARTMENT OF TRANSPORTATION
 ITEM UNIT COSTS BY PROJECTS -- 2020 COST DATA

10:58 Friday, October 2, 2020 198

PROJECT NUMBER	ITEM NUMBER/ PROJECT LOCATION	ITEM DESCRIPTION/ PROJECT LOCATION	DATE LET	UNIT/ QUANTITY	ENGR. EST.	AVERAGE BID	AWARDED BID
=====	606-20014	Tensioned Cable Barrier (TL-4)		Lin Foot	=====		
IM0252-473		I-25 CABLE BARRIER PHASE IV	04/09/20	19,943.00	25.00	18.59	17.78
		WEIGHTED AVERAGE FOR THE SECOND QUARTER		19,943.00	25.00	18.59	17.78
		WEIGHTED AVERAGE FOR THE YEAR		19,943.00	25.00	18.59	17.78
=====	606-21010	End Anchor (Tens Cab Bar)		Each	=====		
NH050A-034		US50A PUEBLO WEST PURCELL INT	03/26/20	3.00	5000.00	3242.41	3300.00
		WEIGHTED AVERAGE FOR THE FIRST QUARTER		3.00	5000.00	3242.41	3300.00
IM0252-473		I-25 CABLE BARRIER PHASE IV	04/09/20	6.00	8000.00	2972.22	2944.44
		WEIGHTED AVERAGE FOR THE SECOND QUARTER		6.00	8000.00	2972.22	2944.44
		WEIGHTED AVERAGE FOR THE YEAR		9.00	7000.00	3152.35	3062.96
=====	606-99999	Gdrail Ty 7 (Precast)		Lin Foot	=====		
NH 0503-093		US50 WEST OF TEXAS CREEK MP 2	01/23/20	300.00	90.00	124.83	109.65
		WEIGHTED AVERAGE FOR THE FIRST QUARTER		300.00	90.00	124.83	109.65
		WEIGHTED AVERAGE FOR THE YEAR		300.00	90.00	124.83	109.65
=====	607-00005	End Post		Each	=====		
BR0343-040 FBR0343-043		US 34 REPUBLICAN RIVER BRIDGE	01/16/20	1.00	200.00	302.34	300.00
		US 34 D-28-P STRUCTURE REPLAC					
		WEIGHTED AVERAGE FOR THE FIRST QUARTER		1.00	200.00	302.34	300.00
CC0852-106		US-85 LOUVIERS TO MP 191.75	04/23/20	12.00	200.00	212.43	192.50

COLORADO DEPARTMENT OF TRANSPORTATION
 ITEM UNIT COSTS BY PROJECTS -- 2020 COST DATA

10:58 Friday, October 2, 2020 199

PROJECT NUMBER	ITEM NUMBER/ PROJECT LOCATION	ITEM DESCRIPTION/ PROJECT LOCATION	DATE LET	UNIT/ QUANTITY	ENGR. EST.	AVERAGE BID	AWARDED BID
=====	607-00005	End Post		Each	=====		
FBR0852-108		US-85 BETWEEN LOUVIERS AND MP					
FSA1602-159		US 160 AND SH 17 INTERSECTION	04/30/20	2.00	350.00	601.67	322.00
	WEIGHTED	AVERAGE FOR THE SECOND QUARTER		14.00	221.43	235.33	211.00
		WEIGHTED AVERAGE FOR THE YEAR		15.00	220.00	239.05	216.93
=====	607-00010	Corner and Line Br Post		Each	=====		
CC0852-106		US-85 LOUVIERS TO MP 191.75	04/23/20	18.00	300.00	254.73	258.50
FBR0852-108		US-85 BETWEEN LOUVIERS AND MP					
	WEIGHTED	AVERAGE FOR THE SECOND QUARTER		18.00	300.00	254.73	258.50
		WEIGHTED AVERAGE FOR THE YEAR		18.00	300.00	254.73	258.50
=====	607-00015	End Post (Spec)		Each	=====		
CC0852-106		US-85 LOUVIERS TO MP 191.75	04/23/20	20.00	400.00	395.31	357.50
FBR0852-108		US-85 BETWEEN LOUVIERS AND MP					
	WEIGHTED	AVERAGE FOR THE SECOND QUARTER		20.00	400.00	395.31	357.50
		WEIGHTED AVERAGE FOR THE YEAR		20.00	400.00	395.31	357.50
=====	607-00020	Corner and Line Br Post (Spec)		Each	=====		
CC0852-106		US-85 LOUVIERS TO MP 191.75	04/23/20	37.00	150.00	558.11	467.50
FBR0852-108		US-85 BETWEEN LOUVIERS AND MP					
	WEIGHTED	AVERAGE FOR THE SECOND QUARTER		37.00	150.00	558.11	467.50
		WEIGHTED AVERAGE FOR THE YEAR		37.00	150.00	558.11	467.50
=====	607-01000	Fence BW MP		Lin Foot	=====		
BR0343-040		US 34 REPUBLICAN RIVER BRIDGE	01/16/20	265.00	5.00	4.50	4.00
FBR0343-043		US 34 D-28-P STRUCTURE REPLAC					
	WEIGHTED	AVERAGE FOR THE FIRST QUARTER		265.00	5.00	4.50	4.00

COLORADO DEPARTMENT OF TRANSPORTATION
 ITEM UNIT COSTS BY PROJECTS -- 2020 COST DATA

10:58 Friday, October 2, 2020 200

PROJECT NUMBER	ITEM NUMBER/ PROJECT LOCATION	ITEM DESCRIPTION/ PROJECT LOCATION	DATE LET	UNIT/ QUANTITY	ENGR. EST.	AVERAGE BID	AWARDED BID
=====	607-01000	Fence BW MP		Lin Foot	=====		
STA340A-021		SH340 MP 6-6.76 MESA COUNTY	04/02/20	700.00	4.00	7.50	10.00
CC0852-106		US-85 LOUVIERS TO MP 191.75	04/23/20	7,260.00	3.00	3.03	2.81
FBR0852-108		US-85 BETWEEN LOUVIERS AND MP					
		WEIGHTED AVERAGE FOR THE SECOND QUARTER		7,960.00	3.09	3.18	3.44
		WEIGHTED AVERAGE FOR THE YEAR		8,225.00	3.15	3.22	3.46
=====	607-01010	Fence BW MP (Spec)		Lin Foot	=====		
CC0852-106		US-85 LOUVIERS TO MP 191.75	04/23/20	240.00	7.00	4.32	3.85
FBR0852-108		US-85 BETWEEN LOUVIERS AND MP					
		WEIGHTED AVERAGE FOR THE SECOND QUARTER		240.00	7.00	4.32	3.85
		WEIGHTED AVERAGE FOR THE YEAR		240.00	7.00	4.32	3.85
=====	607-01100	Fence BW TWP		Lin Foot	=====		
STA340A-021		SH340 MP 6-6.76 MESA COUNTY	04/02/20	80.00	10.00	15.80	30.00
		WEIGHTED AVERAGE FOR THE SECOND QUARTER		80.00	10.00	15.80	30.00
		WEIGHTED AVERAGE FOR THE YEAR		80.00	10.00	15.80	30.00
=====	607-11200	Fence CW MP		Lin Foot	=====		
NH050A-034		US50A PUEBLO WEST PURCELL INT	03/26/20	8,470.00	5.00	4.54	5.45
		WEIGHTED AVERAGE FOR THE FIRST QUARTER		8,470.00	5.00	4.54	5.45
FSA1602-159		US 160 AND SH 17 INTERSECTION	04/30/20	298.00	10.00	30.33	13.00
		WEIGHTED AVERAGE FOR THE SECOND QUARTER		298.00	10.00	30.33	13.00
		WEIGHTED AVERAGE FOR THE YEAR		8,768.00	5.17	4.88	5.71

COLORADO DEPARTMENT OF TRANSPORTATION
ITEM UNIT COSTS BY PROJECTS -- 2020 COST DATA

10:58 Friday, October 2, 2020 201

PROJECT NUMBER	ITEM NUMBER/ PROJECT LOCATION	ITEM DESCRIPTION/ PROJECT LOCATION	DATE LET	UNIT/ QUANTITY	ENGR. EST.	AVERAGE BID	AWARDED BID
=====	607-11350	Fence Deer		Lin Foot	=====		
CC0852-106		US-85 LOUVIERS TO MP 191.75	04/23/20	9,740.00	9.00	11.55	10.18
FBR0852-108		US-85 BETWEEN LOUVIERS AND MP					
		WEIGHTED AVERAGE FOR THE SECOND QUARTER		9,740.00	9.00	11.55	10.18
		WEIGHTED AVERAGE FOR THE YEAR		9,740.00	9.00	11.55	10.18
=====	607-11455	Fence Wood		Lin Foot	=====		
STA340A-021		SH340 MP 6-6.76 MESA COUNTY	04/02/20	24.00	40.00	65.52	150.00
		WEIGHTED AVERAGE FOR THE SECOND QUARTER		24.00	40.00	65.52	150.00
		WEIGHTED AVERAGE FOR THE YEAR		24.00	40.00	65.52	150.00
=====	607-11525	Fence (Plastic)		Lin Foot	=====		
NHPP0253-265		I-25 AT ERIE PARKWAY ON AND O	01/09/20	50.00	5.00	10.48	3.00
FSA0341-097		US 34 & MACGREGOR INTERSECTIO	01/09/20	1,400.00	5.00	5.00	5.00
NHPP0343-041		I-76 & US 34 FT. MORGAN AREA	01/09/20	140.00	4.00	6.66	5.50
NH 0503-093		US50 WEST OF TEXAS CREEK MP 2	01/23/20	1,500.00	5.00	4.13	5.25
PWQM240-172		El Paso County, north Colorad	01/23/20	8,347.00	6.00	1.75	1.50
NHPP 0852-116		US85:HAMPDEN TO FLORIDA-RESUR	02/06/20	100.00	4.00	8.50	7.00
ITS0761-231		ITS FIBER AND CAMERAS ON I-76	02/06/20	1,200.00	10.00	4.55	4.20
NHPP4701-134		C-470 NOISE WALL WEST OF LUCE	02/06/20	9,825.00	7.00	2.82	2.40
STA069A-033		SH69 MP 58.7 TO 71.58	02/13/20	1,110.00	4.00	3.34	4.00
NHPP0702-359		I-70 No Name Tunnel Lighting	02/27/20	2,742.00	3.50	4.70	5.25
C0402-094		US 40 GRAND COUNTY SIGNAL REP	02/27/20	500.00	5.00	3.00	5.00
NHPP0171-105		SH 17 MP 84.5 to US 285 & SH	03/05/20	500.00	10.00	5.17	10.00
NHPP145A-080		SH 145 Keystone-Placerville R	03/05/20	75.00	3.00	2.85	2.85
STRR300-249		Grand and Jackson Counties AD	03/05/20	500.00	7.00	4.83	0.50
CC080-037		VARIOUS ADA RAMP ALONG NORTH	03/05/20	500.00	10.00	2.88	0.50
NHPP0091-044		SH 9 FRISCO MAIN ST TO IRON S	03/05/20	300.00	10.00	8.30	5.00
NH050A-034		US50A PUEBLO WEST PURCELL INT	03/26/20	3,157.00	5.00	3.36	3.20
HPP 0501-067		US 50 AND SH 92 DELTA INTERSE	03/26/20	1,000.00	5.00	3.70	3.25
SHE 0703-461		I-70 and Kipling North Phase	03/26/20	210.00	4.00	5.40	6.00
		WEIGHTED AVERAGE FOR THE FIRST QUARTER		33,156.00	6.08	3.26	3.04
NHPP1602-169		US 160 WC TUNNEL EAST RESURFA	04/02/20	200.00	4.00	3.88	2.85

PROJECT NUMBER	ITEM NUMBER/ PROJECT LOCATION	ITEM DESCRIPTION/ PROJECT LOCATION	DATE LET	UNIT/ QUANTITY	ENGR. EST.	AVERAGE BID	AWARDED BID
===== 607-11525		Fence (Plastic)		Lin Foot	=====		
IM0761-226		I76/SH52 Interchange	04/02/20	1,298.00	3.00	3.87	5.19
STA340A-021		SH340 MP 6-6.76 MESA COUNTY	04/02/20	134.00	3.00	7.08	1.00
SHER100-339		WWD TRAFFIC CONTROL ENHANCEME	04/09/20	200.00	4.00	2.00	2.00
SFTY2254-091		225 Ramp Improvements	04/09/20	680.00	3.00	2.80	2.60
CC0852-106		US-85 LOUVIERS TO MP 191.75	04/23/20	7,409.00	4.00	2.86	3.03
FBR0852-108		US-85 BETWEEN LOUVIERS AND MP					
C1601-082		Hawkins Signal and Curb Ramps	04/30/20	300.00	5.00	6.53	4.60
FSA1602-159		US 160 AND SH 17 INTERSECTION	04/30/20	330.00	4.50	8.33	5.00
FBR0343-042		US 34 D-27-G STRUCTURE REPLAC	05/07/20	800.00	5.00	3.74	2.00
ITS SW02-304		ITS FIBER TO STATE BUILDINGS	05/14/20	1,000.00	10.00	4.79	2.00
NHPP0253-276		I-25 EXPRESS LANES SEGMENT 5	05/15/20	535.00	5.00	4.84	4.84
ITS SW02-303		R1: US 285, SH 83 R2: SH 83,	05/28/20	150.00	4.00	9.46	4.00
ITSSW01-719		FY 20 ITS CAPITAL REPLACEMENT	06/11/20	300.00	4.00	6.25	7.50
FSAR400-356		FY 20 SIGNAL POLE REPLACEMENT	06/11/20	75.00	4.00	5.67	5.00
		WEIGHTED AVERAGE FOR THE SECOND QUARTER		13,411.00	4.42	3.35	3.32
		WEIGHTED AVERAGE FOR THE YEAR		46,567.00	5.60	3.30	3.12
===== 607-11530		Fence (Spec)		Lin Foot	=====		
STA069A-033		SH69 MP 58.7 TO 71.58	02/13/20	832.00	5.00	7.87	10.00
		WEIGHTED AVERAGE FOR THE FIRST QUARTER		832.00	5.00	7.87	10.00
		WEIGHTED AVERAGE FOR THE YEAR		832.00	5.00	7.87	10.00
===== 607-11580		Fence (Temp)		Lin Foot	=====		
STA340A-021		SH340 MP 6-6.76 MESA COUNTY	04/02/20	165.00	5.50	10.50	20.00
SHE016A-043		SH 21 & 16 SIGNALS PROJECT	06/18/20	60.00	12.00	7.91	4.54
		WEIGHTED AVERAGE FOR THE SECOND QUARTER		225.00	7.23	9.52	15.88
		WEIGHTED AVERAGE FOR THE YEAR		225.00	7.23	9.52	15.88
===== 607-15000		Fence Conc (Sound)		Sq Foot	=====		
NHPP4701-134		C-470 NOISE WALL WEST OF LUCE	02/06/20	34,733.00	45.00	43.08	38.40
NHPP0091-044		SH 9 FRISCO MAIN ST TO IRON S	03/05/20	16,837.00	55.00	47.67	32.00
		WEIGHTED AVERAGE FOR THE FIRST QUARTER		51,570.00	48.26	44.11	36.31
		WEIGHTED AVERAGE FOR THE YEAR		51,570.00	48.26	44.11	36.31

COLORADO DEPARTMENT OF TRANSPORTATION
 ITEM UNIT COSTS BY PROJECTS -- 2020 COST DATA

10:58 Friday, October 2, 2020 203

PROJECT NUMBER	ITEM NUMBER/ PROJECT LOCATION	ITEM DESCRIPTION/ PROJECT LOCATION	DATE LET	UNIT/ QUANTITY	ENGR. EST.	AVERAGE BID	AWARDED BID
=====	607-52900	Line Post (CL)		Each	=====		
SHE 0703-461		I-70 and Kipling North Phase	03/26/20	40.00	95.00	88.40	85.00
		WEIGHTED AVERAGE FOR THE FIRST QUARTER		40.00	95.00	88.40	85.00
NH050A-035 NH050A-037		US 50A Pueblo Regional Pond US 50A Pueblo Regional Pond	05/28/20	125.00	85.00	13.43	5.00
		WEIGHTED AVERAGE FOR THE SECOND QUARTER		125.00	85.00	13.43	5.00
		WEIGHTED AVERAGE FOR THE YEAR		165.00	87.42	25.93	24.39
=====	607-52905	End Post (CL)		Each	=====		
NH050A-035 NH050A-037		US 50A Pueblo Regional Pond US 50A Pueblo Regional Pond	05/28/20	4.00	200.00	178.13	230.00
		WEIGHTED AVERAGE FOR THE SECOND QUARTER		4.00	200.00	178.13	230.00
		WEIGHTED AVERAGE FOR THE YEAR		4.00	200.00	178.13	230.00
=====	607-52910	Corner and Line Br Post (CL)		Each	=====		
SHE 0703-461		I-70 and Kipling North Phase	03/26/20	4.00	350.00	342.40	290.00
		WEIGHTED AVERAGE FOR THE FIRST QUARTER		4.00	350.00	342.40	290.00
NH050A-035 NH050A-037		US 50A Pueblo Regional Pond US 50A Pueblo Regional Pond	05/28/20	8.00	225.00	231.38	320.00
		WEIGHTED AVERAGE FOR THE SECOND QUARTER		8.00	225.00	231.38	320.00
		WEIGHTED AVERAGE FOR THE YEAR		12.00	266.67	257.81	310.00
=====	607-53005	Fence CL (Spec)		Lin Foot	=====		
NHPP 0852-116		US85:HAMPDEN TO FLORIDA-RESUR	02/06/20	236.00	270.00	94.50	110.00
		WEIGHTED AVERAGE FOR THE FIRST QUARTER		236.00	270.00	94.50	110.00
		WEIGHTED AVERAGE FOR THE YEAR		236.00	270.00	94.50	110.00

PROJECT NUMBER	ITEM NUMBER/ PROJECT LOCATION	ITEM DESCRIPTION/ PROJECT LOCATION	DATE LET	UNIT/ QUANTITY	ENGR. EST.	AVERAGE BID	AWARDED BID
=====	607-53137	Fence CL (Spec) (36 In)		Lin Foot	=====		
NH050A-034		US50A PUEBLO WEST PURCELL INT	03/26/20	1,177.00	65.00	46.64	47.20
		WEIGHTED AVERAGE FOR THE FIRST QUARTER		1,177.00	65.00	46.64	47.20
IM0761-226		I76/SH52 Interchange	04/02/20	209.00	60.00	64.05	58.46
		WEIGHTED AVERAGE FOR THE SECOND QUARTER		209.00	60.00	64.05	58.46
		WEIGHTED AVERAGE FOR THE YEAR		1,386.00	64.25	48.98	48.90
=====	607-53161	Fence CL (Spec) (60 In)		Lin Foot	=====		
CC0852-106 FBR0852-108		US-85 LOUVIERS TO MP 191.75 US-85 BETWEEN LOUVIERS AND MP	04/23/20	228.00	85.00	92.24	99.00
		WEIGHTED AVERAGE FOR THE SECOND QUARTER		228.00	85.00	92.24	99.00
		WEIGHTED AVERAGE FOR THE YEAR		228.00	85.00	92.24	99.00
=====	607-53172	Fence CL (72 In)		Lin Foot	=====		
SHE 0703-461		I-70 and Kipling North Phase	03/26/20	40.00	80.00	19.40	18.00
		WEIGHTED AVERAGE FOR THE FIRST QUARTER		40.00	80.00	19.40	18.00
NH050A-035 NH050A-037		US 50A Pueblo Regional Pond US 50A Pueblo Regional Pond	05/28/20	1,410.00	15.00	23.49	28.00
		WEIGHTED AVERAGE FOR THE SECOND QUARTER		1,410.00	15.00	23.49	28.00
		WEIGHTED AVERAGE FOR THE YEAR		1,450.00	16.79	23.42	27.72
=====	607-53191	Fence CL (Spec) (92 In)		Lin Foot	=====		
IM0761-226		I76/SH52 Interchange	04/02/20	214.00	80.00	132.91	132.98
		WEIGHTED AVERAGE FOR THE SECOND QUARTER		214.00	80.00	132.91	132.98
		WEIGHTED AVERAGE FOR THE YEAR		214.00	80.00	132.91	132.98

COLORADO DEPARTMENT OF TRANSPORTATION
 ITEM UNIT COSTS BY PROJECTS -- 2020 COST DATA

10:58 Friday, October 2, 2020 205

PROJECT NUMBER	ITEM NUMBER/ PROJECT LOCATION	ITEM DESCRIPTION/ PROJECT LOCATION	DATE LET	UNIT/ QUANTITY	ENGR. EST.	AVERAGE BID	AWARDED BID
=====	607-53220	Fence CL (120 In)		Lin Foot	=====		
NHPP0343-041		I-76 & US 34 FT. MORGAN AREA	01/09/20	1,840.00	60.00	162.17	203.00
	WEIGHTED AVERAGE FOR THE FIRST QUARTER			1,840.00	60.00	162.17	203.00
	WEIGHTED AVERAGE FOR THE YEAR			1,840.00	60.00	162.17	203.00
=====	607-55110	Safety Rail (Cable)		Lin Foot	=====		
NHPP0091-044		SH 9 FRISCO MAIN ST TO IRON S	03/05/20	10.00	10.00	266.67	260.00
	WEIGHTED AVERAGE FOR THE FIRST QUARTER			10.00	10.00	266.67	260.00
NHPP0253-276		I-25 EXPRESS LANES SEGMENT 5	05/15/20	507.00	37.00	37.96	37.96
	WEIGHTED AVERAGE FOR THE SECOND QUARTER			507.00	37.00	37.96	37.96
	WEIGHTED AVERAGE FOR THE YEAR			517.00	36.48	50.74	42.25
=====	607-60002	Game Ramp		Each	=====		
CC0852-106 FBR0852-108		US-85 LOUVIERS TO MP 191.75 US-85 BETWEEN LOUVIERS AND MP	04/23/20	6.00	8000.00	9216.00	6325.00
	WEIGHTED AVERAGE FOR THE SECOND QUARTER			6.00	8000.00	9216.00	6325.00
	WEIGHTED AVERAGE FOR THE YEAR			6.00	8000.00	9216.00	6325.00
=====	607-60116	16 Ft Gate		Each	=====		
NH050A-035 NH050A-037		US 50A Pueblo Regional Pond US 50A Pueblo Regional Pond	05/28/20	1.00	1000.00	1892.13	5000.00
	WEIGHTED AVERAGE FOR THE SECOND QUARTER			1.00	1000.00	1892.13	5000.00
	WEIGHTED AVERAGE FOR THE YEAR			1.00	1000.00	1892.13	5000.00
=====	607-60120	20 Ft Gate		Each	=====		
NH050A-035		US 50A Pueblo Regional Pond	05/28/20	2.00	600.00	2344.50	5500.00

PROJECT NUMBER	ITEM NUMBER/ PROJECT LOCATION	ITEM DESCRIPTION/ PROJECT LOCATION	DATE LET	UNIT/ QUANTITY	ENGR. EST.	AVERAGE BID	AWARDED BID
===== 607-60120	20 Ft Gate			Each			
NH050A-037	US 50A Pueblo Regional Pond						
	WEIGHTED AVERAGE FOR THE SECOND QUARTER			2.00	600.00	2344.50	5500.00
	WEIGHTED AVERAGE FOR THE YEAR			2.00	600.00	2344.50	5500.00
===== 608-00000	Conc Sidewalk			Sq Yard			
FSA0341-097	US 34 & MACGREGOR INTERSECTIO		01/09/20	468.00	75.00	90.00	90.00
NHPP0343-041	I-76 & US 34 FT. MORGAN AREA		01/09/20	931.00	80.00	81.47	102.00
BR0343-040	US 34 REPUBLICAN RIVER BRIDGE		01/16/20	424.00	75.00	75.80	95.00
FBR0343-043	US 34 D-28-P STRUCTURE REPLAC						
NHPP 0852-116	US85:HAMPDEN TO FLORIDA-RESUR		02/06/20	25.20	95.00	125.00	150.00
ITS0761-231	ITS FIBER AND CAMERAS ON I-76		02/06/20	2.00	120.00	381.40	250.00
C0402-094	US 40 GRAND COUNTY SIGNAL REP		02/27/20	110.00	100.00	88.00	100.00
STRR300-249	Grand and Jackson Counties AD		03/05/20	560.00	80.00	115.67	94.00
CC080-037	VARIOUS ADA RAMPS ALONG NORTH		03/05/20	76.00	100.00	98.76	82.00
NHPP0091-044	SH 9 FRISCO MAIN ST TO IRON S		03/05/20	2,232.00	85.00	83.50	85.00
HPP 0501-067	US 50 AND SH 92 DELTA INTERSE		03/26/20	463.00	50.00	83.05	78.20
	WEIGHTED AVERAGE FOR THE FIRST QUARTER			5,291.20	79.43	86.18	90.23
C1211-090	SH-121 & 29th Ave / SH-121 &		04/23/20	110.00	48.00	94.90	120.00
FSA1602-159	US 160 AND SH 17 INTERSECTION		04/30/20	350.00	65.00	95.00	110.00
ITS SW02-304	ITS FIBER TO STATE BUILDINGS		05/14/20	10.00	300.00	247.75	246.00
ITS SW02-303	R1: US 285, SH 83 R2: SH 83,		05/28/20	2.00	150.00	311.90	250.00
FSAR400-356	FY 20 SIGNAL POLE REPLACEMENT		06/11/20	52.00	180.00	151.67	140.00
SHE016A-043	SH 21 & 16 SIGNALS PROJECT		06/18/20	112.00	87.35	132.63	96.16
	WEIGHTED AVERAGE FOR THE SECOND QUARTER			636.00	79.36	112.78	114.32
	WEIGHTED AVERAGE FOR THE YEAR			5,927.20	79.42	89.38	92.82
===== 608-00005	Conc Sidewalk (Spec)			Sq Yard			
FSA0341-097	US 34 & MACGREGOR INTERSECTIO		01/09/20	63.00	125.00	150.00	150.00
	WEIGHTED AVERAGE FOR THE FIRST QUARTER			63.00	125.00	150.00	150.00
IM0761-226	I76/SH52 Interchange		04/02/20	188.00	145.00	109.37	85.33
	WEIGHTED AVERAGE FOR THE SECOND QUARTER			188.00	145.00	109.37	85.33
	WEIGHTED AVERAGE FOR THE YEAR			251.00	139.98	111.23	101.56

COLORADO DEPARTMENT OF TRANSPORTATION
ITEM UNIT COSTS BY PROJECTS -- 2020 COST DATA

10:58 Friday, October 2, 2020 207

PROJECT NUMBER	ITEM NUMBER/ PROJECT LOCATION	ITEM DESCRIPTION/ PROJECT LOCATION	DATE LET	UNIT/ QUANTITY	ENGR. EST.	AVERAGE BID	AWARDED BID
=====	608-00006	Conc Sidewalk (6 In)		Sq Yard	=====		
NHPP4701-134		C-470 NOISE WALL WEST OF LUCE	02/06/20	3,015.00	65.00	66.80	49.00
FSA2873-194		US 287 Longmont Intersection	02/13/20	102.00	90.00	108.77	72.00
NH0242-085		US 24 M.P. 291.38 to M.P. 296	02/27/20	17.00	71.00	203.59	131.50
NH050A-034		US50A PUEBLO WEST PURCELL INT	03/26/20	2,827.00	60.00	63.71	81.00
SHE 0703-461		I-70 and Kipling North Phase	03/26/20	275.00	80.00	90.60	97.00
		WEIGHTED AVERAGE FOR THE FIRST QUARTER		6,236.00	63.82	66.69	66.22
IM0761-226		I76/SH52 Interchange	04/02/20	3,015.00	65.00	58.34	46.64
C1601-082		Hawkins Signal and Curb Ramps	04/30/20	355.00	100.00	145.33	125.00
NHPPR100-303		LONG MAST ARM SIGNALS PROJECT	05/07/20	74.00	120.00	106.00	120.00
NHPP0402-098		US 40 CHIP SEAL MP 126 TO MP	05/14/20	12.00	70.00	145.00	200.00
		WEIGHTED AVERAGE FOR THE SECOND QUARTER		3,456.00	69.79	63.09	56.79
		WEIGHTED AVERAGE FOR THE YEAR		9,692.00	65.95	65.39	62.86
=====	608-00010	Conc Curb Ramp		Sq Yard	=====		
NHPP0253-265		I-25 AT ERIE PARKWAY ON AND O	01/09/20	283.00	200.00	206.67	207.00
FSA0341-097		US 34 & MACGREGOR INTERSECTIO	01/09/20	93.00	185.00	175.00	175.00
NHPP0343-041		I-76 & US 34 FT. MORGAN AREA	01/09/20	661.00	170.00	252.33	311.00
BR0343-040		US 34 REPUBLICAN RIVER BRIDGE	01/16/20	466.00	170.00	184.72	190.00
FBR0343-043		US 34 D-28-P STRUCTURE REPLAC					
NHPP 0852-116		US85:HAMPDEN TO FLORIDA-RESUR	02/06/20	108.30	200.00	225.00	250.00
FSA2873-194		US 287 Longmont Intersection	02/13/20	25.00	185.00	254.60	183.00
CO402-094		US 40 GRAND COUNTY SIGNAL REP	02/27/20	179.00	180.00	187.00	142.00
NH0242-085		US 24 M.P. 291.38 to M.P. 296	02/27/20	50.00	175.00	280.64	131.50
STRR300-249		Grand and Jackson Counties AD	03/05/20	2,123.00	170.00	200.33	192.00
CC080-037		VARIOUS ADA RAMPS ALONG NORTH	03/05/20	630.00	150.00	147.19	137.00
NHPP0091-044		SH 9 FRISCO MAIN ST TO IRON S	03/05/20	683.00	150.00	205.00	180.00
NH050A-034		US50A PUEBLO WEST PURCELL INT	03/26/20	741.00	160.00	158.14	200.00
HPP 0501-067		US 50 AND SH 92 DELTA INTERSE	03/26/20	187.00	150.00	121.60	107.75
SHE 0703-461		I-70 and Kipling North Phase	03/26/20	109.00	200.00	209.80	170.00
		WEIGHTED AVERAGE FOR THE FIRST QUARTER		6,338.30	167.07	187.39	195.06
IM0761-226		I76/SH52 Interchange	04/02/20	430.00	175.00	171.61	212.00

PROJECT NUMBER	ITEM NUMBER/ PROJECT LOCATION	ITEM DESCRIPTION/ PROJECT LOCATION	DATE LET	UNIT/ QUANTITY	ENGR. EST.	AVERAGE BID	AWARDED BID
===== 608-00010 Conc Curb Ramp Sq Yard =====							
C1211-090		SH-121 & 29th Ave / SH-121 &	04/23/20	166.00	160.00	202.07	235.00
C1601-082		Hawkins Signal and Curb Ramps	04/30/20	1,036.00	150.00	220.00	230.00
FSA1602-159		US 160 AND SH 17 INTERSECTION	04/30/20	203.00	150.00	268.00	377.00
NHPPR100-303		LONG MAST ARM SIGNALS PROJECT	05/07/20	265.00	180.00	215.33	245.00
NHPP0402-098		US 40 CHIP SEAL MP 126 TO MP	05/14/20	33.00	175.00	223.33	200.00
FSAR400-356		FY 20 SIGNAL POLE REPLACEMENT	06/11/20	58.00	185.00	244.00	318.00
SHE016A-043		SH 21 & 16 SIGNALS PROJECT	06/18/20	101.00	180.00	230.83	150.16
	WEIGHTED AVERAGE FOR THE SECOND QUARTER			2,292.00	161.45	206.46	240.02
	WEIGHTED AVERAGE FOR THE YEAR			8,630.30	165.58	192.45	207.00
===== 608-00015 Detectable Warnings Sq Foot =====							
NHPP0253-265		I-25 AT ERIE PARKWAY ON AND O	01/09/20	200.00	75.00	60.67	67.00
NHPP0343-041		I-76 & US 34 FT. MORGAN AREA	01/09/20	341.00	75.00	62.70	66.00
NH0242-085		US 24 M.P. 291.38 to M.P. 296	02/27/20	24.00	113.00	131.64	139.50
STRR300-249		Grand and Jackson Counties AD	03/05/20	734.00	100.00	113.33	128.00
CC080-037		VARIOUS ADA RAMP ALONG NORTH	03/05/20	44.00	75.00	46.50	47.00
HPP 0501-067		US 50 AND SH 92 DELTA INTERSE	03/26/20	48.00	60.00	44.40	44.80
	WEIGHTED AVERAGE FOR THE FIRST QUARTER			1,391.00	88.33	89.24	98.80
SHE016A-043		SH 21 & 16 SIGNALS PROJECT	06/18/20	16.00	80.00	96.10	115.50
	WEIGHTED AVERAGE FOR THE SECOND QUARTER			16.00	80.00	96.10	115.50
	WEIGHTED AVERAGE FOR THE YEAR			1,407.00	88.24	89.37	98.99
===== 608-00018 Curb Ramp (Temp Parallel) (Single) Each =====							
NHPP0091-044		SH 9 FRISCO MAIN ST TO IRON S	03/05/20	4.00	1000.00	2720.00	1500.00
	WEIGHTED AVERAGE FOR THE FIRST QUARTER			4.00	1000.00	2720.00	1500.00
NHPP0402-098		US 40 CHIP SEAL MP 126 TO MP	05/14/20	1.00	1500.00	1090.00	1975.00
	WEIGHTED AVERAGE FOR THE SECOND QUARTER			1.00	1500.00	1090.00	1975.00
	WEIGHTED AVERAGE FOR THE YEAR			5.00	1100.00	2394.00	1595.00

COLORADO DEPARTMENT OF TRANSPORTATION
 ITEM UNIT COSTS BY PROJECTS -- 2020 COST DATA

10:58 Friday, October 2, 2020 209

PROJECT NUMBER	ITEM NUMBER/ PROJECT LOCATION	ITEM DESCRIPTION/ PROJECT LOCATION	DATE LET	UNIT/ QUANTITY	ENGR. EST.	AVERAGE BID	AWARDED BID
=====	608-10000	Sidewalk Drain		Lin Foot	=====		
C1601-082		Hawkins Signal and Curb Ramps	04/30/20	6.00	350.00	281.67	250.00
	WEIGHTED AVERAGE FOR THE SECOND QUARTER			6.00	350.00	281.67	250.00
	WEIGHTED AVERAGE FOR THE YEAR			6.00	350.00	281.67	250.00
=====	608-10010	Sidewalk Drain		Each	=====		
FSA2873-194		US 287 Longmont Intersection	02/13/20	1.00	3500.00	3911.67	3620.00
	WEIGHTED AVERAGE FOR THE FIRST QUARTER			1.00	3500.00	3911.67	3620.00
	WEIGHTED AVERAGE FOR THE YEAR			1.00	3500.00	3911.67	3620.00
=====	609-20000	Curb Ty 2 B (Spec)		Lin Foot	=====		
FSA0341-097		US 34 & MACGREGOR INTERSECTIO	01/09/20	143.00	30.00	55.00	55.00
	WEIGHTED AVERAGE FOR THE FIRST QUARTER			143.00	30.00	55.00	55.00
	WEIGHTED AVERAGE FOR THE YEAR			143.00	30.00	55.00	55.00
=====	609-20010	Curb Ty 2 B		Lin Foot	=====		
NHPP0343-041		I-76 & US 34 FT. MORGAN AREA	01/09/20	326.00	51.00	30.37	37.00
BR0343-040		US 34 REPUBLICAN RIVER BRIDGE	01/16/20	40.00	57.00	47.71	65.00
FBR0343-043		US 34 D-28-P STRUCTURE REPLAC					
C0402-094		US 40 GRAND COUNTY SIGNAL REP	02/27/20	26.00	70.00	37.50	31.00
STRR300-249		Grand and Jackson Counties AD	03/05/20	46.00	35.00	63.00	39.00
NHPP0091-044		SH 9 FRISCO MAIN ST TO IRON S	03/05/20	395.00	40.00	31.67	24.00
	WEIGHTED AVERAGE FOR THE FIRST QUARTER			833.00	45.78	34.45	32.10
C1601-082		Hawkins Signal and Curb Ramps	04/30/20	123.00	50.00	72.00	72.00
FSA1602-159		US 160 AND SH 17 INTERSECTION	04/30/20	15.00	75.00	142.00	91.00
	WEIGHTED AVERAGE FOR THE SECOND QUARTER			138.00	52.72	79.61	74.07
	WEIGHTED AVERAGE FOR THE YEAR			971.00	46.77	40.66	38.07

COLORADO DEPARTMENT OF TRANSPORTATION
 ITEM UNIT COSTS BY PROJECTS -- 2020 COST DATA

10:58 Friday, October 2, 2020 210

PROJECT NUMBER	ITEM NUMBER/ PROJECT LOCATION	ITEM DESCRIPTION/ PROJECT LOCATION	DATE LET	UNIT/ QUANTITY	ENGR. EST.	AVERAGE BID	AWARDED BID
=====	609-20011	Curb Ty 2 M		Lin Foot	=====		
HPP 0501-067		US 50 AND SH 92 DELTA INTERSE	03/26/20	1,382.00	25.00	35.60	36.55
		WEIGHTED AVERAGE FOR THE FIRST QUARTER		1,382.00	25.00	35.60	36.55
		WEIGHTED AVERAGE FOR THE YEAR		1,382.00	25.00	35.60	36.55
=====	609-21010	C and G Ty 2 I-B		Lin Foot	=====		
FSA0341-097		US 34 & MACGREGOR INTERSECTIO	01/09/20	493.00	35.00	34.00	34.00
FSA2873-194		US 287 Longmont Intersection	02/13/20	1,700.00	25.00	41.78	23.00
NH0242-085		US 24 M.P. 291.38 to M.P. 296	02/27/20	1,027.00	40.00	57.08	49.10
NHPP0091-044		SH 9 FRISCO MAIN ST TO IRON S	03/05/20	6,215.00	25.00	31.50	35.00
NH050A-034		US50A PUEBLO WEST PURCELL INT	03/26/20	5,363.00	28.00	26.86	28.15
HPP 0501-067		US 50 AND SH 92 DELTA INTERSE	03/26/20	2,456.00	22.00	32.63	32.05
SHE 0703-461		I-70 and Kipling North Phase	03/26/20	24.00	33.50	47.20	58.00
		WEIGHTED AVERAGE FOR THE FIRST QUARTER		17,278.00	26.69	31.42	32.12
IM0761-226		I76/SH52 Interchange	04/02/20	4,517.00	35.00	24.18	28.62
C1211-090		SH-121 & 29th Ave / SH-121 &	04/23/20	527.00	30.00	26.77	34.00
FSA1602-159		US 160 AND SH 17 INTERSECTION	04/30/20	258.00	35.00	75.33	91.00
		WEIGHTED AVERAGE FOR THE SECOND QUARTER		5,302.00	34.50	25.46	32.19
		WEIGHTED AVERAGE FOR THE YEAR		22,580.00	28.53	29.65	32.13
=====	609-21011	C and G Ty 2 I-M		Lin Foot	=====		
NHPP0091-044		SH 9 FRISCO MAIN ST TO IRON S	03/05/20	5,518.00	20.00	41.27	43.00
		WEIGHTED AVERAGE FOR THE FIRST QUARTER		5,518.00	20.00	41.27	43.00
IM0761-226		I76/SH52 Interchange	04/02/20	745.00	40.00	28.00	29.68
CC0852-106		US-85 LOUVIERS TO MP 191.75	04/23/20	20,421.00	17.00	25.47	19.98
FBR0852-108		US-85 BETWEEN LOUVIERS AND MP					
SHE016A-043		SH 21 & 16 SIGNALS PROJECT	06/18/20	67.00	40.00	43.61	45.07
		WEIGHTED AVERAGE FOR THE SECOND QUARTER		21,233.00	17.88	25.59	20.40
		WEIGHTED AVERAGE FOR THE YEAR		26,751.00	18.32	26.99	25.06

COLORADO DEPARTMENT OF TRANSPORTATION
 ITEM UNIT COSTS BY PROJECTS -- 2020 COST DATA

10:58 Friday, October 2, 2020 211

PROJECT NUMBER	ITEM NUMBER/ PROJECT LOCATION	ITEM DESCRIPTION/ PROJECT LOCATION	DATE LET	UNIT/ QUANTITY	ENGR. EST.	AVERAGE BID	AWARDED BID
===== 609-21013 C and G Ty 2 I-M (Spec) Lin Foot =====							
FSA0341-097	US 34 & MACGREGOR INTERSECTIO	US 34 & MACGREGOR INTERSECTIO	01/09/20	271.00	40.00	38.00	38.00
	WEIGHTED AVERAGE FOR THE FIRST QUARTER			271.00	40.00	38.00	38.00
FSA1602-159	US 160 AND SH 17 INTERSECTION	US 160 AND SH 17 INTERSECTION	04/30/20	69.00	35.00	81.00	97.00
	WEIGHTED AVERAGE FOR THE SECOND QUARTER			69.00	35.00	81.00	97.00
	WEIGHTED AVERAGE FOR THE YEAR			340.00	38.99	56.62	49.97
===== 609-21020 C and G Ty 2 II-B Lin Foot =====							
FSA0341-097	US 34 & MACGREGOR INTERSECTIO	US 34 & MACGREGOR INTERSECTIO	01/09/20	1,136.00	35.00	38.00	38.00
NHPP0343-041	I-76 & US 34 FT. MORGAN AREA	I-76 & US 34 FT. MORGAN AREA	01/09/20	2,095.00	40.00	35.03	45.00
BR0343-040	US 34 REPUBLICAN RIVER BRIDGE	US 34 REPUBLICAN RIVER BRIDGE	01/16/20	202.00	30.00	41.20	53.00
FBR0343-043	US 34 D-28-P STRUCTURE REPLAC	US 34 D-28-P STRUCTURE REPLAC					
NHPP 0852-116	US85:HAMPDEN TO FLORIDA-RESUR	US85:HAMPDEN TO FLORIDA-RESUR	02/06/20	30.90	40.00	80.00	70.00
C0402-094	US 40 GRAND COUNTY SIGNAL REP	US 40 GRAND COUNTY SIGNAL REP	02/27/20	275.00	45.00	49.50	47.00
STRR300-249	Grand and Jackson Counties AD	Grand and Jackson Counties AD	03/05/20	457.00	40.00	55.33	41.00
CC080-037	VARIOUS ADA RAMP ALONG NORTH	VARIOUS ADA RAMP ALONG NORTH	03/05/20	98.00	40.00	41.94	38.00
NHPP0091-044	SH 9 FRISCO MAIN ST TO IRON S	SH 9 FRISCO MAIN ST TO IRON S	03/05/20	7,018.00	25.00	28.00	8.00
NH050A-034	US50A PUEBLO WEST PURCELL INT	US50A PUEBLO WEST PURCELL INT	03/26/20	3,857.00	34.00	30.14	31.00
HPP 0501-067	US 50 AND SH 92 DELTA INTERSE	US 50 AND SH 92 DELTA INTERSE	03/26/20	690.00	30.00	45.33	45.15
SHE 0703-461	I-70 and Kipling North Phase	I-70 and Kipling North Phase	03/26/20	616.00	40.00	45.80	44.00
	WEIGHTED AVERAGE FOR THE FIRST QUARTER			16,474.90	31.40	32.07	25.47
IM0761-226	I76/SH52 Interchange	I76/SH52 Interchange	04/02/20	5,734.00	40.00	26.81	30.74
C1211-090	SH-121 & 29th Ave / SH-121 &	SH-121 & 29th Ave / SH-121 &	04/23/20	508.00	30.00	32.10	37.00
C1601-082	Hawkins Signal and Curb Ramps	Hawkins Signal and Curb Ramps	04/30/20	555.00	45.00	75.00	71.00
FSA1602-159	US 160 AND SH 17 INTERSECTION	US 160 AND SH 17 INTERSECTION	04/30/20	287.00	35.00	79.67	91.00
NHPP0402-098	US 40 CHIP SEAL MP 126 TO MP	US 40 CHIP SEAL MP 126 TO MP	05/14/20	90.00	35.00	44.50	39.00
FSAR400-356	FY 20 SIGNAL POLE REPLACEMENT	FY 20 SIGNAL POLE REPLACEMENT	06/11/20	35.00	80.00	72.67	59.00
SHE016A-043	SH 21 & 16 SIGNALS PROJECT	SH 21 & 16 SIGNALS PROJECT	06/18/20	503.00	50.00	44.01	45.05
	WEIGHTED AVERAGE FOR THE SECOND QUARTER			7,712.00	40.29	30.77	37.45
	WEIGHTED AVERAGE FOR THE YEAR			24,186.90	34.24	31.54	29.29

COLORADO DEPARTMENT OF TRANSPORTATION
ITEM UNIT COSTS BY PROJECTS -- 2020 COST DATA

10:58 Friday, October 2, 2020 212

PROJECT NUMBER	ITEM NUMBER/ PROJECT LOCATION	ITEM DESCRIPTION/ PROJECT LOCATION	DATE LET	UNIT/ QUANTITY	ENGR. EST.	AVERAGE BID	AWARDED BID
=====	609-21021	C and G Ty 2 II-M		Lin Foot	=====		
NHPP0343-041		I-76 & US 34 FT. MORGAN AREA	01/09/20	46.00	28.00	40.93	52.00
NHPP0091-044		SH 9 FRISCO MAIN ST TO IRON S	03/05/20	1,142.00	30.00	48.83	48.00
		WEIGHTED AVERAGE FOR THE FIRST QUARTER		1,188.00	29.92	48.53	48.15
IM0761-226		I76/SH52 Interchange	04/02/20	64.00	45.00	41.75	33.92
CC0852-106		US-85 LOUVIERS TO MP 191.75	04/23/20	6,539.00	20.00	31.77	27.40
FBR0852-108		US-85 BETWEEN LOUVIERS AND MP					
		WEIGHTED AVERAGE FOR THE SECOND QUARTER		6,603.00	20.24	31.85	27.46
		WEIGHTED AVERAGE FOR THE YEAR		7,791.00	21.72	32.91	30.62
=====	609-21023	C and G Ty 2 II-B (Spec)		Lin Foot	=====		
FSA0341-097		US 34 & MACGREGOR INTERSECTIO	01/09/20	14.00	45.00	55.00	55.00
		WEIGHTED AVERAGE FOR THE FIRST QUARTER		14.00	45.00	55.00	55.00
NHPPR100-303		LONG MAST ARM SIGNALS PROJECT	05/07/20	268.00	60.00	48.00	40.00
		WEIGHTED AVERAGE FOR THE SECOND QUARTER		268.00	60.00	48.00	40.00
		WEIGHTED AVERAGE FOR THE YEAR		282.00	59.26	48.12	40.74
=====	609-21110	C & G Ty 2 I-B (Spec)		Lin Foot	=====		
FSA1602-159		US 160 AND SH 17 INTERSECTION	04/30/20	165.00	35.00	81.00	95.00
NHPPR100-303		LONG MAST ARM SIGNALS PROJECT	05/07/20	43.00	40.00	52.33	45.00
		WEIGHTED AVERAGE FOR THE SECOND QUARTER		208.00	36.03	75.07	84.66
		WEIGHTED AVERAGE FOR THE YEAR		208.00	36.03	75.07	84.66
=====	609-21900	C and G Ty 2 (Spec)		Lin Foot	=====		
NHPP0091-044		SH 9 FRISCO MAIN ST TO IRON S	03/05/20	616.00	40.00	52.23	45.00
		WEIGHTED AVERAGE FOR THE FIRST QUARTER		616.00	40.00	52.23	45.00

COLORADO DEPARTMENT OF TRANSPORTATION
 ITEM UNIT COSTS BY PROJECTS -- 2020 COST DATA

10:58 Friday, October 2, 2020 213

PROJECT NUMBER	ITEM NUMBER/ PROJECT LOCATION	ITEM DESCRIPTION/ PROJECT LOCATION	DATE LET	UNIT/ QUANTITY	ENGR. EST.	AVERAGE BID	AWARDED BID
===== 609-21900		C and G Ty 2 (Spec)		Lin Foot	=====		
IM0761-226		I76/SH52 Interchange	04/02/20	824.00	45.00	62.39	36.04
FSA1602-159		US 160 AND SH 17 INTERSECTION	04/30/20	134.00	35.00	114.00	104.00
		WEIGHTED AVERAGE FOR THE SECOND QUARTER		958.00	43.60	65.75	45.55
		WEIGHTED AVERAGE FOR THE YEAR		1,574.00	42.19	62.64	45.33
===== 609-23000		Gutter (Special)		Lin Foot	=====		
PWQM240-172		El Paso County, north Colorad	01/23/20	586.00	100.00	147.00	154.00
		WEIGHTED AVERAGE FOR THE FIRST QUARTER		586.00	100.00	147.00	154.00
CC0852-106		US-85 LOUVIERS TO MP 191.75	04/23/20	1,660.00	45.00	56.91	62.83
FBR0852-108		US-85 BETWEEN LOUVIERS AND MP					
		WEIGHTED AVERAGE FOR THE SECOND QUARTER		1,660.00	45.00	56.91	62.83
		WEIGHTED AVERAGE FOR THE YEAR		2,246.00	59.35	64.21	86.62
===== 609-24002		Gutter Ty 2 (2 Ft)		Lin Foot	=====		
NHPP4701-134		C-470 NOISE WALL WEST OF LUCE	02/06/20	632.00	40.00	37.80	19.00
STRR300-249		Grand and Jackson Counties AD	03/05/20	41.00	40.00	76.67	43.00
CC080-037		VARIOUS ADA RAMPS ALONG NORTH	03/05/20	15.00	40.00	43.53	42.00
		WEIGHTED AVERAGE FOR THE FIRST QUARTER		688.00	40.00	39.33	20.93
		WEIGHTED AVERAGE FOR THE YEAR		688.00	40.00	39.33	20.93
===== 609-24003		Gutter Ty 2 (3 Ft)		Lin Foot	=====		
NH050A-034		US50A PUEBLO WEST PURCELL INT	03/26/20	590.00	65.00	30.23	31.50
		WEIGHTED AVERAGE FOR THE FIRST QUARTER		590.00	65.00	30.23	31.50
		WEIGHTED AVERAGE FOR THE YEAR		590.00	65.00	30.23	31.50

COLORADO DEPARTMENT OF TRANSPORTATION
ITEM UNIT COSTS BY PROJECTS -- 2020 COST DATA

10:58 Friday, October 2, 2020 214

PROJECT NUMBER	ITEM NUMBER/ PROJECT LOCATION	ITEM DESCRIPTION/ PROJECT LOCATION	DATE LET	UNIT/ QUANTITY	ENGR. EST.	AVERAGE BID	AWARDED BID
===== 609-24004		Gutter Ty 2 (4 Ft)		Lin Foot	=====		
FSA0253-262		I-25 SB BOTTLENECK I-76 TO I-	01/09/20	124.00	40.00	49.28	50.00
BR0343-040		US 34 REPUBLICAN RIVER BRIDGE	01/16/20	110.00	50.00	48.88	43.00
FBR0343-043		US 34 D-28-P STRUCTURE REPLAC					
NHPP145A-080		SH 145 Keystone-Placerville R	03/05/20	51.00	60.00	85.00	85.00
STRR300-249		Grand and Jackson Counties AD	03/05/20	13.00	50.00	143.67	47.00
HPP 0501-067		US 50 AND SH 92 DELTA INTERSE	03/26/20	44.00	35.00	64.45	52.10
		WEIGHTED AVERAGE FOR THE FIRST QUARTER		342.00	45.94	54.71	53.12
NHPP0402-098		US 40 CHIP SEAL MP 126 TO MP	05/14/20	65.00	41.00	87.67	78.00
		WEIGHTED AVERAGE FOR THE SECOND QUARTER		65.00	41.00	87.67	78.00
		WEIGHTED AVERAGE FOR THE YEAR		407.00	45.15	59.29	57.10
===== 609-24006		Gutter Ty 2 (6 Ft)		Lin Foot	=====		
STA0703-443		I-70 EJMT TUNNELS PAVING	02/06/20	185.00	45.00	194.80	324.59
NHPP145A-080		SH 145 Keystone-Placerville R	03/05/20	127.00	60.00	127.00	127.00
		WEIGHTED AVERAGE FOR THE FIRST QUARTER		312.00	51.11	177.47	244.16
CC0852-106		US-85 LOUVIERS TO MP 191.75	04/23/20	550.00	40.00	63.74	58.17
FBR0852-108		US-85 BETWEEN LOUVIERS AND MP					
		WEIGHTED AVERAGE FOR THE SECOND QUARTER		550.00	40.00	63.74	58.17
		WEIGHTED AVERAGE FOR THE YEAR		862.00	44.02	75.28	125.49
===== 609-24008		Gutter Ty 2 (8 Ft)		Lin Foot	=====		
IM0761-226		I76/SH52 Interchange	04/02/20	68.00	150.00	94.57	51.94
		WEIGHTED AVERAGE FOR THE SECOND QUARTER		68.00	150.00	94.57	51.94
		WEIGHTED AVERAGE FOR THE YEAR		68.00	150.00	94.57	51.94

COLORADO DEPARTMENT OF TRANSPORTATION
ITEM UNIT COSTS BY PROJECTS -- 2020 COST DATA

10:58 Friday, October 2, 2020 215

PROJECT NUMBER	ITEM NUMBER/ PROJECT LOCATION	ITEM DESCRIPTION/ PROJECT LOCATION	DATE LET	UNIT/ QUANTITY	ENGR. EST.	AVERAGE BID	AWARDED BID
=====	609-24010	Gutter Ty 2 (10 Ft)		Lin Foot	=====		
NH050A-034		US50A PUEBLO WEST PURCELL INT	03/26/20	110.00	160.00	104.69	98.00
	WEIGHTED AVERAGE FOR THE FIRST QUARTER			110.00	160.00	104.69	98.00
	WEIGHTED AVERAGE FOR THE YEAR			110.00	160.00	104.69	98.00
=====	609-31010	C and G Ty 2 I-B (Fast Track)		Lin Foot	=====		
SHE 0703-461		I-70 and Kipling North Phase	03/26/20	443.00	55.00	50.60	48.00
	WEIGHTED AVERAGE FOR THE FIRST QUARTER			443.00	55.00	50.60	48.00
	WEIGHTED AVERAGE FOR THE YEAR			443.00	55.00	50.60	48.00
=====	609-40010	Curb Ty 4 B		Lin Foot	=====		
FSA2873-194		US 287 Longmont Intersection	02/13/20	1,056.00	40.00	46.42	24.50
	WEIGHTED AVERAGE FOR THE FIRST QUARTER			1,056.00	40.00	46.42	24.50
	WEIGHTED AVERAGE FOR THE YEAR			1,056.00	40.00	46.42	24.50
=====	609-40011	Curb Ty 4 M		Lin Foot	=====		
NHPP 0852-116		US85:HAMPDEN TO FLORIDA-RESUR	02/06/20	30.00	27.00	85.00	80.00
	WEIGHTED AVERAGE FOR THE FIRST QUARTER			30.00	27.00	85.00	80.00
CC0852-106 FBR0852-108		US-85 LOUVIERS TO MP 191.75 US-85 BETWEEN LOUVIERS AND MP	04/23/20	60.00	45.00	48.67	50.00
	WEIGHTED AVERAGE FOR THE SECOND QUARTER			60.00	45.00	48.67	50.00
	WEIGHTED AVERAGE FOR THE YEAR			90.00	39.00	52.70	60.00
=====	609-40120	Curb Median Special		Sq Yard	=====		
FSA2873-194		US 287 Longmont Intersection	02/13/20	41.00	70.00	149.00	100.00
	WEIGHTED AVERAGE FOR THE FIRST QUARTER			41.00	70.00	149.00	100.00
	WEIGHTED AVERAGE FOR THE YEAR			41.00	70.00	149.00	100.00

COLORADO DEPARTMENT OF TRANSPORTATION
ITEM UNIT COSTS BY PROJECTS -- 2020 COST DATA

10:58 Friday, October 2, 2020 216

PROJECT NUMBER	ITEM NUMBER/ PROJECT LOCATION	ITEM DESCRIPTION/ PROJECT LOCATION	DATE LET	UNIT/ QUANTITY	ENGR. EST.	AVERAGE BID	AWARDED BID
=====	609-60011	Curb Ty 6 M		Lin Foot	=====		
NHPP0343-041		I-76 & US 34 FT. MORGAN AREA	01/09/20	20,338.00	15.00	10.43	7.50
BR0343-040		US 34 REPUBLICAN RIVER BRIDGE	01/16/20	180.00	30.00	37.89	36.00
FBR0343-043		US 34 D-28-P STRUCTURE REPLAC					
STA059A-036		SH 59 SEIBERT TO COPE	02/06/20	150.00	30.00	29.50	25.00
NH0242-085		US 24 M.P. 291.38 to M.P. 296	02/27/20	925.00	15.50	33.69	26.80
NHPP0091-044		SH 9 FRISCO MAIN ST TO IRON S	03/05/20	24.00	50.00	64.17	11.00
NH050A-034		US50A PUEBLO WEST PURCELL INT	03/26/20	1,666.00	16.00	16.27	25.50
		WEIGHTED AVERAGE FOR THE FIRST QUARTER		23,283.00	15.34	12.74	9.89
NHPP1602-169		US 160 WC TUNNEL EAST RESURFA	04/02/20	220.00	35.00	32.14	34.65
FBR0343-042		US 34 D-27-G STRUCTURE REPLAC	05/07/20	77.00	40.00	45.48	45.00
		WEIGHTED AVERAGE FOR THE SECOND QUARTER		297.00	36.30	38.97	37.33
		WEIGHTED AVERAGE FOR THE YEAR		23,580.00	15.60	13.19	10.24
=====	609-71000	Curb (Special)		Lin Foot	=====		
FSA0341-097		US 34 & MACGREGOR INTERSECTIO	01/09/20	484.00	50.00	42.00	42.00
NHPP0343-041		I-76 & US 34 FT. MORGAN AREA	01/09/20	21.00	53.00	22.50	19.00
		WEIGHTED AVERAGE FOR THE FIRST QUARTER		505.00	50.12	39.75	41.04
		WEIGHTED AVERAGE FOR THE YEAR		505.00	50.12	39.75	41.04
=====	610-00010	Median Cover Mat1 (Dec)		Sq Foot	=====		
NHPPR100-303		LONG MAST ARM SIGNALS PROJECT	05/07/20	35.00	50.00	48.17	38.50
		WEIGHTED AVERAGE FOR THE SECOND QUARTER		35.00	50.00	48.17	38.50
		WEIGHTED AVERAGE FOR THE YEAR		35.00	50.00	48.17	38.50
=====	610-00020	Median Cover (Pattern Conc)		Sq Foot	=====		
NHPP0253-265		I-25 AT ERIE PARKWAY ON AND O	01/09/20	225.00	30.00	54.33	70.00

PROJECT NUMBER	ITEM NUMBER/ PROJECT LOCATION	ITEM DESCRIPTION/ PROJECT LOCATION	DATE LET	UNIT/ QUANTITY	ENGR. EST.	AVERAGE BID	AWARDED BID
=====	610-00020	Median Cover (Pattern Conc)		Sq Foot	=====		
FSA0341-097		US 34 & MACGREGOR INTERSECTIO	01/09/20	1,567.00	17.50	15.00	15.00
NHPP0343-041		I-76 & US 34 FT. MORGAN AREA	01/09/20	377.00	18.00	15.03	16.00
BR0343-040		US 34 REPUBLICAN RIVER BRIDGE	01/16/20	124.00	40.00	33.31	35.00
FBR0343-043		US 34 D-28-P STRUCTURE REPLAC					
NHPP0091-044		SH 9 FRISCO MAIN ST TO IRON S	03/05/20	7,259.00	10.00	16.17	14.00
NH050A-034		US50A PUEBLO WEST PURCELL INT	03/26/20	30,825.00	15.00	12.49	11.50
HPP 0501-067		US 50 AND SH 92 DELTA INTERSE	03/26/20	13,320.00	8.00	9.43	8.90
		WEIGHTED AVERAGE FOR THE FIRST QUARTER		53,697.00	12.80	12.66	11.63
CC0852-106		US-85 LOUVIERS TO MP 191.75	04/23/20	1,604.00	12.00	18.22	8.34
FBR0852-108		US-85 BETWEEN LOUVIERS AND MP					
FSA1602-159		US 160 AND SH 17 INTERSECTION	04/30/20	1,264.00	18.00	25.00	30.00
NHPPR100-303		LONG MAST ARM SIGNALS PROJECT	05/07/20	337.00	40.00	33.00	32.00
FSAR400-356		FY 20 SIGNAL POLE REPLACEMENT	06/11/20	207.00	50.00	33.00	37.00
SHE016A-043		SH 21 & 16 SIGNALS PROJECT	06/18/20	1,798.00	18.00	23.16	20.79
		WEIGHTED AVERAGE FOR THE SECOND QUARTER		5,210.00	18.85	21.68	20.56
		WEIGHTED AVERAGE FOR THE YEAR		58,907.00	13.34	13.41	12.42
=====	610-00024	Median Cover (4 In Pattern Conc)		Sq Foot	=====		
SHE 0703-461		I-70 and Kipling North Phase	03/26/20	2,416.00	12.00	17.80	19.00
		WEIGHTED AVERAGE FOR THE FIRST QUARTER		2,416.00	12.00	17.80	19.00
IM0761-226		I76/SH52 Interchange	04/02/20	18,450.00	11.00	10.33	8.48
CC0852-106		US-85 LOUVIERS TO MP 191.75	04/23/20	80,637.00	7.00	8.19	5.49
FBR0852-108		US-85 BETWEEN LOUVIERS AND MP					
		WEIGHTED AVERAGE FOR THE SECOND QUARTER		99,087.00	7.74	8.54	6.05
		WEIGHTED AVERAGE FOR THE YEAR		101,503.00	7.85	8.69	6.36
=====	610-00026	Median Cover (6 In Pattern Conc)		Sq Foot	=====		
NH0242-085		US 24 M.P. 291.38 to M.P. 296	02/27/20	674.00	11.00	24.61	15.50
		WEIGHTED AVERAGE FOR THE FIRST QUARTER		674.00	11.00	24.61	15.50

COLORADO DEPARTMENT OF TRANSPORTATION
 ITEM UNIT COSTS BY PROJECTS -- 2020 COST DATA

10:58 Friday, October 2, 2020 218

PROJECT NUMBER	ITEM NUMBER/ PROJECT LOCATION	ITEM DESCRIPTION/ PROJECT LOCATION	DATE LET	UNIT/ QUANTITY	ENGR. EST.	AVERAGE BID	AWARDED BID
=====	610-00026	Median Cover (6 In Pattern Conc)		Sq Foot	=====		
IM0761-226		I76/SH52 Interchange	04/02/20	5,136.00	14.00	12.66	9.54
		WEIGHTED AVERAGE FOR THE SECOND QUARTER		5,136.00	14.00	12.66	9.54
		WEIGHTED AVERAGE FOR THE YEAR		5,810.00	13.65	13.30	10.23
=====	610-00030	Median Cover Matl (Conc)		Sq Foot	=====		
FSA2873-194		US 287 Longmont Intersection	02/13/20	8,857.00	11.00	13.63	8.00
		WEIGHTED AVERAGE FOR THE FIRST QUARTER		8,857.00	11.00	13.63	8.00
C1211-090		SH-121 & 29th Ave / SH-121 &	04/23/20	1,936.00	12.00	14.60	15.00
		WEIGHTED AVERAGE FOR THE SECOND QUARTER		1,936.00	12.00	14.60	15.00
		WEIGHTED AVERAGE FOR THE YEAR		10,793.00	11.18	13.73	9.26
=====	610-00035	Median Cover Matl (Conc) (Spec)		Sq Foot	=====		
C1601-082		Hawkins Signal and Curb Ramps	04/30/20	965.00	20.00	22.50	17.00
		WEIGHTED AVERAGE FOR THE SECOND QUARTER		965.00	20.00	22.50	17.00
		WEIGHTED AVERAGE FOR THE YEAR		965.00	20.00	22.50	17.00
=====	611-00029	28 Ft Deer Gd		Each	=====		
CC0852-106 FBR0852-108		US-85 LOUVIERS TO MP 191.75 US-85 BETWEEN LOUVIERS AND MP	04/23/20	2.00	60000.00	77863.37	62425.00
		WEIGHTED AVERAGE FOR THE SECOND QUARTER		2.00	60000.00	77863.37	62425.00
		WEIGHTED AVERAGE FOR THE YEAR		2.00	60000.00	77863.37	62425.00
=====	611-00031	30 Ft Deer Gd		Each	=====		
CC0852-106		US-85 LOUVIERS TO MP 191.75	04/23/20	1.00	65000.00	85404.32	67925.00

PROJECT NUMBER	ITEM NUMBER/ PROJECT LOCATION	ITEM DESCRIPTION/ PROJECT LOCATION	DATE LET	UNIT/ QUANTITY	ENGR. EST.	AVERAGE BID	AWARDED BID
=====	611-00031	30 Ft Deer Gd		Each	=====	=====	=====
FBR0852-108		US-85 BETWEEN LOUVIERS AND MP					
	WEIGHTED AVERAGE FOR THE SECOND QUARTER			1.00	65000.00	85404.32	67925.00
	WEIGHTED AVERAGE FOR THE YEAR			1.00	65000.00	85404.32	67925.00
=====	611-00033	32 Ft Deer Gd		Each	=====	=====	=====
CC0852-106		US-85 LOUVIERS TO MP 191.75	04/23/20	1.00	70000.00	90338.17	67925.00
FBR0852-108		US-85 BETWEEN LOUVIERS AND MP					
	WEIGHTED AVERAGE FOR THE SECOND QUARTER			1.00	70000.00	90338.17	67925.00
	WEIGHTED AVERAGE FOR THE YEAR			1.00	70000.00	90338.17	67925.00
=====	612-00001	Delin (Ty I)		Each	=====	=====	=====
FSA0341-097		US 34 & MACGREGOR INTERSECTIO	01/09/20	5.00	25.00	23.00	23.00
STR131A-038		SH 131 MP 51.95-55.73, ROUTT	01/16/20	212.00	30.00	21.00	20.00
STA0703-443		I-70 EJMT TUNNELS PAVING	02/06/20	5.00	45.00	50.38	39.75
FSA2873-194		US 287 Longmont Intersection	02/13/20	4.00	30.00	43.25	31.00
STA069A-033		SH69 MP 58.7 TO 71.58	02/13/20	442.00	26.00	16.55	17.00
NH0242-085		US 24 M.P. 291.38 to M.P. 296	02/27/20	532.00	28.00	24.23	27.40
NHPP0171-105		SH 17 MP 84.5 to US 285 & SH	03/05/20	781.00	22.00	24.15	23.46
C0641-106		SH 64 Meeker West Rural Resur	03/05/20	50.00	30.00	29.00	30.00
NHPP145A-080		SH 145 Keystone-Placerville R	03/05/20	361.00	30.00	22.00	22.00
BR025A-046		K-18-U ON I-25 AT MP112 BRIDG	03/05/20	8.00	30.00	67.21	42.23
HPP 0501-067		US 50 AND SH 92 DELTA INTERSE	03/26/20	10.00	25.00	32.20	32.50
SHE 0703-461		I-70 and Kipling North Phase	03/26/20	10.00	35.00	70.80	28.00
	WEIGHTED AVERAGE FOR THE FIRST QUARTER			2,420.00	26.27	23.71	22.92
NHPP1602-169		US 160 WC TUNNEL EAST RESURFA	04/02/20	267.00	25.00	21.74	22.74
STR092A-030		SH92 MP 31.748-48.5, DELTA AND	04/02/20	38.00	28.00	29.15	30.00
STA340A-021		SH340 MP 6-6.76 MESA COUNTY	04/02/20	14.00	26.00	27.38	30.00
STR0341-101		SH 34 North of Grandby Resurf	04/02/20	11.00	30.00	32.62	35.00
SFTY2254-091		225 Ramp Improvements	04/09/20	26.00	30.00	70.00	68.00
CC0852-106		US-85 LOUVIERS TO MP 191.75	04/23/20	233.00	35.00	22.65	17.60
FBR0852-108		US-85 BETWEEN LOUVIERS AND MP					
FSA1602-159		US 160 AND SH 17 INTERSECTION	04/30/20	59.00	20.00	42.67	54.00
NHPPR100-303		LONG MAST ARM SIGNALS PROJECT	05/07/20	4.00	30.00	95.00	40.00

COLORADO DEPARTMENT OF TRANSPORTATION
 ITEM UNIT COSTS BY PROJECTS -- 2020 COST DATA

10:58 Friday, October 2, 2020 220

PROJECT NUMBER	ITEM NUMBER/ PROJECT LOCATION	ITEM DESCRIPTION/ PROJECT LOCATION	DATE LET	UNIT/ QUANTITY	ENGR. EST.	AVERAGE BID	AWARDED BID
===== 612-00001 Delin (Ty I) Each =====							
FBR0343-042		US 34 D-27-G STRUCTURE REPLAC	05/07/20	24.00	40.00	38.41	70.00
NHPP0402-098		US 40 CHIP SEAL MP 126 TO MP	05/14/20	2.00	30.00	40.28	39.00
ITSSW01-719		FY 20 ITS CAPITAL REPLACEMENT	06/11/20	6.00	25.00	27.50	25.00
SHE016A-043		SH 21 & 16 SIGNALS PROJECT	06/18/20	31.00	25.00	29.50	18.48
WEIGHTED AVERAGE FOR THE SECOND QUARTER				715.00	28.83	26.09	27.57
WEIGHTED AVERAGE FOR THE YEAR				3,135.00	26.85	24.59	23.98
===== 612-00002 Delin (Ty II) Each =====							
FSA0341-097		US 34 & MACGREGOR INTERSECTIO	01/09/20	11.00	23.00	28.00	28.00
FSA2873-194		US 287 Longmont Intersection	02/13/20	1.00	40.00	46.09	35.00
STA069A-033		SH69 MP 58.7 TO 71.58	02/13/20	4.00	26.00	17.58	18.00
NH0242-085		US 24 M.P. 291.38 to M.P. 296	02/27/20	74.00	26.00	26.76	29.65
NHPP0171-105		SH 17 MP 84.5 to US 285 & SH	03/05/20	115.00	23.00	26.83	25.50
NHPP145A-080		SH 145 Keystone-Placerville R	03/05/20	16.00	35.00	26.00	26.00
HPP 0501-067		US 50 AND SH 92 DELTA INTERSE	03/26/20	50.00	25.00	34.45	34.80
SHE 0703-461		I-70 and Kipling North Phase	03/26/20	15.00	40.00	86.80	31.00
WEIGHTED AVERAGE FOR THE FIRST QUARTER				286.00	25.79	33.58	28.54
NHPP1602-169		US 160 WC TUNNEL EAST RESURFA	04/02/20	68.00	26.00	26.43	27.07
STR092A-030		SH92 MP 31.748-48.5, DELTA AND	04/02/20	682.00	26.00	31.80	33.00
STA340A-021		SH340 MP 6-6.76 MESA COUNTY	04/02/20	2.00	28.00	28.08	30.00
CC0852-106		US-85 LOUVIERS TO MP 191.75	04/23/20	141.00	36.00	24.80	19.80
FBR0852-108		US-85 BETWEEN LOUVIERS AND MP					
FSA1602-159		US 160 AND SH 17 INTERSECTION	04/30/20	6.00	25.00	55.00	81.00
FBR0343-042		US 34 D-27-G STRUCTURE REPLAC	05/07/20	11.00	45.00	45.50	80.00
SHE016A-043		SH 21 & 16 SIGNALS PROJECT	06/18/20	8.00	40.00	31.55	20.75
WEIGHTED AVERAGE FOR THE SECOND QUARTER				918.00	27.88	29.27	31.30
WEIGHTED AVERAGE FOR THE YEAR				1,204.00	27.39	30.19	30.64
===== 612-00003 Delin (Ty III) Each =====							
STR131A-038		SH 131 MP 51.95-55.73, ROUTT	01/16/20	35.00	35.00	25.50	24.00
STR012A-050		CULVERT REPAIR I-25 AND US 35	01/30/20	1.00	50.00	50.00	50.00
FSA2873-194		US 287 Longmont Intersection	02/13/20	2.00	50.00	48.67	35.00
STA069A-033		SH69 MP 58.7 TO 71.58	02/13/20	44.00	24.00	19.50	20.00

COLORADO DEPARTMENT OF TRANSPORTATION
 ITEM UNIT COSTS BY PROJECTS -- 2020 COST DATA

10:58 Friday, October 2, 2020 221

PROJECT NUMBER	ITEM NUMBER/ PROJECT LOCATION	ITEM DESCRIPTION/ PROJECT LOCATION	DATE LET	UNIT/ QUANTITY	ENGR. EST.	AVERAGE BID	AWARDED BID
===== 612-00003		Delin (Ty III)		Each =====			
NH0242-085		US 24 M.P. 291.38 to M.P. 296	02/27/20	95.00	34.00	29.32	31.95
NHPP0171-105		SH 17 MP 84.5 to US 285 & SH	03/05/20	82.00	24.00	30.18	27.54
C0641-106		SH 64 Meeker West Rural Resur	03/05/20	15.00	35.00	33.00	34.00
NHPP145A-080		SH 145 Keystone-Placerville R	03/05/20	228.00	23.00	30.00	30.00
BR025A-046		K-18-U ON I-25 AT MP112 BRIDG	03/05/20	1.00	30.00	82.56	46.26
SHE 0703-461		I-70 and Kipling North Phase	03/26/20	5.00	75.00	102.20	35.00
	WEIGHTED AVERAGE FOR THE FIRST QUARTER			508.00	27.17	31.13	28.95
NHPP1602-169		US 160 WC TUNNEL EAST RESURFA	04/02/20	45.00	31.00	29.93	31.40
STR092A-030		SH92 MP 31.748-48.5, DELTA AND	04/02/20	127.00	30.00	33.40	35.00
STA340A-021		SH340 MP 6-6.76 MESA COUNTY	04/02/20	1.00	30.00	28.78	30.00
STR0341-101		SH 34 North of Grandby Resurf	04/02/20	14.00	30.00	40.05	40.00
CC0852-106		US-85 LOUVIERS TO MP 191.75	04/23/20	60.00	80.00	26.96	22.00
FBR0852-108		US-85 BETWEEN LOUVIERS AND MP					
FSA1602-159		US 160 AND SH 17 INTERSECTION	04/30/20	2.00	30.00	60.00	91.00
FBR0343-042		US 34 D-27-G STRUCTURE REPLAC	05/07/20	2.00	50.00	55.73	100.00
ITSSW01-719		FY 20 ITS CAPITAL REPLACEMENT	06/11/20	6.00	30.00	32.50	30.00
	WEIGHTED AVERAGE FOR THE SECOND QUARTER			257.00	42.00	30.65	32.41
	WEIGHTED AVERAGE FOR THE YEAR			765.00	32.15	30.89	30.11
===== 612-00021		Delin (Ty I) (Barrier)		Each =====			
NH0242-085		US 24 M.P. 291.38 to M.P. 296	02/27/20	47.00	59.00	50.91	45.60
	WEIGHTED AVERAGE FOR THE FIRST QUARTER			47.00	59.00	50.91	45.60
	WEIGHTED AVERAGE FOR THE YEAR			47.00	59.00	50.91	45.60
===== 612-00022		Delin (Ty II) (Barrier)		Each =====			
NH0242-085		US 24 M.P. 291.38 to M.P. 296	02/27/20	12.00	53.00	55.80	51.35
	WEIGHTED AVERAGE FOR THE FIRST QUARTER			12.00	53.00	55.80	51.35
	WEIGHTED AVERAGE FOR THE YEAR			12.00	53.00	55.80	51.35
===== 612-00031		Delin (Ty I) (Extra Ht)		Each =====			
NHPP1602-169		US 160 WC TUNNEL EAST RESURFA	04/02/20	49.00	45.00	49.31	45.48
	WEIGHTED AVERAGE FOR THE SECOND QUARTER			49.00	45.00	49.31	45.48
	WEIGHTED AVERAGE FOR THE YEAR			49.00	45.00	49.31	45.48

COLORADO DEPARTMENT OF TRANSPORTATION
 ITEM UNIT COSTS BY PROJECTS -- 2020 COST DATA

10:58 Friday, October 2, 2020 222

PROJECT NUMBER	ITEM NUMBER/ PROJECT LOCATION	ITEM DESCRIPTION/ PROJECT LOCATION	DATE LET	UNIT/ QUANTITY	ENGR. EST.	AVERAGE BID	AWARDED BID
=====	612-00032	Delin (Ty II) (Extra Ht)		Each	=====		
NHPP1602-169		US 160 WC TUNNEL EAST RESURFA	04/02/20	46.00	54.00	57.64	54.14
		WEIGHTED AVERAGE FOR THE SECOND QUARTER		46.00	54.00	57.64	54.14
		WEIGHTED AVERAGE FOR THE YEAR		46.00	54.00	57.64	54.14
=====	612-00033	Delin (Ty III) (Extra Ht)		Each	=====		
NHPP1602-169		US 160 WC TUNNEL EAST RESURFA	04/02/20	149.00	63.00	65.27	62.81
		WEIGHTED AVERAGE FOR THE SECOND QUARTER		149.00	63.00	65.27	62.81
		WEIGHTED AVERAGE FOR THE YEAR		149.00	63.00	65.27	62.81
=====	612-00036	Delin (Flex) (Sq Base)		Each	=====		
STR0101-027		SH 10 Overlay La Junta West	02/27/20	535.00	75.00	80.02	95.00
		WEIGHTED AVERAGE FOR THE FIRST QUARTER		535.00	75.00	80.02	95.00
SHER100-339		WWD TRAFFIC CONTROL ENHANCEME	04/09/20	26.00	20.00	70.00	70.00
		WEIGHTED AVERAGE FOR THE SECOND QUARTER		26.00	20.00	70.00	70.00
		WEIGHTED AVERAGE FOR THE YEAR		561.00	72.45	79.86	93.84
=====	612-00037	Delin (Flex) (Flat Mount)		Each	=====		
BR0343-040		US 34 REPUBLICAN RIVER BRIDGE	01/16/20	16.00	70.00	96.11	125.00
FBR0343-043		US 34 D-28-P STRUCTURE REPLAC					
STR116A-001		SH 116 A Surface Treatment Pr	02/13/20	45.00	70.00	83.23	82.00
STR0101-027		SH 10 Overlay La Junta West	02/27/20	17.00	80.00	84.30	85.00
		WEIGHTED AVERAGE FOR THE FIRST QUARTER		78.00	72.18	87.81	91.47
		WEIGHTED AVERAGE FOR THE YEAR		78.00	72.18	87.81	91.47
=====	612-00039	Delin (Flex) (Surf Mount)		Each	=====		
IM0761-226		I76/SH52 Interchange	04/02/20	11.00	75.00	118.69	127.20

COLORADO DEPARTMENT OF TRANSPORTATION
 ITEM UNIT COSTS BY PROJECTS -- 2020 COST DATA

10:58 Friday, October 2, 2020 223

PROJECT NUMBER	ITEM NUMBER/ PROJECT LOCATION	ITEM DESCRIPTION/ PROJECT LOCATION	DATE LET	UNIT/ QUANTITY	ENGR. EST.	AVERAGE BID	AWARDED BID
===== 612-00039		Delin (Flex) (Surf Mount)		Each =====			
NHPPR100-303		LONG MAST ARM SIGNALS PROJECT	05/07/20	3.00	100.00	146.67	130.00
	WEIGHTED AVERAGE FOR THE SECOND QUARTER			14.00	80.36	121.62	127.80
	WEIGHTED AVERAGE FOR THE YEAR			14.00	80.36	121.62	127.80
===== 612-00041		Delin (Flex) (Ty I)		Each =====			
NH 0503-093		US50 WEST OF TEXAS CREEK MP 2	01/23/20	180.00	25.00	58.88	57.76
STR116A-001		SH 116 A Surface Treatment Pr	02/13/20	626.00	40.00	63.59	65.00
NH0242-085		US 24 M.P. 291.38 to M.P. 296	02/27/20	110.00	68.00	89.65	85.55
NH050A-034		US50A PUEBLO WEST PURCELL INT	03/26/20	200.00	70.00	75.71	78.00
	WEIGHTED AVERAGE FOR THE FIRST QUARTER			1,116.00	45.72	69.90	68.19
IM0761-226		I76/SH52 Interchange	04/02/20	99.00	65.00	88.77	116.60
C1601-082		Hawkins Signal and Curb Ramps	04/30/20	3.00	70.00	168.00	279.00
FSA1602-159		US 160 AND SH 17 INTERSECTION	04/30/20	6.00	30.00	114.67	54.00
C0853-112		US85 & WCR98 INTERSECTION IMP	05/07/20	49.00	100.00	78.63	75.00
	WEIGHTED AVERAGE FOR THE SECOND QUARTER			157.00	74.68	86.26	104.33
	WEIGHTED AVERAGE FOR THE YEAR			1,273.00	49.29	73.34	72.64
===== 612-00042		Delin (Flex) (Ty II)		Each =====			
NH 0503-093		US50 WEST OF TEXAS CREEK MP 2	01/23/20	50.00	26.00	69.13	68.26
NH0242-085		US 24 M.P. 291.38 to M.P. 296	02/27/20	4.00	75.00	95.18	91.25
NH050A-034		US50A PUEBLO WEST PURCELL INT	03/26/20	100.00	80.00	79.88	89.00
	WEIGHTED AVERAGE FOR THE FIRST QUARTER			154.00	62.34	78.90	82.32
IM0761-226		I76/SH52 Interchange	04/02/20	27.00	83.00	95.81	118.72
C0853-112		US85 & WCR98 INTERSECTION IMP	05/07/20	43.00	100.00	84.56	80.00
	WEIGHTED AVERAGE FOR THE SECOND QUARTER			70.00	93.44	88.55	94.93
	WEIGHTED AVERAGE FOR THE YEAR			224.00	72.06	82.46	86.27

COLORADO DEPARTMENT OF TRANSPORTATION
 ITEM UNIT COSTS BY PROJECTS -- 2020 COST DATA

10:58 Friday, October 2, 2020 224

PROJECT NUMBER	ITEM NUMBER/ PROJECT LOCATION	ITEM DESCRIPTION/ PROJECT LOCATION	DATE LET	UNIT/ QUANTITY	ENGR. EST.	AVERAGE BID	AWARDED BID
=====	612-00043	Delin (Flex) (Ty III)		Each	=====		
NH 0503-093		US50 WEST OF TEXAS CREEK MP 2	01/23/20	150.00	27.00	74.26	73.51
STR116A-001		SH 116 A Surface Treatment Pr	02/13/20	29.00	45.00	68.70	70.00
NH0242-085		US 24 M.P. 291.38 to M.P. 296	02/27/20	16.00	75.00	100.71	96.95
NH050A-034		US50A PUEBLO WEST PURCELL INT	03/26/20	10.00	90.00	84.30	100.00
		WEIGHTED AVERAGE FOR THE FIRST QUARTER		205.00	36.37	77.34	76.14
IM0761-226		I76/SH52 Interchange	04/02/20	27.00	87.00	100.42	120.84
		WEIGHTED AVERAGE FOR THE SECOND QUARTER		27.00	87.00	100.42	120.84
		WEIGHTED AVERAGE FOR THE YEAR		232.00	42.26	83.54	81.34
=====	612-00050	Reflector (Type-3)		Each	=====		
SHER100-339		WWD TRAFFIC CONTROL ENHANCEME	04/09/20	212.00	25.00	45.00	45.00
		WEIGHTED AVERAGE FOR THE SECOND QUARTER		212.00	25.00	45.00	45.00
		WEIGHTED AVERAGE FOR THE YEAR		212.00	25.00	45.00	45.00
=====	612-00052	Reflector		Each	=====		
NH 0503-093		US50 WEST OF TEXAS CREEK MP 2	01/23/20	250.00	2.00	36.00	42.00
C0641-106		SH 64 Meeker West Rural Resur	03/05/20	500.00	10.00	6.18	6.35
		WEIGHTED AVERAGE FOR THE FIRST QUARTER		750.00	7.33	16.12	18.23
SHER100-339		WWD TRAFFIC CONTROL ENHANCEME	04/09/20	705.00	5.00	12.00	12.00
		WEIGHTED AVERAGE FOR THE SECOND QUARTER		705.00	5.00	12.00	12.00
		WEIGHTED AVERAGE FOR THE YEAR		1,455.00	6.20	14.80	15.21
=====	612-00060	Reflector (Median Barrier)		Each	=====		
SHER100-339		WWD TRAFFIC CONTROL ENHANCEME	04/09/20	165.00	35.00	45.00	45.00
		WEIGHTED AVERAGE FOR THE SECOND QUARTER		165.00	35.00	45.00	45.00
		WEIGHTED AVERAGE FOR THE YEAR		165.00	35.00	45.00	45.00

COLORADO DEPARTMENT OF TRANSPORTATION
ITEM UNIT COSTS BY PROJECTS -- 2020 COST DATA

10:58 Friday, October 2, 2020 225

PROJECT NUMBER	ITEM NUMBER/ PROJECT LOCATION	ITEM DESCRIPTION/ PROJECT LOCATION	DATE LET	UNIT/ QUANTITY	ENGR. EST.	AVERAGE BID	AWARDED BID
=====	612-00070	Reflector Strip (4 In)		Each	=====	=====	=====
NH0242-085		US 24 M.P. 291.38 to M.P. 296	02/27/20	411.00	30.00	56.46	51.35
NH050A-034		US50A PUEBLO WEST PURCELL INT	03/26/20	130.00	15.00	48.69	63.10
		WEIGHTED AVERAGE FOR THE FIRST QUARTER		541.00	26.40	52.91	54.17
		WEIGHTED AVERAGE FOR THE YEAR		541.00	26.40	52.91	54.17
=====	612-00081	Delin (PM) (Ty I)		Each	=====	=====	=====
STR092A-030		SH92 MP 31.748-48.5, DELTA AND	04/02/20	8.00	60.00	59.85	55.00
		WEIGHTED AVERAGE FOR THE SECOND QUARTER		8.00	60.00	59.85	55.00
		WEIGHTED AVERAGE FOR THE YEAR		8.00	60.00	59.85	55.00
=====	612-00101	Delin (Drv Conc Inst) (Ty I)		Each	=====	=====	=====
STA0142-066		SH 14 New Raymer West	01/09/20	324.00	115.00	110.76	102.04
NHPP0343-041		I-76 & US 34 FT. MORGAN AREA	01/09/20	561.00	105.00	117.41	125.00
STA006A-067		SH 6 Merino to Atwood	01/16/20	269.00	115.00	118.81	120.00
NHPP0091-044		SH 9 FRISCO MAIN ST TO IRON S	03/05/20	189.00	100.00	138.50	240.00
		WEIGHTED AVERAGE FOR THE FIRST QUARTER		1,343.00	108.71	118.41	134.64
		WEIGHTED AVERAGE FOR THE YEAR		1,343.00	108.71	118.41	134.64
=====	612-00102	Delin (Drv Conc Inst) (Ty II)		Each	=====	=====	=====
NHPP0343-041		I-76 & US 34 FT. MORGAN AREA	01/09/20	151.00	107.00	121.45	130.00
STA006A-067		SH 6 Merino to Atwood	01/16/20	6.00	118.00	124.11	125.00
NHPP0091-044		SH 9 FRISCO MAIN ST TO IRON S	03/05/20	123.00	100.00	142.83	240.00
		WEIGHTED AVERAGE FOR THE FIRST QUARTER		280.00	104.16	130.95	178.21
		WEIGHTED AVERAGE FOR THE YEAR		280.00	104.16	130.95	178.21
=====	612-00103	Delin (Drv Conc Inst) (Ty III)		Each	=====	=====	=====
STA0142-066		SH 14 New Raymer West	01/09/20	30.00	120.00	116.29	107.14

COLORADO DEPARTMENT OF TRANSPORTATION
ITEM UNIT COSTS BY PROJECTS -- 2020 COST DATA

10:58 Friday, October 2, 2020 226

PROJECT NUMBER	ITEM NUMBER/ PROJECT LOCATION	ITEM DESCRIPTION/ PROJECT LOCATION	DATE LET	UNIT/ QUANTITY	ENGR. EST.	AVERAGE BID	AWARDED BID
=====	612-00103	Delin (Drv Conc Inst) (Ty III)		Each =====			
NHPP0343-041		I-76 & US 34 FT. MORGAN AREA	01/09/20	99.00	111.00	126.82	136.00
STA006A-067		SH 6 Merino to Atwood	01/16/20	20.00	120.00	129.41	130.00
		WEIGHTED AVERAGE FOR THE FIRST QUARTER		149.00	114.02	124.28	129.38
		WEIGHTED AVERAGE FOR THE YEAR		149.00	114.02	124.28	129.38
=====	612-00111	Delin (Drv) (Ty I)		Each =====			
STA059A-036		SH 59 SEIBERT TO COPE	02/06/20	298.00	100.00	73.00	66.00
STR2871-038		US 287 Passing Lanes Springfi	03/05/20	44.00	90.00	86.56	76.05
		WEIGHTED AVERAGE FOR THE FIRST QUARTER		342.00	98.71	74.74	67.29
		WEIGHTED AVERAGE FOR THE YEAR		342.00	98.71	74.74	67.29
=====	612-00112	Delin (Drv) (Ty II)		Each =====			
STR2871-038		US 287 Passing Lanes Springfi	03/05/20	20.00	90.00	92.34	81.90
		WEIGHTED AVERAGE FOR THE FIRST QUARTER		20.00	90.00	92.34	81.90
		WEIGHTED AVERAGE FOR THE YEAR		20.00	90.00	92.34	81.90
=====	612-00113	Delin (Drv) (Ty III)		Each =====			
STA059A-036		SH 59 SEIBERT TO COPE	02/06/20	30.00	90.00	78.50	71.00
STR2871-038		US 287 Passing Lanes Springfi	03/05/20	8.00	90.00	98.12	87.75
		WEIGHTED AVERAGE FOR THE FIRST QUARTER		38.00	90.00	82.63	74.53
		WEIGHTED AVERAGE FOR THE YEAR		38.00	90.00	82.63	74.53
=====	612-00260	Loc Mark (Fib Opt) (Dome)		Each =====			
FSA0253-262		I-25 SB BOTTLENECK I-76 TO I-	01/09/20	3.00	165.00	131.06	120.00
ITS0761-231		ITS FIBER AND CAMERAS ON I-76	02/06/20	152.00	125.00	82.96	110.00
NHPP0091-044		SH 9 FRISCO MAIN ST TO IRON S	03/05/20	8.00	100.00	383.33	370.00
		WEIGHTED AVERAGE FOR THE FIRST QUARTER		163.00	124.51	92.59	122.94

COLORADO DEPARTMENT OF TRANSPORTATION
ITEM UNIT COSTS BY PROJECTS -- 2020 COST DATA

10:58 Friday, October 2, 2020 227

PROJECT NUMBER	ITEM NUMBER/ PROJECT LOCATION	ITEM DESCRIPTION/ PROJECT LOCATION	DATE LET	UNIT/ QUANTITY	ENGR. EST.	AVERAGE BID	AWARDED BID
===== 612-00260		Loc Mark (Fib Opt) (Dome)		Each	=====		
IM0761-226		I76/SH52 Interchange	04/02/20	8.00	75.00	168.13	183.38
CC0852-106		US-85 LOUVIERS TO MP 191.75	04/23/20	11.00	350.00	79.09	71.50
FBR0852-108		US-85 BETWEEN LOUVIERS AND MP					
ITS SW02-304		ITS FIBER TO STATE BUILDINGS	05/14/20	107.00	80.00	198.75	166.00
ITS SW02-303		R1: US 285, SH 83 R2: SH 83,	05/28/20	104.00	120.00	70.96	60.00
ITSSW01-719		FY 20 ITS CAPITAL REPLACEMENT	06/11/20	1.00	250.00	112.50	125.00
		WEIGHTED AVERAGE FOR THE SECOND QUARTER		231.00	111.43	126.66	114.20
		WEIGHTED AVERAGE FOR THE YEAR		394.00	116.84	112.34	117.82
===== 612-00270		Loc Mark (Util) (Flat Slat)		Each	=====		
FSA0253-262		I-25 SB BOTTLENECK I-76 TO I-	01/09/20	3.00	100.00	125.87	115.00
FSA0341-097		US 34 & MACGREGOR INTERSECTIO	01/09/20	6.00	150.00	65.00	65.00
ITS0761-231		ITS FIBER AND CAMERAS ON I-76	02/06/20	9.00	125.00	68.42	85.00
		WEIGHTED AVERAGE FOR THE FIRST QUARTER		18.00	129.17	76.70	83.33
ITSSW01-719		FY 20 ITS CAPITAL REPLACEMENT	06/11/20	41.00	250.00	75.00	100.00
		WEIGHTED AVERAGE FOR THE SECOND QUARTER		41.00	250.00	75.00	100.00
		WEIGHTED AVERAGE FOR THE YEAR		59.00	213.14	75.72	94.92
===== 612-15000		Inst Marker		Each	=====		
NHPP0253-276		I-25 EXPRESS LANES SEGMENT 5	05/15/20	12.00	100.00	123.05	123.05
		WEIGHTED AVERAGE FOR THE SECOND QUARTER		12.00	100.00	123.05	123.05
		WEIGHTED AVERAGE FOR THE YEAR		12.00	100.00	123.05	123.05
===== 613-00100		1 In Elec Cond		Lin Foot	=====		
NH050A-034		US50A PUEBLO WEST PURCELL INT	03/26/20	20.00	10.00	18.48	13.80
		WEIGHTED AVERAGE FOR THE FIRST QUARTER		20.00	10.00	18.48	13.80

COLORADO DEPARTMENT OF TRANSPORTATION
 ITEM UNIT COSTS BY PROJECTS -- 2020 COST DATA

10:58 Friday, October 2, 2020 228

PROJECT NUMBER	ITEM NUMBER/ PROJECT LOCATION	ITEM DESCRIPTION/ PROJECT LOCATION	DATE LET	UNIT/ QUANTITY	ENGR. EST.	AVERAGE BID	AWARDED BID
=====	613-00100	1 In Elec Cond		Lin Foot	=====		
C1601-082		Hawkins Signal and Curb Ramps	04/30/20	469.00	20.00	15.33	15.00
		WEIGHTED AVERAGE FOR THE SECOND QUARTER		469.00	20.00	15.33	15.00
		WEIGHTED AVERAGE FOR THE YEAR		489.00	19.59	15.65	14.95
=====	613-00102	1 In Elec Cond (GRC) (Special)		Lin Foot	=====		
NHPP0091-044		SH 9 FRISCO MAIN ST TO IRON S	03/05/20	115.00	15.00	50.67	49.00
		WEIGHTED AVERAGE FOR THE FIRST QUARTER		115.00	15.00	50.67	49.00
		WEIGHTED AVERAGE FOR THE YEAR		115.00	15.00	50.67	49.00
=====	613-00200	2 In Elec Cond		Lin Foot	=====		
FSA0253-262		I-25 SB BOTTLENECK I-76 TO I-	01/09/20	2,100.00	12.00	10.87	10.00
NHPP0253-265		I-25 AT ERIE PARKWAY ON AND O	01/09/20	100.00	17.00	20.75	14.25
BR0343-040		US 34 REPUBLICAN RIVER BRIDGE	01/16/20	656.00	17.00	13.55	17.00
FBR0343-043		US 34 D-28-P STRUCTURE REPLAC					
ITS0761-231		ITS FIBER AND CAMERAS ON I-76	02/06/20	60.00	35.00	53.91	45.00
		WEIGHTED AVERAGE FOR THE FIRST QUARTER		2,916.00	13.77	13.30	12.44
IM0761-226		I76/SH52 Interchange	04/02/20	232.00	12.00	15.20	16.96
C1601-082		Hawkins Signal and Curb Ramps	04/30/20	440.00	30.00	21.00	22.00
FBR0343-042		US 34 D-27-G STRUCTURE REPLAC	05/07/20	274.00	17.00	21.57	20.00
ITS SW02-304		ITS FIBER TO STATE BUILDINGS	05/14/20	1,430.00	80.00	42.50	28.00
ITS SW02-303		R1: US 285, SH 83 R2: SH 83,	05/28/20	1,170.00	20.00	41.35	50.00
FSAR400-356		FY 20 SIGNAL POLE REPLACEMENT	06/11/20	340.00	20.00	15.00	15.00
		WEIGHTED AVERAGE FOR THE SECOND QUARTER		3,886.00	42.52	33.66	31.58
		WEIGHTED AVERAGE FOR THE YEAR		6,802.00	30.20	26.01	23.38
=====	613-00206	2 In Elec Cond (Bored)		Lin Foot	=====		
FSA0253-262		I-25 SB BOTTLENECK I-76 TO I-	01/09/20	600.00	25.00	24.49	22.50

COLORADO DEPARTMENT OF TRANSPORTATION
ITEM UNIT COSTS BY PROJECTS -- 2020 COST DATA

10:58 Friday, October 2, 2020 229

PROJECT NUMBER	ITEM NUMBER/ PROJECT LOCATION	ITEM DESCRIPTION/ PROJECT LOCATION	DATE LET	UNIT/ QUANTITY	ENGR. EST.	AVERAGE BID	AWARDED BID
=====	613-00206	2 In Elec Cond (Bored)		Lin Foot	=====	=====	=====
NHPP0253-265		I-25 AT ERIE PARKWAY ON AND O	01/09/20	550.00	25.00	18.67	15.00
ITS0761-231		ITS FIBER AND CAMERAS ON I-76	02/06/20	22,775.00	11.00	9.49	5.74
C0402-094		US 40 GRAND COUNTY SIGNAL REP	02/27/20	505.00	30.00	69.00	23.00
NH050A-034		US50A PUEBLO WEST PURCELL INT	03/26/20	8,855.00	15.50	20.15	21.50
HPP 0501-067		US 50 AND SH 92 DELTA INTERSE	03/26/20	675.00	25.00	25.98	27.00
SHE 0703-461		I-70 and Kipling North Phase	03/26/20	620.00	22.00	26.68	25.00
		WEIGHTED AVERAGE FOR THE FIRST QUARTER		34,580.00	13.37	14.31	11.23
IM0761-226		I76/SH52 Interchange	04/02/20	2,350.00	27.00	17.54	18.39
CC0852-106		US-85 LOUVIERS TO MP 191.75	04/23/20	3,400.00	15.00	12.45	12.10
FBR0852-108		US-85 BETWEEN LOUVIERS AND MP					
C1211-090		SH-121 & 29th Ave / SH-121 &	04/23/20	2,700.00	18.00	15.20	13.00
C1601-082		Hawkins Signal and Curb Ramps	04/30/20	540.00	50.00	52.67	56.00
FSA1602-159		US 160 AND SH 17 INTERSECTION	04/30/20	70.00	20.00	78.67	70.00
NHPPR100-303		LONG MAST ARM SIGNALS PROJECT	05/07/20	1,505.00	17.00	19.00	14.00
ITS SW02-304		ITS FIBER TO STATE BUILDINGS	05/14/20	43,820.00	22.50	13.35	11.47
ITS SW02-303		R1: US 285, SH 83 R2: SH 83,	05/28/20	83,155.00	12.25	12.51	10.14
ITSSW01-719		FY 20 ITS CAPITAL REPLACEMENT	06/11/20	390.00	57.00	41.50	50.00
FSAR400-356		FY 20 SIGNAL POLE REPLACEMENT	06/11/20	690.00	23.00	17.17	20.00
SHE016A-043		SH 21 & 16 SIGNALS PROJECT	06/18/20	7,364.00	20.00	13.71	11.55
		WEIGHTED AVERAGE FOR THE SECOND QUARTER		145,984.00	16.49	13.14	11.23
		WEIGHTED AVERAGE FOR THE YEAR		180,564.00	15.89	13.40	11.23
=====	613-00207	2 In Elec Cond (Bridge) (Spec)		Lin Foot	=====	=====	=====
NH050A-034		US50A PUEBLO WEST PURCELL INT	03/26/20	280.00	15.00	19.15	16.00
		WEIGHTED AVERAGE FOR THE FIRST QUARTER		280.00	15.00	19.15	16.00
		WEIGHTED AVERAGE FOR THE YEAR		280.00	15.00	19.15	16.00
=====	613-00208	Inst 2 In Elec Cond (Bored)		Lin Foot	=====	=====	=====
NHPP0253-276		I-25 EXPRESS LANES SEGMENT 5	05/15/20	285.00	28.00	28.09	28.09
		WEIGHTED AVERAGE FOR THE SECOND QUARTER		285.00	28.00	28.09	28.09
		WEIGHTED AVERAGE FOR THE YEAR		285.00	28.00	28.09	28.09

COLORADO DEPARTMENT OF TRANSPORTATION
ITEM UNIT COSTS BY PROJECTS -- 2020 COST DATA

10:58 Friday, October 2, 2020 230

PROJECT NUMBER	ITEM NUMBER/ PROJECT LOCATION	ITEM DESCRIPTION/ PROJECT LOCATION	DATE LET	UNIT/ QUANTITY	ENGR. EST.	AVERAGE BID	AWARDED BID
=====	613-00300	3 In Elec Cond		Lin Foot	=====		
NHPP0253-265		I-25 AT ERIE PARKWAY ON AND O	01/09/20	190.00	20.00	23.00	16.00
FSA0341-097		US 34 & MACGREGOR INTERSECTIO	01/09/20	116.00	32.00	38.00	38.00
		WEIGHTED AVERAGE FOR THE FIRST QUARTER		306.00	24.55	25.54	24.34
C1601-082		Hawkins Signal and Curb Ramps	04/30/20	230.00	30.00	25.23	27.70
FSAR400-356		FY 20 SIGNAL POLE REPLACEMENT	06/11/20	270.00	30.00	17.33	20.00
		WEIGHTED AVERAGE FOR THE SECOND QUARTER		500.00	30.00	20.97	23.54
		WEIGHTED AVERAGE FOR THE YEAR		806.00	27.93	22.40	23.84
=====	613-00306	3 In Elec Cond (Bored)		Lin Foot	=====		
NHPP0253-265		I-25 AT ERIE PARKWAY ON AND O	01/09/20	1,920.00	30.00	29.67	25.00
C0402-094		US 40 GRAND COUNTY SIGNAL REP	02/27/20	2,860.00	30.00	78.50	27.00
NHPP0091-044		SH 9 FRISCO MAIN ST TO IRON S	03/05/20	3,050.00	40.00	42.33	41.00
NH050A-034		US50A PUEBLO WEST PURCELL INT	03/26/20	860.00	26.00	21.54	23.00
HPP 0501-067		US 50 AND SH 92 DELTA INTERSE	03/26/20	2,320.00	35.00	28.13	30.00
SHE 0703-461		I-70 and Kipling North Phase	03/26/20	1,240.00	25.00	25.44	23.00
		WEIGHTED AVERAGE FOR THE FIRST QUARTER		12,250.00	32.65	37.64	30.05
IM0761-226		I76/SH52 Interchange	04/02/20	1,675.00	30.00	26.44	28.13
CC0852-106		US-85 LOUVIERS TO MP 191.75	04/23/20	1,250.00	21.00	24.94	24.20
FBR0852-108		US-85 BETWEEN LOUVIERS AND MP					
C1211-090		SH-121 & 29th Ave / SH-121 &	04/23/20	3,600.00	22.00	17.27	15.00
C1601-082		Hawkins Signal and Curb Ramps	04/30/20	350.00	50.00	64.00	61.00
FSA1602-159		US 160 AND SH 17 INTERSECTION	04/30/20	140.00	25.00	89.00	79.00
NHPPR100-303		LONG MAST ARM SIGNALS PROJECT	05/07/20	3,005.00	20.00	18.00	15.00
FSAR400-356		FY 20 SIGNAL POLE REPLACEMENT	06/11/20	1,280.00	25.00	18.67	20.00
SHE016A-043		SH 21 & 16 SIGNALS PROJECT	06/18/20	3,134.00	15.00	15.75	11.55
		WEIGHTED AVERAGE FOR THE SECOND QUARTER		14,434.00	21.88	21.29	18.75
		WEIGHTED AVERAGE FOR THE YEAR		26,684.00	26.82	27.51	23.94
=====	613-01075	3/4 In Elec Cond (P)		Lin Foot	=====		
NHPP0253-276		I-25 EXPRESS LANES SEGMENT 5	05/15/20	800.00	17.00	17.12	17.12
		WEIGHTED AVERAGE FOR THE SECOND QUARTER		800.00	17.00	17.12	17.12
		WEIGHTED AVERAGE FOR THE YEAR		800.00	17.00	17.12	17.12

COLORADO DEPARTMENT OF TRANSPORTATION
 ITEM UNIT COSTS BY PROJECTS -- 2020 COST DATA

10:58 Friday, October 2, 2020 231

PROJECT NUMBER	ITEM NUMBER/ PROJECT LOCATION	ITEM DESCRIPTION/ PROJECT LOCATION	DATE LET	UNIT/ QUANTITY	ENGR. EST.	AVERAGE BID	AWARDED BID
=====	613-01100	1 In Elec Cond (P)		Lin Foot	=====		
C0402-094		US 40 GRAND COUNTY SIGNAL REP	02/27/20	175.00	20.00	34.50	15.00
NHPP0091-044		SH 9 FRISCO MAIN ST TO IRON S	03/05/20	345.00	12.00	16.25	16.00
HPP 0501-067		US 50 AND SH 92 DELTA INTERSE	03/26/20	10.00	14.00	55.50	56.00
		WEIGHTED AVERAGE FOR THE FIRST QUARTER		530.00	14.68	21.35	16.42
IM0761-226		I76/SH52 Interchange	04/02/20	250.00	28.00	26.81	32.86
FSA1602-159		US 160 AND SH 17 INTERSECTION	04/30/20	100.00	10.00	12.33	11.00
		WEIGHTED AVERAGE FOR THE SECOND QUARTER		350.00	22.86	24.69	26.61
		WEIGHTED AVERAGE FOR THE YEAR		880.00	17.93	23.33	20.48
=====	613-01200	2 In Elec Cond (P)		Lin Foot	=====		
FSA0341-097		US 34 & MACGREGOR INTERSECTIO	01/09/20	707.00	20.00	34.00	34.00
ITS0761-231		ITS FIBER AND CAMERAS ON I-76	02/06/20	302,020.00	5.00	3.56	2.89
NHPP0702-359		I-70 No Name Tunnel Lighting	02/27/20	4,550.00	15.00	23.13	20.00
C0402-094		US 40 GRAND COUNTY SIGNAL REP	02/27/20	110.00	20.00	29.00	20.00
NHPP0091-044		SH 9 FRISCO MAIN ST TO IRON S	03/05/20	2,755.00	15.00	19.88	19.00
NH050A-034		US50A PUEBLO WEST PURCELL INT	03/26/20	27,659.00	11.00	14.19	16.00
HPP 0501-067		US 50 AND SH 92 DELTA INTERSE	03/26/20	80.00	16.00	22.50	23.00
SHE 0703-461		I-70 and Kipling North Phase	03/26/20	330.00	20.00	13.64	13.00
		WEIGHTED AVERAGE FOR THE FIRST QUARTER		338,211.00	5.76	5.20	4.41
IM0761-226		I76/SH52 Interchange	04/02/20	10,388.00	15.00	13.27	11.30
CC0852-106		US-85 LOUVIERS TO MP 191.75	04/23/20	9,850.00	12.00	9.50	9.35
FBR0852-108		US-85 BETWEEN LOUVIERS AND MP					
C1211-090		SH-121 & 29th Ave / SH-121 &	04/23/20	810.00	15.00	12.82	12.00
FSA1602-159		US 160 AND SH 17 INTERSECTION	04/30/20	330.00	12.00	18.00	16.00
NHPPR100-303		LONG MAST ARM SIGNALS PROJECT	05/07/20	435.00	12.00	12.33	13.00
ITS SW02-304		ITS FIBER TO STATE BUILDINGS	05/14/20	10,780.00	21.00	14.26	13.00
ITS SW02-303		R1: US 285, SH 83 R2: SH 83,	05/28/20	96,530.00	11.25	7.62	7.50
ITSSW01-719		FY 20 ITS CAPITAL REPLACEMENT	06/11/20	3,330.00	20.00	21.25	22.50
SHE016A-043		SH 21 & 16 SIGNALS PROJECT	06/18/20	250.00	18.00	13.22	11.10
		WEIGHTED AVERAGE FOR THE SECOND QUARTER		132,703.00	12.65	9.03	8.83
		WEIGHTED AVERAGE FOR THE YEAR		470,914.00	7.70	6.28	5.66

PROJECT NUMBER	ITEM NUMBER/ PROJECT LOCATION	ITEM DESCRIPTION/ PROJECT LOCATION	DATE LET	UNIT/ QUANTITY	ENGR. EST.	AVERAGE BID	AWARDED BID
=====	613-01201	2 In Elec Cond (P) (Spec)		Lin Foot	=====		
NHPP0702-359		I-70 No Name Tunnel Lighting	02/27/20	4,010.00	25.00	38.48	40.00
	WEIGHTED AVERAGE FOR THE FIRST QUARTER			4,010.00	25.00	38.48	40.00
	WEIGHTED AVERAGE FOR THE YEAR			4,010.00	25.00	38.48	40.00
=====	613-01202	Inst 2 In Elec Cond (P)		Lin Foot	=====		
NHPP0253-276		I-25 EXPRESS LANES SEGMENT 5	05/15/20	1,680.00	16.95	16.32	16.32
	WEIGHTED AVERAGE FOR THE SECOND QUARTER			1,680.00	16.95	16.32	16.32
	WEIGHTED AVERAGE FOR THE YEAR			1,680.00	16.95	16.32	16.32
=====	613-01300	3 In Elec Cond (P)		Lin Foot	=====		
NHPP0702-359		I-70 No Name Tunnel Lighting	02/27/20	380.00	15.00	36.52	25.00
C0402-094		US 40 GRAND COUNTY SIGNAL REP	02/27/20	260.00	22.00	37.00	30.00
NHPP0091-044		SH 9 FRISCO MAIN ST TO IRON S	03/05/20	729.00	35.00	26.00	25.00
NH050A-034		US50A PUEBLO WEST PURCELL INT	03/26/20	927.00	13.00	16.94	18.00
HPP 0501-067		US 50 AND SH 92 DELTA INTERSE	03/26/20	140.00	18.00	24.60	25.00
SHE 0703-461		I-70 and Kipling North Phase	03/26/20	660.00	20.00	14.48	14.00
	WEIGHTED AVERAGE FOR THE FIRST QUARTER			3,096.00	20.90	20.49	20.98
IM0761-226		I76/SH52 Interchange	04/02/20	50.00	36.00	60.39	68.90
CC0852-106		US-85 LOUVIERS TO MP 191.75	04/23/20	150.00	12.00	27.02	26.40
FBR0852-108		US-85 BETWEEN LOUVIERS AND MP					
C1211-090		SH-121 & 29th Ave / SH-121 &	04/23/20	900.00	17.00	14.57	14.00
FSA1602-159		US 160 AND SH 17 INTERSECTION	04/30/20	260.00	15.00	25.67	23.00
NHPPR100-303		LONG MAST ARM SIGNALS PROJECT	05/07/20	975.00	15.00	14.25	13.75
SHE016A-043		SH 21 & 16 SIGNALS PROJECT	06/18/20	260.00	17.00	15.87	12.34
	WEIGHTED AVERAGE FOR THE SECOND QUARTER			2,595.00	16.13	18.93	16.42
	WEIGHTED AVERAGE FOR THE YEAR			5,691.00	18.72	19.90	18.90
=====	613-01400	4 In Elec Cond (P)		Lin Foot	=====		
NHPP0702-359		I-70 No Name Tunnel Lighting	02/27/20	220.00	50.00	46.80	30.00
	WEIGHTED AVERAGE FOR THE FIRST QUARTER			220.00	50.00	46.80	30.00
	WEIGHTED AVERAGE FOR THE YEAR			220.00	50.00	46.80	30.00

COLORADO DEPARTMENT OF TRANSPORTATION
 ITEM UNIT COSTS BY PROJECTS -- 2020 COST DATA

10:58 Friday, October 2, 2020 233

PROJECT NUMBER	ITEM NUMBER/ PROJECT LOCATION	ITEM DESCRIPTION/ PROJECT LOCATION	DATE LET	UNIT/ QUANTITY	ENGR. EST.	AVERAGE BID	AWARDED BID
=====	613-03491	Elec Cond (P) (Mult)		Lin Foot	=====		
NHPP0253-276		I-25 EXPRESS LANES SEGMENT 5	05/15/20	3,130.00	25.00	25.15	25.15
	WEIGHTED AVERAGE FOR THE SECOND QUARTER			3,130.00	25.00	25.15	25.15
	WEIGHTED AVERAGE FOR THE YEAR			3,130.00	25.00	25.15	25.15
=====	613-03492	Elec Cond (P) (Mult) (Bored)		Lin Foot	=====		
NHPP0253-276		I-25 EXPRESS LANES SEGMENT 5	05/15/20	2,735.00	41.00	41.20	41.20
	WEIGHTED AVERAGE FOR THE SECOND QUARTER			2,735.00	41.00	41.20	41.20
	WEIGHTED AVERAGE FOR THE YEAR			2,735.00	41.00	41.20	41.20
=====	613-03500	Elec Cond (P) (Mult) (Spec)		Lin Foot	=====		
FSA1602-159		US 160 AND SH 17 INTERSECTION	04/30/20	2,200.00	12.00	199.00	177.00
	WEIGHTED AVERAGE FOR THE SECOND QUARTER			2,200.00	12.00	199.00	177.00
	WEIGHTED AVERAGE FOR THE YEAR			2,200.00	12.00	199.00	177.00
=====	613-04100	Elect System Mods		LUMP SUM	=====		
NHPP0702-359		I-70 No Name Tunnel Lighting	02/27/20	1.00	30000.00	36367.06	5000.00
NH050A-034		US50A PUEBLO WEST PURCELL INT	03/26/20	1.00	5000.00	4299.74	3450.00
	WEIGHTED AVERAGE FOR THE FIRST QUARTER			2.00	17500.00	14988.84	4225.00
	WEIGHTED AVERAGE FOR THE YEAR			2.00	17500.00	14988.84	4225.00
=====	613-07000	Pull Box (Spec)		Each	=====		
C0402-094		US 40 GRAND COUNTY SIGNAL REP	02/27/20	4.00	800.00	825.00	650.00
HPP 0501-067		US 50 AND SH 92 DELTA INTERSE	03/26/20	7.00	1500.00	872.00	896.00
	WEIGHTED AVERAGE FOR THE FIRST QUARTER			11.00	1245.45	854.91	806.55
NHPP0253-276		I-25 EXPRESS LANES SEGMENT 5	05/15/20	26.00	734.62	735.63	735.63
	WEIGHTED AVERAGE FOR THE SECOND QUARTER			26.00	734.62	735.63	735.63
	WEIGHTED AVERAGE FOR THE YEAR			37.00	886.49	790.30	756.71

COLORADO DEPARTMENT OF TRANSPORTATION
ITEM UNIT COSTS BY PROJECTS -- 2020 COST DATA

10:58 Friday, October 2, 2020 234

PROJECT NUMBER	ITEM NUMBER/ PROJECT LOCATION	ITEM DESCRIPTION/ PROJECT LOCATION	DATE LET	UNIT/ QUANTITY	ENGR. EST.	AVERAGE BID	AWARDED BID
===== 613-07001 Type One Pull Box Each =====							
FSA0253-262		I-25 SB BOTTLENECK I-76 TO I-	01/09/20	4.00	1000.00	944.97	865.00
NHPP0702-359		I-70 No Name Tunnel Lighting	02/27/20	18.00	1000.00	646.25	500.00
NHPP0091-044		SH 9 FRISCO MAIN ST TO IRON S	03/05/20	34.00	800.00	985.00	950.00
		WEIGHTED AVERAGE FOR THE FIRST QUARTER		56.00	878.57	851.29	799.29
=====							
IM0761-226		I76/SH52 Interchange	04/02/20	15.00	800.00	723.00	700.66
C1211-090		SH-121 & 29th Ave / SH-121 &	04/23/20	12.00	850.00	963.42	825.00
NHPP0253-276		I-25 EXPRESS LANES SEGMENT 5	05/15/20	1.00	1900.00	1872.50	1872.50
SHE016A-043		SH 21 & 16 SIGNALS PROJECT	06/18/20	8.00	900.00	750.10	630.50
		WEIGHTED AVERAGE FOR THE SECOND QUARTER		36.00	869.44	782.83	759.07
		WEIGHTED AVERAGE FOR THE YEAR		92.00	875.00	817.43	783.55
=====							
===== 613-07002 Type Two Pull Box Each =====							
NHPP0253-265		I-25 AT ERIE PARKWAY ON AND O	01/09/20	2.00	1000.00	1135.00	1290.00
NHPP0702-359		I-70 No Name Tunnel Lighting	02/27/20	4.00	1000.00	828.38	625.00
STRR300-249		Grand and Jackson Counties AD	03/05/20	8.00	1200.00	1665.00	1500.00
CC080-037		VARIOUS ADA RAMPS ALONG NORTH	03/05/20	4.00	1200.00	1270.00	1000.00
		WEIGHTED AVERAGE FOR THE FIRST QUARTER		18.00	1133.33	1295.87	1171.11
=====							
IM0761-226		I76/SH52 Interchange	04/02/20	21.00	1200.00	1073.81	1016.54
ITSSW01-719		FY 20 ITS CAPITAL REPLACEMENT	06/11/20	21.00	1500.00	900.00	900.00
SHE016A-043		SH 21 & 16 SIGNALS PROJECT	06/18/20	8.00	800.00	899.35	898.25
		WEIGHTED AVERAGE FOR THE SECOND QUARTER		50.00	1262.00	1011.46	948.67
		WEIGHTED AVERAGE FOR THE YEAR		68.00	1227.94	1072.05	1007.55
=====							
===== 613-07003 Type Three Pull Box Each =====							
FSA0253-262		I-25 SB BOTTLENECK I-76 TO I-	01/09/20	1.00	1100.00	1217.45	1115.00
NHPP0253-265		I-25 AT ERIE PARKWAY ON AND O	01/09/20	16.00	1300.00	1545.00	1725.00

COLORADO DEPARTMENT OF TRANSPORTATION
 ITEM UNIT COSTS BY PROJECTS -- 2020 COST DATA

10:58 Friday, October 2, 2020 235

PROJECT NUMBER	ITEM NUMBER/ PROJECT LOCATION	ITEM DESCRIPTION/ PROJECT LOCATION	DATE LET	UNIT/ QUANTITY	ENGR. EST.	AVERAGE BID	AWARDED BID
=====	613-07003	Type Three Pull Box		Each =====			
HPP 0501-067		US 50 AND SH 92 DELTA INTERSE	03/26/20	3.00	1400.00	1090.00	1120.00
		WEIGHTED AVERAGE FOR THE FIRST QUARTER		20.00	1305.00	1479.87	1603.75
IM0761-226		I76/SH52 Interchange	04/02/20	3.00	800.00	1313.59	1217.94
CC0852-106		US-85 LOUVIERS TO MP 191.75	04/23/20	1.00	1500.00	1339.51	1303.50
FBR0852-108		US-85 BETWEEN LOUVIERS AND MP					
FSAR400-356		FY 20 SIGNAL POLE REPLACEMENT	06/11/20	8.00	1100.00	1042.67	965.00
SHE016A-043		SH 21 & 16 SIGNALS PROJECT	06/18/20	9.00	780.00	1107.45	1239.00
		WEIGHTED AVERAGE FOR THE SECOND QUARTER		21.00	939.05	1154.70	1134.68
		WEIGHTED AVERAGE FOR THE YEAR		41.00	1117.56	1274.28	1363.50
=====	613-07004	Type Four Pull Box		Each =====			
NHPP0253-265		I-25 AT ERIE PARKWAY ON AND O	01/09/20	2.00	1750.00	2626.67	2345.00
C0402-094		US 40 GRAND COUNTY SIGNAL REP	02/27/20	6.00	2000.00	1687.50	1275.00
NHPP0091-044		SH 9 FRISCO MAIN ST TO IRON S	03/05/20	6.00	1300.00	2163.33	2100.00
NH050A-034		US50A PUEBLO WEST PURCELL INT	03/26/20	13.00	1400.00	1039.58	1021.00
HPP 0501-067		US 50 AND SH 92 DELTA INTERSE	03/26/20	3.00	1600.00	1635.00	1680.00
SHE 0703-461		I-70 and Kipling North Phase	03/26/20	20.00	1400.00	1515.80	1425.00
		WEIGHTED AVERAGE FOR THE FIRST QUARTER		50.00	1486.00	1400.23	1435.06
IM0761-226		I76/SH52 Interchange	04/02/20	2.00	1500.00	1886.63	1743.70
CC0852-106		US-85 LOUVIERS TO MP 191.75	04/23/20	4.00	1500.00	2015.37	1980.00
FBR0852-108		US-85 BETWEEN LOUVIERS AND MP					
C1211-090		SH-121 & 29th Ave / SH-121 &	04/23/20	18.00	1500.00	1486.90	1385.00
NHPPR100-303		LONG MAST ARM SIGNALS PROJECT	05/07/20	14.00	1300.00	1602.33	1520.00
FSAR400-356		FY 20 SIGNAL POLE REPLACEMENT	06/11/20	5.00	1400.00	1572.00	1485.00
SHE016A-043		SH 21 & 16 SIGNALS PROJECT	06/18/20	1.00	950.00	1426.20	1608.00
		WEIGHTED AVERAGE FOR THE SECOND QUARTER		44.00	1412.50	1661.77	1514.78
		WEIGHTED AVERAGE FOR THE YEAR		94.00	1451.60	1504.07	1472.38
=====	613-07005	Type Five Pull Box		Each =====			
FSA0253-262		I-25 SB BOTTLENECK I-76 TO I-	01/09/20	3.00	1800.00	2086.52	1910.00

COLORADO DEPARTMENT OF TRANSPORTATION
ITEM UNIT COSTS BY PROJECTS -- 2020 COST DATA

10:58 Friday, October 2, 2020 236

PROJECT NUMBER	ITEM NUMBER/ PROJECT LOCATION	ITEM DESCRIPTION/ PROJECT LOCATION	DATE LET	UNIT/ QUANTITY	ENGR. EST.	AVERAGE BID	AWARDED BID
=====	613-07005	Type Five Pull Box		Each =====			
C0402-094		US 40 GRAND COUNTY SIGNAL REP	02/27/20	2.00	2600.00	2625.00	1650.00
NHPP0091-044		SH 9 FRISCO MAIN ST TO IRON S	03/05/20	2.00	1500.00	2816.67	2700.00
NH050A-034		US50A PUEBLO WEST PURCELL INT	03/26/20	4.00	2400.00	1215.65	1160.00
HPP 0501-067		US 50 AND SH 92 DELTA INTERSE	03/26/20	1.00	1800.00	2180.00	2240.00
SHE 0703-461		I-70 and Kipling North Phase	03/26/20	2.00	1500.00	2170.60	2025.00
		WEIGHTED AVERAGE FOR THE FIRST QUARTER		14.00	2000.00	1764.22	1811.43
IM0761-226		I76/SH52 Interchange	04/02/20	1.00	2500.00	2362.29	2229.18
CC0852-106		US-85 LOUVIERS TO MP 191.75	04/23/20	2.00	1500.00	2580.91	2513.50
FBR0852-108		US-85 BETWEEN LOUVIERS AND MP					
C1211-090		SH-121 & 29th Ave / SH-121 &	04/23/20	3.00	1750.00	2145.82	2130.00
NHPPR100-303		LONG MAST ARM SIGNALS PROJECT	05/07/20	4.00	1800.00	2030.33	2134.00
SHE016A-043		SH 21 & 16 SIGNALS PROJECT	06/18/20	6.00	2200.00	1734.25	2056.00
		WEIGHTED AVERAGE FOR THE SECOND QUARTER		16.00	1946.88	2074.79	2157.39
		WEIGHTED AVERAGE FOR THE YEAR		30.00	1971.67	1931.97	1995.94
=====	613-07010	Pull Box (Surf Mtd)		Each =====			
ITS0761-231		ITS FIBER AND CAMERAS ON I-76	02/06/20	2.00	1750.00	935.10	950.00
NHPP0702-359		I-70 No Name Tunnel Lighting	02/27/20	11.00	2000.00	1392.73	1000.00
NH050A-034		US50A PUEBLO WEST PURCELL INT	03/26/20	8.00	2500.00	835.67	711.00
		WEIGHTED AVERAGE FOR THE FIRST QUARTER		21.00	2166.67	1051.81	885.14
ITS SW02-304		ITS FIBER TO STATE BUILDINGS	05/14/20	36.00	1500.00	1675.50	612.00
		WEIGHTED AVERAGE FOR THE SECOND QUARTER		36.00	1500.00	1675.50	612.00
		WEIGHTED AVERAGE FOR THE YEAR		57.00	1745.61	1394.60	712.63
=====	613-07011	Pull Box (11"x18"x12")		Each =====			
FSA0341-097		US 34 & MACGREGOR INTERSECTIO	01/09/20	8.00	800.00	2200.00	2200.00
ITS0761-231		ITS FIBER AND CAMERAS ON I-76	02/06/20	9.00	950.00	900.67	756.00
NHPP0091-044		SH 9 FRISCO MAIN ST TO IRON S	03/05/20	6.00	1200.00	985.00	950.00

COLORADO DEPARTMENT OF TRANSPORTATION
 ITEM UNIT COSTS BY PROJECTS -- 2020 COST DATA

10:58 Friday, October 2, 2020 237

PROJECT NUMBER	ITEM NUMBER/ PROJECT LOCATION	ITEM DESCRIPTION/ PROJECT LOCATION	DATE LET	UNIT/ QUANTITY	ENGR. EST.	AVERAGE BID	AWARDED BID
===== 613-07011		Pull Box (11"x18"x12")		Each =====			
NH050A-034		US50A PUEBLO WEST PURCELL INT	03/26/20	26.00	1500.00	568.85	568.00
	WEIGHTED AVERAGE FOR THE FIRST QUARTER			49.00	1247.96	695.99	915.76
IM0761-226		I76/SH52 Interchange	04/02/20	1.00	750.00	722.29	700.66
NHPP0253-276		I-25 EXPRESS LANES SEGMENT 5	05/15/20	1.00	1900.00	1926.00	1926.00
	WEIGHTED AVERAGE FOR THE SECOND QUARTER			2.00	1325.00	872.75	1313.33
	WEIGHTED AVERAGE FOR THE YEAR			51.00	1250.98	700.92	931.35
===== 613-07023		Pull Box (24"x36"x24")		Each =====			
FSA0341-097		US 34 & MACGREGOR INTERSECTIO	01/09/20	2.00	1750.00	2800.00	2800.00
ITS0761-231		ITS FIBER AND CAMERAS ON I-76	02/06/20	6.00	1600.00	1797.92	1564.00
NH050A-034		US50A PUEBLO WEST PURCELL INT	03/26/20	39.00	1800.00	1021.15	1021.00
	WEIGHTED AVERAGE FOR THE FIRST QUARTER			47.00	1772.34	1099.23	1166.02
IM0761-226		I76/SH52 Interchange	04/02/20	6.00	1500.00	1883.06	1743.70
C1601-082		Hawkins Signal and Curb Ramps	04/30/20	1.00	2500.00	4154.67	2600.00
ITS SW02-304		ITS FIBER TO STATE BUILDINGS	05/14/20	104.00	2000.00	1673.75	1854.00
NHPP0253-276		I-25 EXPRESS LANES SEGMENT 5	05/15/20	1.00	2400.00	2354.00	2354.00
ITS SW02-303		R1: US 285, SH 83 R2: SH 83,	05/28/20	80.00	1900.00	1482.55	1500.00
ITSSW01-719		FY 20 ITS CAPITAL REPLACEMENT	06/11/20	5.00	2500.00	1650.00	1600.00
	WEIGHTED AVERAGE FOR THE SECOND QUARTER			197.00	1961.42	1605.17	1706.76
	WEIGHTED AVERAGE FOR THE YEAR			244.00	1925.00	1462.04	1602.60
===== 613-07024		Pull Box (24"x24"x8")		Each =====			
NHPP0702-359		I-70 No Name Tunnel Lighting	02/27/20	25.00	1000.00	1364.56	1385.00
	WEIGHTED AVERAGE FOR THE FIRST QUARTER			25.00	1000.00	1364.56	1385.00
	WEIGHTED AVERAGE FOR THE YEAR			25.00	1000.00	1364.56	1385.00
===== 613-07027		Pull Box (28"x28"x12")		Each =====			
NHPP0091-044		SH 9 FRISCO MAIN ST TO IRON S	03/05/20	3.00	3000.00	2163.33	2100.00
	WEIGHTED AVERAGE FOR THE FIRST QUARTER			3.00	3000.00	2163.33	2100.00
	WEIGHTED AVERAGE FOR THE YEAR			3.00	3000.00	2163.33	2100.00

PROJECT NUMBER	ITEM NUMBER/ PROJECT LOCATION	ITEM DESCRIPTION/ PROJECT LOCATION	DATE LET	UNIT/ QUANTITY	ENGR. EST.	AVERAGE BID	AWARDED BID
===== 613-07040		Pull Box (30"x48"x24")		Each	=====	=====	=====
ITS0761-231		ITS FIBER AND CAMERAS ON I-76	02/06/20	140.00	1750.00	2046.57	1831.00
NHPP0091-044		SH 9 FRISCO MAIN ST TO IRON S	03/05/20	1.00	3000.00	2816.67	2700.00
NH050A-034		US50A PUEBLO WEST PURCELL INT	03/26/20	22.00	3000.00	1043.57	993.00
		WEIGHTED AVERAGE FOR THE FIRST QUARTER		163.00	1926.38	1848.37	1723.23
CC0852-106		US-85 LOUVIERS TO MP 191.75	04/23/20	4.00	2500.00	2580.91	2513.50
FBR0852-108		US-85 BETWEEN LOUVIERS AND MP					
NHPPR100-303		LONG MAST ARM SIGNALS PROJECT	05/07/20	2.00	2500.00	2102.33	1985.00
ITS SW02-304		ITS FIBER TO STATE BUILDINGS	05/14/20	6.00	2200.00	2340.25	2568.00
ITS SW02-303		R1: US 285, SH 83 R2: SH 83,	05/28/20	21.00	2900.00	1861.91	1800.00
		WEIGHTED AVERAGE FOR THE SECOND QUARTER		33.00	2700.00	2077.07	2037.33
		WEIGHTED AVERAGE FOR THE YEAR		196.00	2056.63	1884.88	1776.11
===== 613-07060		Pull Box (18"x30"x18") Deep		Each	=====	=====	=====
C1601-082		Hawkins Signal and Curb Ramps	04/30/20	25.00	1500.00	1650.33	1100.00
		WEIGHTED AVERAGE FOR THE SECOND QUARTER		25.00	1500.00	1650.33	1100.00
		WEIGHTED AVERAGE FOR THE YEAR		25.00	1500.00	1650.33	1100.00
===== 613-07195		Proof Conduit		Lin Foot	=====	=====	=====
NHPP0253-276		I-25 EXPRESS LANES SEGMENT 5	05/15/20	970.00	2.00	2.41	2.41
		WEIGHTED AVERAGE FOR THE SECOND QUARTER		970.00	2.00	2.41	2.41
		WEIGHTED AVERAGE FOR THE YEAR		970.00	2.00	2.41	2.41
===== 613-07199		Inst Pull Box		Each	=====	=====	=====
NHPP0253-276		I-25 EXPRESS LANES SEGMENT 5	05/15/20	17.00	1800.00	1765.50	1765.50
		WEIGHTED AVERAGE FOR THE SECOND QUARTER		17.00	1800.00	1765.50	1765.50
		WEIGHTED AVERAGE FOR THE YEAR		17.00	1800.00	1765.50	1765.50

PROJECT NUMBER	ITEM NUMBER/ PROJECT LOCATION	ITEM DESCRIPTION/ PROJECT LOCATION	DATE LET	UNIT/ QUANTITY	ENGR. EST.	AVERAGE BID	AWARDED BID
===== 613-10000		Wiring		LUMP SUM	=====		
FSA0253-262		I-25 SB BOTTLENECK I-76 TO I-	01/09/20	1.00	20000.00	22546.67	8140.00
NHPP0253-265		I-25 AT ERIE PARKWAY ON AND O	01/09/20	1.00	12500.00	24263.00	18000.00
FSA0341-097		US 34 & MACGREGOR INTERSECTIO	01/09/20	1.00	10000.00	11000.00	11000.00
ITS0761-231		ITS FIBER AND CAMERAS ON I-76	02/06/20	1.00	60000.00	19429.57	33000.00
FSA2873-194		US 287 Longmont Intersection	02/13/20	1.00	6000.00	11390.83	12730.00
NHPP0702-359		I-70 No Name Tunnel Lighting	02/27/20	1.00	200000.00	308082.74	245000.00
C0402-094		US 40 GRAND COUNTY SIGNAL REP	02/27/20	1.00	30000.00	33000.00	11000.00
NHPP0091-044		SH 9 FRISCO MAIN ST TO IRON S	03/05/20	1.00	75000.00	30780.00	35000.00
NH050A-034		US50A PUEBLO WEST PURCELL INT	03/26/20	1.00	19200.00	54340.11	44000.00
HPP 0501-067		US 50 AND SH 92 DELTA INTERSE	03/26/20	1.00	5000.00	14039.00	14558.00
SHE 0703-461		I-70 and Kipling North Phase	03/26/20	1.00	25000.00	15015.00	25500.00
		WEIGHTED AVERAGE FOR THE FIRST QUARTER		11.00	42063.64	53463.49	41629.82
IM0761-226		I76/SH52 Interchange	04/02/20	1.00	46100.00	53950.23	60320.36
CC0852-106		US-85 LOUVIERS TO MP 191.75	04/23/20	1.00	90.00	8341.06	8151.00
FBR0852-108		US-85 BETWEEN LOUVIERS AND MP					
C1211-090		SH-121 & 29th Ave / SH-121 &	04/23/20	1.00	40000.00	51143.33	20350.00
C1601-082		Hawkins Signal and Curb Ramps	04/30/20	1.00	30000.00	40042.67	25000.00
FSA1602-159		US 160 AND SH 17 INTERSECTION	04/30/20	1.00	25000.00	42554.00	33980.00
NHPPR100-303		LONG MAST ARM SIGNALS PROJECT	05/07/20	1.00	20000.00	38635.67	28850.00
FSAR400-356		FY 20 SIGNAL POLE REPLACEMENT	06/11/20	1.00	12000.00	23493.33	13555.00
SHE016A-043		SH 21 & 16 SIGNALS PROJECT	06/18/20	1.00	30000.00	26547.80	44190.00
		WEIGHTED AVERAGE FOR THE SECOND QUARTER		8.00	25398.75	33277.89	29299.55
		WEIGHTED AVERAGE FOR THE YEAR		19.00	35046.84	44288.22	36438.12
===== 613-10010		Wiring (Spec)		LUMP SUM	=====		
NHPP0702-359		I-70 No Name Tunnel Lighting	02/27/20	1.00	15000.00	29945.54	22000.00
		WEIGHTED AVERAGE FOR THE FIRST QUARTER		1.00	15000.00	29945.54	22000.00
		WEIGHTED AVERAGE FOR THE YEAR		1.00	15000.00	29945.54	22000.00
===== 613-13000		Luminaire (LED) (Spec)		Each	=====		
NHPP0253-265		I-25 AT ERIE PARKWAY ON AND O	01/09/20	6.00	1075.00	845.00	940.00

COLORADO DEPARTMENT OF TRANSPORTATION
ITEM UNIT COSTS BY PROJECTS -- 2020 COST DATA

10:58 Friday, October 2, 2020 240

PROJECT NUMBER	ITEM NUMBER/ PROJECT LOCATION	ITEM DESCRIPTION/ PROJECT LOCATION	DATE LET	UNIT/ QUANTITY	ENGR. EST.	AVERAGE BID	AWARDED BID
=====	613-13000	Luminaire (LED) (Spec)		Each =====			
FSA0341-097		US 34 & MACGREGOR INTERSECTIO	01/09/20	7.00	1500.00	2500.00	2500.00
NHPP0702-359		I-70 No Name Tunnel Lighting	02/27/20	2.00	2500.00	1108.50	1200.00
NH050A-034		US50A PUEBLO WEST PURCELL INT	03/26/20	18.00	2100.00	732.32	729.00
		WEIGHTED AVERAGE FOR THE FIRST QUARTER		33.00	1810.61	830.69	1171.58
IM0761-226		I76/SH52 Interchange	04/02/20	3.00	1000.00	841.57	700.66
		WEIGHTED AVERAGE FOR THE SECOND QUARTER		3.00	1000.00	841.57	700.66
		WEIGHTED AVERAGE FOR THE YEAR		36.00	1743.06	831.85	1132.33
=====	613-13006	Lumin (LED) (6,000 Lumens)		Each =====			
NHPP0091-044		SH 9 FRISCO MAIN ST TO IRON S	03/05/20	6.00	1000.00	1118.33	1100.00
NH050A-034		US50A PUEBLO WEST PURCELL INT	03/26/20	4.00	2100.00	732.15	700.00
		WEIGHTED AVERAGE FOR THE FIRST QUARTER		10.00	1440.00	871.18	940.00
CC0852-106		US-85 LOUVIERS TO MP 191.75	04/23/20	4.00	1000.00	716.54	704.00
FBR0852-108		US-85 BETWEEN LOUVIERS AND MP					
C1211-090		SH-121 & 29th Ave / SH-121 &	04/23/20	12.00	1100.00	817.57	775.00
		WEIGHTED AVERAGE FOR THE SECOND QUARTER		16.00	1075.00	770.02	757.25
		WEIGHTED AVERAGE FOR THE YEAR		26.00	1215.38	812.88	827.54
=====	613-13008	Lumin (LED) (8,000 Lumens)		Each =====			
SHE 0703-461		I-70 and Kipling North Phase	03/26/20	9.00	800.00	1319.60	1234.00
		WEIGHTED AVERAGE FOR THE FIRST QUARTER		9.00	800.00	1319.60	1234.00
C1601-082		Hawkins Signal and Curb Ramps	04/30/20	4.00	1200.00	741.00	920.00
FSA1602-159		US 160 AND SH 17 INTERSECTION	04/30/20	6.00	1200.00	610.67	539.00

COLORADO DEPARTMENT OF TRANSPORTATION
 ITEM UNIT COSTS BY PROJECTS -- 2020 COST DATA

10:58 Friday, October 2, 2020 241

PROJECT NUMBER	ITEM NUMBER/ PROJECT LOCATION	ITEM DESCRIPTION/ PROJECT LOCATION	DATE LET	UNIT/ QUANTITY	ENGR. EST.	AVERAGE BID	AWARDED BID
=====	613-13008	Lumin (LED) (8,000 Lumens)		Each =====			
NHPPR100-303		LONG MAST ARM SIGNALS PROJECT	05/07/20	14.00	1000.00	576.33	525.00
SHE016A-043		SH 21 & 16 SIGNALS PROJECT	06/18/20	4.00	1000.00	987.30	965.50
	WEIGHTED AVERAGE FOR THE SECOND QUARTER			28.00	1071.43	693.87	647.36
	WEIGHTED AVERAGE FOR THE YEAR			37.00	1005.41	899.40	790.05
=====	613-13014	Lumin (LED) (14,000 Lumens)		Each =====			
NHPP0091-044		SH 9 FRISCO MAIN ST TO IRON S	03/05/20	15.00	800.00	1058.33	1000.00
	WEIGHTED AVERAGE FOR THE FIRST QUARTER			15.00	800.00	1058.33	1000.00
IM0761-226		I76/SH52 Interchange	04/02/20	25.00	650.00	841.57	700.66
	WEIGHTED AVERAGE FOR THE SECOND QUARTER			25.00	650.00	841.57	700.66
	WEIGHTED AVERAGE FOR THE YEAR			40.00	706.25	885.91	812.91
=====	613-13030	Lumin (LED) (30,000 Lumens)		Each =====			
NHPP0702-359		I-70 No Name Tunnel Lighting	02/27/20	676.00	2400.00	2337.20	2150.00
	WEIGHTED AVERAGE FOR THE FIRST QUARTER			676.00	2400.00	2337.20	2150.00
	WEIGHTED AVERAGE FOR THE YEAR			676.00	2400.00	2337.20	2150.00
=====	613-13100	Luminare Mounting Support System		LUMP SUM =====			
NHPP0702-359		I-70 No Name Tunnel Lighting	02/27/20	1.00	25000.00	76259.10	5000.00
	WEIGHTED AVERAGE FOR THE FIRST QUARTER			1.00	25000.00	76259.10	5000.00
	WEIGHTED AVERAGE FOR THE YEAR			1.00	25000.00	76259.10	5000.00
=====	613-16000	Luminaire (Spec)		Each =====			
NH050A-034		US50A PUEBLO WEST PURCELL INT	03/26/20	6.00	2500.00	898.25	820.00
	WEIGHTED AVERAGE FOR THE FIRST QUARTER			6.00	2500.00	898.25	820.00

COLORADO DEPARTMENT OF TRANSPORTATION
 ITEM UNIT COSTS BY PROJECTS -- 2020 COST DATA

10:58 Friday, October 2, 2020 242

PROJECT NUMBER	ITEM NUMBER/ PROJECT LOCATION	ITEM DESCRIPTION/ PROJECT LOCATION	DATE LET	UNIT/ QUANTITY	ENGR. EST.	AVERAGE BID	AWARDED BID
=====	613-16000	Luminaire (Spec)		Each	=====	=====	=====
FSAR400-356		FY 20 SIGNAL POLE REPLACEMENT	06/11/20	7.00	750.00	1173.33	810.00
		WEIGHTED AVERAGE FOR THE SECOND QUARTER		7.00	750.00	1173.33	810.00
		WEIGHTED AVERAGE FOR THE YEAR		13.00	1557.69	981.97	814.62
=====	613-20200	Inst Lumin		Each	=====	=====	=====
C0402-094		US 40 GRAND COUNTY SIGNAL REP	02/27/20	8.00	300.00	255.00	150.00
HPP 0501-067		US 50 AND SH 92 DELTA INTERSE	03/26/20	2.00	300.00	411.00	415.00
		WEIGHTED AVERAGE FOR THE FIRST QUARTER		10.00	300.00	286.20	203.00
SHE016A-043		SH 21 & 16 SIGNALS PROJECT	06/18/20	8.00	300.00	247.85	232.25
		WEIGHTED AVERAGE FOR THE SECOND QUARTER		8.00	300.00	247.85	232.25
		WEIGHTED AVERAGE FOR THE YEAR		18.00	300.00	260.63	216.00
=====	613-20300	Furn Lumin		Each	=====	=====	=====
NHPP0702-359		I-70 No Name Tunnel Lighting	02/27/20	10.00	1700.00	1532.78	1800.00
		WEIGHTED AVERAGE FOR THE FIRST QUARTER		10.00	1700.00	1532.78	1800.00
		WEIGHTED AVERAGE FOR THE YEAR		10.00	1700.00	1532.78	1800.00
=====	613-32300	Light Std Steel (30 Ft)		Each	=====	=====	=====
FSA0341-097		US 34 & MACGREGOR INTERSECTIO	01/09/20	5.00	3250.00	7500.00	7500.00
		WEIGHTED AVERAGE FOR THE FIRST QUARTER		5.00	3250.00	7500.00	7500.00
		WEIGHTED AVERAGE FOR THE YEAR		5.00	3250.00	7500.00	7500.00
=====	613-32350	Light Std Steel (35 Ft)		Each	=====	=====	=====
IM0761-226		I76/SH52 Interchange	04/02/20	22.00	4000.00	2858.89	2626.68
		WEIGHTED AVERAGE FOR THE SECOND QUARTER		22.00	4000.00	2858.89	2626.68
		WEIGHTED AVERAGE FOR THE YEAR		22.00	4000.00	2858.89	2626.68

COLORADO DEPARTMENT OF TRANSPORTATION
 ITEM UNIT COSTS BY PROJECTS -- 2020 COST DATA

10:58 Friday, October 2, 2020 243

PROJECT NUMBER	ITEM NUMBER/ PROJECT LOCATION	ITEM DESCRIPTION/ PROJECT LOCATION	DATE LET	UNIT/ QUANTITY	ENGR. EST.	AVERAGE BID	AWARDED BID
=====	613-32400	Light Std Steel (40 Ft)		Each	=====	=====	=====
NH050A-034		US50A PUEBLO WEST PURCELL INT	03/26/20	18.00	5000.00	1987.60	1970.00
		WEIGHTED AVERAGE FOR THE FIRST QUARTER		18.00	5000.00	1987.60	1970.00
		WEIGHTED AVERAGE FOR THE YEAR		18.00	5000.00	1987.60	1970.00
=====	613-34300	Light Std Metal (30 Ft)		Each	=====	=====	=====
NHPP0091-044		SH 9 FRISCO MAIN ST TO IRON S	03/05/20	15.00	3200.00	4333.33	4200.00
		WEIGHTED AVERAGE FOR THE FIRST QUARTER		15.00	3200.00	4333.33	4200.00
		WEIGHTED AVERAGE FOR THE YEAR		15.00	3200.00	4333.33	4200.00
=====	613-34400	Light Std Metal (40 Ft)		Each	=====	=====	=====
FSA1602-159		US 160 AND SH 17 INTERSECTION	04/30/20	2.00	4000.00	6009.33	5350.00
		WEIGHTED AVERAGE FOR THE SECOND QUARTER		2.00	4000.00	6009.33	5350.00
		WEIGHTED AVERAGE FOR THE YEAR		2.00	4000.00	6009.33	5350.00
=====	613-40000	Conc Foundation Pad		Each	=====	=====	=====
NHPP0091-044		SH 9 FRISCO MAIN ST TO IRON S	03/05/20	3.00	1000.00	896.67	860.00
		WEIGHTED AVERAGE FOR THE FIRST QUARTER		3.00	1000.00	896.67	860.00
IM0761-226		I76/SH52 Interchange	04/02/20	3.00	3300.00	734.33	829.98
		WEIGHTED AVERAGE FOR THE SECOND QUARTER		3.00	3300.00	734.33	829.98
		WEIGHTED AVERAGE FOR THE YEAR		6.00	2150.00	783.03	844.99
=====	613-40010	Light Std Foundation		Each	=====	=====	=====
FSA0341-097		US 34 & MACGREGOR INTERSECTIO	01/09/20	5.00	1500.00	4000.00	4000.00

COLORADO DEPARTMENT OF TRANSPORTATION
 ITEM UNIT COSTS BY PROJECTS -- 2020 COST DATA

10:58 Friday, October 2, 2020 244

PROJECT NUMBER	ITEM NUMBER/ PROJECT LOCATION	ITEM DESCRIPTION/ PROJECT LOCATION	DATE LET	UNIT/ QUANTITY	ENGR. EST.	AVERAGE BID	AWARDED BID
=====	613-40010	Light Std Foundation		Each =====			
NHPP0091-044		SH 9 FRISCO MAIN ST TO IRON S	03/05/20	15.00	4000.00	1238.33	1200.00
NH050A-034		US50A PUEBLO WEST PURCELL INT	03/26/20	18.00	2100.00	1456.73	1410.00
		WEIGHTED AVERAGE FOR THE FIRST QUARTER		38.00	2771.05	1471.62	1667.89
IM0761-226		I76/SH52 Interchange	04/02/20	22.00	2750.00	1186.00	955.06
FSA1602-159		US 160 AND SH 17 INTERSECTION	04/30/20	2.00	1750.00	2460.33	2180.00
		WEIGHTED AVERAGE FOR THE SECOND QUARTER		24.00	2666.67	1233.78	1057.14
		WEIGHTED AVERAGE FOR THE YEAR		62.00	2730.65	1364.12	1431.47
=====	613-50100	Lighting Ctrl Center		Each =====			
NHPP0091-044		SH 9 FRISCO MAIN ST TO IRON S	03/05/20	3.00	15000.00	10958.33	10500.00
NH050A-034		US50A PUEBLO WEST PURCELL INT	03/26/20	1.00	10000.00	9579.08	9100.00
		WEIGHTED AVERAGE FOR THE FIRST QUARTER		4.00	13750.00	10309.27	10150.00
IM0761-226		I76/SH52 Interchange	04/02/20	3.00	18000.00	7337.28	8101.58
		WEIGHTED AVERAGE FOR THE SECOND QUARTER		3.00	18000.00	7337.28	8101.58
		WEIGHTED AVERAGE FOR THE YEAR		7.00	15571.43	8666.85	9272.11
=====	613-50105	Lighting Ctrl Center (Pedestal Only)		Each =====			
FSA1602-159		US 160 AND SH 17 INTERSECTION	04/30/20	1.00	7500.00	7020.33	6240.00
		WEIGHTED AVERAGE FOR THE SECOND QUARTER		1.00	7500.00	7020.33	6240.00
		WEIGHTED AVERAGE FOR THE YEAR		1.00	7500.00	7020.33	6240.00
=====	613-50150	Secondary Serv Pedestal		Each =====			
C0402-094		US 40 GRAND COUNTY SIGNAL REP	02/27/20	2.00	4500.00	7500.00	10000.00

COLORADO DEPARTMENT OF TRANSPORTATION
 ITEM UNIT COSTS BY PROJECTS -- 2020 COST DATA

10:58 Friday, October 2, 2020 245

PROJECT NUMBER	ITEM NUMBER/ PROJECT LOCATION	ITEM DESCRIPTION/ PROJECT LOCATION	DATE LET	UNIT/ QUANTITY	ENGR. EST.	AVERAGE BID	AWARDED BID
===== 613-50150		Secondary Serv Pedestal		Each =====			
NHPP0091-044		SH 9 FRISCO MAIN ST TO IRON S	03/05/20	3.00	3000.00	8890.00	8600.00
	WEIGHTED AVERAGE FOR THE FIRST QUARTER			5.00	3600.00	8462.31	9160.00
IM0761-226		I76/SH52 Interchange	04/02/20	1.00	5000.00	5471.13	6990.70
FSA1602-159		US 160 AND SH 17 INTERSECTION	04/30/20	1.00	4000.00	5508.33	4910.00
SHE016A-043		SH 21 & 16 SIGNALS PROJECT	06/18/20	3.00	5000.00	4384.00	4240.00
	WEIGHTED AVERAGE FOR THE SECOND QUARTER			5.00	4800.00	4823.32	4924.14
	WEIGHTED AVERAGE FOR THE YEAR			10.00	4200.00	6068.24	7042.07
===== 613-50210		Temporary Lighting		LUMP SUM =====			
NHPP0253-276		I-25 EXPRESS LANES SEGMENT 5	05/15/20	1.00	67900.00	67945.00	67945.00
	WEIGHTED AVERAGE FOR THE SECOND QUARTER			1.00	67900.00	67945.00	67945.00
	WEIGHTED AVERAGE FOR THE YEAR			1.00	67900.00	67945.00	67945.00
===== 613-50325		Tunnel Lighting Control System		LUMP SUM =====			
NHPP0702-359		I-70 No Name Tunnel Lighting	02/27/20	1.00	200000.00	494903.70	400000.00
	WEIGHTED AVERAGE FOR THE FIRST QUARTER			1.00	200000.00	494903.70	400000.00
	WEIGHTED AVERAGE FOR THE YEAR			1.00	200000.00	494903.70	400000.00
===== 613-50365		Transformer Base		Each =====			
NH050A-034		US50A PUEBLO WEST PURCELL INT	03/26/20	18.00	650.00	728.41	800.00
	WEIGHTED AVERAGE FOR THE FIRST QUARTER			18.00	650.00	728.41	800.00
	WEIGHTED AVERAGE FOR THE YEAR			18.00	650.00	728.41	800.00
===== 613-74000		Light Mast Arm		Each =====			
FSA0341-097		US 34 & MACGREGOR INTERSECTIO	01/09/20	7.00	1600.00	3000.00	3000.00
	WEIGHTED AVERAGE FOR THE FIRST QUARTER			7.00	1600.00	3000.00	3000.00
	WEIGHTED AVERAGE FOR THE YEAR			7.00	1600.00	3000.00	3000.00

COLORADO DEPARTMENT OF TRANSPORTATION
 ITEM UNIT COSTS BY PROJECTS -- 2020 COST DATA

10:58 Friday, October 2, 2020 246

PROJECT NUMBER	ITEM NUMBER/ PROJECT LOCATION	ITEM DESCRIPTION/ PROJECT LOCATION	DATE LET	UNIT/ QUANTITY	ENGR. EST.	AVERAGE BID	AWARDED BID
===== 613-80130		Service Meter Cabinet		Each			
FSA0253-262		I-25 SB BOTTLENECK I-76 TO I-	01/09/20	1.00	6500.00	7480.34	6845.00
NHPP0253-265		I-25 AT ERIE PARKWAY ON AND O	01/09/20	2.00	4232.00	6871.67	6415.00
FSA0341-097		US 34 & MACGREGOR INTERSECTIO	01/09/20	1.00	5000.00	7500.00	7500.00
ITS0761-231		ITS FIBER AND CAMERAS ON I-76	02/06/20	4.00	4000.00	5227.18	5600.00
NHPP0091-044		SH 9 FRISCO MAIN ST TO IRON S	03/05/20	2.00	8000.00	7863.33	7600.00
NH050A-034		US50A PUEBLO WEST PURCELL INT	03/26/20	3.00	4500.00	3773.50	3900.00
SHE 0703-461		I-70 and Kipling North Phase	03/26/20	2.00	6000.00	5654.20	5350.00
		WEIGHTED AVERAGE FOR THE FIRST QUARTER		15.00	5164.27	5285.72	5811.67
C1211-090		SH-121 & 29th Ave / SH-121 &	04/23/20	3.00	5196.83	5348.27	4585.00
NHPPR100-303		LONG MAST ARM SIGNALS PROJECT	05/07/20	4.00	6000.00	5485.33	4600.00
ITSSW01-719		FY 20 ITS CAPITAL REPLACEMENT	06/11/20	6.00	6000.00	3175.00	2500.00
FSAR400-356		FY 20 SIGNAL POLE REPLACEMENT	06/11/20	1.00	5000.00	5491.67	5800.00
		WEIGHTED AVERAGE FOR THE SECOND QUARTER		14.00	5756.46	4681.48	3782.50
		WEIGHTED AVERAGE FOR THE YEAR		29.00	5450.16	5080.51	4832.07
===== 613-81500		Panelboard (5KVA Mini Load Center)		Each			
CC0852-106		US-85 LOUVIERS TO MP 191.75	04/23/20	1.00	7000.00	2847.38	2777.50
FBR0852-108		US-85 BETWEEN LOUVIERS AND MP					
		WEIGHTED AVERAGE FOR THE SECOND QUARTER		1.00	7000.00	2847.38	2777.50
		WEIGHTED AVERAGE FOR THE YEAR		1.00	7000.00	2847.38	2777.50
===== 613-81699		Safe Switch NEMA 3R, 30A, 2-pole, 240 V		Each			
NH050A-034		US50A PUEBLO WEST PURCELL INT	03/26/20	6.00	180.00	359.62	230.00
		WEIGHTED AVERAGE FOR THE FIRST QUARTER		6.00	180.00	359.62	230.00
		WEIGHTED AVERAGE FOR THE YEAR		6.00	180.00	359.62	230.00
===== 614-00011		Sign Panel (CL I)		Sq Foot			
STA0142-066		SH 14 New Raymer West	01/09/20	27.00	22.00	22.44	20.50

PROJECT NUMBER	ITEM NUMBER/ PROJECT LOCATION	ITEM DESCRIPTION/ PROJECT LOCATION	DATE LET	UNIT/ QUANTITY	ENGR. EST.	AVERAGE BID	AWARDED BID
=====	614-00011	Sign Panel (CL I)		Sq Foot	=====	=====	=====
FSA0253-262		I-25 SB BOTTLENECK I-76 TO I-	01/09/20	34.00	25.00	28.35	20.00
NHPP0253-265		I-25 AT ERIE PARKWAY ON AND O	01/09/20	385.10	40.00	28.33	40.00
FSA0341-097		US 34 & MACGREGOR INTERSECTIO	01/09/20	175.00	21.00	25.00	25.00
NHPP0343-041		I-76 & US 34 FT. MORGAN AREA	01/09/20	214.00	20.00	21.47	23.00
NH 0503-093		US50 WEST OF TEXAS CREEK MP 2	01/23/20	645.00	15.00	20.98	19.95
NHPP 0852-116		US85:HAMPDEN TO FLORIDA-RESUR	02/06/20	24.00	27.00	22.50	25.00
STA0703-443		I-70 EJMT TUNNELS PAVING	02/06/20	60.00	25.00	31.55	26.50
STA059A-036		SH 59 SEIBERT TO COPE	02/06/20	320.00	22.50	22.13	20.25
STR116A-001		SH 116 A Surface Treatment Pr	02/13/20	581.00	20.00	19.59	21.00
FSA2873-194		US 287 Longmont Intersection	02/13/20	113.00	30.00	29.56	25.00
STA069A-033		SH69 MP 58.7 TO 71.58	02/13/20	557.00	20.00	21.50	24.00
STR0101-027		SH 10 Overlay La Junta West	02/27/20	521.00	25.00	20.17	22.00
C0402-094		US 40 GRAND COUNTY SIGNAL REP	02/27/20	133.00	40.00	28.00	26.00
NH0242-085		US 24 M.P. 291.38 to M.P. 296	02/27/20	367.00	24.00	25.56	27.40
NHPP0171-105		SH 17 MP 84.5 to US 285 & SH	03/05/20	163.00	16.00	20.79	18.36
NHPP145A-080		SH 145 Keystone-Placerville R	03/05/20	241.00	20.00	18.50	18.50
STR2871-038		US 287 Passing Lanes Springfi	03/05/20	11.00	20.00	23.71	24.57
STRR300-249		Grand and Jackson Counties AD	03/05/20	9.00	20.00	44.67	30.00
NHPP0091-044		SH 9 FRISCO MAIN ST TO IRON S	03/05/20	88.00	25.00	22.00	17.00
NH050A-034		US50A PUEBLO WEST PURCELL INT	03/26/20	298.00	20.00	21.04	20.00
HPP 0501-067		US 50 AND SH 92 DELTA INTERSE	03/26/20	60.00	24.00	27.75	28.00
SHE 0703-461		I-70 and Kipling North Phase	03/26/20	240.00	25.00	30.12	27.00
		WEIGHTED AVERAGE FOR THE FIRST QUARTER		5,266.10	22.89	23.20	23.63
NHPP1602-169		US 160 WC TUNNEL EAST RESURFA	04/02/20	146.00	20.00	19.83	19.49
STR092A-030		SH92 MP 31.748-48.5,DELTA AND	04/02/20	126.00	28.00	27.20	25.00
IM0761-226		I76/SH52 Interchange	04/02/20	439.00	20.00	23.59	20.14
SHER100-339		WWD TRAFFIC CONTROL ENHANCEME	04/09/20	2,362.00	18.00	24.00	24.00
CC0852-106		US-85 LOUVIERS TO MP 191.75	04/23/20	254.00	26.00	22.23	20.35
FBR0852-108		US-85 BETWEEN LOUVIERS AND MP					
C1211-090		SH-121 & 29th Ave / SH-121 &	04/23/20	129.00	22.09	29.63	26.00
FSA1602-159		US 160 AND SH 17 INTERSECTION	04/30/20	156.00	13.00	27.83	32.00
C0853-112		US85 & WCR98 INTERSECTION IMP	05/07/20	5.00	30.00	23.56	22.50
NHPPR100-303		LONG MAST ARM SIGNALS PROJECT	05/07/20	222.50	25.00	31.83	27.00
FBR0343-042		US 34 D-27-G STRUCTURE REPLAC	05/07/20	7.00	30.00	52.60	50.00
NHPP0402-098		US 40 CHIP SEAL MP 126 TO MP	05/14/20	18.00	25.00	37.20	40.00
NHPP0253-276		I-25 EXPRESS LANES SEGMENT 5	05/15/20	11.00	24.00	23.78	23.78
ITSSW01-719		FY 20 ITS CAPITAL REPLACEMENT	06/11/20	41.00	23.00	25.50	15.00
FSAR400-356		FY 20 SIGNAL POLE REPLACEMENT	06/11/20	39.00	25.00	33.33	30.00
SHE016A-043		SH 21 & 16 SIGNALS PROJECT	06/18/20	274.00	25.00	26.19	21.95
		WEIGHTED AVERAGE FOR THE SECOND QUARTER		4,229.50	20.01	24.88	23.71
		WEIGHTED AVERAGE FOR THE YEAR		9,495.60	21.61	23.91	23.67

PROJECT NUMBER	ITEM NUMBER/ PROJECT LOCATION	ITEM DESCRIPTION/ PROJECT LOCATION	DATE LET	UNIT/ QUANTITY	ENGR. EST.	AVERAGE BID	AWARDED BID
===== 614-00012		Sign Panel (CL II)		Sq Foot	=====		
STA0142-066		SH 14 New Raymer West	01/09/20	189.00	26.00	29.00	29.00
FSA0253-262		I-25 SB BOTTLENECK I-76 TO I-	01/09/20	127.00	27.00	31.54	22.00
FSA0341-097		US 34 & MACGREGOR INTERSECTIO	01/09/20	71.00	25.00	30.00	30.00
NHPP0343-041		I-76 & US 34 FT. MORGAN AREA	01/09/20	1,102.00	20.00	26.50	28.00
BR0343-040		US 34 REPUBLICAN RIVER BRIDGE	01/16/20	28.00	35.00	35.38	45.00
FBR0343-043		US 34 D-28-P STRUCTURE REPLAC					
NH 0503-093		US50 WEST OF TEXAS CREEK MP 2	01/23/20	1,178.00	20.00	23.05	23.10
NHPP 0852-116		US85:HAMPDEN TO FLORIDA-RESUR	02/06/20	144.00	27.00	24.00	26.00
STA0703-443		I-70 EJMT TUNNELS PAVING	02/06/20	164.00	28.00	39.06	33.12
STA059A-036		SH 59 SEIBERT TO COPE	02/06/20	18.00	30.00	27.75	25.50
STR116A-001		SH 116 A Surface Treatment Pr	02/13/20	532.00	25.00	25.40	26.00
FSA2873-194		US 287 Longmont Intersection	02/13/20	12.00	45.00	33.50	28.00
STA069A-033		SH69 MP 58.7 TO 71.58	02/13/20	1,482.00	20.00	23.59	25.00
STR0101-027		SH 10 Overlay La Junta West	02/27/20	872.00	25.00	22.27	24.00
NH0242-085		US 24 M.P. 291.38 to M.P. 296	02/27/20	2,970.00	29.00	27.45	29.70
NHPP0171-105		SH 17 MP 84.5 to US 285 & SH	03/05/20	383.00	18.00	24.14	21.42
NHPP145A-080		SH 145 Keystone-Placerville R	03/05/20	229.00	25.00	22.50	22.50
STR2871-038		US 287 Passing Lanes Springfi	03/05/20	140.00	20.00	27.77	30.42
NHPP0091-044		SH 9 FRISCO MAIN ST TO IRON S	03/05/20	630.00	30.00	46.08	22.00
NH050A-034		US50A PUEBLO WEST PURCELL INT	03/26/20	535.00	22.00	21.96	22.15
HPP 0501-067		US 50 AND SH 92 DELTA INTERSE	03/26/20	92.00	26.00	37.75	38.10
SHE 0703-461		I-70 and Kipling North Phase	03/26/20	194.00	30.00	30.70	27.00
		WEIGHTED AVERAGE FOR THE FIRST QUARTER		11,092.00	24.47	26.77	26.31
NHPP1602-169		US 160 WC TUNNEL EAST RESURFA	04/02/20	466.00	24.00	23.33	23.82
IM0761-226		I76/SH52 Interchange	04/02/20	821.00	25.00	26.35	22.26
SHER100-339		WWD TRAFFIC CONTROL ENHANCEME	04/09/20	12,559.00	25.00	29.00	29.00
SFTY2254-091		225 Ramp Improvements	04/09/20	18.00	40.00	34.50	34.00
CC0852-106		US-85 LOUVIERS TO MP 191.75	04/23/20	241.00	25.00	25.77	24.20
FBR0852-108		US-85 BETWEEN LOUVIERS AND MP					
C1211-090		SH-121 & 29th Ave / SH-121 &	04/23/20	150.00	23.17	35.57	31.00
C1601-082		Hawkins Signal and Curb Ramps	04/30/20	76.00	30.00	34.17	31.50
FSA1602-159		US 160 AND SH 17 INTERSECTION	04/30/20	174.00	25.00	33.83	38.00
C0853-112		US85 & WCR98 INTERSECTION IMP	05/07/20	138.00	30.00	28.11	27.00
NHPPR100-303		LONG MAST ARM SIGNALS PROJECT	05/07/20	26.00	30.00	35.83	32.50
FSAR400-356		FY 20 SIGNAL POLE REPLACEMENT	06/11/20	98.00	35.00	40.33	31.00
SHE016A-043		SH 21 & 16 SIGNALS PROJECT	06/18/20	41.00	30.00	28.08	25.41
		WEIGHTED AVERAGE FOR THE SECOND QUARTER		14,808.00	25.13	28.19	28.52
		WEIGHTED AVERAGE FOR THE YEAR		25,900.00	24.85	27.38	27.57
===== 614-00013		Sign Panel (CL III)		Sq Foot	=====		
FSA0253-262		I-25 SB BOTTLENECK I-76 TO I-	01/09/20	285.00	35.00	41.05	33.00

PROJECT NUMBER	ITEM NUMBER/ PROJECT LOCATION	ITEM DESCRIPTION/ PROJECT LOCATION	DATE LET	UNIT/ QUANTITY	ENGR. EST.	AVERAGE BID	AWARDED BID
===== 614-00013		Sign Panel (CL III)		Sq Foot	=====	=====	=====
NHPP0343-041		I-76 & US 34 FT. MORGAN AREA	01/09/20	2,250.00	25.00	29.86	32.00
NH 0503-093		US50 WEST OF TEXAS CREEK MP 2	01/23/20	112.00	35.00	34.30	33.60
NHPP 0852-116		US85:HAMPDEN TO FLORIDA-RESUR	02/06/20	60.00	30.00	33.00	40.00
STA0703-443		I-70 EJMT TUNNELS PAVING	02/06/20	590.00	35.00	44.88	39.75
STR0101-027		SH 10 Overlay La Junta West	02/27/20	119.00	25.00	32.77	34.00
NH0242-085		US 24 M.P. 291.38 to M.P. 296	02/27/20	460.00	32.00	40.40	39.95
NH050A-034		US50A PUEBLO WEST PURCELL INT	03/26/20	647.00	25.50	36.07	34.50
HPP 0501-067		US 50 AND SH 92 DELTA INTERSE	03/26/20	23.00	28.00	35.53	35.85
		WEIGHTED AVERAGE FOR THE FIRST QUARTER		4,546.00	28.03	34.62	34.45
IM0761-226		I76/SH52 Interchange	04/02/20	324.00	30.00	31.79	30.74
SFTY2254-091		225 Ramp Improvements	04/09/20	1,025.00	40.00	35.50	35.00
CC0852-106		US-85 LOUVIERS TO MP 191.75	04/23/20	40.00	30.00	35.02	34.10
FBR0852-108		US-85 BETWEEN LOUVIERS AND MP					
		WEIGHTED AVERAGE FOR THE SECOND QUARTER		1,389.00	37.38	33.66	33.98
		WEIGHTED AVERAGE FOR THE YEAR		5,935.00	30.22	34.41	34.34
===== 614-00014		Lighted Street Name Sign (Inst Only)		Each	=====	=====	=====
SHE016A-043		SH 21 & 16 SIGNALS PROJECT	06/18/20	8.00	920.00	562.55	76.75
		WEIGHTED AVERAGE FOR THE SECOND QUARTER		8.00	920.00	562.55	76.75
		WEIGHTED AVERAGE FOR THE YEAR		8.00	920.00	562.55	76.75
===== 614-00035		Sign Panel (Spec)		Sq Foot	=====	=====	=====
NHPP0253-265		I-25 AT ERIE PARKWAY ON AND O	01/09/20	120.00	55.00	39.33	50.00
FSA2873-194		US 287 Longmont Intersection	02/13/20	7.00	35.00	49.25	55.00
		WEIGHTED AVERAGE FOR THE FIRST QUARTER		127.00	53.90	40.37	50.28
		WEIGHTED AVERAGE FOR THE YEAR		127.00	53.90	40.37	50.28
===== 614-00200		Steel Sign Post (U-2)		Lin Foot	=====	=====	=====
NHPP 0852-116		US85:HAMPDEN TO FLORIDA-RESUR	02/06/20	6.00	30.00	12.50	10.00

COLORADO DEPARTMENT OF TRANSPORTATION
 ITEM UNIT COSTS BY PROJECTS -- 2020 COST DATA

10:58 Friday, October 2, 2020 250

PROJECT NUMBER	ITEM NUMBER/ PROJECT LOCATION	ITEM DESCRIPTION/ PROJECT LOCATION	DATE LET	UNIT/ QUANTITY	ENGR. EST.	AVERAGE BID	AWARDED BID
===== 614-00200 NH050A-034		Steel Sign Post (U-2) US50A PUEBLO WEST PURCELL INT	03/26/20	Lin Foot 37.00	60.00	12.22	22.25
	WEIGHTED AVERAGE FOR THE FIRST QUARTER			43.00	55.81	12.23	20.54
	WEIGHTED AVERAGE FOR THE YEAR			43.00	55.81	12.23	20.54
===== 614-00214		Steel Sign Post (1.75x1.75 In T)		Lin Foot			
SHE 0703-461		I-70 and Kipling North Phase	03/26/20	395.00	11.00	20.20	19.00
	WEIGHTED AVERAGE FOR THE FIRST QUARTER			395.00	11.00	20.20	19.00
	WEIGHTED AVERAGE FOR THE YEAR			395.00	11.00	20.20	19.00
===== 614-00216		Steel Sign Post (2x2 In T)		Lin Foot			
NHPP0343-041		I-76 & US 34 FT. MORGAN AREA	01/09/20	110.50	15.00	7.71	8.00
	WEIGHTED AVERAGE FOR THE FIRST QUARTER			110.50	15.00	7.71	8.00
IM0761-226		I76/SH52 Interchange	04/02/20	20.00	20.00	13.23	10.07
FSA1602-159		US 160 AND SH 17 INTERSECTION	04/30/20	21.00	20.00	29.25	16.00
NHPP0253-276		I-25 EXPRESS LANES SEGMENT 5	05/15/20	60.00	16.00	16.21	16.21
	WEIGHTED AVERAGE FOR THE SECOND QUARTER			101.00	17.62	17.75	14.95
	WEIGHTED AVERAGE FOR THE YEAR			211.50	16.25	12.15	11.32
===== 614-00220		Steel Sign Post (2.5x2.5 In T)		Lin Foot			
NHPP0343-041		I-76 & US 34 FT. MORGAN AREA	01/09/20	797.00	12.00	10.73	11.00
	WEIGHTED AVERAGE FOR THE FIRST QUARTER			797.00	12.00	10.73	11.00
	WEIGHTED AVERAGE FOR THE YEAR			797.00	12.00	10.73	11.00
===== 614-00612		Steel Sign Post (W 6x12)		Lin Foot			
NHPP0343-041		I-76 & US 34 FT. MORGAN AREA	01/09/20	28.00	54.00	63.41	68.00
	WEIGHTED AVERAGE FOR THE FIRST QUARTER			28.00	54.00	63.41	68.00
	WEIGHTED AVERAGE FOR THE YEAR			28.00	54.00	63.41	68.00

COLORADO DEPARTMENT OF TRANSPORTATION
ITEM UNIT COSTS BY PROJECTS -- 2020 COST DATA

10:58 Friday, October 2, 2020 251

PROJECT NUMBER	ITEM NUMBER/ PROJECT LOCATION	ITEM DESCRIPTION/ PROJECT LOCATION	DATE LET	UNIT/ QUANTITY	ENGR. EST.	AVERAGE BID	AWARDED BID
=====	614-00615	Steel Sign Post (W 6x15)		Lin Foot	=====		
NHPP0343-041		I-76 & US 34 FT. MORGAN AREA	01/09/20	116.00	54.00	63.41	68.00
NH0242-085		US 24 M.P. 291.38 to M.P. 296	02/27/20	74.00	47.00	78.12	79.85
NH050A-034		US50A PUEBLO WEST PURCELL INT	03/26/20	86.00	65.00	60.44	75.25
		WEIGHTED AVERAGE FOR THE FIRST QUARTER		276.00	55.55	64.38	73.44
		WEIGHTED AVERAGE FOR THE YEAR		276.00	55.55	64.38	73.44
=====	614-00818	Steel Sign Post (W 8x18)		Lin Foot	=====		
NHPP0343-041		I-76 & US 34 FT. MORGAN AREA	01/09/20	126.00	54.00	79.18	85.00
		WEIGHTED AVERAGE FOR THE FIRST QUARTER		126.00	54.00	79.18	85.00
		WEIGHTED AVERAGE FOR THE YEAR		126.00	54.00	79.18	85.00
=====	614-00821	Steel Sign Post (W 8x21)		Lin Foot	=====		
NHPP0343-041		I-76 & US 34 FT. MORGAN AREA	01/09/20	41.00	54.00	94.95	102.00
NH0242-085		US 24 M.P. 291.38 to M.P. 296	02/27/20	73.00	70.00	94.04	96.95
		WEIGHTED AVERAGE FOR THE FIRST QUARTER		114.00	64.25	94.37	98.77
		WEIGHTED AVERAGE FOR THE YEAR		114.00	64.25	94.37	98.77
=====	614-01022	Steel Sign Post (W 10x22)		Lin Foot	=====		
NHPP0343-041		I-76 & US 34 FT. MORGAN AREA	01/09/20	115.00	54.00	121.12	130.00
		WEIGHTED AVERAGE FOR THE FIRST QUARTER		115.00	54.00	121.12	130.00
		WEIGHTED AVERAGE FOR THE YEAR		115.00	54.00	121.12	130.00
=====	614-01026	Steel Sign Post (W 10x26)		Lin Foot	=====		
NHPP0343-041		I-76 & US 34 FT. MORGAN AREA	01/09/20	80.00	54.00	126.48	136.00
		WEIGHTED AVERAGE FOR THE FIRST QUARTER		80.00	54.00	126.48	136.00
		WEIGHTED AVERAGE FOR THE YEAR		80.00	54.00	126.48	136.00

COLORADO DEPARTMENT OF TRANSPORTATION
ITEM UNIT COSTS BY PROJECTS -- 2020 COST DATA

10:58 Friday, October 2, 2020 252

PROJECT NUMBER	ITEM NUMBER/ PROJECT LOCATION	ITEM DESCRIPTION/ PROJECT LOCATION	DATE LET	UNIT/ QUANTITY	ENGR. EST.	AVERAGE BID	AWARDED BID
=====	614-01402	Steel Sign Surf Mnt Base Plate (Slpbase)		Each	=====	=====	=====
SHER100-339		WWD TRAFFIC CONTROL ENHANCEME	04/09/20	278.00	150.00	350.00	350.00
	WEIGHTED AVERAGE FOR THE SECOND QUARTER			278.00	150.00	350.00	350.00
	WEIGHTED AVERAGE FOR THE YEAR			278.00	150.00	350.00	350.00
=====	614-01503	Steel Sign Supp (2-In Rd) (Po&Sock)		Each	=====	=====	=====
STA059A-036		SH 59 SEIBERT TO COPE	02/06/20	32.00	200.00	277.50	255.00
STR116A-001		SH 116 A Surface Treatment Pr	02/13/20	63.00	200.00	236.87	250.00
STA069A-033		SH69 MP 58.7 TO 71.58	02/13/20	45.00	200.00	251.12	270.00
STR0101-027		SH 10 Overlay La Junta West	02/27/20	34.00	200.00	285.36	320.00
NH0242-085		US 24 M.P. 291.38 to M.P. 296	02/27/20	19.00	174.00	294.31	296.50
STR2871-038		US 287 Passing Lanes Springfi	03/05/20	1.00	350.00	289.00	292.50
	WEIGHTED AVERAGE FOR THE FIRST QUARTER			194.00	198.23	261.09	272.51
STR092A-030		SH92 MP 31.748-48.5, DELTA AND	04/02/20	42.00	200.00	309.50	325.00
IM0761-226		I76/SH52 Interchange	04/02/20	34.00	200.00	249.95	307.40
CC0852-106		US-85 LOUVIERS TO MP 191.75	04/23/20	6.00	200.00	249.97	220.00
FBR0852-108		US-85 BETWEEN LOUVIERS AND MP					
	WEIGHTED AVERAGE FOR THE SECOND QUARTER			82.00	200.00	263.47	310.02
	WEIGHTED AVERAGE FOR THE YEAR			276.00	198.75	262.10	283.65
=====	614-01512	Steel Sign Support (2-In Rd) (Post)		Lin Foot	=====	=====	=====
FSA0341-097		US 34 & MACGREGOR INTERSECTIO	01/09/20	263.00	17.00	35.00	35.00
BR0343-040		US 34 REPUBLICAN RIVER BRIDGE	01/16/20	57.00	13.00	24.41	30.00
FBR0343-043		US 34 D-28-P STRUCTURE REPLAC					
STA069A-033		SH69 MP 58.7 TO 71.58	02/13/20	105.00	10.00	21.50	24.00
NHPP0171-105		SH 17 MP 84.5 to US 285 & SH	03/05/20	56.00	11.00	18.77	16.32
NHPP145A-080		SH 145 Keystone-Placerville R	03/05/20	34.00	15.00	15.50	15.50
	WEIGHTED AVERAGE FOR THE FIRST QUARTER			515.00	14.35	25.32	28.89
NHPP1602-169		US 160 WC TUNNEL EAST RESURFA	04/02/20	12.00	16.00	20.78	16.24

PROJECT NUMBER	ITEM NUMBER/ PROJECT LOCATION	ITEM DESCRIPTION/ PROJECT LOCATION	DATE LET	UNIT/ QUANTITY	ENGR. EST.	AVERAGE BID	AWARDED BID
=====	614-01512	Steel Sign Support (2-In Rd) (Post)		Lin Foot	=====		
FSA1602-159		US 160 AND SH 17 INTERSECTION	04/30/20	55.00	10.00	36.58	81.00
	WEIGHTED AVERAGE FOR THE SECOND QUARTER			67.00	11.07	33.75	69.40
	WEIGHTED AVERAGE FOR THE YEAR			582.00	13.97	26.71	33.55
=====	614-01522	Steel Sign Supp (2-In Rd) (Sock)		Each	=====		
FSA0341-097		US 34 & MACGREGOR INTERSECTIO	01/09/20	27.00	135.00	150.00	150.00
BR0343-040		US 34 REPUBLICAN RIVER BRIDGE	01/16/20	5.00	100.00	155.56	190.00
FBR0343-043		US 34 D-28-P STRUCTURE REPLAC					
NHPP0171-105		SH 17 MP 84.5 to US 285 & SH	03/05/20	114.00	130.00	192.50	127.51
NHPP145A-080		SH 145 Keystone-Placerville R	03/05/20	3.00	100.00	96.00	96.00
	WEIGHTED AVERAGE FOR THE FIRST QUARTER			149.00	129.30	186.17	133.05
NHPP1602-169		US 160 WC TUNNEL EAST RESURFA	04/02/20	1.00	100.00	153.74	102.87
FSA1602-159		US 160 AND SH 17 INTERSECTION	04/30/20	5.00	30.00	145.33	81.00
	WEIGHTED AVERAGE FOR THE SECOND QUARTER			6.00	41.67	146.73	84.65
	WEIGHTED AVERAGE FOR THE YEAR			155.00	125.90	184.48	131.17
=====	614-01554	Steel Sign Post (4 In Rd) (Slip)		Lin Foot	=====		
FSA0253-262		I-25 SB BOTTLENECK I-76 TO I-	01/09/20	36.00	60.00	53.64	42.00
	WEIGHTED AVERAGE FOR THE FIRST QUARTER			36.00	60.00	53.64	42.00
	WEIGHTED AVERAGE FOR THE YEAR			36.00	60.00	53.64	42.00
=====	614-01572	Steel Sign Supp (2-1/2 Rd NP40) (Po&Silp)		Lin Foot	=====		
NHPP0343-041		I-76 & US 34 FT. MORGAN AREA	01/09/20	15.00	44.00	27.51	29.00
STRR300-249		Grand and Jackson Counties AD	03/05/20	17.00	60.00	88.00	50.00
	WEIGHTED AVERAGE FOR THE FIRST QUARTER			32.00	52.50	59.65	40.16
	WEIGHTED AVERAGE FOR THE YEAR			32.00	52.50	59.65	40.16

COLORADO DEPARTMENT OF TRANSPORTATION
 ITEM UNIT COSTS BY PROJECTS -- 2020 COST DATA

10:58 Friday, October 2, 2020 254

PROJECT NUMBER	ITEM NUMBER/ PROJECT LOCATION	ITEM DESCRIPTION/ PROJECT LOCATION	DATE LET	UNIT/ QUANTITY	ENGR. EST.	AVERAGE BID	AWARDED BID
===== 614-01573		Steel Sign Supp (2-1/2 Rd NP40) (Po&Slip)		Each =====			
NH 0503-093		US50 WEST OF TEXAS CREEK MP 2	01/23/20	8.00	350.00	414.02	378.04
STA059A-036		SH 59 SEIBERT TO COPE	02/06/20	2.00	400.00	401.50	383.00
STR116A-001		SH 116 A Surface Treatment Pr	02/13/20	55.00	360.00	405.65	420.00
FSA2873-194		US 287 Longmont Intersection	02/13/20	14.00	400.00	576.33	440.00
STA069A-033		SH69 MP 58.7 TO 71.58	02/13/20	100.00	321.00	413.20	420.00
STR0101-027		SH 10 Overlay La Junta West	02/27/20	90.00	360.00	398.37	410.00
NH0242-085		US 24 M.P. 291.38 to M.P. 296	02/27/20	185.00	410.00	458.81	455.00
STR2871-038		US 287 Passing Lanes Springfi	03/05/20	10.00	400.00	474.11	491.40
NH050A-034		US50A PUEBLO WEST PURCELL INT	03/26/20	53.00	350.00	386.23	437.50
HPP 0501-067		US 50 AND SH 92 DELTA INTERSE	03/26/20	7.00	325.00	416.25	420.00
		WEIGHTED AVERAGE FOR THE FIRST QUARTER		524.00	370.56	426.65	433.52
IM0761-226		I76/SH52 Interchange	04/02/20	69.00	375.00	440.36	503.50
NHPPR100-303		LONG MAST ARM SIGNALS PROJECT	05/07/20	2.00	350.00	454.33	485.00
FBR0343-042		US 34 D-27-G STRUCTURE REPLAC	05/07/20	1.00	400.00	405.21	250.00
SHE016A-043		SH 21 & 16 SIGNALS PROJECT	06/18/20	12.00	412.00	475.65	456.25
		WEIGHTED AVERAGE FOR THE SECOND QUARTER		84.00	379.99	443.74	493.29
		WEIGHTED AVERAGE FOR THE YEAR		608.00	371.87	430.78	441.78
===== 614-01575		Steel Sign Supp (2-1/2 In Rd NP40) (Po)		Lin Foot =====			
NHPP4701-134		C-470 NOISE WALL WEST OF LUCE	02/06/20	12.00	10.00	62.20	50.00
STA069A-033		SH69 MP 58.7 TO 71.58	02/13/20	90.00	16.00	30.84	30.00
NHPP0171-105		SH 17 MP 84.5 to US 285 & SH	03/05/20	12.00	15.00	19.47	20.40
NHPP145A-080		SH 145 Keystone-Placerville R	03/05/20	12.00	25.00	17.00	17.00
NHPP0091-044		SH 9 FRISCO MAIN ST TO IRON S	03/05/20	636.00	25.00	25.42	22.00
		WEIGHTED AVERAGE FOR THE FIRST QUARTER		762.00	23.54	26.72	23.28
C1601-082		Hawkins Signal and Curb Ramps	04/30/20	10.00	20.00	44.08	73.25
FSA1602-159		US 160 AND SH 17 INTERSECTION	04/30/20	149.00	25.00	94.33	242.00
		WEIGHTED AVERAGE FOR THE SECOND QUARTER		159.00	24.69	91.17	231.39
		WEIGHTED AVERAGE FOR THE YEAR		921.00	23.74	38.22	59.21

PROJECT NUMBER	ITEM NUMBER/ PROJECT LOCATION	ITEM DESCRIPTION/ PROJECT LOCATION	DATE LET	UNIT/ QUANTITY	ENGR. EST.	AVERAGE BID	AWARDED BID
===== 614-01578		Steel Sign Supp (2-1/2 In Rd NP40) (Slip)		Each			
NHPP0171-105		SH 17 MP 84.5 to US 285 & SH	03/05/20	35.00	300.00	261.47	224.41
NHPP145A-080		SH 145 Keystone-Placerville R	03/05/20	1.00	250.00	230.00	230.00
NHPP0091-044		SH 9 FRISCO MAIN ST TO IRON S	03/05/20	56.00	250.00	321.67	270.00
		WEIGHTED AVERAGE FOR THE FIRST QUARTER		92.00	269.02	298.26	252.22
C1601-082		Hawkins Signal and Curb Ramps	04/30/20	1.00	400.00	561.67	800.00
FSA1602-159		US 160 AND SH 17 INTERSECTION	04/30/20	15.00	250.00	290.33	242.00
		WEIGHTED AVERAGE FOR THE SECOND QUARTER		16.00	259.38	307.29	276.88
		WEIGHTED AVERAGE FOR THE YEAR		108.00	267.59	299.61	255.87
===== 614-01582		Steel Sign Supp (2-1/2 In Rd) (Po&Slip)		Lin Foot			
FSA0253-262		I-25 SB BOTTLENECK I-76 TO I-	01/09/20	25.00	225.00	41.46	32.00
		WEIGHTED AVERAGE FOR THE FIRST QUARTER		25.00	225.00	41.46	32.00
		WEIGHTED AVERAGE FOR THE YEAR		25.00	225.00	41.46	32.00
===== 614-01583		Stl Sign Supp (2-1/2 In Rd 80) (Po&Slip)		Each			
NH 0503-093		US50 WEST OF TEXAS CREEK MP 2	01/23/20	12.00	365.00	460.02	420.04
NHPP 0852-116		US85:HAMPDEN TO FLORIDA-RESUR	02/06/20	7.00	500.00	725.00	1000.00
STA0703-443		I-70 EJMT TUNNELS PAVING	02/06/20	20.00	750.00	788.71	662.42
FSA2873-194		US 287 Longmont Intersection	02/13/20	1.00	600.00	705.83	605.00
STA069A-033		SH69 MP 58.7 TO 71.58	02/13/20	2.00	410.00	466.67	490.00
NH0242-085		US 24 M.P. 291.38 to M.P. 296	02/27/20	35.00	460.00	551.55	570.35
NH050A-034		US50A PUEBLO WEST PURCELL INT	03/26/20	2.00	425.00	492.09	465.00
HPP 0501-067		US 50 AND SH 92 DELTA INTERSE	03/26/20	1.00	345.00	555.00	560.00
		WEIGHTED AVERAGE FOR THE FIRST QUARTER		80.00	519.94	595.91	604.08
IM0761-226		I76/SH52 Interchange	04/02/20	18.00	557.00	511.29	583.00
SHER100-339		WWD TRAFFIC CONTROL ENHANCEME	04/09/20	1,012.00	450.00	450.00	450.00

PROJECT NUMBER	ITEM NUMBER/ PROJECT LOCATION	ITEM DESCRIPTION/ PROJECT LOCATION	DATE LET	UNIT/ QUANTITY	ENGR. EST.	AVERAGE BID	AWARDED BID
===== 614-01583		Stl Sign Supp (2-1/2 In Rd 80) (Po&Slip)		Each =====			
CC0852-106		US-85 LOUVIERS TO MP 191.75	04/23/20	63.00	500.00	526.19	484.00
FBR0852-108		US-85 BETWEEN LOUVIERS AND MP					
C1211-090		SH-121 & 29th Ave / SH-121 &	04/23/20	2.00	440.00	642.97	550.00
NHPPR100-303		LONG MAST ARM SIGNALS PROJECT	05/07/20	3.00	600.00	527.00	560.00
		WEIGHTED AVERAGE FOR THE SECOND QUARTER		1,098.00	455.01	478.95	454.61
		WEIGHTED AVERAGE FOR THE YEAR		1,178.00	459.42	492.16	464.76
===== 614-01585		Steel Sign Supp (2-1/2 In Rd 80) (Post)		Lin Foot =====			
FSA0341-097		US 34 & MACGREGOR INTERSECTIO	01/09/20	99.00	23.00	40.00	40.00
STA069A-033		SH69 MP 58.7 TO 71.58	02/13/20	62.00	22.00	40.98	45.00
SHE 0703-461		I-70 and Kipling North Phase	03/26/20	68.00	29.00	32.20	22.00
		WEIGHTED AVERAGE FOR THE FIRST QUARTER		229.00	24.51	35.50	36.01
NHPP1602-169		US 160 WC TUNNEL EAST RESURFA	04/02/20	12.00	25.00	31.20	23.82
SHER100-339		WWD TRAFFIC CONTROL ENHANCEME	04/09/20	2,224.00	25.00	30.00	30.00
FSA1602-159		US 160 AND SH 17 INTERSECTION	04/30/20	15.00	35.00	115.67	295.00
C0853-112		US85 & WCR98 INTERSECTION IMP	05/07/20	171.00	30.00	23.56	22.50
NHPP0402-098		US 40 CHIP SEAL MP 126 TO MP	05/14/20	20.00	24.00	37.20	40.00
		WEIGHTED AVERAGE FOR THE SECOND QUARTER		2,442.00	25.40	28.80	31.15
		WEIGHTED AVERAGE FOR THE YEAR		2,671.00	25.33	29.68	31.57
===== 614-01588		Steel Sign Supp (2-1/2 In Rd 80) (Slip)		Each =====			
FSA0341-097		US 34 & MACGREGOR INTERSECTIO	01/09/20	10.00	400.00	188.00	188.00
SHE 0703-461		I-70 and Kipling North Phase	03/26/20	5.00	350.00	390.00	385.00
		WEIGHTED AVERAGE FOR THE FIRST QUARTER		15.00	383.33	332.29	253.67
NHPP1602-169		US 160 WC TUNNEL EAST RESURFA	04/02/20	1.00	250.00	247.76	247.98
FSA1602-159		US 160 AND SH 17 INTERSECTION	04/30/20	1.00	110.00	308.00	295.00
C0853-112		US85 & WCR98 INTERSECTION IMP	05/07/20	15.00	300.00	430.31	420.00
NHPP0402-098		US 40 CHIP SEAL MP 126 TO MP	05/14/20	2.00	320.00	533.33	600.00
		WEIGHTED AVERAGE FOR THE SECOND QUARTER		19.00	289.47	428.07	423.31
		WEIGHTED AVERAGE FOR THE YEAR		34.00	330.88	407.99	348.47

COLORADO DEPARTMENT OF TRANSPORTATION
ITEM UNIT COSTS BY PROJECTS -- 2020 COST DATA

10:58 Friday, October 2, 2020 257

PROJECT NUMBER	ITEM NUMBER/ PROJECT LOCATION	ITEM DESCRIPTION/ PROJECT LOCATION	DATE LET	UNIT/ QUANTITY	ENGR. EST.	AVERAGE BID	AWARDED BID
=====	614-01736	Steel Sign Ground Stub Base (36 In)		Each	=====	=====	=====
SHE 0703-461		I-70 and Kipling North Phase	03/26/20	30.00	100.00	301.00	33.00
	WEIGHTED AVERAGE FOR THE FIRST QUARTER			30.00	100.00	301.00	33.00
	WEIGHTED AVERAGE FOR THE YEAR			30.00	100.00	301.00	33.00
=====	614-03001	Conc Footing (Ty 1)		Each	=====	=====	=====
NHPP0343-041		I-76 & US 34 FT. MORGAN AREA	01/09/20	2.00	1250.00	1159.82	1247.00
	WEIGHTED AVERAGE FOR THE FIRST QUARTER			2.00	1250.00	1159.82	1247.00
	WEIGHTED AVERAGE FOR THE YEAR			2.00	1250.00	1159.82	1247.00
=====	614-03002	Conc Footing (Ty 2)		Each	=====	=====	=====
NHPP0343-041		I-76 & US 34 FT. MORGAN AREA	01/09/20	8.00	1350.00	1790.90	1928.00
NH0242-085		US 24 M.P. 291.38 to M.P. 296	02/27/20	4.00	1330.00	2865.51	2850.00
NH050A-034		US50A PUEBLO WEST PURCELL INT	03/26/20	6.00	1250.00	2720.62	2700.00
	WEIGHTED AVERAGE FOR THE FIRST QUARTER			18.00	1312.22	2475.68	2390.22
	WEIGHTED AVERAGE FOR THE YEAR			18.00	1312.22	2475.68	2390.22
=====	614-03003	Conc Footing (Ty 3)		Each	=====	=====	=====
NHPP0343-041		I-76 & US 34 FT. MORGAN AREA	01/09/20	8.00	1500.00	2106.27	2268.00
	WEIGHTED AVERAGE FOR THE FIRST QUARTER			8.00	1500.00	2106.27	2268.00
	WEIGHTED AVERAGE FOR THE YEAR			8.00	1500.00	2106.27	2268.00
=====	614-03004	Conc Footing (Ty 4)		Each	=====	=====	=====
NHPP0343-041		I-76 & US 34 FT. MORGAN AREA	01/09/20	2.00	2100.00	2632.01	2835.00
NH0242-085		US 24 M.P. 291.38 to M.P. 296	02/27/20	4.00	1320.00	4931.01	5700.00
	WEIGHTED AVERAGE FOR THE FIRST QUARTER			6.00	1580.00	4164.68	4745.00
	WEIGHTED AVERAGE FOR THE YEAR			6.00	1580.00	4164.68	4745.00

COLORADO DEPARTMENT OF TRANSPORTATION
ITEM UNIT COSTS BY PROJECTS -- 2020 COST DATA

10:58 Friday, October 2, 2020 258

PROJECT NUMBER	ITEM NUMBER/ PROJECT LOCATION	ITEM DESCRIPTION/ PROJECT LOCATION	DATE LET	UNIT/ QUANTITY	ENGR. EST.	AVERAGE BID	AWARDED BID
=====	614-03005	Conc Footing (Ty 5)		Each	=====	=====	=====
NHPP0343-041		I-76 & US 34 FT. MORGAN AREA	01/09/20	6.00	2500.00	3157.74	3402.00
	WEIGHTED	AVERAGE FOR THE FIRST QUARTER		6.00	2500.00	3157.74	3402.00
		WEIGHTED AVERAGE FOR THE YEAR		6.00	2500.00	3157.74	3402.00
=====	614-03006	Conc Footing (Ty 6)		Each	=====	=====	=====
NHPP0343-041		I-76 & US 34 FT. MORGAN AREA	01/09/20	4.00	2750.00	3946.18	4252.00
	WEIGHTED	AVERAGE FOR THE FIRST QUARTER		4.00	2750.00	3946.18	4252.00
		WEIGHTED AVERAGE FOR THE YEAR		4.00	2750.00	3946.18	4252.00
=====	614-10035	Paint Ground Sign		Each	=====	=====	=====
SHER100-339		WWD TRAFFIC CONTROL ENHANCEME	04/09/20	380.00	50.00	225.00	225.00
	WEIGHTED	AVERAGE FOR THE SECOND QUARTER		380.00	50.00	225.00	225.00
		WEIGHTED AVERAGE FOR THE YEAR		380.00	50.00	225.00	225.00
=====	614-10050	Mod Overhead Sign Str		Each	=====	=====	=====
SHER100-339		WWD TRAFFIC CONTROL ENHANCEME	04/09/20	14.00	7000.00	7500.00	7500.00
	WEIGHTED	AVERAGE FOR THE SECOND QUARTER		14.00	7000.00	7500.00	7500.00
		WEIGHTED AVERAGE FOR THE YEAR		14.00	7000.00	7500.00	7500.00
=====	614-10120	Var Mesg Sign		Each	=====	=====	=====
ITSSW01-719		FY 20 ITS CAPITAL REPLACEMENT	06/11/20	8.00	65000.00	54966.00	50000.00
	WEIGHTED	AVERAGE FOR THE SECOND QUARTER		8.00	65000.00	54966.00	50000.00
		WEIGHTED AVERAGE FOR THE YEAR		8.00	65000.00	54966.00	50000.00
=====	614-10128	Blankout Sign (Fib Opt)		Each	=====	=====	=====
CC0852-106		US-85 LOUVIERS TO MP 191.75	04/23/20	3.00	12000.00	7651.11	7458.00

COLORADO DEPARTMENT OF TRANSPORTATION
 ITEM UNIT COSTS BY PROJECTS -- 2020 COST DATA

10:58 Friday, October 2, 2020 259

PROJECT NUMBER	ITEM NUMBER/ PROJECT LOCATION	ITEM DESCRIPTION/ PROJECT LOCATION	DATE LET	UNIT/ QUANTITY	ENGR. EST.	AVERAGE BID	AWARDED BID
===== 614-10128 FBR0852-108		Blankout Sign (Fib Opt) US-85 BETWEEN LOUVIERS AND MP		Each =====			
	WEIGHTED AVERAGE FOR THE SECOND QUARTER			3.00	12000.00	7651.11	7458.00
	WEIGHTED AVERAGE FOR THE YEAR			3.00	12000.00	7651.11	7458.00
===== 614-10145		VMS LED (Single Faced)		Each =====			
ITSSW01-719		FY 20 ITS CAPITAL REPLACEMENT	06/11/20	2.00	70000.00	43186.00	36000.00
	WEIGHTED AVERAGE FOR THE SECOND QUARTER			2.00	70000.00	43186.00	36000.00
	WEIGHTED AVERAGE FOR THE YEAR			2.00	70000.00	43186.00	36000.00
===== 614-10147		VMS LED (Overhead)		Each =====			
ITSSW01-719		FY 20 ITS CAPITAL REPLACEMENT	06/11/20	1.00	120000.00	60158.00	54000.00
	WEIGHTED AVERAGE FOR THE SECOND QUARTER			1.00	120000.00	60158.00	54000.00
	WEIGHTED AVERAGE FOR THE YEAR			1.00	120000.00	60158.00	54000.00
===== 614-10156		12 In LED (Arr) (Green)		Each =====			
SHER100-339		WVD TRAFFIC CONTROL ENHANCEME	04/09/20	134.00	52.00	200.00	200.00
	WEIGHTED AVERAGE FOR THE SECOND QUARTER			134.00	52.00	200.00	200.00
	WEIGHTED AVERAGE FOR THE YEAR			134.00	52.00	200.00	200.00
===== 614-10160		Sig Head B-Plates		Each =====			
FSA2873-194 SHE 0703-461		US 287 Longmont Intersection	02/13/20	18.00	450.00	446.00	335.00
		I-70 and Kipling North Phase	03/26/20	7.00	140.00	236.00	220.00
	WEIGHTED AVERAGE FOR THE FIRST QUARTER			25.00	363.20	394.60	302.80
C1601-082		Hawkins Signal and Curb Ramps	04/30/20	8.00	250.00	220.50	365.50

COLORADO DEPARTMENT OF TRANSPORTATION
 ITEM UNIT COSTS BY PROJECTS -- 2020 COST DATA

10:58 Friday, October 2, 2020 260

PROJECT NUMBER	ITEM NUMBER/ PROJECT LOCATION	ITEM DESCRIPTION/ PROJECT LOCATION	DATE LET	UNIT/ QUANTITY	ENGR. EST.	AVERAGE BID	AWARDED BID
===== 614-10160 SHER400-373		Sig Head B-Plates R4 Signal Head Backplate Inst	05/28/20	Each 1,104.00	425.00	387.76	400.00
	WEIGHTED AVERAGE FOR THE SECOND QUARTER			1,112.00	423.74	385.96	399.75
	WEIGHTED AVERAGE FOR THE YEAR			1,137.00	422.41	386.48	397.62
===== 614-10170 SHER400-373		Traffic Signal Head Visors R4 Signal Head Backplate Inst	05/28/20	Each 5,462.00	80.00	45.00	30.00
	WEIGHTED AVERAGE FOR THE SECOND QUARTER			5,462.00	80.00	45.00	30.00
	WEIGHTED AVERAGE FOR THE YEAR			5,462.00	80.00	45.00	30.00
===== 614-30205 ITSSW01-719		VMS Butterfly Support (Roadside) FY 20 ITS CAPITAL REPLACEMENT	06/11/20	Each 8.00	30000.00	26612.50	22000.00
	WEIGHTED AVERAGE FOR THE SECOND QUARTER			8.00	30000.00	26612.50	22000.00
	WEIGHTED AVERAGE FOR THE YEAR			8.00	30000.00	26612.50	22000.00
===== 614-32000 NH050A-034		Monotube Overhead Sign Cant (20 In Dia) US50A PUEBLO WEST PURCELL INT	03/26/20	Each 3.00	50000.00	45192.85	35700.00
	WEIGHTED AVERAGE FOR THE FIRST QUARTER			3.00	50000.00	45192.85	35700.00
	WEIGHTED AVERAGE FOR THE YEAR			3.00	50000.00	45192.85	35700.00
===== 614-32400 ITSSW01-719		Monotube Overhead Sign Cant (24 In Dia) FY 20 ITS CAPITAL REPLACEMENT	06/11/20	Each 1.00	55000.00	55375.00	41000.00
	WEIGHTED AVERAGE FOR THE SECOND QUARTER			1.00	55000.00	55375.00	41000.00
	WEIGHTED AVERAGE FOR THE YEAR			1.00	55000.00	55375.00	41000.00
===== 614-42400 SFTY2254-091		Monotube Overhead Sign Brdg (24 In Dia) 225 Ramp Improvements	04/09/20	Each 1.00	150000.00	126500.00	123000.00
	WEIGHTED AVERAGE FOR THE SECOND QUARTER			1.00	150000.00	126500.00	123000.00
	WEIGHTED AVERAGE FOR THE YEAR			1.00	150000.00	126500.00	123000.00

COLORADO DEPARTMENT OF TRANSPORTATION
 ITEM UNIT COSTS BY PROJECTS -- 2020 COST DATA

10:58 Friday, October 2, 2020 261

PROJECT NUMBER	ITEM NUMBER/ PROJECT LOCATION	ITEM DESCRIPTION/ PROJECT LOCATION	DATE LET	UNIT/ QUANTITY	ENGR. EST.	AVERAGE BID	AWARDED BID
===== 614-70000		Prog Traf Sig Face		Each	=====	=====	=====
CC0852-106		US-85 LOUVIERS TO MP 191.75	04/23/20	2.00	5000.00	4243.92	4152.50
FBR0852-108		US-85 BETWEEN LOUVIERS AND MP					
		WEIGHTED AVERAGE FOR THE SECOND QUARTER		2.00	5000.00	4243.92	4152.50
		WEIGHTED AVERAGE FOR THE YEAR		2.00	5000.00	4243.92	4152.50
===== 614-70024		1310nm SFP Optic Module		Each	=====	=====	=====
FSA0253-262		I-25 SB BOTTLENECK I-76 TO I-	01/09/20	1.00	375.00	944.97	865.00
ITS0761-231		ITS FIBER AND CAMERAS ON I-76	02/06/20	20.00	500.00	530.46	480.00
		WEIGHTED AVERAGE FOR THE FIRST QUARTER		21.00	494.05	542.54	498.33
CC0852-106		US-85 LOUVIERS TO MP 191.75	04/23/20	2.00	350.00	745.47	726.00
FBR0852-108		US-85 BETWEEN LOUVIERS AND MP					
C1211-090		SH-121 & 29th Ave / SH-121 &	04/23/20	3.00	466.67	416.63	330.00
ITS SW02-304		ITS FIBER TO STATE BUILDINGS	05/14/20	130.00	500.00	566.50	587.00
ITS SW02-303		R1: US 285, SH 83 R2: SH 83,	05/28/20	6.00	400.00	706.20	975.00
ITSSW01-719		FY 20 ITS CAPITAL REPLACEMENT	06/11/20	2.00	400.00	875.00	1000.00
		WEIGHTED AVERAGE FOR THE SECOND QUARTER		143.00	491.61	578.49	605.61
		WEIGHTED AVERAGE FOR THE YEAR		164.00	491.92	573.06	591.87
===== 614-70030		Optical Attenuator		Each	=====	=====	=====
FSA0253-262		I-25 SB BOTTLENECK I-76 TO I-	01/09/20	1.00	110.00	256.93	235.00
		WEIGHTED AVERAGE FOR THE FIRST QUARTER		1.00	110.00	256.93	235.00
CC0852-106		US-85 LOUVIERS TO MP 191.75	04/23/20	2.00	100.00	164.40	159.50
FBR0852-108		US-85 BETWEEN LOUVIERS AND MP					
C1211-090		SH-121 & 29th Ave / SH-121 &	04/23/20	3.00	96.67	331.93	125.00
ITS SW02-303		R1: US 285, SH 83 R2: SH 83,	05/28/20	6.00	120.00	99.20	90.00
ITSSW01-719		FY 20 ITS CAPITAL REPLACEMENT	06/11/20	1.00	125.00	3000.00	4500.00
		WEIGHTED AVERAGE FOR THE SECOND QUARTER		12.00	111.25	256.03	477.83
		WEIGHTED AVERAGE FOR THE YEAR		13.00	111.15	256.08	459.15

COLORADO DEPARTMENT OF TRANSPORTATION
ITEM UNIT COSTS BY PROJECTS -- 2020 COST DATA

10:58 Friday, October 2, 2020 262

PROJECT NUMBER	ITEM NUMBER/ PROJECT LOCATION	ITEM DESCRIPTION/ PROJECT LOCATION	DATE LET	UNIT/ QUANTITY	ENGR. EST.	AVERAGE BID	AWARDED BID
===== 614-70150		Ped Sig Face (16) (Countdown)		Each	=====		
NHPP0253-265		I-25 AT ERIE PARKWAY ON AND O	01/09/20	12.00	700.00	576.67	690.00
C0402-094		US 40 GRAND COUNTY SIGNAL REP	02/27/20	14.00	700.00	800.00	600.00
NHPP0091-044		SH 9 FRISCO MAIN ST TO IRON S	03/05/20	8.00	800.00	591.67	570.00
NH050A-034		US50A PUEBLO WEST PURCELL INT	03/26/20	6.00	550.00	613.88	630.00
HPP 0501-067		US 50 AND SH 92 DELTA INTERSE	03/26/20	6.00	650.00	666.00	672.00
SHE 0703-461		I-70 and Kipling North Phase	03/26/20	14.00	750.00	592.40	556.00
		WEIGHTED AVERAGE FOR THE FIRST QUARTER		60.00	705.00	625.17	613.93
IM0761-226		I76/SH52 Interchange	04/02/20	4.00	800.00	559.13	508.80
C1211-090		SH-121 & 29th Ave / SH-121 &	04/23/20	20.00	573.10	564.05	455.00
C1601-082		Hawkins Signal and Curb Ramps	04/30/20	8.00	800.00	695.67	935.00
FSA1602-159		US 160 AND SH 17 INTERSECTION	04/30/20	8.00	700.00	625.33	556.00
NHPPR100-303		LONG MAST ARM SIGNALS PROJECT	05/07/20	28.00	700.00	551.00	451.00
FSAR400-356		FY 20 SIGNAL POLE REPLACEMENT	06/11/20	12.00	700.00	671.67	490.00
SHE016A-043		SH 21 & 16 SIGNALS PROJECT	06/18/20	24.00	650.00	548.04	403.21
		WEIGHTED AVERAGE FOR THE SECOND QUARTER		104.00	675.60	578.28	492.77
		WEIGHTED AVERAGE FOR THE YEAR		164.00	686.35	595.48	537.10
===== 614-70200		Access Ped Sig		Each	=====		
C0402-094		US 40 GRAND COUNTY SIGNAL REP	02/27/20	6.00	1800.00	1220.00	1000.00
NH050A-034		US50A PUEBLO WEST PURCELL INT	03/26/20	11.00	1400.00	1685.48	1715.00
		WEIGHTED AVERAGE FOR THE FIRST QUARTER		17.00	1541.18	1629.62	1462.65
FSAR400-356		FY 20 SIGNAL POLE REPLACEMENT	06/11/20	12.00	1200.00	1322.67	1400.00
		WEIGHTED AVERAGE FOR THE SECOND QUARTER		12.00	1200.00	1322.67	1400.00
		WEIGHTED AVERAGE FOR THE YEAR		29.00	1400.00	1548.37	1436.72
===== 614-70225		Traf Sig Face (12-12)		Each	=====		
FSA0253-262		I-25 SB BOTTLENECK I-76 TO I-	01/09/20	2.00	600.00	796.70	730.00
		WEIGHTED AVERAGE FOR THE FIRST QUARTER		2.00	600.00	796.70	730.00
		WEIGHTED AVERAGE FOR THE YEAR		2.00	600.00	796.70	730.00

COLORADO DEPARTMENT OF TRANSPORTATION
 ITEM UNIT COSTS BY PROJECTS -- 2020 COST DATA

10:58 Friday, October 2, 2020 263

PROJECT NUMBER	ITEM NUMBER/ PROJECT LOCATION	ITEM DESCRIPTION/ PROJECT LOCATION	DATE LET	UNIT/ QUANTITY	ENGR. EST.	AVERAGE BID	AWARDED BID
===== 614-70336		Traf Sig Face (12-12-12)		Each =====			
FSA0253-262		I-25 SB BOTTLENECK I-76 TO I-	01/09/20	4.00	900.00	1038.08	950.00
NHPP0253-265		I-25 AT ERIE PARKWAY ON AND O	01/09/20	25.00	975.00	926.67	1065.00
FSA2873-194		US 287 Longmont Intersection	02/13/20	3.00	1000.00	1234.17	825.00
C0402-094		US 40 GRAND COUNTY SIGNAL REP	02/27/20	34.00	1000.00	695.00	70.00
NHPP0091-044		SH 9 FRISCO MAIN ST TO IRON S	03/05/20	21.00	1200.00	738.33	710.00
NH050A-034		US50A PUEBLO WEST PURCELL INT	03/26/20	24.00	700.00	840.34	843.00
HPP 0501-067		US 50 AND SH 92 DELTA INTERSE	03/26/20	18.00	830.00	864.00	896.00
SHE 0703-461		I-70 and Kipling North Phase	03/26/20	31.00	800.00	796.80	750.00
		WEIGHTED AVERAGE FOR THE FIRST QUARTER		160.00	916.97	830.21	686.25
IM0761-226		I76/SH52 Interchange	04/02/20	9.00	1000.00	717.86	658.26
CC0852-106		US-85 LOUVIERS TO MP 191.75	04/23/20	16.00	800.00	1034.89	731.50
FBR0852-108		US-85 BETWEEN LOUVIERS AND MP					
C1211-090		SH-121 & 29th Ave / SH-121 &	04/23/20	48.00	764.84	777.05	645.00
C1601-082		Hawkins Signal and Curb Ramps	04/30/20	11.00	1200.00	802.33	809.00
FSA1602-159		US 160 AND SH 17 INTERSECTION	04/30/20	8.00	800.00	985.00	877.00
NHPPRI00-303		LONG MAST ARM SIGNALS PROJECT	05/07/20	63.00	800.00	724.00	642.00
FSAR400-356		FY 20 SIGNAL POLE REPLACEMENT	06/11/20	21.00	950.00	881.67	650.00
SHE016A-043		SH 21 & 16 SIGNALS PROJECT	06/18/20	39.00	750.00	736.74	811.69
		WEIGHTED AVERAGE FOR THE SECOND QUARTER		215.00	826.57	805.42	698.86
		WEIGHTED AVERAGE FOR THE YEAR		375.00	865.14	815.94	693.48
===== 614-70448		Traf Sig Face (12-12-12-12)		Each =====			
NHPP0091-044		SH 9 FRISCO MAIN ST TO IRON S	03/05/20	2.00	1500.00	1113.33	1100.00
NH050A-034		US50A PUEBLO WEST PURCELL INT	03/26/20	6.00	1100.00	906.43	898.00
HPP 0501-067		US 50 AND SH 92 DELTA INTERSE	03/26/20	2.00	1200.00	1332.00	1344.00
SHE 0703-461		I-70 and Kipling North Phase	03/26/20	6.00	1000.00	1094.20	1026.00
		WEIGHTED AVERAGE FOR THE FIRST QUARTER		16.00	1125.00	1003.89	1027.00
IM0761-226		I76/SH52 Interchange	04/02/20	2.00	1250.00	949.86	827.86
C1211-090		SH-121 & 29th Ave / SH-121 &	04/23/20	10.00	1125.15	995.00	835.00
C1601-082		Hawkins Signal and Curb Ramps	04/30/20	4.00	1300.00	978.00	1000.00
FSA1602-159		US 160 AND SH 17 INTERSECTION	04/30/20	4.00	1200.00	1200.00	1050.00

COLORADO DEPARTMENT OF TRANSPORTATION
 ITEM UNIT COSTS BY PROJECTS -- 2020 COST DATA

10:58 Friday, October 2, 2020 264

PROJECT NUMBER	ITEM NUMBER/ PROJECT LOCATION	ITEM DESCRIPTION/ PROJECT LOCATION	DATE LET	UNIT/ QUANTITY	ENGR. EST.	AVERAGE BID	AWARDED BID
===== 614-70448		Traf Sig Face (12-12-12-12)		Each =====			
NHPPR100-303		LONG MAST ARM SIGNALS PROJECT	05/07/20	9.00	1100.00	905.33	835.00
FSAR400-356		FY 20 SIGNAL POLE REPLACEMENT	06/11/20	8.00	1200.00	1130.00	875.00
SHE016A-043		SH 21 & 16 SIGNALS PROJECT	06/18/20	22.00	800.00	895.14	925.68
	WEIGHTED AVERAGE FOR THE SECOND QUARTER			59.00	1031.38	957.70	899.76
	WEIGHTED AVERAGE FOR THE YEAR			75.00	1051.35	970.52	926.90
===== 614-70560		Traf Sig Face (12-12-12-12-12)		Each =====			
NHPP0091-044		SH 9 FRISCO MAIN ST TO IRON S	03/05/20	7.00	1700.00	1423.33	1400.00
	WEIGHTED AVERAGE FOR THE FIRST QUARTER			7.00	1700.00	1423.33	1400.00
	WEIGHTED AVERAGE FOR THE YEAR			7.00	1700.00	1423.33	1400.00
===== 614-72741		Blank Out Sign (LED) (SPD RDR)		Each =====			
FSA2873-194		US 287 Longmont Intersection	02/13/20	1.00	9500.00	18257.50	16000.00
	WEIGHTED AVERAGE FOR THE FIRST QUARTER			1.00	9500.00	18257.50	16000.00
	WEIGHTED AVERAGE FOR THE YEAR			1.00	9500.00	18257.50	16000.00
===== 614-72829		Communications Cabinet (Install Only)		Each =====			
IM0761-226		I76/SH52 Interchange	04/02/20	1.00	1500.00	1182.35	979.44
	WEIGHTED AVERAGE FOR THE SECOND QUARTER			1.00	1500.00	1182.35	979.44
	WEIGHTED AVERAGE FOR THE YEAR			1.00	1500.00	1182.35	979.44
===== 614-72830		Communications Cabinet		Each =====			
FSA0253-262		I-25 SB BOTTLENECK I-76 TO I-	01/09/20	1.00	16000.00	15277.04	13995.00
	WEIGHTED AVERAGE FOR THE FIRST QUARTER			1.00	16000.00	15277.04	13995.00
	WEIGHTED AVERAGE FOR THE YEAR			1.00	16000.00	15277.04	13995.00
===== 614-72832		Comm Cabinet (Type 2)		Each =====			
ITS0761-231		ITS FIBER AND CAMERAS ON I-76	02/06/20	4.00	12000.00	10934.65	10700.00
	WEIGHTED AVERAGE FOR THE FIRST QUARTER			4.00	12000.00	10934.65	10700.00
	WEIGHTED AVERAGE FOR THE YEAR			4.00	12000.00	10934.65	10700.00

COLORADO DEPARTMENT OF TRANSPORTATION
 ITEM UNIT COSTS BY PROJECTS -- 2020 COST DATA

10:58 Friday, October 2, 2020 265

PROJECT NUMBER	ITEM NUMBER/ PROJECT LOCATION	ITEM DESCRIPTION/ PROJECT LOCATION	DATE LET	UNIT/ QUANTITY	ENGR. EST.	AVERAGE BID	AWARDED BID
=====	614-72836	Conflict Monitor		Each	=====	=====	=====
SHE 0703-461		I-70 and Kipling North Phase	03/26/20	2.00	900.00	1087.20	1020.00
		WEIGHTED AVERAGE FOR THE FIRST QUARTER		2.00	900.00	1087.20	1020.00
CC0852-106		US-85 LOUVIERS TO MP 191.75	04/23/20	1.00	900.00	1041.25	1012.00
FBR0852-108		US-85 BETWEEN LOUVIERS AND MP					
C1211-090		SH-121 & 29th Ave / SH-121 &	04/23/20	3.00	1000.00	1004.53	855.00
		WEIGHTED AVERAGE FOR THE SECOND QUARTER		4.00	975.00	1021.81	894.25
		WEIGHTED AVERAGE FOR THE YEAR		6.00	950.00	1046.03	936.17
=====	614-72854	Traf Ctrl Cabinet		Each	=====	=====	=====
C1601-082		Hawkins Signal and Curb Ramps	04/30/20	1.00	20000.00	36570.00	31000.00
		WEIGHTED AVERAGE FOR THE SECOND QUARTER		1.00	20000.00	36570.00	31000.00
		WEIGHTED AVERAGE FOR THE YEAR		1.00	20000.00	36570.00	31000.00
=====	614-72855	Traf Sig Ctrl Cabinet		Each	=====	=====	=====
NHPP0253-265		I-25 AT ERIE PARKWAY ON AND O	01/09/20	2.00	22000.00	18778.33	18585.00
C0402-094		US 40 GRAND COUNTY SIGNAL REP	02/27/20	2.00	28000.00	31000.00	27000.00
NHPP0091-044		SH 9 FRISCO MAIN ST TO IRON S	03/05/20	2.00	22000.00	32590.00	31600.00
NH050A-034		US50A PUEBLO WEST PURCELL INT	03/26/20	2.00	18000.00	23193.34	23000.00
HPP 0501-067		US 50 AND SH 92 DELTA INTERSE	03/26/20	1.00	16000.00	24929.00	26092.00
SHE 0703-461		I-70 and Kipling North Phase	03/26/20	2.00	15000.00	21490.80	19300.00
		WEIGHTED AVERAGE FOR THE FIRST QUARTER		11.00	20545.45	24274.31	24096.55
IM0761-226		I76/SH52 Interchange	04/02/20	1.00	19000.00	32296.13	30759.08
CC0852-106		US-85 LOUVIERS TO MP 191.75	04/23/20	1.00	15000.00	14012.23	15884.00
FBR0852-108		US-85 BETWEEN LOUVIERS AND MP					
C1211-090		SH-121 & 29th Ave / SH-121 &	04/23/20	3.00	14666.67	16464.63	15055.00
FSA1602-159		US 160 AND SH 17 INTERSECTION	04/30/20	1.00	25000.00	45944.67	36240.00

PROJECT NUMBER	ITEM NUMBER/ PROJECT LOCATION	ITEM DESCRIPTION/ PROJECT LOCATION	DATE LET	UNIT/ QUANTITY	ENGR. EST.	AVERAGE BID	AWARDED BID
===== 614-72855		Traf Sig Ctrl Cabinet		Each =====			
SHE016A-043	SH 21 & 16 SIGNALS PROJECT		06/18/20	3.00	21000.00	25402.60	23881.00
	WEIGHTED AVERAGE FOR THE SECOND QUARTER			9.00	18444.44	23933.94	22187.90
	WEIGHTED AVERAGE FOR THE YEAR			20.00	19600.00	24108.08	23237.65
===== 614-72860		Ped Push Button		Each =====			
NHPP0253-265	I-25 AT ERIE PARKWAY ON AND O		01/09/20	12.00	425.00	260.00	315.00
NHPP 0852-116	US85:HAMPDEN TO FLORIDA-RESUR		02/06/20	1.00	700.00	1181.00	2000.00
C0402-094	US 40 GRAND COUNTY SIGNAL REP		02/27/20	8.00	400.00	757.50	515.00
NHPP0091-044	SH 9 FRISCO MAIN ST TO IRON S		03/05/20	8.00	1500.00	353.33	340.00
HPP 0501-067	US 50 AND SH 92 DELTA INTERSE		03/26/20	2.00	260.00	499.50	504.00
SHE 0703-461	I-70 and Kipling North Phase		03/26/20	14.00	1000.00	219.60	200.00
	WEIGHTED AVERAGE FOR THE FIRST QUARTER			45.00	789.33	326.92	365.07
IM0761-226	I76/SH52 Interchange		04/02/20	4.00	500.00	1069.26	1350.44
C1211-090	SH-121 & 29th Ave / SH-121 &		04/23/20	20.00	422.10	1634.48	1165.00
FSA1602-159	US 160 AND SH 17 INTERSECTION		04/30/20	7.00	600.00	2382.00	2120.00
NHPPR100-303	LONG MAST ARM SIGNALS PROJECT		05/07/20	23.00	900.00	286.67	220.00
SHE016A-043	SH 21 & 16 SIGNALS PROJECT		06/18/20	24.00	618.00	1158.62	1171.83
	WEIGHTED AVERAGE FOR THE SECOND QUARTER			78.00	643.26	1130.35	983.66
	WEIGHTED AVERAGE FOR THE YEAR			123.00	696.70	858.97	757.35
===== 614-72863		Ped Push Button Post Assem		Each =====			
NHPP 0852-116	US85:HAMPDEN TO FLORIDA-RESUR		02/06/20	1.00	2500.00	2890.50	3200.00
C0402-094	US 40 GRAND COUNTY SIGNAL REP		02/27/20	11.00	2500.00	2250.00	2000.00
STRR300-249	Grand and Jackson Counties AD		03/05/20	1.00	2500.00	6533.33	2500.00
NHPP0091-044	SH 9 FRISCO MAIN ST TO IRON S		03/05/20	1.00	1500.00	2243.33	2200.00
NH050A-034	US50A PUEBLO WEST PURCELL INT		03/26/20	1.00	3000.00	2020.39	2200.00
HPP 0501-067	US 50 AND SH 92 DELTA INTERSE		03/26/20	2.00	1800.00	1887.00	1904.00
SHE 0703-461	I-70 and Kipling North Phase		03/26/20	5.00	2000.00	1554.00	1460.00
	WEIGHTED AVERAGE FOR THE FIRST QUARTER			22.00	2300.00	2151.82	1964.00
IM0761-226	I76/SH52 Interchange		04/02/20	3.00	2500.00	1417.76	1594.24

COLORADO DEPARTMENT OF TRANSPORTATION
ITEM UNIT COSTS BY PROJECTS -- 2020 COST DATA

10:58 Friday, October 2, 2020 267

PROJECT NUMBER	ITEM NUMBER/ PROJECT LOCATION	ITEM DESCRIPTION/ PROJECT LOCATION	DATE LET	UNIT/ QUANTITY	ENGR. EST.	AVERAGE BID	AWARDED BID
=====	614-72863	Ped Push Button Post Assem		Each =====			
C1211-090	SH-121 & 29th Ave / SH-121 &	SH-121 & 29th Ave / SH-121 &	04/23/20	20.00	2793.70	1018.97	770.00
C1601-082	Hawkins Signal and Curb Ramps	Hawkins Signal and Curb Ramps	04/30/20	40.00	2500.00	2729.33	2300.00
FSA1602-159	US 160 AND SH 17 INTERSECTION	US 160 AND SH 17 INTERSECTION	04/30/20	6.00	1500.00	1402.67	1230.00
NHPPR100-303	LONG MAST ARM SIGNALS PROJECT	LONG MAST ARM SIGNALS PROJECT	05/07/20	5.00	2000.00	1316.67	1100.00
FSAR400-356	FY 20 SIGNAL POLE REPLACEMENT	FY 20 SIGNAL POLE REPLACEMENT	06/11/20	3.00	1750.00	985.00	800.00
	WEIGHTED AVERAGE FOR THE SECOND QUARTER			77.00	2436.68	1943.60	1655.36
	WEIGHTED AVERAGE FOR THE YEAR			99.00	2406.30	1988.60	1723.95
=====	614-72864	Fire Preempt Unit		Each =====			
IM0761-226	I76/SH52 Interchange	I76/SH52 Interchange	04/02/20	1.00	13000.00	8714.97	8695.18
	WEIGHTED AVERAGE FOR THE SECOND QUARTER			1.00	13000.00	8714.97	8695.18
	WEIGHTED AVERAGE FOR THE YEAR			1.00	13000.00	8714.97	8695.18
=====	614-72866	Fire Preempt Unit + Timer		Each =====			
NHPP0253-265	I-25 AT ERIE PARKWAY ON AND O	I-25 AT ERIE PARKWAY ON AND O	01/09/20	2.00	5000.00	5843.33	4465.00
SHE 0703-461	I-70 and Kipling North Phase	I-70 and Kipling North Phase	03/26/20	8.00	4000.00	4279.00	4015.00
	WEIGHTED AVERAGE FOR THE FIRST QUARTER			10.00	4200.00	4483.04	4105.00
C1601-082	Hawkins Signal and Curb Ramps	Hawkins Signal and Curb Ramps	04/30/20	2.00	5000.00	6666.67	6800.00
FSA1602-159	US 160 AND SH 17 INTERSECTION	US 160 AND SH 17 INTERSECTION	04/30/20	2.00	5000.00	6424.33	5720.00
	WEIGHTED AVERAGE FOR THE SECOND QUARTER			4.00	5000.00	6545.50	6260.00
	WEIGHTED AVERAGE FOR THE YEAR			14.00	4428.57	4909.76	4720.71
=====	614-72868	Bicycle and Ped Traf Count		Each =====			
IM0761-226	I76/SH52 Interchange	I76/SH52 Interchange	04/02/20	1.00	3600.00	10954.66	8028.44
	WEIGHTED AVERAGE FOR THE SECOND QUARTER			1.00	3600.00	10954.66	8028.44
	WEIGHTED AVERAGE FOR THE YEAR			1.00	3600.00	10954.66	8028.44

PROJECT NUMBER	ITEM NUMBER/ PROJECT LOCATION	ITEM DESCRIPTION/ PROJECT LOCATION	DATE LET	UNIT/ QUANTITY	ENGR. EST.	AVERAGE BID	AWARDED BID
===== 614-72875		Loop Detect Wire		Lin Foot	=====		
STA0703-443		I-70 EJMT TUNNELS PAVING	02/06/20	3,640.00	7.00	7.25	7.55
C0402-094		US 40 GRAND COUNTY SIGNAL REP	02/27/20	950.00	7.00	11.00	2.00
HPP 0501-067		US 50 AND SH 92 DELTA INTERSE	03/26/20	950.00	4.60	9.83	10.10
		WEIGHTED AVERAGE FOR THE FIRST QUARTER		5,540.00	6.59	8.33	7.04
NHPP0402-098		US 40 CHIP SEAL MP 126 TO MP	05/14/20	420.00	6.00	16.25	16.00
		WEIGHTED AVERAGE FOR THE SECOND QUARTER		420.00	6.00	16.25	16.00
		WEIGHTED AVERAGE FOR THE YEAR		5,960.00	6.55	9.14	7.67
===== 614-72884		Detect (Micro Wave)		Each	=====		
FSA0253-262		I-25 SB BOTTLENECK I-76 TO I-	01/09/20	2.00	9100.00	9099.65	8330.00
C0402-094		US 40 GRAND COUNTY SIGNAL REP	02/27/20	5.00	9000.00	9800.00	10000.00
		WEIGHTED AVERAGE FOR THE FIRST QUARTER		7.00	9028.57	9537.37	9522.86
		WEIGHTED AVERAGE FOR THE YEAR		7.00	9028.57	9537.37	9522.86
===== 614-72885		Detect (Spec)		Each	=====		
CC0852-106		US-85 LOUVIERS TO MP 191.75	04/23/20	6.00	7500.00	9411.00	9223.50
FBR0852-108		US-85 BETWEEN LOUVIERS AND MP					
C1211-090		SH-121 & 29th Ave / SH-121 &	04/23/20	24.00	9933.33	7903.60	7685.00
C1601-082		Hawkins Signal and Curb Ramps	04/30/20	6.00	8500.00	10297.78	10200.00
FSA1602-159		US 160 AND SH 17 INTERSECTION	04/30/20	6.00	7000.00	10298.44	9156.67
NHPPR100-303		LONG MAST ARM SIGNALS PROJECT	05/07/20	28.00	8000.00	8044.67	7775.00
		WEIGHTED AVERAGE FOR THE SECOND QUARTER		70.00	8577.14	8613.63	8194.59
		WEIGHTED AVERAGE FOR THE YEAR		70.00	8577.14	8613.63	8194.59
===== 614-72886		Intersection Detect Sys (Camera)		Each	=====		
NHPP0253-265		I-25 AT ERIE PARKWAY ON AND O	01/09/20	6.00	8500.00	7848.33	7095.00
		WEIGHTED AVERAGE FOR THE FIRST QUARTER		6.00	8500.00	7848.33	7095.00

COLORADO DEPARTMENT OF TRANSPORTATION
 ITEM UNIT COSTS BY PROJECTS -- 2020 COST DATA

10:58 Friday, October 2, 2020 269

PROJECT NUMBER	ITEM NUMBER/ PROJECT LOCATION	ITEM DESCRIPTION/ PROJECT LOCATION	DATE LET	UNIT/ QUANTITY	ENGR. EST.	AVERAGE BID	AWARDED BID
=====	614-72886	Intersection Detect Sys (Camera)		Each	=====	=====	=====
FSAR400-356		FY 20 SIGNAL POLE REPLACEMENT	06/11/20	6.00	5500.00	11384.00	12525.00
		WEIGHTED AVERAGE FOR THE SECOND QUARTER		6.00	5500.00	11384.00	12525.00
		WEIGHTED AVERAGE FOR THE YEAR		12.00	7000.00	9616.17	9810.00
=====	614-72887	Detect (Microwave Veh)		Each	=====	=====	=====
FSA0253-262		I-25 SB BOTTLENECK I-76 TO I-	01/09/20	5.00	9300.00	12912.29	11820.00
SHE 0703-461		I-70 and Kipling North Phase	03/26/20	9.00	11500.00	9333.00	8720.00
		WEIGHTED AVERAGE FOR THE FIRST QUARTER		14.00	10714.29	10227.82	9827.14
IM0761-226		I76/SH52 Interchange	04/02/20	6.00	7000.00	8790.26	8235.14
		WEIGHTED AVERAGE FOR THE SECOND QUARTER		6.00	7000.00	8790.26	8235.14
		WEIGHTED AVERAGE FOR THE YEAR		20.00	9600.00	9635.88	9349.54
=====	614-72895	Vehicle Detect Sys (Single Camera)		Each	=====	=====	=====
NHPP0091-044		SH 9 FRISCO MAIN ST TO IRON S	03/05/20	3.00	10000.00	18800.00	18100.00
NH050A-034		US50A PUEBLO WEST PURCELL INT	03/26/20	2.00	9500.00	20679.21	21250.00
SHE 0703-461		I-70 and Kipling North Phase	03/26/20	1.00	12000.00	8725.60	8200.00
		WEIGHTED AVERAGE FOR THE FIRST QUARTER		6.00	10166.67	18123.18	17500.00
SHE016A-043		SH 21 & 16 SIGNALS PROJECT	06/18/20	1.00	10000.00	9267.40	6223.00
		WEIGHTED AVERAGE FOR THE SECOND QUARTER		1.00	10000.00	9267.40	6223.00
		WEIGHTED AVERAGE FOR THE YEAR		7.00	10142.86	16858.07	15889.00
=====	614-72896	Inst Intersect Detect Sys (Camera)		Each	=====	=====	=====
SHE016A-043		SH 21 & 16 SIGNALS PROJECT	06/18/20	8.00	1500.00	2259.85	232.25
		WEIGHTED AVERAGE FOR THE SECOND QUARTER		8.00	1500.00	2259.85	232.25
		WEIGHTED AVERAGE FOR THE YEAR		8.00	1500.00	2259.85	232.25

COLORADO DEPARTMENT OF TRANSPORTATION
ITEM UNIT COSTS BY PROJECTS -- 2020 COST DATA

10:58 Friday, October 2, 2020 270

PROJECT NUMBER	ITEM NUMBER/ PROJECT LOCATION	ITEM DESCRIPTION/ PROJECT LOCATION	DATE LET	UNIT/ QUANTITY	ENGR. EST.	AVERAGE BID	AWARDED BID
=====	614-73005	Piezo (Elec) (CL II)		Each	=====	=====	=====
STA0703-443		I-70 EJMT TUNNELS PAVING	02/06/20	10.00	6000.00	3046.50	3173.00
NHPP0502-082		US 50 MONTROSE RE CHIP SEAL	03/05/20	2.00	3000.00	7550.00	2700.00
		WEIGHTED AVERAGE FOR THE FIRST QUARTER		12.00	5500.00	4333.21	3094.17
NHPP1601-077		US 160 MP 29.750 - MP 34.891	04/09/20	2.00	3000.00	8333.33	12000.00
		WEIGHTED AVERAGE FOR THE SECOND QUARTER		2.00	3000.00	8333.33	12000.00
		WEIGHTED AVERAGE FOR THE YEAR		14.00	5142.86	5039.12	4366.43
=====	614-75868	Inst Fire Preempt Unit		Each	=====	=====	=====
CC0852-106		US-85 LOUVIERS TO MP 191.75	04/23/20	2.00	4000.00	758.69	737.00
FBR0852-108		US-85 BETWEEN LOUVIERS AND MP					
		WEIGHTED AVERAGE FOR THE SECOND QUARTER		2.00	4000.00	758.69	737.00
		WEIGHTED AVERAGE FOR THE YEAR		2.00	4000.00	758.69	737.00
=====	614-80000	Flash Beacon		Each	=====	=====	=====
FSA0253-262		I-25 SB BOTTLENECK I-76 TO I-	01/09/20	2.00	2700.00	2867.67	2625.00
		WEIGHTED AVERAGE FOR THE FIRST QUARTER		2.00	2700.00	2867.67	2625.00
SHE016A-043		SH 21 & 16 SIGNALS PROJECT	06/18/20	6.00	1700.00	2754.55	2209.50
		WEIGHTED AVERAGE FOR THE SECOND QUARTER		6.00	1700.00	2754.55	2209.50
		WEIGHTED AVERAGE FOR THE YEAR		8.00	1950.00	2773.40	2313.38
=====	614-80003	Rect Rapid Flash Beacon		Each	=====	=====	=====
FSA0341-097		US 34 & MACGREGOR INTERSECTIO	01/09/20	1.00	7000.00	19000.00	19000.00
		WEIGHTED AVERAGE FOR THE FIRST QUARTER		1.00	7000.00	19000.00	19000.00

COLORADO DEPARTMENT OF TRANSPORTATION
 ITEM UNIT COSTS BY PROJECTS -- 2020 COST DATA

10:58 Friday, October 2, 2020 271

PROJECT NUMBER	ITEM NUMBER/ PROJECT LOCATION	ITEM DESCRIPTION/ PROJECT LOCATION	DATE LET	UNIT/ QUANTITY	ENGR. EST.	AVERAGE BID	AWARDED BID
===== 614-80003		Rect Rapid Flash Beacon		Each	=====	=====	=====
IM0761-226		I76/SH52 Interchange	04/02/20	4.00	9000.00	5377.63	3869.00
		WEIGHTED AVERAGE FOR THE SECOND QUARTER		4.00	9000.00	5377.63	3869.00
		WEIGHTED AVERAGE FOR THE YEAR		5.00	8600.00	5847.36	6895.20
===== 614-80313		Barricade (Ty 3 F-C)		Each	=====	=====	=====
NHPP0343-041		I-76 & US 34 FT. MORGAN AREA	01/09/20	1.00	3817.00	3590.51	3685.00
		WEIGHTED AVERAGE FOR THE FIRST QUARTER		1.00	3817.00	3590.51	3685.00
		WEIGHTED AVERAGE FOR THE YEAR		1.00	3817.00	3590.51	3685.00
===== 614-80322		Barricade (Ty 3 M-B)		Each	=====	=====	=====
IM0761-226		I76/SH52 Interchange	04/02/20	2.00	400.00	1370.00	1590.00
		WEIGHTED AVERAGE FOR THE SECOND QUARTER		2.00	400.00	1370.00	1590.00
		WEIGHTED AVERAGE FOR THE YEAR		2.00	400.00	1370.00	1590.00
===== 614-80385		Rumble Strip		Lin Foot	=====	=====	=====
NHPP0343-041		I-76 & US 34 FT. MORGAN AREA	01/09/20	66,552.00	0.30	0.24	0.10
NH 0503-093		US50 WEST OF TEXAS CREEK MP 2	01/23/20	54,600.00	0.20	0.10	0.11
FSA2873-194		US 287 Longmont Intersection	02/13/20	300.00	8.00	19.00	33.00
C0641-106		SH 64 Meeker West Rural Resur	03/05/20	62,703.00	0.35	0.13	0.15
NHPP0502-082		US 50 MONTROSE RE CHIP SEAL	03/05/20	33,096.00	0.40	0.21	0.20
BR025A-046		K-18-U ON I-25 AT MP112 BRIDG	03/05/20	512.00	0.25	6.28	3.22
		WEIGHTED AVERAGE FOR THE FIRST QUARTER		217,763.00	0.32	0.27	0.18
NHPP1602-169		US 160 WC TUNNEL EAST RESURFA	04/02/20	900.00	5.00	4.67	6.59
IM0761-226		I76/SH52 Interchange	04/02/20	200.00	2.00	9.63	21.20
		WEIGHTED AVERAGE FOR THE SECOND QUARTER		1,100.00	4.45	6.37	9.25
		WEIGHTED AVERAGE FOR THE YEAR		218,863.00	0.34	0.32	0.23

COLORADO DEPARTMENT OF TRANSPORTATION
ITEM UNIT COSTS BY PROJECTS -- 2020 COST DATA

10:58 Friday, October 2, 2020 272

PROJECT NUMBER	ITEM NUMBER/ PROJECT LOCATION	ITEM DESCRIPTION/ PROJECT LOCATION	DATE LET	UNIT/ QUANTITY	ENGR. EST.	AVERAGE BID	AWARDED BID
===== 614-80390		Rumble Strip (Grinding) (Asphalt) (Sin)		Lin Foot	=====		
STR0101-027		SH 10 Overlay La Junta West	02/27/20	259,958.00	0.35	0.20	0.20
NH050A-034		US50A PUEBLO WEST PURCELL INT	03/26/20	19,430.00	0.50	0.74	0.64
		WEIGHTED AVERAGE FOR THE FIRST QUARTER		279,388.00	0.36	0.29	0.23
		WEIGHTED AVERAGE FOR THE YEAR		279,388.00	0.36	0.29	0.23
===== 614-80391		Rumble Strip (Grind) (Asphalt)		Lin Foot	=====		
STA0142-066		SH 14 New Raymer West	01/09/20	109,510.00	0.12	0.13	0.13
SHER500-210		R5 FY19 CENTER LINE RUMBLE ST	01/09/20	828,644.00	0.30	0.47	0.42
STA006A-067		SH 6 Merino to Atwood	01/16/20	30,870.00	0.25	0.14	0.17
STR141A-044		SH 141 AND SH 145, FROM SLICK	01/30/20	123,391.00	0.20	0.34	0.30
NHPP0171-105		SH 17 MP 84.5 to US 285 & SH	03/05/20	86,127.00	0.25	0.14	0.12
		WEIGHTED AVERAGE FOR THE FIRST QUARTER		1,178,542.00	0.27	0.36	0.35
STR0341-101		SH 34 North of Grandby Resurf	04/02/20	156,000.00	0.10	0.12	0.12
NHPP1601-077		US 160 MP 29.750 - MP 34.891	04/09/20	37,155.00	0.35	0.22	0.25
		WEIGHTED AVERAGE FOR THE SECOND QUARTER		193,155.00	0.15	0.13	0.15
		WEIGHTED AVERAGE FOR THE YEAR		1,371,697.00	0.25	0.31	0.32
===== 614-81000		Sig-Light Pole Steel		Each	=====		
FSA0253-262		I-25 SB BOTTLENECK I-76 TO I-	01/09/20	1.00	13000.00	7500.71	6855.00
SHE 0703-461		I-70 and Kipling North Phase	03/26/20	1.00	15000.00	15554.00	14720.00
		WEIGHTED AVERAGE FOR THE FIRST QUARTER		2.00	14000.00	12534.02	10787.50
		WEIGHTED AVERAGE FOR THE YEAR		2.00	14000.00	12534.02	10787.50
===== 614-81020		Sig-Light Pole Steel (2)		Each	=====		
NHPP0253-265		I-25 AT ERIE PARKWAY ON AND O	01/09/20	2.00	29210.00	32821.67	30955.00
NH050A-034		US50A PUEBLO WEST PURCELL INT	03/26/20	2.00	20000.00	44654.34	47000.00
		WEIGHTED AVERAGE FOR THE FIRST QUARTER		4.00	24605.00	41427.25	38977.50

COLORADO DEPARTMENT OF TRANSPORTATION
 ITEM UNIT COSTS BY PROJECTS -- 2020 COST DATA

10:58 Friday, October 2, 2020 273

PROJECT NUMBER	ITEM NUMBER/ PROJECT LOCATION	ITEM DESCRIPTION/ PROJECT LOCATION	DATE LET	UNIT/ QUANTITY	ENGR. EST.	AVERAGE BID	AWARDED BID
=====	614-81020	Sig-Light Pole Steel (2)		Each	=====	=====	=====
FSAR400-356		FY 20 SIGNAL POLE REPLACEMENT	06/11/20	1.00	30000.00	24303.33	23000.00
		WEIGHTED AVERAGE FOR THE SECOND QUARTER		1.00	30000.00	24303.33	23000.00
		WEIGHTED AVERAGE FOR THE YEAR		5.00	25684.00	39372.38	35782.00
=====	614-81125	Sig-Light Pole Steel (1-25 Ft)		Each	=====	=====	=====
C0402-094		US 40 GRAND COUNTY SIGNAL REP	02/27/20	1.00	13000.00	25500.00	16000.00
SHE 0703-461		I-70 and Kipling North Phase	03/26/20	1.00	16000.00	21996.00	20842.00
		WEIGHTED AVERAGE FOR THE FIRST QUARTER		2.00	14500.00	22997.14	18421.00
CC0852-106		US-85 LOUVIERS TO MP 191.75	04/23/20	2.00	18000.00	12874.95	12650.00
FBR0852-108		US-85 BETWEEN LOUVIERS AND MP					
FSA1602-159		US 160 AND SH 17 INTERSECTION	04/30/20	1.00	15000.00	26694.00	21910.00
FSAR400-356		FY 20 SIGNAL POLE REPLACEMENT	06/11/20	1.00	13000.00	14074.00	12500.00
		WEIGHTED AVERAGE FOR THE SECOND QUARTER		4.00	16000.00	14922.87	14927.50
		WEIGHTED AVERAGE FOR THE YEAR		6.00	15500.00	16871.83	16092.00
=====	614-81130	Sig-Light Pole Steel (1-30 Ft)		Each	=====	=====	=====
C0402-094		US 40 GRAND COUNTY SIGNAL REP	02/27/20	2.00	14000.00	26000.00	17000.00
		WEIGHTED AVERAGE FOR THE FIRST QUARTER		2.00	14000.00	26000.00	17000.00
IM0761-226		I76/SH52 Interchange	04/02/20	1.00	15000.00	17646.61	16008.12
C1211-090		SH-121 & 29th Ave / SH-121 &	04/23/20	1.00	14000.00	12537.05	11500.00
NHPPR100-303		LONG MAST ARM SIGNALS PROJECT	05/07/20	3.00	17000.00	13843.67	11355.00
FSAR400-356		FY 20 SIGNAL POLE REPLACEMENT	06/11/20	1.00	15000.00	14734.33	13250.00
		WEIGHTED AVERAGE FOR THE SECOND QUARTER		6.00	15833.33	14996.98	12470.52
		WEIGHTED AVERAGE FOR THE YEAR		8.00	15375.00	16689.75	13602.89

COLORADO DEPARTMENT OF TRANSPORTATION
 ITEM UNIT COSTS BY PROJECTS -- 2020 COST DATA

10:58 Friday, October 2, 2020 274

PROJECT NUMBER	ITEM NUMBER/ PROJECT LOCATION	ITEM DESCRIPTION/ PROJECT LOCATION	DATE LET	UNIT/ QUANTITY	ENGR. EST.	AVERAGE BID	AWARDED BID
=====	614-81135	Sig-Light Pole Steel (1-35 Ft)		Each	=====		
FSA0253-262		I-25 SB BOTTLENECK I-76 TO I-	01/09/20	1.00	18000.00	15112.65	13835.00
C0402-094		US 40 GRAND COUNTY SIGNAL REP	02/27/20	1.00	15000.00	26500.00	18000.00
SHE 0703-461		I-70 and Kipling North Phase	03/26/20	1.00	18000.00	23288.20	21925.00
		WEIGHTED AVERAGE FOR THE FIRST QUARTER		3.00	17000.00	21477.89	17920.00
C1601-082		Hawkins Signal and Curb Ramps	04/30/20	1.00	16000.00	24666.67	21000.00
FSA1602-159		US 160 AND SH 17 INTERSECTION	04/30/20	1.00	15000.00	29668.00	23630.00
		WEIGHTED AVERAGE FOR THE SECOND QUARTER		2.00	15500.00	27167.33	22315.00
		WEIGHTED AVERAGE FOR THE YEAR		5.00	16400.00	23611.43	19678.00
=====	614-81140	Sig-Light Pole Steel (1-40 Ft)		Each	=====		
NHPP0091-044		SH 9 FRISCO MAIN ST TO IRON S	03/05/20	2.00	17000.00	21806.67	21000.00
		WEIGHTED AVERAGE FOR THE FIRST QUARTER		2.00	17000.00	21806.67	21000.00
CC0852-106		US-85 LOUVIERS TO MP 191.75	04/23/20	1.00	20000.00	15380.38	15075.50
FBR0852-108		US-85 BETWEEN LOUVIERS AND MP					
C1211-090		SH-121 & 29th Ave / SH-121 &	04/23/20	1.00	15000.00	13759.00	12777.00
C1601-082		Hawkins Signal and Curb Ramps	04/30/20	1.00	18000.00	26066.67	22000.00
NHPPR100-303		LONG MAST ARM SIGNALS PROJECT	05/07/20	1.00	18000.00	15092.00	12630.00
FSAR400-356		FY 20 SIGNAL POLE REPLACEMENT	06/11/20	1.00	19000.00	16714.00	15555.00
		WEIGHTED AVERAGE FOR THE SECOND QUARTER		5.00	18000.00	16896.90	15607.50
		WEIGHTED AVERAGE FOR THE YEAR		7.00	17714.29	18029.92	17148.21
=====	614-81145	Sig-Light Pole Steel (1-45 Ft)		Each	=====		
NHPP0091-044		SH 9 FRISCO MAIN ST TO IRON S	03/05/20	2.00	18000.00	22046.67	21200.00
NH050A-034		US50A PUEBLO WEST PURCELL INT	03/26/20	1.00	16250.00	27122.99	30000.00
HPP 0501-067		US 50 AND SH 92 DELTA INTERSE	03/26/20	1.00	15500.00	21400.00	22400.00
SHE 0703-461		I-70 and Kipling North Phase	03/26/20	4.00	20000.00	25484.00	24000.00
		WEIGHTED AVERAGE FOR THE FIRST QUARTER		8.00	18468.75	25048.44	23850.00

COLORADO DEPARTMENT OF TRANSPORTATION
 ITEM UNIT COSTS BY PROJECTS -- 2020 COST DATA

10:58 Friday, October 2, 2020 275

PROJECT NUMBER	ITEM NUMBER/ PROJECT LOCATION	ITEM DESCRIPTION/ PROJECT LOCATION	DATE LET	UNIT/ QUANTITY	ENGR. EST.	AVERAGE BID	AWARDED BID
===== 614-81145		Sig-Light Pole Steel (1-45 Ft)		Each	=====	=====	=====
IM0761-226		I76/SH52 Interchange	04/02/20	2.00	16000.00	18934.31	17577.98
	WEIGHTED AVERAGE FOR THE SECOND QUARTER			2.00	16000.00	18934.31	17577.98
	WEIGHTED AVERAGE FOR THE YEAR			10.00	17975.00	23336.48	22595.60
===== 614-81150		Sig-Light Pole Steel (1-50 Ft)		Each	=====	=====	=====
NHPP0253-265		I-25 AT ERIE PARKWAY ON AND O	01/09/20	1.00	21000.00	15210.00	15380.00
HPP 0501-067		US 50 AND SH 92 DELTA INTERSE	03/26/20	1.00	16000.00	21826.50	22845.00
SHE 0703-461		I-70 and Kipling North Phase	03/26/20	1.00	22000.00	26288.80	24750.00
	WEIGHTED AVERAGE FOR THE FIRST QUARTER			3.00	19666.67	22072.70	20991.67
C1211-090		SH-121 & 29th Ave / SH-121 &	04/23/20	4.00	15372.63	14564.83	13500.00
C1601-082		Hawkins Signal and Curb Ramps	04/30/20	1.00	19000.00	27600.00	23000.00
FSA1602-159		US 160 AND SH 17 INTERSECTION	04/30/20	2.00	20000.00	32756.00	26370.00
NHPPR100-303		LONG MAST ARM SIGNALS PROJECT	05/07/20	1.00	19000.00	15843.67	13350.00
FSAR400-356		FY 20 SIGNAL POLE REPLACEMENT	06/11/20	1.00	23000.00	17463.67	16125.00
	WEIGHTED AVERAGE FOR THE SECOND QUARTER			9.00	18054.50	20519.85	17690.56
	WEIGHTED AVERAGE FOR THE YEAR			12.00	18457.54	20939.54	18515.83
===== 614-81155		Sig-Light Pole Steel (1-55 Ft)		Each	=====	=====	=====
NHPP0253-265		I-25 AT ERIE PARKWAY ON AND O	01/09/20	1.00	22000.00	15584.67	15532.00
C0402-094		US 40 GRAND COUNTY SIGNAL REP	02/27/20	2.00	18000.00	28000.00	21000.00
NH050A-034		US50A PUEBLO WEST PURCELL INT	03/26/20	1.00	16500.00	29000.45	31500.00
HPP 0501-067		US 50 AND SH 92 DELTA INTERSE	03/26/20	1.00	16500.00	22354.00	23180.00
SHE 0703-461		I-70 and Kipling North Phase	03/26/20	1.00	25000.00	26576.40	25052.00
	WEIGHTED AVERAGE FOR THE FIRST QUARTER			6.00	19333.33	25833.98	22877.33
C1211-090		SH-121 & 29th Ave / SH-121 &	04/23/20	1.00	13695.50	14982.05	13585.00

COLORADO DEPARTMENT OF TRANSPORTATION
ITEM UNIT COSTS BY PROJECTS -- 2020 COST DATA

10:58 Friday, October 2, 2020 276

PROJECT NUMBER	ITEM NUMBER/ PROJECT LOCATION	ITEM DESCRIPTION/ PROJECT LOCATION	DATE LET	UNIT/ QUANTITY	ENGR. EST.	AVERAGE BID	AWARDED BID
===== 614-81155		Sig-Light Pole Steel (1-55 Ft)		Each =====			
C1601-082		Hawkins Signal and Curb Ramps	04/30/20	1.00	21000.00	29166.67	23000.00
FSAR400-356		FY 20 SIGNAL POLE REPLACEMENT	06/11/20	1.00	24000.00	17690.00	16500.00
SHE016A-043		SH 21 & 16 SIGNALS PROJECT	06/18/20	1.00	20000.00	17705.20	20080.00
	WEIGHTED AVERAGE FOR THE SECOND QUARTER			4.00	19673.88	19574.44	18291.25
	WEIGHTED AVERAGE FOR THE YEAR			10.00	19469.55	23399.71	21042.90
===== 614-81160		Sig-Light Pole Steel (1-60 Ft)		Each =====			
C0402-094		US 40 GRAND COUNTY SIGNAL REP	02/27/20	2.00	25000.00	32500.00	30000.00
	WEIGHTED AVERAGE FOR THE FIRST QUARTER			2.00	25000.00	32500.00	30000.00
CC0852-106		US-85 LOUVIERS TO MP 191.75	04/23/20	1.00	25000.00	26033.33	25410.00
FBR0852-108		US-85 BETWEEN LOUVIERS AND MP					
FSAR400-356		FY 20 SIGNAL POLE REPLACEMENT	06/11/20	1.00	30000.00	25619.33	24555.00
	WEIGHTED AVERAGE FOR THE SECOND QUARTER			2.00	27500.00	25920.42	24982.50
	WEIGHTED AVERAGE FOR THE YEAR			4.00	26250.00	27674.97	27491.25
===== 614-81165		Sig-Light Pole Steel (1-65 Ft)		Each =====			
NHPP0091-044		SH 9 FRISCO MAIN ST TO IRON S	03/05/20	1.00	28000.00	33638.33	32400.00
	WEIGHTED AVERAGE FOR THE FIRST QUARTER			1.00	28000.00	33638.33	32400.00
CC0852-106		US-85 LOUVIERS TO MP 191.75	04/23/20	1.00	26000.00	26283.87	25690.50
FBR0852-108		US-85 BETWEEN LOUVIERS AND MP					
C1211-090		SH-121 & 29th Ave / SH-121 &	04/23/20	2.00	24000.00	22272.83	20785.00
NHPPR100-303		LONG MAST ARM SIGNALS PROJECT	05/07/20	5.00	22000.00	22325.00	20200.00
SHE016A-043		SH 21 & 16 SIGNALS PROJECT	06/18/20	5.00	24000.00	24065.20	24220.00
	WEIGHTED AVERAGE FOR THE SECOND QUARTER			13.00	23384.62	23711.35	22258.50
	WEIGHTED AVERAGE FOR THE YEAR			14.00	23714.29	24233.82	22982.89
===== 614-81170		Sig-Light Pole Steel (1-70 Ft)		Each =====			
SHE016A-043		SH 21 & 16 SIGNALS PROJECT	06/18/20	1.00	27500.00	26102.40	27095.00
	WEIGHTED AVERAGE FOR THE SECOND QUARTER			1.00	27500.00	26102.40	27095.00
	WEIGHTED AVERAGE FOR THE YEAR			1.00	27500.00	26102.40	27095.00

COLORADO DEPARTMENT OF TRANSPORTATION
ITEM UNIT COSTS BY PROJECTS -- 2020 COST DATA

10:58 Friday, October 2, 2020 277

PROJECT NUMBER	ITEM NUMBER/ PROJECT LOCATION	ITEM DESCRIPTION/ PROJECT LOCATION	DATE LET	UNIT/ QUANTITY	ENGR. EST.	AVERAGE BID	AWARDED BID
=====	614-81175	Sig-Light Pole Steel (1-75 Ft)		Each	=====		
C1211-090		SH-121 & 29th Ave / SH-121 &	04/23/20	1.00	24995.50	24777.42	23040.00
NHPPR100-303		LONG MAST ARM SIGNALS PROJECT	05/07/20	2.00	33000.00	25027.33	22661.00
SHE016A-043		SH 21 & 16 SIGNALS PROJECT	06/18/20	5.00	30000.00	26476.20	27548.00
		WEIGHTED AVERAGE FOR THE SECOND QUARTER		8.00	30124.44	26070.63	25762.75
		WEIGHTED AVERAGE FOR THE YEAR		8.00	30124.44	26070.63	25762.75
=====	614-82015	Sig Pole Steel (1) (Spec)		Each	=====		
C1211-090		SH-121 & 29th Ave / SH-121 &	04/23/20	2.00	30000.00	43625.20	41750.00
NHPPR100-303		LONG MAST ARM SIGNALS PROJECT	05/07/20	2.00	60000.00	36507.67	34603.00
		WEIGHTED AVERAGE FOR THE SECOND QUARTER		4.00	45000.00	40066.43	38176.50
		WEIGHTED AVERAGE FOR THE YEAR		4.00	45000.00	40066.43	38176.50
=====	614-84000	Traf Sig Ped Pole Steel		Each	=====		
FSA0253-262		I-25 SB BOTTLENECK I-76 TO I-	01/09/20	2.00	3500.00	2793.26	2550.00
NHPP0253-265		I-25 AT ERIE PARKWAY ON AND O	01/09/20	4.00	2800.00	1931.67	1795.00
NHPP0091-044		SH 9 FRISCO MAIN ST TO IRON S	03/05/20	3.00	4000.00	3576.67	3600.00
NH050A-034		US50A PUEBLO WEST PURCELL INT	03/26/20	7.00	2200.00	2887.30	3000.00
HPP 0501-067		US 50 AND SH 92 DELTA INTERSE	03/26/20	1.00	3000.00	3815.00	3920.00
SHE 0703-461		I-70 and Kipling North Phase	03/26/20	4.00	2391.00	2197.80	2051.00
		WEIGHTED AVERAGE FOR THE FIRST QUARTER		21.00	2769.71	2718.13	2676.38
C1211-090		SH-121 & 29th Ave / SH-121 &	04/23/20	9.00	2290.50	1757.67	1250.00
FSA1602-159		US 160 AND SH 17 INTERSECTION	04/30/20	1.00	1500.00	4912.67	4260.00
NHPPR100-303		LONG MAST ARM SIGNALS PROJECT	05/07/20	8.00	2750.00	1686.00	1225.00
FSAR400-356		FY 20 SIGNAL POLE REPLACEMENT	06/11/20	4.00	2500.00	2148.33	1550.00
SHE016A-043		SH 21 & 16 SIGNALS PROJECT	06/18/20	12.00	3000.00	1786.95	955.75
		WEIGHTED AVERAGE FOR THE SECOND QUARTER		34.00	2650.43	1870.29	1264.09
		WEIGHTED AVERAGE FOR THE YEAR		55.00	2695.97	2255.67	1803.33
=====	614-85001	Impact Atten		Each	=====		
NHPP0343-041		I-76 & US 34 FT. MORGAN AREA	01/09/20	2.00	17500.00	18726.67	20268.00

COLORADO DEPARTMENT OF TRANSPORTATION
 ITEM UNIT COSTS BY PROJECTS -- 2020 COST DATA

10:58 Friday, October 2, 2020 278

PROJECT NUMBER	ITEM NUMBER/ PROJECT LOCATION	ITEM DESCRIPTION/ PROJECT LOCATION	DATE LET	UNIT/ QUANTITY	ENGR. EST.	AVERAGE BID	AWARDED BID
===== 614-85001		Impact Atten		Each =====			
NHPP 0852-116		US85:HAMPDEN TO FLORIDA-RESUR	02/06/20	2.00	25000.00	45000.00	50000.00
	WEIGHTED AVERAGE FOR THE FIRST QUARTER			4.00	21250.00	29236.00	35134.00
	WEIGHTED AVERAGE FOR THE YEAR			4.00	21250.00	29236.00	35134.00
===== 614-86006		Telemetry (Master)		Each =====			
ITSSW01-719		FY 20 ITS CAPITAL REPLACEMENT	06/11/20	4.00	3000.00	3250.00	3500.00
	WEIGHTED AVERAGE FOR THE SECOND QUARTER			4.00	3000.00	3250.00	3500.00
	WEIGHTED AVERAGE FOR THE YEAR			4.00	3000.00	3250.00	3500.00
===== 614-86007		Serial to IP Converter		Each =====			
FSA0253-262		I-25 SB BOTTLENECK I-76 TO I-	01/09/20	1.00	1650.00	1816.46	1635.00
	WEIGHTED AVERAGE FOR THE FIRST QUARTER			1.00	1650.00	1816.46	1635.00
	WEIGHTED AVERAGE FOR THE YEAR			1.00	1650.00	1816.46	1635.00
===== 614-86105		Telemetry (Field)		Each =====			
NHPP0253-265		I-25 AT ERIE PARKWAY ON AND O	01/09/20	2.00	2810.00	3365.00	3595.00
	WEIGHTED AVERAGE FOR THE FIRST QUARTER			2.00	2810.00	3365.00	3595.00
ITSSW01-719		FY 20 ITS CAPITAL REPLACEMENT	06/11/20	4.00	3000.00	3950.00	5500.00
	WEIGHTED AVERAGE FOR THE SECOND QUARTER			4.00	3000.00	3950.00	5500.00
	WEIGHTED AVERAGE FOR THE YEAR			6.00	2936.67	3699.29	4865.00
===== 614-86248		Traf Ctrlr (Type 2070LC)		Each =====			
SHE 0703-461		I-70 and Kipling North Phase	03/26/20	2.00	20000.00	5893.20	5467.00
	WEIGHTED AVERAGE FOR THE FIRST QUARTER			2.00	20000.00	5893.20	5467.00

PROJECT NUMBER	ITEM NUMBER/ PROJECT LOCATION	ITEM DESCRIPTION/ PROJECT LOCATION	DATE LET	UNIT/ QUANTITY	ENGR. EST.	AVERAGE BID	AWARDED BID
===== 614-86248		Traf Ctrler (Type 2070LC)		Each	=====		
CC0852-106		US-85 LOUVIERS TO MP 191.75	04/23/20	1.00	5000.00	6893.83	6710.00
FBR0852-108		US-85 BETWEEN LOUVIERS AND MP					
C1211-090		SH-121 & 29th Ave / SH-121 &	04/23/20	3.00	4833.33	6371.50	6165.00
	WEIGHTED	AVERAGE FOR THE SECOND QUARTER		4.00	4875.00	6617.30	6301.25
		WEIGHTED AVERAGE FOR THE YEAR		6.00	9916.67	6349.12	6023.17
===== 614-86250		Ctrler (Ramp Metering)		Each	=====		
FSA0253-262		I-25 SB BOTTLENECK I-76 TO I-	01/09/20	1.00	2000.00	2036.54	1865.00
	WEIGHTED	AVERAGE FOR THE FIRST QUARTER		1.00	2000.00	2036.54	1865.00
		WEIGHTED AVERAGE FOR THE YEAR		1.00	2000.00	2036.54	1865.00
===== 614-86748		Ctrler (Ty 2070)		Each	=====		
NHPP0253-265		I-25 AT ERIE PARKWAY ON AND O	01/09/20	2.00	5000.00	6616.67	5500.00
	WEIGHTED	AVERAGE FOR THE FIRST QUARTER		2.00	5000.00	6616.67	5500.00
		WEIGHTED AVERAGE FOR THE YEAR		2.00	5000.00	6616.67	5500.00
===== 614-86800		Uninterrupted Power Supply		Each	=====		
NHPP0253-265		I-25 AT ERIE PARKWAY ON AND O	01/09/20	2.00	7250.00	7310.00	6255.00
SHE 0703-461		I-70 and Kipling North Phase	03/26/20	2.00	12000.00	6565.20	6200.00
	WEIGHTED	AVERAGE FOR THE FIRST QUARTER		4.00	9625.00	6844.50	6227.50
CC0852-106		US-85 LOUVIERS TO MP 191.75	04/23/20	1.00	12000.00	7040.30	6847.50
FBR0852-108		US-85 BETWEEN LOUVIERS AND MP					
C1211-090		SH-121 & 29th Ave / SH-121 &	04/23/20	3.00	7933.33	5962.00	5890.00
	WEIGHTED	AVERAGE FOR THE SECOND QUARTER		4.00	8950.00	6469.43	6129.38
		WEIGHTED AVERAGE FOR THE YEAR		8.00	9287.50	6651.28	6178.44

COLORADO DEPARTMENT OF TRANSPORTATION
ITEM UNIT COSTS BY PROJECTS -- 2020 COST DATA

10:58 Friday, October 2, 2020 280

PROJECT NUMBER	ITEM NUMBER/ PROJECT LOCATION	ITEM DESCRIPTION/ PROJECT LOCATION	DATE LET	UNIT/ QUANTITY	ENGR. EST.	AVERAGE BID	AWARDED BID
===== 614-87006 Fiber Optic Term Panel (6 Fiber) Each =====							
SHE016A-043	SH 21 & 16 SIGNALS PROJECT		06/18/20	2.00	700.00	631.20	597.00
	WEIGHTED AVERAGE FOR THE SECOND QUARTER			2.00	700.00	631.20	597.00
	WEIGHTED AVERAGE FOR THE YEAR			2.00	700.00	631.20	597.00
===== 614-87010 Fiber Optic Cable (S Mode) (12 Fiber) Lin Foot =====							
FSA0253-262	I-25 SB BOTTLENECK I-76 TO I-		01/09/20	2,400.00	10.00	5.47	5.00
NHPP0253-265	I-25 AT ERIE PARKWAY ON AND O		01/09/20	130.00	12.00	3.17	2.00
ITS0761-231	ITS FIBER AND CAMERAS ON I-76		02/06/20	1,230.00	3.50	6.91	0.99
NHPP0091-044	SH 9 FRISCO MAIN ST TO IRON S		03/05/20	300.00	20.00	10.25	10.00
NH050A-034	US50A PUEBLO WEST PURCELL INT		03/26/20	690.00	7.50	2.44	2.41
SHE 0703-461	I-70 and Kipling North Phase		03/26/20	1,760.00	10.80	4.76	4.50
	WEIGHTED AVERAGE FOR THE FIRST QUARTER			6,510.00	9.22	5.10	4.00
IM0761-226	I76/SH52 Interchange		04/02/20	150.00	9.00	36.58	36.04
CC0852-106	US-85 LOUVIERS TO MP 191.75		04/23/20	500.00	9.50	5.62	5.50
FBR0852-108	US-85 BETWEEN LOUVIERS AND MP						
CI211-090	SH-121 & 29th Ave / SH-121 &		04/23/20	300.00	4.83	6.67	6.25
FSA1602-159	US 160 AND SH 17 INTERSECTION		04/30/20	100.00	5.00	3.42	3.00
NHPPR100-303	LONG MAST ARM SIGNALS PROJECT		05/07/20	35.00	20.00	16.67	19.00
ITS SW02-303	R1: US 285, SH 83 R2: SH 83,		05/28/20	750.00	15.00	2.84	2.50
SHE016A-043	SH 21 & 16 SIGNALS PROJECT		06/18/20	175.00	7.00	8.24	10.21
	WEIGHTED AVERAGE FOR THE SECOND QUARTER			2,010.00	10.56	7.97	7.29
	WEIGHTED AVERAGE FOR THE YEAR			8,520.00	9.54	5.89	4.78
===== 614-87012 Fiber Optic Term Panel (12 Fiber) Each =====							
FSA0253-262	I-25 SB BOTTLENECK I-76 TO I-		01/09/20	1.00	1000.00	1708.90	1565.00
NHPP0253-265	I-25 AT ERIE PARKWAY ON AND O		01/09/20	1.00	1200.00	530.00	635.00
ITS0761-231	ITS FIBER AND CAMERAS ON I-76		02/06/20	6.00	700.00	810.82	1200.00
NH050A-034	US50A PUEBLO WEST PURCELL INT		03/26/20	2.00	400.00	1596.05	1733.00
	WEIGHTED AVERAGE FOR THE FIRST QUARTER			10.00	720.00	1088.04	1286.60
CC0852-106	US-85 LOUVIERS TO MP 191.75		04/23/20	1.00	1000.00	1026.03	1001.00

COLORADO DEPARTMENT OF TRANSPORTATION
ITEM UNIT COSTS BY PROJECTS -- 2020 COST DATA

10:58 Friday, October 2, 2020 281

PROJECT NUMBER	ITEM NUMBER/ PROJECT LOCATION	ITEM DESCRIPTION/ PROJECT LOCATION	DATE LET	UNIT/ QUANTITY	ENGR. EST.	AVERAGE BID	AWARDED BID
===== 614-87012 Fiber Optic Term Panel (12 Fiber) Each =====							
FBR0852-108		US-85 BETWEEN LOUVIERS AND MP					
C1211-090		SH-121 & 29th Ave / SH-121 &	04/23/20	3.00	916.67	1070.00	860.00
NHPPR100-303		LONG MAST ARM SIGNALS PROJECT	05/07/20	1.00	1300.00	1107.00	1175.00
SHE016A-043		SH 21 & 16 SIGNALS PROJECT	06/18/20	1.00	1400.00	798.20	796.00
	WEIGHTED AVERAGE FOR THE SECOND QUARTER			6.00	1075.00	1006.01	925.33
	WEIGHTED AVERAGE FOR THE YEAR			16.00	853.13	1061.41	1151.13
===== 614-87015 Buffer Tube Fan Out Kit Each =====							
FSA0253-262		I-25 SB BOTTLENECK I-76 TO I-	01/09/20	1.00	300.00	332.82	305.00
NHPP0253-265		I-25 AT ERIE PARKWAY ON AND O	01/09/20	1.00	120.00	251.67	125.00
NH050A-034		US50A PUEBLO WEST PURCELL INT	03/26/20	2.00	600.00	319.44	316.00
	WEIGHTED AVERAGE FOR THE FIRST QUARTER			4.00	405.00	312.02	265.50
CC0852-106		US-85 LOUVIERS TO MP 191.75	04/23/20	1.00	300.00	169.39	165.00
FBR0852-108		US-85 BETWEEN LOUVIERS AND MP					
C1211-090		SH-121 & 29th Ave / SH-121 &	04/23/20	3.00	933.33	285.93	145.00
FSA1602-159		US 160 AND SH 17 INTERSECTION	04/30/20	1.00	150.00	643.67	407.00
NHPPR100-303		LONG MAST ARM SIGNALS PROJECT	05/07/20	1.00	650.00	406.33	250.00
ITS SW02-303		R1: US 285, SH 83 R2: SH 83,	05/28/20	3.00	300.00	305.30	350.00
	WEIGHTED AVERAGE FOR THE SECOND QUARTER			9.00	533.33	306.79	256.33
	WEIGHTED AVERAGE FOR THE YEAR			13.00	493.85	308.71	259.15
===== 614-87024 Fiber Optic Term Panel (24 Fiber) Each =====							
ITS0761-231		ITS FIBER AND CAMERAS ON I-76	02/06/20	2.00	1500.00	1145.67	2200.00
	WEIGHTED AVERAGE FOR THE FIRST QUARTER			2.00	1500.00	1145.67	2200.00
FSA1602-159		US 160 AND SH 17 INTERSECTION	04/30/20	1.00	1700.00	2907.67	1630.00
ITS SW02-304		ITS FIBER TO STATE BUILDINGS	05/14/20	37.00	1500.00	1402.75	898.00
ITS SW02-303		R1: US 285, SH 83 R2: SH 83,	05/28/20	2.00	1500.00	1452.00	1500.00
ITSSW01-719		FY 20 ITS CAPITAL REPLACEMENT	06/11/20	1.00	1000.00	2450.00	1900.00
	WEIGHTED AVERAGE FOR THE SECOND QUARTER			41.00	1492.68	1446.32	969.66
	WEIGHTED AVERAGE FOR THE YEAR			43.00	1493.02	1428.94	1026.88

PROJECT NUMBER	ITEM NUMBER/ PROJECT LOCATION	ITEM DESCRIPTION/ PROJECT LOCATION	DATE LET	UNIT/ QUANTITY	ENGR. EST.	AVERAGE BID	AWARDED BID
=====	614-87040	Cable Innerduct (1 In)		Lin Foot	=====		
ITS SW02-303		R1: US 285, SH 83 R2: SH 83,	05/28/20	23,455.00	4.00	2.40	1.50
	WEIGHTED	AVERAGE FOR THE SECOND QUARTER		23,455.00	4.00	2.40	1.50
		WEIGHTED AVERAGE FOR THE YEAR		23,455.00	4.00	2.40	1.50
=====	614-87144	Fiber Optic Termi Panel (144 Fiber)		Each	=====		
ITS0761-231		ITS FIBER AND CAMERAS ON I-76	02/06/20	1.00	8000.00	9127.88	5000.00
	WEIGHTED	AVERAGE FOR THE FIRST QUARTER		1.00	8000.00	9127.88	5000.00
		WEIGHTED AVERAGE FOR THE YEAR		1.00	8000.00	9127.88	5000.00
=====	614-87300	TMS Building		Each	=====		
ITS0761-231		ITS FIBER AND CAMERAS ON I-76	02/06/20	1.00	385000.00	312273.00	275000.00
	WEIGHTED	AVERAGE FOR THE FIRST QUARTER		1.00	385000.00	312273.00	275000.00
		WEIGHTED AVERAGE FOR THE YEAR		1.00	385000.00	312273.00	275000.00
=====	614-87310	TMS Building Equip		LUMP SUM	=====		
ITS0761-231		ITS FIBER AND CAMERAS ON I-76	02/06/20	1.00	40000.00	71765.00	23000.00
	WEIGHTED	AVERAGE FOR THE FIRST QUARTER		1.00	40000.00	71765.00	23000.00
		WEIGHTED AVERAGE FOR THE YEAR		1.00	40000.00	71765.00	23000.00
=====	614-87312	Traffic Management Sys Bldg Generator		LUMP SUM	=====		
ITS0761-231		ITS FIBER AND CAMERAS ON I-76	02/06/20	1.00	25000.00	53368.00	62000.00
	WEIGHTED	AVERAGE FOR THE FIRST QUARTER		1.00	25000.00	53368.00	62000.00
		WEIGHTED AVERAGE FOR THE YEAR		1.00	25000.00	53368.00	62000.00
=====	614-87314	Traffic Management Sys Bldg HVAC		Each	=====		
ITS0761-231		ITS FIBER AND CAMERAS ON I-76	02/06/20	1.00	25000.00	22565.20	6500.00
	WEIGHTED	AVERAGE FOR THE FIRST QUARTER		1.00	25000.00	22565.20	6500.00
		WEIGHTED AVERAGE FOR THE YEAR		1.00	25000.00	22565.20	6500.00

COLORADO DEPARTMENT OF TRANSPORTATION
 ITEM UNIT COSTS BY PROJECTS -- 2020 COST DATA

10:58 Friday, October 2, 2020 283

PROJECT NUMBER	ITEM NUMBER/ PROJECT LOCATION	ITEM DESCRIPTION/ PROJECT LOCATION	DATE LET	UNIT/ QUANTITY	ENGR. EST.	AVERAGE BID	AWARDED BID
===== 614-87320		CCTV		Each =====			
ITS0761-231		ITS FIBER AND CAMERAS ON I-76	02/06/20	4.00	4500.00	4840.80	4500.00
NHPP0091-044		SH 9 FRISCO MAIN ST TO IRON S	03/05/20	2.00	6000.00	4900.00	4700.00
SHE 0703-461		I-70 and Kipling North Phase	03/26/20	2.00	5000.00	8903.20	8400.00
		WEIGHTED AVERAGE FOR THE FIRST QUARTER		8.00	5000.00	5979.11	5525.00
CC0852-106		US-85 LOUVIERS TO MP 191.75	04/23/20	1.00	4800.00	6860.79	6682.50
FBR0852-108		US-85 BETWEEN LOUVIERS AND MP					
C1211-090		SH-121 & 29th Ave / SH-121 &	04/23/20	3.00	5666.67	6126.20	6370.00
FSA1602-159		US 160 AND SH 17 INTERSECTION	04/30/20	1.00	5300.00	13051.67	10570.00
ITSSW01-719		FY 20 ITS CAPITAL REPLACEMENT	06/11/20	1.00	5200.00	6250.00	6500.00
SHE016A-043		SH 21 & 16 SIGNALS PROJECT	06/18/20	1.00	5000.00	5129.40	5170.00
		WEIGHTED AVERAGE FOR THE SECOND QUARTER		7.00	5328.57	6937.93	6861.79
		WEIGHTED AVERAGE FOR THE YEAR		15.00	5153.33	6390.03	6148.83
===== 614-87321		CCTV (Inst)		Each =====			
NH050A-034		US50A PUEBLO WEST PURCELL INT	03/26/20	2.00	600.00	4609.24	5000.00
		WEIGHTED AVERAGE FOR THE FIRST QUARTER		2.00	600.00	4609.24	5000.00
SHE016A-043		SH 21 & 16 SIGNALS PROJECT	06/18/20	2.00	2000.00	1150.80	928.00
		WEIGHTED AVERAGE FOR THE SECOND QUARTER		2.00	2000.00	1150.80	928.00
		WEIGHTED AVERAGE FOR THE YEAR		4.00	1300.00	3279.07	2964.00
===== 614-87333		CCTV Camera (Traf Surveil)		Each =====			
C1601-082		Hawkins Signal and Curb Ramps	04/30/20	1.00	8000.00	10700.00	6600.00
		WEIGHTED AVERAGE FOR THE SECOND QUARTER		1.00	8000.00	10700.00	6600.00
		WEIGHTED AVERAGE FOR THE YEAR		1.00	8000.00	10700.00	6600.00

COLORADO DEPARTMENT OF TRANSPORTATION
 ITEM UNIT COSTS BY PROJECTS -- 2020 COST DATA

10:58 Friday, October 2, 2020 284

PROJECT NUMBER	ITEM NUMBER/ PROJECT LOCATION	ITEM DESCRIPTION/ PROJECT LOCATION	DATE LET	UNIT/ QUANTITY	ENGR. EST.	AVERAGE BID	AWARDED BID
===== 614-87350		Test Fiber Optic Cable		LUMP SUM	=====		
FSA0253-262		I-25 SB BOTTLENECK I-76 TO I-	01/09/20	1.00	7500.00	7678.33	2535.00
NHPP0253-265		I-25 AT ERIE PARKWAY ON AND O	01/09/20	1.00	5000.00	921.67	1675.00
ITS0761-231		ITS FIBER AND CAMERAS ON I-76	02/06/20	1.00	20000.00	20177.80	9000.00
NHPP0091-044		SH 9 FRISCO MAIN ST TO IRON S	03/05/20	1.00	10000.00	11960.00	11500.00
NH050A-034		US50A PUEBLO WEST PURCELL INT	03/26/20	1.00	1900.00	9327.88	10800.00
	WEIGHTED AVERAGE FOR THE FIRST QUARTER			5.00	8880.00	10781.46	7102.00
IM0761-226		I76/SH52 Interchange	04/02/20	1.00	5000.00	5888.62	6809.44
CC0852-106		US-85 LOUVIERS TO MP 191.75	04/23/20	1.00	10000.00	6093.62	5940.00
FBR0852-108		US-85 BETWEEN LOUVIERS AND MP					
C1211-090		SH-121 & 29th Ave / SH-121 &	04/23/20	1.00	18000.00	3088.90	3100.00
NHPPR100-303		LONG MAST ARM SIGNALS PROJECT	05/07/20	1.00	550.00	1482.33	1240.00
ITS SW02-304		ITS FIBER TO STATE BUILDINGS	05/14/20	1.00	20000.00	57545.00	77235.00
NHPP0253-276		I-25 EXPRESS LANES SEGMENT 5	05/15/20	1.00	7500.00	7490.00	7490.00
ITS SW02-303		R1: US 285, SH 83 R2: SH 83,	05/28/20	1.00	10000.00	16123.00	7500.00
SHE016A-043		SH 21 & 16 SIGNALS PROJECT	06/18/20	1.00	4500.00	3449.60	4738.00
	WEIGHTED AVERAGE FOR THE SECOND QUARTER			8.00	9443.75	12200.44	14256.56
	WEIGHTED AVERAGE FOR THE YEAR			13.00	9226.92	11662.21	11504.80
===== 614-87364		CCTV Pole w Low Dev (50 Ft)		Each	=====		
ITS0761-231		ITS FIBER AND CAMERAS ON I-76	02/06/20	4.00	20000.00	23269.60	24000.00
	WEIGHTED AVERAGE FOR THE FIRST QUARTER			4.00	20000.00	23269.60	24000.00
	WEIGHTED AVERAGE FOR THE YEAR			4.00	20000.00	23269.60	24000.00
===== 614-87448		Fiber Optic Cable (S Mode) (48 S)		Lin Foot	=====		
ITS0761-231		ITS FIBER AND CAMERAS ON I-76	02/06/20	4,800.00	6.00	2.49	1.01
	WEIGHTED AVERAGE FOR THE FIRST QUARTER			4,800.00	6.00	2.49	1.01
ITS SW02-304		ITS FIBER TO STATE BUILDINGS	05/14/20	68,400.00	6.00	2.60	3.00
	WEIGHTED AVERAGE FOR THE SECOND QUARTER			68,400.00	6.00	2.60	3.00
	WEIGHTED AVERAGE FOR THE YEAR			73,200.00	6.00	2.59	2.87

COLORADO DEPARTMENT OF TRANSPORTATION
 ITEM UNIT COSTS BY PROJECTS -- 2020 COST DATA

10:58 Friday, October 2, 2020 285

PROJECT NUMBER	ITEM NUMBER/ PROJECT LOCATION	ITEM DESCRIPTION/ PROJECT LOCATION	DATE LET	UNIT/ QUANTITY	ENGR. EST.	AVERAGE BID	AWARDED BID
===== 614-87496		Fiber Optic Cable (S Mode) (96 S)		Lin Foot	=====		
ITS0761-231		ITS FIBER AND CAMERAS ON I-76	02/06/20	168,260.00	2.25	2.43	1.42
NHPP0091-044		SH 9 FRISCO MAIN ST TO IRON S	03/05/20	6,800.00	6.00	5.77	5.50
NH050A-034		US50A PUEBLO WEST PURCELL INT	03/26/20	12,280.00	9.50	2.48	2.37
		WEIGHTED AVERAGE FOR THE FIRST QUARTER		187,340.00	2.86	2.51	1.63
IM0761-226		I76/SH52 Interchange	04/02/20	5,300.00	4.00	3.85	4.06
ITS SW02-303		R1: US 285, SH 83 R2: SH 83,	05/28/20	99,745.00	4.00	3.08	1.75
		WEIGHTED AVERAGE FOR THE SECOND QUARTER		105,045.00	4.00	3.13	1.87
		WEIGHTED AVERAGE FOR THE YEAR		292,385.00	3.27	2.73	1.72
===== 614-87498		Fiber Optic Cable (S Mode) (144 S)		Lin Foot	=====		
CC0852-106		US-85 LOUVIERS TO MP 191.75	04/23/20	18,000.00	6.00	5.10	4.95
FBR0852-108		US-85 BETWEEN LOUVIERS AND MP					
		WEIGHTED AVERAGE FOR THE SECOND QUARTER		18,000.00	6.00	5.10	4.95
		WEIGHTED AVERAGE FOR THE YEAR		18,000.00	6.00	5.10	4.95
===== 614-87499		Fiber Optic Cable (S Mode) (Inst)		Lin Foot	=====		
NHPP0253-276		I-25 EXPRESS LANES SEGMENT 5	05/15/20	24,760.00	3.20	3.21	3.21
		WEIGHTED AVERAGE FOR THE SECOND QUARTER		24,760.00	3.20	3.21	3.21
		WEIGHTED AVERAGE FOR THE YEAR		24,760.00	3.20	3.21	3.21
===== 614-87512		Splice FO Cable (12 S)		Each	=====		
FSA0253-262		I-25 SB BOTTLENECK I-76 TO I-	01/09/20	1.00	1700.00	1250.21	1145.00
		WEIGHTED AVERAGE FOR THE FIRST QUARTER		1.00	1700.00	1250.21	1145.00
CC0852-106		US-85 LOUVIERS TO MP 191.75	04/23/20	1.00	1600.00	2092.71	2035.00

COLORADO DEPARTMENT OF TRANSPORTATION
 ITEM UNIT COSTS BY PROJECTS -- 2020 COST DATA

10:58 Friday, October 2, 2020 286

PROJECT NUMBER	ITEM NUMBER/ PROJECT LOCATION	ITEM DESCRIPTION/ PROJECT LOCATION	DATE LET	UNIT/ QUANTITY	ENGR. EST.	AVERAGE BID	AWARDED BID
=====	614-87512	Splice FO Cable (12 S)		Each	=====	=====	=====
FBR0852-108		US-85 BETWEEN LOUVIERS AND MP					
C1211-090		SH-121 & 29th Ave / SH-121 &	04/23/20	3.00	2660.00	1688.17	1735.00
NHPPR100-303		LONG MAST ARM SIGNALS PROJECT	05/07/20	1.00	2200.00	1656.33	2100.00
SHE016A-043		SH 21 & 16 SIGNALS PROJECT	06/18/20	1.00	3000.00	1981.20	1617.00
	WEIGHTED AVERAGE FOR THE SECOND QUARTER			6.00	2463.33	1872.41	1826.17
	WEIGHTED AVERAGE FOR THE YEAR			7.00	2354.29	1805.74	1728.86
=====	614-87524	Splice FO Cable (24 Strand)		Each	=====	=====	=====
FSA1602-159		US 160 AND SH 17 INTERSECTION	04/30/20	1.00	2500.00	19632.00	14830.00
	WEIGHTED AVERAGE FOR THE SECOND QUARTER			1.00	2500.00	19632.00	14830.00
	WEIGHTED AVERAGE FOR THE YEAR			1.00	2500.00	19632.00	14830.00
=====	614-87596	Splice Fiber Optic Cable (96 Strand)		Each	=====	=====	=====
NH050A-034		US50A PUEBLO WEST PURCELL INT	03/26/20	3.00	1000.00	4812.47	5350.00
	WEIGHTED AVERAGE FOR THE FIRST QUARTER			3.00	1000.00	4812.47	5350.00
	WEIGHTED AVERAGE FOR THE YEAR			3.00	1000.00	4812.47	5350.00
=====	614-87612	Term FO Cable (12 S)		Each	=====	=====	=====
SHE016A-043		SH 21 & 16 SIGNALS PROJECT	06/18/20	1.00	3000.00	994.40	416.00
	WEIGHTED AVERAGE FOR THE SECOND QUARTER			1.00	3000.00	994.40	416.00
	WEIGHTED AVERAGE FOR THE YEAR			1.00	3000.00	994.40	416.00
=====	614-87690	Ethernet Switch		Each	=====	=====	=====
NHPP0253-265		I-25 AT ERIE PARKWAY ON AND O	01/09/20	2.00	5000.00	4151.67	3655.00
SHE 0703-461		I-70 and Kipling North Phase	03/26/20	2.00	4510.00	7984.00	7520.00
	WEIGHTED AVERAGE FOR THE FIRST QUARTER			4.00	4755.00	6546.88	5587.50
IM0761-226		I76/SH52 Interchange	04/02/20	1.00	3500.00	3084.50	1100.28
	WEIGHTED AVERAGE FOR THE SECOND QUARTER			1.00	3500.00	3084.50	1100.28
	WEIGHTED AVERAGE FOR THE YEAR			5.00	4504.00	5493.11	4690.06

COLORADO DEPARTMENT OF TRANSPORTATION
ITEM UNIT COSTS BY PROJECTS -- 2020 COST DATA

10:58 Friday, October 2, 2020 287

PROJECT NUMBER	ITEM NUMBER/ PROJECT LOCATION	ITEM DESCRIPTION/ PROJECT LOCATION	DATE LET	UNIT/ QUANTITY	ENGR. EST.	AVERAGE BID	AWARDED BID
===== 614-87691 Ethernet Switch Type I Each =====							
ITS0761-231		ITS FIBER AND CAMERAS ON I-76	02/06/20	2.00	5000.00	7663.87	8700.00
		WEIGHTED AVERAGE FOR THE FIRST QUARTER		2.00	5000.00	7663.87	8700.00
ITSSW01-719							
		FY 20 ITS CAPITAL REPLACEMENT	06/11/20	1.00	6500.00	5250.00	4500.00
		WEIGHTED AVERAGE FOR THE SECOND QUARTER		1.00	6500.00	5250.00	4500.00
		WEIGHTED AVERAGE FOR THE YEAR		3.00	5500.00	7261.56	7300.00
===== 614-87692 Ethernet Switch Type II Each =====							
ITS0761-231		ITS FIBER AND CAMERAS ON I-76	02/06/20	4.00	4500.00	5194.54	9100.00
NH050A-034		US50A PUEBLO WEST PURCELL INT	03/26/20	2.00	3500.00	10509.45	11350.00
		WEIGHTED AVERAGE FOR THE FIRST QUARTER		6.00	4166.67	7556.72	9850.00
CC0852-106							
FBR0852-108		US-85 LOUVIERS TO MP 191.75	04/23/20	1.00	4000.00	9337.90	9130.00
C1211-090		US-85 BETWEEN LOUVIERS AND MP					
		SH-121 & 29th Ave / SH-121 &	04/23/20	3.00	3700.00	7140.75	7750.00
		WEIGHTED AVERAGE FOR THE SECOND QUARTER		4.00	3775.00	8174.70	8095.00
		WEIGHTED AVERAGE FOR THE YEAR		10.00	4010.00	7754.94	9148.00
===== 614-87693 Ethernet Switch Type III Each =====							
ITS0761-231		ITS FIBER AND CAMERAS ON I-76	02/06/20	2.00	7000.00	4447.22	9500.00
		WEIGHTED AVERAGE FOR THE FIRST QUARTER		2.00	7000.00	4447.22	9500.00
ITS SW02-304							
SHE016A-043		ITS FIBER TO STATE BUILDINGS	05/14/20	42.00	7000.00	3281.25	1622.00
		SH 21 & 16 SIGNALS PROJECT	06/18/20	1.00	7000.00	8042.40	9730.00
		WEIGHTED AVERAGE FOR THE SECOND QUARTER		43.00	7000.00	3418.86	1810.56
		WEIGHTED AVERAGE FOR THE YEAR		45.00	7000.00	3475.05	2152.31

COLORADO DEPARTMENT OF TRANSPORTATION
ITEM UNIT COSTS BY PROJECTS -- 2020 COST DATA

10:58 Friday, October 2, 2020 288

PROJECT NUMBER	ITEM NUMBER/ PROJECT LOCATION	ITEM DESCRIPTION/ PROJECT LOCATION	DATE LET	UNIT/ QUANTITY	ENGR. EST.	AVERAGE BID	AWARDED BID
===== 614-87697		Ethernet Agg Switch Type I		Each	=====	=====	=====
FSA0253-262		I-25 SB BOTTLENECK I-76 TO I-	01/09/20	1.00	10000.00	9696.25	8875.00
ITS0761-231		ITS FIBER AND CAMERAS ON I-76	02/06/20	1.00	10000.00	12276.73	8700.00
	WEIGHTED AVERAGE FOR THE FIRST	QUARTER		2.00	10000.00	11309.05	8787.50
	WEIGHTED AVERAGE FOR THE YEAR			2.00	10000.00	11309.05	8787.50
===== 614-87698		Ethernet Agg Switch Type II		Each	=====	=====	=====
ITS0761-231		ITS FIBER AND CAMERAS ON I-76	02/06/20	1.00	25000.00	21164.58	9200.00
	WEIGHTED AVERAGE FOR THE FIRST	QUARTER		1.00	25000.00	21164.58	9200.00
	WEIGHTED AVERAGE FOR THE YEAR			1.00	25000.00	21164.58	9200.00
===== 614-87699		Ethernet Agg Switch Type III		Each	=====	=====	=====
ITS0761-231		ITS FIBER AND CAMERAS ON I-76	02/06/20	1.00	35000.00	28350.78	9700.00
	WEIGHTED AVERAGE FOR THE FIRST	QUARTER		1.00	35000.00	28350.78	9700.00
	WEIGHTED AVERAGE FOR THE YEAR			1.00	35000.00	28350.78	9700.00
===== 614-87700		Ethernet Router		Each	=====	=====	=====
ITS SW02-304		ITS FIBER TO STATE BUILDINGS	05/14/20	14.00	100.00	593.50	62.00
	WEIGHTED AVERAGE FOR THE SECOND	QUARTER		14.00	100.00	593.50	62.00
	WEIGHTED AVERAGE FOR THE YEAR			14.00	100.00	593.50	62.00
===== 614-87704		Ethernet Radio (Single Client)		Each	=====	=====	=====
NHPP0253-265		I-25 AT ERIE PARKWAY ON AND O	01/09/20	2.00	3500.00	3361.67	1585.00
	WEIGHTED AVERAGE FOR THE FIRST	QUARTER		2.00	3500.00	3361.67	1585.00
IM0761-226		I76/SH52 Interchange	04/02/20	1.00	3000.00	3098.89	2634.10
	WEIGHTED AVERAGE FOR THE SECOND	QUARTER		1.00	3000.00	3098.89	2634.10
	WEIGHTED AVERAGE FOR THE YEAR			3.00	3333.33	3220.17	1934.70

COLORADO DEPARTMENT OF TRANSPORTATION
ITEM UNIT COSTS BY PROJECTS -- 2020 COST DATA

10:58 Friday, October 2, 2020 289

PROJECT NUMBER	ITEM NUMBER/ PROJECT LOCATION	ITEM DESCRIPTION/ PROJECT LOCATION	DATE LET	UNIT/ QUANTITY	ENGR. EST.	AVERAGE BID	AWARDED BID
=====	615-00030	Emb Prot Ty 3		Each	=====		
NHPP0343-041		I-76 & US 34 FT. MORGAN AREA	01/09/20	51.00	1650.00	2021.21	2523.00
BR0343-040		US 34 REPUBLICAN RIVER BRIDGE	01/16/20	6.00	1300.00	1484.94	1400.00
FBR0343-043		US 34 D-28-P STRUCTURE REPLAC					
		WEIGHTED AVERAGE FOR THE FIRST QUARTER		57.00	1613.16	1919.06	2404.79
FBR0343-042		US 34 D-27-G STRUCTURE REPLAC	05/07/20	2.00	2000.00	1287.56	1200.00
		WEIGHTED AVERAGE FOR THE SECOND QUARTER		2.00	2000.00	1287.56	1200.00
		WEIGHTED AVERAGE FOR THE YEAR		59.00	1626.27	1864.15	2363.95
=====	615-00050	Emb Prot Ty 5		Each	=====		
NHPP0343-041		I-76 & US 34 FT. MORGAN AREA	01/09/20	12.00	2200.00	3051.48	6146.00
NHPP4701-134		C-470 NOISE WALL WEST OF LUCE	02/06/20	1.00	1000.00	1977.00	285.00
STA059A-036		SH 59 SEIBERT TO COPE	02/06/20	6.00	3000.00	1460.00	1500.00
NHPP0091-044		SH 9 FRISCO MAIN ST TO IRON S	03/05/20	2.00	3000.00	2716.67	2500.00
NH050A-034		US50A PUEBLO WEST PURCELL INT	03/26/20	7.00	1800.00	3183.09	3300.00
		WEIGHTED AVERAGE FOR THE FIRST QUARTER		28.00	2285.71	2885.31	3969.18
IM0761-226		I76/SH52 Interchange	04/02/20	2.00	1500.00	2938.19	1017.00
CC0852-106		US-85 LOUVIERS TO MP 191.75	04/23/20	3.00	4200.00	2322.04	1100.00
FBR0852-108		US-85 BETWEEN LOUVIERS AND MP					
		WEIGHTED AVERAGE FOR THE SECOND QUARTER		5.00	3120.00	2549.05	1066.80
		WEIGHTED AVERAGE FOR THE YEAR		33.00	2412.12	2801.80	3529.42
=====	618-00142	Prestress Conc I (BT42)		Lin Foot	=====		
IM0761-226		I76/SH52 Interchange	04/02/20	180.20	250.00	679.18	545.00
		WEIGHTED AVERAGE FOR THE SECOND QUARTER		180.20	250.00	679.18	545.00
		WEIGHTED AVERAGE FOR THE YEAR		180.20	250.00	679.18	545.00

COLORADO DEPARTMENT OF TRANSPORTATION
ITEM UNIT COSTS BY PROJECTS -- 2020 COST DATA

10:58 Friday, October 2, 2020 290

PROJECT NUMBER	ITEM NUMBER/ PROJECT LOCATION	ITEM DESCRIPTION/ PROJECT LOCATION	DATE LET	UNIT/ QUANTITY	ENGR. EST.	AVERAGE BID	AWARDED BID
=====	618-00154	Prestress Conc I (BT54)		Lin Foot	=====		
NH050A-034		US50A PUEBLO WEST PURCELL INT	03/26/20	3,592.00	300.00	363.76	359.25
	WEIGHTED AVERAGE FOR THE FIRST QUARTER			3,592.00	300.00	363.76	359.25
	WEIGHTED AVERAGE FOR THE YEAR			3,592.00	300.00	363.76	359.25
=====	618-01992	Prestress Conc Box (Depth Less Than 32")		Sq Foot	=====		
CC0852-106		US-85 LOUVIERS TO MP 191.75	04/23/20	3,990.00	75.00	84.88	75.90
FBR0852-108		US-85 BETWEEN LOUVIERS AND MP					
FBR0343-042		US 34 D-27-G STRUCTURE REPLAC	05/07/20	4,028.00	80.00	81.80	64.00
	WEIGHTED AVERAGE FOR THE SECOND QUARTER			8,018.00	77.51	83.24	69.92
	WEIGHTED AVERAGE FOR THE YEAR			8,018.00	77.51	83.24	69.92
=====	618-06036	Prestress Conc Slab (Depth Gr Than 13")		Sq Foot	=====		
BR0343-040		US 34 REPUBLICAN RIVER BRIDGE	01/16/20	9,480.00	70.00	74.50	71.00
FBR0343-043		US 34 D-28-P STRUCTURE REPLAC					
	WEIGHTED AVERAGE FOR THE FIRST QUARTER			9,480.00	70.00	74.50	71.00
	WEIGHTED AVERAGE FOR THE YEAR			9,480.00	70.00	74.50	71.00
=====	619-00007	Connect To Existing Waterline		Each	=====		
IM0761-226		I76/SH52 Interchange	04/02/20	9.00	4000.00	2308.13	1816.00
	WEIGHTED AVERAGE FOR THE SECOND QUARTER			9.00	4000.00	2308.13	1816.00
	WEIGHTED AVERAGE FOR THE YEAR			9.00	4000.00	2308.13	1816.00
=====	619-06060	6 In Duct Iron Pipe		Lin Foot	=====		
IM0761-226		I76/SH52 Interchange	04/02/20	12.00	200.00	203.34	175.99
	WEIGHTED AVERAGE FOR THE SECOND QUARTER			12.00	200.00	203.34	175.99
	WEIGHTED AVERAGE FOR THE YEAR			12.00	200.00	203.34	175.99

COLORADO DEPARTMENT OF TRANSPORTATION
 ITEM UNIT COSTS BY PROJECTS -- 2020 COST DATA

10:58 Friday, October 2, 2020 291

PROJECT NUMBER	ITEM NUMBER/ PROJECT LOCATION	ITEM DESCRIPTION/ PROJECT LOCATION	DATE LET	UNIT/ QUANTITY	ENGR. EST.	AVERAGE BID	AWARDED BID
===== 619-10300		30 In Weld Steel Pipe		Lin Foot	=====		
NHPP0253-276		I-25 EXPRESS LANES SEGMENT 5	05/15/20	60.00	500.00	541.79	541.79
	WEIGHTED AVERAGE FOR THE SECOND QUARTER			60.00	500.00	541.79	541.79
	WEIGHTED AVERAGE FOR THE YEAR			60.00	500.00	541.79	541.79
===== 619-30320		4 In Galv Pipe		Lin Foot	=====		
STA059A-036		SH 59 SEIBERT TO COPE	02/06/20	21.00	200.00	372.50	355.00
	WEIGHTED AVERAGE FOR THE FIRST QUARTER			21.00	200.00	372.50	355.00
	WEIGHTED AVERAGE FOR THE YEAR			21.00	200.00	372.50	355.00
===== 619-30480		6 In Galv Pipe		Lin Foot	=====		
STA059A-036		SH 59 SEIBERT TO COPE	02/06/20	27.00	250.00	425.50	391.00
	WEIGHTED AVERAGE FOR THE FIRST QUARTER			27.00	250.00	425.50	391.00
	WEIGHTED AVERAGE FOR THE YEAR			27.00	250.00	425.50	391.00
===== 619-50480		6 In Plastic Pipe		Lin Foot	=====		
IM0761-226		I76/SH52 Interchange	04/02/20	55.00	250.00	153.56	86.49
	WEIGHTED AVERAGE FOR THE SECOND QUARTER			55.00	250.00	153.56	86.49
	WEIGHTED AVERAGE FOR THE YEAR			55.00	250.00	153.56	86.49
===== 619-50640		8 In Plastic Pipe		Lin Foot	=====		
NH050A-034		US50A PUEBLO WEST PURCELL INT	03/26/20	540.00	80.00	132.25	124.00
	WEIGHTED AVERAGE FOR THE FIRST QUARTER			540.00	80.00	132.25	124.00
IM0761-226		I76/SH52 Interchange	04/02/20	77.00	275.00	150.21	121.99
	WEIGHTED AVERAGE FOR THE SECOND QUARTER			77.00	275.00	150.21	121.99
	WEIGHTED AVERAGE FOR THE YEAR			617.00	104.34	134.24	123.75

COLORADO DEPARTMENT OF TRANSPORTATION
 ITEM UNIT COSTS BY PROJECTS -- 2020 COST DATA

10:58 Friday, October 2, 2020 292

PROJECT NUMBER	ITEM NUMBER/ PROJECT LOCATION	ITEM DESCRIPTION/ PROJECT LOCATION	DATE LET	UNIT/ QUANTITY	ENGR. EST.	AVERAGE BID	AWARDED BID
=====	619-50800	10 In Plastic Pipe		Lin Foot	=====		
NH050A-034		US50A PUEBLO WEST PURCELL INT	03/26/20	52.00	85.00	161.18	125.00
		WEIGHTED AVERAGE FOR THE FIRST QUARTER		52.00	85.00	161.18	125.00
		WEIGHTED AVERAGE FOR THE YEAR		52.00	85.00	161.18	125.00
=====	619-50960	12 In Plastic Pipe		Lin Foot	=====		
NH050A-034		US50A PUEBLO WEST PURCELL INT	03/26/20	488.00	100.00	188.13	155.00
		WEIGHTED AVERAGE FOR THE FIRST QUARTER		488.00	100.00	188.13	155.00
		WEIGHTED AVERAGE FOR THE YEAR		488.00	100.00	188.13	155.00
=====	619-75048	6 In Gate Valve		Each	=====		
IM0761-226		I76/SH52 Interchange	04/02/20	2.00	3000.00	2128.20	2750.01
		WEIGHTED AVERAGE FOR THE SECOND QUARTER		2.00	3000.00	2128.20	2750.01
		WEIGHTED AVERAGE FOR THE YEAR		2.00	3000.00	2128.20	2750.01
=====	619-78048	6 In Fire Hydrant		Each	=====		
IM0761-226		I76/SH52 Interchange	04/02/20	1.00	7000.00	5987.45	4923.77
		WEIGHTED AVERAGE FOR THE SECOND QUARTER		1.00	7000.00	5987.45	4923.77
		WEIGHTED AVERAGE FOR THE YEAR		1.00	7000.00	5987.45	4923.77
=====	620-00001	Field Office (CL 1)		Each	=====		
FSA0341-097		US 34 & MACGREGOR INTERSECTIO	01/09/20	1.00	15000.00	24000.00	24000.00
FSA2873-194		US 287 Longmont Intersection	02/13/20	1.00	18000.00	23500.00	20500.00
		WEIGHTED AVERAGE FOR THE FIRST QUARTER		2.00	16500.00	23571.43	22250.00
IM0252-473		I-25 CABLE BARRIER PHASE IV	04/09/20	1.00	20000.00	23500.00	25000.00

COLORADO DEPARTMENT OF TRANSPORTATION
 ITEM UNIT COSTS BY PROJECTS -- 2020 COST DATA

10:58 Friday, October 2, 2020 293

PROJECT NUMBER	ITEM NUMBER/ PROJECT LOCATION	ITEM DESCRIPTION/ PROJECT LOCATION	DATE LET	UNIT/ QUANTITY	ENGR. EST.	AVERAGE BID	AWARDED BID
=====	620-00001	Field Office (CL 1)		Each =====			
C1211-090		SH-121 & 29th Ave / SH-121 &	04/23/20	1.00	15000.00	37268.33	20805.00
IM025A-048		Northbound I-25 bridge at Exi	05/28/20	1.00	23400.00	16548.67	20000.00
		WEIGHTED AVERAGE FOR THE SECOND QUARTER		3.00	19466.67	26056.38	21935.00
		WEIGHTED AVERAGE FOR THE YEAR		5.00	18280.00	24896.73	22061.00
=====	620-00002	Field Office (CL 2)		Each =====			
STA0142-066		SH 14 New Raymer West	01/09/20	1.00	18000.00	19014.31	18053.24
BR0343-040		US 34 REPUBLICAN RIVER BRIDGE	01/16/20	1.00	22000.00	36166.67	40000.00
FBR0343-043		US 34 D-28-P STRUCTURE REPLAC					
STA006A-067		SH 6 Merino to Atwood	01/16/20	1.00	18000.00	31592.66	40000.00
STR131A-038		SH 131 MP 51.95-55.73, ROUTT	01/16/20	1.00	20000.00	17500.00	15000.00
NH 0503-093		US50 WEST OF TEXAS CREEK MP 2	01/23/20	1.00	20000.00	24606.07	21212.13
STR141A-044		SH 141 AND SH 145, FROM SLICK	01/30/20	1.00	30000.00	48641.58	68000.00
NHPP 0852-116		US85:HAMPDEN TO FLORIDA-RESUR	02/06/20	1.00	55000.00	35000.00	20000.00
STA0703-443		I-70 EJMT TUNNELS PAVING	02/06/20	1.00	25000.00	21985.40	16670.79
STA059A-036		SH 59 SEIBERT TO COPE	02/06/20	1.00	23000.00	27000.00	20000.00
STR116A-001		SH 116 A Surface Treatment Pr	02/13/20	1.00	25000.00	24327.82	22000.00
STA069A-033		SH69 MP 58.7 TO 71.58	02/13/20	1.00	26000.00	17253.19	16000.00
STR0101-027		SH 10 Overlay La Junta West	02/27/20	1.00	25000.00	20432.94	26000.00
NHPP0702-359		I-70 No Name Tunnel Lighting	02/27/20	1.00	30000.00	30560.00	15000.00
C0402-094		US 40 GRAND COUNTY SIGNAL REP	02/27/20	1.00	30000.00	15575.00	13000.00
NH0242-085		US 24 M.P. 291.38 to M.P. 296	02/27/20	1.00	28000.00	19780.00	28500.00
NHPP0171-105		SH 17 MP 84.5 to US 285 & SH	03/05/20	1.00	27000.00	46250.63	32751.88
C0641-106		SH 64 Meeker West Rural Resur	03/05/20	1.00	20000.00	23840.00	30000.00
NHPP145A-080		SH 145 Keystone-Placerville R	03/05/20	1.00	40000.00	44000.00	44000.00
STR2871-038		US 287 Passing Lanes Springfi	03/05/20	1.00	35000.00	20625.89	24675.30
BR025A-046		K-18-U ON I-25 AT MP112 BRIDG	03/05/20	1.00	30000.00	33644.78	13843.36
CC080-037		VARIOUS ADA RAMP ALONG NORTH	03/05/20	1.00	25000.00	8506.25	10000.00
NHPP0091-044		SH 9 FRISCO MAIN ST TO IRON S	03/05/20	1.00	40000.00	77580.00	100000.00
NH050A-034		US50A PUEBLO WEST PURCELL INT	03/26/20	1.00	22000.00	92592.19	95000.00
HPP 0501-067		US 50 AND SH 92 DELTA INTERSE	03/26/20	1.00	28000.00	23000.00	22600.00
		WEIGHTED AVERAGE FOR THE FIRST QUARTER		24.00	27583.33	36761.21	31346.11
NHPP1602-169		US 160 WC TUNNEL EAST RESURFA	04/02/20	1.00	30000.00	25555.93	32485.84
STR092A-030		SH92 MP 31.748-48.5, DELTA AND	04/02/20	1.00	24000.00	23790.00	30000.00
IM0761-226		I76/SH52 Interchange	04/02/20	1.00	22500.00	59158.30	53000.00
STA340A-021		SH340 MP 6-6.76 MESA COUNTY	04/02/20	1.00	35000.00	28400.00	25000.00
STR0341-101		SH 34 North of Grandby Resurf	04/02/20	1.00	25000.00	25749.84	20200.00
SFTY2254-091		225 Ramp Improvements	04/09/20	1.00	25000.00	36250.00	49500.00

COLORADO DEPARTMENT OF TRANSPORTATION
 ITEM UNIT COSTS BY PROJECTS -- 2020 COST DATA

10:58 Friday, October 2, 2020 294

PROJECT NUMBER	ITEM NUMBER/ PROJECT LOCATION	ITEM DESCRIPTION/ PROJECT LOCATION	DATE LET	UNIT/ QUANTITY	ENGR. EST.	AVERAGE BID	AWARDED BID
===== 620-00002 Field Office (CL 2) Each =====							
C1601-082		Hawkins Signal and Curb Ramps	04/30/20	1.00	16000.00	31666.67	18000.00
FSA1602-159		US 160 AND SH 17 INTERSECTION	04/30/20	1.00	12000.00	38470.00	28910.00
C0853-112		US85 & WCR98 INTERSECTION IMP	05/07/20	1.00	20000.00	24206.25	16500.00
FBR0343-042		US 34 D-27-G STRUCTURE REPLAC	05/07/20	1.00	25000.00	22674.63	11000.00
	WEIGHTED AVERAGE FOR THE SECOND QUARTER			10.00	23450.00	31981.52	28459.58
	WEIGHTED AVERAGE FOR THE YEAR			34.00	26367.65	35008.65	30497.13
===== 620-00005 Field Office (Spec) Each =====							
NHPP0343-041		I-76 & US 34 FT. MORGAN AREA	01/09/20	1.00	30000.00	141622.03	192900.00
PWQM240-172		El Paso County, north Colorad	01/23/20	1.00	15000.00	29654.00	47308.00
NHPP4701-134		C-470 NOISE WALL WEST OF LUCE	02/06/20	1.00	20000.00	32800.00	16000.00
SHE 0703-461		I-70 and Kipling North Phase	03/26/20	1.00	27000.00	44264.00	32350.00
	WEIGHTED AVERAGE FOR THE FIRST QUARTER			4.00	23000.00	57966.27	72139.50
CC0852-106		US-85 LOUVIERS TO MP 191.75	04/23/20	1.00	50000.00	97943.93	71500.00
FBR0852-108		US-85 BETWEEN LOUVIERS AND MP					
	WEIGHTED AVERAGE FOR THE SECOND QUARTER			1.00	50000.00	97943.93	71500.00
	WEIGHTED AVERAGE FOR THE YEAR			5.00	28400.00	71871.55	72011.60
===== 620-00011 Field Lab (CL 1) Each =====							
FSA2873-194		US 287 Longmont Intersection	02/13/20	1.00	17000.00	22966.67	18000.00
	WEIGHTED AVERAGE FOR THE FIRST QUARTER			1.00	17000.00	22966.67	18000.00
IM0252-473		I-25 CABLE BARRIER PHASE IV	04/09/20	1.00	20000.00	23500.00	25000.00
	WEIGHTED AVERAGE FOR THE SECOND QUARTER			1.00	20000.00	23500.00	25000.00
	WEIGHTED AVERAGE FOR THE YEAR			2.00	18500.00	23100.00	21500.00
===== 620-00012 Field Lab (CL 2) Each =====							
STA0142-066		SH 14 New Raymer West	01/09/20	1.00	13000.00	18008.25	15000.00

COLORADO DEPARTMENT OF TRANSPORTATION
ITEM UNIT COSTS BY PROJECTS -- 2020 COST DATA

10:58 Friday, October 2, 2020 295

PROJECT NUMBER	ITEM NUMBER/ PROJECT LOCATION	ITEM DESCRIPTION/ PROJECT LOCATION	DATE LET	UNIT/ QUANTITY	ENGR. EST.	AVERAGE BID	AWARDED BID
=====	620-00012	Field Lab (CL 2)		Each =====			
NHPP0343-041		I-76 & US 34 FT. MORGAN AREA	01/09/20	1.00	25000.00	61281.82	70700.00
BR0343-040		US 34 REPUBLICAN RIVER BRIDGE	01/16/20	1.00	22000.00	34308.33	29000.00
FBR0343-043		US 34 D-28-P STRUCTURE REPLAC					
STA006A-067		SH 6 Merino to Atwood	01/16/20	1.00	16000.00	18736.50	20000.00
STR131A-038		SH 131 MP 51.95-55.73, ROUTT	01/16/20	1.00	20000.00	14065.00	11380.00
NH 0503-093		US50 WEST OF TEXAS CREEK MP 2	01/23/20	1.00	15000.00	22555.96	19111.92
NHPP 0852-116		US85:HAMPDEN TO FLORIDA-RESUR	02/06/20	1.00	30000.00	22500.00	20000.00
STA0703-443		I-70 EJMT TUNNELS PAVING	02/06/20	1.00	30000.00	22768.32	13336.63
NHPP4701-134		C-470 NOISE WALL WEST OF LUCE	02/06/20	1.00	20000.00	20100.00	8500.00
STA059A-036		SH 59 SEIBERT TO COPE	02/06/20	1.00	23000.00	23000.00	20000.00
STR116A-001		SH 116 A Surface Treatment Pr	02/13/20	1.00	20000.00	21906.87	19000.00
STA069A-033		SH69 MP 58.7 TO 71.58	02/13/20	1.00	18000.00	14597.84	15000.00
STR0101-027		SH 10 Overlay La Junta West	02/27/20	1.00	20000.00	17079.68	24000.00
C0402-094		US 40 GRAND COUNTY SIGNAL REP	02/27/20	1.00	10000.00	14325.00	12000.00
NH0242-085		US 24 M.P. 291.38 to M.P. 296	02/27/20	1.00	27000.00	24636.67	31950.00
NHPP0171-105		SH 17 MP 84.5 to US 285 & SH	03/05/20	1.00	25000.00	42383.93	31151.79
C0641-106		SH 64 Meeker West Rural Resur	03/05/20	1.00	20000.00	21465.00	27000.00
STR2871-038		US 287 Passing Lanes Springfi	03/05/20	1.00	20000.00	18502.90	22639.50
NHPP0502-082		US 50 MONTROSE RE CHIP SEAL	03/05/20	1.00	23000.00	19625.00	26000.00
BR025A-046		K-18-U ON I-25 AT MP112 BRIDG	03/05/20	1.00	28000.00	21363.22	15872.38
NHPP0091-044		SH 9 FRISCO MAIN ST TO IRON S	03/05/20	1.00	40000.00	47356.67	45000.00
NH050A-034		US50A PUEBLO WEST PURCELL INT	03/26/20	1.00	25000.00	57563.04	85000.00
HPP 0501-067		US 50 AND SH 92 DELTA INTERSE	03/26/20	1.00	26000.00	21815.50	22600.00
SHE 0703-461		I-70 and Kipling North Phase	03/26/20	1.00	20000.00	35032.00	28610.00
		WEIGHTED AVERAGE FOR THE FIRST QUARTER		24.00	22333.33	29299.88	26368.84
NHPP1602-169		US 160 WC TUNNEL EAST RESURFA	04/02/20	1.00	20000.00	22371.20	27071.53
STR092A-030		SH92 MP 31.748-48.5,DELTA AND	04/02/20	1.00	22000.00	20695.00	28000.00
IM0761-226		I76/SH52 Interchange	04/02/20	1.00	25000.00	40769.11	37100.00
STA340A-021		SH340 MP 6-6.76 MESA COUNTY	04/02/20	1.00	25000.00	19500.00	800.00
STR0341-101		SH 34 North of Grandby Resurf	04/02/20	1.00	28000.00	25049.80	18200.00
SFTY2254-091		225 Ramp Improvements	04/09/20	1.00	50000.00	29300.00	36600.00
CC0852-106		US-85 LOUVIERS TO MP 191.75	04/23/20	1.00	175000.00	48434.84	60500.00
FBR0852-108		US-85 BETWEEN LOUVIERS AND MP					
FSA1602-159		US 160 AND SH 17 INTERSECTION	04/30/20	1.00	11000.00	34190.00	18070.00
C0853-112		US85 & WCR98 INTERSECTION IMP	05/07/20	1.00	18000.00	18683.13	10700.00
FBR0343-042		US 34 D-27-G STRUCTURE REPLAC	05/07/20	1.00	26000.00	22921.13	9800.00
		WEIGHTED AVERAGE FOR THE SECOND QUARTER		10.00	40000.00	29734.50	24684.15
		WEIGHTED AVERAGE FOR THE YEAR		34.00	27529.41	29466.26	25873.35
=====	620-00015	Field Lab (State Furn)		Each =====			
STR116A-001		SH 116 A Surface Treatment Pr	02/13/20	1.00	3000.00	8415.76	4000.00

PROJECT NUMBER	ITEM NUMBER/ PROJECT LOCATION	ITEM DESCRIPTION/ PROJECT LOCATION	DATE LET	UNIT/ QUANTITY	ENGR. EST.	AVERAGE BID	AWARDED BID
===== 620-00015		Field Lab (State Furn)		Each =====			
STA069A-033	SH69 MP 58.7 TO 71.58		02/13/20	1.00	8800.00	4339.95	4000.00
	WEIGHTED AVERAGE FOR THE FIRST QUARTER			2.00	5900.00	6785.43	4000.00
	WEIGHTED AVERAGE FOR THE YEAR			2.00	5900.00	6785.43	4000.00
===== 620-00020		Sanitary Facility		Each =====			
STA0142-066	SH 14 New Raymer West		01/09/20	1.00	2000.00	5531.00	10000.00
FSA0253-262	I-25 SB BOTTLENECK I-76 TO I-		01/09/20	1.00	3500.00	1907.59	2500.00
NHPP0253-265	I-25 AT ERIE PARKWAY ON AND O		01/09/20	1.00	1215.00	2076.67	1630.00
FSA0341-097	US 34 & MACGREGOR INTERSECTIO		01/09/20	1.00	2000.00	2500.00	2500.00
NHPP0343-041	I-76 & US 34 FT. MORGAN AREA		01/09/20	1.00	2744.00	26570.24	28013.00
BR0343-040	US 34 REPUBLICAN RIVER BRIDGE		01/16/20	1.00	2500.00	3444.17	5000.00
FBR0343-043	US 34 D-28-P STRUCTURE REPLAC						
STA006A-067	SH 6 Merino to Atwood		01/16/20	1.00	2000.00	4050.16	2500.00
STR131A-038	SH 131 MP 51.95-55.73, ROUTT		01/16/20	1.00	5000.00	3940.00	4130.00
NH 0503-093	US50 WEST OF TEXAS CREEK MP 2		01/23/20	2.00	1000.00	5650.32	6300.63
PWQM240-172	El Paso County, north Colorad		01/23/20	2.00	2500.00	1552.50	2975.00
STR012A-050	CULVERT REPAIR I-25 AND US 35		01/30/20	2.00	2500.00	250.00	250.00
STR141A-044	SH 141 AND SH 145, FROM SLICK		01/30/20	1.00	5000.00	10339.89	3500.00
NHPP 0852-116	US85:HAMPDEN TO FLORIDA-RESUR		02/06/20	3.00	5000.00	2500.00	2000.00
STA0703-443	I-70 EJMT TUNNELS PAVING		02/06/20	1.00	3000.00	7492.39	5834.77
ITS0761-231	ITS FIBER AND CAMERAS ON I-76		02/06/20	1.00	2000.00	4981.42	2000.00
NHPP4701-134	C-470 NOISE WALL WEST OF LUCE		02/06/20	1.00	2000.00	1720.00	1300.00
STA059A-036	SH 59 SEIBERT TO COPE		02/06/20	2.00	2000.00	7500.00	9000.00
STR116A-001	SH 116 A Surface Treatment Pr		02/13/20	1.00	7000.00	9094.67	6000.00
FSA2873-194	US 287 Longmont Intersection		02/13/20	1.00	2000.00	1972.33	1284.00
STA069A-033	SH69 MP 58.7 TO 71.58		02/13/20	2.00	2500.00	5667.54	6000.00
STR0101-027	SH 10 Overlay La Junta West		02/27/20	1.00	3000.00	7373.18	7000.00
NHPP0702-359	I-70 No Name Tunnel Lighting		02/27/20	1.00	4000.00	10887.50	10000.00
C0402-094	US 40 GRAND COUNTY SIGNAL REP		02/27/20	2.00	1500.00	1950.00	900.00
NH0242-085	US 24 M.P. 291.38 to M.P. 296		02/27/20	2.00	2800.00	1890.00	2570.00
NHPP0171-105	SH 17 MP 84.5 to US 285 & SH		03/05/20	1.00	3000.00	8583.50	8750.50
C0641-106	SH 64 Meeker West Rural Resur		03/05/20	2.00	5000.00	5495.00	5000.00
NHPP145A-080	SH 145 Keystone-Placerville R		03/05/20	1.00	2500.00	3200.00	3200.00
STR2871-038	US 287 Passing Lanes Springfi		03/05/20	1.00	5000.00	1758.98	1860.30
NHPP0502-082	US 50 MONTROSE RE CHIP SEAL		03/05/20	1.00	2000.00	3375.00	5000.00
BR025A-046	K-18-U ON I-25 AT MP112 BRIDG		03/05/20	2.00	2500.00	1844.01	2434.83
STRR300-249	Grand and Jackson Counties AD		03/05/20	1.00	2500.00	3350.00	3000.00
CC080-037	VARIOUS ADA RAMPS ALONG NORTH		03/05/20	1.00	2500.00	1387.50	1000.00
NHPP0091-044	SH 9 FRISCO MAIN ST TO IRON S		03/05/20	2.00	3500.00	5941.67	2900.00
NH050A-034	US50A PUEBLO WEST PURCELL INT		03/26/20	2.00	2500.00	7759.16	11000.00
HPP 0501-067	US 50 AND SH 92 DELTA INTERSE		03/26/20	1.00	2000.00	1532.50	1525.00
SHE 0703-461	I-70 and Kipling North Phase		03/26/20	1.00	3000.00	3273.00	1925.00
	WEIGHTED AVERAGE FOR THE FIRST QUARTER			49.00	2919.57	4920.16	4573.74

PROJECT NUMBER	ITEM NUMBER/ PROJECT LOCATION	ITEM DESCRIPTION/ PROJECT LOCATION	DATE LET	UNIT/ QUANTITY	ENGR. EST.	AVERAGE BID	AWARDED BID
===== 620-00020		Sanitary Facility		Each	=====	=====	=====
NHPP1602-169		US 160 WC TUNNEL EAST RESURFA	04/02/20	1.00	5000.00	5801.36	4629.23
STR092A-030		SH92 MP 31.748-48.5, DELTA AND	04/02/20	1.00	3000.00	3515.00	2000.00
IM0761-226		I76/SH52 Interchange	04/02/20	2.00	1500.00	5516.98	5618.00
STA340A-021		SH340 MP 6-6.76 MESA COUNTY	04/02/20	1.00	2000.00	2850.00	5000.00
STR0341-101		SH 34 North of Grandby Resurf	04/02/20	1.00	5000.00	6034.94	6840.00
IM0252-473		I-25 CABLE BARRIER PHASE IV	04/09/20	2.00	2500.00	2812.50	3125.00
SHER100-339		WWD TRAFFIC CONTROL ENHANCEME	04/09/20	2.00	3000.00	3000.00	3000.00
SFTY2254-091		225 Ramp Improvements	04/09/20	2.00	3500.00	2180.00	2860.00
CC0852-106		US-85 LOUVIERS TO MP 191.75	04/23/20	1.00	12000.00	8896.89	16500.00
FBR0852-108		US-85 BETWEEN LOUVIERS AND MP					
C1211-090		SH-121 & 29th Ave / SH-121 &	04/23/20	1.00	600.00	2557.00	700.00
C1601-082		Hawkins Signal and Curb Ramps	04/30/20	1.00	2000.00	3816.67	6000.00
FSA1602-159		US 160 AND SH 17 INTERSECTION	04/30/20	1.00	2000.00	9611.67	7230.00
C0853-112		US85 & WCR98 INTERSECTION IMP	05/07/20	2.00	2000.00	1222.25	1500.00
NHPPR100-303		LONG MAST ARM SIGNALS PROJECT	05/07/20	2.00	2000.00	1366.67	800.00
FBR0343-042		US 34 D-27-G STRUCTURE REPLAC	05/07/20	1.00	3000.00	2708.48	2700.00
ITS SW02-304		ITS FIBER TO STATE BUILDINGS	05/14/20	1.00	2000.00	3396.00	3000.00
NHPP0402-098		US 40 CHIP SEAL MP 126 TO MP	05/14/20	2.00	5000.00	850.00	250.00
NHPP0253-276		I-25 EXPRESS LANES SEGMENT 5	05/15/20	1.00	4000.00	3852.00	3852.00
ITS SW02-303		R1: US 285, SH 83 R2: SH 83,	05/28/20	1.00	2500.00	3573.60	750.00
NH050A-035		US 50A Pueblo Regional Pond	05/28/20	2.00	2500.00	2668.75	5000.00
NH050A-037		US 50A Pueblo Regional Pond					
SHER400-373		R4 Signal Head Backplate Inst	05/28/20	2.00	3000.00	4225.00	5950.00
IM025A-048		Northbound I-25 bridge at Exi	05/28/20	1.00	3100.00	1955.00	1500.00
FSAR400-356		FY 20 SIGNAL POLE REPLACEMENT	06/11/20	1.00	2000.00	2000.00	1500.00
SHE016A-043		SH 21 & 16 SIGNALS PROJECT	06/18/20	1.00	3000.00	2326.00	1525.00
NHPPR100-251		SH 2/ Vasquez	06/25/20	2.00	2000.00	930.18	566.35
	WEIGHTED AVERAGE FOR THE SECOND QUARTER			35.00	3005.71	3401.60	3472.50
	WEIGHTED AVERAGE FOR THE YEAR			84.00	2955.46	4216.05	4122.63
===== 621-00425		Detour		LUMP SUM	=====	=====	=====
BR025A-046		K-18-U ON I-25 AT MP112 BRIDG	03/05/20	1.00	535000.00	771911.37	684453.97
	WEIGHTED AVERAGE FOR THE FIRST QUARTER			1.00	535000.00	771911.37	684453.97
	WEIGHTED AVERAGE FOR THE YEAR			1.00	535000.00	771911.37	684453.97
===== 621-00450		Detour Pvmt		Sq Yard	=====	=====	=====
BR0343-040		US 34 REPUBLICAN RIVER BRIDGE	01/16/20	5,534.00	130.00	93.58	95.00

PROJECT NUMBER	ITEM NUMBER/ PROJECT LOCATION	ITEM DESCRIPTION/ PROJECT LOCATION	DATE LET	UNIT/ QUANTITY	ENGR. EST.	AVERAGE BID	AWARDED BID
=====	621-00450	Detour Pvmt		Sq Yard	=====		
FBR0343-043		US 34 D-28-P STRUCTURE REPLAC					
NHPP0091-044		SH 9 FRISCO MAIN ST TO IRON S	03/05/20	1,346.00	60.00	68.00	70.00
NH050A-034		US50A PUEBLO WEST PURCELL INT	03/26/20	9,530.00	40.00	47.23	35.50
HPP 0501-067		US 50 AND SH 92 DELTA INTERSE	03/26/20	730.00	65.00	72.10	30.00
		WEIGHTED AVERAGE FOR THE FIRST QUARTER		17,140.00	71.69	61.66	57.19
IM0761-226		I76/SH52 Interchange	04/02/20	5,475.00	75.00	43.63	31.41
CC0852-106		US-85 LOUVIERS TO MP 191.75	04/23/20	2,301.00	75.00	57.94	37.56
FBR0852-108		US-85 BETWEEN LOUVIERS AND MP					
FSA1602-159		US 160 AND SH 17 INTERSECTION	04/30/20	2,250.00	60.00	85.00	67.00
FBR0343-042		US 34 D-27-G STRUCTURE REPLAC	05/07/20	3,062.00	125.00	119.15	124.00
NHPP0253-276		I-25 EXPRESS LANES SEGMENT 5	05/15/20	1,414.00	33.00	29.82	29.82
		WEIGHTED AVERAGE FOR THE SECOND QUARTER		14,502.00	79.13	71.80	57.30
		WEIGHTED AVERAGE FOR THE YEAR		31,642.00	75.10	66.18	57.24
=====	621-00451	Detour Pavement		Ton	=====		
NHPPR100-251		SH 2/ Vasquez	06/25/20	190.00	190.00	286.70	283.40
		WEIGHTED AVERAGE FOR THE SECOND QUARTER		190.00	190.00	286.70	283.40
		WEIGHTED AVERAGE FOR THE YEAR		190.00	190.00	286.70	283.40
=====	622-00270	Bollard		Each	=====		
NHPP0091-044		SH 9 FRISCO MAIN ST TO IRON S	03/05/20	8.00	1000.00	780.00	810.00
		WEIGHTED AVERAGE FOR THE FIRST QUARTER		8.00	1000.00	780.00	810.00
FSA1602-159		US 160 AND SH 17 INTERSECTION	04/30/20	2.00	1500.00	1255.00	1020.00
		WEIGHTED AVERAGE FOR THE SECOND QUARTER		2.00	1500.00	1255.00	1020.00
		WEIGHTED AVERAGE FOR THE YEAR		10.00	1100.00	875.00	852.00
=====	622-00540	Wheel Stop		Each	=====		
NHPP0253-276		I-25 EXPRESS LANES SEGMENT 5	05/15/20	48.00	114.00	194.02	194.02
		WEIGHTED AVERAGE FOR THE SECOND QUARTER		48.00	114.00	194.02	194.02
		WEIGHTED AVERAGE FOR THE YEAR		48.00	114.00	194.02	194.02

COLORADO DEPARTMENT OF TRANSPORTATION
ITEM UNIT COSTS BY PROJECTS -- 2020 COST DATA

10:58 Friday, October 2, 2020 299

PROJECT NUMBER	ITEM NUMBER/ PROJECT LOCATION	ITEM DESCRIPTION/ PROJECT LOCATION	DATE LET	UNIT/ QUANTITY	ENGR. EST.	AVERAGE BID	AWARDED BID
=====	623-00604	4 Inch Plastic Pipe (Irrig/Sleve)		Lin Foot	=====		
NHPP0091-044		SH 9 FRISCO MAIN ST TO IRON S	03/05/20	415.00	10.00	12.42	9.50
	WEIGHTED AVERAGE FOR THE FIRST QUARTER			415.00	10.00	12.42	9.50
	WEIGHTED AVERAGE FOR THE YEAR			415.00	10.00	12.42	9.50
=====	624-20012	12 In Drainage Pipe (CL 0)		Lin Foot	=====		
FBR0343-042		US 34 D-27-G STRUCTURE REPLAC	05/07/20	44.00	150.00	63.53	64.00
	WEIGHTED AVERAGE FOR THE SECOND QUARTER			44.00	150.00	63.53	64.00
	WEIGHTED AVERAGE FOR THE YEAR			44.00	150.00	63.53	64.00
=====	624-20013	12 In Drainage Pipe (CL 0) (CIP)		Lin Foot	=====		
NHPP0091-044		SH 9 FRISCO MAIN ST TO IRON S	03/05/20	58.00	100.00	87.73	63.00
	WEIGHTED AVERAGE FOR THE FIRST QUARTER			58.00	100.00	87.73	63.00
	WEIGHTED AVERAGE FOR THE YEAR			58.00	100.00	87.73	63.00
=====	624-20018	18 In Drainage Pipe (CL 0)		Lin Foot	=====		
NHPP0343-041		I-76 & US 34 FT. MORGAN AREA	01/09/20	2,114.00	75.00	72.36	48.00
	WEIGHTED AVERAGE FOR THE FIRST QUARTER			2,114.00	75.00	72.36	48.00
	WEIGHTED AVERAGE FOR THE YEAR			2,114.00	75.00	72.36	48.00
=====	624-20019	18 In Drainage Pipe (CL 0) (CIP)		Lin Foot	=====		
NHPP0091-044		SH 9 FRISCO MAIN ST TO IRON S	03/05/20	108.00	100.00	100.67	54.00
	WEIGHTED AVERAGE FOR THE FIRST QUARTER			108.00	100.00	100.67	54.00
	WEIGHTED AVERAGE FOR THE YEAR			108.00	100.00	100.67	54.00
=====	624-20300	Detour Drainage Pipe (CL 0)		Lin Foot	=====		
BR0343-040		US 34 REPUBLICAN RIVER BRIDGE	01/16/20	300.00	130.00	168.54	145.00

COLORADO DEPARTMENT OF TRANSPORTATION
ITEM UNIT COSTS BY PROJECTS -- 2020 COST DATA

10:58 Friday, October 2, 2020 300

PROJECT NUMBER	ITEM NUMBER/ PROJECT LOCATION	ITEM DESCRIPTION/ PROJECT LOCATION	DATE LET	UNIT/ QUANTITY	ENGR. EST.	AVERAGE BID	AWARDED BID
=====	624-20300	Detour Drainage Pipe (CL 0)		Lin Foot	=====		
FBR0343-043		US 34 D-28-P STRUCTURE REPLAC					
		WEIGHTED AVERAGE FOR THE FIRST QUARTER		300.00	130.00	168.54	145.00
FBR0343-042		US 34 D-27-G STRUCTURE REPLAC	05/07/20	244.00	160.00	138.81	125.00
NHPP0253-276		I-25 EXPRESS LANES SEGMENT 5	05/15/20	869.00	134.00	110.81	110.81
		WEIGHTED AVERAGE FOR THE SECOND QUARTER		1,113.00	139.70	130.87	113.92
		WEIGHTED AVERAGE FOR THE YEAR		1,413.00	137.64	144.81	120.52
=====	624-22012	12 In Drainage Pipe (CL 2)		Lin Foot	=====		
BR0343-040		US 34 REPUBLICAN RIVER BRIDGE	01/16/20	163.00	70.00	82.23	60.00
FBR0343-043		US 34 D-28-P STRUCTURE REPLAC					
		WEIGHTED AVERAGE FOR THE FIRST QUARTER		163.00	70.00	82.23	60.00
		WEIGHTED AVERAGE FOR THE YEAR		163.00	70.00	82.23	60.00
=====	624-29016	15 In Drainage Pipe (CL 9) (CIP)		Lin Foot	=====		
FSA1602-159		US 160 AND SH 17 INTERSECTION	04/30/20	137.00	120.00	180.00	182.00
		WEIGHTED AVERAGE FOR THE SECOND QUARTER		137.00	120.00	180.00	182.00
		WEIGHTED AVERAGE FOR THE YEAR		137.00	120.00	180.00	182.00
=====	624-29019	18 In Drainage Pipe (CL 9) (CIP)		Lin Foot	=====		
FSA1602-159		US 160 AND SH 17 INTERSECTION	04/30/20	275.00	150.00	184.00	197.00
		WEIGHTED AVERAGE FOR THE SECOND QUARTER		275.00	150.00	184.00	197.00
		WEIGHTED AVERAGE FOR THE YEAR		275.00	150.00	184.00	197.00
=====	624-29025	24 In Drainage Pipe (CL 9) (CIP)		Lin Foot	=====		
NHPP0253-276		I-25 EXPRESS LANES SEGMENT 5	05/15/20	328.00	160.00	147.01	147.01
		WEIGHTED AVERAGE FOR THE SECOND QUARTER		328.00	160.00	147.01	147.01
		WEIGHTED AVERAGE FOR THE YEAR		328.00	160.00	147.01	147.01

COLORADO DEPARTMENT OF TRANSPORTATION
 ITEM UNIT COSTS BY PROJECTS -- 2020 COST DATA

10:58 Friday, October 2, 2020 301

PROJECT NUMBER	ITEM NUMBER/ PROJECT LOCATION	ITEM DESCRIPTION/ PROJECT LOCATION	DATE LET	UNIT/ QUANTITY	ENGR. EST.	AVERAGE BID	AWARDED BID
===== 624-29049		48 In Drainage Pipe (CL 9) (CIP)		Lin Foot	=====		
NHPP0253-276		I-25 EXPRESS LANES SEGMENT 5	05/15/20	819.00	231.00	227.94	227.94
	WEIGHTED AVERAGE FOR THE SECOND QUARTER			819.00	231.00	227.94	227.94
	WEIGHTED AVERAGE FOR THE YEAR			819.00	231.00	227.94	227.94
===== 624-30016		15 In Drainage Pipe (CL 10) (CIP)		Lin Foot	=====		
IM0761-226		I76/SH52 Interchange	04/02/20	97.00	45.00	103.50	79.00
	WEIGHTED AVERAGE FOR THE SECOND QUARTER			97.00	45.00	103.50	79.00
	WEIGHTED AVERAGE FOR THE YEAR			97.00	45.00	103.50	79.00
===== 624-30019		18 In Drainage Pipe (CL 10) (CIP)		Lin Foot	=====		
IM0761-226		I76/SH52 Interchange	04/02/20	1,262.00	50.00	100.38	82.50
	WEIGHTED AVERAGE FOR THE SECOND QUARTER			1,262.00	50.00	100.38	82.50
	WEIGHTED AVERAGE FOR THE YEAR			1,262.00	50.00	100.38	82.50
===== 624-30025		24 In Drainage Pipe (CL 10) (CIP)		Lin Foot	=====		
IM0761-226		I76/SH52 Interchange	04/02/20	897.00	80.00	137.74	97.00
	WEIGHTED AVERAGE FOR THE SECOND QUARTER			897.00	80.00	137.74	97.00
	WEIGHTED AVERAGE FOR THE YEAR			897.00	80.00	137.74	97.00
===== 624-30031		30 In Drainage Pipe (CL 10) CIP)		Lin Foot	=====		
IM0761-226		I76/SH52 Interchange	04/02/20	103.00	90.00	160.52	153.00
STA340A-021		SH340 MP 6-6.76 MESA COUNTY	04/02/20	174.00	125.00	212.33	134.00
	WEIGHTED AVERAGE FOR THE SECOND QUARTER			277.00	111.99	182.28	141.06
	WEIGHTED AVERAGE FOR THE YEAR			277.00	111.99	182.28	141.06

PROJECT NUMBER	ITEM NUMBER/ PROJECT LOCATION	ITEM DESCRIPTION/ PROJECT LOCATION	DATE LET	UNIT/ QUANTITY	ENGR. EST.	AVERAGE BID	AWARDED BID
===== 624-49019		18 In Equiv Drain Pipe E (CL 9) (CIP)		Lin Foot	=====		
FSA1602-159		US 160 AND SH 17 INTERSECTION	04/30/20	155.00	200.00	232.00	261.00
		WEIGHTED AVERAGE FOR THE SECOND QUARTER		155.00	200.00	232.00	261.00
		WEIGHTED AVERAGE FOR THE YEAR		155.00	200.00	232.00	261.00
===== 624-50031		30 In Equiv Drain Pipe E (CL 10) (CIP)		Lin Foot	=====		
IM0761-226		I76/SH52 Interchange	04/02/20	461.00	250.00	151.06	99.00
		WEIGHTED AVERAGE FOR THE SECOND QUARTER		461.00	250.00	151.06	99.00
		WEIGHTED AVERAGE FOR THE YEAR		461.00	250.00	151.06	99.00
===== 624-50055		54 In Equiv Drain Pipe E (CL 10) (CIP)		Lin Foot	=====		
IM0761-226		I76/SH52 Interchange	04/02/20	310.00	500.00	437.24	375.99
		WEIGHTED AVERAGE FOR THE SECOND QUARTER		310.00	500.00	437.24	375.99
		WEIGHTED AVERAGE FOR THE YEAR		310.00	500.00	437.24	375.99
===== 625-00000		Const Surveying		LUMP SUM	=====		
STA0142-066		SH 14 New Raymer West	01/09/20	1.00	15000.00	13558.25	18000.00
FSA0253-262		I-25 SB BOTTLENECK I-76 TO I-	01/09/20	1.00	10000.00	18582.27	19191.80
NHPP0253-265		I-25 AT ERIE PARKWAY ON AND O	01/09/20	1.00	6500.00	11718.33	11795.00
FSA0341-097		US 34 & MACGREGOR INTERSECTIO	01/09/20	1.00	25000.00	44000.00	44000.00
NHPP0343-041		I-76 & US 34 FT. MORGAN AREA	01/09/20	1.00	75000.00	188803.33	104374.00
BR0343-040		US 34 REPUBLICAN RIVER BRIDGE	01/16/20	1.00	50000.00	78887.83	60000.00
FBR0343-043		US 34 D-28-P STRUCTURE REPLAC					
STA006A-067		SH 6 Merino to Atwood	01/16/20	1.00	25000.00	19100.52	20000.00
STR131A-038		SH 131 MP 51.95-55.73, ROUTT	01/16/20	1.00	15000.00	8000.00	6000.00
NH 0503-093		US50 WEST OF TEXAS CREEK MP 2	01/23/20	1.00	20000.00	14875.79	15751.58
PWQM240-172		El Paso County, north Colorad	01/23/20	1.00	60000.00	85500.00	105000.00
STR141A-044		SH 141 AND SH 145, FROM SLICK	01/30/20	1.00	33000.00	48499.68	17000.00
NHPP 0852-116		US85:HAMPDEN TO FLORIDA-RESUR	02/06/20	1.00	110000.00	67500.00	75000.00
STA0703-443		I-70 EJMT TUNNELS PAVING	02/06/20	1.00	30000.00	19570.90	8641.80
ITS0761-231		ITS FIBER AND CAMERAS ON I-76	02/06/20	1.00	20000.00	25942.40	2500.00
NHPP4701-134		C-470 NOISE WALL WEST OF LUCE	02/06/20	1.00	10000.00	37274.93	36000.00

PROJECT NUMBER	ITEM NUMBER/ PROJECT LOCATION	ITEM DESCRIPTION/ PROJECT LOCATION	DATE LET	UNIT/ QUANTITY	ENGR. EST.	AVERAGE BID	AWARDED BID
===== 625-00000		Const Surveying		LUMP SUM	=====	=====	=====
STA059A-036	SH 59 SEIBERT TO COPE	SH 59 SEIBERT TO COPE	02/06/20	1.00	40000.00	36500.00	43000.00
STR116A-001	SH 116 A Surface Treatment Pr	SH 116 A Surface Treatment Pr	02/13/20	1.00	25000.00	28563.33	19000.00
FSA2873-194	US 287 Longmont Intersection	US 287 Longmont Intersection	02/13/20	1.00	12000.00	35329.17	20475.00
STA069A-033	SH69 MP 58.7 TO 71.58	SH69 MP 58.7 TO 71.58	02/13/20	1.00	48000.00	22993.36	25000.00
STR0101-027	SH 10 Overlay La Junta West	SH 10 Overlay La Junta West	02/27/20	1.00	25000.00	19079.68	5000.00
C0402-094	US 40 GRAND COUNTY SIGNAL REP	US 40 GRAND COUNTY SIGNAL REP	02/27/20	1.00	10000.00	19500.00	14000.00
NH0242-085	US 24 M.P. 291.38 to M.P. 296	US 24 M.P. 291.38 to M.P. 296	02/27/20	1.00	45000.00	43285.94	68350.00
NHPP0171-105	SH 17 MP 84.5 to US 285 & SH	SH 17 MP 84.5 to US 285 & SH	03/05/20	1.00	100000.00	101668.68	105006.04
NHPP145A-080	SH 145 Keystone-Placerville R	SH 145 Keystone-Placerville R	03/05/20	1.00	70000.00	14000.00	14000.00
STR2871-038	US 287 Passing Lanes Springfi	US 287 Passing Lanes Springfi	03/05/20	1.00	30000.00	33516.08	31590.00
BR025A-046	K-18-U ON I-25 AT MP112 BRIDG	K-18-U ON I-25 AT MP112 BRIDG	03/05/20	1.00	15000.00	23480.81	29920.86
NHPP0091-044	SH 9 FRISCO MAIN ST TO IRON S	SH 9 FRISCO MAIN ST TO IRON S	03/05/20	1.00	150000.00	179023.33	160000.00
NH050A-034	US50A PUEBLO WEST PURCELL INT	US50A PUEBLO WEST PURCELL INT	03/26/20	1.00	450000.00	424187.50	438000.00
HPP 0501-067	US 50 AND SH 92 DELTA INTERSE	US 50 AND SH 92 DELTA INTERSE	03/26/20	1.00	50000.00	48400.00	56000.00
SHE 0703-461	I-70 and Kipling North Phase	I-70 and Kipling North Phase	03/26/20	1.00	15000.00	26849.40	30047.00
	WEIGHTED AVERAGE FOR THE FIRST QUARTER			30.00	52983.33	76477.99	53421.44
IM0761-226	I76/SH52 Interchange	I76/SH52 Interchange	04/02/20	1.00	200000.00	160600.00	84800.00
STA340A-021	SH340 MP 6-6.76 MESA COUNTY	SH340 MP 6-6.76 MESA COUNTY	04/02/20	1.00	15000.00	20366.67	12000.00
SFTY2254-091	225 Ramp Improvements	225 Ramp Improvements	04/09/20	1.00	100000.00	29000.00	25000.00
CC0852-106	US-85 LOUVIERS TO MP 191.75	US-85 LOUVIERS TO MP 191.75	04/23/20	1.00	350000.00	389648.07	110000.00
FBR0852-108	US-85 BETWEEN LOUVIERS AND MP	US-85 BETWEEN LOUVIERS AND MP					
C1211-090	SH-121 & 29th Ave / SH-121 &	SH-121 & 29th Ave / SH-121 &	04/23/20	1.00	65000.00	16064.67	12355.00
C1601-082	Hawkins Signal and Curb Ramps	Hawkins Signal and Curb Ramps	04/30/20	1.00	30000.00	84103.33	109000.00
FSA1602-159	US 160 AND SH 17 INTERSECTION	US 160 AND SH 17 INTERSECTION	04/30/20	1.00	25000.00	78720.00	109100.00
C0853-112	US85 & WCR98 INTERSECTION IMP	US85 & WCR98 INTERSECTION IMP	05/07/20	1.00	15000.00	28462.50	21600.00
NHPPR100-303	LONG MAST ARM SIGNALS PROJECT	LONG MAST ARM SIGNALS PROJECT	05/07/20	1.00	19000.00	21764.67	29680.00
FBR0343-042	US 34 D-27-G STRUCTURE REPLAC	US 34 D-27-G STRUCTURE REPLAC	05/07/20	1.00	39000.00	39074.41	42000.00
ITS SW02-304	ITS FIBER TO STATE BUILDINGS	ITS FIBER TO STATE BUILDINGS	05/14/20	1.00	10000.00	16878.00	25376.00
NHPP0402-098	US 40 CHIP SEAL MP 126 TO MP	US 40 CHIP SEAL MP 126 TO MP	05/14/20	1.00	10000.00	12193.33	20000.00
NHPP0253-276	I-25 EXPRESS LANES SEGMENT 5	I-25 EXPRESS LANES SEGMENT 5	05/15/20	1.00	237600.00	245545.17	245545.17
NH050A-035	US 50A Pueblo Regional Pond	US 50A Pueblo Regional Pond	05/28/20	1.00	22500.00	37892.50	35000.00
NH050A-037	US 50A Pueblo Regional Pond	US 50A Pueblo Regional Pond					
FSAR400-356	FY 20 SIGNAL POLE REPLACEMENT	FY 20 SIGNAL POLE REPLACEMENT	06/11/20	1.00	9000.00	5616.67	5850.00
SHE016A-043	SH 21 & 16 SIGNALS PROJECT	SH 21 & 16 SIGNALS PROJECT	06/18/20	1.00	15000.00	9261.00	8990.00
	WEIGHTED AVERAGE FOR THE SECOND QUARTER			16.00	72631.25	85722.53	56018.51
	WEIGHTED AVERAGE FOR THE YEAR			46.00	59817.39	80401.54	54324.77
===== 625-00001		Const Surveying (Hour)		Hour	=====	=====	=====
NHPP4701-134	C-470 NOISE WALL WEST OF LUCE	C-470 NOISE WALL WEST OF LUCE	02/06/20	20.00	200.00	184.00	175.00

PROJECT NUMBER	ITEM NUMBER/ PROJECT LOCATION	ITEM DESCRIPTION/ PROJECT LOCATION	DATE LET	UNIT/ QUANTITY	ENGR. EST.	AVERAGE BID	AWARDED BID
=====	625-00001	Const Surveying (Hour)		Hour	=====	=====	=====
STRR300-249		Grand and Jackson Counties AD	03/05/20	40.00	200.00	163.33	145.00
NHPP0091-044		SH 9 FRISCO MAIN ST TO IRON S	03/05/20	100.00	200.00	201.17	180.00
SHE 0703-461		I-70 and Kipling North Phase	03/26/20	20.00	170.00	199.80	200.00
	WEIGHTED AVERAGE FOR THE FIRST QUARTER			180.00	196.67	190.85	173.89
STR092A-030		SH92 MP 31.748-48.5, DELTA AND	04/02/20	20.00	150.00	199.00	163.00
IM0252-473		I-25 CABLE BARRIER PHASE IV	04/09/20	100.00	170.00	197.22	194.44
CC0852-106		US-85 LOUVIERS TO MP 191.75	04/23/20	60.00	200.00	198.09	220.00
FBR0852-108		US-85 BETWEEN LOUVIERS AND MP					
C1211-090		SH-121 & 29th Ave / SH-121 &	04/23/20	10.00	175.00	219.33	190.00
	WEIGHTED AVERAGE FOR THE SECOND QUARTER			190.00	177.63	198.76	198.97
	WEIGHTED AVERAGE FOR THE YEAR			370.00	186.89	195.18	186.77
=====	625-00015	Settlement Instrument		LUMP SUM	=====	=====	=====
NH050A-034		US50A PUEBLO WEST PURCELL INT	03/26/20	1.00	20000.00	20750.00	13300.00
	WEIGHTED AVERAGE FOR THE FIRST QUARTER			1.00	20000.00	20750.00	13300.00
	WEIGHTED AVERAGE FOR THE YEAR			1.00	20000.00	20750.00	13300.00
=====	626-00000	Mobilization		LUMP SUM	=====	=====	=====
STA0142-066		SH 14 New Raymer West	01/09/20	1.00	325000.00	353386.75	452047.00
FSA0253-262		I-25 SB BOTTLENECK I-76 TO I-	01/09/20	1.00	120000.00	140633.33	102000.00
NHPP0253-265		I-25 AT ERIE PARKWAY ON AND O	01/09/20	1.00	50000.00	69349.33	22750.00
SHER500-210		R5 FY19 CENTER LINE RUMBLE ST	01/09/20	1.00	100000.00	139000.00	153000.00
FSA0341-097		US 34 & MACGREGOR INTERSECTIO	01/09/20	1.00	90000.00	250000.00	250000.00
NHPP0343-041		I-76 & US 34 FT. MORGAN AREA	01/09/20	1.00	1250000.00	1388914.56	1100000.00
BR0343-040		US 34 REPUBLICAN RIVER BRIDGE	01/16/20	1.00	525000.00	559089.67	514000.00
FBR0343-043		US 34 D-28-P STRUCTURE REPLAC					
STA006A-067		SH 6 Merino to Atwood	01/16/20	1.00	250000.00	325824.05	185000.00
STR131A-038		SH 131 MP 51.95-55.73, ROUTT	01/16/20	1.00	160000.00	173345.00	146690.00
NH 0503-093		US50 WEST OF TEXAS CREEK MP 2	01/23/20	1.00	489674.00	581197.54	558395.07
PWQM240-172		El Paso County, north Colorad	01/23/20	1.00	438611.00	73212.50	62425.00
STR012A-050		CULVERT REPAIR I-25 AND US 35	01/30/20	1.00	60888.75	140000.00	140000.00
STR141A-044		SH 141 AND SH 145, FROM SLICK	01/30/20	1.00	800000.00	1074186.88	512000.00
NHPP 0852-116		US85:HAMPDEN TO FLORIDA-RESUR	02/06/20	1.00	600000.00	735000.00	770000.00

PROJECT NUMBER	ITEM NUMBER/ PROJECT LOCATION	ITEM DESCRIPTION/ PROJECT LOCATION	DATE LET	UNIT/ QUANTITY	ENGR. EST.	AVERAGE BID	AWARDED BID
=====	626-00000	Mobilization		LUMP SUM	=====	=====	=====
STA0703-443		I-70 EJMT TUNNELS PAVING	02/06/20	1.00	350000.00	386500.00	383000.00
MTCER300-257		R3 FY 20/21 Region Wide Epoxy	02/06/20	1.00	13000.00	55000.00	35000.00
ITS0761-231		ITS FIBER AND CAMERAS ON I-76	02/06/20	1.00	275000.00	327570.36	215100.00
NHPP4701-134		C-470 NOISE WALL WEST OF LUCE	02/06/20	1.00	20000.00	334200.00	330000.00
STA059A-036		SH 59 SEIBERT TO COPE	02/06/20	1.00	600000.00	815486.00	703972.00
STR116A-001		SH 116 A Surface Treatment Pr	02/13/20	1.00	604993.60	678122.00	512675.00
MTCER500-213		R5 FY 20 / FY 21 STRIPING	02/13/20	1.00	15000.00	33475.00	45000.00
FSA2873-194		US 287 Longmont Intersection	02/13/20	1.00	100000.00	136585.83	122515.00
STA069A-033		SH69 MP 58.7 TO 71.58	02/13/20	1.00	245743.50	402383.10	281766.20
STR0101-027		SH 10 Overlay La Junta West	02/27/20	1.00	360960.70	466021.55	501699.40
NHPP0702-359		I-70 No Name Tunnel Lighting	02/27/20	1.00	400000.00	330984.71	288006.84
C0402-094		US 40 GRAND COUNTY SIGNAL REP	02/27/20	1.00	110000.00	214172.50	153000.00
NH0242-085		US 24 M.P. 291.38 to M.P. 296	02/27/20	1.00	258258.10	384244.60	275000.00
NHPP0171-105		SH 17 MP 84.5 to US 285 & SH	03/05/20	1.00	1400000.00	1316558.84	1243676.51
C0641-106		SH 64 Meeker West Rural Resur	03/05/20	1.00	700000.00	510610.00	435000.00
NHPP145A-080		SH 145 Keystone-Placerville R	03/05/20	1.00	470000.00	480000.00	480000.00
STR2871-038		US 287 Passing Lanes Springfi	03/05/20	1.00	449105.00	448588.91	432152.07
NHPP0502-082		US 50 MONTROSE RE CHIP SEAL	03/05/20	1.00	300000.00	340000.00	340000.00
BR025A-046		K-18-U ON I-25 AT MP112 BRIDG	03/05/20	1.00	219705.07	217989.92	128573.44
STRR300-249		Grand and Jackson Counties AD	03/05/20	1.00	120000.00	420472.00	212551.00
CC080-037		VARIOUS ADA RAMPS ALONG NORTH	03/05/20	1.00	45000.00	79612.25	40449.00
NHPP0091-044		SH 9 FRISCO MAIN ST TO IRON S	03/05/20	1.00	1200000.00	1454000.00	1412000.00
NH050A-034		US50A PUEBLO WEST PURCELL INT	03/26/20	1.00	2700156.75	3281670.78	3300000.00
HPP 0501-067		US 50 AND SH 92 DELTA INTERSE	03/26/20	1.00	180000.00	142397.88	124800.00
SHE 0703-461		I-70 and Kipling North Phase	03/26/20	1.00	250000.00	242650.20	238000.00
	WEIGHTED AVERAGE FOR THE FIRST QUARTER			39.00	426822.99	612980.83	441083.17
NHPP1602-169		US 160 WC TUNNEL EAST RESURFA	04/02/20	1.00	750000.00	668533.16	613000.00
STR092A-030		SH92 MP 31.748-48.5,DELTA AND	04/02/20	1.00	500000.00	537150.00	578000.00
IM0761-226		I76/SH52 Interchange	04/02/20	1.00	1000000.00	1249364.84	1144453.90
STA340A-021		SH340 MP 6-6.76 MESA COUNTY	04/02/20	1.00	100000.00	152086.67	129260.00
MTCER300-259		MTCE R3 FY20/21 Region Wide S	04/02/20	1.00	20000.00	41250.00	32500.00
STR0341-101		SH 34 North of Grandby Resurf	04/02/20	1.00	870000.00	740550.57	582780.00
IM0252-473		I-25 CABLE BARRIER PHASE IV	04/09/20	1.00	166068.00	205939.45	161878.90
SHER100-339		WWD TRAFFIC CONTROL ENHANCEME	04/09/20	1.00	175000.00	325000.00	325000.00
NHPP1601-077		US 160 MP 29.750 - MP 34.891	04/09/20	1.00	150000.00	237000.00	190000.00
SFTY2254-091		225 Ramp Improvements	04/09/20	1.00	350000.00	311900.00	233800.00
CC0852-106		US-85 LOUVIERS TO MP 191.75	04/23/20	1.00	2500000.00	2215831.68	2126375.35
FBR0852-108		US-85 BETWEEN LOUVIERS AND MP					
C1211-090		SH-121 & 29th Ave / SH-121 &	04/23/20	1.00	100000.00	110738.33	107215.00
C1601-082		Hawkins Signal and Curb Ramps	04/30/20	1.00	140000.00	296666.67	200000.00
FSA1602-159		US 160 AND SH 17 INTERSECTION	04/30/20	1.00	250000.00	620266.67	637300.00
C0853-112		US85 & WCR98 INTERSECTION IMP	05/07/20	1.00	170000.00	176406.53	132000.00
NHPPR100-303		LONG MAST ARM SIGNALS PROJECT	05/07/20	1.00	130000.00	119066.67	120000.00

COLORADO DEPARTMENT OF TRANSPORTATION
ITEM UNIT COSTS BY PROJECTS -- 2020 COST DATA

10:58 Friday, October 2, 2020 306

PROJECT NUMBER	ITEM NUMBER/ PROJECT LOCATION	ITEM DESCRIPTION/ PROJECT LOCATION	DATE LET	UNIT/ QUANTITY	ENGR. EST.	AVERAGE BID	AWARDED BID
=====	626-00000	Mobilization		LUMP SUM	=====		
FBR0343-042		US 34 D-27-G STRUCTURE REPLAC	05/07/20	1.00	300000.00	244160.74	198000.00
ITS SW02-304		ITS FIBER TO STATE BUILDINGS	05/14/20	1.00	500000.00	278649.75	160538.00
NHPP0402-098		US 40 CHIP SEAL MP 126 TO MP	05/14/20	1.00	71500.00	168333.33	150000.00
MTCE R100-341		Various Highways in Region 1	05/21/20	1.00	25000.00	87500.00	50000.00
ITS SW02-303		R1: US 285, SH 83 R2: SH 83,	05/28/20	1.00	400000.00	182546.60	66150.00
MTCER200-265		Pueblo	05/28/20	1.00	35015.05	99750.00	125000.00
NH050A-035		US 50A Pueblo Regional Pond	05/28/20	1.00	130459.00	203862.75	195000.00
NH050A-037		US 50A Pueblo Regional Pond					
SHER400-373		R4 Signal Head Backplate Inst	05/28/20	1.00	170000.00	137500.00	83000.00
IM025A-048		Northbound I-25 bridge at Exi	05/28/20	1.00	74549.00	66457.33	39000.00
ITSSW01-719		FY 20 ITS CAPITAL REPLACEMENT	06/11/20	1.00	360000.00	150000.00	125000.00
FSAR400-356		FY 20 SIGNAL POLE REPLACEMENT	06/11/20	1.00	55000.00	57031.67	38825.00
SHE016A-043		SH 21 & 16 SIGNALS PROJECT	06/18/20	1.00	90290.80	118376.60	83427.00
NHPPR100-251		SH 2/ Vasquez	06/25/20	1.00	75000.00	129000.00	167000.00
		WEIGHTED AVERAGE FOR THE SECOND QUARTER		29.00	333030.41	446846.29	303258.73
		WEIGHTED AVERAGE FOR THE YEAR		68.00	386823.21	535593.38	382305.10
=====	626-00100	Mobilization (w/o Autopay)		LUMP SUM	=====		
NH 0503-093		US50 WEST OF TEXAS CREEK MP 2	01/23/20	1.00	20000.00	4084.16	6168.32
		WEIGHTED AVERAGE FOR THE FIRST QUARTER		1.00	20000.00	4084.16	6168.32
NHPP0253-276		I-25 EXPRESS LANES SEGMENT 5	05/15/20	1.00	1000800.00	946683.59	946683.59
		WEIGHTED AVERAGE FOR THE SECOND QUARTER		1.00	1000800.00	946683.59	946683.59
		WEIGHTED AVERAGE FOR THE YEAR		2.00	673866.67	475383.88	633178.50
=====	626-01111	Public Info Manage (Tier I)		Day	=====		
NHPP0253-276		I-25 EXPRESS LANES SEGMENT 5	05/15/20	90.00	188.00	156.04	156.04
		WEIGHTED AVERAGE FOR THE SECOND QUARTER		90.00	188.00	156.04	156.04
		WEIGHTED AVERAGE FOR THE YEAR		90.00	188.00	156.04	156.04
=====	626-01112	Public Info Manage (Tier II)		Day	=====		
NH0242-085		US 24 M.P. 291.38 to M.P. 296	02/27/20	140.00	90.00	143.52	200.00
		WEIGHTED AVERAGE FOR THE FIRST QUARTER		140.00	90.00	143.52	200.00
		WEIGHTED AVERAGE FOR THE YEAR		140.00	90.00	143.52	200.00

PROJECT NUMBER	ITEM NUMBER/ PROJECT LOCATION	ITEM DESCRIPTION/ PROJECT LOCATION	DATE LET	UNIT/ QUANTITY	ENGR. EST.	AVERAGE BID	AWARDED BID
===== 626-01113		Public Info Manage (Tier III)		Day	=====		
FSA0253-262	I-25 SB BOTTLENECK I-76 TO I-	01/09/20	180.00	27.00	47.50	55.00	
FSA0341-097	US 34 & MACGREGOR INTERSECTIO	01/09/20	125.00	72.00	125.00	125.00	
STR131A-038	SH 131 MP 51.95-55.73, ROUTT	01/16/20	100.00	65.00	55.00	60.00	
NH 0503-093	US50 WEST OF TEXAS CREEK MP 2	01/23/20	120.00	80.00	124.76	94.51	
NHPP 0852-116	US85:HAMPDEN TO FLORIDA-RESUR	02/06/20	80.00	125.00	102.50	125.00	
STA0703-443	I-70 EJMT TUNNELS PAVING	02/06/20	70.00	500.00	179.45	173.89	
NHPP0702-359	I-70 No Name Tunnel Lighting	02/27/20	428.00	80.00	92.70	45.00	
C0402-094	US 40 GRAND COUNTY SIGNAL REP	02/27/20	70.00	200.00	76.25	52.50	
C0641-106	SH 64 Meeker West Rural Resur	03/05/20	166.00	80.00	50.00	50.00	
BR025A-046	K-18-U ON I-25 AT MP112 BRIDG	03/05/20	195.00	80.00	71.45	45.51	
NHPP0091-044	SH 9 FRISCO MAIN ST TO IRON S	03/05/20	433.00	69.00	86.67	70.00	
HPP 0501-067	US 50 AND SH 92 DELTA INTERSE	03/26/20	150.00	120.00	59.50	34.00	
SHE 0703-461	I-70 and Kipling North Phase	03/26/20	115.00	160.00	144.20	155.00	
	WEIGHTED AVERAGE FOR THE FIRST QUARTER		2,232.00	97.83	87.06	70.96	
IM0761-226	I76/SH52 Interchange	04/02/20	275.00	100.00	75.68	70.33	
STR0341-101	SH 34 North of Grandby Resurf	04/02/20	225.00	153.00	64.49	63.20	
IM0252-473	I-25 CABLE BARRIER PHASE IV	04/09/20	148.00	80.00	61.10	72.19	
SFTY2254-091	225 Ramp Improvements	04/09/20	67.00	225.00	78.00	64.00	
CC0852-106	US-85 LOUVIERS TO MP 191.75	04/23/20	410.00	330.00	69.83	66.55	
FBR0852-108	US-85 BETWEEN LOUVIERS AND MP						
C1211-090	SH-121 & 29th Ave / SH-121 &	04/23/20	120.00	85.00	100.33	106.00	
C1601-082	Hawkins Signal and Curb Ramps	04/30/20	215.00	50.00	103.00	74.00	
NHPP0402-098	US 40 CHIP SEAL MP 126 TO MP	05/14/20	60.00	70.00	88.67	125.00	
SHE016A-043	SH 21 & 16 SIGNALS PROJECT	06/18/20	95.00	25.00	91.10	96.50	
NHPPRI00-251	SH 2/ Vasquez	06/25/20	10.00	135.00	858.73	916.46	
	WEIGHTED AVERAGE FOR THE SECOND QUARTER		1,625.00	155.70	77.94	80.17	
	WEIGHTED AVERAGE FOR THE YEAR		3,857.00	122.21	82.18	74.84	
===== 626-01114		Public Info Manage (Tier IV)		Day	=====		
STA0142-066	SH 14 New Raymer West	01/09/20	51.00	100.00	69.75	53.00	
NHPP0253-265	I-25 AT ERIE PARKWAY ON AND O	01/09/20	40.00	120.00	94.00	96.00	
SHER500-210	R5 FY19 CENTER LINE RUMBLE ST	01/09/20	60.00	100.00	100.50	1.00	
BR0343-040	US 34 REPUBLICAN RIVER BRIDGE	01/16/20	185.00	45.00	93.10	69.00	
FBR0343-043	US 34 D-28-P STRUCTURE REPLAC						
STA006A-067	SH 6 Merino to Atwood	01/16/20	50.00	125.00	107.01	74.00	
PWQM240-172	El Paso County, north Colorad	01/23/20	300.00	33.50	25.50	22.00	

PROJECT NUMBER	ITEM NUMBER/ PROJECT LOCATION	ITEM DESCRIPTION/ PROJECT LOCATION	DATE LET	UNIT/ QUANTITY	ENGR. EST.	AVERAGE BID	AWARDED BID
===== 626-01114							
		Public Info Manage (Tier IV)		Day			
STR012A-050		CULVERT REPAIR I-25 AND US 35	01/30/20	90.00	70.00	50.00	50.00
STR141A-044		SH 141 AND SH 145, FROM SLICK	01/30/20	270.00	80.00	46.20	29.00
NHPP4701-134		C-470 NOISE WALL WEST OF LUCE	02/06/20	100.00	50.00	59.40	70.00
STA059A-036		SH 59 SEIBERT TO COPE	02/06/20	257.00	50.00	37.00	34.00
STR116A-001		SH 116 A Surface Treatment Pr	02/13/20	169.00	75.00	51.58	41.00
MTCER500-213		R5 FY 20 / FY 21 STRIPING	02/13/20	90.00	70.00	100.38	66.50
FSA2873-194		US 287 Longmont Intersection	02/13/20	90.00	100.00	94.33	160.00
STA069A-033		SH69 MP 58.7 TO 71.58	02/13/20	165.00	75.00	77.00	50.00
STR0101-027		SH 10 Overlay La Junta West	02/27/20	156.00	75.00	44.43	35.00
NHPP0171-105		SH 17 MP 84.5 to US 285 & SH	03/05/20	370.00	67.00	60.00	60.00
NHPP145A-080		SH 145 Keystone-Placerville R	03/05/20	131.00	80.00	49.00	49.00
STR2871-038		US 287 Passing Lanes Springfi	03/05/20	198.00	75.00	65.68	72.54
NHPP0502-082		US 50 MONTROSE RE CHIP SEAL	03/05/20	120.00	60.00	77.26	35.00
STRR300-249		Grand and Jackson Counties AD	03/05/20	75.00	80.00	106.67	60.00
CC080-037		VARIOUS ADA RAMPS ALONG NORTH	03/05/20	25.00	100.00	192.75	140.00
WEIGHTED AVERAGE FOR THE FIRST QUARTER				2,992.00	68.23	66.42	51.45
NHPP1602-169		US 160 WC TUNNEL EAST RESURFA	04/02/20	98.00	90.00	75.07	74.72
STR092A-030		SH92 MP 31.748-48.5, DELTA AND	04/02/20	68.00	200.00	101.00	100.00
STA340A-021		SH340 MP 6-6.76 MESA COUNTY	04/02/20	50.00	200.00	123.50	116.00
SHER100-339		WWD TRAFFIC CONTROL ENHANCEME	04/09/20	240.00	50.00	100.00	100.00
NHPP1601-077		US 160 MP 29.750 - MP 34.891	04/09/20	83.00	72.00	54.33	40.00
FSA1602-159		US 160 AND SH 17 INTERSECTION	04/30/20	1.00	4000.00	3856.00	86.00
C0853-112		US85 & WCR98 INTERSECTION IMP	05/07/20	47.00	150.00	86.75	65.00
NHPPR100-303		LONG MAST ARM SIGNALS PROJECT	05/07/20	200.00	25.00	61.00	71.00
FBR0343-042		US 34 D-27-G STRUCTURE REPLAC	05/07/20	95.00	65.00	72.07	64.00
ITS SW02-304		ITS FIBER TO STATE BUILDINGS	05/14/20	20.00	200.00	216.75	121.01
ITS SW02-303		R1: US 285, SH 83 R2: SH 83,	05/28/20	10.00	100.00	443.18	200.00
MTCER200-265		Pueblo	05/28/20	120.00	52.00	104.50	125.00
SHER400-373		R4 Signal Head Backplate Inst	05/28/20	90.00	95.00	82.00	95.00
IM025A-048		Northbound I-25 bridge at Exi	05/28/20	82.00	100.00	68.47	50.00
ITSSW01-719		FY 20 ITS CAPITAL REPLACEMENT	06/11/20	10.00	50.00	77.50	55.00
FSAR400-356		FY 20 SIGNAL POLE REPLACEMENT	06/11/20	55.00	135.00	82.33	80.00
WEIGHTED AVERAGE FOR THE SECOND QUARTER				1,269.00	85.53	89.88	84.86
=====							
WEIGHTED AVERAGE FOR THE YEAR				4,261.00	73.38	73.59	61.40
=====							
===== 627-00001							
		Pvmt Mkg Paint		Gallon			
NH 0503-093		US50 WEST OF TEXAS CREEK MP 2	01/23/20	2,054.00	40.00	50.92	48.83
STR116A-001		SH 116 A Surface Treatment Pr	02/13/20	5,692.00	40.00	32.27	40.00

PROJECT NUMBER	ITEM NUMBER/ PROJECT LOCATION	ITEM DESCRIPTION/ PROJECT LOCATION	DATE LET	UNIT/ QUANTITY	ENGR. EST.	AVERAGE BID	AWARDED BID
=====	627-00001	Pvmt Mkg Paint		Gallon	=====	=====	=====
STR0101-027		SH 10 Overlay La Junta West	02/27/20	2,808.00	40.00	53.53	51.00
BR025A-046		K-18-U ON I-25 AT MP112 BRIDG	03/05/20	113.00	100.00	70.94	63.71
		WEIGHTED AVERAGE FOR THE FIRST QUARTER		10,667.00	40.64	41.68	44.85
		WEIGHTED AVERAGE FOR THE YEAR		10,667.00	40.64	41.68	44.85
=====	627-00003	Thermoplastic Pvmt Mkg (Inlaid)		Sq Foot	=====	=====	=====
SHE 0703-461		I-70 and Kipling North Phase	03/26/20	875.00	9.80	17.70	22.00
		WEIGHTED AVERAGE FOR THE FIRST QUARTER		875.00	9.80	17.70	22.00
		WEIGHTED AVERAGE FOR THE YEAR		875.00	9.80	17.70	22.00
=====	627-00006	Mod Epoxy Pvmt Mkg (On-Call)		Gallon	=====	=====	=====
MTCER300-257		R3 FY 20/21 Region Wide Epoxy	02/06/20	1,100.00	66.00	82.75	80.50
		WEIGHTED AVERAGE FOR THE FIRST QUARTER		1,100.00	66.00	82.75	80.50
		WEIGHTED AVERAGE FOR THE YEAR		1,100.00	66.00	82.75	80.50
=====	627-00008	Mod Epoxy Pvmt Mkg		Gallon	=====	=====	=====
STA0142-066		SH 14 New Raymer West	01/09/20	696.00	125.00	81.00	75.00
FSA0253-262		I-25 SB BOTTLENECK I-76 TO I-	01/09/20	104.00	100.00	147.74	132.00
NHPP0253-265		I-25 AT ERIE PARKWAY ON AND O	01/09/20	33.00	100.00	208.33	270.00
FSA0341-097		US 34 & MACGREGOR INTERSECTIO	01/09/20	24.00	200.00	320.00	320.00
NHPP0343-041		I-76 & US 34 FT. MORGAN AREA	01/09/20	1,576.00	82.00	79.18	85.00
BR0343-040		US 34 REPUBLICAN RIVER BRIDGE	01/16/20	21.00	300.00	440.72	500.00
FBR0343-043		US 34 D-28-P STRUCTURE REPLAC					
STA006A-067		SH 6 Merino to Atwood	01/16/20	528.00	100.00	100.29	102.00
STR131A-038		SH 131 MP 51.95-55.73, ROUTT	01/16/20	364.00	90.00	90.75	86.50
NH 0503-093		US50 WEST OF TEXAS CREEK MP 2	01/23/20	1,363.00	125.00	96.42	90.83
NHPP 0852-116		US85:HAMPDEN TO FLORIDA-RESUR	02/06/20	754.00	100.00	85.00	100.00
STA0703-443		I-70 EJMT TUNNELS PAVING	02/06/20	285.00	100.00	132.96	162.29
MTCER300-257		R3 FY 20/21 Region Wide Epoxy	02/06/20	39,082.00	61.00	74.45	73.90
STA059A-036		SH 59 SEIBERT TO COPE	02/06/20	2,035.00	75.00	98.50	87.00
STA069A-033		SH69 MP 58.7 TO 71.58	02/13/20	1,112.00	62.00	136.25	130.00
C0402-094		US 40 GRAND COUNTY SIGNAL REP	02/27/20	18.00	150.00	487.50	500.00
NH0242-085		US 24 M.P. 291.38 to M.P. 296	02/27/20	677.00	66.00	93.51	110.00

PROJECT NUMBER	ITEM NUMBER/ PROJECT LOCATION	ITEM DESCRIPTION/ PROJECT LOCATION	DATE LET	UNIT/ QUANTITY	ENGR. EST.	AVERAGE BID	AWARDED BID
===== 627-00008 Mod Epoxy Pvmt Mkg Gallon =====							
C0641-106	SH 64 Meeker West Rural Resur	SH 64 Meeker West Rural Resur	03/05/20	1,626.00	90.00	67.50	70.00
NHPP0502-082	US 50 MONTROSE RE CHIP SEAL	US 50 MONTROSE RE CHIP SEAL	03/05/20	4,461.00	70.00	95.13	95.50
BR025A-046	K-18-U ON I-25 AT MP112 BRIDG	K-18-U ON I-25 AT MP112 BRIDG	03/05/20	25.00	80.00	275.47	178.62
NHPP0091-044	SH 9 FRISCO MAIN ST TO IRON S	SH 9 FRISCO MAIN ST TO IRON S	03/05/20	88.00	150.00	313.33	320.00
HPP 0501-067	US 50 AND SH 92 DELTA INTERSE	US 50 AND SH 92 DELTA INTERSE	03/26/20	17.00	70.00	463.25	476.00
SHE 0703-461	I-70 and Kipling North Phase	I-70 and Kipling North Phase	03/26/20	20.00	100.00	316.40	360.00
WEIGHTED AVERAGE FOR THE FIRST QUARTER				54,909.00	67.95	82.98	80.84
STR092A-030	SH92 MP 31.748-48.5, DELTA AND	SH92 MP 31.748-48.5, DELTA AND	04/02/20	1,461.00	100.00	95.75	91.50
IM0761-226	I76/SH52 Interchange	I76/SH52 Interchange	04/02/20	173.00	120.00	126.81	100.70
STA340A-021	SH340 MP 6-6.76 MESA COUNTY	SH340 MP 6-6.76 MESA COUNTY	04/02/20	52.00	100.00	237.50	225.00
STR0341-101	SH 34 North of Grandby Resurf	SH 34 North of Grandby Resurf	04/02/20	1,422.00	90.00	105.50	92.00
SFTY2254-091	225 Ramp Improvements	225 Ramp Improvements	04/09/20	91.00	90.00	227.50	298.00
CC0852-106	US-85 LOUVIERS TO MP 191.75	US-85 LOUVIERS TO MP 191.75	04/23/20	883.00	80.00	90.49	88.00
FBR0852-108	US-85 BETWEEN LOUVIERS AND MP	US-85 BETWEEN LOUVIERS AND MP					
C1211-090	SH-121 & 29th Ave / SH-121 &	SH-121 & 29th Ave / SH-121 &	04/23/20	30.00	64.00	206.35	342.00
C0853-112	US85 & WCR98 INTERSECTION IMP	US85 & WCR98 INTERSECTION IMP	05/07/20	81.00	100.00	118.13	117.00
NHPPR100-303	LONG MAST ARM SIGNALS PROJECT	LONG MAST ARM SIGNALS PROJECT	05/07/20	1.00	500.00	618.33	620.00
FBR0343-042	US 34 D-27-G STRUCTURE REPLAC	US 34 D-27-G STRUCTURE REPLAC	05/07/20	29.00	450.00	311.22	300.00
NHPP0402-098	US 40 CHIP SEAL MP 126 TO MP	US 40 CHIP SEAL MP 126 TO MP	05/14/20	1,196.00	85.00	84.93	79.00
MTCE R100-341	Various Highways in Region 1	Various Highways in Region 1	05/21/20	65,653.00	54.00	66.08	68.15
MT CER200-265	Pueblo	Pueblo	05/28/20	36,732.00	63.00	70.63	69.50
SHE016A-043	SH 21 & 16 SIGNALS PROJECT	SH 21 & 16 SIGNALS PROJECT	06/18/20	102.00	160.00	355.81	375.57
WEIGHTED AVERAGE FOR THE SECOND QUARTER				107,906.00	59.12	71.43	70.32
WEIGHTED AVERAGE FOR THE YEAR				162,815.00	62.10	74.78	73.86
===== 627-00009 Mod Epoxy (Inlaid) Gallon =====							
NHPP4701-134	C-470 NOISE WALL WEST OF LUCE	C-470 NOISE WALL WEST OF LUCE	02/06/20	8.00	150.00	587.00	500.00
STR2871-038	US 287 Passing Lanes Springfi	US 287 Passing Lanes Springfi	03/05/20	324.00	150.00	183.22	171.19
NH050A-034	US50A PUEBLO WEST PURCELL INT	US50A PUEBLO WEST PURCELL INT	03/26/20	384.00	180.00	193.57	210.00
WEIGHTED AVERAGE FOR THE FIRST QUARTER				716.00	166.09	195.97	195.68
C0853-112	US85 & WCR98 INTERSECTION IMP	US85 & WCR98 INTERSECTION IMP	05/07/20	45.00	150.00	247.88	250.00
WEIGHTED AVERAGE FOR THE SECOND QUARTER				45.00	150.00	247.88	250.00
WEIGHTED AVERAGE FOR THE YEAR				761.00	165.14	200.51	198.89

PROJECT NUMBER	ITEM NUMBER/ PROJECT LOCATION	ITEM DESCRIPTION/ PROJECT LOCATION	DATE LET	UNIT/ QUANTITY	ENGR. EST.	AVERAGE BID	AWARDED BID
===== 627-00011		Pvmt Mkg Paint (Waterborne)		Gallon	=====		
STA0142-066		SH 14 New Raymer West	01/09/20	1,331.00	50.00	52.00	36.00
BR0343-040		US 34 REPUBLICAN RIVER BRIDGE	01/16/20	90.00	80.00	78.22	68.00
FBR0343-043		US 34 D-28-P STRUCTURE REPLAC					
STA006A-067		SH 6 Merino to Atwood	01/16/20	980.00	50.00	54.88	56.00
NHPP0702-359		I-70 No Name Tunnel Lighting	02/27/20	20.00	90.00	197.76	132.00
		WEIGHTED AVERAGE FOR THE FIRST QUARTER		2,421.00	51.45	55.98	46.08
FBR0343-042		US 34 D-27-G STRUCTURE REPLAC	05/07/20	67.00	75.00	102.05	90.00
NHPP0253-276		I-25 EXPRESS LANES SEGMENT 5	05/15/20	2.00	200.00	169.24	169.24
		WEIGHTED AVERAGE FOR THE SECOND QUARTER		69.00	78.62	102.27	92.30
		WEIGHTED AVERAGE FOR THE YEAR		2,490.00	52.20	59.27	47.36
===== 627-00013		Pvmt Mkg Paint (High Build)		Gallon	=====		
SHER500-210		R5 FY19 CENTER LINE RUMBLE ST	01/09/20	6,812.00	50.00	35.00	32.00
NHPP0343-041		I-76 & US 34 FT. MORGAN AREA	01/09/20	850.00	50.00	58.57	104.00
STR131A-038		SH 131 MP 51.95-55.73, ROUTT	01/16/20	433.00	40.00	63.75	55.50
STR141A-044		SH 141 AND SH 145, FROM SLICK	01/30/20	11,533.00	46.43	33.07	30.92
NHPP 0852-116		US85:HAMPDEN TO FLORIDA-RESUR	02/06/20	2,111.00	37.00	45.00	50.00
STA059A-036		SH 59 SEIBERT TO COPE	02/06/20	2,222.00	47.00	48.00	41.00
STR116A-001		SH 116 A Surface Treatment Pr	02/13/20	2,973.00	45.00	32.43	38.00
MTCER500-213		R5 FY 20 / FY 21 STRIPING	02/13/20	72,200.00	24.00	30.03	27.25
FSA2873-194		US 287 Longmont Intersection	02/13/20	57.00	60.00	112.58	89.00
STA069A-033		SH69 MP 58.7 TO 71.58	02/13/20	2,107.00	30.00	42.98	49.00
STR0101-027		SH 10 Overlay La Junta West	02/27/20	2,429.00	45.00	39.41	42.00
NH0242-085		US 24 M.P. 291.38 to M.P. 296	02/27/20	1,598.00	28.00	58.47	62.00
NHPP0171-105		SH 17 MP 84.5 to US 285 & SH	03/05/20	9,820.00	45.00	38.82	31.47
C0641-106		SH 64 Meeker West Rural Resur	03/05/20	1,245.00	40.00	47.00	60.00
NHPP145A-080		SH 145 Keystone-Placerville R	03/05/20	4,881.00	27171.00	34.67	34.67
STR2871-038		US 287 Passing Lanes Springfi	03/05/20	355.00	100.00	103.80	142.74
NHPP0502-082		US 50 MONTROSE RE CHIP SEAL	03/05/20	8,077.00	30.00	39.25	33.00
NHPP0091-044		SH 9 FRISCO MAIN ST TO IRON S	03/05/20	241.00	50.00	91.92	91.00
NH050A-034		US50A PUEBLO WEST PURCELL INT	03/26/20	560.00	26.00	63.44	54.00
HPP 0501-067		US 50 AND SH 92 DELTA INTERSE	03/26/20	225.00	45.00	59.40	61.60
SHE 0703-461		I-70 and Kipling North Phase	03/26/20	8.00	40.00	309.00	250.00
		WEIGHTED AVERAGE FOR THE FIRST QUARTER		130,737.00	1045.11	33.60	32.21
NHPP1602-169		US 160 WC TUNNEL EAST RESURFA	04/02/20	2,710.00	35.00	47.96	49.81

COLORADO DEPARTMENT OF TRANSPORTATION
ITEM UNIT COSTS BY PROJECTS -- 2020 COST DATA

10:58 Friday, October 2, 2020 312

PROJECT NUMBER	ITEM NUMBER/ PROJECT LOCATION	ITEM DESCRIPTION/ PROJECT LOCATION	DATE LET	UNIT/ QUANTITY	ENGR. EST.	AVERAGE BID	AWARDED BID
=====	627-00013	Pvmt Mkg Paint (High Build)		Gallon	=====	=====	=====
STR092A-030		SH92 MP 31.748-48.5, DELTA AND	04/02/20	4,128.00	40.00	36.35	35.00
IM0761-226		I76/SH52 Interchange	04/02/20	224.00	60.00	65.61	63.60
STA340A-021		SH340 MP 6-6.76 MESA COUNTY	04/02/20	201.00	40.00	63.33	60.00
STR0341-101		SH 34 North of Grandby Resurf	04/02/20	2,290.00	50.00	39.75	28.00
NHPP1601-077		US 160 MP 29.750 - MP 34.891	04/09/20	1,367.00	30.00	46.63	32.25
CC0852-106		US-85 LOUVIERS TO MP 191.75	04/23/20	1,484.00	38.00	49.36	44.00
FBR0852-108		US-85 BETWEEN LOUVIERS AND MP					
C1601-082		Hawkins Signal and Curb Ramps	04/30/20	18.00	50.00	192.33	150.00
FSA1602-159		US 160 AND SH 17 INTERSECTION	04/30/20	43.00	150.00	1034.00	91.00
C0853-112		US85 & WCR98 INTERSECTION IMP	05/07/20	216.00	50.00	65.25	62.00
NHPP0402-098		US 40 CHIP SEAL MP 126 TO MP	05/14/20	622.00	35.00	45.08	46.00
		WEIGHTED AVERAGE FOR THE SECOND QUARTER		13,303.00	40.09	48.73	39.68
		WEIGHTED AVERAGE FOR THE YEAR		144,040.00	952.29	34.98	32.90
=====	627-00014	Pvmt Mkg Paint (Low Temp)		Gallon	=====	=====	=====
STA0703-443		I-70 EJMT TUNNELS PAVING	02/06/20	1,194.00	65.00	48.93	55.18
		WEIGHTED AVERAGE FOR THE FIRST QUARTER		1,194.00	65.00	48.93	55.18
		WEIGHTED AVERAGE FOR THE YEAR		1,194.00	65.00	48.93	55.18
=====	627-00019	Pvmt Mkg Paint (High Build) (Inlaid)		Gallon	=====	=====	=====
NHPP1602-169		US 160 WC TUNNEL EAST RESURFA	04/02/20	1,485.00	80.00	126.58	124.53
		WEIGHTED AVERAGE FOR THE SECOND QUARTER		1,485.00	80.00	126.58	124.53
		WEIGHTED AVERAGE FOR THE YEAR		1,485.00	80.00	126.58	124.53
=====	627-00025	4 In Pvmt Mkg Tape (Rem)		Lin Foot	=====	=====	=====
NHPP 0852-116		US85:HAMPDEN TO FLORIDA-RESUR	02/06/20	9,600.00	5.00	3.75	6.00
NHPP4701-134		C-470 NOISE WALL WEST OF LUCE	02/06/20	1,790.00	1.00	6.00	5.00
		WEIGHTED AVERAGE FOR THE FIRST QUARTER		11,390.00	4.37	4.47	5.84
		WEIGHTED AVERAGE FOR THE YEAR		11,390.00	4.37	4.47	5.84
=====	627-00070	Preform Thermoplastic Pvmt Mkg		Sq Foot	=====	=====	=====
NHPP0343-041		I-76 & US 34 FT. MORGAN AREA	01/09/20	7,912.00	15.00	16.10	17.00
		WEIGHTED AVERAGE FOR THE FIRST QUARTER		7,912.00	15.00	16.10	17.00
		WEIGHTED AVERAGE FOR THE YEAR		7,912.00	15.00	16.10	17.00

PROJECT NUMBER	ITEM NUMBER/ PROJECT LOCATION	ITEM DESCRIPTION/ PROJECT LOCATION	DATE LET	UNIT/ QUANTITY	ENGR. EST.	AVERAGE BID	AWARDED BID
=====	627-00090	Pvmt Mkg (Spec)		Sq Foot	=====		
NHPP0091-044		SH 9 FRISCO MAIN ST TO IRON S	03/05/20	1,000.00	7.00	12.20	11.00
		WEIGHTED AVERAGE FOR THE FIRST QUARTER		1,000.00	7.00	12.20	11.00
		WEIGHTED AVERAGE FOR THE YEAR		1,000.00	7.00	12.20	11.00
=====	627-01010	Preform Plastic Pvmt Mkg (TY I) (Inlaid)		Sq Foot	=====		
FSA0253-262		I-25 SB BOTTLENECK I-76 TO I-	01/09/20	3,024.00	13.00	13.90	13.00
NH 0503-093		US50 WEST OF TEXAS CREEK MP 2	01/23/20	3,950.00	15.00	18.40	16.80
NHPP 0852-116		US85:HAMPDEN TO FLORIDA-RESUR	02/06/20	209.00	14.00	13.75	17.00
STA0703-443		I-70 EJMT TUNNELS PAVING	02/06/20	3,144.00	12.00	20.10	24.34
NHPP4701-134		C-470 NOISE WALL WEST OF LUCE	02/06/20	128.00	15.00	53.20	45.00
NH0242-085		US 24 M.P. 291.38 to M.P. 296	02/27/20	7,149.00	10.00	16.27	18.00
NHPP0091-044		SH 9 FRISCO MAIN ST TO IRON S	03/05/20	969.00	20.00	20.45	18.00
NH050A-034		US50A PUEBLO WEST PURCELL INT	03/26/20	4,832.00	13.00	17.52	19.15
HPP 0501-067		US 50 AND SH 92 DELTA INTERSE	03/26/20	187.00	20.00	32.40	33.60
SHE 0703-461		I-70 and Kipling North Phase	03/26/20	1,300.00	13.00	21.54	29.20
		WEIGHTED AVERAGE FOR THE FIRST QUARTER		24,892.00	12.67	17.78	19.06
IM0761-226		I76/SH52 Interchange	04/02/20	45.00	20.00	17.55	15.90
SFTY2254-091		225 Ramp Improvements	04/09/20	1,240.00	20.00	15.50	16.00
CC0852-106		US-85 LOUVIERS TO MP 191.75	04/23/20	4,313.00	10.00	14.59	13.75
FBR0852-108		US-85 BETWEEN LOUVIERS AND MP					
C1601-082		Hawkins Signal and Curb Ramps	04/30/20	126.00	15.00	29.00	25.00
FSA1602-159		US 160 AND SH 17 INTERSECTION	04/30/20	1,077.00	40.00	18.67	17.00
NHPPR100-303		LONG MAST ARM SIGNALS PROJECT	05/07/20	129.00	20.00	28.33	25.00
MTCE R100-341		Various Highways in Region 1	05/21/20	282,150.00	9.20	10.50	10.00
		WEIGHTED AVERAGE FOR THE SECOND QUARTER		289,080.00	9.38	10.82	10.12
		WEIGHTED AVERAGE FOR THE YEAR		313,972.00	9.64	11.76	10.83
=====	627-01011	Preform Plastic Pvmt Mkg (Contr) (Inlaid)		Sq Foot	=====		
FSA0253-262		I-25 SB BOTTLENECK I-76 TO I-	01/09/20	3,024.00	13.00	13.90	13.00
		WEIGHTED AVERAGE FOR THE FIRST QUARTER		3,024.00	13.00	13.90	13.00

COLORADO DEPARTMENT OF TRANSPORTATION
ITEM UNIT COSTS BY PROJECTS -- 2020 COST DATA

10:58 Friday, October 2, 2020 314

PROJECT NUMBER	ITEM NUMBER/ PROJECT LOCATION	ITEM DESCRIPTION/ PROJECT LOCATION	DATE LET	UNIT/ QUANTITY	ENGR. EST.	AVERAGE BID	AWARDED BID
=====	627-01011	Preform Plastic Pvmt Mkg (Contr) (Inlaid)		Sq Foot	=====		
SFTY2254-091		225 Ramp Improvements	04/09/20	1,240.00	20.00	15.50	16.00
CC0852-106		US-85 LOUVIERS TO MP 191.75	04/23/20	4,313.00	10.00	14.59	13.75
FBR0852-108		US-85 BETWEEN LOUVIERS AND MP					
MTCE R100-341		Various Highways in Region 1	05/21/20	72,488.00	9.60	10.50	10.00
		WEIGHTED AVERAGE FOR THE SECOND QUARTER		78,041.00	9.79	11.34	10.30
		WEIGHTED AVERAGE FOR THE YEAR		81,065.00	9.91	11.46	10.40
=====	627-02010	Preform Plastic Pvmt Mkg (Ty II) (Inlaid)		Sq Foot	=====		
FSA0253-262		I-25 SB BOTTLENECK I-76 TO I-	01/09/20	908.00	11.00	19.61	18.00
NHPP 0852-116		US85:HAMPDEN TO FLORIDA-RESUR	02/06/20	9,846.00	11.00	14.75	18.00
STR2871-038		US 287 Passing Lanes Springfi	03/05/20	1,278.00	15.00	28.21	26.33
HPP 0501-067		US 50 AND SH 92 DELTA INTERSE	03/26/20	89.00	20.00	49.05	50.40
		WEIGHTED AVERAGE FOR THE FIRST QUARTER		12,121.00	11.49	16.89	19.12
IM0761-226		I76/SH52 Interchange	04/02/20	916.00	20.00	18.19	15.90
FSA1602-159		US 160 AND SH 17 INTERSECTION	04/30/20	2,981.00	20.00	21.67	20.00
MTCE R100-341		Various Highways in Region 1	05/21/20	24,849.00	9.60	11.25	10.50
		WEIGHTED AVERAGE FOR THE SECOND QUARTER		28,746.00	11.01	13.37	11.66
		WEIGHTED AVERAGE FOR THE YEAR		40,867.00	11.15	14.35	13.87
=====	627-30105	Pvmt Mkg Paint (WS)		Sq Foot	=====		
NHPP1602-169		US 160 WC TUNNEL EAST RESURFA	04/02/20	1,307.00	20.00	19.97	20.30
		WEIGHTED AVERAGE FOR THE SECOND QUARTER		1,307.00	20.00	19.97	20.30
		WEIGHTED AVERAGE FOR THE YEAR		1,307.00	20.00	19.97	20.30
=====	627-30205	Thermoplastic Pvmt Mkg (WS)		Sq Foot	=====		
FSA2873-194		US 287 Longmont Intersection	02/13/20	221.00	20.00	23.77	21.00
		WEIGHTED AVERAGE FOR THE FIRST QUARTER		221.00	20.00	23.77	21.00
		WEIGHTED AVERAGE FOR THE YEAR		221.00	20.00	23.77	21.00

COLORADO DEPARTMENT OF TRANSPORTATION
ITEM UNIT COSTS BY PROJECTS -- 2020 COST DATA

10:58 Friday, October 2, 2020 315

PROJECT NUMBER	ITEM NUMBER/ PROJECT LOCATION	ITEM DESCRIPTION/ PROJECT LOCATION	DATE LET	UNIT/ QUANTITY	ENGR. EST.	AVERAGE BID	AWARDED BID
=====	627-30210	Thermoplastic Pvmt Mkg (XS)		Sq Foot	=====		
FSA2873-194		US 287 Longmont Intersection	02/13/20	114.00	20.00	20.53	21.00
		WEIGHTED AVERAGE FOR THE FIRST QUARTER		114.00	20.00	20.53	21.00
		WEIGHTED AVERAGE FOR THE YEAR		114.00	20.00	20.53	21.00
=====	627-30323	Preform Plastic Pvmt Mkg (WS) (Typ I) (In)		Sq Foot	=====		
SHE 0703-461		I-70 and Kipling North Phase	03/26/20	250.00	14.40	34.40	44.00
		WEIGHTED AVERAGE FOR THE FIRST QUARTER		250.00	14.40	34.40	44.00
IM0761-226		I76/SH52 Interchange	04/02/20	1,737.00	20.00	24.30	21.20
FSA1602-159		US 160 AND SH 17 INTERSECTION	04/30/20	325.00	30.00	45.00	48.00
		WEIGHTED AVERAGE FOR THE SECOND QUARTER		2,062.00	21.58	25.84	25.42
		WEIGHTED AVERAGE FOR THE YEAR		2,312.00	20.80	26.58	27.43
=====	627-30327	Preform Plastic Pvmt Mkg (WS) (Ty III)		Sq Foot	=====		
NHPP 0852-116		US85:HAMPDEN TO FLORIDA-RESUR	02/06/20	1,069.00	18.00	17.50	20.00
		WEIGHTED AVERAGE FOR THE FIRST QUARTER		1,069.00	18.00	17.50	20.00
		WEIGHTED AVERAGE FOR THE YEAR		1,069.00	18.00	17.50	20.00
=====	627-30328	Pre Plastic Pvmt Mkg (XWalk) (Typ1) (In)		Sq Foot	=====		
SHE 0703-461		I-70 and Kipling North Phase	03/26/20	450.00	11.75	18.00	15.00
		WEIGHTED AVERAGE FOR THE FIRST QUARTER		450.00	11.75	18.00	15.00
IM0761-226		I76/SH52 Interchange	04/02/20	1,600.00	15.00	16.05	15.90

PROJECT NUMBER	ITEM NUMBER/ PROJECT LOCATION	ITEM DESCRIPTION/ PROJECT LOCATION	DATE LET	UNIT/ QUANTITY	ENGR. EST.	AVERAGE BID	AWARDED BID
=====	627-30328	Pre Plastic Pvmt Mkg (XWalk) (Typl) (In)		Sq Foot	=====	=====	=====
FSA1602-159		US 160 AND SH 17 INTERSECTION	04/30/20	772.00	15.00	19.00	16.00
	WEIGHTED AVERAGE FOR THE SECOND QUARTER			2,372.00	15.00	16.55	15.93
	WEIGHTED AVERAGE FOR THE YEAR			2,822.00	14.48	16.76	15.78
=====	627-30329	Preform Plastic Pvmt Mkg (XS) (TY I)		Sq Foot	=====	=====	=====
NHPP0343-041		I-76 & US 34 FT. MORGAN AREA	01/09/20	2,494.00	14.00	13.08	14.00
	WEIGHTED AVERAGE FOR THE FIRST QUARTER			2,494.00	14.00	13.08	14.00
	WEIGHTED AVERAGE FOR THE YEAR			2,494.00	14.00	13.08	14.00
=====	627-30332	Preform Plastic Pvmt Mkg (XS) (Ty III)		Sq Foot	=====	=====	=====
NHPP 0852-116		US85:HAMPDEN TO FLORIDA-RESUR	02/06/20	4,962.00	12.00	10.88	12.00
	WEIGHTED AVERAGE FOR THE FIRST QUARTER			4,962.00	12.00	10.88	12.00
	WEIGHTED AVERAGE FOR THE YEAR			4,962.00	12.00	10.88	12.00
=====	627-30405	Preform Thermoplastic Pvmt Mkg (WS)		Sq Foot	=====	=====	=====
FSA0253-262		I-25 SB BOTTLENECK I-76 TO I-	01/09/20	290.00	12.00	28.54	26.00
NHPP0253-265		I-25 AT ERIE PARKWAY ON AND O	01/09/20	322.00	16.00	20.67	18.00
FSA0341-097		US 34 & MACGREGOR INTERSECTIO	01/09/20	286.00	20.00	31.00	31.00
NHPP0343-041		I-76 & US 34 FT. MORGAN AREA	01/09/20	1,877.00	14.00	17.11	18.00
BR0343-040		US 34 REPUBLICAN RIVER BRIDGE	01/16/20	44.00	25.00	32.91	30.00
FBR0343-043		US 34 D-28-P STRUCTURE REPLAC					
STA006A-067		SH 6 Merino to Atwood	01/16/20	456.00	20.00	18.74	19.00
NH 0503-093		US50 WEST OF TEXAS CREEK MP 2	01/23/20	453.00	20.00	29.15	27.30
STA059A-036		SH 59 SEIBERT TO COPE	02/06/20	138.00	17.00	25.00	30.00
STA069A-033		SH69 MP 58.7 TO 71.58	02/13/20	273.00	17.00	18.86	24.00
STR0101-027		SH 10 Overlay La Junta West	02/27/20	89.00	25.00	32.37	30.00
NH0242-085		US 24 M.P. 291.38 to M.P. 296	02/27/20	939.00	15.00	17.83	18.40
NHPP0171-105		SH 17 MP 84.5 to US 285 & SH	03/05/20	1,134.00	20.00	17.66	16.24
NHPP145A-080		SH 145 Keystone-Placerville R	03/05/20	415.00	20.00	22.50	22.50
STR2871-038		US 287 Passing Lanes Springfi	03/05/20	232.00	20.00	32.60	30.42
NH050A-034		US50A PUEBLO WEST PURCELL INT	03/26/20	1,918.00	16.50	16.72	18.00
	WEIGHTED AVERAGE FOR THE FIRST QUARTER			8,866.00	16.97	18.56	20.11

PROJECT NUMBER	ITEM NUMBER/ PROJECT LOCATION	ITEM DESCRIPTION/ PROJECT LOCATION	DATE LET	UNIT/ QUANTITY	ENGR. EST.	AVERAGE BID	AWARDED BID
===== 627-30405		Preform Thermoplastic Pvmt Mkg (WS)		Sq Foot	=====		
STA340A-021		SH340 MP 6-6.76 MESA COUNTY	04/02/20	17.00	30.00	18.93	18.00
SFTY2254-091		225 Ramp Improvements	04/09/20	226.00	50.00	24.00	24.00
CC0852-106		US-85 LOUVIERS TO MP 191.75	04/23/20	872.00	13.00	18.75	18.70
FBR0852-108		US-85 BETWEEN LOUVIERS AND MP					
C1211-090		SH-121 & 29th Ave / SH-121 &	04/23/20	318.00	16.97	23.03	18.50
C1601-082		Hawkins Signal and Curb Ramps	04/30/20	101.00	17.00	26.50	24.50
C0853-112		US85 & WCR98 INTERSECTION IMP	05/07/20	165.00	20.00	20.26	18.00
NHPPR100-303		LONG MAST ARM SIGNALS PROJECT	05/07/20	15.00	20.00	45.33	31.00
FBR0343-042		US 34 D-27-G STRUCTURE REPLAC	05/07/20	148.00	30.00	29.32	28.00
MTCE R100-341		Various Highways in Region 1	05/21/20	74,908.00	11.00	12.50	12.00
SHE016A-043		SH 21 & 16 SIGNALS PROJECT	06/18/20	612.00	20.00	17.97	17.34
		WEIGHTED AVERAGE FOR THE SECOND QUARTER		77,382.00	11.30	13.20	12.24
		WEIGHTED AVERAGE FOR THE YEAR		86,248.00	11.88	14.10	13.05
===== 627-30407		Preform Thermoplastic Pvmt Mkg (WS) (Sp)		Sq Foot	=====		
C0402-094		US 40 GRAND COUNTY SIGNAL REP	02/27/20	228.00	20.00	20.50	21.00
NHPP0091-044		SH 9 FRISCO MAIN ST TO IRON S	03/05/20	1,488.00	25.00	21.55	20.00
HPP 0501-067		US 50 AND SH 92 DELTA INTERSE	03/26/20	365.00	20.00	16.35	16.80
		WEIGHTED AVERAGE FOR THE FIRST QUARTER		2,081.00	23.58	20.79	19.55
MT CER300-259		MTCE R3 FY20/21 Region Wide S	04/02/20	10,363.00	14.00	18.13	16.25
NHPP0402-098		US 40 CHIP SEAL MP 126 TO MP	05/14/20	560.00	20.00	19.88	16.00
		WEIGHTED AVERAGE FOR THE SECOND QUARTER		10,923.00	14.31	18.26	16.24
		WEIGHTED AVERAGE FOR THE YEAR		13,004.00	15.79	18.77	16.77
===== 627-30408		Pre Thermo Pvmt Mkg (Shield)		Sq Foot	=====		
MTCE R100-341		Various Highways in Region 1	05/21/20	7,568.00	24.00	20.25	18.50
		WEIGHTED AVERAGE FOR THE SECOND QUARTER		7,568.00	24.00	20.25	18.50
		WEIGHTED AVERAGE FOR THE YEAR		7,568.00	24.00	20.25	18.50

PROJECT NUMBER	ITEM NUMBER/ PROJECT LOCATION	ITEM DESCRIPTION/ PROJECT LOCATION	DATE LET	UNIT/ QUANTITY	ENGR. EST.	AVERAGE BID	AWARDED BID
===== 627-30410		Preform Thermoplastic Pvmt Mkg (XS)		Sq Foot	=====		
STA0142-066		SH 14 New Raymer West	01/09/20	348.00	20.00	19.94	18.25
FSA0253-262		I-25 SB BOTTLENECK I-76 TO I-	01/09/20	48.00	12.00	16.38	15.00
NHPP0253-265		I-25 AT ERIE PARKWAY ON AND O	01/09/20	1,036.00	17.00	13.83	14.00
FSA0341-097		US 34 & MACGREGOR INTERSECTIO	01/09/20	120.00	15.00	20.00	20.00
BR0343-040		US 34 REPUBLICAN RIVER BRIDGE	01/16/20	880.00	20.00	12.40	13.00
FBR0343-043		US 34 D-28-P STRUCTURE REPLAC					
STA006A-067		SH 6 Merino to Atwood	01/16/20	119.00	20.00	12.54	12.75
STR141A-044		SH 141 AND SH 145, FROM SLICK	01/30/20	102.00	20.00	40.22	39.00
STA059A-036		SH 59 SEIBERT TO COPE	02/06/20	1,118.00	20.00	13.00	12.00
STA069A-033		SH69 MP 58.7 TO 71.58	02/13/20	1,132.00	13.00	17.36	21.00
NH050A-034		US50A PUEBLO WEST PURCELL INT	03/26/20	2,292.00	12.50	13.33	14.40
		WEIGHTED AVERAGE FOR THE FIRST QUARTER		7,195.00	15.94	14.19	15.44
NHPP1602-169		US 160 WC TUNNEL EAST RESURFA	04/02/20	760.00	20.00	16.70	15.32
CC0852-106		US-85 LOUVIERS TO MP 191.75	04/23/20	590.00	12.00	13.98	13.75
FBR0852-108		US-85 BETWEEN LOUVIERS AND MP					
C1211-090		SH-121 & 29th Ave / SH-121 &	04/23/20	3,648.00	12.06	13.75	11.50
C1601-082		Hawkins Signal and Curb Ramps	04/30/20	2,989.00	17.00	24.58	16.50
C0853-112		US85 & WCR98 INTERSECTION IMP	05/07/20	335.00	15.00	15.56	13.00
NHPPR100-303		LONG MAST ARM SIGNALS PROJECT	05/07/20	3,861.00	16.00	11.00	11.00
FBR0343-042		US 34 D-27-G STRUCTURE REPLAC	05/07/20	70.00	25.00	23.87	23.00
MTCE R100-341		Various Highways in Region 1	05/21/20	160,110.00	8.75	9.63	9.25
FSAR400-356		FY 20 SIGNAL POLE REPLACEMENT	06/11/20	50.00	17.00	37.00	32.00
		WEIGHTED AVERAGE FOR THE SECOND QUARTER		172,413.00	9.21	10.35	9.52
		WEIGHTED AVERAGE FOR THE YEAR		179,608.00	9.48	10.67	9.76
===== 627-30411		Preform Thermoplastic Pvmt Mkg (XS) (Sp)		Sq Foot	=====		
STR0101-027		SH 10 Overlay La Junta West	02/27/20	134.00	20.00	24.58	19.00
C0402-094		US 40 GRAND COUNTY SIGNAL REP	02/27/20	1,700.00	18.00	16.50	17.00
NH0242-085		US 24 M.P. 291.38 to M.P. 296	02/27/20	1,077.00	11.00	12.08	12.85
STRR300-249		Grand and Jackson Counties AD	03/05/20	1,218.00	20.00	21.33	17.00
NHPP0091-044		SH 9 FRISCO MAIN ST TO IRON S	03/05/20	2,678.00	20.00	16.50	15.00
HPP 0501-067		US 50 AND SH 92 DELTA INTERSE	03/26/20	1,182.00	15.00	10.80	11.20
		WEIGHTED AVERAGE FOR THE FIRST QUARTER		7,989.00	17.62	16.18	14.95
MT CER300-259		MTCE R3 FY20/21 Region Wide S	04/02/20	42,618.00	11.50	13.63	12.25

PROJECT NUMBER	ITEM NUMBER/ PROJECT LOCATION	ITEM DESCRIPTION/ PROJECT LOCATION	DATE LET	UNIT/ QUANTITY	ENGR. EST.	AVERAGE BID	AWARDED BID
=====	627-30411	Preform Thermoplastic Pvmt Mkg (XS) (Sp)		Sq Foot	=====	=====	=====
STR0341-101		SH 34 North of Grandby Resurf	04/02/20	180.00	20.00	25.54	20.00
NHPP0402-098		US 40 CHIP SEAL MP 126 TO MP	05/14/20	613.00	20.00	14.38	12.00
SHE016A-043		SH 21 & 16 SIGNALS PROJECT	06/18/20	3,871.00	10.00	12.86	11.32
	WEIGHTED AVERAGE FOR THE SECOND QUARTER			47,282.00	11.52	13.58	12.20
	WEIGHTED AVERAGE FOR THE YEAR			55,271.00	12.40	14.01	12.60
=====	629-01001	Survey Monument (Ty 1)		Each	=====	=====	=====
NH050A-034		US50A PUEBLO WEST PURCELL INT	03/26/20	12.00	800.00	1113.25	415.00
	WEIGHTED AVERAGE FOR THE FIRST QUARTER			12.00	800.00	1113.25	415.00
STA340A-021		SH340 MP 6-6.76 MESA COUNTY	04/02/20	3.00	400.00	663.33	600.00
	WEIGHTED AVERAGE FOR THE SECOND QUARTER			3.00	400.00	663.33	600.00
	WEIGHTED AVERAGE FOR THE YEAR			15.00	720.00	1074.68	452.00
=====	629-01006	Survey Monument (Ty 6)		Each	=====	=====	=====
STRR300-249		Grand and Jackson Counties AD	03/05/20	5.00	700.00	534.83	195.00
NHPP0091-044		SH 9 FRISCO MAIN ST TO IRON S	03/05/20	17.00	150.00	495.00	590.00
	WEIGHTED AVERAGE FOR THE FIRST QUARTER			22.00	275.00	504.05	500.23
	WEIGHTED AVERAGE FOR THE YEAR			22.00	275.00	504.05	500.23
=====	629-01031	Survey Monument (Ty 3A)		Each	=====	=====	=====
STA0142-066		SH 14 New Raymer West	01/09/20	1.00	800.00	600.62	650.00
NHPP0343-041		I-76 & US 34 FT. MORGAN AREA	01/09/20	16.00	700.00	777.33	1182.00
STA059A-036		SH 59 SEIBERT TO COPE	02/06/20	2.00	750.00	862.50	625.00
	WEIGHTED AVERAGE FOR THE FIRST QUARTER			19.00	710.53	770.79	1095.37
	WEIGHTED AVERAGE FOR THE YEAR			19.00	710.53	770.79	1095.37
=====	629-01065	Survey Monument (Ty 5S)		Each	=====	=====	=====
STRR300-249		Grand and Jackson Counties AD	03/05/20	9.00	750.00	534.83	195.00

PROJECT NUMBER	ITEM NUMBER/ PROJECT LOCATION	ITEM DESCRIPTION/ PROJECT LOCATION	DATE LET	UNIT/ QUANTITY	ENGR. EST.	AVERAGE BID	AWARDED BID
=====	629-01065	Survey Monument (Ty 5S)		Each =====			
CC080-037		VARIOUS ADA RAMPS ALONG NORTH	03/05/20	3.00	750.00	2038.75	900.00
NHPP0091-044		SH 9 FRISCO MAIN ST TO IRON S	03/05/20	26.00	500.00	782.00	590.00
		WEIGHTED AVERAGE FOR THE FIRST QUARTER		38.00	578.95	853.86	520.92
		WEIGHTED AVERAGE FOR THE YEAR		38.00	578.95	853.86	520.92
=====	630-00000	Flagging		Hour =====			
STA0142-066		SH 14 New Raymer West	01/09/20	2,000.00	28.00	33.40	30.60
FSA0253-262		I-25 SB BOTTLENECK I-76 TO I-	01/09/20	100.00	35.00	41.14	40.00
NHPP0253-265		I-25 AT ERIE PARKWAY ON AND O	01/09/20	120.00	28.00	33.17	29.00
SHER500-210		R5 FY19 CENTER LINE RUMBLE ST	01/09/20	650.00	25.00	40.50	29.00
FSA0341-097		US 34 & MACGREGOR INTERSECTIO	01/09/20	80.00	35.00	36.00	36.00
NHPP0343-041		I-76 & US 34 FT. MORGAN AREA	01/09/20	7,408.00	28.00	32.22	30.00
BR0343-040		US 34 REPUBLICAN RIVER BRIDGE	01/16/20	3,500.00	28.00	31.33	26.00
FBR0343-043		US 34 D-28-P STRUCTURE REPLAC					
STA006A-067		SH 6 Merino to Atwood	01/16/20	2,200.00	28.00	31.80	30.00
STR131A-038		SH 131 MP 51.95-55.73, ROUTT	01/16/20	2,800.00	25.00	23.50	27.00
NH 0503-093		US50 WEST OF TEXAS CREEK MP 2	01/23/20	3,000.00	22.00	27.65	27.30
STR012A-050		CULVERT REPAIR I-25 AND US 35	01/30/20	20.00	35.00	33.00	33.00
STR141A-044		SH 141 AND SH 145, FROM SLICK	01/30/20	10,020.00	30.00	25.41	22.00
NHPP 0852-116		US85:HAMPDEN TO FLORIDA-RESUR	02/06/20	2,000.00	32.00	32.50	35.00
STA0703-443		I-70 EJMT TUNNELS PAVING	02/06/20	500.00	35.00	43.30	46.37
ITS0761-231		ITS FIBER AND CAMERAS ON I-76	02/06/20	200.00	30.00	41.78	36.00
NHPP4701-134		C-470 NOISE WALL WEST OF LUCE	02/06/20	600.00	25.00	33.60	40.00
STA059A-036		SH 59 SEIBERT TO COPE	02/06/20	2,140.00	28.00	32.00	31.00
STR116A-001		SH 116 A Surface Treatment Pr	02/13/20	3,125.00	24.00	28.31	28.00
FSA2873-194		US 287 Longmont Intersection	02/13/20	920.00	35.00	33.58	30.00
STA069A-033		SH69 MP 58.7 TO 71.58	02/13/20	2,500.00	25.00	28.78	28.00
STR0101-027		SH 10 Overlay La Junta West	02/27/20	2,700.00	24.00	30.16	30.00
NHPP0702-359		I-70 No Name Tunnel Lighting	02/27/20	2,500.00	30.00	29.85	28.00
C0402-094		US 40 GRAND COUNTY SIGNAL REP	02/27/20	160.00	30.00	25.25	30.50
NH0242-085		US 24 M.P. 291.38 to M.P. 296	02/27/20	1,500.00	28.00	37.13	36.50
NHPP0171-105		SH 17 MP 84.5 to US 285 & SH	03/05/20	15,000.00	30.00	24.16	24.48
C0641-106		SH 64 Meeker West Rural Resur	03/05/20	3,800.00	25.00	28.00	28.00
NHPP145A-080		SH 145 Keystone-Placerville R	03/05/20	1,725.00	25.00	23.00	23.00
STR2871-038		US 287 Passing Lanes Springfi	03/05/20	4,300.00	25.00	39.70	38.61
NHPP0502-082		US 50 MONTROSE RE CHIP SEAL	03/05/20	5,000.00	27.00	24.25	22.00
BR025A-046		K-18-U ON I-25 AT MP112 BRIDG	03/05/20	1,000.00	28.00	27.45	29.80
STRR300-249		Grand and Jackson Counties AD	03/05/20	1,600.00	28.00	26.60	3.00
CC080-037		VARIOUS ADA RAMPS ALONG NORTH	03/05/20	1,600.00	30.00	18.83	3.00
NHPP0091-044		SH 9 FRISCO MAIN ST TO IRON S	03/05/20	7,200.00	30.00	37.27	33.00
NH050A-034		US50A PUEBLO WEST PURCELL INT	03/26/20	4,096.00	24.50	27.62	29.33
HPP 0501-067		US 50 AND SH 92 DELTA INTERSE	03/26/20	6,000.00	27.00	25.58	26.90
SHE 0703-461		I-70 and Kipling North Phase	03/26/20	1,000.00	35.00	33.60	31.00
		WEIGHTED AVERAGE FOR THE FIRST QUARTER		103,064.00	27.84	28.71	27.30

PROJECT NUMBER	ITEM NUMBER/ PROJECT LOCATION	ITEM DESCRIPTION/ PROJECT LOCATION	DATE LET	UNIT/ QUANTITY	ENGR. EST.	AVERAGE BID	AWARDED BID
===== 630-00000		Flagging		Hour	=====		
NHPP1602-169		US 160 WC TUNNEL EAST RESURFA	04/02/20	3,800.00	24.00	25.31	23.82
STR092A-030		SH92 MP 31.748-48.5, DELTA AND	04/02/20	4,000.00	25.00	32.15	29.00
IM0761-226		I76/SH52 Interchange	04/02/20	5,500.00	30.00	32.12	28.62
STA340A-021		SH340 MP 6-6.76 MESA COUNTY	04/02/20	1,260.00	26.00	17.97	2.00
MTCER300-259		MTCE R3 FY20/21 Region Wide S	04/02/20	300.00	15.00	31.00	12.00
STR0341-101		SH 34 North of Grandby Resurf	04/02/20	4,800.00	32.00	37.14	31.00
SHER100-339		WWD TRAFFIC CONTROL ENHANCEME	04/09/20	120.00	35.00	25.00	25.00
NHPP1601-077		US 160 MP 29.750 - MP 34.891	04/09/20	1,600.00	25.00	21.33	15.00
CC0852-106		US-85 LOUVIERS TO MP 191.75	04/23/20	5,000.00	32.00	37.81	38.50
FBR0852-108		US-85 BETWEEN LOUVIERS AND MP					
C1211-090		SH-121 & 29th Ave / SH-121 &	04/23/20	500.00	30.00	35.99	42.00
C1601-082		Hawkins Signal and Curb Ramps	04/30/20	1,500.00	25.00	29.50	22.50
FSA1602-159		US 160 AND SH 17 INTERSECTION	04/30/20	6,000.00	25.00	29.67	28.00
C0853-112		US85 & WCR98 INTERSECTION IMP	05/07/20	200.00	30.00	33.73	40.00
NHPPR100-303		LONG MAST ARM SIGNALS PROJECT	05/07/20	1,000.00	30.00	35.07	35.00
FBR0343-042		US 34 D-27-G STRUCTURE REPLAC	05/07/20	1,500.00	28.00	30.47	30.00
ITS SW02-304		ITS FIBER TO STATE BUILDINGS	05/14/20	500.00	30.00	37.00	37.00
NHPP0402-098		US 40 CHIP SEAL MP 126 TO MP	05/14/20	2,000.00	32.00	30.00	25.00
NHPP0253-276		I-25 EXPRESS LANES SEGMENT 5	05/15/20	500.00	30.00	30.42	30.42
ITS SW02-303		R1: US 285, SH 83 R2: SH 83,	05/28/20	40.00	35.00	56.11	39.00
NH050A-035		US 50A Pueblo Regional Pond	05/28/20	326.00	25.00	29.35	24.00
NH050A-037		US 50A Pueblo Regional Pond					
SHER400-373		R4 Signal Head Backplate Inst	05/28/20	940.00	35.00	45.90	50.00
IM025A-048		Northbound I-25 bridge at Exi	05/28/20	1,500.00	52.00	30.79	30.00
ITSSW01-719		FY 20 ITS CAPITAL REPLACEMENT	06/11/20	100.00	30.00	33.50	35.00
SHE016A-043		SH 21 & 16 SIGNALS PROJECT	06/18/20	70.00	30.00	31.14	31.20
NHPPR100-251		SH 2/ Vasquez	06/25/20	100.00	30.00	33.35	31.70
		WEIGHTED AVERAGE FOR THE SECOND QUARTER		43,156.00	29.06	32.61	28.80
		WEIGHTED AVERAGE FOR THE YEAR		146,220.00	28.20	30.07	27.74
===== 630-00001		Pilot Car Operation		Hour	=====		
STA0142-066		SH 14 New Raymer West	01/09/20	500.00	50.50	88.88	75.00
STA006A-067		SH 6 Merino to Atwood	01/16/20	500.00	50.50	67.60	68.00
NH 0503-093		US50 WEST OF TEXAS CREEK MP 2	01/23/20	1,000.00	50.00	56.26	52.51
STR141A-044		SH 141 AND SH 145, FROM SLICK	01/30/20	1,670.00	50.00	49.22	40.00
STA0703-443		I-70 EJMT TUNNELS PAVING	02/06/20	550.00	65.00	82.95	92.74
NHPP0502-082		US 50 MONTROSE RE CHIP SEAL	03/05/20	1,100.00	60.00	47.50	40.00
		WEIGHTED AVERAGE FOR THE FIRST QUARTER		5,320.00	53.71	56.72	53.73

PROJECT NUMBER	ITEM NUMBER/ PROJECT LOCATION	ITEM DESCRIPTION/ PROJECT LOCATION	DATE LET	UNIT/ QUANTITY	ENGR. EST.	AVERAGE BID	AWARDED BID
=====	630-00001	Pilot Car Operation		Hour	=====	=====	=====
STR092A-030		SH92 MP 31.748-48.5, DELTA AND	04/02/20	880.00	60.00	64.80	59.00
NHPP1601-077		US 160 MP 29.750 - MP 34.891	04/09/20	200.00	45.00	50.00	50.00
NHPP0402-098		US 40 CHIP SEAL MP 126 TO MP	05/14/20	100.00	50.00	82.90	75.00
		WEIGHTED AVERAGE FOR THE SECOND QUARTER		1,180.00	56.61	63.50	58.83
		WEIGHTED AVERAGE FOR THE YEAR		6,500.00	54.24	57.55	54.65
=====	630-00003	Uniformed Traf Ctrl		Hour	=====	=====	=====
FSA0253-262		I-25 SB BOTTLENECK I-76 TO I-	01/09/20	200.00	110.00	95.19	96.00
NHPP 0852-116		US85:HAMPDEN TO FLORIDA-RESUR	02/06/20	150.00	110.00	137.50	150.00
STA0703-443		I-70 EJMT TUNNELS PAVING	02/06/20	1,200.00	100.00	146.67	153.14
FSA2873-194		US 287 Longmont Intersection	02/13/20	16.00	80.00	133.28	116.00
NH0242-085		US 24 M.P. 291.38 to M.P. 296	02/27/20	900.00	104.00	88.67	82.00
HPP 0501-067		US 50 AND SH 92 DELTA INTERSE	03/26/20	128.00	100.00	81.00	84.00
SHE 0703-461		I-70 and Kipling North Phase	03/26/20	400.00	100.00	122.80	99.00
		WEIGHTED AVERAGE FOR THE FIRST QUARTER		2,994.00	102.26	116.01	117.39
IM0252-473		I-25 CABLE BARRIER PHASE IV	04/09/20	1,000.00	100.00	125.50	125.00
SHER100-339		WWD TRAFFIC CONTROL ENHANCEME	04/09/20	200.00	100.00	120.00	120.00
SFTY2254-091		225 Ramp Improvements	04/09/20	32.00	150.00	143.50	137.00
C1211-090		SH-121 & 29th Ave / SH-121 &	04/23/20	96.00	105.50	148.12	187.00
NHPPR100-303		LONG MAST ARM SIGNALS PROJECT	05/07/20	96.00	95.00	131.67	95.00
MTCER200-265		Pueblo	05/28/20	900.00	100.00	91.25	85.00
ITSSW01-719		FY 20 ITS CAPITAL REPLACEMENT	06/11/20	16.00	125.00	128.50	125.00
FSAR400-356		FY 20 SIGNAL POLE REPLACEMENT	06/11/20	24.00	100.00	148.00	165.00
SHE016A-043		SH 21 & 16 SIGNALS PROJECT	06/18/20	120.00	145.00	117.31	115.56
NHPPR100-251		SH 2/ Vasquez	06/25/20	750.00	90.00	124.18	112.36
		WEIGHTED AVERAGE FOR THE SECOND QUARTER		3,234.00	99.98	111.60	111.64
		WEIGHTED AVERAGE FOR THE YEAR		6,228.00	101.08	113.77	114.41
=====	630-00004	Traf Ctrl Vehicle		Each	=====	=====	=====
NHPP 0852-116		US85:HAMPDEN TO FLORIDA-RESUR	02/06/20	1.00	5000.00	3850.00	4200.00
		WEIGHTED AVERAGE FOR THE FIRST QUARTER		1.00	5000.00	3850.00	4200.00

PROJECT NUMBER	ITEM NUMBER/ PROJECT LOCATION	ITEM DESCRIPTION/ PROJECT LOCATION	DATE LET	UNIT/ QUANTITY	ENGR. EST.	AVERAGE BID	AWARDED BID
=====	630-00004	Traf Ctrl Vehicle		Each	=====	=====	=====
C1211-090		SH-121 & 29th Ave / SH-121 &	04/23/20	2.00	3750.00	2199.95	1250.00
		WEIGHTED AVERAGE FOR THE SECOND QUARTER		2.00	3750.00	2199.95	1250.00
		WEIGHTED AVERAGE FOR THE YEAR		3.00	4166.67	2612.46	2233.33
=====	630-00006	Uniformed Traf Ctrl (Vehicle)		Hour	=====	=====	=====
FSA0253-262		I-25 SB BOTTLENECK I-76 TO I-	01/09/20	200.00	47.00	20.38	31.00
SHE 0703-461		I-70 and Kipling North Phase	03/26/20	400.00	18.00	30.20	33.00
		WEIGHTED AVERAGE FOR THE FIRST QUARTER		600.00	27.67	27.93	32.33
SFTY2254-091		225 Ramp Improvements	04/09/20	32.00	150.00	29.50	24.00
		WEIGHTED AVERAGE FOR THE SECOND QUARTER		32.00	150.00	29.50	24.00
		WEIGHTED AVERAGE FOR THE YEAR		632.00	33.86	27.97	31.91
=====	630-00007	Traf Ctrl Inspection		Day	=====	=====	=====
STA0142-066		SH 14 New Raymer West	01/09/20	20.00	202.00	438.50	410.00
FSA0253-262		I-25 SB BOTTLENECK I-76 TO I-	01/09/20	30.00	250.00	598.62	225.00
NHPP0253-265		I-25 AT ERIE PARKWAY ON AND O	01/09/20	8.00	250.00	230.00	185.00
FSA0341-097		US 34 & MACGREGOR INTERSECTIO	01/09/20	12.00	210.00	350.00	350.00
NHPP0343-041		I-76 & US 34 FT. MORGAN AREA	01/09/20	153.00	225.00	421.07	203.00
BR0343-040		US 34 REPUBLICAN RIVER BRIDGE	01/16/20	120.00	240.00	262.21	225.00
FBR0343-043		US 34 D-28-P STRUCTURE REPLAC					
STA006A-067		SH 6 Merino to Atwood	01/16/20	20.00	202.00	227.01	230.00
STR131A-038		SH 131 MP 51.95-55.73, ROUTT	01/16/20	50.00	250.00	307.50	350.00
NH 0503-093		US50 WEST OF TEXAS CREEK MP 2	01/23/20	50.00	150.00	311.27	262.53
STR012A-050		CULVERT REPAIR I-25 AND US 35	01/30/20	20.00	265.00	350.00	350.00
STR141A-044		SH 141 AND SH 145, FROM SLICK	01/30/20	86.00	350.00	180.76	150.00
NHPP 0852-116		US85:HAMPDEN TO FLORIDA-RESUR	02/06/20	58.00	250.00	225.00	250.00
STA0703-443		I-70 EJMT TUNNELS PAVING	02/06/20	80.00	250.00	704.08	993.63
ITS0761-231		ITS FIBER AND CAMERAS ON I-76	02/06/20	5.00	250.00	268.68	240.00
NHPP4701-134		C-470 NOISE WALL WEST OF LUCE	02/06/20	40.00	150.00	169.00	50.00

PROJECT NUMBER	ITEM NUMBER/ PROJECT LOCATION	ITEM DESCRIPTION/ PROJECT LOCATION	DATE LET	UNIT/ QUANTITY	ENGR. EST.	AVERAGE BID	AWARDED BID
=====	630-00007	Traf Ctrl Inspection		Day =====			
STA059A-036		SH 59 SEIBERT TO COPE	02/06/20	92.00	200.00	820.00	820.00
STR116A-001		SH 116 A Surface Treatment Pr	02/13/20	40.00	180.00	208.95	220.00
FSA2873-194		US 287 Longmont Intersection	02/13/20	28.00	230.00	292.67	176.00
STA069A-033		SH69 MP 58.7 TO 71.58	02/13/20	55.00	185.00	189.17	220.00
STR0101-027		SH 10 Overlay La Junta West	02/27/20	36.00	180.00	319.97	340.00
NHPP0702-359		I-70 No Name Tunnel Lighting	02/27/20	120.00	500.00	298.54	53.00
C0402-094		US 40 GRAND COUNTY SIGNAL REP	02/27/20	28.00	250.00	385.00	370.00
NH0242-085		US 24 M.P. 291.38 to M.P. 296	02/27/20	44.00	265.00	532.57	515.00
NHPP0171-105		SH 17 MP 84.5 to US 285 & SH	03/05/20	80.00	300.00	191.30	198.91
C0641-106		SH 64 Meeker West Rural Resur	03/05/20	44.00	250.00	245.00	245.00
NHPP145A-080		SH 145 Keystone-Placerville R	03/05/20	26.00	100.00	90.00	90.00
STR2871-038		US 287 Passing Lanes Springfi	03/05/20	48.00	200.00	706.49	702.00
NHPP0502-082		US 50 MONTROSE RE CHIP SEAL	03/05/20	35.00	300.00	282.50	300.00
BR025A-046		K-18-U ON I-25 AT MP112 BRIDG	03/05/20	102.00	250.00	191.44	227.54
STRR300-249		Grand and Jackson Counties AD	03/05/20	30.00	175.00	339.83	400.00
CC080-037		VARIOUS ADA RAMPS ALONG NORTH	03/05/20	10.00	300.00	181.00	300.00
NHPP0091-044		SH 9 FRISCO MAIN ST TO IRON S	03/05/20	111.00	500.00	358.33	280.00
NH050A-034		US50A PUEBLO WEST PURCELL INT	03/26/20	209.00	200.00	118.95	205.00
HPP 0501-067		US 50 AND SH 92 DELTA INTERSE	03/26/20	91.00	200.00	162.00	168.00
SHE 0703-461		I-70 and Kipling North Phase	03/26/20	80.00	250.00	228.60	132.00
	WEIGHTED AVERAGE FOR THE FIRST QUARTER			2,061.00	259.48	266.77	288.75
NHPP1602-169		US 160 WC TUNNEL EAST RESURFA	04/02/20	32.00	110.00	131.11	108.29
STR092A-030		SH92 MP 31.748-48.5,DELTA AND	04/02/20	18.00	300.00	281.50	210.00
IM0761-226		I76/SH52 Interchange	04/02/20	120.00	200.00	233.72	212.00
STA340A-021		SH340 MP 6-6.76 MESA COUNTY	04/02/20	15.00	200.00	275.00	500.00
STR0341-101		SH 34 North of Grandby Resurf	04/02/20	50.00	400.00	387.46	295.00
IM0252-473		I-25 CABLE BARRIER PHASE IV	04/09/20	48.00	167.00	111.06	111.11
SHER100-339		WWD TRAFFIC CONTROL ENHANCEME	04/09/20	60.00	250.00	190.00	190.00
NHPP1601-077		US 160 MP 29.750 - MP 34.891	04/09/20	25.00	110.00	193.33	145.00
SFTY2254-091		225 Ramp Improvements	04/09/20	50.00	300.00	350.00	322.00
CC0852-106		US-85 LOUVIERS TO MP 191.75	04/23/20	275.00	250.00	220.41	220.00
FBR0852-108		US-85 BETWEEN LOUVIERS AND MP					
C1211-090		SH-121 & 29th Ave / SH-121 &	04/23/20	31.00	203.00	134.99	187.00
C1601-082		Hawkins Signal and Curb Ramps	04/30/20	52.00	120.00	132.00	76.00
FSA1602-159		US 160 AND SH 17 INTERSECTION	04/30/20	44.00	200.00	386.00	113.00
C0853-112		US85 & WCR98 INTERSECTION IMP	05/07/20	26.00	225.00	256.25	225.00
NHPPR100-303		LONG MAST ARM SIGNALS PROJECT	05/07/20	40.00	225.00	175.00	145.00
FBR0343-042		US 34 D-27-G STRUCTURE REPLAC	05/07/20	50.00	240.00	303.13	225.00
ITS SW02-304		ITS FIBER TO STATE BUILDINGS	05/14/20	10.00	250.00	253.75	241.00
NHPP0402-098		US 40 CHIP SEAL MP 126 TO MP	05/14/20	20.00	300.00	374.17	425.00
NHPP0253-276		I-25 EXPRESS LANES SEGMENT 5	05/15/20	152.00	161.00	162.94	162.94
ITS SW02-303		R1: US 285, SH 83 R2: SH 83,	05/28/20	5.00	250.00	472.76	125.00
NH050A-035		US 50A Pueblo Regional Pond	05/28/20	70.00	75.00	121.69	70.00

PROJECT NUMBER	ITEM NUMBER/ PROJECT LOCATION	ITEM DESCRIPTION/ PROJECT LOCATION	DATE LET	UNIT/ QUANTITY	ENGR. EST.	AVERAGE BID	AWARDED BID
===== 630-00007		Traf Ctrl Inspection		Day			
NH050A-037		US 50A Pueblo Regional Pond					
IM025A-048		Northbound I-25 bridge at Exi	05/28/20	30.00	270.00	370.13	360.00
ITSSW01-719		FY 20 ITS CAPITAL REPLACEMENT	06/11/20	5.00	200.00	162.50	50.00
FSAR400-356		FY 20 SIGNAL POLE REPLACEMENT	06/11/20	22.00	200.00	210.33	234.00
SHE016A-043		SH 21 & 16 SIGNALS PROJECT	06/18/20	38.00	200.00	93.93	113.66
NHPPR100-251		SH 2/ Vasquez	06/25/20	25.00	225.00	225.65	204.29
	WEIGHTED AVERAGE FOR THE SECOND QUARTER			1,313.00	213.11	223.65	195.23
	WEIGHTED AVERAGE FOR THE YEAR			3,374.00	241.43	247.97	252.35
===== 630-00012		Traf Ctrl Mgmt		Day			
STA0142-066		SH 14 New Raymer West	01/09/20	51.00	900.00	1249.75	1200.00
FSA0253-262		I-25 SB BOTTLENECK I-76 TO I-	01/09/20	70.00	1250.00	856.96	1000.00
NHPP0253-265		I-25 AT ERIE PARKWAY ON AND O	01/09/20	40.00	875.00	1206.67	1185.00
SHER500-210		R5 FY19 CENTER LINE RUMBLE ST	01/09/20	40.00	800.00	1000.50	1.00
FSA0341-097		US 34 & MACGREGOR INTERSECTIO	01/09/20	60.00	800.00	825.00	825.00
NHPP0343-041		I-76 & US 34 FT. MORGAN AREA	01/09/20	137.00	800.00	1725.66	1128.00
BR0343-040		US 34 REPUBLICAN RIVER BRIDGE	01/16/20	185.00	725.00	891.95	900.00
FBR0343-043		US 34 D-28-P STRUCTURE REPLAC					
STA006A-067		SH 6 Merino to Atwood	01/16/20	50.00	900.00	1135.03	1150.00
STR131A-038		SH 131 MP 51.95-55.73, ROUTT	01/16/20	70.00	800.00	862.50	985.00
NH 0503-093		US50 WEST OF TEXAS CREEK MP 2	01/23/20	110.00	850.00	870.04	840.08
STR012A-050		CULVERT REPAIR I-25 AND US 35	01/30/20	50.00	800.00	825.00	825.00
STR141A-044		SH 141 AND SH 145, FROM SLICK	01/30/20	190.00	1000.00	863.61	750.00
NHPP 0852-116		US85:HAMPDEN TO FLORIDA-RESUR	02/06/20	145.00	1250.00	1300.00	1100.00
STA0703-443		I-70 EJMT TUNNELS PAVING	02/06/20	70.00	1000.00	1619.91	1589.81
ITS0761-231		ITS FIBER AND CAMERAS ON I-76	02/06/20	200.00	725.00	1016.28	960.00
NHPP4701-134		C-470 NOISE WALL WEST OF LUCE	02/06/20	50.00	800.00	974.00	720.00
STA059A-036		SH 59 SEIBERT TO COPE	02/06/20	80.00	925.00	1452.50	1505.00
STR116A-001		SH 116 A Surface Treatment Pr	02/13/20	100.00	730.00	1060.20	1100.00
FSA2873-194		US 287 Longmont Intersection	02/13/20	70.00	900.00	980.00	1100.00
STA069A-033		SH69 MP 58.7 TO 71.58	02/13/20	110.00	815.00	919.45	1100.00
STR0101-027		SH 10 Overlay La Junta West	02/27/20	90.00	730.00	1154.94	1200.00
NHPP0702-359		I-70 No Name Tunnel Lighting	02/27/20	300.00	1000.00	827.18	925.00
C0402-094		US 40 GRAND COUNTY SIGNAL REP	02/27/20	70.00	1000.00	1225.00	1050.00
NH0242-085		US 24 M.P. 291.38 to M.P. 296	02/27/20	90.00	915.00	1928.58	1710.00
NHPP0171-105		SH 17 MP 84.5 to US 285 & SH	03/05/20	230.00	750.00	885.78	882.35
C0641-106		SH 64 Meeker West Rural Resur	03/05/20	111.00	900.00	797.50	700.00
NHPP145A-080		SH 145 Keystone-Placerville R	03/05/20	75.00	725.00	650.00	650.00
STR2871-038		US 287 Passing Lanes Springfi	03/05/20	120.00	950.00	1703.49	1755.00
NHPP0502-082		US 50 MONTROSE RE CHIP SEAL	03/05/20	80.00	1000.00	925.00	850.00
BR025A-046		K-18-U ON I-25 AT MP112 BRIDG	03/05/20	68.00	825.00	1112.23	953.48
STRR300-249		Grand and Jackson Counties AD	03/05/20	75.00	1000.00	1159.84	1400.00
CC080-037		VARIOUS ADA RAMPS ALONG NORTH	03/05/20	25.00	1000.00	760.50	1000.00

PROJECT NUMBER	ITEM NUMBER/ PROJECT LOCATION	ITEM DESCRIPTION/ PROJECT LOCATION	DATE LET	UNIT/ QUANTITY	ENGR. EST.	AVERAGE BID	AWARDED BID
===== 630-00012 Traf Ctrl Mgmt Day =====							
NHPP0091-044		SH 9 FRISCO MAIN ST TO IRON S	03/05/20	250.00	1000.00	1366.67	1200.00
NH050A-034		US50A PUEBLO WEST PURCELL INT	03/26/20	527.00	820.00	644.45	709.00
HPP 0501-067		US 50 AND SH 92 DELTA INTERSE	03/26/20	150.00	800.00	852.00	896.00
SHE 0703-461		I-70 and Kipling North Phase	03/26/20	115.00	1500.00	1127.00	880.00
WEIGHTED AVERAGE FOR THE FIRST QUARTER				4,254.00	898.47	955.79	988.23
NHPP1602-169		US 160 WC TUNNEL EAST RESURFA	04/02/20	70.00	1000.00	1234.74	1611.30
STR092A-030		SH92 MP 31.748-48.5, DELTA AND	04/02/20	50.00	1000.00	1107.50	925.00
IM0761-226		I76/SH52 Interchange	04/02/20	275.00	900.00	881.27	881.82
STA340A-021		SH340 MP 6-6.76 MESA COUNTY	04/02/20	35.00	1000.00	973.33	1400.00
MTCER300-259		MTCE R3 FY20/21 Region Wide S	04/02/20	100.00	200.00	1100.00	200.00
STR0341-101		SH 34 North of Grandby Resurf	04/02/20	108.00	1000.00	1242.54	985.00
IM0252-473		I-25 CABLE BARRIER PHASE IV	04/09/20	120.00	1400.00	1081.95	1138.89
SHER100-339		WWD TRAFFIC CONTROL ENHANCEME	04/09/20	150.00	1000.00	1200.00	1200.00
NHPP1601-077		US 160 MP 29.750 - MP 34.891	04/09/20	25.00	800.00	683.33	600.00
SFTY2254-091		225 Ramp Improvements	04/09/20	100.00	1200.00	1390.00	1455.00
CC0852-106		US-85 LOUVIERS TO MP 191.75	04/23/20	300.00	1200.00	932.08	935.00
FBR0852-108		US-85 BETWEEN LOUVIERS AND MP					
C1211-090		SH-121 & 29th Ave / SH-121 &	04/23/20	85.00	850.00	987.05	1215.00
C1601-082		Hawkins Signal and Curb Ramps	04/30/20	130.00	700.00	736.33	609.00
FSA1602-159		US 160 AND SH 17 INTERSECTION	04/30/20	100.00	800.00	1159.00	838.00
C0853-112		US85 & WCR98 INTERSECTION IMP	05/07/20	65.00	750.00	895.63	750.00
NHPPR100-303		LONG MAST ARM SIGNALS PROJECT	05/07/20	120.00	900.00	1108.33	1240.00
FBR0343-042		US 34 D-27-G STRUCTURE REPLAC	05/07/20	95.00	900.00	1023.08	975.00
ITS SW02-304		ITS FIBER TO STATE BUILDINGS	05/14/20	150.00	850.00	894.50	1055.00
NHPP0402-098		US 40 CHIP SEAL MP 126 TO MP	05/14/20	34.00	900.00	1255.00	1200.00
ITS SW02-303		R1: US 285, SH 83 R2: SH 83,	05/28/20	180.00	1500.00	1072.75	250.00
MTCER200-265		Pueblo	05/28/20	30.00	825.00	282.50	200.00
NH050A-035		US 50A Pueblo Regional Pond	05/28/20	106.00	550.00	528.50	353.00
NH050A-037		US 50A Pueblo Regional Pond					
SHER400-373		R4 Signal Head Backplate Inst	05/28/20	90.00	1385.00	1491.00	1530.00
IM025A-048		Northbound I-25 bridge at Exi	05/28/20	61.00	1000.00	814.83	820.00
ITSSW01-719		FY 20 ITS CAPITAL REPLACEMENT	06/11/20	115.00	1250.00	511.50	275.00
FSAR400-356		FY 20 SIGNAL POLE REPLACEMENT	06/11/20	55.00	800.00	750.67	759.00
SHE016A-043		SH 21 & 16 SIGNALS PROJECT	06/18/20	95.00	1200.00	642.63	683.14
NHPPR100-251		SH 2/ Vasquez	06/25/20	59.00	850.00	1104.33	1037.66
WEIGHTED AVERAGE FOR THE SECOND QUARTER				2,903.00	993.01	930.86	883.81
WEIGHTED AVERAGE FOR THE YEAR				7,157.00	936.82	944.98	945.88

===== 630-00015 Uniformed Traf Ctrl Coordination Hour =====							
NHPP0343-041		I-76 & US 34 FT. MORGAN AREA	01/09/20	8.00	48.00	79.33	56.00

COLORADO DEPARTMENT OF TRANSPORTATION
 ITEM UNIT COSTS BY PROJECTS -- 2020 COST DATA

10:58 Friday, October 2, 2020 327

PROJECT NUMBER	ITEM NUMBER/ PROJECT LOCATION	ITEM DESCRIPTION/ PROJECT LOCATION	DATE LET	UNIT/ QUANTITY	ENGR. EST.	AVERAGE BID	AWARDED BID
=====	630-00015	Uniformed Traf Ctrl Coordination		Hour =====			
FSA2873-194		US 287 Longmont Intersection	02/13/20	1.00	1000.00	120.00	330.00
NH050A-034		US50A PUEBLO WEST PURCELL INT	03/26/20	80.00	40.00	35.40	88.56
		WEIGHTED AVERAGE FOR THE FIRST QUARTER		89.00	51.51	37.73	88.35
IM0761-226		I76/SH52 Interchange	04/02/20	8.00	50.00	47.40	53.00
MTCER200-265		Pueblo	05/28/20	75.00	50.00	33.75	20.00
FSAR400-356		FY 20 SIGNAL POLE REPLACEMENT	06/11/20	2.00	80.00	59.33	65.00
SHE016A-043		SH 21 & 16 SIGNALS PROJECT	06/18/20	9.00	40.00	53.78	28.88
		WEIGHTED AVERAGE FOR THE SECOND QUARTER		94.00	49.68	38.22	24.62
		WEIGHTED AVERAGE FOR THE YEAR		183.00	50.57	37.92	55.61
=====	630-00017	Traffic Control Management (Special)		Day =====			
NHPP0253-276		I-25 EXPRESS LANES SEGMENT 5	05/15/20	30.00	749.00	760.41	760.41
		WEIGHTED AVERAGE FOR THE SECOND QUARTER		30.00	749.00	760.41	760.41
		WEIGHTED AVERAGE FOR THE YEAR		30.00	749.00	760.41	760.41
=====	630-00031	Courtesy Patrol		Hour =====			
NH0242-085		US 24 M.P. 291.38 to M.P. 296	02/27/20	400.00	125.00	236.26	280.00
		WEIGHTED AVERAGE FOR THE FIRST QUARTER		400.00	125.00	236.26	280.00
		WEIGHTED AVERAGE FOR THE YEAR		400.00	125.00	236.26	280.00
=====	630-00040	Develop Traf Incident Mgmt Plan		LUMP SUM =====			
NH0242-085		US 24 M.P. 291.38 to M.P. 296	02/27/20	1.00	500.00	7611.10	3995.00
		WEIGHTED AVERAGE FOR THE FIRST QUARTER		1.00	500.00	7611.10	3995.00
		WEIGHTED AVERAGE FOR THE YEAR		1.00	500.00	7611.10	3995.00
=====	630-00041	Implement Traf Incident Mgmt Plan		Month =====			
NH0242-085		US 24 M.P. 291.38 to M.P. 296	02/27/20	5.00	300.00	2269.86	2850.00
		WEIGHTED AVERAGE FOR THE FIRST QUARTER		5.00	300.00	2269.86	2850.00
		WEIGHTED AVERAGE FOR THE YEAR		5.00	300.00	2269.86	2850.00

COLORADO DEPARTMENT OF TRANSPORTATION
 ITEM UNIT COSTS BY PROJECTS -- 2020 COST DATA

10:58 Friday, October 2, 2020 328

PROJECT NUMBER	ITEM NUMBER/ PROJECT LOCATION	ITEM DESCRIPTION/ PROJECT LOCATION	DATE LET	UNIT/ QUANTITY	ENGR. EST.	AVERAGE BID	AWARDED BID
===== 630-80001		Flash Beacon (Port)		Each =====			
STA0142-066		SH 14 New Raymer West	01/09/20	2.00	1200.00	1028.25	1025.00
NHPP0343-041		I-76 & US 34 FT. MORGAN AREA	01/09/20	33.00	865.00	982.47	677.00
BR0343-040		US 34 REPUBLICAN RIVER BRIDGE	01/16/20	24.00	1000.00	997.02	1000.00
FBR0343-043		US 34 D-28-P STRUCTURE REPLAC					
STA006A-067		SH 6 Merino to Atwood	01/16/20	2.00	1200.00	686.02	700.00
STR131A-038		SH 131 MP 51.95-55.73, ROUTT	01/16/20	2.00	1500.00	1200.00	900.00
NHPP 0852-116		US85:HAMPDEN TO FLORIDA-RESUR	02/06/20	16.00	1200.00	1650.00	1800.00
STA0703-443		I-70 EJMT TUNNELS PAVING	02/06/20	12.00	1250.00	708.15	1324.85
STA059A-036		SH 59 SEIBERT TO COPE	02/06/20	4.00	850.00	1200.00	1000.00
STR116A-001		SH 116 A Surface Treatment Pr	02/13/20	4.00	650.00	1940.21	2000.00
STA069A-033		SH69 MP 58.7 TO 71.58	02/13/20	10.00	650.00	1263.90	2000.00
STR0101-027		SH 10 Overlay La Junta West	02/27/20	3.00	650.00	3075.43	4000.00
NH0242-085		US 24 M.P. 291.38 to M.P. 296	02/27/20	10.00	640.00	1396.87	1370.00
C0641-106		SH 64 Meeker West Rural Resur	03/05/20	2.00	1500.00	3000.00	3500.00
STR2871-038		US 287 Passing Lanes Springfi	03/05/20	8.00	650.00	1213.25	2340.00
NHPP0091-044		SH 9 FRISCO MAIN ST TO IRON S	03/05/20	6.00	500.00	1166.67	970.00
HPP 0501-067		US 50 AND SH 92 DELTA INTERSE	03/26/20	10.00	900.00	872.00	896.00
		WEIGHTED AVERAGE FOR THE FIRST QUARTER		148.00	916.18	1159.29	1314.12
STR0341-101		SH 34 North of Grandby Resurf	04/02/20	6.00	1500.00	1255.44	1800.00
IM0252-473		I-25 CABLE BARRIER PHASE IV	04/09/20	10.00	900.00	111.06	111.11
SFTY2254-091		225 Ramp Improvements	04/09/20	16.00	750.00	1192.50	1285.00
CC0852-106		US-85 LOUVIERS TO MP 191.75	04/23/20	8.00	1200.00	1016.59	880.00
FBR0852-108		US-85 BETWEEN LOUVIERS AND MP					
C0853-112		US85 & WCR98 INTERSECTION IMP	05/07/20	4.00	200.00	529.75	560.00
NHPPR100-303		LONG MAST ARM SIGNALS PROJECT	05/07/20	8.00	1200.00	945.00	310.00
FBR0343-042		US 34 D-27-G STRUCTURE REPLAC	05/07/20	8.00	1000.00	1133.98	1690.00
NHPP0402-098		US 40 CHIP SEAL MP 126 TO MP	05/14/20	2.00	500.00	1588.33	2000.00
NHPP0253-276		I-25 EXPRESS LANES SEGMENT 5	05/15/20	2.00	642.00	651.78	651.78
		WEIGHTED AVERAGE FOR THE SECOND QUARTER		64.00	941.94	969.88	985.23
		WEIGHTED AVERAGE FOR THE YEAR		212.00	923.96	1087.48	1214.83
===== 630-80002		Flash Beacon (Solar)		Each =====			
FSA0341-097		US 34 & MACGREGOR INTERSECTIO	01/09/20	4.00	750.00	650.00	650.00
NH 0503-093		US50 WEST OF TEXAS CREEK MP 2	01/23/20	4.00	700.00	1125.06	1050.11
BR025A-046		K-18-U ON I-25 AT MP112 BRIDG	03/05/20	18.00	850.00	602.49	1080.80
NH050A-034		US50A PUEBLO WEST PURCELL INT	03/26/20	33.00	850.00	1009.92	1107.00
		WEIGHTED AVERAGE FOR THE FIRST QUARTER		59.00	833.05	880.93	1064.17

COLORADO DEPARTMENT OF TRANSPORTATION
ITEM UNIT COSTS BY PROJECTS -- 2020 COST DATA

10:58 Friday, October 2, 2020 329

PROJECT NUMBER	ITEM NUMBER/ PROJECT LOCATION	ITEM DESCRIPTION/ PROJECT LOCATION	DATE LET	UNIT/ QUANTITY	ENGR. EST.	AVERAGE BID	AWARDED BID
=====	630-80002	Flash Beacon (Solar)		Each	=====	=====	=====
SHER100-339		WWD TRAFFIC CONTROL ENHANCEME	04/09/20	42.00	1200.00	200.00	200.00
NHPPR100-251		SH 2/ Vasquez	06/25/20	6.00	100.00	532.38	509.75
		WEIGHTED AVERAGE FOR THE SECOND QUARTER		48.00	1062.50	273.86	238.72
		WEIGHTED AVERAGE FOR THE YEAR		107.00	935.98	809.04	693.87
=====	630-80305	Flagging Station Light		Each	=====	=====	=====
FSA2873-194		US 287 Longmont Intersection	02/13/20	2.00	1000.00	2298.33	990.00
		WEIGHTED AVERAGE FOR THE FIRST QUARTER		2.00	1000.00	2298.33	990.00
SHER400-373		R4 Signal Head Backplate Inst	05/28/20	2.00	2855.00	5812.50	9125.00
		WEIGHTED AVERAGE FOR THE SECOND QUARTER		2.00	2855.00	5812.50	9125.00
		WEIGHTED AVERAGE FOR THE YEAR		4.00	1927.50	3176.88	5057.50
=====	630-80331	Barricade (3 F-A) (Temp)		Each	=====	=====	=====
FSA1602-159		US 160 AND SH 17 INTERSECTION	04/30/20	4.00	175.00	234.67	322.00
		WEIGHTED AVERAGE FOR THE SECOND QUARTER		4.00	175.00	234.67	322.00
		WEIGHTED AVERAGE FOR THE YEAR		4.00	175.00	234.67	322.00
=====	630-80335	Barricade (3 M-A) (Temp)		Each	=====	=====	=====
FSA0253-262		I-25 SB BOTTLENECK I-76 TO I-	01/09/20	3.00	150.00	104.03	250.00
NHPP0343-041		I-76 & US 34 FT. MORGAN AREA	01/09/20	31.00	168.42	259.05	169.00
NHPP 0852-116		US85:HAMPDEN TO FLORIDA-RESUR	02/06/20	8.00	130.00	225.00	250.00
NHPP4701-134		C-470 NOISE WALL WEST OF LUCE	02/06/20	3.00	200.00	156.00	60.00
FSA2873-194		US 287 Longmont Intersection	02/13/20	3.00	1500.00	253.00	83.00
NHPP0702-359		I-70 No Name Tunnel Lighting	02/27/20	2.00	825.00	299.25	160.00

PROJECT NUMBER	ITEM NUMBER/ PROJECT LOCATION	ITEM DESCRIPTION/ PROJECT LOCATION	DATE LET	UNIT/ QUANTITY	ENGR. EST.	AVERAGE BID	AWARDED BID
===== 630-80335							
		Barricade (3 M-A) (Temp)		Each			
C0402-094		US 40 GRAND COUNTY SIGNAL REP	02/27/20	4.00	150.00	330.00	160.00
STRR300-249		Grand and Jackson Counties AD	03/05/20	8.00	200.00	195.00	200.00
CC080-037		VARIOUS ADA RAMPS ALONG NORTH	03/05/20	8.00	200.00	154.38	20.00
NHPP0091-044		SH 9 FRISCO MAIN ST TO IRON S	03/05/20	2.00	200.00	436.17	180.00
NH050A-034		US50A PUEBLO WEST PURCELL INT	03/26/20	10.00	200.00	184.99	277.00
HPP 0501-067		US 50 AND SH 92 DELTA INTERSE	03/26/20	2.00	150.00	218.00	224.00
SHE 0703-461		I-70 and Kipling North Phase	03/26/20	2.00	165.00	367.40	880.00
		WEIGHTED AVERAGE FOR THE FIRST QUARTER		86.00	235.94	223.34	191.58
STR0341-101		SH 34 North of Grandby Resurf	04/02/20	2.00	300.00	478.35	350.00
SHER100-339		WWD TRAFFIC CONTROL ENHANCEME	04/09/20	9.00	200.00	200.00	200.00
SFTY2254-091		225 Ramp Improvements	04/09/20	8.00	175.00	217.50	120.00
C1211-090		SH-121 & 29th Ave / SH-121 &	04/23/20	10.00	180.00	57.88	32.00
C0853-112		US85 & WCR98 INTERSECTION IMP	05/07/20	2.00	100.00	86.75	90.00
NHPPR100-303		LONG MAST ARM SIGNALS PROJECT	05/07/20	8.00	150.00	190.00	125.00
NH050A-035		US 50A Pueblo Regional Pond	05/28/20	2.00	175.00	110.84	66.00
NH050A-037		US 50A Pueblo Regional Pond					
NHPPR100-251		SH 2/ Vasquez	06/25/20	6.00	175.00	88.48	84.95
		WEIGHTED AVERAGE FOR THE SECOND QUARTER		47.00	178.72	149.82	119.19
		WEIGHTED AVERAGE FOR THE YEAR		133.00	215.72	202.12	166.00
===== 630-80336							
		Barricade (3 M-B) (Temp)		Each			
ITS0761-231		ITS FIBER AND CAMERAS ON I-76	02/06/20	2.00	250.00	182.20	240.00
NH0242-085		US 24 M.P. 291.38 to M.P. 296	02/27/20	4.00	235.00	1030.15	1025.00
STR2871-038		US 287 Passing Lanes Springfi	03/05/20	16.00	250.00	526.08	994.50
HPP 0501-067		US 50 AND SH 92 DELTA INTERSE	03/26/20	4.00	220.00	436.00	448.00
		WEIGHTED AVERAGE FOR THE FIRST QUARTER		26.00	243.08	556.55	857.08
IM0761-226		I76/SH52 Interchange	04/02/20	20.00	200.00	210.22	132.50
CC0852-106		US-85 LOUVIERS TO MP 191.75	04/23/20	16.00	230.00	82.05	44.00
FBR0852-108		US-85 BETWEEN LOUVIERS AND MP					
FSA1602-159		US 160 AND SH 17 INTERSECTION	04/30/20	12.00	200.00	241.00	215.00
C0853-112		US85 & WCR98 INTERSECTION IMP	05/07/20	2.00	200.00	163.94	160.00
ITS SW02-304		ITS FIBER TO STATE BUILDINGS	05/14/20	2.00	250.00	261.25	241.00
NHPP0402-098		US 40 CHIP SEAL MP 126 TO MP	05/14/20	2.00	315.00	439.50	500.00

PROJECT NUMBER	ITEM NUMBER/ PROJECT LOCATION	ITEM DESCRIPTION/ PROJECT LOCATION	DATE LET	UNIT/ QUANTITY	ENGR. EST.	AVERAGE BID	AWARDED BID
=====	630-80336	Barricade (3 M-B) (Temp)		Each =====			
NHPP0253-276		I-25 EXPRESS LANES SEGMENT 5	05/15/20	2.00	214.00	217.26	217.26
		WEIGHTED AVERAGE FOR THE SECOND QUARTER		56.00	214.96	167.84	145.90
		WEIGHTED AVERAGE FOR THE YEAR		82.00	223.88	228.39	371.40
=====	630-80337	Barricade (3 M-C) (Temp)		Each =====			
FSA0341-097		US 34 & MACGREGOR INTERSECTIO	01/09/20	18.00	250.00	220.00	220.00
BR0343-040		US 34 REPUBLICAN RIVER BRIDGE	01/16/20	10.00	235.00	166.52	125.00
FBR0343-043		US 34 D-28-P STRUCTURE REPLAC					
STA0703-443		I-70 EJMT TUNNELS PAVING	02/06/20	3.00	750.00	409.65	794.91
HPP 0501-067		US 50 AND SH 92 DELTA INTERSE	03/26/20	4.00	240.00	654.00	672.00
		WEIGHTED AVERAGE FOR THE FIRST QUARTER		35.00	287.43	235.23	293.79
FBR0343-042		US 34 D-27-G STRUCTURE REPLAC	05/07/20	1.00	235.00	247.77	225.00
NHPP0253-276		I-25 EXPRESS LANES SEGMENT 5	05/15/20	2.00	321.00	325.89	325.89
		WEIGHTED AVERAGE FOR THE SECOND QUARTER		3.00	292.33	261.98	292.26
		WEIGHTED AVERAGE FOR THE YEAR		38.00	287.82	238.09	293.67
=====	630-80338	Barricade (3 M-D) (Temp)		Each =====			
STA059A-036		SH 59 SEIBERT TO COPE	02/06/20	4.00	400.00	835.00	770.00
BR025A-046		K-18-U ON I-25 AT MP112 BRIDG	03/05/20	2.00	450.00	335.04	398.19
HPP 0501-067		US 50 AND SH 92 DELTA INTERSE	03/26/20	2.00	260.00	777.00	784.00
		WEIGHTED AVERAGE FOR THE FIRST QUARTER		8.00	377.50	556.87	680.55
FBR0343-042		US 34 D-27-G STRUCTURE REPLAC	05/07/20	2.00	250.00	297.60	225.00
		WEIGHTED AVERAGE FOR THE SECOND QUARTER		2.00	250.00	297.60	225.00
		WEIGHTED AVERAGE FOR THE YEAR		10.00	352.00	450.80	589.44
=====	630-80340	Pedestrian Barricade (ADA)		Lin Foot =====			
STRR300-249		Grand and Jackson Counties AD	03/05/20	400.00	45.00	56.33	60.00

PROJECT NUMBER	ITEM NUMBER/ PROJECT LOCATION	ITEM DESCRIPTION/ PROJECT LOCATION	DATE LET	UNIT/ QUANTITY	ENGR. EST.	AVERAGE BID	AWARDED BID
=====	630-80340	Pedestrian Barricade (ADA)		Lin Foot	=====	=====	=====
CC080-037		VARIOUS ADA RAMPS ALONG NORTH	03/05/20	400.00	50.00	48.75	40.00
NHPP0091-044		SH 9 FRISCO MAIN ST TO IRON S	03/05/20	40.00	100.00	55.90	36.00
HPP 0501-067		US 50 AND SH 92 DELTA INTERSE	03/26/20	50.00	50.00	54.50	56.00
		WEIGHTED AVERAGE FOR THE FIRST QUARTER		890.00	50.00	52.24	49.71
C1601-082		Hawkins Signal and Curb Ramps	04/30/20	200.00	30.00	45.33	36.00
FSA1602-159		US 160 AND SH 17 INTERSECTION	04/30/20	150.00	100.00	36.33	32.00
NHPPR100-303		LONG MAST ARM SIGNALS PROJECT	05/07/20	80.00	50.00	58.33	22.00
NHPP0402-098		US 40 CHIP SEAL MP 126 TO MP	05/14/20	30.00	80.00	80.23	77.00
		WEIGHTED AVERAGE FOR THE SECOND QUARTER		460.00	59.57	46.94	34.93
		WEIGHTED AVERAGE FOR THE YEAR		1,350.00	53.26	50.57	44.67
=====	630-80341	Const Traf Sign (A)		Each	=====	=====	=====
STA0142-066		SH 14 New Raymer West	01/09/20	60.00	90.50	73.38	66.50
FSA0253-262		I-25 SB BOTTLENECK I-76 TO I-	01/09/20	25.00	75.00	48.26	85.00
NHPP0253-265		I-25 AT ERIE PARKWAY ON AND O	01/09/20	36.00	55.00	45.33	37.00
SHER500-210		R5 FY19 CENTER LINE RUMBLE ST	01/09/20	12.00	25.00	88.13	26.25
FSA0341-097		US 34 & MACGREGOR INTERSECTIO	01/09/20	20.00	65.00	60.00	60.00
NHPP0343-041		I-76 & US 34 FT. MORGAN AREA	01/09/20	622.00	50.00	89.01	90.00
BR0343-040		US 34 REPUBLICAN RIVER BRIDGE	01/16/20	86.00	65.00	66.67	65.00
FBR0343-043		US 34 D-28-P STRUCTURE REPLAC					
STA006A-067		SH 6 Merino to Atwood	01/16/20	56.00	75.00	39.60	40.00
STR131A-038		SH 131 MP 51.95-55.73, ROUTT	01/16/20	14.00	25.00	40.00	40.00
NH 0503-093		US50 WEST OF TEXAS CREEK MP 2	01/23/20	50.00	50.00	56.26	52.51
STR012A-050		CULVERT REPAIR I-25 AND US 35	01/30/20	20.00	50.00	40.00	40.00
STR141A-044		SH 141 AND SH 145, FROM SLICK	01/30/20	15.00	45.00	25.69	21.00
NHPP 0852-116		US85:HAMPDEN TO FLORIDA-RESUR	02/06/20	58.00	77.00	62.50	70.00
STA0703-443		I-70 EJMT TUNNELS PAVING	02/06/20	8.00	70.00	67.97	99.36
ITS0761-231		ITS FIBER AND CAMERAS ON I-76	02/06/20	18.00	50.00	62.29	66.00
NHPP4701-134		C-470 NOISE WALL WEST OF LUCE	02/06/20	22.00	50.00	68.00	50.00
STA059A-036		SH 59 SEIBERT TO COPE	02/06/20	24.00	55.00	86.00	82.00
STR116A-001		SH 116 A Surface Treatment Pr	02/13/20	4.00	35.00	22.47	24.00
FSA2873-194		US 287 Longmont Intersection	02/13/20	7.00	50.00	61.14	50.00
STA069A-033		SH69 MP 58.7 TO 71.58	02/13/20	30.00	51.00	38.89	25.00
STR0101-027		SH 10 Overlay La Junta West	02/27/20	15.00	35.00	32.51	35.00
NHPP0702-359		I-70 No Name Tunnel Lighting	02/27/20	4.00	76.00	129.63	16.00
CO402-094		US 40 GRAND COUNTY SIGNAL REP	02/27/20	24.00	50.00	18.30	31.60
NH0242-085		US 24 M.P. 291.38 to M.P. 296	02/27/20	30.00	43.00	75.37	74.15
NHPP0171-105		SH 17 MP 84.5 to US 285 & SH	03/05/20	113.00	20.00	41.20	30.60

PROJECT NUMBER	ITEM NUMBER/ PROJECT LOCATION	ITEM DESCRIPTION/ PROJECT LOCATION	DATE LET	UNIT/ QUANTITY	ENGR. EST.	AVERAGE BID	AWARDED BID
=====	630-80341	Const Traf Sign (A)		Each =====			
C0641-106		SH 64 Meeker West Rural Resur	03/05/20	12.00	25.00	32.50	35.00
NHPP145A-080		SH 145 Keystone-Placerville R	03/05/20	57.00	35.00	35.00	35.00
STR2871-038		US 287 Passing Lanes Springfi	03/05/20	28.00	35.00	46.55	58.50
NHPP0502-082		US 50 MONTROSE RE CHIP SEAL	03/05/20	40.00	50.00	23.75	20.00
BR025A-046		K-18-U ON I-25 AT MP112 BRIDG	03/05/20	30.00	45.00	52.03	56.89
STRR300-249		Grand and Jackson Counties AD	03/05/20	84.00	50.00	29.33	5.00
CC080-037		VARIOUS ADA RAMPS ALONG NORTH	03/05/20	84.00	50.00	19.94	5.00
NHPP0091-044		SH 9 FRISCO MAIN ST TO IRON S	03/05/20	82.00	30.00	74.90	36.00
NH050A-034		US50A PUEBLO WEST PURCELL INT	03/26/20	59.00	50.00	76.64	111.00
HPP 0501-067		US 50 AND SH 92 DELTA INTERSE	03/26/20	157.00	55.00	21.80	22.40
SHE 0703-461		I-70 and Kipling North Phase	03/26/20	48.00	65.00	79.60	61.00
		WEIGHTED AVERAGE FOR THE FIRST QUARTER		2,054.00	50.84	62.96	57.33
NHPP1602-169		US 160 WC TUNNEL EAST RESURFA	04/02/20	66.00	40.00	29.89	37.90
STR092A-030		SH92 MP 31.748-48.5,DELTA AND	04/02/20	130.00	50.00	33.90	32.50
IM0761-226		I76/SH52 Interchange	04/02/20	54.00	50.00	90.71	74.20
STA340A-021		SH340 MP 6-6.76 MESA COUNTY	04/02/20	50.00	50.00	23.33	5.00
MTCER300-259		MTCE R3 FY20/21 Region Wide S	04/02/20	21.00	10.00	52.50	5.00
STR0341-101		SH 34 North of Grandby Resurf	04/02/20	12.00	60.00	47.05	40.00
IM0252-473		I-25 CABLE BARRIER PHASE IV	04/09/20	6.00	43.00	33.67	33.33
SHER100-339		WWD TRAFFIC CONTROL ENHANCEME	04/09/20	24.00	75.00	50.00	50.00
NHPP1601-077		US 160 MP 29.750 - MP 34.891	04/09/20	10.00	40.00	28.33	22.00
SFTY2254-091		225 Ramp Improvements	04/09/20	12.00	45.00	85.00	60.00
CC0852-106		US-85 LOUVIERS TO MP 191.75	04/23/20	78.00	75.00	54.46	44.00
FBR0852-108		US-85 BETWEEN LOUVIERS AND MP					
C1211-090		SH-121 & 29th Ave / SH-121 &	04/23/20	20.00	55.00	50.18	32.00
C1601-082		Hawkins Signal and Curb Ramps	04/30/20	112.00	35.00	47.83	43.50
FSA1602-159		US 160 AND SH 17 INTERSECTION	04/30/20	70.00	45.00	44.67	32.00
C0853-112		US85 & WCR98 INTERSECTION IMP	05/07/20	50.00	20.00	47.44	51.00
NHPPR100-303		LONG MAST ARM SIGNALS PROJECT	05/07/20	32.00	50.00	62.00	50.00
FBR0343-042		US 34 D-27-G STRUCTURE REPLAC	05/07/20	13.00	65.00	79.58	80.00
ITS SW02-304		ITS FIBER TO STATE BUILDINGS	05/14/20	8.00	50.00	90.50	67.00
NHPP0402-098		US 40 CHIP SEAL MP 126 TO MP	05/14/20	12.00	30.00	69.72	66.00
NHPP0253-276		I-25 EXPRESS LANES SEGMENT 5	05/15/20	12.00	86.00	86.91	86.91
ITS SW02-303		R1: US 285, SH 83 R2: SH 83,	05/28/20	24.00	71.00	146.76	50.00
MTCER200-265		Pueblo	05/28/20	16.00	50.00	80.00	10.00
NH050A-035		US 50A Pueblo Regional Pond	05/28/20	18.00	65.00	49.58	36.00
NH050A-037		US 50A Pueblo Regional Pond					
SHER400-373		R4 Signal Head Backplate Inst	05/28/20	50.00	70.00	66.25	50.00
IM025A-048		Northbound I-25 bridge at Exi	05/28/20	4.00	51.00	48.33	45.00
ITSSW01-719		FY 20 ITS CAPITAL REPLACEMENT	06/11/20	8.00	31.00	97.00	100.00
FSAR400-356		FY 20 SIGNAL POLE REPLACEMENT	06/11/20	30.00	50.00	59.33	65.00
SHE016A-043		SH 21 & 16 SIGNALS PROJECT	06/18/20	36.00	50.00	61.36	57.78
NHPPR100-251		SH 2/ Vasquez	06/25/20	66.00	60.00	47.15	45.30
		WEIGHTED AVERAGE FOR THE SECOND QUARTER		1,044.00	50.20	57.22	43.26
		WEIGHTED AVERAGE FOR THE YEAR		3,098.00	50.63	60.81	52.59

PROJECT NUMBER	ITEM NUMBER/ PROJECT LOCATION	ITEM DESCRIPTION/ PROJECT LOCATION	DATE LET	UNIT/ QUANTITY	ENGR. EST.	AVERAGE BID	AWARDED BID
===== 630-80342		Const Traf Sign (B)		Each =====			
STA0142-066		SH 14 New Raymer West	01/09/20	94.00	101.00	82.75	76.00
FSA0253-262		I-25 SB BOTTLENECK I-76 TO I-	01/09/20	27.00	100.00	90.70	200.00
NHPP0253-265		I-25 AT ERIE PARKWAY ON AND O	01/09/20	8.00	65.00	65.33	65.00
SHER500-210		R5 FY19 CENTER LINE RUMBLE ST	01/09/20	26.00	30.00	88.13	26.25
FSA0341-097		US 34 & MACGREGOR INTERSECTIO	01/09/20	30.00	65.00	90.00	90.00
NHPP0343-041		I-76 & US 34 FT. MORGAN AREA	01/09/20	81.00	65.00	103.41	113.00
BR0343-040		US 34 REPUBLICAN RIVER BRIDGE	01/16/20	12.00	75.00	157.45	250.00
FBR0343-043		US 34 D-28-P STRUCTURE REPLAC					
STA006A-067		SH 6 Merino to Atwood	01/16/20	106.00	90.00	57.00	58.00
STR131A-038		SH 131 MP 51.95-55.73, ROUTT	01/16/20	49.00	30.00	40.00	40.00
NH 0503-093		US50 WEST OF TEXAS CREEK MP 2	01/23/20	27.00	55.00	64.01	63.01
STR012A-050		CULVERT REPAIR I-25 AND US 35	01/30/20	12.00	75.00	50.00	50.00
STR141A-044		SH 141 AND SH 145, FROM SLICK	01/30/20	62.00	40.00	33.93	31.00
NHPP 0852-116		US85:HAMPDEN TO FLORIDA-RESUR	02/06/20	76.00	110.00	227.50	250.00
STA0703-443		I-70 EJMT TUNNELS PAVING	02/06/20	46.00	100.00	71.29	105.99
ITS0761-231		ITS FIBER AND CAMERAS ON I-76	02/06/20	30.00	70.00	112.09	246.00
NHPP4701-134		C-470 NOISE WALL WEST OF LUCE	02/06/20	19.00	50.00	110.80	80.00
STA059A-036		SH 59 SEIBERT TO COPE	02/06/20	98.00	65.00	93.50	87.00
STR116A-001		SH 116 A Surface Treatment Pr	02/13/20	28.00	40.00	32.71	34.00
FSA2873-194		US 287 Longmont Intersection	02/13/20	37.00	60.00	88.17	72.00
STA069A-033		SH69 MP 58.7 TO 71.58	02/13/20	42.00	55.00	43.89	35.00
STR0101-027		SH 10 Overlay La Junta West	02/27/20	89.00	40.00	53.18	55.00
NHPP0702-359		I-70 No Name Tunnel Lighting	02/27/20	47.00	71.00	138.38	16.00
C0402-094		US 40 GRAND COUNTY SIGNAL REP	02/27/20	62.00	60.00	18.30	31.60
NH0242-085		US 24 M.P. 291.38 to M.P. 296	02/27/20	103.00	72.00	86.45	85.55
NHPP0171-105		SH 17 MP 84.5 to US 285 & SH	03/05/20	33.00	20.00	52.00	51.00
C0641-106		SH 64 Meeker West Rural Resur	03/05/20	57.00	30.00	40.00	40.00
NHPP145A-080		SH 145 Keystone-Placerville R	03/05/20	8.00	35.00	35.00	35.00
STR2871-038		US 287 Passing Lanes Springfi	03/05/20	94.00	40.00	52.40	70.20
NHPP0502-082		US 50 MONTROSE RE CHIP SEAL	03/05/20	177.00	60.00	35.00	30.00
BR025A-046		K-18-U ON I-25 AT MP112 BRIDG	03/05/20	66.00	75.00	62.53	68.27
STRR300-249		Grand and Jackson Counties AD	03/05/20	24.00	55.00	36.33	5.00
CC080-037		VARIOUS ADA RAMPS ALONG NORTH	03/05/20	24.00	55.00	25.25	5.00
NHPP0091-044		SH 9 FRISCO MAIN ST TO IRON S	03/05/20	61.00	40.00	78.23	36.00
NH050A-034		US50A PUEBLO WEST PURCELL INT	03/26/20	101.00	60.00	86.37	111.00
HPP 0501-067		US 50 AND SH 92 DELTA INTERSE	03/26/20	20.00	60.00	44.40	44.80
SHE 0703-461		I-70 and Kipling North Phase	03/26/20	54.00	115.00	97.80	72.00
		WEIGHTED AVERAGE FOR THE FIRST QUARTER		1,930.00	64.29	74.10	74.00
NHPP1602-169		US 160 WC TUNNEL EAST RESURFA	04/02/20	14.00	40.00	33.22	37.90
STR092A-030		SH92 MP 31.748-48.5, DELTA AND	04/02/20	32.00	60.00	42.10	43.00
IM0761-226		I76/SH52 Interchange	04/02/20	140.00	50.00	114.37	84.80

PROJECT NUMBER	ITEM NUMBER/ PROJECT LOCATION	ITEM DESCRIPTION/ PROJECT LOCATION	DATE LET	UNIT/ QUANTITY	ENGR. EST.	AVERAGE BID	AWARDED BID
=====	630-80342	Const Traf Sign (B)		Each	=====	=====	=====
STA340A-021		SH340 MP 6-6.76 MESA COUNTY	04/02/20	28.00	55.00	26.83	5.00
MTCER300-259		MTCE R3 FY20/21 Region Wide S	04/02/20	15.00	10.00	52.50	5.00
STR0341-101		SH 34 North of Grandby Resurf	04/02/20	64.00	70.00	59.73	60.00
IM0252-473		I-25 CABLE BARRIER PHASE IV	04/09/20	51.00	73.00	38.95	38.89
SHER100-339		WWD TRAFFIC CONTROL ENHANCEME	04/09/20	60.00	110.00	50.00	50.00
NHPP1601-077		US 160 MP 29.750 - MP 34.891	04/09/20	62.00	40.00	39.67	44.00
SFTY2254-091		225 Ramp Improvements	04/09/20	48.00	80.00	92.50	60.00
CC0852-106		US-85 LOUVIERS TO MP 191.75	04/23/20	80.00	110.00	54.46	44.00
FBR0852-108		US-85 BETWEEN LOUVIERS AND MP					
C1211-090		SH-121 & 29th Ave / SH-121 &	04/23/20	70.00	65.00	134.66	158.00
C1601-082		Hawkins Signal and Curb Ramps	04/30/20	24.00	40.00	54.00	62.00
FSA1602-159		US 160 AND SH 17 INTERSECTION	04/30/20	21.00	120.00	48.33	43.00
C0853-112		US85 & WCR98 INTERSECTION IMP	05/07/20	12.00	25.00	67.00	80.00
NHPPR100-303		LONG MAST ARM SIGNALS PROJECT	05/07/20	32.00	85.00	140.33	80.00
FBR0343-042		US 34 D-27-G STRUCTURE REPLAC	05/07/20	33.00	75.00	137.08	210.00
ITS SW02-304		ITS FIBER TO STATE BUILDINGS	05/14/20	32.00	55.00	202.25	248.00
NHPP0402-098		US 40 CHIP SEAL MP 126 TO MP	05/14/20	99.00	40.00	80.23	77.00
NHPP0253-276		I-25 EXPRESS LANES SEGMENT 5	05/15/20	24.00	96.00	97.77	97.77
ITS SW02-303		R1: US 285, SH 83 R2: SH 83,	05/28/20	56.00	115.00	165.55	75.00
MTCER200-265		Pueblo	05/28/20	26.00	60.00	80.00	10.00
NH050A-035		US 50A Pueblo Regional Pond	05/28/20	12.00	43.00	57.69	36.00
NH050A-037		US 50A Pueblo Regional Pond					
SHER400-373		R4 Signal Head Backplate Inst	05/28/20	76.00	90.00	92.50	75.00
IM025A-048		Northbound I-25 bridge at Exi	05/28/20	28.00	84.00	61.58	60.00
ITSSW01-719		FY 20 ITS CAPITAL REPLACEMENT	06/11/20	32.00	40.00	109.50	125.00
FSAR400-356		FY 20 SIGNAL POLE REPLACEMENT	06/11/20	8.00	65.00	59.33	65.00
SHE016A-043		SH 21 & 16 SIGNALS PROJECT	06/18/20	34.00	60.00	76.16	57.79
NHPPR100-251		SH 2/ Vasquez	06/25/20	54.00	100.00	59.33	56.65
		WEIGHTED AVERAGE FOR THE SECOND QUARTER		1,267.00	70.71	91.44	75.43
		WEIGHTED AVERAGE FOR THE YEAR		3,197.00	66.83	81.51	74.57
=====	630-80343	Const Traf Sign (C)		Each	=====	=====	=====
FSA0253-262		I-25 SB BOTTLENECK I-76 TO I-	01/09/20	8.00	140.00	92.44	200.00
SHER500-210		R5 FY19 CENTER LINE RUMBLE ST	01/09/20	4.00	35.00	88.13	26.25
NHPP0343-041		I-76 & US 34 FT. MORGAN AREA	01/09/20	32.00	70.00	115.48	124.00
STR131A-038		SH 131 MP 51.95-55.73, ROUTT	01/16/20	4.00	35.00	40.00	40.00
STR012A-050		CULVERT REPAIR I-25 AND US 35	01/30/20	2.00	85.00	65.00	65.00
STR141A-044		SH 141 AND SH 145, FROM SLICK	01/30/20	8.00	50.00	42.38	42.00
NHPP 0852-116		US85:HAMPDEN TO FLORIDA-RESUR	02/06/20	8.00	135.00	227.50	250.00
STA0703-443		I-70 EJMT TUNNELS PAVING	02/06/20	24.00	100.00	74.60	112.61
ITS0761-231		ITS FIBER AND CAMERAS ON I-76	02/06/20	8.00	85.00	119.49	246.00
NHPP4701-134		C-470 NOISE WALL WEST OF LUCE	02/06/20	15.00	80.00	120.40	100.00
STA059A-036		SH 59 SEIBERT TO COPE	02/06/20	16.00	85.00	101.00	92.00

PROJECT NUMBER	ITEM NUMBER/ PROJECT LOCATION	ITEM DESCRIPTION/ PROJECT LOCATION	DATE LET	UNIT/ QUANTITY	ENGR. EST.	AVERAGE BID	AWARDED BID
===== 630-80343							
		Const Traf Sign (C)		Each			
NHPP0702-359		I-70 No Name Tunnel Lighting	02/27/20	28.00	77.00	146.69	16.00
C0641-106		SH 64 Meeker West Rural Resur	03/05/20	12.00	35.00	50.00	50.00
BR025A-046		K-18-U ON I-25 AT MP112 BRIDG	03/05/20	3.00	85.00	93.20	96.71
NHPP0091-044		SH 9 FRISCO MAIN ST TO IRON S	03/05/20	51.00	50.00	83.23	36.00
		WEIGHTED AVERAGE FOR THE FIRST QUARTER		223.00	73.14	104.06	85.72
IM0761-226		I76/SH52 Interchange	04/02/20	8.00	60.00	127.26	106.00
STR0341-101		SH 34 North of Grandby Resurf	04/02/20	48.00	75.00	72.40	80.00
IM0252-473		I-25 CABLE BARRIER PHASE IV	04/09/20	8.00	90.00	55.78	55.56
SHER100-339		WWD TRAFFIC CONTROL ENHANCEME	04/09/20	18.00	120.00	50.00	50.00
SFTY2254-091		225 Ramp Improvements	04/09/20	20.00	100.00	99.00	60.00
CC0852-106		US-85 LOUVIERS TO MP 191.75	04/23/20	25.00	150.00	57.69	44.00
FBR0852-108		US-85 BETWEEN LOUVIERS AND MP					
C1211-090		SH-121 & 29th Ave / SH-121 &	04/23/20	10.00	87.00	114.33	125.00
ITS SW02-304		ITS FIBER TO STATE BUILDINGS	05/14/20	12.00	70.00	233.25	248.00
NHPP0402-098		US 40 CHIP SEAL MP 126 TO MP	05/14/20	8.00	40.00	90.75	88.00
NHPP0253-276		I-25 EXPRESS LANES SEGMENT 5	05/15/20	2.00	107.00	108.64	108.64
ITS SW02-303		R1: US 285, SH 83 R2: SH 83,	05/28/20	8.00	120.00	178.55	100.00
MTCER200-265		Pueblo	05/28/20	8.00	65.00	80.00	10.00
ITSSW01-719		FY 20 ITS CAPITAL REPLACEMENT	06/11/20	12.00	85.00	122.00	150.00
NHPPR100-251		SH 2/ Vasquez	06/25/20	8.00	100.00	70.98	67.95
		WEIGHTED AVERAGE FOR THE SECOND QUARTER		195.00	93.61	93.64	85.66
		WEIGHTED AVERAGE FOR THE YEAR		418.00	82.69	98.71	85.69
===== 630-80344							
		Const Traf Sign (Spec)		Sq Foot			
NHPP0343-041		I-76 & US 34 FT. MORGAN AREA	01/09/20	1,100.00	30.00	25.50	16.00
STA059A-036		SH 59 SEIBERT TO COPE	02/06/20	528.00	30.00	30.50	26.00
FSA2873-194		US 287 Longmont Intersection	02/13/20	103.00	70.00	23.36	16.00
NHPP0702-359		I-70 No Name Tunnel Lighting	02/27/20	119.00	23.00	38.29	21.00
C0641-106		SH 64 Meeker West Rural Resur	03/05/20	240.00	25.00	31.00	32.00
STR2871-038		US 287 Passing Lanes Springfi	03/05/20	64.00	20.00	25.01	29.25
NHPP0502-082		US 50 MONTROSE RE CHIP SEAL	03/05/20	388.00	25.00	30.00	30.00
NHPP0091-044		SH 9 FRISCO MAIN ST TO IRON S	03/05/20	105.00	30.00	27.27	24.00
SHE 0703-461		I-70 and Kipling North Phase	03/26/20	7.50	14.00	32.20	29.00
		WEIGHTED AVERAGE FOR THE FIRST QUARTER		2,654.50	29.77	28.07	22.38
IM0761-226		I76/SH52 Interchange	04/02/20	612.00	20.00	21.67	14.84

PROJECT NUMBER	ITEM NUMBER/ PROJECT LOCATION	ITEM DESCRIPTION/ PROJECT LOCATION	DATE LET	UNIT/ QUANTITY	ENGR. EST.	AVERAGE BID	AWARDED BID
===== 630-80344		Const Traf Sign (Spec)		Sq Foot			
STR0341-101		SH 34 North of Grandby Resurf	04/02/20	96.00	30.00	29.69	35.00
NHPP0402-098		US 40 CHIP SEAL MP 126 TO MP	05/14/20	200.00	18.50	28.62	27.50
NHPP0253-276		I-25 EXPRESS LANES SEGMENT 5	05/15/20	183.00	16.00	16.30	16.30
NH050A-035		US 50A Pueblo Regional Pond	05/28/20	330.00	25.00	19.04	16.25
NH050A-037		US 50A Pueblo Regional Pond					
	WEIGHTED AVERAGE FOR THE SECOND QUARTER			1,421.00	21.11	21.59	18.50
	WEIGHTED AVERAGE FOR THE YEAR			4,075.50	26.75	24.80	21.03
===== 630-80348		Const Info Sign		Each			
STA069A-033		SH69 MP 58.7 TO 71.58	02/13/20	2.00	216.00	152.78	200.00
NH0242-085		US 24 M.P. 291.38 to M.P. 296	02/27/20	2.00	220.00	2093.63	2050.00
	WEIGHTED AVERAGE FOR THE FIRST QUARTER			4.00	218.00	1317.29	1125.00
C0853-112		US85 & WCR98 INTERSECTION IMP	05/07/20	2.00	500.00	246.63	285.00
	WEIGHTED AVERAGE FOR THE SECOND QUARTER			2.00	500.00	246.63	285.00
	WEIGHTED AVERAGE FOR THE YEAR			6.00	312.00	658.42	845.00
===== 630-80350		Vert Panel		Each			
STA0142-066		SH 14 New Raymer West	01/09/20	20.00	30.00	33.38	25.51
FSA0253-262		I-25 SB BOTTLENECK I-76 TO I-	01/09/20	100.00	40.00	23.74	30.00
STA006A-067		SH 6 Merino to Atwood	01/16/20	40.00	30.00	16.90	17.00
STR141A-044		SH 141 AND SH 145, FROM SLICK	01/30/20	200.00	20.00	31.73	31.00
ITS0761-231		ITS FIBER AND CAMERAS ON I-76	02/06/20	30.00	30.00	38.85	30.00
STA059A-036		SH 59 SEIBERT TO COPE	02/06/20	36.00	29.00	17.50	15.00
FSA2873-194		US 287 Longmont Intersection	02/13/20	42.00	70.00	35.64	22.00
STA069A-033		SH69 MP 58.7 TO 71.58	02/13/20	20.00	21.00	48.39	44.00
NH0242-085		US 24 M.P. 291.38 to M.P. 296	02/27/20	20.00	30.00	17.62	17.10
STR2871-038		US 287 Passing Lanes Springfi	03/05/20	30.00	30.00	31.93	29.25
SHE 0703-461		I-70 and Kipling North Phase	03/26/20	50.00	40.00	35.00	39.00
	WEIGHTED AVERAGE FOR THE FIRST QUARTER			588.00	31.64	30.97	28.58
IM0761-226		I76/SH52 Interchange	04/02/20	40.00	35.00	42.26	31.80

PROJECT NUMBER	ITEM NUMBER/ PROJECT LOCATION	ITEM DESCRIPTION/ PROJECT LOCATION	DATE LET	UNIT/ QUANTITY	ENGR. EST.	AVERAGE BID	AWARDED BID
=====	630-80350	Vert Panel		Each =====			
NHPP1601-077	US 160 MP 29.750 - MP 34.891	US 160 MP 29.750 - MP 34.891	04/09/20	30.00	27.00	22.67	20.00
SFTY2254-091	225 Ramp Improvements	225 Ramp Improvements	04/09/20	100.00	40.00	36.00	24.00
FSA1602-159	US 160 AND SH 17 INTERSECTION	US 160 AND SH 17 INTERSECTION	04/30/20	25.00	30.00	26.67	28.00
ITS SW02-304	ITS FIBER TO STATE BUILDINGS	ITS FIBER TO STATE BUILDINGS	05/14/20	50.00	40.00	33.00	31.00
NHPP0253-276	I-25 EXPRESS LANES SEGMENT 5	I-25 EXPRESS LANES SEGMENT 5	05/15/20	50.00	21.00	21.72	21.72
	WEIGHTED AVERAGE FOR THE SECOND QUARTER			295.00	33.93	34.37	25.79
	WEIGHTED AVERAGE FOR THE YEAR			883.00	32.41	31.91	27.65
=====	630-80351	Vert Panel (Plastic)		Each =====			
ITS SW02-303	R1: US 285, SH 83 R2: SH 83,	R1: US 285, SH 83 R2: SH 83,	05/28/20	30.00	32.00	1166.94	50.00
ITSSW01-719	FY 20 ITS CAPITAL REPLACEMENT	FY 20 ITS CAPITAL REPLACEMENT	06/11/20	50.00	45.00	34.00	35.00
	WEIGHTED AVERAGE FOR THE SECOND QUARTER			80.00	40.13	713.76	40.63
	WEIGHTED AVERAGE FOR THE YEAR			80.00	40.13	713.76	40.63
=====	630-80353	Vert Panel (Light) (F)		Each =====			
FSA2873-194	US 287 Longmont Intersection	US 287 Longmont Intersection	02/13/20	24.00	80.00	74.54	110.00
	WEIGHTED AVERAGE FOR THE FIRST QUARTER			24.00	80.00	74.54	110.00
	WEIGHTED AVERAGE FOR THE YEAR			24.00	80.00	74.54	110.00
=====	630-80355	Port Mesg Panel		Each =====			
STA0142-066	SH 14 New Raymer West	SH 14 New Raymer West	01/09/20	2.00	3540.00	4828.00	5000.00
FSA0253-262	I-25 SB BOTTLENECK I-76 TO I-	I-25 SB BOTTLENECK I-76 TO I-	01/09/20	2.00	6500.00	4979.70	6000.00
NHPP0253-265	I-25 AT ERIE PARKWAY ON AND O	I-25 AT ERIE PARKWAY ON AND O	01/09/20	2.00	2500.00	2701.67	2100.00
SHER500-210	R5 FY19 CENTER LINE RUMBLE ST	R5 FY19 CENTER LINE RUMBLE ST	01/09/20	2.00	3000.00	6942.50	3885.00
FSA0341-097	US 34 & MACGREGOR INTERSECTIO	US 34 & MACGREGOR INTERSECTIO	01/09/20	4.00	5000.00	7000.00	7000.00
NHPP0343-041	I-76 & US 34 FT. MORGAN AREA	I-76 & US 34 FT. MORGAN AREA	01/09/20	6.00	6000.00	8004.97	6770.00
BR0343-040	US 34 REPUBLICAN RIVER BRIDGE	US 34 REPUBLICAN RIVER BRIDGE	01/16/20	4.00	5000.00	9056.12	9800.00
FBR0343-043	US 34 D-28-P STRUCTURE REPLAC	US 34 D-28-P STRUCTURE REPLAC					
STA006A-067	SH 6 Merino to Atwood	SH 6 Merino to Atwood	01/16/20	3.00	3540.00	1640.01	3000.00
STR131A-038	SH 131 MP 51.95-55.73, ROUTT	SH 131 MP 51.95-55.73, ROUTT	01/16/20	2.00	5000.00	6250.00	5000.00
NH 0503-093	US50 WEST OF TEXAS CREEK MP 2	US50 WEST OF TEXAS CREEK MP 2	01/23/20	3.00	5000.00	8437.90	7875.79
STR012A-050	CULVERT REPAIR I-25 AND US 35	CULVERT REPAIR I-25 AND US 35	01/30/20	2.00	6000.00	4000.00	4000.00
STR141A-044	SH 141 AND SH 145, FROM SLICK	SH 141 AND SH 145, FROM SLICK	01/30/20	4.00	2000.00	7068.53	7500.00

COLORADO DEPARTMENT OF TRANSPORTATION
 ITEM UNIT COSTS BY PROJECTS -- 2020 COST DATA

10:58 Friday, October 2, 2020 339

PROJECT NUMBER	ITEM NUMBER/ PROJECT LOCATION	ITEM DESCRIPTION/ PROJECT LOCATION	DATE LET	UNIT/ QUANTITY	ENGR. EST.	AVERAGE BID	AWARDED BID
=====	630-80355	Port Mesq Panel		Each =====			
NHPP 0852-116		US85:HAMPDEN TO FLORIDA-RESUR	02/06/20	4.00	6000.00	5250.00	6000.00
STA0703-443		I-70 EJMT TUNNELS PAVING	02/06/20	2.00	5000.00	6233.25	8611.50
ITS0761-231		ITS FIBER AND CAMERAS ON I-76	02/06/20	2.00	5250.00	5804.00	3600.00
NHPP4701-134		C-470 NOISE WALL WEST OF LUCE	02/06/20	1.00	5000.00	5260.00	4000.00
STA059A-036		SH 59 SEIBERT TO COPE	02/06/20	2.00	5000.00	9075.00	6150.00
STR116A-001		SH 116 A Surface Treatment Pr	02/13/20	2.00	5500.00	6784.93	9000.00
FSA2873-194		US 287 Longmont Intersection	02/13/20	2.00	4500.00	5464.17	3300.00
STA069A-033		SH69 MP 58.7 TO 71.58	02/13/20	2.00	5100.00	8977.81	15000.00
STR0101-027		SH 10 Overlay La Junta West	02/27/20	3.00	5500.00	6492.62	8000.00
NHPP0702-359		I-70 No Name Tunnel Lighting	02/27/20	1.00	10000.00	12164.75	1600.00
NH0242-085		US 24 M.P. 291.38 to M.P. 296	02/27/20	2.00	4850.00	7436.63	7415.00
C0641-106		SH 64 Meeker West Rural Resur	03/05/20	2.00	5000.00	6500.00	7500.00
NHPP145A-080		SH 145 Keystone-Placerville R	03/05/20	3.00	4000.00	2200.00	2200.00
STR2871-038		US 287 Passing Lanes Springfi	03/05/20	4.00	5500.00	10966.23	17550.00
NHPP0502-082		US 50 MONTROSE RE CHIP SEAL	03/05/20	10.00	5000.00	4873.75	4500.00
BR025A-046		K-18-U ON I-25 AT MP112 BRIDG	03/05/20	2.00	5100.00	6891.43	8532.57
STRR300-249		Grand and Jackson Counties AD	03/05/20	3.00	3000.00	5566.67	5000.00
CC080-037		VARIOUS ADA RAMPS ALONG NORTH	03/05/20	3.00	3000.00	3162.50	5000.00
NHPP0091-044		SH 9 FRISCO MAIN ST TO IRON S	03/05/20	3.00	8000.00	10405.00	4200.00
NH050A-034		US50A PUEBLO WEST PURCELL INT	03/26/20	4.00	5000.00	13728.49	9400.00
HPP 0501-067		US 50 AND SH 92 DELTA INTERSE	03/26/20	6.00	5000.00	8024.50	8399.00
SHE 0703-461		I-70 and Kipling North Phase	03/26/20	8.00	6000.00	5834.00	6600.00
		WEIGHTED AVERAGE FOR THE FIRST QUARTER		107.00	4979.44	7109.24	6723.64
IM0761-226		I76/SH52 Interchange	04/02/20	4.00	5000.00	10208.64	6890.00
STA340A-021		SH340 MP 6-6.76 MESA COUNTY	04/02/20	2.00	4000.00	3838.33	5000.00
STR0341-101		SH 34 North of Grandby Resurf	04/02/20	2.00	5000.00	15266.09	7500.00
IM0252-473		I-25 CABLE BARRIER PHASE IV	04/09/20	2.00	7000.00	4472.22	4444.44
SHER100-339		WWD TRAFFIC CONTROL ENHANCEME	04/09/20	3.00	7000.00	9500.00	9500.00
NHPP1601-077		US 160 MP 29.750 - MP 34.891	04/09/20	2.00	2000.00	3666.67	3000.00
SFTY2254-091		225 Ramp Improvements	04/09/20	4.00	5000.00	7837.50	4375.00
CC0852-106		US-85 LOUVIERS TO MP 191.75	04/23/20	3.00	6000.00	7295.05	4400.00
FBR0852-108		US-85 BETWEEN LOUVIERS AND MP					
C1211-090		SH-121 & 29th Ave / SH-121 &	04/23/20	1.00	4800.00	5003.83	3225.00
C1601-082		Hawkins Signal and Curb Ramps	04/30/20	4.00	2500.00	4537.67	4300.00
FSA1602-159		US 160 AND SH 17 INTERSECTION	04/30/20	3.00	2700.00	5447.67	4830.00
NHPPR100-303		LONG MAST ARM SIGNALS PROJECT	05/07/20	4.00	6500.00	5138.33	5000.00
FBR0343-042		US 34 D-27-G STRUCTURE REPLAC	05/07/20	2.00	5000.00	4632.12	5000.00
NHPP0253-276		I-25 EXPRESS LANES SEGMENT 5	05/15/20	2.00	6420.00	6517.77	6517.77
ITS SW02-303		R1: US 285, SH 83 R2: SH 83,	05/28/20	2.00	7000.00	4182.00	3500.00
SHER400-373		R4 Signal Head Backplate Inst	05/28/20	8.00	5625.00	5863.50	4280.00
FSAR400-356		FY 20 SIGNAL POLE REPLACEMENT	06/11/20	4.00	2750.00	4079.67	4539.00
NHPPR100-251		SH 2/ Vasquez	06/25/20	4.00	3500.00	2661.30	2548.60
		WEIGHTED AVERAGE FOR THE SECOND QUARTER		56.00	4834.64	6453.01	4896.25
		WEIGHTED AVERAGE FOR THE YEAR		163.00	4929.69	6884.55	6095.82

PROJECT NUMBER	ITEM NUMBER/ PROJECT LOCATION	ITEM DESCRIPTION/ PROJECT LOCATION	DATE LET	UNIT/ QUANTITY	ENGR. EST.	AVERAGE BID	AWARDED BID
===== 630-80356 Flash Arrow Panel (A Ty) Each =====							
FSA2873-194		US 287 Longmont Intersection	02/13/20	2.00	3000.00	1601.67	880.00
NHPP0171-105		SH 17 MP 84.5 to US 285 & SH	03/05/20	2.00	800.00	2760.03	1530.09
		WEIGHTED AVERAGE FOR THE FIRST QUARTER		4.00	1900.00	1987.79	1205.05
		WEIGHTED AVERAGE FOR THE YEAR		4.00	1900.00	1987.79	1205.05
===== 630-80357 Flash Arrow Panel (B Ty) Each =====							
C0402-094		US 40 GRAND COUNTY SIGNAL REP	02/27/20	2.00	900.00	2290.00	1580.00
STRR300-249		Grand and Jackson Counties AD	03/05/20	3.00	1000.00	1066.67	50.00
CC080-037		VARIOUS ADA RAMPS ALONG NORTH	03/05/20	3.00	1000.00	587.50	200.00
		WEIGHTED AVERAGE FOR THE FIRST QUARTER		8.00	975.00	1032.40	488.75
STA340A-021		SH340 MP 6-6.76 MESA COUNTY	04/02/20	2.00	1000.00	360.67	2.00
C1211-090		SH-121 & 29th Ave / SH-121 &	04/23/20	3.00	1320.00	1098.55	620.00
C1601-082		Hawkins Signal and Curb Ramps	04/30/20	4.00	700.00	943.33	965.00
SHE016A-043		SH 21 & 16 SIGNALS PROJECT	06/18/20	2.00	1000.00	1027.30	1386.50
		WEIGHTED AVERAGE FOR THE SECOND QUARTER		11.00	978.18	909.30	772.45
		WEIGHTED AVERAGE FOR THE YEAR		19.00	976.84	958.93	653.00
===== 630-80358 Flash Arrow Panel (C Ty) Each =====							
FSA0253-262		I-25 SB BOTTLENECK I-76 TO I-	01/09/20	2.00	1800.00	1807.24	1800.00
NHPP0253-265		I-25 AT ERIE PARKWAY ON AND O	01/09/20	2.00	735.00	803.33	735.00
NHPP0343-041		I-76 & US 34 FT. MORGAN AREA	01/09/20	4.00	1200.00	1781.94	1805.00
STR012A-050		CULVERT REPAIR I-25 AND US 35	01/30/20	2.00	800.00	660.00	660.00
NHPP 0852-116		US85:HAMPDEN TO FLORIDA-RESUR	02/06/20	3.00	1800.00	1750.00	2000.00
STA0703-443		I-70 EJMT TUNNELS PAVING	02/06/20	2.00	2000.00	1912.37	2384.73
ITS0761-231		ITS FIBER AND CAMERAS ON I-76	02/06/20	1.00	1500.00	1462.60	1200.00
NHPP4701-134		C-470 NOISE WALL WEST OF LUCE	02/06/20	2.00	2000.00	1140.00	500.00
NHPP0702-359		I-70 No Name Tunnel Lighting	02/27/20	1.00	3000.00	4136.25	525.00
NH0242-085		US 24 M.P. 291.38 to M.P. 296	02/27/20	4.00	1200.00	2869.86	2850.00
C0641-106		SH 64 Meeker West Rural Resur	03/05/20	2.00	2000.00	1500.00	1500.00
NHPP0502-082		US 50 MONTROSE RE CHIP SEAL	03/05/20	2.00	1500.00	1703.75	1700.00
BR025A-046		K-18-U ON I-25 AT MP112 BRIDG	03/05/20	2.00	1500.00	1607.52	1137.68

COLORADO DEPARTMENT OF TRANSPORTATION
 ITEM UNIT COSTS BY PROJECTS -- 2020 COST DATA

10:58 Friday, October 2, 2020 341

PROJECT NUMBER	ITEM NUMBER/ PROJECT LOCATION	ITEM DESCRIPTION/ PROJECT LOCATION	DATE LET	UNIT/ QUANTITY	ENGR. EST.	AVERAGE BID	AWARDED BID
===== 630-80358		Flash Arrow Panel (C Ty)		Each =====			
NHPP0091-044		SH 9 FRISCO MAIN ST TO IRON S	03/05/20	2.00	1000.00	2478.33	1800.00
NH050A-034		US50A PUEBLO WEST PURCELL INT	03/26/20	10.00	1600.00	2224.62	2325.00
HPP 0501-067		US 50 AND SH 92 DELTA INTERSE	03/26/20	2.00	1600.00	1635.00	1680.00
SHE 0703-461		I-70 and Kipling North Phase	03/26/20	2.00	1500.00	2708.00	3300.00
		WEIGHTED AVERAGE FOR THE FIRST QUARTER		45.00	1519.33	2045.63	1866.44
IM0761-226		I76/SH52 Interchange	04/02/20	2.00	1900.00	2072.87	2120.00
MTCER300-259		MTCE R3 FY20/21 Region Wide S	04/02/20	2.00	300.00	762.50	775.00
STR0341-101		SH 34 North of Grandby Resurf	04/02/20	2.00	3000.00	1191.94	2500.00
IM0252-473		I-25 CABLE BARRIER PHASE IV	04/09/20	1.00	2500.00	894.45	888.89
SFTY2254-091		225 Ramp Improvements	04/09/20	4.00	1750.00	3591.50	883.00
CC0852-106		US-85 LOUVIERS TO MP 191.75	04/23/20	2.00	1600.00	3555.62	2200.00
FBR0852-108		US-85 BETWEEN LOUVIERS AND MP					
FSA1602-159		US 160 AND SH 17 INTERSECTION	04/30/20	1.00	2000.00	2653.67	1610.00
C0853-112		US85 & WCR98 INTERSECTION IMP	05/07/20	2.00	1500.00	669.38	570.00
NHPPR100-303		LONG MAST ARM SIGNALS PROJECT	05/07/20	4.00	1800.00	1746.67	2110.00
ITS SW02-304		ITS FIBER TO STATE BUILDINGS	05/14/20	2.00	2250.00	3466.75	3013.00
NHPP0402-098		US 40 CHIP SEAL MP 126 TO MP	05/14/20	2.00	1500.00	3111.67	3500.00
ITS SW02-303		R1: US 285, SH 83 R2: SH 83,	05/28/20	1.00	2600.00	5930.35	2500.00
MTCER200-265		Pueblo	05/28/20	2.00	150.00	402.50	100.00
SHER400-373		R4 Signal Head Backplate Inst	05/28/20	4.00	1350.00	4387.50	4815.00
ITSSW01-719		FY 20 ITS CAPITAL REPLACEMENT	06/11/20	2.00	1500.00	1607.50	2500.00
FSAR400-356		FY 20 SIGNAL POLE REPLACEMENT	06/11/20	2.00	1000.00	1748.33	1945.00
NHPPR100-251		SH 2/ Vasquez	06/25/20	3.00	1200.00	709.83	679.65
		WEIGHTED AVERAGE FOR THE SECOND QUARTER		38.00	1571.05	2270.17	2018.84
		WEIGHTED AVERAGE FOR THE YEAR		83.00	1543.01	2137.64	1936.21
===== 630-80359		Port Mesg Panel		Day =====			
NHPP0171-105		SH 17 MP 84.5 to US 285 & SH	03/05/20	1,025.00	40.00	39.87	30.60
		WEIGHTED AVERAGE FOR THE FIRST QUARTER		1,025.00	40.00	39.87	30.60
NHPP1602-169		US 160 WC TUNNEL EAST RESURFA	04/02/20	146.00	55.00	70.69	59.56
STR092A-030		SH92 MP 31.748-48.5, DELTA AND	04/02/20	204.00	100.00	75.50	45.00
C0853-112		US85 & WCR98 INTERSECTION IMP	05/07/20	65.00	85.00	115.13	175.00
ITS SW02-304		ITS FIBER TO STATE BUILDINGS	05/14/20	26.00	200.00	135.00	121.00

PROJECT NUMBER	ITEM NUMBER/ PROJECT LOCATION	ITEM DESCRIPTION/ PROJECT LOCATION	DATE LET	UNIT/ QUANTITY	ENGR. EST.	AVERAGE BID	AWARDED BID
===== 630-80359							
		Port Mesq Panel		Day			
NHPP0402-098		US 40 CHIP SEAL MP 126 TO MP	05/14/20	80.00	100.00	133.00	137.50
ITSSW01-719		FY 20 ITS CAPITAL REPLACEMENT	06/11/20	10.00	3600.00	1050.00	2000.00
SHE016A-043		SH 21 & 16 SIGNALS PROJECT	06/18/20	40.00	90.00	123.05	98.23
		WEIGHTED AVERAGE FOR THE SECOND QUARTER		571.00	151.94	110.47	117.91
		WEIGHTED AVERAGE FOR THE YEAR		1,596.00	80.05	67.09	61.84
===== 630-80360							
		Drum Channel Dev		Each			
STA0142-066		SH 14 New Raymer West	01/09/20	170.00	40.00	30.75	21.00
FSA0253-262		I-25 SB BOTTLENECK I-76 TO I-	01/09/20	100.00	42.00	42.11	60.00
NHPP0253-265		I-25 AT ERIE PARKWAY ON AND O	01/09/20	25.00	40.00	26.17	21.00
SHER500-210		R5 FY19 CENTER LINE RUMBLE ST	01/09/20	20.00	10.00	43.00	21.00
NHPP0343-041		I-76 & US 34 FT. MORGAN AREA	01/09/20	491.00	35.00	50.41	45.00
BR0343-040		US 34 REPUBLICAN RIVER BRIDGE	01/16/20	100.00	40.00	33.21	30.00
FBR0343-043		US 34 D-28-P STRUCTURE REPLAC					
STA006A-067		SH 6 Merino to Atwood	01/16/20	170.00	40.00	22.45	22.50
STR131A-038		SH 131 MP 51.95-55.73, ROUTT	01/16/20	100.00	25.00	30.00	30.00
NH 0503-093		US50 WEST OF TEXAS CREEK MP 2	01/23/20	400.00	30.00	46.13	47.25
STR012A-050		CULVERT REPAIR I-25 AND US 35	01/30/20	100.00	30.00	40.00	40.00
STR141A-044		SH 141 AND SH 145, FROM SLICK	01/30/20	100.00	25.00	31.93	31.00
NHPP 0852-116		US85:HAMPDEN TO FLORIDA-RESUR	02/06/20	100.00	45.00	45.00	50.00
STA0703-443		I-70 EJMT TUNNELS PAVING	02/06/20	275.00	45.00	25.44	26.50
ITS0761-231		ITS FIBER AND CAMERAS ON I-76	02/06/20	50.00	35.00	38.96	66.00
NHPP4701-134		C-470 NOISE WALL WEST OF LUCE	02/06/20	50.00	40.00	47.80	40.00
STA059A-036		SH 59 SEIBERT TO COPE	02/06/20	50.00	40.00	22.00	22.00
STR116A-001		SH 116 A Surface Treatment Pr	02/13/20	150.00	20.00	32.58	35.00
FSA2873-194		US 287 Longmont Intersection	02/13/20	4.00	50.00	73.14	62.00
STA069A-033		SH69 MP 58.7 TO 71.58	02/13/20	40.00	29.00	35.70	45.00
STR0101-027		SH 10 Overlay La Junta West	02/27/20	100.00	20.00	41.09	40.00
NHPP0702-359		I-70 No Name Tunnel Lighting	02/27/20	40.00	30.00	26.11	16.00
C0402-094		US 40 GRAND COUNTY SIGNAL REP	02/27/20	50.00	30.00	65.80	31.60
NH0242-085		US 24 M.P. 291.38 to M.P. 296	02/27/20	104.00	26.00	23.83	22.80
NHPP0171-105		SH 17 MP 84.5 to US 285 & SH	03/05/20	505.00	15.00	28.92	20.40
C0641-106		SH 64 Meeker West Rural Resur	03/05/20	50.00	25.00	40.00	40.00
NHPP145A-080		SH 145 Keystone-Placerville R	03/05/20	25.00	45.00	25.00	25.00
STR2871-038		US 287 Passing Lanes Springfi	03/05/20	200.00	20.00	37.82	46.80
NHPP0502-082		US 50 MONTROSE RE CHIP SEAL	03/05/20	70.00	25.00	11.00	10.00
BR025A-046		K-18-U ON I-25 AT MP112 BRIDG	03/05/20	100.00	30.00	43.47	45.51
NHPP0091-044		SH 9 FRISCO MAIN ST TO IRON S	03/05/20	350.00	35.00	37.23	36.00
NH050A-034		US50A PUEBLO WEST PURCELL INT	03/26/20	160.00	30.00	57.54	72.00
HPP 0501-067		US 50 AND SH 92 DELTA INTERSE	03/26/20	150.00	32.00	21.80	22.40
SHE 0703-461		I-70 and Kipling North Phase	03/26/20	80.00	50.00	43.40	40.00
		WEIGHTED AVERAGE FOR THE FIRST QUARTER		4,479.00	31.06	38.20	36.00

PROJECT NUMBER	ITEM NUMBER/ PROJECT LOCATION	ITEM DESCRIPTION/ PROJECT LOCATION	DATE LET	UNIT/ QUANTITY	ENGR. EST.	AVERAGE BID	AWARDED BID
===== 630-80360		Drum Channel Dev		Each	=====		
NHPP1602-169		US 160 WC TUNNEL EAST RESURFA	04/02/20	42.00	22.00	27.56	21.66
STR092A-030		SH92 MP 31.748-48.5, DELTA AND	04/02/20	100.00	25.00	27.75	32.00
IM0761-226		I76/SH52 Interchange	04/02/20	200.00	35.00	49.26	42.40
STA340A-021		SH340 MP 6-6.76 MESA COUNTY	04/02/20	70.00	20.00	27.67	40.00
STR0341-101		SH 34 North of Grandby Resurf	04/02/20	500.00	15.00	29.91	20.00
IM0252-473		I-25 CABLE BARRIER PHASE IV	04/09/20	335.00	40.00	11.56	11.11
SHER100-339		WWD TRAFFIC CONTROL ENHANCEME	04/09/20	150.00	45.00	15.00	15.00
NHPP1601-077		US 160 MP 29.750 - MP 34.891	04/09/20	35.00	27.00	24.00	22.00
SFTY2254-091		225 Ramp Improvements	04/09/20	50.00	30.00	34.00	24.00
CC0852-106		US-85 LOUVIERS TO MP 191.75	04/23/20	500.00	40.00	42.51	33.00
FBR0852-108		US-85 BETWEEN LOUVIERS AND MP					
C1211-090		SH-121 & 29th Ave / SH-121 &	04/23/20	120.00	35.00	31.17	37.00
C1601-082		Hawkins Signal and Curb Ramps	04/30/20	75.00	20.00	35.00	35.00
FSA1602-159		US 160 AND SH 17 INTERSECTION	04/30/20	50.00	40.00	28.00	32.00
C0853-112		US85 & WCR98 INTERSECTION IMP	05/07/20	200.00	38.00	48.31	51.00
NHPPR100-303		LONG MAST ARM SIGNALS PROJECT	05/07/20	50.00	45.00	38.67	19.00
FBR0343-042		US 34 D-27-G STRUCTURE REPLAC	05/07/20	50.00	40.00	49.83	55.00
ITS SW02-304		ITS FIBER TO STATE BUILDINGS	05/14/20	50.00	35.00	59.00	67.00
NHPP0402-098		US 40 CHIP SEAL MP 126 TO MP	05/14/20	300.00	30.00	32.28	25.00
NHPP0253-276		I-25 EXPRESS LANES SEGMENT 5	05/15/20	50.00	43.00	43.45	43.45
MTCER200-265		Pueblo	05/28/20	120.00	30.00	12.50	5.00
FSAR400-356		FY 20 SIGNAL POLE REPLACEMENT	06/11/20	40.00	40.00	42.00	46.00
SHE016A-043		SH 21 & 16 SIGNALS PROJECT	06/18/20	50.00	30.00	42.49	40.44
NHPPR100-251		SH 2/ Vasquez	06/25/20	150.00	40.00	47.15	45.30
	WEIGHTED AVERAGE FOR THE SECOND QUARTER			3,287.00	32.57	37.84	29.41
	WEIGHTED AVERAGE FOR THE YEAR			7,766.00	31.70	38.02	33.21
===== 630-80363		Drum Channel Dev (Light) (F)		Each	=====		
NHPP0343-041		I-76 & US 34 FT. MORGAN AREA	01/09/20	50.00	42.00	62.78	62.00
BR0343-040		US 34 REPUBLICAN RIVER BRIDGE	01/16/20	20.00	45.00	43.43	35.00
FBR0343-043		US 34 D-28-P STRUCTURE REPLAC					
STR131A-038		SH 131 MP 51.95-55.73, ROUTT	01/16/20	20.00	30.00	30.00	30.00
STA0703-443		I-70 EJMT TUNNELS PAVING	02/06/20	6.00	55.00	37.90	33.12
NHPP0702-359		I-70 No Name Tunnel Lighting	02/27/20	40.00	35.00	31.63	16.00
C0641-106		SH 64 Meeker West Rural Resur	03/05/20	20.00	30.00	60.00	60.00
NHPP0091-044		SH 9 FRISCO MAIN ST TO IRON S	03/05/20	50.00	60.00	39.23	36.00
HPP 0501-067		US 50 AND SH 92 DELTA INTERSE	03/26/20	50.00	45.00	23.33	23.55
SHE 0703-461		I-70 and Kipling North Phase	03/26/20	9.00	50.00	73.80	72.00
	WEIGHTED AVERAGE FOR THE FIRST QUARTER			265.00	43.89	43.19	37.98

PROJECT NUMBER	ITEM NUMBER/ PROJECT LOCATION	ITEM DESCRIPTION/ PROJECT LOCATION	DATE LET	UNIT/ QUANTITY	ENGR. EST.	AVERAGE BID	AWARDED BID
===== 630-80363		Drum Channel Dev (Light) (F)		Each	=====		
NHPP1602-169		US 160 WC TUNNEL EAST RESURFA	04/02/20	10.00	40.00	38.22	37.90
STR092A-030		SH92 MP 31.748-48.5,DELTA AND	04/02/20	10.00	30.00	41.58	53.75
STR0341-101		SH 34 North of Grandby Resurf	04/02/20	20.00	30.00	43.81	60.00
SHER100-339		WWD TRAFFIC CONTROL ENHANCEME	04/09/20	150.00	65.00	20.00	20.00
CC0852-106		US-85 LOUVIERS TO MP 191.75	04/23/20	12.00	65.00	46.40	33.00
FBR0852-108		US-85 BETWEEN LOUVIERS AND MP					
C0853-112		US85 & WCR98 INTERSECTION IMP	05/07/20	100.00	43.00	72.31	62.00
NHPPR100-303		LONG MAST ARM SIGNALS PROJECT	05/07/20	50.00	50.00	50.33	32.00
FBR0343-042		US 34 D-27-G STRUCTURE REPLAC	05/07/20	10.00	50.00	66.01	55.00
NHPP0402-098		US 40 CHIP SEAL MP 126 TO MP	05/14/20	100.00	20.00	33.30	26.00
MTCER200-265		Pueblo	05/28/20	120.00	40.00	20.00	5.00
SHE016A-043		SH 21 & 16 SIGNALS PROJECT	06/18/20	25.00	50.00	51.45	46.24
		WEIGHTED AVERAGE FOR THE SECOND QUARTER		607.00	44.78	47.52	30.01
		WEIGHTED AVERAGE FOR THE YEAR		872.00	44.51	46.39	32.43
===== 630-80364		Drum Channel Dev (Light) (SB)		Each	=====		
BR0343-040		US 34 REPUBLICAN RIVER BRIDGE	01/16/20	40.00	45.00	54.25	40.00
FBR0343-043		US 34 D-28-P STRUCTURE REPLAC					
STR131A-038		SH 131 MP 51.95-55.73, ROUTE	01/16/20	20.00	30.00	30.00	30.00
NH 0503-093		US50 WEST OF TEXAS CREEK MP 2	01/23/20	200.00	40.00	58.88	57.76
C0641-106		SH 64 Meeker West Rural Resur	03/05/20	20.00	30.00	60.00	60.00
NHPP145A-080		SH 145 Keystone-Placerville R	03/05/20	12.00	45.00	40.00	40.00
BR025A-046		K-18-U ON I-25 AT MP112 BRIDG	03/05/20	100.00	40.00	48.10	56.89
NHPP0091-044		SH 9 FRISCO MAIN ST TO IRON S	03/05/20	50.00	60.00	39.23	36.00
HPP 0501-067		US 50 AND SH 92 DELTA INTERSE	03/26/20	100.00	45.00	23.33	23.55
		WEIGHTED AVERAGE FOR THE FIRST QUARTER		542.00	42.51	47.63	46.63
STR092A-030		SH92 MP 31.748-48.5,DELTA AND	04/02/20	25.00	30.00	41.58	53.75
STR0341-101		SH 34 North of Grandby Resurf	04/02/20	40.00	30.00	43.81	60.00
SHER100-339		WWD TRAFFIC CONTROL ENHANCEME	04/09/20	150.00	45.00	20.00	20.00
FSA1602-159		US 160 AND SH 17 INTERSECTION	04/30/20	10.00	30.00	47.67	41.00
FBR0343-042		US 34 D-27-G STRUCTURE REPLAC	05/07/20	20.00	50.00	71.66	55.00
NHPP0402-098		US 40 CHIP SEAL MP 126 TO MP	05/14/20	100.00	42.00	33.30	26.00
NHPP0253-276		I-25 EXPRESS LANES SEGMENT 5	05/15/20	25.00	59.00	59.75	59.75
SHE016A-043		SH 21 & 16 SIGNALS PROJECT	06/18/20	25.00	35.00	51.45	46.24
		WEIGHTED AVERAGE FOR THE SECOND QUARTER		395.00	41.90	43.46	34.19
		WEIGHTED AVERAGE FOR THE YEAR		937.00	42.25	46.11	41.39

PROJECT NUMBER	ITEM NUMBER/ PROJECT LOCATION	ITEM DESCRIPTION/ PROJECT LOCATION	DATE LET	UNIT/ QUANTITY	ENGR. EST.	AVERAGE BID	AWARDED BID
===== 630-80367		Port Traf Speed Monitor		Each	=====		
BR0343-040		US 34 REPUBLICAN RIVER BRIDGE	01/16/20	4.00	4000.00	2361.89	1600.00
FBR0343-043		US 34 D-28-P STRUCTURE REPLAC					
STR131A-038		SH 131 MP 51.95-55.73, ROUTT	01/16/20	2.00	2500.00	3000.00	2500.00
NH 0503-093		US50 WEST OF TEXAS CREEK MP 2	01/23/20	2.00	4200.00	4495.20	3990.40
NHPP0702-359		I-70 No Name Tunnel Lighting	02/27/20	1.00	3000.00	4136.25	525.00
C0641-106		SH 64 Meeker West Rural Resur	03/05/20	2.00	3000.00	5250.00	5500.00
		WEIGHTED AVERAGE FOR THE FIRST QUARTER		11.00	3490.91	3105.28	2809.62
STR0341-101		SH 34 North of Grandby Resurf	04/02/20	2.00	2000.00	2977.58	6500.00
FBR0343-042		US 34 D-27-G STRUCTURE REPLAC	05/07/20	2.00	3000.00	2986.89	4000.00
		WEIGHTED AVERAGE FOR THE SECOND QUARTER		4.00	2500.00	2984.03	5250.00
		WEIGHTED AVERAGE FOR THE YEAR		15.00	3226.67	3057.51	3460.39
===== 630-80370		Barrier (Temp)		Lin Foot	=====		
FSA0253-262		I-25 SB BOTTLENECK I-76 TO I-	01/09/20	1,500.00	45.00	30.67	30.00
NHPP0343-041		I-76 & US 34 FT. MORGAN AREA	01/09/20	500.00	30.00	53.67	70.00
BR0343-040		US 34 REPUBLICAN RIVER BRIDGE	01/16/20	4,165.00	40.00	38.01	32.00
FBR0343-043		US 34 D-28-P STRUCTURE REPLAC					
NHPP4701-134		C-470 NOISE WALL WEST OF LUCE	02/06/20	2,440.00	10.00	19.00	22.00
STA069A-033		SH69 MP 58.7 TO 71.58	02/13/20	1,100.00	36.00	35.38	38.00
NHPP0702-359		I-70 No Name Tunnel Lighting	02/27/20	150.00	70.00	106.53	75.00
NHPP145A-080		SH 145 Keystone-Placerville R	03/05/20	200.00	70.00	73.00	73.00
BR025A-046		K-18-U ON I-25 AT MP112 BRIDG	03/05/20	4,000.00	42.00	42.62	56.95
NHPP0091-044		SH 9 FRISCO MAIN ST TO IRON S	03/05/20	2,000.00	50.00	72.67	35.00
NH050A-034		US50A PUEBLO WEST PURCELL INT	03/26/20	21,950.00	35.00	38.23	27.57
HPP 0501-067		US 50 AND SH 92 DELTA INTERSE	03/26/20	100.00	45.00	82.55	72.80
SHE 0703-461		I-70 and Kipling North Phase	03/26/20	750.00	45.00	51.40	45.00
		WEIGHTED AVERAGE FOR THE FIRST QUARTER		38,855.00	36.34	38.92	32.91
IM0761-226		I76/SH52 Interchange	04/02/20	4,000.00	40.00	31.66	35.00
SFTY2254-091		225 Ramp Improvements	04/09/20	5,300.00	35.00	36.50	31.00
CC0852-106		US-85 LOUVIERS TO MP 191.75	04/23/20	4,300.00	45.00	32.12	33.00
FBR0852-108		US-85 BETWEEN LOUVIERS AND MP					

COLORADO DEPARTMENT OF TRANSPORTATION
ITEM UNIT COSTS BY PROJECTS -- 2020 COST DATA

10:58 Friday, October 2, 2020 346

PROJECT NUMBER	ITEM NUMBER/ PROJECT LOCATION	ITEM DESCRIPTION/ PROJECT LOCATION	DATE LET	UNIT/ QUANTITY	ENGR. EST.	AVERAGE BID	AWARDED BID
=====	630-80370	Barrier (Temp)		Lin Foot	=====		
FSA1602-159	US 160 AND SH 17 INTERSECTION	04/30/20	1,780.00	40.00	74.33	62.00	
C0853-112	US85 & WCR98 INTERSECTION IMP	05/07/20	3,833.00	40.00	32.20	21.00	
FBR0343-042	US 34 D-27-G STRUCTURE REPLAC	05/07/20	679.00	40.00	45.22	31.50	
NHPP0253-276	I-25 EXPRESS LANES SEGMENT 5	05/15/20	9,280.00	22.80	22.63	22.63	
NHPPR100-251	SH 2/ Vasquez	06/25/20	120.00	35.00	71.33	74.65	
	WEIGHTED AVERAGE FOR THE SECOND QUARTER		29,292.00	34.36	34.23	29.95	
	WEIGHTED AVERAGE FOR THE YEAR		68,147.00	35.49	37.40	31.64	
=====	630-80371	Reset Concrete Barrier (Temp)		Lin Foot	=====		
STA069A-033	SH69 MP 58.7 TO 71.58	02/13/20	2,400.00	15.00	7.36	9.00	
	WEIGHTED AVERAGE FOR THE FIRST QUARTER		2,400.00	15.00	7.36	9.00	
	WEIGHTED AVERAGE FOR THE YEAR		2,400.00	15.00	7.36	9.00	
=====	630-80377	Port Water Filled Barrier (Temp)		Lin Foot	=====		
NHPP1602-169	US 160 WC TUNNEL EAST RESURFA	04/02/20	120.00	100.00	81.57	162.43	
STA340A-021	SH340 MP 6-6.76 MESA COUNTY	04/02/20	80.00	50.00	71.67	150.00	
	WEIGHTED AVERAGE FOR THE SECOND QUARTER		200.00	80.00	77.61	157.46	
	WEIGHTED AVERAGE FOR THE YEAR		200.00	80.00	77.61	157.46	
=====	630-80378	Glare Screen (Temp)		Lin Foot	=====		
BR025A-046	K-18-U ON I-25 AT MP112 BRIDG	03/05/20	1,000.00	15.00	19.62	22.72	
	WEIGHTED AVERAGE FOR THE FIRST QUARTER		1,000.00	15.00	19.62	22.72	
	WEIGHTED AVERAGE FOR THE YEAR		1,000.00	15.00	19.62	22.72	
=====	630-80380	Traffic Cone		Each	=====		
STA0142-066	SH 14 New Raymer West	01/09/20	150.00	10.00	10.80	10.20	
FSA0253-262	I-25 SB BOTTLENECK I-76 TO I-	01/09/20	500.00	12.00	11.82	15.00	
NHPP0253-265	I-25 AT ERIE PARKWAY ON AND O	01/09/20	50.00	11.00	10.00	9.00	

PROJECT NUMBER	ITEM NUMBER/ PROJECT LOCATION	ITEM DESCRIPTION/ PROJECT LOCATION	DATE LET	UNIT/ QUANTITY	ENGR. EST.	AVERAGE BID	AWARDED BID
=====	630-80380	Traffic Cone		Each =====			
SHER500-210		R5 FY19 CENTER LINE RUMBLE ST	01/09/20	150.00	2.00	24.60	4.20
NHPP0343-041		I-76 & US 34 FT. MORGAN AREA	01/09/20	50.00	9.00	15.07	15.00
BR0343-040		US 34 REPUBLICAN RIVER BRIDGE	01/16/20	200.00	10.00	10.97	9.00
FBR0343-043		US 34 D-28-P STRUCTURE REPLAC					
STA006A-067		SH 6 Merino to Atwood	01/16/20	300.00	10.00	8.98	9.00
STR131A-038		SH 131 MP 51.95-55.73, ROUTT	01/16/20	100.00	3.00	5.00	5.00
NH 0503-093		US50 WEST OF TEXAS CREEK MP 2	01/23/20	350.00	8.00	14.35	14.70
STR012A-050		CULVERT REPAIR I-25 AND US 35	01/30/20	100.00	10.00	10.00	10.00
STR141A-044		SH 141 AND SH 145, FROM SLICK	01/30/20	300.00	10.00	2.03	1.05
NHPP 0852-116		US85:HAMPDEN TO FLORIDA-RESUR	02/06/20	100.00	12.00	15.25	17.00
STA0703-443		I-70 EJMT TUNNELS PAVING	02/06/20	100.00	12.00	10.29	13.25
ITS0761-231		ITS FIBER AND CAMERAS ON I-76	02/06/20	150.00	10.00	12.76	16.50
STA059A-036		SH 59 SEIBERT TO COPE	02/06/20	400.00	10.00	10.50	10.00
STR116A-001		SH 116 A Surface Treatment Pr	02/13/20	350.00	10.00	1.39	2.00
STA069A-033		SH69 MP 58.7 TO 71.58	02/13/20	450.00	6.00	5.22	2.00
STR0101-027		SH 10 Overlay La Junta West	02/27/20	200.00	10.00	2.40	3.00
NHPP0702-359		I-70 No Name Tunnel Lighting	02/27/20	100.00	6.00	6.40	6.00
C0402-094		US 40 GRAND COUNTY SIGNAL REP	02/27/20	200.00	10.00	5.75	10.50
NH0242-085		US 24 M.P. 291.38 to M.P. 296	02/27/20	500.00	7.50	11.75	11.40
NHPP0171-105		SH 17 MP 84.5 to US 285 & SH	03/05/20	310.00	5.00	5.42	1.02
C0641-106		SH 64 Meeker West Rural Resur	03/05/20	200.00	3.00	3.00	5.00
NHPP145A-080		SH 145 Keystone-Placerville R	03/05/20	300.00	2.00	2.00	2.00
STR2871-038		US 287 Passing Lanes Springfi	03/05/20	200.00	10.00	3.48	2.34
NHPP0502-082		US 50 MONTROSE RE CHIP SEAL	03/05/20	1,000.00	8.00	19.50	20.00
BR025A-046		K-18-U ON I-25 AT MP112 BRIDG	03/05/20	100.00	9.00	11.78	11.38
STRR300-249		Grand and Jackson Counties AD	03/05/20	150.00	6.00	5.37	1.00
CC080-037		VARIOUS ADA RAMPS ALONG NORTH	03/05/20	150.00	10.00	3.06	5.00
NHPP0091-044		SH 9 FRISCO MAIN ST TO IRON S	03/05/20	200.00	10.00	12.63	12.00
HPP 0501-067		US 50 AND SH 92 DELTA INTERSE	03/26/20	400.00	8.00	10.90	11.20
SHE 0703-461		I-70 and Kipling North Phase	03/26/20	50.00	20.00	17.20	11.00
		WEIGHTED AVERAGE FOR THE FIRST QUARTER		7,860.00	8.35	10.40	9.45
NHPP1602-169		US 160 WC TUNNEL EAST RESURFA	04/02/20	264.00	5.00	6.55	5.41
STR092A-030		SH92 MP 31.748-48.5, DELTA AND	04/02/20	400.00	8.00	6.53	1.25
IM0761-226		I76/SH52 Interchange	04/02/20	100.00	8.00	10.30	13.78
STA340A-021		SH340 MP 6-6.76 MESA COUNTY	04/02/20	70.00	8.00	3.92	1.00
MTCER300-259		MTCE R3 FY20/21 Region Wide S	04/02/20	300.00	5.00	7.50	5.00
STR0341-101		SH 34 North of Grandby Resurf	04/02/20	300.00	10.00	8.18	1.00
IM0252-473		I-25 CABLE BARRIER PHASE IV	04/09/20	169.00	10.00	5.78	5.56
SFTY2254-091		225 Ramp Improvements	04/09/20	150.00	10.00	17.50	12.00
CC0852-106		US-85 LOUVIERS TO MP 191.75	04/23/20	100.00	12.00	11.61	11.00
FBR0852-108		US-85 BETWEEN LOUVIERS AND MP					
C1211-090		SH-121 & 29th Ave / SH-121 &	04/23/20	150.00	10.00	11.90	13.00
C1601-082		Hawkins Signal and Curb Ramps	04/30/20	300.00	5.00	10.33	4.00

PROJECT NUMBER	ITEM NUMBER/ PROJECT LOCATION	ITEM DESCRIPTION/ PROJECT LOCATION	DATE LET	UNIT/ QUANTITY	ENGR. EST.	AVERAGE BID	AWARDED BID
=====	630-80380	Traffic Cone		Each =====			
FSA1602-159		US 160 AND SH 17 INTERSECTION	04/30/20	25.00	10.00	10.33	5.00
C0853-112		US85 & WCR98 INTERSECTION IMP	05/07/20	50.00	10.00	9.22	5.00
NHPPR100-303		LONG MAST ARM SIGNALS PROJECT	05/07/20	100.00	10.00	18.00	12.00
FBR0343-042		US 34 D-27-G STRUCTURE REPLAC	05/07/20	50.00	10.00	13.05	14.00
ITS SW02-304		ITS FIBER TO STATE BUILDINGS	05/14/20	200.00	10.00	17.13	17.00
NHPP0402-098		US 40 CHIP SEAL MP 126 TO MP	05/14/20	400.00	3.00	17.68	22.00
NHPP0253-276		I-25 EXPRESS LANES SEGMENT 5	05/15/20	50.00	14.00	13.03	13.03
ITS SW02-303		R1: US 285, SH 83 R2: SH 83,	05/28/20	150.00	12.00	20.63	20.00
MTCER200-265		Pueblo	05/28/20	200.00	9.00	7.63	5.00
SHER400-373		R4 Signal Head Backplate Inst	05/28/20	80.00	15.00	30.50	50.00
IM025A-048		Northbound I-25 bridge at Exi	05/28/20	100.00	10.00	6.29	6.00
ITSSW01-719		FY 20 ITS CAPITAL REPLACEMENT	06/11/20	200.00	5.00	18.00	25.00
FSAR400-356		FY 20 SIGNAL POLE REPLACEMENT	06/11/20	60.00	10.00	14.17	15.50
SHE016A-043		SH 21 & 16 SIGNALS PROJECT	06/18/20	50.00	10.00	18.51	11.56
NHPPR100-251		SH 2/ Vasquez	06/25/20	350.00	10.00	11.68	11.35
		WEIGHTED AVERAGE FOR THE SECOND QUARTER		4,368.00	8.09	11.95	10.62
		WEIGHTED AVERAGE FOR THE YEAR		12,228.00	8.25	10.98	9.87
=====	630-80384	Tubular Marker		Each =====			
C0853-112		US85 & WCR98 INTERSECTION IMP	05/07/20	20.00	10.00	25.66	28.00
		WEIGHTED AVERAGE FOR THE SECOND QUARTER		20.00	10.00	25.66	28.00
		WEIGHTED AVERAGE FOR THE YEAR		20.00	10.00	25.66	28.00
=====	630-80390	Channel Dev (Spec)		Each =====			
NHPP0702-359		I-70 No Name Tunnel Lighting	02/27/20	150.00	20.00	26.75	26.00
		WEIGHTED AVERAGE FOR THE FIRST QUARTER		150.00	20.00	26.75	26.00
		WEIGHTED AVERAGE FOR THE YEAR		150.00	20.00	26.75	26.00
=====	630-80392	Stackable Tubular Marker		Each =====			
NHPP 0852-116		US85:HAMPDEN TO FLORIDA-RESUR	02/06/20	50.00	20.00	40.00	45.00
		WEIGHTED AVERAGE FOR THE FIRST QUARTER		50.00	20.00	40.00	45.00
		WEIGHTED AVERAGE FOR THE YEAR		50.00	20.00	40.00	45.00

COLORADO DEPARTMENT OF TRANSPORTATION
ITEM UNIT COSTS BY PROJECTS -- 2020 COST DATA

10:58 Friday, October 2, 2020 349

PROJECT NUMBER	ITEM NUMBER/ PROJECT LOCATION	ITEM DESCRIPTION/ PROJECT LOCATION	DATE LET	UNIT/ QUANTITY	ENGR. EST.	AVERAGE BID	AWARDED BID
===== 630-80393		Stackable Vertical Panels		Each			
BR0343-040		US 34 REPUBLICAN RIVER BRIDGE	01/16/20	32.00	35.00	31.62	11.00
FBR0343-043		US 34 D-28-P STRUCTURE REPLAC					
NHPP 0852-116		US85:HAMPDEN TO FLORIDA-RESUR	02/06/20	200.00	25.00	40.00	45.00
STRR300-249		Grand and Jackson Counties AD	03/05/20	60.00	15.00	40.00	50.00
CC080-037		VARIOUS ADA RAMPS ALONG NORTH	03/05/20	60.00	40.00	24.38	50.00
		WEIGHTED AVERAGE FOR THE FIRST QUARTER		352.00	26.76	34.70	43.61
IM0252-473		I-25 CABLE BARRIER PHASE IV	04/09/20	26.00	35.00	27.89	27.78
FBR0343-042		US 34 D-27-G STRUCTURE REPLAC	05/07/20	16.00	35.00	49.49	50.00
SHER400-373		R4 Signal Head Backplate Inst	05/28/20	40.00	25.00	41.50	50.00
SHE016A-043		SH 21 & 16 SIGNALS PROJECT	06/18/20	25.00	35.00	37.98	28.88
NHPPR100-251		SH 2/ Vasquez	06/25/20	75.00	25.00	35.50	34.00
		WEIGHTED AVERAGE FOR THE SECOND QUARTER		182.00	28.68	39.87	37.33
		WEIGHTED AVERAGE FOR THE YEAR		534.00	27.42	36.53	41.47
===== 630-80401		Delin (Ty I) (Temp)		Each			
BR0343-040		US 34 REPUBLICAN RIVER BRIDGE	01/16/20	20.00	50.00	29.96	32.00
FBR0343-043		US 34 D-28-P STRUCTURE REPLAC					
		WEIGHTED AVERAGE FOR THE FIRST QUARTER		20.00	50.00	29.96	32.00
		WEIGHTED AVERAGE FOR THE YEAR		20.00	50.00	29.96	32.00
===== 630-80415		Adv Warn Flash or Seq Panel (C Type)		Day			
NHPP0253-276		I-25 EXPRESS LANES SEGMENT 5	05/15/20	2.00	1600.00	1629.45	1629.45
		WEIGHTED AVERAGE FOR THE SECOND QUARTER		2.00	1600.00	1629.45	1629.45
		WEIGHTED AVERAGE FOR THE YEAR		2.00	1600.00	1629.45	1629.45
===== 630-80417		Seq Flashing Warning Light		Each			
NHPPR100-251		SH 2/ Vasquez	06/25/20	1.00	250.00	82.65	79.30
		WEIGHTED AVERAGE FOR THE SECOND QUARTER		1.00	250.00	82.65	79.30
		WEIGHTED AVERAGE FOR THE YEAR		1.00	250.00	82.65	79.30

PROJECT NUMBER	ITEM NUMBER/ PROJECT LOCATION	ITEM DESCRIPTION/ PROJECT LOCATION	DATE LET	UNIT/ QUANTITY	ENGR. EST.	AVERAGE BID	AWARDED BID
===== 630-80430 Rumble Strip (Port) Each =====							
STR131A-038		SH 131 MP 51.95-55.73, ROUTT	01/16/20	2.00	4000.00	2950.00	2400.00
	WEIGHTED AVERAGE FOR THE FIRST QUARTER			2.00	4000.00	2950.00	2400.00
	WEIGHTED AVERAGE FOR THE YEAR			2.00	4000.00	2950.00	2400.00
===== 630-80440 Port Rumble Strips (Temp) Each =====							
STR2871-038		US 287 Passing Lanes Springfi	03/05/20	24.00	300.00	1436.84	1755.00
NHPP0502-082		US 50 MONTROSE RE CHIP SEAL	03/05/20	24.00	1500.00	296.25	350.00
	WEIGHTED AVERAGE FOR THE FIRST QUARTER			48.00	900.00	676.45	1052.50
STR092A-030		SH92 MP 31.748-48.5, DELTA AND	04/02/20	42.00	1500.00	1397.50	1025.00
STA340A-021		SH340 MP 6-6.76 MESA COUNTY	04/02/20	4.00	900.00	775.00	700.00
	WEIGHTED AVERAGE FOR THE SECOND QUARTER			46.00	1447.83	1319.69	996.74
	WEIGHTED AVERAGE FOR THE YEAR			94.00	1168.09	933.74	1025.21
===== 630-80511 Mobile Pvmt Marking Zone LUMP SUM =====							
SHER500-210		R5 FY19 CENTER LINE RUMBLE ST	01/09/20	1.00	10000.00	31250.00	27500.00
STR131A-038		SH 131 MP 51.95-55.73, ROUTT	01/16/20	1.00	4000.00	3500.00	2500.00
STR141A-044		SH 141 AND SH 145, FROM SLICK	01/30/20	1.00	10000.00	5564.98	5000.00
MTCER500-213		R5 FY 20 / FY 21 STRIPING	02/13/20	1.00	15000.00	42894.50	50000.00
STA069A-033		SH69 MP 58.7 TO 71.58	02/13/20	1.00	9740.00	5401.44	6000.00
NH0242-085		US 24 M.P. 291.38 to M.P. 296	02/27/20	1.00	7300.00	5945.49	4565.00
NHPP0171-105		SH 17 MP 84.5 to US 285 & SH	03/05/20	1.00	18000.00	6030.12	6090.35
C0641-106		SH 64 Meeker West Rural Resur	03/05/20	1.00	10000.00	5500.00	7500.00
NHPP0502-082		US 50 MONTROSE RE CHIP SEAL	03/05/20	1.00	5000.00	14117.74	10000.00
	WEIGHTED AVERAGE FOR THE FIRST QUARTER			9.00	9893.33	14189.02	13239.48
NHPP1602-169		US 160 WC TUNNEL EAST RESURFA	04/02/20	1.00	13000.00	8653.79	8121.46
STR092A-030		SH92 MP 31.748-48.5, DELTA AND	04/02/20	1.00	5000.00	11325.00	15000.00

COLORADO DEPARTMENT OF TRANSPORTATION
ITEM UNIT COSTS BY PROJECTS -- 2020 COST DATA

10:58 Friday, October 2, 2020 351

PROJECT NUMBER	ITEM NUMBER/ PROJECT LOCATION	ITEM DESCRIPTION/ PROJECT LOCATION	DATE LET	UNIT/ QUANTITY	ENGR. EST.	AVERAGE BID	AWARDED BID
===== 630-80511 Mobile Pvmr Marking Zone LUMP SUM =====							
STR0341-101		SH 34 North of Grandby Resurf	04/02/20	1.00	10000.00	20906.12	21500.00
NHPP1601-077		US 160 MP 29.750 - MP 34.891	04/09/20	1.00	10000.00	9666.67	12500.00
NHPP0402-098		US 40 CHIP SEAL MP 126 TO MP	05/14/20	1.00	8000.00	7210.50	3000.00
	WEIGHTED AVERAGE FOR THE SECOND QUARTER			5.00	9200.00	12191.16	12024.29
	WEIGHTED AVERAGE FOR THE YEAR			14.00	9645.71	13475.50	12805.49
===== 630-80520 Mobile Pvmr Mkg Zone Day =====							
STA0142-066		SH 14 New Raymer West	01/09/20	2.00	1050.00	9365.50	8586.00
STA006A-067		SH 6 Merino to Atwood	01/16/20	2.00	1500.00	3090.05	4500.00
STA059A-036		SH 59 SEIBERT TO COPE	02/06/20	7.00	2000.00	4750.00	7500.00
STR116A-001		SH 116 A Surface Treatment Pr	02/13/20	15.00	1500.00	1013.55	300.00
STR0101-027		SH 10 Overlay La Junta West	02/27/20	12.00	1500.00	942.14	1800.00
NHPP0091-044		SH 9 FRISCO MAIN ST TO IRON S	03/05/20	2.00	2000.00	4505.00	5900.00
	WEIGHTED AVERAGE FOR THE FIRST QUARTER			40.00	1590.00	2303.90	2914.30
MTCER200-265		Pueblo	05/28/20	120.00	550.00	328.75	415.00
	WEIGHTED AVERAGE FOR THE SECOND QUARTER			120.00	550.00	328.75	415.00
	WEIGHTED AVERAGE FOR THE YEAR			160.00	810.00	705.13	1039.83
===== 630-85006 Impact Atten (Sand Fill) (Temp) Each =====							
NHPP0253-276		I-25 EXPRESS LANES SEGMENT 5	05/15/20	1.00	5400.00	5431.47	5431.47
	WEIGHTED AVERAGE FOR THE SECOND QUARTER			1.00	5400.00	5431.47	5431.47
	WEIGHTED AVERAGE FOR THE YEAR			1.00	5400.00	5431.47	5431.47
===== 630-85010 Impact Atten (Temp) Each =====							
NHPP0343-041		I-76 & US 34 FT. MORGAN AREA	01/09/20	2.00	4500.00	10067.75	9591.00
BR0343-040		US 34 REPUBLICAN RIVER BRIDGE	01/16/20	8.00	5500.00	7841.33	8000.00
FBR0343-043		US 34 D-28-P STRUCTURE REPLAC					
NH 0503-093		US50 WEST OF TEXAS CREEK MP 2	01/23/20	2.00	3000.00	6200.42	8400.84

PROJECT NUMBER	ITEM NUMBER/ PROJECT LOCATION	ITEM DESCRIPTION/ PROJECT LOCATION	DATE LET	UNIT/ QUANTITY	ENGR. EST.	AVERAGE BID	AWARDED BID
===== 630-85010		Impact Atten (Temp)		Each =====			
NHPP4701-134		C-470 NOISE WALL WEST OF LUCE	02/06/20	1.00	5000.00	6020.00	3500.00
STR116A-001		SH 116 A Surface Treatment Pr	02/13/20	2.00	700.00	2027.15	1300.00
NHPP0702-359		I-70 No Name Tunnel Lighting	02/27/20	1.00	7250.00	3754.25	850.00
NHPP145A-080		SH 145 Keystone-Placerville R	03/05/20	2.00	4000.00	2000.00	2000.00
BR025A-046		K-18-U ON I-25 AT MP112 BRIDG	03/05/20	4.00	5000.00	9502.36	9101.40
NHPP0091-044		SH 9 FRISCO MAIN ST TO IRON S	03/05/20	2.00	5000.00	3716.67	1500.00
NH050A-034		US50A PUEBLO WEST PURCELL INT	03/26/20	50.00	4000.00	7810.97	8900.00
HPP 0501-067		US 50 AND SH 92 DELTA INTERSE	03/26/20	4.00	5000.00	4280.00	4480.00
SHE 0703-461		I-70 and Kipling North Phase	03/26/20	2.00	8000.00	5754.00	4400.00
	WEIGHTED AVERAGE FOR THE FIRST QUARTER			80.00	4333.13	7642.13	7775.74
IM0761-226		I76/SH52 Interchange	04/02/20	10.00	4500.00	7628.18	6890.00
STR0341-101		SH 34 North of Grandby Resurf	04/02/20	1.00	5000.00	3490.72	3500.00
SFTY2254-091		225 Ramp Improvements	04/09/20	2.00	5000.00	10000.00	12500.00
CC0852-106		US-85 LOUVIERS TO MP 191.75	04/23/20	8.00	1200.00	5715.35	3300.00
FBR0852-108		US-85 BETWEEN LOUVIERS AND MP					
FSA1602-159		US 160 AND SH 17 INTERSECTION	04/30/20	4.00	4500.00	4223.67	3220.00
FBR0343-042		US 34 D-27-G STRUCTURE REPLAC	05/07/20	2.00	6500.00	7254.59	8500.00
NHPP0253-276		I-25 EXPRESS LANES SEGMENT 5	05/15/20	9.00	7000.00	7060.91	7060.91
	WEIGHTED AVERAGE FOR THE SECOND QUARTER			36.00	4544.44	6621.73	6034.12
	WEIGHTED AVERAGE FOR THE YEAR			116.00	4398.71	7381.27	7235.24
===== 630-85011		Imp Atten (Temp)		Day =====			
FSA0253-262		I-25 SB BOTTLENECK I-76 TO I-	01/09/20	70.00	50.00	137.48	260.00
STR131A-038		SH 131 MP 51.95-55.73, ROUTT	01/16/20	50.00	100.00	26.25	25.00
NHPP 0852-116		US85:HAMPDEN TO FLORIDA-RESUR	02/06/20	4.00	400.00	200.00	220.00
C0641-106		SH 64 Meeker West Rural Resur	03/05/20	50.00	100.00	100.00	100.00
	WEIGHTED AVERAGE FOR THE FIRST QUARTER			174.00	86.78	103.10	145.57
NHPPR100-251		SH 2/ Vasquez	06/25/20	14.00	250.00	246.51	0.01
	WEIGHTED AVERAGE FOR THE SECOND QUARTER			14.00	250.00	246.51	0.01
	WEIGHTED AVERAGE FOR THE YEAR			188.00	98.94	112.10	134.73
===== 630-85020		Mobile Attenuator		Each =====			
NH 0503-093		US50 WEST OF TEXAS CREEK MP 2	01/23/20	1.00	30000.00	19950.95	18901.90

PROJECT NUMBER	ITEM NUMBER/ PROJECT LOCATION	ITEM DESCRIPTION/ PROJECT LOCATION	DATE LET	UNIT/ QUANTITY	ENGR. EST.	AVERAGE BID	AWARDED BID
===== 630-85020 Mobile Attenuator Each =====							
STR012A-050		CULVERT REPAIR I-25 AND US 35	01/30/20	1.00	16000.00	8600.00	8600.00
ITS0761-231		ITS FIBER AND CAMERAS ON I-76	02/06/20	2.00	20000.00	24410.40	950.00
FSA2873-194		US 287 Longmont Intersection	02/13/20	1.00	4000.00	36114.17	38500.00
STA069A-033		SH69 MP 58.7 TO 71.58	02/13/20	2.00	15000.00	15389.03	16000.00
NHPP0702-359		I-70 No Name Tunnel Lighting	02/27/20	2.00	20000.00	52723.88	10525.00
NH0242-085		US 24 M.P. 291.38 to M.P. 296	02/27/20	2.00	22000.00	40453.01	39925.00
NHPP0091-044		SH 9 FRISCO MAIN ST TO IRON S	03/05/20	1.00	20000.00	62366.67	48500.00
WEIGHTED AVERAGE FOR THE FIRST QUARTER				12.00	18666.67	35561.40	20775.16
=====							
IM0761-226		I76/SH52 Interchange	04/02/20	2.00	13450.00	44263.20	53000.00
STR0341-101		SH 34 North of Grandby Resurf	04/02/20	1.00	20000.00	29354.79	54000.00
IM0252-473		I-25 CABLE BARRIER PHASE IV	04/09/20	2.00	19000.00	7261.11	7222.22
C1211-090		SH-121 & 29th Ave / SH-121 &	04/23/20	1.00	13800.00	28635.00	9010.00
NHPPR100-303		LONG MAST ARM SIGNALS PROJECT	05/07/20	4.00	5000.00	11083.33	10250.00
ITS SW02-303		R1: US 285, SH 83 R2: SH 83,	05/28/20	1.00	25000.00	90427.80	5000.00
WEIGHTED AVERAGE FOR THE SECOND QUARTER				11.00	13063.64	34218.87	20859.49
WEIGHTED AVERAGE FOR THE YEAR				23.00	15986.96	34873.76	20815.49
=====							
===== 630-85040 Impact Atten (T-M-A) (Temp) Each =====							
NHPP0343-041		I-76 & US 34 FT. MORGAN AREA	01/09/20	2.00	17500.00	53705.90	94383.00
NHPP4701-134		C-470 NOISE WALL WEST OF LUCE	02/06/20	1.00	20000.00	11116.00	7700.00
WEIGHTED AVERAGE FOR THE FIRST QUARTER				3.00	18333.33	34346.85	65488.67
=====							
SHER400-373		R4 Signal Head Backplate Inst	05/28/20	4.00	10000.00	48110.00	4100.00
WEIGHTED AVERAGE FOR THE SECOND QUARTER				4.00	10000.00	48110.00	4100.00
WEIGHTED AVERAGE FOR THE YEAR				7.00	13571.43	40141.86	30409.43
=====							
===== 630-85041 Mobile Attenuator Day =====							
FSA0253-262		I-25 SB BOTTLENECK I-76 TO I-	01/09/20	20.00	450.00	419.45	600.00
NHPP0253-265		I-25 AT ERIE PARKWAY ON AND O	01/09/20	40.00	385.00	378.33	525.00

PROJECT NUMBER	ITEM NUMBER/ PROJECT LOCATION	ITEM DESCRIPTION/ PROJECT LOCATION	DATE LET	UNIT/ QUANTITY	ENGR. EST.	AVERAGE BID	AWARDED BID
===== 630-85041 Mobile Attenuator Day =====							
NHPP 0852-116		US85:HAMPDEN TO FLORIDA-RESUR	02/06/20	180.00	400.00	550.00	600.00
STA0703-443		I-70 EJMT TUNNELS PAVING	02/06/20	40.00	500.00	474.87	596.18
STR0101-027		SH 10 Overlay La Junta West	02/27/20	10.00	700.00	719.28	800.00
BR025A-046		K-18-U ON I-25 AT MP112 BRIDG	03/05/20	30.00	400.00	624.06	568.84
SHE 0703-461		I-70 and Kipling North Phase	03/26/20	75.00	400.00	591.20	450.00
WEIGHTED AVERAGE FOR THE FIRST QUARTER				395.00	418.73	551.33	566.23
STA340A-021		SH340 MP 6-6.76 MESA COUNTY	04/02/20	35.00	350.00	325.67	2.00
SHER100-339		WWD TRAFFIC CONTROL ENHANCEME	04/09/20	450.00	400.00	300.00	300.00
NHPP1601-077		US 160 MP 29.750 - MP 34.891	04/09/20	25.00	650.00	366.67	200.00
SFTY2254-091		225 Ramp Improvements	04/09/20	25.00	25000.00	952.50	1155.00
CC0852-106		US-85 LOUVIERS TO MP 191.75	04/23/20	20.00	600.00	611.98	660.00
FBR0852-108		US-85 BETWEEN LOUVIERS AND MP					
ITS SW02-304		ITS FIBER TO STATE BUILDINGS	05/14/20	150.00	750.00	514.25	121.00
NHPP0253-276		I-25 EXPRESS LANES SEGMENT 5	05/15/20	20.00	500.00	543.14	543.14
MTCER200-265		Pueblo	05/28/20	30.00	425.00	237.50	100.00
ITSSW01-719		FY 20 ITS CAPITAL REPLACEMENT	06/11/20	55.00	650.00	427.50	250.00
FSAR400-356		FY 20 SIGNAL POLE REPLACEMENT	06/11/20	55.00	400.00	435.00	205.00
SHE016A-043		SH 21 & 16 SIGNALS PROJECT	06/18/20	30.00	300.00	464.36	577.80
NHPPR100-251		SH 2/ Vasquez	06/25/20	60.00	425.00	475.78	211.55
WEIGHTED AVERAGE FOR THE SECOND QUARTER				955.00	1123.56	440.33	281.90
WEIGHTED AVERAGE FOR THE YEAR				1,350.00	917.33	481.13	365.09
===== 630-86801 Traffic Signal (Temp) LUMP SUM =====							
NHPP0343-041		I-76 & US 34 FT. MORGAN AREA	01/09/20	1.00	30000.00	40031.55	8462.00
NH050A-034		US50A PUEBLO WEST PURCELL INT	03/26/20	1.00	14000.00	61800.00	48000.00
WEIGHTED AVERAGE FOR THE FIRST QUARTER				2.00	19333.33	58362.88	34820.67
STR092A-030		SH92 MP 31.748-48.5, DELTA AND	04/02/20	1.00	10000.00	22505.00	25000.00
STA340A-021		SH340 MP 6-6.76 MESA COUNTY	04/02/20	1.00	10000.00	9633.33	12000.00
CC0852-106		US-85 LOUVIERS TO MP 191.75	04/23/20	1.00	25000.00	81471.16	79200.00
FBR0852-108		US-85 BETWEEN LOUVIERS AND MP					
WEIGHTED AVERAGE FOR THE SECOND QUARTER				3.00	15000.00	55821.48	38733.33
WEIGHTED AVERAGE FOR THE YEAR				5.00	17166.67	57330.44	36777.00

COLORADO DEPARTMENT OF TRANSPORTATION
 ITEM UNIT COSTS BY PROJECTS -- 2020 COST DATA

10:58 Friday, October 2, 2020 355

PROJECT NUMBER	ITEM NUMBER/ PROJECT LOCATION	ITEM DESCRIPTION/ PROJECT LOCATION	DATE LET	UNIT/ QUANTITY	ENGR. EST.	AVERAGE BID	AWARDED BID
===== 630-86810		Traffic Signal (Temp)		Each	=====		
STA0703-443		I-70 EJMT TUNNELS PAVING	02/06/20	1.00	20000.00	29435.56	33121.12
STA059A-036		SH 59 SEIBERT TO COPE	02/06/20	2.00	17000.00	18000.00	16000.00
STA069A-033		SH69 MP 58.7 TO 71.58	02/13/20	4.00	18000.00	6430.62	6000.00
NHPP145A-080		SH 145 Keystone-Placerville R	03/05/20	1.00	15000.00	16000.00	16000.00
		WEIGHTED AVERAGE FOR THE FIRST QUARTER		8.00	17625.00	13221.07	13140.14
IM0761-226		I76/SH52 Interchange	04/02/20	2.00	17000.00	34249.66	37100.00
		WEIGHTED AVERAGE FOR THE SECOND QUARTER		2.00	17000.00	34249.66	37100.00
		WEIGHTED AVERAGE FOR THE YEAR		10.00	17500.00	23372.80	17932.11
===== 632-00000		Night Work Lighting		LUMP SUM	=====		
NHPP 0852-116		US85:HAMPDEN TO FLORIDA-RESUR	02/06/20	1.00	50000.00	80190.30	100000.00
FSA2873-194		US 287 Longmont Intersection	02/13/20	1.00	8000.00	22726.67	19360.00
NH0242-085		US 24 M.P. 291.38 to M.P. 296	02/27/20	1.00	28000.00	52522.67	67500.00
BR025A-046		K-18-U ON I-25 AT MP112 BRIDG	03/05/20	1.00	10000.00	31348.87	17760.28
NHPP0091-044		SH 9 FRISCO MAIN ST TO IRON S	03/05/20	1.00	60000.00	158466.67	75100.00
HPP 0501-067		US 50 AND SH 92 DELTA INTERSE	03/26/20	1.00	30000.00	21919.13	33900.00
SHE 0703-461		I-70 and Kipling North Phase	03/26/20	1.00	25000.00	36850.00	68310.00
		WEIGHTED AVERAGE FOR THE FIRST QUARTER		7.00	30142.86	49187.10	54561.47
IM0252-473		I-25 CABLE BARRIER PHASE IV	04/09/20	1.00	10000.00	32500.00	25000.00
SFTY2254-091		225 Ramp Improvements	04/09/20	1.00	25000.00	47000.00	30000.00
C1601-082		Hawkins Signal and Curb Ramps	04/30/20	1.00	1500.00	16883.33	1650.00
NHPPR100-303		LONG MAST ARM SIGNALS PROJECT	05/07/20	1.00	17500.00	6643.33	4365.00
NHPP0402-098		US 40 CHIP SEAL MP 126 TO MP	05/14/20	1.00	10000.00	10526.67	25000.00
NHPP0253-276		I-25 EXPRESS LANES SEGMENT 5	05/15/20	1.00	46300.00	26308.77	26308.77
NHPPR100-251		SH 2/ Vasquez	06/25/20	1.00	15000.00	15095.35	5908.70
		WEIGHTED AVERAGE FOR THE SECOND QUARTER		7.00	17900.00	19853.72	16890.35
		WEIGHTED AVERAGE FOR THE YEAR		14.00	24021.43	38520.42	35725.91