



COLORADO

Department of Transportation

2022 Cost Data (January – December)

Compiled By:

Cost Estimating Services Unit of the
Construction Engineering Services Branch

March 07, 2023

2022 Cost Data: Construction

Table of Contents

Number
of Pages

List of 2022 Bid Projects.....	7
Bridge Cost per Square Feet	1
Item Unit Costs by Projects.....	665

Colorado Cost Data

Foreword

The Colorado Department of Transportation's Cost Estimating Services Unit of the Construction Engineering Services Branch publishes the Cost Data Book annually. A joint effort has been made between CDOT's sections and the Cost Estimating Services Unit to gather and record cost data for this publication.

The following data includes weighted average prices for items on highway construction projects that were bid during the 2022 calendar year. Caution should be used in applying these historical averages to specific projects. Allowances for varying geographic, climatic, social, economic conditions and type of project should be made.

Changes and improvements are continually being made to update and increase the usefulness for future issues. Comments and suggestions for improvements for users of this publication are welcome.

Colorado Department of Transportation
 2022 Cost Data
 PROJECTS BID FROM 01/01/22 THROUGH 12/31/22

19:22 Tuesday, March 7, 2023 1

BID LETTING	CONTRACTOR/ PROJECT NUMBER	LOCATION	DIST	TERRAIN	BIDS	AWARDED BID	INDEX
20220106	BRANNAN SAND AND GRAVEL, LLC NHPP2873-189	US 287 (FEDERAL BLVD) - COLFAX	1	U	4	\$4,704,411.40	106.92
20220106	STURGEON ELECTRIC COMPANY, INC ITS0703-477	ITS EQUIPMENT UPGRADE AT EJMT	00	M	1	\$8,447,636.00	163.49
20220106	ROADSAFE TRAFFIC SYSTEMS, INC MTCE R500-218		5	U	2	\$1,168,613.00	87.75
20220106	Straight Stripe Painting, Inc. MTCE R500-219		5	R	3	\$2,256,065.00	102.19
20220113	INTERMOUNTAIN SLURRY SEAL, INC. STR0505-050		2	P	3	\$2,019,305.00	91.60
20220113	AMES CONSTRUCTION, INC. NHPP0702-383	I-70 EB AUX FRISCO TO SILVERTH	3	M	5	\$26,917,300.00	119.30
20220113	TRICON 2, LLC NH0504-910	US50B L-24-B MIN REP AT MP 406	2	P	8	\$1,697,000.00	80.81
20220113	ROADSAFE TRAFFIC SYSTEMS, INC MTCER400-391	VARIOUS HIGHWAY SEGMENTS ACROS	4	R	4	\$1,564,170.00	101.46
20220203	Myers & Sons Construction, LLC STA0252-459		1	R	3	\$6,297,433.64	131.20
20220203	A and S CONSTRUCTION CO. NHPP1601-083		5	R	2	\$21,890,679.16	120.85
20220203	CC ENTRPRS TRAFFIC CONTROL SPECIALISTS MTCER300-262		3	M	3	\$1,742,097.00	82.96
20220217	MCATEE CONSTRUCTION CO. C0762-055		4	R	4	\$13,997,628.23	109.36
20220217	MCATEE CONSTRUCTION CO. STR0141-031		3	M	3	\$5,420,000.00	92.36
20220217	OLDCASTLE SW GROUP, INC. STR133A-051		3	R	3	\$1,540,725.10	123.76
20220224	OLDCASTLE SW GROUP, INC. NHPP0063-063		3	U	2	\$9,208,179.50	125.31
20220303	A and S CONSTRUCTION CO. STA 067A-048	Hwy 67A MP 0.00 TO MP 11.05 IN	2	R	3	\$4,623,000.00	102.73
20220310	BRANNAN SAND AND GRAVEL, LLC NHPP0703-472		1	U	4	\$8,027,827.75	101.50

Colorado Department of Transportation
2022 Cost Data
PROJECTS BID FROM 01/01/22 THROUGH 12/31/22

19:22 Tuesday, March 7, 2023 2

BID LETTING	CONTRACTOR/ PROJECT NUMBER	LOCATION	DIST	TERRAIN	BIDS	AWARDED BID	INDEX
20220310	FLATIRON CONSTRUCTORS, INC. C0761-239 NHPP 0761-238	I-76 DAHLIA TO YORK	1 1	R R	8	\$25,426,004.45	87.29
20220311	RLW/SEMA, A Joint Venture NHPP0253-275	I-25 EXPRESS LANES SEGMENT 5 &	4	R	1	\$6,514,608.17	111.89
20220314	IHC Scott, Inc. CR100-362		1	U	1	\$4,644,427.21	100.00
20220315	KIEWIT INFRASTRUCTURE CO. ER007A-035		4	M	1	\$5,520,588.70	107.47
20220317	KSK, LLC STR R500-171	Various locations on SH 141 an	5	R	3	\$1,400,000.00	86.60
20220317	OLDCASTLE SW GROUP, INC. STR160A-034	US160A LA VETA PASS EAST SURFA	2	M	2	\$8,614,391.16	99.02
20220317	Myers & Sons Construction, LLC BRC040-057		2	U	4	\$4,120,979.48	124.88
20220317	OLDCASTLE SW GROUP, INC. STR092A-031		3	R	1	\$7,346,956.34	97.35
20220317	KRAEMER NORTH AMERICA, LLC M R100-351	FY22 R1 SIGN STRUCTURE REPLACE	1	U	2	\$1,217,455.60	101.45
20220324	MORTON ELECTRIC, INC. MP0503-098		2	U	2	\$646,748.00	77.92
20220331	CASTLE ROCK CONST. CO. OF COLO, LLC NHM765-007		2	U	3	\$13,605,608.18	102.30
20220331	ABCO CONTRACTING, INC. C0703-499	EJMT GROUT BED REPAIR AND PANE	1	M	2	\$1,341,361.00	148.29
20220407	MARTIN MARIETTA MATERIALS NH0504-911		2	P	2	\$17,781,881.53	107.77
20220414	KSK, LLC CC030-081	ADA RAMP AND CURBS - FT. LUPTO	4	U	3	\$2,035,000.00	82.70
20220418	KIEWIT INFRASTRUCTURE CO. NHPP0702-413	VAIL PASS AUX PHASE 1 CAP 2	3	M	1	\$21,966,094.79	100.00
20220421	CASTLE ROCK CONST. CO. OF COLO, LLC STM1151-038	SH115 MP 27 TO MP 38	2	R	5	\$39,607,433.98	120.02
20220505	RALPH L. WADSWORTH CONSTRUCTION CO., LLC MTCE2873-204	MTCE FY22 SH287 CONC PANEL REP	4	U	2	\$693,896.87	98.15

Colorado Department of Transportation
 2022 Cost Data
 PROJECTS BID FROM 01/01/22 THROUGH 12/31/22

19:22 Tuesday, March 7, 2023 3

BID LETTING	CONTRACTOR/ PROJECT NUMBER	LOCATION	DIST	TERRAIN	BIDS	AWARDED BID	INDEX
20220505	AMERICAN CIVIL CONSTRUCTORS, LLC dba A 2670703-479	I-70 BRIDGE OVER HARLAN	1	R	6	\$17,879,000.00	107.64
20220506	LAWRENCE CONSTRUCTION CO. ER0702-420	PR I-70 GWC MATERIAL FLOWS 202	3	M	2	\$3,888,046.00	121.16
20220512	INTERFACE COMMUNICATIONS COMPANY CM760-047	COLFAX AND QUAIL	1	U	5	\$706,289.00	130.08
20220512	IHC Scott, Inc. STA0712-019	SH 71: Frieght Improvements	4	P	1	\$11,946,689.77	111.68
20220512	ZAK DIRT, INC. NHC540-017	R2 CHAINUP STA @ KENOSHA/HOOSI	2	M	3	\$7,334,391.55	112.84
20220512	COULSON EXCAVATING COMPANY STA001A-005	SH1 WELLINGTON SOUTH RESURFACI	4	P	2	\$5,897,002.35	80.69
20220526	A and S CONSTRUCTION CO. NHPP 3851-018	US 385 NORTH OF CHEYENNE WELLS	4	P	2	\$13,523,000.00	109.88
20220526	CC ENTRPRS TRAFFIC CONTROL SPECIALISTS FSA0702-409	I-70 VAIL WILDLIFE FENCE PHASE	3	M	1	\$3,032,752.00	98.81
20220526	AMERICAN WEST CONSTRUCTION, LLC C0852-120	Rehabilitation of Culvert by s	1	R	1	\$749,206.00	68.11
20220526	STRUCTURES, INC. STAR100-358	3 STRUCTURES IN REGION 1 METRO	1	U	3	\$1,580,730.00	66.09
20220602	MOUNTAIN CONSTRUCTORS, INC. FSA3921-019	SH 392 AND WCR 55 ISLANDS	4	P	3	\$174,037.00	105.44
20220602	MORTON ELECTRIC, INC. ITS 0741-024	VMS SIGN INSTALLATIONS AND VSL	1	M	2	\$2,152,940.00	142.77
20220609	AB Underground FSA052A-046	SH52 WCR 37 INTERSECTION IMPRO	4	R	5	\$3,098,847.35	84.58
20220609	BRANNAN SAND AND GRAVEL, LLC NHPP072A-047	SH-72 RESURFACING: I-70 TO IND	1	R	1	\$8,097,793.64	112.67
20220609	ROADSAFE TRAFFIC SYSTEMS, INC MPR200-278	R2 - VARIOUS LOCATIONS	2	R	3	\$2,824,931.56	95.98
20220609	ROADSAFE TRAFFIC SYSTEMS, INC MPR200-279	FY 23 STENCIL MARKING PROJECT	2	R	3	\$448,255.86	93.48
20220616	RALPH L. WADSWORTH CONSTRUCTION CO., LLC MTCE0253-291	I-25 SIGN REPLACEMENT PHASE 2B	4	R	2	\$2,499,779.84	131.35

Colorado Department of Transportation
 2022 Cost Data
 PROJECTS BID FROM 01/01/22 THROUGH 12/31/22

19:22 Tuesday, March 7, 2023 4

BID LETTING	CONTRACTOR/ PROJECT NUMBER	LOCATION	DIST	TERRAIN	BIDS	AWARDED BID	INDEX
20220623	THE TRUESDELL CORPORATION NHPP0252-448	I-25 TREX NARROWS BRIDGE PREVE	1	U	4	\$2,827,827.00	94.26
20220630	ROADSAFE TRAFFIC SYSTEMS, INC MTCE R100-380	REGION 1 FY 23/24 PAVEMENT MAR	1	U	1	\$11,849,087.88	98.74
20220707	A-1 CHIPSEAL COMPANY MTCE 072A-045	SH 72B MP 37.00 TO MP 45.3 NEA	4	M	1	\$1,096,643.80	95.41
20220707	AMERICAN STRIPING COMPANY LLC MTCE0702-426	I70 FROM MP 155 TO 180 AND MP	3	M	4	\$693,730.00	91.82
20220707	KOLBE STRIPING INC. MTCER300-272	REGION 3 ROUNDABOUT STRIPING A	3	M	3	\$324,225.00	89.44
20220707	KOLBE STRIPING INC. MTCER300-273	I-70 MM 75-116, OTHER REGION 3	3	M	3	\$1,518,388.73	97.40
20220708	KIEWIT INFRASTRUCTURE CO. FBR0702-423 NHPP0702-414	VAIL PASS AUX BE F-12-AT PHASE VAIL PASS AUX PHASE 1 CAP 3	3 3	M M	1	\$47,957,757.02	100.00
20220804	MOUNTAIN CONSTRUCTORS, INC. FSA052A-057	SH52 BOX CULVERT EXTENSION (MP	4	R	3	\$704,678.03	108.34
20220804	TLM CONSTRUCTORS, INC. STR0711-022	SH 71 OVER THE ARKANSAS	2	P	3	\$572,763.00	115.71
20220818	OLDCASTLE SW GROUP, INC. NHPP0063-054	US 6 FROM I70-B TO 33 RD. (MP	3	R	2	\$16,532,414.25	107.63
20220825	ZAK DIRT, INC. FBR0761-236	I-76 OVER CLR CRK SCOUR MIT	1	R	3	\$1,677,136.45	83.86
20220825	STURGEON ELECTRIC COMPANY, INC C1211-099	SH 121 NORTH SGA SIGNALS	1	U	2	\$3,855,000.00	80.00
20220825	AMERICAN STRIPING COMPANY LLC MTCER400-396	REGION 4	4	R	3	\$1,225,327.30	87.91
20220829	WILLIAMS CONSTRUCTION CONTRACTORS ER0502-092	US 50 MP 204 EB MONARCH TRUCK	5	M	3	\$1,024,007.51	87.33
20220831	LAWRENCE CONSTRUCTION CO. BR0343-046 FBR0343-047	US 34 TIMBER BRIDGE REPL. PKG. US 6/US 34 TIMBER BRIDGE REPL.	4 4	P P	1	\$4,432,957.09	103.02
20220901	STRUCTURES, INC. NHPPR100-266	R1 ESSENTIAL REPAIRS	1	U	3	\$3,070,798.76	133.51
20220901	CRUZ CONSTRUCTION, INC. PAN0761-245	ALONG I-76 & RAMPS MILEPOST 95	4	P	2	\$348,232.00	110.33

Colorado Department of Transportation
 2022 Cost Data
 PROJECTS BID FROM 01/01/22 THROUGH 12/31/22

19:22 Tuesday, March 7, 2023 5

BID LETTING	CONTRACTOR/ PROJECT NUMBER	LOCATION	DIST	TERRAIN	BIDS	AWARDED BID	INDEX
20220901	STRUCTURES, INC. STAR100-374	5 STRUCTURES IN REGION 1	1	U	1	\$2,745,838.90	130.43
20220914	RALPH L. WADSWORTH CONSTRUCTION CO., LLC ERO253-297	WCR 34 BRIDGE OVER I-25 (MM 245	4	R	4	\$224,907.20	54.37
20220915	VILLALOBOS CONCRETE INC. SHE2873-193	US 287 & CO 52 INTERSECTION IM	4	R	6	\$5,138,361.59	86.17
20220915	LAWRENCE CONSTRUCTION CO. 2670703-497	I-70_GENESEE WILDLIFE XING	1	M	7	\$9,900,432.72	99.00
20220915	AMERICAN CIVIL CONSTRUCTORS, LLC dba A 2670403-065	US40_FLOYD HILL ROUNDABOUTS	1	M	3	\$9,157,473.00	109.66
20220929	KSK, LLC NHPP0701-231	I-70 SALT WASH BRIDGES SCOUR	3	R	2	\$3,300,000.00	77.89
20221006	ABCO CONTRACTING, INC. MTCE0253-281	MTCE FY23 I-25 CONC PANEL REPL	4	R	4	\$1,351,993.00	107.06
20221013	Kilgore Companies, LLC dba Elam NHPP0821-114	Construc SH 82 ASPEN/INDEPENDENCE PASS	3	M	3	\$1,165,615.42	85.25
20221013	WORK ZONE TRAFFIC CONTROL, LLC C0831-126	SH83 EL PASO COUNTY TO BAYOU G	1	R	2	\$512,963.00	102.17
20221027	SIMON CONTRACTORS STA3852-015	US 385 HOLYOKE NORTH	4	P	1	\$16,494,822.00	103.14
20221027	MARTIN MARIETTA MATERIALS STA207A-004	Resurfacing SH207A MANZANOLA (2	P	3	\$6,049,464.37	100.82
20221027	ZAK DIRT, INC. TRG0253-264	I-25 AND SH 119 PARK-N-RIDE	4	U	8	\$13,166,577.55	101.32
20221027	ABCO CONTRACTING, INC. NHPP0705-088	I-70 AGATE STRUCTURE REHAB	4	P	4	\$5,098,771.00	105.76
20221027	Geovert, LLC C5502-111	US 550 MP 81 AND 89 RED MOUNTA	5	M	2	\$744,942.00	132.84
20221027	TRICON 2, LLC C170A-002	CRITICAL CULVERT CONST. PKG D	4	U	4	\$679,000.00	88.68
20221027	OLDCASTLE SW GROUP, INC. NHPP0701-253	I-70 EAST OF DEBEQUE	3	R	2	\$5,028,719.80	86.05
20221027	ARROW ELECTRIC SERVICE, INC. FSAM240-200	SH21B CO SPRINGS SIGNAL REPLAC	2	P	4	\$2,720,098.85	100.74

Colorado Department of Transportation
2022 Cost Data
PROJECTS BID FROM 01/01/22 THROUGH 12/31/22

19:22 Tuesday, March 7, 2023 6

BID LETTING	CONTRACTOR/ PROJECT NUMBER	LOCATION	DIST	TERRAIN	BIDS	AWARDED BID	INDEX
20221101	LAWRENCE CONSTRUCTION CO. NHPP0343-048	US 34 (MP 169.3-171.4)	4	P	4	\$2,191,362.00	70.77
20221103	AMES CONSTRUCTION, INC. STU0252-457	I-25:ALAMEDA RIVER PH 2.0	1	U	3	\$22,317,300.00	90.58
20221103	TEZAK HEAVY EQUIPMENT CO., INC. SHE0242-087	US 24 SAFETY IMPRVMENTS, E OF F	2	M	3	\$2,097,272.44	110.38
20221110	ASPHALT SPECIALTIES CO., INC. NHPP0853-126	US85C: PLATTEVILLE NORTH MP (2	4	P	5	\$5,111,254.25	74.46
20221110	OLDCASTLE SW GROUP, INC. STR064A-010	SH 64 AND SH 13 AT MEEKER	3	M	2	\$6,203,531.45	90.31
20221117	Kilgore Companies, LLC dba Elam C5502-097	Construc US550 MP 117.28-126.06	3	R	3	\$18,991,815.84	99.30
20221117	ARROW ELECTRIC SERVICE, INC. STRC090-011	US 50B AND SH71/CR18 INTERSECT	2	R	2	\$2,854,417.85	124.11
20221117	WORK ZONE TRAFFIC CONTROL, LLC MPR200-280	PUEBLO AREA	2	R	2	\$894,364.00	99.37
20221201	AMERICAN CIVIL CONSTRUCTORS, LLC dba A BR2854-148 STAM420-001 STM0091-046	INTERSECTION OF US 285 & SH 9 US 285 AT HWY 9C IMPROVEMENTS ADA RAMP IMPROVEMENTS - FAIRPL	2 2 2	R R M	4	\$24,091,000.00	133.10
20221201	STRUCTURES, INC. STR109A-019	M-22-AY BRIDGE REHAB ON SH109	2	R	2	\$5,635,899.39	98.88
20221201	Kilgore Companies, LLC dba Elam STR318A-001	Construc SH 318 MP 0 - 12.5 MOFFAT COUN	3	R	2	\$6,686,562.84	98.21
20221201	BRANNAN SAND AND GRAVEL, LLC NHPP0021-041	SH2 RESURFACING MLK TO 52ND	1	U	4	\$3,269,122.13	86.60
20221201	A and S CONSTRUCTION CO. STR114A-015	SH114 SILLSVILLE SOUTH TO MP30	3	M	2	\$14,324,912.69	86.49
20221201	A and S CONSTRUCTION CO. STA0711-021	SH71: REGION LINE NORTH	4	P	3	\$14,314,966.60	85.12
20221201	Myers & Sons Construction, LLC NHPP0701-252	I-70 RIFLE TO SILT SLAB REPLAC	3	M	2	\$7,080,420.17	66.99
20221201	OLDCASTLE SW GROUP, INC. STR0641-107	SH 13 MM 104-128.1 IN MOFFAT C	3	R	3	\$3,297,815.15	91.83
20221201	SEMA CONSTRUCTION, INC. IM025A-050	I25-MP103.9 - INTERSECTION DRE	2		3	\$10,512,989.35	126.66

Colorado Department of Transportation
 2022 Cost Data
 PROJECTS BID FROM 01/01/22 THROUGH 12/31/22

19:22 Tuesday, March 7, 2023 7

BID LETTING	CONTRACTOR/ PROJECT NUMBER	LOCATION	DIST	TERRAIN	BIDS	AWARDED BID	INDEX	
20221201	Lobato Construction, LLC 2670703-487	I-70 BRIDGES OVER WARD ROAD- B	1	U	5	\$16,387,878.20	101.16	
20221208	BRANNAN SAND AND GRAVEL, LLC NHPP083A-046	SH83 RESURFACING STROH RD TO H	1	R	2	\$3,893,820.48	97.35	
20221215	OLDCASTLE SW GROUP, INC. NHPP0063-048	US6 / 20 ROAD INTERSECTION IMP	3	R	4	\$3,776,448.13	86.54	
20221215	OLDCASTLE SW GROUP, INC. NHPP0931-033	SH93:US6 TO 58TH RESURFACING	1	R	4	\$5,039,495.35	75.72	
20221215	GENEVA ROCK PRODUCTS, INC. NHM175-029	CANON CITY, CO	2	U	2	\$2,012,665.10	105.93	
20221215	MOUNTAIN CONSTRUCTORS, INC. FSA0853-122	WCR14.5 AND US-85, FORT LUPTON	4	R	3	\$289,870.00	82.11	
20221222	TRICON 2, LLC STA385A-016	SH 385 MP 97.76	2	P	4	\$3,775,000.00	126.41	
20221222	Siete, Inc. BR012A-048	CO 12 STRUCTURE P-17-F AT MP 4	2	M	2	\$4,696,233.75	111.82	
20221222	IHC Scott, Inc. NHPP0502-090	SH 50 MP 134.6-136 GUNNISON CO	3	R	5	\$7,499,484.80	96.53	
20221222	MARTIN MARIETTA MATERIALS STA0361-129	US 36: HYGIENE RD AND NELSON R	4	U	5	\$3,618,938.30	78.23	
20221222	Kilgore Companies, LLC dba Elam STR0092-024	Construc SH 9 North of Silverthorne	3	M	2	\$6,632,329.84	96.72	
20221222	A and S CONSTRUCTION CO. STR096A-050	SH 96 MP 168.99 TO 193.77	2	P	3	\$12,723,069.27	123.52	
					=====	=====	=====	
					TOTALS	337	\$773,250,391.75	102.53

Colorado Department of Transportation
 2022 Cost Data
 BRIDGE COST PER SQUARE FOOT
 (01/01/22 THROUGH 12/31/22)

19:22 Tuesday, March 7, 2023 1

DATE LET	PROJECT NUMBER/ PROJECT LOCATION	TERR/ BRIDGE ID	LENGTH	WIDTH	TOTAL SQUARE FT	TOTAL COST	COST PER SQUARE FOOT
BRIDGE REPAIR							
220317	STR R500-171 Various locations on SH 141 an	R K-02-C L-02-B K-01-A	117.4200 103.4200 243.6500	24.0000 28.0000 24.0000	2818.1 2895.8 5847.6	\$133,594 \$109,396 \$202,464	\$47.41 \$37.78 \$34.62
220914	ER0253-297 WCR 34 BRIDGE OVER I-25 (MM 245	R 0300	223.0000	30.0000	6690.0	\$46,840	\$7.00
221201	STA0711-021 SH71: REGION LINE NORTH	P 0300	70.0000	32.0000	2240.0	\$100,994	\$45.09
			WEIGHTED AVERAGE COST: NEW STRUCTURES		20491.4	\$593,288	\$28.95
BRIDGE WIDENING							
221103	STU0252-457 I-25:ALAMEDA RIVER PH 2.0	U 0300	189.0000	142.0000	26838.0	\$9,710,150	\$361.81
			WEIGHTED AVERAGE COST: NEW STRUCTURES		26838.0	\$9,710,150	\$361.81
CONCRETE SLAB AND GIRDER							
220421	STM1151-038 SH115 MP 27 TO MP 38	R J-17-A	94.0000	30.0000	2820.0	\$2,445,085	\$867.05
			WEIGHTED AVERAGE COST: NEW STRUCTURES		2820.0	\$2,445,085	\$867.05
MAJOR STRUCTURE CBC OR PIPES							
221027	STA207A-004 Resurfacing SH207A MANZANOLA (P L-21-BK	21.7000	60.0000	1302.0	\$558,912	\$429.27
221222	STA385A-016 SH 385 MP 97.76	P 0300	26.5000	92.6700	2455.8	\$892,100	\$363.27
			WEIGHTED AVERAGE COST: NEW STRUCTURES		3757.8	\$1,451,012	\$386.14
MISCELLANEOUS							
220708	FBR0702-423 VAIL PASS AUX BE F-12-AT PHASE	M 0300	600.0000	52.0000	31200.0	\$8,819,532	\$282.68
			WEIGHTED AVERAGE COST: NEW STRUCTURES		31200.0	\$8,819,532	\$282.68

COLORADO DEPARTMENT OF TRANSPORTATION
ITEM UNIT COSTS BY PROJECTS -- 2022 COST DATA

11:31 Wednesday, March 8, 2023 1

PROJECT NUMBER	ITEM NUMBER/ PROJECT LOCATION	ITEM DESCRIPTION/ PROJECT LOCATION	DATE LET	UNIT/ QUANTITY	ENGR. EST.	AVERAGE BID	AWARDED BID
=====	201-00000	Clear and Grub		LUMP SUM	=====		
NHPP0702-383		I-70 EB AUX FRISCO TO SILVERT	01/13/22	1.00	160000.00	249794.77	251778.00
NHPP1601-083			02/03/22	1.00	15000.00	100098.69	80000.00
STA0252-459			02/03/22	1.00	119152.17	47566.67	8700.00
STR0141-031			02/17/22	1.00	25000.00	25300.00	12900.00
NHPP0063-063			02/24/22	1.00	20000.00	4875.00	5000.00
CR100-362			03/14/22	1.00	84573.11	84573.11	84573.11
BRC040-057			03/17/22	1.00	12500.00	33000.00	22000.00
M R100-351		FY22 R1 SIGN STRUCTURE REPLAC	03/17/22	1.00	20000.00	2704.50	1709.00
		WEIGHTED AVERAGE FOR THE FIRST QUARTER		8.00	57028.16	86341.06	58332.51
NH0504-911			04/07/22	1.00	10000.00	12150.00	19300.00
NHPP0702-413		VAIL PASS AUX PHASE 1 CAP 2	04/18/22	1.00	108053.02	108053.02	108053.02
STM1151-038		SH115 MP 27 TO MP 38	04/21/22	1.00	100000.00	243401.38	182927.55
2670703-479		I-70 BRIDGE OVER HARLAN	05/05/22	1.00	80000.05	61000.32	21423.73
NHC540-017		R2 CHAINUP STA @ KENOSHA/HOOS	05/12/22	1.00	25000.00	156101.33	193304.00
NHPP 3851-018		US 385 NORTH OF CHEYENNE WELL	05/26/22	1.00	10000.00	31500.00	24000.00
FSA0702-409		I-70 VAIL WILDLIFE FENCE PHAS	05/26/22	1.00	30000.00	13500.00	13500.00
FSA3921-019		SH 392 AND WCR 55 ISLANDS	06/02/22	1.00	2000.00	6484.00	9000.00
FSA052A-046		SH52 WCR 37 INTERSECTION IMPR	06/09/22	1.00	40000.00	38718.17	11350.00
		WEIGHTED AVERAGE FOR THE SECOND QUARTER		9.00	45005.90	88328.88	64762.03
NHPP0702-414		VAIL PASS AUX PHASE 1 CAP 3	07/08/22	1.00	92027.89	92027.89	92027.89
FBR0702-423		VAIL PASS AUX BE F-12-AT PHAS					
NHPP0063-054		US 6 FROM I70-B TO 33 RD. (MP	08/18/22	1.00	20000.00	66654.52	100000.00
C1211-099		SH 121 NORTH SGA SIGNALS	08/25/22	1.00	40000.00	22500.00	20000.00
ER0502-092		US 50 MP 204 EB MONARCH TRUCK	08/29/22	1.00	5000.00	39566.62	8699.87
BR0343-046		US 34 TIMBER BRIDGE REPL. PKG	08/31/22	1.00	5061.04	9470.36	9470.36
FBR0343-047		US 6/US 34 TIMBER BRIDGE REPL					
2670403-065		US40_FLOYD HILL ROUNDABOUTS	09/15/22	1.00	20000.00	66170.75	30000.00
2670703-497		I-70_GENESEE WILDLIFE KING	09/15/22	1.00	80000.00	86034.54	21041.78
SHE2873-193		US 287 & CO 52 INTERSECTION I	09/15/22	1.00	5000.00	75609.63	13000.00
NHPP0701-231		I-70 SALT WASH BRIDGES SCOUR	09/29/22	1.00	70000.00	52375.00	54750.00
		WEIGHTED AVERAGE FOR THE THIRD QUARTER		9.00	34215.00	65098.85	38776.66
FSAM240-200		SH21B CO SPRINGS SIGNAL REPLA	10/27/22	1.00	10000.00	22445.00	2500.00

PROJECT NUMBER	ITEM NUMBER/ PROJECT LOCATION	ITEM DESCRIPTION/ PROJECT LOCATION	DATE LET	UNIT/ QUANTITY	ENGR. EST.	AVERAGE BID	AWARDED BID
=====	201-00000	Clear and Grub		LUMP SUM	=====	=====	=====
C170A-002		CRITICAL CULVERT CONST. PKG D	10/27/22	1.00	30000.00	25937.50	18750.00
TRG0253-264		I-25 AND SH 119 PARK-N-RIDE	10/27/22	1.00	20000.00	76861.02	85000.00
STU0252-457		I-25:ALAMEDA RIVER PH 2.0	11/03/22	1.00	100000.00	78839.30	63000.00
SHE0242-087		US 24 SAFETY IMPRVMENTS, E OF	11/03/22	1.00	30000.00	48280.87	22842.62
STR064A-010		SH 64 AND SH 13 AT MEEKER	11/10/22	1.00	10000.00	16915.00	24000.00
NHPP0853-126		US85C: PLATTEVILLE NORTH MP (11/10/22	1.00	30000.00	11904.00	25000.00
C5502-097		US550 MP 117.28-126.06	11/17/22	1.00	50000.00	114606.07	90980.00
STRC090-011		US 50B AND SH71/CR18 INTERSEC	11/17/22	1.00	1500.00	19933.50	2500.00
2670703-487		I-70 BRIDGES OVER WARD ROAD-	12/01/22	1.00	18091.00	71300.00	100000.00
IM025A-050		I25-MP103.9 - INTERSECTION DR	12/01/22	1.00	25000.00	108333.33	50000.00
NHPP0063-048		US6 / 20 ROAD INTERSECTION IM	12/15/22	1.00	75000.00	123505.86	18000.00
NHPP0931-033		SH93:US6 TO 58TH RESURFACING	12/15/22	1.00	30000.00	21064.33	12300.00
NHPP0502-090		SH 50 MP 134.6-136 GUNNISON C	12/22/22	1.00	50000.00	121763.90	195182.41
STA0361-129		US 36: HYGIENE RD AND NELSON	12/22/22	1.00	30000.00	21389.18	18870.91
BR012A-048		CO 12 STRUCTURE P-17-F AT MP	12/22/22	1.00	100000.00	72500.00	50000.00
		WEIGHTED AVERAGE FOR THE FOURTH QUARTER		16.00	38099.44	63738.47	54642.70
		WEIGHTED AVERAGE FOR THE YEAR		42.00	42163.24	72287.55	54126.38
=====	201-00001	Clear and Grub		Acre	=====	=====	=====
NHPP 0761-238		I-76 DAHLIA TO YORK	03/10/22	1.00	8000.00	33058.05	20000.00
C0761-239							
		WEIGHTED AVERAGE FOR THE FIRST QUARTER		1.00	8000.00	33058.05	20000.00
STA0712-019		SH 71: Frieight Improvements	05/12/22	23.00	900.00	6303.25	6303.25
		WEIGHTED AVERAGE FOR THE SECOND QUARTER		23.00	900.00	6303.25	6303.25
FSA052A-057		SH52 BOX CULVERT EXTENSION (M	08/04/22	0.20	25000.00	55926.71	13260.00
FBR0761-236		I-76 OVER CLR CRK SCOUR MIT	08/25/22	0.40	50000.00	184500.00	18000.00
NHPPR100-266		R1 ESSENTIAL REPAIRS	09/01/22	1.00	2000.00	20097.54	27292.62
		WEIGHTED AVERAGE FOR THE THIRD QUARTER		1.60	16875.00	65676.80	23215.39
STAM420-001		US 285 AT HWY 9C IMPROVEMENTS	12/01/22	9.00	5500.00	7634.83	4928.41

COLORADO DEPARTMENT OF TRANSPORTATION
ITEM UNIT COSTS BY PROJECTS -- 2022 COST DATA

11:31 Wednesday, March 8, 2023 3

PROJECT NUMBER	ITEM NUMBER/ PROJECT LOCATION	ITEM DESCRIPTION/ PROJECT LOCATION	DATE LET	UNIT/ QUANTITY	ENGR. EST.	AVERAGE BID	AWARDED BID
===== 201-00001 Clear and Grub Acre =====							
BR2854-148		INTERSECTION OF US 285 & SH 9					
STM0091-046		ADA RAMP IMPROVEMENTS - FAIRP					
STA385A-016		SH 385 MP 97.76	12/22/22	3.50	7500.00	14875.00	5000.00
	WEIGHTED AVERAGE FOR THE FOURTH QUARTER			12.50	6060.00	9662.08	4948.46
	WEIGHTED AVERAGE FOR THE YEAR			38.10	3450.13	14076.83	6928.48
===== 201-00005 Rem of Debris LUMP SUM =====							
NH0504-911			04/07/22	1.00	5000.00	55050.00	10100.00
STM1151-038		SH115 MP 27 TO MP 38	04/21/22	1.00	10000.00	29776.13	6200.61
	WEIGHTED AVERAGE FOR THE SECOND QUARTER			2.00	7500.00	36997.24	8150.31
NHPP0705-088		I-70 AGATE STRUCTURE REHAB	10/27/22	1.00	10000.00	9131.28	10000.00
STU0252-457		I-25:ALAMEDA RIVER PH 2.0	11/03/22	1.00	5000.00	22240.58	12000.00
STA0711-021		SH71: REGION LINE NORTH	12/01/22	1.00	3000.00	4866.67	5000.00
	WEIGHTED AVERAGE FOR THE FOURTH QUARTER			3.00	6000.00	11784.69	9000.00
	WEIGHTED AVERAGE FOR THE YEAR			5.00	6600.00	22166.32	8660.12
===== 202-00000 Rem Str and Obstructions LUMP SUM =====							
NHPP0063-054		US 6 FROM I70-B TO 33 RD. (MP	08/18/22	1.00	2000.00	16896.96	25000.00
2670403-065		US40 FLOYD HILL ROUNDABOUTS	09/15/22	1.00	20000.00	14456.79	10000.00
SHE2873-193		US 287 & CO 52 INTERSECTION I	09/15/22	1.00	15000.00	21132.50	10000.00
	WEIGHTED AVERAGE FOR THE THIRD QUARTER			3.00	12333.33	18541.75	15000.00
STA3852-015		US 385 HOLYOKE NORTH	10/27/22	1.00	8000.00	5000.00	5000.00
STU0252-457		I-25:ALAMEDA RIVER PH 2.0	11/03/22	1.00	75000.00	41135.14	34086.20
	WEIGHTED AVERAGE FOR THE FOURTH QUARTER			2.00	41500.00	32101.35	19543.10
	WEIGHTED AVERAGE FOR THE YEAR			5.00	24000.00	22157.65	16817.24
===== 202-00001 Rem Structure Each =====							
NHPP 0761-238		I-76 DAHLIA TO YORK	03/10/22	1.00	75000.00	2690.74	2500.00

COLORADO DEPARTMENT OF TRANSPORTATION
 ITEM UNIT COSTS BY PROJECTS -- 2022 COST DATA

11:31 Wednesday, March 8, 2023 4

PROJECT NUMBER	ITEM NUMBER/ PROJECT LOCATION	ITEM DESCRIPTION/ PROJECT LOCATION	DATE LET	UNIT/ QUANTITY	ENGR. EST.	AVERAGE BID	AWARDED BID
=====	202-00001	Rem Structure		Each	=====	=====	=====
C0761-239							
NHM765-007			03/31/22	3.00	900.00	2505.03	238.74
	WEIGHTED AVERAGE FOR THE FIRST QUARTER			4.00	19425.00	2592.42	804.06
NHPP0063-054		US 6 FROM I70-B TO 33 RD. (MP	08/18/22	4.00	3000.00	2887.35	5300.00
SHE2873-193		US 287 & CO 52 INTERSECTION I	09/15/22	2.00	2500.00	5687.08	2500.00
	WEIGHTED AVERAGE FOR THE THIRD QUARTER			6.00	2833.33	4567.19	4366.67
C5502-097		US550 MP 117.28-126.06	11/17/22	2.00	2000.00	7679.68	8050.00
	WEIGHTED AVERAGE FOR THE FOURTH QUARTER			2.00	2000.00	7679.68	8050.00
	WEIGHTED AVERAGE FOR THE YEAR			12.00	8225.00	4220.77	3793.02
=====	202-00002	Rem of Structure (Spec)		Each	=====	=====	=====
NHM765-007			03/31/22	5.00	500.00	2452.92	100.06
	WEIGHTED AVERAGE FOR THE FIRST QUARTER			5.00	500.00	2452.92	100.06
	WEIGHTED AVERAGE FOR THE YEAR			5.00	500.00	2452.92	100.06
=====	202-00003	Rem of Structure (Spec)		LUMP SUM	=====	=====	=====
ER0502-092		US 50 MP 204 EB MONARCH TRUCK	08/29/22	1.00	25000.00	11526.66	14329.99
	WEIGHTED AVERAGE FOR THE THIRD QUARTER			1.00	25000.00	11526.66	14329.99
	WEIGHTED AVERAGE FOR THE YEAR			1.00	25000.00	11526.66	14329.99
=====	202-00009	Tree Trimming		LUMP SUM	=====	=====	=====
NHM765-007			03/31/22	1.00	7200.00	11419.13	3735.30
	WEIGHTED AVERAGE FOR THE FIRST QUARTER			1.00	7200.00	11419.13	3735.30

COLORADO DEPARTMENT OF TRANSPORTATION
 ITEM UNIT COSTS BY PROJECTS -- 2022 COST DATA

11:31 Wednesday, March 8, 2023 5

PROJECT NUMBER	ITEM NUMBER/ PROJECT LOCATION	ITEM DESCRIPTION/ PROJECT LOCATION	DATE LET	UNIT/ QUANTITY	ENGR. EST.	AVERAGE BID	AWARDED BID
===== 202-00009		Tree Trimming		LUMP SUM	=====		
STM1151-038		SH115 MP 27 TO MP 38	04/21/22	1.00	10000.00	25470.10	10000.00
		WEIGHTED AVERAGE FOR THE SECOND QUARTER		1.00	10000.00	25470.10	10000.00
		WEIGHTED AVERAGE FOR THE YEAR		2.00	8600.00	20200.99	6867.65
===== 202-00010		Rem Tree		Each	=====		
STA 067A-048		Hwy 67A MP 0.00 TO MP 11.05 I	03/03/22	6.00	500.00	1147.66	1200.00
		WEIGHTED AVERAGE FOR THE FIRST QUARTER		6.00	500.00	1147.66	1200.00
NH0504-911			04/07/22	1.00	500.00	2300.00	2600.00
NHPP0702-413		VAIL PASS AUX PHASE 1 CAP 2	04/18/22	40.00	551.05	551.05	551.05
STM1151-038		SH115 MP 27 TO MP 38	04/21/22	258.00	340.00	286.19	250.00
2670703-479		I-70 BRIDGE OVER HARLAN	05/05/22	14.00	400.00	962.96	2197.51
NHC540-017		R2 CHAINUP STA @ KENOSHA/HOOS	05/12/22	10.00	700.00	1250.00	750.00
FSA052A-046		SH52 WCR 37 INTERSECTION IMPR	06/09/22	5.00	1200.00	1354.34	576.00
		WEIGHTED AVERAGE FOR THE SECOND QUARTER		328.00	392.87	372.58	397.22
NHPP0702-414		VAIL PASS AUX PHASE 1 CAP 3	07/08/22	16.00	562.07	562.07	562.07
FBR0702-423		VAIL PASS AUX BE F-12-AT PHAS					
NHPP0063-054		US 6 FROM I70-B TO 33 RD. (MP	08/18/22	10.00	500.00	831.89	1350.00
FBR0761-236		I-76 OVER CLR CRK SCOUR MIT	08/25/22	11.00	600.00	1350.00	1200.00
2670403-065		US40_FLOYD HILL ROUNDABOUTS	09/15/22	48.00	1000.00	532.66	200.00
NHPP0701-231		I-70 SALT WASH BRIDGES SCOUR	09/29/22	13.00	1000.00	921.39	1000.00
		WEIGHTED AVERAGE FOR THE THIRD QUARTER		98.00	832.58	714.81	594.83
C5502-111		US 550 MP 81 AND 89 RED MOUNT	10/27/22	2.00	300.00	1375.00	2000.00
C170A-002		CRITICAL CULVERT CONST. PKG D	10/27/22	25.00	400.00	1193.75	375.00
STU0252-457		I-25:ALAMEDA RIVER PH 2.0	11/03/22	109.00	1000.00	753.65	635.00

COLORADO DEPARTMENT OF TRANSPORTATION
 ITEM UNIT COSTS BY PROJECTS -- 2022 COST DATA

11:31 Wednesday, March 8, 2023 6

PROJECT NUMBER	ITEM NUMBER/ PROJECT LOCATION	ITEM DESCRIPTION/ PROJECT LOCATION	DATE LET	UNIT/ QUANTITY	ENGR. EST.	AVERAGE BID	AWARDED BID
===== 202-00010							
		Rem Tree		Each			
C5502-097		US550 MP 117.28-126.06	11/17/22	3.00	1000.00	1380.06	1780.00
STAM420-001		US 285 AT HWY 9C IMPROVEMENTS	12/01/22	10.00	500.00	1929.14	5180.66
BR2854-148		INTERSECTION OF US 285 & SH 9					
STM0091-046		ADA RAMP IMPROVEMENTS - FAIRP					
IM025A-050		I25-MP103.9 - INTERSECTION DR	12/01/22	23.00	350.00	716.67	350.00
BR012A-048		CO 12 STRUCTURE P-17-F AT MP	12/22/22	20.00	500.00	1304.01	2000.00
STA385A-016		SH 385 MP 97.76	12/22/22	15.00	500.00	1362.50	500.00
	WEIGHTED AVERAGE FOR THE FOURTH QUARTER			207.00	739.86	992.70	943.41
	WEIGHTED AVERAGE FOR THE YEAR			639.00	573.72	582.18	612.00
===== 202-00015							
		Rem Headwall		Each			
NHPP0702-383		I-70 EB AUX FRISCO TO SILVERT	01/13/22	1.00	1500.00	2916.21	4981.95
	WEIGHTED AVERAGE FOR THE FIRST QUARTER			1.00	1500.00	2916.21	4981.95
NHPP0702-413		VAIL PASS AUX PHASE 1 CAP 2	04/18/22	1.00	3559.01	3559.01	3559.01
STM1151-038		SH115 MP 27 TO MP 38	04/21/22	3.00	2300.00	3520.78	3415.68
NHC540-017		R2 CHAINUP STA @ KENOSHA/HOOS	05/12/22	3.00	1680.00	1666.67	1500.00
	WEIGHTED AVERAGE FOR THE SECOND QUARTER			7.00	2214.14	2854.83	2615.15
FBR0761-236		I-76 OVER CLR CRK SCOUR MIT	08/25/22	1.00	1500.00	2386.67	970.00
SHE2873-193		US 287 & CO 52 INTERSECTION I	09/15/22	2.00	2200.00	4469.58	1583.00
	WEIGHTED AVERAGE FOR THE THIRD QUARTER			3.00	1966.67	4053.00	1378.67
C5502-097		US550 MP 117.28-126.06	11/17/22	5.00	3000.00	1553.46	130.00
STAM420-001		US 285 AT HWY 9C IMPROVEMENTS	12/01/22	3.00	1736.00	1667.26	1684.92
BR2854-148		INTERSECTION OF US 285 & SH 9					
STM0091-046		ADA RAMP IMPROVEMENTS - FAIRP					
NHPP0063-048		US6 / 20 ROAD INTERSECTION IM	12/15/22	1.00	1500.00	3083.85	2250.00
	WEIGHTED AVERAGE FOR THE FOURTH QUARTER			9.00	2412.00	1794.98	883.86
	WEIGHTED AVERAGE FOR THE YEAR			20.00	2230.35	2663.04	1768.94

COLORADO DEPARTMENT OF TRANSPORTATION
ITEM UNIT COSTS BY PROJECTS -- 2022 COST DATA

11:31 Wednesday, March 8, 2023 7

PROJECT NUMBER	ITEM NUMBER/ PROJECT LOCATION	ITEM DESCRIPTION/ PROJECT LOCATION	DATE LET	UNIT/ QUANTITY	ENGR. EST.	AVERAGE BID	AWARDED BID
===== 202-00019		Rem Inlet		Each =====			
NHPP0702-383		I-70 EB AUX FRISCO TO SILVERT	01/13/22	9.00	1230.00	1757.29	1300.00
NHPP 0761-238		I-76 DAHLIA TO YORK	03/10/22	3.00	1200.00	1581.95	1800.00
C0761-239							
NHM765-007			03/31/22	19.00	1000.00	1416.63	1073.33
		WEIGHTED AVERAGE FOR THE FIRST QUARTER		31.00	1086.13	1569.78	1209.46
NHPP0702-413		VAIL PASS AUX PHASE 1 CAP 2	04/18/22	1.00	1559.71	1559.71	1559.71
STM1151-038		SH115 MP 27 TO MP 38	04/21/22	2.00	1200.00	1581.12	2424.46
2670703-479		I-70 BRIDGE OVER HARLAN	05/05/22	7.00	1500.00	1808.85	1408.54
		WEIGHTED AVERAGE FOR THE SECOND QUARTER		10.00	1445.97	1761.18	1626.84
NHPP0702-414		VAIL PASS AUX PHASE 1 CAP 3	07/08/22	1.00	1650.55	1650.55	1650.55
FBR0702-423		VAIL PASS AUX BE F-12-AT PHAS					
NHPP0063-054		US 6 FROM I70-B TO 33 RD. (MP	08/18/22	14.00	1500.00	417.35	360.00
SHE2873-193		US 287 & CO 52 INTERSECTION I	09/15/22	2.00	1500.00	2289.75	1926.00
		WEIGHTED AVERAGE FOR THE THIRD QUARTER		17.00	1508.86	995.44	620.15
TRG0253-264		I-25 AND SH 119 PARK-N-RIDE	10/27/22	2.00	1400.00	1933.99	700.00
STU0252-457		I-25:ALAMEDA RIVER PH 2.0	11/03/22	7.00	2000.00	2900.59	1200.00
C5502-097		US550 MP 117.28-126.06	11/17/22	1.00	1500.00	1809.13	502.00
STAM420-001		US 285 AT HWY 9C IMPROVEMENTS	12/01/22	2.00	1500.00	1626.89	1684.93
BR2854-148		INTERSECTION OF US 285 & SH 9					
STM0091-046		ADA RAMP IMPROVEMENTS - FAIRP					
2670703-487		I-70 BRIDGES OVER WARD ROAD-	12/01/22	1.00	1776.00	1816.61	1430.00
IM025A-050		I25-MP103.9 - INTERSECTION DR	12/01/22	1.00	2000.00	2700.00	1100.00
STA0361-129		US 36: HYGIENE RD AND NELSON	12/22/22	1.00	1400.00	3898.13	1925.64
		WEIGHTED AVERAGE FOR THE FOURTH QUARTER		15.00	1765.07	2409.38	1208.50
		WEIGHTED AVERAGE FOR THE YEAR		73.00	1373.37	1704.34	1129.20
===== 202-00021		Rem Manhole		Each =====			
NHM765-007			03/31/22	3.00	2000.00	2186.51	3299.39
		WEIGHTED AVERAGE FOR THE FIRST QUARTER		3.00	2000.00	2186.51	3299.39

COLORADO DEPARTMENT OF TRANSPORTATION
ITEM UNIT COSTS BY PROJECTS -- 2022 COST DATA

11:31 Wednesday, March 8, 2023 8

PROJECT NUMBER	ITEM NUMBER/ PROJECT LOCATION	ITEM DESCRIPTION/ PROJECT LOCATION	DATE LET	UNIT/ QUANTITY	ENGR. EST.	AVERAGE BID	AWARDED BID
=====	202-00021	Rem Manhole		Each	=====		
NHPP0702-414		VAIL PASS AUX PHASE 1 CAP 3	07/08/22	7.00	3588.97	3588.97	3588.97
FBR0702-423		VAIL PASS AUX BE F-12-AT PHAS					
NHPP0063-054		US 6 FROM I70-B TO 33 RD. (MP	08/18/22	18.00	1400.00	461.49	400.00
		WEIGHTED AVERAGE FOR THE THIRD QUARTER		25.00	2012.91	970.61	1292.91
NHPP0063-048		US6 / 20 ROAD INTERSECTION IM	12/15/22	1.00	3500.00	2566.24	2600.00
		WEIGHTED AVERAGE FOR THE FOURTH QUARTER		1.00	3500.00	3291.88	5866.67
		WEIGHTED AVERAGE FOR THE YEAR		29.00	2062.85	1576.83	1929.71
=====	202-00023	Rem Emb Prot Ty 3		Each	=====		
NHPP 0761-238		I-76 DAHLIA TO YORK	03/10/22	5.00	1000.00	1328.45	850.00
C0761-239							
		WEIGHTED AVERAGE FOR THE FIRST QUARTER		5.00	1000.00	1328.45	850.00
STM1151-038		SH115 MP 27 TO MP 38	04/21/22	11.00	1000.00	1076.03	1082.07
		WEIGHTED AVERAGE FOR THE SECOND QUARTER		11.00	1000.00	1076.03	1082.07
STR0711-022		SH 71 OVER THE ARKANSAS	08/04/22	4.00	800.00	1438.33	1000.00
		WEIGHTED AVERAGE FOR THE THIRD QUARTER		4.00	800.00	1438.33	1000.00
2670703-487		I-70 BRIDGES OVER WARD ROAD-	12/01/22	2.00	1200.00	1139.45	880.00
		WEIGHTED AVERAGE FOR THE FOURTH QUARTER		2.00	1200.00	1139.45	880.00
		WEIGHTED AVERAGE FOR THE YEAR		22.00	981.82	1204.91	996.04

COLORADO DEPARTMENT OF TRANSPORTATION
ITEM UNIT COSTS BY PROJECTS -- 2022 COST DATA

11:31 Wednesday, March 8, 2023 9

PROJECT NUMBER	ITEM NUMBER/ PROJECT LOCATION	ITEM DESCRIPTION/ PROJECT LOCATION	DATE LET	UNIT/ QUANTITY	ENGR. EST.	AVERAGE BID	AWARDED BID
===== 202-00024		Rem Emb Prot Ty 5		Each =====			
NHPP 0761-238 C0761-239		I-76 DAHLIA TO YORK	03/10/22	2.00	500.00	1264.00	1050.00
	WEIGHTED AVERAGE FOR THE FIRST QUARTER			2.00	500.00	1264.00	1050.00
	WEIGHTED AVERAGE FOR THE YEAR			2.00	500.00	1264.00	1050.00
===== 202-00025		Rem Ditch Lining		Lin Foot =====			
SHE2873-193		US 287 & CO 52 INTERSECTION I	09/15/22	1,450.00	12.00	26.38	15.00
	WEIGHTED AVERAGE FOR THE THIRD QUARTER			1,450.00	12.00	26.38	15.00
C5502-097		US550 MP 117.28-126.06	11/17/22	165.00	20.00	18.18	8.00
	WEIGHTED AVERAGE FOR THE FOURTH QUARTER			165.00	20.00	18.18	8.00
	WEIGHTED AVERAGE FOR THE YEAR			1,615.00	12.82	25.94	14.28
===== 202-00026		Rem S and D Pave		Sq Yard =====			
NHPP 0761-238 C0761-239		I-76 DAHLIA TO YORK	03/10/22	1,252.00	25.00	20.38	27.00
	WEIGHTED AVERAGE FOR THE FIRST QUARTER			1,252.00	25.00	20.38	27.00
2670703-479		I-70 BRIDGE OVER HARLAN	05/05/22	852.00	22.00	20.68	34.75
	WEIGHTED AVERAGE FOR THE SECOND QUARTER			852.00	22.00	20.68	34.75
FSA052A-057 NHPP0063-054		SH52 BOX CULVERT EXTENSION (M	08/04/22	4.00	50.00	281.00	66.30
		US 6 FROM I70-B TO 33 RD. (MP	08/18/22	8.00	50.00	228.16	400.00
	WEIGHTED AVERAGE FOR THE THIRD QUARTER			12.00	50.00	250.81	288.77

COLORADO DEPARTMENT OF TRANSPORTATION
ITEM UNIT COSTS BY PROJECTS -- 2022 COST DATA

11:31 Wednesday, March 8, 2023 10

PROJECT NUMBER	ITEM NUMBER/ PROJECT LOCATION	ITEM DESCRIPTION/ PROJECT LOCATION	DATE LET	UNIT/ QUANTITY	ENGR. EST.	AVERAGE BID	AWARDED BID
===== 202-00026		Rem S and D Pave		Sq Yard	=====		
NHPP0701-253		I-70 EAST OF DEBEQUE	10/27/22	5.00	60.00	1742.00	2500.00
NHPP0343-048		US 34 (MP 169.3-171.4)	11/01/22	1,290.00	25.00	20.08	28.00
2670703-487		I-70 BRIDGES OVER WARD ROAD-	12/01/22	1,050.00	23.90	18.36	17.00
IM025A-050		I25-MP103.9 - INTERSECTION DR	12/01/22	206.00	40.00	37.33	40.00
		WEIGHTED AVERAGE FOR THE FOURTH QUARTER		2,551.00	25.83	22.48	27.98
		WEIGHTED AVERAGE FOR THE YEAR		4,667.00	24.97	21.70	29.30
===== 202-00027		Rem Riprap		Sq Yard	=====		
NHPP 0761-238 C0761-239		I-76 DAHLIA TO YORK	03/10/22	209.00	40.00	32.70	15.00
		WEIGHTED AVERAGE FOR THE FIRST QUARTER		209.00	40.00	32.70	15.00
NHPP0702-413		VAIL PASS AUX PHASE 1 CAP 2	04/18/22	33.00	42.15	42.15	42.15
		WEIGHTED AVERAGE FOR THE SECOND QUARTER		33.00	42.15	42.15	42.15
NHPP0702-414 FBR0702-423 2670403-065 NHPP0701-231		VAIL PASS AUX PHASE 1 CAP 3	07/08/22	180.00	43.19	43.19	43.19
		VAIL PASS AUX BE F-12-AT PHAS					
		US40_FLOYD HILL ROUNDABOUTS	09/15/22	9.00	40.00	117.10	100.00
		I-70 SALT WASH BRIDGES SCOUR	09/29/22	218.00	50.00	29.15	19.00
		WEIGHTED AVERAGE FOR THE THIRD QUARTER		407.00	46.77	36.77	31.49
STAM420-001 BR2854-148 STM0091-046 IM025A-050		US 285 AT HWY 9C IMPROVEMENTS	12/01/22	110.00	20.00	51.87	14.81
		INTERSECTION OF US 285 & SH 9					
		ADA RAMP IMPROVEMENTS - FAIRP					
		I25-MP103.9 - INTERSECTION DR	12/01/22	141.00	40.00	37.33	22.00
		WEIGHTED AVERAGE FOR THE FOURTH QUARTER		251.00	31.24	44.74	18.85
		WEIGHTED AVERAGE FOR THE YEAR		900.00	40.69	36.85	24.53

COLORADO DEPARTMENT OF TRANSPORTATION
ITEM UNIT COSTS BY PROJECTS -- 2022 COST DATA

11:31 Wednesday, March 8, 2023 11

PROJECT NUMBER	ITEM NUMBER/ PROJECT LOCATION	ITEM DESCRIPTION/ PROJECT LOCATION	DATE LET	UNIT/ QUANTITY	ENGR. EST.	AVERAGE BID	AWARDED BID
=====	202-00030	Rem Water Service		Each	=====	=====	=====
STU0252-457		I-25:ALAMEDA RIVER PH 2.0	11/03/22	3.00	2000.00	4193.39	4000.00
		WEIGHTED AVERAGE FOR THE FOURTH QUARTER		3.00	2000.00	4193.39	4000.00
		WEIGHTED AVERAGE FOR THE YEAR		3.00	2000.00	4193.39	4000.00
=====	202-00031	Rem of Fire Hydrant		Each	=====	=====	=====
NHPP0063-054		US 6 FROM I70-B TO 33 RD. (MP 08/18/22		4.00	1800.00	347.12	300.00
		WEIGHTED AVERAGE FOR THE THIRD QUARTER		4.00	1800.00	347.12	300.00
		WEIGHTED AVERAGE FOR THE YEAR		4.00	1800.00	347.12	300.00
=====	202-00032	Rem Valve		Each	=====	=====	=====
NHPP0063-054		US 6 FROM I70-B TO 33 RD. (MP 08/18/22		26.00	300.00	282.76	300.00
		WEIGHTED AVERAGE FOR THE THIRD QUARTER		26.00	300.00	282.76	300.00
STU0252-457		I-25:ALAMEDA RIVER PH 2.0	11/03/22	2.00	1000.00	1923.59	800.00
		WEIGHTED AVERAGE FOR THE FOURTH QUARTER		2.00	1000.00	1923.59	800.00
		WEIGHTED AVERAGE FOR THE YEAR		28.00	350.00	452.50	335.71
=====	202-00033	Rem Pipe		Each	=====	=====	=====
STM1151-038		SH115 MP 27 TO MP 38	04/21/22	9.00	1200.00	1627.80	1211.52
		WEIGHTED AVERAGE FOR THE SECOND QUARTER		9.00	1200.00	1627.80	1211.52
2670703-487		I-70 BRIDGES OVER WARD ROAD-	12/01/22	3.00	4000.00	2676.61	1430.00
		WEIGHTED AVERAGE FOR THE FOURTH QUARTER		3.00	4000.00	2676.61	1430.00
		WEIGHTED AVERAGE FOR THE YEAR		12.00	1900.00	1890.00	1266.14

PROJECT NUMBER	ITEM NUMBER/ PROJECT LOCATION	ITEM DESCRIPTION/ PROJECT LOCATION	DATE LET	UNIT/ QUANTITY	ENGR. EST.	AVERAGE BID	AWARDED BID
=====	202-00035	Rem Pipe		Lin Foot	=====		
NHPP0702-383		I-70 EB AUX FRISCO TO SILVERT	01/13/22	559.00	35.00	83.73	85.00
NHPP1601-083			02/03/22	109.00	75.00	429.49	300.00
NHPP0063-063			02/24/22	617.00	35.00	30.40	26.00
NHPP 0761-238		I-76 DAHLIA TO YORK	03/10/22	782.00	29.00	41.09	28.00
C0761-239							
NHM765-007			03/31/22	276.00	30.00	54.47	49.62
		WEIGHTED AVERAGE FOR THE FIRST QUARTER		2,343.00	34.27	58.89	56.27
NHPP0702-413		VAIL PASS AUX PHASE 1 CAP 2	04/18/22	296.00	38.30	38.30	38.30
2670703-479		I-70 BRIDGE OVER HARLAN	05/05/22	231.00	30.00	56.88	96.59
STA0712-019		SH 71: Frieight Improvements	05/12/22	337.00	35.00	42.81	42.81
		WEIGHTED AVERAGE FOR THE SECOND QUARTER		864.00	34.79	51.81	55.64
NHPP0702-414		VAIL PASS AUX PHASE 1 CAP 3	07/08/22	493.00	50.86	50.86	50.86
FBR0702-423		VAIL PASS AUX BE F-12-AT PHAS					
FSA052A-057		SH52 BOX CULVERT EXTENSION (M	08/04/22	33.00	75.00	118.22	28.32
NHPP0063-054		US 6 FROM I70-B TO 33 RD. (MP	08/18/22	15,727.00	30.00	25.75	28.00
BR0343-046		US 34 TIMBER BRIDGE REPL. PKG	08/31/22	96.00	59.49	28.97	28.97
FBR0343-047		US 6/US 34 TIMBER BRIDGE REPL					
2670403-065		US40 FLOYD HILL ROUNDABOUTS	09/15/22	112.00	55.00	41.23	30.00
SHE2873-193		US 287 & CO 52 INTERSECTION I	09/15/22	289.00	30.00	45.38	41.73
		WEIGHTED AVERAGE FOR THE THIRD QUARTER		16,750.00	31.04	27.54	28.93
C170A-002		CRITICAL CULVERT CONST. PKG D	10/27/22	83.00	75.00	205.38	112.50
TRG0253-264		I-25 AND SH 119 PARK-N-RIDE	10/27/22	320.00	30.00	44.87	28.00
STA3852-015		US 385 HOLYOKE NORTH	10/27/22	42.00	65.00	52.00	52.00
STU0252-457		I-25:ALAMEDA RIVER PH 2.0	11/03/22	293.00	60.00	137.69	63.00
C5502-097		US550 MP 117.28-126.06	11/17/22	3,329.00	40.00	16.47	11.50
STAM420-001		US 285 AT HWY 9C IMPROVEMENTS	12/01/22	867.00	30.00	49.07	75.00
BR2854-148		INTERSECTION OF US 285 & SH 9					
STM0091-046		ADA RAMP IMPROVEMENTS - FAIRP					
IM025A-050		I25-MP103.9 - INTERSECTION DR	12/01/22	361.00	40.00	49.00	32.00
NHPP0063-048		US6 / 20 ROAD INTERSECTION IM	12/15/22	83.00	40.00	77.18	65.00
NHPP0502-090		SH 50 MP 134.6-136 GUNNISON C	12/22/22	40.00	60.00	84.22	53.49

PROJECT NUMBER	ITEM NUMBER/ PROJECT LOCATION	ITEM DESCRIPTION/ PROJECT LOCATION	DATE LET	UNIT/ QUANTITY	ENGR. EST.	AVERAGE BID	AWARDED BID
=====	202-00035	Rem Pipe		Lin Foot	=====	=====	=====
STA0361-129		US 36: HYGIENE RD AND NELSON	12/22/22	135.00	50.00	55.86	45.31
BR012A-048		CO 12 STRUCTURE P-17-F AT MP	12/22/22	95.00	10.00	80.40	100.00
STA385A-016		SH 385 MP 97.76	12/22/22	160.00	20.00	100.00	50.00
	WEIGHTED AVERAGE FOR THE FOURTH QUARTER			5,808.00	38.97	42.98	33.24
	WEIGHTED AVERAGE FOR THE YEAR			25,765.00	33.25	38.20	33.28
=====	202-00036	Rem of Pipe (Spec)		Lin Foot	=====	=====	=====
NHPP0702-413		VAIL PASS AUX PHASE 1 CAP 2	04/18/22	168.00	524.82	524.82	524.82
	WEIGHTED AVERAGE FOR THE SECOND QUARTER			168.00	524.82	524.82	524.82
NHPP0063-054		US 6 FROM I70-B TO 33 RD. (MP	08/18/22	1,572.00	100.00	43.94	38.00
	WEIGHTED AVERAGE FOR THE THIRD QUARTER			1,572.00	100.00	43.94	38.00
	WEIGHTED AVERAGE FOR THE YEAR			1,740.00	141.02	68.33	85.00
=====	202-00037	Rem of End Section		Each	=====	=====	=====
NHPP0702-383		I-70 EB AUX FRISCO TO SILVERT	01/13/22	5.00	430.00	709.42	800.00
NHPP1601-083			02/03/22	8.00	500.00	1175.29	400.00
NHPP 0761-238		I-76 DAHLIA TO YORK	03/10/22	2.00	500.00	424.36	600.00
C0761-239							
	WEIGHTED AVERAGE FOR THE FIRST QUARTER			15.00	476.67	760.17	560.00
NHPP0702-413		VAIL PASS AUX PHASE 1 CAP 2	04/18/22	4.00	698.96	698.96	698.96
STM1151-038		SH115 MP 27 TO MP 38	04/21/22	19.00	515.00	474.77	330.87
NHC540-017		R2 CHAINUP STA @ KENOSHA/HOOS	05/12/22	2.00	360.00	883.33	650.00
	WEIGHTED AVERAGE FOR THE SECOND QUARTER			25.00	532.03	506.66	415.29
NHPP0702-414		VAIL PASS AUX PHASE 1 CAP 3	07/08/22	3.00	912.77	912.77	912.77

PROJECT NUMBER	ITEM NUMBER/ PROJECT LOCATION	ITEM DESCRIPTION/ PROJECT LOCATION	DATE LET	UNIT/ QUANTITY	ENGR. EST.	AVERAGE BID	AWARDED BID
===== 202-00037							
		Rem of End Section		Each			
FBR0702-423		VAIL PASS AUX BE F-12-AT PHAS					
NHPP0063-054		US 6 FROM I70-B TO 33 RD. (MP	08/18/22	3.00	600.00	78.25	68.00
2670403-065		US40 FLOYD HILL ROUNDABOUTS	09/15/22	4.00	800.00	471.63	240.00
SHE2873-193		US 287 & CO 52 INTERSECTION I	09/15/22	1.00	700.00	815.92	481.00
		WEIGHTED AVERAGE FOR THE THIRD QUARTER		11.00	767.12	509.73	398.48
TRG0253-264		I-25 AND SH 119 PARK-N-RIDE	10/27/22	4.00	600.00	684.83	300.00
STA3852-015		US 385 HOLYOKE NORTH	10/27/22	19.00	500.00	550.00	550.00
C5502-097		US550 MP 117.28-126.06	11/17/22	10.00	700.00	643.36	125.00
STAM420-001		US 285 AT HWY 9C IMPROVEMENTS	12/01/22	4.00	443.10	682.63	842.47
BR2854-148		INTERSECTION OF US 285 & SH 9					
STM0091-046		ADA RAMP IMPROVEMENTS - FAIRP					
2670703-487		I-70 BRIDGES OVER WARD ROAD-	12/01/22	5.00	800.00	583.73	440.00
IM025A-050		I25-MP103.9 - INTERSECTION DR	12/01/22	1.00	350.00	1366.67	300.00
NHPP0063-048		US6 / 20 ROAD INTERSECTION IM	12/15/22	1.00	600.00	1019.90	2100.00
NHPP0502-090		SH 50 MP 134.6-136 GUNNISON C	12/22/22	3.00	600.00	1431.85	551.26
		WEIGHTED AVERAGE FOR THE FOURTH QUARTER		47.00	583.46	761.96	520.89
		WEIGHTED AVERAGE FOR THE YEAR		98.00	574.61	663.08	486.89
===== 202-00040							
		Rem Elec Conduit		Lin Foot			
NHPP0702-383		I-70 EB AUX FRISCO TO SILVERT	01/13/22	202.00	10.00	51.56	58.00
NHPP 0761-238		I-76 DAHLIA TO YORK	03/10/22	100.00	16.00	52.11	12.00
C0761-239							
		WEIGHTED AVERAGE FOR THE FIRST QUARTER		302.00	11.99	51.80	42.77
2670703-479		I-70 BRIDGE OVER HARLAN	05/05/22	335.00	15.00	7.82	9.16
		WEIGHTED AVERAGE FOR THE SECOND QUARTER		335.00	15.00	7.82	9.16
TRG0253-264		I-25 AND SH 119 PARK-N-RIDE	10/27/22	483.00	39.00	12.76	12.00
STAM420-001		US 285 AT HWY 9C IMPROVEMENTS	12/01/22	1,878.00	25.00	8.70	11.73
BR2854-148		INTERSECTION OF US 285 & SH 9					

COLORADO DEPARTMENT OF TRANSPORTATION
ITEM UNIT COSTS BY PROJECTS -- 2022 COST DATA

11:31 Wednesday, March 8, 2023 15

PROJECT NUMBER	ITEM NUMBER/ PROJECT LOCATION	ITEM DESCRIPTION/ PROJECT LOCATION	DATE LET	UNIT/ QUANTITY	ENGR. EST.	AVERAGE BID	AWARDED BID
===== 202-00040 STM0091-046		Rem Elec Conduit ADA RAMP IMPROVEMENTS - FAIRP		Lin Foot =====			
	WEIGHTED AVERAGE FOR THE FOURTH QUARTER			2,361.00	27.86	10.08	11.79
	WEIGHTED AVERAGE FOR THE YEAR			2,998.00	24.83	14.75	14.61
===== 202-00055		Rem of FO Cable		Lin Foot =====			
NHPP0702-383		I-70 EB AUX FRISCO TO SILVERT	01/13/22	4,775.00	5.00	2.88	3.00
	WEIGHTED AVERAGE FOR THE FIRST QUARTER			4,775.00	5.00	2.88	3.00
2670703-479		I-70 BRIDGE OVER HARLAN	05/05/22	335.00	3.00	1.17	1.31
	WEIGHTED AVERAGE FOR THE SECOND QUARTER			335.00	3.00	1.17	1.31
2670703-497		I-70_GENESEE WILDLIFE XING	09/15/22	3,452.00	4.40	3.32	2.95
	WEIGHTED AVERAGE FOR THE THIRD QUARTER			3,452.00	4.40	3.32	2.95
TRG0253-264 STAM420-001 BR2854-148 STM0091-046 2670703-487		I-25 AND SH 119 PARK-N-RIDE US 285 AT HWY 9C IMPROVEMENTS INTERSECTION OF US 285 & SH 9 ADA RAMP IMPROVEMENTS - FAIRP I-70 BRIDGES OVER WARD ROAD-	10/27/22 12/01/22 12/01/22	1,771.00 451.00 2,600.00	8.00 11.30 3.50	2.54 5.01 2.84	1.20 3.57 2.80
	WEIGHTED AVERAGE FOR THE FOURTH QUARTER			4,822.00	5.88	2.83	2.28
	WEIGHTED AVERAGE FOR THE YEAR			13,384.00	5.11	2.95	2.69
===== 202-00070		Rem Barricade		Each =====			
MPR200-280		PUEBLO AREA	11/17/22	1.00	750.00	700.00	1200.00
	WEIGHTED AVERAGE FOR THE FOURTH QUARTER			1.00	750.00	700.00	1200.00
	WEIGHTED AVERAGE FOR THE YEAR			1.00	750.00	700.00	1200.00

COLORADO DEPARTMENT OF TRANSPORTATION
ITEM UNIT COSTS BY PROJECTS -- 2022 COST DATA

11:31 Wednesday, March 8, 2023 16

PROJECT NUMBER	ITEM NUMBER/ PROJECT LOCATION	ITEM DESCRIPTION/ PROJECT LOCATION	DATE LET	UNIT/ QUANTITY	ENGR. EST.	AVERAGE BID	AWARDED BID
===== 202-00080		Rem Guard Post		Each =====			
STU0252-457		I-25:ALAMEDA RIVER PH 2.0	11/03/22	4.00	200.00	581.19	280.00
	WEIGHTED AVERAGE FOR THE FOURTH QUARTER			4.00	200.00	581.19	280.00
	WEIGHTED AVERAGE FOR THE YEAR			4.00	200.00	581.19	280.00
===== 202-00090		Rem Delineator		Each =====			
NH0504-910		US50B L-24-B MIN REP AT MP 40	01/13/22	15.00	15.00	24.73	10.00
NHPP0702-383		I-70 EB AUX FRISCO TO SILVERT	01/13/22	189.00	2.00	12.08	10.00
NHPP1601-083			02/03/22	256.00	8.00	23.18	10.00
STR0141-031			02/17/22	253.00	10.00	9.67	9.00
STA 067A-048		Hwy 67A MP 0.00 TO MP 11.05 I	03/03/22	350.00	10.00	9.31	10.00
NHPP 0761-238		I-76 DAHLIA TO YORK	03/10/22	34.00	10.00	16.50	20.00
C0761-239							
NHPP0703-472			03/10/22	375.00	8.00	13.70	14.00
STR092A-031			03/17/22	938.00	6.00	9.00	9.00
NHM765-007			03/31/22	22.00	9.00	33.29	29.64
	WEIGHTED AVERAGE FOR THE FIRST QUARTER			2,432.00	7.34	12.83	10.44
NH0504-911			04/07/22	698.00	8.00	7.00	6.00
CC030-081		ADA RAMP AND CURBS - FT. LUPT	04/14/22	34.00	10.00	60.00	25.00
STM1151-038		SH115 MP 27 TO MP 38	04/21/22	273.00	5.00	7.99	19.67
STA001A-005		SH1 WELLINGTON SOUTH RESURFAC	05/12/22	208.00	9.00	12.30	10.50
NHC540-017		R2 CHAINUP STA @ KENOSHA/HOOS	05/12/22	10.00	10.00	27.33	12.00
NHPP 3851-018		US 385 NORTH OF CHEYENNE WELL	05/26/22	384.00	9.00	10.88	12.00
NHPP072A-047		SH-72 RESURFACING: I-70 TO IN	06/09/22	23.00	12.00	18.13	18.13
	WEIGHTED AVERAGE FOR THE SECOND QUARTER			1,630.00	7.97	10.12	10.88
NHPP0702-414		VAIL PASS AUX PHASE 1 CAP 3	07/08/22	80.00	10.70	10.70	10.70
FBR0702-423		VAIL PASS AUX BE F-12-AT PHAS					
C1211-099		SH 121 NORTH SGA SIGNALS	08/25/22	48.00	10.50	95.00	85.00
ER0502-092		US 50 MP 204 EB MONARCH TRUCK	08/29/22	2.00	30.00	26.95	15.85
2670403-065		US40_FLOYD HILL ROUNDABOUTS	09/15/22	23.00	20.00	12.09	13.00
2670703-497		I-70 GENESEE WILDLIFE XING	09/15/22	14.00	20.00	48.44	4.54
SHE2873-193		US 287 & CO 52 INTERSECTION I	09/15/22	50.00	10.00	23.63	20.00
	WEIGHTED AVERAGE FOR THE THIRD QUARTER			217.00	12.26	35.14	29.17

PROJECT NUMBER	ITEM NUMBER/ PROJECT LOCATION	ITEM DESCRIPTION/ PROJECT LOCATION	DATE LET	UNIT/ QUANTITY	ENGR. EST.	AVERAGE BID	AWARDED BID
===== 202-00090		Rem Delineator		Each	=====	=====	=====
NHPP0821-114		SH 82 ASPEN/INDEPENDENCE PASS	10/13/22	25.00	30.00	44.73	16.20
C0831-126		SH83 EL PASO COUNTY TO BAYOU	10/13/22	78.00	12.00	10.00	10.00
NHPP0701-253		I-70 EAST OF DEBEQUE	10/27/22	240.00	8.00	5.33	5.50
STA207A-004		Resurfacing SH207A MANZANOLA	10/27/22	415.00	10.00	9.77	6.30
SHE0242-087		US 24 SAFETY IMPRVMENTS, E OF	11/03/22	7.00	12.00	37.31	17.92
NHPP0853-126		US85C: PLATTEVILLE NORTH MP (11/10/22	298.00	12.00	12.97	13.25
C5502-097		US550 MP 117.28-126.06	11/17/22	350.00	15.00	8.24	5.40
MPR200-280		PUEBLO AREA	11/17/22	20.00	28.00	13.50	25.00
STRC090-011		US 50B AND SH71/CR18 INTERSEC	11/17/22	100.00	12.00	42.75	10.50
STA0711-021		SH71: REGION LINE NORTH	12/01/22	364.00	8.60	5.58	6.00
STR114A-015		SH114 SILLSVILLE SOUTH TO MP3	12/01/22	4,914.00	10.00	13.25	20.00
2670703-487		I-70 BRIDGES OVER WARD ROAD-	12/01/22	6.00	20.00	41.13	55.00
NHPP0701-252		I-70 RIFLE TO SILT SLAB REPLA	12/01/22	37.00	8.00	34.00	28.00
IM025A-050		I25-MP103.9 - INTERSECTION DR	12/01/22	6.00	15.00	9.00	11.00
NHPP083A-046		SH83 RESURFACING STROH RD TO	12/08/22	177.00	9.25	19.50	14.99
NHPP0063-048		US6 / 20 ROAD INTERSECTION IM	12/15/22	26.00	15.00	23.55	5.25
FSA0853-122		WCR14.5 AND US-85, FORT LUPTO	12/15/22	3.00	75.00	110.13	27.00
NHPP0931-033		SH93:US6 TO 58TH RESURFACING	12/15/22	91.00	10.00	25.90	20.50
NHPP0502-090		SH 50 MP 134.6-136 GUNNISON C	12/22/22	16.00	20.00	30.99	14.24
STA0361-129		US 36: HYGIENE RD AND NELSON	12/22/22	232.00	12.00	22.01	37.34
BR012A-048		CO 12 STRUCTURE P-17-F AT MP	12/22/22	21.00	10.00	25.07	40.00
STA385A-016		SH 385 MP 97.76	12/22/22	30.00	15.00	25.53	11.11
STR096A-050		SH 96 MP 168.99 TO 193.77	12/22/22	566.00	8.10	19.67	6.00
		WEIGHTED AVERAGE FOR THE FOURTH QUARTER		8,022.00	10.31	14.38	16.19
		WEIGHTED AVERAGE FOR THE YEAR		12,301.00	9.45	13.95	14.62
===== 202-00150		Rem Wall		Each	=====	=====	=====
STM1151-038		SH115 MP 27 TO MP 38	04/21/22	6.00	500.00	3661.66	3411.36
		WEIGHTED AVERAGE FOR THE SECOND QUARTER		6.00	500.00	3661.66	3411.36
		WEIGHTED AVERAGE FOR THE YEAR		6.00	500.00	3661.66	3411.36
===== 202-00155		Rem Wall		Lin Foot	=====	=====	=====
STU0252-457		I-25:ALAMEDA RIVER PH 2.0	11/03/22	222.00	80.00	53.71	79.00
STRC090-011		US 50B AND SH71/CR18 INTERSEC	11/17/22	350.00	58.00	58.50	25.00

COLORADO DEPARTMENT OF TRANSPORTATION
 ITEM UNIT COSTS BY PROJECTS -- 2022 COST DATA

11:31 Wednesday, March 8, 2023 18

PROJECT NUMBER	ITEM NUMBER/ PROJECT LOCATION	ITEM DESCRIPTION/ PROJECT LOCATION	DATE LET	UNIT/ QUANTITY	ENGR. EST.	AVERAGE BID	AWARDED BID
=====	202-00155	Rem Wall		Lin Foot	=====	=====	=====
STAM420-001		US 285 AT HWY 9C IMPROVEMENTS	12/01/22	180.00	270.00	193.98	104.27
BR2854-148		INTERSECTION OF US 285 & SH 9					
STM0091-046		ADA RAMP IMPROVEMENTS - FAIRP					
IM025A-050		I25-MP103.9 - INTERSECTION DR	12/01/22	31.00	50.00	186.67	180.00
STR096A-050		SH 96 MP 168.99 TO 193.77	12/22/22	48.00	95.00	135.33	100.00
		WEIGHTED AVERAGE FOR THE FOURTH QUARTER		831.00	111.64	109.01	66.71
		WEIGHTED AVERAGE FOR THE YEAR		831.00	111.64	109.01	66.71
=====	202-00160	Rem Wall		Sq Foot	=====	=====	=====
C5502-097		US550 MP 117.28-126.06	11/17/22	226.00	45.00	31.16	21.00
		WEIGHTED AVERAGE FOR THE FOURTH QUARTER		226.00	45.00	31.16	21.00
		WEIGHTED AVERAGE FOR THE YEAR		226.00	45.00	31.16	21.00
=====	202-00170	Grinding And Texturing Conc Pvmt		Sq Yard	=====	=====	=====
C0762-055			02/17/22	133,975.00	4.50	4.68	4.25
		WEIGHTED AVERAGE FOR THE FIRST QUARTER		133,975.00	4.50	4.68	4.25
NHPP0701-252		I-70 RIFLE TO SILT SLAB REPLA	12/01/22	101,079.00	5.50	5.60	4.80
		WEIGHTED AVERAGE FOR THE FOURTH QUARTER		101,079.00	5.50	5.60	4.80
		WEIGHTED AVERAGE FOR THE YEAR		235,054.00	4.93	4.93	4.49
=====	202-00172	Diamond Grinding Concrete Pavement		Sq Yard	=====	=====	=====
STA0252-459			02/03/22	60,000.00	5.50	7.95	5.00
		WEIGHTED AVERAGE FOR THE FIRST QUARTER		60,000.00	5.50	7.95	5.00
		WEIGHTED AVERAGE FOR THE YEAR		60,000.00	5.50	7.95	5.00
=====	202-00190	Rem of Conc Median Cover Matl		Sq Yard	=====	=====	=====
NHPP0702-383		I-70 EB AUX FRISCO TO SILVERT	01/13/22	64.00	20.00	81.33	92.00

COLORADO DEPARTMENT OF TRANSPORTATION
ITEM UNIT COSTS BY PROJECTS -- 2022 COST DATA

11:31 Wednesday, March 8, 2023 19

PROJECT NUMBER	ITEM NUMBER/ PROJECT LOCATION	ITEM DESCRIPTION/ PROJECT LOCATION	DATE LET	UNIT/ QUANTITY	ENGR. EST.	AVERAGE BID	AWARDED BID
=====	202-00190	Rem of Conc Median Cover Matl		Sq Yard	=====	=====	=====
NHPP0063-063			02/24/22	1,756.00	10.00	7.68	9.00
NHPP 0761-238		I-76 DAHLIA TO YORK	03/10/22	200.00	15.00	16.64	14.00
C0761-239							
NHM765-007			03/31/22	3,438.00	10.00	9.85	2.70
		WEIGHTED AVERAGE FOR THE FIRST QUARTER		5,458.00	10.30	11.51	6.19
CC030-081		ADA RAMP AND CURBS - FT. LUPT	04/14/22	561.00	35.00	21.61	13.00
		WEIGHTED AVERAGE FOR THE SECOND QUARTER		561.00	35.00	21.61	13.00
NHPP0063-054		US 6 FROM I70-B TO 33 RD. (MP	08/18/22	484.00	20.00	16.58	14.00
SHE2873-193		US 287 & CO 52 INTERSECTION I	09/15/22	1,164.00	9.00	20.62	18.00
		WEIGHTED AVERAGE FOR THE THIRD QUARTER		1,648.00	12.23	20.12	16.83
TRG0253-264		I-25 AND SH 119 PARK-N-RIDE	10/27/22	158.00	35.00	22.53	10.00
NHPP083A-046		SH83 RESURFACING STROH RD TO	12/08/22	28.00	65.00	54.49	44.97
NHPP0931-033		SH93:US6 TO 58TH RESURFACING	12/15/22	488.00	15.00	24.69	20.50
		WEIGHTED AVERAGE FOR THE FOURTH QUARTER		674.00	21.77	24.36	19.06
		WEIGHTED AVERAGE FOR THE YEAR		8,341.00	13.27	15.96	9.79
=====	202-00195	Rem of Median Cover		Sq Yard	=====	=====	=====
NHPP2873-189		US 287 (FEDERAL BLVD) - COLFA	01/06/22	32.00	14.00	52.20	44.92
		WEIGHTED AVERAGE FOR THE FIRST QUARTER		32.00	14.00	52.20	44.92
NHPP072A-047		SH-72 RESURFACING: I-70 TO IN	06/09/22	36.00	18.00	21.69	21.69
		WEIGHTED AVERAGE FOR THE SECOND QUARTER		36.00	18.00	21.69	21.69
C1211-099		SH 121 NORTH SGA SIGNALS	08/25/22	444.00	44.00	40.00	42.00
		WEIGHTED AVERAGE FOR THE THIRD QUARTER		444.00	44.00	40.00	42.00

COLORADO DEPARTMENT OF TRANSPORTATION
 ITEM UNIT COSTS BY PROJECTS -- 2022 COST DATA

11:31 Wednesday, March 8, 2023 20

PROJECT NUMBER	ITEM NUMBER/ PROJECT LOCATION	ITEM DESCRIPTION/ PROJECT LOCATION	DATE LET	UNIT/ QUANTITY	ENGR. EST.	AVERAGE BID	AWARDED BID
=====	202-00195	Rem of Median Cover		Sq Yard	=====		
STRC090-011		US 50B AND SH71/CR18 INTERSEC	11/17/22	22.00	40.00	45.80	50.10
		WEIGHTED AVERAGE FOR THE FOURTH QUARTER		22.00	40.00	45.80	50.10
		WEIGHTED AVERAGE FOR THE YEAR		534.00	40.28	41.06	41.14
=====	202-00200	Rem Sidewalk		Sq Yard	=====		
NHPP2873-189		US 287 (FEDERAL BLVD) - COLFA	01/06/22	904.00	36.00	47.08	44.92
NHPP0702-383		I-70 EB AUX FRISCO TO SILVERT	01/13/22	707.00	50.00	24.13	16.00
NHPP0063-063			02/24/22	238.00	30.00	16.73	25.00
NHPP 0761-238		I-76 DAHLIA TO YORK	03/10/22	131.00	30.00	16.23	11.00
C0761-239							
CR100-362			03/14/22	3,974.00	79.84	79.84	79.84
STR092A-031			03/17/22	607.00	30.00	15.00	15.00
NHM765-007			03/31/22	295.00	20.00	49.99	4.83
		WEIGHTED AVERAGE FOR THE FIRST QUARTER		6,856.00	61.31	46.05	56.47
NH0504-911			04/07/22	694.00	31.00	29.95	19.90
CC030-081		ADA RAMP AND CURBS - FT. LUPT	04/14/22	1,371.00	30.00	24.18	19.00
2670703-479		I-70 BRIDGE OVER HARLAN	05/05/22	408.00	26.00	24.11	11.50
CM760-047		COLFAX AND QUAIL	05/12/22	52.00	35.50	40.60	40.00
NHPP072A-047		SH-72 RESURFACING: I-70 TO IN	06/09/22	1,480.00	30.00	43.37	43.37
		WEIGHTED AVERAGE FOR THE SECOND QUARTER		4,005.00	29.84	28.36	27.67
NHPP0063-054		US 6 FROM I70-B TO 33 RD. (MP	08/18/22	1,165.00	15.00	17.83	16.50
C1211-099		SH 121 NORTH SGA SIGNALS	08/25/22	625.00	50.00	39.00	38.00
NHPP0701-231		I-70 SALT WASH BRIDGES SCOUR	09/29/22	267.00	40.00	23.39	23.00
		WEIGHTED AVERAGE FOR THE THIRD QUARTER		2,057.00	28.88	24.98	23.88
STA207A-004		Resurfacing SH207A MANZANOLA	10/27/22	122.00	30.00	43.12	43.35

COLORADO DEPARTMENT OF TRANSPORTATION
ITEM UNIT COSTS BY PROJECTS -- 2022 COST DATA

11:31 Wednesday, March 8, 2023 21

PROJECT NUMBER	ITEM NUMBER/ PROJECT LOCATION	ITEM DESCRIPTION/ PROJECT LOCATION	DATE LET	UNIT/ QUANTITY	ENGR. EST.	AVERAGE BID	AWARDED BID
===== 202-00200 Rem Sidewalk Sq Yard =====							
FSAM240-200		SH21B CO SPRINGS SIGNAL REPLA	10/27/22	150.60	30.00	61.13	39.50
TRG0253-264		I-25 AND SH 119 PARK-N-RIDE	10/27/22	539.00	26.80	20.44	12.00
STA3852-015		US 385 HOLYOKE NORTH	10/27/22	440.00	60.00	60.00	60.00
STU0252-457		I-25:ALAMEDA RIVER PH 2.0	11/03/22	2,097.00	50.00	24.17	13.00
C5502-097		US550 MP 117.28-126.06	11/17/22	53.00	100.00	30.27	15.10
STAM420-001		US 285 AT HWY 9C IMPROVEMENTS	12/01/22	621.00	33.00	33.24	48.78
BR2854-148		INTERSECTION OF US 285 & SH 9					
STM0091-046		ADA RAMP IMPROVEMENTS - FAIRP					
2670703-487		I-70 BRIDGES OVER WARD ROAD-	12/01/22	218.00	60.00	18.62	20.00
IM025A-050		I25-MP103.9 - INTERSECTION DR	12/01/22	378.00	25.00	22.67	12.00
NHPP0021-041		SH2 RESURFACING MLK TO 52ND	12/01/22	150.10	50.00	28.74	5.63
NHPP083A-046		SH83 RESURFACING STROH RD TO	12/08/22	266.00	32.00	38.49	44.97
NHPP0931-033		SH93:US6 TO 58TH RESURFACING	12/15/22	341.00	25.00	23.86	20.50
		WEIGHTED AVERAGE FOR THE FOURTH QUARTER		5,375.70	42.18	26.99	24.40
		WEIGHTED AVERAGE FOR THE YEAR		18,293.70	45.15	32.79	37.07
===== 202-00201 Rem Curb Lin Foot =====							
NHPP2873-189		US 287 (FEDERAL BLVD) - COLFA	01/06/22	93.00	10.00	17.60	14.97
C0762-055			02/17/22	4,648.00	5.00	3.61	0.26
NHPP0063-063			02/24/22	18,887.00	6.00	7.33	6.00
NHPP 0761-238		I-76 DAHLIA TO YORK	03/10/22	271.00	11.00	9.30	6.50
C0761-239							
BRC040-057			03/17/22	120.00	15.00	36.00	23.00
NHM765-007			03/31/22	199.00	12.00	15.04	7.02
		WEIGHTED AVERAGE FOR THE FIRST QUARTER		24,218.00	5.97	6.62	5.03
CC030-081		ADA RAMP AND CURBS - FT. LUPT	04/14/22	59.00	22.00	16.49	13.00
2670703-479		I-70 BRIDGE OVER HARLAN	05/05/22	86.00	25.00	14.04	14.16
NHPP072A-047		SH-72 RESURFACING: I-70 TO IN	06/09/22	299.00	10.00	14.46	14.46
		WEIGHTED AVERAGE FOR THE SECOND QUARTER		444.00	14.50	14.60	14.21
STR0711-022		SH 71 OVER THE ARKANSAS	08/04/22	1,783.00	12.63	10.50	5.00
SHE2873-193		US 287 & CO 52 INTERSECTION I	09/15/22	4,060.00	7.00	7.51	8.00
		WEIGHTED AVERAGE FOR THE THIRD QUARTER		5,843.00	8.72	8.05	7.08

COLORADO DEPARTMENT OF TRANSPORTATION
 ITEM UNIT COSTS BY PROJECTS -- 2022 COST DATA

11:31 Wednesday, March 8, 2023 22

PROJECT NUMBER	ITEM NUMBER/ PROJECT LOCATION	ITEM DESCRIPTION/ PROJECT LOCATION	DATE LET	UNIT/ QUANTITY	ENGR. EST.	AVERAGE BID	AWARDED BID
=====	202-00201	Rem Curb		Lin Foot	=====		
STAM420-001		US 285 AT HWY 9C IMPROVEMENTS	12/01/22	59.00	9.74	112.44	79.26
BR2854-148		INTERSECTION OF US 285 & SH 9					
STM0091-046		ADA RAMP IMPROVEMENTS - FAIRP					
2670703-487		I-70 BRIDGES OVER WARD ROAD-	12/01/22	530.00	25.90	7.90	7.70
NHPP083A-046		SH83 RESURFACING STROH RD TO	12/08/22	6.00	27.00	24.49	24.98
		WEIGHTED AVERAGE FOR THE FOURTH QUARTER		=====	=====	=====	=====
				595.00	24.31	16.49	14.97
		WEIGHTED AVERAGE FOR THE YEAR		=====	=====	=====	=====
				31,100.00	6.96	7.46	5.74
=====	202-00202	Rem Gutter		Lin Foot	=====		
NHPP0063-063			02/24/22	36.00	25.00	30.18	54.00
NHPP 0761-238		I-76 DAHLIA TO YORK	03/10/22	119.00	16.00	11.02	7.00
C0761-239							
NHM765-007			03/31/22	129.00	15.00	17.52	7.02
		WEIGHTED AVERAGE FOR THE FIRST QUARTER		-----	-----	-----	-----
				284.00	16.69	13.78	12.97
NHPP072A-047		SH-72 RESURFACING: I-70 TO IN	06/09/22	55.00	20.00	14.46	14.46
		WEIGHTED AVERAGE FOR THE SECOND QUARTER		-----	-----	-----	-----
				55.00	20.00	14.46	14.46
NHPP0063-054		US 6 FROM I70-B TO 33 RD. (MP	08/18/22	312.00	16.00	8.62	7.25
		WEIGHTED AVERAGE FOR THE THIRD QUARTER		-----	-----	-----	-----
				312.00	16.00	8.62	7.25
STU0252-457		I-25:ALAMEDA RIVER PH 2.0	11/03/22	158.00	20.00	17.00	8.50
		WEIGHTED AVERAGE FOR THE FOURTH QUARTER		-----	-----	-----	-----
				158.00	20.00	17.00	8.50
		WEIGHTED AVERAGE FOR THE YEAR		=====	=====	=====	=====
				809.00	17.29	13.13	9.99
=====	202-00203	Rem Curb and Gutter		Lin Foot	=====		
NHPP2873-189		US 287 (FEDERAL BLVD) - COLFA	01/06/22	257.00	14.00	23.47	14.97

PROJECT NUMBER	ITEM NUMBER/ PROJECT LOCATION	ITEM DESCRIPTION/ PROJECT LOCATION	DATE LET	UNIT/ QUANTITY	ENGR. EST.	AVERAGE BID	AWARDED BID
===== 202-00203							
NHPP0702-383		Rem Curb and Gutter		Lin Foot			
NHPP0063-063		I-70 EB AUX FRISCO TO SILVERT	01/13/22	3,040.00	15.00	8.61	7.00
NHPP 0761-238			02/24/22	15,008.00	6.00	8.33	8.00
C0761-239		I-76 DAHLIA TO YORK	03/10/22	200.00	13.00	9.37	7.00
CR100-362			03/14/22	4,715.00	29.64	29.64	29.64
BRC040-057			03/17/22	120.00	15.00	35.00	34.00
STR092A-031			03/17/22	845.00	12.00	15.00	15.00
NHM765-007			03/31/22	17,689.00	8.00	5.68	1.25
WEIGHTED AVERAGE FOR THE FIRST QUARTER				41,874.00	10.39	8.32	7.77
NH0504-911			04/07/22	2,720.00	10.00	12.50	11.00
CC030-081		ADA RAMP AND CURBS - FT. LUPT	04/14/22	2,307.00	20.00	17.38	15.00
2670703-479		I-70 BRIDGE OVER HARLAN	05/05/22	1,583.00	14.00	10.09	15.25
CM760-047		COLFAX AND QUAIL	05/12/22	103.00	18.00	17.40	19.00
NHPP072A-047		SH-72 RESURFACING: I-70 TO IN	06/09/22	1,415.00	20.00	14.46	14.46
WEIGHTED AVERAGE FOR THE SECOND QUARTER				8,128.00	15.46	13.18	13.67
NHPP0063-054		US 6 FROM I70-B TO 33 RD. (MP	08/18/22	4,015.00	18.00	7.57	8.75
C1211-099		SH 121 NORTH SGA SIGNALS	08/25/22	1,440.00	25.00	18.00	18.00
SHE2873-193		US 287 & CO 52 INTERSECTION I	09/15/22	3,741.00	15.00	10.78	11.00
WEIGHTED AVERAGE FOR THE THIRD QUARTER				9,196.00	17.88	10.63	11.11
STA207A-004		Resurfacing SH207A MANZANOLA	10/27/22	532.00	20.00	15.13	12.40
FSAM240-200		SH21B CO SPRINGS SIGNAL REPLA	10/27/22	422.00	15.00	30.40	15.60
TRG0253-264		I-25 AND SH 119 PARK-N-RIDE	10/27/22	1,013.00	18.00	11.82	14.00
STA3852-015		US 385 HOLYOKE NORTH	10/27/22	760.00	40.00	34.00	34.00
NHPP0343-048		US 34 (MP 169.3-171.4)	11/01/22	1,140.00	13.00	10.61	6.50
STU0252-457		I-25:ALAMEDA RIVER PH 2.0	11/03/22	1,182.00	20.00	17.63	6.50
STRC090-011		US 50B AND SH71/CR18 INTERSEC	11/17/22	194.00	25.00	25.60	24.20
STAM420-001		US 285 AT HWY 9C IMPROVEMENTS	12/01/22	1,118.00	15.00	23.00	28.98
BR2854-148		INTERSECTION OF US 285 & SH 9					
STM0091-046		ADA RAMP IMPROVEMENTS - FAIRP					
2670703-487		I-70 BRIDGES OVER WARD ROAD-	12/01/22	785.00	21.50	11.86	14.00
IM025A-050		I25-MP103.9 - INTERSECTION DR	12/01/22	902.00	20.00	11.33	3.00
NHPP0021-041		SH2 RESURFACING MLK TO 52ND	12/01/22	123.80	30.00	12.02	2.61
NHPP083A-046		SH83 RESURFACING STROH RD TO	12/08/22	563.00	28.00	24.49	24.98

COLORADO DEPARTMENT OF TRANSPORTATION
ITEM UNIT COSTS BY PROJECTS -- 2022 COST DATA

11:31 Wednesday, March 8, 2023 24

PROJECT NUMBER	ITEM NUMBER/ PROJECT LOCATION	ITEM DESCRIPTION/ PROJECT LOCATION	DATE LET	UNIT/ QUANTITY	ENGR. EST.	AVERAGE BID	AWARDED BID
=====	202-00203	Rem Curb and Gutter		Lin Foot	=====	=====	=====
NHPP0063-048		US6 / 20 ROAD INTERSECTION IM	12/15/22	72.00	20.00	25.69	31.50
NHPP0931-033		SH93:US6 TO 58TH RESURFACING	12/15/22	1,096.00	15.00	11.93	10.25
		WEIGHTED AVERAGE FOR THE FOURTH QUARTER		9,902.80	19.99	15.54	14.84
		WEIGHTED AVERAGE FOR THE YEAR		69,100.80	13.36	10.63	9.92
=====	202-00204	Rem C, G and Sidewalk		Lin Foot	=====	=====	=====
STA0361-129		US 36: HYGIENE RD AND NELSON	12/22/22	155.00	35.00	37.66	19.71
		WEIGHTED AVERAGE FOR THE FOURTH QUARTER		155.00	35.00	37.66	19.71
		WEIGHTED AVERAGE FOR THE YEAR		155.00	35.00	37.66	19.71
=====	202-00206	Rem Conc Curb Ramp		Sq Yard	=====	=====	=====
NHPP2873-189		US 287 (FEDERAL BLVD) - COLFA	01/06/22	1,489.00	36.00	48.01	44.92
NHM765-007			03/31/22	321.00	20.00	29.53	9.14
		WEIGHTED AVERAGE FOR THE FIRST QUARTER		1,810.00	33.16	45.44	38.57
NH0504-911			04/07/22	306.00	42.00	35.00	30.00
CC030-081		ADA RAMP AND CURBS - FT. LUPT	04/14/22	2,582.00	32.00	23.86	18.00
2670703-479		I-70 BRIDGE OVER HARLAN	05/05/22	31.00	40.00	64.54	102.51
CM760-047		COLFAX AND QUAIL	05/12/22	24.00	35.00	44.40	43.00
		WEIGHTED AVERAGE FOR THE SECOND QUARTER		2,943.00	33.15	25.81	20.34
C1211-099		SH 121 NORTH SGA SIGNALS	08/25/22	534.00	50.00	41.00	42.00
		WEIGHTED AVERAGE FOR THE THIRD QUARTER		534.00	50.00	41.00	42.00
STA207A-004		Resurfacing SH207A MANZANOLA	10/27/22	31.00	60.00	47.43	43.30
FSAM240-200		SH21B CO SPRINGS SIGNAL REPLA	10/27/22	374.00	25.00	42.69	36.75

COLORADO DEPARTMENT OF TRANSPORTATION
ITEM UNIT COSTS BY PROJECTS -- 2022 COST DATA

11:31 Wednesday, March 8, 2023 25

PROJECT NUMBER	ITEM NUMBER/ PROJECT LOCATION	ITEM DESCRIPTION/ PROJECT LOCATION	DATE LET	UNIT/ QUANTITY	ENGR. EST.	AVERAGE BID	AWARDED BID
===== 202-00206							
		Rem Conc Curb Ramp		Sq Yard			
TRG0253-264		I-25 AND SH 119 PARK-N-RIDE	10/27/22	88.00	50.00	35.09	30.00
STA3852-015		US 385 HOLYOKE NORTH	10/27/22	751.00	45.00	34.00	34.00
STAM420-001		US 285 AT HWY 9C IMPROVEMENTS	12/01/22	603.00	32.26	44.35	46.74
BR2854-148		INTERSECTION OF US 285 & SH 9					
STM0091-046		ADA RAMP IMPROVEMENTS - FAIRP					
NHPP0021-041		SH2 RESURFACING MLK TO 52ND	12/01/22	156.70	65.00	28.81	5.99
	WEIGHTED AVERAGE FOR THE FOURTH QUARTER			2,003.70	39.45	40.04	36.12
	WEIGHTED AVERAGE FOR THE YEAR			7,290.70	36.12	36.30	30.79
===== 202-00207							
		Rem of Brick Pavers		Sq Yard			
CM760-047		COLFAX AND QUAIL	05/12/22	2.00	29.00	88.00	63.00
	WEIGHTED AVERAGE FOR THE SECOND QUARTER			2.00	29.00	88.00	63.00
	WEIGHTED AVERAGE FOR THE YEAR			2.00	29.00	88.00	63.00
===== 202-00210							
		Rem Conc Pavement		Sq Yard			
STA0252-459			02/03/22	1,606.00	26.00	139.33	146.00
NHPP0063-063			02/24/22	237.00	40.00	18.35	24.00
NHPP 0761-238		I-76 DAHLIA TO YORK	03/10/22	38,581.00	21.00	9.37	7.00
C0761-239							
CR100-362			03/14/22	20.00	95.34	95.34	95.34
STR092A-031			03/17/22	46.00	40.00	25.00	25.00
NHM765-007			03/31/22	722.00	20.00	12.44	5.21
	WEIGHTED AVERAGE FOR THE FIRST QUARTER			41,212.00	21.34	11.39	12.55
===== 202-00211							
NH0504-911			04/07/22	1,139.00	16.00	29.95	9.90
CC030-081		ADA RAMP AND CURBS - FT. LUPT	04/14/22	49.00	50.00	34.80	18.00
2670703-479		I-70 BRIDGE OVER HARLAN	05/05/22	4,015.00	16.00	18.42	15.00
CM760-047		COLFAX AND QUAIL	05/12/22	87.00	45.00	51.90	53.00
NHPP072A-047		SH-72 RESURFACING: I-70 TO IN	06/09/22	136.00	30.00	21.69	21.69
	WEIGHTED AVERAGE FOR THE SECOND QUARTER			5,426.00	17.12	20.04	14.73
===== 202-00212							
NHPP0063-054		US 6 FROM I70-B TO 33 RD. (MP	08/18/22	175.00	25.00	30.79	19.25

PROJECT NUMBER	ITEM NUMBER/ PROJECT LOCATION	ITEM DESCRIPTION/ PROJECT LOCATION	DATE LET	UNIT/ QUANTITY	ENGR. EST.	AVERAGE BID	AWARDED BID
===== 202-00210		Rem Conc Pavement		Sq Yard	=====	=====	=====
C1211-099		SH 121 NORTH SGA SIGNALS	08/25/22	298.00	60.00	48.00	46.00
SHE2873-193		US 287 & CO 52 INTERSECTION I	09/15/22	3,693.00	40.00	27.10	19.00
		WEIGHTED AVERAGE FOR THE THIRD QUARTER		4,166.00	40.80	27.70	20.94
FSAM240-200		SH21B CO SPRINGS SIGNAL REPLA	10/27/22	36.00	20.00	300.75	75.00
TRG0253-264		I-25 AND SH 119 PARK-N-RIDE	10/27/22	3,519.00	35.00	27.74	20.00
C5502-097		US550 MP 117.28-126.06	11/17/22	163.00	50.00	43.77	39.30
STAM420-001		US 285 AT HWY 9C IMPROVEMENTS	12/01/22	70.00	21.00	158.23	338.81
BR2854-148		INTERSECTION OF US 285 & SH 9					
STM0091-046		ADA RAMP IMPROVEMENTS - FAIRP					
2670703-487		I-70 BRIDGES OVER WARD ROAD-	12/01/22	2,839.00	20.00	18.75	25.00
IM025A-050		I25-MP103.9 - INTERSECTION DR	12/01/22	216.00	25.00	30.67	22.00
FSA0853-122		WCR14.5 AND US-85, FORT LUPTO	12/15/22	73.00	120.00	100.76	88.00
		WEIGHTED AVERAGE FOR THE FOURTH QUARTER		6,916.00	29.56	27.15	26.80
		WEIGHTED AVERAGE FOR THE YEAR		57,720.00	23.34	14.57	15.07
===== 202-00212		Rem Conc Pavement (Spec)		Sq Yard	=====	=====	=====
NHPP0705-088		I-70 AGATE STRUCTURE REHAB	10/27/22	86.00	50.00	577.61	221.00
		WEIGHTED AVERAGE FOR THE FOURTH QUARTER		86.00	50.00	577.61	221.00
		WEIGHTED AVERAGE FOR THE YEAR		86.00	50.00	577.61	221.00
===== 202-00215		Rem Conc Pvmt (Planing)		Sq Yard	=====	=====	=====
NHPP0705-088		I-70 AGATE STRUCTURE REHAB	10/27/22	1,000.00	22.00	61.42	65.00
		WEIGHTED AVERAGE FOR THE FOURTH QUARTER		1,000.00	22.00	61.42	65.00
		WEIGHTED AVERAGE FOR THE YEAR		1,000.00	22.00	61.42	65.00
===== 202-00217		Rem Conc Pvmt (Planing) (Spec)		Sq Yard	=====	=====	=====
BRC040-057			03/17/22	2,329.00	25.00	49.00	18.00
		WEIGHTED AVERAGE FOR THE FIRST QUARTER		2,329.00	25.00	49.00	18.00

COLORADO DEPARTMENT OF TRANSPORTATION
ITEM UNIT COSTS BY PROJECTS -- 2022 COST DATA

11:31 Wednesday, March 8, 2023 27

PROJECT NUMBER	ITEM NUMBER/ PROJECT LOCATION	ITEM DESCRIPTION/ PROJECT LOCATION	DATE LET	UNIT/ QUANTITY	ENGR. EST.	AVERAGE BID	AWARDED BID
===== 202-00217		Rem Conc Pvmt (Planing) (Spec)		Sq Yard	=====		
NHPP0252-448		I-25 TREX NARROWS BRIDGE PREV	06/23/22	2,827.00	45.00	49.25	25.00
		WEIGHTED AVERAGE FOR THE SECOND QUARTER		2,827.00	45.00	49.25	25.00
NHPP0705-088		I-70 AGATE STRUCTURE REHAB	10/27/22	3,417.00	50.00	69.49	76.00
NHPP0701-252		I-70 RIFLE TO SILT SLAB REPLA	12/01/22	4,480.00	45.00	29.35	4.70
		WEIGHTED AVERAGE FOR THE FOURTH QUARTER		7,897.00	47.16	53.59	35.55
		WEIGHTED AVERAGE FOR THE YEAR		13,053.00	42.74	51.47	30.13
===== 202-00220		Rem Asphalt Mat		Sq Yard	=====		
NHPP2873-189		US 287 (FEDERAL BLVD) - COLFA	01/06/22	33.00	12.00	92.63	200.37
STR0505-050			01/13/22	16.00	100.00	275.00	250.00
NH0504-910		US50B L-24-B MIN REP AT MP 40	01/13/22	7,067.00	10.00	7.13	5.00
NHPP0702-383		I-70 EB AUX FRISCO TO SILVERT	01/13/22	2,256.00	20.00	34.57	38.00
NHPP1601-083			02/03/22	5,163.00	10.00	10.27	11.00
STA0252-459			02/03/22	10.00	6.71	92.52	82.50
STR0141-031			02/17/22	400.00	8.00	19.83	19.00
NHPP0063-063			02/24/22	13,248.00	6.00	7.68	8.50
NHPP 0761-238		I-76 DAHLIA TO YORK	03/10/22	69,358.00	11.00	5.68	4.50
C0761-239							
NHPP0703-472			03/10/22	100.00	7.00	77.76	145.00
CR100-362			03/14/22	50.00	85.71	85.71	85.71
ER007A-035			03/15/22	1,216.00	11.95	12.78	12.78
STR092A-031			03/17/22	13,999.00	10.00	8.00	8.00
NHM765-007			03/31/22	32,352.00	12.00	13.61	6.03
		WEIGHTED AVERAGE FOR THE FIRST QUARTER		145,268.00	10.76	7.49	6.63
NH0504-911			04/07/22	250.00	3.00	49.10	48.20
CC030-081		ADA RAMP AND CURBS - FT. LUPT	04/14/22	1,145.00	32.00	23.57	13.00
NHPP0702-413		VAIL PASS AUX PHASE 1 CAP 2	04/18/22	3,759.00	4.56	4.56	4.56
STM1151-038		SH115 MP 27 TO MP 38	04/21/22	78,045.00	7.00	4.78	3.70
2670703-479		I-70 BRIDGE OVER HARLAN	05/05/22	5,029.00	8.00	10.97	6.90

PROJECT NUMBER	ITEM NUMBER/ PROJECT LOCATION	ITEM DESCRIPTION/ PROJECT LOCATION	DATE LET	UNIT/ QUANTITY	ENGR. EST.	AVERAGE BID	AWARDED BID
=====	202-00220	Rem Asphalt Mat		Sq Yard	=====	=====	=====
STA0712-019		SH 71: Frieght Improvements	05/12/22	12,775.00	8.00	14.07	14.07
NHC540-017		R2 CHAINUP STA @ KENOSHA/HOOS	05/12/22	1,088.00	8.00	39.33	28.00
CM760-047		COLFAX AND QUAIL	05/12/22	128.00	28.50	42.60	48.00
FSA3921-019		SH 392 AND WCR 55 ISLANDS	06/02/22	119.00	13.00	27.67	25.00
NHPP072A-047		SH-72 RESURFACING: I-70 TO IN	06/09/22	1,526.00	10.00	239.80	239.80
FSA052A-046		SH52 WCR 37 INTERSECTION IMPR	06/09/22	14,511.00	9.00	7.79	4.90
		WEIGHTED AVERAGE FOR THE SECOND QUARTER		118,375.00	7.63	6.93	8.65
NHPP0702-414		VAIL PASS AUX PHASE 1 CAP 3	07/08/22	10,997.00	9.60	9.60	9.60
FBR0702-423		VAIL PASS AUX BE F-12-AT PHAS					
FSA052A-057		SH52 BOX CULVERT EXTENSION (M	08/04/22	80.00	50.00	70.04	25.74
NHPP0063-054		US 6 FROM I70-B TO 33 RD. (MP	08/18/22	21,375.00	6.00	12.79	9.00
C1211-099		SH 121 NORTH SGA SIGNALS	08/25/22	452.00	50.00	48.50	37.00
BR0343-046		US 34 TIMBER BRIDGE REPL. PKG	08/31/22	1,650.00	9.28	27.35	27.35
FBR0343-047		US 6/US 34 TIMBER BRIDGE REPL					
2670403-065		US40_FLOYD HILL ROUNDABOUTS	09/15/22	10,696.00	10.00	14.31	9.50
2670703-497		I-70 GENESEE WILDLIFE KING	09/15/22	4,395.00	12.00	11.08	9.22
SHE2873-193		US 287 & CO 52 INTERSECTION I	09/15/22	2,160.00	20.00	14.63	4.85
		WEIGHTED AVERAGE FOR THE THIRD QUARTER		51,805.00	9.24	13.20	9.93
STA207A-004		Resurfacing SH207A MANZANOLA	10/27/22	2,765.00	35.00	15.30	9.90
FSAM240-200		SH21B CO SPRINGS SIGNAL REPLA	10/27/22	299.00	20.00	32.06	20.25
C170A-002		CRITICAL CULVERT CONST. PKG D	10/27/22	164.00	70.00	62.97	6.88
TRG0253-264		I-25 AND SH 119 PARK-N-RIDE	10/27/22	5,703.00	8.25	9.04	3.50
STA3852-015		US 385 HOLYOKE NORTH	10/27/22	19,013.00	8.00	4.50	4.50
NHPP0343-048		US 34 (MP 169.3-171.4)	11/01/22	492.00	26.00	31.20	50.00
STU0252-457		I-25:ALAMEDA RIVER PH 2.0	11/03/22	18,773.00	10.00	10.96	10.50
SHE0242-087		US 24 SAFETY IMPRVMENTS, E OF	11/03/22	644.00	11.00	38.78	17.33
NHPP0853-126		US85C: PLATTEVILLE NORTH MP (11/10/22	1,318.00	30.00	10.53	9.75
C5502-097		US550 MP 117.28-126.06	11/17/22	20,464.00	10.00	14.19	19.30
STRC090-011		US 50B AND SH71/CR18 INTERSEC	11/17/22	6,283.00	6.00	13.10	19.20
STAM420-001		US 285 AT HWY 9C IMPROVEMENTS	12/01/22	29,832.00	3.00	5.97	2.12
BR2854-148		INTERSECTION OF US 285 & SH 9					
STM0091-046		ADA RAMP IMPROVEMENTS - FAIRP					
STR114A-015		SH114 SILLSVILLE SOUTH TO MP3	12/01/22	12,084.00	10.00	16.25	22.00
2670703-487		I-70 BRIDGES OVER WARD ROAD-	12/01/22	5,944.00	10.00	10.04	9.40
IM025A-050		I25-MP103.9 - INTERSECTION DR	12/01/22	9,192.00	8.00	10.00	7.00
NHPP0021-041		SH2 RESURFACING MLK TO 52ND	12/01/22	427.50	75.00	45.80	55.67
NHPP0063-048		US6 / 20 ROAD INTERSECTION IM	12/15/22	3,405.00	9.00	15.40	7.90
FSA0853-122		WCR14.5 AND US-85, FORT LUPTO	12/15/22	418.00	50.00	42.04	23.00

COLORADO DEPARTMENT OF TRANSPORTATION
ITEM UNIT COSTS BY PROJECTS -- 2022 COST DATA

11:31 Wednesday, March 8, 2023 29

PROJECT NUMBER	ITEM NUMBER/ PROJECT LOCATION	ITEM DESCRIPTION/ PROJECT LOCATION	DATE LET	UNIT/ QUANTITY	ENGR. EST.	AVERAGE BID	AWARDED BID
===== 202-00220 Rem Asphalt Mat Sq Yard =====							
NHPP0931-033		SH93:US6 TO 58TH RESURFACING	12/15/22	2,089.00	10.00	12.98	14.35
NHPP0502-090		SH 50 MP 134.6-136 GUNNISON C	12/22/22	3,916.00	10.00	8.86	22.16
STA0361-129		US 36: HYGIENE RD AND NELSON	12/22/22	6,909.00	6.00	9.07	1.95
BR012A-048		CO 12 STRUCTURE P-17-F AT MP	12/22/22	4,352.00	21.00	12.00	10.00
STA385A-016		SH 385 MP 97.76	12/22/22	11,268.00	5.00	10.81	6.25
		WEIGHTED AVERAGE FOR THE FOURTH QUARTER		165,754.50	8.92	10.63	10.42
		WEIGHTED AVERAGE FOR THE YEAR		481,202.50	9.19	8.66	8.84
===== 202-00222 Removal of Detour Pavement Sq Yard =====							
NH0504-911			04/07/22	1,440.00	5.21	7.45	8.90
		WEIGHTED AVERAGE FOR THE SECOND QUARTER		1,440.00	5.21	7.45	8.90
STU0252-457		I-25:ALAMEDA RIVER PH 2.0	11/03/22	1,470.00	20.00	15.33	27.00
		WEIGHTED AVERAGE FOR THE FOURTH QUARTER		1,470.00	20.00	15.33	27.00
		WEIGHTED AVERAGE FOR THE YEAR		2,910.00	12.68	12.22	18.04
===== 202-00226 Rem of Asph Mat (Special) Sq Yard =====							
NHM765-007			03/31/22	15,032.00	20.00	9.98	8.73
		WEIGHTED AVERAGE FOR THE FIRST QUARTER		15,032.00	20.00	9.98	8.73
STA001A-005		SH1 WELLINGTON SOUTH RESURFAC	05/12/22	5.00	50.00	502.00	230.00
		WEIGHTED AVERAGE FOR THE SECOND QUARTER		5.00	50.00	502.00	230.00
		WEIGHTED AVERAGE FOR THE YEAR		15,037.00	20.01	10.57	9.04
===== 202-00240 Rem Asphalt Mat (Planing) Sq Yard =====							
NHPP2873-189		US 287 (FEDERAL BLVD) - COLFA	01/06/22	79,039.00	2.60	4.84	3.33

COLORADO DEPARTMENT OF TRANSPORTATION
ITEM UNIT COSTS BY PROJECTS -- 2022 COST DATA

11:31 Wednesday, March 8, 2023 30

PROJECT NUMBER	ITEM NUMBER/ PROJECT LOCATION	ITEM DESCRIPTION/ PROJECT LOCATION	DATE LET	UNIT/ QUANTITY	ENGR. EST.	AVERAGE BID	AWARDED BID
===== 202-00240							
NHPP0702-383		Rem Asphalt Mat (Planing)		Sq Yard			
	I-70 EB AUX FRISCO TO SILVERT		01/13/22	89,107.00	3.00	3.91	2.50
NHPP1601-083			02/03/22	1,795.00	5.00	17.29	12.00
C0762-055			02/17/22	126,303.00	2.00	1.93	1.50
STR0141-031			02/17/22	33,569.00	5.00	4.27	3.30
NHPP0063-063			02/24/22	122,804.00	2.50	3.85	2.45
STA 067A-048	Hwy 67A MP 0.00 TO MP 11.05 I		03/03/22	9,160.00	4.57	5.85	7.00
NHPP 0761-238	I-76 DAHLIA TO YORK		03/10/22	14,018.00	7.50	4.79	3.50
C0761-239							
NHPP0703-472			03/10/22	324,332.00	2.40	2.36	2.25
ER007A-035			03/15/22	257,206.00	1.76	2.02	2.02
STR160A-034	US160A LA VETA PASS EAST SURF		03/17/22	411,619.00	2.00	2.83	2.66
STR R500-171	Various locations on SH 141 a		03/17/22	1,734.00	14.00	12.33	9.00
STR092A-031			03/17/22	25,696.00	4.00	3.25	3.25
NHM765-007			03/31/22	190.00	10.00	34.71	23.53
WEIGHTED AVERAGE FOR THE FIRST QUARTER				1,496,572.00	2.37	2.99	2.45
NH0504-911			04/07/22	627,069.00	3.00	2.51	1.76
STM1151-038	SH115 MP 27 TO MP 38		04/21/22	8,654.00	7.00	4.51	4.08
2670703-479	I-70 BRIDGE OVER HARLAN		05/05/22	6,204.00	3.00	5.48	4.10
STA0712-019	SH 71: Frieght Improvements		05/12/22	45,074.00	3.50	3.05	3.05
STA001A-005	SH1 WELLINGTON SOUTH RESURFAC		05/12/22	24,391.00	6.50	2.48	3.25
NHC540-017	R2 CHAINUP STA @ KENOSHA/HOOS		05/12/22	1,616.00	2.00	7.33	5.00
CM760-047	COLFAX AND QUAIL		05/12/22	282.00	6.50	23.80	16.00
NHPP 3851-018	US 385 NORTH OF CHEYENNE WELL		05/26/22	201,873.00	3.50	2.13	3.00
NHPP072A-047	SH-72 RESURFACING: I-70 TO IN		06/09/22	164,244.00	6.00	3.81	3.81
FSA052A-046	SH52 WCR 37 INTERSECTION IMPR		06/09/22	5,594.00	7.50	3.47	2.40
WEIGHTED AVERAGE FOR THE SECOND QUARTER				1,085,001.00	3.70	2.68	2.43
NHPP0702-414	VAIL PASS AUX PHASE 1 CAP 3		07/08/22	4,769.00	2.71	2.71	2.71
FBR0702-423	VAIL PASS AUX BE F-12-AT PHAS						
FSA052A-057	SH52 BOX CULVERT EXTENSION (M		08/04/22	297.00	25.00	27.28	17.85
STR0711-022	SH 71 OVER THE ARKANSAS		08/04/22	472.00	3.00	27.67	24.00
NHPP0063-054	US 6 FROM I70-B TO 33 RD. (MP		08/18/22	5,530.00	8.00	6.40	7.25
BR0343-046	US 34 TIMBER BRIDGE REPL. PKG		08/31/22	10,540.00	4.81	6.53	6.53
FBR0343-047	US 6/US 34 TIMBER BRIDGE REPL						
2670403-065	US40 FLOYD HILL ROUNDABOUTS		09/15/22	807.00	25.00	12.36	19.00
2670703-497	I-70_GENESEE WILDLIFE KING		09/15/22	18,517.00	3.60	4.36	2.55
SHE2873-193	US 287 & CO 52 INTERSECTION I		09/15/22	12,160.00	6.50	4.08	3.80
WEIGHTED AVERAGE FOR THE THIRD QUARTER				53,092.00	5.32	4.74	4.66

PROJECT NUMBER	ITEM NUMBER/ PROJECT LOCATION	ITEM DESCRIPTION/ PROJECT LOCATION	DATE LET	UNIT/ QUANTITY	ENGR. EST.	AVERAGE BID	AWARDED BID
===== 202-00240		Rem Asphalt Mat (Planing)		Sq Yard	=====		
NHPP0701-253		I-70 EAST OF DEBEQUE	10/27/22	12,571.00	8.08	5.80	4.80
STA207A-004		Resurfacing SH207A MANZANOLA	10/27/22	38,057.00	6.00	4.20	3.60
STA3852-015		US 385 HOLYOKE NORTH	10/27/22	166,058.00	2.80	1.78	1.78
NHPP0343-048		US 34 (MP 169.3-171.4)	11/01/22	850.00	4.00	10.00	5.80
STU0252-457		I-25:ALAMEDA RIVER PH 2.0	11/03/22	3,777.00	10.00	5.05	7.00
SHE0242-087		US 24 SAFETY IMPRVMTS, E OF	11/03/22	4,090.00	3.00	7.03	6.09
STR064A-010		SH 64 AND SH 13 AT MEEKER	11/10/22	5,357.00	4.00	14.00	8.00
NHPP0853-126		US85C: PLATTEVILLE NORTH MP (11/10/22	42,890.00	3.20	3.36	2.05
C5502-097		US550 MP 117.28-126.06	11/17/22	103,148.00	3.00	2.51	2.15
STRC090-011		US 50B AND SH71/CR18 INTERSEC	11/17/22	8.00	25.00	272.50	295.00
STAM420-001		US 285 AT HWY 9C IMPROVEMENTS	12/01/22	10,007.00	3.00	4.60	1.71
BR2854-148		INTERSECTION OF US 285 & SH 9					
STM0091-046		ADA RAMP IMPROVEMENTS - FAIRP					
STA0711-021		SH71: REGION LINE NORTH	12/01/22	2,319.00	4.60	6.95	7.00
STR114A-015		SH114 SILLSVILLE SOUTH TO MP3	12/01/22	8,939.00	5.00	11.50	9.00
2670703-487		I-70 BRIDGES OVER WARD ROAD-	12/01/22	9,524.00	2.50	4.50	6.20
IM025A-050		I25-MP103.9 - INTERSECTION DR	12/01/22	2,492.00	3.00	6.03	3.60
STR318A-001		SH 318 MP 0 - 12.5 MOFFAT COU	12/01/22	1,689.00	8.00	13.05	17.10
STR109A-019		M-22-AY BRIDGE REHAB ON SH109	12/01/22	6,966.00	8.00	8.36	6.71
NHPP0021-041		SH2 RESURFACING MLK TO 52ND	12/01/22	87,921.90	4.00	3.77	2.65
NHPP083A-046		SH83 RESURFACING STROH RD TO	12/08/22	136,176.00	2.00	2.94	1.97
NHPP0063-048		US6 / 20 ROAD INTERSECTION IM	12/15/22	3,141.00	10.00	6.82	5.60
NHPP0931-033		SH93:US6 TO 58TH RESURFACING	12/15/22	133,972.00	3.50	3.59	2.67
NHPP0502-090		SH 50 MP 134.6-136 GUNNISON C	12/22/22	22,531.00	4.00	3.14	5.59
STR0092-024		SH 9 North of Silverthorne	12/22/22	29,688.00	5.00	5.88	7.45
STA0361-129		US 36: HYGIENE RD AND NELSON	12/22/22	113,135.00	3.00	3.25	2.76
STA385A-016		SH 385 MP 97.76	12/22/22	922.00	10.00	20.06	10.24
STR096A-050		SH 96 MP 168.99 TO 193.77	12/22/22	5,612.00	7.40	8.00	7.00
		WEIGHTED AVERAGE FOR THE FOURTH QUARTER		951,840.90	3.42	3.41	2.75
		WEIGHTED AVERAGE FOR THE YEAR		3,586,505.90	3.09	3.12	2.57
===== 202-00246		Rem Asphalt Mat (Planing)(Special)		Sq Yard	=====		
NHPP1601-083			02/03/22	5.00	25.00	2713.40	2100.00
C0762-055			02/17/22	1,880.00	20.00	11.09	9.50
BRC040-057			03/17/22	1,189.00	12.00	19.50	9.00
STR R500-171		Various locations on SH 141 a	03/17/22	955.00	46.00	26.51	10.00
		WEIGHTED AVERAGE FOR THE FIRST QUARTER		4,029.00	23.81	18.43	12.07
NH0504-911			04/07/22	4,113.00	15.00	6.45	7.90

PROJECT NUMBER	ITEM NUMBER/ PROJECT LOCATION	ITEM DESCRIPTION/ PROJECT LOCATION	DATE LET	UNIT/ QUANTITY	ENGR. EST.	AVERAGE BID	AWARDED BID
=====	202-00246	Rem Asphalt Mat (Planing) (Special)		Sq Yard	=====	=====	=====
STM1151-038		SH115 MP 27 TO MP 38	04/21/22	314.00	32.00	30.22	33.38
		WEIGHTED AVERAGE FOR THE SECOND QUARTER		4,427.00	16.21	10.26	9.71
STA0711-021		SH71: REGION LINE NORTH	12/01/22	386.00	14.00	60.17	40.00
STR114A-015		SH114 SILLSVILLE SOUTH TO MP3	12/01/22	539.00	35.00	43.00	22.00
STR109A-019		M-22-AY BRIDGE REHAB ON SH109	12/01/22	4,693.00	30.00	35.53	36.06
		WEIGHTED AVERAGE FOR THE FOURTH QUARTER		5,618.00	29.38	29.96	30.97
		WEIGHTED AVERAGE FOR THE YEAR		14,074.00	23.64	21.25	19.97
=====	202-00250	Rem Pavement Marking		Sq Foot	=====	=====	=====
NHPP2873-189		US 287 (FEDERAL BLVD) - COLFA	01/06/22	20,000.00	0.60	1.51	0.74
NH0504-910		US50B L-24-B MIN REP AT MP 40	01/13/22	2,200.00	5.00	3.81	3.33
MTCER400-391		VARIOUS HIGHWAY SEGMENTS ACRO	01/13/22	481,308.00	0.60	0.55	0.30
NHPP0702-383		I-70 EB AUX FRISCO TO SILVERT	01/13/22	106,264.00	1.50	0.87	0.75
STA0252-459			02/03/22	15,000.00	4.00	1.53	1.25
C0762-055			02/17/22	59,529.00	1.50	1.46	1.25
STR0141-031			02/17/22	82,991.00	1.50	0.44	0.37
STR133A-051			02/17/22	98,627.00	1.00	0.74	0.90
NHPP0063-063			02/24/22	10,182.00	1.50	6.68	7.00
STA 067A-048		Hwy 67A MP 0.00 TO MP 11.05 I	03/03/22	300.00	3.00	6.03	6.00
NHPP 0761-238		I-76 DAHLIA TO YORK	03/10/22	30,000.00	1.00	1.50	1.50
C0761-239							
NHPP0703-472			03/10/22	60,000.00	0.60	0.74	0.55
CR100-362			03/14/22	1,000.00	5.35	5.35	5.35
ER007A-035			03/15/22	2,000.00	2.30	2.45	2.45
STR R500-171		Various locations on SH 141 a	03/17/22	1,800.00	4.35	4.42	5.00
STR092A-031			03/17/22	74,326.00	1.00	0.85	0.85
NHM765-007			03/31/22	46,550.00	2.00	1.12	0.74
		WEIGHTED AVERAGE FOR THE FIRST QUARTER		1,092,077.00	1.02	0.82	0.67
CC030-081		ADA RAMP AND CURBS - FT. LUPT	04/14/22	1,710.00	6.00	3.10	2.75
NHPP0702-413		VAIL PASS AUX PHASE 1 CAP 2	04/18/22	11,334.00	2.14	2.14	2.14
2670703-479		I-70 BRIDGE OVER HARLAN	05/05/22	1,000.00	0.70	2.66	2.60
STA001A-005		SH1 WELLINGTON SOUTH RESURFAC	05/12/22	80,000.00	0.75	0.41	0.01
NHPP 3851-018		US 385 NORTH OF CHEYENNE WELL	05/26/22	104,292.00	1.00	1.23	1.20

PROJECT NUMBER	ITEM NUMBER/ PROJECT LOCATION	ITEM DESCRIPTION/ PROJECT LOCATION	DATE LET	UNIT/ QUANTITY	ENGR. EST.	AVERAGE BID	AWARDED BID
=====	202-00250	Rem Pavement Marking		Sq Foot	=====	=====	=====
FSA3921-019		SH 392 AND WCR 55 ISLANDS	06/02/22	25.00	5.00	46.33	10.00
NHPP072A-047		SH-72 RESURFACING: I-70 TO IN	06/09/22	43,530.00	1.00	0.65	0.65
MTCE R100-380		REGION 1 FY 23/24 PAVEMENT MA	06/30/22	5,111,908.00	0.36	0.36	0.36
		WEIGHTED AVERAGE FOR THE SECOND QUARTER		5,353,799.00	0.39	0.41	0.38
MTCER300-273		I-70 MM 75-116, OTHER REGION	07/07/22	1,093,411.00	0.35	0.59	0.43
MTCER300-272		REGION 3 ROUNDABOUT STRIPING	07/07/22	11,300.00	4.00	4.17	3.75
NHPP0702-414		VAIL PASS AUX PHASE 1 CAP 3	07/08/22	3,000.00	2.14	2.14	2.14
FBR0702-423		VAIL PASS AUX BE F-12-AT PHAS					
FSA052A-057		SH52 BOX CULVERT EXTENSION (M	08/04/22	510.00	6.50	6.86	13.00
NHPP0063-054		US 6 FROM I70-B TO 33 RD. (MP	08/18/22	16,527.00	4.00	1.34	1.07
MTCER400-396		REGION 4	08/25/22	810,078.00	0.49	0.33	0.35
C1211-099		SH 121 NORTH SGA SIGNALS	08/25/22	7,074.00	3.00	4.00	3.00
2670403-065		US40 FLOYD HILL ROUNDABOUTS	09/15/22	2,500.00	2.75	3.09	3.00
2670703-497		I-70 GENESEE WILDLIFE XING	09/15/22	22,488.00	2.75	1.77	1.70
SHE2873-193		US 287 & CO 52 INTERSECTION I	09/15/22	10,000.00	3.50	2.13	2.00
		WEIGHTED AVERAGE FOR THE THIRD QUARTER		1,976,888.00	0.52	0.57	0.46
NHPP0821-114		SH 82 ASPEN/INDEPENDENCE PASS	10/13/22	92,800.00	1.00	0.68	0.60
NHPP0701-253		I-70 EAST OF DEBEQUE	10/27/22	38,775.00	1.00	0.83	1.20
NHPP0705-088		I-70 AGATE STRUCTURE REHAB	10/27/22	5,460.00	3.00	3.02	4.00
FSAM240-200		SH21B CO SPRINGS SIGNAL REPLA	10/27/22	8,390.00	2.50	3.10	1.40
C170A-002		CRITICAL CULVERT CONST. PKG D	10/27/22	143.00	8.00	17.36	19.44
TRG0253-264		I-25 AND SH 119 PARK-N-RIDE	10/27/22	10,214.00	1.00	3.50	1.25
NHPP0343-048		US 34 (MP 169.3-171.4)	11/01/22	5,199.00	2.20	2.48	1.80
STU0252-457		I-25:ALAMEDA RIVER PH 2.0	11/03/22	15,000.00	0.60	2.28	2.20
SHE0242-087		US 24 SAFETY IMPRVMENTS, E OF	11/03/22	5,000.00	0.43	3.80	2.39
STR064A-010		SH 64 AND SH 13 AT MEEKER	11/10/22	71,148.00	1.00	0.50	0.50
NHPP0853-126		US85C: PLATTEVILLE NORTH MP (11/10/22	24,049.00	1.25	1.11	0.65
C5502-097		US550 MP 117.28-126.06	11/17/22	44,490.00	2.50	1.73	1.60
STAM420-001		US 285 AT HWY 9C IMPROVEMENTS	12/01/22	23,132.00	1.00	2.40	3.09
BR2854-148		INTERSECTION OF US 285 & SH 9					
STM0091-046		ADA RAMP IMPROVEMENTS - FAIRP					
STA0711-021		SH71: REGION LINE NORTH	12/01/22	63,822.00	0.85	0.75	0.80
STR114A-015		SH114 SILLSVILLE SOUTH TO MP3	12/01/22	185,596.00	2.00	0.60	0.70
2670703-487		I-70 BRIDGES OVER WARD ROAD-	12/01/22	5,500.00	2.80	1.70	1.10
NHPP0701-252		I-70 RIFLE TO SILT SLAB REPLA	12/01/22	31,263.00	1.00	2.50	2.25
IM025A-050		I25-MP103.9 - INTERSECTION DR	12/01/22	1,557.00	2.00	4.27	1.30
STR318A-001		SH 318 MP 0 - 12.5 MOFFAT COU	12/01/22	71,887.00	1.00	0.63	0.60
NHPP0021-041		SH2 RESURFACING MLK TO 52ND	12/01/22	8,000.00	1.50	2.19	2.46

PROJECT NUMBER	ITEM NUMBER/ PROJECT LOCATION	ITEM DESCRIPTION/ PROJECT LOCATION	DATE LET	UNIT/ QUANTITY	ENGR. EST.	AVERAGE BID	AWARDED BID
===== 202-00250							
		Rem Pavement Marking		Sq Foot			
STR0641-107		SH 13 MM 104-128.1 IN MOFFAT	12/01/22	178,423.00	1.00	0.60	0.52
NHPP083A-046		SH83 RESURFACING STROH RD TO	12/08/22	30,000.00	1.25	0.88	1.06
NHPP0063-048		US6 / 20 ROAD INTERSECTION IM	12/15/22	10,612.00	2.00	2.20	1.65
FSA0853-122		WCR14.5 AND US-85, FORT LUPTO	12/15/22	750.00	7.50	6.36	5.50
NHPP0931-033		SH93:US6 TO 58TH RESURFACING	12/15/22	52,738.00	1.00	0.87	0.77
NHPP0502-090		SH 50 MP 134.6-136 GUNNISON C	12/22/22	512.00	10.00	7.04	7.05
STR0092-024		SH 9 North of Silverthorne	12/22/22	153,956.00	1.00	0.55	0.50
STA0361-129		US 36: HYGIENE RD AND NELSON	12/22/22	22,999.00	1.30	1.37	0.62
BR012A-048		CO 12 STRUCTURE P-17-F AT MP	12/22/22	700.00	3.00	12.62	12.00
STA385A-016		SH 385 MP 97.76	12/22/22	4,900.00	3.00	2.32	5.56
		WEIGHTED AVERAGE FOR THE FOURTH QUARTER		1,167,015.00	1.28	1.00	0.85
		WEIGHTED AVERAGE FOR THE YEAR		9,589,779.00	0.60	0.66	0.49
===== 202-00251							
		Rem Pvmt Marking (Asph Grooving)		Sq Foot			
MPR200-278		R2 - VARIOUS LOCATIONS	06/09/22	1,146,863.00	0.50	0.44	0.37
		WEIGHTED AVERAGE FOR THE SECOND QUARTER		1,146,863.00	0.50	0.44	0.37
STRC090-011		US 50B AND SH71/CR18 INTERSEC	11/17/22	7,307.00	1.00	3.63	3.25
STR096A-050		SH 96 MP 168.99 TO 193.77	12/22/22	32.00	5.00	49.33	20.00
		WEIGHTED AVERAGE FOR THE FOURTH QUARTER		7,339.00	1.02	1.32	1.20
		WEIGHTED AVERAGE FOR THE YEAR		1,154,202.00	0.50	0.50	0.42
===== 202-00254							
		Rem of Pvmt Mkg (12 In)		Sq Foot			
STA0252-459			02/03/22	5,000.00	1.36	1.57	1.25
		WEIGHTED AVERAGE FOR THE FIRST QUARTER		5,000.00	1.36	1.57	1.25
NHPP083A-046		SH83 RESURFACING STROH RD TO	12/08/22	5,000.00	1.30	1.76	2.81
		WEIGHTED AVERAGE FOR THE FOURTH QUARTER		5,000.00	1.30	1.76	2.81
		WEIGHTED AVERAGE FOR THE YEAR		10,000.00	1.33	1.64	2.03

COLORADO DEPARTMENT OF TRANSPORTATION
ITEM UNIT COSTS BY PROJECTS -- 2022 COST DATA

11:31 Wednesday, March 8, 2023 35

PROJECT NUMBER	ITEM NUMBER/ PROJECT LOCATION	ITEM DESCRIPTION/ PROJECT LOCATION	DATE LET	UNIT/ QUANTITY	ENGR. EST.	AVERAGE BID	AWARDED BID
===== 202-00300 Rem Bldg(s) LUMP SUM =====							
FSA052A-046		SH52 WCR 37 INTERSECTION IMPR	06/09/22	1.00	3000.00	24601.68	6500.00
		WEIGHTED AVERAGE FOR THE SECOND QUARTER		1.00	3000.00	24601.68	6500.00
		WEIGHTED AVERAGE FOR THE YEAR		1.00	3000.00	24601.68	6500.00
===== 202-00400 Rem Bridge Each =====							
NH0504-910		US50B L-24-B MIN REP AT MP 40	01/13/22	1.00	50000.00	33552.98	18750.00
NHPP 0761-238		I-76 DAHLIA TO YORK	03/10/22	2.00	120000.00	126884.70	100000.00
C0761-239							
		WEIGHTED AVERAGE FOR THE FIRST QUARTER		3.00	96666.67	95774.13	72916.67
STM1151-038		SH115 MP 27 TO MP 38	04/21/22	1.00	100000.00	114978.97	73870.94
2670703-479		I-70 BRIDGE OVER HARLAN	05/05/22	1.00	100000.00	272648.49	185000.00
		WEIGHTED AVERAGE FOR THE SECOND QUARTER		2.00	100000.00	200980.52	129435.47
BR0343-046		US 34 TIMBER BRIDGE REPL. PKG	08/31/22	3.00	59697.04	55737.00	55737.00
FBR0343-047		US 6/US 34 TIMBER BRIDGE REPL					
		WEIGHTED AVERAGE FOR THE THIRD QUARTER		3.00	59697.04	55737.00	55737.00
STU0252-457		I-25:ALAMEDA RIVER PH 2.0	11/03/22	1.00	400000.00	344739.58	355000.00
STAM420-001		US 285 AT HWY 9C IMPROVEMENTS	12/01/22	1.00	55000.00	307107.94	73875.38
BR2854-148		INTERSECTION OF US 285 & SH 9					
STM0091-046		ADA RAMP IMPROVEMENTS - FAIRP					
2670703-487		I-70 BRIDGES OVER WARD ROAD-	12/01/22	2.00	230000.00	177916.56	294000.00
BR012A-048		CO 12 STRUCTURE P-17-F AT MP	12/22/22	1.00	100000.00	150000.00	100000.00
STA385A-016		SH 385 MP 97.76	12/22/22	1.00	25000.00	90000.00	25000.00
		WEIGHTED AVERAGE FOR THE FOURTH QUARTER		6.00	173333.33	210182.72	220267.91
		WEIGHTED AVERAGE FOR THE YEAR		14.00	122077.94	159253.99	145780.49

PROJECT NUMBER	ITEM NUMBER/ PROJECT LOCATION	ITEM DESCRIPTION/ PROJECT LOCATION	DATE LET	UNIT/ QUANTITY	ENGR. EST.	AVERAGE BID	AWARDED BID
===== 202-00420		Rem Ped Rail		Lin Foot	=====		
NHPP0702-383		I-70 EB AUX FRISCO TO SILVERT	01/13/22	629.00	10.00	22.65	20.00
	WEIGHTED AVERAGE FOR THE FIRST QUARTER			629.00	10.00	22.65	20.00
	WEIGHTED AVERAGE FOR THE YEAR			629.00	10.00	22.65	20.00
===== 202-00425		Rem Bridge Railing		Lin Foot	=====		
NHPP0702-383		I-70 EB AUX FRISCO TO SILVERT	01/13/22	1,751.00	29.00	27.17	16.00
NHPP 0761-238		I-76 DAHLIA TO YORK	03/10/22	29.00	40.00	147.12	125.00
C0761-239							
	WEIGHTED AVERAGE FOR THE FIRST QUARTER			1,780.00	29.18	30.27	17.78
NHPP0701-253		I-70 EAST OF DEBEQUE	10/27/22	617.00	24.98	41.80	46.00
STA207A-004		Resurfacing SH207A MANZANOLA	10/27/22	920.00	24.00	27.07	27.20
STR064A-010		SH 64 AND SH 13 AT MEEKER	11/10/22	18.00	250.00	23.60	25.00
C5502-097		US550 MP 117.28-126.06	11/17/22	48.00	150.00	24.00	22.10
STA0711-021		SH71: REGION LINE NORTH	12/01/22	248.00	36.00	33.50	30.00
STR114A-015		SH114 SILLSVILLE SOUTH TO MP3	12/01/22	147.00	25.00	125.00	130.00
2670703-487		I-70 BRIDGES OVER WARD ROAD-	12/01/22	378.00	30.00	136.74	110.00
	WEIGHTED AVERAGE FOR THE FOURTH QUARTER			2,376.00	30.78	63.46	51.79
	WEIGHTED AVERAGE FOR THE YEAR			4,156.00	30.09	44.92	37.22
===== 202-00450		Rem Port Present Str (1)		Sq Yard	=====		
BRC040-057			03/17/22	356.00	170.00	253.75	270.00
	WEIGHTED AVERAGE FOR THE FIRST QUARTER			356.00	170.00	253.75	270.00
NHPP0252-448		I-25 TREX NARROWS BRIDGE PREV	06/23/22	141.00	140.00	267.50	155.00
	WEIGHTED AVERAGE FOR THE SECOND QUARTER			141.00	140.00	267.50	155.00
NHPP0701-252		I-70 RIFLE TO SILT SLAB REPLA	12/01/22	13.00	200.00	447.50	595.00
	WEIGHTED AVERAGE FOR THE FOURTH QUARTER			13.00	200.00	286.25	174.39
	WEIGHTED AVERAGE FOR THE YEAR			510.00	162.47	268.15	213.91

COLORADO DEPARTMENT OF TRANSPORTATION
ITEM UNIT COSTS BY PROJECTS -- 2022 COST DATA

11:31 Wednesday, March 8, 2023 37

PROJECT NUMBER	ITEM NUMBER/ PROJECT LOCATION	ITEM DESCRIPTION/ PROJECT LOCATION	DATE LET	UNIT/ QUANTITY	ENGR. EST.	AVERAGE BID	AWARDED BID
===== 202-00453 Rem Port Present Str (2) Sq Yard =====							
NHPP0702-383		I-70 EB AUX FRISCO TO SILVERT	01/13/22	354.00	350.00	624.52	582.00
C0762-055			02/17/22	56.00	400.00	616.30	630.00
BRC040-057			03/17/22	179.00	400.00	462.25	565.00
STR R500-171		Various locations on SH 141 a	03/17/22	76.00	380.00	436.21	463.00
		WEIGHTED AVERAGE FOR THE FIRST QUARTER		665.00	371.10	569.73	567.87
NH0504-911			04/07/22	351.00	337.00	438.00	476.00
STM1151-038		SH115 MP 27 TO MP 38	04/21/22	48.00	746.00	411.41	275.00
		WEIGHTED AVERAGE FOR THE SECOND QUARTER		399.00	386.20	431.23	451.82
NHPP0701-231		I-70 SALT WASH BRIDGES SCOUR	09/29/22	3.00	800.00	1088.32	505.00
		WEIGHTED AVERAGE FOR THE THIRD QUARTER		3.00	800.00	1088.32	505.00
NHPP0705-088		I-70 AGATE STRUCTURE REHAB	10/27/22	439.00	375.00	274.22	231.00
STA0711-021		SH71: REGION LINE NORTH	12/01/22	43.00	330.00	508.33	550.00
NHPP0701-252		I-70 RIFLE TO SILT SLAB REPLA	12/01/22	216.00	600.00	445.00	550.00
STR109A-019		M-22-AY BRIDGE REHAB ON SH109	12/01/22	1,916.00	325.00	325.06	328.11
		WEIGHTED AVERAGE FOR THE FOURTH QUARTER		2,614.00	356.20	338.23	327.09
		WEIGHTED AVERAGE FOR THE YEAR		3,681.00	362.51	407.41	380.18
===== 202-00458 Rem Port Pres Str (Hydrodem) (Fast-Track) Sq Yard =====							
NHPP0705-088		I-70 AGATE STRUCTURE REHAB	10/27/22	3,417.00	150.00	187.82	192.00
		WEIGHTED AVERAGE FOR THE FOURTH QUARTER		3,417.00	150.00	187.82	192.00
		WEIGHTED AVERAGE FOR THE YEAR		3,417.00	150.00	187.82	192.00
===== 202-00460 Rem Port Present Str (3) Sq Yard =====							
NHPP0702-383		I-70 EB AUX FRISCO TO SILVERT	01/13/22	71.00	700.00	1444.84	1820.00

COLORADO DEPARTMENT OF TRANSPORTATION
 ITEM UNIT COSTS BY PROJECTS -- 2022 COST DATA

11:31 Wednesday, March 8, 2023 38

PROJECT NUMBER	ITEM NUMBER/ PROJECT LOCATION	ITEM DESCRIPTION/ PROJECT LOCATION	DATE LET	UNIT/ QUANTITY	ENGR. EST.	AVERAGE BID	AWARDED BID
===== 202-00460		Rem Port Present Str (3)		Sq Yard			
BRC040-057			03/17/22	10.00	900.00	1161.75	1000.00
STR R500-171		Various locations on SH 141 a	03/17/22	20.00	685.00	1440.67	1775.00
		WEIGHTED AVERAGE FOR THE FIRST QUARTER		101.00	716.83	1419.40	1729.90
NH0504-911			04/07/22	40.00	645.00	1740.00	2380.00
STM1151-038		SH115 MP 27 TO MP 38	04/21/22	16.00	900.00	1155.57	800.00
		WEIGHTED AVERAGE FOR THE SECOND QUARTER		56.00	717.86	1447.78	1928.57
NHPP0701-231		I-70 SALT WASH BRIDGES SCOUR	09/29/22	3.00	1800.00	2035.12	565.00
		WEIGHTED AVERAGE FOR THE THIRD QUARTER		3.00	1800.00	2035.12	565.00
NHPP0705-088		I-70 AGATE STRUCTURE REHAB	10/27/22	101.00	1100.00	440.07	385.00
STA0711-021		SH71: REGION LINE NORTH	12/01/22	12.00	800.00	1221.67	1200.00
NHPP0701-252		I-70 RIFLE TO SILT SLAB REPLA	12/01/22	12.00	1800.00	990.00	1160.00
STR109A-019		M-22-AY BRIDGE REHAB ON SH109	12/01/22	238.00	500.00	554.05	330.10
		WEIGHTED AVERAGE FOR THE FOURTH QUARTER		363.00	719.83	671.90	459.88
		WEIGHTED AVERAGE FOR THE YEAR		523.00	725.24	894.22	777.40
===== 202-00495		Rem Port Present Str		LUMP SUM			
STAR100-358		3 STRUCTURES IN REGION 1 METR	05/26/22	1.00	3000.00	4801.89	3337.00
		WEIGHTED AVERAGE FOR THE SECOND QUARTER		1.00	3000.00	4801.89	3337.00
NHPP0702-414		VAIL PASS AUX PHASE 1 CAP 3	07/08/22	1.00	18377.13	18377.13	18377.13
FBR0702-423		VAIL PASS AUX BE F-12-AT PHAS					
FSA052A-057		SH52 BOX CULVERT EXTENSION (M	08/04/22	1.00	10000.00	20871.21	3827.20
STAR100-374		5 STRUCTURES IN REGION 1	09/01/22	1.00	5000.00	4700.64	4700.64
		WEIGHTED AVERAGE FOR THE THIRD QUARTER		3.00	11125.71	17138.28	8968.32

COLORADO DEPARTMENT OF TRANSPORTATION
 ITEM UNIT COSTS BY PROJECTS -- 2022 COST DATA

11:31 Wednesday, March 8, 2023 39

PROJECT NUMBER	ITEM NUMBER/ PROJECT LOCATION	ITEM DESCRIPTION/ PROJECT LOCATION	DATE LET	UNIT/ QUANTITY	ENGR. EST.	AVERAGE BID	AWARDED BID
===== 202-00495		Rem Port Present Str		LUMP SUM	=====		
STU0252-457		I-25:ALAMEDA RIVER PH 2.0	11/03/22	1.00	100000.00	13788.68	9000.00
C5502-097		US550 MP 117.28-126.06	11/17/22	1.00	50000.00	53090.71	21610.00
		WEIGHTED AVERAGE FOR THE FOURTH QUARTER		2.00	75000.00	33439.70	15305.00
		WEIGHTED AVERAGE FOR THE YEAR		6.00	31062.86	21481.09	10142.00
===== 202-00500		Rem Port Present Str		Each	=====		
BRC040-057			03/17/22	34.00	400.00	333.50	200.00
		WEIGHTED AVERAGE FOR THE FIRST QUARTER		34.00	400.00	333.50	200.00
IM025A-050		I25-MP103.9 - INTERSECTION DR	12/01/22	2.00	5000.00	9833.33	10000.00
		WEIGHTED AVERAGE FOR THE FOURTH QUARTER		2.00	5000.00	9833.33	10000.00
		WEIGHTED AVERAGE FOR THE YEAR		36.00	655.56	734.90	744.44
===== 202-00502		Rem Port Present Str		Cubic Yard	=====		
NHPP0702-383		I-70 EB AUX FRISCO TO SILVERT	01/13/22	1.00	1000.00	3722.92	2762.00
NHPP1601-083			02/03/22	8.00	5000.00	3255.09	1600.00
STR R500-171		Various locations on SH 141 a	03/17/22	12.00	1070.00	2635.94	1580.00
NHM765-007			03/31/22	1.00	3000.00	5188.32	11483.22
		WEIGHTED AVERAGE FOR THE FIRST QUARTER		22.00	2583.64	3019.25	2091.15
ER0253-297		WCR 34 BRIDGE OVER I-25(MM 24	09/14/22	4.00	8000.00	18660.94	3600.00
NHPP0701-231		I-70 SALT WASH BRIDGES SCOUR	09/29/22	3.00	3000.00	2707.66	3100.00
		WEIGHTED AVERAGE FOR THE THIRD QUARTER		7.00	5857.14	14310.05	3385.71
NHPP0701-253		I-70 EAST OF DEBEQUE	10/27/22	1.00	5000.00	5145.00	7500.00

COLORADO DEPARTMENT OF TRANSPORTATION
ITEM UNIT COSTS BY PROJECTS -- 2022 COST DATA

11:31 Wednesday, March 8, 2023 40

PROJECT NUMBER	ITEM NUMBER/ PROJECT LOCATION	ITEM DESCRIPTION/ PROJECT LOCATION	DATE LET	UNIT/ QUANTITY	ENGR. EST.	AVERAGE BID	AWARDED BID
=====	202-00502	Rem Port Present Str		Cubic Yard	=====	=====	=====
STR0092-024		SH 9 North of Silverthorne	12/22/22	16.00	2000.00	5805.00	4310.00
		WEIGHTED AVERAGE FOR THE FOURTH QUARTER		17.00	2176.47	5766.18	4497.65
		WEIGHTED AVERAGE FOR THE YEAR		46.00	2931.30	5965.74	3177.50
=====	202-00503	Rem Port Present Str		Sq Yard	=====	=====	=====
STA0252-459			02/03/22	42.00	320.00	874.67	387.00
NHPP 0761-238		I-76 DAHLIA TO YORK	03/10/22	55.00	800.00	365.99	230.00
C0761-239							
C0703-499		EJMT GROUT BED REPAIR AND PAN	03/31/22	65.00	2000.00	4490.00	3280.00
		WEIGHTED AVERAGE FOR THE FIRST QUARTER		162.00	1157.04	1228.37	1494.47
STU0252-457		I-25:ALAMEDA RIVER PH 2.0	11/03/22	295.00	300.00	59.85	55.00
STR064A-010		SH 64 AND SH 13 AT MEEKER	11/10/22	21.00	400.00	2875.00	3000.00
STA0711-021		SH71: REGION LINE NORTH	12/01/22	35.00	270.00	267.67	300.00
IM025A-050		I25-MP103.9 - INTERSECTION DR	12/01/22	11.00	150.00	923.33	520.00
STR109A-019		M-22-AY BRIDGE REHAB ON SH109	12/01/22	584.00	1100.00	1096.74	868.47
		WEIGHTED AVERAGE FOR THE FOURTH QUARTER		946.00	793.23	677.69	637.03
		WEIGHTED AVERAGE FOR THE YEAR		1,108.00	846.43	808.54	762.40
=====	202-00504	Rem Exp Device		Lin Foot	=====	=====	=====
NHPP0702-383		I-70 EB AUX FRISCO TO SILVERT	01/13/22	256.00	200.00	293.40	230.00
NHPP1601-083			02/03/22	68.00	500.00	518.14	400.00
C0762-055			02/17/22	100.00	250.00	372.90	475.00
		WEIGHTED AVERAGE FOR THE FIRST QUARTER		424.00	259.91	327.74	315.05
STM1151-038		SH115 MP 27 TO MP 38	04/21/22	154.00	170.00	197.26	125.00
		WEIGHTED AVERAGE FOR THE SECOND QUARTER		154.00	170.00	197.26	125.00
NHPP0701-231		I-70 SALT WASH BRIDGES SCOUR	09/29/22	40.00	400.00	359.30	275.00
		WEIGHTED AVERAGE FOR THE THIRD QUARTER		40.00	400.00	359.30	275.00

PROJECT NUMBER	ITEM NUMBER/ PROJECT LOCATION	ITEM DESCRIPTION/ PROJECT LOCATION	DATE LET	UNIT/ QUANTITY	ENGR. EST.	AVERAGE BID	AWARDED BID
===== 202-00504		Rem Exp Device		Lin Foot	=====		
NHPP0705-088		I-70 AGATE STRUCTURE REHAB	10/27/22	203.00	315.00	133.52	124.00
NHPP0701-252		I-70 RIFLE TO SILT SLAB REPLA	12/01/22	552.00	250.00	99.00	88.00
STR109A-019		M-22-AY BRIDGE REHAB ON SH109	12/01/22	60.00	225.00	439.58	654.15
STR096A-050		SH 96 MP 168.99 TO 193.77	12/22/22	252.00	220.00	55.67	60.00
		WEIGHTED AVERAGE FOR THE FOURTH QUARTER		1,067.00	253.88	118.12	122.51
		WEIGHTED AVERAGE FOR THE YEAR		1,685.00	251.20	196.17	170.56
===== 202-00505		Rem Port of Present Structure		Sq Foot	=====		
NHPP0702-383		I-70 EB AUX FRISCO TO SILVERT	01/13/22	2,413.00	95.00	85.54	57.00
BRC040-057			03/17/22	21.00	122.00	399.00	175.00
		WEIGHTED AVERAGE FOR THE FIRST QUARTER		2,434.00	95.23	87.71	58.02
NH0504-911			04/07/22	205.00	122.00	398.75	297.50
STM1151-038		SH115 MP 27 TO MP 38	04/21/22	410.00	180.00	123.87	75.00
		WEIGHTED AVERAGE FOR THE SECOND QUARTER		615.00	160.67	169.68	149.17
NHPP0705-088		I-70 AGATE STRUCTURE REHAB	10/27/22	255.00	185.00	124.07	97.00
STA0711-021		SH71: REGION LINE NORTH	12/01/22	60.00	150.00	240.33	260.00
STR096A-050		SH 96 MP 168.99 TO 193.77	12/22/22	169.00	180.00	206.67	220.00
		WEIGHTED AVERAGE FOR THE FOURTH QUARTER		484.00	178.92	162.67	161.47
		WEIGHTED AVERAGE FOR THE YEAR		3,533.00	118.09	108.06	88.37
===== 202-00520		Rem of Exp Joint Matl		Lin Foot	=====		
STR0711-022		SH 71 OVER THE ARKANSAS	08/04/22	80.00	330.00	58.67	67.00
		WEIGHTED AVERAGE FOR THE THIRD QUARTER		80.00	330.00	58.67	67.00

COLORADO DEPARTMENT OF TRANSPORTATION
 ITEM UNIT COSTS BY PROJECTS -- 2022 COST DATA

11:31 Wednesday, March 8, 2023 42

PROJECT NUMBER	ITEM NUMBER/ PROJECT LOCATION	ITEM DESCRIPTION/ PROJECT LOCATION	DATE LET	UNIT/ QUANTITY	ENGR. EST.	AVERAGE BID	AWARDED BID
===== 202-00520		Rem of Exp Joint Matl		Lin Foot	=====		
STR064A-010		SH 64 AND SH 13 AT MEEKER	11/10/22	50.00	350.00	738.00	800.00
	WEIGHTED AVERAGE FOR THE FOURTH QUARTER			50.00	350.00	738.00	800.00
	WEIGHTED AVERAGE FOR THE YEAR			130.00	337.69	258.47	348.92
===== 202-00700		Rem Light Standard		Each	=====		
NHM765-007			03/31/22	27.00	500.00	1065.10	957.60
	WEIGHTED AVERAGE FOR THE FIRST QUARTER			27.00	500.00	1065.10	957.60
2670403-065		US40_FLOYD HILL ROUNDABOUTS	09/15/22	4.00	800.00	2425.52	1840.00
	WEIGHTED AVERAGE FOR THE THIRD QUARTER			4.00	800.00	2425.52	1840.00
TRG0253-264		I-25 AND SH 119 PARK-N-RIDE	10/27/22	6.00	250.00	438.75	450.00
STU0252-457		I-25:ALAMEDA RIVER PH 2.0	11/03/22	1.00	1000.00	2100.02	2100.00
STRC090-011		US 50B AND SH71/CR18 INTERSEC	11/17/22	2.00	764.00	1512.50	1525.00
STAM420-001		US 285 AT HWY 9C IMPROVEMENTS	12/01/22	4.00	750.00	968.40	1466.09
BR2854-148		INTERSECTION OF US 285 & SH 9					
STM0091-046		ADA RAMP IMPROVEMENTS - FAIRP					
IM025A-050		I25-MP103.9 - INTERSECTION DR	12/01/22	3.00	1100.00	866.67	1300.00
	WEIGHTED AVERAGE FOR THE FOURTH QUARTER			16.00	645.50	708.81	1100.90
	WEIGHTED AVERAGE FOR THE YEAR			47.00	575.06	994.71	1081.48
===== 202-00705		Rem Light Standard Foundation		Each	=====		
NHPP0702-383		I-70 EB AUX FRISCO TO SILVERT	01/13/22	13.00	900.00	2218.91	2900.00
NHPP0063-063			02/24/22	59.00	960.00	677.00	710.00
NHM765-007			03/31/22	27.00	250.00	1553.28	1396.50
	WEIGHTED AVERAGE FOR THE FIRST QUARTER			99.00	758.48	1325.49	1184.80

PROJECT NUMBER	ITEM NUMBER/ PROJECT LOCATION	ITEM DESCRIPTION/ PROJECT LOCATION	DATE LET	UNIT/ QUANTITY	ENGR. EST.	AVERAGE BID	AWARDED BID
===== 202-00705		Rem Light Standard Foundation		Each	=====		
2670703-479		I-70 BRIDGE OVER HARLAN	05/05/22	13.00	750.00	521.21	614.00
	WEIGHTED AVERAGE FOR THE SECOND QUARTER			13.00	750.00	521.21	614.00
2670403-065		US40_FLOYD HILL ROUNDABOUTS	09/15/22	4.00	1000.00	4480.89	3800.00
	WEIGHTED AVERAGE FOR THE THIRD QUARTER			4.00	1000.00	4480.89	3800.00
TRG0253-264		I-25 AND SH 119 PARK-N-RIDE	10/27/22	6.00	350.00	698.56	700.00
STAM420-001		US 285 AT HWY 9C IMPROVEMENTS	12/01/22	4.00	850.00	1588.06	2541.23
BR2854-148		INTERSECTION OF US 285 & SH 9					
STM0091-046		ADA RAMP IMPROVEMENTS - FAIRP					
IM025A-050		I25-MP103.9 - INTERSECTION DR	12/01/22	4.00	1137.50	1466.67	1100.00
	WEIGHTED AVERAGE FOR THE FOURTH QUARTER			14.00	717.86	1015.64	1360.31
	WEIGHTED AVERAGE FOR THE YEAR			130.00	760.69	1209.29	1229.11
===== 202-00710		Rem Power Pole		Each	=====		
STAM420-001		US 285 AT HWY 9C IMPROVEMENTS	12/01/22	1.00	4000.00	1660.58	1787.31
BR2854-148		INTERSECTION OF US 285 & SH 9					
STM0091-046		ADA RAMP IMPROVEMENTS - FAIRP					
	WEIGHTED AVERAGE FOR THE FOURTH QUARTER			1.00	4000.00	1660.58	1787.31
	WEIGHTED AVERAGE FOR THE YEAR			1.00	4000.00	1660.58	1787.31
===== 202-00715		Rem CCTV Pole		Each	=====		
2670703-479		I-70 BRIDGE OVER HARLAN	05/05/22	1.00	750.00	3210.11	3783.49
	WEIGHTED AVERAGE FOR THE SECOND QUARTER			1.00	750.00	3210.11	3783.49
TRG0253-264		I-25 AND SH 119 PARK-N-RIDE	10/27/22	2.00	550.00	736.15	770.00
	WEIGHTED AVERAGE FOR THE FOURTH QUARTER			2.00	550.00	736.15	770.00
	WEIGHTED AVERAGE FOR THE YEAR			3.00	616.67	1410.87	1774.50

PROJECT NUMBER	ITEM NUMBER/ PROJECT LOCATION	ITEM DESCRIPTION/ PROJECT LOCATION	DATE LET	UNIT/ QUANTITY	ENGR. EST.	AVERAGE BID	AWARDED BID
===== 202-00720		Rem CCTV Camera		Each =====			
ITS0703-477		ITS EQUIPMENT UPGRADE AT EJMT	01/06/22	106.00	450.00	965.00	965.00
	WEIGHTED AVERAGE FOR THE FIRST QUARTER			106.00	450.00	965.00	965.00
TRG0253-264		I-25 AND SH 119 PARK-N-RIDE	10/27/22	3.00	275.00	55.46	55.00
	WEIGHTED AVERAGE FOR THE FOURTH QUARTER			3.00	275.00	55.46	55.00
	WEIGHTED AVERAGE FOR THE YEAR			109.00	445.18	797.08	939.95
===== 202-00750		Rem Luminaire		Each =====			
NHM765-007			03/31/22	54.00	200.00	221.90	199.50
	WEIGHTED AVERAGE FOR THE FIRST QUARTER			54.00	200.00	221.90	199.50
NHPP0063-054		US 6 FROM I70-B TO 33 RD. (MP	08/18/22	7.00	100.00	421.39	365.00
	WEIGHTED AVERAGE FOR THE THIRD QUARTER			7.00	100.00	421.39	365.00
STU0252-457		I-25:ALAMEDA RIVER PH 2.0	11/03/22	1.00	500.00	276.22	276.00
STAM420-001		US 285 AT HWY 9C IMPROVEMENTS	12/01/22	4.00	130.00	258.74	390.96
BR2854-148		INTERSECTION OF US 285 & SH 9					
STM0091-046		ADA RAMP IMPROVEMENTS - FAIRP					
2670703-487		I-70 BRIDGES OVER WARD ROAD-	12/01/22	2.00	400.00	156.84	150.00
	WEIGHTED AVERAGE FOR THE FOURTH QUARTER			7.00	260.00	225.41	305.69
	WEIGHTED AVERAGE FOR THE YEAR			68.00	195.88	236.02	227.47
===== 202-00800		Rem Overpass Mtd Sign Brkt		Each =====			
2670703-479		I-70 BRIDGE OVER HARLAN	05/05/22	11.00	5000.00	105.45	120.44
	WEIGHTED AVERAGE FOR THE SECOND QUARTER			11.00	5000.00	105.45	120.44
	WEIGHTED AVERAGE FOR THE YEAR			11.00	5000.00	105.45	120.44

PROJECT NUMBER	ITEM NUMBER/ PROJECT LOCATION	ITEM DESCRIPTION/ PROJECT LOCATION	DATE LET	UNIT/ QUANTITY	ENGR. EST.	AVERAGE BID	AWARDED BID
===== 202-00805 Rem Overhead Sign Str Each =====							
NHPP 0761-238 C0761-239 M R100-351	I-76 DAHLIA TO YORK		03/10/22	2.00	7000.00	17326.05	7500.00
	FY22 R1 SIGN STRUCTURE REPLAC		03/17/22	4.00	15000.00	16048.50	14347.00
	WEIGHTED AVERAGE FOR THE FIRST QUARTER			6.00	12333.33	16900.20	12064.67

2670703-479	I-70 BRIDGE OVER HARLAN		05/05/22	2.00	5000.00	5769.53	5978.96
	WEIGHTED AVERAGE FOR THE SECOND QUARTER			2.00	5000.00	5769.53	5978.96

2670703-487	I-70 BRIDGES OVER WARD ROAD-		12/01/22	2.00	8000.00	9139.54	7680.00
	WEIGHTED AVERAGE FOR THE FOURTH QUARTER			2.00	8000.00	9139.54	7680.00
	WEIGHTED AVERAGE FOR THE YEAR			10.00	10000.00	12309.45	9970.59
===== 202-00810 Rem Ground Sign Each =====							
ITS0703-477	ITS EQUIPMENT UPGRADE AT EJMT		01/06/22	4.00	300.00	1285.00	1285.00
NHPP2873-189	US 287 (FEDERAL BLVD) - COLFA		01/06/22	20.00	100.00	171.58	210.84
NHPP0702-383	I-70 EB AUX FRISCO TO SILVERT		01/13/22	74.00	150.00	132.93	110.00
MTCER300-262			02/03/22	483.00	125.00	206.67	120.00
C0762-055			02/17/22	104.00	150.00	124.13	155.00
STR0141-031			02/17/22	7.00	185.00	191.67	180.00
NHPP0063-063			02/24/22	27.00	120.00	165.00	172.00
STA 067A-048	Hwy 67A MP 0.00 TO MP 11.05 I		03/03/22	132.00	100.00	75.33	80.00
NHPP 0761-238 C0761-239	I-76 DAHLIA TO YORK		03/10/22	32.00	120.00	167.25	100.00
NHPP0703-472			03/10/22	14.00	120.00	187.06	150.00
ER007A-035			03/15/22	133.00	173.40	185.50	185.50
M R100-351	FY22 R1 SIGN STRUCTURE REPLAC		03/17/22	3.00	2000.00	3046.50	2088.00
NHM765-007			03/31/22	47.00	95.00	125.54	114.00
	WEIGHTED AVERAGE FOR THE FIRST QUARTER			1,080.00	136.16	170.27	138.55

NH0504-911			04/07/22	14.00	75.00	134.75	119.50

PROJECT NUMBER	ITEM NUMBER/ PROJECT LOCATION	ITEM DESCRIPTION/ PROJECT LOCATION	DATE LET	UNIT/ QUANTITY	ENGR. EST.	AVERAGE BID	AWARDED BID
=====	202-00810	Rem Ground Sign		Each =====			
STM1151-038		SH115 MP 27 TO MP 38	04/21/22	158.00	105.00	80.91	75.00
2670703-479		I-70 BRIDGE OVER HARLAN	05/05/22	18.00	105.00	122.98	134.84
STA0712-019		SH 71: Frieght Improvements	05/12/22	10.00	120.00	207.01	207.01
NHC540-017		R2 CHAINUP STA @ KENOSHA/HOOS	05/12/22	1.00	90.00	398.33	195.00
NHPP 3851-018		US 385 NORTH OF CHEYENNE WELL	05/26/22	21.00	120.00	162.50	150.00
FSA3921-019		SH 392 AND WCR 55 ISLANDS	06/02/22	1.00	100.00	198.33	200.00
NHPP072A-047		SH-72 RESURFACING: I-70 TO IN	06/09/22	96.00	120.00	151.05	151.05
FSA052A-046		SH52 WCR 37 INTERSECTION IMPR	06/09/22	20.00	125.00	108.40	20.00
MTCE0253-291		I-25 SIGN REPLACEMENT PHASE 2	06/16/22	128.00	200.00	346.53	381.06
		WEIGHTED AVERAGE FOR THE SECOND QUARTER		467.00	135.03	143.25	182.53
NHPP0702-414		VAIL PASS AUX PHASE 1 CAP 3	07/08/22	12.00	163.71	163.71	163.71
FBR0702-423		VAIL PASS AUX BE F-12-AT PHAS					
FSA052A-057		SH52 BOX CULVERT EXTENSION (M	08/04/22	2.00	350.00	312.85	93.60
NHPP0063-054		US 6 FROM I70-B TO 33 RD. (MP	08/18/22	31.00	110.00	173.68	225.00
C1211-099		SH 121 NORTH SGA SIGNALS	08/25/22	17.00	200.00	210.00	220.00
2670403-065		US40 FLOYD HILL ROUNDABOUTS	09/15/22	15.00	200.00	220.25	170.00
SHE2873-193		US 287 & CO 52 INTERSECTION I	09/15/22	17.00	100.00	160.29	160.50
		WEIGHTED AVERAGE FOR THE THIRD QUARTER		94.00	150.79	183.95	193.03
C0831-126		SH83 EL PASO COUNTY TO BAYOU	10/13/22	174.00	120.00	150.00	150.00
TRG0253-264		I-25 AND SH 119 PARK-N-RIDE	10/27/22	20.00	90.00	138.59	145.00
STA3852-015		US 385 HOLYOKE NORTH	10/27/22	17.00	165.00	165.00	165.00
STU0252-457		I-25:ALAMEDA RIVER PH 2.0	11/03/22	19.00	150.00	174.62	175.00
NHPP0853-126		US85C: PLATTEVILLE NORTH MP (11/10/22	7.00	200.00	164.60	170.00
C5502-097		US550 MP 117.28-126.06	11/17/22	38.00	200.00	152.44	151.00
MPR200-280		PUEBLO AREA	11/17/22	311.00	97.00	90.00	120.00
STRC090-011		US 50B AND SH71/CR18 INTERSEC	11/17/22	9.00	180.00	156.50	175.00
STAM420-001		US 285 AT HWY 9C IMPROVEMENTS	12/01/22	54.00	115.00	181.05	113.86
BR2854-148		INTERSECTION OF US 285 & SH 9					
STM0091-046		ADA RAMP IMPROVEMENTS - FAIRP					
STA0711-021		SH71: REGION LINE NORTH	12/01/22	16.00	140.00	156.67	150.00
2670703-487		I-70 BRIDGES OVER WARD ROAD-	12/01/22	15.00	150.00	618.94	850.00
IM025A-050		I25-MP103.9 - INTERSECTION DR	12/01/22	12.00	100.00	93.33	110.00
NHPP0021-041		SH2 RESURFACING MLK TO 52ND	12/01/22	16.00	150.00	200.60	254.21
NHPP083A-046		SH83 RESURFACING STROH RD TO	12/08/22	37.00	150.00	88.34	103.68
NHPP0063-048		US6 / 20 ROAD INTERSECTION IM	12/15/22	21.00	170.00	220.84	165.00
NHPP0931-033		SH93:US6 TO 58TH RESURFACING	12/15/22	70.00	200.00	186.07	230.00
NHPP0502-090		SH 50 MP 134.6-136 GUNNISON C	12/22/22	14.00	180.00	215.43	234.74
STR0092-024		SH 9 North of Silverthorne	12/22/22	1.00	350.00	189.00	178.00

COLORADO DEPARTMENT OF TRANSPORTATION
ITEM UNIT COSTS BY PROJECTS -- 2022 COST DATA

11:31 Wednesday, March 8, 2023 47

PROJECT NUMBER	ITEM NUMBER/ PROJECT LOCATION	ITEM DESCRIPTION/ PROJECT LOCATION	DATE LET	UNIT/ QUANTITY	ENGR. EST.	AVERAGE BID	AWARDED BID
===== 202-00810							
		Rem Ground Sign		Each			
STA0361-129		US 36: HYGIENE RD AND NELSON	12/22/22	7.00	300.00	147.09	103.46
BR012A-048		CO 12 STRUCTURE P-17-F AT MP	12/22/22	1.00	50.00	121.50	91.00
STA385A-016		SH 385 MP 97.76	12/22/22	3.00	100.00	162.42	166.67
STR096A-050		SH 96 MP 168.99 TO 193.77	12/22/22	156.00	140.00	228.33	150.00
		WEIGHTED AVERAGE FOR THE FOURTH QUARTER		1,018.00	131.34	170.44	156.34
		WEIGHTED AVERAGE FOR THE YEAR		2,659.00	134.63	165.91	155.02
===== 202-00815							
		Rem of Sign (Special)		Each			
ITS 0741-024		VMS SIGN INSTALLATIONS AND VS	06/02/22	14.00	500.00	955.50	400.00
		WEIGHTED AVERAGE FOR THE SECOND QUARTER		14.00	500.00	955.50	400.00
NHPP0702-414		VAIL PASS AUX PHASE 1 CAP 3	07/08/22	1.00	1309.68	1309.68	1309.68
FBR0702-423		VAIL PASS AUX BE F-12-AT PHAS					
		WEIGHTED AVERAGE FOR THE THIRD QUARTER		1.00	1309.68	1309.68	1309.68
STU0252-457		I-25:ALAMEDA RIVER PH 2.0	11/03/22	4.00	300.00	290.14	289.00
		WEIGHTED AVERAGE FOR THE FOURTH QUARTER		4.00	300.00	290.14	289.00
		WEIGHTED AVERAGE FOR THE YEAR		19.00	500.51	769.40	424.51
===== 202-00821							
		Rem Sign Panel		Each			
NHPP2873-189		US 287 (FEDERAL BLVD) - COLFA	01/06/22	10.00	80.00	71.27	37.21
NHPP0702-383		I-70 EB AUX FRISCO TO SILVERT	01/13/22	3.00	70.00	605.44	707.00
MTCER300-262			02/03/22	3,039.00	30.00	131.67	80.00
C0762-055			02/17/22	10.00	125.00	144.78	80.00
NHPP0063-063			02/24/22	44.00	40.00	55.40	58.00
NHPP 0761-238		I-76 DAHLIA TO YORK	03/10/22	4.00	80.00	1313.54	600.00
C0761-239							
NHPP0703-472			03/10/22	2.00	60.00	110.90	110.00
M R100-351		FY22 R1 SIGN STRUCTURE REPLAC	03/17/22	32.00	1000.00	951.00	1114.00
NHM765-007			03/31/22	38.00	45.00	107.38	114.00
		WEIGHTED AVERAGE FOR THE FIRST QUARTER		3,182.00	40.65	140.68	91.63

PROJECT NUMBER	ITEM NUMBER/ PROJECT LOCATION	ITEM DESCRIPTION/ PROJECT LOCATION	DATE LET	UNIT/ QUANTITY	ENGR. EST.	AVERAGE BID	AWARDED BID
=====	202-00821	Rem Sign Panel		Each	=====		
NH0504-911			04/07/22	2.00	75.00	159.75	119.50
2670703-479		I-70 BRIDGE OVER HARLAN	05/05/22	12.00	60.00	71.94	70.70
NHPP 3851-018		US 385 NORTH OF CHEYENNE WELL	05/26/22	116.00	80.00	110.50	160.00
NHPP072A-047		SH-72 RESURFACING: I-70 TO IN	06/09/22	24.00	80.00	151.05	151.05
		WEIGHTED AVERAGE FOR THE SECOND QUARTER		154.00	78.38	105.66	151.12
C1211-099		SH 121 NORTH SGA SIGNALS	08/25/22	1.00	100.00	230.00	110.00
2670403-065		US40 FLOYD HILL ROUNDABOUTS	09/15/22	2.00	700.00	179.38	140.00
SHE2873-193		US 287 & CO 52 INTERSECTION I	09/15/22	9.00	100.00	57.58	31.00
		WEIGHTED AVERAGE FOR THE THIRD QUARTER		12.00	200.00	74.93	55.75
C0831-126		SH83 EL PASO COUNTY TO BAYOU	10/13/22	143.00	105.00	85.00	125.00
STU0252-457		I-25:ALAMEDA RIVER PH 2.0	11/03/22	6.00	120.00	70.37	87.00
MPR200-280		PUEBLO AREA	11/17/22	138.00	87.00	80.00	100.00
STRC090-011		US 50B AND SH71/CR18 INTERSEC	11/17/22	2.00	120.00	120.00	100.00
STR114A-015		SH114 SILLSVILLE SOUTH TO MP3	12/01/22	82.00	100.00	153.75	250.00
2670703-487		I-70 BRIDGES OVER WARD ROAD-	12/01/22	1.00	200.00	607.06	57.00
IM025A-050		I25-MP103.9 - INTERSECTION DR	12/01/22	12.00	90.00	88.33	110.00
NHPP083A-046		SH83 RESURFACING STROH RD TO	12/08/22	12.00	80.00	48.48	64.96
NHPP0063-048		US6 / 20 ROAD INTERSECTION IM	12/15/22	1.00	160.00	147.82	100.00
NHPP0931-033		SH93:US6 TO 58TH RESURFACING	12/15/22	3.00	50.00	154.23	205.00
		WEIGHTED AVERAGE FOR THE FOURTH QUARTER		400.00	96.83	100.66	139.45
		WEIGHTED AVERAGE FOR THE YEAR		3,748.00	48.70	136.12	99.07
=====	202-00823	Rem Dynamic Message Sign		Each	=====		
ITS0703-477		ITS EQUIPMENT UPGRADE AT EJMT	01/06/22	125.00	1000.00	1285.00	1285.00
		WEIGHTED AVERAGE FOR THE FIRST QUARTER		125.00	1000.00	1285.00	1285.00
		WEIGHTED AVERAGE FOR THE YEAR		125.00	1000.00	1285.00	1285.00
=====	202-00825	Rem Flashing Beacon		Each	=====		
NHM765-007			03/31/22	3.00	500.00	1553.28	1396.50
		WEIGHTED AVERAGE FOR THE FIRST QUARTER		3.00	500.00	1553.28	1396.50

COLORADO DEPARTMENT OF TRANSPORTATION
 ITEM UNIT COSTS BY PROJECTS -- 2022 COST DATA

11:31 Wednesday, March 8, 2023 49

PROJECT NUMBER	ITEM NUMBER/ PROJECT LOCATION	ITEM DESCRIPTION/ PROJECT LOCATION	DATE LET	UNIT/ QUANTITY	ENGR. EST.	AVERAGE BID	AWARDED BID
===== 202-00825		Rem Flashing Beacon		Each	=====	=====	=====
2670403-065		US40_FLOYD HILL ROUNDABOUTS	09/15/22	2.00	2000.00	1729.18	630.00
SHE2873-193		US 287 & CO 52 INTERSECTION I	09/15/22	4.00	500.00	645.22	568.17
		WEIGHTED AVERAGE FOR THE THIRD QUARTER		6.00	1000.00	862.01	588.78
STAM420-001		US 285 AT HWY 9C IMPROVEMENTS	12/01/22	2.00	450.00	1681.10	1869.39
BR2854-148		INTERSECTION OF US 285 & SH 9					
STM0091-046		ADA RAMP IMPROVEMENTS - FAIRP					
		WEIGHTED AVERAGE FOR THE FOURTH QUARTER		2.00	450.00	1681.10	1869.39
		WEIGHTED AVERAGE FOR THE YEAR		11.00	763.64	1133.80	1041.91
===== 202-00827		Rem of Pull Box		Each	=====	=====	=====
NHPP0702-383		I-70 EB AUX FRISCO TO SILVERT	01/13/22	6.00	500.00	392.49	415.00
NHPP0063-063			02/24/22	49.00	650.00	728.50	765.00
NHPP 0761-238		I-76 DAHLIA TO YORK	03/10/22	1.00	465.00	332.72	100.00
C0761-239							
CR100-362			03/14/22	25.00	428.00	428.00	428.00
MP0503-098			03/24/22	2.00	320.00	340.00	500.00
		WEIGHTED AVERAGE FOR THE FIRST QUARTER		83.00	562.11	593.27	623.80
CC030-081		ADA RAMP AND CURBS - FT. LUPT	04/14/22	26.00	600.00	495.49	620.00
NHPP072A-047		SH-72 RESURFACING: I-70 TO IN	06/09/22	24.00	500.00	569.36	569.36
		WEIGHTED AVERAGE FOR THE SECOND QUARTER		50.00	552.00	512.87	595.69
NHPP0702-414		VAIL PASS AUX PHASE 1 CAP 3	07/08/22	7.00	1309.68	1309.68	1309.68
FBR0702-423		VAIL PASS AUX BE F-12-AT PHAS					
		WEIGHTED AVERAGE FOR THE THIRD QUARTER		7.00	1309.68	1309.68	1309.68

PROJECT NUMBER	ITEM NUMBER/ PROJECT LOCATION	ITEM DESCRIPTION/ PROJECT LOCATION	DATE LET	UNIT/ QUANTITY	ENGR. EST.	AVERAGE BID	AWARDED BID
===== 202-00827		Rem of Pull Box		Each	=====	=====	=====
STA3852-015		US 385 HOLYOKE NORTH	10/27/22	4.00	500.00	525.00	525.00
STAM420-001		US 285 AT HWY 9C IMPROVEMENTS	12/01/22	8.00	610.00	386.86	586.44
BR2854-148		INTERSECTION OF US 285 & SH 9					
STM0091-046		ADA RAMP IMPROVEMENTS - FAIRP					
2670703-487		I-70 BRIDGES OVER WARD ROAD-	12/01/22	2.00	300.00	156.19	150.00
NHPP083A-046		SH83 RESURFACING STROH RD TO	12/08/22	5.00	250.00	138.96	129.91
NHPP0931-033		SH93:US6 TO 58TH RESURFACING	12/15/22	11.00	550.00	386.54	445.00
		WEIGHTED AVERAGE FOR THE FOURTH QUARTER		30.00	492.67	400.12	488.63
		WEIGHTED AVERAGE FOR THE YEAR		170.00	577.66	530.32	618.39
===== 202-00828		Rem Traf Sig Equipment		LUMP SUM	=====	=====	=====
2670703-479		I-70 BRIDGE OVER HARLAN	05/05/22	1.00	40000.00	17766.45	20772.54
CM760-047		COLFAX AND QUAIL	05/12/22	1.00	5000.00	9895.00	6450.00
NHPP072A-047		SH-72 RESURFACING: I-70 TO IN	06/09/22	1.00	20000.00	28767.76	28767.76
		WEIGHTED AVERAGE FOR THE SECOND QUARTER		3.00	21666.67	15403.45	18663.43
NHPP0063-054		US 6 FROM I70-B TO 33 RD. (MP	08/18/22	1.00	25000.00	44907.77	50000.00
C1211-099		SH 121 NORTH SGA SIGNALS	08/25/22	1.00	100000.00	62375.00	59750.00
SHE2873-193		US 287 & CO 52 INTERSECTION I	09/15/22	1.00	10000.00	12010.47	8500.00
		WEIGHTED AVERAGE FOR THE THIRD QUARTER		3.00	45000.00	28662.83	39416.67
FSAM240-200		SH21B CO SPRINGS SIGNAL REPLA	10/27/22	1.00	22000.00	28375.00	19200.00
TRG0253-264		I-25 AND SH 119 PARK-N-RIDE	10/27/22	1.00	25000.00	1298.41	1260.00
STU0252-457		I-25:ALAMEDA RIVER PH 2.0	11/03/22	1.00	70000.00	26517.75	26500.00
STAM420-001		US 285 AT HWY 9C IMPROVEMENTS	12/01/22	1.00	9200.00	23877.16	36163.65
BR2854-148		INTERSECTION OF US 285 & SH 9					
STM0091-046		ADA RAMP IMPROVEMENTS - FAIRP					
NHPP0931-033		SH93:US6 TO 58TH RESURFACING	12/15/22	1.00	18000.00	9808.84	7150.00
		WEIGHTED AVERAGE FOR THE FOURTH QUARTER		5.00	28840.00	14703.67	18054.73
		WEIGHTED AVERAGE FOR THE YEAR		11.00	31290.91	17992.32	24046.72

COLORADO DEPARTMENT OF TRANSPORTATION
 ITEM UNIT COSTS BY PROJECTS -- 2022 COST DATA

11:31 Wednesday, March 8, 2023 51

PROJECT NUMBER	ITEM NUMBER/ PROJECT LOCATION	ITEM DESCRIPTION/ PROJECT LOCATION	DATE LET	UNIT/ QUANTITY	ENGR. EST.	AVERAGE BID	AWARDED BID
=====	202-00831	Rem Traf Sig Head		Each	=====	=====	=====
TRG0253-264		I-25 AND SH 119 PARK-N-RIDE	10/27/22	9.00	325.00	57.02	55.00
NHPP083A-046		SH83 RESURFACING STROH RD TO	12/08/22	4.00	150.00	186.94	174.88
		WEIGHTED AVERAGE FOR THE FOURTH QUARTER		13.00	271.15	70.01	91.89
		WEIGHTED AVERAGE FOR THE YEAR		13.00	271.15	70.01	91.89
=====	202-00848	Rem Traf Sig Control+Cab		Each	=====	=====	=====
NHPP2873-189		US 287 (FEDERAL BLVD) - COLFA	01/06/22	1.00	2000.00	726.16	682.13
		WEIGHTED AVERAGE FOR THE FIRST QUARTER		1.00	2000.00	726.16	682.13
		WEIGHTED AVERAGE FOR THE YEAR		1.00	2000.00	726.16	682.13
=====	202-00855	Rem Traf Sig Control Cab		Each	=====	=====	=====
ITS0703-477		ITS EQUIPMENT UPGRADE AT EJMT	01/06/22	1.00	2500.00	3850.00	3850.00
		WEIGHTED AVERAGE FOR THE FIRST QUARTER		1.00	2500.00	3850.00	3850.00
		WEIGHTED AVERAGE FOR THE YEAR		1.00	2500.00	3850.00	3850.00
=====	202-00858	Rem Pedestal Pole		Each	=====	=====	=====
CR100-362			03/14/22	13.00	936.25	936.25	936.25
		WEIGHTED AVERAGE FOR THE FIRST QUARTER		13.00	936.25	936.25	936.25
		WEIGHTED AVERAGE FOR THE YEAR		13.00	936.25	936.25	936.25
=====	202-00860	Rem Ped Push Button		Each	=====	=====	=====
NHPP2873-189		US 287 (FEDERAL BLVD) - COLFA	01/06/22	8.00	120.00	85.80	79.89
CR100-362			03/14/22	83.00	363.80	363.80	363.80
NHM765-007			03/31/22	8.00	150.00	177.52	159.60
		WEIGHTED AVERAGE FOR THE FIRST QUARTER		99.00	326.82	267.64	324.36

PROJECT NUMBER	ITEM NUMBER/ PROJECT LOCATION	ITEM DESCRIPTION/ PROJECT LOCATION	DATE LET	UNIT/ QUANTITY	ENGR. EST.	AVERAGE BID	AWARDED BID
=====	202-00860	Rem Ped Push Button		Each	=====	=====	=====
CC030-081		ADA RAMP AND CURBS - FT. LUPT	04/14/22	12.00	150.00	425.49	410.00
NHPP072A-047		SH-72 RESURFACING: I-70 TO IN	06/09/22	46.00	90.00	41.95	41.95
		WEIGHTED AVERAGE FOR THE SECOND QUARTER		58.00	102.41	210.33	118.10
TRG0253-264		I-25 AND SH 119 PARK-N-RIDE	10/27/22	9.00	400.00	38.49	31.00
NHPP0931-033		SH93:US6 TO 58TH RESURFACING	12/15/22	20.00	400.00	32.75	27.65
		WEIGHTED AVERAGE FOR THE FOURTH QUARTER		29.00	400.00	35.47	28.69
		WEIGHTED AVERAGE FOR THE YEAR		186.00	268.25	160.43	213.94
=====	202-00887	Rem Radar Detect Sys		Each	=====	=====	=====
MP0503-098			03/24/22	42.00	500.00	280.00	440.00
		WEIGHTED AVERAGE FOR THE FIRST QUARTER		42.00	500.00	280.00	440.00
2670703-487		I-70 BRIDGES OVER WARD ROAD-	12/01/22	2.00	1000.00	366.18	350.00
		WEIGHTED AVERAGE FOR THE FOURTH QUARTER		2.00	1000.00	366.18	350.00
		WEIGHTED AVERAGE FOR THE YEAR		44.00	522.73	289.17	435.91
=====	202-00888	Rem Video Detect Sys		Each	=====	=====	=====
MP0503-098			03/24/22	75.00	600.00	295.00	440.00
		WEIGHTED AVERAGE FOR THE FIRST QUARTER		75.00	600.00	295.00	440.00
		WEIGHTED AVERAGE FOR THE YEAR		75.00	600.00	295.00	440.00
=====	202-00889	Rem of Detect Warning		Each	=====	=====	=====
STR0505-050			01/13/22	1.00	500.00	1833.33	2000.00
		WEIGHTED AVERAGE FOR THE FIRST QUARTER		1.00	500.00	1833.33	2000.00

PROJECT NUMBER	ITEM NUMBER/ PROJECT LOCATION	ITEM DESCRIPTION/ PROJECT LOCATION	DATE LET	UNIT/ QUANTITY	ENGR. EST.	AVERAGE BID	AWARDED BID
===== 202-00889		Rem of Detect Warning		Each	=====		
C1211-099		SH 121 NORTH SGA SIGNALS	08/25/22	2.00	200.00	375.00	420.00
		WEIGHTED AVERAGE FOR THE THIRD QUARTER		2.00	200.00	375.00	420.00
		WEIGHTED AVERAGE FOR THE YEAR		3.00	300.00	1000.00	946.67
===== 202-00895		Rem of Impact Attenuator		Each	=====		
NHPP0702-383		I-70 EB AUX FRISCO TO SILVERT	01/13/22	2.00	1500.00	2057.89	1600.00
NHPP 0761-238		I-76 DAHLIA TO YORK	03/10/22	4.00	1800.00	1880.66	1800.00
C0761-239							
		WEIGHTED AVERAGE FOR THE FIRST QUARTER		6.00	1700.00	1922.86	1733.33
		WEIGHTED AVERAGE FOR THE YEAR		6.00	1700.00	1922.86	1733.33
===== 202-00900		Rem Conc Footing		Each	=====		
STAM420-001		US 285 AT HWY 9C IMPROVEMENTS	12/01/22	2.00	1500.00	4584.39	10949.94
BR2854-148		INTERSECTION OF US 285 & SH 9					
STM0091-046		ADA RAMP IMPROVEMENTS - FAIRP					
		WEIGHTED AVERAGE FOR THE FOURTH QUARTER		2.00	1500.00	4584.39	10949.94
		WEIGHTED AVERAGE FOR THE YEAR		2.00	1500.00	4584.39	10949.94
===== 202-01000		Rem Fence		Lin Foot	=====		
NH0504-910		US50B L-24-B MIN REP AT MP 40	01/13/22	1,420.00	3.00	3.63	1.88
NHPP0702-383		I-70 EB AUX FRISCO TO SILVERT	01/13/22	28,572.00	5.00	1.70	1.40
STA0252-459			02/03/22	57,215.00	1.24	0.73	0.50
NHPP 0761-238		I-76 DAHLIA TO YORK	03/10/22	1,886.00	1.50	5.78	6.00
C0761-239							
		WEIGHTED AVERAGE FOR THE FIRST QUARTER		89,093.00	2.48	1.46	0.93
STM1151-038		SH115 MP 27 TO MP 38	04/21/22	257.00	16.00	8.79	8.00

PROJECT NUMBER	ITEM NUMBER/ PROJECT LOCATION	ITEM DESCRIPTION/ PROJECT LOCATION	DATE LET	UNIT/ QUANTITY	ENGR. EST.	AVERAGE BID	AWARDED BID
===== 202-01000							
		Rem Fence		Lin Foot			
2670703-479		I-70 BRIDGE OVER HARLAN	05/05/22	767.00	3.00	6.73	7.50
FSA0702-409		I-70 VAIL WILDLIFE FENCE PHAS	05/26/22	7,741.00	10.00	6.00	6.00
		WEIGHTED AVERAGE FOR THE SECOND QUARTER		8,765.00	9.56	6.51	6.19
=====							
FSA052A-057		SH52 BOX CULVERT EXTENSION (M	08/04/22	120.00	10.00	9.37	9.10
NHPP0063-054		US 6 FROM I70-B TO 33 RD. (MP	08/18/22	131.00	6.00	16.81	11.00
BR0343-046		US 34 TIMBER BRIDGE REPL. PKG	08/31/22	356.00	3.75	8.04	8.04
FBR0343-047		US 6/US 34 TIMBER BRIDGE REPL					
2670703-497		I-70 GENESEE WILDLIFE XING	09/15/22	18,410.00	3.70	1.08	0.70
SHE2873-193		US 287 & CO 52 INTERSECTION I	09/15/22	185.00	2.50	11.24	7.00
		WEIGHTED AVERAGE FOR THE THIRD QUARTER		19,202.00	3.74	1.24	1.02
=====							
STU0252-457		I-25:ALAMEDA RIVER PH 2.0	11/03/22	1,535.00	4.00	9.60	8.00
SHE0242-087		US 24 SAFETY IMPRVMENTS, E OF	11/03/22	195.00	2.00	7.00	2.99
C5502-097		US550 MP 117.28-126.06	11/17/22	6,535.00	6.00	2.28	2.55
STAM420-001		US 285 AT HWY 9C IMPROVEMENTS	12/01/22	1,213.00	4.50	4.10	3.78
BR2854-148		INTERSECTION OF US 285 & SH 9					
STM0091-046		ADA RAMP IMPROVEMENTS - FAIRP					
2670703-487		I-70 BRIDGES OVER WARD ROAD-	12/01/22	252.00	3.00	6.80	6.50
IM025A-050		I25-MP103.9 - INTERSECTION DR	12/01/22	46.00	2.00	14.50	6.50
NHPP0931-033		SH93:US6 TO 58TH RESURFACING	12/15/22	506.00	3.00	4.45	7.65
NHPP0502-090		SH 50 MP 134.6-136 GUNNISON C	12/22/22	2,174.00	2.00	5.05	3.90
BR012A-048		CO 12 STRUCTURE P-17-F AT MP	12/22/22	1,384.00	10.00	5.04	5.00
STA385A-016		SH 385 MP 97.76	12/22/22	500.00	2.00	5.35	4.39
		WEIGHTED AVERAGE FOR THE FOURTH QUARTER		14,340.00	5.07	4.35	4.01
		WEIGHTED AVERAGE FOR THE YEAR		131,400.00	3.42	1.80	1.63
=====							
===== 202-01020							
		Rem Noise Barrier Fence		Lin Foot			
2670703-479		I-70 BRIDGE OVER HARLAN	05/05/22	1,310.00	50.00	22.61	4.40
		WEIGHTED AVERAGE FOR THE SECOND QUARTER		1,310.00	50.00	22.61	4.40
		WEIGHTED AVERAGE FOR THE YEAR		1,310.00	50.00	22.61	4.40
=====							
===== 202-01030							
		Rem of Road Closure Gate		Each			
NHPP0702-383		I-70 EB AUX FRISCO TO SILVERT	01/13/22	2.00	2000.00	2034.79	1800.00
		WEIGHTED AVERAGE FOR THE FIRST QUARTER		2.00	2000.00	2034.79	1800.00

PROJECT NUMBER	ITEM NUMBER/ PROJECT LOCATION	ITEM DESCRIPTION/ PROJECT LOCATION	DATE LET	UNIT/ QUANTITY	ENGR. EST.	AVERAGE BID	AWARDED BID
===== 202-01030		Rem of Road Closure Gate		Each	=====	=====	=====
STA3852-015		US 385 HOLYOKE NORTH	10/27/22	2.00	3000.00	3250.00	3250.00
STR096A-050		SH 96 MP 168.99 TO 193.77	12/22/22	1.00	1700.00	3100.00	3000.00
		WEIGHTED AVERAGE FOR THE FOURTH QUARTER		3.00	2566.67	3160.00	3166.67
		WEIGHTED AVERAGE FOR THE YEAR		5.00	2340.00	2409.86	2620.00
===== 202-01035		Rem of Gate		Each	=====	=====	=====
STA0252-459			02/03/22	12.00	160.00	232.29	225.00
		WEIGHTED AVERAGE FOR THE FIRST QUARTER		12.00	160.00	232.29	225.00
C5502-097		US550 MP 117.28-126.06	11/17/22	17.00	300.00	286.04	227.00
		WEIGHTED AVERAGE FOR THE FOURTH QUARTER		17.00	300.00	286.04	227.00
		WEIGHTED AVERAGE FOR THE YEAR		29.00	242.07	263.80	226.17
===== 202-01130		Rem Gdrail Ty 3		Lin Foot	=====	=====	=====
NH0504-910		US50B L-24-B MIN REP AT MP 40	01/13/22	1,145.00	5.00	8.20	8.94
NHPP0702-383		I-70 EB AUX FRISCO TO SILVERT	01/13/22	3,766.00	5.00	4.92	4.00
NHPP1601-083			02/03/22	7,117.50	5.00	4.51	5.00
STA0252-459			02/03/22	720.00	5.00	5.96	5.75
C0762-055			02/17/22	957.00	6.00	5.98	7.00
STA 067A-048		Hwy 67A MP 0.00 TO MP 11.05 I	03/03/22	3,279.00	8.00	7.08	6.00
NHPP 0761-238		I-76 DAHLIA TO YORK	03/10/22	16,888.00	6.00	4.07	4.00
C0761-239							
STR160A-034		US160A LA VETA PASS EAST SURF	03/17/22	15,626.00	5.00	5.79	5.58
STR092A-031			03/17/22	2,656.00	6.00	8.00	8.00
		WEIGHTED AVERAGE FOR THE FIRST QUARTER		52,154.50	5.58	4.80	5.13
NH0504-911			04/07/22	6,550.00	11.51	6.10	6.20

COLORADO DEPARTMENT OF TRANSPORTATION
ITEM UNIT COSTS BY PROJECTS -- 2022 COST DATA

11:31 Wednesday, March 8, 2023 56

PROJECT NUMBER	ITEM NUMBER/ PROJECT LOCATION	ITEM DESCRIPTION/ PROJECT LOCATION	DATE LET	UNIT/ QUANTITY	ENGR. EST.	AVERAGE BID	AWARDED BID
=====	202-01130	Rem Gdrail Ty 3		Lin Foot	=====	=====	=====
STM1151-038		SH115 MP 27 TO MP 38	04/21/22	13,203.00	5.00	5.60	5.60
2670703-479		I-70 BRIDGE OVER HARLAN	05/05/22	1,049.00	6.00	5.17	5.10
NHPP 3851-018		US 385 NORTH OF CHEYENNE WELL	05/26/22	590.00	5.00	11.00	12.00
NHPP072A-047		SH-72 RESURFACING: I-70 TO IN	06/09/22	768.00	6.00	14.42	14.42
		WEIGHTED AVERAGE FOR THE SECOND QUARTER		22,160.00	7.01	5.79	6.23
NHPP0702-414		VAIL PASS AUX PHASE 1 CAP 3	07/08/22	401.00	15.43	15.43	15.43
FBR0702-423		VAIL PASS AUX BE F-12-AT PHAS					
ER0502-092		US 50 MP 204 EB MONARCH TRUCK	08/29/22	387.50	15.00	7.55	8.22
BR0343-046		US 34 TIMBER BRIDGE REPL. PKG	08/31/22	1,248.00	5.72	5.72	5.72
FBR0343-047		US 6/US 34 TIMBER BRIDGE REPL					
PAN0761-245		ALONG I-76 & RAMPS MILEPOST 9	09/01/22	150.00	8.00	13.00	5.00
2670403-065		US40 FLOYD HILL ROUNDABOUTS	09/15/22	1,136.00	8.00	9.17	9.00
2670703-497		I-70_GENESEE WILDLIFE XING	09/15/22	3,965.00	6.00	10.45	10.17
NHPP0701-231		I-70 SALT WASH BRIDGES SCOUR	09/29/22	445.00	20.00	10.77	11.00
		WEIGHTED AVERAGE FOR THE THIRD QUARTER		7,732.50	8.03	10.15	9.40
NHPP0701-253		I-70 EAST OF DEBEQUE	10/27/22	10,793.00	7.00	5.43	7.00
STA207A-004		Resurfacing SH207A MANZANOLA	10/27/22	665.00	6.50	7.75	8.25
TRG0253-264		I-25 AND SH 119 PARK-N-RIDE	10/27/22	250.00	7.50	13.04	5.00
STU0252-457		I-25:ALAMEDA RIVER PH 2.0	11/03/22	526.00	10.00	7.49	6.50
SHE0242-087		US 24 SAFETY IMPRVMENTS, E OF	11/03/22	1,342.00	6.00	6.75	9.26
STR064A-010		SH 64 AND SH 13 AT MEEKER	11/10/22	1,475.00	8.00	4.95	5.10
C5502-097		US550 MP 117.28-126.06	11/17/22	5,008.00	8.00	5.30	4.90
STRC090-011		US 50B AND SH71/CR18 INTERSEC	11/17/22	395.00	10.00	8.13	8.25
STAM420-001		US 285 AT HWY 9C IMPROVEMENTS	12/01/22	1,202.00	4.20	5.99	7.19
BR2854-148		INTERSECTION OF US 285 & SH 9					
STM0091-046		ADA RAMP IMPROVEMENTS - FAIRP					
STA0711-021		SH71: REGION LINE NORTH	12/01/22	150.00	7.00	8.08	5.00
STR114A-015		SH114 SILLSVILLE SOUTH TO MP3	12/01/22	1,108.00	12.00	14.25	15.00
2670703-487		I-70 BRIDGES OVER WARD ROAD-	12/01/22	3,123.00	3.80	5.62	5.20
NHPP0701-252		I-70 RIFLE TO SILT SLAB REPLA	12/01/22	11,961.00	7.00	8.75	2.50
IM025A-050		I25-MP103.9 - INTERSECTION DR	12/01/22	254.00	4.00	8.33	7.50
NHPP0063-048		US6 / 20 ROAD INTERSECTION IM	12/15/22	400.00	8.00	20.39	13.15
NHPP0931-033		SH93:US6 TO 58TH RESURFACING	12/15/22	2,248.00	6.00	4.29	3.35
NHPP0502-090		SH 50 MP 134.6-136 GUNNISON C	12/22/22	878.00	10.00	9.48	7.21
STR0092-024		SH 9 North of Silverthorne	12/22/22	6,605.00	7.00	9.15	4.30
STA0361-129		US 36: HYGIENE RD AND NELSON	12/22/22	590.00	15.00	5.39	5.66
BR012A-048		CO 12 STRUCTURE P-17-F AT MP	12/22/22	429.00	5.00	11.30	15.00
STA385A-016		SH 385 MP 97.76	12/22/22	1,025.00	6.00	6.75	5.00

COLORADO DEPARTMENT OF TRANSPORTATION
 ITEM UNIT COSTS BY PROJECTS -- 2022 COST DATA

11:31 Wednesday, March 8, 2023 57

PROJECT NUMBER	ITEM NUMBER/ PROJECT LOCATION	ITEM DESCRIPTION/ PROJECT LOCATION	DATE LET	UNIT/ QUANTITY	ENGR. EST.	AVERAGE BID	AWARDED BID
===== 202-01130		Rem Gdrail Ty 3		Lin Foot			
STR096A-050		SH 96 MP 168.99 TO 193.77	12/22/22	1,143.50	6.60	6.33	6.00
		WEIGHTED AVERAGE FOR THE FOURTH QUARTER		51,570.50	7.04	7.13	5.57
		WEIGHTED AVERAGE FOR THE YEAR		133,617.50	6.52	6.07	5.72
===== 202-01140		Rem Gdrail Ty 4		Lin Foot			
2670703-479		I-70 BRIDGE OVER HARLAN	05/05/22	1,559.00	25.00	26.10	42.00
		WEIGHTED AVERAGE FOR THE SECOND QUARTER		1,559.00	25.00	26.10	42.00
STR064A-010		SH 64 AND SH 13 AT MEEKER	11/10/22	520.00	60.00	37.60	20.00
		WEIGHTED AVERAGE FOR THE FOURTH QUARTER		520.00	60.00	37.60	20.00
		WEIGHTED AVERAGE FOR THE YEAR		2,079.00	33.75	27.25	36.50
===== 202-01170		Rem Gdrail Ty 7		Lin Foot			
NHPP 0761-238		I-76 DAHLIA TO YORK	03/10/22	6,766.00	18.00	19.65	13.00
C0761-239							
NHPP0703-472		FY22 R1 SIGN STRUCTURE REPLAC	03/10/22	584.00	26.00	58.85	55.00
M R100-351			03/17/22	361.00	100.00	145.50	95.00
		WEIGHTED AVERAGE FOR THE FIRST QUARTER		7,711.00	22.44	22.84	20.02
2670703-479		I-70 BRIDGE OVER HARLAN	05/05/22	1,312.00	25.00	18.51	18.75
		WEIGHTED AVERAGE FOR THE SECOND QUARTER		1,312.00	25.00	18.51	18.75
NHPP0702-414		VAIL PASS AUX PHASE 1 CAP 3	07/08/22	1,478.00	17.04	17.04	17.04
FBR0702-423		VAIL PASS AUX BE F-12-AT PHAS					
		WEIGHTED AVERAGE FOR THE THIRD QUARTER		1,478.00	17.04	17.04	17.04

COLORADO DEPARTMENT OF TRANSPORTATION
ITEM UNIT COSTS BY PROJECTS -- 2022 COST DATA

11:31 Wednesday, March 8, 2023 58

PROJECT NUMBER	ITEM NUMBER/ PROJECT LOCATION	ITEM DESCRIPTION/ PROJECT LOCATION	DATE LET	UNIT/ QUANTITY	ENGR. EST.	AVERAGE BID	AWARDED BID
=====	202-01170	Rem Gdrail Ty 7		Lin Foot	=====		
STU0252-457		I-25:ALAMEDA RIVER PH 2.0	11/03/22	82.00	30.00	52.19	58.00
IM025A-050		I25-MP103.9 - INTERSECTION DR	12/01/22	252.00	22.00	30.00	15.00
STR0092-024		SH 9 North of Silverthorne	12/22/22	463.00	30.00	154.00	108.00
		WEIGHTED AVERAGE FOR THE FOURTH QUARTER		797.00	27.47	66.10	57.37
		WEIGHTED AVERAGE FOR THE YEAR		11,298.00	22.39	24.40	23.31
=====	202-01175	Rem of Guardrail (Spec)		Lin Foot	=====		
2670403-065		US40_FLOYD HILL ROUNDABOUTS	09/15/22	108.00	100.00	32.04	35.00
		WEIGHTED AVERAGE FOR THE THIRD QUARTER		108.00	100.00	32.04	35.00
STR096A-050		SH 96 MP 168.99 TO 193.77	12/22/22	84.00	100.00	82.00	75.00
		WEIGHTED AVERAGE FOR THE FOURTH QUARTER		84.00	100.00	82.00	75.00
		WEIGHTED AVERAGE FOR THE YEAR		192.00	100.00	53.90	52.50
=====	202-01200	Rem High-Tension Cable Barrier		Lin Foot	=====		
FSA0853-122		WCRI4.5 AND US-85, FORT LUPTO	12/15/22	200.00	20.00	13.70	15.00
		WEIGHTED AVERAGE FOR THE FOURTH QUARTER		200.00	20.00	13.70	15.00
		WEIGHTED AVERAGE FOR THE YEAR		200.00	20.00	13.70	15.00
=====	202-01300	Rem End Anchorage		Each	=====		
NH0504-910		US50B L-24-B MIN REP AT MP 40	01/13/22	5.00	600.00	389.24	373.33
NHPP0702-383		I-70 EB AUX FRISCO TO SILVERT	01/13/22	10.00	350.00	193.20	235.00
NHPP1601-083			02/03/22	30.00	200.00	483.93	400.00
STA0252-459			02/03/22	2.00	400.00	417.08	418.00
NHPP 0761-238		I-76 DAHLIA TO YORK	03/10/22	9.00	340.00	291.98	300.00

PROJECT NUMBER	ITEM NUMBER/ PROJECT LOCATION	ITEM DESCRIPTION/ PROJECT LOCATION	DATE LET	UNIT/ QUANTITY	ENGR. EST.	AVERAGE BID	AWARDED BID
=====	202-01300	Rem End Anchorage		Each =====			
C0761-239							
STR160A-034		US160A LA VETA PASS EAST SURF	03/17/22	26.00	300.00	270.44	240.87
STR092A-031			03/17/22	16.00	350.00	550.00	550.00
		WEIGHTED AVERAGE FOR THE FIRST QUARTER		98.00	303.67	340.04	355.26
NH0504-911			04/07/22	42.00	324.90	324.50	324.00
STM1151-038		SH115 MP 27 TO MP 38	04/21/22	50.00	350.00	373.98	278.00
2670703-479		I-70 BRIDGE OVER HARLAN	05/05/22	3.00	350.00	285.53	301.93
NHPP 3851-018		US 385 NORTH OF CHEYENNE WELL	05/26/22	4.00	350.00	642.50	700.00
NHPP072A-047		SH-72 RESURFACING: I-70 TO IN	06/09/22	14.00	350.00	650.30	650.30
MTCE0253-291		I-25 SIGN REPLACEMENT PHASE 2	06/16/22	1.00	375.00	221.68	206.36
		WEIGHTED AVERAGE FOR THE SECOND QUARTER		114.00	340.97	373.88	355.48
NHPP0702-414		VAIL PASS AUX PHASE 1 CAP 3	07/08/22	3.00	588.53	588.53	588.53
FBR0702-423		VAIL PASS AUX BE F-12-AT PHAS					
ER0502-092		US 50 MP 204 EB MONARCH TRUCK	08/29/22	4.00	600.00	647.90	920.38
PAN0761-245		ALONG I-76 & RAMPS MILEPOST 9	09/01/22	24.00	340.00	450.00	475.00
2670403-065		US40 FLOYD HILL ROUNDABOUTS	09/15/22	8.00	400.00	403.74	380.00
NHPP0701-231		I-70 SALT WASH BRIDGES SCOUR	09/29/22	4.00	700.00	346.51	505.00
		WEIGHTED AVERAGE FOR THE THIRD QUARTER		43.00	426.18	458.97	509.47
NHPP0701-253		I-70 EAST OF DEBEQUE	10/27/22	22.00	300.00	504.00	265.00
STA207A-004		Resurfacing SH207A MANZANOLA	10/27/22	8.00	360.00	693.33	850.00
STU0252-457		I-25:ALAMEDA RIVER PH 2.0	11/03/22	3.00	350.00	338.42	300.00
SHE0242-087		US 24 SAFETY IMPRVMENTS, E OF	11/03/22	4.00	350.00	628.23	354.69
STR064A-010		SH 64 AND SH 13 AT MEEKER	11/10/22	12.00	700.00	1352.50	1375.00
C5502-097		US550 MP 117.28-126.06	11/17/22	26.00	500.00	529.42	492.00
STRC090-011		US 50B AND SH71/CR18 INTERSEC	11/17/22	1.00	870.00	780.00	810.00
STAM420-001		US 285 AT HWY 9C IMPROVEMENTS	12/01/22	14.00	400.00	305.02	366.36
BR2854-148		INTERSECTION OF US 285 & SH 9					
STM0091-046		ADA RAMP IMPROVEMENTS - FAIRP					
STR114A-015		SH114 SILLSVILLE SOUTH TO MP3	12/01/22	12.00	550.00	607.50	600.00
NHPP0701-252		I-70 RIFLE TO SILT SLAB REPLA	12/01/22	43.00	600.00	385.00	400.00
IM025A-050		I25-MP103.9 - INTERSECTION DR	12/01/22	3.00	350.00	320.00	260.00
NHPP083A-046		SH83 RESURFACING STROH RD TO	12/08/22	2.00	900.00	12959.76	7819.52
FSA0853-122		WCR14.5 AND US-85, FORT LUPTO	12/15/22	2.00	500.00	638.14	700.00

COLORADO DEPARTMENT OF TRANSPORTATION
 ITEM UNIT COSTS BY PROJECTS -- 2022 COST DATA

11:31 Wednesday, March 8, 2023 60

PROJECT NUMBER	ITEM NUMBER/ PROJECT LOCATION	ITEM DESCRIPTION/ PROJECT LOCATION	DATE LET	UNIT/ QUANTITY	ENGR. EST.	AVERAGE BID	AWARDED BID
===== 202-01300							
		Rem End Anchorage		Each			
NHPP0931-033		SH93:US6 TO 58TH RESURFACING	12/15/22	16.00	450.00	316.94	425.50
NHPP0502-090		SH 50 MP 134.6-136 GUNNISON C	12/22/22	39.00	500.00	702.53	533.72
STR0092-024		SH 9 North of Silverthorne	12/22/22	38.00	1000.00	367.50	275.00
STA0361-129		US 36: HYGIENE RD AND NELSON	12/22/22	10.00	700.00	407.13	430.44
BR012A-048		CO 12 STRUCTURE P-17-F AT MP	12/22/22	4.00	400.00	502.67	600.00
STR096A-050		SH 96 MP 168.99 TO 193.77	12/22/22	16.00	370.00	470.33	600.00
		WEIGHTED AVERAGE FOR THE FOURTH QUARTER		275.00	564.62	582.71	522.10
		WEIGHTED AVERAGE FOR THE YEAR		530.00	457.03	485.12	457.32
===== 202-04000							
		Plug Structure		Each			
2670703-479		I-70 BRIDGE OVER HARLAN	05/05/22	1.00	3000.00	2368.16	3923.57
		WEIGHTED AVERAGE FOR THE SECOND QUARTER		1.00	3000.00	2368.16	3923.57
		WEIGHTED AVERAGE FOR THE YEAR		1.00	3000.00	3362.92	7961.79
===== 202-04001							
		Plug Culvert		Each			
NHPP1601-083			02/03/22	2.00	4000.00	8548.07	4000.00
NHPP 0761-238		I-76 DAHLIA TO YORK	03/10/22	1.00	3820.00	3250.63	2500.00
C0761-239							
NHM765-007			03/31/22	1.00	3000.00	18142.27	3100.01
		WEIGHTED AVERAGE FOR THE FIRST QUARTER		4.00	3705.00	7641.61	3400.00
===== 2670703-479							
		I-70 BRIDGE OVER HARLAN	05/05/22	1.00	4000.00	2351.29	3923.57
		WEIGHTED AVERAGE FOR THE SECOND QUARTER		1.00	4000.00	2351.29	3923.57
===== 2670403-065							
		US40_FLOYD HILL ROUNDABOUTS	09/15/22	1.00	2500.00	2021.24	1200.00
		WEIGHTED AVERAGE FOR THE THIRD QUARTER		1.00	2500.00	2021.24	1200.00
===== TRG0253-264							
		I-25 AND SH 119 PARK-N-RIDE	10/27/22	3.00	4000.00	4042.16	1100.00

COLORADO DEPARTMENT OF TRANSPORTATION
 ITEM UNIT COSTS BY PROJECTS -- 2022 COST DATA

11:31 Wednesday, March 8, 2023 61

PROJECT NUMBER	ITEM NUMBER/ PROJECT LOCATION	ITEM DESCRIPTION/ PROJECT LOCATION	DATE LET	UNIT/ QUANTITY	ENGR. EST.	AVERAGE BID	AWARDED BID
=====	202-04001	Plug Culvert		Each =====			
STU0252-457		I-25:ALAMEDA RIVER PH 2.0	11/03/22	1.00	3000.00	3312.80	2300.00
		WEIGHTED AVERAGE FOR THE FOURTH QUARTER		4.00	3750.00	3961.12	1400.00
		WEIGHTED AVERAGE FOR THE YEAR		10.00	3632.00	4740.12	2432.36
=====	202-04002	Clean Culvert		Each =====			
NHPP0702-383		I-70 EB AUX FRISCO TO SILVERT	01/13/22	44.00	2000.00	3003.89	2800.00
NHPP1601-083			02/03/22	19.00	4000.00	3760.92	3600.00
STA 067A-048		Hwy 67A MP 0.00 TO MP 11.05 I	03/03/22	18.00	500.00	2352.63	1600.00
NHPP 0761-238		I-76 DAHLIA TO YORK	03/10/22	5.00	1700.00	2199.47	2000.00
C0761-239							
		WEIGHTED AVERAGE FOR THE FIRST QUARTER		86.00	2110.47	2894.29	2679.07
NH0504-911			04/07/22	3.00	2000.00	2015.00	1530.00
NHPP0702-413		VAIL PASS AUX PHASE 1 CAP 2	04/18/22	11.00	2428.24	2428.24	2428.24
STM1151-038		SH115 MP 27 TO MP 38	04/21/22	62.00	1000.00	2673.08	2749.91
2670703-479		I-70 BRIDGE OVER HARLAN	05/05/22	4.00	2000.00	1992.72	2429.43
NHC540-017		R2 CHAINUP STA @ KENOSHA/HOOS	05/12/22	6.00	1900.00	4733.33	7700.00
		WEIGHTED AVERAGE FOR THE SECOND QUARTER		86.00	1326.87	2711.33	2996.66
NHPP0702-414		VAIL PASS AUX PHASE 1 CAP 3	07/08/22	25.00	3759.87	3759.87	3759.87
FBR0702-423		VAIL PASS AUX BE F-12-AT PHAS					
FSA052A-057		SH52 BOX CULVERT EXTENSION (M	08/04/22	1.00	3000.00	5424.46	3213.60
NHPP0063-054		US 6 FROM I70-B TO 33 RD. (MP	08/18/22	1.00	2000.00	4811.22	3025.00
FBR0761-236		I-76 OVER CLR CRK SCOUR MIT	08/25/22	1.00	3000.00	9500.00	4500.00
C1211-099		SH 121 NORTH SGA SIGNALS	08/25/22	5.00	3500.00	2875.00	4000.00
NHPPR100-266		R1 ESSENTIAL REPAIRS	09/01/22	8.00	1500.00	2469.93	3159.80
		WEIGHTED AVERAGE FOR THE THIRD QUARTER		41.00	3207.24	3528.67	3658.87
STA207A-004		Resurfacing SH207A MANZANOLA	10/27/22	2.00	1200.00	3843.33	1830.00
TRG0253-264		I-25 AND SH 119 PARK-N-RIDE	10/27/22	10.00	2500.00	2327.01	2500.00
STA3852-015		US 385 HOLYOKE NORTH	10/27/22	30.00	2200.00	1550.00	1550.00

PROJECT NUMBER	ITEM NUMBER/ PROJECT LOCATION	ITEM DESCRIPTION/ PROJECT LOCATION	DATE LET	UNIT/ QUANTITY	ENGR. EST.	AVERAGE BID	AWARDED BID
=====	202-04002	Clean Culvert		Each =====			
SHE0242-087		US 24 SAFETY IMPRVMENTS, E OF	11/03/22	1.00	2000.00	2026.70	780.11
C5502-097		US550 MP 117.28-126.06	11/17/22	129.00	2500.00	2007.60	2210.00
STRC090-011		US 50B AND SH71/CR18 INTERSEC	11/17/22	1.00	5400.00	3363.00	3000.00
STAM420-001		US 285 AT HWY 9C IMPROVEMENTS	12/01/22	5.00	1883.00	2661.19	2215.98
BR2854-148		INTERSECTION OF US 285 & SH 9					
STM0091-046		ADA RAMP IMPROVEMENTS - FAIRP					
NHPP083A-046		SH83 RESURFACING STROH RD TO	12/08/22	10.00	1600.00	3165.09	1530.18
NHPP0063-048		US6 / 20 ROAD INTERSECTION IM	12/15/22	5.00	4000.00	3172.14	300.00
FSA0853-122		WCR14.5 AND US-85, FORT LUPTO	12/15/22	1.00	3000.00	2802.96	2600.00
NHPP0931-033		SH93:US6 TO 58TH RESURFACING	12/15/22	2.00	5000.00	3805.13	2560.00
NHPP0502-090		SH 50 MP 134.6-136 GUNNISON C	12/22/22	4.00	3000.00	3486.28	7012.77
STA0361-129		US 36: HYGIENE RD AND NELSON	12/22/22	10.00	3000.00	3123.32	1506.59
		WEIGHTED AVERAGE FOR THE FOURTH QUARTER		210.00	2493.88	2415.67	2114.77
		WEIGHTED AVERAGE FOR THE YEAR		423.00	2247.81	2654.41	2548.21
=====	202-04003	Clean Culvert (Spec)		Each =====			
C5502-097		US550 MP 117.28-126.06	11/17/22	1.00	10000.00	38212.89	39140.00
		WEIGHTED AVERAGE FOR THE FOURTH QUARTER		1.00	10000.00	38212.89	39140.00
		WEIGHTED AVERAGE FOR THE YEAR		1.00	10000.00	38212.89	39140.00
=====	202-04005	Clean Valve Box		Each =====			
NHPP2873-189		US 287 (FEDERAL BLVD) - COLFA	01/06/22	38.00	240.00	293.24	92.18
CR100-362			03/14/22	5.00	555.82	555.82	555.82
		WEIGHTED AVERAGE FOR THE FIRST QUARTER		43.00	276.72	301.60	146.09
2670703-479		I-70 BRIDGE OVER HARLAN	05/05/22	7.00	360.00	546.54	127.42
NHPP072A-047		SH-72 RESURFACING: I-70 TO IN	06/09/22	55.00	300.00	89.00	89.00
		WEIGHTED AVERAGE FOR THE SECOND QUARTER		62.00	306.77	287.11	93.34
STU0252-457		I-25:ALAMEDA RIVER PH 2.0	11/03/22	6.00	500.00	615.91	125.00

COLORADO DEPARTMENT OF TRANSPORTATION
ITEM UNIT COSTS BY PROJECTS -- 2022 COST DATA

11:31 Wednesday, March 8, 2023 63

PROJECT NUMBER	ITEM NUMBER/ PROJECT LOCATION	ITEM DESCRIPTION/ PROJECT LOCATION	DATE LET	UNIT/ QUANTITY	ENGR. EST.	AVERAGE BID	AWARDED BID
=====	202-04005	Clean Valve Box		Each	=====	=====	=====
C5502-097		US550 MP 117.28-126.06	11/17/22	13.00	300.00	396.28	244.00
2670703-487		I-70 BRIDGES OVER WARD ROAD-	12/01/22	7.00	150.00	400.90	440.00
NHPP0021-041		SH2 RESURFACING MLK TO 52ND	12/01/22	32.00	400.00	357.32	282.36
NHPP083A-046		SH83 RESURFACING STROH RD TO	12/08/22	4.00	150.00	381.60	81.19
NHPP0931-033		SH93:US6 TO 58TH RESURFACING	12/15/22	4.00	300.00	359.10	355.00
		WEIGHTED AVERAGE FOR THE FOURTH QUARTER		66.00	341.67	389.79	269.43
		WEIGHTED AVERAGE FOR THE YEAR		171.00	312.68	341.99	174.57
=====	202-04007	Plug Culvert		Cubic Yard	=====	=====	=====
NHPP0702-383		I-70 EB AUX FRISCO TO SILVERT	01/13/22	43.00	200.00	432.44	375.00
		WEIGHTED AVERAGE FOR THE FIRST QUARTER		43.00	200.00	432.44	375.00
		WEIGHTED AVERAGE FOR THE YEAR		43.00	200.00	623.01	587.26
=====	202-04008	Clean Culvert		Lin Foot	=====	=====	=====
STU0252-457		I-25:ALAMEDA RIVER PH 2.0	11/03/22	1,200.00	70.00	59.85	28.00
		WEIGHTED AVERAGE FOR THE FOURTH QUARTER		1,200.00	70.00	59.85	28.00
		WEIGHTED AVERAGE FOR THE YEAR		1,200.00	70.00	59.85	28.00
=====	202-04010	Clean Inlet		Each	=====	=====	=====
NHPP2873-189		US 287 (FEDERAL BLVD) - COLFA	01/06/22	98.00	500.00	708.13	202.79
C0762-055			02/17/22	4.00	1100.00	1174.42	350.00
NHPP0703-472			03/10/22	29.00	600.00	1286.53	300.00
BRC040-057			03/17/22	26.00	500.00	1048.75	75.00
		WEIGHTED AVERAGE FOR THE FIRST QUARTER		157.00	533.76	883.26	203.33
NH0504-911			04/07/22	38.00	730.00	4087.00	8024.00
STM1151-038		SH115 MP 27 TO MP 38	04/21/22	8.00	1500.00	866.25	906.30
2670703-479		I-70 BRIDGE OVER HARLAN	05/05/22	8.00	900.00	687.62	285.84
NHPP072A-047		SH-72 RESURFACING: I-70 TO IN	06/09/22	54.00	2000.00	195.80	195.80

COLORADO DEPARTMENT OF TRANSPORTATION
ITEM UNIT COSTS BY PROJECTS -- 2022 COST DATA

11:31 Wednesday, March 8, 2023 64

PROJECT NUMBER	ITEM NUMBER/ PROJECT LOCATION	ITEM DESCRIPTION/ PROJECT LOCATION	DATE LET	UNIT/ QUANTITY	ENGR. EST.	AVERAGE BID	AWARDED BID
=====	202-04010	Clean Inlet		Each	=====	=====	=====
NHPP0252-448		I-25 TREX NARROWS BRIDGE PREV	06/23/22	31.00	300.00	610.50	1000.00
		WEIGHTED AVERAGE FOR THE SECOND QUARTER		139.00	1181.58	1358.31	2561.31
C1211-099		SH 121 NORTH SGA SIGNALS	08/25/22	7.00	1000.00	2375.00	4000.00
		WEIGHTED AVERAGE FOR THE THIRD QUARTER		7.00	1000.00	2375.00	4000.00
STA207A-004		Resurfacing SH207A MANZANOLA	10/27/22	44.00	850.00	1315.00	3540.00
STU0252-457		I-25:ALAMEDA RIVER PH 2.0	11/03/22	37.00	1000.00	1335.06	650.00
2670703-487		I-70 BRIDGES OVER WARD ROAD-	12/01/22	5.00	1076.30	1713.05	550.00
IM025A-050		I25-MP103.9 - INTERSECTION DR	12/01/22	16.00	300.00	1173.33	520.00
STR109A-019		M-22-AY BRIDGE REHAB ON SH109	12/01/22	80.00	150.00	221.61	164.22
NHPP0021-041		SH2 RESURFACING MLK TO 52ND	12/01/22	43.00	850.00	1111.84	282.36
NHPP083A-046		SH83 RESURFACING STROH RD TO	12/08/22	25.00	860.00	1528.00	356.00
NHPP0931-033		SH93:US6 TO 58TH RESURFACING	12/15/22	12.00	1000.00	1517.03	1530.00
STR096A-050		SH 96 MP 168.99 TO 193.77	12/22/22	16.00	780.00	301.00	300.00
		WEIGHTED AVERAGE FOR THE FOURTH QUARTER		278.00	644.29	1021.76	892.87
		WEIGHTED AVERAGE FOR THE YEAR		581.00	747.25	1048.23	1143.14
=====	202-04050	Clean Exp Joint		Lin Foot	=====	=====	=====
BRC040-057			03/17/22	927.00	10.00	13.75	7.00
		WEIGHTED AVERAGE FOR THE FIRST QUARTER		927.00	10.00	13.75	7.00
NH0504-911			04/07/22	140.00	16.00	89.75	59.50
NHPP0252-448		I-25 TREX NARROWS BRIDGE PREV	06/23/22	1,504.00	10.00	16.50	15.00
		WEIGHTED AVERAGE FOR THE SECOND QUARTER		1,644.00	10.51	19.76	18.79
NHPP0021-041		SH2 RESURFACING MLK TO 52ND	12/01/22	293.00	20.00	28.21	15.77
		WEIGHTED AVERAGE FOR THE FOURTH QUARTER		293.00	20.00	28.21	15.77
		WEIGHTED AVERAGE FOR THE YEAR		2,864.00	11.32	18.65	14.66

COLORADO DEPARTMENT OF TRANSPORTATION
ITEM UNIT COSTS BY PROJECTS -- 2022 COST DATA

11:31 Wednesday, March 8, 2023 65

PROJECT NUMBER	ITEM NUMBER/ PROJECT LOCATION	ITEM DESCRIPTION/ PROJECT LOCATION	DATE LET	UNIT/ QUANTITY	ENGR. EST.	AVERAGE BID	AWARDED BID
=====	202-05008	Sawing Concrete (8 In)		Lin Foot	=====		
2670703-487		I-70 BRIDGES OVER WARD ROAD-	12/01/22	144.00	20.00	7.81	4.10
		WEIGHTED AVERAGE FOR THE FOURTH QUARTER		144.00	20.00	7.81	4.10
		WEIGHTED AVERAGE FOR THE YEAR		144.00	20.00	7.81	4.10
=====	202-05026	Sawing Asphalt Mat (6 In)		Lin Foot	=====		
BR0343-046 FBR0343-047		US 34 TIMBER BRIDGE REPL. PKG US 6/US 34 TIMBER BRIDGE REPL	08/31/22	6,170.00	4.85	10.21	10.21
		WEIGHTED AVERAGE FOR THE THIRD QUARTER		6,170.00	4.85	10.21	10.21
FSAM240-200		SH21B CO SPRINGS SIGNAL REPLA	10/27/22	1,506.00	3.00	7.08	6.30
		WEIGHTED AVERAGE FOR THE FOURTH QUARTER		1,506.00	3.00	7.08	6.30
		WEIGHTED AVERAGE FOR THE YEAR		7,676.00	4.49	8.66	9.44
=====	202-05030	Sawing Asphalt Mat (10 In)		Lin Foot	=====		
STR160A-034		US160A LA VETA PASS EAST SURF	03/17/22	2,000.00	6.00	2.33	1.66
		WEIGHTED AVERAGE FOR THE FIRST QUARTER		2,000.00	6.00	2.33	1.66
NHPP 3851-018		US 385 NORTH OF CHEYENNE WELL	05/26/22	13,000.00	3.00	3.25	3.00
		WEIGHTED AVERAGE FOR THE SECOND QUARTER		13,000.00	3.00	3.25	3.00
2670703-487 BR012A-048		I-70 BRIDGES OVER WARD ROAD-	12/01/22	1,471.00	10.00	4.87	5.10
		CO 12 STRUCTURE P-17-F AT MP	12/22/22	56.00	5.00	36.57	63.00
		WEIGHTED AVERAGE FOR THE FOURTH QUARTER		1,527.00	9.82	5.34	7.22
		WEIGHTED AVERAGE FOR THE YEAR		16,527.00	3.99	3.57	3.23

COLORADO DEPARTMENT OF TRANSPORTATION
 ITEM UNIT COSTS BY PROJECTS -- 2022 COST DATA

11:31 Wednesday, March 8, 2023 66

PROJECT NUMBER	ITEM NUMBER/ PROJECT LOCATION	ITEM DESCRIPTION/ PROJECT LOCATION	DATE LET	UNIT/ QUANTITY	ENGR. EST.	AVERAGE BID	AWARDED BID
===== 202-05100 Sandblasting Reinf Steel Sq Yard =====							
STR064A-010		SH 64 AND SH 13 AT MEEKER	11/10/22	32.00	50.00	83.60	88.00
		WEIGHTED AVERAGE FOR THE FOURTH QUARTER		32.00	50.00	83.60	88.00
		WEIGHTED AVERAGE FOR THE YEAR		32.00	50.00	83.60	88.00
===== 202-05300 Rem and Disposal of Paint LUMP SUM =====							
NH0504-911			04/07/22	1.00	45000.00	78000.00	150000.00
		WEIGHTED AVERAGE FOR THE SECOND QUARTER		1.00	45000.00	78000.00	150000.00
		WEIGHTED AVERAGE FOR THE YEAR		1.00	45000.00	51950.00	117375.00
===== 203-00000 Uncl Excav Cubic Yard =====							
STA0252-459			02/03/22	40.00	48.00	110.40	54.50
ER007A-035			03/15/22	49.00	268.35	149.75	149.75
STR092A-031			03/17/22	8,288.00	40.00	19.00	19.00
		WEIGHTED AVERAGE FOR THE FIRST QUARTER		8,377.00	41.37	21.05	19.93
NH0504-911			04/07/22	111.00	20.00	65.00	100.00
		WEIGHTED AVERAGE FOR THE SECOND QUARTER		111.00	20.00	65.00	100.00
FBR0761-236		I-76 OVER CLR CRK SCOUR MIT	08/25/22	303.00	30.00	140.67	65.00
		WEIGHTED AVERAGE FOR THE THIRD QUARTER		303.00	30.00	140.67	65.00
FSAM240-200		SH21B CO SPRINGS SIGNAL REPLA	10/27/22	110.00	80.00	211.25	150.00
STA0711-021		SH71: REGION LINE NORTH	12/01/22	153.00	40.00	82.33	55.00
STR114A-015		SH114 SILLSVILLE SOUTH TO MP3	12/01/22	9,181.00	40.00	57.50	65.00

COLORADO DEPARTMENT OF TRANSPORTATION
ITEM UNIT COSTS BY PROJECTS -- 2022 COST DATA

11:31 Wednesday, March 8, 2023 67

PROJECT NUMBER	ITEM NUMBER/ PROJECT LOCATION	ITEM DESCRIPTION/ PROJECT LOCATION	DATE LET	UNIT/ QUANTITY	ENGR. EST.	AVERAGE BID	AWARDED BID
===== 203-00000							
FSA0853-122	Uncl Excav	WCR14.5 AND US-85, FORT LUPTO	12/15/22	Cubic Yard	50.00	241.70	130.00
STA385A-016		SH 385 MP 97.76	12/22/22		10.00	64.75	50.00
WEIGHTED AVERAGE FOR THE FOURTH QUARTER				9,836.00	39.64	64.29	65.98
WEIGHTED AVERAGE FOR THE YEAR				18,627.00	40.15	54.52	45.46
===== 203-00010							
Uncl Excav (CIP) Cubic Yard =====							
NH0504-910		US50B L-24-B MIN REP AT MP 40	01/13/22	5,029.00	50.00	15.14	25.00
NHPP0702-383		I-70 EB AUX FRISCO TO SILVERT	01/13/22	27,784.00	22.00	27.60	14.50
NHPP0063-063			02/24/22	1,748.00	25.00	41.10	59.00
NHPP 0761-238		I-76 DAHLIA TO YORK	03/10/22	33,816.00	30.00	23.33	18.00
C0761-239							
WEIGHTED AVERAGE FOR THE FIRST QUARTER				68,377.00	28.09	24.05	18.14
NHPP0702-413		VAIL PASS AUX PHASE 1 CAP 2	04/18/22	45,687.00	20.99	20.99	20.99
2670703-479		I-70 BRIDGE OVER HARLAN	05/05/22	6,341.00	25.00	30.66	18.00
STA0712-019		SH 71: Frieight Improvements	05/12/22	41,564.00	40.00	17.07	17.07
STA001A-005		SH1 WELLINGTON SOUTH RESURFAC	05/12/22	100.00	20.00	61.50	38.00
NHC540-017		R2 CHAINUP STA @ KENOSHA/HOOS	05/12/22	28,977.00	32.00	32.17	32.50
FSA3921-019		SH 392 AND WCR 55 ISLANDS	06/02/22	94.00	60.00	70.67	28.00
FSA052A-046		SH52 WCR 37 INTERSECTION IMPR	06/09/22	14,437.00	20.00	26.67	18.75
WEIGHTED AVERAGE FOR THE SECOND QUARTER				137,200.00	29.18	26.63	21.88
NHPP0702-414		VAIL PASS AUX PHASE 1 CAP 3	07/08/22	146,165.00	25.41	25.41	25.41
FBR0702-423		VAIL PASS AUX BE F-12-AT PHAS					
FSA052A-057		SH52 BOX CULVERT EXTENSION (M	08/04/22	215.00	65.00	85.80	44.26
NHPP0063-054		US 6 FROM I70-B TO 33 RD. (MP	08/18/22	13,183.00	35.00	47.44	56.25
2670403-065		US40_FLOYD HILL ROUNDABOUTS	09/15/22	8,152.00	25.00	73.68	60.00
2670703-497		I-70 GENESEE WILDLIFE XING	09/15/22	22,221.00	35.00	27.77	11.96
SHE2873-193		US 287 & CO 52 INTERSECTION I	09/15/22	11,144.00	38.00	31.47	20.00
NHPP0701-231		I-70 SALT WASH BRIDGES SCOUR	09/29/22	2,850.00	40.00	70.83	51.00
WEIGHTED AVERAGE FOR THE THIRD QUARTER				203,930.00	27.99	32.06	27.40
STA207A-004		Resurfacing SH207A MANZANOLA	10/27/22	860.00	80.00	60.47	55.40

PROJECT NUMBER	ITEM NUMBER/ PROJECT LOCATION	ITEM DESCRIPTION/ PROJECT LOCATION	DATE LET	UNIT/ QUANTITY	ENGR. EST.	AVERAGE BID	AWARDED BID
=====	203-00010	Uncl Excav (CIP)		Cubic Yard	=====	=====	=====
NHPP0343-048		US 34 (MP 169.3-171.4)	11/01/22	297.00	40.00	88.22	90.00
STU0252-457		I-25:ALAMEDA RIVER PH 2.0	11/03/22	16,696.00	28.00	53.26	29.50
NHPP0853-126		US85C: PLATTEVILLE NORTH MP (11/10/22	1,332.00	30.00	29.70	24.40
C5502-097		US550 MP 117.28-126.06	11/17/22	32,317.00	30.00	23.07	22.10
STRC090-011		US 50B AND SH71/CR18 INTERSEC	11/17/22	1,371.00	62.00	37.95	29.90
2670703-487		I-70 BRIDGES OVER WARD ROAD-	12/01/22	4,007.00	20.00	27.94	23.00
IM025A-050		I25-MP103.9 - INTERSECTION DR	12/01/22	19,049.00	30.00	33.33	25.00
NHPP0931-033		SH93:US6 TO 58TH RESURFACING	12/15/22	2,994.00	50.00	47.14	34.80
NHPP0502-090		SH 50 MP 134.6-136 GUNNISON C	12/22/22	58,514.00	25.00	20.57	15.53
STA0361-129		US 36: HYGIENE RD AND NELSON	12/22/22	725.00	35.00	51.45	47.35
BR012A-048		CO 12 STRUCTURE P-17-F AT MP	12/22/22	7,097.00	50.00	35.95	40.00
STA385A-016		SH 385 MP 97.76	12/22/22	2,537.00	20.00	45.50	25.00
		WEIGHTED AVERAGE FOR THE FOURTH QUARTER		147,796.00	29.35	27.50	22.45
		WEIGHTED AVERAGE FOR THE YEAR		557,303.00	28.66	27.58	23.59
=====	203-00040	Uncl Excav (Spec)		Cubic Yard	=====	=====	=====
NHPP0702-413		VAIL PASS AUX PHASE 1 CAP 2	04/18/22	26,721.00	4.93	4.93	4.93
		WEIGHTED AVERAGE FOR THE SECOND QUARTER		26,721.00	4.93	4.93	4.93
NHPP0702-414		VAIL PASS AUX PHASE 1 CAP 3	07/08/22	800.00	46.38	46.38	46.38
FBR0702-423		VAIL PASS AUX BE F-12-AT PHAS					
		WEIGHTED AVERAGE FOR THE THIRD QUARTER		800.00	46.38	46.38	46.38
		WEIGHTED AVERAGE FOR THE YEAR		27,521.00	6.13	6.13	6.13
=====	203-00041	Uncl Excav (Spec)		Ton	=====	=====	=====
ER0702-420		PR I-70 GWC MATERIAL FLOWS 20	05/06/22	15,086.00	35.00	45.50	41.00
		WEIGHTED AVERAGE FOR THE SECOND QUARTER		15,086.00	35.00	45.50	41.00
		WEIGHTED AVERAGE FOR THE YEAR		15,086.00	35.00	45.50	41.00
=====	203-00050	Unsuitable Material		Cubic Yard	=====	=====	=====
STA0252-459			02/03/22	10.00	32.00	255.03	145.75

COLORADO DEPARTMENT OF TRANSPORTATION
 ITEM UNIT COSTS BY PROJECTS -- 2022 COST DATA

11:31 Wednesday, March 8, 2023 69

PROJECT NUMBER	ITEM NUMBER/ PROJECT LOCATION	ITEM DESCRIPTION/ PROJECT LOCATION	DATE LET	UNIT/ QUANTITY	ENGR. EST.	AVERAGE BID	AWARDED BID
=====	203-00050	Unsuitable Material		Cubic Yard	=====	=====	=====
NHPP 0761-238		I-76 DAHLIA TO YORK	03/10/22	725.00	100.00	47.96	22.00
C0761-239							
CR100-362			03/14/22	250.00	265.31	265.31	265.31
STR160A-034		US160A LA VETA PASS EAST SURF	03/17/22	323.00	40.00	46.63	49.25
		WEIGHTED AVERAGE FOR THE FIRST QUARTER		1,308.00	116.26	56.83	76.18
CC030-081		ADA RAMP AND CURBS - FT. LUPT	04/14/22	100.00	75.00	61.36	42.00
2670703-479		I-70 BRIDGE OVER HARLAN	05/05/22	200.00	75.00	50.63	22.55
STA0712-019		SH 71: Frieight Improvements	05/12/22	1,000.00	20.00	37.61	37.61
NHPP 3851-018		US 385 NORTH OF CHEYENNE WELL	05/26/22	2,500.00	30.00	17.50	16.00
FSA052A-046		SH52 WCR 37 INTERSECTION IMPR	06/09/22	1,000.00	35.00	40.82	10.00
		WEIGHTED AVERAGE FOR THE SECOND QUARTER		4,800.00	31.77	32.67	20.07
BR0343-046		US 34 TIMBER BRIDGE REPL. PKG	08/31/22	300.00	35.16	25.36	25.36
FBR0343-047		US 6/US 34 TIMBER BRIDGE REPL					
		WEIGHTED AVERAGE FOR THE THIRD QUARTER		300.00	35.16	25.36	25.36
TRG0253-264		I-25 AND SH 119 PARK-N-RIDE	10/27/22	200.00	100.00	78.46	63.00
NHPP0343-048		US 34 (MP 169.3-171.4)	11/01/22	148.00	48.00	65.36	90.00
STU0252-457		I-25:ALAMEDA RIVER PH 2.0	11/03/22	5,046.00	70.00	76.00	38.00
SHE0242-087		US 24 SAFETY IMPRVMENTS, E OF	11/03/22	50.00	20.00	95.36	134.09
C5502-097		US550 MP 117.28-126.06	11/17/22	150.00	80.00	167.47	86.90
STRC090-011		US 50B AND SH71/CR18 INTERSEC	11/17/22	220.00	21.00	34.55	35.60
STAM420-001		US 285 AT HWY 9C IMPROVEMENTS	12/01/22	1,020.00	13.04	45.16	36.60
BR2854-148		INTERSECTION OF US 285 & SH 9					
STM0091-046		ADA RAMP IMPROVEMENTS - FAIRP					
STA0711-021		SH71: REGION LINE NORTH	12/01/22	247.00	40.00	58.11	51.00
2670703-487		I-70 BRIDGES OVER WARD ROAD-	12/01/22	100.00	30.00	62.12	66.00
NHPP0701-252		I-70 RIFLE TO SILT SLAB REPLA	12/01/22	260.00	50.00	190.75	96.50
IM025A-050		I25-MP103.9 - INTERSECTION DR	12/01/22	100.00	50.00	83.33	65.00
NHPP0021-041		SH2 RESURFACING MLK TO 52ND	12/01/22	10.00	150.00	176.31	180.00
NHPP0931-033		SH93:US6 TO 58TH RESURFACING	12/15/22	100.00	150.00	68.21	76.90
NHPP0502-090		SH 50 MP 134.6-136 GUNNISON C	12/22/22	250.00	40.00	73.95	61.61
STA385A-016		SH 385 MP 97.76	12/22/22	500.00	40.00	106.00	100.00
		WEIGHTED AVERAGE FOR THE FOURTH QUARTER		8,401.00	58.16	75.92	48.60
		WEIGHTED AVERAGE FOR THE YEAR		14,809.00	54.27	61.58	41.31

COLORADO DEPARTMENT OF TRANSPORTATION
ITEM UNIT COSTS BY PROJECTS -- 2022 COST DATA

11:31 Wednesday, March 8, 2023 70

PROJECT NUMBER	ITEM NUMBER/ PROJECT LOCATION	ITEM DESCRIPTION/ PROJECT LOCATION	DATE LET	UNIT/ QUANTITY	ENGR. EST.	AVERAGE BID	AWARDED BID
===== 203-00060		Emb Matl (CIP)		Cubic Yard	=====		
NH0504-910		US50B L-24-B MIN REP AT MP 40	01/13/22	6,726.00	35.00	35.34	25.00
NHPP1601-083			02/03/22	48,171.00	18.00	27.82	26.00
STA0252-459			02/03/22	160.00	51.00	105.42	45.25
STR0141-031			02/17/22	770.00	80.00	57.67	61.00
NHM765-007			03/31/22	1,880.00	22.00	42.84	48.78
		WEIGHTED AVERAGE FOR THE FIRST QUARTER		57,707.00	21.03	31.58	27.15
STM1151-038		SH115 MP 27 TO MP 38	04/21/22	137,735.00	16.00	23.36	21.34
NHPP 3851-018		US 385 NORTH OF CHEYENNE WELL	05/26/22	25,833.00	25.00	17.46	7.00
		WEIGHTED AVERAGE FOR THE SECOND QUARTER		163,568.00	17.42	22.95	19.08
ER0502-092		US 50 MP 204 EB MONARCH TRUCK	08/29/22	680.00	75.00	45.64	26.93
BR0343-046		US 34 TIMBER BRIDGE REPL. PKG	08/31/22	4,305.00	75.10	78.16	78.16
FBR0343-047		US 6/US 34 TIMBER BRIDGE REPL					
		WEIGHTED AVERAGE FOR THE THIRD QUARTER		4,985.00	75.08	67.71	71.17
C170A-002		CRITICAL CULVERT CONST. PKG D	10/27/22	312.00	75.00	94.69	43.75
TRG0253-264		I-25 AND SH 119 PARK-N-RIDE	10/27/22	39,052.00	25.00	21.20	12.50
STA3852-015		US 385 HOLYOKE NORTH	10/27/22	56,428.00	28.00	34.00	34.00
SHE0242-087		US 24 SAFETY IMPRVMENTS, E OF	11/03/22	1,500.00	28.00	76.06	55.18
STR064A-010		SH 64 AND SH 13 AT MEEKER	11/10/22	880.00	16.00	87.50	85.00
STAM420-001		US 285 AT HWY 9C IMPROVEMENTS	12/01/22	23,899.00	10.00	29.56	27.00
BR2854-148		INTERSECTION OF US 285 & SH 9					
STM0091-046		ADA RAMP IMPROVEMENTS - FAIRP					
STA0711-021		SH71: REGION LINE NORTH	12/01/22	900.00	50.00	71.33	44.00
NHPP083A-046		SH83 RESURFACING STROH RD TO	12/08/22	2.00	100.00	2981.15	2562.30
NHPP0063-048		US6 / 20 ROAD INTERSECTION IM	12/15/22	4,942.00	70.00	45.09	48.00
BR012A-048		CO 12 STRUCTURE P-17-F AT MP	12/22/22	11,281.00	30.00	45.64	35.00
STA385A-016		SH 385 MP 97.76	12/22/22	4,896.00	30.00	64.00	50.00
STR096A-050		SH 96 MP 168.99 TO 193.77	12/22/22	506.00	40.00	133.67	66.00
		WEIGHTED AVERAGE FOR THE FOURTH QUARTER		144,598.00	26.08	32.12	30.79
		WEIGHTED AVERAGE FOR THE YEAR		370,858.00	22.13	28.22	26.37

PROJECT NUMBER	ITEM NUMBER/ PROJECT LOCATION	ITEM DESCRIPTION/ PROJECT LOCATION	DATE LET	UNIT/ QUANTITY	ENGR. EST.	AVERAGE BID	AWARDED BID
=====	203-00062	Emb Matl (CIP) (Spec)		Cubic Yard	=====		
NHPP 0761-238 C0761-239		I-76 DAHLIA TO YORK	03/10/22	24,521.00	24.00	24.37	19.75
		WEIGHTED AVERAGE FOR THE FIRST QUARTER		24,521.00	24.00	24.37	19.75
		WEIGHTED AVERAGE FOR THE YEAR		24,521.00	24.00	24.37	19.75
=====	203-00065	Emb Matl (CIP) (R20)		Cubic Yard	=====		
2670703-487		I-70 BRIDGES OVER WARD ROAD-	12/01/22	2,992.00	150.00	37.78	32.00
		WEIGHTED AVERAGE FOR THE FOURTH QUARTER		2,992.00	150.00	37.78	32.00
		WEIGHTED AVERAGE FOR THE YEAR		2,992.00	150.00	37.78	32.00
=====	203-00066	Emb Matl (CIP) (R40)		Cubic Yard	=====		
STA0712-019		SH 71: Frieght Improvements	05/12/22	20,092.00	30.00	37.42	37.42
STA001A-005		SH1 WELLINGTON SOUTH RESURFAC	05/12/22	78.00	20.00	74.60	62.00
NHPP 3851-018		US 385 NORTH OF CHEYENNE WELL	05/26/22	528.00	50.00	43.00	60.00
FSA3921-019		SH 392 AND WCR 55 ISLANDS	06/02/22	52.00	60.00	115.00	90.00
		WEIGHTED AVERAGE FOR THE SECOND QUARTER		20,750.00	30.55	38.53	38.22
FSA052A-057 SHE2873-193		SH52 BOX CULVERT EXTENSION (M	08/04/22	162.00	80.00	112.33	104.56
		US 287 & CO 52 INTERSECTION I	09/15/22	6,245.00	40.00	34.93	21.00
		WEIGHTED AVERAGE FOR THE THIRD QUARTER		6,407.00	41.01	35.92	23.11
TRG0253-264		I-25 AND SH 119 PARK-N-RIDE	10/27/22	8,771.00	25.00	36.69	29.00
STA3852-015		US 385 HOLYOKE NORTH	10/27/22	13,410.00	44.00	50.00	50.00
NHPP0853-126		US85C: PLATTEVILLE NORTH MP (11/10/22	1,286.00	45.00	39.58	28.20
STA0711-021		SH71: REGION LINE NORTH	12/01/22	185.00	25.00	85.47	50.00
STA0361-129		US 36: HYGIENE RD AND NELSON	12/22/22	715.00	60.00	65.45	49.82
		WEIGHTED AVERAGE FOR THE FOURTH QUARTER		24,367.00	37.54	40.16	41.29
		WEIGHTED AVERAGE FOR THE YEAR		51,524.00	35.15	38.89	37.79

PROJECT NUMBER	ITEM NUMBER/ PROJECT LOCATION	ITEM DESCRIPTION/ PROJECT LOCATION	DATE LET	UNIT/ QUANTITY	ENGR. EST.	AVERAGE BID	AWARDED BID
=====	203-00100	Muck Excav		Cubic Yard	=====		
NHPP1601-083			02/03/22	500.00	36.00	55.03	40.00
		WEIGHTED AVERAGE FOR THE FIRST QUARTER		500.00	36.00	55.03	40.00
ER0502-092		US 50 MP 204 EB MONARCH TRUCK	08/29/22	20.00	100.00	186.88	190.64
		WEIGHTED AVERAGE FOR THE THIRD QUARTER		20.00	100.00	186.88	190.64
		WEIGHTED AVERAGE FOR THE YEAR		520.00	38.46	62.49	45.79
=====	203-00400	Rock Excav		Cubic Yard	=====		
FBR0761-236		I-76 OVER CLR CRK SCOUR MIT	08/25/22	855.00	180.00	195.92	125.00
ER0502-092		US 50 MP 204 EB MONARCH TRUCK	08/29/22	20.00	275.00	269.01	232.03
NHPPR100-266		R1 ESSENTIAL REPAIRS	09/01/22	40.00	50.00	459.57	852.71
2670403-065		US40_FLOYD HILL ROUNDABOUTS	09/15/22	659.00	200.00	169.15	78.00
		WEIGHTED AVERAGE FOR THE THIRD QUARTER		1,574.00	186.28	192.34	125.18
SHE0242-087		US 24 SAFETY IMPRVMTS, E OF	11/03/22	4,801.00	80.00	88.02	88.55
		WEIGHTED AVERAGE FOR THE FOURTH QUARTER		4,801.00	80.00	88.02	88.55
		WEIGHTED AVERAGE FOR THE YEAR		6,375.00	106.24	113.77	97.59
=====	203-00440	Rock Excav (Spec)		Cubic Yard	=====		
NHPP0702-413		VAIL PASS AUX PHASE 1 CAP 2	04/18/22	7,197.00	25.52	25.52	25.52
		WEIGHTED AVERAGE FOR THE SECOND QUARTER		7,197.00	25.52	25.52	25.52
		WEIGHTED AVERAGE FOR THE YEAR		7,197.00	25.52	25.52	25.52
=====	203-00450	Rem Rock		Each	=====		
STM1151-038		SH115 MP 27 TO MP 38	04/21/22	19.00	105.00	840.46	77.74
		WEIGHTED AVERAGE FOR THE SECOND QUARTER		19.00	105.00	840.46	77.74
		WEIGHTED AVERAGE FOR THE YEAR		19.00	105.00	840.46	77.74

COLORADO DEPARTMENT OF TRANSPORTATION
ITEM UNIT COSTS BY PROJECTS -- 2022 COST DATA

11:31 Wednesday, March 8, 2023 73

PROJECT NUMBER	ITEM NUMBER/ PROJECT LOCATION	ITEM DESCRIPTION/ PROJECT LOCATION	DATE LET	UNIT/ QUANTITY	ENGR. EST.	AVERAGE BID	AWARDED BID
=====	203-00710	Clay Plating (CIP)		Cubic Yard	=====		
NHPP0702-414 FBR0702-423		VAIL PASS AUX PHASE 1 CAP 3 VAIL PASS AUX BE F-12-AT PHAS	07/08/22	50.00	463.85	463.85	463.85
		WEIGHTED AVERAGE FOR THE THIRD QUARTER		50.00	463.85	463.85	463.85
		WEIGHTED AVERAGE FOR THE YEAR		50.00	463.85	463.85	463.85
=====	203-00850	Polystyrene Fill (CIP)		Cubic Yard	=====		
STAR100-358		3 STRUCTURES IN REGION 1 METR	05/26/22	8.59	300.00	1864.02	1300.00
		WEIGHTED AVERAGE FOR THE SECOND QUARTER		8.59	300.00	1864.02	1300.00
		WEIGHTED AVERAGE FOR THE YEAR		8.59	300.00	1864.02	1300.00
=====	203-01100	Proof Rolling		Hour	=====		
NHPP0702-383 NHPP 0761-238 C0761-239 ER007A-035 NHM765-007		I-70 EB AUX FRISCO TO SILVERT I-76 DAHLIA TO YORK	01/13/22 03/10/22	40.00 750.00	125.00 140.00	204.23 119.41	245.00 110.00
			03/15/22	25.00	234.05	242.73	242.73
			03/31/22	40.00	100.00	144.54	100.00
		WEIGHTED AVERAGE FOR THE FIRST QUARTER		855.00	140.18	123.04	119.73
STM1151-038 2670703-479 NHC540-017 FSA052A-046		SH115 MP 27 TO MP 38 I-70 BRIDGE OVER HARLAN R2 CHAINUP STA @ KENOSHA/HOOS SH52 WCR 37 INTERSECTION IMPR	04/21/22 05/05/22 05/12/22 06/09/22	80.00 40.00 40.00 40.00	155.00 170.00 130.00 150.00	147.33 157.95 133.33 159.40	110.00 209.04 100.00 125.00
		WEIGHTED AVERAGE FOR THE SECOND QUARTER		200.00	152.00	150.75	130.81
SHE2873-193		US 287 & CO 52 INTERSECTION I	09/15/22	20.00	120.00	143.12	250.00
		WEIGHTED AVERAGE FOR THE THIRD QUARTER		20.00	120.00	143.12	250.00
STU0252-457		I-25:ALAMEDA RIVER PH 2.0	11/03/22	50.00	100.00	241.39	269.00

COLORADO DEPARTMENT OF TRANSPORTATION
 ITEM UNIT COSTS BY PROJECTS -- 2022 COST DATA

11:31 Wednesday, March 8, 2023 74

PROJECT NUMBER	ITEM NUMBER/ PROJECT LOCATION	ITEM DESCRIPTION/ PROJECT LOCATION	DATE LET	UNIT/ QUANTITY	ENGR. EST.	AVERAGE BID	AWARDED BID
===== 203-01100 Proof Rolling Hour =====							
2670703-487		I-70 BRIDGES OVER WARD ROAD-	12/01/22	10.00	250.00	146.68	99.00
STA385A-016		SH 385 MP 97.76	12/22/22	10.00	100.00	213.00	125.00
	WEIGHTED AVERAGE FOR THE FOURTH QUARTER			70.00	121.43	216.93	224.14
	WEIGHTED AVERAGE FOR THE YEAR			1,145.00	140.74	129.76	130.32
===== 203-01140 Rolling Hour =====							
NHPP1601-083			02/03/22	20.00	150.00	276.06	110.00
	WEIGHTED AVERAGE FOR THE FIRST QUARTER			20.00	150.00	276.06	110.00
	WEIGHTED AVERAGE FOR THE YEAR			20.00	150.00	276.06	110.00
===== 203-01500 Blading Hour =====							
NHPP0702-383		I-70 EB AUX FRISCO TO SILVERT	01/13/22	140.00	150.00	221.00	255.00
NHPP1601-083			02/03/22	20.00	160.00	283.02	130.00
STA0252-459			02/03/22	15.00	150.00	278.48	290.00
STR0141-031			02/17/22	40.00	200.00	145.00	175.00
NHPP0063-063			02/24/22	20.00	140.00	155.00	160.00
NHPP 0761-238		I-76 DAHLIA TO YORK	03/10/22	30.00	150.00	175.25	130.00
C0761-239							
ER007A-035			03/15/22	10.00	170.83	182.79	182.79
STR092A-031			03/17/22	40.00	160.00	125.00	125.00
NHM765-007			03/31/22	30.00	150.00	188.00	110.00
	WEIGHTED AVERAGE FOR THE FIRST QUARTER			345.00	157.56	202.24	193.85
NH0504-911			04/07/22	150.00	175.00	162.65	155.30
NHPP0702-413		VAIL PASS AUX PHASE 1 CAP 2	04/18/22	35.00	277.93	277.93	277.93
STM1151-038		SH115 MP 27 TO MP 38	04/21/22	200.00	150.00	202.59	140.00
2670703-479		I-70 BRIDGE OVER HARLAN	05/05/22	20.00	155.00	207.39	233.16
STA0712-019		SH 71: Frieght Improvements	05/12/22	40.00	150.00	164.01	164.01
NHC540-017		R2 CHAINUP STA @ KENOSHA/HOOS	05/12/22	30.00	150.00	160.00	160.00
CM760-047		COLFAX AND QUAIL	05/12/22	1.00	175.00	397.40	132.00
NHPP 3851-018		US 385 NORTH OF CHEYENNE WELL	05/26/22	20.00	150.00	140.00	120.00
FSA052A-046		SH52 WCR 37 INTERSECTION IMPR	06/09/22	40.00	190.00	172.00	135.00
	WEIGHTED AVERAGE FOR THE SECOND QUARTER			536.00	168.57	190.68	158.54

PROJECT NUMBER	ITEM NUMBER/ PROJECT LOCATION	ITEM DESCRIPTION/ PROJECT LOCATION	DATE LET	UNIT/ QUANTITY	ENGR. EST.	AVERAGE BID	AWARDED BID
===== 203-01500		Blading		Hour	=====	=====	=====
NHPP0702-414		VAIL PASS AUX PHASE 1 CAP 3	07/08/22	55.00	283.34	283.34	283.34
FBR0702-423		VAIL PASS AUX BE F-12-AT PHAS					
STR0711-022		SH 71 OVER THE ARKANSAS	08/04/22	30.00	159.00	188.33	115.00
NHPP0063-054		US 6 FROM I70-B TO 33 RD. (MP	08/18/22	100.00	140.00	192.26	125.00
C1211-099		SH 121 NORTH SGA SIGNALS	08/25/22	16.00	200.00	300.00	400.00
BR0343-046		US 34 TIMBER BRIDGE REPL. PKG	08/31/22	72.00	205.16	226.10	226.10
FBR0343-047		US 6/US 34 TIMBER BRIDGE REPL					
NHPPR100-266		R1 ESSENTIAL REPAIRS	09/01/22	10.00	120.00	266.09	232.27
2670403-065		US40 FLOYD HILL ROUNDABOUTS	09/15/22	40.00	300.00	186.59	168.00
2670703-497		I-70_GENESEE WILDLIFE KING	09/15/22	40.00	300.00	179.32	161.29
SHE2873-193		US 287 & CO 52 INTERSECTION I	09/15/22	20.00	150.00	183.94	125.00
NHPP0701-231		I-70 SALT WASH BRIDGES SCOUR	09/29/22	40.00	180.00	124.16	20.00
		WEIGHTED AVERAGE FOR THE THIRD QUARTER		423.00	207.39	194.12	172.59
NHPP0701-253		I-70 EAST OF DEBEQUE	10/27/22	10.00	150.00	139.00	126.00
STA207A-004		Resurfacing SH207A MANZANOLA	10/27/22	100.00	150.00	149.57	183.70
TRG0253-264		I-25 AND SH 119 PARK-N-RIDE	10/27/22	240.00	150.00	187.24	130.00
STA3852-015		US 385 HOLYOKE NORTH	10/27/22	50.00	150.00	155.00	155.00
NHPP0343-048		US 34 (MP 169.3-171.4)	11/01/22	55.00	150.00	190.59	170.00
STU0252-457		I-25:ALAMEDA RIVER PH 2.0	11/03/22	200.00	200.00	263.73	275.00
SHE0242-087		US 24 SAFETY IMPRVMENTS, E OF	11/03/22	80.00	150.00	188.27	284.81
STR064A-010		SH 64 AND SH 13 AT MEEKER	11/10/22	20.00	180.00	142.50	125.00
NHPP0853-126		US85C: PLATTEVILLE NORTH MP (11/10/22	40.00	150.00	201.36	248.80
C5502-097		US550 MP 117.28-126.06	11/17/22	60.00	180.00	261.10	280.00
STAM420-001		US 285 AT HWY 9C IMPROVEMENTS	12/01/22	80.00	150.00	198.72	300.87
BR2854-148		INTERSECTION OF US 285 & SH 9					
STM0091-046		ADA RAMP IMPROVEMENTS - FAIRP					
STA0711-021		SH71: REGION LINE NORTH	12/01/22	6.00	150.00	162.67	130.00
STR114A-015		SH114 SILLSVILLE SOUTH TO MP3	12/01/22	80.00	180.00	127.50	130.00
2670703-487		I-70 BRIDGES OVER WARD ROAD-	12/01/22	40.00	300.00	202.92	180.00
NHPP0701-252		I-70 RIFLE TO SILT SLAB REPLA	12/01/22	20.00	150.00	192.50	100.00
IM025A-050		I25-MP103.9 - INTERSECTION DR	12/01/22	40.00	145.00	178.33	210.00
STR318A-001		SH 318 MP 0 - 12.5 MOFFAT COU	12/01/22	40.00	170.00	143.00	160.00
NHPP083A-046		SH83 RESURFACING STROH RD TO	12/08/22	8.00	160.00	311.68	200.35
NHPP0931-033		SH93:US6 TO 58TH RESURFACING	12/15/22	20.00	150.00	198.52	179.40
NHPP0502-090		SH 50 MP 134.6-136 GUNNISON C	12/22/22	20.00	180.00	209.80	244.54
BR012A-048		CO 12 STRUCTURE P-17-F AT MP	12/22/22	40.00	140.00	201.41	190.00
STA385A-016		SH 385 MP 97.76	12/22/22	50.00	150.00	244.50	150.00
		WEIGHTED AVERAGE FOR THE FOURTH QUARTER		1,299.00	166.69	199.26	198.36
		WEIGHTED AVERAGE FOR THE YEAR		2,603.00	172.48	197.46	185.57

COLORADO DEPARTMENT OF TRANSPORTATION
ITEM UNIT COSTS BY PROJECTS -- 2022 COST DATA

11:31 Wednesday, March 8, 2023 76

PROJECT NUMBER	ITEM NUMBER/ PROJECT LOCATION	ITEM DESCRIPTION/ PROJECT LOCATION	DATE LET	UNIT/ QUANTITY	ENGR. EST.	AVERAGE BID	AWARDED BID
===== 203-01510 Backhoe Hour =====							
NHPP0702-383		I-70 EB AUX FRISCO TO SILVERT	01/13/22	80.00	150.00	178.68	230.00
NHPP1601-083			02/03/22	20.00	200.00	327.13	200.00
NHPP0063-063			02/24/22	20.00	200.00	155.00	160.00
CR100-362			03/14/22	50.00	138.33	138.33	138.33
STR092A-031			03/17/22	30.00	150.00	113.00	113.00
WEIGHTED AVERAGE FOR THE FIRST QUARTER				200.00	157.08	180.47	179.53
NHPP0702-413		VAIL PASS AUX PHASE 1 CAP 2	04/18/22	20.00	274.20	274.20	274.20
STM1151-038		SH115 MP 27 TO MP 38	04/21/22	80.00	140.00	180.76	130.00
FSA0702-409		I-70 VAIL WILDLIFE FENCE PHAS	05/26/22	40.00	180.00	60.00	60.00
WEIGHTED AVERAGE FOR THE SECOND QUARTER				140.00	170.60	174.32	130.60
NHPP0702-414		VAIL PASS AUX PHASE 1 CAP 3	07/08/22	20.00	188.55	188.55	188.55
FBR0702-423		VAIL PASS AUX BE F-12-AT PHAS					
ER0502-092		US 50 MP 204 EB MONARCH TRUCK	08/29/22	20.00	200.00	159.49	103.47
2670703-497		I-70 GENESEE WILDLIFE XING	09/15/22	60.00	150.00	169.95	144.52
NHPP0701-231		I-70 SALT WASH BRIDGES SCOUR	09/29/22	40.00	180.00	61.40	20.00
WEIGHTED AVERAGE FOR THE THIRD QUARTER				140.00	171.22	154.54	109.37
C5502-097		US550 MP 117.28-126.06	11/17/22	60.00	200.00	154.64	165.00
STR114A-015		SH114 SILLSVILLE SOUTH TO MP3	12/01/22	40.00	200.00	132.50	140.00
2670703-487		I-70 BRIDGES OVER WARD ROAD-	12/01/22	20.00	200.00	207.48	150.00
STR318A-001		SH 318 MP 0 - 12.5 MOFFAT COU	12/01/22	40.00	200.00	123.25	125.00
WEIGHTED AVERAGE FOR THE FOURTH QUARTER				160.00	200.00	156.92	146.88
WEIGHTED AVERAGE FOR THE YEAR				640.00	173.86	166.63	145.32
===== 203-01549 Pump Hour =====							
NHPP0702-413		VAIL PASS AUX PHASE 1 CAP 2	04/18/22	100.00	107.27	107.27	107.27
WEIGHTED AVERAGE FOR THE SECOND QUARTER				100.00	107.27	107.27	107.27

COLORADO DEPARTMENT OF TRANSPORTATION
ITEM UNIT COSTS BY PROJECTS -- 2022 COST DATA

11:31 Wednesday, March 8, 2023 77

PROJECT NUMBER	ITEM NUMBER/ PROJECT LOCATION	ITEM DESCRIPTION/ PROJECT LOCATION	DATE LET	UNIT/ QUANTITY	ENGR. EST.	AVERAGE BID	AWARDED BID
=====	203-01549	Pump		Hour	=====	=====	=====
NHPP0702-414		VAIL PASS AUX PHASE 1 CAP 3	07/08/22	100.00	182.99	182.99	182.99
FBR0702-423		VAIL PASS AUX BE F-12-AT PHAS					
		WEIGHTED AVERAGE FOR THE THIRD QUARTER		100.00	182.99	182.99	182.99
		WEIGHTED AVERAGE FOR THE YEAR		200.00	145.13	145.13	145.13
=====	203-01550	Dozing		Hour	=====	=====	=====
NHPP0702-383		I-70 EB AUX FRISCO TO SILVERT	01/13/22	80.00	150.00	214.07	260.00
STR0141-031			02/17/22	40.00	185.00	137.00	131.00
NHPP0063-063			02/24/22	20.00	160.00	180.00	180.00
NHPP 0761-238		I-76 DAHLIA TO YORK	03/10/22	30.00	160.00	180.89	135.00
C0761-239							
		WEIGHTED AVERAGE FOR THE FIRST QUARTER		170.00	161.18	190.85	198.18
NHPP0702-413		VAIL PASS AUX PHASE 1 CAP 2	04/18/22	45.00	263.97	263.97	263.97
2670703-479		I-70 BRIDGE OVER HARLAN	05/05/22	20.00	170.00	211.12	248.64
STA0712-019		SH 71: Frieight Improvements	05/12/22	20.00	175.00	184.11	184.11
NHC540-017		R2 CHAINUP STA @ KENOSHA/HOOS	05/12/22	30.00	175.00	156.67	150.00
FSA0702-409		I-70 VAIL WILDLIFE FENCE PHAS	05/26/22	40.00	200.00	30.00	30.00
		WEIGHTED AVERAGE FOR THE SECOND QUARTER		155.00	206.64	178.40	169.25
NHPP0702-414		VAIL PASS AUX PHASE 1 CAP 3	07/08/22	165.00	90.26	90.26	90.26
FBR0702-423		VAIL PASS AUX BE F-12-AT PHAS					
NHPP0063-054		US 6 FROM I70-B TO 33 RD. (MP	08/18/22	100.00	150.00	211.11	130.00
NHPPR100-266		R1 ESSENTIAL REPAIRS	09/01/22	10.00	130.00	306.07	198.20
2670703-497		I-70_GENESEE WILDLIFE XING	09/15/22	80.00	180.00	186.87	124.12
NHPP0701-231		I-70 SALT WASH BRIDGES SCOUR	09/29/22	40.00	200.00	107.99	20.00
		WEIGHTED AVERAGE FOR THE THIRD QUARTER		395.00	135.68	173.51	102.80
C5502-097		US550 MP 117.28-126.06	11/17/22	60.00	200.00	197.51	175.00

COLORADO DEPARTMENT OF TRANSPORTATION
ITEM UNIT COSTS BY PROJECTS -- 2022 COST DATA

11:31 Wednesday, March 8, 2023 78

PROJECT NUMBER	ITEM NUMBER/ PROJECT LOCATION	ITEM DESCRIPTION/ PROJECT LOCATION	DATE LET	UNIT/ QUANTITY	ENGR. EST.	AVERAGE BID	AWARDED BID
===== 203-01550 Dozing Hour =====							
STAM420-001		US 285 AT HWY 9C IMPROVEMENTS	12/01/22	80.00	175.00	181.10	321.38
BR2854-148		INTERSECTION OF US 285 & SH 9					
STM0091-046		ADA RAMP IMPROVEMENTS - FAIRP					
2670703-487		I-70 BRIDGES OVER WARD ROAD-	12/01/22	40.00	325.00	212.12	180.00
IM025A-050		I25-MP103.9 - INTERSECTION DR	12/01/22	40.00	180.00	156.67	180.00
NHPP0063-048		US6 / 20 ROAD INTERSECTION IM	12/15/22	20.00	200.00	187.61	160.00
NHPP0931-033		SH93:US6 TO 58TH RESURFACING	12/15/22	20.00	170.00	235.13	256.00
NHPP0502-090		SH 50 MP 134.6-136 GUNNISON C	12/22/22	20.00	200.00	238.11	272.65
BR012A-048		CO 12 STRUCTURE P-17-F AT MP	12/22/22	40.00	140.00	196.34	190.00
	WEIGHTED AVERAGE FOR THE FOURTH QUARTER			320.00	197.50	196.60	217.18
	WEIGHTED AVERAGE FOR THE YEAR			1,040.00	169.44	186.73	165.47
===== 203-01565 Hydraulic Excavator Hour =====							
NHPP0702-413		VAIL PASS AUX PHASE 1 CAP 2	04/18/22	400.00	349.32	349.32	349.32
ER0702-420		PR I-70 GWC MATERIAL FLOWS 20	05/06/22	60.00	240.00	229.50	229.00
	WEIGHTED AVERAGE FOR THE SECOND QUARTER			460.00	335.06	321.67	333.63
NHPP0702-414		VAIL PASS AUX PHASE 1 CAP 3	07/08/22	400.00	359.21	359.21	359.21
FBR0702-423		VAIL PASS AUX BE F-12-AT PHAS					
	WEIGHTED AVERAGE FOR THE THIRD QUARTER			400.00	359.21	359.21	359.21
	WEIGHTED AVERAGE FOR THE YEAR			860.00	346.29	337.99	345.53
===== 203-01582 Truck (Dump) Hour =====							
NHPP1601-083			02/03/22	10.00	150.00	404.51	110.00
STA 067A-048		Hwy 67A MP 0.00 TO MP 11.05 I	03/03/22	20.00	120.00	103.75	90.00
STR092A-031			03/17/22	20.00	160.00	141.00	141.00
	WEIGHTED AVERAGE FOR THE FIRST QUARTER			50.00	142.00	171.35	114.40
NHPP0702-413		VAIL PASS AUX PHASE 1 CAP 2	04/18/22	35.00	154.08	154.08	154.08
FSA0702-409		I-70 VAIL WILDLIFE FENCE PHAS	05/26/22	40.00	100.00	90.00	90.00
	WEIGHTED AVERAGE FOR THE SECOND QUARTER			75.00	125.24	119.90	119.90

COLORADO DEPARTMENT OF TRANSPORTATION
ITEM UNIT COSTS BY PROJECTS -- 2022 COST DATA

11:31 Wednesday, March 8, 2023 79

PROJECT NUMBER	ITEM NUMBER/ PROJECT LOCATION	ITEM DESCRIPTION/ PROJECT LOCATION	DATE LET	UNIT/ QUANTITY	ENGR. EST.	AVERAGE BID	AWARDED BID
===== 203-01582 Truck (Dump) Hour =====							
NHPP0702-414		VAIL PASS AUX PHASE 1 CAP 3	07/08/22	35.00	180.02	180.02	180.02
FBR0702-423		VAIL PASS AUX BE F-12-AT PHAS					
ER0502-092		US 50 MP 204 EB MONARCH TRUCK	08/29/22	20.00	200.00	128.62	130.87
NHPP0701-231		I-70 SALT WASH BRIDGES SCOUR	09/29/22	40.00	110.00	85.40	20.00
WEIGHTED AVERAGE FOR THE THIRD QUARTER				95.00	154.74	119.14	102.30
STR064A-010		SH 64 AND SH 13 AT MEEKER	11/10/22	20.00	150.00	137.00	114.00
STR114A-015		SH114 SILLSVILLE SOUTH TO MP3	12/01/22	10.00	160.00	112.50	100.00
NHPP0701-252		I-70 RIFLE TO SILT SLAB REPLA	12/01/22	20.00	132.00	180.00	90.00
STR318A-001		SH 318 MP 0 - 12.5 MOFFAT COU	12/01/22	40.00	150.00	141.25	160.00
WEIGHTED AVERAGE FOR THE FOURTH QUARTER				90.00	147.11	145.72	127.56
WEIGHTED AVERAGE FOR THE YEAR				310.00	143.33	138.13	115.84
===== 203-01590 Front End Loader (Rubber) Hour =====							
STA 067A-048		Hwy 67A MP 0.00 TO MP 11.05 I	03/03/22	30.00	150.00	133.27	130.00
WEIGHTED AVERAGE FOR THE FIRST QUARTER				30.00	150.00	133.27	130.00
NHPP0702-413		VAIL PASS AUX PHASE 1 CAP 2	04/18/22	75.00	179.12	179.12	179.12
STM1151-038		SH115 MP 27 TO MP 38	04/21/22	80.00	145.00	168.58	140.00
WEIGHTED AVERAGE FOR THE SECOND QUARTER				155.00	161.51	170.25	158.93
NHPP0702-414		VAIL PASS AUX PHASE 1 CAP 3	07/08/22	200.00	69.08	69.08	69.08
FBR0702-423		VAIL PASS AUX BE F-12-AT PHAS					
NHPP0701-231		I-70 SALT WASH BRIDGES SCOUR	09/29/22	40.00	150.00	67.77	20.00
WEIGHTED AVERAGE FOR THE THIRD QUARTER				240.00	82.57	68.70	60.90
C5502-097		US550 MP 117.28-126.06	11/17/22	96.00	200.00	226.67	255.00
WEIGHTED AVERAGE FOR THE FOURTH QUARTER				96.00	200.00	226.67	255.00
WEIGHTED AVERAGE FOR THE YEAR				521.00	131.57	156.56	129.81

COLORADO DEPARTMENT OF TRANSPORTATION
ITEM UNIT COSTS BY PROJECTS -- 2022 COST DATA

11:31 Wednesday, March 8, 2023 80

PROJECT NUMBER	ITEM NUMBER/ PROJECT LOCATION	ITEM DESCRIPTION/ PROJECT LOCATION	DATE LET	UNIT/ QUANTITY	ENGR. EST.	AVERAGE BID	AWARDED BID
===== 203-01594		Combination Loader		Hour =====			
NHPP0702-383		I-70 EB AUX FRISCO TO SILVERT	01/13/22	80.00	150.00	184.02	157.00
NHPP1601-083			02/03/22	20.00	150.00	287.13	120.00
C0762-055			02/17/22	10.00	160.00	112.07	90.00
NHPP0063-063			02/24/22	20.00	140.00	145.00	140.00
NHPP 0761-238		I-76 DAHLIA TO YORK	03/10/22	30.00	150.00	132.71	100.00
C0761-239							
ER007A-035			03/15/22	10.00	145.08	155.24	155.24
STR R500-171		Various locations on SH 141 a	03/17/22	15.00	200.00	132.56	10.00
		WEIGHTED AVERAGE FOR THE FIRST QUARTER		185.00	153.25	165.33	126.28
NHC540-017		R2 CHAINUP STA @ KENOSHA/HOOS	05/12/22	30.00	130.00	138.33	115.00
FSA0702-409		I-70 VAIL WILDLIFE FENCE PHAS	05/26/22	40.00	200.00	30.00	30.00
NHPP072A-047		SH-72 RESURFACING: I-70 TO IN	06/09/22	20.00	150.00	210.51	210.51
		WEIGHTED AVERAGE FOR THE SECOND QUARTER		90.00	165.56	119.07	98.45
NHPP0063-054		US 6 FROM I70-B TO 33 RD. (MP	08/18/22	100.00	150.00	125.85	125.00
ER0502-092		US 50 MP 204 EB MONARCH TRUCK	08/29/22	20.00	200.00	123.63	115.90
2670703-497		I-70 GENESEE WILDLIFE KING	09/15/22	80.00	120.00	184.99	141.71
SHE2873-193		US 287 & CO 52 INTERSECTION I	09/15/22	20.00	130.00	157.88	110.00
		WEIGHTED AVERAGE FOR THE THIRD QUARTER		220.00	141.82	165.03	128.89
C170A-002		CRITICAL CULVERT CONST. PKG D	10/27/22	24.00	140.00	171.88	112.50
STA3852-015		US 385 HOLYOKE NORTH	10/27/22	50.00	160.00	155.00	155.00
STU0252-457		I-25:ALAMEDA RIVER PH 2.0	11/03/22	200.00	200.00	235.25	174.00
STR064A-010		SH 64 AND SH 13 AT MEEKER	11/10/22	20.00	150.00	140.50	121.00
STAM420-001		US 285 AT HWY 9C IMPROVEMENTS	12/01/22	80.00	130.00	178.27	308.06
BR2854-148		INTERSECTION OF US 285 & SH 9					
STM0091-046		ADA RAMP IMPROVEMENTS - FAIRP					
2670703-487		I-70 BRIDGES OVER WARD ROAD-	12/01/22	20.00	100.00	188.60	150.00
NHPP0701-252		I-70 RIFLE TO SILT SLAB REPLA	12/01/22	20.00	157.00	370.00	90.00
IM025A-050		I25-MP103.9 - INTERSECTION DR	12/01/22	40.00	130.00	143.67	150.00
NHPP0063-048		US6 / 20 ROAD INTERSECTION IM	12/15/22	20.00	150.00	127.18	119.00
NHPP0931-033		SH93:US6 TO 58TH RESURFACING	12/15/22	20.00	140.00	183.72	205.00
STR0092-024		SH 9 North of Silverthorne	12/22/22	50.00	150.00	139.50	160.00
		WEIGHTED AVERAGE FOR THE FOURTH QUARTER		544.00	162.50	195.12	177.73
		WEIGHTED AVERAGE FOR THE YEAR		1,039.00	156.74	177.79	152.34

PROJECT NUMBER	ITEM NUMBER/ PROJECT LOCATION	ITEM DESCRIPTION/ PROJECT LOCATION	DATE LET	UNIT/ QUANTITY	ENGR. EST.	AVERAGE BID	AWARDED BID
=====	203-01597	Potholing		Hour =====			
ITS0703-477		ITS EQUIPMENT UPGRADE AT EJMT	01/06/22	10.00	250.00	665.00	665.00
MTCE R500-218			01/06/22	8.00	300.00	250.00	50.00
NHPP2873-189		US 287 (FEDERAL BLVD) - COLFA	01/06/22	120.00	260.00	316.48	215.09
NHPP0702-383		I-70 EB AUX FRISCO TO SILVERT	01/13/22	80.00	350.00	387.65	395.00
NHPP1601-083			02/03/22	10.00	350.00	620.37	350.00
STA0252-459			02/03/22	600.00	250.00	311.67	380.00
STR0141-031			02/17/22	20.00	400.00	359.78	289.34
NHPP0063-063			02/24/22	100.00	250.00	282.50	215.00
STA 067A-048		Hwy 67A MP 0.00 TO MP 11.05 I	03/03/22	20.00	200.00	296.63	300.00
NHPP 0761-238		I-76 DAHLIA TO YORK	03/10/22	750.00	280.00	252.17	185.00
C0761-239							
NHPP0703-472			03/10/22	30.00	280.00	322.73	250.00
CR100-362			03/14/22	200.00	278.92	278.92	278.92
STR R500-171		Various locations on SH 141 a	03/17/22	20.00	330.00	336.23	350.00
M R100-351		FY22 R1 SIGN STRUCTURE REPLAC	03/17/22	50.00	400.00	417.00	439.00
STR092A-031			03/17/22	50.00	350.00	500.00	500.00
NHM765-007			03/31/22	120.00	220.00	412.24	456.00
WEIGHTED AVERAGE FOR THE FIRST QUARTER				2,188.00	273.90	284.79	292.48
NH0504-911			04/07/22	200.00	250.00	353.50	307.00
CC030-081		ADA RAMP AND CURBS - FT. LUPT	04/14/22	40.00	250.00	261.13	50.00
NHPP0702-413		VAIL PASS AUX PHASE 1 CAP 2	04/18/22	100.00	616.94	616.94	616.94
STM1151-038		SH115 MP 27 TO MP 38	04/21/22	100.00	275.00	353.93	370.00
2670703-479		I-70 BRIDGE OVER HARLAN	05/05/22	100.00	260.00	282.03	322.98
ER0702-420		PR I-70 GWC MATERIAL FLOWS 20	05/06/22	80.00	275.00	425.00	350.00
STA0712-019		SH 71: Frieght Improvements	05/12/22	100.00	100.00	297.19	297.19
CM760-047		COLFAX AND QUAIL	05/12/22	100.00	235.00	348.20	276.00
FSA0702-409		I-70 VAIL WILDLIFE FENCE PHAS	05/26/22	100.00	350.00	425.00	425.00
ITS 0741-024		VMS SIGN INSTALLATIONS AND VS	06/02/22	120.00	220.00	187.50	275.00
NHPP072A-047		SH-72 RESURFACING: I-70 TO IN	06/09/22	150.00	350.00	207.67	207.67
FSA052A-046		SH52 WCR 37 INTERSECTION IMPR	06/09/22	40.00	300.00	270.20	250.00
MTCE0253-291		I-25 SIGN REPLACEMENT PHASE 2	06/16/22	80.00	350.00	283.50	202.00
WEIGHTED AVERAGE FOR THE SECOND QUARTER				1,310.00	293.58	321.47	314.90
NHPP0702-414		VAIL PASS AUX PHASE 1 CAP 3	07/08/22	100.00	636.41	636.41	636.41
FBR0702-423		VAIL PASS AUX BE F-12-AT PHAS					
FSA052A-057		SH52 BOX CULVERT EXTENSION (M	08/04/22	4.00	500.00	498.69	267.80
STR0711-022		SH 71 OVER THE ARKANSAS	08/04/22	20.00	300.00	296.67	190.00

PROJECT NUMBER	ITEM NUMBER/ PROJECT LOCATION	ITEM DESCRIPTION/ PROJECT LOCATION	DATE LET	UNIT/ QUANTITY	ENGR. EST.	AVERAGE BID	AWARDED BID
===== 203-01597		Potholing		Hour =====			
NHPP0063-054		US 6 FROM I70-B TO 33 RD. (MP	08/18/22	300.00	250.00	476.60	390.00
C1211-099		SH 121 NORTH SGA SIGNALS	08/25/22	200.00	250.00	335.00	380.00
ER0502-092		US 50 MP 204 EB MONARCH TRUCK	08/29/22	8.00	400.00	356.79	270.38
BR0343-046		US 34 TIMBER BRIDGE REPL. PKG	08/31/22	30.00	268.72	309.60	309.60
FBR0343-047		US 6/US 34 TIMBER BRIDGE REPL					
2670403-065		US40 FLOYD HILL ROUNDABOUTS	09/15/22	40.00	260.00	363.69	314.00
2670703-497		I-70 GENESEE WILDLIFE XING	09/15/22	60.00	270.00	399.20	439.58
SHE2873-193		US 287 & CO 52 INTERSECTION I	09/15/22	40.00	200.00	337.14	220.00
NHPP0701-231		I-70 SALT WASH BRIDGES SCOUR	09/29/22	16.00	400.00	316.10	200.00
	WEIGHTED AVERAGE FOR THE THIRD	QUARTER		818.00	304.28	406.07	395.96
C0831-126		SH83 EL PASO COUNTY TO BAYOU	10/13/22	50.00	275.00	325.00	300.00
NHPP0701-253		I-70 EAST OF DEBEQUE	10/27/22	20.00	400.00	386.00	500.00
FSAM240-200		SH21B CO SPRINGS SIGNAL REPLA	10/27/22	209.00	175.00	325.00	225.00
STA3852-015		US 385 HOLYOKE NORTH	10/27/22	50.00	350.00	400.00	400.00
NHPP0343-048		US 34 (MP 169.3-171.4)	11/01/22	33.00	270.00	328.19	450.00
STU0252-457		I-25:ALAMEDA RIVER PH 2.0	11/03/22	500.00	400.00	405.82	430.00
SHE0242-087		US 24 SAFETY IMPRVMENTS, E OF	11/03/22	40.00	275.00	279.87	214.62
STR064A-010		SH 64 AND SH 13 AT MEEKER	11/10/22	10.00	500.00	425.00	400.00
C5502-097		US550 MP 117.28-126.06	11/17/22	100.00	400.00	426.67	450.00
STRC090-011		US 50B AND SH71/CR18 INTERSEC	11/17/22	40.00	439.00	302.50	255.00
STAM420-001		US 285 AT HWY 9C IMPROVEMENTS	12/01/22	92.00	250.00	375.66	401.96
BR2854-148		INTERSECTION OF US 285 & SH 9					
STM0091-046		ADA RAMP IMPROVEMENTS - FAIRP					
STR114A-015		SH114 SILLSVILLE SOUTH TO MP3	12/01/22	25.00	400.00	365.00	330.00
2670703-487		I-70 BRIDGES OVER WARD ROAD-	12/01/22	100.00	400.00	364.66	400.00
NHPP0701-252		I-70 RIFLE TO SILT SLAB REPLA	12/01/22	80.00	400.00	470.00	340.00
STR318A-001		SH 318 MP 0 - 12.5 MOFFAT COU	12/01/22	20.00	400.00	425.00	450.00
NHPP0021-041		SH2 RESURFACING MLK TO 52ND	12/01/22	35.00	300.00	357.82	282.36
STR0641-107		SH 13 MM 104-128.1 IN MOFFAT	12/01/22	10.00	50.00	320.00	200.00
NHPP083A-046		SH83 RESURFACING STROH RD TO	12/08/22	20.00	270.00	362.65	287.30
NHPP0063-048		US6 / 20 ROAD INTERSECTION IM	12/15/22	30.00	400.00	516.15	265.00
FSA0853-122		WCR14.5 AND US-85, FORT LUPTO	12/15/22	5.00	400.00	299.03	255.00
NHPP0931-033		SH93:US6 TO 58TH RESURFACING	12/15/22	150.00	350.00	292.47	358.50
NHPP0502-090		SH 50 MP 134.6-136 GUNNISON C	12/22/22	40.00	350.00	377.87	524.28
STA385A-016		SH 385 MP 97.76	12/22/22	20.00	200.00	304.38	187.50
	WEIGHTED AVERAGE FOR THE FOURTH	QUARTER		1,679.00	340.80	368.24	367.15
	WEIGHTED AVERAGE FOR THE YEAR			5,995.00	301.08	324.65	332.41
===== 203-01598		Potholing (Spec)		Each =====			
STA0252-459			02/03/22	16.00	2000.00	493.33	380.00
	WEIGHTED AVERAGE FOR THE FIRST	QUARTER		16.00	2000.00	493.33	380.00
	WEIGHTED AVERAGE FOR THE YEAR			16.00	2000.00	493.33	380.00

COLORADO DEPARTMENT OF TRANSPORTATION
ITEM UNIT COSTS BY PROJECTS -- 2022 COST DATA

11:31 Wednesday, March 8, 2023 83

PROJECT NUMBER	ITEM NUMBER/ PROJECT LOCATION	ITEM DESCRIPTION/ PROJECT LOCATION	DATE LET	UNIT/ QUANTITY	ENGR. EST.	AVERAGE BID	AWARDED BID
=====	203-01620	Sweeping		Hour	=====	=====	=====
FSA3921-019		SH 392 AND WCR 55 ISLANDS	06/02/22	10.00	145.00	176.33	150.00
MPR200-278		R2 - VARIOUS LOCATIONS	06/09/22	50.00	50.00	100.00	50.00
		WEIGHTED AVERAGE FOR THE SECOND QUARTER		60.00	65.83	112.72	66.67
		WEIGHTED AVERAGE FOR THE YEAR		60.00	65.83	112.72	66.67
=====	203-01622	Sweeping (With Pickup Broom)		Hour	=====	=====	=====
MTCE R500-218			01/06/22	150.00	200.00	155.00	75.00
		WEIGHTED AVERAGE FOR THE FIRST QUARTER		150.00	200.00	155.00	75.00
		WEIGHTED AVERAGE FOR THE YEAR		150.00	200.00	155.00	75.00
=====	203-02300	Rock Scaler		Hour	=====	=====	=====
C5502-111		US 550 MP 81 AND 89 RED MOUNT	10/27/22	20.00	250.00	450.00	400.00
SHE0242-087		US 24 SAFETY IMPRVMENTS, E OF	11/03/22	60.00	100.00	453.74	161.23
		WEIGHTED AVERAGE FOR THE FOURTH QUARTER		80.00	137.50	453.06	220.92
		WEIGHTED AVERAGE FOR THE YEAR		80.00	137.50	453.06	220.92
=====	203-02330	Laborer		Hour	=====	=====	=====
NHPP2873-189		US 287 (FEDERAL BLVD) - COLFA	01/06/22	20.00	60.00	70.81	90.53
NHPP1601-083			02/03/22	40.00	60.00	153.72	88.00
NHPP0063-063			02/24/22	50.00	60.00	49.50	49.00
STA 067A-048		Hwy 67A MP 0.00 TO MP 11.05 I	03/03/22	30.00	50.00	60.48	90.00
CR100-362			03/14/22	250.00	52.88	52.88	52.88
ER007A-035			03/15/22	10.00	58.43	62.52	62.52
STR R500-171		Various locations on SH 141 a	03/17/22	30.00	83.00	47.62	20.00
		WEIGHTED AVERAGE FOR THE FIRST QUARTER		430.00	56.73	66.41	57.97
NHPP0702-413		VAIL PASS AUX PHASE 1 CAP 2	04/18/22	40.00	49.11	49.11	49.11

PROJECT NUMBER	ITEM NUMBER/ PROJECT LOCATION	ITEM DESCRIPTION/ PROJECT LOCATION	DATE LET	UNIT/ QUANTITY	ENGR. EST.	AVERAGE BID	AWARDED BID
===== 203-02330 Laborer Hour =====							
ER0702-420		PR I-70 GWC MATERIAL FLOWS 20	05/06/22	1,120.00	50.00	50.00	50.00
FSA0702-409		I-70 VAIL WILDLIFE FENCE PHAS	05/26/22	50.00	70.00	50.00	50.00
WEIGHTED AVERAGE FOR THE SECOND QUARTER				1,210.00	50.80	49.98	49.97
NHPP0702-414		VAIL PASS AUX PHASE 1 CAP 3	07/08/22	40.00	49.56	49.56	49.56
FBR0702-423		VAIL PASS AUX BE F-12-AT PHAS					
FBR0761-236		I-76 OVER CLR CRK SCOUR MIT	08/25/22	20.00	60.00	56.42	45.00
ER0502-092		US 50 MP 204 EB MONARCH TRUCK	08/29/22	40.00	60.00	57.99	50.21
2670703-497		I-70_GENESEE WILDLIFE XING	09/15/22	80.00	52.00	67.11	58.67
WEIGHTED AVERAGE FOR THE THIRD QUARTER				180.00	54.12	63.99	53.25
NHPP0701-253		I-70 EAST OF DEBEQUE	10/27/22	20.00	55.00	46.15	46.00
C5502-111		US 550 MP 81 AND 89 RED MOUNT	10/27/22	20.00	70.00	117.50	160.00
STR064A-010		SH 64 AND SH 13 AT MEEKER	11/10/22	20.00	60.00	63.00	46.00
2670703-487		I-70 BRIDGES OVER WARD ROAD-	12/01/22	60.00	60.00	59.18	61.00
STR318A-001		SH 318 MP 0 - 12.5 MOFFAT COU	12/01/22	20.00	60.00	50.75	55.00
STR0092-024		SH 9 North of Silverthorne	12/22/22	80.00	80.00	53.00	60.00
WEIGHTED AVERAGE FOR THE FOURTH QUARTER				220.00	67.73	60.21	66.36
WEIGHTED AVERAGE FOR THE YEAR				2,040.00	54.17	56.48	53.71
===== 206-00000 Str Excav Cubic Yard =====							
NH0504-910		US50B L-24-B MIN REP AT MP 40	01/13/22	170.00	25.00	45.95	28.75
NHPP0702-383		I-70 EB AUX FRISCO TO SILVERT	01/13/22	1,868.00	33.52	44.91	24.00
NHPP1601-083			02/03/22	158.00	50.00	566.80	140.00
STA0252-459			02/03/22	300.00	54.00	141.69	242.75
NHPP 0761-238		I-76 DAHLIA TO YORK	03/10/22	3,576.00	22.00	23.12	27.00
C0761-239							
NHPP0253-275		I-25 EXPRESS LANES SEGMENT 5	03/11/22	132.00	83.51	92.07	92.07
STR R500-171		Various locations on SH 141 a	03/17/22	13.00	380.00	361.65	88.00
WEIGHTED AVERAGE FOR THE FIRST QUARTER				6,217.00	29.85	36.28	40.94
NH0504-911			04/07/22	642.00	27.98	44.75	49.50

PROJECT NUMBER	ITEM NUMBER/ PROJECT LOCATION	ITEM DESCRIPTION/ PROJECT LOCATION	DATE LET	UNIT/ QUANTITY	ENGR. EST.	AVERAGE BID	AWARDED BID
=====	206-00000	Str Excav		Cubic Yard	=====	=====	=====
NHPP0702-413		VAIL PASS AUX PHASE 1 CAP 2	04/18/22	9,503.00	35.19	35.19	35.19
STM1151-038		SH115 MP 27 TO MP 38	04/21/22	878.00	25.00	26.64	26.01
MTCE2873-204		MTCE FY22 SH287 CONC PANEL RE	05/05/22	19.00	80.00	131.70	153.40
2670703-479		I-70 BRIDGE OVER HARLAN	05/05/22	19,899.00	28.00	29.63	20.00
		WEIGHTED AVERAGE FOR THE SECOND QUARTER		30,941.00	30.15	30.10	25.53
NHPP0702-414		VAIL PASS AUX PHASE 1 CAP 3	07/08/22	4,392.00	56.44	56.44	56.44
FBR0702-423		VAIL PASS AUX BE F-12-AT PHAS					
FSA052A-057		SH52 BOX CULVERT EXTENSION (M	08/04/22	124.00	90.00	69.74	65.50
NHPP0063-054		US 6 FROM I70-B TO 33 RD. (MP	08/18/22	216.00	35.00	55.95	80.75
ER0502-092		US 50 MP 204 EB MONARCH TRUCK	08/29/22	1,014.00	75.00	45.72	27.17
NHPPR100-266		R1 ESSENTIAL REPAIRS	09/01/22	103.00	35.00	125.93	198.78
2670403-065		US40 FLOYD HILL ROUNDABOUTS	09/15/22	370.00	80.00	71.12	51.00
2670703-497		I-70 GENESEE WILDLIFE XING	09/15/22	2,145.00	31.00	40.08	21.57
SHE2873-193		US 287 & CO 52 INTERSECTION I	09/15/22	507.00	25.00	34.92	23.50
		WEIGHTED AVERAGE FOR THE THIRD QUARTER		8,871.00	51.29	45.57	44.92
C170A-002		CRITICAL CULVERT CONST. PKG D	10/27/22	129.00	100.00	133.88	62.50
TRG0253-264		I-25 AND SH 119 PARK-N-RIDE	10/27/22	5,176.00	27.00	26.75	13.50
NHPP0343-048		US 34 (MP 169.3-171.4)	11/01/22	2.00	40.00	863.28	440.00
STU0252-457		I-25:ALAMEDA RIVER PH 2.0	11/03/22	5,000.00	60.00	41.40	49.50
C5502-097		US550 MP 117.28-126.06	11/17/22	434.00	70.00	64.70	83.20
STAM420-001		US 285 AT HWY 9C IMPROVEMENTS	12/01/22	2,095.00	28.00	51.20	16.71
BR2854-148		INTERSECTION OF US 285 & SH 9					
STM0091-046		ADA RAMP IMPROVEMENTS - FAIRP					
2670703-487		I-70 BRIDGES OVER WARD ROAD-	12/01/22	14,099.00	40.00	30.32	26.00
IM025A-050		I25-MP103.9 - INTERSECTION DR	12/01/22	1,883.00	20.00	36.67	35.00
NHPP0502-090		SH 50 MP 134.6-136 GUNNISON C	12/22/22	108.00	50.00	83.80	34.97
STA0361-129		US 36: HYGIENE RD AND NELSON	12/22/22	286.00	50.00	66.12	28.32
BR012A-048		CO 12 STRUCTURE P-17-F AT MP	12/22/22	1,164.00	35.00	32.60	50.00
STA385A-016		SH 385 MP 97.76	12/22/22	710.00	35.00	62.50	35.00
		WEIGHTED AVERAGE FOR THE FOURTH QUARTER		31,086.00	39.53	34.43	29.76
		WEIGHTED AVERAGE FOR THE YEAR		77,115.00	36.34	33.87	30.70
=====	206-00010	Str Excav (Spec)		Cubic Yard	=====	=====	=====
ER0702-420		PR I-70 GWC MATERIAL FLOWS 20	05/06/22	559.00	300.00	240.50	231.00
		WEIGHTED AVERAGE FOR THE SECOND QUARTER		559.00	300.00	240.50	231.00
		WEIGHTED AVERAGE FOR THE YEAR		559.00	300.00	240.50	231.00

COLORADO DEPARTMENT OF TRANSPORTATION
ITEM UNIT COSTS BY PROJECTS -- 2022 COST DATA

11:31 Wednesday, March 8, 2023 86

PROJECT NUMBER	ITEM NUMBER/ PROJECT LOCATION	ITEM DESCRIPTION/ PROJECT LOCATION	DATE LET	UNIT/ QUANTITY	ENGR. EST.	AVERAGE BID	AWARDED BID
=====	206-00050	Str Bkfl (Spec)		Cubic Yard	=====		
2670703-479		I-70 BRIDGE OVER HARLAN	05/05/22	1,708.00	100.00	83.38	46.00
		WEIGHTED AVERAGE FOR THE SECOND QUARTER		1,708.00	100.00	83.38	46.00
NHPP0702-414 FBR0702-423		VAIL PASS AUX PHASE 1 CAP 3 VAIL PASS AUX BE F-12-AT PHAS	07/08/22	736.00	72.37	72.37	72.37
		WEIGHTED AVERAGE FOR THE THIRD QUARTER		736.00	72.37	72.37	72.37
STAM420-001 BR2854-148 STM0091-046		US 285 AT HWY 9C IMPROVEMENTS INTERSECTION OF US 285 & SH 9 ADA RAMP IMPROVEMENTS - FAIRP	12/01/22	5,850.00	40.00	48.63	16.36
		WEIGHTED AVERAGE FOR THE FOURTH QUARTER		5,850.00	40.00	48.63	16.36
		WEIGHTED AVERAGE FOR THE YEAR		8,294.00	55.23	59.50	27.43
=====	206-00060	Str Bkfl (Spec) (Flow-Fill)		Cubic Yard	=====		
NHPP 0761-238 C0761-239		I-76 DAHLIA TO YORK	03/10/22	160.00	180.00	238.16	150.00
		WEIGHTED AVERAGE FOR THE FIRST QUARTER		160.00	180.00	238.16	150.00
STAM420-001 BR2854-148 STM0091-046		US 285 AT HWY 9C IMPROVEMENTS INTERSECTION OF US 285 & SH 9 ADA RAMP IMPROVEMENTS - FAIRP	12/01/22	288.00	135.00	442.11	584.16
		WEIGHTED AVERAGE FOR THE FOURTH QUARTER		288.00	135.00	442.11	584.16
		WEIGHTED AVERAGE FOR THE YEAR		448.00	151.07	334.77	429.10
=====	206-00065	Str Bkfl (Flow-Fill)		Cubic Yard	=====		
NHPP1601-083			02/03/22	4.00	250.00	3072.78	2400.00

COLORADO DEPARTMENT OF TRANSPORTATION
ITEM UNIT COSTS BY PROJECTS -- 2022 COST DATA

11:31 Wednesday, March 8, 2023 87

PROJECT NUMBER	ITEM NUMBER/ PROJECT LOCATION	ITEM DESCRIPTION/ PROJECT LOCATION	DATE LET	UNIT/ QUANTITY	ENGR. EST.	AVERAGE BID	AWARDED BID
===== 206-00065 Str Bkfl (Flow-Fill) Cubic Yard =====							
BRC040-057			03/17/22	20.00	230.00	677.00	710.00
STR R500-171		Various locations on SH 141 a	03/17/22	12.00	390.00	1003.57	455.00
		WEIGHTED AVERAGE FOR THE FIRST QUARTER		36.00	285.56	926.38	812.78
NH0504-911			04/07/22	138.00	142.00	298.25	196.50
NHPP0702-413		VAIL PASS AUX PHASE 1 CAP 2	04/18/22	133.00	395.56	395.56	395.56
		WEIGHTED AVERAGE FOR THE SECOND QUARTER		271.00	266.44	329.89	294.19
NHPP0702-414		VAIL PASS AUX PHASE 1 CAP 3	07/08/22	50.00	463.44	463.44	463.44
FBR0702-423		VAIL PASS AUX BE F-12-AT PHAS					
ER0502-092		US 50 MP 204 EB MONARCH TRUCK	08/29/22	137.00	350.00	265.40	281.19
SHE2873-193		US 287 & CO 52 INTERSECTION I	09/15/22	178.00	250.00	241.18	214.00
		WEIGHTED AVERAGE FOR THE THIRD QUARTER		365.00	316.77	254.96	273.39
TRG0253-264		I-25 AND SH 119 PARK-N-RIDE	10/27/22	5.00	240.00	642.19	169.00
NHPP0343-048		US 34 (MP 169.3-171.4)	11/01/22	27.00	260.00	316.61	270.00
STA0711-021		SH71: REGION LINE NORTH	12/01/22	10.00	280.00	823.33	800.00
STR096A-050		SH 96 MP 168.99 TO 193.77	12/22/22	45.00	260.00	693.33	680.00
		WEIGHTED AVERAGE FOR THE FOURTH QUARTER		87.00	261.15	569.27	537.18
		WEIGHTED AVERAGE FOR THE YEAR		759.00	290.95	344.34	336.64
===== 206-00066 Str Bkfl (FF Ash) Cubic Yard =====							
STA0252-459			02/03/22	155.00	257.50	327.05	244.50
		WEIGHTED AVERAGE FOR THE FIRST QUARTER		155.00	257.50	327.05	244.50
		WEIGHTED AVERAGE FOR THE YEAR		155.00	257.50	327.05	244.50
===== 206-00100 Str Bkfl (CL 1) Cubic Yard =====							
NHPP0702-383		I-70 EB AUX FRISCO TO SILVERT	01/13/22	365.00	63.00	92.57	71.00

COLORADO DEPARTMENT OF TRANSPORTATION
ITEM UNIT COSTS BY PROJECTS -- 2022 COST DATA

11:31 Wednesday, March 8, 2023 88

PROJECT NUMBER	ITEM NUMBER/ PROJECT LOCATION	ITEM DESCRIPTION/ PROJECT LOCATION	DATE LET	UNIT/ QUANTITY	ENGR. EST.	AVERAGE BID	AWARDED BID
=====	206-00100	Str Bkfl (CL 1)		Cubic Yard	=====	=====	=====
NHPP 0761-238		I-76 DAHLIA TO YORK	03/10/22	1,678.00	44.00	54.17	43.00
C0761-239							
NHPP0253-275		I-25 EXPRESS LANES SEGMENT 5	03/11/22	868.00	47.25	48.19	48.19
		WEIGHTED AVERAGE FOR THE FIRST QUARTER		2,911.00	47.35	58.19	48.06
NHPP0702-413		VAIL PASS AUX PHASE 1 CAP 2	04/18/22	20,246.00	74.92	74.92	74.92
STM1151-038		SH115 MP 27 TO MP 38	04/21/22	1,242.00	60.00	66.18	66.30
2670703-479		I-70 BRIDGE OVER HARLAN	05/05/22	22,183.00	35.00	42.40	36.00
		WEIGHTED AVERAGE FOR THE SECOND QUARTER		43,671.00	54.22	47.45	54.91
NHPP0702-414		VAIL PASS AUX PHASE 1 CAP 3	07/08/22	5,337.00	78.52	78.52	78.52
FBR0702-423		VAIL PASS AUX BE F-12-AT PHAS					
FSA052A-057		SH52 BOX CULVERT EXTENSION (M	08/04/22	106.00	100.00	92.12	76.18
NHPP0063-054		US 6 FROM I70-B TO 33 RD. (MP	08/18/22	208.00	40.00	137.33	195.00
FBR0761-236		I-76 OVER CLR CRK SCOUR MIT	08/25/22	363.00	50.00	99.83	75.00
ER0502-092		US 50 MP 204 EB MONARCH TRUCK	08/29/22	171.00	75.00	121.86	144.58
BR0343-046		US 34 TIMBER BRIDGE REPL. PKG	08/31/22	1,311.00	139.56	109.77	109.77
FBR0343-047		US 6/US 34 TIMBER BRIDGE REPL					
2670403-065		US40 FLOYD HILL ROUNDABOUTS	09/15/22	140.00	80.00	80.17	70.00
2670703-497		I-70 GENESEE WILDLIFE KING	09/15/22	1,283.00	65.00	58.86	53.28
SHE2873-193		US 287 & CO 52 INTERSECTION I	09/15/22	265.00	50.00	63.09	70.50
		WEIGHTED AVERAGE FOR THE THIRD QUARTER		9,184.00	82.73	74.25	82.80
C170A-002		CRITICAL CULVERT CONST. PKG D	10/27/22	124.00	85.00	147.25	75.00
TRG0253-264		I-25 AND SH 119 PARK-N-RIDE	10/27/22	1,397.00	41.00	118.23	145.00
NHPP0343-048		US 34 (MP 169.3-171.4)	11/01/22	31.00	90.00	235.58	58.00
STU0252-457		I-25:ALAMEDA RIVER PH 2.0	11/03/22	4,078.00	65.00	65.08	42.00
C5502-097		US550 MP 117.28-126.06	11/17/22	259.00	85.00	96.59	98.80
STAM420-001		US 285 AT HWY 9C IMPROVEMENTS	12/01/22	1,200.00	33.00	48.88	49.51
BR2854-148		INTERSECTION OF US 285 & SH 9					
STM0091-046		ADA RAMP IMPROVEMENTS - FAIRP					
2670703-487		I-70 BRIDGES OVER WARD ROAD-	12/01/22	12,811.00	80.00	38.37	48.00
IM025A-050		I25-MP103.9 - INTERSECTION DR	12/01/22	2,234.00	40.00	77.00	60.00
NHPP0502-090		SH 50 MP 134.6-136 GUNNISON C	12/22/22	38.00	65.00	155.52	248.91
STA0361-129		US 36: HYGIENE RD AND NELSON	12/22/22	68.20	90.00	139.09	67.96
BR012A-048		CO 12 STRUCTURE P-17-F AT MP	12/22/22	719.00	70.00	89.54	112.00

COLORADO DEPARTMENT OF TRANSPORTATION
ITEM UNIT COSTS BY PROJECTS -- 2022 COST DATA

11:31 Wednesday, March 8, 2023 89

PROJECT NUMBER	ITEM NUMBER/ PROJECT LOCATION	ITEM DESCRIPTION/ PROJECT LOCATION	DATE LET	UNIT/ QUANTITY	ENGR. EST.	AVERAGE BID	AWARDED BID
=====	206-00100	Str Bkfl (CL 1)		Cubic Yard	=====		
STA385A-016		SH 385 MP 97.76	12/22/22	485.00	50.00	117.50	50.00
		WEIGHTED AVERAGE FOR THE FOURTH QUARTER		23,444.20	68.02	56.25	56.93
		WEIGHTED AVERAGE FOR THE YEAR		79,210.20	61.36	52.94	58.46
=====	206-00200	Str Bkfl (CL 2)		Cubic Yard	=====		
NH0504-910		US50B L-24-B MIN REP AT MP 40	01/13/22	145.00	40.00	80.18	50.00
NHPP0702-383		I-70 EB AUX FRISCO TO SILVERT	01/13/22	906.00	31.50	52.97	24.00
NHPP 0761-238		I-76 DAHLIA TO YORK	03/10/22	172.00	40.00	31.93	43.00
C0761-239							
NHPP0253-275		I-25 EXPRESS LANES SEGMENT 5	03/11/22	2,374.00	33.29	31.10	31.10
		WEIGHTED AVERAGE FOR THE FIRST QUARTER		3,597.00	33.43	47.75	30.64
NH0504-911			04/07/22	174.00	174.00	85.90	51.80
NHPP0702-413		VAIL PASS AUX PHASE 1 CAP 2	04/18/22	689.00	67.14	67.14	67.14
STM1151-038		SH115 MP 27 TO MP 38	04/21/22	235.00	28.00	30.94	19.86
2670703-479		I-70 BRIDGE OVER HARLAN	05/05/22	1,117.00	35.00	26.30	15.00
		WEIGHTED AVERAGE FOR THE SECOND QUARTER		2,215.00	55.17	32.39	34.63
NHPP0702-414		VAIL PASS AUX PHASE 1 CAP 3	07/08/22	879.00	46.73	46.73	46.73
FBR0702-423		VAIL PASS AUX BE F-12-AT PHAS					
BR0343-046		US 34 TIMBER BRIDGE REPL. PKG	08/31/22	82.00	37.69	28.56	28.56
FBR0343-047		US 6/US 34 TIMBER BRIDGE REPL					
NHPPR100-266		R1 ESSENTIAL REPAIRS	09/01/22	172.00	35.00	125.67	110.01
2670703-497		I-70_GENESEE WILDLIFE XING	09/15/22	169.00	41.00	48.02	7.15
		WEIGHTED AVERAGE FOR THE THIRD QUARTER		1,302.00	43.87	62.06	48.81
STU0252-457		I-25:ALAMEDA RIVER PH 2.0	11/03/22	117.00	50.00	50.37	35.00
STAM420-001		US 285 AT HWY 9C IMPROVEMENTS	12/01/22	1,665.00	25.00	30.92	51.00
BR2854-148		INTERSECTION OF US 285 & SH 9					
STM0091-046		ADA RAMP IMPROVEMENTS - FAIRP					
STA0711-021		SH71: REGION LINE NORTH	12/01/22	109.00	47.00	58.33	64.00

COLORADO DEPARTMENT OF TRANSPORTATION
ITEM UNIT COSTS BY PROJECTS -- 2022 COST DATA

11:31 Wednesday, March 8, 2023 90

PROJECT NUMBER	ITEM NUMBER/ PROJECT LOCATION	ITEM DESCRIPTION/ PROJECT LOCATION	DATE LET	UNIT/ QUANTITY	ENGR. EST.	AVERAGE BID	AWARDED BID
===== 206-00200							
		Str Bkfl (CL 2)		Cubic Yard			
2670703-487		I-70 BRIDGES OVER WARD ROAD-	12/01/22	113.00	50.00	28.44	22.00
IM025A-050		I25-MP103.9 - INTERSECTION DR	12/01/22	330.00	30.00	41.67	20.00
BR012A-048		CO 12 STRUCTURE P-17-F AT MP	12/22/22	89.00	60.00	193.76	325.00
STA385A-016		SH 385 MP 97.76	12/22/22	165.00	20.00	80.00	50.00
	WEIGHTED AVERAGE FOR THE FOURTH QUARTER			2,588.00	29.67	39.94	52.48
	WEIGHTED AVERAGE FOR THE YEAR			9,702.00	38.79	41.97	40.28
===== 206-00360							
		Mechanical Reinforcement of Soil		Cubic Yard			
NHPP0702-383		I-70 EB AUX FRISCO TO SILVERT	01/13/22	365.00	125.00	30.64	34.00
NHPP 0761-238		I-76 DAHLIA TO YORK	03/10/22	1,641.00	22.00	24.45	20.00
C0761-239							
	WEIGHTED AVERAGE FOR THE FIRST QUARTER			2,006.00	40.74	25.20	22.55
NHPP0702-413		VAIL PASS AUX PHASE 1 CAP 2	04/18/22	11,728.00	2.11	2.11	2.11
STM1151-038		SH115 MP 27 TO MP 38	04/21/22	1,050.00	20.00	27.85	24.99
2670703-479		I-70 BRIDGE OVER HARLAN	05/05/22	17,527.00	18.00	14.51	7.25
	WEIGHTED AVERAGE FOR THE SECOND QUARTER			30,305.00	11.92	13.90	5.88
NHPP0702-414		VAIL PASS AUX PHASE 1 CAP 3	07/08/22	3,972.00	0.94	0.94	0.94
FBR0702-423		VAIL PASS AUX BE F-12-AT PHAS					
2670703-497		I-70_GENESEE WILDLIFE KING	09/15/22	1,283.00	21.00	29.18	48.93
	WEIGHTED AVERAGE FOR THE THIRD QUARTER			5,255.00	5.84	20.52	12.66
STU0252-457		I-25:ALAMEDA RIVER PH 2.0	11/03/22	3,400.00	35.00	35.61	32.00
STAM420-001		US 285 AT HWY 9C IMPROVEMENTS	12/01/22	4,370.00	21.00	41.66	30.21
BR285A-148		INTERSECTION OF US 285 & SH 9					
STM0091-046		ADA RAMP IMPROVEMENTS - FAIRP					
2670703-487		I-70 BRIDGES OVER WARD ROAD-	12/01/22	9,449.00	10.20	21.75	8.50
IM025A-050		I25-MP103.9 - INTERSECTION DR	12/01/22	1,420.00	16.00	18.33	20.00
BR012A-048		CO 12 STRUCTURE P-17-F AT MP	12/22/22	719.00	30.00	42.69	27.00
	WEIGHTED AVERAGE FOR THE FOURTH QUARTER			19,358.00	18.15	29.20	18.85
	WEIGHTED AVERAGE FOR THE YEAR			56,924.00	14.49	20.51	11.63

PROJECT NUMBER	ITEM NUMBER/ PROJECT LOCATION	ITEM DESCRIPTION/ PROJECT LOCATION	DATE LET	UNIT/ QUANTITY	ENGR. EST.	AVERAGE BID	AWARDED BID
=====	206-00510	Filter Matl (CL A)		Cubic Yard	=====		
2670703-479		I-70 BRIDGE OVER HARLAN	05/05/22	4.00	140.00	314.00	845.64
		WEIGHTED AVERAGE FOR THE SECOND QUARTER		4.00	140.00	314.00	845.64
SHE2873-193		US 287 & CO 52 INTERSECTION I	09/15/22	70.00	100.00	117.42	118.00
		WEIGHTED AVERAGE FOR THE THIRD QUARTER		70.00	100.00	117.42	118.00
C5502-097 IM025A-050		US550 MP 117.28-126.06	11/17/22	74.00	200.00	115.70	156.00
		I25-MP103.9 - INTERSECTION DR	12/01/22	106.00	100.00	146.67	140.00
		WEIGHTED AVERAGE FOR THE FOURTH QUARTER		180.00	141.11	133.93	146.58
		WEIGHTED AVERAGE FOR THE YEAR		254.00	129.76	131.28	149.71
=====	206-00520	Filter Matl (CL B)		Cubic Yard	=====		
NHPP0702-383		I-70 EB AUX FRISCO TO SILVERT	01/13/22	24.00	45.00	211.06	145.00
		WEIGHTED AVERAGE FOR THE FIRST QUARTER		24.00	45.00	211.06	145.00
		WEIGHTED AVERAGE FOR THE YEAR		24.00	45.00	211.06	145.00
=====	206-00530	Filter Matl (CL C)		Cubic Yard	=====		
NHPP 0761-238 C0761-239		I-76 DAHLIA TO YORK	03/10/22	117.00	125.00	104.90	75.00
		WEIGHTED AVERAGE FOR THE FIRST QUARTER		117.00	125.00	104.90	75.00
		WEIGHTED AVERAGE FOR THE YEAR		117.00	125.00	104.90	75.00
=====	206-01001	Bed Course Matl (Spec)		Cubic Yard	=====		
FSA052A-057		SH52 BOX CULVERT EXTENSION (M	08/04/22	5.00	110.00	263.83	256.88
		WEIGHTED AVERAGE FOR THE THIRD QUARTER		5.00	110.00	263.83	256.88
		WEIGHTED AVERAGE FOR THE YEAR		5.00	110.00	263.83	256.88

COLORADO DEPARTMENT OF TRANSPORTATION
ITEM UNIT COSTS BY PROJECTS -- 2022 COST DATA

11:31 Wednesday, March 8, 2023 92

PROJECT NUMBER	ITEM NUMBER/ PROJECT LOCATION	ITEM DESCRIPTION/ PROJECT LOCATION	DATE LET	UNIT/ QUANTITY	ENGR. EST.	AVERAGE BID	AWARDED BID
===== 206-01600 Temp Excav Support LUMP SUM =====							
C170A-002		CRITICAL CULVERT CONST. PKG D	10/27/22	1.00	15000.00	22500.00	10000.00
		WEIGHTED AVERAGE FOR THE FOURTH QUARTER		1.00	15000.00	22500.00	10000.00
		WEIGHTED AVERAGE FOR THE YEAR		1.00	15000.00	22500.00	10000.00
===== 206-01750 Shoring LUMP SUM =====							
NHC540-017		R2 CHAINUP STA @ KENOSHA/HOOS	05/12/22	1.00	30000.00	335000.00	55000.00
		WEIGHTED AVERAGE FOR THE SECOND QUARTER		1.00	30000.00	335000.00	55000.00
ER0502-092 NHPPR100-266		US 50 MP 204 EB MONARCH TRUCK	08/29/22	1.00	30000.00	59686.72	41060.16
		R1 ESSENTIAL REPAIRS	09/01/22	1.00	30000.00	36638.41	52415.22
		WEIGHTED AVERAGE FOR THE THIRD QUARTER		2.00	30000.00	48162.56	46737.69
STAM420-001 BR2854-148 STM0091-046 STA385A-016		US 285 AT HWY 9C IMPROVEMENTS	12/01/22	1.00	85000.00	176537.50	150000.00
		INTERSECTION OF US 285 & SH 9					
		ADA RAMP IMPROVEMENTS - FAIRP					
		SH 385 MP 97.76	12/22/22	1.00	40000.00	83486.11	30944.44
		WEIGHTED AVERAGE FOR THE FOURTH QUARTER		2.00	62500.00	130011.81	90472.22
		WEIGHTED AVERAGE FOR THE YEAR		5.00	43000.00	137298.22	65883.96
===== 206-01781 Shoring (A 1) LUMP SUM =====							
NHPP0702-383 NHPP 0761-238 C0761-239		I-70 EB AUX FRISCO TO SILVERT	01/13/22	1.00	25000.00	142131.28	126000.00
		I-76 DAHLIA TO YORK	03/10/22	1.00	44000.00	38880.85	6000.00
		WEIGHTED AVERAGE FOR THE FIRST QUARTER		2.00	34500.00	78592.55	66000.00
NHPP0702-413		VAIL PASS AUX PHASE 1 CAP 2	04/18/22	1.00	828.18	828.18	828.18

COLORADO DEPARTMENT OF TRANSPORTATION
ITEM UNIT COSTS BY PROJECTS -- 2022 COST DATA

11:31 Wednesday, March 8, 2023 93

PROJECT NUMBER	ITEM NUMBER/ PROJECT LOCATION	ITEM DESCRIPTION/ PROJECT LOCATION	DATE LET	UNIT/ QUANTITY	ENGR. EST.	AVERAGE BID	AWARDED BID
===== 206-01781 Shoring (A 1) LUMP SUM =====							
STM1151-038		SH115 MP 27 TO MP 38	04/21/22	1.00	75000.00	50053.34	37400.00
2670703-479		I-70 BRIDGE OVER HARLAN	05/05/22	1.00	90000.00	51296.27	58691.78
		WEIGHTED AVERAGE FOR THE SECOND QUARTER		3.00	55276.06	46572.71	32306.65
NHPP0702-414		VAIL PASS AUX PHASE 1 CAP 3	07/08/22	1.00	64075.85	64075.85	64075.85
FBR0702-423		VAIL PASS AUX BE F-12-AT PHAS					
NHPPR100-266		R1 ESSENTIAL REPAIRS	09/01/22	1.00	30000.00	88189.92	21319.76
2670703-497		I-70 GENESEE WILDLIFE XING	09/15/22	1.00	62000.00	126917.17	76802.90
NHPP0701-231		I-70 SALT WASH BRIDGES SCOUR	09/29/22	1.00	25000.00	37637.64	21200.00
		WEIGHTED AVERAGE FOR THE THIRD QUARTER		4.00	45268.96	99410.85	45849.63
TRG0253-264		I-25 AND SH 119 PARK-N-RIDE	10/27/22	1.00	65000.00	76775.00	95000.00
STU0252-457		I-25:ALAMEDA RIVER PH 2.0	11/03/22	1.00	60000.00	146018.72	95000.00
STAM420-001		US 285 AT HWY 9C IMPROVEMENTS	12/01/22	1.00	353800.00	74025.00	15000.00
BR2854-148		INTERSECTION OF US 285 & SH 9					
STM0091-046		ADA RAMP IMPROVEMENTS - FAIRP					
2670703-487		I-70 BRIDGES OVER WARD ROAD-	12/01/22	1.00	8000.00	76151.42	57500.00
		WEIGHTED AVERAGE FOR THE FOURTH QUARTER		4.00	121700.00	86455.66	65625.00
		WEIGHTED AVERAGE FOR THE YEAR		13.00	69438.77	79345.35	51909.11
===== 206-01782 Shoring (A 2) LUMP SUM =====							
NHPP0702-383		I-70 EB AUX FRISCO TO SILVERT	01/13/22	1.00	25000.00	138233.63	99600.00
NHPP 0761-238		I-76 DAHLIA TO YORK	03/10/22	1.00	40000.00	38630.85	5000.00
C0761-239							
		WEIGHTED AVERAGE FOR THE FIRST QUARTER		2.00	32500.00	76939.62	52300.00
NHPP0702-413		VAIL PASS AUX PHASE 1 CAP 2	04/18/22	1.00	8868.16	8868.16	8868.16
STM1151-038		SH115 MP 27 TO MP 38	04/21/22	1.00	35000.00	47134.78	35750.00
2670703-479		I-70 BRIDGE OVER HARLAN	05/05/22	1.00	90000.00	82518.71	95798.27
		WEIGHTED AVERAGE FOR THE SECOND QUARTER		3.00	44622.72	61637.86	46805.48

COLORADO DEPARTMENT OF TRANSPORTATION
ITEM UNIT COSTS BY PROJECTS -- 2022 COST DATA

11:31 Wednesday, March 8, 2023 94

PROJECT NUMBER	ITEM NUMBER/ PROJECT LOCATION	ITEM DESCRIPTION/ PROJECT LOCATION	DATE LET	UNIT/ QUANTITY	ENGR. EST.	AVERAGE BID	AWARDED BID
===== 206-01782 Shoring (A 2) LUMP SUM =====							
2670703-497		I-70_GENESEE WILDLIFE KING	09/15/22	1.00	24000.00	90966.74	45344.24
NHPP0701-231		I-70 SALT WASH BRIDGES SCOUR	09/29/22	1.00	25000.00	40152.76	21200.00
		WEIGHTED AVERAGE FOR THE THIRD QUARTER		2.00	24500.00	79674.74	33272.12
TRG0253-264		I-25 AND SH 119 PARK-N-RIDE	10/27/22	1.00	65000.00	71139.63	90000.00
STU0252-457		I-25:ALAMEDA RIVER PH 2.0	11/03/22	1.00	60000.00	181823.91	95000.00
STAM420-001		US 285 AT HWY 9C IMPROVEMENTS	12/01/22	1.00	39000.00	57487.50	15000.00
BR2854-148		INTERSECTION OF US 285 & SH 9					
STM0091-046		ADA RAMP IMPROVEMENTS - FAIRP					
2670703-487		I-70 BRIDGES OVER WARD ROAD-	12/01/22	1.00	8000.00	77527.52	61700.00
		WEIGHTED AVERAGE FOR THE FOURTH QUARTER		4.00	43000.00	86608.82	65425.00
		WEIGHTED AVERAGE FOR THE YEAR		11.00	38169.83	77576.27	52114.61
===== 206-01783 Shoring (A 3) LUMP SUM =====							
NHPP0702-383		I-70 EB AUX FRISCO TO SILVERT	01/13/22	1.00	25000.00	58350.22	23000.00
NHPP 0761-238		I-76 DAHLIA TO YORK	03/10/22	1.00	16000.00	38269.41	5000.00
C0761-239							
		WEIGHTED AVERAGE FOR THE FIRST QUARTER		2.00	20500.00	45992.80	14000.00
NHPP0702-413		VAIL PASS AUX PHASE 1 CAP 2	04/18/22	1.00	8868.16	8868.16	8868.16
2670703-479		I-70 BRIDGE OVER HARLAN	05/05/22	1.00	20000.00	90225.65	83766.73
		WEIGHTED AVERAGE FOR THE SECOND QUARTER		2.00	14434.08	78603.15	46317.45
2670703-497		I-70_GENESEE WILDLIFE KING	09/15/22	1.00	126000.00	99625.99	97397.01
NHPP0701-231		I-70 SALT WASH BRIDGES SCOUR	09/29/22	1.00	25000.00	30992.25	23000.00
		WEIGHTED AVERAGE FOR THE THIRD QUARTER		2.00	75500.00	84374.04	60198.51

COLORADO DEPARTMENT OF TRANSPORTATION
 ITEM UNIT COSTS BY PROJECTS -- 2022 COST DATA

11:31 Wednesday, March 8, 2023 95

PROJECT NUMBER	ITEM NUMBER/ PROJECT LOCATION	ITEM DESCRIPTION/ PROJECT LOCATION	DATE LET	UNIT/ QUANTITY	ENGR. EST.	AVERAGE BID	AWARDED BID
===== 206-01783		Shoring (A 3)		LUMP SUM	=====		
TRG0253-264		I-25 AND SH 119 PARK-N-RIDE	10/27/22	1.00	65000.00	37826.55	8000.00
STU0252-457		I-25:ALAMEDA RIVER PH 2.0	11/03/22	1.00	20000.00	82159.08	69000.00
STAM420-001		US 285 AT HWY 9C IMPROVEMENTS	12/01/22	1.00	19500.00	55762.50	15000.00
BR2854-148		INTERSECTION OF US 285 & SH 9					
STM0091-046		ADA RAMP IMPROVEMENTS - FAIRP					
2670703-487		I-70 BRIDGES OVER WARD ROAD-	12/01/22	1.00	8000.00	75151.42	57500.00
		WEIGHTED AVERAGE FOR THE FOURTH QUARTER		4.00	28125.00	57394.84	37375.00
		WEIGHTED AVERAGE FOR THE YEAR		10.00	33336.82	62354.93	39053.19
===== 206-01784		Shoring (A 4)		LUMP SUM	=====		
NHPP0702-383		I-70 EB AUX FRISCO TO SILVERT	01/13/22	1.00	25000.00	76866.80	85000.00
NHPP 0761-238		I-76 DAHLIA TO YORK	03/10/22	1.00	18000.00	37251.35	4000.00
C0761-239							
		WEIGHTED AVERAGE FOR THE FIRST QUARTER		2.00	21500.00	52488.07	44500.00
2670703-479		I-70 BRIDGE OVER HARLAN	05/05/22	1.00	20000.00	97308.54	88688.37
		WEIGHTED AVERAGE FOR THE SECOND QUARTER		1.00	20000.00	97308.54	88688.37
2670703-497		I-70_GENESEE WILDLIFE XING	09/15/22	1.00	24000.00	50685.66	29147.66
NHPP0701-231		I-70 SALT WASH BRIDGES SCOUR	09/29/22	1.00	25000.00	36022.51	23000.00
		WEIGHTED AVERAGE FOR THE THIRD QUARTER		2.00	24500.00	47427.18	26073.83
TRG0253-264		I-25 AND SH 119 PARK-N-RIDE	10/27/22	1.00	65000.00	63599.13	55000.00
STU0252-457		I-25:ALAMEDA RIVER PH 2.0	11/03/22	1.00	20000.00	92709.77	66000.00
2670703-487		I-70 BRIDGES OVER WARD ROAD-	12/01/22	1.00	8000.00	76109.77	57400.00
		WEIGHTED AVERAGE FOR THE FOURTH QUARTER		3.00	31000.00	72966.95	59466.67
		WEIGHTED AVERAGE FOR THE YEAR		8.00	25625.00	65011.64	51029.50

PROJECT NUMBER	ITEM NUMBER/ PROJECT LOCATION	ITEM DESCRIPTION/ PROJECT LOCATION	DATE LET	UNIT/ QUANTITY	ENGR. EST.	AVERAGE BID	AWARDED BID	
===== 206-01785				Shoring (A 5)				LUMP SUM =====
NHPP0702-383		I-70 EB AUX FRISCO TO SILVERT	01/13/22	1.00	25000.00	75266.80	85000.00	
NHPP 0761-238		I-76 DAHLIA TO YORK	03/10/22	1.00	18000.00	37343.35	4000.00	
C0761-239								
		WEIGHTED AVERAGE FOR THE FIRST QUARTER		2.00	21500.00	51929.30	44500.00	
2670703-479		I-70 BRIDGE OVER HARLAN	05/05/22	1.00	65000.00	78924.19	85264.05	
		WEIGHTED AVERAGE FOR THE SECOND QUARTER		1.00	65000.00	78924.19	85264.05	
2670703-497		I-70_GENESEE WILDLIFE XING	09/15/22	1.00	142000.00	160488.20	121237.26	
		WEIGHTED AVERAGE FOR THE THIRD QUARTER		1.00	142000.00	160488.20	121237.26	
TRG0253-264		I-25 AND SH 119 PARK-N-RIDE	10/27/22	1.00	65000.00	31686.48	8000.00	
STU0252-457		I-25:ALAMEDA RIVER PH 2.0	11/03/22	1.00	60000.00	187192.03	105000.00	
2670703-487		I-70 BRIDGES OVER WARD ROAD-	12/01/22	1.00	6000.00	118230.32	98100.00	
		WEIGHTED AVERAGE FOR THE FOURTH QUARTER		3.00	43666.67	87888.72	70366.67	
		WEIGHTED AVERAGE FOR THE YEAR		7.00	54428.57	87577.69	72371.62	
===== 206-01786				Shoring (A 6)				LUMP SUM =====
NHPP0702-383		I-70 EB AUX FRISCO TO SILVERT	01/13/22	1.00	25000.00	77066.80	85000.00	
NHPP 0761-238		I-76 DAHLIA TO YORK	03/10/22	1.00	42000.00	37382.97	4000.00	
C0761-239								
		WEIGHTED AVERAGE FOR THE FIRST QUARTER		2.00	33500.00	52645.98	44500.00	
2670703-479		I-70 BRIDGE OVER HARLAN	05/05/22	1.00	65000.00	85503.47	86618.50	
		WEIGHTED AVERAGE FOR THE SECOND QUARTER		1.00	65000.00	85503.47	86618.50	

COLORADO DEPARTMENT OF TRANSPORTATION
 ITEM UNIT COSTS BY PROJECTS -- 2022 COST DATA

11:31 Wednesday, March 8, 2023 97

PROJECT NUMBER	ITEM NUMBER/ PROJECT LOCATION	ITEM DESCRIPTION/ PROJECT LOCATION	DATE LET	UNIT/ QUANTITY	ENGR. EST.	AVERAGE BID	AWARDED BID
===== 206-01786		Shoring (A 6)		LUMP SUM	=====		
2670703-497		I-70_GENESEE WILDLIFE KING	09/15/22	1.00	96000.00	99755.37	99228.20
		WEIGHTED AVERAGE FOR THE THIRD QUARTER		1.00	96000.00	99755.37	99228.20
TRG0253-264		I-25 AND SH 119 PARK-N-RIDE	10/27/22	1.00	65000.00	31973.98	8000.00
STU0252-457		I-25:ALAMEDA RIVER PH 2.0	11/03/22	1.00	60000.00	129759.69	125000.00
2670703-487		I-70 BRIDGES OVER WARD ROAD-	12/01/22	1.00	6000.00	116658.12	89600.00
		WEIGHTED AVERAGE FOR THE FOURTH QUARTER		3.00	43666.67	76772.60	74200.00
		WEIGHTED AVERAGE FOR THE YEAR		7.00	51285.71	74382.57	71063.81
===== 206-01787		Shoring (A 7)		LUMP SUM	=====		
NHPP0702-383		I-70 EB AUX FRISCO TO SILVERT	01/13/22	1.00	25000.00	58891.25	22000.00
		WEIGHTED AVERAGE FOR THE FIRST QUARTER		1.00	25000.00	58891.25	22000.00
2670703-479		I-70 BRIDGE OVER HARLAN	05/05/22	1.00	20000.00	87353.19	80373.69
		WEIGHTED AVERAGE FOR THE SECOND QUARTER		1.00	20000.00	87353.19	80373.69
STU0252-457		I-25:ALAMEDA RIVER PH 2.0	11/03/22	1.00	10000.00	17069.53	32700.00
		WEIGHTED AVERAGE FOR THE FOURTH QUARTER		1.00	10000.00	17069.53	32700.00
		WEIGHTED AVERAGE FOR THE YEAR		3.00	18333.33	62127.43	45024.56
===== 206-01788		Shoring (A 8)		LUMP SUM	=====		
2670703-479		I-70 BRIDGE OVER HARLAN	05/05/22	1.00	20000.00	94561.48	88073.17
		WEIGHTED AVERAGE FOR THE SECOND QUARTER		1.00	20000.00	94561.48	88073.17
		WEIGHTED AVERAGE FOR THE YEAR		1.00	20000.00	94561.48	88073.17

COLORADO DEPARTMENT OF TRANSPORTATION
 ITEM UNIT COSTS BY PROJECTS -- 2022 COST DATA

11:31 Wednesday, March 8, 2023 98

PROJECT NUMBER	ITEM NUMBER/ PROJECT LOCATION	ITEM DESCRIPTION/ PROJECT LOCATION	DATE LET	UNIT/ QUANTITY	ENGR. EST.	AVERAGE BID	AWARDED BID
=====	206-01789	Shoring (A 9)		LUMP SUM	=====		
2670703-479		I-70 BRIDGE OVER HARLAN	05/05/22	1.00	90000.00	87599.07	97733.18
	WEIGHTED	AVERAGE FOR THE SECOND QUARTER		1.00	90000.00	87599.07	97733.18
		WEIGHTED AVERAGE FOR THE YEAR		1.00	90000.00	87599.07	97733.18
=====	206-01790	Shoring (A 10)		LUMP SUM	=====		
2670703-479		I-70 BRIDGE OVER HARLAN	05/05/22	1.00	90000.00	95730.30	94000.00
	WEIGHTED	AVERAGE FOR THE SECOND QUARTER		1.00	90000.00	95730.30	94000.00
		WEIGHTED AVERAGE FOR THE YEAR		1.00	90000.00	95730.30	94000.00
=====	206-01791	Shoring (A 11)		LUMP SUM	=====		
2670703-479		I-70 BRIDGE OVER HARLAN	05/05/22	1.00	50000.00	138220.45	103000.00
	WEIGHTED	AVERAGE FOR THE SECOND QUARTER		1.00	50000.00	138220.45	103000.00
		WEIGHTED AVERAGE FOR THE YEAR		1.00	50000.00	138220.45	103000.00
=====	206-01803	Shoring (A 23)		LUMP SUM	=====		
NHPP0253-275		I-25 EXPRESS LANES SEGMENT 5	03/11/22	1.00	31720.06	33715.23	33715.23
	WEIGHTED	AVERAGE FOR THE FIRST QUARTER		1.00	31720.06	33715.23	33715.23
		WEIGHTED AVERAGE FOR THE YEAR		1.00	31720.06	33715.23	33715.23
=====	206-01804	Shoring (A 24)		LUMP SUM	=====		
NHPP0253-275		I-25 EXPRESS LANES SEGMENT 5	03/11/22	1.00	39247.42	33715.23	33715.23
	WEIGHTED	AVERAGE FOR THE FIRST QUARTER		1.00	39247.42	33715.23	33715.23
		WEIGHTED AVERAGE FOR THE YEAR		1.00	39247.42	33715.23	33715.23
=====	206-01805	Shoring (A 25)		LUMP SUM	=====		
NHPP0253-275		I-25 EXPRESS LANES SEGMENT 5	03/11/22	1.00	36947.87	33715.23	33715.23
	WEIGHTED	AVERAGE FOR THE FIRST QUARTER		1.00	36947.87	33715.23	33715.23
		WEIGHTED AVERAGE FOR THE YEAR		1.00	36947.87	33715.23	33715.23

COLORADO DEPARTMENT OF TRANSPORTATION
ITEM UNIT COSTS BY PROJECTS -- 2022 COST DATA

11:31 Wednesday, March 8, 2023 99

PROJECT NUMBER	ITEM NUMBER/ PROJECT LOCATION	ITEM DESCRIPTION/ PROJECT LOCATION	DATE LET	UNIT/ QUANTITY	ENGR. EST.	AVERAGE BID	AWARDED BID
=====	206-01806	Shoring (A 26)		LUMP SUM	=====		
NHPP0253-275		I-25 EXPRESS LANES SEGMENT 5	03/11/22	1.00	33633.23	33715.23	33715.23
	WEIGHTED AVERAGE FOR THE FIRST QUARTER			1.00	33633.23	33715.23	33715.23
	WEIGHTED AVERAGE FOR THE YEAR			1.00	33633.23	33715.23	33715.23
=====	207-00205	Topsoil		Cubic Yard	=====		
FBR0761-236		I-76 OVER CLR CRK SCOUR MIT	08/25/22	235.00	20.00	41.83	13.00
	WEIGHTED AVERAGE FOR THE THIRD QUARTER			235.00	20.00	41.83	13.00
	WEIGHTED AVERAGE FOR THE YEAR			235.00	20.00	41.83	13.00
=====	207-00210	Stockpile Topsoil		Cubic Yard	=====		
C170A-002		CRITICAL CULVERT CONST. PKG D	10/27/22	396.00	8.00	27.44	18.75
	WEIGHTED AVERAGE FOR THE FOURTH QUARTER			396.00	8.00	27.44	18.75
	WEIGHTED AVERAGE FOR THE YEAR			396.00	8.00	27.44	18.75
=====	207-00305	Wetland Topsoil		Cubic Yard	=====		
NHPP0702-413		VAIL PASS AUX PHASE 1 CAP 2	04/18/22	82.00	115.08	115.08	115.08
	WEIGHTED AVERAGE FOR THE SECOND QUARTER			82.00	115.08	115.08	115.08
FBR0761-236		I-76 OVER CLR CRK SCOUR MIT	08/25/22	78.00	18.00	59.00	26.00
	WEIGHTED AVERAGE FOR THE THIRD QUARTER			78.00	18.00	59.00	26.00
	WEIGHTED AVERAGE FOR THE YEAR			160.00	67.75	73.55	71.65
=====	207-00310	Stockpile Wetland Topsoil		Cubic Yard	=====		
NHPP0931-033		SH93:US6 TO 58TH RESURFACING	12/15/22	50.00	25.00	104.23	25.60
	WEIGHTED AVERAGE FOR THE FOURTH QUARTER			50.00	25.00	104.23	25.60
	WEIGHTED AVERAGE FOR THE YEAR			50.00	25.00	104.23	25.60

COLORADO DEPARTMENT OF TRANSPORTATION
ITEM UNIT COSTS BY PROJECTS -- 2022 COST DATA

11:31 Wednesday, March 8, 2023 100

PROJECT NUMBER	ITEM NUMBER/ PROJECT LOCATION	ITEM DESCRIPTION/ PROJECT LOCATION	DATE LET	UNIT/ QUANTITY	ENGR. EST.	AVERAGE BID	AWARDED BID
=====	207-00700	Topsoil (Onsite)		Cubic Yard	=====		
NH0504-910		US50B L-24-B MIN REP AT MP 40	01/13/22	544.00	10.00	16.76	15.00
NHPP0702-383		I-70 EB AUX FRISCO TO SILVERT	01/13/22	10,350.00	15.00	18.10	14.00
NHPP1601-083			02/03/22	12,298.00	6.00	8.49	9.00
C0762-055			02/17/22	2,581.00	10.00	17.55	1.25
STR0141-031			02/17/22	333.00	50.00	36.67	25.00
NHPP 0761-238		I-76 DAHLIA TO YORK	03/10/22	4,073.00	15.00	15.53	11.00
C0761-239							
WEIGHTED AVERAGE FOR THE FIRST QUARTER				30,179.00	11.20	15.59	10.61
NHPP0702-413		VAIL PASS AUX PHASE 1 CAP 2	04/18/22	4,832.00	30.72	30.72	30.72
STM1151-038		SH115 MP 27 TO MP 38	04/21/22	41,631.00	18.00	9.68	4.81
2670703-479		I-70 BRIDGE OVER HARLAN	05/05/22	1,694.00	10.00	25.47	27.75
STA0712-019		SH 71: Frieight Improvements	05/12/22	7,704.00	12.00	5.08	5.08
STA001A-005		SH1 WELLINGTON SOUTH RESURFAC	05/12/22	10.00	12.00	54.35	35.00
NHC540-017		R2 CHAINUP STA @ KENOSHA/HOOS	05/12/22	3,028.00	17.00	18.33	15.00
CM760-047		COLFAX AND QUAIL	05/12/22	7.00	25.00	110.20	95.00
NHPP 3851-018		US 385 NORTH OF CHEYENNE WELL	05/26/22	2,460.00	12.00	5.13	4.00
FSA0702-409		I-70 VAIL WILDLIFE FENCE PHAS	05/26/22	200.00	130.00	120.00	120.00
FSA3921-019		SH 392 AND WCR 55 ISLANDS	06/02/22	60.00	25.00	31.67	45.00
FSA052A-046		SH52 WCR 37 INTERSECTION IMPR	06/09/22	3,767.00	15.00	13.24	6.30
WEIGHTED AVERAGE FOR THE SECOND QUARTER				65,393.00	17.93	11.12	8.28
NHPP0702-414		VAIL PASS AUX PHASE 1 CAP 3	07/08/22	6,840.00	33.46	33.46	33.46
FBR0702-423		VAIL PASS AUX BE F-12-AT PHAS					
FSA052A-057		SH52 BOX CULVERT EXTENSION (M	08/04/22	161.00	30.00	48.75	36.17
STR0711-022		SH 71 OVER THE ARKANSAS	08/04/22	40.00	17.00	81.67	35.00
ER0502-092		US 50 MP 204 EB MONARCH TRUCK	08/29/22	298.00	30.00	34.30	25.90
BR0343-046		US 34 TIMBER BRIDGE REPL. PKG	08/31/22	4,316.00	29.47	29.56	29.56
FBR0343-047		US 6/US 34 TIMBER BRIDGE REPL					
NHPPR100-266		R1 ESSENTIAL REPAIRS	09/01/22	1,500.00	25.00	31.09	20.77
2670403-065		US40 FLOYD HILL ROUNDABOUTS	09/15/22	587.00	15.00	53.55	95.00
2670703-497		I-70_GENESEE WILDLIFE KING	09/15/22	1,673.00	26.00	24.88	40.12
SHE2873-193		US 287 & CO 52 INTERSECTION I	09/15/22	4,203.00	20.00	21.08	32.00
NHPP0701-231		I-70 SALT WASH BRIDGES SCOUR	09/29/22	3,896.00	40.00	42.21	41.00
WEIGHTED AVERAGE FOR THE THIRD QUARTER				23,514.00	29.78	28.39	34.86
NHPP0701-253		I-70 EAST OF DEBEQUE	10/27/22	589.00	11.20	53.40	52.00

COLORADO DEPARTMENT OF TRANSPORTATION
ITEM UNIT COSTS BY PROJECTS -- 2022 COST DATA

11:31 Wednesday, March 8, 2023 101

PROJECT NUMBER	ITEM NUMBER/ PROJECT LOCATION	ITEM DESCRIPTION/ PROJECT LOCATION	DATE LET	UNIT/ QUANTITY	ENGR. EST.	AVERAGE BID	AWARDED BID
===== 207-00700 Topsoil (Onsite) Cubic Yard =====							
FSAM240-200		SH21B CO SPRINGS SIGNAL REPLA	10/27/22	50.00	60.00	170.25	72.00
C170A-002		CRITICAL CULVERT CONST. PKG D	10/27/22	396.00	40.00	29.31	18.75
TRG0253-264		I-25 AND SH 119 PARK-N-RIDE	10/27/22	9,820.00	10.00	14.46	8.00
STA3852-015		US 385 HOLYOKE NORTH	10/27/22	21,156.00	5.00	3.75	3.75
STU0252-457		I-25:ALAMEDA RIVER PH 2.0	11/03/22	2,912.00	45.00	33.18	23.00
SHE0242-087		US 24 SAFETY IMPRVMENTS, E OF	11/03/22	670.00	13.40	49.39	45.18
NHPP0853-126		US85C: PLATTEVILLE NORTH MP (11/10/22	565.00	30.00	26.20	13.30
C5502-097		US550 MP 117.28-126.06	11/17/22	34,848.00	20.00	13.08	15.20
STRC090-011		US 50B AND SH71/CR18 INTERSEC	11/17/22	320.00	25.00	44.05	52.10
STAM420-001		US 285 AT HWY 9C IMPROVEMENTS	12/01/22	2,689.00	15.00	15.73	22.39
BR2854-148		INTERSECTION OF US 285 & SH 9					
STM0091-046		ADA RAMP IMPROVEMENTS - FAIRP					
STA0711-021		SH71: REGION LINE NORTH	12/01/22	242.00	24.00	41.77	26.00
2670703-487		I-70 BRIDGES OVER WARD ROAD-	12/01/22	1,252.00	45.10	30.59	18.00
NHPP0701-252		I-70 RIFLE TO SILT SLAB REPLA	12/01/22	40.00	15.80	125.50	66.00
IM025A-050		I25-MP103.9 - INTERSECTION DR	12/01/22	3,023.00	30.00	25.00	14.00
NHPP0063-048		US6 / 20 ROAD INTERSECTION IM	12/15/22	2,453.00	35.00	22.40	18.00
NHPP0931-033		SH93:US6 TO 58TH RESURFACING	12/15/22	716.00	20.00	36.78	18.45
NHPP0502-090		SH 50 MP 134.6-136 GUNNISON C	12/22/22	7,260.00	35.00	14.74	5.77
STA0361-129		US 36: HYGIENE RD AND NELSON	12/22/22	575.00	30.00	32.36	18.12
BR012A-048		CO 12 STRUCTURE P-17-F AT MP	12/22/22	304.00	30.00	95.37	135.00
STA385A-016		SH 385 MP 97.76	12/22/22	1,580.00	15.00	31.00	20.00
		WEIGHTED AVERAGE FOR THE FOURTH QUARTER		91,460.00	18.47	16.62	13.99
		WEIGHTED AVERAGE FOR THE YEAR		210,546.00	18.52	15.56	14.06
===== 207-00702 Topsoil (Offsite) Cubic Yard =====							
NHPP 0761-238		I-76 DAHLIA TO YORK	03/10/22	118.00	50.00	53.69	55.00
C0761-239							
BRC040-057			03/17/22	80.00	50.00	262.75	140.00
NHM765-007			03/31/22	10.00	100.00	183.24	190.76
		WEIGHTED AVERAGE FOR THE FIRST QUARTER		208.00	52.40	108.39	94.22
NH0504-911			04/07/22	1,500.00	82.00	56.05	47.10
		WEIGHTED AVERAGE FOR THE SECOND QUARTER		1,500.00	82.00	56.05	47.10
NHPP0063-054		US 6 FROM I70-B TO 33 RD. (MP	08/18/22	210.00	40.00	213.73	170.00
		WEIGHTED AVERAGE FOR THE THIRD QUARTER		210.00	40.00	213.73	170.00

COLORADO DEPARTMENT OF TRANSPORTATION
ITEM UNIT COSTS BY PROJECTS -- 2022 COST DATA

11:31 Wednesday, March 8, 2023 102

PROJECT NUMBER	ITEM NUMBER/ PROJECT LOCATION	ITEM DESCRIPTION/ PROJECT LOCATION	DATE LET	UNIT/ QUANTITY	ENGR. EST.	AVERAGE BID	AWARDED BID
===== 207-00702		Topsoil (Offsite)		Cubic Yard	=====		
SHE0242-087		US 24 SAFETY IMPRVMENTS, E OF	11/03/22	150.00	76.10	113.32	134.95
STAM420-001		US 285 AT HWY 9C IMPROVEMENTS	12/01/22	20.00	76.10	155.16	197.92
BR2854-148		INTERSECTION OF US 285 & SH 9					
STM0091-046		ADA RAMP IMPROVEMENTS - FAIRP					
NHPP0931-033		SH93:US6 TO 58TH RESURFACING	12/15/22	355.00	120.00	86.40	45.10
STR096A-050		SH 96 MP 168.99 TO 193.77	12/22/22	444.00	140.00	103.67	90.00
		WEIGHTED AVERAGE FOR THE FOURTH QUARTER		969.00	121.46	102.64	87.37
		WEIGHTED AVERAGE FOR THE YEAR		2,887.00	90.06	92.00	73.05
===== 207-00703		Topsoil (Wetlnd)		Cubic Yard	=====		
NH0504-910		US50B L-24-B MIN REP AT MP 40	01/13/22	17.00	60.00	104.39	46.25
		WEIGHTED AVERAGE FOR THE FIRST QUARTER		17.00	60.00	104.39	46.25
NHPP0702-414		VAIL PASS AUX PHASE 1 CAP 3	07/08/22	900.00	47.66	47.66	47.66
FBR0702-423		VAIL PASS AUX BE F-12-AT PHAS					
ER0502-092		US 50 MP 204 EB MONARCH TRUCK	08/29/22	100.00	30.00	54.24	50.73
		WEIGHTED AVERAGE FOR THE THIRD QUARTER		1,000.00	45.89	49.30	47.96
NHPP0931-033		SH93:US6 TO 58TH RESURFACING	12/15/22	50.00	50.00	78.97	41.00
STA385A-016		SH 385 MP 97.76	12/22/22	150.00	20.00	82.00	80.00
		WEIGHTED AVERAGE FOR THE FOURTH QUARTER		200.00	27.50	81.24	70.25
		WEIGHTED AVERAGE FOR THE YEAR		1,217.00	43.07	64.77	51.60
===== 207-00704		Sub Soil Prep		Sq Yard	=====		
NH0504-910		US50B L-24-B MIN REP AT MP 40	01/13/22	12,100.00	2.00	1.69	1.00
NHPP0702-383		I-70 EB AUX FRISCO TO SILVERT	01/13/22	1,320.00	5.00	3.43	2.00

COLORADO DEPARTMENT OF TRANSPORTATION
ITEM UNIT COSTS BY PROJECTS -- 2022 COST DATA

11:31 Wednesday, March 8, 2023 103

PROJECT NUMBER	ITEM NUMBER/ PROJECT LOCATION	ITEM DESCRIPTION/ PROJECT LOCATION	DATE LET	UNIT/ QUANTITY	ENGR. EST.	AVERAGE BID	AWARDED BID
=====	207-00704	Sub Soil Prep		Sq Yard	=====	=====	=====
NHPP1601-083			02/03/22	57,112.00	0.50	1.66	2.00
C0762-055			02/17/22	14,520.00	2.00	2.03	2.00
NHPP 0761-238	I-76 DAHLIA TO YORK		03/10/22	25,091.00	2.00	1.37	2.50
C0761-239							
WEIGHTED AVERAGE FOR THE FIRST QUARTER				110,143.00	1.26	1.61	2.00
STM1151-038		SH115 MP 27 TO MP 38	04/21/22	249,787.00	0.50	0.50	0.52
2670703-479		I-70 BRIDGE OVER HARLAN	05/05/22	3,872.00	2.50	4.01	3.60
STA0712-019		SH 71: Frieight Improvements	05/12/22	46,222.00	2.00	0.37	0.37
NHC540-017		R2 CHAINUP STA @ KENOSHA/HOOS	05/12/22	15,004.00	2.50	1.92	0.75
NHPP 3851-018		US 385 NORTH OF CHEYENNE WELL	05/26/22	14,762.00	2.00	1.50	2.00
WEIGHTED AVERAGE FOR THE SECOND QUARTER				329,647.00	0.89	0.62	0.61
FSA052A-057		SH52 BOX CULVERT EXTENSION (M	08/04/22	968.00	2.50	8.24	6.85
STR0711-022		SH 71 OVER THE ARKANSAS	08/04/22	300.00	2.00	25.50	7.00
BR0343-046		US 34 TIMBER BRIDGE REPL. PKG	08/31/22	25,894.00	2.41	2.90	2.90
FBR0343-047		US 6/US 34 TIMBER BRIDGE REPL					
2670403-065		US40 FLOYD HILL ROUNDABOUTS	09/15/22	1,207.00	3.00	9.62	5.00
NHPP0701-231		I-70 SALT WASH BRIDGES SCOUR	09/29/22	23,377.00	2.50	4.40	1.50
WEIGHTED AVERAGE FOR THE THIRD QUARTER				51,746.00	2.46	4.53	2.41
C170A-002		CRITICAL CULVERT CONST. PKG D	10/27/22	2,372.00	3.00	5.97	1.88
TRG0253-264		I-25 AND SH 119 PARK-N-RIDE	10/27/22	58,919.00	2.00	0.91	0.30
STA3852-015		US 385 HOLYOKE NORTH	10/27/22	190,406.00	0.60	1.05	1.05
STU0252-457		I-25:ALAMEDA RIVER PH 2.0	11/03/22	17,476.00	2.00	2.92	2.30
SHE0242-087		US 24 SAFETY IMPRVMENTS, E OF	11/03/22	4,017.00	3.00	6.71	3.62
NHPP0853-126		US85C: PLATTEVILLE NORTH MP (11/10/22	3,388.00	3.80	2.52	1.20
STAM420-001		US 285 AT HWY 9C IMPROVEMENTS	12/01/22	24,200.00	1.00	1.31	1.55
BR2854-148		INTERSECTION OF US 285 & SH 9					
STM0091-046		ADA RAMP IMPROVEMENTS - FAIRP					
STA0711-021		SH71: REGION LINE NORTH	12/01/22	1,460.00	1.60	2.37	1.00
2670703-487		I-70 BRIDGES OVER WARD ROAD-	12/01/22	10,572.00	5.00	1.84	3.30
IM025A-050		I25-MP103.9 - INTERSECTION DR	12/01/22	12,100.00	2.00	1.33	0.40
NHPP0931-033		SH93:US6 TO 58TH RESURFACING	12/15/22	7,580.00	2.00	3.10	6.15
BR012A-048		CO 12 STRUCTURE P-17-F AT MP	12/22/22	4,187.00	5.00	3.15	3.25
STA385A-016		SH 385 MP 97.76	12/22/22	14,520.00	1.00	2.31	1.00
WEIGHTED AVERAGE FOR THE FOURTH QUARTER				351,197.00	1.29	1.52	1.21
WEIGHTED AVERAGE FOR THE YEAR				842,733.00	1.20	1.22	1.16

COLORADO DEPARTMENT OF TRANSPORTATION
ITEM UNIT COSTS BY PROJECTS -- 2022 COST DATA

11:31 Wednesday, March 8, 2023 104

PROJECT NUMBER	ITEM NUMBER/ PROJECT LOCATION	ITEM DESCRIPTION/ PROJECT LOCATION	DATE LET	UNIT/ QUANTITY	ENGR. EST.	AVERAGE BID	AWARDED BID
=====	207-00706	Seeding Media		Cubic Yard	=====		
2670703-487		I-70 BRIDGES OVER WARD ROAD-	12/01/22	1,289.00	50.00	32.50	19.00
		WEIGHTED AVERAGE FOR THE FOURTH QUARTER		1,289.00	50.00	32.50	19.00
		WEIGHTED AVERAGE FOR THE YEAR		1,289.00	50.00	32.50	19.00
=====	208-00002	Erosion Log Type 1 (12 In)		Lin Foot	=====		
NHPP0702-383		I-70 EB AUX FRISCO TO SILVERT	01/13/22	10,960.00	6.25	6.37	10.50
NHPP1601-083			02/03/22	11,032.00	10.00	5.91	6.00
STR0141-031			02/17/22	500.00	8.00	10.47	10.41
NHPP0063-063			02/24/22	150.00	6.00	10.33	15.00
NHPP 0761-238		I-76 DAHLIA TO YORK	03/10/22	420.00	6.00	6.53	5.00
C0761-239							
STR160A-034		US160A LA VETA PASS EAST SURF	03/17/22	1,000.00	5.00	6.16	5.31
STR R500-171		Various locations on SH 141 a	03/17/22	100.00	6.00	13.79	30.00
STR092A-031			03/17/22	1,850.00	8.00	6.00	6.00
		WEIGHTED AVERAGE FOR THE FIRST QUARTER		26,012.00	7.94	6.36	8.08
NH0504-911			04/07/22	300.00	5.00	4.08	2.90
NHPP0702-413		VAIL PASS AUX PHASE 1 CAP 2	04/18/22	10,000.00	5.67	5.67	5.67
STM1151-038		SH115 MP 27 TO MP 38	04/21/22	68,080.00	4.50	5.87	4.24
2670703-479		I-70 BRIDGE OVER HARLAN	05/05/22	120.00	5.00	6.11	6.63
ER0702-420		PR I-70 GWC MATERIAL FLOWS 20	05/06/22	1,000.00	6.00	7.18	8.35
STA0712-019		SH 71: Frieght Improvements	05/12/22	4,300.00	5.00	4.88	4.88
STA001A-005		SH1 WELLINGTON SOUTH RESURFAC	05/12/22	300.00	5.00	5.30	5.00
NHC540-017		R2 CHAINUP STA @ KENOSHA/HOOS	05/12/22	1,580.00	5.00	7.57	7.70
C0852-120		Rehabilitation of Culvert by	05/26/22	850.00	10.00	4.00	4.00
FSA0702-409		I-70 VAIL WILDLIFE FENCE PHAS	05/26/22	1,000.00	11.00	10.00	10.00
ITS 0741-024		VMS SIGN INSTALLATIONS AND VS	06/02/22	1,400.00	7.00	13.00	12.00
FSA3921-019		SH 392 AND WCR 55 ISLANDS	06/02/22	200.00	5.00	7.90	7.50
NHPP072A-047		SH-72 RESURFACING: I-70 TO IN	06/09/22	100.00	5.00	31.11	31.11
FSA052A-046		SH52 WCR 37 INTERSECTION IMPR	06/09/22	9,660.00	8.00	5.25	5.15
MTCE0253-291		I-25 SIGN REPLACEMENT PHASE 2	06/16/22	125.00	10.00	9.66	9.32
		WEIGHTED AVERAGE FOR THE SECOND QUARTER		99,015.00	5.16	5.87	4.80
NHPP0702-414		VAIL PASS AUX PHASE 1 CAP 3	07/08/22	7,500.00	7.16	7.16	7.16

PROJECT NUMBER	ITEM NUMBER/ PROJECT LOCATION	ITEM DESCRIPTION/ PROJECT LOCATION	DATE LET	UNIT/ QUANTITY	ENGR. EST.	AVERAGE BID	AWARDED BID
=====	208-00002	Erosion Log Type 1 (12 In)		Lin Foot	=====		
FBR0702-423		VAIL PASS AUX BE F-12-AT PHAS					
FSA052A-057		SH52 BOX CULVERT EXTENSION (M	08/04/22	600.00	7.00	6.94	6.50
STR0711-022		SH 71 OVER THE ARKANSAS	08/04/22	30.00	4.84	56.17	15.00
NHPP0063-054		US 6 FROM I70-B TO 33 RD. (MP	08/18/22	2,150.00	4.00	6.27	4.75
FBR0761-236		I-76 OVER CLR CRK SCOUR MIT	08/25/22	2,171.00	8.00	5.97	7.30
CL211-099		SH 121 NORTH SGA SIGNALS	08/25/22	96.00	10.00	18.00	25.00
ER0502-092		US 50 MP 204 EB MONARCH TRUCK	08/29/22	875.00	10.00	8.01	7.03
BR0343-046		US 34 TIMBER BRIDGE REPL. PKG	08/31/22	8,536.00	8.56	10.90	10.90
FBR0343-047		US 6/US 34 TIMBER BRIDGE REPL					
NHPPR100-266		R1 ESSENTIAL REPAIRS	09/01/22	700.00	10.00	6.58	8.40
ER0253-297		WCR 34 BRIDGE OVER I-25(MM 24	09/14/22	40.00	10.00	17.49	21.00
2670403-065		US40 FLOYD HILL ROUNDABOUTS	09/15/22	2,351.00	6.00	8.95	7.00
2670703-497		I-70 GENESEE WILDLIFE XING	09/15/22	5,000.00	6.00	6.76	8.68
SHE2873-193		US 287 & CO 52 INTERSECTION I	09/15/22	20,395.00	6.00	6.29	4.86
NHPP0701-231		I-70 SALT WASH BRIDGES SCOUR	09/29/22	1,561.00	6.00	10.24	15.00
		WEIGHTED AVERAGE FOR THE THIRD QUARTER		52,005.00	6.73	6.82	7.21
C0831-126		SH83 EL PASO COUNTY TO BAYOU	10/13/22	300.00	8.00	11.00	12.00
NHPP0701-253		I-70 EAST OF DEBEQUE	10/27/22	100.00	7.00	18.13	31.00
FSAM240-200		SH21B CO SPRINGS SIGNAL REPLA	10/27/22	250.00	6.00	12.69	13.75
C5502-111		US 550 MP 81 AND 89 RED MOUNT	10/27/22	40.00	15.00	27.50	15.00
C170A-002		CRITICAL CULVERT CONST. PKG D	10/27/22	900.00	6.50	7.75	7.50
TRG0253-264		I-25 AND SH 119 PARK-N-RIDE	10/27/22	5,136.00	5.00	5.80	6.00
STU0252-457		I-25:ALAMEDA RIVER PH 2.0	11/03/22	8,000.00	15.00	6.83	11.50
STR064A-010		SH 64 AND SH 13 AT MEEKER	11/10/22	800.00	8.50	5.83	6.00
NHPP0853-126		US85C: PLATTEVILLE NORTH MP (11/10/22	230.00	8.00	8.08	6.25
C5502-097		US550 MP 117.28-126.06	11/17/22	3,500.00	6.00	6.79	5.65
MPR200-280		PUEBLO AREA	11/17/22	1,000.00	5.00	5.13	8.25
STRC090-011		US 50B AND SH71/CR18 INTERSEC	11/17/22	750.00	8.00	7.30	8.10
STAM420-001		US 285 AT HWY 9C IMPROVEMENTS	12/01/22	16,622.00	5.00	5.70	6.75
BR2854-148		INTERSECTION OF US 285 & SH 9					
STM0091-046		ADA RAMP IMPROVEMENTS - FAIRP					
STA0711-021		SH71: REGION LINE NORTH	12/01/22	350.00	6.00	6.48	8.00
STR114A-015		SH114 SILLSVILLE SOUTH TO MP3	12/01/22	800.00	10.00	7.85	10.00
2670703-487		I-70 BRIDGES OVER WARD ROAD-	12/01/22	400.00	5.00	6.96	5.20
NHPP0701-252		I-70 RIFLE TO SILT SLAB REPLA	12/01/22	150.00	12.00	12.75	13.50
IM025A-050		I25-MP103.9 - INTERSECTION DR	12/01/22	6,160.00	5.00	6.00	5.00
STR109A-019		M-22-AY BRIDGE REHAB ON SH109	12/01/22	788.00	5.00	7.73	8.45
NHPP0021-041		SH2 RESURFACING MLK TO 52ND	12/01/22	250.00	7.00	9.98	10.20
NHPP083A-046		SH83 RESURFACING STROH RD TO	12/08/22	2,365.00	5.00	6.17	5.73
NHPP0063-048		US6 / 20 ROAD INTERSECTION IM	12/15/22	3,270.00	7.00	7.29	7.00
NHPP0931-033		SH93:US6 TO 58TH RESURFACING	12/15/22	800.00	5.00	5.40	4.70
NHPP0502-090		SH 50 MP 134.6-136 GUNNISON C	12/22/22	500.00	10.00	6.75	8.14
STR0092-024		SH 9 North of Silverthorne	12/22/22	200.00	25.00	6.13	5.75

COLORADO DEPARTMENT OF TRANSPORTATION
ITEM UNIT COSTS BY PROJECTS -- 2022 COST DATA

11:31 Wednesday, March 8, 2023 106

PROJECT NUMBER	ITEM NUMBER/ PROJECT LOCATION	ITEM DESCRIPTION/ PROJECT LOCATION	DATE LET	UNIT/ QUANTITY	ENGR. EST.	AVERAGE BID	AWARDED BID
=====	208-00002	Erosion Log Type 1 (12 In)		Lin Foot	=====		
STA0361-129		US 36: HYGIENE RD AND NELSON	12/22/22	1,480.00	8.50	5.87	5.65
STR096A-050		SH 96 MP 168.99 TO 193.77	12/22/22	120.00	7.90	9.53	12.00
	WEIGHTED AVERAGE FOR THE FOURTH QUARTER			55,261.00	7.11	6.27	7.26
	WEIGHTED AVERAGE FOR THE YEAR			232,293.00	6.29	6.22	6.30
=====	208-00004	Silt Berm		Lin Foot	=====		
STA0712-019		SH 71: Frieght Improvements	05/12/22	12.00	75.00	16.04	16.04
NHC540-017		R2 CHAINUP STA @ KENOSHA/HOOS	05/12/22	1,000.00	0.50	12.00	19.00
	WEIGHTED AVERAGE FOR THE SECOND QUARTER			1,012.00	1.38	12.02	18.96
	WEIGHTED AVERAGE FOR THE YEAR			1,012.00	1.38	12.02	18.96
=====	208-00008	Erosion Log Type 2 (12 In)		Lin Foot	=====		
NH0504-911			04/07/22	300.00	5.57	6.65	5.80
	WEIGHTED AVERAGE FOR THE SECOND QUARTER			300.00	5.57	6.65	5.80
SHE0242-087		US 24 SAFETY IMPRVMENTS, E OF	11/03/22	3,115.00	8.00	8.95	9.85
	WEIGHTED AVERAGE FOR THE FOURTH QUARTER			3,115.00	8.00	8.95	9.85
	WEIGHTED AVERAGE FOR THE YEAR			3,415.00	7.79	8.81	9.49
=====	208-00009	Erosion Log Type 2 (18 In)		Lin Foot	=====		
STA0252-459			02/03/22	900.00	10.00	12.67	11.30
NHM765-007			03/31/22	100.00	8.00	22.31	16.19
	WEIGHTED AVERAGE FOR THE FIRST QUARTER			1,000.00	9.80	13.64	11.79
2670703-497		I-70_GENESEE WILDLIFE XING	09/15/22	50.00	7.00	14.70	22.76
	WEIGHTED AVERAGE FOR THE THIRD QUARTER			50.00	7.00	14.70	22.76

COLORADO DEPARTMENT OF TRANSPORTATION
 ITEM UNIT COSTS BY PROJECTS -- 2022 COST DATA

11:31 Wednesday, March 8, 2023 107

PROJECT NUMBER	ITEM NUMBER/ PROJECT LOCATION	ITEM DESCRIPTION/ PROJECT LOCATION	DATE LET	UNIT/ QUANTITY	ENGR. EST.	AVERAGE BID	AWARDED BID
===== 208-00009		Erosion Log Type 2 (18 In)		Lin Foot	=====		
SHE0242-087		US 24 SAFETY IMPRVMENTS, E OF	11/03/22	330.00	14.00	15.17	16.52
		WEIGHTED AVERAGE FOR THE FOURTH QUARTER		330.00	14.00	15.17	16.52
		WEIGHTED AVERAGE FOR THE YEAR		1,380.00	10.70	14.07	13.32
===== 208-00011		Erosion Bales (Weed Free)		Each	=====		
NH0504-910		US50B L-24-B MIN REP AT MP 40	01/13/22	20.00	10.00	37.62	43.75
		WEIGHTED AVERAGE FOR THE FIRST QUARTER		20.00	10.00	37.62	43.75
SHE0242-087		US 24 SAFETY IMPRVMENTS, E OF	11/03/22	48.00	40.00	41.88	34.64
BR012A-048		CO 12 STRUCTURE P-17-F AT MP	12/22/22	20.00	40.00	65.57	75.00
STA385A-016		SH 385 MP 97.76	12/22/22	10.00	50.00	54.25	20.00
		WEIGHTED AVERAGE FOR THE FOURTH QUARTER		78.00	41.28	48.32	43.11
		WEIGHTED AVERAGE FOR THE YEAR		98.00	34.90	43.86	43.24
===== 208-00012		Erosion Log Type 1 (9 In)		Lin Foot	=====		
M R100-351		FY22 R1 SIGN STRUCTURE REPLAC	03/17/22	200.00	22.00	19.00	25.00
		WEIGHTED AVERAGE FOR THE FIRST QUARTER		200.00	22.00	19.00	25.00
NH0504-911			04/07/22	300.00	13.00	6.90	10.80
		WEIGHTED AVERAGE FOR THE SECOND QUARTER		300.00	13.00	6.90	10.80
STR0711-022		SH 71 OVER THE ARKANSAS	08/04/22	30.00	5.80	56.17	15.00
		WEIGHTED AVERAGE FOR THE THIRD QUARTER		30.00	5.80	56.17	15.00
		WEIGHTED AVERAGE FOR THE YEAR		530.00	15.99	15.41	16.40

COLORADO DEPARTMENT OF TRANSPORTATION
ITEM UNIT COSTS BY PROJECTS -- 2022 COST DATA

11:31 Wednesday, March 8, 2023 108

PROJECT NUMBER	ITEM NUMBER/ PROJECT LOCATION	ITEM DESCRIPTION/ PROJECT LOCATION	DATE LET	UNIT/ QUANTITY	ENGR. EST.	AVERAGE BID	AWARDED BID
===== 208-00013		Erosion Log Type 1 (20 In)		Lin Foot	=====		
NH0504-910		US50B L-24-B MIN REP AT MP 40	01/13/22	790.00	6.00	8.71	8.75
NHPP0702-383		I-70 EB AUX FRISCO TO SILVERT	01/13/22	3,460.00	8.90	8.73	13.00
		WEIGHTED AVERAGE FOR THE FIRST QUARTER		4,250.00	8.36	8.73	12.21
NH0504-911			04/07/22	300.00	8.00	9.00	8.00
NHPP0702-413		VAIL PASS AUX PHASE 1 CAP 2	04/18/22	100.00	23.61	23.61	23.61
ER0702-420		PR I-70 GWC MATERIAL FLOWS 20	05/06/22	1,000.00	10.00	11.00	12.00
C0852-120		Rehabilitation of Culvert by	05/26/22	300.00	10.00	7.00	7.00
NHPP072A-047		SH-72 RESURFACING: I-70 TO IN	06/09/22	100.00	8.00	33.70	33.70
		WEIGHTED AVERAGE FOR THE SECOND QUARTER		1,800.00	10.31	11.36	12.35
NHPP0702-414		VAIL PASS AUX PHASE 1 CAP 3	07/08/22	1,000.00	12.11	12.11	12.11
FBR0702-423		VAIL PASS AUX BE F-12-AT PHAS					
NHPPR100-266		R1 ESSENTIAL REPAIRS	09/01/22	100.00	16.00	14.42	13.72
2670403-065		US40 FLOYD HILL ROUNDABOUTS	09/15/22	60.00	10.00	11.51	11.00
NHPP0701-231		I-70 SALT WASH BRIDGES SCOUR	09/29/22	2,755.00	8.00	11.63	15.00
		WEIGHTED AVERAGE FOR THE THIRD QUARTER		3,915.00	9.28	11.81	14.17
2670703-487		I-70 BRIDGES OVER WARD ROAD-	12/01/22	60.00	12.00	14.67	8.10
NHPP0931-033		SH93:US6 TO 58TH RESURFACING	12/15/22	400.00	8.00	9.35	6.75
NHPP0502-090		SH 50 MP 134.6-136 GUNNISON C	12/22/22	2,180.00	12.00	9.52	9.37
BR012A-048		CO 12 STRUCTURE P-17-F AT MP	12/22/22	400.00	6.00	11.53	15.00
STA385A-016		SH 385 MP 97.76	12/22/22	2,000.00	7.00	11.25	10.00
		WEIGHTED AVERAGE FOR THE FOURTH QUARTER		5,040.00	9.22	10.30	9.84
		WEIGHTED AVERAGE FOR THE YEAR		15,005.00	9.13	9.88	11.94
===== 208-00016		Erosion Log Type 1 (Special) (12 In)		Lin Foot	=====		
NHPP 3851-018		US 385 NORTH OF CHEYENNE WELL	05/26/22	900.00	10.00	7.75	8.00
		WEIGHTED AVERAGE FOR THE SECOND QUARTER		900.00	10.00	7.75	8.00

COLORADO DEPARTMENT OF TRANSPORTATION
ITEM UNIT COSTS BY PROJECTS -- 2022 COST DATA

11:31 Wednesday, March 8, 2023 109

PROJECT NUMBER	ITEM NUMBER/ PROJECT LOCATION	ITEM DESCRIPTION/ PROJECT LOCATION	DATE LET	UNIT/ QUANTITY	ENGR. EST.	AVERAGE BID	AWARDED BID
=====	208-00016	Erosion Log Type 1 (Special) (12 In)		Lin Foot	=====		
STA3852-015		US 385 HOLYOKE NORTH	10/27/22	2,475.00	6.00	5.75	5.75
		WEIGHTED AVERAGE FOR THE FOURTH QUARTER		2,475.00	6.00	5.75	5.75
		WEIGHTED AVERAGE FOR THE YEAR		3,375.00	7.07	6.59	6.35
=====	208-00017	Erosion Log Type 2 BioD Netting (12 In)		Lin Foot	=====		
C0762-055			02/17/22	4,980.00	5.00	7.84	9.50
		WEIGHTED AVERAGE FOR THE FIRST QUARTER		4,980.00	5.00	7.84	9.50
		WEIGHTED AVERAGE FOR THE YEAR		4,980.00	5.00	7.84	9.50
=====	208-00020	Silt Fence		Lin Foot	=====		
NH0504-910		US50B L-24-B MIN REP AT MP 40	01/13/22	200.00	4.00	3.79	2.50
NHPP1601-083			02/03/22	1,547.00	5.00	4.57	3.00
STA0252-459			02/03/22	5,000.00	1.69	3.24	1.30
NHPP 0761-238		I-76 DAHLIA TO YORK	03/10/22	16,270.00	2.25	2.04	1.25
C0761-239							
STR R500-171		Various locations on SH 141 a	03/17/22	100.00	3.00	3.58	5.00
		WEIGHTED AVERAGE FOR THE FIRST QUARTER		23,117.00	2.33	2.23	1.40
NH0504-911			04/07/22	4,600.00	5.00	1.50	1.50
2670703-479		I-70 BRIDGE OVER HARLAN	05/05/22	1,455.00	2.50	1.65	1.60
NHC540-017		R2 CHAINUP STA @ KENOSHA/HOOS	05/12/22	1,580.00	4.00	6.05	3.15
		WEIGHTED AVERAGE FOR THE SECOND QUARTER		7,635.00	4.32	2.51	1.86
STR0711-022		SH 71 OVER THE ARKANSAS	08/04/22	200.00	2.00	14.25	5.75
FBR0761-236		I-76 OVER CLR CRK SCOUR MIT	08/25/22	500.00	2.00	2.48	3.50
ER0253-297		WCR 34 BRIDGE OVER I-25(MM 24	09/14/22	200.00	3.00	3.32	2.10

COLORADO DEPARTMENT OF TRANSPORTATION
ITEM UNIT COSTS BY PROJECTS -- 2022 COST DATA

11:31 Wednesday, March 8, 2023 110

PROJECT NUMBER	ITEM NUMBER/ PROJECT LOCATION	ITEM DESCRIPTION/ PROJECT LOCATION	DATE LET	UNIT/ QUANTITY	ENGR. EST.	AVERAGE BID	AWARDED BID
===== 208-00020		Silt Fence		Lin Foot			
SHE2873-193		US 287 & CO 52 INTERSECTION I	09/15/22	1,600.00	2.10	3.08	1.32
		WEIGHTED AVERAGE FOR THE THIRD QUARTER		2,500.00	2.14	3.56	2.17
STA207A-004		Resurfacing SH207A MANZANOLA	10/27/22	2,600.00	4.00	3.42	3.75
C170A-002		CRITICAL CULVERT CONST. PKG D	10/27/22	825.00	3.00	3.06	2.25
TRG0253-264		I-25 AND SH 119 PARK-N-RIDE	10/27/22	100.00	2.00	5.19	8.00
SHE0242-087		US 24 SAFETY IMPRVMTS, E OF	11/03/22	1,750.00	2.25	2.21	1.62
STRC090-011		US 50B AND SH71/CR18 INTERSEC	11/17/22	1,200.00	2.50	3.23	2.45
STAM420-001		US 285 AT HWY 9C IMPROVEMENTS	12/01/22	250.00	1.50	3.63	5.81
BR2854-148		INTERSECTION OF US 285 & SH 9					
STM0091-046		ADA RAMP IMPROVEMENTS - FAIRP					
2670703-487		I-70 BRIDGES OVER WARD ROAD-	12/01/22	4,099.00	7.60	2.57	1.40
IM025A-050		I25-MP103.9 - INTERSECTION DR	12/01/22	870.00	2.00	2.87	1.60
STR109A-019		M-22-AY BRIDGE REHAB ON SH109	12/01/22	1,490.00	3.00	3.66	5.31
BR012A-048		CO 12 STRUCTURE P-17-F AT MP	12/22/22	400.00	3.00	6.69	10.00
STA385A-016		SH 385 MP 97.76	12/22/22	500.00	5.00	4.25	6.00
		WEIGHTED AVERAGE FOR THE FOURTH QUARTER		14,084.00	4.36	2.66	2.52
		WEIGHTED AVERAGE FOR THE YEAR		47,336.00	3.25	2.46	1.99
===== 208-00021		Silt Fence (Reinf)		Lin Foot			
STA 067A-048		Hwy 67A MP 0.00 TO MP 11.05 I	03/03/22	1,500.00	5.00	5.06	5.00
BRC040-057			03/17/22	706.00	10.00	4.76	3.54
		WEIGHTED AVERAGE FOR THE FIRST QUARTER		2,206.00	6.60	4.94	4.53
NHPP0702-413		VAIL PASS AUX PHASE 1 CAP 2	04/18/22	100.00	16.09	16.09	16.09
STM1151-038		SH115 MP 27 TO MP 38	04/21/22	4,545.00	3.00	5.90	3.25
2670703-479		I-70 BRIDGE OVER HARLAN	05/05/22	100.00	3.00	4.97	5.58
C0852-120		Rehabilitation of Culvert by	05/26/22	300.00	10.00	4.00	4.00
		WEIGHTED AVERAGE FOR THE SECOND QUARTER		5,045.00	3.68	5.90	3.60
NHPP0702-414		VAIL PASS AUX PHASE 1 CAP 3	07/08/22	100.00	22.35	22.35	22.35

COLORADO DEPARTMENT OF TRANSPORTATION
ITEM UNIT COSTS BY PROJECTS -- 2022 COST DATA

11:31 Wednesday, March 8, 2023 111

PROJECT NUMBER	ITEM NUMBER/ PROJECT LOCATION	ITEM DESCRIPTION/ PROJECT LOCATION	DATE LET	UNIT/ QUANTITY	ENGR. EST.	AVERAGE BID	AWARDED BID
=====	208-00021	Silt Fence (Reinf)		Lin Foot	=====		
FBR0702-423		VAIL PASS AUX BE F-12-AT PHAS					
ER0253-297		WCR 34 BRIDGE OVER I-25(MM 24	09/14/22	100.00	6.00	7.40	8.00
2670403-065		US40_FLOYD HILL ROUNDABOUTS	09/15/22	386.00	5.00	7.38	7.00
		WEIGHTED AVERAGE FOR THE THIRD QUARTER		586.00	8.13	8.29	9.79
STU0252-457		I-25:ALAMEDA RIVER PH 2.0	11/03/22	792.00	8.00	7.15	9.00
STAM420-001		US 285 AT HWY 9C IMPROVEMENTS	12/01/22	850.00	3.50	5.83	6.41
BR2854-148		INTERSECTION OF US 285 & SH 9					
STM0091-046		ADA RAMP IMPROVEMENTS - FAIRP					
STA385A-016		SH 385 MP 97.76	12/22/22	1,500.00	7.00	7.75	6.00
		WEIGHTED AVERAGE FOR THE FOURTH QUARTER		3,142.00	6.31	7.07	6.87
		WEIGHTED AVERAGE FOR THE YEAR		10,979.00	5.25	6.14	5.05
=====	208-00023	Erosion Log (Type 3) (12 In)		Lin Foot	=====		
STA0252-459			02/03/22	200.00	7.13	5.84	5.08
		WEIGHTED AVERAGE FOR THE FIRST QUARTER		200.00	7.13	5.84	5.08
NHPP0705-088		I-70 AGATE STRUCTURE REHAB	10/27/22	3,668.00	6.70	6.89	6.00
C170A-002		CRITICAL CULVERT CONST. PKG D	10/27/22	755.00	5.50	8.88	8.75
		WEIGHTED AVERAGE FOR THE FOURTH QUARTER		4,423.00	6.50	7.23	6.47
		WEIGHTED AVERAGE FOR THE YEAR		4,623.00	6.52	7.19	6.41
=====	208-00024	Erosion Log (Type 3) (20 In)		Lin Foot	=====		
NHPP0703-472			03/10/22	100.00	7.00	19.21	40.00
		WEIGHTED AVERAGE FOR THE FIRST QUARTER		100.00	7.00	19.21	40.00
2670703-497		I-70_GENESEE WILDLIFE XING	09/15/22	400.00	8.40	19.01	33.36
		WEIGHTED AVERAGE FOR THE THIRD QUARTER		400.00	8.40	19.01	33.36
		WEIGHTED AVERAGE FOR THE YEAR		500.00	8.12	19.03	34.69

COLORADO DEPARTMENT OF TRANSPORTATION
ITEM UNIT COSTS BY PROJECTS -- 2022 COST DATA

11:31 Wednesday, March 8, 2023 112

PROJECT NUMBER	ITEM NUMBER/ PROJECT LOCATION	ITEM DESCRIPTION/ PROJECT LOCATION	DATE LET	UNIT/ QUANTITY	ENGR. EST.	AVERAGE BID	AWARDED BID
===== 208-00026 Coir Roll Lin Foot =====							
NHPP0702-413		VAIL PASS AUX PHASE 1 CAP 2	04/18/22	130.00	50.05	50.05	50.05
		WEIGHTED AVERAGE FOR THE SECOND QUARTER		130.00	50.05	50.05	50.05
===== 208-00027 Silt Fence (Type 2) Lin Foot =====							
STA3852-015		US 385 HOLYOKE NORTH	10/27/22	3,500.00	5.00	4.35	4.35
		WEIGHTED AVERAGE FOR THE FOURTH QUARTER		3,500.00	5.00	4.35	4.35
		WEIGHTED AVERAGE FOR THE YEAR		3,500.00	5.00	4.35	4.35
===== 208-00033 Sediment Trap Each =====							
STA 067A-048		Hwy 67A MP 0.00 TO MP 11.05 I	03/03/22	1.00	2500.00	3707.09	1200.00
		WEIGHTED AVERAGE FOR THE FIRST QUARTER		1.00	2500.00	3707.09	1200.00
		WEIGHTED AVERAGE FOR THE YEAR		1.00	2500.00	3707.09	1200.00
===== 208-00035 Aggregate Bag Lin Foot =====							
ITS0703-477		ITS EQUIPMENT UPGRADE AT EJMT	01/06/22	120.00	10.00	23.00	23.00
MTCE R500-218			01/06/22	100.00	10.00	11.88	7.75
NHPP2873-189		US 287 (FEDERAL BLVD) - COLFA	01/06/22	484.00	9.00	11.01	7.67
STR0505-050			01/13/22	80.00	6.00	65.33	150.00
NHPP0702-383		I-70 EB AUX FRISCO TO SILVERT	01/13/22	600.00	10.00	11.86	18.00
STA0252-459			02/03/22	200.00	10.00	7.20	6.65
C0762-055			02/17/22	600.00	7.00	7.48	8.75
STR0141-031			02/17/22	100.00	15.00	8.58	7.75

COLORADO DEPARTMENT OF TRANSPORTATION
ITEM UNIT COSTS BY PROJECTS -- 2022 COST DATA

11:31 Wednesday, March 8, 2023 113

PROJECT NUMBER	ITEM NUMBER/ PROJECT LOCATION	ITEM DESCRIPTION/ PROJECT LOCATION	DATE LET	UNIT/ QUANTITY	ENGR. EST.	AVERAGE BID	AWARDED BID
===== 208-00035 Aggregate Bag Lin Foot =====							
STR133A-051			02/17/22	250.00	10.00	13.80	13.00
NHPP0063-063			02/24/22	900.00	8.00	12.30	11.00
STA 067A-048		Hwy 67A MP 0.00 TO MP 11.05 I	03/03/22	250.00	6.00	10.44	10.00
NHPP 0761-238		I-76 DAHLIA TO YORK	03/10/22	90.00	9.00	9.92	7.25
C0761-239							
NHPP0703-472			03/10/22	100.00	9.00	11.30	14.00
BRC040-057			03/17/22	176.00	12.00	11.61	9.45
STR R500-171		Various locations on SH 141 a	03/17/22	100.00	14.00	10.28	5.00
STR092A-031			03/17/22	100.00	10.00	8.75	8.75
NHM765-007			03/31/22	600.00	11.00	15.48	8.61
WEIGHTED AVERAGE FOR THE FIRST QUARTER				4,850.00	9.23	12.07	13.05
NH0504-911			04/07/22	400.00	9.00	9.60	10.20
NHPP0702-413		VAIL PASS AUX PHASE 1 CAP 2	04/18/22	1,000.00	13.37	13.37	13.37
STM1151-038		SH115 MP 27 TO MP 38	04/21/22	690.00	8.50	10.24	9.50
MTCE2873-204		MTCE FY22 SH287 CONC PANEL RE	05/05/22	200.00	10.00	13.12	11.24
2670703-479		I-70 BRIDGE OVER HARLAN	05/05/22	72.00	10.00	9.64	10.39
ER0702-420		PR I-70 GWC MATERIAL FLOWS 20	05/06/22	400.00	11.00	16.00	15.00
STA001A-005		SH1 WELLINGTON SOUTH RESURFAC	05/12/22	60.00	9.00	6.70	6.50
CM760-047		COLFAX AND QUAIL	05/12/22	72.00	15.50	27.70	20.00
NHPP 3851-018		US 385 NORTH OF CHEYENNE WELL	05/26/22	300.00	10.00	16.75	18.00
STAR100-358		3 STRUCTURES IN REGION 1 METR	05/26/22	25.00	20.00	17.20	13.00
C0852-120		Rehabilitation of Culvert by	05/26/22	20.00	15.00	12.00	12.00
FSA0702-409		I-70 VAIL WILDLIFE FENCE PHAS	05/26/22	100.00	22.00	17.00	17.00
ITS 0741-024		VMS SIGN INSTALLATIONS AND VS	06/02/22	100.00	15.00	13.00	12.00
NHPP072A-047		SH-72 RESURFACING: I-70 TO IN	06/09/22	440.00	10.00	29.67	29.67
FSA052A-046		SH52 WCR 37 INTERSECTION IMPR	06/09/22	1,500.00	6.00	7.38	7.00
MPR200-278		R2 - VARIOUS LOCATIONS	06/09/22	150.00	12.00	27.17	6.50
MPR200-279		FY 23 STENCIL MARKING PROJECT	06/09/22	50.00	25.00	20.00	20.00
MTCE0253-291		I-25 SIGN REPLACEMENT PHASE 2	06/16/22	35.00	15.00	17.06	23.12
NHPP0252-448		I-25 TREX NARROWS BRIDGE PREV	06/23/22	290.00	20.00	19.53	7.60
WEIGHTED AVERAGE FOR THE SECOND QUARTER				5,904.00	10.48	11.74	12.24
NHPP0702-414		VAIL PASS AUX PHASE 1 CAP 3	07/08/22	100.00	8.61	8.61	8.61
FBR0702-423		VAIL PASS AUX BE F-12-AT PHAS					
FSA052A-057		SH52 BOX CULVERT EXTENSION (M	08/04/22	200.00	15.00	11.95	13.00
STR0711-022		SH 71 OVER THE ARKANSAS	08/04/22	100.00	12.00	23.67	13.00
NHPP0063-054		US 6 FROM I70-B TO 33 RD. (MP	08/18/22	1,404.00	8.00	10.65	8.00
FBR0761-236		I-76 OVER CLR CRK SCOUR MIT	08/25/22	100.00	12.00	10.17	13.50
C1211-099		SH 121 NORTH SGA SIGNALS	08/25/22	102.00	15.00	17.00	25.00

COLORADO DEPARTMENT OF TRANSPORTATION
 ITEM UNIT COSTS BY PROJECTS -- 2022 COST DATA

11:31 Wednesday, March 8, 2023 114

PROJECT NUMBER	ITEM NUMBER/ PROJECT LOCATION	ITEM DESCRIPTION/ PROJECT LOCATION	DATE LET	UNIT/ QUANTITY	ENGR. EST.	AVERAGE BID	AWARDED BID
===== 208-00035 Aggregate Bag Lin Foot =====							
BR0343-046		US 34 TIMBER BRIDGE REPL. PKG	08/31/22	108.00	8.58	10.35	10.35
FBR0343-047		US 6/US 34 TIMBER BRIDGE REPL					
STAR100-374		5 STRUCTURES IN REGION 1	09/01/22	25.00	20.00	12.34	12.34
NHPPR100-266		R1 ESSENTIAL REPAIRS	09/01/22	500.00	12.00	12.59	14.46
PAN0761-245		ALONG I-76 & RAMPS MILEPOST 9	09/01/22	100.00	20.00	23.50	13.00
ER0253-297		WCR 34 BRIDGE OVER I-25(MM 24	09/14/22	180.00	12.00	12.60	5.00
2670403-065		US40 FLOYD HILL ROUNDABOUTS	09/15/22	2,802.00	12.00	13.51	14.00
SHE2873-193		US 287 & CO 52 INTERSECTION I	09/15/22	700.00	8.00	14.46	7.49
NHPP0701-231		I-70 SALT WASH BRIDGES SCOUR	09/29/22	100.00	10.00	9.14	5.00
WEIGHTED AVERAGE FOR THE THIRD QUARTER				6,521.00	10.86	13.31	11.61
MTCE0253-281		MTCE FY23 I-25 CONC PANEL REP	10/06/22	400.00	12.00	19.27	10.00
NHPP0821-114		SH 82 ASPEN/INDEPENDENCE PASS	10/13/22	150.00	15.00	20.00	27.00
C0831-126		SH83 EL PASO COUNTY TO BAYOU	10/13/22	100.00	15.00	12.50	15.00
NHPP0701-253		I-70 EAST OF DEBEQUE	10/27/22	50.00	12.00	23.80	35.00
FSAM240-200		SH21B CO SPRINGS SIGNAL REPLA	10/27/22	60.00	12.00	18.15	11.60
C5502-111		US 550 MP 81 AND 89 RED MOUNT	10/27/22	40.00	16.00	35.00	30.00
TRG0253-264		I-25 AND SH 119 PARK-N-RIDE	10/27/22	48.00	10.00	11.87	15.00
STA3852-015		US 385 HOLYOKE NORTH	10/27/22	2,500.00	8.00	7.85	7.85
NHPP0343-048		US 34 (MP 169.3-171.4)	11/01/22	82.00	14.00	19.89	18.00
STU0252-457		I-25:ALAMEDA RIVER PH 2.0	11/03/22	3,040.00	20.00	9.43	13.00
STR064A-010		SH 64 AND SH 13 AT MEEKER	11/10/22	250.00	40.00	10.85	9.00
NHPP0853-126		US85C: PLATTEVILLE NORTH MP (11/10/22	200.00	10.00	9.80	8.30
C5502-097		US550 MP 117.28-126.06	11/17/22	1,100.00	10.00	11.86	13.00
STRC090-011		US 50B AND SH71/CR18 INTERSEC	11/17/22	48.00	10.00	13.05	12.10
STAM420-001		US 285 AT HWY 9C IMPROVEMENTS	12/01/22	1,240.00	13.05	8.60	9.83
BR2854-148		INTERSECTION OF US 285 & SH 9					
STM0091-046		ADA RAMP IMPROVEMENTS - FAIRP					
STA0711-021		SH71: REGION LINE NORTH	12/01/22	300.00	9.00	9.79	11.00
STR114A-015		SH114 SILLSVILLE SOUTH TO MP3	12/01/22	150.00	15.00	12.50	15.00
2670703-487		I-70 BRIDGES OVER WARD ROAD-	12/01/22	240.00	8.70	11.76	7.80
NHPP0701-252		I-70 RIFLE TO SILT SLAB REPLA	12/01/22	150.00	15.00	13.27	8.54
IM025A-050		I25-MP103.9 - INTERSECTION DR	12/01/22	119.00	9.00	11.00	8.00
STR318A-001		SH 318 MP 0 - 12.5 MOFFAT COU	12/01/22	150.00	20.00	25.50	20.00
STR109A-019		M-22-AY BRIDGE REHAB ON SH109	12/01/22	1,184.00	10.00	10.06	11.11
NHPP0021-041		SH2 RESURFACING MLK TO 52ND	12/01/22	120.00	12.00	9.37	9.82
STR0641-107		SH 13 MM 104-128.1 IN MOFFAT	12/01/22	100.00	20.00	25.33	15.00
NHPP083A-046		SH83 RESURFACING STROH RD TO	12/08/22	500.00	11.50	9.92	8.84
NHPP0063-048		US6 / 20 ROAD INTERSECTION IM	12/15/22	100.00	20.00	12.73	23.00
NHM175-029		CANON CITY, CO	12/15/22	80.00	12.00	10.00	15.00
NHPP0931-033		SH93:US6 TO 58TH RESURFACING	12/15/22	300.00	9.00	8.71	7.70
STR0092-024		SH 9 North of Silverthorne	12/22/22	100.00	30.00	18.10	13.20
WEIGHTED AVERAGE FOR THE FOURTH QUARTER				12,901.00	13.62	11.12	11.55
WEIGHTED AVERAGE FOR THE YEAR				30,176.00	11.70	11.90	11.94

COLORADO DEPARTMENT OF TRANSPORTATION
ITEM UNIT COSTS BY PROJECTS -- 2022 COST DATA

11:31 Wednesday, March 8, 2023 115

PROJECT NUMBER	ITEM NUMBER/ PROJECT LOCATION	ITEM DESCRIPTION/ PROJECT LOCATION	DATE LET	UNIT/ QUANTITY	ENGR. EST.	AVERAGE BID	AWARDED BID
===== 208-00041		Rock Check Dam		Each	=====	=====	=====
NHPP0702-383		I-70 EB AUX FRISCO TO SILVERT	01/13/22	39.00	900.00	1262.72	1000.00
BRC040-057			03/17/22	1.00	1000.00	2980.25	6714.00
		WEIGHTED AVERAGE FOR THE FIRST QUARTER		40.00	902.50	1297.24	1142.85
NHPP0701-231		I-70 SALT WASH BRIDGES SCOUR	09/29/22	2.00	5000.00	3574.15	6500.00
		WEIGHTED AVERAGE FOR THE THIRD QUARTER		2.00	5000.00	3574.15	6500.00
NHPP0705-088		I-70 AGATE STRUCTURE REHAB	10/27/22	8.00	1200.00	2337.19	3500.00
IM025A-050		I25-MP103.9 - INTERSECTION DR	12/01/22	2.00	750.00	1360.00	980.00
STA385A-016		SH 385 MP 97.76	12/22/22	4.00	500.00	1337.50	600.00
		WEIGHTED AVERAGE FOR THE FOURTH QUARTER		14.00	935.71	1808.76	2033.75
		WEIGHTED AVERAGE FOR THE YEAR		56.00	1057.14	1451.29	1573.34
===== 208-00045		Conc Washout Str		Each	=====	=====	=====
NHPP1601-083			02/03/22	3.00	1500.00	2720.56	1500.00
MP0503-098			03/24/22	1.00	1500.00	580.00	250.00
NHM765-007			03/31/22	2.00	5000.00	1794.15	1140.00
C0703-499		EJMT GROUT BED REPAIR AND PAN	03/31/22	1.00	4000.00	3310.00	4000.00
		WEIGHTED AVERAGE FOR THE FIRST QUARTER		7.00	2857.14	2179.26	1575.71
MTCE2873-204		MTCE FY22 SH287 CONC PANEL RE	05/05/22	1.00	2000.00	4905.16	4210.31
STA0712-019		SH 71: Frieght Improvements	05/12/22	2.00	3200.00	803.79	803.79
FSA3921-019		SH 392 AND WCR 55 ISLANDS	06/02/22	1.00	3000.00	766.67	100.00
		WEIGHTED AVERAGE FOR THE SECOND QUARTER		4.00	2850.00	1959.70	1479.47
BR0343-046		US 34 TIMBER BRIDGE REPL. PKG	08/31/22	6.00	3424.00	2893.68	2893.68

COLORADO DEPARTMENT OF TRANSPORTATION
ITEM UNIT COSTS BY PROJECTS -- 2022 COST DATA

11:31 Wednesday, March 8, 2023 116

PROJECT NUMBER	ITEM NUMBER/ PROJECT LOCATION	ITEM DESCRIPTION/ PROJECT LOCATION	DATE LET	UNIT/ QUANTITY	ENGR. EST.	AVERAGE BID	AWARDED BID
=====	208-00045	Conc Washout Str		Each	=====		
FBR0343-047		US 6/US 34 TIMBER BRIDGE REPL					
2670403-065		US40_FLOYD HILL ROUNDABOUTS	09/15/22	4.00	3000.00	2249.00	2400.00
		WEIGHTED AVERAGE FOR THE THIRD QUARTER		10.00	3254.40	2463.89	2696.21
MTCE0253-281		MTCE FY23 I-25 CONC PANEL REP	10/06/22	1.00	5000.00	4091.83	5500.00
NHPP0705-088		I-70 AGATE STRUCTURE REHAB	10/27/22	4.00	2000.00	2364.84	2600.00
TRG0253-264		I-25 AND SH 119 PARK-N-RIDE	10/27/22	2.00	2000.00	3996.41	1900.00
MPR200-280		PUEBLO AREA	11/17/22	1.00	1850.00	1450.00	2500.00
STAM420-001		US 285 AT HWY 9C IMPROVEMENTS	12/01/22	5.00	2909.00	2937.01	3898.02
BR2854-148		INTERSECTION OF US 285 & SH 9					
STM0091-046		ADA RAMP IMPROVEMENTS - FAIRP					
IM025A-050		I25-MP103.9 - INTERSECTION DR	12/01/22	3.00	2700.00	2070.00	860.00
STR109A-019		M-22-AY BRIDGE REHAB ON SH109	12/01/22	4.00	2000.00	2637.88	2170.76
		WEIGHTED AVERAGE FOR THE FOURTH QUARTER		20.00	2474.75	2963.16	2664.44
		WEIGHTED AVERAGE FOR THE YEAR		41.00	2766.80	2725.22	2377.69
=====	208-00046	Pre-fab Conc Washout Str (Type 1)		Each	=====		
NHPP2873-189		US 287 (FEDERAL BLVD) - COLFA	01/06/22	2.00	1600.00	3491.14	3641.09
NH0504-910		US50B L-24-B MIN REP AT MP 40	01/13/22	1.00	2000.00	2266.06	500.00
NHPP0702-383		I-70 EB AUX FRISCO TO SILVERT	01/13/22	3.00	1500.00	4670.52	6500.00
STA0252-459			02/03/22	6.00	2000.00	3698.00	2050.00
C0762-055			02/17/22	2.00	1500.00	2987.66	2500.00
NHPP0063-063			02/24/22	4.00	3000.00	1519.50	2300.00
STA 067A-048		Hwy 67A MP 0.00 TO MP 11.05 I	03/03/22	1.00	3000.00	1055.10	300.00
NHPP 0761-238		I-76 DAHLIA TO YORK	03/10/22	5.00	3000.00	4493.82	1100.00
C0761-239							
NHPP0703-472			03/10/22	2.00	2050.00	2452.09	2000.00
BRC040-057			03/17/22	4.00	1500.00	2476.43	498.72
STR R500-171		Various locations on SH 141 a	03/17/22	2.00	790.00	2114.08	2500.00
M R100-351		FY22 R1 SIGN STRUCTURE REPLAC	03/17/22	1.00	10800.00	6566.00	10828.00
STR092A-031			03/17/22	1.00	3500.00	3000.00	3000.00
		WEIGHTED AVERAGE FOR THE FIRST QUARTER		34.00	2372.94	3473.13	2482.50
NH0504-911			04/07/22	8.00	5000.00	595.00	590.00
NHPP0702-413		VAIL PASS AUX PHASE 1 CAP 2	04/18/22	2.00	10903.84	10903.84	10903.84

COLORADO DEPARTMENT OF TRANSPORTATION
ITEM UNIT COSTS BY PROJECTS -- 2022 COST DATA

11:31 Wednesday, March 8, 2023 117

PROJECT NUMBER	ITEM NUMBER/ PROJECT LOCATION	ITEM DESCRIPTION/ PROJECT LOCATION	DATE LET	UNIT/ QUANTITY	ENGR. EST.	AVERAGE BID	AWARDED BID
=====	208-00046	Pre-fab Conc Washout Str (Type 1)		Each =====			
STM1151-038		SH115 MP 27 TO MP 38	04/21/22	5.00	1370.00	3609.26	2500.00
2670703-479		I-70 BRIDGE OVER HARLAN	05/05/22	2.00	1800.00	5943.34	2198.06
NHC540-017		R2 CHAINUP STA @ KENOSHA/HOOS	05/12/22	2.00	2100.00	4833.33	3500.00
CM760-047		COLFAX AND QUAIL	05/12/22	1.00	1900.00	2338.60	1678.00
C0852-120		Rehabilitation of Culvert by	05/26/22	3.00	5000.00	960.00	960.00
FSA0702-409		I-70 VAIL WILDLIFE FENCE PHAS	05/26/22	2.00	1500.00	2500.00	2500.00
ITS 0741-024		VMS SIGN INSTALLATIONS AND VS	06/02/22	3.00	500.00	1289.50	550.00
NHPP072A-047		SH-72 RESURFACING: I-70 TO IN	06/09/22	2.00	2000.00	2871.75	2871.75
MTCE0253-291		I-25 SIGN REPLACEMENT PHASE 2	06/16/22	1.00	2500.00	5667.83	3185.65
NHPP0252-448		I-25 TREX NARROWS BRIDGE PREV	06/23/22	10.00	600.00	882.50	1.00
		WEIGHTED AVERAGE FOR THE SECOND QUARTER		41.00	2691.65	2492.30	1721.24
NHPP0702-414		VAIL PASS AUX PHASE 1 CAP 3	07/08/22	2.00	11174.01	11174.01	11174.01
FBR0702-423		VAIL PASS AUX BE F-12-AT PHAS					
STR0711-022		SH 71 OVER THE ARKANSAS	08/04/22	1.00	2100.00	2516.67	2000.00
NHPP0063-054		US 6 FROM I70-B TO 33 RD. (MP	08/18/22	2.00	2500.00	5500.69	6250.00
FBR0761-236		I-76 OVER CLR CRK SCOUR MIT	08/25/22	1.00	1800.00	6500.00	10000.00
C1211-099		SH 121 NORTH SGA SIGNALS	08/25/22	5.00	2500.00	1780.00	2000.00
ER0502-092		US 50 MP 204 EB MONARCH TRUCK	08/29/22	1.00	3000.00	1333.18	2349.55
NHPPR100-266		R1 ESSENTIAL REPAIRS	09/01/22	2.00	1200.00	2948.11	3144.33
ER0253-297		WCR 34 BRIDGE OVER I-25(MM 24	09/14/22	1.00	3000.00	6018.71	1200.00
2670703-497		I-70 GENESEE WILDLIFE XING	09/15/22	1.00	2500.00	6357.03	5319.11
SHE2873-193		US 287 & CO 52 INTERSECTION I	09/15/22	2.00	3000.00	4734.80	1500.00
NHPP0701-231		I-70 SALT WASH BRIDGES SCOUR	09/29/22	2.00	2200.00	1531.47	2500.00
		WEIGHTED AVERAGE FOR THE THIRD QUARTER		20.00	3252.40	4179.42	4000.27
C0831-126		SH83 EL PASO COUNTY TO BAYOU	10/13/22	1.00	2500.00	2000.00	2500.00
STA207A-004		Resurfacing SH207A MANZANOLA	10/27/22	2.00	3000.00	2365.00	3095.00
FSAM240-200		SH21B CO SPRINGS SIGNAL REPLA	10/27/22	2.00	2000.00	1992.50	1450.00
C5502-111		US 550 MP 81 AND 89 RED MOUNT	10/27/22	1.00	2000.00	4000.00	6500.00
C170A-002		CRITICAL CULVERT CONST. PKG D	10/27/22	1.00	5000.00	2547.50	1000.00
STU0252-457		I-25:ALAMEDA RIVER PH 2.0	11/03/22	15.00	5000.00	1855.58	3400.00
STR064A-010		SH 64 AND SH 13 AT MEEKER	11/10/22	1.00	2000.00	2200.00	2500.00
C5502-097		US550 MP 117.28-126.06	11/17/22	2.00	4000.00	1584.05	541.00
STRC090-011		US 50B AND SH71/CR18 INTERSEC	11/17/22	2.00	2500.00	1070.00	1390.00
STR114A-015		SH114 SILLSVILLE SOUTH TO MP3	12/01/22	1.00	3500.00	2750.00	3000.00
2670703-487		I-70 BRIDGES OVER WARD ROAD-	12/01/22	2.00	3070.80	4982.04	2750.00
NHPP0701-252		I-70 RIFLE TO SILT SLAB REPLA	12/01/22	2.00	2373.00	5562.50	5800.00
NHPP0021-041		SH2 RESURFACING MLK TO 52ND	12/01/22	2.00	3500.00	4830.71	2602.59
NHPP083A-046		SH83 RESURFACING STROH RD TO	12/08/22	2.00	2000.00	6461.44	2522.88

COLORADO DEPARTMENT OF TRANSPORTATION
ITEM UNIT COSTS BY PROJECTS -- 2022 COST DATA

11:31 Wednesday, March 8, 2023 118

PROJECT NUMBER	ITEM NUMBER/ PROJECT LOCATION	ITEM DESCRIPTION/ PROJECT LOCATION	DATE LET	UNIT/ QUANTITY	ENGR. EST.	AVERAGE BID	AWARDED BID
===== 208-00046 Pre-fab Conc Washout Str (Type 1) Each =====							
NHPP0063-048		US6 / 20 ROAD INTERSECTION IM	12/15/22	4.00	3000.00	1713.37	1950.00
NHPP0931-033		SH93:US6 TO 58TH RESURFACING	12/15/22	2.00	2000.00	2249.76	2560.00
NHPP0502-090		SH 50 MP 134.6-136 GUNNISON C	12/22/22	2.00	2500.00	2680.19	4054.52
STR0092-024		SH 9 North of Silverthorne	12/22/22	1.00	5000.00	3052.00	604.00
BR012A-048		CO 12 STRUCTURE P-17-F AT MP	12/22/22	2.00	3000.00	3276.72	2500.00
STA385A-016		SH 385 MP 97.76	12/22/22	2.00	1000.00	3812.50	1000.00
STR096A-050		SH 96 MP 168.99 TO 193.77	12/22/22	1.00	2500.00	2283.33	2300.00
	WEIGHTED AVERAGE FOR THE FOURTH QUARTER			50.00	3427.75	2718.02	2745.02
	WEIGHTED AVERAGE FOR THE YEAR			145.00	2948.09	3058.81	2568.34
===== 208-00051 Storm Drain Inlet Protection (Type I) Lin Foot =====							
NHPP0702-383		I-70 EB AUX FRISCO TO SILVERT	01/13/22	100.00	20.00	24.76	37.00
NHPP0063-063			02/24/22	54.00	20.00	21.30	29.00
NHPP 0761-238		I-76 DAHLIA TO YORK	03/10/22	500.00	19.00	11.75	10.00
C0761-239							
BRC040-057			03/17/22	14.00	15.00	23.79	18.15
	WEIGHTED AVERAGE FOR THE FIRST QUARTER			668.00	19.15	13.51	15.75
NH0504-911			04/07/22	50.00	13.00	14.30	13.60
2670703-479		I-70 BRIDGE OVER HARLAN	05/05/22	42.00	15.00	10.32	10.39
ITS 0741-024		VMS SIGN INSTALLATIONS AND VS	06/02/22	40.00	30.00	23.00	21.00
	WEIGHTED AVERAGE FOR THE SECOND QUARTER			132.00	18.79	13.59	14.82
NHPP0063-054		US 6 FROM I70-B TO 33 RD. (MP	08/18/22	290.00	12.00	17.14	13.00
C1211-099		SH 121 NORTH SGA SIGNALS	08/25/22	68.00	30.00	28.00	31.00
	WEIGHTED AVERAGE FOR THE THIRD QUARTER			358.00	15.42	19.21	16.42
STA207A-004		Resurfacing SH207A MANZANOLA	10/27/22	72.00	20.00	22.35	22.05
FSAM240-200		SH21B CO SPRINGS SIGNAL REPLA	10/27/22	160.00	10.00	18.56	17.25
TRG0253-264		I-25 AND SH 119 PARK-N-RIDE	10/27/22	175.00	10.00	10.24	11.00
STU0252-457		I-25:ALAMEDA RIVER PH 2.0	11/03/22	32.00	25.00	18.79	39.00

COLORADO DEPARTMENT OF TRANSPORTATION
ITEM UNIT COSTS BY PROJECTS -- 2022 COST DATA

11:31 Wednesday, March 8, 2023 119

PROJECT NUMBER	ITEM NUMBER/ PROJECT LOCATION	ITEM DESCRIPTION/ PROJECT LOCATION	DATE LET	UNIT/ QUANTITY	ENGR. EST.	AVERAGE BID	AWARDED BID
===== 208-00051		Storm Drain Inlet Protection (Type I)		Lin Foot	=====	=====	=====
NHPP0021-041		SH2 RESURFACING MLK TO 52ND	12/01/22	117.00	20.00	15.70	16.16
	WEIGHTED AVERAGE FOR THE FOURTH QUARTER			556.00	14.26	14.25	16.93
	WEIGHTED AVERAGE FOR THE YEAR			1,714.00	16.76	14.23	16.20
===== 208-00052		Storm Drain Inlet Protection (Type II)		Lin Foot	=====	=====	=====
NHPP0702-383		I-70 EB AUX FRISCO TO SILVERT	01/13/22	20.00	20.00	75.57	107.00
STR092A-031			03/17/22	70.00	70.00	11.00	11.00
C0703-499		EJMT GROUT BED REPAIR AND PAN	03/31/22	180.00	80.00	30.25	12.50
	WEIGHTED AVERAGE FOR THE FIRST QUARTER			270.00	72.96	36.26	19.11
NH0504-911			04/07/22	100.00	18.00	25.70	26.40
ITS 0741-024		VMS SIGN INSTALLATIONS AND VS	06/02/22	40.00	60.00	82.50	76.00
	WEIGHTED AVERAGE FOR THE SECOND QUARTER			140.00	30.00	41.93	40.57
NHPP0063-054		US 6 FROM I70-B TO 33 RD. (MP	08/18/22	49.00	15.00	57.26	43.00
	WEIGHTED AVERAGE FOR THE THIRD QUARTER			49.00	15.00	57.26	43.00
STU0252-457		I-25:ALAMEDA RIVER PH 2.0	11/03/22	162.00	50.00	63.52	73.00
	WEIGHTED AVERAGE FOR THE FOURTH QUARTER			162.00	50.00	60.72	71.39
	WEIGHTED AVERAGE FOR THE YEAR			621.00	52.71	52.07	46.89
===== 208-00053		Storm Drain Inlet Protect (Ty I) (84 In)		Each	=====	=====	=====
NHPP2873-189		US 287 (FEDERAL BLVD) - COLFA	01/06/22	2.00	220.00	243.93	169.71
NHM765-007			03/31/22	12.00	120.00	240.37	173.64
	WEIGHTED AVERAGE FOR THE FIRST QUARTER			14.00	134.29	241.01	173.08

COLORADO DEPARTMENT OF TRANSPORTATION
 ITEM UNIT COSTS BY PROJECTS -- 2022 COST DATA

11:31 Wednesday, March 8, 2023 120

PROJECT NUMBER	ITEM NUMBER/ PROJECT LOCATION	ITEM DESCRIPTION/ PROJECT LOCATION	DATE LET	UNIT/ QUANTITY	ENGR. EST.	AVERAGE BID	AWARDED BID
===== 208-00053		Storm Drain Inlet Protect (Ty I) (84 In)		Each	=====	=====	=====
C0852-120		Rehabilitation of Culvert by	05/26/22	2.00	250.00	295.00	295.00
NHPP072A-047		SH-72 RESURFACING: I-70 TO IN	06/09/22	33.00	190.00	485.45	485.45
		WEIGHTED AVERAGE FOR THE SECOND QUARTER		35.00	193.43	474.57	474.57
NHPPR100-266		R1 ESSENTIAL REPAIRS	09/01/22	1.00	20.00	275.65	323.94
2670403-065		US40 FLOYD HILL ROUNDABOUTS	09/15/22	7.00	150.00	283.06	140.00
SHE2873-193		US 287 & CO 52 INTERSECTION I	09/15/22	1.00	205.00	286.58	197.00
		WEIGHTED AVERAGE FOR THE THIRD QUARTER		9.00	141.67	283.03	166.77
STAM420-001		US 285 AT HWY 9C IMPROVEMENTS	12/01/22	38.00	180.00	194.30	176.38
BR2854-148		INTERSECTION OF US 285 & SH 9					
STM0091-046		ADA RAMP IMPROVEMENTS - FAIRP					
IM025A-050		I25-MP103.9 - INTERSECTION DR	12/01/22	8.00	175.00	203.33	210.00
NHPP083A-046		SH83 RESURFACING STROH RD TO	12/08/22	2.00	250.00	240.17	237.34
NHPP0931-033		SH93:US6 TO 58TH RESURFACING	12/15/22	9.00	200.00	205.05	225.60
		WEIGHTED AVERAGE FOR THE FOURTH QUARTER		57.00	184.91	197.94	191.01
		WEIGHTED AVERAGE FOR THE YEAR		115.00	177.96	241.42	273.23
===== 208-00054		Storm Drain Inlet Protection (Type II)		Each	=====	=====	=====
NHPP2873-189		US 287 (FEDERAL BLVD) - COLFA	01/06/22	98.00	280.00	215.24	214.13
NHPP0063-063			02/24/22	174.00	260.00	125.50	115.00
NHM765-007			03/31/22	22.00	200.00	321.15	283.21
		WEIGHTED AVERAGE FOR THE FIRST QUARTER		294.00	262.18	185.16	160.63
2670703-479		I-70 BRIDGE OVER HARLAN	05/05/22	17.00	300.00	220.09	266.56
STAR100-358		3 STRUCTURES IN REGION 1 METR	05/26/22	2.00	300.00	293.40	348.00
NHPP072A-047		SH-72 RESURFACING: I-70 TO IN	06/09/22	14.00	240.00	911.20	911.20
		WEIGHTED AVERAGE FOR THE SECOND QUARTER		33.00	274.55	303.00	544.98

COLORADO DEPARTMENT OF TRANSPORTATION
ITEM UNIT COSTS BY PROJECTS -- 2022 COST DATA

11:31 Wednesday, March 8, 2023 121

PROJECT NUMBER	ITEM NUMBER/ PROJECT LOCATION	ITEM DESCRIPTION/ PROJECT LOCATION	DATE LET	UNIT/ QUANTITY	ENGR. EST.	AVERAGE BID	AWARDED BID
===== 208-00054		Storm Drain Inlet Protection (Type II)		Each	=====		
STAR100-374		5 STRUCTURES IN REGION 1	09/01/22	2.00	300.00	348.21	348.21
NHPPR100-266		R1 ESSENTIAL REPAIRS	09/01/22	1.00	20.00	268.78	313.34
2670403-065		US40_FLOYD HILL ROUNDABOUTS	09/15/22	5.00	55.00	346.40	240.00
		WEIGHTED AVERAGE FOR THE THIRD QUARTER		8.00	111.88	334.94	276.22
STA207A-004		Resurfacing SH207A MANZANOLA	10/27/22	54.00	250.00	220.65	211.95
STAM420-001		US 285 AT HWY 9C IMPROVEMENTS	12/01/22	15.00	295.00	296.73	337.52
BR2854-148		INTERSECTION OF US 285 & SH 9					
STM0091-046		ADA RAMP IMPROVEMENTS - FAIRP					
2670703-487		I-70 BRIDGES OVER WARD ROAD-	12/01/22	2.00	400.00	320.53	200.00
IM025A-050		I25-MP103.9 - INTERSECTION DR	12/01/22	4.00	300.00	233.33	200.00
NHPP0021-041		SH2 RESURFACING MLK TO 52ND	12/01/22	30.00	350.00	289.26	251.67
NHPP0931-033		SH93:US6 TO 58TH RESURFACING	12/15/22	3.00	250.00	274.81	205.00
		WEIGHTED AVERAGE FOR THE FOURTH QUARTER		108.00	288.66	259.48	239.57
		WEIGHTED AVERAGE FOR THE YEAR		443.00	266.84	219.39	210.59
===== 208-00055		Rigid Inlet Prot Device		Each	=====		
ITS0703-477		ITS EQUIPMENT UPGRADE AT EJMT	01/06/22	10.00	150.00	905.00	905.00
STA 067A-048		Hwy 67A MP 0.00 TO MP 11.05 I	03/03/22	1.00	400.00	453.09	450.00
		WEIGHTED AVERAGE FOR THE FIRST QUARTER		11.00	172.73	800.71	863.64
NHPP0021-041		SH2 RESURFACING MLK TO 52ND	12/01/22	1.00	500.00	526.54	313.05
		WEIGHTED AVERAGE FOR THE FOURTH QUARTER		1.00	500.00	526.54	313.05
		WEIGHTED AVERAGE FOR THE YEAR		12.00	200.00	736.20	817.75
===== 208-00056		Storm Drain Inlet Protection (Type III)		Each	=====		
ITS0703-477		ITS EQUIPMENT UPGRADE AT EJMT	01/06/22	10.00	300.00	510.00	510.00

COLORADO DEPARTMENT OF TRANSPORTATION
ITEM UNIT COSTS BY PROJECTS -- 2022 COST DATA

11:31 Wednesday, March 8, 2023 122

PROJECT NUMBER	ITEM NUMBER/ PROJECT LOCATION	ITEM DESCRIPTION/ PROJECT LOCATION	DATE LET	UNIT/ QUANTITY	ENGR. EST.	AVERAGE BID	AWARDED BID
===== 208-00056		Storm Drain Inlet Protection (Type III)		Each =====			
STA0252-459			02/03/22	100.00	260.00	166.20	130.00
NHPP0063-063			02/24/22	48.00	280.00	116.50	115.00
NHPP0703-472			03/10/22	30.00	350.00	209.79	250.00
BRC040-057			03/17/22	36.00	300.00	296.88	208.50
NHM765-007			03/31/22	10.00	300.00	344.67	326.15
		WEIGHTED AVERAGE FOR THE FIRST QUARTER		234.00	285.21	206.30	179.01
2670703-479		I-70 BRIDGE OVER HARLAN	05/05/22	30.00	320.00	159.78	177.71
ITS 0741-024		VMS SIGN INSTALLATIONS AND VS	06/02/22	1.00	400.00	230.50	213.00
NHPP0252-448		I-25 TREX NARROWS BRIDGE PREV	06/23/22	36.00	250.00	288.00	150.00
		WEIGHTED AVERAGE FOR THE SECOND QUARTER		67.00	283.58	216.85	163.35
NHPP0063-054		US 6 FROM I70-B TO 33 RD. (MP	08/18/22	30.00	150.00	386.13	290.00
NHPPR100-266		R1 ESSENTIAL REPAIRS	09/01/22	6.00	20.00	284.81	244.44
2670403-065		US40_FLOYD HILL ROUNDABOUTS	09/15/22	6.00	350.00	325.97	145.00
		WEIGHTED AVERAGE FOR THE THIRD QUARTER		42.00	160.00	355.85	262.78
NHPP0705-088		I-70 AGATE STRUCTURE REHAB	10/27/22	2.00	260.00	406.44	312.00
STAM420-001		US 285 AT HWY 9C IMPROVEMENTS	12/01/22	7.00	220.00	266.71	267.73
BR2854-148		INTERSECTION OF US 285 & SH 9					
STM0091-046		ADA RAMP IMPROVEMENTS - FAIRP					
IM025A-050		I25-MP103.9 - INTERSECTION DR	12/01/22	4.00	250.00	180.00	140.00
NHPP083A-046		SH83 RESURFACING STROH RD TO	12/08/22	3.00	500.00	210.95	149.89
		WEIGHTED AVERAGE FOR THE FOURTH QUARTER		16.00	285.00	261.94	219.24
		WEIGHTED AVERAGE FOR THE YEAR		359.00	270.25	223.99	187.68
===== 208-00057		Storm Drain Inlet Protect (Ty I) (144 In)		Each =====			
SHE2873-193		US 287 & CO 52 INTERSECTION I	09/15/22	1.00	250.00	424.76	267.00
		WEIGHTED AVERAGE FOR THE THIRD QUARTER		1.00	250.00	424.76	267.00
2670703-487		I-70 BRIDGES OVER WARD ROAD-	12/01/22	8.00	250.00	386.22	280.00

COLORADO DEPARTMENT OF TRANSPORTATION
 ITEM UNIT COSTS BY PROJECTS -- 2022 COST DATA

11:31 Wednesday, March 8, 2023 123

PROJECT NUMBER	ITEM NUMBER/ PROJECT LOCATION	ITEM DESCRIPTION/ PROJECT LOCATION	DATE LET	UNIT/ QUANTITY	ENGR. EST.	AVERAGE BID	AWARDED BID
=====	208-00057	Storm Drain Inlet Protect (Ty I) (144 In)		Each			
IM025A-050		I25-MP103.9 - INTERSECTION DR	12/01/22	1.00	225.00	276.67	280.00
NHPP083A-046		SH83 RESURFACING STROH RD TO	12/08/22	3.00	220.00	282.89	324.77
		WEIGHTED AVERAGE FOR THE FOURTH QUARTER		12.00	240.42	366.86	291.19
		WEIGHTED AVERAGE FOR THE YEAR		13.00	241.15	373.18	289.33
=====	208-00058	Storm Drain Inlet Protect (Ty I) (204 In)		Each			
STAM420-001		US 285 AT HWY 9C IMPROVEMENTS	12/01/22	2.00	301.00	395.25	387.01
BR2854-148		INTERSECTION OF US 285 & SH 9					
STM0091-046		ADA RAMP IMPROVEMENTS - FAIRP					
IM025A-050		I25-MP103.9 - INTERSECTION DR	12/01/22	1.00	275.00	310.00	280.00
NHPP083A-046		SH83 RESURFACING STROH RD TO	12/08/22	1.00	300.00	299.64	337.27
		WEIGHTED AVERAGE FOR THE FOURTH QUARTER		4.00	294.25	360.86	347.82
		WEIGHTED AVERAGE FOR THE YEAR		4.00	294.25	360.86	347.82
=====	208-00070	Vehicle Tracking Pad		Each			
NHPP1601-083			02/03/22	2.00	3500.00	11027.81	1200.00
STA0252-459			02/03/22	2.00	4000.00	2574.67	2345.00
NHM765-007			03/31/22	4.00	4300.00	6784.67	855.00
		WEIGHTED AVERAGE FOR THE FIRST QUARTER		8.00	4025.00	6407.97	1313.75
2670703-479		I-70 BRIDGE OVER HARLAN	05/05/22	3.00	4000.00	6784.48	3437.96
NHC540-017		R2 CHAINUP STA @ KENOSHA/HOOS	05/12/22	4.00	2945.00	3900.00	3700.00
NHPP072A-047		SH-72 RESURFACING: I-70 TO IN	06/09/22	1.00	3000.00	11439.50	11439.50
		WEIGHTED AVERAGE FOR THE SECOND QUARTER		8.00	3347.50	5818.07	4569.17
STR0711-022		SH 71 OVER THE ARKANSAS	08/04/22	1.00	3400.00	4766.67	4000.00
BR0343-046		US 34 TIMBER BRIDGE REPL. PKG	08/31/22	6.00	2995.28	1981.32	1981.32
FBR0343-047		US 6/US 34 TIMBER BRIDGE REPL					
NHPPR100-266		R1 ESSENTIAL REPAIRS	09/01/22	2.00	3500.00	5655.91	3217.72
2670403-065		US40_FLOYD HILL ROUNDABOUTS	09/15/22	4.00	5000.00	5307.83	4675.00

COLORADO DEPARTMENT OF TRANSPORTATION
ITEM UNIT COSTS BY PROJECTS -- 2022 COST DATA

11:31 Wednesday, March 8, 2023 124

PROJECT NUMBER	ITEM NUMBER/ PROJECT LOCATION	ITEM DESCRIPTION/ PROJECT LOCATION	DATE LET	UNIT/ QUANTITY	ENGR. EST.	AVERAGE BID	AWARDED BID
=====	208-00070	Vehicle Tracking Pad		Each	=====	=====	=====
2670703-497		I-70_GENESEE WILDLIFE XING	09/15/22	2.00	5000.00	3346.23	2346.78
NHPP0701-231		I-70 SALT WASH BRIDGES SCOUR	09/29/22	12.00	2300.00	1400.62	100.00
		WEIGHTED AVERAGE FOR THE THIRD QUARTER		27.00	3184.14	3142.76	1737.66
NHPP0705-088		I-70 AGATE STRUCTURE REHAB	10/27/22	4.00	3500.00	4131.48	3250.00
TRG0253-264		I-25 AND SH 119 PARK-N-RIDE	10/27/22	2.00	3000.00	7318.27	3800.00
STAM420-001		US 285 AT HWY 9C IMPROVEMENTS	12/01/22	5.00	4051.00	6454.32	3894.21
BR2854-148		INTERSECTION OF US 285 & SH 9					
STM0091-046		ADA RAMP IMPROVEMENTS - FAIRP					
2670703-487		I-70 BRIDGES OVER WARD ROAD-	12/01/22	1.00	3544.90	4298.36	3860.00
STR109A-019		M-22-AY BRIDGE REHAB ON SH109	12/01/22	4.00	3000.00	5078.67	6024.34
NHPP083A-046		SH83 RESURFACING STROH RD TO	12/08/22	1.00	3500.00	4183.23	3266.45
NHPP0931-033		SH93:US6 TO 58TH RESURFACING	12/15/22	2.00	3000.00	2769.41	2050.00
NHPP0502-090		SH 50 MP 134.6-136 GUNNISON C	12/22/22	2.00	4000.00	6526.71	10812.05
		WEIGHTED AVERAGE FOR THE FOURTH QUARTER		21.00	3490.47	5556.29	4479.09
		WEIGHTED AVERAGE FOR THE YEAR		64.00	3410.18	4940.04	2984.84
=====	208-00071	Maint Aggregate (Veh Track Pad)		Cubic Yard	=====	=====	=====
NHPP1601-083			02/03/22	31.00	135.00	182.77	30.00
		WEIGHTED AVERAGE FOR THE FIRST QUARTER		31.00	135.00	182.77	30.00
NHC540-017		R2 CHAINUP STA @ KENOSHA/HOOS	05/12/22	60.00	110.00	66.67	90.00
		WEIGHTED AVERAGE FOR THE SECOND QUARTER		60.00	110.00	66.67	90.00
2670703-497		I-70_GENESEE WILDLIFE XING	09/15/22	30.00	94.00	95.65	49.22
		WEIGHTED AVERAGE FOR THE THIRD QUARTER		30.00	94.00	95.65	49.22
TRG0253-264		I-25 AND SH 119 PARK-N-RIDE	10/27/22	14.00	100.00	248.75	200.00

COLORADO DEPARTMENT OF TRANSPORTATION
ITEM UNIT COSTS BY PROJECTS -- 2022 COST DATA

11:31 Wednesday, March 8, 2023 125

PROJECT NUMBER	ITEM NUMBER/ PROJECT LOCATION	ITEM DESCRIPTION/ PROJECT LOCATION	DATE LET	UNIT/ QUANTITY	ENGR. EST.	AVERAGE BID	AWARDED BID
===== 208-00071		Maint Aggregate (Veh Track Pad)		Cubic Yard			
2670703-487		I-70 BRIDGES OVER WARD ROAD-	12/01/22	35.00	60.00	116.12	170.00
		WEIGHTED AVERAGE FOR THE FOURTH QUARTER		49.00	71.43	159.65	128.75
		WEIGHTED AVERAGE FOR THE YEAR		170.00	100.62	126.34	90.08
===== 208-00075		Pre-fab Vehicle Track Pad		Each			
NH0504-910		US50B L-24-B MIN REP AT MP 40	01/13/22	2.00	5000.00	4988.40	17500.00
STA0252-459			02/03/22	2.00	5000.00	16333.33	17000.00
C0762-055			02/17/22	2.00	3000.00	5387.48	4300.00
STR0141-031			02/17/22	2.00	2000.00	5600.00	11100.00
NHPP0063-063			02/24/22	2.00	3000.00	9875.00	1400.00
STA 067A-048		Hwy 67A MP 0.00 TO MP 11.05 I	03/03/22	1.00	3000.00	5074.40	600.00
NHPP 0761-238		I-76 DAHLIA TO YORK	03/10/22	5.00	4600.00	7946.23	2700.00
C0761-239							
NHPP0703-472			03/10/22	1.00	10900.00	4581.50	5000.00
BRC040-057			03/17/22	4.00	5000.00	10297.28	423.11
STR092A-031			03/17/22	2.00	4000.00	11300.00	11300.00
		WEIGHTED AVERAGE FOR THE FIRST QUARTER		23.00	4386.96	7931.13	6347.50
NH0504-911			04/07/22	8.00	4065.00	5125.00	7750.00
NHPP0702-413		VAIL PASS AUX PHASE 1 CAP 2	04/18/22	3.00	22892.42	22892.42	22892.42
STM1151-038		SH115 MP 27 TO MP 38	04/21/22	15.00	7000.00	6215.42	1400.00
STA0712-019		SH 71: Frieight Improvements	05/12/22	8.00	3000.00	5023.67	5023.67
CM760-047		COLFAX AND QUAIL	05/12/22	1.00	4000.00	2202.60	500.00
NHPP 3851-018		US 385 NORTH OF CHEYENNE WELL	05/26/22	4.00	6600.00	1857.50	800.00
C0852-120		Rehabilitation of Culvert by	05/26/22	2.00	5000.00	1500.00	1500.00
FSA0702-409		I-70 VAIL WILDLIFE FENCE PHAS	05/26/22	2.00	20000.00	9750.00	9750.00
FSA052A-046		SH52 WCR 37 INTERSECTION IMPR	06/09/22	4.00	6000.00	5317.20	1380.00
		WEIGHTED AVERAGE FOR THE SECOND QUARTER		47.00	7119.09	5839.86	4757.16
NHPP0702-414		VAIL PASS AUX PHASE 1 CAP 3	07/08/22	4.00	23790.20	23790.20	23790.20
FBR0702-423		VAIL PASS AUX BE F-12-AT PHAS					
FSA052A-057		SH52 BOX CULVERT EXTENSION (M	08/04/22	2.00	6000.00	2911.90	750.00
NHPP0063-054		US 6 FROM I70-B TO 33 RD. (MP	08/18/22	2.00	2500.00	11668.96	7500.00
FBR0761-236		I-76 OVER CLR CRK SCOUR MIT	08/25/22	2.00	4500.00	10866.67	4500.00
ER0502-092		US 50 MP 204 EB MONARCH TRUCK	08/29/22	1.00	5000.00	5043.88	5556.64

COLORADO DEPARTMENT OF TRANSPORTATION
ITEM UNIT COSTS BY PROJECTS -- 2022 COST DATA

11:31 Wednesday, March 8, 2023 126

PROJECT NUMBER	ITEM NUMBER/ PROJECT LOCATION	ITEM DESCRIPTION/ PROJECT LOCATION	DATE LET	UNIT/ QUANTITY	ENGR. EST.	AVERAGE BID	AWARDED BID
===== 208-00075 Pre-fab Vehicle Track Pad Each =====							
ER0253-297	WCR 34 BRIDGE OVER I-25(MM 24	09/14/22	1.00	5000.00	7759.28	2300.00	
SHE2873-193	US 287 & CO 52 INTERSECTION I	09/15/22	4.00	2000.00	8712.09	2000.00	
NHPP0701-231	I-70 SALT WASH BRIDGES SCOUR	09/29/22	12.00	5000.00	3345.51	100.00	
WEIGHTED AVERAGE FOR THE THIRD QUARTER				28.00	7112.89	7467.45	4918.48
STA207A-004	Resurfacing SH207A MANZANOLA	10/27/22	2.00	6000.00	3623.55	8170.65	
FSAM240-200	SH21B CO SPRINGS SIGNAL REPLA	10/27/22	1.00	5000.00	8600.00	2900.00	
C170A-002	CRITICAL CULVERT CONST. PKG D	10/27/22	1.00	5000.00	6238.75	3125.00	
STA3852-015	US 385 HOLYOKE NORTH	10/27/22	5.00	4500.00	7600.00	7600.00	
STU0252-457	I-25:ALAMEDA RIVER PH 2.0	11/03/22	5.00	4000.00	5061.92	9500.00	
SHE0242-087	US 24 SAFETY IMPRVMENTS, E OF	11/03/22	2.00	4340.00	8527.77	19083.32	
NHPP0853-126	US85C: PLATTEVILLE NORTH MP (11/10/22	2.00	4300.00	6401.00	5600.00	
C5502-097	US550 MP 117.28-126.06	11/17/22	10.00	3000.00	5206.57	2880.00	
STRC090-011	US 50B AND SH71/CR18 INTERSEC	11/17/22	2.00	5000.00	3625.00	4750.00	
STA0711-021	SH71: REGION LINE NORTH	12/01/22	2.00	5300.00	4381.67	1200.00	
2670703-487	I-70 BRIDGES OVER WARD ROAD-	12/01/22	8.00	2167.30	8011.34	5510.00	
IM025A-050	I25-MP103.9 - INTERSECTION DR	12/01/22	7.00	6000.00	7000.00	16500.00	
NHPP0063-048	US6 / 20 ROAD INTERSECTION IM	12/15/22	4.00	5500.00	11139.56	4000.00	
STR0092-024	SH 9 North of Silverthorne	12/22/22	2.00	7000.00	11535.00	20470.00	
STA0361-129	US 36: HYGIENE RD AND NELSON	12/22/22	2.00	6000.00	3627.08	1804.88	
BR012A-048	CO 12 STRUCTURE P-17-F AT MP	12/22/22	2.00	2500.00	3783.40	2500.00	
STA385A-016	SH 385 MP 97.76	12/22/22	2.00	2000.00	7712.50	18750.00	
WEIGHTED AVERAGE FOR THE FOURTH QUARTER				59.00	4215.57	6804.92	8059.39
WEIGHTED AVERAGE FOR THE YEAR				157.00	5626.60	6870.17	6282.51
===== 208-00082 Construction Mat Sq Foot =====							
NHPP0702-414	VAIL PASS AUX PHASE 1 CAP 3	07/08/22	18,827.00	7.27	7.27	7.27	
FBR0702-423	VAIL PASS AUX BE F-12-AT PHAS						
NHPPR100-266	R1 ESSENTIAL REPAIRS	09/01/22	3,000.00	30.00	14.19	10.74	
WEIGHTED AVERAGE FOR THE THIRD QUARTER				21,827.00	10.39	9.51	7.75
WEIGHTED AVERAGE FOR THE YEAR				21,827.00	10.39	9.51	7.75
===== 208-00090 Erosion Control (Curb Ramp) Each =====							
CR100-362		03/14/22	265.00	707.31	707.31	707.31	
WEIGHTED AVERAGE FOR THE FIRST QUARTER				265.00	707.31	707.31	707.31

COLORADO DEPARTMENT OF TRANSPORTATION
ITEM UNIT COSTS BY PROJECTS -- 2022 COST DATA

11:31 Wednesday, March 8, 2023 127

PROJECT NUMBER	ITEM NUMBER/ PROJECT LOCATION	ITEM DESCRIPTION/ PROJECT LOCATION	DATE LET	UNIT/ QUANTITY	ENGR. EST.	AVERAGE BID	AWARDED BID
===== 208-00090		Erosion Control (Curb Ramp)		Each	=====	=====	=====
CC030-081		ADA RAMP AND CURBS - FT. LUPT	04/14/22	153.00	600.00	511.28	400.00
		WEIGHTED AVERAGE FOR THE SECOND QUARTER		153.00	600.00	511.28	400.00
STA3852-015		US 385 HOLYOKE NORTH	10/27/22	66.00	500.00	523.99	523.99
STAM420-001		US 285 AT HWY 9C IMPROVEMENTS	12/01/22	32.00	420.00	417.01	539.28
BR2854-148		INTERSECTION OF US 285 & SH 9					
STM0091-046		ADA RAMP IMPROVEMENTS - FAIRP					
		WEIGHTED AVERAGE FOR THE FOURTH QUARTER		98.00	473.88	453.40	528.98
		WEIGHTED AVERAGE FOR THE YEAR		516.00	631.16	555.64	582.32
===== 208-00103		Removal and Disposal of Sediment (Labor)		Hour	=====	=====	=====
NHPP2873-189		US 287 (FEDERAL BLVD) - COLFA	01/06/22	80.00	60.00	98.21	90.53
STR0505-050			01/13/22	10.00	60.00	98.00	100.00
NH0504-910		US50B L-24-B MIN REP AT MP 40	01/13/22	20.00	70.00	78.13	50.00
NHPP0702-383		I-70 EB AUX FRISCO TO SILVERT	01/13/22	600.00	100.00	102.04	62.00
NHPP1601-083			02/03/22	20.00	60.00	196.19	60.00
STA0252-459			02/03/22	10.00	50.00	175.07	72.00
C0762-055			02/17/22	150.00	50.00	67.21	85.00
STR0141-031			02/17/22	40.00	70.00	55.03	51.10
STR133A-051			02/17/22	20.00	35.00	79.33	43.00
NHPP0063-063			02/24/22	20.00	65.00	45.00	40.00
STA 067A-048		Hwy 67A MP 0.00 TO MP 11.05 I	03/03/22	40.00	50.00	93.97	55.00
NHPP 0761-238		I-76 DAHLIA TO YORK	03/10/22	20.00	60.00	78.47	60.00
C0761-239							
NHPP0703-472			03/10/22	15.00	60.00	108.31	120.00
BRC040-057			03/17/22	20.00	100.00	88.72	52.89
STR R500-171		Various locations on SH 141 a	03/17/22	20.00	70.00	50.46	20.00
M R100-351		FY22 R1 SIGN STRUCTURE REPLAC	03/17/22	10.00	100.00	78.50	100.00
STR092A-031			03/17/22	40.00	65.00	110.50	110.50
NHM765-007			03/31/22	100.00	50.00	74.62	57.00
		WEIGHTED AVERAGE FOR THE FIRST QUARTER		1,235.00	78.46	93.21	66.88
NH0504-911			04/07/22	120.00	61.90	74.55	94.10

PROJECT NUMBER	ITEM NUMBER/ PROJECT LOCATION	ITEM DESCRIPTION/ PROJECT LOCATION	DATE LET	UNIT/ QUANTITY	ENGR. EST.	AVERAGE BID	AWARDED BID
=====	208-00103	Removal and Disposal of Sediment (Labor)		Hour =====			
NHPP0702-413	VAIL PASS AUX PHASE 1 CAP 2		04/18/22	80.00	240.22	240.22	240.22
STM1151-038	SH115 MP 27 TO MP 38		04/21/22	1,080.00	55.00	58.54	50.00
2670703-479	I-70 BRIDGE OVER HARLAN		05/05/22	20.00	72.00	101.83	80.98
ER0702-420	PR I-70 GWC MATERIAL FLOWS 20		05/06/22	20.00	50.00	82.50	65.00
STA0712-019	SH 71: Frieight Improvements		05/12/22	60.00	70.00	49.74	49.74
STA001A-005	SH1 WELLINGTON SOUTH RESURFAC		05/12/22	10.00	65.00	91.75	48.00
NHC540-017	R2 CHAINUP STA @ KENOSHA/HOOS		05/12/22	40.00	66.00	109.67	49.00
CM760-047	COLFAX AND QUAIL		05/12/22	8.00	68.00	84.60	87.00
NHPP 3851-018	US 385 NORTH OF CHEYENNE WELL		05/26/22	60.00	70.00	55.50	60.00
C0852-120	Rehabilitation of Culvert by		05/26/22	16.00	125.00	50.00	50.00
FSA0702-409	I-70 VAIL WILDLIFE FENCE PHAS		05/26/22	10.00	100.00	90.00	90.00
ITS 0741-024	VMS SIGN INSTALLATIONS AND VS		06/02/22	30.00	75.00	106.00	120.00
FSA3921-019	SH 392 AND WCR 55 ISLANDS		06/02/22	10.00	55.00	55.00	65.00
NHPP072A-047	SH-72 RESURFACING: I-70 TO IN		06/09/22	30.00	55.00	144.54	144.54
FSA052A-046	SH52 WCR 37 INTERSECTION IMPR		06/09/22	144.00	95.00	61.00	45.00
NHPP0252-448	I-25 TREX NARROWS BRIDGE PREV		06/23/22	100.00	60.00	77.00	75.00
WEIGHTED AVERAGE FOR THE SECOND QUARTER				1,838.00	69.56	64.69	66.06
NHPP0702-414	VAIL PASS AUX PHASE 1 CAP 3		07/08/22	120.00	241.71	241.71	241.71
FBR0702-423	VAIL PASS AUX BE F-12-AT PHAS						
FSA052A-057	SH52 BOX CULVERT EXTENSION (M		08/04/22	60.00	100.00	61.00	65.52
STR0711-022	SH 71 OVER THE ARKANSAS		08/04/22	20.00	68.00	65.33	60.00
NHPP0063-054	US 6 FROM I70-B TO 33 RD. (MP		08/18/22	40.00	70.00	54.43	66.00
FBR0761-236	I-76 OVER CLR CRK SCOUR MIT		08/25/22	20.00	60.00	57.17	45.00
ER0502-092	US 50 MP 204 EB MONARCH TRUCK		08/29/22	10.00	70.00	139.58	294.99
BR0343-046	US 34 TIMBER BRIDGE REPL. PKG		08/31/22	24.00	49.37	116.25	116.25
FBR0343-047	US 6/US 34 TIMBER BRIDGE REPL						
NHPPR100-266	R1 ESSENTIAL REPAIRS		09/01/22	10.00	55.00	69.00	46.01
2670403-065	US40 FLOYD HILL ROUNDABOUTS		09/15/22	100.00	100.00	54.60	63.00
2670703-497	I-70 GENESEE WILDLIFE KING		09/15/22	10.00	100.00	65.71	80.39
SHE2873-193	US 287 & CO 52 INTERSECTION I		09/15/22	160.00	75.00	66.26	50.00
NHPP0701-231	I-70 SALT WASH BRIDGES SCOUR		09/29/22	40.00	120.00	31.32	5.00
WEIGHTED AVERAGE FOR THE THIRD QUARTER				614.00	114.98	74.14	96.38
NHPP0821-114	SH 82 ASPEN/INDEPENDENCE PASS		10/13/22	40.00	90.00	56.60	48.80
NHPP0701-253	I-70 EAST OF DEBEQUE		10/27/22	20.00	50.00	48.65	51.00
STA207A-004	Resurfacing SH207A MANZANOLA		10/27/22	40.00	60.00	65.40	81.20
NHPP0705-088	I-70 AGATE STRUCTURE REHAB		10/27/22	160.00	63.00	57.75	65.00
FSAM240-200	SH21B CO SPRINGS SIGNAL REPLA		10/27/22	30.00	40.00	103.75	100.00
C5502-111	US 550 MP 81 AND 89 RED MOUNT		10/27/22	10.00	90.00	122.50	170.00

PROJECT NUMBER	ITEM NUMBER/ PROJECT LOCATION	ITEM DESCRIPTION/ PROJECT LOCATION	DATE LET	UNIT/ QUANTITY	ENGR. EST.	AVERAGE BID	AWARDED BID
=====	208-00103	Removal and Disposal of Sediment (Labor)		Hour =====			
C170A-002		CRITICAL CULVERT CONST. PKG D	10/27/22	8.00	100.00	73.44	43.75
TRG0253-264		I-25 AND SH 119 PARK-N-RIDE	10/27/22	80.00	70.00	64.45	45.00
STA3852-015		US 385 HOLYOKE NORTH	10/27/22	224.00	60.00	53.00	53.00
NHPP0343-048		US 34 (MP 169.3-171.4)	11/01/22	11.00	63.00	76.85	157.00
STU0252-457		I-25:ALAMEDA RIVER PH 2.0	11/03/22	3,000.00	70.00	68.74	73.00
STR064A-010		SH 64 AND SH 13 AT MEEKER	11/10/22	20.00	60.00	50.75	51.50
NHPP0853-126		US85C: PLATTEVILLE NORTH MP (11/10/22	40.00	80.00	153.54	70.00
C5502-097		US550 MP 117.28-126.06	11/17/22	104.00	100.00	55.58	50.00
STRC090-011		US 50B AND SH71/CR18 INTERSEC	11/17/22	100.00	94.00	80.00	75.00
STAM420-001		US 285 AT HWY 9C IMPROVEMENTS	12/01/22	80.00	69.10	52.90	70.09
BR2854-148		INTERSECTION OF US 285 & SH 9					
STM0091-046		ADA RAMP IMPROVEMENTS - FAIRP					
STA0711-021		SH71: REGION LINE NORTH	12/01/22	60.00	59.00	53.61	60.00
STR114A-015		SH114 SILLSVILLE SOUTH TO MP3	12/01/22	40.00	70.00	56.00	60.00
2670703-487		I-70 BRIDGES OVER WARD ROAD-	12/01/22	200.00	50.00	84.58	180.00
NHPP0701-252		I-70 RIFLE TO SILT SLAB REPLA	12/01/22	20.00	90.00	53.50	40.00
IM025A-050		I25-MP103.9 - INTERSECTION DR	12/01/22	40.00	60.00	52.33	44.00
STR318A-001		SH 318 MP 0 - 12.5 MOFFAT COU	12/01/22	15.00	100.00	53.25	55.00
STR0641-107		SH 13 MM 104-128.1 IN MOFFAT	12/01/22	24.00	70.00	115.00	35.00
NHPP083A-046		SH83 RESURFACING STROH RD TO	12/08/22	20.00	75.00	174.46	124.91
NHPP0063-048		US6 / 20 ROAD INTERSECTION IM	12/15/22	100.00	70.00	51.45	50.00
NHPP0931-033		SH93:US6 TO 58TH RESURFACING	12/15/22	40.00	55.00	90.98	51.25
NHPP0502-090		SH 50 MP 134.6-136 GUNNISON C	12/22/22	80.00	75.00	108.42	52.61
STR0092-024		SH 9 North of Silverthorne	12/22/22	40.00	120.00	49.35	48.70
STA0361-129		US 36: HYGIENE RD AND NELSON	12/22/22	100.00	60.00	112.25	119.74
BR012A-048		CO 12 STRUCTURE P-17-F AT MP	12/22/22	80.00	60.00	47.34	44.00
STA385A-016		SH 385 MP 97.76	12/22/22	30.00	100.00	53.44	43.75
		WEIGHTED AVERAGE FOR THE FOURTH QUARTER		4,856.00	69.70	71.87	73.62
		WEIGHTED AVERAGE FOR THE YEAR		8,543.00	74.19	73.93	72.66
=====	208-00105	Removal and Disposal of Sediment (Equip)		Hour =====			
STR0505-050			01/13/22	10.00	120.00	206.67	100.00
NH0504-910		US50B I-24-B MIN REP AT MP 40	01/13/22	20.00	120.00	125.44	100.00
NHPP0702-383		I-70 EB AUX FRISCO TO SILVERT	01/13/22	250.00	150.00	197.34	289.00
NHPP1601-083			02/03/22	20.00	150.00	281.01	130.00
STA0252-459			02/03/22	10.00	117.01	172.30	87.50
C0762-055			02/17/22	60.00	120.00	132.54	165.00
STR0141-031			02/17/22	40.00	135.00	114.80	89.40
NHPP0063-063			02/24/22	20.00	150.00	82.50	40.00
STA 067A-048		Hwy 67A MP 0.00 TO MP 11.05 I	03/03/22	40.00	150.00	127.70	120.00
NHPP 0761-238		I-76 DAHLIA TO YORK	03/10/22	20.00	140.00	160.46	100.00
C0761-239							
NHPP0703-472			03/10/22	15.00	120.00	183.30	230.00

COLORADO DEPARTMENT OF TRANSPORTATION
ITEM UNIT COSTS BY PROJECTS -- 2022 COST DATA

11:31 Wednesday, March 8, 2023 130

PROJECT NUMBER	ITEM NUMBER/ PROJECT LOCATION	ITEM DESCRIPTION/ PROJECT LOCATION	DATE LET	UNIT/ QUANTITY	ENGR. EST.	AVERAGE BID	AWARDED BID
=====	208-00105	Removal and Disposal of Sediment (Equip)		Hour =====			
STR R500-171		Various locations on SH 141 a	03/17/22	20.00	173.00	114.90	20.00
STR092A-031			03/17/22	40.00	140.00	154.00	154.00
NHM765-007			03/31/22	100.00	120.00	148.08	136.80
		WEIGHTED AVERAGE FOR THE FIRST QUARTER		665.00	139.14	168.95	185.70
NH0504-911			04/07/22	120.00	131.43	126.80	123.60
NHPP0702-413		VAIL PASS AUX PHASE 1 CAP 2	04/18/22	80.00	125.40	125.40	125.40
STM1151-038		SH115 MP 27 TO MP 38	04/21/22	540.00	105.00	163.43	100.00
2670703-479		I-70 BRIDGE OVER HARLAN	05/05/22	20.00	130.00	197.93	138.82
ER0702-420		PR I-70 GWC MATERIAL FLOWS 20	05/06/22	20.00	150.00	162.50	125.00
STA0712-019		SH 71: Frieight Improvements	05/12/22	20.00	160.00	133.83	133.83
NHC540-017		R2 CHAINUP STA @ KENOSHA/HOOS	05/12/22	40.00	125.00	123.67	136.00
CM760-047		COLFAX AND QUAIL	05/12/22	8.00	145.00	151.40	92.00
NHPP 3851-018		US 385 NORTH OF CHEYENNE WELL	05/26/22	20.00	130.00	107.50	120.00
C0852-120		Rehabilitation of Culvert by	05/26/22	16.00	170.00	100.00	100.00
FSA0702-409		I-70 VAIL WILDLIFE FENCE PHAS	05/26/22	10.00	220.00	190.00	190.00
ITS 0741-024		VMS SIGN INSTALLATIONS AND VS	06/02/22	30.00	150.00	124.00	150.00
NHPP072A-047		SH-72 RESURFACING: I-70 TO IN	06/09/22	30.00	125.00	249.20	249.20
FSA052A-046		SH52 WCR 37 INTERSECTION IMPR	06/09/22	20.00	250.00	152.40	100.00
NHPP0252-448		I-25 TREX NARROWS BRIDGE PREV	06/23/22	100.00	115.00	90.25	95.00
		WEIGHTED AVERAGE FOR THE SECOND QUARTER		1,074.00	120.79	151.80	113.94
NHPP0702-414		VAIL PASS AUX PHASE 1 CAP 3	07/08/22	120.00	131.10	131.10	131.10
FBR0702-423		VAIL PASS AUX BE F-12-AT PHAS					
FSA052A-057		SH52 BOX CULVERT EXTENSION (M	08/04/22	20.00	150.00	114.61	166.92
STR0711-022		SH 71 OVER THE ARKANSAS	08/04/22	20.00	130.00	149.67	225.00
NHPP0063-054		US 6 FROM I70-B TO 33 RD. (MP	08/18/22	40.00	120.00	169.83	215.00
FBR0761-236		I-76 OVER CLR CRK SCOUR MIT	08/25/22	20.00	120.00	118.33	135.00
ER0502-092		US 50 MP 204 EB MONARCH TRUCK	08/29/22	10.00	150.00	156.52	182.06
BR0343-046		US 34 TIMBER BRIDGE REPL. PKG	08/31/22	24.00	137.49	88.36	88.36
FBR0343-047		US 6/US 34 TIMBER BRIDGE REPL					
NHPPR100-266		R1 ESSENTIAL REPAIRS	09/01/22	10.00	85.00	108.80	104.41
2670403-065		US40 FLOYD HILL ROUNDABOUTS	09/15/22	40.00	150.00	115.00	133.00
2670703-497		I-70_GENESEE WILDLIFE XING	09/15/22	10.00	150.00	119.31	116.53
SHE2873-193		US 287 & CO 52 INTERSECTION I	09/15/22	50.00	150.00	132.68	105.00
NHPP0701-231		I-70 SALT WASH BRIDGES SCOUR	09/29/22	40.00	180.00	57.67	5.00
		WEIGHTED AVERAGE FOR THE THIRD QUARTER		404.00	139.56	124.68	128.20
NHPP0701-253		I-70 EAST OF DEBEQUE	10/27/22	20.00	150.00	130.50	155.00

PROJECT NUMBER	ITEM NUMBER/ PROJECT LOCATION	ITEM DESCRIPTION/ PROJECT LOCATION	DATE LET	UNIT/ QUANTITY	ENGR. EST.	AVERAGE BID	AWARDED BID
=====	208-00105	Removal and Disposal of Sediment (Equip)		Hour =====			
STA207A-004		Resurfacing SH207A MANZANOLA	10/27/22	40.00	120.00	140.55	121.65
NHPP0705-088		I-70 AGATE STRUCTURE REHAB	10/27/22	160.00	130.00	115.68	106.00
FSAM240-200		SH21B CO SPRINGS SIGNAL REPLA	10/27/22	30.00	100.00	176.25	150.00
TRG0253-264		I-25 AND SH 119 PARK-N-RIDE	10/27/22	40.00	115.00	153.79	105.00
STA3852-015		US 385 HOLYOKE NORTH	10/27/22	64.00	120.00	96.00	96.00
NHPP0343-048		US 34 (MP 169.3-171.4)	11/01/22	4.00	130.00	163.11	335.00
STU0252-457		I-25:ALAMEDA RIVER PH 2.0	11/03/22	500.00	300.00	186.10	330.00
STR064A-010		SH 64 AND SH 13 AT MEEKER	11/10/22	20.00	150.00	125.00	125.00
NHPP0853-126		US85C: PLATTEVILLE NORTH MP (11/10/22	8.00	130.00	157.78	151.90
C5502-097		US550 MP 117.28-126.06	11/17/22	52.00	150.00	131.00	115.00
STR090-011		US 50B AND SH71/CR18 INTERSEC	11/17/22	100.00	160.00	145.00	140.00
STAM420-001		US 285 AT HWY 9C IMPROVEMENTS	12/01/22	80.00	117.10	174.81	321.74
BR2854-148		INTERSECTION OF US 285 & SH 9					
STM0091-046		ADA RAMP IMPROVEMENTS - FAIRP					
STA0711-021		SH71: REGION LINE NORTH	12/01/22	20.00	120.00	122.86	120.00
STR114A-015		SH114 SILLSVILLE SOUTH TO MP3	12/01/22	40.00	160.00	117.50	110.00
2670703-487		I-70 BRIDGES OVER WARD ROAD-	12/01/22	200.00	100.00	184.21	190.00
NHPP0701-252		I-70 RIFLE TO SILT SLAB REPLA	12/01/22	20.00	200.00	80.00	45.00
IM025A-050		I25-MP103.9 - INTERSECTION DR	12/01/22	40.00	130.00	132.33	150.00
NHPP083A-046		SH83 RESURFACING STROH RD TO	12/08/22	20.00	145.00	327.41	249.82
NHPP0063-048		US6 / 20 ROAD INTERSECTION IM	12/15/22	40.00	150.00	160.26	185.00
NHPP0931-033		SH93:US6 TO 58TH RESURFACING	12/15/22	40.00	125.00	133.23	102.55
NHPP0502-090		SH 50 MP 134.6-136 GUNNISON C	12/22/22	40.00	150.00	198.47	174.14
STR0092-024		SH 9 North of Silverthorne	12/22/22	12.00	120.00	150.50	111.00
STA0361-129		US 36: HYGIENE RD AND NELSON	12/22/22	100.00	95.00	157.20	124.99
BR012A-048		CO 12 STRUCTURE P-17-F AT MP	12/22/22	80.00	120.00	83.84	117.00
STA385A-016		SH 385 MP 97.76	12/22/22	30.00	150.00	107.38	112.50
		WEIGHTED AVERAGE FOR THE FOURTH QUARTER		1,800.00	174.75	160.38	196.89
		WEIGHTED AVERAGE FOR THE YEAR		3,943.00	150.44	156.93	165.69
=====	208-00106	Sweeping (Sediment Removal)		Hour =====			
ITS0703-477		ITS EQUIPMENT UPGRADE AT EJMT	01/06/22	20.00	150.00	605.00	605.00
NHPP2873-189		US 287 (FEDERAL BLVD) - COLFA	01/06/22	20.00	150.00	219.31	172.07
NH0504-910		US50B L-24-B MIN REP AT MP 40	01/13/22	20.00	200.00	176.49	100.00
NHPP0702-383		I-70 EB AUX FRISCO TO SILVERT	01/13/22	120.00	152.75	192.91	152.00
NHPP1601-083			02/03/22	40.00	150.00	217.84	200.00
STA0252-459			02/03/22	200.00	150.00	279.20	301.50
C0762-055			02/17/22	240.00	125.00	161.89	140.00
STR0141-031			02/17/22	40.00	200.00	221.67	250.00
NHPP0063-063			02/24/22	20.00	160.00	82.50	40.00
STA 067A-048		Hwy 67A MP 0.00 TO MP 11.05 I	03/03/22	40.00	150.00	167.70	180.00
NHPP 0761-238		I-76 DAHLIA TO YORK	03/10/22	20.00	150.00	207.52	100.00
C0761-239							

COLORADO DEPARTMENT OF TRANSPORTATION
ITEM UNIT COSTS BY PROJECTS -- 2022 COST DATA

11:31 Wednesday, March 8, 2023 132

PROJECT NUMBER	ITEM NUMBER/ PROJECT LOCATION	ITEM DESCRIPTION/ PROJECT LOCATION	DATE LET	UNIT/ QUANTITY	ENGR. EST.	AVERAGE BID	AWARDED BID
===== 208-00106							
		Sweeping (Sediment Removal)		Hour			
STR160A-034		US160A LA VETA PASS EAST SURF	03/17/22	40.00	160.00	197.87	165.74
BRC040-057			03/17/22	8.00	140.00	203.10	168.38
STR R500-171		Various locations on SH 141 a	03/17/22	60.00	280.00	131.85	20.00
M R100-351		FY22 R1 SIGN STRUCTURE REPLAC	03/17/22	10.00	300.00	194.50	271.00
STR092A-031			03/17/22	40.00	160.00	125.00	125.00
NHM765-007			03/31/22	200.00	150.00	291.23	285.00
C0703-499		EJMT GROUT BED REPAIR AND PAN	03/31/22	20.00	200.00	234.50	315.00
WEIGHTED AVERAGE FOR THE FIRST QUARTER				1,158.00	157.38	212.69	205.41
NH0504-911			04/07/22	150.00	178.32	232.75	235.50
NHPP0702-413		VAIL PASS AUX PHASE 1 CAP 2	04/18/22	80.00	199.11	199.11	199.11
STM1151-038		SH115 MP 27 TO MP 38	04/21/22	1,125.00	175.00	154.22	20.00
2670703-479		I-70 BRIDGE OVER HARLAN	05/05/22	40.00	150.00	184.08	185.10
ER0702-420		PR I-70 GWC MATERIAL FLOWS 20	05/06/22	10.00	150.00	225.00	200.00
STA0712-019		SH 71: Frieight Improvements	05/12/22	40.00	160.00	148.60	148.60
STA001A-005		SH1 WELLINGTON SOUTH RESURFAC	05/12/22	30.00	160.00	134.50	130.00
NHC540-017		R2 CHAINUP STA @ KENOSHA/HOOS	05/12/22	20.00	152.00	187.67	113.00
CM760-047		COLFAX AND QUAIL	05/12/22	8.00	174.00	267.40	92.00
NHPP 3851-018		US 385 NORTH OF CHEYENNE WELL	05/26/22	80.00	165.00	157.50	160.00
STAR100-358		3 STRUCTURES IN REGION 1 METR	05/26/22	5.00	200.00	187.61	125.00
C0852-120		Rehabilitation of Culvert by	05/26/22	20.00	200.00	100.00	100.00
FSA0702-409		I-70 VAIL WILDLIFE FENCE PHAS	05/26/22	20.00	200.00	180.00	180.00
ITS 0741-024		VMS SIGN INSTALLATIONS AND VS	06/02/22	20.00	50.00	109.00	120.00
NHPP072A-047		SH-72 RESURFACING: I-70 TO IN	06/09/22	30.00	150.00	178.00	178.00
FSA052A-046		SH52 WCR 37 INTERSECTION IMPR	06/09/22	120.00	250.00	138.40	85.00
MTCE0253-291		I-25 SIGN REPLACEMENT PHASE 2	06/16/22	10.00	160.00	156.56	222.11
NHPP0252-448		I-25 TREX NARROWS BRIDGE PREV	06/23/22	100.00	170.00	213.25	150.00
WEIGHTED AVERAGE FOR THE SECOND QUARTER				1,908.00	177.66	161.22	78.71
NHPP0702-414		VAIL PASS AUX PHASE 1 CAP 3	07/08/22	120.00	202.59	202.59	202.59
FBR0702-423		VAIL PASS AUX BE F-12-AT PHAS					
FSA052A-057		SH52 BOX CULVERT EXTENSION (M	08/04/22	50.00	200.00	190.45	143.52
STR0711-022		SH 71 OVER THE ARKANSAS	08/04/22	80.00	165.00	220.67	225.00
NHPP0063-054		US 6 FROM I70-B TO 33 RD. (MP	08/18/22	40.00	130.00	180.63	180.00
C1211-099		SH 121 NORTH SGA SIGNALS	08/25/22	200.00	200.00	151.00	120.00
ER0502-092		US 50 MP 204 EB MONARCH TRUCK	08/29/22	10.00	150.00	145.18	158.04
BR0343-046		US 34 TIMBER BRIDGE REPL. PKG	08/31/22	24.00	254.13	103.37	103.37
FBR0343-047		US 6/US 34 TIMBER BRIDGE REPL					
STAR100-374		5 STRUCTURES IN REGION 1	09/01/22	10.00	200.00	113.73	113.73
NHPPR100-266		R1 ESSENTIAL REPAIRS	09/01/22	50.00	85.00	203.71	114.14

PROJECT NUMBER	ITEM NUMBER/ PROJECT LOCATION	ITEM DESCRIPTION/ PROJECT LOCATION	DATE LET	UNIT/ QUANTITY	ENGR. EST.	AVERAGE BID	AWARDED BID
===== 208-00106		Sweeping (Sediment Removal)		Hour =====			
ER0253-297		WCR 34 BRIDGE OVER I-25(MM 24	09/14/22	20.00	200.00	220.94	200.00
2670403-065		US40 FLOYD HILL ROUNDABOUTS	09/15/22	40.00	250.00	142.33	175.00
2670703-497		I-70 GENESEE WILDLIFE XING	09/15/22	60.00	160.00	148.20	99.96
SHE2873-193		US 287 & CO 52 INTERSECTION I	09/15/22	320.00	150.00	185.08	190.00
NHPP0701-231		I-70 SALT WASH BRIDGES SCOUR	09/29/22	40.00	150.00	168.05	120.00
		WEIGHTED AVERAGE FOR THE THIRD QUARTER		1,064.00	173.08	179.13	163.71
C0831-126		SH83 EL PASO COUNTY TO BAYOU	10/13/22	16.00	205.00	147.50	250.00
NHPP0701-253		I-70 EAST OF DEBEQUE	10/27/22	20.00	175.00	244.20	400.00
STA207A-004		Resurfacing SH207A MANZANOLA	10/27/22	40.00	175.00	235.17	230.50
NHPP0705-088		I-70 AGATE STRUCTURE REHAB	10/27/22	160.00	160.00	160.81	177.00
FSAM240-200		SH21B CO SPRINGS SIGNAL REPLA	10/27/22	40.00	110.00	212.50	105.00
TRG0253-264		I-25 AND SH 119 PARK-N-RIDE	10/27/22	80.00	150.00	163.27	150.00
STA3852-015		US 385 HOLYOKE NORTH	10/27/22	224.00	150.00	134.00	134.00
NHPP0343-048		US 34 (MP 169.3-171.4)	11/01/22	66.00	160.00	149.86	250.00
STU0252-457		I-25:ALAMEDA RIVER PH 2.0	11/03/22	180.00	170.00	181.32	198.00
SHE0242-087		US 24 SAFETY IMPRVMENTS, E OF	11/03/22	16.00	124.00	175.39	186.18
STR064A-010		SH 64 AND SH 13 AT MEEKER	11/10/22	20.00	150.00	137.50	150.00
NHPP0853-126		US85C: PLATTEVILLE NORTH MP (11/10/22	40.00	150.00	191.40	160.00
C5502-097		US550 MP 117.28-126.06	11/17/22	52.00	170.00	238.74	95.00
STRC090-011		US 50B AND SH71/CR18 INTERSEC	11/17/22	20.00	200.00	219.50	255.00
STA0711-021		SH71: REGION LINE NORTH	12/01/22	176.00	150.00	200.67	170.00
STR114A-015		SH114 SILLSVILLE SOUTH TO MP3	12/01/22	40.00	160.00	210.00	160.00
2670703-487		I-70 BRIDGES OVER WARD ROAD-	12/01/22	120.00	100.00	194.60	190.00
NHPP0701-252		I-70 RIFLE TO SILT SLAB REPLA	12/01/22	20.00	200.00	295.00	165.00
IM025A-050		I25-MP103.9 - INTERSECTION DR	12/01/22	50.00	160.00	143.33	180.00
NHPP0021-041		SH2 RESURFACING MLK TO 52ND	12/01/22	20.00	200.00	210.95	175.00
NHPP083A-046		SH83 RESURFACING STROH RD TO	12/08/22	40.00	170.00	290.06	206.11
NHPP0063-048		US6 / 20 ROAD INTERSECTION IM	12/15/22	40.00	180.00	178.39	152.00
NHM175-029		CANON CITY, CO	12/15/22	15.00	170.00	132.50	250.00
NHPP0931-033		SH93:US6 TO 58TH RESURFACING	12/15/22	40.00	150.00	177.96	153.80
NHPP0502-090		SH 50 MP 134.6-136 GUNNISON C	12/22/22	50.00	180.00	194.82	274.97
STR0092-024		SH 9 North of Silverthorne	12/22/22	30.00	200.00	154.00	157.00
STA0361-129		US 36: HYGIENE RD AND NELSON	12/22/22	100.00	180.00	180.46	176.32
BR012A-048		CO 12 STRUCTURE P-17-F AT MP	12/22/22	40.00	150.00	307.38	117.00
STR096A-050		SH 96 MP 168.99 TO 193.77	12/22/22	20.00	160.00	231.67	200.00
		WEIGHTED AVERAGE FOR THE FOURTH QUARTER		1,775.00	157.70	185.13	176.94
		WEIGHTED AVERAGE FOR THE YEAR		5,905.00	166.86	180.53	148.78
===== 208-00107		Rem Trash		Hour =====			
ITS0703-477		ITS EQUIPMENT UPGRADE AT EJMT	01/06/22	20.00	100.00	160.00	160.00

PROJECT NUMBER	ITEM NUMBER/ PROJECT LOCATION	ITEM DESCRIPTION/ PROJECT LOCATION	DATE LET	UNIT/ QUANTITY	ENGR. EST.	AVERAGE BID	AWARDED BID
=====	208-00107	Rem Trash		Hour =====			
MTCE R500-218			01/06/22	16.00	75.00	64.00	28.00
NHPP2873-189		US 287 (FEDERAL BLVD) - COLFA	01/06/22	40.00	98.00	159.81	90.53
NH0504-910		US50B L-24-B MIN REP AT MP 40	01/13/22	10.00	100.00	106.69	50.00
NHPP0702-383		I-70 EB AUX FRISCO TO SILVERT	01/13/22	60.00	40.00	159.67	160.00
NHPP1601-083			02/03/22	25.00	50.00	371.30	100.00
STA0252-459			02/03/22	100.00	90.00	222.76	123.00
C0762-055			02/17/22	40.00	70.00	135.83	100.00
STR0141-031			02/17/22	16.00	150.00	68.37	51.10
NHPP0063-063			02/24/22	20.00	80.00	87.50	40.00
STA 067A-048		Hwy 67A MP 0.00 TO MP 11.05 I	03/03/22	40.00	100.00	79.15	90.00
NHPP0703-472			03/10/22	40.00	105.00	154.06	120.00
STR160A-034		US160A LA VETA PASS EAST SURF	03/17/22	20.00	50.00	127.87	165.74
BRC040-057			03/17/22	10.00	100.00	101.72	52.89
STR R500-171		Various locations on SH 141 a	03/17/22	40.00	116.00	80.90	20.00
M R100-351		FY22 R1 SIGN STRUCTURE REPLAC	03/17/22	10.00	95.00	118.00	100.00
STR092A-031			03/17/22	40.00	100.00	242.00	242.00
NHM765-007			03/31/22	100.00	95.00	166.38	57.00
		WEIGHTED AVERAGE FOR THE FIRST QUARTER		647.00	87.88	155.74	103.88
NH0504-911			04/07/22	120.00	98.46	84.55	94.10
STM1151-038		SH115 MP 27 TO MP 38	04/21/22	100.00	50.00	99.47	50.00
ER0702-420		PR I-70 GWC MATERIAL FLOWS 20	05/06/22	30.00	50.00	230.00	110.00
STA0712-019		SH 71: Frieight Improvements	05/12/22	20.00	100.00	68.84	68.84
NHC540-017		R2 CHAINUP STA @ KENOSHA/HOOS	05/12/22	20.00	105.00	132.67	48.00
NHPP 3851-018		US 385 NORTH OF CHEYENNE WELL	05/26/22	30.00	110.00	65.50	80.00
STAR100-358		3 STRUCTURES IN REGION 1 METR	05/26/22	5.00	100.00	387.20	202.00
C0852-120		Rehabilitation of Culvert by	05/26/22	8.00	185.00	50.00	50.00
FSA0702-409		I-70 VAIL WILDLIFE FENCE PHAS	05/26/22	20.00	100.00	50.00	50.00
ITS 0741-024		VMS SIGN INSTALLATIONS AND VS	06/02/22	20.00	50.00	106.00	120.00
FSA3921-019		SH 392 AND WCR 55 ISLANDS	06/02/22	3.00	90.00	130.00	140.00
NHPP072A-047		SH-72 RESURFACING: I-70 TO IN	06/09/22	20.00	100.00	124.60	124.60
FSA052A-046		SH52 WCR 37 INTERSECTION IMPR	06/09/22	30.00	150.00	103.80	45.00
NHPP0252-448		I-25 TREX NARROWS BRIDGE PREV	06/23/22	100.00	110.00	88.25	75.00
		WEIGHTED AVERAGE FOR THE SECOND QUARTER		526.00	92.14	101.79	77.76
STR0711-022		SH 71 OVER THE ARKANSAS	08/04/22	80.00	108.00	87.67	75.00
NHPP0063-054		US 6 FROM I70-B TO 33 RD. (MP	08/18/22	40.00	100.00	66.75	66.00
FBR0761-236		I-76 OVER CLR CRK SCOUR MIT	08/25/22	32.00	100.00	92.83	45.00
C1211-099		SH 121 NORTH SGA SIGNALS	08/25/22	50.00	200.00	116.50	95.00
BR0343-046		US 34 TIMBER BRIDGE REPL. PKG	08/31/22	24.00	183.28	194.10	194.10

PROJECT NUMBER	ITEM NUMBER/ PROJECT LOCATION	ITEM DESCRIPTION/ PROJECT LOCATION	DATE LET	UNIT/ QUANTITY	ENGR. EST.	AVERAGE BID	AWARDED BID
===== 208-00107		Rem Trash		Hour =====			
FBR0343-047		US 6/US 34 TIMBER BRIDGE REPL					
STAR100-374		5 STRUCTURES IN REGION 1	09/01/22	10.00	200.00	173.69	173.69
NHPPR100-266		R1 ESSENTIAL REPAIRS	09/01/22	15.00	100.00	406.07	113.21
2670403-065		US40_FLOYD HILL ROUNDABOUTS	09/15/22	20.00	100.00	61.93	85.00
2670703-497		I-70_GENESEE WILDLIFE KING	09/15/22	60.00	100.00	119.82	197.04
SHE2873-193		US 287 & CO 52 INTERSECTION I	09/15/22	24.00	120.00	110.20	50.00
NHPP0701-231		I-70 SALT WASH BRIDGES SCOUR	09/29/22	20.00	130.00	139.61	40.00
		WEIGHTED AVERAGE FOR THE THIRD QUARTER		375.00	125.92	116.84	102.52
C0831-126		SH83 EL PASO COUNTY TO BAYOU	10/13/22	2.00	200.00	37.50	50.00
NHPP0701-253		I-70 EAST OF DEBEQUE	10/27/22	10.00	150.00	48.65	51.00
STA207A-004		Resurfacing SH207A MANZANOLA	10/27/22	40.00	120.00	98.93	141.80
NHPP0705-088		I-70 AGATE STRUCTURE REHAB	10/27/22	160.00	86.00	68.23	70.00
FSAM240-200		SH21B CO SPRINGS SIGNAL REPLA	10/27/22	30.00	50.00	124.25	95.00
C5502-111		US 550 MP 81 AND 89 RED MOUNT	10/27/22	10.00	80.00	127.50	180.00
TRG0253-264		I-25 AND SH 119 PARK-N-RIDE	10/27/22	40.00	100.00	97.42	45.00
STA3852-015		US 385 HOLYOKE NORTH	10/27/22	40.00	70.00	53.00	53.00
STU0252-457		I-25:ALAMEDA RIVER PH 2.0	11/03/22	650.00	175.00	128.05	230.00
SHE0242-087		US 24 SAFETY IMPRVMENTS, E OF	11/03/22	8.00	77.00	75.79	84.36
STR064A-010		SH 64 AND SH 13 AT MEEKER	11/10/22	5.00	200.00	64.50	54.00
NHPP0853-126		US85C: PLATTEVILLE NORTH MP (11/10/22	32.00	90.00	144.00	120.00
C5502-097		US550 MP 117.28-126.06	11/17/22	26.00	140.00	203.56	50.00
STAM420-001		US 285 AT HWY 9C IMPROVEMENTS	12/01/22	80.00	92.60	142.50	314.48
BR2854-148		INTERSECTION OF US 285 & SH 9					
STM0091-046		ADA RAMP IMPROVEMENTS - FAIRP					
2670703-487		I-70 BRIDGES OVER WARD ROAD-	12/01/22	200.00	60.00	110.61	110.00
NHPP0701-252		I-70 RIFLE TO SILT SLAB REPLA	12/01/22	15.00	180.00	77.50	72.00
IM025A-050		I25-MP103.9 - INTERSECTION DR	12/01/22	50.00	90.00	92.67	90.00
STR318A-001		SH 318 MP 0 - 12.5 MOFFAT COU	12/01/22	15.00	150.00	52.25	55.00
STR109A-019		M-22-AY BRIDGE REHAB ON SH109	12/01/22	10.00	100.00	135.16	146.32
NHPP0021-041		SH2 RESURFACING MLK TO 52ND	12/01/22	10.00	200.00	142.01	90.42
STR0641-107		SH 13 MM 104-128.1 IN MOFFAT	12/01/22	10.00	100.00	156.67	35.00
NHPP083A-046		SH83 RESURFACING STROH RD TO	12/08/22	40.00	120.00	116.96	124.91
NHPP0063-048		US6 / 20 ROAD INTERSECTION IM	12/15/22	10.00	130.00	130.45	50.00
NHPP0931-033		SH93:US6 TO 58TH RESURFACING	12/15/22	20.00	100.00	95.98	51.25
NHPP0502-090		SH 50 MP 134.6-136 GUNNISON C	12/22/22	50.00	115.00	147.55	220.71
STR0092-024		SH 9 North of Silverthorne	12/22/22	16.00	200.00	100.50	150.00
STA0361-129		US 36: HYGIENE RD AND NELSON	12/22/22	40.00	75.00	123.67	162.87
BR012A-048		CO 12 STRUCTURE P-17-F AT MP	12/22/22	40.00	90.00	72.67	44.00
		WEIGHTED AVERAGE FOR THE FOURTH QUARTER		1,659.00	125.35	115.34	157.66
		WEIGHTED AVERAGE FOR THE YEAR		3,207.00	112.41	121.03	127.63
===== 208-00146		Pre-fab Conc Washout Str (Type 2)		Each =====			
NHPP1601-083			02/03/22	1.00	1500.00	2977.08	400.00
		WEIGHTED AVERAGE FOR THE FIRST QUARTER		1.00	1500.00	2977.08	400.00

COLORADO DEPARTMENT OF TRANSPORTATION
ITEM UNIT COSTS BY PROJECTS -- 2022 COST DATA

11:31 Wednesday, March 8, 2023 136

PROJECT NUMBER	ITEM NUMBER/ PROJECT LOCATION	ITEM DESCRIPTION/ PROJECT LOCATION	DATE LET	UNIT/ QUANTITY	ENGR. EST.	AVERAGE BID	AWARDED BID
=====	208-00146	Pre-fab Conc Washout Str (Type 2)		Each	=====		
NHPP 3851-018		US 385 NORTH OF CHEYENNE WELL	05/26/22	1.00	2200.00	650.00	800.00
FSA052A-046		SH52 WCR 37 INTERSECTION IMPR	06/09/22	3.00	3000.00	971.20	525.00
		WEIGHTED AVERAGE FOR THE SECOND QUARTER		4.00	2800.00	933.41	593.75
FSA052A-057		SH52 BOX CULVERT EXTENSION (M	08/04/22	2.00	2000.00	1617.46	977.60
		WEIGHTED AVERAGE FOR THE THIRD QUARTER		2.00	2000.00	1617.46	977.60
NHPP0343-048		US 34 (MP 169.3-171.4)	11/01/22	1.00	2000.00	2379.27	3200.00
NHPP0853-126		US85C: PLATTEVILLE NORTH MP (11/10/22	2.00	1500.00	1766.40	610.00
STA0711-021		SH71: REGION LINE NORTH	12/01/22	5.00	1400.00	3163.33	500.00
		WEIGHTED AVERAGE FOR THE FOURTH QUARTER		8.00	1500.00	2573.48	865.00
		WEIGHTED AVERAGE FOR THE YEAR		15.00	1913.33	1965.89	776.68
=====	208-00200	Erosion Control Management		LUMP SUM	=====		
ER0253-297		WCR 34 BRIDGE OVER I-25(MM 24	09/14/22	1.00	5500.00	20525.00	1100.00
		WEIGHTED AVERAGE FOR THE THIRD QUARTER		1.00	5500.00	20525.00	1100.00
		WEIGHTED AVERAGE FOR THE YEAR		1.00	5500.00	20525.00	1100.00
=====	208-00207	Erosion Control Management		Day	=====		
NH0504-910		US50B L-24-B MIN REP AT MP 40	01/13/22	30.00	300.00	295.74	75.00
NHPP0702-383		I-70 EB AUX FRISCO TO SILVERT	01/13/22	80.00	500.00	561.64	720.00
NHPP1601-083			02/03/22	40.00	300.00	580.04	500.00
STA0252-459			02/03/22	200.00	270.11	307.83	197.00
C0762-055			02/17/22	30.00	400.00	321.77	400.00
NHPP0063-063			02/24/22	115.00	260.00	672.50	75.00
NHPP 0761-238		I-76 DAHLIA TO YORK	03/10/22	546.00	250.00	192.47	10.00

COLORADO DEPARTMENT OF TRANSPORTATION
 ITEM UNIT COSTS BY PROJECTS -- 2022 COST DATA

11:31 Wednesday, March 8, 2023 137

PROJECT NUMBER	ITEM NUMBER/ PROJECT LOCATION	ITEM DESCRIPTION/ PROJECT LOCATION	DATE LET	UNIT/ QUANTITY	ENGR. EST.	AVERAGE BID	AWARDED BID
=====	208-00207	Erosion Control Management		Day =====			
C0761-239							
STR160A-034		US160A LA VETA PASS EAST SURF	03/17/22	25.00	200.00	529.10	718.20
STR092A-031			03/17/22	32.00	200.00	450.00	450.00
NHM765-007			03/31/22	200.00	240.00	296.32	228.00
		WEIGHTED AVERAGE FOR THE FIRST QUARTER		1,298.00	271.82	264.79	172.03
NH0504-911			04/07/22	140.00	279.88	97.00	144.00
NHPP0702-413		VAIL PASS AUX PHASE 1 CAP 2	04/18/22	40.00	1284.00	1284.00	1284.00
STM1151-038		SH115 MP 27 TO MP 38	04/21/22	150.00	340.00	486.90	300.00
2670703-479		I-70 BRIDGE OVER HARLAN	05/05/22	497.00	150.00	233.30	330.00
STA0712-019		SH 71: Frieight Improvements	05/12/22	40.00	250.00	172.88	172.88
NHC540-017		R2 CHAINUP STA @ KENOSHA/HOOS	05/12/22	70.00	300.00	222.00	316.00
NHPP 3851-018		US 385 NORTH OF CHEYENNE WELL	05/26/22	16.00	300.00	687.50	500.00
ITS 0741-024		VMS SIGN INSTALLATIONS AND VS	06/02/22	15.00	150.00	1113.00	988.00
FSA3921-019		SH 392 AND WCR 55 ISLANDS	06/02/22	5.00	280.00	339.33	300.00
FSA052A-046		SH52 WCR 37 INTERSECTION IMPR	06/09/22	12.00	350.00	382.40	115.00
		WEIGHTED AVERAGE FOR THE SECOND QUARTER		985.00	263.70	287.53	340.37
NHPP0702-414		VAIL PASS AUX PHASE 1 CAP 3	07/08/22	52.00	1234.62	1234.62	1234.62
FBR0702-423		VAIL PASS AUX BE F-12-AT PHAS					
STR0711-022		SH 71 OVER THE ARKANSAS	08/04/22	40.00	322.00	203.33	200.00
NHPP0063-054		US 6 FROM I70-B TO 33 RD. (MP	08/18/22	174.00	110.00	175.57	100.00
FBR0761-236		I-76 OVER CLR CRK SCOUR MIT	08/25/22	120.00	250.00	173.33	100.00
ER0502-092		US 50 MP 204 EB MONARCH TRUCK	08/29/22	7.00	300.00	685.56	1625.44
BR0343-046		US 34 TIMBER BRIDGE REPL. PKG	08/31/22	99.00	456.26	519.11	519.11
FBR0343-047		US 6/US 34 TIMBER BRIDGE REPL					
NHPPR100-266		R1 ESSENTIAL REPAIRS	09/01/22	30.00	150.00	250.27	349.80
2670403-065		US40 FLOYD HILL ROUNDABOUTS	09/15/22	100.00	400.00	250.01	170.00
2670703-497		I-70 GENESEE WILDLIFE XING	09/15/22	60.00	200.00	344.63	209.88
SHE2873-193		US 287 & CO 52 INTERSECTION I	09/15/22	40.00	230.00	325.69	290.00
NHPP0701-231		I-70 SALT WASH BRIDGES SCOUR	09/29/22	85.00	225.00	617.53	1100.00
		WEIGHTED AVERAGE FOR THE THIRD QUARTER		807.00	320.09	316.80	383.59
STA207A-004		Resurfacing SH207A MANZANOLA	10/27/22	140.00	400.00	404.88	914.65
NHPP0705-088		I-70 AGATE STRUCTURE REHAB	10/27/22	40.00	240.00	481.33	842.00
C170A-002		CRITICAL CULVERT CONST. PKG D	10/27/22	30.00	300.00	300.00	100.00

PROJECT NUMBER	ITEM NUMBER/ PROJECT LOCATION	ITEM DESCRIPTION/ PROJECT LOCATION	DATE LET	UNIT/ QUANTITY	ENGR. EST.	AVERAGE BID	AWARDED BID
===== 208-00207 Erosion Control Management Day =====							
TRG0253-264		I-25 AND SH 119 PARK-N-RIDE	10/27/22	120.00	265.00	287.45	300.00
STA3852-015		US 385 HOLYOKE NORTH	10/27/22	56.00	650.00	700.00	700.00
NHPP0343-048		US 34 (MP 169.3-171.4)	11/01/22	30.00	300.00	343.10	400.00
STU0252-457		I-25:ALAMEDA RIVER PH 2.0	11/03/22	500.00	400.00	350.08	410.00
SHE0242-087		US 24 SAFETY IMPRVMENTS, E OF	11/03/22	60.00	240.00	132.99	223.96
NHPP0853-126		US85C: PLATTEVILLE NORTH MP (11/10/22	10.00	500.00	550.70	280.00
C5502-097		US550 MP 117.28-126.06	11/17/22	180.00	600.00	453.43	735.00
STRC090-011		US 50B AND SH71/CR18 INTERSEC	11/17/22	30.00	450.00	1042.50	1150.00
STAM420-001		US 285 AT HWY 9C IMPROVEMENTS	12/01/22	52.00	354.00	760.64	507.55
BR2854-148		INTERSECTION OF US 285 & SH 9					
STM0091-046		ADA RAMP IMPROVEMENTS - FAIRP					
2670703-487		I-70 BRIDGES OVER WARD ROAD-	12/01/22	180.00	189.80	301.40	110.00
IM025A-050		I25-MP103.9 - INTERSECTION DR	12/01/22	60.00	250.00	500.00	450.00
NHPP0063-048		US6 / 20 ROAD INTERSECTION IM	12/15/22	61.00	200.00	340.86	50.00
NHPP0931-033		SH93:US6 TO 58TH RESURFACING	12/15/22	80.00	250.00	354.14	266.60
NHPP0502-090		SH 50 MP 134.6-136 GUNNISON C	12/22/22	42.00	300.00	725.34	651.15
BR012A-048		CO 12 STRUCTURE P-17-F AT MP	12/22/22	30.00	250.00	338.67	500.00
STA385A-016		SH 385 MP 97.76	12/22/22	35.00	300.00	698.75	200.00
		WEIGHTED AVERAGE FOR THE FOURTH QUARTER		1,736.00	358.91	393.58	455.46
		WEIGHTED AVERAGE FOR THE YEAR		4,826.00	309.56	318.80	345.65
===== 208-00300 Temporary Berms Lin Foot =====							
NHPP1601-083			02/03/22	22,725.00	3.00	1.37	2.00
		WEIGHTED AVERAGE FOR THE FIRST QUARTER		22,725.00	3.00	1.37	2.00
STM1151-038		SH115 MP 27 TO MP 38	04/21/22	500.00	5.00	7.60	1.94
STA0712-019		SH 71: Frieight Improvements	05/12/22	22,962.00	3.00	0.51	0.51
		WEIGHTED AVERAGE FOR THE SECOND QUARTER		23,462.00	3.04	1.21	0.54
STU0252-457		I-25:ALAMEDA RIVER PH 2.0	11/03/22	1,500.00	1.80	7.91	15.00
		WEIGHTED AVERAGE FOR THE FOURTH QUARTER		1,500.00	1.80	7.91	15.00
		WEIGHTED AVERAGE FOR THE YEAR		47,687.00	2.98	1.70	1.69
===== 208-00301 Temporary Diversion Lin Foot =====							
BRC040-057			03/17/22	175.00	120.00	195.96	261.84
		WEIGHTED AVERAGE FOR THE FIRST QUARTER		175.00	120.00	195.96	261.84

COLORADO DEPARTMENT OF TRANSPORTATION
 ITEM UNIT COSTS BY PROJECTS -- 2022 COST DATA

11:31 Wednesday, March 8, 2023 139

PROJECT NUMBER	ITEM NUMBER/ PROJECT LOCATION	ITEM DESCRIPTION/ PROJECT LOCATION	DATE LET	UNIT/ QUANTITY	ENGR. EST.	AVERAGE BID	AWARDED BID
=====	208-00301	Temporary Diversion		Lin Foot	=====		
FBR0761-236		I-76 OVER CLR CRK SCOUR MIT	08/25/22	550.00	260.00	529.00	68.00
		WEIGHTED AVERAGE FOR THE THIRD QUARTER		550.00	260.00	529.00	68.00
IM025A-050		I25-MP103.9 - INTERSECTION DR	12/01/22	300.00	200.00	86.67	150.00
STR109A-019		M-22-AY BRIDGE REHAB ON SH109	12/01/22	60.00	65.00	62.39	59.78
		WEIGHTED AVERAGE FOR THE FOURTH QUARTER		360.00	177.50	120.09	99.59
		WEIGHTED AVERAGE FOR THE YEAR		1,085.00	210.05	301.59	108.44
=====	208-00400	Water Control		LUMP SUM	=====		
NHPP 0761-238		I-76 DAHLIA TO YORK	03/10/22	1.00	30000.00	27164.11	1000.00
C0761-239		WEIGHTED AVERAGE FOR THE FIRST QUARTER		1.00	30000.00	27164.11	1000.00
2670703-479		I-70 BRIDGE OVER HARLAN	05/05/22	1.00	2000.00	44061.62	7601.39
		WEIGHTED AVERAGE FOR THE SECOND QUARTER		1.00	2000.00	44061.62	7601.39
ER0502-092		US 50 MP 204 EB MONARCH TRUCK	08/29/22	1.00	100000.00	164453.46	8360.38
NHPPR100-266		R1 ESSENTIAL REPAIRS	09/01/22	1.00	300000.00	297793.58	313380.75
		WEIGHTED AVERAGE FOR THE THIRD QUARTER		2.00	200000.00	231123.52	160870.57
TRG0253-264		I-25 AND SH 119 PARK-N-RIDE	10/27/22	1.00	15000.00	33560.82	15000.00
C5502-097		US550 MP 117.28-126.06	11/17/22	1.00	70000.00	66786.78	29500.00
STAM420-001		US 285 AT HWY 9C IMPROVEMENTS	12/01/22	1.00	50000.00	106152.48	53883.26

COLORADO DEPARTMENT OF TRANSPORTATION
ITEM UNIT COSTS BY PROJECTS -- 2022 COST DATA

11:31 Wednesday, March 8, 2023 140

PROJECT NUMBER	ITEM NUMBER/ PROJECT LOCATION	ITEM DESCRIPTION/ PROJECT LOCATION	DATE LET	UNIT/ QUANTITY	ENGR. EST.	AVERAGE BID	AWARDED BID
===== 208-00400 Water Control LUMP SUM =====							
BR2854-148		INTERSECTION OF US 285 & SH 9					
STM0091-046		ADA RAMP IMPROVEMENTS - FAIRP					
IM025A-050		I25-MP103.9 - INTERSECTION DR	12/01/22	1.00	20000.00	88333.33	100000.00
NHPP0502-090		SH 50 MP 134.6-136 GUNNISON C	12/22/22	1.00	10000.00	44779.36	67575.30
BR012A-048		CO 12 STRUCTURE P-17-F AT MP	12/22/22	1.00	10000.00	125000.00	100000.00
STA385A-016		SH 385 MP 97.76	12/22/22	1.00	40000.00	113500.00	75000.00
	WEIGHTED AVERAGE FOR THE FOURTH QUARTER			7.00	30714.29	71943.23	62994.08
	WEIGHTED AVERAGE FOR THE YEAR			11.00	58818.18	80709.74	70118.28
===== 208-00520 Temp Stream Crossing LUMP SUM =====							
NHPP0702-414		VAIL PASS AUX PHASE 1 CAP 3	07/08/22	1.00	703374.62	703374.62	703374.62
FBR0702-423		VAIL PASS AUX BE F-12-AT PHAS					
	WEIGHTED AVERAGE FOR THE THIRD QUARTER			1.00	703374.62	703374.62	703374.62
STU0252-457		I-25:ALAMEDA RIVER PH 2.0	11/03/22	1.00	75000.00	545019.65	315000.00
	WEIGHTED AVERAGE FOR THE FOURTH QUARTER			1.00	75000.00	545019.65	315000.00
	WEIGHTED AVERAGE FOR THE YEAR			2.00	389187.31	584608.40	509187.31
===== 209-00000 Water M Gallon =====							
BR0343-046		US 34 TIMBER BRIDGE REPL. PKG	08/31/22	48.00	395.41	1027.60	1027.60
FBR0343-047		US 6/US 34 TIMBER BRIDGE REPL					
	WEIGHTED AVERAGE FOR THE THIRD QUARTER			48.00	395.41	1027.60	1027.60
	WEIGHTED AVERAGE FOR THE YEAR			48.00	395.41	1027.60	1027.60
===== 210-00001 Res Structure Each =====							
NHM765-007			03/31/22	2.00	300.00	5984.09	3990.00
C0703-499		EJMT GROUT BED REPAIR AND PAN	03/31/22	12.00	5000.00	5937.50	4000.00
	WEIGHTED AVERAGE FOR THE FIRST QUARTER			14.00	4328.57	5946.82	3998.57

COLORADO DEPARTMENT OF TRANSPORTATION
ITEM UNIT COSTS BY PROJECTS -- 2022 COST DATA

11:31 Wednesday, March 8, 2023 141

PROJECT NUMBER	ITEM NUMBER/ PROJECT LOCATION	ITEM DESCRIPTION/ PROJECT LOCATION	DATE LET	UNIT/ QUANTITY	ENGR. EST.	AVERAGE BID	AWARDED BID
===== 210-00001		Res Structure		Each	=====	=====	=====
NHPP072A-047		SH-72 RESURFACING: I-70 TO IN	06/09/22	1.00	5000.00	7533.06	7533.06
		WEIGHTED AVERAGE FOR THE SECOND QUARTER		1.00	5000.00	7533.06	7533.06
FBR0761-236		I-76 OVER CLR CRK SCOUR MIT	08/25/22	3.00	10000.00	1900.00	800.00
		WEIGHTED AVERAGE FOR THE THIRD QUARTER		3.00	10000.00	1900.00	800.00
TRG0253-264		I-25 AND SH 119 PARK-N-RIDE	10/27/22	1.00	5000.00	5874.73	1900.00
NHPP0931-033		SH93:US6 TO 58TH RESURFACING	12/15/22	3.00	10000.00	3880.32	1535.00
		WEIGHTED AVERAGE FOR THE FOURTH QUARTER		4.00	8750.00	6061.12	4417.50
		WEIGHTED AVERAGE FOR THE YEAR		22.00	5936.36	5481.60	3850.75
===== 210-00009		Res Communications Cabinet		Each	=====	=====	=====
2670703-487		I-70 BRIDGES OVER WARD ROAD-	12/01/22	2.00	5000.00	1196.44	1200.00
		WEIGHTED AVERAGE FOR THE FOURTH QUARTER		2.00	5000.00	1196.44	1200.00
		WEIGHTED AVERAGE FOR THE YEAR		2.00	5000.00	1196.44	1200.00
===== 210-00010		Res Mailbox Str		Each	=====	=====	=====
STM1151-038		SH115 MP 27 TO MP 38	04/21/22	6.00	435.00	486.97	1000.00
FSA052A-046		SH52 WCR 37 INTERSECTION IMPR	06/09/22	9.00	450.00	356.28	135.00
		WEIGHTED AVERAGE FOR THE SECOND QUARTER		15.00	444.00	408.56	481.00
C5502-097		US550 MP 117.28-126.06	11/17/22	1.00	500.00	552.09	378.00
		WEIGHTED AVERAGE FOR THE FOURTH QUARTER		1.00	500.00	552.09	378.00
		WEIGHTED AVERAGE FOR THE YEAR		16.00	447.50	414.08	474.56

COLORADO DEPARTMENT OF TRANSPORTATION
ITEM UNIT COSTS BY PROJECTS -- 2022 COST DATA

11:31 Wednesday, March 8, 2023 142

PROJECT NUMBER	ITEM NUMBER/ PROJECT LOCATION	ITEM DESCRIPTION/ PROJECT LOCATION	DATE LET	UNIT/ QUANTITY	ENGR. EST.	AVERAGE BID	AWARDED BID
=====	210-00011	Res Mailbox Str (Ty 1)		Each	=====	=====	=====
NHPP0502-090		SH 50 MP 134.6-136 GUNNISON C	12/22/22	4.00	350.00	637.48	533.50
STR0092-024		SH 9 North of Silverthorne	12/22/22	1.00	500.00	375.50	351.00
		WEIGHTED AVERAGE FOR THE FOURTH QUARTER		5.00	380.00	613.67	497.00
		WEIGHTED AVERAGE FOR THE YEAR		5.00	380.00	613.67	497.00
=====	210-00012	Res Mailbox Str (Ty 2)		Each	=====	=====	=====
STR0092-024		SH 9 North of Silverthorne	12/22/22	1.00	1000.00	517.50	485.00
		WEIGHTED AVERAGE FOR THE FOURTH QUARTER		1.00	1000.00	517.50	485.00
		WEIGHTED AVERAGE FOR THE YEAR		1.00	1000.00	517.50	485.00
=====	210-00013	Res Mailbox Str (Ty 3)		Each	=====	=====	=====
STR0092-024		SH 9 North of Silverthorne	12/22/22	1.00	3000.00	745.50	701.00
		WEIGHTED AVERAGE FOR THE FOURTH QUARTER		1.00	3000.00	745.50	701.00
		WEIGHTED AVERAGE FOR THE YEAR		1.00	3000.00	745.50	701.00
=====	210-00035	Res Water Meter		Each	=====	=====	=====
NHPP0063-054		US 6 FROM I70-B TO 33 RD. (MP 08/18/22		1.00	3000.00	1622.04	1400.00
		WEIGHTED AVERAGE FOR THE THIRD QUARTER		1.00	3000.00	1622.04	1400.00
		WEIGHTED AVERAGE FOR THE YEAR		1.00	3000.00	1622.04	1400.00
=====	210-00050	Res Fire Hydrant		Each	=====	=====	=====
STAM420-001		US 285 AT HWY 9C IMPROVEMENTS	12/01/22	1.00	5394.00	5579.44	5575.90
BR2854-148		INTERSECTION OF US 285 & SH 9					
STM0091-046		ADA RAMP IMPROVEMENTS - FAIRP					
		WEIGHTED AVERAGE FOR THE FOURTH QUARTER		1.00	5394.00	5579.44	5575.90
		WEIGHTED AVERAGE FOR THE YEAR		1.00	5394.00	5579.44	5575.90

PROJECT NUMBER	ITEM NUMBER/ PROJECT LOCATION	ITEM DESCRIPTION/ PROJECT LOCATION	DATE LET	UNIT/ QUANTITY	ENGR. EST.	AVERAGE BID	AWARDED BID
===== 210-00060		Res Marker		Each			
C170A-002		CRITICAL CULVERT CONST. PKG D	10/27/22	2.00	400.00	445.00	500.00
STAM420-001		US 285 AT HWY 9C IMPROVEMENTS	12/01/22	2.00	425.00	844.41	631.86
BR2854-148		INTERSECTION OF US 285 & SH 9					
STM0091-046		ADA RAMP IMPROVEMENTS - FAIRP					
		WEIGHTED AVERAGE FOR THE FOURTH QUARTER		4.00	412.50	644.70	565.93
		WEIGHTED AVERAGE FOR THE YEAR		4.00	412.50	644.70	565.93
===== 210-00065		Res Monument (Ty 3A)		Each			
CC030-081		ADA RAMP AND CURBS - FT. LUPT	04/14/22	3.00	1000.00	1035.16	500.00
NHC540-017		R2 CHAINUP STA @ KENOSHA/HOOS	05/12/22	4.00	1000.00	2061.67	685.00
		WEIGHTED AVERAGE FOR THE SECOND QUARTER		7.00	1000.00	1621.74	605.71
		WEIGHTED AVERAGE FOR THE YEAR		7.00	1000.00	1621.74	605.71
===== 210-00090		Res Delineator		Each			
NHPP0702-413		VAIL PASS AUX PHASE 1 CAP 2	04/18/22	5.00	26.75	26.75	26.75
		WEIGHTED AVERAGE FOR THE SECOND QUARTER		5.00	26.75	26.75	26.75
NHPP0343-048		US 34 (MP 169.3-171.4)	11/01/22	5.00	35.00	96.32	60.00
		WEIGHTED AVERAGE FOR THE FOURTH QUARTER		5.00	35.00	96.32	60.00
		WEIGHTED AVERAGE FOR THE YEAR		10.00	30.88	82.40	43.38
===== 210-00100		Res Trash Guard		Each			
SHE2873-193		US 287 & CO 52 INTERSECTION I	09/15/22	1.00	1500.00	1260.38	1284.00
		WEIGHTED AVERAGE FOR THE THIRD QUARTER		1.00	1500.00	1260.38	1284.00
		WEIGHTED AVERAGE FOR THE YEAR		1.00	1500.00	1260.38	1284.00

COLORADO DEPARTMENT OF TRANSPORTATION
ITEM UNIT COSTS BY PROJECTS -- 2022 COST DATA

11:31 Wednesday, March 8, 2023 144

PROJECT NUMBER	ITEM NUMBER/ PROJECT LOCATION	ITEM DESCRIPTION/ PROJECT LOCATION	DATE LET	UNIT/ QUANTITY	ENGR. EST.	AVERAGE BID	AWARDED BID
===== 210-00473 Res TV Cameras Each =====							
NHPP0702-383		I-70 EB AUX FRISCO TO SILVERT	01/13/22	1.00	1880.00	2030.47	2100.00
		WEIGHTED AVERAGE FOR THE FIRST QUARTER		1.00	1880.00	2030.47	2100.00
NHPP0702-414 FBR0702-423		VAIL PASS AUX PHASE 1 CAP 3 VAIL PASS AUX BE F-12-AT PHAS	07/08/22	1.00	3852.00	3852.00	3852.00
		WEIGHTED AVERAGE FOR THE THIRD QUARTER		1.00	3852.00	3852.00	3852.00
STAM420-001 BR2854-148 STM0091-046 2670703-487 NHPP0931-033		US 285 AT HWY 9C IMPROVEMENTS INTERSECTION OF US 285 & SH 9 ADA RAMP IMPROVEMENTS - FAIRP I-70 BRIDGES OVER WARD ROAD- SH93:US6 TO 58TH RESURFACING	12/01/22 12/01/22 12/15/22	1.00 1.00 1.00	1250.00 4000.00 2000.00	2254.60 1429.90 585.19	3420.89 1420.00 690.00
		WEIGHTED AVERAGE FOR THE FOURTH QUARTER		3.00	2416.67	1423.74	1843.63
		WEIGHTED AVERAGE FOR THE YEAR		5.00	2596.40	1711.21	2296.58
===== 210-00474 Res Traf Contr Signal Head Each =====							
FSA0853-122		WCR14.5 AND US-85, FORT LUPTO	12/15/22	2.00	1000.00	2284.27	1000.00
		WEIGHTED AVERAGE FOR THE FOURTH QUARTER		2.00	1000.00	2284.27	1000.00
		WEIGHTED AVERAGE FOR THE YEAR		2.00	1000.00	2284.27	1000.00
===== 210-00475 Res CCTV Pole Each =====							
NHPP0702-383		I-70 EB AUX FRISCO TO SILVERT	01/13/22	1.00	7600.00	5106.34	4800.00
		WEIGHTED AVERAGE FOR THE FIRST QUARTER		1.00	7600.00	5106.34	4800.00
STAM420-001		US 285 AT HWY 9C IMPROVEMENTS	12/01/22	3.00	5500.00	17421.17	26389.69

COLORADO DEPARTMENT OF TRANSPORTATION
 ITEM UNIT COSTS BY PROJECTS -- 2022 COST DATA

11:31 Wednesday, March 8, 2023 145

PROJECT NUMBER	ITEM NUMBER/ PROJECT LOCATION	ITEM DESCRIPTION/ PROJECT LOCATION	DATE LET	UNIT/ QUANTITY	ENGR. EST.	AVERAGE BID	AWARDED BID
===== 210-00475 BR2854-148 STM0091-046	210-00475	Res CCTV Pole INTERSECTION OF US 285 & SH 9 ADA RAMP IMPROVEMENTS - FAIRP		Each =====			
	WEIGHTED AVERAGE FOR THE FOURTH QUARTER			3.00	5500.00	17421.17	26389.69
	WEIGHTED AVERAGE FOR THE YEAR			4.00	6025.00	13799.16	20992.27
===== 210-00476	210-00476	Reset MVRD		Each =====			
2670703-487	I-70 BRIDGES OVER WARD ROAD-	12/01/22	1.00	1000.00	1429.90	1420.00	
	WEIGHTED AVERAGE FOR THE FOURTH QUARTER		1.00	1000.00	1429.90	1420.00	
	WEIGHTED AVERAGE FOR THE YEAR		1.00	1000.00	1429.90	1420.00	
===== 210-00477	210-00477	Reset Weather Station		Each =====			
NHPP0702-414 FBR0702-423	VAIL PASS AUX PHASE 1 CAP 3 VAIL PASS AUX BE F-12-AT PHAS	07/08/22	1.00	7704.00	7704.00	7704.00	
	WEIGHTED AVERAGE FOR THE THIRD QUARTER		1.00	7704.00	7704.00	7704.00	
STAM420-001 BR2854-148 STM0091-046	US 285 AT HWY 9C IMPROVEMENTS INTERSECTION OF US 285 & SH 9 ADA RAMP IMPROVEMENTS - FAIRP	12/01/22	1.00	6000.00	27080.16	41050.63	
	WEIGHTED AVERAGE FOR THE FOURTH QUARTER		1.00	6000.00	27080.16	41050.63	
	WEIGHTED AVERAGE FOR THE YEAR		2.00	6852.00	23204.93	24377.32	
===== 210-00479	210-00479	Res Radio Com Antenna		Each =====			
NHPP0702-383	I-70 EB AUX FRISCO TO SILVERT	01/13/22	1.00	940.00	1690.05	1800.00	
	WEIGHTED AVERAGE FOR THE FIRST QUARTER		1.00	940.00	1690.05	1800.00	
SHE2873-193	US 287 & CO 52 INTERSECTION I	09/15/22	3.00	600.00	1030.81	792.00	
	WEIGHTED AVERAGE FOR THE THIRD QUARTER		3.00	600.00	1030.81	792.00	

COLORADO DEPARTMENT OF TRANSPORTATION
ITEM UNIT COSTS BY PROJECTS -- 2022 COST DATA

11:31 Wednesday, March 8, 2023 146

PROJECT NUMBER	ITEM NUMBER/ PROJECT LOCATION	ITEM DESCRIPTION/ PROJECT LOCATION	DATE LET	UNIT/ QUANTITY	ENGR. EST.	AVERAGE BID	AWARDED BID
===== 210-00479		Res Radio Com Antenna		Each	=====		
FSAM240-200		SH21B CO SPRINGS SIGNAL REPLA	10/27/22	1.00	1200.00	2033.75	1895.00
STAM420-001		US 285 AT HWY 9C IMPROVEMENTS	12/01/22	3.00	1030.00	1537.44	2345.75
BR2854-148		INTERSECTION OF US 285 & SH 9					
STM0091-046		ADA RAMP IMPROVEMENTS - FAIRP					
	WEIGHTED AVERAGE FOR THE FOURTH QUARTER			4.00	1072.50	1661.52	2233.06
	WEIGHTED AVERAGE FOR THE YEAR			8.00	878.75	1374.08	1638.53
===== 210-00481		Reset DSRC (Roadside Unit)		Each	=====		
NHPP0702-414		VAIL PASS AUX PHASE 1 CAP 3	07/08/22	1.00	3852.00	3852.00	3852.00
FBR0702-423		VAIL PASS AUX BE F-12-AT PHAS					
	WEIGHTED AVERAGE FOR THE THIRD QUARTER			1.00	3852.00	3852.00	3852.00
	WEIGHTED AVERAGE FOR THE YEAR			1.00	3852.00	3852.00	3852.00
===== 210-00750		Res Light Standard		Each	=====		
NHPP0702-383		I-70 EB AUX FRISCO TO SILVERT	01/13/22	12.00	2200.00	7583.91	7300.00
	WEIGHTED AVERAGE FOR THE FIRST QUARTER			12.00	2200.00	7583.91	7300.00
2670703-479		I-70 BRIDGE OVER HARLAN	05/05/22	1.00	2000.00	1396.75	1640.38
CM760-047		COLFAX AND QUAIL	05/12/22	1.00	1000.00	2735.80	2534.00
	WEIGHTED AVERAGE FOR THE SECOND QUARTER			2.00	1500.00	2005.41	2087.19
IM025A-050		I25-MP103.9 - INTERSECTION DR	12/01/22	2.00	1800.00	1683.33	3200.00
	WEIGHTED AVERAGE FOR THE FOURTH QUARTER			2.00	1800.00	3166.97	2350.00
	WEIGHTED AVERAGE FOR THE YEAR			16.00	2062.50	6134.49	5620.80

COLORADO DEPARTMENT OF TRANSPORTATION
ITEM UNIT COSTS BY PROJECTS -- 2022 COST DATA

11:31 Wednesday, March 8, 2023 147

PROJECT NUMBER	ITEM NUMBER/ PROJECT LOCATION	ITEM DESCRIPTION/ PROJECT LOCATION	DATE LET	UNIT/ QUANTITY	ENGR. EST.	AVERAGE BID	AWARDED BID
===== 210-00760 Res Luminaire Each =====							
2670703-479		I-70 BRIDGE OVER HARLAN	05/05/22	1.00	400.00	359.96	421.55
		WEIGHTED AVERAGE FOR THE SECOND QUARTER		1.00	400.00	359.96	421.55
NHPP0063-054		US 6 FROM I70-B TO 33 RD. (MP 08/18/22		1.00	400.00	700.66	605.00
		WEIGHTED AVERAGE FOR THE THIRD QUARTER		1.00	400.00	700.66	605.00
STU0252-457		I-25:ALAMEDA RIVER PH 2.0	11/03/22	2.00	500.00	580.18	580.00
		WEIGHTED AVERAGE FOR THE FOURTH QUARTER		2.00	500.00	580.18	580.00
		WEIGHTED AVERAGE FOR THE YEAR		4.00	450.00	503.01	546.64
===== 210-00805 Res Overhead Sign Str Each =====							
NHPP0702-414		VAIL PASS AUX PHASE 1 CAP 3	07/08/22	1.00	4333.50	4333.50	4333.50
FBR0702-423		VAIL PASS AUX BE F-12-AT PHAS					
ER0502-092		US 50 MP 204 EB MONARCH TRUCK	08/29/22	1.00	3500.00	23331.04	17993.11
		WEIGHTED AVERAGE FOR THE THIRD QUARTER		2.00	3916.75	18581.65	11163.31
STAM420-001		US 285 AT HWY 9C IMPROVEMENTS	12/01/22	1.00	18000.00	16780.58	25412.30
BR2854-148		INTERSECTION OF US 285 & SH 9					
STM0091-046		ADA RAMP IMPROVEMENTS - FAIRP					
2670703-487		I-70 BRIDGES OVER WARD ROAD-	12/01/22	1.00	2500.00	38608.90	40800.00
		WEIGHTED AVERAGE FOR THE FOURTH QUARTER		2.00	10250.00	28907.42	33106.15
		WEIGHTED AVERAGE FOR THE YEAR		4.00	7083.38	25730.26	22134.73
===== 210-00810 Res Ground Sign Each =====							
NHPP0702-383		I-70 EB AUX FRISCO TO SILVERT	01/13/22	10.00	300.00	689.84	135.00

COLORADO DEPARTMENT OF TRANSPORTATION
 ITEM UNIT COSTS BY PROJECTS -- 2022 COST DATA

11:31 Wednesday, March 8, 2023 148

PROJECT NUMBER	ITEM NUMBER/ PROJECT LOCATION	ITEM DESCRIPTION/ PROJECT LOCATION	DATE LET	UNIT/ QUANTITY	ENGR. EST.	AVERAGE BID	AWARDED BID
=====	210-00810	Res Ground Sign		Each =====			
MTCER300-262			02/03/22	30.00	400.00	475.00	375.00
NHPP1601-083			02/03/22	63.00	400.00	455.79	500.00
STA0252-459			02/03/22	5.00	500.00	409.89	350.00
CR100-362			03/14/22	10.00	268.30	268.30	268.30
ER007A-035			03/15/22	3.00	663.00	709.45	709.45
STR092A-031			03/17/22	13.00	400.00	545.00	545.00
				-----	-----	-----	-----
		WEIGHTED AVERAGE FOR THE FIRST QUARTER		134.00	392.33	497.44	430.94
				-----	-----	-----	-----
CC030-081		ADA RAMP AND CURBS - FT. LUPT	04/14/22	38.00	400.00	425.46	750.00
NHPP0702-413		VAIL PASS AUX PHASE 1 CAP 2	04/18/22	4.00	695.50	695.50	695.50
STA0712-019		SH 71: Frieight Improvements	05/12/22	1.00	400.00	207.01	207.01
NHC540-017		R2 CHAINUP STA @ KENOSHA/HOOS	05/12/22	1.00	408.00	1046.67	640.00
NHPP072A-047		SH-72 RESURFACING: I-70 TO IN	06/09/22	2.00	450.00	604.21	604.21
				-----	-----	-----	-----
		WEIGHTED AVERAGE FOR THE SECOND QUARTER		46.00	428.04	450.32	724.73
				-----	-----	-----	-----
NHPP0702-414		VAIL PASS AUX PHASE 1 CAP 3	07/08/22	8.00	518.42	518.42	518.42
FBR0702-423		VAIL PASS AUX BE F-12-AT PHAS					
STR0711-022		SH 71 OVER THE ARKANSAS	08/04/22	2.00	400.00	735.00	450.00
NHPP0063-054		US 6 FROM I70-B TO 33 RD. (MP	08/18/22	4.00	500.00	669.54	605.00
C1211-099		SH 121 NORTH SGA SIGNALS	08/25/22	2.00	430.00	492.50	625.00
ER0502-092		US 50 MP 204 EB MONARCH TRUCK	08/29/22	2.00	400.00	348.92	274.26
2670403-065		US40 FLOYD HILL ROUNDABOUTS	09/15/22	14.00	700.00	676.96	531.00
2670703-497		I-70 GENESEE WILDLIFE KING	09/15/22	1.00	480.00	611.04	96.55
SHE2873-193		US 287 & CO 52 INTERSECTION I	09/15/22	30.00	350.00	297.55	223.63
				-----	-----	-----	-----
		WEIGHTED AVERAGE FOR THE THIRD QUARTER		63.00	466.47	399.41	373.10
				-----	-----	-----	-----
NHPP0821-114		SH 82 ASPEN/INDEPENDENCE PASS	10/13/22	10.00	500.00	633.67	701.00
STA207A-004		Resurfacing SH207A MANZANOLA	10/27/22	10.00	400.00	648.07	694.20
FSAM240-200		SH21B CO SPRINGS SIGNAL REPLA	10/27/22	8.00	300.00	507.75	355.00
TRG0253-264		I-25 AND SH 119 PARK-N-RIDE	10/27/22	10.00	90.00	556.25	580.00
STA3852-015		US 385 HOLYOKE NORTH	10/27/22	30.00	500.00	425.00	425.00
NHPP0343-048		US 34 (MP 169.3-171.4)	11/01/22	2.00	460.00	412.64	115.00
STU0252-457		I-25:ALAMEDA RIVER PH 2.0	11/03/22	3.00	425.00	455.04	460.00
C5502-097		US550 MP 117.28-126.06	11/17/22	1.00	700.00	693.19	513.00
STRC090-011		US 50B AND SH71/CR18 INTERSEC	11/17/22	6.00	350.00	467.50	550.00
STAM420-001		US 285 AT HWY 9C IMPROVEMENTS	12/01/22	3.00	394.00	597.10	410.90

PROJECT NUMBER	ITEM NUMBER/ PROJECT LOCATION	ITEM DESCRIPTION/ PROJECT LOCATION	DATE LET	UNIT/ QUANTITY	ENGR. EST.	AVERAGE BID	AWARDED BID
=====	210-00810	Res Ground Sign		Each	=====		
BR2854-148		INTERSECTION OF US 285 & SH 9					
STM0091-046		ADA RAMP IMPROVEMENTS - FAIRP					
IM025A-050		I25-MP103.9 - INTERSECTION DR	12/01/22	10.00	450.00	340.00	370.00
NHPP0021-041		SH2 RESURFACING MLK TO 52ND	12/01/22	1.00	600.00	645.12	576.62
NHPP083A-046		SH83 RESURFACING STROH RD TO	12/08/22	5.00	600.00	247.01	341.01
NHPP0931-033		SH93:US6 TO 58TH RESURFACING	12/15/22	2.00	300.00	635.87	615.00
STA0361-129		US 36: HYGIENE RD AND NELSON	12/22/22	17.00	550.00	304.16	373.38
BR012A-048		CO 12 STRUCTURE P-17-F AT MP	12/22/22	4.00	400.00	390.51	325.00
		WEIGHTED AVERAGE FOR THE FOURTH QUARTER		122.00	435.47	469.35	466.04
		WEIGHTED AVERAGE FOR THE YEAR		365.00	424.04	458.28	469.71
=====	210-00815	Res Sign Panel		Each	=====		
NHPP2873-189		US 287 (FEDERAL BLVD) - COLFA	01/06/22	1.00	240.00	99.91	37.20
NHPP1601-083			02/03/22	8.00	100.00	495.03	150.00
STA0252-459			02/03/22	2.00	271.58	254.52	225.00
STA 067A-048		Hwy 67A MP 0.00 TO MP 11.05 I	03/03/22	2.00	150.00	166.93	170.00
NHPP 0761-238		I-76 DAHLIA TO YORK	03/10/22	1.00	250.00	1064.63	200.00
C0761-239							
NHPP0703-472			03/10/22	3.00	180.00	158.31	150.00
		WEIGHTED AVERAGE FOR THE FIRST QUARTER		17.00	157.24	408.95	157.48
2670703-479		I-70 BRIDGE OVER HARLAN	05/05/22	11.00	200.00	155.47	179.36
STA0712-019		SH 71: Frieight Improvements	05/12/22	2.00	100.00	207.01	207.01
NHPP 3851-018		US 385 NORTH OF CHEYENNE WELL	05/26/22	1.00	200.00	652.50	640.00
NHPP072A-047		SH-72 RESURFACING: I-70 TO IN	06/09/22	4.00	250.00	302.11	302.11
		WEIGHTED AVERAGE FOR THE SECOND QUARTER		18.00	200.00	178.22	235.30
NHPP0702-414		VAIL PASS AUX PHASE 1 CAP 3	07/08/22	1.00	1309.68	1309.68	1309.68
FBR0702-423		VAIL PASS AUX BE F-12-AT PHAS					
C1211-099		SH 121 NORTH SGA SIGNALS	08/25/22	21.00	150.00	297.50	380.00
2670403-065		US40_FLOYD HILL ROUNDABOUTS	09/15/22	4.00	160.00	293.75	280.00
		WEIGHTED AVERAGE FOR THE THIRD QUARTER		26.00	196.14	315.09	400.37
C0831-126		SH83 EL PASO COUNTY TO BAYOU	10/13/22	9.00	185.00	425.00	350.00

PROJECT NUMBER	ITEM NUMBER/ PROJECT LOCATION	ITEM DESCRIPTION/ PROJECT LOCATION	DATE LET	UNIT/ QUANTITY	ENGR. EST.	AVERAGE BID	AWARDED BID
=====	210-00815	Res Sign Panel		Each	=====	=====	=====
FSAM240-200		SH21B CO SPRINGS SIGNAL REPLA	10/27/22	12.00	50.00	645.25	600.00
TRG0253-264		I-25 AND SH 119 PARK-N-RIDE	10/27/22	3.00	200.00	281.09	300.00
STU0252-457		I-25:ALAMEDA RIVER PH 2.0	11/03/22	3.00	175.00	366.58	350.00
SHE0242-087		US 24 SAFETY IMPRVMTS, E OF	11/03/22	2.00	150.00	452.56	477.69
MPR200-280		PUEBLO AREA	11/17/22	1.00	680.00	225.00	300.00
STA0711-021		SH71: REGION LINE NORTH	12/01/22	20.00	160.00	173.33	200.00
NHPP083A-046		SH83 RESURFACING STROH RD TO	12/08/22	3.00	250.00	189.01	341.01
NHPP0063-048		US6 / 20 ROAD INTERSECTION IM	12/15/22	2.00	350.00	357.93	480.00
FSA0853-122		WCRI4.5 AND US-85, FORT LUPTO	12/15/22	4.00	200.00	316.04	150.00
		WEIGHTED AVERAGE FOR THE FOURTH QUARTER		59.00	166.44	362.07	343.25
		WEIGHTED AVERAGE FOR THE YEAR		120.00	176.61	326.07	313.61
=====	210-00816	Res Sign Panel (Spec)		Each	=====	=====	=====
2670703-487		I-70 BRIDGES OVER WARD ROAD-	12/01/22	1.00	6000.00	6367.50	8190.00
		WEIGHTED AVERAGE FOR THE FOURTH QUARTER		1.00	6000.00	6367.50	8190.00
		WEIGHTED AVERAGE FOR THE YEAR		1.00	6000.00	6367.50	8190.00
=====	210-00820	Res Var Mesg Sign		Each	=====	=====	=====
NHPP0702-414		VAIL PASS AUX PHASE 1 CAP 3	07/08/22	1.00	35310.00	35310.00	35310.00
FBR0702-423		VAIL PASS AUX BE F-12-AT PHAS					
		WEIGHTED AVERAGE FOR THE THIRD QUARTER		1.00	35310.00	35310.00	35310.00
STAM420-001		US 285 AT HWY 9C IMPROVEMENTS	12/01/22	1.00	16000.00	27080.16	41050.63
BR2854-148		INTERSECTION OF US 285 & SH 9					
STM0091-046		ADA RAMP IMPROVEMENTS - FAIRP					
		WEIGHTED AVERAGE FOR THE FOURTH QUARTER		1.00	16000.00	27080.16	41050.63
		WEIGHTED AVERAGE FOR THE YEAR		2.00	25655.00	28726.13	38180.32
=====	210-00825	Res Flashing Beacon		Each	=====	=====	=====
C0831-126		SH83 EL PASO COUNTY TO BAYOU	10/13/22	2.00	5000.00	1350.00	1200.00

COLORADO DEPARTMENT OF TRANSPORTATION
ITEM UNIT COSTS BY PROJECTS -- 2022 COST DATA

11:31 Wednesday, March 8, 2023 151

PROJECT NUMBER	ITEM NUMBER/ PROJECT LOCATION	ITEM DESCRIPTION/ PROJECT LOCATION	DATE LET	UNIT/ QUANTITY	ENGR. EST.	AVERAGE BID	AWARDED BID
===== 210-00825 Res Flashing Beacon Each =====							
STAM420-001		US 285 AT HWY 9C IMPROVEMENTS	12/01/22	1.00	5000.00	4404.17	2517.69
BR2854-148		INTERSECTION OF US 285 & SH 9					
STM0091-046		ADA RAMP IMPROVEMENTS - FAIRP					
	WEIGHTED AVERAGE FOR THE FOURTH QUARTER			3.00	5000.00	2877.09	1639.23
	WEIGHTED AVERAGE FOR THE YEAR			3.00	5000.00	2877.09	1639.23
===== 210-00827 Res Pull Box Each =====							
NHPP2873-189		US 287 (FEDERAL BLVD) - COLFA	01/06/22	23.00	440.00	553.31	522.35
NHPP0063-063			02/24/22	5.00	700.00	2105.00	2500.00
CR100-362			03/14/22	17.00	1032.55	1032.55	1032.55
MP0503-098			03/24/22	1.00	2000.00	1245.00	780.00
	WEIGHTED AVERAGE FOR THE FIRST QUARTER			46.00	721.16	760.31	931.47
===== 210-00827 Res Pull Box Each =====							
2670703-479		I-70 BRIDGE OVER HARLAN	05/05/22	1.00	1500.00	824.63	970.09
ITS 0741-024		VMS SIGN INSTALLATIONS AND VS	06/02/22	1.00	900.00	1296.50	800.00
	WEIGHTED AVERAGE FOR THE SECOND QUARTER			2.00	1200.00	942.60	885.05
===== 210-00827 Res Pull Box Each =====							
TRG0253-264		I-25 AND SH 119 PARK-N-RIDE	10/27/22	1.00	1000.00	1796.24	1500.00
NHPP0021-041		SH2 RESURFACING MLK TO 52ND	12/01/22	5.00	850.00	2337.12	2002.27
	WEIGHTED AVERAGE FOR THE FOURTH QUARTER			6.00	875.00	2182.58	1918.56
	WEIGHTED AVERAGE FOR THE YEAR			54.00	755.99	1023.25	1039.42
===== 210-00830 Res Traf Sig Face Each =====							
NHPP0931-033		SH93:US6 TO 58TH RESURFACING	12/15/22	7.00	1000.00	554.35	392.75
	WEIGHTED AVERAGE FOR THE FOURTH QUARTER			7.00	1000.00	554.35	392.75
	WEIGHTED AVERAGE FOR THE YEAR			7.00	1000.00	554.35	392.75
===== 210-00831 Res Traf Sig Head Each =====							
STU0252-457		I-25:ALAMEDA RIVER PH 2.0	11/03/22	6.00	1000.00	1270.71	1270.00
	WEIGHTED AVERAGE FOR THE FOURTH QUARTER			6.00	1000.00	1270.71	1270.00
	WEIGHTED AVERAGE FOR THE YEAR			6.00	1000.00	1270.71	1270.00

COLORADO DEPARTMENT OF TRANSPORTATION
ITEM UNIT COSTS BY PROJECTS -- 2022 COST DATA

11:31 Wednesday, March 8, 2023 152

PROJECT NUMBER	ITEM NUMBER/ PROJECT LOCATION	ITEM DESCRIPTION/ PROJECT LOCATION	DATE LET	UNIT/ QUANTITY	ENGR. EST.	AVERAGE BID	AWARDED BID
=====	210-00845	Res Traf Sig Cntrlr		Each	=====	=====	=====
NHPP0931-033		SH93:US6 TO 58TH RESURFACING	12/15/22	1.00	3000.00	374.26	179.50
	WEIGHTED	AVERAGE FOR THE FOURTH QUARTER		1.00	3000.00	374.26	179.50
		WEIGHTED AVERAGE FOR THE YEAR		1.00	3000.00	374.26	179.50
=====	210-00846	Port Non-Intrus Traf Sens (Reset)		Each	=====	=====	=====
CM760-047		COLFAX AND QUAIL	05/12/22	4.00	286.00	1660.00	1182.00
	WEIGHTED	AVERAGE FOR THE SECOND QUARTER		4.00	286.00	1660.00	1182.00
		WEIGHTED AVERAGE FOR THE YEAR		4.00	286.00	1660.00	1182.00
=====	210-00848	Res Traf Sig Control+Cab		Each	=====	=====	=====
NHPP072A-047		SH-72 RESURFACING: I-70 TO IN	06/09/22	1.00	7000.00	5927.36	5927.36
	WEIGHTED	AVERAGE FOR THE SECOND QUARTER		1.00	7000.00	5927.36	5927.36
		WEIGHTED AVERAGE FOR THE YEAR		1.00	7000.00	5927.36	5927.36
=====	210-00855	Res Traf Sig Control Cab		Each	=====	=====	=====
NHPP0702-383		I-70 EB AUX FRISCO TO SILVERT	01/13/22	1.00	5173.00	9163.09	8800.00
	WEIGHTED	AVERAGE FOR THE FIRST QUARTER		1.00	5173.00	9163.09	8800.00
FSAM240-200		SH21B CO SPRINGS SIGNAL REPLA	10/27/22	2.00	300.00	5718.75	5995.00
	WEIGHTED	AVERAGE FOR THE FOURTH QUARTER		2.00	300.00	5718.75	5995.00
		WEIGHTED AVERAGE FOR THE YEAR		3.00	1924.33	7043.50	6930.00
=====	210-00858	Res Pedestal Pole		Each	=====	=====	=====
CC030-081		ADA RAMP AND CURBS - FT. LUPT	04/14/22	1.00	1300.00	760.98	750.00
	WEIGHTED	AVERAGE FOR THE SECOND QUARTER		1.00	1300.00	760.98	750.00

COLORADO DEPARTMENT OF TRANSPORTATION
 ITEM UNIT COSTS BY PROJECTS -- 2022 COST DATA

11:31 Wednesday, March 8, 2023 153

PROJECT NUMBER	ITEM NUMBER/ PROJECT LOCATION	ITEM DESCRIPTION/ PROJECT LOCATION	DATE LET	UNIT/ QUANTITY	ENGR. EST.	AVERAGE BID	AWARDED BID
=====	210-00858	Res Pedestal Pole		Each	=====	=====	=====
TRG0253-264		I-25 AND SH 119 PARK-N-RIDE	10/27/22	1.00	750.00	858.02	810.00
NHPP0021-041		SH2 RESURFACING MLK TO 52ND	12/01/22	1.00	3000.00	1937.10	2285.85
		WEIGHTED AVERAGE FOR THE FOURTH QUARTER		2.00	1875.00	1217.71	1547.93
		WEIGHTED AVERAGE FOR THE YEAR		3.00	1683.33	1126.36	1281.95
=====	210-00859	Mod Ped Push Button		Each	=====	=====	=====
CR100-362			03/14/22	7.00	882.75	882.75	882.75
		WEIGHTED AVERAGE FOR THE FIRST QUARTER		7.00	882.75	882.75	882.75
NHPP072A-047		SH-72 RESURFACING: I-70 TO IN	06/09/22	11.00	500.00	515.42	515.42
		WEIGHTED AVERAGE FOR THE SECOND QUARTER		11.00	500.00	515.42	515.42
NHPP0931-033		SH93:US6 TO 58TH RESURFACING	12/15/22	1.00	600.00	408.71	435.00
		WEIGHTED AVERAGE FOR THE FOURTH QUARTER		1.00	600.00	408.71	435.00
		WEIGHTED AVERAGE FOR THE YEAR		19.00	646.28	612.90	646.52
=====	210-00860	Res Ped Push Button		Each	=====	=====	=====
NHPP2873-189		US 287 (FEDERAL BLVD) - COLFA	01/06/22	1.00	800.00	102.41	95.86
NHPP0063-063			02/24/22	1.00	1000.00	1527.00	2500.00
CR100-362			03/14/22	25.00	449.40	449.40	449.40
		WEIGHTED AVERAGE FOR THE FIRST QUARTER		27.00	482.78	474.15	512.25
CC030-081		ADA RAMP AND CURBS - FT. LUPT	04/14/22	17.00	1200.00	472.16	550.00
		WEIGHTED AVERAGE FOR THE SECOND QUARTER		17.00	1200.00	472.16	550.00
		WEIGHTED AVERAGE FOR THE YEAR		44.00	759.89	472.91	526.84

COLORADO DEPARTMENT OF TRANSPORTATION
ITEM UNIT COSTS BY PROJECTS -- 2022 COST DATA

11:31 Wednesday, March 8, 2023 154

PROJECT NUMBER	ITEM NUMBER/ PROJECT LOCATION	ITEM DESCRIPTION/ PROJECT LOCATION	DATE LET	UNIT/ QUANTITY	ENGR. EST.	AVERAGE BID	AWARDED BID
===== 210-00861		Reset Wiring		LUMP SUM	=====	=====	=====
TRG0253-264		I-25 AND SH 119 PARK-N-RIDE	10/27/22	1.00	4000.00	1742.69	1400.00
		WEIGHTED AVERAGE FOR THE FOURTH QUARTER		1.00	4000.00	1742.69	1400.00
		WEIGHTED AVERAGE FOR THE YEAR		1.00	4000.00	1742.69	1400.00
===== 210-00865		Res Ped Sig Head		Each	=====	=====	=====
CR100-362			03/14/22	2.00	690.15	690.15	690.15
		WEIGHTED AVERAGE FOR THE FIRST QUARTER		2.00	690.15	690.15	690.15
CC030-081		ADA RAMP AND CURBS - FT. LUPT	04/14/22	1.00	300.00	547.16	775.00
		WEIGHTED AVERAGE FOR THE SECOND QUARTER		1.00	300.00	547.16	775.00
		WEIGHTED AVERAGE FOR THE YEAR		3.00	560.10	604.35	718.43
===== 210-00867		Res Fire Preempt Unit		Each	=====	=====	=====
CM760-047		COLFAX AND QUAIL	05/12/22	2.00	873.00	1312.40	677.00
NHPP072A-047		SH-72 RESURFACING: I-70 TO IN	06/09/22	2.00	1000.00	1192.66	1192.66
		WEIGHTED AVERAGE FOR THE SECOND QUARTER		4.00	936.50	1292.44	934.83
C1211-099		SH 121 NORTH SGA SIGNALS	08/25/22	11.00	3000.00	1425.00	1200.00
		WEIGHTED AVERAGE FOR THE THIRD QUARTER		11.00	3000.00	1425.00	1200.00
STU0252-457		I-25:ALAMEDA RIVER PH 2.0	11/03/22	2.00	2500.00	1270.71	1270.00
		WEIGHTED AVERAGE FOR THE FOURTH QUARTER		2.00	2500.00	1270.71	1270.00
		WEIGHTED AVERAGE FOR THE YEAR		17.00	2455.65	1362.09	1145.84

COLORADO DEPARTMENT OF TRANSPORTATION
 ITEM UNIT COSTS BY PROJECTS -- 2022 COST DATA

11:31 Wednesday, March 8, 2023 155

PROJECT NUMBER	ITEM NUMBER/ PROJECT LOCATION	ITEM DESCRIPTION/ PROJECT LOCATION	DATE LET	UNIT/ QUANTITY	ENGR. EST.	AVERAGE BID	AWARDED BID
===== 210-00882 Res Detector Each =====							
NHPP072A-047		SH-72 RESURFACING: I-70 TO IN	06/09/22	2.00	1000.00	1186.67	1186.67
		WEIGHTED AVERAGE FOR THE SECOND QUARTER		2.00	1000.00	1186.67	1186.67
STAM420-001 BR2854-148 STM0091-046 NHPP0931-033		US 285 AT HWY 9C IMPROVEMENTS INTERSECTION OF US 285 & SH 9 ADA RAMP IMPROVEMENTS - FAIRP SH93:US6 TO 58TH RESURFACING	12/01/22 12/15/22	1.00 2.00	2000.00 1000.00	2587.40 1043.98	3909.59 1320.00
		WEIGHTED AVERAGE FOR THE FOURTH QUARTER		3.00	1333.33	1558.45	2183.20
		WEIGHTED AVERAGE FOR THE YEAR		5.00	1200.00	1505.34	1784.59
===== 210-01000 Res Fence Lin Foot =====							
STR092A-031			03/17/22	31.00	25.00	115.00	115.00
		WEIGHTED AVERAGE FOR THE FIRST QUARTER		31.00	25.00	115.00	115.00
FSA052A-046		SH52 WCR 37 INTERSECTION IMPR	06/09/22	3,200.00	10.00	8.62	5.75
		WEIGHTED AVERAGE FOR THE SECOND QUARTER		3,200.00	10.00	8.62	5.75
NHPP0063-054 ER0502-092 NHPP0701-231		US 6 FROM I70-B TO 33 RD. (MP US 50 MP 204 EB MONARCH TRUCK I-70 SALT WASH BRIDGES SCOUR	08/18/22 08/29/22 09/29/22	22.00 100.00 600.00	100.00 100.00 12.00	32.75 77.68 44.11	56.00 93.05 45.00
		WEIGHTED AVERAGE FOR THE THIRD QUARTER		722.00	26.87	50.31	51.99
C5502-097 STAM420-001 BR2854-148		US550 MP 117.28-126.06 US 285 AT HWY 9C IMPROVEMENTS INTERSECTION OF US 285 & SH 9	11/17/22 12/01/22	8,060.00 161.00	6.00 25.00	15.13 40.77	17.90 50.63

COLORADO DEPARTMENT OF TRANSPORTATION
 ITEM UNIT COSTS BY PROJECTS -- 2022 COST DATA

11:31 Wednesday, March 8, 2023 156

PROJECT NUMBER	ITEM NUMBER/ PROJECT LOCATION	ITEM DESCRIPTION/ PROJECT LOCATION	DATE LET	UNIT/ QUANTITY	ENGR. EST.	AVERAGE BID	AWARDED BID
=====	210-01000	Res Fence		Lin Foot	=====		
STM0091-046		ADA RAMP IMPROVEMENTS - FAIRP					
	WEIGHTED AVERAGE FOR THE FOURTH QUARTER			8,221.00	6.37	15.80	18.54
	WEIGHTED AVERAGE FOR THE YEAR			12,174.00	8.59	14.42	17.41
=====	210-01011	Res Gate		Each	=====		
C5502-097		US550 MP 117.28-126.06	11/17/22	4.00	1000.00	492.91	448.00
	WEIGHTED AVERAGE FOR THE FOURTH QUARTER			4.00	1000.00	492.91	448.00
	WEIGHTED AVERAGE FOR THE YEAR			4.00	1000.00	492.91	448.00
=====	210-01050	Res C L Fence		Lin Foot	=====		
NHM765-007			03/31/22	101.00	30.00	52.14	45.60
	WEIGHTED AVERAGE FOR THE FIRST QUARTER			101.00	30.00	52.14	45.60
NHPPR100-266		R1 ESSENTIAL REPAIRS	09/01/22	50.00	50.00	55.87	79.61
	WEIGHTED AVERAGE FOR THE THIRD QUARTER			50.00	50.00	55.87	79.61
STAM420-001 BR2854-148 STM0091-046		US 285 AT HWY 9C IMPROVEMENTS INTERSECTION OF US 285 & SH 9 ADA RAMP IMPROVEMENTS - FAIRP	12/01/22	156.00	22.20	55.91	69.73
	WEIGHTED AVERAGE FOR THE FOURTH QUARTER			156.00	22.20	55.91	69.73
	WEIGHTED AVERAGE FOR THE YEAR			307.00	29.29	54.84	63.40
=====	210-01130	Res Gdrail Ty 3		Lin Foot	=====		
STA385A-016		SH 385 MP 97.76	12/22/22	100.00	30.00	29.06	27.22
	WEIGHTED AVERAGE FOR THE FOURTH QUARTER			100.00	30.00	29.06	27.22
	WEIGHTED AVERAGE FOR THE YEAR			100.00	30.00	29.06	27.22

COLORADO DEPARTMENT OF TRANSPORTATION
ITEM UNIT COSTS BY PROJECTS -- 2022 COST DATA

11:31 Wednesday, March 8, 2023 157

PROJECT NUMBER	ITEM NUMBER/ PROJECT LOCATION	ITEM DESCRIPTION/ PROJECT LOCATION	DATE LET	UNIT/ QUANTITY	ENGR. EST.	AVERAGE BID	AWARDED BID
=====	210-01170	Res Gdrail Ty 7		Lin Foot	=====		
FSA0702-409		I-70 VAIL WILDLIFE FENCE PHAS	05/26/22	100.00	550.00	350.00	350.00
	WEIGHTED AVERAGE FOR THE SECOND QUARTER			100.00	550.00	350.00	350.00
	WEIGHTED AVERAGE FOR THE YEAR			100.00	550.00	350.00	350.00
=====	210-01180	Reset Guardrail (Special)		Lin Foot	=====		
STR R500-171		Various locations on SH 141 a	03/17/22	120.00	125.00	80.18	142.00
	WEIGHTED AVERAGE FOR THE FIRST QUARTER			120.00	125.00	80.18	142.00
NH0504-911			04/07/22	212.00	100.00	35.15	35.30
	WEIGHTED AVERAGE FOR THE SECOND QUARTER			212.00	100.00	35.15	35.30
	WEIGHTED AVERAGE FOR THE YEAR			332.00	109.04	55.83	73.87
=====	210-01190	Reset High-Tension Cable Barrier		Lin Foot	=====		
TRG0253-264		I-25 AND SH 119 PARK-N-RIDE	10/27/22	2,231.00	20.00	39.48	35.00
	WEIGHTED AVERAGE FOR THE FOURTH QUARTER			2,231.00	20.00	39.48	35.00
	WEIGHTED AVERAGE FOR THE YEAR			2,231.00	20.00	39.48	35.00
=====	210-01200	Res End Anchorage		Each	=====		
NHPP 0761-238 C0761-239		I-76 DAHLIA TO YORK	03/10/22	2.00	2000.00	1715.78	1650.00
	WEIGHTED AVERAGE FOR THE FIRST QUARTER			2.00	2000.00	1715.78	1650.00
TRG0253-264		I-25 AND SH 119 PARK-N-RIDE	10/27/22	2.00	1700.00	6123.81	6500.00
	WEIGHTED AVERAGE FOR THE FOURTH QUARTER			2.00	1700.00	6123.81	6500.00
	WEIGHTED AVERAGE FOR THE YEAR			4.00	1850.00	3919.80	4075.00

COLORADO DEPARTMENT OF TRANSPORTATION
ITEM UNIT COSTS BY PROJECTS -- 2022 COST DATA

11:31 Wednesday, March 8, 2023 158

PROJECT NUMBER	ITEM NUMBER/ PROJECT LOCATION	ITEM DESCRIPTION/ PROJECT LOCATION	DATE LET	UNIT/ QUANTITY	ENGR. EST.	AVERAGE BID	AWARDED BID
=====	210-01710	Res Valve		Each	=====	=====	=====
STAM420-001 BR2854-148 STM0091-046		US 285 AT HWY 9C IMPROVEMENTS INTERSECTION OF US 285 & SH 9 ADA RAMP IMPROVEMENTS - FAIRP	12/01/22	1.00	380.12	2489.60	2787.96
		WEIGHTED AVERAGE FOR THE FOURTH QUARTER		1.00	380.12	2489.60	2787.96
		WEIGHTED AVERAGE FOR THE YEAR		1.00	380.12	2489.60	2787.96
=====	210-02804	Grinding: Sidwlk and/or Curb Ramp Repair		Lin Foot	=====	=====	=====
CR100-362			03/14/22	200.00	65.54	65.54	65.54
		WEIGHTED AVERAGE FOR THE FIRST QUARTER		200.00	65.54	65.54	65.54
		WEIGHTED AVERAGE FOR THE YEAR		200.00	65.54	65.54	65.54
=====	210-02900	Relay Riprap		Cubic Yard	=====	=====	=====
NHPP 0761-238 C0761-239 CR100-362		I-76 DAHLIA TO YORK	03/10/22	120.00	48.00	68.65	35.00
			03/14/22	10.00	406.65	406.65	406.65
		WEIGHTED AVERAGE FOR THE FIRST QUARTER		130.00	75.59	72.14	63.59
NHPP0701-231		I-70 SALT WASH BRIDGES SCOUR	09/29/22	156.00	100.00	73.71	68.00
		WEIGHTED AVERAGE FOR THE THIRD QUARTER		156.00	100.00	73.71	68.00
		WEIGHTED AVERAGE FOR THE YEAR		286.00	88.90	72.52	65.99
=====	210-03100	Replace Conc Pvmt		Sq Yard	=====	=====	=====
MTCE2873-204		MTCE FY22 SH287 CONC PANEL RE	05/05/22	2,071.00	180.00	229.29	161.58
		WEIGHTED AVERAGE FOR THE SECOND QUARTER		2,071.00	180.00	229.29	161.58
MTCE0253-281		MTCE FY23 I-25 CONC PANEL REP	10/06/22	4,574.00	200.00	259.69	243.00

COLORADO DEPARTMENT OF TRANSPORTATION
ITEM UNIT COSTS BY PROJECTS -- 2022 COST DATA

11:31 Wednesday, March 8, 2023 159

PROJECT NUMBER	ITEM NUMBER/ PROJECT LOCATION	ITEM DESCRIPTION/ PROJECT LOCATION	DATE LET	UNIT/ QUANTITY	ENGR. EST.	AVERAGE BID	AWARDED BID
===== 210-03100		Replace Conc Pvmt		Sq Yard			
NHPP0701-252		I-70 RIFLE TO SILT SLAB REPLA	12/01/22	13,365.00	300.00	237.17	206.33
	WEIGHTED AVERAGE FOR THE FOURTH QUARTER			17,939.00	274.50	246.32	215.68
	WEIGHTED AVERAGE FOR THE YEAR			20,010.00	264.72	244.88	210.08
===== 210-04000		Adj Structure		Each			
NHM765-007			03/31/22	6.00	2000.00	5062.58	2661.47
	WEIGHTED AVERAGE FOR THE FIRST QUARTER			6.00	2000.00	5062.58	2661.47
	WEIGHTED AVERAGE FOR THE YEAR			6.00	2000.00	5062.58	2661.47
===== 210-04010		Adj Manhole		Each			
NHPP2873-189		US 287 (FEDERAL BLVD) - COLFA	01/06/22	130.00	900.00	906.76	889.27
NHPP0702-383		I-70 EB AUX FRISCO TO SILVERT	01/13/22	1.00	2000.00	1983.57	2500.00
STR0141-031			02/17/22	1.00	1500.00	3366.67	3100.00
NHPP0063-063			02/24/22	102.00	800.00	1725.00	1300.00
CR100-362			03/14/22	6.00	1097.62	1097.62	1097.62
STR092A-031			03/17/22	1.00	1100.00	1300.00	1300.00
	WEIGHTED AVERAGE FOR THE FIRST QUARTER			241.00	870.48	1151.98	1085.85
NH0504-911			04/07/22	4.00	1615.53	885.00	1220.00
CC030-081		ADA RAMP AND CURBS - FT. LUPT	04/14/22	1.00	1200.00	604.43	600.00
2670703-479		I-70 BRIDGE OVER HARLAN	05/05/22	9.00	1200.00	1234.56	1811.38
FSA3921-019		SH 392 AND WCR 55 ISLANDS	06/02/22	1.00	900.00	586.67	660.00
NHPP072A-047		SH-72 RESURFACING: I-70 TO IN	06/09/22	68.00	1200.00	1009.04	1009.04
	WEIGHTED AVERAGE FOR THE SECOND QUARTER			83.00	1216.41	1073.04	1097.07
NHPP0702-414		VAIL PASS AUX PHASE 1 CAP 3	07/08/22	13.00	2728.50	2728.50	2728.50
FBR0702-423		VAIL PASS AUX BE F-12-AT PHAS					
NHPP0063-054		US 6 FROM I70-B TO 33 RD. (MP	08/18/22	4.00	1100.00	1760.89	1800.00
C1211-099		SH 121 NORTH SGA SIGNALS	08/25/22	1.00	1500.00	1750.00	2500.00
	WEIGHTED AVERAGE FOR THE THIRD QUARTER			18.00	2298.36	2306.85	2509.47

PROJECT NUMBER	ITEM NUMBER/ PROJECT LOCATION	ITEM DESCRIPTION/ PROJECT LOCATION	DATE LET	UNIT/ QUANTITY	ENGR. EST.	AVERAGE BID	AWARDED BID
===== 210-04010		Adj Manhole		Each	=====		
TRG0253-264		I-25 AND SH 119 PARK-N-RIDE	10/27/22	1.00	2000.00	1677.21	1050.00
STU0252-457		I-25:ALAMEDA RIVER PH 2.0	11/03/22	10.00	1500.00	2768.36	1360.00
C5502-097		US550 MP 117.28-126.06	11/17/22	1.00	2000.00	4690.43	2610.00
STRC090-011		US 50B AND SH71/CR18 INTERSEC	11/17/22	1.00	1200.00	2625.00	2750.00
STAM420-001		US 285 AT HWY 9C IMPROVEMENTS	12/01/22	5.00	1300.00	1834.53	1684.92
BR2854-148		INTERSECTION OF US 285 & SH 9					
STM0091-046		ADA RAMP IMPROVEMENTS - FAIRP					
2670703-487		I-70 BRIDGES OVER WARD ROAD-	12/01/22	6.00	1000.00	1143.80	1030.00
IM025A-050		I25-MP103.9 - INTERSECTION DR	12/01/22	2.00	1200.00	2600.00	1200.00
NHPP0021-041		SH2 RESURFACING MLK TO 52ND	12/01/22	14.00	1000.00	1175.48	994.49
NHPP083A-046		SH83 RESURFACING STROH RD TO	12/08/22	8.00	975.00	1269.95	939.89
NHPP0931-033		SH93:US6 TO 58TH RESURFACING	12/15/22	4.00	1000.00	1424.87	2560.00
		WEIGHTED AVERAGE FOR THE FOURTH QUARTER		52.00	1171.15	1664.91	1321.09
		WEIGHTED AVERAGE FOR THE YEAR		394.00	1048.27	1254.97	1184.30
===== 210-04011		Adj Manhole (Spec)		Each	=====		
2670703-487		I-70 BRIDGES OVER WARD ROAD-	12/01/22	2.00	3500.00	2998.90	2800.00
		WEIGHTED AVERAGE FOR THE FOURTH QUARTER		2.00	3500.00	2998.90	2800.00
		WEIGHTED AVERAGE FOR THE YEAR		2.00	3500.00	2998.90	2800.00
===== 210-04015		Modify Manhole		Each	=====		
NHPP0063-063			02/24/22	1.00	3500.00	8650.00	15000.00
		WEIGHTED AVERAGE FOR THE FIRST QUARTER		1.00	3500.00	8650.00	15000.00
NHPP0702-413		VAIL PASS AUX PHASE 1 CAP 2	04/18/22	1.00	7019.67	7019.67	7019.67
2670703-479		I-70 BRIDGE OVER HARLAN	05/05/22	5.00	4500.00	4136.88	2520.07
		WEIGHTED AVERAGE FOR THE SECOND QUARTER		6.00	4919.95	4229.87	3270.00
NHPP0063-054		US 6 FROM I70-B TO 33 RD. (MP	08/18/22	3.00	2500.00	1071.56	925.00
		WEIGHTED AVERAGE FOR THE THIRD QUARTER		3.00	2500.00	1071.56	925.00

COLORADO DEPARTMENT OF TRANSPORTATION
ITEM UNIT COSTS BY PROJECTS -- 2022 COST DATA

11:31 Wednesday, March 8, 2023 161

PROJECT NUMBER	ITEM NUMBER/ PROJECT LOCATION	ITEM DESCRIPTION/ PROJECT LOCATION	DATE LET	UNIT/ QUANTITY	ENGR. EST.	AVERAGE BID	AWARDED BID
===== 210-04015 Modify Manhole Each =====							
TRG0253-264		I-25 AND SH 119 PARK-N-RIDE	10/27/22	1.00	3700.00	4425.59	4500.00
STU0252-457		I-25:ALAMEDA RIVER PH 2.0	11/03/22	3.00	3500.00	7896.11	5600.00
IM025A-050		I25-MP103.9 - INTERSECTION DR	12/01/22	1.00	3500.00	5366.67	3100.00
		WEIGHTED AVERAGE FOR THE FOURTH QUARTER		5.00	3540.00	6128.48	4880.00
		WEIGHTED AVERAGE FOR THE YEAR		15.00	3881.31	4702.12	4119.67
===== 210-04020 Modify Inlet Each =====							
NHPP 0761-238 C0761-239		I-76 DAHLIA TO YORK	03/10/22	1.00	3500.00	3010.40	2500.00
		WEIGHTED AVERAGE FOR THE FIRST QUARTER		1.00	3500.00	3010.40	2500.00
2670703-479		I-70 BRIDGE OVER HARLAN	05/05/22	1.00	4000.00	3651.55	4880.26
		WEIGHTED AVERAGE FOR THE SECOND QUARTER		1.00	4000.00	3651.55	4880.26
NHPP0702-414 FBR0702-423 NHPP0063-054		VAIL PASS AUX PHASE 1 CAP 3	07/08/22	7.00	8195.41	8195.41	8195.41
		VAIL PASS AUX BE F-12-AT PHAS					
		US 6 FROM I70-B TO 33 RD. (MP	08/18/22	1.00	3000.00	2308.95	1995.00
		WEIGHTED AVERAGE FOR THE THIRD QUARTER		8.00	7545.98	6887.31	7420.36
IM025A-050 NHPP083A-046		I25-MP103.9 - INTERSECTION DR	12/01/22	2.00	5000.00	7633.33	4900.00
		SH83 RESURFACING STROH RD TO	12/08/22	1.00	5000.00	10834.22	9368.43
		WEIGHTED AVERAGE FOR THE FOURTH QUARTER		3.00	5000.00	8433.55	6389.48
		WEIGHTED AVERAGE FOR THE YEAR		13.00	6374.45	5659.57	6608.58
===== 210-04050 Adj Valve Box Each =====							
NHPP2873-189		US 287 (FEDERAL BLVD) - COLFA	01/06/22	76.00	460.00	507.45	723.02

COLORADO DEPARTMENT OF TRANSPORTATION
ITEM UNIT COSTS BY PROJECTS -- 2022 COST DATA

11:31 Wednesday, March 8, 2023 162

PROJECT NUMBER	ITEM NUMBER/ PROJECT LOCATION	ITEM DESCRIPTION/ PROJECT LOCATION	DATE LET	UNIT/ QUANTITY	ENGR. EST.	AVERAGE BID	AWARDED BID
===== 210-04050 Adj Valve Box Each =====							
STR0141-031			02/17/22	4.00	500.00	1933.33	1300.00
NHPP0063-063			02/24/22	97.00	500.00	1012.50	425.00
CR100-362			03/14/22	5.00	970.00	970.00	970.00
STR092A-031			03/17/22	18.00	500.00	900.00	900.00
NHM765-007			03/31/22	50.00	300.00	709.10	205.68
WEIGHTED AVERAGE FOR THE FIRST QUARTER				250.00	457.24	733.97	530.83
NH0504-911			04/07/22	2.00	1000.00	222.50	45.00
CC030-081		ADA RAMP AND CURBS - FT. LUPT	04/14/22	6.00	500.00	527.21	750.00
2670703-479		I-70 BRIDGE OVER HARLAN	05/05/22	14.00	620.00	767.09	1172.70
NHPP072A-047		SH-72 RESURFACING: I-70 TO IN	06/09/22	110.00	500.00	800.19	800.19
WEIGHTED AVERAGE FOR THE SECOND QUARTER				132.00	520.30	753.87	825.98
NHPP0063-054		US 6 FROM I70-B TO 33 RD. (MP	08/18/22	2.00	700.00	680.89	1225.00
WEIGHTED AVERAGE FOR THE THIRD QUARTER				2.00	700.00	680.89	1225.00
STU0252-457		I-25:ALAMEDA RIVER PH 2.0	11/03/22	6.00	600.00	1016.30	850.00
C5502-097		US550 MP 117.28-126.06	11/17/22	13.00	700.00	372.57	228.00
STAM420-001		US 285 AT HWY 9C IMPROVEMENTS	12/01/22	3.00	700.00	1214.75	2787.95
BR2854-148		INTERSECTION OF US 285 & SH 9					
STM0091-046		ADA RAMP IMPROVEMENTS - FAIRP					
2670703-487		I-70 BRIDGES OVER WARD ROAD-	12/01/22	14.00	1300.00	653.40	600.00
NHPP0021-041		SH2 RESURFACING MLK TO 52ND	12/01/22	64.00	750.00	450.62	688.72
NHPP083A-046		SH83 RESURFACING STROH RD TO	12/08/22	8.00	1000.00	879.31	852.62
NHPP0931-033		SH93:US6 TO 58TH RESURFACING	12/15/22	8.00	500.00	684.25	1225.00
WEIGHTED AVERAGE FOR THE FOURTH QUARTER				116.00	801.72	551.83	737.30
WEIGHTED AVERAGE FOR THE YEAR				500.00	554.78	677.06	659.43
===== 210-04060 Adj Water Meter Each =====							
STR092A-031			03/17/22	1.00	2000.00	890.00	890.00
WEIGHTED AVERAGE FOR THE FIRST QUARTER				1.00	2000.00	890.00	890.00

COLORADO DEPARTMENT OF TRANSPORTATION
 ITEM UNIT COSTS BY PROJECTS -- 2022 COST DATA

11:31 Wednesday, March 8, 2023 163

PROJECT NUMBER	ITEM NUMBER/ PROJECT LOCATION	ITEM DESCRIPTION/ PROJECT LOCATION	DATE LET	UNIT/ QUANTITY	ENGR. EST.	AVERAGE BID	AWARDED BID
=====	210-04060	Adj Water Meter		Each	=====		
NHPP0063-054		US 6 FROM I70-B TO 33 RD. (MP 08/18/22		1.00	700.00	522.69	450.00
		WEIGHTED AVERAGE FOR THE THIRD QUARTER		1.00	700.00	522.69	450.00
STU0252-457		I-25:ALAMEDA RIVER PH 2.0	11/03/22	1.00	1000.00	1928.03	850.00
C5502-097		US550 MP 117.28-126.06	11/17/22	9.00	700.00	646.24	25.40
		WEIGHTED AVERAGE FOR THE FOURTH QUARTER		10.00	730.00	774.42	107.86
		WEIGHTED AVERAGE FOR THE YEAR		12.00	833.33	762.66	201.55
=====	210-04200	Adj Gdrail		Lin Foot	=====		
STA0361-129		US 36: HYGIENE RD AND NELSON	12/22/22	1,000.00	20.00	10.56	10.76
		WEIGHTED AVERAGE FOR THE FOURTH QUARTER		1,000.00	20.00	10.56	10.76
		WEIGHTED AVERAGE FOR THE YEAR		1,000.00	20.00	10.56	10.76
=====	211-01200	Rock Anchor		Lin Foot	=====		
SHE0242-087		US 24 SAFETY IMPRVMENTS, E OF	11/03/22	200.00	70.00	293.67	166.00
		WEIGHTED AVERAGE FOR THE FOURTH QUARTER		200.00	70.00	293.67	166.00
		WEIGHTED AVERAGE FOR THE YEAR		200.00	70.00	293.67	166.00
=====	211-01300	Rock Anchor		Each	=====		
C5502-111		US 550 MP 81 AND 89 RED MOUNT	10/27/22	22.00	2500.00	5800.00	6600.00
		WEIGHTED AVERAGE FOR THE FOURTH QUARTER		22.00	2500.00	5800.00	6600.00
		WEIGHTED AVERAGE FOR THE YEAR		22.00	2500.00	5800.00	6600.00
=====	211-02270	Cement Grout		Cubic Foot	=====		
BRC040-057			03/17/22	1,121.00	40.00	36.74	19.96
		WEIGHTED AVERAGE FOR THE FIRST QUARTER		1,121.00	40.00	36.74	19.96
		WEIGHTED AVERAGE FOR THE YEAR		1,121.00	40.00	36.74	19.96

COLORADO DEPARTMENT OF TRANSPORTATION
ITEM UNIT COSTS BY PROJECTS -- 2022 COST DATA

11:31 Wednesday, March 8, 2023 164

PROJECT NUMBER	ITEM NUMBER/ PROJECT LOCATION	ITEM DESCRIPTION/ PROJECT LOCATION	DATE LET	UNIT/ QUANTITY	ENGR. EST.	AVERAGE BID	AWARDED BID
===== 211-02275 Cement Grout Cubic Yard =====							
C0703-499		EJMT GROUT BED REPAIR AND PAN	03/31/22	8.00	1000.00	24300.00	32000.00
	WEIGHTED AVERAGE FOR THE FIRST QUARTER			8.00	1000.00	24300.00	32000.00
	WEIGHTED AVERAGE FOR THE YEAR			8.00	1000.00	24300.00	32000.00
===== 211-03005 Dewatering LUMP SUM =====							
NHPP 0761-238 C0761-239		I-76 DAHLIA TO YORK	03/10/22	1.00	10000.00	26353.44	1000.00
	WEIGHTED AVERAGE FOR THE FIRST QUARTER			1.00	10000.00	26353.44	1000.00
FSA052A-057 NHPP0063-054		SH52 BOX CULVERT EXTENSION (M US 6 FROM I70-B TO 33 RD. (MP	08/04/22 08/18/22	1.00 1.00	10000.00 20000.00	13315.00 54564.89	6344.00 47500.00
	WEIGHTED AVERAGE FOR THE THIRD QUARTER			2.00	15000.00	29814.95	26922.00
C170A-002 NHPP0343-048 BR012A-048		CRITICAL CULVERT CONST. PKG D US 34 (MP 169.3-171.4) CO 12 STRUCTURE P-17-F AT MP	10/27/22 11/01/22 12/22/22	1.00 1.00 1.00	15000.00 2000.00 20000.00	8575.00 21343.75 150000.00	1000.00 38000.00 150000.00
	WEIGHTED AVERAGE FOR THE FOURTH QUARTER			3.00	12333.33	41967.50	63000.00
	WEIGHTED AVERAGE FOR THE YEAR			6.00	12833.33	33894.67	40640.67
===== 211-04000 Monitor and Abandon of Instrument LUMP SUM =====							
NHPP0702-414 FBR0702-423		VAIL PASS AUX PHASE 1 CAP 3 VAIL PASS AUX BE F-12-AT PHAS	07/08/22	1.00	241526.82	241526.82	241526.82
	WEIGHTED AVERAGE FOR THE THIRD QUARTER			1.00	241526.82	241526.82	241526.82
	WEIGHTED AVERAGE FOR THE YEAR			1.00	241526.82	241526.82	241526.82
===== 212-00006 Seeding (Native) Acre =====							
NHPP2873-189		US 287 (FEDERAL BLVD) - COLFA	01/06/22	0.10	1000.00	9776.72	9072.80

COLORADO DEPARTMENT OF TRANSPORTATION
ITEM UNIT COSTS BY PROJECTS -- 2022 COST DATA

11:31 Wednesday, March 8, 2023 165

PROJECT NUMBER	ITEM NUMBER/ PROJECT LOCATION	ITEM DESCRIPTION/ PROJECT LOCATION	DATE LET	UNIT/ QUANTITY	ENGR. EST.	AVERAGE BID	AWARDED BID
=====	212-00006	Seeding (Native)		Acre =====			
NHPP0703-472			03/10/22	0.50	900.00	5242.64	4000.00
M R100-351		FY22 R1 SIGN STRUCTURE REPLAC	03/17/22	0.10	12000.00	9665.50	10371.00
		WEIGHTED AVERAGE FOR THE FIRST QUARTER		0.70	2500.00	6280.41	5634.83
NHPP0021-041		SH2 RESURFACING MLK TO 52ND	12/01/22	0.10	8000.00	16970.12	25534.80
		WEIGHTED AVERAGE FOR THE FOURTH QUARTER		0.10	8000.00	16970.12	25534.80
		WEIGHTED AVERAGE FOR THE YEAR		0.80	3187.50	7705.70	8122.33
=====	212-00007	Seeding (Native) (Hydraulic)		Acre =====			
STA0361-129		US 36: HYGIENE RD AND NELSON	12/22/22	0.07	30000.00	15396.30	8996.48
		WEIGHTED AVERAGE FOR THE FOURTH QUARTER		0.07	30000.00	15396.30	8996.48
		WEIGHTED AVERAGE FOR THE YEAR		0.07	30000.00	15396.30	8996.48
=====	212-00009	Seeding (Temporary)		Acre =====			
BRC040-057			03/17/22	0.10	4000.00	11648.65	5000.00
		WEIGHTED AVERAGE FOR THE FIRST QUARTER		0.10	4000.00	11648.65	5000.00
IM025A-050		I25-MP103.9 - INTERSECTION DR	12/01/22	1.40	1000.00	1333.33	1700.00
STR109A-019		M-22-AY BRIDGE REHAB ON SH109	12/01/22	0.13	10000.00	6806.25	7759.50
		WEIGHTED AVERAGE FOR THE FOURTH QUARTER		1.53	1764.71	2143.83	2900.85
		WEIGHTED AVERAGE FOR THE YEAR		1.63	1901.84	2698.04	2999.41
=====	212-00022	Seeding (Riparian)		Acre =====			
FBR0761-236		I-76 OVER CLR CRK SCOUR MIT	08/25/22	0.64	2000.00	5366.67	5900.00
NHPPR100-266		R1 ESSENTIAL REPAIRS	09/01/22	0.75	850.00	3329.83	2464.50
		WEIGHTED AVERAGE FOR THE THIRD QUARTER		1.39	1379.50	4267.66	4046.31
		WEIGHTED AVERAGE FOR THE YEAR		1.39	1379.50	4267.66	4046.31

COLORADO DEPARTMENT OF TRANSPORTATION
ITEM UNIT COSTS BY PROJECTS -- 2022 COST DATA

11:31 Wednesday, March 8, 2023 166

PROJECT NUMBER	ITEM NUMBER/ PROJECT LOCATION	ITEM DESCRIPTION/ PROJECT LOCATION	DATE LET	UNIT/ QUANTITY	ENGR. EST.	AVERAGE BID	AWARDED BID
===== 212-00028 Seeding (Wetlands) Acre =====							
FBR0761-236		I-76 OVER CLR CRK SCOUR MIT	08/25/22	0.05	6000.00	7116.67	7750.00
ER0502-092		US 50 MP 204 EB MONARCH TRUCK	08/29/22	0.01	4000.00	76465.00	111145.00
		WEIGHTED AVERAGE FOR THE THIRD QUARTER		0.06	5666.67	18674.72	24982.50
		WEIGHTED AVERAGE FOR THE YEAR		0.06	5666.67	18674.72	24982.50
===== 212-00032 Soil Conditioning Acre =====							
NHPP2873-189		US 287 (FEDERAL BLVD) - COLFA	01/06/22	0.10	3000.00	14528.66	18185.10
STA 067A-048		Hwy 67A MP 0.00 TO MP 11.05 I	03/03/22	0.65	3000.00	10060.41	11000.00
M R100-351		FY22 R1 SIGN STRUCTURE REPLAC	03/17/22	0.10	14500.00	15855.50	17401.00
		WEIGHTED AVERAGE FOR THE FIRST QUARTER		0.85	4352.94	11215.83	12598.36
FSA3921-019		SH 392 AND WCR 55 ISLANDS	06/02/22	0.10	2700.00	3382.33	4000.00
		WEIGHTED AVERAGE FOR THE SECOND QUARTER		0.10	2700.00	3382.33	4000.00
FSAM240-200		SH21B CO SPRINGS SIGNAL REPLA	10/27/22	0.50	5000.00	7375.63	2752.50
NHPP0021-041		SH2 RESURFACING MLK TO 52ND	12/01/22	0.10	10000.00	27113.44	32998.70
		WEIGHTED AVERAGE FOR THE FOURTH QUARTER		0.60	5833.33	10665.26	7793.53
		WEIGHTED AVERAGE FOR THE YEAR		1.55	4819.35	10516.51	10183.70
===== 212-00050 Sod Sq Foot =====							
NHPP0063-063			02/24/22	800.00	3.00	11.65	2.30
MP0503-098			03/24/22	10.00	20.00	27.50	25.00
		WEIGHTED AVERAGE FOR THE FIRST QUARTER		810.00	3.21	11.85	2.58
CC030-081		ADA RAMP AND CURBS - FT. LUPT	04/14/22	3,592.00	5.00	4.74	5.00
		WEIGHTED AVERAGE FOR THE SECOND QUARTER		3,592.00	5.00	4.74	5.00

COLORADO DEPARTMENT OF TRANSPORTATION
ITEM UNIT COSTS BY PROJECTS -- 2022 COST DATA

11:31 Wednesday, March 8, 2023 167

PROJECT NUMBER	ITEM NUMBER/ PROJECT LOCATION	ITEM DESCRIPTION/ PROJECT LOCATION	DATE LET	UNIT/ QUANTITY	ENGR. EST.	AVERAGE BID	AWARDED BID
===== 212-00050 Sod Sq Foot =====							
NHPP0063-054		US 6 FROM I70-B TO 33 RD. (MP 08/18/22		10,790.00	3.00	2.42	1.50
		WEIGHTED AVERAGE FOR THE THIRD QUARTER		10,790.00	3.00	2.42	1.50
STA3852-015		US 385 HOLYOKE NORTH	10/27/22	1,500.00	4.00	3.50	3.50
STAM420-001		US 285 AT HWY 9C IMPROVEMENTS	12/01/22	180.00	1.60	13.02	19.21
BR2854-148		INTERSECTION OF US 285 & SH 9					
STM0091-046		ADA RAMP IMPROVEMENTS - FAIRP					
		WEIGHTED AVERAGE FOR THE FOURTH QUARTER		1,680.00	3.74	6.59	5.18
		WEIGHTED AVERAGE FOR THE YEAR		16,872.00	3.51	3.79	2.66
===== 212-00700 Organic Fertilizer Pound =====							
NHPP0702-383		I-70 EB AUX FRISCO TO SILVERT	01/13/22	7,600.00	0.50	0.78	1.20
NHPP1601-083			02/03/22	19,200.00	1.50	1.37	1.30
C0762-055			02/17/22	960.00	1.75	0.88	0.50
STR0141-031			02/17/22	200.00	3.00	3.42	6.00
STA 067A-048		Hwy 67A MP 0.00 TO MP 11.05 I	03/03/22	75.00	10.00	6.48	8.00
NHPP 0761-238		I-76 DAHLIA TO YORK	03/10/22	3,900.00	3.00	0.60	0.35
C0761-239							
BRC040-057			03/17/22	90.00	5.00	6.18	4.72
STR R500-171		Various locations on SH 141 a	03/17/22	30.00	2.00	4.34	2.00
STR092A-031			03/17/22	150.00	0.40	3.80	3.80
NHM765-007			03/31/22	30.00	10.00	13.50	35.69
		WEIGHTED AVERAGE FOR THE FIRST QUARTER		32,235.00	1.50	0.99	1.24
NH0504-911			04/07/22	900.00	1.64	2.05	2.10
CC030-081		ADA RAMP AND CURBS - FT. LUPT	04/14/22	36.00	10.00	41.59	50.00
NHPP0702-413		VAIL PASS AUX PHASE 1 CAP 2	04/18/22	11,200.00	0.36	0.36	0.36
2670703-479		I-70 BRIDGE OVER HARLAN	05/05/22	1,260.00	1.40	0.76	0.95
ER0702-420		PR I-70 GWC MATERIAL FLOWS 20	05/06/22	900.00	3.00	1.83	1.65
STA001A-005		SH1 WELLINGTON SOUTH RESURFAC	05/12/22	9.00	1.40	26.50	22.00
NHC540-017		R2 CHAINUP STA @ KENOSHA/HOOS	05/12/22	1,700.00	2.00	1.37	0.60

COLORADO DEPARTMENT OF TRANSPORTATION
ITEM UNIT COSTS BY PROJECTS -- 2022 COST DATA

11:31 Wednesday, March 8, 2023 168

PROJECT NUMBER	ITEM NUMBER/ PROJECT LOCATION	ITEM DESCRIPTION/ PROJECT LOCATION	DATE LET	UNIT/ QUANTITY	ENGR. EST.	AVERAGE BID	AWARDED BID
=====	212-00700	Organic Fertilizer		Pound	=====	=====	=====
CM760-047		COLFAX AND QUAIL	05/12/22	4.00	1.60	107.80	80.00
NHPP 3851-018		US 385 NORTH OF CHEYENNE WELL	05/26/22	610.00	2.00	2.63	3.00
FSA0702-409		I-70 VAIL WILDLIFE FENCE PHAS	05/26/22	150.00	50.00	12.00	12.00
ITS 0741-024		VMS SIGN INSTALLATIONS AND VS	06/02/22	270.00	2.00	2.65	2.30
FSA3921-019		SH 392 AND WCR 55 ISLANDS	06/02/22	21.00	1.00	8.00	7.00
FSA052A-046		SH52 WCR 37 INTERSECTION IMPR	06/09/22	1,746.00	1.20	1.11	1.30
		WEIGHTED AVERAGE FOR THE SECOND QUARTER		18,806.00	1.34	1.24	0.99
NHPP0702-414		VAIL PASS AUX PHASE 1 CAP 3	07/08/22	11,840.00	0.35	0.35	0.35
FBR0702-423		VAIL PASS AUX BE F-12-AT PHAS					
FSA052A-057		SH52 BOX CULVERT EXTENSION (M	08/04/22	60.00	4.50	2.69	2.60
STR0711-022		SH 71 OVER THE ARKANSAS	08/04/22	300.00	2.00	5.80	5.00
NHPP0063-054		US 6 FROM I70-B TO 33 RD. (MP	08/18/22	16.00	2.00	4.99	2.50
ER0502-092		US 50 MP 204 EB MONARCH TRUCK	08/29/22	147.00	1.50	2.91	2.92
BR0343-046		US 34 TIMBER BRIDGE REPL. PKG	08/31/22	324.00	1.18	1.18	1.18
FBR0343-047		US 6/US 34 TIMBER BRIDGE REPL					
2670403-065		US40 FLOYD HILL ROUNDABOUTS	09/15/22	2,622.00	1.50	1.75	1.50
2670703-497		I-70 GENESEE WILDLIFE XING	09/15/22	972.00	1.50	3.66	3.81
SHE2873-193		US 287 & CO 52 INTERSECTION I	09/15/22	1,300.00	1.00	1.74	0.98
NHPP0701-231		I-70 SALT WASH BRIDGES SCOUR	09/29/22	288.00	4.00	1.50	2.00
		WEIGHTED AVERAGE FOR THE THIRD QUARTER		17,869.00	0.76	1.76	0.90
NHPP0701-253		I-70 EAST OF DEBEQUE	10/27/22	219.00	5.00	4.05	5.50
STA207A-004		Resurfacing SH207A MANZANOLA	10/27/22	730.00	1.25	2.70	2.60
NHPP0705-088		I-70 AGATE STRUCTURE REHAB	10/27/22	321.00	2.10	2.78	6.00
FSAM240-200		SH21B CO SPRINGS SIGNAL REPLA	10/27/22	150.00	2.00	12.24	10.95
TRG0253-264		I-25 AND SH 119 PARK-N-RIDE	10/27/22	2,435.00	1.00	1.16	1.30
STA3852-015		US 385 HOLYOKE NORTH	10/27/22	10,771.00	1.55	2.25	2.25
STU0252-457		I-25:ALAMEDA RIVER PH 2.0	11/03/22	900.00	2.00	1.46	2.30
SHE0242-087		US 24 SAFETY IMPRVMENTS, E OF	11/03/22	249.00	1.00	1.85	1.71
STR064A-010		SH 64 AND SH 13 AT MEEKER	11/10/22	180.00	5.00	2.78	3.30
NHPP0853-126		US85C: PLATTEVILLE NORTH MP (11/10/22	420.00	4.00	1.97	1.35
C5502-097		US550 MP 117.28-126.06	11/17/22	15,015.00	1.50	0.79	0.70
STAM420-001		US 285 AT HWY 9C IMPROVEMENTS	12/01/22	1,518.00	1.00	1.46	2.08
BR2854-148		INTERSECTION OF US 285 & SH 9					
STM0091-046		ADA RAMP IMPROVEMENTS - FAIRP					
STA0711-021		SH71: REGION LINE NORTH	12/01/22	90.00	1.60	9.32	10.00
STR114A-015		SH114 SILLSVILLE SOUTH TO MP3	12/01/22	150.00	5.00	25.00	40.00
NHPP0701-252		I-70 RIFLE TO SILT SLAB REPLA	12/01/22	15.00	7.00	2.15	0.30
IM025A-050		I25-MP103.9 - INTERSECTION DR	12/01/22	2,012.00	1.00	0.90	0.95

COLORADO DEPARTMENT OF TRANSPORTATION
ITEM UNIT COSTS BY PROJECTS -- 2022 COST DATA

11:31 Wednesday, March 8, 2023 169

PROJECT NUMBER	ITEM NUMBER/ PROJECT LOCATION	ITEM DESCRIPTION/ PROJECT LOCATION	DATE LET	UNIT/ QUANTITY	ENGR. EST.	AVERAGE BID	AWARDED BID
===== 212-00700 Organic Fertilizer Pound =====							
STR109A-019	M-22-AY BRIDGE REHAB ON SH109		12/01/22	78.00	5.00	8.72	12.93
NHPP0063-048	US6 / 20 ROAD INTERSECTION IM		12/15/22	912.00	2.50	1.76	0.60
NHPP0502-090	SH 50 MP 134.6-136 GUNNISON C		12/22/22	2,884.00	2.00	1.42	0.78
STA0361-129	US 36: HYGIENE RD AND NELSON		12/22/22	234.00	3.00	2.80	3.63
BR012A-048	CO 12 STRUCTURE P-17-F AT MP		12/22/22	3,250.00	1.50	1.77	1.50
WEIGHTED AVERAGE FOR THE FOURTH QUARTER				42,533.00	1.59	1.55	1.62
WEIGHTED AVERAGE FOR THE YEAR				111,443.00	1.39	1.34	1.30
===== 212-00701 Compost (Mech App) Cubic Yard =====							
NH0504-910	US50B L-24-B MIN REP AT MP 40		01/13/22	162.50	50.00	74.23	125.00
C0762-055			02/17/22	384.00	105.00	42.21	30.00
STA 067A-048	Hwy 67A MP 0.00 TO MP 11.05 I		03/03/22	17.00	100.00	189.25	220.00
NHPP 0761-238	I-76 DAHLIA TO YORK		03/10/22	211.00	50.00	56.35	39.00
C0761-239							
BRC040-057			03/17/22	10.00	100.00	110.88	107.50
NHM765-007			03/31/22	7.00	100.00	349.06	238.86
WEIGHTED AVERAGE FOR THE FIRST QUARTER				791.50	78.83	59.93	58.81
CC030-081	ADA RAMP AND CURBS - FT. LUPT		04/14/22	8.00	150.00	210.65	100.00
NHPP0702-413	VAIL PASS AUX PHASE 1 CAP 2		04/18/22	715.00	1.44	1.44	1.44
2670703-479	I-70 BRIDGE OVER HARLAN		05/05/22	52.00	50.00	66.02	83.32
STA0712-019	SH 71: Frieight Improvements		05/12/22	142.00	35.00	97.11	97.11
STA001A-005	SH1 WELLINGTON SOUTH RESURFAC		05/12/22	2.00	43.00	222.25	210.00
CM760-047	COLFAX AND QUAIL		05/12/22	1.00	132.00	326.20	362.00
NHPP 3851-018	US 385 NORTH OF CHEYENNE WELL		05/26/22	198.00	45.00	77.65	90.00
C0852-120	Rehabilitation of Culvert by		05/26/22	35.00	100.00	53.00	53.00
ITS 0741-024	VMS SIGN INSTALLATIONS AND VS		06/02/22	59.00	100.00	75.00	69.00
FSA3921-019	SH 392 AND WCR 55 ISLANDS		06/02/22	5.00	55.00	67.33	50.00
FSA052A-046	SH52 WCR 37 INTERSECTION IMPR		06/09/22	379.00	36.00	45.05	40.00
WEIGHTED AVERAGE FOR THE SECOND QUARTER				1,596.00	26.47	46.66	37.52
NHPP0702-414	VAIL PASS AUX PHASE 1 CAP 3		07/08/22	572.00	89.00	89.00	89.00
FBR0702-423	VAIL PASS AUX BE F-12-AT PHAS						
FSA052A-057	SH52 BOX CULVERT EXTENSION (M		08/04/22	13.00	100.00	54.21	52.00
NHPP0063-054	US 6 FROM I70-B TO 33 RD. (MP		08/18/22	4.00	32.00	115.70	105.00

COLORADO DEPARTMENT OF TRANSPORTATION
ITEM UNIT COSTS BY PROJECTS -- 2022 COST DATA

11:31 Wednesday, March 8, 2023 170

PROJECT NUMBER	ITEM NUMBER/ PROJECT LOCATION	ITEM DESCRIPTION/ PROJECT LOCATION	DATE LET	UNIT/ QUANTITY	ENGR. EST.	AVERAGE BID	AWARDED BID
===== 212-00701							
		Compost (Mech App)		Cubic Yard			
FBR0761-236		I-76 OVER CLR CRK SCOUR MIT	08/25/22	11.10	150.00	80.00	80.00
BR0343-046		US 34 TIMBER BRIDGE REPL. PKG	08/31/22	342.00	69.55	69.55	69.55
FBR0343-047		US 6/US 34 TIMBER BRIDGE REPL					
NHPPR100-266		R1 ESSENTIAL REPAIRS	09/01/22	32.50	65.00	109.34	88.51
2670403-065		US40 FLOYD HILL ROUNDABOUTS	09/15/22	14.00	150.00	112.62	150.00
SHE2873-193		US 287 & CO 52 INTERSECTION I	09/15/22	423.00	45.00	54.06	64.26
NHPP0701-231		I-70 SALT WASH BRIDGES SCOUR	09/29/22	314.00	50.00	63.70	55.00
		WEIGHTED AVERAGE FOR THE THIRD QUARTER		1,725.60	67.65	63.49	73.08
STA207A-004		Resurfacing SH207A MANZANOLA	10/27/22	60.00	75.00	135.18	130.55
NHPP0705-088		I-70 AGATE STRUCTURE REHAB	10/27/22	70.00	60.00	78.24	71.00
TRG0253-264		I-25 AND SH 119 PARK-N-RIDE	10/27/22	791.00	30.00	42.81	40.00
STA3852-015		US 385 HOLYOKE NORTH	10/27/22	3,489.00	45.00	43.10	43.10
STU0252-457		I-25:ALAMEDA RIVER PH 2.0	11/03/22	195.00	90.00	77.92	92.00
NHPP0853-126		US85C: PLATTEVILLE NORTH MP (11/10/22	46.00	65.00	69.38	47.50
C5502-097		US550 MP 117.28-126.06	11/17/22	3,250.00	60.00	61.83	60.70
STAM420-001		US 285 AT HWY 9C IMPROVEMENTS	12/01/22	2.00	38.00	589.81	224.16
BR2854-148		INTERSECTION OF US 285 & SH 9					
STM0091-046		ADA RAMP IMPROVEMENTS - FAIRP					
STA0711-021		SH71: REGION LINE NORTH	12/01/22	20.00	49.00	166.34	180.00
2670703-487		I-70 BRIDGES OVER WARD ROAD-	12/01/22	143.00	60.00	68.19	69.00
IM025A-050		I25-MP103.9 - INTERSECTION DR	12/01/22	360.00	45.00	77.67	93.00
STR109A-019		M-22-AY BRIDGE REHAB ON SH109	12/01/22	9.00	120.00	146.95	164.39
NHPP0063-048		US6 / 20 ROAD INTERSECTION IM	12/15/22	62.00	120.00	118.32	120.00
NHPP0931-033		SH93:US6 TO 58TH RESURFACING	12/15/22	26.00	50.00	71.62	61.50
NHPP0502-090		SH 50 MP 134.6-136 GUNNISON C	12/22/22	209.00	70.00	92.79	106.18
STA0361-129		US 36: HYGIENE RD AND NELSON	12/22/22	104.00	85.00	70.37	70.91
		WEIGHTED AVERAGE FOR THE FOURTH QUARTER		8,836.00	52.52	61.19	57.86
		WEIGHTED AVERAGE FOR THE YEAR		12,949.10	52.94	59.95	57.46
===== 212-00702							
		Bio Soil Amd (Hyd App)		Pound			
NHPP0702-383		I-70 EB AUX FRISCO TO SILVERT	01/13/22	20,150.00	2.00	1.26	1.70
NHPP1601-083			02/03/22	96,000.00	1.00	1.42	1.50
STA0252-459			02/03/22	2,240.00	1.00	1.64	1.18
NHPP 0761-238		I-76 DAHLIA TO YORK	03/10/22	650.00	1.00	1.66	1.50
C0761-239							
STR092A-031			03/17/22	1,750.00	0.90	5.45	5.45
		WEIGHTED AVERAGE FOR THE FIRST QUARTER		120,790.00	1.17	1.40	1.58

COLORADO DEPARTMENT OF TRANSPORTATION
ITEM UNIT COSTS BY PROJECTS -- 2022 COST DATA

11:31 Wednesday, March 8, 2023 171

PROJECT NUMBER	ITEM NUMBER/ PROJECT LOCATION	ITEM DESCRIPTION/ PROJECT LOCATION	DATE LET	UNIT/ QUANTITY	ENGR. EST.	AVERAGE BID	AWARDED BID
=====	212-00702	Bio Soil Amd (Hyd App)		Pound	=====		
NH0504-911			04/07/22	10,500.00	0.85	1.45	1.50
NHPP0702-413		VAIL PASS AUX PHASE 1 CAP 2	04/18/22	10,500.00	0.92	0.92	0.92
STM1151-038		SH115 MP 27 TO MP 38	04/21/22	180,600.00	1.50	1.07	0.86
2670703-479		I-70 BRIDGE OVER HARLAN	05/05/22	260.00	1.50	2.99	4.05
NHC540-017		R2 CHAINUP STA @ KENOSHA/HOOS	05/12/22	10,850.00	0.85	1.95	1.85
		WEIGHTED AVERAGE FOR THE SECOND QUARTER		212,710.00	1.41	1.11	0.95
NHPP0702-414		VAIL PASS AUX PHASE 1 CAP 3	07/08/22	21,000.00	0.93	0.93	0.93
FBR0702-423		VAIL PASS AUX BE F-12-AT PHAS					
BR0343-046		US 34 TIMBER BRIDGE REPL. PKG	08/31/22	355.00	1.34	1.34	1.34
FBR0343-047		US 6/US 34 TIMBER BRIDGE REPL					
NHPPR100-266		R1 ESSENTIAL REPAIRS	09/01/22	8,750.00	1.30	1.43	1.43
2670403-065		US40 FLOYD HILL ROUNDABOUTS	09/15/22	6,192.00	2.00	2.17	2.00
2670703-497		I-70 GENESEE WILDLIFE XING	09/15/22	2,625.00	2.00	4.14	6.82
NHPP0701-231		I-70 SALT WASH BRIDGES SCOUR	09/29/22	385.00	3.00	2.03	2.00
		WEIGHTED AVERAGE FOR THE THIRD QUARTER		39,307.00	1.28	2.06	1.62
FSAM240-200		SH21B CO SPRINGS SIGNAL REPLA	10/27/22	1,750.00	2.00	5.02	7.08
SHE0242-087		US 24 SAFETY IMPRVMENTS, E OF	11/03/22	2,905.00	1.60	2.11	2.08
C5502-097		US550 MP 117.28-126.06	11/17/22	175.00	2.00	3.87	2.55
STAM420-001		US 285 AT HWY 9C IMPROVEMENTS	12/01/22	17,500.00	2.00	1.70	2.50
BR2854-148		INTERSECTION OF US 285 & SH 9					
STM0091-046		ADA RAMP IMPROVEMENTS - FAIRP					
STR114A-015		SH114 SILLSVILLE SOUTH TO MP3	12/01/22	1,750.00	4.00	8.83	16.00
2670703-487		I-70 BRIDGES OVER WARD ROAD-	12/01/22	5,250.00	2.00	1.29	1.40
IM025A-050		I25-MP103.9 - INTERSECTION DR	12/01/22	19,355.00	2.00	1.35	1.40
NHPP0063-048		US6 / 20 ROAD INTERSECTION IM	12/15/22	7,350.00	2.00	2.58	1.30
NHPP0931-033		SH93:US6 TO 58TH RESURFACING	12/15/22	5,250.00	2.00	2.00	1.20
NHPP0502-090		SH 50 MP 134.6-136 GUNNISON C	12/22/22	22,400.00	1.50	1.81	1.62
STA0361-129		US 36: HYGIENE RD AND NELSON	12/22/22	245.00	2.00	6.48	4.02
BR012A-048		CO 12 STRUCTURE P-17-F AT MP	12/22/22	5,850.00	2.00	1.21	1.00
STR096A-050		SH 96 MP 168.99 TO 193.77	12/22/22	2,250.00	1.50	1.75	2.00
		WEIGHTED AVERAGE FOR THE FOURTH QUARTER		92,030.00	1.89	1.89	2.05
		WEIGHTED AVERAGE FOR THE YEAR		464,837.00	1.43	1.37	1.39

COLORADO DEPARTMENT OF TRANSPORTATION
ITEM UNIT COSTS BY PROJECTS -- 2022 COST DATA

11:31 Wednesday, March 8, 2023 172

PROJECT NUMBER	ITEM NUMBER/ PROJECT LOCATION	ITEM DESCRIPTION/ PROJECT LOCATION	DATE LET	UNIT/ QUANTITY	ENGR. EST.	AVERAGE BID	AWARDED BID
=====	212-00703	Humate		Pound	=====	=====	=====
NH0504-910		US50B I-24-B MIN REP AT MP 40	01/13/22	375.00	4.00	1.38	2.25
NHPP0702-383		I-70 EB AUX FRISCO TO SILVERT	01/13/22	1,850.00	40.00	0.87	1.00
NHPP1601-083			02/03/22	1,800.00	1.50	3.47	2.00
STA0252-459			02/03/22	128.00	1.00	1.11	0.74
C0762-055			02/17/22	480.00	2.00	1.33	0.75
STR0141-031			02/17/22	130.00	3.00	5.45	10.00
STA 067A-048		Hwy 67A MP 0.00 TO MP 11.05 I	03/03/22	50.00	10.00	10.04	9.00
NHPP 0761-238		I-76 DAHLIA TO YORK	03/10/22	1,300.00	3.60	1.04	0.75
C0761-239							
BRC040-057			03/17/22	30.00	2.00	9.17	0.57
STR R500-171		Various locations on SH 141 a	03/17/22	20.00	2.50	5.67	2.00
STR092A-031			03/17/22	100.00	1.00	4.35	4.35
NHM765-007			03/31/22	20.00	10.00	19.34	48.80
		WEIGHTED AVERAGE FOR THE FIRST QUARTER		6,283.00	13.57	1.53	1.74
NH0504-911			04/07/22	225.00	1.65	2.65	2.80
CC030-081		ADA RAMP AND CURBS - FT. LUPT	04/14/22	24.00	15.00	41.83	50.00
NHPP0702-413		VAIL PASS AUX PHASE 1 CAP 2	04/18/22	1,875.00	0.33	0.33	0.33
STM1151-038		SH115 MP 27 TO MP 38	04/21/22	3,870.00	0.85	0.74	0.43
2670703-479		I-70 BRIDGE OVER HARLAN	05/05/22	420.00	1.50	0.67	0.72
ER0702-420		PR I-70 GWC MATERIAL FLOWS 20	05/06/22	900.00	20.00	1.56	1.46
STA0712-019		SH 71: Frieight Improvements	05/12/22	1,433.00	1.50	1.28	1.28
STA001A-005		SH1 WELLINGTON SOUTH RESURFAC	05/12/22	6.00	1.50	29.40	11.00
NHC540-017		R2 CHAINUP STA @ KENOSHA/HOOS	05/12/22	233.00	2.00	2.95	0.85
CM760-047		COLFAX AND QUAIL	05/12/22	3.00	3.50	142.40	119.00
NHPP 3851-018		US 385 NORTH OF CHEYENNE WELL	05/26/22	458.00	2.00	4.25	5.00
C0852-120		Rehabilitation of Culvert by	05/26/22	120.00	5.00	3.00	3.00
FSA0702-409		I-70 VAIL WILDLIFE FENCE PHAS	05/26/22	150.00	17.00	12.00	12.00
ITS 0741-024		VMS SIGN INSTALLATIONS AND VS	06/02/22	180.00	5.00	2.75	2.50
FSA3921-019		SH 392 AND WCR 55 ISLANDS	06/02/22	13.00	2.50	8.67	7.00
FSA052A-046		SH52 WCR 37 INTERSECTION IMPR	06/09/22	873.00	1.50	1.53	1.90
		WEIGHTED AVERAGE FOR THE SECOND QUARTER		10,783.00	2.99	1.29	1.38
NHPP0702-414		VAIL PASS AUX PHASE 1 CAP 3	07/08/22	1,770.00	0.46	0.46	0.46
FBR0702-423		VAIL PASS AUX BE F-12-AT PHAS					
FSA052A-057		SH52 BOX CULVERT EXTENSION (M	08/04/22	30.00	10.00	4.41	2.60
STR0711-022		SH 71 OVER THE ARKANSAS	08/04/22	150.00	3.00	10.25	8.00
NHPP0063-054		US 6 FROM I70-B TO 33 RD. (MP	08/18/22	11.00	3.00	7.07	2.50

COLORADO DEPARTMENT OF TRANSPORTATION
ITEM UNIT COSTS BY PROJECTS -- 2022 COST DATA

11:31 Wednesday, March 8, 2023 173

PROJECT NUMBER	ITEM NUMBER/ PROJECT LOCATION	ITEM DESCRIPTION/ PROJECT LOCATION	DATE LET	UNIT/ QUANTITY	ENGR. EST.	AVERAGE BID	AWARDED BID
===== 212-00703 Humate Pound =====							
FBR0761-236		I-76 OVER CLR CRK SCOUR MIT	08/25/22	34.00	5.00	6.33	7.00
ER0502-092		US 50 MP 204 EB MONARCH TRUCK	08/29/22	74.00	3.50	3.54	3.36
BR0343-046		US 34 TIMBER BRIDGE REPL. PKG	08/31/22	794.00	0.96	0.96	0.96
FBR0343-047		US 6/US 34 TIMBER BRIDGE REPL					
NHPPR100-266		R1 ESSENTIAL REPAIRS	09/01/22	100.00	2.50	1.20	1.59
2670403-065		US40 FLOYD HILL ROUNDABOUTS	09/15/22	147.00	3.00	4.18	3.00
2670703-497		I-70 GENESEE WILDLIFE XING	09/15/22	648.00	1.50	4.36	4.54
SHE2873-193		US 287 & CO 52 INTERSECTION I	09/15/22	975.00	2.14	1.63	0.72
NHPP0701-231		I-70 SALT WASH BRIDGES SCOUR	09/29/22	742.00	3.00	2.55	4.00
WEIGHTED AVERAGE FOR THE THIRD QUARTER				5,475.00	1.60	2.71	1.93
NHPP0701-253		I-70 EAST OF DEBEQUE	10/27/22	146.00	7.00	4.53	5.50
STA207A-004		Resurfacing SH207A MANZANOLA	10/27/22	168.00	1.25	8.13	7.40
NHPP0705-088		I-70 AGATE STRUCTURE REHAB	10/27/22	193.00	1.75	4.27	8.00
FSAM240-200		SH21B CO SPRINGS SIGNAL REPLA	10/27/22	37.50	5.00	13.13	11.92
C170A-002		CRITICAL CULVERT CONST. PKG D	10/27/22	74.00	6.00	3.78	3.13
TRG0253-264		I-25 AND SH 119 PARK-N-RIDE	10/27/22	1,826.00	1.00	1.09	1.00
STA3852-015		US 385 HOLYOKE NORTH	10/27/22	8,060.00	1.75	2.50	2.50
STU0252-457		I-25:ALAMEDA RIVER PH 2.0	11/03/22	450.00	3.00	3.34	3.00
SHE0242-087		US 24 SAFETY IMPRVMENTS, E OF	11/03/22	63.00	1.60	85.33	2.99
STR064A-010		SH 64 AND SH 13 AT MEEKER	11/10/22	120.00	3.50	3.50	4.40
NHPP0853-126		US85C: PLATTEVILLE NORTH MP (11/10/22	105.00	4.00	2.67	2.60
C5502-097		US550 MP 117.28-126.06	11/17/22	10,010.00	1.75	1.01	0.95
STAM420-001		US 285 AT HWY 9C IMPROVEMENTS	12/01/22	381.00	1.00	2.77	1.92
BR2854-148		INTERSECTION OF US 285 & SH 9					
STM0091-046		ADA RAMP IMPROVEMENTS - FAIRP					
STA0711-021		SH71: REGION LINE NORTH	12/01/22	45.00	1.50	16.77	20.00
STR114A-015		SH114 SILLSVILLE SOUTH TO MP3	12/01/22	100.00	10.00	11.00	7.00
2670703-487		I-70 BRIDGES OVER WARD ROAD-	12/01/22	740.00	5.00	1.73	1.60
NHPP0701-252		I-70 RIFLE TO SILT SLAB REPLA	12/01/22	10.00	7.00	3.88	1.75
IM025A-050		I25-MP103.9 - INTERSECTION DR	12/01/22	845.00	1.00	1.37	2.00
STR109A-019		M-22-AY BRIDGE REHAB ON SH109	12/01/22	26.00	5.00	23.23	39.46
NHPP0063-048		US6 / 20 ROAD INTERSECTION IM	12/15/22	608.00	1.75	1.87	0.60
NHPP0931-033		SH93:US6 TO 58TH RESURFACING	12/15/22	380.00	2.00	1.96	1.15
NHPP0502-090		SH 50 MP 134.6-136 GUNNISON C	12/22/22	1,923.00	2.00	1.82	1.07
STA0361-129		US 36: HYGIENE RD AND NELSON	12/22/22	112.00	5.00	3.22	3.79
BR012A-048		CO 12 STRUCTURE P-17-F AT MP	12/22/22	98.00	2.25	5.04	5.00
STA385A-016		SH 385 MP 97.76	12/22/22	480.00	1.00	3.33	2.81
WEIGHTED AVERAGE FOR THE FOURTH QUARTER				27,000.50	1.89	2.00	1.78
WEIGHTED AVERAGE FOR THE YEAR				49,541.50	3.58	1.84	1.70
===== 212-00704 Mycorrhizae Pound =====							
NH0504-910		US50B L-24-B MIN REP AT MP 40	01/13/22	20.00	30.00	18.32	35.00

COLORADO DEPARTMENT OF TRANSPORTATION
ITEM UNIT COSTS BY PROJECTS -- 2022 COST DATA

11:31 Wednesday, March 8, 2023 174

PROJECT NUMBER	ITEM NUMBER/ PROJECT LOCATION	ITEM DESCRIPTION/ PROJECT LOCATION	DATE LET	UNIT/ QUANTITY	ENGR. EST.	AVERAGE BID	AWARDED BID
===== 212-00704 Mycorrhizae Pound =====							
NHPP0702-383		I-70 EB AUX FRISCO TO SILVERT	01/13/22	270.00	50.00	7.88	2.50
NHPP1601-083			02/03/22	480.00	20.00	25.70	21.00
STA0252-459			02/03/22	12.80	15.00	26.40	13.50
C0762-055			02/17/22	28.00	20.00	22.34	16.00
BRC040-057			03/17/22	15.00	25.00	38.93	9.70
WEIGHTED AVERAGE FOR THE FIRST QUARTER				825.80	30.06	16.45	14.80
NH0504-911			04/07/22	60.00	23.50	13.15	11.30
NHPP0702-413		VAIL PASS AUX PHASE 1 CAP 2	04/18/22	280.00	11.56	11.56	11.56
STM1151-038		SH115 MP 27 TO MP 38	04/21/22	1,032.00	17.50	11.19	9.60
STA0712-019		SH 71: Frieight Improvements	05/12/22	76.00	20.00	12.19	12.19
NHC540-017		R2 CHAINUP STA @ KENOSHA/HOOS	05/12/22	62.00	19.00	23.00	14.00
NHPP 3851-018		US 385 NORTH OF CHEYENNE WELL	05/26/22	25.00	18.00	43.25	50.00
C0852-120		Rehabilitation of Culvert by	05/26/22	12.00	30.00	18.00	18.00
ITS 0741-024		VMS SIGN INSTALLATIONS AND VS	06/02/22	8.00	25.00	81.00	75.00
FSA3921-019		SH 392 AND WCR 55 ISLANDS	06/02/22	1.00	45.00	197.00	13.00
FSA052A-046		SH52 WCR 37 INTERSECTION IMPR	06/09/22	47.00	23.00	24.35	30.00
WEIGHTED AVERAGE FOR THE SECOND QUARTER				1,603.00	17.18	12.66	11.92
NHPP0702-414		VAIL PASS AUX PHASE 1 CAP 3	07/08/22	296.00	11.30	11.30	11.30
FBR0702-423		VAIL PASS AUX BE F-12-AT PHAS					
FSA052A-057		SH52 BOX CULVERT EXTENSION (M	08/04/22	4.00	40.00	91.75	26.00
STR0711-022		SH 71 OVER THE ARKANSAS	08/04/22	8.00	19.00	195.33	125.00
FBR0761-236		I-76 OVER CLR CRK SCOUR MIT	08/25/22	1.40	18.00	21.67	20.00
ER0502-092		US 50 MP 204 EB MONARCH TRUCK	08/29/22	10.00	30.00	40.88	38.88
BR0343-046		US 34 TIMBER BRIDGE REPL. PKG	08/31/22	43.00	26.75	26.75	26.75
FBR0343-047		US 6/US 34 TIMBER BRIDGE REPL					
NHPPR100-266		R1 ESSENTIAL REPAIRS	09/01/22	10.00	35.00	24.27	23.06
2670403-065		US40 FLOYD HILL ROUNDABOUTS	09/15/22	37.00	50.00	23.57	30.00
SHE2873-193		US 287 & CO 52 INTERSECTION I	09/15/22	60.00	25.00	20.84	14.50
NHPP0701-231		I-70 SALT WASH BRIDGES SCOUR	09/29/22	46.00	20.00	21.28	20.00
WEIGHTED AVERAGE FOR THE THIRD QUARTER				515.40	18.92	24.35	17.75
NHPP0705-088		I-70 AGATE STRUCTURE REHAB	10/27/22	9.00	23.00	26.88	45.00
FSAM240-200		SH21B CO SPRINGS SIGNAL REPLA	10/27/22	10.00	12.00	44.21	45.82
C170A-002		CRITICAL CULVERT CONST. PKG D	10/27/22	4.00	50.00	60.75	70.00

COLORADO DEPARTMENT OF TRANSPORTATION
ITEM UNIT COSTS BY PROJECTS -- 2022 COST DATA

11:31 Wednesday, March 8, 2023 175

PROJECT NUMBER	ITEM NUMBER/ PROJECT LOCATION	ITEM DESCRIPTION/ PROJECT LOCATION	DATE LET	UNIT/ QUANTITY	ENGR. EST.	AVERAGE BID	AWARDED BID
===== 212-00704 Mycorrhizae Pound =====							
TRG0253-264		I-25 AND SH 119 PARK-N-RIDE	10/27/22	101.00	20.00	20.05	21.00
STA3852-015		US 385 HOLYOKE NORTH	10/27/22	435.00	20.00	22.10	22.10
STU0252-457		I-25:ALAMEDA RIVER PH 2.0	11/03/22	24.00	25.00	19.68	29.00
SHE0242-087		US 24 SAFETY IMPRVMENTS, E OF	11/03/22	17.00	21.00	22.01	17.02
NHPP0853-126		US85C: PLATTEVILLE NORTH MP (11/10/22	14.00	50.00	20.85	46.50
STAM420-001		US 285 AT HWY 9C IMPROVEMENTS	12/01/22	100.00	17.07	18.39	3.89
BR2854-148		INTERSECTION OF US 285 & SH 9					
STM0091-046		ADA RAMP IMPROVEMENTS - FAIRP					
STA0711-021		SH71: REGION LINE NORTH	12/01/22	6.00	17.00	139.99	120.00
2670703-487		I-70 BRIDGES OVER WARD ROAD-	12/01/22	50.00	15.00	14.80	15.00
IM025A-050		I25-MP103.9 - INTERSECTION DR	12/01/22	46.00	20.00	14.33	17.00
STR109A-019		M-22-AY BRIDGE REHAB ON SH109	12/01/22	13.00	50.00	73.07	85.13
NHPP0931-033		SH93:US6 TO 58TH RESURFACING	12/15/22	34.00	25.00	14.57	12.30
STA0361-129		US 36: HYGIENE RD AND NELSON	12/22/22	7.10	75.00	19.24	21.99
BR012A-048		CO 12 STRUCTURE P-17-F AT MP	12/22/22	26.00	35.00	26.85	10.00
STA385A-016		SH 385 MP 97.76	12/22/22	27.00	30.00	27.38	37.50
	WEIGHTED AVERAGE FOR THE FOURTH QUARTER			923.10	21.81	21.55	21.78
	WEIGHTED AVERAGE FOR THE YEAR			3,867.30	21.27	16.32	15.67
===== 212-00705 Elemental Sulfur Pound =====							
BRC040-057			03/17/22	3.00	20.00	52.50	10.00
	WEIGHTED AVERAGE FOR THE FIRST QUARTER			3.00	20.00	52.50	10.00
STA0712-019		SH 71: Frieght Improvements	05/12/22	948.00	1.50	1.03	1.03
C0852-120		Rehabilitation of Culvert by	05/26/22	36.00	15.00	3.00	3.00
ITS 0741-024		VMS SIGN INSTALLATIONS AND VS	06/02/22	8.00	20.00	22.50	21.00
	WEIGHTED AVERAGE FOR THE SECOND QUARTER			992.00	2.14	1.44	1.26
NHPP0702-414		VAIL PASS AUX PHASE 1 CAP 3	07/08/22	880.00	0.71	0.71	0.71
FBR0702-423		VAIL PASS AUX BE F-12-AT PHAS					
ER0502-092		US 50 MP 204 EB MONARCH TRUCK	08/29/22	29.00	20.00	9.56	8.68
NHPPRI00-266		R1 ESSENTIAL REPAIRS	09/01/22	30.00	2.00	7.75	4.24
	WEIGHTED AVERAGE FOR THE THIRD QUARTER			939.00	1.35	2.04	1.07
STR109A-019		M-22-AY BRIDGE REHAB ON SH109	12/01/22	3.00	100.00	141.22	220.43
	WEIGHTED AVERAGE FOR THE FOURTH QUARTER			3.00	100.00	141.22	220.43
	WEIGHTED AVERAGE FOR THE YEAR			1,937.00	1.93	2.45	1.52

COLORADO DEPARTMENT OF TRANSPORTATION
ITEM UNIT COSTS BY PROJECTS -- 2022 COST DATA

11:31 Wednesday, March 8, 2023 176

PROJECT NUMBER	ITEM NUMBER/ PROJECT LOCATION	ITEM DESCRIPTION/ PROJECT LOCATION	DATE LET	UNIT/ QUANTITY	ENGR. EST.	AVERAGE BID	AWARDED BID
=====	212-00706	Seed (Native) Drill		Acre	=====		
NH0504-910		US50B L-24-B MIN REP AT MP 40	01/13/22	2.50	3500.00	1189.93	1250.00
NHPP0702-383		I-70 EB AUX FRISCO TO SILVERT	01/13/22	9.60	900.00	959.55	1300.00
C0762-055			02/17/22	3.00	1200.00	809.48	570.00
STR0141-031			02/17/22	0.65	5000.00	3375.00	1625.00
NHPP 0761-238		I-76 DAHLIA TO YORK	03/10/22	3.25	2000.00	571.82	500.00
C0761-239							
NHPP0253-275		I-25 EXPRESS LANES SEGMENT 5	03/11/22	1.54	11283.00	7710.52	7710.52
		WEIGHTED AVERAGE FOR THE FIRST QUARTER		20.54	2342.54	1031.08	1551.63
NHPP0702-413		VAIL PASS AUX PHASE 1 CAP 2	04/18/22	10.00	4708.00	4708.00	4708.00
2670703-479		I-70 BRIDGE OVER HARLAN	05/05/22	1.20	1400.00	1215.70	1190.28
STA0712-019		SH 71: Frieght Improvements	05/12/22	9.60	1000.00	738.88	738.88
NHPP 3851-018		US 385 NORTH OF CHEYENNE WELL	05/26/22	3.05	1200.00	1400.00	1600.00
ITS 0741-024		VMS SIGN INSTALLATIONS AND VS	06/02/22	0.90	5000.00	2813.50	2600.00
FSA3921-019		SH 392 AND WCR 55 ISLANDS	06/02/22	0.10	1300.00	5712.67	7000.00
FSA052A-046		SH52 WCR 37 INTERSECTION IMPR	06/09/22	5.82	1000.00	1053.10	1015.00
		WEIGHTED AVERAGE FOR THE SECOND QUARTER		30.67	2362.90	1698.75	2263.74
NHPP0702-414		VAIL PASS AUX PHASE 1 CAP 3	07/08/22	8.30	1309.68	1309.68	1309.68
FBR0702-423		VAIL PASS AUX BE F-12-AT PHAS					
STR0711-022		SH 71 OVER THE ARKANSAS	08/04/22	0.50	1165.27	7064.00	12000.00
NHPP0063-054		US 6 FROM I70-B TO 33 RD. (MP	08/18/22	0.05	2500.00	15482.31	15000.00
FBR0761-236		I-76 OVER CLR CRK SCOUR MIT	08/25/22	0.17	3000.00	4300.00	5000.00
BR0343-046		US 34 TIMBER BRIDGE REPL. PKG	08/31/22	5.25	722.25	722.25	722.25
FBR0343-047		US 6/US 34 TIMBER BRIDGE REPL					
ER0253-297		WCR 34 BRIDGE OVER I-25(MM 24	09/14/22	0.50	3000.00	4510.24	960.00
2670703-497		I-70 GENESEE WILDLIFE XING	09/15/22	2.49	1700.00	1163.69	1431.22
SHE2873-193		US 287 & CO 52 INTERSECTION I	09/15/22	5.90	2000.00	1199.78	1064.00
NHPP0701-231		I-70 SALT WASH BRIDGES SCOUR	09/29/22	4.40	3000.00	1569.31	1600.00
		WEIGHTED AVERAGE FOR THE THIRD QUARTER		27.56	1691.35	1445.49	1438.21
NHPP0705-088		I-70 AGATE STRUCTURE REHAB	10/27/22	1.07	1900.00	1888.43	5000.00
C170A-002		CRITICAL CULVERT CONST. PKG D	10/27/22	0.49	4000.00	4187.50	5000.00
TRG0253-264		I-25 AND SH 119 PARK-N-RIDE	10/27/22	11.91	1050.00	1465.13	1200.00

PROJECT NUMBER	ITEM NUMBER/ PROJECT LOCATION	ITEM DESCRIPTION/ PROJECT LOCATION	DATE LET	UNIT/ QUANTITY	ENGR. EST.	AVERAGE BID	AWARDED BID
===== 212-00706 Seed (Native) Drill Acre =====							
STA3852-015		US 385 HOLYOKE NORTH	10/27/22	53.10	800.00	870.00	870.00
STU0252-457		I-25:ALAMEDA RIVER PH 2.0	11/03/22	5.00	2000.00	1608.85	1400.00
C5502-097		US550 MP 117.28-126.06	11/17/22	43.20	1000.00	914.89	831.00
STRC090-011		US 50B AND SH71/CR18 INTERSEC	11/17/22	0.60	1050.00	12182.50	10950.00
2670703-487		I-70 BRIDGES OVER WARD ROAD-	12/01/22	2.00	706.20	981.98	990.00
IM025A-050		I25-MP103.9 - INTERSECTION DR	12/01/22	5.23	2000.00	1700.00	1800.00
NHPP0063-048		US6 / 20 ROAD INTERSECTION IM	12/15/22	0.94	1100.00	2657.93	2200.00
NHPP0931-033		SH93:US6 TO 58TH RESURFACING	12/15/22	0.40	2500.00	1929.55	1025.50
NHPP0502-090		SH 50 MP 134.6-136 GUNNISON C	12/22/22	3.20	1500.00	1241.43	1167.94
STA0361-129		US 36: HYGIENE RD AND NELSON	12/22/22	0.71	2000.00	2216.37	2461.22
STA385A-016		SH 385 MP 97.76	12/22/22	3.00	1000.00	2430.63	2687.50
	WEIGHTED AVERAGE FOR THE FOURTH QUARTER			130.85	1038.86	1364.14	1146.35
	WEIGHTED AVERAGE FOR THE YEAR			209.62	1446.11	1350.98	1378.29
===== 212-00707 Seed (Native) Hyd Acre =====							
NHPP0702-383		I-70 EB AUX FRISCO TO SILVERT	01/13/22	6.60	1500.00	1290.84	1600.00
NHPP1601-083			02/03/22	24.00	1000.00	1581.32	1500.00
STA0252-459			02/03/22	0.64	800.00	4846.49	4925.00
NHPP 0761-238		I-76 DAHLIA TO YORK	03/10/22	3.25	2000.00	891.42	1000.00
C0761-239							
STR092A-031			03/17/22	0.50	2000.00	1845.00	1845.00
	WEIGHTED AVERAGE FOR THE FIRST QUARTER			34.99	1197.83	1388.28	1540.00
NH0504-911			04/07/22	3.00	5000.00	2175.00	2250.00
NHPP0702-413		VAIL PASS AUX PHASE 1 CAP 2	04/18/22	3.00	2427.83	2427.83	2427.83
STM1151-038		SH115 MP 27 TO MP 38	04/21/22	51.60	1400.00	1383.47	1382.00
2670703-479		I-70 BRIDGE OVER HARLAN	05/05/22	2.00	1800.00	1168.39	1003.33
ER0702-420		PR I-70 GWC MATERIAL FLOWS 20	05/06/22	1.50	4500.00	2400.00	2300.00
NHC540-017		R2 CHAINUP STA @ KENOSHA/HOOS	05/12/22	3.10	700.00	2390.00	1670.00
	WEIGHTED AVERAGE FOR THE SECOND QUARTER			64.20	1667.34	1444.27	1494.99
NHPP0702-414		VAIL PASS AUX PHASE 1 CAP 3	07/08/22	6.00	3039.55	3039.55	3039.55
FBR0702-423		VAIL PASS AUX BE F-12-AT PHAS					
BR0343-046		US 34 TIMBER BRIDGE REPL. PKG	08/31/22	0.09	1141.33	1247.31	1247.31
FBR0343-047		US 6/US 34 TIMBER BRIDGE REPL					

COLORADO DEPARTMENT OF TRANSPORTATION
ITEM UNIT COSTS BY PROJECTS -- 2022 COST DATA

11:31 Wednesday, March 8, 2023 178

PROJECT NUMBER	ITEM NUMBER/ PROJECT LOCATION	ITEM DESCRIPTION/ PROJECT LOCATION	DATE LET	UNIT/ QUANTITY	ENGR. EST.	AVERAGE BID	AWARDED BID
===== 212-00707 Seed (Native) Hyd Acre =====							
NHPPR100-266		R1 ESSENTIAL REPAIRS	09/01/22	2.50	1800.00	1819.27	1727.80
2670403-065		US40 FLOYD HILL ROUNDABOUTS	09/15/22	1.55	2500.00	1409.87	1100.00
2670703-497		I-70 GENESEE WILDLIFE KING	09/15/22	0.75	2500.00	1681.16	2266.10
NHPP0701-231		I-70 SALT WASH BRIDGES SCOUR	09/29/22	0.10	6000.00	3488.81	1600.00
WEIGHTED AVERAGE FOR THE THIRD QUARTER				10.99	2656.05	2029.29	2387.05
NHPP0701-253		I-70 EAST OF DEBEQUE	10/27/22	0.73	2000.00	3115.00	3500.00
FSAM240-200		SH21B CO SPRINGS SIGNAL REPLA	10/27/22	0.50	3000.00	6400.00	5650.00
SHE0242-087		US 24 SAFETY IMPRVMENTS, E OF	11/03/22	0.63	2000.00	2049.67	2814.00
STR064A-010		SH 64 AND SH 13 AT MEEKER	11/10/22	0.40	3000.00	2605.00	2900.00
C5502-097		US550 MP 117.28-126.06	11/17/22	0.05	2000.00	9200.33	10690.00
STAM420-001		US 285 AT HWY 9C IMPROVEMENTS	12/01/22	5.00	1754.00	2418.01	3714.72
BR2854-148		INTERSECTION OF US 285 & SH 9					
STM0091-046		ADA RAMP IMPROVEMENTS - FAIRP					
STR114A-015		SH114 SILLSVILLE SOUTH TO MP3	12/01/22	0.50	3000.00	10750.00	14000.00
2670703-487		I-70 BRIDGES OVER WARD ROAD-	12/01/22	1.50	1200.00	1547.10	1560.00
IM025A-050		I25-MP103.9 - INTERSECTION DR	12/01/22	0.30	1500.00	5093.53	3880.60
NHPP0063-048		US6 / 20 ROAD INTERSECTION IM	12/15/22	2.10	1250.00	3355.16	2650.00
NHPP0931-033		SH93:US6 TO 58TH RESURFACING	12/15/22	1.50	2500.00	1558.61	1230.00
NHPP0502-090		SH 50 MP 134.6-136 GUNNISON C	12/22/22	6.40	1500.00	1733.40	2096.65
BR012A-048		CO 12 STRUCTURE P-17-F AT MP	12/22/22	1.30	3500.00	1948.62	2000.00
STR096A-050		SH 96 MP 168.99 TO 193.77	12/22/22	0.50	1700.00	2993.00	3300.00
WEIGHTED AVERAGE FOR THE FOURTH QUARTER				21.41	1840.96	2349.69	2942.72
WEIGHTED AVERAGE FOR THE YEAR				131.59	1653.32	1612.27	1817.01
===== 212-00708 Seed (Native) Brdcst Acre =====							
NHPP0702-383		I-70 EB AUX FRISCO TO SILVERT	01/13/22	1.40	15000.00	2337.03	3000.00
C0762-055			02/17/22	0.20	3000.00	1737.01	650.00
STA 067A-048		Hwy 67A MP 0.00 TO MP 11.05 I	03/03/22	0.65	1000.00	2330.48	1500.00
BRC040-057			03/17/22	0.15	4000.00	11244.05	3522.00
STR R500-171		Various locations on SH 141 a	03/17/22	0.10	1620.00	4581.39	5000.00
NHM765-007			03/31/22	0.10	20000.00	11797.38	18319.33
WEIGHTED AVERAGE FOR THE FIRST QUARTER				2.60	9620.00	3100.76	3140.47
CC030-081		ADA RAMP AND CURBS - FT. LUPT	04/14/22	0.12	15000.00	12923.45	5000.00

COLORADO DEPARTMENT OF TRANSPORTATION
ITEM UNIT COSTS BY PROJECTS -- 2022 COST DATA

11:31 Wednesday, March 8, 2023 179

PROJECT NUMBER	ITEM NUMBER/ PROJECT LOCATION	ITEM DESCRIPTION/ PROJECT LOCATION	DATE LET	UNIT/ QUANTITY	ENGR. EST.	AVERAGE BID	AWARDED BID
=====	212-00708	Seed (Native) Brdcst		Acre =====			
NHPP0702-413	VAIL PASS AUX PHASE 1 CAP 2	VAIL PASS AUX PHASE 1 CAP 2	04/18/22	1.00	4716.56	4716.56	4716.56
ER0702-420	PR I-70 GWC MATERIAL FLOWS 20	PR I-70 GWC MATERIAL FLOWS 20	05/06/22	2.00	4500.00	1500.00	1500.00
STA001A-005	SH1 WELLINGTON SOUTH RESURFAC	SH1 WELLINGTON SOUTH RESURFAC	05/12/22	0.03	900.00	24286.78	5000.00
CM760-047	COLFAX AND QUAIL	COLFAX AND QUAIL	05/12/22	0.01	4000.00	72837.40	58387.00
C0852-120	Rehabilitation of Culvert by	Rehabilitation of Culvert by	05/26/22	0.76	5000.00	1200.00	1200.00
FSA0702-409	I-70 VAIL WILDLIFE FENCE PHAS	I-70 VAIL WILDLIFE FENCE PHAS	05/26/22	0.75	6000.00	12500.00	12500.00
MTCE0253-291	I-25 SIGN REPLACEMENT PHASE 2	I-25 SIGN REPLACEMENT PHASE 2	06/16/22	0.10	2000.00	11012.80	3275.60
	WEIGHTED AVERAGE FOR THE SECOND QUARTER			4.77	5048.31	4732.48	4156.75
NHPP0702-414	VAIL PASS AUX PHASE 1 CAP 3	VAIL PASS AUX PHASE 1 CAP 3	07/08/22	0.50	1424.28	1424.28	1424.28
FBR0702-423	VAIL PASS AUX BE F-12-AT PHAS	VAIL PASS AUX BE F-12-AT PHAS					
FSA052A-057	SH52 BOX CULVERT EXTENSION (M	SH52 BOX CULVERT EXTENSION (M	08/04/22	0.20	5000.00	4219.89	4550.00
ER0502-092	US 50 MP 204 EB MONARCH TRUCK	US 50 MP 204 EB MONARCH TRUCK	08/29/22	0.72	4000.00	5392.35	11127.06
NHPPR100-266	R1 ESSENTIAL REPAIRS	R1 ESSENTIAL REPAIRS	09/01/22	0.50	3500.00	1532.00	1696.00
2670403-065	US40 FLOYD HILL ROUNDABOUTS	US40 FLOYD HILL ROUNDABOUTS	09/15/22	0.20	6000.00	1693.93	2200.00
SHE2873-193	US 287 & CO 52 INTERSECTION I	US 287 & CO 52 INTERSECTION I	09/15/22	0.60	4000.00	2264.70	1798.00
NHPP0701-231	I-70 SALT WASH BRIDGES SCOUR	I-70 SALT WASH BRIDGES SCOUR	09/29/22	0.40	7000.00	1938.30	1600.00
	WEIGHTED AVERAGE FOR THE THIRD QUARTER			3.12	4084.02	2859.58	4051.42
STA207A-004	Resurfacing SH207A MANZANOLA	Resurfacing SH207A MANZANOLA	10/27/22	0.84	2500.00	5677.67	6033.00
C5502-111	US 550 MP 81 AND 89 RED MOUNT	US 550 MP 81 AND 89 RED MOUNT	10/27/22	0.01	4000.00	112750.00	69000.00
TRG0253-264	I-25 AND SH 119 PARK-N-RIDE	I-25 AND SH 119 PARK-N-RIDE	10/27/22	0.26	5000.00	2694.71	2900.00
STA3852-015	US 385 HOLYOKE NORTH	US 385 HOLYOKE NORTH	10/27/22	0.50	2000.00	2600.00	2600.00
SHE0242-087	US 24 SAFETY IMPRVMENTS, E OF	US 24 SAFETY IMPRVMENTS, E OF	11/03/22	0.20	4238.00	1970.00	1610.00
STR064A-010	SH 64 AND SH 13 AT MEEKER	SH 64 AND SH 13 AT MEEKER	11/10/22	0.20	3000.00	1715.00	2300.00
NHPP0853-126	US85C: PLATTEVILLE NORTH MP (US85C: PLATTEVILLE NORTH MP (11/10/22	0.70	3400.00	3904.10	1575.00
C5502-097	US550 MP 117.28-126.06	US550 MP 117.28-126.06	11/17/22	6.80	2000.00	1152.85	1020.00
MPR200-280	PUEBLO AREA	PUEBLO AREA	11/17/22	0.20	1850.00	2250.00	3500.00
STAM420-001	US 285 AT HWY 9C IMPROVEMENTS	US 285 AT HWY 9C IMPROVEMENTS	12/01/22	0.03	2961.00	36163.81	29035.00
BR2854-148	INTERSECTION OF US 285 & SH 9	INTERSECTION OF US 285 & SH 9					
STM0091-046	ADA RAMP IMPROVEMENTS - FAIRP	ADA RAMP IMPROVEMENTS - FAIRP					
STA0711-021	SH71: REGION LINE NORTH	SH71: REGION LINE NORTH	12/01/22	0.30	3400.00	6829.30	6000.00
2670703-487	I-70 BRIDGES OVER WARD ROAD-	I-70 BRIDGES OVER WARD ROAD-	12/01/22	0.20	2500.00	1282.22	1290.00
NHPP0701-252	I-70 RIFLE TO SILT SLAB REPLA	I-70 RIFLE TO SILT SLAB REPLA	12/01/22	0.05	10000.00	35377.50	39755.00
IM025A-050	I25-MP103.9 - INTERSECTION DR	I25-MP103.9 - INTERSECTION DR	12/01/22	0.10	8000.00	9277.57	2432.70
STR109A-019	M-22-AY BRIDGE REHAB ON SH109	M-22-AY BRIDGE REHAB ON SH109	12/01/22	0.13	15000.00	11044.65	13444.30
NHPP083A-046	SH83 RESURFACING STROH RD TO	SH83 RESURFACING STROH RD TO	12/08/22	0.10	5000.00	6080.70	1461.40
STA385A-016	SH 385 MP 97.76	SH 385 MP 97.76	12/22/22	0.20	2000.00	4187.50	6250.00
	WEIGHTED AVERAGE FOR THE FOURTH QUARTER			10.82	2587.47	2715.18	2495.69
	WEIGHTED AVERAGE FOR THE YEAR			21.31	4215.56	3032.41	3158.53

COLORADO DEPARTMENT OF TRANSPORTATION
 ITEM UNIT COSTS BY PROJECTS -- 2022 COST DATA

11:31 Wednesday, March 8, 2023 180

PROJECT NUMBER	ITEM NUMBER/ PROJECT LOCATION	ITEM DESCRIPTION/ PROJECT LOCATION	DATE LET	UNIT/ QUANTITY	ENGR. EST.	AVERAGE BID	AWARDED BID
===== 212-00709		Seeding (Wetland) Drill		Acre	=====		
NHPP0702-383		I-70 EB AUX FRISCO TO SILVERT	01/13/22	0.10	2500.00	9434.76	9400.00
NHPP 0761-238		I-76 DAHLIA TO YORK	03/10/22	0.05	5000.00	12028.27	15500.00
C0761-239							
		WEIGHTED AVERAGE FOR THE FIRST QUARTER		0.15	3333.33	10587.43	11433.33
NHPP0705-088		I-70 AGATE STRUCTURE REHAB	10/27/22	0.59	11000.00	3106.50	7600.00
NHPP0931-033		SH93:US6 TO 58TH RESURFACING	12/15/22	0.10	5000.00	10392.86	1230.00
		WEIGHTED AVERAGE FOR THE FOURTH QUARTER		0.69	10130.43	4162.49	6676.81
		WEIGHTED AVERAGE FOR THE YEAR		0.84	8916.67	5742.40	7526.19
===== 212-00710		Seeding (Wetland) Hydraulic		Acre	=====		
STAM420-001		US 285 AT HWY 9C IMPROVEMENTS	12/01/22	1.00	4000.00	5089.34	3535.39
BR2854-148		INTERSECTION OF US 285 & SH 9					
STM0091-046		ADA RAMP IMPROVEMENTS - FAIRP					
		WEIGHTED AVERAGE FOR THE FOURTH QUARTER		1.00	4000.00	5089.34	3535.39
		WEIGHTED AVERAGE FOR THE YEAR		1.00	4000.00	5089.34	3535.39
===== 212-00711		Seeding (Wetland) Broadcast		Acre	=====		
NH0504-910		US50B L-24-B MIN REP AT MP 40	01/13/22	0.10	9000.00	9890.78	7500.00
		WEIGHTED AVERAGE FOR THE FIRST QUARTER		0.10	9000.00	9890.78	7500.00
NHPP0702-413		VAIL PASS AUX PHASE 1 CAP 2	04/18/22	0.14	3705.41	3705.41	3705.41
		WEIGHTED AVERAGE FOR THE SECOND QUARTER		0.14	3705.41	3705.41	3705.41
NHPP0702-414		VAIL PASS AUX PHASE 1 CAP 3	07/08/22	0.62	3481.07	3481.07	3481.07

COLORADO DEPARTMENT OF TRANSPORTATION
ITEM UNIT COSTS BY PROJECTS -- 2022 COST DATA

11:31 Wednesday, March 8, 2023 181

PROJECT NUMBER	ITEM NUMBER/ PROJECT LOCATION	ITEM DESCRIPTION/ PROJECT LOCATION	DATE LET	UNIT/ QUANTITY	ENGR. EST.	AVERAGE BID	AWARDED BID
===== 212-00711 Seeding (Wetland) Broadcast Acre =====							
FBR0702-423		VAIL PASS AUX BE F-12-AT PHAS					
BR0343-046		US 34 TIMBER BRIDGE REPL. PKG	08/31/22	0.01	6322.73	6955.00	6955.00
FBR0343-047		US 6/US 34 TIMBER BRIDGE REPL					
	WEIGHTED AVERAGE FOR THE THIRD QUARTER			0.63	3526.18	3536.21	3536.21
	WEIGHTED AVERAGE FOR THE YEAR			0.87	4184.19	6789.29	4019.05
===== 212-01200 Landscape Restoration LUMP SUM =====							
NHPP2873-189		US 287 (FEDERAL BLVD) - COLFA	01/06/22	1.00	5000.00	18705.76	3384.42
	WEIGHTED AVERAGE FOR THE FIRST QUARTER			1.00	5000.00	18705.76	3384.42
CC030-081		ADA RAMP AND CURBS - FT. LUPT	04/14/22	1.00	20000.00	15878.96	5000.00
NHPP072A-047		SH-72 RESURFACING: I-70 TO IN	06/09/22	1.00	10000.00	17800.05	17800.05
	WEIGHTED AVERAGE FOR THE SECOND QUARTER			2.00	15000.00	16359.24	11400.03
NHPP0063-054		US 6 FROM I70-B TO 33 RD. (MP	08/18/22	1.00	10000.00	20410.01	5000.00
C1211-099		SH 121 NORTH SGA SIGNALS	08/25/22	1.00	30000.00	34250.00	25000.00
	WEIGHTED AVERAGE FOR THE THIRD QUARTER			2.00	20000.00	27330.00	15000.00
STAM420-001		US 285 AT HWY 9C IMPROVEMENTS	12/01/22	1.00	10000.00	19740.54	11312.17
BR2854-148		INTERSECTION OF US 285 & SH 9					
STM0091-046		ADA RAMP IMPROVEMENTS - FAIRP					
NHPP0021-041		SH2 RESURFACING MLK TO 52ND	12/01/22	1.00	8000.00	8134.04	3069.09
	WEIGHTED AVERAGE FOR THE FOURTH QUARTER			2.00	9000.00	13937.29	7190.63
	WEIGHTED AVERAGE FOR THE YEAR			7.00	13285.71	18053.92	10080.82
===== 213-00002 Mulching (Weed Free Hay) Acre =====							
NH0504-910		US50B L-24-B MIN REP AT MP 40	01/13/22	3.90	1500.00	1471.92	1000.00

COLORADO DEPARTMENT OF TRANSPORTATION
ITEM UNIT COSTS BY PROJECTS -- 2022 COST DATA

11:31 Wednesday, March 8, 2023 182

PROJECT NUMBER	ITEM NUMBER/ PROJECT LOCATION	ITEM DESCRIPTION/ PROJECT LOCATION	DATE LET	UNIT/ QUANTITY	ENGR. EST.	AVERAGE BID	AWARDED BID
===== 213-00002 Mulching (Weed Free Hay) Acre =====							
NHPP0702-383		I-70 EB AUX FRISCO TO SILVERT	01/13/22	0.20	2000.00	2937.56	5500.00
NHPP 0761-238		I-76 DAHLIA TO YORK	03/10/22	1.91	4000.00	903.77	1100.00
C0761-239							
M R100-351		FY22 R1 SIGN STRUCTURE REPLAC	03/17/22	0.10	9800.00	7702.00	8144.00
	WEIGHTED AVERAGE FOR THE FIRST QUARTER			6.11	2433.72	1346.72	1295.48
=====							
NHPP0702-413		VAIL PASS AUX PHASE 1 CAP 2	04/18/22	7.00	1926.00	1926.00	1926.00
	WEIGHTED AVERAGE FOR THE SECOND QUARTER			7.00	1926.00	1926.00	1926.00
=====							
NHPP0702-414		VAIL PASS AUX PHASE 1 CAP 3	07/08/22	3.80	1282.40	1282.40	1282.40
FBR0702-423		VAIL PASS AUX BE F-12-AT PHAS					
FBR0761-236		I-76 OVER CLR CRK SCOUR MIT	08/25/22	0.17	1500.00	4866.67	5500.00
	WEIGHTED AVERAGE FOR THE THIRD QUARTER			3.97	1291.72	1706.52	1463.00
=====							
STA207A-004		Resurfacing SH207A MANZANOLA	10/27/22	0.84	3500.00	2860.00	2780.00
NHPP0705-088		I-70 AGATE STRUCTURE REHAB	10/27/22	1.66	2900.00	1563.65	3250.00
C170A-002		CRITICAL CULVERT CONST. PKG D	10/27/22	0.49	4000.00	3068.75	3125.00
MPR200-280		PUEBLO AREA	11/17/22	0.20	2350.00	2250.00	3500.00
IM025A-050		I25-MP103.9 - INTERSECTION DR	12/01/22	5.23	1500.00	1300.00	1100.00
STR109A-019		M-22-AY BRIDGE REHAB ON SH109	12/01/22	0.13	7000.00	9366.47	10470.94
NHPP083A-046		SH83 RESURFACING STROH RD TO	12/08/22	0.10	5000.00	13546.40	10292.80
	WEIGHTED AVERAGE FOR THE FOURTH QUARTER			8.65	2247.28	1841.82	1696.92
	WEIGHTED AVERAGE FOR THE YEAR			25.73	2056.71	1649.95	1646.04
=====							
===== 213-00003 Mulching (Weed Free) Acre =====							
NHPP2873-189		US 287 (FEDERAL BLVD) - COLFA	01/06/22	0.10	1000.00	8143.33	5756.90
NHPP1601-083			02/03/22	24.00	800.00	2370.48	2500.00
NHPP0703-472			03/10/22	0.50	602.00	3502.96	3100.00
	WEIGHTED AVERAGE FOR THE FIRST QUARTER			24.60	796.79	2461.24	2525.43
=====							
CC030-081		ADA RAMP AND CURBS - FT. LUPT	04/14/22	0.12	9000.00	11053.14	7500.00

COLORADO DEPARTMENT OF TRANSPORTATION
ITEM UNIT COSTS BY PROJECTS -- 2022 COST DATA

11:31 Wednesday, March 8, 2023 183

PROJECT NUMBER	ITEM NUMBER/ PROJECT LOCATION	ITEM DESCRIPTION/ PROJECT LOCATION	DATE LET	UNIT/ QUANTITY	ENGR. EST.	AVERAGE BID	AWARDED BID
===== 213-00003 Mulching (Weed Free) Acre =====							
2670703-479		I-70 BRIDGE OVER HARIAN	05/05/22	1.20	750.00	1048.65	1159.13
C0852-120		Rehabilitation of Culvert by	05/26/22	0.10	5000.00	9400.00	9400.00
ITS 0741-024		VMS SIGN INSTALLATIONS AND VS	06/02/22	0.90	5000.00	1716.00	1600.00
WEIGHTED AVERAGE FOR THE SECOND QUARTER				2.32	3008.62	1644.63	2013.34
ER0502-092		US 50 MP 204 EB MONARCH TRUCK	08/29/22	0.49	5000.00	3808.90	4526.69
BR0343-046		US 34 TIMBER BRIDGE REPL. PKG	08/31/22	5.25	668.75	668.75	668.75
FBR0343-047		US 6/US 34 TIMBER BRIDGE REPL					
NHPPR100-266		R1 ESSENTIAL REPAIRS	09/01/22	3.00	1500.00	1785.67	1007.00
ER0253-297		WCR 34 BRIDGE OVER I-25(MM 24	09/14/22	0.50	5000.00	2753.28	882.00
NHPP0701-231		I-70 SALT WASH BRIDGES SCOUR	09/29/22	4.40	1000.00	1661.40	1500.00
WEIGHTED AVERAGE FOR THE THIRD QUARTER				13.64	1272.80	1708.44	1157.70
C5502-111		US 550 MP 81 AND 89 RED MOUNT	10/27/22	0.01	15000.00	88600.00	52000.00
STU0252-457		I-25:ALAMEDA RIVER PH 2.0	11/03/22	5.00	2500.00	1192.92	850.00
SHE0242-087		US 24 SAFETY IMPRVMENTS, E OF	11/03/22	0.20	736.00	5651.33	9554.00
STRC090-011		US 50B AND SH71/CR18 INTERSEC	11/17/22	0.60	600.00	1968.50	2050.00
STAM420-001		US 285 AT HWY 9C IMPROVEMENTS	12/01/22	0.03	662.40	28422.98	35158.00
BR2854-148		INTERSECTION OF US 285 & SH 9					
STM0091-046		ADA RAMP IMPROVEMENTS - FAIRP					
2670703-487		I-70 BRIDGES OVER WARD ROAD-	12/01/22	2.50	1300.00	1013.88	1110.00
NHPP0021-041		SH2 RESURFACING MLK TO 52ND	12/01/22	0.10	8000.00	14492.37	17677.80
NHPP0063-048		US6 / 20 ROAD INTERSECTION IM	12/15/22	0.94	2600.00	3131.86	2700.00
NHPP0502-090		SH 50 MP 134.6-136 GUNNISON C	12/22/22	2.10	1000.00	1699.70	1625.22
STA385A-016		SH 385 MP 97.76	12/22/22	3.20	1000.00	1896.88	2187.50
WEIGHTED AVERAGE FOR THE FOURTH QUARTER				14.68	1701.03	1778.60	1802.40
WEIGHTED AVERAGE FOR THE YEAR				55.24	1247.52	1996.89	1974.06
===== 213-00004 Mulching (Weed Free Straw) Acre =====							
BRC040-057			03/17/22	0.08	1500.00	13160.81	7439.00
STR R500-171		Various locations on SH 141 a	03/17/22	0.10	3300.00	4775.99	5000.00
WEIGHTED AVERAGE FOR THE FIRST QUARTER				0.18	2500.00	9103.64	6084.00
STA0712-019		SH 71: Frieght Improvements	05/12/22	8.40	1100.00	744.16	744.16
WEIGHTED AVERAGE FOR THE SECOND QUARTER				8.40	1100.00	744.16	744.16

COLORADO DEPARTMENT OF TRANSPORTATION
 ITEM UNIT COSTS BY PROJECTS -- 2022 COST DATA

11:31 Wednesday, March 8, 2023 184

PROJECT NUMBER	ITEM NUMBER/ PROJECT LOCATION	ITEM DESCRIPTION/ PROJECT LOCATION	DATE LET	UNIT/ QUANTITY	ENGR. EST.	AVERAGE BID	AWARDED BID
=====	213-00004	Mulching (Weed Free Straw)		Acre	=====		
2670703-497		I-70_GENESEE WILDLIFE KING	09/15/22	2.49	1900.00	1991.02	1647.03
		WEIGHTED AVERAGE FOR THE THIRD QUARTER		2.49	1900.00	1991.02	1647.03
TRG0253-264		I-25 AND SH 119 PARK-N-RIDE	10/27/22	8.92	2000.00	1022.02	950.00
STA3852-015		US 385 HOLYOKE NORTH	10/27/22	53.10	1000.00	875.00	875.00
C5502-097		US550 MP 117.28-126.06	11/17/22	43.20	900.00	1498.91	1530.00
NHPP0931-033		SH93:US6 TO 58TH RESURFACING	12/15/22	0.40	2000.00	1946.73	1640.00
STA0361-129		US 36: HYGIENE RD AND NELSON	12/22/22	0.46	2500.00	3939.49	2149.96
BR012A-048		CO 12 STRUCTURE P-17-F AT MP	12/22/22	1.00	5000.00	5856.81	3000.00
		WEIGHTED AVERAGE FOR THE FOURTH QUARTER		107.08	1090.49	1298.44	1173.68
		WEIGHTED AVERAGE FOR THE YEAR		118.15	1110.38	1341.23	1160.60
=====	213-00006	Mulching (Weed Free)		Ton	=====		
NHPP0063-063			02/24/22	250.00	10.00	105.50	132.00
		WEIGHTED AVERAGE FOR THE FIRST QUARTER		250.00	10.00	105.50	132.00
		WEIGHTED AVERAGE FOR THE YEAR		250.00	10.00	105.50	132.00
=====	213-00007	Mulching (Wood Strand)		Acre	=====		
ER0702-420		PR I-70 GWC MATERIAL FLOWS 20	05/06/22	2.00	5000.00	15000.00	15000.00
		WEIGHTED AVERAGE FOR THE SECOND QUARTER		2.00	5000.00	15000.00	15000.00
NHPP0702-414		VAIL PASS AUX PHASE 1 CAP 3	07/08/22	0.54	21849.14	21849.14	21849.14
FBR0702-423		VAIL PASS AUX BE F-12-AT PHAS					
		WEIGHTED AVERAGE FOR THE THIRD QUARTER		0.54	21849.14	21849.14	21849.14
		WEIGHTED AVERAGE FOR THE YEAR		2.54	8582.10	15814.66	16456.12

COLORADO DEPARTMENT OF TRANSPORTATION
ITEM UNIT COSTS BY PROJECTS -- 2022 COST DATA

11:31 Wednesday, March 8, 2023 185

PROJECT NUMBER	ITEM NUMBER/ PROJECT LOCATION	ITEM DESCRIPTION/ PROJECT LOCATION	DATE LET	UNIT/ QUANTITY	ENGR. EST.	AVERAGE BID	AWARDED BID
===== 213-00008 Mulching (Wood Chip) Cubic Foot =====							
STU0252-457	I-25:ALAMEDA RIVER PH 2.0		11/03/22	245.00	2.50	10.07	9.00
	WEIGHTED AVERAGE FOR THE FOURTH QUARTER			245.00	2.50	10.07	9.00
	WEIGHTED AVERAGE FOR THE YEAR			245.00	2.50	10.07	9.00
===== 213-00011 Mulching (Hydraulic) Acre =====							
2670403-065	US40_FLOYD HILL ROUNDABOUTS		09/15/22	1.55	1600.00	3086.97	3300.00
2670703-497	I-70_GENESEE WILDLIFE KING		09/15/22	0.75	1600.00	3086.38	2896.50
	WEIGHTED AVERAGE FOR THE THIRD QUARTER			2.30	1600.00	3086.65	3168.42
	WEIGHTED AVERAGE FOR THE YEAR			2.30	1600.00	3086.65	3168.42
===== 213-00012 Spray-on Mulch Blanket Acre =====							
NHPP0702-383	I-70 EB AUX FRISCO TO SILVERT		01/13/22	6.00	2000.00	4217.83	2600.00
C0762-055			02/17/22	3.00	3500.00	3768.58	2900.00
STA 067A-048	Hwy 67A MP 0.00 TO MP 11.05 I		03/03/22	0.65	4500.00	6483.33	7000.00
NHPP 0761-238	I-76 DAHLIA TO YORK		03/10/22	0.29	4000.00	5475.05	5500.00
C0761-239							
STR092A-031			03/17/22	0.50	4700.00	4835.00	4835.00
	WEIGHTED AVERAGE FOR THE FIRST QUARTER			10.44	2771.55	4265.98	3147.75
NHPP0702-413	VAIL PASS AUX PHASE 1 CAP 2		04/18/22	3.00	5605.73	5605.73	5605.73
STM1151-038	SH115 MP 27 TO MP 38		04/21/22	51.60	4090.00	3799.39	3100.00
ER0702-420	PR I-70 GWC MATERIAL FLOWS 20		05/06/22	1.50	4000.00	7850.00	7700.00
FSA0702-409	I-70 VAIL WILDLIFE FENCE PHAS		05/26/22	0.75	17000.00	17500.00	17500.00
FSA052A-046	SH52 WCR 37 INTERSECTION IMPR		06/09/22	4.91	3768.00	4216.40	4000.00
MTCE0253-291	I-25 SIGN REPLACEMENT PHASE 2		06/16/22	0.10	1200.00	11012.80	3275.60
	WEIGHTED AVERAGE FOR THE SECOND QUARTER			61.86	4287.62	3935.93	3579.37
NHPP0702-414	VAIL PASS AUX PHASE 1 CAP 3		07/08/22	6.00	5042.27	5042.27	5042.27

COLORADO DEPARTMENT OF TRANSPORTATION
ITEM UNIT COSTS BY PROJECTS -- 2022 COST DATA

11:31 Wednesday, March 8, 2023 186

PROJECT NUMBER	ITEM NUMBER/ PROJECT LOCATION	ITEM DESCRIPTION/ PROJECT LOCATION	DATE LET	UNIT/ QUANTITY	ENGR. EST.	AVERAGE BID	AWARDED BID
===== 213-00012 Spray-on Mulch Blanket Acre =====							
FBR0702-423		VAIL PASS AUX BE F-12-AT PHAS					
NHPP0063-054		US 6 FROM I70-B TO 33 RD. (MP	08/18/22	1.00	4000.00	12922.64	18445.00
BR0343-046		US 34 TIMBER BRIDGE REPL. PKG	08/31/22	0.09	6955.00	6955.00	6955.00
FBR0343-047		US 6/US 34 TIMBER BRIDGE REPL					
2670403-065		US40 FLOYD HILL ROUNDABOUTS	09/15/22	0.20	7000.00	6566.90	7900.00
SHE2873-193		US 287 & CO 52 INTERSECTION I	09/15/22	5.80	3500.00	3941.53	4272.00
NHPP0701-231		I-70 SALT WASH BRIDGES SCOUR	09/29/22	0.60	6000.00	5827.11	4000.00
		WEIGHTED AVERAGE FOR THE THIRD QUARTER		13.69	4395.88	4583.19	5703.59
=====							
NHPP0701-253		I-70 EAST OF DEBEQUE	10/27/22	0.73	3000.00	7175.00	7500.00
FSAM240-200		SH21B CO SPRINGS SIGNAL REPLA	10/27/22	0.50	6000.00	8541.50	7950.00
TRG0253-264		I-25 AND SH 119 PARK-N-RIDE	10/27/22	10.00	3250.00	3770.13	3700.00
STU0252-457		I-25:ALAMEDA RIVER PH 2.0	11/03/22	10.00	3500.00	4151.89	4400.00
C5502-097		US550 MP 117.28-126.06	11/17/22	0.05	7000.00	7183.41	9890.00
STAM420-001		US 285 AT HWY 9C IMPROVEMENTS	12/01/22	2.07	4070.00	5015.71	6104.95
BR2854-148		INTERSECTION OF US 285 & SH 9					
STM0091-046		ADA RAMP IMPROVEMENTS - FAIRP					
STR114A-015		SH114 SILLSVILLE SOUTH TO MP3	12/01/22	0.50	5000.00	12750.00	16000.00
2670703-487		I-70 BRIDGES OVER WARD ROAD-	12/01/22	0.50	5000.00	4598.58	4640.00
NHPP0063-048		US6 / 20 ROAD INTERSECTION IM	12/15/22	1.70	5000.00	5634.81	4400.00
NHPP0931-033		SH93:US6 TO 58TH RESURFACING	12/15/22	1.50	5000.00	4143.07	3691.00
NHPP0502-090		SH 50 MP 134.6-136 GUNNISON C	12/22/22	4.60	5000.00	5520.91	5412.19
STA0361-129		US 36: HYGIENE RD AND NELSON	12/22/22	0.07	20000.00	15349.79	9228.45
BR012A-048		CO 12 STRUCTURE P-17-F AT MP	12/22/22	1.30	5000.00	3869.88	3000.00
STR096A-050		SH 96 MP 168.99 TO 193.77	12/22/22	0.50	5400.00	5010.67	5600.00
		WEIGHTED AVERAGE FOR THE FOURTH QUARTER		34.02	3999.56	4429.40	4678.43
		WEIGHTED AVERAGE FOR THE YEAR		120.01	4086.42	4166.63	4095.70
=====							
===== 213-00016 Mulching Pelletized Matl (Waterless Appl) Acre =====							
NHPP 3851-018		US 385 NORTH OF CHEYENNE WELL	05/26/22	4.45	5400.00	6650.00	8000.00
		WEIGHTED AVERAGE FOR THE SECOND QUARTER		4.45	5400.00	6650.00	8000.00
		WEIGHTED AVERAGE FOR THE YEAR		4.45	5400.00	6650.00	8000.00
=====							
===== 213-00061 Mulch Tackifier Pound =====							
NHPP2873-189		US 287 (FEDERAL BLVD) - COLFA	01/06/22	40.00	3.20	16.44	16.38

COLORADO DEPARTMENT OF TRANSPORTATION
 ITEM UNIT COSTS BY PROJECTS -- 2022 COST DATA

11:31 Wednesday, March 8, 2023 187

PROJECT NUMBER	ITEM NUMBER/ PROJECT LOCATION	ITEM DESCRIPTION/ PROJECT LOCATION	DATE LET	UNIT/ QUANTITY	ENGR. EST.	AVERAGE BID	AWARDED BID
===== 213-00061							
		Mulch Tackifier		Pound			
NHPP0702-383		I-70 EB AUX FRISCO TO SILVERT	01/13/22	80.00	5.00	4.68	5.00
NHPP1601-083			02/03/22	4,600.00	6.00	4.49	4.00
NHPP 0761-238		I-76 DAHLIA TO YORK	03/10/22	230.00	5.00	3.66	3.50
C0761-239							
NHPP0703-472			03/10/22	125.00	3.00	11.42	5.00
BRC040-057			03/17/22	10.00	5.00	48.01	28.05
STR R500-171		Various locations on SH 141 a	03/17/22	300.00	12.00	10.52	2.00
M R100-351		FY22 R1 SIGN STRUCTURE REPLAC	03/17/22	20.00	35.00	34.00	38.00
WEIGHTED AVERAGE FOR THE FIRST QUARTER				5,405.00	6.29	5.43	4.17
CC030-081		ADA RAMP AND CURBS - FT. LUPT	04/14/22	24.00	65.00	47.21	50.00
NHPP0702-413		VAIL PASS AUX PHASE 1 CAP 2	04/18/22	1,400.00	4.28	4.28	4.28
2670703-479		I-70 BRIDGE OVER HARLAN	05/05/22	240.00	3.00	4.17	5.05
STA0712-019		SH 71: Frieight Improvements	05/12/22	1,676.00	4.00	3.91	3.91
CM760-047		COLFAX AND QUAIL	05/12/22	3.00	6.00	149.80	135.00
C0852-120		Rehabilitation of Culvert by	05/26/22	20.00	50.00	47.00	47.00
ITS 0741-024		VMS SIGN INSTALLATIONS AND VS	06/02/22	180.00	15.00	3.75	3.50
WEIGHTED AVERAGE FOR THE SECOND QUARTER				3,543.00	5.28	5.32	4.78
NHPP0702-414		VAIL PASS AUX PHASE 1 CAP 3	07/08/22	700.00	5.68	5.68	5.68
FBR0702-423		VAIL PASS AUX BE F-12-AT PHAS					
FBR0761-236		I-76 OVER CLR CRK SCOUR MIT	08/25/22	34.00	5.00	4.00	5.00
ER0502-092		US 50 MP 204 EB MONARCH TRUCK	08/29/22	98.00	5.00	8.88	10.38
BR0343-046		US 34 TIMBER BRIDGE REPL. PKG	08/31/22	1,050.00	3.16	3.16	3.16
FBR0343-047		US 6/US 34 TIMBER BRIDGE REPL					
NHPPR100-266		R1 ESSENTIAL REPAIRS	09/01/22	1,000.00	5.00	3.23	2.93
ER0253-297		WCR 34 BRIDGE OVER I-25(MM 24	09/14/22	100.00	20.00	6.79	4.70
2670403-065		US40 FLOYD HILL ROUNDABOUTS	09/15/22	100.00	25.00	5.76	10.00
2670703-497		I-70 GENESEE WILDLIFE KING	09/15/22	490.00	3.60	3.57	3.41
NHPP0701-231		I-70 SALT WASH BRIDGES SCOUR	09/29/22	878.00	4.00	5.29	6.00
WEIGHTED AVERAGE FOR THE THIRD QUARTER				4,450.00	5.11	4.17	4.45
STA207A-004		Resurfacing SH207A MANZANOLA	10/27/22	168.00	15.00	9.67	10.00
TRG0253-264		I-25 AND SH 119 PARK-N-RIDE	10/27/22	1,784.00	2.50	3.37	4.00
STA3852-015		US 385 HOLYOKE NORTH	10/27/22	10,624.00	4.00	4.00	4.00
STU0252-457		I-25:ALAMEDA RIVER PH 2.0	11/03/22	722.00	2.20	3.77	3.30

PROJECT NUMBER	ITEM NUMBER/ PROJECT LOCATION	ITEM DESCRIPTION/ PROJECT LOCATION	DATE LET	UNIT/ QUANTITY	ENGR. EST.	AVERAGE BID	AWARDED BID
===== 213-00061 Mulch Tackifier Pound =====							
SHE0242-087		US 24 SAFETY IMPRVMENTS, E OF	11/03/22	600.00	3.00	4.61	3.84
C5502-097		US550 MP 117.28-126.06	11/17/22	8,640.00	4.00	4.08	4.20
MPR200-280		PUEBLO AREA	11/17/22	40.00	11.00	27.50	45.00
STRC090-011		US 50B AND SH71/CR18 INTERSEC	11/17/22	120.00	5.00	7.05	3.10
STAM420-001		US 285 AT HWY 9C IMPROVEMENTS	12/01/22	65.00	2.30	10.83	5.20
BR2854-148		INTERSECTION OF US 285 & SH 9					
STM0091-046		ADA RAMP IMPROVEMENTS - FAIRP					
2670703-487		I-70 BRIDGES OVER WARD ROAD-	12/01/22	250.00	5.00	5.02	5.10
IM025A-050		I25-MP103.9 - INTERSECTION DR	12/01/22	1,046.00	5.00	3.63	3.40
STR109A-019		M-22-AY BRIDGE REHAB ON SH109	12/01/22	28.00	15.00	27.84	38.68
NHPP0021-041		SH2 RESURFACING MLK TO 52ND	12/01/22	40.00	20.00	8.89	4.70
NHPP083A-046		SH83 RESURFACING STROH RD TO	12/08/22	20.00	15.00	17.69	28.17
NHPP0063-048		US6 / 20 ROAD INTERSECTION IM	12/15/22	188.00	4.00	4.97	4.00
NHPP0931-033		SH93:US6 TO 58TH RESURFACING	12/15/22	400.00	3.00	3.03	2.55
NHPP0502-090		SH 50 MP 134.6-136 GUNNISON C	12/22/22	420.00	5.00	4.93	4.24
STA385A-016		SH 385 MP 97.76	12/22/22	640.00	5.00	5.22	3.38
	WEIGHTED AVERAGE FOR THE FOURTH QUARTER			25,795.00	4.03	4.20	4.22
	WEIGHTED AVERAGE FOR THE YEAR			39,193.00	4.57	4.40	4.29
===== 213-00066 Mulch (Paper Base) Acre =====							
C0762-055			02/17/22	2.00	2000.00	2038.78	1600.00
	WEIGHTED AVERAGE FOR THE FIRST QUARTER			2.00	2000.00	2038.78	1600.00
	WEIGHTED AVERAGE FOR THE YEAR			2.00	2000.00	2038.78	1600.00
===== 213-00067 Rock Mulch (Weed Free) Sq Foot =====							
NHPP0063-063			02/24/22	16,034.00	3.00	3.53	3.35
	WEIGHTED AVERAGE FOR THE FIRST QUARTER			16,034.00	3.00	3.53	3.35
NHPP0063-054		US 6 FROM I70-B TO 33 RD. (MP	08/18/22	12,099.00	4.00	4.18	2.75
	WEIGHTED AVERAGE FOR THE THIRD QUARTER			12,099.00	4.00	4.18	2.75
STU0252-457		I-25:ALAMEDA RIVER PH 2.0	11/03/22	848.00	20.00	7.32	11.00
	WEIGHTED AVERAGE FOR THE FOURTH QUARTER			848.00	20.00	7.32	11.00
	WEIGHTED AVERAGE FOR THE YEAR			28,981.00	3.91	3.96	3.32

COLORADO DEPARTMENT OF TRANSPORTATION
 ITEM UNIT COSTS BY PROJECTS -- 2022 COST DATA

11:31 Wednesday, March 8, 2023 189

PROJECT NUMBER	ITEM NUMBER/ PROJECT LOCATION	ITEM DESCRIPTION/ PROJECT LOCATION	DATE LET	UNIT/ QUANTITY	ENGR. EST.	AVERAGE BID	AWARDED BID
===== 213-00070 Landscape Weed Barr Fabric Sq Yard =====							
NHPP0063-063			02/24/22	1,782.00	2.00	5.40	7.65
		WEIGHTED AVERAGE FOR THE FIRST QUARTER		1,782.00	2.00	5.40	7.65
		WEIGHTED AVERAGE FOR THE YEAR		1,782.00	2.00	5.40	7.65
===== 213-00071 Vegetation Control Mat Sq Yard =====							
NHPPR100-266		R1 ESSENTIAL REPAIRS	09/01/22	67.00	50.00	86.01	133.03
		WEIGHTED AVERAGE FOR THE THIRD QUARTER		67.00	50.00	86.01	133.03
		WEIGHTED AVERAGE FOR THE YEAR		67.00	50.00	86.01	133.03
===== 213-00150 Bonded Fiber Matrix Acre =====							
NH0504-910		US50B L-24-B MIN REP AT MP 40	01/13/22	1.00	6500.00	4356.87	5250.00
NHPP0702-383		I-70 EB AUX FRISCO TO SILVERT	01/13/22	20.00	3000.00	3797.97	2900.00
NHM765-007			03/31/22	0.10	10000.00	14054.97	11142.65
		WEIGHTED AVERAGE FOR THE FIRST QUARTER		21.10	3199.05	3867.67	3050.44
NH0504-911			04/07/22	3.00	3000.00	3890.00	3980.00
NHPP0702-413		VAIL PASS AUX PHASE 1 CAP 2	04/18/22	20.00	4896.32	4896.32	4896.32
STM1151-038		SH115 MP 27 TO MP 38	04/21/22	10.00	2956.00	3880.38	2700.00
STA0712-019		SH 71: Frieight Improvements	05/12/22	0.20	3000.00	6069.40	6069.40
NHC540-017		R2 CHAINUP STA @ KENOSHA/HOOS	05/12/22	3.10	3400.00	6616.67	5350.00
FSA052A-046		SH52 WCR 37 INTERSECTION IMPR	06/09/22	3.00	3000.00	3838.00	3675.00
		WEIGHTED AVERAGE FOR THE SECOND QUARTER		39.30	3985.40	4334.37	4216.04
NHPP0702-414		VAIL PASS AUX PHASE 1 CAP 3	07/08/22	20.00	4545.68	4545.68	4545.68
FBR0702-423		VAIL PASS AUX BE F-12-AT PHAS					
SHE2873-193		US 287 & CO 52 INTERSECTION I	09/15/22	4.50	3500.00	3784.15	3996.00
		WEIGHTED AVERAGE FOR THE THIRD QUARTER		24.50	4353.62	4108.21	4444.72

PROJECT NUMBER	ITEM NUMBER/ PROJECT LOCATION	ITEM DESCRIPTION/ PROJECT LOCATION	DATE LET	UNIT/ QUANTITY	ENGR. EST.	AVERAGE BID	AWARDED BID
=====	213-00150	Bonded Fiber Matrix		Acre	=====		
STA3852-015		US 385 HOLYOKE NORTH	10/27/22	18.00	4200.00	3800.00	3800.00
SHE0242-087		US 24 SAFETY IMPRVMENTS, E OF	11/03/22	0.14	3100.00	8347.67	7543.00
NHPP0853-126		US85C: PLATTEVILLE NORTH MP (11/10/22	0.50	5000.00	7913.00	4250.00
C5502-097		US550 MP 117.28-126.06	11/17/22	12.50	5000.00	6021.71	6470.00
IM025A-050		I25-MP103.9 - INTERSECTION DR	12/01/22	1.40	3500.00	5266.67	4300.00
NHPP0063-048		US6 / 20 ROAD INTERSECTION IM	12/15/22	2.00	3800.00	5438.76	4700.00
NHPP0502-090		SH 50 MP 134.6-136 GUNNISON C	12/22/22	9.00	5000.00	5235.00	4068.76
BR012A-048		CO 12 STRUCTURE P-17-F AT MP	12/22/22	0.50	5000.00	4471.00	4000.00
STA385A-016		SH 385 MP 97.76	12/22/22	0.60	5000.00	6075.00	4500.00
		WEIGHTED AVERAGE FOR THE FOURTH QUARTER		44.64	4570.65	5358.42	4686.26
		WEIGHTED AVERAGE FOR THE YEAR		129.54	4128.64	4496.34	4231.47
=====	213-00151	Bonded Fiber Matrix		Pound	=====		
NHC540-017		R2 CHAINUP STA @ KENOSHA/HOOS	05/12/22	6,000.00	1.75	2.33	1.80
		WEIGHTED AVERAGE FOR THE SECOND QUARTER		6,000.00	1.75	2.33	1.80
		WEIGHTED AVERAGE FOR THE YEAR		6,000.00	1.75	2.71	1.85
=====	213-00300	Conc Landscape Border		Lin Foot	=====		
NHPP0253-275		I-25 EXPRESS LANES SEGMENT 5	03/11/22	3,902.00	39.29	48.17	48.17
		WEIGHTED AVERAGE FOR THE FIRST QUARTER		3,902.00	39.29	48.17	48.17
		WEIGHTED AVERAGE FOR THE YEAR		3,902.00	39.29	48.17	48.17
=====	213-00610	Landscape Log		Each	=====		
NHPP0702-413		VAIL PASS AUX PHASE 1 CAP 2	04/18/22	24.00	531.79	531.79	531.79
		WEIGHTED AVERAGE FOR THE SECOND QUARTER		24.00	531.79	531.79	531.79
NHPP0702-414		VAIL PASS AUX PHASE 1 CAP 3	07/08/22	12.00	546.57	546.57	546.57

COLORADO DEPARTMENT OF TRANSPORTATION
ITEM UNIT COSTS BY PROJECTS -- 2022 COST DATA

11:31 Wednesday, March 8, 2023 191

PROJECT NUMBER	ITEM NUMBER/ PROJECT LOCATION	ITEM DESCRIPTION/ PROJECT LOCATION	DATE LET	UNIT/ QUANTITY	ENGR. EST.	AVERAGE BID	AWARDED BID
=====	213-00610	Landscape Log		Each	=====	=====	=====
FBR0702-423		VAIL PASS AUX BE F-12-AT PHAS					
		WEIGHTED AVERAGE FOR THE THIRD QUARTER		12.00	546.57	546.57	546.57
		WEIGHTED AVERAGE FOR THE YEAR		36.00	536.72	536.72	536.72
=====	213-00700	Landscape Boulder		Each	=====	=====	=====
NHPP0702-383		I-70 EB AUX FRISCO TO SILVERT	01/13/22	48.00	500.00	630.90	550.00
NHPP 0761-238		I-76 DAHLIA TO YORK	03/10/22	180.00	300.00	299.15	195.00
C0761-239							
		WEIGHTED AVERAGE FOR THE FIRST QUARTER		228.00	342.11	346.54	269.74
NHPP0702-413		VAIL PASS AUX PHASE 1 CAP 2	04/18/22	48.00	531.79	531.79	531.79
NHC540-017		R2 CHAINUP STA @ KENOSHA/HOOS	05/12/22	224.00	23.00	1150.00	650.00
		WEIGHTED AVERAGE FOR THE SECOND QUARTER		272.00	112.79	1108.79	629.14
NHPP0702-414		VAIL PASS AUX PHASE 1 CAP 3	07/08/22	133.00	494.62	494.62	494.62
FBR0702-423		VAIL PASS AUX BE F-12-AT PHAS					
NHPP0063-054		US 6 FROM I70-B TO 33 RD. (MP	08/18/22	20.00	600.00	686.95	875.00
		WEIGHTED AVERAGE FOR THE THIRD QUARTER		153.00	508.40	539.09	544.34
		WEIGHTED AVERAGE FOR THE YEAR		653.00	285.55	572.79	483.78
=====	213-00705	Landscape Boulder (Special)		Each	=====	=====	=====
IM025A-050		I25-MP103.9 - INTERSECTION DR	12/01/22	130.00	400.00	451.67	130.00
		WEIGHTED AVERAGE FOR THE FOURTH QUARTER		130.00	400.00	451.67	130.00
		WEIGHTED AVERAGE FOR THE YEAR		130.00	400.00	451.67	130.00
=====	213-00800	Brush Fill		Cubic Yard	=====	=====	=====
NHPP0702-414		VAIL PASS AUX PHASE 1 CAP 3	07/08/22	30.00	56.21	56.21	56.21

COLORADO DEPARTMENT OF TRANSPORTATION
ITEM UNIT COSTS BY PROJECTS -- 2022 COST DATA

11:31 Wednesday, March 8, 2023 192

PROJECT NUMBER	ITEM NUMBER/ PROJECT LOCATION	ITEM DESCRIPTION/ PROJECT LOCATION	DATE LET	UNIT/ QUANTITY	ENGR. EST.	AVERAGE BID	AWARDED BID
=====	213-00800	Brush Fill		Cubic Yard	=====		
FBR0702-423		VAIL PASS AUX BE F-12-AT PHAS					
		WEIGHTED AVERAGE FOR THE THIRD QUARTER		30.00	56.21	56.21	56.21
		WEIGHTED AVERAGE FOR THE YEAR		30.00	56.21	56.21	56.21
=====	214-00000	Landscape Maintenance		LUMP SUM	=====		
NHPP0253-275		I-25 EXPRESS LANES SEGMENT 5	03/11/22	1.00	31080.00	36920.98	36920.98
		WEIGHTED AVERAGE FOR THE FIRST QUARTER		1.00	31080.00	36920.98	36920.98
2670703-479		I-70 BRIDGE OVER HARLAN	05/05/22	1.00	4500.00	13487.17	10245.22
		WEIGHTED AVERAGE FOR THE SECOND QUARTER		1.00	4500.00	13487.17	10245.22
		WEIGHTED AVERAGE FOR THE YEAR		2.00	17790.00	16834.86	23583.10
=====	214-00008	Extended Landscape Preservation		LUMP SUM	=====		
FBR0761-236		I-76 OVER CLR CRK SCOUR MIT	08/25/22	1.00	15000.00	22833.33	38000.00
NHPPR100-266		R1 ESSENTIAL REPAIRS	09/01/22	1.00	50000.00	143666.93	170320.80
2670403-065		US40_FLOYD HILL ROUNDABOUTS	09/15/22	1.00	10000.00	90539.33	62000.00
2670703-497		I-70_GENESEE WILDLIFE XING	09/15/22	1.00	5000.00	24071.45	21581.86
		WEIGHTED AVERAGE FOR THE THIRD QUARTER		4.00	20000.00	58726.18	72975.67
STU0252-457		I-25:ALAMEDA RIVER PH 2.0	11/03/22	1.00	25000.00	36777.54	40000.00
2670703-487		I-70 BRIDGES OVER WARD ROAD-	12/01/22	1.00	15000.00	24600.96	24800.00
NHPP0931-033		SH93:US6 TO 58TH RESURFACING	12/15/22	1.00	10000.00	27996.73	16900.00
		WEIGHTED AVERAGE FOR THE FOURTH QUARTER		3.00	16666.67	28777.03	27233.33
		WEIGHTED AVERAGE FOR THE YEAR		7.00	18571.43	45890.83	53371.81
=====	214-00205	Deciduous Tree (5 Gal)		Each	=====		
STM1151-038		SH115 MP 27 TO MP 38	04/21/22	10.00	500.00	169.14	7.00
		WEIGHTED AVERAGE FOR THE SECOND QUARTER		10.00	500.00	169.14	7.00

COLORADO DEPARTMENT OF TRANSPORTATION
ITEM UNIT COSTS BY PROJECTS -- 2022 COST DATA

11:31 Wednesday, March 8, 2023 193

PROJECT NUMBER	ITEM NUMBER/ PROJECT LOCATION	ITEM DESCRIPTION/ PROJECT LOCATION	DATE LET	UNIT/ QUANTITY	ENGR. EST.	AVERAGE BID	AWARDED BID
===== 214-00205		Deciduous Tree (5 Gal)		Each	=====	=====	=====
NHPPR100-266		R1 ESSENTIAL REPAIRS	09/01/22	28.00	25.00	92.17	54.80
		WEIGHTED AVERAGE FOR THE THIRD QUARTER		28.00	25.00	92.17	54.80
		WEIGHTED AVERAGE FOR THE YEAR		38.00	150.00	120.89	42.22
===== 214-00215		Deciduous Tree (1.5 In C)		Each	=====	=====	=====
BR012A-048		CO 12 STRUCTURE P-17-F AT MP	12/22/22	60.00	500.00	441.68	250.00
		WEIGHTED AVERAGE FOR THE FOURTH QUARTER		60.00	500.00	441.68	250.00
		WEIGHTED AVERAGE FOR THE YEAR		60.00	500.00	441.68	250.00
===== 214-00220		Deciduous Tree (2 In C)		Each	=====	=====	=====
NHPP0253-275		I-25 EXPRESS LANES SEGMENT 5	03/11/22	8.00	665.00	798.43	798.43
		WEIGHTED AVERAGE FOR THE FIRST QUARTER		8.00	665.00	798.43	798.43
2670703-479		I-70 BRIDGE OVER HARLAN	05/05/22	4.00	650.00	821.09	987.13
		WEIGHTED AVERAGE FOR THE SECOND QUARTER		4.00	650.00	821.09	987.13
		WEIGHTED AVERAGE FOR THE YEAR		12.00	660.00	815.43	861.33
===== 214-00222		Decid Tree (2 In Cal) (Furnish)		Each	=====	=====	=====
2670703-479		I-70 BRIDGE OVER HARLAN	05/05/22	5.00	250.00	613.11	719.16
		WEIGHTED AVERAGE FOR THE SECOND QUARTER		5.00	250.00	613.11	719.16
2670403-065		US40_FLOYD HILL ROUNDABOUTS	09/15/22	24.00	500.00	539.17	565.00
		WEIGHTED AVERAGE FOR THE THIRD QUARTER		24.00	500.00	539.17	565.00
		WEIGHTED AVERAGE FOR THE YEAR		29.00	456.90	560.92	591.58

COLORADO DEPARTMENT OF TRANSPORTATION
ITEM UNIT COSTS BY PROJECTS -- 2022 COST DATA

11:31 Wednesday, March 8, 2023 194

PROJECT NUMBER	ITEM NUMBER/ PROJECT LOCATION	ITEM DESCRIPTION/ PROJECT LOCATION	DATE LET	UNIT/ QUANTITY	ENGR. EST.	AVERAGE BID	AWARDED BID
=====	214-00227	Furn Deciduous Tree (2.5 In C)		Each	=====	=====	=====
STU0252-457		I-25:ALAMEDA RIVER PH 2.0	11/03/22	9.00	1000.00	565.45	380.00
	WEIGHTED	AVERAGE FOR THE FOURTH QUARTER		9.00	1000.00	565.45	380.00
		WEIGHTED AVERAGE FOR THE YEAR		9.00	1000.00	565.45	380.00
=====	214-00310	Deciduous Shrub (1 Gal)		Each	=====	=====	=====
NHPPR100-266		R1 ESSENTIAL REPAIRS	09/01/22	30.00	15.00	48.14	39.33
	WEIGHTED	AVERAGE FOR THE THIRD QUARTER		30.00	15.00	48.14	39.33
		WEIGHTED AVERAGE FOR THE YEAR		30.00	15.00	48.14	39.33
=====	214-00506	Evergreen Tree (6 Ft) (B-B)		Each	=====	=====	=====
2670703-479		I-70 BRIDGE OVER HARLAN	05/05/22	5.00	550.00	728.03	866.23
	WEIGHTED	AVERAGE FOR THE SECOND QUARTER		5.00	550.00	728.03	866.23
2670403-065		US40_FLOYD HILL ROUNDABOUTS	09/15/22	5.00	660.00	782.83	730.00
	WEIGHTED	AVERAGE FOR THE THIRD QUARTER		5.00	660.00	782.83	730.00
		WEIGHTED AVERAGE FOR THE YEAR		10.00	605.00	746.30	798.12
=====	214-00507	Furn Evergreen Tree (6 Ft) (B-B)		Each	=====	=====	=====
2670403-065		US40_FLOYD HILL ROUNDABOUTS	09/15/22	24.00	470.00	535.40	620.00
	WEIGHTED	AVERAGE FOR THE THIRD QUARTER		24.00	470.00	535.40	620.00
		WEIGHTED AVERAGE FOR THE YEAR		24.00	470.00	535.40	620.00
=====	214-01009	Brush Windrow		Lin Foot	=====	=====	=====
2670703-497		I-70_GENESEE WILDLIFE XING	09/15/22	340.00	9.10	24.56	56.29
	WEIGHTED	AVERAGE FOR THE THIRD QUARTER		340.00	9.10	24.56	56.29
		WEIGHTED AVERAGE FOR THE YEAR		340.00	9.10	24.56	56.29

COLORADO DEPARTMENT OF TRANSPORTATION
ITEM UNIT COSTS BY PROJECTS -- 2022 COST DATA

11:31 Wednesday, March 8, 2023 195

PROJECT NUMBER	ITEM NUMBER/ PROJECT LOCATION	ITEM DESCRIPTION/ PROJECT LOCATION	DATE LET	UNIT/ QUANTITY	ENGR. EST.	AVERAGE BID	AWARDED BID
===== 214-01010		Brush Layer Cutting		Each =====			
ER0502-092		US 50 MP 204 EB MONARCH TRUCK	08/29/22	40.00	5.00	13.57	14.59
		WEIGHTED AVERAGE FOR THE THIRD QUARTER		40.00	5.00	13.57	14.59
BR012A-048		CO 12 STRUCTURE P-17-F AT MP	12/22/22	200.00	20.00	14.06	20.00
		WEIGHTED AVERAGE FOR THE FOURTH QUARTER		200.00	20.00	14.06	20.00
		WEIGHTED AVERAGE FOR THE YEAR		240.00	17.50	13.94	19.10
===== 214-01013		Live Willow Stakes		Each =====			
NHPP0702-383		I-70 EB AUX FRISCO TO SILVERT	01/13/22	150.00	6.00	8.52	7.00
		WEIGHTED AVERAGE FOR THE FIRST QUARTER		150.00	6.00	8.52	7.00
NHPP0702-414		VAIL PASS AUX PHASE 1 CAP 3	07/08/22	400.00	11.46	11.46	11.46
FBR0702-423		VAIL PASS AUX BE F-12-AT PHAS					
NHPP0701-231		I-70 SALT WASH BRIDGES SCOUR	09/29/22	1,075.00	12.00	7.70	10.00
		WEIGHTED AVERAGE FOR THE THIRD QUARTER		1,475.00	11.85	8.29	10.40
STU0252-457		I-25:ALAMEDA RIVER PH 2.0	11/03/22	352.00	12.00	7.18	7.00
		WEIGHTED AVERAGE FOR THE FOURTH QUARTER		352.00	12.00	7.18	7.00
		WEIGHTED AVERAGE FOR THE YEAR		1,977.00	11.44	8.06	9.53
===== 214-01015		Willow Cuttings		Each =====			
FBR0761-236		I-76 OVER CLR CRK SCOUR MIT	08/25/22	1,081.00	10.00	9.17	10.00
		WEIGHTED AVERAGE FOR THE THIRD QUARTER		1,081.00	10.00	9.17	10.00
		WEIGHTED AVERAGE FOR THE YEAR		1,081.00	10.00	9.17	10.00

COLORADO DEPARTMENT OF TRANSPORTATION
ITEM UNIT COSTS BY PROJECTS -- 2022 COST DATA

11:31 Wednesday, March 8, 2023 196

PROJECT NUMBER	ITEM NUMBER/ PROJECT LOCATION	ITEM DESCRIPTION/ PROJECT LOCATION	DATE LET	UNIT/ QUANTITY	ENGR. EST.	AVERAGE BID	AWARDED BID
===== 214-01016		Live Willow Poles		Each =====			
STU0252-457		I-25:ALAMEDA RIVER PH 2.0	11/03/22	18.00	100.00	72.10	130.00
	WEIGHTED AVERAGE FOR THE FOURTH QUARTER			18.00	100.00	72.10	130.00
	WEIGHTED AVERAGE FOR THE YEAR			18.00	100.00	72.10	130.00
===== 214-01228		Riprap Planting Pocket		Each =====			
FBR0761-236		I-76 OVER CLR CRK SCOUR MIT	08/25/22	78.00	200.00	58.33	20.00
	WEIGHTED AVERAGE FOR THE THIRD QUARTER			78.00	200.00	58.33	20.00
STU0252-457		I-25:ALAMEDA RIVER PH 2.0	11/03/22	63.00	20.00	201.77	205.00
	WEIGHTED AVERAGE FOR THE FOURTH QUARTER			63.00	20.00	201.77	205.00
	WEIGHTED AVERAGE FOR THE YEAR			141.00	119.57	122.42	102.66
===== 214-01401		Nursery Stock Container (DRC #10)		Each =====			
NHPP0702-414 FBR0702-423		VAIL PASS AUX PHASE 1 CAP 3	07/08/22	2,000.00	4.09	4.09	4.09
	WEIGHTED AVERAGE FOR THE THIRD QUARTER	VAIL PASS AUX BE F-12-AT PHAS		2,000.00	4.09	4.09	4.09
STU0252-457		I-25:ALAMEDA RIVER PH 2.0	11/03/22	101.00	15.00	8.72	15.00
	WEIGHTED AVERAGE FOR THE FOURTH QUARTER			101.00	15.00	8.72	15.00
	WEIGHTED AVERAGE FOR THE YEAR			2,101.00	4.61	4.70	4.61
===== 214-01403		Nursery Stock Container (DRC # 60)		Each =====			
NHPP0702-414		VAIL PASS AUX PHASE 1 CAP 3	07/08/22	205.00	28.10	28.10	28.10

COLORADO DEPARTMENT OF TRANSPORTATION
 ITEM UNIT COSTS BY PROJECTS -- 2022 COST DATA

11:31 Wednesday, March 8, 2023 197

PROJECT NUMBER	ITEM NUMBER/ PROJECT LOCATION	ITEM DESCRIPTION/ PROJECT LOCATION	DATE LET	UNIT/ QUANTITY	ENGR. EST.	AVERAGE BID	AWARDED BID
=====	214-01403	Nursery Stock Container (DRC # 60)		Each	=====	=====	=====
FBR0702-423		VAIL PASS AUX BE F-12-AT PHAS					
FBR0761-236		I-76 OVER CLR CRK SCOUR MIT	08/25/22	108.00	20.00	10.17	11.00
	WEIGHTED AVERAGE FOR THE THIRD QUARTER			313.00	25.31	17.12	22.20
	WEIGHTED AVERAGE FOR THE YEAR			313.00	25.31	17.12	22.20
=====	214-01404	Nursery Stock Container (DRC # 180)		Each	=====	=====	=====
STU0252-457		I-25:ALAMEDA RIVER PH 2.0	11/03/22	18.00	25.00	27.93	41.00
	WEIGHTED AVERAGE FOR THE FOURTH QUARTER			18.00	25.00	27.93	41.00
	WEIGHTED AVERAGE FOR THE YEAR			18.00	25.00	27.93	41.00
=====	214-01420	(SNC #1) Nursery Stock Container		Each	=====	=====	=====
NHPP0702-383		I-70 EB AUX FRISCO TO SILVERT	01/13/22	30.00	22.00	81.90	220.00
	WEIGHTED AVERAGE FOR THE FIRST QUARTER			30.00	22.00	81.90	220.00
NHPP0931-033		SH93:US6 TO 58TH RESURFACING	12/15/22	79.00	30.00	46.24	18.45
	WEIGHTED AVERAGE FOR THE FOURTH QUARTER			79.00	30.00	46.24	18.45
	WEIGHTED AVERAGE FOR THE YEAR			109.00	27.80	57.72	73.92
=====	215-00600	Transplant Plug		Each	=====	=====	=====
NHPP0702-414		VAIL PASS AUX PHASE 1 CAP 3	07/08/22	1,000.00	13.64	13.64	13.64
FBR0702-423		VAIL PASS AUX BE F-12-AT PHAS					
	WEIGHTED AVERAGE FOR THE THIRD QUARTER			1,000.00	13.64	13.64	13.64
	WEIGHTED AVERAGE FOR THE YEAR			1,000.00	13.64	13.64	13.64
=====	216-00021	Soil Reten Blanket (C1 1)		Sq Yard	=====	=====	=====
FSA3921-019		SH 392 AND WCR 55 ISLANDS	06/02/22	340.00	5.00	6.33	7.00
	WEIGHTED AVERAGE FOR THE SECOND QUARTER			340.00	5.00	6.33	7.00
	WEIGHTED AVERAGE FOR THE YEAR			340.00	5.00	6.33	7.00

COLORADO DEPARTMENT OF TRANSPORTATION
ITEM UNIT COSTS BY PROJECTS -- 2022 COST DATA

11:31 Wednesday, March 8, 2023 198

PROJECT NUMBER	ITEM NUMBER/ PROJECT LOCATION	ITEM DESCRIPTION/ PROJECT LOCATION	DATE LET	UNIT/ QUANTITY	ENGR. EST.	AVERAGE BID	AWARDED BID
=====	216-00022	Soil Reten Blanket (C1 2)		Sq Yard	=====		
2670403-065		US40_FLOYD HILL ROUNDABOUTS	09/15/22	595.00	5.00	4.92	5.00
		WEIGHTED AVERAGE FOR THE THIRD QUARTER		595.00	5.00	4.92	5.00
		WEIGHTED AVERAGE FOR THE YEAR		595.00	5.00	4.92	5.00
=====	216-00041	Soil Reten Blanket (S/C)		Sq Yard	=====		
SHE0242-087		US 24 SAFETY IMPRVMTS, E OF	11/03/22	2,408.00	3.00	3.82	3.70
NHPP083A-046		SH83 RESURFACING STROH RD TO	12/08/22	1,492.00	4.00	3.34	3.27
		WEIGHTED AVERAGE FOR THE FOURTH QUARTER		3,900.00	3.38	3.68	3.54
		WEIGHTED AVERAGE FOR THE YEAR		3,900.00	3.38	3.68	3.54
=====	216-00042	Soil Retent Blanket (BioD S/C)		Sq Yard	=====		
STA0361-129		US 36: HYGIENE RD AND NELSON	12/22/22	1,210.00	10.00	3.08	3.47
		WEIGHTED AVERAGE FOR THE FOURTH QUARTER		1,210.00	10.00	3.08	3.47
		WEIGHTED AVERAGE FOR THE YEAR		1,210.00	10.00	3.08	3.47
=====	216-00070	Geocell Confinement Sys		Sq Yard	=====		
2670703-487		I-70 BRIDGES OVER WARD ROAD-	12/01/22	1,250.00	30.00	34.34	31.00
		WEIGHTED AVERAGE FOR THE FOURTH QUARTER		1,250.00	30.00	34.34	31.00
		WEIGHTED AVERAGE FOR THE YEAR		1,250.00	30.00	34.34	31.00
=====	216-00101	Soil Reten Blanket (S-C) (PhotoD C1 1)		Sq Yard	=====		
NHPP1601-083			02/03/22	5,704.00	3.50	4.59	4.00
NHPP 0761-238		I-76 DAHLIA TO YORK	03/10/22	21,975.00	3.20	2.51	2.50
C0761-239							
BRC040-057			03/17/22	150.00	5.00	5.28	2.83
		WEIGHTED AVERAGE FOR THE FIRST QUARTER		27,829.00	3.27	2.64	2.81

COLORADO DEPARTMENT OF TRANSPORTATION
ITEM UNIT COSTS BY PROJECTS -- 2022 COST DATA

11:31 Wednesday, March 8, 2023 199

PROJECT NUMBER	ITEM NUMBER/ PROJECT LOCATION	ITEM DESCRIPTION/ PROJECT LOCATION	DATE LET	UNIT/ QUANTITY	ENGR. EST.	AVERAGE BID	AWARDED BID
=====	216-00101	Soil Reten Blanket (S-C) (PhotoD Cl 1)		Sq Yard	=====		
NH0504-911			04/07/22	1,500.00	2.41	3.85	4.20
NHPP0702-413		VAIL PASS AUX PHASE 1 CAP 2	04/18/22	19,000.00	2.43	2.43	2.43
		WEIGHTED AVERAGE FOR THE SECOND QUARTER		20,500.00	2.43	2.62	2.56
STR0711-022		SH 71 OVER THE ARKANSAS	08/04/22	70.00	3.00	25.03	9.00
		WEIGHTED AVERAGE FOR THE THIRD QUARTER		70.00	3.00	25.03	9.00
STAM420-001 BR2854-148 STM0091-046		US 285 AT HWY 9C IMPROVEMENTS INTERSECTION OF US 285 & SH 9 ADA RAMP IMPROVEMENTS - FAIRP	12/01/22	14,127.00	2.75	2.96	3.14
		WEIGHTED AVERAGE FOR THE FOURTH QUARTER		14,127.00	2.75	2.96	3.14
		WEIGHTED AVERAGE FOR THE YEAR		62,526.00	2.88	2.72	2.81
=====	216-00111	Soil Reten Blanket (Excel) (PhotoD Cl 1)		Sq Yard	=====		
NH0504-911			04/07/22	1,500.00	5.00	3.80	3.90
		WEIGHTED AVERAGE FOR THE SECOND QUARTER		1,500.00	5.00	3.80	3.90
		WEIGHTED AVERAGE FOR THE YEAR		1,500.00	5.00	3.80	3.90
=====	216-00201	Soil Reten Blanket (S-C) (BioD Cl 1)		Sq Yard	=====		
NHPP0702-383 C0762-055		I-70 EB AUX FRISCO TO SILVERT	01/13/22	48,320.00	2.50	2.26	1.50
STR0141-031			02/17/22	970.00	5.00	2.76	3.00
STR092A-031			02/17/22	3,146.00	4.00	2.87	2.35
			03/17/22	2,420.00	4.00	2.35	2.35
		WEIGHTED AVERAGE FOR THE FIRST QUARTER		54,856.00	2.70	2.29	1.61
2670703-479		I-70 BRIDGE OVER HARLAN	05/05/22	5,855.00	2.75	2.82	3.10

COLORADO DEPARTMENT OF TRANSPORTATION
ITEM UNIT COSTS BY PROJECTS -- 2022 COST DATA

11:31 Wednesday, March 8, 2023 200

PROJECT NUMBER	ITEM NUMBER/ PROJECT LOCATION	ITEM DESCRIPTION/ PROJECT LOCATION	DATE LET	UNIT/ QUANTITY	ENGR. EST.	AVERAGE BID	AWARDED BID
=====	216-00201	Soil Reten Blanket (S-C) (BioD Cl 1)		Sq Yard	=====	=====	=====
STA0712-019		SH 71: Frieght Improvements	05/12/22	5,634.00	2.50	2.64	2.64
C0852-120		Rehabilitation of Culvert by	05/26/22	2,450.00	5.00	2.50	2.50
FSA0702-409		I-70 VAIL WILDLIFE FENCE PHAS	05/26/22	40.00	12.00	10.00	10.00
ITS 0741-024		VMS SIGN INSTALLATIONS AND VS	06/02/22	100.00	10.00	4.50	4.00
FSA052A-046		SH52 WCR 37 INTERSECTION IMPR	06/09/22	4,405.00	3.00	3.33	3.20
		WEIGHTED AVERAGE FOR THE SECOND QUARTER		18,484.00	3.09	2.97	2.92
NHPP0702-414		VAIL PASS AUX PHASE 1 CAP 3	07/08/22	21,780.00	3.66	3.66	3.66
FBR0702-423		VAIL PASS AUX BE F-12-AT PHAS					
FSA052A-057		SH52 BOX CULVERT EXTENSION (M	08/04/22	968.00	5.50	4.95	6.50
BR0343-046		US 34 TIMBER BRIDGE REPL. PKG	08/31/22	986.00	2.41	2.41	2.41
FBR0343-047		US 6/US 34 TIMBER BRIDGE REPL					
NHPPR100-266		RI ESSENTIAL REPAIRS	09/01/22	400.00	10.00	4.43	3.23
ER0253-297		WCR 34 BRIDGE OVER I-25(MM 24	09/14/22	240.00	7.00	5.60	4.70
2670403-065		US40 FLOYD HILL ROUNDABOUTS	09/15/22	7,289.00	4.00	4.28	5.00
2670703-497		I-70_GENESEE WILDLIFE KING	09/15/22	5,550.00	4.00	3.66	2.67
SHE2873-193		US 287 & CO 52 INTERSECTION I	09/15/22	3,390.00	5.00	2.83	2.43
		WEIGHTED AVERAGE FOR THE THIRD QUARTER		40,603.00	3.98	3.68	3.70
NHPP0705-088		I-70 AGATE STRUCTURE REHAB	10/27/22	970.00	3.30	3.32	4.00
FSAM240-200		SH21B CO SPRINGS SIGNAL REPLA	10/27/22	680.00	3.00	6.24	5.95
STA3852-015		US 385 HOLYOKE NORTH	10/27/22	2,311.00	3.50	3.50	3.50
STU0252-457		I-25:ALAMEDA RIVER PH 2.0	11/03/22	5,258.00	3.00	3.05	2.50
STR064A-010		SH 64 AND SH 13 AT MEEKER	11/10/22	2,904.00	3.50	3.20	2.60
NHPP0853-126		US85C: PLATTEVILLE NORTH MP (11/10/22	3,388.00	4.00	2.99	3.10
C5502-097		US550 MP 117.28-126.06	11/17/22	6,888.00	3.50	3.96	4.00
STA0711-021		SH71: REGION LINE NORTH	12/01/22	1,460.00	3.90	3.76	4.00
STR114A-015		SH114 SILLSVILLE SOUTH TO MP3	12/01/22	1,000.00	3.00	5.25	6.00
2670703-487		I-70 BRIDGES OVER WARD ROAD-	12/01/22	2,981.00	3.50	2.75	2.70
NHPP0701-252		I-70 RIFLE TO SILT SLAB REPLA	12/01/22	242.00	5.00	7.38	9.75
IM025A-050		I25-MP103.9 - INTERSECTION DR	12/01/22	3,878.00	3.00	3.43	2.80
NHPP0063-048		US6 / 20 ROAD INTERSECTION IM	12/15/22	1,917.00	4.00	4.63	4.40
NHPP0931-033		SH93:US6 TO 58TH RESURFACING	12/15/22	1,500.00	4.00	3.75	4.00
NHPP0502-090		SH 50 MP 134.6-136 GUNNISON C	12/22/22	12,300.00	2.50	3.86	4.60
BR012A-048		CO 12 STRUCTURE P-17-F AT MP	12/22/22	2,310.00	5.00	4.19	5.00
STA385A-016		SH 385 MP 97.76	12/22/22	700.00	10.00	4.60	4.38
		WEIGHTED AVERAGE FOR THE FOURTH QUARTER		50,687.00	3.39	3.67	3.83
		WEIGHTED AVERAGE FOR THE YEAR		164,630.00	3.27	3.03	2.97

COLORADO DEPARTMENT OF TRANSPORTATION
ITEM UNIT COSTS BY PROJECTS -- 2022 COST DATA

11:31 Wednesday, March 8, 2023 201

PROJECT NUMBER	ITEM NUMBER/ PROJECT LOCATION	ITEM DESCRIPTION/ PROJECT LOCATION	DATE LET	UNIT/ QUANTITY	ENGR. EST.	AVERAGE BID	AWARDED BID
=====	216-00221	Soil Reten Blanket (C) (BioD Cl 1)		Sq Yard	=====		
TRG0253-264		I-25 AND SH 119 PARK-N-RIDE	10/27/22	10,619.00	3.00	3.47	3.55
		WEIGHTED AVERAGE FOR THE FOURTH QUARTER		10,619.00	3.00	3.47	3.55
		WEIGHTED AVERAGE FOR THE YEAR		10,619.00	3.00	3.47	3.55
=====	216-00301	Turf Reinf Mat (Cl 1)		Sq Yard	=====		
NH0504-911			04/07/22	1,500.00	4.73	8.95	9.40
		WEIGHTED AVERAGE FOR THE SECOND QUARTER		1,500.00	4.73	8.95	9.40
2670403-065		US40_FLOYD HILL ROUNDABOUTS	09/15/22	735.00	5.00	6.92	7.00
		WEIGHTED AVERAGE FOR THE THIRD QUARTER		735.00	5.00	6.92	7.00
		WEIGHTED AVERAGE FOR THE YEAR		2,235.00	4.82	8.09	8.61
=====	216-00302	Turf Reinf Mat (Cl 2)		Sq Yard	=====		
STM1151-038		SH115 MP 27 TO MP 38	04/21/22	100.00	6.00	8.61	6.50
		WEIGHTED AVERAGE FOR THE SECOND QUARTER		100.00	6.00	8.61	6.50
2670703-487		I-70 BRIDGES OVER WARD ROAD-	12/01/22	2,981.00	10.00	7.33	6.50
		WEIGHTED AVERAGE FOR THE FOURTH QUARTER		2,981.00	10.00	7.33	6.50
		WEIGHTED AVERAGE FOR THE YEAR		3,081.00	9.87	7.37	6.50
=====	216-00303	Turf Reinf Mat (Cl 3)		Sq Yard	=====		
NHPP0702-383		I-70 EB AUX FRISCO TO SILVERT	01/13/22	6,860.00	5.30	7.53	7.50
		WEIGHTED AVERAGE FOR THE FIRST QUARTER		6,860.00	5.30	7.53	7.50

COLORADO DEPARTMENT OF TRANSPORTATION
 ITEM UNIT COSTS BY PROJECTS -- 2022 COST DATA

11:31 Wednesday, March 8, 2023 202

PROJECT NUMBER	ITEM NUMBER/ PROJECT LOCATION	ITEM DESCRIPTION/ PROJECT LOCATION	DATE LET	UNIT/ QUANTITY	ENGR. EST.	AVERAGE BID	AWARDED BID
=====	216-00303	Turf Reinf Mat (Cl 3)		Sq Yard	=====		
SHE0242-087		US 24 SAFETY IMPRVMTS, E OF	11/03/22	2,372.00	7.50	11.74	12.21
NHPP0502-090		SH 50 MP 134.6-136 GUNNISON C	12/22/22	2,050.00	8.00	10.09	13.39
	WEIGHTED AVERAGE FOR THE FOURTH QUARTER			4,422.00	7.73	10.76	12.76
	WEIGHTED AVERAGE FOR THE YEAR			11,282.00	6.25	8.61	9.56
=====	216-00304	Turf Reinforcement Mat (Special)		Sq Yard	=====		
STAM420-001		US 285 AT HWY 9C IMPROVEMENTS	12/01/22	322.00	7.00	38.17	45.25
BR2854-148		INTERSECTION OF US 285 & SH 9					
STM0091-046		ADA RAMP IMPROVEMENTS - FAIRP					
	WEIGHTED AVERAGE FOR THE FOURTH QUARTER			322.00	7.00	38.17	45.25
	WEIGHTED AVERAGE FOR THE YEAR			322.00	7.00	38.17	45.25
=====	217-00000	Herbicide Treatment		Sq Yard	=====		
STA 067A-048		Hwy 67A MP 0.00 TO MP 11.05 I	03/03/22	500.00	10.00	3.72	4.00
	WEIGHTED AVERAGE FOR THE FIRST QUARTER			500.00	10.00	3.72	4.00
STA0712-019		SH 71: Frieight Improvements	05/12/22	10,000.00	1.50	0.72	0.72
CM760-047		COLFAX AND QUAIL	05/12/22	1.00	5.00	186.40	625.00
	WEIGHTED AVERAGE FOR THE SECOND QUARTER			10,001.00	1.50	0.81	0.78
IM025A-050		I25-MP103.9 - INTERSECTION DR	12/01/22	13,552.00	1.00	0.43	0.50
	WEIGHTED AVERAGE FOR THE FOURTH QUARTER			13,552.00	1.00	0.43	0.50
	WEIGHTED AVERAGE FOR THE YEAR			24,053.00	1.40	0.60	0.69
=====	217-00020	Herbicide Treatment		Hour	=====		
STA0252-459			02/03/22	60.00	150.00	179.56	175.00

COLORADO DEPARTMENT OF TRANSPORTATION
 ITEM UNIT COSTS BY PROJECTS -- 2022 COST DATA

11:31 Wednesday, March 8, 2023 203

PROJECT NUMBER	ITEM NUMBER/ PROJECT LOCATION	ITEM DESCRIPTION/ PROJECT LOCATION	DATE LET	UNIT/ QUANTITY	ENGR. EST.	AVERAGE BID	AWARDED BID
===== 217-00020							
NHPP 0761-238		Herbicide Treatment		Hour			
C0761-239	I-76 DAHLIA TO YORK		03/10/22	40.00	180.00	189.56	185.00
CR100-362			03/14/22	100.00	144.34	144.34	144.34
BRC040-057			03/17/22	8.00	200.00	186.00	179.00
M R100-351	FY22 R1 SIGN STRUCTURE REPLAC		03/17/22	10.00	160.00	149.50	209.00
WEIGHTED AVERAGE FOR THE FIRST QUARTER				218.00	155.20	178.46	164.48
STM1151-038		SH115 MP 27 TO MP 38	04/21/22	80.00	145.00	217.35	150.00
C0852-120		Rehabilitation of Culvert by	05/26/22	16.00	250.00	125.00	125.00
ITS 0741-024		VMS SIGN INSTALLATIONS AND VS	06/02/22	5.00	100.00	203.00	187.00
WEIGHTED AVERAGE FOR THE SECOND QUARTER				101.00	159.41	213.55	147.87
FBR0761-236		I-76 OVER CLR CRK SCOUR MIT	08/25/22	30.00	160.00	155.00	145.00
C1211-099		SH 121 NORTH SGA SIGNALS	08/25/22	8.00	180.00	199.50	279.00
NHPPR100-266		R1 ESSENTIAL REPAIRS	09/01/22	15.00	130.00	188.20	222.60
2670403-065		US40_FLOYD HILL ROUNDABOUTS	09/15/22	100.00	155.00	188.07	99.00
2670703-497		I-70_GENESEE WILDLIFE XING	09/15/22	20.00	155.00	210.40	193.10
WEIGHTED AVERAGE FOR THE THIRD QUARTER				173.00	154.86	188.64	136.90
NHPP0705-088		I-70 AGATE STRUCTURE REHAB	10/27/22	80.00	150.00	171.13	148.00
TRG0253-264		I-25 AND SH 119 PARK-N-RIDE	10/27/22	25.00	180.00	176.19	200.00
STU0252-457		I-25:ALAMEDA RIVER PH 2.0	11/03/22	96.00	140.00	212.90	246.00
STA0711-021		SH71: REGION LINE NORTH	12/01/22	16.00	150.00	678.37	650.00
STR109A-019		M-22-AY BRIDGE REHAB ON SH109	12/01/22	16.00	175.00	156.04	141.08
NHPP0931-033		SH93:US6 TO 58TH RESURFACING	12/15/22	40.00	150.00	159.46	143.50
STA0361-129		US 36: HYGIENE RD AND NELSON	12/22/22	40.00	200.00	116.49	111.60
WEIGHTED AVERAGE FOR THE FOURTH QUARTER				313.00	157.00	190.45	202.29
WEIGHTED AVERAGE FOR THE YEAR				805.00	156.35	190.78	171.17
===== 218-00000							
				LUMP SUM			
NHPP0702-413		VAIL PASS AUX PHASE 1 CAP 2	04/18/22	1.00	10357.60	10357.60	10357.60
WEIGHTED AVERAGE FOR THE SECOND QUARTER				1.00	10357.60	10357.60	10357.60

COLORADO DEPARTMENT OF TRANSPORTATION
 ITEM UNIT COSTS BY PROJECTS -- 2022 COST DATA

11:31 Wednesday, March 8, 2023 204

PROJECT NUMBER	ITEM NUMBER/ PROJECT LOCATION	ITEM DESCRIPTION/ PROJECT LOCATION	DATE LET	UNIT/ QUANTITY	ENGR. EST.	AVERAGE BID	AWARDED BID
===== 218-00000 Noxious Weed Management LUMP SUM =====							
NHPP0702-414		VAIL PASS AUX PHASE 1 CAP 3	07/08/22	1.00	18837.89	18837.89	18837.89
FBR0702-423		VAIL PASS AUX BE F-12-AT PHAS					
		WEIGHTED AVERAGE FOR THE THIRD QUARTER		1.00	18837.89	18837.89	18837.89
===== 240-00000 Wildlife Biologist Hour =====							
ITS0703-477		ITS EQUIPMENT UPGRADE AT EJMT	01/06/22	24.00	150.00	135.00	135.00
NHPP0702-383		I-70 EB AUX FRISCO TO SILVERT	01/13/22	60.00	125.00	152.11	150.00
NHPP1601-083			02/03/22	40.00	140.00	259.90	240.00
STA0252-459			02/03/22	60.00	120.00	117.80	130.00
NHPP 0761-238		I-76 DAHLIA TO YORK	03/10/22	250.00	160.00	114.25	120.00
C0761-239							
NHPP0703-472			03/10/22	60.00	125.00	94.49	85.00
BRC040-057			03/17/22	40.00	200.00	152.50	135.00
STR R500-171		Various locations on SH 141 a	03/17/22	45.00	260.00	103.85	10.00
		WEIGHTED AVERAGE FOR THE FIRST QUARTER		579.00	157.34	121.98	121.92
NHPP0702-413		VAIL PASS AUX PHASE 1 CAP 2	04/18/22	16.00	107.00	107.00	107.00
STM1151-038		SH115 MP 27 TO MP 38	04/21/22	24.00	126.00	120.96	90.00
2670703-479		I-70 BRIDGE OVER HARLAN	05/05/22	40.00	120.00	98.85	95.41
NHC540-017		R2 CHAINUP STA @ KENOSHA/HOOS	05/12/22	20.00	130.00	138.33	140.00
CM760-047		COLFAX AND QUAIL	05/12/22	20.00	130.00	113.60	100.00
STAR100-358		3 STRUCTURES IN REGION 1 METR	05/26/22	100.00	125.00	83.37	85.00
C0852-120		Rehabilitation of Culvert by	05/26/22	16.00	175.00	30.00	30.00
FSA0702-409		I-70 VAIL WILDLIFE FENCE PHAS	05/26/22	40.00	170.00	150.00	150.00
NHPP072A-047		SH-72 RESURFACING: I-70 TO IN	06/09/22	48.00	130.00	106.80	106.80
NHPP0252-448		I-25 TREX NARROWS BRIDGE PREV	06/23/22	96.00	125.00	97.75	90.00
		WEIGHTED AVERAGE FOR THE SECOND QUARTER		420.00	131.13	101.03	98.18

PROJECT NUMBER	ITEM NUMBER/ PROJECT LOCATION	ITEM DESCRIPTION/ PROJECT LOCATION	DATE LET	UNIT/ QUANTITY	ENGR. EST.	AVERAGE BID	AWARDED BID
===== 240-00000		Wildlife Biologist		Hour =====			
NHPP0702-414		VAIL PASS AUX PHASE 1 CAP 3	07/08/22	16.00	107.00	107.00	107.00
FBR0702-423		VAIL PASS AUX BE F-12-AT PHAS					
NHPP0063-054		US 6 FROM I70-B TO 33 RD. (MP	08/18/22	20.00	130.00	117.84	115.00
FBR0761-236		I-76 OVER CLR CRK SCOUR MIT	08/25/22	30.00	140.00	126.67	125.00
C1211-099		SH 121 NORTH SGA SIGNALS	08/25/22	8.00	150.00	170.00	220.00
ER0502-092		US 50 MP 204 EB MONARCH TRUCK	08/29/22	10.00	140.00	191.48	259.44
STAR100-374		5 STRUCTURES IN REGION 1	09/01/22	75.00	85.00	95.40	95.40
NHPPR100-266		R1 ESSENTIAL REPAIRS	09/01/22	60.00	140.00	132.07	127.20
2670403-065		US40_FLOYD HILL ROUNDABOUTS	09/15/22	20.00	110.00	140.87	140.00
2670703-497		I-70_GENESEE WILDLIFE KING	09/15/22	20.00	120.00	130.37	113.59
		WEIGHTED AVERAGE FOR THE THIRD QUARTER		259.00	117.71	129.71	123.46
NHPP0705-088		I-70 AGATE STRUCTURE REHAB	10/27/22	20.00	150.00	150.13	148.00
C5502-111		US 550 MP 81 AND 89 RED MOUNT	10/27/22	30.00	150.00	190.00	190.00
TRG0253-264		I-25 AND SH 119 PARK-N-RIDE	10/27/22	16.00	135.00	126.41	140.00
STU0252-457		I-25:ALAMEDA RIVER PH 2.0	11/03/22	96.00	140.00	121.47	135.00
C5502-097		US550 MP 117.28-126.06	11/17/22	40.00	130.00	233.29	242.00
STR114A-015		SH114 SILLSVILLE SOUTH TO MP3	12/01/22	10.00	150.00	220.00	190.00
2670703-487		I-70 BRIDGES OVER WARD ROAD-	12/01/22	10.00	185.00	130.62	94.00
NHPP0701-252		I-70 RIFLE TO SILT SLAB REPLA	12/01/22	24.00	200.00	200.00	180.00
IM025A-050		I25-MP103.9 - INTERSECTION DR	12/01/22	8.00	120.00	146.67	130.00
NHPP0063-048		US6 / 20 ROAD INTERSECTION IM	12/15/22	20.00	150.00	186.05	90.00
NHPP0931-033		SH93:US6 TO 58TH RESURFACING	12/15/22	24.00	130.00	182.49	254.00
NHPP0502-090		SH 50 MP 134.6-136 GUNNISON C	12/22/22	40.00	150.00	365.54	1027.58
STA0361-129		US 36: HYGIENE RD AND NELSON	12/22/22	40.00	150.00	134.71	94.86
		WEIGHTED AVERAGE FOR THE FOURTH QUARTER		378.00	146.90	187.00	244.82
		WEIGHTED AVERAGE FOR THE YEAR		1,636.00	141.93	133.77	146.86
===== 240-00010		Rem of Nests		Hour =====			
ITS0703-477		ITS EQUIPMENT UPGRADE AT EJMT	01/06/22	24.00	150.00	130.00	130.00
NHPP0702-383		I-70 EB AUX FRISCO TO SILVERT	01/13/22	40.00	100.00	127.07	130.00
NHPP1601-083			02/03/22	10.00	150.00	399.74	125.00
STA0252-459			02/03/22	40.00	110.00	88.27	107.00
STA 067A-048		Hwy 67A MP 0.00 TO MP 11.05 I	03/03/22	10.00	100.00	138.78	150.00
NHPP 0761-238		I-76 DAHLIA TO YORK	03/10/22	80.00	120.00	115.77	100.00

COLORADO DEPARTMENT OF TRANSPORTATION
ITEM UNIT COSTS BY PROJECTS -- 2022 COST DATA

11:31 Wednesday, March 8, 2023 206

PROJECT NUMBER	ITEM NUMBER/ PROJECT LOCATION	ITEM DESCRIPTION/ PROJECT LOCATION	DATE LET	UNIT/ QUANTITY	ENGR. EST.	AVERAGE BID	AWARDED BID
===== 240-00010							
		Rem of Nests		Hour			
C0761-239							
NHPP0703-472			03/10/22	60.00	100.00	87.57	75.00
BRC040-057			03/17/22	40.00	115.00	181.00	53.00
STR R500-171		Various locations on SH 141 a	03/17/22	112.00	215.00	161.52	10.00
WEIGHTED AVERAGE FOR THE FIRST QUARTER				416.00	141.30	129.73	74.74
STM1151-038		SH115 MP 27 TO MP 38	04/21/22	8.00	190.00	144.59	90.00
2670703-479		I-70 BRIDGE OVER HARLAN	05/05/22	40.00	120.00	111.23	89.45
NHC540-017		R2 CHAINUP STA @ KENOSHA/HOOS	05/12/22	16.00	115.00	138.33	140.00
CM760-047		COLFAX AND QUAIL	05/12/22	20.00	120.00	101.00	94.00
STAR100-358		3 STRUCTURES IN REGION 1 METR	05/26/22	100.00	80.00	69.26	53.00
FSA0702-409		I-70 VAIL WILDLIFE FENCE PHAS	05/26/22	100.00	170.00	150.00	150.00
NHPP072A-047		SH-72 RESURFACING: I-70 TO IN	06/09/22	48.00	120.00	106.80	106.80
NHPP0252-448		I-25 TREX NARROWS BRIDGE PREV	06/23/22	96.00	80.00	194.75	95.00
WEIGHTED AVERAGE FOR THE SECOND QUARTER				428.00	114.49	130.88	100.38
NHPP0063-054		US 6 FROM I70-B TO 33 RD. (MP	08/18/22	20.00	140.00	126.89	115.00
FBR0761-236		I-76 OVER CLR CRK SCOUR MIT	08/25/22	30.00	120.00	213.33	135.00
STAR100-374		5 STRUCTURES IN REGION 1	09/01/22	75.00	75.00	175.97	175.97
NHPPR100-266		R1 ESSENTIAL REPAIRS	09/01/22	60.00	160.00	235.36	198.09
SHE2873-193		US 287 & CO 52 INTERSECTION I	09/15/22	10.00	100.00	101.12	120.00
WEIGHTED AVERAGE FOR THE THIRD QUARTER				195.00	116.03	193.05	167.35
STA207A-004		Resurfacing SH207A MANZANOLA	10/27/22	4.00	120.00	298.57	185.70
NHPP0705-088		I-70 AGATE STRUCTURE REHAB	10/27/22	16.00	150.00	183.69	142.00
TRG0253-264		I-25 AND SH 119 PARK-N-RIDE	10/27/22	4.00	125.00	153.56	140.00
STU0252-457		I-25:ALAMEDA RIVER PH 2.0	11/03/22	40.00	140.00	98.96	105.00
SHE0242-087		US 24 SAFETY IMPRVMENTS, E OF	11/03/22	10.00	91.80	144.22	182.67
STAM420-001		US 285 AT HWY 9C IMPROVEMENTS	12/01/22	300.00	100.00	150.52	148.68
BR2854-148		INTERSECTION OF US 285 & SH 9					
STM0091-046		ADA RAMP IMPROVEMENTS - FAIRP					
2670703-487		I-70 BRIDGES OVER WARD ROAD-	12/01/22	10.00	150.00	133.81	88.00
NHPP0701-252		I-70 RIFLE TO SILT SLAB REPLA	12/01/22	24.00	160.00	270.50	111.00
STR109A-019		M-22-AY BRIDGE REHAB ON SH109	12/01/22	20.00	120.00	369.14	343.27
NHPP0502-090		SH 50 MP 134.6-136 GUNNISON C	12/22/22	40.00	130.00	144.58	150.80
STA0361-129		US 36: HYGIENE RD AND NELSON	12/22/22	40.00	150.00	92.99	89.28

COLORADO DEPARTMENT OF TRANSPORTATION
 ITEM UNIT COSTS BY PROJECTS -- 2022 COST DATA

11:31 Wednesday, March 8, 2023 207

PROJECT NUMBER	ITEM NUMBER/ PROJECT LOCATION	ITEM DESCRIPTION/ PROJECT LOCATION	DATE LET	UNIT/ QUANTITY	ENGR. EST.	AVERAGE BID	AWARDED BID
===== 240-00010		Rem of Nests		Hour =====			
BR012A-048		CO 12 STRUCTURE P-17-F AT MP	12/22/22	20.00	100.00	114.07	142.00
	WEIGHTED AVERAGE FOR THE FOURTH QUARTER			528.00	115.22	151.32	146.23
	WEIGHTED AVERAGE FOR THE YEAR			1,567.00	122.04	143.32	118.07
===== 240-00017		Protect Migratory Birds		LUMP SUM =====			
TRG0253-264		I-25 AND SH 119 PARK-N-RIDE	10/27/22	1.00	9000.00	10220.45	3500.00
	WEIGHTED AVERAGE FOR THE FOURTH QUARTER			1.00	9000.00	10220.45	3500.00
	WEIGHTED AVERAGE FOR THE YEAR			1.00	9000.00	10220.45	3500.00
===== 240-00020		Netting		Sq Yard =====			
STA 067A-048		Hwy 67A MP 0.00 TO MP 11.05 I	03/03/22	4,500.00	10.00	7.08	4.00
NHPP 0761-238		I-76 DAHLIA TO YORK	03/10/22	300.00	32.00	11.15	10.00
C0761-239			03/17/22	200.00	15.00	35.00	6.00
BRC040-057			03/31/22	20.00	10.00	41.85	57.00
NHM765-007							
	WEIGHTED AVERAGE FOR THE FIRST QUARTER			5,020.00	11.51	9.12	4.65
STM1151-038		SH115 MP 27 TO MP 38	04/21/22	178.00	8.50	15.51	12.00
	WEIGHTED AVERAGE FOR THE SECOND QUARTER			178.00	8.50	15.51	12.00
SHE2873-193		US 287 & CO 52 INTERSECTION I	09/15/22	50.00	25.00	25.89	79.00
	WEIGHTED AVERAGE FOR THE THIRD QUARTER			50.00	25.00	25.89	79.00
STA207A-004		Resurfacing SH207A MANZANOLA	10/27/22	200.00	35.00	13.30	9.90
SHE0242-087		US 24 SAFETY IMPRVMENTS, E OF	11/03/22	20.00	27.00	38.54	43.62
STAM420-001		US 285 AT HWY 9C IMPROVEMENTS	12/01/22	1,400.00	27.00	8.35	7.59

COLORADO DEPARTMENT OF TRANSPORTATION
 ITEM UNIT COSTS BY PROJECTS -- 2022 COST DATA

11:31 Wednesday, March 8, 2023 208

PROJECT NUMBER	ITEM NUMBER/ PROJECT LOCATION	ITEM DESCRIPTION/ PROJECT LOCATION	DATE LET	UNIT/ QUANTITY	ENGR. EST.	AVERAGE BID	AWARDED BID
===== 240-00020							
		Netting		Sq Yard			
BR2854-148		INTERSECTION OF US 285 & SH 9					
STM0091-046		ADA RAMP IMPROVEMENTS - FAIRP					
STR109A-019		M-22-AY BRIDGE REHAB ON SH109	12/01/22	6,100.00	7.00	14.26	9.51
STA385A-016		SH 385 MP 97.76	12/22/22	100.00	10.00	22.82	31.25
		WEIGHTED AVERAGE FOR THE FOURTH QUARTER		7,820.00	11.39	12.88	9.61
		WEIGHTED AVERAGE FOR THE YEAR		13,068.00	11.45	11.35	8.01
===== 240-00100							
		Prairie Dog Mgmt		LUMP SUM			
NHPP 0761-238		I-76 DAHLIA TO YORK	03/10/22	1.00	10000.00	13672.35	15000.00
C0761-239							
		WEIGHTED AVERAGE FOR THE FIRST QUARTER		1.00	10000.00	13672.35	15000.00
C1211-099		SH 121 NORTH SGA SIGNALS	08/25/22	1.00	5000.00	17500.00	18000.00
		WEIGHTED AVERAGE FOR THE THIRD QUARTER		1.00	5000.00	17500.00	18000.00
TRG0253-264		I-25 AND SH 119 PARK-N-RIDE	10/27/22	1.00	28000.00	23036.31	25000.00
		WEIGHTED AVERAGE FOR THE FOURTH QUARTER		1.00	28000.00	23036.31	25000.00
		WEIGHTED AVERAGE FOR THE YEAR		3.00	14333.33	18259.41	19333.33
===== 250-00010							
		Envir Health/Safety Mngmt		LUMP SUM			
NHPP0702-383		I-70 EB AUX FRISCO TO SILVERT	01/13/22	1.00	10000.00	4864.84	3700.00
NHPP0063-063			02/24/22	1.00	5000.00	6075.00	7500.00
ER007A-035			03/15/22	1.00	43000.00	45000.00	45000.00
		WEIGHTED AVERAGE FOR THE FIRST QUARTER		3.00	19333.33	10184.28	18733.33
NHPP0063-054		US 6 FROM I70-B TO 33 RD. (MP	08/18/22	1.00	5000.00	4805.89	7500.00

COLORADO DEPARTMENT OF TRANSPORTATION
 ITEM UNIT COSTS BY PROJECTS -- 2022 COST DATA

11:31 Wednesday, March 8, 2023 209

PROJECT NUMBER	ITEM NUMBER/ PROJECT LOCATION	ITEM DESCRIPTION/ PROJECT LOCATION	DATE LET	UNIT/ QUANTITY	ENGR. EST.	AVERAGE BID	AWARDED BID
=====	250-00010	Envir Health/Safety Mngmt		LUMP SUM	=====	=====	=====
C1211-099		SH 121 NORTH SGA SIGNALS	08/25/22	1.00	30000.00	13750.00	15000.00
2670703-497		I-70 GENESEE WILDLIFE XING	09/15/22	1.00	10000.00	6449.31	11358.87
NHPP0701-231		I-70 SALT WASH BRIDGES SCOUR	09/29/22	1.00	15000.00	37902.47	65000.00
		WEIGHTED AVERAGE FOR THE THIRD QUARTER		4.00	15000.00	12158.60	24714.72
STU0252-457		I-25:ALAMEDA RIVER PH 2.0	11/03/22	1.00	75000.00	38594.92	4400.00
NHPP0063-048		US6 / 20 ROAD INTERSECTION IM	12/15/22	1.00	10000.00	16800.03	5000.00
		WEIGHTED AVERAGE FOR THE FOURTH QUARTER		2.00	42500.00	21068.09	4133.33
		WEIGHTED AVERAGE FOR THE YEAR		9.00	22555.56	14727.66	16745.89
=====	250-00050	Monitoring Technician		Hour	=====	=====	=====
NHPP0063-063			02/24/22	40.00	140.00	124.00	48.00
NHPP 0761-238		I-76 DAHLIA TO YORK	03/10/22	30.00	140.00	132.45	115.00
C0761-239							
		WEIGHTED AVERAGE FOR THE FIRST QUARTER		70.00	140.00	130.34	76.71
NHPP0063-054		US 6 FROM I70-B TO 33 RD. (MP	08/18/22	40.00	140.00	245.63	265.00
C1211-099		SH 121 NORTH SGA SIGNALS	08/25/22	20.00	150.00	170.00	210.00
NHPP0701-231		I-70 SALT WASH BRIDGES SCOUR	09/29/22	10.00	200.00	142.53	150.00
		WEIGHTED AVERAGE FOR THE THIRD QUARTER		70.00	151.43	209.29	232.86
STU0252-457		I-25:ALAMEDA RIVER PH 2.0	11/03/22	1,000.00	135.00	98.33	99.00
NHPP0063-048		US6 / 20 ROAD INTERSECTION IM	12/15/22	10.00	78.00	197.79	45.00
		WEIGHTED AVERAGE FOR THE FOURTH QUARTER		1,010.00	134.44	103.96	102.25
		WEIGHTED AVERAGE FOR THE YEAR		1,150.00	135.81	110.03	108.23
=====	250-00100	Environmental Health and Safety		LUMP SUM	=====	=====	=====
STR R500-171		Various locations on SH 141 a	03/17/22	1.00	7850.00	13902.67	30000.00
		WEIGHTED AVERAGE FOR THE FIRST QUARTER		1.00	7850.00	13902.67	30000.00
		WEIGHTED AVERAGE FOR THE YEAR		1.00	7850.00	13902.67	30000.00

COLORADO DEPARTMENT OF TRANSPORTATION
ITEM UNIT COSTS BY PROJECTS -- 2022 COST DATA

11:31 Wednesday, March 8, 2023 210

PROJECT NUMBER	ITEM NUMBER/ PROJECT LOCATION	ITEM DESCRIPTION/ PROJECT LOCATION	DATE LET	UNIT/ QUANTITY	ENGR. EST.	AVERAGE BID	AWARDED BID
===== 250-00110		Health and Safety Officer		Hour	=====	=====	=====
NHPP0702-383		I-70 EB AUX FRISCO TO SILVERT	01/13/22	80.00	200.00	108.79	150.00
NHPP0063-063			02/24/22	20.00	130.00	195.50	170.00
NHPP 0761-238		I-76 DAHLIA TO YORK	03/10/22	20.00	160.00	115.24	125.00
C0761-239							
STR R500-171		Various locations on SH 141 a	03/17/22	60.00	300.00	79.08	50.00
		WEIGHTED AVERAGE FOR THE FIRST QUARTER		180.00	221.11	107.70	116.11
CM760-047		COLFAX AND QUAIL	05/12/22	16.00	130.00	117.40	107.00
		WEIGHTED AVERAGE FOR THE SECOND QUARTER		16.00	130.00	117.40	107.00
NHPP0063-054		US 6 FROM I70-B TO 33 RD. (MP	08/18/22	40.00	150.00	180.27	265.00
C1211-099		SH 121 NORTH SGA SIGNALS	08/25/22	8.00	150.00	187.50	245.00
NHPP0701-231		I-70 SALT WASH BRIDGES SCOUR	09/29/22	10.00	200.00	161.44	150.00
		WEIGHTED AVERAGE FOR THE THIRD QUARTER		58.00	158.62	178.02	242.41
STU0252-457		I-25:ALAMEDA RIVER PH 2.0	11/03/22	650.00	150.00	121.12	120.00
NHPP0063-048		US6 / 20 ROAD INTERSECTION IM	12/15/22	10.00	200.00	226.52	125.00
		WEIGHTED AVERAGE FOR THE FOURTH QUARTER		660.00	150.76	126.25	125.47
		WEIGHTED AVERAGE FOR THE YEAR		914.00	164.75	123.46	130.30
===== 250-00120		Material Sampling and Delivery		Each	=====	=====	=====
NHPP0702-383		I-70 EB AUX FRISCO TO SILVERT	01/13/22	2.00	2000.00	474.05	86.00
		WEIGHTED AVERAGE FOR THE FIRST QUARTER		2.00	2000.00	474.05	86.00
NHPP0063-054		US 6 FROM I70-B TO 33 RD. (MP	08/18/22	10.00	200.00	250.98	150.00
		WEIGHTED AVERAGE FOR THE THIRD QUARTER		10.00	200.00	250.98	150.00
		WEIGHTED AVERAGE FOR THE YEAR		12.00	500.00	325.34	139.33

COLORADO DEPARTMENT OF TRANSPORTATION
ITEM UNIT COSTS BY PROJECTS -- 2022 COST DATA

11:31 Wednesday, March 8, 2023 211

PROJECT NUMBER	ITEM NUMBER/ PROJECT LOCATION	ITEM DESCRIPTION/ PROJECT LOCATION	DATE LET	UNIT/ QUANTITY	ENGR. EST.	AVERAGE BID	AWARDED BID
=====	250-00200	Material Handling (Stockpile)		Cubic Yard	=====		
NHPP0063-054		US 6 FROM I70-B TO 33 RD.	08/18/22	1,415.00	30.00	26.69	17.00
		WEIGHTED AVERAGE FOR THE THIRD QUARTER		1,415.00	30.00	26.69	17.00
STU0252-457		I-25:ALAMEDA RIVER PH 2.0	11/03/22	5,000.00	45.00	25.30	23.00
		WEIGHTED AVERAGE FOR THE FOURTH QUARTER		5,000.00	45.00	25.30	23.00
		WEIGHTED AVERAGE FOR THE YEAR		6,415.00	41.69	25.52	21.68
=====	250-00204	Materials Management Plan		LUMP SUM	=====		
ER007A-035			03/15/22	1.00	40550.00	40000.00	40000.00
		WEIGHTED AVERAGE FOR THE FIRST QUARTER		1.00	40550.00	40000.00	40000.00
		WEIGHTED AVERAGE FOR THE YEAR		1.00	40550.00	40000.00	40000.00
=====	250-00210	Solid Waste Disposal		Cubic Yard	=====		
NHPP1601-083			02/03/22	20.00	400.00	456.61	200.00
NHPP0063-063			02/24/22	85.00	100.00	189.00	155.00
		WEIGHTED AVERAGE FOR THE FIRST QUARTER		105.00	157.14	239.97	163.57
STU0252-457		I-25:ALAMEDA RIVER PH 2.0	11/03/22	5,000.00	80.00	74.01	43.50
		WEIGHTED AVERAGE FOR THE FOURTH QUARTER		5,000.00	80.00	74.01	43.50
		WEIGHTED AVERAGE FOR THE YEAR		5,105.00	81.59	76.30	45.97
=====	250-00224	Hazardous Waster Disposal (Radioactive)		Cubic Yard	=====		
NHPP0063-063			02/24/22	100.00	85.00	177.00	64.00
		WEIGHTED AVERAGE FOR THE FIRST QUARTER		100.00	85.00	177.00	64.00

COLORADO DEPARTMENT OF TRANSPORTATION
 ITEM UNIT COSTS BY PROJECTS -- 2022 COST DATA

11:31 Wednesday, March 8, 2023 212

PROJECT NUMBER	ITEM NUMBER/ PROJECT LOCATION	ITEM DESCRIPTION/ PROJECT LOCATION	DATE LET	UNIT/ QUANTITY	ENGR. EST.	AVERAGE BID	AWARDED BID
===== 250-00224		Hazardous Waster Disposal (Radioactive)		Cubic Yard	=====		
NHPP0063-054		US 6 FROM I70-B TO 33 RD. (MP 08/18/22		1,415.00	30.00	29.33	28.00
	WEIGHTED AVERAGE FOR THE THIRD QUARTER			1,415.00	30.00	29.33	28.00
NHPP0063-048		US6 / 20 ROAD INTERSECTION IM 12/15/22		50.00	150.00	285.23	766.00
	WEIGHTED AVERAGE FOR THE FOURTH QUARTER			50.00	150.00	285.23	766.00
	WEIGHTED AVERAGE FOR THE YEAR			1,565.00	37.35	54.31	53.88
===== 304-01000		ABC (CL 1)		Ton	=====		
STR092A-031			03/17/22	6,091.39	30.00	38.00	38.00
	WEIGHTED AVERAGE FOR THE FIRST QUARTER			6,091.39	30.00	38.00	38.00
NHPP0502-090		SH 50 MP 134.6-136 GUNNISON C 12/22/22		18,884.00	30.00	33.61	36.59
	WEIGHTED AVERAGE FOR THE FOURTH QUARTER			18,884.00	30.00	33.61	36.59
	WEIGHTED AVERAGE FOR THE YEAR			24,975.39	30.00	33.88	36.93
===== 304-01005		ABC (CL 1)		Cubic Yard	=====		
NHPP0702-383		I-70 EB AUX FRISCO TO SILVERT 01/13/22		20,654.00	25.00	65.09	67.00
	WEIGHTED AVERAGE FOR THE FIRST QUARTER			20,654.00	25.00	65.09	67.00
NHPP0702-414 FBR0702-423		VAIL PASS AUX PHASE 1 CAP 3 07/08/22		2,115.00	42.35	42.35	42.35
	WEIGHTED AVERAGE FOR THE THIRD QUARTER			2,115.00	42.35	42.35	42.35

COLORADO DEPARTMENT OF TRANSPORTATION
 ITEM UNIT COSTS BY PROJECTS -- 2022 COST DATA

11:31 Wednesday, March 8, 2023 213

PROJECT NUMBER	ITEM NUMBER/ PROJECT LOCATION	ITEM DESCRIPTION/ PROJECT LOCATION	DATE LET	UNIT/ QUANTITY	ENGR. EST.	AVERAGE BID	AWARDED BID
=====	304-01005	ABC (CL 1)		Cubic Yard	=====		
C5502-097		US550 MP 117.28-126.06	11/17/22	34,089.00	45.00	52.15	54.20
		WEIGHTED AVERAGE FOR THE FOURTH QUARTER		34,089.00	45.00	52.15	54.20
		WEIGHTED AVERAGE FOR THE YEAR		56,858.00	37.64	58.49	58.41
=====	304-02000	ABC (CL 2)		Ton	=====		
NHPP1601-083			02/03/22	67,481.00	20.00	24.18	28.00
		WEIGHTED AVERAGE FOR THE FIRST QUARTER		67,481.00	20.00	24.18	28.00
STR114A-015		SH114 SILLSVILLE SOUTH TO MP3	12/01/22	4,000.29	60.00	41.00	37.00
		WEIGHTED AVERAGE FOR THE FOURTH QUARTER		4,000.29	60.00	41.00	37.00
		WEIGHTED AVERAGE FOR THE YEAR		71,481.29	22.24	25.12	28.50
=====	304-03000	ABC (CL 3)		Ton	=====		
NHPP0063-054		US 6 FROM I70-B TO 33 RD. (MP	08/18/22	6,650.00	32.00	27.34	32.50
		WEIGHTED AVERAGE FOR THE THIRD QUARTER		6,650.00	32.00	27.34	32.50
NHPP0502-090		SH 50 MP 134.6-136 GUNNISON C	12/22/22	120.00	50.00	57.82	51.25
		WEIGHTED AVERAGE FOR THE FOURTH QUARTER		120.00	50.00	57.82	51.25
		WEIGHTED AVERAGE FOR THE YEAR		6,770.00	32.32	28.65	32.83
=====	304-03005	ABC (CL 3)		Cubic Yard	=====		
NHPP0702-383		I-70 EB AUX FRISCO TO SILVERT	01/13/22	266.00	30.00	94.80	75.00
		WEIGHTED AVERAGE FOR THE FIRST QUARTER		266.00	30.00	94.80	75.00

COLORADO DEPARTMENT OF TRANSPORTATION
ITEM UNIT COSTS BY PROJECTS -- 2022 COST DATA

11:31 Wednesday, March 8, 2023 214

PROJECT NUMBER	ITEM NUMBER/ PROJECT LOCATION	ITEM DESCRIPTION/ PROJECT LOCATION	DATE LET	UNIT/ QUANTITY	ENGR. EST.	AVERAGE BID	AWARDED BID
===== 304-03005	ABC (CL 3)			Cubic Yard	=====		
C5502-097		US550 MP 117.28-126.06	11/17/22	329.00	65.00	46.01	43.80
NHPP0701-252		I-70 RIFLE TO SILT SLAB REPLA	12/01/22	225.00	30.00	327.50	410.00
		WEIGHTED AVERAGE FOR THE FOURTH QUARTER		554.00	50.79	134.16	192.53
		WEIGHTED AVERAGE FOR THE YEAR		820.00	44.04	115.24	154.40
===== 304-06000	ABC (CL 6)			Ton	=====		
NHPP2873-189		US 287 (FEDERAL BLVD) - COLFA	01/06/22	847.00	60.00	88.46	59.54
NHPP1601-083			02/03/22	31,010.00	20.00	25.18	29.00
STA0252-459			02/03/22	220.00	40.00	80.45	100.00
NHPP0063-063			02/24/22	3,281.00	30.00	51.90	70.00
NHPP0703-472			03/10/22	20.00	25.00	171.79	175.00
CR100-362			03/14/22	500.00	121.66	121.66	121.66
STR092A-031			03/17/22	4,568.53	32.00	39.00	39.00
		WEIGHTED AVERAGE FOR THE FIRST QUARTER		40,446.53	24.37	32.24	35.70
NH0504-911			04/07/22	896.00	40.00	37.50	35.00
CC030-081		ADA RAMP AND CURBS - FT. LUPT	04/14/22	1,840.00	55.00	58.57	32.00
NHPP0702-413		VAIL PASS AUX PHASE 1 CAP 2	04/18/22	3,708.00	55.37	55.37	55.37
STM1151-038		SH115 MP 27 TO MP 38	04/21/22	37,707.00	26.00	25.70	22.69
MTCE2873-204		MTCE FY22 SH287 CONC PANEL RE	05/05/22	34.00	150.00	168.76	107.52
NHC540-017		R2 CHAINUP STA @ KENOSHA/HOOS	05/12/22	4,958.00	35.00	45.00	55.00
NHPP 3851-018		US 385 NORTH OF CHEYENNE WELL	05/26/22	200.00	30.00	63.50	66.00
FSA3921-019		SH 392 AND WCR 55 ISLANDS	06/02/22	95.00	90.00	62.33	60.00
NHPP072A-047		SH-72 RESURFACING: I-70 TO IN	06/09/22	488.00	50.00	49.01	49.01
		WEIGHTED AVERAGE FOR THE SECOND QUARTER		49,926.00	30.85	28.69	29.45
NHPP0063-054		US 6 FROM I70-B TO 33 RD. (MP	08/18/22	7,476.00	40.00	75.89	85.00
C1211-099		SH 121 NORTH SGA SIGNALS	08/25/22	24.00	300.00	157.50	150.00
ER0502-092		US 50 MP 204 EB MONARCH TRUCK	08/29/22	24.00	22.50	122.94	84.50
		WEIGHTED AVERAGE FOR THE THIRD QUARTER		7,524.00	40.77	76.37	85.21

COLORADO DEPARTMENT OF TRANSPORTATION
 ITEM UNIT COSTS BY PROJECTS -- 2022 COST DATA

11:31 Wednesday, March 8, 2023 215

PROJECT NUMBER	ITEM NUMBER/ PROJECT LOCATION	ITEM DESCRIPTION/ PROJECT LOCATION	DATE LET	UNIT/ QUANTITY	ENGR. EST.	AVERAGE BID	AWARDED BID
=====	304-06000	ABC (CL 6)		Ton	=====	=====	=====
FSAM240-200		SH21B CO SPRINGS SIGNAL REPLA	10/27/22	160.00	40.00	214.43	66.70
TRG0253-264		I-25 AND SH 119 PARK-N-RIDE	10/27/22	6,996.00	45.00	38.32	32.00
STR064A-010		SH 64 AND SH 13 AT MEEKER	11/10/22	5,428.00	50.00	40.85	41.00
STRC090-011		US 50B AND SH71/CR18 INTERSEC	11/17/22	1,928.00	35.00	83.75	71.50
STAM420-001		US 285 AT HWY 9C IMPROVEMENTS	12/01/22	15,414.00	18.00	41.25	50.00
BR2854-148		INTERSECTION OF US 285 & SH 9					
STM0091-046		ADA RAMP IMPROVEMENTS - FAIRP					
STR114A-015		SH114 SILLSVILLE SOUTH TO MP3	12/01/22	2,000.20	65.00	68.00	40.00
NHPP0701-252		I-70 RIFLE TO SILT SLAB REPLA	12/01/22	144.00	80.00	294.00	410.00
STR318A-001		SH 318 MP 0 - 12.5 MOFFAT COU	12/01/22	15,292.00	40.00	59.83	59.70
NHPP0021-041		SH2 RESURFACING MLK TO 52ND	12/01/22	68.30	110.00	145.07	85.32
NHPP0931-033		SH93:US6 TO 58TH RESURFACING	12/15/22	1,854.00	50.00	42.76	43.55
NHPP0502-090		SH 50 MP 134.6-136 GUNNISON C	12/22/22	7,427.00	75.00	36.54	38.50
		WEIGHTED AVERAGE FOR THE FOURTH QUARTER		56,711.50	41.40	43.30	45.25
		WEIGHTED AVERAGE FOR THE YEAR		154,608.03	33.51	37.25	40.08
=====	304-06007	ABC (CL 6)		Cubic Yard	=====	=====	=====
NH0504-910		US50B L-24-B MIN REP AT MP 40	01/13/22	592.00	75.00	83.08	50.00
NHPP0702-383		I-70 EB AUX FRISCO TO SILVERT	01/13/22	2,586.00	41.00	96.93	66.00
STR0141-031			02/17/22	691.00	40.00	104.75	76.25
NHPP 0761-238		I-76 DAHLIA TO YORK	03/10/22	16,146.00	60.00	46.94	41.00
C0761-239							
ER007A-035			03/15/22	54.00	244.50	157.65	157.65
STR092A-031			03/17/22	484.00	70.00	70.00	70.00
NHM765-007			03/31/22	11,853.00	65.00	84.81	55.52
		WEIGHTED AVERAGE FOR THE FIRST QUARTER		32,406.00	60.62	59.38	49.85
2670703-479		I-70 BRIDGE OVER HARLAN	05/05/22	3,307.00	45.00	59.90	62.00
STA0712-019		SH 71: Frieght Improvements	05/12/22	21,354.00	65.00	82.42	82.42
STA001A-005		SH1 WELLINGTON SOUTH RESURFAC	05/12/22	158.00	58.00	63.90	40.00
FSA052A-046		SH52 WCR 37 INTERSECTION IMPR	06/09/22	6,083.00	60.00	62.39	48.00
		WEIGHTED AVERAGE FOR THE SECOND QUARTER		30,902.00	61.84	67.66	73.24
NHPP0702-414		VAIL PASS AUX PHASE 1 CAP 3	07/08/22	2,706.00	98.08	98.08	98.08

COLORADO DEPARTMENT OF TRANSPORTATION
 ITEM UNIT COSTS BY PROJECTS -- 2022 COST DATA

11:31 Wednesday, March 8, 2023 216

PROJECT NUMBER	ITEM NUMBER/ PROJECT LOCATION	ITEM DESCRIPTION/ PROJECT LOCATION	DATE LET	UNIT/ QUANTITY	ENGR. EST.	AVERAGE BID	AWARDED BID
===== 304-06007	ABC (CL 6)			Cubic Yard	=====		
FBR0702-423		VAIL PASS AUX BE F-12-AT PHAS					
FSA052A-057		SH52 BOX CULVERT EXTENSION (M	08/04/22	51.00	150.00	222.62	222.53
BR0343-046		US 34 TIMBER BRIDGE REPL. PKG	08/31/22	794.00	76.05	87.81	87.81
FBR0343-047		US 6/US 34 TIMBER BRIDGE REPL					
2670403-065		US40 FLOYD HILL ROUNDABOUTS	09/15/22	2,545.00	70.00	71.95	67.00
2670703-497		I-70 GENESEE WILDLIFE XING	09/15/22	584.00	94.00	88.67	87.47
SHE2873-193		US 287 & CO 52 INTERSECTION I	09/15/22	3,124.00	85.00	52.03	28.00
NHPP0701-231		I-70 SALT WASH BRIDGES SCOUR	09/29/22	45.00	250.00	174.16	58.00
	WEIGHTED AVERAGE FOR THE THIRD QUARTER			9,849.00	85.62	66.41	66.82
STA207A-004		Resurfacing SH207A MANZANOLA	10/27/22	526.00	60.00	93.00	78.00
C170A-002		CRITICAL CULVERT CONST. PKG D	10/27/22	39.00	225.00	240.31	56.25
STA3852-015		US 385 HOLYOKE NORTH	10/27/22	9,545.00	100.00	102.00	102.00
NHPP0343-048		US 34 (MP 169.3-171.4)	11/01/22	164.00	49.00	142.98	102.00
STU0252-457		I-25:ALAMEDA RIVER PH 2.0	11/03/22	2,091.00	70.00	112.39	82.00
SHE0242-087		US 24 SAFETY IMPRVMENTS, E OF	11/03/22	544.00	70.00	137.40	107.20
NHPP0853-126		US85C: PLATTEVILLE NORTH MP (11/10/22	688.00	70.00	73.63	46.15
C5502-097		US550 MP 117.28-126.06	11/17/22	12,725.00	60.00	57.90	54.60
STAM420-001		US 285 AT HWY 9C IMPROVEMENTS	12/01/22	15.00	64.40	531.73	221.06
BR2854-148		INTERSECTION OF US 285 & SH 9					
STM0091-046		ADA RAMP IMPROVEMENTS - FAIRP					
STA0711-021		SH71: REGION LINE NORTH	12/01/22	62.00	74.00	165.00	100.00
2670703-487		I-70 BRIDGES OVER WARD ROAD-	12/01/22	2,093.00	45.00	55.55	52.00
NHPP0701-252		I-70 RIFLE TO SILT SLAB REPLA	12/01/22	37.00	61.00	330.00	410.00
IM025A-050		I25-MP103.9 - INTERSECTION DR	12/01/22	3,443.00	43.19	77.83	55.00
NHPP0063-048		US6 / 20 ROAD INTERSECTION IM	12/15/22	3,388.00	68.00	80.61	72.00
FSA0853-122		WCR14.5 AND US-85, FORT LUPTO	12/15/22	101.00	150.00	150.58	122.00
STA0361-129		US 36: HYGIENE RD AND NELSON	12/22/22	226.50	70.00	100.94	122.33
BR012A-048		CO 12 STRUCTURE P-17-F AT MP	12/22/22	533.00	65.00	108.00	130.00
STA385A-016		SH 385 MP 97.76	12/22/22	2,264.00	60.00	115.96	70.83
	WEIGHTED AVERAGE FOR THE FOURTH QUARTER			38,484.50	69.68	79.26	73.44
	WEIGHTED AVERAGE FOR THE YEAR			111,641.50	66.28	66.84	65.95
===== 304-06008	ABC (CL 6) (Spec)			Cubic Yard	=====		
NHPP0703-472			03/10/22	141.00	50.00	154.79	95.00
	WEIGHTED AVERAGE FOR THE FIRST QUARTER			141.00	50.00	154.79	95.00
STA0712-019		SH 71: Frieght Improvements	05/12/22	3,735.00	70.00	94.37	94.37

COLORADO DEPARTMENT OF TRANSPORTATION
ITEM UNIT COSTS BY PROJECTS -- 2022 COST DATA

11:31 Wednesday, March 8, 2023 217

PROJECT NUMBER	ITEM NUMBER/ PROJECT LOCATION	ITEM DESCRIPTION/ PROJECT LOCATION	DATE LET	UNIT/ QUANTITY	ENGR. EST.	AVERAGE BID	AWARDED BID
=====	304-06008	ABC (CL 6) (Spec)		Cubic Yard	=====	=====	=====
STA001A-005		SH1 WELLINGTON SOUTH RESURFAC	05/12/22	3,470.00	60.00	51.65	42.00
FSA3921-019		SH 392 AND WCR 55 ISLANDS	06/02/22	13.00	53.00	173.67	250.00
		WEIGHTED AVERAGE FOR THE SECOND QUARTER		7,218.00	65.16	66.99	69.47
NHPP0853-126		US85C: PLATTEVILLE NORTH MP (11/10/22	3,752.00	55.00	52.38	53.10
STA0711-021		SH71: REGION LINE NORTH	12/01/22	9,607.00	50.00	84.58	80.00
STA0361-129		US 36: HYGIENE RD AND NELSON	12/22/22	440.00	80.00	92.65	108.91
		WEIGHTED AVERAGE FOR THE FOURTH QUARTER		13,799.00	52.32	72.80	73.61
		WEIGHTED AVERAGE FOR THE YEAR		21,158.00	56.68	72.54	72.34
=====	304-06009	ABC (CL 6) (Spec)		Ton	=====	=====	=====
NHPP1601-083			02/03/22	8,585.00	22.00	22.90	25.00
		WEIGHTED AVERAGE FOR THE FIRST QUARTER		8,585.00	22.00	22.90	25.00
NHPP 3851-018		US 385 NORTH OF CHEYENNE WELL	05/26/22	1,317.00	30.00	60.50	56.00
		WEIGHTED AVERAGE FOR THE SECOND QUARTER		1,317.00	30.00	60.50	56.00
		WEIGHTED AVERAGE FOR THE YEAR		9,902.00	23.06	27.90	29.12
=====	304-07000	ABC (CL 7)		Ton	=====	=====	=====
STR092A-031			03/17/22	3,190.43	30.00	32.00	32.00
		WEIGHTED AVERAGE FOR THE FIRST QUARTER		3,190.43	30.00	32.00	32.00
NHPP0821-114		SH 82 ASPEN/INDEPENDENCE PASS	10/13/22	231.82	40.00	127.23	81.70
NHPP0701-253		I-70 EAST OF DEBEQUE	10/27/22	3,360.00	35.00	39.50	40.70
STR114A-015		SH114 SILLSVILLE SOUTH TO MP3	12/01/22	16,197.93	55.00	37.50	42.00
NHPP0502-090		SH 50 MP 134.6-136 GUNNISON C	12/22/22	1,307.00	35.00	46.35	69.11
		WEIGHTED AVERAGE FOR THE FOURTH QUARTER		21,096.75	50.41	40.38	43.91
		WEIGHTED AVERAGE FOR THE YEAR		24,287.18	47.73	39.84	42.34

COLORADO DEPARTMENT OF TRANSPORTATION
ITEM UNIT COSTS BY PROJECTS -- 2022 COST DATA

11:31 Wednesday, March 8, 2023 218

PROJECT NUMBER	ITEM NUMBER/ PROJECT LOCATION	ITEM DESCRIPTION/ PROJECT LOCATION	DATE LET	UNIT/ QUANTITY	ENGR. EST.	AVERAGE BID	AWARDED BID
=====	304-07005	ABC (CL 7)		Cubic Yard	=====		
STR0141-031			02/17/22	1,675.00	40.00	77.00	60.00
		WEIGHTED AVERAGE FOR THE FIRST QUARTER		1,675.00	40.00	77.00	60.00
C5502-097		US550 MP 117.28-126.06	11/17/22	4,021.00	75.00	68.28	80.90
NHPP0063-048		US6 / 20 ROAD INTERSECTION IM	12/15/22	174.00	80.00	96.15	81.00
STR0092-024		SH 9 North of Silverthorne	12/22/22	679.00	80.00	121.00	117.00
		WEIGHTED AVERAGE FOR THE FOURTH QUARTER		4,874.00	75.88	74.72	85.93
		WEIGHTED AVERAGE FOR THE YEAR		6,549.00	66.70	75.32	79.30
=====	304-07009	ABC (CL 7) (Spec)		Ton	=====		
C0762-055			02/17/22	5,032.00	40.00	37.04	33.00
		WEIGHTED AVERAGE FOR THE FIRST QUARTER		5,032.00	40.00	37.04	33.00
		WEIGHTED AVERAGE FOR THE YEAR		5,032.00	40.00	37.04	33.00
=====	304-08000	ABC (Shoulder Material)		Ton	=====		
ER007A-035			03/15/22	5,023.00	30.15	32.25	32.25
		WEIGHTED AVERAGE FOR THE FIRST QUARTER		5,023.00	30.15	32.25	32.25
STR096A-050		SH 96 MP 168.99 TO 193.77	12/22/22	5,755.00	30.00	59.33	48.00
		WEIGHTED AVERAGE FOR THE FOURTH QUARTER		5,755.00	30.00	59.33	48.00
		WEIGHTED AVERAGE FOR THE YEAR		10,778.00	30.07	53.23	40.66
=====	304-08002	ABC (Shoulder Material)		Cubic Yard	=====		
STR160A-034		US160A LA VETA PASS EAST SURF	03/17/22	955.00	60.00	69.04	58.07
		WEIGHTED AVERAGE FOR THE FIRST QUARTER		955.00	60.00	69.04	58.07

COLORADO DEPARTMENT OF TRANSPORTATION
 ITEM UNIT COSTS BY PROJECTS -- 2022 COST DATA

11:31 Wednesday, March 8, 2023 219

PROJECT NUMBER	ITEM NUMBER/ PROJECT LOCATION	ITEM DESCRIPTION/ PROJECT LOCATION	DATE LET	UNIT/ QUANTITY	ENGR. EST.	AVERAGE BID	AWARDED BID
=====	304-08002	ABC (Shoulder Material)		Cubic Yard	=====		
STA207A-004		Resurfacing SH207A MANZANOLA	10/27/22	1,299.00	60.00	91.40	98.20
SHE0242-087		US 24 SAFETY IMPRVMENTS, E OF	11/03/22	100.00	65.00	180.67	152.01
		WEIGHTED AVERAGE FOR THE FOURTH QUARTER		1,399.00	60.36	95.16	98.51
		WEIGHTED AVERAGE FOR THE YEAR		2,354.00	60.21	89.43	86.52
=====	304-09000	ABC (Spec)		Cubic Yard	=====		
NHPP0702-383		I-70 EB AUX FRISCO TO SILVERT	01/13/22	6,390.00	25.00	29.13	23.50
		WEIGHTED AVERAGE FOR THE FIRST QUARTER		6,390.00	25.00	29.13	23.50
		WEIGHTED AVERAGE FOR THE YEAR		6,390.00	25.00	29.13	23.50
=====	304-09006	ABC (Spec)		Sq Yard	=====		
STA 067A-048		Hwy 67A MP 0.00 TO MP 11.05 I	03/03/22	25,870.00	3.00	4.01	3.60
		WEIGHTED AVERAGE FOR THE FIRST QUARTER		25,870.00	3.00	4.01	3.60
		WEIGHTED AVERAGE FOR THE YEAR		25,870.00	3.00	4.01	3.60
=====	304-09014	ABC (Spec)		Ton	=====		
NHPP1601-083			02/03/22	11,215.00	22.00	30.62	34.00
		WEIGHTED AVERAGE FOR THE FIRST QUARTER		11,215.00	22.00	30.62	34.00
		WEIGHTED AVERAGE FOR THE YEAR		11,215.00	22.00	30.62	34.00
=====	304-09102	ABC (RAP)		Cubic Yard	=====		
STR160A-034		US160A LA VETA PASS EAST SURF	03/17/22	323.00	60.00	42.62	66.24
		WEIGHTED AVERAGE FOR THE FIRST QUARTER		323.00	60.00	42.62	66.24

COLORADO DEPARTMENT OF TRANSPORTATION
 ITEM UNIT COSTS BY PROJECTS -- 2022 COST DATA

11:31 Wednesday, March 8, 2023 220

PROJECT NUMBER	ITEM NUMBER/ PROJECT LOCATION	ITEM DESCRIPTION/ PROJECT LOCATION	DATE LET	UNIT/ QUANTITY	ENGR. EST.	AVERAGE BID	AWARDED BID
=====	304-09102	ABC (RAP)		Cubic Yard	=====		
NHPP0702-413		VAIL PASS AUX PHASE 1 CAP 2	04/18/22	138.00	156.81	156.81	156.81
STM1151-038		SH115 MP 27 TO MP 38	04/21/22	19,371.00	30.00	25.48	11.04
		WEIGHTED AVERAGE FOR THE SECOND QUARTER		19,509.00	30.90	25.67	12.07
NHPP0702-414		VAIL PASS AUX PHASE 1 CAP 3	07/08/22	472.00	141.37	141.37	141.37
FBR0702-423		VAIL PASS AUX BE F-12-AT PHAS					
PAN0761-245		ALONG I-76 & RAMPS MILEPOST 9	09/01/22	216.00	60.00	172.50	90.00
		WEIGHTED AVERAGE FOR THE THIRD QUARTER		688.00	115.82	156.25	125.24
		WEIGHTED AVERAGE FOR THE YEAR		20,520.00	34.20	27.22	17.00
=====	306-01000	Reconditioning		Sq Yard	=====		
NHPP 0761-238		I-76 DAHLIA TO YORK	03/10/22	49,883.00	1.40	3.12	2.20
C0761-239							
		WEIGHTED AVERAGE FOR THE FIRST QUARTER		49,883.00	1.40	3.12	2.20
MTCE2873-204		MTCE FY22 SH287 CONC PANEL RE	05/05/22	113.00	10.00	67.58	13.16
		WEIGHTED AVERAGE FOR THE SECOND QUARTER		113.00	10.00	67.58	13.16
		WEIGHTED AVERAGE FOR THE YEAR		49,996.00	1.42	3.16	2.22
=====	310-00608	Full Depth Reclam. of HMA Pvmt (0-8 in.)		Sq Yard	=====		
STM1151-038		SH115 MP 27 TO MP 38	04/21/22	172,383.00	3.50	1.72	2.71
STA001A-005		SH1 WELLINGTON SOUTH RESURFAC	05/12/22	65,200.00	4.00	4.50	3.00
NHPP 3851-018		US 385 NORTH OF CHEYENNE WELL	05/26/22	58,857.00	6.00	5.13	7.00
		WEIGHTED AVERAGE FOR THE SECOND QUARTER		296,440.00	4.11	2.40	3.63
STR064A-010		SH 64 AND SH 13 AT MEEKER	11/10/22	16,466.00	5.00	10.98	4.65

COLORADO DEPARTMENT OF TRANSPORTATION
ITEM UNIT COSTS BY PROJECTS -- 2022 COST DATA

11:31 Wednesday, March 8, 2023 221

PROJECT NUMBER	ITEM NUMBER/ PROJECT LOCATION	ITEM DESCRIPTION/ PROJECT LOCATION	DATE LET	UNIT/ QUANTITY	ENGR. EST.	AVERAGE BID	AWARDED BID
===== 310-00608	STA0711-021	Full Depth Reclam. of HMA Pvmt (0-8 in.) SH71: REGION LINE NORTH	12/01/22	Sq Yard 247,636.00	3.00	3.63	5.00
		WEIGHTED AVERAGE FOR THE FOURTH QUARTER		264,102.00	3.12	3.94	4.98
		WEIGHTED AVERAGE FOR THE YEAR		560,542.00	3.64	3.04	4.26
===== 310-00610	NHPP0702-383	Full Depth Reclam. of HMA Pvmt (8-12 in.) I-70 EB AUX FRISCO TO SILVERT	01/13/22	Sq Yard 16,432.00	3.00	4.40	2.40
		WEIGHTED AVERAGE FOR THE FIRST QUARTER		16,432.00	3.00	4.40	2.40
STM1151-038 NHPP 3851-018		SH115 MP 27 TO MP 38 US 385 NORTH OF CHEYENNE WELL	04/21/22 05/26/22	43,739.00 4,928.00	3.75 6.00	2.48 6.72	3.65 10.00
		WEIGHTED AVERAGE FOR THE SECOND QUARTER		48,667.00	3.98	2.67	4.29
STA0711-021		SH71: REGION LINE NORTH	12/01/22	11,499.00	3.50	4.66	6.00
		WEIGHTED AVERAGE FOR THE FOURTH QUARTER		11,499.00	3.50	4.66	6.00
		WEIGHTED AVERAGE FOR THE YEAR		76,598.00	3.70	3.28	4.14
===== 310-00614	NHPP1601-083	Full Depth Reclam of HMA Pvmt (12-16 in.)	02/03/22	Sq Yard 156,865.00	3.25	5.33	7.40
		WEIGHTED AVERAGE FOR THE FIRST QUARTER		156,865.00	3.25	5.33	7.40
STM1151-038		SH115 MP 27 TO MP 38	04/21/22	41,166.00	4.50	4.53	7.33
		WEIGHTED AVERAGE FOR THE SECOND QUARTER		41,166.00	4.50	4.53	7.33
		WEIGHTED AVERAGE FOR THE YEAR		198,031.00	3.51	5.01	7.39
===== 310-00700	NHPP1601-083	Asphalt Emulsion Full Depth Reclamation	02/03/22	Sq Yard 190,232.00	3.50	4.56	6.50
		WEIGHTED AVERAGE FOR THE FIRST QUARTER		190,232.00	3.50	4.56	6.50
		WEIGHTED AVERAGE FOR THE YEAR		190,232.00	3.50	4.56	6.50

COLORADO DEPARTMENT OF TRANSPORTATION
ITEM UNIT COSTS BY PROJECTS -- 2022 COST DATA

11:31 Wednesday, March 8, 2023 222

PROJECT NUMBER	ITEM NUMBER/ PROJECT LOCATION	ITEM DESCRIPTION/ PROJECT LOCATION	DATE LET	UNIT/ QUANTITY	ENGR. EST.	AVERAGE BID	AWARDED BID
=====	310-00800	Process Cem Tr Full Depth Reclam		Sq Yard	=====		
STM1151-038		SH115 MP 27 TO MP 38	04/21/22	257,288.00	2.40	3.45	3.13
		WEIGHTED AVERAGE FOR THE SECOND QUARTER		257,288.00	2.40	3.45	3.13
		WEIGHTED AVERAGE FOR THE YEAR		257,288.00	2.40	3.45	3.13
=====	310-00900	Hydraulic Cement		Ton	=====		
STM1151-038		SH115 MP 27 TO MP 38	04/21/22	5,019.00	165.00	228.60	240.00
		WEIGHTED AVERAGE FOR THE SECOND QUARTER		5,019.00	165.00	228.60	240.00
		WEIGHTED AVERAGE FOR THE YEAR		5,019.00	165.00	228.60	240.00
=====	403-00720	HMA (Patching) (Asph)		Ton	=====		
NHPP2873-189		US 287 (FEDERAL BLVD) - COLFA	01/06/22	1,226.00	220.00	199.06	140.63
STR0505-050			01/13/22	6.00	250.00	1311.67	2000.00
NH0504-910		US50B L-24-B MIN REP AT MP 40	01/13/22	55.00	230.00	391.90	446.67
STA0252-459			02/03/22	10.00	200.00	531.03	531.00
C0762-055			02/17/22	517.00	175.00	178.38	172.00
STR0141-031			02/17/22	610.00	400.00	311.67	265.00
NHPP0063-063			02/24/22	4,870.00	180.00	194.00	165.00
STA 067A-048		Hwy 67A MP 0.00 TO MP 11.05 I	03/03/22	200.00	150.00	170.54	190.00
NHPP 0761-238		I-76 DAHLIA TO YORK	03/10/22	482.00	220.00	300.79	250.00
C0761-239							
NHPP0703-472			03/10/22	220.00	180.00	211.75	165.00
CR100-362			03/14/22	60.00	259.77	259.77	259.77
STR160A-034		US160A LA VETA PASS EAST SURF	03/17/22	583.83	170.00	181.95	153.89
STR R500-171		Various locations on SH 141 a	03/17/22	356.00	350.00	511.52	462.00
NHM765-007			03/31/22	776.00	200.00	242.80	222.30
		WEIGHTED AVERAGE FOR THE FIRST QUARTER		9,971.83	207.31	234.74	191.10
NH0504-911			04/07/22	755.00	150.00	193.25	166.50
CC030-081		ADA RAMP AND CURBS - FT. LUPT	04/14/22	471.00	275.00	265.81	300.00
STM1151-038		SH115 MP 27 TO MP 38	04/21/22	1,000.00	180.00	194.56	165.00
2670703-479		I-70 BRIDGE OVER HARLAN	05/05/22	244.00	240.00	297.16	310.76
STA0712-019		SH 71: Frieght Improvements	05/12/22	346.00	175.00	222.54	222.54

COLORADO DEPARTMENT OF TRANSPORTATION
ITEM UNIT COSTS BY PROJECTS -- 2022 COST DATA

11:31 Wednesday, March 8, 2023 223

PROJECT NUMBER	ITEM NUMBER/ PROJECT LOCATION	ITEM DESCRIPTION/ PROJECT LOCATION	DATE LET	UNIT/ QUANTITY	ENGR. EST.	AVERAGE BID	AWARDED BID
=====	403-00720	HMA (Patching) (Asph)		Ton =====			
STA001A-005		SH1 WELLINGTON SOUTH RESURFAC	05/12/22	500.00	185.00	157.50	150.00
NHC540-017		R2 CHAINUP STA @ KENOSHA/HOOS	05/12/22	50.00	200.00	256.00	318.00
CM760-047		COLFAX AND QUAIL	05/12/22	94.00	230.00	376.40	313.00
NHPP 3851-018		US 385 NORTH OF CHEYENNE WELL	05/26/22	800.00	150.00	177.50	165.00
FSA3921-019		SH 392 AND WCR 55 ISLANDS	06/02/22	3.20	250.00	1799.67	1000.00
NHPP072A-047		SH-72 RESURFACING: I-70 TO IN	06/09/22	454.00	190.00	174.75	174.75
FSA052A-046		SH52 WCR 37 INTERSECTION IMPR	06/09/22	50.00	350.00	251.32	241.50
		WEIGHTED AVERAGE FOR THE SECOND QUARTER		4,767.20	186.81	217.21	195.45
NHPP0702-414		VAIL PASS AUX PHASE 1 CAP 3	07/08/22	31.00	369.39	369.39	369.39
FBR0702-423		VAIL PASS AUX BE F-12-AT PHAS					
FSA052A-057		SH52 BOX CULVERT EXTENSION (M	08/04/22	5.00	750.00	358.68	378.04
STR0711-022		SH 71 OVER THE ARKANSAS	08/04/22	60.00	325.00	405.00	325.00
NHPP0063-054		US 6 FROM I70-B TO 33 RD. (MP	08/18/22	509.00	400.00	341.26	275.00
C1211-099		SH 121 NORTH SGA SIGNALS	08/25/22	151.00	400.00	262.50	185.00
BR0343-046		US 34 TIMBER BRIDGE REPL. PKG	08/31/22	3.00	554.31	762.42	762.42
FBR0343-047		US 6/US 34 TIMBER BRIDGE REPL					
PAN0761-245		ALONG I-76 & RAMPS MILEPOST 9	09/01/22	27.00	300.00	710.00	400.00
2670703-497		I-70_GENESEE WILDLIFE KING	09/15/22	208.00	260.00	250.06	232.85
SHE2873-193		US 287 & CO 52 INTERSECTION I	09/15/22	22.00	300.00	345.20	358.00
		WEIGHTED AVERAGE FOR THE THIRD QUARTER		1,016.00	363.33	302.94	265.89
NHPP0821-114		SH 82 ASPEN/INDEPENDENCE PASS	10/13/22	25.00	400.00	640.33	308.00
STA207A-004		Resurfacing SH207A MANZANOLA	10/27/22	225.00	220.00	288.00	224.00
FSAM240-200		SH21B CO SPRINGS SIGNAL REPLA	10/27/22	223.20	300.00	300.50	220.00
C170A-002		CRITICAL CULVERT CONST. PKG D	10/27/22	89.00	250.00	378.20	277.78
STA3852-015		US 385 HOLYOKE NORTH	10/27/22	200.00	225.00	210.00	210.00
NHPP0343-048		US 34 (MP 169.3-171.4)	11/01/22	164.00	230.00	522.19	530.00
STU0252-457		I-25:ALAMEDA RIVER PH 2.0	11/03/22	140.00	500.00	558.28	590.00
STR064A-010		SH 64 AND SH 13 AT MEEKER	11/10/22	92.00	350.00	401.00	460.00
NHPP0853-126		US85C: PLATTEVILLE NORTH MP (11/10/22	500.00	300.00	178.50	167.50
STAM420-001		US 285 AT HWY 9C IMPROVEMENTS	12/01/22	226.00	220.00	281.20	279.56
BR2854-148		INTERSECTION OF US 285 & SH 9					
STM0091-046		ADA RAMP IMPROVEMENTS - FAIRP					
STA0711-021		SH71: REGION LINE NORTH	12/01/22	163.00	250.00	267.00	240.00
2670703-487		I-70 BRIDGES OVER WARD ROAD-	12/01/22	172.00	161.10	274.22	180.00
IM025A-050		I25-MP103.9 - INTERSECTION DR	12/01/22	35.00	200.00	385.00	430.00
STR318A-001		SH 318 MP 0 - 12.5 MOFFAT COU	12/01/22	338.00	350.00	429.00	508.00
NHPP0021-041		SH2 RESURFACING MLK TO 52ND	12/01/22	50.00	350.00	312.15	325.75
NHPP083A-046		SH83 RESURFACING STROH RD TO	12/08/22	800.00	450.00	346.50	270.00

COLORADO DEPARTMENT OF TRANSPORTATION
ITEM UNIT COSTS BY PROJECTS -- 2022 COST DATA

11:31 Wednesday, March 8, 2023 224

PROJECT NUMBER	ITEM NUMBER/ PROJECT LOCATION	ITEM DESCRIPTION/ PROJECT LOCATION	DATE LET	UNIT/ QUANTITY	ENGR. EST.	AVERAGE BID	AWARDED BID
===== 403-00720							
		HMA (Patching) (Asph)		Ton			
FSA0853-122		WCR14.5 AND US-85, FORT LUPTO	12/15/22	34.00	300.00	539.71	400.00
NHPP0931-033		SH93:US6 TO 58TH RESURFACING	12/15/22	258.00	250.00	212.02	136.80
STR0092-024		SH 9 North of Silverthorne	12/22/22	50.00	80.00	524.50	569.00
STA0361-129		US 36: HYGIENE RD AND NELSON	12/22/22	496.00	225.00	198.30	177.01
BR012A-048		CO 12 STRUCTURE P-17-F AT MP	12/22/22	24.00	200.00	201.34	200.00
STA385A-016		SH 385 MP 97.76	12/22/22	175.00	300.00	336.53	261.11
STR096A-050		SH 96 MP 168.99 TO 193.77	12/22/22	208.85	280.00	310.00	400.00
		WEIGHTED AVERAGE FOR THE FOURTH QUARTER		4,688.05	300.91	290.35	278.76
		WEIGHTED AVERAGE FOR THE YEAR		20,443.08	231.75	249.69	217.29
===== 403-00721							
		HMA (Patching) (Asph)		Sq Yard			
STA0252-459			02/03/22	1,500.00	40.00	169.28	93.00
C0762-055			02/17/22	27,366.00	9.75	22.65	22.00
STR133A-051			02/17/22	100.00	300.00	114.67	130.00
STR092A-031			03/17/22	232.00	220.00	95.00	95.00
NHM765-007			03/31/22	37.00	100.00	101.29	85.50
		WEIGHTED AVERAGE FOR THE FIRST QUARTER		29,235.00	14.08	28.87	26.67
ER0502-092		US 50 MP 204 EB MONARCH TRUCK	08/29/22	79.00	150.00	141.57	134.71
		WEIGHTED AVERAGE FOR THE THIRD QUARTER		79.00	150.00	141.57	134.71
STA3852-015		US 385 HOLYOKE NORTH	10/27/22	279.00	95.00	92.00	92.00
SHE0242-087		US 24 SAFETY IMPRVMENTS, E OF	11/03/22	100.00	130.00	108.70	116.11
STAM420-001		US 285 AT HWY 9C IMPROVEMENTS	12/01/22	640.00	27.00	149.42	96.95
BR2854-148		INTERSECTION OF US 285 & SH 9					
STM0091-046		ADA RAMP IMPROVEMENTS - FAIRP					
NHPP0063-048		US6 / 20 ROAD INTERSECTION IM	12/15/22	1,022.00	100.00	101.25	77.00
		WEIGHTED AVERAGE FOR THE FOURTH QUARTER		2,041.00	77.90	125.69	83.37
		WEIGHTED AVERAGE FOR THE YEAR		31,355.00	18.57	35.41	30.97
===== 403-00800							
		Emerg Pothole Rep		Ton			
STM1151-038		SH115 MP 27 TO MP 38	04/21/22	100.00	255.00	324.96	200.00

COLORADO DEPARTMENT OF TRANSPORTATION
ITEM UNIT COSTS BY PROJECTS -- 2022 COST DATA

11:31 Wednesday, March 8, 2023 225

PROJECT NUMBER	ITEM NUMBER/ PROJECT LOCATION	ITEM DESCRIPTION/ PROJECT LOCATION	DATE LET	UNIT/ QUANTITY	ENGR. EST.	AVERAGE BID	AWARDED BID
=====	403-00800	Emerg Pothole Rep		Ton =====			
NHPP072A-047		SH-72 RESURFACING: I-70 TO IN	06/09/22	200.00	600.00	497.01	497.01
		WEIGHTED AVERAGE FOR THE SECOND QUARTER		300.00	485.00	374.12	398.01
2670703-487		I-70 BRIDGES OVER WARD ROAD-	12/01/22	75.00	700.00	545.75	500.00
NHPP0021-041		SH2 RESURFACING MLK TO 52ND	12/01/22	50.00	600.00	556.54	569.31
		WEIGHTED AVERAGE FOR THE FOURTH QUARTER		125.00	660.00	549.50	527.72
		WEIGHTED AVERAGE FOR THE YEAR		425.00	536.47	453.21	436.16
=====	403-09221	SMA (Fibers) (Asph)		Ton =====			
NHPP2873-189		US 287 (FEDERAL BLVD) - COLFA	01/06/22	11,980.30	128.00	149.37	132.48
NHPP 0761-238		I-76 DAHLIA TO YORK	03/10/22	2,642.00	140.00	198.43	185.00
C0761-239							
NHPP0703-472			03/10/22	40,588.00	135.00	136.91	125.00
		WEIGHTED AVERAGE FOR THE FIRST QUARTER		55,210.30	133.72	145.11	129.49
2670703-479		I-70 BRIDGE OVER HARLAN	05/05/22	2,598.00	140.00	195.22	215.00
		WEIGHTED AVERAGE FOR THE SECOND QUARTER		2,598.00	140.00	195.22	215.00
2670403-065		US40_FLOYD HILL ROUNDABOUTS	09/15/22	1,287.00	170.00	280.90	400.00
2670703-497		I-70_GENESEE WILDLIFE KING	09/15/22	4,469.00	220.00	171.42	181.11
		WEIGHTED AVERAGE FOR THE THIRD QUARTER		5,756.00	208.82	183.44	230.05
2670703-487		I-70 BRIDGES OVER WARD ROAD-	12/01/22	1,488.00	180.00	204.74	190.00
NHPP0021-041		SH2 RESURFACING MLK TO 52ND	12/01/22	13,004.00	150.00	150.92	141.89
NHPP083A-046		SH83 RESURFACING STROH RD TO	12/08/22	8,236.00	150.00	243.97	191.94
		WEIGHTED AVERAGE FOR THE FOURTH QUARTER		22,728.00	151.96	176.38	163.18
		WEIGHTED AVERAGE FOR THE YEAR		86,292.30	143.72	157.68	147.65

COLORADO DEPARTMENT OF TRANSPORTATION
 ITEM UNIT COSTS BY PROJECTS -- 2022 COST DATA

11:31 Wednesday, March 8, 2023 226

PROJECT NUMBER	ITEM NUMBER/ PROJECT LOCATION	ITEM DESCRIPTION/ PROJECT LOCATION	DATE LET	UNIT/ QUANTITY	ENGR. EST.	AVERAGE BID	AWARDED BID
=====	403-09500	Furnish HMA		Ton	=====	=====	=====
NH0504-911			04/07/22	750.00	70.00	102.65	75.30
		WEIGHTED AVERAGE FOR THE SECOND QUARTER		750.00	70.00	102.65	75.30
		WEIGHTED AVERAGE FOR THE YEAR		750.00	70.00	102.65	75.30
=====	403-33741	HMA (Gr S) (75) (PG 64-22)		Ton	=====	=====	=====
STA001A-005		SH1 WELLINGTON SOUTH RESURFAC	05/12/22	11,429.00	115.00	88.38	80.00
NHPP 3851-018		US 385 NORTH OF CHEYENNE WELL	05/26/22	35,372.00	110.00	135.50	131.00
		WEIGHTED AVERAGE FOR THE SECOND QUARTER		46,801.00	111.22	123.99	118.55
TRG0253-264		I-25 AND SH 119 PARK-N-RIDE	10/27/22	3,750.00	100.00	113.94	100.00
STA3852-015		US 385 HOLYOKE NORTH	10/27/22	28,558.00	135.50	144.00	144.00
STA0711-021		SH71: REGION LINE NORTH	12/01/22	44,358.00	130.00	116.25	100.00
		WEIGHTED AVERAGE FOR THE FOURTH QUARTER		76,666.00	130.58	120.02	116.39
		WEIGHTED AVERAGE FOR THE YEAR		123,467.00	123.24	121.33	117.21
=====	403-33841	HMA (Gr S) (100) (PG 64-22)		Ton	=====	=====	=====
NHPP 0761-238		I-76 DAHLIA TO YORK	03/10/22	2,353.00	110.00	105.62	100.00
C0761-239							
		WEIGHTED AVERAGE FOR THE FIRST QUARTER		2,353.00	110.00	105.62	100.00
STM1151-038		SH115 MP 27 TO MP 38	04/21/22	9,246.00	90.00	113.28	110.00
2670703-479		I-70 BRIDGE OVER HARLAN	05/05/22	3,509.00	85.00	102.74	140.00
FSA052A-046		SH52 WCR 37 INTERSECTION IMPR	06/09/22	4,088.00	100.00	110.74	115.00
		WEIGHTED AVERAGE FOR THE SECOND QUARTER		16,843.00	91.39	110.16	117.46
2670703-497		I-70_GENESEE WILDLIFE XING	09/15/22	914.00	150.00	147.68	150.28

COLORADO DEPARTMENT OF TRANSPORTATION
 ITEM UNIT COSTS BY PROJECTS -- 2022 COST DATA

11:31 Wednesday, March 8, 2023 227

PROJECT NUMBER	ITEM NUMBER/ PROJECT LOCATION	ITEM DESCRIPTION/ PROJECT LOCATION	DATE LET	UNIT/ QUANTITY	ENGR. EST.	AVERAGE BID	AWARDED BID
===== 403-33841		HMA (Gr S) (100) (PG 64-22)		Ton =====			
SHE2873-193		US 287 & CO 52 INTERSECTION I	09/15/22	1,754.00	120.00	127.95	126.00
		WEIGHTED AVERAGE FOR THE THIRD QUARTER		2,668.00	130.28	135.41	134.32
STU0252-457		I-25:ALAMEDA RIVER PH 2.0	11/03/22	2,874.00	130.00	129.89	135.00
NHPP0853-126		US85C: PLATTEVILLE NORTH MP (11/10/22	4,477.00	130.00	101.90	94.50
2670703-487		I-70 BRIDGES OVER WARD ROAD-	12/01/22	2,536.00	100.00	130.33	110.00
NHPP0931-033		SH93:US6 TO 58TH RESURFACING	12/15/22	1,360.00	115.00	92.96	71.40
		WEIGHTED AVERAGE FOR THE FOURTH QUARTER		11,247.00	121.42	113.16	105.55
		WEIGHTED AVERAGE FOR THE YEAR		33,111.00	106.04	112.99	113.53
===== 403-34701		HMA (Gr SX) (75)		Ton =====			
NHPP0702-383		I-70 EB AUX FRISCO TO SILVERT	01/13/22	40,335.00	100.00	108.42	105.00
STR0141-031			02/17/22	18,314.00	90.00	86.67	85.00
STR092A-031			03/17/22	22,713.91	78.00	72.00	72.00
		WEIGHTED AVERAGE FOR THE FIRST QUARTER		81,362.91	91.61	101.18	91.29
NHPP0702-414		VAIL PASS AUX PHASE 1 CAP 3	07/08/22	6,839.00	162.98	162.98	162.98
FBR0702-423		VAIL PASS AUX BE F-12-AT PHAS					
		WEIGHTED AVERAGE FOR THE THIRD QUARTER		6,839.00	162.98	162.98	162.98
STR064A-010		SH 64 AND SH 13 AT MEEKER	11/10/22	24,232.00	90.00	88.00	86.00
C5502-097		US550 MP 117.28-126.06	11/17/22	37,552.00	80.00	100.14	88.60
STR114A-015		SH114 SILLSVILLE SOUTH TO MP3	12/01/22	47,360.11	80.00	84.00	70.00
STR318A-001		SH 318 MP 0 - 12.5 MOFFAT COU	12/01/22	15,776.00	80.00	120.00	107.00
NHPP0502-090		SH 50 MP 134.6-136 GUNNISON C	12/22/22	12,337.00	90.00	104.22	99.00
STR0092-024		SH 9 North of Silverthorne	12/22/22	15,247.00	125.00	115.00	105.00
		WEIGHTED AVERAGE FOR THE FOURTH QUARTER		152,504.11	86.90	98.07	86.80
		WEIGHTED AVERAGE FOR THE YEAR		240,706.02	90.65	100.04	90.48
===== 403-34721		HMA (Gr SX) (75) (PG 58-28)		Ton =====			
NH0504-910		US50B L-24-B MIN REP AT MP 40	01/13/22	2,399.00	150.00	141.52	151.11

COLORADO DEPARTMENT OF TRANSPORTATION
ITEM UNIT COSTS BY PROJECTS -- 2022 COST DATA

11:31 Wednesday, March 8, 2023 228

PROJECT NUMBER	ITEM NUMBER/ PROJECT LOCATION	ITEM DESCRIPTION/ PROJECT LOCATION	DATE LET	UNIT/ QUANTITY	ENGR. EST.	AVERAGE BID	AWARDED BID
=====	403-34721	HMA (Gr SX) (75) (PG 58-28)		Ton =====			
NHPP1601-083			02/03/22	45,768.00	105.00	104.67	95.00
STA 067A-048		Hwy 67A MP 0.00 TO MP 11.05 I	03/03/22	17,181.00	95.00	94.66	90.00
STR160A-034		US160A LA VETA PASS EAST SURF	03/17/22	50,772.78	105.00	98.26	97.52
		WEIGHTED AVERAGE FOR THE FIRST QUARTER		116,120.78	104.45	102.93	96.52
NH0504-911			04/07/22	440.00	100.00	175.25	100.50
NHPP0702-413		VAIL PASS AUX PHASE 1 CAP 2	04/18/22	2,698.00	190.37	190.37	190.37
NHC540-017		R2 CHAINUP STA @ KENOSHA/HOOS	05/12/22	5,129.00	240.00	169.33	168.00
		WEIGHTED AVERAGE FOR THE SECOND QUARTER		8,267.00	216.35	172.60	171.71
NHPP0702-414		VAIL PASS AUX PHASE 1 CAP 3	07/08/22	1,360.00	226.41	226.41	226.41
FBR0702-423		VAIL PASS AUX BE F-12-AT PHAS					
2670403-065		US40_FLOYD HILL ROUNDABOUTS	09/15/22	2,352.00	140.00	171.14	207.00
		WEIGHTED AVERAGE FOR THE THIRD QUARTER		3,712.00	171.66	180.07	214.11
STA207A-004		Resurfacing SH207A MANZANOLA	10/27/22	24,853.00	120.00	130.23	121.70
SHE0242-087		US 24 SAFETY IMPRVMENTS, E OF	11/03/22	1,771.00	170.00	199.40	203.19
STAM420-001		US 285 AT HWY 9C IMPROVEMENTS	12/01/22	9,988.00	150.00	222.77	225.00
BR2854-148		INTERSECTION OF US 285 & SH 9					
STM0091-046		ADA RAMP IMPROVEMENTS - FAIRP					
IM025A-050		I25-MP103.9 - INTERSECTION DR	12/01/22	4,662.00	100.00	153.33	160.00
BR012A-048		CO 12 STRUCTURE P-17-F AT MP	12/22/22	1,701.00	155.00	171.14	170.00
STR096A-050		SH 96 MP 168.99 TO 193.77	12/22/22	40,331.63	100.00	141.67	122.00
		WEIGHTED AVERAGE FOR THE FOURTH QUARTER		83,306.63	114.57	156.58	142.32
		WEIGHTED AVERAGE FOR THE YEAR		211,406.41	113.99	134.21	121.10
=====	403-34731	HMA (Gr SX) (75) (PG 58-34)		Ton =====			
ER007A-035			03/15/22	28,450.00	114.80	124.95	124.95
		WEIGHTED AVERAGE FOR THE FIRST QUARTER		28,450.00	114.80	124.95	124.95
STAM420-001		US 285 AT HWY 9C IMPROVEMENTS	12/01/22	6,689.00	155.00	236.22	245.00

COLORADO DEPARTMENT OF TRANSPORTATION
 ITEM UNIT COSTS BY PROJECTS -- 2022 COST DATA

11:31 Wednesday, March 8, 2023 229

PROJECT NUMBER	ITEM NUMBER/ PROJECT LOCATION	ITEM DESCRIPTION/ PROJECT LOCATION	DATE LET	UNIT/ QUANTITY	ENGR. EST.	AVERAGE BID	AWARDED BID
=====	403-34731	HMA (Gr SX) (75) (PG 58-34)		Ton	=====	=====	=====
BR2854-148		INTERSECTION OF US 285 & SH 9					
STM0091-046		ADA RAMP IMPROVEMENTS - FAIRP					
	WEIGHTED AVERAGE FOR THE FOURTH QUARTER			6,689.00	155.00	236.22	245.00
	WEIGHTED AVERAGE FOR THE YEAR			35,139.00	122.45	178.88	147.80
=====	403-34741	HMA (Gr SX) (75) (PG 64-22)		Ton	=====	=====	=====
STM1151-038		SH115 MP 27 TO MP 38	04/21/22	16,337.00	85.00	112.05	108.00
2670703-479		I-70 BRIDGE OVER HARLAN	05/05/22	1,223.00	60.00	129.51	145.00
STA0712-019		SH 71: Frieight Improvements	05/12/22	9,395.00	130.00	140.77	140.77
	WEIGHTED AVERAGE FOR THE SECOND QUARTER			26,955.00	99.55	116.09	121.10
FSA052A-057		SH52 BOX CULVERT EXTENSION (M	08/04/22	99.00	200.00	282.83	340.68
NHPP0063-054		US 6 FROM I70-B TO 33 RD. (MP	08/18/22	2,350.00	200.00	200.47	145.00
	WEIGHTED AVERAGE FOR THE THIRD QUARTER			2,449.00	200.00	205.36	152.91
STA385A-016		SH 385 MP 97.76	12/22/22	2,659.00	190.00	173.81	172.22
	WEIGHTED AVERAGE FOR THE FOURTH QUARTER			2,659.00	190.00	173.81	172.22
	WEIGHTED AVERAGE FOR THE YEAR			32,063.00	114.72	125.38	127.77
=====	403-34751	HMA (Gr SX) (75) (PG 64-28)		Ton	=====	=====	=====
BRC040-057			03/17/22	177.00	200.00	322.00	300.00
	WEIGHTED AVERAGE FOR THE FIRST QUARTER			177.00	200.00	322.00	300.00
2670703-479		I-70 BRIDGE OVER HARLAN	05/05/22	610.00	90.00	147.81	155.00
STA0712-019		SH 71: Frieight Improvements	05/12/22	16,168.00	130.00	155.78	155.78
STA001A-005		SH1 WELLINGTON SOUTH RESURFAC	05/12/22	33,402.00	120.00	104.63	103.00

COLORADO DEPARTMENT OF TRANSPORTATION
ITEM UNIT COSTS BY PROJECTS -- 2022 COST DATA

11:31 Wednesday, March 8, 2023 230

PROJECT NUMBER	ITEM NUMBER/ PROJECT LOCATION	ITEM DESCRIPTION/ PROJECT LOCATION	DATE LET	UNIT/ QUANTITY	ENGR. EST.	AVERAGE BID	AWARDED BID
=====	403-34751	HMA (Gr SX) (75) (PG 64-28)		Ton =====			
NHPP 3851-018		US 385 NORTH OF CHEYENNE WELL	05/26/22	35,336.00	120.00	148.00	139.00
FSA3921-019		SH 392 AND WCR 55 ISLANDS	06/02/22	89.00	200.00	592.00	448.00
FSA052A-046		SH52 WCR 37 INTERSECTION IMPR	06/09/22	7,927.00	135.00	130.57	138.00
		WEIGHTED AVERAGE FOR THE SECOND QUARTER		93,532.00	122.88	131.04	129.36
FSA052A-057		SH52 BOX CULVERT EXTENSION (M	08/04/22	33.00	300.00	296.81	372.04
BR0343-046		US 34 TIMBER BRIDGE REPL. PKG	08/31/22	4,240.00	165.85	165.85	165.85
FBR0343-047		US 6/US 34 TIMBER BRIDGE REPL					
		WEIGHTED AVERAGE FOR THE THIRD QUARTER		4,273.00	166.89	168.84	167.44
STA3852-015		US 385 HOLYOKE NORTH	10/27/22	24,781.00	151.25	153.00	153.00
NHPP0343-048		US 34 (MP 169.3-171.4)	11/01/22	120.00	120.00	499.69	530.00
STA0711-021		SH71: REGION LINE NORTH	12/01/22	45,310.00	150.00	126.33	108.00
STA0361-129		US 36: HYGIENE RD AND NELSON	12/22/22	19,030.00	140.00	105.15	101.64
STA385A-016		SH 385 MP 97.76	12/22/22	1,582.00	210.00	182.95	177.78
		WEIGHTED AVERAGE FOR THE FOURTH QUARTER		90,823.00	149.25	123.22	120.72
		WEIGHTED AVERAGE FOR THE YEAR		188,805.00	136.63	127.27	126.22
=====	403-34771	HMA (Gr SX) (75) (PG 76-28)		Ton =====			
NH0504-911			04/07/22	95,923.00	90.00	110.00	101.00
		WEIGHTED AVERAGE FOR THE SECOND QUARTER		95,923.00	90.00	110.00	101.00
TRG0253-264		I-25 AND SH 119 PARK-N-RIDE	10/27/22	1,250.00	150.00	136.05	112.00
STRC090-011		US 50B AND SH71/CR18 INTERSEC	11/17/22	1,963.00	165.00	249.50	270.00
IM025A-050		I25-MP103.9 - INTERSECTION DR	12/01/22	804.00	100.00	160.00	160.00
STR109A-019		M-22-AY BRIDGE REHAB ON SH109	12/01/22	1,618.00	220.00	266.30	254.60
		WEIGHTED AVERAGE FOR THE FOURTH QUARTER		5,635.00	168.19	134.95	118.86
		WEIGHTED AVERAGE FOR THE YEAR		101,558.00	94.34	120.09	106.49
=====	403-34801	HMA (Gr SX) (100)		Ton =====			
NHPP0063-063			02/24/22	16,484.00	65.00	102.00	100.00
		WEIGHTED AVERAGE FOR THE FIRST QUARTER		16,484.00	65.00	102.00	100.00

COLORADO DEPARTMENT OF TRANSPORTATION
 ITEM UNIT COSTS BY PROJECTS -- 2022 COST DATA

11:31 Wednesday, March 8, 2023 231

PROJECT NUMBER	ITEM NUMBER/ PROJECT LOCATION	ITEM DESCRIPTION/ PROJECT LOCATION	DATE LET	UNIT/ QUANTITY	ENGR. EST.	AVERAGE BID	AWARDED BID
=====	403-34801	HMA (Gr SX) (100)		Ton	=====	=====	=====
NHPP0063-054		US 6 FROM I70-B TO 33 RD. (MP 08/18/22		2,248.00	200.00	181.78	130.00
		WEIGHTED AVERAGE FOR THE THIRD QUARTER		2,248.00	200.00	181.78	130.00
NHPP0701-253		I-70 EAST OF DEBEQUE	10/27/22	16,467.00	100.00	92.00	95.00
NHPP0063-048		US6 / 20 ROAD INTERSECTION IM	12/15/22	5,943.74	175.00	153.09	117.00
		WEIGHTED AVERAGE FOR THE FOURTH QUARTER		22,410.74	119.89	117.61	100.83
		WEIGHTED AVERAGE FOR THE YEAR		41,142.74	102.28	115.21	102.09
=====	403-34841	HMA (Gr SX) (100) (PG 64-22)		Ton	=====	=====	=====
NHM765-007			03/31/22	1,145.00	180.00	230.95	210.90
		WEIGHTED AVERAGE FOR THE FIRST QUARTER		1,145.00	180.00	230.95	210.90
		WEIGHTED AVERAGE FOR THE YEAR		1,145.00	180.00	230.95	210.90
=====	403-34851	HMA (Gr SX) (100) (PG 64-28)		Ton	=====	=====	=====
C0762-055			02/17/22	30,038.00	115.00	113.55	108.00
		WEIGHTED AVERAGE FOR THE FIRST QUARTER		30,038.00	115.00	113.55	108.00
STM1151-038		SH115 MP 27 TO MP 38	04/21/22	32,043.00	96.00	119.29	115.00
2670703-479		I-70 BRIDGE OVER HARLAN	05/05/22	122.00	90.00	188.34	165.00
		WEIGHTED AVERAGE FOR THE SECOND QUARTER		32,165.00	95.98	119.60	115.19
SHE2873-193		US 287 & CO 52 INTERSECTION I	09/15/22	2,053.00	150.00	145.57	143.00
		WEIGHTED AVERAGE FOR THE THIRD QUARTER		2,053.00	150.00	145.57	143.00

COLORADO DEPARTMENT OF TRANSPORTATION
ITEM UNIT COSTS BY PROJECTS -- 2022 COST DATA

11:31 Wednesday, March 8, 2023 232

PROJECT NUMBER	ITEM NUMBER/ PROJECT LOCATION	ITEM DESCRIPTION/ PROJECT LOCATION	DATE LET	UNIT/ QUANTITY	ENGR. EST.	AVERAGE BID	AWARDED BID
===== 403-34851		HMA (Gr SX) (100) (PG 64-28)		Ton	=====	=====	=====
NHPP0853-126		US85C: PLATTEVILLE NORTH MP (11/10/22	29,324.00	135.00	106.63	97.65
	WEIGHTED AVERAGE FOR THE FOURTH QUARTER			29,324.00	135.00	106.63	97.65
	WEIGHTED AVERAGE FOR THE YEAR			93,580.00	115.50	114.35	108.00
===== 403-34871		HMA (Gr SX) (100) (PG 76-28)		Ton	=====	=====	=====
NHPP1601-083 C0762-055			02/03/22 02/17/22	22,114.00 14,402.00	115.00 115.00	119.91 116.70	110.00 111.00
	WEIGHTED AVERAGE FOR THE FIRST QUARTER			36,516.00	115.00	118.09	110.39
CM760-047 NHPP072A-047		COLFAX AND QUAIL SH-72 RESURFACING: I-70 TO IN	05/12/22 06/09/22	31.00 23,343.00	167.50 85.00	472.60 102.03	544.00 102.03
	WEIGHTED AVERAGE FOR THE SECOND QUARTER			23,374.00	85.11	104.47	102.62
STU0252-457 2670703-487 IM025A-050 NHPP0931-033		I-25:ALAMEDA RIVER PH 2.0 I-70 BRIDGES OVER WARD ROAD- I25-MP103.9 - INTERSECTION DR SH93:US6 TO 58TH RESURFACING	11/03/22 12/01/22 12/01/22 12/15/22	1,902.00 1,652.00 760.00 18,988.00	150.00 110.00 100.00 122.00	176.45 145.22 166.67 96.81	184.00 140.00 170.00 77.15
	WEIGHTED AVERAGE FOR THE FOURTH QUARTER			23,302.00	122.72	107.80	93.36
	WEIGHTED AVERAGE FOR THE YEAR			83,192.00	108.76	112.26	103.44
===== 403-36621		HMA (Gr ST) (50) (PG 58-28)		Ton	=====	=====	=====
STA 067A-048		Hwy 67A MP 0.00 TO MP 11.05 I	03/03/22	11,201.00	100.00	102.63	99.00
	WEIGHTED AVERAGE FOR THE FIRST QUARTER			11,201.00	100.00	102.63	99.00
STR096A-050		SH 96 MP 168.99 TO 193.77	12/22/22	27,635.77	120.00	143.83	133.00
	WEIGHTED AVERAGE FOR THE FOURTH QUARTER			27,635.77	120.00	143.83	133.00
	WEIGHTED AVERAGE FOR THE YEAR			38,836.77	114.23	131.95	123.19

COLORADO DEPARTMENT OF TRANSPORTATION
ITEM UNIT COSTS BY PROJECTS -- 2022 COST DATA

11:31 Wednesday, March 8, 2023 233

PROJECT NUMBER	ITEM NUMBER/ PROJECT LOCATION	ITEM DESCRIPTION/ PROJECT LOCATION	DATE LET	UNIT/ QUANTITY	ENGR. EST.	AVERAGE BID	AWARDED BID
=====	403-36701	HMA (Gr ST) (75)		Ton	=====	=====	=====
STR0141-031			02/17/22	8,729.00	95.00	86.42	78.25
STR092A-031			03/17/22	9,260.72	88.00	74.00	74.00
		WEIGHTED AVERAGE FOR THE FIRST QUARTER		17,989.72	91.40	83.17	76.06
STR114A-015		SH114 SILLSVILLE SOUTH TO MP3	12/01/22	27,531.46	85.00	89.50	79.00
STR318A-001		SH 318 MP 0 - 12.5 MOFFAT COU	12/01/22	11,238.00	90.00	122.50	108.00
		WEIGHTED AVERAGE FOR THE FOURTH QUARTER		38,769.46	86.45	99.07	87.41
		WEIGHTED AVERAGE FOR THE YEAR		56,759.18	88.02	94.08	83.81
=====	403-40000	HMA Safety Edge		Lin Foot	=====	=====	=====
NHPP 0761-238 C0761-239		I-76 DAHLIA TO YORK	03/10/22	360.00	2.50	23.10	20.00
		WEIGHTED AVERAGE FOR THE FIRST QUARTER		360.00	2.50	23.10	20.00
FSA052A-046		SH52 WCR 37 INTERSECTION IMPR	06/09/22	12,962.00	0.75	1.72	1.70
		WEIGHTED AVERAGE FOR THE SECOND QUARTER		12,962.00	0.75	1.72	1.70
		WEIGHTED AVERAGE FOR THE YEAR		13,322.00	0.80	2.63	2.19
=====	408-01100	Joint Sealant		Lin Foot	=====	=====	=====
NHPP2873-189 C0762-055		US 287 (FEDERAL BLVD) - COLFA	01/06/22	164.00	25.00	34.66	55.31
NHPP0703-472 BRC040-057			02/17/22	299.00	30.00	35.97	37.00
			03/10/22	995.00	25.00	26.39	20.00
			03/17/22	228.00	30.00	51.75	35.00
		WEIGHTED AVERAGE FOR THE FIRST QUARTER		1,686.00	26.56	32.32	28.48
NH0504-911			04/07/22	608.00	27.00	37.75	35.50

COLORADO DEPARTMENT OF TRANSPORTATION
ITEM UNIT COSTS BY PROJECTS -- 2022 COST DATA

11:31 Wednesday, March 8, 2023 234

PROJECT NUMBER	ITEM NUMBER/ PROJECT LOCATION	ITEM DESCRIPTION/ PROJECT LOCATION	DATE LET	UNIT/ QUANTITY	ENGR. EST.	AVERAGE BID	AWARDED BID
===== 2670703-479	408-01100	Joint Sealant I-70 BRIDGE OVER HARLAN	05/05/22	Lin Foot 268.00	26.00	38.83	40.49
		WEIGHTED AVERAGE FOR THE SECOND QUARTER		876.00	26.69	38.37	37.03
NHPP0702-414 FBR0702-423 ER0502-092 2670703-479		VAIL PASS AUX PHASE 1 CAP 3 VAIL PASS AUX BE F-12-AT PHAS US 50 MP 204 EB MONARCH TRUCK I-70_GENESEE WILDLIFE KING	07/08/22 08/29/22 09/15/22	104.00 616.00 448.00	20.14 25.00 26.00	20.14 40.79 23.13	20.14 44.86 28.40
		WEIGHTED AVERAGE FOR THE THIRD QUARTER		1,168.00	24.95	29.48	36.35
C5502-097 STA0711-021 2670703-487 NHPP0701-252 BR012A-048		US550 MP 117.28-126.06 SH71: REGION LINE NORTH I-70 BRIDGES OVER WARD ROAD- I-70 RIFLE TO SILT SLAB REPLA CO 12 STRUCTURE P-17-F AT MP	11/17/22 12/01/22 12/01/22 12/01/22 12/22/22	145.00 121.00 812.00 306.00 101.00	40.00 26.00 50.00 40.00 40.00	31.67 38.83 26.39 25.58 52.98	41.10 42.00 51.00 21.15 80.00
		WEIGHTED AVERAGE FOR THE FOURTH QUARTER		1,485.00	44.33	28.45	45.12
		WEIGHTED AVERAGE FOR THE YEAR		5,215.00	31.28	31.37	36.42
===== 2670703-479	409-01010	CC Matl (Ty I)		Ton			
NHPP0821-114		SH 82 ASPEN/INDEPENDENCE PASS	10/13/22	2,289.37	145.00	255.92	124.00
		WEIGHTED AVERAGE FOR THE FOURTH QUARTER		2,289.37	145.00	255.92	124.00
		WEIGHTED AVERAGE FOR THE YEAR		2,289.37	145.00	255.92	124.00
===== 2670703-479	409-01015	CC Matl (Ty I)		Sq Yard			
STR133A-051			02/17/22	285,117.00	1.00	1.58	1.50
		WEIGHTED AVERAGE FOR THE FIRST QUARTER		285,117.00	1.00	1.58	1.50
STR0641-107		SH 13 MM 104-128.1 IN MOFFAT	12/01/22	568,140.00	1.60	3.01	2.00

COLORADO DEPARTMENT OF TRANSPORTATION
 ITEM UNIT COSTS BY PROJECTS -- 2022 COST DATA

11:31 Wednesday, March 8, 2023 235

PROJECT NUMBER	ITEM NUMBER/ PROJECT LOCATION	ITEM DESCRIPTION/ PROJECT LOCATION	DATE LET	UNIT/ QUANTITY	ENGR. EST.	AVERAGE BID	AWARDED BID
===== 409-01015 STR0092-024	CC Matl (Ty I) SH 9 North of Silverthorne		12/22/22	Sq Yard 266,778.00	1.50	1.65	1.85
	WEIGHTED AVERAGE FOR THE FOURTH QUARTER			834,918.00	1.57	2.61	1.96
	WEIGHTED AVERAGE FOR THE YEAR			1,120,035.00	1.42	2.40	1.87
===== 409-02030 MTCE 072A-045	CC Matl (Ty I) (Special) SH 72B MP 37.00 TO MP 45.3 NE		07/07/22	Sq Yard 173,835.00	3.00	4.43	4.43
	WEIGHTED AVERAGE FOR THE THIRD QUARTER			173,835.00	3.00	4.43	4.43
	WEIGHTED AVERAGE FOR THE YEAR			173,835.00	3.00	4.43	4.43
===== 409-09000 STR0505-050	Micro-Surfacing Seal Coat		01/13/22	Ton 5,897.00	230.00	230.00	175.00
	WEIGHTED AVERAGE FOR THE FIRST QUARTER			5,897.00	230.00	230.00	175.00
NH0504-911			04/07/22	1,154.00	250.00	280.00	300.00
	WEIGHTED AVERAGE FOR THE SECOND QUARTER			1,154.00	250.00	280.00	300.00
NHM175-029	CANON CITY, CO		12/15/22	4,198.00	230.00	260.00	220.00
	WEIGHTED AVERAGE FOR THE FOURTH QUARTER			4,198.00	230.00	260.00	220.00
	WEIGHTED AVERAGE FOR THE YEAR			11,249.00	232.05	242.93	204.62
===== 411-03342 STR092A-031	Asph Cem (PG 64-28)		03/17/22	Ton 1,160.00	750.00	868.00	868.00
	WEIGHTED AVERAGE FOR THE FIRST QUARTER			1,160.00	750.00	868.00	868.00
C5502-097	US550 MP 117.28-126.06		11/17/22	1,229.00	1000.00	844.98	817.00
	WEIGHTED AVERAGE FOR THE FOURTH QUARTER			1,229.00	1000.00	844.98	817.00
	WEIGHTED AVERAGE FOR THE YEAR			2,389.00	878.61	850.49	841.76

COLORADO DEPARTMENT OF TRANSPORTATION
ITEM UNIT COSTS BY PROJECTS -- 2022 COST DATA

11:31 Wednesday, March 8, 2023 236

PROJECT NUMBER	ITEM NUMBER/ PROJECT LOCATION	ITEM DESCRIPTION/ PROJECT LOCATION	DATE LET	UNIT/ QUANTITY	ENGR. EST.	AVERAGE BID	AWARDED BID
===== 411-03345 Asph Cem (PG 76-28) Ton =====							
NHPP0063-063			02/24/22	989.10	600.00	642.50	500.00
	WEIGHTED AVERAGE FOR THE FIRST QUARTER			989.10	600.00	642.50	500.00
NHPP0063-054		US 6 FROM I70-B TO 33 RD. (MP 08/18/22		154.00	1300.00	1066.82	510.00
	WEIGHTED AVERAGE FOR THE THIRD QUARTER			154.00	1300.00	1066.82	510.00
NHPP0701-253		I-70 EAST OF DEBEQUE	10/27/22	989.00	1000.00	765.00	600.00
NHPP0063-048		US6 / 20 ROAD INTERSECTION IM	12/15/22	236.25	600.00	1072.71	875.00
	WEIGHTED AVERAGE FOR THE FOURTH QUARTER			1,225.25	922.87	864.48	653.02
	WEIGHTED AVERAGE FOR THE YEAR			2,368.35	812.55	792.15	579.82
===== 411-03352 Asph Cem (PG 58-28) Ton =====							
NHPP0702-383		I-70 EB AUX FRISCO TO SILVERT	01/13/22	1,392.00	500.00	650.28	630.00
STR0141-031			02/17/22	593.00	550.00	551.67	540.00
STR092A-031			03/17/22	878.03	700.00	623.00	623.00
	WEIGHTED AVERAGE FOR THE FIRST QUARTER			2,863.03	571.69	629.55	609.21
NHPP0702-414		VAIL PASS AUX PHASE 1 CAP 3	07/08/22	410.00	1069.89	1069.89	1069.89
FBR0702-423		VAIL PASS AUX BE F-12-AT PHAS					
	WEIGHTED AVERAGE FOR THE THIRD QUARTER			410.00	1069.89	1069.89	1069.89
STR064A-010		SH 64 AND SH 13 AT MEEKER	11/10/22	272.00	1000.00	737.50	745.00
C5502-097		US550 MP 117.28-126.06	11/17/22	1,024.00	600.00	731.21	711.00
STR114A-015		SH114 SILLSVILLE SOUTH TO MP3	12/01/22	1,873.30	900.00	625.00	700.00
STR318A-001		SH 318 MP 0 - 12.5 MOFFAT COU	12/01/22	764.00	1000.00	621.50	668.00

COLORADO DEPARTMENT OF TRANSPORTATION
 ITEM UNIT COSTS BY PROJECTS -- 2022 COST DATA

11:31 Wednesday, March 8, 2023 237

PROJECT NUMBER	ITEM NUMBER/ PROJECT LOCATION	ITEM DESCRIPTION/ PROJECT LOCATION	DATE LET	UNIT/ QUANTITY	ENGR. EST.	AVERAGE BID	AWARDED BID
=====	411-03352	Asph Cem (PG 58-28)		Ton =====			
NHPP0502-090		SH 50 MP 134.6-136 GUNNISON C	12/22/22	295.00	750.00	698.97	680.00
		WEIGHTED AVERAGE FOR THE FOURTH QUARTER		4,228.30	841.38	672.39	698.38
		WEIGHTED AVERAGE FOR THE YEAR		7,501.33	750.94	660.18	684.65
=====	411-03354	Asph Cem (PG 64-22)		Ton =====			
NHPP0063-054		US 6 FROM I70-B TO 33 RD. (MP 08/18/22		181.00	900.00	930.34	445.00
		WEIGHTED AVERAGE FOR THE THIRD QUARTER		181.00	900.00	930.34	445.00
NHPP0063-048		US6 / 20 ROAD INTERSECTION IM	12/15/22	120.37	450.00	882.63	705.00
		WEIGHTED AVERAGE FOR THE FOURTH QUARTER		120.37	450.00	882.63	705.00
		WEIGHTED AVERAGE FOR THE YEAR		301.37	720.27	903.11	548.85
=====	411-03355	Asph Cem (PG 58-34)		Ton =====			
NHPP0702-383		I-70 EB AUX FRISCO TO SILVERT	01/13/22	1,037.00	600.00	838.84	826.00
STR0141-031			02/17/22	1,099.00	750.00	658.33	660.00
		WEIGHTED AVERAGE FOR THE FIRST QUARTER		2,136.00	677.18	768.67	740.59
STR064A-010		SH 64 AND SH 13 AT MEEKER	11/10/22	1,155.00	1200.00	837.00	837.00
STR114A-015		SH114 SILLSVILLE SOUTH TO MP3	12/01/22	2,840.15	1000.00	700.00	800.00
STR318A-001		SH 318 MP 0 - 12.5 MOFFAT COU	12/01/22	947.00	1200.00	698.50	742.00
NHPP0502-090		SH 50 MP 134.6-136 GUNNISON C	12/22/22	445.00	900.00	820.68	800.00
STR0092-024		SH 9 North of Silverthorne	12/22/22	915.00	900.00	753.50	751.00
		WEIGHTED AVERAGE FOR THE FOURTH QUARTER		6,302.15	1045.13	748.79	790.95
		WEIGHTED AVERAGE FOR THE YEAR		8,438.15	951.99	756.31	778.20
=====	411-10216	Emul Asph (CRS-2P)		Gallon =====			
STR133A-051			02/17/22	111,196.00	2.70	3.07	2.60
		WEIGHTED AVERAGE FOR THE FIRST QUARTER		111,196.00	2.70	3.07	2.60

COLORADO DEPARTMENT OF TRANSPORTATION
 ITEM UNIT COSTS BY PROJECTS -- 2022 COST DATA

11:31 Wednesday, March 8, 2023 238

PROJECT NUMBER	ITEM NUMBER/ PROJECT LOCATION	ITEM DESCRIPTION/ PROJECT LOCATION	DATE LET	UNIT/ QUANTITY	ENGR. EST.	AVERAGE BID	AWARDED BID
===== 411-10216		Emul Asph (CRS-2P)		Gallon	=====		
MTCE 072A-045		SH 72B MP 37.00 TO MP 45.3 NE	07/07/22	86,918.00	3.50	0.75	0.75
		WEIGHTED AVERAGE FOR THE THIRD QUARTER		86,918.00	3.50	0.75	0.75
NHPP0821-114		SH 82 ASPEN/INDEPENDENCE PASS	10/13/22	71,503.00	3.00	4.35	3.70
STR0641-107		SH 13 MM 104-128.1 IN MOFFAT	12/01/22	221,580.00	3.40	4.00	3.25
STR0092-024		SH 9 North of Silverthorne	12/22/22	104,043.00	2.70	3.50	3.80
		WEIGHTED AVERAGE FOR THE FOURTH QUARTER		397,126.00	3.14	4.10	3.57
		WEIGHTED AVERAGE FOR THE YEAR		595,240.00	3.11	3.76	3.06
===== 411-10253		Emul Asph (CSS-1H)		Gallon	=====		
STR133A-051			02/17/22	18,818.00	2.60	3.88	3.65
		WEIGHTED AVERAGE FOR THE FIRST QUARTER		18,818.00	2.60	3.88	3.65
MTCE 072A-045		SH 72B MP 37.00 TO MP 45.3 NE	07/07/22	11,255.00	3.80	0.75	0.75
		WEIGHTED AVERAGE FOR THE THIRD QUARTER		11,255.00	3.80	0.75	0.75
NHPP0821-114		SH 82 ASPEN/INDEPENDENCE PASS	10/13/22	12,101.00	4.00	3.67	2.15
STR0641-107		SH 13 MM 104-128.1 IN MOFFAT	12/01/22	37,487.00	4.20	4.53	3.25
STR0092-024		SH 9 North of Silverthorne	12/22/22	17,607.00	4.00	3.05	3.25
		WEIGHTED AVERAGE FOR THE FOURTH QUARTER		67,195.00	4.11	4.20	3.04
		WEIGHTED AVERAGE FOR THE YEAR		97,268.00	3.78	4.02	2.92
===== 411-10255		Emul Asph (SS)		Gallon	=====		
NHPP2873-189		US 287 (FEDERAL BLVD) - COLFA	01/06/22	7,904.00	3.80	6.35	2.95

PROJECT NUMBER	ITEM NUMBER/ PROJECT LOCATION	ITEM DESCRIPTION/ PROJECT LOCATION	DATE LET	UNIT/ QUANTITY	ENGR. EST.	AVERAGE BID	AWARDED BID
=====	411-10255	Emul Asph (SS)		Gallon =====			
STR0505-050			01/13/22	10,679.00	4.00	4.58	5.00
NH0504-910		US50B L-24-B MIN REP AT MP 40	01/13/22	374.00	6.00	8.24	6.56
NHPP0702-383		I-70 EB AUX FRISCO TO SILVERT	01/13/22	14,899.00	4.00	2.65	2.30
NHPP1601-083			02/03/22	39,759.00	5.00	3.34	2.00
STR0141-031			02/17/22	12,266.00	5.00	3.00	2.50
NHPP0063-063			02/24/22	16,437.00	4.00	2.88	2.50
STA 067A-048		Hwy 67A MP 0.00 TO MP 11.05 I	03/03/22	20,159.00	3.00	3.36	3.00
NHPP 0761-238		I-76 DAHLIA TO YORK	03/10/22	1,248.00	6.00	4.07	3.75
C0761-239							
NHPP0703-472			03/10/22	16,217.00	4.00	6.36	3.00
STR160A-034		US160A LA VETA PASS EAST SURF	03/17/22	20,688.00	3.00	3.00	3.00
STR092A-031			03/17/22	20,655.00	3.00	2.75	2.75
NHM765-007			03/31/22	251.00	7.00	10.81	9.12
		WEIGHTED AVERAGE FOR THE FIRST QUARTER		181,536.00	3.96	3.86	2.75
NH0504-911			04/07/22	33,917.00	3.51	5.10	8.20
NHPP0702-413		VAIL PASS AUX PHASE 1 CAP 2	04/18/22	1,115.00	2.68	2.68	2.68
STM1151-038		SH115 MP 27 TO MP 38	04/21/22	41,407.00	3.50	5.60	5.30
2670703-479		I-70 BRIDGE OVER HARLAN	05/05/22	3,586.00	3.50	5.18	12.25
NHC540-017		R2 CHAINUP STA @ KENOSHA/HOOS	05/12/22	3,021.00	3.00	6.67	9.00
NHPP 3851-018		US 385 NORTH OF CHEYENNE WELL	05/26/22	26,660.00	3.50	3.13	3.00
NHPP072A-047		SH-72 RESURFACING: I-70 TO IN	06/09/22	16,424.00	5.00	3.52	3.52
		WEIGHTED AVERAGE FOR THE SECOND QUARTER		126,130.00	3.68	5.06	5.62
NHPP0702-414		VAIL PASS AUX PHASE 1 CAP 3	07/08/22	2,175.00	2.68	2.68	2.68
FBR0702-423		VAIL PASS AUX BE F-12-AT PHAS					
NHPP0063-054		US 6 FROM I70-B TO 33 RD. (MP	08/18/22	1,605.00	5.00	3.90	3.00
2670703-497		I-70_GENESEE WILDLIFE KING	09/15/22	2,240.00	8.10	8.82	9.09
		WEIGHTED AVERAGE FOR THE THIRD QUARTER		6,020.00	5.32	7.44	5.15
NHPP0701-253		I-70 EAST OF DEBEQUE	10/27/22	7,737.00	4.50	3.55	3.00
STA207A-004		Resurfacing SH207A MANZANOLA	10/27/22	14,562.00	5.00	5.37	6.10
STU0252-457		I-25:ALAMEDA RIVER PH 2.0	11/03/22	468.00	5.00	10.02	9.90
SHE0242-087		US 24 SAFETY IMPRVMENTS, E OF	11/03/22	445.00	5.00	8.60	5.81
STR064A-010		SH 64 AND SH 13 AT MEEKER	11/10/22	12,573.00	4.00	3.60	3.00
C5502-097		US550 MP 117.28-126.06	11/17/22	11,901.00	5.00	4.35	4.30

COLORADO DEPARTMENT OF TRANSPORTATION
ITEM UNIT COSTS BY PROJECTS -- 2022 COST DATA

11:31 Wednesday, March 8, 2023 240

PROJECT NUMBER	ITEM NUMBER/ PROJECT LOCATION	ITEM DESCRIPTION/ PROJECT LOCATION	DATE LET	UNIT/ QUANTITY	ENGR. EST.	AVERAGE BID	AWARDED BID
=====	411-10255	Emul Asph (SS)		Gallon	=====	=====	=====
STRC090-011		US 50B AND SH71/CR18 INTERSEC	11/17/22	1,444.00	4.00	10.25	10.50
STAM420-001		US 285 AT HWY 9C IMPROVEMENTS	12/01/22	10,000.00	3.50	11.70	7.14
BR2854-148		INTERSECTION OF US 285 & SH 9					
STM0091-046		ADA RAMP IMPROVEMENTS - FAIRP					
STA0711-021		SH71: REGION LINE NORTH	12/01/22	25,143.00	3.50	3.33	4.00
STR114A-015		SH114 SILLSVILLE SOUTH TO MP3	12/01/22	51,492.00	5.00	3.50	4.00
2670703-487		I-70 BRIDGES OVER WARD ROAD-	12/01/22	1,168.00	25.00	5.37	5.80
IM025A-050		I25-MP103.9 - INTERSECTION DR	12/01/22	1,692.00	3.00	5.50	5.50
STR318A-001		SH 318 MP 0 - 12.5 MOFFAT COU	12/01/22	19,264.00	5.00	3.65	4.30
STR109A-019		M-22-AY BRIDGE REHAB ON SH109	12/01/22	348.00	5.00	12.25	5.49
NHPP0021-041		SH2 RESURFACING MLK TO 52ND	12/01/22	8,161.00	3.00	5.75	4.00
NHPP083A-046		SH83 RESURFACING STROH RD TO	12/08/22	6,810.00	5.00	5.19	4.37
NHPP0063-048		US6 / 20 ROAD INTERSECTION IM	12/15/22	1,640.00	4.00	6.60	4.20
NHM175-029		CANON CITY, CO	12/15/22	12,555.00	4.00	6.25	4.00
NHPP0931-033		SH93:US6 TO 58TH RESURFACING	12/15/22	14,633.00	5.00	3.95	4.80
NHPP0502-090		SH 50 MP 134.6-136 GUNNISON C	12/22/22	3,473.00	4.00	8.13	8.00
STR0092-024		SH 9 North of Silverthorne	12/22/22	9,240.00	6.00	3.63	3.25
BR012A-048		CO 12 STRUCTURE P-17-F AT MP	12/22/22	438.00	4.00	5.04	5.00
STA385A-016		SH 385 MP 97.76	12/22/22	1,773.00	6.00	10.78	11.11
STR096A-050		SH 96 MP 168.99 TO 193.77	12/22/22	45,498.00	3.60	3.25	4.00
		WEIGHTED AVERAGE FOR THE FOURTH QUARTER		262,458.00	4.48	4.61	4.38
		WEIGHTED AVERAGE FOR THE YEAR		576,144.00	4.15	4.53	4.15
=====	411-90040	Recycling Agent		Gallon	=====	=====	=====
NHPP1601-083			02/03/22	627,765.00	1.75	3.58	3.30
		WEIGHTED AVERAGE FOR THE FIRST QUARTER		627,765.00	1.75	3.58	3.30
		WEIGHTED AVERAGE FOR THE YEAR		627,765.00	1.75	3.58	3.30
=====	412-00000	Furn Conc Pvmt		Cubic Yard	=====	=====	=====
STM1151-038		SH115 MP 27 TO MP 38	04/21/22	18,267.00	130.00	142.15	110.29
		WEIGHTED AVERAGE FOR THE SECOND QUARTER		18,267.00	130.00	142.15	110.29
		WEIGHTED AVERAGE FOR THE YEAR		18,267.00	130.00	142.15	110.29
=====	412-00050	P1 Conc Pvmt		Sq Yard	=====	=====	=====
STM1151-038		SH115 MP 27 TO MP 38	04/21/22	66,685.00	12.00	31.49	30.07
		WEIGHTED AVERAGE FOR THE SECOND QUARTER		66,685.00	12.00	31.49	30.07
		WEIGHTED AVERAGE FOR THE YEAR		66,685.00	12.00	31.49	30.07

COLORADO DEPARTMENT OF TRANSPORTATION
ITEM UNIT COSTS BY PROJECTS -- 2022 COST DATA

11:31 Wednesday, March 8, 2023 241

PROJECT NUMBER	ITEM NUMBER/ PROJECT LOCATION	ITEM DESCRIPTION/ PROJECT LOCATION	DATE LET	UNIT/ QUANTITY	ENGR. EST.	AVERAGE BID	AWARDED BID
=====	412-00190	Conc Pvmt (Patching)		Sq Yard	=====		
STA0252-459			02/03/22	1,606.00	160.00	451.85	493.50
		WEIGHTED AVERAGE FOR THE FIRST QUARTER		1,606.00	160.00	451.85	493.50
CC030-081		ADA RAMP AND CURBS - FT. LUPT	04/14/22	658.00	200.00	148.35	115.00
NHPP072A-047		SH-72 RESURFACING: I-70 TO IN	06/09/22	10.00	150.00	132.52	132.52
		WEIGHTED AVERAGE FOR THE SECOND QUARTER		668.00	199.25	148.27	115.26
TRG0253-264		I-25 AND SH 119 PARK-N-RIDE	10/27/22	1,636.00	125.00	145.19	145.00
STAM420-001		US 285 AT HWY 9C IMPROVEMENTS	12/01/22	74.00	110.00	210.41	282.80
BR2854-148		INTERSECTION OF US 285 & SH 9					
STM0091-046		ADA RAMP IMPROVEMENTS - FAIRP					
FSA0853-122		WCRI4.5 AND US-85, FORT LUPTO	12/15/22	15.00	225.00	561.15	290.00
NHPP0931-033		SH93:US6 TO 58TH RESURFACING	12/15/22	5.00	150.00	609.71	515.00
		WEIGHTED AVERAGE FOR THE FOURTH QUARTER		1,730.00	125.30	148.71	153.22
		WEIGHTED AVERAGE FOR THE YEAR		4,004.00	151.55	220.79	283.37
=====	412-00600	Conc Pvmt (6 In)		Sq Yard	=====		
NHPP0063-063			02/24/22	238.00	150.00	168.10	275.00
STR092A-031			03/17/22	46.00	300.00	160.00	160.00
NHM765-007			03/31/22	1,181.00	70.00	96.88	81.82
		WEIGHTED AVERAGE FOR THE FIRST QUARTER		1,465.00	90.22	105.93	115.66
NHPP072A-047		SH-72 RESURFACING: I-70 TO IN	06/09/22	136.00	100.00	131.32	131.32
		WEIGHTED AVERAGE FOR THE SECOND QUARTER		136.00	100.00	131.32	131.32
STU0252-457		I-25:ALAMEDA RIVER PH 2.0	11/03/22	451.00	100.00	75.20	83.00
		WEIGHTED AVERAGE FOR THE FOURTH QUARTER		451.00	100.00	75.20	83.00
		WEIGHTED AVERAGE FOR THE YEAR		2,052.00	93.02	99.07	109.52

COLORADO DEPARTMENT OF TRANSPORTATION
ITEM UNIT COSTS BY PROJECTS -- 2022 COST DATA

11:31 Wednesday, March 8, 2023 242

PROJECT NUMBER	ITEM NUMBER/ PROJECT LOCATION	ITEM DESCRIPTION/ PROJECT LOCATION	DATE LET	UNIT/ QUANTITY	ENGR. EST.	AVERAGE BID	AWARDED BID
=====	412-00700	Conc Pvmt (7 In)		Sq Yard	=====		
NH0504-911			04/07/22	1,139.00	110.00	104.40	103.80
		WEIGHTED AVERAGE FOR THE SECOND QUARTER		1,139.00	110.00	104.40	103.80
		WEIGHTED AVERAGE FOR THE YEAR		1,139.00	110.00	104.40	103.80
=====	412-00800	Conc Pvmt (8 In)		Sq Yard	=====		
NHPP 0761-238 C0761-239		I-76 DAHLIA TO YORK	03/10/22	40.00	45.00	105.99	90.00
		WEIGHTED AVERAGE FOR THE FIRST QUARTER		40.00	45.00	105.99	90.00
STM1151-038		SH115 MP 27 TO MP 38	04/21/22	85,051.00	48.00	64.26	54.79
		WEIGHTED AVERAGE FOR THE SECOND QUARTER		85,051.00	48.00	64.26	54.79
C1211-099 SHE2873-193		SH 121 NORTH SGA SIGNALS	08/25/22	323.00	300.00	161.00	170.00
		US 287 & CO 52 INTERSECTION I	09/15/22	7,846.00	85.00	105.95	73.50
		WEIGHTED AVERAGE FOR THE THIRD QUARTER		8,169.00	93.50	106.70	77.32
TRG0253-264 C5502-097 STAM420-001 BR2854-148 STM0091-046 2670703-487		I-25 AND SH 119 PARK-N-RIDE	10/27/22	288.00	85.00	121.76	105.00
		US550 MP 117.28-126.06	11/17/22	168.00	250.00	178.27	182.00
		US 285 AT HWY 9C IMPROVEMENTS	12/01/22	380.00	51.40	138.08	135.75
		INTERSECTION OF US 285 & SH 9					
		ADA RAMP IMPROVEMENTS - FAIRP					
		I-70 BRIDGES OVER WARD ROAD-	12/01/22	2,698.00	110.00	158.43	150.00
		WEIGHTED AVERAGE FOR THE FOURTH QUARTER		3,534.00	108.32	152.51	146.32
		WEIGHTED AVERAGE FOR THE YEAR		96,794.00	54.04	71.61	60.05
=====	412-00801	Conc Pvmt (8 In) (Spec)		Sq Yard	=====		
2670403-065		US40_FLOYD HILL ROUNDABOUTS	09/15/22	1,352.00	150.00	108.05	108.00
		WEIGHTED AVERAGE FOR THE THIRD QUARTER		1,352.00	150.00	108.05	108.00
		WEIGHTED AVERAGE FOR THE YEAR		1,352.00	150.00	108.05	108.00

COLORADO DEPARTMENT OF TRANSPORTATION
ITEM UNIT COSTS BY PROJECTS -- 2022 COST DATA

11:31 Wednesday, March 8, 2023 243

PROJECT NUMBER	ITEM NUMBER/ PROJECT LOCATION	ITEM DESCRIPTION/ PROJECT LOCATION	DATE LET	UNIT/ QUANTITY	ENGR. EST.	AVERAGE BID	AWARDED BID
=====	412-00805	Conc Pvmt (8 In) (Fast Track)		Sq Yard	=====		
SHE2873-193		US 287 & CO 52 INTERSECTION I	09/15/22	387.00	150.00	232.03	124.00
		WEIGHTED AVERAGE FOR THE THIRD QUARTER		387.00	150.00	232.03	124.00
2670703-487		I-70 BRIDGES OVER WARD ROAD-	12/01/22	141.00	190.00	203.35	170.00
		WEIGHTED AVERAGE FOR THE FOURTH QUARTER		141.00	190.00	203.35	170.00
		WEIGHTED AVERAGE FOR THE YEAR		528.00	160.68	225.35	136.28
=====	412-00850	Conc Pvmt (8-1/2 In)		Sq Yard	=====		
NHM765-007			03/31/22	38,372.00	90.00	90.56	74.63
		WEIGHTED AVERAGE FOR THE FIRST QUARTER		38,372.00	90.00	90.56	74.63
		WEIGHTED AVERAGE FOR THE YEAR		38,372.00	90.00	90.56	74.63
=====	412-00900	Conc Pvmt (9 In)		Sq Yard	=====		
NHPP0063-054		US 6 FROM I70-B TO 33 RD. (MP	08/18/22	12,878.00	100.00	142.85	155.00
		WEIGHTED AVERAGE FOR THE THIRD QUARTER		12,878.00	100.00	142.85	155.00
		WEIGHTED AVERAGE FOR THE YEAR		12,878.00	100.00	142.85	155.00
=====	412-00901	Conc Pvmt (9 In) (Spec)		Sq Yard	=====		
NHPP0063-054		US 6 FROM I70-B TO 33 RD. (MP	08/18/22	382.00	130.00	213.91	170.00
		WEIGHTED AVERAGE FOR THE THIRD QUARTER		382.00	130.00	213.91	170.00
		WEIGHTED AVERAGE FOR THE YEAR		382.00	130.00	213.91	170.00
=====	412-00920	Conc Pvmt (9 In) (Fast Track)		Sq Yard	=====		
NHPP0063-054		US 6 FROM I70-B TO 33 RD. (MP	08/18/22	420.00	300.00	158.21	175.00
		WEIGHTED AVERAGE FOR THE THIRD QUARTER		420.00	300.00	158.21	175.00
		WEIGHTED AVERAGE FOR THE YEAR		420.00	300.00	158.21	175.00

COLORADO DEPARTMENT OF TRANSPORTATION
 ITEM UNIT COSTS BY PROJECTS -- 2022 COST DATA

11:31 Wednesday, March 8, 2023 244

PROJECT NUMBER	ITEM NUMBER/ PROJECT LOCATION	ITEM DESCRIPTION/ PROJECT LOCATION	DATE LET	UNIT/ QUANTITY	ENGR. EST.	AVERAGE BID	AWARDED BID
=====	412-01000	Conc Pvmt (10 In)		Sq Yard	=====		
CR100-362			03/14/22	95.00	337.59	337.59	337.59
		WEIGHTED AVERAGE FOR THE FIRST QUARTER		95.00	337.59	337.59	337.59
IM025A-050		I25-MP103.9 - INTERSECTION DR	12/01/22	282.00	150.00	265.00	240.00
		WEIGHTED AVERAGE FOR THE FOURTH QUARTER		282.00	150.00	265.00	240.00
		WEIGHTED AVERAGE FOR THE YEAR		377.00	197.27	272.33	264.59
=====	412-01020	Conc Pvmt (10 In) (Fast Track)		Sq Yard	=====		
IM025A-050		I25-MP103.9 - INTERSECTION DR	12/01/22	556.00	250.00	281.67	250.00
		WEIGHTED AVERAGE FOR THE FOURTH QUARTER		556.00	250.00	281.67	250.00
		WEIGHTED AVERAGE FOR THE YEAR		556.00	250.00	281.67	250.00
=====	412-01050	Conc Pvmt (10-1/2 In)		Sq Yard	=====		
NHPP 0761-238 C0761-239		I-76 DAHLIA TO YORK	03/10/22	68,317.00	90.00	80.55	78.00
		WEIGHTED AVERAGE FOR THE FIRST QUARTER		68,317.00	90.00	80.55	78.00
		WEIGHTED AVERAGE FOR THE YEAR		68,317.00	90.00	80.55	78.00
=====	412-01100	Conc Pvmt (11 In)		Sq Yard	=====		
TRG0253-264 STU0252-457		I-25 AND SH 119 PARK-N-RIDE	10/27/22	4,534.00	100.00	134.58	124.00
		I-25:ALAMEDA RIVER PH 2.0	11/03/22	152.00	150.00	116.38	125.00
		WEIGHTED AVERAGE FOR THE FOURTH QUARTER		4,686.00	101.62	134.35	124.03
		WEIGHTED AVERAGE FOR THE YEAR		4,686.00	101.62	134.35	124.03
=====	412-01150	Conc Pvmt (11-1/2 In)		Sq Yard	=====		
FSA0853-122		WCR14.5 AND US-85, FORT LUPTO	12/15/22	420.00	310.00	199.92	200.00
		WEIGHTED AVERAGE FOR THE FOURTH QUARTER		420.00	310.00	199.92	200.00
		WEIGHTED AVERAGE FOR THE YEAR		420.00	310.00	199.92	200.00

COLORADO DEPARTMENT OF TRANSPORTATION
 ITEM UNIT COSTS BY PROJECTS -- 2022 COST DATA

11:31 Wednesday, March 8, 2023 245

PROJECT NUMBER	ITEM NUMBER/ PROJECT LOCATION	ITEM DESCRIPTION/ PROJECT LOCATION	DATE LET	UNIT/ QUANTITY	ENGR. EST.	AVERAGE BID	AWARDED BID
=====	412-01200	Conc Pvmt (12 In)		Sq Yard	=====		
NHPP0705-088		I-70 AGATE STRUCTURE REHAB	10/27/22	63.00	200.00	596.18	310.00
TRG0253-264		I-25 AND SH 119 PARK-N-RIDE	10/27/22	3,689.00	120.00	143.41	132.00
		WEIGHTED AVERAGE FOR THE FOURTH QUARTER		3,752.00	121.34	147.25	134.99
		WEIGHTED AVERAGE FOR THE YEAR		3,752.00	121.34	147.25	134.99
=====	412-02000	Conc Safety Edge		Lin Foot	=====		
NHPP 0761-238		I-76 DAHLIA TO YORK	03/10/22	4,871.00	6.00	5.03	4.00
C0761-239							
		WEIGHTED AVERAGE FOR THE FIRST QUARTER		4,871.00	6.00	5.03	4.00
		WEIGHTED AVERAGE FOR THE YEAR		4,871.00	6.00	5.03	4.00
=====	412-05000	Partial Depth Repair of Conc Pvmt		Sq Foot	=====		
STA0252-459			02/03/22	330.00	300.00	236.07	163.60
C0762-055			02/17/22	1,000.00	50.00	121.19	120.00
		WEIGHTED AVERAGE FOR THE FIRST QUARTER		1,330.00	112.03	143.98	130.82
		WEIGHTED AVERAGE FOR THE YEAR		1,330.00	112.03	143.98	130.82
=====	412-05002	Full Depth Repair of Conc Pavement		Sq Foot	=====		
STA0252-459			02/03/22	330.00	180.00	321.10	240.00
C0762-055			02/17/22	246,294.00	8.75	10.84	11.00
		WEIGHTED AVERAGE FOR THE FIRST QUARTER		246,624.00	8.98	11.15	11.31
		WEIGHTED AVERAGE FOR THE YEAR		246,624.00	8.98	11.15	11.31
=====	412-05100	Poly Slab Jacking		Pound	=====		
NHPP0021-041		SH2 RESURFACING MLK TO 52ND	12/01/22	1,247.00	8.00	18.82	19.93
		WEIGHTED AVERAGE FOR THE FOURTH QUARTER		1,247.00	8.00	18.82	19.93
		WEIGHTED AVERAGE FOR THE YEAR		1,247.00	8.00	18.82	19.93

COLORADO DEPARTMENT OF TRANSPORTATION
 ITEM UNIT COSTS BY PROJECTS -- 2022 COST DATA

11:31 Wednesday, March 8, 2023 246

PROJECT NUMBER	ITEM NUMBER/ PROJECT LOCATION	ITEM DESCRIPTION/ PROJECT LOCATION	DATE LET	UNIT/ QUANTITY	ENGR. EST.	AVERAGE BID	AWARDED BID
=====	412-14000	Sawing and Sealing Joints		Lin Foot	=====		
STA0252-459			02/03/22	381,522.90	1.80	2.33	2.50
C0762-055			02/17/22	292,140.00	1.90	2.19	2.25
	WEIGHTED AVERAGE FOR THE FIRST QUARTER			673,662.90	1.84	2.26	2.39
	WEIGHTED AVERAGE FOR THE YEAR			673,662.90	1.84	2.26	2.39
=====	412-15000	Routing and Sealing Cracks		Lin Foot	=====		
STA0252-459			02/03/22	1,056.55	28.00	21.93	11.25
	WEIGHTED AVERAGE FOR THE FIRST QUARTER			1,056.55	28.00	21.93	11.25
	WEIGHTED AVERAGE FOR THE YEAR			1,056.55	28.00	21.93	11.25
=====	412-15060	Rep Conc Cr (Stitch)		Each	=====		
STA0252-459			02/03/22	493.00	35.70	88.67	119.00
	WEIGHTED AVERAGE FOR THE FIRST QUARTER			493.00	35.70	88.67	119.00
	WEIGHTED AVERAGE FOR THE YEAR			493.00	35.70	88.67	119.00
=====	420-00000	Geomembrane		Sq Yard	=====		
NHPP0702-413		VAIL PASS AUX PHASE 1 CAP 2	04/18/22	2,700.00	20.65	20.65	20.65
2670703-479		I-70 BRIDGE OVER HARLAN	05/05/22	6,320.00	14.00	9.66	8.90
	WEIGHTED AVERAGE FOR THE SECOND QUARTER			9,020.00	15.99	10.39	12.42
NHPP0702-414		VAIL PASS AUX PHASE 1 CAP 3	07/08/22	1,423.00	29.26	29.26	29.26
FBR0702-423		VAIL PASS AUX BE F-12-AT PHAS					
	WEIGHTED AVERAGE FOR THE THIRD QUARTER			1,423.00	29.26	29.26	29.26
STAM420-001		US 285 AT HWY 9C IMPROVEMENTS	12/01/22	1,354.00	15.00	12.03	11.68

COLORADO DEPARTMENT OF TRANSPORTATION
ITEM UNIT COSTS BY PROJECTS -- 2022 COST DATA

11:31 Wednesday, March 8, 2023 247

PROJECT NUMBER	ITEM NUMBER/ PROJECT LOCATION	ITEM DESCRIPTION/ PROJECT LOCATION	DATE LET	UNIT/ QUANTITY	ENGR. EST.	AVERAGE BID	AWARDED BID
===== 420-00000 Geomembrane Sq Yard =====							
BR2854-148		INTERSECTION OF US 285 & SH 9					
STM0091-046		ADA RAMP IMPROVEMENTS - FAIRP					
2670703-487		I-70 BRIDGES OVER WARD ROAD-	12/01/22	3,492.00	14.00	12.82	7.40
IM025A-050		I25-MP103.9 - INTERSECTION DR	12/01/22	525.00	10.00	17.00	18.00
	WEIGHTED AVERAGE FOR THE FOURTH QUARTER			5,371.00	13.86	12.91	9.52
	WEIGHTED AVERAGE FOR THE YEAR			15,814.00	16.46	11.72	12.95
===== 420-00102 Geotextile (Er Cont) (CL 1) Sq Yard =====							
NH0504-910		US50B L-24-B MIN REP AT MP 40	01/13/22	145.00	10.00	10.48	6.25
NHPP0702-383		I-70 EB AUX FRISCO TO SILVERT	01/13/22	245.00	8.60	21.67	24.00
	WEIGHTED AVERAGE FOR THE FIRST QUARTER			390.00	9.12	16.23	17.40
NHPP0702-413		VAIL PASS AUX PHASE 1 CAP 2	04/18/22	224.00	116.87	116.87	116.87
	WEIGHTED AVERAGE FOR THE SECOND QUARTER			224.00	116.87	116.87	116.87
FSA052A-057		SH52 BOX CULVERT EXTENSION (M	08/04/22	63.00	9.00	11.65	6.50
BR0343-046		US 34 TIMBER BRIDGE REPL. PKG	08/31/22	24.00	6.86	3.68	3.68
FBR0343-047		US 6/US 34 TIMBER BRIDGE REPL					
NHPPR100-266		R1 ESSENTIAL REPAIRS	09/01/22	77.00	15.00	17.15	10.44
2670403-065		US40 FLOYD HILL ROUNDABOUTS	09/15/22	71.00	15.00	16.86	18.00
NHPP0701-231		I-70 SALT WASH BRIDGES SCOUR	09/29/22	1,006.00	5.00	13.64	20.00
	WEIGHTED AVERAGE FOR THE THIRD QUARTER			1,241.00	6.43	13.97	18.29
NHPP0705-088		I-70 AGATE STRUCTURE REHAB	10/27/22	36.00	20.00	16.45	14.00
STU0252-457		I-25:ALAMEDA RIVER PH 2.0	11/03/22	2,838.00	6.00	6.37	4.20
	WEIGHTED AVERAGE FOR THE FOURTH QUARTER			2,874.00	6.18	6.54	4.32
	WEIGHTED AVERAGE FOR THE YEAR			4,729.00	11.73	11.39	14.40
===== 420-00103 Geotextile (Er Cont) (CL 2) Sq Yard =====							
STR0711-022		SH 71 OVER THE ARKANSAS	08/04/22	225.00	25.00	13.92	9.00
	WEIGHTED AVERAGE FOR THE THIRD QUARTER			225.00	25.00	13.92	9.00

COLORADO DEPARTMENT OF TRANSPORTATION
 ITEM UNIT COSTS BY PROJECTS -- 2022 COST DATA

11:31 Wednesday, March 8, 2023 248

PROJECT NUMBER	ITEM NUMBER/ PROJECT LOCATION	ITEM DESCRIPTION/ PROJECT LOCATION	DATE LET	UNIT/ QUANTITY	ENGR. EST.	AVERAGE BID	AWARDED BID
=====	420-00103	Geotextile (Er Cont) (CL 2)		Sq Yard	=====		
2670703-487		I-70 BRIDGES OVER WARD ROAD-	12/01/22	31.00	5.00	25.44	22.00
	WEIGHTED AVERAGE FOR THE FOURTH QUARTER			31.00	5.00	25.44	22.00
	WEIGHTED AVERAGE FOR THE YEAR			256.00	22.58	16.07	10.57
=====	420-00112	Geotextile (Drain) (CL 1)		Sq Yard	=====		
STM1151-038		SH115 MP 27 TO MP 38	04/21/22	275.10	10.00	12.65	3.63
FSA052A-046		SH52 WCR 37 INTERSECTION IMPR	06/09/22	201.20	5.00	13.79	3.50
	WEIGHTED AVERAGE FOR THE SECOND QUARTER			476.30	7.89	13.13	3.58
2670703-497		I-70_GENESEE WILDLIFE KING	09/15/22	106.00	7.00	13.58	3.95
	WEIGHTED AVERAGE FOR THE THIRD QUARTER			106.00	7.00	13.58	3.95
TRG0253-264		I-25 AND SH 119 PARK-N-RIDE	10/27/22	428.00	5.00	7.12	10.00
NHPP0343-048		US 34 (MP 169.3-171.4)	11/01/22	1,215.00	3.90	5.83	4.00
STA0711-021		SH71: REGION LINE NORTH	12/01/22	49.00	10.00	5.53	6.00
NHPP0063-048		US6 / 20 ROAD INTERSECTION IM	12/15/22	31.00	100.00	70.31	40.00
	WEIGHTED AVERAGE FOR THE FOURTH QUARTER			1,723.00	6.08	7.28	6.20
	WEIGHTED AVERAGE FOR THE YEAR			2,305.30	6.49	8.87	5.55
=====	420-00113	Geotextile (Drain) (CL 2)		Sq Yard	=====		
NHPP 0761-238		I-76 DAHLIA TO YORK	03/10/22	22.00	20.00	33.51	44.00
C0761-239			03/17/22	310.00	10.00	11.63	13.50
BRC040-057							
	WEIGHTED AVERAGE FOR THE FIRST QUARTER			332.00	10.66	14.35	15.52
NHPP0702-413		VAIL PASS AUX PHASE 1 CAP 2	04/18/22	1,400.00	8.77	8.77	8.77
	WEIGHTED AVERAGE FOR THE SECOND QUARTER			1,400.00	8.77	8.77	8.77

COLORADO DEPARTMENT OF TRANSPORTATION
 ITEM UNIT COSTS BY PROJECTS -- 2022 COST DATA

11:31 Wednesday, March 8, 2023 249

PROJECT NUMBER	ITEM NUMBER/ PROJECT LOCATION	ITEM DESCRIPTION/ PROJECT LOCATION	DATE LET	UNIT/ QUANTITY	ENGR. EST.	AVERAGE BID	AWARDED BID
=====	420-00113	Geotextile (Drain) (CL 2)		Sq Yard	=====		
NHPP0702-414		VAIL PASS AUX PHASE 1 CAP 3	07/08/22	954.00	8.84	8.84	8.84
FBR0702-423		VAIL PASS AUX BE F-12-AT PHAS					
NHPP0063-054		US 6 FROM I70-B TO 33 RD. (MP	08/18/22	3,012.00	4.00	3.23	2.75
		WEIGHTED AVERAGE FOR THE THIRD QUARTER		3,966.00	5.16	3.99	4.21
STA3852-015		US 385 HOLYOKE NORTH	10/27/22	147.00	20.00	5.08	5.08
STU0252-457		I-25:ALAMEDA RIVER PH 2.0	11/03/22	3,985.00	6.50	4.76	5.30
		WEIGHTED AVERAGE FOR THE FOURTH QUARTER		4,132.00	6.98	4.76	5.29
		WEIGHTED AVERAGE FOR THE YEAR		9,830.00	6.63	5.39	5.70
=====	420-00114	Geotextile (Drain) (CL 3)		Sq Yard	=====		
STAM420-001		US 285 AT HWY 9C IMPROVEMENTS	12/01/22	59.00	3.50	57.55	22.83
BR2854-148		INTERSECTION OF US 285 & SH 9					
STM0091-046		ADA RAMP IMPROVEMENTS - FAIRP					
		WEIGHTED AVERAGE FOR THE FOURTH QUARTER		59.00	3.50	57.55	22.83
		WEIGHTED AVERAGE FOR THE YEAR		59.00	3.50	57.55	22.83
=====	420-00132	Geotextile (Separator) (CL 1)		Sq Yard	=====		
STA0712-019		SH 71: Frieight Improvements	05/12/22	1,000.00	5.00	7.65	7.65
NHPP 3851-018		US 385 NORTH OF CHEYENNE WELL	05/26/22	2,500.00	5.00	4.63	3.00
		WEIGHTED AVERAGE FOR THE SECOND QUARTER		3,500.00	5.00	5.13	4.33
TRG0253-264		I-25 AND SH 119 PARK-N-RIDE	10/27/22	14,866.00	3.50	3.79	2.50
STA0711-021		SH71: REGION LINE NORTH	12/01/22	275.00	10.00	5.63	6.00
		WEIGHTED AVERAGE FOR THE FOURTH QUARTER		15,141.00	3.62	3.83	2.64
		WEIGHTED AVERAGE FOR THE YEAR		18,641.00	3.88	3.89	2.95

COLORADO DEPARTMENT OF TRANSPORTATION
ITEM UNIT COSTS BY PROJECTS -- 2022 COST DATA

11:31 Wednesday, March 8, 2023 250

PROJECT NUMBER	ITEM NUMBER/ PROJECT LOCATION	ITEM DESCRIPTION/ PROJECT LOCATION	DATE LET	UNIT/ QUANTITY	ENGR. EST.	AVERAGE BID	AWARDED BID
=====	420-00133	Geotextile (Separator) (CL 2)		Sq Yard	=====		
NHPP1601-083			02/03/22	1,505.00	10.00	10.45	6.00
		WEIGHTED AVERAGE FOR THE FIRST QUARTER		1,505.00	10.00	10.45	6.00
NHPP0701-252		I-70 RIFLE TO SILT SLAB REPLA	12/01/22	335.00	10.00	10.00	10.00
		WEIGHTED AVERAGE FOR THE FOURTH QUARTER		335.00	10.00	10.00	10.00
		WEIGHTED AVERAGE FOR THE YEAR		1,840.00	10.00	10.36	6.73
=====	420-00134	Geotextile (Separator) (CL 3)		Sq Yard	=====		
C5502-097		US550 MP 117.28-126.06	11/17/22	298.00	5.00	2.09	2.30
		WEIGHTED AVERAGE FOR THE FOURTH QUARTER		298.00	5.00	2.09	2.30
		WEIGHTED AVERAGE FOR THE YEAR		298.00	5.00	2.09	2.30
=====	420-00200	Geotextile (Weed Barrier)		Sq Yard	=====		
NHPP0703-472			03/10/22	1,685.00	7.00	6.00	2.65
		WEIGHTED AVERAGE FOR THE FIRST QUARTER		1,685.00	7.00	6.00	2.65
		WEIGHTED AVERAGE FOR THE YEAR		1,685.00	7.00	6.00	2.65
=====	420-00300	Geotextile (Reinforcement)		Sq Yard	=====		
2670703-479		I-70 BRIDGE OVER HARLAN	05/05/22	639.00	5.00	10.18	12.25
		WEIGHTED AVERAGE FOR THE SECOND QUARTER		639.00	5.00	10.18	12.25
ER0502-092		US 50 MP 204 EB MONARCH TRUCK	08/29/22	578.00	10.00	21.63	28.89
		WEIGHTED AVERAGE FOR THE THIRD QUARTER		578.00	10.00	21.63	28.89

COLORADO DEPARTMENT OF TRANSPORTATION
 ITEM UNIT COSTS BY PROJECTS -- 2022 COST DATA

11:31 Wednesday, March 8, 2023 251

PROJECT NUMBER	ITEM NUMBER/ PROJECT LOCATION	ITEM DESCRIPTION/ PROJECT LOCATION	DATE LET	UNIT/ QUANTITY	ENGR. EST.	AVERAGE BID	AWARDED BID
=====	420-00300	Geotextile (Reinforcement)		Sq Yard	=====		
STA207A-004		Resurfacing SH207A MANZANOLA	10/27/22	866.00	4.00	5.20	7.10
	WEIGHTED AVERAGE FOR THE FOURTH QUARTER			866.00	4.00	5.20	7.10
	WEIGHTED AVERAGE FOR THE YEAR			2,083.00	5.97	11.03	14.73
=====	420-00510	Geotextile (Cr Reduc) (H D)		Sq Yard	=====		
NHPP1601-083			02/03/22	267.00	45.00	38.97	40.00
	WEIGHTED AVERAGE FOR THE FIRST QUARTER			267.00	45.00	38.97	40.00
STR114A-015		SH114 SILLSVILLE SOUTH TO MP3	12/01/22	315.00	65.00	38.00	44.00
	WEIGHTED AVERAGE FOR THE FOURTH QUARTER			315.00	65.00	38.00	44.00
	WEIGHTED AVERAGE FOR THE YEAR			582.00	55.82	38.44	42.16
=====	501-00200	Steel Sheet Pile (Ty II)		Sq Foot	=====		
NHPP0343-048		US 34 (MP 169.3-171.4)	11/01/22	27,040.00	75.00	52.62	42.00
	WEIGHTED AVERAGE FOR THE FOURTH QUARTER			27,040.00	75.00	52.62	42.00
	WEIGHTED AVERAGE FOR THE YEAR			27,040.00	75.00	52.62	42.00
=====	502-00100	Drill Hole Fac Pile Driving		Lin Foot	=====		
2670703-497		I-70_GENESEE WILDLIFE XING	09/15/22	247.00	144.00	234.17	27.39
	WEIGHTED AVERAGE FOR THE THIRD QUARTER			247.00	144.00	234.17	27.39
2670703-487		I-70 BRIDGES OVER WARD ROAD-	12/01/22	2,354.00	40.00	43.45	13.00
	WEIGHTED AVERAGE FOR THE FOURTH QUARTER			2,354.00	40.00	43.45	13.00
	WEIGHTED AVERAGE FOR THE YEAR			2,601.00	49.88	67.88	14.37

COLORADO DEPARTMENT OF TRANSPORTATION
ITEM UNIT COSTS BY PROJECTS -- 2022 COST DATA

11:31 Wednesday, March 8, 2023 252

PROJECT NUMBER	ITEM NUMBER/ PROJECT LOCATION	ITEM DESCRIPTION/ PROJECT LOCATION	DATE LET	UNIT/ QUANTITY	ENGR. EST.	AVERAGE BID	AWARDED BID
===== 502-00460 File Tip Each =====							
NHPP0702-383		I-70 EB AUX FRISCO TO SILVERT	01/13/22	14.00	250.00	273.07	350.00
NHPP 0761-238		I-76 DAHLIA TO YORK	03/10/22	37.00	200.00	188.11	300.00
C0761-239							
NHPP0253-275		I-25 EXPRESS LANES SEGMENT 5	03/11/22	64.00	257.75	133.75	133.75
		WEIGHTED AVERAGE FOR THE FIRST QUARTER		115.00	238.23	193.85	213.57
STM1151-038		SH115 MP 27 TO MP 38	04/21/22	26.00	210.00	268.29	185.00
2670703-479		I-70 BRIDGE OVER HARLAN	05/05/22	46.00	210.00	249.92	209.54
		WEIGHTED AVERAGE FOR THE SECOND QUARTER		72.00	210.00	255.80	200.68
2670703-497		I-70_GENESEE WILDLIFE KING	09/15/22	24.00	230.00	304.64	159.03
		WEIGHTED AVERAGE FOR THE THIRD QUARTER		24.00	230.00	304.64	159.03
2670703-487		I-70 BRIDGES OVER WARD ROAD-	12/01/22	44.00	243.10	382.10	260.00
IM025A-050		I25-MP103.9 - INTERSECTION DR	12/01/22	4.00	200.00	210.00	160.00
BR012A-048		CO 12 STRUCTURE P-17-F AT MP	12/22/22	18.00	200.00	472.55	500.00
		WEIGHTED AVERAGE FOR THE FOURTH QUARTER		66.00	228.73	375.68	298.50
		WEIGHTED AVERAGE FOR THE YEAR		277.00	227.91	271.17	229.23
===== 502-00500 CJP Splice Each =====							
NHPP0702-383		I-70 EB AUX FRISCO TO SILVERT	01/13/22	2.00	1500.00	1098.57	1600.00
NHPP0253-275		I-25 EXPRESS LANES SEGMENT 5	03/11/22	8.00	664.57	1289.84	1289.84
		WEIGHTED AVERAGE FOR THE FIRST QUARTER		10.00	831.66	1183.58	1351.87
STM1151-038		SH115 MP 27 TO MP 38	04/21/22	26.00	1300.00	862.23	1.00

COLORADO DEPARTMENT OF TRANSPORTATION
ITEM UNIT COSTS BY PROJECTS -- 2022 COST DATA

11:31 Wednesday, March 8, 2023 253

PROJECT NUMBER	ITEM NUMBER/ PROJECT LOCATION	ITEM DESCRIPTION/ PROJECT LOCATION	DATE LET	UNIT/ QUANTITY	ENGR. EST.	AVERAGE BID	AWARDED BID
===== 502-00500		CJP Splice		Each			
2670703-479		I-70 BRIDGE OVER HARLAN	05/05/22	4.00	1500.00	1215.16	1899.30
		WEIGHTED AVERAGE FOR THE SECOND QUARTER		30.00	1326.67	917.23	254.11
2670703-487		I-70 BRIDGES OVER WARD ROAD-	12/01/22	4.00	2000.00	832.29	1000.00
IM025A-050		I25-MP103.9 - INTERSECTION DR	12/01/22	4.00	1000.00	404.00	310.00
		WEIGHTED AVERAGE FOR THE FOURTH QUARTER		8.00	1500.00	1302.11	184.44
		WEIGHTED AVERAGE FOR THE YEAR		48.00	1252.43	1107.79	365.55
===== 502-02000		Dynamic Load Testing		LUMP SUM			
NHPP0702-383		I-70 EB AUX FRISCO TO SILVERT	01/13/22	1.00	32000.00	3828.44	5300.00
		WEIGHTED AVERAGE FOR THE FIRST QUARTER		1.00	32000.00	3828.44	5300.00
		WEIGHTED AVERAGE FOR THE YEAR		1.00	32000.00	3828.44	5300.00
===== 502-02010		Dynamic Pile Test		Each			
STM1151-038		SH115 MP 27 TO MP 38	04/21/22	2.00	3000.00	3670.86	2500.00
2670703-479		I-70 BRIDGE OVER HARLAN	05/05/22	2.00	3000.00	3658.49	4049.05
		WEIGHTED AVERAGE FOR THE SECOND QUARTER		4.00	3000.00	3664.11	3274.53
2670703-497		I-70_GENESEE WILDLIFE XING	09/15/22	4.00	2900.00	4254.39	3066.90
		WEIGHTED AVERAGE FOR THE THIRD QUARTER		4.00	2900.00	4254.39	3066.90
2670703-487		I-70 BRIDGES OVER WARD ROAD-	12/01/22	6.00	5000.00	4536.87	3710.00
IM025A-050		I25-MP103.9 - INTERSECTION DR	12/01/22	1.00	3000.00	4166.67	4500.00
		WEIGHTED AVERAGE FOR THE FOURTH QUARTER		7.00	4714.29	4503.22	3822.86
		WEIGHTED AVERAGE FOR THE YEAR		15.00	3773.33	4196.86	3475.05

COLORADO DEPARTMENT OF TRANSPORTATION
ITEM UNIT COSTS BY PROJECTS -- 2022 COST DATA

11:31 Wednesday, March 8, 2023 254

PROJECT NUMBER	ITEM NUMBER/ PROJECT LOCATION	ITEM DESCRIPTION/ PROJECT LOCATION	DATE LET	UNIT/ QUANTITY	ENGR. EST.	AVERAGE BID	AWARDED BID
=====	502-02012	Static Pile Load Test		Each	=====	=====	=====
NHPP 0761-238 C0761-239		I-76 DAHLIA TO YORK	03/10/22	1.00	10000.00	15076.27	12000.00
		WEIGHTED AVERAGE FOR THE FIRST QUARTER		1.00	10000.00	15076.27	12000.00
STM1151-038 2670703-479		SH115 MP 27 TO MP 38	04/21/22	1.00	15000.00	15658.96	8000.00
		I-70 BRIDGE OVER HARLAN	05/05/22	1.00	3000.00	28242.49	42964.97
		WEIGHTED AVERAGE FOR THE SECOND QUARTER		2.00	9000.00	22522.70	25482.49
		WEIGHTED AVERAGE FOR THE YEAR		3.00	9333.33	19387.36	20988.32
=====	502-11057	Steel Pile (HP 10x57)		Lin Foot	=====	=====	=====
NHPP0702-383		I-70 EB AUX FRISCO TO SILVERT	01/13/22	37.00	100.00	206.20	106.00
		WEIGHTED AVERAGE FOR THE FIRST QUARTER		37.00	100.00	206.20	106.00
		WEIGHTED AVERAGE FOR THE YEAR		37.00	100.00	206.20	106.00
=====	502-11274	Steel Pile (HP 12x74)		Lin Foot	=====	=====	=====
NHPP0702-383 NHPP 0761-238 C0761-239		I-70 EB AUX FRISCO TO SILVERT	01/13/22	360.00	100.00	211.28	210.00
		I-76 DAHLIA TO YORK	03/10/22	1,258.00	86.00	134.50	200.00
		WEIGHTED AVERAGE FOR THE FIRST QUARTER		1,618.00	89.11	146.15	202.22
		WEIGHTED AVERAGE FOR THE YEAR		1,618.00	89.11	147.88	200.47
=====	502-11284	Steel Pile (HP 12x84)		Lin Foot	=====	=====	=====
BR012A-048		CO 12 STRUCTURE P-17-F AT MP	12/22/22	320.00	160.00	307.94	275.00
		WEIGHTED AVERAGE FOR THE FOURTH QUARTER		320.00	160.00	307.94	275.00
		WEIGHTED AVERAGE FOR THE YEAR		320.00	160.00	307.94	275.00

COLORADO DEPARTMENT OF TRANSPORTATION
ITEM UNIT COSTS BY PROJECTS -- 2022 COST DATA

11:31 Wednesday, March 8, 2023 255

PROJECT NUMBER	ITEM NUMBER/ PROJECT LOCATION	ITEM DESCRIPTION/ PROJECT LOCATION	DATE LET	UNIT/ QUANTITY	ENGR. EST.	AVERAGE BID	AWARDED BID
===== 502-11489 Steel Pile (HP 14x89) Lin Foot =====							
NHPP0253-275		I-25 EXPRESS LANES SEGMENT 5	03/11/22	3,200.00	152.31	160.83	160.83
		WEIGHTED AVERAGE FOR THE FIRST QUARTER		3,200.00	152.31	160.83	160.83
STM1151-038		SH115 MP 27 TO MP 38	04/21/22	1,274.00	150.00	125.61	150.00
2670703-479		I-70 BRIDGE OVER HARLAN	05/05/22	1,928.00	110.00	175.80	150.00
		WEIGHTED AVERAGE FOR THE SECOND QUARTER		3,202.00	125.92	157.98	150.00
2670703-497		I-70_GENESEE WILDLIFE XING	09/15/22	1,008.00	140.00	156.15	110.25
		WEIGHTED AVERAGE FOR THE THIRD QUARTER		1,008.00	140.00	156.15	110.25
2670703-487		I-70 BRIDGES OVER WARD ROAD-	12/01/22	2,482.00	135.00	149.83	140.00
		WEIGHTED AVERAGE FOR THE FOURTH QUARTER		2,482.00	135.00	154.71	151.64
		WEIGHTED AVERAGE FOR THE YEAR		9,892.00	138.17	156.80	149.93
===== 502-14117 Steel Pile (HP 14x117) Lin Foot =====							
IM025A-050		I25-MP103.9 - INTERSECTION DR	12/01/22	110.00	150.00	333.33	290.00
		WEIGHTED AVERAGE FOR THE FOURTH QUARTER		110.00	150.00	211.34	265.67
		WEIGHTED AVERAGE FOR THE YEAR		110.00	150.00	211.34	265.67
===== 503-00018 Drilled Shaft (18 In) Lin Foot =====							
NHPP 0761-238		I-76 DAHLIA TO YORK	03/10/22	16.00	320.00	279.99	210.00
C0761-239		WEIGHTED AVERAGE FOR THE FIRST QUARTER		16.00	320.00	279.99	210.00

COLORADO DEPARTMENT OF TRANSPORTATION
ITEM UNIT COSTS BY PROJECTS -- 2022 COST DATA

11:31 Wednesday, March 8, 2023 256

PROJECT NUMBER	ITEM NUMBER/ PROJECT LOCATION	ITEM DESCRIPTION/ PROJECT LOCATION	DATE LET	UNIT/ QUANTITY	ENGR. EST.	AVERAGE BID	AWARDED BID
===== 503-00018 Drilled Shaft (18 In) Lin Foot =====							
CC030-081		ADA RAMP AND CURBS - FT. LUPT	04/14/22	5.00	250.00	360.63	400.00
2670703-479		I-70 BRIDGE OVER HARLAN	05/05/22	10.00	330.00	151.61	179.36
		WEIGHTED AVERAGE FOR THE SECOND QUARTER		15.00	303.33	193.41	252.91
NHPP0063-054		US 6 FROM I70-B TO 33 RD. (MP	08/18/22	20.00	350.00	421.39	365.00
C1211-099		SH 121 NORTH SGA SIGNALS	08/25/22	20.00	350.00	397.50	395.00
		WEIGHTED AVERAGE FOR THE THIRD QUARTER		40.00	350.00	409.45	380.00
FSAM240-200		SH21B CO SPRINGS SIGNAL REPLA	10/27/22	30.00	300.00	371.25	305.00
TRG0253-264		I-25 AND SH 119 PARK-N-RIDE	10/27/22	32.00	400.00	218.51	520.00
STAM420-001		US 285 AT HWY 9C IMPROVEMENTS	12/01/22	25.00	370.00	474.86	595.77
BR2854-148		INTERSECTION OF US 285 & SH 9					
STM0091-046		ADA RAMP IMPROVEMENTS - FAIRP					
NHPP0931-033		SH93:US6 TO 58TH RESURFACING	12/15/22	5.00	300.00	239.87	222.50
		WEIGHTED AVERAGE FOR THE FOURTH QUARTER		92.00	353.80	308.01	454.31
		WEIGHTED AVERAGE FOR THE YEAR		163.00	344.91	302.79	393.56
===== 503-00024 Drilled Shaft (24 In) Lin Foot =====							
NHPP0702-383		I-70 EB AUX FRISCO TO SILVERT	01/13/22	9.00	360.00	1136.12	1300.00
NHPP 0761-238		I-76 DAHLIA TO YORK	03/10/22	8.00	350.00	455.98	410.00
C0761-239							
		WEIGHTED AVERAGE FOR THE FIRST QUARTER		17.00	355.29	736.77	881.18
2670703-479		I-70 BRIDGE OVER HARLAN	05/05/22	9.00	500.00	454.30	534.14
ITS 0741-024		VMS SIGN INSTALLATIONS AND VS	06/02/22	113.00	500.00	1107.50	650.00
		WEIGHTED AVERAGE FOR THE SECOND QUARTER		122.00	500.00	981.53	641.45

COLORADO DEPARTMENT OF TRANSPORTATION
ITEM UNIT COSTS BY PROJECTS -- 2022 COST DATA

11:31 Wednesday, March 8, 2023 257

PROJECT NUMBER	ITEM NUMBER/ PROJECT LOCATION	ITEM DESCRIPTION/ PROJECT LOCATION	DATE LET	UNIT/ QUANTITY	ENGR. EST.	AVERAGE BID	AWARDED BID
===== 503-00024 Drilled Shaft (24 In) Lin Foot =====							
TRG0253-264		I-25 AND SH 119 PARK-N-RIDE	10/27/22	23.00	1300.00	446.08	690.00
STU0252-457		I-25:ALAMEDA RIVER PH 2.0	11/03/22	2,847.00	600.00	285.00	230.00
		WEIGHTED AVERAGE FOR THE FOURTH QUARTER		2,870.00	605.61	288.40	233.69
		WEIGHTED AVERAGE FOR THE YEAR		3,009.00	599.91	315.05	253.88
===== 503-00030 Drilled Shaft (30 In) Lin Foot =====							
NHPP 0761-238 C0761-239		I-76 DAHLIA TO YORK	03/10/22	329.00	420.00	400.98	350.00
		WEIGHTED AVERAGE FOR THE FIRST QUARTER		329.00	420.00	400.98	350.00
NHPP0702-413		VAIL PASS AUX PHASE 1 CAP 2	04/18/22	697.00	600.48	600.48	600.48
		WEIGHTED AVERAGE FOR THE SECOND QUARTER		697.00	600.48	600.48	600.48
NHPP0702-414 FBR0702-423		VAIL PASS AUX PHASE 1 CAP 3	07/08/22	300.00	412.01	412.01	412.01
		VAIL PASS AUX BE F-12-AT PHAS					
		WEIGHTED AVERAGE FOR THE THIRD QUARTER		300.00	412.01	412.01	412.01
IM025A-050		I25-MP103.9 - INTERSECTION DR	12/01/22	141.00	400.00	575.00	450.00
		WEIGHTED AVERAGE FOR THE FOURTH QUARTER		141.00	400.00	575.00	450.00
		WEIGHTED AVERAGE FOR THE YEAR		1,467.00	502.19	454.28	491.30
===== 503-00036 Drilled Shaft (36 In) Lin Foot =====							
NHPP 0761-238		I-76 DAHLIA TO YORK	03/10/22	19.00	580.00	508.44	465.00

COLORADO DEPARTMENT OF TRANSPORTATION
ITEM UNIT COSTS BY PROJECTS -- 2022 COST DATA

11:31 Wednesday, March 8, 2023 258

PROJECT NUMBER	ITEM NUMBER/ PROJECT LOCATION	ITEM DESCRIPTION/ PROJECT LOCATION	DATE LET	UNIT/ QUANTITY	ENGR. EST.	AVERAGE BID	AWARDED BID
===== 503-00036 Drilled Shaft (36 In) Lin Foot =====							
C0761-239							
	WEIGHTED AVERAGE FOR THE FIRST QUARTER			19.00	580.00	508.44	465.00
STM1151-038		SH115 MP 27 TO MP 38	04/21/22	32.00	650.00	759.31	720.00
2670703-479		I-70 BRIDGE OVER HARLAN	05/05/22	1,161.00	350.00	304.03	225.00
CM760-047		COLFAX AND QUAIL	05/12/22	30.00	430.00	508.60	473.00
NHPP072A-047		SH-72 RESURFACING: I-70 TO IN	06/09/22	76.00	450.00	743.17	743.17
	WEIGHTED AVERAGE FOR THE SECOND QUARTER			1,299.00	365.09	322.65	273.24
NHPP0063-054		US 6 FROM I70-B TO 33 RD. (MP	08/18/22	19.00	700.00	785.93	680.00
C1211-099		SH 121 NORTH SGA SIGNALS	08/25/22	86.00	600.00	740.00	680.00
	WEIGHTED AVERAGE FOR THE THIRD QUARTER			105.00	618.10	748.31	680.00
STU0252-457		I-25:ALAMEDA RIVER PH 2.0	11/03/22	96.00	900.00	807.87	830.00
STRC090-011		US 50B AND SH71/CR18 INTERSEC	11/17/22	38.00	800.00	925.00	1000.00
STAM420-001		US 285 AT HWY 9C IMPROVEMENTS	12/01/22	1,321.00	800.00	679.69	675.00
BR2854-148		INTERSECTION OF US 285 & SH 9					
STM0091-046		ADA RAMP IMPROVEMENTS - FAIRP					
2670703-487		I-70 BRIDGES OVER WARD ROAD-	12/01/22	16.00	400.00	604.65	640.00
NHPP0063-048		US6 / 20 ROAD INTERSECTION IM	12/15/22	38.00	750.00	1069.71	990.00
NHPP0931-033		SH93:US6 TO 58TH RESURFACING	12/15/22	38.00	700.00	724.10	612.20
	WEIGHTED AVERAGE FOR THE FOURTH QUARTER			1,547.00	798.38	698.85	698.43
	WEIGHTED AVERAGE FOR THE YEAR			2,970.00	601.10	496.29	510.32
===== 503-00042 Drilled Shaft (42 In) Lin Foot =====							
NHPP 0761-238		I-76 DAHLIA TO YORK	03/10/22	17.00	600.00	772.63	550.00
C0761-239							
M R100-351		FY22 R1 SIGN STRUCTURE REPLAC	03/17/22	19.00	1500.00	1477.00	1618.00
	WEIGHTED AVERAGE FOR THE FIRST QUARTER			36.00	1075.00	926.46	1113.67
2670703-479		I-70 BRIDGE OVER HARLAN	05/05/22	17.00	600.00	596.79	704.33

COLORADO DEPARTMENT OF TRANSPORTATION
ITEM UNIT COSTS BY PROJECTS -- 2022 COST DATA

11:31 Wednesday, March 8, 2023 259

PROJECT NUMBER	ITEM NUMBER/ PROJECT LOCATION	ITEM DESCRIPTION/ PROJECT LOCATION	DATE LET	UNIT/ QUANTITY	ENGR. EST.	AVERAGE BID	AWARDED BID
===== 503-00042							
NHC540-017		Drilled Shaft (42 In)		Lin Foot			
ITS 0741-024		R2 CHAINUP STA @ KENOSHA/HOOS	05/12/22	18.00	554.00	1233.33	1200.00
		VMS SIGN INSTALLATIONS AND VS	06/02/22	34.00	500.00	1935.50	800.00
		WEIGHTED AVERAGE FOR THE SECOND QUARTER		69.00	538.72	1156.64	880.78
NHPP0702-414		VAIL PASS AUX PHASE 1 CAP 3	07/08/22	19.00	615.88	615.88	615.88
FBR0702-423		VAIL PASS AUX BE F-12-AT PHAS					
C1211-099		SH 121 NORTH SGA SIGNALS	08/25/22	17.00	700.00	807.50	750.00
		WEIGHTED AVERAGE FOR THE THIRD QUARTER		36.00	655.60	738.81	679.21
FSAM240-200		SH21B CO SPRINGS SIGNAL REPLA	10/27/22	21.00	450.00	922.50	1190.00
		WEIGHTED AVERAGE FOR THE FOURTH QUARTER		21.00	450.00	922.50	1190.00
		WEIGHTED AVERAGE FOR THE YEAR		162.00	672.37	1003.62	927.82
===== 503-00048							
Drilled Shaft (48 In) Lin Foot =====							
NHPP0702-383		I-70 EB AUX FRISCO TO SILVERT	01/13/22	52.00	1200.00	1328.51	1450.00
NHPP 0761-238		I-76 DAHLIA TO YORK	03/10/22	36.00	880.00	787.18	600.00
C0761-239							
M R100-351		FY22 R1 SIGN STRUCTURE REPLAC	03/17/22	69.00	1750.00	1506.00	1540.00
		WEIGHTED AVERAGE FOR THE FIRST QUARTER		157.00	1368.34	1136.95	1294.65
STM1151-038		SH115 MP 27 TO MP 38	04/21/22	31.00	725.00	879.46	800.00
2670703-479		I-70 BRIDGE OVER HARLAN	05/05/22	66.00	700.00	669.63	792.05
CM760-047		COLFAX AND QUAIL	05/12/22	42.00	555.00	673.80	604.00
ITS 0741-024		VMS SIGN INSTALLATIONS AND VS	06/02/22	32.00	750.00	2139.00	850.00
MTCE0253-291		I-25 SIGN REPLACEMENT PHASE 2	06/16/22	300.00	700.00	914.38	728.76
		WEIGHTED AVERAGE FOR THE SECOND QUARTER		471.00	692.11	862.11	739.43
NHPP0702-414		VAIL PASS AUX PHASE 1 CAP 3	07/08/22	188.00	1012.24	1012.24	1012.24

COLORADO DEPARTMENT OF TRANSPORTATION
ITEM UNIT COSTS BY PROJECTS -- 2022 COST DATA

11:31 Wednesday, March 8, 2023 260

PROJECT NUMBER	ITEM NUMBER/ PROJECT LOCATION	ITEM DESCRIPTION/ PROJECT LOCATION	DATE LET	UNIT/ QUANTITY	ENGR. EST.	AVERAGE BID	AWARDED BID
===== 503-00048 Drilled Shaft (48 In) Lin Foot =====							
FBR0702-423		VAIL PASS AUX BE F-12-AT PHAS					
NHPP0063-054		US 6 FROM I70-B TO 33 RD. (MP	08/18/22	21.00	1000.00	1052.23	910.00
C1211-099		SH 121 NORTH SGA SIGNALS	08/25/22	210.00	800.00	840.00	760.00
SHE2873-193		US 287 & CO 52 INTERSECTION I	09/15/22	84.00	750.00	649.69	124.00
		WEIGHTED AVERAGE FOR THE THIRD QUARTER		503.00	879.33	792.67	754.33
STU0252-457		I-25:ALAMEDA RIVER PH 2.0	11/03/22	477.00	700.00	868.33	1010.00
STRC090-011		US 50B AND SH71/CR18 INTERSEC	11/17/22	21.00	700.00	1100.00	1250.00
STAM420-001		US 285 AT HWY 9C IMPROVEMENTS	12/01/22	127.00	660.00	1016.01	1161.75
BR2854-148		INTERSECTION OF US 285 & SH 9					
STM0091-046		ADA RAMP IMPROVEMENTS - FAIRP					
2670703-487		I-70 BRIDGES OVER WARD ROAD-	12/01/22	337.00	400.00	717.19	480.00
NHPP0063-048		US6 / 20 ROAD INTERSECTION IM	12/15/22	42.00	900.00	1666.09	2090.00
NHPP0931-033		SH93:US6 TO 58TH RESURFACING	12/15/22	36.00	850.00	935.05	836.80
		WEIGHTED AVERAGE FOR THE FOURTH QUARTER		1,040.00	611.17	861.72	899.26
		WEIGHTED AVERAGE FOR THE YEAR		2,171.00	745.62	876.87	859.60
===== 503-00054 Drilled Shaft (54 In) Lin Foot =====							
2670703-479		I-70 BRIDGE OVER HARLAN	05/05/22	424.00	900.00	757.82	435.00
		WEIGHTED AVERAGE FOR THE SECOND QUARTER		424.00	900.00	757.82	435.00
C1211-099		SH 121 NORTH SGA SIGNALS	08/25/22	21.00	900.00	1125.00	850.00
		WEIGHTED AVERAGE FOR THE THIRD QUARTER		21.00	900.00	1125.00	850.00
FSAM240-200		SH21B CO SPRINGS SIGNAL REPLA	10/27/22	210.00	650.00	963.75	1005.00
STRC090-011		US 50B AND SH71/CR18 INTERSEC	11/17/22	21.00	640.00	1155.00	1310.00
2670703-487		I-70 BRIDGES OVER WARD ROAD-	12/01/22	106.00	500.00	901.83	940.00
		WEIGHTED AVERAGE FOR THE FOURTH QUARTER		337.00	602.20	946.20	1003.56
		WEIGHTED AVERAGE FOR THE YEAR		782.00	771.66	828.21	691.16

COLORADO DEPARTMENT OF TRANSPORTATION
 ITEM UNIT COSTS BY PROJECTS -- 2022 COST DATA

11:31 Wednesday, March 8, 2023 261

PROJECT NUMBER	ITEM NUMBER/ PROJECT LOCATION	ITEM DESCRIPTION/ PROJECT LOCATION	DATE LET	UNIT/ QUANTITY	ENGR. EST.	AVERAGE BID	AWARDED BID
=====	503-00060	Drilled Shaft (60 In)		Lin Foot	=====		
M R100-351		FY22 R1 SIGN STRUCTURE REPLAC	03/17/22	33.00	2100.00	2030.00	1984.00
		WEIGHTED AVERAGE FOR THE FIRST QUARTER		33.00	2100.00	2030.00	1984.00
		WEIGHTED AVERAGE FOR THE YEAR		33.00	2100.00	2030.00	1984.00
=====	503-00072	Drilled Shaft (72 In)		Lin Foot	=====		
IM025A-050		I25-MP103.9 - INTERSECTION DR	12/01/22	122.00	1000.00	1775.00	1600.00
		WEIGHTED AVERAGE FOR THE FOURTH QUARTER		122.00	1000.00	1907.87	2247.74
		WEIGHTED AVERAGE FOR THE YEAR		122.00	1000.00	1907.87	2247.74
=====	503-00310	CSL Testing		Each	=====		
NHPP 0761-238 C0761-239		I-76 DAHLIA TO YORK	03/10/22	7.00	2800.00	3559.35	2500.00
		WEIGHTED AVERAGE FOR THE FIRST QUARTER		7.00	2800.00	3559.35	2500.00
NHPP0702-413 2670703-479		VAIL PASS AUX PHASE 1 CAP 2	04/18/22	8.00	1163.63	1163.63	1163.63
		I-70 BRIDGE OVER HARLAN	05/05/22	9.00	3000.00	1745.93	3470.61
		WEIGHTED AVERAGE FOR THE SECOND QUARTER		17.00	2135.83	1670.79	2384.97
NHPP0702-414 FBR0702-423		VAIL PASS AUX PHASE 1 CAP 3	07/08/22	12.00	6805.76	6805.76	6805.76
		VAIL PASS AUX BE F-12-AT PHAS					
		WEIGHTED AVERAGE FOR THE THIRD QUARTER		12.00	6805.76	6805.76	6805.76
STU0252-457 STAM420-001		I-25:ALAMEDA RIVER PH 2.0	11/03/22	62.00	4000.00	2109.70	4100.00
		US 285 AT HWY 9C IMPROVEMENTS	12/01/22	24.00	1100.00	2664.88	885.86

COLORADO DEPARTMENT OF TRANSPORTATION
 ITEM UNIT COSTS BY PROJECTS -- 2022 COST DATA

11:31 Wednesday, March 8, 2023 262

PROJECT NUMBER	ITEM NUMBER/ PROJECT LOCATION	ITEM DESCRIPTION/ PROJECT LOCATION	DATE LET	UNIT/ QUANTITY	ENGR. EST.	AVERAGE BID	AWARDED BID
=====	503-00310	CSL Testing		Each	=====	=====	=====
BR2854-148		INTERSECTION OF US 285 & SH 9					
STM0091-046		ADA RAMP IMPROVEMENTS - FAIRP					
2670703-487		I-70 BRIDGES OVER WARD ROAD-	12/01/22	9.00	4500.00	2673.00	2960.00
IM025A-050		I25-MP103.9 - INTERSECTION DR	12/01/22	6.00	4500.00	2300.00	3600.00
		WEIGHTED AVERAGE FOR THE FOURTH QUARTER		101.00	3385.15	2347.58	3204.96
		WEIGHTED AVERAGE FOR THE YEAR		137.00	3499.84	2514.73	3382.59
=====	503-01080	M Pile (8 In)		Lin Foot	=====	=====	=====
NHPP0701-231		I-70 SALT WASH BRIDGES SCOUR	09/29/22	4,512.00	400.00	228.11	252.60
		WEIGHTED AVERAGE FOR THE THIRD QUARTER		4,512.00	400.00	228.11	252.60
		WEIGHTED AVERAGE FOR THE YEAR		4,512.00	400.00	228.11	252.60
=====	503-01100	M Pile (10 In)		Lin Foot	=====	=====	=====
NHPP0702-383		I-70 EB AUX FRISCO TO SILVERT	01/13/22	2,090.00	167.00	261.78	270.00
		WEIGHTED AVERAGE FOR THE FIRST QUARTER		2,090.00	167.00	261.78	270.00
ER0702-420		PR I-70 GWC MATERIAL FLOWS 20	05/06/22	726.00	150.00	340.00	280.00
		WEIGHTED AVERAGE FOR THE SECOND QUARTER		726.00	150.00	340.00	280.00
NHPPR100-266		R1 ESSENTIAL REPAIRS	09/01/22	1,304.00	300.00	655.07	640.32
		WEIGHTED AVERAGE FOR THE THIRD QUARTER		1,304.00	300.00	655.07	640.32
		WEIGHTED AVERAGE FOR THE YEAR		4,120.00	206.10	366.25	388.97
=====	503-02000	Verification Test Pile		Each	=====	=====	=====
NHPP0702-383		I-70 EB AUX FRISCO TO SILVERT	01/13/22	6.00	22000.00	29607.63	21500.00
		WEIGHTED AVERAGE FOR THE FIRST QUARTER		6.00	22000.00	29607.63	21500.00

COLORADO DEPARTMENT OF TRANSPORTATION
ITEM UNIT COSTS BY PROJECTS -- 2022 COST DATA

11:31 Wednesday, March 8, 2023 263

PROJECT NUMBER	ITEM NUMBER/ PROJECT LOCATION	ITEM DESCRIPTION/ PROJECT LOCATION	DATE LET	UNIT/ QUANTITY	ENGR. EST.	AVERAGE BID	AWARDED BID
=====	503-02000	Verification Test Pile		Each	=====	=====	=====
NHPPR100-266		R1 ESSENTIAL REPAIRS	09/01/22	3.00	4000.00	31002.26	4506.77
NHPP0701-231		I-70 SALT WASH BRIDGES SCOUR	09/29/22	2.00	50000.00	17243.91	28000.00
		WEIGHTED AVERAGE FOR THE THIRD QUARTER		5.00	22400.00	26768.92	13904.06
		WEIGHTED AVERAGE FOR THE YEAR		11.00	22181.82	28749.42	18047.30
=====	504-04420	Precast Panel Facing		Sq Foot	=====	=====	=====
NHPP0702-413		VAIL PASS AUX PHASE 1 CAP 2	04/18/22	13,344.00	61.85	61.85	61.85
2670703-479		I-70 BRIDGE OVER HARLAN	05/05/22	22,490.00	50.00	54.24	52.00
		WEIGHTED AVERAGE FOR THE SECOND QUARTER		35,834.00	54.41	54.92	55.67
NHPP0702-414		VAIL PASS AUX PHASE 1 CAP 3	07/08/22	5,167.00	71.12	71.12	71.12
FBR0702-423		VAIL PASS AUX BE F-12-AT PHAS					
		WEIGHTED AVERAGE FOR THE THIRD QUARTER		5,167.00	71.12	71.12	71.12
STAM420-001		US 285 AT HWY 9C IMPROVEMENTS	12/01/22	7,787.00	56.00	50.86	44.24
BR2854-148		INTERSECTION OF US 285 & SH 9					
STM0091-046		ADA RAMP IMPROVEMENTS - FAIRP					
2670703-487		I-70 BRIDGES OVER WARD ROAD-	12/01/22	10,901.00	50.00	54.13	38.00
IM025A-050		I25-MP103.9 - INTERSECTION DR	12/01/22	2,825.00	45.00	88.00	79.00
		WEIGHTED AVERAGE FOR THE FOURTH QUARTER		21,513.00	51.52	56.10	45.64
		WEIGHTED AVERAGE FOR THE YEAR		62,514.00	54.80	55.71	53.50
=====	504-05000	Wire Mesh Facing		Sq Foot	=====	=====	=====
NHPP0702-413		VAIL PASS AUX PHASE 1 CAP 2	04/18/22	213.00	63.44	63.44	63.44
		WEIGHTED AVERAGE FOR THE SECOND QUARTER		213.00	63.44	63.44	63.44

COLORADO DEPARTMENT OF TRANSPORTATION
 ITEM UNIT COSTS BY PROJECTS -- 2022 COST DATA

11:31 Wednesday, March 8, 2023 264

PROJECT NUMBER	ITEM NUMBER/ PROJECT LOCATION	ITEM DESCRIPTION/ PROJECT LOCATION	DATE LET	UNIT/ QUANTITY	ENGR. EST.	AVERAGE BID	AWARDED BID
=====	504-05000	Wire Mesh Facing		Sq Foot	=====		
NHPP0702-414		VAIL PASS AUX PHASE 1 CAP 3	07/08/22	4,354.00	29.36	29.36	29.36
FBR0702-423		VAIL PASS AUX BE F-12-AT PHAS					
		WEIGHTED AVERAGE FOR THE THIRD QUARTER		4,354.00	29.36	29.36	29.36
STAM420-001		US 285 AT HWY 9C IMPROVEMENTS	12/01/22	7,787.00	12.00	28.51	35.05
BR2854-148		INTERSECTION OF US 285 & SH 9					
STM0091-046		ADA RAMP IMPROVEMENTS - FAIRP					
		WEIGHTED AVERAGE FOR THE FOURTH QUARTER		7,787.00	12.00	28.51	35.05
		WEIGHTED AVERAGE FOR THE YEAR		12,354.00	19.01	28.82	33.53
=====	504-06300	Ground Nail		Lin Foot	=====		
ER0702-420		PR I-70 GWC MATERIAL FLOWS 20	05/06/22	210.00	75.00	548.50	532.00
		WEIGHTED AVERAGE FOR THE SECOND QUARTER		210.00	75.00	548.50	532.00
		WEIGHTED AVERAGE FOR THE YEAR		210.00	75.00	548.50	532.00
=====	504-06406	Soil Nail		Lin Foot	=====		
NHPP0702-413		VAIL PASS AUX PHASE 1 CAP 2	04/18/22	16,159.00	74.10	74.10	74.10
NHC540-017		R2 CHAINUP STA @ KENOSHA/HOOS	05/12/22	2,008.00	65.00	89.33	83.00
		WEIGHTED AVERAGE FOR THE SECOND QUARTER		18,167.00	73.09	78.24	75.08
NHPP0702-414		VAIL PASS AUX PHASE 1 CAP 3	07/08/22	57,565.00	45.56	45.56	45.56
FBR0702-423		VAIL PASS AUX BE F-12-AT PHAS					
2670403-065		US40_FLOYD HILL ROUNDABOUTS	09/15/22	7,337.00	70.00	83.92	54.00
		WEIGHTED AVERAGE FOR THE THIRD QUARTER		64,902.00	48.32	56.17	46.51
		WEIGHTED AVERAGE FOR THE YEAR		83,069.00	53.74	60.98	52.76

PROJECT NUMBER	ITEM NUMBER/ PROJECT LOCATION	ITEM DESCRIPTION/ PROJECT LOCATION	DATE LET	UNIT/ QUANTITY	ENGR. EST.	AVERAGE BID	AWARDED BID
=====	504-06410	Verification Testing		Each	=====		
NHPP0702-413		VAIL PASS AUX PHASE 1 CAP 2	04/18/22	6.00	4815.00	4815.00	4815.00
NHC540-017		R2 CHAINUP STA @ KENOSHA/HOOS	05/12/22	6.00	535.00	3733.33	3200.00
		WEIGHTED AVERAGE FOR THE SECOND QUARTER		12.00	2675.00	4003.75	4007.50
NHPP0702-414		VAIL PASS AUX PHASE 1 CAP 3	07/08/22	16.00	3782.45	3782.45	3782.45
FBR0702-423		VAIL PASS AUX BE F-12-AT PHAS					
2670403-065		US40_FLOYD HILL ROUNDABOUTS	09/15/22	4.00	2000.00	3420.33	2136.00
		WEIGHTED AVERAGE FOR THE THIRD QUARTER		20.00	3425.96	3627.26	3453.16
		WEIGHTED AVERAGE FOR THE YEAR		32.00	3144.35	3801.02	3661.04
=====	506-00012	Riprap (Special)		Each	=====		
ER0502-092		US 50 MP 204 EB MONARCH TRUCK	08/29/22	2.00	500.00	1765.30	1170.89
		WEIGHTED AVERAGE FOR THE THIRD QUARTER		2.00	500.00	1765.30	1170.89
		WEIGHTED AVERAGE FOR THE YEAR		2.00	500.00	1765.30	1170.89
=====	506-00020	Place Riprap		Cubic Yard	=====		
ER0502-092		US 50 MP 204 EB MONARCH TRUCK	08/29/22	37.00	250.00	111.69	80.08
		WEIGHTED AVERAGE FOR THE THIRD QUARTER		37.00	250.00	111.69	80.08
		WEIGHTED AVERAGE FOR THE YEAR		37.00	250.00	111.69	80.08
=====	506-00030	Grouted Riprap		Cubic Yard	=====		
ER0502-092		US 50 MP 204 EB MONARCH TRUCK	08/29/22	47.00	500.00	402.08	543.74
		WEIGHTED AVERAGE FOR THE THIRD QUARTER		47.00	500.00	402.08	543.74
IM025A-050		I25-MP103.9 - INTERSECTION DR	12/01/22	67.00	700.00	310.00	230.00
		WEIGHTED AVERAGE FOR THE FOURTH QUARTER		67.00	700.00	310.00	230.00
		WEIGHTED AVERAGE FOR THE YEAR		114.00	617.54	347.96	359.35

COLORADO DEPARTMENT OF TRANSPORTATION
 ITEM UNIT COSTS BY PROJECTS -- 2022 COST DATA

11:31 Wednesday, March 8, 2023 266

PROJECT NUMBER	ITEM NUMBER/ PROJECT LOCATION	ITEM DESCRIPTION/ PROJECT LOCATION	DATE LET	UNIT/ QUANTITY	ENGR. EST.	AVERAGE BID	AWARDED BID
=====	506-00035	Grouted Riprap		Sq Yard	=====		
STAM420-001 BR2854-148 STM0091-046		US 285 AT HWY 9C IMPROVEMENTS INTERSECTION OF US 285 & SH 9 ADA RAMP IMPROVEMENTS - FAIRP	12/01/22	56.00	80.00	283.20	395.93
	WEIGHTED AVERAGE FOR THE FOURTH QUARTER			56.00	80.00	283.20	395.93
	WEIGHTED AVERAGE FOR THE YEAR			56.00	80.00	283.20	395.93
=====	506-00050	Slope Mattress		Cubic Yard	=====		
NHPP0702-383		I-70 EB AUX FRISCO TO SILVERT	01/13/22	388.00	100.00	315.78	250.00
	WEIGHTED AVERAGE FOR THE FIRST QUARTER			388.00	100.00	315.78	250.00
	WEIGHTED AVERAGE FOR THE YEAR			388.00	100.00	315.78	250.00
=====	506-00100	Riprap (Gabions)		Cubic Yard	=====		
ER0702-420		PR I-70 GWC MATERIAL FLOWS 20	05/06/22	2,087.00	350.00	312.50	170.00
	WEIGHTED AVERAGE FOR THE SECOND QUARTER			2,087.00	350.00	312.50	170.00
	WEIGHTED AVERAGE FOR THE YEAR			2,087.00	350.00	312.50	170.00
=====	506-00206	Riprap (6 In)		Cubic Yard	=====		
NH0504-910		US50B L-24-B MIN REP AT MP 40	01/13/22	51.00	150.00	194.97	93.75
	WEIGHTED AVERAGE FOR THE FIRST QUARTER			51.00	150.00	194.97	93.75
NH0504-911 NHPP0702-413 STA0712-019		VAIL PASS AUX PHASE 1 CAP 2 SH 71: Frieight Improvements	04/07/22 04/18/22 05/12/22	307.00 41.00 4.00	150.00 92.32 300.00	125.50 92.32 489.86	131.00 92.32 489.86
	WEIGHTED AVERAGE FOR THE SECOND QUARTER			352.00	144.99	125.65	130.57
NHPP0702-414		VAIL PASS AUX PHASE 1 CAP 3	07/08/22	50.00	94.96	94.96	94.96

COLORADO DEPARTMENT OF TRANSPORTATION
 ITEM UNIT COSTS BY PROJECTS -- 2022 COST DATA

11:31 Wednesday, March 8, 2023 267

PROJECT NUMBER	ITEM NUMBER/ PROJECT LOCATION	ITEM DESCRIPTION/ PROJECT LOCATION	DATE LET	UNIT/ QUANTITY	ENGR. EST.	AVERAGE BID	AWARDED BID
===== 506-00206 Riprap (6 In) Cubic Yard =====							
FBR0702-423		VAIL PASS AUX BE F-12-AT PHAS					
FSA052A-057		SH52 BOX CULVERT EXTENSION (M	08/04/22	17.00	300.00	352.09	325.31
2670703-497		I-70_GENESEE WILDLIFE KING	09/15/22	28.00	170.00	198.05	110.18
		WEIGHTED AVERAGE FOR THE THIRD QUARTER		95.00	153.77	207.15	140.67

NHPP0343-048		US 34 (MP 169.3-171.4)	11/01/22	325.00	150.00	180.07	125.00
		WEIGHTED AVERAGE FOR THE FOURTH QUARTER		325.00	150.00	180.07	125.00
		WEIGHTED AVERAGE FOR THE YEAR		823.00	148.29	171.91	127.26
===== 506-00209 Riprap (9 In) Cubic Yard =====							
NHPP0702-383		I-70 EB AUX FRISCO TO SILVERT	01/13/22	164.00	160.00	192.88	150.00
		WEIGHTED AVERAGE FOR THE FIRST QUARTER		164.00	160.00	192.88	150.00

NHPP0702-413		VAIL PASS AUX PHASE 1 CAP 2	04/18/22	71.00	92.32	92.32	92.32
2670703-479		I-70 BRIDGE OVER HARLAN	05/05/22	12.00	150.00	240.49	154.41
FSA052A-046		SH52 WCR 37 INTERSECTION IMPR	06/09/22	100.90	215.00	175.30	124.00
		WEIGHTED AVERAGE FOR THE SECOND QUARTER		183.90	163.39	173.45	113.75

NHPP0702-414		VAIL PASS AUX PHASE 1 CAP 3	07/08/22	66.00	94.96	94.96	94.96
FBR0702-423		VAIL PASS AUX BE F-12-AT PHAS					
STR0711-022		SH 71 OVER THE ARKANSAS	08/04/22	106.00	90.00	266.67	200.00
NHPP0063-054		US 6 FROM I70-B TO 33 RD. (MP	08/18/22	42.00	200.00	399.39	345.00
C1211-099		SH 121 NORTH SGA SIGNALS	08/25/22	2.00	140.00	500.00	500.00
2670403-065		US40_FLOYD HILL ROUNDABOUTS	09/15/22	32.00	160.00	149.50	139.00
SHE2873-193		US 287 & CO 52 INTERSECTION I	09/15/22	29.00	150.00	200.65	201.00
		WEIGHTED AVERAGE FOR THE THIRD QUARTER		277.00	122.59	237.04	192.18

NHPP0705-088		I-70 AGATE STRUCTURE REHAB	10/27/22	18.00	190.00	396.49	505.00

COLORADO DEPARTMENT OF TRANSPORTATION
 ITEM UNIT COSTS BY PROJECTS -- 2022 COST DATA

11:31 Wednesday, March 8, 2023 268

PROJECT NUMBER	ITEM NUMBER/ PROJECT LOCATION	ITEM DESCRIPTION/ PROJECT LOCATION	DATE LET	UNIT/ QUANTITY	ENGR. EST.	AVERAGE BID	AWARDED BID
===== 506-00209 Riprap (9 In) Cubic Yard =====							
STA3852-015	US 385 HOLYOKE NORTH		10/27/22	74.00	175.00	210.00	210.00
C5502-097	US550 MP 117.28-126.06		11/17/22	51.00	200.00	291.60	325.00
2670703-487	I-70 BRIDGES OVER WARD ROAD-		12/01/22	19.00	300.00	180.20	170.00
IM025A-050	I25-MP103.9 - INTERSECTION DR		12/01/22	33.00	150.00	235.00	180.00
NHPP0063-048	US6 / 20 ROAD INTERSECTION IM		12/15/22	6.00	500.00	616.33	680.00
STR0092-024	SH 9 North of Silverthorne		12/22/22	66.00	400.00	593.50	687.00
WEIGHTED AVERAGE FOR THE FOURTH QUARTER				267.00	249.51	340.77	366.08
WEIGHTED AVERAGE FOR THE YEAR				891.90	175.88	236.11	223.15
===== 506-00212 Riprap (12 In) Cubic Yard =====							
NHPP0702-383	I-70 EB AUX FRISCO TO SILVERT		01/13/22	185.00	200.00	149.27	124.00
NHPP1601-083			02/03/22	123.00	250.00	244.80	240.00
C0762-055			02/17/22	12.00	200.00	196.04	200.00
BRC040-057			03/17/22	146.00	200.00	494.75	665.00
WEIGHTED AVERAGE FOR THE FIRST QUARTER				466.00	213.20	275.45	326.07
NHPP0702-413	VAIL PASS AUX PHASE 1 CAP 2		04/18/22	32.00	92.32	92.32	92.32
STM1151-038	SH115 MP 27 TO MP 38		04/21/22	448.50	160.00	154.49	89.20
STA0712-019	SH 71: Frieight Improvements		05/12/22	120.00	300.00	236.49	236.49
WEIGHTED AVERAGE FOR THE SECOND QUARTER				600.50	184.37	157.77	118.80
NHPP0702-414	VAIL PASS AUX PHASE 1 CAP 3		07/08/22	16.00	94.96	94.96	94.96
FBR0702-423	VAIL PASS AUX BE F-12-AT PHAS						
STR0711-022	SH 71 OVER THE ARKANSAS		08/04/22	245.00	135.00	307.67	200.00
NHPP0063-054	US 6 FROM I70-B TO 33 RD. (MP		08/18/22	994.00	160.00	284.22	245.00
BR0343-046	US 34 TIMBER BRIDGE REPL. PKG		08/31/22	12.00	265.24	233.46	233.46
FBR0343-047	US 6/US 34 TIMBER BRIDGE REPL						
NHPP0701-231	I-70 SALT WASH BRIDGES SCOUR		09/29/22	574.00	300.00	225.95	278.00
WEIGHTED AVERAGE FOR THE THIRD QUARTER				1,841.00	200.44	270.55	247.92
TRG0253-264	I-25 AND SH 119 PARK-N-RIDE		10/27/22	57.00	130.00	184.95	150.00

COLORADO DEPARTMENT OF TRANSPORTATION
ITEM UNIT COSTS BY PROJECTS -- 2022 COST DATA

11:31 Wednesday, March 8, 2023 269

PROJECT NUMBER	ITEM NUMBER/ PROJECT LOCATION	ITEM DESCRIPTION/ PROJECT LOCATION	DATE LET	UNIT/ QUANTITY	ENGR. EST.	AVERAGE BID	AWARDED BID
=====	506-00212	Riprap (12 In)		Cubic Yard	=====	=====	=====
STAM420-001		US 285 AT HWY 9C IMPROVEMENTS	12/01/22	26.00	120.00	156.86	189.16
BR2854-148		INTERSECTION OF US 285 & SH 9					
STM0091-046		ADA RAMP IMPROVEMENTS - FAIRP					
STA0711-021		SH71: REGION LINE NORTH	12/01/22	23.00	100.00	263.33	260.00
IM025A-050		I25-MP103.9 - INTERSECTION DR	12/01/22	26.00	150.00	313.33	190.00
		WEIGHTED AVERAGE FOR THE FOURTH QUARTER		132.00	126.74	202.63	184.76
		WEIGHTED AVERAGE FOR THE YEAR		3,039.50	196.02	235.42	231.65
=====	506-00218	Riprap (18 In)		Cubic Yard	=====	=====	=====
NHPP1601-083			02/03/22	143.00	260.00	242.45	250.00
		WEIGHTED AVERAGE FOR THE FIRST QUARTER		143.00	260.00	242.45	250.00
ER0502-092		US 50 MP 204 EB MONARCH TRUCK	08/29/22	46.00	350.00	218.31	269.66
		WEIGHTED AVERAGE FOR THE THIRD QUARTER		46.00	350.00	218.31	269.66
STU0252-457		I-25:ALAMEDA RIVER PH 2.0	11/03/22	2,115.00	150.00	137.09	134.00
C5502-097		US550 MP 117.28-126.06	11/17/22	70.00	300.00	255.10	249.00
STAM420-001		US 285 AT HWY 9C IMPROVEMENTS	12/01/22	3,067.00	85.00	94.86	130.00
BR2854-148		INTERSECTION OF US 285 & SH 9					
STM0091-046		ADA RAMP IMPROVEMENTS - FAIRP					
STA0711-021		SH71: REGION LINE NORTH	12/01/22	39.00	120.00	266.67	270.00
IM025A-050		I25-MP103.9 - INTERSECTION DR	12/01/22	576.00	225.00	111.00	73.00
BR012A-048		CO 12 STRUCTURE P-17-F AT MP	12/22/22	610.00	155.00	183.05	140.00
		WEIGHTED AVERAGE FOR THE FOURTH QUARTER		6,477.00	127.80	115.74	129.31
		WEIGHTED AVERAGE FOR THE YEAR		6,666.00	132.17	118.00	132.87
=====	506-00224	Riprap (24 In)		Cubic Yard	=====	=====	=====
ER0502-092		US 50 MP 204 EB MONARCH TRUCK	08/29/22	151.00	200.00	243.81	332.55
		WEIGHTED AVERAGE FOR THE THIRD QUARTER		151.00	200.00	243.81	332.55
		WEIGHTED AVERAGE FOR THE YEAR		151.00	200.00	243.81	332.55

COLORADO DEPARTMENT OF TRANSPORTATION
ITEM UNIT COSTS BY PROJECTS -- 2022 COST DATA

11:31 Wednesday, March 8, 2023 270

PROJECT NUMBER	ITEM NUMBER/ PROJECT LOCATION	ITEM DESCRIPTION/ PROJECT LOCATION	DATE LET	UNIT/ QUANTITY	ENGR. EST.	AVERAGE BID	AWARDED BID
===== 506-00409 Soil Riprap (9 In) Cubic Yard =====							
NHPP 0761-238 C0761-239	I-76 DAHLIA TO YORK		03/10/22	19.00	160.00	185.02	160.00
	WEIGHTED AVERAGE FOR THE FIRST QUARTER			19.00	160.00	185.02	160.00
	WEIGHTED AVERAGE FOR THE YEAR			19.00	160.00	212.15	244.33
===== 506-00412 Soil Riprap (12 In) Cubic Yard =====							
FBR0761-236 NHPP0701-231	I-76 OVER CLR CRK SCOUR MIT		08/25/22	36.00	150.00	172.67	120.00
	I-70 SALT WASH BRIDGES SCOUR		09/29/22	47.00	300.00	401.29	235.00
	WEIGHTED AVERAGE FOR THE THIRD QUARTER			83.00	234.94	279.05	185.12
TRG0253-264	I-25 AND SH 119 PARK-N-RIDE		10/27/22	106.00	110.00	157.10	111.00
	WEIGHTED AVERAGE FOR THE FOURTH QUARTER			106.00	110.00	157.10	111.00
	WEIGHTED AVERAGE FOR THE YEAR			189.00	164.87	180.56	143.55
===== 506-00418 Soil Riprap (18 In) Cubic Yard =====							
TRG0253-264 STU0252-457	I-25 AND SH 119 PARK-N-RIDE		10/27/22	146.00	150.00	159.76	110.00
	I-25:ALAMEDA RIVER PH 2.0		11/03/22	445.00	125.00	134.42	123.00
	WEIGHTED AVERAGE FOR THE FOURTH QUARTER			591.00	131.18	146.25	119.79
	WEIGHTED AVERAGE FOR THE YEAR			591.00	131.18	146.25	119.79
===== 506-00606 In-Channel Boulder Grouted (24 In) Cubic Yard =====							
FBR0761-236	I-76 OVER CLR CRK SCOUR MIT		08/25/22	1,243.00	400.00	625.67	478.00
	WEIGHTED AVERAGE FOR THE THIRD QUARTER			1,243.00	400.00	625.67	478.00
	WEIGHTED AVERAGE FOR THE YEAR			1,243.00	400.00	625.67	478.00
===== 506-00612 Matrix Riprap (12 In) Cubic Yard =====							
NHPPR100-266	R1 ESSENTIAL REPAIRS		09/01/22	38.00	250.00	517.19	376.58
	WEIGHTED AVERAGE FOR THE THIRD QUARTER			38.00	250.00	517.19	376.58
	WEIGHTED AVERAGE FOR THE YEAR			38.00	250.00	517.19	376.58

COLORADO DEPARTMENT OF TRANSPORTATION
ITEM UNIT COSTS BY PROJECTS -- 2022 COST DATA

11:31 Wednesday, March 8, 2023 271

PROJECT NUMBER	ITEM NUMBER/ PROJECT LOCATION	ITEM DESCRIPTION/ PROJECT LOCATION	DATE LET	UNIT/ QUANTITY	ENGR. EST.	AVERAGE BID	AWARDED BID
===== 506-00700 Void-Filled Riprap Cubic Yard =====							
FBR0761-236		I-76 OVER CLR CRK SCOUR MIT	08/25/22	93.00	200.00	347.00	130.00
		WEIGHTED AVERAGE FOR THE THIRD QUARTER		93.00	200.00	347.00	130.00
===== 506-01020 Geogrid Reinforce Sq Yard =====							
NHPP0502-090		SH 50 MP 134.6-136 GUNNISON C	12/22/22	43.00	200.00	339.19	408.26
		WEIGHTED AVERAGE FOR THE FOURTH QUARTER		43.00	200.00	339.19	408.26
		WEIGHTED AVERAGE FOR THE YEAR		136.00	200.00	343.60	217.98
NHPP0702-383		I-70 EB AUX FRISCO TO SILVERT	01/13/22	223.00	5.00	18.06	8.00
STR092A-031			03/17/22	1,000.00	5.00	3.15	3.15
NHM765-007			03/31/22	16,566.00	5.00	6.70	8.62
		WEIGHTED AVERAGE FOR THE FIRST QUARTER		17,789.00	5.00	6.88	8.30
NHPP0063-054		US 6 FROM I70-B TO 33 RD. (MP	08/18/22	5,556.00	10.00	3.54	3.25
		WEIGHTED AVERAGE FOR THE THIRD QUARTER		5,556.00	10.00	3.54	3.25
STA207A-004		Resurfacing SH207A MANZANOLA	10/27/22	866.00	5.00	6.37	8.60
C5502-097		US550 MP 117.28-126.06	11/17/22	894.00	15.00	3.91	4.60
NHPP0502-090		SH 50 MP 134.6-136 GUNNISON C	12/22/22	100.00	5.00	14.45	4.03
		WEIGHTED AVERAGE FOR THE FOURTH QUARTER		1,860.00	9.81	5.93	6.43
		WEIGHTED AVERAGE FOR THE YEAR		25,205.00	6.46	6.26	7.05
===== 507-00000 Conc S and D Pave Cubic Yard =====							
NHPP0702-383		I-70 EB AUX FRISCO TO SILVERT	01/13/22	25.00	1000.00	1294.40	500.00

COLORADO DEPARTMENT OF TRANSPORTATION
ITEM UNIT COSTS BY PROJECTS -- 2022 COST DATA

11:31 Wednesday, March 8, 2023 272

PROJECT NUMBER	ITEM NUMBER/ PROJECT LOCATION	ITEM DESCRIPTION/ PROJECT LOCATION	DATE LET	UNIT/ QUANTITY	ENGR. EST.	AVERAGE BID	AWARDED BID
=====	507-00000	Conc S and D Pave		Cubic Yard	=====	=====	=====
NHPP 0761-238 C0761-239	I-76 DAHLIA TO YORK	I-76 DAHLIA TO YORK	03/10/22	6.50	1200.00	1126.28	1900.00
	WEIGHTED AVERAGE FOR THE FIRST QUARTER			31.50	1041.27	1245.01	788.89
2670703-479	I-70 BRIDGE OVER HARLAN	I-70 BRIDGE OVER HARLAN	05/05/22	66.00	800.00	832.55	887.71
	WEIGHTED AVERAGE FOR THE SECOND QUARTER			66.00	800.00	832.55	887.71
2670403-065	US40_FLOYD HILL ROUNDABOUTS	US40_FLOYD HILL ROUNDABOUTS	09/15/22	46.00	800.00	1076.76	885.00
	WEIGHTED AVERAGE FOR THE THIRD QUARTER			46.00	800.00	1076.76	885.00
NHPP0701-253 2670703-487 IM025A-050	I-70 EAST OF DEBEQUE I-70 BRIDGES OVER WARD ROAD- I25-MP103.9 - INTERSECTION DR	I-70 EAST OF DEBEQUE I-70 BRIDGES OVER WARD ROAD- I25-MP103.9 - INTERSECTION DR	10/27/22 12/01/22 12/01/22	1.00 36.00 55.00	2000.00 1000.00 750.00	11830.00 1240.88 1250.00	13000.00 690.00 1600.00
	WEIGHTED AVERAGE FOR THE FOURTH QUARTER			92.00	861.41	1456.36	1279.38
	WEIGHTED AVERAGE FOR THE YEAR			235.50	856.26	1300.86	1163.39
=====	507-00100	Conc S and D Pave (Reinf)		Cubic Yard	=====	=====	=====
NHPP 0761-238 C0761-239	I-76 DAHLIA TO YORK	I-76 DAHLIA TO YORK	03/10/22	208.00	800.00	829.17	660.00
	WEIGHTED AVERAGE FOR THE FIRST QUARTER			208.00	800.00	829.17	660.00
NHPP0702-413	VAIL PASS AUX PHASE 1 CAP 2	VAIL PASS AUX PHASE 1 CAP 2	04/18/22	7.00	2274.15	2274.15	2274.15
	WEIGHTED AVERAGE FOR THE SECOND QUARTER			7.00	2274.15	2274.15	2274.15
NHPP0702-414	VAIL PASS AUX PHASE 1 CAP 3	VAIL PASS AUX PHASE 1 CAP 3	07/08/22	1.00	4888.61	4888.61	4888.61

COLORADO DEPARTMENT OF TRANSPORTATION
ITEM UNIT COSTS BY PROJECTS -- 2022 COST DATA

11:31 Wednesday, March 8, 2023 273

PROJECT NUMBER	ITEM NUMBER/ PROJECT LOCATION	ITEM DESCRIPTION/ PROJECT LOCATION	DATE LET	UNIT/ QUANTITY	ENGR. EST.	AVERAGE BID	AWARDED BID
=====	507-00100	Conc S and D Pave (Reinf)		Cubic Yard	=====		
FBR0702-423		VAIL PASS AUX BE F-12-AT PHAS					
NHPP0063-054		US 6 FROM I70-B TO 33 RD. (MP	08/18/22	25.00	500.00	915.34	850.00
	WEIGHTED AVERAGE FOR THE THIRD QUARTER			26.00	668.79	993.25	1005.33
STU0252-457		I-25:ALAMEDA RIVER PH 2.0	11/03/22	101.00	1000.00	1358.29	770.00
	WEIGHTED AVERAGE FOR THE FOURTH QUARTER			101.00	1000.00	1182.59	1005.51
	WEIGHTED AVERAGE FOR THE YEAR			342.00	879.26	947.88	869.84
=====	507-00400	Asphalt S and D Pave (Asph)		Ton	=====		
STM1151-038		SH115 MP 27 TO MP 38	04/21/22	24.50	250.00	231.24	198.40
	WEIGHTED AVERAGE FOR THE SECOND QUARTER			24.50	250.00	231.24	198.40
STR0711-022		SH 71 OVER THE ARKANSAS	08/04/22	46.00	212.00	313.33	325.00
	WEIGHTED AVERAGE FOR THE THIRD QUARTER			46.00	212.00	313.33	325.00
STR096A-050		SH 96 MP 168.99 TO 193.77	12/22/22	1.00	390.00	1308.00	544.00
	WEIGHTED AVERAGE FOR THE FOURTH QUARTER			1.00	390.00	1308.00	544.00
	WEIGHTED AVERAGE FOR THE YEAR			71.50	227.51	286.49	284.68
=====	507-00550	Concrete Lined Ditch		Lin Foot	=====		
NHC540-017		R2 CHAINUP STA @ KENOSHA/HOOS	05/12/22	25.00	869.00	253.33	160.00
	WEIGHTED AVERAGE FOR THE SECOND QUARTER			25.00	869.00	253.33	160.00
IM025A-050		I25-MP103.9 - INTERSECTION DR	12/01/22	81.00	100.00	141.67	150.00
	WEIGHTED AVERAGE FOR THE FOURTH QUARTER			81.00	100.00	141.67	150.00
	WEIGHTED AVERAGE FOR THE YEAR			106.00	281.37	168.00	152.36

COLORADO DEPARTMENT OF TRANSPORTATION
ITEM UNIT COSTS BY PROJECTS -- 2022 COST DATA

11:31 Wednesday, March 8, 2023 274

PROJECT NUMBER	ITEM NUMBER/ PROJECT LOCATION	ITEM DESCRIPTION/ PROJECT LOCATION	DATE LET	UNIT/ QUANTITY	ENGR. EST.	AVERAGE BID	AWARDED BID
===== 508-90000 Paint Existing Structure LUMP SUM =====							
NH0504-911			04/07/22	1.00	45000.00	87500.00	75000.00
	WEIGHTED AVERAGE FOR THE SECOND QUARTER			1.00	45000.00	87500.00	75000.00
	WEIGHTED AVERAGE FOR THE YEAR			1.00	45000.00	87500.00	75000.00
===== 509-00000 Str Steel Pound =====							
NHPP0702-383		I-70 EB AUX FRISCO TO SILVERT	01/13/22	541,937.00	4.25	4.63	4.90
	WEIGHTED AVERAGE FOR THE FIRST QUARTER			541,937.00	4.25	4.63	4.90
NHPP0063-054		US 6 FROM I70-B TO 33 RD. (MP	08/18/22	1,400.00	4.00	2.88	2.50
	WEIGHTED AVERAGE FOR THE THIRD QUARTER			1,400.00	4.00	2.88	2.50
	WEIGHTED AVERAGE FOR THE YEAR			543,337.00	4.25	4.63	4.89
===== 509-00001 Str Steel (Galv) Pound =====							
SHE2873-193		US 287 & CO 52 INTERSECTION I	09/15/22	2,401.00	17.00	12.86	2.41
	WEIGHTED AVERAGE FOR THE THIRD QUARTER			2,401.00	17.00	12.86	2.41
STU0252-457		I-25:ALAMEDA RIVER PH 2.0	11/03/22	14,638.00	15.00	9.00	9.20
STR064A-010		SH 64 AND SH 13 AT MEEKER	11/10/22	530.00	40.00	83.70	85.00
STR0092-024		SH 9 North of Silverthorne	12/22/22	70.00	20.00	180.25	75.50
	WEIGHTED AVERAGE FOR THE FOURTH QUARTER			15,238.00	15.89	11.28	12.14
	WEIGHTED AVERAGE FOR THE YEAR			17,639.00	16.04	11.66	10.82
===== 509-08100 Provide Temporary Support LUMP SUM =====							
2670703-479		I-70 BRIDGE OVER HARLAN	05/05/22	1.00	80000.00	37203.85	17091.22
	WEIGHTED AVERAGE FOR THE SECOND QUARTER			1.00	80000.00	37203.85	17091.22
	WEIGHTED AVERAGE FOR THE YEAR			1.00	80000.00	37203.85	17091.22

COLORADO DEPARTMENT OF TRANSPORTATION
ITEM UNIT COSTS BY PROJECTS -- 2022 COST DATA

11:31 Wednesday, March 8, 2023 275

PROJECT NUMBER	ITEM NUMBER/ PROJECT LOCATION	ITEM DESCRIPTION/ PROJECT LOCATION	DATE LET	UNIT/ QUANTITY	ENGR. EST.	AVERAGE BID	AWARDED BID
===== 509-50000 Cor Steel Br Plank Sq Foot =====							
STAR100-358		3 STRUCTURES IN REGION 1	05/26/22	33,359.00	54.00	36.04	32.00
		WEIGHTED AVERAGE FOR THE SECOND QUARTER		33,359.00	54.00	36.04	32.00
STAR100-374		5 STRUCTURES IN REGION 1	09/01/22	38,835.00	38.00	49.13	49.13
		WEIGHTED AVERAGE FOR THE THIRD QUARTER		38,835.00	38.00	49.13	49.13
		WEIGHTED AVERAGE FOR THE YEAR		72,194.00	45.39	39.70	41.21
===== 509-90001 Paint Existing Structure Each =====							
NH0504-911			04/07/22	32.00	1000.00	4250.00	2500.00
		WEIGHTED AVERAGE FOR THE SECOND QUARTER		32.00	1000.00	4250.00	2500.00
		WEIGHTED AVERAGE FOR THE YEAR		32.00	1000.00	4250.00	2500.00
===== 512-00101 Bearing Device (Type I) Each =====							
NHPP0702-383		I-70 EB AUX FRISCO TO SILVERT	01/13/22	4.00	5000.00	5057.94	6100.00
		WEIGHTED AVERAGE FOR THE FIRST QUARTER		4.00	5000.00	5057.94	6100.00
STU0252-457		I-25:ALAMEDA RIVER PH 2.0	11/03/22	24.00	3000.00	2355.33	4300.00
		WEIGHTED AVERAGE FOR THE FOURTH QUARTER		24.00	3000.00	2355.33	4300.00
		WEIGHTED AVERAGE FOR THE YEAR		28.00	3285.71	2942.85	4557.14
===== 512-00102 Bearing Device (Type II) Each =====							
NHPP0702-383		I-70 EB AUX FRISCO TO SILVERT	01/13/22	16.00	2100.00	7095.67	7900.00
		WEIGHTED AVERAGE FOR THE FIRST QUARTER		16.00	2100.00	7095.67	7900.00
		WEIGHTED AVERAGE FOR THE YEAR		16.00	2100.00	7095.67	7900.00

COLORADO DEPARTMENT OF TRANSPORTATION
ITEM UNIT COSTS BY PROJECTS -- 2022 COST DATA

11:31 Wednesday, March 8, 2023 276

PROJECT NUMBER	ITEM NUMBER/ PROJECT LOCATION	ITEM DESCRIPTION/ PROJECT LOCATION	DATE LET	UNIT/ QUANTITY	ENGR. EST.	AVERAGE BID	AWARDED BID
=====	512-00103	Bearing Device (Type III)		Each	=====	=====	=====
NHPP0702-414 FBR0702-423		VAIL PASS AUX PHASE 1 CAP 3 VAIL PASS AUX BE F-12-AT PHAS	07/08/22	6.00	14314.30	14314.30	14314.30
	WEIGHTED AVERAGE FOR THE THIRD QUARTER			6.00	14314.30	14314.30	14314.30
	WEIGHTED AVERAGE FOR THE YEAR			6.00	14314.30	14314.30	14314.30
=====	512-00120	Bearing Repair Corbel		Each	=====	=====	=====
STR109A-019		M-22-AY BRIDGE REHAB ON SH109	12/01/22	4.00	20000.00	20883.37	16940.74
	WEIGHTED AVERAGE FOR THE FOURTH QUARTER			4.00	20000.00	20883.37	16940.74
	WEIGHTED AVERAGE FOR THE YEAR			4.00	20000.00	20883.37	16940.74
=====	513-00600	Bridge Drain		Each	=====	=====	=====
2670703-479		I-70 BRIDGE OVER HARLAN	05/05/22	1.00	5000.00	13666.78	10637.83
	WEIGHTED AVERAGE FOR THE SECOND QUARTER			1.00	5000.00	13666.78	10637.83
	WEIGHTED AVERAGE FOR THE YEAR			1.00	5000.00	13666.78	10637.83
=====	513-00690	Bridge Drain (Spec)		Each	=====	=====	=====
NHPP0702-414 FBR0702-423		VAIL PASS AUX PHASE 1 CAP 3 VAIL PASS AUX BE F-12-AT PHAS	07/08/22	1.00	16644.64	16644.64	16644.64
	WEIGHTED AVERAGE FOR THE THIRD QUARTER			1.00	16644.64	16644.64	16644.64
IM025A-050		I25-MP103.9 - INTERSECTION DR	12/01/22	4.00	5000.00	6033.33	6000.00
	WEIGHTED AVERAGE FOR THE FOURTH QUARTER			4.00	5000.00	6033.33	6000.00
	WEIGHTED AVERAGE FOR THE YEAR			5.00	7328.93	6849.59	8128.93
=====	513-00691	Inst Bridge Drain (Spec)		Each	=====	=====	=====
NHPP0705-088		I-70 AGATE STRUCTURE REHAB	10/27/22	3.00	150.00	1133.01	1500.00
	WEIGHTED AVERAGE FOR THE FOURTH QUARTER			3.00	150.00	1133.01	1500.00
	WEIGHTED AVERAGE FOR THE YEAR			3.00	150.00	1133.01	1500.00

COLORADO DEPARTMENT OF TRANSPORTATION
ITEM UNIT COSTS BY PROJECTS -- 2022 COST DATA

11:31 Wednesday, March 8, 2023 277

PROJECT NUMBER	ITEM NUMBER/ PROJECT LOCATION	ITEM DESCRIPTION/ PROJECT LOCATION	DATE LET	UNIT/ QUANTITY	ENGR. EST.	AVERAGE BID	AWARDED BID
===== 514-00000 Pipe Railing Lin Foot =====							
NHPP0702-383		I-70 EB AUX FRISCO TO SILVERT	01/13/22	676.00	50.00	246.72	210.00
		WEIGHTED AVERAGE FOR THE FIRST QUARTER		676.00	50.00	246.72	210.00
C5502-097		US550 MP 117.28-126.06	11/17/22	46.00	400.00	390.06	384.00
STAM420-001		US 285 AT HWY 9C IMPROVEMENTS	12/01/22	249.00	230.00	327.72	428.38
BR2854-148		INTERSECTION OF US 285 & SH 9					
STM0091-046		ADA RAMP IMPROVEMENTS - FAIRP					
		WEIGHTED AVERAGE FOR THE FOURTH QUARTER		295.00	256.51	335.30	421.46
		WEIGHTED AVERAGE FOR THE YEAR		971.00	112.74	268.98	274.24
===== 514-00048 Ped Railing (48 In) Lin Foot =====							
C1211-099		SH 121 NORTH SGA SIGNALS	08/25/22	50.00	300.00	475.00	500.00
		WEIGHTED AVERAGE FOR THE THIRD QUARTER		50.00	300.00	475.00	500.00
		WEIGHTED AVERAGE FOR THE YEAR		50.00	300.00	475.00	500.00
===== 514-00054 Ped Railing (54 In) Lin Foot =====							
STU0252-457		I-25:ALAMEDA RIVER PH 2.0	11/03/22	150.00	250.00	600.24	680.00
		WEIGHTED AVERAGE FOR THE FOURTH QUARTER		150.00	250.00	600.24	680.00
		WEIGHTED AVERAGE FOR THE YEAR		150.00	250.00	600.24	680.00
===== 514-00100 Hand Rail Lin Foot =====							
BR0343-046		US 34 TIMBER BRIDGE REPL. PKG	08/31/22	290.00	142.31	134.86	134.86
FBR0343-047		US 6/US 34 TIMBER BRIDGE REPL					
		WEIGHTED AVERAGE FOR THE THIRD QUARTER		290.00	142.31	134.86	134.86
TRG0253-264		I-25 AND SH 119 PARK-N-RIDE	10/27/22	16.00	300.00	392.68	330.00
		WEIGHTED AVERAGE FOR THE FOURTH QUARTER		16.00	300.00	392.68	330.00
		WEIGHTED AVERAGE FOR THE YEAR		306.00	150.56	213.81	145.06

COLORADO DEPARTMENT OF TRANSPORTATION
ITEM UNIT COSTS BY PROJECTS -- 2022 COST DATA

11:31 Wednesday, March 8, 2023 278

PROJECT NUMBER	ITEM NUMBER/ PROJECT LOCATION	ITEM DESCRIPTION/ PROJECT LOCATION	DATE LET	UNIT/ QUANTITY	ENGR. EST.	AVERAGE BID	AWARDED BID
===== 514-00200 Pedestrian Railing (Steel) Lin Foot =====							
NHPP0702-413	VAIL PASS AUX PHASE 1 CAP 2	VAIL PASS AUX PHASE 1 CAP 2	04/18/22	1,279.00	304.98	304.98	304.98
	WEIGHTED AVERAGE FOR THE SECOND QUARTER			1,279.00	304.98	304.98	304.98
===== 514-00201 Ped Railing (Steel) (Spec) Lin Foot =====							
NHPP0702-414 FBR0702-423	VAIL PASS AUX PHASE 1 CAP 3	VAIL PASS AUX BE F-12-AT PHAS	07/08/22	491.00	344.54	344.54	344.54
	WEIGHTED AVERAGE FOR THE THIRD QUARTER			491.00	344.54	344.54	344.54
	WEIGHTED AVERAGE FOR THE YEAR			1,770.00	315.95	315.95	315.95
===== 514-00201 Ped Railing (Steel) (Spec) Lin Foot =====							
STU0252-457	I-25:ALAMEDA RIVER PH 2.0	I-25:ALAMEDA RIVER PH 2.0	11/03/22	445.00	500.00	348.82	277.00
STAM420-001	US 285 AT HWY 9C IMPROVEMENTS	US 285 AT HWY 9C IMPROVEMENTS	12/01/22	1,280.00	100.00	133.60	130.00
BR2854-148	INTERSECTION OF US 285 & SH 9	INTERSECTION OF US 285 & SH 9					
STM0091-046	ADA RAMP IMPROVEMENTS - FAIRP	ADA RAMP IMPROVEMENTS - FAIRP					
	WEIGHTED AVERAGE FOR THE FOURTH QUARTER			1,725.00	203.19	178.11	167.92
	WEIGHTED AVERAGE FOR THE YEAR			1,725.00	203.19	178.11	167.92
===== 514-02150 Inst Anchor Bolt Each =====							
2670403-065	US40_FLOYD HILL ROUNDABOUTS	US40_FLOYD HILL ROUNDABOUTS	09/15/22	196.00	170.00	238.00	225.00
	WEIGHTED AVERAGE FOR THE THIRD QUARTER			196.00	170.00	238.00	225.00
	WEIGHTED AVERAGE FOR THE YEAR			196.00	170.00	238.00	225.00
===== 515-00120 Waterproofing (Membrane) Sq Yard =====							
NH0504-910	US50B L-24-B MIN REP AT MP 40	US50B L-24-B MIN REP AT MP 40	01/13/22	147.00	40.00	45.93	41.11
NHPP0702-383	I-70 EB AUX FRISCO TO SILVERT	I-70 EB AUX FRISCO TO SILVERT	01/13/22	5,839.00	21.00	23.57	21.00
NHPP1601-083			02/03/22	12.00	26.00	303.95	60.00
C0762-055			02/17/22	1,610.00	25.00	25.71	35.00
NHPP 0761-238	I-76 DAHLIA TO YORK	I-76 DAHLIA TO YORK	03/10/22	3,126.00	22.00	21.15	19.00

COLORADO DEPARTMENT OF TRANSPORTATION
ITEM UNIT COSTS BY PROJECTS -- 2022 COST DATA

11:31 Wednesday, March 8, 2023 279

PROJECT NUMBER	ITEM NUMBER/ PROJECT LOCATION	ITEM DESCRIPTION/ PROJECT LOCATION	DATE LET	UNIT/ QUANTITY	ENGR. EST.	AVERAGE BID	AWARDED BID
=====	515-00120	Waterproofing (Membrane)		Sq Yard	=====	=====	=====
C0761-239							
BRC040-057			03/17/22	469.00	30.00	38.75	30.00
STR R500-171		Various locations on SH 141 a	03/17/22	1,271.00	15.50	30.41	40.00
		WEIGHTED AVERAGE FOR THE FIRST QUARTER		12,474.00	21.77	24.18	24.85
NH0504-911			04/07/22	4,217.00	24.00	25.00	20.00
STM1151-038		SH115 MP 27 TO MP 38	04/21/22	363.00	27.00	39.85	40.00
2670703-479		I-70 BRIDGE OVER HARLAN	05/05/22	2,606.00	22.00	16.99	19.50
STA0712-019		SH 71: Frieight Improvements	05/12/22	796.00	30.00	16.64	16.64
		WEIGHTED AVERAGE FOR THE SECOND QUARTER		7,982.00	24.08	21.07	20.41
NHPP0702-414		VAIL PASS AUX PHASE 1 CAP 3	07/08/22	3,374.00	26.06	26.06	26.06
FBR0702-423		VAIL PASS AUX BE F-12-AT PHAS					
FSA052A-057		SH52 BOX CULVERT EXTENSION (M	08/04/22	122.00	42.00	39.97	56.52
BR0343-046		US 34 TIMBER BRIDGE REPL. PKG	08/31/22	553.00	28.89	27.36	27.36
FBR0343-047		US 6/US 34 TIMBER BRIDGE REPL					
2670703-497		I-70_GENESEE WILDLIFE XING	09/15/22	1,850.00	24.00	24.72	22.83
		WEIGHTED AVERAGE FOR THE THIRD QUARTER		5,899.00	26.01	25.39	25.80
TRG0253-264		I-25 AND SH 119 PARK-N-RIDE	10/27/22	1,935.00	20.00	28.17	41.00
STU0252-457		I-25:ALAMEDA RIVER PH 2.0	11/03/22	2,944.00	25.00	22.40	19.00
C5502-097		US550 MP 117.28-126.06	11/17/22	116.00	40.00	47.78	43.20
STAM420-001		US 285 AT HWY 9C IMPROVEMENTS	12/01/22	1,646.00	36.00	24.03	27.22
BR2854-148		INTERSECTION OF US 285 & SH 9					
STM0091-046		ADA RAMP IMPROVEMENTS - FAIRP					
STA0711-021		SH71: REGION LINE NORTH	12/01/22	387.00	23.44	29.33	32.00
STR114A-015		SH114 SILLSVILLE SOUTH TO MP3	12/01/22	471.00	16.00	39.50	33.00
2670703-487		I-70 BRIDGES OVER WARD ROAD-	12/01/22	3,771.00	25.00	18.15	18.00
IM025A-050		I25-MP103.9 - INTERSECTION DR	12/01/22	1,100.00	20.00	27.67	25.00
STR109A-019		M-22-AY BRIDGE REHAB ON SH109	12/01/22	4,693.00	25.00	23.34	27.67
BR012A-048		CO 12 STRUCTURE P-17-F AT MP	12/22/22	573.00	40.00	30.36	35.00
STA385A-016		SH 385 MP 97.76	12/22/22	295.00	50.00	69.86	194.44
		WEIGHTED AVERAGE FOR THE FOURTH QUARTER		17,931.00	25.88	24.48	28.99
		WEIGHTED AVERAGE FOR THE YEAR		44,286.00	24.42	23.99	26.11

COLORADO DEPARTMENT OF TRANSPORTATION
ITEM UNIT COSTS BY PROJECTS -- 2022 COST DATA

11:31 Wednesday, March 8, 2023 280

PROJECT NUMBER	ITEM NUMBER/ PROJECT LOCATION	ITEM DESCRIPTION/ PROJECT LOCATION	DATE LET	UNIT/ QUANTITY	ENGR. EST.	AVERAGE BID	AWARDED BID
=====	515-00400	Concrete Sealer		Sq Yard	=====		
NHPP0702-383		I-70 EB AUX FRISCO TO SILVERT	01/13/22	1,175.00	21.00	20.31	17.00
NHPP1601-083			02/03/22	887.00	30.00	57.74	50.00
C0762-055			02/17/22	338.00	175.00	30.11	37.00
STR R500-171		Various locations on SH 141 a	03/17/22	699.00	23.00	36.72	51.00
C0703-499		EJMT GROUT BED REPAIR AND PAN	03/31/22	65.00	50.00	206.00	150.00
		WEIGHTED AVERAGE FOR THE FIRST QUARTER		3,164.00	41.01	32.62	38.63
NHPP0702-413		VAIL PASS AUX PHASE 1 CAP 2	04/18/22	881.00	22.72	22.72	22.72
NHPP0252-448		I-25 TREX NARROWS BRIDGE PREV	06/23/22	9,252.00	12.00	10.91	6.00
		WEIGHTED AVERAGE FOR THE SECOND QUARTER		10,133.00	12.93	11.19	7.45
NHPP0702-414		VAIL PASS AUX PHASE 1 CAP 3	07/08/22	6,499.00	24.46	24.46	24.46
FBR0702-423		VAIL PASS AUX BE F-12-AT PHAS					
2670403-065		US40_FLOYD HILL ROUNDABOUTS	09/15/22	100.00	23.00	18.30	20.00
		WEIGHTED AVERAGE FOR THE THIRD QUARTER		6,599.00	24.44	24.19	24.39
NHPP0705-088		I-70 AGATE STRUCTURE REHAB	10/27/22	1,357.00	20.00	19.36	13.00
STR114A-015		SH114 SILLSVILLE SOUTH TO MP3	12/01/22	244.00	20.00	37.08	50.00
BR012A-048		CO 12 STRUCTURE P-17-F AT MP	12/22/22	286.00	20.00	18.39	17.00
		WEIGHTED AVERAGE FOR THE FOURTH QUARTER		1,887.00	20.00	20.61	18.39
		WEIGHTED AVERAGE FOR THE YEAR		21,783.00	21.11	17.44	18.06
=====	515-00402	Furnish Concrete Sealer (HMWM Resin)		Gallon	=====		
BRC040-057			03/17/22	274.00	100.00	94.25	101.00
		WEIGHTED AVERAGE FOR THE FIRST QUARTER		274.00	100.00	94.25	101.00
		WEIGHTED AVERAGE FOR THE YEAR		274.00	100.00	94.25	101.00
=====	515-00404	Place Concrete Sealer (HMWM Resin)		Sq Foot	=====		
BRC040-057			03/17/22	20,486.00	2.00	1.75	1.55
		WEIGHTED AVERAGE FOR THE FIRST QUARTER		20,486.00	2.00	1.75	1.55
		WEIGHTED AVERAGE FOR THE YEAR		20,486.00	2.00	1.75	1.55

COLORADO DEPARTMENT OF TRANSPORTATION
 ITEM UNIT COSTS BY PROJECTS -- 2022 COST DATA

11:31 Wednesday, March 8, 2023 281

PROJECT NUMBER	ITEM NUMBER/ PROJECT LOCATION	ITEM DESCRIPTION/ PROJECT LOCATION	DATE LET	UNIT/ QUANTITY	ENGR. EST.	AVERAGE BID	AWARDED BID
=====	518-00000	Brdg Compress Joint Sealer		Lin Foot	=====		
C0762-055			02/17/22	100.00	100.00	290.15	375.00
		WEIGHTED AVERAGE FOR THE FIRST QUARTER		100.00	100.00	290.15	375.00
STM1151-038		SH115 MP 27 TO MP 38	04/21/22	148.00	240.00	72.30	135.00
		WEIGHTED AVERAGE FOR THE SECOND QUARTER		148.00	240.00	72.30	135.00
NHPP0705-088		I-70 AGATE STRUCTURE REHAB	10/27/22	724.00	115.00	93.42	87.00
NHPP0701-252		I-70 RIFLE TO SILT SLAB REPLA	12/01/22	552.00	300.00	170.50	161.00
STR109A-019		M-22-AY BRIDGE REHAB ON SH109	12/01/22	120.00	150.00	136.53	143.06
		WEIGHTED AVERAGE FOR THE FOURTH QUARTER		1,396.00	191.16	115.93	121.08
		WEIGHTED AVERAGE FOR THE YEAR		1,644.00	190.01	122.88	137.78
=====	518-00100	Waterstop		Lin Foot	=====		
STR096A-050		SH 96 MP 168.99 TO 193.77	12/22/22	20.00	8.50	216.67	240.00
		WEIGHTED AVERAGE FOR THE FOURTH QUARTER		20.00	8.50	80.52	75.56
		WEIGHTED AVERAGE FOR THE YEAR		20.00	8.50	80.52	75.56
=====	518-00106	Waterstop (6 In)		Lin Foot	=====		
TRG0253-264		I-25 AND SH 119 PARK-N-RIDE	10/27/22	267.00	20.00	17.65	15.00
		WEIGHTED AVERAGE FOR THE FOURTH QUARTER		267.00	20.00	17.65	15.00
		WEIGHTED AVERAGE FOR THE YEAR		267.00	20.00	17.65	15.00
=====	518-01001	Br Expan Joint (Asphaltic Plug)		Lin Foot	=====		
NHPP0702-383		I-70 EB AUX FRISCO TO SILVERT	01/13/22	181.00	200.00	388.68	275.00

COLORADO DEPARTMENT OF TRANSPORTATION
 ITEM UNIT COSTS BY PROJECTS -- 2022 COST DATA

11:31 Wednesday, March 8, 2023 282

PROJECT NUMBER	ITEM NUMBER/ PROJECT LOCATION	ITEM DESCRIPTION/ PROJECT LOCATION	DATE LET	UNIT/ QUANTITY	ENGR. EST.	AVERAGE BID	AWARDED BID
=====	518-01001	Br Expan Joint (Asphaltic Plug)		Lin Foot	=====	=====	=====
STA 067A-048		Hwy 67A MP 0.00 TO MP 11.05 I	03/03/22	80.00	200.00	282.90	300.00
BRC040-057			03/17/22	120.00	250.00	513.25	320.00
		WEIGHTED AVERAGE FOR THE FIRST QUARTER		381.00	215.75	409.85	294.42
NH0504-911			04/07/22	192.00	300.00	352.00	374.00
		WEIGHTED AVERAGE FOR THE SECOND QUARTER		192.00	300.00	352.00	374.00
STA207A-004		Resurfacing SH207A MANZANOLA	10/27/22	151.00	380.00	367.77	303.30
STR109A-019		M-22-AY BRIDGE REHAB ON SH109	12/01/22	510.00	300.00	310.66	315.32
STR096A-050		SH 96 MP 168.99 TO 193.77	12/22/22	252.00	220.00	191.33	200.00
		WEIGHTED AVERAGE FOR THE FOURTH QUARTER		913.00	291.15	305.57	290.66
		WEIGHTED AVERAGE FOR THE YEAR		1,486.00	272.96	343.53	300.93
=====	518-01004	Br Expan Device (0-4 In)		Lin Foot	=====	=====	=====
NHPP0702-383		I-70 EB AUX FRISCO TO SILVERT	01/13/22	124.00	325.00	486.27	355.00
NHPP1601-083			02/03/22	68.00	400.00	931.22	400.00
NHPP 0761-238		I-76 DAHLIA TO YORK	03/10/22	440.00	380.00	400.32	350.00
C0761-239							
STR R500-171		Various locations on SH 141 a	03/17/22	103.00	604.00	496.22	482.00
		WEIGHTED AVERAGE FOR THE FIRST QUARTER		735.00	403.96	434.15	373.97
STM1151-038		SH115 MP 27 TO MP 38	04/21/22	154.00	300.00	306.58	375.00
2670703-479		I-70 BRIDGE OVER HARLAN	05/05/22	268.00	300.00	318.64	340.09
		WEIGHTED AVERAGE FOR THE SECOND QUARTER		422.00	300.00	314.74	352.83
NHPP0702-414		VAIL PASS AUX PHASE 1 CAP 3	07/08/22	104.00	628.12	628.12	628.12
FBR0702-423		VAIL PASS AUX BE F-12-AT PHAS					

COLORADO DEPARTMENT OF TRANSPORTATION
ITEM UNIT COSTS BY PROJECTS -- 2022 COST DATA

11:31 Wednesday, March 8, 2023 283

PROJECT NUMBER	ITEM NUMBER/ PROJECT LOCATION	ITEM DESCRIPTION/ PROJECT LOCATION	DATE LET	UNIT/ QUANTITY	ENGR. EST.	AVERAGE BID	AWARDED BID
=====	518-01004	Br Expan Device (0-4 In)		Lin Foot	=====	=====	=====
STR0711-022		SH 71 OVER THE ARKANSAS	08/04/22	80.00	380.00	167.17	100.00
		WEIGHTED AVERAGE FOR THE THIRD QUARTER		184.00	520.24	306.52	398.50
STU0252-457		I-25:ALAMEDA RIVER PH 2.0	11/03/22	167.00	450.00	390.03	304.00
STR064A-010		SH 64 AND SH 13 AT MEEKER	11/10/22	50.00	500.00	616.00	625.00
STAM420-001		US 285 AT HWY 9C IMPROVEMENTS	12/01/22	200.00	260.00	232.49	278.26
BR2854-148		INTERSECTION OF US 285 & SH 9					
STM0091-046		ADA RAMP IMPROVEMENTS - FAIRP					
IM025A-050		I25-MP103.9 - INTERSECTION DR	12/01/22	46.00	350.00	471.67	480.00
		WEIGHTED AVERAGE FOR THE FOURTH QUARTER		463.00	363.39	374.69	354.88
		WEIGHTED AVERAGE FOR THE YEAR		1,804.00	381.09	386.22	366.00
=====	518-01060	Br Expan Device (Gland) (0-4 In)		Lin Foot	=====	=====	=====
BRC040-057			03/17/22	104.00	350.00	163.25	320.00
		WEIGHTED AVERAGE FOR THE FIRST QUARTER		104.00	350.00	163.25	320.00
NH0504-911			04/07/22	140.00	310.00	161.25	142.50
NHPP0252-448		I-25 TREX NARROWS BRIDGE PREV	06/23/22	190.00	26.32	134.00	115.00
		WEIGHTED AVERAGE FOR THE SECOND QUARTER		330.00	146.67	141.34	126.67
STU0252-457		I-25:ALAMEDA RIVER PH 2.0	11/03/22	362.00	400.00	66.50	60.00
		WEIGHTED AVERAGE FOR THE FOURTH QUARTER		362.00	400.00	75.76	68.61
		WEIGHTED AVERAGE FOR THE YEAR		796.00	288.44	113.52	120.56
=====	518-01250	Br Expan Cover Plate		Lin Foot	=====	=====	=====
BRC040-057			03/17/22	2.00	500.00	2731.75	2100.00
		WEIGHTED AVERAGE FOR THE FIRST QUARTER		2.00	500.00	2731.75	2100.00

COLORADO DEPARTMENT OF TRANSPORTATION
ITEM UNIT COSTS BY PROJECTS -- 2022 COST DATA

11:31 Wednesday, March 8, 2023 284

PROJECT NUMBER	ITEM NUMBER/ PROJECT LOCATION	ITEM DESCRIPTION/ PROJECT LOCATION	DATE LET	UNIT/ QUANTITY	ENGR. EST.	AVERAGE BID	AWARDED BID
=====	518-01250	Br Expan Cover Plate		Lin Foot	=====		
STU0252-457		I-25:ALAMEDA RIVER PH 2.0	11/03/22	103.00	300.00	326.06	407.00
		WEIGHTED AVERAGE FOR THE FOURTH QUARTER		103.00	300.00	326.06	407.00
		WEIGHTED AVERAGE FOR THE YEAR		105.00	303.81	386.77	439.25
=====	518-02030	Polyester Conc End Dam		Cubic Foot	=====		
NHPP0702-414 FBR0702-423		VAIL PASS AUX PHASE 1 CAP 3	07/08/22	156.00	129.25	129.25	129.25
		VAIL PASS AUX BE F-12-AT PHAS					
		WEIGHTED AVERAGE FOR THE THIRD QUARTER		156.00	129.25	129.25	129.25
		WEIGHTED AVERAGE FOR THE YEAR		156.00	129.25	129.25	129.25
=====	518-03000	Saw and Seal Br Joint		Lin Foot	=====		
NHPP1601-083 BRC040-057 STR R500-171			02/03/22	120.00	50.00	119.31	100.00
			03/17/22	104.00	35.00	60.00	35.00
		Various locations on SH 141 a	03/17/22	52.00	56.00	52.31	45.00
		WEIGHTED AVERAGE FOR THE FIRST QUARTER		276.00	45.48	76.05	65.14
NHPP0252-448		I-25 TREX NARROWS BRIDGE PREV	06/23/22	112.00	35.00	42.50	75.00
		WEIGHTED AVERAGE FOR THE SECOND QUARTER		112.00	35.00	42.50	75.00
NHPP0701-231		I-70 SALT WASH BRIDGES SCOUR	09/29/22	40.00	100.00	83.02	85.00
		WEIGHTED AVERAGE FOR THE THIRD QUARTER		40.00	100.00	83.02	85.00
NHPP0701-253		I-70 EAST OF DEBEQUE	10/27/22	152.00	60.00	50.10	52.00

COLORADO DEPARTMENT OF TRANSPORTATION
ITEM UNIT COSTS BY PROJECTS -- 2022 COST DATA

11:31 Wednesday, March 8, 2023 285

PROJECT NUMBER	ITEM NUMBER/ PROJECT LOCATION	ITEM DESCRIPTION/ PROJECT LOCATION	DATE LET	UNIT/ QUANTITY	ENGR. EST.	AVERAGE BID	AWARDED BID
===== 518-03000							
		Saw and Seal Br Joint		Lin Foot			
STA207A-004		Resurfacing SH207A MANZANOLA	10/27/22	151.00	35.00	53.77	43.30
NHPP0705-088		I-70 AGATE STRUCTURE REHAB	10/27/22	1,325.00	50.00	25.60	33.00
STR064A-010		SH 64 AND SH 13 AT MEEKER	11/10/22	100.00	100.00	32.35	33.00
STR114A-015		SH114 SILLSVILLE SOUTH TO MP3	12/01/22	186.00	25.00	59.73	70.00
NHPP0701-252		I-70 RIFLE TO SILT SLAB REPLA	12/01/22	178.00	45.00	39.50	44.00
STR0092-024		SH 9 North of Silverthorne	12/22/22	182.00	100.00	88.50	129.00
	WEIGHTED AVERAGE FOR THE FOURTH QUARTER			2,274.00	53.44	34.05	46.52
	WEIGHTED AVERAGE FOR THE YEAR			2,702.00	52.55	38.86	50.18
===== 518-03100							
		Rapid Cure Silicone Jt Seal		Lin Foot			
BRC040-057			03/17/22	79.00	100.00	58.25	50.00
	WEIGHTED AVERAGE FOR THE FIRST QUARTER			79.00	100.00	58.25	50.00
	WEIGHTED AVERAGE FOR THE YEAR			79.00	100.00	58.25	50.00
===== 519-02000							
		Corner Monuments		Each			
NHPP0253-275		I-25 EXPRESS LANES SEGMENT 5	03/11/22	4.00	445575.86	619235.21	619235.21
	WEIGHTED AVERAGE FOR THE FIRST QUARTER			4.00	445575.86	619235.21	619235.21
	WEIGHTED AVERAGE FOR THE YEAR			4.00	445575.86	619235.21	619235.21
===== 519-03000							
		Thin Bonded Epoxy Overlay		Sq Yard			
NHPP0701-231		I-70 SALT WASH BRIDGES SCOUR	09/29/22	11.00	300.00	389.58	455.00
	WEIGHTED AVERAGE FOR THE THIRD QUARTER			11.00	300.00	389.58	455.00
	WEIGHTED AVERAGE FOR THE YEAR			11.00	300.00	389.58	455.00
===== 519-03035							
		Place Thin Bond Overlay (Poly Conc)		Sq Yard			
STA0252-459			02/03/22	42.00	60.00	827.23	965.00
BRC040-057			03/17/22	15,526.00	30.00	38.40	28.60
	WEIGHTED AVERAGE FOR THE FIRST QUARTER			15,568.00	30.08	40.00	31.13

COLORADO DEPARTMENT OF TRANSPORTATION
 ITEM UNIT COSTS BY PROJECTS -- 2022 COST DATA

11:31 Wednesday, March 8, 2023 286

PROJECT NUMBER	ITEM NUMBER/ PROJECT LOCATION	ITEM DESCRIPTION/ PROJECT LOCATION	DATE LET	UNIT/ QUANTITY	ENGR. EST.	AVERAGE BID	AWARDED BID
===== 519-03035		Place Thin Bond Overlay (Poly Conc)		Sq Yard	=====		
STM1151-038		SH115 MP 27 TO MP 38	04/21/22	1,247.00	55.00	79.59	73.00
NHPP0252-448		I-25 TREX NARROWS BRIDGE PREV	06/23/22	13,654.00	50.00	61.69	66.00
		WEIGHTED AVERAGE FOR THE SECOND QUARTER		14,901.00	50.42	63.52	66.59
NHPP0705-088		I-70 AGATE STRUCTURE REHAB	10/27/22	4,417.00	70.00	120.56	74.00
NHPP0701-252		I-70 RIFLE TO SILT SLAB REPLA	12/01/22	4,480.00	90.00	67.65	72.30
		WEIGHTED AVERAGE FOR THE FOURTH QUARTER		8,897.00	80.07	102.75	73.14
		WEIGHTED AVERAGE FOR THE YEAR		39,366.00	49.08	60.72	54.04
===== 519-03055		Furnish Thin Bond Overlay (Poly Conc)		Cubic Foot	=====		
STA0252-459			02/03/22	92.00	240.00	469.45	569.30
BRC040-057			03/17/22	11,650.00	105.00	133.13	158.50
		WEIGHTED AVERAGE FOR THE FIRST QUARTER		11,742.00	106.06	135.11	161.72
STM1151-038		SH115 MP 27 TO MP 38	04/21/22	702.00	175.00	174.99	167.00
NHPP0252-448		I-25 TREX NARROWS BRIDGE PREV	06/23/22	9,819.00	120.00	112.80	71.00
		WEIGHTED AVERAGE FOR THE SECOND QUARTER		10,521.00	123.67	117.90	77.41
NHPP0705-088		I-70 AGATE STRUCTURE REHAB	10/27/22	9,995.00	145.00	137.87	111.00
NHPP0701-252		I-70 RIFLE TO SILT SLAB REPLA	12/01/22	3,360.00	220.00	135.25	149.50
		WEIGHTED AVERAGE FOR THE FOURTH QUARTER		13,355.00	163.87	137.50	120.69
		WEIGHTED AVERAGE FOR THE YEAR		35,618.00	132.94	130.53	121.43
===== 601-01000		Conc CL B		Cubic Yard	=====		
NHPP0702-383		I-70 EB AUX FRISCO TO SILVERT	01/13/22	25.00	1000.00	1541.24	2090.00

COLORADO DEPARTMENT OF TRANSPORTATION
ITEM UNIT COSTS BY PROJECTS -- 2022 COST DATA

11:31 Wednesday, March 8, 2023 287

PROJECT NUMBER	ITEM NUMBER/ PROJECT LOCATION	ITEM DESCRIPTION/ PROJECT LOCATION	DATE LET	UNIT/ QUANTITY	ENGR. EST.	AVERAGE BID	AWARDED BID
=====	601-01000	Conc CL B		Cubic Yard	=====	=====	=====
NHPP0253-275		I-25 EXPRESS LANES SEGMENT 5	03/11/22	52.00	763.44	689.33	689.33
	WEIGHTED AVERAGE FOR THE FIRST QUARTER			77.00	840.25	1290.96	1144.09
STM1151-038		SH115 MP 27 TO MP 38	04/21/22	7.10	1500.00	2033.07	1750.00
	WEIGHTED AVERAGE FOR THE SECOND QUARTER			7.10	1500.00	2033.07	1750.00
FBR0761-236		I-76 OVER CLR CRK SCOUR MIT	08/25/22	5.00	1400.00	2622.67	1900.00
NHPPR100-266		R1 ESSENTIAL REPAIRS	09/01/22	283.00	1000.00	871.93	1037.79
2670403-065		US40 FLOYD HILL ROUNDABOUTS	09/15/22	17.00	1500.00	1381.77	885.00
SHE2873-193		US 287 & CO 52 INTERSECTION I	09/15/22	220.00	1100.00	952.50	438.00
	WEIGHTED AVERAGE FOR THE THIRD QUARTER			525.00	1061.90	942.90	789.71
C170A-002		CRITICAL CULVERT CONST. PKG D	10/27/22	27.00	1400.00	2363.20	1277.78
STA3852-015		US 385 HOLYOKE NORTH	10/27/22	9.00	1300.00	875.00	875.00
NHPP0343-048		US 34 (MP 169.3-171.4)	11/01/22	12.70	1600.00	1714.65	1100.00
STU0252-457		I-25:ALAMEDA RIVER PH 2.0	11/03/22	2.00	3000.00	2230.50	1450.00
C5502-097		US550 MP 117.28-126.06	11/17/22	54.70	2200.00	2348.10	1890.00
STAM420-001		US 285 AT HWY 9C IMPROVEMENTS	12/01/22	24.00	1406.00	1708.57	904.97
BR2854-148		INTERSECTION OF US 285 & SH 9					
STM0091-046		ADA RAMP IMPROVEMENTS - FAIRP					
NHPP0063-048		US6 / 20 ROAD INTERSECTION IM	12/15/22	4.00	4000.00	1378.99	1300.00
	WEIGHTED AVERAGE FOR THE FOURTH QUARTER			133.40	1843.36	2074.92	1476.72
	WEIGHTED AVERAGE FOR THE YEAR			742.50	1183.51	1158.61	961.99
=====	601-01025	Conc CL B (Misc)		Cubic Yard	=====	=====	=====
NHPP0702-413		VAIL PASS AUX PHASE 1 CAP 2	04/18/22	105.00	2005.37	2005.37	2005.37
2670703-479		I-70 BRIDGE OVER HARLAN	05/05/22	25.00	900.00	760.99	526.58
	WEIGHTED AVERAGE FOR THE SECOND QUARTER			130.00	1792.80	1273.38	1720.99
	WEIGHTED AVERAGE FOR THE YEAR			130.00	1792.80	1273.38	1720.99

COLORADO DEPARTMENT OF TRANSPORTATION
 ITEM UNIT COSTS BY PROJECTS -- 2022 COST DATA

11:31 Wednesday, March 8, 2023 288

PROJECT NUMBER	ITEM NUMBER/ PROJECT LOCATION	ITEM DESCRIPTION/ PROJECT LOCATION	DATE LET	UNIT/ QUANTITY	ENGR. EST.	AVERAGE BID	AWARDED BID
=====	601-03000	Conc CL D		Cubic Yard	=====		
NHPP1601-083			02/03/22	103.00	800.00	2262.00	1800.00
NHPP0253-275		I-25 EXPRESS LANES SEGMENT 5	03/11/22	348.00	789.55	832.54	832.54
		WEIGHTED AVERAGE FOR THE FIRST QUARTER		451.00	791.94	1364.07	1053.49
STA0712-019		SH 71: Frieight Improvements	05/12/22	49.00	1200.00	2929.17	2929.17
		WEIGHTED AVERAGE FOR THE SECOND QUARTER		49.00	1200.00	2929.17	2929.17
FBR0761-236		I-76 OVER CLR CRK SCOUR MIT	08/25/22	165.00	1200.00	1296.67	1200.00
ER0502-092		US 50 MP 204 EB MONARCH TRUCK	08/29/22	51.90	1982.66	2091.71	1535.25
2670403-065		US40_FLOYD HILL ROUNDABOUTS	09/15/22	68.00	1400.00	631.36	625.00
		WEIGHTED AVERAGE FOR THE THIRD QUARTER		284.90	1390.31	1282.70	1123.83
C5502-111		US 550 MP 81 AND 89 RED MOUNT	10/27/22	11.90	6000.00	12250.00	12500.00
TRG0253-264		I-25 AND SH 119 PARK-N-RIDE	10/27/22	346.00	110.00	971.11	665.00
STU0252-457		I-25:ALAMEDA RIVER PH 2.0	11/03/22	8.00	3000.00	1490.18	1260.00
IM025A-050		I25-MP103.9 - INTERSECTION DR	12/01/22	8.00	1000.00	2366.67	1200.00
NHPP0502-090		SH 50 MP 134.6-136 GUNNISON C	12/22/22	54.00	1500.00	2473.15	2136.65
STR0092-024		SH 9 North of Silverthorne	12/22/22	16.00	2500.00	6890.00	1780.00
		WEIGHTED AVERAGE FOR THE FOURTH QUARTER		443.90	591.26	1475.73	1214.46
		WEIGHTED AVERAGE FOR THE YEAR		1,228.80	874.45	1447.47	1204.57
=====	601-03025	Conc CL D (Misc) (C)		Cubic Yard	=====		
NHPP0702-413		VAIL PASS AUX PHASE 1 CAP 2	04/18/22	244.00	1564.83	1564.83	1564.83
		WEIGHTED AVERAGE FOR THE SECOND QUARTER		244.00	1564.83	1564.83	1564.83
NHPP0702-414		VAIL PASS AUX PHASE 1 CAP 3	07/08/22	113.00	1424.55	1424.55	1424.55

COLORADO DEPARTMENT OF TRANSPORTATION
ITEM UNIT COSTS BY PROJECTS -- 2022 COST DATA

11:31 Wednesday, March 8, 2023 289

PROJECT NUMBER	ITEM NUMBER/ PROJECT LOCATION	ITEM DESCRIPTION/ PROJECT LOCATION	DATE LET	UNIT/ QUANTITY	ENGR. EST.	AVERAGE BID	AWARDED BID
=====	601-03025	Conc CL D (Misc) (C)		Cubic Yard	=====		
FBR0702-423		VAIL PASS AUX BE F-12-AT PHAS					
		WEIGHTED AVERAGE FOR THE THIRD QUARTER		113.00	1424.55	1424.55	1424.55
		WEIGHTED AVERAGE FOR THE YEAR		357.00	1520.43	1520.43	1520.43
=====	601-03030	Conc CL D (Box)		Cubic Yard	=====		
NH0504-910		US50B L-24-B MIN REP AT MP 40	01/13/22	132.50	1000.00	1505.55	1000.14
		WEIGHTED AVERAGE FOR THE FIRST QUARTER		132.50	1000.00	1505.55	1000.14
STM1151-038		SH115 MP 27 TO MP 38	04/21/22	39.00	1500.00	1921.93	1750.00
		WEIGHTED AVERAGE FOR THE SECOND QUARTER		39.00	1500.00	1921.93	1750.00
FSA052A-057		SH52 BOX CULVERT EXTENSION (M	08/04/22	85.00	1200.00	1527.75	1024.71
BR0343-046		US 34 TIMBER BRIDGE REPL. PKG	08/31/22	133.00	983.04	894.50	894.50
FBR0343-047		US 6/US 34 TIMBER BRIDGE REPL					
		WEIGHTED AVERAGE FOR THE THIRD QUARTER		218.00	1067.64	1310.68	945.27
TRG0253-264		I-25 AND SH 119 PARK-N-RIDE	10/27/22	962.00	750.00	1013.85	700.00
C5502-097		US550 MP 117.28-126.06	11/17/22	95.60	2000.00	1768.07	2320.00
STA0711-021		SH71: REGION LINE NORTH	12/01/22	86.00	1100.00	1391.67	1500.00
IM025A-050		I25-MP103.9 - INTERSECTION DR	12/01/22	66.00	1000.00	1700.00	1700.00
STA385A-016		SH 385 MP 97.76	12/22/22	351.00	1000.00	1526.25	1500.00
		WEIGHTED AVERAGE FOR THE FOURTH QUARTER		1,560.60	912.66	1132.62	1065.55
		WEIGHTED AVERAGE FOR THE YEAR		1,950.10	947.67	1186.46	1061.35
=====	601-03040	Conc CL D (Bridge)		Cubic Yard	=====		
NHPP0702-383		I-70 EB AUX FRISCO TO SILVERT	01/13/22	661.10	1515.00	2003.96	1720.00

COLORADO DEPARTMENT OF TRANSPORTATION
ITEM UNIT COSTS BY PROJECTS -- 2022 COST DATA

11:31 Wednesday, March 8, 2023 290

PROJECT NUMBER	ITEM NUMBER/ PROJECT LOCATION	ITEM DESCRIPTION/ PROJECT LOCATION	DATE LET	UNIT/ QUANTITY	ENGR. EST.	AVERAGE BID	AWARDED BID
=====	601-03040	Conc CL D (Bridge)		Cubic Yard	=====	=====	=====
NHPP 0761-238 C0761-239		I-76 DAHLIA TO YORK	03/10/22	40.00	1200.00	1105.87	820.00
	WEIGHTED AVERAGE FOR THE FIRST QUARTER			701.10	1497.03	1924.69	1668.65
NHPP0702-413 STM1151-038		VAIL PASS AUX PHASE 1 CAP 2 SH115 MP 27 TO MP 38	04/18/22 04/21/22	263.00 82.20	1791.95 1300.00	1791.95 1186.49	1791.95 1000.00
	WEIGHTED AVERAGE FOR THE SECOND QUARTER			345.20	1674.81	1422.75	1603.37
NHPP0702-414 FBR0702-423 NHPP0701-231		VAIL PASS AUX PHASE 1 CAP 3 VAIL PASS AUX BE F-12-AT PHAS I-70 SALT WASH BRIDGES SCOUR	07/08/22 09/29/22	1,773.00 18.70	1439.41 3000.00	1439.41 2873.77	1439.41 1450.00
	WEIGHTED AVERAGE FOR THE THIRD QUARTER			1,791.70	1455.70	1469.04	1439.52
NHPP0701-253 STU0252-457 STR064A-010 STAM420-001 BR2854-148 STM0091-046 IM025A-050 BR012A-048		I-70 EAST OF DEBEQUE I-25:ALAMEDA RIVER PH 2.0 SH 64 AND SH 13 AT MEEKER US 285 AT HWY 9C IMPROVEMENTS INTERSECTION OF US 285 & SH 9 ADA RAMP IMPROVEMENTS - FAIRP I25-MP103.9 - INTERSECTION DR CO 12 STRUCTURE P-17-F AT MP	10/27/22 11/03/22 11/10/22 12/01/22 12/01/22 12/01/22 12/22/22	1.00 2,869.00 7.00 106.00 115.00 94.50	6000.00 1000.00 3000.00 1250.00 1000.00 2000.00	14010.00 1056.67 562.00 1821.02 2266.67 2250.00	15000.00 860.00 570.00 1100.00 1900.00 1800.00
	WEIGHTED AVERAGE FOR THE FOURTH QUARTER			3,192.50	1043.85	1159.58	937.05
	WEIGHTED AVERAGE FOR THE YEAR			6,030.50	1255.02	1383.38	1209.53
=====	601-03050	Conc CL D (Wall)		Cubic Yard	=====	=====	=====
NHPP0702-413 STM1151-038 2670703-479		VAIL PASS AUX PHASE 1 CAP 2 SH115 MP 27 TO MP 38 I-70 BRIDGE OVER HARLAN	04/18/22 04/21/22 05/05/22	23.00 41.00 39.00	1602.28 1500.00 950.00	1602.28 1848.99 1225.33	1602.28 1750.00 529.86
	WEIGHTED AVERAGE FOR THE SECOND QUARTER			103.00	1314.59	1520.83	1255.02
NHPP0702-414		VAIL PASS AUX PHASE 1 CAP 3	07/08/22	7.00	1868.56	1868.56	1868.56

COLORADO DEPARTMENT OF TRANSPORTATION
ITEM UNIT COSTS BY PROJECTS -- 2022 COST DATA

11:31 Wednesday, March 8, 2023 291

PROJECT NUMBER	ITEM NUMBER/ PROJECT LOCATION	ITEM DESCRIPTION/ PROJECT LOCATION	DATE LET	UNIT/ QUANTITY	ENGR. EST.	AVERAGE BID	AWARDED BID
=====	601-03050	Conc CL D (Wall)		Cubic Yard	=====		
FBR0702-423		VAIL PASS AUX BE F-12-AT PHAS					
NHPP0063-054		US 6 FROM I70-B TO 33 RD. (MP	08/18/22	14.00	1100.00	1453.49	1000.00
		WEIGHTED AVERAGE FOR THE THIRD QUARTER		21.00	1356.19	1536.50	1289.52
TRG0253-264		I-25 AND SH 119 PARK-N-RIDE	10/27/22	82.00	850.00	1317.28	950.00
STU0252-457		I-25:ALAMEDA RIVER PH 2.0	11/03/22	46.00	1800.00	1789.93	1300.00
C5502-097		US550 MP 117.28-126.06	11/17/22	24.00	1900.00	1797.59	1820.00
STAM420-001		US 285 AT HWY 9C IMPROVEMENTS	12/01/22	285.00	1250.00	1210.12	1100.00
BR2854-148		INTERSECTION OF US 285 & SH 9					
STM0091-046		ADA RAMP IMPROVEMENTS - FAIRP					
2670703-487		I-70 BRIDGES OVER WARD ROAD-	12/01/22	71.00	800.00	1391.62	1200.00
IM025A-050		I25-MP103.9 - INTERSECTION DR	12/01/22	25.00	1100.00	2616.67	3000.00
		WEIGHTED AVERAGE FOR THE FOURTH QUARTER		533.00	1198.22	1358.94	1229.04
		WEIGHTED AVERAGE FOR THE YEAR		657.00	1221.51	1386.56	1235.05
=====	601-03056	Conc CL DF		Cubic Yard	=====		
NHPPR100-266		R1 ESSENTIAL REPAIRS	09/01/22	203.00	1350.00	1027.92	1164.77
2670703-497		I-70_GENESEE WILDLIFE XING	09/15/22	856.00	900.00	1084.25	827.60
		WEIGHTED AVERAGE FOR THE THIRD QUARTER		1,059.00	986.26	1079.05	892.23
STAM420-001		US 285 AT HWY 9C IMPROVEMENTS	12/01/22	681.00	1050.00	1380.57	900.00
BR2854-148		INTERSECTION OF US 285 & SH 9					
STM0091-046		ADA RAMP IMPROVEMENTS - FAIRP					
IM025A-050		I25-MP103.9 - INTERSECTION DR	12/01/22	493.00	1200.00	1400.00	1400.00
BR012A-048		CO 12 STRUCTURE P-17-F AT MP	12/22/22	169.60	2500.00	2150.00	1800.00
		WEIGHTED AVERAGE FOR THE FOURTH QUARTER		1,343.60	1288.07	1300.30	1176.88
		WEIGHTED AVERAGE FOR THE YEAR		2,402.60	1155.04	1204.09	1088.52
=====	601-03057	Conc CL DR		Cubic Yard	=====		
NHPP0702-383		I-70 EB AUX FRISCO TO SILVERT	01/13/22	119.00	2640.00	1368.83	1100.00

COLORADO DEPARTMENT OF TRANSPORTATION
ITEM UNIT COSTS BY PROJECTS -- 2022 COST DATA

11:31 Wednesday, March 8, 2023 292

PROJECT NUMBER	ITEM NUMBER/ PROJECT LOCATION	ITEM DESCRIPTION/ PROJECT LOCATION	DATE LET	UNIT/ QUANTITY	ENGR. EST.	AVERAGE BID	AWARDED BID
===== 601-03057 Conc CL DR Cubic Yard =====							
NHPP1601-083			02/03/22	10.00	2500.00	4057.53	2000.00
C0762-055			02/17/22	12.00	2500.00	5317.92	6500.00
BRC040-057			03/17/22	26.00	2100.00	2889.50	2180.00
STR R500-171		Various locations on SH 141 a	03/17/22	23.00	3850.00	3426.14	2975.00
WEIGHTED AVERAGE FOR THE FIRST QUARTER				190.00	2696.37	2018.87	1863.18
NH0504-911			04/07/22	48.00	2016.00	3135.00	2970.00
STM1151-038		SH115 MP 27 TO MP 38	04/21/22	23.00	2300.00	1799.99	2250.00
WEIGHTED AVERAGE FOR THE SECOND QUARTER				71.00	2108.00	2407.39	2736.76
NHPP0701-231		I-70 SALT WASH BRIDGES SCOUR	09/29/22	1.10	6000.00	4173.74	3400.00
WEIGHTED AVERAGE FOR THE THIRD QUARTER				1.10	6000.00	4173.74	3400.00
NHPP0705-088		I-70 AGATE STRUCTURE REHAB	10/27/22	72.00	2400.00	2283.99	2100.00
STA0711-021		SH71: REGION LINE NORTH	12/01/22	8.00	2000.00	3508.33	3600.00
NHPP0701-252		I-70 RIFLE TO SILT SLAB REPLA	12/01/22	28.00	3000.00	2580.00	2160.00
STR109A-019		M-22-AY BRIDGE REHAB ON SH109	12/01/22	260.00	2500.00	2367.95	1712.90
WEIGHTED AVERAGE FOR THE FOURTH QUARTER				368.00	2507.61	2508.31	1974.96
WEIGHTED AVERAGE FOR THE YEAR				630.10	2525.60	2318.55	2023.57
===== 601-03540 Conc CL DT (Deck Topping) Cubic Yard =====							
NHPP0705-088		I-70 AGATE STRUCTURE REHAB	10/27/22	68.00	3000.00	1365.26	1280.00
WEIGHTED AVERAGE FOR THE FOURTH QUARTER				68.00	3000.00	1365.26	1280.00
WEIGHTED AVERAGE FOR THE YEAR				68.00	3000.00	1365.26	1280.00
===== 601-04550 Conc CL G Cubic Yard =====							
NHPP 0761-238		I-76 DAHLIA TO YORK	03/10/22	1,521.00	1200.00	1018.94	1030.00

COLORADO DEPARTMENT OF TRANSPORTATION
 ITEM UNIT COSTS BY PROJECTS -- 2022 COST DATA

11:31 Wednesday, March 8, 2023 293

PROJECT NUMBER	ITEM NUMBER/ PROJECT LOCATION	ITEM DESCRIPTION/ PROJECT LOCATION	DATE LET	UNIT/ QUANTITY	ENGR. EST.	AVERAGE BID	AWARDED BID
=====	601-04550	Conc CL G		Cubic Yard	=====		
C0761-239							
	WEIGHTED AVERAGE FOR THE FIRST QUARTER			1,521.00	1200.00	1018.94	1030.00
STM1151-038		SH115 MP 27 TO MP 38	04/21/22	481.40	990.00	979.29	1100.00
2670703-479		I-70 BRIDGE OVER HARLAN	05/05/22	958.00	600.00	1111.77	850.00
	WEIGHTED AVERAGE FOR THE SECOND QUARTER			1,439.40	730.43	1072.67	933.61
STU0252-457		I-25:ALAMEDA RIVER PH 2.0	11/03/22	475.00	1100.00	716.67	670.00
2670703-487		I-70 BRIDGES OVER WARD ROAD-	12/01/22	1,958.00	850.00	1134.00	990.00
	WEIGHTED AVERAGE FOR THE FOURTH QUARTER			2,433.00	898.81	1080.97	927.53
	WEIGHTED AVERAGE FOR THE YEAR			5,393.40	938.81	1054.89	958.05
=====	601-06020	Conc (Patching) (Polymer)		Cubic Yard	=====		
STR R500-171		Various locations on SH 141 a	03/17/22	1.00	3400.00	2922.84	4300.00
	WEIGHTED AVERAGE FOR THE FIRST QUARTER			1.00	3400.00	2922.84	4300.00
	WEIGHTED AVERAGE FOR THE YEAR			1.00	3400.00	2922.84	4300.00
=====	601-06100	Conc (Patching)		Cubic Yard	=====		
NHM765-007			03/31/22	1.00	3500.00	4649.60	11730.60
	WEIGHTED AVERAGE FOR THE FIRST QUARTER			1.00	3500.00	4649.60	11730.60
NHPP0701-231		I-70 SALT WASH BRIDGES SCOUR	09/29/22	0.10	5000.00	5025.51	3000.00
	WEIGHTED AVERAGE FOR THE THIRD QUARTER			0.10	5000.00	5025.51	3000.00
STR109A-019		M-22-AY BRIDGE REHAB ON SH109	12/01/22	64.00	6000.00	6388.80	5322.60
	WEIGHTED AVERAGE FOR THE FOURTH QUARTER			64.00	6000.00	6388.80	5322.60
	WEIGHTED AVERAGE FOR THE YEAR			65.10	5960.06	6346.95	5417.47

COLORADO DEPARTMENT OF TRANSPORTATION
ITEM UNIT COSTS BY PROJECTS -- 2022 COST DATA

11:31 Wednesday, March 8, 2023 294

PROJECT NUMBER	ITEM NUMBER/ PROJECT LOCATION	ITEM DESCRIPTION/ PROJECT LOCATION	DATE LET	UNIT/ QUANTITY	ENGR. EST.	AVERAGE BID	AWARDED BID
===== 601-06102 Concrete (Patching) Cubic Foot =====							
BRC040-057			03/17/22	8.00	325.00	904.25	1975.00
	WEIGHTED AVERAGE FOR THE FIRST QUARTER			8.00	325.00	904.25	1975.00
NH0504-911			04/07/22	76.00	300.00	1035.00	870.00
STM1151-038		SH115 MP 27 TO MP 38	04/21/22	48.00	500.00	517.23	450.00
	WEIGHTED AVERAGE FOR THE SECOND QUARTER			124.00	377.42	718.00	707.42
ER0253-297		WCR 34 BRIDGE OVER I-25(MM 24	09/14/22	149.00	1000.00	789.32	130.00
	WEIGHTED AVERAGE FOR THE THIRD QUARTER			149.00	1000.00	789.32	130.00
NHPP0705-088		I-70 AGATE STRUCTURE REHAB	10/27/22	30.00	400.00	876.62	850.00
STA0711-021		SH71: REGION LINE NORTH	12/01/22	11.00	320.00	860.00	850.00
STR096A-050		SH 96 MP 168.99 TO 193.77	12/22/22	42.30	120.00	811.00	900.00
	WEIGHTED AVERAGE FOR THE FOURTH QUARTER			83.30	247.25	864.81	892.60
	WEIGHTED AVERAGE FOR THE YEAR			364.30	601.14	787.57	545.01
===== 601-06150 Conc (Patching) Sq Foot =====							
FBR0761-236		I-76 OVER CLR CRK SCOUR MIT	08/25/22	200.00	150.00	96.83	25.00
	WEIGHTED AVERAGE FOR THE THIRD QUARTER			200.00	150.00	96.83	25.00
	WEIGHTED AVERAGE FOR THE YEAR			200.00	150.00	96.83	25.00
===== 601-06300 Cement Grout Cubic Foot =====							
STA 067A-048		Hwy 67A MP 0.00 TO MP 11.05 I	03/03/22	1.00	1000.00	1169.20	800.00
	WEIGHTED AVERAGE FOR THE FIRST QUARTER			1.00	1000.00	1169.20	800.00

PROJECT NUMBER	ITEM NUMBER/ PROJECT LOCATION	ITEM DESCRIPTION/ PROJECT LOCATION	DATE LET	UNIT/ QUANTITY	ENGR. EST.	AVERAGE BID	AWARDED BID
=====	601-06300	Cement Grout		Cubic Foot	=====		
C0852-120		Rehabilitation of Culvert by	05/26/22	2,916.00	52.00	20.00	20.00
	WEIGHTED AVERAGE FOR THE SECOND QUARTER			2,916.00	52.00	20.00	20.00
	WEIGHTED AVERAGE FOR THE YEAR			2,917.00	52.32	61.51	25.15
=====	601-07000	Conc Retaining Wall		Sq Foot	=====		
NHPP0063-054		US 6 FROM I70-B TO 33 RD. (MP	08/18/22	550.00	800.00	60.75	56.00
	WEIGHTED AVERAGE FOR THE THIRD QUARTER			550.00	800.00	60.75	56.00
STRC090-011		US 50B AND SH71/CR18 INTERSEC	11/17/22	1,550.00	33.60	132.50	100.00
	WEIGHTED AVERAGE FOR THE FOURTH QUARTER			1,550.00	33.60	132.50	100.00
	WEIGHTED AVERAGE FOR THE YEAR			2,100.00	234.32	113.71	88.48
=====	601-10250	Slab Jacking		Pound	=====		
STR0711-022		SH 71 OVER THE ARKANSAS	08/04/22	4,800.00	8.50	17.33	14.00
	WEIGHTED AVERAGE FOR THE THIRD QUARTER			4,800.00	8.50	17.33	14.00
	WEIGHTED AVERAGE FOR THE YEAR			4,800.00	8.50	17.33	14.00
=====	601-10310	Fly Ash Slurry		Cubic Yard	=====		
NHPP0702-414 FBR0702-423		VAIL PASS AUX PHASE 1 CAP 3	07/08/22	7.00	739.42	739.42	739.42
	WEIGHTED AVERAGE FOR THE THIRD QUARTER	VAIL PASS AUX BE F-12-AT PHAS		7.00	739.42	739.42	739.42
	WEIGHTED AVERAGE FOR THE YEAR			7.00	739.42	739.42	739.42
=====	601-10400	Drilled Hole		Each	=====		
STA0252-459			02/03/22	100.00	80.00	129.00	93.00
	WEIGHTED AVERAGE FOR THE FIRST QUARTER			100.00	80.00	129.00	93.00
	WEIGHTED AVERAGE FOR THE YEAR			100.00	80.00	129.00	93.00

COLORADO DEPARTMENT OF TRANSPORTATION
ITEM UNIT COSTS BY PROJECTS -- 2022 COST DATA

11:31 Wednesday, March 8, 2023 296

PROJECT NUMBER	ITEM NUMBER/ PROJECT LOCATION	ITEM DESCRIPTION/ PROJECT LOCATION	DATE LET	UNIT/ QUANTITY	ENGR. EST.	AVERAGE BID	AWARDED BID
=====	601-13001	Str Conc Stain (Special)		Sq Yard	=====		
NHPP0702-413		VAIL PASS AUX PHASE 1 CAP 2	04/18/22	628.00	21.38	21.38	21.38
		WEIGHTED AVERAGE FOR THE SECOND QUARTER		628.00	21.38	21.38	21.38
NHPP0702-414 FBR0702-423		VAIL PASS AUX PHASE 1 CAP 3 VAIL PASS AUX BE F-12-AT PHAS	07/08/22	1,223.00	109.42	109.42	109.42
		WEIGHTED AVERAGE FOR THE THIRD QUARTER		1,223.00	109.42	109.42	109.42
		WEIGHTED AVERAGE FOR THE YEAR		1,851.00	79.55	79.55	79.55
=====	601-25735	Precast Deck Panel (3.5 In)		Sq Yard	=====		
NHPP0702-414 FBR0702-423		VAIL PASS AUX PHASE 1 CAP 3 VAIL PASS AUX BE F-12-AT PHAS	07/08/22	2,416.00	139.14	139.14	139.14
		WEIGHTED AVERAGE FOR THE THIRD QUARTER		2,416.00	139.14	139.14	139.14
		WEIGHTED AVERAGE FOR THE YEAR		2,416.00	139.14	139.14	139.14
=====	601-40300	Struct Conc Coating		Sq Yard	=====		
NHPP0702-383 NHPP 0761-238 C0761-239		I-70 EB AUX FRISCO TO SILVERT I-76 DAHLIA TO YORK	01/13/22 03/10/22	1,175.00 4,097.00	15.00 19.00	19.15 15.59	21.00 10.00
		WEIGHTED AVERAGE FOR THE FIRST QUARTER		5,272.00	18.11	16.13	12.45
2670703-497		I-70_GENESEE WILDLIFE XING	09/15/22	1,589.00	18.00	19.05	13.09
		WEIGHTED AVERAGE FOR THE THIRD QUARTER		1,589.00	18.00	19.05	13.09
STU0252-457		I-25:ALAMEDA RIVER PH 2.0	11/03/22	382.00	15.00	18.81	13.00

COLORADO DEPARTMENT OF TRANSPORTATION
ITEM UNIT COSTS BY PROJECTS -- 2022 COST DATA

11:31 Wednesday, March 8, 2023 297

PROJECT NUMBER	ITEM NUMBER/ PROJECT LOCATION	ITEM DESCRIPTION/ PROJECT LOCATION	DATE LET	UNIT/ QUANTITY	ENGR. EST.	AVERAGE BID	AWARDED BID
=====	601-40300	Struct Conc Coating		Sq Yard	=====	=====	=====
C5502-097		US550 MP 117.28-126.06	11/17/22	79.00	35.00	23.22	13.00
		WEIGHTED AVERAGE FOR THE FOURTH QUARTER		461.00	18.43	19.56	13.00
		WEIGHTED AVERAGE FOR THE YEAR		7,322.00	18.11	16.86	12.62
=====	601-40301	Struct Conc Coating		Sq Foot	=====	=====	=====
NHPP 0761-238 C0761-239		I-76 DAHLIA TO YORK	03/10/22	194.00	12.00	5.07	1.10
		WEIGHTED AVERAGE FOR THE FIRST QUARTER		194.00	12.00	5.07	1.10
		WEIGHTED AVERAGE FOR THE YEAR		194.00	12.00	5.07	1.10
=====	601-40302	Struct Conc Coating (Anti-Graf)		Sq Foot	=====	=====	=====
NHPP0702-383		I-70 EB AUX FRISCO TO SILVERT	01/13/22	2,284.00	3.00	2.88	4.00
		WEIGHTED AVERAGE FOR THE FIRST QUARTER		2,284.00	3.00	2.88	4.00
NH0504-911 NHPP0702-413		VAIL PASS AUX PHASE 1 CAP 2	04/07/22 04/18/22	5,600.00 28,262.00	4.00 2.68	10.20 2.68	18.00 2.68
		WEIGHTED AVERAGE FOR THE SECOND QUARTER		33,862.00	2.90	4.81	5.21
STU0252-457		I-25:ALAMEDA RIVER PH 2.0	11/03/22	19,291.00	2.50	2.05	2.00
		WEIGHTED AVERAGE FOR THE FOURTH QUARTER		19,291.00	2.50	2.05	2.00
		WEIGHTED AVERAGE FOR THE YEAR		55,437.00	2.76	3.14	4.05
=====	601-40400	Struct Conc Stain		Sq Yard	=====	=====	=====
NHPP0253-275		I-25 EXPRESS LANES SEGMENT 5	03/11/22	415.00	44.10	48.65	48.65
		WEIGHTED AVERAGE FOR THE FIRST QUARTER		415.00	44.10	48.65	48.65

COLORADO DEPARTMENT OF TRANSPORTATION
 ITEM UNIT COSTS BY PROJECTS -- 2022 COST DATA

11:31 Wednesday, March 8, 2023 298

PROJECT NUMBER	ITEM NUMBER/ PROJECT LOCATION	ITEM DESCRIPTION/ PROJECT LOCATION	DATE LET	UNIT/ QUANTITY	ENGR. EST.	AVERAGE BID	AWARDED BID
=====	601-40400	Struct Conc Stain		Sq Yard	=====		
NHPP0702-413		VAIL PASS AUX PHASE 1 CAP 2	04/18/22	2,133.00	40.56	40.56	40.56
2670703-479		I-70 BRIDGE OVER HARLAN	05/05/22	7,048.00	22.00	12.93	14.50
		WEIGHTED AVERAGE FOR THE SECOND QUARTER		9,181.00	26.31	14.26	20.55
NHPP0702-414		VAIL PASS AUX PHASE 1 CAP 3	07/08/22	5,827.00	43.61	43.61	43.61
FBR0702-423		VAIL PASS AUX BE F-12-AT PHAS					
2670403-065		US40_FLOYD HILL ROUNDABOUTS	09/15/22	1,600.00	50.00	19.57	20.00
		WEIGHTED AVERAGE FOR THE THIRD QUARTER		7,427.00	44.99	32.75	38.52
TRG0253-264		I-25 AND SH 119 PARK-N-RIDE	10/27/22	2,696.00	25.00	21.96	25.00
STU0252-457		I-25:ALAMEDA RIVER PH 2.0	11/03/22	2,147.00	15.00	14.04	13.00
STAM420-001		US 285 AT HWY 9C IMPROVEMENTS	12/01/22	1,340.00	26.00	26.11	36.20
BR2854-148		INTERSECTION OF US 285 & SH 9					
STM0091-046		ADA RAMP IMPROVEMENTS - FAIRP					
2670703-487		I-70 BRIDGES OVER WARD ROAD-	12/01/22	3,181.00	30.00	13.32	13.00
IM025A-050		I25-MP103.9 - INTERSECTION DR	12/01/22	1,895.00	14.00	13.33	13.00
		WEIGHTED AVERAGE FOR THE FOURTH QUARTER		11,259.00	22.77	18.04	18.63
		WEIGHTED AVERAGE FOR THE YEAR		28,282.00	30.07	18.05	24.92
=====	601-51005	Galvanic Anodes		Each	=====		
NHPP0702-383		I-70 EB AUX FRISCO TO SILVERT	01/13/22	2,125.00	40.00	38.37	33.00
C0762-055			02/17/22	280.00	44.00	30.41	35.00
BRC040-057			03/17/22	550.00	30.00	68.38	61.50
STR R500-171		Various locations on SH 141 a	03/17/22	476.00	33.00	30.89	38.00
		WEIGHTED AVERAGE FOR THE FIRST QUARTER		3,431.00	37.75	41.39	38.43
NH0504-911			04/07/22	1,955.00	30.00	29.15	33.30

COLORADO DEPARTMENT OF TRANSPORTATION
ITEM UNIT COSTS BY PROJECTS -- 2022 COST DATA

11:31 Wednesday, March 8, 2023 299

PROJECT NUMBER	ITEM NUMBER/ PROJECT LOCATION	ITEM DESCRIPTION/ PROJECT LOCATION	DATE LET	UNIT/ QUANTITY	ENGR. EST.	AVERAGE BID	AWARDED BID
=====	601-51005	Galvanic Anodes		Each =====			
STM1151-038		SH115 MP 27 TO MP 38	04/21/22	320.00	40.00	28.47	10.00
		WEIGHTED AVERAGE FOR THE SECOND QUARTER		2,275.00	31.41	28.95	30.02
NHPP0701-231		I-70 SALT WASH BRIDGES SCOUR	09/29/22	30.00	50.00	48.22	35.00
		WEIGHTED AVERAGE FOR THE THIRD QUARTER		30.00	50.00	48.22	35.00
NHPP0705-088		I-70 AGATE STRUCTURE REHAB	10/27/22	2,700.00	39.78	29.71	31.00
STA0711-021		SH71: REGION LINE NORTH	12/01/22	275.00	33.40	44.28	44.00
NHPP0701-252		I-70 RIFLE TO SILT SLAB REPLA	12/01/22	1,140.00	45.00	36.50	44.00
STR109A-019		M-22-AY BRIDGE REHAB ON SH109	12/01/22	1,300.00	35.00	36.44	31.88
		WEIGHTED AVERAGE FOR THE FOURTH QUARTER		5,415.00	39.41	32.43	34.61
		WEIGHTED AVERAGE FOR THE YEAR		11,151.00	37.30	35.62	34.85
=====	602-00000	Reinf Steel		Pound =====			
NHPP0702-383		I-70 EB AUX FRISCO TO SILVERT	01/13/22	17,371.00	3.00	1.73	1.65
C0762-055			02/17/22	280.00	4.00	7.42	9.00
NHPP0253-275		I-25 EXPRESS LANES SEGMENT 5	03/11/22	64,145.00	1.15	1.40	1.40
BRC040-057			03/17/22	600.00	2.00	5.94	3.75
		WEIGHTED AVERAGE FOR THE FIRST QUARTER		82,396.00	1.56	1.70	1.50
NH0504-911			04/07/22	2,155.00	2.00	6.50	6.00
NHPP0702-413		VAIL PASS AUX PHASE 1 CAP 2	04/18/22	66,202.00	1.87	1.87	1.87
STM1151-038		SH115 MP 27 TO MP 38	04/21/22	32,751.00	1.25	1.71	1.50
		WEIGHTED AVERAGE FOR THE SECOND QUARTER		101,108.00	1.67	1.84	1.84
NHPP0702-414		VAIL PASS AUX PHASE 1 CAP 3	07/08/22	140,740.00	1.81	1.81	1.81
FBR0702-423		VAIL PASS AUX BE F-12-AT PHAS					

COLORADO DEPARTMENT OF TRANSPORTATION
ITEM UNIT COSTS BY PROJECTS -- 2022 COST DATA

11:31 Wednesday, March 8, 2023 300

PROJECT NUMBER	ITEM NUMBER/ PROJECT LOCATION	ITEM DESCRIPTION/ PROJECT LOCATION	DATE LET	UNIT/ QUANTITY	ENGR. EST.	AVERAGE BID	AWARDED BID
===== 602-00000 Reinf Steel Pound =====							
ER0253-297		WCR 34 BRIDGE OVER I-25(MM 24	09/14/22	2,229.00	2.00	16.79	3.80
NHPP0701-231		I-70 SALT WASH BRIDGES SCOUR	09/29/22	4,480.00	5.00	2.42	2.00
		WEIGHTED AVERAGE FOR THE THIRD QUARTER		147,449.00	1.91	2.69	1.85
NHPP0705-088		I-70 AGATE STRUCTURE REHAB	10/27/22	3,205.00	2.10	5.36	5.00
C5502-111		US 550 MP 81 AND 89 RED MOUNT	10/27/22	815.00	10.00	35.00	30.00
C170A-002		CRITICAL CULVERT CONST. PKG D	10/27/22	3,620.00	2.00	4.35	3.23
STU0252-457		I-25:ALAMEDA RIVER PH 2.0	11/03/22	206,770.00	1.50	1.72	1.70
C5502-097		US550 MP 117.28-126.06	11/17/22	22,105.00	2.00	2.43	3.25
STA0711-021		SH71: REGION LINE NORTH	12/01/22	155.00	2.80	4.84	5.00
2670703-487		I-70 BRIDGES OVER WARD ROAD-	12/01/22	1,229.00	3.00	1.88	1.30
IM025A-050		I25-MP103.9 - INTERSECTION DR	12/01/22	16,122.00	2.00	1.90	1.80
STR109A-019		M-22-AY BRIDGE REHAB ON SH109	12/01/22	8,100.00	4.00	3.47	1.93
NHPP0502-090		SH 50 MP 134.6-136 GUNNISON C	12/22/22	10,025.00	2.00	3.55	4.94
BR012A-048		CO 12 STRUCTURE P-17-F AT MP	12/22/22	13,221.00	3.00	1.86	2.00
		WEIGHTED AVERAGE FOR THE FOURTH QUARTER		285,367.00	1.77	2.08	1.98
		WEIGHTED AVERAGE FOR THE YEAR		616,320.00	1.76	2.07	1.88
===== 602-00020 Reinf Steel (Epoxy) Pound =====							
NH0504-910		US50B L-24-B MIN REP AT MP 40	01/13/22	26,600.00	2.00	2.60	2.53
NHPP0702-383		I-70 EB AUX FRISCO TO SILVERT	01/13/22	163,271.00	2.00	1.86	1.80
NHPP1601-083			02/03/22	9,863.00	5.00	3.97	3.00
NHPP 0761-238		I-76 DAHLIA TO YORK	03/10/22	316,162.00	1.60	1.65	1.35
C0761-239							
BRC040-057			03/17/22	395.00	2.00	7.93	4.20
STR R500-171		Various locations on SH 141 a	03/17/22	3,432.00	5.00	3.71	3.50
		WEIGHTED AVERAGE FOR THE FIRST QUARTER		519,723.00	1.83	1.77	1.60
NHPP0702-413		VAIL PASS AUX PHASE 1 CAP 2	04/18/22	36,366.00	3.85	3.85	3.85
STM1151-038		SH115 MP 27 TO MP 38	04/21/22	99,633.00	1.80	1.82	1.70
2670703-479		I-70 BRIDGE OVER HARLAN	05/05/22	363,735.00	1.50	1.70	1.50
STA0712-019		SH 71: Frieight Improvements	05/12/22	8,307.00	2.60	3.01	3.01
		WEIGHTED AVERAGE FOR THE SECOND QUARTER		508,041.00	1.75	1.75	1.73
NHPP0702-414		VAIL PASS AUX PHASE 1 CAP 3	07/08/22	323,170.00	2.88	2.88	2.88

PROJECT NUMBER	ITEM NUMBER/ PROJECT LOCATION	ITEM DESCRIPTION/ PROJECT LOCATION	DATE LET	UNIT/ QUANTITY	ENGR. EST.	AVERAGE BID	AWARDED BID
===== 602-00020 Reinf Steel (Epoxy) Pound =====							
FBR0702-423		VAIL PASS AUX BE F-12-AT PHAS					
FSA052A-057		SH52 BOX CULVERT EXTENSION (M	08/04/22	27,691.00	3.00	3.19	3.32
NHPP0063-054		US 6 FROM I70-B TO 33 RD. (MP	08/18/22	1,030.00	4.00	3.38	3.50
FBR0761-236		I-76 OVER CLR CRK SCOUR MIT	08/25/22	11,269.00	4.00	5.08	3.85
ER0502-092		US 50 MP 204 EB MONARCH TRUCK	08/29/22	3,717.00	7.00	3.23	1.95
BR0343-046		US 34 TIMBER BRIDGE REPL. PKG	08/31/22	13,522.00	1.52	1.70	1.70
FBR0343-047		US 6/US 34 TIMBER BRIDGE REPL					
NHPPR100-266		R1 ESSENTIAL REPAIRS	09/01/22	25,941.00	6.00	3.34	2.53
2670403-065		US40 FLOYD HILL ROUNDABOUTS	09/15/22	54,110.00	4.00	2.58	2.80
2670703-497		I-70 GENESEE WILDLIFE XING	09/15/22	145,149.00	1.80	1.97	1.90
SHE2873-193		US 287 & CO 52 INTERSECTION I	09/15/22	24,735.00	3.00	2.85	1.64
		WEIGHTED AVERAGE FOR THE THIRD QUARTER		630,334.00	2.88	2.42	2.59
NHPP0701-253		I-70 EAST OF DEBEQUE	10/27/22	45.00	8.00	26.80	28.00
NHPP0705-088		I-70 AGATE STRUCTURE REHAB	10/27/22	2,444.00	2.50	5.90	6.50
TRG0253-264		I-25 AND SH 119 PARK-N-RIDE	10/27/22	339,023.00	2.00	2.08	1.90
NHPP0343-048		US 34 (MP 169.3-171.4)	11/01/22	188.00	2.50	6.16	5.00
STU0252-457		I-25:ALAMEDA RIVER PH 2.0	11/03/22	456,270.00	1.70	2.14	2.00
STR064A-010		SH 64 AND SH 13 AT MEEKER	11/10/22	500.00	4.00	2.70	2.75
C5502-097		US550 MP 117.28-126.06	11/17/22	18,640.00	2.75	3.15	4.30
STAM420-001		US 285 AT HWY 9C IMPROVEMENTS	12/01/22	164,162.00	2.00	2.17	2.00
BR2854-148		INTERSECTION OF US 285 & SH 9					
STM0091-046		ADA RAMP IMPROVEMENTS - FAIRP					
STA0711-021		SH71: REGION LINE NORTH	12/01/22	14,715.00	2.00	2.76	3.00
2670703-487		I-70 BRIDGES OVER WARD ROAD-	12/01/22	547,743.00	1.50	2.11	1.80
NHPP0701-252		I-70 RIFLE TO SILT SLAB REPLA	12/01/22	787.00	4.00	8.50	13.00
IM025A-050		I25-MP103.9 - INTERSECTION DR	12/01/22	169,300.00	2.00	2.17	2.50
NHPP0063-048		US6 / 20 ROAD INTERSECTION IM	12/15/22	209.00	7.00	5.62	5.25
BR012A-048		CO 12 STRUCTURE P-17-F AT MP	12/22/22	47,519.00	3.50	2.53	3.00
STA385A-016		SH 385 MP 97.76	12/22/22	58,265.00	2.00	3.76	3.23
STR096A-050		SH 96 MP 168.99 TO 193.77	12/22/22	39.00	2.50	8.91	10.00
		WEIGHTED AVERAGE FOR THE FOURTH QUARTER		1,819,849.00	1.82	2.20	2.05
		WEIGHTED AVERAGE FOR THE YEAR		3,477,947.00	2.01	2.07	2.04
===== 602-00030 Reinf (FRP) (Surface) M Kip Foot =====							
STR109A-019		M-22-AY BRIDGE REHAB ON SH109	12/01/22	96.00	4500.00	5332.91	3956.81
		WEIGHTED AVERAGE FOR THE FOURTH QUARTER		96.00	4500.00	5332.91	3956.81
		WEIGHTED AVERAGE FOR THE YEAR		96.00	4500.00	5332.91	3956.81

COLORADO DEPARTMENT OF TRANSPORTATION
 ITEM UNIT COSTS BY PROJECTS -- 2022 COST DATA

11:31 Wednesday, March 8, 2023 302

PROJECT NUMBER	ITEM NUMBER/ PROJECT LOCATION	ITEM DESCRIPTION/ PROJECT LOCATION	DATE LET	UNIT/ QUANTITY	ENGR. EST.	AVERAGE BID	AWARDED BID
=====	602-00060	Reinf Steel Splice		Each	=====	=====	=====
ER0253-297		WCR 34 BRIDGE OVER I-25(MM 24	09/14/22	20.00	99.00	896.03	230.00
	WEIGHTED	AVERAGE FOR THE THIRD QUARTER		20.00	99.00	896.03	230.00
		WEIGHTED AVERAGE FOR THE YEAR		20.00	99.00	896.03	230.00
=====	602-00210	Welded Wire Fabric		Sq Yard	=====	=====	=====
C5502-111		US 550 MP 81 AND 89 RED MOUNT	10/27/22	41.00	50.00	213.72	200.00
	WEIGHTED	AVERAGE FOR THE FOURTH QUARTER		41.00	50.00	213.72	200.00
		WEIGHTED AVERAGE FOR THE YEAR		41.00	50.00	213.72	200.00
=====	603-00025	Culvert Lining (24 Inch) (Special)		Lin Foot	=====	=====	=====
NHPP0702-383		I-70 EB AUX FRISCO TO SILVERT	01/13/22	612.00	300.00	326.98	382.00
	WEIGHTED	AVERAGE FOR THE FIRST QUARTER		612.00	300.00	326.98	382.00
		WEIGHTED AVERAGE FOR THE YEAR		612.00	300.00	326.98	382.00
=====	603-00047	Prepare Culvert Pipe (48 In)		Lin Foot	=====	=====	=====
C0852-120		Rehabilitation of Culvert by	05/26/22	990.00	200.00	35.00	35.00
	WEIGHTED	AVERAGE FOR THE SECOND QUARTER		990.00	200.00	35.00	35.00
		WEIGHTED AVERAGE FOR THE YEAR		990.00	200.00	35.00	35.00
=====	603-00049	Culvert Lining (48 Inch) (Special)		Lin Foot	=====	=====	=====
C0852-120		Rehabilitation of Culvert by	05/26/22	990.00	500.00	485.00	485.00
	WEIGHTED	AVERAGE FOR THE SECOND QUARTER		990.00	500.00	485.00	485.00
		WEIGHTED AVERAGE FOR THE YEAR		990.00	500.00	485.00	485.00
=====	603-00054	Culvert Lining (54 In)		Lin Foot	=====	=====	=====
NHPP0701-253		I-70 EAST OF DEBEQUE	10/27/22	391.00	1000.00	1115.00	1050.00
	WEIGHTED	AVERAGE FOR THE FOURTH QUARTER		391.00	1000.00	1115.00	1050.00
		WEIGHTED AVERAGE FOR THE YEAR		391.00	1000.00	1115.00	1050.00

COLORADO DEPARTMENT OF TRANSPORTATION
ITEM UNIT COSTS BY PROJECTS -- 2022 COST DATA

11:31 Wednesday, March 8, 2023 303

PROJECT NUMBER	ITEM NUMBER/ PROJECT LOCATION	ITEM DESCRIPTION/ PROJECT LOCATION	DATE LET	UNIT/ QUANTITY	ENGR. EST.	AVERAGE BID	AWARDED BID
=====	603-00084	Culvert Lining (84 In)		Lin Foot	=====	=====	=====
NHPP0701-253		I-70 EAST OF DEBEQUE	10/27/22	415.00	200.00	343.00	335.00
		WEIGHTED AVERAGE FOR THE FOURTH QUARTER		415.00	200.00	343.00	335.00
		WEIGHTED AVERAGE FOR THE YEAR		415.00	200.00	343.00	335.00
=====	603-01125	12 In RCP (CIP)		Lin Foot	=====	=====	=====
NHPP0063-054		US 6 FROM I70-B TO 33 RD. (MP 08/18/22		481.00	150.00	77.43	67.00
		WEIGHTED AVERAGE FOR THE THIRD QUARTER		481.00	150.00	77.43	67.00
STU0252-457 NHPP0063-048		I-25:ALAMEDA RIVER PH 2.0 11/03/22 US6 / 20 ROAD INTERSECTION IM 12/15/22		138.00 163.00	125.00 150.00	202.99 106.39	230.00 128.00
		WEIGHTED AVERAGE FOR THE FOURTH QUARTER		301.00	138.54	143.90	174.76
		WEIGHTED AVERAGE FOR THE YEAR		782.00	145.59	112.37	108.48
=====	603-01155	15 In RCP (CIP)		Lin Foot	=====	=====	=====
NHPP0063-063 NHM765-007			02/24/22 03/31/22	607.00 1,034.00	225.00 97.00	201.60 197.54	305.00 234.49
		WEIGHTED AVERAGE FOR THE FIRST QUARTER		1,641.00	144.35	198.68	260.57
C5502-097 STAM420-001 BR2854-148 STM0091-046		US550 MP 117.28-126.06 11/17/22 US 285 AT HWY 9C IMPROVEMENTS 12/01/22 INTERSECTION OF US 285 & SH 9 ADA RAMP IMPROVEMENTS - FAIRP		119.00 264.00	350.00 128.50	150.79 205.76	107.00 213.77
		WEIGHTED AVERAGE FOR THE FOURTH QUARTER		383.00	197.32	191.87	180.60
		WEIGHTED AVERAGE FOR THE YEAR		2,024.00	154.37	197.00	245.44
=====	603-01180	18 In RCP		Lin Foot	=====	=====	=====
STM1151-038		SH115 MP 27 TO MP 38 04/21/22		365.00	125.00	127.50	151.64
		WEIGHTED AVERAGE FOR THE SECOND QUARTER		365.00	125.00	127.50	151.64
		WEIGHTED AVERAGE FOR THE YEAR		365.00	125.00	127.50	151.64

COLORADO DEPARTMENT OF TRANSPORTATION
ITEM UNIT COSTS BY PROJECTS -- 2022 COST DATA

11:31 Wednesday, March 8, 2023 304

PROJECT NUMBER	ITEM NUMBER/ PROJECT LOCATION	ITEM DESCRIPTION/ PROJECT LOCATION	DATE LET	UNIT/ QUANTITY	ENGR. EST.	AVERAGE BID	AWARDED BID
===== 603-01185 18 In RCP (CIP) Lin Foot =====							
NHM765-007			03/31/22	332.00	109.00	170.68	183.45
	WEIGHTED AVERAGE FOR THE FIRST QUARTER			332.00	109.00	170.68	183.45
2670703-479 FSA052A-046		I-70 BRIDGE OVER HARLAN SH52 WCR 37 INTERSECTION IMPR	05/05/22 06/09/22	283.00 149.00	160.00 200.00	211.89 138.07	189.89 74.00
	WEIGHTED AVERAGE FOR THE SECOND QUARTER			432.00	173.80	189.38	149.92
NHPP0063-054 C1211-099 2670403-065 2670703-497 SHE2873-193		US 6 FROM I70-B TO 33 RD. (MP SH 121 NORTH SGA SIGNALS US40 FLOYD HILL ROUNDABOUTS I-70 GENESEE WILDLIFE XING US 287 & CO 52 INTERSECTION I	08/18/22 08/25/22 09/15/22 09/15/22 09/15/22	244.00 16.00 874.00 80.00 13.00	200.00 140.00 200.00 130.00 140.00	109.99 290.00 159.60 156.48 300.24	120.00 230.00 158.00 151.50 267.00
	WEIGHTED AVERAGE FOR THE THIRD QUARTER			1,227.00	194.02	156.74	152.11
STU0252-457 C5502-097 STAM420-001 BR2854-148 STM0091-046 2670703-487 NHPP0063-048		I-25:ALAMEDA RIVER PH 2.0 US550 MP 117.28-126.06 US 285 AT HWY 9C IMPROVEMENTS INTERSECTION OF US 285 & SH 9 ADA RAMP IMPROVEMENTS - FAIRP I-70 BRIDGES OVER WARD ROAD- US6 / 20 ROAD INTERSECTION IM	11/03/22 11/17/22 12/01/22 12/01/22 12/15/22	489.00 733.00 3,155.00 114.00 83.00	135.00 200.00 135.00 300.00 200.00	253.73 171.24 160.10 231.12 132.85	310.00 117.00 125.00 230.00 162.00
	WEIGHTED AVERAGE FOR THE FOURTH QUARTER			4,574.00	150.71	162.45	149.22
	WEIGHTED AVERAGE FOR THE YEAR			6,565.00	158.21	164.29	151.22
===== 603-01240 24 In RCP Lin Foot =====							
STM1151-038		SH115 MP 27 TO MP 38	04/21/22	457.00	100.00	212.02	265.04
	WEIGHTED AVERAGE FOR THE SECOND QUARTER			457.00	100.00	212.02	265.04
STA0361-129		US 36: HYGIENE RD AND NELSON	12/22/22	140.00	210.00	244.87	215.22
	WEIGHTED AVERAGE FOR THE FOURTH QUARTER			140.00	210.00	244.87	215.22
	WEIGHTED AVERAGE FOR THE YEAR			597.00	125.80	219.72	253.36

COLORADO DEPARTMENT OF TRANSPORTATION
ITEM UNIT COSTS BY PROJECTS -- 2022 COST DATA

11:31 Wednesday, March 8, 2023 305

PROJECT NUMBER	ITEM NUMBER/ PROJECT LOCATION	ITEM DESCRIPTION/ PROJECT LOCATION	DATE LET	UNIT/ QUANTITY	ENGR. EST.	AVERAGE BID	AWARDED BID
===== 603-01245 24 In RCP (CIP) Lin Foot =====							
NHM765-007			03/31/22	828.00	125.00	196.68	203.55
		WEIGHTED AVERAGE FOR THE FIRST QUARTER		828.00	125.00	196.68	203.55
2670703-479		I-70 BRIDGE OVER HARLAN	05/05/22	32.00	170.00	306.39	250.75
		WEIGHTED AVERAGE FOR THE SECOND QUARTER		32.00	170.00	306.39	250.75
NHPP0063-054		US 6 FROM I70-B TO 33 RD. (MP	08/18/22	1,464.00	275.00	155.68	135.00
2670403-065		US40 FLOYD HILL ROUNDABOUTS	09/15/22	69.00	210.00	260.08	192.00
SHE2873-193		US 287 & CO 52 INTERSECTION I	09/15/22	1,087.00	160.00	173.16	168.00
		WEIGHTED AVERAGE FOR THE THIRD QUARTER		2,620.00	225.58	169.73	150.19
TRG0253-264		I-25 AND SH 119 PARK-N-RIDE	10/27/22	20.00	150.00	289.33	150.00
STA3852-015		US 385 HOLYOKE NORTH	10/27/22	92.00	150.00	130.00	130.00
STU0252-457		I-25:ALAMEDA RIVER PH 2.0	11/03/22	192.00	175.00	237.51	267.00
C5502-097		US550 MP 117.28-126.06	11/17/22	403.00	250.00	185.83	137.00
STAM420-001		US 285 AT HWY 9C IMPROVEMENTS	12/01/22	746.00	170.00	230.37	219.82
BR2854-148		INTERSECTION OF US 285 & SH 9					
STM0091-046		ADA RAMP IMPROVEMENTS - FAIRP					
NHPP0063-048		US6 / 20 ROAD INTERSECTION IM	12/15/22	7.00	400.00	298.29	590.00
NHPP0502-090		SH 50 MP 134.6-136 GUNNISON C	12/22/22	52.00	200.00	421.19	507.16
		WEIGHTED AVERAGE FOR THE FOURTH QUARTER		1,512.00	192.57	237.77	221.91
		WEIGHTED AVERAGE FOR THE YEAR		4,992.00	198.54	197.76	183.35
===== 603-01305 30 In RCP (CIP) Lin Foot =====							
NHPP0063-054		US 6 FROM I70-B TO 33 RD. (MP	08/18/22	424.00	300.00	146.59	160.00
		WEIGHTED AVERAGE FOR THE THIRD QUARTER		424.00	300.00	146.59	160.00
STA3852-015		US 385 HOLYOKE NORTH	10/27/22	41.00	250.00	180.00	180.00

COLORADO DEPARTMENT OF TRANSPORTATION
ITEM UNIT COSTS BY PROJECTS -- 2022 COST DATA

11:31 Wednesday, March 8, 2023 306

PROJECT NUMBER	ITEM NUMBER/ PROJECT LOCATION	ITEM DESCRIPTION/ PROJECT LOCATION	DATE LET	UNIT/ QUANTITY	ENGR. EST.	AVERAGE BID	AWARDED BID
=====	603-01305	30 In RCP (CIP)		Lin Foot	=====	=====	=====
STAM420-001		US 285 AT HWY 9C IMPROVEMENTS	12/01/22	369.00	235.00	273.41	252.42
BR2854-148		INTERSECTION OF US 285 & SH 9					
STM0091-046		ADA RAMP IMPROVEMENTS - FAIRP					
	WEIGHTED AVERAGE FOR THE FOURTH QUARTER			410.00	236.50	270.88	245.18
	WEIGHTED AVERAGE FOR THE YEAR			834.00	268.78	226.32	201.87
=====	603-01365	36 In RCP (CIP)		Lin Foot	=====	=====	=====
FSA052A-057		SH52 BOX CULVERT EXTENSION (M	08/04/22	24.00	350.00	621.80	347.32
NHPP0063-054		US 6 FROM I70-B TO 33 RD. (MP	08/18/22	1,507.00	325.00	287.73	250.00
2670403-065		US40 FLOYD HILL ROUNDABOUTS	09/15/22	379.00	250.00	297.17	260.00
SHE2873-193		US 287 & CO 52 INTERSECTION I	09/15/22	284.00	600.00	242.89	212.00
	WEIGHTED AVERAGE FOR THE THIRD QUARTER			2,194.00	347.91	280.70	247.87
STA3852-015		US 385 HOLYOKE NORTH	10/27/22	35.00	400.00	230.00	230.00
C5502-097		US550 MP 117.28-126.06	11/17/22	42.00	400.00	352.52	231.00
STAM420-001		US 285 AT HWY 9C IMPROVEMENTS	12/01/22	529.00	228.00	305.60	266.87
BR2854-148		INTERSECTION OF US 285 & SH 9					
STM0091-046		ADA RAMP IMPROVEMENTS - FAIRP					
NHPP0063-048		US6 / 20 ROAD INTERSECTION IM	12/15/22	27.00	420.00	257.03	303.00
	WEIGHTED AVERAGE FOR THE FOURTH QUARTER			633.00	257.11	304.77	263.99
	WEIGHTED AVERAGE FOR THE YEAR			2,827.00	327.58	287.61	251.48
=====	603-01420	42 In RCP		Lin Foot	=====	=====	=====
STM1151-038		SH115 MP 27 TO MP 38	04/21/22	51.00	240.00	314.29	396.15
	WEIGHTED AVERAGE FOR THE SECOND QUARTER			51.00	240.00	314.29	396.15
	WEIGHTED AVERAGE FOR THE YEAR			51.00	240.00	314.29	396.15
=====	603-01425	42 In RCP (CIP)		Lin Foot	=====	=====	=====
NHPP0063-054		US 6 FROM I70-B TO 33 RD. (MP	08/18/22	258.00	350.00	516.17	445.00

COLORADO DEPARTMENT OF TRANSPORTATION
ITEM UNIT COSTS BY PROJECTS -- 2022 COST DATA

11:31 Wednesday, March 8, 2023 307

PROJECT NUMBER	ITEM NUMBER/ PROJECT LOCATION	ITEM DESCRIPTION/ PROJECT LOCATION	DATE LET	UNIT/ QUANTITY	ENGR. EST.	AVERAGE BID	AWARDED BID
=====	603-01425	42 In RCP (CIP)		Lin Foot	=====	=====	=====
2670403-065		US40_FLOYD HILL ROUNDABOUTS	09/15/22	480.00	300.00	390.75	348.00
		WEIGHTED AVERAGE FOR THE THIRD QUARTER		738.00	317.48	423.83	381.91
STAM420-001		US 285 AT HWY 9C IMPROVEMENTS	12/01/22	473.00	295.00	393.27	375.73
BR2854-148		INTERSECTION OF US 285 & SH 9					
STM0091-046		ADA RAMP IMPROVEMENTS - FAIRP		21.00	400.00	344.94	382.00
NHPP0063-048		US6 / 20 ROAD INTERSECTION IM	12/15/22				
		WEIGHTED AVERAGE FOR THE FOURTH QUARTER		494.00	299.46	391.22	376.00
		WEIGHTED AVERAGE FOR THE YEAR		1,232.00	310.26	407.44	379.54
=====	603-01485	48 In RCP (CIP)		Lin Foot	=====	=====	=====
STAM420-001		US 285 AT HWY 9C IMPROVEMENTS	12/01/22	120.00	375.00	524.93	462.11
BR2854-148		INTERSECTION OF US 285 & SH 9					
STM0091-046		ADA RAMP IMPROVEMENTS - FAIRP		22.00	450.00	380.34	402.00
NHPP0063-048		US6 / 20 ROAD INTERSECTION IM	12/15/22				
		WEIGHTED AVERAGE FOR THE FOURTH QUARTER		142.00	386.62	502.53	452.80
		WEIGHTED AVERAGE FOR THE YEAR		142.00	386.62	502.53	452.80
=====	603-01545	54 In RCP (CIP)		Lin Foot	=====	=====	=====
STA3852-015		US 385 HOLYOKE NORTH	10/27/22	32.00	750.00	420.00	420.00
STAM420-001		US 285 AT HWY 9C IMPROVEMENTS	12/01/22	980.00	500.00	607.13	450.00
BR2854-148		INTERSECTION OF US 285 & SH 9					
STM0091-046		ADA RAMP IMPROVEMENTS - FAIRP					
		WEIGHTED AVERAGE FOR THE FOURTH QUARTER		1,012.00	507.91	605.61	449.05
		WEIGHTED AVERAGE FOR THE YEAR		1,012.00	507.91	605.61	449.05
=====	603-01785	78 In RCP (CIP)		Lin Foot	=====	=====	=====
ER0502-092		US 50 MP 204 EB MONARCH TRUCK	08/29/22	136.00	500.00	573.44	750.31
		WEIGHTED AVERAGE FOR THE THIRD QUARTER		136.00	500.00	573.44	750.31
		WEIGHTED AVERAGE FOR THE YEAR		136.00	500.00	573.44	750.31

COLORADO DEPARTMENT OF TRANSPORTATION
 ITEM UNIT COSTS BY PROJECTS -- 2022 COST DATA

11:31 Wednesday, March 8, 2023 308

PROJECT NUMBER	ITEM NUMBER/ PROJECT LOCATION	ITEM DESCRIPTION/ PROJECT LOCATION	DATE LET	UNIT/ QUANTITY	ENGR. EST.	AVERAGE BID	AWARDED BID
=====	603-02185	23x14 In RCP (CIP)		Lin Foot	=====		
NHM765-007			03/31/22	368.00	140.00	200.93	209.70
		WEIGHTED AVERAGE FOR THE FIRST QUARTER		368.00	140.00	200.93	209.70
NHPP0063-054		US 6 FROM I70-B TO 33 RD. (MP 08/18/22)		61.00	200.00	302.18	260.00
		WEIGHTED AVERAGE FOR THE THIRD QUARTER		61.00	200.00	302.18	260.00
C5502-097		US550 MP 117.28-126.06	11/17/22	34.00	300.00	212.20	184.00
STA385A-016		SH 385 MP 97.76	12/22/22	64.00	300.00	276.25	250.00
		WEIGHTED AVERAGE FOR THE FOURTH QUARTER		98.00	300.00	258.00	227.10
		WEIGHTED AVERAGE FOR THE YEAR		527.00	176.70	221.62	218.76
=====	603-02240	30x19 In RCP		Lin Foot	=====		
STA0712-019		SH 71: Frieight Improvements	05/12/22	66.00	250.00	328.75	328.75
		WEIGHTED AVERAGE FOR THE SECOND QUARTER		66.00	250.00	328.75	328.75
		WEIGHTED AVERAGE FOR THE YEAR		66.00	250.00	328.75	328.75
=====	603-02245	30x19 In RCP (CIP)		Lin Foot	=====		
NHM765-007			03/31/22	18.00	145.00	356.00	350.61
		WEIGHTED AVERAGE FOR THE FIRST QUARTER		18.00	145.00	356.00	350.61
FSA052A-046		SH52 WCR 37 INTERSECTION IMPR	06/09/22	305.00	180.00	246.49	170.00
		WEIGHTED AVERAGE FOR THE SECOND QUARTER		305.00	180.00	246.49	170.00
STA385A-016		SH 385 MP 97.76	12/22/22	80.00	350.00	326.88	312.50
		WEIGHTED AVERAGE FOR THE FOURTH QUARTER		80.00	350.00	326.88	312.50
		WEIGHTED AVERAGE FOR THE YEAR		403.00	212.18	263.15	206.35

COLORADO DEPARTMENT OF TRANSPORTATION
ITEM UNIT COSTS BY PROJECTS -- 2022 COST DATA

11:31 Wednesday, March 8, 2023 309

PROJECT NUMBER	ITEM NUMBER/ PROJECT LOCATION	ITEM DESCRIPTION/ PROJECT LOCATION	DATE LET	UNIT/ QUANTITY	ENGR. EST.	AVERAGE BID	AWARDED BID
=====	603-02270	34x22 In RCP		Lin Foot	=====		
NHM765-007			03/31/22	310.00	150.00	289.31	277.12
		WEIGHTED AVERAGE FOR THE FIRST QUARTER		310.00	150.00	289.31	277.12
		WEIGHTED AVERAGE FOR THE YEAR		310.00	150.00	289.31	277.12
=====	603-02305	38x24 In RCP (CIP)		Lin Foot	=====		
NHM765-007			03/31/22	82.00	186.00	290.92	283.06
		WEIGHTED AVERAGE FOR THE FIRST QUARTER		82.00	186.00	290.92	283.06
C5502-097		US550 MP 117.28-126.06	11/17/22	164.00	320.00	254.71	214.00
		WEIGHTED AVERAGE FOR THE FOURTH QUARTER		164.00	320.00	254.71	214.00
		WEIGHTED AVERAGE FOR THE YEAR		246.00	275.33	266.78	237.02
=====	603-02365	45x29 In RCP (CIP)		Lin Foot	=====		
NHPP0063-054		US 6 FROM I70-B TO 33 RD. (MP 08/18/22		152.00	350.00	659.12	570.00
		WEIGHTED AVERAGE FOR THE THIRD QUARTER		152.00	350.00	659.12	570.00
C5502-097		US550 MP 117.28-126.06	11/17/22	19.00	400.00	350.24	324.00
		WEIGHTED AVERAGE FOR THE FOURTH QUARTER		19.00	400.00	350.24	324.00
		WEIGHTED AVERAGE FOR THE YEAR		171.00	355.56	610.35	542.67
=====	603-02485	60x38 In. RCP (CIP)		Lin Foot	=====		
STA385A-016		SH 385 MP 97.76	12/22/22	60.00	400.00	600.00	750.00
		WEIGHTED AVERAGE FOR THE FOURTH QUARTER		60.00	400.00	600.00	750.00
		WEIGHTED AVERAGE FOR THE YEAR		60.00	400.00	600.00	750.00

COLORADO DEPARTMENT OF TRANSPORTATION
ITEM UNIT COSTS BY PROJECTS -- 2022 COST DATA

11:31 Wednesday, March 8, 2023 310

PROJECT NUMBER	ITEM NUMBER/ PROJECT LOCATION	ITEM DESCRIPTION/ PROJECT LOCATION	DATE LET	UNIT/ QUANTITY	ENGR. EST.	AVERAGE BID	AWARDED BID
=====	603-05012	12 In RCES		Each	=====	=====	=====
NHPP0063-054		US 6 FROM I70-B TO 33 RD. (MP 08/18/22		3.00	1200.00	1098.54	950.00
		WEIGHTED AVERAGE FOR THE THIRD QUARTER		3.00	1200.00	1098.54	950.00
		WEIGHTED AVERAGE FOR THE YEAR		3.00	1200.00	1098.54	950.00
=====	603-05015	15 In RCES		Each	=====	=====	=====
C5502-097		US550 MP 117.28-126.06	11/17/22	1.00	4000.00	1565.58	859.00
		WEIGHTED AVERAGE FOR THE FOURTH QUARTER		1.00	4000.00	1565.58	859.00
		WEIGHTED AVERAGE FOR THE YEAR		1.00	4000.00	1565.58	859.00
=====	603-05018	18 In RCES		Each	=====	=====	=====
NHPP 0761-238 C0761-239		I-76 DAHLIA TO YORK	03/10/22	2.00	1400.00	1620.34	1900.00
		WEIGHTED AVERAGE FOR THE FIRST QUARTER		2.00	1400.00	1620.34	1900.00
STM1151-038		SH115 MP 27 TO MP 38	04/21/22	2.00	1600.00	2043.02	2269.98
2670703-479		I-70 BRIDGE OVER HARLAN	05/05/22	1.00	1500.00	2072.74	2197.49
FSA052A-046		SH52 WCR 37 INTERSECTION IMPR	06/09/22	6.00	1000.00	1782.50	1470.00
		WEIGHTED AVERAGE FOR THE SECOND QUARTER		9.00	1188.89	1876.99	1728.61
NHPP0702-414		VAIL PASS AUX PHASE 1 CAP 3	07/08/22	5.00	1774.82	1774.82	1774.82
FBR0702-423		VAIL PASS AUX BE F-12-AT PHAS					
C1211-099		SH 121 NORTH SGA SIGNALS	08/25/22	2.00	2100.00	2135.00	1770.00
2670403-065		US40_FLOYD HILL ROUNDABOUTS	09/15/22	2.00	2000.00	2773.59	3070.00
2670703-497		I-70_GENESEE WILDLIFE XING	09/15/22	1.00	1800.00	2606.33	1698.73
SHE2873-193		US 287 & CO 52 INTERSECTION I	09/15/22	2.00	1000.00	2915.96	2438.00
		WEIGHTED AVERAGE FOR THE THIRD QUARTER		12.00	1739.51	2567.40	2094.07
C5502-097		US550 MP 117.28-126.06	11/17/22	29.00	1800.00	1696.21	1100.00

COLORADO DEPARTMENT OF TRANSPORTATION
 ITEM UNIT COSTS BY PROJECTS -- 2022 COST DATA

11:31 Wednesday, March 8, 2023 311

PROJECT NUMBER	ITEM NUMBER/ PROJECT LOCATION	ITEM DESCRIPTION/ PROJECT LOCATION	DATE LET	UNIT/ QUANTITY	ENGR. EST.	AVERAGE BID	AWARDED BID
=====	603-05018	18 In RCES		Each =====			
STAM420-001		US 285 AT HWY 9C IMPROVEMENTS	12/01/22	1.00	1600.00	2618.61	3338.78
BR2854-148		INTERSECTION OF US 285 & SH 9					
STM0091-046		ADA RAMP IMPROVEMENTS - FAIRP					
2670703-487		I-70 BRIDGES OVER WARD ROAD-	12/01/22	1.00	2500.00	2220.40	2420.00
NHPP0063-048		US6 / 20 ROAD INTERSECTION IM	12/15/22	2.00	3000.00	2261.45	1400.00
		WEIGHTED AVERAGE FOR THE FOURTH QUARTER		33.00	1887.88	1800.37	1226.02
		WEIGHTED AVERAGE FOR THE YEAR		56.00	1726.32	1933.99	1516.88
=====	603-05024	24 In RCES		Each =====			
NHPP0702-383		I-70 EB AUX FRISCO TO SILVERT	01/13/22	2.00	1700.00	4510.18	2500.00
NHPP 0761-238		I-76 DAHLIA TO YORK	03/10/22	2.00	1600.00	1948.63	2100.00
C0761-239							
		WEIGHTED AVERAGE FOR THE FIRST QUARTER		4.00	1650.00	2933.84	2300.00
STM1151-038		SH115 MP 27 TO MP 38	04/21/22	17.00	1500.00	2246.16	2481.15
		WEIGHTED AVERAGE FOR THE SECOND QUARTER		17.00	1500.00	2246.16	2481.15
NHPP0702-414		VAIL PASS AUX PHASE 1 CAP 3	07/08/22	2.00	1988.82	1988.82	1988.82
FBR0702-423		VAIL PASS AUX BE F-12-AT PHAS					
NHPP0063-054		US 6 FROM I70-B TO 33 RD. (MP	08/18/22	2.00	1600.00	1840.94	1590.00
2670403-065		US40 FLOYD HILL ROUNDABOUTS	09/15/22	1.00	2500.00	2985.35	3240.00
SHE2873-193		US 287 & CO 52 INTERSECTION I	09/15/22	2.00	1600.00	3529.10	2650.00
		WEIGHTED AVERAGE FOR THE THIRD QUARTER		7.00	1839.66	2983.17	2242.52
STA3852-015		US 385 HOLYOKE NORTH	10/27/22	9.00	2500.00	2600.00	2600.00
SHE0242-087		US 24 SAFETY IMPRVMENTS, E OF	11/03/22	1.00	2000.00	3092.92	3278.77
C5502-097		US550 MP 117.28-126.06	11/17/22	9.00	2000.00	1941.43	1360.00
STAM420-001		US 285 AT HWY 9C IMPROVEMENTS	12/01/22	6.00	1700.00	2749.19	3564.22
BR2854-148		INTERSECTION OF US 285 & SH 9					
STM0091-046		ADA RAMP IMPROVEMENTS - FAIRP					
NHPP0063-048		US6 / 20 ROAD INTERSECTION IM	12/15/22	1.00	3500.00	2547.80	1640.00

COLORADO DEPARTMENT OF TRANSPORTATION
ITEM UNIT COSTS BY PROJECTS -- 2022 COST DATA

11:31 Wednesday, March 8, 2023 312

PROJECT NUMBER	ITEM NUMBER/ PROJECT LOCATION	ITEM DESCRIPTION/ PROJECT LOCATION	DATE LET	UNIT/ QUANTITY	ENGR. EST.	AVERAGE BID	AWARDED BID
=====	603-05024	24 In RCES		Each =====			
NHPP0502-090		SH 50 MP 134.6-136 GUNNISON C	12/22/22	2.00	2500.00	3304.58	5761.85
		WEIGHTED AVERAGE FOR THE FOURTH QUARTER		28.00	2185.71	2557.56	2619.58
		WEIGHTED AVERAGE FOR THE YEAR		56.00	1896.03	2521.19	2509.56
=====	603-05030	30 In RCES		Each =====			
NHPP0702-414		VAIL PASS AUX PHASE 1 CAP 3	07/08/22	1.00	2416.82	2416.82	2416.82
FBR0702-423		VAIL PASS AUX BE F-12-AT PHAS					
		WEIGHTED AVERAGE FOR THE THIRD QUARTER		1.00	2416.82	2416.82	2416.82
STA3852-015		US 385 HOLYOKE NORTH	10/27/22	4.00	3000.00	3000.00	3000.00
		WEIGHTED AVERAGE FOR THE FOURTH QUARTER		4.00	3000.00	3000.00	3000.00
		WEIGHTED AVERAGE FOR THE YEAR		5.00	2883.36	2883.36	2883.36
=====	603-05036	36 In RCES		Each =====			
STA3852-015		US 385 HOLYOKE NORTH	10/27/22	4.00	3800.00	3600.00	3600.00
C5502-097		US550 MP 117.28-126.06	11/17/22	1.00	2600.00	2892.85	2350.00
NHPP0063-048		US6 / 20 ROAD INTERSECTION IM	12/15/22	1.00	2500.00	3795.18	2964.00
		WEIGHTED AVERAGE FOR THE FOURTH QUARTER		6.00	3383.33	3478.12	3285.67
		WEIGHTED AVERAGE FOR THE YEAR		6.00	3383.33	3478.12	3285.67
=====	603-05042	42 In RCES		Each =====			
STM1151-038		SH115 MP 27 TO MP 38	04/21/22	1.00	2700.00	3342.19	3674.15
		WEIGHTED AVERAGE FOR THE SECOND QUARTER		1.00	2700.00	3342.19	3674.15
NHPP0063-054		US 6 FROM I70-B TO 33 RD. (MP	08/18/22	1.00	3000.00	3614.95	3125.00

COLORADO DEPARTMENT OF TRANSPORTATION
 ITEM UNIT COSTS BY PROJECTS -- 2022 COST DATA

11:31 Wednesday, March 8, 2023 313

PROJECT NUMBER	ITEM NUMBER/ PROJECT LOCATION	ITEM DESCRIPTION/ PROJECT LOCATION	DATE LET	UNIT/ QUANTITY	ENGR. EST.	AVERAGE BID	AWARDED BID
===== 603-05042	42 In RCES			Each =====			
2670403-065	US40_FLOYD HILL ROUNDABOUTS		09/15/22	1.00	3200.00	4274.16	4580.00
	WEIGHTED AVERAGE FOR THE THIRD QUARTER			2.00	3100.00	4010.48	3852.50
	WEIGHTED AVERAGE FOR THE YEAR			3.00	2966.67	3676.33	3793.05
===== 603-05048	48 In RCES			Each =====			
STA3852-015	US 385 HOLYOKE NORTH		10/27/22	2.00	4000.00	4100.00	4100.00
	WEIGHTED AVERAGE FOR THE FOURTH QUARTER			2.00	4000.00	4100.00	4100.00
	WEIGHTED AVERAGE FOR THE YEAR			2.00	4000.00	4100.00	4100.00
===== 603-05054	54 In RCES			Each =====			
STA3852-015	US 385 HOLYOKE NORTH		10/27/22	2.00	4500.00	4900.00	4900.00
	WEIGHTED AVERAGE FOR THE FOURTH QUARTER			2.00	4500.00	4900.00	4900.00
	WEIGHTED AVERAGE FOR THE YEAR			2.00	4500.00	4900.00	4900.00
===== 603-05118	23x14 In RCES			Each =====			
NHPP 0761-238 C0761-239	I-76 DAHLIA TO YORK		03/10/22	1.00	4000.00	2463.90	2250.00
	WEIGHTED AVERAGE FOR THE FIRST QUARTER			1.00	4000.00	2463.90	2250.00
C5502-097	US550 MP 117.28-126.06		11/17/22	1.00	4000.00	2390.42	1820.00
	WEIGHTED AVERAGE FOR THE FOURTH QUARTER			1.00	4000.00	2390.42	1820.00
	WEIGHTED AVERAGE FOR THE YEAR			2.00	4000.00	2443.86	2035.00
===== 603-05124	30x19 In RCES			Each =====			
STA0712-019	SH 71: Frieght Improvements		05/12/22	2.00	3000.00	5174.75	5174.75

COLORADO DEPARTMENT OF TRANSPORTATION
ITEM UNIT COSTS BY PROJECTS -- 2022 COST DATA

11:31 Wednesday, March 8, 2023 314

PROJECT NUMBER	ITEM NUMBER/ PROJECT LOCATION	ITEM DESCRIPTION/ PROJECT LOCATION	DATE LET	UNIT/ QUANTITY	ENGR. EST.	AVERAGE BID	AWARDED BID
=====	603-05124	30x19 In RCES		Each =====			
FSA052A-046		SH52 WCR 37 INTERSECTION IMPR	06/09/22	10.00	1500.00	2406.19	2050.00
	WEIGHTED AVERAGE FOR THE SECOND QUARTER			12.00	1750.00	2512.67	2570.79
	WEIGHTED AVERAGE FOR THE YEAR			12.00	1750.00	2512.67	2570.79
=====	603-05130	38x24 In RCES		Each =====			
C5502-097		US550 MP 117.28-126.06	11/17/22	1.00	5000.00	3479.83	2850.00
	WEIGHTED AVERAGE FOR THE FOURTH QUARTER			1.00	5000.00	3479.83	2850.00
	WEIGHTED AVERAGE FOR THE YEAR			1.00	5000.00	3479.83	2850.00
=====	603-05136	45x29 In RCES		Each =====			
C5502-097		US550 MP 117.28-126.06	11/17/22	2.00	7000.00	4221.84	3730.00
	WEIGHTED AVERAGE FOR THE FOURTH QUARTER			2.00	7000.00	4221.84	3730.00
	WEIGHTED AVERAGE FOR THE YEAR			2.00	7000.00	4221.84	3730.00
=====	603-10060	6 In CSP		Lin Foot =====			
NHPP0702-383		I-70 EB AUX FRISCO TO SILVERT	01/13/22	20.00	150.00	192.41	220.00
	WEIGHTED AVERAGE FOR THE FIRST QUARTER			20.00	150.00	192.41	220.00
	WEIGHTED AVERAGE FOR THE YEAR			20.00	150.00	192.41	220.00
=====	603-10120	12 In CSP		Lin Foot =====			
NHM765-007			03/31/22	60.00	200.00	122.96	57.75
	WEIGHTED AVERAGE FOR THE FIRST QUARTER			60.00	200.00	122.96	57.75
STM1151-038		SH115 MP 27 TO MP 38	04/21/22	24.00	95.00	139.71	177.64
	WEIGHTED AVERAGE FOR THE SECOND QUARTER			24.00	95.00	139.71	177.64
	WEIGHTED AVERAGE FOR THE YEAR			84.00	170.00	129.66	92.00

COLORADO DEPARTMENT OF TRANSPORTATION
 ITEM UNIT COSTS BY PROJECTS -- 2022 COST DATA

11:31 Wednesday, March 8, 2023 315

PROJECT NUMBER	ITEM NUMBER/ PROJECT LOCATION	ITEM DESCRIPTION/ PROJECT LOCATION	DATE LET	UNIT/ QUANTITY	ENGR. EST.	AVERAGE BID	AWARDED BID
=====	603-10150	15 In CSP		Lin Foot	=====		
STM1151-038		SH115 MP 27 TO MP 38	04/21/22	96.00	105.00	153.76	178.50
		WEIGHTED AVERAGE FOR THE SECOND QUARTER		96.00	105.00	153.76	178.50
2670703-487		I-70 BRIDGES OVER WARD ROAD-	12/01/22	112.00	500.00	154.06	120.00
STR096A-050		SH 96 MP 168.99 TO 193.77	12/22/22	104.00	190.00	124.33	100.00
		WEIGHTED AVERAGE FOR THE FOURTH QUARTER		216.00	350.74	143.42	110.37
		WEIGHTED AVERAGE FOR THE YEAR		312.00	275.13	147.09	131.33
=====	603-10180	18 In CSP		Lin Foot	=====		
NHPP1601-083			02/03/22	40.00	125.00	235.03	130.00
		WEIGHTED AVERAGE FOR THE FIRST QUARTER		40.00	125.00	235.03	130.00
STM1151-038		SH115 MP 27 TO MP 38	04/21/22	866.00	135.00	141.34	190.98
STA0712-019		SH 71: Frieght Improvements	05/12/22	48.00	80.00	137.13	137.13
NHC540-017		R2 CHAINUP STA @ KENOSHA/HOOS	05/12/22	30.00	160.00	175.00	125.00
		WEIGHTED AVERAGE FOR THE SECOND QUARTER		944.00	133.00	141.98	186.15
SHE2873-193		US 287 & CO 52 INTERSECTION I	09/15/22	38.00	120.00	140.88	157.00
		WEIGHTED AVERAGE FOR THE THIRD QUARTER		38.00	120.00	140.88	157.00
STA3852-015		US 385 HOLYOKE NORTH	10/27/22	26.00	125.00	115.00	115.00
		WEIGHTED AVERAGE FOR THE FOURTH QUARTER		26.00	125.00	115.00	115.00
		WEIGHTED AVERAGE FOR THE YEAR		1,048.00	132.02	143.33	181.18

COLORADO DEPARTMENT OF TRANSPORTATION
ITEM UNIT COSTS BY PROJECTS -- 2022 COST DATA

11:31 Wednesday, March 8, 2023 316

PROJECT NUMBER	ITEM NUMBER/ PROJECT LOCATION	ITEM DESCRIPTION/ PROJECT LOCATION	DATE LET	UNIT/ QUANTITY	ENGR. EST.	AVERAGE BID	AWARDED BID
===== 603-10240 24 In CSP Lin Foot =====							
NHPP0702-383		I-70 EB AUX FRISCO TO SILVERT	01/13/22	141.00	150.00	217.04	350.00
NHPP1601-083			02/03/22	304.00	150.00	333.89	280.00
		WEIGHTED AVERAGE FOR THE FIRST QUARTER		445.00	150.00	271.15	302.18
STM1151-038		SH115 MP 27 TO MP 38	04/21/22	152.00	150.00	238.03	406.71
NHC540-017		R2 CHAINUP STA @ KENOSHA/HOOS	05/12/22	150.00	180.00	203.33	140.00
NHPP 3851-018		US 385 NORTH OF CHEYENNE WELL	05/26/22	18.00	140.00	202.50	300.00
		WEIGHTED AVERAGE FOR THE SECOND QUARTER		320.00	163.50	224.47	275.69
SHE2873-193		US 287 & CO 52 INTERSECTION I	09/15/22	7.00	150.00	293.96	345.00
		WEIGHTED AVERAGE FOR THE THIRD QUARTER		7.00	150.00	293.96	345.00
NHPP0502-090		SH 50 MP 134.6-136 GUNNISON C	12/22/22	18.00	350.00	441.71	453.22
STA0361-129		US 36: HYGIENE RD AND NELSON	12/22/22	7.00	300.00	349.33	339.82
BR012A-048		CO 12 STRUCTURE P-17-F AT MP	12/22/22	135.00	350.00	137.40	200.00
		WEIGHTED AVERAGE FOR THE FOURTH QUARTER		160.00	347.81	225.52	234.60
		WEIGHTED AVERAGE FOR THE YEAR		932.00	188.59	246.04	281.80
===== 603-10300 30 In CSP Lin Foot =====							
NHPP1601-083			02/03/22	60.00	150.00	342.41	300.00
		WEIGHTED AVERAGE FOR THE FIRST QUARTER		60.00	150.00	342.41	300.00
NHPP0502-090		SH 50 MP 134.6-136 GUNNISON C	12/22/22	23.00	300.00	437.46	412.61
		WEIGHTED AVERAGE FOR THE FOURTH QUARTER		23.00	300.00	437.46	412.61
		WEIGHTED AVERAGE FOR THE YEAR		83.00	191.57	388.93	331.21

COLORADO DEPARTMENT OF TRANSPORTATION
ITEM UNIT COSTS BY PROJECTS -- 2022 COST DATA

11:31 Wednesday, March 8, 2023 317

PROJECT NUMBER	ITEM NUMBER/ PROJECT LOCATION	ITEM DESCRIPTION/ PROJECT LOCATION	DATE LET	UNIT/ QUANTITY	ENGR. EST.	AVERAGE BID	AWARDED BID
===== 603-10360 36 In CSP Lin Foot =====							
NHPP1601-083			02/03/22	112.00	200.00	393.63	350.00
		WEIGHTED AVERAGE FOR THE FIRST QUARTER		112.00	200.00	393.63	350.00
STM1151-038		SH115 MP 27 TO MP 38	04/21/22	30.00	200.00	257.78	308.89
		WEIGHTED AVERAGE FOR THE SECOND QUARTER		30.00	200.00	257.78	308.89
STA3852-015		US 385 HOLYOKE NORTH	10/27/22	8.00	300.00	375.00	375.00
STR096A-050		SH 96 MP 168.99 TO 193.77	12/22/22	136.00	240.00	181.67	150.00
		WEIGHTED AVERAGE FOR THE FOURTH QUARTER		144.00	243.33	185.38	162.50
		WEIGHTED AVERAGE FOR THE YEAR		286.00	221.82	258.18	251.28
===== 603-10420 42 In CSP Lin Foot =====							
NHPP1601-083			02/03/22	32.00	200.00	487.76	500.00
		WEIGHTED AVERAGE FOR THE FIRST QUARTER		32.00	200.00	487.76	500.00
STM1151-038		SH115 MP 27 TO MP 38	04/21/22	15.00	250.00	386.61	571.64
		WEIGHTED AVERAGE FOR THE SECOND QUARTER		15.00	250.00	386.61	571.64
		WEIGHTED AVERAGE FOR THE YEAR		47.00	215.96	433.18	522.86
===== 603-10480 48 In CSP Lin Foot =====							
NHPP0702-413		VAIL PASS AUX PHASE 1 CAP 2	04/18/22	70.00	434.44	434.44	434.44
		WEIGHTED AVERAGE FOR THE SECOND QUARTER		70.00	434.44	434.44	434.44
NHPP0502-090		SH 50 MP 134.6-136 GUNNISON C	12/22/22	20.00	400.00	575.73	623.08
		WEIGHTED AVERAGE FOR THE FOURTH QUARTER		20.00	400.00	575.73	623.08
		WEIGHTED AVERAGE FOR THE YEAR		90.00	426.79	517.55	476.36

COLORADO DEPARTMENT OF TRANSPORTATION
ITEM UNIT COSTS BY PROJECTS -- 2022 COST DATA

11:31 Wednesday, March 8, 2023 318

PROJECT NUMBER	ITEM NUMBER/ PROJECT LOCATION	ITEM DESCRIPTION/ PROJECT LOCATION	DATE LET	UNIT/ QUANTITY	ENGR. EST.	AVERAGE BID	AWARDED BID
=====	603-10720	72 In CSP		Lin Foot	=====		
NHPP0502-090		SH 50 MP 134.6-136 GUNNISON C	12/22/22	79.00	600.00	676.95	790.56
		WEIGHTED AVERAGE FOR THE FOURTH QUARTER		79.00	600.00	676.95	790.56
		WEIGHTED AVERAGE FOR THE YEAR		79.00	600.00	676.95	790.56
=====	603-15036	36 In Equiv CSP		Lin Foot	=====		
STA3852-015		US 385 HOLYOKE NORTH	10/27/22	20.00	200.00	190.00	190.00
		WEIGHTED AVERAGE FOR THE FOURTH QUARTER		20.00	200.00	190.00	190.00
		WEIGHTED AVERAGE FOR THE YEAR		20.00	200.00	190.00	190.00
=====	603-30012	12 In SES		Each	=====		
NHM765-007			03/31/22	2.00	400.00	949.67	388.82
		WEIGHTED AVERAGE FOR THE FIRST QUARTER		2.00	400.00	949.67	388.82
STM1151-038		SH115 MP 27 TO MP 38	04/21/22	2.00	750.00	666.66	1271.28
		WEIGHTED AVERAGE FOR THE SECOND QUARTER		2.00	750.00	666.66	1271.28
		WEIGHTED AVERAGE FOR THE YEAR		4.00	575.00	772.79	830.05
=====	603-30015	15 In SES		Each	=====		
STM1151-038		SH115 MP 27 TO MP 38	04/21/22	2.00	800.00	703.69	1289.76
		WEIGHTED AVERAGE FOR THE SECOND QUARTER		2.00	800.00	703.69	1289.76
2670703-487		I-70 BRIDGES OVER WARD ROAD-	12/01/22	6.00	400.00	884.40	1320.00
		WEIGHTED AVERAGE FOR THE FOURTH QUARTER		6.00	400.00	884.40	1320.00
		WEIGHTED AVERAGE FOR THE YEAR		8.00	500.00	839.22	1312.44

COLORADO DEPARTMENT OF TRANSPORTATION
ITEM UNIT COSTS BY PROJECTS -- 2022 COST DATA

11:31 Wednesday, March 8, 2023 319

PROJECT NUMBER	ITEM NUMBER/ PROJECT LOCATION	ITEM DESCRIPTION/ PROJECT LOCATION	DATE LET	UNIT/ QUANTITY	ENGR. EST.	AVERAGE BID	AWARDED BID
===== 603-30018 18 In SES Each =====							
NHPP1601-083			02/03/22	2.00	200.00	2171.90	650.00
	WEIGHTED AVERAGE FOR THE FIRST QUARTER			2.00	200.00	2171.90	650.00
STM1151-038		SH115 MP 27 TO MP 38	04/21/22	6.00	440.00	768.67	1335.78
STA0712-019		SH 71: Frieight Improvements	05/12/22	2.00	700.00	1042.61	1042.61
NHC540-017		R2 CHAINUP STA @ KENOSHA/HOOS	05/12/22	2.00	626.00	1558.33	925.00
	WEIGHTED AVERAGE FOR THE SECOND QUARTER			10.00	529.20	907.77	1194.99
IM025A-050		I25-MP103.9 - INTERSECTION DR	12/01/22	1.00	600.00	1676.67	430.00
	WEIGHTED AVERAGE FOR THE FOURTH QUARTER			1.00	600.00	1676.67	430.00
	WEIGHTED AVERAGE FOR THE YEAR			13.00	484.00	1071.40	1052.30
===== 603-30024 24 In SES Each =====							
NHPP0702-383		I-70 EB AUX FRISCO TO SILVERT	01/13/22	3.00	650.00	1156.37	550.00
NHPP1601-083			02/03/22	32.00	200.00	1488.73	800.00
STA 067A-048		Hwy 67A MP 0.00 TO MP 11.05 I	03/03/22	4.00	500.00	1908.15	600.00
	WEIGHTED AVERAGE FOR THE FIRST QUARTER			39.00	265.38	1489.25	760.26
STM1151-038		SH115 MP 27 TO MP 38	04/21/22	7.00	900.00	876.13	1450.59
NHC540-017		R2 CHAINUP STA @ KENOSHA/HOOS	05/12/22	5.00	880.00	2316.67	2000.00
NHPP 3851-018		US 385 NORTH OF CHEYENNE WELL	05/26/22	2.00	1000.00	1232.50	1165.00
	WEIGHTED AVERAGE FOR THE SECOND QUARTER			14.00	907.14	1302.68	1606.01
NHPP0502-090		SH 50 MP 134.6-136 GUNNISON C	12/22/22	1.00	1000.00	1977.62	3499.98
	WEIGHTED AVERAGE FOR THE FOURTH QUARTER			1.00	1000.00	1977.62	3499.98
	WEIGHTED AVERAGE FOR THE YEAR			54.00	445.37	1438.37	1030.26

COLORADO DEPARTMENT OF TRANSPORTATION
ITEM UNIT COSTS BY PROJECTS -- 2022 COST DATA

11:31 Wednesday, March 8, 2023 320

PROJECT NUMBER	ITEM NUMBER/ PROJECT LOCATION	ITEM DESCRIPTION/ PROJECT LOCATION	DATE LET	UNIT/ QUANTITY	ENGR. EST.	AVERAGE BID	AWARDED BID
===== 603-30030 30 In SES Each =====							
NHPP1601-083			02/03/22	4.00	200.00	2435.84	1200.00
		WEIGHTED AVERAGE FOR THE FIRST QUARTER		4.00	200.00	2435.84	1200.00
C5502-097		US550 MP 117.28-126.06	11/17/22	2.00	2500.00	1515.28	909.00
NHPP0502-090		SH 50 MP 134.6-136 GUNNISON C	12/22/22	1.00	1200.00	2596.48	3991.86
		WEIGHTED AVERAGE FOR THE FOURTH QUARTER		3.00	2066.67	2006.73	1936.62
		WEIGHTED AVERAGE FOR THE YEAR		7.00	1000.00	2187.41	1515.69
===== 603-30036 36 In SES Each =====							
NHPP1601-083			02/03/22	14.00	300.00	2514.39	2000.00
		WEIGHTED AVERAGE FOR THE FIRST QUARTER		14.00	300.00	2514.39	2000.00
STM1151-038		SH115 MP 27 TO MP 38	04/21/22	2.00	1530.00	1611.02	2070.86
		WEIGHTED AVERAGE FOR THE SECOND QUARTER		2.00	1530.00	1611.02	2070.86
STA3852-015		US 385 HOLYOKE NORTH	10/27/22	2.00	1800.00	1800.00	1800.00
		WEIGHTED AVERAGE FOR THE FOURTH QUARTER		2.00	1800.00	1800.00	1800.00
		WEIGHTED AVERAGE FOR THE YEAR		18.00	603.33	2252.83	1985.65
===== 603-30042 42 In SES Each =====							
NHPP1601-083			02/03/22	2.00	500.00	4571.59	3000.00
		WEIGHTED AVERAGE FOR THE FIRST QUARTER		2.00	500.00	4571.59	3000.00
STM1151-038		SH115 MP 27 TO MP 38	04/21/22	1.00	2000.00	2504.52	2881.90
		WEIGHTED AVERAGE FOR THE SECOND QUARTER		1.00	2000.00	2504.52	2881.90
		WEIGHTED AVERAGE FOR THE YEAR		3.00	1000.00	3423.21	2960.63

COLORADO DEPARTMENT OF TRANSPORTATION
ITEM UNIT COSTS BY PROJECTS -- 2022 COST DATA

11:31 Wednesday, March 8, 2023 321

PROJECT NUMBER	ITEM NUMBER/ PROJECT LOCATION	ITEM DESCRIPTION/ PROJECT LOCATION	DATE LET	UNIT/ QUANTITY	ENGR. EST.	AVERAGE BID	AWARDED BID
=====	603-31336	36 In Equiv Arch SES		Each	=====	=====	=====
STA3852-015		US 385 HOLYOKE NORTH	10/27/22	2.00	2000.00	2000.00	2000.00
		WEIGHTED AVERAGE FOR THE FOURTH QUARTER		2.00	2000.00	2000.00	2000.00
		WEIGHTED AVERAGE FOR THE YEAR		2.00	2000.00	2000.00	2000.00
=====	603-50006	6 In Plastic Pipe		Lin Foot	=====	=====	=====
NHPP0702-413		VAIL PASS AUX PHASE 1 CAP 2	04/18/22	35.00	47.24	47.24	47.24
		WEIGHTED AVERAGE FOR THE SECOND QUARTER		35.00	47.24	47.24	47.24
NHPP0063-054		US 6 FROM I70-B TO 33 RD. (MP	08/18/22	8.00	300.00	115.17	100.00
		WEIGHTED AVERAGE FOR THE THIRD QUARTER		8.00	300.00	115.17	100.00
		WEIGHTED AVERAGE FOR THE YEAR		43.00	94.27	68.55	57.06
=====	603-50015	15 In Plastic Pipe		Lin Foot	=====	=====	=====
BR0343-046 FBR0343-047		US 34 TIMBER BRIDGE REPL. PKG	08/31/22	48.00	153.92	111.30	111.30
		US 6/US 34 TIMBER BRIDGE REPL					
		WEIGHTED AVERAGE FOR THE THIRD QUARTER		48.00	153.92	111.30	111.30
STU0252-457		I-25:ALAMEDA RIVER PH 2.0	11/03/22	114.00	110.00	278.72	430.00
		WEIGHTED AVERAGE FOR THE FOURTH QUARTER		114.00	110.00	278.72	430.00
		WEIGHTED AVERAGE FOR THE YEAR		162.00	123.01	258.11	335.57
=====	603-50018	18 In Plastic Pipe		Lin Foot	=====	=====	=====
IM025A-050		I25-MP103.9 - INTERSECTION DR	12/01/22	27.00	125.00	198.33	210.00
		WEIGHTED AVERAGE FOR THE FOURTH QUARTER		27.00	125.00	198.33	210.00
		WEIGHTED AVERAGE FOR THE YEAR		27.00	125.00	198.33	210.00

COLORADO DEPARTMENT OF TRANSPORTATION
ITEM UNIT COSTS BY PROJECTS -- 2022 COST DATA

11:31 Wednesday, March 8, 2023 322

PROJECT NUMBER	ITEM NUMBER/ PROJECT LOCATION	ITEM DESCRIPTION/ PROJECT LOCATION	DATE LET	UNIT/ QUANTITY	ENGR. EST.	AVERAGE BID	AWARDED BID
=====	603-50024	24 In Plastic Pipe		Lin Foot	=====		
NHPP0702-383		I-70 EB AUX FRISCO TO SILVERT	01/13/22	50.00	150.00	230.00	200.00
	WEIGHTED AVERAGE FOR THE FIRST QUARTER			50.00	150.00	230.00	200.00
	WEIGHTED AVERAGE FOR THE YEAR			50.00	150.00	230.00	200.00
=====	603-50030	30 In Plastic Pipe		Lin Foot	=====		
C5502-097		US550 MP 117.28-126.06	11/17/22	125.00	500.00	209.94	116.00
	WEIGHTED AVERAGE FOR THE FOURTH QUARTER			125.00	500.00	209.94	116.00
	WEIGHTED AVERAGE FOR THE YEAR			125.00	500.00	209.94	116.00
=====	603-61120	12 In Flexible Pipe		Lin Foot	=====		
2670403-065		US40_FLOYD HILL ROUNDABOUTS	09/15/22	58.00	93.00	103.37	108.00
	WEIGHTED AVERAGE FOR THE THIRD QUARTER			58.00	93.00	103.37	108.00
	WEIGHTED AVERAGE FOR THE YEAR			58.00	93.00	103.37	108.00
=====	603-61180	18 In Flexible Pipe		Lin Foot	=====		
NHPP1601-083			02/03/22	25.00	150.00	242.39	112.00
	WEIGHTED AVERAGE FOR THE FIRST QUARTER			25.00	150.00	242.39	112.00
	WEIGHTED AVERAGE FOR THE YEAR			25.00	150.00	242.39	112.00
=====	603-70503	5x3 Ft CBC (Precast)		Lin Foot	=====		
STA0712-019		SH 71: Frieght Improvements	05/12/22	60.00	1000.00	1591.97	1591.97
	WEIGHTED AVERAGE FOR THE SECOND QUARTER			60.00	1000.00	1591.97	1591.97
	WEIGHTED AVERAGE FOR THE YEAR			60.00	1000.00	1591.97	1591.97
=====	603-70804	8x4 Ft CBC (Precast)		Lin Foot	=====		
C170A-002		CRITICAL CULVERT CONST. PKG D	10/27/22	56.00	1800.00	2199.17	2516.67
	WEIGHTED AVERAGE FOR THE FOURTH QUARTER			56.00	1800.00	2199.17	2516.67
	WEIGHTED AVERAGE FOR THE YEAR			56.00	1800.00	2199.17	2516.67

COLORADO DEPARTMENT OF TRANSPORTATION
ITEM UNIT COSTS BY PROJECTS -- 2022 COST DATA

11:31 Wednesday, March 8, 2023 323

PROJECT NUMBER	ITEM NUMBER/ PROJECT LOCATION	ITEM DESCRIPTION/ PROJECT LOCATION	DATE LET	UNIT/ QUANTITY	ENGR. EST.	AVERAGE BID	AWARDED BID
=====	603-71204	12x4 Ft CBC (Precast)		Lin Foot	=====		
STA0712-019		SH 71: Frieight Improvements	05/12/22	198.00	2000.00	3578.51	3578.51
		WEIGHTED AVERAGE FOR THE SECOND QUARTER		198.00	2000.00	3578.51	3578.51
		WEIGHTED AVERAGE FOR THE YEAR		198.00	2000.00	3578.51	3578.51
=====	603-71209	12x8 Ft CBC (Precast) (Inst Only)		Lin Foot	=====		
BR0343-046 FBR0343-047		US 34 TIMBER BRIDGE REPL. PKG US 6/US 34 TIMBER BRIDGE REPL	08/31/22	68.00	1879.59	1505.64	1505.64
		WEIGHTED AVERAGE FOR THE THIRD QUARTER		68.00	1879.59	1505.64	1505.64
		WEIGHTED AVERAGE FOR THE YEAR		68.00	1879.59	1505.64	1505.64
=====	603-72007	20x8 Ft CBC (Precast) (Inst Only)		Lin Foot	=====		
BR0343-046 FBR0343-047		US 34 TIMBER BRIDGE REPL. PKG US 6/US 34 TIMBER BRIDGE REPL	08/31/22	150.00	2036.79	1529.69	1529.69
		WEIGHTED AVERAGE FOR THE THIRD QUARTER		150.00	2036.79	1529.69	1529.69
		WEIGHTED AVERAGE FOR THE YEAR		150.00	2036.79	1529.69	1529.69
=====	603-82006	6 In Duct Iron Pipe		Lin Foot	=====		
STU0252-457		I-25:ALAMEDA RIVER PH 2.0	11/03/22	146.00	120.00	310.79	402.00
		WEIGHTED AVERAGE FOR THE FOURTH QUARTER		146.00	120.00	310.79	402.00
		WEIGHTED AVERAGE FOR THE YEAR		146.00	120.00	310.79	402.00
=====	604-00305	Inlet Ty C (5 Ft)		Each	=====		
NHPP0702-383		I-70 EB AUX FRISCO TO SILVERT	01/13/22	7.00	5000.00	5983.78	4800.00
		WEIGHTED AVERAGE FOR THE FIRST QUARTER		7.00	5000.00	5983.78	4800.00
NHPP0702-414		VAIL PASS AUX PHASE 1 CAP 3	07/08/22	13.00	7424.15	7424.15	7424.15

PROJECT NUMBER	ITEM NUMBER/ PROJECT LOCATION	ITEM DESCRIPTION/ PROJECT LOCATION	DATE LET	UNIT/ QUANTITY	ENGR. EST.	AVERAGE BID	AWARDED BID
===== 604-00305 Inlet Ty C (5 Ft) Each =====							
FBR0702-423		VAIL PASS AUX BE F-12-AT PHAS					
NHPP0063-054		US 6 FROM I70-B TO 33 RD. (MP	08/18/22	6.00	3500.00	5792.28	5000.00
2670403-065		US40 FLOYD HILL ROUNDABOUTS	09/15/22	2.00	7000.00	7724.41	5566.00
2670703-497		I-70_GENESEE WILDLIFE XING	09/15/22	1.00	5100.00	8397.00	8088.31
		WEIGHTED AVERAGE FOR THE THIRD QUARTER		22.00	6209.73	7135.44	6624.28
TRG0253-264		I-25 AND SH 119 PARK-N-RIDE	10/27/22	3.00	5000.00	6674.01	4500.00
C5502-097		US550 MP 117.28-126.06	11/17/22	2.00	8000.00	4956.77	3390.00
STAM420-001		US 285 AT HWY 9C IMPROVEMENTS	12/01/22	7.00	5000.00	7934.06	7029.64
BR2854-148		INTERSECTION OF US 285 & SH 9					
STM0091-046		ADA RAMP IMPROVEMENTS - FAIRP					
2670703-487		I-70 BRIDGES OVER WARD ROAD-	12/01/22	1.00	10000.00	6928.40	4850.00
NHPP0063-048		US6 / 20 ROAD INTERSECTION IM	12/15/22	2.00	8000.00	5633.71	4160.00
		WEIGHTED AVERAGE FOR THE FOURTH QUARTER		15.00	6133.33	6975.19	6038.68
		WEIGHTED AVERAGE FOR THE YEAR		44.00	5991.23	6786.97	6130.26
===== 604-00310 Inlet Ty C (10 Ft) Each =====							
NHPP0702-383		I-70 EB AUX FRISCO TO SILVERT	01/13/22	3.00	7000.00	7478.01	5500.00
		WEIGHTED AVERAGE FOR THE FIRST QUARTER		3.00	7000.00	7478.01	5500.00
NHPP0063-054		US 6 FROM I70-B TO 33 RD. (MP	08/18/22	2.00	6500.00	6456.76	5600.00
		WEIGHTED AVERAGE FOR THE THIRD QUARTER		2.00	6500.00	6456.76	5600.00
STAM420-001		US 285 AT HWY 9C IMPROVEMENTS	12/01/22	3.00	7000.00	9978.36	10286.35
BR2854-148		INTERSECTION OF US 285 & SH 9					
STM0091-046		ADA RAMP IMPROVEMENTS - FAIRP					
IM025A-050		I25-MP103.9 - INTERSECTION DR	12/01/22	1.00	5500.00	8300.00	8000.00
		WEIGHTED AVERAGE FOR THE FOURTH QUARTER		4.00	6625.00	9642.69	9714.76
		WEIGHTED AVERAGE FOR THE YEAR		9.00	6722.22	8312.87	7395.45

COLORADO DEPARTMENT OF TRANSPORTATION
ITEM UNIT COSTS BY PROJECTS -- 2022 COST DATA

11:31 Wednesday, March 8, 2023 325

PROJECT NUMBER	ITEM NUMBER/ PROJECT LOCATION	ITEM DESCRIPTION/ PROJECT LOCATION	DATE LET	UNIT/ QUANTITY	ENGR. EST.	AVERAGE BID	AWARDED BID
=====	604-00505	Inlet Ty D (5 Ft)		Each	=====		
NHPP0702-413		VAIL PASS AUX PHASE 1 CAP 2	04/18/22	2.00	9058.43	9058.43	9058.43
STM1151-038		SH115 MP 27 TO MP 38	04/21/22	5.00	6700.00	5631.84	7013.49
		WEIGHTED AVERAGE FOR THE SECOND QUARTER		7.00	7373.84	5885.67	7597.76
NHPP0702-414		VAIL PASS AUX PHASE 1 CAP 3	07/08/22	7.00	9010.17	9010.17	9010.17
FBR0702-423		VAIL PASS AUX BE F-12-AT PHAS					
NHPP0063-054		US 6 FROM I70-B TO 33 RD. (MP	08/18/22	1.00	5500.00	8989.69	7800.00
2670403-065		US40_FLOYD HILL ROUNDABOUTS	09/15/22	1.00	7500.00	10209.36	7211.00
SHE2873-193		US 287 & CO 52 INTERSECTION I	09/15/22	1.00	6000.00	9442.25	9500.00
		WEIGHTED AVERAGE FOR THE THIRD QUARTER		10.00	8207.12	9351.78	8758.22
TRG0253-264		I-25 AND SH 119 PARK-N-RIDE	10/27/22	1.00	6500.00	8271.05	5700.00
STAM420-001		US 285 AT HWY 9C IMPROVEMENTS	12/01/22	1.00	6187.00	10592.26	8881.06
BR2854-148		INTERSECTION OF US 285 & SH 9					
STM0091-046		ADA RAMP IMPROVEMENTS - FAIRP					
		WEIGHTED AVERAGE FOR THE FOURTH QUARTER		2.00	6343.50	9044.79	7290.53
		WEIGHTED AVERAGE FOR THE YEAR		19.00	7703.95	7645.31	8176.19
=====	604-00510	Inlet Ty D (10 Ft)		Each	=====		
NHPP0702-413		VAIL PASS AUX PHASE 1 CAP 2	04/18/22	2.00	10649.59	10649.59	10649.59
STM1151-038		SH115 MP 27 TO MP 38	04/21/22	1.00	8000.00	8476.04	12194.50
		WEIGHTED AVERAGE FOR THE SECOND QUARTER		3.00	9766.39	9097.05	11164.56
NHPP0063-054		US 6 FROM I70-B TO 33 RD. (MP	08/18/22	2.00	8000.00	9806.34	8500.00
2670403-065		US40_FLOYD HILL ROUNDABOUTS	09/15/22	1.00	13000.00	13356.11	7758.00
		WEIGHTED AVERAGE FOR THE THIRD QUARTER		3.00	9666.67	11327.67	8252.67
STAM420-001		US 285 AT HWY 9C IMPROVEMENTS	12/01/22	1.00	6500.00	12383.15	12419.91

COLORADO DEPARTMENT OF TRANSPORTATION
ITEM UNIT COSTS BY PROJECTS -- 2022 COST DATA

11:31 Wednesday, March 8, 2023 326

PROJECT NUMBER	ITEM NUMBER/ PROJECT LOCATION	ITEM DESCRIPTION/ PROJECT LOCATION	DATE LET	UNIT/ QUANTITY	ENGR. EST.	AVERAGE BID	AWARDED BID
=====	604-00510	Inlet Ty D (10 Ft)		Each	=====	=====	=====
BR2854-148		INTERSECTION OF US 285 & SH 9					
STM0091-046		ADA RAMP IMPROVEMENTS - FAIRP					
	WEIGHTED AVERAGE FOR THE FOURTH QUARTER			1.00	6500.00	12383.15	12419.91
	WEIGHTED AVERAGE FOR THE YEAR			7.00	9257.03	10694.76	10095.94
=====	604-00515	Inlet Ty D (15 Ft)		Each	=====	=====	=====
2670403-065		US40_FLOYD HILL ROUNDABOUTS	09/15/22	1.00	15000.00	17679.53	10235.00
	WEIGHTED AVERAGE FOR THE THIRD QUARTER			1.00	15000.00	17679.53	10235.00
	WEIGHTED AVERAGE FOR THE YEAR			1.00	15000.00	17679.53	10235.00
=====	604-13005	Inlet Ty 13 (5 Ft)		Each	=====	=====	=====
NHPP0063-054		US 6 FROM I70-B TO 33 RD. (MP 08/18/22		1.00	5500.00	5427.47	4700.00
	WEIGHTED AVERAGE FOR THE THIRD QUARTER			1.00	5500.00	5427.47	4700.00
	WEIGHTED AVERAGE FOR THE YEAR			1.00	5500.00	5427.47	4700.00
=====	604-16005	Inlet Ty 16 (5 Ft)		Each	=====	=====	=====
NHM765-007			03/31/22	15.00	4500.00	9889.48	6972.35
	WEIGHTED AVERAGE FOR THE FIRST QUARTER			15.00	4500.00	9889.48	6972.35
2670703-479		I-70 BRIDGE OVER HARLAN	05/05/22	2.00	5500.00	7641.80	5077.49
	WEIGHTED AVERAGE FOR THE SECOND QUARTER			2.00	5500.00	7641.80	5077.49
NHPP0063-054		US 6 FROM I70-B TO 33 RD. (MP 08/18/22		2.00	5000.00	6478.48	5600.00
2670403-065		US40_FLOYD HILL ROUNDABOUTS	09/15/22	7.00	8000.00	9999.65	8000.00
	WEIGHTED AVERAGE FOR THE THIRD QUARTER			9.00	7333.33	9436.26	7466.67

COLORADO DEPARTMENT OF TRANSPORTATION
ITEM UNIT COSTS BY PROJECTS -- 2022 COST DATA

11:31 Wednesday, March 8, 2023 327

PROJECT NUMBER	ITEM NUMBER/ PROJECT LOCATION	ITEM DESCRIPTION/ PROJECT LOCATION	DATE LET	UNIT/ QUANTITY	ENGR. EST.	AVERAGE BID	AWARDED BID
=====	604-16005	Inlet Ty 16 (5 Ft)		Each	=====		
STAM420-001		US 285 AT HWY 9C IMPROVEMENTS	12/01/22	2.00	6500.00	10554.82	9805.06
BR2854-148		INTERSECTION OF US 285 & SH 9					
STM0091-046		ADA RAMP IMPROVEMENTS - FAIRP					
IM025A-050		I25-MP103.9 - INTERSECTION DR	12/01/22	2.00	6500.00	10500.00	10200.00
		WEIGHTED AVERAGE FOR THE FOURTH QUARTER		4.00	6500.00	10531.33	10002.53
		WEIGHTED AVERAGE FOR THE YEAR		30.00	5683.33	9584.09	7398.35
=====	604-16010	Inlet Ty 16 (10 Ft)		Each	=====		
NHPP0063-054		US 6 FROM I70-B TO 33 RD. (MP	08/18/22	1.00	7000.00	8892.22	7700.00
		WEIGHTED AVERAGE FOR THE THIRD QUARTER		1.00	7000.00	8892.22	7700.00
STU0252-457		I-25:ALAMEDA RIVER PH 2.0	11/03/22	2.00	8000.00	11286.22	9500.00
STAM420-001		US 285 AT HWY 9C IMPROVEMENTS	12/01/22	1.00	12000.00	18420.83	27001.01
BR2854-148		INTERSECTION OF US 285 & SH 9					
STM0091-046		ADA RAMP IMPROVEMENTS - FAIRP					
		WEIGHTED AVERAGE FOR THE FOURTH QUARTER		3.00	9333.33	14140.07	15333.67
		WEIGHTED AVERAGE FOR THE YEAR		4.00	8750.00	13265.42	13425.25
=====	604-16505	Inlet Ty 16 (D) (5 Ft)		Each	=====		
NHM765-007			03/31/22	4.00	8200.00	11408.03	9419.75
		WEIGHTED AVERAGE FOR THE FIRST QUARTER		4.00	8200.00	11408.03	9419.75
TRG0253-264		I-25 AND SH 119 PARK-N-RIDE	10/27/22	1.00	8000.00	10684.35	13000.00
STU0252-457		I-25:ALAMEDA RIVER PH 2.0	11/03/22	1.00	10000.00	12609.05	10000.00
STAM420-001		US 285 AT HWY 9C IMPROVEMENTS	12/01/22	3.00	8064.00	13650.60	14256.92
BR2854-148		INTERSECTION OF US 285 & SH 9					

COLORADO DEPARTMENT OF TRANSPORTATION
 ITEM UNIT COSTS BY PROJECTS -- 2022 COST DATA

11:31 Wednesday, March 8, 2023 328

PROJECT NUMBER	ITEM NUMBER/ PROJECT LOCATION	ITEM DESCRIPTION/ PROJECT LOCATION	DATE LET	UNIT/ QUANTITY	ENGR. EST.	AVERAGE BID	AWARDED BID
===== 604-16505 STM0091-046		Inlet Ty 16 (D) (5 Ft) ADA RAMP IMPROVEMENTS - FAIRP		Each =====			
	WEIGHTED AVERAGE FOR THE FOURTH QUARTER			5.00	8438.40	12483.01	13154.15
	WEIGHTED AVERAGE FOR THE YEAR			9.00	8332.44	12114.44	11494.42
===== 604-16510 NHPP0063-054		Inlet Ty 16 (D) (10 Ft) US 6 FROM I70-B TO 33 RD. (MP 08/18/22		Each =====			
	WEIGHTED AVERAGE FOR THE THIRD QUARTER			1.00	13000.00	12806.38	11100.00
	WEIGHTED AVERAGE FOR THE YEAR			1.00	13000.00	12806.38	11100.00
STAM420-001 BR2854-148 STM0091-046		US 285 AT HWY 9C IMPROVEMENTS 12/01/22 INTERSECTION OF US 285 & SH 9 ADA RAMP IMPROVEMENTS - FAIRP		Each =====			
	WEIGHTED AVERAGE FOR THE FOURTH QUARTER			6.00	15000.00	16467.31	18400.51
	WEIGHTED AVERAGE FOR THE YEAR			7.00	14714.29	16185.70	17357.58
===== 604-16605 NHM765-007		Inlet Ty 16 (T) (5 Ft)		Each =====			
	WEIGHTED AVERAGE FOR THE FIRST QUARTER		03/31/22	16.00	10000.00	14205.26	11991.63
	WEIGHTED AVERAGE FOR THE YEAR			16.00	10000.00	14205.26	11991.63
STU0252-457 IM025A-050		I-25:ALAMEDA RIVER PH 2.0 11/03/22 I25-MP103.9 - INTERSECTION DR 12/01/22		Each =====			
	WEIGHTED AVERAGE FOR THE FOURTH QUARTER			2.00	15000.00	22994.07	16900.00
	WEIGHTED AVERAGE FOR THE YEAR			3.00	13333.33	21818.27	18900.00
	WEIGHTED AVERAGE FOR THE YEAR			19.00	10526.32	15407.31	13082.43
===== 604-16610 STU0252-457		Inlet Ty 16 (T) (10 Ft) I-25:ALAMEDA RIVER PH 2.0 11/03/22		Each =====			
	WEIGHTED AVERAGE FOR THE FOURTH QUARTER			1.00	20000.00	21746.22	17700.00
	WEIGHTED AVERAGE FOR THE YEAR			1.00	20000.00	21746.22	17700.00

COLORADO DEPARTMENT OF TRANSPORTATION
 ITEM UNIT COSTS BY PROJECTS -- 2022 COST DATA

11:31 Wednesday, March 8, 2023 329

PROJECT NUMBER	ITEM NUMBER/ PROJECT LOCATION	ITEM DESCRIPTION/ PROJECT LOCATION	DATE LET	UNIT/ QUANTITY	ENGR. EST.	AVERAGE BID	AWARDED BID
=====	604-19005	Inlet Spec (5 Ft)		Each	=====	=====	=====
STU0252-457		I-25:ALAMEDA RIVER PH 2.0	11/03/22	1.00	10000.00	19191.85	9500.00
	WEIGHTED AVERAGE FOR THE FOURTH QUARTER			1.00	10000.00	19191.85	9500.00
	WEIGHTED AVERAGE FOR THE YEAR			1.00	10000.00	19191.85	9500.00
=====	604-19010	Inlet Spec (10 Ft)		Each	=====	=====	=====
NHPP0063-063			02/24/22	3.00	7500.00	10145.00	4500.00
	WEIGHTED AVERAGE FOR THE FIRST QUARTER			3.00	7500.00	10145.00	4500.00
	WEIGHTED AVERAGE FOR THE YEAR			3.00	7500.00	10145.00	4500.00
=====	604-19035	Inlet Spec (35 Ft)		Each	=====	=====	=====
2670703-479		I-70 BRIDGE OVER HARLAN	05/05/22	1.00	20000.00	36452.93	19319.67
	WEIGHTED AVERAGE FOR THE SECOND QUARTER			1.00	20000.00	36452.93	19319.67
	WEIGHTED AVERAGE FOR THE YEAR			1.00	20000.00	36452.93	19319.67
=====	604-19105	Inlet Ty R L5 (5 Ft)		Each	=====	=====	=====
2670703-479		I-70 BRIDGE OVER HARLAN	05/05/22	1.00	10000.00	7816.88	7402.01
	WEIGHTED AVERAGE FOR THE SECOND QUARTER			1.00	10000.00	7816.88	7402.01
NHPP0063-054		US 6 FROM I70-B TO 33 RD. (MP	08/18/22	16.00	6500.00	11305.96	9800.00
2670403-065		US40 FLOYD HILL ROUNDABOUTS	09/15/22	4.00	8000.00	11524.05	8053.00
SHE2873-193		US 287 & CO 52 INTERSECTION I	09/15/22	1.00	6500.00	9202.65	8300.00
	WEIGHTED AVERAGE FOR THE THIRD QUARTER			21.00	6785.71	11105.90	9395.81
TRG0253-264		I-25 AND SH 119 PARK-N-RIDE	10/27/22	1.00	8000.00	9420.85	9000.00

COLORADO DEPARTMENT OF TRANSPORTATION
ITEM UNIT COSTS BY PROJECTS -- 2022 COST DATA

11:31 Wednesday, March 8, 2023 330

PROJECT NUMBER	ITEM NUMBER/ PROJECT LOCATION	ITEM DESCRIPTION/ PROJECT LOCATION	DATE LET	UNIT/ QUANTITY	ENGR. EST.	AVERAGE BID	AWARDED BID
===== 604-19105 Inlet Ty R L5 (5 Ft) Each =====							
STU0252-457		I-25:ALAMEDA RIVER PH 2.0	11/03/22	1.00	7500.00	10616.76	10000.00
STAM420-001		US 285 AT HWY 9C IMPROVEMENTS	12/01/22	15.00	7010.00	9219.11	9301.05
BR2854-148		INTERSECTION OF US 285 & SH 9					
STM0091-046		ADA RAMP IMPROVEMENTS - FAIRP					
IM025A-050		I25-MP103.9 - INTERSECTION DR	12/01/22	2.00	7500.00	9666.67	9100.00
	WEIGHTED AVERAGE FOR THE FOURTH QUARTER			19.00	7139.47	9329.40	9300.83
	WEIGHTED AVERAGE FOR THE YEAR			41.00	7028.05	9929.02	9303.16
===== 604-19110 Inlet Ty R L5 (10 Ft) Each =====							
2670703-479		I-70 BRIDGE OVER HARLAN	05/05/22	1.00	12000.00	11752.68	13735.85
	WEIGHTED AVERAGE FOR THE SECOND QUARTER			1.00	12000.00	11752.68	13735.85
NHPP0063-054		US 6 FROM I70-B TO 33 RD. (MP	08/18/22	13.00	8000.00	15095.99	13000.00
2670403-065		US40_FLOYD HILL ROUNDABOUTS	09/15/22	2.00	10000.00	17665.67	9724.00
	WEIGHTED AVERAGE FOR THE THIRD QUARTER			15.00	8266.67	15577.80	12563.20
STU0252-457		I-25:ALAMEDA RIVER PH 2.0	11/03/22	2.00	10000.00	13038.08	12200.00
STAM420-001		US 285 AT HWY 9C IMPROVEMENTS	12/01/22	14.00	8550.00	12058.25	13671.45
BR2854-148		INTERSECTION OF US 285 & SH 9					
STM0091-046		ADA RAMP IMPROVEMENTS - FAIRP					
IM025A-050		I25-MP103.9 - INTERSECTION DR	12/01/22	4.00	9000.00	12433.33	10500.00
	WEIGHTED AVERAGE FOR THE FOURTH QUARTER			20.00	8785.00	12198.52	12890.02
	WEIGHTED AVERAGE FOR THE YEAR			36.00	8658.33	13140.15	12777.34
===== 604-19115 Inlet Ty R L5 (15 Ft) Each =====							
STAM420-001		US 285 AT HWY 9C IMPROVEMENTS	12/01/22	2.00	10525.00	19374.67	23899.01
BR2854-148		INTERSECTION OF US 285 & SH 9					
STM0091-046		ADA RAMP IMPROVEMENTS - FAIRP					
	WEIGHTED AVERAGE FOR THE FOURTH QUARTER			2.00	10525.00	19374.67	23899.01
	WEIGHTED AVERAGE FOR THE YEAR			2.00	10525.00	19374.67	23899.01

COLORADO DEPARTMENT OF TRANSPORTATION
ITEM UNIT COSTS BY PROJECTS -- 2022 COST DATA

11:31 Wednesday, March 8, 2023 331

PROJECT NUMBER	ITEM NUMBER/ PROJECT LOCATION	ITEM DESCRIPTION/ PROJECT LOCATION	DATE LET	UNIT/ QUANTITY	ENGR. EST.	AVERAGE BID	AWARDED BID
=====	604-19205	Inlet Ty R L10 (5 Ft)		Each	=====	=====	=====
NHPP0063-054		US 6 FROM I70-B TO 33 RD. (MP 08/18/22		2.00	12000.00	17143.30	14800.00
SHE2873-193		US 287 & CO 52 INTERSECTION I 09/15/22		1.00	9500.00	11026.02	9100.00
		WEIGHTED AVERAGE FOR THE THIRD QUARTER		3.00	11166.67	13472.93	12900.00
TRG0253-264		I-25 AND SH 119 PARK-N-RIDE	10/27/22	2.00	11000.00	12879.18	12000.00
		WEIGHTED AVERAGE FOR THE FOURTH QUARTER		2.00	11000.00	12879.18	12000.00
		WEIGHTED AVERAGE FOR THE YEAR		5.00	11100.00	13107.54	12540.00
=====	604-19210	Inlet Ty R L10 (10 Ft)		Each	=====	=====	=====
NHPP0063-054		US 6 FROM I70-B TO 33 RD. (MP 08/18/22		1.00	12000.00	21551.13	18600.00
		WEIGHTED AVERAGE FOR THE THIRD QUARTER		1.00	12000.00	21551.13	18600.00
IM025A-050		I25-MP103.9 - INTERSECTION DR 12/01/22		1.00	12000.00	17533.33	14600.00
		WEIGHTED AVERAGE FOR THE FOURTH QUARTER		1.00	12000.00	17533.33	14600.00
		WEIGHTED AVERAGE FOR THE YEAR		2.00	12000.00	19140.45	16600.00
=====	604-19305	Inlet Ty R L15 (5 Ft)		Each	=====	=====	=====
TRG0253-264		I-25 AND SH 119 PARK-N-RIDE	10/27/22	2.00	13000.00	16213.91	19000.00
IM025A-050		I25-MP103.9 - INTERSECTION DR 12/01/22		1.00	13000.00	22133.33	18400.00
		WEIGHTED AVERAGE FOR THE FOURTH QUARTER		3.00	13000.00	17148.55	18800.00
		WEIGHTED AVERAGE FOR THE YEAR		3.00	13000.00	17148.55	18800.00
=====	604-19310	Inlet Ty R L15 (10 Ft)		Each	=====	=====	=====
STAM420-001		US 285 AT HWY 9C IMPROVEMENTS	12/01/22	1.00	12774.00	22949.10	17392.57

COLORADO DEPARTMENT OF TRANSPORTATION
 ITEM UNIT COSTS BY PROJECTS -- 2022 COST DATA

11:31 Wednesday, March 8, 2023 332

PROJECT NUMBER	ITEM NUMBER/ PROJECT LOCATION	ITEM DESCRIPTION/ PROJECT LOCATION	DATE LET	UNIT/ QUANTITY	ENGR. EST.	AVERAGE BID	AWARDED BID
=====	604-19310	Inlet Ty R L15 (10 Ft)		Each	=====	=====	=====
BR2854-148		INTERSECTION OF US 285 & SH 9					
STM0091-046		ADA RAMP IMPROVEMENTS - FAIRP					
	WEIGHTED AVERAGE FOR THE FOURTH QUARTER			1.00	12774.00	22949.10	17392.57
	WEIGHTED AVERAGE FOR THE YEAR			1.00	12774.00	22949.10	17392.57
=====	604-19712	Inlet Spec (Trench) (12 In)		Lin Foot	=====	=====	=====
NHPP0063-063			02/24/22	45.00	400.00	454.50	460.00
	WEIGHTED AVERAGE FOR THE FIRST QUARTER			45.00	400.00	454.50	460.00
	WEIGHTED AVERAGE FOR THE YEAR			45.00	400.00	454.50	460.00
=====	604-20000	Outlet Structure		Each	=====	=====	=====
NHPP0702-413		VAIL PASS AUX PHASE 1 CAP 2	04/18/22	4.00	2279.10	2279.10	2279.10
	WEIGHTED AVERAGE FOR THE SECOND QUARTER			4.00	2279.10	2279.10	2279.10
NHPP0702-414		VAIL PASS AUX PHASE 1 CAP 3	07/08/22	3.00	3866.27	3866.27	3866.27
FBR0702-423		VAIL PASS AUX BE F-12-AT PHAS					
NHPP0063-054		US 6 FROM I70-B TO 33 RD. (MP 08/18/22)		1.00	15000.00	11218.14	9700.00
	WEIGHTED AVERAGE FOR THE THIRD QUARTER			4.00	6649.70	6807.02	5324.70
TRG0253-264		I-25 AND SH 119 PARK-N-RIDE	10/27/22	2.00	30000.00	21892.71	9500.00
	WEIGHTED AVERAGE FOR THE FOURTH QUARTER			2.00	30000.00	21892.71	9500.00
	WEIGHTED AVERAGE FOR THE YEAR			10.00	9571.52	15737.39	4941.52
=====	604-25000	Vane Grate Inlet Spec		Each	=====	=====	=====
2670703-479		I-70 BRIDGE OVER HARLAN	05/05/22	2.00	6000.00	15114.39	14223.04

COLORADO DEPARTMENT OF TRANSPORTATION
 ITEM UNIT COSTS BY PROJECTS -- 2022 COST DATA

11:31 Wednesday, March 8, 2023 333

PROJECT NUMBER	ITEM NUMBER/ PROJECT LOCATION	ITEM DESCRIPTION/ PROJECT LOCATION	DATE LET	UNIT/ QUANTITY	ENGR. EST.	AVERAGE BID	AWARDED BID
=====	604-25000	Vane Grate Inlet Spec		Each	=====	=====	=====
ER0702-420		PR I-70 GWC MATERIAL FLOWS 20	05/06/22	1.00	12000.00	19750.00	22000.00
		WEIGHTED AVERAGE FOR THE SECOND QUARTER		3.00	8000.00	15776.62	16815.36
STU0252-457		I-25:ALAMEDA RIVER PH 2.0	11/03/22	3.00	10000.00	21131.48	18500.00
STAM420-001		US 285 AT HWY 9C IMPROVEMENTS	12/01/22	2.00	8240.00	17363.00	26300.54
BR2854-148		INTERSECTION OF US 285 & SH 9					
STM0091-046		ADA RAMP IMPROVEMENTS - FAIRP					
BR012A-048		CO 12 STRUCTURE P-17-F AT MP	12/22/22	1.00	9000.00	10353.13	10000.00
		WEIGHTED AVERAGE FOR THE FOURTH QUARTER		6.00	9246.67	18410.19	19683.51
		WEIGHTED AVERAGE FOR THE YEAR		9.00	8831.11	17292.92	18727.46
=====	604-25005	Vane Grate Inlet (5 Ft)		Each	=====	=====	=====
2670703-479		I-70 BRIDGE OVER HARLAN	05/05/22	1.00	5500.00	8418.43	7881.07
		WEIGHTED AVERAGE FOR THE SECOND QUARTER		1.00	5500.00	8418.43	7881.07
NHPP0702-414		VAIL PASS AUX PHASE 1 CAP 3	07/08/22	2.00	15141.41	15141.41	15141.41
FBR0702-423		VAIL PASS AUX BE F-12-AT PHAS					
NHPP0063-054		US 6 FROM I70-B TO 33 RD. (MP	08/18/22	2.00	6000.00	5313.10	4600.00
		WEIGHTED AVERAGE FOR THE THIRD QUARTER		4.00	10570.71	8589.20	9870.71
STAM420-001		US 285 AT HWY 9C IMPROVEMENTS	12/01/22	1.00	4040.00	8869.60	9451.41
BR2854-148		INTERSECTION OF US 285 & SH 9					
STM0091-046		ADA RAMP IMPROVEMENTS - FAIRP					
IM025A-050		I25-MP103.9 - INTERSECTION DR	12/01/22	2.00	6000.00	12100.00	8800.00
		WEIGHTED AVERAGE FOR THE FOURTH QUARTER		3.00	5346.67	10807.84	9017.14
		WEIGHTED AVERAGE FOR THE YEAR		8.00	7977.85	9551.10	9301.91
=====	604-25007	Vane Grate Inlet Spec (D) (5 Ft)		Each	=====	=====	=====
NHPP0702-383		I-70 EB AUX FRISCO TO SILVERT	01/13/22	1.00	10000.00	9053.39	7000.00
		WEIGHTED AVERAGE FOR THE FIRST QUARTER		1.00	10000.00	9053.39	7000.00
		WEIGHTED AVERAGE FOR THE YEAR		1.00	10000.00	9053.39	7000.00

COLORADO DEPARTMENT OF TRANSPORTATION
ITEM UNIT COSTS BY PROJECTS -- 2022 COST DATA

11:31 Wednesday, March 8, 2023 334

PROJECT NUMBER	ITEM NUMBER/ PROJECT LOCATION	ITEM DESCRIPTION/ PROJECT LOCATION	DATE LET	UNIT/ QUANTITY	ENGR. EST.	AVERAGE BID	AWARDED BID
=====	604-25010	Vane Grate Inlet (10 Ft)		Each	=====	=====	=====
2670703-479		I-70 BRIDGE OVER HARLAN	05/05/22	1.00	7000.00	10090.46	9431.98
		WEIGHTED AVERAGE FOR THE SECOND QUARTER		1.00	7000.00	10090.46	9431.98
NHPP0702-414		VAIL PASS AUX PHASE 1 CAP 3	07/08/22	2.00	17101.53	17101.53	17101.53
FBR0702-423		VAIL PASS AUX BE F-12-AT PHAS					
NHPP0063-054		US 6 FROM I70-B TO 33 RD. (MP 08/18/22)	08/18/22	2.00	8500.00	7838.79	6800.00
		WEIGHTED AVERAGE FOR THE THIRD QUARTER		4.00	12800.77	10926.37	11950.77
		WEIGHTED AVERAGE FOR THE YEAR		5.00	11640.61	10508.42	11447.01
=====	604-25025	Vane Grate Inlet (25 Ft)		Each	=====	=====	=====
STAM420-001		US 285 AT HWY 9C IMPROVEMENTS	12/01/22	1.00	20000.00	26089.21	37500.85
BR2854-148		INTERSECTION OF US 285 & SH 9					
STM0091-046		ADA RAMP IMPROVEMENTS - FAIRP					
		WEIGHTED AVERAGE FOR THE FOURTH QUARTER		1.00	20000.00	26089.21	37500.85
		WEIGHTED AVERAGE FOR THE YEAR		1.00	20000.00	26089.21	37500.85
=====	604-26005	Vane Grate Inlet (D) (5 Ft)		Each	=====	=====	=====
NHPP 0761-238		I-76 DAHLIA TO YORK	03/10/22	1.00	9000.00	7153.33	3900.00
C0761-239							
		WEIGHTED AVERAGE FOR THE FIRST QUARTER		1.00	9000.00	7153.33	3900.00
NHPP0063-054		US 6 FROM I70-B TO 33 RD. (MP 08/18/22)	08/18/22	2.00	10000.00	8194.76	7100.00
		WEIGHTED AVERAGE FOR THE THIRD QUARTER		2.00	10000.00	8194.76	7100.00
		WEIGHTED AVERAGE FOR THE YEAR		3.00	9666.67	7500.47	6033.33
=====	604-30000	MH Slab Base (Spec)		Each	=====	=====	=====
NHPP0063-054		US 6 FROM I70-B TO 33 RD. (MP 08/18/22)	08/18/22	5.00	10000.00	3404.35	2950.00
		WEIGHTED AVERAGE FOR THE THIRD QUARTER		5.00	10000.00	3404.35	2950.00

COLORADO DEPARTMENT OF TRANSPORTATION
ITEM UNIT COSTS BY PROJECTS -- 2022 COST DATA

11:31 Wednesday, March 8, 2023 335

PROJECT NUMBER	ITEM NUMBER/ PROJECT LOCATION	ITEM DESCRIPTION/ PROJECT LOCATION	DATE LET	UNIT/ QUANTITY	ENGR. EST.	AVERAGE BID	AWARDED BID
=====	604-30000	MH Slab Base (Spec)		Each	=====	=====	=====
NHPP0502-090		SH 50 MP 134.6-136 GUNNISON C	12/22/22	1.00	5000.00	18916.80	10211.87
		WEIGHTED AVERAGE FOR THE FOURTH QUARTER		1.00	5000.00	18916.80	10211.87
		WEIGHTED AVERAGE FOR THE YEAR		6.00	9166.67	8575.16	4160.31
=====	604-30005	MH Slab Base (5 Ft)		Each	=====	=====	=====
NHM765-007			03/31/22	12.00	5000.00	9262.28	7122.80
		WEIGHTED AVERAGE FOR THE FIRST QUARTER		12.00	5000.00	9262.28	7122.80
SHE2873-193		US 287 & CO 52 INTERSECTION I	09/15/22	4.00	5500.00	5306.43	7500.00
		WEIGHTED AVERAGE FOR THE THIRD QUARTER		4.00	5500.00	5306.43	7500.00
TRG0253-264		I-25 AND SH 119 PARK-N-RIDE	10/27/22	2.00	5800.00	8723.50	6500.00
C5502-097		US550 MP 117.28-126.06	11/17/22	1.00	10000.00	5813.06	5040.00
STAM420-001		US 285 AT HWY 9C IMPROVEMENTS	12/01/22	2.00	5272.00	8469.83	7096.85
BR2854-148		INTERSECTION OF US 285 & SH 9					
STM0091-046		ADA RAMP IMPROVEMENTS - FAIRP					
		WEIGHTED AVERAGE FOR THE FOURTH QUARTER		5.00	6428.80	8324.96	6446.74
		WEIGHTED AVERAGE FOR THE YEAR		21.00	5435.43	7880.12	7033.68
=====	604-30010	MH Slab Base (10 Ft)		Each	=====	=====	=====
NHPP0702-383		I-70 EB AUX FRISCO TO SILVERT	01/13/22	2.00	7000.00	7676.11	6400.00
NHM765-007			03/31/22	5.00	6600.00	13081.71	11008.24
		WEIGHTED AVERAGE FOR THE FIRST QUARTER		7.00	6714.29	10919.47	9691.60
NHPP0702-413		VAIL PASS AUX PHASE 1 CAP 2	04/18/22	5.00	11512.80	11512.80	11512.80

COLORADO DEPARTMENT OF TRANSPORTATION
 ITEM UNIT COSTS BY PROJECTS -- 2022 COST DATA

11:31 Wednesday, March 8, 2023 336

PROJECT NUMBER	ITEM NUMBER/ PROJECT LOCATION	ITEM DESCRIPTION/ PROJECT LOCATION	DATE LET	UNIT/ QUANTITY	ENGR. EST.	AVERAGE BID	AWARDED BID
=====	604-30010	MH Slab Base (10 Ft)		Each =====			
2670703-479		I-70 BRIDGE OVER HARLAN	05/05/22	1.00	6200.00	10408.75	7560.08
		WEIGHTED AVERAGE FOR THE SECOND QUARTER		6.00	10627.33	10910.59	10854.01
NHPP0702-414		VAIL PASS AUX PHASE 1 CAP 3	07/08/22	4.00	10388.56	10388.56	10388.56
FBR0702-423		VAIL PASS AUX BE F-12-AT PHAS					
FSA052A-057		SH52 BOX CULVERT EXTENSION (M	08/04/22	2.00	7500.00	8828.45	6006.00
NHPP0063-054		US 6 FROM I70-B TO 33 RD. (MP	08/18/22	19.00	5500.00	6078.20	5250.00
2670403-065		US40 FLOYD HILL ROUNDABOUTS	09/15/22	6.00	10000.00	12637.69	7282.00
SHE2873-193		US 287 & CO 52 INTERSECTION I	09/15/22	1.00	6000.00	8242.23	9300.00
		WEIGHTED AVERAGE FOR THE THIRD QUARTER		32.00	7095.45	8367.06	6447.13
TRG0253-264		I-25 AND SH 119 PARK-N-RIDE	10/27/22	1.00	7000.00	10497.89	8300.00
STU0252-457		I-25:ALAMEDA RIVER PH 2.0	11/03/22	3.00	8000.00	20935.19	17500.00
STAM420-001		US 285 AT HWY 9C IMPROVEMENTS	12/01/22	10.00	6300.00	10471.20	11015.20
BR2854-148		INTERSECTION OF US 285 & SH 9					
STM0091-046		ADA RAMP IMPROVEMENTS - FAIRP					
IM025A-050		I25-MP103.9 - INTERSECTION DR	12/01/22	4.00	7500.00	12800.00	7900.00
NHPP0063-048		US6 / 20 ROAD INTERSECTION IM	12/15/22	3.00	9000.00	18449.63	12356.00
		WEIGHTED AVERAGE FOR THE FOURTH QUARTER		21.00	7190.48	13157.18	11234.17
		WEIGHTED AVERAGE FOR THE YEAR		66.00	7406.34	11040.04	8824.54
=====	604-30015	MH Slab Base (15 Ft)		Each =====			
NHPP 0761-238		I-76 DAHLIA TO YORK	03/10/22	1.00	9000.00	9494.19	9100.00
C0761-239							
NHM765-007			03/31/22	2.00	8000.00	19782.45	23352.16
		WEIGHTED AVERAGE FOR THE FIRST QUARTER		3.00	8333.33	13903.44	18601.44
STM1151-038		SH115 MP 27 TO MP 38	04/21/22	1.00	8500.00	12059.36	13872.24
		WEIGHTED AVERAGE FOR THE SECOND QUARTER		1.00	8500.00	12059.36	13872.24
NHPP0702-414		VAIL PASS AUX PHASE 1 CAP 3	07/08/22	1.00	16764.35	16764.35	16764.35

COLORADO DEPARTMENT OF TRANSPORTATION
ITEM UNIT COSTS BY PROJECTS -- 2022 COST DATA

11:31 Wednesday, March 8, 2023 337

PROJECT NUMBER	ITEM NUMBER/ PROJECT LOCATION	ITEM DESCRIPTION/ PROJECT LOCATION	DATE LET	UNIT/ QUANTITY	ENGR. EST.	AVERAGE BID	AWARDED BID
=====	604-30015	MH Slab Base (15 Ft)		Each	=====	=====	=====
FBR0702-423		VAIL PASS AUX BE F-12-AT PHAS					
NHPP0063-054		US 6 FROM I70-B TO 33 RD. (MP	08/18/22	5.00	12000.00	7986.95	6900.00
2670403-065		US40_FLOYD HILL ROUNDABOUTS	09/15/22	3.00	12000.00	25520.56	10870.00
		WEIGHTED AVERAGE FOR THE THIRD QUARTER		9.00	12529.37	16315.94	9319.37
STAM420-001		US 285 AT HWY 9C IMPROVEMENTS	12/01/22	4.00	8000.00	15349.74	18039.60
BR2854-148		INTERSECTION OF US 285 & SH 9					
STM0091-046		ADA RAMP IMPROVEMENTS - FAIRP					
		WEIGHTED AVERAGE FOR THE FOURTH QUARTER		4.00	8000.00	14607.89	16431.68
		WEIGHTED AVERAGE FOR THE YEAR		17.00	10486.14	14803.76	13094.96
=====	604-30020	MH Slab Base (20 Ft)		Each	=====	=====	=====
NHPP0702-413		VAIL PASS AUX PHASE 1 CAP 2	04/18/22	2.00	18984.15	18984.15	18984.15
		WEIGHTED AVERAGE FOR THE SECOND QUARTER		2.00	18984.15	18984.15	18984.15
STAM420-001		US 285 AT HWY 9C IMPROVEMENTS	12/01/22	1.00	10000.00	18627.14	23380.32
BR2854-148		INTERSECTION OF US 285 & SH 9					
STM0091-046		ADA RAMP IMPROVEMENTS - FAIRP					
		WEIGHTED AVERAGE FOR THE FOURTH QUARTER		1.00	10000.00	18627.14	23380.32
		WEIGHTED AVERAGE FOR THE YEAR		3.00	15989.43	18746.15	20449.54
=====	604-31005	MH Box Base (5 Ft)		Each	=====	=====	=====
NHPP0063-054		US 6 FROM I70-B TO 33 RD. (MP	08/18/22	4.00	15000.00	5999.29	5200.00
		WEIGHTED AVERAGE FOR THE THIRD QUARTER		4.00	15000.00	5999.29	5200.00
		WEIGHTED AVERAGE FOR THE YEAR		4.00	15000.00	5999.29	5200.00
=====	604-31015	MH Box Base (15 Ft)		Each	=====	=====	=====
STAM420-001		US 285 AT HWY 9C IMPROVEMENTS	12/01/22	6.00	22000.00	32586.40	37947.02

COLORADO DEPARTMENT OF TRANSPORTATION
 ITEM UNIT COSTS BY PROJECTS -- 2022 COST DATA

11:31 Wednesday, March 8, 2023 338

PROJECT NUMBER	ITEM NUMBER/ PROJECT LOCATION	ITEM DESCRIPTION/ PROJECT LOCATION	DATE LET	UNIT/ QUANTITY	ENGR. EST.	AVERAGE BID	AWARDED BID
=====	604-31015	MH Box Base (15 Ft)		Each	=====	=====	=====
BR2854-148		INTERSECTION OF US 285 & SH 9					
STM0091-046		ADA RAMP IMPROVEMENTS - FAIRP					
	WEIGHTED AVERAGE FOR THE FOURTH QUARTER			6.00	22000.00	30159.77	35298.01
	WEIGHTED AVERAGE FOR THE YEAR			6.00	22000.00	30159.77	35298.01
=====	604-31020	MH Box Base (20 Ft)		Each	=====	=====	=====
STAM420-001		US 285 AT HWY 9C IMPROVEMENTS	12/01/22	8.00	22000.00	36087.69	35000.00
BR2854-148		INTERSECTION OF US 285 & SH 9					
STM0091-046		ADA RAMP IMPROVEMENTS - FAIRP					
	WEIGHTED AVERAGE FOR THE FOURTH QUARTER			8.00	22000.00	35744.16	35555.56
	WEIGHTED AVERAGE FOR THE YEAR			8.00	22000.00	35744.16	35555.56
=====	604-39000	MH Spec		Each	=====	=====	=====
NHPP0702-413		VAIL PASS AUX PHASE 1 CAP 2	04/18/22	8.00	18190.00	18190.00	18190.00
	WEIGHTED AVERAGE FOR THE SECOND QUARTER			8.00	18190.00	18190.00	18190.00
NHPP0702-414		VAIL PASS AUX PHASE 1 CAP 3	07/08/22	6.00	20736.60	20736.60	20736.60
FBR0702-423		VAIL PASS AUX BE F-12-AT PHAS					
	WEIGHTED AVERAGE FOR THE THIRD QUARTER			6.00	20736.60	20736.60	20736.60
	WEIGHTED AVERAGE FOR THE YEAR			14.00	19281.40	19281.40	19281.40
=====	604-39050	MH (TMS)		Each	=====	=====	=====
NHM765-007			03/31/22	2.00	10000.00	19843.90	17841.00
	WEIGHTED AVERAGE FOR THE FIRST QUARTER			2.00	10000.00	19843.90	17841.00
STM1151-038		SH115 MP 27 TO MP 38	04/21/22	5.00	7600.00	11572.04	11152.00
	WEIGHTED AVERAGE FOR THE SECOND QUARTER			5.00	7600.00	11572.04	11152.00
	WEIGHTED AVERAGE FOR THE YEAR			7.00	8285.71	13173.04	13063.14

COLORADO DEPARTMENT OF TRANSPORTATION
ITEM UNIT COSTS BY PROJECTS -- 2022 COST DATA

11:31 Wednesday, March 8, 2023 339

PROJECT NUMBER	ITEM NUMBER/ PROJECT LOCATION	ITEM DESCRIPTION/ PROJECT LOCATION	DATE LET	UNIT/ QUANTITY	ENGR. EST.	AVERAGE BID	AWARDED BID
=====	604-83108	8 In PPS (PVC)		Lin Foot	=====		
2670703-479		I-70 BRIDGE OVER HARLAN	05/05/22	660.00	75.00	167.40	195.00
		WEIGHTED AVERAGE FOR THE SECOND QUARTER		660.00	75.00	167.40	195.00
		WEIGHTED AVERAGE FOR THE YEAR		660.00	75.00	164.96	180.13
=====	605-00040	4 In PP Underdrain		Lin Foot	=====		
FBR0761-236		I-76 OVER CLR CRK SCOUR MIT	08/25/22	168.00	40.00	58.50	50.00
		WEIGHTED AVERAGE FOR THE THIRD QUARTER		168.00	40.00	58.50	50.00
		WEIGHTED AVERAGE FOR THE YEAR		168.00	40.00	58.50	50.00
=====	605-00060	6 In PP Underdrain		Lin Foot	=====		
NHPP0702-413		VAIL PASS AUX PHASE 1 CAP 2	04/18/22	51.00	12.22	12.22	12.22
		WEIGHTED AVERAGE FOR THE SECOND QUARTER		51.00	12.22	12.22	12.22
NHPP0702-414 FBR0702-423		VAIL PASS AUX PHASE 1 CAP 3 VAIL PASS AUX BE F-12-AT PHAS	07/08/22	52.00	19.66	19.66	19.66
		WEIGHTED AVERAGE FOR THE THIRD QUARTER		52.00	19.66	19.66	19.66
		WEIGHTED AVERAGE FOR THE YEAR		103.00	15.98	15.98	15.98
=====	605-00061	6 In PP Underdrain (Special)		Lin Foot	=====		
2670403-065		US40_FLOYD HILL ROUNDABOUTS	09/15/22	1,060.00	60.00	30.24	34.00
		WEIGHTED AVERAGE FOR THE THIRD QUARTER		1,060.00	60.00	30.24	34.00
		WEIGHTED AVERAGE FOR THE YEAR		1,060.00	60.00	30.24	34.00
=====	605-01020	2 In Hor Drain		Lin Foot	=====		
NHPP0702-414		VAIL PASS AUX PHASE 1 CAP 3	07/08/22	2,792.00	67.44	67.44	67.44

COLORADO DEPARTMENT OF TRANSPORTATION
ITEM UNIT COSTS BY PROJECTS -- 2022 COST DATA

11:31 Wednesday, March 8, 2023 340

PROJECT NUMBER	ITEM NUMBER/ PROJECT LOCATION	ITEM DESCRIPTION/ PROJECT LOCATION	DATE LET	UNIT/ QUANTITY	ENGR. EST.	AVERAGE BID	AWARDED BID
=====	605-01020	2 In Hor Drain		Lin Foot	=====	=====	=====
FBR0702-423		VAIL PASS AUX BE F-12-AT PHAS					
	WEIGHTED AVERAGE FOR THE THIRD QUARTER			2,792.00	67.44	67.44	67.44
	WEIGHTED AVERAGE FOR THE YEAR			2,792.00	67.44	67.44	67.44
=====	605-01030	3 In Hor Drain		Lin Foot	=====	=====	=====
NHPP0702-414		VAIL PASS AUX PHASE 1 CAP 3	07/08/22	5,265.00	85.11	85.11	85.11
FBR0702-423		VAIL PASS AUX BE F-12-AT PHAS					
	WEIGHTED AVERAGE FOR THE THIRD QUARTER			5,265.00	85.11	85.11	85.11
	WEIGHTED AVERAGE FOR THE YEAR			5,265.00	85.11	85.11	85.11
=====	605-82100	Pipe Edge Drain		Lin Foot	=====	=====	=====
NHPP0702-414		VAIL PASS AUX PHASE 1 CAP 3	07/08/22	1,036.00	71.26	71.26	71.26
FBR0702-423		VAIL PASS AUX BE F-12-AT PHAS					
	WEIGHTED AVERAGE FOR THE THIRD QUARTER			1,036.00	71.26	71.26	71.26
	WEIGHTED AVERAGE FOR THE YEAR			1,036.00	71.26	71.26	71.26
=====	605-83000	Geocomp Drain		Sq Yard	=====	=====	=====
NHPP0253-275		I-25 EXPRESS LANES SEGMENT 5	03/11/22	32.00	87.10	115.22	115.22
	WEIGHTED AVERAGE FOR THE FIRST QUARTER			32.00	87.10	115.22	115.22
	WEIGHTED AVERAGE FOR THE YEAR			32.00	87.10	115.22	115.22
=====	605-83002	Geocomp Drain (w/ Pipe)		Sq Yard	=====	=====	=====
NH0504-911			04/07/22	68.00	40.00	54.30	53.60
NHPP0702-413		VAIL PASS AUX PHASE 1 CAP 2	04/18/22	210.00	44.79	44.79	44.79
2670703-479		I-70 BRIDGE OVER HARLAN	05/05/22	127.00	30.00	87.29	46.58
	WEIGHTED AVERAGE FOR THE SECOND QUARTER			405.00	39.35	75.19	46.83
	WEIGHTED AVERAGE FOR THE YEAR			405.00	39.35	75.19	46.83

COLORADO DEPARTMENT OF TRANSPORTATION
 ITEM UNIT COSTS BY PROJECTS -- 2022 COST DATA

11:31 Wednesday, March 8, 2023 341

PROJECT NUMBER	ITEM NUMBER/ PROJECT LOCATION	ITEM DESCRIPTION/ PROJECT LOCATION	DATE LET	UNIT/ QUANTITY	ENGR. EST.	AVERAGE BID	AWARDED BID
=====	605-84000	Subsurface Drain Outlet		Lin Foot	=====		
NHPP0702-413		VAIL PASS AUX PHASE 1 CAP 2	04/18/22	618.00	25.99	25.99	25.99
		WEIGHTED AVERAGE FOR THE SECOND QUARTER		618.00	25.99	25.99	25.99
NHPP0702-414 FBR0702-423		VAIL PASS AUX PHASE 1 CAP 3 VAIL PASS AUX BE F-12-AT PHAS	07/08/22	284.00	48.64	48.64	48.64
		WEIGHTED AVERAGE FOR THE THIRD QUARTER		284.00	48.64	48.64	48.64
		WEIGHTED AVERAGE FOR THE YEAR		902.00	33.12	33.12	33.12
=====	605-84100	Subsurface Drain Outlet Str		Each	=====		
NHPP0702-413		VAIL PASS AUX PHASE 1 CAP 2	04/18/22	1.00	1838.72	1838.72	1838.72
		WEIGHTED AVERAGE FOR THE SECOND QUARTER		1.00	1838.72	1838.72	1838.72
NHPP0702-414 FBR0702-423		VAIL PASS AUX PHASE 1 CAP 3 VAIL PASS AUX BE F-12-AT PHAS	07/08/22	1.00	1878.18	1878.18	1878.18
		WEIGHTED AVERAGE FOR THE THIRD QUARTER		1.00	1878.18	1878.18	1878.18
		WEIGHTED AVERAGE FOR THE YEAR		2.00	1858.45	1858.45	1858.45
=====	606-00301	Gdrail Ty 3 (6-3)		Lin Foot	=====		
C0762-055 STR092A-031			02/17/22 03/17/22	1,175.00 2,525.00	30.00 45.00	36.83 42.00	38.00 42.00
		WEIGHTED AVERAGE FOR THE FIRST QUARTER		3,700.00	40.24	38.63	40.73
2670703-479 NHPP 3851-018		I-70 BRIDGE OVER HARLAN US 385 NORTH OF CHEYENNE WELL	05/05/22 05/26/22	325.00 462.50	40.00 38.00	77.46 55.00	85.28 60.00
		WEIGHTED AVERAGE FOR THE SECOND QUARTER		787.50	38.83	70.23	70.43

COLORADO DEPARTMENT OF TRANSPORTATION
 ITEM UNIT COSTS BY PROJECTS -- 2022 COST DATA

11:31 Wednesday, March 8, 2023 342

PROJECT NUMBER	ITEM NUMBER/ PROJECT LOCATION	ITEM DESCRIPTION/ PROJECT LOCATION	DATE LET	UNIT/ QUANTITY	ENGR. EST.	AVERAGE BID	AWARDED BID
=====	606-00301	Gd rail Ty 3 (6-3)		Lin Foot	=====		
STA207A-004		Resurfacing SH207A MANZANOLA	10/27/22	1,587.50	40.00	48.13	43.40
TRG0253-264		I-25 AND SH 119 PARK-N-RIDE	10/27/22	200.00	30.00	58.96	57.00
STRC090-011		US 50B AND SH71/CR18 INTERSEC	11/17/22	387.50	47.50	81.50	82.00
STA0711-021		SH71: REGION LINE NORTH	12/01/22	550.00	41.00	45.00	44.00
NHPP0931-033		SH93:US6 TO 58TH RESURFACING	12/15/22	2,762.00	45.00	42.03	34.10
STR0092-024		SH 9 North of Silverthorne	12/22/22	5,716.00	50.00	56.10	52.20
		WEIGHTED AVERAGE FOR THE FOURTH QUARTER		11,203.00	46.46	50.10	47.20
		WEIGHTED AVERAGE FOR THE YEAR		15,690.50	44.61	49.50	46.84
=====	606-00302	Gd rail Ty 3 (31 In MGS)		Lin Foot	=====		
NH0504-910		US50B L-24-B MIN REP AT MP 40	01/13/22	800.00	60.00	51.79	51.94
NHPP0702-383		I-70 EB AUX FRISCO TO SILVERT	01/13/22	5,530.00	40.00	51.83	52.00
NHPP1601-083			02/03/22	10,812.50	40.00	38.50	38.00
STA0252-459			02/03/22	5,250.00	36.00	37.96	32.60
STA 067A-048		Hwy 67A MP 0.00 TO MP 11.05 I	03/03/22	2,167.00	50.00	41.34	43.00
NHPP 0761-238		I-76 DAHLIA TO YORK	03/10/22	10,803.00	40.00	38.72	37.50
C0761-239							
STR160A-034		US160A LA VETA PASS EAST SURF	03/17/22	14,475.00	30.00	42.26	38.51
		WEIGHTED AVERAGE FOR THE FIRST QUARTER		49,837.50	37.43	41.56	39.47
NH0504-911			04/07/22	7,200.00	27.41	43.00	43.00
STM1151-038		SH115 MP 27 TO MP 38	04/21/22	21,800.00	32.00	35.04	29.40
STA0712-019		SH 71: Frieight Improvements	05/12/22	3,438.00	35.00	39.01	39.01
ITS 0741-024		VMS SIGN INSTALLATIONS AND VS	06/02/22	425.00	30.00	61.00	57.00
NHPP072A-047		SH-72 RESURFACING: I-70 TO IN	06/09/22	768.00	35.00	68.47	68.47
MTCE0253-291		I-25 SIGN REPLACEMENT PHASE 2	06/16/22	3,913.00	42.00	49.46	45.91
		WEIGHTED AVERAGE FOR THE SECOND QUARTER		37,544.00	32.48	37.16	35.72
NHPP0702-414		VAIL PASS AUX PHASE 1 CAP 3	07/08/22	50.00	109.42	109.42	109.42
FBR0702-423		VAIL PASS AUX BE F-12-AT PHAS					
ER0502-092		US 50 MP 204 EB MONARCH TRUCK	08/29/22	387.50	50.00	67.16	73.77

PROJECT NUMBER	ITEM NUMBER/ PROJECT LOCATION	ITEM DESCRIPTION/ PROJECT LOCATION	DATE LET	UNIT/ QUANTITY	ENGR. EST.	AVERAGE BID	AWARDED BID
===== 606-00302							
		Gd rail Ty 3 (31 In MGS)		Lin Foot			
BR0343-046		US 34 TIMBER BRIDGE REPL. PKG	08/31/22	400.00	53.60	84.37	84.37
FBR0343-047		US 6/US 34 TIMBER BRIDGE REPL					
PAN0761-245		ALONG I-76 & RAMPS MILEPOST 9	09/01/22	150.00	50.00	56.90	38.80
2670403-065		US40_FLOYD HILL ROUNDABOUTS	09/15/22	1,775.00	45.00	50.13	47.00
2670703-497		I-70_GENESEE WILDLIFE XING	09/15/22	3,975.00	40.00	50.22	51.12
NHPP0701-231		I-70 SALT WASH BRIDGES SCOUR	09/29/22	125.00	50.00	71.54	75.00
		WEIGHTED AVERAGE FOR THE THIRD QUARTER		6,862.50	43.56	51.45	53.86
NHPP0701-253		I-70 EAST OF DEBEQUE	10/27/22	10,593.00	50.00	35.40	37.00
C170A-002		CRITICAL CULVERT CONST. PKG D	10/27/22	581.25	60.00	57.21	54.83
STU0252-457		I-25:ALAMEDA RIVER PH 2.0	11/03/22	50.00	150.00	129.53	114.00
SHE0242-087		US 24 SAFETY IMPRVMTS, E OF	11/03/22	1,750.00	50.00	43.72	41.15
STR064A-010		SH 64 AND SH 13 AT MEEKER	11/10/22	1,275.00	55.00	40.25	41.00
C5502-097		US550 MP 117.28-126.06	11/17/22	8,081.25	50.00	38.87	36.20
STAM420-001		US 285 AT HWY 9C IMPROVEMENTS	12/01/22	1,350.00	30.00	43.92	52.88
BR2854-148		INTERSECTION OF US 285 & SH 9					
STM0091-046		ADA RAMP IMPROVEMENTS - FAIRP					
STR114A-015		SH114 SILLSVILLE SOUTH TO MP3	12/01/22	400.00	50.00	60.00	60.00
2670703-487		I-70 BRIDGES OVER WARD ROAD-	12/01/22	3,164.00	50.00	42.42	42.00
NHPP0701-252		I-70 RIFLE TO SILT SLAB REPLA	12/01/22	10,968.00	55.00	38.30	32.60
IM025A-050		I25-MP103.9 - INTERSECTION DR	12/01/22	1,681.00	40.00	41.33	40.00
NHPP0063-048		US6 / 20 ROAD INTERSECTION IM	12/15/22	456.00	80.00	58.41	46.75
NHPP0502-090		SH 50 MP 134.6-136 GUNNISON C	12/22/22	1,450.00	50.00	53.32	54.85
STA0361-129		US 36: HYGIENE RD AND NELSON	12/22/22	650.00	50.00	41.65	44.29
BR012A-048		CO 12 STRUCTURE P-17-F AT MP	12/22/22	150.00	55.00	90.80	126.00
STA385A-016		SH 385 MP 97.76	12/22/22	200.00	35.00	67.92	46.67
STR096A-050		SH 96 MP 168.99 TO 193.77	12/22/22	1,187.50	40.00	50.33	66.00
		WEIGHTED AVERAGE FOR THE FOURTH QUARTER		43,987.00	50.63	41.73	39.75
		WEIGHTED AVERAGE FOR THE YEAR		138,231.00	40.59	41.12	39.28
===== 606-00305							
		Gd rail Ty 3 (Spec)		Lin Foot			
NHPP0702-383		I-70 EB AUX FRISCO TO SILVERT	01/13/22	914.00	60.00	54.92	55.00
NHPP 0761-238		I-76 DAHLIA TO YORK	03/10/22	1,584.00	52.00	45.43	41.00
C0761-239							
		WEIGHTED AVERAGE FOR THE FIRST QUARTER		2,498.00	54.93	47.94	46.12
IM025A-050		I25-MP103.9 - INTERSECTION DR	12/01/22	7.00	80.00	81.67	79.00
		WEIGHTED AVERAGE FOR THE FOURTH QUARTER		7.00	80.00	81.67	79.00
		WEIGHTED AVERAGE FOR THE YEAR		2,505.00	55.00	47.98	46.21

COLORADO DEPARTMENT OF TRANSPORTATION
ITEM UNIT COSTS BY PROJECTS -- 2022 COST DATA

11:31 Wednesday, March 8, 2023 344

PROJECT NUMBER	ITEM NUMBER/ PROJECT LOCATION	ITEM DESCRIPTION/ PROJECT LOCATION	DATE LET	UNIT/ QUANTITY	ENGR. EST.	AVERAGE BID	AWARDED BID
===== 606-00350 Gdrail Ty 3 (D) (6-3) Lin Foot =====							
NHPP 0761-238 C0761-239		I-76 DAHLIA TO YORK	03/10/22	564.00	58.00	67.83	69.00
		WEIGHTED AVERAGE FOR THE FIRST QUARTER		564.00	58.00	67.83	69.00
NHPP0701-231		I-70 SALT WASH BRIDGES SCOUR	09/29/22	300.00	100.00	106.30	112.00
		WEIGHTED AVERAGE FOR THE THIRD QUARTER		300.00	100.00	106.30	112.00
2670703-487		I-70 BRIDGES OVER WARD ROAD-	12/01/22	125.00	100.00	58.75	58.00
		WEIGHTED AVERAGE FOR THE FOURTH QUARTER		125.00	100.00	58.75	58.00
		WEIGHTED AVERAGE FOR THE YEAR		989.00	76.05	70.87	80.65
===== 606-00710 Gdrail Ty 7 (Sty CA) Lin Foot =====							
M R100-351		FY22 R1 SIGN STRUCTURE REPLAC	03/17/22	494.00	300.00	248.00	280.00
		WEIGHTED AVERAGE FOR THE FIRST QUARTER		494.00	300.00	248.00	280.00
STR064A-010 STR0092-024		SH 64 AND SH 13 AT MEEKER	11/10/22	520.00	400.00	151.50	165.00
		SH 9 North of Silverthorne	12/22/22	563.00	50.00	504.00	208.00
		WEIGHTED AVERAGE FOR THE FOURTH QUARTER		1,083.00	218.05	334.75	187.35
		WEIGHTED AVERAGE FOR THE YEAR		1,577.00	243.72	307.57	216.38
===== 606-00910 Guardrail Type 9 (Style CA) Lin Foot =====							
NHPP0702-383 NHPP 0761-238 C0761-239		I-70 EB AUX FRISCO TO SILVERT	01/13/22	803.00	150.00	213.02	165.00
		I-76 DAHLIA TO YORK	03/10/22	1,414.00	140.00	116.85	90.00

COLORADO DEPARTMENT OF TRANSPORTATION
 ITEM UNIT COSTS BY PROJECTS -- 2022 COST DATA

11:31 Wednesday, March 8, 2023 345

PROJECT NUMBER	ITEM NUMBER/ PROJECT LOCATION	ITEM DESCRIPTION/ PROJECT LOCATION	DATE LET	UNIT/ QUANTITY	ENGR. EST.	AVERAGE BID	AWARDED BID
=====	606-00910	Guardrail Type 9 (Style CA)		Lin Foot	=====	=====	=====
NHPP0703-472			03/10/22	584.00	160.00	1461.79	440.00
	WEIGHTED AVERAGE FOR THE FIRST QUARTER			2,801.00	147.04	316.58	184.48
STM1151-038		SH115 MP 27 TO MP 38	04/21/22	2,743.00	125.00	171.89	150.00
2670703-479		I-70 BRIDGE OVER HARLAN	05/05/22	3,235.00	110.00	117.79	120.00
	WEIGHTED AVERAGE FOR THE SECOND QUARTER			5,978.00	116.88	140.19	133.77
NHPP0702-414		VAIL PASS AUX PHASE 1 CAP 3	07/08/22	1,295.00	197.39	197.39	197.39
FBR0702-423		VAIL PASS AUX BE F-12-AT PHAS					
	WEIGHTED AVERAGE FOR THE THIRD QUARTER			1,295.00	197.39	197.39	197.39
TRG0253-264		I-25 AND SH 119 PARK-N-RIDE	10/27/22	211.00	100.00	217.38	190.00
C5502-097		US550 MP 117.28-126.06	11/17/22	331.00	400.00	287.69	351.00
	WEIGHTED AVERAGE FOR THE FOURTH QUARTER			542.00	283.21	243.42	288.32
	WEIGHTED AVERAGE FOR THE YEAR			10,616.00	143.15	203.49	162.80
=====	606-00915	Guardrail Type 9 (Style CG)		Lin Foot	=====	=====	=====
NHPP 0761-238		I-76 DAHLIA TO YORK	03/10/22	8,760.00	155.00	117.08	96.00
C0761-239							
	WEIGHTED AVERAGE FOR THE FIRST QUARTER			8,760.00	155.00	117.08	96.00
NHPP0702-414		VAIL PASS AUX PHASE 1 CAP 3	07/08/22	1,597.00	237.64	237.64	237.64
FBR0702-423		VAIL PASS AUX BE F-12-AT PHAS					
	WEIGHTED AVERAGE FOR THE THIRD QUARTER			1,597.00	237.64	237.64	237.64
2670703-487		I-70 BRIDGES OVER WARD ROAD-	12/01/22	370.00	300.00	196.85	150.00
	WEIGHTED AVERAGE FOR THE FOURTH QUARTER			370.00	300.00	196.85	150.00
	WEIGHTED AVERAGE FOR THE YEAR			10,727.00	172.30	121.70	118.95

COLORADO DEPARTMENT OF TRANSPORTATION
 ITEM UNIT COSTS BY PROJECTS -- 2022 COST DATA

11:31 Wednesday, March 8, 2023 346

PROJECT NUMBER	ITEM NUMBER/ PROJECT LOCATION	ITEM DESCRIPTION/ PROJECT LOCATION	DATE LET	UNIT/ QUANTITY	ENGR. EST.	AVERAGE BID	AWARDED BID
=====	606-00916	Guardrail Type 9 (Style CA) (Special)		Lin Foot	=====		
NHPP0702-383		I-70 EB AUX FRISCO TO SILVERT	01/13/22	575.00	175.00	382.21	320.00
		WEIGHTED AVERAGE FOR THE FIRST QUARTER		575.00	175.00	382.21	320.00
2670703-479		I-70 BRIDGE OVER HARLAN	05/05/22	304.00	150.00	279.72	325.00
		WEIGHTED AVERAGE FOR THE SECOND QUARTER		304.00	150.00	279.72	325.00
		WEIGHTED AVERAGE FOR THE YEAR		879.00	166.35	342.43	321.73
=====	606-00917	Guardrail Type 9 (Style CG) (Special)		Lin Foot	=====		
NHPP 0761-238 C0761-239		I-76 DAHLIA TO YORK	03/10/22	186.00	150.00	298.65	235.00
		WEIGHTED AVERAGE FOR THE FIRST QUARTER		186.00	150.00	298.65	235.00
		WEIGHTED AVERAGE FOR THE YEAR		186.00	150.00	298.65	235.00
=====	606-00930	Guardrail Type 9 (Style CD)		Lin Foot	=====		
2670703-479		I-70 BRIDGE OVER HARLAN	05/05/22	596.00	175.00	174.53	155.00
		WEIGHTED AVERAGE FOR THE SECOND QUARTER		596.00	175.00	174.53	155.00
2670703-487		I-70 BRIDGES OVER WARD ROAD-	12/01/22	410.00	160.00	144.61	120.00
		WEIGHTED AVERAGE FOR THE FOURTH QUARTER		410.00	160.00	144.61	120.00
		WEIGHTED AVERAGE FOR THE YEAR		1,006.00	168.89	163.63	140.74
=====	606-00931	Guardrail Type 9 (Style CD) (Special)		Lin Foot	=====		
NHPP 0761-238		I-76 DAHLIA TO YORK	03/10/22	80.00	175.00	299.38	370.00

COLORADO DEPARTMENT OF TRANSPORTATION
 ITEM UNIT COSTS BY PROJECTS -- 2022 COST DATA

11:31 Wednesday, March 8, 2023 347

PROJECT NUMBER	ITEM NUMBER/ PROJECT LOCATION	ITEM DESCRIPTION/ PROJECT LOCATION	DATE LET	UNIT/ QUANTITY	ENGR. EST.	AVERAGE BID	AWARDED BID
=====	606-00931	Guardrail Type 9 (Style CD) (Special)		Lin Foot	=====		
C0761-239							
		WEIGHTED AVERAGE FOR THE FIRST QUARTER		80.00	175.00	299.38	370.00
2670703-479		I-70 BRIDGE OVER HARLAN	05/05/22	35.00	220.00	299.67	200.84
		WEIGHTED AVERAGE FOR THE SECOND QUARTER		35.00	220.00	299.67	200.84
		WEIGHTED AVERAGE FOR THE YEAR		115.00	188.70	299.45	318.52
=====	606-00940	Guardrail Type 9 (Style CE)		Lin Foot	=====		
NHPP0702-383		I-70 EB AUX FRISCO TO SILVERT	01/13/22	676.00	225.00	516.12	570.00
NHPP 0761-238		I-76 DAHLIA TO YORK	03/10/22	521.00	170.00	241.76	180.00
C0761-239							
		WEIGHTED AVERAGE FOR THE FIRST QUARTER		1,197.00	201.06	364.62	400.25
C5502-097		US550 MP 117.28-126.06	11/17/22	1,042.00	400.00	392.08	502.00
		WEIGHTED AVERAGE FOR THE FOURTH QUARTER		1,042.00	400.00	392.08	502.00
		WEIGHTED AVERAGE FOR THE YEAR		2,239.00	293.64	372.66	447.60
=====	606-01320	End Anchor Ty 3B		Each	=====		
C170A-002		CRITICAL CULVERT CONST. PKG D	10/27/22	4.00	4200.00	4582.92	4366.67
STR0092-024		SH 9 North of Silverthorne	12/22/22	2.00	6000.00	7500.00	2240.00
STA0361-129		US 36: HYGIENE RD AND NELSON	12/22/22	1.00	4500.00	2721.93	2531.65
		WEIGHTED AVERAGE FOR THE FOURTH QUARTER		7.00	4757.14	4677.45	3496.90
		WEIGHTED AVERAGE FOR THE YEAR		7.00	4757.14	4677.45	3496.90
=====	606-01340	End Anchor Ty 3D		Each	=====		
NHPP0702-383		I-70 EB AUX FRISCO TO SILVERT	01/13/22	8.00	1800.00	2077.86	1600.00

COLORADO DEPARTMENT OF TRANSPORTATION
ITEM UNIT COSTS BY PROJECTS -- 2022 COST DATA

11:31 Wednesday, March 8, 2023 348

PROJECT NUMBER	ITEM NUMBER/ PROJECT LOCATION	ITEM DESCRIPTION/ PROJECT LOCATION	DATE LET	UNIT/ QUANTITY	ENGR. EST.	AVERAGE BID	AWARDED BID
=====	606-01340	End Anchor Ty 3D		Each =====			
STA0252-459			02/03/22	3.00	920.00	1515.33	1418.00
C0762-055			02/17/22	2.00	2000.00	1758.28	1400.00
NHPP 0761-238	I-76 DAHLIA TO YORK		03/10/22	5.00	1800.00	1170.05	1100.00
C0761-239							
	WEIGHTED AVERAGE FOR THE FIRST QUARTER			18.00	1675.56	1624.95	1408.56
STM1151-038	SH115 MP 27 TO MP 38		04/21/22	1.00	2200.00	1851.05	1280.00
STA0712-019	SH 71: Frieight Improvements		05/12/22	3.00	1300.00	2142.76	2142.76
ITS 0741-024	VMS SIGN INSTALLATIONS AND VS		06/02/22	2.00	2000.00	3076.00	3784.00
MTCE0253-291	I-25 SIGN REPLACEMENT PHASE 2		06/16/22	15.00	2000.00	2028.06	1891.12
	WEIGHTED AVERAGE FOR THE SECOND QUARTER			21.00	1909.52	2114.98	2078.24
ER0502-092	US 50 MP 204 EB MONARCH TRUCK		08/29/22	2.00	2000.00	3140.17	4600.52
2670703-497	I-70_GENESEE WILDLIFE XING		09/15/22	5.00	1600.00	1790.48	1795.84
	WEIGHTED AVERAGE FOR THE THIRD QUARTER			7.00	1714.29	1988.00	2597.18
NHPP0701-253	I-70 EAST OF DEBEQUE		10/27/22	11.00	2000.00	1830.00	1560.00
C5502-097	US550 MP 117.28-126.06		11/17/22	2.00	2000.00	2458.13	2680.00
2670703-487	I-70 BRIDGES OVER WARD ROAD-		12/01/22	3.00	1800.00	1279.21	1270.00
NHPP0701-252	I-70 RIFLE TO SILT SLAB REPLA		12/01/22	9.00	2000.00	1900.00	2100.00
IM025A-050	I25-MP103.9 - INTERSECTION DR		12/01/22	4.00	1700.00	1333.33	1300.00
NHPP0063-048	US6 / 20 ROAD INTERSECTION IM		12/15/22	1.00	2000.00	3098.94	2843.00
	WEIGHTED AVERAGE FOR THE FOURTH QUARTER			30.00	1940.00	1649.82	1661.54
	WEIGHTED AVERAGE FOR THE YEAR			76.00	1848.16	1756.68	1785.06
=====	606-01370	Transition Ty 3G		Each =====			
NHPP2873-189	US 287 (FEDERAL BLVD) - COLFA		01/06/22	1.00	3000.00	12442.37	6145.29
NHPP0702-383	I-70 EB AUX FRISCO TO SILVERT		01/13/22	7.00	2800.00	5232.74	5400.00
NHPP1601-083			02/03/22	8.00	4000.00	4520.46	4200.00
C0762-055			02/17/22	4.00	3000.00	3845.15	3900.00
STA 067A-048	Hwy 67A MP 0.00 TO MP 11.05 I		03/03/22	12.00	3000.00	4178.98	4000.00

COLORADO DEPARTMENT OF TRANSPORTATION
 ITEM UNIT COSTS BY PROJECTS -- 2022 COST DATA

11:31 Wednesday, March 8, 2023 349

PROJECT NUMBER	ITEM NUMBER/ PROJECT LOCATION	ITEM DESCRIPTION/ PROJECT LOCATION	DATE LET	UNIT/ QUANTITY	ENGR. EST.	AVERAGE BID	AWARDED BID
=====	606-01370	Transition Ty 3G		Each =====			
NHPP 0761-238		I-76 DAHLIA TO YORK	03/10/22	11.00	3200.00	4726.44	4500.00
C0761-239							
NHPP0703-472			03/10/22	2.00	2100.00	7179.33	6750.00
		WEIGHTED AVERAGE FOR THE FIRST QUARTER		45.00	3155.56	4879.66	4536.56
NH0504-911			04/07/22	13.00	3000.00	3975.00	3950.00
STM1151-038		SH115 MP 27 TO MP 38	04/21/22	37.00	3300.00	3979.09	3375.00
2670703-479		I-70 BRIDGE OVER HARLAN	05/05/22	3.00	3200.00	4193.14	4732.34
NHPP 3851-018		US 385 NORTH OF CHEYENNE WELL	05/26/22	4.00	3300.00	6750.00	7000.00
NHPP072A-047		SH-72 RESURFACING: I-70 TO IN	06/09/22	4.00	3500.00	5005.38	5005.38
		WEIGHTED AVERAGE FOR THE SECOND QUARTER		61.00	3244.26	4103.65	3908.91
NHPP0702-414		VAIL PASS AUX PHASE 1 CAP 3	07/08/22	2.00	7776.98	7776.98	7776.98
FBR0702-423		VAIL PASS AUX BE F-12-AT PHAS					
2670403-065		US40 FLOYD HILL ROUNDABOUTS	09/15/22	4.00	5000.00	5267.45	4900.00
2670703-497		I-70 GENESEE WILDLIFE KING	09/15/22	4.00	3500.00	5897.79	6401.85
NHPP0701-231		I-70 SALT WASH BRIDGES SCOUR	09/29/22	1.00	5000.00	6507.46	7150.00
		WEIGHTED AVERAGE FOR THE THIRD QUARTER		11.00	4959.45	5839.01	6173.76
NHPP0701-253		I-70 EAST OF DEBEQUE	10/27/22	4.00	5000.00	3954.50	3809.00
STA207A-004		Resurfacing SH207A MANZANOLA	10/27/22	4.00	4000.00	4800.00	5300.00
TRG0253-264		I-25 AND SH 119 PARK-N-RIDE	10/27/22	1.00	3000.00	4481.24	4700.00
STR064A-010		SH 64 AND SH 13 AT MEEKER	11/10/22	8.00	7000.00	4695.00	4800.00
C5502-097		US550 MP 117.28-126.06	11/17/22	9.00	8000.00	4878.07	4540.00
STAM420-001		US 285 AT HWY 9C IMPROVEMENTS	12/01/22	2.00	3050.00	4584.20	5509.26
BR2854-148		INTERSECTION OF US 285 & SH 9					
STM0091-046		ADA RAMP IMPROVEMENTS - FAIRP					
STA0711-021		SH71: REGION LINE NORTH	12/01/22	8.00	3400.00	4120.00	4000.00
STR114A-015		SH114 SILLSVILLE SOUTH TO MP3	12/01/22	15.00	4000.00	5775.00	6000.00
2670703-487		I-70 BRIDGES OVER WARD ROAD-	12/01/22	3.00	5000.00	3990.10	3950.00
NHPP0701-252		I-70 RIFLE TO SILT SLAB REPLA	12/01/22	26.00	4500.00	4188.00	3861.00
IM025A-050		I25-MP103.9 - INTERSECTION DR	12/01/22	3.00	2750.00	4100.00	3900.00
NHPP0063-048		US6 / 20 ROAD INTERSECTION IM	12/15/22	1.00	5000.00	5571.72	4745.00
NHPP0931-033		SH93:US6 TO 58TH RESURFACING	12/15/22	4.00	3000.00	3949.50	3140.00
STR0092-024		SH 9 North of Silverthorne	12/22/22	41.00	7000.00	8385.00	4970.00
BR012A-048		CO 12 STRUCTURE P-17-F AT MP	12/22/22	4.00	3300.00	4676.19	5000.00

COLORADO DEPARTMENT OF TRANSPORTATION
 ITEM UNIT COSTS BY PROJECTS -- 2022 COST DATA

11:31 Wednesday, March 8, 2023 350

PROJECT NUMBER	ITEM NUMBER/ PROJECT LOCATION	ITEM DESCRIPTION/ PROJECT LOCATION	DATE LET	UNIT/ QUANTITY	ENGR. EST.	AVERAGE BID	AWARDED BID
===== 606-01370	STR096A-050	Transition Ty 3G SH 96 MP 168.99 TO 193.77	12/22/22	Each 4.00	3500.00	3625.00	4000.00
		WEIGHTED AVERAGE FOR THE FOURTH QUARTER		137.00	5341.24	5369.06	4602.28
		WEIGHTED AVERAGE FOR THE YEAR		254.00	4433.87	4912.89	4494.71
===== 606-01371	STR092A-031	Transition Ty 3G (Spec)	03/17/22	Each 4.00	4000.00	5000.00	5000.00
		WEIGHTED AVERAGE FOR THE FIRST QUARTER		4.00	4000.00	5000.00	5000.00
STR114A-015 NHPP0701-252		SH114 SILLSVILLE SOUTH TO MP3 I-70 RIFLE TO SILT SLAB REPLA	12/01/22 12/01/22	9.00 12.00	5000.00 5000.00	5307.50 2440.00	5500.00 3000.00
		WEIGHTED AVERAGE FOR THE FOURTH QUARTER		21.00	5000.00	3668.93	4071.43
		WEIGHTED AVERAGE FOR THE YEAR		25.00	4840.00	3784.67	4220.00
===== 606-01372	NHPP0702-383 NHPP 0761-238 C0761-239 NHPP0703-472	Transition Type GR9-GR3 I-70 EB AUX FRISCO TO SILVERT I-76 DAHLIA TO YORK	01/13/22 03/10/22	4.00 1.00	1800.00 5000.00	8086.92 6555.57	8800.00 5900.00
		WEIGHTED AVERAGE FOR THE FIRST QUARTER	03/10/22	2.00	3500.00	7092.16	6750.00
		WEIGHTED AVERAGE FOR THE FIRST QUARTER		7.00	2742.86	7525.56	7800.00
STM1151-038 2670703-479		SH115 MP 27 TO MP 38 I-70 BRIDGE OVER HARLAN	04/21/22 05/05/22	11.00 3.00	6000.00 6500.00	8104.64 10087.37	3000.00 21228.78
		WEIGHTED AVERAGE FOR THE SECOND QUARTER		14.00	6107.14	8593.53	6906.17
NHPP0702-414 FBR0702-423		VAIL PASS AUX PHASE 1 CAP 3 VAIL PASS AUX BE F-12-AT PHAS	07/08/22	1.00	4353.81	4353.81	4353.81
		WEIGHTED AVERAGE FOR THE THIRD QUARTER		1.00	4353.81	4353.81	4353.81

COLORADO DEPARTMENT OF TRANSPORTATION
ITEM UNIT COSTS BY PROJECTS -- 2022 COST DATA

11:31 Wednesday, March 8, 2023 351

PROJECT NUMBER	ITEM NUMBER/ PROJECT LOCATION	ITEM DESCRIPTION/ PROJECT LOCATION	DATE LET	UNIT/ QUANTITY	ENGR. EST.	AVERAGE BID	AWARDED BID
=====	606-01372	Transition Type GR9-GR3		Each	=====		
2670703-487		I-70 BRIDGES OVER WARD ROAD-	12/01/22	2.00	10000.00	8707.94	4410.00
	WEIGHTED AVERAGE FOR THE FOURTH QUARTER			2.00	10000.00	8707.94	4410.00
	WEIGHTED AVERAGE FOR THE YEAR			24.00	5377.24	8247.34	6852.51
=====	606-01380	Transition Ty 3H		Each	=====		
NHPP0702-383		I-70 EB AUX FRISCO TO SILVERT	01/13/22	5.00	1800.00	2342.83	2500.00
C0762-055			02/17/22	2.00	1500.00	1554.55	1700.00
NHPP 0761-238		I-76 DAHLIA TO YORK	03/10/22	9.00	1800.00	1723.39	1600.00
C0761-239							
	WEIGHTED AVERAGE FOR THE FIRST QUARTER			16.00	1762.50	1858.01	1893.75
NH0504-911			04/07/22	8.00	2000.00	1630.00	1560.00
2670703-479		I-70 BRIDGE OVER HARLAN	05/05/22	1.00	3000.00	1585.00	1793.12
	WEIGHTED AVERAGE FOR THE SECOND QUARTER			9.00	2111.11	1617.73	1585.90
2670703-497		I-70_GENESEE WILDLIFE KING	09/15/22	4.00	1800.00	2757.93	2656.83
	WEIGHTED AVERAGE FOR THE THIRD QUARTER			4.00	1800.00	2757.93	2656.83
NHPP0701-253		I-70 EAST OF DEBEQUE	10/27/22	4.00	2000.00	1607.50	1725.00
C5502-097		US550 MP 117.28-126.06	11/17/22	3.00	3000.00	2948.96	2740.00
STAM420-001		US 285 AT HWY 9C IMPROVEMENTS	12/01/22	2.00	1950.00	2158.46	2585.27
BR2854-148		INTERSECTION OF US 285 & SH 9					
STM0091-046		ADA RAMP IMPROVEMENTS - FAIRP					
2670703-487		I-70 BRIDGES OVER WARD ROAD-	12/01/22	5.00	2500.00	1584.38	1590.00
NHPP0701-252		I-70 RIFLE TO SILT SLAB REPLA	12/01/22	4.00	3500.00	1925.00	1560.00
IM025A-050		I25-MP103.9 - INTERSECTION DR	12/01/22	2.00	1350.00	1866.67	1800.00
NHPP0063-048		US6 / 20 ROAD INTERSECTION IM	12/15/22	1.00	2000.00	2452.30	1960.00
	WEIGHTED AVERAGE FOR THE FOURTH QUARTER			21.00	2480.95	1952.41	1904.81
	WEIGHTED AVERAGE FOR THE YEAR			50.00	2130.00	1975.37	1904.06

COLORADO DEPARTMENT OF TRANSPORTATION
ITEM UNIT COSTS BY PROJECTS -- 2022 COST DATA

11:31 Wednesday, March 8, 2023 352

PROJECT NUMBER	ITEM NUMBER/ PROJECT LOCATION	ITEM DESCRIPTION/ PROJECT LOCATION	DATE LET	UNIT/ QUANTITY	ENGR. EST.	AVERAGE BID	AWARDED BID
=====	606-01381	Transition Ty 3H (Spec)		Each	=====	=====	=====
NHPP0701-252		I-70 RIFLE TO SILT SLAB REPLA	12/01/22	2.00	5000.00	1605.00	1340.00
		WEIGHTED AVERAGE FOR THE FOURTH QUARTER		2.00	5000.00	1605.00	1340.00
		WEIGHTED AVERAGE FOR THE YEAR		2.00	5000.00	1605.00	1340.00
=====	606-01385	Transition Ty 3J		Each	=====	=====	=====
STA 067A-048		Hwy 67A MP 0.00 TO MP 11.05 I	03/03/22	1.00	4000.00	2435.92	3000.00
STR160A-034		US160A LA VETA PASS EAST SURF	03/17/22	1.00	3000.00	2602.71	2605.42
		WEIGHTED AVERAGE FOR THE FIRST QUARTER		2.00	3500.00	2502.64	2802.71
STM1151-038		SH115 MP 27 TO MP 38	04/21/22	7.00	1900.00	1748.70	1597.00
ITS 0741-024		VMS SIGN INSTALLATIONS AND VS	06/02/22	1.00	2000.00	3335.50	1936.00
		WEIGHTED AVERAGE FOR THE SECOND QUARTER		8.00	1912.50	1834.47	1639.38
2670403-065		US40_FLOYD HILL ROUNDABOUTS	09/15/22	2.00	3500.00	2382.52	2200.00
		WEIGHTED AVERAGE FOR THE THIRD QUARTER		2.00	3500.00	2382.52	2200.00
STA207A-004		Resurfacing SH207A MANZANOLA	10/27/22	5.00	2500.00	2466.67	2500.00
STU0252-457		I-25:ALAMEDA RIVER PH 2.0	11/03/22	2.00	2200.00	4068.57	3300.00
C5502-097		US550 MP 117.28-126.06	11/17/22	3.00	3000.00	3385.60	3150.00
STAM420-001		US 285 AT HWY 9C IMPROVEMENTS	12/01/22	2.00	2600.00	3642.82	4548.42
BR2854-148		INTERSECTION OF US 285 & SH 9					
STM0091-046		ADA RAMP IMPROVEMENTS - FAIRP					
STA0711-021		SH71: REGION LINE NORTH	12/01/22	1.00	2000.00	3475.00	3800.00
STR114A-015		SH114 SILLSVILLE SOUTH TO MP3	12/01/22	1.00	2500.00	4325.00	4500.00
NHPP0502-090		SH 50 MP 134.6-136 GUNNISON C	12/22/22	1.00	2500.00	3996.73	4452.36
STR0092-024		SH 9 North of Silverthorne	12/22/22	4.00	3000.00	5540.00	2180.00
STA0361-129		US 36: HYGIENE RD AND NELSON	12/22/22	1.00	2200.00	4512.91	3704.03
		WEIGHTED AVERAGE FOR THE FOURTH QUARTER		20.00	2615.00	3720.78	3141.16
		WEIGHTED AVERAGE FOR THE YEAR		32.00	2550.00	2950.93	2685.74

COLORADO DEPARTMENT OF TRANSPORTATION
ITEM UNIT COSTS BY PROJECTS -- 2022 COST DATA

11:31 Wednesday, March 8, 2023 353

PROJECT NUMBER	ITEM NUMBER/ PROJECT LOCATION	ITEM DESCRIPTION/ PROJECT LOCATION	DATE LET	UNIT/ QUANTITY	ENGR. EST.	AVERAGE BID	AWARDED BID
===== 606-01390		End Anchor Ty 3K		Each	=====	=====	=====
STR160A-034		US160A LA VETA PASS EAST SURF	03/17/22	1.00	2000.00	1996.65	1993.29
		WEIGHTED AVERAGE FOR THE FIRST QUARTER		1.00	2000.00	1996.65	1993.29
STM1151-038		SH115 MP 27 TO MP 38	04/21/22	7.00	2400.00	2222.92	1849.00
STA0712-019		SH 71: Frieight Improvements	05/12/22	1.00	1800.00	2007.54	2007.54
		WEIGHTED AVERAGE FOR THE SECOND QUARTER		8.00	2325.00	2216.93	1868.82
STA207A-004		Resurfacing SH207A MANZANOLA	10/27/22	5.00	2000.00	3000.00	3200.00
STU0252-457		I-25:ALAMEDA RIVER PH 2.0	11/03/22	1.00	2200.00	3505.76	3000.00
C5502-097		US550 MP 117.28-126.06	11/17/22	4.00	2300.00	3064.50	2850.00
STAM420-001		US 285 AT HWY 9C IMPROVEMENTS	12/01/22	2.00	1900.00	3282.87	3753.49
BR2854-148		INTERSECTION OF US 285 & SH 9					
STM0091-046		ADA RAMP IMPROVEMENTS - FAIRP					
STA0711-021		SH71: REGION LINE NORTH	12/01/22	1.00	2300.00	2845.00	3200.00
STR114A-015		SH114 SILLSVILLE SOUTH TO MP3	12/01/22	2.00	2500.00	3065.00	3200.00
NHPP0502-090		SH 50 MP 134.6-136 GUNNISON C	12/22/22	1.00	2200.00	3528.40	3673.72
STR0092-024		SH 9 North of Silverthorne	12/22/22	4.00	3000.00	6725.00	2950.00
STA0361-129		US 36: HYGIENE RD AND NELSON	12/22/22	1.00	2100.00	3141.12	2979.08
		WEIGHTED AVERAGE FOR THE FOURTH QUARTER		21.00	2323.81	3595.19	3140.94
		WEIGHTED AVERAGE FOR THE YEAR		30.00	2313.33	3072.27	2763.45
===== 606-01400		Transition Type BR10M-GR3		Each	=====	=====	=====
NHPP0701-253		I-70 EAST OF DEBEQUE	10/27/22	8.00	7000.00	16320.00	13800.00
STA207A-004		Resurfacing SH207A MANZANOLA	10/27/22	4.00	4000.00	8826.67	7680.00
STU0252-457		I-25:ALAMEDA RIVER PH 2.0	11/03/22	2.00	10000.00	12165.50	7800.00
C5502-097		US550 MP 117.28-126.06	11/17/22	2.00	7000.00	6938.05	5450.00
STAM420-001		US 285 AT HWY 9C IMPROVEMENTS	12/01/22	4.00	2360.00	5456.07	4831.84
BR2854-148		INTERSECTION OF US 285 & SH 9					
STM0091-046		ADA RAMP IMPROVEMENTS - FAIRP					
STA0711-021		SH71: REGION LINE NORTH	12/01/22	8.00	5000.00	7683.33	8000.00
STR114A-015		SH114 SILLSVILLE SOUTH TO MP3	12/01/22	4.00	3500.00	10050.00	10000.00
IM025A-050		I25-MP103.9 - INTERSECTION DR	12/01/22	4.00	5000.00	7933.33	6300.00
BR012A-048		CO 12 STRUCTURE P-17-F AT MP	12/22/22	4.00	3600.00	4584.80	1500.00
		WEIGHTED AVERAGE FOR THE FOURTH QUARTER		40.00	5096.00	8941.08	8053.68
		WEIGHTED AVERAGE FOR THE YEAR		40.00	5096.00	8941.08	8053.68

COLORADO DEPARTMENT OF TRANSPORTATION
ITEM UNIT COSTS BY PROJECTS -- 2022 COST DATA

11:31 Wednesday, March 8, 2023 354

PROJECT NUMBER	ITEM NUMBER/ PROJECT LOCATION	ITEM DESCRIPTION/ PROJECT LOCATION	DATE LET	UNIT/ QUANTITY	ENGR. EST.	AVERAGE BID	AWARDED BID
===== 606-01402 Transition Type BR10B-GR3 Each =====							
STM1151-038		SH115 MP 27 TO MP 38	04/21/22	4.00	4000.00	5261.58	1000.00
		WEIGHTED AVERAGE FOR THE SECOND QUARTER		4.00	4000.00	5261.58	1000.00
2670403-065		US40_FLOYD HILL ROUNDABOUTS	09/15/22	4.00	14000.00	8302.83	5200.00
		WEIGHTED AVERAGE FOR THE THIRD QUARTER		4.00	14000.00	8302.83	5200.00
STR064A-010		SH 64 AND SH 13 AT MEEKER	11/10/22	4.00	10000.00	17635.00	18000.00
NHPP0701-252		I-70 RIFLE TO SILT SLAB REPLA	12/01/22	16.00	16000.00	7637.50	4000.00
		WEIGHTED AVERAGE FOR THE FOURTH QUARTER		20.00	14800.00	9637.00	6800.00
		WEIGHTED AVERAGE FOR THE YEAR		28.00	13142.86	8199.24	5742.86
===== 606-01403 Transition Type BR9-GR9 Each =====							
2670703-479		I-70 BRIDGE OVER HARLAN	05/05/22	8.00	3200.00	5801.75	5050.30
		WEIGHTED AVERAGE FOR THE SECOND QUARTER		8.00	3200.00	5801.75	5050.30
NHPP0702-414		VAIL PASS AUX PHASE 1 CAP 3	07/08/22	2.00	4353.81	4353.81	4353.81
FBR0702-423		VAIL PASS AUX BE F-12-AT PHAS					
		WEIGHTED AVERAGE FOR THE THIRD QUARTER		2.00	4353.81	4353.81	4353.81
		WEIGHTED AVERAGE FOR THE YEAR		10.00	3430.76	5743.83	4911.00
===== 606-01407 Transition Type BR9-GR3 Each =====							
NHPP0702-383		I-70 EB AUX FRISCO TO SILVERT	01/13/22	4.00	2000.00	10190.78	9400.00
NHPP 0761-238		I-76 DAHLIA TO YORK	03/10/22	4.00	2400.00	6872.91	6000.00
C0761-239							
		WEIGHTED AVERAGE FOR THE FIRST QUARTER		8.00	2200.00	8149.02	7700.00

COLORADO DEPARTMENT OF TRANSPORTATION
 ITEM UNIT COSTS BY PROJECTS -- 2022 COST DATA

11:31 Wednesday, March 8, 2023 355

PROJECT NUMBER	ITEM NUMBER/ PROJECT LOCATION	ITEM DESCRIPTION/ PROJECT LOCATION	DATE LET	UNIT/ QUANTITY	ENGR. EST.	AVERAGE BID	AWARDED BID
=====	606-01407	Transition Type BR9-GR3		Each	=====		
NHPP0702-414		VAIL PASS AUX PHASE 1 CAP 3	07/08/22	1.00	8975.76	8975.76	8975.76
FBR0702-423		VAIL PASS AUX BE F-12-AT PHAS					
2670703-497		I-70_GENESEE WILDLIFE XING	09/15/22	8.00	5100.00	8968.50	6147.77
		WEIGHTED AVERAGE FOR THE THIRD QUARTER		9.00	5530.64	8968.63	6461.99
2670703-487		I-70 BRIDGES OVER WARD ROAD-	12/01/22	4.00	7000.00	10984.57	6980.00
		WEIGHTED AVERAGE FOR THE FOURTH QUARTER		4.00	7000.00	8616.02	7990.00
		WEIGHTED AVERAGE FOR THE YEAR		21.00	4541.70	8587.15	7347.12
=====	606-01460	Median Terminal		Each	=====		
NHPP 0761-238		I-76 DAHLIA TO YORK	03/10/22	1.00	12000.00	12125.55	11000.00
C0761-239							
		WEIGHTED AVERAGE FOR THE FIRST QUARTER		1.00	12000.00	12125.55	11000.00
NHPP0701-231		I-70 SALT WASH BRIDGES SCOUR	09/29/22	2.00	12000.00	16276.01	16900.00
		WEIGHTED AVERAGE FOR THE THIRD QUARTER		2.00	12000.00	16276.01	16900.00
2670703-487		I-70 BRIDGES OVER WARD ROAD-	12/01/22	1.00	12000.00	10461.55	10400.00
		WEIGHTED AVERAGE FOR THE FOURTH QUARTER		1.00	12000.00	10461.55	10400.00
		WEIGHTED AVERAGE FOR THE YEAR		4.00	12000.00	12612.72	13800.00
=====	606-02003	End Anchor (Nonflared)		Each	=====		
NH0504-910		US50B L-24-B MIN REP AT MP 40	01/13/22	5.00	4000.00	4104.47	3892.22

COLORADO DEPARTMENT OF TRANSPORTATION
ITEM UNIT COSTS BY PROJECTS -- 2022 COST DATA

11:31 Wednesday, March 8, 2023 356

PROJECT NUMBER	ITEM NUMBER/ PROJECT LOCATION	ITEM DESCRIPTION/ PROJECT LOCATION	DATE LET	UNIT/ QUANTITY	ENGR. EST.	AVERAGE BID	AWARDED BID
=====	606-02003	End Anchor (Nonflared)		Each =====			
NHPP0702-383		I-70 EB AUX FRISCO TO SILVERT	01/13/22	3.00	3800.00	5192.97	5600.00
NHPP1601-083			02/03/22	36.00	4000.00	4163.70	4800.00
STA0252-459			02/03/22	11.00	3800.00	4001.67	3384.00
C0762-055			02/17/22	2.00	3000.00	3585.46	3500.00
STA 067A-048		Hwy 67A MP 0.00 TO MP 11.05 I	03/03/22	4.00	4000.00	4825.95	7000.00
NHPP 0761-238		I-76 DAHLIA TO YORK	03/10/22	4.00	3600.00	4297.67	4000.00
C0761-239							
STR160A-034		US160A LA VETA PASS EAST SURF	03/17/22	23.00	4500.00	4777.83	3555.65
STR092A-031			03/17/22	10.00	5000.00	6000.00	6000.00
		WEIGHTED AVERAGE FOR THE FIRST QUARTER		98.00	4154.08	4394.83	4480.26
NH0504-911			04/07/22	43.00	3300.00	3765.00	3630.00
STM1151-038		SH115 MP 27 TO MP 38	04/21/22	76.00	3200.00	3510.42	3152.00
2670703-479		I-70 BRIDGE OVER HARLAN	05/05/22	2.00	4000.00	4351.30	4904.88
STA0712-019		SH 71: Frieight Improvements	05/12/22	19.00	3600.00	3281.75	3281.75
NHPP072A-047		SH-72 RESURFACING: I-70 TO IN	06/09/22	9.00	4000.00	4946.04	4946.04
		WEIGHTED AVERAGE FOR THE SECOND QUARTER		149.00	3338.93	3590.58	3438.39
NHPP0702-414		VAIL PASS AUX PHASE 1 CAP 3	07/08/22	2.00	7942.73	7942.73	7942.73
FBR0702-423		VAIL PASS AUX BE F-12-AT PHAS					
ER0502-092		US 50 MP 204 EB MONARCH TRUCK	08/29/22	2.00	5000.00	5981.64	6899.37
PAN0761-245		ALONG I-76 & RAMPS MILEPOST 9	09/01/22	24.00	5000.00	4592.50	3760.00
2670403-065		US40_FLOYD HILL ROUNDABOUTS	09/15/22	7.00	5000.00	5618.00	5250.00
2670703-497		I-70_GENESEE WILDLIFE XING	09/15/22	4.00	5000.00	5851.41	5913.43
		WEIGHTED AVERAGE FOR THE THIRD QUARTER		39.00	5150.91	5276.50	4623.79
STA207A-004		Resurfacing SH207A MANZANOLA	10/27/22	18.00	4200.00	5083.33	4350.00
TRG0253-264		I-25 AND SH 119 PARK-N-RIDE	10/27/22	1.00	3500.00	4538.25	4750.00
SHE0242-087		US 24 SAFETY IMPRVMENTS, E OF	11/03/22	2.00	3725.00	4727.18	3981.55
C5502-097		US550 MP 117.28-126.06	11/17/22	20.00	5000.00	4225.00	3930.00
STRC090-011		US 50B AND SH71/CR18 INTERSEC	11/17/22	1.00	4600.00	7950.00	8200.00
STAM420-001		US 285 AT HWY 9C IMPROVEMENTS	12/01/22	6.00	3600.00	4479.38	5384.83
BR2854-148		INTERSECTION OF US 285 & SH 9					
STM0091-046		ADA RAMP IMPROVEMENTS - FAIRP					
STR114A-015		SH114 SILLSVILLE SOUTH TO MP3	12/01/22	22.00	6000.00	7150.00	7000.00
NHPP0701-252		I-70 RIFLE TO SILT SLAB REPLA	12/01/22	2.00	5000.00	4100.00	3490.00

PROJECT NUMBER	ITEM NUMBER/ PROJECT LOCATION	ITEM DESCRIPTION/ PROJECT LOCATION	DATE LET	UNIT/ QUANTITY	ENGR. EST.	AVERAGE BID	AWARDED BID
=====	606-02003	End Anchor (Nonflared)		Each =====			
IM025A-050		I25-MP103.9 - INTERSECTION DR	12/01/22	4.00	3700.00	3766.67	3700.00
NHPP0063-048		US6 / 20 ROAD INTERSECTION IM	12/15/22	2.00	6000.00	4988.96	4090.00
NHPP0931-033		SH93:US6 TO 58TH RESURFACING	12/15/22	5.00	4400.00	3890.34	3550.00
NHPP0502-090		SH 50 MP 134.6-136 GUNNISON C	12/22/22	19.00	5000.00	5074.50	5131.89
STA0361-129		US 36: HYGIENE RD AND NELSON	12/22/22	2.00	3700.00	4142.07	4372.34
BR012A-048		CO 12 STRUCTURE P-17-F AT MP	12/22/22	4.00	3800.00	4691.39	5000.00
STA385A-016		SH 385 MP 97.76	12/22/22	2.00	3500.00	4387.50	4000.00
STR096A-050		SH 96 MP 168.99 TO 193.77	12/22/22	20.00	3700.00	4388.33	6000.00
		WEIGHTED AVERAGE FOR THE FOURTH QUARTER		130.00	4631.92	4936.75	4986.78
		WEIGHTED AVERAGE FOR THE YEAR		416.00	4104.89	4349.72	4303.47
=====	606-02005	End Anchor (Flared)		Each =====			
NHPP0702-383		I-70 EB AUX FRISCO TO SILVERT	01/13/22	8.00	3200.00	4969.40	5500.00
C0762-055			02/17/22	2.00	3200.00	3936.13	4000.00
STA 067A-048		Hwy 67A MP 0.00 TO MP 11.05 I	03/03/22	16.00	4000.00	5024.59	7200.00
NHPP 0761-238		I-76 DAHLIA TO YORK	03/10/22	1.00	3600.00	4500.03	4200.00
C0761-239							
STR092A-031			03/17/22	6.00	4000.00	7800.00	7800.00
		WEIGHTED AVERAGE FOR THE FIRST QUARTER		33.00	3745.45	5038.60	6612.12
2670703-479		I-70 BRIDGE OVER HARLAN	05/05/22	1.00	3500.00	4686.87	5283.21
STA0712-019		SH 71: Frieight Improvements	05/12/22	1.00	4000.00	3952.67	3952.67
NHPP 3851-018		US 385 NORTH OF CHEYENNE WELL	05/26/22	4.00	3500.00	6550.00	7600.00
ITS 0741-024		VMS SIGN INSTALLATIONS AND VS	06/02/22	2.00	3000.00	5451.50	4924.00
NHPP072A-047		SH-72 RESURFACING: I-70 TO IN	06/09/22	3.00	4000.00	5501.40	5501.40
MTCE0253-291		I-25 SIGN REPLACEMENT PHASE 2	06/16/22	14.00	4000.00	4191.95	3908.89
		WEIGHTED AVERAGE FOR THE SECOND QUARTER		25.00	3820.00	4803.17	4828.50
BR0343-046		US 34 TIMBER BRIDGE REPL. PKG	08/31/22	4.00	5031.73	2498.45	2498.45
FBR0343-047		US 6/US 34 TIMBER BRIDGE REPL					
2670703-497		I-70 GENESEE WILDLIFE XING	09/15/22	1.00	3700.00	5814.22	5821.42
NHPP0701-231		I-70 SALT WASH BRIDGES SCOUR	09/29/22	2.00	5000.00	6346.65	6810.00
		WEIGHTED AVERAGE FOR THE THIRD QUARTER		7.00	4832.42	5072.00	4205.03
NHPP0701-253		I-70 EAST OF DEBEQUE	10/27/22	11.00	5000.00	4500.00	5100.00

PROJECT NUMBER	ITEM NUMBER/ PROJECT LOCATION	ITEM DESCRIPTION/ PROJECT LOCATION	DATE LET	UNIT/ QUANTITY	ENGR. EST.	AVERAGE BID	AWARDED BID
=====	606-02005	End Anchor (Flared)		Each	=====	=====	=====
STR064A-010		SH 64 AND SH 13 AT MEEKER	11/10/22	12.00	6500.00	4500.00	4750.00
C5502-097		US550 MP 117.28-126.06	11/17/22	6.00	6000.00	4708.53	4380.00
STA0711-021		SH71: REGION LINE NORTH	12/01/22	7.00	3500.00	4250.00	4400.00
NHPP0701-252		I-70 RIFLE TO SILT SLAB REPLA	12/01/22	31.00	5000.00	4270.00	3515.00
NHPP0063-048		US6 / 20 ROAD INTERSECTION IM	12/15/22	1.00	6000.00	5414.79	4495.00
NHPP0931-033		SH93:US6 TO 58TH RESURFACING	12/15/22	13.00	4200.00	4236.45	3885.00
NHPP0502-090		SH 50 MP 134.6-136 GUNNISON C	12/22/22	21.00	5100.00	5687.31	5634.45
STR0092-024		SH 9 North of Silverthorne	12/22/22	31.00	6000.00	8670.00	5340.00
STA0361-129		US 36: HYGIENE RD AND NELSON	12/22/22	6.00	6000.00	4908.62	4831.10
		WEIGHTED AVERAGE FOR THE FOURTH QUARTER		139.00	5310.79	5392.51	4645.35
		WEIGHTED AVERAGE FOR THE YEAR		204.00	4858.47	5266.94	4967.68
=====	606-10200	Brdg Rail (Spec)		Lin Foot	=====	=====	=====
STR114A-015		SH114 SILLSVILLE SOUTH TO MP3	12/01/22	91.00	200.00	124.50	130.00
		WEIGHTED AVERAGE FOR THE FOURTH QUARTER		91.00	200.00	124.50	130.00
		WEIGHTED AVERAGE FOR THE YEAR		91.00	200.00	124.50	130.00
=====	606-10700	Brdg Rail Ty 7		Lin Foot	=====	=====	=====
NHPP 0761-238 C0761-239		I-76 DAHLIA TO YORK	03/10/22	29.00	240.00	311.64	200.00
		WEIGHTED AVERAGE FOR THE FIRST QUARTER		29.00	240.00	311.64	200.00
2670703-487		I-70 BRIDGES OVER WARD ROAD-	12/01/22	378.00	100.00	244.19	170.00
		WEIGHTED AVERAGE FOR THE FOURTH QUARTER		378.00	100.00	244.19	170.00
		WEIGHTED AVERAGE FOR THE YEAR		407.00	109.98	251.56	172.14
=====	606-10705	Brdg Rail Ty 7 (Spec)		Lin Foot	=====	=====	=====
NHPP 0761-238 C0761-239		I-76 DAHLIA TO YORK	03/10/22	15.00	150.00	464.35	250.00
		WEIGHTED AVERAGE FOR THE FIRST QUARTER		15.00	150.00	464.35	250.00
		WEIGHTED AVERAGE FOR THE YEAR		15.00	150.00	464.35	250.00

COLORADO DEPARTMENT OF TRANSPORTATION
 ITEM UNIT COSTS BY PROJECTS -- 2022 COST DATA

11:31 Wednesday, March 8, 2023 359

PROJECT NUMBER	ITEM NUMBER/ PROJECT LOCATION	ITEM DESCRIPTION/ PROJECT LOCATION	DATE LET	UNIT/ QUANTITY	ENGR. EST.	AVERAGE BID	AWARDED BID
=====	606-10900	Brdg Rail Ty 9		Lin Foot	=====		
NHPP0702-383		I-70 EB AUX FRISCO TO SILVERT	01/13/22	940.00	150.00	435.54	366.00
NHPP 0761-238		I-76 DAHLIA TO YORK	03/10/22	435.00	420.00	412.34	370.00
C0761-239							
		WEIGHTED AVERAGE FOR THE FIRST QUARTER		1,375.00	235.42	425.67	367.27
2670703-479		I-70 BRIDGE OVER HARLAN	05/05/22	350.00	275.00	428.41	430.00
		WEIGHTED AVERAGE FOR THE SECOND QUARTER		350.00	275.00	428.41	430.00
NHPP0702-414		VAIL PASS AUX PHASE 1 CAP 3	07/08/22	1,206.00	430.48	430.48	430.48
FBR0702-423		VAIL PASS AUX BE F-12-AT PHAS					
2670703-497		I-70_GENESEE WILDLIFE XING	09/15/22	630.00	330.00	392.75	442.02
		WEIGHTED AVERAGE FOR THE THIRD QUARTER		1,836.00	396.00	400.85	434.44
2670703-487		I-70 BRIDGES OVER WARD ROAD-	12/01/22	378.00	450.00	374.62	260.00
		WEIGHTED AVERAGE FOR THE FOURTH QUARTER		378.00	450.00	356.93	325.70
		WEIGHTED AVERAGE FOR THE YEAR		3,939.00	334.38	400.77	384.82
=====	606-10905	Brdg Rail Ty 9 (Spec)		Lin Foot	=====		
2670703-479		I-70 BRIDGE OVER HARLAN	05/05/22	350.00	300.00	672.49	625.00
		WEIGHTED AVERAGE FOR THE SECOND QUARTER		350.00	300.00	672.49	625.00
		WEIGHTED AVERAGE FOR THE YEAR		350.00	300.00	672.49	625.00
=====	606-11010	Brdg Rail Ty 10R		Lin Foot	=====		
STA207A-004		Resurfacing SH207A MANZANOLA	10/27/22	920.00	230.00	221.24	320.73

COLORADO DEPARTMENT OF TRANSPORTATION
ITEM UNIT COSTS BY PROJECTS -- 2022 COST DATA

11:31 Wednesday, March 8, 2023 360

PROJECT NUMBER	ITEM NUMBER/ PROJECT LOCATION	ITEM DESCRIPTION/ PROJECT LOCATION	DATE LET	UNIT/ QUANTITY	ENGR. EST.	AVERAGE BID	AWARDED BID
=====	606-11010	Brdg Rail Ty 10R		Lin Foot	=====	=====	=====
STR114A-015		SH114 SILLSVILLE SOUTH TO MP3	12/01/22	49.00	210.00	860.00	900.00
	WEIGHTED AVERAGE FOR THE FOURTH QUARTER			969.00	228.99	243.15	350.02
	WEIGHTED AVERAGE FOR THE YEAR			969.00	228.99	243.15	350.02
=====	606-11035	Brdg Rail Ty 10 MASH		Lin Foot	=====	=====	=====
STM1151-038		SH115 MP 27 TO MP 38	04/21/22	302.00	240.00	324.78	440.00
	WEIGHTED AVERAGE FOR THE SECOND QUARTER			302.00	240.00	324.78	440.00
STU0252-457		I-25:ALAMEDA RIVER PH 2.0	11/03/22	445.00	500.00	480.87	490.00
C5502-097		US550 MP 117.28-126.06	11/17/22	48.00	500.00	300.25	279.00
STAM420-001		US 285 AT HWY 9C IMPROVEMENTS	12/01/22	306.00	400.00	389.78	554.75
BR2854-148		INTERSECTION OF US 285 & SH 9					
STM0091-046		ADA RAMP IMPROVEMENTS - FAIRP					
IM025A-050		I25-MP103.9 - INTERSECTION DR	12/01/22	980.00	330.00	307.67	270.00
BR012A-048		CO 12 STRUCTURE P-17-F AT MP	12/22/22	248.00	250.00	525.11	650.00
	WEIGHTED AVERAGE FOR THE FOURTH QUARTER			2,027.00	372.13	379.10	407.99
	WEIGHTED AVERAGE FOR THE YEAR			2,329.00	354.99	368.37	412.14
=====	606-11037	Brdg Rail Ty 10R MASH		Lin Foot	=====	=====	=====
NHPP0701-253		I-70 EAST OF DEBEQUE	10/27/22	617.00	400.00	231.00	240.00
STA0711-021		SH71: REGION LINE NORTH	12/01/22	220.00	500.00	256.67	240.00
STR114A-015		SH114 SILLSVILLE SOUTH TO MP3	12/01/22	88.00	400.00	502.50	520.00
	WEIGHTED AVERAGE FOR THE FOURTH QUARTER			925.00	423.78	262.27	266.64
	WEIGHTED AVERAGE FOR THE YEAR			925.00	423.78	262.27	266.64
=====	606-21010	End Anchor (High-Tens Cab Bar)		Each	=====	=====	=====
FSA0853-122		WCR14.5 AND US-85, FORT LUPTO	12/15/22	2.00	3500.00	13821.85	15000.00
	WEIGHTED AVERAGE FOR THE FOURTH QUARTER			2.00	3500.00	12717.05	13000.00
	WEIGHTED AVERAGE FOR THE YEAR			2.00	3500.00	12717.05	13000.00

COLORADO DEPARTMENT OF TRANSPORTATION
ITEM UNIT COSTS BY PROJECTS -- 2022 COST DATA

11:31 Wednesday, March 8, 2023 361

PROJECT NUMBER	ITEM NUMBER/ PROJECT LOCATION	ITEM DESCRIPTION/ PROJECT LOCATION	DATE LET	UNIT/ QUANTITY	ENGR. EST.	AVERAGE BID	AWARDED BID
=====	607-00000	Line Post		Each	=====		
C5502-097		US550 MP 117.28-126.06	11/17/22	524.00	15.00	69.97	30.90
STAM420-001		US 285 AT HWY 9C IMPROVEMENTS	12/01/22	300.00	80.00	53.99	67.05
BR2854-148		INTERSECTION OF US 285 & SH 9					
STM0091-046		ADA RAMP IMPROVEMENTS - FAIRP					
BR012A-048		CO 12 STRUCTURE P-17-F AT MP	12/22/22	88.00	10.00	22.70	15.00
		WEIGHTED AVERAGE FOR THE FOURTH QUARTER		912.00	35.90	60.64	41.26
		WEIGHTED AVERAGE FOR THE YEAR		912.00	35.90	60.64	41.26
=====	607-00005	End Post		Each	=====		
STA0252-459			02/03/22	32.00	320.00	705.92	656.00
		WEIGHTED AVERAGE FOR THE FIRST QUARTER		32.00	320.00	705.92	656.00
FSA0702-409		I-70 VAIL WILDLIFE FENCE PHAS	05/26/22	42.00	1300.00	1100.00	1100.00
		WEIGHTED AVERAGE FOR THE SECOND QUARTER		42.00	1300.00	1100.00	1100.00
FSA052A-057		SH52 BOX CULVERT EXTENSION (M	08/04/22	2.00	400.00	441.47	487.50
		WEIGHTED AVERAGE FOR THE THIRD QUARTER		2.00	400.00	441.47	487.50
C5502-097		US550 MP 117.28-126.06	11/17/22	81.00	1100.00	571.84	494.00
STAM420-001		US 285 AT HWY 9C IMPROVEMENTS	12/01/22	40.00	285.00	433.77	540.14
BR2854-148		INTERSECTION OF US 285 & SH 9					
STM0091-046		ADA RAMP IMPROVEMENTS - FAIRP					
2670703-487		I-70 BRIDGES OVER WARD ROAD-	12/01/22	8.00	1000.00	292.97	290.00
NHPP0502-090		SH 50 MP 134.6-136 GUNNISON C	12/22/22	8.00	800.00	802.02	693.69
BR012A-048		CO 12 STRUCTURE P-17-F AT MP	12/22/22	4.00	500.00	433.41	350.00
		WEIGHTED AVERAGE FOR THE FOURTH QUARTER		141.00	829.08	520.63	502.76
		WEIGHTED AVERAGE FOR THE YEAR		217.00	841.20	586.21	640.81

COLORADO DEPARTMENT OF TRANSPORTATION
ITEM UNIT COSTS BY PROJECTS -- 2022 COST DATA

11:31 Wednesday, March 8, 2023 362

PROJECT NUMBER	ITEM NUMBER/ PROJECT LOCATION	ITEM DESCRIPTION/ PROJECT LOCATION	DATE LET	UNIT/ QUANTITY	ENGR. EST.	AVERAGE BID	AWARDED BID
=====	607-00010	Corner and Line Br Post		Each	=====	=====	=====
STA0252-459			02/03/22	258.00	360.00	897.00	811.00
		WEIGHTED AVERAGE FOR THE FIRST QUARTER		258.00	360.00	897.00	811.00
FSA0702-409		I-70 VAIL WILDLIFE FENCE PHAS	05/26/22	110.00	1600.00	1450.00	1450.00
		WEIGHTED AVERAGE FOR THE SECOND QUARTER		110.00	1600.00	1450.00	1450.00
FSA052A-057		SH52 BOX CULVERT EXTENSION (M	08/04/22	3.00	500.00	506.37	520.00
		WEIGHTED AVERAGE FOR THE THIRD QUARTER		3.00	500.00	506.37	520.00
C5502-097		US550 MP 117.28-126.06	11/17/22	33.00	1200.00	690.52	580.00
2670703-487		I-70 BRIDGES OVER WARD ROAD-	12/01/22	3.00	800.00	401.59	400.00
NHPP0502-090		SH 50 MP 134.6-136 GUNNISON C	12/22/22	8.00	800.00	977.42	832.43
BR012A-048		CO 12 STRUCTURE P-17-F AT MP	12/22/22	11.00	1000.00	416.34	250.00
STA385A-016		SH 385 MP 97.76	12/22/22	4.00	500.00	735.56	722.22
		WEIGHTED AVERAGE FOR THE FOURTH QUARTER		59.00	1040.68	700.06	553.19
		WEIGHTED AVERAGE FOR THE YEAR		430.00	771.58	914.97	937.06
=====	607-00015	End Post (Spec)		Each	=====	=====	=====
C5502-097		US550 MP 117.28-126.06	11/17/22	42.00	1200.00	1113.80	968.00
		WEIGHTED AVERAGE FOR THE FOURTH QUARTER		42.00	1200.00	1113.80	968.00
		WEIGHTED AVERAGE FOR THE YEAR		42.00	1200.00	1113.80	968.00
=====	607-00020	Corner and Line Br Post (Spec)		Each	=====	=====	=====
C5502-097		US550 MP 117.28-126.06	11/17/22	53.00	1500.00	1585.13	1440.00
		WEIGHTED AVERAGE FOR THE FOURTH QUARTER		53.00	1500.00	1585.13	1440.00
		WEIGHTED AVERAGE FOR THE YEAR		53.00	1500.00	1585.13	1440.00

COLORADO DEPARTMENT OF TRANSPORTATION
ITEM UNIT COSTS BY PROJECTS -- 2022 COST DATA

11:31 Wednesday, March 8, 2023 363

PROJECT NUMBER	ITEM NUMBER/ PROJECT LOCATION	ITEM DESCRIPTION/ PROJECT LOCATION	DATE LET	UNIT/ QUANTITY	ENGR. EST.	AVERAGE BID	AWARDED BID
===== 607-01000 Fence BW MP Lin Foot =====							
NH0504-910		US50B L-24-B MIN REP AT MP 40	01/13/22	1,420.00	5.00	5.77	4.06
		WEIGHTED AVERAGE FOR THE FIRST QUARTER		1,420.00	5.00	5.77	4.06
FSA052A-057		SH52 BOX CULVERT EXTENSION (M	08/04/22	120.00	12.00	11.36	15.60
BR0343-046		US 34 TIMBER BRIDGE REPL. PKG	08/31/22	312.00	34.24	35.85	35.85
FBR0343-047		US 6/US 34 TIMBER BRIDGE REPL					
		WEIGHTED AVERAGE FOR THE THIRD QUARTER		432.00	28.06	22.73	30.23
SHE0242-087		US 24 SAFETY IMPRVMENTS, E OF	11/03/22	195.00	10.00	18.08	9.25
C5502-097		US550 MP 117.28-126.06	11/17/22	2,284.00	6.00	5.84	5.35
NHPP0502-090		SH 50 MP 134.6-136 GUNNISON C	12/22/22	2,180.00	7.00	8.67	6.38
BR012A-048		CO 12 STRUCTURE P-17-F AT MP	12/22/22	1,500.00	5.00	9.91	15.00
STA385A-016		SH 385 MP 97.76	12/22/22	500.00	5.00	8.77	8.06
		WEIGHTED AVERAGE FOR THE FOURTH QUARTER		6,659.00	6.14	8.24	8.18
		WEIGHTED AVERAGE FOR THE YEAR		8,511.00	7.07	7.72	8.61
===== 607-01050 Fence Wire MP Lin Foot =====							
STM1151-038		SH115 MP 27 TO MP 38	04/21/22	200.00	12.00	17.58	16.00
		WEIGHTED AVERAGE FOR THE SECOND QUARTER		200.00	12.00	17.58	16.00
		WEIGHTED AVERAGE FOR THE YEAR		200.00	12.00	17.58	16.00
===== 607-11200 Fence CW MP Lin Foot =====							
C5502-097		US550 MP 117.28-126.06	11/17/22	14,467.00	6.00	8.37	7.45
		WEIGHTED AVERAGE FOR THE FOURTH QUARTER		14,467.00	6.00	8.37	7.45
		WEIGHTED AVERAGE FOR THE YEAR		14,467.00	6.00	8.37	7.45
===== 607-11300 Fence CW TWP Lin Foot =====							
STAM420-001		US 285 AT HWY 9C IMPROVEMENTS	12/01/22	5,400.00	5.00	4.37	5.45

COLORADO DEPARTMENT OF TRANSPORTATION
 ITEM UNIT COSTS BY PROJECTS -- 2022 COST DATA

11:31 Wednesday, March 8, 2023 364

PROJECT NUMBER	ITEM NUMBER/ PROJECT LOCATION	ITEM DESCRIPTION/ PROJECT LOCATION	DATE LET	UNIT/ QUANTITY	ENGR. EST.	AVERAGE BID	AWARDED BID
=====	607-11300	Fence CW TWP		Lin Foot	=====		
BR2854-148		INTERSECTION OF US 285 & SH 9					
STM0091-046		ADA RAMP IMPROVEMENTS - FAIRP					
	WEIGHTED AVERAGE FOR THE FOURTH QUARTER			5,400.00	5.00	4.37	5.45
	WEIGHTED AVERAGE FOR THE YEAR			5,400.00	5.00	4.37	5.45
=====	607-11350	Fence Deer		Lin Foot	=====		
NHPP0702-383		I-70 EB AUX FRISCO TO SILVERT	01/13/22	28,000.00	25.00	25.48	26.00
STA0252-459			02/03/22	58,249.00	7.86	13.33	10.12
	WEIGHTED AVERAGE FOR THE FIRST QUARTER			86,249.00	13.42	18.73	15.28
FSA0702-409		I-70 VAIL WILDLIFE FENCE PHAS	05/26/22	28,098.00	33.00	32.00	32.00
	WEIGHTED AVERAGE FOR THE SECOND QUARTER			28,098.00	33.00	32.00	32.00
2670703-497		I-70_GENESEE WILDLIFE XING	09/15/22	28,675.00	22.00	27.68	27.13
	WEIGHTED AVERAGE FOR THE THIRD QUARTER			28,675.00	22.00	27.68	27.13
C5502-097		US550 MP 117.28-126.06	11/17/22	10,503.00	30.00	28.68	22.80
	WEIGHTED AVERAGE FOR THE FOURTH QUARTER			10,503.00	30.00	28.68	22.80
	WEIGHTED AVERAGE FOR THE YEAR			153,525.00	19.74	23.05	21.07
=====	607-11360	Fence Deer (Spec)		Lin Foot	=====		
STA0252-459			02/03/22	580.00	10.90	18.05	14.00
	WEIGHTED AVERAGE FOR THE FIRST QUARTER			580.00	10.90	18.05	14.00
	WEIGHTED AVERAGE FOR THE YEAR			580.00	10.90	18.05	14.00

COLORADO DEPARTMENT OF TRANSPORTATION
ITEM UNIT COSTS BY PROJECTS -- 2022 COST DATA

11:31 Wednesday, March 8, 2023 365

PROJECT NUMBER	ITEM NUMBER/ PROJECT LOCATION	ITEM DESCRIPTION/ PROJECT LOCATION	DATE LET	UNIT/ QUANTITY	ENGR. EST.	AVERAGE BID	AWARDED BID
===== 607-11455 Fence Wood Lin Foot =====							
NHPP0063-054		US 6 FROM I70-B TO 33 RD. (MP	08/18/22	43.00	150.00	96.89	75.00
	WEIGHTED AVERAGE FOR THE THIRD	QUARTER		43.00	150.00	96.89	75.00
	WEIGHTED AVERAGE FOR THE YEAR			43.00	150.00	96.89	75.00
===== 607-11525 Fence (Plastic) Lin Foot =====							
MTCE R500-218			01/06/22	500.00	6.00	4.38	2.75
NH0504-910		US50B L-24-B MIN REP AT MP 40	01/13/22	210.00	4.00	4.62	6.25
NHPP0702-383		I-70 EB AUX FRISCO TO SILVERT	01/13/22	5,830.00	5.00	5.38	6.00
NHPP1601-083			02/03/22	900.00	3.00	6.85	4.00
STA0252-459			02/03/22	5,000.00	3.03	2.78	1.88
NHPP0063-063			02/24/22	200.00	3.50	8.10	12.00
STA 067A-048		Hwy 67A MP 0.00 TO MP 11.05 I	03/03/22	1,500.00	5.00	3.98	3.00
NHPP 0761-238		I-76 DAHLIA TO YORK	03/10/22	2,390.00	6.00	4.62	5.00
C0761-239							
CR100-362			03/14/22	100.00	6.72	6.72	6.72
STR R500-171		Various locations on SH 141 a	03/17/22	400.00	4.00	2.92	0.50
STR092A-031			03/17/22	500.00	5.00	4.85	4.85
NHM765-007			03/31/22	3,000.00	6.00	3.07	2.85
	WEIGHTED AVERAGE FOR THE FIRST	QUARTER		20,530.00	4.68	4.39	3.96
NHPP0702-413		VAIL PASS AUX PHASE 1 CAP 2	04/18/22	5,600.00	2.13	2.13	2.13
STM1151-038		SH115 MP 27 TO MP 38	04/21/22	1,000.00	2.50	5.90	10.39
2670703-479		I-70 BRIDGE OVER HARLAN	05/05/22	245.00	3.50	3.98	2.00
NHC540-017		R2 CHAINUP STA @ KENOSHA/HOOS	05/12/22	600.00	4.00	6.42	4.25
FSA0702-409		I-70 VAIL WILDLIFE FENCE PHAS	05/26/22	200.00	6.00	3.00	3.00
ITS 0741-024		VMS SIGN INSTALLATIONS AND VS	06/02/22	250.00	5.00	7.00	7.00
	WEIGHTED AVERAGE FOR THE SECOND	QUARTER		7,895.00	2.55	4.32	3.51
NHPP0702-414		VAIL PASS AUX PHASE 1 CAP 3	07/08/22	5,300.00	3.00	3.00	3.00
FBR0702-423		VAIL PASS AUX BE F-12-AT PHAS					
NHPP0063-054		US 6 FROM I70-B TO 33 RD. (MP	08/18/22	280.00	5.00	9.13	13.50
FBR0761-236		I-76 OVER CLR CRK SCOUR MIT	08/25/22	1,000.00	6.00	3.55	5.00
C1211-099		SH 121 NORTH SGA SIGNALS	08/25/22	1,820.00	5.00	8.50	11.00

PROJECT NUMBER	ITEM NUMBER/ PROJECT LOCATION	ITEM DESCRIPTION/ PROJECT LOCATION	DATE LET	UNIT/ QUANTITY	ENGR. EST.	AVERAGE BID	AWARDED BID
=====	607-11525	Fence (Plastic)		Lin Foot	=====	=====	=====
ER0502-092		US 50 MP 204 EB MONARCH TRUCK	08/29/22	100.00	5.00	5.99	6.22
BR0343-046		US 34 TIMBER BRIDGE REPL. PKG	08/31/22	3,156.00	9.10	7.59	7.59
FBR0343-047		US 6/US 34 TIMBER BRIDGE REPL					
NHPPR100-266		R1 ESSENTIAL REPAIRS	09/01/22	400.00	4.00	3.82	4.05
ER0253-297		WCR 34 BRIDGE OVER I-25(MM 24	09/14/22	300.00	6.00	6.82	10.00
2670403-065		US40 FLOYD HILL ROUNDABOUTS	09/15/22	200.00	5.00	4.13	4.30
2670703-497		I-70_GENESEE WILDLIFE XING	09/15/22	250.00	4.50	5.09	4.54
SHE2873-193		US 287 & CO 52 INTERSECTION I	09/15/22	100.00	8.00	5.01	2.00
NHPP0701-231		I-70 SALT WASH BRIDGES SCOUR	09/29/22	3,225.00	5.00	4.66	5.00
		WEIGHTED AVERAGE FOR THE THIRD QUARTER		16,131.00	5.21	5.24	5.72
STA207A-004		Resurfacing SH207A MANZANOLA	10/27/22	500.00	3.25	97.97	4.90
STU0252-457		I-25:ALAMEDA RIVER PH 2.0	11/03/22	3,500.00	5.00	4.02	6.30
C5502-097		US550 MP 117.28-126.06	11/17/22	4,461.00	5.00	6.06	6.10
STRC090-011		US 50B AND SH71/CR18 INTERSEC	11/17/22	2,085.00	3.00	4.55	5.10
STAM420-001		US 285 AT HWY 9C IMPROVEMENTS	12/01/22	500.00	3.50	6.36	5.38
BR2854-148		INTERSECTION OF US 285 & SH 9					
STM0091-046		ADA RAMP IMPROVEMENTS - FAIRP					
2670703-487		I-70 BRIDGES OVER WARD ROAD-	12/01/22	965.00	4.00	4.01	4.70
IM025A-050		I25-MP103.9 - INTERSECTION DR	12/01/22	1,000.00	4.00	3.20	4.10
STR109A-019		M-22-AY BRIDGE REHAB ON SH109	12/01/22	1,550.00	4.00	4.84	3.67
NHPP083A-046		SH83 RESURFACING STROH RD TO	12/08/22	100.00	5.00	4.93	2.56
NHPP0063-048		US6 / 20 ROAD INTERSECTION IM	12/15/22	8,345.00	4.00	2.93	2.50
NHPP0931-033		SH93:US6 TO 58TH RESURFACING	12/15/22	800.00	4.00	5.15	3.10
STA0361-129		US 36: HYGIENE RD AND NELSON	12/22/22	115.00	5.00	6.97	4.55
STA385A-016		SH 385 MP 97.76	12/22/22	150.00	5.00	6.17	6.67
		WEIGHTED AVERAGE FOR THE FOURTH QUARTER		24,071.00	4.23	5.83	4.34
		WEIGHTED AVERAGE FOR THE YEAR		68,627.00	4.40	5.06	4.46
=====	607-11530	Fence (Spec)		Lin Foot	=====	=====	=====
NHPP0253-275		I-25 EXPRESS LANES SEGMENT 5	03/11/22	358.00	789.04	804.77	804.77
		WEIGHTED AVERAGE FOR THE FIRST QUARTER		358.00	789.04	804.77	804.77
2670703-497		I-70_GENESEE WILDLIFE XING	09/15/22	120.00	53.00	152.91	143.12
		WEIGHTED AVERAGE FOR THE THIRD QUARTER		120.00	53.00	152.91	143.12
		WEIGHTED AVERAGE FOR THE YEAR		478.00	604.26	347.71	638.66

COLORADO DEPARTMENT OF TRANSPORTATION
ITEM UNIT COSTS BY PROJECTS -- 2022 COST DATA

11:31 Wednesday, March 8, 2023 367

PROJECT NUMBER	ITEM NUMBER/ PROJECT LOCATION	ITEM DESCRIPTION/ PROJECT LOCATION	DATE LET	UNIT/ QUANTITY	ENGR. EST.	AVERAGE BID	AWARDED BID
=====	607-11560	Debris Barrier		Sq Foot	=====		
ER0702-420		PR I-70 GWC MATERIAL FLOWS 20	05/06/22	3,680.00	150.00	218.15	195.27
		WEIGHTED AVERAGE FOR THE SECOND QUARTER		3,680.00	150.00	218.15	195.27
		WEIGHTED AVERAGE FOR THE YEAR		3,680.00	150.00	218.15	195.27
=====	607-11580	Fence (Temp)		Lin Foot	=====		
NH0504-910		US50B L-24-B MIN REP AT MP 40	01/13/22	1,450.00	6.00	7.15	4.06
		WEIGHTED AVERAGE FOR THE FIRST QUARTER		1,450.00	6.00	7.15	4.06
BR0343-046 FBR0343-047		US 34 TIMBER BRIDGE REPL. PKG US 6/US 34 TIMBER BRIDGE REPL	08/31/22	136.00	34.24	35.85	35.85
		WEIGHTED AVERAGE FOR THE THIRD QUARTER		136.00	34.24	35.85	35.85
STU0252-457 SHE0242-087		I-25:ALAMEDA RIVER PH 2.0 US 24 SAFETY IMPRVMENTS, E OF	11/03/22 11/03/22	860.00 179.00	10.00 20.00	20.20 6.12	27.00 4.37
		WEIGHTED AVERAGE FOR THE FOURTH QUARTER		1,039.00	11.72	16.16	20.13
		WEIGHTED AVERAGE FOR THE YEAR		2,625.00	9.73	9.94	13.09
=====	607-11937	Fence Metal (36 In)		Lin Foot	=====		
NHPP0253-275		I-25 EXPRESS LANES SEGMENT 5	03/11/22	724.00	506.10	549.78	549.78
		WEIGHTED AVERAGE FOR THE FIRST QUARTER		724.00	506.10	549.78	549.78
		WEIGHTED AVERAGE FOR THE YEAR		724.00	506.10	549.78	549.78
=====	607-15144	Fence Concrete (Noise)(144 In)		Lin Foot	=====		
2670703-479		I-70 BRIDGE OVER HARLAN	05/05/22	1,336.00	460.00	497.89	420.00
		WEIGHTED AVERAGE FOR THE SECOND QUARTER		1,336.00	460.00	497.89	420.00
		WEIGHTED AVERAGE FOR THE YEAR		1,336.00	460.00	497.89	420.00

COLORADO DEPARTMENT OF TRANSPORTATION
 ITEM UNIT COSTS BY PROJECTS -- 2022 COST DATA

11:31 Wednesday, March 8, 2023 368

PROJECT NUMBER	ITEM NUMBER/ PROJECT LOCATION	ITEM DESCRIPTION/ PROJECT LOCATION	DATE LET	UNIT/ QUANTITY	ENGR. EST.	AVERAGE BID	AWARDED BID
=====	607-32000	Fence Picket Snow		Lin Foot	=====		
NHPP0931-033		SH93:US6 TO 58TH RESURFACING	12/15/22	1,800.00	10.00	10.66	5.15
		WEIGHTED AVERAGE FOR THE FOURTH QUARTER		1,800.00	10.00	10.66	5.15
		WEIGHTED AVERAGE FOR THE YEAR		1,800.00	10.00	10.66	5.15
=====	607-52900	Line Post (CL)		Each	=====		
NHM765-007			03/31/22	4.00	105.00	269.07	285.00
		WEIGHTED AVERAGE FOR THE FIRST QUARTER		4.00	105.00	269.07	285.00
		WEIGHTED AVERAGE FOR THE YEAR		4.00	105.00	57.30	55.88
=====	607-52905	End Post (CL)		Each	=====		
NHM765-007			03/31/22	3.00	275.00	533.31	570.00
		WEIGHTED AVERAGE FOR THE FIRST QUARTER		3.00	275.00	533.31	570.00
		WEIGHTED AVERAGE FOR THE YEAR		3.00	275.00	211.64	224.12
=====	607-53137	Fence CL (Spec) (36 In)		Lin Foot	=====		
NHPP 0761-238 C0761-239		I-76 DAHLIA TO YORK	03/10/22	435.00	44.00	83.64	80.00
		WEIGHTED AVERAGE FOR THE FIRST QUARTER		435.00	44.00	83.64	80.00
2670703-479		I-70 BRIDGE OVER HARLAN	05/05/22	350.00	80.00	74.97	83.37
		WEIGHTED AVERAGE FOR THE SECOND QUARTER		350.00	80.00	74.97	83.37
2670703-497		I-70_GENESEE WILDLIFE XING	09/15/22	630.00	65.00	82.66	79.34
		WEIGHTED AVERAGE FOR THE THIRD QUARTER		630.00	65.00	82.66	79.34

COLORADO DEPARTMENT OF TRANSPORTATION
 ITEM UNIT COSTS BY PROJECTS -- 2022 COST DATA

11:31 Wednesday, March 8, 2023 369

PROJECT NUMBER	ITEM NUMBER/ PROJECT LOCATION	ITEM DESCRIPTION/ PROJECT LOCATION	DATE LET	UNIT/ QUANTITY	ENGR. EST.	AVERAGE BID	AWARDED BID
=====	607-53137	Fence CL (Spec) (36 In)		Lin Foot	=====		
STU0252-457		I-25:ALAMEDA RIVER PH 2.0	11/03/22	165.00	110.00	170.85	170.00
STAM420-001		US 285 AT HWY 9C IMPROVEMENTS	12/01/22	487.00	70.00	71.34	86.88
BR2854-148		INTERSECTION OF US 285 & SH 9					
STM0091-046		ADA RAMP IMPROVEMENTS - FAIRP					
2670703-487		I-70 BRIDGES OVER WARD ROAD-	12/01/22	374.00	90.00	85.44	85.00
IM025A-050		I25-MP103.9 - INTERSECTION DR	12/01/22	245.00	85.00	80.67	77.00
		WEIGHTED AVERAGE FOR THE FOURTH QUARTER		1,271.00	83.97	87.68	95.21
		WEIGHTED AVERAGE FOR THE YEAR		2,686.00	72.53	83.50	87.48
=====	607-53160	Fence CL (60 In)		Lin Foot	=====		
2670703-487		I-70 BRIDGES OVER WARD ROAD-	12/01/22	249.00	80.00	36.12	36.00
		WEIGHTED AVERAGE FOR THE FOURTH QUARTER		249.00	80.00	36.12	36.00
		WEIGHTED AVERAGE FOR THE YEAR		249.00	80.00	36.12	36.00
=====	607-53172	Fence CL (72 In)		Lin Foot	=====		
ER0502-092		US 50 MP 204 EB MONARCH TRUCK	08/29/22	50.00	80.00	117.90	58.71
		WEIGHTED AVERAGE FOR THE THIRD QUARTER		50.00	80.00	117.90	58.71
		WEIGHTED AVERAGE FOR THE YEAR		50.00	80.00	117.90	58.71
=====	607-55110	Safety Rail (Cable)		Lin Foot	=====		
STM1151-038		SH115 MP 27 TO MP 38	04/21/22	152.00	70.00	71.99	66.00
2670703-479		I-70 BRIDGE OVER HARLAN	05/05/22	1,000.00	50.00	52.13	58.00
		WEIGHTED AVERAGE FOR THE SECOND QUARTER		1,152.00	52.64	54.36	59.06
TRG0253-264		I-25 AND SH 119 PARK-N-RIDE	10/27/22	174.00	230.00	117.56	125.00

COLORADO DEPARTMENT OF TRANSPORTATION
ITEM UNIT COSTS BY PROJECTS -- 2022 COST DATA

11:31 Wednesday, March 8, 2023 370

PROJECT NUMBER	ITEM NUMBER/ PROJECT LOCATION	ITEM DESCRIPTION/ PROJECT LOCATION	DATE LET	UNIT/ QUANTITY	ENGR. EST.	AVERAGE BID	AWARDED BID
===== 607-55110 2670703-487	Safety Rail (Cable)	I-70 BRIDGES OVER WARD ROAD-	12/01/22	Lin Foot 160.00	30.00	107.42	110.00
	WEIGHTED AVERAGE FOR THE FOURTH QUARTER			334.00	134.19	113.86	117.81
	WEIGHTED AVERAGE FOR THE YEAR			1,486.00	70.97	68.93	72.26
===== 607-55200 ER0702-420	Rock Anchor	PR I-70 GWC MATERIAL FLOWS 20	05/06/22	Lin Foot 770.00	150.00	340.00	330.00
	WEIGHTED AVERAGE FOR THE SECOND QUARTER			770.00	150.00	340.00	330.00
	WEIGHTED AVERAGE FOR THE YEAR			770.00	150.00	340.00	330.00
===== 607-60001 2670703-497	Pedest Gate (Spec)	I-70_GENESEE WILDLIFE XING	09/15/22	Each 2.00	550.00	1599.73	1505.05
	WEIGHTED AVERAGE FOR THE THIRD QUARTER			2.00	550.00	1599.73	1505.05
C5502-097		US550 MP 117.28-126.06	11/17/22	2.00	2000.00	1622.84	1450.00
	WEIGHTED AVERAGE FOR THE FOURTH QUARTER			2.00	2000.00	1622.84	1450.00
	WEIGHTED AVERAGE FOR THE YEAR			4.00	1275.00	1606.66	1477.53
===== 607-60002 NHPP0702-383 STA0252-459	Game Ramp	I-70 EB AUX FRISCO TO SILVERT	01/13/22 02/03/22	Each 14.00 31.00	13000.00 8000.00	20452.70 8851.67	24000.00 9155.00
	WEIGHTED AVERAGE FOR THE FIRST QUARTER			45.00	9555.56	13833.70	13773.44
2670703-497		I-70_GENESEE WILDLIFE XING	09/15/22	14.00	9600.00	14600.27	17109.23
	WEIGHTED AVERAGE FOR THE THIRD QUARTER			14.00	9600.00	14600.27	17109.23

COLORADO DEPARTMENT OF TRANSPORTATION
ITEM UNIT COSTS BY PROJECTS -- 2022 COST DATA

11:31 Wednesday, March 8, 2023 371

PROJECT NUMBER	ITEM NUMBER/ PROJECT LOCATION	ITEM DESCRIPTION/ PROJECT LOCATION	DATE LET	UNIT/ QUANTITY	ENGR. EST.	AVERAGE BID	AWARDED BID
=====	607-60002	Game Ramp		Each	=====	=====	=====
C5502-097		US550 MP 117.28-126.06	11/17/22	2.00	15000.00	14238.94	13070.00
		WEIGHTED AVERAGE FOR THE FOURTH QUARTER		2.00	15000.00	14238.94	13070.00
		WEIGHTED AVERAGE FOR THE YEAR		61.00	9744.26	14124.17	14515.97
=====	607-60004	4 Ft Gate Walk		Each	=====	=====	=====
NHPP0702-383		I-70 EB AUX FRISCO TO SILVERT	01/13/22	3.00	1500.00	883.11	935.00
		WEIGHTED AVERAGE FOR THE FIRST QUARTER		3.00	1500.00	883.11	935.00
		WEIGHTED AVERAGE FOR THE YEAR		3.00	1500.00	883.11	935.00
=====	607-60008	Game Ramp (Special)		Each	=====	=====	=====
FSA0702-409		I-70 VAIL WILDLIFE FENCE PHAS	05/26/22	9.00	20000.00	19000.00	19000.00
		WEIGHTED AVERAGE FOR THE SECOND QUARTER		9.00	20000.00	19000.00	19000.00
		WEIGHTED AVERAGE FOR THE YEAR		9.00	20000.00	19000.00	19000.00
=====	607-60109	8 Foot Gate (Spec)		Each	=====	=====	=====
2670703-497		I-70_GENESEE WILDLIFE XING	09/15/22	1.00	2400.00	3087.05	3038.50
		WEIGHTED AVERAGE FOR THE THIRD QUARTER		1.00	2400.00	3087.05	3038.50
		WEIGHTED AVERAGE FOR THE YEAR		1.00	2400.00	3087.05	3038.50
=====	607-60111	10 Ft Gate (Spec)		Each	=====	=====	=====
C5502-097		US550 MP 117.28-126.06	11/17/22	3.00	2500.00	2625.11	1570.00
		WEIGHTED AVERAGE FOR THE FOURTH QUARTER		3.00	2500.00	2625.11	1570.00
		WEIGHTED AVERAGE FOR THE YEAR		3.00	2500.00	2625.11	1570.00

COLORADO DEPARTMENT OF TRANSPORTATION
 ITEM UNIT COSTS BY PROJECTS -- 2022 COST DATA

11:31 Wednesday, March 8, 2023 372

PROJECT NUMBER	ITEM NUMBER/ PROJECT LOCATION	ITEM DESCRIPTION/ PROJECT LOCATION	DATE LET	UNIT/ QUANTITY	ENGR. EST.	AVERAGE BID	AWARDED BID
=====	607-60114	14 Ft Gate		Each	=====	=====	=====
2670703-497		I-70_GENESEE WILDLIFE XING	09/15/22	4.00	1600.00	1661.39	1573.20
		WEIGHTED AVERAGE FOR THE THIRD QUARTER		4.00	1600.00	1661.39	1573.20
C5502-097 IM025A-050		US550 MP 117.28-126.06	11/17/22	1.00	2500.00	2248.67	744.00
		I25-MP103.9 - INTERSECTION DR	12/01/22	1.00	1700.00	2166.67	1500.00
		WEIGHTED AVERAGE FOR THE FOURTH QUARTER		2.00	2100.00	2207.67	1122.00
		WEIGHTED AVERAGE FOR THE YEAR		6.00	1766.67	1757.79	1422.80
=====	607-60116	16 Ft Gate		Each	=====	=====	=====
NHPP0702-383 STA0252-459		I-70 EB AUX FRISCO TO SILVERT	01/13/22	1.00	2500.00	2213.03	2500.00
			02/03/22	1.00	3072.00	3117.00	2750.00
		WEIGHTED AVERAGE FOR THE FIRST QUARTER		2.00	2786.00	2552.02	2625.00
NHPP0931-033		SH93:US6 TO 58TH RESURFACING	12/15/22	2.00	2500.00	1470.44	2565.00
		WEIGHTED AVERAGE FOR THE FOURTH QUARTER		2.00	2500.00	1547.80	1926.00
		WEIGHTED AVERAGE FOR THE YEAR		4.00	2643.00	1834.72	2125.71
=====	607-60117	16 Ft Gate (Spec)		Each	=====	=====	=====
C5502-097		US550 MP 117.28-126.06	11/17/22	4.00	2800.00	4591.83	2590.00
		WEIGHTED AVERAGE FOR THE FOURTH QUARTER		4.00	2800.00	4591.83	2590.00
		WEIGHTED AVERAGE FOR THE YEAR		4.00	2800.00	4591.83	2590.00
=====	607-60120	20 Ft Gate		Each	=====	=====	=====
NHPP0702-383		I-70 EB AUX FRISCO TO SILVERT	01/13/22	1.00	2500.00	2519.88	2800.00
		WEIGHTED AVERAGE FOR THE FIRST QUARTER		1.00	2500.00	2519.88	2800.00

COLORADO DEPARTMENT OF TRANSPORTATION
ITEM UNIT COSTS BY PROJECTS -- 2022 COST DATA

11:31 Wednesday, March 8, 2023 373

PROJECT NUMBER	ITEM NUMBER/ PROJECT LOCATION	ITEM DESCRIPTION/ PROJECT LOCATION	DATE LET	UNIT/ QUANTITY	ENGR. EST.	AVERAGE BID	AWARDED BID
=====	607-60120	20 Ft Gate		Each	=====	=====	=====
C5502-097		US550 MP 117.28-126.06	11/17/22	1.00	3000.00	3925.51	1190.00
		WEIGHTED AVERAGE FOR THE FOURTH QUARTER		1.00	3000.00	3925.51	1190.00
		WEIGHTED AVERAGE FOR THE YEAR		2.00	2750.00	3046.99	1995.00
=====	607-60121	20 Ft Gate (Spec)		Each	=====	=====	=====
C5502-097		US550 MP 117.28-126.06	11/17/22	4.00	3500.00	6580.07	2670.00
		WEIGHTED AVERAGE FOR THE FOURTH QUARTER		4.00	3500.00	6580.07	2670.00
		WEIGHTED AVERAGE FOR THE YEAR		4.00	3500.00	6580.07	2670.00
=====	607-60320	20 Ft Gate Twin		Each	=====	=====	=====
FSA052A-057		SH52 BOX CULVERT EXTENSION (M 08/04/22		1.00	1000.00	1255.87	1560.00
		WEIGHTED AVERAGE FOR THE THIRD QUARTER		1.00	1000.00	1255.87	1560.00
		WEIGHTED AVERAGE FOR THE YEAR		1.00	1000.00	1255.87	1560.00
=====	607-60620	Road Closure Gate		Each	=====	=====	=====
NHPP0702-383 ER007A-035		I-70 EB AUX FRISCO TO SILVERT	01/13/22	2.00	1700.00	23864.66	23000.00
			03/15/22	4.00	38760.00	41473.00	41473.00
		WEIGHTED AVERAGE FOR THE FIRST QUARTER		6.00	26406.67	28895.61	35315.33
2670403-065		US40_FLOYD HILL ROUNDABOUTS	09/15/22	1.00	15000.00	38818.53	35300.00
		WEIGHTED AVERAGE FOR THE THIRD QUARTER		1.00	15000.00	38818.53	35300.00
STA3852-015		US 385 HOLYOKE NORTH	10/27/22	2.00	30000.00	45000.00	45000.00

COLORADO DEPARTMENT OF TRANSPORTATION
ITEM UNIT COSTS BY PROJECTS -- 2022 COST DATA

11:31 Wednesday, March 8, 2023 374

PROJECT NUMBER	ITEM NUMBER/ PROJECT LOCATION	ITEM DESCRIPTION/ PROJECT LOCATION	DATE LET	UNIT/ QUANTITY	ENGR. EST.	AVERAGE BID	AWARDED BID
=====	607-60620	Road Closure Gate		Each =====			
STR096A-050	SH 96 MP 168.99 TO 193.77		12/22/22	1.00	16300.00	72666.67	70000.00
	WEIGHTED AVERAGE FOR THE FOURTH QUARTER			3.00	25433.33	61600.00	53333.33
	WEIGHTED AVERAGE FOR THE YEAR			10.00	24974.00	37681.55	40719.20
=====	608-00000	Conc Sidewalk		Sq Yard =====			
NHPP2873-189	US 287 (FEDERAL BLVD) - COLFA		01/06/22	210.00	75.00	114.28	97.33
STA0252-459			02/03/22	15.00	250.00	200.88	350.00
CR100-362			03/14/22	1,509.00	214.76	214.76	214.76
STR092A-031			03/17/22	223.00	90.00	124.00	124.00
NHM765-007			03/31/22	600.00	65.00	99.60	60.76
	WEIGHTED AVERAGE FOR THE FIRST QUARTER			2,557.00	157.47	144.00	161.86
NH0504-911			04/07/22	694.00	93.00	91.90	91.80
CC030-081	ADA RAMP AND CURBS - FT. LUPT		04/14/22	1,281.00	120.00	121.90	79.00
CM760-047	COLFAX AND QUAIL		05/12/22	73.00	120.00	118.40	148.00
	WEIGHTED AVERAGE FOR THE SECOND QUARTER			2,048.00	110.85	114.23	85.80
NHPP0701-231	I-70 SALT WASH BRIDGES SCOUR		09/29/22	212.00	150.00	80.50	71.00
	WEIGHTED AVERAGE FOR THE THIRD QUARTER			212.00	150.00	80.50	71.00
STA207A-004	Resurfacing SH207A MANZANOLA		10/27/22	99.00	175.00	142.07	136.20
FSAM240-200	SH21B CO SPRINGS SIGNAL REPLA		10/27/22	169.40	85.00	191.00	132.00
TRG0253-264	I-25 AND SH 119 PARK-N-RIDE		10/27/22	2,950.00	40.00	63.81	58.00
STA3852-015	US 385 HOLYOKE NORTH		10/27/22	317.00	120.00	125.00	125.00
C5502-097	US550 MP 117.28-126.06		11/17/22	29.00	200.00	131.70	102.00
STAM420-001	US 285 AT HWY 9C IMPROVEMENTS		12/01/22	121.00	77.00	93.22	89.86
BR2854-148	INTERSECTION OF US 285 & SH 9						
STM0091-046	ADA RAMP IMPROVEMENTS - FAIRP						
IM025A-050	I25-MP103.9 - INTERSECTION DR		12/01/22	550.00	80.00	105.67	75.00
NHPP0021-041	SH2 RESURFACING MLK TO 52ND		12/01/22	119.90	115.00	98.54	128.14
	WEIGHTED AVERAGE FOR THE FOURTH QUARTER			4,355.30	59.85	72.32	72.79
	WEIGHTED AVERAGE FOR THE YEAR			9,172.30	100.53	86.90	100.48

COLORADO DEPARTMENT OF TRANSPORTATION
ITEM UNIT COSTS BY PROJECTS -- 2022 COST DATA

11:31 Wednesday, March 8, 2023 375

PROJECT NUMBER	ITEM NUMBER/ PROJECT LOCATION	ITEM DESCRIPTION/ PROJECT LOCATION	DATE LET	UNIT/ QUANTITY	ENGR. EST.	AVERAGE BID	AWARDED BID
=====	608-00006	Conc Sidewalk (6 In)		Sq Yard	=====		
NHPP0702-383		I-70 EB AUX FRISCO TO SILVERT	01/13/22	882.00	80.00	76.49	77.00
NHPP0063-063			02/24/22	140.00	120.00	119.70	175.00
NHPP 0761-238		I-76 DAHLIA TO YORK	03/10/22	124.00	70.00	71.83	70.00
C0761-239							
		WEIGHTED AVERAGE FOR THE FIRST QUARTER		1,146.00	83.80	77.81	88.21
2670703-479		I-70 BRIDGE OVER HARLAN	05/05/22	628.00	75.00	118.03	83.50
NHPP072A-047		SH-72 RESURFACING: I-70 TO IN	06/09/22	216.00	85.00	95.17	95.17
		WEIGHTED AVERAGE FOR THE SECOND QUARTER		844.00	77.56	116.79	86.49
NHPP0063-054		US 6 FROM I70-B TO 33 RD. (MP	08/18/22	2,147.00	70.00	81.75	65.00
C1211-099		SH 121 NORTH SGA SIGNALS	08/25/22	644.00	90.00	143.00	150.00
		WEIGHTED AVERAGE FOR THE THIRD QUARTER		2,791.00	74.61	95.88	84.61
TRG0253-264		I-25 AND SH 119 PARK-N-RIDE	10/27/22	1,089.00	80.00	75.23	67.00
STU0252-457		I-25:ALAMEDA RIVER PH 2.0	11/03/22	2,486.00	80.00	66.88	73.00
STAM420-001		US 285 AT HWY 9C IMPROVEMENTS	12/01/22	1,650.00	70.00	79.81	89.86
BR2854-148		INTERSECTION OF US 285 & SH 9					
STM0091-046		ADA RAMP IMPROVEMENTS - FAIRP					
2670703-487		I-70 BRIDGES OVER WARD ROAD-	12/01/22	193.00	110.00	128.64	80.00
NHPP083A-046		SH83 RESURFACING STROH RD TO	12/08/22	100.00	90.00	104.59	101.18
NHPP0931-033		SH93:US6 TO 58TH RESURFACING	12/15/22	163.00	80.00	83.24	69.70
		WEIGHTED AVERAGE FOR THE FOURTH QUARTER		5,681.00	78.29	76.48	77.39
		WEIGHTED AVERAGE FOR THE YEAR		10,462.00	77.86	83.42	81.23
=====	608-00010	Conc Curb Ramp		Sq Yard	=====		
NHPP2873-189		US 287 (FEDERAL BLVD) - COLFA	01/06/22	2,411.00	140.00	197.88	180.93
NHPP0702-383		I-70 EB AUX FRISCO TO SILVERT	01/13/22	18.00	200.00	178.66	190.00
NHPP0063-063			02/24/22	122.00	200.00	157.50	200.00

COLORADO DEPARTMENT OF TRANSPORTATION
ITEM UNIT COSTS BY PROJECTS -- 2022 COST DATA

11:31 Wednesday, March 8, 2023 376

PROJECT NUMBER	ITEM NUMBER/ PROJECT LOCATION	ITEM DESCRIPTION/ PROJECT LOCATION	DATE LET	UNIT/ QUANTITY	ENGR. EST.	AVERAGE BID	AWARDED BID
===== 608-00010							
		Conc Curb Ramp		Sq Yard			
CR100-362			03/14/22	3,397.00	278.80	278.80	278.80
STR092A-031			03/17/22	502.00	180.00	216.00	216.00
NHM765-007			03/31/22	486.00	200.00	230.76	297.08
WEIGHTED AVERAGE FOR THE FIRST QUARTER				6,936.00	216.29	218.77	239.90
NH0504-911			04/07/22	306.00	195.00	206.60	243.20
CC030-081		ADA RAMP AND CURBS - FT. LUPT	04/14/22	2,922.00	200.00	178.60	155.00
2670703-479		I-70 BRIDGE OVER HARLAN	05/05/22	142.00	180.00	233.67	266.51
CM760-047		COLFAX AND QUAIL	05/12/22	68.00	229.00	228.00	282.00
NHPP072A-047		SH-72 RESURFACING: I-70 TO IN	06/09/22	1,555.00	200.00	162.64	162.64
WEIGHTED AVERAGE FOR THE SECOND QUARTER				4,993.00	199.52	183.22	167.69
NHPP0063-054		US 6 FROM I70-B TO 33 RD. (MP	08/18/22	667.00	60.00	239.32	150.00
C1211-099		SH 121 NORTH SGA SIGNALS	08/25/22	662.00	220.00	192.50	175.00
SHE2873-193		US 287 & CO 52 INTERSECTION I	09/15/22	156.00	230.00	194.50	162.00
WEIGHTED AVERAGE FOR THE THIRD QUARTER				1,485.00	149.19	210.40	162.41
STA207A-004		Resurfacing SH207A MANZANOLA	10/27/22	154.00	250.00	312.67	328.00
FSAM240-200		SH21B CO SPRINGS SIGNAL REPLA	10/27/22	160.00	100.00	290.00	270.00
TRG0253-264		I-25 AND SH 119 PARK-N-RIDE	10/27/22	521.00	200.00	237.44	210.00
STA3852-015		US 385 HOLYOKE NORTH	10/27/22	1,004.00	230.00	200.00	200.00
STU0252-457		I-25:ALAMEDA RIVER PH 2.0	11/03/22	242.00	185.00	177.52	215.00
STAM420-001		US 285 AT HWY 9C IMPROVEMENTS	12/01/22	866.00	250.00	284.01	338.61
BR2854-148		INTERSECTION OF US 285 & SH 9					
STM0091-046		ADA RAMP IMPROVEMENTS - FAIRP					
IM025A-050		I25-MP103.9 - INTERSECTION DR	12/01/22	153.00	150.00	246.67	200.00
NHPP0021-041		SH2 RESURFACING MLK TO 52ND	12/01/22	241.30	275.00	179.09	191.58
NHPP083A-046		SH83 RESURFACING STROH RD TO	12/08/22	253.00	175.00	221.92	224.84
NHPP0931-033		SH93:US6 TO 58TH RESURFACING	12/15/22	494.00	250.00	167.37	140.45
WEIGHTED AVERAGE FOR THE FOURTH QUARTER				4,088.30	222.09	233.98	232.93
WEIGHTED AVERAGE FOR THE YEAR				17,502.30	207.17	213.43	211.10
===== 608-00012							
		Curb Ramp (Spec)		Sq Yard			
FSAM240-200		SH21B CO SPRINGS SIGNAL REPLA	10/27/22	312.00	150.00	297.75	295.00

COLORADO DEPARTMENT OF TRANSPORTATION
 ITEM UNIT COSTS BY PROJECTS -- 2022 COST DATA

11:31 Wednesday, March 8, 2023 377

PROJECT NUMBER	ITEM NUMBER/ PROJECT LOCATION	ITEM DESCRIPTION/ PROJECT LOCATION	DATE LET	UNIT/ QUANTITY	ENGR. EST.	AVERAGE BID	AWARDED BID
=====	608-00012	Curb Ramp (Spec)		Sq Yard			
STA3852-015		US 385 HOLYOKE NORTH	10/27/22	105.00	250.00	252.00	252.00
		WEIGHTED AVERAGE FOR THE FOURTH QUARTER		417.00	175.18	294.20	284.17
		WEIGHTED AVERAGE FOR THE YEAR		417.00	175.18	294.20	284.17
=====	608-00015	Detectable Warnings		Sq Foot			
NHPP2873-189		US 287 (FEDERAL BLVD) - COLFA	01/06/22	430.00	96.00	114.55	112.30
STR0505-050			01/13/22	6.00	100.00	1175.00	1000.00
NHPP0063-063			02/24/22	30.00	75.00	58.60	75.00
CR100-362			03/14/22	140.00	103.97	103.97	103.97
		WEIGHTED AVERAGE FOR THE FIRST QUARTER		606.00	96.84	121.90	117.32
CC030-081		ADA RAMP AND CURBS - FT. LUPT	04/14/22	12.00	100.00	88.44	82.00
		WEIGHTED AVERAGE FOR THE SECOND QUARTER		12.00	100.00	88.44	82.00
C1211-099		SH 121 NORTH SGA SIGNALS	08/25/22	32.00	125.00	92.50	120.00
		WEIGHTED AVERAGE FOR THE THIRD QUARTER		32.00	125.00	92.50	120.00
		WEIGHTED AVERAGE FOR THE YEAR		650.00	98.29	120.39	116.80
=====	608-00017	Curb Ramp (Temp Perpendicular)		Each			
NHPP0063-063			02/24/22	2.00	500.00	964.00	1400.00
		WEIGHTED AVERAGE FOR THE FIRST QUARTER		2.00	500.00	964.00	1400.00
		WEIGHTED AVERAGE FOR THE YEAR		2.00	500.00	964.00	1400.00
=====	608-00018	Curb Ramp (Temp Parallel) (Single)		Each			
NHPP0063-063			02/24/22	2.00	500.00	964.00	1400.00
		WEIGHTED AVERAGE FOR THE FIRST QUARTER		2.00	500.00	964.00	1400.00
		WEIGHTED AVERAGE FOR THE YEAR		2.00	500.00	964.00	1400.00

COLORADO DEPARTMENT OF TRANSPORTATION
ITEM UNIT COSTS BY PROJECTS -- 2022 COST DATA

11:31 Wednesday, March 8, 2023 378

PROJECT NUMBER	ITEM NUMBER/ PROJECT LOCATION	ITEM DESCRIPTION/ PROJECT LOCATION	DATE LET	UNIT/ QUANTITY	ENGR. EST.	AVERAGE BID	AWARDED BID
=====	608-00026	Conc Bikeway (6 In)		Sq Yard	=====		
STU0252-457		I-25:ALAMEDA RIVER PH 2.0	11/03/22	1,150.00	90.00	96.79	78.00
	WEIGHTED	AVERAGE FOR THE FOURTH QUARTER		1,150.00	90.00	96.79	78.00
		WEIGHTED AVERAGE FOR THE YEAR		1,150.00	90.00	96.79	78.00
=====	608-00350	Conc Sidewalk (C)		Sq Yard	=====		
NHPP0701-231		I-70 SALT WASH BRIDGES SCOUR	09/29/22	55.00	300.00	103.51	101.00
	WEIGHTED	AVERAGE FOR THE THIRD QUARTER		55.00	300.00	103.51	101.00
		WEIGHTED AVERAGE FOR THE YEAR		55.00	300.00	103.51	101.00
=====	608-01600	Aggregate Walkway		Sq Yard	=====		
FBR0761-236		I-76 OVER CLR CRK SCOUR MIT	08/25/22	84.00	75.00	68.00	65.00
	WEIGHTED	AVERAGE FOR THE THIRD QUARTER		84.00	75.00	68.00	65.00
		WEIGHTED AVERAGE FOR THE YEAR		84.00	75.00	68.00	65.00
=====	608-10000	Sidewalk Drain		Lin Foot	=====		
NH0504-911			04/07/22	5.00	400.00	802.00	854.00
CC030-081		ADA RAMP AND CURBS - FT. LUPT	04/14/22	10.00	500.00	524.76	350.00
	WEIGHTED	AVERAGE FOR THE SECOND QUARTER		15.00	466.67	594.07	518.00
		WEIGHTED AVERAGE FOR THE YEAR		15.00	466.67	594.07	518.00
=====	608-10010	Sidewalk Drain		Each	=====		
STU0252-457		I-25:ALAMEDA RIVER PH 2.0	11/03/22	1.00	2500.00	5803.33	3600.00
	WEIGHTED	AVERAGE FOR THE FOURTH QUARTER		1.00	2500.00	5803.33	3600.00
		WEIGHTED AVERAGE FOR THE YEAR		1.00	2500.00	5803.33	3600.00

COLORADO DEPARTMENT OF TRANSPORTATION
ITEM UNIT COSTS BY PROJECTS -- 2022 COST DATA

11:31 Wednesday, March 8, 2023 379

PROJECT NUMBER	ITEM NUMBER/ PROJECT LOCATION	ITEM DESCRIPTION/ PROJECT LOCATION	DATE LET	UNIT/ QUANTITY	ENGR. EST.	AVERAGE BID	AWARDED BID
===== 609-20004		Curb and Gutter Ty 2 (Sect II-M) (Spec)		Lin Foot	=====		
FSAM240-200		SH21B CO SPRINGS SIGNAL REPLA	10/27/22	176.00	80.00	100.24	53.95
	WEIGHTED AVERAGE FOR THE FOURTH QUARTER			176.00	80.00	100.24	53.95
	WEIGHTED AVERAGE FOR THE YEAR			176.00	80.00	100.24	53.95
===== 609-20010		Curb Ty 2 B		Lin Foot	=====		
NHPP0063-063			02/24/22	35,832.00	15.00	28.50	28.00
	WEIGHTED AVERAGE FOR THE FIRST QUARTER			35,832.00	15.00	28.50	28.00
CC030-081		ADA RAMP AND CURBS - FT. LUPT	04/14/22	518.00	55.00	44.58	41.00
	WEIGHTED AVERAGE FOR THE SECOND QUARTER			518.00	55.00	44.58	41.00
NHPP0063-054 C1211-099		US 6 FROM I70-B TO 33 RD. (MP SH 121 NORTH SGA SIGNALS	08/18/22 08/25/22	1,175.00 214.00	30.00 40.00	32.09 32.50	27.00 30.00
	WEIGHTED AVERAGE FOR THE THIRD QUARTER			1,389.00	31.54	32.15	27.46
STRC090-011 STAM420-001 BR2854-148 STM0091-046 NHPP083A-046		US 50B AND SH71/CR18 INTERSEC US 285 AT HWY 9C IMPROVEMENTS INTERSECTION OF US 285 & SH 9 ADA RAMP IMPROVEMENTS - FAIRP SH83 RESURFACING STROH RD TO	11/17/22 12/01/22 12/08/22	1,105.00 272.00 6.00	52.00 31.38 50.00	68.50 45.31 74.74	51.00 33.86 37.47
	WEIGHTED AVERAGE FOR THE FOURTH QUARTER			1,383.00	47.94	60.90	47.57
	WEIGHTED AVERAGE FOR THE YEAR			39,122.00	17.28	30.30	28.84
===== 609-20011		Curb Ty 2 M		Lin Foot	=====		
2670703-479		I-70 BRIDGE OVER HARLAN	05/05/22	86.00	50.00	45.88	44.64
	WEIGHTED AVERAGE FOR THE SECOND QUARTER			86.00	50.00	45.88	44.64
	WEIGHTED AVERAGE FOR THE YEAR			86.00	50.00	45.88	44.64

COLORADO DEPARTMENT OF TRANSPORTATION
ITEM UNIT COSTS BY PROJECTS -- 2022 COST DATA

11:31 Wednesday, March 8, 2023 380

PROJECT NUMBER	ITEM NUMBER/ PROJECT LOCATION	ITEM DESCRIPTION/ PROJECT LOCATION	DATE LET	UNIT/ QUANTITY	ENGR. EST.	AVERAGE BID	AWARDED BID
===== 609-21010		C and G Ty 2 I-B		Lin Foot	=====		
NHPP0702-383		I-70 EB AUX FRISCO TO SILVERT	01/13/22	378.00	50.00	37.56	36.00
NHPP 0761-238		I-76 DAHLIA TO YORK	03/10/22	100.00	30.00	38.74	28.00
C0761-239							
CR100-362			03/14/22	421.00	58.30	58.30	58.30
NHM765-007			03/31/22	5.00	40.00	98.44	157.32
		WEIGHTED AVERAGE FOR THE FIRST QUARTER		904.00	51.60	40.95	46.17
2670703-479		I-70 BRIDGE OVER HARLAN	05/05/22	650.00	30.00	39.15	29.00
NHPP072A-047		SH-72 RESURFACING: I-70 TO IN	06/09/22	2,906.00	35.00	54.21	54.21
		WEIGHTED AVERAGE FOR THE SECOND QUARTER		3,556.00	34.09	45.58	49.60
NHPP0063-054		US 6 FROM I70-B TO 33 RD. (MP	08/18/22	5,980.00	25.00	26.76	22.00
C1211-099		SH 121 NORTH SGA SIGNALS	08/25/22	700.00	45.00	36.50	35.00
2670403-065		US40_FLOYD HILL ROUNDABOUTS	09/15/22	1,732.00	50.00	31.02	24.00
		WEIGHTED AVERAGE FOR THE THIRD QUARTER		8,412.00	31.81	28.69	23.49
TRG0253-264		I-25 AND SH 119 PARK-N-RIDE	10/27/22	2,620.00	30.00	39.29	35.00
STU0252-457		I-25:ALAMEDA RIVER PH 2.0	11/03/22	687.00	50.00	36.09	33.50
NHPP0853-126		US85C: PLATTEVILLE NORTH MP (11/10/22	458.00	30.00	41.94	31.00
STAM420-001		US 285 AT HWY 9C IMPROVEMENTS	12/01/22	440.00	37.00	50.80	44.28
BR2854-148		INTERSECTION OF US 285 & SH 9					
STM0091-046		ADA RAMP IMPROVEMENTS - FAIRP					
2670703-487		I-70 BRIDGES OVER WARD ROAD-	12/01/22	172.00	32.00	50.78	70.00
IM025A-050		I25-MP103.9 - INTERSECTION DR	12/01/22	1,149.00	32.00	41.67	35.00
NHPP083A-046		SH83 RESURFACING STROH RD TO	12/08/22	258.00	45.00	56.98	49.96
NHPP0063-048		US6 / 20 ROAD INTERSECTION IM	12/15/22	355.00	40.00	42.47	32.00
NHPP0931-033		SH93:US6 TO 58TH RESURFACING	12/15/22	307.00	30.00	48.23	41.00
		WEIGHTED AVERAGE FOR THE FOURTH QUARTER		6,446.00	34.17	41.10	36.84
		WEIGHTED AVERAGE FOR THE YEAR		19,318.00	33.94	37.92	33.82
===== 609-21011		C and G Ty 2 I-M		Lin Foot	=====		
FSA3921-019		SH 392 AND WCR 55 ISLANDS	06/02/22	41.00	33.00	123.33	90.00
		WEIGHTED AVERAGE FOR THE SECOND QUARTER		41.00	33.00	123.33	90.00

COLORADO DEPARTMENT OF TRANSPORTATION
ITEM UNIT COSTS BY PROJECTS -- 2022 COST DATA

11:31 Wednesday, March 8, 2023 381

PROJECT NUMBER	ITEM NUMBER/ PROJECT LOCATION	ITEM DESCRIPTION/ PROJECT LOCATION	DATE LET	UNIT/ QUANTITY	ENGR. EST.	AVERAGE BID	AWARDED BID
===== 609-21011		C and G Ty 2 I-M		Lin Foot	=====		
NHPP0063-054		US 6 FROM I70-B TO 33 RD. (MP	08/18/22	140.00	30.00	31.42	30.00
SHE2873-193		US 287 & CO 52 INTERSECTION I	09/15/22	527.00	30.00	36.69	25.00
		WEIGHTED AVERAGE FOR THE THIRD QUARTER		667.00	30.00	36.26	26.05
IM025A-050		I25-MP103.9 - INTERSECTION DR	12/01/22	634.00	30.00	46.00	35.00
		WEIGHTED AVERAGE FOR THE FOURTH QUARTER		634.00	30.00	46.00	35.00
		WEIGHTED AVERAGE FOR THE YEAR		1,342.00	30.09	41.61	32.23
===== 609-21013		C and G Ty 2 I-M (Spec)		Lin Foot	=====		
2670403-065		US40_FLOYD HILL ROUNDABOUTS	09/15/22	578.00	50.00	36.46	32.00
		WEIGHTED AVERAGE FOR THE THIRD QUARTER		578.00	50.00	36.46	32.00
		WEIGHTED AVERAGE FOR THE YEAR		578.00	50.00	36.46	32.00
===== 609-21020		C and G Ty 2 II-B		Lin Foot	=====		
NHPP2873-189		US 287 (FEDERAL BLVD) - COLFA	01/06/22	387.00	36.00	54.51	44.92
NHPP1601-083			02/03/22	912.00	50.00	80.11	80.00
NHPP0063-063			02/24/22	1,218.00	40.00	38.85	45.00
NHPP 0761-238		I-76 DAHLIA TO YORK	03/10/22	140.00	35.00	41.52	28.00
C0761-239							
CR100-362			03/14/22	473.00	71.36	71.36	71.36
STR092A-031			03/17/22	271.00	60.00	81.50	81.50
NHM765-007			03/31/22	8,167.00	32.00	42.79	39.33
		WEIGHTED AVERAGE FOR THE FIRST QUARTER		11,568.00	36.70	45.87	45.48
NH0504-911			04/07/22	2,720.00	32.00	44.85	49.70
CC030-081		ADA RAMP AND CURBS - FT. LUPT	04/14/22	2,426.00	50.00	52.02	41.00

PROJECT NUMBER	ITEM NUMBER/ PROJECT LOCATION	ITEM DESCRIPTION/ PROJECT LOCATION	DATE LET	UNIT/ QUANTITY	ENGR. EST.	AVERAGE BID	AWARDED BID
=====	609-21020	C and G Ty 2 II-B		Lin Foot	=====	=====	=====
2670703-479		I-70 BRIDGE OVER HARLAN	05/05/22	1,096.00	36.00	42.22	30.50
CM760-047		COLFAX AND QUAIL	05/12/22	82.00	42.50	59.40	57.00
NHPP072A-047		SH-72 RESURFACING: I-70 TO IN	06/09/22	76.00	40.00	54.21	54.21
		WEIGHTED AVERAGE FOR THE SECOND QUARTER		6,400.00	39.74	46.95	43.26
NHPP063-054		US 6 FROM I70-B TO 33 RD. (MP	08/18/22	5,544.00	30.00	32.77	22.00
C1211-099		SH 121 NORTH SGA SIGNALS	08/25/22	947.00	50.00	38.50	35.00
2670403-065		US40_FLOYD HILL ROUNDABOUTS	09/15/22	4,439.00	50.00	33.91	28.00
		WEIGHTED AVERAGE FOR THE THIRD QUARTER		10,930.00	39.86	33.76	25.56
STA207A-004		Resurfacing SH207A MANZANOLA	10/27/22	567.00	75.00	50.17	49.50
FSAM240-200		SH21B CO SPRINGS SIGNAL REPLA	10/27/22	148.00	40.00	95.94	44.75
TRG0253-264		I-25 AND SH 119 PARK-N-RIDE	10/27/22	5,191.00	30.00	40.73	35.00
STA3852-015		US 385 HOLYOKE NORTH	10/27/22	374.00	95.00	95.00	95.00
NHPP0343-048		US 34 (MP 169.3-171.4)	11/01/22	1,107.00	40.54	74.84	83.00
STU0252-457		I-25:ALAMEDA RIVER PH 2.0	11/03/22	2,072.00	55.00	39.65	41.00
STRC090-011		US 50B AND SH71/CR18 INTERSEC	11/17/22	553.00	36.00	63.63	52.25
STAM420-001		US 285 AT HWY 9C IMPROVEMENTS	12/01/22	9,712.00	35.00	45.45	49.49
BR2854-148		INTERSECTION OF US 285 & SH 9					
STM0091-046		ADA RAMP IMPROVEMENTS - FAIRP					
IM025A-050		I25-MP103.9 - INTERSECTION DR	12/01/22	1,959.00	40.00	47.33	35.00
NHPP0021-041		SH2 RESURFACING MLK TO 52ND	12/01/22	66.40	75.00	62.73	96.03
NHPP083A-046		SH83 RESURFACING STROH RD TO	12/08/22	121.00	65.00	60.11	56.21
NHPP0063-048		US6 / 20 ROAD INTERSECTION IM	12/15/22	170.00	42.00	49.47	37.00
NHPP0931-033		SH93:US6 TO 58TH RESURFACING	12/15/22	784.00	50.00	48.23	41.00
		WEIGHTED AVERAGE FOR THE FOURTH QUARTER		22,824.40	39.25	45.50	46.37
		WEIGHTED AVERAGE FOR THE YEAR		51,722.40	38.87	44.04	41.39
=====	609-21021	C and G Ty 2 II-M		Lin Foot	=====	=====	=====
NHPP0702-413		VAIL PASS AUX PHASE 1 CAP 2	04/18/22	3,006.00	55.82	55.82	55.82
		WEIGHTED AVERAGE FOR THE SECOND QUARTER		3,006.00	55.82	55.82	55.82
2670403-065		US40_FLOYD HILL ROUNDABOUTS	09/15/22	412.00	50.00	41.73	29.00

COLORADO DEPARTMENT OF TRANSPORTATION
ITEM UNIT COSTS BY PROJECTS -- 2022 COST DATA

11:31 Wednesday, March 8, 2023 383

PROJECT NUMBER	ITEM NUMBER/ PROJECT LOCATION	ITEM DESCRIPTION/ PROJECT LOCATION	DATE LET	UNIT/ QUANTITY	ENGR. EST.	AVERAGE BID	AWARDED BID
=====	609-21021	C and G Ty 2 II-M		Lin Foot	=====	=====	=====
SHE2873-193		US 287 & CO 52 INTERSECTION I	09/15/22	3,448.00	38.00	31.32	25.00
		WEIGHTED AVERAGE FOR THE THIRD QUARTER		3,860.00	39.28	31.91	25.43
TRG0253-264		I-25 AND SH 119 PARK-N-RIDE	10/27/22	55.00	35.00	67.45	92.00
STU0252-457		I-25:ALAMEDA RIVER PH 2.0	11/03/22	48.00	45.00	56.31	51.00
STAM420-001		US 285 AT HWY 9C IMPROVEMENTS	12/01/22	110.00	35.00	56.27	49.85
BR2854-148		INTERSECTION OF US 285 & SH 9					
STM0091-046		ADA RAMP IMPROVEMENTS - FAIRP					
IM025A-050		I25-MP103.9 - INTERSECTION DR	12/01/22	108.00	35.00	60.00	35.00
		WEIGHTED AVERAGE FOR THE FOURTH QUARTER		321.00	36.50	60.82	52.25
		WEIGHTED AVERAGE FOR THE YEAR		7,187.00	46.07	36.12	39.34
=====	609-21023	C and G Ty 2 II-B (Spec)		Lin Foot	=====	=====	=====
FSAM240-200		SH21B CO SPRINGS SIGNAL REPLA	10/27/22	108.00	80.00	149.23	49.90
NHPP083A-046		SH83 RESURFACING STROH RD TO	12/08/22	10.00	75.00	96.60	81.19
		WEIGHTED AVERAGE FOR THE FOURTH QUARTER		118.00	79.58	146.90	52.55
		WEIGHTED AVERAGE FOR THE YEAR		118.00	79.58	146.90	52.55
=====	609-21100	C and G Ty 2 Variable		Lin Foot	=====	=====	=====
BRC040-057			03/17/22	120.00	50.00	54.75	50.00
		WEIGHTED AVERAGE FOR THE FIRST QUARTER		120.00	50.00	54.75	50.00
		WEIGHTED AVERAGE FOR THE YEAR		120.00	50.00	54.75	50.00
=====	609-21110	C & G Ty 2 I-B (Spec)		Lin Foot	=====	=====	=====
NHPP083A-046		SH83 RESURFACING STROH RD TO	12/08/22	66.00	70.00	93.48	74.95
		WEIGHTED AVERAGE FOR THE FOURTH QUARTER		66.00	70.00	93.48	74.95
		WEIGHTED AVERAGE FOR THE YEAR		66.00	70.00	93.48	74.95

COLORADO DEPARTMENT OF TRANSPORTATION
 ITEM UNIT COSTS BY PROJECTS -- 2022 COST DATA

11:31 Wednesday, March 8, 2023 384

PROJECT NUMBER	ITEM NUMBER/ PROJECT LOCATION	ITEM DESCRIPTION/ PROJECT LOCATION	DATE LET	UNIT/ QUANTITY	ENGR. EST.	AVERAGE BID	AWARDED BID
=====	609-21900	C and G Ty 2 (Spec)		Lin Foot	=====		
IM025A-050		I25-MP103.9 - INTERSECTION DR	12/01/22	384.00	50.00	72.00	75.00
	WEIGHTED AVERAGE FOR THE FOURTH QUARTER			384.00	50.00	72.00	75.00
	WEIGHTED AVERAGE FOR THE YEAR			384.00	50.00	72.00	75.00
=====	609-23000	Gutter (Special)		Lin Foot	=====		
NHPP0702-383		I-70 EB AUX FRISCO TO SILVERT	01/13/22	144.00	100.00	60.97	44.00
	WEIGHTED AVERAGE FOR THE FIRST QUARTER			144.00	100.00	60.97	44.00
	WEIGHTED AVERAGE FOR THE YEAR			144.00	100.00	60.97	44.00
=====	609-24002	Gutter Ty 2 (2 Ft)		Lin Foot	=====		
NHPP0702-383		I-70 EB AUX FRISCO TO SILVERT	01/13/22	750.00	30.00	26.34	24.50
	WEIGHTED AVERAGE FOR THE FIRST QUARTER			750.00	30.00	26.34	24.50
	WEIGHTED AVERAGE FOR THE YEAR			750.00	30.00	26.34	24.50
=====	609-24004	Gutter Ty 2 (4 Ft)		Lin Foot	=====		
STR092A-031			03/17/22	3.00	170.00	240.50	240.50
NHM765-007			03/31/22	213.00	53.00	98.24	34.05
	WEIGHTED AVERAGE FOR THE FIRST QUARTER			216.00	54.63	98.90	36.92
STM1151-038		SH115 MP 27 TO MP 38	04/21/22	1,039.00	40.00	60.75	84.72
	WEIGHTED AVERAGE FOR THE SECOND QUARTER			1,039.00	40.00	60.75	84.72
2670403-065		US40_FLOYD HILL ROUNDABOUTS	09/15/22	95.00	50.00	125.50	136.00
	WEIGHTED AVERAGE FOR THE THIRD QUARTER			95.00	50.00	125.50	136.00

COLORADO DEPARTMENT OF TRANSPORTATION
ITEM UNIT COSTS BY PROJECTS -- 2022 COST DATA

11:31 Wednesday, March 8, 2023 385

PROJECT NUMBER	ITEM NUMBER/ PROJECT LOCATION	ITEM DESCRIPTION/ PROJECT LOCATION	DATE LET	UNIT/ QUANTITY	ENGR. EST.	AVERAGE BID	AWARDED BID
=====	609-24004	Gutter Ty 2 (4 Ft)		Lin Foot	=====		
STAM420-001 BR2854-148 STM0091-046		US 285 AT HWY 9C IMPROVEMENTS INTERSECTION OF US 285 & SH 9 ADA RAMP IMPROVEMENTS - FAIRP	12/01/22	1,180.00	39.20	51.42	44.28
	WEIGHTED AVERAGE FOR THE FOURTH QUARTER			1,180.00	39.20	51.42	44.28
	WEIGHTED AVERAGE FOR THE YEAR			2,530.00	41.25	60.65	63.70
=====	609-24005	Gutter Ty 2 (5 Ft)		Lin Foot	=====		
STU0252-457		I-25:ALAMEDA RIVER PH 2.0	11/03/22	35.00	40.00	63.24	77.00
	WEIGHTED AVERAGE FOR THE FOURTH QUARTER			35.00	40.00	63.24	77.00
	WEIGHTED AVERAGE FOR THE YEAR			35.00	40.00	63.24	77.00
=====	609-24006	Gutter Ty 2 (6 Ft)		Lin Foot	=====		
NHPP0063-063			02/24/22	36.00	70.00	124.80	200.00
	WEIGHTED AVERAGE FOR THE FIRST QUARTER			36.00	70.00	124.80	200.00
NHPP072A-047		SH-72 RESURFACING: I-70 TO IN	06/09/22	55.00	85.00	89.00	89.00
	WEIGHTED AVERAGE FOR THE SECOND QUARTER			55.00	85.00	89.00	89.00
STA207A-004 IM025A-050		Resurfacing SH207A MANZANOLA I25-MP103.9 - INTERSECTION DR	10/27/22 12/01/22	50.00 109.00	125.00 80.00	101.85 165.00	70.55 120.00
	WEIGHTED AVERAGE FOR THE FOURTH QUARTER			159.00	94.15	145.14	104.45
	WEIGHTED AVERAGE FOR THE YEAR			250.00	88.66	137.60	114.81
=====	609-24008	Gutter Ty 2 (8 Ft)		Lin Foot	=====		
TRG0253-264		I-25 AND SH 119 PARK-N-RIDE	10/27/22	145.00	100.00	102.95	110.00

COLORADO DEPARTMENT OF TRANSPORTATION
 ITEM UNIT COSTS BY PROJECTS -- 2022 COST DATA

11:31 Wednesday, March 8, 2023 386

PROJECT NUMBER	ITEM NUMBER/ PROJECT LOCATION	ITEM DESCRIPTION/ PROJECT LOCATION	DATE LET	UNIT/ QUANTITY	ENGR. EST.	AVERAGE BID	AWARDED BID
=====	609-24008	Gutter Ty 2 (8 Ft)		Lin Foot	=====	=====	=====
STU0252-457		I-25:ALAMEDA RIVER PH 2.0	11/03/22	32.00	80.00	80.88	105.00
		WEIGHTED AVERAGE FOR THE FOURTH QUARTER		177.00	96.38	101.27	109.10
		WEIGHTED AVERAGE FOR THE YEAR		177.00	96.38	101.27	109.10
=====	609-40010	Curb Ty 4 B		Lin Foot	=====	=====	=====
STAM420-001 BR2854-148 STM0091-046		US 285 AT HWY 9C IMPROVEMENTS INTERSECTION OF US 285 & SH 9 ADA RAMP IMPROVEMENTS - FAIRP	12/01/22	220.00	41.20	30.45	23.45
		WEIGHTED AVERAGE FOR THE FOURTH QUARTER		220.00	41.20	30.45	23.45
		WEIGHTED AVERAGE FOR THE YEAR		220.00	41.20	30.45	23.45
=====	609-40100	Curb Ty 4 Variable		Lin Foot	=====	=====	=====
BRC040-057			03/17/22	120.00	50.00	58.00	50.00
		WEIGHTED AVERAGE FOR THE FIRST QUARTER		120.00	50.00	58.00	50.00
		WEIGHTED AVERAGE FOR THE YEAR		120.00	50.00	58.00	50.00
=====	609-40120	Curb Median Special		Sq Yard	=====	=====	=====
NHPP072A-047		SH-72 RESURFACING: I-70 TO IN	06/09/22	18.00	200.00	118.67	118.67
		WEIGHTED AVERAGE FOR THE SECOND QUARTER		18.00	200.00	118.67	118.67
NHPP0853-126		US85C: PLATTEVILLE NORTH MP (11/10/22	20.00	120.00	152.00	129.00
		WEIGHTED AVERAGE FOR THE FOURTH QUARTER		20.00	120.00	152.00	129.00
		WEIGHTED AVERAGE FOR THE YEAR		38.00	157.89	146.92	124.11
=====	609-60011	Curb Ty 6 M		Lin Foot	=====	=====	=====
NHPP0702-383		I-70 EB AUX FRISCO TO SILVERT	01/13/22	254.00	30.00	50.25	118.00

COLORADO DEPARTMENT OF TRANSPORTATION
ITEM UNIT COSTS BY PROJECTS -- 2022 COST DATA

11:31 Wednesday, March 8, 2023 387

PROJECT NUMBER	ITEM NUMBER/ PROJECT LOCATION	ITEM DESCRIPTION/ PROJECT LOCATION	DATE LET	UNIT/ QUANTITY	ENGR. EST.	AVERAGE BID	AWARDED BID
===== 609-60011 Curb Ty 6 M Lin Foot =====							
NHPP1601-083			02/03/22	1,125.00	8.00	23.95	25.00
STA0252-459			02/03/22	30.00	40.00	99.72	160.00
C0762-055			02/17/22	4,648.00	15.00	14.40	18.00
NHPP 0761-238		I-76 DAHLIA TO YORK	03/10/22	1,250.00	16.00	30.98	53.00
C0761-239							
BRC040-057			03/17/22	100.00	40.00	62.50	50.00
WEIGHTED AVERAGE FOR THE FIRST QUARTER				7,407.00	15.06	22.37	29.41
NH0504-911			04/07/22	349.00	25.00	18.30	21.60
STM1151-038		SH115 MP 27 TO MP 38	04/21/22	8,079.00	17.00	10.44	9.90
WEIGHTED AVERAGE FOR THE SECOND QUARTER				8,428.00	17.33	10.57	10.38
BR0343-046		US 34 TIMBER BRIDGE REPL. PKG	08/31/22	360.00	42.80	42.80	42.80
FBR0343-047		US 6/US 34 TIMBER BRIDGE REPL					
PAN0761-245		ALONG I-76 & RAMPS MILEPOST 9	09/01/22	75.00	70.00	161.50	195.00
WEIGHTED AVERAGE FOR THE THIRD QUARTER				435.00	47.49	77.71	69.04
2670703-487		I-70 BRIDGES OVER WARD ROAD-	12/01/22	536.00	30.00	25.28	11.00
IM025A-050		I25-MP103.9 - INTERSECTION DR	12/01/22	563.00	10.00	77.00	21.00
STR096A-050		SH 96 MP 168.99 TO 193.77	12/22/22	27.00	21.00	102.33	150.00
WEIGHTED AVERAGE FOR THE FOURTH QUARTER				1,126.00	19.78	46.31	19.33
WEIGHTED AVERAGE FOR THE YEAR				17,396.00	17.28	17.92	20.53
===== 609-60900 Curb Ty 6 M Special Lin Foot =====							
STR0711-022		SH 71 OVER THE ARKANSAS	08/04/22	1,783.00	25.00	15.00	13.00
WEIGHTED AVERAGE FOR THE THIRD QUARTER				1,783.00	25.00	15.00	13.00
WEIGHTED AVERAGE FOR THE YEAR				1,783.00	25.00	15.00	13.00
===== 609-71000 Curb (Special) Lin Foot =====							
NHPP0253-275		I-25 EXPRESS LANES SEGMENT 5	03/11/22	1,600.00	46.88	54.36	54.36

COLORADO DEPARTMENT OF TRANSPORTATION
ITEM UNIT COSTS BY PROJECTS -- 2022 COST DATA

11:31 Wednesday, March 8, 2023 388

PROJECT NUMBER	ITEM NUMBER/ PROJECT LOCATION	ITEM DESCRIPTION/ PROJECT LOCATION	DATE LET	UNIT/ QUANTITY	ENGR. EST.	AVERAGE BID	AWARDED BID
===== 609-71000 Curb (Special) Lin Foot =====							
NHM765-007			03/31/22	103.00	45.00	57.27	21.14
	WEIGHTED AVERAGE FOR THE FIRST QUARTER			1,703.00	46.77	54.83	52.35
	WEIGHTED AVERAGE FOR THE YEAR			1,703.00	46.77	54.83	52.35
===== 610-00020 Median Cover (Pattern Conc) Sq Foot =====							
NHPP0702-383		I-70 EB AUX FRISCO TO SILVERT	01/13/22	55.00	30.00	43.83	22.00
NHM765-007			03/31/22	478.00	13.00	16.61	17.67
	WEIGHTED AVERAGE FOR THE FIRST QUARTER			533.00	14.75	20.99	18.12
2670703-479		I-70 BRIDGE OVER HARLAN	05/05/22	5,924.00	25.00	17.16	15.25
NHPP072A-047		SH-72 RESURFACING: I-70 TO IN	06/09/22	9,643.00	16.00	24.09	24.09
	WEIGHTED AVERAGE FOR THE SECOND QUARTER			15,567.00	19.42	18.64	20.73
C1211-099		SH 121 NORTH SGA SIGNALS	08/25/22	5,491.00	20.00	24.00	24.00
2670403-065		US40_FLOYD HILL ROUNDABOUTS	09/15/22	13,895.00	22.00	20.82	14.20
	WEIGHTED AVERAGE FOR THE THIRD QUARTER			19,386.00	21.43	21.49	16.98
FSAM240-200		SH21B CO SPRINGS SIGNAL REPLA	10/27/22	13,220.00	25.00	14.79	18.15
TRG0253-264		I-25 AND SH 119 PARK-N-RIDE	10/27/22	337.00	22.00	24.82	20.00
NHPP0931-033		SH93:US6 TO 58TH RESURFACING	12/15/22	4,145.00	25.00	13.57	11.25
	WEIGHTED AVERAGE FOR THE FOURTH QUARTER			17,702.00	24.94	14.88	16.57
	WEIGHTED AVERAGE FOR THE YEAR			53,188.00	21.95	17.96	17.95
===== 610-00024 Median Cover (4 In Pattern Conc) Sq Foot =====							
NHPP0063-054		US 6 FROM I70-B TO 33 RD. (MP	08/18/22	11,594.00	15.00	9.95	8.00
	WEIGHTED AVERAGE FOR THE THIRD QUARTER			11,594.00	15.00	9.95	8.00
	WEIGHTED AVERAGE FOR THE YEAR			11,594.00	15.00	9.95	8.00

COLORADO DEPARTMENT OF TRANSPORTATION
ITEM UNIT COSTS BY PROJECTS -- 2022 COST DATA

11:31 Wednesday, March 8, 2023 389

PROJECT NUMBER	ITEM NUMBER/ PROJECT LOCATION	ITEM DESCRIPTION/ PROJECT LOCATION	DATE LET	UNIT/ QUANTITY	ENGR. EST.	AVERAGE BID	AWARDED BID
===== 610-00026 Median Cover (6 In Pattern Conc) Sq Foot =====							
NHPP0063-063			02/24/22	23,417.00	10.00	11.35	12.00
	WEIGHTED AVERAGE FOR THE FIRST QUARTER			23,417.00	10.00	11.35	12.00
	WEIGHTED AVERAGE FOR THE YEAR			23,417.00	10.00	11.35	12.00
===== 610-00030 Median Cover Matl (Conc) Sq Foot =====							
NHPP2873-189		US 287 (FEDERAL BLVD) - COLFA	01/06/22	523.00	9.00	23.41	19.96
NHPP 0761-238		I-76 DAHLIA TO YORK	03/10/22	1,800.00	13.00	13.02	10.00
C0761-239							
NHPP0253-275		I-25 EXPRESS LANES SEGMENT 5	03/11/22	11,308.00	13.10	12.33	12.33
CR100-362			03/14/22	25.00	375.27	375.27	375.27
	WEIGHTED AVERAGE FOR THE FIRST QUARTER			13,656.00	13.59	13.85	12.98
NH0504-911			04/07/22	150.00	13.73	115.35	30.70
CC030-081		ADA RAMP AND CURBS - FT. LUPT	04/14/22	5,989.00	16.00	18.68	12.00
FSA3921-019		SH 392 AND WCR 55 ISLANDS	06/02/22	105.00	25.00	54.67	24.00
	WEIGHTED AVERAGE FOR THE SECOND QUARTER			6,244.00	16.10	20.85	12.65
NHPP0063-054		US 6 FROM I70-B TO 33 RD. (MP	08/18/22	1,682.00	12.00	10.47	9.00
SHE2873-193		US 287 & CO 52 INTERSECTION I	09/15/22	1,646.00	15.00	13.54	11.00
	WEIGHTED AVERAGE FOR THE THIRD QUARTER			3,328.00	13.48	12.76	9.99
STA3852-015		US 385 HOLYOKE NORTH	10/27/22	1,063.00	35.00	34.00	34.00
STU0252-457		I-25:ALAMEDA RIVER PH 2.0	11/03/22	2,530.00	20.00	13.78	15.50
NHPP0853-126		US85C: PLATTEVILLE NORTH MP (11/10/22	1,337.00	13.00	16.53	16.10
STRC090-011		US 50B AND SH71/CR18 INTERSEC	11/17/22	5,835.00	20.00	20.10	19.20
STAM420-001		US 285 AT HWY 9C IMPROVEMENTS	12/01/22	4,267.00	16.00	17.33	19.53
BR2854-148		INTERSECTION OF US 285 & SH 9					
STM0091-046		ADA RAMP IMPROVEMENTS - FAIRP					
IM025A-050		I25-MP103.9 - INTERSECTION DR	12/01/22	11,091.00	10.00	26.00	17.00

COLORADO DEPARTMENT OF TRANSPORTATION
ITEM UNIT COSTS BY PROJECTS -- 2022 COST DATA

11:31 Wednesday, March 8, 2023 390

PROJECT NUMBER	ITEM NUMBER/ PROJECT LOCATION	ITEM DESCRIPTION/ PROJECT LOCATION	DATE LET	UNIT/ QUANTITY	ENGR. EST.	AVERAGE BID	AWARDED BID
===== 610-00030 Median Cover Matl (Conc) Sq Foot =====							
NHPP0021-041		SH2 RESURFACING MLK TO 52ND	12/01/22	3.30	35.00	107.87	385.99
NHPP083A-046		SH83 RESURFACING STROH RD TO	12/08/22	397.00	20.00	21.49	24.98
NHPP0063-048		US6 / 20 ROAD INTERSECTION IM	12/15/22	2,258.00	18.00	13.23	9.00
	WEIGHTED AVERAGE FOR THE FOURTH QUARTER			28,781.30	15.63	20.47	17.80
	WEIGHTED AVERAGE FOR THE YEAR			52,009.30	15.01	18.57	15.42
===== 610-00055 Median Cover Matl (Stone) Sq Foot =====							
CR100-362			03/14/22	180.00	24.45	24.45	24.45
	WEIGHTED AVERAGE FOR THE FIRST QUARTER			180.00	24.45	24.45	24.45
===== 610-00110 Median Edging Lin Foot =====							
STA207A-004		Resurfacing SH207A MANZANOLA	10/27/22	75.00	30.00	37.70	37.10
IM025A-050		I25-MP103.9 - INTERSECTION DR	12/01/22	1,504.00	3.00	14.90	4.70
	WEIGHTED AVERAGE FOR THE FOURTH QUARTER			1,579.00	4.28	15.98	6.24
	WEIGHTED AVERAGE FOR THE YEAR			1,759.00	6.35	16.29	8.10
===== 610-00110 Median Edging Lin Foot =====							
IM025A-050		I25-MP103.9 - INTERSECTION DR	12/01/22	263.00	50.00	144.33	100.00
	WEIGHTED AVERAGE FOR THE FOURTH QUARTER			263.00	50.00	144.33	100.00
	WEIGHTED AVERAGE FOR THE YEAR			263.00	50.00	144.33	100.00
===== 611-00013 12 Ft Deer Gd Each =====							
C5502-097		US550 MP 117.28-126.06	11/17/22	1.00	45000.00	61261.49	38900.00
	WEIGHTED AVERAGE FOR THE FOURTH QUARTER			1.00	45000.00	61261.49	38900.00
	WEIGHTED AVERAGE FOR THE YEAR			1.00	45000.00	61261.49	38900.00
===== 611-00017 16 Ft Deer Gd Each =====							
2670703-497		I-70_GENESEE WILDLIFE XING	09/15/22	1.00	44700.00	76972.31	109198.99
	WEIGHTED AVERAGE FOR THE THIRD QUARTER			1.00	44700.00	76972.31	109198.99
	WEIGHTED AVERAGE FOR THE YEAR			1.00	44700.00	76972.31	109198.99

COLORADO DEPARTMENT OF TRANSPORTATION
ITEM UNIT COSTS BY PROJECTS -- 2022 COST DATA

11:31 Wednesday, March 8, 2023 391

PROJECT NUMBER	ITEM NUMBER/ PROJECT LOCATION	ITEM DESCRIPTION/ PROJECT LOCATION	DATE LET	UNIT/ QUANTITY	ENGR. EST.	AVERAGE BID	AWARDED BID
=====	611-00021	20 Ft Deer Guard		Each	=====	=====	=====
C5502-097		US550 MP 117.28-126.06	11/17/22	5.00	55000.00	101470.61	64830.00
		WEIGHTED AVERAGE FOR THE FOURTH QUARTER		5.00	55000.00	101470.61	64830.00
		WEIGHTED AVERAGE FOR THE YEAR		5.00	55000.00	101470.61	64830.00
=====	611-00029	28 Ft Deer Gd		Each	=====	=====	=====
STA0252-459			02/03/22	2.00	75000.00	128599.33	2500.00
		WEIGHTED AVERAGE FOR THE FIRST QUARTER		2.00	75000.00	128599.33	2500.00
		WEIGHTED AVERAGE FOR THE YEAR		2.00	75000.00	128599.33	2500.00
=====	611-00041	40 Ft Deer Gd		Each	=====	=====	=====
2670703-497		I-70_GENESEE WILDLIFE KING	09/15/22	3.00	125400.00	166436.12	237704.50
		WEIGHTED AVERAGE FOR THE THIRD QUARTER		3.00	125400.00	166436.12	237704.50
		WEIGHTED AVERAGE FOR THE YEAR		3.00	125400.00	166436.12	237704.50
=====	612-00001	Delin (Ty I)		Each	=====	=====	=====
NH0504-910		US50B L-24-B MIN REP AT MP 40	01/13/22	4.00	40.00	124.63	25.00
NHPP0702-383		I-70 EB AUX FRISCO TO SILVERT	01/13/22	143.00	26.00	22.05	17.00
NHPP1601-083			02/03/22	324.00	40.00	34.81	23.00
STR0141-031			02/17/22	235.00	40.00	28.67	26.00
STA 067A-048		Hwy 67A MP 0.00 TO MP 11.05 I	03/03/22	359.00	20.00	20.11	20.00
NHPP 0761-238		I-76 DAHLIA TO YORK	03/10/22	350.00	28.00	66.33	33.00
C0761-239							
NHPP0703-472			03/10/22	550.00	30.00	33.81	26.00
CR100-362			03/14/22	50.00	31.49	31.49	31.49
STR092A-031			03/17/22	845.00	35.00	29.00	29.00
		WEIGHTED AVERAGE FOR THE FIRST QUARTER		2,860.00	31.77	40.82	26.29
CC030-081		ADA RAMP AND CURBS - FT. LUPT	04/14/22	34.00	50.00	79.31	50.00

COLORADO DEPARTMENT OF TRANSPORTATION
ITEM UNIT COSTS BY PROJECTS -- 2022 COST DATA

11:31 Wednesday, March 8, 2023 392

PROJECT NUMBER	ITEM NUMBER/ PROJECT LOCATION	ITEM DESCRIPTION/ PROJECT LOCATION	DATE LET	UNIT/ QUANTITY	ENGR. EST.	AVERAGE BID	AWARDED BID
===== 612-00001 Delin (Ty I) Each =====							
STM1151-038		SH115 MP 27 TO MP 38	04/21/22	241.00	20.00	21.70	20.00
2670703-479		I-70 BRIDGE OVER HARLAN	05/05/22	8.00	25.00	44.60	51.68
STA0712-019		SH 71: Frieight Improvements	05/12/22	61.00	25.00	103.51	103.51
STA001A-005		SH1 WELLINGTON SOUTH RESURFAC	05/12/22	160.00	25.00	30.35	25.50
NHPP072A-047		SH-72 RESURFACING: I-70 TO IN	06/09/22	56.00	30.00	29.00	29.00
WEIGHTED AVERAGE FOR THE SECOND QUARTER				560.00	24.87	30.15	33.84
C1211-099		SH 121 NORTH SGA SIGNALS	08/25/22	19.00	25.00	172.50	245.00
PAN0761-245		ALONG I-76 & RAMPS MILEPOST 9	09/01/22	48.00	35.00	68.50	40.00
2670403-065		US40 FLOYD HILL ROUNDABOUTS	09/15/22	49.00	50.00	39.88	27.00
2670703-497		I-70 GENESEE WILDLIFE XING	09/15/22	98.00	23.00	89.07	24.99
SHE2873-193		US 287 & CO 52 INTERSECTION I	09/15/22	9.00	30.00	58.86	50.29
WEIGHTED AVERAGE FOR THE THIRD QUARTER				223.00	31.97	81.56	48.43
NHPP0821-114		SH 82 ASPEN/INDEPENDENCE PASS	10/13/22	10.00	50.00	31.47	32.40
C0831-126		SH83 EL PASO COUNTY TO BAYOU	10/13/22	130.00	25.00	23.50	24.00
NHPP0701-253		I-70 EAST OF DEBEQUE	10/27/22	200.00	40.00	25.30	26.00
TRG0253-264		I-25 AND SH 119 PARK-N-RIDE	10/27/22	8.00	30.00	26.93	28.00
SHE0242-087		US 24 SAFETY IMPRVMENTS, E OF	11/03/22	21.00	50.00	57.35	31.05
STR064A-010		SH 64 AND SH 13 AT MEEKER	11/10/22	100.00	25.00	45.15	65.00
C5502-097		US550 MP 117.28-126.06	11/17/22	289.00	20.00	33.76	25.90
STRC090-011		US 50B AND SH71/CR18 INTERSEC	11/17/22	27.00	24.00	27.10	29.20
STR114A-015		SH114 SILLSVILLE SOUTH TO MP3	12/01/22	4,630.00	50.00	27.38	26.00
2670703-487		I-70 BRIDGES OVER WARD ROAD-	12/01/22	27.00	50.00	37.21	43.00
NHPP0701-252		I-70 RIFLE TO SILT SLAB REPLA	12/01/22	37.00	40.00	41.50	45.00
IM025A-050		I25-MP103.9 - INTERSECTION DR	12/01/22	10.00	25.00	27.67	28.00
NHPP0063-048		US6 / 20 ROAD INTERSECTION IM	12/15/22	42.00	30.00	49.22	22.50
NHPP0931-033		SH93:US6 TO 58TH RESURFACING	12/15/22	72.00	30.00	38.44	27.70
NHPP0502-090		SH 50 MP 134.6-136 GUNNISON C	12/22/22	29.00	30.00	39.98	34.15
STA0361-129		US 36: HYGIENE RD AND NELSON	12/22/22	92.00	30.00	49.58	35.32
BR012A-048		CO 12 STRUCTURE P-17-F AT MP	12/22/22	16.00	30.00	42.74	50.00
WEIGHTED AVERAGE FOR THE FOURTH QUARTER				5,740.00	46.01	29.75	26.98
WEIGHTED AVERAGE FOR THE YEAR				9,383.00	40.07	35.82	27.67
===== 612-00002 Delin (Ty II) Each =====							
NHPP0702-383		I-70 EB AUX FRISCO TO SILVERT	01/13/22	89.00	28.00	24.45	21.00

COLORADO DEPARTMENT OF TRANSPORTATION
ITEM UNIT COSTS BY PROJECTS -- 2022 COST DATA

11:31 Wednesday, March 8, 2023 393

PROJECT NUMBER	ITEM NUMBER/ PROJECT LOCATION	ITEM DESCRIPTION/ PROJECT LOCATION	DATE LET	UNIT/ QUANTITY	ENGR. EST.	AVERAGE BID	AWARDED BID
===== 612-00002 Delin (Ty II) Each =====							
NHPP1601-083			02/03/22	53.00	30.00	80.87	26.00
STA 067A-048	Hwy 67A MP 0.00 TO MP 11.05 I		03/03/22	127.00	20.00	21.21	21.00
NHPP0703-472			03/10/22	150.00	32.00	36.26	28.00
STR092A-031			03/17/22	35.00	30.00	30.00	30.00
WEIGHTED AVERAGE FOR THE FIRST QUARTER				454.00	27.47	32.13	24.59
STM1151-038		SH115 MP 27 TO MP 38	04/21/22	171.00	25.00	22.55	21.00
STA0712-019		SH 71: Frieight Improvements	05/12/22	24.00	25.00	103.51	103.51
STA001A-005		SH1 WELLINGTON SOUTH RESURFAC	05/12/22	30.00	40.00	34.20	29.00
WEIGHTED AVERAGE FOR THE SECOND QUARTER				225.00	27.00	25.36	30.87
SHE2873-193		US 287 & CO 52 INTERSECTION I	09/15/22	33.00	35.00	62.98	55.64
WEIGHTED AVERAGE FOR THE THIRD QUARTER				33.00	35.00	62.98	55.64
NHPP0821-114		SH 82 ASPEN/INDEPENDENCE PASS	10/13/22	10.00	60.00	35.93	37.80
FSAM240-200		SH21B CO SPRINGS SIGNAL REPLA	10/27/22	3.00	200.00	286.31	25.25
STR064A-010		SH 64 AND SH 13 AT MEEKER	11/10/22	20.00	30.00	47.75	68.00
C5502-097		US550 MP 117.28-126.06	11/17/22	113.00	30.00	36.72	27.00
STRC090-011		US 50B AND SH71/CR18 INTERSEC	11/17/22	6.00	24.00	33.50	32.00
2670703-487		I-70 BRIDGES OVER WARD ROAD-	12/01/22	35.00	60.00	45.48	53.00
NHPP0701-252		I-70 RIFLE TO SILT SLAB REPLA	12/01/22	1.00	45.00	46.00	50.00
NHPP0021-041		SH2 RESURFACING MLK TO 52ND	12/01/22	20.00	36.00	88.93	111.91
NHPP0063-048		US6 / 20 ROAD INTERSECTION IM	12/15/22	42.00	40.00	49.91	23.50
NHPP0931-033		SH93:US6 TO 58TH RESURFACING	12/15/22	29.00	30.00	42.47	30.75
NHPP0502-090		SH 50 MP 134.6-136 GUNNISON C	12/22/22	37.00	35.00	45.76	35.57
STA0361-129		US 36: HYGIENE RD AND NELSON	12/22/22	92.00	35.00	54.75	39.04
WEIGHTED AVERAGE FOR THE FOURTH QUARTER				408.00	37.41	48.92	38.10
WEIGHTED AVERAGE FOR THE YEAR				1,120.00	31.22	38.67	31.90
===== 612-00003 Delin (Ty III) Each =====							
NH0504-910		US50B L-24-B MIN REP AT MP 40	01/13/22	2.00	40.00	140.35	25.00

COLORADO DEPARTMENT OF TRANSPORTATION
ITEM UNIT COSTS BY PROJECTS -- 2022 COST DATA

11:31 Wednesday, March 8, 2023 394

PROJECT NUMBER	ITEM NUMBER/ PROJECT LOCATION	ITEM DESCRIPTION/ PROJECT LOCATION	DATE LET	UNIT/ QUANTITY	ENGR. EST.	AVERAGE BID	AWARDED BID
===== 612-00003 Delin (Ty III) Each =====							
NHPP0702-383		I-70 EB AUX FRISCO TO SILVERT	01/13/22	25.00	31.00	25.71	22.00
NHPP1601-083			02/03/22	129.00	35.00	55.66	28.00
STR0141-031			02/17/22	18.00	50.00	31.67	30.00
STA 067A-048		Hwy 67A MP 0.00 TO MP 11.05 I	03/03/22	50.00	20.00	23.38	23.00
NHPP 0761-238		I-76 DAHLIA TO YORK	03/10/22	5.00	50.00	72.00	38.00
C0761-239							
NHPP0703-472			03/10/22	50.00	34.00	39.80	32.00
CR100-362			03/14/22	10.00	33.79	33.79	33.79
STR092A-031			03/17/22	58.00	40.00	31.00	31.00
WEIGHTED AVERAGE FOR THE FIRST QUARTER				347.00	34.23	41.73	28.32
STM1151-038		SH115 MP 27 TO MP 38	04/21/22	33.00	30.00	27.87	39.03
2670703-479		I-70 BRIDGE OVER HARLAN	05/05/22	6.00	32.00	57.74	66.95
STA0712-019		SH 71: Frieght Improvements	05/12/22	18.00	25.00	103.51	103.51
STA001A-005		SH1 WELLINGTON SOUTH RESURFAC	05/12/22	18.00	45.00	39.00	33.00
NHPP072A-047		SH-72 RESURFACING: I-70 TO IN	06/09/22	7.00	40.00	32.63	32.63
WEIGHTED AVERAGE FOR THE SECOND QUARTER				82.00	33.20	38.82	53.36
FSA052A-057		SH52 BOX CULVERT EXTENSION (M	08/04/22	2.00	50.00	110.21	126.49
C1211-099		SH 121 NORTH SGA SIGNALS	08/25/22	39.00	25.00	172.50	245.00
ER0502-092		US 50 MP 204 EB MONARCH TRUCK	08/29/22	2.00	35.00	78.99	46.96
2670703-497		I-70 GENESEE WILDLIFE XING	09/15/22	4.00	46.00	97.13	34.08
SHE2873-193		US 287 & CO 52 INTERSECTION I	09/15/22	12.00	35.00	68.11	60.99
WEIGHTED AVERAGE FOR THE THIRD QUARTER				59.00	29.64	116.91	182.54
NHPP0821-114		SH 82 ASPEN/INDEPENDENCE PASS	10/13/22	10.00	70.00	41.07	43.20
NHPP0701-253		I-70 EAST OF DEBEQUE	10/27/22	40.00	50.00	27.35	28.00
STU0252-457		I-25:ALAMEDA RIVER PH 2.0	11/03/22	4.00	30.00	132.63	115.00
SHE0242-087		US 24 SAFETY IMPRVMENTS, E OF	11/03/22	6.00	50.00	61.60	41.80
STR064A-010		SH 64 AND SH 13 AT MEEKER	11/10/22	20.00	35.00	49.75	71.00
C5502-097		US550 MP 117.28-126.06	11/17/22	48.00	35.00	39.68	28.10
STR114A-015		SH114 SILLSVILLE SOUTH TO MP3	12/01/22	284.00	60.00	32.00	34.00
2670703-487		I-70 BRIDGES OVER WARD ROAD-	12/01/22	4.00	35.00	52.78	62.00
NHPP0701-252		I-70 RIFLE TO SILT SLAB REPLA	12/01/22	37.00	50.00	50.00	55.00
NHPP0063-048		US6 / 20 ROAD INTERSECTION IM	12/15/22	6.00	45.00	51.86	24.50
NHPP0931-033		SH93:US6 TO 58TH RESURFACING	12/15/22	9.00	30.00	49.96	33.80

COLORADO DEPARTMENT OF TRANSPORTATION
ITEM UNIT COSTS BY PROJECTS -- 2022 COST DATA

11:31 Wednesday, March 8, 2023 395

PROJECT NUMBER	ITEM NUMBER/ PROJECT LOCATION	ITEM DESCRIPTION/ PROJECT LOCATION	DATE LET	UNIT/ QUANTITY	ENGR. EST.	AVERAGE BID	AWARDED BID
=====	612-00003	Delin (Ty III)		Each =====			
NHPP0502-090	SH 50 MP 134.6-136	GUNNISON C	12/22/22	7.00	40.00	49.72	36.99
STA0361-129	US 36: HYGIENE RD AND NELSON		12/22/22	37.00	40.00	57.91	42.76
BR012A-048	CO 12 STRUCTURE P-17-F AT MP		12/22/22	8.00	35.00	55.27	70.00
	WEIGHTED AVERAGE FOR THE FOURTH QUARTER			520.00	52.13	40.86	37.49
	WEIGHTED AVERAGE FOR THE YEAR			1,008.00	43.11	46.17	43.86
=====	612-00021	Delin (Ty I) (Barrier)		Each =====			
NHPP0702-383	I-70 EB AUX FRISCO TO SILVERT		01/13/22	6.00	75.00	104.92	130.00
	WEIGHTED AVERAGE FOR THE FIRST QUARTER			6.00	75.00	104.92	130.00
NHPP0702-414	VAIL PASS AUX PHASE 1 CAP 3		07/08/22	31.00	81.86	81.86	81.86
FBR0702-423	VAIL PASS AUX BE F-12-AT PHAS						
	WEIGHTED AVERAGE FOR THE THIRD QUARTER			31.00	81.86	81.86	81.86
	WEIGHTED AVERAGE FOR THE YEAR			37.00	80.75	93.20	89.67
=====	612-00031	Delin (Ty I) (Extra Ht)		Each =====			
NHPP0702-414	VAIL PASS AUX PHASE 1 CAP 3		07/08/22	43.00	54.57	54.57	54.57
FBR0702-423	VAIL PASS AUX BE F-12-AT PHAS						
	WEIGHTED AVERAGE FOR THE THIRD QUARTER			43.00	54.57	54.57	54.57
	WEIGHTED AVERAGE FOR THE YEAR			43.00	54.57	54.57	54.57
=====	612-00032	Delin (Ty II) (Extra Ht)		Each =====			
C5502-111	US 550 MP 81 AND 89 RED MOUNT		10/27/22	2.00	50.00	1000.00	1500.00
	WEIGHTED AVERAGE FOR THE FOURTH QUARTER			2.00	50.00	1000.00	1500.00
	WEIGHTED AVERAGE FOR THE YEAR			2.00	50.00	1000.00	1500.00
=====	612-00033	Delin (Ty III) (Extra Ht)		Each =====			
NHPP0702-414	VAIL PASS AUX PHASE 1 CAP 3		07/08/22	41.00	60.03	60.03	60.03

COLORADO DEPARTMENT OF TRANSPORTATION
ITEM UNIT COSTS BY PROJECTS -- 2022 COST DATA

11:31 Wednesday, March 8, 2023 396

PROJECT NUMBER	ITEM NUMBER/ PROJECT LOCATION	ITEM DESCRIPTION/ PROJECT LOCATION	DATE LET	UNIT/ QUANTITY	ENGR. EST.	AVERAGE BID	AWARDED BID
=====	612-00033	Delin (Ty III) (Extra Ht)		Each			
FBR0702-423		VAIL PASS AUX BE F-12-AT PHAS					
	WEIGHTED AVERAGE FOR THE THIRD QUARTER			41.00	60.03	60.03	60.03
	WEIGHTED AVERAGE FOR THE YEAR			41.00	60.03	60.03	60.03
=====	612-00036	Delin (Flex) (Sq Base)		Each			
STA207A-004		Resurfacing SH207A MANZANOLA	10/27/22	410.00	66.00	88.95	85.85
	WEIGHTED AVERAGE FOR THE FOURTH QUARTER			410.00	66.00	88.95	85.85
	WEIGHTED AVERAGE FOR THE YEAR			410.00	66.00	88.95	85.85
=====	612-00037	Delin (Flex) (Flat Mount)		Each			
STA207A-004		Resurfacing SH207A MANZANOLA	10/27/22	67.00	78.50	78.00	53.00
STA385A-016		SH 385 MP 97.76	12/22/22	15.00	60.00	87.14	75.56
	WEIGHTED AVERAGE FOR THE FOURTH QUARTER			82.00	75.12	80.10	57.13
	WEIGHTED AVERAGE FOR THE YEAR			82.00	75.12	80.10	57.13
=====	612-00039	Delin (Flex) (Surf Mount)		Each			
CR100-362			03/14/22	5.00	60.43	60.43	60.43
	WEIGHTED AVERAGE FOR THE FIRST QUARTER			5.00	60.43	60.43	60.43
NHPP0702-414		VAIL PASS AUX PHASE 1 CAP 3	07/08/22	90.00	87.31	87.31	87.31
FBR0702-423		VAIL PASS AUX BE F-12-AT PHAS					
	WEIGHTED AVERAGE FOR THE THIRD QUARTER			90.00	87.31	87.31	87.31
MPR200-280		PUEBLO AREA	11/17/22	16.00	80.00	70.00	65.00
	WEIGHTED AVERAGE FOR THE FOURTH QUARTER			16.00	80.00	70.00	65.00
	WEIGHTED AVERAGE FOR THE YEAR			111.00	85.05	81.89	82.88

COLORADO DEPARTMENT OF TRANSPORTATION
ITEM UNIT COSTS BY PROJECTS -- 2022 COST DATA

11:31 Wednesday, March 8, 2023 397

PROJECT NUMBER	ITEM NUMBER/ PROJECT LOCATION	ITEM DESCRIPTION/ PROJECT LOCATION	DATE LET	UNIT/ QUANTITY	ENGR. EST.	AVERAGE BID	AWARDED BID
===== 612-00041 Delin (Flex) (Ty I) Each =====							
ER007A-035			03/15/22	1,372.00	133.62	143.00	143.00
	WEIGHTED AVERAGE FOR THE FIRST QUARTER			1,372.00	133.62	143.00	143.00
NH0504-911			04/07/22	378.00	73.40	69.50	72.00
STA0712-019		SH 71: Frieight Improvements	05/12/22	16.00	100.00	207.01	207.01
NHC540-017		R2 CHAINUP STA @ KENOSHA/HOOS	05/12/22	200.00	20.00	101.67	80.00
	WEIGHTED AVERAGE FOR THE SECOND QUARTER			594.00	56.14	85.17	78.33
NHPP0063-054		US 6 FROM I70-B TO 33 RD. (MP	08/18/22	15.00	70.00	91.68	61.00
	WEIGHTED AVERAGE FOR THE THIRD QUARTER			15.00	70.00	91.68	61.00
NHPP083A-046		SH83 RESURFACING STROH RD TO	12/08/22	43.00	70.00	164.48	69.95
STR096A-050		SH 96 MP 168.99 TO 193.77	12/22/22	516.00	63.00	101.00	80.00
	WEIGHTED AVERAGE FOR THE FOURTH QUARTER			559.00	63.54	104.34	79.23
	WEIGHTED AVERAGE FOR THE YEAR			2,540.00	99.70	110.32	113.36
===== 612-00042 Delin (Flex) (Ty II) Each =====							
ER007A-035			03/15/22	6.00	137.70	147.50	147.50
	WEIGHTED AVERAGE FOR THE FIRST QUARTER			6.00	137.70	147.50	147.50
NH0504-911			04/07/22	186.00	86.45	81.80	83.60
STA0712-019		SH 71: Frieight Improvements	05/12/22	7.00	100.00	207.01	207.01
NHC540-017		R2 CHAINUP STA @ KENOSHA/HOOS	05/12/22	60.00	20.00	104.00	81.00
	WEIGHTED AVERAGE FOR THE SECOND QUARTER			253.00	71.07	90.52	86.40

COLORADO DEPARTMENT OF TRANSPORTATION
 ITEM UNIT COSTS BY PROJECTS -- 2022 COST DATA

11:31 Wednesday, March 8, 2023 398

PROJECT NUMBER	ITEM NUMBER/ PROJECT LOCATION	ITEM DESCRIPTION/ PROJECT LOCATION	DATE LET	UNIT/ QUANTITY	ENGR. EST.	AVERAGE BID	AWARDED BID
=====	612-00042	Delin (Flex) (Ty II)		Each	=====	=====	=====
NHPP083A-046		SH83 RESURFACING STROH RD TO	12/08/22	87.00	75.00	134.10	71.20
		WEIGHTED AVERAGE FOR THE FOURTH QUARTER		87.00	75.00	134.10	71.20
		WEIGHTED AVERAGE FOR THE YEAR		346.00	73.21	101.24	83.64
=====	612-00043	Delin (Flex) (Ty III)		Each	=====	=====	=====
ER007A-035			03/15/22	272.00	137.70	147.50	147.50
		WEIGHTED AVERAGE FOR THE FIRST QUARTER		272.00	137.70	147.50	147.50
NH0504-911			04/07/22	136.00	81.06	87.30	89.60
STA0712-019		SH 71: Frieight Improvements	05/12/22	4.00	100.00	207.01	207.01
NHC540-017		R2 CHAINUP STA @ KENOSHA/HOOS	05/12/22	20.00	20.00	105.67	82.00
		WEIGHTED AVERAGE FOR THE SECOND QUARTER		160.00	73.90	92.00	91.59
NHPP083A-046		SH83 RESURFACING STROH RD TO	12/08/22	47.00	80.00	159.73	72.45
STR096A-050		SH 96 MP 168.99 TO 193.77	12/22/22	50.00	84.00	109.33	84.00
		WEIGHTED AVERAGE FOR THE FOURTH QUARTER		97.00	82.06	128.75	78.40
		WEIGHTED AVERAGE FOR THE YEAR		529.00	108.20	120.24	117.92
=====	612-00052	Reflector		Each	=====	=====	=====
STA0252-459			02/03/22	600.00	47.00	76.58	65.00
C0762-055			02/17/22	240.00	12.00	29.73	47.00
NHPP0703-472			03/10/22	648.00	18.00	53.86	18.00
		WEIGHTED AVERAGE FOR THE FIRST QUARTER		1,488.00	28.73	57.17	41.63
STR064A-010		SH 64 AND SH 13 AT MEEKER	11/10/22	50.00	20.00	6.45	5.50

COLORADO DEPARTMENT OF TRANSPORTATION
 ITEM UNIT COSTS BY PROJECTS -- 2022 COST DATA

11:31 Wednesday, March 8, 2023 399

PROJECT NUMBER	ITEM NUMBER/ PROJECT LOCATION	ITEM DESCRIPTION/ PROJECT LOCATION	DATE LET	UNIT/ QUANTITY	ENGR. EST.	AVERAGE BID	AWARDED BID
=====	612-00052	Reflector		Each =====			
NHPP0701-252		I-70 RIFLE TO SILT SLAB REPLA	12/01/22	800.00	29.00	15.00	5.00
		WEIGHTED AVERAGE FOR THE FOURTH QUARTER		850.00	28.47	14.50	5.03
		WEIGHTED AVERAGE FOR THE YEAR		2,338.00	28.63	46.89	28.32
=====	612-00060	Reflector (Median Barrier)		Each =====			
STA0252-459			02/03/22	300.00	41.91	119.23	100.00
		WEIGHTED AVERAGE FOR THE FIRST QUARTER		300.00	41.91	119.23	100.00
		WEIGHTED AVERAGE FOR THE YEAR		300.00	41.91	119.23	100.00
=====	612-00070	Reflector Strip (4 In)		Each =====			
NHPP0702-414 FBR0702-423		VAIL PASS AUX PHASE 1 CAP 3	07/08/22	231.00	65.48	65.48	65.48
		VAIL PASS AUX BE F-12-AT PHAS					
		WEIGHTED AVERAGE FOR THE THIRD QUARTER		231.00	65.48	65.48	65.48
		WEIGHTED AVERAGE FOR THE YEAR		231.00	65.48	65.48	65.48
=====	612-00075	Reflector Strip (6 In)		Each =====			
NHPP0703-472			03/10/22	264.00	40.00	85.48	90.00
		WEIGHTED AVERAGE FOR THE FIRST QUARTER		264.00	40.00	85.48	90.00
		WEIGHTED AVERAGE FOR THE YEAR		264.00	40.00	85.48	90.00
=====	612-00081	Delin (PM) (Ty I)		Each =====			
C0762-055			02/17/22	12.00	75.00	83.24	65.00
		WEIGHTED AVERAGE FOR THE FIRST QUARTER		12.00	75.00	83.24	65.00
BR0343-046		US 34 TIMBER BRIDGE REPL. PKG	08/31/22	8.00	89.24	89.35	89.35

COLORADO DEPARTMENT OF TRANSPORTATION
 ITEM UNIT COSTS BY PROJECTS -- 2022 COST DATA

11:31 Wednesday, March 8, 2023 400

PROJECT NUMBER	ITEM NUMBER/ PROJECT LOCATION	ITEM DESCRIPTION/ PROJECT LOCATION	DATE LET	UNIT/ QUANTITY	ENGR. EST.	AVERAGE BID	AWARDED BID
=====	612-00081	Delin (PM) (Ty I)		Each	=====		
FBR0343-047		US 6/US 34 TIMBER BRIDGE REPL					
		WEIGHTED AVERAGE FOR THE THIRD QUARTER		8.00	89.24	89.35	89.35
		WEIGHTED AVERAGE FOR THE YEAR		20.00	80.70	84.12	74.74
=====	612-00083	Delin (PM) (Ty III)		Each	=====		
C0762-055			02/17/22	4.00	80.00	90.27	70.00
		WEIGHTED AVERAGE FOR THE FIRST QUARTER		4.00	80.00	90.27	70.00
BR0343-046		US 34 TIMBER BRIDGE REPL. PKG	08/31/22	2.00	88.91	94.16	94.16
FBR0343-047		US 6/US 34 TIMBER BRIDGE REPL					
		WEIGHTED AVERAGE FOR THE THIRD QUARTER		2.00	88.91	94.16	94.16
STAM420-001		US 285 AT HWY 9C IMPROVEMENTS	12/01/22	6.00	80.00	108.13	127.53
BR2854-148		INTERSECTION OF US 285 & SH 9					
STM0091-046		ADA RAMP IMPROVEMENTS - FAIRP					
		WEIGHTED AVERAGE FOR THE FOURTH QUARTER		6.00	80.00	108.13	127.53
		WEIGHTED AVERAGE FOR THE YEAR		12.00	81.48	100.66	102.79
=====	612-00101	Delin (Drv Conc Inst) (Ty I)		Each	=====		
C0762-055			02/17/22	470.00	130.00	136.51	205.00
ER007A-035			03/15/22	458.00	163.20	174.60	174.60
		WEIGHTED AVERAGE FOR THE FIRST QUARTER		928.00	146.39	143.97	190.00
FSA3921-019		SH 392 AND WCR 55 ISLANDS	06/02/22	7.00	140.00	79.00	86.00
		WEIGHTED AVERAGE FOR THE SECOND QUARTER		7.00	140.00	79.00	86.00

COLORADO DEPARTMENT OF TRANSPORTATION
ITEM UNIT COSTS BY PROJECTS -- 2022 COST DATA

11:31 Wednesday, March 8, 2023 401

PROJECT NUMBER	ITEM NUMBER/ PROJECT LOCATION	ITEM DESCRIPTION/ PROJECT LOCATION	DATE LET	UNIT/ QUANTITY	ENGR. EST.	AVERAGE BID	AWARDED BID
=====	612-00101	Delin (Drv Conc Inst) (Ty I)		Each	=====	=====	=====
STA3852-015		US 385 HOLYOKE NORTH	10/27/22	320.00	100.00	125.00	125.00
NHPP0853-126		US85C: PLATTEVILLE NORTH MP (11/10/22	138.00	135.00	97.40	95.00
		WEIGHTED AVERAGE FOR THE FOURTH QUARTER		458.00	110.55	106.14	115.96
		WEIGHTED AVERAGE FOR THE YEAR		1,393.00	134.57	132.22	165.13
=====	612-00102	Delin (Drv Conc Inst) (Ty II)		Each	=====	=====	=====
ER007A-035			03/15/22	25.00	168.30	180.00	180.00
		WEIGHTED AVERAGE FOR THE FIRST QUARTER		25.00	168.30	180.00	180.00
STA3852-015		US 385 HOLYOKE NORTH	10/27/22	13.00	160.00	135.00	135.00
NHPP0853-126		US85C: PLATTEVILLE NORTH MP (11/10/22	140.00	150.00	107.00	105.00
		WEIGHTED AVERAGE FOR THE FOURTH QUARTER		153.00	150.85	107.51	107.55
		WEIGHTED AVERAGE FOR THE YEAR		178.00	153.30	109.97	117.72
=====	612-00103	Delin (Drv Conc Inst) (Ty III)		Each	=====	=====	=====
C0762-055			02/17/22	4.00	135.00	143.73	225.00
ER007A-035			03/15/22	91.00	173.40	185.50	185.50
		WEIGHTED AVERAGE FOR THE FIRST QUARTER		95.00	171.78	179.25	187.16
STA3852-015		US 385 HOLYOKE NORTH	10/27/22	44.00	175.00	140.00	140.00
NHPP0853-126		US85C: PLATTEVILLE NORTH MP (11/10/22	20.00	150.00	116.00	115.00
		WEIGHTED AVERAGE FOR THE FOURTH QUARTER		64.00	167.19	123.33	132.19
		WEIGHTED AVERAGE FOR THE YEAR		159.00	169.93	147.17	165.03
=====	612-00111	Delin (Drv) (Ty I)		Each	=====	=====	=====
NHPP 3851-018		US 385 NORTH OF CHEYENNE WELL	05/26/22	356.00	105.00	102.50	120.00
		WEIGHTED AVERAGE FOR THE SECOND QUARTER		356.00	105.00	102.50	120.00

COLORADO DEPARTMENT OF TRANSPORTATION
 ITEM UNIT COSTS BY PROJECTS -- 2022 COST DATA

11:31 Wednesday, March 8, 2023 402

PROJECT NUMBER	ITEM NUMBER/ PROJECT LOCATION	ITEM DESCRIPTION/ PROJECT LOCATION	DATE LET	UNIT/ QUANTITY	ENGR. EST.	AVERAGE BID	AWARDED BID
=====	612-00111	Delin (Drv) (Ty I)		Each	=====		
BR0343-046		US 34 TIMBER BRIDGE REPL. PKG	08/31/22	15.00	153.01	153.01	153.01
FBR0343-047		US 6/US 34 TIMBER BRIDGE REPL					
		WEIGHTED AVERAGE FOR THE THIRD QUARTER		15.00	153.01	153.01	153.01
STAM420-001		US 285 AT HWY 9C IMPROVEMENTS	12/01/22	87.00	112.00	124.35	105.91
BR2854-148		INTERSECTION OF US 285 & SH 9					
STM0091-046		ADA RAMP IMPROVEMENTS - FAIRP					
STA0711-021		SH71: REGION LINE NORTH	12/01/22	354.00	86.00	79.83	98.00
STA385A-016		SH 385 MP 97.76	12/22/22	12.00	90.00	118.33	133.33
		WEIGHTED AVERAGE FOR THE FOURTH QUARTER		453.00	91.10	91.73	100.46
		WEIGHTED AVERAGE FOR THE YEAR		824.00	98.23	95.66	109.86
=====	612-00112	Delin (Drv) (Ty II)		Each	=====		
STAM420-001		US 285 AT HWY 9C IMPROVEMENTS	12/01/22	24.00	105.00	129.43	111.21
BR2854-148		INTERSECTION OF US 285 & SH 9					
STM0091-046		ADA RAMP IMPROVEMENTS - FAIRP					
		WEIGHTED AVERAGE FOR THE FOURTH QUARTER		24.00	105.00	129.43	111.21
		WEIGHTED AVERAGE FOR THE YEAR		24.00	105.00	129.43	111.21
=====	612-00113	Delin (Drv) (Ty III)		Each	=====		
NHPP 3851-018		US 385 NORTH OF CHEYENNE WELL	05/26/22	2.00	110.00	110.00	130.00
		WEIGHTED AVERAGE FOR THE SECOND QUARTER		2.00	110.00	110.00	130.00
BR0343-046		US 34 TIMBER BRIDGE REPL. PKG	08/31/22	2.00	152.26	160.50	160.50
FBR0343-047		US 6/US 34 TIMBER BRIDGE REPL					
		WEIGHTED AVERAGE FOR THE THIRD QUARTER		2.00	152.26	160.50	160.50

COLORADO DEPARTMENT OF TRANSPORTATION
 ITEM UNIT COSTS BY PROJECTS -- 2022 COST DATA

11:31 Wednesday, March 8, 2023 403

PROJECT NUMBER	ITEM NUMBER/ PROJECT LOCATION	ITEM DESCRIPTION/ PROJECT LOCATION	DATE LET	UNIT/ QUANTITY	ENGR. EST.	AVERAGE BID	AWARDED BID
=====	612-00113	Delin (Drv) (Ty III)		Each	=====		
STAM420-001		US 285 AT HWY 9C IMPROVEMENTS	12/01/22	8.00	113.00	137.32	116.77
BR2854-148		INTERSECTION OF US 285 & SH 9					
STM0091-046		ADA RAMP IMPROVEMENTS - FAIRP					
STA0711-021		SH71: REGION LINE NORTH	12/01/22	10.00	89.00	86.33	110.00
STA385A-016		SH 385 MP 97.76	12/22/22	10.00	90.00	119.58	133.33
		WEIGHTED AVERAGE FOR THE FOURTH QUARTER		28.00	96.21	115.37	120.27
		WEIGHTED AVERAGE FOR THE YEAR		32.00	100.58	116.00	123.39
=====	612-00260	Loc Mark (Fib Opt) (Dome)		Each	=====		
NHPP0702-383		I-70 EB AUX FRISCO TO SILVERT	01/13/22	8.00	120.00	276.27	230.00
NHM765-007			03/31/22	10.00	150.00	462.81	416.10
		WEIGHTED AVERAGE FOR THE FIRST QUARTER		18.00	136.67	356.22	333.39
STM1151-038		SH115 MP 27 TO MP 38	04/21/22	44.00	120.00	336.17	370.00
NHC540-017		R2 CHAINUP STA @ KENOSHA/HOOS	05/12/22	260.00	84.00	106.67	115.00
ITS 0741-024		VMS SIGN INSTALLATIONS AND VS	06/02/22	21.00	100.00	265.00	213.00
		WEIGHTED AVERAGE FOR THE SECOND QUARTER		325.00	89.91	161.51	155.86
NHPP0702-414		VAIL PASS AUX PHASE 1 CAP 3	07/08/22	3.00	87.31	87.31	87.31
FBR0702-423		VAIL PASS AUX BE F-12-AT PHAS					
2670703-497		I-70_GENESEE WILDLIFE XING	09/15/22	1.00	130.00	275.62	283.98
		WEIGHTED AVERAGE FOR THE THIRD QUARTER		4.00	97.98	219.13	136.48
TRG0253-264		I-25 AND SH 119 PARK-N-RIDE	10/27/22	9.00	130.00	124.73	130.00
STAM420-001		US 285 AT HWY 9C IMPROVEMENTS	12/01/22	2.00	125.00	289.52	439.83
BR2854-148		INTERSECTION OF US 285 & SH 9					
STM0091-046		ADA RAMP IMPROVEMENTS - FAIRP					

COLORADO DEPARTMENT OF TRANSPORTATION
ITEM UNIT COSTS BY PROJECTS -- 2022 COST DATA

11:31 Wednesday, March 8, 2023 404

PROJECT NUMBER	ITEM NUMBER/ PROJECT LOCATION	ITEM DESCRIPTION/ PROJECT LOCATION	DATE LET	UNIT/ QUANTITY	ENGR. EST.	AVERAGE BID	AWARDED BID
===== 2670703-487	612-00260	Loc Mark (Fib Opt) (Dome) I-70 BRIDGES OVER WARD ROAD-	12/01/22	Each 1.00	100.00	257.61	260.00
		WEIGHTED AVERAGE FOR THE FOURTH QUARTER		12.00	126.67	148.06	192.47
		WEIGHTED AVERAGE FOR THE YEAR		359.00	93.57	172.33	165.76
===== 1321151-038	612-00270	Loc Mark (Util) (Flat Slat)		Each			
ITS 0741-024		SH115 MP 27 TO MP 38 VMS SIGN INSTALLATIONS AND VS	04/21/22 06/02/22	3.00 4.00	100.00 100.00	244.67 130.50	260.00 205.00
		WEIGHTED AVERAGE FOR THE SECOND QUARTER		7.00	100.00	204.96	228.57
TRG0253-264 STAM420-001 BR2854-148 STM0091-046		I-25 AND SH 119 PARK-N-RIDE US 285 AT HWY 9C IMPROVEMENTS INTERSECTION OF US 285 & SH 9 ADA RAMP IMPROVEMENTS - FAIRP	10/27/22 12/01/22	5.00 71.00	100.00 36.10	124.98 353.58	132.00 537.57
		WEIGHTED AVERAGE FOR THE FOURTH QUARTER		76.00	40.30	325.36	510.89
		WEIGHTED AVERAGE FOR THE YEAR		83.00	45.34	317.38	487.08
===== 1320252-459	612-01080	Barrier Striping (6 In)		Lin Foot			
			02/03/22	8,600.00	2.50	5.84	4.00
		WEIGHTED AVERAGE FOR THE FIRST QUARTER		8,600.00	2.50	5.84	4.00
		WEIGHTED AVERAGE FOR THE YEAR		8,600.00	2.50	5.84	4.00
===== 2670703-487	613-00075	3/4 In Elec Cond		Lin Foot			
		I-70 BRIDGES OVER WARD ROAD-	12/01/22	725.00	10.00	29.81	29.00
		WEIGHTED AVERAGE FOR THE FOURTH QUARTER		725.00	10.00	29.81	29.00
		WEIGHTED AVERAGE FOR THE YEAR		725.00	10.00	29.81	29.00
===== 1320703-477	613-00100	1 In Elec Cond		Lin Foot			
		ITS EQUIPMENT UPGRADE AT EJMT	01/06/22	2,050.00	40.00	155.00	155.00

COLORADO DEPARTMENT OF TRANSPORTATION
 ITEM UNIT COSTS BY PROJECTS -- 2022 COST DATA

11:31 Wednesday, March 8, 2023 405

PROJECT NUMBER	ITEM NUMBER/ PROJECT LOCATION	ITEM DESCRIPTION/ PROJECT LOCATION	DATE LET	UNIT/ QUANTITY	ENGR. EST.	AVERAGE BID	AWARDED BID
=====	613-00100	1 In Elec Cond		Lin Foot	=====	=====	=====
NHPP 0761-238		I-76 DAHLIA TO YORK	03/10/22	397.00	22.00	36.88	30.00
C0761-239							
		WEIGHTED AVERAGE FOR THE FIRST QUARTER		2,447.00	37.08	83.21	134.72
2670703-479		I-70 BRIDGE OVER HARLAN	05/05/22	330.00	24.00	28.92	34.04
		WEIGHTED AVERAGE FOR THE SECOND QUARTER		330.00	24.00	28.92	34.04
TRG0253-264		I-25 AND SH 119 PARK-N-RIDE	10/27/22	646.00	10.00	11.64	12.00
IM025A-050		I25-MP103.9 - INTERSECTION DR	12/01/22	340.00	20.00	35.00	25.00
		WEIGHTED AVERAGE FOR THE FOURTH QUARTER		986.00	13.45	15.49	16.48
		WEIGHTED AVERAGE FOR THE YEAR		3,763.00	29.74	43.90	94.91
=====	613-00102	1 In Elec Cond (GRC) (Special)		Lin Foot	=====	=====	=====
NHC540-017		R2 CHAINUP STA @ KENOSHA/HOOS	05/12/22	50.00	50.00	58.33	35.00
		WEIGHTED AVERAGE FOR THE SECOND QUARTER		50.00	50.00	58.33	35.00
		WEIGHTED AVERAGE FOR THE YEAR		50.00	50.00	58.33	35.00
=====	613-00200	2 In Elec Cond		Lin Foot	=====	=====	=====
NHPP0702-383		I-70 EB AUX FRISCO TO SILVERT	01/13/22	1,600.00	25.00	79.13	80.00
NHPP 0761-238		I-76 DAHLIA TO YORK	03/10/22	175.00	24.00	45.18	46.00
C0761-239							
		WEIGHTED AVERAGE FOR THE FIRST QUARTER		1,775.00	24.90	74.08	76.65
CC030-081		ADA RAMP AND CURBS - FT. LUPT	04/14/22	266.00	20.00	56.46	38.00
NHPP0702-413		VAIL PASS AUX PHASE 1 CAP 2	04/18/22	20,832.00	32.10	32.10	32.10
STM1151-038		SH115 MP 27 TO MP 38	04/21/22	5,550.00	17.00	28.21	30.00

COLORADO DEPARTMENT OF TRANSPORTATION
ITEM UNIT COSTS BY PROJECTS -- 2022 COST DATA

11:31 Wednesday, March 8, 2023 406

PROJECT NUMBER	ITEM NUMBER/ PROJECT LOCATION	ITEM DESCRIPTION/ PROJECT LOCATION	DATE LET	UNIT/ QUANTITY	ENGR. EST.	AVERAGE BID	AWARDED BID
===== 613-00200							
2670703-479		2 In Elec Cond		Lin Foot			
CM760-047		I-70 BRIDGE OVER HARLAN	05/05/22	1,915.00	25.00	21.24	24.75
		COLFAX AND QUAIL	05/12/22	174.00	20.00	28.60	41.00
		WEIGHTED AVERAGE FOR THE SECOND QUARTER		28,737.00	28.53	28.59	31.31
NHPP0702-414		VAIL PASS AUX PHASE 1 CAP 3	07/08/22	700.00	39.59	39.59	39.59
FBR0702-423		VAIL PASS AUX BE F-12-AT PHAS					
NHPP0063-054		US 6 FROM I70-B TO 33 RD. (MP	08/18/22	3,100.00	25.00	28.43	25.00
2670403-065		US40 FLOYD HILL ROUNDABOUTS	09/15/22	4,550.00	30.00	58.76	53.00
2670703-497		I-70 GENESEE WILDLIFE XING	09/15/22	630.00	24.00	28.42	28.40
		WEIGHTED AVERAGE FOR THE THIRD QUARTER		8,980.00	28.60	45.33	40.56
TRG0253-264		I-25 AND SH 119 PARK-N-RIDE	10/27/22	6,905.00	20.00	21.03	22.00
STU0252-457		I-25:ALAMEDA RIVER PH 2.0	11/03/22	1,338.00	35.00	40.93	41.00
C5502-097		US550 MP 117.28-126.06	11/17/22	58.00	30.00	95.90	216.00
STAM420-001		US 285 AT HWY 9C IMPROVEMENTS	12/01/22	434.00	25.60	37.32	40.51
BR2854-148		INTERSECTION OF US 285 & SH 9					
STM0091-046		ADA RAMP IMPROVEMENTS - FAIRP					
2670703-487		I-70 BRIDGES OVER WARD ROAD-	12/01/22	755.00	35.00	29.81	29.00
		WEIGHTED AVERAGE FOR THE FOURTH QUARTER		9,490.00	23.63	23.41	27.27
		WEIGHTED AVERAGE FOR THE YEAR		48,982.00	27.46	31.75	33.87
===== 613-00206							
2 In Elec Cond (Bored)							
Lin Foot							
NHPP0702-383		I-70 EB AUX FRISCO TO SILVERT	01/13/22	265.00	30.00	110.21	106.00
NHPP 0761-238		I-76 DAHLIA TO YORK	03/10/22	725.00	24.00	44.91	31.00
C0761-239							
NHM765-007			03/31/22	1,500.00	40.00	44.38	39.90
		WEIGHTED AVERAGE FOR THE FIRST QUARTER		2,490.00	34.28	52.15	44.34
STM1151-038		SH115 MP 27 TO MP 38	04/21/22	55,890.00	11.00	29.21	30.00
2670703-479		I-70 BRIDGE OVER HARLAN	05/05/22	1,840.00	25.00	21.20	24.75
NHC540-017		R2 CHAINUP STA @ KENOSHA/HOOS	05/12/22	325.00	33.00	55.33	56.00

COLORADO DEPARTMENT OF TRANSPORTATION
 ITEM UNIT COSTS BY PROJECTS -- 2022 COST DATA

11:31 Wednesday, March 8, 2023 407

PROJECT NUMBER	ITEM NUMBER/ PROJECT LOCATION	ITEM DESCRIPTION/ PROJECT LOCATION	DATE LET	UNIT/ QUANTITY	ENGR. EST.	AVERAGE BID	AWARDED BID
=====	613-00206	2 In Elec Cond (Bored)		Lin Foot	=====	=====	=====
CM760-047		COLFAX AND QUAIL	05/12/22	606.00	19.00	25.20	24.00
ITS 0741-024		VMS SIGN INSTALLATIONS AND VS	06/02/22	545.00	50.00	63.50	60.00
NHPP072A-047		SH-72 RESURFACING: I-70 TO IN	06/09/22	210.00	15.00	27.57	27.57
		WEIGHTED AVERAGE FOR THE SECOND QUARTER		59,416.00	12.01	29.08	30.19
NHPP0702-414		VAIL PASS AUX PHASE 1 CAP 3	07/08/22	250.00	98.23	98.23	98.23
FBR0702-423		VAIL PASS AUX BE F-12-AT PHAS					
NHPP0063-054		US 6 FROM I70-B TO 33 RD. (MP	08/18/22	4,535.00	50.00	28.43	25.00
C1211-099		SH 121 NORTH SGA SIGNALS	08/25/22	2,025.00	25.00	28.50	30.00
SHE2873-193		US 287 & CO 52 INTERSECTION I	09/15/22	470.00	32.00	26.42	26.75
		WEIGHTED AVERAGE FOR THE THIRD QUARTER		7,280.00	43.54	29.17	29.02
FSAM240-200		SH21B CO SPRINGS SIGNAL REPLA	10/27/22	8,355.00	20.00	22.63	19.50
TRG0253-264		I-25 AND SH 119 PARK-N-RIDE	10/27/22	1,473.00	25.00	25.41	26.60
STRC090-011		US 50B AND SH71/CR18 INTERSEC	11/17/22	1,880.00	29.00	24.00	22.00
STAM420-001		US 285 AT HWY 9C IMPROVEMENTS	12/01/22	1,956.00	45.00	56.11	60.77
BR2854-148		INTERSECTION OF US 285 & SH 9					
STM0091-046		ADA RAMP IMPROVEMENTS - FAIRP					
2670703-487		I-70 BRIDGES OVER WARD ROAD-	12/01/22	100.00	50.00	63.64	62.00
IM025A-050		I25-MP103.9 - INTERSECTION DR	12/01/22	320.00	25.00	36.00	25.00
NHPP0063-048		US6 / 20 ROAD INTERSECTION IM	12/15/22	345.00	35.00	42.69	26.50
NHPP0931-033		SH93:US6 TO 58TH RESURFACING	12/15/22	115.00	27.00	33.19	31.80
		WEIGHTED AVERAGE FOR THE FOURTH QUARTER		14,544.00	25.76	28.71	26.77
		WEIGHTED AVERAGE FOR THE YEAR		83,730.00	17.80	29.72	29.91
=====	613-00207	2 In Elec Cond (Bridge) (Spec)		Lin Foot	=====	=====	=====
STM1151-038		SH115 MP 27 TO MP 38	04/21/22	360.00	50.00	115.94	130.00
		WEIGHTED AVERAGE FOR THE SECOND QUARTER		360.00	50.00	115.94	130.00
		WEIGHTED AVERAGE FOR THE YEAR		360.00	50.00	115.94	130.00
=====	613-00300	3 In Elec Cond		Lin Foot	=====	=====	=====
STM1151-038		SH115 MP 27 TO MP 38	04/21/22	674.00	35.00	32.11	33.00

COLORADO DEPARTMENT OF TRANSPORTATION
ITEM UNIT COSTS BY PROJECTS -- 2022 COST DATA

11:31 Wednesday, March 8, 2023 408

PROJECT NUMBER	ITEM NUMBER/ PROJECT LOCATION	ITEM DESCRIPTION/ PROJECT LOCATION	DATE LET	UNIT/ QUANTITY	ENGR. EST.	AVERAGE BID	AWARDED BID
=====	613-00300	3 In Elec Cond		Lin Foot	=====	=====	=====
CM760-047		COLFAX AND QUAIL	05/12/22	108.00	21.50	46.60	66.00
		WEIGHTED AVERAGE FOR THE SECOND QUARTER		782.00	33.14	34.11	37.56
NHPP0063-054		US 6 FROM I70-B TO 33 RD. (MP	08/18/22	40.00	50.00	36.71	32.00
2670703-497		I-70_GENESEE WILDLIFE XING	09/15/22	1,789.00	30.00	58.40	59.07
		WEIGHTED AVERAGE FOR THE THIRD QUARTER		1,829.00	30.44	58.27	58.48
TRG0253-264		I-25 AND SH 119 PARK-N-RIDE	10/27/22	60.00	30.00	45.63	48.00
STAM420-001		US 285 AT HWY 9C IMPROVEMENTS	12/01/22	233.00	25.00	36.23	39.32
BR2854-148		INTERSECTION OF US 285 & SH 9					
STM0091-046		ADA RAMP IMPROVEMENTS - FAIRP					
		WEIGHTED AVERAGE FOR THE FOURTH QUARTER		293.00	26.02	39.43	41.10
		WEIGHTED AVERAGE FOR THE YEAR		2,904.00	30.72	51.51	51.09
=====	613-00306	3 In Elec Cond (Bored)		Lin Foot	=====	=====	=====
NHPP0063-063			02/24/22	6,100.00	25.00	26.60	28.00
NHPP0253-275		I-25 EXPRESS LANES SEGMENT 5	03/11/22	900.00	45.92	49.14	49.14
NHM765-007			03/31/22	6,150.00	42.00	47.03	42.18
		WEIGHTED AVERAGE FOR THE FIRST QUARTER		13,150.00	34.38	39.19	36.08
2670703-479		I-70 BRIDGE OVER HARLAN	05/05/22	2,020.00	30.00	26.72	31.50
NHC540-017		R2 CHAINUP STA @ KENOSHA/HOOS	05/12/22	1,160.00	36.00	62.00	68.00
CM760-047		COLFAX AND QUAIL	05/12/22	606.00	19.50	29.00	28.00
NHPP072A-047		SH-72 RESURFACING: I-70 TO IN	06/09/22	430.00	30.00	27.57	27.57
		WEIGHTED AVERAGE FOR THE SECOND QUARTER		4,216.00	30.14	33.54	40.64
C1211-099		SH 121 NORTH SGA SIGNALS	08/25/22	3,935.00	28.00	32.00	35.00

COLORADO DEPARTMENT OF TRANSPORTATION
 ITEM UNIT COSTS BY PROJECTS -- 2022 COST DATA

11:31 Wednesday, March 8, 2023 409

PROJECT NUMBER	ITEM NUMBER/ PROJECT LOCATION	ITEM DESCRIPTION/ PROJECT LOCATION	DATE LET	UNIT/ QUANTITY	ENGR. EST.	AVERAGE BID	AWARDED BID
=====	613-00306	3 In Elec Cond (Bored)		Lin Foot	=====	=====	=====
2670403-065		US40_FLOYD HILL ROUNDABOUTS	09/15/22	550.00	40.00	140.80	127.00
SHE2873-193		US 287 & CO 52 INTERSECTION I	09/15/22	940.00	30.00	31.20	32.10
		WEIGHTED AVERAGE FOR THE THIRD QUARTER		5,425.00	29.56	43.54	43.82
FSAM240-200		SH21B CO SPRINGS SIGNAL REPLA	10/27/22	2,855.00	12.00	26.38	21.50
TRG0253-264		I-25 AND SH 119 PARK-N-RIDE	10/27/22	1,490.00	58.00	35.96	37.77
STA3852-015		US 385 HOLYOKE NORTH	10/27/22	43.00	200.00	200.00	200.00
STRC090-011		US 50B AND SH71/CR18 INTERSEC	11/17/22	780.00	33.00	24.75	23.50
STAM420-001		US 285 AT HWY 9C IMPROVEMENTS	12/01/22	586.00	30.00	56.11	60.77
BR2854-148		INTERSECTION OF US 285 & SH 9					
STM0091-046		ADA RAMP IMPROVEMENTS - FAIRP					
IM025A-050		I25-MP103.9 - INTERSECTION DR	12/01/22	1,500.00	40.00	39.00	26.00
NHPP0063-048		US6 / 20 ROAD INTERSECTION IM	12/15/22	2,260.00	35.00	49.38	33.00
NHPP0931-033		SH93:US6 TO 58TH RESURFACING	12/15/22	420.00	27.00	35.30	33.85
		WEIGHTED AVERAGE FOR THE FOURTH QUARTER		9,934.00	32.52	37.40	31.00
		WEIGHTED AVERAGE FOR THE YEAR		32,725.00	32.47	38.10	36.41
=====	613-00400	4 In Elec Cond		Lin Foot	=====	=====	=====
NHPP 0761-238		I-76 DAHLIA TO YORK	03/10/22	200.00	40.00	45.91	46.00
C0761-239							
		WEIGHTED AVERAGE FOR THE FIRST QUARTER		200.00	40.00	45.91	46.00
		WEIGHTED AVERAGE FOR THE YEAR		200.00	40.00	45.91	46.00
=====	613-00408	4 In Elec Cond (Bored)		Lin Foot	=====	=====	=====
NHPP 0761-238		I-76 DAHLIA TO YORK	03/10/22	1,600.00	15.00	39.00	38.00
C0761-239							
		WEIGHTED AVERAGE FOR THE FIRST QUARTER		1,600.00	15.00	39.00	38.00
		WEIGHTED AVERAGE FOR THE YEAR		1,600.00	15.00	39.00	38.00
=====	613-00607	6 In Elec Cond (Brdg) (Spec)		Lin Foot	=====	=====	=====
NHPP0702-414		VAIL PASS AUX PHASE 1 CAP 3	07/08/22	1,264.00	45.48	45.48	45.48

COLORADO DEPARTMENT OF TRANSPORTATION
 ITEM UNIT COSTS BY PROJECTS -- 2022 COST DATA

11:31 Wednesday, March 8, 2023 410

PROJECT NUMBER	ITEM NUMBER/ PROJECT LOCATION	ITEM DESCRIPTION/ PROJECT LOCATION	DATE LET	UNIT/ QUANTITY	ENGR. EST.	AVERAGE BID	AWARDED BID
=====	613-00607	6 In Elec Cond (Brdg) (Spec)		Lin Foot	=====		
FBR0702-423		VAIL PASS AUX BE F-12-AT PHAS					
		WEIGHTED AVERAGE FOR THE THIRD QUARTER		1,264.00	45.48	45.48	45.48
2670703-487		I-70 BRIDGES OVER WARD ROAD-	12/01/22	433.00	20.00	189.47	180.00
		WEIGHTED AVERAGE FOR THE FOURTH QUARTER		433.00	20.00	189.47	180.00
		WEIGHTED AVERAGE FOR THE YEAR		1,697.00	38.98	136.39	79.80
=====	613-01075	3/4 In Elec Cond (P)		Lin Foot	=====		
TRG0253-264		I-25 AND SH 119 PARK-N-RIDE	10/27/22	1,210.00	25.00	6.77	7.00
		WEIGHTED AVERAGE FOR THE FOURTH QUARTER		1,210.00	25.00	6.77	7.00
		WEIGHTED AVERAGE FOR THE YEAR		1,210.00	25.00	6.77	7.00
=====	613-01100	1 In Elec Cond (P)		Lin Foot	=====		
NHPP 0761-238		I-76 DAHLIA TO YORK	03/10/22	397.00	15.00	22.46	30.00
C0761-239		I-25 EXPRESS LANES SEGMENT 5	03/11/22	720.00	30.61	32.76	32.76
NHPP0253-275							
		WEIGHTED AVERAGE FOR THE FIRST QUARTER		1,117.00	25.06	24.36	31.78
2670703-479		I-70 BRIDGE OVER HARLAN	05/05/22	100.00	15.00	28.92	34.04
NHC540-017		R2 CHAINUP STA @ KENOSHA/HOOS	05/12/22	279.00	25.00	20.67	17.00
ITS 0741-024		VMS SIGN INSTALLATIONS AND VS	06/02/22	220.00	15.00	35.00	40.00
		WEIGHTED AVERAGE FOR THE SECOND QUARTER		599.00	19.66	26.66	28.29
NHPP0063-054		US 6 FROM I70-B TO 33 RD. (MP	08/18/22	290.00	25.00	25.34	22.00
		WEIGHTED AVERAGE FOR THE THIRD QUARTER		290.00	25.00	25.34	22.00

PROJECT NUMBER	ITEM NUMBER/ PROJECT LOCATION	ITEM DESCRIPTION/ PROJECT LOCATION	DATE LET	UNIT/ QUANTITY	ENGR. EST.	AVERAGE BID	AWARDED BID
=====	613-01100	1 In Elec Cond (P)		Lin Foot	=====		
TRG0253-264		I-25 AND SH 119 PARK-N-RIDE	10/27/22	420.00	30.00	24.43	26.00
STA3852-015		US 385 HOLYOKE NORTH	10/27/22	238.00	70.00	60.00	60.00
STU0252-457		I-25:ALAMEDA RIVER PH 2.0	11/03/22	160.00	30.00	39.86	40.00
IM025A-050		I25-MP103.9 - INTERSECTION DR	12/01/22	40.00	15.00	21.00	21.00
		WEIGHTED AVERAGE FOR THE FOURTH QUARTER		858.00	40.40	28.11	37.81
		WEIGHTED AVERAGE FOR THE YEAR		2,864.00	28.52	26.32	31.87
=====	613-01150	1-1/2 In Elec Cond (P)		Lin Foot	=====		
TRG0253-264		I-25 AND SH 119 PARK-N-RIDE	10/27/22	310.00	35.00	9.02	10.00
		WEIGHTED AVERAGE FOR THE FOURTH QUARTER		310.00	35.00	9.02	10.00
		WEIGHTED AVERAGE FOR THE YEAR		310.00	35.00	9.02	10.00
=====	613-01200	2 In Elec Cond (P)		Lin Foot	=====		
ITS0703-477		ITS EQUIPMENT UPGRADE AT EJMT	01/06/22	90.00	25.00	175.00	175.00
NHPP2873-189		US 287 (FEDERAL BLVD) - COLFA	01/06/22	50.00	5.00	91.17	86.03
NHPP0702-383		I-70 EB AUX FRISCO TO SILVERT	01/13/22	2,250.00	25.00	80.13	80.00
STA0252-459			02/03/22	20.00	30.81	34.40	44.00
NHPP 0761-238		I-76 DAHLIA TO YORK	03/10/22	1,402.00	6.00	28.87	33.50
C0761-239							
NHPP0253-275		I-25 EXPRESS LANES SEGMENT 5	03/11/22	2,300.00	27.55	29.48	29.48
M R100-351		FY22 R1 SIGN STRUCTURE REPLAC	03/17/22	60.00	60.00	59.50	56.00
NHM765-007			03/31/22	4,532.00	20.00	44.38	39.90
		WEIGHTED AVERAGE FOR THE FIRST QUARTER		10,704.00	21.06	49.95	46.70
STM1151-038		SH115 MP 27 TO MP 38	04/21/22	914.00	20.00	38.53	41.00
2670703-479		I-70 BRIDGE OVER HARLAN	05/05/22	545.00	16.00	35.74	42.00
NHC540-017		R2 CHAINUP STA @ KENOSHA/HOOS	05/12/22	29,377.00	35.00	24.17	19.50
ITS 0741-024		VMS SIGN INSTALLATIONS AND VS	06/02/22	270.00	25.00	58.00	60.00
NHPP072A-047		SH-72 RESURFACING: I-70 TO IN	06/09/22	130.00	10.00	32.36	32.36
		WEIGHTED AVERAGE FOR THE SECOND QUARTER		31,236.00	34.04	25.44	20.93

PROJECT NUMBER	ITEM NUMBER/ PROJECT LOCATION	ITEM DESCRIPTION/ PROJECT LOCATION	DATE LET	UNIT/ QUANTITY	ENGR. EST.	AVERAGE BID	AWARDED BID
=====	613-01200	2 In Elec Cond (P)		Lin Foot	=====		
NHPP0702-414		VAIL PASS AUX PHASE 1 CAP 3	07/08/22	19,865.00	28.38	28.38	28.38
FBR0702-423		VAIL PASS AUX BE F-12-AT PHAS					
C1211-099		SH 121 NORTH SGA SIGNALS	08/25/22	505.00	25.00	26.00	25.00
2670703-497		I-70_GENESEE WILDLIFE KING	09/15/22	5,202.00	10.00	52.85	53.39
SHE2873-193		US 287 & CO 52 INTERSECTION I	09/15/22	130.00	40.00	37.70	39.59
		WEIGHTED AVERAGE FOR THE THIRD QUARTER		25,702.00	24.65	43.81	33.43
FSAM240-200		SH21B CO SPRINGS SIGNAL REPLA	10/27/22	1,839.00	15.00	22.00	21.00
TRG0253-264		I-25 AND SH 119 PARK-N-RIDE	10/27/22	7,300.00	20.00	23.19	24.50
STU0252-457		I-25:ALAMEDA RIVER PH 2.0	11/03/22	1,260.00	25.00	45.21	45.00
STRC090-011		US 50B AND SH71/CR18 INTERSEC	11/17/22	160.00	25.00	22.50	19.00
STAM420-001		US 285 AT HWY 9C IMPROVEMENTS	12/01/22	7,233.00	25.00	30.78	33.36
BR2854-148		INTERSECTION OF US 285 & SH 9					
STM0091-046		ADA RAMP IMPROVEMENTS - FAIRP					
2670703-487		I-70 BRIDGES OVER WARD ROAD-	12/01/22	985.00	30.00	34.03	33.00
IM025A-050		I25-MP103.9 - INTERSECTION DR	12/01/22	1,100.00	30.00	24.33	23.00
NHPP0063-048		US6 / 20 ROAD INTERSECTION IM	12/15/22	495.00	40.00	34.61	26.50
NHPP0931-033		SH93:US6 TO 58TH RESURFACING	12/15/22	150.00	32.00	38.73	36.90
		WEIGHTED AVERAGE FOR THE FOURTH QUARTER		20,522.00	23.25	26.68	28.99
		WEIGHTED AVERAGE FOR THE YEAR		88,164.00	27.21	32.55	29.58
=====	613-01250	2-1/2 In Elec Cond (P)		Lin Foot	=====		
NHM765-007			03/31/22	33,120.00	22.00	43.80	42.18
		WEIGHTED AVERAGE FOR THE FIRST QUARTER		33,120.00	22.00	43.80	42.18
		WEIGHTED AVERAGE FOR THE YEAR		33,120.00	22.00	43.80	42.18
=====	613-01300	3 In Elec Cond (P)		Lin Foot	=====		
NHPP2873-189		US 287 (FEDERAL BLVD) - COLFA	01/06/22	150.00	20.00	57.28	54.08
NHPP0063-063			02/24/22	4,045.00	20.00	21.05	22.00
		WEIGHTED AVERAGE FOR THE FIRST QUARTER		4,195.00	20.00	23.55	23.15

COLORADO DEPARTMENT OF TRANSPORTATION
ITEM UNIT COSTS BY PROJECTS -- 2022 COST DATA

11:31 Wednesday, March 8, 2023 413

PROJECT NUMBER	ITEM NUMBER/ PROJECT LOCATION	ITEM DESCRIPTION/ PROJECT LOCATION	DATE LET	UNIT/ QUANTITY	ENGR. EST.	AVERAGE BID	AWARDED BID
=====	613-01300	3 In Elec Cond (P)		Lin Foot	=====		
2670703-479		I-70 BRIDGE OVER HARLAN	05/05/22	680.00	18.00	43.32	51.00
NHPP072A-047		SH-72 RESURFACING: I-70 TO IN	06/09/22	390.00	26.00	39.56	39.56
		WEIGHTED AVERAGE FOR THE SECOND QUARTER		1,070.00	20.92	42.99	46.83
C1211-099		SH 121 NORTH SGA SIGNALS	08/25/22	250.00	28.00	29.50	30.00
SHE2873-193		US 287 & CO 52 INTERSECTION I	09/15/22	120.00	40.00	54.71	63.13
		WEIGHTED AVERAGE FOR THE THIRD QUARTER		370.00	31.89	44.38	40.74
FSAM240-200		SH21B CO SPRINGS SIGNAL REPLA	10/27/22	1,839.00	17.00	23.25	23.00
TRG0253-264		I-25 AND SH 119 PARK-N-RIDE	10/27/22	7,290.00	28.00	33.24	35.00
STU0252-457		I-25:ALAMEDA RIVER PH 2.0	11/03/22	370.00	35.00	53.03	53.00
STRC090-011		US 50B AND SH71/CR18 INTERSEC	11/17/22	180.00	24.00	23.00	20.00
STAM420-001		US 285 AT HWY 9C IMPROVEMENTS	12/01/22	136.00	20.00	36.23	39.32
BR2854-148		INTERSECTION OF US 285 & SH 9					
STM0091-046		ADA RAMP IMPROVEMENTS - FAIRP					
IM025A-050		I25-MP103.9 - INTERSECTION DR	12/01/22	1,020.00	20.00	32.33	25.00
NHPP0063-048		US6 / 20 ROAD INTERSECTION IM	12/15/22	140.00	40.00	39.36	33.00
NHPP0931-033		SH93:US6 TO 58TH RESURFACING	12/15/22	275.00	40.00	54.80	54.35
BR012A-048		CO 12 STRUCTURE P-17-F AT MP	12/22/22	268.00	20.00	32.39	35.00
		WEIGHTED AVERAGE FOR THE FOURTH QUARTER		11,518.00	25.85	32.66	32.45
		WEIGHTED AVERAGE FOR THE YEAR		17,153.00	24.24	32.45	31.32
=====	613-01400	4 In Elec Cond (P)		Lin Foot	=====		
STU0252-457		I-25:ALAMEDA RIVER PH 2.0	11/03/22	1,890.00	35.00	65.14	65.00
STAM420-001		US 285 AT HWY 9C IMPROVEMENTS	12/01/22	326.00	43.00	51.75	56.00
BR2854-148		INTERSECTION OF US 285 & SH 9					
STM0091-046		ADA RAMP IMPROVEMENTS - FAIRP					
		WEIGHTED AVERAGE FOR THE FOURTH QUARTER		2,216.00	36.18	62.64	63.68
		WEIGHTED AVERAGE FOR THE YEAR		2,216.00	36.18	62.64	63.68

COLORADO DEPARTMENT OF TRANSPORTATION
ITEM UNIT COSTS BY PROJECTS -- 2022 COST DATA

11:31 Wednesday, March 8, 2023 414

PROJECT NUMBER	ITEM NUMBER/ PROJECT LOCATION	ITEM DESCRIPTION/ PROJECT LOCATION	DATE LET	UNIT/ QUANTITY	ENGR. EST.	AVERAGE BID	AWARDED BID
=====	613-01600	6 In Elec Cond (P)		Lin Foot	=====		
STU0252-457		I-25:ALAMEDA RIVER PH 2.0	11/03/22	756.00	50.00	116.04	116.00
	WEIGHTED AVERAGE FOR THE FOURTH QUARTER			756.00	50.00	116.04	116.00
	WEIGHTED AVERAGE FOR THE YEAR			756.00	50.00	116.04	116.00
=====	613-04020	Hanger System		LUMP SUM	=====		
NHPP0702-413		VAIL PASS AUX PHASE 1 CAP 2	04/18/22	1.00	21400.00	21400.00	21400.00
	WEIGHTED AVERAGE FOR THE SECOND QUARTER			1.00	21400.00	21400.00	21400.00
NHPP0702-414 FBR0702-423		VAIL PASS AUX PHASE 1 CAP 3 VAIL PASS AUX BE F-12-AT PHAS	07/08/22	1.00	116724.27	116724.27	116724.27
	WEIGHTED AVERAGE FOR THE THIRD QUARTER			1.00	116724.27	116724.27	116724.27
	WEIGHTED AVERAGE FOR THE YEAR			2.00	53174.76	53174.76	53174.76
=====	613-04100	Elect System Mods		LUMP SUM	=====		
ITS 0741-024		VMS SIGN INSTALLATIONS AND VS	06/02/22	1.00	15000.00	14564.50	25500.00
	WEIGHTED AVERAGE FOR THE SECOND QUARTER			1.00	15000.00	14564.50	25500.00
TRG0253-264 STAM420-001 BR2854-148 STM0091-046		I-25 AND SH 119 PARK-N-RIDE US 285 AT HWY 9C IMPROVEMENTS INTERSECTION OF US 285 & SH 9 ADA RAMP IMPROVEMENTS - FAIRP	10/27/22 12/01/22	1.00 1.00	10000.00 3500.99	579.99 19776.93	1500.00 21447.71
	WEIGHTED AVERAGE FOR THE FOURTH QUARTER			2.00	6750.50	6978.97	11473.86
	WEIGHTED AVERAGE FOR THE YEAR			3.00	9500.33	8062.62	16149.24
=====	613-04120	1 In Elec Cond (Liquidtight Flx Met)		Lin Foot	=====		
NHC540-017		R2 CHAINUP STA @ KENOSHA/HOOS	05/12/22	80.00	42.00	33.00	32.00
	WEIGHTED AVERAGE FOR THE SECOND QUARTER			80.00	42.00	33.00	32.00
	WEIGHTED AVERAGE FOR THE YEAR			80.00	42.00	33.00	32.00

COLORADO DEPARTMENT OF TRANSPORTATION
 ITEM UNIT COSTS BY PROJECTS -- 2022 COST DATA

11:31 Wednesday, March 8, 2023 415

PROJECT NUMBER	ITEM NUMBER/ PROJECT LOCATION	ITEM DESCRIPTION/ PROJECT LOCATION	DATE LET	UNIT/ QUANTITY	ENGR. EST.	AVERAGE BID	AWARDED BID
=====	613-05606	6 In Wide Cable Tray		Lin Foot	=====		
ITS0703-477		ITS EQUIPMENT UPGRADE AT EJMT	01/06/22	4,000.00	20.00	140.00	140.00
		WEIGHTED AVERAGE FOR THE FIRST QUARTER		4,000.00	20.00	140.00	140.00
		WEIGHTED AVERAGE FOR THE YEAR		4,000.00	20.00	140.00	140.00
=====	613-07000	Pull Box (Spec)		Each	=====		
NHPP0702-383		I-70 EB AUX FRISCO TO SILVERT	01/13/22	2.00	1000.00	2205.74	2000.00
NHPP0063-063			02/24/22	2.00	1000.00	1780.00	2500.00
CR100-362			03/14/22	3.00	1096.75	1096.75	1096.75
		WEIGHTED AVERAGE FOR THE FIRST QUARTER		7.00	1041.46	1909.86	1755.75
NHC540-017		R2 CHAINUP STA @ KENOSHA/HOOS	05/12/22	4.00	1037.00	3566.67	3200.00
		WEIGHTED AVERAGE FOR THE SECOND QUARTER		4.00	1037.00	3566.67	3200.00
NHPP0702-414		VAIL PASS AUX PHASE 1 CAP 3	07/08/22	15.00	15861.68	15861.68	15861.68
FBR0702-423		VAIL PASS AUX BE F-12-AT PHAS					
NHPP0063-054		US 6 FROM I70-B TO 33 RD. (MP	08/18/22	9.00	800.00	1446.32	1300.00
		WEIGHTED AVERAGE FOR THE THIRD QUARTER		24.00	10213.55	7998.75	10401.05
NHPP0063-048		US6 / 20 ROAD INTERSECTION IM	12/15/22	6.00	2500.00	1702.41	1100.00
		WEIGHTED AVERAGE FOR THE FOURTH QUARTER		6.00	2500.00	1702.41	1100.00
		WEIGHTED AVERAGE FOR THE YEAR		41.00	6623.50	4419.59	6861.35
=====	613-07001	Type One Pull Box		Each	=====		
NHPP0702-383		I-70 EB AUX FRISCO TO SILVERT	01/13/22	4.00	1000.00	1527.02	1400.00

COLORADO DEPARTMENT OF TRANSPORTATION
ITEM UNIT COSTS BY PROJECTS -- 2022 COST DATA

11:31 Wednesday, March 8, 2023 416

PROJECT NUMBER	ITEM NUMBER/ PROJECT LOCATION	ITEM DESCRIPTION/ PROJECT LOCATION	DATE LET	UNIT/ QUANTITY	ENGR. EST.	AVERAGE BID	AWARDED BID
===== 613-07001 Type One Pull Box Each =====							
NHPP0063-063			02/24/22	74.00	1000.00	1046.00	1100.00
NHPP 0761-238	I-76 DAHLIA TO YORK		03/10/22	5.00	800.00	1623.75	1400.00
C0761-239							
CR100-362			03/14/22	7.00	1508.70	1508.70	1508.70
NHM765-007			03/31/22	50.00	850.00	1901.97	1710.00
WEIGHTED AVERAGE FOR THE FIRST QUARTER				140.00	964.72	1496.31	1357.58
CC030-081	ADA RAMP AND CURBS - FT. LUPT		04/14/22	2.00	900.00	1630.46	950.00
STM1151-038	SH115 MP 27 TO MP 38		04/21/22	5.00	950.00	1642.92	1600.00
NHPP072A-047	SH-72 RESURFACING: I-70 TO IN		06/09/22	13.00	1200.00	1168.69	1168.69
WEIGHTED AVERAGE FOR THE SECOND QUARTER				20.00	1107.50	1501.11	1254.65
TRG0253-264	I-25 AND SH 119 PARK-N-RIDE		10/27/22	69.00	1500.00	1078.33	1150.00
2670703-487	I-70 BRIDGES OVER WARD ROAD-		12/01/22	1.00	2000.00	1583.79	1540.00
IM025A-050	I25-MP103.9 - INTERSECTION DR		12/01/22	7.00	950.00	1075.00	1400.00
NHPP083A-046	SH83 RESURFACING STROH RD TO		12/08/22	2.00	1500.00	1978.10	1856.20
NHPP0931-033	SH93:US6 TO 58TH RESURFACING		12/15/22	6.00	1000.00	1302.56	1120.00
WEIGHTED AVERAGE FOR THE FOURTH QUARTER				85.00	1425.29	1097.20	1189.68
WEIGHTED AVERAGE FOR THE YEAR				245.00	1136.17	1258.23	1290.92
===== 613-07002 Type Two Pull Box Each =====							
NHPP0702-383	I-70 EB AUX FRISCO TO SILVERT		01/13/22	16.00	1800.00	1938.23	1900.00
STA0252-459			02/03/22	2.00	1354.43	1985.00	2645.00
NHPP0253-275	I-25 EXPRESS LANES SEGMENT 5		03/11/22	10.00	1545.92	1508.92	1508.92
CR100-362			03/14/22	20.00	1599.65	1599.65	1599.65
NHM765-007			03/31/22	36.00	1324.00	2187.27	1966.50
WEIGHTED AVERAGE FOR THE FIRST QUARTER				84.00	1507.44	2010.16	1828.17
CC030-081	ADA RAMP AND CURBS - FT. LUPT		04/14/22	6.00	1400.00	1663.79	1050.00
STM1151-038	SH115 MP 27 TO MP 38		04/21/22	12.00	1100.00	1788.10	1700.00
2670703-479	I-70 BRIDGE OVER HARLAN		05/05/22	21.00	1750.00	1390.11	1644.31

COLORADO DEPARTMENT OF TRANSPORTATION
 ITEM UNIT COSTS BY PROJECTS -- 2022 COST DATA

11:31 Wednesday, March 8, 2023 417

PROJECT NUMBER	ITEM NUMBER/ PROJECT LOCATION	ITEM DESCRIPTION/ PROJECT LOCATION	DATE LET	UNIT/ QUANTITY	ENGR. EST.	AVERAGE BID	AWARDED BID
=====	613-07002	Type Two Pull Box		Each =====			
NHC540-017		R2 CHAINUP STA @ KENOSHA/HOOS	05/12/22	74.00	1200.00	2833.33	2500.00
		WEIGHTED AVERAGE FOR THE SECOND QUARTER		113.00	1302.21	2209.83	2179.03
NHPP0702-414		VAIL PASS AUX PHASE 1 CAP 3	07/08/22	8.00	2728.50	2728.50	2728.50
FBR0702-423		VAIL PASS AUX BE F-12-AT PHAS					
NHPP0063-054		US 6 FROM I70-B TO 33 RD. (MP	08/18/22	32.00	1300.00	1396.32	1200.00
2670403-065		US40_FLOYD HILL ROUNDABOUTS	09/15/22	36.00	2000.00	3098.53	2727.00
		WEIGHTED AVERAGE FOR THE THIRD QUARTER		76.00	1781.95	2476.85	2084.21
FSAM240-200		SH21B CO SPRINGS SIGNAL REPLA	10/27/22	7.00	900.00	1425.00	1050.00
TRG0253-264		I-25 AND SH 119 PARK-N-RIDE	10/27/22	41.00	1900.00	1361.61	1450.00
STA3852-015		US 385 HOLYOKE NORTH	10/27/22	10.00	4000.00	4350.00	4350.00
STU0252-457		I-25:ALAMEDA RIVER PH 2.0	11/03/22	5.00	2000.00	1745.63	1700.00
STRC090-011		US 50B AND SH71/CR18 INTERSEC	11/17/22	7.00	2685.00	2300.00	1610.00
STAM420-001		US 285 AT HWY 9C IMPROVEMENTS	12/01/22	3.00	1095.00	1987.69	2144.77
BR2854-148		INTERSECTION OF US 285 & SH 9					
STM0091-046		ADA RAMP IMPROVEMENTS - FAIRP					
IM025A-050		I25-MP103.9 - INTERSECTION DR	12/01/22	11.00	1200.00	1366.67	1600.00
NHPP0063-048		US6 / 20 ROAD INTERSECTION IM	12/15/22	3.00	2700.00	2133.78	1650.00
		WEIGHTED AVERAGE FOR THE FOURTH QUARTER		87.00	2041.15	1510.95	1828.21
		WEIGHTED AVERAGE FOR THE YEAR		360.00	1629.95	1966.03	1992.36
=====	613-07003	Type Three Pull Box		Each =====			
NHPP0063-063			02/24/22	1.00	1400.00	2175.00	3000.00
NHPP 0761-238		I-76 DAHLIA TO YORK	03/10/22	12.00	2000.00	2505.81	1700.00
C0761-239							
CR100-362			03/14/22	10.00	1968.80	1968.80	1968.80
MP0503-098			03/24/22	2.00	1400.00	2299.00	2600.00
		WEIGHTED AVERAGE FOR THE FIRST QUARTER		25.00	1915.52	2444.57	1931.52
CC030-081		ADA RAMP AND CURBS - FT. LUPT	04/14/22	16.00	1300.00	2101.72	1100.00
		WEIGHTED AVERAGE FOR THE SECOND QUARTER		16.00	1300.00	2101.72	1100.00

COLORADO DEPARTMENT OF TRANSPORTATION
 ITEM UNIT COSTS BY PROJECTS -- 2022 COST DATA

11:31 Wednesday, March 8, 2023 418

PROJECT NUMBER	ITEM NUMBER/ PROJECT LOCATION	ITEM DESCRIPTION/ PROJECT LOCATION	DATE LET	UNIT/ QUANTITY	ENGR. EST.	AVERAGE BID	AWARDED BID
===== 613-07003		Type Three Pull Box		Each	=====		
TRG0253-264		I-25 AND SH 119 PARK-N-RIDE	10/27/22	7.00	1300.00	1632.44	1700.00
STU0252-457		I-25:ALAMEDA RIVER PH 2.0	11/03/22	5.00	2000.00	2314.05	2300.00
NHPP083A-046		SH83 RESURFACING STROH RD TO	12/08/22	1.00	3000.00	2451.07	2302.14
		WEIGHTED AVERAGE FOR THE FOURTH QUARTER		13.00	1700.00	1794.93	1977.09
		WEIGHTED AVERAGE FOR THE YEAR		54.00	1681.26	2170.40	1696.11
===== 613-07004		Type Four Pull Box		Each	=====		
NHPP0702-383		I-70 EB AUX FRISCO TO SILVERT	01/13/22	10.00	1800.00	3429.72	3200.00
NHPP0063-063			02/24/22	18.00	1500.00	2090.00	2200.00
NHPP 0761-238		I-76 DAHLIA TO YORK	03/10/22	2.00	1800.00	3583.20	2550.00
C0761-239							
CR100-362			03/14/22	3.00	1674.55	1674.55	1674.55
		WEIGHTED AVERAGE FOR THE FIRST QUARTER		33.00	1624.96	2943.63	2476.47
CC030-081		ADA RAMP AND CURBS - FT. LUPT	04/14/22	2.00	1700.00	2736.32	1700.00
STM1151-038		SH115 MP 27 TO MP 38	04/21/22	46.00	1500.00	3200.65	3100.00
2670703-479		I-70 BRIDGE OVER HARLAN	05/05/22	11.00	3000.00	2634.47	3085.70
CM760-047		COLFAX AND QUAIL	05/12/22	4.00	2000.00	2349.60	2402.00
NHPP072A-047		SH-72 RESURFACING: I-70 TO IN	06/09/22	6.00	1800.00	3296.31	3296.31
		WEIGHTED AVERAGE FOR THE SECOND QUARTER		69.00	1800.00	3028.08	3033.75
NHPP0063-054		US 6 FROM I70-B TO 33 RD. (MP	08/18/22	2.00	2200.00	4238.94	3700.00
C1211-099		SH 121 NORTH SGA SIGNALS	08/25/22	17.00	2000.00	2212.50	2500.00
SHE2873-193		US 287 & CO 52 INTERSECTION I	09/15/22	4.00	1800.00	2676.71	2480.00
		WEIGHTED AVERAGE FOR THE THIRD QUARTER		23.00	1982.61	2522.93	2600.87
FSAM240-200		SH21B CO SPRINGS SIGNAL REPLA	10/27/22	12.00	1200.00	2404.00	1895.00

PROJECT NUMBER	ITEM NUMBER/ PROJECT LOCATION	ITEM DESCRIPTION/ PROJECT LOCATION	DATE LET	UNIT/ QUANTITY	ENGR. EST.	AVERAGE BID	AWARDED BID
===== 613-07004 Type Four Pull Box Each =====							
TRG0253-264		I-25 AND SH 119 PARK-N-RIDE	10/27/22	8.00	2500.00	3023.91	3200.00
STU0252-457		I-25:ALAMEDA RIVER PH 2.0	11/03/22	2.00	1700.00	4093.01	4100.00
STRC090-011		US 50B AND SH71/CR18 INTERSEC	11/17/22	3.00	1675.00	2770.00	2190.00
STAM420-001		US 285 AT HWY 9C IMPROVEMENTS	12/01/22	11.00	1500.00	4277.50	4647.00
BR2854-148		INTERSECTION OF US 285 & SH 9					
STM0091-046		ADA RAMP IMPROVEMENTS - FAIRP					
2670703-487		I-70 BRIDGES OVER WARD ROAD-	12/01/22	1.00	10000.00	3504.31	3400.00
NHPP083A-046		SH83 RESURFACING STROH RD TO	12/08/22	1.00	3200.00	4429.17	4158.33
NHPP0063-048		US6 / 20 ROAD INTERSECTION IM	12/15/22	3.00	3200.00	3875.79	3300.00
NHPP0931-033		SH93:US6 TO 58TH RESURFACING	12/15/22	8.00	3000.00	3144.25	2780.00
	WEIGHTED AVERAGE FOR THE FOURTH QUARTER			49.00	2165.82	3250.30	3141.33
	WEIGHTED AVERAGE FOR THE YEAR			174.00	1893.96	3039.96	2901.14
===== 613-07005 Type Five Pull Box Each =====							
NHPP2873-189		US 287 (FEDERAL BLVD) - COLFA	01/06/22	1.00	2800.00	2589.20	2443.37
NHPP0063-063			02/24/22	6.00	2000.00	2615.00	3000.00
CR100-362			03/14/22	3.00	1915.30	1915.30	1915.30
M R100-351		FY22 R1 SIGN STRUCTURE REPLAC	03/17/22	3.00	7400.00	5187.00	7874.00
	WEIGHTED AVERAGE FOR THE FIRST QUARTER			13.00	3288.15	3144.19	3831.64
STM1151-038		SH115 MP 27 TO MP 38	04/21/22	1.00	2500.00	3771.09	3699.00
2670703-479		I-70 BRIDGE OVER HARLAN	05/05/22	2.00	2300.00	3102.03	3652.58
CM760-047		COLFAX AND QUAIL	05/12/22	1.00	2500.00	3158.80	3049.00
NHPP072A-047		SH-72 RESURFACING: I-70 TO IN	06/09/22	5.00	2600.00	6472.75	6472.75
	WEIGHTED AVERAGE FOR THE SECOND QUARTER			9.00	2511.11	3860.65	5157.43
NHPP0063-054		US 6 FROM I70-B TO 33 RD. (MP	08/18/22	1.00	2500.00	5635.24	4900.00
C1211-099		SH 121 NORTH SGA SIGNALS	08/25/22	5.00	2400.00	2909.50	3295.00
SHE2873-193		US 287 & CO 52 INTERSECTION I	09/15/22	1.00	2400.00	3563.13	3389.00
	WEIGHTED AVERAGE FOR THE THIRD QUARTER			7.00	2414.29	3430.24	3537.71
TRG0253-264		I-25 AND SH 119 PARK-N-RIDE	10/27/22	7.00	2000.00	6199.90	6500.00

COLORADO DEPARTMENT OF TRANSPORTATION
ITEM UNIT COSTS BY PROJECTS -- 2022 COST DATA

11:31 Wednesday, March 8, 2023 420

PROJECT NUMBER	ITEM NUMBER/ PROJECT LOCATION	ITEM DESCRIPTION/ PROJECT LOCATION	DATE LET	UNIT/ QUANTITY	ENGR. EST.	AVERAGE BID	AWARDED BID
===== 613-07005							
		Type Five Pull Box		Each			
STRC090-011		US 50B AND SH71/CR18 INTERSEC	11/17/22	2.00	2400.00	3340.00	2910.00
STAM420-001		US 285 AT HWY 9C IMPROVEMENTS	12/01/22	1.00	2533.00	5829.04	6315.16
BR2854-148		INTERSECTION OF US 285 & SH 9					
STM0091-046		ADA RAMP IMPROVEMENTS - FAIRP					
NHPP0063-048		US6 / 20 ROAD INTERSECTION IM	12/15/22	2.00	3500.00	5199.17	4400.00
NHPP0931-033		SH93:US6 TO 58TH RESURFACING	12/15/22	2.00	6000.00	6511.22	6540.00
		WEIGHTED AVERAGE FOR THE FOURTH QUARTER		14.00	2880.93	5969.42	5679.65
		WEIGHTED AVERAGE FOR THE YEAR		43.00	2850.67	4814.27	4662.96
===== 613-07010							
		Pull Box (Surf Mtd)		Each			
2670703-479		I-70 BRIDGE OVER HARLAN	05/05/22	10.00	1000.00	365.01	429.41
		WEIGHTED AVERAGE FOR THE SECOND QUARTER		10.00	1000.00	365.01	429.41
		WEIGHTED AVERAGE FOR THE YEAR		10.00	1000.00	365.01	429.41
===== 613-07011							
		Pull Box (11"x18"x12")		Each			
STM1151-038		SH115 MP 27 TO MP 38	04/21/22	8.00	1100.00	1602.92	1600.00
CM760-047		COLFAX AND QUAIL	05/12/22	1.00	500.00	1078.80	1369.00
ITS 0741-024		VMS SIGN INSTALLATIONS AND VS	06/02/22	3.00	1000.00	1547.00	1240.00
		WEIGHTED AVERAGE FOR THE SECOND QUARTER		12.00	1025.00	1544.95	1490.75
===== 613-07023							
		Pull Box (24"x36"x24")		Each			
STU0252-457		I-25:ALAMEDA RIVER PH 2.0	11/03/22	8.00	3000.00	1638.61	1600.00
STAM420-001		US 285 AT HWY 9C IMPROVEMENTS	12/01/22	62.00	1500.00	1878.66	2025.62
BR2854-148		INTERSECTION OF US 285 & SH 9					
STM0091-046		ADA RAMP IMPROVEMENTS - FAIRP					
		WEIGHTED AVERAGE FOR THE FOURTH QUARTER		70.00	1671.43	1857.47	1976.98
		WEIGHTED AVERAGE FOR THE YEAR		82.00	1576.83	1808.13	1905.82
===== 613-07023							
		Pull Box (24"x36"x24")		Each			
NHC540-017		R2 CHAINUP STA @ KENOSHA/HOOS	05/12/22	22.00	1400.00	4466.67	3900.00

COLORADO DEPARTMENT OF TRANSPORTATION
ITEM UNIT COSTS BY PROJECTS -- 2022 COST DATA

11:31 Wednesday, March 8, 2023 421

PROJECT NUMBER	ITEM NUMBER/ PROJECT LOCATION	ITEM DESCRIPTION/ PROJECT LOCATION	DATE LET	UNIT/ QUANTITY	ENGR. EST.	AVERAGE BID	AWARDED BID
=====	613-07023	Pull Box (24"x36"x24")		Each =====			
ITS 0741-024		VMS SIGN INSTALLATIONS AND VS	06/02/22	11.00	1500.00	3305.00	2655.00
		WEIGHTED AVERAGE FOR THE SECOND QUARTER		33.00	1433.33	4176.25	3485.00
NHPP0702-414		VAIL PASS AUX PHASE 1 CAP 3	07/08/22	5.00	3492.48	3492.48	3492.48
FBR0702-423		VAIL PASS AUX BE F-12-AT PHAS					
2670703-497		I-70_GENESEE WILDLIFE XING	09/15/22	2.00	1800.00	4883.62	4943.38
		WEIGHTED AVERAGE FOR THE THIRD QUARTER		7.00	3008.91	4517.53	3907.02
STU0252-457		I-25:ALAMEDA RIVER PH 2.0	11/03/22	13.00	2100.00	3771.96	3800.00
STAM420-001		US 285 AT HWY 9C IMPROVEMENTS	12/01/22	9.00	1620.00	3187.12	3455.46
BR2854-148		INTERSECTION OF US 285 & SH 9					
STM0091-046		ADA RAMP IMPROVEMENTS - FAIRP					
		WEIGHTED AVERAGE FOR THE FOURTH QUARTER		22.00	1903.64	3594.46	3646.40
		WEIGHTED AVERAGE FOR THE YEAR		62.00	1778.10	3928.13	3594.90
=====	613-07034	Pull Box (24"x36"x18")		Each =====			
STM1151-038		SH115 MP 27 TO MP 38	04/21/22	4.00	1500.00	2554.74	2600.00
		WEIGHTED AVERAGE FOR THE SECOND QUARTER		4.00	1500.00	2554.74	2600.00
FSAM240-200		SH21B CO SPRINGS SIGNAL REPLA	10/27/22	3.00	1500.00	2292.75	2125.00
TRG0253-264		I-25 AND SH 119 PARK-N-RIDE	10/27/22	4.00	1500.00	3023.91	3200.00
		WEIGHTED AVERAGE FOR THE FOURTH QUARTER		7.00	1500.00	2824.50	2739.29
		WEIGHTED AVERAGE FOR THE YEAR		11.00	1500.00	2740.20	2688.64
=====	613-07040	Pull Box (30"x48"x24")		Each =====			
ITS0703-477		ITS EQUIPMENT UPGRADE AT EJMT	01/06/22	1.00	3500.00	4005.00	4005.00
		WEIGHTED AVERAGE FOR THE FIRST QUARTER		1.00	3500.00	4005.00	4005.00

COLORADO DEPARTMENT OF TRANSPORTATION
 ITEM UNIT COSTS BY PROJECTS -- 2022 COST DATA

11:31 Wednesday, March 8, 2023 422

PROJECT NUMBER	ITEM NUMBER/ PROJECT LOCATION	ITEM DESCRIPTION/ PROJECT LOCATION	DATE LET	UNIT/ QUANTITY	ENGR. EST.	AVERAGE BID	AWARDED BID
===== 613-07040		Pull Box (30"x48"x24")		Each	=====	=====	=====
ITS 0741-024		VMS SIGN INSTALLATIONS AND VS	06/02/22	2.00	2000.00	4218.50	3300.00
		WEIGHTED AVERAGE FOR THE SECOND QUARTER		2.00	2000.00	4218.50	3300.00
2670703-497		I-70_GENESEE WILDLIFE XING	09/15/22	1.00	2600.00	5834.76	5871.40
		WEIGHTED AVERAGE FOR THE THIRD QUARTER		1.00	2600.00	5834.76	5871.40
FSAM240-200		SH21B CO SPRINGS SIGNAL REPLA	10/27/22	3.00	1900.00	3496.50	3140.00
		WEIGHTED AVERAGE FOR THE FOURTH QUARTER		3.00	1900.00	3496.50	3140.00
		WEIGHTED AVERAGE FOR THE YEAR		7.00	2257.14	4320.01	3699.49
===== 613-07060		Pull Box (18"x30"x18") Deep		Each	=====	=====	=====
NHM765-007			03/31/22	3.00	1200.00	2891.00	2599.20
		WEIGHTED AVERAGE FOR THE FIRST QUARTER		3.00	1200.00	2891.00	2599.20
		WEIGHTED AVERAGE FOR THE YEAR		3.00	1200.00	2891.00	2599.20
===== 613-07195		Proof Conduit		Lin Foot	=====	=====	=====
ITS0703-477		ITS EQUIPMENT UPGRADE AT EJMT	01/06/22	5,975.00	3.00	17.00	17.00
		WEIGHTED AVERAGE FOR THE FIRST QUARTER		5,975.00	3.00	17.00	17.00
ITS 0741-024		VMS SIGN INSTALLATIONS AND VS	06/02/22	700.00	5.00	7.00	8.00
		WEIGHTED AVERAGE FOR THE SECOND QUARTER		700.00	5.00	7.00	8.00
		WEIGHTED AVERAGE FOR THE YEAR		6,675.00	3.21	15.10	16.06

COLORADO DEPARTMENT OF TRANSPORTATION
ITEM UNIT COSTS BY PROJECTS -- 2022 COST DATA

11:31 Wednesday, March 8, 2023 423

PROJECT NUMBER	ITEM NUMBER/ PROJECT LOCATION	ITEM DESCRIPTION/ PROJECT LOCATION	DATE LET	UNIT/ QUANTITY	ENGR. EST.	AVERAGE BID	AWARDED BID
===== 613-10000 Wiring LUMP SUM =====							
ITS0703-477		ITS EQUIPMENT UPGRADE AT EJMT	01/06/22	1.00	50000.00	210000.00	210000.00
NHPP2873-189		US 287 (FEDERAL BLVD) - COLFA	01/06/22	1.00	52000.00	6396.06	6028.53
NHPP0702-383		I-70 EB AUX FRISCO TO SILVERT	01/13/22	1.00	5000.00	82184.01	72000.00
STA0252-459			02/03/22	1.00	6500.00	1863.00	2444.00
NHPP 0761-238		I-76 DAHLIA TO YORK	03/10/22	1.00	30000.00	54332.23	130000.00
C0761-239							
NHPP0253-275		I-25 EXPRESS LANES SEGMENT 5	03/11/22	1.00	63823.47	56551.69	56551.69
NHM765-007			03/31/22	1.00	255000.00	297975.47	267900.00
WEIGHTED AVERAGE FOR THE FIRST QUARTER				7.00	66046.21	81489.17	106417.75
STM1151-038		SH115 MP 27 TO MP 38	04/21/22	1.00	100000.00	102055.69	97000.00
2670703-479		I-70 BRIDGE OVER HARLAN	05/05/22	1.00	40000.00	36815.42	36282.23
NHC540-017		R2 CHAINUP STA @ KENOSHA/HOOS	05/12/22	1.00	310000.00	217666.67	203000.00
CM760-047		COLFAX AND QUAIL	05/12/22	1.00	10000.00	20351.40	12537.00
ITS 0741-024		VMS SIGN INSTALLATIONS AND VS	06/02/22	1.00	40000.00	55038.00	34000.00
NHPP072A-047		SH-72 RESURFACING: I-70 TO IN	06/09/22	1.00	50000.00	30565.75	30565.75
WEIGHTED AVERAGE FOR THE SECOND QUARTER				6.00	91666.67	73934.99	68897.50
NHPP0063-054		US 6 FROM I70-B TO 33 RD. (MP	08/18/22	1.00	70000.00	71422.84	75000.00
C1211-099		SH 121 NORTH SGA SIGNALS	08/25/22	1.00	120000.00	120000.00	90000.00
2670403-065		US40 FLOYD HILL ROUNDABOUTS	09/15/22	1.00	10000.00	117011.77	101000.00
2670703-497		I-70 GENESEE WILDLIFE XING	09/15/22	1.00	20000.00	82076.44	81420.37
SHE2873-193		US 287 & CO 52 INTERSECTION I	09/15/22	1.00	25000.00	22080.16	15865.00
WEIGHTED AVERAGE FOR THE THIRD QUARTER				5.00	49000.00	72044.85	72657.07
FSAM240-200		SH21B CO SPRINGS SIGNAL REPLA	10/27/22	1.00	20000.00	63690.00	41000.00
TRG0253-264		I-25 AND SH 119 PARK-N-RIDE	10/27/22	1.00	107500.00	80415.90	80000.00
STA3852-015		US 385 HOLYOKE NORTH	10/27/22	1.00	25232.62	18000.00	18000.00
STU0252-457		I-25:ALAMEDA RIVER PH 2.0	11/03/22	1.00	150000.00	55912.72	55000.00
STRC090-011		US 50B AND SH71/CR18 INTERSEC	11/17/22	1.00	25000.00	30750.00	39500.00
STAM420-001		US 285 AT HWY 9C IMPROVEMENTS	12/01/22	1.00	250000.00	224525.00	225000.00
BR2854-148		INTERSECTION OF US 285 & SH 9					
STM0091-046		ADA RAMP IMPROVEMENTS - FAIRP					
2670703-487		I-70 BRIDGES OVER WARD ROAD-	12/01/22	1.00	20000.00	9481.41	9100.00

COLORADO DEPARTMENT OF TRANSPORTATION
ITEM UNIT COSTS BY PROJECTS -- 2022 COST DATA

11:31 Wednesday, March 8, 2023 424

PROJECT NUMBER	ITEM NUMBER/ PROJECT LOCATION	ITEM DESCRIPTION/ PROJECT LOCATION	DATE LET	UNIT/ QUANTITY	ENGR. EST.	AVERAGE BID	AWARDED BID
===== 613-10000 Wiring LUMP SUM =====							
IM025A-050		I25-MP103.9 - INTERSECTION DR	12/01/22	1.00	40000.00	51666.67	50000.00
NHPP083A-046		SH83 RESURFACING STROH RD TO	12/08/22	1.00	10000.00	14481.50	13562.99
NHPP0063-048		US6 / 20 ROAD INTERSECTION IM	12/15/22	1.00	20000.00	30342.62	26500.00
FSA0853-122		WCR14.5 AND US-85, FORT LUPTO	12/15/22	1.00	5000.00	5139.71	2500.00
NHPP0931-033		SH93:US6 TO 58TH RESURFACING	12/15/22	1.00	35000.00	17292.88	10880.00
		WEIGHTED AVERAGE FOR THE FOURTH QUARTER		12.00	62710.20	61256.54	50080.23
		WEIGHTED AVERAGE FOR THE YEAR		30.00	66856.65	69735.42	70085.08
===== 613-13000 Luminaire (LED) (Spec) Each =====							
NHPP0253-275		I-25 EXPRESS LANES SEGMENT 5	03/11/22	8.00	2017.35	2382.39	2382.39
NHM765-007			03/31/22	46.00	1500.00	1711.78	1539.00
		WEIGHTED AVERAGE FOR THE FIRST QUARTER		54.00	1576.64	1748.52	1663.95
CM760-047		COLFAX AND QUAIL	05/12/22	4.00	5000.00	1041.20	1075.00
		WEIGHTED AVERAGE FOR THE SECOND QUARTER		4.00	5000.00	1041.20	1075.00
SHE2873-193		US 287 & CO 52 INTERSECTION I	09/15/22	4.00	1250.00	1217.33	1035.00
		WEIGHTED AVERAGE FOR THE THIRD QUARTER		4.00	1250.00	1217.33	1035.00
		WEIGHTED AVERAGE FOR THE YEAR		62.00	1776.43	1606.97	1585.37
===== 613-13005 Lumin (Spec) (LED) (Step) (Light) Each =====							
NHPP0253-275		I-25 EXPRESS LANES SEGMENT 5	03/11/22	58.00	864.29	999.03	999.03
		WEIGHTED AVERAGE FOR THE FIRST QUARTER		58.00	864.29	999.03	999.03
		WEIGHTED AVERAGE FOR THE YEAR		58.00	864.29	999.03	999.03
===== 613-13006 Lumin (LED) (6,000 Lumens) Each =====							
TRG0253-264		I-25 AND SH 119 PARK-N-RIDE	10/27/22	43.00	1200.00	1622.53	1700.00

COLORADO DEPARTMENT OF TRANSPORTATION
ITEM UNIT COSTS BY PROJECTS -- 2022 COST DATA

11:31 Wednesday, March 8, 2023 425

PROJECT NUMBER	ITEM NUMBER/ PROJECT LOCATION	ITEM DESCRIPTION/ PROJECT LOCATION	DATE LET	UNIT/ QUANTITY	ENGR. EST.	AVERAGE BID	AWARDED BID
=====	613-13006	Lumin (LED) (6,000 Lumens)		Each =====			
STA3852-015		US 385 HOLYOKE NORTH	10/27/22	1.00	3500.00	3700.00	3700.00
2670703-487		I-70 BRIDGES OVER WARD ROAD-	12/01/22	16.00	9000.00	3166.38	3030.00
		WEIGHTED AVERAGE FOR THE FOURTH QUARTER		60.00	3318.33	1918.02	2088.00
		WEIGHTED AVERAGE FOR THE YEAR		60.00	3318.33	1918.02	2088.00
=====	613-13008	Lumin (LED) (8,000 Lumens)		Each =====			
NHPP072A-047		SH-72 RESURFACING: I-70 TO IN	06/09/22	4.00	1000.00	839.06	839.06
		WEIGHTED AVERAGE FOR THE SECOND QUARTER		4.00	1000.00	839.06	839.06
2670403-065		US40_FLOYD HILL ROUNDABOUTS	09/15/22	33.00	1300.00	1158.12	1000.00
		WEIGHTED AVERAGE FOR THE THIRD QUARTER		33.00	1300.00	1158.12	1000.00
FSAM240-200		SH21B CO SPRINGS SIGNAL REPLA	10/27/22	11.00	800.00	1173.25	1015.00
TRG0253-264		I-25 AND SH 119 PARK-N-RIDE	10/27/22	15.00	1000.00	1578.55	1650.00
STRC090-011		US 50B AND SH71/CR18 INTERSEC	11/17/22	4.00	1305.00	1187.50	1025.00
STAM420-001		US 285 AT HWY 9C IMPROVEMENTS	12/01/22	43.00	1000.00	1178.42	1280.91
BR2854-148		INTERSECTION OF US 285 & SH 9					
STM0091-046		ADA RAMP IMPROVEMENTS - FAIRP					
NHPP0063-048		US6 / 20 ROAD INTERSECTION IM	12/15/22	4.00	1250.00	1171.45	880.00
NHPP0931-033		SH93:US6 TO 58TH RESURFACING	12/15/22	3.00	1000.00	1410.26	1260.00
		WEIGHTED AVERAGE FOR THE FOURTH QUARTER		80.00	1000.25	1314.26	1279.93
		WEIGHTED AVERAGE FOR THE YEAR		117.00	1084.79	1277.71	1185.90
=====	613-13010	Lumin(LED) (10,000 Lumens)		Each =====			
NHPP0063-054		US 6 FROM I70-B TO 33 RD. (MP	08/18/22	29.00	1500.00	1266.68	1100.00
		WEIGHTED AVERAGE FOR THE THIRD QUARTER		29.00	1500.00	1266.68	1100.00
IM025A-050		I25-MP103.9 - INTERSECTION DR	12/01/22	13.00	700.00	800.00	1200.00
		WEIGHTED AVERAGE FOR THE FOURTH QUARTER		13.00	700.00	800.00	1200.00
		WEIGHTED AVERAGE FOR THE YEAR		42.00	1252.38	1079.05	1130.95

COLORADO DEPARTMENT OF TRANSPORTATION
ITEM UNIT COSTS BY PROJECTS -- 2022 COST DATA

11:31 Wednesday, March 8, 2023 426

PROJECT NUMBER	ITEM NUMBER/ PROJECT LOCATION	ITEM DESCRIPTION/ PROJECT LOCATION	DATE LET	UNIT/ QUANTITY	ENGR. EST.	AVERAGE BID	AWARDED BID
=====	613-13011	Lumin (LED) (11,000 Lumens)		Each	=====	=====	=====
NHC540-017		R2 CHAINUP STA @ KENOSHA/HOOS	05/12/22	54.00	815.00	1066.67	1100.00
	WEIGHTED AVERAGE FOR THE SECOND QUARTER			54.00	815.00	1066.67	1100.00
	WEIGHTED AVERAGE FOR THE YEAR			54.00	815.00	1066.67	1100.00
=====	613-13012	Lumin (LED) (12,000 Lumens)		Each	=====	=====	=====
IM025A-050		I25-MP103.9 - INTERSECTION DR	12/01/22	2.00	750.00	900.00	1200.00
	WEIGHTED AVERAGE FOR THE FOURTH QUARTER			2.00	750.00	900.00	1200.00
	WEIGHTED AVERAGE FOR THE YEAR			2.00	750.00	900.00	1200.00
=====	613-13014	Lumin (LED) (14,000 Lumens)		Each	=====	=====	=====
C1211-099		SH 121 NORTH SGA SIGNALS	08/25/22	18.00	200.00	1100.00	1100.00
	WEIGHTED AVERAGE FOR THE THIRD QUARTER			18.00	200.00	1100.00	1100.00
TRG0253-264 STU0252-457		I-25 AND SH 119 PARK-N-RIDE	10/27/22	24.00	1900.00	4006.93	4200.00
		I-25:ALAMEDA RIVER PH 2.0	11/03/22	7.00	1500.00	3310.55	3300.00
	WEIGHTED AVERAGE FOR THE FOURTH QUARTER			31.00	1809.68	3938.27	3996.77
	WEIGHTED AVERAGE FOR THE YEAR			49.00	1218.37	3527.92	2932.65
=====	613-13016	Lumin (LED) (16,000 Lumens)		Each	=====	=====	=====
STM1151-038		SH115 MP 27 TO MP 38	04/21/22	11.00	1000.00	1037.23	950.00
	WEIGHTED AVERAGE FOR THE SECOND QUARTER			11.00	1000.00	1037.23	950.00
	WEIGHTED AVERAGE FOR THE YEAR			11.00	1000.00	1037.23	950.00
=====	613-13025	Lumin (LED) (25,000 Lumens)		Each	=====	=====	=====
NHPP0702-383		I-70 EB AUX FRISCO TO SILVERT	01/13/22	6.00	800.00	1906.87	1800.00
	WEIGHTED AVERAGE FOR THE FIRST QUARTER			6.00	800.00	1906.87	1800.00

COLORADO DEPARTMENT OF TRANSPORTATION
ITEM UNIT COSTS BY PROJECTS -- 2022 COST DATA

11:31 Wednesday, March 8, 2023 427

PROJECT NUMBER	ITEM NUMBER/ PROJECT LOCATION	ITEM DESCRIPTION/ PROJECT LOCATION	DATE LET	UNIT/ QUANTITY	ENGR. EST.	AVERAGE BID	AWARDED BID
=====	613-13025	Lumin (LED) (25,000 Lumens)		Each	=====		
2670703-479		I-70 BRIDGE OVER HARLAN	05/05/22	9.00	3500.00	1376.63	1620.75
		WEIGHTED AVERAGE FOR THE SECOND QUARTER		9.00	3500.00	1376.63	1620.75
		WEIGHTED AVERAGE FOR THE YEAR		15.00	2420.00	1566.00	1692.45
=====	613-13060	Lumin (LED) (1300 Lumin)		Each	=====		
TRG0253-264		I-25 AND SH 119 PARK-N-RIDE	10/27/22	18.00	950.00	1124.46	1200.00
		WEIGHTED AVERAGE FOR THE FOURTH QUARTER		18.00	950.00	1124.46	1200.00
		WEIGHTED AVERAGE FOR THE YEAR		18.00	950.00	1124.46	1200.00
=====	613-13065	Lumin (LED) (5400 Lumen)		Each	=====		
TRG0253-264		I-25 AND SH 119 PARK-N-RIDE	10/27/22	26.00	3000.00	3950.51	4200.00
		WEIGHTED AVERAGE FOR THE FOURTH QUARTER		26.00	3000.00	3950.51	4200.00
		WEIGHTED AVERAGE FOR THE YEAR		26.00	3000.00	3950.51	4200.00
=====	613-13100	Luminare Mounting Support System		LUMP SUM	=====		
NHPP 0761-238 C0761-239		I-76 DAHLIA TO YORK	03/10/22	1.00	50000.00	18833.47	8500.00
		WEIGHTED AVERAGE FOR THE FIRST QUARTER		1.00	50000.00	18833.47	8500.00
		WEIGHTED AVERAGE FOR THE YEAR		1.00	50000.00	18833.47	8500.00
=====	613-15000	Floodlight		Each	=====		
NHPP0253-275		I-25 EXPRESS LANES SEGMENT 5	03/11/22	24.00	1942.86	2314.70	2314.70
		WEIGHTED AVERAGE FOR THE FIRST QUARTER		24.00	1942.86	2314.70	2314.70

COLORADO DEPARTMENT OF TRANSPORTATION
 ITEM UNIT COSTS BY PROJECTS -- 2022 COST DATA

11:31 Wednesday, March 8, 2023 428

PROJECT NUMBER	ITEM NUMBER/ PROJECT LOCATION	ITEM DESCRIPTION/ PROJECT LOCATION	DATE LET	UNIT/ QUANTITY	ENGR. EST.	AVERAGE BID	AWARDED BID
=====	613-15000	Floodlight		Each	=====	=====	=====
IM025A-050		I25-MP103.9 - INTERSECTION DR	12/01/22	8.00	1500.00	1700.00	1500.00
		WEIGHTED AVERAGE FOR THE FOURTH QUARTER		8.00	1500.00	1700.00	1500.00
		WEIGHTED AVERAGE FOR THE YEAR		32.00	1832.15	2007.35	2111.03
=====	613-15050	Spot Light		Each	=====	=====	=====
NHPP0253-275		I-25 EXPRESS LANES SEGMENT 5	03/11/22	4.00	1942.86	2314.70	2314.70
		WEIGHTED AVERAGE FOR THE FIRST QUARTER		4.00	1942.86	2314.70	2314.70
		WEIGHTED AVERAGE FOR THE YEAR		4.00	1942.86	2314.70	2314.70
=====	613-20000	Inst Light Std + Lumin		Each	=====	=====	=====
NHM765-007			03/31/22	4.00	1000.00	2599.36	2337.00
		WEIGHTED AVERAGE FOR THE FIRST QUARTER		4.00	1000.00	2599.36	2337.00
		WEIGHTED AVERAGE FOR THE YEAR		4.00	1000.00	2599.36	2337.00
=====	613-20200	Inst Lumin		Each	=====	=====	=====
NHPP0063-054		US 6 FROM I70-B TO 33 RD. (MP	08/18/22	1.00	300.00	700.66	605.00
		WEIGHTED AVERAGE FOR THE THIRD QUARTER		1.00	300.00	700.66	605.00
		WEIGHTED AVERAGE FOR THE YEAR		1.00	300.00	700.66	605.00
=====	613-30005	Light Std + Lumin (Pedest)		Each	=====	=====	=====
STAM420-001 BR2854-148 STM0091-046		US 285 AT HWY 9C IMPROVEMENTS	12/01/22	21.00	6000.00	7137.50	7745.01
		INTERSECTION OF US 285 & SH 9					
		ADA RAMP IMPROVEMENTS - FAIRP					
		WEIGHTED AVERAGE FOR THE FOURTH QUARTER		21.00	6000.00	7137.50	7745.01
		WEIGHTED AVERAGE FOR THE YEAR		21.00	6000.00	7137.50	7745.01

COLORADO DEPARTMENT OF TRANSPORTATION
ITEM UNIT COSTS BY PROJECTS -- 2022 COST DATA

11:31 Wednesday, March 8, 2023 429

PROJECT NUMBER	ITEM NUMBER/ PROJECT LOCATION	ITEM DESCRIPTION/ PROJECT LOCATION	DATE LET	UNIT/ QUANTITY	ENGR. EST.	AVERAGE BID	AWARDED BID
=====	613-30300	Light Std Alum (30 Ft)		Each	=====	=====	=====
IM025A-050		I25-MP103.9 - INTERSECTION DR	12/01/22	15.00	2400.00	4466.67	4100.00
	WEIGHTED AVERAGE FOR THE FOURTH QUARTER			15.00	2400.00	4466.67	4100.00
	WEIGHTED AVERAGE FOR THE YEAR			15.00	2400.00	4466.67	4100.00
=====	613-32180	Light Std Steel (18 Ft)		Each	=====	=====	=====
2670403-065		US40_FLOYD HILL ROUNDABOUTS	09/15/22	7.00	5000.00	6422.12	5800.00
	WEIGHTED AVERAGE FOR THE THIRD QUARTER			7.00	5000.00	6422.12	5800.00
	WEIGHTED AVERAGE FOR THE YEAR			7.00	5000.00	6422.12	5800.00
=====	613-32300	Light Std Steel (30 Ft)		Each	=====	=====	=====
NHC540-017		R2 CHAINUP STA @ KENOSHA/HOOS	05/12/22	6.00	3000.00	8866.67	10100.00
	WEIGHTED AVERAGE FOR THE SECOND QUARTER			6.00	3000.00	8866.67	10100.00
NHPP0063-054		US 6 FROM I70-B TO 33 RD. (MP	08/18/22	29.00	6000.00	4498.20	3900.00
2670403-065		US40_FLOYD HILL ROUNDABOUTS	09/15/22	26.00	7000.00	7935.61	7200.00
	WEIGHTED AVERAGE FOR THE THIRD QUARTER			55.00	6472.73	6469.65	5460.00
STAM420-001		US 285 AT HWY 9C IMPROVEMENTS	12/01/22	35.00	3500.00	3950.39	4289.54
BR2854-148		INTERSECTION OF US 285 & SH 9					
STM0091-046		ADA RAMP IMPROVEMENTS - FAIRP					
	WEIGHTED AVERAGE FOR THE FOURTH QUARTER			35.00	3500.00	3950.39	4289.54
	WEIGHTED AVERAGE FOR THE YEAR			96.00	5171.88	5416.76	5323.27
=====	613-32350	Light Std Steel (35 Ft)		Each	=====	=====	=====
STU0252-457		I-25:ALAMEDA RIVER PH 2.0	11/03/22	7.00	10000.00	7938.66	7900.00
	WEIGHTED AVERAGE FOR THE FOURTH QUARTER			7.00	10000.00	7938.66	7900.00
	WEIGHTED AVERAGE FOR THE YEAR			7.00	10000.00	7938.66	7900.00

COLORADO DEPARTMENT OF TRANSPORTATION
ITEM UNIT COSTS BY PROJECTS -- 2022 COST DATA

11:31 Wednesday, March 8, 2023 430

PROJECT NUMBER	ITEM NUMBER/ PROJECT LOCATION	ITEM DESCRIPTION/ PROJECT LOCATION	DATE LET	UNIT/ QUANTITY	ENGR. EST.	AVERAGE BID	AWARDED BID
=====	613-34120	Light Std Metal (12 Ft)		Each	=====	=====	=====
TRG0253-264		I-25 AND SH 119 PARK-N-RIDE	10/27/22	26.00	1500.00	1904.23	2000.00
	WEIGHTED AVERAGE FOR THE FOURTH QUARTER			26.00	1500.00	1904.23	2000.00
	WEIGHTED AVERAGE FOR THE YEAR			26.00	1500.00	1904.23	2000.00
=====	613-34300	Light Std Metal (30 Ft)		Each	=====	=====	=====
TRG0253-264		I-25 AND SH 119 PARK-N-RIDE	10/27/22	6.00	1800.00	2812.50	3000.00
	WEIGHTED AVERAGE FOR THE FOURTH QUARTER			6.00	1800.00	2812.50	3000.00
	WEIGHTED AVERAGE FOR THE YEAR			6.00	1800.00	2812.50	3000.00
=====	613-34302	Light Std Metal (30 Ft) (2)		Each	=====	=====	=====
TRG0253-264		I-25 AND SH 119 PARK-N-RIDE	10/27/22	9.00	1900.00	2990.43	3200.00
	WEIGHTED AVERAGE FOR THE FOURTH QUARTER			9.00	1900.00	2990.43	3200.00
	WEIGHTED AVERAGE FOR THE YEAR			9.00	1900.00	2990.43	3200.00
=====	613-34303	Light Std Metal (30 Ft) (2) (Spec)		Each	=====	=====	=====
NHC540-017		R2 CHAINUP STA @ KENOSHA/HOOS	05/12/22	24.00	10000.00	11766.67	12300.00
	WEIGHTED AVERAGE FOR THE SECOND QUARTER			24.00	10000.00	11766.67	12300.00
	WEIGHTED AVERAGE FOR THE YEAR			24.00	10000.00	11766.67	12300.00
=====	613-34350	Light Std Metal (35 Ft)		Each	=====	=====	=====
NHM765-007			03/31/22	46.00	4500.00	4913.42	4417.50
	WEIGHTED AVERAGE FOR THE FIRST QUARTER			46.00	4500.00	4913.42	4417.50
	WEIGHTED AVERAGE FOR THE YEAR			46.00	4500.00	4913.42	4417.50
=====	613-34400	Light Std Metal (40 Ft)		Each	=====	=====	=====
NHPP0702-383		I-70 EB AUX FRISCO TO SILVERT	01/13/22	4.00	5000.00	6896.96	7000.00
	WEIGHTED AVERAGE FOR THE FIRST QUARTER			4.00	5000.00	6896.96	7000.00

COLORADO DEPARTMENT OF TRANSPORTATION
ITEM UNIT COSTS BY PROJECTS -- 2022 COST DATA

11:31 Wednesday, March 8, 2023 431

PROJECT NUMBER	ITEM NUMBER/ PROJECT LOCATION	ITEM DESCRIPTION/ PROJECT LOCATION	DATE LET	UNIT/ QUANTITY	ENGR. EST.	AVERAGE BID	AWARDED BID
=====	613-34400	Light Std Metal (40 Ft)		Each	=====		
STM1151-038		SH115 MP 27 TO MP 38	04/21/22	11.00	4200.00	4432.47	4100.00
		WEIGHTED AVERAGE FOR THE SECOND QUARTER		11.00	4200.00	4432.47	4100.00
TRG0253-264		I-25 AND SH 119 PARK-N-RIDE	10/27/22	15.00	2100.00	5106.39	5400.00
		WEIGHTED AVERAGE FOR THE FOURTH QUARTER		15.00	2100.00	5106.39	5400.00
		WEIGHTED AVERAGE FOR THE YEAR		30.00	3256.67	5099.95	5136.67
=====	613-40000	Conc Foundation Pad		Each	=====		
NHPP0702-383		I-70 EB AUX FRISCO TO SILVERT	01/13/22	1.00	5600.00	4075.79	3800.00
NHPP0253-275		I-25 EXPRESS LANES SEGMENT 5	03/11/22	2.00	3157.15	3275.52	3275.52
		WEIGHTED AVERAGE FOR THE FIRST QUARTER		3.00	3971.43	3847.14	3450.35
2670703-479		I-70 BRIDGE OVER HARLAN	05/05/22	2.00	5000.00	361.65	425.48
ER0702-420		PR I-70 GWC MATERIAL FLOWS 20	05/06/22	6.00	3000.00	19875.00	19000.00
NHC540-017		R2 CHAINUP STA @ KENOSHA/HOOS	05/12/22	2.00	2500.00	2483.33	700.00
		WEIGHTED AVERAGE FOR THE SECOND QUARTER		10.00	3300.00	8591.33	11625.10
NHPP0063-054		US 6 FROM I70-B TO 33 RD. (MP	08/18/22	1.00	8000.00	4238.94	3700.00
2670403-065		US40_FLOYD HILL ROUNDABOUTS	09/15/22	2.00	3500.00	6805.58	6200.00
		WEIGHTED AVERAGE FOR THE THIRD QUARTER		3.00	5000.00	6163.92	5366.67
TRG0253-264		I-25 AND SH 119 PARK-N-RIDE	10/27/22	2.00	2800.00	600.82	800.00
IM025A-050		I25-MP103.9 - INTERSECTION DR	12/01/22	1.00	700.00	1775.00	2500.00

COLORADO DEPARTMENT OF TRANSPORTATION
 ITEM UNIT COSTS BY PROJECTS -- 2022 COST DATA

11:31 Wednesday, March 8, 2023 432

PROJECT NUMBER	ITEM NUMBER/ PROJECT LOCATION	ITEM DESCRIPTION/ PROJECT LOCATION	DATE LET	UNIT/ QUANTITY	ENGR. EST.	AVERAGE BID	AWARDED BID
=====	613-40000	Conc Foundation Pad		Each =====			
NHPP0063-048		US6 / 20 ROAD INTERSECTION IM	12/15/22	1.00	3500.00	5176.58	3300.00
		WEIGHTED AVERAGE FOR THE FOURTH QUARTER		4.00	2450.00	1549.76	1850.00
		WEIGHTED AVERAGE FOR THE YEAR		20.00	3485.72	5435.67	7505.10
=====	613-40010	Light Std Foundation		Each =====			
NHPP0702-383		I-70 EB AUX FRISCO TO SILVERT	01/13/22	6.00	3000.00	4981.37	4500.00
NHPP0063-063			02/24/22	59.00	1700.00	1145.00	1200.00
NHPP0253-275		I-25 EXPRESS LANES SEGMENT 5	03/11/22	32.00	624.49	620.17	620.17
NHM765-007			03/31/22	50.00	2500.00	5103.62	4588.50
		WEIGHTED AVERAGE FOR THE FIRST QUARTER		147.00	1791.05	3242.24	2361.02
STM1151-038		SH115 MP 27 TO MP 38	04/21/22	11.00	1600.00	6013.88	6250.00
2670703-479		I-70 BRIDGE OVER HARLAN	05/05/22	1.00	3000.00	2470.58	2914.21
NHC540-017		R2 CHAINUP STA @ KENOSHA/HOOS	05/12/22	30.00	3000.00	4116.67	3850.00
		WEIGHTED AVERAGE FOR THE SECOND QUARTER		42.00	2633.33	4742.30	4456.29
NHPP0063-054		US 6 FROM I70-B TO 33 RD. (MP	08/18/22	29.00	2500.00	2842.62	2500.00
2670403-065		US40_FLOYD HILL ROUNDABOUTS	09/15/22	26.00	4000.00	7554.20	7000.00
		WEIGHTED AVERAGE FOR THE THIRD QUARTER		55.00	3209.09	5544.85	4627.27
TRG0253-264		I-25 AND SH 119 PARK-N-RIDE	10/27/22	30.00	2600.00	3878.84	4100.00
STU0252-457		I-25:ALAMEDA RIVER PH 2.0	11/03/22	7.00	2000.00	5624.61	5600.00
STAM420-001		US 285 AT HWY 9C IMPROVEMENTS	12/01/22	56.00	6000.00	9344.75	9500.00
BR2854-148		INTERSECTION OF US 285 & SH 9					
STM0091-046		ADA RAMP IMPROVEMENTS - FAIRP					
IM025A-050		I25-MP103.9 - INTERSECTION DR	12/01/22	17.00	2500.00	2333.33	3100.00
		WEIGHTED AVERAGE FOR THE FOURTH QUARTER		110.00	4277.27	6084.44	6790.00
		WEIGHTED AVERAGE FOR THE YEAR		354.00	2883.85	5031.56	4337.95
=====	613-40012	Light Std Foundation Spec		Each =====			
2670703-479		I-70 BRIDGE OVER HARLAN	05/05/22	8.00	5000.00	1867.58	2195.47
		WEIGHTED AVERAGE FOR THE SECOND QUARTER		8.00	5000.00	1867.58	2195.47

COLORADO DEPARTMENT OF TRANSPORTATION
ITEM UNIT COSTS BY PROJECTS -- 2022 COST DATA

11:31 Wednesday, March 8, 2023 433

PROJECT NUMBER	ITEM NUMBER/ PROJECT LOCATION	ITEM DESCRIPTION/ PROJECT LOCATION	DATE LET	UNIT/ QUANTITY	ENGR. EST.	AVERAGE BID	AWARDED BID
=====	613-40012	Light Std Foundation Spec		Each	=====	=====	=====
2670403-065		US40_FLOYD HILL ROUNDABOUTS	09/15/22	7.00	6000.00	8136.53	7600.00
		WEIGHTED AVERAGE FOR THE THIRD QUARTER		7.00	6000.00	8136.53	7600.00
TRG0253-264		I-25 AND SH 119 PARK-N-RIDE	10/27/22	26.00	2200.00	3051.60	3500.00
		WEIGHTED AVERAGE FOR THE FOURTH QUARTER		26.00	2200.00	3051.60	3500.00
		WEIGHTED AVERAGE FOR THE YEAR		41.00	3395.12	3231.92	3945.46
=====	613-40020	Transformer Base Alum		Each	=====	=====	=====
NHC540-017		R2 CHAINUP STA @ KENOSHA/HOOS	05/12/22	30.00	700.00	1200.00	1100.00
		WEIGHTED AVERAGE FOR THE SECOND QUARTER		30.00	700.00	1200.00	1100.00
STA3852-015 IM025A-050		US 385 HOLYOKE NORTH	10/27/22	2.00	2500.00	2000.00	2000.00
		I25-MP103.9 - INTERSECTION DR	12/01/22	13.00	700.00	933.33	1100.00
		WEIGHTED AVERAGE FOR THE FOURTH QUARTER		15.00	940.00	985.37	1220.00
		WEIGHTED AVERAGE FOR THE YEAR		45.00	780.00	1132.82	1140.00
=====	613-50010	Photoel Cell		Each	=====	=====	=====
STU0252-457		I-25:ALAMEDA RIVER PH 2.0	11/03/22	1.00	1000.00	1136.85	1200.00
		WEIGHTED AVERAGE FOR THE FOURTH QUARTER		1.00	1000.00	1136.85	1200.00
		WEIGHTED AVERAGE FOR THE YEAR		1.00	1000.00	1136.85	1200.00
=====	613-50100	Lighting Ctrl Center		Each	=====	=====	=====
NHPP 0761-238		I-76 DAHLIA TO YORK	03/10/22	1.00	9000.00	12816.88	7300.00

COLORADO DEPARTMENT OF TRANSPORTATION
 ITEM UNIT COSTS BY PROJECTS -- 2022 COST DATA

11:31 Wednesday, March 8, 2023 434

PROJECT NUMBER	ITEM NUMBER/ PROJECT LOCATION	ITEM DESCRIPTION/ PROJECT LOCATION	DATE LET	UNIT/ QUANTITY	ENGR. EST.	AVERAGE BID	AWARDED BID
===== 613-50100 C0761-239		Lighting Ctrl Center		Each =====			
	WEIGHTED AVERAGE FOR THE FIRST QUARTER			1.00	9000.00	12816.88	7300.00
STM1151-038		SH115 MP 27 TO MP 38	04/21/22	1.00	9200.00	10730.04	11000.00
	WEIGHTED AVERAGE FOR THE SECOND QUARTER			1.00	9200.00	10730.04	11000.00
NHPP0063-054 2670403-065		US 6 FROM I70-B TO 33 RD. (MP 08/18/22 US40_FLOYD HILL ROUNDABOUTS 09/15/22		1.00 2.00	12000.00 8500.00	12268.64 21676.24	11000.00 18500.00
	WEIGHTED AVERAGE FOR THE THIRD QUARTER			3.00	9666.67	19324.34	16000.00
TRG0253-264 STAM420-001 BR2854-148 STM0091-046		I-25 AND SH 119 PARK-N-RIDE 10/27/22 US 285 AT HWY 9C IMPROVEMENTS 12/01/22 INTERSECTION OF US 285 & SH 9 ADA RAMP IMPROVEMENTS - FAIRP		1.00 1.00	38000.00 12700.99	46599.41 20607.22	50000.00 22341.37
	WEIGHTED AVERAGE FOR THE FOURTH QUARTER			2.00	25350.50	37935.35	36170.69
	WEIGHTED AVERAGE FOR THE YEAR			7.00	13985.86	23212.25	19805.91
===== 613-50105		Lighting Ctrl Center (Pedestal Only)		Each =====			
TRG0253-264 NHPP0063-048		I-25 AND SH 119 PARK-N-RIDE 10/27/22 US6 / 20 ROAD INTERSECTION IM 12/15/22		1.00 1.00	25000.00 10000.00	13888.92 12705.57	14500.00 8500.00
	WEIGHTED AVERAGE FOR THE FOURTH QUARTER			2.00	17500.00	13494.47	11500.00
	WEIGHTED AVERAGE FOR THE YEAR			2.00	17500.00	13494.47	11500.00
===== 613-50106		Light Cont Center (Spec)		Each =====			
NHC540-017		R2 CHAINUP STA @ KENOSHA/HOOS 05/12/22		2.00	12000.00	9900.00	7700.00
	WEIGHTED AVERAGE FOR THE SECOND QUARTER			2.00	12000.00	9900.00	7700.00

COLORADO DEPARTMENT OF TRANSPORTATION
ITEM UNIT COSTS BY PROJECTS -- 2022 COST DATA

11:31 Wednesday, March 8, 2023 435

PROJECT NUMBER	ITEM NUMBER/ PROJECT LOCATION	ITEM DESCRIPTION/ PROJECT LOCATION	DATE LET	UNIT/ QUANTITY	ENGR. EST.	AVERAGE BID	AWARDED BID
=====	613-50106	Light Cont Center (Spec)		Each	=====	=====	=====
IM025A-050		I25-MP103.9 - INTERSECTION DR	12/01/22	1.00	8000.00	16400.00	21200.00
		WEIGHTED AVERAGE FOR THE FOURTH QUARTER		1.00	8000.00	16400.00	21200.00
		WEIGHTED AVERAGE FOR THE YEAR		3.00	10666.67	12066.67	12200.00
=====	613-50109	Meter Power Pedestal		Each	=====	=====	=====
NHPP0253-275		I-25 EXPRESS LANES SEGMENT 5	03/11/22	2.00	12480.61	14098.89	14098.89
		WEIGHTED AVERAGE FOR THE FIRST QUARTER		2.00	12480.61	14098.89	14098.89
STM1151-038		SH115 MP 27 TO MP 38	04/21/22	4.00	8000.00	10190.04	11000.00
2670703-479		I-70 BRIDGE OVER HARLAN	05/05/22	2.00	4000.00	8116.62	9496.69
NHC540-017		R2 CHAINUP STA @ KENOSHA/HOOS	05/12/22	1.00	8000.00	11000.00	11000.00
		WEIGHTED AVERAGE FOR THE SECOND QUARTER		7.00	6857.14	9548.58	10570.48
NHPP0063-054		US 6 FROM I70-B TO 33 RD. (MP	08/18/22	1.00	7000.00	9126.02	7900.00
		WEIGHTED AVERAGE FOR THE THIRD QUARTER		1.00	7000.00	9126.02	7900.00
STAM420-001		US 285 AT HWY 9C IMPROVEMENTS	12/01/22	1.00	6000.00	12639.43	13702.71
BR2854-148		INTERSECTION OF US 285 & SH 9					
STM0091-046		ADA RAMP IMPROVEMENTS - FAIRP					
		WEIGHTED AVERAGE FOR THE FOURTH QUARTER		1.00	6000.00	12639.43	13702.71
		WEIGHTED AVERAGE FOR THE YEAR		11.00	7814.66	10028.09	11253.99
=====	613-50132	2-Plex Recept. (W/Box & Cover)		Each	=====	=====	=====
NHPP0253-275		I-25 EXPRESS LANES SEGMENT 5	03/11/22	12.00	838.78	824.34	824.34
		WEIGHTED AVERAGE FOR THE FIRST QUARTER		12.00	838.78	824.34	824.34
		WEIGHTED AVERAGE FOR THE YEAR		12.00	838.78	824.34	824.34

COLORADO DEPARTMENT OF TRANSPORTATION
 ITEM UNIT COSTS BY PROJECTS -- 2022 COST DATA

11:31 Wednesday, March 8, 2023 436

PROJECT NUMBER	ITEM NUMBER/ PROJECT LOCATION	ITEM DESCRIPTION/ PROJECT LOCATION	DATE LET	UNIT/ QUANTITY	ENGR. EST.	AVERAGE BID	AWARDED BID
=====	613-50150	Secondary Serv Pedestal		Each	=====	=====	=====
FSAM240-200		SH21B CO SPRINGS SIGNAL REPLA	10/27/22	3.00	4000.00	7853.75	6195.00
STU0252-457		I-25:ALAMEDA RIVER PH 2.0	11/03/22	1.00	10000.00	12245.71	12200.00
STRC090-011		US 50B AND SH71/CR18 INTERSEC	11/17/22	1.00	8875.00	9562.50	6625.00
		WEIGHTED AVERAGE FOR THE FOURTH QUARTER		5.00	6175.00	8829.83	7482.00
		WEIGHTED AVERAGE FOR THE YEAR		5.00	6175.00	8829.83	7482.00
=====	613-50210	Temporary Lighting		LUMP SUM	=====	=====	=====
C0762-055			02/17/22	1.00	125000.00	58186.61	32000.00
		WEIGHTED AVERAGE FOR THE FIRST QUARTER		1.00	125000.00	58186.61	32000.00
		WEIGHTED AVERAGE FOR THE YEAR		1.00	125000.00	58186.61	32000.00
=====	613-50350	Power Transformer		LUMP SUM	=====	=====	=====
NHC540-017		R2 CHAINUP STA @ KENOSHA/HOOS	05/12/22	1.00	6000.00	3633.33	2900.00
		WEIGHTED AVERAGE FOR THE SECOND QUARTER		1.00	6000.00	3633.33	2900.00
		WEIGHTED AVERAGE FOR THE YEAR		1.00	6000.00	3633.33	2900.00
=====	613-50365	Transformer Base		Each	=====	=====	=====
TRG0253-264		I-25 AND SH 119 PARK-N-RIDE	10/27/22	15.00	400.00	445.21	500.00
		WEIGHTED AVERAGE FOR THE FOURTH QUARTER		15.00	400.00	445.21	500.00
		WEIGHTED AVERAGE FOR THE YEAR		15.00	400.00	445.21	500.00
=====	613-60700	Troubleshooting		Hour	=====	=====	=====
ITS0703-477		ITS EQUIPMENT UPGRADE AT EJMT	01/06/22	100.00	135.00	330.00	330.00
		WEIGHTED AVERAGE FOR THE FIRST QUARTER		100.00	135.00	330.00	330.00
ITS 0741-024		VMS SIGN INSTALLATIONS AND VS	06/02/22	60.00	150.00	197.50	175.00
		WEIGHTED AVERAGE FOR THE SECOND QUARTER		60.00	150.00	197.50	175.00
		WEIGHTED AVERAGE FOR THE YEAR		160.00	140.63	257.73	271.88

COLORADO DEPARTMENT OF TRANSPORTATION
 ITEM UNIT COSTS BY PROJECTS -- 2022 COST DATA

11:31 Wednesday, March 8, 2023 437

PROJECT NUMBER	ITEM NUMBER/ PROJECT LOCATION	ITEM DESCRIPTION/ PROJECT LOCATION	DATE LET	UNIT/ QUANTITY	ENGR. EST.	AVERAGE BID	AWARDED BID
=====	613-70400	Lumin HPS (400 W)		Each	=====	=====	=====
STU0252-457		I-25:ALAMEDA RIVER PH 2.0	11/03/22	4.00	1500.00	5517.59	5500.00
		WEIGHTED AVERAGE FOR THE FOURTH QUARTER		4.00	1500.00	5517.59	5500.00
		WEIGHTED AVERAGE FOR THE YEAR		4.00	1500.00	5517.59	5500.00
=====	613-80010	Ballast Un		Each	=====	=====	=====
NHPP0253-275		I-25 EXPRESS LANES SEGMENT 5	03/11/22	2.00	2653.06	2798.39	2798.39
		WEIGHTED AVERAGE FOR THE FIRST QUARTER		2.00	2653.06	2798.39	2798.39
		WEIGHTED AVERAGE FOR THE YEAR		2.00	2653.06	2798.39	2798.39
=====	613-80130	Service Meter Cabinet		Each	=====	=====	=====
STM1151-038		SH115 MP 27 TO MP 38	04/21/22	3.00	6500.00	11250.04	11000.00
ITS 0741-024		VMS SIGN INSTALLATIONS AND VS	06/02/22	3.00	4000.00	7957.00	6900.00
		WEIGHTED AVERAGE FOR THE SECOND QUARTER		6.00	5250.00	10309.17	8950.00
C1211-099		SH 121 NORTH SGA SIGNALS	08/25/22	2.00	8000.00	8500.00	8500.00
SHE2873-193		US 287 & CO 52 INTERSECTION I	09/15/22	1.00	1500.00	9576.80	8700.00
		WEIGHTED AVERAGE FOR THE THIRD QUARTER		3.00	5833.33	9146.08	8566.67
STAM420-001		US 285 AT HWY 9C IMPROVEMENTS	12/01/22	3.00	6000.00	12639.43	13702.71
BR2854-148		INTERSECTION OF US 285 & SH 9					
STM0091-046		ADA RAMP IMPROVEMENTS - FAIRP					
NHPP0931-033		SH93:US6 TO 58TH RESURFACING	12/15/22	1.00	5000.00	11815.28	10100.00
		WEIGHTED AVERAGE FOR THE FOURTH QUARTER		4.00	5750.00	12433.39	12802.03
		WEIGHTED AVERAGE FOR THE YEAR		13.00	5538.46	10784.84	10046.78
=====	613-81690	Safety Switch		Each	=====	=====	=====
NHPP0702-383		I-70 EB AUX FRISCO TO SILVERT	01/13/22	2.00	5000.00	6663.87	4900.00
		WEIGHTED AVERAGE FOR THE FIRST QUARTER		2.00	5000.00	6663.87	4900.00

COLORADO DEPARTMENT OF TRANSPORTATION
ITEM UNIT COSTS BY PROJECTS -- 2022 COST DATA

11:31 Wednesday, March 8, 2023 438

PROJECT NUMBER	ITEM NUMBER/ PROJECT LOCATION	ITEM DESCRIPTION/ PROJECT LOCATION	DATE LET	UNIT/ QUANTITY	ENGR. EST.	AVERAGE BID	AWARDED BID
=====	613-81690	Safety Switch		Each	=====	=====	=====
NHC540-017		R2 CHAINUP STA @ KENOSHA/HOOS	05/12/22	4.00	980.00	641.00	423.00
		WEIGHTED AVERAGE FOR THE SECOND QUARTER		4.00	980.00	641.00	423.00
		WEIGHTED AVERAGE FOR THE YEAR		6.00	2320.00	3378.67	1915.33
=====	613-81699	Safe Switch NEMA 3R, 30A, 2-pole, 240 V		Each	=====	=====	=====
NHC540-017		R2 CHAINUP STA @ KENOSHA/HOOS	05/12/22	6.00	1000.00	1258.33	775.00
		WEIGHTED AVERAGE FOR THE SECOND QUARTER		6.00	1000.00	1258.33	775.00
		WEIGHTED AVERAGE FOR THE YEAR		6.00	1000.00	1258.33	775.00
=====	613-81700	Safe Switch NEMA 3R 60A 2 Pole 240V		Each	=====	=====	=====
NHC540-017		R2 CHAINUP STA @ KENOSHA/HOOS	05/12/22	1.00	1000.00	1966.67	1400.00
		WEIGHTED AVERAGE FOR THE SECOND QUARTER		1.00	1000.00	1966.67	1400.00
		WEIGHTED AVERAGE FOR THE YEAR		1.00	1000.00	1966.67	1400.00
=====	614-00011	Sign Panel (CL I)		Sq Foot	=====	=====	=====
NHPP2873-189		US 287 (FEDERAL BLVD) - COLFA	01/06/22	179.00	35.00	26.73	27.28
NHPP0702-383		I-70 EB AUX FRISCO TO SILVERT	01/13/22	165.00	24.00	31.31	27.00
NHPP1601-083			02/03/22	44.00	32.00	90.53	25.00
C0762-055			02/17/22	324.00	35.00	24.58	30.00
NHPP0063-063			02/24/22	852.00	18.00	24.10	25.00
STA 067A-048		Hwy 67A MP 0.00 TO MP 11.05 I	03/03/22	60.00	20.00	22.20	24.00
NHPP 0761-238		I-76 DAHLIA TO YORK	03/10/22	51.00	34.00	41.45	31.00
C0761-239							
NHPP0703-472			03/10/22	38.25	24.00	27.87	30.00
ER007A-035			03/15/22	695.00	28.56	30.65	30.65
NHM765-007			03/31/22	282.00	21.00	26.86	23.94
		WEIGHTED AVERAGE FOR THE FIRST QUARTER		2,690.25	25.25	28.22	27.39
NH0504-911			04/07/22	25.38	23.21	25.05	25.10

PROJECT NUMBER	ITEM NUMBER/ PROJECT LOCATION	ITEM DESCRIPTION/ PROJECT LOCATION	DATE LET	UNIT/ QUANTITY	ENGR. EST.	AVERAGE BID	AWARDED BID
=====	614-00011	Sign Panel (CL I)		Sq Foot	=====	=====	=====
NHPP0702-413		VAIL PASS AUX PHASE 1 CAP 2	04/18/22	36.00	23.54	23.54	23.54
STM1151-038		SH115 MP 27 TO MP 38	04/21/22	66.00	25.00	22.75	21.00
2670703-479		I-70 BRIDGE OVER HARLAN	05/05/22	171.00	26.00	26.03	30.11
STA0712-019		SH 71: Frieght Improvements	05/12/22	45.00	35.00	31.05	31.05
NHC540-017		R2 CHAINUP STA @ KENOSHA/HOOS	05/12/22	15.00	25.00	40.67	30.00
CM760-047		COLFAX AND QUAIL	05/12/22	52.00	26.00	39.00	30.00
NHPP 3851-018		US 385 NORTH OF CHEYENNE WELL	05/26/22	549.00	28.00	26.00	27.00
FSA3921-019		SH 392 AND WCR 55 ISLANDS	06/02/22	9.00	33.00	30.00	21.00
NHPP072A-047		SH-72 RESURFACING: I-70 TO IN	06/09/22	773.00	24.00	29.00	29.00
FSA052A-046		SH52 WCR 37 INTERSECTION IMPR	06/09/22	75.40	30.00	26.17	25.00
MTCE0253-291		I-25 SIGN REPLACEMENT PHASE 2	06/16/22	427.00	50.00	30.17	37.33
		WEIGHTED AVERAGE FOR THE SECOND QUARTER		2,243.78	30.60	27.86	29.72
NHPP0702-414		VAIL PASS AUX PHASE 1 CAP 3	07/08/22	17.00	27.29	27.29	27.29
FBR0702-423		VAIL PASS AUX BE F-12-AT PHAS					
NHPP0063-054		US 6 FROM I70-B TO 33 RD. (MP	08/18/22	650.00	22.00	28.55	31.00
FBR0761-236		I-76 OVER CLR CRK SCOUR MIT	08/25/22	28.00	28.00	68.33	50.00
C1211-099		SH 121 NORTH SGA SIGNALS	08/25/22	545.00	30.00	43.50	52.00
2670403-065		US40 FLOYD HILL ROUNDABOUTS	09/15/22	421.00	25.00	24.77	24.00
SHE2873-193		US 287 & CO 52 INTERSECTION I	09/15/22	90.00	50.00	37.99	34.24
		WEIGHTED AVERAGE FOR THE THIRD QUARTER		1,751.00	26.80	33.19	36.29
C0831-126		SH83 EL PASO COUNTY TO BAYOU	10/13/22	689.00	35.00	23.00	24.00
FSAM240-200		SH21B CO SPRINGS SIGNAL REPLA	10/27/22	208.00	23.00	58.19	27.75
TRG0253-264		I-25 AND SH 119 PARK-N-RIDE	10/27/22	170.00	24.00	28.15	28.00
STA3852-015		US 385 HOLYOKE NORTH	10/27/22	120.00	30.00	27.00	27.00
STU0252-457		I-25:ALAMEDA RIVER PH 2.0	11/03/22	145.00	50.00	29.08	30.00
NHPP0853-126		US85C: PLATTEVILLE NORTH MP (11/10/22	15.00	50.00	25.40	25.00
C5502-097		US550 MP 117.28-126.06	11/17/22	263.00	35.00	28.18	25.90
MPR200-280		PUEBLO AREA	11/17/22	923.00	21.20	22.00	22.00
STRC090-011		US 50B AND SH71/CR18 INTERSEC	11/17/22	23.00	27.00	29.00	33.00
STAM420-001		US 285 AT HWY 9C IMPROVEMENTS	12/01/22	286.00	24.00	30.95	47.21
BR2854-148		INTERSECTION OF US 285 & SH 9					
STM0091-046		ADA RAMP IMPROVEMENTS - FAIRP					
STR114A-015		SH114 SILLSVILLE SOUTH TO MP3	12/01/22	255.00	25.00	27.50	30.00
2670703-487		I-70 BRIDGES OVER WARD ROAD-	12/01/22	17.00	80.00	36.00	42.00
IM025A-050		I25-MP103.9 - INTERSECTION DR	12/01/22	155.00	23.00	27.00	27.00
NHPP0021-041		SH2 RESURFACING MLK TO 52ND	12/01/22	54.00	35.00	39.40	35.40
NHPP083A-046		SH83 RESURFACING STROH RD TO	12/08/22	161.00	25.00	36.74	42.47
NHPP0063-048		US6 / 20 ROAD INTERSECTION IM	12/15/22	101.00	35.00	34.34	24.00

PROJECT NUMBER	ITEM NUMBER/ PROJECT LOCATION	ITEM DESCRIPTION/ PROJECT LOCATION	DATE LET	UNIT/ QUANTITY	ENGR. EST.	AVERAGE BID	AWARDED BID
===== 614-00011 Sign Panel (CL I) Sq Foot =====							
NHPP0931-033		SH93:US6 TO 58TH RESURFACING	12/15/22	272.00	25.00	39.76	26.65
NHPP0502-090		SH 50 MP 134.6-136 GUNNISON C	12/22/22	186.00	50.00	34.82	34.15
STR0092-024		SH 9 North of Silverthorne	12/22/22	21.00	50.00	28.50	27.00
STA0361-129		US 36: HYGIENE RD AND NELSON	12/22/22	63.00	50.00	32.64	42.90
STA385A-016		SH 385 MP 97.76	12/22/22	34.00	30.00	35.70	27.78
STR096A-050		SH 96 MP 168.99 TO 193.77	12/22/22	438.00	21.00	28.00	26.00
WEIGHTED AVERAGE FOR THE FOURTH QUARTER				4,599.00	28.72	30.93	28.11
WEIGHTED AVERAGE FOR THE YEAR				11,284.03	27.97	30.13	29.53
===== 614-00012 Sign Panel (CL II) Sq Foot =====							
NHPP2873-189		US 287 (FEDERAL BLVD) - COLFA	01/06/22	240.00	45.00	36.29	39.69
NHPP0702-383		I-70 EB AUX FRISCO TO SILVERT	01/13/22	657.00	26.00	37.60	34.00
NHPP1601-083			02/03/22	241.00	20.00	49.72	29.00
STA0252-459			02/03/22	372.00	27.00	30.70	26.00
C0762-055			02/17/22	541.00	30.00	27.43	33.00
STR0141-031			02/17/22	61.25	28.00	31.00	30.00
STA 067A-048		Hwy 67A MP 0.00 TO MP 11.05 I	03/03/22	1,220.71	25.00	28.68	30.00
NHPP 0761-238		I-76 DAHLIA TO YORK	03/10/22	248.00	36.00	43.35	33.00
C0761-239							
NHPP0703-472			03/10/22	70.00	26.00	33.05	35.00
ER007A-035			03/15/22	150.00	36.72	39.35	39.35
NHM765-007			03/31/22	361.00	23.00	32.52	28.50
WEIGHTED AVERAGE FOR THE FIRST QUARTER				4,161.96	27.82	34.07	31.63
NH0504-911			04/07/22	259.75	26.29	28.85	28.70
STM1151-038		SH115 MP 27 TO MP 38	04/21/22	1,533.00	27.00	25.92	24.00
2670703-479		I-70 BRIDGE OVER HARLAN	05/05/22	306.00	28.00	33.28	39.27
STA0712-019		SH 71: Frieight Improvements	05/12/22	142.00	30.00	34.16	34.16
NHC540-017		R2 CHAINUP STA @ KENOSHA/HOOS	05/12/22	287.00	27.00	47.00	34.00
NHPP 3851-018		US 385 NORTH OF CHEYENNE WELL	05/26/22	498.00	30.00	31.50	33.00
NHPP072A-047		SH-72 RESURFACING: I-70 TO IN	06/09/22	715.00	27.00	35.04	35.04
FSA052A-046		SH52 WCR 37 INTERSECTION IMPR	06/09/22	122.00	32.00	36.24	27.00
MTCE0253-291		I-25 SIGN REPLACEMENT PHASE 2	06/16/22	1,625.00	45.00	40.61	44.21
WEIGHTED AVERAGE FOR THE SECOND QUARTER				5,487.75	32.81	31.97	34.17
NHPP0702-414		VAIL PASS AUX PHASE 1 CAP 3	07/08/22	39.00	32.74	32.74	32.74

COLORADO DEPARTMENT OF TRANSPORTATION
ITEM UNIT COSTS BY PROJECTS -- 2022 COST DATA

11:31 Wednesday, March 8, 2023 441

PROJECT NUMBER	ITEM NUMBER/ PROJECT LOCATION	ITEM DESCRIPTION/ PROJECT LOCATION	DATE LET	UNIT/ QUANTITY	ENGR. EST.	AVERAGE BID	AWARDED BID
===== 614-00012 Sign Panel (CL II) Sq Foot =====							
FBR0702-423		VAIL PASS AUX BE F-12-AT PHAS					
FSA052A-057		SH52 BOX CULVERT EXTENSION (M	08/04/22	60.00	35.00	29.05	28.41
NHPP0063-054		US 6 FROM I70-B TO 33 RD. (MP	08/18/22	105.00	25.00	33.18	37.00
C1211-099		SH 121 NORTH SGA SIGNALS	08/25/22	126.00	35.00	48.00	61.00
2670403-065		US40 FLOYD HILL ROUNDABOUTS	09/15/22	9.00	40.00	31.48	31.00
SHE2873-193		US 287 & CO 52 INTERSECTION I	09/15/22	96.00	40.00	43.84	41.73
WEIGHTED AVERAGE FOR THE THIRD QUARTER				435.00	33.59	40.24	43.30
C0831-126		SH83 EL PASO COUNTY TO BAYOU	10/13/22	2,055.00	32.00	27.00	28.00
TRG0253-264		I-25 AND SH 119 PARK-N-RIDE	10/27/22	286.00	26.00	31.93	33.00
STA3852-015		US 385 HOLYOKE NORTH	10/27/22	45.00	35.00	29.00	29.00
STU0252-457		I-25:ALAMEDA RIVER PH 2.0	11/03/22	107.00	70.00	37.95	40.50
SHE0242-087		US 24 SAFETY IMPRVMENTS, E OF	11/03/22	3.00	27.00	30.29	29.86
NHPP0853-126		US85C: PLATTEVILLE NORTH MP (11/10/22	38.00	40.00	31.82	31.00
C5502-097		US550 MP 117.28-126.06	11/17/22	264.00	40.00	32.72	28.60
MPR200-280		PUEBLO AREA	11/17/22	5,086.00	26.20	28.00	28.00
STRC090-011		US 50B AND SH71/CR18 INTERSEC	11/17/22	37.00	35.00	34.50	37.00
STAM420-001		US 285 AT HWY 9C IMPROVEMENTS	12/01/22	501.00	27.00	37.20	54.29
BR2854-148		INTERSECTION OF US 285 & SH 9					
STM0091-046		ADA RAMP IMPROVEMENTS - FAIRP					
STA0711-021		SH71: REGION LINE NORTH	12/01/22	132.00	27.00	29.25	32.00
STR114A-015		SH114 SILLSVILLE SOUTH TO MP3	12/01/22	380.00	30.00	32.00	35.00
2670703-487		I-70 BRIDGES OVER WARD ROAD-	12/01/22	178.00	60.00	33.06	34.00
IM025A-050		I25-MP103.9 - INTERSECTION DR	12/01/22	294.00	28.00	29.33	30.00
NHPP0021-041		SH2 RESURFACING MLK TO 52ND	12/01/22	160.00	40.00	46.84	43.40
NHPP083A-046		SH83 RESURFACING STROH RD TO	12/08/22	286.00	30.00	47.86	43.72
NHPP0063-048		US6 / 20 ROAD INTERSECTION IM	12/15/22	140.00	40.00	40.88	28.00
NHPP0931-033		SH93:US6 TO 58TH RESURFACING	12/15/22	767.00	40.00	43.60	36.90
NHPP0502-090		SH 50 MP 134.6-136 GUNNISON C	12/22/22	20.00	55.00	39.05	36.99
STR0092-024		SH 9 North of Silverthorne	12/22/22	63.00	60.00	31.90	30.20
STA0361-129		US 36: HYGIENE RD AND NELSON	12/22/22	84.00	30.00	40.84	49.34
STR096A-050		SH 96 MP 168.99 TO 193.77	12/22/22	950.00	28.00	33.33	30.00
WEIGHTED AVERAGE FOR THE FOURTH QUARTER				11,876.00	30.45	32.56	31.29
WEIGHTED AVERAGE FOR THE YEAR				21,960.71	30.60	32.92	32.31
===== 614-00013 Sign Panel (CL III) Sq Foot =====							
NHPP0702-383		I-70 EB AUX FRISCO TO SILVERT	01/13/22	1,087.00	33.00	53.54	52.00
C0762-055			02/17/22	1,066.00	35.00	38.16	36.00
NHPP 0761-238		I-76 DAHLIA TO YORK	03/10/22	563.00	38.00	43.67	34.00

COLORADO DEPARTMENT OF TRANSPORTATION
 ITEM UNIT COSTS BY PROJECTS -- 2022 COST DATA

11:31 Wednesday, March 8, 2023 442

PROJECT NUMBER	ITEM NUMBER/ PROJECT LOCATION	ITEM DESCRIPTION/ PROJECT LOCATION	DATE LET	UNIT/ QUANTITY	ENGR. EST.	AVERAGE BID	AWARDED BID
=====	614-00013	Sign Panel (CL III)		Sq Foot	=====		
C0761-239							
	WEIGHTED AVERAGE FOR THE FIRST	QUARTER		2,716.00	34.82	45.79	41.99
NH0504-911			04/07/22	212.75	36.11	48.75	47.50
STM1151-038	SH115 MP 27 TO MP 38		04/21/22	132.00	43.00	35.81	33.00
2670703-479	I-70 BRIDGE OVER HARLAN		05/05/22	506.00	32.00	34.49	40.50
NHC540-017	R2 CHAINUP STA @ KENOSHA/HOOS		05/12/22	120.00	36.00	59.33	45.00
MTCE0253-291	I-25 SIGN REPLACEMENT PHASE 2		06/16/22	3,534.00	45.00	41.69	50.38
	WEIGHTED AVERAGE FOR THE SECOND	QUARTER		4,504.75	42.82	40.27	48.48
NHPP0702-414	VAIL PASS AUX PHASE 1 CAP 3		07/08/22	66.00	43.66	43.66	43.66
FBR0702-423	VAIL PASS AUX BE F-12-AT PHAS						
NHPP0063-054	US 6 FROM I70-B TO 33 RD. (MP		08/18/22	64.00	30.00	40.45	45.00
2670403-065	US40_FLOYD HILL ROUNDABOUTS		09/15/22	448.00	40.00	41.00	42.00
	WEIGHTED AVERAGE FOR THE THIRD	QUARTER		578.00	39.31	41.07	42.52
C0831-126	SH83 EL PASO COUNTY TO BAYOU		10/13/22	96.00	45.00	38.50	42.00
TRG0253-264	I-25 AND SH 119 PARK-N-RIDE		10/27/22	253.00	33.00	42.79	45.00
STAM420-001	US 285 AT HWY 9C IMPROVEMENTS		12/01/22	220.00	38.00	60.30	62.43
BR2854-148	INTERSECTION OF US 285 & SH 9						
STM0091-046	ADA RAMP IMPROVEMENTS - FAIRP						
2670703-487	I-70 BRIDGES OVER WARD ROAD-		12/01/22	862.00	70.00	43.09	41.00
	WEIGHTED AVERAGE FOR THE FOURTH	QUARTER		1,431.00	56.86	45.09	45.00
	WEIGHTED AVERAGE FOR THE YEAR			9,229.75	42.42	43.60	45.65
=====	614-00025	Inst Sign Panel (CL I)		Sq Foot	=====		
MTCER300-262			02/03/22	30,695.00	13.00	13.08	8.00
	WEIGHTED AVERAGE FOR THE FIRST	QUARTER		30,695.00	13.00	13.08	8.00
	WEIGHTED AVERAGE FOR THE YEAR			30,695.00	13.00	13.08	8.00

COLORADO DEPARTMENT OF TRANSPORTATION
 ITEM UNIT COSTS BY PROJECTS -- 2022 COST DATA

11:31 Wednesday, March 8, 2023 443

PROJECT NUMBER	ITEM NUMBER/ PROJECT LOCATION	ITEM DESCRIPTION/ PROJECT LOCATION	DATE LET	UNIT/ QUANTITY	ENGR. EST.	AVERAGE BID	AWARDED BID
===== 614-00027		Inst Sign Panel (CL II)		Sq Foot	=====		
MTCER300-262			02/03/22	16,711.00	17.00	16.00	10.00
M R100-351		FY22 R1 SIGN STRUCTURE REPLAC	03/17/22	24.00	24.00	15.00	13.00
	WEIGHTED AVERAGE FOR THE FIRST QUARTER			16,735.00	17.01	16.00	10.00
	WEIGHTED AVERAGE FOR THE YEAR			16,735.00	17.01	16.00	10.00
===== 614-00028		Inst Sign Panel (CL III)		Sq Foot	=====		
MTCER300-262			02/03/22	13,703.00	28.00	20.92	15.00
M R100-351		FY22 R1 SIGN STRUCTURE REPLAC	03/17/22	4,534.00	9.00	15.00	9.00
	WEIGHTED AVERAGE FOR THE FIRST QUARTER			18,237.00	23.28	19.85	13.51
MPR200-280		PUEBLO AREA	11/17/22	2,565.00	16.50	17.00	19.00
	WEIGHTED AVERAGE FOR THE FOURTH QUARTER			2,565.00	16.50	17.00	19.00
	WEIGHTED AVERAGE FOR THE YEAR			20,802.00	22.44	19.58	14.19
===== 614-00035		Sign Panel (Spec)		Sq Foot	=====		
CM760-047		COLFAX AND QUAIL	05/12/22	28.00	26.00	75.00	47.00
	WEIGHTED AVERAGE FOR THE SECOND QUARTER			28.00	26.00	75.00	47.00
FSA052A-057		SH52 BOX CULVERT EXTENSION (M	08/04/22	18.00	50.00	766.78	2229.93
	WEIGHTED AVERAGE FOR THE THIRD QUARTER			18.00	50.00	766.78	2229.93
IM025A-050		I25-MP103.9 - INTERSECTION DR	12/01/22	8.00	30.00	30.67	34.00
	WEIGHTED AVERAGE FOR THE FOURTH QUARTER			8.00	30.00	30.67	34.00
	WEIGHTED AVERAGE FOR THE YEAR			54.00	34.59	241.48	772.72

COLORADO DEPARTMENT OF TRANSPORTATION
ITEM UNIT COSTS BY PROJECTS -- 2022 COST DATA

11:31 Wednesday, March 8, 2023 444

PROJECT NUMBER	ITEM NUMBER/ PROJECT LOCATION	ITEM DESCRIPTION/ PROJECT LOCATION	DATE LET	UNIT/ QUANTITY	ENGR. EST.	AVERAGE BID	AWARDED BID
===== 614-00037 Sign Panel (Spec) Each =====							
CR100-362			03/14/22	10.00	107.00	107.00	107.00
		WEIGHTED AVERAGE FOR THE FIRST QUARTER		10.00	107.00	107.00	107.00
C0852-120 Rehabilitation of Culvert by 05/26/22							
		WEIGHTED AVERAGE FOR THE SECOND QUARTER		3.00	1300.00	240.00	240.00
TRG0253-264 I-25 AND SH 119 PARK-N-RIDE 10/27/22							
		WEIGHTED AVERAGE FOR THE FOURTH QUARTER		4.00	9475.00	13479.63	18125.00
		WEIGHTED AVERAGE FOR THE YEAR		17.00	2521.76	9625.29	4370.00
===== 614-00041 Signpost (Spec) Each =====							
ITS 0741-024		VMS SIGN INSTALLATIONS AND VS	06/02/22	14.00	3500.00	4215.00	4101.00
		WEIGHTED AVERAGE FOR THE SECOND QUARTER		14.00	3500.00	4215.00	4101.00
		WEIGHTED AVERAGE FOR THE YEAR		14.00	3500.00	4215.00	4101.00
===== 614-00044 Timber Signpost (4x4 In) Lin Foot =====							
2670703-479		I-70 BRIDGE OVER HARLAN	05/05/22	11.00	50.00	37.24	41.89
		WEIGHTED AVERAGE FOR THE SECOND QUARTER		11.00	50.00	37.24	41.89
		WEIGHTED AVERAGE FOR THE YEAR		11.00	50.00	37.24	41.89
===== 614-00200 Steel Signpost (U-2) Lin Foot =====							
STA0252-459			02/03/22	108.00	27.00	41.49	35.00
		WEIGHTED AVERAGE FOR THE FIRST QUARTER		108.00	27.00	41.49	35.00

COLORADO DEPARTMENT OF TRANSPORTATION
 ITEM UNIT COSTS BY PROJECTS -- 2022 COST DATA

11:31 Wednesday, March 8, 2023 445

PROJECT NUMBER	ITEM NUMBER/ PROJECT LOCATION	ITEM DESCRIPTION/ PROJECT LOCATION	DATE LET	UNIT/ QUANTITY	ENGR. EST.	AVERAGE BID	AWARDED BID
===== 614-00200		Steel Signpost (U-2)		Lin Foot	=====		
NHPP0702-413		VAIL PASS AUX PHASE 1 CAP 2	04/18/22	21.00	19.26	19.26	19.26
		WEIGHTED AVERAGE FOR THE SECOND QUARTER		21.00	19.26	19.26	19.26
NHPP083A-046		SH83 RESURFACING STROH RD TO	12/08/22	6.00	35.00	9.50	5.00
		WEIGHTED AVERAGE FOR THE FOURTH QUARTER		6.00	35.00	9.50	5.00
		WEIGHTED AVERAGE FOR THE YEAR		135.00	26.15	39.11	31.22
===== 614-00216		Steel Signpost (2x2 In T)		Lin Foot	=====		
NHPP2873-189		US 287 (FEDERAL BLVD) - COLFA	01/06/22	240.00	16.00	30.86	24.80
		WEIGHTED AVERAGE FOR THE FIRST QUARTER		240.00	16.00	30.86	24.80
FSA052A-046		SH52 WCR 37 INTERSECTION IMPR	06/09/22	112.00	20.00	45.28	22.00
		WEIGHTED AVERAGE FOR THE SECOND QUARTER		112.00	20.00	45.28	22.00
STU0252-457		I-25:ALAMEDA RIVER PH 2.0	11/03/22	206.00	50.00	44.50	52.00
C5502-097		US550 MP 117.28-126.06	11/17/22	20.00	50.00	16.23	13.00
NHPP0021-041		SH2 RESURFACING MLK TO 52ND	12/01/22	190.00	30.00	19.54	13.02
		WEIGHTED AVERAGE FOR THE FOURTH QUARTER		416.00	40.87	30.13	32.32
		WEIGHTED AVERAGE FOR THE YEAR		768.00	30.05	33.23	28.47
===== 614-00220		Steel Signpost (2.5x2.5 In T)		Lin Foot	=====		
C1211-099		SH 121 NORTH SGA SIGNALS	08/25/22	348.00	22.00	39.50	55.00
		WEIGHTED AVERAGE FOR THE THIRD QUARTER		348.00	22.00	39.50	55.00

COLORADO DEPARTMENT OF TRANSPORTATION
ITEM UNIT COSTS BY PROJECTS -- 2022 COST DATA

11:31 Wednesday, March 8, 2023 446

PROJECT NUMBER	ITEM NUMBER/ PROJECT LOCATION	ITEM DESCRIPTION/ PROJECT LOCATION	DATE LET	UNIT/ QUANTITY	ENGR. EST.	AVERAGE BID	AWARDED BID
=====	614-00220	Steel Signpost (2.5x2.5 In T)		Lin Foot	=====		
SHE0242-087		US 24 SAFETY IMPRVMTS, E OF	11/03/22	11.00	20.00	40.43	26.28
		WEIGHTED AVERAGE FOR THE FOURTH QUARTER		11.00	20.00	40.43	26.28
		WEIGHTED AVERAGE FOR THE YEAR		359.00	21.94	39.54	54.12
=====	614-00612	Steel Signpost (W 6x12)		Lin Foot	=====		
MTCER300-262			02/03/22	50.00	60.00	106.67	60.00
		WEIGHTED AVERAGE FOR THE FIRST QUARTER		50.00	60.00	106.67	60.00
NHPP0702-414		VAIL PASS AUX PHASE 1 CAP 3	07/08/22	30.00	60.03	60.03	60.03
FBR0702-423		VAIL PASS AUX BE F-12-AT PHAS					
NHPP0063-054		US 6 FROM I70-B TO 33 RD. (MP	08/18/22	32.00	70.00	97.21	121.00
		WEIGHTED AVERAGE FOR THE THIRD QUARTER		62.00	65.18	85.34	91.50
MPR200-280		PUEBLO AREA	11/17/22	61.00	88.00	82.50	100.00
		WEIGHTED AVERAGE FOR THE FOURTH QUARTER		61.00	88.00	82.50	100.00
		WEIGHTED AVERAGE FOR THE YEAR		173.00	71.73	93.13	85.39
=====	614-00615	Steel Signpost (W 6x15)		Lin Foot	=====		
C0762-055			02/17/22	32.00	85.00	128.82	200.00
NHPP0703-472			03/10/22	90.00	55.00	136.15	150.00
M R100-351		FY22 R1 SIGN STRUCTURE REPLAC	03/17/22	58.00	150.00	143.50	157.00
		WEIGHTED AVERAGE FOR THE FIRST QUARTER		180.00	90.94	136.01	161.14
NHC540-017		R2 CHAINUP STA @ KENOSHA/HOOS	05/12/22	75.00	88.00	120.33	126.00
		WEIGHTED AVERAGE FOR THE SECOND QUARTER		75.00	88.00	120.33	126.00

COLORADO DEPARTMENT OF TRANSPORTATION
 ITEM UNIT COSTS BY PROJECTS -- 2022 COST DATA

11:31 Wednesday, March 8, 2023 447

PROJECT NUMBER	ITEM NUMBER/ PROJECT LOCATION	ITEM DESCRIPTION/ PROJECT LOCATION	DATE LET	UNIT/ QUANTITY	ENGR. EST.	AVERAGE BID	AWARDED BID
=====	614-00615	Steel Signpost (W 6x15)		Lin Foot	=====		
MPR200-280		PUEBLO AREA	11/17/22	32.00	98.00	97.50	120.00
		WEIGHTED AVERAGE FOR THE FOURTH QUARTER		32.00	98.00	97.50	120.00
		WEIGHTED AVERAGE FOR THE YEAR		287.00	90.96	129.30	147.37
=====	614-00818	Steel Signpost (W 8x18)		Lin Foot	=====		
C0762-055			02/17/22	75.00	90.00	136.65	205.00
M R100-351		FY22 R1 SIGN STRUCTURE REPLAC	03/17/22	31.00	160.00	149.50	163.00
		WEIGHTED AVERAGE FOR THE FIRST QUARTER		106.00	110.47	138.85	192.72
MPR200-280		PUEBLO AREA	11/17/22	176.00	125.00	122.50	120.00
		WEIGHTED AVERAGE FOR THE FOURTH QUARTER		176.00	125.00	123.92	120.00
		WEIGHTED AVERAGE FOR THE YEAR		282.00	119.54	131.01	146.22
=====	614-00821	Steel Signpost (W 8x21)		Lin Foot	=====		
C0831-126		SH83 EL PASO COUNTY TO BAYOU	10/13/22	84.00	130.00	140.00	130.00
TRG0253-264		I-25 AND SH 119 PARK-N-RIDE	10/27/22	76.00	125.00	167.00	175.00
MPR200-280		PUEBLO AREA	11/17/22	62.00	138.00	125.00	120.00
		WEIGHTED AVERAGE FOR THE FOURTH QUARTER		222.00	130.52	156.17	142.61
		WEIGHTED AVERAGE FOR THE YEAR		222.00	130.52	156.17	142.61
=====	614-01022	Steel Signpost (W 10x22)		Lin Foot	=====		
C0762-055			02/17/22	73.00	140.00	143.15	210.00
		WEIGHTED AVERAGE FOR THE FIRST QUARTER		73.00	140.00	143.15	210.00
MPR200-280		PUEBLO AREA	11/17/22	124.00	148.00	150.00	140.00
		WEIGHTED AVERAGE FOR THE FOURTH QUARTER		124.00	148.00	150.00	140.00
		WEIGHTED AVERAGE FOR THE YEAR		197.00	145.04	146.29	165.94

PROJECT NUMBER	ITEM NUMBER/ PROJECT LOCATION	ITEM DESCRIPTION/ PROJECT LOCATION	DATE LET	UNIT/ QUANTITY	ENGR. EST.	AVERAGE BID	AWARDED BID
=====	614-01026	Steel Signpost (W 10x26)		Lin Foot	=====		
ITS0703-477		ITS EQUIPMENT UPGRADE AT EJMT	01/06/22	96.00	150.00	170.00	170.00
NHPP 0761-238		I-76 DAHLIA TO YORK	03/10/22	45.00	150.00	136.17	80.00
C0761-239							
		WEIGHTED AVERAGE FOR THE FIRST QUARTER		141.00	150.00	143.29	141.28
MTCE0253-291		I-25 SIGN REPLACEMENT PHASE 2	06/16/22	41.00	85.00	108.25	133.49
		WEIGHTED AVERAGE FOR THE SECOND QUARTER		41.00	85.00	108.25	133.49
2670703-487		I-70 BRIDGES OVER WARD ROAD-	12/01/22	78.00	120.00	120.23	100.00
		WEIGHTED AVERAGE FOR THE FOURTH QUARTER		78.00	120.00	120.23	100.00
		WEIGHTED AVERAGE FOR THE YEAR		260.00	130.75	130.50	127.67
=====	614-01226	Steel Signpost (W 12x26)		Lin Foot	=====		
NHPP0702-383		I-70 EB AUX FRISCO TO SILVERT	01/13/22	53.00	120.00	163.05	140.00
MTCER300-262			02/03/22	50.00	80.00	150.00	140.00
NHPP 0761-238		I-76 DAHLIA TO YORK	03/10/22	46.00	160.00	147.76	90.00
C0761-239							
		WEIGHTED AVERAGE FOR THE FIRST QUARTER		149.00	118.93	153.36	124.56
STM1151-038		SH115 MP 27 TO MP 38	04/21/22	93.00	190.00	130.58	120.00
NHC540-017		R2 CHAINUP STA @ KENOSHA/HOOS	05/12/22	56.00	184.00	172.67	158.00
MTCE0253-291		I-25 SIGN REPLACEMENT PHASE 2	06/16/22	257.99	105.00	107.45	127.89
		WEIGHTED AVERAGE FOR THE SECOND QUARTER		406.99	135.29	126.34	130.23
		WEIGHTED AVERAGE FOR THE YEAR		555.99	130.91	137.29	128.71
=====	614-01401	Steel Sign Support Casting		Each	=====		
MTCER300-262			02/03/22	696.00	90.00	191.67	100.00
		WEIGHTED AVERAGE FOR THE FIRST QUARTER		696.00	90.00	191.67	100.00
		WEIGHTED AVERAGE FOR THE YEAR		696.00	90.00	191.67	100.00

COLORADO DEPARTMENT OF TRANSPORTATION
ITEM UNIT COSTS BY PROJECTS -- 2022 COST DATA

11:31 Wednesday, March 8, 2023 449

PROJECT NUMBER	ITEM NUMBER/ PROJECT LOCATION	ITEM DESCRIPTION/ PROJECT LOCATION	DATE LET	UNIT/ QUANTITY	ENGR. EST.	AVERAGE BID	AWARDED BID
===== 614-01502 Steel Sign Supp (2-In Rd) (Po&Sock) Lin Foot =====							
NHPP 0761-238		I-76 DAHLIA TO YORK	03/10/22	20.00	30.00	36.04	40.00
C0761-239							
NHM765-007			03/31/22	223.00	25.00	39.60	31.92
		WEIGHTED AVERAGE FOR THE FIRST QUARTER		243.00	25.41	38.91	32.59

NHPP0702-413		VAIL PASS AUX PHASE 1 CAP 2	04/18/22	97.00	26.75	26.75	26.75
		WEIGHTED AVERAGE FOR THE SECOND QUARTER		97.00	26.75	26.75	26.75

NHPP0063-048		US6 / 20 ROAD INTERSECTION IM	12/15/22	72.00	25.00	29.80	19.00
		WEIGHTED AVERAGE FOR THE FOURTH QUARTER		72.00	25.00	53.05	20.05
		WEIGHTED AVERAGE FOR THE YEAR		412.00	25.65	42.63	28.25
=====							
===== 614-01503 Steel Sign Supp (2-In Rd) (Po&Sock) Each =====							
NHPP0702-383		I-70 EB AUX FRISCO TO SILVERT	01/13/22	25.00	250.00	418.53	435.00
C0762-055			02/17/22	83.00	275.00	386.37	500.00
STA 067A-048		Hwy 67A MP 0.00 TO MP 11.05 I	03/03/22	27.00	30.00	283.43	290.00
NHPP0703-472			03/10/22	8.00	240.00	487.36	400.00
ER007A-035			03/15/22	127.00	433.50	463.85	463.85
		WEIGHTED AVERAGE FOR THE FIRST QUARTER		270.00	321.70	398.93	453.01

NH0504-911			04/07/22	4.00	225.00	376.30	372.60
STM1151-038		SH115 MP 27 TO MP 38	04/21/22	22.00	270.00	323.45	300.00
2670703-479		I-70 BRIDGE OVER HARLAN	05/05/22	67.00	260.00	480.31	587.82
STA0712-019		SH 71: Frieight Improvements	05/12/22	5.00	300.00	491.65	491.65
MTCE0253-291		I-25 SIGN REPLACEMENT PHASE 2	06/16/22	63.00	280.00	398.93	360.86
		WEIGHTED AVERAGE FOR THE SECOND QUARTER		161.00	269.57	436.86	451.35

NHPP0063-054		US 6 FROM I70-B TO 33 RD. (MP	08/18/22	32.00	500.00	512.98	455.00
		WEIGHTED AVERAGE FOR THE THIRD QUARTER		32.00	500.00	512.98	455.00

COLORADO DEPARTMENT OF TRANSPORTATION
ITEM UNIT COSTS BY PROJECTS -- 2022 COST DATA

11:31 Wednesday, March 8, 2023 450

PROJECT NUMBER	ITEM NUMBER/ PROJECT LOCATION	ITEM DESCRIPTION/ PROJECT LOCATION	DATE LET	UNIT/ QUANTITY	ENGR. EST.	AVERAGE BID	AWARDED BID
===== 614-01503		Steel Sign Supp (2-In Rd) (Po&Sock)		Each	=====		
C0831-126		SH83 EL PASO COUNTY TO BAYOU	10/13/22	67.00	500.00	295.00	290.00
TRG0253-264		I-25 AND SH 119 PARK-N-RIDE	10/27/22	18.00	250.00	361.85	360.00
STA3852-015		US 385 HOLYOKE NORTH	10/27/22	12.00	450.00	300.00	300.00
NHPP0853-126		US85C: PLATTEVILLE NORTH MP (11/10/22	5.00	290.00	342.80	310.00
MPR200-280		PUEBLO AREA	11/17/22	72.00	310.00	325.00	300.00
STAM420-001		US 285 AT HWY 9C IMPROVEMENTS	12/01/22	24.00	230.00	415.81	590.75
BR2854-148		INTERSECTION OF US 285 & SH 9					
STM0091-046		ADA RAMP IMPROVEMENTS - FAIRP					
STR114A-015		SH114 SILLSVILLE SOUTH TO MP3	12/01/22	2.00	300.00	400.00	400.00
STR0092-024		SH 9 North of Silverthorne	12/22/22	14.00	500.00	313.50	297.00
STA0361-129		US 36: HYGIENE RD AND NELSON	12/22/22	10.00	300.00	409.53	536.80
STA385A-016		SH 385 MP 97.76	12/22/22	1.00	500.00	513.75	500.00
STR096A-050		SH 96 MP 168.99 TO 193.77	12/22/22	52.00	260.00	379.33	400.00
		WEIGHTED AVERAGE FOR THE FOURTH QUARTER		277.00	351.30	354.59	355.47
		WEIGHTED AVERAGE FOR THE YEAR		740.00	329.15	397.42	416.22
===== 614-01512		Steel Sign Support (2-In Rd) (Post)		Lin Foot	=====		
MTCER300-262			02/03/22	4,856.00	18.00	19.33	12.00
NHPP1601-083			02/03/22	12.00	20.00	248.93	35.00
NHPP0063-063			02/24/22	615.00	12.00	13.35	14.00
		WEIGHTED AVERAGE FOR THE FIRST QUARTER		5,483.00	17.33	19.22	12.27
FSA052A-046		SH52 WCR 37 INTERSECTION IMPR	06/09/22	26.00	25.00	43.90	22.00
		WEIGHTED AVERAGE FOR THE SECOND QUARTER		26.00	25.00	43.90	22.00
NHPP0702-414		VAIL PASS AUX PHASE 1 CAP 3	07/08/22	40.00	13.10	13.10	13.10
FBR0702-423		VAIL PASS AUX BE F-12-AT PHAS					
SHE2873-193		US 287 & CO 52 INTERSECTION I	09/15/22	22.00	15.00	16.56	12.84
		WEIGHTED AVERAGE FOR THE THIRD QUARTER		62.00	13.77	15.76	13.01
C5502-097		US550 MP 117.28-126.06	11/17/22	514.00	20.00	16.94	15.10

COLORADO DEPARTMENT OF TRANSPORTATION
ITEM UNIT COSTS BY PROJECTS -- 2022 COST DATA

11:31 Wednesday, March 8, 2023 451

PROJECT NUMBER	ITEM NUMBER/ PROJECT LOCATION	ITEM DESCRIPTION/ PROJECT LOCATION	DATE LET	UNIT/ QUANTITY	ENGR. EST.	AVERAGE BID	AWARDED BID
=====	614-01512	Steel Sign Support (2-In Rd) (Post)		Lin Foot	=====	=====	=====
STRC090-011		US 50B AND SH71/CR18 INTERSEC	11/17/22	60.00	30.00	22.55	27.10
NHPP0502-090		SH 50 MP 134.6-136 GUNNISON C	12/22/22	35.00	15.00	16.85	14.24
		WEIGHTED AVERAGE FOR THE FOURTH QUARTER		609.00	20.70	17.30	16.23
		WEIGHTED AVERAGE FOR THE YEAR		6,180.00	17.66	19.17	12.71
=====	614-01522	Steel Sign Supp (2-In Rd) (Sock)		Each	=====	=====	=====
NHPP2873-189		US 287 (FEDERAL BLVD) - COLFA	01/06/22	6.00	140.00	289.57	409.27
MTCER300-262			02/03/22	347.00	90.00	258.33	200.00
NHPP1601-083			02/03/22	51.00	60.00	189.31	160.00
NHPP0063-063			02/24/22	57.00	150.00	160.00	167.00
		WEIGHTED AVERAGE FOR THE FIRST QUARTER		461.00	94.75	244.67	194.22
2670703-479		I-70 BRIDGE OVER HARLAN	05/05/22	6.00	170.00	187.16	225.18
FSA052A-046		SH52 WCR 37 INTERSECTION IMPR	06/09/22	2.00	200.00	219.76	200.00
		WEIGHTED AVERAGE FOR THE SECOND QUARTER		8.00	177.50	194.24	218.89
NHPP0702-414		VAIL PASS AUX PHASE 1 CAP 3	07/08/22	4.00	300.14	300.14	300.14
FBR0702-423		VAIL PASS AUX BE F-12-AT PHAS					
ER0502-092		US 50 MP 204 EB MONARCH TRUCK	08/29/22	2.00	60.00	444.47	460.92
SHE2873-193		US 287 & CO 52 INTERSECTION I	09/15/22	2.00	150.00	139.06	133.75
		WEIGHTED AVERAGE FOR THE THIRD QUARTER		8.00	202.57	251.64	298.74
STA3852-015		US 385 HOLYOKE NORTH	10/27/22	11.00	200.00	160.00	160.00
C5502-097		US550 MP 117.28-126.06	11/17/22	50.00	300.00	190.99	178.00
STRC090-011		US 50B AND SH71/CR18 INTERSEC	11/17/22	5.00	300.00	186.50	290.00
STA0711-021		SH71: REGION LINE NORTH	12/01/22	26.00	140.00	206.67	300.00
NHPP0021-041		SH2 RESURFACING MLK TO 52ND	12/01/22	15.00	200.00	396.37	258.55
NHPP0502-090		SH 50 MP 134.6-136 GUNNISON C	12/22/22	3.00	200.00	363.47	355.66
		WEIGHTED AVERAGE FOR THE FOURTH QUARTER		110.00	235.82	239.59	225.96
		WEIGHTED AVERAGE FOR THE YEAR		587.00	123.78	242.39	201.93

COLORADO DEPARTMENT OF TRANSPORTATION
 ITEM UNIT COSTS BY PROJECTS -- 2022 COST DATA

11:31 Wednesday, March 8, 2023 452

PROJECT NUMBER	ITEM NUMBER/ PROJECT LOCATION	ITEM DESCRIPTION/ PROJECT LOCATION	DATE LET	UNIT/ QUANTITY	ENGR. EST.	AVERAGE BID	AWARDED BID
=====	614-01554	Steel Signpost (4 In Rd) (Slip)		Lin Foot	=====		
NHPP 0761-238 C0761-239		I-76 DAHLIA TO YORK	03/10/22	36.00	60.00	78.98	83.00
		WEIGHTED AVERAGE FOR THE FIRST QUARTER		36.00	60.00	78.98	83.00
		WEIGHTED AVERAGE FOR THE YEAR		36.00	60.00	78.98	83.00
=====	614-01572	Steel Sign Supp (2-1/2 Rd NP40) (Po&Slip)		Lin Foot	=====		
NHM765-007			03/31/22	336.00	45.00	54.43	43.32
		WEIGHTED AVERAGE FOR THE FIRST QUARTER		336.00	45.00	54.43	43.32
FBR0761-236		I-76 OVER CLR CRK SCOUR MIT	08/25/22	42.00	40.00	68.33	80.00
		WEIGHTED AVERAGE FOR THE THIRD QUARTER		42.00	40.00	68.33	80.00
NHPP0063-048		US6 / 20 ROAD INTERSECTION IM	12/15/22	156.00	50.00	57.13	48.00
		WEIGHTED AVERAGE FOR THE FOURTH QUARTER		156.00	50.00	86.22	43.05
		WEIGHTED AVERAGE FOR THE YEAR		534.00	46.07	70.21	45.66
=====	614-01573	Steel Sign Supp (2-1/2 Rd NP40) (Po&Slip)		Each	=====		
NHPP0702-383 C0762-055 STA 067A-048 ER007A-035		I-70 EB AUX FRISCO TO SILVERT	01/13/22	32.00	450.00	571.54	540.00
			02/17/22	19.00	425.00	599.27	800.00
		Hwy 67A MP 0.00 TO MP 11.05 I	03/03/22	122.00	400.00	476.48	500.00
			03/15/22	18.00	637.50	682.15	682.15
		WEIGHTED AVERAGE FOR THE FIRST QUARTER		191.00	433.25	522.04	553.71
NH0504-911			04/07/22	14.00	400.00	483.80	507.60

COLORADO DEPARTMENT OF TRANSPORTATION
 ITEM UNIT COSTS BY PROJECTS -- 2022 COST DATA

11:31 Wednesday, March 8, 2023 453

PROJECT NUMBER	ITEM NUMBER/ PROJECT LOCATION	ITEM DESCRIPTION/ PROJECT LOCATION	DATE LET	UNIT/ QUANTITY	ENGR. EST.	AVERAGE BID	AWARDED BID
=====	614-01573	Steel Sign Supp (2-1/2 Rd NP40) (Po&Slip)		Each	=====	=====	=====
STM1151-038		SH115 MP 27 TO MP 38	04/21/22	135.00	450.00	483.79	475.00
STA0712-019		SH 71: Frieight Improvements	05/12/22	14.00	500.00	776.29	776.29
MTCE0253-291		I-25 SIGN REPLACEMENT PHASE 2	06/16/22	115.00	475.00	690.67	602.34
		WEIGHTED AVERAGE FOR THE SECOND QUARTER		278.00	460.34	538.36	544.49
FSA052A-057		SH52 BOX CULVERT EXTENSION (M	08/04/22	2.00	700.00	546.92	708.50
NHPP0063-054		US 6 FROM I70-B TO 33 RD. (MP	08/18/22	58.00	550.00	745.54	757.00
2670403-065		US40_FLOYD HILL ROUNDABOUTS	09/15/22	49.00	550.00	712.21	467.00
		WEIGHTED AVERAGE FOR THE THIRD QUARTER		109.00	552.75	722.90	625.74
C0831-126		SH83 EL PASO COUNTY TO BAYOU	10/13/22	137.00	600.00	532.50	515.00
FSAM240-200		SH21B CO SPRINGS SIGNAL REPLA	10/27/22	2.00	450.00	836.50	575.00
TRG0253-264		I-25 AND SH 119 PARK-N-RIDE	10/27/22	28.00	500.00	575.28	600.00
STA3852-015		US 385 HOLYOKE NORTH	10/27/22	4.00	650.00	600.00	600.00
NHPP0853-126		US85C: PLATTEVILLE NORTH MP (11/10/22	2.00	450.00	485.80	450.00
MPR200-280		PUEBLO AREA	11/17/22	257.00	503.00	532.50	515.00
STAM420-001		US 285 AT HWY 9C IMPROVEMENTS	12/01/22	70.00	430.00	548.61	561.95
BR2854-148		INTERSECTION OF US 285 & SH 9					
STM0091-046		ADA RAMP IMPROVEMENTS - FAIRP					
STA0711-021		SH71: REGION LINE NORTH	12/01/22	8.00	430.00	626.67	600.00
STR114A-015		SH114 SILLSVILLE SOUTH TO MP3	12/01/22	1.00	500.00	565.00	500.00
2670703-487		I-70 BRIDGES OVER WARD ROAD-	12/01/22	7.00	1000.00	677.64	770.00
IM025A-050		I25-MP103.9 - INTERSECTION DR	12/01/22	45.00	425.00	546.67	590.00
STA0361-129		US 36: HYGIENE RD AND NELSON	12/22/22	7.00	450.00	578.33	510.63
STA385A-016		SH 385 MP 97.76	12/22/22	2.00	700.00	560.28	611.11
STR096A-050		SH 96 MP 168.99 TO 193.77	12/22/22	71.00	450.00	532.33	500.00
		WEIGHTED AVERAGE FOR THE FOURTH QUARTER		641.00	509.42	548.04	532.03
		WEIGHTED AVERAGE FOR THE YEAR		1,219.00	490.16	554.08	546.65
=====	614-01575	Steel Sign Supp (2-1/2 In Rd NP40) (Po)		Lin Foot	=====	=====	=====
MT CER300-262			02/03/22	232.00	40.00	39.33	20.00
NHPP1601-083			02/03/22	120.00	20.00	57.12	40.00
STR0141-031			02/17/22	74.50	25.00	34.00	30.00
NHPP0063-063			02/24/22	264.00	25.00	22.05	23.00
		WEIGHTED AVERAGE FOR THE FIRST QUARTER		690.50	29.17	35.75	25.70

COLORADO DEPARTMENT OF TRANSPORTATION
ITEM UNIT COSTS BY PROJECTS -- 2022 COST DATA

11:31 Wednesday, March 8, 2023 454

PROJECT NUMBER	ITEM NUMBER/ PROJECT LOCATION	ITEM DESCRIPTION/ PROJECT LOCATION	DATE LET	UNIT/ QUANTITY	ENGR. EST.	AVERAGE BID	AWARDED BID
===== 614-01575		Steel Sign Supp (2-1/2 In Rd NP40) (Po)		Lin Foot	=====		
2670703-479		I-70 BRIDGE OVER HARLAN	05/05/22	310.00	20.00	33.00	36.66
NHC540-017		R2 CHAINUP STA @ KENOSHA/HOOS	05/12/22	57.00	28.00	51.00	38.00
NHPP 3851-018		US 385 NORTH OF CHEYENNE WELL	05/26/22	182.00	25.00	35.00	40.00
FSA3921-019		SH 392 AND WCR 55 ISLANDS	06/02/22	11.00	20.00	41.33	46.00
FSA052A-046		SH52 WCR 37 INTERSECTION IMPR	06/09/22	89.00	30.00	61.28	28.00
		WEIGHTED AVERAGE FOR THE SECOND QUARTER		649.00	23.48	38.80	36.69
NHPP0702-414		VAIL PASS AUX PHASE 1 CAP 3	07/08/22	52.00	30.56	30.56	30.56
FBR0702-423		VAIL PASS AUX BE F-12-AT PHAS					
2670403-065		US40 FLOYD HILL ROUNDABOUTS	09/15/22	95.00	35.00	48.98	31.00
SHE2873-193		US 287 & CO 52 INTERSECTION I	09/15/22	31.00	25.00	31.91	31.00
		WEIGHTED AVERAGE FOR THE THIRD QUARTER		178.00	31.96	41.08	30.87
C5502-097		US550 MP 117.28-126.06	11/17/22	232.00	40.00	26.64	23.80
STRC090-011		US 50B AND SH71/CR18 INTERSEC	11/17/22	58.00	32.00	27.45	39.90
NHPP0502-090		SH 50 MP 134.6-136 GUNNISON C	12/22/22	241.00	30.00	32.34	31.29
		WEIGHTED AVERAGE FOR THE FOURTH QUARTER		531.00	34.59	30.09	28.96
		WEIGHTED AVERAGE FOR THE YEAR		2,048.50	29.01	35.77	30.47
===== 614-01578		Steel Sign Supp (2-1/2 In Rd NP40) (Slip)		Each	=====		
MTCER300-262			02/03/22	252.00	350.00	325.00	325.00
NHPP1601-083			02/03/22	24.00	250.00	373.75	250.00
STR0141-031			02/17/22	6.00	450.00	307.67	330.00
NHPP0063-063			02/24/22	25.00	300.00	359.00	375.00
		WEIGHTED AVERAGE FOR THE FIRST QUARTER		307.00	340.07	329.28	323.31
2670703-479		I-70 BRIDGE OVER HARLAN	05/05/22	28.00	360.00	422.79	538.07

COLORADO DEPARTMENT OF TRANSPORTATION
ITEM UNIT COSTS BY PROJECTS -- 2022 COST DATA

11:31 Wednesday, March 8, 2023 455

PROJECT NUMBER	ITEM NUMBER/ PROJECT LOCATION	ITEM DESCRIPTION/ PROJECT LOCATION	DATE LET	UNIT/ QUANTITY	ENGR. EST.	AVERAGE BID	AWARDED BID
=====	614-01578	Steel Sign Supp (2-1/2 In Rd NP40) (Slip)		Each =====			
NHC540-017		R2 CHAINUP STA @ KENOSHA/HOOS	05/12/22	5.00	321.00	431.67	320.00
NHPP 3851-018		US 385 NORTH OF CHEYENNE WELL	05/26/22	13.00	375.00	385.00	320.00
FSA3921-019		SH 392 AND WCR 55 ISLANDS	06/02/22	1.00	375.00	290.67	240.00
FSA052A-046		SH52 WCR 37 INTERSECTION IMPR	06/09/22	6.00	500.00	386.91	275.00
		WEIGHTED AVERAGE FOR THE SECOND QUARTER		53.00	376.13	413.20	428.60
NHPP0702-414		VAIL PASS AUX PHASE 1 CAP 3	07/08/22	5.00	436.56	436.56	436.56
FBR0702-423		VAIL PASS AUX BE F-12-AT PHAS					
SHE2873-193		US 287 & CO 52 INTERSECTION I	09/15/22	36.00	75.00	310.26	362.73
		WEIGHTED AVERAGE FOR THE THIRD QUARTER		41.00	119.09	313.12	371.73
STA3852-015		US 385 HOLYOKE NORTH	10/27/22	8.00	350.00	260.00	260.00
C5502-097		US550 MP 117.28-126.06	11/17/22	21.00	400.00	471.97	486.00
STRC090-011		US 50B AND SH71/CR18 INTERSEC	11/17/22	5.00	400.00	337.50	395.00
NHPP0502-090		SH 50 MP 134.6-136 GUNNISON C	12/22/22	24.00	350.00	591.13	675.78
		WEIGHTED AVERAGE FOR THE FOURTH QUARTER		58.00	372.41	527.98	525.51
		WEIGHTED AVERAGE FOR THE YEAR		459.00	328.58	366.17	365.34
=====	614-01582	Steel Sign Supp (2-1/2 In Rd) (Po&Slip)		Lin Foot =====			
C1211-099		SH 121 NORTH SGA SIGNALS	08/25/22	102.00	500.00	71.00	79.00
		WEIGHTED AVERAGE FOR THE THIRD QUARTER		102.00	500.00	71.00	79.00
		WEIGHTED AVERAGE FOR THE YEAR		102.00	500.00	71.00	79.00
=====	614-01583	Stl Sign Supp (2-1/2 In Rd 80) (Po&Slip)		Each =====			
NHPP0702-383		I-70 EB AUX FRISCO TO SILVERT	01/13/22	25.00	550.00	674.50	635.00
STA0252-459			02/03/22	10.00	500.00	529.07	450.00
STA 067A-048		Hwy 67A MP 0.00 TO MP 11.05 I	03/03/22	2.00	500.00	573.20	600.00
NHPP 0761-238		I-76 DAHLIA TO YORK	03/10/22	25.00	600.00	673.00	400.00
C0761-239							
NHPP0703-472			03/10/22	3.00	480.00	709.47	615.00
		WEIGHTED AVERAGE FOR THE FIRST QUARTER		65.00	556.77	661.49	514.15

COLORADO DEPARTMENT OF TRANSPORTATION
ITEM UNIT COSTS BY PROJECTS -- 2022 COST DATA

11:31 Wednesday, March 8, 2023 456

PROJECT NUMBER	ITEM NUMBER/ PROJECT LOCATION	ITEM DESCRIPTION/ PROJECT LOCATION	DATE LET	UNIT/ QUANTITY	ENGR. EST.	AVERAGE BID	AWARDED BID
===== 614-01583		Stl Sign Supp (2-1/2 In Rd 80) (Po&Slip)		Each	=====	=====	=====
NHPP072A-047		SH-72 RESURFACING: I-70 TO IN	06/09/22	97.00	500.00	622.34	622.34
		WEIGHTED AVERAGE FOR THE SECOND QUARTER		97.00	500.00	622.34	622.34
FSA052A-057		SH52 BOX CULVERT EXTENSION (M	08/04/22	2.00	600.00	696.38	877.50
2670403-065		US40_FLOYD HILL ROUNDABOUTS	09/15/22	11.00	600.00	778.36	566.00
		WEIGHTED AVERAGE FOR THE THIRD QUARTER		13.00	600.00	765.75	613.92
MPR200-280		PUEBLO AREA	11/17/22	35.00	570.00	600.00	550.00
STAM420-001		US 285 AT HWY 9C IMPROVEMENTS	12/01/22	1.00	540.00	731.01	839.02
BR2854-148		INTERSECTION OF US 285 & SH 9					
STM0091-046		ADA RAMP IMPROVEMENTS - FAIRP					
2670703-487		I-70 BRIDGES OVER WARD ROAD-	12/01/22	11.00	700.00	812.15	890.00
IM025A-050		I25-MP103.9 - INTERSECTION DR	12/01/22	2.00	525.00	418.33	640.00
NHPP0021-041		SH2 RESURFACING MLK TO 52ND	12/01/22	5.00	550.00	1083.21	843.22
NHPP083A-046		SH83 RESURFACING STROH RD TO	12/08/22	38.00	625.00	770.77	654.54
NHPP0931-033		SH93:US6 TO 58TH RESURFACING	12/15/22	81.00	500.00	870.34	630.65
STR0092-024		SH 9 North of Silverthorne	12/22/22	10.00	900.00	740.50	701.00
STR096A-050		SH 96 MP 168.99 TO 193.77	12/22/22	10.00	580.00	657.33	600.00
		WEIGHTED AVERAGE FOR THE FOURTH QUARTER		193.00	575.34	808.04	644.25
		WEIGHTED AVERAGE FOR THE YEAR		368.00	553.07	741.32	614.42
===== 614-01585		Steel Sign Supp (2-1/2 In Rd 80) (Post)		Lin Foot	=====	=====	=====
MTCER300-262			02/03/22	2,793.00	50.00	33.33	30.00
		WEIGHTED AVERAGE FOR THE FIRST QUARTER		2,793.00	50.00	33.33	30.00
NHC540-017		R2 CHAINUP STA @ KENOSHA/HOOS	05/12/22	116.00	30.00	60.00	45.00
		WEIGHTED AVERAGE FOR THE SECOND QUARTER		116.00	30.00	60.00	45.00

COLORADO DEPARTMENT OF TRANSPORTATION
ITEM UNIT COSTS BY PROJECTS -- 2022 COST DATA

11:31 Wednesday, March 8, 2023 457

PROJECT NUMBER	ITEM NUMBER/ PROJECT LOCATION	ITEM DESCRIPTION/ PROJECT LOCATION	DATE LET	UNIT/ QUANTITY	ENGR. EST.	AVERAGE BID	AWARDED BID
=====	614-01585	Steel Sign Supp (2-1/2 In Rd 80) (Post)		Lin Foot	=====		
2670403-065		US40_FLOYD HILL ROUNDABOUTS	09/15/22	84.00	40.00	58.23	38.00
		WEIGHTED AVERAGE FOR THE THIRD QUARTER		84.00	40.00	58.23	38.00
STU0252-457		I-25:ALAMEDA RIVER PH 2.0	11/03/22	84.00	70.00	53.23	64.00
		WEIGHTED AVERAGE FOR THE FOURTH QUARTER		84.00	70.00	53.23	64.00
		WEIGHTED AVERAGE FOR THE YEAR		3,077.00	49.52	35.56	31.71
=====	614-01588	Steel Sign Supp (2-1/2 In Rd 80) (Slip)		Each	=====		
NHC540-017		R2 CHAINUP STA @ KENOSHA/HOOS	05/12/22	8.00	386.00	430.67	317.00
		WEIGHTED AVERAGE FOR THE SECOND QUARTER		8.00	386.00	430.67	317.00
STU0252-457		I-25:ALAMEDA RIVER PH 2.0	11/03/22	7.00	700.00	605.30	800.00
		WEIGHTED AVERAGE FOR THE FOURTH QUARTER		7.00	700.00	605.30	800.00
		WEIGHTED AVERAGE FOR THE YEAR		15.00	532.53	512.16	542.40
=====	614-03001	Conc Footing (Ty 1)		Each	=====		
MTCER300-262			02/03/22	2.00	1500.00	2250.00	1250.00
		WEIGHTED AVERAGE FOR THE FIRST QUARTER		2.00	1500.00	2250.00	1250.00
NHPP0702-414		VAIL PASS AUX PHASE 1 CAP 3	07/08/22	2.00	2182.80	2182.80	2182.80
FBR0702-423		VAIL PASS AUX BE F-12-AT PHAS					
NHPP0063-054		US 6 FROM I70-B TO 33 RD. (MP	08/18/22	2.00	2000.00	1886.29	1815.00
		WEIGHTED AVERAGE FOR THE THIRD QUARTER		4.00	2091.40	1985.12	1998.90

COLORADO DEPARTMENT OF TRANSPORTATION
 ITEM UNIT COSTS BY PROJECTS -- 2022 COST DATA

11:31 Wednesday, March 8, 2023 458

PROJECT NUMBER	ITEM NUMBER/ PROJECT LOCATION	ITEM DESCRIPTION/ PROJECT LOCATION	DATE LET	UNIT/ QUANTITY	ENGR. EST.	AVERAGE BID	AWARDED BID
=====	614-03001	Conc Footing (Ty 1)		Each	=====	=====	=====
MPR200-280		PUEBLO AREA	11/17/22	4.00	1850.00	1800.00	2200.00
		WEIGHTED AVERAGE FOR THE FOURTH QUARTER		4.00	1850.00	1800.00	2200.00
		WEIGHTED AVERAGE FOR THE YEAR		10.00	1876.56	1990.54	1929.56
=====	614-03002	Conc Footing (Ty 2)		Each	=====	=====	=====
C0762-055			02/17/22	2.00	2400.00	3141.44	4000.00
NHPP0703-472			03/10/22	6.00	1200.00	2779.63	2000.00
M R100-351		FY22 R1 SIGN STRUCTURE REPLAC	03/17/22	4.00	2400.00	2766.00	2923.00
		WEIGHTED AVERAGE FOR THE FIRST QUARTER		12.00	1800.00	2849.26	2641.00
NHC540-017		R2 CHAINUP STA @ KENOSHA/HOOS	05/12/22	4.00	2531.00	3633.33	4400.00
		WEIGHTED AVERAGE FOR THE SECOND QUARTER		4.00	2531.00	3633.33	4400.00
MPR200-280		PUEBLO AREA	11/17/22	2.00	2350.00	2220.00	2700.00
		WEIGHTED AVERAGE FOR THE FOURTH QUARTER		2.00	2350.00	2220.00	2700.00
		WEIGHTED AVERAGE FOR THE YEAR		18.00	2023.56	2972.33	3038.44
=====	614-03003	Conc Footing (Ty 3)		Each	=====	=====	=====
C0762-055			02/17/22	4.00	2500.00	3401.63	4200.00
M R100-351		FY22 R1 SIGN STRUCTURE REPLAC	03/17/22	2.00	3200.00	2894.00	3132.00
		WEIGHTED AVERAGE FOR THE FIRST QUARTER		6.00	2733.33	3300.10	3844.00
MPR200-280		PUEBLO AREA	11/17/22	10.00	2550.00	3000.00	3500.00
		WEIGHTED AVERAGE FOR THE FOURTH QUARTER		10.00	2550.00	2791.99	3250.00
		WEIGHTED AVERAGE FOR THE YEAR		16.00	2618.75	3003.71	3448.00

COLORADO DEPARTMENT OF TRANSPORTATION
 ITEM UNIT COSTS BY PROJECTS -- 2022 COST DATA

11:31 Wednesday, March 8, 2023 459

PROJECT NUMBER	ITEM NUMBER/ PROJECT LOCATION	ITEM DESCRIPTION/ PROJECT LOCATION	DATE LET	UNIT/ QUANTITY	ENGR. EST.	AVERAGE BID	AWARDED BID
=====	614-03004	Conc Footing (Ty 4)		Each	=====	=====	=====
C0831-126		SH83 EL PASO COUNTY TO BAYOU	10/13/22	4.00	2500.00	3500.00	4000.00
TRG0253-264		I-25 AND SH 119 PARK-N-RIDE	10/27/22	4.00	3000.00	3436.75	3600.00
MPR200-280		PUEBLO AREA	11/17/22	4.00	2650.00	3250.00	3500.00
		WEIGHTED AVERAGE FOR THE FOURTH QUARTER		12.00	2716.67	3416.17	3700.00
		WEIGHTED AVERAGE FOR THE YEAR		12.00	2716.67	3416.17	3700.00
=====	614-03005	Conc Footing (Ty 5)		Each	=====	=====	=====
C0762-055			02/17/22	4.00	3500.00	3755.08	4300.00
		WEIGHTED AVERAGE FOR THE FIRST QUARTER		4.00	3500.00	3755.08	4300.00
MPR200-280		PUEBLO AREA	11/17/22	6.00	3200.00	3550.00	3600.00
		WEIGHTED AVERAGE FOR THE FOURTH QUARTER		6.00	3200.00	3550.00	3600.00
		WEIGHTED AVERAGE FOR THE YEAR		10.00	3320.00	3667.19	3880.00
=====	614-03006	Conc Footing (Ty 6)		Each	=====	=====	=====
ITS0703-477		ITS EQUIPMENT UPGRADE AT EJMT	01/06/22	6.00	4500.00	10825.00	10825.00
NHPP 0761-238		I-76 DAHLIA TO YORK	03/10/22	2.00	4500.00	3105.26	2300.00
C0761-239							
		WEIGHTED AVERAGE FOR THE FIRST QUARTER		8.00	4500.00	5210.64	8693.75
MTCE0253-291		I-25 SIGN REPLACEMENT PHASE 2	06/16/22	2.00	3500.00	7563.22	6626.43
		WEIGHTED AVERAGE FOR THE SECOND QUARTER		2.00	3500.00	7563.22	6626.43
2670703-487		I-70 BRIDGES OVER WARD ROAD-	12/01/22	4.00	4000.00	7812.80	21200.00
		WEIGHTED AVERAGE FOR THE FOURTH QUARTER		4.00	4000.00	7812.80	21200.00
		WEIGHTED AVERAGE FOR THE YEAR		14.00	4214.29	6546.59	11971.63

COLORADO DEPARTMENT OF TRANSPORTATION
ITEM UNIT COSTS BY PROJECTS -- 2022 COST DATA

11:31 Wednesday, March 8, 2023 460

PROJECT NUMBER	ITEM NUMBER/ PROJECT LOCATION	ITEM DESCRIPTION/ PROJECT LOCATION	DATE LET	UNIT/ QUANTITY	ENGR. EST.	AVERAGE BID	AWARDED BID
=====	614-03007	Conc Footing (Ty 7)		Each	=====	=====	=====
NHPP0702-383		I-70 EB AUX FRISCO TO SILVERT	01/13/22	2.00	4000.00	6524.02	5200.00
MTCER300-262			02/03/22	2.00	5000.00	4166.67	4500.00
NHPP 0761-238		I-76 DAHLIA TO YORK	03/10/22	2.00	4500.00	3537.64	3300.00
C0761-239							
		WEIGHTED AVERAGE FOR THE FIRST QUARTER		6.00	4500.00	4588.82	4333.33
STM1151-038		SH115 MP 27 TO MP 38	04/21/22	8.00	4000.00	3580.89	3300.00
NHC540-017		R2 CHAINUP STA @ KENOSHA/HOOS	05/12/22	4.00	2608.00	4666.67	5000.00
MTCE0253-291		I-25 SIGN REPLACEMENT PHASE 2	06/16/22	12.00	3750.00	7715.76	5931.51
		WEIGHTED AVERAGE FOR THE SECOND QUARTER		24.00	3643.00	5058.08	4899.09
		WEIGHTED AVERAGE FOR THE YEAR		30.00	3814.40	4919.04	4785.94
=====	614-10050	Mod Overhead Sign Str		Each	=====	=====	=====
M R100-351		FY22 R1 SIGN STRUCTURE REPLAC	03/17/22	4.00	7500.00	8764.50	8179.00
		WEIGHTED AVERAGE FOR THE FIRST QUARTER		4.00	7500.00	8764.50	8179.00
		WEIGHTED AVERAGE FOR THE YEAR		4.00	7500.00	8764.50	8179.00
=====	614-10120	Var Mesg Sign		Each	=====	=====	=====
NHC540-017		R2 CHAINUP STA @ KENOSHA/HOOS	05/12/22	1.00	5175.00	134000.00	127000.00
ITS 0741-024		VMS SIGN INSTALLATIONS AND VS	06/02/22	3.00	75000.00	85780.50	79856.00
		WEIGHTED AVERAGE FOR THE SECOND QUARTER		4.00	57543.75	101853.67	91642.00
		WEIGHTED AVERAGE FOR THE YEAR		4.00	57543.75	101853.67	91642.00
=====	614-10127	Var Speed Limit Sign		Each	=====	=====	=====
NHC540-017		R2 CHAINUP STA @ KENOSHA/HOOS	05/12/22	4.00	13655.00	27333.33	27000.00
ITS 0741-024		VMS SIGN INSTALLATIONS AND VS	06/02/22	14.00	16000.00	16095.50	14500.00
		WEIGHTED AVERAGE FOR THE SECOND QUARTER		18.00	15478.89	19466.85	17277.78
		WEIGHTED AVERAGE FOR THE YEAR		18.00	15478.89	19466.85	17277.78

COLORADO DEPARTMENT OF TRANSPORTATION
ITEM UNIT COSTS BY PROJECTS -- 2022 COST DATA

11:31 Wednesday, March 8, 2023 461

PROJECT NUMBER	ITEM NUMBER/ PROJECT LOCATION	ITEM DESCRIPTION/ PROJECT LOCATION	DATE LET	UNIT/ QUANTITY	ENGR. EST.	AVERAGE BID	AWARDED BID
=====	614-10140	VMS LED (Double Faced)		Each	=====	=====	=====
ITS0703-477		ITS EQUIPMENT UPGRADE AT EJMT	01/06/22	22.00	70000.00	96065.00	96065.00
	WEIGHTED	AVERAGE FOR THE FIRST QUARTER		22.00	70000.00	96065.00	96065.00
		WEIGHTED AVERAGE FOR THE YEAR		22.00	70000.00	96065.00	96065.00
=====	614-10142	Public Info Display		Each	=====	=====	=====
TRG0253-264		I-25 AND SH 119 PARK-N-RIDE	10/27/22	3.00	50000.00	44043.75	45000.00
	WEIGHTED	AVERAGE FOR THE FOURTH QUARTER		3.00	50000.00	44043.75	45000.00
		WEIGHTED AVERAGE FOR THE YEAR		3.00	50000.00	44043.75	45000.00
=====	614-10145	VMS LED (Single Faced)		Each	=====	=====	=====
ITS0703-477		ITS EQUIPMENT UPGRADE AT EJMT	01/06/22	1.00	50000.00	107210.00	107210.00
	WEIGHTED	AVERAGE FOR THE FIRST QUARTER		1.00	50000.00	107210.00	107210.00
		WEIGHTED AVERAGE FOR THE YEAR		1.00	50000.00	107210.00	107210.00
=====	614-10146	VMS (LED) (Ground Mounted)		Each	=====	=====	=====
ITS0703-477		ITS EQUIPMENT UPGRADE AT EJMT	01/06/22	4.00	30000.00	58775.00	58775.00
	WEIGHTED	AVERAGE FOR THE FIRST QUARTER		4.00	30000.00	58775.00	58775.00
		WEIGHTED AVERAGE FOR THE YEAR		4.00	30000.00	58775.00	58775.00
=====	614-10147	VMS LED (Overhead)		Each	=====	=====	=====
ITS0703-477		ITS EQUIPMENT UPGRADE AT EJMT	01/06/22	4.00	40000.00	70175.00	70175.00
	WEIGHTED	AVERAGE FOR THE FIRST QUARTER		4.00	40000.00	70175.00	70175.00
STM1151-038		SH115 MP 27 TO MP 38	04/21/22	1.00	70000.00	88074.73	88250.00
	WEIGHTED	AVERAGE FOR THE SECOND QUARTER		1.00	70000.00	88074.73	88250.00

COLORADO DEPARTMENT OF TRANSPORTATION
 ITEM UNIT COSTS BY PROJECTS -- 2022 COST DATA

11:31 Wednesday, March 8, 2023 462

PROJECT NUMBER	ITEM NUMBER/ PROJECT LOCATION	ITEM DESCRIPTION/ PROJECT LOCATION	DATE LET	UNIT/ QUANTITY	ENGR. EST.	AVERAGE BID	AWARDED BID
=====	614-10147	VMS LED (Overhead)		Each	=====		
STAM420-001 BR2854-148 STM0091-046		US 285 AT HWY 9C IMPROVEMENTS INTERSECTION OF US 285 & SH 9 ADA RAMP IMPROVEMENTS - FAIRP	12/01/22	1.00	100000.00	109913.49	119153.97
	WEIGHTED	AVERAGE FOR THE FOURTH QUARTER		1.00	100000.00	109913.49	119153.97
		WEIGHTED AVERAGE FOR THE YEAR		6.00	55000.00	89286.74	81350.66
=====	614-10154	12 In Heated LED (Ball) (Red)		Each	=====		
C1211-099		SH 121 NORTH SGA SIGNALS	08/25/22	5.00	400.00	687.50	875.00
	WEIGHTED	AVERAGE FOR THE THIRD QUARTER		5.00	400.00	687.50	875.00
		WEIGHTED AVERAGE FOR THE YEAR		5.00	400.00	687.50	875.00
=====	614-10160	Sig Head B-Plates		Each	=====		
STU0252-457 NHPP083A-046		I-25:ALAMEDA RIVER PH 2.0 SH83 RESURFACING STROH RD TO	11/03/22 12/08/22	15.00 53.00	300.00 275.00	397.93 283.41	398.00 264.81
	WEIGHTED	AVERAGE FOR THE FOURTH QUARTER		68.00	280.51	317.54	294.19
		WEIGHTED AVERAGE FOR THE YEAR		68.00	280.51	317.54	294.19
=====	614-10240	LUS LED (Double Faced)		Each	=====		
ITS0703-477		ITS EQUIPMENT UPGRADE AT EJMT	01/06/22	88.00	4200.00	11960.00	11960.00
	WEIGHTED	AVERAGE FOR THE FIRST QUARTER		88.00	4200.00	11960.00	11960.00
		WEIGHTED AVERAGE FOR THE YEAR		88.00	4200.00	11960.00	11960.00
=====	614-10320	System Integration and Testing		LUMP SUM	=====		
STAM420-001		US 285 AT HWY 9C IMPROVEMENTS	12/01/22	1.00	10000.99	23073.08	25022.33

COLORADO DEPARTMENT OF TRANSPORTATION
ITEM UNIT COSTS BY PROJECTS -- 2022 COST DATA

11:31 Wednesday, March 8, 2023 463

PROJECT NUMBER	ITEM NUMBER/ PROJECT LOCATION	ITEM DESCRIPTION/ PROJECT LOCATION	DATE LET	UNIT/ QUANTITY	ENGR. EST.	AVERAGE BID	AWARDED BID
=====	614-10320	System Integration and Testing		LUMP SUM	=====	=====	=====
BR2854-148		INTERSECTION OF US 285 & SH 9					
STM0091-046		ADA RAMP IMPROVEMENTS - FAIRP					
	WEIGHTED	AVERAGE FOR THE FOURTH QUARTER		1.00	10000.99	23073.08	25022.33
		WEIGHTED AVERAGE FOR THE YEAR		1.00	10000.99	23073.08	25022.33
=====	614-30110	Btrfly Str		Each	=====	=====	=====
2670703-479		I-70 BRIDGE OVER HARLAN	05/05/22	1.00	30000.00	50423.75	60366.96
NHC540-017		R2 CHAINUP STA @ KENOSHA/HOOS	05/12/22	1.00	44100.00	58000.00	59000.00
	WEIGHTED	AVERAGE FOR THE SECOND QUARTER		2.00	37050.00	52949.17	59683.48
		WEIGHTED AVERAGE FOR THE YEAR		2.00	37050.00	52949.17	59683.48
=====	614-30205	VMS Butterfly Support (Roadside)		Each	=====	=====	=====
ITS 0741-024		VMS SIGN INSTALLATIONS AND VS	06/02/22	2.00	30000.00	47887.00	45000.00
	WEIGHTED	AVERAGE FOR THE SECOND QUARTER		2.00	30000.00	47887.00	45000.00
		WEIGHTED AVERAGE FOR THE YEAR		2.00	30000.00	47887.00	45000.00
=====	614-31800	Monotube Overhead Sign Cant (18 In Dia)		Each	=====	=====	=====
NHPP 0761-238		I-76 DAHLIA TO YORK	03/10/22	1.00	30000.00	54018.81	47000.00
C0761-239							
	WEIGHTED	AVERAGE FOR THE FIRST QUARTER		1.00	30000.00	54018.81	47000.00
		WEIGHTED AVERAGE FOR THE YEAR		1.00	30000.00	54018.81	47000.00
=====	614-32000	Monotube Overhead Sign Cant (20 In Dia)		Each	=====	=====	=====
NHPP 0761-238		I-76 DAHLIA TO YORK	03/10/22	2.00	40000.00	58102.27	51000.00
C0761-239							
	WEIGHTED	AVERAGE FOR THE FIRST QUARTER		2.00	40000.00	58102.27	51000.00
		WEIGHTED AVERAGE FOR THE YEAR		2.00	40000.00	58102.27	51000.00

COLORADO DEPARTMENT OF TRANSPORTATION
ITEM UNIT COSTS BY PROJECTS -- 2022 COST DATA

11:31 Wednesday, March 8, 2023 464

PROJECT NUMBER	ITEM NUMBER/ PROJECT LOCATION	ITEM DESCRIPTION/ PROJECT LOCATION	DATE LET	UNIT/ QUANTITY	ENGR. EST.	AVERAGE BID	AWARDED BID
=====	614-32400	Monotube Overhead Sign Cant (24 In Dia)		Each	=====	=====	=====
NHPP0702-383		I-70 EB AUX FRISCO TO SILVERT	01/13/22	2.00	55000.00	86362.57	83000.00
		WEIGHTED AVERAGE FOR THE FIRST QUARTER		2.00	55000.00	86362.57	83000.00
STM1151-038		SH115 MP 27 TO MP 38	04/21/22	1.00	44000.00	87546.92	90000.00
2670703-479		I-70 BRIDGE OVER HARLAN	05/05/22	1.00	42000.00	62327.86	72230.62
ITS 0741-024		VMS SIGN INSTALLATIONS AND VS	06/02/22	1.00	50000.00	74791.50	66290.00
MTCE0253-291		I-25 SIGN REPLACEMENT PHASE 2	06/16/22	15.00	40000.00	55451.50	52185.00
		WEIGHTED AVERAGE FOR THE SECOND QUARTER		18.00	40888.89	61042.55	56183.09
STAM420-001		US 285 AT HWY 9C IMPROVEMENTS	12/01/22	1.00	45000.00	71995.22	78045.86
BR2854-148		INTERSECTION OF US 285 & SH 9					
STM0091-046		ADA RAMP IMPROVEMENTS - FAIRP					
2670703-487		I-70 BRIDGES OVER WARD ROAD-	12/01/22	1.00	7500.00	72987.24	73000.00
		WEIGHTED AVERAGE FOR THE FOURTH QUARTER		2.00	26250.00	72546.34	75522.93
		WEIGHTED AVERAGE FOR THE YEAR		22.00	40840.91	66796.33	60379.16
=====	614-32900	Inst Monotube Overhead Sign Cant		Each	=====	=====	=====
M R100-351		FY22 R1 SIGN STRUCTURE REPLAC	03/17/22	5.00	11000.00	9832.00	11516.00
		WEIGHTED AVERAGE FOR THE FIRST QUARTER		5.00	11000.00	9832.00	11516.00
		WEIGHTED AVERAGE FOR THE YEAR		5.00	11000.00	9832.00	11516.00
=====	614-42400	Monotube Overhead Sign Brdg (24 In Dia)		Each	=====	=====	=====
2670703-487		I-70 BRIDGES OVER WARD ROAD-	12/01/22	1.00	35000.00	151012.59	151000.00
		WEIGHTED AVERAGE FOR THE FOURTH QUARTER		1.00	35000.00	151012.59	151000.00
		WEIGHTED AVERAGE FOR THE YEAR		1.00	35000.00	151012.59	151000.00
=====	614-70000	Prog Traf Sig Face		Each	=====	=====	=====
2670703-479		I-70 BRIDGE OVER HARLAN	05/05/22	3.00	5500.00	5617.38	6616.53
		WEIGHTED AVERAGE FOR THE SECOND QUARTER		3.00	5500.00	5617.38	6616.53
		WEIGHTED AVERAGE FOR THE YEAR		3.00	5500.00	5617.38	6616.53

COLORADO DEPARTMENT OF TRANSPORTATION
ITEM UNIT COSTS BY PROJECTS -- 2022 COST DATA

11:31 Wednesday, March 8, 2023 465

PROJECT NUMBER	ITEM NUMBER/ PROJECT LOCATION	ITEM DESCRIPTION/ PROJECT LOCATION	DATE LET	UNIT/ QUANTITY	ENGR. EST.	AVERAGE BID	AWARDED BID
===== 614-70010		Mod Sig Face		Each	=====	=====	=====
C1211-099		SH 121 NORTH SGA SIGNALS	08/25/22	3.00	400.00	575.00	650.00
		WEIGHTED AVERAGE FOR THE THIRD QUARTER		3.00	400.00	575.00	650.00
		WEIGHTED AVERAGE FOR THE YEAR		3.00	400.00	575.00	650.00
===== 614-70024		1310nm SFP Optic Module		Each	=====	=====	=====
ITS0703-477		ITS EQUIPMENT UPGRADE AT EJMT	01/06/22	120.00	500.00	350.00	350.00
NHPP 0761-238		I-76 DAHLIA TO YORK	03/10/22	4.00	500.00	185.99	160.00
C0761-239							
		WEIGHTED AVERAGE FOR THE FIRST QUARTER		124.00	500.00	315.47	343.87
STM1151-038		SH115 MP 27 TO MP 38	04/21/22	8.00	475.00	666.28	700.00
NHC540-017		R2 CHAINUP STA @ KENOSHA/HOOS	05/12/22	4.00	475.00	1033.33	600.00
ITS 0741-024		VMS SIGN INSTALLATIONS AND VS	06/02/22	4.00	500.00	715.00	660.00
		WEIGHTED AVERAGE FOR THE SECOND QUARTER		16.00	481.25	746.18	665.00
C1211-099		SH 121 NORTH SGA SIGNALS	08/25/22	2.00	160.00	657.50	765.00
		WEIGHTED AVERAGE FOR THE THIRD QUARTER		2.00	160.00	657.50	765.00
TRG0253-264		I-25 AND SH 119 PARK-N-RIDE	10/27/22	6.00	350.00	768.73	800.00
		WEIGHTED AVERAGE FOR THE FOURTH QUARTER		6.00	350.00	768.73	800.00
		WEIGHTED AVERAGE FOR THE YEAR		148.00	487.30	500.95	402.77
===== 614-70026		CWDM Multiplexor Demultiplexor Module		Each	=====	=====	=====
TRG0253-264		I-25 AND SH 119 PARK-N-RIDE	10/27/22	2.00	20000.00	4080.38	4300.00
		WEIGHTED AVERAGE FOR THE FOURTH QUARTER		2.00	20000.00	4080.38	4300.00
		WEIGHTED AVERAGE FOR THE YEAR		2.00	20000.00	4080.38	4300.00

COLORADO DEPARTMENT OF TRANSPORTATION
ITEM UNIT COSTS BY PROJECTS -- 2022 COST DATA

11:31 Wednesday, March 8, 2023 466

PROJECT NUMBER	ITEM NUMBER/ PROJECT LOCATION	ITEM DESCRIPTION/ PROJECT LOCATION	DATE LET	UNIT/ QUANTITY	ENGR. EST.	AVERAGE BID	AWARDED BID
=====	614-70028	CWDM SFP Optic Module		Each	=====	=====	=====
ITS 0741-024		VMS SIGN INSTALLATIONS AND VS	06/02/22	4.00	800.00	953.50	880.00
		WEIGHTED AVERAGE FOR THE SECOND QUARTER		4.00	800.00	953.50	880.00
TRG0253-264		I-25 AND SH 119 PARK-N-RIDE	10/27/22	8.00	1100.00	1220.28	1300.00
		WEIGHTED AVERAGE FOR THE FOURTH QUARTER		8.00	1100.00	1220.28	1300.00
		WEIGHTED AVERAGE FOR THE YEAR		12.00	1000.00	1190.64	1160.00
=====	614-70030	Optical Attenuator		Each	=====	=====	=====
NHPP 0761-238 C0761-239		I-76 DAHLIA TO YORK	03/10/22	4.00	500.00	146.60	125.00
		WEIGHTED AVERAGE FOR THE FIRST QUARTER		4.00	500.00	146.60	125.00
NHC540-017 ITS 0741-024		R2 CHAINUP STA @ KENOSHA/HOOS	05/12/22	4.00	164.00	916.67	650.00
		VMS SIGN INSTALLATIONS AND VS	06/02/22	8.00	175.00	179.00	165.00
		WEIGHTED AVERAGE FOR THE SECOND QUARTER		12.00	171.33	495.14	326.67
C1211-099		SH 121 NORTH SGA SIGNALS	08/25/22	2.00	125.00	282.50	365.00
		WEIGHTED AVERAGE FOR THE THIRD QUARTER		2.00	125.00	282.50	365.00
TRG0253-264		I-25 AND SH 119 PARK-N-RIDE	10/27/22	12.00	150.00	184.28	185.00
		WEIGHTED AVERAGE FOR THE FOURTH QUARTER		12.00	150.00	184.28	185.00
		WEIGHTED AVERAGE FOR THE YEAR		30.00	203.53	233.60	245.67
=====	614-70032	Optical Filter		Each	=====	=====	=====
ITS 0741-024		VMS SIGN INSTALLATIONS AND VS	06/02/22	12.00	750.00	596.00	550.00
		WEIGHTED AVERAGE FOR THE SECOND QUARTER		12.00	750.00	596.00	550.00

COLORADO DEPARTMENT OF TRANSPORTATION
ITEM UNIT COSTS BY PROJECTS -- 2022 COST DATA

11:31 Wednesday, March 8, 2023 467

PROJECT NUMBER	ITEM NUMBER/ PROJECT LOCATION	ITEM DESCRIPTION/ PROJECT LOCATION	DATE LET	UNIT/ QUANTITY	ENGR. EST.	AVERAGE BID	AWARDED BID
=====	614-70032	Optical Filter		Each	=====	=====	=====
TRG0253-264		I-25 AND SH 119 PARK-N-RIDE	10/27/22	8.00	1000.00	405.51	425.00
		WEIGHTED AVERAGE FOR THE FOURTH QUARTER		8.00	1000.00	405.51	425.00
		WEIGHTED AVERAGE FOR THE YEAR		20.00	850.00	457.46	500.00
=====	614-70150	Ped Sig Face (16) (Countdown)		Each	=====	=====	=====
CC030-081		ADA RAMP AND CURBS - FT. LUPT	04/14/22	2.00	750.00	1175.86	900.00
2670703-479		I-70 BRIDGE OVER HARLAN	05/05/22	10.00	650.00	511.70	603.53
CM760-047		COLFAX AND QUAIL	05/12/22	6.00	480.00	672.60	707.00
NHPP072A-047		SH-72 RESURFACING: I-70 TO IN	06/09/22	8.00	700.00	635.29	635.29
		WEIGHTED AVERAGE FOR THE SECOND QUARTER		26.00	633.85	605.93	659.99
NHPP0063-054		US 6 FROM I70-B TO 33 RD. (MP	08/18/22	6.00	700.00	982.42	850.00
C1211-099		SH 121 NORTH SGA SIGNALS	08/25/22	36.00	700.00	702.00	825.00
SHE2873-193		US 287 & CO 52 INTERSECTION I	09/15/22	8.00	800.00	716.49	564.00
		WEIGHTED AVERAGE FOR THE THIRD QUARTER		50.00	716.00	732.76	786.24
FSAM240-200		SH21B CO SPRINGS SIGNAL REPLA	10/27/22	24.00	500.00	878.75	890.00
TRG0253-264		I-25 AND SH 119 PARK-N-RIDE	10/27/22	11.00	700.00	766.45	800.00
STU0252-457		I-25:ALAMEDA RIVER PH 2.0	11/03/22	8.00	700.00	989.48	990.00
STAM420-001		US 285 AT HWY 9C IMPROVEMENTS	12/01/22	8.00	610.00	1136.40	1221.33
BR2854-148		INTERSECTION OF US 285 & SH 9					
STM0091-046		ADA RAMP IMPROVEMENTS - FAIRP					
NHPP083A-046		SH83 RESURFACING STROH RD TO	12/08/22	2.00	750.00	1143.37	1086.74
NHPP0931-033		SH93:US6 TO 58TH RESURFACING	12/15/22	4.00	700.00	577.44	690.00
		WEIGHTED AVERAGE FOR THE FOURTH QUARTER		57.00	604.91	868.20	926.04
		WEIGHTED AVERAGE FOR THE YEAR		133.00	652.33	777.17	821.47
=====	614-70200	Access Ped Sig		Each	=====	=====	=====
CR100-362			03/14/22	37.00	2327.25	2327.25	2327.25
		WEIGHTED AVERAGE FOR THE FIRST QUARTER		37.00	2327.25	2327.25	2327.25

COLORADO DEPARTMENT OF TRANSPORTATION
ITEM UNIT COSTS BY PROJECTS -- 2022 COST DATA

11:31 Wednesday, March 8, 2023 468

PROJECT NUMBER	ITEM NUMBER/ PROJECT LOCATION	ITEM DESCRIPTION/ PROJECT LOCATION	DATE LET	UNIT/ QUANTITY	ENGR. EST.	AVERAGE BID	AWARDED BID
=====	614-70200	Access Ped Sig		Each	=====		
NHPP072A-047		SH-72 RESURFACING: I-70 TO IN	06/09/22	32.00	1400.00	1772.81	1772.81
		WEIGHTED AVERAGE FOR THE SECOND QUARTER		32.00	1400.00	1772.81	1772.81
C1211-099		SH 121 NORTH SGA SIGNALS	08/25/22	3.00	2500.00	1279.50	1400.00
		WEIGHTED AVERAGE FOR THE THIRD QUARTER		3.00	2500.00	1279.50	1400.00
NHPP083A-046		SH83 RESURFACING STROH RD TO	12/08/22	8.00	1750.00	3077.75	2855.50
NHPP0931-033		SH93:US6 TO 58TH RESURFACING	12/15/22	8.00	1400.00	2013.11	1730.00
		WEIGHTED AVERAGE FOR THE FOURTH QUARTER		16.00	1575.00	2367.99	2292.75
		WEIGHTED AVERAGE FOR THE YEAR		88.00	1859.18	2147.79	2087.75
=====	614-70225	Traf Sig Face (12-12)		Each	=====		
NHPP 0761-238		I-76 DAHLIA TO YORK	03/10/22	2.00	750.00	705.67	550.00
C0761-239		WEIGHTED AVERAGE FOR THE FIRST QUARTER		2.00	750.00	705.67	550.00
		WEIGHTED AVERAGE FOR THE YEAR		2.00	750.00	705.67	550.00
=====	614-70324	Traf Sig Face (8-8-8)		Each	=====		
STU0252-457		I-25:ALAMEDA RIVER PH 2.0	11/03/22	4.00	900.00	2100.02	2100.00
		WEIGHTED AVERAGE FOR THE FOURTH QUARTER		4.00	900.00	2100.02	2100.00
		WEIGHTED AVERAGE FOR THE YEAR		4.00	900.00	2100.02	2100.00
=====	614-70336	Traf Sig Face (12-12-12)		Each	=====		
NHPP 0761-238		I-76 DAHLIA TO YORK	03/10/22	4.00	1000.00	924.93	750.00

COLORADO DEPARTMENT OF TRANSPORTATION
ITEM UNIT COSTS BY PROJECTS -- 2022 COST DATA

11:31 Wednesday, March 8, 2023 469

PROJECT NUMBER	ITEM NUMBER/ PROJECT LOCATION	ITEM DESCRIPTION/ PROJECT LOCATION	DATE LET	UNIT/ QUANTITY	ENGR. EST.	AVERAGE BID	AWARDED BID
=====	614-70336	Traf Sig Face (12-12-12)		Each	=====	=====	=====
C0761-239							
		WEIGHTED AVERAGE FOR THE FIRST QUARTER		4.00	1000.00	924.93	750.00
2670703-479		I-70 BRIDGE OVER HARLAN	05/05/22	34.00	900.00	688.58	809.06
CM760-047		COLFAX AND QUAIL	05/12/22	12.00	750.00	1141.80	1040.00
NHPP072A-047		SH-72 RESURFACING: I-70 TO IN	06/09/22	111.00	850.00	946.94	946.94
		WEIGHTED AVERAGE FOR THE SECOND QUARTER		157.00	853.18	837.57	924.19
NHPP0063-054		US 6 FROM I70-B TO 33 RD. (MP	08/18/22	16.00	800.00	1408.82	1225.00
C1211-099		SH 121 NORTH SGA SIGNALS	08/25/22	64.00	900.00	937.50	1175.00
SHE2873-193		US 287 & CO 52 INTERSECTION I	09/15/22	24.00	1100.00	920.51	719.00
		WEIGHTED AVERAGE FOR THE THIRD QUARTER		104.00	930.77	979.06	1077.46
FSAM240-200		SH21B CO SPRINGS SIGNAL REPLA	10/27/22	65.00	650.00	1044.50	990.00
TRG0253-264		I-25 AND SH 119 PARK-N-RIDE	10/27/22	2.00	830.00	1130.70	1200.00
STU0252-457		I-25:ALAMEDA RIVER PH 2.0	11/03/22	12.00	1100.00	1797.38	1800.00
STRC090-011		US 50B AND SH71/CR18 INTERSEC	11/17/22	11.00	1100.00	865.50	990.00
STAM420-001		US 285 AT HWY 9C IMPROVEMENTS	12/01/22	18.00	850.00	1526.54	1668.16
BR2854-148		INTERSECTION OF US 285 & SH 9					
STM0091-046		ADA RAMP IMPROVEMENTS - FAIRP					
NHPP0063-048		US6 / 20 ROAD INTERSECTION IM	12/15/22	15.00	1200.00	1560.56	1210.00
NHPP0931-033		SH93:US6 TO 58TH RESURFACING	12/15/22	11.00	1000.00	977.63	846.00
		WEIGHTED AVERAGE FOR THE FOURTH QUARTER		134.00	847.09	1215.62	1169.57
		WEIGHTED AVERAGE FOR THE YEAR		399.00	872.83	1033.00	1044.81
=====	614-70448	Traf Sig Face (12-12-12-12)		Each	=====	=====	=====
2670703-479		I-70 BRIDGE OVER HARLAN	05/05/22	6.00	1100.00	838.63	987.11
CM760-047		COLFAX AND QUAIL	05/12/22	8.00	920.00	1372.00	968.00
NHPP072A-047		SH-72 RESURFACING: I-70 TO IN	06/09/22	26.00	1050.00	1396.43	1396.43
		WEIGHTED AVERAGE FOR THE SECOND QUARTER		40.00	1031.50	1189.98	1249.35

COLORADO DEPARTMENT OF TRANSPORTATION
ITEM UNIT COSTS BY PROJECTS -- 2022 COST DATA

11:31 Wednesday, March 8, 2023 470

PROJECT NUMBER	ITEM NUMBER/ PROJECT LOCATION	ITEM DESCRIPTION/ PROJECT LOCATION	DATE LET	UNIT/ QUANTITY	ENGR. EST.	AVERAGE BID	AWARDED BID
===== 614-70448		Traf Sig Face (12-12-12-12)		Each	=====		
C1211-099		SH 121 NORTH SGA SIGNALS	08/25/22	33.00	1100.00	1125.00	1400.00
		WEIGHTED AVERAGE FOR THE THIRD QUARTER		33.00	1100.00	1125.00	1400.00
FSAM240-200		SH21B CO SPRINGS SIGNAL REPLA	10/27/22	8.00	1200.00	1251.50	1035.00
STU0252-457		I-25:ALAMEDA RIVER PH 2.0	11/03/22	4.00	1200.00	2207.03	2200.00
STRC090-011		US 50B AND SH71/CR18 INTERSEC	11/17/22	11.00	1300.00	986.00	1040.00
STAM420-001		US 285 AT HWY 9C IMPROVEMENTS	12/01/22	2.00	1050.00	1811.64	1966.05
BR2854-148		INTERSECTION OF US 285 & SH 9					
STM0091-046		ADA RAMP IMPROVEMENTS - FAIRP					
NHPP083A-046		SH83 RESURFACING STROH RD TO	12/08/22	4.00	950.00	1617.59	1535.17
NHPP0931-033		SH93:US6 TO 58TH RESURFACING	12/15/22	2.00	3000.00	1456.11	1328.00
		WEIGHTED AVERAGE FOR THE FOURTH QUARTER		31.00	1309.68	1414.52	1330.61
		WEIGHTED AVERAGE FOR THE YEAR		104.00	1136.15	1251.69	1321.37
===== 614-70560		Traf Sig Face (12-12-12-12-12)		Each	=====		
NHPP0063-048		US6 / 20 ROAD INTERSECTION IM	12/15/22	2.00	1800.00	2267.65	1760.00
		WEIGHTED AVERAGE FOR THE FOURTH QUARTER		2.00	1800.00	2267.65	1760.00
		WEIGHTED AVERAGE FOR THE YEAR		2.00	1800.00	2267.65	1760.00
===== 614-72740		Blank Out Sign(LED) (Sing Fac)		Each	=====		
C1211-099		SH 121 NORTH SGA SIGNALS	08/25/22	1.00	10000.00	8531.00	10500.00
		WEIGHTED AVERAGE FOR THE THIRD QUARTER		1.00	10000.00	8531.00	10500.00
STRC090-011		US 50B AND SH71/CR18 INTERSEC	11/17/22	1.00	6000.00	7206.50	8100.00
		WEIGHTED AVERAGE FOR THE FOURTH QUARTER		1.00	6000.00	7206.50	8100.00
		WEIGHTED AVERAGE FOR THE YEAR		2.00	8000.00	7868.75	9300.00

COLORADO DEPARTMENT OF TRANSPORTATION
 ITEM UNIT COSTS BY PROJECTS -- 2022 COST DATA

11:31 Wednesday, March 8, 2023 471

PROJECT NUMBER	ITEM NUMBER/ PROJECT LOCATION	ITEM DESCRIPTION/ PROJECT LOCATION	DATE LET	UNIT/ QUANTITY	ENGR. EST.	AVERAGE BID	AWARDED BID
===== 614-72765		Traf Sig (24x24 Blank Out LED Sign)		Each			
STU0252-457		I-25:ALAMEDA RIVER PH 2.0	11/03/22	2.00	10000.00	7938.66	7900.00
	WEIGHTED AVERAGE FOR THE FOURTH QUARTER			2.00	10000.00	7938.66	7900.00
	WEIGHTED AVERAGE FOR THE YEAR			2.00	10000.00	7938.66	7900.00
===== 614-72830		Communications Cabinet		Each			
ITS0703-477		ITS EQUIPMENT UPGRADE AT EJMT	01/06/22	1.00	25000.00	27800.00	27800.00
NHPP 0761-238		I-76 DAHLIA TO YORK	03/10/22	1.00	16000.00	16270.09	16000.00
C0761-239							
	WEIGHTED AVERAGE FOR THE FIRST QUARTER			2.00	20500.00	17551.19	21900.00
TRG0253-264		I-25 AND SH 119 PARK-N-RIDE	10/27/22	4.00	15000.00	19321.19	20400.00
	WEIGHTED AVERAGE FOR THE FOURTH QUARTER			4.00	15000.00	19321.19	20400.00
	WEIGHTED AVERAGE FOR THE YEAR			6.00	16833.33	18932.65	20900.00
===== 614-72831		Comm Cabinet (Type 1)		Each			
ITS0703-477		ITS EQUIPMENT UPGRADE AT EJMT	01/06/22	4.00	25000.00	28900.00	28900.00
	WEIGHTED AVERAGE FOR THE FIRST QUARTER			4.00	25000.00	28900.00	28900.00
2670703-497		I-70_GENESEE WILDLIFE XING	09/15/22	1.00	10200.00	21747.25	20405.08
	WEIGHTED AVERAGE FOR THE THIRD QUARTER			1.00	10200.00	21747.25	20405.08
	WEIGHTED AVERAGE FOR THE YEAR			5.00	22040.00	24348.25	27201.02
===== 614-72832		Comm Cabinet (Type 2)		Each			
STM1151-038		SH115 MP 27 TO MP 38	04/21/22	2.00	10000.00	22143.03	22250.00
	WEIGHTED AVERAGE FOR THE SECOND QUARTER			2.00	10000.00	22143.03	22250.00

COLORADO DEPARTMENT OF TRANSPORTATION
ITEM UNIT COSTS BY PROJECTS -- 2022 COST DATA

11:31 Wednesday, March 8, 2023 472

PROJECT NUMBER	ITEM NUMBER/ PROJECT LOCATION	ITEM DESCRIPTION/ PROJECT LOCATION	DATE LET	UNIT/ QUANTITY	ENGR. EST.	AVERAGE BID	AWARDED BID
=====	614-72832	Comm Cabinet (Type 2)		Each	=====		
2670703-497		I-70_GENESEE WILDLIFE KING	09/15/22	1.00	12400.00	15868.76	15166.37
		WEIGHTED AVERAGE FOR THE THIRD QUARTER		1.00	12400.00	15868.76	15166.37
TRG0253-264		I-25 AND SH 119 PARK-N-RIDE	10/27/22	1.00	15000.00	11812.70	12400.00
STAM420-001		US 285 AT HWY 9C IMPROVEMENTS	12/01/22	1.00	14513.00	25278.85	27405.41
BR2854-148		INTERSECTION OF US 285 & SH 9					
STM0091-046		ADA RAMP IMPROVEMENTS - FAIRP					
		WEIGHTED AVERAGE FOR THE FOURTH QUARTER		2.00	14756.50	16301.42	19902.71
		WEIGHTED AVERAGE FOR THE YEAR		5.00	12382.60	18211.33	19894.36
=====	614-72836	Conflict Monitor		Each	=====		
2670703-479		I-70 BRIDGE OVER HARLAN	05/05/22	2.00	1100.00	1629.69	1921.86
NHPP072A-047		SH-72 RESURFACING: I-70 TO IN	06/09/22	1.00	1000.00	3416.18	3416.18
		WEIGHTED AVERAGE FOR THE SECOND QUARTER		3.00	1066.67	1767.12	2419.97
C1211-099		SH 121 NORTH SGA SIGNALS	08/25/22	2.00	1000.00	1662.50	1325.00
		WEIGHTED AVERAGE FOR THE THIRD QUARTER		2.00	1000.00	1662.50	1325.00
		WEIGHTED AVERAGE FOR THE YEAR		5.00	1040.00	1742.50	1981.98
=====	614-72854	Traf Ctrl Cabinet		Each	=====		
NHPP2873-189		US 287 (FEDERAL BLVD) - COLFA	01/06/22	1.00	26000.00	34710.36	32755.64
		WEIGHTED AVERAGE FOR THE FIRST QUARTER		1.00	26000.00	34710.36	32755.64
		WEIGHTED AVERAGE FOR THE YEAR		1.00	26000.00	34710.36	32755.64
=====	614-72855	Traf Sig Ctrl Cabinet		Each	=====		
2670703-479		I-70 BRIDGE OVER HARLAN	05/05/22	2.00	25000.00	22233.52	26227.84

COLORADO DEPARTMENT OF TRANSPORTATION
 ITEM UNIT COSTS BY PROJECTS -- 2022 COST DATA

11:31 Wednesday, March 8, 2023 473

PROJECT NUMBER	ITEM NUMBER/ PROJECT LOCATION	ITEM DESCRIPTION/ PROJECT LOCATION	DATE LET	UNIT/ QUANTITY	ENGR. EST.	AVERAGE BID	AWARDED BID
=====	614-72855	Traf Sig Ctrl Cabinet		Each	=====	=====	=====
CM760-047		COLFAX AND QUAIL	05/12/22	1.00	21500.00	24836.40	25413.00
NHPP072A-047		SH-72 RESURFACING: I-70 TO IN	06/09/22	1.00	20000.00	35180.56	35180.56
		WEIGHTED AVERAGE FOR THE SECOND QUARTER		4.00	22875.00	23675.82	28262.31
C1211-099		SH 121 NORTH SGA SIGNALS	08/25/22	2.00	35000.00	21500.00	22000.00
SHE2873-193		US 287 & CO 52 INTERSECTION I	09/15/22	1.00	30000.00	42011.25	38780.00
		WEIGHTED AVERAGE FOR THE THIRD QUARTER		3.00	33333.33	33806.75	27593.33
FSAM240-200		SH21B CO SPRINGS SIGNAL REPLA	10/27/22	3.00	21000.00	25766.25	26950.00
STRC090-011		US 50B AND SH71/CR18 INTERSEC	11/17/22	1.00	40000.00	32750.00	29500.00
STAM420-001		US 285 AT HWY 9C IMPROVEMENTS	12/01/22	1.00	26680.00	46716.36	50640.43
BR2854-148		INTERSECTION OF US 285 & SH 9					
STM0091-046		ADA RAMP IMPROVEMENTS - FAIRP					
NHPP0063-048		US6 / 20 ROAD INTERSECTION IM	12/15/22	1.00	35000.00	50416.72	40700.00
NHPP0931-033		SH93:US6 TO 58TH RESURFACING	12/15/22	1.00	35000.00	36236.89	33330.00
		WEIGHTED AVERAGE FOR THE FOURTH QUARTER		7.00	28525.71	34929.80	33574.35
		WEIGHTED AVERAGE FOR THE YEAR		14.00	27941.43	30970.50	30774.98
=====	614-72860	Ped Push Button		Each	=====	=====	=====
CR100-362			03/14/22	45.00	652.70	652.70	652.70
		WEIGHTED AVERAGE FOR THE FIRST QUARTER		45.00	652.70	652.70	652.70
CC030-081		ADA RAMP AND CURBS - FT. LUPT	04/14/22	5.00	1100.00	671.26	750.00
2670703-479		I-70 BRIDGE OVER HARLAN	05/05/22	10.00	700.00	436.67	514.50
CM760-047		COLFAX AND QUAIL	05/12/22	3.00	900.00	918.80	809.00
NHPP072A-047		SH-72 RESURFACING: I-70 TO IN	06/09/22	14.00	750.00	572.96	572.96
		WEIGHTED AVERAGE FOR THE SECOND QUARTER		32.00	803.13	558.39	604.48
NHPP0063-054		US 6 FROM I70-B TO 33 RD. (MP	08/18/22	6.00	600.00	700.66	605.00

COLORADO DEPARTMENT OF TRANSPORTATION
ITEM UNIT COSTS BY PROJECTS -- 2022 COST DATA

11:31 Wednesday, March 8, 2023 474

PROJECT NUMBER	ITEM NUMBER/ PROJECT LOCATION	ITEM DESCRIPTION/ PROJECT LOCATION	DATE LET	UNIT/ QUANTITY	ENGR. EST.	AVERAGE BID	AWARDED BID
===== 614-72860 Ped Push Button Each =====							
C1211-099		SH 121 NORTH SGA SIGNALS	08/25/22	10.00	800.00	487.50	475.00
SHE2873-193		US 287 & CO 52 INTERSECTION I	09/15/22	8.00	800.00	873.23	344.00
		WEIGHTED AVERAGE FOR THE THIRD QUARTER		24.00	750.00	750.91	463.83
===== 614-72862 Ped Push Button (Spec) Each =====							
FSAM240-200		SH21B CO SPRINGS SIGNAL REPLA	10/27/22	24.00	400.00	1371.25	1355.00
TRG0253-264		I-25 AND SH 119 PARK-N-RIDE	10/27/22	11.00	1000.00	1841.10	1925.00
STU0252-457		I-25:ALAMEDA RIVER PH 2.0	11/03/22	6.00	700.00	555.44	550.00
STAM420-001		US 285 AT HWY 9C IMPROVEMENTS	12/01/22	8.00	550.00	604.71	655.35
BR2854-148		INTERSECTION OF US 285 & SH 9					
STM0091-046		ADA RAMP IMPROVEMENTS - FAIRP					
NHPP0931-033		SH93:US6 TO 58TH RESURFACING	12/15/22	12.00	800.00	358.82	289.20
		WEIGHTED AVERAGE FOR THE FOURTH QUARTER		61.00	636.07	1206.48	1077.18
		WEIGHTED AVERAGE FOR THE YEAR		162.00	690.56	954.49	775.03
===== 614-72863 Ped Push Button Post Assem Each =====							
CC030-081		ADA RAMP AND CURBS - FT. LUPT	04/14/22	8.00	1500.00	1921.38	1600.00
		WEIGHTED AVERAGE FOR THE SECOND QUARTER		8.00	1500.00	1921.38	1600.00
		WEIGHTED AVERAGE FOR THE YEAR		8.00	1500.00	1921.38	1600.00
===== 614-72863 Ped Push Button Post Assem Each =====							
NHPP2873-189		US 287 (FEDERAL BLVD) - COLFA	01/06/22	8.00	2600.00	2310.20	2504.70
CR100-362			03/14/22	62.00	3397.25	3397.25	3397.25
NHM765-007			03/31/22	8.00	3500.00	3582.04	3220.50
		WEIGHTED AVERAGE FOR THE FIRST QUARTER		78.00	3326.02	3140.04	3287.58
CC030-081		ADA RAMP AND CURBS - FT. LUPT	04/14/22	7.00	2000.00	1920.46	1850.00
2670703-479		I-70 BRIDGE OVER HARLAN	05/05/22	10.00	2000.00	1458.29	1705.84
CM760-047		COLFAX AND QUAIL	05/12/22	4.00	2300.00	2969.20	2787.00
NHPP072A-047		SH-72 RESURFACING: I-70 TO IN	06/09/22	21.00	2500.00	1252.60	1252.60
		WEIGHTED AVERAGE FOR THE SECOND QUARTER		42.00	2278.57	1750.13	1606.21

COLORADO DEPARTMENT OF TRANSPORTATION
ITEM UNIT COSTS BY PROJECTS -- 2022 COST DATA

11:31 Wednesday, March 8, 2023 475

PROJECT NUMBER	ITEM NUMBER/ PROJECT LOCATION	ITEM DESCRIPTION/ PROJECT LOCATION	DATE LET	UNIT/ QUANTITY	ENGR. EST.	AVERAGE BID	AWARDED BID
===== 614-72863		Ped Push Button Post Assem		Each	=====		
NHPP0063-054		US 6 FROM I70-B TO 33 RD. (MP	08/18/22	2.00	2000.00	3503.28	3025.00
C1211-099		SH 121 NORTH SGA SIGNALS	08/25/22	28.00	2500.00	2475.00	3350.00
SHE2873-193		US 287 & CO 52 INTERSECTION I	09/15/22	4.00	2000.00	1604.92	1335.00
		WEIGHTED AVERAGE FOR THE THIRD QUARTER		34.00	2411.76	2275.37	3093.82
FSAM240-200		SH21B CO SPRINGS SIGNAL REPLA	10/27/22	17.00	1000.00	1815.25	985.00
TRG0253-264		I-25 AND SH 119 PARK-N-RIDE	10/27/22	1.00	3300.00	1279.42	1350.00
STU0252-457		I-25:ALAMEDA RIVER PH 2.0	11/03/22	2.00	2000.00	2207.04	2200.00
NHPP083A-046		SH83 RESURFACING STROH RD TO	12/08/22	2.00	3300.00	3951.83	3703.65
NHPP0931-033		SH93:US6 TO 58TH RESURFACING	12/15/22	16.00	1500.00	1613.81	1140.00
		WEIGHTED AVERAGE FOR THE FOURTH QUARTER		38.00	1444.74	1773.37	1266.90
		WEIGHTED AVERAGE FOR THE YEAR		192.00	2562.65	2196.58	2485.54
===== 614-72864		Fire Preempt Unit		Each	=====		
SHE2873-193		US 287 & CO 52 INTERSECTION I	09/15/22	1.00	3000.00	11167.72	8100.00
		WEIGHTED AVERAGE FOR THE THIRD QUARTER		1.00	3000.00	11167.72	8100.00
		WEIGHTED AVERAGE FOR THE YEAR		1.00	3000.00	11167.72	8100.00
===== 614-72875		Loop Detect Wire		Lin Foot	=====		
NHPP0702-383		I-70 EB AUX FRISCO TO SILVERT	01/13/22	200.00	10.00	45.55	47.00
NHPP0063-063			02/24/22	1,000.00	4.50	11.25	12.00
NHPP0703-472			03/10/22	1,200.00	6.00	16.85	17.00
		WEIGHTED AVERAGE FOR THE FIRST QUARTER		2,400.00	5.71	19.09	17.42
STM1151-038		SH115 MP 27 TO MP 38	04/21/22	1,400.00	10.00	10.65	11.00
MTCE2873-204		MTCE FY22 SH287 CONC PANEL RE	05/05/22	150.00	60.00	48.08	43.16
		WEIGHTED AVERAGE FOR THE SECOND QUARTER		1,550.00	14.84	12.18	14.11

COLORADO DEPARTMENT OF TRANSPORTATION
 ITEM UNIT COSTS BY PROJECTS -- 2022 COST DATA

11:31 Wednesday, March 8, 2023 476

PROJECT NUMBER	ITEM NUMBER/ PROJECT LOCATION	ITEM DESCRIPTION/ PROJECT LOCATION	DATE LET	UNIT/ QUANTITY	ENGR. EST.	AVERAGE BID	AWARDED BID
===== 614-72875		Loop Detect Wire		Lin Foot	=====		
NHPP0063-054		US 6 FROM I70-B TO 33 RD. (MP 08/18/22		5,447.00	15.00	13.97	12.00
		WEIGHTED AVERAGE FOR THE THIRD QUARTER		5,447.00	15.00	13.97	12.00
STAM420-001		US 285 AT HWY 9C IMPROVEMENTS 12/01/22		100.00	8.50	43.87	47.66
BR2854-148		INTERSECTION OF US 285 & SH 9					
STM0091-046		ADA RAMP IMPROVEMENTS - FAIRP					
NHPP0063-048		US6 / 20 ROAD INTERSECTION IM 12/15/22		1,870.00	12.00	17.96	15.50
NHPP0931-033		SH93:US6 TO 58TH RESURFACING 12/15/22		598.00	20.00	9.76	8.20
		WEIGHTED AVERAGE FOR THE FOURTH QUARTER		2,568.00	13.73	17.06	15.05
		WEIGHTED AVERAGE FOR THE YEAR		11,965.00	12.84	15.58	14.02
===== 614-72884		Detect (Micro Wave)		Each	=====		
NHPP 0761-238 C0761-239		I-76 DAHLIA TO YORK	03/10/22	2.00	12000.00	13217.79	17300.00
		WEIGHTED AVERAGE FOR THE FIRST QUARTER		2.00	12000.00	13217.79	17300.00
2670703-479		I-70 BRIDGE OVER HARLAN	05/05/22	11.00	11000.00	8484.72	8900.00
		WEIGHTED AVERAGE FOR THE SECOND QUARTER		11.00	11000.00	8484.72	8900.00
		WEIGHTED AVERAGE FOR THE YEAR		13.00	11153.85	9408.24	10192.31
===== 614-72885		Detect (Spec)		Each	=====		
MP0503-098			03/24/22	38.00	14500.00	13045.50	12222.00
		WEIGHTED AVERAGE FOR THE FIRST QUARTER		38.00	14500.00	13045.50	12222.00
NHPP072A-047		SH-72 RESURFACING: I-70 TO IN 06/09/22		32.00	9000.00	10182.59	10182.59
		WEIGHTED AVERAGE FOR THE SECOND QUARTER		32.00	9000.00	10182.59	10182.59

COLORADO DEPARTMENT OF TRANSPORTATION
ITEM UNIT COSTS BY PROJECTS -- 2022 COST DATA

11:31 Wednesday, March 8, 2023 477

PROJECT NUMBER	ITEM NUMBER/ PROJECT LOCATION	ITEM DESCRIPTION/ PROJECT LOCATION	DATE LET	UNIT/ QUANTITY	ENGR. EST.	AVERAGE BID	AWARDED BID
=====	614-72885	Detect (Spec)		Each	=====		
FSAM240-200		SH21B CO SPRINGS SIGNAL REPLA	10/27/22	6.00	7000.00	16820.50	16100.00
STRC090-011		US 50B AND SH71/CR18 INTERSEC	11/17/22	2.00	14500.00	15956.50	17100.00
NHPP0931-033		SH93:US6 TO 58TH RESURFACING	12/15/22	11.00	9000.00	10937.86	10030.00
		WEIGHTED AVERAGE FOR THE FOURTH QUARTER		19.00	8947.37	13177.55	12691.05
		WEIGHTED AVERAGE FOR THE YEAR		89.00	11337.08	12589.36	11588.86
=====	614-72886	Intersection Detect Sys (Camera)		Each	=====		
NHPP0063-063			02/24/22	16.00	9000.00	11280.00	12000.00
		WEIGHTED AVERAGE FOR THE FIRST QUARTER		16.00	9000.00	11280.00	12000.00
SHE2873-193		US 287 & CO 52 INTERSECTION I	09/15/22	4.00	9000.00	13430.05	12890.00
		WEIGHTED AVERAGE FOR THE THIRD QUARTER		4.00	9000.00	13430.05	12890.00
STU0252-457		I-25:ALAMEDA RIVER PH 2.0	11/03/22	1.00	10000.00	12621.15	12000.00
		WEIGHTED AVERAGE FOR THE FOURTH QUARTER		1.00	10000.00	12621.15	12000.00
		WEIGHTED AVERAGE FOR THE YEAR		21.00	9047.62	12222.79	12169.52
=====	614-72887	Detect (Microwave Veh)		Each	=====		
NHPP 0761-238 C0761-239		I-76 DAHLIA TO YORK	03/10/22	1.00	8000.00	17198.55	12800.00
		WEIGHTED AVERAGE FOR THE FIRST QUARTER		1.00	8000.00	17198.55	12800.00
STM1151-038		SH115 MP 27 TO MP 38	04/21/22	1.00	10500.00	11093.43	11500.00

COLORADO DEPARTMENT OF TRANSPORTATION
 ITEM UNIT COSTS BY PROJECTS -- 2022 COST DATA

11:31 Wednesday, March 8, 2023 478

PROJECT NUMBER	ITEM NUMBER/ PROJECT LOCATION	ITEM DESCRIPTION/ PROJECT LOCATION	DATE LET	UNIT/ QUANTITY	ENGR. EST.	AVERAGE BID	AWARDED BID
===== 614-72887 2670703-479		Detect (Microwave Veh) I-70 BRIDGE OVER HARLAN	05/05/22	Each 1.00	10000.00	12191.89	14332.75
		WEIGHTED AVERAGE FOR THE SECOND QUARTER		2.00	10250.00	11692.59	12916.38
C1211-099		SH 121 NORTH SGA SIGNALS	08/25/22	31.00	15000.00	8700.00	8900.00
		WEIGHTED AVERAGE FOR THE THIRD QUARTER		31.00	15000.00	8700.00	8900.00
NHPP083A-046		SH83 RESURFACING STROH RD TO	12/08/22	12.00	7000.00	14467.76	13535.51
		WEIGHTED AVERAGE FOR THE FOURTH QUARTER		12.00	7000.00	14467.76	13535.51
		WEIGHTED AVERAGE FOR THE YEAR		46.00	12554.35	10979.36	10368.67
===== 614-72894		Emergency Telephone		Each			
TRG0253-264		I-25 AND SH 119 PARK-N-RIDE	10/27/22	4.00	2000.00	8442.51	8900.00
		WEIGHTED AVERAGE FOR THE FOURTH QUARTER		4.00	2000.00	8442.51	8900.00
		WEIGHTED AVERAGE FOR THE YEAR		4.00	2000.00	8442.51	8900.00
===== 614-72895		Vehicle Detect Sys (Single Camera)		Each			
ITS0703-477		ITS EQUIPMENT UPGRADE AT EJMT	01/06/22	2.00	8500.00	7130.00	7130.00
		WEIGHTED AVERAGE FOR THE FIRST QUARTER		2.00	8500.00	7130.00	7130.00
		WEIGHTED AVERAGE FOR THE YEAR		2.00	8500.00	7130.00	7130.00
===== 614-73000		Piezo (Elec) (CL I) (11 Ft)		Each			
MTCE2873-204		MTCE FY22 SH287 CONC PANEL RE	05/05/22	2.00	6000.00	11012.11	9874.22
		WEIGHTED AVERAGE FOR THE SECOND QUARTER		2.00	6000.00	11012.11	9874.22
		WEIGHTED AVERAGE FOR THE YEAR		2.00	6000.00	11012.11	9874.22

COLORADO DEPARTMENT OF TRANSPORTATION
ITEM UNIT COSTS BY PROJECTS -- 2022 COST DATA

11:31 Wednesday, March 8, 2023 479

PROJECT NUMBER	ITEM NUMBER/ PROJECT LOCATION	ITEM DESCRIPTION/ PROJECT LOCATION	DATE LET	UNIT/ QUANTITY	ENGR. EST.	AVERAGE BID	AWARDED BID
=====	614-73005	Piezo (Elec) (CL II)		Each	=====	=====	=====
NHPP0703-472			03/10/22	6.00	4600.00	2763.30	2800.00
		WEIGHTED AVERAGE FOR THE FIRST QUARTER		6.00	4600.00	2763.30	2800.00
STAM420-001 BR2854-148 STM0091-046		US 285 AT HWY 9C IMPROVEMENTS INTERSECTION OF US 285 & SH 9 ADA RAMP IMPROVEMENTS - FAIRP	12/01/22	2.00	4350.00	4956.73	5361.93
		WEIGHTED AVERAGE FOR THE FOURTH QUARTER		2.00	4350.00	4956.73	5361.93
		WEIGHTED AVERAGE FOR THE YEAR		8.00	4537.50	3311.65	3440.48
=====	614-75868	Inst Fire Preempt Unit		Each	=====	=====	=====
2670703-479		I-70 BRIDGE OVER HARLAN	05/05/22	3.00	1500.00	759.75	894.16
		WEIGHTED AVERAGE FOR THE SECOND QUARTER		3.00	1500.00	759.75	894.16
		WEIGHTED AVERAGE FOR THE YEAR		3.00	1500.00	759.75	894.16
=====	614-80000	Flash Beacon		Each	=====	=====	=====
ITS0703-477 NHPP 0761-238 C0761-239		ITS EQUIPMENT UPGRADE AT EJMT I-76 DAHLIA TO YORK	01/06/22 03/10/22	6.00 2.00	750.00 3400.00	1930.00 4124.60	1930.00 5500.00
		WEIGHTED AVERAGE FOR THE FIRST QUARTER		8.00	1412.50	3526.07	2822.50
NHC540-017		R2 CHAINUP STA @ KENOSHA/HOOS	05/12/22	8.00	4698.00	2933.33	2300.00
		WEIGHTED AVERAGE FOR THE SECOND QUARTER		8.00	4698.00	2933.33	2300.00
FSAM240-200		SH21B CO SPRINGS SIGNAL REPLA	10/27/22	8.00	3000.00	4130.00	2870.00

COLORADO DEPARTMENT OF TRANSPORTATION
ITEM UNIT COSTS BY PROJECTS -- 2022 COST DATA

11:31 Wednesday, March 8, 2023 480

PROJECT NUMBER	ITEM NUMBER/ PROJECT LOCATION	ITEM DESCRIPTION/ PROJECT LOCATION	DATE LET	UNIT/ QUANTITY	ENGR. EST.	AVERAGE BID	AWARDED BID
=====	614-80000	Flash Beacon		Each	=====	=====	=====
C5502-097		US550 MP 117.28-126.06	11/17/22	2.00	4000.00	4571.93	5130.00
STRC090-011		US 50B AND SH71/CR18 INTERSEC	11/17/22	2.00	570.00	4011.50	3990.00
		WEIGHTED AVERAGE FOR THE FOURTH QUARTER		12.00	2761.67	4181.85	3433.33
		WEIGHTED AVERAGE FOR THE YEAR		28.00	2929.43	3677.40	2935.00
=====	614-80001	Flash Beacon (Solar Pwred)		Each	=====	=====	=====
STA0252-459			02/03/22	2.00	3400.00	6680.67	9500.00
NHPP0703-472			03/10/22	6.00	3400.00	5600.29	5500.00
		WEIGHTED AVERAGE FOR THE FIRST QUARTER		8.00	3400.00	5816.37	6500.00
NHPP0063-054		US 6 FROM I70-B TO 33 RD. (MP 08/18/22		1.00	4000.00	10961.23	9500.00
		WEIGHTED AVERAGE FOR THE THIRD QUARTER		1.00	4000.00	10961.23	9500.00
C0831-126		SH83 EL PASO COUNTY TO BAYOU	10/13/22	2.00	8000.00	5850.00	7500.00
		WEIGHTED AVERAGE FOR THE FOURTH QUARTER		2.00	8000.00	5850.00	7500.00
		WEIGHTED AVERAGE FOR THE YEAR		11.00	4290.91	6105.93	6954.55
=====	614-80003	Rect Rapid Flash Beacon		Each	=====	=====	=====
NHPP0063-054		US 6 FROM I70-B TO 33 RD. (MP 08/18/22		12.00	7000.00	12048.28	10400.00
		WEIGHTED AVERAGE FOR THE THIRD QUARTER		12.00	7000.00	12048.28	10400.00
TRG0253-264		I-25 AND SH 119 PARK-N-RIDE	10/27/22	2.00	10000.00	11227.89	11800.00
		WEIGHTED AVERAGE FOR THE FOURTH QUARTER		2.00	10000.00	11227.89	11800.00
		WEIGHTED AVERAGE FOR THE YEAR		14.00	7428.57	11720.12	10600.00

COLORADO DEPARTMENT OF TRANSPORTATION
 ITEM UNIT COSTS BY PROJECTS -- 2022 COST DATA

11:31 Wednesday, March 8, 2023 481

PROJECT NUMBER	ITEM NUMBER/ PROJECT LOCATION	ITEM DESCRIPTION/ PROJECT LOCATION	DATE LET	UNIT/ QUANTITY	ENGR. EST.	AVERAGE BID	AWARDED BID
=====	614-80312	Barricade (Ty 3 F-B)		Each	=====		
STR096A-050		SH 96 MP 168.99 TO 193.77	12/22/22	1.00	2200.00	3693.33	3700.00
		WEIGHTED AVERAGE FOR THE FOURTH QUARTER		1.00	2200.00	3693.33	3700.00
		WEIGHTED AVERAGE FOR THE YEAR		1.00	2200.00	3693.33	3700.00
=====	614-80321	Barricade (Ty 3 M-A)		Each	=====		
CM760-047		COLFAX AND QUAIL	05/12/22	4.00	400.00	1169.60	563.00
		WEIGHTED AVERAGE FOR THE SECOND QUARTER		4.00	400.00	1169.60	563.00
		WEIGHTED AVERAGE FOR THE YEAR		4.00	400.00	1169.60	563.00
=====	614-80385	Rumble Strip		Lin Foot	=====		
NH0504-910		US50B L-24-B MIN REP AT MP 40	01/13/22	1,120.00	3.50	7.08	1.67
STA0252-459			02/03/22	120,000.00	0.30	0.80	1.25
STR0141-031			02/17/22	27,000.00	0.50	0.45	0.35
ER007A-035			03/15/22	74,532.00	0.16	0.16	0.16
STR160A-034		US160A LA VETA PASS EAST SURF	03/17/22	201,136.00	0.50	0.10	0.10
		WEIGHTED AVERAGE FOR THE FIRST QUARTER		423,788.00	0.39	0.47	0.46
NH0504-911			04/07/22	267,040.00	0.32	0.22	0.13
STM1151-038		SH115 MP 27 TO MP 38	04/21/22	116,100.00	0.25	0.25	0.12
STA0712-019		SH 71: Frieght Improvements	05/12/22	17,287.00	0.50	0.58	0.58
STA001A-005		SH1 WELLINGTON SOUTH RESURFAC	05/12/22	11,136.00	0.50	0.69	1.10
NHPP0252-448		I-25 TREX NARROWS BRIDGE PREV	06/23/22	12.00	5.00	604.00	450.00
		WEIGHTED AVERAGE FOR THE SECOND QUARTER		411,575.00	0.31	0.27	0.19
NHPP0701-253		I-70 EAST OF DEBEQUE	10/27/22	50,104.00	0.50	0.30	0.25
NHPP0853-126		US85C: PLATTEVILLE NORTH MP (11/10/22	13,199.00	0.50	0.54	0.55
STR318A-001		SH 318 MP 0 - 12.5 MOFFAT COU	12/01/22	65,352.00	1.00	0.30	0.15
NHPP0502-090		SH 50 MP 134.6-136 GUNNISON C	12/22/22	13,585.00	0.50	1.49	3.80

COLORADO DEPARTMENT OF TRANSPORTATION
 ITEM UNIT COSTS BY PROJECTS -- 2022 COST DATA

11:31 Wednesday, March 8, 2023 482

PROJECT NUMBER	ITEM NUMBER/ PROJECT LOCATION	ITEM DESCRIPTION/ PROJECT LOCATION	DATE LET	UNIT/ QUANTITY	ENGR. EST.	AVERAGE BID	AWARDED BID
===== 614-80385		Rumble Strip		Lin Foot			
BR012A-048		CO 12 STRUCTURE P-17-F AT MP	12/22/22	600.00	3.00	29.45	4.00
	WEIGHTED AVERAGE FOR THE FOURTH QUARTER			142,840.00	0.74	0.54	0.45
	WEIGHTED AVERAGE FOR THE YEAR			978,203.00	0.41	0.40	0.35
===== 614-80387		Rumble Strip (Grind)		Lin Foot			
NHPP1601-083			02/03/22	45.33	7.75	132.35	100.00
	WEIGHTED AVERAGE FOR THE FIRST QUARTER			45.33	7.75	132.35	100.00
STR064A-010		SH 64 AND SH 13 AT MEEKER	11/10/22	82,155.00	1.00	0.22	0.23
STR0641-107		SH 13 MM 104-128.1 IN MOFFAT	12/01/22	77,616.00	0.50	0.31	0.34
	WEIGHTED AVERAGE FOR THE FOURTH QUARTER			159,771.00	0.76	0.27	0.28
	WEIGHTED AVERAGE FOR THE YEAR			159,816.33	0.76	0.30	0.31
===== 614-80390		Rumble Strip (Grinding) (Asphalt) (Sin)		Lin Foot			
STA 067A-048		Hwy 67A MP 0.00 TO MP 11.05 I	03/03/22	15,133.00	0.50	0.65	0.60
	WEIGHTED AVERAGE FOR THE FIRST QUARTER			15,133.00	0.50	0.65	0.60
SHE0242-087		US 24 SAFETY IMPRVMENTS, E OF	11/03/22	1,422.00	0.50	4.13	3.89
NHPP0931-033		SH93:US6 TO 58TH RESURFACING	12/15/22	8,350.00	0.60	1.49	0.67
STA0361-129		US 36: HYGIENE RD AND NELSON	12/22/22	21,100.00	0.40	0.70	0.61
	WEIGHTED AVERAGE FOR THE FOURTH QUARTER			30,872.00	0.46	0.98	0.78
	WEIGHTED AVERAGE FOR THE YEAR			46,005.00	0.47	0.90	0.72
===== 614-80391		Rumble Strip (Grind) (Asphalt)		Lin Foot			
NHPP1601-083			02/03/22	79,044.00	0.60	0.18	0.14

COLORADO DEPARTMENT OF TRANSPORTATION
 ITEM UNIT COSTS BY PROJECTS -- 2022 COST DATA

11:31 Wednesday, March 8, 2023 483

PROJECT NUMBER	ITEM NUMBER/ PROJECT LOCATION	ITEM DESCRIPTION/ PROJECT LOCATION	DATE LET	UNIT/ QUANTITY	ENGR. EST.	AVERAGE BID	AWARDED BID
=====	614-80391	Rumble Strip (Grind) (Asphalt)		Lin Foot	=====	=====	=====
C0762-055			02/17/22	48,190.00	0.25	0.24	0.20
	WEIGHTED AVERAGE FOR THE FIRST QUARTER			127,234.00	0.47	0.21	0.16
STA3852-015		US 385 HOLYOKE NORTH	10/27/22	98,368.00	0.15	0.17	0.17
C5502-097		US550 MP 117.28-126.06	11/17/22	49,588.00	0.50	0.26	0.35
STR114A-015		SH114 SILLSVILLE SOUTH TO MP3	12/01/22	98,419.00	0.30	0.17	0.14
	WEIGHTED AVERAGE FOR THE FOURTH QUARTER			246,375.00	0.28	0.20	0.19
	WEIGHTED AVERAGE FOR THE YEAR			373,609.00	0.34	0.20	0.18
=====	614-80392	Rumble Strip (Grind) (Conc)		Lin Foot	=====	=====	=====
NHPP0701-252		I-70 RIFLE TO SILT SLAB REPLA	12/01/22	95,694.00	0.80	0.94	0.78
	WEIGHTED AVERAGE FOR THE FOURTH QUARTER			95,694.00	0.80	0.94	0.78
	WEIGHTED AVERAGE FOR THE YEAR			95,694.00	0.80	0.94	0.78
=====	614-81000	Sig-Light Pole Steel		Each	=====	=====	=====
NHPP 0761-238		I-76 DAHLIA TO YORK	03/10/22	2.00	12000.00	7162.33	7000.00
C0761-239							
	WEIGHTED AVERAGE FOR THE FIRST QUARTER			2.00	12000.00	7162.33	7000.00
	WEIGHTED AVERAGE FOR THE YEAR			2.00	12000.00	7162.33	7000.00
=====	614-81020	Sig-Light Pole Steel (2)		Each	=====	=====	=====
2670703-479		I-70 BRIDGE OVER HARLAN	05/05/22	1.00	32000.00	50286.61	59154.67
	WEIGHTED AVERAGE FOR THE SECOND QUARTER			1.00	32000.00	50286.61	59154.67
NHPP0063-054		US 6 FROM I70-B TO 33 RD. (MP	08/18/22	1.00	40000.00	64789.56	56000.00
	WEIGHTED AVERAGE FOR THE THIRD QUARTER			1.00	40000.00	64789.56	56000.00
	WEIGHTED AVERAGE FOR THE YEAR			2.00	36000.00	53912.34	57577.34

COLORADO DEPARTMENT OF TRANSPORTATION
ITEM UNIT COSTS BY PROJECTS -- 2022 COST DATA

11:31 Wednesday, March 8, 2023 484

PROJECT NUMBER	ITEM NUMBER/ PROJECT LOCATION	ITEM DESCRIPTION/ PROJECT LOCATION	DATE LET	UNIT/ QUANTITY	ENGR. EST.	AVERAGE BID	AWARDED BID
=====	614-81125	Sig-Light Pole Steel (1-25 Ft)		Each	=====	=====	=====
2670703-479		I-70 BRIDGE OVER HARLAN	05/05/22	1.00	17000.00	26646.28	31363.69
		WEIGHTED AVERAGE FOR THE SECOND QUARTER		1.00	17000.00	26646.28	31363.69
		WEIGHTED AVERAGE FOR THE YEAR		1.00	17000.00	26646.28	31363.69
=====	614-81130	Sig-Light Pole Steel (1-30 Ft)		Each	=====	=====	=====
C1211-099		SH 121 NORTH SGA SIGNALS	08/25/22	2.00	23000.00	22055.00	22110.00
		WEIGHTED AVERAGE FOR THE THIRD QUARTER		2.00	23000.00	22055.00	22110.00
		WEIGHTED AVERAGE FOR THE YEAR		2.00	23000.00	22055.00	22110.00
=====	614-81135	Sig-Light Pole Steel (1-35 Ft)		Each	=====	=====	=====
NHPP072A-047		SH-72 RESURFACING: I-70 TO IN	06/09/22	1.00	17000.00	41053.99	41053.99
		WEIGHTED AVERAGE FOR THE SECOND QUARTER		1.00	17000.00	41053.99	41053.99
C1211-099		SH 121 NORTH SGA SIGNALS	08/25/22	3.00	27000.00	22235.00	22470.00
		WEIGHTED AVERAGE FOR THE THIRD QUARTER		3.00	27000.00	22235.00	22470.00
		WEIGHTED AVERAGE FOR THE YEAR		4.00	24500.00	24923.43	27116.00
=====	614-81140	Sig-Light Pole Steel (1-40 Ft)		Each	=====	=====	=====
2670703-479		I-70 BRIDGE OVER HARLAN	05/05/22	2.00	18000.00	29475.28	34719.09
CM760-047		COLFAX AND QUAIL	05/12/22	1.00	13500.00	29266.19	26640.97
		WEIGHTED AVERAGE FOR THE SECOND QUARTER		3.00	16500.00	29413.78	32026.38
C1211-099		SH 121 NORTH SGA SIGNALS	08/25/22	1.00	30000.00	23955.00	23910.00
		WEIGHTED AVERAGE FOR THE THIRD QUARTER		1.00	30000.00	23955.00	23910.00

COLORADO DEPARTMENT OF TRANSPORTATION
ITEM UNIT COSTS BY PROJECTS -- 2022 COST DATA

11:31 Wednesday, March 8, 2023 485

PROJECT NUMBER	ITEM NUMBER/ PROJECT LOCATION	ITEM DESCRIPTION/ PROJECT LOCATION	DATE LET	UNIT/ QUANTITY	ENGR. EST.	AVERAGE BID	AWARDED BID
===== 614-81140		Sig-Light Pole Steel (1-40 Ft)		Each	=====	=====	=====
NHPP0063-048		US6 / 20 ROAD INTERSECTION IM	12/15/22	1.00	25000.00	28630.86	25740.00
NHPP0931-033		SH93:US6 TO 58TH RESURFACING	12/15/22	1.00	20000.00	25518.82	22920.00
		WEIGHTED AVERAGE FOR THE FOURTH QUARTER		2.00	22500.00	27074.84	24330.00
		WEIGHTED AVERAGE FOR THE YEAR		6.00	20750.00	28316.41	28108.19
===== 614-81145		Sig-Light Pole Steel (1-45 Ft)		Each	=====	=====	=====
NHPP 0761-238		I-76 DAHLIA TO YORK	03/10/22	1.00	22000.00	29369.83	30000.00
C0761-239							
		WEIGHTED AVERAGE FOR THE FIRST QUARTER		1.00	22000.00	29369.83	30000.00
CM760-047		COLFAX AND QUAIL	05/12/22	1.00	20200.00	29865.00	27453.00
		WEIGHTED AVERAGE FOR THE SECOND QUARTER		1.00	20200.00	29865.00	27453.00
STAM420-001		US 285 AT HWY 9C IMPROVEMENTS	12/01/22	1.00	19450.00	35712.51	38725.04
BR2854-148		INTERSECTION OF US 285 & SH 9					
STM0091-046		ADA RAMP IMPROVEMENTS - FAIRP					
NHPP0931-033		SH93:US6 TO 58TH RESURFACING	12/15/22	1.00	25000.00	25939.66	23150.00
		WEIGHTED AVERAGE FOR THE FOURTH QUARTER		2.00	22225.00	30826.08	30937.52
		WEIGHTED AVERAGE FOR THE YEAR		4.00	21662.50	30042.49	29832.01
===== 614-81150		Sig-Light Pole Steel (1-50 Ft)		Each	=====	=====	=====
C1211-099		SH 121 NORTH SGA SIGNALS	08/25/22	1.00	34000.00	25975.00	25950.00
		WEIGHTED AVERAGE FOR THE THIRD QUARTER		1.00	34000.00	25975.00	25950.00
FSAM240-200		SH21B CO SPRINGS SIGNAL REPLA	10/27/22	1.00	25000.00	25243.75	23900.00

COLORADO DEPARTMENT OF TRANSPORTATION
 ITEM UNIT COSTS BY PROJECTS -- 2022 COST DATA

11:31 Wednesday, March 8, 2023 486

PROJECT NUMBER	ITEM NUMBER/ PROJECT LOCATION	ITEM DESCRIPTION/ PROJECT LOCATION	DATE LET	UNIT/ QUANTITY	ENGR. EST.	AVERAGE BID	AWARDED BID
===== 614-81150 Sig-Light Pole Steel (1-50 Ft) Each =====							
STU0252-457		I-25:ALAMEDA RIVER PH 2.0	11/03/22	1.00	30000.00	38921.35	40500.00
STRC090-011		US 50B AND SH71/CR18 INTERSEC	11/17/22	1.00	33000.00	25450.00	25900.00
	WEIGHTED AVERAGE FOR THE FOURTH QUARTER			3.00	29333.33	29848.78	30100.00
	WEIGHTED AVERAGE FOR THE YEAR			4.00	30500.00	29144.46	29062.50
===== 614-81155 Sig-Light Pole Steel (1-55 Ft) Each =====							
2670703-479		I-70 BRIDGE OVER HARLAN	05/05/22	4.00	22000.00	31288.38	33000.00
NHPP072A-047		SH-72 RESURFACING: I-70 TO IN	06/09/22	3.00	20000.00	45548.95	45548.95
	WEIGHTED AVERAGE FOR THE SECOND QUARTER			7.00	21142.86	32872.89	38378.12
C1211-099		SH 121 NORTH SGA SIGNALS	08/25/22	1.00	35000.00	26410.00	25820.00
	WEIGHTED AVERAGE FOR THE THIRD QUARTER			1.00	35000.00	26410.00	25820.00
STU0252-457		I-25:ALAMEDA RIVER PH 2.0	11/03/22	2.00	40000.00	53031.99	55200.00
STRC090-011		US 50B AND SH71/CR18 INTERSEC	11/17/22	1.00	35000.00	26850.00	26700.00
NHPP0063-048		US6 / 20 ROAD INTERSECTION IM	12/15/22	1.00	28000.00	30128.27	26620.00
	WEIGHTED AVERAGE FOR THE FOURTH QUARTER			4.00	35750.00	41033.75	40930.00
	WEIGHTED AVERAGE FOR THE YEAR			12.00	27166.67	34946.17	38182.24
===== 614-81160 Sig-Light Pole Steel (1-60 Ft) Each =====							
2670703-479		I-70 BRIDGE OVER HARLAN	05/05/22	1.00	25000.00	45998.86	54192.93
CM760-047		COLFAX AND QUAIL	05/12/22	1.00	24500.00	48616.60	43328.00
	WEIGHTED AVERAGE FOR THE SECOND QUARTER			2.00	24750.00	47188.74	48760.47
C1211-099		SH 121 NORTH SGA SIGNALS	08/25/22	3.00	37000.00	38415.00	38830.00
	WEIGHTED AVERAGE FOR THE THIRD QUARTER			3.00	37000.00	38415.00	38830.00

COLORADO DEPARTMENT OF TRANSPORTATION
ITEM UNIT COSTS BY PROJECTS -- 2022 COST DATA

11:31 Wednesday, March 8, 2023 487

PROJECT NUMBER	ITEM NUMBER/ PROJECT LOCATION	ITEM DESCRIPTION/ PROJECT LOCATION	DATE LET	UNIT/ QUANTITY	ENGR. EST.	AVERAGE BID	AWARDED BID
=====	614-81160	Sig-Light Pole Steel (1-60 Ft)		Each	=====		
STAM420-001		US 285 AT HWY 9C IMPROVEMENTS	12/01/22	1.00	28000.00	50557.71	54810.82
BR2854-148		INTERSECTION OF US 285 & SH 9					
STM0091-046		ADA RAMP IMPROVEMENTS - FAIRP					
NHPP0931-033		SH93:US6 TO 58TH RESURFACING	12/15/22	1.00	35000.00	44867.14	40620.00
	WEIGHTED AVERAGE FOR THE FOURTH QUARTER			2.00	31500.00	47712.42	47715.41
	WEIGHTED AVERAGE FOR THE YEAR			7.00	31928.57	45250.62	44205.96
=====	614-81165	Sig-Light Pole Steel (1-65 Ft)		Each	=====		
CM760-047		COLFAX AND QUAIL	05/12/22	1.00	22500.00	48901.20	43453.00
	WEIGHTED AVERAGE FOR THE SECOND QUARTER			1.00	22500.00	48901.20	43453.00
C1211-099		SH 121 NORTH SGA SIGNALS	08/25/22	5.00	40000.00	39150.00	39300.00
SHE2873-193		US 287 & CO 52 INTERSECTION I	09/15/22	4.00	26000.00	42469.26	38000.00
	WEIGHTED AVERAGE FOR THE THIRD QUARTER			9.00	33777.78	41493.00	38722.22
STU0252-457		I-25:ALAMEDA RIVER PH 2.0	11/03/22	1.00	60000.00	60421.52	63000.00
STRC090-011		US 50B AND SH71/CR18 INTERSEC	11/17/22	1.00	40000.00	35670.00	36400.00
STAM420-001		US 285 AT HWY 9C IMPROVEMENTS	12/01/22	2.00	46000.00	51102.90	55406.60
BR2854-148		INTERSECTION OF US 285 & SH 9					
STM0091-046		ADA RAMP IMPROVEMENTS - FAIRP					
NHPP0063-048		US6 / 20 ROAD INTERSECTION IM	12/15/22	2.00	30000.00	46461.43	41140.00
	WEIGHTED AVERAGE FOR THE FOURTH QUARTER			6.00	42000.00	49196.15	48748.87
	WEIGHTED AVERAGE FOR THE YEAR			16.00	36156.25	44806.46	42777.89
=====	614-81170	Sig-Light Pole Steel (1-70 Ft)		Each	=====		
C1211-099		SH 121 NORTH SGA SIGNALS	08/25/22	1.00	42000.00	43282.50	43565.00
	WEIGHTED AVERAGE FOR THE THIRD QUARTER			1.00	42000.00	43282.50	43565.00

COLORADO DEPARTMENT OF TRANSPORTATION
 ITEM UNIT COSTS BY PROJECTS -- 2022 COST DATA

11:31 Wednesday, March 8, 2023 488

PROJECT NUMBER	ITEM NUMBER/ PROJECT LOCATION	ITEM DESCRIPTION/ PROJECT LOCATION	DATE LET	UNIT/ QUANTITY	ENGR. EST.	AVERAGE BID	AWARDED BID
=====	614-81170	Sig-Light Pole Steel (1-70 Ft)		Each	=====	=====	=====
FSAM240-200		SH21B CO SPRINGS SIGNAL REPLA	10/27/22	9.00	40000.00	39385.75	34400.00
		WEIGHTED AVERAGE FOR THE FOURTH QUARTER		9.00	40000.00	39385.75	34400.00
		WEIGHTED AVERAGE FOR THE YEAR		10.00	40200.00	39590.84	35316.50
=====	614-81175	Sig-Light Pole Steel (1-75 Ft)		Each	=====	=====	=====
STRC090-011		US 50B AND SH71/CR18 INTERSEC	11/17/22	1.00	45000.00	40065.00	41050.00
		WEIGHTED AVERAGE FOR THE FOURTH QUARTER		1.00	45000.00	40065.00	41050.00
		WEIGHTED AVERAGE FOR THE YEAR		1.00	45000.00	40065.00	41050.00
=====	614-81255	Sig-Light Pole Steel (2-55 Ft)		Each	=====	=====	=====
C1211-099		SH 121 NORTH SGA SIGNALS	08/25/22	1.00	45000.00	61225.00	62450.00
		WEIGHTED AVERAGE FOR THE THIRD QUARTER		1.00	45000.00	61225.00	62450.00
		WEIGHTED AVERAGE FOR THE YEAR		1.00	45000.00	61225.00	62450.00
=====	614-81570	Sig-Light Pole Steel (2-70&75 Ft)		Each	=====	=====	=====
FSAM240-200		SH21B CO SPRINGS SIGNAL REPLA	10/27/22	1.00	70000.00	66742.50	51700.00
		WEIGHTED AVERAGE FOR THE FOURTH QUARTER		1.00	70000.00	66742.50	51700.00
		WEIGHTED AVERAGE FOR THE YEAR		1.00	70000.00	66742.50	51700.00
=====	614-84000	Traf Sig Ped Pole Steel		Each	=====	=====	=====
2670703-479		I-70 BRIDGE OVER HARLAN	05/05/22	2.00	2600.00	2945.64	3464.06
		WEIGHTED AVERAGE FOR THE SECOND QUARTER		2.00	2600.00	2945.64	3464.06
NHPP0063-054		US 6 FROM I70-B TO 33 RD. (MP	08/18/22	4.00	3000.00	5066.72	4400.00

COLORADO DEPARTMENT OF TRANSPORTATION
ITEM UNIT COSTS BY PROJECTS -- 2022 COST DATA

11:31 Wednesday, March 8, 2023 489

PROJECT NUMBER	ITEM NUMBER/ PROJECT LOCATION	ITEM DESCRIPTION/ PROJECT LOCATION	DATE LET	UNIT/ QUANTITY	ENGR. EST.	AVERAGE BID	AWARDED BID
=====	614-84000	Traf Sig Ped Pole Steel		Each =====			
C1211-099		SH 121 NORTH SGA SIGNALS	08/25/22	4.00	2000.00	3400.00	3800.00
		WEIGHTED AVERAGE FOR THE THIRD QUARTER		8.00	2500.00	4233.36	4100.00
FSAM240-200		SH21B CO SPRINGS SIGNAL REPLA	10/27/22	6.00	1400.00	3527.75	2910.00
TRG0253-264		I-25 AND SH 119 PARK-N-RIDE	10/27/22	3.00	3000.00	3719.98	3900.00
STAM420-001		US 285 AT HWY 9C IMPROVEMENTS	12/01/22	5.00	2400.00	3001.58	3336.31
BR2854-148		INTERSECTION OF US 285 & SH 9					
STM0091-046		ADA RAMP IMPROVEMENTS - FAIRP					
NHPP0931-033		SH93:US6 TO 58TH RESURFACING	12/15/22	1.00	3000.00	2448.88	1900.00
		WEIGHTED AVERAGE FOR THE FOURTH QUARTER		15.00	2160.00	3385.73	3182.77
		WEIGHTED AVERAGE FOR THE YEAR		25.00	2304.00	3468.54	3498.79
=====	614-84100	Traf Sig Ped Pole Alum		Each =====			
STU0252-457		I-25:ALAMEDA RIVER PH 2.0	11/03/22	5.00	3000.00	1922.82	1900.00
		WEIGHTED AVERAGE FOR THE FOURTH QUARTER		5.00	3000.00	1922.82	1900.00
		WEIGHTED AVERAGE FOR THE YEAR		5.00	3000.00	1922.82	1900.00
=====	614-85001	Impact Atten		Each =====			
NHPP0702-383		I-70 EB AUX FRISCO TO SILVERT	01/13/22	2.00	30000.00	42494.82	48000.00
NHPP 0761-238		I-76 DAHLIA TO YORK	03/10/22	5.00	22000.00	36252.14	39000.00
C0761-239							
		WEIGHTED AVERAGE FOR THE FIRST QUARTER		7.00	24285.71	37500.68	41571.43
C5502-097		US550 MP 117.28-126.06	11/17/22	2.00	45000.00	45848.12	42650.00
2670703-487		I-70 BRIDGES OVER WARD ROAD-	12/01/22	1.00	5000.00	29691.68	26300.00
NHPP083A-046		SH83 RESURFACING STROH RD TO	12/08/22	1.00	42000.00	45694.23	53888.45
		WEIGHTED AVERAGE FOR THE FOURTH QUARTER		4.00	34250.00	39610.43	41372.11
		WEIGHTED AVERAGE FOR THE YEAR		11.00	27909.09	37936.02	41498.95

COLORADO DEPARTMENT OF TRANSPORTATION
ITEM UNIT COSTS BY PROJECTS -- 2022 COST DATA

11:31 Wednesday, March 8, 2023 490

PROJECT NUMBER	ITEM NUMBER/ PROJECT LOCATION	ITEM DESCRIPTION/ PROJECT LOCATION	DATE LET	UNIT/ QUANTITY	ENGR. EST.	AVERAGE BID	AWARDED BID
=====	614-85003	Impact Atten (LM)		Each	=====	=====	=====
TRG0253-264		I-25 AND SH 119 PARK-N-RIDE	10/27/22	1.00	32000.00	36668.33	44000.00
		WEIGHTED AVERAGE FOR THE FOURTH QUARTER		1.00	32000.00	36668.33	44000.00
		WEIGHTED AVERAGE FOR THE YEAR		1.00	32000.00	36668.33	44000.00
=====	614-86007	Serial to IP Converter		Each	=====	=====	=====
NHPP 0761-238 C0761-239		I-76 DAHLIA TO YORK	03/10/22	1.00	1500.00	3246.88	3900.00
		WEIGHTED AVERAGE FOR THE FIRST QUARTER		1.00	1500.00	3246.88	3900.00
		WEIGHTED AVERAGE FOR THE YEAR		1.00	1500.00	3246.88	3900.00
=====	614-86105	Telemetry (Field)		Each	=====	=====	=====
NHPP2873-189		US 287 (FEDERAL BLVD) - COLFA	01/06/22	1.00	3800.00	6364.72	6005.19
		WEIGHTED AVERAGE FOR THE FIRST QUARTER		1.00	3800.00	6364.72	6005.19
NHC540-017		R2 CHAINUP STA @ KENOSHA/HOOS	05/12/22	3.00	5196.00	2933.33	2800.00
		WEIGHTED AVERAGE FOR THE SECOND QUARTER		3.00	5196.00	2933.33	2800.00
STU0252-457 STAM420-001 BR2854-148 STM0091-046		I-25:ALAMEDA RIVER PH 2.0	11/03/22	2.00	4000.00	8543.93	8500.00
		US 285 AT HWY 9C IMPROVEMENTS	12/01/22	3.00	5570.00	12094.24	13106.94
		INTERSECTION OF US 285 & SH 9					
		ADA RAMP IMPROVEMENTS - FAIRP					
		WEIGHTED AVERAGE FOR THE FOURTH QUARTER		5.00	4942.00	10910.80	11264.16
		WEIGHTED AVERAGE FOR THE YEAR		9.00	4899.78	8008.17	7858.45
=====	614-86106	Telemetry (Field) (Install Only)		Each	=====	=====	=====
NHPP0063-048		US6 / 20 ROAD INTERSECTION IM	12/15/22	1.00	3000.00	4757.88	3080.00
		WEIGHTED AVERAGE FOR THE FOURTH QUARTER		1.00	3000.00	4757.88	3080.00
		WEIGHTED AVERAGE FOR THE YEAR		1.00	3000.00	4757.88	3080.00

COLORADO DEPARTMENT OF TRANSPORTATION
ITEM UNIT COSTS BY PROJECTS -- 2022 COST DATA

11:31 Wednesday, March 8, 2023 491

PROJECT NUMBER	ITEM NUMBER/ PROJECT LOCATION	ITEM DESCRIPTION/ PROJECT LOCATION	DATE LET	UNIT/ QUANTITY	ENGR. EST.	AVERAGE BID	AWARDED BID
=====	614-86248	Traf Ctrler (Type 2070LC)		Each	=====	=====	=====
NHPP2873-189		US 287 (FEDERAL BLVD) - COLFA	01/06/22	1.00	6800.00	6669.34	6294.01
		WEIGHTED AVERAGE FOR THE FIRST QUARTER		1.00	6800.00	6669.34	6294.01
2670703-479		I-70 BRIDGE OVER HARLAN	05/05/22	2.00	7000.00	5706.91	6716.02
CM760-047		COLFAX AND QUAIL	05/12/22	1.00	6300.00	4902.40	4443.00
NHPP072A-047		SH-72 RESURFACING: I-70 TO IN	06/09/22	1.00	8000.00	6532.67	6532.67
		WEIGHTED AVERAGE FOR THE SECOND QUARTER		4.00	7075.00	5529.31	6101.93
C1211-099		SH 121 NORTH SGA SIGNALS	08/25/22	2.00	5000.00	5600.00	5200.00
		WEIGHTED AVERAGE FOR THE THIRD QUARTER		2.00	5000.00	5600.00	5200.00
FSAM240-200		SH21B CO SPRINGS SIGNAL REPLA	10/27/22	3.00	6500.00	5740.50	5175.00
STRC090-011		US 50B AND SH71/CR18 INTERSEC	11/17/22	1.00	5300.00	6297.50	5995.00
STAM420-001		US 285 AT HWY 9C IMPROVEMENTS	12/01/22	1.00	5340.00	7388.12	8102.48
BR2854-148		INTERSECTION OF US 285 & SH 9					
STM0091-046		ADA RAMP IMPROVEMENTS - FAIRP					
		WEIGHTED AVERAGE FOR THE FOURTH QUARTER		5.00	6028.00	6168.53	5924.50
		WEIGHTED AVERAGE FOR THE YEAR		12.00	6270.00	5900.87	5893.68
=====	614-86250	Ctrler (Ramp Metering)		Each	=====	=====	=====
NHPP 0761-238		I-76 DAHLIA TO YORK	03/10/22	1.00	12000.00	7498.20	7900.00
C0761-239							
		WEIGHTED AVERAGE FOR THE FIRST QUARTER		1.00	12000.00	7498.20	7900.00
		WEIGHTED AVERAGE FOR THE YEAR		1.00	12000.00	7498.20	7900.00
=====	614-86741	Weather Monitor System		Each	=====	=====	=====
STM1151-038		SH115 MP 27 TO MP 38	04/21/22	1.00	60000.00	62703.86	68000.00
		WEIGHTED AVERAGE FOR THE SECOND QUARTER		1.00	60000.00	62703.86	68000.00
		WEIGHTED AVERAGE FOR THE YEAR		1.00	60000.00	62703.86	68000.00

COLORADO DEPARTMENT OF TRANSPORTATION
ITEM UNIT COSTS BY PROJECTS -- 2022 COST DATA

11:31 Wednesday, March 8, 2023 492

PROJECT NUMBER	ITEM NUMBER/ PROJECT LOCATION	ITEM DESCRIPTION/ PROJECT LOCATION	DATE LET	UNIT/ QUANTITY	ENGR. EST.	AVERAGE BID	AWARDED BID
=====	614-86752	Fold-Over Tower (ITS)		Each	=====	=====	=====
2670703-497		I-70_GENESEE WILDLIFE XING	09/15/22	2.00	15900.00	29626.92	28690.23
		WEIGHTED AVERAGE FOR THE THIRD QUARTER		2.00	15900.00	29626.92	28690.23
		WEIGHTED AVERAGE FOR THE YEAR		2.00	15900.00	29626.92	28690.23
=====	614-86800	Uninterrupted Power Supply		Each	=====	=====	=====
NHPP2873-189		US 287 (FEDERAL BLVD) - COLFA	01/06/22	1.00	26000.00	10076.25	9508.00
		WEIGHTED AVERAGE FOR THE FIRST QUARTER		1.00	26000.00	10076.25	9508.00
2670703-479 CM760-047		I-70 BRIDGE OVER HARLAN COLFAX AND QUAIL	05/05/22 05/12/22	2.00 1.00	7500.00 7100.00	6924.03 14011.80	8156.11 14059.00
		WEIGHTED AVERAGE FOR THE SECOND QUARTER		3.00	7366.67	9008.67	10123.74
C1211-099		SH 121 NORTH SGA SIGNALS	08/25/22	2.00	7000.00	6900.00	6800.00
		WEIGHTED AVERAGE FOR THE THIRD QUARTER		2.00	7000.00	6900.00	6800.00
TRG0253-264 STRC090-011 STAM420-001 BR2854-148 STM0091-046 NHPP0931-033		I-25 AND SH 119 PARK-N-RIDE US 50B AND SH71/CR18 INTERSEC US 285 AT HWY 9C IMPROVEMENTS INTERSECTION OF US 285 & SH 9 ADA RAMP IMPROVEMENTS - FAIRP SH93:US6 TO 58TH RESURFACING	10/27/22 11/17/22 12/01/22 12/15/22	5.00 1.00 1.00 1.00	8000.00 11000.00 7040.00 10000.00	14598.74 6285.00 9234.24 8796.09	15300.00 6470.00 10008.94 8160.00
		WEIGHTED AVERAGE FOR THE FOURTH QUARTER		8.00	8505.00	13372.82	12642.37
		WEIGHTED AVERAGE FOR THE YEAR		14.00	9295.71	11862.58	11044.15
=====	614-87006	Fiber Optic Term Panel (6 Fiber)		Each	=====	=====	=====
ITS0703-477		ITS EQUIPMENT UPGRADE AT EJMT	01/06/22	12.00	800.00	830.00	830.00
		WEIGHTED AVERAGE FOR THE FIRST QUARTER		12.00	800.00	830.00	830.00

COLORADO DEPARTMENT OF TRANSPORTATION
 ITEM UNIT COSTS BY PROJECTS -- 2022 COST DATA

11:31 Wednesday, March 8, 2023 493

PROJECT NUMBER	ITEM NUMBER/ PROJECT LOCATION	ITEM DESCRIPTION/ PROJECT LOCATION	DATE LET	UNIT/ QUANTITY	ENGR. EST.	AVERAGE BID	AWARDED BID
=====	614-87006	Fiber Optic Term Panel (6 Fiber)		Each	=====		
NHC540-017		R2 CHAINUP STA @ KENOSHA/HOOS	05/12/22	6.00	950.00	2250.00	1750.00
ITS 0741-024		VMS SIGN INSTALLATIONS AND VS	06/02/22	3.00	750.00	715.00	660.00
		WEIGHTED AVERAGE FOR THE SECOND QUARTER		9.00	883.33	1866.25	1386.67
FSAM240-200		SH21B CO SPRINGS SIGNAL REPLA	10/27/22	2.00	600.00	903.75	825.00
		WEIGHTED AVERAGE FOR THE FOURTH QUARTER		2.00	600.00	903.75	825.00
		WEIGHTED AVERAGE FOR THE YEAR		23.00	815.22	1408.64	1047.39
=====	614-87010	Fiber Optic Cable (S Mode) (12 Fiber)		Lin Foot	=====		
NHPP0702-383		I-70 EB AUX FRISCO TO SILVERT	01/13/22	2,800.00	10.00	6.43	6.50
NHPP 0761-238		I-76 DAHLIA TO YORK	03/10/22	225.00	20.00	9.56	8.00
C0761-239							
		WEIGHTED AVERAGE FOR THE FIRST QUARTER		3,025.00	10.74	6.79	6.61
STM1151-038		SH115 MP 27 TO MP 38	04/21/22	675.00	7.00	6.39	6.00
2670703-479		I-70 BRIDGE OVER HARLAN	05/05/22	1,185.00	10.00	7.82	9.20
NHC540-017		R2 CHAINUP STA @ KENOSHA/HOOS	05/12/22	12,585.00	5.00	7.00	6.00
ITS 0741-024		VMS SIGN INSTALLATIONS AND VS	06/02/22	445.00	5.00	8.50	10.00
		WEIGHTED AVERAGE FOR THE SECOND QUARTER		14,890.00	5.49	7.10	6.37
C1211-099		SH 121 NORTH SGA SIGNALS	08/25/22	70.00	10.00	12.50	15.00
2670703-497		I-70_GENESEE WILDLIFE XING	09/15/22	1,280.00	7.40	11.90	11.36
		WEIGHTED AVERAGE FOR THE THIRD QUARTER		1,350.00	7.53	11.91	11.55
TRG0253-264		I-25 AND SH 119 PARK-N-RIDE	10/27/22	2,880.00	8.00	8.97	9.50

COLORADO DEPARTMENT OF TRANSPORTATION
ITEM UNIT COSTS BY PROJECTS -- 2022 COST DATA

11:31 Wednesday, March 8, 2023 494

PROJECT NUMBER	ITEM NUMBER/ PROJECT LOCATION	ITEM DESCRIPTION/ PROJECT LOCATION	DATE LET	UNIT/ QUANTITY	ENGR. EST.	AVERAGE BID	AWARDED BID
===== 2670703-487	614-87010	Fiber Optic Cable (S Mode) (12 Fiber) I-70 BRIDGES OVER WARD ROAD-	12/01/22	Lin Foot 350.00	20.00	7.80	7.70
		WEIGHTED AVERAGE FOR THE FOURTH QUARTER		3,230.00	9.30	8.89	9.30
		WEIGHTED AVERAGE FOR THE YEAR		22,495.00	6.87	7.94	7.14
===== NHPP 0761-238 C0761-239	614-87012	Fiber Optic Term Panel (12 Fiber)		Each			
		I-76 DAHLIA TO YORK	03/10/22	1.00	1400.00	1851.66	1600.00
		WEIGHTED AVERAGE FOR THE FIRST QUARTER		1.00	1400.00	1851.66	1600.00
2670703-479 CM760-047		I-70 BRIDGE OVER HARLAN COLFAX AND QUAIL	05/05/22 05/12/22	2.00 1.00	1100.00 1200.00	1731.61 1334.20	2046.23 1075.00
		WEIGHTED AVERAGE FOR THE SECOND QUARTER		3.00	1133.33	1614.72	1722.49
C1211-099		SH 121 NORTH SGA SIGNALS	08/25/22	2.00	1600.00	1072.50	1145.00
		WEIGHTED AVERAGE FOR THE THIRD QUARTER		2.00	1600.00	1072.50	1145.00
		WEIGHTED AVERAGE FOR THE YEAR		6.00	1333.33	1605.30	1509.58
===== NHPP 0761-238 C0761-239	614-87015	Buffer Tube Fan Out Kit		Each			
		I-76 DAHLIA TO YORK	03/10/22	1.00	200.00	221.75	190.00
		WEIGHTED AVERAGE FOR THE FIRST QUARTER		1.00	200.00	221.75	190.00
STM1151-038		SH115 MP 27 TO MP 38	04/21/22	3.00	450.00	714.29	380.00
		WEIGHTED AVERAGE FOR THE SECOND QUARTER		3.00	450.00	714.29	380.00
C1211-099		SH 121 NORTH SGA SIGNALS	08/25/22	2.00	200.00	607.50	715.00
		WEIGHTED AVERAGE FOR THE THIRD QUARTER		2.00	200.00	607.50	715.00

COLORADO DEPARTMENT OF TRANSPORTATION
ITEM UNIT COSTS BY PROJECTS -- 2022 COST DATA

11:31 Wednesday, March 8, 2023 495

PROJECT NUMBER	ITEM NUMBER/ PROJECT LOCATION	ITEM DESCRIPTION/ PROJECT LOCATION	DATE LET	UNIT/ QUANTITY	ENGR. EST.	AVERAGE BID	AWARDED BID
=====	614-87015	Buffer Tube Fan Out Kit		Each	=====	=====	=====
FSAM240-200		SH21B CO SPRINGS SIGNAL REPLA	10/27/22	2.00	200.00	380.00	490.00
		WEIGHTED AVERAGE FOR THE FOURTH QUARTER		2.00	200.00	380.00	490.00
		WEIGHTED AVERAGE FOR THE YEAR		8.00	293.75	513.10	467.50
=====	614-87024	Fiber Optic Term Panel (24 Fiber)		Each	=====	=====	=====
STM1151-038		SH115 MP 27 TO MP 38	04/21/22	3.00	1020.00	2161.13	1720.00
		WEIGHTED AVERAGE FOR THE SECOND QUARTER		3.00	1020.00	2161.13	1720.00
		WEIGHTED AVERAGE FOR THE YEAR		3.00	1020.00	2161.13	1720.00
=====	614-87100	Auto Traf Rec Sta		Each	=====	=====	=====
STM1151-038		SH115 MP 27 TO MP 38	04/21/22	1.00	15000.00	34779.66	35500.00
		WEIGHTED AVERAGE FOR THE SECOND QUARTER		1.00	15000.00	34779.66	35500.00
		WEIGHTED AVERAGE FOR THE YEAR		1.00	15000.00	34779.66	35500.00
=====	614-87320	CCTV		Each	=====	=====	=====
ITS0703-477		ITS EQUIPMENT UPGRADE AT EJMT	01/06/22	63.00	4000.00	4435.00	4435.00
NHPP 0761-238		I-76 DAHLIA TO YORK	03/10/22	1.00	8000.00	7664.06	5900.00
C0761-239							
		WEIGHTED AVERAGE FOR THE FIRST QUARTER		64.00	4062.50	4798.84	4457.89
STM1151-038		SH115 MP 27 TO MP 38	04/21/22	4.00	5000.00	6075.38	5700.00
2670703-479		I-70 BRIDGE OVER HARLAN	05/05/22	3.00	5000.00	4978.05	5863.75
ITS 0741-024		VMS SIGN INSTALLATIONS AND VS	06/02/22	2.00	5000.00	6607.00	7500.00
NHPP072A-047		SH-72 RESURFACING: I-70 TO IN	06/09/22	1.00	5000.00	6952.21	6952.21
		WEIGHTED AVERAGE FOR THE SECOND QUARTER		10.00	5000.00	5685.88	6234.35

COLORADO DEPARTMENT OF TRANSPORTATION
 ITEM UNIT COSTS BY PROJECTS -- 2022 COST DATA

11:31 Wednesday, March 8, 2023 496

PROJECT NUMBER	ITEM NUMBER/ PROJECT LOCATION	ITEM DESCRIPTION/ PROJECT LOCATION	DATE LET	UNIT/ QUANTITY	ENGR. EST.	AVERAGE BID	AWARDED BID
=====	614-87320	CCTV		Each	=====	=====	=====
2670703-497		I-70_GENESEE WILDLIFE KING	09/15/22	1.00	5500.00	10436.94	10543.30
		WEIGHTED AVERAGE FOR THE THIRD QUARTER		1.00	5500.00	10436.94	10543.30
TRG0253-264		I-25 AND SH 119 PARK-N-RIDE	10/27/22	8.00	5000.00	3091.12	3300.00
2670703-487		I-70 BRIDGES OVER WARD ROAD-	12/01/22	1.00	6500.00	5831.15	5810.00
		WEIGHTED AVERAGE FOR THE FOURTH QUARTER		9.00	5166.67	3289.67	3578.89
		WEIGHTED AVERAGE FOR THE YEAR		84.00	4309.52	4659.24	4647.64
=====	614-87321	CCTV (Inst)		Each	=====	=====	=====
FSAM240-200		SH21B CO SPRINGS SIGNAL REPLA	10/27/22	2.00	950.00	3640.00	3220.00
		WEIGHTED AVERAGE FOR THE FOURTH QUARTER		2.00	950.00	3640.00	3220.00
		WEIGHTED AVERAGE FOR THE YEAR		2.00	950.00	3640.00	3220.00
=====	614-87325	CCTV Pole		Each	=====	=====	=====
STM1151-038		SH115 MP 27 TO MP 38	04/21/22	2.00	6700.00	51362.00	56000.00
		WEIGHTED AVERAGE FOR THE SECOND QUARTER		2.00	6700.00	51362.00	56000.00
		WEIGHTED AVERAGE FOR THE YEAR		2.00	6700.00	51362.00	56000.00
=====	614-87333	CCTV Camera (Traf Surveil)		Each	=====	=====	=====
ITS0703-477		ITS EQUIPMENT UPGRADE AT EJMT	01/06/22	45.00	8000.00	7680.00	7680.00
		WEIGHTED AVERAGE FOR THE FIRST QUARTER		45.00	8000.00	7680.00	7680.00
CM760-047		COLFAX AND QUAIL	05/12/22	1.00	7500.00	6417.60	5531.00
		WEIGHTED AVERAGE FOR THE SECOND QUARTER		1.00	7500.00	6417.60	5531.00

COLORADO DEPARTMENT OF TRANSPORTATION
ITEM UNIT COSTS BY PROJECTS -- 2022 COST DATA

11:31 Wednesday, March 8, 2023 497

PROJECT NUMBER	ITEM NUMBER/ PROJECT LOCATION	ITEM DESCRIPTION/ PROJECT LOCATION	DATE LET	UNIT/ QUANTITY	ENGR. EST.	AVERAGE BID	AWARDED BID
===== 614-87333		CCTV Camera (Traf Surveil)		Each	=====	=====	=====
C1211-099		SH 121 NORTH SGA SIGNALS	08/25/22	5.00	6500.00	5700.00	5400.00
2670703-497		I-70_GENESEE WILDLIFE XING	09/15/22	2.00	6000.00	13319.82	12161.93
		WEIGHTED AVERAGE FOR THE THIRD QUARTER		7.00	6357.14	10144.90	7331.98
TRG0253-264		I-25 AND SH 119 PARK-N-RIDE	10/27/22	2.00	7500.00	6284.39	6700.00
STU0252-457		I-25:ALAMEDA RIVER PH 2.0	11/03/22	1.00	5500.00	10533.41	10600.00
		WEIGHTED AVERAGE FOR THE FOURTH QUARTER		3.00	6833.33	6955.29	8000.00
		WEIGHTED AVERAGE FOR THE YEAR		56.00	7723.21	8100.17	7615.27
===== 614-87350		Test Fiber Optic Cable		LUMP SUM	=====	=====	=====
ITS0703-477		ITS EQUIPMENT UPGRADE AT EJMT	01/06/22	1.00	20000.00	19400.00	19400.00
NHPP0702-383		I-70 EB AUX FRISCO TO SILVERT	01/13/22	1.00	5000.00	18394.36	6200.00
NHPP 0761-238		I-76 DAHLIA TO YORK	03/10/22	1.00	5000.00	3436.99	6100.00
C0761-239							
NHM765-007			03/31/22	1.00	10000.00	27895.58	25080.00
		WEIGHTED AVERAGE FOR THE FIRST QUARTER		4.00	10000.00	13091.44	14195.00
STM1151-038		SH115 MP 27 TO MP 38	04/21/22	1.00	10000.00	23545.98	22500.00
2670703-479		I-70 BRIDGE OVER HARLAN	05/05/22	1.00	10000.00	10761.18	12683.20
NHC540-017		R2 CHAINUP STA @ KENOSHA/HOOS	05/12/22	1.00	12280.00	23666.67	16000.00
ITS 0741-024		VMS SIGN INSTALLATIONS AND VS	06/02/22	1.00	7500.00	5335.00	4500.00
		WEIGHTED AVERAGE FOR THE SECOND QUARTER		4.00	9945.00	16497.94	13920.80
NHPP0702-414		VAIL PASS AUX PHASE 1 CAP 3	07/08/22	1.00	15279.60	15279.60	15279.60
FBR0702-423		VAIL PASS AUX BE F-12-AT PHAS					
C1211-099		SH 121 NORTH SGA SIGNALS	08/25/22	1.00	6000.00	4000.00	5000.00
2670703-497		I-70_GENESEE WILDLIFE XING	09/15/22	1.00	10000.00	17374.29	15505.99
		WEIGHTED AVERAGE FOR THE THIRD QUARTER		3.00	10426.53	14489.96	11928.53

COLORADO DEPARTMENT OF TRANSPORTATION
ITEM UNIT COSTS BY PROJECTS -- 2022 COST DATA

11:31 Wednesday, March 8, 2023 498

PROJECT NUMBER	ITEM NUMBER/ PROJECT LOCATION	ITEM DESCRIPTION/ PROJECT LOCATION	DATE LET	UNIT/ QUANTITY	ENGR. EST.	AVERAGE BID	AWARDED BID
===== 614-87350		Test Fiber Optic Cable		LUMP SUM	=====		
TRG0253-264		I-25 AND SH 119 PARK-N-RIDE	10/27/22	1.00	12500.00	9963.90	10600.00
STU0252-457		I-25:ALAMEDA RIVER PH 2.0	11/03/22	1.00	8000.00	13777.30	13700.00
2670703-487		I-70 BRIDGES OVER WARD ROAD-	12/01/22	1.00	13000.00	10272.91	10300.00
	WEIGHTED AVERAGE FOR THE FOURTH QUARTER			3.00	11166.67	10775.48	11533.33
	WEIGHTED AVERAGE FOR THE YEAR			14.00	10325.69	13624.22	13060.63
===== 614-87364		CCTV Pole w Low Dev (50 Ft)		Each	=====		
2670703-487		I-70 BRIDGES OVER WARD ROAD-	12/01/22	1.00	30000.00	28817.79	28900.00
	WEIGHTED AVERAGE FOR THE FOURTH QUARTER			1.00	30000.00	28817.79	28900.00
	WEIGHTED AVERAGE FOR THE YEAR			1.00	30000.00	28817.79	28900.00
===== 614-87400		Brkaway Taper ITS Pole Steel (30 Ft)		Each	=====		
NHPP 0761-238 C0761-239		I-76 DAHLIA TO YORK	03/10/22	1.00	8000.00	7076.32	8300.00
	WEIGHTED AVERAGE FOR THE FIRST QUARTER			1.00	8000.00	7076.32	8300.00
	WEIGHTED AVERAGE FOR THE YEAR			1.00	8000.00	7076.32	8300.00
===== 614-87401		Fiber Optic Cable (Spec)		Lin Foot	=====		
NHPP0702-414 FBR0702-423		VAIL PASS AUX PHASE 1 CAP 3	07/08/22	22,000.00	4.80	4.80	4.80
		VAIL PASS AUX BE F-12-AT PHAS					
	WEIGHTED AVERAGE FOR THE THIRD QUARTER			22,000.00	4.80	4.80	4.80
	WEIGHTED AVERAGE FOR THE YEAR			22,000.00	4.80	4.80	4.80
===== 614-87402		Brkaway Taper ITS Pole Steel (40 Ft)		Each	=====		
2670703-479		I-70 BRIDGE OVER HARLAN	05/05/22	1.00	6000.00	13930.83	16396.00

COLORADO DEPARTMENT OF TRANSPORTATION
ITEM UNIT COSTS BY PROJECTS -- 2022 COST DATA

11:31 Wednesday, March 8, 2023 499

PROJECT NUMBER	ITEM NUMBER/ PROJECT LOCATION	ITEM DESCRIPTION/ PROJECT LOCATION	DATE LET	UNIT/ QUANTITY	ENGR. EST.	AVERAGE BID	AWARDED BID
=====	614-87402	Brkaway Taper ITS Pole Steel (40 Ft)		Each =====			
ITS 0741-024		VMS SIGN INSTALLATIONS AND VS	06/02/22	2.00	7000.00	11235.00	8035.00
	WEIGHTED AVERAGE FOR THE SECOND QUARTER			3.00	6666.67	12852.50	10822.00
	WEIGHTED AVERAGE FOR THE YEAR			3.00	6666.67	12852.50	10822.00
=====	614-87404	Brkaway Taper Pole Steel (50 Ft)		Each =====			
TRG0253-264		I-25 AND SH 119 PARK-N-RIDE	10/27/22	2.00	15000.00	9321.45	9800.00
	WEIGHTED AVERAGE FOR THE FOURTH QUARTER			2.00	15000.00	9321.45	9800.00
	WEIGHTED AVERAGE FOR THE YEAR			2.00	15000.00	9321.45	9800.00
=====	614-87424	Fiber Optic Cable (S Mode) (24 S)		Lin Foot =====			
NHM765-007			03/31/22	430.00	20.00	11.41	10.26
	WEIGHTED AVERAGE FOR THE FIRST QUARTER			430.00	20.00	11.41	10.26
	WEIGHTED AVERAGE FOR THE YEAR			430.00	20.00	11.41	10.26
=====	614-87425	Fiber Optic Cable (M Mode) (24 S)		Lin Foot =====			
ITS0703-477		ITS EQUIPMENT UPGRADE AT EJMT	01/06/22	10,835.00	8.00	4.00	4.00
	WEIGHTED AVERAGE FOR THE FIRST QUARTER			10,835.00	8.00	4.00	4.00
	WEIGHTED AVERAGE FOR THE YEAR			10,835.00	8.00	4.00	4.00
=====	614-87448	Fiber Optic Cable (S Mode) (48 S)		Lin Foot =====			
NHPP0702-383		I-70 EB AUX FRISCO TO SILVERT	01/13/22	2,200.00	5.00	7.01	7.00
	WEIGHTED AVERAGE FOR THE FIRST QUARTER			2,200.00	5.00	7.01	7.00
	WEIGHTED AVERAGE FOR THE YEAR			2,200.00	5.00	7.01	7.00
=====	614-87495	Fiber Optic Cable (S Mode) (96 S) (Inst)		Lin Foot =====			
NHM765-007			03/31/22	8,000.00	1.00	6.35	5.70
	WEIGHTED AVERAGE FOR THE FIRST QUARTER			8,000.00	1.00	6.35	5.70
	WEIGHTED AVERAGE FOR THE YEAR			8,000.00	1.00	6.35	5.70

COLORADO DEPARTMENT OF TRANSPORTATION
 ITEM UNIT COSTS BY PROJECTS -- 2022 COST DATA

11:31 Wednesday, March 8, 2023 500

PROJECT NUMBER	ITEM NUMBER/ PROJECT LOCATION	ITEM DESCRIPTION/ PROJECT LOCATION	DATE LET	UNIT/ QUANTITY	ENGR. EST.	AVERAGE BID	AWARDED BID
===== 614-87496 Fiber Optic Cable (S Mode) (96 S) Lin Foot =====							
NHM765-007			03/31/22	1,500.00	50.00	10.80	9.69
	WEIGHTED AVERAGE FOR THE FIRST QUARTER			1,500.00	50.00	10.80	9.69
STM1151-038		SH115 MP 27 TO MP 38	04/21/22	31,205.00	4.50	5.41	5.00
	WEIGHTED AVERAGE FOR THE SECOND QUARTER			31,205.00	4.50	5.41	5.00
STU0252-457		I-25:ALAMEDA RIVER PH 2.0	11/03/22	750.00	10.00	13.18	13.00
2670703-487		I-70 BRIDGES OVER WARD ROAD-	12/01/22	1,100.00	15.00	7.81	7.90
	WEIGHTED AVERAGE FOR THE FOURTH QUARTER			1,850.00	12.97	9.37	9.97
	WEIGHTED AVERAGE FOR THE YEAR			34,555.00	6.93	5.74	5.47
===== 614-87498 Fiber Optic Cable (S Mode) (144 S) Lin Foot =====							
NHPP0702-414		VAIL PASS AUX PHASE 1 CAP 3	07/08/22	5,300.00	3.06	3.06	3.06
FBR0702-423		VAIL PASS AUX BE F-12-AT PHAS					
2670703-497		I-70_GENESEE WILDLIFE XING	09/15/22	1,734.00	4.60	14.82	14.77
	WEIGHTED AVERAGE FOR THE THIRD QUARTER			7,034.00	3.44	11.24	5.95
2670703-487		I-70 BRIDGES OVER WARD ROAD-	12/01/22	1,500.00	16.00	7.83	8.00
	WEIGHTED AVERAGE FOR THE FOURTH QUARTER			1,500.00	16.00	7.83	8.00
	WEIGHTED AVERAGE FOR THE YEAR			8,534.00	5.65	10.22	6.31
===== 614-87506 Splice FO Cable (6 S) Each =====							
FSAM240-200		SH21B CO SPRINGS SIGNAL REPLA	10/27/22	2.00	1000.00	1411.25	825.00
	WEIGHTED AVERAGE FOR THE FOURTH QUARTER			2.00	1000.00	1411.25	825.00
	WEIGHTED AVERAGE FOR THE YEAR			2.00	1000.00	1411.25	825.00

COLORADO DEPARTMENT OF TRANSPORTATION
ITEM UNIT COSTS BY PROJECTS -- 2022 COST DATA

11:31 Wednesday, March 8, 2023 501

PROJECT NUMBER	ITEM NUMBER/ PROJECT LOCATION	ITEM DESCRIPTION/ PROJECT LOCATION	DATE LET	UNIT/ QUANTITY	ENGR. EST.	AVERAGE BID	AWARDED BID
=====	614-87512	Splice FO Cable (12 S)		Each	=====	=====	=====
NHPP0702-383		I-70 EB AUX FRISCO TO SILVERT	01/13/22	2.00	2000.00	2493.28	2200.00
NHPP 0761-238		I-76 DAHLIA TO YORK	03/10/22	1.00	2600.00	1472.25	1250.00
C0761-239							
		WEIGHTED AVERAGE FOR THE FIRST QUARTER		3.00	2200.00	2039.49	1883.33
C1211-099		SH 121 NORTH SGA SIGNALS	08/25/22	2.00	2000.00	950.00	1100.00
		WEIGHTED AVERAGE FOR THE THIRD QUARTER		2.00	2000.00	950.00	1100.00
		WEIGHTED AVERAGE FOR THE YEAR		5.00	2120.00	1841.40	1570.00
=====	614-87524	Splice FO Cable (24 Strand)		Each	=====	=====	=====
NHM765-007			03/31/22	16.00	4000.00	3550.34	3192.00
		WEIGHTED AVERAGE FOR THE FIRST QUARTER		16.00	4000.00	3550.34	3192.00
		WEIGHTED AVERAGE FOR THE YEAR		16.00	4000.00	3550.34	3192.00
=====	614-87548	Splice FO Cable (48 Strand)		Each	=====	=====	=====
NHPP0702-383		I-70 EB AUX FRISCO TO SILVERT	01/13/22	1.00	5000.00	5383.77	4300.00
		WEIGHTED AVERAGE FOR THE FIRST QUARTER		1.00	5000.00	5383.77	4300.00
		WEIGHTED AVERAGE FOR THE YEAR		1.00	5000.00	5383.77	4300.00
=====	614-87612	Term FO Cable (12 S)		Each	=====	=====	=====
NHPP0702-383		I-70 EB AUX FRISCO TO SILVERT	01/13/22	2.00	2000.00	2263.15	2100.00
		WEIGHTED AVERAGE FOR THE FIRST QUARTER		2.00	2000.00	2263.15	2100.00
		WEIGHTED AVERAGE FOR THE YEAR		2.00	2000.00	2263.15	2100.00
=====	614-87624	Term FO Cable (24 Strand)		Each	=====	=====	=====
NHM765-007			03/31/22	3.00	4000.00	9192.86	8265.00
		WEIGHTED AVERAGE FOR THE FIRST QUARTER		3.00	4000.00	9192.86	8265.00
		WEIGHTED AVERAGE FOR THE YEAR		3.00	4000.00	9192.86	8265.00

COLORADO DEPARTMENT OF TRANSPORTATION
ITEM UNIT COSTS BY PROJECTS -- 2022 COST DATA

11:31 Wednesday, March 8, 2023 502

PROJECT NUMBER	ITEM NUMBER/ PROJECT LOCATION	ITEM DESCRIPTION/ PROJECT LOCATION	DATE LET	UNIT/ QUANTITY	ENGR. EST.	AVERAGE BID	AWARDED BID
=====	614-87648	Term FO Cable (48 Strand)		Each	=====	=====	=====
NHPP0702-383		I-70 EB AUX FRISCO TO SILVERT	01/13/22	1.00	3000.00	4459.50	3500.00
		WEIGHTED AVERAGE FOR THE FIRST QUARTER		1.00	3000.00	4459.50	3500.00
		WEIGHTED AVERAGE FOR THE YEAR		1.00	3000.00	4459.50	3500.00
=====	614-87650	Fiber Optic Cable (S Mode) (216 S)		Lin Foot	=====	=====	=====
2670703-497		I-70_GENESEE WILDLIFE XING	09/15/22	1,986.00	9.00	14.89	14.77
		WEIGHTED AVERAGE FOR THE THIRD QUARTER		1,986.00	9.00	14.89	14.77
		WEIGHTED AVERAGE FOR THE YEAR		1,986.00	9.00	14.89	14.77
=====	614-87690	Ethernet Switch		Each	=====	=====	=====
NHPP2873-189		US 287 (FEDERAL BLVD) - COLFA	01/06/22	1.00	5000.00	7840.84	7398.93
		WEIGHTED AVERAGE FOR THE FIRST QUARTER		1.00	5000.00	7840.84	7398.93
CM760-047		COLFAX AND QUAIL	05/12/22	1.00	5000.00	6850.60	6125.00
		WEIGHTED AVERAGE FOR THE SECOND QUARTER		1.00	5000.00	6850.60	6125.00
C1211-099		SH 121 NORTH SGA SIGNALS	08/25/22	2.00	7000.00	9552.50	9700.00
2670703-497		I-70_GENESEE WILDLIFE XING	09/15/22	1.00	4900.00	12136.27	11531.53
		WEIGHTED AVERAGE FOR THE THIRD QUARTER		3.00	6300.00	11196.72	10310.51
		WEIGHTED AVERAGE FOR THE YEAR		5.00	5780.00	9439.01	8891.09
=====	614-87691	Ethernet Switch Type I		Each	=====	=====	=====
ITS0703-477		ITS EQUIPMENT UPGRADE AT EJMT	01/06/22	11.00	5500.00	4260.00	4260.00
		WEIGHTED AVERAGE FOR THE FIRST QUARTER		11.00	5500.00	4260.00	4260.00

COLORADO DEPARTMENT OF TRANSPORTATION
 ITEM UNIT COSTS BY PROJECTS -- 2022 COST DATA

11:31 Wednesday, March 8, 2023 503

PROJECT NUMBER	ITEM NUMBER/ PROJECT LOCATION	ITEM DESCRIPTION/ PROJECT LOCATION	DATE LET	UNIT/ QUANTITY	ENGR. EST.	AVERAGE BID	AWARDED BID
===== 614-87691		Ethernet Switch Type I		Each	=====	=====	=====
STM1151-038		SH115 MP 27 TO MP 38	04/21/22	1.00	3500.00	6236.84	6500.00
ITS 0741-024		VMS SIGN INSTALLATIONS AND VS	06/02/22	3.00	10000.00	6665.50	5445.00
		WEIGHTED AVERAGE FOR THE SECOND QUARTER		4.00	8375.00	6470.65	5708.75
		WEIGHTED AVERAGE FOR THE YEAR		15.00	6266.67	5365.33	4646.33
===== 614-87692		Ethernet Switch Type II		Each	=====	=====	=====
ITS0703-477		ITS EQUIPMENT UPGRADE AT EJMT	01/06/22	36.00	6000.00	3475.00	3475.00
NHPP 0761-238		I-76 DAHLIA TO YORK	03/10/22	1.00	8000.00	7080.85	6400.00
C0761-239							
		WEIGHTED AVERAGE FOR THE FIRST QUARTER		37.00	6054.05	4130.61	3554.05
STM1151-038		SH115 MP 27 TO MP 38	04/21/22	2.00	7500.00	6336.84	6500.00
2670703-479		I-70 BRIDGE OVER HARLAN	05/05/22	2.00	4800.00	7028.08	8266.08
NHC540-017		R2 CHAINUP STA @ KENOSHA/HOOS	05/12/22	2.00	5100.00	7466.67	5400.00
		WEIGHTED AVERAGE FOR THE SECOND QUARTER		6.00	5800.00	6875.19	6722.03
TRG0253-264		I-25 AND SH 119 PARK-N-RIDE	10/27/22	5.00	5000.00	13276.47	14000.00
		WEIGHTED AVERAGE FOR THE FOURTH QUARTER		5.00	5000.00	13276.47	14000.00
		WEIGHTED AVERAGE FOR THE YEAR		48.00	5912.50	8083.13	5038.17
===== 614-87693		Ethernet Switch Type III		Each	=====	=====	=====
FSAM240-200		SH21B CO SPRINGS SIGNAL REPLA	10/27/22	3.00	5000.00	9184.25	7700.00
STRC090-011		US 50B AND SH71/CR18 INTERSEC	11/17/22	1.00	6600.00	8200.00	10000.00
		WEIGHTED AVERAGE FOR THE FOURTH QUARTER		4.00	5400.00	9043.64	8275.00
		WEIGHTED AVERAGE FOR THE YEAR		4.00	5400.00	9043.64	8275.00

COLORADO DEPARTMENT OF TRANSPORTATION
 ITEM UNIT COSTS BY PROJECTS -- 2022 COST DATA

11:31 Wednesday, March 8, 2023 504

PROJECT NUMBER	ITEM NUMBER/ PROJECT LOCATION	ITEM DESCRIPTION/ PROJECT LOCATION	DATE LET	UNIT/ QUANTITY	ENGR. EST.	AVERAGE BID	AWARDED BID
=====	614-87698	Ethernet Agg Switch Type II		Each	=====	=====	=====
ITS0703-477		ITS EQUIPMENT UPGRADE AT EJMT	01/06/22	3.00	15000.00	9985.00	9985.00
	WEIGHTED AVERAGE FOR THE FIRST QUARTER			3.00	15000.00	9985.00	9985.00
	WEIGHTED AVERAGE FOR THE YEAR			3.00	15000.00	9985.00	9985.00
=====	614-87700	Ethernet Router		Each	=====	=====	=====
CM760-047		COLFAX AND QUAIL	05/12/22	1.00	3800.00	3030.40	2988.00
	WEIGHTED AVERAGE FOR THE SECOND QUARTER			1.00	3800.00	3030.40	2988.00
	WEIGHTED AVERAGE FOR THE YEAR			1.00	3800.00	3030.40	2988.00
=====	614-87704	Ethernet Radio (Single Client)		Each	=====	=====	=====
CM760-047		COLFAX AND QUAIL	05/12/22	1.00	2700.00	4968.00	3648.00
	WEIGHTED AVERAGE FOR THE SECOND QUARTER			1.00	2700.00	4968.00	3648.00
	WEIGHTED AVERAGE FOR THE YEAR			1.00	2700.00	4968.00	3648.00
=====	614-87708	Cellular Modem (CDMA)		Each	=====	=====	=====
ITS 0741-024		VMS SIGN INSTALLATIONS AND VS	06/02/22	1.00	5000.00	5277.00	6500.00
	WEIGHTED AVERAGE FOR THE SECOND QUARTER			1.00	5000.00	5277.00	6500.00
STRC090-011		US 50B AND SH71/CR18 INTERSEC	11/17/22	1.00	5000.00	2987.50	1200.00
	WEIGHTED AVERAGE FOR THE FOURTH QUARTER			1.00	5000.00	2987.50	1200.00
	WEIGHTED AVERAGE FOR THE YEAR			2.00	5000.00	4132.25	3850.00
=====	615-00030	Emb Prot Ty 3		Each	=====	=====	=====
NHPP0702-383		I-70 EB AUX FRISCO TO SILVERT	01/13/22	1.00	2100.00	4233.41	3600.00

COLORADO DEPARTMENT OF TRANSPORTATION
 ITEM UNIT COSTS BY PROJECTS -- 2022 COST DATA

11:31 Wednesday, March 8, 2023 505

PROJECT NUMBER	ITEM NUMBER/ PROJECT LOCATION	ITEM DESCRIPTION/ PROJECT LOCATION	DATE LET	UNIT/ QUANTITY	ENGR. EST.	AVERAGE BID	AWARDED BID
=====	615-00030	Emb Prot Ty 3		Each =====			
NHPP1601-083			02/03/22	2.00	2250.00	7789.16	5200.00
C0762-055			02/17/22	9.00	1750.00	2126.08	2800.00
NHPP 0761-238		I-76 DAHLIA TO YORK	03/10/22	5.00	2400.00	2215.25	2200.00
C0761-239							
		WEIGHTED AVERAGE FOR THE FIRST QUARTER		17.00	2020.59	2558.50	2952.94
STM1151-038		SH115 MP 27 TO MP 38	04/21/22	14.00	4000.00	1589.92	1331.35
		WEIGHTED AVERAGE FOR THE SECOND QUARTER		14.00	4000.00	1589.92	1331.35
BR0343-046		US 34 TIMBER BRIDGE REPL. PKG	08/31/22	3.00	1675.54	2271.46	2271.46
FBR0343-047		US 6/US 34 TIMBER BRIDGE REPL					
2670403-065		US40_FLOYD HILL ROUNDABOUTS	09/15/22	1.00	3000.00	3351.00	1890.00
		WEIGHTED AVERAGE FOR THE THIRD QUARTER		4.00	2006.66	2811.23	2176.10
2670703-487		I-70 BRIDGES OVER WARD ROAD-	12/01/22	3.00	3000.00	1889.25	1650.00
IM025A-050		I25-MP103.9 - INTERSECTION DR	12/01/22	1.00	1800.00	4996.67	990.00
		WEIGHTED AVERAGE FOR THE FOURTH QUARTER		4.00	2700.00	2823.74	1788.00
		WEIGHTED AVERAGE FOR THE YEAR		39.00	2799.40	2228.18	2162.08
=====	615-00050	Emb Prot Ty 5		Each =====			
NHPP0702-383		I-70 EB AUX FRISCO TO SILVERT	01/13/22	4.00	2500.00	3710.71	4600.00
NHPP 0761-238		I-76 DAHLIA TO YORK	03/10/22	1.00	2800.00	3952.54	1400.00
C0761-239							
		WEIGHTED AVERAGE FOR THE FIRST QUARTER		5.00	2560.00	3779.80	3960.00
STR0711-022		SH 71 OVER THE ARKANSAS	08/04/22	6.00	3000.00	5608.33	2500.00
2670403-065		US40_FLOYD HILL ROUNDABOUTS	09/15/22	3.00	4000.00	1087.67	1700.00
		WEIGHTED AVERAGE FOR THE THIRD QUARTER		9.00	3333.33	4101.44	2233.33

PROJECT NUMBER	ITEM NUMBER/ PROJECT LOCATION	ITEM DESCRIPTION/ PROJECT LOCATION	DATE LET	UNIT/ QUANTITY	ENGR. EST.	AVERAGE BID	AWARDED BID
=====	615-00050	Emb Prot Ty 5		Each	=====		
STAM420-001 BR2854-148 STM0091-046 STR096A-050		US 285 AT HWY 9C IMPROVEMENTS INTERSECTION OF US 285 & SH 9 ADA RAMP IMPROVEMENTS - FAIRP SH 96 MP 168.99 TO 193.77	12/01/22 12/22/22	1.00 1.00	1627.00 3000.00	3358.97 2225.00	4217.79 3000.00
		WEIGHTED AVERAGE FOR THE FOURTH QUARTER		2.00	2313.50	2872.98	3608.90
		WEIGHTED AVERAGE FOR THE YEAR		16.00	2964.19	3817.49	2944.86
=====	615-00150	Emb Prot (Spec)		Each	=====		
NHPP0705-088		I-70 AGATE STRUCTURE REHAB	10/27/22	6.00	3600.00	6744.60	7700.00
		WEIGHTED AVERAGE FOR THE FOURTH QUARTER		6.00	3600.00	6744.60	7700.00
		WEIGHTED AVERAGE FOR THE YEAR		6.00	3600.00	6744.60	7700.00
=====	615-00600	Log Dam		Each	=====		
NHPP0702-414 FBR0702-423		VAIL PASS AUX PHASE 1 CAP 3 VAIL PASS AUX BE F-12-AT PHAS	07/08/22	8.00	818.55	818.55	818.55
		WEIGHTED AVERAGE FOR THE THIRD QUARTER		8.00	818.55	818.55	818.55
		WEIGHTED AVERAGE FOR THE YEAR		8.00	818.55	818.55	818.55
=====	615-20804	8 In Sl Hdgate (4 Ft)		Each	=====		
C5502-097		US550 MP 117.28-126.06	11/17/22	1.00	500.00	6162.88	8200.00
		WEIGHTED AVERAGE FOR THE FOURTH QUARTER		1.00	500.00	6162.88	8200.00
		WEIGHTED AVERAGE FOR THE YEAR		1.00	500.00	6162.88	8200.00
=====	615-20899	8 In Sl Hdgate Spec		Each	=====		
C5502-097		US550 MP 117.28-126.06	11/17/22	6.00	500.00	1976.22	2080.00
		WEIGHTED AVERAGE FOR THE FOURTH QUARTER		6.00	500.00	1976.22	2080.00
		WEIGHTED AVERAGE FOR THE YEAR		6.00	500.00	1976.22	2080.00

COLORADO DEPARTMENT OF TRANSPORTATION
 ITEM UNIT COSTS BY PROJECTS -- 2022 COST DATA

11:31 Wednesday, March 8, 2023 507

PROJECT NUMBER	ITEM NUMBER/ PROJECT LOCATION	ITEM DESCRIPTION/ PROJECT LOCATION	DATE LET	UNIT/ QUANTITY	ENGR. EST.	AVERAGE BID	AWARDED BID
=====	615-21203	12 In Sl Hdgate (3 Ft)		Each	=====	=====	=====
C5502-097		US550 MP 117.28-126.06	11/17/22	3.00	500.00	6754.65	9010.00
		WEIGHTED AVERAGE FOR THE FOURTH QUARTER		3.00	500.00	6754.65	9010.00
		WEIGHTED AVERAGE FOR THE YEAR		3.00	500.00	6754.65	9010.00
=====	615-21503	15 In Sl Hdgate (3 Ft)		Each	=====	=====	=====
C5502-097		US550 MP 117.28-126.06	11/17/22	2.00	500.00	6926.09	9290.00
		WEIGHTED AVERAGE FOR THE FOURTH QUARTER		2.00	500.00	6926.09	9290.00
		WEIGHTED AVERAGE FOR THE YEAR		2.00	500.00	6926.09	9290.00
=====	615-21803	18 In Sl Hdgate (3 Ft)		Each	=====	=====	=====
SHE2873-193		US 287 & CO 52 INTERSECTION I	09/15/22	3.00	4000.00	2942.34	2600.00
		WEIGHTED AVERAGE FOR THE THIRD QUARTER		3.00	4000.00	2942.34	2600.00
C5502-097		US550 MP 117.28-126.06	11/17/22	1.00	10000.00	7253.42	9590.00
		WEIGHTED AVERAGE FOR THE FOURTH QUARTER		1.00	10000.00	7253.42	9590.00
		WEIGHTED AVERAGE FOR THE YEAR		4.00	5500.00	3558.21	4347.50
=====	615-22404	24 In Sl Hdgate (4 Ft)		Each	=====	=====	=====
SHE2873-193		US 287 & CO 52 INTERSECTION I	09/15/22	3.00	5000.00	3824.38	3300.00
		WEIGHTED AVERAGE FOR THE THIRD QUARTER		3.00	5000.00	3824.38	3300.00
		WEIGHTED AVERAGE FOR THE YEAR		3.00	5000.00	3824.38	3300.00
=====	615-52412	24x12 In Parshall Flume		Each	=====	=====	=====
SHE2873-193		US 287 & CO 52 INTERSECTION I	09/15/22	2.00	12000.00	10696.61	9135.00
		WEIGHTED AVERAGE FOR THE THIRD QUARTER		2.00	12000.00	10696.61	9135.00
		WEIGHTED AVERAGE FOR THE YEAR		2.00	12000.00	10696.61	9135.00

COLORADO DEPARTMENT OF TRANSPORTATION
ITEM UNIT COSTS BY PROJECTS -- 2022 COST DATA

11:31 Wednesday, March 8, 2023 508

PROJECT NUMBER	ITEM NUMBER/ PROJECT LOCATION	ITEM DESCRIPTION/ PROJECT LOCATION	DATE LET	UNIT/ QUANTITY	ENGR. EST.	AVERAGE BID	AWARDED BID
=====	616-23180	18 In Plastic Siphon Pipe		Lin Foot	=====		
C5502-097		US550 MP 117.28-126.06	11/17/22	112.00	100.00	190.00	173.00
		WEIGHTED AVERAGE FOR THE FOURTH QUARTER		112.00	100.00	190.00	173.00
		WEIGHTED AVERAGE FOR THE YEAR		112.00	100.00	190.00	173.00
=====	616-30018	18 In Trash Guard		Each	=====		
C5502-097		US550 MP 117.28-126.06	11/17/22	2.00	2000.00	5139.76	6100.00
		WEIGHTED AVERAGE FOR THE FOURTH QUARTER		2.00	2000.00	5139.76	6100.00
		WEIGHTED AVERAGE FOR THE YEAR		2.00	2000.00	5139.76	6100.00
=====	616-30499	Trash Guard Spec		Each	=====		
FSA052A-057 SHE2873-193		SH52 BOX CULVERT EXTENSION (M US 287 & CO 52 INTERSECTION I	08/04/22 09/15/22	1.00 1.00	3000.00 1000.00	4511.11 4395.75	3577.60 6400.00
		WEIGHTED AVERAGE FOR THE THIRD QUARTER		2.00	2000.00	4434.20	4988.80
		WEIGHTED AVERAGE FOR THE YEAR		2.00	2000.00	4434.20	4988.80
=====	618-00003	Prestress Steel		M Kip Foot	=====		
NHPP0702-414 FBR0702-423		VAIL PASS AUX PHASE 1 CAP 3 VAIL PASS AUX BE F-12-AT PHAS	07/08/22	3,872.00	77.42	77.42	77.42
		WEIGHTED AVERAGE FOR THE THIRD QUARTER		3,872.00	77.42	77.42	77.42
		WEIGHTED AVERAGE FOR THE YEAR		3,872.00	77.42	77.42	77.42
=====	618-01137	Prestress Concrete I (CBT 37.5)		Lin Foot	=====		
NHPP 0761-238 C0761-239		I-76 DAHLIA TO YORK	03/10/22	2,614.00	320.00	428.80	395.00
		WEIGHTED AVERAGE FOR THE FIRST QUARTER		2,614.00	320.00	428.80	395.00

COLORADO DEPARTMENT OF TRANSPORTATION
 ITEM UNIT COSTS BY PROJECTS -- 2022 COST DATA

11:31 Wednesday, March 8, 2023 509

PROJECT NUMBER	ITEM NUMBER/ PROJECT LOCATION	ITEM DESCRIPTION/ PROJECT LOCATION	DATE LET	UNIT/ QUANTITY	ENGR. EST.	AVERAGE BID	AWARDED BID
=====	618-01137	Prestress Concrete I (CBT 37.5)		Lin Foot	=====		
2670703-487		I-70 BRIDGES OVER WARD ROAD-	12/01/22	2,936.00	420.00	416.87	380.00
		WEIGHTED AVERAGE FOR THE FOURTH QUARTER		2,936.00	420.00	416.87	380.00
		WEIGHTED AVERAGE FOR THE YEAR		5,550.00	372.90	423.88	387.06
=====	618-01145	Prestress Conc I (CBT45)		Lin Foot	=====		
BR012A-048		CO 12 STRUCTURE P-17-F AT MP	12/22/22	408.00	350.00	873.50	1120.00
		WEIGHTED AVERAGE FOR THE FOURTH QUARTER		408.00	350.00	873.50	1120.00
		WEIGHTED AVERAGE FOR THE YEAR		408.00	350.00	873.50	1120.00
=====	618-01154	Prestress Conc I (CBT54)		Lin Foot	=====		
2670703-497		I-70_GENESEE WILDLIFE XING	09/15/22	1,390.00	380.00	469.94	466.06
		WEIGHTED AVERAGE FOR THE THIRD QUARTER		1,390.00	380.00	469.94	466.06
		WEIGHTED AVERAGE FOR THE YEAR		1,390.00	380.00	469.94	466.06
=====	618-01163	Prestress Conc I (CBT63)		Lin Foot	=====		
STM1151-038		SH115 MP 27 TO MP 38	04/21/22	875.00	425.00	464.30	550.00
		WEIGHTED AVERAGE FOR THE SECOND QUARTER		875.00	425.00	464.30	550.00
STAM420-001		US 285 AT HWY 9C IMPROVEMENTS	12/01/22	995.00	600.00	548.90	500.00
BR2854-148		INTERSECTION OF US 285 & SH 9					
STM0091-046		ADA RAMP IMPROVEMENTS - FAIRP					
IM025A-050		I25-MP103.9 - INTERSECTION DR	12/01/22	1,346.00	350.00	515.00	440.00
		WEIGHTED AVERAGE FOR THE FOURTH QUARTER		2,341.00	456.26	542.53	513.00
		WEIGHTED AVERAGE FOR THE YEAR		3,216.00	447.75	527.98	518.40

COLORADO DEPARTMENT OF TRANSPORTATION
ITEM UNIT COSTS BY PROJECTS -- 2022 COST DATA

11:31 Wednesday, March 8, 2023 510

PROJECT NUMBER	ITEM NUMBER/ PROJECT LOCATION	ITEM DESCRIPTION/ PROJECT LOCATION	DATE LET	UNIT/ QUANTITY	ENGR. EST.	AVERAGE BID	AWARDED BID
=====	618-01992	Prestress Conc Box (Depth Less Than 32")		Sq Foot	=====		
2670703-479		I-70 BRIDGE OVER HARLAN	05/05/22	17,820.00	80.00	96.36	80.00
		WEIGHTED AVERAGE FOR THE SECOND QUARTER		17,820.00	80.00	96.36	80.00
STU0252-457		I-25:ALAMEDA RIVER PH 2.0	11/03/22	12,993.00	110.00	96.38	89.00
		WEIGHTED AVERAGE FOR THE FOURTH QUARTER		12,993.00	110.00	96.38	89.00
		WEIGHTED AVERAGE FOR THE YEAR		30,813.00	92.65	96.36	83.80
=====	618-10372	Precast Concrete U Girder (U72) (Curved)		Lin Foot	=====		
NHPP0702-414 FBR0702-423		VAIL PASS AUX PHASE 1 CAP 3 VAIL PASS AUX BE F-12-AT PHAS	07/08/22	1,626.00	1363.39	1363.39	1363.39
		WEIGHTED AVERAGE FOR THE THIRD QUARTER		1,626.00	1363.39	1363.39	1363.39
		WEIGHTED AVERAGE FOR THE YEAR		1,626.00	1363.39	1363.39	1363.39
=====	619-00007	Connect To Existing Waterline		Each	=====		
NHPP0063-054		US 6 FROM I70-B TO 33 RD. (MP 08/18/22)		19.00	2500.00	3464.75	3000.00
		WEIGHTED AVERAGE FOR THE THIRD QUARTER		19.00	2500.00	3464.75	3000.00
TRG0253-264		I-25 AND SH 119 PARK-N-RIDE	10/27/22	1.00	4000.00	4642.89	2700.00
		WEIGHTED AVERAGE FOR THE FOURTH QUARTER		1.00	4000.00	4642.89	2700.00
		WEIGHTED AVERAGE FOR THE YEAR		20.00	2575.00	3669.64	2985.00
=====	619-06060	6 In Duct Iron Pipe		Lin Foot	=====		
TRG0253-264		I-25 AND SH 119 PARK-N-RIDE	10/27/22	25.00	640.00	263.20	134.00
		WEIGHTED AVERAGE FOR THE FOURTH QUARTER		25.00	640.00	263.20	134.00
		WEIGHTED AVERAGE FOR THE YEAR		25.00	640.00	263.20	134.00

COLORADO DEPARTMENT OF TRANSPORTATION
 ITEM UNIT COSTS BY PROJECTS -- 2022 COST DATA

11:31 Wednesday, March 8, 2023 511

PROJECT NUMBER	ITEM NUMBER/ PROJECT LOCATION	ITEM DESCRIPTION/ PROJECT LOCATION	DATE LET	UNIT/ QUANTITY	ENGR. EST.	AVERAGE BID	AWARDED BID
=====	619-30320	4 In Galv Pipe		Lin Foot	=====		
NHPP0705-088		I-70 AGATE STRUCTURE REHAB	10/27/22	33.00	300.00	386.01	210.00
STA0711-021		SH71: REGION LINE NORTH	12/01/22	9.00	350.00	391.67	400.00
		WEIGHTED AVERAGE FOR THE FOURTH QUARTER		42.00	310.71	386.97	250.71
		WEIGHTED AVERAGE FOR THE YEAR		42.00	310.71	386.97	250.71
=====	619-30480	6 In Galv Pipe		Lin Foot	=====		
NHPP0705-088		I-70 AGATE STRUCTURE REHAB	10/27/22	15.00	400.00	529.81	238.00
		WEIGHTED AVERAGE FOR THE FOURTH QUARTER		15.00	400.00	529.81	238.00
		WEIGHTED AVERAGE FOR THE YEAR		15.00	400.00	529.81	238.00
=====	619-40060	3/4 In Copper Pipe		Lin Foot	=====		
NHPP0063-054		US 6 FROM I70-B TO 33 RD. (MP 08/18/22		560.00	100.00	111.82	97.00
		WEIGHTED AVERAGE FOR THE THIRD QUARTER		560.00	100.00	111.82	97.00
		WEIGHTED AVERAGE FOR THE YEAR		560.00	100.00	111.82	97.00
=====	619-50100	1-1/4 In Plastic Pipe		Lin Foot	=====		
C5502-111		US 550 MP 81 AND 89 RED MOUNT	10/27/22	866.00	50.00	70.00	100.00
		WEIGHTED AVERAGE FOR THE FOURTH QUARTER		866.00	50.00	70.00	100.00
		WEIGHTED AVERAGE FOR THE YEAR		866.00	50.00	70.00	100.00
=====	619-50235	3 In Plastic Pipe (Spec)		Lin Foot	=====		
NH0504-911			04/07/22	40.00	30.00	76.60	33.20
		WEIGHTED AVERAGE FOR THE SECOND QUARTER		40.00	30.00	76.60	33.20
		WEIGHTED AVERAGE FOR THE YEAR		40.00	30.00	76.60	33.20

COLORADO DEPARTMENT OF TRANSPORTATION
 ITEM UNIT COSTS BY PROJECTS -- 2022 COST DATA

11:31 Wednesday, March 8, 2023 512

PROJECT NUMBER	ITEM NUMBER/ PROJECT LOCATION	ITEM DESCRIPTION/ PROJECT LOCATION	DATE LET	UNIT/ QUANTITY	ENGR. EST.	AVERAGE BID	AWARDED BID
=====	619-50320	4 In Plastic Pipe		Lin Foot	=====		
NHPP0063-054		US 6 FROM I70-B TO 33 RD. (MP 08/18/22		619.00	60.00	297.46	257.00
	WEIGHTED AVERAGE FOR THE THIRD QUARTER			619.00	60.00	297.46	257.00
	WEIGHTED AVERAGE FOR THE YEAR			619.00	60.00	297.46	257.00
=====	619-50480	6 In Plastic Pipe		Lin Foot	=====		
NHPP0063-054		US 6 FROM I70-B TO 33 RD. (MP 08/18/22		646.00	80.00	149.93	165.00
	WEIGHTED AVERAGE FOR THE THIRD QUARTER			646.00	80.00	149.93	165.00
C5502-111		US 550 MP 81 AND 89 RED MOUNT 10/27/22		24.00	100.00	127.50	200.00
	WEIGHTED AVERAGE FOR THE FOURTH QUARTER			24.00	100.00	127.50	200.00
	WEIGHTED AVERAGE FOR THE YEAR			670.00	80.72	149.13	166.25
=====	619-50640	8 In Plastic Pipe		Lin Foot	=====		
NHPP0063-054		US 6 FROM I70-B TO 33 RD. (MP 08/18/22		3,083.00	100.00	294.05	255.00
	WEIGHTED AVERAGE FOR THE THIRD QUARTER			3,083.00	100.00	294.05	255.00
	WEIGHTED AVERAGE FOR THE YEAR			3,083.00	100.00	294.05	255.00
=====	619-50800	10 In Plastic Pipe		Lin Foot	=====		
NHPP0063-054		US 6 FROM I70-B TO 33 RD. (MP 08/18/22		2,436.00	120.00	276.09	240.00
	WEIGHTED AVERAGE FOR THE THIRD QUARTER			2,436.00	120.00	276.09	240.00
TRG0253-264		I-25 AND SH 119 PARK-N-RIDE 10/27/22		45.00	200.00	199.09	165.00
	WEIGHTED AVERAGE FOR THE FOURTH QUARTER			45.00	200.00	199.09	165.00
	WEIGHTED AVERAGE FOR THE YEAR			2,481.00	121.45	270.79	238.64

COLORADO DEPARTMENT OF TRANSPORTATION
 ITEM UNIT COSTS BY PROJECTS -- 2022 COST DATA

11:31 Wednesday, March 8, 2023 513

PROJECT NUMBER	ITEM NUMBER/ PROJECT LOCATION	ITEM DESCRIPTION/ PROJECT LOCATION	DATE LET	UNIT/ QUANTITY	ENGR. EST.	AVERAGE BID	AWARDED BID
=====	619-51200	15 In Plastic Pipe		Lin Foot	=====		
NHPP0063-054		US 6 FROM I70-B TO 33 RD. (MP 08/18/22		453.00	270.00	294.05	255.00
	WEIGHTED AVERAGE FOR THE THIRD QUARTER			453.00	270.00	294.05	255.00
	WEIGHTED AVERAGE FOR THE YEAR			453.00	270.00	294.05	255.00
=====	619-71516	2 In Air and Vacuum Valve		Each	=====		
NHPP0063-054		US 6 FROM I70-B TO 33 RD. (MP 08/18/22		4.00	2000.00	6567.10	5700.00
	WEIGHTED AVERAGE FOR THE THIRD QUARTER			4.00	2000.00	6567.10	5700.00
	WEIGHTED AVERAGE FOR THE YEAR			4.00	2000.00	6567.10	5700.00
=====	619-75048	6 In Gate Valve		Each	=====		
NHPP0063-054		US 6 FROM I70-B TO 33 RD. (MP 08/18/22		5.00	1100.00	2326.10	2010.00
	WEIGHTED AVERAGE FOR THE THIRD QUARTER			5.00	1100.00	2326.10	2010.00
TRG0253-264		I-25 AND SH 119 PARK-N-RIDE 10/27/22		1.00	1040.00	3281.40	2850.00
	WEIGHTED AVERAGE FOR THE FOURTH QUARTER			1.00	1040.00	3281.40	2850.00
	WEIGHTED AVERAGE FOR THE YEAR			6.00	1090.00	2750.68	2150.00
=====	619-75064	8 In Gate Valve		Each	=====		
NHPP0063-054		US 6 FROM I70-B TO 33 RD. (MP 08/18/22		5.00	1300.00	4051.06	3500.00
	WEIGHTED AVERAGE FOR THE THIRD QUARTER			5.00	1300.00	4051.06	3500.00
	WEIGHTED AVERAGE FOR THE YEAR			5.00	1300.00	4051.06	3500.00
=====	619-75080	10 In Gate Valve		Each	=====		
NHPP0063-054		US 6 FROM I70-B TO 33 RD. (MP 08/18/22		10.00	1600.00	5796.31	5000.00
	WEIGHTED AVERAGE FOR THE THIRD QUARTER			10.00	1600.00	5796.31	5000.00
	WEIGHTED AVERAGE FOR THE YEAR			10.00	1600.00	5796.31	5000.00

COLORADO DEPARTMENT OF TRANSPORTATION
 ITEM UNIT COSTS BY PROJECTS -- 2022 COST DATA

11:31 Wednesday, March 8, 2023 514

PROJECT NUMBER	ITEM NUMBER/ PROJECT LOCATION	ITEM DESCRIPTION/ PROJECT LOCATION	DATE LET	UNIT/ QUANTITY	ENGR. EST.	AVERAGE BID	AWARDED BID
=====	619-75116	16 In Gate Valve		Each	=====	=====	=====
NHPP0063-054		US 6 FROM I70-B TO 33 RD.	MP 08/18/22	1.00	4000.00	20906.78	18000.00
	WEIGHTED AVERAGE FOR THE THIRD QUARTER			1.00	4000.00	20906.78	18000.00
	WEIGHTED AVERAGE FOR THE YEAR			1.00	4000.00	20906.78	18000.00
=====	619-77210	Restrained Plug (Spec)		Each	=====	=====	=====
TRG0253-264		I-25 AND SH 119 PARK-N-RIDE	10/27/22	1.00	4300.00	3484.26	5400.00
	WEIGHTED AVERAGE FOR THE FOURTH QUARTER			1.00	4300.00	3484.26	5400.00
	WEIGHTED AVERAGE FOR THE YEAR			1.00	4300.00	3484.26	5400.00
=====	619-78036	4-1/2 In Fire Hydrant		Each	=====	=====	=====
NHPP0063-054		US 6 FROM I70-B TO 33 RD.	MP 08/18/22	8.00	3500.00	8176.13	6300.00
	WEIGHTED AVERAGE FOR THE THIRD QUARTER			8.00	3500.00	8176.13	6300.00
	WEIGHTED AVERAGE FOR THE YEAR			8.00	3500.00	8176.13	6300.00
=====	619-78048	6 In Fire Hydrant		Each	=====	=====	=====
TRG0253-264		I-25 AND SH 119 PARK-N-RIDE	10/27/22	1.00	14000.00	10844.10	10000.00
	WEIGHTED AVERAGE FOR THE FOURTH QUARTER			1.00	14000.00	10844.10	10000.00
	WEIGHTED AVERAGE FOR THE YEAR			1.00	14000.00	10844.10	10000.00
=====	620-00001	Field Office (CL 1)		Each	=====	=====	=====
STR R500-171		Various locations on SH 141 a	03/17/22	1.00	22000.00	26705.59	25000.00
	WEIGHTED AVERAGE FOR THE FIRST QUARTER			1.00	22000.00	26705.59	25000.00
C0831-126		SH83 EL PASO COUNTY TO BAYOU	10/13/22	1.00	24000.00	21250.00	20500.00

COLORADO DEPARTMENT OF TRANSPORTATION
ITEM UNIT COSTS BY PROJECTS -- 2022 COST DATA

11:31 Wednesday, March 8, 2023 515

PROJECT NUMBER	ITEM NUMBER/ PROJECT LOCATION	ITEM DESCRIPTION/ PROJECT LOCATION	DATE LET	UNIT/ QUANTITY	ENGR. EST.	AVERAGE BID	AWARDED BID
===== 620-00001 Field Office (CL 1) Each =====							
NHPP0705-088		I-70 AGATE STRUCTURE REHAB	10/27/22	1.00	23400.00	61024.40	41000.00
C5502-111		US 550 MP 81 AND 89 RED MOUNT	10/27/22	1.00	25000.00	32750.00	35500.00
C170A-002		CRITICAL CULVERT CONST. PKG D	10/27/22	1.00	30000.00	19512.50	17500.00
NHPP0343-048		US 34 (MP 169.3-171.4)	11/01/22	1.00	36500.00	42697.61	18000.00
NHM175-029		CANON CITY, CO	12/15/22	1.00	25000.00	31500.00	30000.00
	WEIGHTED AVERAGE FOR THE FOURTH QUARTER			6.00	27316.67	36885.45	27083.33
	WEIGHTED AVERAGE FOR THE YEAR			7.00	26557.14	35431.18	26785.71
===== 620-00002 Field Office (CL 2) Each =====							
NHPP2873-189		US 287 (FEDERAL BLVD) - COLFA	01/06/22	1.00	34000.00	55339.61	66548.99
NH0504-910		US50B L-24-B MIN REP AT MP 40	01/13/22	1.00	30000.00	26746.98	25000.00
NHPP0702-383		I-70 EB AUX FRISCO TO SILVERT	01/13/22	1.00	30000.00	165227.43	110000.00
NHPP1601-083			02/03/22	1.00	60000.00	44551.88	48000.00
STA0252-459			02/03/22	1.00	28000.00	69230.00	68000.00
C0762-055			02/17/22	1.00	25000.00	28626.00	50000.00
STR0141-031			02/17/22	1.00	30000.00	36666.67	16000.00
NHPP0063-063			02/24/22	1.00	35000.00	32790.00	44000.00
STA 067A-048		Hwy 67A MP 0.00 TO MP 11.05 I	03/03/22	1.00	30000.00	29874.04	31092.95
NHPP0703-472			03/10/22	1.00	28000.00	33934.57	35000.00
STR160A-034		US160A LA VETA PASS EAST SURF	03/17/22	1.00	50000.00	29154.19	24308.38
BRC040-057			03/17/22	1.00	25000.00	36893.25	40000.00
STR092A-031			03/17/22	1.00	40000.00	40000.00	40000.00
NHM765-007			03/31/22	1.00	40000.00	125944.44	64410.00
	WEIGHTED AVERAGE FOR THE FIRST QUARTER			14.00	34642.86	56196.34	47311.45
STM1151-038		SH115 MP 27 TO MP 38	04/21/22	1.00	30000.00	103706.90	88888.00
STA0712-019		SH 71: Frieight Improvements	05/12/22	1.00	30000.00	40697.08	40697.08
STA001A-005		SH1 WELLINGTON SOUTH RESURFAC	05/12/22	1.00	40000.00	29576.40	35000.00
NHC540-017		R2 CHAINUP STA @ KENOSHA/HOOS	05/12/22	1.00	29727.00	76666.67	95000.00
CM760-047		COLFAX AND QUAIL	05/12/22	1.00	27000.00	22771.60	10608.00
NHPP 3851-018		US 385 NORTH OF CHEYENNE WELL	05/26/22	1.00	30000.00	37000.00	34000.00
FSA052A-046		SH52 WCR 37 INTERSECTION IMPR	06/09/22	1.00	35000.00	39115.80	26540.00
	WEIGHTED AVERAGE FOR THE SECOND QUARTER			7.00	31675.29	53557.45	47247.58
NHPP0063-054		US 6 FROM I70-B TO 33 RD. (MP	08/18/22	1.00	30000.00	163718.09	116000.00

PROJECT NUMBER	ITEM NUMBER/ PROJECT LOCATION	ITEM DESCRIPTION/ PROJECT LOCATION	DATE LET	UNIT/ QUANTITY	ENGR. EST.	AVERAGE BID	AWARDED BID
===== 620-00002		Field Office (CL 2)		Each =====			
FBR0761-236		I-76 OVER CLR CRK SCOUR MIT	08/25/22	1.00	28000.00	41333.33	39000.00
C1211-099		SH 121 NORTH SGA SIGNALS	08/25/22	1.00	36250.00	40000.00	35000.00
ER0502-092		US 50 MP 204 EB MONARCH TRUCK	08/29/22	1.00	25000.00	13877.42	16132.26
BR0343-046		US 34 TIMBER BRIDGE REPL. PKG	08/31/22	2.00	10613.03	15493.60	15493.60
FBR0343-047		US 6/US 34 TIMBER BRIDGE REPL					
NHPPR100-266		R1 ESSENTIAL REPAIRS	09/01/22	1.00	25000.00	31316.27	31348.80
2670403-065		US40 FLOYD HILL ROUNDABOUTS	09/15/22	1.00	60000.00	67827.81	34500.00
2670703-497		I-70_GENESEE WILDLIFE KING	09/15/22	1.00	60000.00	110682.70	70804.77
SHE2873-193		US 287 & CO 52 INTERSECTION I	09/15/22	1.00	40000.00	55772.98	28500.00
NHPP0701-231		I-70 SALT WASH BRIDGES SCOUR	09/29/22	1.00	50000.00	41673.32	25000.00
		WEIGHTED AVERAGE FOR THE THIRD QUARTER		11.00	34134.19	63462.16	38843.00
NHPP0821-114		SH 82 ASPEN/INDEPENDENCE PASS	10/13/22	1.00	45000.00	15333.33	1000.00
NHPP0701-253		I-70 EAST OF DEBEQUE	10/27/22	1.00	45000.00	36215.00	50000.00
STA207A-004		Resurfacing SH207A MANZANOLA	10/27/22	1.00	30000.00	55500.00	52500.00
TRG0253-264		I-25 AND SH 119 PARK-N-RIDE	10/27/22	1.00	35000.00	115778.03	500.00
STA3852-015		US 385 HOLYOKE NORTH	10/27/22	1.00	50000.00	25000.00	25000.00
SHE0242-087		US 24 SAFETY IMPRVMENTS, E OF	11/03/22	1.00	35000.00	44176.17	36528.52
STR064A-010		SH 64 AND SH 13 AT MEEKER	11/10/22	1.00	45000.00	40495.00	55000.00
NHPP0853-126		US85C: PLATTEVILLE NORTH MP (11/10/22	1.00	35000.00	39557.43	34738.15
STAM420-001		US 285 AT HWY 9C IMPROVEMENTS	12/01/22	1.00	46000.00	112019.67	106382.08
BR2854-148		INTERSECTION OF US 285 & SH 9					
STM0091-046		ADA RAMP IMPROVEMENTS - FAIRP					
STA0711-021		SH71: REGION LINE NORTH	12/01/22	1.00	33100.00	45000.00	55000.00
STR114A-015		SH114 SILLSVILLE SOUTH TO MP3	12/01/22	1.00	50000.00	69500.00	52000.00
NHPP0701-252		I-70 RIFLE TO SILT SLAB REPLA	12/01/22	1.00	50000.00	51536.00	46072.00
IM025A-050		I25-MP103.9 - INTERSECTION DR	12/01/22	1.00	35000.00	146666.67	90000.00
STR318A-001		SH 318 MP 0 - 12.5 MOFFAT COU	12/01/22	1.00	50000.00	36850.00	17700.00
NHPP0021-041		SH2 RESURFACING MLK TO 52ND	12/01/22	1.00	45000.00	33066.78	32907.15
NHPP0063-048		US6 / 20 ROAD INTERSECTION IM	12/15/22	1.00	45000.00	43090.41	41000.00
NHPP0502-090		SH 50 MP 134.6-136 GUNNISON C	12/22/22	1.00	40000.00	52439.95	33111.94
STR0092-024		SH 9 North of Silverthorne	12/22/22	1.00	45000.00	33825.00	20650.00
BR012A-048		CO 12 STRUCTURE P-17-F AT MP	12/22/22	1.00	30000.00	30478.84	30000.00
STA385A-016		SH 385 MP 97.76	12/22/22	1.00	25000.00	39812.50	31250.00
STR096A-050		SH 96 MP 168.99 TO 193.77	12/22/22	1.00	36500.00	45333.33	58000.00
		WEIGHTED AVERAGE FOR THE FOURTH QUARTER		21.00	40504.76	61042.50	42632.17
		WEIGHTED AVERAGE FOR THE YEAR		53.00	36467.98	59217.09	43652.84
===== 620-00005		Field Office (Spec)		Each =====			
NHPP 0761-238		I-76 DAHLIA TO YORK	03/10/22	1.00	250000.00	311126.84	433500.00

COLORADO DEPARTMENT OF TRANSPORTATION
ITEM UNIT COSTS BY PROJECTS -- 2022 COST DATA

11:31 Wednesday, March 8, 2023 517

PROJECT NUMBER	ITEM NUMBER/ PROJECT LOCATION	ITEM DESCRIPTION/ PROJECT LOCATION	DATE LET	UNIT/ QUANTITY	ENGR. EST.	AVERAGE BID	AWARDED BID
===== 620-00005 Field Office (Spec) Each =====							
C0761-239							
ER007A-035			03/15/22	1.00	25000.00	15000.00	15000.00
	WEIGHTED AVERAGE FOR THE FIRST QUARTER			2.00	137500.00	278223.86	224250.00
NH0504-911			04/07/22	1.00	25000.00	28000.00	41000.00
2670703-479		I-70 BRIDGE OVER HARLAN	05/05/22	1.00	30000.00	249721.63	173530.63
FSA0702-409		I-70 VAIL WILDLIFE FENCE PHAS	05/26/22	1.00	55000.00	80000.00	80000.00
NHPP072A-047		SH-72 RESURFACING: I-70 TO IN	06/09/22	1.00	50000.00	50345.07	50345.07
	WEIGHTED AVERAGE FOR THE SECOND QUARTER			4.00	40000.00	168467.49	86218.93
STU0252-457		I-25:ALAMEDA RIVER PH 2.0	11/03/22	1.00	50000.00	110329.69	90000.00
2670703-487		I-70 BRIDGES OVER WARD ROAD-	12/01/22	1.00	80000.00	185748.59	103000.00
NHPP083A-046		SH83 RESURFACING STROH RD TO	12/08/22	1.00	50000.00	51544.76	48089.51
NHPP0931-033		SH93:US6 TO 58TH RESURFACING	12/15/22	1.00	50000.00	47444.34	29500.00
	WEIGHTED AVERAGE FOR THE FOURTH QUARTER			4.00	57500.00	110899.92	67647.38
	WEIGHTED AVERAGE FOR THE YEAR			10.00	66500.00	173978.44	106396.52
===== 620-00011 Field Lab (CL 1) Each =====							
STR0505-050			01/13/22	1.00	25000.00	21666.67	30000.00
	WEIGHTED AVERAGE FOR THE FIRST QUARTER			1.00	25000.00	21666.67	30000.00
NHPP0705-088		I-70 AGATE STRUCTURE REHAB	10/27/22	1.00	24300.00	49024.46	46000.00
NHPP083A-046		SH83 RESURFACING STROH RD TO	12/08/22	1.00	35000.00	46201.85	37403.70
NHM175-029		CANON CITY, CO	12/15/22	1.00	25000.00	27500.00	30000.00
	WEIGHTED AVERAGE FOR THE FOURTH QUARTER			3.00	28100.00	42937.69	37801.23
	WEIGHTED AVERAGE FOR THE YEAR			4.00	27325.00	37136.50	35850.93
===== 620-00012 Field Lab (CL 2) Each =====							
NHPP2873-189		US 287 (FEDERAL BLVD) - COLFA	01/06/22	1.00	32000.00	51471.36	54885.70

COLORADO DEPARTMENT OF TRANSPORTATION
ITEM UNIT COSTS BY PROJECTS -- 2022 COST DATA

11:31 Wednesday, March 8, 2023 518

PROJECT NUMBER	ITEM NUMBER/ PROJECT LOCATION	ITEM DESCRIPTION/ PROJECT LOCATION	DATE LET	UNIT/ QUANTITY	ENGR. EST.	AVERAGE BID	AWARDED BID	
===== 620-00012								
		Field Lab (CL 2)		Each				
NH0504-910		US50B L-24-B MIN REP AT MP 40	01/13/22	1.00	25000.00	24650.93	22500.00	
NHPP0702-383		I-70 EB AUX FRISCO TO SILVERT	01/13/22	1.00	25000.00	123198.38	55000.00	
NHPP1601-083			02/03/22	1.00	60000.00	43159.36	44000.00	
STA0252-459			02/03/22	1.00	26000.00	51141.67	61225.00	
C0762-055			02/17/22	1.00	20000.00	37578.37	65000.00	
STR0141-031			02/17/22	1.00	30000.00	35666.67	19000.00	
STR133A-051			02/17/22	1.00	25000.00	19333.33	28000.00	
NHPP0063-063			02/24/22	1.00	25000.00	30445.00	41000.00	
STA 067A-048		Hwy 67A MP 0.00 TO MP 11.05 I	03/03/22	1.00	25000.00	26021.60	28092.95	
NHPP 0761-238		I-76 DAHLIA TO YORK	03/10/22	1.00	120000.00	90294.77	80000.00	
C0761-239								
NHPP0703-472			03/10/22	1.00	26000.00	26484.79	25000.00	
ER007A-035			03/15/22	1.00	13000.00	5000.00	5000.00	
STR160A-034		US160A LA VETA PASS EAST SURF	03/17/22	1.00	55000.00	33513.08	35026.16	
BRC040-057			03/17/22	1.00	25000.00	50043.25	100000.00	
STR092A-031			03/17/22	1.00	30000.00	55000.00	55000.00	
NHM765-007			03/31/22	1.00	40000.00	85118.49	69008.76	
WEIGHTED AVERAGE FOR THE FIRST QUARTER					17.00	35411.76	52065.81	46337.56
NH0504-911			04/07/22	1.00	20000.00	29500.00	51000.00	
NHPP0702-413		VAIL PASS AUX PHASE 1 CAP 2	04/18/22	1.00	70638.19	70638.19	70638.19	
STM1151-038		SH115 MP 27 TO MP 38	04/21/22	1.00	25000.00	75867.57	74618.00	
2670703-479		I-70 BRIDGE OVER HARLAN	05/05/22	1.00	26000.00	68869.62	46274.84	
STA0712-019		SH 71: Frieight Improvements	05/12/22	1.00	25000.00	33200.25	33200.25	
NHC540-017		R2 CHAINUP STA @ KENOSHA/HOOS	05/12/22	1.00	25662.00	76666.67	85000.00	
NHPP 3851-018		US 385 NORTH OF CHEYENNE WELL	05/26/22	1.00	30000.00	41000.00	37000.00	
NHPP072A-047		SH-72 RESURFACING: I-70 TO IN	06/09/22	1.00	25000.00	29203.95	29203.95	
FSA052A-046		SH52 WCR 37 INTERSECTION IMPR	06/09/22	1.00	30000.00	27816.00	24150.00	
WEIGHTED AVERAGE FOR THE SECOND QUARTER					9.00	30811.13	55218.38	50120.58
NHPP0702-414		VAIL PASS AUX PHASE 1 CAP 3	07/08/22	1.00	105930.00	105930.00	105930.00	
FBR0702-423		VAIL PASS AUX BE F-12-AT PHAS						
NHPP0063-054		US 6 FROM I70-B TO 33 RD. (MP	08/18/22	1.00	25000.00	76797.40	114000.00	
BR0343-046		US 34 TIMBER BRIDGE REPL. PKG	08/31/22	2.00	6420.00	8800.75	8800.75	
FBR0343-047		US 6/US 34 TIMBER BRIDGE REPL						
2670403-065		US40_FLOYD HILL ROUNDABOUTS	09/15/22	1.00	60000.00	38455.88	32200.00	
2670703-497		I-70_GENESEE WILDLIFE XING	09/15/22	1.00	60000.00	79352.41	44526.76	
SHE2873-193		US 287 & CO 52 INTERSECTION I	09/15/22	1.00	35000.00	46640.69	26000.00	
WEIGHTED AVERAGE FOR THE THIRD QUARTER					7.00	42681.43	58466.90	48608.32

PROJECT NUMBER	ITEM NUMBER/ PROJECT LOCATION	ITEM DESCRIPTION/ PROJECT LOCATION	DATE LET	UNIT/ QUANTITY	ENGR. EST.	AVERAGE BID	AWARDED BID
===== 620-00012		Field Lab (CL 2)		Each	=====	=====	=====
NHPP0821-114		SH 82 ASPEN/INDEPENDENCE PASS	10/13/22	1.00	45000.00	16333.33	1000.00
NHPP0701-253		I-70 EAST OF DEBEQUE	10/27/22	1.00	45000.00	30290.00	40000.00
STA207A-004		Resurfacing SH207A MANZANOLA	10/27/22	1.00	28000.00	49733.33	48200.00
TRG0253-264		I-25 AND SH 119 PARK-N-RIDE	10/27/22	1.00	30000.00	77979.89	45000.00
STA3852-015		US 385 HOLYOKE NORTH	10/27/22	1.00	60000.00	34000.00	34000.00
STU0252-457		I-25:ALAMEDA RIVER PH 2.0	11/03/22	1.00	100000.00	50703.46	56000.00
SHE0242-087		US 24 SAFETY IMPRVMENTS, E OF	11/03/22	1.00	30000.00	42085.31	40255.92
STR064A-010		SH 64 AND SH 13 AT MEEKER	11/10/22	1.00	50000.00	39425.00	55000.00
NHPP0853-126		US85C: PLATTEVILLE NORTH MP (11/10/22	1.00	30000.00	42470.00	20000.00
STAM420-001		US 285 AT HWY 9C IMPROVEMENTS	12/01/22	1.00	49000.00	93303.78	73215.34
BR2854-148		INTERSECTION OF US 285 & SH 9					
STM0091-046		ADA RAMP IMPROVEMENTS - FAIRP					
STA0711-021		SH71: REGION LINE NORTH	12/01/22	1.00	26400.00	43666.67	51000.00
2670703-487		I-70 BRIDGES OVER WARD ROAD-	12/01/22	1.00	55000.00	61612.28	96800.00
NHPP0701-252		I-70 RIFLE TO SILT SLAB REPLA	12/01/22	1.00	60000.00	43000.00	42000.00
IM025A-050		I25-MP103.9 - INTERSECTION DR	12/01/22	1.00	30000.00	121666.67	60000.00
STR318A-001		SH 318 MP 0 - 12.5 MOFFAT COU	12/01/22	1.00	50000.00	38620.00	16240.00
NHPP0021-041		SH2 RESURFACING MLK TO 52ND	12/01/22	1.00	40000.00	26031.92	25526.91
NHPP0063-048		US6 / 20 ROAD INTERSECTION IM	12/15/22	1.00	45000.00	44769.77	41000.00
NHPP0931-033		SH93:US6 TO 58TH RESURFACING	12/15/22	1.00	26000.00	34866.50	29600.00
NHPP0502-090		SH 50 MP 134.6-136 GUNNISON C	12/22/22	1.00	40000.00	50346.29	29733.17
STR0092-024		SH 9 North of Silverthorne	12/22/22	1.00	45000.00	30975.00	18950.00
STA0361-129		US 36: HYGIENE RD AND NELSON	12/22/22	1.00	30000.00	20401.12	5.58
BR012A-048		CO 12 STRUCTURE P-17-F AT MP	12/22/22	1.00	25000.00	29205.45	30000.00
STA385A-016		SH 385 MP 97.76	12/22/22	1.00	20000.00	38562.50	31250.00
STR096A-050		SH 96 MP 168.99 TO 193.77	12/22/22	1.00	28200.00	43666.67	54000.00
		WEIGHTED AVERAGE FOR THE FOURTH QUARTER		24.00	41150.00	49252.47	39782.85
		WEIGHTED AVERAGE FOR THE YEAR		57.00	37994.21	51839.56	44220.32
===== 620-00020		Sanitary Facility		Each	=====	=====	=====
ITS0703-477		ITS EQUIPMENT UPGRADE AT EJMT	01/06/22	1.00	2500.00	69425.00	69425.00
MTCE R500-218			01/06/22	1.00	2000.00	2250.00	1000.00
NHPP2873-189		US 287 (FEDERAL BLVD) - COLFA	01/06/22	2.00	2400.00	4216.39	3578.45
STR0505-050			01/13/22	1.00	3000.00	2666.67	5000.00
NH0504-910		US50B I-24-B MIN REP AT MP 40	01/13/22	2.00	3000.00	2636.54	3125.00
MTCER400-391		VARIOUS HIGHWAY SEGMENTS ACRO	01/13/22	2.00	1500.00	3000.00	1000.00
NHPP0702-383		I-70 EB AUX FRISCO TO SILVERT	01/13/22	1.00	3000.00	11655.66	4300.00
NHPP1601-083			02/03/22	2.00	4000.00	7956.30	8300.00
STA0252-459			02/03/22	1.00	2500.00	12696.67	14000.00

PROJECT NUMBER	ITEM NUMBER/ PROJECT LOCATION	ITEM DESCRIPTION/ PROJECT LOCATION	DATE LET	UNIT/ QUANTITY	ENGR. EST.	AVERAGE BID	AWARDED BID
=====	620-00020	Sanitary Facility		Each			
C0762-055			02/17/22	2.00	2500.00	3812.29	1200.00
STR0141-031			02/17/22	1.00	3000.00	8666.67	15000.00
STR133A-051			02/17/22	1.00	2000.00	2933.33	5000.00
NHPP0063-063			02/24/22	1.00	2700.00	30485.00	50000.00
STA 067A-048		Hwy 67A MP 0.00 TO MP 11.05 I	03/03/22	2.00	2500.00	5110.45	6000.00
NHPP 0761-238		I-76 DAHLIA TO YORK	03/10/22	2.00	5000.00	11698.04	7000.00
C0761-239							
NHPP0703-472			03/10/22	2.00	2400.00	2639.04	2400.00
ER007A-035			03/15/22	1.00	2465.00	2933.00	2933.00
STR160A-034		US160A LA VETA PASS EAST SURF	03/17/22	1.00	2500.00	7119.71	8839.41
BRC040-057			03/17/22	2.00	3000.00	2732.00	2400.00
STR R500-171		Various locations on SH 141 a	03/17/22	2.00	3500.00	2610.26	3000.00
M R100-351		FY22 R1 SIGN STRUCTURE REPLAC	03/17/22	1.00	2000.00	1500.00	1566.00
STR092A-031			03/17/22	1.00	2500.00	8000.00	8000.00
NHM765-007			03/31/22	1.00	7500.00	13026.98	5739.90
C0703-499		EJMT GROUT BED REPAIR AND PAN	03/31/22	1.00	5000.00	3340.00	4500.00
WEIGHTED AVERAGE FOR THE FIRST QUARTER				34.00	3007.79	6501.63	7979.71
NH0504-911			04/07/22	2.00	5000.00	3750.00	3500.00
NHPP0702-413		VAIL PASS AUX PHASE 1 CAP 2	04/18/22	1.00	4815.00	4815.00	4815.00
STM1151-038		SH115 MP 27 TO MP 38	04/21/22	10.00	2700.00	3663.56	2100.00
MTCE2873-204		MTCE FY22 SH287 CONC PANEL RE	05/05/22	1.00	2500.00	1071.03	842.06
2670703-479		I-70 BRIDGE OVER HARLAN	05/05/22	1.00	3200.00	10892.29	4049.05
ER0702-420		PR I-70 GWC MATERIAL FLOWS 20	05/06/22	2.00	4500.00	2250.00	1000.00
STA0712-019		SH 71: Frieght Improvements	05/12/22	2.00	3000.00	2210.41	2210.41
STA001A-005		SH1 WELLINGTON SOUTH RESURFAC	05/12/22	1.00	3000.00	8889.00	9000.00
NHC540-017		R2 CHAINUP STA @ KENOSHA/HOOS	05/12/22	2.00	3356.00	5666.67	8000.00
CM760-047		COLFAX AND QUAIL	05/12/22	1.00	5600.00	9065.00	875.00
NHPP 3851-018		US 385 NORTH OF CHEYENNE WELL	05/26/22	2.00	2000.00	8450.00	5400.00
STAR100-358		3 STRUCTURES IN REGION 1 METR	05/26/22	2.00	2500.00	1731.95	1568.00
C0852-120		Rehabilitation of Culvert by	05/26/22	1.00	5000.00	230.00	230.00
FSA0702-409		I-70 VAIL WILDLIFE FENCE PHAS	05/26/22	1.00	7000.00	7500.00	7500.00
ITS 0741-024		VMS SIGN INSTALLATIONS AND VS	06/02/22	1.00	2000.00	3559.00	3500.00
FSA3921-019		SH 392 AND WCR 55 ISLANDS	06/02/22	1.00	2000.00	873.33	650.00
NHPP072A-047		SH-72 RESURFACING: I-70 TO IN	06/09/22	1.00	3000.00	2539.47	2539.47
FSA052A-046		SH52 WCR 37 INTERSECTION IMPR	06/09/22	2.00	3000.00	2029.00	2300.00
NHPP0252-448		I-25 TREX NARROWS BRIDGE PREV	06/23/22	2.00	1350.00	3474.50	5000.00
WEIGHTED AVERAGE FOR THE SECOND QUARTER				36.00	3181.31	4180.49	3137.71
MTCE 072A-045		SH 72B MP 37.00 TO MP 45.3 NE	07/07/22	1.00	2000.00	1500.00	1500.00

PROJECT NUMBER	ITEM NUMBER/ PROJECT LOCATION	ITEM DESCRIPTION/ PROJECT LOCATION	DATE LET	UNIT/ QUANTITY	ENGR. EST.	AVERAGE BID	AWARDED BID
=====	620-00020	Sanitary Facility		Each	=====	=====	=====
NHPP0702-414		VAIL PASS AUX PHASE 1 CAP 3	07/08/22	1.00	4815.00	4815.00	4815.00
FBR0702-423		VAIL PASS AUX BE F-12-AT PHAS					
STR0711-022		SH 71 OVER THE ARKANSAS	08/04/22	1.00	2500.00	1666.67	1500.00
NHPP0063-054		US 6 FROM I70-B TO 33 RD. (MP	08/18/22	1.00	3000.00	34210.85	51000.00
FBR0761-236		I-76 OVER CLR CRK SCOUR MIT	08/25/22	2.00	2400.00	2833.33	3800.00
CL211-099		SH 121 NORTH SGA SIGNALS	08/25/22	1.00	6000.00	4225.00	3950.00
ER0502-092		US 50 MP 204 EB MONARCH TRUCK	08/29/22	1.00	4000.00	1242.43	1152.30
BR0343-046		US 34 TIMBER BRIDGE REPL. PKG	08/31/22	2.00	738.30	505.04	505.04
FBR0343-047		US 6/US 34 TIMBER BRIDGE REPL					
STAR100-374		5 STRUCTURES IN REGION 1	09/01/22	2.00	1600.00	1890.00	1890.00
NHPPR100-266		R1 ESSENTIAL REPAIRS	09/01/22	1.00	1500.00	3564.80	2094.40
PAN0761-245		ALONG I-76 & RAMPS MILEPOST 9	09/01/22	1.00	4170.00	3325.00	1850.00
ER0253-297		WCR 34 BRIDGE OVER I-25(MM 24	09/14/22	1.00	5000.00	3925.00	200.00
2670403-065		US40 FLOYD HILL ROUNDABOUTS	09/15/22	2.00	3000.00	5297.22	2875.00
2670703-497		I-70 GENESEE WILDLIFE XING	09/15/22	1.00	3000.00	11047.14	2385.37
SHE2873-193		US 287 & CO 52 INTERSECTION I	09/15/22	2.00	3500.00	3734.78	1800.00
NHPP0701-231		I-70 SALT WASH BRIDGES SCOUR	09/29/22	1.00	4000.00	2188.55	2000.00
		WEIGHTED AVERAGE FOR THE THIRD QUARTER		21.00	2974.36	5259.59	4485.10
MTCE0253-281		MTCE FY23 I-25 CONC PANEL REP	10/06/22	1.00	2000.00	1509.56	1500.00
NHPP0821-114		SH 82 ASPEN/INDEPENDENCE PASS	10/13/22	1.00	3000.00	4166.67	500.00
C0831-126		SH83 EL PASO COUNTY TO BAYOU	10/13/22	2.00	2300.00	5000.00	7500.00
NHPP0701-253		I-70 EAST OF DEBEQUE	10/27/22	1.00	5000.00	7505.00	2500.00
STA207A-004		Resurfacing SH207A MANZANOLA	10/27/22	1.00	3350.00	6260.13	8780.40
NHPP0705-088		I-70 AGATE STRUCTURE REHAB	10/27/22	1.00	3500.00	7191.60	11000.00
FSAM240-200		SH21B CO SPRINGS SIGNAL REPLA	10/27/22	1.00	1000.00	5375.00	3000.00
C5502-111		US 550 MP 81 AND 89 RED MOUNT	10/27/22	1.00	2000.00	3750.00	5000.00
C170A-002		CRITICAL CULVERT CONST. PKG D	10/27/22	1.00	3300.00	1896.25	3125.00
TRG0253-264		I-25 AND SH 119 PARK-N-RIDE	10/27/22	2.00	2500.00	7672.41	5000.00
STA3852-015		US 385 HOLYOKE NORTH	10/27/22	1.00	20000.00	34000.00	34000.00
NHPP0343-048		US 34 (MP 169.3-171.4)	11/01/22	1.00	3200.00	2646.05	1500.00
STU0252-457		I-25:ALAMEDA RIVER PH 2.0	11/03/22	2.00	4000.00	12492.13	6500.00
SHE0242-087		US 24 SAFETY IMPRVMENTS, E OF	11/03/22	1.00	3500.00	3795.18	2385.54
STR064A-010		SH 64 AND SH 13 AT MEEKER	11/10/22	2.00	5000.00	6390.00	1500.00
NHPP0853-126		US85C: PLATTEVILLE NORTH MP (11/10/22	2.00	8000.00	3899.05	3215.25
C5502-097		US550 MP 117.28-126.06	11/17/22	2.00	3500.00	6634.33	5400.00
STRC090-011		US 50B AND SH71/CR18 INTERSEC	11/17/22	1.00	2000.00	1725.00	1950.00
STAM420-001		US 285 AT HWY 9C IMPROVEMENTS	12/01/22	2.00	1200.99	8801.76	12067.05
BR2854-148		INTERSECTION OF US 285 & SH 9					
STM0091-046		ADA RAMP IMPROVEMENTS - FAIRP					
STA0711-021		SH71: REGION LINE NORTH	12/01/22	2.00	3000.00	7166.67	7000.00
STR114A-015		SH114 SILLSVILLE SOUTH TO MP3	12/01/22	1.00	8000.00	7000.00	9000.00
2670703-487		I-70 BRIDGES OVER WARD ROAD-	12/01/22	1.00	4000.00	11446.60	19000.00
NHPP0701-252		I-70 RIFLE TO SILT SLAB REPLA	12/01/22	2.00	5000.00	3065.00	3630.00

PROJECT NUMBER	ITEM NUMBER/ PROJECT LOCATION	ITEM DESCRIPTION/ PROJECT LOCATION	DATE LET	UNIT/ QUANTITY	ENGR. EST.	AVERAGE BID	AWARDED BID
=====	620-00020	Sanitary Facility		Each	=====	=====	=====
IM025A-050		I25-MP103.9 - INTERSECTION DR	12/01/22	2.00	3500.00	5166.67	2500.00
STR318A-001		SH 318 MP 0 - 12.5 MOFFAT COU	12/01/22	2.00	5000.00	7220.00	11040.00
STR109A-019		M-22-AY BRIDGE REHAB ON SH109	12/01/22	1.00	3000.00	10369.00	3052.00
NHPP0021-041		SH2 RESURFACING MLK TO 52ND	12/01/22	2.00	3500.00	1999.21	2003.69
STR0641-107		SH 13 MM 104-128.1 IN MOFFAT	12/01/22	2.00	3000.00	4733.33	1300.00
NHPP083A-046		SH83 RESURFACING STROH RD TO	12/08/22	2.00	3000.00	5436.57	2673.13
NHPP0063-048		US6 / 20 ROAD INTERSECTION IM	12/15/22	1.00	4000.00	5572.88	6000.00
NHM175-029		CANON CITY, CO	12/15/22	1.00	3000.00	2051.20	500.00
FSA0853-122		WCRI4.5 AND US-85, FORT LUPTO	12/15/22	1.00	2500.00	748.85	1000.00
NHPP0931-033		SH93:US6 TO 58TH RESURFACING	12/15/22	1.00	3000.00	5147.24	6150.00
NHPP0502-090		SH 50 MP 134.6-136 GUNNISON C	12/22/22	1.00	3000.00	7391.53	2229.98
STR0092-024		SH 9 North of Silverthorne	12/22/22	1.00	5000.00	8245.00	8490.00
STA0361-129		US 36: HYGIENE RD AND NELSON	12/22/22	2.00	5000.00	2726.60	558.00
BR012A-048		CO 12 STRUCTURE P-17-F AT MP	12/22/22	2.00	4000.00	8866.98	5000.00
STA385A-016		SH 385 MP 97.76	12/22/22	1.00	3000.00	3581.25	3125.00
STR096A-050		SH 96 MP 168.99 TO 193.77	12/22/22	1.00	3200.00	11009.08	9000.00
		WEIGHTED AVERAGE FOR THE FOURTH QUARTER		=====	=====	=====	=====
				55.00	3937.31	6205.07	5675.73
		WEIGHTED AVERAGE FOR THE YEAR		=====	=====	=====	=====
				146.00	3395.93	5674.51	5420.45
=====	621-00411	Str Temp Acc Rd (Loc 1)		LUMP SUM	=====	=====	=====
NHPP0701-231		I-70 SALT WASH BRIDGES SCOUR	09/29/22	1.00	150000.00	115424.99	142300.00
		WEIGHTED AVERAGE FOR THE THIRD QUARTER		=====	=====	=====	=====
				1.00	150000.00	115424.99	142300.00
		WEIGHTED AVERAGE FOR THE YEAR		=====	=====	=====	=====
				1.00	150000.00	115424.99	142300.00
=====	621-00412	Str Temp Acc Rd (Loc 2)		LUMP SUM	=====	=====	=====
NHPP0701-231		I-70 SALT WASH BRIDGES SCOUR	09/29/22	1.00	50000.00	69104.07	55400.00
		WEIGHTED AVERAGE FOR THE THIRD QUARTER		=====	=====	=====	=====
				1.00	50000.00	69104.07	55400.00
		WEIGHTED AVERAGE FOR THE YEAR		=====	=====	=====	=====
				1.00	50000.00	69104.07	55400.00
=====	621-00450	Detour Pvmt		Sq Yard	=====	=====	=====
NHPP0702-383		I-70 EB AUX FRISCO TO SILVERT	01/13/22	1,560.00	50.00	167.19	177.00
C0762-055			02/17/22	6,006.00	100.00	95.95	100.00
NHPP 0761-238		I-76 DAHLIA TO YORK	03/10/22	8,810.00	62.00	63.85	58.00

COLORADO DEPARTMENT OF TRANSPORTATION
ITEM UNIT COSTS BY PROJECTS -- 2022 COST DATA

11:31 Wednesday, March 8, 2023 523

PROJECT NUMBER	ITEM NUMBER/ PROJECT LOCATION	ITEM DESCRIPTION/ PROJECT LOCATION	DATE LET	UNIT/ QUANTITY	ENGR. EST.	AVERAGE BID	AWARDED BID
=====	621-00450	Detour Pvmt		Sq Yard	=====		
C0761-239							
	WEIGHTED AVERAGE FOR THE FIRST QUARTER			16,376.00	74.79	79.26	84.74
NH0504-911			04/07/22	1,440.00	57.30	78.00	36.00
NHPP0702-413	VAIL PASS AUX PHASE 1 CAP 2		04/18/22	1,841.00	47.86	47.86	47.86
STM1151-038	SH115 MP 27 TO MP 38		04/21/22	7,800.00	50.00	63.43	53.48
2670703-479	I-70 BRIDGE OVER HARLAN		05/05/22	702.00	70.00	155.01	250.00
STA0712-019	SH 71: Frieight Improvements		05/12/22	529.00	80.00	72.53	72.53
	WEIGHTED AVERAGE FOR THE SECOND QUARTER			12,312.00	52.96	71.76	62.62
NHPP0702-414	VAIL PASS AUX PHASE 1 CAP 3		07/08/22	33,467.00	90.07	90.07	90.07
FBR0702-423	VAIL PASS AUX BE F-12-AT PHAS						
NHPP0063-054	US 6 FROM I70-B TO 33 RD. (MP		08/18/22	1,600.00	200.00	144.23	108.00
C1211-099	SH 121 NORTH SGA SIGNALS		08/25/22	100.00	100.00	225.00	250.00
2670403-065	US40_FLOYD HILL ROUNDABOUTS		09/15/22	5,240.00	80.00	85.97	109.00
2670703-497	I-70_GENESEE WILDLIFE XING		09/15/22	11,032.00	57.00	70.12	62.48
	WEIGHTED AVERAGE FOR THE THIRD QUARTER			51,439.00	85.39	79.25	86.95
TRG0253-264	I-25 AND SH 119 PARK-N-RIDE		10/27/22	9,943.00	75.00	98.50	78.00
STAM420-001	US 285 AT HWY 9C IMPROVEMENTS		12/01/22	1,800.00	65.00	103.51	116.38
BR2854-148	INTERSECTION OF US 285 & SH 9						
STM0091-046	ADA RAMP IMPROVEMENTS - FAIRP						
2670703-487	I-70 BRIDGES OVER WARD ROAD-		12/01/22	11,760.00	80.00	84.59	80.00
IM025A-050	I25-MP103.9 - INTERSECTION DR		12/01/22	7,070.00	60.00	78.33	72.00
	WEIGHTED AVERAGE FOR THE FOURTH QUARTER			30,573.00	72.87	91.25	79.64
	WEIGHTED AVERAGE FOR THE YEAR			110,700.00	76.76	82.91	81.90
=====	621-00451	Detour Pavement		Ton	=====		
STU0252-457	I-25:ALAMEDA RIVER PH 2.0		11/03/22	372.00	200.00	348.68	339.00
	WEIGHTED AVERAGE FOR THE FOURTH QUARTER			372.00	200.00	348.68	339.00
	WEIGHTED AVERAGE FOR THE YEAR			372.00	200.00	348.68	339.00

COLORADO DEPARTMENT OF TRANSPORTATION
ITEM UNIT COSTS BY PROJECTS -- 2022 COST DATA

11:31 Wednesday, March 8, 2023 524

PROJECT NUMBER	ITEM NUMBER/ PROJECT LOCATION	ITEM DESCRIPTION/ PROJECT LOCATION	DATE LET	UNIT/ QUANTITY	ENGR. EST.	AVERAGE BID	AWARDED BID
=====	621-00650	Ped Stair Str		LUMP SUM	=====		
TRG0253-264		I-25 AND SH 119 PARK-N-RIDE	10/27/22	1.00	30000.00	11071.88	6500.00
	WEIGHTED	AVERAGE FOR THE FOURTH QUARTER		1.00	30000.00	11071.88	6500.00
		WEIGHTED AVERAGE FOR THE YEAR		1.00	30000.00	11071.88	6500.00
=====	622-00000	Sewage Pumping		Each	=====		
2670703-479		I-70 BRIDGE OVER HARLAN	05/05/22	1.00	20000.00	70574.30	55287.70
	WEIGHTED	AVERAGE FOR THE SECOND QUARTER		1.00	20000.00	70574.30	55287.70
NHPP0063-054		US 6 FROM I70-B TO 33 RD. (MP 08/18/22		10.00	500.00	2548.22	2200.00
	WEIGHTED	AVERAGE FOR THE THIRD QUARTER		10.00	500.00	2548.22	2200.00
		WEIGHTED AVERAGE FOR THE YEAR		11.00	2272.73	18246.55	7026.15
=====	622-00010	Bicycle Rack		Each	=====		
TRG0253-264		I-25 AND SH 119 PARK-N-RIDE	10/27/22	11.00	1700.00	1018.35	750.00
	WEIGHTED	AVERAGE FOR THE FOURTH QUARTER		11.00	1700.00	1018.35	750.00
		WEIGHTED AVERAGE FOR THE YEAR		11.00	1700.00	1018.35	750.00
=====	622-00100	Shade Shelter		Each	=====		
TRG0253-264		I-25 AND SH 119 PARK-N-RIDE	10/27/22	2.00	37450.00	48772.72	75000.00
	WEIGHTED	AVERAGE FOR THE FOURTH QUARTER		2.00	37450.00	48772.72	75000.00
		WEIGHTED AVERAGE FOR THE YEAR		2.00	37450.00	48772.72	75000.00
=====	622-00155	Planter Box (Spec)		Each	=====		
NHPP0253-275		I-25 EXPRESS LANES SEGMENT 5	03/11/22	26.00	2731.73	2127.31	2127.31
	WEIGHTED	AVERAGE FOR THE FIRST QUARTER		26.00	2731.73	2127.31	2127.31
		WEIGHTED AVERAGE FOR THE YEAR		26.00	2731.73	2127.31	2127.31

COLORADO DEPARTMENT OF TRANSPORTATION
ITEM UNIT COSTS BY PROJECTS -- 2022 COST DATA

11:31 Wednesday, March 8, 2023 525

PROJECT NUMBER	ITEM NUMBER/ PROJECT LOCATION	ITEM DESCRIPTION/ PROJECT LOCATION	DATE LET	UNIT/ QUANTITY	ENGR. EST.	AVERAGE BID	AWARDED BID
=====	622-00200	Table		Each	=====	=====	=====
NHPP0702-413		VAIL PASS AUX PHASE 1 CAP 2	04/18/22	2.00	2736.32	2736.32	2736.32
		WEIGHTED AVERAGE FOR THE SECOND QUARTER		2.00	2736.32	2736.32	2736.32
		WEIGHTED AVERAGE FOR THE YEAR		2.00	2736.32	2736.32	2736.32
=====	622-00250	Bench		Each	=====	=====	=====
NHPP0702-383		I-70 EB AUX FRISCO TO SILVERT	01/13/22	1.00	2000.00	3204.80	3300.00
		WEIGHTED AVERAGE FOR THE FIRST QUARTER		1.00	2000.00	3204.80	3300.00
TRG0253-264		I-25 AND SH 119 PARK-N-RIDE	10/27/22	3.00	2000.00	2813.41	2500.00
		WEIGHTED AVERAGE FOR THE FOURTH QUARTER		3.00	2000.00	2813.41	2500.00
		WEIGHTED AVERAGE FOR THE YEAR		4.00	2000.00	2880.89	2700.00
=====	622-00251	Inst Bench		Each	=====	=====	=====
STU0252-457		I-25:ALAMEDA RIVER PH 2.0	11/03/22	1.00	1000.00	4556.67	3600.00
		WEIGHTED AVERAGE FOR THE FOURTH QUARTER		1.00	1000.00	4556.67	3600.00
		WEIGHTED AVERAGE FOR THE YEAR		1.00	1000.00	4556.67	3600.00
=====	622-00270	Bollard		Each	=====	=====	=====
TRG0253-264		I-25 AND SH 119 PARK-N-RIDE	10/27/22	29.00	545.00	1022.23	900.00
STU0252-457		I-25:ALAMEDA RIVER PH 2.0	11/03/22	11.00	2000.00	2125.37	3200.00
		WEIGHTED AVERAGE FOR THE FOURTH QUARTER		40.00	945.13	1159.60	1532.50
		WEIGHTED AVERAGE FOR THE YEAR		40.00	945.13	1159.60	1532.50
=====	622-00350	Trash Receptacle		Each	=====	=====	=====
TRG0253-264		I-25 AND SH 119 PARK-N-RIDE	10/27/22	7.00	1800.00	2571.04	2500.00
		WEIGHTED AVERAGE FOR THE FOURTH QUARTER		7.00	1800.00	2571.04	2500.00
		WEIGHTED AVERAGE FOR THE YEAR		7.00	1800.00	2571.04	2500.00

COLORADO DEPARTMENT OF TRANSPORTATION
 ITEM UNIT COSTS BY PROJECTS -- 2022 COST DATA

11:31 Wednesday, March 8, 2023 526

PROJECT NUMBER	ITEM NUMBER/ PROJECT LOCATION	ITEM DESCRIPTION/ PROJECT LOCATION	DATE LET	UNIT/ QUANTITY	ENGR. EST.	AVERAGE BID	AWARDED BID
=====	622-20080	Flagpole		Each	=====	=====	=====
NHM765-007			03/31/22	50.00	250.00	336.09	171.00
		WEIGHTED AVERAGE FOR THE FIRST QUARTER		50.00	250.00	336.09	171.00
		WEIGHTED AVERAGE FOR THE YEAR		50.00	250.00	336.09	171.00
=====	623-00603	3 In Plastic Pipe (Irrig/Sleeve)		Lin Foot	=====	=====	=====
NHPP0253-275		I-25 EXPRESS LANES SEGMENT 5	03/11/22	1,270.00	31.73	33.84	33.84
		WEIGHTED AVERAGE FOR THE FIRST QUARTER		1,270.00	31.73	33.84	33.84
		WEIGHTED AVERAGE FOR THE YEAR		1,270.00	31.73	33.84	33.84
=====	623-00604	4 In Plastic Pipe (Irrig/Sleeve)		Lin Foot	=====	=====	=====
NHPP0253-275		I-25 EXPRESS LANES SEGMENT 5	03/11/22	305.00	40.48	43.19	43.19
		WEIGHTED AVERAGE FOR THE FIRST QUARTER		305.00	40.48	43.19	43.19
		WEIGHTED AVERAGE FOR THE YEAR		305.00	40.48	43.19	43.19
=====	623-07006	3/4 In Water Meter		Each	=====	=====	=====
STU0252-457		I-25:ALAMEDA RIVER PH 2.0	11/03/22	3.00	1000.00	5702.55	1900.00
		WEIGHTED AVERAGE FOR THE FOURTH QUARTER		3.00	1000.00	5702.55	1900.00
		WEIGHTED AVERAGE FOR THE YEAR		3.00	1000.00	5702.55	1900.00
=====	623-09900	Sprinkler System		LUMP SUM	=====	=====	=====
NHPP0253-275		I-25 EXPRESS LANES SEGMENT 5	03/11/22	1.00	526344.30	133187.30	133187.30
		WEIGHTED AVERAGE FOR THE FIRST QUARTER		1.00	526344.30	133187.30	133187.30
2670703-479		I-70 BRIDGE OVER HARLAN	05/05/22	1.00	9500.00	16589.40	21811.60
		WEIGHTED AVERAGE FOR THE SECOND QUARTER		1.00	9500.00	16589.40	21811.60
		WEIGHTED AVERAGE FOR THE YEAR		2.00	267922.15	33246.25	77499.45

COLORADO DEPARTMENT OF TRANSPORTATION
ITEM UNIT COSTS BY PROJECTS -- 2022 COST DATA

11:31 Wednesday, March 8, 2023 527

PROJECT NUMBER	ITEM NUMBER/ PROJECT LOCATION	ITEM DESCRIPTION/ PROJECT LOCATION	DATE LET	UNIT/ QUANTITY	ENGR. EST.	AVERAGE BID	AWARDED BID
=====	623-09905	Irrig Assembly		Each	=====	=====	=====
NHPP0063-054		US 6 FROM I70-B TO 33 RD.	08/18/22	1.00	5000.00	7297.54	6300.00
		WEIGHTED AVERAGE FOR THE THIRD QUARTER		1.00	5000.00	7297.54	6300.00
		WEIGHTED AVERAGE FOR THE YEAR		1.00	5000.00	7297.54	6300.00
=====	624-20016	15 In Drainage Pipe (CL 0) (CIP)		Lin Foot	=====	=====	=====
BR0343-046 FBR0343-047		US 34 TIMBER BRIDGE REPL.	08/31/22	96.00	153.92	70.51	70.51
		US 6/US 34 TIMBER BRIDGE REPL					
		WEIGHTED AVERAGE FOR THE THIRD QUARTER		96.00	153.92	70.51	70.51
		WEIGHTED AVERAGE FOR THE YEAR		96.00	153.92	70.51	70.51
=====	624-20025	24 In Drainage Pipe (CL 0) (CIP)		Lin Foot	=====	=====	=====
NH0504-910		US50B L-24-B MIN REP AT MP 40	01/13/22	140.00	150.00	118.49	68.75
		WEIGHTED AVERAGE FOR THE FIRST QUARTER		140.00	150.00	118.49	68.75
		WEIGHTED AVERAGE FOR THE YEAR		140.00	150.00	118.49	68.75
=====	624-20300	Detour Drainage Pipe (CL 0)		Lin Foot	=====	=====	=====
NHPP0702-414 FBR0702-423		VAIL PASS AUX PHASE 1 CAP 3	07/08/22	248.00	279.92	279.92	279.92
		VAIL PASS AUX BE F-12-AT PHAS					
		WEIGHTED AVERAGE FOR THE THIRD QUARTER		248.00	279.92	279.92	279.92
STU0252-457 BR012A-048		I-25:ALAMEDA RIVER PH 2.0	11/03/22	100.00	200.00	302.20	295.00
		CO 12 STRUCTURE P-17-F AT MP	12/22/22	315.00	300.00	318.29	375.00
		WEIGHTED AVERAGE FOR THE FOURTH QUARTER		415.00	275.90	313.10	355.72
		WEIGHTED AVERAGE FOR THE YEAR		663.00	277.41	306.11	327.37
=====	624-20301	Detour Drainage Pipe (CL 0)		LUMP SUM	=====	=====	=====
NHPP 0761-238		I-76 DAHLIA TO YORK	03/10/22	1.00	20000.00	43688.71	7500.00

COLORADO DEPARTMENT OF TRANSPORTATION
ITEM UNIT COSTS BY PROJECTS -- 2022 COST DATA

11:31 Wednesday, March 8, 2023 528

PROJECT NUMBER	ITEM NUMBER/ PROJECT LOCATION	ITEM DESCRIPTION/ PROJECT LOCATION	DATE LET	UNIT/ QUANTITY	ENGR. EST.	AVERAGE BID	AWARDED BID
===== 624-20301 C0761-239		Detour Drainage Pipe (CL 0)		LUMP SUM	=====	=====	=====
	WEIGHTED AVERAGE FOR THE FIRST QUARTER			1.00	20000.00	43688.71	7500.00
STU0252-457		I-25:ALAMEDA RIVER PH 2.0	11/03/22	1.00	100000.00	31334.01	48000.00
	WEIGHTED AVERAGE FOR THE FOURTH QUARTER			1.00	100000.00	31334.01	48000.00
	WEIGHTED AVERAGE FOR THE YEAR			2.00	60000.00	40319.24	27750.00
===== 624-23019		18 In Drainage Pipe (CL 3) (CIP)		Lin Foot	=====	=====	=====
NHPP0702-383		I-70 EB AUX FRISCO TO SILVERT	01/13/22	549.00	100.00	131.25	112.00
	WEIGHTED AVERAGE FOR THE FIRST QUARTER			549.00	100.00	131.25	112.00
	WEIGHTED AVERAGE FOR THE YEAR			549.00	100.00	131.25	112.00
===== 624-23025		24 In Drainage Pipe (CL 3) (CIP)		Lin Foot	=====	=====	=====
NHPP0702-383		I-70 EB AUX FRISCO TO SILVERT	01/13/22	237.00	150.00	173.30	180.00
	WEIGHTED AVERAGE FOR THE FIRST QUARTER			237.00	150.00	173.30	180.00
	WEIGHTED AVERAGE FOR THE YEAR			237.00	150.00	173.30	180.00
===== 624-23031		30 In Drainage Pipe (CL 3) (CIP)		Lin Foot	=====	=====	=====
TRG0253-264		I-25 AND SH 119 PARK-N-RIDE	10/27/22	79.00	200.00	215.70	155.00
	WEIGHTED AVERAGE FOR THE FOURTH QUARTER			79.00	200.00	215.70	155.00
	WEIGHTED AVERAGE FOR THE YEAR			79.00	200.00	215.70	155.00
===== 624-23055		54 In Drainage Pipe (CL 3) (CIP)		Lin Foot	=====	=====	=====
TRG0253-264		I-25 AND SH 119 PARK-N-RIDE	10/27/22	134.00	300.00	401.08	320.00
	WEIGHTED AVERAGE FOR THE FOURTH QUARTER			134.00	300.00	401.08	320.00
	WEIGHTED AVERAGE FOR THE YEAR			134.00	300.00	401.08	320.00

COLORADO DEPARTMENT OF TRANSPORTATION
ITEM UNIT COSTS BY PROJECTS -- 2022 COST DATA

11:31 Wednesday, March 8, 2023 529

PROJECT NUMBER	ITEM NUMBER/ PROJECT LOCATION	ITEM DESCRIPTION/ PROJECT LOCATION	DATE LET	UNIT/ QUANTITY	ENGR. EST.	AVERAGE BID	AWARDED BID
=====	624-25031	30 In Drainage Pipe (CL 5) (CIP)		Lin Foot	=====		
IM025A-050		I25-MP103.9 - INTERSECTION DR	12/01/22	112.00	180.00	253.33	180.00
	WEIGHTED AVERAGE FOR THE FOURTH QUARTER			112.00	180.00	253.33	180.00
	WEIGHTED AVERAGE FOR THE YEAR			112.00	180.00	253.33	180.00
=====	624-27015	15 In Drainage Pipe (CL 7)		Lin Foot	=====		
NHPP 0761-238 C0761-239		I-76 DAHLIA TO YORK	03/10/22	137.00	75.00	76.37	60.00
	WEIGHTED AVERAGE FOR THE FIRST QUARTER			137.00	75.00	76.37	60.00
	WEIGHTED AVERAGE FOR THE YEAR			137.00	75.00	76.37	60.00
=====	624-27024	24 In Drainage Pipe (CL 7)		Lin Foot	=====		
NHPP 0761-238 C0761-239		I-76 DAHLIA TO YORK	03/10/22	143.00	95.00	311.83	105.00
	WEIGHTED AVERAGE FOR THE FIRST QUARTER			143.00	95.00	311.83	105.00
	WEIGHTED AVERAGE FOR THE YEAR			143.00	95.00	311.83	105.00
=====	624-28007	6 In Drainage Pipe (CL 8) (CIP)		Lin Foot	=====		
NHPP0702-414 FBR0702-423		VAIL PASS AUX PHASE 1 CAP 3 VAIL PASS AUX BE F-12-AT PHAS	07/08/22	85.00	385.81	385.81	385.81
	WEIGHTED AVERAGE FOR THE THIRD QUARTER			85.00	385.81	385.81	385.81
	WEIGHTED AVERAGE FOR THE YEAR			85.00	385.81	385.81	385.81
=====	624-28019	18 In Drainage Pipe (CL 8) (CIP)		Lin Foot	=====		
NHPP0702-414 FBR0702-423		VAIL PASS AUX PHASE 1 CAP 3 VAIL PASS AUX BE F-12-AT PHAS	07/08/22	2,050.00	233.29	233.29	233.29
	WEIGHTED AVERAGE FOR THE THIRD QUARTER			2,050.00	233.29	233.29	233.29
	WEIGHTED AVERAGE FOR THE YEAR			2,050.00	233.29	233.29	233.29

COLORADO DEPARTMENT OF TRANSPORTATION
ITEM UNIT COSTS BY PROJECTS -- 2022 COST DATA

11:31 Wednesday, March 8, 2023 530

PROJECT NUMBER	ITEM NUMBER/ PROJECT LOCATION	ITEM DESCRIPTION/ PROJECT LOCATION	DATE LET	UNIT/ QUANTITY	ENGR. EST.	AVERAGE BID	AWARDED BID
=====	624-28025	24 In Drainage Pipe (CL 8) (CIP)		Lin Foot	=====		
NHPP0702-414 FBR0702-423		VAIL PASS AUX PHASE 1 CAP 3 VAIL PASS AUX BE F-12-AT PHAS	07/08/22	207.00	343.86	343.86	343.86
		WEIGHTED AVERAGE FOR THE THIRD QUARTER		207.00	343.86	343.86	343.86
		WEIGHTED AVERAGE FOR THE YEAR		207.00	343.86	343.86	343.86
=====	624-28031	30 In Drainage Pipe (CL 8) (CIP)		Lin Foot	=====		
NHPP0702-414 FBR0702-423		VAIL PASS AUX PHASE 1 CAP 3 VAIL PASS AUX BE F-12-AT PHAS	07/08/22	342.00	317.91	317.91	317.91
		WEIGHTED AVERAGE FOR THE THIRD QUARTER		342.00	317.91	317.91	317.91
		WEIGHTED AVERAGE FOR THE YEAR		342.00	317.91	317.91	317.91
=====	624-29015	15 In Drainage Pipe (CL 9)		Lin Foot	=====		
NHPP 0761-238 C0761-239		I-76 DAHLIA TO YORK	03/10/22	276.00	160.00	76.65	59.00
		WEIGHTED AVERAGE FOR THE FIRST QUARTER		276.00	160.00	76.65	59.00
		WEIGHTED AVERAGE FOR THE YEAR		276.00	160.00	76.65	59.00
=====	624-29018	18 In Drainage Pipe (CL 9)		Lin Foot	=====		
NHPP 0761-238 C0761-239		I-76 DAHLIA TO YORK	03/10/22	163.00	160.00	176.38	79.00
		WEIGHTED AVERAGE FOR THE FIRST QUARTER		163.00	160.00	176.38	79.00
		WEIGHTED AVERAGE FOR THE YEAR		163.00	160.00	176.38	79.00
=====	624-29019	18 In Drainage Pipe (CL 9) (CIP)		Lin Foot	=====		
TRG0253-264		I-25 AND SH 119 PARK-N-RIDE	10/27/22	372.00	125.00	132.77	85.00
		WEIGHTED AVERAGE FOR THE FOURTH QUARTER		372.00	125.00	132.77	85.00
		WEIGHTED AVERAGE FOR THE YEAR		372.00	125.00	132.77	85.00

COLORADO DEPARTMENT OF TRANSPORTATION
ITEM UNIT COSTS BY PROJECTS -- 2022 COST DATA

11:31 Wednesday, March 8, 2023 531

PROJECT NUMBER	ITEM NUMBER/ PROJECT LOCATION	ITEM DESCRIPTION/ PROJECT LOCATION	DATE LET	UNIT/ QUANTITY	ENGR. EST.	AVERAGE BID	AWARDED BID
=====	624-29024	24 In Drainage Pipe (CL 9)		Lin Foot	=====		
NHPP 0761-238 C0761-239		I-76 DAHLIA TO YORK	03/10/22	155.00	220.00	196.64	105.00
		WEIGHTED AVERAGE FOR THE FIRST QUARTER		155.00	220.00	196.64	105.00
		WEIGHTED AVERAGE FOR THE YEAR		155.00	220.00	196.64	105.00
=====	624-29025	24 In Drainage Pipe (CL 9) (CIP)		Lin Foot	=====		
TRG0253-264		I-25 AND SH 119 PARK-N-RIDE	10/27/22	468.00	200.00	152.96	90.00
		WEIGHTED AVERAGE FOR THE FOURTH QUARTER		468.00	200.00	152.96	90.00
		WEIGHTED AVERAGE FOR THE YEAR		468.00	200.00	152.96	90.00
=====	624-29031	30 In Drainage Pipe (CL 9) (CIP)		Lin Foot	=====		
TRG0253-264		I-25 AND SH 119 PARK-N-RIDE	10/27/22	289.00	320.00	188.24	117.00
		WEIGHTED AVERAGE FOR THE FOURTH QUARTER		289.00	320.00	188.24	117.00
		WEIGHTED AVERAGE FOR THE YEAR		289.00	320.00	188.24	117.00
=====	624-30013	12 In Drainage Pipe (CL 10) (CIP)		Lin Foot	=====		
SHE2873-193		US 287 & CO 52 INTERSECTION I	09/15/22	100.00	180.00	157.33	133.75
		WEIGHTED AVERAGE FOR THE THIRD QUARTER		100.00	180.00	157.33	133.75
		WEIGHTED AVERAGE FOR THE YEAR		100.00	180.00	157.33	133.75
=====	624-30018	18 In Drainage Pipe (CL 10)		Lin Foot	=====		
IM025A-050		I25-MP103.9 - INTERSECTION DR	12/01/22	288.00	110.00	160.00	140.00
		WEIGHTED AVERAGE FOR THE FOURTH QUARTER		288.00	110.00	160.00	140.00
		WEIGHTED AVERAGE FOR THE YEAR		288.00	110.00	160.00	140.00

COLORADO DEPARTMENT OF TRANSPORTATION
ITEM UNIT COSTS BY PROJECTS -- 2022 COST DATA

11:31 Wednesday, March 8, 2023 532

PROJECT NUMBER	ITEM NUMBER/ PROJECT LOCATION	ITEM DESCRIPTION/ PROJECT LOCATION	DATE LET	UNIT/ QUANTITY	ENGR. EST.	AVERAGE BID	AWARDED BID
===== 624-30019		18 In Drainage Pipe (CL 10) (CIP)		Lin Foot	=====		
NHPP0702-413		VAIL PASS AUX PHASE 1 CAP 2	04/18/22	566.00	235.16	235.16	235.16
		WEIGHTED AVERAGE FOR THE SECOND QUARTER		566.00	235.16	235.16	235.16
SHE2873-193		US 287 & CO 52 INTERSECTION I	09/15/22	111.00	200.00	173.47	144.00
		WEIGHTED AVERAGE FOR THE THIRD QUARTER		111.00	200.00	173.47	144.00
IM025A-050		I25-MP103.9 - INTERSECTION DR	12/01/22	208.00	125.00	176.67	160.00
		WEIGHTED AVERAGE FOR THE FOURTH QUARTER		208.00	125.00	176.67	160.00
		WEIGHTED AVERAGE FOR THE YEAR		885.00	204.86	193.36	206.06
===== 624-30025		24 In Drainage Pipe (CL 10) (CIP)		Lin Foot	=====		
NHPP0702-413		VAIL PASS AUX PHASE 1 CAP 2	04/18/22	102.00	350.26	350.26	350.26
		WEIGHTED AVERAGE FOR THE SECOND QUARTER		102.00	350.26	350.26	350.26
IM025A-050		I25-MP103.9 - INTERSECTION DR	12/01/22	125.00	160.00	218.33	220.00
		WEIGHTED AVERAGE FOR THE FOURTH QUARTER		125.00	160.00	218.33	220.00
		WEIGHTED AVERAGE FOR THE YEAR		227.00	245.49	246.54	278.53
===== 624-30031		30 In Drainage Pipe (CL 10) CIP)		Lin Foot	=====		
IM025A-050		I25-MP103.9 - INTERSECTION DR	12/01/22	151.00	180.00	286.67	260.00
		WEIGHTED AVERAGE FOR THE FOURTH QUARTER		151.00	180.00	286.67	260.00
		WEIGHTED AVERAGE FOR THE YEAR		151.00	180.00	286.67	260.00

COLORADO DEPARTMENT OF TRANSPORTATION
 ITEM UNIT COSTS BY PROJECTS -- 2022 COST DATA

11:31 Wednesday, March 8, 2023 533

PROJECT NUMBER	ITEM NUMBER/ PROJECT LOCATION	ITEM DESCRIPTION/ PROJECT LOCATION	DATE LET	UNIT/ QUANTITY	ENGR. EST.	AVERAGE BID	AWARDED BID
===== 624-30037		36 In Drainage Pipe (CL 10) (CIP)		Lin Foot	=====		
NHPP0702-413		VAIL PASS AUX PHASE 1 CAP 2	04/18/22	203.00	330.84	330.84	330.84
	WEIGHTED	AVERAGE FOR THE SECOND QUARTER		203.00	330.84	330.84	330.84
		WEIGHTED AVERAGE FOR THE YEAR		203.00	330.84	330.84	330.84
===== 624-30043		42 In Drainage Pipe (CL 10) (CIP)		Lin Foot	=====		
NHPP0702-413		VAIL PASS AUX PHASE 1 CAP 2	04/18/22	63.00	406.01	406.01	406.01
	WEIGHTED	AVERAGE FOR THE SECOND QUARTER		63.00	406.01	406.01	406.01
		WEIGHTED AVERAGE FOR THE YEAR		63.00	406.01	406.01	406.01
===== 624-30055		54 In Drainage Pipe (CL 10) (CIP)		Lin Foot	=====		
IM025A-050		I25-MP103.9 - INTERSECTION DR	12/01/22	429.00	415.00	510.00	440.00
	WEIGHTED	AVERAGE FOR THE FOURTH QUARTER		429.00	415.00	510.00	440.00
		WEIGHTED AVERAGE FOR THE YEAR		429.00	415.00	510.00	440.00
===== 624-49018		18 In Equiv Drain Pipe E (CL 9)		Lin Foot	=====		
NHPP 0761-238 C0761-239		I-76 DAHLIA TO YORK	03/10/22	589.00	90.00	149.36	64.00
	WEIGHTED	AVERAGE FOR THE FIRST QUARTER		589.00	90.00	149.36	64.00
		WEIGHTED AVERAGE FOR THE YEAR		589.00	90.00	149.36	64.00
===== 624-49031		30 In Equiv Drain Pipe E (CL 9) (CIP)		Lin Foot	=====		
TRG0253-264		I-25 AND SH 119 PARK-N-RIDE	10/27/22	314.00	300.00	208.65	103.00
	WEIGHTED	AVERAGE FOR THE FOURTH QUARTER		314.00	300.00	208.65	103.00
		WEIGHTED AVERAGE FOR THE YEAR		314.00	300.00	208.65	103.00

PROJECT NUMBER	ITEM NUMBER/ PROJECT LOCATION	ITEM DESCRIPTION/ PROJECT LOCATION	DATE LET	UNIT/ QUANTITY	ENGR. EST.	AVERAGE BID	AWARDED BID
===== 624-50019		18 In Equiv Drain Pipe E (CL 10)	(CIP)	Lin Foot	=====	=====	=====
NHPP0702-413		VAIL PASS AUX PHASE 1 CAP 2	04/18/22	48.00	292.77	292.77	292.77
	WEIGHTED AVERAGE FOR THE SECOND QUARTER			48.00	292.77	292.77	292.77
	WEIGHTED AVERAGE FOR THE YEAR			48.00	292.77	292.77	292.77
===== 625-00000		Const Surveying		LUMP SUM	=====	=====	=====
ITS0703-477		ITS EQUIPMENT UPGRADE AT EJMT	01/06/22	1.00	20000.00	32500.00	32500.00
NHPP2873-189		US 287 (FEDERAL BLVD) - COLFA	01/06/22	1.00	80000.00	153941.80	145680.79
NH0504-910		US50B L-24-B MIN REP AT MP 40	01/13/22	1.00	25000.00	25733.33	16666.67
NHPP0702-383		I-70 EB AUX FRISCO TO SILVERT	01/13/22	1.00	150000.00	424347.35	280000.00
NHPP1601-083			02/03/22	1.00	150000.00	211269.43	130000.00
C0762-055			02/17/22	1.00	15000.00	66558.26	50000.00
STR0141-031			02/17/22	1.00	20000.00	27000.00	27000.00
NHPP0063-063			02/24/22	1.00	200000.00	99205.00	125000.00
STA 067A-048		Hwy 67A MP 0.00 TO MP 11.05 I	03/03/22	1.00	20000.00	14334.48	14000.00
NHPP 0761-238		I-76 DAHLIA TO YORK	03/10/22	1.00	192000.00	313622.73	188000.00
C0761-239							
NHPP0253-275		I-25 EXPRESS LANES SEGMENT 5	03/11/22	1.00	61723.27	89636.36	89636.36
CR100-362			03/14/22	1.00	7393.27	7393.27	7393.27
ER007A-035			03/15/22	1.00	41540.00	44448.00	44448.00
STR160A-034		US160A LA VETA PASS EAST SURF	03/17/22	1.00	15000.00	22601.73	23203.45
BRC040-057			03/17/22	1.00	10000.00	41625.00	50000.00
M R100-351		FY22 R1 SIGN STRUCTURE REPLAC	03/17/22	1.00	19000.00	24197.00	16594.00
NHM765-007			03/31/22	1.00	250000.00	109731.12	113715.00
	WEIGHTED AVERAGE FOR THE FIRST QUARTER			17.00	75097.44	133829.75	79637.50
NH0504-911			04/07/22	1.00	20000.00	126500.00	153000.00
CC030-081		ADA RAMP AND CURBS - FT. LUPT	04/14/22	1.00	70000.00	27384.54	4000.00
NHPP0702-413		VAIL PASS AUX PHASE 1 CAP 2	04/18/22	1.00	469491.15	469491.15	469491.15
STM1151-038		SH115 MP 27 TO MP 38	04/21/22	1.00	310000.00	497446.46	250975.00
2670703-479		I-70 BRIDGE OVER HARLAN	05/05/22	1.00	350000.00	237150.92	86765.32
STA0712-019		SH 71: Frieght Improvements	05/12/22	1.00	35000.00	187083.96	187083.96
NHC540-017		R2 CHAINUP STA @ KENOSHA/HOOS	05/12/22	1.00	42000.00	103333.33	135000.00
CM760-047		COLFAX AND QUAIL	05/12/22	1.00	14000.00	10118.00	6350.00
NHPP 3851-018		US 385 NORTH OF CHEYENNE WELL	05/26/22	1.00	10000.00	42500.00	30000.00
FSA0702-409		I-70 VAIL WILDLIFE FENCE PHAS	05/26/22	1.00	30000.00	28000.00	28000.00
ITS 0741-024		VMS SIGN INSTALLATIONS AND VS	06/02/22	1.00	10000.00	31356.50	35000.00
FSA3921-019		SH 392 AND WCR 55 ISLANDS	06/02/22	1.00	4000.00	8033.33	4500.00

COLORADO DEPARTMENT OF TRANSPORTATION
 ITEM UNIT COSTS BY PROJECTS -- 2022 COST DATA

11:31 Wednesday, March 8, 2023 535

PROJECT NUMBER	ITEM NUMBER/ PROJECT LOCATION	ITEM DESCRIPTION/ PROJECT LOCATION	DATE LET	UNIT/ QUANTITY	ENGR. EST.	AVERAGE BID	AWARDED BID
=====	625-00000	Const Surveying		LUMP SUM	=====	=====	=====
NHPP072A-047		SH-72 RESURFACING: I-70 TO IN	06/09/22	1.00	65000.00	90175.05	90175.05
FSA052A-046		SH52 WCR 37 INTERSECTION IMPR	06/09/22	1.00	80000.00	62863.75	23000.00
MTCE0253-291		I-25 SIGN REPLACEMENT PHASE 2	06/16/22	1.00	25000.00	43062.36	43674.71
		WEIGHTED AVERAGE FOR THE SECOND QUARTER		15.00	102299.41	141735.43	103134.35
NHPP0702-414		VAIL PASS AUX PHASE 1 CAP 3	07/08/22	1.00	728948.15	728948.15	728948.15
FBR0702-423		VAIL PASS AUX BE F-12-AT PHAS					
FSA052A-057		SH52 BOX CULVERT EXTENSION (M	08/04/22	1.00	8000.00	15364.67	10634.00
STR0711-022		SH 71 OVER THE ARKANSAS	08/04/22	1.00	10000.00	13500.00	13000.00
NHPP0063-054		US 6 FROM I70-B TO 33 RD. (MP	08/18/22	1.00	200000.00	331659.65	450000.00
FBR0761-236		I-76 OVER CLR CRK SCOUR MIT	08/25/22	1.00	8000.00	46000.00	45000.00
C1211-099		SH 121 NORTH SGA SIGNALS	08/25/22	1.00	90000.00	40500.00	26000.00
ER0502-092		US 50 MP 204 EB MONARCH TRUCK	08/29/22	1.00	25000.00	14093.14	16390.53
BR0343-046		US 34 TIMBER BRIDGE REPL. PKG	08/31/22	1.00	25421.36	32100.00	32100.00
FBR0343-047		US 6/US 34 TIMBER BRIDGE REPL					
NHPPR100-266		R1 ESSENTIAL REPAIRS	09/01/22	1.00	45000.00	44750.00	66250.00
2670403-065		US40 FLOYD HILL ROUNDABOUTS	09/15/22	1.00	100000.00	155334.98	108000.00
2670703-497		I-70 GENESEE WILDLIFE XING	09/15/22	1.00	100000.00	162199.45	134436.18
SHE2873-193		US 287 & CO 52 INTERSECTION I	09/15/22	1.00	15000.00	112125.00	62000.00
NHPP0701-231		I-70 SALT WASH BRIDGES SCOUR	09/29/22	1.00	25000.00	42434.00	34868.00
		WEIGHTED AVERAGE FOR THE THIRD QUARTER		13.00	100413.63	107440.25	125694.78
STA207A-004		Resurfacing SH207A MANZANOLA	10/27/22	1.00	20000.00	52100.00	88300.00
NHPP0705-088		I-70 AGATE STRUCTURE REHAB	10/27/22	1.00	35000.00	48065.89	35500.00
FSAM240-200		SH21B CO SPRINGS SIGNAL REPLA	10/27/22	1.00	10000.00	29925.00	22000.00
C170A-002		CRITICAL CULVERT CONST. PKG D	10/27/22	1.00	10000.00	16575.28	13611.11
TRG0253-264		I-25 AND SH 119 PARK-N-RIDE	10/27/22	1.00	80000.00	264411.25	125000.00
STA3852-015		US 385 HOLYOKE NORTH	10/27/22	1.00	120000.00	120000.00	120000.00
NHPP0343-048		US 34 (MP 169.3-171.4)	11/01/22	1.00	25000.00	45585.19	26000.00
STU0252-457		I-25:ALAMEDA RIVER PH 2.0	11/03/22	1.00	300000.00	353013.65	280000.00
SHE0242-087		US 24 SAFETY IMPRVMENTS, E OF	11/03/22	1.00	35000.00	49825.07	29475.21
STR064A-010		SH 64 AND SH 13 AT MEEKER	11/10/22	1.00	50000.00	32265.00	45000.00
NHPP0853-126		US85C: PLATTEVILLE NORTH MP (11/10/22	1.00	35000.00	23720.00	45000.00
C5502-097		US550 MP 117.28-126.06	11/17/22	1.00	200000.00	211133.81	180000.00
STRC090-011		US 50B AND SH71/CR18 INTERSEC	11/17/22	1.00	50000.00	29000.00	28000.00
STAM420-001		US 285 AT HWY 9C IMPROVEMENTS	12/01/22	1.00	200000.00	307934.15	254774.13
BR2854-148		INTERSECTION OF US 285 & SH 9					
STM0091-046		ADA RAMP IMPROVEMENTS - FAIRP					
STA0711-021		SH71: REGION LINE NORTH	12/01/22	1.00	66825.00	64666.67	40000.00
2670703-487		I-70 BRIDGES OVER WARD ROAD-	12/01/22	1.00	100000.00	217980.90	110000.00

PROJECT NUMBER	ITEM NUMBER/ PROJECT LOCATION	ITEM DESCRIPTION/ PROJECT LOCATION	DATE LET	UNIT/ QUANTITY	ENGR. EST.	AVERAGE BID	AWARDED BID
===== 625-00000 Const Surveying LUMP SUM =====							
NHPP0701-252		I-70 RIFLE TO SILT SLAB REPLA	12/01/22	1.00	50000.00	20250.00	20000.00
IM025A-050		I25-MP103.9 - INTERSECTION DR	12/01/22	1.00	149000.00	195000.00	230000.00
NHPP0021-041		SH2 RESURFACING MLK TO 52ND	12/01/22	1.00	95000.00	49755.22	30690.83
NHPP0063-048		US6 / 20 ROAD INTERSECTION IM	12/15/22	1.00	60000.00	86338.39	152000.00
NHPP0931-033		SH93:US6 TO 58TH RESURFACING	12/15/22	1.00	20000.00	58510.17	76900.00
NHPP0502-090		SH 50 MP 134.6-136 GUNNISON C	12/22/22	1.00	120000.00	103260.84	94578.09
STA0361-129		US 36: HYGIENE RD AND NELSON	12/22/22	1.00	30000.00	42342.84	26114.18
BR012A-048		CO 12 STRUCTURE P-17-F AT MP	12/22/22	1.00	50000.00	65908.40	50000.00
STA385A-016		SH 385 MP 97.76	12/22/22	1.00	40000.00	54222.22	31888.89
STR096A-050		SH 96 MP 168.99 TO 193.77	12/22/22	1.00	40000.00	53333.33	35000.00
	WEIGHTED AVERAGE FOR THE FOURTH QUARTER			26.00	76570.19	110750.80	85992.23
	WEIGHTED AVERAGE FOR THE YEAR			71.00	86218.94	120941.50	95518.41
===== 625-00001 Const Surveying (Hour) Hour =====							
NHPP2873-189		US 287 (FEDERAL BLVD) - COLFA	01/06/22	240.00	180.00	250.69	245.81
NHPP0702-383		I-70 EB AUX FRISCO TO SILVERT	01/13/22	80.00	200.00	222.86	264.00
STA0252-459			02/03/22	150.00	183.75	256.10	220.00
NHPP0063-063			02/24/22	10.00	200.00	177.50	185.00
	WEIGHTED AVERAGE FOR THE FIRST QUARTER			480.00	184.92	245.13	239.51
FSA0702-409		I-70 VAIL WILDLIFE FENCE PHAS	05/26/22	10.00	220.00	200.00	200.00
	WEIGHTED AVERAGE FOR THE SECOND QUARTER			10.00	220.00	200.00	200.00
NHPP0063-054		US 6 FROM I70-B TO 33 RD. (MP	08/18/22	280.00	200.00	210.59	210.00
NHPP0701-231		I-70 SALT WASH BRIDGES SCOUR	09/29/22	10.00	250.00	204.75	215.00
	WEIGHTED AVERAGE FOR THE THIRD QUARTER			290.00	201.72	210.39	210.17
C5502-097		US550 MP 117.28-126.06	11/17/22	240.00	200.00	256.22	240.00
NHPP0701-252		I-70 RIFLE TO SILT SLAB REPLA	12/01/22	20.00	250.00	249.50	224.00
NHPP0021-041		SH2 RESURFACING MLK TO 52ND	12/01/22	220.00	250.00	297.29	257.80
NHPP083A-046		SH83 RESURFACING STROH RD TO	12/08/22	50.00	175.00	258.90	299.79

COLORADO DEPARTMENT OF TRANSPORTATION
 ITEM UNIT COSTS BY PROJECTS -- 2022 COST DATA

11:31 Wednesday, March 8, 2023 537

PROJECT NUMBER	ITEM NUMBER/ PROJECT LOCATION	ITEM DESCRIPTION/ PROJECT LOCATION	DATE LET	UNIT/ QUANTITY	ENGR. EST.	AVERAGE BID	AWARDED BID
===== 625-00001							
		Const Surveying (Hour)		Hour			
NHPP0063-048		US6 / 20 ROAD INTERSECTION IM	12/15/22	40.00	200.00	217.72	180.00
STA0361-129		US 36: HYGIENE RD AND NELSON	12/22/22	20.00	125.00	241.18	200.88
		WEIGHTED AVERAGE FOR THE FOURTH QUARTER		590.00	215.68	270.45	245.77
		WEIGHTED AVERAGE FOR THE YEAR		1,370.00	201.98	251.93	235.71
===== 626-00000							
		Mobilization		LUMP SUM			
ITS0703-477		ITS EQUIPMENT UPGRADE AT EJMT	01/06/22	1.00	700000.00	780000.00	780000.00
MTCE R500-219			01/06/22	1.00	60000.00	96666.67	75000.00
MTCE R500-218			01/06/22	1.00	75000.00	76184.50	100000.00
NHPP2873-189		US 287 (FEDERAL BLVD) - COLFA	01/06/22	1.00	380207.00	428203.10	321624.56
STR0505-050			01/13/22	1.00	175000.00	232037.08	275000.00
NH0504-910		US50B L-24-B MIN REP AT MP 40	01/13/22	1.00	229601.00	246791.10	165124.86
MTCER400-391		VARIOUS HIGHWAY SEGMENTS ACRO	01/13/22	1.00	50000.00	73750.00	45000.00
NHPP0702-383		I-70 EB AUX FRISCO TO SILVERT	01/13/22	1.00	2000000.00	2673888.12	2067000.00
MTCER300-262			02/03/22	1.00	200000.00	353333.33	180000.00
NHPP1601-083			02/03/22	1.00	1700000.00	1859589.50	2000000.00
STA0252-459			02/03/22	1.00	400000.00	530225.33	201000.00
C0762-055			02/17/22	1.00	694114.50	1088724.56	700000.00
STR0141-031			02/17/22	1.00	637754.29	743046.79	660640.38
STR133A-051			02/17/22	1.00	120000.00	169333.33	225000.00
NHPP0063-063			02/24/22	1.00	700000.00	1037000.00	914000.00
STA 067A-048		Hwy 67A MP 0.00 TO MP 11.05 I	03/03/22	1.00	321199.25	381542.22	450000.00
NHPP 0761-238		I-76 DAHLIA TO YORK	03/10/22	1.00	1000000.00	1092058.79	1150000.00
C0761-239							
NHPP0703-472			03/10/22	1.00	521125.20	543595.54	671250.00
STR160A-034		US160A LA VETA PASS EAST SURF	03/17/22	1.00	654967.00	641994.83	643989.66
BRC040-057			03/17/22	1.00	451919.00	358979.88	255000.00
STR R500-171		Various locations on SH 141 a	03/17/22	1.00	360000.00	457851.67	200555.00
M R100-351		FY22 R1 SIGN STRUCTURE REPLAC	03/17/22	1.00	73077.00	130237.00	153524.00
STR092A-031			03/17/22	1.00	800000.00	800000.00	800000.00
MP0503-098			03/24/22	1.00	101620.00	66180.00	61000.00
NHM765-007			03/31/22	1.00	1866244.00	1271408.30	1574060.76
C0703-499		EJMT GROUT BED REPAIR AND PAN	03/31/22	1.00	175000.00	170600.00	131000.00
		WEIGHTED AVERAGE FOR THE FIRST QUARTER		26.00	572104.75	706952.48	590732.19
NH0504-911			04/07/22	1.00	1841988.88	1562500.00	1155000.00
CC030-081		ADA RAMP AND CURBS - FT. LUPT	04/14/22	1.00	200000.00	277825.42	202976.25
STM1151-038		SH115 MP 27 TO MP 38	04/21/22	1.00	1507599.90	3292354.76	3608092.00
MTCE2873-204		MTCE FY22 SH287 CONC PANEL RE	05/05/22	1.00	63350.00	193500.00	185000.00

PROJECT NUMBER	ITEM NUMBER/ PROJECT LOCATION	ITEM DESCRIPTION/ PROJECT LOCATION	DATE LET	UNIT/ QUANTITY	ENGR. EST.	AVERAGE BID	AWARDED BID
=====	626-00000	Mobilization		LUMP SUM	=====	=====	=====
2670703-479		I-70 BRIDGE OVER HARLAN	05/05/22	1.00	1855630.20	1674815.66	1625525.96
ER0702-420		PR I-70 GWC MATERIAL FLOWS 20	05/06/22	1.00	250000.00	472500.00	345000.00
STA0712-019		SH 71: Frieight Improvements	05/12/22	1.00	780000.00	937665.73	937665.73
STA001A-005		SH1 WELLINGTON SOUTH RESURFAC	05/12/22	1.00	650000.00	212500.00	300000.00
NHC540-017		R2 CHAINUP STA @ KENOSHA/HOOS	05/12/22	1.00	805912.50	770000.00	680000.00
CM760-047		COLFAX AND QUAIL	05/12/22	1.00	2650.00	91669.60	62348.00
NHPP 3851-018		US 385 NORTH OF CHEYENNE WELL	05/26/22	1.00	975000.00	1356315.01	897798.60
STAR100-358		3 STRUCTURES IN REGION 1 METR	05/26/22	1.00	199937.00	239364.00	135092.00
C0852-120		Rehabilitation of Culvert by	05/26/22	1.00	85000.00	58000.00	58000.00
FSA0702-409		I-70 VAIL WILDLIFE FENCE PHAS	05/26/22	1.00	660000.00	750000.00	750000.00
ITS 0741-024		VMS SIGN INSTALLATIONS AND VS	06/02/22	1.00	219795.00	334927.95	460000.00
FSA3921-019		SH 392 AND WCR 55 ISLANDS	06/02/22	1.00	20000.00	29191.67	9000.00
NHPP072A-047		SH-72 RESURFACING: I-70 TO IN	06/09/22	1.00	600000.00	585384.22	585384.22
FSA052A-046		SH52 WCR 37 INTERSECTION IMPR	06/09/22	1.00	300000.00	228195.00	175350.00
MPR200-278		R2 - VARIOUS LOCATIONS	06/09/22	1.00	120000.00	83333.33	75000.00
MPR200-279		FY 23 STENCIL MARKING PROJECT	06/09/22	1.00	32001.55	40000.00	35000.00
MTCE0253-291		I-25 SIGN REPLACEMENT PHASE 2	06/16/22	1.00	161253.55	318953.50	400000.00
NHPP0252-448		I-25 TREX NARROWS BRIDGE PREV	06/23/22	1.00	334355.00	294493.25	371973.00
MTCE R100-380		REGION 1 FY 23/24 PAVEMENT MA	06/30/22	1.00	239858.11	75000.00	75000.00
		WEIGHTED AVERAGE FOR THE SECOND QUARTER		23.00	517579.64	724444.35	570835.03
MT CER300-273		I-70 MM 75-116, OTHER REGION	07/07/22	1.00	35000.00	42333.33	42000.00
MTCE 072A-045		SH 72B MP 37.00 TO MP 45.3 NE	07/07/22	1.00	99988.00	95000.00	95000.00
MTCE0702-426		I70 FROM MP 155 TO 180 AND MP	07/07/22	1.00	35000.00	23125.00	20000.00
MT CER300-272		REGION 3 ROUNDABOUT STRIPING	07/07/22	1.00	40000.00	39333.33	33000.00
FSA052A-057		SH52 BOX CULVERT EXTENSION (M	08/04/22	1.00	50000.00	93889.31	75000.00
STR0711-022		SH 71 OVER THE ARKANSAS	08/04/22	1.00	59585.87	83333.33	105000.00
NHPP0063-054		US 6 FROM I70-B TO 33 RD. (MP	08/18/22	1.00	200000.00	1403962.76	1807000.00
FBR0761-236		I-76 OVER CLR CRK SCOUR MIT	08/25/22	1.00	425530.80	143000.00	141000.00
MT CER400-396		REGION 4	08/25/22	1.00	20000.00	18333.33	25000.00
C1211-099		SH 121 NORTH SGA SIGNALS	08/25/22	1.00	70000.00	459562.50	244125.00
ER0502-092		US 50 MP 204 EB MONARCH TRUCK	08/29/22	1.00	100000.00	109784.37	93467.73
BR0343-046		US 34 TIMBER BRIDGE REPL. PKG	08/31/22	1.00	460790.60	507868.90	507868.90
FBR0343-047		US 6/US 34 TIMBER BRIDGE REPL					
STAR100-374		5 STRUCTURES IN REGION 1	09/01/22	1.00	165420.00	241564.95	241564.95
NHPPR100-266		R1 ESSENTIAL REPAIRS	09/01/22	1.00	198379.00	212775.89	262146.67
PAN0761-245		ALONG I-76 & RAMPS MILEPOST 9	09/01/22	1.00	50000.00	102500.00	95000.00
ER0253-297		WCR 34 BRIDGE OVER I-25(MM 24	09/14/22	1.00	20000.00	521179.75	20800.00
2670403-065		US40 FLOYD HILL ROUNDABOUTS	09/15/22	1.00	800000.00	808041.60	750000.00
2670703-497		I-70 GENESEE WILDLIFE XING	09/15/22	1.00	1170660.40	1180743.63	474032.90
SHE2873-193		US 287 & CO 52 INTERSECTION I	09/15/22	1.00	365000.00	657242.97	380000.00
NHPP0701-231		I-70 SALT WASH BRIDGES SCOUR	09/29/22	1.00	300000.00	548798.65	297597.30
		WEIGHTED AVERAGE FOR THE THIRD QUARTER		20.00	359816.44	422244.70	285480.17

PROJECT NUMBER	ITEM NUMBER/ PROJECT LOCATION	ITEM DESCRIPTION/ PROJECT LOCATION	DATE LET	UNIT/ QUANTITY	ENGR. EST.	AVERAGE BID	AWARDED BID
=====	626-00000	Mobilization		LUMP SUM	=====		
MTCE0253-281		MTCE FY23 I-25 CONC PANEL REP	10/06/22	1.00	200000.00	173967.00	85000.00
NHPP0821-114		SH 82 ASPEN/INDEPENDENCE PASS	10/13/22	1.00	200000.00	244833.33	250000.00
C0831-126		SH83 EL PASO COUNTY TO BAYOU	10/13/22	1.00	35406.00	105000.00	60000.00
NHPP0701-253		I-70 EAST OF DEBEQUE	10/27/22	1.00	650000.00	538500.00	412000.00
STA207A-004		Resurfacing SH207A MANZANOLA	10/27/22	1.00	770784.50	714363.00	475000.00
NHPP0705-088		I-70 AGATE STRUCTURE REHAB	10/27/22	1.00	400000.00	509111.82	511000.00
FSAM240-200		SH21B CO SPRINGS SIGNAL REPLA	10/27/22	1.00	309066.29	305150.00	145000.00
C5502-111		US 550 MP 81 AND 89 RED MOUNT	10/27/22	1.00	50000.00	96300.00	67600.00
C170A-002		CRITICAL CULVERT CONST. PKG D	10/27/22	1.00	68530.50	84681.96	75527.82
TRG0253-264		I-25 AND SH 119 PARK-N-RIDE	10/27/22	1.00	719011.55	1341771.51	980000.00
STA3852-015		US 385 HOLYOKE NORTH	10/27/22	1.00	1483430.38	1542000.90	1542000.90
NHPP0343-048		US 34 (MP 169.3-171.4)	11/01/22	1.00	400000.00	267401.45	123688.80
STU0252-457		I-25:ALAMEDA RIVER PH 2.0	11/03/22	1.00	2500000.00	2261717.98	2092000.00
SHE0242-087		US 24 SAFETY IMPRVMENTS, E OF	11/03/22	1.00	412941.90	226659.04	223977.13
STR064A-010		SH 64 AND SH 13 AT MEEKER	11/10/22	1.00	680000.00	860000.00	840000.00
NHPP0853-126		US85C: PLATTEVILLE NORTH MP (11/10/22	1.00	600683.30	313007.60	345000.00
C5502-097		US550 MP 117.28-126.06	11/17/22	1.00	1900000.00	1716991.13	1895000.89
MPR200-280		PUEBLO AREA	11/17/22	1.00	108129.70	140000.00	85000.00
STRC090-011		US 50B AND SH71/CR18 INTERSEC	11/17/22	1.00	320620.75	407000.00	264000.00
STAM420-001		US 285 AT HWY 9C IMPROVEMENTS	12/01/22	1.00	1670011.38	2327674.33	2315469.85
BR2854-148		INTERSECTION OF US 285 & SH 9					
STM0091-046		ADA RAMP IMPROVEMENTS - FAIRP					
STA0711-021		SH71: REGION LINE NORTH	12/01/22	1.00	1200000.00	1351666.67	934000.00
STR114A-015		SH114 SILLSVILLE SOUTH TO MP3	12/01/22	1.00	1500000.00	1707500.00	905000.00
2670703-487		I-70 BRIDGES OVER WARD ROAD-	12/01/22	1.00	1072997.30	1538231.21	1631000.00
NHPP0701-252		I-70 RIFLE TO SILT SLAB REPLA	12/01/22	1.00	1200000.00	476500.00	284000.00
IM025A-050		I25-MP103.9 - INTERSECTION DR	12/01/22	1.00	597119.00	1143333.33	1000000.00
STR318A-001		SH 318 MP 0 - 12.5 MOFFAT COU	12/01/22	1.00	780000.00	771000.07	600000.14
STR109A-019		M-22-AY BRIDGE REHAB ON SH109	12/01/22	1.00	998932.00	1180012.98	1230025.96
NHPP0021-041		SH2 RESURFACING MLK TO 52ND	12/01/22	1.00	300000.00	293795.76	204249.23
STR0641-107		SH 13 MM 104-128.1 IN MOFFAT	12/01/22	1.00	400000.00	422340.00	495000.00
NHPP083A-046		SH83 RESURFACING STROH RD TO	12/08/22	1.00	980366.75	434065.19	308130.38
NHPP0063-048		US6 / 20 ROAD INTERSECTION IM	12/15/22	1.00	450000.00	422634.11	400000.00
NHM175-029		CANON CITY, CO	12/15/22	1.00	296150.20	275500.00	301000.00
FSA0853-122		WCR14.5 AND US-85, FORT LUPTO	12/15/22	1.00	35000.00	76384.45	28000.00
NHPP0931-033		SH93:US6 TO 58TH RESURFACING	12/15/22	1.00	565857.00	371773.50	306000.00
NHPP0502-090		SH 50 MP 134.6-136 GUNNISON C	12/22/22	1.00	800000.00	968174.52	552753.69
STR0092-024		SH 9 North of Silverthorne	12/22/22	1.00	800000.00	1010000.25	875000.49
STA0361-129		US 36: HYGIENE RD AND NELSON	12/22/22	1.00	350000.00	285872.84	213648.18
BR012A-048		CO 12 STRUCTURE P-17-F AT MP	12/22/22	1.00	655191.00	1030000.00	460000.00
STA385A-016		SH 385 MP 97.76	12/22/22	1.00	300000.00	578534.71	464138.85
STR096A-050		SH 96 MP 168.99 TO 193.77	12/22/22	1.00	1074879.80	1403566.72	1761000.00
		WEIGHTED AVERAGE FOR THE FOURTH QUARTER		40.00	695877.73	773422.84	657926.10
		WEIGHTED AVERAGE FOR THE YEAR		109.00	565246.98	688319.00	558224.79

COLORADO DEPARTMENT OF TRANSPORTATION
ITEM UNIT COSTS BY PROJECTS -- 2022 COST DATA

11:31 Wednesday, March 8, 2023 540

PROJECT NUMBER	ITEM NUMBER/ PROJECT LOCATION	ITEM DESCRIPTION/ PROJECT LOCATION	DATE LET	UNIT/ QUANTITY	ENGR. EST.	AVERAGE BID	AWARDED BID
===== 626-00100		Mobilization (w/o Autopay)		LUMP SUM	=====		
NHPP0253-275		I-25 EXPRESS LANES SEGMENT 5	03/11/22	1.00	319481.37	432828.97	432828.97
CR100-362			03/14/22	1.00	1152902.83	1152902.83	1152902.83
ER007A-035			03/15/22	1.00	171239.00	149920.78	149920.78
		WEIGHTED AVERAGE FOR THE FIRST QUARTER		3.00	490776.14	542120.39	542120.39
NHPP0702-413		VAIL PASS AUX PHASE 1 CAP 2	04/18/22	1.00	6642018.74	6642018.74	6642018.74
		WEIGHTED AVERAGE FOR THE SECOND QUARTER		1.00	6642018.74	6642018.74	6642018.74
NHPP0702-414		VAIL PASS AUX PHASE 1 CAP 3	07/08/22	1.00	12721547.66	12721547.67	12721547.67
FBR0702-423		VAIL PASS AUX BE F-12-AT PHAS					
		WEIGHTED AVERAGE FOR THE THIRD QUARTER		1.00	12721547.66	12721547.67	12721547.67
		WEIGHTED AVERAGE FOR THE YEAR		5.00	3554445.16	3588674.66	3588674.66
===== 626-01111		Public Info Manage (Tier I)		Day	=====		
NHPP0253-275		I-25 EXPRESS LANES SEGMENT 5	03/11/22	205.00	125.00	133.75	133.75
		WEIGHTED AVERAGE FOR THE FIRST QUARTER		205.00	125.00	133.75	133.75
2670703-487		I-70 BRIDGES OVER WARD ROAD-	12/01/22	588.00	300.00	158.98	130.00
		WEIGHTED AVERAGE FOR THE FOURTH QUARTER		588.00	300.00	158.98	130.00
		WEIGHTED AVERAGE FOR THE YEAR		793.00	254.76	157.33	130.97
===== 626-01112		Public Info Manage (Tier II)		Day	=====		
NHM765-007			03/31/22	600.00	100.00	87.55	79.80
		WEIGHTED AVERAGE FOR THE FIRST QUARTER		600.00	100.00	87.55	79.80

COLORADO DEPARTMENT OF TRANSPORTATION
ITEM UNIT COSTS BY PROJECTS -- 2022 COST DATA

11:31 Wednesday, March 8, 2023 541

PROJECT NUMBER	ITEM NUMBER/ PROJECT LOCATION	ITEM DESCRIPTION/ PROJECT LOCATION	DATE LET	UNIT/ QUANTITY	ENGR. EST.	AVERAGE BID	AWARDED BID
=====	626-01112	Public Info Manage (Tier II)		Day	=====		
NHPP0702-413		VAIL PASS AUX PHASE 1 CAP 2	04/18/22	180.00	474.37	474.37	474.37
		WEIGHTED AVERAGE FOR THE SECOND QUARTER		180.00	474.37	474.37	474.37
NHPP0702-414 FBR0702-423		VAIL PASS AUX PHASE 1 CAP 3 VAIL PASS AUX BE F-12-AT PHAS	07/08/22	330.00	256.80	256.80	256.80
		WEIGHTED AVERAGE FOR THE THIRD QUARTER		330.00	256.80	256.80	256.80
STU0252-457		I-25:ALAMEDA RIVER PH 2.0	11/03/22	510.00	300.00	103.70	110.00
		WEIGHTED AVERAGE FOR THE FOURTH QUARTER		510.00	300.00	103.70	110.00
		WEIGHTED AVERAGE FOR THE YEAR		1,620.00	236.50	126.66	169.20
=====	626-01113	Public Info Manage (Tier III)		Day	=====		
ITS0703-477		ITS EQUIPMENT UPGRADE AT EJMT	01/06/22	100.00	100.00	2635.00	2635.00
NHPP2873-189		US 287 (FEDERAL BLVD) - COLFA	01/06/22	100.00	200.00	102.36	122.18
NHPP0702-383		I-70 EB AUX FRISCO TO SILVERT	01/13/22	426.00	75.00	78.77	75.00
STA0252-459			02/03/22	200.00	80.00	84.00	75.00
STR0141-031			02/17/22	94.00	200.00	64.50	72.00
NHPP0063-063			02/24/22	175.00	217.00	57.50	55.00
NHPP 0761-238 C0761-239		I-76 DAHLIA TO YORK	03/10/22	800.00	120.00	70.58	125.00
NHPP0703-472			03/10/22	90.00	100.00	148.94	100.00
BRC040-057			03/17/22	125.00	100.00	84.00	63.00
STR092A-031			03/17/22	145.00	70.00	68.00	68.00
		WEIGHTED AVERAGE FOR THE FIRST QUARTER		2,255.00	116.35	99.24	206.56
2670703-479		I-70 BRIDGE OVER HARLAN	05/05/22	696.00	90.00	83.17	92.50
ER0702-420		PR I-70 GWC MATERIAL FLOWS 20	05/06/22	185.00	180.00	81.50	88.00

COLORADO DEPARTMENT OF TRANSPORTATION
ITEM UNIT COSTS BY PROJECTS -- 2022 COST DATA

11:31 Wednesday, March 8, 2023 542

PROJECT NUMBER	ITEM NUMBER/ PROJECT LOCATION	ITEM DESCRIPTION/ PROJECT LOCATION	DATE LET	UNIT/ QUANTITY	ENGR. EST.	AVERAGE BID	AWARDED BID
===== 626-01113 Public Info Manage (Tier III) Day =====							
NHC540-017		R2 CHAINUP STA @ KENOSHA/HOOS	05/12/22	313.00	78.00	73.33	80.00
STAR100-358		3 STRUCTURES IN REGION 1 METR	05/26/22	150.00	100.00	67.61	64.00
FSA0702-409		I-70 VAIL WILDLIFE FENCE PHAS	05/26/22	140.00	110.00	90.00	90.00
NHPP072A-047		SH-72 RESURFACING: I-70 TO IN	06/09/22	180.00	120.00	102.92	102.92
NHPP0252-448		I-25 TREX NARROWS BRIDGE PREV	06/23/22	222.00	95.00	76.23	85.00
WEIGHTED AVERAGE FOR THE SECOND QUARTER				1,886.00	102.57	80.58	87.64
STAR100-374		5 STRUCTURES IN REGION 1	09/01/22	189.00	70.00	87.22	87.22
ER0253-297		WCR 34 BRIDGE OVER I-25(MM 24	09/14/22	20.00	100.00	694.50	340.00
2670403-065		US40 FLOYD HILL ROUNDABOUTS	09/15/22	290.00	80.00	82.08	80.00
2670703-497		I-70_GENESEE WILDLIFE XING	09/15/22	445.00	87.00	77.53	91.30
NHPP0701-231		I-70 SALT WASH BRIDGES SCOUR	09/29/22	144.00	110.00	100.67	110.00
WEIGHTED AVERAGE FOR THE THIRD QUARTER				1,088.00	85.46	91.14	94.63
NHPP0701-253		I-70 EAST OF DEBEQUE	10/27/22	130.00	90.00	60.75	60.00
FSAM240-200		SH21B CO SPRINGS SIGNAL REPLA	10/27/22	171.00	70.00	80.50	98.00
C170A-002		CRITICAL CULVERT CONST. PKG D	10/27/22	44.00	200.00	141.00	120.00
SHE0242-087		US 24 SAFETY IMPRVMENTS, E OF	11/03/22	100.00	80.00	107.15	76.44
STR064A-010		SH 64 AND SH 13 AT MEEKER	11/10/22	179.00	90.00	66.80	65.00
C5502-097		US550 MP 117.28-126.06	11/17/22	275.00	70.00	63.40	59.40
STRC090-011		US 50B AND SH71/CR18 INTERSEC	11/17/22	165.00	90.00	94.00	105.00
STAM420-001		US 285 AT HWY 9C IMPROVEMENTS	12/01/22	600.00	70.00	82.37	82.69
BR2854-148		INTERSECTION OF US 285 & SH 9					
STM0091-046		ADA RAMP IMPROVEMENTS - FAIRP					
NHPP0701-252		I-70 RIFLE TO SILT SLAB REPLA	12/01/22	215.00	80.00	55.00	55.00
STR318A-001		SH 318 MP 0 - 12.5 MOFFAT COU	12/01/22	152.00	90.00	53.45	53.90
STR109A-019		M-22-AY BRIDGE REHAB ON SH109	12/01/22	420.00	75.00	46.40	41.80
NHPP0021-041		SH2 RESURFACING MLK TO 52ND	12/01/22	55.00	150.00	110.26	104.35
NHPP0063-048		US6 / 20 ROAD INTERSECTION IM	12/15/22	99.00	90.00	145.76	128.00
NHPP0931-033		SH93:US6 TO 58TH RESURFACING	12/15/22	200.00	120.00	86.32	82.00
NHPP0502-090		SH 50 MP 134.6-136 GUNNISON C	12/22/22	284.00	75.00	44.19	41.84
STR0092-024		SH 9 North of Silverthorne	12/22/22	180.00	200.00	67.55	70.10
WEIGHTED AVERAGE FOR THE FOURTH QUARTER				3,269.00	89.79	74.46	70.47
WEIGHTED AVERAGE FOR THE YEAR				8,498.00	99.12	86.31	112.50
===== 626-01114 Public Info Manage (Tier IV) Day =====							
MTCE R500-219			01/06/22	95.00	90.00	78.50	85.00

COLORADO DEPARTMENT OF TRANSPORTATION
ITEM UNIT COSTS BY PROJECTS -- 2022 COST DATA

11:31 Wednesday, March 8, 2023 543

PROJECT NUMBER	ITEM NUMBER/ PROJECT LOCATION	ITEM DESCRIPTION/ PROJECT LOCATION	DATE LET	UNIT/ QUANTITY	ENGR. EST.	AVERAGE BID	AWARDED BID
===== 626-01114							
		Public Info Manage (Tier IV)		Day			
MTCE R500-218			01/06/22	50.00	50.00	102.50	75.00
STR0505-050			01/13/22	75.00	100.00	91.00	100.00
NH0504-910		US50B L-24-B MIN REP AT MP 40	01/13/22	184.00	70.00	70.51	66.67
NHPP1601-083			02/03/22	277.00	150.00	73.48	66.00
C0762-055			02/17/22	160.00	70.00	58.53	57.00
STR133A-051			02/17/22	49.00	100.00	81.67	65.00
STA 067A-048		Hwy 67A MP 0.00 TO MP 11.05 I	03/03/22	115.00	80.00	68.75	55.00
CR100-362			03/14/22	300.00	74.90	74.90	74.90
STR R500-171		Various locations on SH 141 a	03/17/22	140.00	46.00	88.59	150.00
M R100-351		FY22 R1 SIGN STRUCTURE REPLAC	03/17/22	86.00	100.00	84.50	96.00
MP0503-098			03/24/22	35.00	80.00	94.50	80.00
WEIGHTED AVERAGE FOR THE FIRST QUARTER				1,566.00	88.50	74.34	78.56
NH0504-911			04/07/22	350.00	100.00	63.80	77.60
CC030-081		ADA RAMP AND CURBS - FT. LUPT	04/14/22	120.00	75.00	73.29	60.00
MTCE2873-204		MTCE FY22 SH287 CONC PANEL RE	05/05/22	10.00	300.00	199.08	163.15
STA0712-019		SH 71: Frieght Improvements	05/12/22	180.00	75.00	55.49	55.49
STA001A-005		SH1 WELLINGTON SOUTH RESURFAC	05/12/22	86.00	85.00	81.95	75.00
CM760-047		COLFAX AND QUAIL	05/12/22	70.00	60.00	94.20	63.00
NHPP 3851-018		US 385 NORTH OF CHEYENNE WELL	05/26/22	103.00	100.00	59.50	60.00
C0852-120		Rehabilitation of Culvert by	05/26/22	37.00	175.00	80.00	80.00
ITS 0741-024		VMS SIGN INSTALLATIONS AND VS	06/02/22	50.00	80.00	83.50	77.00
FSA3921-019		SH 392 AND WCR 55 ISLANDS	06/02/22	24.00	100.00	122.67	140.00
MPR200-278		R2 - VARIOUS LOCATIONS	06/09/22	161.00	125.00	88.33	105.00
MPR200-279		FY 23 STENCIL MARKING PROJECT	06/09/22	47.00	100.00	130.00	115.00
WEIGHTED AVERAGE FOR THE SECOND QUARTER				1,238.00	96.94	79.93	77.14
MTCE 072A-045		SH 72B MP 37.00 TO MP 45.3 NE	07/07/22	15.00	180.00	115.00	115.00
STR0711-022		SH 71 OVER THE ARKANSAS	08/04/22	40.00	100.00	76.67	90.00
FBR0761-236		I-76 OVER CLR CRK SCOUR MIT	08/25/22	160.00	100.00	53.17	60.00
C1211-099		SH 121 NORTH SGA SIGNALS	08/25/22	150.00	80.00	82.50	80.00
WEIGHTED AVERAGE FOR THE THIRD QUARTER				365.00	95.07	66.88	73.77
MTCE0253-281		MTCE FY23 I-25 CONC PANEL REP	10/06/22	25.00	200.00	112.41	119.00
NHPP0821-114		SH 82 ASPEN/INDEPENDENCE PASS	10/13/22	60.00	120.00	66.60	64.80
C0831-126		SH83 EL PASO COUNTY TO BAYOU	10/13/22	77.00	90.00	85.00	75.00

PROJECT NUMBER	ITEM NUMBER/ PROJECT LOCATION	ITEM DESCRIPTION/ PROJECT LOCATION	DATE LET	UNIT/ QUANTITY	ENGR. EST.	AVERAGE BID	AWARDED BID
===== 626-01114 Public Info Manage (Tier IV) Day =====							
STA207A-004		Resurfacing SH207A MANZANOLA	10/27/22	210.00	75.00	60.37	76.10
NHPP0705-088		I-70 AGATE STRUCTURE REHAB	10/27/22	201.00	75.00	70.76	68.00
C5502-111		US 550 MP 81 AND 89 RED MOUNT	10/27/22	91.00	65.00	92.50	100.00
STA3852-015		US 385 HOLYOKE NORTH	10/27/22	160.00	75.00	57.00	57.00
MPR200-280		PUEBLO AREA	11/17/22	177.00	67.00	97.50	120.00
STA0711-021		SH71: REGION LINE NORTH	12/01/22	115.00	63.00	71.00	60.00
STR114A-015		SH114 SILLSVILLE SOUTH TO MP3	12/01/22	169.00	250.00	49.50	57.00
STR0641-107		SH 13 MM 104-128.1 IN MOFFAT	12/01/22	138.00	60.00	73.97	25.00
NHPP083A-046		SH83 RESURFACING STROH RD TO	12/08/22	114.00	75.00	117.09	83.17
NHM175-029		CANON CITY, CO	12/15/22	75.00	100.00	57.50	90.00
STA0361-129		US 36: HYGIENE RD AND NELSON	12/22/22	99.00	75.00	91.69	61.38
STA385A-016		SH 385 MP 97.76	12/22/22	224.00	50.00	76.53	69.10
STR096A-050		SH 96 MP 168.99 TO 193.77	12/22/22	175.00	68.00	55.33	55.00
	WEIGHTED AVERAGE FOR THE FOURTH QUARTER			2,110.00	87.24	73.62	70.51
	WEIGHTED AVERAGE FOR THE YEAR			5,279.00	90.43	74.64	74.63
===== 627-00001 Pvmt Mkg Paint Gallon =====							
NH0504-910		US50B L-24-B MIN REP AT MP 40	01/13/22	68.00	70.00	106.57	127.78
	WEIGHTED AVERAGE FOR THE FIRST QUARTER			68.00	70.00	106.57	127.78
STR0711-022		SH 71 OVER THE ARKANSAS	08/04/22	2.00	200.00	933.33	1300.00
	WEIGHTED AVERAGE FOR THE THIRD QUARTER			2.00	200.00	933.33	1300.00
BR012A-048		CO 12 STRUCTURE P-17-F AT MP	12/22/22	20.00	200.00	462.39	430.00
STA385A-016		SH 385 MP 97.76	12/22/22	186.00	130.00	109.22	138.89
STR096A-050		SH 96 MP 168.99 TO 193.77	12/22/22	3,835.00	51.00	57.00	54.00
	WEIGHTED AVERAGE FOR THE FOURTH QUARTER			4,041.00	55.37	61.48	59.77
	WEIGHTED AVERAGE FOR THE YEAR			4,111.00	55.69	63.80	61.50
===== 627-00002 Thermoplastic Pvmt Mkg Sq Foot =====							
C170A-002		CRITICAL CULVERT CONST. PKG D	10/27/22	10.00	75.00	56.53	61.11
	WEIGHTED AVERAGE FOR THE FOURTH QUARTER			10.00	75.00	56.53	61.11
	WEIGHTED AVERAGE FOR THE YEAR			10.00	75.00	56.53	61.11

COLORADO DEPARTMENT OF TRANSPORTATION
 ITEM UNIT COSTS BY PROJECTS -- 2022 COST DATA

11:31 Wednesday, March 8, 2023 545

PROJECT NUMBER	ITEM NUMBER/ PROJECT LOCATION	ITEM DESCRIPTION/ PROJECT LOCATION	DATE LET	UNIT/ QUANTITY	ENGR. EST.	AVERAGE BID	AWARDED BID
=====	627-00003	Thermoplastic Pvmt Mkg (Inlaid)		Sq Foot	=====		
STR096A-050		SH 96 MP 168.99 TO 193.77	12/22/22	32.00	25.00	49.67	54.00
		WEIGHTED AVERAGE FOR THE FOURTH QUARTER		32.00	25.00	37.49	37.84
		WEIGHTED AVERAGE FOR THE YEAR		32.00	25.00	37.49	37.84
=====	627-00005	Epoxy Pvmt Mkg		Gallon	=====		
NHPP0252-448		I-25 TREX NARROWS BRIDGE PREV	06/23/22	27.00	60.00	1700.00	1700.00
		WEIGHTED AVERAGE FOR THE SECOND QUARTER		27.00	60.00	1700.00	1700.00
SHE0242-087		US 24 SAFETY IMPRVMTS, E OF	11/03/22	28.00	98.00	299.62	238.85
		WEIGHTED AVERAGE FOR THE FOURTH QUARTER		28.00	98.00	299.62	238.85
		WEIGHTED AVERAGE FOR THE YEAR		55.00	79.35	1087.33	956.14
=====	627-00006	Mod Epoxy Pvmt Mkg (On-Call)		Gallon	=====		
FSA052A-046		SH52 WCR 37 INTERSECTION IMPR	06/09/22	188.00	140.00	174.55	200.00
		WEIGHTED AVERAGE FOR THE SECOND QUARTER		188.00	140.00	174.55	200.00
		WEIGHTED AVERAGE FOR THE YEAR		188.00	140.00	174.55	200.00
=====	627-00008	Mod Epoxy Pvmt Mkg		Gallon	=====		
NHPP2873-189		US 287 (FEDERAL BLVD) - COLFA	01/06/22	182.00	68.00	246.57	217.26
STR0505-050			01/13/22	513.00	110.00	156.42	200.00
NH0504-910		US50B L-24-B MIN REP AT MP 40	01/13/22	10.00	500.00	761.72	472.22
MTCER400-391		VARIOUS HIGHWAY SEGMENTS ACRO	01/13/22	6,541.00	68.00	93.44	85.75
NHPP0702-383		I-70 EB AUX FRISCO TO SILVERT	01/13/22	1,318.00	135.00	98.55	81.00
STA0252-459			02/03/22	124.00	100.00	447.93	225.00
C0762-055			02/17/22	946.00	120.00	101.40	121.00
STR0141-031			02/17/22	968.00	70.00	115.67	110.00
STR133A-051			02/17/22	1,534.00	80.00	124.67	124.00

COLORADO DEPARTMENT OF TRANSPORTATION
ITEM UNIT COSTS BY PROJECTS -- 2022 COST DATA

11:31 Wednesday, March 8, 2023 546

PROJECT NUMBER	ITEM NUMBER/ PROJECT LOCATION	ITEM DESCRIPTION/ PROJECT LOCATION	DATE LET	UNIT/ QUANTITY	ENGR. EST.	AVERAGE BID	AWARDED BID
=====	627-00008	Mod Epoxy Pvmt Mkg		Gallon =====			
NHPP 0761-238		I-76 DAHLIA TO YORK	03/10/22	324.00	70.00	122.53	150.00
C0761-239							
NHPP0703-472			03/10/22	705.00	74.00	109.92	110.00
ER007A-035			03/15/22	1,434.00	99.45	106.45	106.45
STR160A-034		US160A LA VETA PASS EAST SURF	03/17/22	1,343.00	100.00	118.01	116.02
BRC040-057			03/17/22	41.00	75.00	490.75	425.00
STR092A-031			03/17/22	838.00	140.00	175.00	175.00
WEIGHTED AVERAGE FOR THE FIRST QUARTER				16,821.00	88.29	110.99	110.12
NH0504-911			04/07/22	976.00	71.83	202.25	154.50
CC030-081		ADA RAMP AND CURBS - FT. LUPT	04/14/22	9.00	500.00	633.55	575.00
NHPP0702-413		VAIL PASS AUX PHASE 1 CAP 2	04/18/22	95.00	219.35	219.35	219.35
MTCE2873-204		MTCE FY22 SH287 CONC PANEL RE	05/05/22	4.00	750.00	1555.65	526.29
2670703-479		I-70 BRIDGE OVER HARLAN	05/05/22	55.00	85.00	493.96	645.23
STA0712-019		SH 71: Frieight Improvements	05/12/22	335.00	150.00	119.03	119.03
STA001A-005		SH1 WELLINGTON SOUTH RESURFAC	05/12/22	916.00	95.00	125.25	110.00
NHC540-017		R2 CHAINUP STA @ KENOSHA/HOOS	05/12/22	60.00	92.00	268.33	315.00
CM760-047		COLFAX AND QUAIL	05/12/22	3.00	280.00	1164.40	625.00
NHPP 3851-018		US 385 NORTH OF CHEYENNE WELL	05/26/22	1,205.00	75.00	147.00	149.00
FSA3921-019		SH 392 AND WCR 55 ISLANDS	06/02/22	6.00	350.00	666.67	500.00
NHPP072A-047		SH-72 RESURFACING: I-70 TO IN	06/09/22	199.00	95.00	136.47	136.47
MPR200-278		R2 - VARIOUS LOCATIONS	06/09/22	22,133.00	80.00	89.08	89.75
MTCE R100-380		REGION 1 FY 23/24 PAVEMENT MA	06/30/22	56,785.00	90.50	90.50	90.50
WEIGHTED AVERAGE FOR THE SECOND QUARTER				82,781.00	87.80	94.89	93.15
MT CER300-273		I-70 MM 75-116, OTHER REGION	07/07/22	12,271.00	93.00	91.25	82.00
MTCE 072A-045		SH 72B MP 37.00 TO MP 45.3 NE	07/07/22	852.00	130.00	130.00	130.00
MT CER300-272		REGION 3 ROUNDABOUT STRIPING	07/07/22	240.00	450.00	416.67	450.00
NHPP0702-414		VAIL PASS AUX PHASE 1 CAP 3	07/08/22	339.00	256.80	256.80	256.80
FBR0702-423		VAIL PASS AUX BE F-12-AT PHAS					
FSA052A-057		SH52 BOX CULVERT EXTENSION (M	08/04/22	10.00	500.00	644.83	1280.50
NHPP0063-054		US 6 FROM I70-B TO 33 RD. (MP	08/18/22	61.00	100.00	537.60	225.00
MT CER400-396		REGION 4	08/25/22	12,024.00	80.00	82.83	75.00
C1211-099		SH 121 NORTH SGA SIGNALS	08/25/22	62.00	500.00	312.50	200.00
BR0343-046		US 34 TIMBER BRIDGE REPL. PKG	08/31/22	48.00	165.85	165.85	165.85
FBR0343-047		US 6/US 34 TIMBER BRIDGE REPL					
ER0253-297		WCR 34 BRIDGE OVER I-25 (MM 24	09/14/22	10.00	150.00	243.59	190.00
2670703-497		I-70 GENESEE WILDLIFE XING	09/15/22	392.00	230.00	200.73	198.78
SHE2873-193		US 287 & CO 52 INTERSECTION I	09/15/22	227.00	180.00	213.63	168.00
WEIGHTED AVERAGE FOR THE THIRD QUARTER				26,536.00	97.66	98.76	89.64

PROJECT NUMBER	ITEM NUMBER/ PROJECT LOCATION	ITEM DESCRIPTION/ PROJECT LOCATION	DATE LET	UNIT/ QUANTITY	ENGR. EST.	AVERAGE BID	AWARDED BID
=====	627-00008	Mod Epoxy Pvmt Mkg		Gallon	=====		
MTCE0253-281		MTCE FY23 I-25 CONC PANEL REP	10/06/22	14.00	500.00	233.51	230.00
NHPP0701-253		I-70 EAST OF DEBEQUE	10/27/22	405.00	250.00	154.50	160.00
NHPP0705-088		I-70 AGATE STRUCTURE REHAB	10/27/22	110.00	200.00	302.75	237.00
FSAM240-200		SH21B CO SPRINGS SIGNAL REPLA	10/27/22	40.00	300.00	466.75	440.00
TRG0253-264		I-25 AND SH 119 PARK-N-RIDE	10/27/22	178.00	100.00	477.05	160.00
STA3852-015		US 385 HOLYOKE NORTH	10/27/22	747.00	130.00	120.00	120.00
NHPP0343-048		US 34 (MP 169.3-171.4)	11/01/22	30.00	200.00	296.53	118.00
STU0252-457		I-25:ALAMEDA RIVER PH 2.0	11/03/22	43.00	100.00	245.97	238.00
STR064A-010		SH 64 AND SH 13 AT MEEKER	11/10/22	1,615.00	150.00	125.50	130.00
NHPP0853-126		US85C: PLATTEVILLE NORTH MP (11/10/22	554.00	150.00	159.40	140.00
C5502-097		US550 MP 117.28-126.06	11/17/22	735.00	160.00	179.88	167.00
STRC090-011		US 50B AND SH71/CR18 INTERSEC	11/17/22	86.00	210.00	356.00	420.00
STAM420-001		US 285 AT HWY 9C IMPROVEMENTS	12/01/22	179.00	90.00	212.82	216.44
BR2854-148		INTERSECTION OF US 285 & SH 9					
STM0091-046		ADA RAMP IMPROVEMENTS - FAIRP					
STA0711-021		SH71: REGION LINE NORTH	12/01/22	1,067.00	110.00	149.33	160.00
STR114A-015		SH114 SILLSVILLE SOUTH TO MP3	12/01/22	2,184.00	110.00	152.50	150.00
2670703-487		I-70 BRIDGES OVER WARD ROAD-	12/01/22	452.00	300.00	185.50	140.00
NHPP0701-252		I-70 RIFLE TO SILT SLAB REPLA	12/01/22	366.00	200.00	303.50	275.00
STR318A-001		SH 318 MP 0 - 12.5 MOFFAT COU	12/01/22	1,417.00	120.00	125.50	124.00
NHPP0021-041		SH2 RESURFACING MLK TO 52ND	12/01/22	95.00	250.00	228.47	202.56
STR0641-107		SH 13 MM 104-128.1 IN MOFFAT	12/01/22	2,628.00	150.00	128.83	105.00
NHPP083A-046		SH83 RESURFACING STROH RD TO	12/08/22	225.00	195.00	193.56	206.11
NHPP0063-048		US6 / 20 ROAD INTERSECTION IM	12/15/22	128.00	200.00	237.24	181.50
NHM175-029		CANON CITY, CO	12/15/22	620.00	110.00	132.50	150.00
FSA0853-122		WCR14.5 AND US-85, FORT LUPTO	12/15/22	9.00	500.00	624.09	500.00
NHPP0931-033		SH93:US6 TO 58TH RESURFACING	12/15/22	368.00	65.00	136.96	125.00
NHPP0502-090		SH 50 MP 134.6-136 GUNNISON C	12/22/22	213.00	200.00	240.90	260.61
STR0092-024		SH 9 North of Silverthorne	12/22/22	2,186.00	90.00	127.50	119.00
STA0361-129		US 36: HYGIENE RD AND NELSON	12/22/22	798.00	130.00	174.28	164.25
		WEIGHTED AVERAGE FOR THE FOURTH QUARTER		17,492.00	137.67	161.61	142.72
		WEIGHTED AVERAGE FOR THE YEAR		143,630.00	95.75	110.57	101.31
=====	627-00009	Mod Epoxy (Inlaid)		Gallon	=====		
NHM765-007			03/31/22	86.00	352.00	375.94	342.00
		WEIGHTED AVERAGE FOR THE FIRST QUARTER		86.00	352.00	375.94	342.00
STM1151-038		SH115 MP 27 TO MP 38	04/21/22	1,461.00	120.00	174.63	165.00
		WEIGHTED AVERAGE FOR THE SECOND QUARTER		1,461.00	120.00	174.63	165.00

COLORADO DEPARTMENT OF TRANSPORTATION
 ITEM UNIT COSTS BY PROJECTS -- 2022 COST DATA

11:31 Wednesday, March 8, 2023 548

PROJECT NUMBER	ITEM NUMBER/ PROJECT LOCATION	ITEM DESCRIPTION/ PROJECT LOCATION	DATE LET	UNIT/ QUANTITY	ENGR. EST.	AVERAGE BID	AWARDED BID
=====	627-00009	Mod Epoxy (Inlaid)		Gallon	=====		
2670403-065		US40_FLOYD HILL ROUNDABOUTS	09/15/22	51.00	250.00	349.83	328.00
		WEIGHTED AVERAGE FOR THE THIRD QUARTER		51.00	250.00	349.83	328.00
2670703-487		I-70 BRIDGES OVER WARD ROAD-	12/01/22	45.00	400.00	368.70	250.00
IM025A-050		I25-MP103.9 - INTERSECTION DR	12/01/22	71.00	300.00	295.00	160.00
BR012A-048		CO 12 STRUCTURE P-17-F AT MP	12/22/22	9.00	500.00	1236.62	1150.00
		WEIGHTED AVERAGE FOR THE FOURTH QUARTER		125.00	350.40	368.53	263.68
		WEIGHTED AVERAGE FOR THE YEAR		1,723.00	152.14	195.09	185.82
=====	627-00011	Pvmt Mkg Paint (Waterborne)		Gallon	=====		
NHM765-007			03/31/22	490.00	75.00	174.47	74.67
		WEIGHTED AVERAGE FOR THE FIRST QUARTER		490.00	75.00	174.47	74.67
STM1151-038		SH115 MP 27 TO MP 38	04/21/22	2,900.00	45.00	56.32	58.50
		WEIGHTED AVERAGE FOR THE SECOND QUARTER		2,900.00	45.00	56.32	58.50
		WEIGHTED AVERAGE FOR THE YEAR		3,390.00	49.34	67.19	60.84
=====	627-00013	Pvmt Mkg Paint (High Build)		Gallon	=====		
MTCE R500-219			01/06/22	62,700.00	33.00	34.93	33.70
NHPP2873-189		US 287 (FEDERAL BLVD) - COLFA	01/06/22	884.00	32.00	67.95	65.18
STR0505-050			01/13/22	1,195.00	100.00	72.22	65.00
NHPP0702-383		I-70 EB AUX FRISCO TO SILVERT	01/13/22	344.00	100.00	55.13	43.00
NHPP1601-083			02/03/22	3,015.00	60.00	42.53	42.67
STA0252-459			02/03/22	71.00	104.00	198.57	125.00
C0762-055			02/17/22	1,818.00	60.00	60.17	90.00
STR0141-031			02/17/22	1,643.00	40.00	83.33	79.00

COLORADO DEPARTMENT OF TRANSPORTATION
ITEM UNIT COSTS BY PROJECTS -- 2022 COST DATA

11:31 Wednesday, March 8, 2023 549

PROJECT NUMBER	ITEM NUMBER/ PROJECT LOCATION	ITEM DESCRIPTION/ PROJECT LOCATION	DATE LET	UNIT/ QUANTITY	ENGR. EST.	AVERAGE BID	AWARDED BID
=====	627-00013	Pvmt Mkg Paint (High Build)		Gallon =====			
STR133A-051			02/17/22	772.00	35.00	62.67	54.00
NHPP0063-063			02/24/22	979.00	50.00	138.00	162.00
STA 067A-048		Hwy 67A MP 0.00 TO MP 11.05 I	03/03/22	3,978.00	40.00	46.02	44.00
NHPP 0761-238		I-76 DAHLIA TO YORK	03/10/22	2,510.00	125.00	78.94	80.00
C0761-239							
NHPP0703-472			03/10/22	3,028.00	31.00	44.93	34.00
STR160A-034		US160A LA VETA PASS EAST SURF	03/17/22	2,500.00	60.00	57.63	55.25
STR R500-171		Various locations on SH 141 a	03/17/22	19.00	137.00	121.82	110.00
STR092A-031			03/17/22	782.00	80.00	75.00	75.00
		WEIGHTED AVERAGE FOR THE FIRST QUARTER		86,238.00	40.26	43.61	41.42
NH0504-911			04/07/22	3,904.00	34.46	66.60	83.20
NHPP0702-413		VAIL PASS AUX PHASE 1 CAP 2	04/18/22	133.00	142.76	142.76	142.76
2670703-479		I-70 BRIDGE OVER HARLAN	05/05/22	138.00	40.00	132.19	129.05
STA0712-019		SH 71: Frieight Improvements	05/12/22	762.00	150.00	46.58	46.58
STA001A-005		SH1 WELLINGTON SOUTH RESURFAC	05/12/22	2,000.00	40.00	64.05	72.00
NHC540-017		R2 CHAINUP STA @ KENOSHA/HOOS	05/12/22	40.00	36.00	128.00	159.00
NHPP 3851-018		US 385 NORTH OF CHEYENNE WELL	05/26/22	3,058.00	65.00	87.50	90.00
NHPP072A-047		SH-72 RESURFACING: I-70 TO IN	06/09/22	1,737.00	60.00	77.13	77.13
FSA052A-046		SH52 WCR 37 INTERSECTION IMPR	06/09/22	476.00	80.00	83.35	75.00
		WEIGHTED AVERAGE FOR THE SECOND QUARTER		12,248.00	56.81	76.33	81.02
NHPP0702-414		VAIL PASS AUX PHASE 1 CAP 3	07/08/22	223.00	144.45	144.45	144.45
FBR0702-423		VAIL PASS AUX BE F-12-AT PHAS					
FSA052A-057		SH52 BOX CULVERT EXTENSION (M	08/04/22	5.00	250.00	466.67	780.00
STR0711-022		SH 71 OVER THE ARKANSAS	08/04/22	2.00	200.00	933.33	1300.00
NHPP0063-054		US 6 FROM I70-B TO 33 RD. (MP	08/18/22	186.00	80.00	517.99	900.00
BR0343-046		US 34 TIMBER BRIDGE REPL. PKG	08/31/22	87.00	165.85	165.85	165.85
FBR0343-047		US 6/US 34 TIMBER BRIDGE REPL					
SHE2873-193		US 287 & CO 52 INTERSECTION I	09/15/22	100.00	60.00	83.31	74.00
		WEIGHTED AVERAGE FOR THE THIRD QUARTER		603.00	114.71	231.71	378.01
NHPP0821-114		SH 82 ASPEN/INDEPENDENCE PASS	10/13/22	2,078.00	80.00	50.53	41.60
NHPP0701-253		I-70 EAST OF DEBEQUE	10/27/22	557.00	150.00	88.55	110.00
STA207A-004		Resurfacing SH207A MANZANOLA	10/27/22	1,711.00	80.00	82.00	74.00
NHPP0705-088		I-70 AGATE STRUCTURE REHAB	10/27/22	384.00	76.00	134.13	60.00

COLORADO DEPARTMENT OF TRANSPORTATION
 ITEM UNIT COSTS BY PROJECTS -- 2022 COST DATA

11:31 Wednesday, March 8, 2023 550

PROJECT NUMBER	ITEM NUMBER/ PROJECT LOCATION	ITEM DESCRIPTION/ PROJECT LOCATION	DATE LET	UNIT/ QUANTITY	ENGR. EST.	AVERAGE BID	AWARDED BID
=====	627-00013	Pvmt Mkg Paint (High Build)		Gallon	=====	=====	=====
TRG0253-264		I-25 AND SH 119 PARK-N-RIDE	10/27/22	146.00	120.00	137.56	95.00
STA3852-015		US 385 HOLYOKE NORTH	10/27/22	2,074.00	75.00	75.00	75.00
STU0252-457		I-25:ALAMEDA RIVER PH 2.0	11/03/22	791.00	85.00	74.38	72.00
SHE0242-087		US 24 SAFETY IMPRVMENTS, E OF	11/03/22	50.00	42.00	151.48	119.43
STR064A-010		SH 64 AND SH 13 AT MEEKER	11/10/22	1,172.00	100.00	76.50	87.00
NHPP0853-126		US85C: PLATTEVILLE NORTH MP (11/10/22	2,000.00	80.00	73.20	55.00
C5502-097		US550 MP 117.28-126.06	11/17/22	4,964.00	90.00	40.01	37.30
STRC090-011		US 50B AND SH71/CR18 INTERSEC	11/17/22	100.00	120.00	217.00	230.00
STAM420-001		US 285 AT HWY 9C IMPROVEMENTS	12/01/22	477.00	35.00	94.84	105.13
BR2854-148		INTERSECTION OF US 285 & SH 9					
STM0091-046		ADA RAMP IMPROVEMENTS - FAIRP					
STA0711-021		SH71: REGION LINE NORTH	12/01/22	2,386.00	75.00	73.33	60.00
STR114A-015		SH114 SILLSVILLE SOUTH TO MP3	12/01/22	1,900.00	55.00	106.50	80.00
2670703-487		I-70 BRIDGES OVER WARD ROAD-	12/01/22	453.00	80.00	125.86	79.00
NHPP0701-252		I-70 RIFLE TO SILT SLAB REPLA	12/01/22	309.00	150.00	61.00	55.00
IM025A-050		I25-MP103.9 - INTERSECTION DR	12/01/22	96.00	60.00	147.00	91.00
STR318A-001		SH 318 MP 0 - 12.5 MOFFAT COU	12/01/22	2,158.00	100.00	68.50	48.00
STR109A-019		M-22-AY BRIDGE REHAB ON SH109	12/01/22	37.00	150.00	330.25	104.50
NHPP0021-041		SH2 RESURFACING MLK TO 52ND	12/01/22	596.00	75.00	90.51	67.52
STR0641-107		SH 13 MM 104-128.1 IN MOFFAT	12/01/22	7,154.00	70.00	39.53	32.00
NHPP083A-046		SH83 RESURFACING STROH RD TO	12/08/22	161.00	48.00	104.72	102.43
NHM175-029		CANON CITY, CO	12/15/22	1,033.00	100.00	87.50	90.00
NHPP0931-033		SH93:US6 TO 58TH RESURFACING	12/15/22	1,092.00	80.00	82.09	79.45
NHPP0502-090		SH 50 MP 134.6-136 GUNNISON C	12/22/22	470.00	100.00	153.52	225.78
STR0092-024		SH 9 North of Silverthorne	12/22/22	2,799.00	90.00	50.50	41.00
STA0361-129		US 36: HYGIENE RD AND NELSON	12/22/22	488.00	90.00	95.07	96.85
STA385A-016		SH 385 MP 97.76	12/22/22	68.00	80.00	120.33	183.33
STR096A-050		SH 96 MP 168.99 TO 193.77	12/22/22	2,425.00	51.00	48.33	54.00
		WEIGHTED AVERAGE FOR THE FOURTH QUARTER		40,129.00	80.24	67.56	58.38
		WEIGHTED AVERAGE FOR THE YEAR		139,218.00	53.56	53.16	51.37
=====	627-00014	Pvmt Mkg Paint (Low Temp)		Gallon	=====	=====	=====
ER007A-035			03/15/22	2,000.00	63.75	68.25	68.25
		WEIGHTED AVERAGE FOR THE FIRST QUARTER		2,000.00	63.75	68.25	68.25
2670403-065		US40_FLOYD HILL ROUNDABOUTS	09/15/22	610.00	60.00	92.31	93.00
		WEIGHTED AVERAGE FOR THE THIRD QUARTER		610.00	60.00	92.31	93.00
NHPP0343-048		US 34 (MP 169.3-171.4)	11/01/22	30.00	70.00	242.16	248.00
		WEIGHTED AVERAGE FOR THE FOURTH QUARTER		30.00	70.00	242.16	248.00
		WEIGHTED AVERAGE FOR THE YEAR		2,640.00	62.95	84.68	76.01

COLORADO DEPARTMENT OF TRANSPORTATION
ITEM UNIT COSTS BY PROJECTS -- 2022 COST DATA

11:31 Wednesday, March 8, 2023 551

PROJECT NUMBER	ITEM NUMBER/ PROJECT LOCATION	ITEM DESCRIPTION/ PROJECT LOCATION	DATE LET	UNIT/ QUANTITY	ENGR. EST.	AVERAGE BID	AWARDED BID
=====	627-00029	24 In Pvmt Mkg Tape (Rem)		Lin Foot	=====		
STA0711-021		SH71: REGION LINE NORTH	12/01/22	120.00	28.00	29.00	30.00
		WEIGHTED AVERAGE FOR THE FOURTH QUARTER		120.00	28.00	29.00	30.00
		WEIGHTED AVERAGE FOR THE YEAR		120.00	28.00	29.00	30.00
=====	627-00030	Raised Pvmt Marker (Temp)		Each	=====		
C0762-055			02/17/22	300.00	10.00	8.44	17.00
		WEIGHTED AVERAGE FOR THE FIRST QUARTER		300.00	10.00	8.44	17.00
MTCE 072A-045		SH 72B MP 37.00 TO MP 45.3 NE	07/07/22	3,375.00	2.00	5.00	5.00
		WEIGHTED AVERAGE FOR THE THIRD QUARTER		3,375.00	2.00	5.00	5.00
		WEIGHTED AVERAGE FOR THE YEAR		3,675.00	2.65	5.90	5.98
=====	627-00031	Raised Pvmt Marker		Each	=====		
NHPP0063-063			02/24/22	112.00	200.00	176.73	345.00
		WEIGHTED AVERAGE FOR THE FIRST QUARTER		112.00	200.00	176.73	345.00
NHPP0063-054		US 6 FROM I70-B TO 33 RD. (MP	08/18/22	53.00	250.00	48.49	25.00
		WEIGHTED AVERAGE FOR THE THIRD QUARTER		53.00	250.00	48.49	25.00
		WEIGHTED AVERAGE FOR THE YEAR		165.00	216.06	135.53	242.21
=====	627-00032	Raised Flex Pvmt Marker (Temp)		Each	=====		
NHPP0821-114		SH 82 ASPEN/INDEPENDENCE PASS	10/13/22	4,000.00	2.00	1.57	0.95
		WEIGHTED AVERAGE FOR THE FOURTH QUARTER		4,000.00	2.00	1.57	0.95
		WEIGHTED AVERAGE FOR THE YEAR		4,000.00	2.00	1.57	0.95

COLORADO DEPARTMENT OF TRANSPORTATION
 ITEM UNIT COSTS BY PROJECTS -- 2022 COST DATA

11:31 Wednesday, March 8, 2023 552

PROJECT NUMBER	ITEM NUMBER/ PROJECT LOCATION	ITEM DESCRIPTION/ PROJECT LOCATION	DATE LET	UNIT/ QUANTITY	ENGR. EST.	AVERAGE BID	AWARDED BID
=====	627-00070	Preform Thermoplastic Pvmt Mkg		Sq Foot	=====		
CM760-047		COLFAX AND QUAIL	05/12/22	33.00	17.00	115.25	444.00
		WEIGHTED AVERAGE FOR THE SECOND QUARTER		33.00	17.00	115.25	444.00
		WEIGHTED AVERAGE FOR THE YEAR		33.00	17.00	115.25	444.00
=====	627-01001	Preform Plastic Pvmt Mkg (Ty I)		Sq Foot	=====		
STR0505-050			01/13/22	14,340.00	14.00	18.37	15.00
		WEIGHTED AVERAGE FOR THE FIRST QUARTER		14,340.00	14.00	18.37	15.00
		WEIGHTED AVERAGE FOR THE YEAR		14,340.00	14.00	18.37	15.00
=====	627-01010	Preform Plastic Pvmt Mkg (TY I) (Inlaid)		Sq Foot	=====		
MTCE R500-218			01/06/22	9,178.00	16.50	16.25	14.25
NHPP0702-383		I-70 EB AUX FRISCO TO SILVERT	01/13/22	5,417.00	17.00	14.32	12.00
STA0252-459			02/03/22	5,150.00	17.42	26.98	12.00
C0762-055			02/17/22	3,765.00	18.00	12.96	15.00
NHPP 0761-238		I-76 DAHLIA TO YORK	03/10/22	6,008.00	12.00	15.63	19.00
C0761-239							
NHPP0703-472			03/10/22	10,694.00	12.00	15.43	15.00
		WEIGHTED AVERAGE FOR THE FIRST QUARTER		40,212.00	14.96	16.24	14.64
STM1151-038		SH115 MP 27 TO MP 38	04/21/22	19,116.00	15.00	14.85	16.75
NHPP072A-047		SH-72 RESURFACING: I-70 TO IN	06/09/22	18,221.00	15.00	19.58	19.58
MPR200-278		R2 - VARIOUS LOCATIONS	06/09/22	21,034.00	15.00	14.03	13.25
MTCE R100-380		REGION 1 FY 23/24 PAVEMENT MA	06/30/22	174,271.00	12.25	12.25	12.25
		WEIGHTED AVERAGE FOR THE SECOND QUARTER		232,642.00	12.94	13.66	13.28
MTCE0702-426		I70 FROM MP 155 TO 180 AND MP	07/07/22	48,840.00	14.00	13.83	13.00
ER0253-297		WCR 34 BRIDGE OVER I-25(MM 24	09/14/22	350.00	15.00	59.35	36.00
		WEIGHTED AVERAGE FOR THE THIRD QUARTER		49,190.00	14.01	14.15	13.16

COLORADO DEPARTMENT OF TRANSPORTATION
ITEM UNIT COSTS BY PROJECTS -- 2022 COST DATA

11:31 Wednesday, March 8, 2023 553

PROJECT NUMBER	ITEM NUMBER/ PROJECT LOCATION	ITEM DESCRIPTION/ PROJECT LOCATION	DATE LET	UNIT/ QUANTITY	ENGR. EST.	AVERAGE BID	AWARDED BID
=====	627-01010	Preform Plastic Pvmt Mkg (TY I) (Inlaid)		Sq Foot	=====		
NHPP0701-253		I-70 EAST OF DEBEQUE	10/27/22	4,329.00	20.00	18.85	19.50
STU0252-457		I-25:ALAMEDA RIVER PH 2.0	11/03/22	409.00	20.00	28.38	27.00
2670703-487		I-70 BRIDGES OVER WARD ROAD-	12/01/22	4,100.00	20.00	20.64	19.00
NHPP083A-046		SH83 RESURFACING STROH RD TO	12/08/22	6,003.00	11.00	23.37	23.73
NHPP0931-033		SH93:US6 TO 58TH RESURFACING	12/15/22	10,314.00	18.00	19.84	17.95
		WEIGHTED AVERAGE FOR THE FOURTH QUARTER		25,155.00	17.03	21.52	20.33
		WEIGHTED AVERAGE FOR THE YEAR		347,199.00	13.62	15.45	14.16
=====	627-01011	Preform Plastic Pvmt Mkg (Contr) (Inlaid)		Sq Foot	=====		
NHPP 0761-238 C0761-239		I-76 DAHLIA TO YORK	03/10/22	3,004.00	12.00	16.64	18.50
		WEIGHTED AVERAGE FOR THE FIRST QUARTER		3,004.00	12.00	16.64	18.50
MTCE2873-204 MTCE R100-380		MTCE FY22 SH287 CONC PANEL RE REGION 1 FY 23/24 PAVEMENT MA	05/05/22 06/30/22	67.00 55,784.00	60.00 12.00	43.03 12.25	21.05 12.25
		WEIGHTED AVERAGE FOR THE SECOND QUARTER		55,851.00	12.06	12.32	12.26
MTCE0253-281		MTCE FY23 I-25 CONC PANEL REP	10/06/22	4.00	65.00	35.72	42.00
		WEIGHTED AVERAGE FOR THE FOURTH QUARTER		4.00	65.00	35.72	42.00
		WEIGHTED AVERAGE FOR THE YEAR		58,859.00	12.06	13.63	12.58
=====	627-02001	Preform Plastic Pvmt Mkg (Ty II)		Sq Foot	=====		
BRC040-057			03/17/22	779.00	20.00	34.00	30.00
		WEIGHTED AVERAGE FOR THE FIRST QUARTER		779.00	20.00	34.00	30.00
NHPP0252-448		I-25 TREX NARROWS BRIDGE PREV	06/23/22	1,873.00	25.00	36.32	35.00
		WEIGHTED AVERAGE FOR THE SECOND QUARTER		1,873.00	25.00	36.32	35.00

COLORADO DEPARTMENT OF TRANSPORTATION
ITEM UNIT COSTS BY PROJECTS -- 2022 COST DATA

11:31 Wednesday, March 8, 2023 554

PROJECT NUMBER	ITEM NUMBER/ PROJECT LOCATION	ITEM DESCRIPTION/ PROJECT LOCATION	DATE LET	UNIT/ QUANTITY	ENGR. EST.	AVERAGE BID	AWARDED BID
===== 627-02001		Preform Plastic Pvmt Mkg (Ty II)		Sq Foot	=====		
NHPP0705-088		I-70 AGATE STRUCTURE REHAB	10/27/22	147.00	24.00	31.02	60.00
		WEIGHTED AVERAGE FOR THE FOURTH QUARTER		147.00	24.00	31.02	60.00
		WEIGHTED AVERAGE FOR THE YEAR		2,799.00	23.56	35.39	34.92
===== 627-02010		Preform Plastic Pvmt Mkg (Ty II) (Inlaid)		Sq Foot	=====		
MTCE R500-218			01/06/22	39,155.00	17.50	16.88	15.50
STA0252-459			02/03/22	203.00	20.00	23.12	15.00
C0762-055			02/17/22	9,421.00	19.00	14.05	16.00
NHPP 0761-238		I-76 DAHLIA TO YORK	03/10/22	352.00	22.00	17.29	25.00
C0761-239							
NHM765-007			03/31/22	1,065.00	14.00	26.87	27.36
		WEIGHTED AVERAGE FOR THE FIRST QUARTER		50,196.00	17.75	16.31	15.91
MTCE R100-380		REGION 1 FY 23/24 PAVEMENT MA	06/30/22	14,750.00	12.50	12.50	12.50
		WEIGHTED AVERAGE FOR THE SECOND QUARTER		14,750.00	12.50	12.50	12.50
NHPP0701-252		I-70 RIFLE TO SILT SLAB REPLA	12/01/22	397.00	20.00	40.50	36.00
		WEIGHTED AVERAGE FOR THE FOURTH QUARTER		397.00	20.00	40.50	36.00
		WEIGHTED AVERAGE FOR THE YEAR		65,343.00	16.58	16.04	15.26
===== 627-30110		Pvmt Mkg Paint (XS)		Sq Foot	=====		
NHPP 3851-018		US 385 NORTH OF CHEYENNE WELL	05/26/22	240.00	15.00	22.50	24.00
		WEIGHTED AVERAGE FOR THE SECOND QUARTER		240.00	15.00	22.50	24.00
		WEIGHTED AVERAGE FOR THE YEAR		240.00	15.00	22.50	24.00

COLORADO DEPARTMENT OF TRANSPORTATION
ITEM UNIT COSTS BY PROJECTS -- 2022 COST DATA

11:31 Wednesday, March 8, 2023 555

PROJECT NUMBER	ITEM NUMBER/ PROJECT LOCATION	ITEM DESCRIPTION/ PROJECT LOCATION	DATE LET	UNIT/ QUANTITY	ENGR. EST.	AVERAGE BID	AWARDED BID
=====	627-30205	Thermoplastic Pvmt Mkg (WS)		Sq Foot	=====		
TRG0253-264		I-25 AND SH 119 PARK-N-RIDE	10/27/22	514.00	20.00	33.02	37.00
NHPP0931-033		SH93:US6 TO 58TH RESURFACING	12/15/22	1,521.00	20.00	22.83	22.55
		WEIGHTED AVERAGE FOR THE FOURTH QUARTER		2,035.00	20.00	26.94	26.20
		WEIGHTED AVERAGE FOR THE YEAR		2,035.00	20.00	26.94	26.20
=====	627-30210	Thermoplastic Pvmt Mkg (XS)		Sq Foot	=====		
FSA052A-057		SH52 BOX CULVERT EXTENSION (M	08/04/22	40.00	25.00	29.67	32.50
		WEIGHTED AVERAGE FOR THE THIRD QUARTER		40.00	25.00	29.67	32.50
TRG0253-264		I-25 AND SH 119 PARK-N-RIDE	10/27/22	1,006.00	13.00	21.24	23.00
SHE0242-087		US 24 SAFETY IMPRVMENTS, E OF	11/03/22	24.00	15.00	26.31	14.93
NHPP0931-033		SH93:US6 TO 58TH RESURFACING	12/15/22	5,788.00	15.00	14.68	13.80
		WEIGHTED AVERAGE FOR THE FOURTH QUARTER		6,818.00	14.70	16.39	15.16
		WEIGHTED AVERAGE FOR THE YEAR		6,858.00	14.76	16.45	15.26
=====	627-30310	Plastic Pvmt Mkg (60 Mil) (XS)		Sq Foot	=====		
STRC090-011		US 50B AND SH71/CR18 INTERSEC	11/17/22	479.00	15.00	28.95	29.90
		WEIGHTED AVERAGE FOR THE FOURTH QUARTER		479.00	15.00	28.95	29.90
		WEIGHTED AVERAGE FOR THE YEAR		479.00	15.00	28.95	29.90
=====	627-30324	Preform Plastic Pvmt Mkg (WS) (TY I)		Sq Foot	=====		
ER007A-035			03/15/22	145.00	18.87	20.20	20.20
		WEIGHTED AVERAGE FOR THE FIRST QUARTER		145.00	18.87	20.20	20.20
NHPP0252-448		I-25 TREX NARROWS BRIDGE PREV	06/23/22	488.00	22.00	47.38	47.00
		WEIGHTED AVERAGE FOR THE SECOND QUARTER		488.00	22.00	47.38	47.00
		WEIGHTED AVERAGE FOR THE YEAR		633.00	21.28	45.50	40.86

COLORADO DEPARTMENT OF TRANSPORTATION
ITEM UNIT COSTS BY PROJECTS -- 2022 COST DATA

11:31 Wednesday, March 8, 2023 556

PROJECT NUMBER	ITEM NUMBER/ PROJECT LOCATION	ITEM DESCRIPTION/ PROJECT LOCATION	DATE LET	UNIT/ QUANTITY	ENGR. EST.	AVERAGE BID	AWARDED BID
===== 627-30329							
		Preform Plastic Pvmt Mkg (XS) (TY I)		Sq Foot			
ER007A-035			03/15/22	140.00	12.75	13.65	13.65
		WEIGHTED AVERAGE FOR THE FIRST QUARTER		140.00	12.75	13.65	13.65
NHPP0252-448		I-25 TREX NARROWS BRIDGE PREV	06/23/22	549.00	15.00	26.50	26.00
		WEIGHTED AVERAGE FOR THE SECOND QUARTER		549.00	15.00	26.50	26.00
		WEIGHTED AVERAGE FOR THE YEAR		689.00	14.54	25.73	23.49
===== 627-30405							
		Preform Thermoplastic Pvmt Mkg (WS)		Sq Foot			
MTCE R500-218			01/06/22	4,337.00	18.00	22.13	20.50
NHPP2873-189		US 287 (FEDERAL BLVD) - COLFA	01/06/22	344.00	16.00	25.09	19.55
STR0505-050			01/13/22	1,387.00	30.00	22.32	25.00
MTCER400-391		VARIOUS HIGHWAY SEGMENTS ACRO	01/13/22	26,783.00	12.50	17.11	15.05
NHPP1601-083			02/03/22	490.00	18.00	36.56	32.00
STA 067A-048		Hwy 67A MP 0.00 TO MP 11.05 I	03/03/22	393.10	25.00	26.85	30.00
NHPP0703-472			03/10/22	396.00	16.00	21.69	23.00
STR160A-034		US160A LA VETA PASS EAST SURF	03/17/22	451.00	30.00	23.55	22.10
BRC040-057			03/17/22	28.00	17.00	28.50	25.00
NHM765-007			03/31/22	512.00	28.00	21.85	21.09
		WEIGHTED AVERAGE FOR THE FIRST QUARTER		35,121.10	14.61	18.12	16.84
NH0504-911			04/07/22	1,718.56	13.15	22.10	23.20
2670703-479		I-70 BRIDGE OVER HARLAN	05/05/22	1,193.00	30.00	28.80	32.26
STA0712-019		SH 71: Frieght Improvements	05/12/22	522.00	27.00	15.53	15.53
STA001A-005		SH1 WELLINGTON SOUTH RESURFAC	05/12/22	885.00	22.00	17.75	17.00
CM760-047		COLFAX AND QUAIL	05/12/22	1,123.00	20.00	17.15	15.00
NHPP072A-047		SH-72 RESURFACING: I-70 TO IN	06/09/22	1,759.00	19.00	21.36	21.36
FSA052A-046		SH52 WCR 37 INTERSECTION IMPR	06/09/22	268.00	32.00	23.54	26.00
MPR200-279		FY 23 STENCIL MARKING PROJECT	06/09/22	12,628.03	15.00	17.40	15.25
MTCE R100-380		REGION 1 FY 23/24 PAVEMENT MA	06/30/22	44,250.00	12.00	12.00	12.00
		WEIGHTED AVERAGE FOR THE SECOND QUARTER		64,346.59	13.63	16.17	13.78
2670403-065		US40_FLOYD HILL ROUNDABOUTS	09/15/22	567.00	22.00	58.42	55.00

COLORADO DEPARTMENT OF TRANSPORTATION
ITEM UNIT COSTS BY PROJECTS -- 2022 COST DATA

11:31 Wednesday, March 8, 2023 557

PROJECT NUMBER	ITEM NUMBER/ PROJECT LOCATION	ITEM DESCRIPTION/ PROJECT LOCATION	DATE LET	UNIT/ QUANTITY	ENGR. EST.	AVERAGE BID	AWARDED BID
===== 627-30405		Preform Thermoplastic Pvmt Mkg (WS)		Sq Foot			
SHE2873-193		US 287 & CO 52 INTERSECTION I	09/15/22	1,450.00	25.00	29.75	33.75
		WEIGHTED AVERAGE FOR THE THIRD QUARTER		2,017.00	24.16	34.44	39.72
STA207A-004		Resurfacing SH207A MANZANOLA	10/27/22	100.00	30.00	32.27	32.80
FSAM240-200		SH21B CO SPRINGS SIGNAL REPLA	10/27/22	698.95	15.00	18.73	17.90
STA3852-015		US 385 HOLYOKE NORTH	10/27/22	220.00	30.00	23.00	23.00
STU0252-457		I-25:ALAMEDA RIVER PH 2.0	11/03/22	525.00	30.00	40.13	39.00
NHPP0853-126		US85C: PLATTEVILLE NORTH MP (11/10/22	1,055.00	20.00	24.22	22.00
STRC090-011		US 50B AND SH71/CR18 INTERSEC	11/17/22	566.00	15.00	29.55	30.10
STAM420-001		US 285 AT HWY 9C IMPROVEMENTS	12/01/22	1,246.00	17.00	20.49	22.26
BR2854-148		INTERSECTION OF US 285 & SH 9					
STM0091-046		ADA RAMP IMPROVEMENTS - FAIRP					
2670703-487		I-70 BRIDGES OVER WARD ROAD-	12/01/22	145.00	30.00	31.23	25.00
STR109A-019		M-22-AY BRIDGE REHAB ON SH109	12/01/22	76.00	40.00	32.13	29.26
NHPP0021-041		SH2 RESURFACING MLK TO 52ND	12/01/22	283.00	30.00	32.04	34.37
NHPP083A-046		SH83 RESURFACING STROH RD TO	12/08/22	676.00	23.00	24.24	27.48
NHM175-029		CANON CITY, CO	12/15/22	2,399.10	30.00	25.00	25.00
FSA0853-122		WCRI4.5 AND US-85, FORT LUPTO	12/15/22	31.00	35.00	77.39	35.00
		WEIGHTED AVERAGE FOR THE FOURTH QUARTER		8,021.05	23.82	25.16	25.50
		WEIGHTED AVERAGE FOR THE YEAR		109,505.74	14.88	18.64	16.10
===== 627-30407		Preform Thermoplastic Pvmt Mkg (WS) (Sp)		Sq Foot			
MTCE R500-218			01/06/22	1,534.00	27.00	23.38	24.50
NHPP0702-383		I-70 EB AUX FRISCO TO SILVERT	01/13/22	138.00	30.00	25.15	22.00
NHPP0063-063			02/24/22	1,740.00	20.00	19.88	20.75
STA 067A-048		Hwy 67A MP 0.00 TO MP 11.05 I	03/03/22	138.00	30.00	26.85	30.00
STR092A-031			03/17/22	2,673.00	22.00	19.00	19.00
		WEIGHTED AVERAGE FOR THE FIRST QUARTER		6,223.00	23.03	21.32	21.16
STM1151-038		SH115 MP 27 TO MP 38	04/21/22	1,649.00	24.00	19.43	16.50
		WEIGHTED AVERAGE FOR THE SECOND QUARTER		1,649.00	24.00	19.43	16.50
MTCER300-272		REGION 3 ROUNDABOUT STRIPING	07/07/22	2,300.00	24.00	26.17	22.50

COLORADO DEPARTMENT OF TRANSPORTATION
ITEM UNIT COSTS BY PROJECTS -- 2022 COST DATA

11:31 Wednesday, March 8, 2023 558

PROJECT NUMBER	ITEM NUMBER/ PROJECT LOCATION	ITEM DESCRIPTION/ PROJECT LOCATION	DATE LET	UNIT/ QUANTITY	ENGR. EST.	AVERAGE BID	AWARDED BID
=====	627-30407	Preform Thermoplastic Pvmt Mkg (WS) (Sp)		Sq Foot	=====	=====	=====
NHPP0063-054		US 6 FROM I70-B TO 33 RD. (MP 08/18/22		3,434.00	25.00	25.40	22.00
		WEIGHTED AVERAGE FOR THE THIRD QUARTER		5,734.00	24.60	25.78	22.20
STR064A-010		SH 64 AND SH 13 AT MEEKER	11/10/22	97.00	30.00	36.90	40.00
C5502-097		US550 MP 117.28-126.06	11/17/22	872.00	30.00	37.16	34.60
IM025A-050		I25-MP103.9 - INTERSECTION DR	12/01/22	656.00	22.00	28.00	26.00
NHPP0063-048		US6 / 20 ROAD INTERSECTION IM	12/15/22	691.00	30.00	28.15	28.50
NHPP0502-090		SH 50 MP 134.6-136 GUNNISON C	12/22/22	484.00	20.00	33.89	35.21
STR0092-024		SH 9 North of Silverthorne	12/22/22	129.00	30.00	21.00	20.00
STA0361-129		US 36: HYGIENE RD AND NELSON	12/22/22	1,237.00	20.00	27.86	18.69
		WEIGHTED AVERAGE FOR THE FOURTH QUARTER		4,166.00	24.61	30.30	27.25
		WEIGHTED AVERAGE FOR THE YEAR		17,772.00	24.00	25.28	22.49
=====	627-30408	Pre Thermo Pvmt Mkg (Shield)		Sq Foot	=====	=====	=====
NHPP0703-472			03/10/22	744.00	24.00	23.68	25.00
		WEIGHTED AVERAGE FOR THE FIRST QUARTER		744.00	24.00	23.68	25.00
MTCE R100-380		REGION 1 FY 23/24 PAVEMENT MA	06/30/22	4,790.00	22.50	22.50	22.50
		WEIGHTED AVERAGE FOR THE SECOND QUARTER		4,790.00	22.50	22.50	22.50
		WEIGHTED AVERAGE FOR THE YEAR		5,534.00	22.70	22.95	22.84
=====	627-30410	Preform Thermoplastic Pvmt Mkg (XS)		Sq Foot	=====	=====	=====
MTCE R500-218			01/06/22	11,111.00	13.00	13.38	12.50
NHPP2873-189		US 287 (FEDERAL BLVD) - COLFA	01/06/22	17,017.00	14.00	15.46	13.35
MTCER400-391		VARIOUS HIGHWAY SEGMENTS ACRO	01/13/22	34,174.00	10.50	13.01	11.05
NHPP1601-083			02/03/22	36.00	20.00	94.42	22.00
STA 067A-048		Hwy 67A MP 0.00 TO MP 11.05 I	03/03/22	184.00	30.00	18.24	20.00
NHPP 0761-238		I-76 DAHLIA TO YORK	03/10/22	68.00	44.00	24.45	18.00
C0761-239							
NHPP0703-472			03/10/22	232.00	12.00	16.48	19.00

COLORADO DEPARTMENT OF TRANSPORTATION
ITEM UNIT COSTS BY PROJECTS -- 2022 COST DATA

11:31 Wednesday, March 8, 2023 559

PROJECT NUMBER	ITEM NUMBER/ PROJECT LOCATION	ITEM DESCRIPTION/ PROJECT LOCATION	DATE LET	UNIT/ QUANTITY	ENGR. EST.	AVERAGE BID	AWARDED BID
=====	627-30410	Preform Thermoplastic Pvmt Mkg (XS)		Sq Foot	=====	=====	=====
CR100-362			03/14/22	3,662.00	16.05	16.05	16.05
NHM765-007			03/31/22	1,470.00	20.00	20.87	16.53
		WEIGHTED AVERAGE FOR THE FIRST QUARTER		67,954.00	12.39	14.02	12.32
CC030-081		ADA RAMP AND CURBS - FT. LUPT	04/14/22	6,005.00	15.00	14.60	12.25
2670703-479		I-70 BRIDGE OVER HARLAN	05/05/22	1,352.00	30.00	16.68	19.25
STA001A-005		SH1 WELLINGTON SOUTH RESURFAC	05/12/22	797.00	20.00	15.25	17.00
FSA3921-019		SH 392 AND WCR 55 ISLANDS	06/02/22	55.00	20.00	51.00	25.00
NHPP072A-047		SH-72 RESURFACING: I-70 TO IN	06/09/22	10,734.00	13.00	14.24	14.24
FSA052A-046		SH52 WCR 37 INTERSECTION IMPR	06/09/22	68.00	30.00	20.05	19.00
MTCE R100-380		REGION 1 FY 23/24 PAVEMENT MA	06/30/22	118,301.00	9.75	9.75	9.75
		WEIGHTED AVERAGE FOR THE SECOND QUARTER		137,312.00	10.51	11.09	10.36
NHPP0063-054		US 6 FROM I70-B TO 33 RD. (MP	08/18/22	250.00	25.00	22.80	20.00
C1211-099		SH 121 NORTH SGA SIGNALS	08/25/22	7,762.00	24.00	20.00	18.00
SHE2873-193		US 287 & CO 52 INTERSECTION I	09/15/22	1,930.00	15.00	19.51	20.25
		WEIGHTED AVERAGE FOR THE THIRD QUARTER		9,942.00	22.28	19.84	18.49
STA207A-004		Resurfacing SH207A MANZANOLA	10/27/22	192.00	25.00	21.13	20.40
STA3852-015		US 385 HOLYOKE NORTH	10/27/22	1,154.00	22.00	16.00	16.00
STU0252-457		I-25:ALAMEDA RIVER PH 2.0	11/03/22	3,494.00	30.00	13.63	13.00
NHPP0853-126		US85C: PLATTEVILLE NORTH MP (11/10/22	478.00	15.00	16.99	16.50
STAM420-001		US 285 AT HWY 9C IMPROVEMENTS	12/01/22	140.00	12.72	17.64	22.26
BR2854-148		INTERSECTION OF US 285 & SH 9					
STM0091-046		ADA RAMP IMPROVEMENTS - FAIRP					
STA0711-021		SH71: REGION LINE NORTH	12/01/22	264.00	16.00	36.67	40.00
2670703-487		I-70 BRIDGES OVER WARD ROAD-	12/01/22	116.00	12.00	24.49	22.00
STR109A-019		M-22-AY BRIDGE REHAB ON SH109	12/01/22	120.00	25.00	26.09	27.17
NHPP0021-041		SH2 RESURFACING MLK TO 52ND	12/01/22	5,540.00	18.00	18.01	14.73
NHPP083A-046		SH83 RESURFACING STROH RD TO	12/08/22	7,234.00	11.00	16.56	18.11
FSA0853-122		WCR14.5 AND US-85, FORT LUPTO	12/15/22	48.00	25.00	52.59	21.00
STA0361-129		US 36: HYGIENE RD AND NELSON	12/22/22	120.00	20.00	16.69	13.31
		WEIGHTED AVERAGE FOR THE FOURTH QUARTER		18,900.00	17.75	17.17	16.42
		WEIGHTED AVERAGE FOR THE YEAR		234,108.00	12.14	13.75	11.76

COLORADO DEPARTMENT OF TRANSPORTATION
ITEM UNIT COSTS BY PROJECTS -- 2022 COST DATA

11:31 Wednesday, March 8, 2023 560

PROJECT NUMBER	ITEM NUMBER/ PROJECT LOCATION	ITEM DESCRIPTION/ PROJECT LOCATION	DATE LET	UNIT/ QUANTITY	ENGR. EST.	AVERAGE BID	AWARDED BID
===== 627-30411		Preform Thermoplastic Pvmt Mkg (XS) (Sp)		Sq Foot	=====		
MTCE R500-218			01/06/22	207.00	28.00	17.75	16.00
STR0505-050			01/13/22	1,820.00	20.00	16.32	17.00
NHPP0702-383		I-70 EB AUX FRISCO TO SILVERT	01/13/22	350.00	20.00	17.06	13.00
STR0141-031			02/17/22	850.00	40.00	17.67	16.00
NHPP0063-063			02/24/22	5,352.00	15.00	14.35	15.00
STR092A-031			03/17/22	415.00	17.00	17.00	17.00
		WEIGHTED AVERAGE FOR THE FIRST QUARTER		8,994.00	18.96	15.59	15.54
NH0504-911			04/07/22	1,344.00	12.91	15.60	17.20
MPR200-279		FY 23 STENCIL MARKING PROJECT	06/09/22	16,124.00	12.00	13.37	11.60
		WEIGHTED AVERAGE FOR THE SECOND QUARTER		17,468.00	12.07	13.48	12.03
MTCE R300-272		REGION 3 ROUNDABOUT STRIPING	07/07/22	4,000.00	22.00	21.83	18.00
NHPP0063-054		US 6 FROM I70-B TO 33 RD. (MP	08/18/22	2,953.00	18.00	25.40	22.00
		WEIGHTED AVERAGE FOR THE THIRD QUARTER		6,953.00	20.30	23.01	19.70
FSAM240-200		SH21B CO SPRINGS SIGNAL REPLA	10/27/22	5,233.33	12.00	16.66	13.90
STAM420-001		US 285 AT HWY 9C IMPROVEMENTS	12/01/22	2,050.00	12.00	17.07	19.79
BR2854-148		INTERSECTION OF US 285 & SH 9					
STM0091-046		ADA RAMP IMPROVEMENTS - FAIRP					
IM025A-050		I25-MP103.9 - INTERSECTION DR	12/01/22	912.00	20.00	26.33	23.00
NHPP0063-048		US6 / 20 ROAD INTERSECTION IM	12/15/22	730.00	18.00	21.22	18.75
NHM175-029		CANON CITY, CO	12/15/22	4,765.84	20.00	15.00	15.00
NHPP0502-090		SH 50 MP 134.6-136 GUNNISON C	12/22/22	28.00	17.00	31.75	28.18
STR0092-024		SH 9 North of Silverthorne	12/22/22	130.00	25.00	16.55	15.60
		WEIGHTED AVERAGE FOR THE FOURTH QUARTER		13,849.17	15.73	17.32	16.05
		WEIGHTED AVERAGE FOR THE YEAR		47,264.17	15.66	16.35	15.00
===== 628-00001		Brdg Girder + Deck Unit		Each	=====		
NHPP0702-413		VAIL PASS AUX PHASE 1 CAP 2	04/18/22	2.00	72652.26	72652.26	72652.26
		WEIGHTED AVERAGE FOR THE SECOND QUARTER		2.00	72652.26	72652.26	72652.26
		WEIGHTED AVERAGE FOR THE YEAR		2.00	72652.26	72652.26	72652.26

COLORADO DEPARTMENT OF TRANSPORTATION
ITEM UNIT COSTS BY PROJECTS -- 2022 COST DATA

11:31 Wednesday, March 8, 2023 561

PROJECT NUMBER	ITEM NUMBER/ PROJECT LOCATION	ITEM DESCRIPTION/ PROJECT LOCATION	DATE LET	UNIT/ QUANTITY	ENGR. EST.	AVERAGE BID	AWARDED BID
=====	629-01001	Survey Monument (Ty 1)		Each	=====		
NHPP2873-189		US 287 (FEDERAL BLVD) - COLFA	01/06/22	19.00	1020.00	459.76	215.09
		WEIGHTED AVERAGE FOR THE FIRST QUARTER		19.00	1020.00	459.76	215.09
NHPP0063-054		US 6 FROM I70-B TO 33 RD. (MP	08/18/22	86.00	200.00	156.53	136.00
		WEIGHTED AVERAGE FOR THE THIRD QUARTER		86.00	200.00	156.53	136.00
STU0252-457 BR012A-048		I-25:ALAMEDA RIVER PH 2.0	11/03/22	2.00	1000.00	794.46	1000.00
		CO 12 STRUCTURE P-17-F AT MP	12/22/22	8.00	1000.00	1840.89	1500.00
		WEIGHTED AVERAGE FOR THE FOURTH QUARTER		10.00	1000.00	1555.50	1400.00
		WEIGHTED AVERAGE FOR THE YEAR		115.00	405.04	355.88	258.98
=====	629-01002	Survey Monument (Ty 2)		Each	=====		
NHPP0702-414 FBR0702-423		VAIL PASS AUX PHASE 1 CAP 3	07/08/22	6.00	5350.00	5350.00	5350.00
		VAIL PASS AUX BE F-12-AT PHAS					
		WEIGHTED AVERAGE FOR THE THIRD QUARTER		6.00	5350.00	5350.00	5350.00
		WEIGHTED AVERAGE FOR THE YEAR		6.00	5350.00	5350.00	5350.00
=====	629-01003	Survey Monument (Ty 3)		Each	=====		
STU0252-457		I-25:ALAMEDA RIVER PH 2.0	11/03/22	2.00	1500.00	1361.05	1500.00
		WEIGHTED AVERAGE FOR THE FOURTH QUARTER		2.00	1500.00	1361.05	1500.00
		WEIGHTED AVERAGE FOR THE YEAR		2.00	1500.00	1361.05	1500.00
=====	629-01004	Survey Monument (Ty 4)		Each	=====		
FSAM240-200		SH21B CO SPRINGS SIGNAL REPLA	10/27/22	10.00	400.00	1010.00	440.00
		WEIGHTED AVERAGE FOR THE FOURTH QUARTER		10.00	400.00	1010.00	440.00
		WEIGHTED AVERAGE FOR THE YEAR		10.00	400.00	1010.00	440.00

COLORADO DEPARTMENT OF TRANSPORTATION
 ITEM UNIT COSTS BY PROJECTS -- 2022 COST DATA

11:31 Wednesday, March 8, 2023 562

PROJECT NUMBER	ITEM NUMBER/ PROJECT LOCATION	ITEM DESCRIPTION/ PROJECT LOCATION	DATE LET	UNIT/ QUANTITY	ENGR. EST.	AVERAGE BID	AWARDED BID
=====	629-01005	Survey Monument (Ty 5)		Each	=====	=====	=====
NHPP0063-054		US 6 FROM I70-B TO 33 RD.	08/18/22	6.00	400.00	173.20	150.00
		WEIGHTED AVERAGE FOR THE THIRD QUARTER		6.00	400.00	173.20	150.00
TRG0253-264		I-25 AND SH 119 PARK-N-RIDE	10/27/22	4.00	535.00	1988.81	500.00
STU0252-457		I-25:ALAMEDA RIVER PH 2.0	11/03/22	2.00	1000.00	1108.74	2000.00
		WEIGHTED AVERAGE FOR THE FOURTH QUARTER		6.00	690.00	1849.85	1000.00
		WEIGHTED AVERAGE FOR THE YEAR		12.00	545.00	1447.46	575.00
=====	629-01006	Survey Monument (Ty 6)		Each	=====	=====	=====
NHM765-007			03/31/22	68.00	500.00	239.18	399.00
		WEIGHTED AVERAGE FOR THE FIRST QUARTER		68.00	500.00	239.18	399.00
NHPP0063-054		US 6 FROM I70-B TO 33 RD.	08/18/22	5.00	800.00	323.72	280.00
		WEIGHTED AVERAGE FOR THE THIRD QUARTER		5.00	800.00	323.72	280.00
		WEIGHTED AVERAGE FOR THE YEAR		73.00	520.55	243.13	390.85
=====	629-01031	Survey Monument (Ty 3A)		Each	=====	=====	=====
STA0712-019		SH 71: Frieght Improvements	05/12/22	2.00	1000.00	1358.27	1358.27
NHPP 3851-018		US 385 NORTH OF CHEYENNE WELL	05/26/22	9.00	1000.00	1425.00	2000.00
		WEIGHTED AVERAGE FOR THE SECOND QUARTER		11.00	1000.00	1418.33	1883.32
STA3852-015		US 385 HOLYOKE NORTH	10/27/22	3.00	1200.00	850.00	850.00
STA0711-021		SH71: REGION LINE NORTH	12/01/22	1.00	970.00	1683.33	2000.00
		WEIGHTED AVERAGE FOR THE FOURTH QUARTER		4.00	1142.50	1266.67	1137.50
		WEIGHTED AVERAGE FOR THE YEAR		15.00	1038.00	1383.33	1684.44

COLORADO DEPARTMENT OF TRANSPORTATION
ITEM UNIT COSTS BY PROJECTS -- 2022 COST DATA

11:31 Wednesday, March 8, 2023 563

PROJECT NUMBER	ITEM NUMBER/ PROJECT LOCATION	ITEM DESCRIPTION/ PROJECT LOCATION	DATE LET	UNIT/ QUANTITY	ENGR. EST.	AVERAGE BID	AWARDED BID
=====	629-01050	Monument Box		Each	=====	=====	=====
NHPP0063-063			02/24/22	6.00	1200.00	1436.50	2000.00
		WEIGHTED AVERAGE FOR THE FIRST QUARTER		6.00	1200.00	1436.50	2000.00
		WEIGHTED AVERAGE FOR THE YEAR		6.00	1200.00	1436.50	2000.00
=====	629-01065	Survey Monument (Ty 5S)		Each	=====	=====	=====
NHPP2873-189		US 287 (FEDERAL BLVD) - COLFA	01/06/22	21.00	900.00	443.33	184.36
CR100-362			03/14/22	10.00	891.31	891.31	891.31
		WEIGHTED AVERAGE FOR THE FIRST QUARTER		31.00	897.20	490.99	412.41
C1211-099		SH 121 NORTH SGA SIGNALS	08/25/22	5.00	500.00	825.00	550.00
		WEIGHTED AVERAGE FOR THE THIRD QUARTER		5.00	500.00	825.00	550.00
		WEIGHTED AVERAGE FOR THE YEAR		36.00	842.03	523.10	431.52
=====	629-01110	Locate Monuments		Hour	=====	=====	=====
NHPP2873-189		US 287 (FEDERAL BLVD) - COLFA	01/06/22	8.00	300.00	250.69	245.81
NHPP0063-063			02/24/22	70.00	300.00	177.00	185.00
		WEIGHTED AVERAGE FOR THE FIRST QUARTER		78.00	300.00	190.71	191.24
		WEIGHTED AVERAGE FOR THE YEAR		78.00	300.00	190.71	191.24
=====	629-01210	Adjust Monument Box		Each	=====	=====	=====
NHPP0063-063			02/24/22	25.00	800.00	1058.50	1325.00
		WEIGHTED AVERAGE FOR THE FIRST QUARTER		25.00	800.00	1058.50	1325.00
		WEIGHTED AVERAGE FOR THE YEAR		25.00	800.00	1058.50	1325.00
=====	630-00000	Flagging		Hour	=====	=====	=====
ITS0703-477		ITS EQUIPMENT UPGRADE AT EJMT	01/06/22	1,200.00	35.00	40.00	40.00

PROJECT NUMBER	ITEM NUMBER/ PROJECT LOCATION	ITEM DESCRIPTION/ PROJECT LOCATION	DATE LET	UNIT/ QUANTITY	ENGR. EST.	AVERAGE BID	AWARDED BID
=====	630-00000	Flagging		Hour =====			
MTCE R500-218			01/06/22	1,440.00	30.00	26.40	12.00
NHPP2873-189		US 287 (FEDERAL BLVD) - COLFA	01/06/22	800.00	30.00	46.49	55.26
STR0505-050			01/13/22	2,000.00	28.00	24.33	15.00
NH0504-910		US50B L-24-B MIN REP AT MP 40	01/13/22	600.00	40.00	33.86	33.33
MTCER400-391		VARIOUS HIGHWAY SEGMENTS ACRO	01/13/22	600.00	20.00	27.25	12.00
NHPP0702-383		I-70 EB AUX FRISCO TO SILVERT	01/13/22	3,500.00	32.00	38.58	38.00
MTCER300-262			02/03/22	500.00	31.00	21.67	1.00
NHPP1601-083			02/03/22	7,680.00	30.00	31.96	28.00
STA0252-459			02/03/22	150.00	30.00	40.65	35.90
C0762-055			02/17/22	3,500.00	28.00	39.31	48.00
STR0141-031			02/17/22	3,000.00	35.00	35.53	39.60
STR133A-051			02/17/22	2,500.00	30.00	21.67	20.00
NHPP0063-063			02/24/22	5,000.00	30.00	25.70	25.00
STA 067A-048		Hwy 67A MP 0.00 TO MP 11.05 I	03/03/22	4,000.00	25.00	31.72	29.00
NHPP 0761-238		I-76 DAHLIA TO YORK	03/10/22	2,000.00	30.00	44.05	39.00
C0761-239							
NHPP0703-472			03/10/22	600.00	30.00	39.49	38.00
CR100-362			03/14/22	500.00	40.66	40.66	40.66
STR160A-034		US160A LA VETA PASS EAST SURF	03/17/22	4,500.00	30.00	32.08	33.15
BRC040-057			03/17/22	500.00	30.00	44.75	32.00
STR R500-171		Various locations on SH 141 a	03/17/22	3,300.00	42.25	37.80	35.00
M R100-351		FY22 R1 SIGN STRUCTURE REPLAC	03/17/22	50.00	55.00	47.50	53.00
STR092A-031			03/17/22	7,000.00	30.00	31.00	31.00
NHM765-007			03/31/22	11,000.00	30.00	48.27	39.90
C0703-499		EJMT GROUT BED REPAIR AND PAN	03/31/22	500.00	38.00	46.00	44.00
		WEIGHTED AVERAGE FOR THE FIRST QUARTER		66,420.00	30.73	36.92	32.83
NH0504-911			04/07/22	3,000.00	25.00	34.40	35.80
CC030-081		ADA RAMP AND CURBS - FT. LUPT	04/14/22	500.00	30.00	40.42	40.00
NHPP0702-413		VAIL PASS AUX PHASE 1 CAP 2	04/18/22	8,200.00	42.80	42.80	42.80
STM1151-038		SH115 MP 27 TO MP 38	04/21/22	6,300.00	31.00	42.05	32.00
MTCE2873-204		MTCE FY22 SH287 CONC PANEL RE	05/05/22	800.00	35.00	41.06	33.11
2670703-479		I-70 BRIDGE OVER HARLAN	05/05/22	4,000.00	32.00	32.95	35.00
ER0702-420		PR I-70 GWC MATERIAL FLOWS 20	05/06/22	4,392.00	35.00	36.50	36.00
STA0712-019		SH 71: Frieght Improvements	05/12/22	6,600.00	30.00	45.54	45.54
STA001A-005		SH1 WELLINGTON SOUTH RESURFAC	05/12/22	4,100.00	36.00	47.45	52.00
NHC540-017		R2 CHAINUP STA @ KENOSHA/HOOS	05/12/22	1,300.00	30.00	50.33	56.00
CM760-047		COLFAX AND QUAIL	05/12/22	30.00	31.00	42.40	68.00
NHPP 3851-018		US 385 NORTH OF CHEYENNE WELL	05/26/22	3,750.00	35.00	59.00	42.00
STAR100-358		3 STRUCTURES IN REGION 1 METR	05/26/22	1,500.00	32.00	27.02	27.00
FSA0702-409		I-70 VAIL WILDLIFE FENCE PHAS	05/26/22	2,000.00	41.00	45.00	45.00
ITS 0741-024		VMS SIGN INSTALLATIONS AND VS	06/02/22	480.00	35.00	42.75	36.50
FSA3921-019		SH 392 AND WCR 55 ISLANDS	06/02/22	800.00	35.00	43.07	45.00
NHPP072A-047		SH-72 RESURFACING: I-70 TO IN	06/09/22	1,500.00	30.00	45.50	45.50

COLORADO DEPARTMENT OF TRANSPORTATION
ITEM UNIT COSTS BY PROJECTS -- 2022 COST DATA

11:31 Wednesday, March 8, 2023 565

PROJECT NUMBER	ITEM NUMBER/ PROJECT LOCATION	ITEM DESCRIPTION/ PROJECT LOCATION	DATE LET	UNIT/ QUANTITY	ENGR. EST.	AVERAGE BID	AWARDED BID
===== 630-00000							
		Flagging		Hour			
FSA052A-046		SH52 WCR 37 INTERSECTION IMPR	06/09/22	1,000.00	35.00	48.15	46.00
MPR200-279		FY 23 STENCIL MARKING PROJECT	06/09/22	140.00	25.00	42.33	12.00
MTCE0253-291		I-25 SIGN REPLACEMENT PHASE 2	06/16/22	500.00	30.00	46.33	44.65
NHPP0252-448		I-25 TREX NARROWS BRIDGE PREV	06/23/22	2,000.00	35.00	45.00	43.00
WEIGHTED AVERAGE FOR THE SECOND QUARTER				52,892.00	34.15	41.46	40.82
MTCE 072A-045		SH 72B MP 37.00 TO MP 45.3 NE	07/07/22	550.00	30.00	16.00	16.00
MTCE0702-426		I70 FROM MP 155 TO 180 AND MP	07/07/22	200.00	30.00	53.25	150.00
MTCER300-272		REGION 3 ROUNDABOUT STRIPING	07/07/22	300.00	30.00	65.00	25.00
NHPP0702-414		VAIL PASS AUX PHASE 1 CAP 3	07/08/22	5,196.00	46.14	46.14	46.14
FBR0702-423		VAIL PASS AUX BE F-12-AT PHAS					
FSA052A-057		SH52 BOX CULVERT EXTENSION (M	08/04/22	120.00	50.00	62.22	64.35
STR0711-022		SH 71 OVER THE ARKANSAS	08/04/22	800.00	33.00	35.33	40.00
NHPP0063-054		US 6 FROM I70-B TO 33 RD. (MP	08/18/22	11,520.00	38.00	40.18	41.00
FBR0761-236		I-76 OVER CLR CRK SCOUR MIT	08/25/22	2,000.00	30.00	39.17	35.00
C1211-099		SH 121 NORTH SGA SIGNALS	08/25/22	200.00	40.00	34.50	32.00
ER0502-092		US 50 MP 204 EB MONARCH TRUCK	08/29/22	1,100.00	45.00	40.92	39.08
BR0343-046		US 34 TIMBER BRIDGE REPL. PKG	08/31/22	2,500.00	42.80	42.80	42.80
FBR0343-047		US 6/US 34 TIMBER BRIDGE REPL					
STAR100-374		5 STRUCTURES IN REGION 1	09/01/22	900.00	32.00	55.12	55.12
NHPPR100-266		R1 ESSENTIAL REPAIRS	09/01/22	800.00	25.00	55.06	47.17
ER0253-297		WCR 34 BRIDGE OVER I-25(MM 24	09/14/22	320.00	35.00	41.27	46.00
2670403-065		US40 FLOYD HILL ROUNDABOUTS	09/15/22	6,800.00	25.00	44.45	58.00
2670703-497		I-70 GENESEE WILDLIFE KING	09/15/22	2,000.00	30.00	39.92	37.49
SHE2873-193		US 287 & CO 52 INTERSECTION I	09/15/22	4,000.00	45.00	35.86	33.92
NHPP0701-231		I-70 SALT WASH BRIDGES SCOUR	09/29/22	1,700.00	45.00	17.21	2.00
WEIGHTED AVERAGE FOR THE THIRD QUARTER				41,006.00	36.88	40.18	42.31
NHPP0821-114		SH 82 ASPEN/INDEPENDENCE PASS	10/13/22	900.00	45.00	39.67	54.00
C0831-126		SH83 EL PASO COUNTY TO BAYOU	10/13/22	350.00	65.00	34.00	38.00
NHPP0701-253		I-70 EAST OF DEBEQUE	10/27/22	900.00	45.00	42.95	50.00
STA207A-004		Resurfacing SH207A MANZANOLA	10/27/22	3,200.00	32.00	37.58	39.75
NHPP0705-088		I-70 AGATE STRUCTURE REHAB	10/27/22	1,580.00	35.00	44.68	47.00
FSAM240-200		SH21B CO SPRINGS SIGNAL REPLA	10/27/22	100.00	30.00	44.00	42.00
C5502-111		US 550 MP 81 AND 89 RED MOUNT	10/27/22	800.00	35.00	41.10	39.00
C170A-002		CRITICAL CULVERT CONST. PKG D	10/27/22	720.00	35.00	47.75	50.00
TRG0253-264		I-25 AND SH 119 PARK-N-RIDE	10/27/22	9,600.00	30.00	31.44	25.00
STA3852-015		US 385 HOLYOKE NORTH	10/27/22	4,500.00	40.00	46.00	46.00
NHPP0343-048		US 34 (MP 169.3-171.4)	11/01/22	1,198.00	30.00	44.00	48.00
STU0252-457		I-25:ALAMEDA RIVER PH 2.0	11/03/22	5,500.00	40.00	47.37	44.00

PROJECT NUMBER	ITEM NUMBER/ PROJECT LOCATION	ITEM DESCRIPTION/ PROJECT LOCATION	DATE LET	UNIT/ QUANTITY	ENGR. EST.	AVERAGE BID	AWARDED BID
===== 630-00000							
		Flagging		Hour			
SHE0242-087		US 24 SAFETY IMPRVMENTS, E OF	11/03/22	1,200.00	33.00	41.80	39.41
STR064A-010		SH 64 AND SH 13 AT MEEKER	11/10/22	3,300.00	45.00	41.10	40.00
NHPP0853-126		US85C: PLATTEVILLE NORTH MP (11/10/22	2,250.00	40.00	51.50	52.80
C5502-097		US550 MP 117.28-126.06	11/17/22	11,000.00	45.00	40.71	41.10
MPR200-280		PUEBLO AREA	11/17/22	10.00	24.20	22.50	20.00
STRC090-011		US 50B AND SH71/CR18 INTERSEC	11/17/22	300.00	30.00	38.25	39.50
STAM420-001		US 285 AT HWY 9C IMPROVEMENTS	12/01/22	3,120.00	32.00	44.49	48.15
BR2854-148		INTERSECTION OF US 285 & SH 9					
STM0091-046		ADA RAMP IMPROVEMENTS - FAIRP					
STA0711-021		SH71: REGION LINE NORTH	12/01/22	3,330.00	30.00	41.33	37.00
STR114A-015		SH114 SILLSVILLE SOUTH TO MP3	12/01/22	8,000.00	45.00	38.00	36.00
2670703-487		I-70 BRIDGES OVER WARD ROAD-	12/01/22	4,000.00	40.00	45.18	46.00
NHPP0701-252		I-70 RIFLE TO SILT SLAB REPLA	12/01/22	3,600.00	45.00	41.50	38.00
IM025A-050		I25-MP103.9 - INTERSECTION DR	12/01/22	1,100.00	28.00	38.33	35.00
STR318A-001		SH 318 MP 0 - 12.5 MOFFAT COU	12/01/22	1,930.00	45.00	48.60	47.50
STR109A-019		M-22-AY BRIDGE REHAB ON SH109	12/01/22	500.00	35.00	45.36	39.71
NHPP0021-041		SH2 RESURFACING MLK TO 52ND	12/01/22	500.00	50.00	48.58	49.11
STR0641-107		SH 13 MM 104-128.1 IN MOFFAT	12/01/22	1,750.00	45.00	46.33	42.00
NHPP083A-046		SH83 RESURFACING STROH RD TO	12/08/22	1,000.00	31.00	46.98	47.95
NHPP0063-048		US6 / 20 ROAD INTERSECTION IM	12/15/22	2,000.00	45.00	44.91	40.00
NHM175-029		CANON CITY, CO	12/15/22	2,000.00	30.00	32.50	50.00
FSA0853-122		WCRI4.5 AND US-85, FORT LUPTO	12/15/22	80.00	65.00	54.32	54.00
NHPP0931-033		SH93:US6 TO 58TH RESURFACING	12/15/22	2,300.00	35.00	44.62	40.50
NHPP0502-090		SH 50 MP 134.6-136 GUNNISON C	12/22/22	5,830.00	40.00	45.98	42.79
STR0092-024		SH 9 North of Silverthorne	12/22/22	4,000.00	45.00	43.65	45.30
STA0361-129		US 36: HYGIENE RD AND NELSON	12/22/22	3,500.00	45.00	49.12	40.04
BR012A-048		CO 12 STRUCTURE P-17-F AT MP	12/22/22	1,500.00	35.00	39.27	38.00
STA385A-016		SH 385 MP 97.76	12/22/22	500.00	30.00	43.61	44.44
STR096A-050		SH 96 MP 168.99 TO 193.77	12/22/22	3,400.00	30.00	37.67	36.00
		WEIGHTED AVERAGE FOR THE FOURTH QUARTER		101,348.00	38.99	40.84	40.61
		WEIGHTED AVERAGE FOR THE YEAR		261,666.00	35.58	39.95	38.99
===== 630-00001							
		Pilot Car Operation		Hour			
ITS0703-477		ITS EQUIPMENT UPGRADE AT EJMT	01/06/22	200.00	80.00	75.00	75.00
NHPP1601-083			02/03/22	1,350.00	50.00	67.33	70.00
STR133A-051			02/17/22	200.00	60.00	50.00	40.00
STA 067A-048		Hwy 67A MP 0.00 TO MP 11.05 I	03/03/22	1,000.00	50.00	61.87	40.00
STR092A-031			03/17/22	240.00	65.00	57.00	57.00
C0703-499		EJMT GROUT BED REPAIR AND PAN	03/31/22	550.00	70.00	191.00	207.00
		WEIGHTED AVERAGE FOR THE FIRST QUARTER		3,540.00	56.38	81.14	80.52
STM1151-038		SH115 MP 27 TO MP 38	04/21/22	600.00	52.00	112.34	120.00
		WEIGHTED AVERAGE FOR THE SECOND QUARTER		600.00	52.00	112.34	120.00

COLORADO DEPARTMENT OF TRANSPORTATION
ITEM UNIT COSTS BY PROJECTS -- 2022 COST DATA

11:31 Wednesday, March 8, 2023 567

PROJECT NUMBER	ITEM NUMBER/ PROJECT LOCATION	ITEM DESCRIPTION/ PROJECT LOCATION	DATE LET	UNIT/ QUANTITY	ENGR. EST.	AVERAGE BID	AWARDED BID
=====	630-00001	Pilot Car Operation		Hour	=====	=====	=====
MTCE 072A-045		SH 72B MP 37.00 TO MP 45.3 NE	07/07/22	165.00	75.00	40.00	40.00
		WEIGHTED AVERAGE FOR THE THIRD QUARTER		165.00	75.00	40.00	40.00
NHPP0821-114		SH 82 ASPEN/INDEPENDENCE PASS	10/13/22	300.00	120.00	78.00	119.00
STA3852-015		US 385 HOLYOKE NORTH	10/27/22	800.00	90.00	120.00	120.00
STR064A-010		SH 64 AND SH 13 AT MEEKER	11/10/22	300.00	80.00	77.10	75.00
STR114A-015		SH114 SILLSVILLE SOUTH TO MP3	12/01/22	1,100.00	90.00	100.00	90.00
STR318A-001		SH 318 MP 0 - 12.5 MOFFAT COU	12/01/22	480.00	70.00	95.45	80.90
STR0641-107		SH 13 MM 104-128.1 IN MOFFAT	12/01/22	300.00	100.00	91.50	50.00
		WEIGHTED AVERAGE FOR THE FOURTH QUARTER		3,280.00	89.82	93.52	96.23
		WEIGHTED AVERAGE FOR THE YEAR		7,585.00	70.90	90.85	89.79
=====	630-00003	Uniformed Traf Ctrl		Hour	=====	=====	=====
NHPP2873-189		US 287 (FEDERAL BLVD) - COLFA	01/06/22	750.00	120.00	163.30	155.03
NHPP0702-383		I-70 EB AUX FRISCO TO SILVERT	01/13/22	120.00	150.00	167.81	160.00
STA 067A-048		Hwy 67A MP 0.00 TO MP 11.05 I	03/03/22	1,000.00	100.00	56.48	6.00
BRC040-057			03/17/22	100.00	110.00	129.75	120.00
M R100-351		FY22 R1 SIGN STRUCTURE REPLAC	03/17/22	20.00	120.00	139.00	146.00
		WEIGHTED AVERAGE FOR THE FIRST QUARTER		1,990.00	111.26	116.12	78.59
NHPP0702-413		VAIL PASS AUX PHASE 1 CAP 2	04/18/22	200.00	171.20	171.20	171.20
STM1151-038		SH115 MP 27 TO MP 38	04/21/22	800.00	110.00	121.30	115.00
CM760-047		COLFAX AND QUAIL	05/12/22	25.00	125.00	168.20	163.00
STAR100-358		3 STRUCTURES IN REGION 1 METR	05/26/22	300.00	150.00	142.32	148.00
FSA0702-409		I-70 VAIL WILDLIFE FENCE PHAS	05/26/22	500.00	160.00	145.00	145.00
ITS 0741-024		VMS SIGN INSTALLATIONS AND VS	06/02/22	48.00	110.00	116.00	138.00
MPR200-278		R2 - VARIOUS LOCATIONS	06/09/22	150.00	200.00	166.67	125.00
MPR200-279		FY 23 STENCIL MARKING PROJECT	06/09/22	140.00	100.00	146.67	115.00
NHPP0252-448		I-25 TREX NARROWS BRIDGE PREV	06/23/22	280.00	130.00	144.50	138.00
		WEIGHTED AVERAGE FOR THE SECOND QUARTER		2,443.00	137.55	134.51	133.99

COLORADO DEPARTMENT OF TRANSPORTATION
ITEM UNIT COSTS BY PROJECTS -- 2022 COST DATA

11:31 Wednesday, March 8, 2023 568

PROJECT NUMBER	ITEM NUMBER/ PROJECT LOCATION	ITEM DESCRIPTION/ PROJECT LOCATION	DATE LET	UNIT/ QUANTITY	ENGR. EST.	AVERAGE BID	AWARDED BID
===== 630-00003		Uniformed Traf Ctrl		Hour	=====		
NHPP0702-414		VAIL PASS AUX PHASE 1 CAP 3	07/08/22	200.00	164.79	164.79	164.79
FBR0702-423		VAIL PASS AUX BE F-12-AT PHAS					
C1211-099		SH 121 NORTH SGA SIGNALS	08/25/22	60.00	150.00	148.00	146.00
STAR100-374		5 STRUCTURES IN REGION 1	09/01/22	560.00	150.00	185.50	185.50
NHPPR100-266		R1 ESSENTIAL REPAIRS	09/01/22	50.00	120.00	138.17	132.50
2670703-497		I-70_GENESEE WILDLIFE XING	09/15/22	100.00	120.00	180.88	198.78
		WEIGHTED AVERAGE FOR THE THIRD QUARTER		970.00	148.41	174.53	177.42
FSAM240-200		SH21B CO SPRINGS SIGNAL REPLA	10/27/22	144.00	120.00	109.50	110.00
STU0252-457		I-25:ALAMEDA RIVER PH 2.0	11/03/22	500.00	100.00	183.87	154.00
SHE0242-087		US 24 SAFETY IMPRVMENTS, E OF	11/03/22	120.00	120.00	171.33	208.99
STRC090-011		US 50B AND SH71/CR18 INTERSEC	11/17/22	100.00	150.00	171.50	150.00
STAM420-001		US 285 AT HWY 9C IMPROVEMENTS	12/01/22	160.00	120.00	145.39	228.07
BR2854-148		INTERSECTION OF US 285 & SH 9					
STM0091-046		ADA RAMP IMPROVEMENTS - FAIRP					
2670703-487		I-70 BRIDGES OVER WARD ROAD-	12/01/22	250.00	150.00	147.28	160.00
NHPP0021-041		SH2 RESURFACING MLK TO 52ND	12/01/22	400.00	175.00	201.24	245.53
		WEIGHTED AVERAGE FOR THE FOURTH QUARTER		1,674.00	133.44	168.79	183.76
		WEIGHTED AVERAGE FOR THE YEAR		7,077.00	130.67	141.10	136.14
===== 630-00004		Traf Ctrl Vehicle		Each	=====		
NHPP2873-189		US 287 (FEDERAL BLVD) - COLFA	01/06/22	1.00	6000.00	17413.04	9301.64
		WEIGHTED AVERAGE FOR THE FIRST QUARTER		1.00	6000.00	17413.04	9301.64
NHPP0252-448		I-25 TREX NARROWS BRIDGE PREV	06/23/22	1.00	5000.00	8501.25	8120.00
		WEIGHTED AVERAGE FOR THE SECOND QUARTER		1.00	5000.00	8501.25	8120.00
STU0252-457		I-25:ALAMEDA RIVER PH 2.0	11/03/22	2.00	2500.00	23223.33	13000.00

COLORADO DEPARTMENT OF TRANSPORTATION
ITEM UNIT COSTS BY PROJECTS -- 2022 COST DATA

11:31 Wednesday, March 8, 2023 569

PROJECT NUMBER	ITEM NUMBER/ PROJECT LOCATION	ITEM DESCRIPTION/ PROJECT LOCATION	DATE LET	UNIT/ QUANTITY	ENGR. EST.	AVERAGE BID	AWARDED BID
===== 630-00004 Traf Ctrl Vehicle Each =====							
2670703-487		I-70 BRIDGES OVER WARD ROAD-	12/01/22	2.00	10000.00	12844.00	13800.00
NHPP0021-041		SH2 RESURFACING MLK TO 52ND	12/01/22	1.00	9500.00	27850.51	24552.66
		WEIGHTED AVERAGE FOR THE FOURTH QUARTER		5.00	6900.00	18959.10	15630.53
		WEIGHTED AVERAGE FOR THE YEAR		7.00	6500.00	17244.26	13653.47
===== 630-00006 Uniformed Traf Ctrl (Vehicle) Hour =====							
BRC040-057			03/17/22	100.00	30.00	100.00	105.00
M R100-351		FY22 R1 SIGN STRUCTURE REPLAC	03/17/22	20.00	30.00	44.00	35.00
C0703-499		EJMT GROUT BED REPAIR AND PAN	03/31/22	200.00	125.00	236.50	250.00
		WEIGHTED AVERAGE FOR THE FIRST QUARTER		320.00	89.38	162.33	191.25
2670703-479		I-70 BRIDGE OVER HARLAN	05/05/22	600.00	70.00	123.20	170.00
ITS 0741-024		VMS SIGN INSTALLATIONS AND VS	06/02/22	48.00	40.00	88.50	83.00
NHPP072A-047		SH-72 RESURFACING: I-70 TO IN	06/09/22	1,000.00	50.00	149.68	149.68
		WEIGHTED AVERAGE FOR THE SECOND QUARTER		1,648.00	56.99	128.13	155.14
C1211-099		SH 121 NORTH SGA SIGNALS	08/25/22	60.00	35.00	99.50	49.00
NHPPR100-266		R1 ESSENTIAL REPAIRS	09/01/22	50.00	35.00	60.50	79.50
		WEIGHTED AVERAGE FOR THE THIRD QUARTER		110.00	35.00	77.83	62.86
2670703-487		I-70 BRIDGES OVER WARD ROAD-	12/01/22	250.00	220.00	38.90	29.00
NHPP0931-033		SH93:US6 TO 58TH RESURFACING	12/15/22	800.00	100.00	128.64	25.65
		WEIGHTED AVERAGE FOR THE FOURTH QUARTER		1,050.00	128.57	103.43	26.45
		WEIGHTED AVERAGE FOR THE YEAR		3,128.00	83.56	118.89	112.39
===== 630-00007 Traf Ctrl Inspection Day =====							
ITS0703-477		ITS EQUIPMENT UPGRADE AT EJMT	01/06/22	30.00	250.00	395.00	395.00

PROJECT NUMBER	ITEM NUMBER/ PROJECT LOCATION	ITEM DESCRIPTION/ PROJECT LOCATION	DATE LET	UNIT/ QUANTITY	ENGR. EST.	AVERAGE BID	AWARDED BID
=====	630-00007	Traf Ctrl Inspection		Day =====			
MTCE R500-218			01/06/22	11.00	400.00	180.60	150.00
NHPP2873-189		US 287 (FEDERAL BLVD) - COLFA	01/06/22	30.00	300.00	255.40	186.03
STR0505-050			01/13/22	22.00	350.00	277.67	250.00
NH0504-910		US50B L-24-B MIN REP AT MP 40	01/13/22	135.00	300.00	402.35	277.78
NHPP0702-383		I-70 EB AUX FRISCO TO SILVERT	01/13/22	189.00	400.00	598.47	845.00
NHPP1601-083			02/03/22	81.00	250.00	273.98	240.00
STA0252-459			02/03/22	74.00	300.00	359.38	373.00
C0762-055			02/17/22	55.00	250.00	322.94	750.00
STR0141-031			02/17/22	34.00	500.00	391.67	450.00
STR133A-051			02/17/22	10.00	425.00	278.33	375.00
NHPP0063-063			02/24/22	46.00	250.00	332.00	400.00
STA 067A-048		Hwy 67A MP 0.00 TO MP 11.05 I	03/03/22	36.00	200.00	254.12	300.00
NHPP 0761-238		I-76 DAHLIA TO YORK	03/10/22	206.00	400.00	299.78	170.00
C0761-239							
NHPP0703-472			03/10/22	28.00	300.00	317.80	275.00
CR100-362			03/14/22	60.00	187.25	187.25	187.25
STR160A-034		US160A LA VETA PASS EAST SURF	03/17/22	70.00	300.00	227.87	165.74
BRC040-057			03/17/22	50.00	300.00	223.50	200.00
STR R500-171		Various locations on SH 141 a	03/17/22	42.00	1012.00	907.56	700.00
M R100-351		FY22 R1 SIGN STRUCTURE REPLAC	03/17/22	16.00	100.00	249.50	313.00
STR092A-031			03/17/22	42.00	300.00	218.00	218.00
MP0503-098			03/24/22	10.00	200.00	313.00	308.00
NHM765-007			03/31/22	150.00	250.00	924.10	627.00
C0703-499		EJMT GROUT BED REPAIR AND PAN	03/31/22	80.00	400.00	435.50	500.00
		WEIGHTED AVERAGE FOR THE FIRST QUARTER		1,507.00	336.49	421.25	407.82
NH0504-911			04/07/22	150.00	250.00	99.70	119.40
CC030-081		ADA RAMP AND CURBS - FT. LUPT	04/14/22	55.00	275.00	380.91	500.00
NHPP0702-413		VAIL PASS AUX PHASE 1 CAP 2	04/18/22	28.00	481.50	481.50	481.50
STM1151-038		SH115 MP 27 TO MP 38	04/21/22	230.00	250.00	162.83	150.00
MTCE2873-204		MTCE FY22 SH287 CONC PANEL RE	05/05/22	8.00	350.00	224.37	123.74
2670703-479		I-70 BRIDGE OVER HARLAN	05/05/22	256.00	265.00	327.09	375.00
ER0702-420		PR I-70 GWC MATERIAL FLOWS 20	05/06/22	53.00	300.00	430.00	400.00
STA0712-019		SH 71: Frieight Improvements	05/12/22	50.00	350.00	465.77	465.77
STA001A-005		SH1 WELLINGTON SOUTH RESURFAC	05/12/22	30.00	300.00	208.00	230.00
NHC540-017		R2 CHAINUP STA @ KENOSHA/HOOS	05/12/22	90.00	265.00	586.67	650.00
CM760-047		COLFAX AND QUAIL	05/12/22	14.00	240.00	194.40	88.00
NHPP 3851-018		US 385 NORTH OF CHEYENNE WELL	05/26/22	38.00	200.00	650.00	350.00
STAR100-358		3 STRUCTURES IN REGION 1 METR	05/26/22	34.00	350.00	193.66	265.00
C0852-120		Rehabilitation of Culvert by	05/26/22	21.00	300.00	300.00	300.00
FSA0702-409		I-70 VAIL WILDLIFE FENCE PHAS	05/26/22	60.00	440.00	400.00	400.00
ITS 0741-024		VMS SIGN INSTALLATIONS AND VS	06/02/22	5.00	200.00	453.50	650.00
FSA3921-019		SH 392 AND WCR 55 ISLANDS	06/02/22	6.00	300.00	153.83	162.50
NHPP072A-047		SH-72 RESURFACING: I-70 TO IN	06/09/22	54.00	230.00	179.62	179.62

COLORADO DEPARTMENT OF TRANSPORTATION
ITEM UNIT COSTS BY PROJECTS -- 2022 COST DATA

11:31 Wednesday, March 8, 2023 571

PROJECT NUMBER	ITEM NUMBER/ PROJECT LOCATION	ITEM DESCRIPTION/ PROJECT LOCATION	DATE LET	UNIT/ QUANTITY	ENGR. EST.	AVERAGE BID	AWARDED BID
=====	630-00007	Traf Ctrl Inspection		Day =====			
FSA052A-046		SH52 WCR 37 INTERSECTION IMPR	06/09/22	33.00	500.00	294.45	200.00
MTCE0253-291		I-25 SIGN REPLACEMENT PHASE 2	06/16/22	20.00	250.00	315.96	318.92
NHPP0252-448		I-25 TREX NARROWS BRIDGE PREV	06/23/22	53.00	250.00	314.00	300.00
		WEIGHTED AVERAGE FOR THE SECOND QUARTER		1,288.00	284.18	287.67	308.16
MTCE 072A-045		SH 72B MP 37.00 TO MP 45.3 NE	07/07/22	2.00	350.00	120.00	120.00
NHPP0702-414		VAIL PASS AUX PHASE 1 CAP 3	07/08/22	180.00	549.30	549.30	549.30
FBR0702-423		VAIL PASS AUX BE F-12-AT PHAS					
FSA052A-057		SH52 BOX CULVERT EXTENSION (M	08/04/22	20.00	250.00	317.67	325.00
STR0711-022		SH 71 OVER THE ARKANSAS	08/04/22	16.00	300.00	186.67	260.00
NHPP0063-054		US 6 FROM I70-B TO 33 RD. (MP	08/18/22	125.00	500.00	407.98	245.00
FBR0761-236		I-76 OVER CLR CRK SCOUR MIT	08/25/22	30.00	250.00	213.33	300.00
C1211-099		SH 121 NORTH SGA SIGNALS	08/25/22	30.00	400.00	165.50	81.00
ER0502-092		US 50 MP 204 EB MONARCH TRUCK	08/29/22	10.00	350.00	450.52	432.11
BR0343-046		US 34 TIMBER BRIDGE REPL. PKG	08/31/22	55.00	139.10	267.50	267.50
FBR0343-047		US 6/US 34 TIMBER BRIDGE REPL					
STAR100-374		5 STRUCTURES IN REGION 1	09/01/22	46.00	275.00	556.50	556.50
NHPPR100-266		R1 ESSENTIAL REPAIRS	09/01/22	65.00	250.00	523.33	848.00
PAN0761-245		ALONG I-76 & RAMPS MILEPOST 9	09/01/22	15.00	400.00	410.00	275.00
ER0253-297		WCR 34 BRIDGE OVER I-25(MM 24	09/14/22	8.00	400.00	249.69	180.00
2670403-065		US40 FLOYD HILL ROUNDABOUTS	09/15/22	90.00	300.00	373.67	600.00
2670703-497		I-70_GENESEE WILDLIFE XING	09/15/22	300.00	300.00	257.34	255.57
SHE2873-193		US 287 & CO 52 INTERSECTION I	09/15/22	77.00	280.00	291.83	212.00
NHPP0701-231		I-70 SALT WASH BRIDGES SCOUR	09/29/22	32.00	450.00	589.09	800.00
		WEIGHTED AVERAGE FOR THE THIRD QUARTER		1,101.00	357.48	314.11	390.32
MTCE0253-281		MTCE FY23 I-25 CONC PANEL REP	10/06/22	10.00	250.00	261.40	420.00
NHPP0821-114		SH 82 ASPEN/INDEPENDENCE PASS	10/13/22	10.00	400.00	488.67	486.00
C0831-126		SH83 EL PASO COUNTY TO BAYOU	10/13/22	18.00	200.00	275.00	400.00
NHPP0701-253		I-70 EAST OF DEBEQUE	10/27/22	35.00	400.00	397.00	410.00
STA207A-004		Resurfacing SH207A MANZANOLA	10/27/22	65.00	330.00	235.63	235.90
NHPP0705-088		I-70 AGATE STRUCTURE REHAB	10/27/22	208.00	300.00	577.25	650.00
FSAM240-200		SH21B CO SPRINGS SIGNAL REPLA	10/27/22	71.00	200.00	221.50	170.00
C5502-111		US 550 MP 81 AND 89 RED MOUNT	10/27/22	10.00	700.00	442.00	410.00
C170A-002		CRITICAL CULVERT CONST. PKG D	10/27/22	15.00	325.00	322.45	227.78
TRG0253-264		I-25 AND SH 119 PARK-N-RIDE	10/27/22	110.00	250.00	771.88	1200.00
STA3852-015		US 385 HOLYOKE NORTH	10/27/22	60.00	300.00	415.00	415.00
NHPP0343-048		US 34 (MP 169.3-171.4)	11/01/22	50.00	250.00	373.28	295.00
STU0252-457		I-25-ALAMEDA RIVER PH 2.0	11/03/22	257.00	400.00	462.45	408.00
SHE0242-087		US 24 SAFETY IMPRVMENTS, E OF	11/03/22	24.00	230.00	382.25	256.76

PROJECT NUMBER	ITEM NUMBER/ PROJECT LOCATION	ITEM DESCRIPTION/ PROJECT LOCATION	DATE LET	UNIT/ QUANTITY	ENGR. EST.	AVERAGE BID	AWARDED BID
=====	630-00007	Traf Ctrl Inspection		Day =====			
STR064A-010		SH 64 AND SH 13 AT MEEKER	11/10/22	45.00	400.00	465.50	535.00
NHPP0853-126		US85C: PLATTEVILLE NORTH MP (11/10/22	28.00	350.00	237.30	247.50
C5502-097		US550 MP 117.28-126.06	11/17/22	80.00	350.00	418.04	378.00
MPR200-280		PUEBLO AREA	11/17/22	4.00	75.00	75.00	100.00
STR090-011		US 50B AND SH71/CR18 INTERSEC	11/17/22	70.00	250.00	395.00	390.00
STAM420-001		US 285 AT HWY 9C IMPROVEMENTS	12/01/22	390.00	250.38	488.61	570.17
BR2854-148		INTERSECTION OF US 285 & SH 9					
STM0091-046		ADA RAMP IMPROVEMENTS - FAIRP					
STA0711-021		SH71: REGION LINE NORTH	12/01/22	48.00	240.00	571.67	330.00
STR114A-015		SH114 SILLSVILLE SOUTH TO MP3	12/01/22	50.00	500.00	660.00	320.00
2670703-487		I-70 BRIDGES OVER WARD ROAD-	12/01/22	248.00	400.00	397.24	430.00
NHPP0701-252		I-70 RIFLE TO SILT SLAB REPLA	12/01/22	51.00	400.00	445.00	350.00
IM025A-050		I25-MP103.9 - INTERSECTION DR	12/01/22	118.00	260.00	118.33	160.00
STR318A-001		SH 318 MP 0 - 12.5 MOFFAT COU	12/01/22	40.00	350.00	502.00	534.00
STR109A-019		M-22-AY BRIDGE REHAB ON SH109	12/01/22	116.00	800.00	525.46	545.92
NHPP0021-041		SH2 RESURFACING MLK TO 52ND	12/01/22	20.00	300.00	577.68	982.11
STR0641-107		SH 13 MM 104-128.1 IN MOFFAT	12/01/22	27.00	400.00	304.50	250.00
NHPP083A-046		SH83 RESURFACING STROH RD TO	12/08/22	40.00	250.00	229.71	233.42
NHPP0063-048		US6 / 20 ROAD INTERSECTION IM	12/15/22	39.00	400.00	468.03	275.00
NHM175-029		CANON CITY, CO	12/15/22	22.00	350.00	537.50	1000.00
FSA0853-122		WCR14.5 AND US-85, FORT LUPTO	12/15/22	16.00	250.00	237.64	231.00
NHPP0931-033		SH93:US6 TO 58TH RESURFACING	12/15/22	55.00	250.00	287.46	256.00
NHPP0502-090		SH 50 MP 134.6-136 GUNNISON C	12/22/22	56.00	300.00	475.21	533.50
STR0092-024		SH 9 North of Silverthorne	12/22/22	52.00	400.00	467.50	485.00
STA0361-129		US 36: HYGIENE RD AND NELSON	12/22/22	30.00	350.00	272.10	400.36
BR012A-048		CO 12 STRUCTURE P-17-F AT MP	12/22/22	180.00	350.00	428.34	350.00
STA385A-016		SH 385 MP 97.76	12/22/22	60.00	300.00	446.61	444.44
STR096A-050		SH 96 MP 168.99 TO 193.77	12/22/22	46.00	250.00	363.33	400.00
		WEIGHTED AVERAGE FOR THE FOURTH QUARTER		2,874.00	338.78	433.12	427.82
		WEIGHTED AVERAGE FOR THE YEAR		6,770.00	330.92	388.64	397.28
=====	630-00012	Traf Ctrl Mgmt		Day =====			
ITS0703-477		ITS EQUIPMENT UPGRADE AT EJMT	01/06/22	241.00	900.00	2285.00	2285.00
MTCE R500-218			01/06/22	36.00	900.00	1209.00	450.00
NHPP2873-189		US 287 (FEDERAL BLVD) - COLFA	01/06/22	170.00	900.00	1475.64	1121.23
STR0505-050			01/13/22	40.00	1100.00	983.33	1000.00
NH0504-910		US50B L-24-B MIN REP AT MP 40	01/13/22	45.00	1100.00	984.49	888.89
MTCER400-391		VARIOUS HIGHWAY SEGMENTS ACRO	01/13/22	65.00	250.00	656.25	250.00
NHPP0702-383		I-70 EB AUX FRISCO TO SILVERT	01/13/22	237.00	1300.00	1642.26	1580.00
MTCER300-262			02/03/22	150.00	1200.00	1500.00	1000.00
NHPP1601-083			02/03/22	180.00	900.00	1280.98	1500.00
STA0252-459			02/03/22	185.00	900.00	1879.00	1415.00
C0762-055			02/17/22	135.00	1500.00	1894.27	2400.00

PROJECT NUMBER	ITEM NUMBER/ PROJECT LOCATION	ITEM DESCRIPTION/ PROJECT LOCATION	DATE LET	UNIT/ QUANTITY	ENGR. EST.	AVERAGE BID	AWARDED BID
===== 630-00012 Traf Ctrl Mgmt Day =====							
STR0141-031			02/17/22	68.00	1200.00	1416.67	1500.00
STR133A-051			02/17/22	25.00	1200.00	1343.33	1000.00
NHPP0063-063			02/24/22	115.00	1000.00	1277.50	1395.00
STA 067A-048		Hwy 67A MP 0.00 TO MP 11.05 I	03/03/22	75.00	850.00	1214.33	1000.00
NHPP 0761-238		I-76 DAHLIA TO YORK	03/10/22	516.00	1200.00	1569.89	1600.00
C0761-239							
NHPP0703-472			03/10/22	80.00	900.00	1563.64	1750.00
CR100-362			03/14/22	240.00	1096.75	1096.75	1096.75
STR160A-034		US160A LA VETA PASS EAST SURF	03/17/22	100.00	1000.00	997.22	994.43
STR R500-171		Various locations on SH 141 a	03/17/22	90.00	1012.00	1374.23	2100.00
M R100-351		FY22 R1 SIGN STRUCTURE REPLAC	03/17/22	60.00	1600.00	1361.00	1462.00
STR092A-031			03/17/22	89.00	1000.00	1305.00	1305.00
MP0503-098			03/24/22	25.00	1200.00	1350.00	1045.00
NHM765-007			03/31/22	450.00	1500.00	1990.37	1710.00
C0703-499		EJMT GROUT BED REPAIR AND PAN	03/31/22	70.00	1200.00	2289.50	2315.00
WEIGHTED AVERAGE FOR THE FIRST QUARTER				3,487.00	1130.20	1569.17	1512.82
NH0504-911			04/07/22	180.00	1000.00	1245.00	1490.00
CC030-081		ADA RAMP AND CURBS - FT. LUPT	04/14/22	110.00	1100.00	1604.36	2000.00
NHPP0702-413		VAIL PASS AUX PHASE 1 CAP 2	04/18/22	168.00	2354.00	2354.00	2354.00
STM1151-038		SH115 MP 27 TO MP 38	04/21/22	310.00	1000.00	1379.81	1250.00
MTCE2873-204		MTCE FY22 SH287 CONC PANEL RE	05/05/22	20.00	1300.00	1533.68	1567.35
2670703-479		I-70 BRIDGE OVER HARLAN	05/05/22	437.00	950.00	1173.61	1025.00
ER0702-420		PR I-70 GWC MATERIAL FLOWS 20	05/06/22	122.00	900.00	2250.00	2300.00
STA0712-019		SH 71: Frieight Improvements	05/12/22	180.00	1500.00	2018.35	2018.35
STA001A-005		SH1 WELLINGTON SOUTH RESURFAC	05/12/22	72.00	1000.00	1294.75	1800.00
CM760-047		COLFAX AND QUAIL	05/12/22	35.00	900.00	1364.80	1161.00
NHPP 3851-018		US 385 NORTH OF CHEYENNE WELL	05/26/22	75.00	800.00	2550.00	1100.00
STAR100-358		3 STRUCTURES IN REGION 1 METR	05/26/22	86.00	1500.00	943.37	1113.00
C0852-120		Rehabilitation of Culvert by	05/26/22	32.00	1500.00	1650.00	1650.00
FSA0702-409		I-70 VAIL WILDLIFE FENCE PHAS	05/26/22	120.00	1500.00	1600.00	1600.00
ITS 0741-024		VMS SIGN INSTALLATIONS AND VS	06/02/22	115.00	800.00	1558.00	1540.00
FSA3921-019		SH 392 AND WCR 55 ISLANDS	06/02/22	20.00	950.00	851.33	818.00
NHPP072A-047		SH-72 RESURFACING: I-70 TO IN	06/09/22	105.00	1000.00	1227.38	1227.38
FSA052A-046		SH52 WCR 37 INTERSECTION IMPR	06/09/22	60.00	2000.00	1352.40	892.00
MPR200-278		R2 - VARIOUS LOCATIONS	06/09/22	15.00	1000.00	516.67	225.00
MPR200-279		FY 23 STENCIL MARKING PROJECT	06/09/22	37.00	200.00	600.00	150.00
MTCE0253-291		I-25 SIGN REPLACEMENT PHASE 2	06/16/22	50.00	1000.00	1337.45	1236.90
NHPP0252-448		I-25 TREX NARROWS BRIDGE PREV	06/23/22	118.00	1000.00	1266.75	1210.00
WEIGHTED AVERAGE FOR THE SECOND QUARTER				2,467.00	1165.11	1362.77	1449.94
MTCE 072A-045		SH 72B MP 37.00 TO MP 45.3 NE	07/07/22	8.00	1000.00	575.00	575.00

PROJECT NUMBER	ITEM NUMBER/ PROJECT LOCATION	ITEM DESCRIPTION/ PROJECT LOCATION	DATE LET	UNIT/ QUANTITY	ENGR. EST.	AVERAGE BID	AWARDED BID
=====	630-00012	Traf Ctrl Mgmt		Day =====			
MTCE0702-426		I70 FROM MP 155 TO 180 AND MP	07/07/22	20.00	800.00	350.00	100.00
MTCER300-272		REGION 3 ROUNDABOUT STRIPING	07/07/22	30.00	500.00	383.33	250.00
NHPP0702-414		VAIL PASS AUX PHASE 1 CAP 3	07/08/22	232.00	2746.52	2746.52	2746.52
FBR0702-423		VAIL PASS AUX BE F-12-AT PHAS					
FSA052A-057		SH52 BOX CULVERT EXTENSION (M	08/04/22	44.00	1200.00	1119.82	1170.00
STR0711-022		SH 71 OVER THE ARKANSAS	08/04/22	40.00	1000.00	1266.67	1300.00
NHPP0063-054		US 6 FROM I70-B TO 33 RD. (MP	08/18/22	375.00	1800.00	1543.39	1250.00
FBR0761-236		I-76 OVER CLR CRK SCOUR MIT	08/25/22	100.00	900.00	1033.33	1000.00
CL211-099		SH 121 NORTH SGA SIGNALS	08/25/22	120.00	1900.00	1320.00	1190.00
ER0502-092		US 50 MP 204 EB MONARCH TRUCK	08/29/22	45.00	1500.00	1391.37	1218.55
BR0343-046		US 34 TIMBER BRIDGE REPL. PKG	08/31/22	150.00	1073.57	1073.57	1073.57
FBR0343-047		US 6/US 34 TIMBER BRIDGE REPL					
STAR100-374		5 STRUCTURES IN REGION 1	09/01/22	113.00	1200.00	2093.50	2093.50
NHPPR100-266		R1 ESSENTIAL REPAIRS	09/01/22	100.00	450.00	1594.63	960.89
PAN0761-245		ALONG I-76 & RAMPS MILEPOST 9	09/01/22	30.00	1500.00	1497.50	815.00
ER0253-297		WCR 34 BRIDGE OVER I-25(MM 24	09/14/22	20.00	2000.00	1717.67	1500.00
2670403-065		US40_FLOYD HILL ROUNDABOUTS	09/15/22	190.00	1000.00	1795.83	2055.00
2670703-497		I-70 GENESEE WILDLIFE XING	09/15/22	140.00	1000.00	1676.55	1703.82
SHE2873-193		US 287 & CO 52 INTERSECTION I	09/15/22	200.00	1200.00	1548.00	1575.00
NHPP0701-231		I-70 SALT WASH BRIDGES SCOUR	09/29/22	85.00	1600.00	1508.90	1000.00
		WEIGHTED AVERAGE FOR THE THIRD QUARTER		2,042.00	1450.60	1551.72	1517.28
MTCE0253-281		MTCE FY23 I-25 CONC PANEL REP	10/06/22	25.00	1600.00	1635.90	1260.00
NHPP0821-114		SH 82 ASPEN/INDEPENDENCE PASS	10/13/22	25.00	1500.00	1290.00	1620.00
C0831-126		SH83 EL PASO COUNTY TO BAYOU	10/13/22	45.00	1300.00	1425.00	1500.00
NHPP0701-253		I-70 EAST OF DEBEQUE	10/27/22	81.00	1200.00	1380.00	1430.00
STA207A-004		Resurfacing SH207A MANZANOLA	10/27/22	140.00	1100.00	1487.00	1676.00
NHPP0705-088		I-70 AGATE STRUCTURE REHAB	10/27/22	61.00	1100.00	1910.00	1540.00
FSAM240-200		SH21B CO SPRINGS SIGNAL REPLA	10/27/22	122.00	2000.00	1202.50	1095.00
C5502-111		US 550 MP 81 AND 89 RED MOUNT	10/27/22	20.00	1200.00	999.50	925.00
C170A-002		CRITICAL CULVERT CONST. PKG D	10/27/22	30.00	1200.00	1142.50	1150.00
TRG0253-264		I-25 AND SH 119 PARK-N-RIDE	10/27/22	300.00	1200.00	1379.04	1200.00
STA3852-015		US 385 HOLYOKE NORTH	10/27/22	140.00	2300.00	1875.00	1875.00
NHPP0343-048		US 34 (MP 169.3-171.4)	11/01/22	109.00	1200.00	1356.25	1300.00
STU0252-457		I-25:ALAMEDA RIVER PH 2.0	11/03/22	500.00	1850.00	1413.33	1220.00
SHE0242-087		US 24 SAFETY IMPRVMENTS, E OF	11/03/22	60.00	1200.00	1563.78	1791.34
STR064A-010		SH 64 AND SH 13 AT MEEKER	11/10/22	110.00	1500.00	1615.00	1750.00
NHPP0853-126		US85C: PLATTEVILLE NORTH MP (11/10/22	75.00	1200.00	1553.00	1650.00
C5502-097		US550 MP 117.28-126.06	11/17/22	180.00	1200.00	1362.17	1350.00
MPR200-280		PUEBLO AREA	11/17/22	116.00	1240.00	850.00	1000.00
STRC090-011		US 50B AND SH71/CR18 INTERSEC	11/17/22	115.00	1300.00	1502.50	1410.00
STAM420-001		US 285 AT HWY 9C IMPROVEMENTS	12/01/22	100.00	1100.00	1366.40	1900.58
BR2854-148		INTERSECTION OF US 285 & SH 9					
STM0091-046		ADA RAMP IMPROVEMENTS - FAIRP					

PROJECT NUMBER	ITEM NUMBER/ PROJECT LOCATION	ITEM DESCRIPTION/ PROJECT LOCATION	DATE LET	UNIT/ QUANTITY	ENGR. EST.	AVERAGE BID	AWARDED BID
===== 630-00012 Traf Ctrl Mgmt Day =====							
STA0711-021		SH71: REGION LINE NORTH	12/01/22	102.00	1200.00	1808.33	1400.00
STR114A-015		SH114 SILLSVILLE SOUTH TO MP3	12/01/22	105.00	1200.00	1850.00	1400.00
2670703-487		I-70 BRIDGES OVER WARD ROAD-	12/01/22	340.00	1200.00	1447.70	1270.00
NHPP0701-252		I-70 RIFLE TO SILT SLAB REPLA	12/01/22	128.00	1500.00	1550.00	1300.00
IM025A-050		I25-MP103.9 - INTERSECTION DR	12/01/22	265.00	925.00	1008.33	1200.00
STR318A-001		SH 318 MP 0 - 12.5 MOFFAT COU	12/01/22	105.00	1300.00	1550.00	1400.00
STR109A-019		M-22-AY BRIDGE REHAB ON SH109	12/01/22	290.00	1200.00	1154.00	1045.00
NHPP0021-041		SH2 RESURFACING MLK TO 52ND	12/01/22	50.00	1500.00	1618.70	908.45
STR0641-107		SH 13 MM 104-128.1 IN MOFFAT	12/01/22	50.00	1500.00	1104.50	750.00
NHPP083A-046		SH83 RESURFACING STROH RD TO	12/08/22	60.00	1000.00	1630.54	1461.07
NHPP0063-048		US6 / 20 ROAD INTERSECTION IM	12/15/22	85.00	1400.00	1668.10	1200.00
NHM175-029		CANON CITY, CO	12/15/22	40.00	1100.00	827.50	1200.00
FSA0853-122		WCR14.5 AND US-85, FORT LUPTO	12/15/22	17.00	1300.00	1546.50	1250.00
NHPP0931-033		SH93:US6 TO 58TH RESURFACING	12/15/22	115.00	1300.00	1614.04	1540.00
NHPP0502-090		SH 50 MP 134.6-136 GUNNISON C	12/22/22	120.00	1500.00	1759.35	2062.86
STR0092-024		SH 9 North of Silverthorne	12/22/22	104.00	1300.00	1505.00	1560.00
STA0361-129		US 36: HYGIENE RD AND NELSON	12/22/22	85.00	1200.00	1497.61	1487.06
BR012A-048		CO 12 STRUCTURE P-17-F AT MP	12/22/22	30.00	1000.00	1156.68	1300.00
STA385A-016		SH 385 MP 97.76	12/22/22	150.00	1000.00	1365.28	1111.11
STR096A-050		SH 96 MP 168.99 TO 193.77	12/22/22	115.00	990.00	2100.00	1400.00
WEIGHTED AVERAGE FOR THE FOURTH QUARTER				4,710.00	1332.51	1463.94	1381.50
WEIGHTED AVERAGE FOR THE YEAR				12,706.00	1263.46	1487.67	1451.00
===== 630-00015 Uniformed Traf Ctrl Coordination Hour =====							
STA0252-459			02/03/22	10.00	40.00	42.45	25.65
NHPP 0761-238		I-76 DAHLIA TO YORK	03/10/22	150.00	35.00	18.17	11.00
C0761-239							
NHPP0703-472			03/10/22	80.00	60.00	70.29	70.00
WEIGHTED AVERAGE FOR THE FIRST QUARTER				240.00	43.54	29.40	31.28
2670703-479		I-70 BRIDGE OVER HARLAN	05/05/22	30.00	50.00	28.64	30.41
MPR200-278		R2 - VARIOUS LOCATIONS	06/09/22	15.00	100.00	30.00	20.00
MPR200-279		FY 23 STENCIL MARKING PROJECT	06/09/22	24.00	100.00	66.67	25.00
WEIGHTED AVERAGE FOR THE SECOND QUARTER				69.00	78.26	38.06	26.27
FSAM240-200		SH21B CO SPRINGS SIGNAL REPLA	10/27/22	20.00	40.00	30.50	10.00

COLORADO DEPARTMENT OF TRANSPORTATION
ITEM UNIT COSTS BY PROJECTS -- 2022 COST DATA

11:31 Wednesday, March 8, 2023 576

PROJECT NUMBER	ITEM NUMBER/ PROJECT LOCATION	ITEM DESCRIPTION/ PROJECT LOCATION	DATE LET	UNIT/ QUANTITY	ENGR. EST.	AVERAGE BID	AWARDED BID
===== 630-00015 Uniformed Traf Ctrl Coordination Hour =====							
NHPP0853-126		US85C: PLATTEVILLE NORTH MP (11/10/22	20.00	50.00	64.58	27.50
STRC090-011		US 50B AND SH71/CR18 INTERSEC	11/17/22	20.00	30.00	41.00	10.00
2670703-487		I-70 BRIDGES OVER WARD ROAD-	12/01/22	100.00	15.00	36.70	29.00
NHPP083A-046		SH83 RESURFACING STROH RD TO	12/08/22	90.00	40.00	118.97	120.94
NHPP0063-048		US6 / 20 ROAD INTERSECTION IM	12/15/22	25.00	30.00	110.86	95.00
	WEIGHTED AVERAGE FOR THE FOURTH QUARTER			275.00	30.00	61.39	62.22
	WEIGHTED AVERAGE FOR THE YEAR			584.00	41.27	41.54	45.25
===== 630-00017 Traffic Control Management (Special) Day =====							
BRC040-057			03/17/22	125.00	800.00	1866.00	1500.00
	WEIGHTED AVERAGE FOR THE FIRST QUARTER			125.00	800.00	1866.00	1500.00
STM1151-038		SH115 MP 27 TO MP 38	04/21/22	24.00	2000.00	5492.97	4200.00
NHC540-017		R2 CHAINUP STA @ KENOSHA/HOOS	05/12/22	160.00	1013.00	2033.33	2300.00
	WEIGHTED AVERAGE FOR THE SECOND QUARTER			184.00	1141.74	2725.26	2547.83
STAM420-001		US 285 AT HWY 9C IMPROVEMENTS	12/01/22	25.00	1100.00	2253.90	1900.58
BR2854-148		INTERSECTION OF US 285 & SH 9					
STM0091-046		ADA RAMP IMPROVEMENTS - FAIRP					
	WEIGHTED AVERAGE FOR THE FOURTH QUARTER			25.00	1100.00	2253.90	1900.58
	WEIGHTED AVERAGE FOR THE YEAR			334.00	1010.72	2327.96	2107.23
===== 630-00030 Courtesy Patrol Day =====							
NHPP 0761-238		I-76 DAHLIA TO YORK	03/10/22	722.00	870.00	1417.35	1490.00
C0761-239							
	WEIGHTED AVERAGE FOR THE FIRST QUARTER			722.00	870.00	1417.35	1490.00
	WEIGHTED AVERAGE FOR THE YEAR			722.00	870.00	1417.35	1490.00
===== 630-00031 Courtesy Patrol Hour =====							
STM1151-038		SH115 MP 27 TO MP 38	04/21/22	144.00	100.00	221.56	200.00
	WEIGHTED AVERAGE FOR THE SECOND QUARTER			144.00	100.00	221.56	200.00
	WEIGHTED AVERAGE FOR THE YEAR			144.00	100.00	221.56	200.00

COLORADO DEPARTMENT OF TRANSPORTATION
ITEM UNIT COSTS BY PROJECTS -- 2022 COST DATA

11:31 Wednesday, March 8, 2023 577

PROJECT NUMBER	ITEM NUMBER/ PROJECT LOCATION	ITEM DESCRIPTION/ PROJECT LOCATION	DATE LET	UNIT/ QUANTITY	ENGR. EST.	AVERAGE BID	AWARDED BID	
===== 630-00040				Develop Traf Incident Mgmt Plan				LUMP SUM =====
NHPP 0761-238 C0761-239	I-76 DAHLIA TO YORK		03/10/22	1.00	4000.00	5460.96	3300.00	
	WEIGHTED AVERAGE FOR THE FIRST QUARTER			1.00	4000.00	5460.96	3300.00	
STM1151-038	SH115 MP 27 TO MP 38		04/21/22	1.00	3500.00	6381.63	5000.00	
	WEIGHTED AVERAGE FOR THE SECOND QUARTER			1.00	3500.00	6381.63	5000.00	
TRG0253-264 IM025A-050	I-25 AND SH 119 PARK-N-RIDE		10/27/22	1.00	3300.00	6140.63	5700.00	
	I25-MP103.9 - INTERSECTION DR		12/01/22	1.00	3000.00	11766.67	4300.00	
	WEIGHTED AVERAGE FOR THE FOURTH QUARTER			2.00	3150.00	7675.00	5000.00	
	WEIGHTED AVERAGE FOR THE YEAR			4.00	3450.00	6667.54	4575.00	
===== 630-00041				Implement Traf Incident Mgmt Plan				Month =====
NHPP 0761-238 C0761-239	I-76 DAHLIA TO YORK		03/10/22	24.00	800.00	648.87	450.00	
	WEIGHTED AVERAGE FOR THE FIRST QUARTER			24.00	800.00	648.87	450.00	
STM1151-038	SH115 MP 27 TO MP 38		04/21/22	18.00	1500.00	3211.43	500.00	
	WEIGHTED AVERAGE FOR THE SECOND QUARTER			18.00	1500.00	3211.43	500.00	
TRG0253-264 IM025A-050	I-25 AND SH 119 PARK-N-RIDE		10/27/22	12.00	450.00	968.13	600.00	
	I25-MP103.9 - INTERSECTION DR		12/01/22	12.00	500.00	1066.67	1100.00	
	WEIGHTED AVERAGE FOR THE FOURTH QUARTER			24.00	475.00	995.00	850.00	
	WEIGHTED AVERAGE FOR THE YEAR			66.00	872.73	1316.31	609.09	

COLORADO DEPARTMENT OF TRANSPORTATION
 ITEM UNIT COSTS BY PROJECTS -- 2022 COST DATA

11:31 Wednesday, March 8, 2023 578

PROJECT NUMBER	ITEM NUMBER/ PROJECT LOCATION	ITEM DESCRIPTION/ PROJECT LOCATION	DATE LET	UNIT/ QUANTITY	ENGR. EST.	AVERAGE BID	AWARDED BID
=====	630-80001	Flash Beacon (Port)		Each =====			
NHPP0702-383		I-70 EB AUX FRISCO TO SILVERT	01/13/22	10.00	150.00	1084.20	330.00
C0762-055			02/17/22	12.00	1000.00	1018.50	800.00
STR0141-031			02/17/22	6.00	2000.00	1583.33	1650.00
STA 067A-048		Hwy 67A MP 0.00 TO MP 11.05 I	03/03/22	8.00	850.00	885.79	1200.00
NHPP 0761-238		I-76 DAHLIA TO YORK	03/10/22	61.00	1000.00	1051.86	1050.00
C0761-239							
STR160A-034		US160A LA VETA PASS EAST SURF	03/17/22	13.00	1000.00	1152.47	1104.93
BRC040-057			03/17/22	10.00	1000.00	1085.75	1000.00
NHM765-007			03/31/22	16.00	1600.00	1659.91	2166.00
C0703-499		EJMT GROUT BED REPAIR AND PAN	03/31/22	12.00	900.00	2629.50	2750.00
		WEIGHTED AVERAGE FOR THE FIRST QUARTER		148.00	1031.76	1151.88	1273.45
NHPP0702-413		VAIL PASS AUX PHASE 1 CAP 2	04/18/22	4.00	1712.00	1712.00	1712.00
STM1151-038		SH115 MP 27 TO MP 38	04/21/22	20.00	850.00	919.23	850.00
STAR100-358		3 STRUCTURES IN REGION 1 METR	05/26/22	6.00	1500.00	1582.62	2120.00
NHPP0252-448		I-25 TREX NARROWS BRIDGE PREV	06/23/22	8.00	1200.00	536.00	550.00
		WEIGHTED AVERAGE FOR THE SECOND QUARTER		38.00	1117.05	937.73	1078.11
NHPP0702-414		VAIL PASS AUX PHASE 1 CAP 3	07/08/22	16.00	1647.91	1647.91	1647.91
FBR0702-423		VAIL PASS AUX BE F-12-AT PHAS					
C1211-099		SH 121 NORTH SGA SIGNALS	08/25/22	6.00	1200.00	604.00	108.00
BR0343-046		US 34 TIMBER BRIDGE REPL. PKG	08/31/22	12.00	6.00	6.00	6.00
FBR0343-047		US 6/US 34 TIMBER BRIDGE REPL					
STAR100-374		5 STRUCTURES IN REGION 1	09/01/22	6.00	2200.00	795.00	795.00
NHPPR100-266		R1 ESSENTIAL REPAIRS	09/01/22	20.00	1100.00	1911.13	95.40
ER0253-297		WCR 34 BRIDGE OVER I-25(MM 24	09/14/22	6.00	1500.00	910.93	200.00
2670703-497		I-70_GENESEE WILDLIFE KING	09/15/22	3.00	970.00	989.47	1135.88
		WEIGHTED AVERAGE FOR THE THIRD QUARTER		69.00	1170.27	1296.46	556.12
NHPP0701-253		I-70 EAST OF DEBEQUE	10/27/22	8.00	30.00	1215.00	1200.00
STA207A-004		Resurfacing SH207A MANZANOLA	10/27/22	4.00	1000.00	1248.33	1245.00
NHPP0705-088		I-70 AGATE STRUCTURE REHAB	10/27/22	24.00	1300.00	1723.86	3000.00
C170A-002		CRITICAL CULVERT CONST. PKG D	10/27/22	6.00	1800.00	289.17	316.67
TRG0253-264		I-25 AND SH 119 PARK-N-RIDE	10/27/22	4.00	850.00	2417.88	2800.00

COLORADO DEPARTMENT OF TRANSPORTATION
 ITEM UNIT COSTS BY PROJECTS -- 2022 COST DATA

11:31 Wednesday, March 8, 2023 579

PROJECT NUMBER	ITEM NUMBER/ PROJECT LOCATION	ITEM DESCRIPTION/ PROJECT LOCATION	DATE LET	UNIT/ QUANTITY	ENGR. EST.	AVERAGE BID	AWARDED BID
=====	630-80001	Flash Beacon (Port)		Each =====			
STA3852-015		US 385 HOLYOKE NORTH	10/27/22	2.00	1200.00	2100.00	2100.00
STU0252-457		I-25:ALAMEDA RIVER PH 2.0	11/03/22	12.00	1500.00	1863.65	1900.00
SHE0242-087		US 24 SAFETY IMPRVMENTS, E OF	11/03/22	6.00	1000.00	1471.22	1313.65
STR064A-010		SH 64 AND SH 13 AT MEEKER	11/10/22	2.00	2500.00	1215.00	1000.00
STRC090-011		US 50B AND SH71/CR18 INTERSEC	11/17/22	8.00	900.00	1175.00	1250.00
STA0711-021		SH71: REGION LINE NORTH	12/01/22	8.00	920.00	1376.67	1500.00
NHPP0701-252		I-70 RIFLE TO SILT SLAB REPLA	12/01/22	10.00	2000.00	1127.50	500.00
IM025A-050		I25-MP103.9 - INTERSECTION DR	12/01/22	12.00	900.00	1200.00	1100.00
STR318A-001		SH 318 MP 0 - 12.5 MOFFAT COU	12/01/22	2.00	2000.00	1535.00	1620.00
STR109A-019		M-22-AY BRIDGE REHAB ON SH109	12/01/22	10.00	1000.00	1385.00	1254.00
STR0641-107		SH 13 MM 104-128.1 IN MOFFAT	12/01/22	6.00	25.00	1386.67	1100.00
NHPP083A-046		SH83 RESURFACING STROH RD TO	12/08/22	16.00	650.00	1515.09	1530.18
NHPP0063-048		US6 / 20 ROAD INTERSECTION IM	12/15/22	17.00	1500.00	1270.86	1100.00
STR0092-024		SH 9 North of Silverthorne	12/22/22	4.00	600.00	1245.00	1290.00
BR012A-048		CO 12 STRUCTURE P-17-F AT MP	12/22/22	9.00	1000.00	1256.68	1500.00
STA385A-016		SH 385 MP 97.76	12/22/22	2.00	650.00	1674.17	1666.67
		WEIGHTED AVERAGE FOR THE FOURTH QUARTER		172.00	1099.71	1444.82	1519.34
		WEIGHTED AVERAGE FOR THE YEAR		427.00	1089.10	1244.15	1246.85
=====	630-80002	Flash Beacon (Solar)		Each =====			
NH0504-910		US50B L-24-B MIN REP AT MP 40	01/13/22	8.00	1500.00	1142.04	1333.33
		WEIGHTED AVERAGE FOR THE FIRST QUARTER		8.00	1500.00	1142.04	1333.33
NH0504-911			04/07/22	44.00	1000.00	927.50	955.00
ER0702-420		PR I-70 GWC MATERIAL FLOWS 20	05/06/22	10.00	1000.00	1050.00	1000.00
NHPP 3851-018		US 385 NORTH OF CHEYENNE WELL	05/26/22	2.00	1000.00	2200.00	1400.00
FSA052A-046		SH52 WCR 37 INTERSECTION IMPR	06/09/22	4.00	1500.00	1387.93	700.00
		WEIGHTED AVERAGE FOR THE SECOND QUARTER		60.00	1033.33	1054.38	960.33
STR0711-022		SH 71 OVER THE ARKANSAS	08/04/22	4.00	900.00	1433.33	2100.00
		WEIGHTED AVERAGE FOR THE THIRD QUARTER		4.00	900.00	1433.33	2100.00
NHPP0853-126		US85C: PLATTEVILLE NORTH MP (11/10/22	4.00	1000.00	666.95	660.00

COLORADO DEPARTMENT OF TRANSPORTATION
 ITEM UNIT COSTS BY PROJECTS -- 2022 COST DATA

11:31 Wednesday, March 8, 2023 580

PROJECT NUMBER	ITEM NUMBER/ PROJECT LOCATION	ITEM DESCRIPTION/ PROJECT LOCATION	DATE LET	UNIT/ QUANTITY	ENGR. EST.	AVERAGE BID	AWARDED BID
=====	630-80002	Flash Beacon (Solar)		Each	=====	=====	=====
2670703-487		I-70 BRIDGES OVER WARD ROAD-	12/01/22	8.00	1500.00	2749.60	3220.00
NHPP0502-090		SH 50 MP 134.6-136 GUNNISON C	12/22/22	5.00	1400.00	1827.14	2134.00
STR096A-050		SH 96 MP 168.99 TO 193.77	12/22/22	8.00	900.00	1400.00	2000.00
	WEIGHTED AVERAGE FOR THE FOURTH QUARTER			25.00	1208.00	1858.73	2202.80
	WEIGHTED AVERAGE FOR THE YEAR			97.00	1111.34	1363.00	1358.32
=====	630-80305	Flagging Station Light		Each	=====	=====	=====
MTCER400-391		VARIOUS HIGHWAY SEGMENTS ACRO	01/13/22	4.00	400.00	562.50	250.00
	WEIGHTED AVERAGE FOR THE FIRST QUARTER			4.00	400.00	562.50	250.00
MPR200-279		FY 23 STENCIL MARKING PROJECT	06/09/22	4.00	500.00	766.67	150.00
	WEIGHTED AVERAGE FOR THE SECOND QUARTER			4.00	500.00	766.67	150.00
	WEIGHTED AVERAGE FOR THE YEAR			8.00	450.00	650.00	200.00
=====	630-80310	Automated Flagging Assistance Device		Each	=====	=====	=====
STM1151-038		SH115 MP 27 TO MP 38	04/21/22	2.00	10000.00	9618.56	12000.00
	WEIGHTED AVERAGE FOR THE SECOND QUARTER			2.00	10000.00	9618.56	12000.00
	WEIGHTED AVERAGE FOR THE YEAR			2.00	10000.00	9618.56	12000.00
=====	630-80331	Barricade (3 F-A) (Temp)		Each	=====	=====	=====
ER0502-092		US 50 MP 204 EB MONARCH TRUCK	08/29/22	2.00	1000.00	413.93	447.36
	WEIGHTED AVERAGE FOR THE THIRD QUARTER			2.00	1000.00	413.93	447.36
	WEIGHTED AVERAGE FOR THE YEAR			2.00	1000.00	413.93	447.36
=====	630-80335	Barricade (3 M-A) (Temp)		Each	=====	=====	=====
ITS0703-477		ITS EQUIPMENT UPGRADE AT EJMT	01/06/22	2.00	250.00	66.00	66.00

COLORADO DEPARTMENT OF TRANSPORTATION
ITEM UNIT COSTS BY PROJECTS -- 2022 COST DATA

11:31 Wednesday, March 8, 2023 581

PROJECT NUMBER	ITEM NUMBER/ PROJECT LOCATION	ITEM DESCRIPTION/ PROJECT LOCATION	DATE LET	UNIT/ QUANTITY	ENGR. EST.	AVERAGE BID	AWARDED BID
===== 630-80335							
		Barricade (3 M-A) (Temp)		Each			
NHPP2873-189		US 287 (FEDERAL BLVD) - COLFA	01/06/22	6.00	180.00	97.35	93.02
NH0504-910		US50B L-24-B MIN REP AT MP 40	01/13/22	4.00	300.00	214.39	111.11
NHPP0702-383		I-70 EB AUX FRISCO TO SILVERT	01/13/22	6.00	300.00	323.83	66.00
NHPP1601-083			02/03/22	2.00	300.00	1617.51	300.00
STA0252-459			02/03/22	8.00	200.00	85.02	61.50
C0762-055			02/17/22	6.00	225.00	228.68	400.00
NHPP 0761-238		I-76 DAHLIA TO YORK	03/10/22	55.00	150.00	113.81	110.00
C0761-239							
NHPP0703-472			03/10/22	4.00	160.00	134.10	40.00
CR100-362			03/14/22	10.00	133.75	133.75	133.75
STR160A-034		US160A LA VETA PASS EAST SURF	03/17/22	4.00	200.00	263.12	276.23
BRC040-057			03/17/22	10.00	175.00	436.25	350.00
M R100-351		FY22 R1 SIGN STRUCTURE REPLAC	03/17/22	4.00	220.00	84.00	104.00
STR092A-031			03/17/22	14.00	200.00	380.50	380.50
NHM765-007			03/31/22	30.00	400.00	345.00	456.00
WEIGHTED AVERAGE FOR THE FIRST QUARTER				165.00	221.74	186.95	221.81
NH0504-911			04/07/22	4.00	142.00	239.50	239.00
NHPP0702-413		VAIL PASS AUX PHASE 1 CAP 2	04/18/22	6.00	481.50	481.50	481.50
STM1151-038		SH115 MP 27 TO MP 38	04/21/22	4.00	150.00	381.80	350.00
MTCE2873-204		MTCE FY22 SH287 CONC PANEL RE	05/05/22	4.00	300.00	290.60	191.20
STA001A-005		SH1 WELLINGTON SOUTH RESURFAC	05/12/22	4.00	180.00	98.95	102.00
STAR100-358		3 STRUCTURES IN REGION 1 METR	05/26/22	4.00	200.00	175.79	238.00
C0852-120		Rehabilitation of Culvert by	05/26/22	2.00	200.00	375.00	375.00
NHPP072A-047		SH-72 RESURFACING: I-70 TO IN	06/09/22	2.00	250.00	89.81	89.81
NHPP0252-448		I-25 TREX NARROWS BRIDGE PREV	06/23/22	14.00	150.00	125.25	150.00
WEIGHTED AVERAGE FOR THE SECOND QUARTER				44.00	222.20	209.92	236.35
NHPP0702-414		VAIL PASS AUX PHASE 1 CAP 3	07/08/22	8.00	494.37	494.37	494.37
FBR0702-423		VAIL PASS AUX BE F-12-AT PHAS					
STR0711-022		SH 71 OVER THE ARKANSAS	08/04/22	2.00	200.00	271.67	65.00
NHPP0063-054		US 6 FROM I70-B TO 33 RD. (MP	08/18/22	10.00	140.00	200.19	245.00
C1211-099		SH 121 NORTH SGA SIGNALS	08/25/22	6.00	225.00	140.50	81.00
BR0343-046		US 34 TIMBER BRIDGE REPL. PKG	08/31/22	36.00	62.08	62.08	62.08
FBR0343-047		US 6/US 34 TIMBER BRIDGE REPL					
STAR100-374		5 STRUCTURES IN REGION 1	09/01/22	4.00	250.00	190.80	190.80
NHPPR100-266		R1 ESSENTIAL REPAIRS	09/01/22	4.00	95.00	130.67	53.00
2670403-065		US40 FLOYD HILL ROUNDABOUTS	09/15/22	19.00	150.00	504.58	667.00
NHPP0701-231		I-70 SALT WASH BRIDGES SCOUR	09/29/22	2.00	350.00	412.08	500.00
WEIGHTED AVERAGE FOR THE THIRD QUARTER				91.00	156.81	290.88	262.68

PROJECT NUMBER	ITEM NUMBER/ PROJECT LOCATION	ITEM DESCRIPTION/ PROJECT LOCATION	DATE LET	UNIT/ QUANTITY	ENGR. EST.	AVERAGE BID	AWARDED BID
===== 630-80335		Barricade (3 M-A) (Temp)		Each	=====		
MTCE0253-281		MTCE FY23 I-25 CONC PANEL REP	10/06/22	4.00	300.00	235.70	395.00
TRG0253-264		I-25 AND SH 119 PARK-N-RIDE	10/27/22	8.00	220.00	1029.13	1500.00
NHPP0343-048		US 34 (MP 169.3-171.4)	11/01/22	4.00	160.00	321.55	165.00
STU0252-457		I-25:ALAMEDA RIVER PH 2.0	11/03/22	75.00	300.00	431.60	410.00
SHE0242-087		US 24 SAFETY IMPRVMTS, E OF	11/03/22	7.00	150.00	392.66	417.98
NHPP0853-126		US85C: PLATTEVILLE NORTH MP (11/10/22	8.00	200.00	104.10	104.50
STRC090-011		US 50B AND SH71/CR18 INTERSEC	11/17/22	5.00	400.00	287.50	190.00
2670703-487		I-70 BRIDGES OVER WARD ROAD-	12/01/22	15.00	400.00	409.50	430.00
IM025A-050		I25-MP103.9 - INTERSECTION DR	12/01/22	24.00	175.00	256.67	320.00
STR109A-019		M-22-AY BRIDGE REHAB ON SH109	12/01/22	2.00	250.00	133.54	141.08
NHPP0021-041		SH2 RESURFACING MLK TO 52ND	12/01/22	4.00	250.00	279.19	184.14
NHPP0063-048		US6 / 20 ROAD INTERSECTION IM	12/15/22	8.00	500.00	286.84	250.00
NHM175-029		CANON CITY, CO	12/15/22	8.00	200.00	225.00	300.00
FSA0853-122		WCR14.5 AND US-85, FORT LUPTO	12/15/22	8.00	300.00	156.52	80.00
NHPP0931-033		SH93:US6 TO 58TH RESURFACING	12/15/22	4.00	300.00	114.48	128.00
STR096A-050		SH 96 MP 168.99 TO 193.77	12/22/22	2.00	160.00	350.00	300.00
		WEIGHTED AVERAGE FOR THE FOURTH QUARTER		186.00	279.41	403.27	384.18
		WEIGHTED AVERAGE FOR THE YEAR		486.00	231.70	282.69	294.03
===== 630-80336		Barricade (3 M-B) (Temp)		Each	=====		
MTCE R500-218			01/06/22	3.00	200.00	127.50	75.00
STR0141-031			02/17/22	2.00	350.00	496.67	700.00
NHPP0063-063			02/24/22	14.00	230.00	514.00	500.00
STR R500-171		Various locations on SH 141 a	03/17/22	6.00	250.00	2894.87	50.00
		WEIGHTED AVERAGE FOR THE FIRST QUARTER		25.00	240.80	1211.12	357.00
NH0504-911			04/07/22	10.00	300.00	299.00	298.00
STM1151-038		SH115 MP 27 TO MP 38	04/21/22	4.00	360.00	434.34	400.00
2670703-479		I-70 BRIDGE OVER HARLAN	05/05/22	5.00	220.00	287.95	273.71
MTCE0253-291		I-25 SIGN REPLACEMENT PHASE 2	06/16/22	4.00	250.00	900.85	1394.70
NHPP0252-448		I-25 TREX NARROWS BRIDGE PREV	06/23/22	8.00	260.00	125.25	150.00
		WEIGHTED AVERAGE FOR THE SECOND QUARTER		31.00	278.06	313.82	410.56
ER0253-297		WCR 34 BRIDGE OVER I-25(MM 24	09/14/22	10.00	240.00	372.12	51.00

COLORADO DEPARTMENT OF TRANSPORTATION
ITEM UNIT COSTS BY PROJECTS -- 2022 COST DATA

11:31 Wednesday, March 8, 2023 583

PROJECT NUMBER	ITEM NUMBER/ PROJECT LOCATION	ITEM DESCRIPTION/ PROJECT LOCATION	DATE LET	UNIT/ QUANTITY	ENGR. EST.	AVERAGE BID	AWARDED BID
=====	630-80336	Barricade (3 M-B) (Temp)		Each =====			
SHE2873-193		US 287 & CO 52 INTERSECTION I	09/15/22	4.00	150.00	376.67	397.00
		WEIGHTED AVERAGE FOR THE THIRD QUARTER		14.00	214.29	373.83	149.86
NHPP0705-088		I-70 AGATE STRUCTURE REHAB	10/27/22	24.00	400.00	468.20	385.00
SHE0242-087		US 24 SAFETY IMPRVMENTS, E OF	11/03/22	2.00	300.00	529.23	477.69
C5502-097		US550 MP 117.28-126.06	11/17/22	2.00	180.00	775.73	864.00
STA0711-021		SH71: REGION LINE NORTH	12/01/22	4.00	250.00	438.33	300.00
2670703-487		I-70 BRIDGES OVER WARD ROAD-	12/01/22	15.00	180.00	429.50	430.00
STR109A-019		M-22-AY BRIDGE REHAB ON SH109	12/01/22	5.00	350.00	380.67	193.33
NHPP0502-090		SH 50 MP 134.6-136 GUNNISON C	12/22/22	6.00	300.00	505.91	711.33
BR012A-048		CO 12 STRUCTURE P-17-F AT MP	12/22/22	4.00	300.00	402.67	400.00
STA385A-016		SH 385 MP 97.76	12/22/22	8.00	250.00	444.11	444.44
		WEIGHTED AVERAGE FOR THE FOURTH QUARTER		70.00	300.14	480.40	431.94
		WEIGHTED AVERAGE FOR THE YEAR		140.00	276.07	513.36	386.90
=====	630-80337	Barricade (3 M-C) (Temp)		Each =====			
C0703-499		EJMT GROUT BED REPAIR AND PAN	03/31/22	2.00	250.00	391.50	280.00
		WEIGHTED AVERAGE FOR THE FIRST QUARTER		2.00	250.00	391.50	280.00
NH0504-911			04/07/22	4.00	300.00	409.00	418.00
		WEIGHTED AVERAGE FOR THE SECOND QUARTER		4.00	300.00	409.00	418.00
2670703-497		I-70_GENESEE WILDLIFE KING	09/15/22	1.00	300.00	623.72	511.15
		WEIGHTED AVERAGE FOR THE THIRD QUARTER		1.00	300.00	623.72	511.15
		WEIGHTED AVERAGE FOR THE YEAR		7.00	285.71	484.42	391.88
=====	630-80338	Barricade (3 M-D) (Temp)		Each =====			
STR0505-050			01/13/22	8.00	300.00	567.67	600.00

COLORADO DEPARTMENT OF TRANSPORTATION
ITEM UNIT COSTS BY PROJECTS -- 2022 COST DATA

11:31 Wednesday, March 8, 2023 584

PROJECT NUMBER	ITEM NUMBER/ PROJECT LOCATION	ITEM DESCRIPTION/ PROJECT LOCATION	DATE LET	UNIT/ QUANTITY	ENGR. EST.	AVERAGE BID	AWARDED BID
=====	630-80338	Barricade (3 M-D) (Temp)		Each =====			
C0762-055			02/17/22	4.00	400.00	796.62	500.00
		WEIGHTED AVERAGE FOR THE FIRST QUARTER		12.00	333.33	659.25	566.67
NH0504-911			04/07/22	2.00	600.00	409.00	418.00
STA0712-019		SH 71: Frieight Improvements	05/12/22	12.00	250.00	517.53	517.53
		WEIGHTED AVERAGE FOR THE SECOND QUARTER		14.00	300.00	490.40	503.31
		WEIGHTED AVERAGE FOR THE YEAR		26.00	315.38	611.00	532.55
=====	630-80340	Pedestrian Barricade (ADA)		Lin Foot =====			
NHPP0702-383		I-70 EB AUX FRISCO TO SILVERT	01/13/22	40.00	50.00	35.42	46.00
NHPP0063-063			02/24/22	100.00	45.00	30.55	40.00
CR100-362			03/14/22	500.00	37.45	37.45	37.45
STR092A-031			03/17/22	350.00	40.00	27.00	27.00
		WEIGHTED AVERAGE FOR THE FIRST QUARTER		990.00	39.62	33.10	34.36
CC030-081		ADA RAMP AND CURBS - FT. LUPT	04/14/22	100.00	55.00	73.98	60.00
		WEIGHTED AVERAGE FOR THE SECOND QUARTER		100.00	55.00	73.98	60.00
NHPP0063-054		US 6 FROM I70-B TO 33 RD. (MP	08/18/22	300.00	17.00	34.54	38.00
C1211-099		SH 121 NORTH SGA SIGNALS	08/25/22	400.00	35.00	75.50	98.00
NHPPR100-266		R1 ESSENTIAL REPAIRS	09/01/22	100.00	50.00	84.98	39.94
		WEIGHTED AVERAGE FOR THE THIRD QUARTER		800.00	30.13	62.71	68.24
STA207A-004		Resurfacing SH207A MANZANOLA	10/27/22	195.00	50.00	73.57	80.70
STAM420-001		US 285 AT HWY 9C IMPROVEMENTS	12/01/22	100.00	35.80	55.34	62.87
BR2854-148		INTERSECTION OF US 285 & SH 9					
STM0091-046		ADA RAMP IMPROVEMENTS - FAIRP					

COLORADO DEPARTMENT OF TRANSPORTATION
 ITEM UNIT COSTS BY PROJECTS -- 2022 COST DATA

11:31 Wednesday, March 8, 2023 585

PROJECT NUMBER	ITEM NUMBER/ PROJECT LOCATION	ITEM DESCRIPTION/ PROJECT LOCATION	DATE LET	UNIT/ QUANTITY	ENGR. EST.	AVERAGE BID	AWARDED BID
=====	630-80340	Pedestrian Barricade (ADA)		Lin Foot	=====	=====	=====
NHPP0021-041		SH2 RESURFACING MLK TO 52ND	12/01/22	50.00	50.00	124.83	46.26
NHPP083A-046		SH83 RESURFACING STROH RD TO	12/08/22	100.00	45.00	45.69	46.37
		WEIGHTED AVERAGE FOR THE FOURTH QUARTER		445.00	45.69	71.68	65.11
		WEIGHTED AVERAGE FOR THE YEAR		2,335.00	38.18	58.13	52.93
=====	630-80341	Const Traf Sign (A)		Each	=====	=====	=====
ITS0703-477		ITS EQUIPMENT UPGRADE AT EJMT	01/06/22	26.00	50.00	44.00	44.00
MTCE R500-218			01/06/22	72.00	35.00	30.20	10.00
NHPP2873-189		US 287 (FEDERAL BLVD) - COLFA	01/06/22	20.00	46.00	60.27	55.81
STR0505-050			01/13/22	68.00	40.00	72.00	90.00
NH0504-910		US50B L-24-B MIN REP AT MP 40	01/13/22	34.00	80.00	60.67	55.56
MTCER400-391		VARIOUS HIGHWAY SEGMENTS ACRO	01/13/22	56.00	20.00	20.00	5.00
NHPP0702-383		I-70 EB AUX FRISCO TO SILVERT	01/13/22	56.00	80.00	67.10	43.00
MTCER300-262			02/03/22	18.00	40.00	43.33	10.00
NHPP1601-083			02/03/22	40.00	35.00	113.66	35.00
STA0252-459			02/03/22	36.00	69.59	69.45	41.00
C0762-055			02/17/22	66.00	60.00	203.84	56.00
STR0141-031			02/17/22	100.00	60.00	68.33	85.00
STR133A-051			02/17/22	35.00	50.00	58.33	67.00
NHPP0063-063			02/24/22	174.00	45.00	88.25	92.00
STA 067A-048		Hwy 67A MP 0.00 TO MP 11.05 I	03/03/22	64.00	55.00	40.82	44.00
NHPP 0761-238		I-76 DAHLIA TO YORK	03/10/22	281.00	50.00	90.94	110.00
C0761-239							
NHPP0703-472			03/10/22	70.00	50.00	53.00	50.00
CR100-362			03/14/22	20.00	58.85	58.85	58.85
STR160A-034		US160A LA VETA PASS EAST SURF	03/17/22	89.00	40.00	52.63	55.25
BRC040-057			03/17/22	56.00	51.00	51.25	35.00
STR R500-171		Various locations on SH 141 a	03/17/22	117.00	52.00	34.41	5.00
M R100-351		FY22 R1 SIGN STRUCTURE REPLAC	03/17/22	27.00	52.00	75.00	63.00
STR092A-031			03/17/22	79.00	50.00	54.50	54.50
MP0503-098			03/24/22	20.00	40.00	59.00	61.00
NHM765-007			03/31/22	148.00	125.00	129.69	171.00
C0703-499		EJMT GROUT BED REPAIR AND PAN	03/31/22	14.00	80.00	64.00	70.00
		WEIGHTED AVERAGE FOR THE FIRST QUARTER		1,786.00	56.25	79.39	70.92
NH0504-911			04/07/22	53.00	50.00	52.85	53.70
CC030-081		ADA RAMP AND CURBS - FT. LUPT	04/14/22	44.00	60.00	52.03	10.00
NHPP0702-413		VAIL PASS AUX PHASE 1 CAP 2	04/18/22	52.00	74.90	74.90	74.90
STM1151-038		SH115 MP 27 TO MP 38	04/21/22	170.00	100.00	70.31	65.00

PROJECT NUMBER	ITEM NUMBER/ PROJECT LOCATION	ITEM DESCRIPTION/ PROJECT LOCATION	DATE LET	UNIT/ QUANTITY	ENGR. EST.	AVERAGE BID	AWARDED BID
=====	630-80341	Const Traf Sign (A)		Each =====			
MTCE2873-204		MTCE FY22 SH287 CONC PANEL RE	05/05/22	18.00	65.00	182.64	265.28
2670703-479		I-70 BRIDGE OVER HARLAN	05/05/22	35.00	58.00	92.72	54.74
ER0702-420		PR I-70 GWC MATERIAL FLOWS 20	05/06/22	26.00	30.00	147.50	145.00
STA0712-019		SH 71: Frieght Improvements	05/12/22	60.00	70.00	62.10	62.10
STA001A-005		SH1 WELLINGTON SOUTH RESURFAC	05/12/22	92.00	64.00	83.75	38.00
NHC540-017		R2 CHAINUP STA @ KENOSHA/HOOS	05/12/22	4.00	57.00	52.00	51.00
CM760-047		COLFAX AND QUAIL	05/12/22	32.00	54.00	50.20	60.00
NHPP 3851-018		US 385 NORTH OF CHEYENNE WELL	05/26/22	12.00	65.00	300.00	50.00
STAR100-358		3 STRUCTURES IN REGION 1 METR	05/26/22	18.00	75.00	37.36	51.00
C0852-120		Rehabilitation of Culvert by	05/26/22	12.00	75.00	65.00	65.00
FSA0702-409		I-70 VAIL WILDLIFE FENCE PHAS	05/26/22	8.00	44.00	40.00	40.00
ITS 0741-024		VMS SIGN INSTALLATIONS AND VS	06/02/22	16.00	50.00	79.00	61.00
FSA3921-019		SH 392 AND WCR 55 ISLANDS	06/02/22	28.00	50.00	28.67	30.00
NHPP072A-047		SH-72 RESURFACING: I-70 TO IN	06/09/22	180.00	50.00	53.89	53.89
FSA052A-046		SH52 WCR 37 INTERSECTION IMPR	06/09/22	6.00	65.00	80.65	132.00
MPR200-278		R2 - VARIOUS LOCATIONS	06/09/22	24.00	15.00	13.33	5.00
MPR200-279		FY 23 STENCIL MARKING PROJECT	06/09/22	24.00	15.00	16.67	5.00
MTCE0253-291		I-25 SIGN REPLACEMENT PHASE 2	06/16/22	14.00	50.00	81.02	68.03
NHPP0252-448		I-25 TREX NARROWS BRIDGE PREV	06/23/22	110.00	75.00	61.25	70.00
		WEIGHTED AVERAGE FOR THE SECOND QUARTER		1,038.00	64.40	67.95	59.59
MTCE 072A-045		SH 72B MP 37.00 TO MP 45.3 NE	07/07/22	20.00	50.00	20.00	20.00
MTCE0702-426		I70 FROM MP 155 TO 180 AND MP	07/07/22	8.00	10.00	21.25	50.00
MT CER300-272		REGION 3 ROUNDABOUT STRIPING	07/07/22	8.00	50.00	50.00	50.00
NHPP0702-414		VAIL PASS AUX PHASE 1 CAP 3	07/08/22	28.00	109.86	109.86	109.86
FBR0702-423		VAIL PASS AUX BE F-12-AT PHAS					
FSA052A-057		SH52 BOX CULVERT EXTENSION (M	08/04/22	78.00	75.00	70.46	71.50
STR0711-022		SH 71 OVER THE ARKANSAS	08/04/22	14.00	62.00	63.33	55.00
NHPP0063-054		US 6 FROM I70-B TO 33 RD. (MP	08/18/22	84.00	50.00	63.40	75.00
FBR0761-236		I-76 OVER CLR CRK SCOUR MIT	08/25/22	9.00	50.00	83.33	105.00
C1211-099		SH 121 NORTH SGA SIGNALS	08/25/22	18.00	50.00	60.00	54.00
ER0502-092		US 50 MP 204 EB MONARCH TRUCK	08/29/22	28.00	35.00	59.08	69.14
BR0343-046		US 34 TIMBER BRIDGE REPL. PKG	08/31/22	785.00	84.24	84.24	84.24
FBR0343-047		US 6/US 34 TIMBER BRIDGE REPL					
STAR100-374		5 STRUCTURES IN REGION 1	09/01/22	18.00	60.00	106.00	106.00
NHPPR100-266		R1 ESSENTIAL REPAIRS	09/01/22	52.00	55.00	86.83	79.50
PAN0761-245		ALONG I-76 & RAMPS MILEPOST 9	09/01/22	36.00	75.00	91.50	62.00
ER0253-297		WCR 34 BRIDGE OVER I-25(MM 24	09/14/22	16.00	60.00	80.79	33.00
2670403-065		US40 FLOYD HILL ROUNDABOUTS	09/15/22	223.00	60.00	137.93	278.00
2670703-497		I-70 GENESEE WILDLIFE XING	09/15/22	16.00	54.00	139.13	85.19
SHE2873-193		US 287 & CO 52 INTERSECTION I	09/15/22	50.00	45.00	60.59	58.30
NHPP0701-231		I-70 SALT WASH BRIDGES SCOUR	09/29/22	34.00	60.00	29.51	5.00
		WEIGHTED AVERAGE FOR THE THIRD QUARTER		1,525.00	72.17	90.48	106.33

PROJECT NUMBER	ITEM NUMBER/ PROJECT LOCATION	ITEM DESCRIPTION/ PROJECT LOCATION	DATE LET	UNIT/ QUANTITY	ENGR. EST.	AVERAGE BID	AWARDED BID
===== 630-80341		Const Traf Sign (A)		Each =====			
MTCE0253-281		MTCE FY23 I-25 CONC PANEL REP	10/06/22	22.00	180.00	67.06	110.00
NHPP0821-114		SH 82 ASPEN/INDEPENDENCE PASS	10/13/22	58.00	70.00	35.93	37.80
C0831-126		SH83 EL PASO COUNTY TO BAYOU	10/13/22	22.00	60.00	70.00	100.00
NHPP0701-253		I-70 EAST OF DEBEQUE	10/27/22	50.00	50.00	75.95	75.00
STA207A-004		Resurfacing SH207A MANZANOLA	10/27/22	20.00	80.00	61.10	68.30
NHPP0705-088		I-70 AGATE STRUCTURE REHAB	10/27/22	32.00	65.00	93.12	106.00
FSAM240-200		SH21B CO SPRINGS SIGNAL REPLA	10/27/22	22.00	60.00	64.75	65.00
C5502-111		US 550 MP 81 AND 89 RED MOUNT	10/27/22	22.00	60.00	70.00	68.00
C170A-002		CRITICAL CULVERT CONST. PKG D	10/27/22	8.00	150.00	151.42	146.67
TRG0253-264		I-25 AND SH 119 PARK-N-RIDE	10/27/22	35.00	55.00	372.99	625.00
STA3852-015		US 385 HOLYOKE NORTH	10/27/22	26.00	75.00	115.00	115.00
NHPP0343-048		US 34 (MP 169.3-171.4)	11/01/22	40.00	54.00	135.35	212.00
STU0252-457		I-25:ALAMEDA RIVER PH 2.0	11/03/22	126.00	65.00	98.21	99.00
SHE0242-087		US 24 SAFETY IMPRVMENTS, E OF	11/03/22	102.00	50.00	80.90	65.69
STR064A-010		SH 64 AND SH 13 AT MEEKER	11/10/22	20.00	50.00	87.25	90.00
NHPP0853-126		US85C: PLATTEVILLE NORTH MP (11/10/22	40.00	60.00	70.48	55.00
C5502-097		US550 MP 117.28-126.06	11/17/22	176.00	65.00	99.16	113.00
STRC090-011		US 50B AND SH71/CR18 INTERSEC	11/17/22	68.00	60.00	73.00	85.00
STAM420-001		US 285 AT HWY 9C IMPROVEMENTS	12/01/22	76.00	57.10	104.52	103.38
BR2854-148		INTERSECTION OF US 285 & SH 9					
STM0091-046		ADA RAMP IMPROVEMENTS - FAIRP					
STA0711-021		SH71: REGION LINE NORTH	12/01/22	40.00	52.00	77.33	50.00
STR114A-015		SH114 SILLSVILLE SOUTH TO MP3	12/01/22	66.00	60.00	80.00	50.00
2670703-487		I-70 BRIDGES OVER WARD ROAD-	12/01/22	152.00	60.00	96.28	100.00
NHPP0701-252		I-70 RIFLE TO SILT SLAB REPLA	12/01/22	88.00	60.00	75.00	50.00
IM025A-050		I25-MP103.9 - INTERSECTION DR	12/01/22	106.00	45.00	79.00	65.00
STR318A-001		SH 318 MP 0 - 12.5 MOFFAT COU	12/01/22	12.00	50.00	77.35	64.70
STR109A-019		M-22-AY BRIDGE REHAB ON SH109	12/01/22	8.00	55.00	77.75	104.50
NHPP0021-041		SH2 RESURFACING MLK TO 52ND	12/01/22	44.00	65.00	92.87	92.07
STR0641-107		SH 13 MM 104-128.1 IN MOFFAT	12/01/22	42.00	50.00	84.33	75.00
NHPP083A-046		SH83 RESURFACING STROH RD TO	12/08/22	52.00	65.00	62.05	63.09
NHPP0063-048		US6 / 20 ROAD INTERSECTION IM	12/15/22	29.00	45.00	71.84	60.00
NHM175-029		CANON CITY, CO	12/15/22	68.00	40.00	100.00	125.00
FSA0853-122		WCR14.5 AND US-85, FORT LUPTO	12/15/22	14.00	120.00	54.90	80.00
NHPP0931-033		SH93:US6 TO 58TH RESURFACING	12/15/22	184.00	55.00	68.59	56.40
NHPP0502-090		SH 50 MP 134.6-136 GUNNISON C	12/22/22	79.00	50.00	91.52	113.81
STR0092-024		SH 9 North of Silverthorne	12/22/22	40.00	50.00	93.55	97.10
STA0361-129		US 36: HYGIENE RD AND NELSON	12/22/22	24.00	50.00	89.49	93.33
BR012A-048		CO 12 STRUCTURE P-17-F AT MP	12/22/22	31.00	50.00	70.34	90.00
STA385A-016		SH 385 MP 97.76	12/22/22	8.00	35.00	69.61	44.44
STR096A-050		SH 96 MP 168.99 TO 193.77	12/22/22	50.00	54.00	101.67	50.00
		WEIGHTED AVERAGE FOR THE FOURTH QUARTER		2,102.00	59.01	95.70	92.53
		WEIGHTED AVERAGE FOR THE YEAR		6,451.00	62.23	85.51	84.70

PROJECT NUMBER	ITEM NUMBER/ PROJECT LOCATION	ITEM DESCRIPTION/ PROJECT LOCATION	DATE LET	UNIT/ QUANTITY	ENGR. EST.	AVERAGE BID	AWARDED BID
===== 630-80342		Const Traf Sign (B)		Each =====			
ITS0703-477		ITS EQUIPMENT UPGRADE AT EJMT	01/06/22	84.00	70.00	55.00	55.00
MTCE R500-218			01/06/22	18.00	40.00	33.40	20.00
NHPP2873-189		US 287 (FEDERAL BLVD) - COLFA	01/06/22	66.00	66.00	70.26	68.21
STR0505-050			01/13/22	54.00	50.00	81.33	100.00
NH0504-910		US50B L-24-B MIN REP AT MP 40	01/13/22	5.00	100.00	77.55	66.67
MTCE400-391		VARIOUS HIGHWAY SEGMENTS ACRO	01/13/22	40.00	20.00	21.25	5.00
NHPP0702-383		I-70 EB AUX FRISCO TO SILVERT	01/13/22	61.00	80.00	84.83	54.00
MTCE300-262			02/03/22	78.00	40.00	76.67	50.00
NHPP1601-083			02/03/22	93.00	50.00	78.67	40.00
STA0252-459			02/03/22	102.00	90.17	108.19	51.25
C0762-055			02/17/22	154.00	85.00	379.10	69.00
STR0141-031			02/17/22	16.00	70.00	71.67	85.00
STR133A-051			02/17/22	100.00	60.00	67.33	78.00
NHPP0063-063			02/24/22	28.00	75.00	93.85	98.00
STA 067A-048		Hwy 67A MP 0.00 TO MP 11.05 I	03/03/22	32.00	65.00	45.22	46.00
NHPP 0761-238		I-76 DAHLIA TO YORK	03/10/22	145.00	70.00	96.31	110.00
C0761-239							
NHPP0703-472			03/10/22	58.00	70.00	67.00	70.00
CR100-362			03/14/22	33.00	69.55	69.55	69.55
BRC040-057			03/17/22	84.00	75.00	58.00	40.00
STR R500-171		Various locations on SH 141 a	03/17/22	48.00	61.00	39.26	5.00
M R100-351		FY22 R1 SIGN STRUCTURE REPLAC	03/17/22	27.00	71.00	138.00	77.00
STR092A-031			03/17/22	161.00	80.00	65.25	65.25
MP0503-098			03/24/22	30.00	60.00	71.00	72.00
NHM765-007			03/31/22	35.00	150.00	160.00	210.90
C0703-499		EJMT GROUT BED REPAIR AND PAN	03/31/22	21.00	90.00	104.00	113.00
		WEIGHTED AVERAGE FOR THE FIRST QUARTER		1,573.00	70.35	115.03	67.36
NH0504-911			04/07/22	108.00	75.00	94.85	59.70
CC030-081		ADA RAMP AND CURBS - FT. LUPT	04/14/22	4.00	70.00	55.77	10.00
NHPP0702-413		VAIL PASS AUX PHASE 1 CAP 2	04/18/22	67.00	85.60	85.60	85.60
STM1151-038		SH115 MP 27 TO MP 38	04/21/22	40.00	70.00	107.09	100.00
MTCE2873-204		MTCE FY22 SH287 CONC PANEL RE	05/05/22	52.00	75.00	194.49	83.98
2670703-479		I-70 BRIDGE OVER HARLAN	05/05/22	55.00	70.00	129.03	105.83
ER0702-420		PR I-70 GWC MATERIAL FLOWS 20	05/06/22	80.00	40.00	170.00	165.00
STA0712-019		SH 71: Frieght Improvements	05/12/22	114.00	80.00	72.45	72.45
STA001A-005		SH1 WELLINGTON SOUTH RESURFAC	05/12/22	24.00	84.00	178.00	55.00
NHC540-017		R2 CHAINUP STA @ KENOSHA/HOOS	05/12/22	34.00	74.00	63.00	64.00
CM760-047		COLFAX AND QUAIL	05/12/22	32.00	92.00	54.40	63.00
NHPP 3851-018		US 385 NORTH OF CHEYENNE WELL	05/26/22	56.00	90.00	302.50	55.00
STAR100-358		3 STRUCTURES IN REGION 1 METR	05/26/22	47.00	100.00	80.25	95.00
C0852-120		Rehabilitation of Culvert by	05/26/22	4.00	100.00	75.00	75.00

PROJECT NUMBER	ITEM NUMBER/ PROJECT LOCATION	ITEM DESCRIPTION/ PROJECT LOCATION	DATE LET	UNIT/ QUANTITY	ENGR. EST.	AVERAGE BID	AWARDED BID
=====	630-80342	Const Traf Sign (B)		Each =====			
FSA0702-409		I-70 VAIL WILDLIFE FENCE PHAS	05/26/22	64.00	60.00	100.00	100.00
ITS 0741-024		VMS SIGN INSTALLATIONS AND VS	06/02/22	38.00	60.00	212.50	72.00
FSA3921-019		SH 392 AND WCR 55 ISLANDS	06/02/22	20.00	65.00	64.33	68.00
NHPP072A-047		SH-72 RESURFACING: I-70 TO IN	06/09/22	102.00	70.00	65.86	65.86
FSA052A-046		SH52 WCR 37 INTERSECTION IMPR	06/09/22	28.00	70.00	200.45	305.00
MPR200-278		R2 - VARIOUS LOCATIONS	06/09/22	28.00	15.00	13.33	5.00
MPR200-279		FY 23 STENCIL MARKING PROJECT	06/09/22	48.00	15.00	18.33	5.00
MTCE0253-291		I-25 SIGN REPLACEMENT PHASE 2	06/16/22	34.00	70.00	216.08	88.16
NHPP0252-448		I-25 TREX NARROWS BRIDGE PREV	06/23/22	42.00	100.00	61.25	70.00
		WEIGHTED AVERAGE FOR THE SECOND QUARTER		1,121.00	70.33	114.23	83.23
MTCE 072A-045		SH 72B MP 37.00 TO MP 45.3 NE	07/07/22	53.00	70.00	25.00	25.00
MTCE0702-426		I70 FROM MP 155 TO 180 AND MP	07/07/22	48.00	10.00	21.25	50.00
MTCER300-272		REGION 3 ROUNDABOUT STRIPING	07/07/22	18.00	50.00	50.00	50.00
NHPP0702-414		VAIL PASS AUX PHASE 1 CAP 3	07/08/22	43.00	137.33	137.33	137.33
FBR0702-423		VAIL PASS AUX BE F-12-AT PHAS					
FSA052A-057		SH52 BOX CULVERT EXTENSION (M	08/04/22	20.00	85.00	74.77	71.50
STR0711-022		SH 71 OVER THE ARKANSAS	08/04/22	20.00	80.00	84.67	79.00
NHPP0063-054		US 6 FROM I70-B TO 33 RD. (MP	08/18/22	30.00	60.00	75.90	100.00
FBR0761-236		I-76 OVER CLR CRK SCOUR MIT	08/25/22	11.00	70.00	91.67	105.00
CL211-099		SH 121 NORTH SGA SIGNALS	08/25/22	16.00	60.00	65.50	54.00
ER0502-092		US 50 MP 204 EB MONARCH TRUCK	08/29/22	8.00	50.00	68.41	74.90
BR0343-046		US 34 TIMBER BRIDGE REPL. PKG	08/31/22	49.00	195.30	195.30	195.30
FBR0343-047		US 6/US 34 TIMBER BRIDGE REPL					
STAR100-374		5 STRUCTURES IN REGION 1	09/01/22	47.00	100.00	106.00	106.00
NHPPR100-266		R1 ESSENTIAL REPAIRS	09/01/22	30.00	60.00	95.67	106.00
PAN0761-245		ALONG I-76 & RAMPS MILEPOST 9	09/01/22	48.00	90.00	128.00	135.00
ER0253-297		WCR 34 BRIDGE OVER I-25(MM 24	09/14/22	37.00	70.00	204.51	77.00
2670403-065		US40 FLOYD HILL ROUNDABOUTS	09/15/22	135.00	70.00	153.29	278.00
2670703-497		I-70 GENESEE WILDLIFE KING	09/15/22	14.00	78.00	164.50	119.27
SHE2873-193		US 287 & CO 52 INTERSECTION I	09/15/22	20.00	55.00	80.75	79.50
NHPP0701-231		I-70 SALT WASH BRIDGES SCOUR	09/29/22	76.00	65.00	34.92	5.00
		WEIGHTED AVERAGE FOR THE THIRD QUARTER		723.00	79.93	106.72	120.87
MTCE0253-281		MTCE FY23 I-25 CONC PANEL REP	10/06/22	42.00	100.00	108.75	134.00
NHPP0821-114		SH 82 ASPEN/INDEPENDENCE PASS	10/13/22	8.00	100.00	42.60	37.80
C0831-126		SH83 EL PASO COUNTY TO BAYOU	10/13/22	52.00	65.00	85.00	120.00
NHPP0701-253		I-70 EAST OF DEBEQUE	10/27/22	152.00	60.00	96.20	95.00
STA207A-004		Resurfacing SH207A MANZANOLA	10/27/22	120.00	70.00	83.10	99.30
NHPP0705-088		I-70 AGATE STRUCTURE REHAB	10/27/22	175.00	78.00	106.48	130.00

PROJECT NUMBER	ITEM NUMBER/ PROJECT LOCATION	ITEM DESCRIPTION/ PROJECT LOCATION	DATE LET	UNIT/ QUANTITY	ENGR. EST.	AVERAGE BID	AWARDED BID
=====	630-80342	Const Traf Sign (B)		Each =====			
FSAM240-200		SH21B CO SPRINGS SIGNAL REPLA	10/27/22	40.00	70.00	74.75	72.00
C5502-111		US 550 MP 81 AND 89 RED MOUNT	10/27/22	8.00	70.00	91.50	87.00
C170A-002		CRITICAL CULVERT CONST. PKG D	10/27/22	27.00	95.00	214.36	224.45
TRG0253-264		I-25 AND SH 119 PARK-N-RIDE	10/27/22	28.00	87.00	381.72	630.00
STA3852-015		US 385 HOLYOKE NORTH	10/27/22	78.00	95.00	125.00	125.00
NHPP0343-048		US 34 (MP 169.3-171.4)	11/01/22	1.00	78.00	1246.49	4590.00
STU0252-457		I-25:ALAMEDA RIVER PH 2.0	11/03/22	47.00	75.00	117.78	120.00
SHE0242-087		US 24 SAFETY IMPRVMENTS, E OF	11/03/22	14.00	80.00	82.19	89.57
STR064A-010		SH 64 AND SH 13 AT MEEKER	11/10/22	98.00	60.00	89.85	90.00
NHPP0853-126		US85C: PLATTEVILLE NORTH MP (11/10/22	122.00	80.00	105.08	55.00
C5502-097		US550 MP 117.28-126.06	11/17/22	27.00	80.00	120.44	119.00
MPR200-280		PUEBLO AREA	11/17/22	25.00	62.00	70.00	65.00
STRC090-011		US 50B AND SH71/CR18 INTERSEC	11/17/22	46.00	70.00	91.50	95.00
STAM420-001		US 285 AT HWY 9C IMPROVEMENTS	12/01/22	25.00	83.10	134.13	120.61
BR2854-148		INTERSECTION OF US 285 & SH 9					
STM0091-046		ADA RAMP IMPROVEMENTS - FAIRP					
STA0711-021		SH71: REGION LINE NORTH	12/01/22	99.00	77.00	87.67	60.00
STR114A-015		SH114 SILLSVILLE SOUTH TO MP3	12/01/22	111.00	70.00	87.50	55.00
2670703-487		I-70 BRIDGES OVER WARD ROAD-	12/01/22	76.00	100.00	121.32	130.00
NHPP0701-252		I-70 RIFLE TO SILT SLAB REPLA	12/01/22	117.00	80.00	82.50	50.00
IM025A-050		I25-MP103.9 - INTERSECTION DR	12/01/22	58.00	80.00	92.67	85.00
STR318A-001		SH 318 MP 0 - 12.5 MOFFAT COU	12/01/22	70.00	60.00	114.50	129.00
STR109A-019		M-22-AY BRIDGE REHAB ON SH109	12/01/22	26.00	65.00	103.32	130.63
NHPP0021-041		SH2 RESURFACING MLK TO 52ND	12/01/22	64.00	75.00	119.79	107.42
STR0641-107		SH 13 MM 104-128.1 IN MOFFAT	12/01/22	105.00	50.00	96.33	85.00
NHPP083A-046		SH83 RESURFACING STROH RD TO	12/08/22	106.00	85.00	43.77	44.54
NHPP0063-048		US6 / 20 ROAD INTERSECTION IM	12/15/22	61.00	60.00	81.32	70.00
NHM175-029		CANON CITY, CO	12/15/22	54.00	50.00	175.00	250.00
FSA0853-122		WCRI4.5 AND US-85, FORT LUPTO	12/15/22	46.00	90.00	86.90	120.00
NHPP0931-033		SH93:US6 TO 58TH RESURFACING	12/15/22	103.00	70.00	100.40	66.65
NHPP0502-090		SH 50 MP 134.6-136 GUNNISON C	12/22/22	21.00	75.00	114.06	128.04
STR0092-024		SH 9 North of Silverthorne	12/22/22	126.00	60.00	98.50	102.00
STA0361-129		US 36: HYGIENE RD AND NELSON	12/22/22	41.00	90.00	139.60	108.89
BR012A-048		CO 12 STRUCTURE P-17-F AT MP	12/22/22	4.00	65.00	75.34	100.00
STA385A-016		SH 385 MP 97.76	12/22/22	62.00	40.00	93.70	77.78
STR096A-050		SH 96 MP 168.99 TO 193.77	12/22/22	10.00	78.00	116.67	55.00
		WEIGHTED AVERAGE FOR THE FOURTH QUARTER		2,495.00	72.42	109.88	104.91
		WEIGHTED AVERAGE FOR THE YEAR		5,912.00	72.39	111.67	93.32
=====	630-80343	Const Traf Sign (C)		Each =====			
ITS0703-477		ITS EQUIPMENT UPGRADE AT EJMT	01/06/22	8.00	90.00	65.00	65.00
NHPP2873-189		US 287 (FEDERAL BLVD) - COLFA	01/06/22	8.00	86.00	78.56	80.61
NHPP0702-383		I-70 EB AUX FRISCO TO SILVERT	01/13/22	2.00	80.00	90.91	60.00

COLORADO DEPARTMENT OF TRANSPORTATION
ITEM UNIT COSTS BY PROJECTS -- 2022 COST DATA

11:31 Wednesday, March 8, 2023 591

PROJECT NUMBER	ITEM NUMBER/ PROJECT LOCATION	ITEM DESCRIPTION/ PROJECT LOCATION	DATE LET	UNIT/ QUANTITY	ENGR. EST.	AVERAGE BID	AWARDED BID
=====	630-80343	Const Traf Sign (C)		Each =====			
MTCER300-262			02/03/22	8.00	50.00	86.67	60.00
STA0252-459			02/03/22	20.00	88.00	81.17	56.50
STR0141-031			02/17/22	24.00	80.00	77.33	92.00
NHPP 0761-238		I-76 DAHLIA TO YORK	03/10/22	72.00	90.00	103.19	110.00
C0761-239							
NHPP0703-472			03/10/22	14.00	90.00	78.45	80.00
BRC040-057			03/17/22	20.00	90.00	82.75	65.00
M R100-351		FY22 R1 SIGN STRUCTURE REPLAC	03/17/22	14.00	100.00	159.00	90.00
MP0503-098			03/24/22	8.00	80.00	373.00	664.00
C0703-499		EJMT GROUT BED REPAIR AND PAN	03/31/22	24.00	100.00	144.50	157.00
WEIGHTED AVERAGE FOR THE FIRST QUARTER				222.00	88.41	103.23	116.14
NH0504-911			04/07/22	20.00	90.00	67.85	65.70
NHPP0702-413		VAIL PASS AUX PHASE 1 CAP 2	04/18/22	60.00	32.10	32.10	32.10
MTCE2873-204		MTCE FY22 SH287 CONC PANEL RE	05/05/22	16.00	80.00	225.70	96.40
2670703-479		I-70 BRIDGE OVER HARLAN	05/05/22	4.00	95.00	182.80	127.73
NHC540-017		R2 CHAINUP STA @ KENOSHA/HOOS	05/12/22	8.00	84.00	70.00	70.00
STAR100-358		3 STRUCTURES IN REGION 1 METR	05/26/22	12.00	200.00	105.00	132.00
FSA0702-409		I-70 VAIL WILDLIFE FENCE PHAS	05/26/22	16.00	75.00	120.00	120.00
FSA052A-046		SH52 WCR 37 INTERSECTION IMPR	06/09/22	14.00	80.00	233.85	310.00
MPR200-278		R2 - VARIOUS LOCATIONS	06/09/22	8.00	15.00	21.67	5.00
MPR200-279		FY 23 STENCIL MARKING PROJECT	06/09/22	24.00	15.00	18.33	5.00
NHPP0252-448		I-25 TREX NARROWS BRIDGE PREV	06/23/22	10.00	200.00	61.25	70.00
WEIGHTED AVERAGE FOR THE SECOND QUARTER				192.00	69.05	101.12	75.82
MTCE0702-426		I70 FROM MP 155 TO 180 AND MP	07/07/22	8.00	10.00	21.25	50.00
NHPP0702-414		VAIL PASS AUX PHASE 1 CAP 3	07/08/22	32.00	164.79	164.79	164.79
FBR0702-423		VAIL PASS AUX BE F-12-AT PHAS					
STR0711-022		SH 71 OVER THE ARKANSAS	08/04/22	8.00	100.00	102.33	92.00
NHPP0063-054		US 6 FROM I70-B TO 33 RD. (MP	08/18/22	4.00	90.00	100.90	150.00
FBR0761-236		I-76 OVER CLR CRK SCOUR MIT	08/25/22	2.00	90.00	125.00	105.00
STAR100-374		5 STRUCTURES IN REGION 1	09/01/22	12.00	135.00	106.00	106.00
NHPPR100-266		R1 ESSENTIAL REPAIRS	09/01/22	4.00	65.00	119.50	132.50
ER0253-297		WCR 34 BRIDGE OVER I-25(MM 24	09/14/22	9.00	90.00	174.71	79.00
2670703-497		I-70 GENESEE WILDLIFE XING	09/15/22	10.00	110.00	194.05	141.99
SHE2873-193		US 287 & CO 52 INTERSECTION I	09/15/22	8.00	65.00	113.79	106.00
WEIGHTED AVERAGE FOR THE THIRD QUARTER				97.00	113.44	135.74	123.71
MTCE0253-281		MTCE FY23 I-25 CONC PANEL REP	10/06/22	22.00	120.00	123.09	145.00

PROJECT NUMBER	ITEM NUMBER/ PROJECT LOCATION	ITEM DESCRIPTION/ PROJECT LOCATION	DATE LET	UNIT/ QUANTITY	ENGR. EST.	AVERAGE BID	AWARDED BID
===== 630-80343							
		Const Traf Sign (C)		Each			
C0831-126		SH83 EL PASO COUNTY TO BAYOU	10/13/22	12.00	90.00	95.00	130.00
NHPP0705-088		I-70 AGATE STRUCTURE REHAB	10/27/22	32.00	110.00	135.83	136.00
FSAM240-200		SH21B CO SPRINGS SIGNAL REPLA	10/27/22	16.00	80.00	87.50	82.00
C170A-002		CRITICAL CULVERT CONST. PKG D	10/27/22	4.00	100.00	261.47	248.89
TRG0253-264		I-25 AND SH 119 PARK-N-RIDE	10/27/22	5.00	105.00	381.25	635.00
STU0252-457		I-25:ALAMEDA RIVER PH 2.0	11/03/22	4.00	90.00	127.60	127.00
STR064A-010		SH 64 AND SH 13 AT MEEKER	11/10/22	16.00	70.00	92.50	90.00
NHPP0853-126		US85C: PLATTEVILLE NORTH MP (11/10/22	18.00	90.00	115.84	66.00
MPR200-280		PUEBLO AREA	11/17/22	25.00	62.00	72.50	65.00
STRC090-011		US 50B AND SH71/CR18 INTERSEC	11/17/22	21.00	100.00	118.00	120.00
STA0711-021		SH71: REGION LINE NORTH	12/01/22	16.00	100.00	96.00	65.00
2670703-487		I-70 BRIDGES OVER WARD ROAD-	12/01/22	37.00	150.00	129.84	140.00
NHPP0701-252		I-70 RIFLE TO SILT SLAB REPLA	12/01/22	20.00	90.00	90.00	50.00
IM025A-050		I25-MP103.9 - INTERSECTION DR	12/01/22	4.00	110.00	118.33	100.00
STR318A-001		SH 318 MP 0 - 12.5 MOFFAT COU	12/01/22	12.00	70.00	146.50	173.00
STR109A-019		M-22-AY BRIDGE REHAB ON SH109	12/01/22	5.00	75.00	133.54	141.08
NHPP0021-041		SH2 RESURFACING MLK TO 52ND	12/01/22	8.00	120.00	146.75	184.15
STR0641-107		SH 13 MM 104-128.1 IN MOFFAT	12/01/22	16.00	60.00	117.00	95.00
NHPP083A-046		SH83 RESURFACING STROH RD TO	12/08/22	20.00	100.00	56.77	57.54
NHPP0063-048		US6 / 20 ROAD INTERSECTION IM	12/15/22	10.00	75.00	90.79	80.00
		WEIGHTED AVERAGE FOR THE FOURTH QUARTER		323.00	97.43	125.53	115.39
		WEIGHTED AVERAGE FOR THE YEAR		834.00	90.36	114.84	107.56
===== 630-80344							
		Const Traf Sign (Spec)		Sq Foot			
NHPP2873-189		US 287 (FEDERAL BLVD) - COLFA	01/06/22	50.00	30.00	38.72	49.61
C0762-055			02/17/22	518.00	31.00	50.97	115.00
STR0141-031			02/17/22	96.00	35.00	28.67	31.00
STR133A-051			02/17/22	292.00	25.00	26.00	28.00
NHPP 0761-238		I-76 DAHLIA TO YORK	03/10/22	520.00	30.00	46.34	28.00
C0761-239							
STR R500-171		Various locations on SH 141 a	03/17/22	98.00	19.00	21.72	30.00
STR092A-031			03/17/22	160.00	50.00	32.50	32.50
NHM765-007			03/31/22	160.00	25.00	44.51	21.66
		WEIGHTED AVERAGE FOR THE FIRST QUARTER		1,894.00	30.45	43.39	52.46
NH0504-911			04/07/22	128.00	20.00	22.35	22.70
2670703-479		I-70 BRIDGE OVER HARLAN	05/05/22	40.00	28.00	32.22	36.49
STA0712-019		SH 71: Frieght Improvements	05/12/22	380.00	28.00	87.98	87.98
NHPP 3851-018		US 385 NORTH OF CHEYENNE WELL	05/26/22	140.00	35.00	67.00	24.00

PROJECT NUMBER	ITEM NUMBER/ PROJECT LOCATION	ITEM DESCRIPTION/ PROJECT LOCATION	DATE LET	UNIT/ QUANTITY	ENGR. EST.	AVERAGE BID	AWARDED BID
===== 630-80344							
		Const Traf Sign (Spec)		Sq Foot			
FSA0702-409		I-70 VAIL WILDLIFE FENCE PHAS	05/26/22	96.00	35.00	30.00	30.00
NHPP072A-047		SH-72 RESURFACING: I-70 TO IN	06/09/22	55.00	35.00	47.90	47.90
FSA052A-046		SH52 WCR 37 INTERSECTION IMPR	06/09/22	100.00	20.00	52.75	32.00
WEIGHTED AVERAGE FOR THE SECOND QUARTER				939.00	28.23	53.98	53.11
FSA052A-057		SH52 BOX CULVERT EXTENSION (M	08/04/22	238.00	26.00	41.87	45.50
NHPP0063-054		US 6 FROM I70-B TO 33 RD. (MP	08/18/22	600.00	23.00	29.36	38.00
ER0502-092		US 50 MP 204 EB MONARCH TRUCK	08/29/22	27.00	50.00	54.02	57.62
ER0253-297		WCR 34 BRIDGE OVER I-25(MM 24	09/14/22	20.00	40.00	26.27	15.00
NHPP0701-231		I-70 SALT WASH BRIDGES SCOUR	09/29/22	80.00	30.00	35.81	50.00
WEIGHTED AVERAGE FOR THE THIRD QUARTER				965.00	25.43	34.60	40.92
NHPP0705-088		I-70 AGATE STRUCTURE REHAB	10/27/22	262.00	50.00	47.17	53.00
STR064A-010		SH 64 AND SH 13 AT MEEKER	11/10/22	480.00	40.00	28.85	26.00
NHPP0853-126		US85C: PLATTEVILLE NORTH MP (11/10/22	192.00	29.72	57.94	66.00
C5502-097		US550 MP 117.28-126.06	11/17/22	120.00	80.00	38.46	32.40
STRC090-011		US 50B AND SH71/CR18 INTERSEC	11/17/22	50.00	30.00	40.50	32.00
STA0711-021		SH71: REGION LINE NORTH	12/01/22	580.00	25.00	28.67	25.00
2670703-487		I-70 BRIDGES OVER WARD ROAD-	12/01/22	672.00	30.00	36.02	40.00
STR0641-107		SH 13 MM 104-128.1 IN MOFFAT	12/01/22	209.00	25.00	34.67	30.00
NHPP0063-048		US6 / 20 ROAD INTERSECTION IM	12/15/22	21.00	55.00	35.92	30.00
STA385A-016		SH 385 MP 97.76	12/22/22	64.00	20.00	44.58	33.33
STR096A-050		SH 96 MP 168.99 TO 193.77	12/22/22	64.00	26.00	23.00	26.00
WEIGHTED AVERAGE FOR THE FOURTH QUARTER				2,714.00	34.30	36.96	35.54
WEIGHTED AVERAGE FOR THE YEAR				6,512.00	30.99	40.39	43.44
===== 630-80348							
		Const Info Sign		Each			
STR160A-034		US160A LA VETA PASS EAST SURF	03/17/22	6.00	300.00	233.15	66.30
M R100-351		FY22 R1 SIGN STRUCTURE REPLAC	03/17/22	2.00	11350.00	517.50	696.00
WEIGHTED AVERAGE FOR THE FIRST QUARTER				8.00	3062.50	304.24	223.73
STR0092-024		SH 9 North of Silverthorne	12/22/22	4.00	200.00	519.50	539.00
WEIGHTED AVERAGE FOR THE FOURTH QUARTER				4.00	200.00	519.50	539.00
WEIGHTED AVERAGE FOR THE YEAR				12.00	2108.33	375.99	328.82

PROJECT NUMBER	ITEM NUMBER/ PROJECT LOCATION	ITEM DESCRIPTION/ PROJECT LOCATION	DATE LET	UNIT/ QUANTITY	ENGR. EST.	AVERAGE BID	AWARDED BID
=====	630-80350	Vert Panel		Each =====			
ITS0703-477		ITS EQUIPMENT UPGRADE AT EJMT	01/06/22	30.00	25.00	28.00	28.00
MTCE R500-218			01/06/22	40.00	30.00	25.00	20.00
NHPP2873-189		US 287 (FEDERAL BLVD) - COLFA	01/06/22	50.00	36.00	35.00	37.21
NHPP0702-383		I-70 EB AUX FRISCO TO SILVERT	01/13/22	4.00	80.00	26.58	40.00
MTCER300-262			02/03/22	26.00	10.00	38.33	15.00
NHPP1601-083			02/03/22	100.00	35.00	66.50	50.00
STA0252-459			02/03/22	100.00	40.00	34.78	25.65
C0762-055			02/17/22	40.00	32.00	55.72	90.00
STR R500-171		Various locations on SH 141 a	03/17/22	75.00	23.00	34.31	60.00
M R100-351		FY22 R1 SIGN STRUCTURE REPLAC	03/17/22	50.00	30.00	25.00	35.00
MP0503-098			03/24/22	40.00	30.00	49.00	28.00
WEIGHTED AVERAGE FOR THE FIRST QUARTER				555.00	31.59	40.84	40.69
NH0504-911			04/07/22	40.00	30.00	35.40	35.80
CC030-081		ADA RAMP AND CURBS - FT. LUPT	04/14/22	30.00	50.00	57.44	60.00
STM1151-038		SH115 MP 27 TO MP 38	04/21/22	200.00	29.00	48.69	45.00
2670703-479		I-70 BRIDGE OVER HARLAN	05/05/22	50.00	35.00	52.76	54.74
CM760-047		COLFAX AND QUAIL	05/12/22	30.00	33.00	41.20	38.00
NHPP 3851-018		US 385 NORTH OF CHEYENNE WELL	05/26/22	25.00	40.00	80.00	50.00
FSA052A-046		SH52 WCR 37 INTERSECTION IMPR	06/09/22	25.00	30.00	60.65	21.00
WEIGHTED AVERAGE FOR THE SECOND QUARTER				400.00	32.48	50.30	44.71
MTCE0702-426		I70 FROM MP 155 TO 180 AND MP	07/07/22	50.00	10.00	13.75	25.00
FSA052A-057		SH52 BOX CULVERT EXTENSION (M	08/04/22	100.00	35.00	24.07	26.00
STR0711-022		SH 71 OVER THE ARKANSAS	08/04/22	150.00	38.00	56.67	75.00
ER0253-297		WCR 34 BRIDGE OVER I-25(MM 24	09/14/22	200.00	32.00	46.29	5.00
2670403-065		US40 FLOYD HILL ROUNDABOUTS	09/15/22	11.00	35.00	69.26	72.00
SHE2873-193		US 287 & CO 52 INTERSECTION I	09/15/22	100.00	35.00	63.53	58.30
WEIGHTED AVERAGE FOR THE THIRD QUARTER				611.00	32.71	47.38	37.19
NHPP0701-253		I-70 EAST OF DEBEQUE	10/27/22	180.00	50.00	20.25	20.00
TRG0253-264		I-25 AND SH 119 PARK-N-RIDE	10/27/22	100.00	32.00	91.37	120.00
STU0252-457		I-25:ALAMEDA RIVER PH 2.0	11/03/22	50.00	60.00	46.85	55.00
SHE0242-087		US 24 SAFETY IMPRVMENTS, E OF	11/03/22	10.00	40.00	50.90	65.69

PROJECT NUMBER	ITEM NUMBER/ PROJECT LOCATION	ITEM DESCRIPTION/ PROJECT LOCATION	DATE LET	UNIT/ QUANTITY	ENGR. EST.	AVERAGE BID	AWARDED BID
===== 630-80350 Vert Panel Each =====							
MPR200-280		PUEBLO AREA	11/17/22	30.00	30.00	45.00	65.00
STA0711-021		SH71: REGION LINE NORTH	12/01/22	18.00	30.00	37.00	60.00
NHPP0701-252		I-70 RIFLE TO SILT SLAB REPLA	12/01/22	150.00	50.00	29.50	25.00
IM025A-050		I25-MP103.9 - INTERSECTION DR	12/01/22	100.00	35.00	51.67	50.00
NHPP0021-041		SH2 RESURFACING MLK TO 52ND	12/01/22	50.00	40.00	47.98	24.55
NHM175-029		CANON CITY, CO	12/15/22	32.00	35.00	40.00	50.00
FSA0853-122		WCRI4.5 AND US-85, FORT LUPTO	12/15/22	40.00	40.00	8.98	10.00
STA385A-016		SH 385 MP 97.76	12/22/22	30.00	30.00	27.06	22.22
		WEIGHTED AVERAGE FOR THE FOURTH QUARTER		790.00	42.61	52.57	43.90
		WEIGHTED AVERAGE FOR THE YEAR		2,356.00	35.73	48.46	41.54
===== 630-80351 Vert Panel (Plastic) Each =====							
ITS 0741-024		VMS SIGN INSTALLATIONS AND VS	06/02/22	100.00	30.00	59.50	61.00
		WEIGHTED AVERAGE FOR THE SECOND QUARTER		100.00	30.00	59.50	61.00
		WEIGHTED AVERAGE FOR THE YEAR		100.00	30.00	59.50	61.00
===== 630-80354 Vert Panel (Light) (SB) Each =====							
NHPP 0761-238 C0761-239		I-76 DAHLIA TO YORK	03/10/22	250.00	40.00	55.22	55.00
		WEIGHTED AVERAGE FOR THE FIRST QUARTER		250.00	40.00	55.22	55.00
		WEIGHTED AVERAGE FOR THE YEAR		250.00	40.00	55.22	55.00
===== 630-80355 Port Mesg Panel Each =====							
ITS0703-477		ITS EQUIPMENT UPGRADE AT EJMT	01/06/22	2.00	6000.00	5885.00	5885.00
MTCE R500-218			01/06/22	4.00	4000.00	812.50	250.00
NHPP2873-189		US 287 (FEDERAL BLVD) - COLFA	01/06/22	2.00	5400.00	7211.86	6945.24
NH0504-910		US50B L-24-B MIN REP AT MP 40	01/13/22	2.00	10000.00	8472.64	11111.11
MTCER400-391		VARIOUS HIGHWAY SEGMENTS ACRO	01/13/22	2.00	6000.00	5125.00	500.00
NHPP0702-383		I-70 EB AUX FRISCO TO SILVERT	01/13/22	8.00	5000.00	11659.99	6200.00
NHPP1601-083			02/03/22	3.00	4000.00	13521.96	18000.00
STA0252-459			02/03/22	2.00	5500.00	6361.67	5400.00
C0762-055			02/17/22	4.00	5000.00	7817.35	8500.00
STR0141-031			02/17/22	4.00	8000.00	12500.00	13000.00

PROJECT NUMBER	ITEM NUMBER/ PROJECT LOCATION	ITEM DESCRIPTION/ PROJECT LOCATION	DATE LET	UNIT/ QUANTITY	ENGR. EST.	AVERAGE BID	AWARDED BID
=====	630-80355	Port Mesg Panel		Each =====			
STR133A-051			02/17/22	3.00	5000.00	3866.67	4500.00
NHPP0063-063			02/24/22	2.00	5500.00	7180.00	7500.00
STA 067A-048		Hwy 67A MP 0.00 TO MP 11.05 I	03/03/22	4.00	6500.00	6359.01	9000.00
NHPP 0761-238		I-76 DAHLIA TO YORK	03/10/22	9.00	5500.00	11493.56	11000.00
C0761-239							
NHPP0703-472			03/10/22	8.00	5500.00	3846.96	2490.00
CR100-362			03/14/22	6.00	5885.00	5885.00	5885.00
STR160A-034		US160A LA VETA PASS EAST SURF	03/17/22	3.00	4000.00	9649.04	6298.08
BRC040-057			03/17/22	6.00	6250.00	4362.25	3500.00
STR R500-171		Various locations on SH 141 a	03/17/22	6.00	5863.00	6492.30	8500.00
M R100-351		FY22 R1 SIGN STRUCTURE REPLAC	03/17/22	2.00	8000.00	5064.00	7796.00
STR092A-031			03/17/22	4.00	7000.00	655.00	655.00
NHM765-007			03/31/22	3.00	15000.00	13873.09	18240.00
C0703-499		EJMT GROUT BED REPAIR AND PAN	03/31/22	2.00	6000.00	19800.00	20000.00
		WEIGHTED AVERAGE FOR THE FIRST QUARTER		91.00	6069.10	8421.68	7393.83
NH0504-911			04/07/22	12.00	4000.00	5975.00	5950.00
CC030-081		ADA RAMP AND CURBS - FT. LUPT	04/14/22	2.00	7500.00	9755.14	10000.00
STM1151-038		SH115 MP 27 TO MP 38	04/21/22	6.00	6500.00	9192.28	8500.00
MTCE2873-204		MTCE FY22 SH287 CONC PANEL RE	05/05/22	2.00	7500.00	4589.20	5623.39
2670703-479		I-70 BRIDGE OVER HARLAN	05/05/22	8.00	6000.00	18959.94	19000.00
STA0712-019		SH 71: Frieght Improvements	05/12/22	7.00	6000.00	5434.02	5434.02
STA001A-005		SH1 WELLINGTON SOUTH RESURFAC	05/12/22	2.00	6500.00	4852.50	6000.00
NHC540-017		R2 CHAINUP STA @ KENOSHA/HOOS	05/12/22	4.00	6045.00	13500.00	10500.00
CM760-047		COLFAX AND QUAIL	05/12/22	4.00	5300.00	3055.00	2500.00
NHPP 3851-018		US 385 NORTH OF CHEYENNE WELL	05/26/22	2.00	6600.00	7250.00	9000.00
STAR100-358		3 STRUCTURES IN REGION 1 METR	05/26/22	2.00	7500.00	5976.49	7950.00
C0852-120		Rehabilitation of Culvert by	05/26/22	1.00	7500.00	9900.00	9900.00
FSA0702-409		I-70 VAIL WILDLIFE FENCE PHAS	05/26/22	4.00	11000.00	15000.00	15000.00
ITS 0741-024		VMS SIGN INSTALLATIONS AND VS	06/02/22	2.00	2500.00	13381.50	8800.00
FSA3921-019		SH 392 AND WCR 55 ISLANDS	06/02/22	4.00	5200.00	795.67	850.00
NHPP072A-047		SH-72 RESURFACING: I-70 TO IN	06/09/22	4.00	5500.00	6705.70	6705.70
FSA052A-046		SH52 WCR 37 INTERSECTION IMPR	06/09/22	4.00	6500.00	7025.00	3850.00
MTCE0253-291		I-25 SIGN REPLACEMENT PHASE 2	06/16/22	4.00	6500.00	7209.76	5669.52
NHPP0252-448		I-25 TREX NARROWS BRIDGE PREV	06/23/22	6.00	6000.00	6930.25	7000.00
		WEIGHTED AVERAGE FOR THE SECOND QUARTER		80.00	6011.00	9404.30	7992.32
MTCE 072A-045		SH 72B MP 37.00 TO MP 45.3 NE	07/07/22	2.00	3500.00	185.00	185.00
FSA052A-057		SH52 BOX CULVERT EXTENSION (M	08/04/22	4.00	6000.00	9296.67	10075.00
NHPP0063-054		US 6 FROM I70-B TO 33 RD. (MP	08/18/22	4.00	5000.00	9089.45	13000.00

PROJECT NUMBER	ITEM NUMBER/ PROJECT LOCATION	ITEM DESCRIPTION/ PROJECT LOCATION	DATE LET	UNIT/ QUANTITY	ENGR. EST.	AVERAGE BID	AWARDED BID
=====	630-80355	Port Mesq Panel		Each	=====	=====	=====
FBR0761-236		I-76 OVER CLR CRK SCOUR MIT	08/25/22	2.00	6000.00	3366.67	3800.00
C1211-099		SH 121 NORTH SGA SIGNALS	08/25/22	4.00	8500.00	5250.00	3240.00
ER0502-092		US 50 MP 204 EB MONARCH TRUCK	08/29/22	3.00	4000.00	5158.47	5761.52
BR0343-046		US 34 TIMBER BRIDGE REPL. PKG	08/31/22	6.00	2251.06	2251.06	2251.06
FBR0343-047		US 6/US 34 TIMBER BRIDGE REPL					
STAR100-374		5 STRUCTURES IN REGION 1	09/01/22	2.00	8000.00	8480.00	8480.00
NHPPR100-266		R1 ESSENTIAL REPAIRS	09/01/22	5.00	6500.00	12066.67	15900.00
PAN0761-245		ALONG I-76 & RAMPS MILEPOST 9	09/01/22	2.00	7000.00	5500.00	1900.00
ER0253-297		WCR 34 BRIDGE OVER I-25(MM 24	09/14/22	2.00	9000.00	5315.57	1200.00
2670403-065		US40 FLOYD HILL ROUNDABOUTS	09/15/22	9.00	10000.00	10037.13	10500.00
2670703-497		I-70_GENESEE WILDLIFE KING	09/15/22	2.00	10000.00	11785.04	14198.59
SHE2873-193		US 287 & CO 52 INTERSECTION I	09/15/22	4.00	10000.00	9245.83	7950.00
NHPP0701-231		I-70 SALT WASH BRIDGES SCOUR	09/29/22	2.00	5500.00	11011.61	15000.00
		WEIGHTED AVERAGE FOR THE THIRD QUARTER		53.00	6868.04	8531.56	8139.21
MTCE0253-281		MTCE FY23 I-25 CONC PANEL REP	10/06/22	2.00	6000.00	3632.11	9000.00
NHPP0821-114		SH 82 ASPEN/INDEPENDENCE PASS	10/13/22	3.00	10000.00	2746.67	3240.00
C0831-126		SH83 EL PASO COUNTY TO BAYOU	10/13/22	2.00	7000.00	5625.00	8000.00
NHPP0701-253		I-70 EAST OF DEBEQUE	10/27/22	2.00	9000.00	7080.00	7500.00
STA207A-004		Resurfacing SH207A MANZANOLA	10/27/22	4.00	10000.00	11230.00	8690.00
NHPP0705-088		I-70 AGATE STRUCTURE REHAB	10/27/22	2.00	7000.00	10994.41	22300.00
FSAM240-200		SH21B CO SPRINGS SIGNAL REPLA	10/27/22	2.00	4000.00	6875.00	6400.00
C5502-111		US 550 MP 81 AND 89 RED MOUNT	10/27/22	2.00	3600.00	4350.00	4500.00
C170A-002		CRITICAL CULVERT CONST. PKG D	10/27/22	6.00	7000.00	1717.72	1938.89
TRG0253-264		I-25 AND SH 119 PARK-N-RIDE	10/27/22	8.00	6500.00	6299.38	500.00
STA3852-015		US 385 HOLYOKE NORTH	10/27/22	3.00	10000.00	13000.00	13000.00
NHPP0343-048		US 34 (MP 169.3-171.4)	11/01/22	2.00	6000.00	13256.25	5900.00
STU0252-457		I-25:ALAMEDA RIVER PH 2.0	11/03/22	21.00	10000.00	15359.90	19100.00
SHE0242-087		US 24 SAFETY IMPRVMENTS, E OF	11/03/22	2.00	7100.00	7903.32	6209.97
STR064A-010		SH 64 AND SH 13 AT MEEKER	11/10/22	3.00	10000.00	9750.00	10000.00
NHPP0853-126		US85C: PLATTEVILLE NORTH MP (11/10/22	4.00	5000.00	6485.00	7150.00
C5502-097		US550 MP 117.28-126.06	11/17/22	4.00	5500.00	14945.74	16210.00
STRC090-011		US 50B AND SH71/CR18 INTERSEC	11/17/22	4.00	4000.00	7675.00	8750.00
STAM420-001		US 285 AT HWY 9C IMPROVEMENTS	12/01/22	8.00	5618.50	3196.29	10.14
BR2854-148		INTERSECTION OF US 285 & SH 9					
STM0091-046		ADA RAMP IMPROVEMENTS - FAIRP					
STA0711-021		SH71: REGION LINE NORTH	12/01/22	4.00	5600.00	13166.67	12000.00
STR114A-015		SH114 SILLSVILLE SOUTH TO MP3	12/01/22	2.00	6000.00	12750.00	12000.00
2670703-487		I-70 BRIDGES OVER WARD ROAD-	12/01/22	10.00	20000.00	18276.00	20700.00
NHPP0701-252		I-70 RIFLE TO SILT SLAB REPLA	12/01/22	4.00	9000.00	6380.00	1500.00
IM025A-050		I25-MP103.9 - INTERSECTION DR	12/01/22	4.00	7500.00	12333.33	10000.00
STR318A-001		SH 318 MP 0 - 12.5 MOFFAT COU	12/01/22	2.00	9000.00	10795.00	8090.00
STR109A-019		M-22-AY BRIDGE REHAB ON SH109	12/01/22	2.00	10000.00	21230.75	23512.50
NHPP0021-041		SH2 RESURFACING MLK TO 52ND	12/01/22	4.00	6500.00	4668.80	184.14

PROJECT NUMBER	ITEM NUMBER/ PROJECT LOCATION	ITEM DESCRIPTION/ PROJECT LOCATION	DATE LET	UNIT/ QUANTITY	ENGR. EST.	AVERAGE BID	AWARDED BID
=====	630-80355	Port Mesg Panel		Each	=====	=====	=====
STR0641-107		SH 13 MM 104-128.1 IN MOFFAT	12/01/22	2.00	6000.00	8566.67	8500.00
NHPP083A-046		SH83 RESURFACING STROH RD TO	12/08/22	4.00	5250.00	3127.18	3154.36
NHPP0063-048		US6 / 20 ROAD INTERSECTION IM	12/15/22	5.00	10000.00	6242.46	5775.00
NHM175-029		CANON CITY, CO	12/15/22	6.00	4000.00	5500.00	7500.00
NHPP0931-033		SH93:US6 TO 58TH RESURFACING	12/15/22	4.00	5500.00	6284.16	5740.00
NHPP0502-090		SH 50 MP 134.6-136 GUNNISON C	12/22/22	3.00	7000.00	12301.44	15293.68
STR0092-024		SH 9 North of Silverthorne	12/22/22	4.00	8000.00	11170.00	11590.00
STA0361-129		US 36: HYGIENE RD AND NELSON	12/22/22	2.00	7000.00	6524.09	7588.94
BR012A-048		CO 12 STRUCTURE P-17-F AT MP	12/22/22	3.00	6000.00	7803.44	7500.00
STA385A-016		SH 385 MP 97.76	12/22/22	2.00	5500.00	11850.00	11200.00
STR096A-050		SH 96 MP 168.99 TO 193.77	12/22/22	4.00	6000.00	9833.33	14000.00
		WEIGHTED AVERAGE FOR THE FOURTH QUARTER		155.00	8062.89	9464.39	9878.35
		WEIGHTED AVERAGE FOR THE YEAR		379.00	6983.96	9080.97	8672.31
=====	630-80356	Flash Arrow Panel (A Ty)		Each	=====	=====	=====
CM760-047		COLFAX AND QUAIL	05/12/22	2.00	1050.00	931.60	313.00
MTCE0253-291		I-25 SIGN REPLACEMENT PHASE 2	06/16/22	2.00	1500.00	2767.95	1785.90
NHPP0252-448		I-25 TREX NARROWS BRIDGE PREV	06/23/22	2.00	1500.00	1267.50	1500.00
		WEIGHTED AVERAGE FOR THE SECOND QUARTER		6.00	1350.00	1387.63	1199.63
C1211-099		SH 121 NORTH SGA SIGNALS	08/25/22	4.00	3000.00	2082.00	864.00
		WEIGHTED AVERAGE FOR THE THIRD QUARTER		4.00	3000.00	2082.00	864.00
		WEIGHTED AVERAGE FOR THE YEAR		10.00	2010.00	1572.79	1065.38
=====	630-80357	Flash Arrow Panel (B Ty)		Each	=====	=====	=====
MTCE R500-218			01/06/22	1.00	700.00	1187.50	1000.00
NHPP0063-063			02/24/22	4.00	1300.00	1335.00	1400.00
CR100-362			03/14/22	8.00	1605.00	1605.00	1605.00
		WEIGHTED AVERAGE FOR THE FIRST QUARTER		13.00	1441.54	1438.61	1495.38
STM1151-038		SH115 MP 27 TO MP 38	04/21/22	6.00	1200.00	1636.28	1500.00

COLORADO DEPARTMENT OF TRANSPORTATION
ITEM UNIT COSTS BY PROJECTS -- 2022 COST DATA

11:31 Wednesday, March 8, 2023 599

PROJECT NUMBER	ITEM NUMBER/ PROJECT LOCATION	ITEM DESCRIPTION/ PROJECT LOCATION	DATE LET	UNIT/ QUANTITY	ENGR. EST.	AVERAGE BID	AWARDED BID
===== 630-80357 Flash Arrow Panel (B Ty) Each =====							
2670703-479		I-70 BRIDGE OVER HARLAN	05/05/22	4.00	1700.00	3110.51	1338.12
NHPP072A-047		SH-72 RESURFACING: I-70 TO IN	06/09/22	4.00	1500.00	2095.53	2095.53
	WEIGHTED AVERAGE FOR THE SECOND QUARTER			14.00	1428.57	2277.98	1623.90

ER0502-092		US 50 MP 204 EB MONARCH TRUCK	08/29/22	1.00	2000.00	1603.93	1728.46
	WEIGHTED AVERAGE FOR THE THIRD QUARTER			1.00	2000.00	1603.93	1728.46

STRC090-011		US 50B AND SH71/CR18 INTERSEC	11/17/22	3.00	1300.00	1580.00	1510.00
2670703-487		I-70 BRIDGES OVER WARD ROAD-	12/01/22	4.00	1600.00	2766.00	2880.00
NHPP0931-033		SH93:US6 TO 58TH RESURFACING	12/15/22	4.00	2000.00	1492.66	1535.00
NHPP0502-090		SH 50 MP 134.6-136 GUNNISON C	12/22/22	1.00	2000.00	3029.97	2489.66
	WEIGHTED AVERAGE FOR THE FOURTH QUARTER			12.00	1691.67	2209.20	2056.64
	WEIGHTED AVERAGE FOR THE YEAR			40.00	1526.00	2116.37	1714.57
===== 630-80358 Flash Arrow Panel (C Ty) Each =====							
ITS0703-477		ITS EQUIPMENT UPGRADE AT EJMT	01/06/22	2.00	1250.00	1760.00	1760.00
NHPP2873-189		US 287 (FEDERAL BLVD) - COLFA	01/06/22	3.00	1600.00	2246.44	2170.39
MTCER400-391		VARIOUS HIGHWAY SEGMENTS ACRO	01/13/22	2.00	300.00	756.25	750.00
NHPP0702-383		I-70 EB AUX FRISCO TO SILVERT	01/13/22	2.00	3500.00	2559.24	1800.00
MTCER300-262			02/03/22	2.00	500.00	2100.00	1800.00
STA0252-459			02/03/22	4.00	1800.00	1410.67	1354.00
C0762-055			02/17/22	2.00	1650.00	3668.00	8500.00
STR0141-031			02/17/22	2.00	3500.00	2033.33	1600.00
NHPP 0761-238		I-76 DAHLIA TO YORK	03/10/22	11.00	1600.00	3672.42	4200.00
C0761-239							
NHPP0703-472			03/10/22	4.00	1500.00	640.05	350.00
STR160A-034		US160A LA VETA PASS EAST SURF	03/17/22	5.00	2000.00	1690.58	1381.16
BRC040-057			03/17/22	2.00	1500.00	2073.50	1200.00
MP0503-098			03/24/22	3.00	1000.00	1157.50	495.00
NHM765-007			03/31/22	4.00	3500.00	5266.86	3990.00
C0703-499		EJMT GROUT BED REPAIR AND PAN	03/31/22	2.00	2500.00	3470.00	3760.00
	WEIGHTED AVERAGE FOR THE FIRST QUARTER			50.00	1840.00	2808.30	2524.36

NH0504-911			04/07/22	12.00	2000.00	1197.50	1195.00

PROJECT NUMBER	ITEM NUMBER/ PROJECT LOCATION	ITEM DESCRIPTION/ PROJECT LOCATION	DATE LET	UNIT/ QUANTITY	ENGR. EST.	AVERAGE BID	AWARDED BID
=====	630-80358	Flash Arrow Panel (C Ty)		Each	=====	=====	=====
CC030-081		ADA RAMP AND CURBS - FT. LUPT	04/14/22	2.00	2000.00	3467.52	5000.00
NHPP0702-413		VAIL PASS AUX PHASE 1 CAP 2	04/18/22	1.00	2942.50	2942.50	2942.50
MTCE2873-204		MTCE FY22 SH287 CONC PANEL RE	05/05/22	2.00	2000.00	1370.69	1771.37
ER0702-420		PR I-70 GWC MATERIAL FLOWS 20	05/06/22	2.00	1500.00	1825.00	1800.00
STA0712-019		SH 71: Frieight Improvements	05/12/22	4.00	1800.00	4657.73	4657.73
STAR100-358		3 STRUCTURES IN REGION 1 METR	05/26/22	2.00	1500.00	1499.28	2120.00
C0852-120		Rehabilitation of Culvert by	05/26/22	2.00	3000.00	2300.00	2300.00
FSA0702-409		I-70 VAIL WILDLIFE FENCE PHAS	05/26/22	4.00	2200.00	2000.00	2000.00
ITS 0741-024		VMS SIGN INSTALLATIONS AND VS	06/02/22	2.00	1500.00	3070.50	1650.00
MPR200-278		R2 - VARIOUS LOCATIONS	06/09/22	4.00	100.00	283.33	100.00
MPR200-279		FY 23 STENCIL MARKING PROJECT	06/09/22	4.00	100.00	333.33	100.00
		WEIGHTED AVERAGE FOR THE SECOND QUARTER		41.00	1627.87	1508.18	1804.78
MTCE0702-426		I70 FROM MP 155 TO 180 AND MP	07/07/22	2.00	500.00	375.00	150.00
NHPP0702-414		VAIL PASS AUX PHASE 1 CAP 3	07/08/22	2.00	4614.15	4614.15	4614.15
FBR0702-423		VAIL PASS AUX BE F-12-AT PHAS					
NHPP0063-054		US 6 FROM I70-B TO 33 RD. (MP	08/18/22	4.00	1500.00	4653.67	6200.00
STAR100-374		5 STRUCTURES IN REGION 1	09/01/22	2.00	2200.00	2968.00	2968.00
NHPPR100-266		R1 ESSENTIAL REPAIRS	09/01/22	2.00	2000.00	4033.00	4770.00
PAN0761-245		ALONG I-76 & RAMPS MILEPOST 9	09/01/22	2.00	3000.00	1650.00	275.00
ER0253-297		WCR 34 BRIDGE OVER I-25(MM 24	09/14/22	3.00	1800.00	1329.29	250.00
SHE2873-193		US 287 & CO 52 INTERSECTION I	09/15/22	4.00	2000.00	2346.50	1908.00
NHPP0701-231		I-70 SALT WASH BRIDGES SCOUR	09/29/22	2.00	4000.00	3148.30	5000.00
		WEIGHTED AVERAGE FOR THE THIRD QUARTER		23.00	2262.10	2443.60	2988.53
MTCE0253-281		MTCE FY23 I-25 CONC PANEL REP	10/06/22	2.00	2000.00	1048.36	2300.00
NHPP0701-253		I-70 EAST OF DEBEQUE	10/27/22	2.00	3000.00	2175.00	2500.00
NHPP0705-088		I-70 AGATE STRUCTURE REHAB	10/27/22	4.00	2500.00	2449.96	4200.00
FSAM240-200		SH21B CO SPRINGS SIGNAL REPLA	10/27/22	2.00	1000.00	1812.75	1790.00
NHPP0343-048		US 34 (MP 169.3-171.4)	11/01/22	2.00	1700.00	1804.47	1400.00
STU0252-457		I-25:ALAMEDA RIVER PH 2.0	11/03/22	2.00	5000.00	2441.57	2700.00
STR064A-010		SH 64 AND SH 13 AT MEEKER	11/10/22	2.00	2000.00	2116.50	3600.00
NHPP0853-126		US85C: PLATTEVILLE NORTH MP (11/10/22	4.00	1500.00	1155.00	1210.00
MPR200-280		PUEBLO AREA	11/17/22	2.00	1560.00	1750.00	2500.00
2670703-487		I-70 BRIDGES OVER WARD ROAD-	12/01/22	4.00	4800.00	2995.02	3160.00
NHPP0701-252		I-70 RIFLE TO SILT SLAB REPLA	12/01/22	4.00	2400.00	2070.00	500.00
IM025A-050		I25-MP103.9 - INTERSECTION DR	12/01/22	2.00	1500.00	2200.00	1600.00
STR109A-019		M-22-AY BRIDGE REHAB ON SH109	12/01/22	2.00	3000.00	4507.50	5225.00
NHPP0021-041		SH2 RESURFACING MLK TO 52ND	12/01/22	3.00	2200.00	1123.90	55.24
NHPP083A-046		SH83 RESURFACING STROH RD TO	12/08/22	6.00	1600.00	1006.01	1022.01

COLORADO DEPARTMENT OF TRANSPORTATION
ITEM UNIT COSTS BY PROJECTS -- 2022 COST DATA

11:31 Wednesday, March 8, 2023 601

PROJECT NUMBER	ITEM NUMBER/ PROJECT LOCATION	ITEM DESCRIPTION/ PROJECT LOCATION	DATE LET	UNIT/ QUANTITY	ENGR. EST.	AVERAGE BID	AWARDED BID
===== 630-80358 Flash Arrow Panel (C Ty) Each =====							
NHM175-029	CANON CITY, CO		12/15/22	2.00	100.00	1875.00	2250.00
FSA0853-122	WCR14.5 AND US-85, FORT LUPTO		12/15/22	2.00	1500.00	728.07	380.00
STR0092-024	SH 9 North of Silverthorne		12/22/22	4.00	4000.00	3895.00	4040.00
STA0361-129	US 36: HYGIENE RD AND NELSON		12/22/22	2.00	1700.00	1918.68	2399.42
STR096A-050	SH 96 MP 168.99 TO 193.77		12/22/22	2.00	1700.00	2166.67	2400.00
	WEIGHTED AVERAGE FOR THE FOURTH QUARTER			55.00	2336.73	2033.83	2215.71
	WEIGHTED AVERAGE FOR THE YEAR			169.00	2007.64	2300.52	2310.27
===== 630-80359 Port Mesg Panel Day =====							
NHPP0702-413	VAIL PASS AUX PHASE 1 CAP 2		04/18/22	392.00	90.95	90.95	90.95
ER0702-420	PR I-70 GWC MATERIAL FLOWS 20		05/06/22	244.00	70.00	177.50	175.00
	WEIGHTED AVERAGE FOR THE SECOND QUARTER			636.00	82.91	138.95	123.20
NHPP0702-414	VAIL PASS AUX PHASE 1 CAP 3		07/08/22	824.00	98.87	98.87	98.87
FBR0702-423	VAIL PASS AUX BE F-12-AT PHAS						
BR0343-046	US 34 TIMBER BRIDGE REPL. PKG		08/31/22	168.00	53.50	53.50	53.50
FBR0343-047	US 6/US 34 TIMBER BRIDGE REPL						
	WEIGHTED AVERAGE FOR THE THIRD QUARTER			992.00	91.19	91.19	91.19
FSA0853-122	WCR14.5 AND US-85, FORT LUPTO		12/15/22	52.00	150.00	116.97	110.00
	WEIGHTED AVERAGE FOR THE FOURTH QUARTER			52.00	150.00	116.97	110.00
	WEIGHTED AVERAGE FOR THE YEAR			1,680.00	89.87	113.89	103.89
===== 630-80360 Drum Channel Dev Each =====							
NHPP2873-189	US 287 (FEDERAL BLVD) - COLFA		01/06/22	150.00	32.00	38.67	43.41
NHPP0702-383	I-70 EB AUX FRISCO TO SILVERT		01/13/22	300.00	32.00	22.54	22.00
MTCER300-262			02/03/22	26.00	25.00	56.67	25.00
NHPP1601-083			02/03/22	150.00	25.00	62.92	30.00
STA0252-459			02/03/22	300.00	35.00	30.90	20.50
C0762-055			02/17/22	250.00	40.00	54.40	40.00

PROJECT NUMBER	ITEM NUMBER/ PROJECT LOCATION	ITEM DESCRIPTION/ PROJECT LOCATION	DATE LET	UNIT/ QUANTITY	ENGR. EST.	AVERAGE BID	AWARDED BID
=====	630-80360	Drum Channel Dev		Each =====			
STR0141-031			02/17/22	250.00	40.00	37.33	37.00
STR133A-051			02/17/22	50.00	25.00	38.00	30.00
NHPP0063-063			02/24/22	400.00	30.00	27.70	29.00
STA 067A-048		Hwy 67A MP 0.00 TO MP 11.05 I	03/03/22	100.00	30.00	46.93	40.00
NHPP0703-472			03/10/22	200.00	34.00	36.05	30.00
CR100-362			03/14/22	75.00	26.75	26.75	26.75
STR160A-034		US160A LA VETA PASS EAST SURF	03/17/22	100.00	30.00	50.13	55.25
BRC040-057			03/17/22	75.00	32.00	66.25	55.00
STR R500-171		Various locations on SH 141 a	03/17/22	90.00	25.00	35.51	60.00
M R100-351		FY22 R1 SIGN STRUCTURE REPLAC	03/17/22	50.00	40.00	33.00	42.00
STR092A-031			03/17/22	100.00	30.00	54.00	54.00
NHM765-007			03/31/22	225.00	55.00	56.30	74.10
C0703-499		EJMT GROUT BED REPAIR AND PAN	03/31/22	270.00	40.00	115.50	125.00
WEIGHTED AVERAGE FOR THE FIRST QUARTER				3,161.00	34.86	43.64	44.84
NH0504-911			04/07/22	300.00	38.02	40.90	41.80
CC030-081		ADA RAMP AND CURBS - FT. LUPT	04/14/22	60.00	35.00	55.57	60.00
NHPP0702-413		VAIL PASS AUX PHASE 1 CAP 2	04/18/22	50.00	26.75	26.75	26.75
MTCE2873-204		MTCE FY22 SH287 CONC PANEL RE	05/05/22	150.00	60.00	75.51	54.01
2670703-479		I-70 BRIDGE OVER HARLAN	05/05/22	200.00	40.00	59.43	66.91
ER0702-420		PR I-70 GWC MATERIAL FLOWS 20	05/06/22	300.00	30.00	24.50	24.00
STA0712-019		SH 71: Frieight Improvements	05/12/22	330.00	30.00	56.93	56.93
STA001A-005		SH1 WELLINGTON SOUTH RESURFAC	05/12/22	40.00	43.00	33.05	30.00
NHC540-017		R2 CHAINUP STA @ KENOSHA/HOOS	05/12/22	150.00	35.00	40.00	40.00
CM760-047		COLFAX AND QUAIL	05/12/22	50.00	31.00	41.20	38.00
NHPP 3851-018		US 385 NORTH OF CHEYENNE WELL	05/26/22	25.00	45.00	80.00	50.00
STAR100-358		3 STRUCTURES IN REGION 1 METR	05/26/22	50.00	50.00	56.05	69.00
C0852-120		Rehabilitation of Culvert by	05/26/22	50.00	60.00	62.00	62.00
FSA0702-409		I-70 VAIL WILDLIFE FENCE PHAS	05/26/22	100.00	30.00	25.00	25.00
ITS 0741-024		VMS SIGN INSTALLATIONS AND VS	06/02/22	100.00	40.00	71.50	72.00
FSA3921-019		SH 392 AND WCR 55 ISLANDS	06/02/22	40.00	35.00	8.67	10.00
NHPP072A-047		SH-72 RESURFACING: I-70 TO IN	06/09/22	50.00	30.00	41.91	41.91
FSA052A-046		SH52 WCR 37 INTERSECTION IMPR	06/09/22	100.00	60.00	73.05	36.00
MPR200-278		R2 - VARIOUS LOCATIONS	06/09/22	250.00	40.00	13.33	10.00
MPR200-279		FY 23 STENCIL MARKING PROJECT	06/09/22	100.00	40.00	26.67	5.00
MTCE0253-291		I-25 SIGN REPLACEMENT PHASE 2	06/16/22	400.00	35.00	75.35	56.70
NHPP0252-448		I-25 TREX NARROWS BRIDGE PREV	06/23/22	100.00	35.00	23.50	30.00
WEIGHTED AVERAGE FOR THE SECOND QUARTER				2,995.00	37.83	47.13	42.18
NHPP0702-414		VAIL PASS AUX PHASE 1 CAP 3	07/08/22	100.00	38.45	38.45	38.45

PROJECT NUMBER	ITEM NUMBER/ PROJECT LOCATION	ITEM DESCRIPTION/ PROJECT LOCATION	DATE LET	UNIT/ QUANTITY	ENGR. EST.	AVERAGE BID	AWARDED BID
=====	630-80360	Drum Channel Dev		Each	=====	=====	=====
FBR0702-423		VAIL PASS AUX BE F-12-AT PHAS					
STR0711-022		SH 71 OVER THE ARKANSAS	08/04/22	100.00	43.00	70.00	95.00
NHPP0063-054		US 6 FROM I70-B TO 33 RD. (MP	08/18/22	200.00	30.00	38.40	25.00
FBR0761-236		I-76 OVER CLR CRK SCOUR MIT	08/25/22	14.00	34.00	65.00	65.00
C1211-099		SH 121 NORTH SGA SIGNALS	08/25/22	100.00	70.00	32.50	25.00
ER0502-092		US 50 MP 204 EB MONARCH TRUCK	08/29/22	25.00	25.00	54.83	63.38
BR0343-046		US 34 TIMBER BRIDGE REPL. PKG	08/31/22	155.00	23.37	23.37	23.37
FBR0343-047		US 6/US 34 TIMBER BRIDGE REPL					
STAR100-374		5 STRUCTURES IN REGION 1	09/01/22	50.00	70.00	31.80	31.80
NHPPR100-266		R1 ESSENTIAL REPAIRS	09/01/22	250.00	45.00	44.00	53.00
PAN0761-245		ALONG I-76 & RAMPS MILEPOST 9	09/01/22	30.00	60.00	53.00	15.00
ER0253-297		WCR 34 BRIDGE OVER I-25(MM 24	09/14/22	100.00	40.00	45.29	6.00
2670403-065		US40 FLOYD HILL ROUNDABOUTS	09/15/22	57.00	70.00	71.93	83.00
2670703-497		I-70_GENESEE WILDLIFE KING	09/15/22	100.00	36.00	60.38	68.15
SHE2873-193		US 287 & CO 52 INTERSECTION I	09/15/22	200.00	30.00	67.53	58.30
NHPP0701-231		I-70 SALT WASH BRIDGES SCOUR	09/29/22	80.00	55.00	38.51	50.00
		WEIGHTED AVERAGE FOR THE THIRD QUARTER		1,561.00	41.26	53.50	44.88
MTCE0253-281		MTCE FY23 I-25 CONC PANEL REP	10/06/22	150.00	60.00	35.55	66.00
NHPP0821-114		SH 82 ASPEN/INDEPENDENCE PASS	10/13/22	30.00	70.00	23.60	10.80
C0831-126		SH83 EL PASO COUNTY TO BAYOU	10/13/22	50.00	42.00	37.50	65.00
NHPP0701-253		I-70 EAST OF DEBEQUE	10/27/22	90.00	50.00	30.40	30.00
STA207A-004		Resurfacing SH207A MANZANOLA	10/27/22	300.00	25.00	66.10	68.30
NHPP0705-088		I-70 AGATE STRUCTURE REHAB	10/27/22	500.00	38.00	50.87	65.00
FSAM240-200		SH21B CO SPRINGS SIGNAL REPLA	10/27/22	50.00	55.00	64.50	62.00
C5502-111		US 550 MP 81 AND 89 RED MOUNT	10/27/22	30.00	5.00	24.00	24.00
TRG0253-264		I-25 AND SH 119 PARK-N-RIDE	10/27/22	100.00	50.00	92.68	120.00
STA3852-015		US 385 HOLYOKE NORTH	10/27/22	150.00	75.00	36.00	36.00
NHPP0343-048		US 34 (MP 169.3-171.4)	11/01/22	82.00	36.00	54.78	40.00
STU0252-457		I-25:ALAMEDA RIVER PH 2.0	11/03/22	60.00	40.00	60.03	61.00
STR064A-010		SH 64 AND SH 13 AT MEEKER	11/10/22	50.00	40.00	53.70	81.00
NHPP0853-126		US85C: PLATTEVILLE NORTH MP (11/10/22	25.00	36.30	19.24	16.50
C5502-097		US550 MP 117.28-126.06	11/17/22	650.00	50.00	39.95	43.20
MPR200-280		PUEBLO AREA	11/17/22	15.00	47.00	47.50	65.00
STAM420-001		US 285 AT HWY 9C IMPROVEMENTS	12/01/22	84.00	43.00	51.07	79.58
BR2854-148		INTERSECTION OF US 285 & SH 9					
STM0091-046		ADA RAMP IMPROVEMENTS - FAIRP					
STA0711-021		SH71: REGION LINE NORTH	12/01/22	260.00	35.00	33.67	50.00
STR114A-015		SH114 SILLSVILLE SOUTH TO MP3	12/01/22	100.00	50.00	37.50	50.00
2670703-487		I-70 BRIDGES OVER WARD ROAD-	12/01/22	200.00	70.00	61.06	63.00
NHPP0701-252		I-70 RIFLE TO SILT SLAB REPLA	12/01/22	300.00	40.00	75.50	75.00
IM025A-050		I25-MP103.9 - INTERSECTION DR	12/01/22	250.00	30.00	60.00	53.00
STR318A-001		SH 318 MP 0 - 12.5 MOFFAT COU	12/01/22	50.00	50.00	38.20	32.40
STR109A-019		M-22-AY BRIDGE REHAB ON SH109	12/01/22	100.00	75.00	65.47	67.93

PROJECT NUMBER	ITEM NUMBER/ PROJECT LOCATION	ITEM DESCRIPTION/ PROJECT LOCATION	DATE LET	UNIT/ QUANTITY	ENGR. EST.	AVERAGE BID	AWARDED BID
===== 630-80360							
		Drum Channel Dev		Each			
NHPP0021-041		SH2 RESURFACING MLK TO 52ND	12/01/22	200.00	35.00	62.02	30.69
STR0641-107		SH 13 MM 104-128.1 IN MOFFAT	12/01/22	40.00	22.00	33.00	25.00
NHPP083A-046		SH83 RESURFACING STROH RD TO	12/08/22	600.00	30.00	43.58	44.16
NHPP0063-048		US6 / 20 ROAD INTERSECTION IM	12/15/22	100.00	50.00	27.27	15.25
NHMI75-029		CANON CITY, CO	12/15/22	50.00	60.00	22.50	25.00
FSA0853-122		WCRI4.5 AND US-85, FORT LUPTO	12/15/22	40.00	70.00	10.97	12.00
NHPP0931-033		SH93:US6 TO 58TH RESURFACING	12/15/22	100.00	30.00	38.22	35.90
NHPP0502-090		SH 50 MP 134.6-136 GUNNISON C	12/22/22	275.00	40.00	43.37	42.69
STR0092-024		SH 9 North of Silverthorne	12/22/22	400.00	35.00	36.40	37.80
STA0361-129		US 36: HYGIENE RD AND NELSON	12/22/22	125.00	40.00	38.83	71.85
BR012A-048		CO 12 STRUCTURE P-17-F AT MP	12/22/22	75.00	65.00	56.84	63.00
STA385A-016		SH 385 MP 97.76	12/22/22	200.00	20.00	63.89	55.56
STR096A-050		SH 96 MP 168.99 TO 193.77	12/22/22	150.00	36.00	60.33	50.00
		WEIGHTED AVERAGE FOR THE FOURTH QUARTER		6,031.00	41.45	50.64	52.12
		WEIGHTED AVERAGE FOR THE YEAR		13,748.00	39.12	48.74	47.53
===== 630-80363							
		Drum Channel Dev (Light) (F)		Each			
ITS0703-477		ITS EQUIPMENT UPGRADE AT EJMT	01/06/22	50.00	50.00	22.00	22.00
NHPP0702-383		I-70 EB AUX FRISCO TO SILVERT	01/13/22	20.00	35.00	26.44	23.00
NHPP1601-083			02/03/22	25.00	40.00	154.66	32.00
C0762-055			02/17/22	6.00	40.00	102.17	45.00
STR0141-031			02/17/22	20.00	50.00	42.00	41.00
NHPP0063-063			02/24/22	50.00	40.00	33.35	35.00
NHPP 0761-238		I-76 DAHLIA TO YORK	03/10/22	80.00	40.00	80.37	85.00
C0761-239							
NHPP0703-472			03/10/22	16.00	38.00	45.74	40.00
CR100-362			03/14/22	16.00	26.75	26.75	26.75
STR092A-031			03/17/22	50.00	40.00	70.00	70.00
C0703-499		EJMT GROUT BED REPAIR AND PAN	03/31/22	6.00	65.00	146.00	160.00
		WEIGHTED AVERAGE FOR THE FIRST QUARTER		339.00	41.49	68.47	51.71
NH0504-911			04/07/22	150.00	45.00	46.90	47.80
NHPP0702-413		VAIL PASS AUX PHASE 1 CAP 2	04/18/22	10.00	32.10	32.10	32.10
MTCE2873-204		MTCE FY22 SH287 CONC PANEL RE	05/05/22	10.00	50.00	84.71	59.41
ER0702-420		PR I-70 GWC MATERIAL FLOWS 20	05/06/22	50.00	50.00	24.50	24.00
STA0712-019		SH 71: Frieight Improvements	05/12/22	12.00	35.00	77.63	77.63
FSA0702-409		I-70 VAIL WILDLIFE FENCE PHAS	05/26/22	20.00	35.00	25.00	25.00
MTCE0253-291		I-25 SIGN REPLACEMENT PHASE 2	06/16/22	200.00	45.00	84.68	62.36
		WEIGHTED AVERAGE FOR THE SECOND QUARTER		452.00	44.67	62.46	51.30

COLORADO DEPARTMENT OF TRANSPORTATION
ITEM UNIT COSTS BY PROJECTS -- 2022 COST DATA

11:31 Wednesday, March 8, 2023 605

PROJECT NUMBER	ITEM NUMBER/ PROJECT LOCATION	ITEM DESCRIPTION/ PROJECT LOCATION	DATE LET	UNIT/ QUANTITY	ENGR. EST.	AVERAGE BID	AWARDED BID
===== 630-80363		Drum Channel Dev (Light) (F)		Each	=====		
NHPP0702-414		VAIL PASS AUX PHASE 1 CAP 3	07/08/22	10.00	43.94	43.94	43.94
FBR0702-423		VAIL PASS AUX BE F-12-AT PHAS					
NHPP0063-054		US 6 FROM I70-B TO 33 RD. (MP	08/18/22	50.00	35.00	50.90	50.00
FBR0761-236		I-76 OVER CLR CRK SCOUR MIT	08/25/22	2.00	38.00	71.67	65.00
C1211-099		SH 121 NORTH SGA SIGNALS	08/25/22	30.00	80.00	65.00	35.00
ER0502-092		US 50 MP 204 EB MONARCH TRUCK	08/29/22	25.00	40.00	56.70	40.33
NHPP0701-231		I-70 SALT WASH BRIDGES SCOUR	09/29/22	10.00	55.00	41.21	50.00
		WEIGHTED AVERAGE FOR THE THIRD QUARTER		127.00	48.94	55.11	44.31
MTCE0253-281		MTCE FY23 I-25 CONC PANEL REP	10/06/22	50.00	70.00	55.93	133.00
NHPP0821-114		SH 82 ASPEN/INDEPENDENCE PASS	10/13/22	30.00	75.00	26.93	10.80
C0831-126		SH83 EL PASO COUNTY TO BAYOU	10/13/22	25.00	40.00	55.00	100.00
NHPP0701-253		I-70 EAST OF DEBEQUE	10/27/22	25.00	55.00	35.45	35.00
STR064A-010		SH 64 AND SH 13 AT MEEKER	11/10/22	20.00	60.00	56.35	81.00
C5502-097		US550 MP 117.28-126.06	11/17/22	25.00	50.00	58.70	48.60
MPR200-280		PUEBLO AREA	11/17/22	1.00	47.00	57.50	85.00
STRC090-011		US 50B AND SH71/CR18 INTERSEC	11/17/22	100.00	50.00	89.00	95.00
STA0711-021		SH71: REGION LINE NORTH	12/01/22	10.00	40.00	38.67	55.00
STR114A-015		SH114 SILLSVILLE SOUTH TO MP3	12/01/22	25.00	60.00	40.00	55.00
NHPP0701-252		I-70 RIFLE TO SILT SLAB REPLA	12/01/22	26.00	50.00	92.50	75.00
IM025A-050		I25-MP103.9 - INTERSECTION DR	12/01/22	10.00	40.00	65.00	60.00
STR318A-001		SH 318 MP 0 - 12.5 MOFFAT COU	12/01/22	20.00	80.00	54.85	64.70
STR109A-019		M-22-AY BRIDGE REHAB ON SH109	12/01/22	50.00	100.00	107.42	88.83
STR0641-107		SH 13 MM 104-128.1 IN MOFFAT	12/01/22	4.00	30.00	46.00	25.00
NHPP0063-048		US6 / 20 ROAD INTERSECTION IM	12/15/22	20.00	50.00	27.96	18.00
NHPP0502-090		SH 50 MP 134.6-136 GUNNISON C	12/22/22	25.00	50.00	56.78	42.69
STR0092-024		SH 9 North of Silverthorne	12/22/22	200.00	40.00	41.55	43.10
STA0361-129		US 36: HYGIENE RD AND NELSON	12/22/22	4.00	40.00	52.62	102.62
		WEIGHTED AVERAGE FOR THE FOURTH QUARTER		670.00	54.26	60.82	66.62
		WEIGHTED AVERAGE FOR THE YEAR		1,588.00	48.38	62.87	57.75
===== 630-80364		Drum Channel Dev (Light) (SB)		Each	=====		
NH0504-910		US50B I-24-B MIN REP AT MP 40	01/13/22	50.00	90.00	69.85	55.56
NHPP0702-383		I-70 EB AUX FRISCO TO SILVERT	01/13/22	40.00	35.00	27.08	24.00
NHPP1601-083			02/03/22	200.00	40.00	66.57	40.00

COLORADO DEPARTMENT OF TRANSPORTATION
ITEM UNIT COSTS BY PROJECTS -- 2022 COST DATA

11:31 Wednesday, March 8, 2023 606

PROJECT NUMBER	ITEM NUMBER/ PROJECT LOCATION	ITEM DESCRIPTION/ PROJECT LOCATION	DATE LET	UNIT/ QUANTITY	ENGR. EST.	AVERAGE BID	AWARDED BID
===== 630-80364							
		Drum Channel Dev (Light) (SB)		Each			
STR0141-031			02/17/22	40.00	60.00	42.00	41.00
NHPP0063-063			02/24/22	50.00	40.00	33.35	35.00
NHPP 0761-238	I-76 DAHLIA TO YORK		03/10/22	350.00	40.00	80.37	85.00
C0761-239							
STR160A-034	US160A LA VETA PASS EAST SURF		03/17/22	100.00	45.00	60.91	71.82
STR R500-171	Various locations on SH 141 a		03/17/22	30.00	50.00	51.03	60.00
STR092A-031			03/17/22	25.00	60.00	70.00	70.00
NHM765-007			03/31/22	10.00	65.00	118.26	96.90
WEIGHTED AVERAGE FOR THE FIRST QUARTER				895.00	45.20	72.27	63.22
NHPP0702-413	VAIL PASS AUX PHASE 1 CAP 2		04/18/22	10.00	32.10	32.10	32.10
ER0702-420	PR I-70 GWC MATERIAL FLOWS 20		05/06/22	50.00	50.00	24.50	24.00
FSA0702-409	I-70 VAIL WILDLIFE FENCE PHAS		05/26/22	10.00	40.00	25.00	25.00
MPR200-278	R2 - VARIOUS LOCATIONS		06/09/22	150.00	40.00	15.00	10.00
MPR200-279	FY 23 STENCIL MARKING PROJECT		06/09/22	50.00	40.00	44.17	7.50
WEIGHTED AVERAGE FOR THE SECOND QUARTER				270.00	41.56	22.77	13.50
NHPP0702-414	VAIL PASS AUX PHASE 1 CAP 3		07/08/22	10.00	43.94	43.94	43.94
FBR0702-423	VAIL PASS AUX BE F-12-AT PHAS						
NHPP0063-054	US 6 FROM I70-B TO 33 RD. (MP		08/18/22	50.00	40.00	50.90	50.00
ER0502-092	US 50 MP 204 EB MONARCH TRUCK		08/29/22	25.00	50.00	56.70	40.33
ER0253-297	WCR 34 BRIDGE OVER I-25(MM 24		09/14/22	50.00	45.00	56.26	8.00
NHPP0701-231	I-70 SALT WASH BRIDGES SCOUR		09/29/22	10.00	60.00	41.21	50.00
WEIGHTED AVERAGE FOR THE THIRD QUARTER				145.00	45.10	53.97	33.43
NHPP0821-114	SH 82 ASPEN/INDEPENDENCE PASS		10/13/22	30.00	75.00	26.93	10.80
NHPP0701-253	I-70 EAST OF DEBEQUE		10/27/22	50.00	50.00	35.45	35.00
FSAM240-200	SH21B CO SPRINGS SIGNAL REPLA		10/27/22	25.00	55.00	75.00	73.00
STR064A-010	SH 64 AND SH 13 AT MEEKER		11/10/22	20.00	60.00	56.35	81.00
C5502-097	US550 MP 117.28-126.06		11/17/22	25.00	50.00	58.70	48.60
MPR200-280	PUEBLO AREA		11/17/22	4.00	47.00	57.50	85.00
STA0711-021	SH71: REGION LINE NORTH		12/01/22	10.00	39.00	38.67	55.00
STR114A-015	SH114 SILLSVILLE SOUTH TO MP3		12/01/22	10.00	70.00	40.00	55.00
NHPP0701-252	I-70 RIFLE TO SILT SLAB REPLA		12/01/22	66.00	80.00	92.50	75.00
IM025A-050	I25-MP103.9 - INTERSECTION DR		12/01/22	75.00	40.00	69.67	60.00
STR318A-001	SH 318 MP 0 - 12.5 MOFFAT COU		12/01/22	20.00	90.00	54.85	64.70

COLORADO DEPARTMENT OF TRANSPORTATION
 ITEM UNIT COSTS BY PROJECTS -- 2022 COST DATA

11:31 Wednesday, March 8, 2023 607

PROJECT NUMBER	ITEM NUMBER/ PROJECT LOCATION	ITEM DESCRIPTION/ PROJECT LOCATION	DATE LET	UNIT/ QUANTITY	ENGR. EST.	AVERAGE BID	AWARDED BID
=====	630-80364	Drum Channel Dev (Light) (SB)		Each =====			
STR0641-107		SH 13 MM 104-128.1 IN MOFFAT	12/01/22	4.00	30.00	46.00	25.00
NHPP0063-048		US6 / 20 ROAD INTERSECTION IM	12/15/22	10.00	50.00	28.46	20.00
NHPP0502-090		SH 50 MP 134.6-136 GUNNISON C	12/22/22	25.00	52.00	56.78	42.69
STR0092-024		SH 9 North of Silverthorne	12/22/22	200.00	45.00	41.55	43.10
BR012A-048		CO 12 STRUCTURE P-17-F AT MP	12/22/22	25.00	75.00	85.67	70.00
STR096A-050		SH 96 MP 168.99 TO 193.77	12/22/22	150.00	40.00	68.67	55.00
	WEIGHTED AVERAGE FOR THE FOURTH QUARTER			749.00	51.71	62.05	55.95
	WEIGHTED AVERAGE FOR THE YEAR			2,059.00	47.08	63.74	52.14
=====	630-80367	Port Traf Speed Monitor		Each =====			
NHPP0702-383		I-70 EB AUX FRISCO TO SILVERT	01/13/22	2.00	5000.00	4909.54	4700.00
C0762-055			02/17/22	4.00	1800.00	3375.33	8500.00
STR0141-031			02/17/22	2.00	5000.00	6100.00	7800.00
NHPP 0761-238		I-76 DAHLIA TO YORK	03/10/22	2.00	6000.00	5188.67	4200.00
C0761-239							
	WEIGHTED AVERAGE FOR THE FIRST QUARTER			10.00	3920.00	4639.99	6740.00
ER0702-420		PR I-70 GWC MATERIAL FLOWS 20	05/06/22	2.00	4500.00	2175.00	2500.00
FSA0702-409		I-70 VAIL WILDLIFE FENCE PHAS	05/26/22	1.00	7000.00	8000.00	8000.00
	WEIGHTED AVERAGE FOR THE SECOND QUARTER			3.00	5333.33	3340.00	4333.33
NHPP0063-054		US 6 FROM I70-B TO 33 RD. (MP	08/18/22	2.00	3500.00	4128.67	5150.00
	WEIGHTED AVERAGE FOR THE THIRD QUARTER			2.00	3500.00	4128.67	5150.00
MTCE0253-281		MTCE FY23 I-25 CONC PANEL REP	10/06/22	2.00	3000.00	1578.87	2845.00
NHPP0701-253		I-70 EAST OF DEBEQUE	10/27/22	2.00	1000.00	7080.00	7500.00
STA3852-015		US 385 HOLYOKE NORTH	10/27/22	2.00	5000.00	8700.00	8700.00
STR064A-010		SH 64 AND SH 13 AT MEEKER	11/10/22	2.00	7000.00	3700.00	540.00
STA0711-021		SH71: REGION LINE NORTH	12/01/22	4.00	3600.00	4883.33	3000.00
NHPP0701-252		I-70 RIFLE TO SILT SLAB REPLA	12/01/22	4.00	8000.00	3500.00	500.00
STR318A-001		SH 318 MP 0 - 12.5 MOFFAT COU	12/01/22	2.00	5000.00	5495.00	2700.00
	WEIGHTED AVERAGE FOR THE FOURTH QUARTER			18.00	4911.11	4326.93	3253.89
	WEIGHTED AVERAGE FOR THE YEAR			33.00	4563.64	4420.86	4523.33

COLORADO DEPARTMENT OF TRANSPORTATION
ITEM UNIT COSTS BY PROJECTS -- 2022 COST DATA

11:31 Wednesday, March 8, 2023 608

PROJECT NUMBER	ITEM NUMBER/ PROJECT LOCATION	ITEM DESCRIPTION/ PROJECT LOCATION	DATE LET	UNIT/ QUANTITY	ENGR. EST.	AVERAGE BID	AWARDED BID
===== 630-80370		Barrier (Temp)		Lin Foot	=====		
NH0504-910		US50B L-24-B MIN REP AT MP 40	01/13/22	1,600.00	60.00	41.75	37.50
NHPP0702-383		I-70 EB AUX FRISCO TO SILVERT	01/13/22	19,000.00	50.00	44.32	38.00
NHPP1601-083			02/03/22	1,125.00	100.00	121.16	120.00
C0762-055			02/17/22	1,197.00	50.00	54.79	60.00
STR0141-031			02/17/22	1,400.00	45.00	40.67	42.00
NHPP 0761-238		I-76 DAHLIA TO YORK	03/10/22	30,800.00	43.00	52.94	25.00
C0761-239							
NHPP0703-472			03/10/22	600.00	35.00	42.78	45.00
STR160A-034		US160A LA VETA PASS EAST SURF	03/17/22	1,275.00	40.00	47.39	39.78
STR R500-171		Various locations on SH 141 a	03/17/22	750.00	190.00	64.98	82.00
NHM765-007			03/31/22	2,200.00	85.00	46.92	42.12
		WEIGHTED AVERAGE FOR THE FIRST QUARTER		59,947.00	50.17	50.56	34.19
NH0504-911			04/07/22	600.00	40.00	60.35	40.70
NHPP0702-413		VAIL PASS AUX PHASE 1 CAP 2	04/18/22	12,045.00	55.44	55.44	55.44
STM1151-038		SH115 MP 27 TO MP 38	04/21/22	1,500.00	36.00	55.91	50.22
2670703-479		I-70 BRIDGE OVER HARLAN	05/05/22	4,000.00	50.00	58.22	45.00
		WEIGHTED AVERAGE FOR THE SECOND QUARTER		18,145.00	52.12	57.14	52.22
NHPP0702-414		VAIL PASS AUX PHASE 1 CAP 3	07/08/22	23,461.00	56.46	56.46	56.46
FBR0702-423		VAIL PASS AUX BE F-12-AT PHAS					
FSA052A-057		SH52 BOX CULVERT EXTENSION (M	08/04/22	300.00	60.00	48.13	30.80
ER0502-092		US 50 MP 204 EB MONARCH TRUCK	08/29/22	850.00	80.00	66.62	64.86
ER0253-297		WCR 34 BRIDGE OVER I-25(MM 24	09/14/22	500.00	50.00	29.31	9.50
2670403-065		US40_FLOYD HILL ROUNDABOUTS	09/15/22	400.00	70.00	66.54	68.00
2670703-497		I-70_GENESEE WILDLIFE KING	09/15/22	8,000.00	44.00	70.07	29.37
SHE2873-193		US 287 & CO 52 INTERSECTION I	09/15/22	4,000.00	40.00	58.96	45.00
		WEIGHTED AVERAGE FOR THE THIRD QUARTER		37,511.00	52.67	63.71	48.94
NHPP0701-253		I-70 EAST OF DEBEQUE	10/27/22	664.00	50.00	56.50	70.00
NHPP0705-088		I-70 AGATE STRUCTURE REHAB	10/27/22	2,800.00	38.00	128.17	98.00
C170A-002		CRITICAL CULVERT CONST. PKG D	10/27/22	810.00	50.00	65.13	62.50
NHPP0343-048		US 34 (MP 169.3-171.4)	11/01/22	1,272.00	44.00	47.51	53.00
STU0252-457		I-25:ALAMEDA RIVER PH 2.0	11/03/22	1,640.00	80.00	86.00	113.00

PROJECT NUMBER	ITEM NUMBER/ PROJECT LOCATION	ITEM DESCRIPTION/ PROJECT LOCATION	DATE LET	UNIT/ QUANTITY	ENGR. EST.	AVERAGE BID	AWARDED BID
=====	630-80370	Barrier (Temp)		Lin Foot	=====		
SHE0242-087		US 24 SAFETY IMPRVMENTS, E OF	11/03/22	900.00	52.00	51.12	53.34
NHPP0853-126		US85C: PLATTEVILLE NORTH MP (11/10/22	1,500.00	50.00	37.56	35.20
C5502-097		US550 MP 117.28-126.06	11/17/22	2,790.00	75.00	144.65	220.00
STRC090-011		US 50B AND SH71/CR18 INTERSEC	11/17/22	2,000.00	41.00	38.50	40.00
STAM420-001		US 285 AT HWY 9C IMPROVEMENTS	12/01/22	2,270.00	45.00	83.01	76.21
BR2854-148		INTERSECTION OF US 285 & SH 9					
STM0091-046		ADA RAMP IMPROVEMENTS - FAIRP					
STA0711-021		SH71: REGION LINE NORTH	12/01/22	200.00	43.00	62.33	66.00
NHPP0701-252		I-70 RIFLE TO SILT SLAB REPLA	12/01/22	500.00	50.00	143.00	223.00
IM025A-050		I25-MP103.9 - INTERSECTION DR	12/01/22	2,500.00	40.00	56.00	70.00
NHPP0063-048		US6 / 20 ROAD INTERSECTION IM	12/15/22	1,000.00	40.00	118.04	67.00
FSA0853-122		WCRI4.5 AND US-85, FORT LUPTO	12/15/22	500.00	60.00	46.81	40.00
NHPP0931-033		SH93:US6 TO 58TH RESURFACING	12/15/22	1,750.00	50.00	27.34	30.75
NHPP0502-090		SH 50 MP 134.6-136 GUNNISON C	12/22/22	6,900.00	45.00	65.22	45.35
BR012A-048		CO 12 STRUCTURE P-17-F AT MP	12/22/22	1,550.00	50.00	87.71	80.00
STA385A-016		SH 385 MP 97.76	12/22/22	800.00	45.00	85.69	68.75
		WEIGHTED AVERAGE FOR THE FOURTH QUARTER		32,346.00	49.39	75.60	77.84
		WEIGHTED AVERAGE FOR THE YEAR		147,949.00	50.87	57.83	49.73
=====	630-80371	Reset Concrete Barrier (Temp)		Lin Foot	=====		
NHPP0702-413		VAIL PASS AUX PHASE 1 CAP 2	04/18/22	1,500.00	3.18	3.18	3.18
		WEIGHTED AVERAGE FOR THE SECOND QUARTER		1,500.00	3.18	3.18	3.18
NHPP0702-414		VAIL PASS AUX PHASE 1 CAP 3	07/08/22	22,680.00	4.29	4.29	4.29
FBR0702-423		VAIL PASS AUX BE F-12-AT PHAS					
		WEIGHTED AVERAGE FOR THE THIRD QUARTER		22,680.00	4.29	4.29	4.29
C170A-002		CRITICAL CULVERT CONST. PKG D	10/27/22	470.00	20.00	14.88	10.00
		WEIGHTED AVERAGE FOR THE FOURTH QUARTER		470.00	20.00	14.88	10.00
		WEIGHTED AVERAGE FOR THE YEAR		24,650.00	4.52	4.99	4.33
=====	630-80372	Conc Barrier (Temp) (Furnish & Install)		Lin Foot	=====		
NHPP 0761-238		I-76 DAHLIA TO YORK	03/10/22	5,630.00	40.00	69.20	50.00

COLORADO DEPARTMENT OF TRANSPORTATION
ITEM UNIT COSTS BY PROJECTS -- 2022 COST DATA

11:31 Wednesday, March 8, 2023 610

PROJECT NUMBER	ITEM NUMBER/ PROJECT LOCATION	ITEM DESCRIPTION/ PROJECT LOCATION	DATE LET	UNIT/ QUANTITY	ENGR. EST.	AVERAGE BID	AWARDED BID
=====	630-80372	Conc Barrier (Temp) (Furnish & Install)		Lin Foot	=====		
C0761-239							
M R100-351		FY22 R1 SIGN STRUCTURE REPLAC	03/17/22	3,600.00	30.00	29.50	34.00
STR092A-031			03/17/22	2,500.00	50.00	65.00	65.00
		WEIGHTED AVERAGE FOR THE FIRST QUARTER		11,730.00	39.06	63.79	48.29
STA0712-019		SH 71: Frieight Improvements	05/12/22	550.00	50.00	70.54	70.54
		WEIGHTED AVERAGE FOR THE SECOND QUARTER		550.00	50.00	70.54	70.54
NHPP0063-054		US 6 FROM I70-B TO 33 RD. (MP	08/18/22	1,000.00	50.00	109.11	67.00
BR0343-046		US 34 TIMBER BRIDGE REPL. PKG	08/31/22	600.00	35.10	51.36	51.36
FBR0343-047		US 6/US 34 TIMBER BRIDGE REPL					
		WEIGHTED AVERAGE FOR THE THIRD QUARTER		1,600.00	44.41	95.78	61.14
TRG0253-264		I-25 AND SH 119 PARK-N-RIDE	10/27/22	4,395.00	65.00	67.25	40.00
STU0252-457		I-25:ALAMEDA RIVER PH 2.0	11/03/22	1,180.00	80.00	108.17	139.00
2670703-487		I-70 BRIDGES OVER WARD ROAD-	12/01/22	5,938.00	78.09	62.39	34.00
		WEIGHTED AVERAGE FOR THE FOURTH QUARTER		11,513.00	73.29	63.02	46.50
		WEIGHTED AVERAGE FOR THE YEAR		25,393.00	55.15	63.93	48.44
=====	630-80377	Port Water Filled Barrier (Temp)		Lin Foot	=====		
NHPP0701-231		I-70 SALT WASH BRIDGES SCOUR	09/29/22	400.00	50.00	51.41	65.00
		WEIGHTED AVERAGE FOR THE THIRD QUARTER		400.00	50.00	51.41	65.00
		WEIGHTED AVERAGE FOR THE YEAR		400.00	50.00	51.41	65.00
=====	630-80378	Glare Screen (Temp)		Lin Foot	=====		
NHPP 0761-238		I-76 DAHLIA TO YORK	03/10/22	22,580.00	32.00	20.69	18.00

COLORADO DEPARTMENT OF TRANSPORTATION
 ITEM UNIT COSTS BY PROJECTS -- 2022 COST DATA

11:31 Wednesday, March 8, 2023 611

PROJECT NUMBER	ITEM NUMBER/ PROJECT LOCATION	ITEM DESCRIPTION/ PROJECT LOCATION	DATE LET	UNIT/ QUANTITY	ENGR. EST.	AVERAGE BID	AWARDED BID
=====	630-80378	Glare Screen (Temp)		Lin Foot	=====		
C0761-239							
	WEIGHTED AVERAGE FOR THE FIRST QUARTER			22,580.00	32.00	20.69	18.00
NHPP0702-413		VAIL PASS AUX PHASE 1 CAP 2	04/18/22	7,370.00	26.75	26.75	26.75
	WEIGHTED AVERAGE FOR THE SECOND QUARTER			7,370.00	26.75	26.75	26.75
2670703-487		I-70 BRIDGES OVER WARD ROAD-	12/01/22	1,200.00	50.00	31.18	22.00
	WEIGHTED AVERAGE FOR THE FOURTH QUARTER			1,200.00	50.00	27.18	20.53
	WEIGHTED AVERAGE FOR THE YEAR			31,150.00	31.45	21.51	20.20
=====	630-80380	Traffic Cone		Each	=====		
ITS0703-477		ITS EQUIPMENT UPGRADE AT EJMT	01/06/22	275.00	10.00	5.00	5.00
MTCE R500-218			01/06/22	300.00	5.00	5.00	5.00
NHPP2873-189		US 287 (FEDERAL BLVD) - COLFA	01/06/22	50.00	9.00	14.80	21.70
STR0505-050			01/13/22	225.00	10.00	18.33	25.00
NH0504-910		US50B L-24-B MIN REP AT MP 40	01/13/22	50.00	20.00	15.04	1.11
MTCER400-391		VARIOUS HIGHWAY SEGMENTS ACRO	01/13/22	300.00	6.00	7.50	5.00
NHPP0702-383		I-70 EB AUX FRISCO TO SILVERT	01/13/22	1,000.00	10.00	9.44	10.00
MTCER300-262			02/03/22	250.00	10.00	10.33	1.00
NHPP1601-083			02/03/22	300.00	10.00	27.06	22.00
STA0252-459			02/03/22	300.00	9.00	7.12	4.10
C0762-055			02/17/22	200.00	7.00	17.24	23.00
STR0141-031			02/17/22	300.00	15.00	12.00	16.00
STR133A-051			02/17/22	500.00	10.00	11.67	15.00
NHPP0063-063			02/24/22	300.00	10.00	16.40	17.00
STA 067A-048		Hwy 67A MP 0.00 TO MP 11.05 I	03/03/22	350.00	10.00	10.29	4.00
NHPP 0761-238		I-76 DAHLIA TO YORK	03/10/22	300.00	9.00	10.29	11.00
C0761-239							
NHPP0703-472			03/10/22	350.00	9.00	11.55	10.00
CR100-362			03/14/22	200.00	9.63	9.63	9.63
STR160A-034		US160A LA VETA PASS EAST SURF	03/17/22	220.00	5.00	9.13	13.26
BRC040-057			03/17/22	75.00	10.00	19.50	12.00
STR R500-171		Various locations on SH 141 a	03/17/22	90.00	9.00	7.18	5.00
M R100-351		FY22 R1 SIGN STRUCTURE REPLAC	03/17/22	600.00	12.00	9.00	11.00
STR092A-031			03/17/22	680.00	10.00	10.50	10.50

COLORADO DEPARTMENT OF TRANSPORTATION
ITEM UNIT COSTS BY PROJECTS -- 2022 COST DATA

11:31 Wednesday, March 8, 2023 612

PROJECT NUMBER	ITEM NUMBER/ PROJECT LOCATION	ITEM DESCRIPTION/ PROJECT LOCATION	DATE LET	UNIT/ QUANTITY	ENGR. EST.	AVERAGE BID	AWARDED BID
===== 630-80380 Traffic Cone Each =====							
MP0503-098			03/24/22	250.00	8.00	19.00	19.00
NHM765-007			03/31/22	200.00	20.00	21.77	28.50
C0703-499		EJMT GROUT BED REPAIR AND PAN	03/31/22	50.00	10.00	17.50	19.00
WEIGHTED AVERAGE FOR THE FIRST QUARTER				7,715.00	9.89	11.55	11.76
NH0504-911			04/07/22	400.00	11.95	12.00	12.00
CC030-081		ADA RAMP AND CURBS - FT. LUPT	04/14/22	100.00	10.00	16.73	10.00
NHPP0702-413		VAIL PASS AUX PHASE 1 CAP 2	04/18/22	288.00	16.05	16.05	16.05
MTCE2873-204		MTCE FY22 SH287 CONC PANEL RE	05/05/22	50.00	15.00	17.86	9.72
2670703-479		I-70 BRIDGE OVER HARLAN	05/05/22	100.00	10.00	16.08	18.25
ER0702-420		PR I-70 GWC MATERIAL FLOWS 20	05/06/22	200.00	11.00	19.00	18.00
STA0712-019		SH 71: Frieight Improvements	05/12/22	300.00	8.00	25.88	25.88
STA001A-005		SH1 WELLINGTON SOUTH RESURFAC	05/12/22	200.00	10.00	11.65	12.00
NHC540-017		R2 CHAINUP STA @ KENOSHA/HOOS	05/12/22	100.00	11.00	14.33	13.00
CM760-047		COLFAX AND QUAIL	05/12/22	50.00	10.00	11.00	3.00
NHPP 3851-018		US 385 NORTH OF CHEYENNE WELL	05/26/22	500.00	15.00	3.63	6.00
STAR100-358		3 STRUCTURES IN REGION 1 METR	05/26/22	200.00	20.00	10.99	16.00
C0852-120		Rehabilitation of Culvert by	05/26/22	50.00	13.00	20.00	20.00
FSA0702-409		I-70 VAIL WILDLIFE FENCE PHAS	05/26/22	500.00	15.00	15.00	15.00
ITS 0741-024		VMS SIGN INSTALLATIONS AND VS	06/02/22	100.00	20.00	22.50	20.00
FSA3921-019		SH 392 AND WCR 55 ISLANDS	06/02/22	100.00	10.00	2.77	3.00
NHPP072A-047		SH-72 RESURFACING: I-70 TO IN	06/09/22	300.00	10.00	20.96	20.96
MPR200-278		R2 - VARIOUS LOCATIONS	06/09/22	350.00	10.00	6.33	5.00
MPR200-279		FY 23 STENCIL MARKING PROJECT	06/09/22	150.00	10.00	6.67	5.00
MTCE0253-291		I-25 SIGN REPLACEMENT PHASE 2	06/16/22	200.00	15.00	21.10	10.20
WEIGHTED AVERAGE FOR THE SECOND QUARTER				4,238.00	12.74	12.36	13.16
MTCE 072A-045		SH 72B MP 37.00 TO MP 45.3 NE	07/07/22	500.00	10.00	2.50	2.50
MTCE0702-426		I70 FROM MP 155 TO 180 AND MP	07/07/22	660.00	10.00	4.50	3.00
MTCE300-272		REGION 3 ROUNDABOUT STRIPING	07/07/22	80.00	10.00	18.33	10.00
NHPP0702-414		VAIL PASS AUX PHASE 1 CAP 3	07/08/22	100.00	16.48	16.48	16.48
FBR0702-423		VAIL PASS AUX BE F-12-AT PHAS					
STR0711-022		SH 71 OVER THE ARKANSAS	08/04/22	100.00	11.00	12.50	2.50
NHPP0063-054		US 6 FROM I70-B TO 33 RD. (MP	08/18/22	300.00	15.00	13.57	1.25
FBR0761-236		I-76 OVER CLR CRK SCOUR MIT	08/25/22	250.00	9.00	11.67	10.00
C1211-099		SH 121 NORTH SGA SIGNALS	08/25/22	100.00	15.00	9.00	8.00
ER0502-092		US 50 MP 204 EB MONARCH TRUCK	08/29/22	100.00	10.00	17.73	11.52
BR0343-046		US 34 TIMBER BRIDGE REPL. PKG	08/31/22	120.00	6.91	6.90	6.90
FBR0343-047		US 6/US 34 TIMBER BRIDGE REPL					
PAN0761-245		ALONG I-76 & RAMPS MILEPOST 9	09/01/22	300.00	16.00	23.50	10.00

COLORADO DEPARTMENT OF TRANSPORTATION
 ITEM UNIT COSTS BY PROJECTS -- 2022 COST DATA

11:31 Wednesday, March 8, 2023 613

PROJECT NUMBER	ITEM NUMBER/ PROJECT LOCATION	ITEM DESCRIPTION/ PROJECT LOCATION	DATE LET	UNIT/ QUANTITY	ENGR. EST.	AVERAGE BID	AWARDED BID
=====	630-80380	Traffic Cone		Each	=====	=====	=====
ER0253-297		WCR 34 BRIDGE OVER I-25(MM 24	09/14/22	500.00	10.00	14.45	3.10
2670403-065		US40 FLOYD HILL ROUNDABOUTS	09/15/22	60.00	10.00	21.19	28.00
2670703-497		I-70 GENESEE WILDLIFE XING	09/15/22	200.00	10.00	20.70	20.45
SHE2873-193		US 287 & CO 52 INTERSECTION I	09/15/22	100.00	15.00	18.99	15.90
NHPP0701-231		I-70 SALT WASH BRIDGES SCOUR	09/29/22	100.00	30.00	6.41	2.00
		WEIGHTED AVERAGE FOR THE THIRD QUARTER		3,570.00	11.80	12.70	6.64
NHPP0821-114		SH 82 ASPEN/INDEPENDENCE PASS	10/13/22	200.00	15.00	2.37	1.10
C0831-126		SH83 EL PASO COUNTY TO BAYOU	10/13/22	100.00	10.00	14.00	18.00
NHPP0701-253		I-70 EAST OF DEBEQUE	10/27/22	200.00	10.00	10.15	10.00
STA207A-004		Resurfacing SH207A MANZANOLA	10/27/22	1,000.00	12.00	12.22	18.65
FSAM240-200		SH21B CO SPRINGS SIGNAL REPLA	10/27/22	50.00	11.00	24.00	24.00
C5502-111		US 550 MP 81 AND 89 RED MOUNT	10/27/22	60.00	10.00	1.60	2.00
STA3852-015		US 385 HOLYOKE NORTH	10/27/22	350.00	25.00	15.00	15.00
NHPP0343-048		US 34 (MP 169.3-171.4)	11/01/22	110.00	10.00	17.03	20.00
STU0252-457		I-25:ALAMEDA RIVER PH 2.0	11/03/22	200.00	15.00	22.10	16.60
STR064A-010		SH 64 AND SH 13 AT MEEKER	11/10/22	120.00	10.00	21.40	27.00
NHPP0853-126		US85C: PLATTEVILLE NORTH MP (11/10/22	260.00	8.00	11.56	11.00
C5502-097		US550 MP 117.28-126.06	11/17/22	300.00	12.00	22.14	27.00
MPR200-280		PUEBLO AREA	11/17/22	300.00	15.00	12.50	15.00
STAM420-001		US 285 AT HWY 9C IMPROVEMENTS	12/01/22	210.00	10.00	12.94	34.21
BR2854-148		INTERSECTION OF US 285 & SH 9					
STM0091-046		ADA RAMP IMPROVEMENTS - FAIRP					
STA0711-021		SH71: REGION LINE NORTH	12/01/22	600.00	9.30	8.08	4.00
STR114A-015		SH114 SILLSVILLE SOUTH TO MP3	12/01/22	400.00	10.00	7.00	4.00
2670703-487		I-70 BRIDGES OVER WARD ROAD-	12/01/22	500.00	20.00	16.78	17.00
NHPP0701-252		I-70 RIFLE TO SILT SLAB REPLA	12/01/22	100.00	10.00	34.00	35.00
IM025A-050		I25-MP103.9 - INTERSECTION DR	12/01/22	156.00	10.00	18.33	15.00
STR318A-001		SH 318 MP 0 - 12.5 MOFFAT COU	12/01/22	200.00	10.00	13.23	6.45
STR109A-019		M-22-AY BRIDGE REHAB ON SH109	12/01/22	50.00	20.00	10.04	18.81
NHPP0021-041		SH2 RESURFACING MLK TO 52ND	12/01/22	50.00	12.00	25.06	24.55
STR0641-107		SH 13 MM 104-128.1 IN MOFFAT	12/01/22	325.00	10.00	12.10	15.00
NHPP083A-046		SH83 RESURFACING STROH RD TO	12/08/22	600.00	10.00	18.47	18.93
NHPP0063-048		US6 / 20 ROAD INTERSECTION IM	12/15/22	200.00	15.00	15.97	10.00
NHM175-029		CANON CITY, CO	12/15/22	225.00	10.00	15.00	20.00
NHPP0931-033		SH93:US6 TO 58TH RESURFACING	12/15/22	300.00	10.00	23.10	35.90
NHPP0502-090		SH 50 MP 134.6-136 GUNNISON C	12/22/22	270.00	12.00	16.92	21.33
STR0092-024		SH 9 North of Silverthorne	12/22/22	400.00	10.00	15.60	16.20
STA0361-129		US 36: HYGIENE RD AND NELSON	12/22/22	150.00	12.00	17.93	27.45
BR012A-048		CO 12 STRUCTURE P-17-F AT MP	12/22/22	150.00	16.00	13.01	25.00
STA385A-016		SH 385 MP 97.76	12/22/22	100.00	10.00	18.03	11.11
STR096A-050		SH 96 MP 168.99 TO 193.77	12/22/22	350.00	10.00	13.33	4.00
		WEIGHTED AVERAGE FOR THE FOURTH QUARTER		8,586.00	12.19	14.49	16.05
		WEIGHTED AVERAGE FOR THE YEAR		24,109.00	11.49	12.99	12.87

COLORADO DEPARTMENT OF TRANSPORTATION
ITEM UNIT COSTS BY PROJECTS -- 2022 COST DATA

11:31 Wednesday, March 8, 2023 614

PROJECT NUMBER	ITEM NUMBER/ PROJECT LOCATION	ITEM DESCRIPTION/ PROJECT LOCATION	DATE LET	UNIT/ QUANTITY	ENGR. EST.	AVERAGE BID	AWARDED BID
===== 630-80384		Tubular Marker		Each			
NHPP0702-383		I-70 EB AUX FRISCO TO SILVERT	01/13/22	20.00	60.00	25.98	39.00
NHM765-007			03/31/22	100.00	50.00	89.10	96.90
		WEIGHTED AVERAGE FOR THE FIRST QUARTER		120.00	51.67	73.32	87.25
NH0504-911			04/07/22	400.00	25.66	35.90	35.80
STM1151-038		SH115 MP 27 TO MP 38	04/21/22	500.00	20.00	70.31	65.00
		WEIGHTED AVERAGE FOR THE SECOND QUARTER		900.00	22.52	61.97	52.02
STR0711-022		SH 71 OVER THE ARKANSAS	08/04/22	100.00	28.00	48.33	50.00
		WEIGHTED AVERAGE FOR THE THIRD QUARTER		100.00	28.00	48.33	50.00
STU0252-457		I-25:ALAMEDA RIVER PH 2.0	11/03/22	200.00	25.00	49.82	50.00
SHE0242-087		US 24 SAFETY IMPRVMENTS, E OF	11/03/22	30.00	30.00	50.57	59.72
		WEIGHTED AVERAGE FOR THE FOURTH QUARTER		230.00	25.65	49.92	51.27
		WEIGHTED AVERAGE FOR THE YEAR		1,350.00	26.05	60.29	54.88
===== 630-80385		Lane Divider (Temp)		Each			
NHPP0931-033		SH93:US6 TO 58TH RESURFACING	12/15/22	54.00	80.00	101.74	205.00
		WEIGHTED AVERAGE FOR THE FOURTH QUARTER		54.00	80.00	101.74	205.00
		WEIGHTED AVERAGE FOR THE YEAR		54.00	80.00	101.74	205.00
===== 630-80390		Channel Dev (Spec)		Each			
C0762-055			02/17/22	942.00	50.00	33.70	28.00
		WEIGHTED AVERAGE FOR THE FIRST QUARTER		942.00	50.00	33.70	28.00

COLORADO DEPARTMENT OF TRANSPORTATION
 ITEM UNIT COSTS BY PROJECTS -- 2022 COST DATA

11:31 Wednesday, March 8, 2023 615

PROJECT NUMBER	ITEM NUMBER/ PROJECT LOCATION	ITEM DESCRIPTION/ PROJECT LOCATION	DATE LET	UNIT/ QUANTITY	ENGR. EST.	AVERAGE BID	AWARDED BID
=====	630-80390	Channel Dev (Spec)		Each	=====	=====	=====
NHPP0701-231		I-70 SALT WASH BRIDGES SCOUR	09/29/22	100.00	30.00	65.52	50.00
		WEIGHTED AVERAGE FOR THE THIRD QUARTER		100.00	30.00	65.52	50.00
		WEIGHTED AVERAGE FOR THE YEAR		1,042.00	48.08	35.31	30.11
=====	630-80392	Stackable Tubular Marker		Each	=====	=====	=====
C0762-055			02/17/22	300.00	22.00	26.97	28.00
		WEIGHTED AVERAGE FOR THE FIRST QUARTER		300.00	22.00	26.97	28.00
		WEIGHTED AVERAGE FOR THE YEAR		300.00	22.00	26.97	28.00
=====	630-80393	Stackable Vertical Panels		Each	=====	=====	=====
MTCER400-391		VARIOUS HIGHWAY SEGMENTS ACRO	01/13/22	50.00	6.00	16.25	5.00
NHPP0703-472			03/10/22	100.00	38.00	27.60	20.00
CR100-362			03/14/22	50.00	26.75	26.75	26.75
BRC040-057			03/17/22	100.00	35.00	56.25	55.00
		WEIGHTED AVERAGE FOR THE FIRST QUARTER		300.00	29.79	36.31	30.29
NHPP0702-413		VAIL PASS AUX PHASE 1 CAP 2	04/18/22	25.00	21.40	21.40	21.40
STAR100-358		3 STRUCTURES IN REGION 1 METR	05/26/22	120.00	50.00	46.96	48.00
C0852-120		Rehabilitation of Culvert by	05/26/22	50.00	40.00	50.00	50.00
NHPP072A-047		SH-72 RESURFACING: I-70 TO IN	06/09/22	100.00	45.00	35.92	35.92
		WEIGHTED AVERAGE FOR THE SECOND QUARTER		295.00	44.19	43.99	41.99
MTCE 072A-045		SH 72B MP 37.00 TO MP 45.3 NE	07/07/22	60.00	15.00	8.00	8.00
NHPP0702-414		VAIL PASS AUX PHASE 1 CAP 3	07/08/22	100.00	27.47	27.47	27.47
FBR0702-423		VAIL PASS AUX BE F-12-AT PHAS					
FBR0761-236		I-76 OVER CLR CRK SCOUR MIT	08/25/22	25.00	38.00	34.00	40.00

COLORADO DEPARTMENT OF TRANSPORTATION
ITEM UNIT COSTS BY PROJECTS -- 2022 COST DATA

11:31 Wednesday, March 8, 2023 616

PROJECT NUMBER	ITEM NUMBER/ PROJECT LOCATION	ITEM DESCRIPTION/ PROJECT LOCATION	DATE LET	UNIT/ QUANTITY	ENGR. EST.	AVERAGE BID	AWARDED BID
=====	630-80393	Stackable Vertical Panels		Each	=====	=====	=====
C1211-099		SH 121 NORTH SGA SIGNALS	08/25/22	50.00	20.00	28.50	17.00
BR0343-046		US 34 TIMBER BRIDGE REPL. PKG	08/31/22	120.00	13.61	13.61	13.61
FBR0343-047		US 6/US 34 TIMBER BRIDGE REPL					
STAR100-374		5 STRUCTURES IN REGION 1	09/01/22	120.00	50.00	21.20	21.20
		WEIGHTED AVERAGE FOR THE THIRD QUARTER		475.00	27.85	22.27	19.48
NHPP0853-126		US85C: PLATTEVILLE NORTH MP (11/10/22	136.00	36.93	17.84	16.50
2670703-487		I-70 BRIDGES OVER WARD ROAD-	12/01/22	100.00	30.00	52.14	52.00
NHPP0063-048		US6 / 20 ROAD INTERSECTION IM	12/15/22	100.00	25.00	27.21	15.00
NHPP0931-033		SH93:US6 TO 58TH RESURFACING	12/15/22	50.00	50.00	45.91	66.65
		WEIGHTED AVERAGE FOR THE FOURTH QUARTER		386.00	33.74	32.73	31.80
		WEIGHTED AVERAGE FOR THE YEAR		1,456.00	33.12	33.69	29.54
=====	630-80401	Delin (Ty I) (Temp)		Each	=====	=====	=====
2670703-487		I-70 BRIDGES OVER WARD ROAD-	12/01/22	150.00	45.00	49.60	22.00
		WEIGHTED AVERAGE FOR THE FOURTH QUARTER		150.00	45.00	49.60	22.00
		WEIGHTED AVERAGE FOR THE YEAR		150.00	45.00	49.60	22.00
=====	630-80402	Delin (Ty II) (Temp)		Each	=====	=====	=====
2670703-487		I-70 BRIDGES OVER WARD ROAD-	12/01/22	75.00	20.00	56.02	33.00
		WEIGHTED AVERAGE FOR THE FOURTH QUARTER		75.00	20.00	56.02	33.00
		WEIGHTED AVERAGE FOR THE YEAR		75.00	20.00	56.02	33.00
=====	630-80403	Delin (Ty III) (Temp)		Each	=====	=====	=====
2670703-487		I-70 BRIDGES OVER WARD ROAD-	12/01/22	20.00	15.00	74.25	55.00
		WEIGHTED AVERAGE FOR THE FOURTH QUARTER		20.00	15.00	74.25	55.00
		WEIGHTED AVERAGE FOR THE YEAR		20.00	15.00	74.25	55.00

COLORADO DEPARTMENT OF TRANSPORTATION
 ITEM UNIT COSTS BY PROJECTS -- 2022 COST DATA

11:31 Wednesday, March 8, 2023 617

PROJECT NUMBER	ITEM NUMBER/ PROJECT LOCATION	ITEM DESCRIPTION/ PROJECT LOCATION	DATE LET	UNIT/ QUANTITY	ENGR. EST.	AVERAGE BID	AWARDED BID
=====	630-80415	Adv Warn Flash or Seq Panel (C Type)		Day	=====	=====	=====
M R100-351		FY22 R1 SIGN STRUCTURE REPLAC	03/17/22	40.00	130.00	69.00	90.00
		WEIGHTED AVERAGE FOR THE FIRST QUARTER		40.00	130.00	69.00	90.00
		WEIGHTED AVERAGE FOR THE YEAR		40.00	130.00	69.00	90.00
=====	630-80417	Seq Flashing Warning Light		Each	=====	=====	=====
STA0252-459			02/03/22	75.00	36.00	170.68	180.00
M R100-351		FY22 R1 SIGN STRUCTURE REPLAC	03/17/22	100.00	35.00	20.50	35.00
		WEIGHTED AVERAGE FOR THE FIRST QUARTER		175.00	35.43	100.01	97.14
ITS 0741-024		VMS SIGN INSTALLATIONS AND VS	06/02/22	100.00	50.00	62.25	27.50
		WEIGHTED AVERAGE FOR THE SECOND QUARTER		100.00	50.00	62.25	27.50
NHPP0701-231		I-70 SALT WASH BRIDGES SCOUR	09/29/22	30.00	150.00	98.62	100.00
		WEIGHTED AVERAGE FOR THE THIRD QUARTER		30.00	150.00	98.62	100.00
		WEIGHTED AVERAGE FOR THE YEAR		305.00	51.48	88.86	74.59
=====	630-80430	Rumble Strip (Port)		Each	=====	=====	=====
STA0712-019		SH 71: Frieght Improvements	05/12/22	12.00	1000.00	2587.63	2587.63
		WEIGHTED AVERAGE FOR THE SECOND QUARTER		12.00	1000.00	2587.63	2587.63
NHPP0502-090		SH 50 MP 134.6-136 GUNNISON C	12/22/22	36.00	2600.00	1625.24	2134.00
		WEIGHTED AVERAGE FOR THE FOURTH QUARTER		36.00	2600.00	1625.24	2134.00
		WEIGHTED AVERAGE FOR THE YEAR		48.00	2200.00	1685.39	2247.41

COLORADO DEPARTMENT OF TRANSPORTATION
ITEM UNIT COSTS BY PROJECTS -- 2022 COST DATA

11:31 Wednesday, March 8, 2023 618

PROJECT NUMBER	ITEM NUMBER/ PROJECT LOCATION	ITEM DESCRIPTION/ PROJECT LOCATION	DATE LET	UNIT/ QUANTITY	ENGR. EST.	AVERAGE BID	AWARDED BID
===== 630-80440		Port Rumble Strips (Temp)		Each	=====	=====	=====
NHPP1601-083			02/03/22	12.00	2050.00	1305.26	1200.00
STR133A-051			02/17/22	12.00	800.00	1353.33	1560.00
NHPP0063-063			02/24/22	36.00	1500.00	1327.50	1385.00
STR R500-171		Various locations on SH 141 a	03/17/22	6.00	1575.00	2305.15	4500.00
STR092A-031			03/17/22	12.00	1500.00	900.00	900.00
		WEIGHTED AVERAGE FOR THE FIRST QUARTER		78.00	1482.69	1406.91	1548.46
NHPP0063-054		US 6 FROM I70-B TO 33 RD. (MP	08/18/22	24.00	1000.00	1208.95	1900.00
NHPP0701-231		I-70 SALT WASH BRIDGES SCOUR	09/29/22	6.00	2000.00	2310.37	3000.00
		WEIGHTED AVERAGE FOR THE THIRD QUARTER		30.00	1200.00	1429.23	2120.00
STR114A-015		SH114 SILLSVILLE SOUTH TO MP3	12/01/22	12.00	2000.00	2225.00	2600.00
NHPP0063-048		US6 / 20 ROAD INTERSECTION IM	12/15/22	18.00	1500.00	1173.36	1100.00
		WEIGHTED AVERAGE FOR THE FOURTH QUARTER		30.00	1700.00	1460.01	1608.57
		WEIGHTED AVERAGE FOR THE YEAR		138.00	1468.48	1431.46	1679.60
===== 630-80511		Mobile Pvmt Marking Zone		LUMP SUM	=====	=====	=====
MTCE R500-219			01/06/22	1.00	70000.00	86666.67	60000.00
NHPP0702-383		I-70 EB AUX FRISCO TO SILVERT	01/13/22	1.00	7500.00	8598.83	11000.00
NHPP1601-083			02/03/22	1.00	5000.00	15655.53	12000.00
STR0141-031			02/17/22	1.00	10000.00	12166.67	8500.00
STR133A-051			02/17/22	1.00	10000.00	10000.00	10000.00
STA 067A-048		Hwy 67A MP 0.00 TO MP 11.05 I	03/03/22	1.00	3500.00	8319.42	6000.00
STR160A-034		US160A LA VETA PASS EAST SURF	03/17/22	1.00	20000.00	11024.63	11049.26
STR092A-031			03/17/22	1.00	10000.00	15000.00	15000.00
		WEIGHTED AVERAGE FOR THE FIRST QUARTER		8.00	17000.00	21036.94	16693.66
NH0504-911			04/07/22	1.00	10000.00	15645.00	11290.00
STM1151-038		SH115 MP 27 TO MP 38	04/21/22	1.00	10000.00	20491.59	5000.00

PROJECT NUMBER	ITEM NUMBER/ PROJECT LOCATION	ITEM DESCRIPTION/ PROJECT LOCATION	DATE LET	UNIT/ QUANTITY	ENGR. EST.	AVERAGE BID	AWARDED BID
=====	630-80511	Mobile Pvmt Marking Zone		LUMP SUM	=====	=====	=====
MTCE2873-204		MTCE FY22 SH287 CONC PANEL RE	05/05/22	1.00	10000.00	4581.44	5262.88
STA001A-005		SH1 WELLINGTON SOUTH RESURFAC	05/12/22	1.00	15000.00	8208.25	8000.00
		WEIGHTED AVERAGE FOR THE SECOND QUARTER		4.00	11250.00	14484.30	7388.22
MTCE 072A-045		SH 72B MP 37.00 TO MP 45.3 NE	07/07/22	1.00	3500.00	3000.00	3000.00
MTCER400-396		REGION 4	08/25/22	1.00	15000.00	15833.33	15000.00
2670703-497		I-70_GENESEE WILDLIFE KING	09/15/22	1.00	8000.00	7312.99	5679.44
		WEIGHTED AVERAGE FOR THE THIRD QUARTER		3.00	8833.33	9244.63	7893.15
MTCE0253-281		MTCE FY23 I-25 CONC PANEL REP	10/06/22	1.00	5000.00	6129.14	6050.00
SHE0242-087		US 24 SAFETY IMPRVMTS, E OF	11/03/22	1.00	2500.00	3644.03	3932.10
STR064A-010		SH 64 AND SH 13 AT MEEKER	11/10/22	1.00	15000.00	7640.00	10000.00
STAM420-001		US 285 AT HWY 9C IMPROVEMENTS	12/01/22	1.00	10000.00	13494.02	9276.07
BR2854-148		INTERSECTION OF US 285 & SH 9					
STM0091-046		ADA RAMP IMPROVEMENTS - FAIRP					
STR114A-015		SH114 SILLSVILLE SOUTH TO MP3	12/01/22	1.00	15000.00	13500.00	12000.00
STR318A-001		SH 318 MP 0 - 12.5 MOFFAT COU	12/01/22	1.00	15000.00	8195.00	5390.00
STR0641-107		SH 13 MM 104-128.1 IN MOFFAT	12/01/22	1.00	15000.00	9827.77	7500.00
STR096A-050		SH 96 MP 168.99 TO 193.77	12/22/22	1.00	10000.00	6366.67	5000.00
		WEIGHTED AVERAGE FOR THE FOURTH QUARTER		8.00	10937.50	8831.60	7631.82
		WEIGHTED AVERAGE FOR THE YEAR		23.00	12826.09	13361.88	10523.99
=====	630-80520	Mobile Pvmt Mkg Zone		Day	=====	=====	=====
C0762-055			02/17/22	2.00	1300.00	2592.70	2000.00
NHM765-007			03/31/22	8.00	1000.00	1627.64	228.00
		WEIGHTED AVERAGE FOR THE FIRST QUARTER		10.00	1060.00	1868.90	582.40
MPR200-278		R2 - VARIOUS LOCATIONS	06/09/22	97.00	650.00	150.00	100.00
		WEIGHTED AVERAGE FOR THE SECOND QUARTER		97.00	650.00	150.00	100.00
STA207A-004		Resurfacing SH207A MANZANOLA	10/27/22	12.00	1200.00	1415.00	495.00

COLORADO DEPARTMENT OF TRANSPORTATION
ITEM UNIT COSTS BY PROJECTS -- 2022 COST DATA

11:31 Wednesday, March 8, 2023 620

PROJECT NUMBER	ITEM NUMBER/ PROJECT LOCATION	ITEM DESCRIPTION/ PROJECT LOCATION	DATE LET	UNIT/ QUANTITY	ENGR. EST.	AVERAGE BID	AWARDED BID
===== 630-80520 Mobile Pymt Mkg Zone Day =====							
STA3852-015		US 385 HOLYOKE NORTH	10/27/22	2.00	3000.00	2750.00	2750.00
NHPP0853-126		US85C: PLATTEVILLE NORTH MP (11/10/22	4.00	1500.00	1641.10	1650.00
STA0711-021		SH71: REGION LINE NORTH	12/01/22	6.00	2000.00	566.67	600.00
	WEIGHTED AVERAGE FOR THE FOURTH QUARTER			24.00	1600.00	1308.71	901.67
	WEIGHTED AVERAGE FOR THE YEAR			131.00	855.34	508.56	283.69
===== 630-80560 Mobile Profilograph Oper Zone LUMP SUM =====							
NH0504-911			04/07/22	1.00	3000.00	7200.00	9400.00
	WEIGHTED AVERAGE FOR THE SECOND QUARTER			1.00	3000.00	7200.00	9400.00
	WEIGHTED AVERAGE FOR THE YEAR			1.00	3000.00	7200.00	9400.00
===== 630-85006 Impact Atten (Sand Fill) (Temp) Each =====							
ER0253-297		WCR 34 BRIDGE OVER I-25(MM 24	09/14/22	2.00	1850.00	4329.50	490.00
2670703-497		I-70_GENESEE WILDLIFE XING	09/15/22	2.00	4800.00	6897.70	5679.44
	WEIGHTED AVERAGE FOR THE THIRD QUARTER			4.00	3325.00	5963.81	3084.72
IM025A-050		I25-MP103.9 - INTERSECTION DR	12/01/22	6.00	7000.00	7733.33	4900.00
	WEIGHTED AVERAGE FOR THE FOURTH QUARTER			6.00	7000.00	7733.33	4900.00
	WEIGHTED AVERAGE FOR THE YEAR			10.00	5530.00	6760.10	4173.89
===== 630-85010 Impact Atten (Temp) Each =====							
NH0504-910		US50B L-24-B MIN REP AT MP 40	01/13/22	4.00	10000.00	7363.06	8444.44
NHPP0702-383		I-70 EB AUX FRISCO TO SILVERT	01/13/22	16.00	2500.00	9595.60	14400.00
NHPP1601-083			02/03/22	2.00	6000.00	8675.47	5000.00
C0762-055			02/17/22	4.00	6500.00	8372.76	8500.00
STR0141-031			02/17/22	4.00	10000.00	7166.67	8000.00
NHPP 0761-238		I-76 DAHLIA TO YORK	03/10/22	19.00	9000.00	8599.85	5000.00
C0761-239							
NHPP0703-472			03/10/22	1.00	4000.00	5714.07	6500.00

COLORADO DEPARTMENT OF TRANSPORTATION
 ITEM UNIT COSTS BY PROJECTS -- 2022 COST DATA

11:31 Wednesday, March 8, 2023 621

PROJECT NUMBER	ITEM NUMBER/ PROJECT LOCATION	ITEM DESCRIPTION/ PROJECT LOCATION	DATE LET	UNIT/ QUANTITY	ENGR. EST.	AVERAGE BID	AWARDED BID
=====	630-85010	Impact Atten (Temp)		Each =====			
STR160A-034		US160A LA VETA PASS EAST SURF	03/17/22	4.00	6000.00	3709.85	4419.70
STR R500-171		Various locations on SH 141 a	03/17/22	6.00	5600.00	7507.36	7500.00
M R100-351		FY22 R1 SIGN STRUCTURE REPLAC	03/17/22	5.00	6000.00	6408.00	3356.00
NHM765-007			03/31/22	4.00	11800.00	11260.95	9690.00
		WEIGHTED AVERAGE FOR THE FIRST QUARTER		69.00	6779.71	8482.72	8114.44
NHPP0702-413		VAIL PASS AUX PHASE 1 CAP 2	04/18/22	3.00	9362.50	9362.50	9362.50
STM1151-038		SH115 MP 27 TO MP 38	04/21/22	5.00	8500.00	7865.83	6800.00
2670703-479		I-70 BRIDGE OVER HARLAN	05/05/22	3.00	7000.00	14097.37	17353.06
STA0712-019		SH 71: Frieight Improvements	05/12/22	6.00	8000.00	7762.88	7762.88
FSA0702-409		I-70 VAIL WILDLIFE FENCE PHAS	05/26/22	2.00	8000.00	8000.00	8000.00
		WEIGHTED AVERAGE FOR THE SECOND QUARTER		19.00	8188.82	10019.69	9301.26
NHPP0702-414		VAIL PASS AUX PHASE 1 CAP 3	07/08/22	10.00	13047.68	13047.68	13047.68
FBR0702-423		VAIL PASS AUX BE F-12-AT PHAS					
FSA052A-057		SH52 BOX CULVERT EXTENSION (M	08/04/22	4.00	8000.00	3757.50	4125.55
NHPP0063-054		US 6 FROM I70-B TO 33 RD. (MP	08/18/22	2.00	3500.00	2471.47	3700.00
ER0502-092		US 50 MP 204 EB MONARCH TRUCK	08/29/22	2.00	10000.00	5523.08	8930.36
BR0343-046		US 34 TIMBER BRIDGE REPL. PKG	08/31/22	6.00	7276.00	8990.13	8990.13
FBR0343-047		US 6/US 34 TIMBER BRIDGE REPL					
2670403-065		US40 FLOYD HILL ROUNDABOUTS	09/15/22	2.00	10000.00	7820.22	7110.00
SHE2873-193		US 287 & CO 52 INTERSECTION I	09/15/22	4.00	5000.00	6433.12	5250.00
		WEIGHTED AVERAGE FOR THE THIRD QUARTER		30.00	9104.43	6968.35	8713.35
NHPP0701-253		I-70 EAST OF DEBEQUE	10/27/22	2.00	8000.00	4255.00	4200.00
NHPP0705-088		I-70 AGATE STRUCTURE REHAB	10/27/22	8.00	7500.00	6402.47	14200.00
C170A-002		CRITICAL CULVERT CONST. PKG D	10/27/22	2.00	8000.00	2940.28	1761.11
TRG0253-264		I-25 AND SH 119 PARK-N-RIDE	10/27/22	3.00	7500.00	9324.08	11800.00
NHPP0343-048		US 34 (MP 169.3-171.4)	11/01/22	2.00	5500.00	8055.55	4700.00
STU0252-457		I-25:ALAMEDA RIVER PH 2.0	11/03/22	16.00	10000.00	9175.97	14000.00
SHE0242-087		US 24 SAFETY IMPRVMENTS, E OF	11/03/22	2.00	8400.00	3791.34	5374.01
NHPP0853-126		US85C: PLATTEVILLE NORTH MP (11/10/22	4.00	7500.00	7903.00	8250.00
C5502-097		US550 MP 117.28-126.06	11/17/22	10.00	8000.00	7681.11	9720.00
STRC090-011		US 50B AND SH71/CR18 INTERSEC	11/17/22	5.00	6500.00	9775.00	12400.00
STAM420-001		US 285 AT HWY 9C IMPROVEMENTS	12/01/22	9.00	7500.00	6695.79	12493.16
BR2854-148		INTERSECTION OF US 285 & SH 9					

PROJECT NUMBER	ITEM NUMBER/ PROJECT LOCATION	ITEM DESCRIPTION/ PROJECT LOCATION	DATE LET	UNIT/ QUANTITY	ENGR. EST.	AVERAGE BID	AWARDED BID
===== 630-85010 Impact Atten (Temp) Each =====							
STM0091-046		ADA RAMP IMPROVEMENTS - FAIRP					
STA0711-021		SH71: REGION LINE NORTH	12/01/22	4.00	5500.00	5383.33	3000.00
2670703-487		I-70 BRIDGES OVER WARD ROAD-	12/01/22	8.00	18000.00	11339.02	12100.00
NHPP0701-252		I-70 RIFLE TO SILT SLAB REPLA	12/01/22	4.00	9000.00	7250.00	2000.00
IM025A-050		I25-MP103.9 - INTERSECTION DR	12/01/22	2.00	7000.00	7766.67	5000.00
NHPP0063-048		US6 / 20 ROAD INTERSECTION IM	12/15/22	2.00	10000.00	7981.09	7700.00
NHPP0931-033		SH93:US6 TO 58TH RESURFACING	12/15/22	1.00	8500.00	6112.11	14350.00
BR012A-048		CO 12 STRUCTURE P-17-F AT MP	12/22/22	4.00	6000.00	9053.44	10000.00
STA385A-016		SH 385 MP 97.76	12/22/22	4.00	8500.00	9347.22	8888.89
	WEIGHTED AVERAGE FOR THE FOURTH QUARTER			92.00	8856.52	8227.95	10220.35
	WEIGHTED AVERAGE FOR THE YEAR			210.00	8149.14	8348.73	9261.91
===== 630-85011 Imp Atten (Temp) Day =====							
STR064A-010		SH 64 AND SH 13 AT MEEKER	11/10/22	25.00	400.00	138.00	65.00
	WEIGHTED AVERAGE FOR THE FOURTH QUARTER			25.00	400.00	138.00	65.00
	WEIGHTED AVERAGE FOR THE YEAR			25.00	400.00	138.00	65.00
===== 630-85020 Mobile Attenuator Each =====							
ITS0703-477		ITS EQUIPMENT UPGRADE AT EJMT	01/06/22	2.00	70000.00	55700.00	55700.00
MTCE R500-218			01/06/22	1.00	5000.00	3875.00	2500.00
NHPP0702-383		I-70 EB AUX FRISCO TO SILVERT	01/13/22	2.00	70000.00	92555.92	56000.00
STR0141-031			02/17/22	1.00	20000.00	24333.33	21000.00
STA 067A-048		Hwy 67A MP 0.00 TO MP 11.05 I	03/03/22	2.00	30000.00	38590.22	32000.00
STR160A-034		US160A LA VETA PASS EAST SURF	03/17/22	2.00	30000.00	40098.53	44197.05
BRC040-057			03/17/22	3.00	25000.00	25216.50	25000.00
MP0503-098			03/24/22	2.00	30000.00	10225.00	7150.00
	WEIGHTED AVERAGE FOR THE FIRST QUARTER			15.00	37333.33	43096.34	32572.94
NH0504-911			04/07/22	4.00	5000.00	29950.00	29900.00
CC030-081		ADA RAMP AND CURBS - FT. LUPT	04/14/22	1.00	20000.00	34785.68	30000.00
NHC540-017		R2 CHAINUP STA @ KENOSHA/HOOS	05/12/22	3.00	10000.00	30666.67	27000.00
MPR200-279		FY 23 STENCIL MARKING PROJECT	06/09/22	2.00	10000.00	18866.67	100.00
	WEIGHTED AVERAGE FOR THE SECOND QUARTER			10.00	9000.00	28198.35	23080.00

COLORADO DEPARTMENT OF TRANSPORTATION
ITEM UNIT COSTS BY PROJECTS -- 2022 COST DATA

11:31 Wednesday, March 8, 2023 623

PROJECT NUMBER	ITEM NUMBER/ PROJECT LOCATION	ITEM DESCRIPTION/ PROJECT LOCATION	DATE LET	UNIT/ QUANTITY	ENGR. EST.	AVERAGE BID	AWARDED BID
===== 630-85020		Mobile Attenuator		Each	=====	=====	=====
NHPPR100-266		R1 ESSENTIAL REPAIRS	09/01/22	2.00	35000.00	100804.45	31813.36
PAN0761-245		ALONG I-76 & RAMPS MILEPOST 9	09/01/22	2.00	5000.00	39725.00	25000.00
SHE2873-193		US 287 & CO 52 INTERSECTION I	09/15/22	2.00	25000.00	42128.33	37100.00
		WEIGHTED AVERAGE FOR THE THIRD QUARTER		6.00	21666.67	57693.94	31304.45
STU0252-457		I-25:ALAMEDA RIVER PH 2.0	11/03/22	2.00	20000.00	93193.52	83000.00
NHPP0853-126		US85C: PLATTEVILLE NORTH MP (11/10/22	1.00	50000.00	84519.80	66000.00
MPR200-280		PUEBLO AREA	11/17/22	2.00	39000.00	38000.00	31000.00
STRC090-011		US 50B AND SH71/CR18 INTERSEC	11/17/22	2.00	30000.00	39125.00	43050.00
STR109A-019		M-22-AY BRIDGE REHAB ON SH109	12/01/22	2.00	30000.00	52772.29	48696.58
STR096A-050		SH 96 MP 168.99 TO 193.77	12/22/22	2.00	25700.00	32000.00	35000.00
		WEIGHTED AVERAGE FOR THE FOURTH QUARTER		11.00	30854.55	52023.14	46501.65
		WEIGHTED AVERAGE FOR THE YEAR		42.00	26652.38	45212.76	34627.64
===== 630-85040		Impact Atten (T-M-A) (Temp)		Each	=====	=====	=====
STR0505-050			01/13/22	2.00	8000.00	15500.00	10000.00
MTCER400-391		VARIOUS HIGHWAY SEGMENTS ACRO	01/13/22	2.00	7500.00	29375.00	1000.00
		WEIGHTED AVERAGE FOR THE FIRST QUARTER		4.00	7750.00	23428.57	5500.00
MTCE2873-204		MTCE FY22 SH287 CONC PANEL RE	05/05/22	2.00	20000.00	14960.20	13115.39
FSA0702-409		I-70 VAIL WILDLIFE FENCE PHAS	05/26/22	1.00	125000.00	120000.00	120000.00
		WEIGHTED AVERAGE FOR THE SECOND QUARTER		3.00	55000.00	35968.16	48743.59
MTCE0702-426		I70 FROM MP 155 TO 180 AND MP	07/07/22	2.00	3000.00	785.00	40.00
		WEIGHTED AVERAGE FOR THE THIRD QUARTER		2.00	3000.00	785.00	40.00
MTCE0253-281		MTCE FY23 I-25 CONC PANEL REP	10/06/22	2.00	15000.00	25570.97	19370.00

COLORADO DEPARTMENT OF TRANSPORTATION
ITEM UNIT COSTS BY PROJECTS -- 2022 COST DATA

11:31 Wednesday, March 8, 2023 624

PROJECT NUMBER	ITEM NUMBER/ PROJECT LOCATION	ITEM DESCRIPTION/ PROJECT LOCATION	DATE LET	UNIT/ QUANTITY	ENGR. EST.	AVERAGE BID	AWARDED BID
===== 630-85040							
		Impact Atten (T-M-A) (Temp)		Each			
FSAM240-200		SH21B CO SPRINGS SIGNAL REPLA	10/27/22	2.00	40000.00	36337.50	30050.00
2670703-487		I-70 BRIDGES OVER WARD ROAD-	12/01/22	2.00	15000.00	87610.00	86300.00
NHM175-029		CANON CITY, CO	12/15/22	2.00	8000.00	32500.00	45000.00
	WEIGHTED AVERAGE FOR THE FOURTH QUARTER			8.00	19500.00	50045.59	45180.00
	WEIGHTED AVERAGE FOR THE YEAR			17.00	21058.82	35359.45	31161.81
===== 630-85041							
		Mobile Attenuator		Day			
NHPP2873-189		US 287 (FEDERAL BLVD) - COLFA	01/06/22	25.00	550.00	1015.88	1364.02
MTCER300-262			02/03/22	150.00	180.00	1033.33	550.00
STA0252-459			02/03/22	185.00	900.00	745.83	820.50
C0762-055			02/17/22	30.00	500.00	1741.69	2000.00
NHPP0063-063			02/24/22	50.00	500.00	462.50	450.00
NHPP 0761-238		I-76 DAHLIA TO YORK	03/10/22	200.00	800.00	575.68	510.00
C0761-239							
NHPP0703-472			03/10/22	80.00	320.00	1045.80	1000.00
CR100-362			03/14/22	240.00	535.00	535.00	535.00
M R100-351		FY22 R1 SIGN STRUCTURE REPLAC	03/17/22	50.00	620.00	798.50	696.00
C0703-499		EJMT GROUT BED REPAIR AND PAN	03/31/22	40.00	800.00	1380.50	1065.00
	WEIGHTED AVERAGE FOR THE FIRST QUARTER			1,050.00	594.52	766.77	703.52
NHPP0702-413		VAIL PASS AUX PHASE 1 CAP 2	04/18/22	60.00	856.00	856.00	856.00
2670703-479		I-70 BRIDGE OVER HARLAN	05/05/22	1.00	450.00	936.21	1094.82
ER0702-420		PR I-70 GWC MATERIAL FLOWS 20	05/06/22	250.00	550.00	1037.50	1025.00
NHPP 3851-018		US 385 NORTH OF CHEYENNE WELL	05/26/22	5.00	600.00	1800.00	3000.00
STAR100-358		3 STRUCTURES IN REGION 1 METR	05/26/22	91.00	650.00	755.91	1007.00
ITS 0741-024		VMS SIGN INSTALLATIONS AND VS	06/02/22	115.00	750.00	1242.00	1650.00
NHPP072A-047		SH-72 RESURFACING: I-70 TO IN	06/09/22	105.00	800.00	598.72	598.72
MPR200-278		R2 - VARIOUS LOCATIONS	06/09/22	15.00	600.00	243.33	100.00
MTCE0253-291		I-25 SIGN REPLACEMENT PHASE 2	06/16/22	80.00	550.00	774.67	736.33
NHPP0252-448		I-25 TREX NARROWS BRIDGE PREV	06/23/22	16.00	800.00	918.25	900.00
	WEIGHTED AVERAGE FOR THE SECOND QUARTER			738.00	660.58	923.80	1006.46
NHPP0702-414		VAIL PASS AUX PHASE 1 CAP 3	07/08/22	100.00	933.82	933.82	933.82
FBR0702-423		VAIL PASS AUX BE F-12-AT PHAS					
C1211-099		SH 121 NORTH SGA SIGNALS	08/25/22	70.00	640.00	547.50	245.00

COLORADO DEPARTMENT OF TRANSPORTATION
ITEM UNIT COSTS BY PROJECTS -- 2022 COST DATA

11:31 Wednesday, March 8, 2023 625

PROJECT NUMBER	ITEM NUMBER/ PROJECT LOCATION	ITEM DESCRIPTION/ PROJECT LOCATION	DATE LET	UNIT/ QUANTITY	ENGR. EST.	AVERAGE BID	AWARDED BID
===== 630-85041 Mobile Attenuator Day =====							
STAR100-374		5 STRUCTURES IN REGION 1	09/01/22	113.00	1000.00	802.97	802.97
ER0253-297		WCR 34 BRIDGE OVER I-25(MM 24	09/14/22	60.00	350.00	1273.04	900.00
NHPP0701-231		I-70 SALT WASH BRIDGES SCOUR	09/29/22	85.00	1100.00	721.71	525.00
	WEIGHTED AVERAGE FOR THE THIRD QUARTER			428.00	854.40	903.00	700.68
NHPP0821-114		SH 82 ASPEN/INDEPENDENCE PASS	10/13/22	5.00	2000.00	922.33	917.00
NHPP0701-253		I-70 EAST OF DEBEQUE	10/27/22	30.00	900.00	797.00	825.00
STA207A-004		Resurfacing SH207A MANZANOLA	10/27/22	4.00	35000.00	1433.33	1550.00
SHE0242-087		US 24 SAFETY IMPRVMENTS, E OF	11/03/22	20.00	700.00	1077.69	1433.07
STAM420-001		US 285 AT HWY 9C IMPROVEMENTS	12/01/22	30.00	550.00	798.93	998.72
BR2854-148		INTERSECTION OF US 285 & SH 9					
STM0091-046		ADA RAMP IMPROVEMENTS - FAIRP					
NHPP0701-252		I-70 RIFLE TO SILT SLAB REPLA	12/01/22	300.00	1000.00	825.00	700.00
IM025A-050		I25-MP103.9 - INTERSECTION DR	12/01/22	20.00	550.00	883.33	1500.00
NHPP0021-041		SH2 RESURFACING MLK TO 52ND	12/01/22	25.00	1000.00	1170.84	1129.42
NHPP083A-046		SH83 RESURFACING STROH RD TO	12/08/22	60.00	550.00	1316.83	1333.66
NHPP0931-033		SH93:US6 TO 58TH RESURFACING	12/15/22	100.00	750.00	1140.68	820.00
	WEIGHTED AVERAGE FOR THE FOURTH QUARTER			594.00	1096.80	981.75	882.85
	WEIGHTED AVERAGE FOR THE YEAR			2,810.00	757.63	856.25	820.56
===== 630-86801 Traffic Signal (Temp) LUMP SUM =====							
MTCE2873-204		MTCE FY22 SH287 CONC PANEL RE	05/05/22	1.00	82000.00	11960.31	8420.61
	WEIGHTED AVERAGE FOR THE SECOND QUARTER			1.00	82000.00	11960.31	8420.61
NHPP0063-054		US 6 FROM I70-B TO 33 RD. (MP	08/18/22	1.00	20000.00	95532.77	95000.00
	WEIGHTED AVERAGE FOR THE THIRD QUARTER			1.00	20000.00	95532.77	95000.00
STU0252-457		I-25:ALAMEDA RIVER PH 2.0	11/03/22	1.00	100000.00	167447.43	198000.00
BR012A-048		CO 12 STRUCTURE P-17-F AT MP	12/22/22	1.00	50000.00	38626.95	36000.00
	WEIGHTED AVERAGE FOR THE FOURTH QUARTER			2.00	75000.00	115919.24	117000.00
	WEIGHTED AVERAGE FOR THE YEAR			4.00	63000.00	88286.93	84355.15

COLORADO DEPARTMENT OF TRANSPORTATION
ITEM UNIT COSTS BY PROJECTS -- 2022 COST DATA

11:31 Wednesday, March 8, 2023 626

PROJECT NUMBER	ITEM NUMBER/ PROJECT LOCATION	ITEM DESCRIPTION/ PROJECT LOCATION	DATE LET	UNIT/ QUANTITY	ENGR. EST.	AVERAGE BID	AWARDED BID
===== 630-86810		Traffic Signal (Temp)		Each	=====	=====	=====
NHPP1601-083			02/03/22	1.00	30000.00	39780.84	50000.00
STR R500-171		Various locations on SH 141 a	03/17/22	3.00	30000.00	18115.23	500.00
C0703-499		EJMT GROUT BED REPAIR AND PAN	03/31/22	2.00	75000.00	48625.00	45000.00
		WEIGHTED AVERAGE FOR THE FIRST QUARTER		6.00	45000.00	29139.92	23583.33
2670703-479		I-70 BRIDGE OVER HARLAN	05/05/22	1.00	65000.00	50711.64	52756.84
STA0712-019		SH 71: Frieight Improvements	05/12/22	3.00	12000.00	30016.48	30016.48
		WEIGHTED AVERAGE FOR THE SECOND QUARTER		4.00	25250.00	43813.25	35701.57
SHE2873-193		US 287 & CO 52 INTERSECTION I	09/15/22	1.00	20000.00	151946.11	135820.00
		WEIGHTED AVERAGE FOR THE THIRD QUARTER		1.00	20000.00	151946.11	135820.00
C170A-002		CRITICAL CULVERT CONST. PKG D	10/27/22	3.00	8000.00	4852.64	3955.56
STR064A-010		SH 64 AND SH 13 AT MEEKER	11/10/22	2.00	20000.00	6430.00	6000.00
STAM420-001		US 285 AT HWY 9C IMPROVEMENTS	12/01/22	1.00	15000.00	151739.44	43757.75
BR2854-148		INTERSECTION OF US 285 & SH 9					
STM0091-046		ADA RAMP IMPROVEMENTS - FAIRP					
STA0711-021		SH71: REGION LINE NORTH	12/01/22	4.00	29800.00	11833.33	12000.00
STR109A-019		M-22-AY BRIDGE REHAB ON SH109	12/01/22	1.00	100000.00	124166.50	159903.00
STA385A-016		SH 385 MP 97.76	12/22/22	1.00	30000.00	55388.89	50555.56
		WEIGHTED AVERAGE FOR THE FOURTH QUARTER		12.00	27350.00	34284.16	27173.58
		WEIGHTED AVERAGE FOR THE YEAR		23.00	31269.57	44792.54	32443.88
===== 630-88001		Work Zone Intrusion Alarm System		Day	=====	=====	=====
NHPP0063-063			02/24/22	115.00	100.00	123.50	120.00
		WEIGHTED AVERAGE FOR THE FIRST QUARTER		115.00	100.00	123.50	120.00
NHPP0701-231		I-70 SALT WASH BRIDGES SCOUR	09/29/22	45.00	130.00	164.58	5.00
		WEIGHTED AVERAGE FOR THE THIRD QUARTER		45.00	130.00	164.58	5.00
		WEIGHTED AVERAGE FOR THE YEAR		160.00	108.44	135.05	87.66

COLORADO DEPARTMENT OF TRANSPORTATION
ITEM UNIT COSTS BY PROJECTS -- 2022 COST DATA

11:31 Wednesday, March 8, 2023 627

PROJECT NUMBER	ITEM NUMBER/ PROJECT LOCATION	ITEM DESCRIPTION/ PROJECT LOCATION	DATE LET	UNIT/ QUANTITY	ENGR. EST.	AVERAGE BID	AWARDED BID
=====	632-00000	Night Work Lighting		LUMP SUM	=====		
NHPP2873-189		US 287 (FEDERAL BLVD) - COLFA	01/06/22	1.00	60000.00	57207.24	57724.44
NHPP0702-383		I-70 EB AUX FRISCO TO SILVERT	01/13/22	1.00	100000.00	75394.20	60000.00
STA0252-459			02/03/22	1.00	68036.37	118195.00	230225.00
NHPP0063-063			02/24/22	1.00	50000.00	150430.00	150000.00
NHPP 0761-238		I-76 DAHLIA TO YORK	03/10/22	1.00	144000.00	99956.98	80000.00
C0761-239							
NHPP0703-472			03/10/22	1.00	30000.00	49728.14	55000.00
BRC040-057			03/17/22	1.00	30000.00	81125.00	79000.00
M R100-351		FY22 R1 SIGN STRUCTURE REPLAC	03/17/22	1.00	12500.00	29364.50	9009.00
C0703-499		EJMT GROUT BED REPAIR AND PAN	03/31/22	1.00	75000.00	47350.00	22000.00
		WEIGHTED AVERAGE FOR THE FIRST QUARTER		9.00	63281.82	80521.83	82550.94
2670703-479		I-70 BRIDGE OVER HARLAN	05/05/22	1.00	20000.00	62372.60	42681.59
ER0702-420		PR I-70 GWC MATERIAL FLOWS 20	05/06/22	1.00	20000.00	33500.00	7000.00
NHPP072A-047		SH-72 RESURFACING: I-70 TO IN	06/09/22	1.00	45000.00	16670.93	16670.93
MTCE0253-291		I-25 SIGN REPLACEMENT PHASE 2	06/16/22	1.00	15000.00	9440.41	15635.82
NHPP0252-448		I-25 TREX NARROWS BRIDGE PREV	06/23/22	1.00	10000.00	24185.00	5000.00
		WEIGHTED AVERAGE FOR THE SECOND QUARTER		5.00	22000.00	38235.16	17397.67
NHPP0063-054		US 6 FROM I70-B TO 33 RD. (MP	08/18/22	1.00	100000.00	37421.45	50000.00
C1211-099		SH 121 NORTH SGA SIGNALS	08/25/22	1.00	7150.00	19250.00	20000.00
BR0343-046		US 34 TIMBER BRIDGE REPL. PKG	08/31/22	1.00	12339.24	8834.99	8834.99
FBR0343-047		US 6/US 34 TIMBER BRIDGE REPL					
		WEIGHTED AVERAGE FOR THE THIRD QUARTER		3.00	32957.12	21835.48	21917.50
STU0252-457		I-25:ALAMEDA RIVER PH 2.0	11/03/22	1.00	100000.00	43356.44	28100.00
2670703-487		I-70 BRIDGES OVER WARD ROAD-	12/01/22	1.00	50000.00	84930.71	87400.00
NHPP0701-252		I-70 RIFLE TO SILT SLAB REPLA	12/01/22	1.00	50000.00	83000.00	151000.00
IM025A-050		I25-MP103.9 - INTERSECTION DR	12/01/22	1.00	20000.00	39133.33	38900.00
NHPP0021-041		SH2 RESURFACING MLK TO 52ND	12/01/22	1.00	40000.00	51814.16	23815.53
NHPP083A-046		SH83 RESURFACING STROH RD TO	12/08/22	1.00	50000.00	25349.68	20699.36
NHPP0063-048		US6 / 20 ROAD INTERSECTION IM	12/15/22	1.00	75000.00	64249.43	21000.00
NHM175-029		CANON CITY, CO	12/15/22	1.00	20000.00	21000.00	7000.00
NHPP0931-033		SH93:US6 TO 58TH RESURFACING	12/15/22	1.00	35000.00	39452.08	3585.00
		WEIGHTED AVERAGE FOR THE FOURTH QUARTER		9.00	48888.89	54098.08	40649.99
		WEIGHTED AVERAGE FOR THE YEAR		26.00	46346.85	59403.63	47289.88

COLORADO DEPARTMENT OF TRANSPORTATION
ITEM UNIT COSTS BY PROJECTS -- 2022 COST DATA

11:31 Wednesday, March 8, 2023 628

PROJECT NUMBER	ITEM NUMBER/ PROJECT LOCATION	ITEM DESCRIPTION/ PROJECT LOCATION	DATE LET	UNIT/ QUANTITY	ENGR. EST.	AVERAGE BID	AWARDED BID
=====	641-10000	Shotcrete		Sq Yard	=====		
NHC540-017		R2 CHAINUP STA @ KENOSHA/HOOS	05/12/22	428.00	126.00	473.33	470.00
	WEIGHTED AVERAGE FOR THE SECOND QUARTER			428.00	126.00	473.33	470.00
	WEIGHTED AVERAGE FOR THE YEAR			428.00	126.00	473.33	470.00
=====	641-10010	Initial Shotcrete Facing		Sq Foot	=====		
NHPP0702-413		VAIL PASS AUX PHASE 1 CAP 2	04/18/22	23,934.00	17.58	17.58	17.58
	WEIGHTED AVERAGE FOR THE SECOND QUARTER			23,934.00	17.58	17.58	17.58
NHPP0702-414 FBR0702-423 2670403-065		VAIL PASS AUX PHASE 1 CAP 3	07/08/22	49,623.00	21.30	21.30	21.30
		VAIL PASS AUX BE F-12-AT PHAS					
		US40_FLOYD HILL ROUNDABOUTS	09/15/22	9,885.00	20.00	33.48	22.00
	WEIGHTED AVERAGE FOR THE THIRD QUARTER			59,508.00	21.08	25.85	21.42
	WEIGHTED AVERAGE FOR THE YEAR			83,442.00	20.08	23.94	20.32
=====	641-10070	Shotcrete Sculpting		Sq Yard	=====		
2670403-065		US40_FLOYD HILL ROUNDABOUTS	09/15/22	1,130.00	250.00	157.81	237.00
	WEIGHTED AVERAGE FOR THE THIRD QUARTER			1,130.00	250.00	157.81	237.00
	WEIGHTED AVERAGE FOR THE YEAR			1,130.00	250.00	157.81	237.00
=====	641-11000	Shotcrete (CL A)		Cubic Yard	=====		
NHPP0702-413		VAIL PASS AUX PHASE 1 CAP 2	04/18/22	754.00	1027.20	1027.20	1027.20
	WEIGHTED AVERAGE FOR THE SECOND QUARTER			754.00	1027.20	1027.20	1027.20
NHPP0702-414		VAIL PASS AUX PHASE 1 CAP 3	07/08/22	1,454.00	979.11	979.11	979.11

COLORADO DEPARTMENT OF TRANSPORTATION
 ITEM UNIT COSTS BY PROJECTS -- 2022 COST DATA

11:31 Wednesday, March 8, 2023 629

PROJECT NUMBER	ITEM NUMBER/ PROJECT LOCATION	ITEM DESCRIPTION/ PROJECT LOCATION	DATE LET	UNIT/ QUANTITY	ENGR. EST.	AVERAGE BID	AWARDED BID
=====	641-11000	Shotcrete (CL A)		Cubic Yard	=====		
FBR0702-423		VAIL PASS AUX BE F-12-AT PHAS					
	WEIGHTED AVERAGE FOR THE THIRD QUARTER			1,454.00	979.11	979.11	979.11
	WEIGHTED AVERAGE FOR THE YEAR			2,208.00	995.53	995.53	995.53
=====	641-11003	Shotcrete (CL D)		Cubic Yard	=====		
2670403-065		US40_FLOYD HILL ROUNDABOUTS	09/15/22	520.00	900.00	646.21	520.00
	WEIGHTED AVERAGE FOR THE THIRD QUARTER			520.00	900.00	646.21	520.00
	WEIGHTED AVERAGE FOR THE YEAR			520.00	900.00	646.21	520.00
=====	641-11006	Shotcrete (Smooth) (Suppl)		Cubic Yard	=====		
NHPP0702-414		VAIL PASS AUX PHASE 1 CAP 3	07/08/22	81.00	1001.81	1001.81	1001.81
FBR0702-423		VAIL PASS AUX BE F-12-AT PHAS					
	WEIGHTED AVERAGE FOR THE THIRD QUARTER			81.00	1001.81	1001.81	1001.81
	WEIGHTED AVERAGE FOR THE YEAR			81.00	1001.81	1001.81	1001.81
=====	642-00010	Exploder (Ty 1) (Install)		Each	=====		
C5502-111		US 550 MP 81 AND 89 RED MOUNT	10/27/22	2.00	60000.00	27250.00	21000.00
	WEIGHTED AVERAGE FOR THE FOURTH QUARTER			2.00	60000.00	27250.00	21000.00
	WEIGHTED AVERAGE FOR THE YEAR			2.00	60000.00	27250.00	21000.00
=====	642-00020	Exploder (Ty 2) (Install)		Each	=====		
C5502-111		US 550 MP 81 AND 89 RED MOUNT	10/27/22	3.00	20000.00	20500.00	17000.00
	WEIGHTED AVERAGE FOR THE FOURTH QUARTER			3.00	20000.00	20500.00	17000.00
	WEIGHTED AVERAGE FOR THE YEAR			3.00	20000.00	20500.00	17000.00
=====	642-00030	Cntrl Shelter (Ty 1) (Install)		Each	=====		
C5502-111		US 550 MP 81 AND 89 RED MOUNT	10/27/22	1.00	30000.00	22500.00	14000.00
	WEIGHTED AVERAGE FOR THE FOURTH QUARTER			1.00	30000.00	22500.00	14000.00
	WEIGHTED AVERAGE FOR THE YEAR			1.00	30000.00	22500.00	14000.00

COLORADO DEPARTMENT OF TRANSPORTATION
ITEM UNIT COSTS BY PROJECTS -- 2022 COST DATA

11:31 Wednesday, March 8, 2023 630

PROJECT NUMBER	ITEM NUMBER/ PROJECT LOCATION	ITEM DESCRIPTION/ PROJECT LOCATION	DATE LET	UNIT/ QUANTITY	ENGR. EST.	AVERAGE BID	AWARDED BID
=====	700-70002	F/A ANTICIPATED CMO		Force Acct	=====		
NHPP0343-048		US 34 (MP 169.3-171.4)	.	1.00	644309.40	.	.
NHPP0701-252		I-70 RIFLE TO SILT SLAB REPLA	.	1.00	2419959.60	.	.
		WEIGHTED AVERAGE FOR THE FOURTH QUARTER		-----	2.00	1532134.50	.
		WEIGHTED AVERAGE FOR THE YEAR		=====	2.00	1532134.50	.
=====	700-70010	F/A Minor Contract Revisions		Force Acct	=====		
ITS0703-477		ITS EQUIPMENT UPGRADE AT EJMT	.	1.00	400000.00	.	.
MTCE R500-219			.	1.00	40000.00	.	.
MTCE R500-218			.	1.00	75000.00	.	.
NHPP2873-189		US 287 (FEDERAL BLVD) - COLFA	.	1.00	225000.00	.	.
STR0505-050			.	1.00	100000.00	.	.
NH0504-910		US50B I-24-B MIN REP AT MP 40	.	1.00	200000.00	.	.
MTCER400-391		VARIOUS HIGHWAY SEGMENTS ACRO	.	1.00	60000.00	.	.
NHPP0702-383		I-70 EB AUX FRISCO TO SILVERT	.	1.00	950000.00	.	.
MTCER300-262			.	1.00	40000.00	.	.
NHPP1601-083			.	1.00	400000.00	.	.
STA0252-459			.	1.00	200000.00	.	.
C0762-055			.	1.00	200000.00	.	.
STR0141-031			.	1.00	260000.00	.	.
STR133A-051			.	1.00	60000.00	.	.
NHPP0063-063			.	1.00	186000.00	.	.
STA 067A-048		Hwy 67A MP 0.00 TO MP 11.05 I	.	1.00	180000.00	.	.
NHPP 0761-238		I-76 DAHLIA TO YORK	.	2.00	550000.00	.	.
C0761-239			.			.	.
NHPP0703-472			.	1.00	650000.00	.	.
NHPP0253-275		I-25 EXPRESS LANES SEGMENT 5	.	1.00	5000.00	.	.
CR100-362			.	1.00	30000.00	.	.
ER007A-035			.	1.00	250000.00	.	.
STR160A-034		US160A LA VETA PASS EAST SURF	.	1.00	250000.00	.	.
BRC040-057			.	1.00	300000.00	.	.
STR R500-171		Various locations on SH 141 a	.	1.00	80000.00	.	.
M R100-351		FY22 R1 SIGN STRUCTURE REPLAC	.	1.00	75000.00	.	.
STR092A-031			.	1.00	125000.00	.	.
MP0503-098			.	1.00	40000.00	.	.
NHM765-007			.	1.00	500000.00	.	.
C0703-499		EJMT GROUT BED REPAIR AND PAN	.	1.00	100000.00	.	.
		WEIGHTED AVERAGE FOR THE FIRST QUARTER		-----	30.00	236033.33	.
NH0504-911			.	1.00	200000.00	.	.

PROJECT NUMBER	ITEM NUMBER/ PROJECT LOCATION	ITEM DESCRIPTION/ PROJECT LOCATION	DATE LET	UNIT/ QUANTITY	ENGR. EST.	AVERAGE BID	AWARDED BID
=====	700-70010	F/A Minor Contract Revisions		Force Acct	=====		
CC030-081		ADA RAMP AND CURBS - FT. LUPT .		1.00	200000.00	.	.
NHPP0702-413		VAIL PASS AUX PHASE 1 CAP 2 .		1.00	600000.00	.	.
STM1151-038		SH115 MP 27 TO MP 38 .		1.00	1300000.00	.	.
MTCE2873-204		MTCE FY22 SH287 CONC PANEL RE .		1.00	25000.00	.	.
2670703-479		I-70 BRIDGE OVER HARLAN .		1.00	700000.00	.	.
ER0702-420		PR I-70 GWC MATERIAL FLOWS 20 .		1.00	500000.00	.	.
STA0712-019		SH 71: Frieight Improvements .		1.00	500000.00	.	.
STA001A-005		SH1 WELLINGTON SOUTH RESURFAC .		1.00	75000.00	.	.
NHC540-017		R2 CHAINUP STA @ KENOSHA/HOOS .		1.00	200000.00	.	.
CM760-047		COLFAX AND QUAIL .		1.00	56900.00	.	.
NHPP 3851-018		US 385 NORTH OF CHEYENNE WELL .		1.00	800000.00	.	.
STAR100-358		3 STRUCTURES IN REGION 1 METR .		1.00	100000.00	.	.
C0852-120		Rehabilitation of Culvert by .		1.00	90000.00	.	.
FSA0702-409		I-70 VAIL WILDLIFE FENCE PHAS .		1.00	65000.00	.	.
ITS 0741-024		VMS SIGN INSTALLATIONS AND VS .		1.00	80000.00	.	.
FSA3921-019		SH 392 AND WCR 55 ISLANDS .		1.00	25000.00	.	.
NHPP072A-047		SH-72 RESURFACING: I-70 TO IN .		1.00	330000.00	.	.
FSA052A-046		SH52 WCR 37 INTERSECTION IMPR .		1.00	110000.00	.	.
MPR200-278		R2 - VARIOUS LOCATIONS .		1.00	100000.00	.	.
MPR200-279		FY 23 STENCIL MARKING PROJECT .		1.00	55000.00	.	.
MTCE0253-291		I-25 SIGN REPLACEMENT PHASE 2 .		1.00	75000.00	.	.
NHPP0252-448		I-25 TREX NARROWS BRIDGE PREV .		1.00	200000.00	.	.
MTCE R100-380		REGION 1 FY 23/24 PAVEMENT MA .		1.00	25000.00	.	.
	WEIGHTED AVERAGE FOR THE SECOND QUARTER			24.00	267162.50	.	.
MT CER300-273		I-70 MM 75-116, OTHER REGION .		1.00	25000.00	.	.
MTCE 072A-045		SH 72B MP 37.00 TO MP 45.3 NE .		1.00	25000.00	.	.
MTCE0702-426		I70 FROM MP 155 TO 180 AND MP .		1.00	20000.00	.	.
MT CER300-272		REGION 3 ROUNDABOUT STRIPING .		1.00	30000.00	.	.
NHPP0702-414		VAIL PASS AUX PHASE 1 CAP 3 .		2.00	475000.00	.	.
FBR0702-423		VAIL PASS AUX BE F-12-AT PHAS .				.	.
FSA052A-057		SH52 BOX CULVERT EXTENSION (M .		1.00	30000.00	.	.
STR0711-022		SH 71 OVER THE ARKANSAS .		1.00	15000.00	.	.
NHPP0063-054		US 6 FROM I70-B TO 33 RD. (MP .		1.00	400000.00	.	.
FBR0761-236		I-76 OVER CLR CRK SCOUR MIT .		1.00	200000.00	.	.
MT CER400-396		REGION 4 .		1.00	50000.00	.	.
C1211-099		SH 121 NORTH SGA SIGNALS .		1.00	290000.00	.	.
ER0502-092		US 50 MP 204 EB MONARCH TRUCK .		1.00	75000.00	.	.
BR0343-046		US 34 TIMBER BRIDGE REPL. PKG .		2.00	18100.00	.	.
FBR0343-047		US 6/US 34 TIMBER BRIDGE REPL .				.	.
STAR100-374		5 STRUCTURES IN REGION 1 .		1.00	100000.00	.	.
NHPPR100-266		R1 ESSENTIAL REPAIRS .		1.00	150000.00	.	.
PAN0761-245		ALONG I-76 & RAMPS MILEPOST 9 .		1.00	50000.00	.	.
ER0253-297		WCR 34 BRIDGE OVER I-25(MM 24 .		1.00	50000.00	.	.

COLORADO DEPARTMENT OF TRANSPORTATION
 ITEM UNIT COSTS BY PROJECTS -- 2022 COST DATA

11:31 Wednesday, March 8, 2023 632

PROJECT NUMBER	ITEM NUMBER/ PROJECT LOCATION	ITEM DESCRIPTION/ PROJECT LOCATION	DATE LET	UNIT/ QUANTITY	ENGR. EST.	AVERAGE BID	AWARDED BID
=====	700-70010	F/A Minor Contract Revisions		Force Acct	=====		
2670403-065		US40_FLOYD HILL ROUNDABOUTS .		1.00	300000.00	.	.
2670703-497		I-70_GENESEE WILDLIFE XING .		1.00	350000.00	.	.
SHE2873-193		US 287 & CO 52 INTERSECTION I .		1.00	210000.00	.	.
NHPP0701-231		I-70 SALT WASH BRIDGES SCOUR .		1.00	250000.00	.	.
		WEIGHTED AVERAGE FOR THE THIRD QUARTER		23.00	156791.30	.	.
MTCE0253-281		MTCE FY23 I-25 CONC PANEL REP .		1.00	20000.00	.	.
NHPP0821-114		SH 82 ASPEN/INDEPENDENCE PASS .		1.00	70000.00	.	.
C0831-126		SH83 EL PASO COUNTY TO BAYOU .		1.00	15000.00	.	.
NHPP0701-253		I-70 EAST OF DEBEQUE .		1.00	150000.00	.	.
STA207A-004		Resurfacing SH207A MANZANOLA .		1.00	200000.00	.	.
NHPP0705-088		I-70 AGATE STRUCTURE REHAB .		1.00	300000.00	.	.
FSAM240-200		SH21B CO SPRINGS SIGNAL REPLA .		1.00	90000.00	.	.
C5502-111		US 550 MP 81 AND 89 RED MOUNT .		1.00	40000.00	.	.
C170A-002		CRITICAL CULVERT CONST. PKG D .		1.00	45000.00	.	.
TRG0253-264		I-25 AND SH 119 PARK-N-RIDE .		1.00	1200000.00	.	.
STA3852-015		US 385 HOLYOKE NORTH .		1.00	200000.00	.	.
NHPP0343-048		US 34 (MP 169.3-171.4) .		1.00	200000.00	.	.
STU0252-457		I-25:ALAMEDA RIVER PH 2.0 .		1.00	1500000.00	.	.
SHE0242-087		US 24 SAFETY IMPRVMENTS, E OF .		1.00	40000.00	.	.
STR064A-010		SH 64 AND SH 13 AT MEEKER .		1.00	183000.00	.	.
NHPP0853-126		US85C: PLATTEVILLE NORTH MP (.		1.00	150000.00	.	.
C5502-097		US550 MP 117.28-126.06 .		1.00	500000.00	.	.
MPR200-280		PUEBLO AREA .		1.00	50000.00	.	.
STRC090-011		US 50B AND SH71/CR18 INTERSEC .		1.00	120000.00	.	.
STAM420-001		US 285 AT HWY 9C IMPROVEMENTS .		1.00	450000.00	.	.
BR2854-148		INTERSECTION OF US 285 & SH 9 .				.	.
STM0091-046		ADA RAMP IMPROVEMENTS - FAIRP .				.	.
STA0711-021		SH71: REGION LINE NORTH .		1.00	1000000.00	.	.
STR114A-015		SH114 SILLSVILLE SOUTH TO MP3 .		1.00	356000.00	.	.
2670703-487		I-70 BRIDGES OVER WARD ROAD- .		1.00	815000.00	.	.
NHPP0701-252		I-70 RIFLE TO SILT SLAB REPLA .		1.00	255000.00	.	.
IM025A-050		I25-MP103.9 - INTERSECTION DR .		1.00	400000.00	.	.
STR318A-001		SH 318 MP 0 - 12.5 MOFFAT COU .		1.00	188000.00	.	.
STR109A-019		M-22-AY BRIDGE REHAB ON SH109 .		1.00	175000.00	.	.
NHPP0021-041		SH2 RESURFACING MLK TO 52ND .		1.00	200000.00	.	.
STR0641-107		SH 13 MM 104-128.1 IN MOFFAT .		1.00	60000.00	.	.
NHPP083A-046		SH83 RESURFACING STROH RD TO .		1.00	175000.00	.	.
NHPP0063-048		US6 / 20 ROAD INTERSECTION IM .		1.00	90000.00	.	.
NHM175-029		CANON CITY, CO .		1.00	200000.00	.	.
FSA0853-122		WCR14.5 AND US-85, FORT LUPTO .		1.00	5000.00	.	.
NHPP0931-033		SH93:US6 TO 58TH RESURFACING .		1.00	360000.00	.	.
NHPP0502-090		SH 50 MP 134.6-136 GUNNISON C .		1.00	200000.00	.	.
STR0092-024		SH 9 North of Silverthorne .		1.00	300000.00	.	.

COLORADO DEPARTMENT OF TRANSPORTATION
ITEM UNIT COSTS BY PROJECTS -- 2022 COST DATA

11:31 Wednesday, March 8, 2023 633

PROJECT NUMBER	ITEM NUMBER/ PROJECT LOCATION	ITEM DESCRIPTION/ PROJECT LOCATION	DATE LET	UNIT/ QUANTITY	ENGR. EST.	AVERAGE BID	AWARDED BID
===== 700-70010 F/A Minor Contract Revisions Force Acct =====							
STA0361-129		US 36: HYGIENE RD AND NELSON .		1.00	275000.00	.	.
BR012A-048		CO 12 STRUCTURE P-17-F AT MP .		1.00	200000.00	.	.
STA385A-016		SH 385 MP 97.76 .		1.00	130000.00	.	.
STR096A-050		SH 96 MP 168.99 TO 193.77 .		1.00	300000.00	.	.
	WEIGHTED AVERAGE FOR THE FOURTH QUARTER			40.00	280175.00	.	.
	WEIGHTED AVERAGE FOR THE YEAR			117.00	241932.48	.	.
===== 700-70012 F/A Asph Pvmt Incentive Force Acct =====							
NHPP2873-189		US 287 (FEDERAL BLVD) - COLFA .		1.00	53100.00	.	.
NHPP0702-383		I-70 EB AUX FRISCO TO SILVERT .		1.00	15000.00	.	.
C0762-055			1.00	150000.00	.	.
STA 067A-048		Hwy 67A MP 0.00 TO MP 11.05 I .		1.00	71000.00	.	.
	WEIGHTED AVERAGE FOR THE FIRST QUARTER			4.00	72275.00	.	.
NHPP0702-413		VAIL PASS AUX PHASE 1 CAP 2 .		1.00	2100.00	.	.
STM1151-038		SH115 MP 27 TO MP 38 .		1.00	245000.00	.	.
2670703-479		I-70 BRIDGE OVER HARLAN .		1.00	22000.00	.	.
STA0712-019		SH 71: Frieght Improvements .		1.00	100000.00	.	.
STA001A-005		SH1 WELLINGTON SOUTH RESURFAC .		1.00	175000.00	.	.
NHC540-017		R2 CHAINUP STA @ KENOSHA/HOOS .		1.00	15000.00	.	.
NHPP072A-047		SH-72 RESURFACING: I-70 TO IN .		1.00	126000.00	.	.
FSA052A-046		SH52 WCR 37 INTERSECTION IMPR .		1.00	46498.05	.	.
	WEIGHTED AVERAGE FOR THE SECOND QUARTER			8.00	91449.76	.	.
NHPP0702-414		VAIL PASS AUX PHASE 1 CAP 3 .		2.00	4350.00	.	.
FBR0702-423		VAIL PASS AUX BE F-12-AT PHAS .		1.00	1000.00	.	.
FSA052A-057		SH52 BOX CULVERT EXTENSION (M .		2.00	6000.00	.	.
BR0343-046		US 34 TIMBER BRIDGE REPL. PKG .		1.00	9000.00	.	.
FBR0343-047		US 6/US 34 TIMBER BRIDGE REPL .		1.00	5300.00	.	.
2670403-065		US40 FLOYD HILL ROUNDABOUTS .		1.00	9000.00	.	.
SHE2873-193		US 287 & CO 52 INTERSECTION I .		1.00	5300.00	.	.
	WEIGHTED AVERAGE FOR THE THIRD QUARTER			7.00	5142.86	.	.
STA3852-015		US 385 HOLYOKE NORTH .		1.00	170000.00	.	.

COLORADO DEPARTMENT OF TRANSPORTATION
ITEM UNIT COSTS BY PROJECTS -- 2022 COST DATA

11:31 Wednesday, March 8, 2023 634

PROJECT NUMBER	ITEM NUMBER/ PROJECT LOCATION	ITEM DESCRIPTION/ PROJECT LOCATION	DATE LET	UNIT/ QUANTITY	ENGR. EST.	AVERAGE BID	AWARDED BID
===== 700-70012 F/A Asph Pmnt Incentive Force Acct =====							
NHPP0853-126		US85C: PLATTEVILLE NORTH MP (.		1.00	200000.00	.	.
STRC090-011		US 50B AND SH71/CR18 INTERSEC .		1.00	5000.00	.	.
2670703-487		I-70 BRIDGES OVER WARD ROAD- .		1.00	19000.00	.	.
IM025A-050		I25-MP103.9 - INTERSECTION DR .		1.00	7000.00	.	.
NHPP0021-041		SH2 RESURFACING MLK TO 52ND .		1.00	67108.00	.	.
NHPP083A-046		SH83 RESURFACING STROH RD TO .		1.00	61000.00	.	.
NHPP0931-033		SH93:US6 TO 58TH RESURFACING .		1.00	126000.00	.	.
STA0361-129		US 36: HYGIENE RD AND NELSON .		1.00	137665.00	.	.
	WEIGHTED AVERAGE FOR THE FOURTH QUARTER			9.00	88085.89	.	.
	WEIGHTED AVERAGE FOR THE YEAR			28.00	66052.54	.	.
===== 700-70013 F/A Conc Pmnt Incentive Force Acct =====							
NHPP 0761-238		I-76 DAHLIA TO YORK .		2.00	100000.00	.	.
C0761-239							
	WEIGHTED AVERAGE FOR THE FIRST QUARTER			2.00	100000.00	.	.
STM1151-038		SH115 MP 27 TO MP 38 .		1.00	293000.00	.	.
	WEIGHTED AVERAGE FOR THE SECOND QUARTER			1.00	293000.00	.	.
SHE2873-193		US 287 & CO 52 INTERSECTION I .		1.00	44000.00	.	.
	WEIGHTED AVERAGE FOR THE THIRD QUARTER			1.00	44000.00	.	.
2670703-487		I-70 BRIDGES OVER WARD ROAD- .		1.00	17000.00	.	.
IM025A-050		I25-MP103.9 - INTERSECTION DR .		1.00	1000.00	.	.
	WEIGHTED AVERAGE FOR THE FOURTH QUARTER			2.00	9000.00	.	.
	WEIGHTED AVERAGE FOR THE YEAR			6.00	92500.00	.	.
===== 700-70014 F/A Incentive Force Acct =====							
MTCE R500-219				1.00	15000.00	.	.

COLORADO DEPARTMENT OF TRANSPORTATION
ITEM UNIT COSTS BY PROJECTS -- 2022 COST DATA

11:31 Wednesday, March 8, 2023 635

PROJECT NUMBER	ITEM NUMBER/ PROJECT LOCATION	ITEM DESCRIPTION/ PROJECT LOCATION	DATE LET	UNIT/ QUANTITY	ENGR. EST.	AVERAGE BID	AWARDED BID
===== 700-70014 F/A Incentive Force Acct =====							
NHPP2873-189		US 287 (FEDERAL BLVD) - COLFA .		1.00	40000.00	.	.
BRC040-057		.		1.00	10000.00	.	.
	WEIGHTED AVERAGE FOR THE FIRST QUARTER			3.00	21666.67	.	.
NHC540-017		R2 CHAINUP STA @ KENOSHA/HOOS .		1.00	40000.00	.	.
MTCE R100-380		REGION 1 FY 23/24 PAVEMENT MA .		1.00	50000.00	.	.
	WEIGHTED AVERAGE FOR THE SECOND QUARTER			2.00	45000.00	.	.
ER0253-297		WCR 34 BRIDGE OVER I-25(MM 24 .		1.00	50000.00	.	.
	WEIGHTED AVERAGE FOR THE THIRD QUARTER			1.00	50000.00	.	.
	WEIGHTED AVERAGE FOR THE YEAR			6.00	34166.67	.	.
===== 700-70016 F/A Fuel Cost Adjustment Force Acct =====							
ITS0703-477		ITS EQUIPMENT UPGRADE AT EJMT .		1.00	1000.00	.	.
NHPP2873-189		US 287 (FEDERAL BLVD) - COLFA .		1.00	31000.00	.	.
NH0504-910		US50B L-24-B MIN REP AT MP 40 .		1.00	1000.00	.	.
NHPP0702-383		I-70 EB AUX FRISCO TO SILVERT .		1.00	50000.00	.	.
NHPP1601-083		.		1.00	50000.00	.	.
STA0252-459		.		1.00	5000.00	.	.
C0762-055		.		1.00	140000.00	.	.
STR0141-031		.		1.00	40000.00	.	.
STR133A-051		.		1.00	0.01	.	.
NHPP0063-063		.		1.00	46500.00	.	.
STA 067A-048		Hwy 67A MP 0.00 TO MP 11.05 I .		1.00	25000.00	.	.
NHPP 0761-238		I-76 DAHLIA TO YORK .		2.00	100000.00	.	.
C0761-239		.				.	.
NHPP0703-472		.		1.00	250.00	.	.
NHPP0253-275		I-25 EXPRESS LANES SEGMENT 5 .		1.00	1.00	.	.
ER007A-035		.		1.00	39000.00	.	.
STR160A-034		US160A LA VETA PASS EAST SURF .		1.00	45000.00	.	.
BRC040-057		.		1.00	5000.00	.	.
STR R500-171		Various locations on SH 141 a .		1.00	700.00	.	.
M R100-351		FY22 R1 SIGN STRUCTURE REPLAC .		1.00	100.00	.	.
STR092A-031		.		1.00	30000.00	.	.
NHM765-007		.		1.00	20000.00	.	.
	WEIGHTED AVERAGE FOR THE FIRST QUARTER			22.00	33161.41	.	.

COLORADO DEPARTMENT OF TRANSPORTATION
ITEM UNIT COSTS BY PROJECTS -- 2022 COST DATA

11:31 Wednesday, March 8, 2023 636

PROJECT NUMBER	ITEM NUMBER/ PROJECT LOCATION	ITEM DESCRIPTION/ PROJECT LOCATION	DATE LET	UNIT/ QUANTITY	ENGR. EST.	AVERAGE BID	AWARDED BID
=====	700-70016	F/A Fuel Cost Adjustment		Force Acct	=====		
NH0504-911				1.00	80787.00	.	.
NHPP0702-413		VAIL PASS AUX PHASE 1 CAP 2		1.00	150000.00	.	.
STM1151-038		SH115 MP 27 TO MP 38		1.00	10000.00	.	.
MTCE2873-204		MTCE FY22 SH287 CONC PANEL RE		1.00	2500.00	.	.
2670703-479		I-70 BRIDGE OVER HARLAN		1.00	15000.00	.	.
ER0702-420		PR I-70 GWC MATERIAL FLOWS 20		1.00	5000.00	.	.
STA0712-019		SH 71: Frieght Improvements		1.00	40000.00	.	.
STA001A-005		SH1 WELLINGTON SOUTH RESURFAC		1.00	100000.00	.	.
NHC540-017		R2 CHAINUP STA @ KENOSHA/HOOS		1.00	5000.00	.	.
CM760-047		COLFAX AND QUAIL		1.00	1000.00	.	.
NHPP 3851-018		US 385 NORTH OF CHEYENNE WELL		1.00	107000.00	.	.
FSA0702-409		I-70 VAIL WILDLIFE FENCE PHAS		1.00	2000.00	.	.
ITS 0741-024		VMS SIGN INSTALLATIONS AND VS		1.00	1000.00	.	.
FSA3921-019		SH 392 AND WCR 55 ISLANDS		1.00	500.00	.	.
NHPP072A-047		SH-72 RESURFACING: I-70 TO IN		1.00	30000.00	.	.
FSA052A-046		SH52 WCR 37 INTERSECTION IMPR		1.00	38683.63	.	.
MPR200-278		R2 - VARIOUS LOCATIONS		1.00	500.00	.	.
MPR200-279		FY 23 STENCIL MARKING PROJECT		1.00	500.00	.	.
MTCE R100-380		REGION 1 FY 23/24 PAVEMENT MA		1.00	500.00	.	.
		WEIGHTED AVERAGE FOR THE SECOND QUARTER		19.00	31051.09	.	.
FSA052A-057		SH52 BOX CULVERT EXTENSION (M		1.00	1000.00	.	.
NHPP0063-054		US 6 FROM I70-B TO 33 RD. (MP		1.00	70000.00	.	.
C1211-099		SH 121 NORTH SGA SIGNALS		1.00	10000.00	.	.
BR0343-046		US 34 TIMBER BRIDGE REPL. PKG		2.00	9500.00	.	.
FBR0343-047		US 6/US 34 TIMBER BRIDGE REPL				.	.
PAN0761-245		ALONG I-76 & RAMPS MILEPOST 9		1.00	500.00	.	.
2670403-065		US40 FLOYD HILL ROUNDABOUTS		1.00	33000.00	.	.
2670703-497		I-70 GENESEE WILDLIFE XING		1.00	20000.00	.	.
SHE2873-193		US 287 & CO 52 INTERSECTION I		1.00	19000.00	.	.
NHPP0701-231		I-70 SALT WASH BRIDGES SCOUR		1.00	30000.00	.	.
		WEIGHTED AVERAGE FOR THE THIRD QUARTER		10.00	20250.00	.	.
MTCE0253-281		MTCE FY23 I-25 CONC PANEL REP		1.00	0.01	.	.
NHPP0821-114		SH 82 ASPEN/INDEPENDENCE PASS		1.00	1500.00	.	.
C0831-126		SH83 EL PASO COUNTY TO BAYOU		1.00	4800.00	.	.

PROJECT NUMBER	ITEM NUMBER/ PROJECT LOCATION	ITEM DESCRIPTION/ PROJECT LOCATION	DATE LET	UNIT/ QUANTITY	ENGR. EST.	AVERAGE BID	AWARDED BID
=====	700-70016	F/A Fuel Cost Adjustment		Force Acct	=====		
NHPP0701-253		I-70 EAST OF DEBEQUE .		1.00	0.01	.	.
STA207A-004		Resurfacing SH207A MANZANOLA .		1.00	10000.00	.	.
NHPP0705-088		I-70 AGATE STRUCTURE REHAB .		1.00	0.01	.	.
FSAM240-200		SH21B CO SPRINGS SIGNAL REPLA .		1.00	1000.00	.	.
TRG0253-264		I-25 AND SH 119 PARK-N-RIDE .		1.00	40000.00	.	.
STA3852-015		US 385 HOLYOKE NORTH .		1.00	75000.00	.	.
NHPP0343-048		US 34 (MP 169.3-171.4) .		1.00	1000.00	.	.
STU0252-457		I-25:ALAMEDA RIVER PH 2.0 .		1.00	25000.00	.	.
SHE0242-087		US 24 SAFETY IMPRVMENTS, E OF .		1.00	2000.00	.	.
STR064A-010		SH 64 AND SH 13 AT MEEKER .		1.00	45750.00	.	.
NHPP0853-126		US85C: PLATTEVILLE NORTH MP (.		1.00	150000.00	.	.
C5502-097		US550 MP 117.28-126.06 .		1.00	15000.00	.	.
STRC090-011		US 50B AND SH71/CR18 INTERSEC .		1.00	10000.00	.	.
STAM420-001		US 285 AT HWY 9C IMPROVEMENTS .		1.00	56000.00	.	.
BR2854-148		INTERSECTION OF US 285 & SH 9 .				.	.
STM0091-046		ADA RAMP IMPROVEMENTS - FAIRP .				.	.
STA0711-021		SH71: REGION LINE NORTH .		1.00	190428.57	.	.
STR114A-015		SH114 SILLSVILLE SOUTH TO MP3 .		1.00	25000.00	.	.
2670703-487		I-70 BRIDGES OVER WARD ROAD- .		1.00	20000.00	.	.
NHPP0701-252		I-70 RIFLE TO SILT SLAB REPLA .		1.00	65000.00	.	.
IM025A-050		I25-MP103.9 - INTERSECTION DR .		1.00	50000.00	.	.
STR318A-001		SH 318 MP 0 - 12.5 MOFFAT COU .		1.00	47000.00	.	.
STR109A-019		M-22-AY BRIDGE REHAB ON SH109 .		1.00	1000.00	.	.
NHPP0021-041		SH2 RESURFACING MLK TO 52ND .		1.00	10000.00	.	.
STR0641-107		SH 13 MM 104-128.1 IN MOFFAT .		1.00	15000.00	.	.
NHPP083A-046		SH83 RESURFACING STROH RD TO .		1.00	20000.00	.	.
NHPP0063-048		US6 / 20 ROAD INTERSECTION IM .		1.00	21500.00	.	.
FSA0853-122		WCRI4.5 AND US-85, FORT LUPTO .		1.00	1000.00	.	.
NHPP0931-033		SH93:US6 TO 58TH RESURFACING .		1.00	30000.00	.	.
NHPP0502-090		SH 50 MP 134.6-136 GUNNISON C .		1.00	15000.00	.	.
STR0092-024		SH 9 North of Silverthorne .		1.00	41500.00	.	.
STA0361-129		US 36: HYGIENE RD AND NELSON .		1.00	28000.00	.	.
BR012A-048		CO 12 STRUCTURE P-17-F AT MP .		1.00	3600.00	.	.
STA385A-016		SH 385 MP 97.76 .		1.00	25000.00	.	.
STR096A-050		SH 96 MP 168.99 TO 193.77 .		1.00	55500.00	.	.
		WEIGHTED AVERAGE FOR THE FOURTH QUARTER		36.00	30599.41	.	.
		WEIGHTED AVERAGE FOR THE YEAR		87.00	30156.32	.	.
=====	700-70018	F/A Road Smooth Incentive		Force Acct	=====		
NHPP2873-189		US 287 (FEDERAL BLVD) - COLFA .		1.00	90910.00	.	.
NHPP0702-383		I-70 EB AUX FRISCO TO SILVERT .		1.00	100000.00	.	.
NHPP1601-083				1.00	150000.00	.	.
C0762-055				1.00	125000.00	.	.

COLORADO DEPARTMENT OF TRANSPORTATION
ITEM UNIT COSTS BY PROJECTS -- 2022 COST DATA

11:31 Wednesday, March 8, 2023 638

PROJECT NUMBER	ITEM NUMBER/ PROJECT LOCATION	ITEM DESCRIPTION/ PROJECT LOCATION	DATE LET	UNIT/ QUANTITY	ENGR. EST.	AVERAGE BID	AWARDED BID
=====	700-70018	F/A Road Smooth Incentive		Force Acct	=====		
STR0141-031			.	1.00	50000.00	.	.
NHPP0063-063			.	1.00	53500.00	.	.
STA 067A-048		Hwy 67A MP 0.00 TO MP 11.05 I	.	1.00	159000.00	.	.
NHPP 0761-238		I-76 DAHLIA TO YORK	.	2.00	50000.00	.	.
C0761-239			.				
NHPP0703-472			.	1.00	225745.00	.	.
ER007A-035			.	1.00	233200.00	.	.
STR160A-034		US160A LA VETA PASS EAST SURF	.	1.00	200000.00	.	.
STR092A-031			.	1.00	100000.00	.	.
NHM765-007			.	1.00	105000.00	.	.
		WEIGHTED AVERAGE FOR THE FIRST QUARTER		14.00	120882.50	.	.
NH0504-911			.	1.00	412000.00	.	.
STM1151-038		SH115 MP 27 TO MP 38	.	1.00	557000.00	.	.
2670703-479		I-70 BRIDGE OVER HARLAN	.	1.00	11500.00	.	.
STA0712-019		SH 71: Frieght Improvements	.	1.00	28000.00	.	.
STA001A-005		SH1 WELLINGTON SOUTH RESURFAC	.	1.00	100000.00	.	.
NHPP 3851-018		US 385 NORTH OF CHEYENNE WELL	.	1.00	250700.00	.	.
NHPP072A-047		SH-72 RESURFACING: I-70 TO IN	.	1.00	224000.00	.	.
FSA052A-046		SH52 WCR 37 INTERSECTION IMPR	.	1.00	154000.00	.	.
		WEIGHTED AVERAGE FOR THE SECOND QUARTER		8.00	217150.00	.	.
NHPP0063-054		US 6 FROM I70-B TO 33 RD. (MP	.	1.00	10000.00	.	.
2670403-065		US40_FLOYD HILL ROUNDABOUTS	.	1.00	8000.00	.	.
2670703-497		I-70_GENESEE WILDLIFE KING	.	1.00	43000.00	.	.
SHE2873-193		US 287 & CO 52 INTERSECTION I	.	1.00	59500.00	.	.
		WEIGHTED AVERAGE FOR THE THIRD QUARTER		4.00	30125.00	.	.
NHPP0701-253		I-70 EAST OF DEBEQUE	.	1.00	42500.00	.	.
STA207A-004		Resurfacing SH207A MANZANOLA	.	1.00	165000.00	.	.
TRG0253-264		I-25 AND SH 119 PARK-N-RIDE	.	1.00	50000.00	.	.
STA3852-015		US 385 HOLYOKE NORTH	.	1.00	150000.00	.	.
STU0252-457		I-25:ALAMEDA RIVER PH 2.0	.	1.00	10500.00	.	.
SHE0242-087		US 24 SAFETY IMPRVNNTS, E OF	.	1.00	2000.00	.	.
STR064A-010		SH 64 AND SH 13 AT MEEKER	.	1.00	29357.50	.	.
NHPP0853-126		US85C: PLATTEVILLE NORTH MP (.	1.00	100000.00	.	.

PROJECT NUMBER	ITEM NUMBER/ PROJECT LOCATION	ITEM DESCRIPTION/ PROJECT LOCATION	DATE LET	UNIT/ QUANTITY	ENGR. EST.	AVERAGE BID	AWARDED BID
=====	700-70018	F/A Road Smooth Incentive		Force Acct	=====		
C5502-097		US550 MP 117.28-126.06 .		1.00	80000.00	.	.
STAM420-001		US 285 AT HWY 9C IMPROVEMENTS .		1.00	26000.00	.	.
BR2854-148		INTERSECTION OF US 285 & SH 9					
STM0091-046		ADA RAMP IMPROVEMENTS - FAIRP					
STA0711-021		SH71: REGION LINE NORTH .		1.00	204576.77	.	.
STR114A-015		SH114 SILLSVILLE SOUTH TO MP3 .		1.00	175000.00	.	.
2670703-487		I-70 BRIDGES OVER WARD ROAD- .		1.00	14000.00	.	.
STR318A-001		SH 318 MP 0 - 12.5 MOFFAT COU .		1.00	176000.00	.	.
NHPP0021-041		SH2 RESURFACING MLK TO 52ND .		1.00	96100.00	.	.
NHPP083A-046		SH83 RESURFACING STROH RD TO .		1.00	100000.00	.	.
NHPP0063-048		US6 / 20 ROAD INTERSECTION IM .		1.00	10000.00	.	.
FSA0853-122		WCR14.5 AND US-85, FORT LUPTO .		1.00	1000.00	.	.
NHPP0931-033		SH93:US6 TO 58TH RESURFACING .		1.00	175000.00	.	.
NHPP0502-090		SH 50 MP 134.6-136 GUNNISON C .		1.00	22083.50	.	.
STA0361-129		US 36: HYGIENE RD AND NELSON .		1.00	67000.00	.	.
BR012A-048		CO 12 STRUCTURE P-17-F AT MP .		1.00	1000.00	.	.
STA385A-016		SH 385 MP 97.76 .		1.00	6000.00	.	.
STR096A-050		SH 96 MP 168.99 TO 193.77 .		1.00	268000.00	.	.
		WEIGHTED AVERAGE FOR THE FOURTH QUARTER		24.00	82129.91	.	.
		WEIGHTED AVERAGE FOR THE YEAR		50.00	110423.46	.	.
=====	700-70019	F/A Asphalt Cement Cost Adjustment		Force Acct	=====		
NHPP2873-189		US 287 (FEDERAL BLVD) - COLFA .		1.00	50950.00	.	.
NH0504-910		US50B L-24-B MIN REP AT MP 40 .		1.00	1000.00	.	.
NHPP0702-383		I-70 EB AUX FRISCO TO SILVERT .		1.00	20000.00	.	.
NHPP1601-083				1.00	25000.00	.	.
C0762-055				1.00	225000.00	.	.
STR0141-031				1.00	20000.00	.	.
STR133A-051				1.00	0.01	.	.
NHPP0063-063				1.00	12500.00	.	.
STA 067A-048		Hwy 67A MP 0.00 TO MP 11.05 I .		1.00	1000.00	.	.
NHPP 0761-238		I-76 DAHLIA TO YORK .		2.00	10000.00	.	.
C0761-239							
NHPP0703-472				1.00	194820.00	.	.
ER007A-035				1.00	189500.00	.	.
STR160A-034		US160A LA VETA PASS EAST SURF .		1.00	1000.00	.	.
BRC040-057				1.00	5000.00	.	.
STR092A-031				1.00	20000.00	.	.
NHM765-007				1.00	4000.00	.	.
		WEIGHTED AVERAGE FOR THE FIRST QUARTER		17.00	46457.06	.	.
NH0504-911				1.00	24040.00	.	.

COLORADO DEPARTMENT OF TRANSPORTATION
 ITEM UNIT COSTS BY PROJECTS -- 2022 COST DATA

11:31 Wednesday, March 8, 2023 640

PROJECT NUMBER	ITEM NUMBER/ PROJECT LOCATION	ITEM DESCRIPTION/ PROJECT LOCATION	DATE LET	UNIT/ QUANTITY	ENGR. EST.	AVERAGE BID	AWARDED BID
=====	700-70019	F/A Asphalt Cement Cost Adjustment		Force Acct	=====		
NHPP0702-413		VAIL PASS AUX PHASE 1 CAP 2 .		1.00	2025.00	.	.
STM1151-038		SH115 MP 27 TO MP 38 .		1.00	82107.00	.	.
2670703-479		I-70 BRIDGE OVER HARLAN .		1.00	145000.00	.	.
STA0712-019		SH 71: Frieght Improvements .		1.00	15000.00	.	.
STA001A-005		SH1 WELLINGTON SOUTH RESURFAC .		1.00	175000.00	.	.
NHC540-017		R2 CHAINUP STA @ KENOSHA/HOOS .		1.00	5000.00	.	.
NHPP 3851-018		US 385 NORTH OF CHEYENNE WELL .		1.00	375000.00	.	.
FSA3921-019		SH 392 AND WCR 55 ISLANDS .		1.00	200.00	.	.
NHPP072A-047		SH-72 RESURFACING: I-70 TO IN .		1.00	124000.00	.	.
FSA052A-046		SH52 WCR 37 INTERSECTION IMPR .		1.00	98441.01	.	.
		WEIGHTED AVERAGE FOR THE SECOND QUARTER		11.00	95073.91	.	.
NHPP0702-414		VAIL PASS AUX PHASE 1 CAP 3 .		2.00	2550.00	.	.
FBR0702-423		VAIL PASS AUX BE F-12-AT PHAS .				.	.
FSA052A-057		SH52 BOX CULVERT EXTENSION (M .		1.00	1000.00	.	.
NHPP0063-054		US 6 FROM I70-B TO 33 RD. (MP .		1.00	17000.00	.	.
BR0343-046		US 34 TIMBER BRIDGE REPL. PKG .		2.00	20000.00	.	.
FBR0343-047		US 6/US 34 TIMBER BRIDGE REPL .				.	.
2670403-065		US40 FLOYD HILL ROUNDABOUTS .		1.00	16500.00	.	.
2670703-497		I-70 GENESEE WILDLIFE XING .		1.00	43000.00	.	.
SHE2873-193		US 287 & CO 52 INTERSECTION I .		1.00	31000.00	.	.
		WEIGHTED AVERAGE FOR THE THIRD QUARTER		9.00	17066.67	.	.
NHPP0701-253		I-70 EAST OF DEBEQUE .		1.00	0.01	.	.
STA207A-004		Resurfacing SH207A MANZANOLA .		1.00	50000.00	.	.
C170A-002		CRITICAL CULVERT CONST. PKG D .		1.00	5000.00	.	.
TRG0253-264		I-25 AND SH 119 PARK-N-RIDE .		1.00	135000.00	.	.
STA3852-015		US 385 HOLYOKE NORTH .		1.00	200000.00	.	.
NHPP0343-048		US 34 (MP 169.3-171.4) .		1.00	1000.00	.	.
STU0252-457		I-25:ALAMEDA RIVER PH 2.0 .		1.00	65000.00	.	.
SHE0242-087		US 24 SAFETY IMPRVMENTS, E OF .		1.00	2000.00	.	.
STR064A-010		SH 64 AND SH 13 AT MEEKER .		1.00	17575.00	.	.
NHPP0853-126		US85C: PLATTEVILLE NORTH MP (.		1.00	225000.00	.	.
C5502-097		US550 MP 117.28-126.06 .		1.00	10000.00	.	.
STAM420-001		US 285 AT HWY 9C IMPROVEMENTS .		1.00	1000.00	.	.
BR2854-148		INTERSECTION OF US 285 & SH 9 .				.	.
STM0091-046		ADA RAMP IMPROVEMENTS - FAIRP .				.	.
STA0711-021		SH71: REGION LINE NORTH .		1.00	577811.23	.	.
STR114A-015		SH114 SILLSVILLE SOUTH TO MP3 .		1.00	25000.00	.	.
2670703-487		I-70 BRIDGES OVER WARD ROAD- .		1.00	52000.00	.	.

PROJECT NUMBER	ITEM NUMBER/ PROJECT LOCATION	ITEM DESCRIPTION/ PROJECT LOCATION	DATE LET	UNIT/ QUANTITY	ENGR. EST.	AVERAGE BID	AWARDED BID
=====	700-70019	F/A Asphalt Cement Cost Adjustment		Force Acct	=====		
IM025A-050		I25-MP103.9 - INTERSECTION DR .		1.00	20000.00	.	.
STR318A-001		SH 318 MP 0 - 12.5 MOFFAT COU .		1.00	22138.00	.	.
STR109A-019		M-22-AY BRIDGE REHAB ON SH109 .		1.00	1000.00	.	.
NHPP0021-041		SH2 RESURFACING MLK TO 52ND .		1.00	53861.00	.	.
NHPP083A-046		SH83 RESURFACING STROH RD TO .		1.00	49000.00	.	.
NHPP0063-048		US6 / 20 ROAD INTERSECTION IM .		1.00	60000.00	.	.
NHPP0931-033		SH93:US6 TO 58TH RESURFACING .		1.00	0.01	.	.
NHPP0502-090		SH 50 MP 134.6-136 GUNNISON C .		1.00	9250.00	.	.
STR0092-024		SH 9 North of Silverthorne .		1.00	11500.00	.	.
STA0361-129		US 36: HYGIENE RD AND NELSON .		1.00	170000.00	.	.
BR012A-048		CO 12 STRUCTURE P-17-F AT MP .		1.00	3500.00	.	.
STA385A-016		SH 385 MP 97.76 .		1.00	10000.00	.	.
STR096A-050		SH 96 MP 168.99 TO 193.77 .		1.00	137500.00	.	.
	WEIGHTED AVERAGE FOR THE FOURTH QUARTER			28.00	68361.97	.	.
	WEIGHTED AVERAGE FOR THE YEAR			65.00	60051.05	.	.
=====	700-70023	F/A On-The-Job Trainee		Force Acct	=====		
ITS0703-477		ITS EQUIPMENT UPGRADE AT EJMT .		1.00	5000.00	.	.
NHPP2873-189		US 287 (FEDERAL BLVD) - COLFA .		1.00	1920.00	.	.
STR0505-050		. .		1.00	1000.00	.	.
NHPP0702-383		I-70 EB AUX FRISCO TO SILVERT .		1.00	5120.00	.	.
NHPP1601-083		. .		1.00	10000.00	.	.
STA0252-459		. .		1.00	10000.00	.	.
C0762-055		. .		1.00	19200.00	.	.
STR0141-031		. .		1.00	10000.00	.	.
NHPP0063-063		. .		1.00	6400.00	.	.
NHPP 0761-238		I-76 DAHLIA TO YORK .		2.00	5000.00	.	.
C0761-239		. .		1.00	10000.00	.	.
NHPP0703-472		. .		1.00	12800.00	.	.
NHPP0253-275		I-25 EXPRESS LANES SEGMENT 5 .		1.00	12800.00	.	.
ER007A-035		. .		1.00	3200.00	.	.
STR R500-171		Various locations on SH 141 a .		1.00	3200.00	.	.
STR092A-031		. .		1.00	20000.00	.	.
NHM765-007		. .		1.00	6400.00	.	.
C0703-499		EJMT GROUT BED REPAIR AND PAN .		1.00	6400.00	.	.
	WEIGHTED AVERAGE FOR THE FIRST QUARTER			18.00	8168.89	.	.
NH0504-911		. .		1.00	25000.00	.	.
NHPP0702-413		VAIL PASS AUX PHASE 1 CAP 2 .		1.00	25600.00	.	.

PROJECT NUMBER	ITEM NUMBER/ PROJECT LOCATION	ITEM DESCRIPTION/ PROJECT LOCATION	DATE LET	UNIT/ QUANTITY	ENGR. EST.	AVERAGE BID	AWARDED BID
=====	700-70023	F/A On-The-Job Trainee		Force Acct	=====		
STM1151-038		SH115 MP 27 TO MP 38 .		1.00	42000.00	.	.
STA0712-019		SH 71: Frieight Improvements .		1.00	19200.00	.	.
STA001A-005		SH1 WELLINGTON SOUTH RESURFAC .		1.00	16000.00	.	.
NHC540-017		R2 CHAINUP STA @ KENOSHA/HOOS .		1.00	6400.00	.	.
NHPP 3851-018		US 385 NORTH OF CHEYENNE WELL .		1.00	15000.00	.	.
STAR100-358		3 STRUCTURES IN REGION 1 METR .		1.00	3000.00	.	.
C0852-120		Rehabilitation of Culvert by .		1.00	500.00	.	.
ITS 0741-024		VMS SIGN INSTALLATIONS AND VS .		1.00	2000.00	.	.
NHPP072A-047		SH-72 RESURFACING: I-70 TO IN .		1.00	8000.00	.	.
FSA052A-046		SH52 WCR 37 INTERSECTION IMPR .		1.00	6400.00	.	.
NHPP0252-448		I-25 TREX NARROWS BRIDGE PREV .		1.00	6400.00	.	.
		WEIGHTED AVERAGE FOR THE SECOND QUARTER		13.00	13500.00	.	.
NHPP0702-414		VAIL PASS AUX PHASE 1 CAP 3 .		2.00	12800.00	.	.
FBR0702-423		VAIL PASS AUX BE F-12-AT PHAS .				.	.
STAR100-374		5 STRUCTURES IN REGION 1 .		1.00	3200.00	.	.
NHPPR100-266		R1 ESSENTIAL REPAIRS .		1.00	10000.00	.	.
2670403-065		US40 FLOYD HILL ROUNDABOUTS .		1.00	19200.00	.	.
SHE2873-193		US 287 & CO 52 INTERSECTION I .		1.00	16000.00	.	.
		WEIGHTED AVERAGE FOR THE THIRD QUARTER		6.00	12333.33	.	.
NHPP0701-253		I-70 EAST OF DEBEQUE .		1.00	5000.00	.	.
STA207A-004		Resurfacing SH207A MANZANOLA .		1.00	12800.00	.	.
NHPP0705-088		I-70 AGATE STRUCTURE REHAB .		1.00	6400.00	.	.
TRG0253-264		I-25 AND SH 119 PARK-N-RIDE .		1.00	1000.00	.	.
STA3852-015		US 385 HOLYOKE NORTH .		1.00	19200.00	.	.
NHPP0343-048		US 34 (MP 169.3-171.4) .		1.00	1000.00	.	.
STU0252-457		I-25:ALAMEDA RIVER PH 2.0 .		1.00	40000.00	.	.
SHE0242-087		US 24 SAFETY IMPRVMENTS, E OF .		1.00	2000.00	.	.
NHPP0853-126		US85C: PLATTEVILLE NORTH MP (.		1.00	12800.00	.	.
C5502-097		US550 MP 117.28-126.06 .		1.00	1000.00	.	.
STAM420-001		US 285 AT HWY 9C IMPROVEMENTS .		1.00	22000.00	.	.
BR2854-148		INTERSECTION OF US 285 & SH 9 .				.	.
STM0091-046		ADA RAMP IMPROVEMENTS - FAIRP .				.	.
STA0711-021		SH71: REGION LINE NORTH .		1.00	18000.00	.	.
STR114A-015		SH114 SILLSVILLE SOUTH TO MP3 .		1.00	20000.00	.	.
NHPP0701-252		I-70 RIFLE TO SILT SLAB REPLA .		1.00	6400.00	.	.
IM025A-050		I25-MP103.9 - INTERSECTION DR .		1.00	16000.00	.	.
STR318A-001		SH 318 MP 0 - 12.5 MOFFAT COU .		1.00	0.01	.	.
STR109A-019		M-22-AY BRIDGE REHAB ON SH109 .		1.00	11000.00	.	.

COLORADO DEPARTMENT OF TRANSPORTATION
ITEM UNIT COSTS BY PROJECTS -- 2022 COST DATA

11:31 Wednesday, March 8, 2023 643

PROJECT NUMBER	ITEM NUMBER/ PROJECT LOCATION	ITEM DESCRIPTION/ PROJECT LOCATION	DATE LET	UNIT/ QUANTITY	ENGR. EST.	AVERAGE BID	AWARDED BID
===== 700-70023 F/A On-The-Job Trainee Force Acct =====							
NHPP0021-041		SH2 RESURFACING MLK TO 52ND .		1.00	3400.00	.	.
STR0641-107		SH 13 MM 104-128.1 IN MOFFAT .		1.00	3200.00	.	.
NHPP083A-046		SH83 RESURFACING STROH RD TO .		1.00	5000.00	.	.
NHPP0063-048		US6 / 20 ROAD INTERSECTION IM .		1.00	3200.00	.	.
NHM175-029		CANON CITY, CO .		1.00	2000.00	.	.
NHPP0931-033		SH93:US6 TO 58TH RESURFACING .		1.00	16000.00	.	.
STR0092-024		SH 9 North of Silverthorne .		1.00	20000.00	.	.
STA0361-129		US 36: HYGIENE RD AND NELSON .		1.00	6400.00	.	.
BR012A-048		CO 12 STRUCTURE P-17-F AT MP .		1.00	5000.00	.	.
STA385A-016		SH 385 MP 97.76 .		1.00	6000.00	.	.
	WEIGHTED AVERAGE FOR THE FOURTH QUARTER			27.00	9807.41	.	.
	WEIGHTED AVERAGE FOR THE YEAR			64.00	10333.44	.	.
===== 700-70025 F/A Quality Incentive Pymt Force Acct =====							
NH0504-910		US50B L-24-B MIN REP AT MP 40 .		1.00	1000.00	.	.
NHPP1601-083				1.00	250000.00	.	.
STA0252-459				1.00	100000.00	.	.
STR0141-031				1.00	15000.00	.	.
NHPP0063-063				1.00	8000.00	.	.
NHPP0703-472				1.00	263720.00	.	.
ER007A-035				1.00	215000.00	.	.
STR160A-034		US160A LA VETA PASS EAST SURF .		1.00	200000.00	.	.
STR092A-031				1.00	15000.00	.	.
NHM765-007				1.00	200000.00	.	.
	WEIGHTED AVERAGE FOR THE FIRST QUARTER			10.00	126772.00	.	.
NH0504-911				1.00	335000.00	.	.
NHPP 3851-018		US 385 NORTH OF CHEYENNE WELL .		1.00	295000.00	.	.
	WEIGHTED AVERAGE FOR THE SECOND QUARTER			2.00	315000.00	.	.
NHPP0063-054		US 6 FROM I70-B TO 33 RD. (MP .		1.00	50000.00	.	.
2670703-497		I-70_GENESEE WILDLIFE KING .		1.00	27000.00	.	.
	WEIGHTED AVERAGE FOR THE THIRD QUARTER			2.00	38500.00	.	.
NHPP0701-253		I-70 EAST OF DEBEQUE .		1.00	7750.00	.	.

PROJECT NUMBER	ITEM NUMBER/ PROJECT LOCATION	ITEM DESCRIPTION/ PROJECT LOCATION	DATE LET	UNIT/ QUANTITY	ENGR. EST.	AVERAGE BID	AWARDED BID
=====	700-70025	F/A Quality Incentive Pymt		Force Acct	=====		
STA207A-004		Resurfacing SH207A MANZANOLA .		1.00	75000.00	.	.
TRG0253-264		I-25 AND SH 119 PARK-N-RIDE .		1.00	50000.00	.	.
STU0252-457		I-25:ALAMEDA RIVER PH 2.0 .		1.00	50000.00	.	.
SHE0242-087		US 24 SAFETY IMPRVMENTS, E OF .		1.00	2000.00	.	.
STR064A-010		SH 64 AND SH 13 AT MEEKER .		1.00	22241.00	.	.
C5502-097		US550 MP 117.28-126.06 .		1.00	10000.00	.	.
STAM420-001		US 285 AT HWY 9C IMPROVEMENTS .		1.00	60000.00	.	.
BR2854-148		INTERSECTION OF US 285 & SH 9					
STM0091-046		ADA RAMP IMPROVEMENTS - FAIRP					
STA0711-021		SH71: REGION LINE NORTH .		1.00	472399.88	.	.
STR114A-015		SH114 SILLSVILLE SOUTH TO MP3 .		1.00	150000.00	.	.
STR318A-001		SH 318 MP 0 - 12.5 MOFFAT COU .		1.00	21834.00	.	.
NHPP0063-048		US6 / 20 ROAD INTERSECTION IM .		1.00	6000.00	.	.
FSA0853-122		WCR14.5 AND US-85, FORT LUPTO .		1.00	1000.00	.	.
NHPP0502-090		SH 50 MP 134.6-136 GUNNISON C .		1.00	6000.00	.	.
STR0092-024		SH 9 North of Silverthorne .		1.00	14000.00	.	.
STA0361-129		US 36: HYGIENE RD AND NELSON .		1.00	60000.00	.	.
BR012A-048		CO 12 STRUCTURE P-17-F AT MP .		1.00	3000.00	.	.
STA385A-016		SH 385 MP 97.76 .		1.00	17000.00	.	.
STR096A-050		SH 96 MP 168.99 TO 193.77 .		1.00	269000.00	.	.
		WEIGHTED AVERAGE FOR THE FOURTH QUARTER		19.00	68274.99	.	.
		WEIGHTED AVERAGE FOR THE YEAR		33.00	99149.84	.	.
=====	700-70031	F/A Interim Surface Repair		Force Acct	=====		
NHPP2873-189		US 287 (FEDERAL BLVD) - COLFA .		1.00	10350.00	.	.
NHPP 0761-238		I-76 DAHLIA TO YORK .		2.00	7500.00	.	.
C0761-239							
NHPP0703-472				1.00	43480.00	.	.
NHM765-007				1.00	10000.00	.	.
		WEIGHTED AVERAGE FOR THE FIRST QUARTER		5.00	15766.00	.	.
STM1151-038		SH115 MP 27 TO MP 38 .		1.00	20000.00	.	.
2670703-479		I-70 BRIDGE OVER HARLAN .		1.00	1100.00	.	.
NHPP072A-047		SH-72 RESURFACING: I-70 TO IN .		1.00	36000.00	.	.
		WEIGHTED AVERAGE FOR THE SECOND QUARTER		3.00	19033.33	.	.
2670403-065		US40_FLOYD HILL ROUNDABOUTS .		1.00	1000.00	.	.

COLORADO DEPARTMENT OF TRANSPORTATION
ITEM UNIT COSTS BY PROJECTS -- 2022 COST DATA

11:31 Wednesday, March 8, 2023 645

PROJECT NUMBER	ITEM NUMBER/ PROJECT LOCATION	ITEM DESCRIPTION/ PROJECT LOCATION	DATE LET	UNIT/ QUANTITY	ENGR. EST.	AVERAGE BID	AWARDED BID
=====	700-70031	F/A Interim Surface Repair		Force Acct	=====		
2670703-497		I-70_GENESEE WILDLIFE XING .		1.00	4000.00	.	.
		WEIGHTED AVERAGE FOR THE THIRD QUARTER		2.00	2500.00	.	.
2670703-487		I-70 BRIDGES OVER WARD ROAD- .		1.00	2000.00	.	.
NHPP0021-041		SH2 RESURFACING MLK TO 52ND .		1.00	10941.00	.	.
NHPP0931-033		SH93:US6 TO 58TH RESURFACING .		1.00	40000.00	.	.
NHPP0502-090		SH 50 MP 134.6-136 GUNNISON C .		1.00	10000.00	.	.
		WEIGHTED AVERAGE FOR THE FOURTH QUARTER		4.00	15735.25	.	.
		WEIGHTED AVERAGE FOR THE YEAR		14.00	14562.21	.	.
=====	700-70034	F/A		Force Acct	=====		
NHPP 0761-238		I-76 DAHLIA TO YORK .		1.00	12000.00	.	.
C0761-239							
STR092A-031				1.00	10000.00	.	.
		WEIGHTED AVERAGE FOR THE FIRST QUARTER		2.00	11000.00	.	.
NH0504-911				1.00	50000.00	.	.
NHPP0702-413		VAIL PASS AUX PHASE 1 CAP 2 .		1.00	40000.00	.	.
ER0702-420		PR I-70 GWC MATERIAL FLOWS 20 .		3.00	183333.33	.	.
NHC540-017		R2 CHAINUP STA @ KENOSHA/HOOS .		1.00	43000.00	.	.
		WEIGHTED AVERAGE FOR THE SECOND QUARTER		6.00	113833.33	.	.
NHPP0702-414		VAIL PASS AUX PHASE 1 CAP 3 .		2.00	20000.00	.	.
FBR0702-423		VAIL PASS AUX BE F-12-AT PHAS .					
FBR0761-236		I-76 OVER CLR CRK SCOUR MIT .		1.00	60000.00	.	.
		WEIGHTED AVERAGE FOR THE THIRD QUARTER		3.00	33333.33	.	.
STU0252-457		I-25:ALAMEDA RIVER PH 2.0 .		2.00	10000.00	.	.

COLORADO DEPARTMENT OF TRANSPORTATION
ITEM UNIT COSTS BY PROJECTS -- 2022 COST DATA

11:31 Wednesday, March 8, 2023 646

PROJECT NUMBER	ITEM NUMBER/ PROJECT LOCATION	ITEM DESCRIPTION/ PROJECT LOCATION	DATE LET	UNIT/ QUANTITY	ENGR. EST.	AVERAGE BID	AWARDED BID
===== 700-70034 F/A Force Acct =====							
STAM420-001		US 285 AT HWY 9C IMPROVEMENTS .		1.00	120000.00	.	.
BR2854-148		INTERSECTION OF US 285 & SH 9				.	.
STM0091-046		ADA RAMP IMPROVEMENTS - FAIRP				.	.
	WEIGHTED AVERAGE FOR THE FOURTH QUARTER			3.00	46666.67	.	.
	WEIGHTED AVERAGE FOR THE YEAR			14.00	67500.00	.	.
===== 700-70035 F/A Force Acct =====							
NHPP2873-189		US 287 (FEDERAL BLVD) - COLFA .		1.00	75000.00	.	.
NHPP1601-083				1.00	643283.53	.	.
NHPP0063-063				1.00	10000.00	.	.
	WEIGHTED AVERAGE FOR THE FIRST QUARTER			3.00	242761.18	.	.
NHPP0702-413		VAIL PASS AUX PHASE 1 CAP 2 .		1.00	1000.00	.	.
	WEIGHTED AVERAGE FOR THE SECOND QUARTER			1.00	1000.00	.	.
NHPP0702-414		VAIL PASS AUX PHASE 1 CAP 3 .		2.00	500.00	.	.
FBR0702-423		VAIL PASS AUX BE F-12-AT PHAS				.	.
NHPP0063-054		US 6 FROM I70-B TO 33 RD. (MP .		2.00	35000.00	.	.
FBR0761-236		I-76 OVER CLR CRK SCOUR MIT .		1.00	20000.00	.	.
NHPP0701-231		I-70 SALT WASH BRIDGES SCOUR .		1.00	120000.00	.	.
	WEIGHTED AVERAGE FOR THE THIRD QUARTER			6.00	35166.67	.	.
STU0252-457		I-25:ALAMEDA RIVER PH 2.0 .		2.00	20000.00	.	.
STR064A-010		SH 64 AND SH 13 AT MEEKER .		1.00	5000.00	.	.
C5502-097		US550 MP 117.28-126.06 .		1.00	10000.00	.	.
STAM420-001		US 285 AT HWY 9C IMPROVEMENTS .		1.00	30000.00	.	.
BR2854-148		INTERSECTION OF US 285 & SH 9				.	.
STM0091-046		ADA RAMP IMPROVEMENTS - FAIRP				.	.
NHPP0021-041		SH2 RESURFACING MLK TO 52ND .		1.00	40000.00	.	.
NHPP0931-033		SH93:US6 TO 58TH RESURFACING .		1.00	5000.00	.	.
	WEIGHTED AVERAGE FOR THE FOURTH QUARTER			7.00	18571.43	.	.
	WEIGHTED AVERAGE FOR THE YEAR			17.00	62957.85	.	.

COLORADO DEPARTMENT OF TRANSPORTATION
 ITEM UNIT COSTS BY PROJECTS -- 2022 COST DATA

11:31 Wednesday, March 8, 2023 647

PROJECT NUMBER	ITEM NUMBER/ PROJECT LOCATION	ITEM DESCRIPTION/ PROJECT LOCATION	DATE LET	UNIT/ QUANTITY	ENGR. EST.	AVERAGE BID	AWARDED BID
=====	700-70036	F/A		Force Acct	=====		
STAM420-001 BR2854-148 STM0091-046		US 285 AT HWY 9C IMPROVEMENTS . INTERSECTION OF US 285 & SH 9 ADA RAMP IMPROVEMENTS - FAIRP		1.00	10000.00	.	.
		WEIGHTED AVERAGE FOR THE FOURTH QUARTER		1.00	10000.00	.	.
		WEIGHTED AVERAGE FOR THE YEAR		1.00	10000.00	.	.
=====	700-70040	F/A Railroad		Force Acct	=====		
C0762-055				1.00	38400.00	.	.
		WEIGHTED AVERAGE FOR THE FIRST QUARTER		1.00	38400.00	.	.
STAR100-374		5 STRUCTURES IN REGION 1 .		1.00	15000.00	.	.
		WEIGHTED AVERAGE FOR THE THIRD QUARTER		1.00	15000.00	.	.
		WEIGHTED AVERAGE FOR THE YEAR		2.00	26700.00	.	.
=====	700-70042	F/A RR Flagging		Force Acct	=====		
BRC040-057				1.00	50000.00	.	.
		WEIGHTED AVERAGE FOR THE FIRST QUARTER		1.00	50000.00	.	.
STA001A-005		SH1 WELLINGTON SOUTH RESURFAC .		1.00	25000.00	.	.
		WEIGHTED AVERAGE FOR THE SECOND QUARTER		1.00	25000.00	.	.
BR0343-046 FBR0343-047 STAR100-374		US 34 TIMBER BRIDGE REPL. PKG . US 6/US 34 TIMBER BRIDGE REPL 5 STRUCTURES IN REGION 1 .		1.00 1.00	22500.00 125000.00	.	.
		WEIGHTED AVERAGE FOR THE THIRD QUARTER		2.00	73750.00	.	.

COLORADO DEPARTMENT OF TRANSPORTATION
ITEM UNIT COSTS BY PROJECTS -- 2022 COST DATA

11:31 Wednesday, March 8, 2023 648

PROJECT NUMBER	ITEM NUMBER/ PROJECT LOCATION	ITEM DESCRIPTION/ PROJECT LOCATION	DATE LET	UNIT/ QUANTITY	ENGR. EST.	AVERAGE BID	AWARDED BID
===== 700-70042		F/A RR Flagging		Force Acct	=====		
STA207A-004		Resurfacing SH207A MANZANOLA .		1.00	12000.00	.	.
STA3852-015		US 385 HOLYOKE NORTH .		1.00	8000.00	.	.
STRC090-011		US 50B AND SH71/CR18 INTERSEC .		1.00	25000.00	.	.
STR109A-019		M-22-AY BRIDGE REHAB ON SH109 .		1.00	50000.00	.	.
NHPP0021-041		SH2 RESURFACING MLK TO 52ND .		1.00	25000.00	.	.
NHPP0063-048		US6 / 20 ROAD INTERSECTION IM .		1.00	50000.00	.	.
	WEIGHTED AVERAGE FOR THE FOURTH QUARTER			6.00	28333.33	.	.
	WEIGHTED AVERAGE FOR THE YEAR			10.00	39250.00	.	.
===== 700-70060		F/A Adjust		Force Acct	=====		
NHPP0063-054		US 6 FROM I70-B TO 33 RD. (MP .		1.00	30000.00	.	.
ER0502-092		US 50 MP 204 EB MONARCH TRUCK .		1.00	15000.00	.	.
	WEIGHTED AVERAGE FOR THE THIRD QUARTER			2.00	22500.00	.	.
NHPP0063-048		US6 / 20 ROAD INTERSECTION IM .		1.00	5000.00	.	.
	WEIGHTED AVERAGE FOR THE FOURTH QUARTER			1.00	5000.00	.	.
	WEIGHTED AVERAGE FOR THE YEAR			3.00	16666.67	.	.
===== 700-70070		F/A Obtain		Force Acct	=====		
STU0252-457		I-25:ALAMEDA RIVER PH 2.0 .		1.00	50000.00	.	.
	WEIGHTED AVERAGE FOR THE FOURTH QUARTER			1.00	50000.00	.	.
	WEIGHTED AVERAGE FOR THE YEAR			1.00	50000.00	.	.
===== 700-70072		F/A Obtain Power from Xcel		Force Acct	=====		
NHC540-017		R2 CHAINUP STA @ KENOSHA/HOOS .		1.00	100000.00	.	.
	WEIGHTED AVERAGE FOR THE SECOND QUARTER			1.00	100000.00	.	.
	WEIGHTED AVERAGE FOR THE YEAR			1.00	100000.00	.	.

COLORADO DEPARTMENT OF TRANSPORTATION
ITEM UNIT COSTS BY PROJECTS -- 2022 COST DATA

11:31 Wednesday, March 8, 2023 649

PROJECT NUMBER	ITEM NUMBER/ PROJECT LOCATION	ITEM DESCRIPTION/ PROJECT LOCATION	DATE LET	UNIT/ QUANTITY	ENGR. EST.	AVERAGE BID	AWARDED BID
===== 700-70074 F/A Obtain Power from Force Acct =====							
NHC540-017		R2 CHAINUP STA @ KENOSHA/HOOS .		1.00	50000.00	.	.
		WEIGHTED AVERAGE FOR THE SECOND QUARTER		1.00	50000.00	.	.
NHPP0063-048		US6 / 20 ROAD INTERSECTION IM .		1.00	5000.00	.	.
		WEIGHTED AVERAGE FOR THE FOURTH QUARTER		1.00	5000.00	.	.
		WEIGHTED AVERAGE FOR THE YEAR		2.00	27500.00	.	.
===== 700-70081 F/A Provide Force Acct =====							
STU0252-457		I-25:ALAMEDA RIVER PH 2.0 .		1.00	150000.00	.	.
		WEIGHTED AVERAGE FOR THE FOURTH QUARTER		1.00	150000.00	.	.
		WEIGHTED AVERAGE FOR THE YEAR		1.00	150000.00	.	.
===== 700-70082 F/A Furn & Inst Elec Serv Force Acct =====							
NHPP0702-383		I-70 EB AUX FRISCO TO SILVERT .		1.00	20000.00	.	.
NHPP 0761-238		I-76 DAHLIA TO YORK .		2.00	7500.00	.	.
C0761-239							
NHPP0253-275		I-25 EXPRESS LANES SEGMENT 5 .		1.00	5000.00	.	.
NHM765-007				1.00	20000.00	.	.
		WEIGHTED AVERAGE FOR THE FIRST QUARTER		5.00	12000.00	.	.
STM1151-038		SH115 MP 27 TO MP 38 .		1.00	60000.00	.	.
2670703-479		I-70 BRIDGE OVER HARLAN .		1.00	5000.00	.	.
CM760-047		COLFAX AND QUAIL .		1.00	7000.00	.	.
ITS 0741-024		VMS SIGN INSTALLATIONS AND VS .		1.00	60000.00	.	.
		WEIGHTED AVERAGE FOR THE SECOND QUARTER		4.00	33000.00	.	.
NHPP0063-054		US 6 FROM I70-B TO 33 RD. (MP .		1.00	10000.00	.	.

COLORADO DEPARTMENT OF TRANSPORTATION
ITEM UNIT COSTS BY PROJECTS -- 2022 COST DATA

11:31 Wednesday, March 8, 2023 650

PROJECT NUMBER	ITEM NUMBER/ PROJECT LOCATION	ITEM DESCRIPTION/ PROJECT LOCATION	DATE LET	UNIT/ QUANTITY	ENGR. EST.	AVERAGE BID	AWARDED BID
=====	700-70082	F/A Furn & Inst Elec Serv		Force Acct	=====		
C1211-099		SH 121 NORTH SGA SIGNALS .		1.00	40000.00	.	.
2670403-065		US40 FLOYD HILL ROUNDABOUTS .		1.00	25000.00	.	.
SHE2873-193		US 287 & CO 52 INTERSECTION I .		1.00	5000.00	.	.
		WEIGHTED AVERAGE FOR THE THIRD QUARTER		4.00	20000.00	.	.
FSAM240-200		SH21B CO SPRINGS SIGNAL REPLA .		1.00	12000.00	.	.
TRG0253-264		I-25 AND SH 119 PARK-N-RIDE .		1.00	40000.00	.	.
STA3852-015		US 385 HOLYOKE NORTH .		1.00	8000.00	.	.
STU0252-457		I-25:ALAMEDA RIVER PH 2.0 .		1.00	20000.00	.	.
STRC090-011		US 50B AND SH71/CR18 INTERSEC .		1.00	15000.00	.	.
STAM420-001		US 285 AT HWY 9C IMPROVEMENTS .		1.00	60000.00	.	.
BR2854-148		INTERSECTION OF US 285 & SH 9					
STM0091-046		ADA RAMP IMPROVEMENTS - FAIRP					
2670703-487		I-70 BRIDGES OVER WARD ROAD- .		1.00	10000.00	.	.
IM025A-050		I25-MP103.9 - INTERSECTION DR .		1.00	10000.00	.	.
NHPP0063-048		US6 / 20 ROAD INTERSECTION IM .		1.00	5000.00	.	.
NHPP0931-033		SH93:US6 TO 58TH RESURFACING .		1.00	2000.00	.	.
STR096A-050		SH 96 MP 168.99 TO 193.77 .		1.00	5000.00	.	.
		WEIGHTED AVERAGE FOR THE FOURTH QUARTER		11.00	17000.00	.	.
		WEIGHTED AVERAGE FOR THE YEAR		24.00	19125.00	.	.
=====	700-70090	F/A Reset		Force Acct	=====		
NHPP0702-414		VAIL PASS AUX PHASE 1 CAP 3 .		1.00	5000.00	.	.
FBR0702-423		VAIL PASS AUX BE F-12-AT PHAS					
		WEIGHTED AVERAGE FOR THE THIRD QUARTER		1.00	5000.00	.	.
		WEIGHTED AVERAGE FOR THE YEAR		1.00	5000.00	.	.
=====	700-70100	F/A Relocate		Force Acct	=====		
NH0504-911		I-70 BRIDGE OVER HARLAN .		1.00	10000.00	.	.
2670703-479		I-70 BRIDGE OVER HARLAN .		1.00	10000.00	.	.
		WEIGHTED AVERAGE FOR THE SECOND QUARTER		2.00	10000.00	.	.
C5502-097		US550 MP 117.28-126.06 .		1.00	152000.00	.	.

COLORADO DEPARTMENT OF TRANSPORTATION
ITEM UNIT COSTS BY PROJECTS -- 2022 COST DATA

11:31 Wednesday, March 8, 2023 651

PROJECT NUMBER	ITEM NUMBER/ PROJECT LOCATION	ITEM DESCRIPTION/ PROJECT LOCATION	DATE LET	UNIT/ QUANTITY	ENGR. EST.	AVERAGE BID	AWARDED BID
=====	700-70100	F/A Relocate		Force Acct	=====		
IM025A-050		I25-MP103.9 - INTERSECTION DR .		1.00	5000.00	.	.
		WEIGHTED AVERAGE FOR THE FOURTH QUARTER		2.00	78500.00	.	.
		WEIGHTED AVERAGE FOR THE YEAR		4.00	44250.00	.	.
=====	700-70110	F/A Install		Force Acct	=====		
STU0252-457		I-25:ALAMEDA RIVER PH 2.0 .		1.00	25000.00	.	.
		WEIGHTED AVERAGE FOR THE FOURTH QUARTER		1.00	25000.00	.	.
		WEIGHTED AVERAGE FOR THE YEAR		1.00	25000.00	.	.
=====	700-70111	Project First Program		Force Acct	=====		
ITS0703-477		ITS EQUIPMENT UPGRADE AT EJMT .		1.00	1000.00	.	.
MTCE R500-219		.		1.00	1000.00	.	.
MTCE R500-218		.		1.00	1000.00	.	.
NHPP2873-189		US 287 (FEDERAL BLVD) - COLFA .		1.00	2500.00	.	.
STR0505-050		.		1.00	2000.00	.	.
MTCER400-391		VARIOUS HIGHWAY SEGMENTS ACRO .		1.00	500.00	.	.
NHPP0702-383		I-70 EB AUX FRISCO TO SILVERT .		1.00	15000.00	.	.
NHPP1601-083		.		1.00	4000.00	.	.
STA0252-459		.		1.00	8000.00	.	.
C0762-055		.		1.00	2000.00	.	.
STR0141-031		.		1.00	2000.00	.	.
STR133A-051		.		1.00	1500.00	.	.
NHPP0063-063		.		1.00	2000.00	.	.
STA 067A-048		Hwy 67A MP 0.00 TO MP 11.05 I .		1.00	10000.00	.	.
NHPP 0761-238		I-76 DAHLIA TO YORK .		1.00	5000.00	.	.
C0761-239		.				.	.
NHPP0703-472		.		1.00	500.00	.	.
ER007A-035		.		1.00	10000.00	.	.
STR160A-034		US160A LA VETA PASS EAST SURF .		1.00	1000.00	.	.
BRC040-057		.		1.00	5000.00	.	.
STR R500-171		Various locations on SH 141 a .		1.00	500.00	.	.
STR092A-031		.		1.00	2500.00	.	.
NHM765-007		.		1.00	10000.00	.	.
C0703-499		EJMT GROUT BED REPAIR AND PAN .		1.00	2000.00	.	.
		WEIGHTED AVERAGE FOR THE FIRST QUARTER		23.00	3869.57	.	.
NH0504-911		.		1.00	5000.00	.	.

PROJECT NUMBER	ITEM NUMBER/ PROJECT LOCATION	ITEM DESCRIPTION/ PROJECT LOCATION	DATE LET	UNIT/ QUANTITY	ENGR. EST.	AVERAGE BID	AWARDED BID
=====	700-70111	Project First Program		Force Acct	=====		
CC030-081		ADA RAMP AND CURBS - FT. LUPT .		1.00	5000.00	.	.
NHPP0702-413		VAIL PASS AUX PHASE 1 CAP 2 .		1.00	3000.00	.	.
STM1151-038		SH115 MP 27 TO MP 38 .		1.00	30000.00	.	.
2670703-479		I-70 BRIDGE OVER HARLAN .		1.00	4000.00	.	.
ER0702-420		PR I-70 GWC MATERIAL FLOWS 20 .		1.00	7000.00	.	.
STA0712-019		SH 71: Frieight Improvements .		1.00	3000.00	.	.
STA001A-005		SH1 WELLINGTON SOUTH RESURFAC .		1.00	5000.00	.	.
NHC540-017		R2 CHAINUP STA @ KENOSHA/HOOS .		1.00	2000.00	.	.
CM760-047		COLFAX AND QUAIL .		1.00	1000.00	.	.
NHPP 3851-018		US 385 NORTH OF CHEYENNE WELL .		1.00	5000.00	.	.
STAR100-358		3 STRUCTURES IN REGION 1 METR .		1.00	500.00	.	.
FSA0702-409		I-70 VAIL WILDLIFE FENCE PHAS .		1.00	4000.00	.	.
ITS 0741-024		VMS SIGN INSTALLATIONS AND VS .		1.00	1000.00	.	.
NHPP072A-047		SH-72 RESURFACING: I-70 TO IN .		1.00	2000.00	.	.
FSA052A-046		SH52 WCR 37 INTERSECTION IMPR .		1.00	2000.00	.	.
MPR200-278		R2 - VARIOUS LOCATIONS .		1.00	500.00	.	.
MTCE0253-291		I-25 SIGN REPLACEMENT PHASE 2 .		1.00	100.00	.	.
NHPP0252-448		I-25 TREX NARROWS BRIDGE PREV .		1.00	1500.00	.	.
MTCE R100-380		REGION 1 FY 23/24 PAVEMENT MA .		1.00	500.00	.	.
		WEIGHTED AVERAGE FOR THE SECOND QUARTER		20.00	4105.00	.	.
MT CER300-273		I-70 MM 75-116, OTHER REGION .		1.00	2000.00	.	.
NHPP0702-414		VAIL PASS AUX PHASE 1 CAP 3 .		2.00	1500.00	.	.
FBR0702-423		VAIL PASS AUX BE F-12-AT PHAS .				.	.
FSA052A-057		SH52 BOX CULVERT EXTENSION (M .		1.00	1000.00	.	.
STR0711-022		SH 71 OVER THE ARKANSAS .		1.00	1000.00	.	.
NHPP0063-054		US 6 FROM I70-B TO 33 RD. (MP .		1.00	3000.00	.	.
FBR0761-236		I-76 OVER CLR CRK SCOUR MIT .		1.00	5000.00	.	.
MT CER400-396		REGION 4 .		1.00	500.00	.	.
ER0502-092		US 50 MP 204 EB MONARCH TRUCK .		1.00	1000.00	.	.
BR0343-046		US 34 TIMBER BRIDGE REPL. PKG .		2.00	2500.00	.	.
FBR0343-047		US 6/US 34 TIMBER BRIDGE REPL .				.	.
STAR100-374		5 STRUCTURES IN REGION 1 .		1.00	500.00	.	.
NHPPR100-266		R1 ESSENTIAL REPAIRS .		1.00	10000.00	.	.
ER0253-297		WCR 34 BRIDGE OVER I-25(MM 24 .		1.00	5000.00	.	.
2670403-065		US40 FLOYD HILL ROUNDABOUTS .		1.00	2000.00	.	.
2670703-497		I-70 GENESEE WILDLIFE XING .		1.00	2000.00	.	.
SHE2873-193		US 287 & CO 52 INTERSECTION I .		1.00	5000.00	.	.
NHPP0701-231		I-70 SALT WASH BRIDGES SCOUR .		1.00	2000.00	.	.
		WEIGHTED AVERAGE FOR THE THIRD QUARTER		18.00	2666.67	.	.
NHPP0821-114		SH 82 ASPEN/INDEPENDENCE PASS .		1.00	1000.00	.	.

PROJECT NUMBER	ITEM NUMBER/ PROJECT LOCATION	ITEM DESCRIPTION/ PROJECT LOCATION	DATE LET	UNIT/ QUANTITY	ENGR. EST.	AVERAGE BID	AWARDED BID
=====	700-70111	Project First Program		Force Acct	=====		
C0831-126		SH83 EL PASO COUNTY TO BAYOU .		1.00	5000.00	.	.
NHPP0701-253		I-70 EAST OF DEBEQUE .		1.00	7000.00	.	.
STA207A-004		Resurfacing SH207A MANZANOLA .		1.00	5000.00	.	.
NHPP0705-088		I-70 AGATE STRUCTURE REHAB .		1.00	3000.00	.	.
FSAM240-200		SH21B CO SPRINGS SIGNAL REPLA .		1.00	1500.00	.	.
C170A-002		CRITICAL CULVERT CONST. PKG D .		1.00	500.00	.	.
TRG0253-264		I-25 AND SH 119 PARK-N-RIDE .		1.00	10000.00	.	.
STA3852-015		US 385 HOLYOKE NORTH .		1.00	2000.00	.	.
NHPP0343-048		US 34 (MP 169.3-171.4) .		1.00	500.00	.	.
STU0252-457		I-25:ALAMEDA RIVER PH 2.0 .		1.00	20000.00	.	.
SHE0242-087		US 24 SAFETY IMPRVMENTS, E OF .		1.00	2000.00	.	.
NHPP0853-126		US85C: PLATTEVILLE NORTH MP (.		1.00	5000.00	.	.
C5502-097		US550 MP 117.28-126.06 .		1.00	10000.00	.	.
MPR200-280		PUEBLO AREA .		1.00	1000.00	.	.
STRC090-011		US 50B AND SH71/CR18 INTERSEC .		1.00	3000.00	.	.
STAM420-001		US 285 AT HWY 9C IMPROVEMENTS .		1.00	20000.00	.	.
BR2854-148		INTERSECTION OF US 285 & SH 9 .				.	.
STM0091-046		ADA RAMP IMPROVEMENTS - FAIRP .				.	.
STA0711-021		SH71: REGION LINE NORTH .		1.00	2500.00	.	.
STR114A-015		SH114 SILLSVILLE SOUTH TO MP3 .		1.00	5000.00	.	.
2670703-487		I-70 BRIDGES OVER WARD ROAD- .		1.00	5000.00	.	.
NHPP0701-252		I-70 RIFLE TO SILT SLAB REPLA .		1.00	7000.00	.	.
IM025A-050		I25-MP103.9 - INTERSECTION DR .		1.00	5000.00	.	.
STR318A-001		SH 318 MP 0 - 12.5 MOFFAT COU .		1.00	7000.00	.	.
STR109A-019		M-22-AY BRIDGE REHAB ON SH109 .		1.00	5000.00	.	.
NHPP0021-041		SH2 RESURFACING MLK TO 52ND .		1.00	2500.00	.	.
STR0641-107		SH 13 MM 104-128.1 IN MOFFAT .		1.00	1500.00	.	.
NHPP083A-046		SH83 RESURFACING STROH RD TO .		1.00	5000.00	.	.
NHPP0063-048		US6 / 20 ROAD INTERSECTION IM .		1.00	15000.00	.	.
NHM175-029		CANON CITY, CO .		1.00	2000.00	.	.
NHPP0931-033		SH93:US6 TO 58TH RESURFACING .		1.00	2000.00	.	.
NHPP0502-090		SH 50 MP 134.6-136 GUNNISON C .		1.00	10000.00	.	.
STR0092-024		SH 9 North of Silverthorne .		1.00	2000.00	.	.
STA0361-129		US 36: HYGIENE RD AND NELSON .		1.00	3000.00	.	.
BR012A-048		CO 12 STRUCTURE P-17-F AT MP .		1.00	5000.00	.	.
STA385A-016		SH 385 MP 97.76 .		1.00	5000.00	.	.
STR096A-050		SH 96 MP 168.99 TO 193.77 .		1.00	2000.00	.	.
		WEIGHTED AVERAGE FOR THE FOURTH QUARTER		36.00	5222.22	.	.
		WEIGHTED AVERAGE FOR THE YEAR		97.00	4196.91	.	.
=====	700-70129	F/A Deck Rehab		Force Acct	=====		
NHPP0252-448		I-25 TREX NARROWS BRIDGE PREV .		1.00	50000.00	.	.
		WEIGHTED AVERAGE FOR THE SECOND QUARTER		1.00	50000.00	.	.
		WEIGHTED AVERAGE FOR THE YEAR		1.00	50000.00	.	.

COLORADO DEPARTMENT OF TRANSPORTATION
ITEM UNIT COSTS BY PROJECTS -- 2022 COST DATA

11:31 Wednesday, March 8, 2023 654

PROJECT NUMBER	ITEM NUMBER/ PROJECT LOCATION	ITEM DESCRIPTION/ PROJECT LOCATION	DATE LET	UNIT/ QUANTITY	ENGR. EST.	AVERAGE BID	AWARDED BID
=====	700-70130	F/A Repair		Force Acct	=====		
STU0252-457		I-25:ALAMEDA RIVER PH 2.0	.	1.00	10000.00	.	.
	WEIGHTED	AVERAGE FOR THE FOURTH QUARTER		1.00	10000.00	.	.
		WEIGHTED AVERAGE FOR THE YEAR		1.00	10000.00	.	.
=====	700-70155	F/A Pvmt Surf Course Maint		Force Acct	=====		
STA0361-129		US 36: HYGIENE RD AND NELSON	.	1.00	25000.00	.	.
	WEIGHTED	AVERAGE FOR THE FOURTH QUARTER		1.00	25000.00	.	.
		WEIGHTED AVERAGE FOR THE YEAR		1.00	25000.00	.	.
=====	700-70160	F/A Detour		Force Acct	=====		
BR0343-046 FBR0343-047		US 34 TIMBER BRIDGE REPL. PKG US 6/US 34 TIMBER BRIDGE REPL	.	2.00	5000.00	.	.
	WEIGHTED	AVERAGE FOR THE THIRD QUARTER		2.00	5000.00	.	.
		WEIGHTED AVERAGE FOR THE YEAR		2.00	5000.00	.	.
=====	700-70195	F/A Util and Maint of Field Facil		Force Acct	=====		
STR0505-050			.	1.00	5000.00	.	.
	WEIGHTED	AVERAGE FOR THE FIRST QUARTER		1.00	5000.00	.	.
STAM420-001 BR2854-148 STM0091-046 NHM175-029		US 285 AT HWY 9C IMPROVEMENTS INTERSECTION OF US 285 & SH 9 ADA RAMP IMPROVEMENTS - FAIRP CANON CITY, CO	.	1.00	20000.00	.	.
	WEIGHTED	AVERAGE FOR THE FOURTH QUARTER		2.00	12500.00	.	.
		WEIGHTED AVERAGE FOR THE YEAR		3.00	10000.00	.	.

COLORADO DEPARTMENT OF TRANSPORTATION
ITEM UNIT COSTS BY PROJECTS -- 2022 COST DATA

11:31 Wednesday, March 8, 2023 655

PROJECT NUMBER	ITEM NUMBER/ PROJECT LOCATION	ITEM DESCRIPTION/ PROJECT LOCATION	DATE LET	UNIT/ QUANTITY	ENGR. EST.	AVERAGE BID	AWARDED BID
=====	700-70200	F/A Power Lines		Force Acct	=====		
TRG0253-264		I-25 AND SH 119 PARK-N-RIDE .		1.00	5000.00	.	.
		WEIGHTED AVERAGE FOR THE FOURTH QUARTER		1.00	5000.00	.	.
		WEIGHTED AVERAGE FOR THE YEAR		1.00	5000.00	.	.
=====	700-70210	F/A Lights		Force Acct	=====		
STU0252-457		I-25:ALAMEDA RIVER PH 2.0 .		1.00	50000.00	.	.
		WEIGHTED AVERAGE FOR THE FOURTH QUARTER		1.00	50000.00	.	.
		WEIGHTED AVERAGE FOR THE YEAR		1.00	50000.00	.	.
=====	700-70220	F/A Phone Serv		Force Acct	=====		
TRG0253-264		I-25 AND SH 119 PARK-N-RIDE .		1.00	5000.00	.	.
		WEIGHTED AVERAGE FOR THE FOURTH QUARTER		1.00	5000.00	.	.
		WEIGHTED AVERAGE FOR THE YEAR		1.00	5000.00	.	.
=====	700-70230	F/A Communication Lines		Force Acct	=====		
ITS0703-477		ITS EQUIPMENT UPGRADE AT EJMT .		1.00	130000.00	.	.
		WEIGHTED AVERAGE FOR THE FIRST QUARTER		1.00	130000.00	.	.
ITS 0741-024		VMS SIGN INSTALLATIONS AND VS .		1.00	50000.00	.	.
		WEIGHTED AVERAGE FOR THE SECOND QUARTER		1.00	50000.00	.	.
2670703-487 NHPP0502-090		I-70 BRIDGES OVER WARD ROAD- .		1.00	10000.00	.	.
		SH 50 MP 134.6-136 GUNNISON C .		1.00	5000.00	.	.
		WEIGHTED AVERAGE FOR THE FOURTH QUARTER		2.00	7500.00	.	.
		WEIGHTED AVERAGE FOR THE YEAR		4.00	48750.00	.	.

COLORADO DEPARTMENT OF TRANSPORTATION
 ITEM UNIT COSTS BY PROJECTS -- 2022 COST DATA

11:31 Wednesday, March 8, 2023 656

PROJECT NUMBER	ITEM NUMBER/ PROJECT LOCATION	ITEM DESCRIPTION/ PROJECT LOCATION	DATE LET	UNIT/ QUANTITY	ENGR. EST.	AVERAGE BID	AWARDED BID
===== 700-70255 F/A Water Force Acct =====							
STU0252-457		I-25:ALAMEDA RIVER PH 2.0 .		1.00	30000.00	.	.
	WEIGHTED AVERAGE FOR THE FOURTH QUARTER			1.00	30000.00	.	.
	WEIGHTED AVERAGE FOR THE YEAR			1.00	30000.00	.	.
===== 700-70310 F/A Landscaping Force Acct =====							
NHPP2873-189		US 287 (FEDERAL BLVD) - COLFA .		1.00	3000.00	.	.
STR092A-031		.		1.00	3500.00	.	.
NHM765-007		.		1.00	20000.00	.	.
	WEIGHTED AVERAGE FOR THE FIRST QUARTER			3.00	8833.33	.	.
CM760-047		COLFAX AND QUAIL .		1.00	5000.00	.	.
	WEIGHTED AVERAGE FOR THE SECOND QUARTER			1.00	5000.00	.	.
NHPP0063-054		US 6 FROM I70-B TO 33 RD. (MP .		1.00	10000.00	.	.
	WEIGHTED AVERAGE FOR THE THIRD QUARTER			1.00	10000.00	.	.
STA3852-015		US 385 HOLYOKE NORTH .		1.00	5000.00	.	.
STU0252-457		I-25:ALAMEDA RIVER PH 2.0 .		1.00	50000.00	.	.
STAM420-001		US 285 AT HWY 9C IMPROVEMENTS .		1.00	26500.00	.	.
BR2854-148		INTERSECTION OF US 285 & SH 9 .				.	.
STM0091-046		ADA RAMP IMPROVEMENTS - FAIRP .				.	.
BR012A-048		CO 12 STRUCTURE P-17-F AT MP .		1.00	5000.00	.	.
	WEIGHTED AVERAGE FOR THE FOURTH QUARTER			4.00	21625.00	.	.
	WEIGHTED AVERAGE FOR THE YEAR			9.00	14222.22	.	.
===== 700-70320 F/A Sprinklers Force Acct =====							
CC030-081		ADA RAMP AND CURBS - FT. LUPT .		1.00	10000.00	.	.
	WEIGHTED AVERAGE FOR THE SECOND QUARTER			1.00	10000.00	.	.

COLORADO DEPARTMENT OF TRANSPORTATION
ITEM UNIT COSTS BY PROJECTS -- 2022 COST DATA

11:31 Wednesday, March 8, 2023 657

PROJECT NUMBER	ITEM NUMBER/ PROJECT LOCATION	ITEM DESCRIPTION/ PROJECT LOCATION	DATE LET	UNIT/ QUANTITY	ENGR. EST.	AVERAGE BID	AWARDED BID
=====	700-70320	F/A Sprinklers		Force Acct	=====		
NHPP0063-054		US 6 FROM I70-B TO 33 RD. (MP .		1.00	10000.00	.	.
		WEIGHTED AVERAGE FOR THE THIRD QUARTER		1.00	10000.00	.	.
STAM420-001 BR2854-148 STM0091-046		US 285 AT HWY 9C IMPROVEMENTS . INTERSECTION OF US 285 & SH 9 ADA RAMP IMPROVEMENTS - FAIRP		1.00	5000.00	.	.
		WEIGHTED AVERAGE FOR THE FOURTH QUARTER		1.00	5000.00	.	.
		WEIGHTED AVERAGE FOR THE YEAR		3.00	8333.33	.	.
=====	700-70350	F/A Removal of Obstruction		Force Acct	=====		
NHPP 0761-238 C0761-239		I-76 DAHLIA TO YORK .		1.00	10000.00	.	.
		WEIGHTED AVERAGE FOR THE FIRST QUARTER		1.00	10000.00	.	.
		WEIGHTED AVERAGE FOR THE YEAR		1.00	10000.00	.	.
=====	700-70380	F/A Erosion Ctrl		Force Acct	=====		
ITS0703-477		ITS EQUIPMENT UPGRADE AT EJMT .		1.00	20000.00	.	.
MTCE R500-219		.		1.00	1000.00	.	.
MTCE R500-218		.		1.00	1000.00	.	.
NHPP2873-189		US 287 (FEDERAL BLVD) - COLFA .		1.00	6000.00	.	.
STR0505-050		.		1.00	5000.00	.	.
NH0504-910		US50B I-24-B MIN REP AT MP 40 .		1.00	5000.00	.	.
MTCER400-391		VARIOUS HIGHWAY SEGMENTS ACRO .		1.00	500.00	.	.
MTCER300-262		.		1.00	5000.00	.	.
NHPP1601-083		.		1.00	5000.00	.	.
STA0252-459		.		1.00	15000.00	.	.
C0762-055		.		1.00	5000.00	.	.
STR133A-051		.		1.00	2000.00	.	.
NHPP0063-063		.		1.00	7500.00	.	.
STA 067A-048		Hwy 67A MP 0.00 TO MP 11.05 I .		1.00	10000.00	.	.

COLORADO DEPARTMENT OF TRANSPORTATION
ITEM UNIT COSTS BY PROJECTS -- 2022 COST DATA

11:31 Wednesday, March 8, 2023 658

PROJECT NUMBER	ITEM NUMBER/ PROJECT LOCATION	ITEM DESCRIPTION/ PROJECT LOCATION	DATE LET	UNIT/ QUANTITY	ENGR. EST.	AVERAGE BID	AWARDED BID
=====	700-70380	F/A Erosion Ctrl		Force Acct	=====		
NHPP 0761-238		I-76 DAHLIA TO YORK	.	1.00	20000.00	.	.
C0761-239							
NHPP0703-472			.	1.00	2500.00	.	.
ER007A-035			.	1.00	10000.00	.	.
STR160A-034		US160A LA VETA PASS EAST SURF	.	1.00	10000.00	.	.
BRC040-057			.	1.00	10000.00	.	.
STR R500-171		Various locations on SH 141 a	.	1.00	5000.00	.	.
M R100-351		FY22 R1 SIGN STRUCTURE REPLAC	.	1.00	2500.00	.	.
STR092A-031			.	1.00	5000.00	.	.
NHM765-007			.	1.00	20000.00	.	.
C0703-499		EJMT GROUT BED REPAIR AND PAN	.	1.00	2000.00	.	.
		WEIGHTED AVERAGE FOR THE FIRST QUARTER		24.00	7291.67	.	.
NH0504-911			.	1.00	5000.00	.	.
CC030-081		ADA RAMP AND CURBS - FT. LUPT	.	1.00	10000.00	.	.
STM1151-038		SH115 MP 27 TO MP 38	.	1.00	10000.00	.	.
MTCE2873-204		MTCE FY22 SH287 CONC PANEL RE	.	1.00	2500.00	.	.
2670703-479		I-70 BRIDGE OVER HARLAN	.	1.00	5000.00	.	.
ER0702-420		PR I-70 GWC MATERIAL FLOWS 20	.	1.00	8000.00	.	.
STA0712-019		SH 71: Frieight Improvements	.	1.00	3000.00	.	.
STA001A-005		SH1 WELLINGTON SOUTH RESURFAC	.	1.00	5000.00	.	.
NHC540-017		R2 CHAINUP STA @ KENOSHA/HOOS	.	1.00	33600.00	.	.
CM760-047		COLFAX AND QUAIL	.	1.00	3000.00	.	.
NHPP 3851-018		US 385 NORTH OF CHEYENNE WELL	.	1.00	10000.00	.	.
STAR100-358		3 STRUCTURES IN REGION 1 METR	.	1.00	2500.00	.	.
C0852-120		Rehabilitation of Culvert by	.	1.00	2000.00	.	.
ITS 0741-024		VMS SIGN INSTALLATIONS AND VS	.	1.00	5000.00	.	.
FSA3921-019		SH 392 AND WCR 55 ISLANDS	.	1.00	3750.00	.	.
NHPP072A-047		SH-72 RESURFACING: I-70 TO IN	.	1.00	5000.00	.	.
FSA052A-046		SH52 WCR 37 INTERSECTION IMPR	.	1.00	3600.00	.	.
MTCE0253-291		I-25 SIGN REPLACEMENT PHASE 2	.	1.00	2000.00	.	.
NHPP0252-448		I-25 TREX NARROWS BRIDGE PREV	.	1.00	1200.00	.	.
MTCE R100-380		REGION 1 FY 23/24 PAVEMENT MA	.	1.00	5000.00	.	.
		WEIGHTED AVERAGE FOR THE SECOND QUARTER		20.00	6257.50	.	.
MTCE 072A-045		SH 72B MP 37.00 TO MP 45.3 NE	.	1.00	2000.00	.	.
FSA052A-057		SH52 BOX CULVERT EXTENSION (M	.	1.00	1000.00	.	.
STR0711-022		SH 71 OVER THE ARKANSAS	.	1.00	1000.00	.	.
NHPP0063-054		US 6 FROM I70-B TO 33 RD. (MP	.	1.00	10000.00	.	.
FBR0761-236		I-76 OVER CLR CRK SCOUR MIT	.	1.00	5000.00	.	.

PROJECT NUMBER	ITEM NUMBER/ PROJECT LOCATION	ITEM DESCRIPTION/ PROJECT LOCATION	DATE LET	UNIT/ QUANTITY	ENGR. EST.	AVERAGE BID	AWARDED BID
=====	700-70380	F/A Erosion Ctrl		Force Acct	=====		
MTCER400-396	REGION 4		.	1.00	500.00	.	.
C1211-099	SH 121 NORTH SGA SIGNALS		.	1.00	20000.00	.	.
ER0502-092	US 50 MP 204 EB MONARCH TRUCK		.	1.00	5000.00	.	.
BR0343-046	US 34 TIMBER BRIDGE REPL. PKG		.	2.00	10000.00	.	.
FBR0343-047	US 6/US 34 TIMBER BRIDGE REPL		.			.	.
STAR100-374	5 STRUCTURES IN REGION 1		.	1.00	1200.00	.	.
NHPPR100-266	R1 ESSENTIAL REPAIRS		.	1.00	10000.00	.	.
PAN0761-245	ALONG I-76 & RAMPS MILEPOST 9		.	1.00	1000.00	.	.
2670403-065	US40 FLOYD HILL ROUNDABOUTS		.	1.00	5000.00	.	.
2670703-497	I-70 GENESEE WILDLIFE XING		.	1.00	5000.00	.	.
SHE2873-193	US 287 & CO 52 INTERSECTION I		.	1.00	5000.00	.	.
NHPP0701-231	I-70 SALT WASH BRIDGES SCOUR		.	1.00	10000.00	.	.
	WEIGHTED AVERAGE FOR THE THIRD QUARTER			17.00	5982.35	.	.
MTCE0253-281	MTCE FY23 I-25 CONC PANEL REP		.	1.00	2000.00	.	.
NHPP0821-114	SH 82 ASPEN/INDEPENDENCE PASS		.	1.00	12000.00	.	.
C0831-126	SH83 EL PASO COUNTY TO BAYOU		.	1.00	5000.00	.	.
NHPP0701-253	I-70 EAST OF DEBEQUE		.	1.00	1500.00	.	.
STA207A-004	Resurfacing SH207A MANZANOLA		.	1.00	5000.00	.	.
NHPP0705-088	I-70 AGATE STRUCTURE REHAB		.	1.00	5000.00	.	.
FSAM240-200	SH21B CO SPRINGS SIGNAL REPLA		.	1.00	2500.00	.	.
C5502-111	US 550 MP 81 AND 89 RED MOUNT		.	1.00	1000.00	.	.
TRG0253-264	I-25 AND SH 119 PARK-N-RIDE		.	1.00	25000.00	.	.
STA3852-015	US 385 HOLYOKE NORTH		.	1.00	2000.00	.	.
NHPP0343-048	US 34 (MP 169.3-171.4)		.	1.00	5000.00	.	.
STU0252-457	I-25:ALAMEDA RIVER PH 2.0		.	1.00	75000.00	.	.
SHE0242-087	US 24 SAFETY IMPRVMENTS, E OF		.	1.00	5000.00	.	.
STR064A-010	SH 64 AND SH 13 AT MEEKER		.	1.00	5000.00	.	.
C5502-097	US550 MP 117.28-126.06		.	1.00	20000.00	.	.
STRC090-011	US 50B AND SH71/CR18 INTERSEC		.	1.00	5000.00	.	.
STAM420-001	US 285 AT HWY 9C IMPROVEMENTS		.	1.00	90000.00	.	.
BR2854-148	INTERSECTION OF US 285 & SH 9		.			.	.
STM0091-046	ADA RAMP IMPROVEMENTS - FAIRP		.			.	.
STA0711-021	SH71: REGION LINE NORTH		.	1.00	25000.00	.	.
STR114A-015	SH114 SILLSVILLE SOUTH TO MP3		.	1.00	5000.00	.	.
2670703-487	I-70 BRIDGES OVER WARD ROAD-		.	1.00	5000.00	.	.
NHPP0701-252	I-70 RIFLE TO SILT SLAB REPLA		.	1.00	5000.00	.	.
IM025A-050	I25-MP103.9 - INTERSECTION DR		.	1.00	5000.00	.	.
STR318A-001	SH 318 MP 0 - 12.5 MOFFAT COU		.	1.00	5000.00	.	.
STR109A-019	M-22-AY BRIDGE REHAB ON SH109		.	1.00	10000.00	.	.
NHPP0021-041	SH2 RESURFACING MLK TO 52ND		.	1.00	5000.00	.	.
STR0641-107	SH 13 MM 104-128.1 IN MOFFAT		.	1.00	2000.00	.	.
NHPP083A-046	SH83 RESURFACING STROH RD TO		.	1.00	5000.00	.	.
NHPP0063-048	US6 / 20 ROAD INTERSECTION IM		.	1.00	10000.00	.	.

COLORADO DEPARTMENT OF TRANSPORTATION
ITEM UNIT COSTS BY PROJECTS -- 2022 COST DATA

11:31 Wednesday, March 8, 2023 660

PROJECT NUMBER	ITEM NUMBER/ PROJECT LOCATION	ITEM DESCRIPTION/ PROJECT LOCATION	DATE LET	UNIT/ QUANTITY	ENGR. EST.	AVERAGE BID	AWARDED BID
=====	700-70380	F/A Erosion Ctrl		Force Acct	=====		
NHM175-029		CANON CITY, CO	.	1.00	5000.00	.	.
NHPP0931-033		SH93:US6 TO 58TH RESURFACING	.	1.00	5000.00	.	.
NHPP0502-090		SH 50 MP 134.6-136 GUNNISON C	.	1.00	5000.00	.	.
STA0361-129		US 36: HYGIENE RD AND NELSON	.	1.00	5000.00	.	.
BR012A-048		CO 12 STRUCTURE P-17-F AT MP	.	1.00	5000.00	.	.
STA385A-016		SH 385 MP 97.76	.	1.00	10000.00	.	.
STR096A-050		SH 96 MP 168.99 TO 193.77	.	1.00	5000.00	.	.
		WEIGHTED AVERAGE FOR THE FOURTH QUARTER		35.00	11085.71	.	.
		WEIGHTED AVERAGE FOR THE YEAR		96.00	8227.60	.	.
=====	700-70495	F/A Asbestos Abatement Work		Force Acct	=====		
ITS0703-477		ITS EQUIPMENT UPGRADE AT EJMT	.	1.00	5000.00	.	.
		WEIGHTED AVERAGE FOR THE FIRST QUARTER		1.00	5000.00	.	.
		WEIGHTED AVERAGE FOR THE YEAR		1.00	5000.00	.	.
=====	700-70496	F/A Lead Abatement Work		Force Acct	=====		
ITS0703-477		ITS EQUIPMENT UPGRADE AT EJMT	.	1.00	5000.00	.	.
		WEIGHTED AVERAGE FOR THE FIRST QUARTER		1.00	5000.00	.	.
		WEIGHTED AVERAGE FOR THE YEAR		1.00	5000.00	.	.
=====	700-70530	F/A Drainage Improvement		Force Acct	=====		
NHPP083A-046		SH83 RESURFACING STROH RD TO	.	1.00	5000.00	.	.
		WEIGHTED AVERAGE FOR THE FOURTH QUARTER		1.00	5000.00	.	.
		WEIGHTED AVERAGE FOR THE YEAR		1.00	5000.00	.	.
=====	700-70587	F/A Hazardous Waste Disposal		Force Acct	=====		
NHPP0063-063			.	1.00	10000.00	.	.
NHPP 0761-238		I-76 DAHLIA TO YORK	.	1.00	7000.00	.	.

COLORADO DEPARTMENT OF TRANSPORTATION
ITEM UNIT COSTS BY PROJECTS -- 2022 COST DATA

11:31 Wednesday, March 8, 2023 661

PROJECT NUMBER	ITEM NUMBER/ PROJECT LOCATION	ITEM DESCRIPTION/ PROJECT LOCATION	DATE LET	UNIT/ QUANTITY	ENGR. EST.	AVERAGE BID	AWARDED BID
===== 700-70587 F/A Hazardous Waste Disposal Force Acct =====							
C0761-239				1.00	10000.00	.	.
NHM765-007							
	WEIGHTED AVERAGE FOR THE FIRST QUARTER			3.00	9000.00	.	.
NHPP0063-054		US 6 FROM I70-B TO 33 RD. (MP .		1.00	10000.00	.	.
NHPP0701-231		I-70 SALT WASH BRIDGES SCOUR .		1.00	5000.00	.	.
	WEIGHTED AVERAGE FOR THE THIRD QUARTER			2.00	7500.00	.	.
STU0252-457		I-25:ALAMEDA RIVER PH 2.0 .		1.00	150000.00	.	.
NHPP0063-048		US6 / 20 ROAD INTERSECTION IM .		1.00	10000.00	.	.
	WEIGHTED AVERAGE FOR THE FOURTH QUARTER			2.00	80000.00	.	.
	WEIGHTED AVERAGE FOR THE YEAR			7.00	28857.14	.	.
===== 700-70589 F/A Environ Health & Safety Mgmt Force Acct =====							
NHPP 0761-238		I-76 DAHLIA TO YORK .		2.00	7500.00	.	.
C0761-239				1.00	5000.00	.	.
ER007A-035		Various locations on SH 141 a .		1.00	4000.00	.	.
STR R500-171							
	WEIGHTED AVERAGE FOR THE FIRST QUARTER			4.00	6000.00	.	.
STM1151-038		SH115 MP 27 TO MP 38 .		1.00	15000.00	.	.
2670703-479		I-70 BRIDGE OVER HARLAN .		1.00	5000.00	.	.
CM760-047		COLFAX AND QUAIL .		1.00	10000.00	.	.
	WEIGHTED AVERAGE FOR THE SECOND QUARTER			3.00	10000.00	.	.
NHPP0063-054		US 6 FROM I70-B TO 33 RD. (MP .		1.00	50000.00	.	.
C1211-099		SH 121 NORTH SGA SIGNALS .		1.00	8000.00	.	.

COLORADO DEPARTMENT OF TRANSPORTATION
ITEM UNIT COSTS BY PROJECTS -- 2022 COST DATA

11:31 Wednesday, March 8, 2023 662

PROJECT NUMBER	ITEM NUMBER/ PROJECT LOCATION	ITEM DESCRIPTION/ PROJECT LOCATION	DATE LET	UNIT/ QUANTITY	ENGR. EST.	AVERAGE BID	AWARDED BID
=====	700-70589	F/A Environ Health & Safety Mgmt		Force Acct	=====		
STAR100-374		5 STRUCTURES IN REGION 1	.	1.00	10000.00	.	.
		WEIGHTED AVERAGE FOR THE THIRD QUARTER		3.00	22666.67	.	.
STU0252-457		I-25:ALAMEDA RIVER PH 2.0	.	1.00	155000.00	.	.
C5502-097		US550 MP 117.28-126.06	.	1.00	10000.00	.	.
STAM420-001		US 285 AT HWY 9C IMPROVEMENTS	.	1.00	10000.00	.	.
BR2854-148		INTERSECTION OF US 285 & SH 9	.			.	.
STM0091-046		ADA RAMP IMPROVEMENTS - FAIRP	.			.	.
2670703-487		I-70 BRIDGES OVER WARD ROAD-	.	1.00	10000.00	.	.
NHPP0502-090		SH 50 MP 134.6-136 GUNNISON C	.	1.00	2000.00	.	.
		WEIGHTED AVERAGE FOR THE FOURTH QUARTER		5.00	37400.00	.	.
		WEIGHTED AVERAGE FOR THE YEAR		15.00	20600.00	.	.
=====	700-70595	F/A DRB On-Demand Committee		Force Acct	=====		
SHE2873-193		US 287 & CO 52 INTERSECTION I	.	1.00	4000.00	.	.
		WEIGHTED AVERAGE FOR THE THIRD QUARTER		1.00	4000.00	.	.
TRG0253-264		I-25 AND SH 119 PARK-N-RIDE	.	1.00	20000.00	.	.
		WEIGHTED AVERAGE FOR THE FOURTH QUARTER		1.00	20000.00	.	.
		WEIGHTED AVERAGE FOR THE YEAR		2.00	12000.00	.	.
=====	700-70596	Standing DRB		Force Acct	=====		
NHPP 0761-238		I-76 DAHLIA TO YORK	.	2.00	25000.00	.	.
C0761-239							
		WEIGHTED AVERAGE FOR THE FIRST QUARTER		2.00	25000.00	.	.
STM1151-038		SH115 MP 27 TO MP 38	.	1.00	25000.00	.	.
		WEIGHTED AVERAGE FOR THE SECOND QUARTER		1.00	25000.00	.	.
		WEIGHTED AVERAGE FOR THE YEAR		3.00	25000.00	.	.

COLORADO DEPARTMENT OF TRANSPORTATION
ITEM UNIT COSTS BY PROJECTS -- 2022 COST DATA

11:31 Wednesday, March 8, 2023 663

PROJECT NUMBER	ITEM NUMBER/ PROJECT LOCATION	ITEM DESCRIPTION/ PROJECT LOCATION	DATE LET	UNIT/ QUANTITY	ENGR. EST.	AVERAGE BID	AWARDED BID
===== 700-71000 CMGC Overrun Pool Force Acct =====							
NHPP0253-275		I-25 EXPRESS LANES SEGMENT 5 .		1.00	270000.00	.	.
CR100-362				1.00	80000.00	.	.
		WEIGHTED AVERAGE FOR THE FIRST QUARTER		2.00	175000.00	.	.
===== 700-71002 CDOT Risk Pool Force Acct =====							
BR0343-046		US 34 TIMBER BRIDGE REPL. PKG .		2.00	72900.00	.	.
FBR0343-047		US 6/US 34 TIMBER BRIDGE REPL				.	.
		WEIGHTED AVERAGE FOR THE THIRD QUARTER		2.00	72900.00	.	.
		WEIGHTED AVERAGE FOR THE YEAR		4.00	123950.00	.	.
===== 700-71002 CDOT Risk Pool Force Acct =====							
CR100-362				1.00	90000.00	.	.
ER007A-035				1.00	250000.00	.	.
		WEIGHTED AVERAGE FOR THE FIRST QUARTER		2.00	170000.00	.	.
NHPP0702-413		VAIL PASS AUX PHASE 1 CAP 2 .		1.00	542581.00	.	.
		WEIGHTED AVERAGE FOR THE SECOND QUARTER		1.00	542581.00	.	.
NHPP0702-414		VAIL PASS AUX PHASE 1 CAP 3 .		2.00	700000.00	.	.
FBR0702-423		VAIL PASS AUX BE F-12-AT PHAS				.	.
		WEIGHTED AVERAGE FOR THE THIRD QUARTER		2.00	700000.00	.	.
		WEIGHTED AVERAGE FOR THE YEAR		5.00	456516.20	.	.
===== 700-73351 F/A Force Acct =====							
STA0252-459				1.00	255000.00	.	.

COLORADO DEPARTMENT OF TRANSPORTATION
ITEM UNIT COSTS BY PROJECTS -- 2022 COST DATA

11:31 Wednesday, March 8, 2023 664

PROJECT NUMBER	ITEM NUMBER/ PROJECT LOCATION	ITEM DESCRIPTION/ PROJECT LOCATION	DATE LET	UNIT/ QUANTITY	ENGR. EST.	AVERAGE BID	AWARDED BID
===== 700-73351 F/A Force Acct =====							
NHPP0063-063				1.00	10000.00	.	.
STA 067A-048		Hwy 67A MP 0.00 TO MP 11.05 I		1.00	50000.00	.	.
NHPP0703-472				1.00	81600.00	.	.
BRC040-057				1.00	160000.00	.	.
WEIGHTED AVERAGE FOR THE FIRST QUARTER				5.00	111320.00	.	.
NH0504-911				1.00	30000.00	.	.
STM1151-038		SH115 MP 27 TO MP 38		1.00	100000.00	.	.
2670703-479		I-70 BRIDGE OVER HARLAN		1.00	50000.00	.	.
ER0702-420		PR I-70 GWC MATERIAL FLOWS 20		1.00	10000.00	.	.
NHC540-017		R2 CHAINUP STA @ KENOSHA/HOOS		1.00	100000.00	.	.
FSA052A-046		SH52 WCR 37 INTERSECTION IMPR		1.00	50000.00	.	.
WEIGHTED AVERAGE FOR THE SECOND QUARTER				6.00	56666.67	.	.
NHPP0063-054		US 6 FROM I70-B TO 33 RD. (MP		1.00	10000.00	.	.
ER0502-092		US 50 MP 204 EB MONARCH TRUCK		1.00	30000.00	.	.
SHE2873-193		US 287 & CO 52 INTERSECTION I		1.00	50000.00	.	.
WEIGHTED AVERAGE FOR THE THIRD QUARTER				3.00	30000.00	.	.
NHPP0701-253		I-70 EAST OF DEBEQUE		1.00	10000.00	.	.
SHE0242-087		US 24 SAFETY IMPRVMENTS, E OF		1.00	15000.00	.	.
STR064A-010		SH 64 AND SH 13 AT MEEKER		1.00	15000.00	.	.
NHPP0853-126		US85C: PLATTEVILLE NORTH MP (1.00	50000.00	.	.
STAM420-001		US 285 AT HWY 9C IMPROVEMENTS		1.00	50000.00	.	.
BR2854-148		INTERSECTION OF US 285 & SH 9				.	.
STM0091-046		ADA RAMP IMPROVEMENTS - FAIRP				.	.
2670703-487		I-70 BRIDGES OVER WARD ROAD-		1.00	50000.00	.	.
NHPP0701-252		I-70 RIFLE TO SILT SLAB REPLA		1.00	10000.00	.	.
NHPP083A-046		SH83 RESURFACING STROH RD TO		1.00	120000.00	.	.
NHPP0063-048		US6 / 20 ROAD INTERSECTION IM		1.00	10000.00	.	.
NHM175-029		CANON CITY, CO		1.00	40000.00	.	.
WEIGHTED AVERAGE FOR THE FOURTH QUARTER				10.00	37000.00	.	.
WEIGHTED AVERAGE FOR THE YEAR				24.00	56525.00	.	.
===== 700-90026 F/A Landscaping Force Acct =====							
STM1151-038		SH115 MP 27 TO MP 38		1.00	10000.00	.	.
WEIGHTED AVERAGE FOR THE SECOND QUARTER				1.00	10000.00	.	.

COLORADO DEPARTMENT OF TRANSPORTATION
 ITEM UNIT COSTS BY PROJECTS -- 2022 COST DATA

11:31 Wednesday, March 8, 2023 665

PROJECT NUMBER	ITEM NUMBER/ PROJECT LOCATION	ITEM DESCRIPTION/ PROJECT LOCATION	DATE LET	UNIT/ QUANTITY	ENGR. EST.	AVERAGE BID	AWARDED BID
=====	700-90026	F/A Landscaping		Force Acct	=====		
NHPP083A-046		SH83 RESURFACING STROH RD TO .		1.00	5000.00	.	.
		WEIGHTED AVERAGE FOR THE FOURTH QUARTER		1.00	5000.00	.	.
		WEIGHTED AVERAGE FOR THE YEAR		2.00	7500.00	.	.