



CO L O R A D O

Department of Transportation

2023 Cost Data

(January – March)

Compiled By:

Cost Estimating Services Unit of the
Construction Engineering Services Branch

May 18, 2023

2023 Cost Data: Construction

Table of Contents

Number
of Pages

| | |
|-----------------------------------|-----|
| List of 2023 Bid Projects | 2 |
| Bridge Cost per Square Feet | 1 |
| Item Unit Costs by Projects | 128 |

Colorado Cost Data

Foreword

The Colorado Department of Transportation's Cost Estimating Services Unit of the Construction Engineering Services Branch publishes the Cost Data Book annually. A joint effort has been made between CDOT's sections and the Cost Estimating Services Unit to gather and record cost data for this publication.

The following data includes weighted average prices for items on highway construction projects that were bid during the 2023 calendar year. Caution should be used in applying these historical averages to specific projects. Allowances for varying geographic, climatic, social, economic conditions and type of project should be made.

Changes and improvements are continually being made to update and increase the usefulness for future issues. Comments and suggestions for improvements for users of this publication are welcome.

Colorado Department of Transportation
 2023 Cost Data
 PROJECTS BID FROM 01/01/23 THROUGH 03/31/23

12:18 Wednesday, May 17, 2023 1

| BID LETTING | CONTRACTOR/ PROJECT NUMBER | LOCATION | DIST | TERRAIN | BIDS | AWARDED BID | INDEX |
|----------------|--|--|------|---------|------|-----------------|--------|
| 20230105 | Straight Stripe Painting, Inc. MTCER500-221 | REGION 5 | 5 | R | 2 | \$2,089,265.00 | 107.41 |
| 20230112 | Kilgore Companies, LLC dba Elam NHPP0701-250 | Construc I-70B: DDI TO 24 RD, MAIN ST T | 3 | U | 2 | \$9,490,148.53 | 94.56 |
| 20230112 | CASTLE ROCK CONST. CO. OF COLO, STR2871-040 | LLC US 287 MP 0.0 TO MP 122 VARIOU | 2 | P | 5 | \$1,853,073.44 | 115.82 |
| 20230112 | OLDCASTLE SW GROUP, INC. STA172A-022 | SH 172 IGNACIO TO ELMORE'S COR | 5 | R | 2 | \$14,126,484.41 | 106.27 |
| 20230119 | CC ENTRPRS TRAFFIC CONTROL SPECIALISTS SFTYR200-277 | REGION 2 WIDE, VARIOUS HWY & C | 2 | R | 2 | \$1,636,786.00 | 109.12 |
| 20230126 | BRANNAN SAND AND GRAVEL, LLC STA066A-008 | SH 66 @ WCR 7 | 4 | R | 5 | \$2,330,855.24 | 98.45 |
| 20230126 | COULSON EXCAVATING COMPANY FSA0853-123 | US 85 AND WCR 66 LEFT TURN ACC | 4 | P | 6 | \$1,223,303.25 | 101.94 |
| 20230126 | ABCO CONTRACTING, INC. NHPPR100-383 | I70 OVER WASHINGTON ST | 1 | U | 3 | \$1,850,028.00 | 123.34 |
| 20230202 | Lumin8 Transportation Tech. C0342-066 | US 034A (MP 113-150) | 4 | P | 3 | \$558,097.50 | 117.53 |
| 20230207 | RLW/SEMA, A Joint Venture NHPP0253-296 | I-25 @ LCR 16 (MP 253.8-254.5) | 4 | U | 1 | \$3,507,949.39 | 107.82 |
| 20230216 | MCATEE CONSTRUCTION CO. STA1381-011 | SH 138 STERLING NORTH PART 2 | 4 | R | 1 | \$12,796,063.70 | 116.33 |
| 20230216 | KSK, LLC STM C440-013 | R3 EAGLE RESIDENCY ADA RAMP IM | 3 | M | 1 | \$715,000.00 | 116.02 |
| 20230216 | AMERICAN WEST CONSTRUCTION, LLC C1601-084 | US 160 SECTION3 PRIORITY CULVE | 5 | M | 2 | \$2,095,832.00 | 104.61 |
| 20230216 | Meridian Engineering Co. C133A-052 | SH 133 ROCKFALL N OF MCCLURE P | 3 | M | 4 | \$3,896,461.00 | 130.03 |
| 20230216 | AMERICAN WEST CONSTRUCTION, LLC C0703-498 | EISENHOWER JOHNSON MEMORIAL TU | 1 | M | 3 | \$6,596,527.00 | 119.84 |
| 20230216 | Bixby Electric, Inc. C 1601-086 | MAPLE & CHESTNUT SIGNALS AT IN | 5 | U | 1 | \$1,634,083.00 | 125.39 |
| 20230216 | KSK, LLC C0881-036 | R1 CURB RAMPS-SH88B & US285D | 1 | U | 4 | \$2,475,000.00 | 68.75 |

Colorado Department of Transportation
 2023 Cost Data
 PROJECTS BID FROM 01/01/23 THROUGH 03/31/23

12:18 Wednesday, May 17, 2023 2

| BID LETTING | CONTRACTOR/ PROJECT NUMBER | LOCATION | DIST | TERRAIN | BIDS | AWARDED BID | INDEX | |
|----------------|--|--------------------------------|------|---------|--------|-----------------|------------------|--------|
| 20230216 | OLDCASTLE SW GROUP, INC. NHPP0701-256 | I-70B/31.5 RD MESA COUNTY | 3 | U | 2 | \$545,861.50 | 112.11 | |
| 20230302 | Native Sun Materials Inc SHE067A-044 | SH 67F M.P. 56.5-57.6 AND SH 6 | 2 | M | 1 | \$2,021,561.69 | 67.39 | |
| 20230302 | Scodeller Construction, Inc. STRR300-265 | MOUNTAIN RE FY23 CRACK SEALS | 3 | M | 1 | \$1,194,545.00 | 133.83 | |
| 20230302 | ABCO CONTRACTING, INC. NHPP0253-290 | I25 @ 58TH AND 62ND | 1 | U | 3 | \$4,128,231.00 | 97.81 | |
| 20230309 | OLDCASTLE SW GROUP, INC. STR194A-002 | SH194A SUR. TREAT.& DRAI IMP M | 2 | P | 2 | \$5,695,695.99 | 98.20 | |
| 20230316 | ENGINEERING AND CONSTRUCTION FBR 0703-520 | EISENHOWER-JOHNSON MEMORIAL TU | 1 | M | 2 | \$23,979,880.00 | 111.51 | |
| 20230316 | ROADSAFE TRAFFIC SYSTEMS, INC MTCER300-276 | I-70 MM 116-207, US 6F MM 208. | 3 | M | 2 | \$2,546,291.82 | 87.23 | |
| 20230330 | COULSON EXCAVATING COMPANY STA257A-008 | SH 257 WINDSOR RESURFACING | 4 | R | 2 | \$6,035,626.55 | 77.36 | |
| 20230330 | HARRISON WESTERN CONSTRUCTION CORP. NHPP R100-376 | VARIOUS LOCATIONS IN REGION 1 | 1 | R | 2 | \$2,924,208.00 | 115.30 | |
| 20230331 | STRUCTURES, INC. ER0703-524 | STRUCTURE F-13-P, EB I-70 EXIT | 1 | M | 3 | \$837,006.00 | 100.00 | |
| | | | | | ===== | ===== | ===== | |
| | | | | | TOTALS | 67 | \$118,783,865.01 | 104.02 |

2023 Cost Data

BRIDGE COST PER SQUARE FOOT
(01/01/23 THROUGH 03/31/23)

| DATE LET | PROJECT NUMBER/ PROJECT LOCATION | TERR/ BRIDGE ID | LENGTH | WIDTH | TOTAL SQUARE FT | TOTAL COST | COST PER SQUARE FOOT |
|----------|-------------------------------------|--------------------|------------------------|----------------|--------------------|---------------|-------------------------|
| | | BRIDGE REPAIR | | | | | |
| 230302 | NHPP0253-290 I25 @ 58TH AND 62ND | U | | | | | |
| | | E-17-OX | 191.5000 | 239.0000 | 45768.5 | \$1,524,362 | \$33.31 |
| | | E-17-OW | 168.5000 | 245.0000 | 41282.5 | \$1,446,538 | \$35.04 |
| | | | WEIGHTED AVERAGE COST: | | | | |
| | | | | NEW STRUCTURES | 87051.0 | \$2,970,900 | \$34.13 |

| PROJECT NUMBER | ITEM NUMBER/ PROJECT LOCATION | ITEM DESCRIPTION/ PROJECT LOCATION | DATE LET | UNIT/ QUANTITY | ENGR. EST. | AVERAGE BID | AWARDED BID |
|-----------------|--|---------------------------------------|----------|-------------------|------------|-------------|-------------|
| ===== 201-00000 | | Clear and Grub | | LUMP SUM | ===== | | |
| STA172A-022 | | SH 172 IGNACIO TO ELMORE'S CO | 01/12/23 | 1.00 | 20000.00 | 21924.61 | 29219.22 |
| STA066A-008 | | SH 66 @ WCR 7 | 01/26/23 | 1.00 | 20000.00 | 30160.00 | 10850.00 |
| NHPP0253-296 | | I-25 @ LCR 16 (MP 253.8-254.5 | 02/07/23 | 1.00 | 6422.61 | 6872.20 | 6872.20 |
| C1601-084 | | US 160 SECTION3 PRIORITY CULV | 02/16/23 | 1.00 | 10000.00 | 183534.59 | 338000.00 |
| NHPP0701-256 | | I-70B/31.5 RD MESA COUNTY | 02/16/23 | 1.00 | 20000.00 | 22500.00 | 20000.00 |
| SHE067A-044 | | SH 67F M.P. 56.5-57.6 AND SH | 03/02/23 | 1.00 | 30000.00 | 15924.69 | 15924.69 |
| STA257A-008 | | SH 257 WINDSOR RESURFACING | 03/30/23 | 1.00 | 10000.00 | 10425.00 | 11500.00 |
| NHPP R100-376 | | VARIOUS LOCATIONS IN REGION 1 | 03/30/23 | 1.00 | 8000.00 | 29150.00 | 8300.00 |
| | WEIGHTED AVERAGE FOR THE FIRST QUARTER | | | 8.00 | 15552.83 | 41686.19 | 55083.26 |
| | WEIGHTED AVERAGE FOR THE YEAR | | | 8.00 | 15552.83 | 41686.19 | 55083.26 |
| ===== 201-00001 | | Clear and Grub | | Acre | ===== | | |
| C133A-052 | | SH 133 ROCKFALL N OF MCCLURE | 02/16/23 | 4.00 | 35000.00 | 9043.75 | 10000.00 |
| | WEIGHTED AVERAGE FOR THE FIRST QUARTER | | | 4.00 | 35000.00 | 9043.75 | 10000.00 |
| | WEIGHTED AVERAGE FOR THE YEAR | | | 4.00 | 35000.00 | 9043.75 | 10000.00 |
| ===== 201-00005 | | Rem of Debris | | LUMP SUM | ===== | | |
| STA172A-022 | | SH 172 IGNACIO TO ELMORE'S CO | 01/12/23 | 1.00 | 1500.00 | 9467.34 | 9154.68 |
| NHPPR100-383 | | I70 OVER WASHINGTON ST | 01/26/23 | 1.00 | 15600.00 | 20841.43 | 11000.00 |
| | WEIGHTED AVERAGE FOR THE FIRST QUARTER | | | 2.00 | 8550.00 | 16291.79 | 10077.34 |
| | WEIGHTED AVERAGE FOR THE YEAR | | | 2.00 | 8550.00 | 16291.79 | 10077.34 |
| ===== 202-00001 | | Rem Structure | | Each | ===== | | |
| STA172A-022 | | SH 172 IGNACIO TO ELMORE'S CO | 01/12/23 | 1.00 | 1500.00 | 5335.76 | 5041.52 |
| C1601-084 | | US 160 SECTION3 PRIORITY CULV | 02/16/23 | 4.00 | 8250.00 | 14026.79 | 5800.00 |
| | WEIGHTED AVERAGE FOR THE FIRST QUARTER | | | 5.00 | 6900.00 | 12288.59 | 5648.30 |
| | WEIGHTED AVERAGE FOR THE YEAR | | | 5.00 | 6900.00 | 12288.59 | 5648.30 |
| ===== 202-00003 | | Rem of Structure (Spec) | | LUMP SUM | ===== | | |
| STA257A-008 | | SH 257 WINDSOR RESURFACING | 03/30/23 | 1.00 | 5000.00 | 3880.00 | 3500.00 |
| | WEIGHTED AVERAGE FOR THE FIRST QUARTER | | | 1.00 | 5000.00 | 3880.00 | 3500.00 |
| | WEIGHTED AVERAGE FOR THE YEAR | | | 1.00 | 5000.00 | 3880.00 | 3500.00 |

COLORADO DEPARTMENT OF TRANSPORTATION
 ITEM UNIT COSTS BY PROJECTS -- 2023 COST DATA

12:26 Wednesday, May 17, 2023 2

| PROJECT NUMBER | ITEM NUMBER/ PROJECT LOCATION | ITEM DESCRIPTION/ PROJECT LOCATION | DATE LET | UNIT/ QUANTITY | ENGR. EST. | AVERAGE BID | AWARDED BID |
|----------------|----------------------------------|--|----------|-------------------|------------|-------------|-------------|
| ===== | 202-00010 | Rem Tree | | Each | ===== | ===== | ===== |
| SHE067A-044 | | SH 67F M.P. 56.5-57.6 AND SH | 03/02/23 | 1.00 | 1000.00 | 1306.80 | 1306.80 |
| | | WEIGHTED AVERAGE FOR THE FIRST QUARTER | | 1.00 | 1000.00 | 1306.80 | 1306.80 |
| | | WEIGHTED AVERAGE FOR THE YEAR | | 1.00 | 1000.00 | 1306.80 | 1306.80 |
| ===== | 202-00014 | Brush Clearing | | Hour | ===== | ===== | ===== |
| STA172A-022 | | SH 172 IGNACIO TO ELMORE'S CO | 01/12/23 | 20.00 | 250.00 | 354.92 | 317.84 |
| | | WEIGHTED AVERAGE FOR THE FIRST QUARTER | | 20.00 | 250.00 | 354.92 | 317.84 |
| | | WEIGHTED AVERAGE FOR THE YEAR | | 20.00 | 250.00 | 354.92 | 317.84 |
| ===== | 202-00019 | Rem Inlet | | Each | ===== | ===== | ===== |
| STA172A-022 | | SH 172 IGNACIO TO ELMORE'S CO | 01/12/23 | 1.00 | 1000.00 | 3693.56 | 5027.12 |
| NHPPR100-383 | | I70 OVER WASHINGTON ST | 01/26/23 | 1.00 | 1400.00 | 10953.07 | 6500.00 |
| NHPP0253-296 | | I-25 @ LCR 16 (MP 253.8-254.5 | 02/07/23 | 1.00 | 1583.43 | 1694.27 | 1694.27 |
| C0703-498 | | EISENHOWER JOHNSON MEMORIAL T | 02/16/23 | 1.00 | 2000.00 | 2342.72 | 1500.00 |
| NHPP0701-256 | | I-70B/31.5 RD MESA COUNTY | 02/16/23 | 1.00 | 2000.00 | 2800.00 | 2500.00 |
| | | WEIGHTED AVERAGE FOR THE FIRST QUARTER | | 5.00 | 1596.69 | 4960.80 | 3444.28 |
| | | WEIGHTED AVERAGE FOR THE YEAR | | 5.00 | 1596.69 | 4960.80 | 3444.28 |
| ===== | 202-00020 | Rem CBC | | Each | ===== | ===== | ===== |
| STA1381-011 | | SH 138 STERLING NORTH PART 2 | 02/16/23 | 2.00 | 2000.00 | 6600.00 | 6600.00 |
| | | WEIGHTED AVERAGE FOR THE FIRST QUARTER | | 2.00 | 2000.00 | 6600.00 | 6600.00 |
| | | WEIGHTED AVERAGE FOR THE YEAR | | 2.00 | 2000.00 | 6600.00 | 6600.00 |
| ===== | 202-00026 | Rem S and D Pave | | Sq Yard | ===== | ===== | ===== |
| STR194A-002 | | SH194A SUR. TREAT.& DRAI IMP | 03/09/23 | 171.00 | 20.00 | 36.50 | 28.00 |
| | | WEIGHTED AVERAGE FOR THE FIRST QUARTER | | 171.00 | 20.00 | 36.50 | 28.00 |
| | | WEIGHTED AVERAGE FOR THE YEAR | | 171.00 | 20.00 | 36.50 | 28.00 |

| PROJECT NUMBER | ITEM NUMBER/ PROJECT LOCATION | ITEM DESCRIPTION/ PROJECT LOCATION | DATE LET | UNIT/ QUANTITY | ENGR. EST. | AVERAGE BID | AWARDED BID |
|-----------------|----------------------------------|--|----------|-------------------|------------|-------------|-------------|
| ===== 202-00035 | | Rem Pipe | | Lin Foot | ===== | | |
| STA172A-022 | | SH 172 IGNACIO TO ELMORE'S CO | 01/12/23 | 223.00 | 25.00 | 59.29 | 70.88 |
| FSA0853-123 | | US 85 AND WCR 66 LEFT TURN AC | 01/26/23 | 55.00 | 50.00 | 43.17 | 38.00 |
| NHPPR100-383 | | I70 OVER WASHINGTON ST | 01/26/23 | 120.00 | 20.00 | 165.70 | 260.00 |
| NHPP0253-296 | | I-25 @ LCR 16 (MP 253.8-254.5 | 02/07/23 | 58.00 | 67.88 | 72.63 | 72.63 |
| C0703-498 | | EISENHOWER JOHNSON MEMORIAL T | 02/16/23 | 58.00 | 60.00 | 77.10 | 58.00 |
| STA1381-011 | | SH 138 STERLING NORTH PART 2 | 02/16/23 | 222.00 | 60.00 | 60.00 | 60.00 |
| C1601-084 | | US 160 SECTION3 PRIORITY CULV | 02/16/23 | 20.00 | 200.00 | 307.72 | 150.00 |
| NHPP0701-256 | | I-70B/31.5 RD MESA COUNTY | 02/16/23 | 8.00 | 150.00 | 78.50 | 100.00 |
| | | WEIGHTED AVERAGE FOR THE FIRST QUARTER | | 764.00 | 47.99 | 88.00 | 96.59 |
| | | WEIGHTED AVERAGE FOR THE YEAR | | 764.00 | 47.99 | 88.00 | 96.59 |
| ===== 202-00037 | | Rem of End Section | | Each | ===== | | |
| STA172A-022 | | SH 172 IGNACIO TO ELMORE'S CO | 01/12/23 | 1.00 | 500.00 | 1606.47 | 2496.93 |
| FSA0853-123 | | US 85 AND WCR 66 LEFT TURN AC | 01/26/23 | 4.00 | 500.00 | 434.00 | 150.00 |
| NHPP0253-296 | | I-25 @ LCR 16 (MP 253.8-254.5 | 02/07/23 | 2.00 | 294.20 | 314.79 | 314.79 |
| | | WEIGHTED AVERAGE FOR THE FIRST QUARTER | | 7.00 | 441.20 | 509.23 | 532.36 |
| | | WEIGHTED AVERAGE FOR THE YEAR | | 7.00 | 441.20 | 509.23 | 532.36 |
| ===== 202-00090 | | Rem Delineator | | Each | ===== | | |
| FSA0853-123 | | US 85 AND WCR 66 LEFT TURN AC | 01/26/23 | 38.00 | 20.00 | 28.33 | 21.00 |
| STA066A-008 | | SH 66 @ WCR 7 | 01/26/23 | 63.00 | 25.00 | 52.59 | 28.00 |
| C1601-084 | | US 160 SECTION3 PRIORITY CULV | 02/16/23 | 18.00 | 20.00 | 66.18 | 10.00 |
| SHE067A-044 | | SH 67F M.P. 56.5-57.6 AND SH | 03/02/23 | 75.00 | 10.00 | 17.82 | 17.82 |
| NHPP R100-376 | | VARIOUS LOCATIONS IN REGION 1 | 03/30/23 | 13.00 | 18.11 | 45.07 | 35.00 |
| | | WEIGHTED AVERAGE FOR THE FIRST QUARTER | | 207.00 | 17.78 | 41.05 | 21.90 |
| | | WEIGHTED AVERAGE FOR THE YEAR | | 207.00 | 17.78 | 41.05 | 21.90 |
| ===== 202-00190 | | Rem of Conc Median Cover Matl | | Sq Yard | ===== | | |
| C 1601-086 | | MAPLE & CHESTNUT SIGNALS AT I | 02/16/23 | 14.00 | 60.00 | 72.00 | 72.00 |
| | | WEIGHTED AVERAGE FOR THE FIRST QUARTER | | 14.00 | 60.00 | 72.00 | 72.00 |
| | | WEIGHTED AVERAGE FOR THE YEAR | | 14.00 | 60.00 | 72.00 | 72.00 |

COLORADO DEPARTMENT OF TRANSPORTATION
ITEM UNIT COSTS BY PROJECTS -- 2023 COST DATA

12:26 Wednesday, May 17, 2023 4

| PROJECT NUMBER | ITEM NUMBER/ PROJECT LOCATION | ITEM DESCRIPTION/ PROJECT LOCATION | DATE LET | UNIT/ QUANTITY | ENGR. EST. | AVERAGE BID | AWARDED BID |
|-----------------|--|---------------------------------------|----------|-------------------|------------|-------------|-------------|
| ===== 202-00200 | | Rem Sidewalk | | Sq Yard | | | |
| STA172A-022 | | SH 172 IGNACIO TO ELMORE'S CO | 01/12/23 | 1,088.00 | 18.00 | 22.85 | 27.79 |
| STM C440-013 | | R3 EAGLE RESIDENCY ADA RAMP I | 02/16/23 | 282.00 | 50.00 | 47.00 | 47.00 |
| C0881-036 | | R1 CURB RAMPS-SH88B & US285D | 02/16/23 | 3,238.00 | 70.00 | 28.50 | 19.00 |
| STA257A-008 | | SH 257 WINDSOR RESURFACING | 03/30/23 | 240.00 | 50.00 | 17.88 | 15.50 |
| | WEIGHTED AVERAGE FOR THE FIRST QUARTER | | | 4,848.00 | 56.18 | 27.73 | 22.43 |
| | WEIGHTED AVERAGE FOR THE YEAR | | | 4,848.00 | 56.18 | 27.73 | 22.43 |
| ===== 202-00201 | | Rem Curb | | Lin Foot | | | |
| STA172A-022 | | SH 172 IGNACIO TO ELMORE'S CO | 01/12/23 | 48.00 | 15.00 | 60.83 | 92.85 |
| | WEIGHTED AVERAGE FOR THE FIRST QUARTER | | | 48.00 | 15.00 | 60.83 | 92.85 |
| | WEIGHTED AVERAGE FOR THE YEAR | | | 48.00 | 15.00 | 60.83 | 92.85 |
| ===== 202-00202 | | Rem Gutter | | Lin Foot | | | |
| STA172A-022 | | SH 172 IGNACIO TO ELMORE'S CO | 01/12/23 | 94.00 | 25.00 | 54.95 | 82.39 |
| | WEIGHTED AVERAGE FOR THE FIRST QUARTER | | | 94.00 | 25.00 | 54.95 | 82.39 |
| | WEIGHTED AVERAGE FOR THE YEAR | | | 94.00 | 25.00 | 54.95 | 82.39 |
| ===== 202-00203 | | Rem Curb and Gutter | | Lin Foot | | | |
| STA172A-022 | | SH 172 IGNACIO TO ELMORE'S CO | 01/12/23 | 2,553.00 | 30.00 | 19.23 | 27.55 |
| STM C440-013 | | R3 EAGLE RESIDENCY ADA RAMP I | 02/16/23 | 488.00 | 20.00 | 32.00 | 32.00 |
| C0881-036 | | R1 CURB RAMPS-SH88B & US285D | 02/16/23 | 4,003.00 | 9.00 | 17.20 | 16.00 |
| STA257A-008 | | SH 257 WINDSOR RESURFACING | 03/30/23 | 430.00 | 25.00 | 9.38 | 11.50 |
| | WEIGHTED AVERAGE FOR THE FIRST QUARTER | | | 7,474.00 | 17.81 | 17.68 | 20.73 |
| | WEIGHTED AVERAGE FOR THE YEAR | | | 7,474.00 | 17.81 | 17.68 | 20.73 |
| ===== 202-00206 | | Rem Conc Curb Ramp | | Sq Yard | | | |
| STA172A-022 | | SH 172 IGNACIO TO ELMORE'S CO | 01/12/23 | 151.00 | 40.00 | 49.27 | 75.93 |

COLORADO DEPARTMENT OF TRANSPORTATION
ITEM UNIT COSTS BY PROJECTS -- 2023 COST DATA

12:26 Wednesday, May 17, 2023 5

| PROJECT NUMBER | ITEM NUMBER/ PROJECT LOCATION | ITEM DESCRIPTION/ PROJECT LOCATION | DATE LET | UNIT/ QUANTITY | ENGR. EST. | AVERAGE BID | AWARDED BID |
|----------------|--|---------------------------------------|----------|-------------------|------------|-------------|-------------|
| ===== | 202-00206 | Rem Conc Curb Ramp | | Sq Yard | ===== | ===== | ===== |
| C 1601-086 | | MAPLE & CHESTNUT SIGNALS AT I | 02/16/23 | 45.00 | 55.00 | 126.00 | 126.00 |
| STA257A-008 | | SH 257 WINDSOR RESURFACING | 03/30/23 | 10.00 | 40.00 | 34.75 | 50.00 |
| | WEIGHTED AVERAGE FOR THE FIRST QUARTER | | | 206.00 | 43.28 | 57.88 | 85.61 |
| | WEIGHTED AVERAGE FOR THE YEAR | | | 206.00 | 43.28 | 57.88 | 85.61 |
| ===== | 202-00207 | Rem of Brick Pavers | | Sq Yard | ===== | ===== | ===== |
| STM C440-013 | | R3 EAGLE RESIDENCY ADA RAMP I | 02/16/23 | 82.00 | 30.00 | 38.00 | 38.00 |
| | WEIGHTED AVERAGE FOR THE FIRST QUARTER | | | 82.00 | 30.00 | 38.00 | 38.00 |
| | WEIGHTED AVERAGE FOR THE YEAR | | | 82.00 | 30.00 | 38.00 | 38.00 |
| ===== | 202-00210 | Rem Conc Pavement | | Sq Yard | ===== | ===== | ===== |
| STA172A-022 | | SH 172 IGNACIO TO ELMORE'S CO | 01/12/23 | 14.00 | 50.00 | 212.10 | 309.19 |
| STR2871-040 | | US 287 MP 0.0 TO MP 122 VARIO | 01/12/23 | 4,140.00 | 30.00 | 81.62 | 72.27 |
| FSA0853-123 | | US 85 AND WCR 66 LEFT TURN AC | 01/26/23 | 87.00 | 20.00 | 27.83 | 32.00 |
| NHPPR100-383 | | I70 OVER WASHINGTON ST | 01/26/23 | 180.00 | 20.00 | 155.79 | 138.00 |
| STA1381-011 | | SH 138 STERLING NORTH PART 2 | 02/16/23 | 99.00 | 25.00 | 450.00 | 450.00 |
| STM C440-013 | | R3 EAGLE RESIDENCY ADA RAMP I | 02/16/23 | 36.00 | 35.00 | 54.00 | 54.00 |
| C0881-036 | | R1 CURB RAMPS-SH88B & US285D | 02/16/23 | 245.00 | 25.00 | 36.50 | 22.00 |
| NHPP0253-290 | | I25 @ 58TH AND 62ND | 03/02/23 | 278.00 | 50.00 | 181.06 | 90.00 |
| | WEIGHTED AVERAGE FOR THE FIRST QUARTER | | | 5,079.00 | 30.32 | 85.41 | 80.34 |
| | WEIGHTED AVERAGE FOR THE YEAR | | | 5,079.00 | 30.32 | 85.41 | 80.34 |
| ===== | 202-00215 | Rem Conc Pvmt (Planing) | | Sq Yard | ===== | ===== | ===== |
| NHPPR100-383 | | I70 OVER WASHINGTON ST | 01/26/23 | 320.00 | 30.00 | 76.71 | 76.00 |
| | WEIGHTED AVERAGE FOR THE FIRST QUARTER | | | 320.00 | 30.00 | 76.71 | 76.00 |
| | WEIGHTED AVERAGE FOR THE YEAR | | | 320.00 | 30.00 | 76.71 | 76.00 |
| ===== | 202-00217 | Rem Conc Pvmt (Planing) (Spec) | | Sq Yard | ===== | ===== | ===== |
| NHPP0253-290 | | I25 @ 58TH AND 62ND | 03/02/23 | 1,321.00 | 50.00 | 49.05 | 54.00 |
| | WEIGHTED AVERAGE FOR THE FIRST QUARTER | | | 1,321.00 | 50.00 | 49.05 | 54.00 |
| | WEIGHTED AVERAGE FOR THE YEAR | | | 1,321.00 | 50.00 | 49.05 | 54.00 |

| PROJECT NUMBER | ITEM NUMBER/ PROJECT LOCATION | ITEM DESCRIPTION/ PROJECT LOCATION | DATE LET | UNIT/ QUANTITY | ENGR. EST. | AVERAGE BID | AWARDED BID |
|-----------------|--|---------------------------------------|----------|-------------------|------------|-------------|-------------|
| ===== 202-00220 | | Rem Asphalt Mat | | Sq Yard | ===== | | |
| STA172A-022 | | SH 172 IGNACIO TO ELMORE'S CO | 01/12/23 | 1,395.00 | 15.00 | 38.09 | 21.38 |
| NHPP0701-250 | | I-70B: DDI TO 24 RD, MAIN ST | 01/12/23 | 1,638.00 | 8.00 | 24.85 | 33.70 |
| FSA0853-123 | | US 85 AND WCR 66 LEFT TURN AC | 01/26/23 | 1,416.00 | 25.00 | 20.33 | 7.00 |
| STA066A-008 | | SH 66 @ WCR 7 | 01/26/23 | 253.00 | 20.00 | 36.72 | 18.00 |
| NHPP0253-296 | | I-25 @ LCR 16 (MP 253.8-254.5 | 02/07/23 | 3,500.00 | 5.45 | 5.83 | 5.83 |
| C0703-498 | | EISENHOWER JOHNSON MEMORIAL T | 02/16/23 | 803.00 | 25.00 | 21.97 | 17.00 |
| STA1381-011 | | SH 138 STERLING NORTH PART 2 | 02/16/23 | 6,280.00 | 3.00 | 30.00 | 30.00 |
| C133A-052 | | SH 133 ROCKFALL N OF MCCLURE | 02/16/23 | 20.00 | 100.00 | 205.63 | 270.00 |
| STM C440-013 | | R3 EAGLE RESIDENCY ADA RAMP I | 02/16/23 | 147.00 | 30.00 | 41.00 | 41.00 |
| NHPP0701-256 | | I-70B/31.5 RD MESA COUNTY | 02/16/23 | 356.00 | 40.00 | 12.50 | 10.00 |
| C0881-036 | | R1 CURB RAMPS-SH88B & US285D | 02/16/23 | 890.00 | 100.00 | 31.65 | 14.00 |
| SHE067A-044 | | SH 67F M.P. 56.5-57.6 AND SH | 03/02/23 | 507.00 | 20.00 | 6.72 | 6.72 |
| STR194A-002 | | SH194A SUR. TREAT.& DRAI IMP | 03/09/23 | 166.00 | 37.00 | 40.00 | 30.00 |
| STA257A-008 | | SH 257 WINDSOR RESURFACING | 03/30/23 | 35,025.00 | 12.00 | 5.18 | 4.50 |
| | WEIGHTED AVERAGE FOR THE FIRST QUARTER | | | 52,396.00 | 12.95 | 11.53 | 9.84 |
| | WEIGHTED AVERAGE FOR THE YEAR | | | 52,396.00 | 12.95 | 11.53 | 9.84 |
| ===== 202-00226 | | Rem of Asph Mat (Special) | | Sq Yard | ===== | | |
| STA257A-008 | | SH 257 WINDSOR RESURFACING | 03/30/23 | 29.00 | 60.00 | 95.00 | 30.00 |
| | WEIGHTED AVERAGE FOR THE FIRST QUARTER | | | 29.00 | 60.00 | 95.00 | 30.00 |
| | WEIGHTED AVERAGE FOR THE YEAR | | | 29.00 | 60.00 | 95.00 | 30.00 |
| ===== 202-00240 | | Rem Asphalt Mat (Planning) | | Sq Yard | ===== | | |
| STA172A-022 | | SH 172 IGNACIO TO ELMORE'S CO | 01/12/23 | 50,265.00 | 4.00 | 3.84 | 4.53 |
| NHPP0701-250 | | I-70B: DDI TO 24 RD, MAIN ST | 01/12/23 | 342,490.00 | 3.00 | 2.08 | 2.35 |
| FSA0853-123 | | US 85 AND WCR 66 LEFT TURN AC | 01/26/23 | 284.00 | 20.00 | 22.25 | 12.50 |
| STA066A-008 | | SH 66 @ WCR 7 | 01/26/23 | 6,130.00 | 6.00 | 6.15 | 3.25 |
| C0703-498 | | EISENHOWER JOHNSON MEMORIAL T | 02/16/23 | 57,151.00 | 6.00 | 2.92 | 3.00 |
| STA1381-011 | | SH 138 STERLING NORTH PART 2 | 02/16/23 | 163,894.00 | 2.50 | 1.40 | 1.40 |
| C133A-052 | | SH 133 ROCKFALL N OF MCCLURE | 02/16/23 | 20.00 | 30.00 | 200.63 | 175.00 |
| NHPP0701-256 | | I-70B/31.5 RD MESA COUNTY | 02/16/23 | 135.00 | 25.00 | 45.00 | 45.00 |
| SHE067A-044 | | SH 67F M.P. 56.5-57.6 AND SH | 03/02/23 | 1,559.00 | 10.00 | 8.61 | 8.61 |
| STR194A-002 | | SH194A SUR. TREAT.& DRAI IMP | 03/09/23 | 4,269.00 | 7.00 | 12.00 | 8.00 |
| STA257A-008 | | SH 257 WINDSOR RESURFACING | 03/30/23 | 87,359.00 | 4.00 | 3.05 | 3.10 |
| | WEIGHTED AVERAGE FOR THE FIRST QUARTER | | | 713,556.00 | 3.39 | 2.57 | 2.50 |
| | WEIGHTED AVERAGE FOR THE YEAR | | | 713,556.00 | 3.39 | 2.57 | 2.50 |

COLORADO DEPARTMENT OF TRANSPORTATION
ITEM UNIT COSTS BY PROJECTS -- 2023 COST DATA

12:26 Wednesday, May 17, 2023 7

| PROJECT NUMBER | ITEM NUMBER/ PROJECT LOCATION | ITEM DESCRIPTION/ PROJECT LOCATION | DATE LET | UNIT/ QUANTITY | ENGR. EST. | AVERAGE BID | AWARDED BID |
|-----------------|--|---------------------------------------|----------|-------------------|------------|-------------|-------------|
| ===== 202-00246 | | Rem Asphalt Mat (Planing) (Special) | | Sq Yard | ===== | | |
| STA257A-008 | | SH 257 WINDSOR RESURFACING | 03/30/23 | 1,194.00 | 12.00 | 13.75 | 12.00 |
| ER0703-524 | | STRUCTURE F-13-P, EB I-70 EXI | 03/31/23 | 1,375.00 | 50.00 | 59.45 | 50.00 |
| | WEIGHTED AVERAGE FOR THE FIRST QUARTER | | | 2,569.00 | 32.34 | 42.69 | 32.34 |
| | WEIGHTED AVERAGE FOR THE YEAR | | | 2,569.00 | 32.34 | 42.69 | 32.34 |
| ===== 202-00250 | | Rem Pavement Marking | | Sq Foot | ===== | | |
| NHPP0701-250 | | I-70B: DDI TO 24 RD, MAIN ST | 01/12/23 | 89,014.00 | 3.00 | 0.90 | 0.60 |
| FSA0853-123 | | US 85 AND WCR 66 LEFT TURN AC | 01/26/23 | 1,600.00 | 10.00 | 6.83 | 6.50 |
| NHPPR100-383 | | I70 OVER WASHINGTON ST | 01/26/23 | 388.00 | 3.00 | 14.07 | 4.00 |
| STA066A-008 | | SH 66 @ WCR 7 | 01/26/23 | 15,654.00 | 2.50 | 0.81 | 0.80 |
| C0703-498 | | EISENHOWER JOHNSON MEMORIAL T | 02/16/23 | 496.00 | 10.00 | 7.17 | 6.00 |
| STM C440-013 | | R3 EAGLE RESIDENCY ADA RAMP I | 02/16/23 | 192.00 | 3.50 | 3.50 | 3.50 |
| C0881-036 | | R1 CURB RAMPS-SH88B & US285D | 02/16/23 | 878.00 | 1.00 | 11.25 | 3.00 |
| NHPP0253-290 | | I25 @ 58TH AND 62ND | 03/02/23 | 1,667.00 | 1.00 | 2.47 | 3.00 |
| SHE067A-044 | | SH 67F M.P. 56.5-57.6 AND SH | 03/02/23 | 1,000.00 | 2.00 | 5.05 | 5.05 |
| MTCER300-276 | | I-70 MM 116-207, US 6F MM 208 | 03/16/23 | 1,227,689.00 | 0.50 | 0.42 | 0.38 |
| STA257A-008 | | SH 257 WINDSOR RESURFACING | 03/30/23 | 23,000.00 | 2.50 | 1.08 | 0.80 |
| | WEIGHTED AVERAGE FOR THE FIRST QUARTER | | | 1,361,578.00 | 0.74 | 0.52 | 0.43 |
| | WEIGHTED AVERAGE FOR THE YEAR | | | 1,361,578.00 | 0.74 | 0.52 | 0.43 |
| ===== 202-00425 | | Rem Bridge Railing | | Lin Foot | ===== | | |
| NHPP0701-250 | | I-70B: DDI TO 24 RD, MAIN ST | 01/12/23 | 50.00 | 150.00 | 17.80 | 13.60 |
| STA1381-011 | | SH 138 STERLING NORTH PART 2 | 02/16/23 | 78.00 | 60.00 | 15.00 | 15.00 |
| STA257A-008 | | SH 257 WINDSOR RESURFACING | 03/30/23 | 140.00 | 40.00 | 51.38 | 66.00 |
| | WEIGHTED AVERAGE FOR THE FIRST QUARTER | | | 268.00 | 66.34 | 37.85 | 41.38 |
| | WEIGHTED AVERAGE FOR THE YEAR | | | 268.00 | 66.34 | 37.85 | 41.38 |
| ===== 202-00426 | | Rem Bridge Railing (Spec) | | Lin Foot | ===== | | |
| NHPPR100-383 | | I70 OVER WASHINGTON ST | 01/26/23 | 72.00 | 20.00 | 239.71 | 224.00 |
| | WEIGHTED AVERAGE FOR THE FIRST QUARTER | | | 72.00 | 20.00 | 239.71 | 224.00 |
| | WEIGHTED AVERAGE FOR THE YEAR | | | 72.00 | 20.00 | 239.71 | 224.00 |

COLORADO DEPARTMENT OF TRANSPORTATION
ITEM UNIT COSTS BY PROJECTS -- 2023 COST DATA

12:26 Wednesday, May 17, 2023 8

| PROJECT NUMBER | ITEM NUMBER/ PROJECT LOCATION | ITEM DESCRIPTION/ PROJECT LOCATION | DATE LET | UNIT/ QUANTITY | ENGR. EST. | AVERAGE BID | AWARDED BID |
|-----------------|--|---------------------------------------|----------|-------------------|------------|-------------|-------------|
| ===== 202-00450 | | Rem Port Present Str (1) | | Sq Yard | ===== | | |
| NHPP0253-290 | I25 @ 58TH AND 62ND | | 03/02/23 | 461.00 | 145.00 | 383.91 | 170.00 |
| | WEIGHTED AVERAGE FOR THE FIRST QUARTER | | | 461.00 | 145.00 | 383.91 | 170.00 |
| | WEIGHTED AVERAGE FOR THE YEAR | | | 461.00 | 145.00 | 383.91 | 170.00 |
| ===== 202-00453 | | Rem Port Present Str (2) | | Sq Yard | ===== | | |
| NHPPR100-383 | I70 OVER WASHINGTON ST | | 01/26/23 | 69.00 | 550.00 | 357.14 | 170.00 |
| NHPP0253-290 | I25 @ 58TH AND 62ND | | 03/02/23 | 461.00 | 360.00 | 537.64 | 265.00 |
| STA257A-008 | SH 257 WINDSOR RESURFACING | | 03/30/23 | 12.00 | 300.00 | 1300.00 | 1100.00 |
| ER0703-524 | STRUCTURE F-13-P, EB I-70 EXI | | 03/31/23 | 138.00 | 561.00 | 1281.38 | 561.00 |
| | WEIGHTED AVERAGE FOR THE FIRST QUARTER | | | 680.00 | 419.01 | 680.07 | 330.17 |
| | WEIGHTED AVERAGE FOR THE YEAR | | | 680.00 | 419.01 | 680.07 | 330.17 |
| ===== 202-00460 | | Rem Port Present Str (3) | | Sq Yard | ===== | | |
| NHPPR100-383 | I70 OVER WASHINGTON ST | | 01/26/23 | 34.00 | 1200.00 | 570.74 | 510.00 |
| NHPP0253-290 | I25 @ 58TH AND 62ND | | 03/02/23 | 93.00 | 510.00 | 1256.35 | 465.00 |
| STA257A-008 | SH 257 WINDSOR RESURFACING | | 03/30/23 | 4.00 | 500.00 | 2625.00 | 2050.00 |
| ER0703-524 | STRUCTURE F-13-P, EB I-70 EXI | | 03/31/23 | 28.00 | 892.00 | 2032.36 | 892.00 |
| | WEIGHTED AVERAGE FOR THE FIRST QUARTER | | | 159.00 | 724.57 | 1269.46 | 589.69 |
| | WEIGHTED AVERAGE FOR THE YEAR | | | 159.00 | 724.57 | 1269.46 | 589.69 |
| ===== 202-00502 | | Rem Port Present Str | | Cubic Yard | ===== | | |
| NHPPR100-383 | I70 OVER WASHINGTON ST | | 01/26/23 | 5.00 | 2000.00 | 1310.78 | 1300.00 |
| C1601-084 | US 160 SECTION3 PRIORITY CULV | | 02/16/23 | 3.00 | 2500.00 | 1343.60 | 720.00 |
| | WEIGHTED AVERAGE FOR THE FIRST QUARTER | | | 8.00 | 2187.50 | 1320.15 | 1082.50 |
| | WEIGHTED AVERAGE FOR THE YEAR | | | 8.00 | 2187.50 | 1320.15 | 1082.50 |
| ===== 202-00503 | | Rem Port Present Str | | Sq Yard | ===== | | |
| NHPPR100-383 | I70 OVER WASHINGTON ST | | 01/26/23 | 11.00 | 1500.00 | 896.26 | 890.00 |
| | WEIGHTED AVERAGE FOR THE FIRST QUARTER | | | 11.00 | 1500.00 | 896.26 | 890.00 |
| | WEIGHTED AVERAGE FOR THE YEAR | | | 11.00 | 1500.00 | 896.26 | 890.00 |

COLORADO DEPARTMENT OF TRANSPORTATION
ITEM UNIT COSTS BY PROJECTS -- 2023 COST DATA

12:26 Wednesday, May 17, 2023 9

| PROJECT NUMBER | ITEM NUMBER/ PROJECT LOCATION | ITEM DESCRIPTION/ PROJECT LOCATION | DATE LET | UNIT/ QUANTITY | ENGR. EST. | AVERAGE BID | AWARDED BID |
|----------------|----------------------------------|---------------------------------------|----------|-------------------|------------|-------------|-------------|
| ===== | 202-00504 | Rem Exp Device | | Lin Foot | ===== | | |
| NHPPR100-383 | | I70 OVER WASHINGTON ST | 01/26/23 | 302.00 | 300.00 | 590.83 | 261.00 |
| NHPP0253-290 | | I25 @ 58TH AND 62ND | 03/02/23 | 780.00 | 220.00 | 271.70 | 185.00 |
| | WEIGHTED | AVERAGE FOR THE FIRST QUARTER | | 1,082.00 | 242.33 | 360.77 | 206.21 |
| | | WEIGHTED AVERAGE FOR THE YEAR | | 1,082.00 | 242.33 | 360.77 | 206.21 |
| ===== | 202-00505 | Rem Port of Present Structure | | Sq Foot | ===== | | |
| C0703-498 | | EISENHOWER JOHNSON MEMORIAL T | 02/16/23 | 728.00 | 200.00 | 106.50 | 24.00 |
| NHPP0253-290 | | I25 @ 58TH AND 62ND | 03/02/23 | 29.00 | 250.00 | 646.24 | 300.00 |
| STA257A-008 | | SH 257 WINDSOR RESURFACING | 03/30/23 | 202.00 | 150.00 | 380.00 | 300.00 |
| | WEIGHTED | AVERAGE FOR THE FIRST QUARTER | | 959.00 | 190.98 | 165.36 | 90.48 |
| | | WEIGHTED AVERAGE FOR THE YEAR | | 959.00 | 190.98 | 165.36 | 90.48 |
| ===== | 202-00700 | Rem Light Standard | | Each | ===== | | |
| NHPP0253-296 | | I-25 @ LCR 16 (MP 253.8-254.5 | 02/07/23 | 1.00 | 505.92 | 541.33 | 541.33 |
| | WEIGHTED | AVERAGE FOR THE FIRST QUARTER | | 1.00 | 505.92 | 541.33 | 541.33 |
| | | WEIGHTED AVERAGE FOR THE YEAR | | 1.00 | 505.92 | 541.33 | 541.33 |
| ===== | 202-00705 | Rem Light Standard Foundation | | Each | ===== | | |
| NHPP0253-296 | | I-25 @ LCR 16 (MP 253.8-254.5 | 02/07/23 | 1.00 | 804.49 | 860.80 | 860.80 |
| | WEIGHTED | AVERAGE FOR THE FIRST QUARTER | | 1.00 | 804.49 | 860.80 | 860.80 |
| | | WEIGHTED AVERAGE FOR THE YEAR | | 1.00 | 804.49 | 860.80 | 860.80 |
| ===== | 202-00810 | Rem Ground Sign | | Each | ===== | | |
| STA066A-008 | | SH 66 @ WCR 7 | 01/26/23 | 12.00 | 170.00 | 166.72 | 148.30 |
| NHPP0253-296 | | I-25 @ LCR 16 (MP 253.8-254.5 | 02/07/23 | 2.00 | 93.29 | 99.82 | 99.82 |
| STA1381-011 | | SH 138 STERLING NORTH PART 2 | 02/16/23 | 93.00 | 165.00 | 160.00 | 160.00 |

| PROJECT NUMBER | ITEM NUMBER/ PROJECT LOCATION | ITEM DESCRIPTION/ PROJECT LOCATION | DATE LET | UNIT/ QUANTITY | ENGR. EST. | AVERAGE BID | AWARDED BID |
|----------------|--|---------------------------------------|----------|-------------------|------------|-------------|-------------|
| ===== | 202-00810 | Rem Ground Sign | | Each | ===== | ===== | ===== |
| SHE067A-044 | | SH 67F M.P. 56.5-57.6 AND SH | 03/02/23 | 12.00 | 150.00 | 237.60 | 237.60 |
| STR194A-002 | | SH194A SUR. TREAT.& DRAI IMP | 03/09/23 | 41.00 | 125.00 | 160.00 | 150.00 |
| STA257A-008 | | SH 257 WINDSOR RESURFACING | 03/30/23 | 75.00 | 80.00 | 82.50 | 105.00 |
| NHPP R100-376 | | VARIOUS LOCATIONS IN REGION 1 | 03/30/23 | 19.00 | 155.00 | 140.27 | 60.00 |
| | WEIGHTED AVERAGE FOR THE FIRST QUARTER | | | ===== | ===== | ===== | ===== |
| | | | | 254.00 | 131.66 | 134.46 | 137.30 |
| | WEIGHTED AVERAGE FOR THE YEAR | | | ===== | ===== | ===== | ===== |
| | | | | 254.00 | 131.66 | 134.46 | 137.30 |
| ===== | 202-00821 | Rem Sign Panel | | Each | ===== | ===== | ===== |
| NHPP0701-250 | | I-70B: DDI TO 24 RD, MAIN ST | 01/12/23 | 2.00 | 60.00 | 108.95 | 87.90 |
| SHE067A-044 | | SH 67F M.P. 56.5-57.6 AND SH | 03/02/23 | 9.00 | 100.00 | 207.90 | 207.90 |
| STR194A-002 | | SH194A SUR. TREAT.& DRAI IMP | 03/09/23 | 26.00 | 71.00 | 116.50 | 83.00 |
| | WEIGHTED AVERAGE FOR THE FIRST QUARTER | | | ===== | ===== | ===== | ===== |
| | | | | 37.00 | 77.46 | 128.69 | 113.65 |
| | WEIGHTED AVERAGE FOR THE YEAR | | | ===== | ===== | ===== | ===== |
| | | | | 37.00 | 77.46 | 128.69 | 113.65 |
| ===== | 202-00827 | Rem of Pull Box | | Each | ===== | ===== | ===== |
| C 1601-086 | | MAPLE & CHESTNUT SIGNALS AT I | 02/16/23 | 8.00 | 200.00 | 170.00 | 170.00 |
| STM C440-013 | | R3 EAGLE RESIDENCY ADA RAMP I | 02/16/23 | 1.00 | 1100.00 | 250.00 | 250.00 |
| C0881-036 | | R1 CURB RAMPS-SH88B & US285D | 02/16/23 | 51.00 | 750.00 | 482.50 | 100.00 |
| | WEIGHTED AVERAGE FOR THE FIRST QUARTER | | | ===== | ===== | ===== | ===== |
| | | | | 60.00 | 682.50 | 469.67 | 111.83 |
| | WEIGHTED AVERAGE FOR THE YEAR | | | ===== | ===== | ===== | ===== |
| | | | | 60.00 | 682.50 | 469.67 | 111.83 |
| ===== | 202-00828 | Rem Traf Sig Equipment | | LUMP SUM | ===== | ===== | ===== |
| STA066A-008 | | SH 66 @ WCR 7 | 01/26/23 | 1.00 | 24000.00 | 26341.47 | 26750.00 |
| C 1601-086 | | MAPLE & CHESTNUT SIGNALS AT I | 02/16/23 | 1.00 | 15000.00 | 35100.00 | 35100.00 |
| NHPP0701-256 | | I-70B/31.5 RD MESA COUNTY | 02/16/23 | 1.00 | 8500.00 | 12500.00 | 15000.00 |
| | WEIGHTED AVERAGE FOR THE FIRST QUARTER | | | ===== | ===== | ===== | ===== |
| | | | | 3.00 | 15625.00 | 25211.93 | 27987.50 |
| | WEIGHTED AVERAGE FOR THE YEAR | | | ===== | ===== | ===== | ===== |
| | | | | 3.00 | 15625.00 | 25211.93 | 27987.50 |
| ===== | 202-00858 | Rem Pedestal Pole | | Each | ===== | ===== | ===== |
| C0881-036 | | R1 CURB RAMPS-SH88B & US285D | 02/16/23 | 4.00 | 1000.00 | 683.75 | 200.00 |
| | WEIGHTED AVERAGE FOR THE FIRST QUARTER | | | ===== | ===== | ===== | ===== |
| | | | | 4.00 | 1000.00 | 683.75 | 200.00 |
| | WEIGHTED AVERAGE FOR THE YEAR | | | ===== | ===== | ===== | ===== |
| | | | | 4.00 | 1000.00 | 683.75 | 200.00 |

| PROJECT NUMBER | ITEM NUMBER/ PROJECT LOCATION | ITEM DESCRIPTION/ PROJECT LOCATION | DATE LET | UNIT/ QUANTITY | ENGR. EST. | AVERAGE BID | AWARDED BID |
|----------------|----------------------------------|---------------------------------------|----------|-------------------|------------|-------------|-------------|
| ===== | 202-00860 | Rem Ped Push Button | | Each | ===== | ===== | ===== |
| C0881-036 | | R1 CURB RAMPS-SH88B & US285D | 02/16/23 | 45.00 | 350.00 | 249.25 | 42.00 |
| | WEIGHTED | AVERAGE FOR THE FIRST QUARTER | | 45.00 | 350.00 | 249.25 | 42.00 |
| | | WEIGHTED AVERAGE FOR THE YEAR | | 45.00 | 350.00 | 249.25 | 42.00 |
| ===== | 202-00895 | Rem of Impact Attenuator | | Each | ===== | ===== | ===== |
| NHPP0701-250 | | I-70B: DDI TO 24 RD, MAIN ST | 01/12/23 | 1.00 | 4000.00 | 3350.00 | 2700.00 |
| | WEIGHTED | AVERAGE FOR THE FIRST QUARTER | | 1.00 | 4000.00 | 3350.00 | 2700.00 |
| | | WEIGHTED AVERAGE FOR THE YEAR | | 1.00 | 4000.00 | 3350.00 | 2700.00 |
| ===== | 202-01000 | Rem Fence | | Lin Foot | ===== | ===== | ===== |
| STA172A-022 | | SH 172 IGNACIO TO ELMORE'S CO | 01/12/23 | 343.00 | 10.00 | 3.04 | 1.97 |
| C1601-084 | | US 160 SECTION3 PRIORITY CULV | 02/16/23 | 185.00 | 10.00 | 10.57 | 4.00 |
| | WEIGHTED | AVERAGE FOR THE FIRST QUARTER | | 528.00 | 10.00 | 5.67 | 2.68 |
| | | WEIGHTED AVERAGE FOR THE YEAR | | 528.00 | 10.00 | 5.67 | 2.68 |
| ===== | 202-01030 | Rem of Road Closure Gate | | Each | ===== | ===== | ===== |
| STA1381-011 | | SH 138 STERLING NORTH PART 2 | 02/16/23 | 1.00 | 10000.00 | 5000.00 | 5000.00 |
| | WEIGHTED | AVERAGE FOR THE FIRST QUARTER | | 1.00 | 10000.00 | 5000.00 | 5000.00 |
| | | WEIGHTED AVERAGE FOR THE YEAR | | 1.00 | 10000.00 | 5000.00 | 5000.00 |
| ===== | 202-01130 | Rem Gdrail Ty 3 | | Lin Foot | ===== | ===== | ===== |
| STA172A-022 | | SH 172 IGNACIO TO ELMORE'S CO | 01/12/23 | 5,275.00 | 4.00 | 4.77 | 4.84 |
| NHPP0701-250 | | I-70B: DDI TO 24 RD, MAIN ST | 01/12/23 | 1,921.00 | 10.00 | 9.25 | 8.50 |
| SFTYR200-277 | | REGION 2 WIDE, VARIOUS HWY & | 01/19/23 | 545.00 | 30.00 | 9.25 | 8.00 |
| C0703-498 | | EISENHOWER JOHNSON MEMORIAL T | 02/16/23 | 5,028.00 | 6.00 | 6.15 | 6.00 |
| STA1381-011 | | SH 138 STERLING NORTH PART 2 | 02/16/23 | 1,861.00 | 5.00 | 4.40 | 4.40 |

COLORADO DEPARTMENT OF TRANSPORTATION
ITEM UNIT COSTS BY PROJECTS -- 2023 COST DATA

12:26 Wednesday, May 17, 2023 12

| PROJECT NUMBER | ITEM NUMBER/ PROJECT LOCATION | ITEM DESCRIPTION/ PROJECT LOCATION | DATE LET | UNIT/ QUANTITY | ENGR. EST. | AVERAGE BID | AWARDED BID |
|----------------|--|---------------------------------------|----------|-------------------|------------|-------------|-------------|
| ===== | 202-01130 | Rem Gdrail Ty 3 | | Lin Foot | ===== | ===== | ===== |
| SHE067A-044 | | SH 67F M.P. 56.5-57.6 AND SH | 03/02/23 | 850.00 | 4.00 | 12.95 | 12.95 |
| STR194A-002 | | SH194A SUR. TREAT.& DRAI IMP | 03/09/23 | 1,315.00 | 6.40 | 9.50 | 5.00 |
| STA257A-008 | | SH 257 WINDSOR RESURFACING | 03/30/23 | 641.00 | 8.00 | 11.38 | 10.50 |
| NHPP R100-376 | | VARIOUS LOCATIONS IN REGION 1 | 03/30/23 | 3,914.00 | 5.37 | 6.15 | 7.00 |
| | WEIGHTED AVERAGE FOR THE FIRST QUARTER | | | 21,350.00 | 6.28 | 6.57 | 6.38 |
| | WEIGHTED AVERAGE FOR THE YEAR | | | 21,350.00 | 6.28 | 6.57 | 6.38 |
| ===== | 202-01140 | Rem Gdrail Ty 4 | | Lin Foot | ===== | ===== | ===== |
| NHPP0701-250 | | I-70B: DDI TO 24 RD, MAIN ST | 01/12/23 | 600.00 | 15.00 | 21.68 | 31.10 |
| | WEIGHTED AVERAGE FOR THE FIRST QUARTER | | | 600.00 | 15.00 | 21.68 | 31.10 |
| | WEIGHTED AVERAGE FOR THE YEAR | | | 600.00 | 15.00 | 21.68 | 31.10 |
| ===== | 202-01170 | Rem Gdrail Ty 7 | | Lin Foot | ===== | ===== | ===== |
| C0703-498 | | EISENHOWER JOHNSON MEMORIAL T | 02/16/23 | 2,278.00 | 20.00 | 35.16 | 44.00 |
| | WEIGHTED AVERAGE FOR THE FIRST QUARTER | | | 2,278.00 | 20.00 | 35.16 | 44.00 |
| | WEIGHTED AVERAGE FOR THE YEAR | | | 2,278.00 | 20.00 | 35.16 | 44.00 |
| ===== | 202-01300 | Rem End Anchorage | | Each | ===== | ===== | ===== |
| STA172A-022 | | SH 172 IGNACIO TO ELMORE'S CO | 01/12/23 | 28.00 | 300.00 | 475.92 | 483.83 |
| NHPP0701-250 | | I-70B: DDI TO 24 RD, MAIN ST | 01/12/23 | 12.00 | 600.00 | 738.50 | 677.00 |
| SFTYR200-277 | | REGION 2 WIDE, VARIOUS HWY & | 01/19/23 | 94.00 | 350.00 | 562.50 | 600.00 |
| SHE067A-044 | | SH 67F M.P. 56.5-57.6 AND SH | 03/02/23 | 2.00 | 500.00 | 104.54 | 104.54 |
| STR194A-002 | | SH194A SUR. TREAT.& DRAI IMP | 03/09/23 | 14.00 | 370.00 | 640.00 | 780.00 |
| STA257A-008 | | SH 257 WINDSOR RESURFACING | 03/30/23 | 6.00 | 350.00 | 517.50 | 475.00 |
| NHPP R100-376 | | VARIOUS LOCATIONS IN REGION 1 | 03/30/23 | 4.00 | 505.00 | 489.63 | 450.00 |
| | WEIGHTED AVERAGE FOR THE FIRST QUARTER | | | 160.00 | 367.50 | 560.95 | 586.56 |
| | WEIGHTED AVERAGE FOR THE YEAR | | | 160.00 | 367.50 | 560.95 | 586.56 |
| ===== | 202-04001 | Plug Culvert | | Each | ===== | ===== | ===== |
| NHPP0253-296 | | I-25 @ LCR 16 (MP 253.8-254.5 | 02/07/23 | 1.00 | 2395.73 | 2563.43 | 2563.43 |
| | WEIGHTED AVERAGE FOR THE FIRST QUARTER | | | 1.00 | 2395.73 | 2563.43 | 2563.43 |
| | WEIGHTED AVERAGE FOR THE YEAR | | | 1.00 | 2395.73 | 2563.43 | 2563.43 |

| PROJECT NUMBER | ITEM NUMBER/ PROJECT LOCATION | ITEM DESCRIPTION/ PROJECT LOCATION | DATE LET | UNIT/ QUANTITY | ENGR. EST. | AVERAGE BID | AWARDED BID |
|-----------------|--|---------------------------------------|----------|-------------------|------------|-------------|-------------|
| ===== 202-04002 | | Clean Culvert | | Each | ===== | | |
| STA172A-022 | | SH 172 IGNACIO TO ELMORE'S CO | 01/12/23 | 2.00 | 500.00 | 4870.05 | 3190.10 |
| C0703-498 | | EISENHOWER JOHNSON MEMORIAL T | 02/16/23 | 17.00 | 4000.00 | 2136.91 | 1400.00 |
| C1601-084 | | US 160 SECTION3 PRIORITY CULV | 02/16/23 | 7.00 | 4000.00 | 7435.50 | 4300.00 |
| NHPP0701-256 | | I-70B/31.5 RD MESA COUNTY | 02/16/23 | 1.00 | 5000.00 | 5450.00 | 4400.00 |
| NHPP R100-376 | | VARIOUS LOCATIONS IN REGION 1 | 03/30/23 | 2.00 | 2429.43 | 3661.41 | 4000.00 |
| | WEIGHTED AVERAGE FOR THE FIRST QUARTER | | | 29.00 | 3684.79 | 3441.40 | 2506.21 |
| | WEIGHTED AVERAGE FOR THE YEAR | | | 29.00 | 3684.79 | 3441.40 | 2506.21 |
| ===== 202-04005 | | Clean Valve Box | | Each | ===== | | |
| C0881-036 | | R1 CURB RAMPS-SH88B & US285D | 02/16/23 | 7.00 | 175.00 | 342.50 | 200.00 |
| | WEIGHTED AVERAGE FOR THE FIRST QUARTER | | | 7.00 | 175.00 | 342.50 | 200.00 |
| | WEIGHTED AVERAGE FOR THE YEAR | | | 7.00 | 175.00 | 342.50 | 200.00 |
| ===== 202-04007 | | Plug Culvert | | Cubic Yard | ===== | | |
| STA172A-022 | | SH 172 IGNACIO TO ELMORE'S CO | 01/12/23 | 140.00 | 400.00 | 303.43 | 274.85 |
| C1601-084 | | US 160 SECTION3 PRIORITY CULV | 02/16/23 | 51.00 | 60.00 | 538.01 | 550.00 |
| | WEIGHTED AVERAGE FOR THE FIRST QUARTER | | | 191.00 | 309.21 | 366.06 | 348.32 |
| | WEIGHTED AVERAGE FOR THE YEAR | | | 191.00 | 309.21 | 366.06 | 348.32 |
| ===== 202-04010 | | Clean Inlet | | Each | ===== | | |
| STA172A-022 | | SH 172 IGNACIO TO ELMORE'S CO | 01/12/23 | 12.00 | 300.00 | 1045.02 | 1276.04 |
| NHPPR100-383 | | I70 OVER WASHINGTON ST | 01/26/23 | 10.00 | 1350.00 | 1126.16 | 1500.00 |
| C0881-036 | | R1 CURB RAMPS-SH88B & US285D | 02/16/23 | 4.00 | 350.00 | 783.75 | 200.00 |
| NHPP0253-290 | | I25 @ 58TH AND 62ND | 03/02/23 | 4.00 | 700.00 | 1168.53 | 1055.00 |
| | WEIGHTED AVERAGE FOR THE FIRST QUARTER | | | 30.00 | 710.00 | 1041.80 | 1177.75 |
| | WEIGHTED AVERAGE FOR THE YEAR | | | 30.00 | 710.00 | 1041.80 | 1177.75 |
| ===== 202-04050 | | Clean Exp Joint | | Lin Foot | ===== | | |
| NHPPR100-383 | | I70 OVER WASHINGTON ST | 01/26/23 | 89.00 | 20.00 | 107.70 | 70.00 |
| | WEIGHTED AVERAGE FOR THE FIRST QUARTER | | | 89.00 | 20.00 | 107.70 | 70.00 |
| | WEIGHTED AVERAGE FOR THE YEAR | | | 89.00 | 20.00 | 107.70 | 70.00 |

| PROJECT NUMBER | ITEM NUMBER/ PROJECT LOCATION | ITEM DESCRIPTION/ PROJECT LOCATION | DATE LET | UNIT/ QUANTITY | ENGR. EST. | AVERAGE BID | AWARDED BID |
|--|----------------------------------|---|--|--|--|---|---|
| ===== | 202-05100 | Sandblasting Reinf Steel | | Sq Yard | ===== | ===== | ===== |
| C0703-498 | | EISENHOWER JOHNSON MEMORIAL T | 02/16/23 | 30.00 | 40.00 | 249.62 | 78.00 |
| | WEIGHTED | AVERAGE FOR THE FIRST QUARTER | | 30.00 | 40.00 | 249.62 | 78.00 |
| | | WEIGHTED AVERAGE FOR THE YEAR | | 30.00 | 40.00 | 249.62 | 78.00 |
| ===== | 202-06520 | Rem of Existing Wall Panels | | LUMP SUM | ===== | ===== | ===== |
| NHPP R100-376 | | VARIOUS LOCATIONS IN REGION 1 | 03/30/23 | 1.00 | 20000.00 | 31450.00 | 12900.00 |
| | WEIGHTED | AVERAGE FOR THE FIRST QUARTER | | 1.00 | 20000.00 | 31450.00 | 12900.00 |
| | | WEIGHTED AVERAGE FOR THE YEAR | | 1.00 | 20000.00 | 31450.00 | 12900.00 |
| ===== | 203-00000 | Uncl Excav | | Cubic Yard | ===== | ===== | ===== |
| NHPP0701-250 C133A-052 | | I-70B: DDI TO 24 RD, MAIN ST SH 133 ROCKFALL N OF MCCLURE | 01/12/23 02/16/23 | 910.00 24,128.00 | 40.00 20.00 | 38.30 44.23 | 40.60 26.00 |
| | WEIGHTED | AVERAGE FOR THE FIRST QUARTER | | 25,038.00 | 20.73 | 44.12 | 26.53 |
| | | WEIGHTED AVERAGE FOR THE YEAR | | 25,038.00 | 20.73 | 44.12 | 26.53 |
| ===== | 203-00010 | Uncl Excav (CIP) | | Cubic Yard | ===== | ===== | ===== |
| STA172A-022 FSA0853-123 STA066A-008 C0703-498 NHPP0701-256 SHE067A-044 STA257A-008 | | SH 172 IGNACIO TO ELMORE'S CO US 85 AND WCR 66 LEFT TURN AC SH 66 @ WCR 7 EISENHOWER JOHNSON MEMORIAL T I-70B/31.5 RD MESA COUNTY SH 67F M.P. 56.5-57.6 AND SH SH 257 WINDSOR RESURFACING | 01/12/23 01/26/23 01/26/23 02/16/23 02/16/23 03/02/23 03/30/23 | 726.00 3,855.00 192.00 538.00 289.00 277.00 9,321.00 | 40.00 20.00 100.00 40.00 60.00 50.00 40.00 | 96.83 24.50 79.86 73.54 53.00 17.79 17.38 | 102.65 20.50 95.00 130.00 25.00 17.79 20.75 |
| | WEIGHTED | AVERAGE FOR THE FIRST QUARTER | | 15,198.00 | 36.25 | 27.05 | 29.43 |
| | | WEIGHTED AVERAGE FOR THE YEAR | | 15,198.00 | 36.25 | 27.05 | 29.43 |
| ===== | 203-00050 | Unsuitable Material | | Cubic Yard | ===== | ===== | ===== |
| STR2871-040 | | US 287 MP 0.0 TO MP 122 VARIO | 01/12/23 | 138.00 | 50.00 | 132.40 | 154.47 |

COLORADO DEPARTMENT OF TRANSPORTATION
ITEM UNIT COSTS BY PROJECTS -- 2023 COST DATA

12:26 Wednesday, May 17, 2023 15

| PROJECT NUMBER | ITEM NUMBER/ PROJECT LOCATION | ITEM DESCRIPTION/ PROJECT LOCATION | DATE LET | UNIT/ QUANTITY | ENGR. EST. | AVERAGE BID | AWARDED BID |
|----------------|----------------------------------|--|----------|-------------------|------------|-------------|-------------|
| ===== | 203-00050 | Unsuitable Material | | Cubic Yard | ===== | ===== | ===== |
| C0881-036 | | R1 CURB RAMPS-SH88B & US285D | 02/16/23 | 500.00 | 170.00 | 66.50 | 45.00 |
| NHPP0253-290 | | I25 @ 58TH AND 62ND | 03/02/23 | 50.00 | 100.00 | 162.18 | 165.00 |
| | | WEIGHTED AVERAGE FOR THE FIRST QUARTER | | 688.00 | 140.84 | 87.56 | 75.68 |
| | | WEIGHTED AVERAGE FOR THE YEAR | | 688.00 | 140.84 | 87.56 | 75.68 |
| ===== | 203-00060 | Emb Matl (CIP) | | Cubic Yard | ===== | ===== | ===== |
| STA172A-022 | | SH 172 IGNACIO TO ELMORE'S CO | 01/12/23 | 246.00 | 50.00 | 99.10 | 98.60 |
| NHPP0253-296 | | I-25 @ LCR 16 (MP 253.8-254.5 | 02/07/23 | 7,114.00 | 14.83 | 15.87 | 15.87 |
| STA1381-011 | | SH 138 STERLING NORTH PART 2 | 02/16/23 | 9,582.00 | 40.00 | 37.00 | 37.00 |
| C1601-084 | | US 160 SECTION3 PRIORITY CULV | 02/16/23 | 205.00 | 100.00 | 112.97 | 63.00 |
| SHE067A-044 | | SH 67F M.P. 56.5-57.6 AND SH | 03/02/23 | 740.00 | 50.00 | 26.19 | 26.19 |
| STR194A-002 | | SH194A SUR. TREAT.& DRAI IMP | 03/09/23 | 3.00 | 40.00 | 500.00 | 500.00 |
| NHPP R100-376 | | VARIOUS LOCATIONS IN REGION 1 | 03/30/23 | 27.00 | 61.00 | 456.18 | 320.00 |
| | | WEIGHTED AVERAGE FOR THE FIRST QUARTER | | 17,917.00 | 31.27 | 33.13 | 29.81 |
| | | WEIGHTED AVERAGE FOR THE YEAR | | 17,917.00 | 31.27 | 33.13 | 29.81 |
| ===== | 203-00066 | Emb Matl (CIP) (R40) | | Cubic Yard | ===== | ===== | ===== |
| FSA0853-123 | | US 85 AND WCR 66 LEFT TURN AC | 01/26/23 | 2,809.00 | 30.00 | 41.25 | 42.00 |
| STA066A-008 | | SH 66 @ WCR 7 | 01/26/23 | 201.00 | 75.00 | 104.45 | 102.00 |
| | | WEIGHTED AVERAGE FOR THE FIRST QUARTER | | 3,010.00 | 33.00 | 44.81 | 46.01 |
| | | WEIGHTED AVERAGE FOR THE YEAR | | 3,010.00 | 33.00 | 44.81 | 46.01 |
| ===== | 203-00100 | Muck Excav | | Cubic Yard | ===== | ===== | ===== |
| C1601-084 | | US 160 SECTION3 PRIORITY CULV | 02/16/23 | 15.00 | 100.00 | 269.37 | 170.00 |
| STR194A-002 | | SH194A SUR. TREAT.& DRAI IMP | 03/09/23 | 1,275.00 | 50.00 | 45.50 | 47.00 |
| | | WEIGHTED AVERAGE FOR THE FIRST QUARTER | | 1,290.00 | 50.58 | 48.10 | 48.43 |
| | | WEIGHTED AVERAGE FOR THE YEAR | | 1,290.00 | 50.58 | 48.10 | 48.43 |
| ===== | 203-00400 | Rock Excav | | Cubic Yard | ===== | ===== | ===== |
| C133A-052 | | SH 133 ROCKFALL N OF MCCLURE | 02/16/23 | 100.00 | 300.00 | 147.63 | 110.00 |

| PROJECT NUMBER | ITEM NUMBER/ PROJECT LOCATION | ITEM DESCRIPTION/ PROJECT LOCATION | DATE LET | UNIT/ QUANTITY | ENGR. EST. | AVERAGE BID | AWARDED BID |
|-----------------|--|---------------------------------------|----------|-------------------|------------|-------------|-------------|
| ===== 203-00400 | | Rock Excav | | Cubic Yard | | | |
| C1601-084 | | US 160 SECTION3 PRIORITY CULV | 02/16/23 | 5.00 | 300.00 | 414.34 | 370.00 |
| SHE067A-044 | | SH 67F M.P. 56.5-57.6 AND SH | 03/02/23 | 6,346.00 | 90.00 | 45.99 | 45.99 |
| | WEIGHTED AVERAGE FOR THE FIRST QUARTER | | | 6,451.00 | 93.42 | 52.55 | 47.23 |
| | WEIGHTED AVERAGE FOR THE YEAR | | | 6,451.00 | 93.42 | 52.55 | 47.23 |
| ===== 203-01100 | | Proof Rolling | | Hour | | | |
| NHPP0253-296 | | I-25 @ LCR 16 (MP 253.8-254.5 | 02/07/23 | 10.00 | 131.45 | 140.65 | 140.65 |
| STA1381-011 | | SH 138 STERLING NORTH PART 2 | 02/16/23 | 50.00 | 100.00 | 140.00 | 140.00 |
| SHE067A-044 | | SH 67F M.P. 56.5-57.6 AND SH | 03/02/23 | 20.00 | 150.00 | 134.40 | 134.40 |
| STA257A-008 | | SH 257 WINDSOR RESURFACING | 03/30/23 | 20.00 | 120.00 | 116.00 | 140.00 |
| | WEIGHTED AVERAGE FOR THE FIRST QUARTER | | | 100.00 | 117.15 | 131.12 | 138.95 |
| | WEIGHTED AVERAGE FOR THE YEAR | | | 100.00 | 117.15 | 131.12 | 138.95 |
| ===== 203-01500 | | Blading | | Hour | | | |
| NHPP0701-250 | | I-70B: DDI TO 24 RD, MAIN ST | 01/12/23 | 20.00 | 300.00 | 140.00 | 160.00 |
| STA066A-008 | | SH 66 @ WCR 7 | 01/26/23 | 20.00 | 160.00 | 251.82 | 180.00 |
| STA1381-011 | | SH 138 STERLING NORTH PART 2 | 02/16/23 | 200.00 | 150.00 | 155.00 | 155.00 |
| C133A-052 | | SH 133 ROCKFALL N OF MCCLURE | 02/16/23 | 40.00 | 170.00 | 171.06 | 145.00 |
| NHPP0701-256 | | I-70B/31.5 RD MESA COUNTY | 02/16/23 | 30.00 | 150.00 | 70.00 | 120.00 |
| STR194A-002 | | SH194A SUR. TREAT.& DRAI IMP | 03/09/23 | 80.00 | 150.00 | 137.50 | 135.00 |
| STA257A-008 | | SH 257 WINDSOR RESURFACING | 03/30/23 | 10.00 | 150.00 | 165.00 | 150.00 |
| NHPP R100-376 | | VARIOUS LOCATIONS IN REGION 1 | 03/30/23 | 18.00 | 233.16 | 305.95 | 360.00 |
| | WEIGHTED AVERAGE FOR THE FIRST QUARTER | | | 418.00 | 163.15 | 167.10 | 157.85 |
| | WEIGHTED AVERAGE FOR THE YEAR | | | 418.00 | 163.15 | 167.10 | 157.85 |
| ===== 203-01510 | | Backhoe | | Hour | | | |
| NHPP0701-250 | | I-70B: DDI TO 24 RD, MAIN ST | 01/12/23 | 10.00 | 400.00 | 122.50 | 125.00 |
| STA066A-008 | | SH 66 @ WCR 7 | 01/26/23 | 20.00 | 150.00 | 221.49 | 155.00 |
| NHPP R100-376 | | VARIOUS LOCATIONS IN REGION 1 | 03/30/23 | 6.00 | 123.01 | 170.12 | 225.00 |
| | WEIGHTED AVERAGE FOR THE FIRST QUARTER | | | 36.00 | 214.95 | 201.82 | 158.33 |
| | WEIGHTED AVERAGE FOR THE YEAR | | | 36.00 | 214.95 | 201.82 | 158.33 |

COLORADO DEPARTMENT OF TRANSPORTATION
ITEM UNIT COSTS BY PROJECTS -- 2023 COST DATA

12:26 Wednesday, May 17, 2023 17

| PROJECT NUMBER | ITEM NUMBER/ PROJECT LOCATION | ITEM DESCRIPTION/ PROJECT LOCATION | DATE LET | UNIT/ QUANTITY | ENGR. EST. | AVERAGE BID | AWARDED BID |
|-----------------|--|---------------------------------------|----------|-------------------|------------|-------------|-------------|
| ===== 203-01582 | | Truck (Dump) | | Hour | ===== | | |
| NHPP0701-250 | | I-70B: DDI TO 24 RD, MAIN ST | 01/12/23 | 10.00 | 200.00 | 155.00 | 160.00 |
| C133A-052 | | SH 133 ROCKFALL N OF MCCLURE | 02/16/23 | 100.00 | 150.00 | 156.44 | 160.00 |
| | WEIGHTED AVERAGE FOR THE FIRST QUARTER | | | 110.00 | 154.55 | 156.37 | 160.00 |
| | WEIGHTED AVERAGE FOR THE YEAR | | | 110.00 | 154.55 | 156.37 | 160.00 |
| ===== 203-01590 | | Front End Loader (Rubber) | | Hour | ===== | | |
| C133A-052 | | SH 133 ROCKFALL N OF MCCLURE | 02/16/23 | 50.00 | 175.00 | 165.31 | 155.00 |
| C0881-036 | | R1 CURB RAMPS-SH88B & US285D | 02/16/23 | 20.00 | 150.00 | 148.75 | 20.00 |
| | WEIGHTED AVERAGE FOR THE FIRST QUARTER | | | 70.00 | 167.86 | 160.58 | 116.43 |
| | WEIGHTED AVERAGE FOR THE YEAR | | | 70.00 | 167.86 | 160.58 | 116.43 |
| ===== 203-01594 | | Combination Loader | | Hour | ===== | | |
| STA172A-022 | | SH 172 IGNACIO TO ELMORE'S CO | 01/12/23 | 20.00 | 150.00 | 154.61 | 159.21 |
| C0703-498 | | EISENHOWER JOHNSON MEMORIAL T | 02/16/23 | 8.00 | 150.00 | 143.33 | 130.00 |
| STA1381-011 | | SH 138 STERLING NORTH PART 2 | 02/16/23 | 80.00 | 160.00 | 165.00 | 165.00 |
| C1601-084 | | US 160 SECTION3 PRIORITY CULV | 02/16/23 | 20.00 | 150.00 | 143.94 | 150.00 |
| SHE067A-044 | | SH 67F M.P. 56.5-57.6 AND SH | 03/02/23 | 60.00 | 250.00 | 105.56 | 105.56 |
| | WEIGHTED AVERAGE FOR THE FIRST QUARTER | | | 188.00 | 186.17 | 143.10 | 142.33 |
| | WEIGHTED AVERAGE FOR THE YEAR | | | 188.00 | 186.17 | 143.10 | 142.33 |
| ===== 203-01597 | | Potholing | | Hour | ===== | | |
| STA172A-022 | | SH 172 IGNACIO TO ELMORE'S CO | 01/12/23 | 60.00 | 400.00 | 437.68 | 425.35 |
| NHPP0701-250 | | I-70B: DDI TO 24 RD, MAIN ST | 01/12/23 | 25.00 | 500.00 | 325.00 | 450.00 |
| SFTYR200-277 | | REGION 2 WIDE, VARIOUS HWY & | 01/19/23 | 40.00 | 350.00 | 300.00 | 250.00 |
| STA066A-008 | | SH 66 @ WCR 7 | 01/26/23 | 70.00 | 300.00 | 364.37 | 320.00 |
| C0342-066 | | US 034A (MP 113-150) | 02/02/23 | 8.00 | 500.00 | 340.67 | 237.00 |
| NHPP0253-296 | | I-25 @ LCR 16 (MP 253.8-254.5 | 02/07/23 | 40.00 | 299.90 | 320.89 | 320.89 |
| STA1381-011 | | SH 138 STERLING NORTH PART 2 | 02/16/23 | 20.00 | 400.00 | 250.00 | 250.00 |
| C133A-052 | | SH 133 ROCKFALL N OF MCCLURE | 02/16/23 | 50.00 | 500.00 | 382.00 | 160.00 |
| C1601-084 | | US 160 SECTION3 PRIORITY CULV | 02/16/23 | 80.00 | 350.00 | 280.06 | 390.00 |
| C 1601-086 | | MAPLE & CHESTNUT SIGNALS AT I | 02/16/23 | 40.00 | 300.00 | 650.00 | 650.00 |

| PROJECT NUMBER | ITEM NUMBER/ PROJECT LOCATION | ITEM DESCRIPTION/ PROJECT LOCATION | DATE LET | UNIT/ QUANTITY | ENGR. EST. | AVERAGE BID | AWARDED BID |
|---|--|---------------------------------------|----------|-------------------|------------|-------------|-------------|
| ===== 203-01597 Potholing Hour ===== | | | | | | | |
| STM C440-013 | R3 EAGLE RESIDENCY ADA RAMP I | R3 EAGLE RESIDENCY ADA RAMP I | 02/16/23 | 15.00 | 500.00 | 50.00 | 50.00 |
| NHPP0701-256 | I-70B/31.5 RD MESA COUNTY | I-70B/31.5 RD MESA COUNTY | 02/16/23 | 10.00 | 450.00 | 245.00 | 290.00 |
| C0881-036 | R1 CURB RAMPS-SH88B & US285D | R1 CURB RAMPS-SH88B & US285D | 02/16/23 | 100.00 | 225.00 | 283.75 | 20.00 |
| SHE067A-044 | SH 67F M.P. 56.5-57.6 AND SH | SH 67F M.P. 56.5-57.6 AND SH | 03/02/23 | 20.00 | 250.00 | 433.62 | 433.62 |
| STA257A-008 | SH 257 WINDSOR RESURFACING | SH 257 WINDSOR RESURFACING | 03/30/23 | 15.00 | 250.00 | 327.73 | 250.00 |
| NHPP R100-376 | VARIOUS LOCATIONS IN REGION 1 | VARIOUS LOCATIONS IN REGION 1 | 03/30/23 | 10.00 | 314.00 | 435.07 | 600.00 |
| | WEIGHTED AVERAGE FOR THE FIRST QUARTER | | | 603.00 | 343.09 | 339.76 | 295.48 |
| | WEIGHTED AVERAGE FOR THE YEAR | | | 603.00 | 343.09 | 339.76 | 295.48 |
| ===== 203-02300 Rock Scaler Hour ===== | | | | | | | |
| C133A-052 | SH 133 ROCKFALL N OF MCCLURE | SH 133 ROCKFALL N OF MCCLURE | 02/16/23 | 120.00 | 180.00 | 450.87 | 300.00 |
| | WEIGHTED AVERAGE FOR THE FIRST QUARTER | | | 120.00 | 180.00 | 450.87 | 300.00 |
| | WEIGHTED AVERAGE FOR THE YEAR | | | 120.00 | 180.00 | 450.87 | 300.00 |
| ===== 203-02315 Mechanized Scaling Hour ===== | | | | | | | |
| C133A-052 | SH 133 ROCKFALL N OF MCCLURE | SH 133 ROCKFALL N OF MCCLURE | 02/16/23 | 40.00 | 500.00 | 555.04 | 520.00 |
| | WEIGHTED AVERAGE FOR THE FIRST QUARTER | | | 40.00 | 500.00 | 555.04 | 520.00 |
| | WEIGHTED AVERAGE FOR THE YEAR | | | 40.00 | 500.00 | 555.04 | 520.00 |
| ===== 203-02330 Laborer Hour ===== | | | | | | | |
| STA172A-022 | SH 172 IGNACIO TO ELMORE'S CO | SH 172 IGNACIO TO ELMORE'S CO | 01/12/23 | 40.00 | 75.00 | 59.26 | 63.51 |
| SFTYR200-277 | REGION 2 WIDE, VARIOUS HWY & | REGION 2 WIDE, VARIOUS HWY & | 01/19/23 | 20.00 | 30.00 | 65.00 | 55.00 |
| C1601-084 | US 160 SECTION3 PRIORITY CULV | US 160 SECTION3 PRIORITY CULV | 02/16/23 | 20.00 | 80.00 | 67.22 | 75.00 |
| STM C440-013 | R3 EAGLE RESIDENCY ADA RAMP I | R3 EAGLE RESIDENCY ADA RAMP I | 02/16/23 | 20.00 | 50.00 | 20.00 | 20.00 |
| STRR300-265 | MOUNTAIN RE FY23 CRACK SEALS | MOUNTAIN RE FY23 CRACK SEALS | 03/02/23 | 40.00 | 70.00 | 50.00 | 50.00 |
| | WEIGHTED AVERAGE FOR THE FIRST QUARTER | | | 140.00 | 64.29 | 56.50 | 53.86 |
| | WEIGHTED AVERAGE FOR THE YEAR | | | 140.00 | 64.29 | 56.50 | 53.86 |
| ===== 206-00000 Str Excav Cubic Yard ===== | | | | | | | |
| STA172A-022 | SH 172 IGNACIO TO ELMORE'S CO | SH 172 IGNACIO TO ELMORE'S CO | 01/12/23 | 642.00 | 50.00 | 88.80 | 96.20 |

COLORADO DEPARTMENT OF TRANSPORTATION
ITEM UNIT COSTS BY PROJECTS -- 2023 COST DATA

12:26 Wednesday, May 17, 2023 19

| PROJECT NUMBER | ITEM NUMBER/ PROJECT LOCATION | ITEM DESCRIPTION/ PROJECT LOCATION | DATE LET | UNIT/ QUANTITY | ENGR. EST. | AVERAGE BID | AWARDED BID |
|---|--|---------------------------------------|----------|-------------------|------------|-------------|-------------|
| ===== 206-00000 Str Excav Cubic Yard ===== | | | | | | | |
| FSA0853-123 | | US 85 AND WCR 66 LEFT TURN AC | 01/26/23 | 48.00 | 70.00 | 36.83 | 38.00 |
| NHPP0253-296 | | I-25 @ LCR 16 (MP 253.8-254.5 | 02/07/23 | 16.00 | 65.37 | 69.95 | 69.95 |
| STA1381-011 | | SH 138 STERLING NORTH PART 2 | 02/16/23 | 24.00 | 150.00 | 170.00 | 170.00 |
| C1601-084 | | US 160 SECTION3 PRIORITY CULV | 02/16/23 | 343.00 | 100.00 | 127.72 | 61.00 |
| SHE067A-044 | | SH 67F M.P. 56.5-57.6 AND SH | 03/02/23 | 7.00 | 100.00 | 21.77 | 21.77 |
| NHPP R100-376 | | VARIOUS LOCATIONS IN REGION 1 | 03/30/23 | 40.00 | 70.00 | 431.42 | 310.00 |
| | WEIGHTED AVERAGE FOR THE FIRST QUARTER | | | 1,120.00 | 69.56 | 105.70 | 91.30 |
| | WEIGHTED AVERAGE FOR THE YEAR | | | 1,120.00 | 69.56 | 105.70 | 91.30 |
| ===== 206-00065 Str Bkfl (Flow-Fill) Cubic Yard ===== | | | | | | | |
| STA172A-022 | | SH 172 IGNACIO TO ELMORE'S CO | 01/12/23 | 87.00 | 275.00 | 266.21 | 284.41 |
| FSA0853-123 | | US 85 AND WCR 66 LEFT TURN AC | 01/26/23 | 7.00 | 260.00 | 398.33 | 290.00 |
| NHPP0253-290 | | I25 @ 58TH AND 62ND | 03/02/23 | 5.00 | 1000.00 | 2122.31 | 1780.00 |
| | WEIGHTED AVERAGE FOR THE FIRST QUARTER | | | 99.00 | 310.56 | 410.75 | 360.34 |
| | WEIGHTED AVERAGE FOR THE YEAR | | | 99.00 | 310.56 | 410.75 | 360.34 |
| ===== 206-00066 Str Bkfl (FF Ash) Cubic Yard ===== | | | | | | | |
| NHPP0253-290 | | I25 @ 58TH AND 62ND | 03/02/23 | 50.00 | 75.00 | 494.74 | 670.00 |
| | WEIGHTED AVERAGE FOR THE FIRST QUARTER | | | 50.00 | 75.00 | 494.74 | 670.00 |
| | WEIGHTED AVERAGE FOR THE YEAR | | | 50.00 | 75.00 | 494.74 | 670.00 |
| ===== 206-00100 Str Bkfl (CL 1) Cubic Yard ===== | | | | | | | |
| STA172A-022 | | SH 172 IGNACIO TO ELMORE'S CO | 01/12/23 | 56.00 | 150.00 | 223.90 | 272.79 |
| FSA0853-123 | | US 85 AND WCR 66 LEFT TURN AC | 01/26/23 | 21.00 | 90.00 | 97.67 | 75.00 |
| NHPPR100-383 | | I70 OVER WASHINGTON ST | 01/26/23 | 20.00 | 60.00 | 259.75 | 234.00 |
| C0703-498 | | EISENHOWER JOHNSON MEMORIAL T | 02/16/23 | 162.00 | 80.00 | 104.17 | 180.00 |
| C1601-084 | | US 160 SECTION3 PRIORITY CULV | 02/16/23 | 313.00 | 75.00 | 236.50 | 81.00 |
| NHPP0701-256 | | I-70B/31.5 RD MESA COUNTY | 02/16/23 | 3.00 | 300.00 | 500.00 | 750.00 |
| NHPP R100-376 | | VARIOUS LOCATIONS IN REGION 1 | 03/30/23 | 17.00 | 90.00 | 829.50 | 300.00 |
| | WEIGHTED AVERAGE FOR THE FIRST QUARTER | | | 592.00 | 85.06 | 195.06 | 140.87 |
| | WEIGHTED AVERAGE FOR THE YEAR | | | 592.00 | 85.06 | 195.06 | 140.87 |

COLORADO DEPARTMENT OF TRANSPORTATION
ITEM UNIT COSTS BY PROJECTS -- 2023 COST DATA

12:26 Wednesday, May 17, 2023 20

| PROJECT NUMBER | ITEM NUMBER/ PROJECT LOCATION | ITEM DESCRIPTION/ PROJECT LOCATION | DATE LET | UNIT/ QUANTITY | ENGR. EST. | AVERAGE BID | AWARDED BID |
|----------------|----------------------------------|--|----------|-------------------|------------|-------------|-------------|
| ===== | 206-00200 | Str Bkfl (CL 2) | | Cubic Yard | ===== | | |
| NHPP0253-296 | | I-25 @ LCR 16 (MP 253.8-254.5 | 02/07/23 | 241.00 | 75.67 | 80.97 | 80.97 |
| STA1381-011 | | SH 138 STERLING NORTH PART 2 | 02/16/23 | 11.00 | 300.00 | 260.00 | 260.00 |
| | | WEIGHTED AVERAGE FOR THE FIRST QUARTER | | ----- | ----- | ----- | ----- |
| | | | | 252.00 | 85.46 | 88.78 | 88.78 |
| | | WEIGHTED AVERAGE FOR THE YEAR | | ===== | ===== | ===== | ===== |
| | | | | 252.00 | 85.46 | 88.78 | 88.78 |
| ===== | 206-00510 | Filter Matl (CL A) | | Cubic Yard | ===== | | |
| STA172A-022 | | SH 172 IGNACIO TO ELMORE'S CO | 01/12/23 | 91.00 | 100.00 | 225.05 | 316.09 |
| | | WEIGHTED AVERAGE FOR THE FIRST QUARTER | | ----- | ----- | ----- | ----- |
| | | | | 91.00 | 100.00 | 225.05 | 316.09 |
| | | WEIGHTED AVERAGE FOR THE YEAR | | ===== | ===== | ===== | ===== |
| | | | | 91.00 | 100.00 | 225.05 | 316.09 |
| ===== | 206-01781 | Shoring (A 1) | | LUMP SUM | ===== | | |
| STA172A-022 | | SH 172 IGNACIO TO ELMORE'S CO | 01/12/23 | 1.00 | 15000.00 | 90707.47 | 67374.94 |
| C0703-498 | | EISENHOWER JOHNSON MEMORIAL T | 02/16/23 | 1.00 | 60000.00 | 80835.76 | 80000.00 |
| C1601-084 | | US 160 SECTION3 PRIORITY CULV | 02/16/23 | 1.00 | 15000.00 | 20661.88 | 6100.00 |
| | | WEIGHTED AVERAGE FOR THE FIRST QUARTER | | ----- | ----- | ----- | ----- |
| | | | | 3.00 | 30000.00 | 66463.71 | 51158.31 |
| | | WEIGHTED AVERAGE FOR THE YEAR | | ===== | ===== | ===== | ===== |
| | | | | 3.00 | 30000.00 | 66463.71 | 51158.31 |
| ===== | 206-01782 | Shoring (A 2) | | LUMP SUM | ===== | | |
| STA172A-022 | | SH 172 IGNACIO TO ELMORE'S CO | 01/12/23 | 1.00 | 10000.00 | 90707.47 | 67374.94 |
| C0703-498 | | EISENHOWER JOHNSON MEMORIAL T | 02/16/23 | 1.00 | 50000.00 | 53563.34 | 60000.00 |
| C1601-084 | | US 160 SECTION3 PRIORITY CULV | 02/16/23 | 1.00 | 10000.00 | 12351.36 | 6100.00 |
| | | WEIGHTED AVERAGE FOR THE FIRST QUARTER | | ----- | ----- | ----- | ----- |
| | | | | 3.00 | 23333.33 | 52401.10 | 44491.65 |
| | | WEIGHTED AVERAGE FOR THE YEAR | | ===== | ===== | ===== | ===== |
| | | | | 3.00 | 23333.33 | 52401.10 | 44491.65 |
| ===== | 206-01783 | Shoring (A 3) | | LUMP SUM | ===== | | |
| C1601-084 | | US 160 SECTION3 PRIORITY CULV | 02/16/23 | 1.00 | 10000.00 | 13201.36 | 7800.00 |
| | | WEIGHTED AVERAGE FOR THE FIRST QUARTER | | ----- | ----- | ----- | ----- |
| | | | | 1.00 | 10000.00 | 13201.36 | 7800.00 |
| | | WEIGHTED AVERAGE FOR THE YEAR | | ===== | ===== | ===== | ===== |
| | | | | 1.00 | 10000.00 | 13201.36 | 7800.00 |

| PROJECT NUMBER | ITEM NUMBER/ PROJECT LOCATION | ITEM DESCRIPTION/ PROJECT LOCATION | DATE LET | UNIT/ QUANTITY | ENGR. EST. | AVERAGE BID | AWARDED BID |
|-----------------|--|---------------------------------------|----------|-------------------|------------|-------------|-------------|
| ===== 207-00310 | | Stockpile Wetland Topsoil | | Cubic Yard | ===== | | |
| STA172A-022 | | SH 172 IGNACIO TO ELMORE'S CO | 01/12/23 | 153.00 | 25.00 | 53.80 | 17.59 |
| C1601-084 | | US 160 SECTION3 PRIORITY CULV | 02/16/23 | 72.00 | 30.00 | 72.19 | 21.00 |
| STR194A-002 | | SH194A SUR. TREAT.& DRAI IMP | 03/09/23 | 1,007.00 | 17.00 | 69.00 | 70.00 |
| | WEIGHTED AVERAGE FOR THE FIRST QUARTER | | | 1,232.00 | 18.75 | 67.30 | 60.63 |
| | WEIGHTED AVERAGE FOR THE YEAR | | | 1,232.00 | 18.75 | 67.30 | 60.63 |
| ===== 207-00700 | | Topsoil (Onsite) | | Cubic Yard | ===== | | |
| STA172A-022 | | SH 172 IGNACIO TO ELMORE'S CO | 01/12/23 | 720.00 | 30.00 | 58.11 | 13.22 |
| FSA0853-123 | | US 85 AND WCR 66 LEFT TURN AC | 01/26/23 | 546.00 | 16.00 | 28.00 | 28.00 |
| STA066A-008 | | SH 66 @ WCR 7 | 01/26/23 | 298.00 | 35.00 | 34.17 | 38.90 |
| C0342-066 | | US 034A (MP 113-150) | 02/02/23 | 81.00 | 35.00 | 88.67 | 76.00 |
| C0703-498 | | EISENHOWER JOHNSON MEMORIAL T | 02/16/23 | 208.00 | 30.00 | 23.50 | 20.00 |
| STA1381-011 | | SH 138 STERLING NORTH PART 2 | 02/16/23 | 12,664.00 | 4.50 | 4.00 | 4.00 |
| C133A-052 | | SH 133 ROCKFALL N OF MCCLURE | 02/16/23 | 3,250.00 | 20.00 | 24.50 | 25.00 |
| C1601-084 | | US 160 SECTION3 PRIORITY CULV | 02/16/23 | 672.00 | 30.00 | 37.64 | 20.25 |
| NHPP0701-256 | | I-70B/31.5 RD MESA COUNTY | 02/16/23 | 135.00 | 35.00 | 54.00 | 40.00 |
| SHE067A-044 | | SH 67F M.P. 56.5-57.6 AND SH | 03/02/23 | 221.00 | 50.00 | 9.84 | 9.84 |
| STR194A-002 | | SH194A SUR. TREAT.& DRAI IMP | 03/09/23 | 138.00 | 26.00 | 93.00 | 98.00 |
| STA257A-008 | | SH 257 WINDSOR RESURFACING | 03/30/23 | 242.00 | 30.00 | 21.13 | 18.00 |
| | WEIGHTED AVERAGE FOR THE FIRST QUARTER | | | 19,175.00 | 11.40 | 20.80 | 11.35 |
| | WEIGHTED AVERAGE FOR THE YEAR | | | 19,175.00 | 11.40 | 20.80 | 11.35 |
| ===== 207-00702 | | Topsoil (Offsite) | | Cubic Yard | ===== | | |
| NHPP R100-376 | | VARIOUS LOCATIONS IN REGION 1 | 03/30/23 | 116.00 | 150.00 | 256.55 | 97.00 |
| | WEIGHTED AVERAGE FOR THE FIRST QUARTER | | | 116.00 | 150.00 | 256.55 | 97.00 |
| | WEIGHTED AVERAGE FOR THE YEAR | | | 116.00 | 150.00 | 256.55 | 97.00 |
| ===== 207-00703 | | Topsoil (Wetlnd) | | Cubic Yard | ===== | | |
| STA172A-022 | | SH 172 IGNACIO TO ELMORE'S CO | 01/12/23 | 153.00 | 50.00 | 35.22 | 11.24 |
| C1601-084 | | US 160 SECTION3 PRIORITY CULV | 02/16/23 | 72.00 | 50.00 | 85.61 | 21.00 |
| | WEIGHTED AVERAGE FOR THE FIRST QUARTER | | | 225.00 | 50.00 | 51.34 | 14.36 |
| | WEIGHTED AVERAGE FOR THE YEAR | | | 225.00 | 50.00 | 51.34 | 14.36 |

COLORADO DEPARTMENT OF TRANSPORTATION
ITEM UNIT COSTS BY PROJECTS -- 2023 COST DATA

12:26 Wednesday, May 17, 2023 22

| PROJECT NUMBER | ITEM NUMBER/ PROJECT LOCATION | ITEM DESCRIPTION/ PROJECT LOCATION | DATE LET | UNIT/ QUANTITY | ENGR. EST. | AVERAGE BID | AWARDED BID |
|----------------|--|---------------------------------------|----------|-------------------|------------|-------------|-------------|
| ===== | 207-00704 | Sub Soil Prep | | Sq Yard | ===== | | |
| NHPP0701-256 | | I-70B/31.5 RD MESA COUNTY | 02/16/23 | 812.00 | 2.00 | 3.13 | 3.25 |
| SHE067A-044 | | SH 67F M.P. 56.5-57.6 AND SH | 03/02/23 | 1,113.00 | 1.00 | 2.38 | 2.38 |
| | WEIGHTED AVERAGE FOR THE FIRST QUARTER | | | 1,925.00 | 1.42 | 2.82 | 2.75 |
| | WEIGHTED AVERAGE FOR THE YEAR | | | 1,925.00 | 1.42 | 2.82 | 2.75 |
| ===== | 208-00002 | Erosion Log Type 1 (12 In) | | Lin Foot | ===== | | |
| STA172A-022 | | SH 172 IGNACIO TO ELMORE'S CO | 01/12/23 | 1,595.00 | 9.00 | 5.49 | 5.58 |
| NHPP0701-250 | | I-70B: DDI TO 24 RD, MAIN ST | 01/12/23 | 100.00 | 10.00 | 6.18 | 6.35 |
| FSA0853-123 | | US 85 AND WCR 66 LEFT TURN AC | 01/26/23 | 180.00 | 6.00 | 7.33 | 7.00 |
| STA066A-008 | | SH 66 @ WCR 7 | 01/26/23 | 490.00 | 15.00 | 7.39 | 7.50 |
| C0342-066 | | US 034A (MP 113-150) | 02/02/23 | 300.00 | 7.00 | 14.57 | 16.00 |
| STA1381-011 | | SH 138 STERLING NORTH PART 2 | 02/16/23 | 6,300.00 | 6.00 | 6.50 | 6.50 |
| C133A-052 | | SH 133 ROCKFALL N OF MCCLURE | 02/16/23 | 1,200.00 | 10.00 | 7.48 | 9.00 |
| C1601-084 | | US 160 SECTION3 PRIORITY CULV | 02/16/23 | 1,160.00 | 10.00 | 6.61 | 6.25 |
| NHPP0701-256 | | I-70B/31.5 RD MESA COUNTY | 02/16/23 | 160.00 | 10.00 | 12.50 | 10.00 |
| STR194A-002 | | SH194A SUR. TREAT.& DRAI IMP | 03/09/23 | 7,401.00 | 5.10 | 6.00 | 5.00 |
| | WEIGHTED AVERAGE FOR THE FIRST QUARTER | | | 18,886.00 | 6.70 | 6.68 | 6.19 |
| | WEIGHTED AVERAGE FOR THE YEAR | | | 18,886.00 | 6.70 | 6.68 | 6.19 |
| ===== | 208-00008 | Erosion Log Type 2 (12 In) | | Lin Foot | ===== | | |
| C0703-498 | | EISENHOWER JOHNSON MEMORIAL T | 02/16/23 | 762.00 | 8.00 | 8.23 | 10.00 |
| SHE067A-044 | | SH 67F M.P. 56.5-57.6 AND SH | 03/02/23 | 400.00 | 7.00 | 9.88 | 9.88 |
| | WEIGHTED AVERAGE FOR THE FIRST QUARTER | | | 1,162.00 | 7.66 | 8.48 | 9.96 |
| | WEIGHTED AVERAGE FOR THE YEAR | | | 1,162.00 | 7.66 | 8.48 | 9.96 |
| ===== | 208-00011 | Erosion Bales (Weed Free) | | Each | ===== | | |
| SHE067A-044 | | SH 67F M.P. 56.5-57.6 AND SH | 03/02/23 | 20.00 | 50.00 | 59.01 | 59.01 |
| STR194A-002 | | SH194A SUR. TREAT.& DRAI IMP | 03/09/23 | 3.00 | 28.00 | 103.75 | 107.50 |
| | WEIGHTED AVERAGE FOR THE FIRST QUARTER | | | 23.00 | 47.13 | 69.33 | 65.33 |
| | WEIGHTED AVERAGE FOR THE YEAR | | | 23.00 | 47.13 | 69.33 | 65.33 |

COLORADO DEPARTMENT OF TRANSPORTATION
ITEM UNIT COSTS BY PROJECTS -- 2023 COST DATA

12:26 Wednesday, May 17, 2023 23

| PROJECT NUMBER | ITEM NUMBER/ PROJECT LOCATION | ITEM DESCRIPTION/ PROJECT LOCATION | DATE LET | UNIT/ QUANTITY | ENGR. EST. | AVERAGE BID | AWARDED BID |
|-----------------|--|---------------------------------------|----------|-------------------|------------|-------------|-------------|
| ===== 208-00013 | | Erosion Log Type 1 (20 In) | | Lin Foot | ===== | | |
| NHPPR100-383 | I70 OVER WASHINGTON ST | | 01/26/23 | 100.00 | 12.00 | 22.16 | 16.00 |
| SHE067A-044 | SH 67F M.P. 56.5-57.6 AND SH | | 03/02/23 | 100.00 | 15.00 | 9.28 | 9.28 |
| STR194A-002 | SH194A SUR. TREAT.& DRAI IMP | | 03/09/23 | 308.00 | 7.70 | 9.75 | 8.50 |
| NHPP R100-376 | VARIOUS LOCATIONS IN REGION 1 | | 03/30/23 | 250.00 | 33.70 | 10.36 | 8.50 |
| | WEIGHTED AVERAGE FOR THE FIRST QUARTER | | | 758.00 | 17.81 | 12.38 | 9.59 |
| | WEIGHTED AVERAGE FOR THE YEAR | | | 758.00 | 17.81 | 12.38 | 9.59 |
| ===== 208-00020 | | Silt Fence | | Lin Foot | ===== | | |
| STA172A-022 | SH 172 IGNACIO TO ELMORE'S CO | | 01/12/23 | 37.00 | 7.00 | 4.13 | 4.20 |
| STA1381-011 | SH 138 STERLING NORTH PART 2 | | 02/16/23 | 2,040.00 | 2.50 | 3.25 | 3.25 |
| C1601-084 | US 160 SECTION3 PRIORITY CULV | | 02/16/23 | 100.00 | 10.00 | 4.19 | 4.20 |
| SHE067A-044 | SH 67F M.P. 56.5-57.6 AND SH | | 03/02/23 | 2,900.00 | 5.00 | 2.29 | 2.29 |
| | WEIGHTED AVERAGE FOR THE FIRST QUARTER | | | 5,077.00 | 4.11 | 2.76 | 2.73 |
| | WEIGHTED AVERAGE FOR THE YEAR | | | 5,077.00 | 4.11 | 2.76 | 2.73 |
| ===== 208-00021 | | Silt Fence (Reinf) | | Lin Foot | ===== | | |
| STR194A-002 | SH194A SUR. TREAT.& DRAI IMP | | 03/09/23 | 2,726.00 | 3.30 | 4.18 | 4.35 |
| | WEIGHTED AVERAGE FOR THE FIRST QUARTER | | | 2,726.00 | 3.30 | 4.18 | 4.35 |
| | WEIGHTED AVERAGE FOR THE YEAR | | | 2,726.00 | 3.30 | 4.18 | 4.35 |
| ===== 208-00022 | | Erosion Log (Type 3) (9 In) | | Lin Foot | ===== | | |
| SFTYR200-277 | REGION 2 WIDE, VARIOUS HWY & | | 01/19/23 | 100.00 | 8.00 | 14.50 | 14.00 |
| | WEIGHTED AVERAGE FOR THE FIRST QUARTER | | | 100.00 | 8.00 | 14.50 | 14.00 |
| | WEIGHTED AVERAGE FOR THE YEAR | | | 100.00 | 8.00 | 14.50 | 14.00 |
| ===== 208-00023 | | Erosion Log (Type 3) (12 In) | | Lin Foot | ===== | | |
| STA257A-008 | SH 257 WINDSOR RESURFACING | | 03/30/23 | 200.00 | 5.00 | 7.15 | 8.00 |
| | WEIGHTED AVERAGE FOR THE FIRST QUARTER | | | 200.00 | 5.00 | 7.15 | 8.00 |
| | WEIGHTED AVERAGE FOR THE YEAR | | | 200.00 | 5.00 | 7.15 | 8.00 |

COLORADO DEPARTMENT OF TRANSPORTATION
 ITEM UNIT COSTS BY PROJECTS -- 2023 COST DATA

12:26 Wednesday, May 17, 2023 24

| PROJECT NUMBER | ITEM NUMBER/ PROJECT LOCATION | ITEM DESCRIPTION/ PROJECT LOCATION | DATE LET | UNIT/ QUANTITY | ENGR. EST. | AVERAGE BID | AWARDED BID |
|----------------|----------------------------------|--|----------|-------------------|------------|-------------|-------------|
| ===== | 208-00033 | Sediment Trap | | Each | ===== | ===== | ===== |
| STR194A-002 | | SH194A SUR. TREAT.& DRAI IMP | 03/09/23 | 1.00 | 4300.00 | 5100.00 | 3200.00 |
| | | WEIGHTED AVERAGE FOR THE FIRST QUARTER | | ----- | ----- | ----- | ----- |
| | | | | 1.00 | 4300.00 | 5100.00 | 3200.00 |
| | | WEIGHTED AVERAGE FOR THE YEAR | | ===== | ===== | ===== | ===== |
| | | | | 1.00 | 4300.00 | 5100.00 | 3200.00 |
| ===== | 208-00035 | Aggregate Bag | | Lin Foot | ===== | ===== | ===== |
| STA172A-022 | | SH 172 IGNACIO TO ELMORE'S CO | 01/12/23 | 914.00 | 8.00 | 12.53 | 12.76 |
| NHPP0701-250 | | I-70B: DDI TO 24 RD, MAIN ST | 01/12/23 | 150.00 | 14.00 | 10.75 | 12.50 |
| STR2871-040 | | US 287 MP 0.0 TO MP 122 VARIO | 01/12/23 | 100.00 | 20.00 | 20.09 | 23.20 |
| SFTYR200-277 | | REGION 2 WIDE, VARIOUS HWY & | 01/19/23 | 100.00 | 10.00 | 24.75 | 22.00 |
| FSA0853-123 | | US 85 AND WCR 66 LEFT TURN AC | 01/26/23 | 200.00 | 10.00 | 9.33 | 8.00 |
| STA066A-008 | | SH 66 @ WCR 7 | 01/26/23 | 200.00 | 25.00 | 11.56 | 8.50 |
| C0342-066 | | US 034A (MP 113-150) | 02/02/23 | 40.00 | 35.00 | 15.83 | 14.00 |
| C0703-498 | | EISENHOWER JOHNSON MEMORIAL T | 02/16/23 | 285.00 | 15.00 | 11.03 | 11.00 |
| STA1381-011 | | SH 138 STERLING NORTH PART 2 | 02/16/23 | 500.00 | 12.00 | 11.00 | 11.00 |
| C133A-052 | | SH 133 ROCKFALL N OF MCCLURE | 02/16/23 | 200.00 | 12.00 | 15.76 | 35.00 |
| C 1601-086 | | MAPLE & CHESTNUT SIGNALS AT I | 02/16/23 | 100.00 | 15.00 | 19.00 | 19.00 |
| NHPP0701-256 | | I-70B/31.5 RD MESA COUNTY | 02/16/23 | 100.00 | 10.00 | 10.00 | 15.00 |
| NHPP0253-290 | | I25 @ 58TH AND 62ND | 03/02/23 | 300.00 | 8.00 | 17.82 | 13.00 |
| FBR 0703-520 | | EISENHOWER-JOHNSON MEMORIAL T | 03/16/23 | 1,450.00 | 25.00 | 14.28 | 20.00 |
| STA257A-008 | | SH 257 WINDSOR RESURFACING | 03/30/23 | 4,350.00 | 8.00 | 7.63 | 7.25 |
| NHPP R100-376 | | VARIOUS LOCATIONS IN REGION 1 | 03/30/23 | 1,000.00 | 15.00 | 6.98 | 2.50 |
| | | WEIGHTED AVERAGE FOR THE FIRST QUARTER | | ----- | ----- | ----- | ----- |
| | | | | 9,989.00 | 12.46 | 10.63 | 10.80 |
| | | WEIGHTED AVERAGE FOR THE YEAR | | ===== | ===== | ===== | ===== |
| | | | | 9,989.00 | 12.46 | 10.63 | 10.80 |
| ===== | 208-00045 | Conc Washout Str | | Each | ===== | ===== | ===== |
| C0342-066 | | US 034A (MP 113-150) | 02/02/23 | 1.00 | 3000.00 | 3342.67 | 3774.00 |
| C0703-498 | | EISENHOWER JOHNSON MEMORIAL T | 02/16/23 | 2.00 | 5000.00 | 3618.34 | 3300.00 |
| C133A-052 | | SH 133 ROCKFALL N OF MCCLURE | 02/16/23 | 1.00 | 4000.00 | 5579.49 | 4500.00 |
| | | WEIGHTED AVERAGE FOR THE FIRST QUARTER | | ----- | ----- | ----- | ----- |
| | | | | 4.00 | 4250.00 | 4158.15 | 3718.50 |
| | | WEIGHTED AVERAGE FOR THE YEAR | | ===== | ===== | ===== | ===== |
| | | | | 4.00 | 4250.00 | 4158.15 | 3718.50 |
| ===== | 208-00046 | Pre-fab Conc Washout Str (Type 1) | | Each | ===== | ===== | ===== |
| STA172A-022 | | SH 172 IGNACIO TO ELMORE'S CO | 01/12/23 | 17.00 | 2000.00 | 272.77 | 277.54 |

| PROJECT NUMBER | ITEM NUMBER/ PROJECT LOCATION | ITEM DESCRIPTION/ PROJECT LOCATION | DATE LET | UNIT/ QUANTITY | ENGR. EST. | AVERAGE BID | AWARDED BID |
|----------------|--|--|----------|-------------------|------------|-------------|-------------|
| ===== | 208-00046 | Pre-fab Conc Washout Str (Type I) | | Each | ===== | ===== | ===== |
| STR2871-040 | US 287 MP 0.0 TO MP 122 VARIO | 01/12/23 | 2.00 | 500.00 | 6559.52 | 4060.00 | |
| NHPPR100-383 | I70 OVER WASHINGTON ST | 01/26/23 | 1.00 | 2200.00 | 3688.52 | 2700.00 | |
| C1601-084 | US 160 SECTION3 PRIORITY CULV | 02/16/23 | 1.00 | 3000.00 | 4984.47 | 5000.00 | |
| NHPP0701-256 | I-70B/31.5 RD MESA COUNTY | 02/16/23 | 1.00 | 2500.00 | 1700.00 | 400.00 | |
| NHPP0253-290 | I25 @ 58TH AND 62ND | 03/02/23 | 2.00 | 2500.00 | 3744.08 | 3210.00 | |
| FBR 0703-520 | EISENHOWER-JOHNSON MEMORIAL T | 03/16/23 | 2.00 | 5000.00 | 28625.00 | 10000.00 | |
| NHPP R100-376 | VARIOUS LOCATIONS IN REGION 1 | 03/30/23 | 2.00 | 3148.49 | 3093.01 | 4300.00 | |
| | WEIGHTED AVERAGE FOR THE FIRST QUARTER | | 28.00 | 2285.61 | 3825.24 | 1998.51 | |
| | WEIGHTED AVERAGE FOR THE YEAR | | 28.00 | 2285.61 | 3825.24 | 1998.51 | |
| ===== | 208-00052 | Storm Drain Inlet Protection (Type II) | | Lin Foot | ===== | ===== | ===== |
| NHPP0701-250 | I-70B: DDI TO 24 RD, MAIN ST | 01/12/23 | 100.00 | 100.00 | 75.65 | 86.30 | |
| | WEIGHTED AVERAGE FOR THE FIRST QUARTER | | 100.00 | 100.00 | 75.65 | 86.30 | |
| | WEIGHTED AVERAGE FOR THE YEAR | | 100.00 | 100.00 | 75.65 | 86.30 | |
| ===== | 208-00053 | Storm Drain Inlet Protect (Ty I) (84 In) | | Each | ===== | ===== | ===== |
| NHPP0253-290 | I25 @ 58TH AND 62ND | 03/02/23 | 3.00 | 200.00 | 613.18 | 305.00 | |
| | WEIGHTED AVERAGE FOR THE FIRST QUARTER | | 3.00 | 200.00 | 613.18 | 305.00 | |
| | WEIGHTED AVERAGE FOR THE YEAR | | 3.00 | 200.00 | 613.18 | 305.00 | |
| ===== | 208-00054 | Storm Drain Inlet Protection (Type II) | | Each | ===== | ===== | ===== |
| STA172A-022 | SH 172 IGNACIO TO ELMORE'S CO | 01/12/23 | 4.00 | 250.00 | 212.43 | 215.86 | |
| C0703-498 | EISENHOWER JOHNSON MEMORIAL T | 02/16/23 | 17.00 | 300.00 | 245.03 | 340.00 | |
| C 1601-086 | MAPLE & CHESTNUT SIGNALS AT I | 02/16/23 | 8.00 | 250.00 | 300.00 | 300.00 | |
| | WEIGHTED AVERAGE FOR THE FIRST QUARTER | | 29.00 | 279.31 | 247.70 | 311.84 | |
| | WEIGHTED AVERAGE FOR THE YEAR | | 29.00 | 279.31 | 247.70 | 311.84 | |
| ===== | 208-00055 | Rigid Inlet Prot Device | | Each | ===== | ===== | ===== |
| C0703-498 | EISENHOWER JOHNSON MEMORIAL T | 02/16/23 | 55.00 | 900.00 | 307.02 | 200.00 | |
| | WEIGHTED AVERAGE FOR THE FIRST QUARTER | | 55.00 | 900.00 | 307.02 | 200.00 | |
| | WEIGHTED AVERAGE FOR THE YEAR | | 55.00 | 900.00 | 307.02 | 200.00 | |

COLORADO DEPARTMENT OF TRANSPORTATION
 ITEM UNIT COSTS BY PROJECTS -- 2023 COST DATA

12:26 Wednesday, May 17, 2023 26

| PROJECT NUMBER | ITEM NUMBER/ PROJECT LOCATION | ITEM DESCRIPTION/ PROJECT LOCATION | DATE LET | UNIT/ QUANTITY | ENGR. EST. | AVERAGE BID | AWARDED BID |
|----------------|--|---|----------|-------------------|------------|-------------|-------------|
| ===== | 208-00056 | Storm Drain Inlet Protection (Type III) | | Each | ===== | ===== | ===== |
| NHPPR100-383 | | I70 OVER WASHINGTON ST | 01/26/23 | 13.00 | 250.00 | 386.50 | 330.00 |
| NHPP R100-376 | | VARIOUS LOCATIONS IN REGION 1 | 03/30/23 | 1.00 | 213.00 | 203.17 | 92.00 |
| | WEIGHTED AVERAGE FOR THE FIRST QUARTER | | | 14.00 | 247.36 | 377.56 | 313.00 |
| | WEIGHTED AVERAGE FOR THE YEAR | | | 14.00 | 247.36 | 377.56 | 313.00 |
| ===== | 208-00058 | Storm Drain Inlet Protect (Ty I) (204 In) | | Each | ===== | ===== | ===== |
| STA257A-008 | | SH 257 WINDSOR RESURFACING | 03/30/23 | 2.00 | 400.00 | 237.50 | 180.00 |
| | WEIGHTED AVERAGE FOR THE FIRST QUARTER | | | 2.00 | 400.00 | 237.50 | 180.00 |
| | WEIGHTED AVERAGE FOR THE YEAR | | | 2.00 | 400.00 | 237.50 | 180.00 |
| ===== | 208-00070 | Vehicle Tracking Pad | | Each | ===== | ===== | ===== |
| STR194A-002 | | SH194A SUR. TREAT.& DRAI IMP | 03/09/23 | 2.00 | 3500.00 | 3250.00 | 1500.00 |
| | WEIGHTED AVERAGE FOR THE FIRST QUARTER | | | 2.00 | 3500.00 | 3250.00 | 1500.00 |
| | WEIGHTED AVERAGE FOR THE YEAR | | | 2.00 | 3500.00 | 3250.00 | 1500.00 |
| ===== | 208-00075 | Pre-fab Vehicle Track Pad | | Each | ===== | ===== | ===== |
| STA172A-022 | | SH 172 IGNACIO TO ELMORE'S CO | 01/12/23 | 5.00 | 6500.00 | 4026.98 | 4093.96 |
| FSA0853-123 | | US 85 AND WCR 66 LEFT TURN AC | 01/26/23 | 4.00 | 5000.00 | 3903.50 | 2800.00 |
| NHPPR100-383 | | I70 OVER WASHINGTON ST | 01/26/23 | 1.00 | 5250.00 | 8042.00 | 4600.00 |
| STA066A-008 | | SH 66 @ WCR 7 | 01/26/23 | 2.00 | 5000.00 | 2969.03 | 2500.00 |
| STA1381-011 | | SH 138 STERLING NORTH PART 2 | 02/16/23 | 8.00 | 3000.00 | 2500.00 | 2500.00 |
| C133A-052 | | SH 133 ROCKFALL N OF MCCLURE | 02/16/23 | 4.00 | 5000.00 | 7746.25 | 18000.00 |
| C1601-084 | | US 160 SECTION3 PRIORITY CULV | 02/16/23 | 1.00 | 5000.00 | 10617.44 | 3800.00 |
| C 1601-086 | | MAPLE & CHESTNUT SIGNALS AT I | 02/16/23 | 1.00 | 5000.00 | 23600.00 | 23600.00 |
| NHPP0701-256 | | I-70B/31.5 RD MESA COUNTY | 02/16/23 | 1.00 | 5000.00 | 1750.00 | 2000.00 |
| NHPP0253-290 | | I25 @ 58TH AND 62ND | 03/02/23 | 1.00 | 3000.00 | 6788.80 | 5750.00 |
| SHE067A-044 | | SH 67F M.P. 56.5-57.6 AND SH | 03/02/23 | 4.00 | 6000.00 | 7560.00 | 7560.00 |
| STA257A-008 | | SH 257 WINDSOR RESURFACING | 03/30/23 | 1.00 | 3000.00 | 5087.50 | 2600.00 |
| NHPP R100-376 | | VARIOUS LOCATIONS IN REGION 1 | 03/30/23 | 2.00 | 4300.00 | 3909.77 | 4350.00 |
| | WEIGHTED AVERAGE FOR THE FIRST QUARTER | | | 35.00 | 4724.29 | 5128.83 | 5998.85 |
| | WEIGHTED AVERAGE FOR THE YEAR | | | 35.00 | 4724.29 | 5128.83 | 5998.85 |

| PROJECT NUMBER | ITEM NUMBER/ PROJECT LOCATION | ITEM DESCRIPTION/ PROJECT LOCATION | DATE LET | UNIT/ QUANTITY | ENGR. EST. | AVERAGE BID | AWARDED BID |
|-----------------|--|--|----------|-------------------|------------|-------------|-------------|
| ===== 208-00082 | | Construction Mat | | Sq Foot | ===== | | |
| STA172A-022 | | SH 172 IGNACIO TO ELMORE'S CO | 01/12/23 | 1,200.00 | 15.00 | 24.35 | 14.09 |
| C1601-084 | | US 160 SECTION3 PRIORITY CULV | 02/16/23 | 475.00 | 50.00 | 26.28 | 27.00 |
| STA257A-008 | | SH 257 WINDSOR RESURFACING | 03/30/23 | 1,000.00 | 15.00 | 18.75 | 25.00 |
| | WEIGHTED AVERAGE FOR THE FIRST QUARTER | | | 2,675.00 | 21.21 | 22.60 | 20.46 |
| | WEIGHTED AVERAGE FOR THE YEAR | | | 2,675.00 | 21.21 | 22.60 | 20.46 |
| ===== 208-00090 | | Erosion Control (Curb Ramp) | | Each | ===== | | |
| STM C440-013 | | R3 EAGLE RESIDENCY ADA RAMP I | 02/16/23 | 27.00 | 300.00 | 500.00 | 500.00 |
| C0881-036 | | R1 CURB RAMPS-SH88B & US285D | 02/16/23 | 198.00 | 700.00 | 515.00 | 800.00 |
| | WEIGHTED AVERAGE FOR THE FIRST QUARTER | | | 225.00 | 652.00 | 514.51 | 764.00 |
| | WEIGHTED AVERAGE FOR THE YEAR | | | 225.00 | 652.00 | 514.51 | 764.00 |
| ===== 208-00103 | | Removal and Disposal of Sediment (Labor) | | Hour | ===== | | |
| STA172A-022 | | SH 172 IGNACIO TO ELMORE'S CO | 01/12/23 | 10.00 | 60.00 | 61.72 | 62.74 |
| NHPP0701-250 | | I-70B: DDI TO 24 RD, MAIN ST | 01/12/23 | 20.00 | 100.00 | 55.75 | 60.00 |
| FSA0853-123 | | US 85 AND WCR 66 LEFT TURN AC | 01/26/23 | 40.00 | 75.00 | 56.92 | 47.00 |
| NHPPR100-383 | | I70 OVER WASHINGTON ST | 01/26/23 | 20.00 | 75.00 | 86.62 | 105.00 |
| STA066A-008 | | SH 66 @ WCR 7 | 01/26/23 | 32.00 | 120.00 | 106.45 | 115.00 |
| C0342-066 | | US 034A (MP 113-150) | 02/02/23 | 2.00 | 105.00 | 85.00 | 55.00 |
| C0703-498 | | EISENHOWER JOHNSON MEMORIAL T | 02/16/23 | 16.00 | 85.00 | 64.00 | 59.00 |
| STA1381-011 | | SH 138 STERLING NORTH PART 2 | 02/16/23 | 200.00 | 60.00 | 95.00 | 95.00 |
| C133A-052 | | SH 133 ROCKFALL N OF MCCLURE | 02/16/23 | 80.00 | 70.00 | 78.31 | 140.00 |
| C1601-084 | | US 160 SECTION3 PRIORITY CULV | 02/16/23 | 10.00 | 80.00 | 111.45 | 75.00 |
| C 1601-086 | | MAPLE & CHESTNUT SIGNALS AT I | 02/16/23 | 10.00 | 75.00 | 90.00 | 90.00 |
| NHPP0701-256 | | I-70B/31.5 RD MESA COUNTY | 02/16/23 | 20.00 | 75.00 | 25.00 | 40.00 |
| NHPP0253-290 | | I25 @ 58TH AND 62ND | 03/02/23 | 50.00 | 70.00 | 72.13 | 123.00 |
| SHE067A-044 | | SH 67F M.P. 56.5-57.6 AND SH | 03/02/23 | 80.00 | 75.00 | 43.20 | 43.20 |
| STRR300-265 | | MOUNTAIN RE FY23 CRACK SEALS | 03/02/23 | 40.00 | 75.00 | 75.00 | 75.00 |
| FBR 0703-520 | | EISENHOWER-JOHNSON MEMORIAL T | 03/16/23 | 5.00 | 110.00 | 149.00 | 223.00 |
| STA257A-008 | | SH 257 WINDSOR RESURFACING | 03/30/23 | 80.00 | 50.00 | 45.31 | 54.00 |
| NHPP R100-376 | | VARIOUS LOCATIONS IN REGION 1 | 03/30/23 | 12.00 | 87.00 | 86.47 | 81.00 |
| | WEIGHTED AVERAGE FOR THE FIRST QUARTER | | | 727.00 | 70.50 | 73.23 | 85.56 |
| | WEIGHTED AVERAGE FOR THE YEAR | | | 727.00 | 70.50 | 73.23 | 85.56 |
| ===== 208-00105 | | Removal and Disposal of Sediment (Equip) | | Hour | ===== | | |
| FSA0853-123 | | US 85 AND WCR 66 LEFT TURN AC | 01/26/23 | 8.00 | 130.00 | 145.67 | 90.00 |

| PROJECT NUMBER | ITEM NUMBER/ PROJECT LOCATION | ITEM DESCRIPTION/ PROJECT LOCATION | DATE LET | UNIT/ QUANTITY | ENGR. EST. | AVERAGE BID | AWARDED BID |
|-----------------|--|--|----------|-------------------|------------|-------------|-------------|
| ===== 208-00105 | | Removal and Disposal of Sediment (Equip) | | Hour ===== | | | |
| NHPPR100-383 | I70 OVER WASHINGTON ST | | 01/26/23 | 20.00 | 150.00 | 163.55 | 190.00 |
| STA066A-008 | SH 66 @ WCR 7 | | 01/26/23 | 16.00 | 300.00 | 201.29 | 200.00 |
| C0342-066 | US 034A (MP 113-150) | | 02/02/23 | 2.00 | 250.00 | 146.33 | 64.00 |
| C0703-498 | EISENHOWER JOHNSON MEMORIAL T | | 02/16/23 | 16.00 | 180.00 | 136.67 | 160.00 |
| STA1381-011 | SH 138 STERLING NORTH PART 2 | | 02/16/23 | 80.00 | 120.00 | 135.00 | 135.00 |
| C133A-052 | SH 133 ROCKFALL N OF MCCLURE | | 02/16/23 | 80.00 | 160.00 | 177.19 | 240.00 |
| C1601-084 | US 160 SECTION3 PRIORITY CULV | | 02/16/23 | 10.00 | 200.00 | 187.88 | 150.00 |
| C 1601-086 | MAPLE & CHESTNUT SIGNALS AT I | | 02/16/23 | 10.00 | 225.00 | 200.00 | 200.00 |
| NHPP0701-256 | I-70B/31.5 RD MESA COUNTY | | 02/16/23 | 20.00 | 175.00 | 105.00 | 200.00 |
| SHE067A-044 | SH 67F M.P. 56.5-57.6 AND SH | | 03/02/23 | 80.00 | 125.00 | 108.00 | 108.00 |
| STA257A-008 | SH 257 WINDSOR RESURFACING | | 03/30/23 | 40.00 | 120.00 | 114.50 | 121.00 |
| NHPP R100-376 | VARIOUS LOCATIONS IN REGION 1 | | 03/30/23 | 12.00 | 138.82 | 266.99 | 360.00 |
| | WEIGHTED AVERAGE FOR THE FIRST QUARTER | | | 394.00 | 149.33 | 158.49 | 166.77 |
| | WEIGHTED AVERAGE FOR THE YEAR | | | 394.00 | 149.33 | 158.49 | 166.77 |
| ===== 208-00106 | | Sweeping (Sediment Removal) | | Hour ===== | | | |
| STA172A-022 | SH 172 IGNACIO TO ELMORE'S CO | | 01/12/23 | 10.00 | 160.00 | 148.73 | 173.45 |
| NHPP0701-250 | I-70B: DDI TO 24 RD, MAIN ST | | 01/12/23 | 20.00 | 250.00 | 190.00 | 180.00 |
| SFTYR200-277 | REGION 2 WIDE, VARIOUS HWY & | | 01/19/23 | 45.00 | 160.00 | 120.00 | 40.00 |
| FSA0853-123 | US 85 AND WCR 66 LEFT TURN AC | | 01/26/23 | 80.00 | 150.00 | 150.00 | 100.00 |
| NHPPR100-383 | I70 OVER WASHINGTON ST | | 01/26/23 | 40.00 | 170.00 | 218.65 | 225.00 |
| STA066A-008 | SH 66 @ WCR 7 | | 01/26/23 | 32.00 | 250.00 | 218.90 | 205.00 |
| C0342-066 | US 034A (MP 113-150) | | 02/02/23 | 2.00 | 200.00 | 159.67 | 29.00 |
| C0703-498 | EISENHOWER JOHNSON MEMORIAL T | | 02/16/23 | 4.00 | 200.00 | 180.00 | 170.00 |
| STA1381-011 | SH 138 STERLING NORTH PART 2 | | 02/16/23 | 160.00 | 140.00 | 215.00 | 215.00 |
| C133A-052 | SH 133 ROCKFALL N OF MCCLURE | | 02/16/23 | 40.00 | 190.00 | 169.25 | 130.00 |
| C 1601-086 | MAPLE & CHESTNUT SIGNALS AT I | | 02/16/23 | 20.00 | 75.00 | 100.00 | 100.00 |
| NHPP0701-256 | I-70B/31.5 RD MESA COUNTY | | 02/16/23 | 40.00 | 175.00 | 67.50 | 100.00 |
| NHPP0253-290 | I25 @ 58TH AND 62ND | | 03/02/23 | 75.00 | 125.00 | 175.25 | 245.00 |
| SHE067A-044 | SH 67F M.P. 56.5-57.6 AND SH | | 03/02/23 | 160.00 | 250.00 | 64.07 | 64.07 |
| FBR 0703-520 | EISENHOWER-JOHNSON MEMORIAL T | | 03/16/23 | 5.00 | 180.00 | 212.50 | 250.00 |
| STA257A-008 | SH 257 WINDSOR RESURFACING | | 03/30/23 | 176.00 | 130.00 | 127.50 | 125.00 |
| NHPP R100-376 | VARIOUS LOCATIONS IN REGION 1 | | 03/30/23 | 60.00 | 178.00 | 225.61 | 250.00 |
| | WEIGHTED AVERAGE FOR THE FIRST QUARTER | | | 969.00 | 169.39 | 158.19 | 148.51 |
| | WEIGHTED AVERAGE FOR THE YEAR | | | 969.00 | 169.39 | 158.19 | 148.51 |
| ===== 208-00107 | | Rem Trash | | Hour ===== | | | |
| NHPP0701-250 | I-70B: DDI TO 24 RD, MAIN ST | | 01/12/23 | 80.00 | 150.00 | 100.75 | 150.00 |

| PROJECT NUMBER | ITEM NUMBER/ PROJECT LOCATION | ITEM DESCRIPTION/ PROJECT LOCATION | DATE LET | UNIT/ QUANTITY | ENGR. EST. | AVERAGE BID | AWARDED BID |
|-----------------|----------------------------------|--|----------|-------------------|------------|-------------|-------------|
| ===== 208-00107 | | Rem Trash | | Hour ===== | | | |
| FSA0853-123 | | US 85 AND WCR 66 LEFT TURN AC | 01/26/23 | 16.00 | 70.00 | 163.67 | 64.00 |
| NHPPR100-383 | | I70 OVER WASHINGTON ST | 01/26/23 | 20.00 | 110.00 | 127.09 | 113.00 |
| STA066A-008 | | SH 66 @ WCR 7 | 01/26/23 | 8.00 | 250.00 | 104.45 | 115.00 |
| C0703-498 | | EISENHOWER JOHNSON MEMORIAL T | 02/16/23 | 8.00 | 150.00 | 64.00 | 59.00 |
| STA1381-011 | | SH 138 STERLING NORTH PART 2 | 02/16/23 | 40.00 | 100.00 | 125.00 | 125.00 |
| C133A-052 | | SH 133 ROCKFALL N OF MCCLURE | 02/16/23 | 5.00 | 125.00 | 116.25 | 100.00 |
| NHPP0701-256 | | I-70B/31.5 RD MESA COUNTY | 02/16/23 | 10.00 | 100.00 | 33.00 | 46.00 |
| NHPP0253-290 | | I25 @ 58TH AND 62ND | 03/02/23 | 30.00 | 100.00 | 110.25 | 155.00 |
| SHE067A-044 | | SH 67F M.P. 56.5-57.6 AND SH | 03/02/23 | 80.00 | 100.00 | 81.00 | 81.00 |
| FBR 0703-520 | | EISENHOWER-JOHNSON MEMORIAL T | 03/16/23 | 5.00 | 200.00 | 95.00 | 105.00 |
| STA257A-008 | | SH 257 WINDSOR RESURFACING | 03/30/23 | 30.00 | 50.00 | 53.50 | 70.00 |
| NHPP R100-376 | | VARIOUS LOCATIONS IN REGION 1 | 03/30/23 | 10.00 | 124.60 | 152.28 | 180.00 |
| | | WEIGHTED AVERAGE FOR THE FIRST QUARTER | | 342.00 | 113.72 | 106.62 | 111.67 |
| | | WEIGHTED AVERAGE FOR THE YEAR | | 342.00 | 113.72 | 106.62 | 111.67 |
| ===== 208-00146 | | Pre-fab Conc Washout Str (Type 2) | | Each ===== | | | |
| FSA0853-123 | | US 85 AND WCR 66 LEFT TURN AC | 01/26/23 | 2.00 | 1200.00 | 1692.00 | 600.00 |
| STA1381-011 | | SH 138 STERLING NORTH PART 2 | 02/16/23 | 5.00 | 1500.00 | 2100.00 | 2100.00 |
| C 1601-086 | | MAPLE & CHESTNUT SIGNALS AT I | 02/16/23 | 2.00 | 500.00 | 350.00 | 350.00 |
| STA257A-008 | | SH 257 WINDSOR RESURFACING | 03/30/23 | 2.00 | 2000.00 | 3025.00 | 1550.00 |
| | | WEIGHTED AVERAGE FOR THE FIRST QUARTER | | 11.00 | 1354.55 | 1895.83 | 1409.09 |
| | | WEIGHTED AVERAGE FOR THE YEAR | | 11.00 | 1354.55 | 1895.83 | 1409.09 |
| ===== 208-00200 | | Erosion Control Management | | LUMP SUM ===== | | | |
| STA172A-022 | | SH 172 IGNACIO TO ELMORE'S CO | 01/12/23 | 1.00 | 50000.00 | 8652.34 | 8804.68 |
| | | WEIGHTED AVERAGE FOR THE FIRST QUARTER | | 1.00 | 50000.00 | 8652.34 | 8804.68 |
| | | WEIGHTED AVERAGE FOR THE YEAR | | 1.00 | 50000.00 | 8652.34 | 8804.68 |
| ===== 208-00207 | | Erosion Control Management | | Day ===== | | | |
| SFTYR200-277 | | REGION 2 WIDE, VARIOUS HWY & | 01/19/23 | 20.00 | 250.00 | 362.50 | 350.00 |
| FSA0853-123 | | US 85 AND WCR 66 LEFT TURN AC | 01/26/23 | 18.00 | 700.00 | 367.67 | 420.00 |
| NHPPR100-383 | | I70 OVER WASHINGTON ST | 01/26/23 | 10.00 | 250.00 | 443.87 | 450.00 |
| C0703-498 | | EISENHOWER JOHNSON MEMORIAL T | 02/16/23 | 30.00 | 300.00 | 193.33 | 130.00 |

| PROJECT NUMBER | ITEM NUMBER/ PROJECT LOCATION | ITEM DESCRIPTION/ PROJECT LOCATION | DATE LET | UNIT/ QUANTITY | ENGR. EST. | AVERAGE BID | AWARDED BID |
|----------------|--|---------------------------------------|----------|-------------------|------------|-------------|-------------|
| ===== | 208-00207 | Erosion Control Management | | Day | ===== | ===== | ===== |
| STA1381-011 | SH 138 STERLING NORTH PART 2 | 02/16/23 | 20.00 | 750.00 | 415.00 | 415.00 | |
| C133A-052 | SH 133 ROCKFALL N OF MCCLURE | 02/16/23 | 16.00 | 350.00 | 903.94 | 700.00 | |
| SHE067A-044 | SH 67F M.P. 56.5-57.6 AND SH | 03/02/23 | 50.00 | 500.00 | 1041.16 | 1041.16 | |
| STA257A-008 | SH 257 WINDSOR RESURFACING | 03/30/23 | 22.00 | 320.00 | 295.00 | 450.00 | |
| NHPP R100-376 | VARIOUS LOCATIONS IN REGION 1 | 03/30/23 | 10.00 | 244.66 | 476.89 | 420.00 | |
| | WEIGHTED AVERAGE FOR THE FIRST QUARTER | | 196.00 | 429.52 | 484.23 | 554.17 | |
| | WEIGHTED AVERAGE FOR THE YEAR | | 196.00 | 429.52 | 484.23 | 554.17 | |
| ===== | 208-00400 | Water Control | | LUMP SUM | ===== | ===== | ===== |
| STA172A-022 | SH 172 IGNACIO TO ELMORE'S CO | 01/12/23 | 1.00 | 50000.00 | 75972.62 | 32945.24 | |
| C1601-084 | US 160 SECTION3 PRIORITY CULV | 02/16/23 | 1.00 | 7000.00 | 12192.24 | 4500.00 | |
| STR194A-002 | SH194A SUR. TREAT.& DRAI IMP | 03/09/23 | 1.00 | 55000.00 | 77000.00 | 80000.00 | |
| | WEIGHTED AVERAGE FOR THE FIRST QUARTER | | 3.00 | 22166.67 | 33623.59 | 21824.21 | |
| | WEIGHTED AVERAGE FOR THE YEAR | | 3.00 | 22166.67 | 33623.59 | 21824.21 | |
| ===== | 210-00011 | Res Mailbox Str (Ty 1) | | Each | ===== | ===== | ===== |
| STA1381-011 | SH 138 STERLING NORTH PART 2 | 02/16/23 | 4.00 | 335.00 | 575.00 | 575.00 | |
| | WEIGHTED AVERAGE FOR THE FIRST QUARTER | | 4.00 | 335.00 | 575.00 | 575.00 | |
| | WEIGHTED AVERAGE FOR THE YEAR | | 4.00 | 335.00 | 575.00 | 575.00 | |
| ===== | 210-00012 | Res Mailbox Str (Ty 2) | | Each | ===== | ===== | ===== |
| STA1381-011 | SH 138 STERLING NORTH PART 2 | 02/16/23 | 2.00 | 400.00 | 575.00 | 575.00 | |
| | WEIGHTED AVERAGE FOR THE FIRST QUARTER | | 2.00 | 400.00 | 575.00 | 575.00 | |
| | WEIGHTED AVERAGE FOR THE YEAR | | 2.00 | 400.00 | 575.00 | 575.00 | |
| ===== | 210-00013 | Res Mailbox Str (Ty 3) | | Each | ===== | ===== | ===== |
| STA1381-011 | SH 138 STERLING NORTH PART 2 | 02/16/23 | 1.00 | 550.00 | 575.00 | 575.00 | |
| | WEIGHTED AVERAGE FOR THE FIRST QUARTER | | 1.00 | 550.00 | 575.00 | 575.00 | |
| | WEIGHTED AVERAGE FOR THE YEAR | | 1.00 | 550.00 | 575.00 | 575.00 | |

| PROJECT NUMBER | ITEM NUMBER/ PROJECT LOCATION | ITEM DESCRIPTION/ PROJECT LOCATION | DATE LET | UNIT/ QUANTITY | ENGR. EST. | AVERAGE BID | AWARDED BID |
|----------------|--|---------------------------------------|----------|-------------------|------------|-------------|-------------|
| ===== | 210-00065 | Res Monument (Ty 3A) | | Each | ===== | | |
| C0881-036 | | R1 CURB RAMPS-SH88B & US285D | 02/16/23 | 4.00 | 800.00 | 787.50 | 100.00 |
| STA257A-008 | | SH 257 WINDSOR RESURFACING | 03/30/23 | 6.00 | 1000.00 | 1065.00 | 1150.00 |
| | WEIGHTED AVERAGE FOR THE FIRST QUARTER | | | 10.00 | 920.00 | 906.43 | 730.00 |
| | WEIGHTED AVERAGE FOR THE YEAR | | | 10.00 | 920.00 | 906.43 | 730.00 |
| ===== | 210-00075 | Reset Pre-Fab Veh Tracking Pad | | Each | ===== | | |
| NHPP R100-376 | | VARIOUS LOCATIONS IN REGION 1 | 03/30/23 | 2.00 | 1400.00 | 863.26 | 570.00 |
| | WEIGHTED AVERAGE FOR THE FIRST QUARTER | | | 2.00 | 1400.00 | 863.26 | 570.00 |
| | WEIGHTED AVERAGE FOR THE YEAR | | | 2.00 | 1400.00 | 863.26 | 570.00 |
| ===== | 210-00090 | Res Delineator | | Each | ===== | | |
| STA172A-022 | | SH 172 IGNACIO TO ELMORE'S CO | 01/12/23 | 4.00 | 45.00 | 13.61 | 13.82 |
| C0881-036 | | R1 CURB RAMPS-SH88B & US285D | 02/16/23 | 15.00 | 35.00 | 119.25 | 50.00 |
| | WEIGHTED AVERAGE FOR THE FIRST QUARTER | | | 19.00 | 37.11 | 106.82 | 42.38 |
| | WEIGHTED AVERAGE FOR THE YEAR | | | 19.00 | 37.11 | 106.82 | 42.38 |
| ===== | 210-00810 | Res Ground Sign | | Each | ===== | | |
| STA172A-022 | | SH 172 IGNACIO TO ELMORE'S CO | 01/12/23 | 31.00 | 350.00 | 392.38 | 398.76 |
| FSA0853-123 | | US 85 AND WCR 66 LEFT TURN AC | 01/26/23 | 9.00 | 400.00 | 406.17 | 630.00 |
| NHPP0253-296 | | I-25 @ LCR 16 (MP 253.8-254.5 | 02/07/23 | 1.00 | 336.66 | 360.23 | 360.23 |
| C0703-498 | | EISENHOWER JOHNSON MEMORIAL T | 02/16/23 | 10.00 | 700.00 | 834.88 | 42.00 |
| STA1381-011 | | SH 138 STERLING NORTH PART 2 | 02/16/23 | 1.00 | 420.00 | 330.00 | 330.00 |
| C133A-052 | | SH 133 ROCKFALL N OF MCCLURE | 02/16/23 | 3.00 | 550.00 | 817.08 | 1300.00 |
| C1601-084 | | US 160 SECTION3 PRIORITY CULV | 02/16/23 | 2.00 | 500.00 | 320.29 | 350.00 |
| STM C440-013 | | R3 EAGLE RESIDENCY ADA RAMP I | 02/16/23 | 1.00 | 450.00 | 200.00 | 200.00 |
| NHPP0701-256 | | I-70B/31.5 RD MESA COUNTY | 02/16/23 | 2.00 | 600.00 | 625.00 | 450.00 |
| C0881-036 | | R1 CURB RAMPS-SH88B & US285D | 02/16/23 | 27.00 | 450.00 | 408.75 | 500.00 |
| SHE067A-044 | | SH 67F M.P. 56.5-57.6 AND SH | 03/02/23 | 1.00 | 500.00 | 772.20 | 772.20 |
| | WEIGHTED AVERAGE FOR THE FIRST QUARTER | | | 88.00 | 444.96 | 470.15 | 444.48 |
| | WEIGHTED AVERAGE FOR THE YEAR | | | 88.00 | 444.96 | 470.15 | 444.48 |

COLORADO DEPARTMENT OF TRANSPORTATION
ITEM UNIT COSTS BY PROJECTS -- 2023 COST DATA

12:26 Wednesday, May 17, 2023 32

| PROJECT NUMBER | ITEM NUMBER/ PROJECT LOCATION | ITEM DESCRIPTION/ PROJECT LOCATION | DATE LET | UNIT/ QUANTITY | ENGR. EST. | AVERAGE BID | AWARDED BID |
|----------------|----------------------------------|--|----------|-------------------|------------|-------------|-------------|
| ===== | 210-00815 | Res Sign Panel | | Each | ===== | ===== | ===== |
| STA172A-022 | | SH 172 IGNACIO TO ELMORE'S CO | 01/12/23 | 22.00 | 150.00 | 261.42 | 265.84 |
| C 1601-086 | | MAPLE & CHESTNUT SIGNALS AT I | 02/16/23 | 2.00 | 300.00 | 150.00 | 150.00 |
| STR194A-002 | | SH194A SUR. TREAT.& DRAI IMP | 03/09/23 | 10.00 | 170.00 | 287.50 | 275.00 |
| | | WEIGHTED AVERAGE FOR THE FIRST QUARTER | | 34.00 | 164.71 | 265.95 | 261.72 |
| | | WEIGHTED AVERAGE FOR THE YEAR | | 34.00 | 164.71 | 265.95 | 261.72 |
| ===== | 210-00858 | Res Pedestal Pole | | Each | ===== | ===== | ===== |
| STM C440-013 | | R3 EAGLE RESIDENCY ADA RAMP I | 02/16/23 | 1.00 | 1200.00 | 12000.00 | 12000.00 |
| C0881-036 | | R1 CURB RAMPS-SH88B & US285D | 02/16/23 | 9.00 | 750.00 | 2475.00 | 2380.00 |
| | | WEIGHTED AVERAGE FOR THE FIRST QUARTER | | 10.00 | 795.00 | 2732.43 | 3342.00 |
| | | WEIGHTED AVERAGE FOR THE YEAR | | 10.00 | 795.00 | 2732.43 | 3342.00 |
| ===== | 210-00859 | Mod Ped Push Button | | Each | ===== | ===== | ===== |
| STM C440-013 | | R3 EAGLE RESIDENCY ADA RAMP I | 02/16/23 | 2.00 | 700.00 | 1500.00 | 1500.00 |
| | | WEIGHTED AVERAGE FOR THE FIRST QUARTER | | 2.00 | 700.00 | 1500.00 | 1500.00 |
| | | WEIGHTED AVERAGE FOR THE YEAR | | 2.00 | 700.00 | 1500.00 | 1500.00 |
| ===== | 210-00860 | Res Ped Push Button | | Each | ===== | ===== | ===== |
| STM C440-013 | | R3 EAGLE RESIDENCY ADA RAMP I | 02/16/23 | 9.00 | 500.00 | 500.00 | 500.00 |
| C0881-036 | | R1 CURB RAMPS-SH88B & US285D | 02/16/23 | 17.00 | 1400.00 | 649.00 | 166.00 |
| | | WEIGHTED AVERAGE FOR THE FIRST QUARTER | | 26.00 | 1088.46 | 631.58 | 281.62 |
| | | WEIGHTED AVERAGE FOR THE YEAR | | 26.00 | 1088.46 | 631.58 | 281.62 |
| ===== | 210-01000 | Res Fence | | Lin Foot | ===== | ===== | ===== |
| C0881-036 | | R1 CURB RAMPS-SH88B & US285D | 02/16/23 | 40.00 | 20.00 | 47.50 | 20.00 |
| NHPP0253-290 | | I25 @ 58TH AND 62ND | 03/02/23 | 40.00 | 80.00 | 145.82 | 245.00 |
| | | WEIGHTED AVERAGE FOR THE FIRST QUARTER | | 80.00 | 50.00 | 89.64 | 132.50 |
| | | WEIGHTED AVERAGE FOR THE YEAR | | 80.00 | 50.00 | 89.64 | 132.50 |

COLORADO DEPARTMENT OF TRANSPORTATION
ITEM UNIT COSTS BY PROJECTS -- 2023 COST DATA

12:26 Wednesday, May 17, 2023 33

| PROJECT NUMBER | ITEM NUMBER/ PROJECT LOCATION | ITEM DESCRIPTION/ PROJECT LOCATION | DATE LET | UNIT/ QUANTITY | ENGR. EST. | AVERAGE BID | AWARDED BID |
|----------------|----------------------------------|--|----------|-------------------|------------|-------------|-------------|
| ===== | 210-01011 | Res Gate | | Each | ===== | ===== | ===== |
| STR194A-002 | | SH194A SUR. TREAT.& DRAI IMP | 03/09/23 | 1.00 | 820.00 | 3137.50 | 5475.00 |
| | WEIGHTED | AVERAGE FOR THE FIRST QUARTER | | 1.00 | 820.00 | 3137.50 | 5475.00 |
| | | WEIGHTED AVERAGE FOR THE YEAR | | 1.00 | 820.00 | 3137.50 | 5475.00 |
| ===== | 210-01130 | Res Gdrail Ty 3 | | Lin Foot | ===== | ===== | ===== |
| C133A-052 | | SH 133 ROCKFALL N OF MCCLURE | 02/16/23 | 25.00 | 40.00 | 132.75 | 275.00 |
| | WEIGHTED | AVERAGE FOR THE FIRST QUARTER | | 25.00 | 40.00 | 132.75 | 275.00 |
| | | WEIGHTED AVERAGE FOR THE YEAR | | 25.00 | 40.00 | 132.75 | 275.00 |
| ===== | 210-01180 | Reset Guardrail (Special) | | Lin Foot | ===== | ===== | ===== |
| STA1381-011 | | SH 138 STERLING NORTH PART 2 | 02/16/23 | 31.00 | 100.00 | 112.50 | 112.50 |
| | WEIGHTED | AVERAGE FOR THE FIRST QUARTER | | 31.00 | 100.00 | 112.50 | 112.50 |
| | | WEIGHTED AVERAGE FOR THE YEAR | | 31.00 | 100.00 | 112.50 | 112.50 |
| ===== | 210-02510 | Relay Sprinkler System | | LUMP SUM | ===== | ===== | ===== |
| STA172A-022 | | SH 172 IGNACIO TO ELMORE'S CO | 01/12/23 | 1.00 | 250.00 | 2646.53 | 4263.05 |
| C0881-036 | | R1 CURB RAMPS-SH88B & US285D | 02/16/23 | 1.00 | 2000.00 | 51875.00 | 25000.00 |
| | WEIGHTED | AVERAGE FOR THE FIRST QUARTER | | 2.00 | 833.33 | 27260.76 | 11175.37 |
| | | WEIGHTED AVERAGE FOR THE YEAR | | 2.00 | 833.33 | 27260.76 | 11175.37 |
| ===== | 210-02804 | Grinding: Sidwlk and/or Curb Ramp Repair | | Lin Foot | ===== | ===== | ===== |
| STM C440-013 | | R3 EAGLE RESIDENCY ADA RAMP I | 02/16/23 | 89.00 | 45.00 | 55.00 | 55.00 |
| | WEIGHTED | AVERAGE FOR THE FIRST QUARTER | | 89.00 | 45.00 | 55.00 | 55.00 |
| | | WEIGHTED AVERAGE FOR THE YEAR | | 89.00 | 45.00 | 55.00 | 55.00 |

| PROJECT NUMBER | ITEM NUMBER/ PROJECT LOCATION | ITEM DESCRIPTION/ PROJECT LOCATION | DATE LET | UNIT/ QUANTITY | ENGR. EST. | AVERAGE BID | AWARDED BID |
|-----------------|--|---------------------------------------|----------|-------------------|------------|-------------|-------------|
| ===== 210-04010 | | Adj Manhole | | Each | | | |
| STA172A-022 | | SH 172 IGNACIO TO ELMORE'S CO | 01/12/23 | 5.00 | 1100.00 | 1813.43 | 1496.85 |
| NHPP0701-250 | | I-70B: DDI TO 24 RD, MAIN ST | 01/12/23 | 100.00 | 1300.00 | 1605.00 | 1110.00 |
| STA066A-008 | | SH 66 @ WCR 7 | 01/26/23 | 1.00 | 1000.00 | 2126.52 | 1718.67 |
| NHPP0253-296 | | I-25 @ LCR 16 (MP 253.8-254.5 | 02/07/23 | 2.00 | 1595.29 | 1706.96 | 1706.96 |
| STM C440-013 | | R3 EAGLE RESIDENCY ADA RAMP I | 02/16/23 | 2.00 | 2000.00 | 500.00 | 500.00 |
| C0881-036 | | R1 CURB RAMPS-SH88B & US285D | 02/16/23 | 5.00 | 1500.00 | 801.25 | 450.00 |
| | WEIGHTED AVERAGE FOR THE FIRST QUARTER | | | 115.00 | 1314.70 | 1548.98 | 1103.19 |
| | WEIGHTED AVERAGE FOR THE YEAR | | | 115.00 | 1314.70 | 1548.98 | 1103.19 |
| ===== 210-04020 | | Modify Inlet | | Each | | | |
| C0881-036 | | R1 CURB RAMPS-SH88B & US285D | 02/16/23 | 5.00 | 3500.00 | 8262.50 | 750.00 |
| NHPP0253-290 | | I25 @ 58TH AND 62ND | 03/02/23 | 1.00 | 3200.00 | 7177.90 | 3600.00 |
| | WEIGHTED AVERAGE FOR THE FIRST QUARTER | | | 6.00 | 3450.00 | 8121.03 | 1225.00 |
| | WEIGHTED AVERAGE FOR THE YEAR | | | 6.00 | 3450.00 | 8121.03 | 1225.00 |
| ===== 210-04050 | | Adj Valve Box | | Each | | | |
| STA172A-022 | | SH 172 IGNACIO TO ELMORE'S CO | 01/12/23 | 2.00 | 1200.00 | 1779.06 | 1478.11 |
| NHPP0701-250 | | I-70B: DDI TO 24 RD, MAIN ST | 01/12/23 | 104.00 | 500.00 | 522.00 | 544.00 |
| STM C440-013 | | R3 EAGLE RESIDENCY ADA RAMP I | 02/16/23 | 2.00 | 900.00 | 500.00 | 500.00 |
| C0881-036 | | R1 CURB RAMPS-SH88B & US285D | 02/16/23 | 7.00 | 700.00 | 576.25 | 500.00 |
| | WEIGHTED AVERAGE FOR THE FIRST QUARTER | | | 115.00 | 531.30 | 548.87 | 556.80 |
| | WEIGHTED AVERAGE FOR THE YEAR | | | 115.00 | 531.30 | 548.87 | 556.80 |
| ===== 211-00100 | | Drilling Hole | | Lin Foot | | | |
| FBR 0703-520 | | EISENHOWER-JOHNSON MEMORIAL T | 03/16/23 | 14,700.00 | 350.00 | 348.00 | 300.00 |
| | WEIGHTED AVERAGE FOR THE FIRST QUARTER | | | 14,700.00 | 350.00 | 348.00 | 300.00 |
| | WEIGHTED AVERAGE FOR THE YEAR | | | 14,700.00 | 350.00 | 348.00 | 300.00 |
| ===== 211-00116 | | 2 In Drilled Hole | | Lin Foot | | | |
| FBR 0703-520 | | EISENHOWER-JOHNSON MEMORIAL T | 03/16/23 | 2,205.00 | 350.00 | 1084.80 | 825.00 |
| | WEIGHTED AVERAGE FOR THE FIRST QUARTER | | | 2,205.00 | 350.00 | 1084.80 | 825.00 |
| | WEIGHTED AVERAGE FOR THE YEAR | | | 2,205.00 | 350.00 | 1084.80 | 825.00 |

| PROJECT NUMBER | ITEM NUMBER/ PROJECT LOCATION | ITEM DESCRIPTION/ PROJECT LOCATION | DATE LET | UNIT/ QUANTITY | ENGR. EST. | AVERAGE BID | AWARDED BID |
|----------------|----------------------------------|---------------------------------------|----------|-------------------|------------|-------------|-------------|
| ===== | 211-00224 | 3 In Core Drilled Hole | | Lin Foot | ===== | | |
| FBR 0703-520 | | EISENHOWER-JOHNSON MEMORIAL T | 03/16/23 | 1,838.00 | 1000.00 | 408.50 | 425.00 |
| | WEIGHTED | AVERAGE FOR THE FIRST QUARTER | | 1,838.00 | 1000.00 | 408.50 | 425.00 |
| | | WEIGHTED AVERAGE FOR THE YEAR | | 1,838.00 | 1000.00 | 408.50 | 425.00 |
| ===== | 211-01115 | Rock Reinf (No.10) | | Lin Foot | ===== | | |
| C133A-052 | | SH 133 ROCKFALL N OF MCCLURE | 02/16/23 | 360.00 | 140.00 | 239.08 | 260.00 |
| | WEIGHTED | AVERAGE FOR THE FIRST QUARTER | | 360.00 | 140.00 | 239.08 | 260.00 |
| | | WEIGHTED AVERAGE FOR THE YEAR | | 360.00 | 140.00 | 239.08 | 260.00 |
| ===== | 211-02210 | Pre Grouting | | Ton | ===== | | |
| FBR 0703-520 | | EISENHOWER-JOHNSON MEMORIAL T | 03/16/23 | 421.00 | 3000.00 | 6967.06 | 2175.00 |
| | WEIGHTED | AVERAGE FOR THE FIRST QUARTER | | 421.00 | 3000.00 | 6967.06 | 2175.00 |
| | | WEIGHTED AVERAGE FOR THE YEAR | | 421.00 | 3000.00 | 6967.06 | 2175.00 |
| ===== | 211-02232 | Grout Conn (Pre-Grout) | | Each | ===== | | |
| FBR 0703-520 | | EISENHOWER-JOHNSON MEMORIAL T | 03/16/23 | 2,205.00 | 3500.00 | 4801.50 | 3995.00 |
| | WEIGHTED | AVERAGE FOR THE FIRST QUARTER | | 2,205.00 | 3500.00 | 4801.50 | 3995.00 |
| | | WEIGHTED AVERAGE FOR THE YEAR | | 2,205.00 | 3500.00 | 4801.50 | 3995.00 |
| ===== | 211-02277 | Cement Grout (Voids) | | Cubic Yard | ===== | | |
| STA172A-022 | | SH 172 IGNACIO TO ELMORE'S CO | 01/12/23 | 5.00 | 1200.00 | 1851.30 | 1882.59 |
| C1601-084 | | US 160 SECTION3 PRIORITY CULV | 02/16/23 | 23.00 | 1000.00 | 1880.47 | 2100.00 |
| | WEIGHTED | AVERAGE FOR THE FIRST QUARTER | | 28.00 | 1035.71 | 1875.26 | 2061.18 |
| | | WEIGHTED AVERAGE FOR THE YEAR | | 28.00 | 1035.71 | 1875.26 | 2061.18 |

COLORADO DEPARTMENT OF TRANSPORTATION
ITEM UNIT COSTS BY PROJECTS -- 2023 COST DATA

12:26 Wednesday, May 17, 2023 36

| PROJECT NUMBER | ITEM NUMBER/ PROJECT LOCATION | ITEM DESCRIPTION/ PROJECT LOCATION | DATE LET | UNIT/ QUANTITY | ENGR. EST. | AVERAGE BID | AWARDED BID |
|----------------|----------------------------------|--|----------|-------------------|------------|-------------|-------------|
| ===== | 211-03005 | Dewatering | | LUMP SUM | ===== | | |
| C1601-084 | | US 160 SECTION3 PRIORITY CULV | 02/16/23 | 1.00 | 7000.00 | 9499.06 | 7100.00 |
| | | WEIGHTED AVERAGE FOR THE FIRST QUARTER | | 1.00 | 7000.00 | 9499.06 | 7100.00 |
| | | WEIGHTED AVERAGE FOR THE YEAR | | 1.00 | 7000.00 | 9499.06 | 7100.00 |
| ===== | 212-00006 | Seeding (Native) | | Acre | ===== | | |
| SFTYR200-277 | | REGION 2 WIDE, VARIOUS HWY & | 01/19/23 | 0.78 | 5000.00 | 10100.00 | 2200.00 |
| | | WEIGHTED AVERAGE FOR THE FIRST QUARTER | | 0.78 | 5000.00 | 10100.00 | 2200.00 |
| | | WEIGHTED AVERAGE FOR THE YEAR | | 0.78 | 5000.00 | 10100.00 | 2200.00 |
| ===== | 212-00700 | Organic Fertilizer | | Pound | ===== | | |
| STA172A-022 | | SH 172 IGNACIO TO ELMORE'S CO | 01/12/23 | 261.00 | 3.00 | 1.58 | 1.60 |
| NHPP0701-250 | | I-70B: DDI TO 24 RD, MAIN ST | 01/12/23 | 75.00 | 50.00 | 1.55 | 2.35 |
| FSA0853-123 | | US 85 AND WCR 66 LEFT TURN AC | 01/26/23 | 420.00 | 1.50 | 2.00 | 1.75 |
| STA066A-008 | | SH 66 @ WCR 7 | 01/26/23 | 150.00 | 10.00 | 7.02 | 5.75 |
| C0342-066 | | US 034A (MP 113-150) | 02/02/23 | 30.00 | 10.00 | 20.67 | 16.00 |
| C0703-498 | | EISENHOWER JOHNSON MEMORIAL T | 02/16/23 | 117.00 | 3.00 | 3.63 | 4.00 |
| C133A-052 | | SH 133 ROCKFALL N OF MCCLURE | 02/16/23 | 1,200.00 | 0.50 | 1.92 | 2.00 |
| C1601-084 | | US 160 SECTION3 PRIORITY CULV | 02/16/23 | 345.00 | 2.00 | 1.73 | 2.00 |
| C 1601-086 | | MAPLE & CHESTNUT SIGNALS AT I | 02/16/23 | 3.30 | 500.00 | 26.00 | 26.00 |
| NHPP0701-256 | | I-70B/31.5 RD MESA COUNTY | 02/16/23 | 50.00 | 3.00 | 15.00 | 10.00 |
| SHE067A-044 | | SH 67F M.P. 56.5-57.6 AND SH | 03/02/23 | 90.00 | 2.00 | 2.96 | 2.96 |
| STR194A-002 | | SH194A SUR. TREAT.& DRAI IMP | 03/09/23 | 400.00 | 1.90 | 4.00 | 4.00 |
| | | WEIGHTED AVERAGE FOR THE FIRST QUARTER | | 3,141.30 | 3.61 | 2.76 | 2.76 |
| | | WEIGHTED AVERAGE FOR THE YEAR | | 3,141.30 | 3.61 | 2.76 | 2.76 |
| ===== | 212-00701 | Compost (Mech App) | | Cubic Yard | ===== | | |
| FSA0853-123 | | US 85 AND WCR 66 LEFT TURN AC | 01/26/23 | 84.00 | 45.00 | 65.24 | 68.00 |
| STA066A-008 | | SH 66 @ WCR 7 | 01/26/23 | 25.00 | 70.00 | 66.38 | 77.79 |
| C0342-066 | | US 034A (MP 113-150) | 02/02/23 | 7.00 | 65.00 | 159.33 | 218.00 |
| C0703-498 | | EISENHOWER JOHNSON MEMORIAL T | 02/16/23 | 54.00 | 100.00 | 81.92 | 84.00 |
| C133A-052 | | SH 133 ROCKFALL N OF MCCLURE | 02/16/23 | 39.00 | 60.00 | 117.83 | 145.00 |

| PROJECT NUMBER | ITEM NUMBER/ PROJECT LOCATION | ITEM DESCRIPTION/ PROJECT LOCATION | DATE LET | UNIT/ QUANTITY | ENGR. EST. | AVERAGE BID | AWARDED BID |
|-----------------|--|---------------------------------------|----------|-------------------|------------|-------------|-------------|
| ===== 212-00701 | | Compost (Mech App) | | Cubic Yard | | | |
| STR194A-002 | | SH194A SUR. TREAT.& DRAI IMP | 03/09/23 | 52.00 | 52.00 | 115.00 | 130.00 |
| | WEIGHTED AVERAGE FOR THE FIRST QUARTER | | | 261.00 | 62.95 | 82.22 | 100.13 |
| | WEIGHTED AVERAGE FOR THE YEAR | | | 261.00 | 62.95 | 82.22 | 100.13 |
| ===== 212-00702 | | Bio Soil Amd (Hyd App) | | Pound | | | |
| NHPP0701-250 | | I-70B: DDI TO 24 RD, MAIN ST | 01/12/23 | 875.00 | 1.50 | 2.05 | 2.35 |
| C133A-052 | | SH 133 ROCKFALL N OF MCCLURE | 02/16/23 | 11,900.00 | 1.80 | 2.29 | 2.50 |
| NHPP0701-256 | | I-70B/31.5 RD MESA COUNTY | 02/16/23 | 590.00 | 2.00 | 11.50 | 3.00 |
| SHE067A-044 | | SH 67F M.P. 56.5-57.6 AND SH | 03/02/23 | 1,050.00 | 2.00 | 2.70 | 2.70 |
| STA257A-008 | | SH 257 WINDSOR RESURFACING | 03/30/23 | 1,050.00 | 3.00 | 1.65 | 1.40 |
| | WEIGHTED AVERAGE FOR THE FIRST QUARTER | | | 15,465.00 | 1.89 | 2.46 | 2.45 |
| | WEIGHTED AVERAGE FOR THE YEAR | | | 15,465.00 | 1.89 | 2.46 | 2.45 |
| ===== 212-00703 | | Humate | | Pound | | | |
| STA172A-022 | | SH 172 IGNACIO TO ELMORE'S CO | 01/12/23 | 130.50 | 3.50 | 2.84 | 2.87 |
| NHPP0701-250 | | I-70B: DDI TO 24 RD, MAIN ST | 01/12/23 | 50.00 | 50.00 | 1.23 | 1.70 |
| FSA0853-123 | | US 85 AND WCR 66 LEFT TURN AC | 01/26/23 | 105.00 | 7.00 | 3.53 | 2.50 |
| STA066A-008 | | SH 66 @ WCR 7 | 01/26/23 | 50.00 | 7.00 | 10.43 | 12.91 |
| C0342-066 | | US 034A (MP 113-150) | 02/02/23 | 15.00 | 10.00 | 47.00 | 58.00 |
| C0703-498 | | EISENHOWER JOHNSON MEMORIAL T | 02/16/23 | 59.00 | 4.00 | 5.11 | 5.00 |
| STA1381-011 | | SH 138 STERLING NORTH PART 2 | 02/16/23 | 3,555.00 | 2.50 | 2.40 | 2.40 |
| C133A-052 | | SH 133 ROCKFALL N OF MCCLURE | 02/16/23 | 680.00 | 0.70 | 2.22 | 2.50 |
| C1601-084 | | US 160 SECTION3 PRIORITY CULV | 02/16/23 | 172.00 | 5.00 | 2.80 | 3.00 |
| C 1601-086 | | MAPLE & CHESTNUT SIGNALS AT I | 02/16/23 | 1.65 | 200.00 | 52.00 | 52.00 |
| NHPP0701-256 | | I-70B/31.5 RD MESA COUNTY | 02/16/23 | 35.00 | 2.00 | 15.00 | 10.00 |
| SHE067A-044 | | SH 67F M.P. 56.5-57.6 AND SH | 03/02/23 | 60.00 | 2.00 | 2.84 | 2.84 |
| STR194A-002 | | SH194A SUR. TREAT.& DRAI IMP | 03/09/23 | 160.00 | 1.90 | 6.00 | 8.00 |
| STA257A-008 | | SH 257 WINDSOR RESURFACING | 03/30/23 | 45.00 | 3.00 | 2.45 | 3.50 |
| | WEIGHTED AVERAGE FOR THE FIRST QUARTER | | | 5,118.15 | 3.05 | 3.21 | 2.99 |
| | WEIGHTED AVERAGE FOR THE YEAR | | | 5,118.15 | 3.05 | 3.21 | 2.99 |
| ===== 212-00704 | | Mycorrhizae | | Pound | | | |
| STA172A-022 | | SH 172 IGNACIO TO ELMORE'S CO | 01/12/23 | 17.40 | 36.00 | 23.57 | 23.93 |

| PROJECT NUMBER | ITEM NUMBER/ PROJECT LOCATION | ITEM DESCRIPTION/ PROJECT LOCATION | DATE LET | UNIT/ QUANTITY | ENGR. EST. | AVERAGE BID | AWARDED BID |
|-----------------|--|---------------------------------------|----------|-------------------|------------|-------------|-------------|
| ===== 212-00704 | | Mycorrhizae | | Pound | ===== | ===== | ===== |
| FSA0853-123 | US 85 AND WCR 66 LEFT TURN AC | 01/26/23 | 14.00 | 22.00 | 41.17 | 35.00 | |
| STA066A-008 | SH 66 @ WCR 7 | 01/26/23 | 8.00 | 50.00 | 73.06 | 86.37 | |
| C0342-066 | US 034A (MP 113-150) | 02/02/23 | 2.00 | 25.00 | 265.00 | 280.00 | |
| C0703-498 | EISENHOWER JOHNSON MEMORIAL T | 02/16/23 | 8.00 | 50.00 | 69.24 | 75.00 | |
| STA1381-011 | SH 138 STERLING NORTH PART 2 | 02/16/23 | 190.00 | 25.00 | 22.00 | 22.00 | |
| C1601-084 | US 160 SECTION3 PRIORITY CULV | 02/16/23 | 23.00 | 30.00 | 31.05 | 31.00 | |
| C 1601-086 | MAPLE & CHESTNUT SIGNALS AT I | 02/16/23 | 0.66 | 200.00 | 130.00 | 130.00 | |
| STR194A-002 | SH194A SUR. TREAT.& DRAI IMP | 03/09/23 | 16.00 | 22.00 | 45.00 | 60.00 | |
| STA257A-008 | SH 257 WINDSOR RESURFACING | 03/30/23 | 6.00 | 30.00 | 47.08 | 46.00 | |
| | WEIGHTED AVERAGE FOR THE FIRST QUARTER | | 285.06 | 27.67 | 38.66 | 31.47 | |
| | WEIGHTED AVERAGE FOR THE YEAR | | 285.06 | 27.67 | 38.66 | 31.47 | |
| ===== 212-00705 | | Elemental Sulfur | | Pound | ===== | ===== | ===== |
| STA172A-022 | SH 172 IGNACIO TO ELMORE'S CO | 01/12/23 | 52.20 | 4.00 | 3.97 | 4.04 | |
| C1601-084 | US 160 SECTION3 PRIORITY CULV | 02/16/23 | 69.00 | 8.75 | 6.07 | 6.00 | |
| C 1601-086 | MAPLE & CHESTNUT SIGNALS AT I | 02/16/23 | 0.66 | 100.00 | 130.00 | 130.00 | |
| | WEIGHTED AVERAGE FOR THE FIRST QUARTER | | 121.86 | 7.21 | 5.50 | 5.83 | |
| | WEIGHTED AVERAGE FOR THE YEAR | | 121.86 | 7.21 | 5.50 | 5.83 | |
| ===== 212-00706 | | Seed (Native) Drill | | Acre | ===== | ===== | ===== |
| STA1381-011 | SH 138 STERLING NORTH PART 2 | 02/16/23 | 23.70 | 2300.00 | 1275.00 | 1275.00 | |
| C133A-052 | SH 133 ROCKFALL N OF MCCLURE | 02/16/23 | 0.60 | 2000.00 | 2156.25 | 3900.00 | |
| | WEIGHTED AVERAGE FOR THE FIRST QUARTER | | 24.30 | 2292.59 | 1356.03 | 1339.81 | |
| | WEIGHTED AVERAGE FOR THE YEAR | | 24.30 | 2292.59 | 1356.03 | 1339.81 | |
| ===== 212-00707 | | Seed (Native) Hyd) | | Acre | ===== | ===== | ===== |
| NHPP0701-250 | I-70B: DDI TO 24 RD, MAIN ST | 01/12/23 | 0.30 | 3000.00 | 4565.00 | 5880.00 | |
| C133A-052 | SH 133 ROCKFALL N OF MCCLURE | 02/16/23 | 3.40 | 4000.00 | 2912.19 | 4100.00 | |
| SHE067A-044 | SH 67F M.P. 56.5-57.6 AND SH | 03/02/23 | 0.35 | 2000.00 | 5173.40 | 5173.40 | |
| STA257A-008 | SH 257 WINDSOR RESURFACING | 03/30/23 | 0.30 | 2000.00 | 3350.00 | 4200.00 | |
| | WEIGHTED AVERAGE FOR THE FIRST QUARTER | | 4.35 | 3632.18 | 3047.22 | 4316.02 | |
| | WEIGHTED AVERAGE FOR THE YEAR | | 4.35 | 3632.18 | 3047.22 | 4316.02 | |

| PROJECT NUMBER | ITEM NUMBER/ PROJECT LOCATION | ITEM DESCRIPTION/ PROJECT LOCATION | DATE LET | UNIT/ QUANTITY | ENGR. EST. | AVERAGE BID | AWARDED BID |
|-----------------|----------------------------------|--|----------|-------------------|------------|-------------|-------------|
| ===== 212-00708 | | Seed (Native) Brdcst | | Acre | ===== | | |
| STA172A-022 | | SH 172 IGNACIO TO ELMORE'S CO | 01/12/23 | 0.87 | 3000.00 | 956.99 | 972.98 |
| FSA0853-123 | | US 85 AND WCR 66 LEFT TURN AC | 01/26/23 | 0.70 | 4000.00 | 2170.83 | 2600.00 |
| STA066A-008 | | SH 66 @ WCR 7 | 01/26/23 | 0.37 | 3500.00 | 5800.04 | 5160.32 |
| C0342-066 | | US 034A (MP 113-150) | 02/02/23 | 0.10 | 3500.00 | 9420.00 | 13120.00 |
| C0703-498 | | EISENHOWER JOHNSON MEMORIAL T | 02/16/23 | 0.40 | 4000.00 | 4321.10 | 4800.00 |
| C1601-084 | | US 160 SECTION3 PRIORITY CULV | 02/16/23 | 1.15 | 2000.00 | 1078.57 | 1100.00 |
| C 1601-086 | | MAPLE & CHESTNUT SIGNALS AT I | 02/16/23 | 0.01 | 5000.00 | 14000.00 | 14000.00 |
| NHPP0701-256 | | I-70B/31.5 RD MESA COUNTY | 02/16/23 | 0.20 | 5000.00 | 8250.00 | 6500.00 |
| STR194A-002 | | SH194A SUR. TREAT.& DRAI IMP | 03/09/23 | 0.80 | 3100.00 | 4875.00 | 4750.00 |
| NHPP R100-376 | | VARIOUS LOCATIONS IN REGION 1 | 03/30/23 | 0.14 | 3635.00 | 9275.50 | 11900.00 |
| | | WEIGHTED AVERAGE FOR THE FIRST QUARTER | | 4.74 | 3163.66 | 3303.50 | 3373.30 |
| | | WEIGHTED AVERAGE FOR THE YEAR | | 4.74 | 3163.66 | 3303.50 | 3373.30 |
| ===== 212-00711 | | Seeding (Wetland) Broadcast | | Acre | ===== | | |
| STA172A-022 | | SH 172 IGNACIO TO ELMORE'S CO | 01/12/23 | 0.17 | 3000.00 | 2999.87 | 3049.74 |
| C1601-084 | | US 160 SECTION3 PRIORITY CULV | 02/16/23 | 0.12 | 2500.00 | 2517.42 | 2500.00 |
| STA257A-008 | | SH 257 WINDSOR RESURFACING | 03/30/23 | 0.02 | 10000.00 | 10400.00 | 16000.00 |
| | | WEIGHTED AVERAGE FOR THE FIRST QUARTER | | 0.31 | 11967.74 | 3290.54 | 3672.44 |
| | | WEIGHTED AVERAGE FOR THE YEAR | | 0.31 | 11967.74 | 3290.54 | 3672.44 |
| ===== 213-00002 | | Mulching (Weed Free Hay) | | Acre | ===== | | |
| NHPP R100-376 | | VARIOUS LOCATIONS IN REGION 1 | 03/30/23 | 0.14 | 5500.00 | 18357.93 | 24600.00 |
| | | WEIGHTED AVERAGE FOR THE FIRST QUARTER | | 0.14 | 5500.00 | 18357.93 | 24600.00 |
| | | WEIGHTED AVERAGE FOR THE YEAR | | 0.14 | 5500.00 | 18357.93 | 24600.00 |
| ===== 213-00003 | | Mulching (Weed Free) | | Acre | ===== | | |
| STA172A-022 | | SH 172 IGNACIO TO ELMORE'S CO | 01/12/23 | 1.04 | 1100.00 | 1717.50 | 1744.99 |
| SFTYR200-277 | | REGION 2 WIDE, VARIOUS HWY & | 01/19/23 | 0.78 | 3000.00 | 4250.00 | 4500.00 |
| C1601-084 | | US 160 SECTION3 PRIORITY CULV | 02/16/23 | 1.15 | 2500.00 | 4987.35 | 5000.00 |
| C 1601-086 | | MAPLE & CHESTNUT SIGNALS AT I | 02/16/23 | 0.01 | 4000.00 | 13000.00 | 13000.00 |
| STR194A-002 | | SH194A SUR. TREAT.& DRAI IMP | 03/09/23 | 0.80 | 2000.00 | 3137.50 | 4275.00 |
| | | WEIGHTED AVERAGE FOR THE FIRST QUARTER | | 3.78 | 2116.64 | 3554.00 | 3871.41 |
| | | WEIGHTED AVERAGE FOR THE YEAR | | 3.78 | 2116.64 | 3554.00 | 3871.41 |

| PROJECT NUMBER | ITEM NUMBER/ PROJECT LOCATION | ITEM DESCRIPTION/ PROJECT LOCATION | DATE LET | UNIT/ QUANTITY | ENGR. EST. | AVERAGE BID | AWARDED BID |
|-----------------|--|---------------------------------------|----------|-------------------|------------|-------------|-------------|
| ===== 213-00004 | | Mulching (Weed Free Straw) | | Acre | ===== | | |
| STA1381-011 | | SH 138 STERLING NORTH PART 2 | 02/16/23 | 23.70 | 950.00 | 905.00 | 905.00 |
| C133A-052 | | SH 133 ROCKFALL N OF MCCLURE | 02/16/23 | 0.60 | 3200.00 | 2150.00 | 3700.00 |
| | WEIGHTED AVERAGE FOR THE FIRST QUARTER | | | 24.30 | 1005.56 | 1019.48 | 974.01 |
| | WEIGHTED AVERAGE FOR THE YEAR | | | 24.30 | 1005.56 | 1019.48 | 974.01 |
| ===== 213-00012 | | Spray-on Mulch Blanket | | Acre | ===== | | |
| NHPP0701-250 | | I-70B: DDI TO 24 RD, MAIN ST | 01/12/23 | 0.30 | 10000.00 | 7745.00 | 9990.00 |
| C0342-066 | | US 034A (MP 113-150) | 02/02/23 | 0.10 | 4000.00 | 14041.67 | 16255.00 |
| C133A-052 | | SH 133 ROCKFALL N OF MCCLURE | 02/16/23 | 3.40 | 7000.00 | 6486.67 | 7800.00 |
| C1601-084 | | US 160 SECTION3 PRIORITY CULV | 02/16/23 | 1.15 | 5500.00 | 7584.66 | 7600.00 |
| NHPP0701-256 | | I-70B/31.5 RD MESA COUNTY | 02/16/23 | 0.20 | 10000.00 | 12400.00 | 9800.00 |
| SHE067A-044 | | SH 67F M.P. 56.5-57.6 AND SH | 03/02/23 | 0.25 | 15000.00 | 6232.72 | 6232.72 |
| | WEIGHTED AVERAGE FOR THE FIRST QUARTER | | | 5.40 | 7273.15 | 6936.45 | 8037.16 |
| | WEIGHTED AVERAGE FOR THE YEAR | | | 5.40 | 7273.15 | 6936.45 | 8037.16 |
| ===== 213-00013 | | Spray-on Mulch Blanket | | Pound | ===== | | |
| SHE067A-044 | | SH 67F M.P. 56.5-57.6 AND SH | 03/02/23 | 150.00 | 16.00 | 3.88 | 3.88 |
| | WEIGHTED AVERAGE FOR THE FIRST QUARTER | | | 150.00 | 16.00 | 3.88 | 3.88 |
| | WEIGHTED AVERAGE FOR THE YEAR | | | 150.00 | 16.00 | 3.88 | 3.88 |
| ===== 213-00061 | | Mulch Tackifier | | Pound | ===== | | |
| STA172A-022 | | SH 172 IGNACIO TO ELMORE'S CO | 01/12/23 | 150.00 | 7.00 | 7.01 | 7.12 |
| STA1381-011 | | SH 138 STERLING NORTH PART 2 | 02/16/23 | 4,740.00 | 4.00 | 3.85 | 3.85 |
| C133A-052 | | SH 133 ROCKFALL N OF MCCLURE | 02/16/23 | 120.00 | 10.00 | 5.38 | 8.00 |
| C 1601-086 | | MAPLE & CHESTNUT SIGNALS AT I | 02/16/23 | 2.80 | 20.00 | 31.00 | 31.00 |
| NHPP R100-376 | | VARIOUS LOCATIONS IN REGION 1 | 03/30/23 | 28.00 | 10.00 | 44.40 | 71.00 |
| | WEIGHTED AVERAGE FOR THE FIRST QUARTER | | | 5,040.80 | 4.27 | 4.57 | 4.43 |
| | WEIGHTED AVERAGE FOR THE YEAR | | | 5,040.80 | 4.27 | 4.57 | 4.43 |
| ===== 213-00067 | | Rock Mulch (Weed Free) | | Sq Foot | ===== | | |
| STM C440-013 | | R3 EAGLE RESIDENCY ADA RAMP I | 02/16/23 | 29.00 | 20.00 | 5.00 | 5.00 |
| | WEIGHTED AVERAGE FOR THE FIRST QUARTER | | | 29.00 | 20.00 | 5.00 | 5.00 |
| | WEIGHTED AVERAGE FOR THE YEAR | | | 29.00 | 20.00 | 5.00 | 5.00 |

| PROJECT NUMBER | ITEM NUMBER/ PROJECT LOCATION | ITEM DESCRIPTION/ PROJECT LOCATION | DATE LET | UNIT/ QUANTITY | ENGR. EST. | AVERAGE BID | AWARDED BID |
|-----------------|----------------------------------|---------------------------------------|----------|-------------------|------------|-------------|-------------|
| ===== 213-00070 | | Landscape Weed Barr Fabric | | Sq Yard | ===== | ===== | ===== |
| NHPP0253-296 | | I-25 @ LCR 16 (MP 253.8-254.5 | 02/07/23 | 1,850.00 | 2.66 | 2.85 | 2.85 |
| | WEIGHTED | AVERAGE FOR THE FIRST QUARTER | | 1,850.00 | 2.66 | 2.85 | 2.85 |
| | | WEIGHTED AVERAGE FOR THE YEAR | | 1,850.00 | 2.66 | 2.85 | 2.85 |
| ===== 213-00150 | | Bonded Fiber Matrix | | Acre | ===== | ===== | ===== |
| STA066A-008 | | SH 66 @ WCR 7 | 01/26/23 | 0.20 | 5000.00 | 9733.68 | 7463.25 |
| STA1381-011 | | SH 138 STERLING NORTH PART 2 | 02/16/23 | 15.00 | 3800.00 | 3900.00 | 3900.00 |
| STA257A-008 | | SH 257 WINDSOR RESURFACING | 03/30/23 | 1.00 | 3500.00 | 4700.00 | 4200.00 |
| | WEIGHTED | AVERAGE FOR THE FIRST QUARTER | | 16.20 | 3796.30 | 4312.98 | 3962.51 |
| | | WEIGHTED AVERAGE FOR THE YEAR | | 16.20 | 3796.30 | 4312.98 | 3962.51 |
| ===== 214-00506 | | Evergreen Tree (6 Ft)(B-B) | | Each | ===== | ===== | ===== |
| SHE067A-044 | | SH 67F M.P. 56.5-57.6 AND SH | 03/02/23 | 5.00 | 1000.00 | 994.06 | 994.06 |
| | WEIGHTED | AVERAGE FOR THE FIRST QUARTER | | 5.00 | 1000.00 | 994.06 | 994.06 |
| | | WEIGHTED AVERAGE FOR THE YEAR | | 5.00 | 1000.00 | 994.06 | 994.06 |
| ===== 214-01010 | | Brush Layer Cutting | | Each | ===== | ===== | ===== |
| STA172A-022 | | SH 172 IGNACIO TO ELMORE'S CO | 01/12/23 | 170.00 | 15.00 | 9.98 | 10.16 |
| C1601-084 | | US 160 SECTION3 PRIORITY CULV | 02/16/23 | 415.00 | 20.00 | 16.34 | 16.00 |
| | WEIGHTED | AVERAGE FOR THE FIRST QUARTER | | 585.00 | 18.55 | 14.49 | 14.30 |
| | | WEIGHTED AVERAGE FOR THE YEAR | | 585.00 | 18.55 | 14.49 | 14.30 |
| ===== 216-00021 | | Soil Reten Blanket (C1 1) | | Sq Yard | ===== | ===== | ===== |
| STA172A-022 | | SH 172 IGNACIO TO ELMORE'S CO | 01/12/23 | 1,247.00 | 5.00 | 3.92 | 3.99 |
| | WEIGHTED | AVERAGE FOR THE FIRST QUARTER | | 1,247.00 | 5.00 | 3.92 | 3.99 |
| | | WEIGHTED AVERAGE FOR THE YEAR | | 1,247.00 | 5.00 | 3.92 | 3.99 |

COLORADO DEPARTMENT OF TRANSPORTATION
ITEM UNIT COSTS BY PROJECTS -- 2023 COST DATA

12:26 Wednesday, May 17, 2023 42

| PROJECT NUMBER | ITEM NUMBER/ PROJECT LOCATION | ITEM DESCRIPTION/ PROJECT LOCATION | DATE LET | UNIT/ QUANTITY | ENGR. EST. | AVERAGE BID | AWARDED BID |
|-----------------|----------------------------------|--|----------|-------------------|------------|-------------|-------------|
| ===== 216-00101 | | Soil Reten Blanket (S-C) (PhotoD Cl 1) | | Sq Yard | ===== | ===== | ===== |
| C0703-498 | | EISENHOWER JOHNSON MEMORIAL T | 02/16/23 | 1,888.00 | 5.00 | 3.73 | 4.00 |
| | WEIGHTED | AVERAGE FOR THE FIRST QUARTER | | 1,888.00 | 5.00 | 3.73 | 4.00 |
| | | WEIGHTED AVERAGE FOR THE YEAR | | 1,888.00 | 5.00 | 3.73 | 4.00 |
| ===== 216-00201 | | Soil Reten Blanket (S-C) (BioD Cl 1) | | Sq Yard | ===== | ===== | ===== |
| SFTYR200-277 | | REGION 2 WIDE, VARIOUS HWY & | 01/19/23 | 1,000.00 | 4.00 | 9.00 | 8.00 |
| STA066A-008 | | SH 66 @ WCR 7 | 01/26/23 | 1,790.00 | 3.50 | 4.09 | 4.14 |
| STR194A-002 | | SH194A SUR. TREAT.& DRAI IMP | 03/09/23 | 5,184.00 | 3.30 | 3.68 | 3.35 |
| STA257A-008 | | SH 257 WINDSOR RESURFACING | 03/30/23 | 1,460.00 | 3.00 | 3.08 | 3.25 |
| | WEIGHTED | AVERAGE FOR THE FIRST QUARTER | | 9,434.00 | 3.37 | 4.20 | 3.98 |
| | | WEIGHTED AVERAGE FOR THE YEAR | | 9,434.00 | 3.37 | 4.20 | 3.98 |
| ===== 216-00211 | | Soil Reten Blanket (Exc) (BioD Cl 1) | | Sq Yard | ===== | ===== | ===== |
| FSA0853-123 | | US 85 AND WCR 66 LEFT TURN AC | 01/26/23 | 3,388.00 | 3.00 | 4.14 | 3.50 |
| | WEIGHTED | AVERAGE FOR THE FIRST QUARTER | | 3,388.00 | 3.00 | 4.14 | 3.50 |
| | | WEIGHTED AVERAGE FOR THE YEAR | | 3,388.00 | 3.00 | 4.14 | 3.50 |
| ===== 217-00020 | | Herbicide Treatment | | Hour | ===== | ===== | ===== |
| FSA0853-123 | | US 85 AND WCR 66 LEFT TURN AC | 01/26/23 | 16.00 | 250.00 | 157.33 | 95.00 |
| STA066A-008 | | SH 66 @ WCR 7 | 01/26/23 | 24.00 | 130.00 | 159.96 | 106.77 |
| C0703-498 | | EISENHOWER JOHNSON MEMORIAL T | 02/16/23 | 4.00 | 250.00 | 204.82 | 240.00 |
| STA1381-011 | | SH 138 STERLING NORTH PART 2 | 02/16/23 | 10.00 | 200.00 | 650.00 | 650.00 |
| NHPP0701-256 | | I-70B/31.5 RD MESA COUNTY | 02/16/23 | 8.00 | 200.00 | 70.00 | 100.00 |
| C0881-036 | | R1 CURB RAMPS-SH88B & US285D | 02/16/23 | 24.00 | 110.00 | 171.25 | 20.00 |
| SHE067A-044 | | SH 67F M.P. 56.5-57.6 AND SH | 03/02/23 | 40.00 | 200.00 | 142.56 | 142.56 |
| STA257A-008 | | SH 257 WINDSOR RESURFACING | 03/30/23 | 10.00 | 200.00 | 212.50 | 105.00 |
| | WEIGHTED | AVERAGE FOR THE FIRST QUARTER | | 136.00 | 179.12 | 172.61 | 143.93 |
| | | WEIGHTED AVERAGE FOR THE YEAR | | 136.00 | 179.12 | 172.61 | 143.93 |
| ===== 240-00000 | | Wildlife Biologist | | Hour | ===== | ===== | ===== |
| STA172A-022 | | SH 172 IGNACIO TO ELMORE'S CO | 01/12/23 | 20.00 | 150.00 | 150.56 | 153.12 |

| PROJECT NUMBER | ITEM NUMBER/ PROJECT LOCATION | ITEM DESCRIPTION/ PROJECT LOCATION | DATE LET | UNIT/ QUANTITY | ENGR. EST. | AVERAGE BID | AWARDED BID |
|-----------------|--|---------------------------------------|----------|-------------------|------------|-------------|-------------|
| ===== 240-00000 | | Wildlife Biologist | | Hour ===== | | | |
| NHPPR100-383 | | I70 OVER WASHINGTON ST | 01/26/23 | 40.00 | 125.00 | 112.03 | 106.00 |
| C133A-052 | | SH 133 ROCKFALL N OF MCCLURE | 02/16/23 | 40.00 | 130.00 | 205.06 | 320.00 |
| C1601-084 | | US 160 SECTION3 PRIORITY CULV | 02/16/23 | 20.00 | 140.00 | 171.43 | 150.00 |
| C 1601-086 | | MAPLE & CHESTNUT SIGNALS AT I | 02/16/23 | 20.00 | 200.00 | 160.00 | 160.00 |
| NHPP0253-290 | | I25 @ 58TH AND 62ND | 03/02/23 | 80.00 | 125.00 | 93.03 | 104.00 |
| NHPP R100-376 | | VARIOUS LOCATIONS IN REGION 1 | 03/30/23 | 16.00 | 140.00 | 368.73 | 550.00 |
| | WEIGHTED AVERAGE FOR THE FIRST QUARTER | | | 236.00 | 136.61 | 147.95 | 183.99 |
| | WEIGHTED AVERAGE FOR THE YEAR | | | 236.00 | 136.61 | 147.95 | 183.99 |
| ===== 240-00010 | | Rem of Nests | | Hour ===== | | | |
| NHPPR100-383 | | I70 OVER WASHINGTON ST | 01/26/23 | 40.00 | 100.00 | 197.01 | 205.00 |
| STA066A-008 | | SH 66 @ WCR 7 | 01/26/23 | 10.00 | 150.00 | 131.85 | 100.84 |
| STA1381-011 | | SH 138 STERLING NORTH PART 2 | 02/16/23 | 20.00 | 150.00 | 135.00 | 135.00 |
| NHPP0253-290 | | I25 @ 58TH AND 62ND | 03/02/23 | 80.00 | 80.00 | 265.19 | 175.00 |
| SHE067A-044 | | SH 67F M.P. 56.5-57.6 AND SH | 03/02/23 | 10.00 | 150.00 | 154.44 | 154.44 |
| STA257A-008 | | SH 257 WINDSOR RESURFACING | 03/30/23 | 20.00 | 50.00 | 135.00 | 95.00 |
| | WEIGHTED AVERAGE FOR THE FIRST QUARTER | | | 180.00 | 96.67 | 215.67 | 163.07 |
| | WEIGHTED AVERAGE FOR THE YEAR | | | 180.00 | 96.67 | 215.67 | 163.07 |
| ===== 240-00020 | | Netting | | Sq Yard ===== | | | |
| STA1381-011 | | SH 138 STERLING NORTH PART 2 | 02/16/23 | 200.00 | 10.00 | 11.00 | 11.00 |
| STA257A-008 | | SH 257 WINDSOR RESURFACING | 03/30/23 | 300.00 | 10.00 | 16.75 | 19.00 |
| | WEIGHTED AVERAGE FOR THE FIRST QUARTER | | | 500.00 | 10.00 | 15.31 | 15.80 |
| | WEIGHTED AVERAGE FOR THE YEAR | | | 500.00 | 10.00 | 15.31 | 15.80 |
| ===== 240-00100 | | Prairie Dog Mgmt | | LUMP SUM ===== | | | |
| SHE067A-044 | | SH 67F M.P. 56.5-57.6 AND SH | 03/02/23 | 1.00 | 10000.00 | 13068.00 | 13068.00 |
| | WEIGHTED AVERAGE FOR THE FIRST QUARTER | | | 1.00 | 10000.00 | 13068.00 | 13068.00 |
| | WEIGHTED AVERAGE FOR THE YEAR | | | 1.00 | 10000.00 | 13068.00 | 13068.00 |
| ===== 250-00010 | | Envir Health/Safety Mngmt | | LUMP SUM ===== | | | |
| STA172A-022 | | SH 172 IGNACIO TO ELMORE'S CO | 01/12/23 | 1.00 | 10000.00 | 9243.42 | 5316.84 |

COLORADO DEPARTMENT OF TRANSPORTATION
ITEM UNIT COSTS BY PROJECTS -- 2023 COST DATA

12:26 Wednesday, May 17, 2023 44

| PROJECT NUMBER | ITEM NUMBER/ PROJECT LOCATION | ITEM DESCRIPTION/ PROJECT LOCATION | DATE LET | UNIT/ QUANTITY | ENGR. EST. | AVERAGE BID | AWARDED BID |
|----------------|--|---------------------------------------|----------|-------------------|------------|-------------|-------------|
| ===== | 250-00010 | Envir Health/Safety Mngmt | | LUMP SUM | ===== | ===== | ===== |
| FBR 0703-520 | | EISENHOWER-JOHNSON MEMORIAL T | 03/16/23 | 1.00 | 1500000.00 | 2510000.00 | 2000000.00 |
| NHPP R100-376 | | VARIOUS LOCATIONS IN REGION 1 | 03/30/23 | 1.00 | 10000.00 | 56374.41 | 39700.00 |
| | WEIGHTED AVERAGE FOR THE FIRST QUARTER | | | 3.00 | 506666.67 | 858539.28 | 681672.28 |
| | WEIGHTED AVERAGE FOR THE YEAR | | | 3.00 | 506666.67 | 858539.28 | 681672.28 |
| ===== | 250-00050 | Monitoring Technician | | Hour | ===== | ===== | ===== |
| FBR 0703-520 | | EISENHOWER-JOHNSON MEMORIAL T | 03/16/23 | 200.00 | 150.00 | 205.00 | 300.00 |
| | WEIGHTED AVERAGE FOR THE FIRST QUARTER | | | 200.00 | 150.00 | 205.00 | 300.00 |
| | WEIGHTED AVERAGE FOR THE YEAR | | | 200.00 | 150.00 | 205.00 | 300.00 |
| ===== | 250-00110 | Health and Safety Officer | | Hour | ===== | ===== | ===== |
| FBR 0703-520 | | EISENHOWER-JOHNSON MEMORIAL T | 03/16/23 | 100.00 | 200.00 | 535.00 | 250.00 |
| | WEIGHTED AVERAGE FOR THE FIRST QUARTER | | | 100.00 | 200.00 | 535.00 | 250.00 |
| | WEIGHTED AVERAGE FOR THE YEAR | | | 100.00 | 200.00 | 535.00 | 250.00 |
| ===== | 250-10005 | Custom Fire Extinguisher Cab | | Each | ===== | ===== | ===== |
| C0703-498 | | EISENHOWER JOHNSON MEMORIAL T | 02/16/23 | 68.00 | 180.00 | 1524.00 | 1400.00 |
| | WEIGHTED AVERAGE FOR THE FIRST QUARTER | | | 68.00 | 180.00 | 1524.00 | 1400.00 |
| | WEIGHTED AVERAGE FOR THE YEAR | | | 68.00 | 180.00 | 1524.00 | 1400.00 |
| ===== | 250-10021 | Fire Preempt Unit + Timer | | Each | ===== | ===== | ===== |
| C 1601-086 | | MAPLE & CHESTNUT SIGNALS AT I | 02/16/23 | 4.00 | 7500.00 | 5200.00 | 5200.00 |
| | WEIGHTED AVERAGE FOR THE FIRST QUARTER | | | 4.00 | 7500.00 | 5200.00 | 5200.00 |
| | WEIGHTED AVERAGE FOR THE YEAR | | | 4.00 | 7500.00 | 5200.00 | 5200.00 |
| ===== | 304-01000 | ABC (CL 1) | | Ton | ===== | ===== | ===== |
| NHPP0701-256 | | I-70B/31.5 RD MESA COUNTY | 02/16/23 | 363.00 | 40.00 | 46.00 | 34.00 |
| | WEIGHTED AVERAGE FOR THE FIRST QUARTER | | | 363.00 | 40.00 | 46.00 | 34.00 |
| | WEIGHTED AVERAGE FOR THE YEAR | | | 363.00 | 40.00 | 46.00 | 34.00 |

COLORADO DEPARTMENT OF TRANSPORTATION
ITEM UNIT COSTS BY PROJECTS -- 2023 COST DATA

12:26 Wednesday, May 17, 2023 45

| PROJECT NUMBER | ITEM NUMBER/ PROJECT LOCATION | ITEM DESCRIPTION/ PROJECT LOCATION | DATE LET | UNIT/ QUANTITY | ENGR. EST. | AVERAGE BID | AWARDED BID |
|----------------|--|---------------------------------------|----------|-------------------|------------|-------------|-------------|
| ===== | 304-03005 | ABC (CL 3) | | Cubic Yard | ===== | | |
| NHPP0701-250 | | I-70B: DDI TO 24 RD, MAIN ST | 01/12/23 | 819.00 | 50.00 | 109.00 | 126.00 |
| | WEIGHTED AVERAGE FOR THE FIRST QUARTER | | | 819.00 | 50.00 | 109.00 | 126.00 |
| | WEIGHTED AVERAGE FOR THE YEAR | | | 819.00 | 50.00 | 109.00 | 126.00 |
| ===== | 304-06000 | ABC (CL 6) | | Ton | ===== | | |
| STA172A-022 | | SH 172 IGNACIO TO ELMORE'S CO | 01/12/23 | 2,684.00 | 50.00 | 98.27 | 87.54 |
| SFTYR200-277 | | REGION 2 WIDE, VARIOUS HWY & | 01/19/23 | 120.00 | 300.00 | 67.50 | 65.00 |
| C1601-084 | | US 160 SECTION3 PRIORITY CULV | 02/16/23 | 51.00 | 130.00 | 229.04 | 120.00 |
| NHPP0701-256 | | I-70B/31.5 RD MESA COUNTY | 02/16/23 | 284.00 | 50.00 | 49.50 | 38.00 |
| C0881-036 | | R1 CURB RAMPS-SH88B & US285D | 02/16/23 | 209.00 | 45.00 | 67.50 | 35.00 |
| NHPP0253-290 | | I25 @ 58TH AND 62ND | 03/02/23 | 50.00 | 85.00 | 126.68 | 100.00 |
| SHE067A-044 | | SH 67F M.P. 56.5-57.6 AND SH | 03/02/23 | 937.00 | 50.00 | 36.28 | 36.28 |
| NHPP R100-376 | | VARIOUS LOCATIONS IN REGION 1 | 03/30/23 | 50.00 | 32.00 | 285.25 | 170.00 |
| | WEIGHTED AVERAGE FOR THE FIRST QUARTER | | | 4,385.00 | 57.73 | 88.32 | 71.72 |
| | WEIGHTED AVERAGE FOR THE YEAR | | | 4,385.00 | 57.73 | 88.32 | 71.72 |
| ===== | 304-06007 | ABC (CL 6) | | Cubic Yard | ===== | | |
| NHPP0701-250 | | I-70B: DDI TO 24 RD, MAIN ST | 01/12/23 | 273.00 | 70.00 | 142.00 | 190.00 |
| STR2871-040 | | US 287 MP 0.0 TO MP 122 VARIO | 01/12/23 | 138.00 | 90.00 | 324.66 | 250.61 |
| FSA0853-123 | | US 85 AND WCR 66 LEFT TURN AC | 01/26/23 | 1,137.00 | 55.00 | 63.75 | 59.00 |
| NHPPR100-383 | | I70 OVER WASHINGTON ST | 01/26/23 | 32.00 | 100.00 | 205.38 | 170.00 |
| STA066A-008 | | SH 66 @ WCR 7 | 01/26/23 | 53.00 | 125.00 | 172.94 | 130.00 |
| NHPP0253-296 | | I-25 @ LCR 16 (MP 253.8-254.5) | 02/07/23 | 3,342.00 | 51.00 | 54.57 | 54.57 |
| STA1381-011 | | SH 138 STERLING NORTH PART 2 | 02/16/23 | 7,784.00 | 95.00 | 104.00 | 104.00 |
| STM C440-013 | | R3 EAGLE RESIDENCY ADA RAMP I | 02/16/23 | 300.00 | 90.00 | 72.00 | 72.00 |
| STA257A-008 | | SH 257 WINDSOR RESURFACING | 03/30/23 | 6,062.00 | 50.00 | 53.88 | 55.00 |
| | WEIGHTED AVERAGE FOR THE FIRST QUARTER | | | 19,121.00 | 70.28 | 77.22 | 79.12 |
| | WEIGHTED AVERAGE FOR THE YEAR | | | 19,121.00 | 70.28 | 77.22 | 79.12 |
| ===== | 304-06008 | ABC (CL 6) (Spec) | | Cubic Yard | ===== | | |
| FSA0853-123 | | US 85 AND WCR 66 LEFT TURN AC | 01/26/23 | 298.00 | 95.00 | 71.17 | 70.00 |

COLORADO DEPARTMENT OF TRANSPORTATION
ITEM UNIT COSTS BY PROJECTS -- 2023 COST DATA

12:26 Wednesday, May 17, 2023 46

| PROJECT NUMBER | ITEM NUMBER/ PROJECT LOCATION | ITEM DESCRIPTION/ PROJECT LOCATION | DATE LET | UNIT/ QUANTITY | ENGR. EST. | AVERAGE BID | AWARDED BID |
|----------------|----------------------------------|--|----------|-------------------|------------|-------------|-------------|
| ===== | 304-06008 | ABC (CL 6) (Spec) | | Cubic Yard | ===== | ===== | ===== |
| STA066A-008 | | SH 66 @ WCR 7 | 01/26/23 | 301.00 | 95.00 | 118.68 | 96.00 |
| STA257A-008 | | SH 257 WINDSOR RESURFACING | 03/30/23 | 1,354.00 | 50.00 | 56.33 | 55.00 |
| | | WEIGHTED AVERAGE FOR THE FIRST QUARTER | | 1,953.00 | 63.80 | 76.39 | 63.61 |
| | | WEIGHTED AVERAGE FOR THE YEAR | | 1,953.00 | 63.80 | 76.39 | 63.61 |
| ===== | 304-07000 | ABC (CL 7) | | Ton | ===== | ===== | ===== |
| NHPP0701-250 | | I-70B: DDI TO 24 RD, MAIN ST | 01/12/23 | 389.34 | 50.00 | 83.05 | 87.10 |
| | | WEIGHTED AVERAGE FOR THE FIRST QUARTER | | 389.34 | 50.00 | 83.05 | 87.10 |
| | | WEIGHTED AVERAGE FOR THE YEAR | | 389.34 | 50.00 | 83.05 | 87.10 |
| ===== | 304-08000 | ABC (Shoulder Material) | | Ton | ===== | ===== | ===== |
| SHE067A-044 | | SH 67F M.P. 56.5-57.6 AND SH | 03/02/23 | 333.00 | 50.00 | 39.57 | 39.57 |
| STR194A-002 | | SH194A SUR. TREAT.& DRAI IMP | 03/09/23 | 5,068.93 | 31.00 | 44.75 | 41.50 |
| | | WEIGHTED AVERAGE FOR THE FIRST QUARTER | | 5,401.93 | 32.17 | 44.59 | 41.38 |
| | | WEIGHTED AVERAGE FOR THE YEAR | | 5,401.93 | 32.17 | 44.59 | 41.38 |
| ===== | 304-08002 | ABC (Shoulder Material) | | Cubic Yard | ===== | ===== | ===== |
| NHPP0253-296 | | I-25 @ LCR 16 (MP 253.8-254.5 | 02/07/23 | 43.00 | 229.98 | 246.08 | 246.08 |
| | | WEIGHTED AVERAGE FOR THE FIRST QUARTER | | 43.00 | 229.98 | 246.08 | 246.08 |
| | | WEIGHTED AVERAGE FOR THE YEAR | | 43.00 | 229.98 | 246.08 | 246.08 |
| ===== | 304-09014 | ABC (Spec) | | Ton | ===== | ===== | ===== |
| STA172A-022 | | SH 172 IGNACIO TO ELMORE'S CO | 01/12/23 | 5,356.00 | 35.00 | 44.96 | 59.51 |
| | | WEIGHTED AVERAGE FOR THE FIRST QUARTER | | 5,356.00 | 35.00 | 44.96 | 59.51 |
| | | WEIGHTED AVERAGE FOR THE YEAR | | 5,356.00 | 35.00 | 44.96 | 59.51 |
| ===== | 306-01000 | Reconditioning | | Sq Yard | ===== | ===== | ===== |
| NHPP0253-296 | | I-25 @ LCR 16 (MP 253.8-254.5 | 02/07/23 | 83.00 | 12.05 | 12.89 | 12.89 |

| PROJECT NUMBER | ITEM NUMBER/ PROJECT LOCATION | ITEM DESCRIPTION/ PROJECT LOCATION | DATE LET | UNIT/ QUANTITY | ENGR. EST. | AVERAGE BID | AWARDED BID |
|-----------------|--|--|----------|-------------------|------------|-------------|-------------|
| ===== 306-01000 | | Reconditioning | | Sq Yard | | | |
| STA257A-008 | | SH 257 WINDSOR RESURFACING | 03/30/23 | 35,277.00 | 2.00 | 1.88 | 2.45 |
| | WEIGHTED AVERAGE FOR THE FIRST QUARTER | | | 35,360.00 | 2.02 | 1.89 | 2.47 |
| | WEIGHTED AVERAGE FOR THE YEAR | | | 35,360.00 | 2.02 | 1.89 | 2.47 |
| ===== 310-00608 | | Full Depth Reclam. of HMA Pvmt (0-8 in.) | | Sq Yard | | | |
| NHPP0253-296 | | I-25 @ LCR 16 (MP 253.8-254.5 | 02/07/23 | 6,190.00 | 3.30 | 3.53 | 3.53 |
| | WEIGHTED AVERAGE FOR THE FIRST QUARTER | | | 6,190.00 | 3.30 | 3.53 | 3.53 |
| | WEIGHTED AVERAGE FOR THE YEAR | | | 6,190.00 | 3.30 | 3.53 | 3.53 |
| ===== 403-00720 | | HMA (Patching) (Asph) | | Ton | | | |
| STA172A-022 | | SH 172 IGNACIO TO ELMORE'S CO | 01/12/23 | 158.00 | 350.00 | 381.20 | 548.40 |
| NHPP0701-250 | | I-70B: DDI TO 24 RD, MAIN ST | 01/12/23 | 540.54 | 300.00 | 298.50 | 297.00 |
| SFTYR200-277 | | REGION 2 WIDE, VARIOUS HWY & | 01/19/23 | 20.00 | 500.00 | 337.50 | 275.00 |
| FSA0853-123 | | US 85 AND WCR 66 LEFT TURN AC | 01/26/23 | 69.00 | 300.00 | 299.33 | 190.00 |
| NHPP0253-296 | | I-25 @ LCR 16 (MP 253.8-254.5 | 02/07/23 | 34.00 | 255.62 | 273.52 | 273.52 |
| C0703-498 | | EISENHOWER JOHNSON MEMORIAL T | 02/16/23 | 93.00 | 500.00 | 350.76 | 390.00 |
| STA1381-011 | | SH 138 STERLING NORTH PART 2 | 02/16/23 | 500.00 | 200.00 | 400.00 | 400.00 |
| C133A-052 | | SH 133 ROCKFALL N OF MCCLURE | 02/16/23 | 50.00 | 500.00 | 578.44 | 1150.00 |
| STM C440-013 | | R3 EAGLE RESIDENCY ADA RAMP I | 02/16/23 | 50.00 | 300.00 | 200.00 | 200.00 |
| NHPP0701-256 | | I-70B/31.5 RD MESA COUNTY | 02/16/23 | 10.00 | 350.00 | 262.50 | 265.00 |
| SHE067A-044 | | SH 67F M.P. 56.5-57.6 AND SH | 03/02/23 | 105.00 | 250.00 | 332.64 | 332.64 |
| STR194A-002 | | SH194A SUR. TREAT.& DRAI IMP | 03/09/23 | 95.62 | 280.00 | 252.50 | 185.00 |
| STA257A-008 | | SH 257 WINDSOR RESURFACING | 03/30/23 | 105.00 | 250.00 | 166.00 | 155.00 |
| NHPP R100-376 | | VARIOUS LOCATIONS IN REGION 1 | 03/30/23 | 60.00 | 309.51 | 1016.31 | 930.00 |
| | WEIGHTED AVERAGE FOR THE FIRST QUARTER | | | 1,890.16 | 288.18 | 353.54 | 373.62 |
| | WEIGHTED AVERAGE FOR THE YEAR | | | 1,890.16 | 288.18 | 353.54 | 373.62 |
| ===== 403-00721 | | HMA (Patching) (Asph) | | Sq Yard | | | |
| C1601-084 | | US 160 SECTION3 PRIORITY CULV | 02/16/23 | 170.00 | 100.00 | 205.29 | 120.00 |
| C0881-036 | | R1 CURB RAMPS-SH88B & US285D | 02/16/23 | 467.00 | 60.00 | 163.75 | 100.00 |
| | WEIGHTED AVERAGE FOR THE FIRST QUARTER | | | 637.00 | 70.68 | 170.15 | 105.34 |
| | WEIGHTED AVERAGE FOR THE YEAR | | | 637.00 | 70.68 | 170.15 | 105.34 |

COLORADO DEPARTMENT OF TRANSPORTATION
ITEM UNIT COSTS BY PROJECTS -- 2023 COST DATA

12:26 Wednesday, May 17, 2023 48

| PROJECT NUMBER | ITEM NUMBER/ PROJECT LOCATION | ITEM DESCRIPTION/ PROJECT LOCATION | DATE LET | UNIT/ QUANTITY | ENGR. EST. | AVERAGE BID | AWARDED BID |
|-----------------|----------------------------------|---------------------------------------|----------|-------------------|------------|-------------|-------------|
| ===== 403-33841 | | HMA (Gr S) (100) (PG 64-22) | | Ton ===== | | | |
| STA257A-008 | | SH 257 WINDSOR RESURFACING | 03/30/23 | 17,985.00 | 105.00 | 90.83 | 83.00 |
| | WEIGHTED | AVERAGE FOR THE FIRST QUARTER | | 17,985.00 | 105.00 | 90.83 | 83.00 |
| | | WEIGHTED AVERAGE FOR THE YEAR | | 17,985.00 | 105.00 | 90.83 | 83.00 |
| ===== 403-34721 | | HMA (Gr SX) (75) (PG 58-28) | | Ton ===== | | | |
| STA172A-022 | | SH 172 IGNACIO TO ELMORE'S CO | 01/12/23 | 36,995.00 | 120.00 | 118.10 | 116.69 |
| C0703-498 | | EISENHOWER JOHNSON MEMORIAL T | 02/16/23 | 6,939.00 | 150.00 | 154.45 | 160.00 |
| SHE067A-044 | | SH 67F M.P. 56.5-57.6 AND SH | 03/02/23 | 1,950.00 | 200.00 | 178.20 | 178.20 |
| STR194A-002 | | SH194A SUR. TREAT.& DRAI IMP | 03/09/23 | 23,155.74 | 150.00 | 131.50 | 133.00 |
| | WEIGHTED | AVERAGE FOR THE FIRST QUARTER | | 69,039.74 | 135.34 | 128.54 | 128.25 |
| | | WEIGHTED AVERAGE FOR THE YEAR | | 69,039.74 | 135.34 | 128.54 | 128.25 |
| ===== 403-34741 | | HMA (Gr SX) (75) (PG 64-22) | | Ton ===== | | | |
| NHPP0253-296 | | I-25 @ LCR 16 (MP 253.8-254.5 | 02/07/23 | 4,321.00 | 99.18 | 106.12 | 106.12 |
| | WEIGHTED | AVERAGE FOR THE FIRST QUARTER | | 4,321.00 | 99.18 | 106.12 | 106.12 |
| | | WEIGHTED AVERAGE FOR THE YEAR | | 4,321.00 | 99.18 | 106.12 | 106.12 |
| ===== 403-34751 | | HMA (Gr SX) (75) (PG 64-28) | | Ton ===== | | | |
| FSA0853-123 | | US 85 AND WCR 66 LEFT TURN AC | 01/26/23 | 1,843.00 | 125.00 | 121.17 | 96.00 |
| STA066A-008 | | SH 66 @ WCR 7 | 01/26/23 | 4,449.00 | 140.00 | 124.46 | 99.75 |
| NHPP0253-296 | | I-25 @ LCR 16 (MP 253.8-254.5 | 02/07/23 | 1,838.00 | 115.71 | 123.81 | 123.81 |
| STA1381-011 | | SH 138 STERLING NORTH PART 2 | 02/16/23 | 53,035.00 | 120.00 | 139.00 | 139.00 |
| | WEIGHTED | AVERAGE FOR THE FIRST QUARTER | | 61,165.00 | 121.48 | 132.78 | 134.39 |
| | | WEIGHTED AVERAGE FOR THE YEAR | | 61,165.00 | 121.48 | 132.78 | 134.39 |
| ===== 403-34801 | | HMA (Gr SX) (100) | | Ton ===== | | | |
| NHPP0701-250 | | I-70B: DDI TO 24 RD, MAIN ST | 01/12/23 | 40,125.29 | 95.00 | 88.70 | 82.40 |
| | WEIGHTED | AVERAGE FOR THE FIRST QUARTER | | 40,125.29 | 95.00 | 88.70 | 82.40 |
| | | WEIGHTED AVERAGE FOR THE YEAR | | 40,125.29 | 95.00 | 88.70 | 82.40 |

COLORADO DEPARTMENT OF TRANSPORTATION
ITEM UNIT COSTS BY PROJECTS -- 2023 COST DATA

12:26 Wednesday, May 17, 2023 49

| PROJECT NUMBER | ITEM NUMBER/ PROJECT LOCATION | ITEM DESCRIPTION/ PROJECT LOCATION | DATE LET | UNIT/ QUANTITY | ENGR. EST. | AVERAGE BID | AWARDED BID |
|-----------------|----------------------------------|--|----------|-------------------|------------|-------------|-------------|
| ===== 403-34871 | | HMA (Gr SX) (100) (PG 76-28) | | Ton | ===== | ===== | ===== |
| NHPP0701-256 | | I-70B/31.5 RD MESA COUNTY | 02/16/23 | 303.00 | 150.00 | 257.50 | 230.00 |
| STA257A-008 | | SH 257 WINDSOR RESURFACING | 03/30/23 | 17,116.00 | 140.00 | 100.63 | 92.00 |
| ER0703-524 | | STRUCTURE F-13-P, EB I-70 EXI | 03/31/23 | 227.00 | 204.00 | 373.81 | 204.00 |
| | | WEIGHTED AVERAGE FOR THE FIRST QUARTER | | 17,646.00 | 141.00 | 108.54 | 95.81 |
| | | WEIGHTED AVERAGE FOR THE YEAR | | 17,646.00 | 141.00 | 108.54 | 95.81 |
| ===== 403-36721 | | HMA (Gr ST) (75) (PG 58-28) | | Ton | ===== | ===== | ===== |
| STA172A-022 | | SH 172 IGNACIO TO ELMORE'S CO | 01/12/23 | 26,481.00 | 120.00 | 126.55 | 126.09 |
| | | WEIGHTED AVERAGE FOR THE FIRST QUARTER | | 26,481.00 | 120.00 | 126.55 | 126.09 |
| | | WEIGHTED AVERAGE FOR THE YEAR | | 26,481.00 | 120.00 | 126.55 | 126.09 |
| ===== 408-01000 | | Hot Joint-Crack Sealant | | Ton | ===== | ===== | ===== |
| STRR300-265 | | MOUNTAIN RE FY23 CRACK SEALS | 03/02/23 | 135.00 | 3500.00 | 5055.00 | 5055.00 |
| | | WEIGHTED AVERAGE FOR THE FIRST QUARTER | | 135.00 | 3500.00 | 5055.00 | 5055.00 |
| | | WEIGHTED AVERAGE FOR THE YEAR | | 135.00 | 3500.00 | 5055.00 | 5055.00 |
| ===== 408-01100 | | Joint Sealant | | Lin Foot | ===== | ===== | ===== |
| STA172A-022 | | SH 172 IGNACIO TO ELMORE'S CO | 01/12/23 | 324.00 | 30.00 | 9.88 | 9.75 |
| C1601-084 | | US 160 SECTION3 PRIORITY CULV | 02/16/23 | 488.00 | 40.00 | 17.72 | 5.50 |
| STA257A-008 | | SH 257 WINDSOR RESURFACING | 03/30/23 | 270.00 | 35.00 | 46.88 | 36.50 |
| | | WEIGHTED AVERAGE FOR THE FIRST QUARTER | | 1,082.00 | 35.76 | 22.64 | 14.51 |
| | | WEIGHTED AVERAGE FOR THE YEAR | | 1,082.00 | 35.76 | 22.64 | 14.51 |
| ===== 409-01015 | | CC Matl (Ty I) | | Sq Yard | ===== | ===== | ===== |
| SHE067A-044 | | SH 67F M.P. 56.5-57.6 AND SH | 03/02/23 | 3,705.00 | 10.00 | 2.97 | 2.97 |
| | | WEIGHTED AVERAGE FOR THE FIRST QUARTER | | 3,705.00 | 10.00 | 2.97 | 2.97 |
| | | WEIGHTED AVERAGE FOR THE YEAR | | 3,705.00 | 10.00 | 2.97 | 2.97 |

COLORADO DEPARTMENT OF TRANSPORTATION
ITEM UNIT COSTS BY PROJECTS -- 2023 COST DATA

12:26 Wednesday, May 17, 2023 50

| PROJECT NUMBER | ITEM NUMBER/ PROJECT LOCATION | ITEM DESCRIPTION/ PROJECT LOCATION | DATE LET | UNIT/ QUANTITY | ENGR. EST. | AVERAGE BID | AWARDED BID |
|----------------|----------------------------------|---------------------------------------|----------|-------------------|------------|-------------|-------------|
| ===== | 409-03060 | Furn CC Matl | | Ton | ===== | ===== | ===== |
| STR194A-002 | | SH194A SUR. TREAT.& DRAI IMP | 03/09/23 | 150.00 | 100.00 | 88.50 | 105.00 |
| | WEIGHTED | AVERAGE FOR THE FIRST QUARTER | | 150.00 | 100.00 | 88.50 | 105.00 |
| | | WEIGHTED AVERAGE FOR THE YEAR | | 150.00 | 100.00 | 88.50 | 105.00 |
| ===== | 411-03345 | Asph Cem (PG 76-28) | | Ton | ===== | ===== | ===== |
| NHPP0701-250 | | I-70B: DDI TO 24 RD, MAIN ST | 01/12/23 | 2,408.32 | 600.00 | 716.00 | 882.00 |
| | WEIGHTED | AVERAGE FOR THE FIRST QUARTER | | 2,408.32 | 600.00 | 716.00 | 882.00 |
| | | WEIGHTED AVERAGE FOR THE YEAR | | 2,408.32 | 600.00 | 716.00 | 882.00 |
| ===== | 411-10216 | Emul Asph (CRS-2P) | | Gallon | ===== | ===== | ===== |
| SHE067A-044 | | SH 67F M.P. 56.5-57.6 AND SH | 03/02/23 | 1,912.00 | 5.00 | 17.82 | 17.82 |
| | WEIGHTED | AVERAGE FOR THE FIRST QUARTER | | 1,912.00 | 5.00 | 17.82 | 17.82 |
| | | WEIGHTED AVERAGE FOR THE YEAR | | 1,912.00 | 5.00 | 17.82 | 17.82 |
| ===== | 411-10255 | Emul Asph (SS) | | Gallon | ===== | ===== | ===== |
| STA172A-022 | | SH 172 IGNACIO TO ELMORE'S CO | 01/12/23 | 43,875.00 | 4.00 | 5.44 | 5.57 |
| NHPP0701-250 | | I-70B: DDI TO 24 RD, MAIN ST | 01/12/23 | 18,795.00 | 3.00 | 4.25 | 4.50 |
| C0703-498 | | EISENHOWER JOHNSON MEMORIAL T | 02/16/23 | 6,172.00 | 4.00 | 3.95 | 4.00 |
| NHPP0701-256 | | I-70B/31.5 RD MESA COUNTY | 02/16/23 | 54.00 | 10.00 | 3.50 | 2.50 |
| SHE067A-044 | | SH 67F M.P. 56.5-57.6 AND SH | 03/02/23 | 610.00 | 5.00 | 24.95 | 24.95 |
| STR194A-002 | | SH194A SUR. TREAT.& DRAI IMP | 03/09/23 | 10,884.00 | 3.60 | 4.00 | 4.00 |
| | WEIGHTED | AVERAGE FOR THE FIRST QUARTER | | 80,390.00 | 3.72 | 4.88 | 5.13 |
| | | WEIGHTED AVERAGE FOR THE YEAR | | 80,390.00 | 3.72 | 4.88 | 5.13 |
| ===== | 412-00190 | Conc Pvmt (Patching) | | Sq Yard | ===== | ===== | ===== |
| STR2871-040 | | US 287 MP 0.0 TO MP 122 VARIO | 01/12/23 | 4,140.00 | 200.00 | 267.28 | 204.94 |

| PROJECT NUMBER | ITEM NUMBER/ PROJECT LOCATION | ITEM DESCRIPTION/ PROJECT LOCATION | DATE LET | UNIT/ QUANTITY | ENGR. EST. | AVERAGE BID | AWARDED BID |
|----------------|--|---------------------------------------|----------|-------------------|------------|-------------|-------------|
| ===== | 412-00190 | Conc Pvmt (Patching) | | Sq Yard | ===== | ===== | ===== |
| C0881-036 | R1 CURB RAMPS-SH88B & US285D | | 02/16/23 | 594.00 | 140.00 | 184.75 | 124.00 |
| NHPP0253-290 | I25 @ 58TH AND 62ND | | 03/02/23 | 278.00 | 493.00 | 561.72 | 435.00 |
| | WEIGHTED AVERAGE FOR THE FIRST QUARTER | | | 5,012.00 | 209.14 | 269.35 | 208.11 |
| | WEIGHTED AVERAGE FOR THE YEAR | | | 5,012.00 | 209.14 | 269.35 | 208.11 |
| ===== | 412-00600 | Conc Pvmt (6 In) | | Sq Yard | ===== | ===== | ===== |
| STA172A-022 | SH 172 IGNACIO TO ELMORE'S CO | | 01/12/23 | 408.00 | 150.00 | 122.92 | 144.83 |
| STM C440-013 | R3 EAGLE RESIDENCY ADA RAMP I | | 02/16/23 | 36.00 | 200.00 | 149.00 | 149.00 |
| | WEIGHTED AVERAGE FOR THE FIRST QUARTER | | | 444.00 | 154.05 | 124.02 | 145.17 |
| | WEIGHTED AVERAGE FOR THE YEAR | | | 444.00 | 154.05 | 124.02 | 145.17 |
| ===== | 412-00801 | Conc Pvmt (8 In) (Spec) | | Sq Yard | ===== | ===== | ===== |
| NHPP0253-296 | I-25 @ LCR 16 (MP 253.8-254.5 | | 02/07/23 | 1,514.00 | 137.55 | 147.18 | 147.18 |
| | WEIGHTED AVERAGE FOR THE FIRST QUARTER | | | 1,514.00 | 137.55 | 147.18 | 147.18 |
| | WEIGHTED AVERAGE FOR THE YEAR | | | 1,514.00 | 137.55 | 147.18 | 147.18 |
| ===== | 412-01250 | Conc Pvmt (12-1/2 In) | | Sq Yard | ===== | ===== | ===== |
| NHPPR100-383 | I70 OVER WASHINGTON ST | | 01/26/23 | 180.00 | 300.00 | 403.49 | 332.00 |
| | WEIGHTED AVERAGE FOR THE FIRST QUARTER | | | 180.00 | 300.00 | 403.49 | 332.00 |
| | WEIGHTED AVERAGE FOR THE YEAR | | | 180.00 | 300.00 | 403.49 | 332.00 |
| ===== | 412-05100 | Poly Slab Jacking | | Pound | ===== | ===== | ===== |
| NHPP0701-250 | I-70B: DDI TO 24 RD, MAIN ST | | 01/12/23 | 113.00 | 10.00 | 66.35 | 51.70 |
| | WEIGHTED AVERAGE FOR THE FIRST QUARTER | | | 113.00 | 10.00 | 66.35 | 51.70 |
| | WEIGHTED AVERAGE FOR THE YEAR | | | 113.00 | 10.00 | 66.35 | 51.70 |
| ===== | 420-00000 | Geomembrane | | Sq Yard | ===== | ===== | ===== |
| STA172A-022 | SH 172 IGNACIO TO ELMORE'S CO | | 01/12/23 | 96.00 | 50.00 | 20.94 | 22.17 |
| | WEIGHTED AVERAGE FOR THE FIRST QUARTER | | | 96.00 | 50.00 | 20.94 | 22.17 |
| | WEIGHTED AVERAGE FOR THE YEAR | | | 96.00 | 50.00 | 20.94 | 22.17 |

| PROJECT NUMBER | ITEM NUMBER/ PROJECT LOCATION | ITEM DESCRIPTION/ PROJECT LOCATION | DATE LET | UNIT/ QUANTITY | ENGR. EST. | AVERAGE BID | AWARDED BID |
|-----------------|--|---------------------------------------|----------|-------------------|------------|-------------|-------------|
| ===== 420-00102 | | Geotextile (Er Cont) (CL 1) | | Sq Yard | ===== | | |
| NHPP0253-296 | | I-25 @ LCR 16 (MP 253.8-254.5 | 02/07/23 | 153.00 | 13.89 | 14.86 | 14.86 |
| | WEIGHTED AVERAGE FOR THE FIRST QUARTER | | | 153.00 | 13.89 | 14.86 | 14.86 |
| | WEIGHTED AVERAGE FOR THE YEAR | | | 153.00 | 13.89 | 14.86 | 14.86 |
| ===== 420-00112 | | Geotextile (Drain) (CL 1) | | Sq Yard | ===== | | |
| SHE067A-044 | | SH 67F M.P. 56.5-57.6 AND SH | 03/02/23 | 26.00 | 20.00 | 10.98 | 10.98 |
| STR194A-002 | | SH194A SUR. TREAT.& DRAI IMP | 03/09/23 | 99.00 | 6.60 | 11.00 | 10.00 |
| | WEIGHTED AVERAGE FOR THE FIRST QUARTER | | | 125.00 | 9.39 | 11.00 | 10.20 |
| | WEIGHTED AVERAGE FOR THE YEAR | | | 125.00 | 9.39 | 11.00 | 10.20 |
| ===== 420-00113 | | Geotextile (Drain) (CL 2) | | Sq Yard | ===== | | |
| STA172A-022 | | SH 172 IGNACIO TO ELMORE'S CO | 01/12/23 | 490.00 | 5.00 | 8.05 | 12.20 |
| | WEIGHTED AVERAGE FOR THE FIRST QUARTER | | | 490.00 | 5.00 | 8.05 | 12.20 |
| | WEIGHTED AVERAGE FOR THE YEAR | | | 490.00 | 5.00 | 8.05 | 12.20 |
| ===== 420-00114 | | Geotextile (Drain) (CL 3) | | Sq Yard | ===== | | |
| NHPP R100-376 | | VARIOUS LOCATIONS IN REGION 1 | 03/30/23 | 72.00 | 21.59 | 13.98 | 12.00 |
| | WEIGHTED AVERAGE FOR THE FIRST QUARTER | | | 72.00 | 21.59 | 13.98 | 12.00 |
| | WEIGHTED AVERAGE FOR THE YEAR | | | 72.00 | 21.59 | 13.98 | 12.00 |
| ===== 420-00133 | | Geotextile (Separator) (CL 2) | | Sq Yard | ===== | | |
| STA172A-022 | | SH 172 IGNACIO TO ELMORE'S CO | 01/12/23 | 685.00 | 8.00 | 6.59 | 9.23 |
| STA1381-011 | | SH 138 STERLING NORTH PART 2 | 02/16/23 | 8,758.00 | 4.00 | 3.50 | 3.50 |
| C1601-084 | | US 160 SECTION3 PRIORITY CULV | 02/16/23 | 192.00 | 10.00 | 5.59 | 5.00 |
| | WEIGHTED AVERAGE FOR THE FIRST QUARTER | | | 9,635.00 | 4.40 | 3.98 | 3.94 |
| | WEIGHTED AVERAGE FOR THE YEAR | | | 9,635.00 | 4.40 | 3.98 | 3.94 |

| PROJECT NUMBER | ITEM NUMBER/ PROJECT LOCATION | ITEM DESCRIPTION/ PROJECT LOCATION | DATE LET | UNIT/ QUANTITY | ENGR. EST. | AVERAGE BID | AWARDED BID |
|----------------|----------------------------------|---------------------------------------|----------|-------------------|------------|-------------|-------------|
| ===== | 420-00300 | Geotextile (Reinforcement) | | Sq Yard | ===== | | |
| STA172A-022 | | SH 172 IGNACIO TO ELMORE'S CO | 01/12/23 | 933.00 | 10.00 | 4.78 | 5.06 |
| | WEIGHTED | AVERAGE FOR THE FIRST QUARTER | | 933.00 | 10.00 | 4.78 | 5.06 |
| | | WEIGHTED AVERAGE FOR THE YEAR | | 933.00 | 10.00 | 4.78 | 5.06 |
| ===== | 502-00460 | Pile Tip | | Each | ===== | | |
| NHPP0253-296 | | I-25 @ LCR 16 (MP 253.8-254.5 | 02/07/23 | 8.00 | 209.91 | 224.60 | 224.60 |
| | WEIGHTED | AVERAGE FOR THE FIRST QUARTER | | 8.00 | 209.91 | 224.60 | 224.60 |
| | | WEIGHTED AVERAGE FOR THE YEAR | | 8.00 | 209.91 | 224.60 | 224.60 |
| ===== | 502-11489 | Steel Pile (HP 14x89) | | Lin Foot | ===== | | |
| NHPP0253-296 | | I-25 @ LCR 16 (MP 253.8-254.5 | 02/07/23 | 220.00 | 196.88 | 211.84 | 211.84 |
| | WEIGHTED | AVERAGE FOR THE FIRST QUARTER | | 220.00 | 196.88 | 211.84 | 211.84 |
| | | WEIGHTED AVERAGE FOR THE YEAR | | 220.00 | 196.88 | 211.84 | 211.84 |
| ===== | 503-00018 | Drilled Shaft (18 In) | | Lin Foot | ===== | | |
| STA066A-008 | | SH 66 @ WCR 7 | 01/26/23 | 5.00 | 700.00 | 401.80 | 431.63 |
| NHPP0701-256 | | I-70B/31.5 RD MESA COUNTY | 02/16/23 | 5.00 | 400.00 | 1500.00 | 2000.00 |
| | WEIGHTED | AVERAGE FOR THE FIRST QUARTER | | 10.00 | 550.00 | 715.57 | 1215.82 |
| | | WEIGHTED AVERAGE FOR THE YEAR | | 10.00 | 550.00 | 715.57 | 1215.82 |
| ===== | 503-00036 | Drilled Shaft (36 In) | | Lin Foot | ===== | | |
| STA066A-008 | | SH 66 @ WCR 7 | 01/26/23 | 114.00 | 750.00 | 891.55 | 924.75 |
| C0342-066 | | US 034A (MP 113-150) | 02/02/23 | 18.00 | 650.00 | 782.33 | 767.00 |
| | WEIGHTED | AVERAGE FOR THE FIRST QUARTER | | 132.00 | 736.36 | 882.10 | 903.24 |
| | | WEIGHTED AVERAGE FOR THE YEAR | | 132.00 | 736.36 | 882.10 | 903.24 |

| PROJECT NUMBER | ITEM NUMBER/ PROJECT LOCATION | ITEM DESCRIPTION/ PROJECT LOCATION | DATE LET | UNIT/ QUANTITY | ENGR. EST. | AVERAGE BID | AWARDED BID |
|----------------|----------------------------------|---------------------------------------|----------|-------------------|------------|-------------|-------------|
| ===== | 503-00042 | Drilled Shaft (42 In) | | Lin Foot | ===== | | |
| C 1601-086 | | MAPLE & CHESTNUT SIGNALS AT I | 02/16/23 | 17.00 | 900.00 | 1620.00 | 1620.00 |
| | WEIGHTED | AVERAGE FOR THE FIRST QUARTER | | 17.00 | 900.00 | 1620.00 | 1620.00 |
| | | WEIGHTED AVERAGE FOR THE YEAR | | 17.00 | 900.00 | 1620.00 | 1620.00 |
| ===== | 503-00048 | Drilled Shaft (48 In) | | Lin Foot | ===== | | |
| STA066A-008 | | SH 66 @ WCR 7 | 01/26/23 | 21.00 | 1200.00 | 932.44 | 939.22 |
| C 1601-086 | | MAPLE & CHESTNUT SIGNALS AT I | 02/16/23 | 63.00 | 1000.00 | 1980.00 | 1980.00 |
| | WEIGHTED | AVERAGE FOR THE FIRST QUARTER | | 84.00 | 1050.00 | 1325.28 | 1719.81 |
| | | WEIGHTED AVERAGE FOR THE YEAR | | 84.00 | 1050.00 | 1325.28 | 1719.81 |
| ===== | 504-03411 | Retaining Wall (Boulder) | | Sq Foot | ===== | | |
| SHE067A-044 | | SH 67F M.P. 56.5-57.6 AND SH | 03/02/23 | 882.00 | 100.00 | 59.40 | 59.40 |
| | WEIGHTED | AVERAGE FOR THE FIRST QUARTER | | 882.00 | 100.00 | 59.40 | 59.40 |
| | | WEIGHTED AVERAGE FOR THE YEAR | | 882.00 | 100.00 | 59.40 | 59.40 |
| ===== | 504-06300 | Ground Nail | | Lin Foot | ===== | | |
| C133A-052 | | SH 133 ROCKFALL N OF MCCLURE | 02/16/23 | 360.00 | 500.00 | 237.39 | 240.00 |
| | WEIGHTED | AVERAGE FOR THE FIRST QUARTER | | 360.00 | 500.00 | 237.39 | 240.00 |
| | | WEIGHTED AVERAGE FOR THE YEAR | | 360.00 | 500.00 | 237.39 | 240.00 |
| ===== | 504-06406 | Soil Nail | | Lin Foot | ===== | | |
| NHPP R100-376 | | VARIOUS LOCATIONS IN REGION 1 | 03/30/23 | 4,101.00 | 61.23 | 101.08 | 108.00 |
| | WEIGHTED | AVERAGE FOR THE FIRST QUARTER | | 4,101.00 | 61.23 | 101.08 | 108.00 |
| | | WEIGHTED AVERAGE FOR THE YEAR | | 4,101.00 | 61.23 | 101.08 | 108.00 |

| PROJECT NUMBER | ITEM NUMBER/ PROJECT LOCATION | ITEM DESCRIPTION/ PROJECT LOCATION | DATE LET | UNIT/ QUANTITY | ENGR. EST. | AVERAGE BID | AWARDED BID |
|----------------|----------------------------------|---------------------------------------|----------|-------------------|------------|-------------|-------------|
| ===== | 504-06410 | Verification Testing | | Each | ===== | ===== | ===== |
| NHPP R100-376 | | VARIOUS LOCATIONS IN REGION 1 | 03/30/23 | 10.00 | 2400.00 | 4498.47 | 7300.00 |
| | WEIGHTED | AVERAGE FOR THE FIRST QUARTER | | 10.00 | 2400.00 | 4498.47 | 7300.00 |
| | | WEIGHTED AVERAGE FOR THE YEAR | | 10.00 | 2400.00 | 4498.47 | 7300.00 |
| ===== | 506-00020 | Place Riprap | | Cubic Yard | ===== | ===== | ===== |
| STA172A-022 | | SH 172 IGNACIO TO ELMORE'S CO | 01/12/23 | 36.00 | 35.00 | 98.39 | 83.78 |
| | WEIGHTED | AVERAGE FOR THE FIRST QUARTER | | 36.00 | 35.00 | 98.39 | 83.78 |
| | | WEIGHTED AVERAGE FOR THE YEAR | | 36.00 | 35.00 | 98.39 | 83.78 |
| ===== | 506-00206 | Riprap (6 In) | | Cubic Yard | ===== | ===== | ===== |
| NHPP0253-296 | | I-25 @ LCR 16 (MP 253.8-254.5 | 02/07/23 | 463.00 | 168.88 | 180.70 | 180.70 |
| C0703-498 | | EISENHOWER JOHNSON MEMORIAL T | 02/16/23 | 4.00 | 400.00 | 342.52 | 300.00 |
| STR194A-002 | | SH194A SUR. TREAT.& DRAI IMP | 03/09/23 | 12.40 | 170.00 | 285.00 | 270.00 |
| | WEIGHTED | AVERAGE FOR THE FIRST QUARTER | | 479.40 | 170.84 | 189.76 | 184.01 |
| | | WEIGHTED AVERAGE FOR THE YEAR | | 479.40 | 170.84 | 189.76 | 184.01 |
| ===== | 506-00209 | Riprap (9 In) | | Cubic Yard | ===== | ===== | ===== |
| NHPP0253-296 | | I-25 @ LCR 16 (MP 253.8-254.5 | 02/07/23 | 77.00 | 188.31 | 201.49 | 201.49 |
| STA1381-011 | | SH 138 STERLING NORTH PART 2 | 02/16/23 | 37.00 | 250.00 | 300.00 | 300.00 |
| STR194A-002 | | SH194A SUR. TREAT.& DRAI IMP | 03/09/23 | 31.40 | 190.00 | 278.50 | 247.00 |
| NHPP R100-376 | | VARIOUS LOCATIONS IN REGION 1 | 03/30/23 | 36.00 | 205.11 | 236.75 | 84.00 |
| | WEIGHTED | AVERAGE FOR THE FIRST QUARTER | | 181.40 | 204.52 | 245.78 | 206.14 |
| | | WEIGHTED AVERAGE FOR THE YEAR | | 181.40 | 204.52 | 245.78 | 206.14 |
| ===== | 506-00212 | Riprap (12 In) | | Cubic Yard | ===== | ===== | ===== |
| STA172A-022 | | SH 172 IGNACIO TO ELMORE'S CO | 01/12/23 | 108.00 | 125.00 | 326.96 | 372.92 |

COLORADO DEPARTMENT OF TRANSPORTATION
ITEM UNIT COSTS BY PROJECTS -- 2023 COST DATA

12:26 Wednesday, May 17, 2023 56

| PROJECT NUMBER | ITEM NUMBER/ PROJECT LOCATION | ITEM DESCRIPTION/ PROJECT LOCATION | DATE LET | UNIT/ QUANTITY | ENGR. EST. | AVERAGE BID | AWARDED BID |
|----------------|--|---------------------------------------|----------|-------------------|------------|-------------|-------------|
| ===== | 506-00212 | Riprap (12 In) | | Cubic Yard | ===== | | |
| STA1381-011 | | SH 138 STERLING NORTH PART 2 | 02/16/23 | 8.00 | 235.00 | 325.00 | 325.00 |
| C1601-084 | | US 160 SECTION3 PRIORITY CULV | 02/16/23 | 89.00 | 230.00 | 302.54 | 310.00 |
| | WEIGHTED AVERAGE FOR THE FIRST QUARTER | | | 205.00 | 174.88 | 316.11 | 343.73 |
| | WEIGHTED AVERAGE FOR THE YEAR | | | 205.00 | 174.88 | 316.11 | 343.73 |
| ===== | 506-00218 | Riprap (18 In) | | Cubic Yard | ===== | | |
| STA172A-022 | | SH 172 IGNACIO TO ELMORE'S CO | 01/12/23 | 59.00 | 275.00 | 316.84 | 367.68 |
| STA1381-011 | | SH 138 STERLING NORTH PART 2 | 02/16/23 | 27.00 | 275.00 | 440.00 | 440.00 |
| C1601-084 | | US 160 SECTION3 PRIORITY CULV | 02/16/23 | 88.00 | 275.00 | 341.73 | 320.00 |
| SHE067A-044 | | SH 67F M.P. 56.5-57.6 AND SH | 03/02/23 | 7.00 | 200.00 | 241.06 | 241.06 |
| | WEIGHTED AVERAGE FOR THE FIRST QUARTER | | | 181.00 | 272.10 | 338.72 | 350.39 |
| | WEIGHTED AVERAGE FOR THE YEAR | | | 181.00 | 272.10 | 338.72 | 350.39 |
| ===== | 506-01020 | Geogrid Reinforce | | Sq Yard | ===== | | |
| NHPP0701-250 | | I-70B: DDI TO 24 RD, MAIN ST | 01/12/23 | 3,276.00 | 6.00 | 4.30 | 4.60 |
| STA1381-011 | | SH 138 STERLING NORTH PART 2 | 02/16/23 | 8,758.00 | 4.00 | 2.75 | 2.75 |
| STA257A-008 | | SH 257 WINDSOR RESURFACING | 03/30/23 | 950.00 | 8.00 | 4.40 | 4.00 |
| | WEIGHTED AVERAGE FOR THE FIRST QUARTER | | | 12,984.00 | 4.80 | 3.52 | 3.31 |
| | WEIGHTED AVERAGE FOR THE YEAR | | | 12,984.00 | 4.80 | 3.52 | 3.31 |
| ===== | 507-00000 | Conc S and D Pave | | Cubic Yard | ===== | | |
| C0703-498 | | EISENHOWER JOHNSON MEMORIAL T | 02/16/23 | 48.00 | 900.00 | 1294.15 | 1800.00 |
| | WEIGHTED AVERAGE FOR THE FIRST QUARTER | | | 48.00 | 900.00 | 1294.15 | 1800.00 |
| | WEIGHTED AVERAGE FOR THE YEAR | | | 48.00 | 900.00 | 1294.15 | 1800.00 |
| ===== | 507-00400 | Asphalt S and D Pave (Asph) | | Ton | ===== | | |
| NHPP R100-376 | | VARIOUS LOCATIONS IN REGION 1 | 03/30/23 | 4.00 | 553.17 | 1282.63 | 360.00 |
| | WEIGHTED AVERAGE FOR THE FIRST QUARTER | | | 4.00 | 553.17 | 1282.63 | 360.00 |
| | WEIGHTED AVERAGE FOR THE YEAR | | | 4.00 | 553.17 | 1282.63 | 360.00 |

COLORADO DEPARTMENT OF TRANSPORTATION
ITEM UNIT COSTS BY PROJECTS -- 2023 COST DATA

12:26 Wednesday, May 17, 2023 57

| PROJECT NUMBER | ITEM NUMBER/ PROJECT LOCATION | ITEM DESCRIPTION/ PROJECT LOCATION | DATE LET | UNIT/ QUANTITY | ENGR. EST. | AVERAGE BID | AWARDED BID |
|----------------|----------------------------------|---------------------------------------|----------|-------------------|------------|-------------|-------------|
| ===== | 509-00000 | Str Steel | | Pound | ===== | ===== | ===== |
| NHPP0253-296 | | I-25 @ LCR 16 (MP 253.8-254.5 | 02/07/23 | 26,700.00 | 1.54 | 1.65 | 1.65 |
| | WEIGHTED | AVERAGE FOR THE FIRST QUARTER | | 26,700.00 | 1.54 | 1.65 | 1.65 |
| | | WEIGHTED AVERAGE FOR THE YEAR | | 26,700.00 | 1.54 | 1.65 | 1.65 |
| ===== | 515-00120 | Waterproofing (Membrane) | | Sq Yard | ===== | ===== | ===== |
| STA257A-008 | | SH 257 WINDSOR RESURFACING | 03/30/23 | 234.00 | 25.00 | 37.45 | 29.00 |
| ER0703-524 | | STRUCTURE F-13-P, EB I-70 EXI | 03/31/23 | 1,375.00 | 27.00 | 37.78 | 27.00 |
| | WEIGHTED | AVERAGE FOR THE FIRST QUARTER | | 1,609.00 | 26.71 | 37.75 | 27.29 |
| | | WEIGHTED AVERAGE FOR THE YEAR | | 1,609.00 | 26.71 | 37.75 | 27.29 |
| ===== | 515-00400 | Concrete Sealer | | Sq Yard | ===== | ===== | ===== |
| STA172A-022 | | SH 172 IGNACIO TO ELMORE'S CO | 01/12/23 | 123.00 | 20.00 | 18.63 | 18.95 |
| C1601-084 | | US 160 SECTION3 PRIORITY CULV | 02/16/23 | 170.00 | 100.00 | 21.47 | 28.75 |
| STA257A-008 | | SH 257 WINDSOR RESURFACING | 03/30/23 | 165.00 | 30.00 | 33.50 | 26.00 |
| | WEIGHTED | AVERAGE FOR THE FIRST QUARTER | | 458.00 | 53.30 | 25.04 | 25.13 |
| | | WEIGHTED AVERAGE FOR THE YEAR | | 458.00 | 53.30 | 25.04 | 25.13 |
| ===== | 518-01001 | Br Expan Joint (Asphaltic Plug) | | Lin Foot | ===== | ===== | ===== |
| STA257A-008 | | SH 257 WINDSOR RESURFACING | 03/30/23 | 30.00 | 300.00 | 331.00 | 260.00 |
| | WEIGHTED | AVERAGE FOR THE FIRST QUARTER | | 30.00 | 300.00 | 331.00 | 260.00 |
| | | WEIGHTED AVERAGE FOR THE YEAR | | 30.00 | 300.00 | 331.00 | 260.00 |
| ===== | 518-01004 | Br Expan Device (0-4 In) | | Lin Foot | ===== | ===== | ===== |
| NHPPR100-383 | | I70 OVER WASHINGTON ST | 01/26/23 | 301.00 | 375.00 | 713.87 | 445.00 |
| NHPP0253-290 | | I25 @ 58TH AND 62ND | 03/02/23 | 780.00 | 300.00 | 475.60 | 370.00 |
| | WEIGHTED | AVERAGE FOR THE FIRST QUARTER | | 1,081.00 | 320.88 | 541.95 | 390.88 |
| | | WEIGHTED AVERAGE FOR THE YEAR | | 1,081.00 | 320.88 | 541.95 | 390.88 |

COLORADO DEPARTMENT OF TRANSPORTATION
ITEM UNIT COSTS BY PROJECTS -- 2023 COST DATA

12:26 Wednesday, May 17, 2023 58

| PROJECT NUMBER | ITEM NUMBER/ PROJECT LOCATION | ITEM DESCRIPTION/ PROJECT LOCATION | DATE LET | UNIT/ QUANTITY | ENGR. EST. | AVERAGE BID | AWARDED BID |
|----------------|--|---------------------------------------|----------|-------------------|------------|-------------|-------------|
| ===== | 518-01250 | Br Expan Cover Plate | | Lin Foot | ===== | | |
| NHPP0253-290 | I25 @ 58TH AND 62ND | | 03/02/23 | 32.00 | 500.00 | 599.69 | 470.00 |
| | WEIGHTED AVERAGE FOR THE FIRST QUARTER | | | 32.00 | 500.00 | 599.69 | 470.00 |
| | WEIGHTED AVERAGE FOR THE YEAR | | | 32.00 | 500.00 | 599.69 | 470.00 |
| ===== | 518-03000 | Saw and Seal Br Joint | | Lin Foot | ===== | | |
| STA172A-022 | SH 172 IGNACIO TO ELMORE'S CO | | 01/12/23 | 97.00 | 44.00 | 43.48 | 42.76 |
| NHPP0701-250 | I-70B: DDI TO 24 RD, MAIN ST | | 01/12/23 | 438.00 | 25.00 | 35.95 | 25.90 |
| NHPPR100-383 | I70 OVER WASHINGTON ST | | 01/26/23 | 391.00 | 30.00 | 37.85 | 40.00 |
| NHPP0253-290 | I25 @ 58TH AND 62ND | | 03/02/23 | 4,691.00 | 30.00 | 14.00 | 16.00 |
| | WEIGHTED AVERAGE FOR THE FIRST QUARTER | | | 5,617.00 | 29.85 | 17.25 | 18.90 |
| | WEIGHTED AVERAGE FOR THE YEAR | | | 5,617.00 | 29.85 | 17.25 | 18.90 |
| ===== | 519-03035 | Place Thin Bond Overlay (Poly Conc) | | Sq Yard | ===== | | |
| NHPPR100-383 | I70 OVER WASHINGTON ST | | 01/26/23 | 320.00 | 60.00 | 290.01 | 187.00 |
| NHPP0253-290 | I25 @ 58TH AND 62ND | | 03/02/23 | 11,173.00 | 40.00 | 53.76 | 48.00 |
| | WEIGHTED AVERAGE FOR THE FIRST QUARTER | | | 11,493.00 | 40.56 | 60.34 | 51.87 |
| | WEIGHTED AVERAGE FOR THE YEAR | | | 11,493.00 | 40.56 | 60.34 | 51.87 |
| ===== | 519-03055 | Furnish Thin Bond Overlay (Poly Conc) | | Cubic Foot | ===== | | |
| NHPPR100-383 | I70 OVER WASHINGTON ST | | 01/26/23 | 240.00 | 135.00 | 284.52 | 180.00 |
| NHPP0253-290 | I25 @ 58TH AND 62ND | | 03/02/23 | 10,336.00 | 135.00 | 138.52 | 119.75 |
| | WEIGHTED AVERAGE FOR THE FIRST QUARTER | | | 10,576.00 | 135.00 | 141.83 | 121.12 |
| | WEIGHTED AVERAGE FOR THE YEAR | | | 10,576.00 | 135.00 | 141.83 | 121.12 |
| ===== | 521-00000 | Slurry Cut-Off Wall | | Sq Foot | ===== | | |
| STA172A-022 | SH 172 IGNACIO TO ELMORE'S CO | | 01/12/23 | 1,680.00 | 25.00 | 37.41 | 35.32 |
| | WEIGHTED AVERAGE FOR THE FIRST QUARTER | | | 1,680.00 | 25.00 | 37.41 | 35.32 |
| | WEIGHTED AVERAGE FOR THE YEAR | | | 1,680.00 | 25.00 | 37.41 | 35.32 |

COLORADO DEPARTMENT OF TRANSPORTATION
 ITEM UNIT COSTS BY PROJECTS -- 2023 COST DATA

12:26 Wednesday, May 17, 2023 59

| PROJECT NUMBER | ITEM NUMBER/ PROJECT LOCATION | ITEM DESCRIPTION/ PROJECT LOCATION | DATE LET | UNIT/ QUANTITY | ENGR. EST. | AVERAGE BID | AWARDED BID |
|----------------|--|---------------------------------------|----------|-------------------|------------|-------------|-------------|
| ===== | 601-01000 | Conc CL B | | Cubic Yard | ===== | | |
| NHPP0253-296 | | I-25 @ LCR 16 (MP 253.8-254.5 | 02/07/23 | 4.00 | 1036.84 | 1109.42 | 1109.42 |
| | WEIGHTED AVERAGE FOR THE FIRST QUARTER | | | 4.00 | 1036.84 | 1109.42 | 1109.42 |
| | WEIGHTED AVERAGE FOR THE YEAR | | | 4.00 | 1036.84 | 1109.42 | 1109.42 |
| ===== | 601-01050 | Conc CL B (Wall) | | Cubic Yard | ===== | | |
| C0881-036 | | R1 CURB RAMPS-SH88B & US285D | 02/16/23 | 1.00 | 5000.00 | 2315.00 | 3000.00 |
| | WEIGHTED AVERAGE FOR THE FIRST QUARTER | | | 1.00 | 5000.00 | 2315.00 | 3000.00 |
| | WEIGHTED AVERAGE FOR THE YEAR | | | 1.00 | 5000.00 | 2315.00 | 3000.00 |
| ===== | 601-03000 | Conc CL D | | Cubic Yard | ===== | | |
| STA172A-022 | | SH 172 IGNACIO TO ELMORE'S CO | 01/12/23 | 28.00 | 1000.00 | 1207.63 | 1225.25 |
| NHPP0253-296 | | I-25 @ LCR 16 (MP 253.8-254.5 | 02/07/23 | 45.00 | 987.05 | 1056.14 | 1056.14 |
| C0703-498 | | EISENHOWER JOHNSON MEMORIAL T | 02/16/23 | 8.00 | 2000.00 | 3104.84 | 4200.00 |
| C1601-084 | | US 160 SECTION3 PRIORITY CULV | 02/16/23 | 45.00 | 1800.00 | 2301.36 | 3000.00 |
| | WEIGHTED AVERAGE FOR THE FIRST QUARTER | | | 126.00 | 1344.58 | 1845.54 | 1987.57 |
| | WEIGHTED AVERAGE FOR THE YEAR | | | 126.00 | 1344.58 | 1845.54 | 1987.57 |
| ===== | 601-03050 | Conc CL D (Wall) | | Cubic Yard | ===== | | |
| STA1381-011 | | SH 138 STERLING NORTH PART 2 | 02/16/23 | 11.10 | 900.00 | 6000.00 | 6000.00 |
| NHPP R100-376 | | VARIOUS LOCATIONS IN REGION 1 | 03/30/23 | 49.00 | 1000.00 | 2486.03 | 1850.00 |
| | WEIGHTED AVERAGE FOR THE FIRST QUARTER | | | 60.10 | 981.53 | 2843.55 | 2616.47 |
| | WEIGHTED AVERAGE FOR THE YEAR | | | 60.10 | 981.53 | 2843.55 | 2616.47 |
| ===== | 601-03056 | Conc CL DF | | Cubic Yard | ===== | | |
| STA172A-022 | | SH 172 IGNACIO TO ELMORE'S CO | 01/12/23 | 17.00 | 750.00 | 1911.88 | 1943.75 |
| NHPPR100-383 | | I70 OVER WASHINGTON ST | 01/26/23 | 10.00 | 1000.00 | 4370.05 | 2300.00 |

COLORADO DEPARTMENT OF TRANSPORTATION
ITEM UNIT COSTS BY PROJECTS -- 2023 COST DATA

12:26 Wednesday, May 17, 2023 60

| PROJECT NUMBER | ITEM NUMBER/ PROJECT LOCATION | ITEM DESCRIPTION/ PROJECT LOCATION | DATE LET | UNIT/ QUANTITY | ENGR. EST. | AVERAGE BID | AWARDED BID |
|----------------|----------------------------------|--|----------|-------------------|------------|-------------|-------------|
| ===== | 601-03056 | Conc CL DF | | Cubic Yard | ===== | | |
| C0703-498 | | EISENHOWER JOHNSON MEMORIAL T | 02/16/23 | 120.00 | 892.23 | 1758.50 | 2000.00 |
| C1601-084 | | US 160 SECTION3 PRIORITY CULV | 02/16/23 | 29.00 | 1800.00 | 1702.33 | 1700.00 |
| | | WEIGHTED AVERAGE FOR THE FIRST QUARTER | | 176.00 | 1034.19 | 1925.11 | 1962.18 |
| | | WEIGHTED AVERAGE FOR THE YEAR | | 176.00 | 1034.19 | 1925.11 | 1962.18 |
| ===== | 601-03057 | Conc CL DR | | Cubic Yard | ===== | | |
| NHPPR100-383 | | I70 OVER WASHINGTON ST | 01/26/23 | 49.00 | 2500.00 | 3360.67 | 2825.00 |
| NHPP0253-290 | | I25 @ 58TH AND 62ND | 03/02/23 | 128.00 | 2500.00 | 3171.48 | 2000.00 |
| STA257A-008 | | SH 257 WINDSOR RESURFACING | 03/30/23 | 2.00 | 3000.00 | 6700.00 | 5250.00 |
| ER0703-524 | | STRUCTURE F-13-P, EB I-70 EXI | 03/31/23 | 22.00 | 3163.00 | 6828.78 | 3163.00 |
| | | WEIGHTED AVERAGE FOR THE FIRST QUARTER | | 201.00 | 2577.54 | 3642.87 | 2360.75 |
| | | WEIGHTED AVERAGE FOR THE YEAR | | 201.00 | 2577.54 | 3642.87 | 2360.75 |
| ===== | 601-06102 | Concrete (Patching) | | Cubic Foot | ===== | | |
| NHPP0253-290 | | I25 @ 58TH AND 62ND | 03/02/23 | 22.00 | 2200.00 | 697.99 | 415.00 |
| STA257A-008 | | SH 257 WINDSOR RESURFACING | 03/30/23 | 59.00 | 250.00 | 952.50 | 745.00 |
| | | WEIGHTED AVERAGE FOR THE FIRST QUARTER | | 81.00 | 779.63 | 861.21 | 655.37 |
| | | WEIGHTED AVERAGE FOR THE YEAR | | 81.00 | 779.63 | 861.21 | 655.37 |
| ===== | 601-06150 | Conc (Patching) | | Sq Foot | ===== | | |
| STA172A-022 | | SH 172 IGNACIO TO ELMORE'S CO | 01/12/23 | 10.00 | 200.00 | 373.08 | 489.15 |
| C0703-498 | | EISENHOWER JOHNSON MEMORIAL T | 02/16/23 | 728.00 | 150.00 | 187.91 | 220.00 |
| | | WEIGHTED AVERAGE FOR THE FIRST QUARTER | | 738.00 | 150.68 | 189.59 | 223.65 |
| | | WEIGHTED AVERAGE FOR THE YEAR | | 738.00 | 150.68 | 189.59 | 223.65 |
| ===== | 601-40000 | Masonry Veneer | | Sq Foot | ===== | | |
| C0703-498 | | EISENHOWER JOHNSON MEMORIAL T | 02/16/23 | 538.00 | 18.00 | 137.44 | 90.00 |
| | | WEIGHTED AVERAGE FOR THE FIRST QUARTER | | 538.00 | 18.00 | 137.44 | 90.00 |
| | | WEIGHTED AVERAGE FOR THE YEAR | | 538.00 | 18.00 | 137.44 | 90.00 |

COLORADO DEPARTMENT OF TRANSPORTATION
ITEM UNIT COSTS BY PROJECTS -- 2023 COST DATA

12:26 Wednesday, May 17, 2023 61

| PROJECT NUMBER | ITEM NUMBER/ PROJECT LOCATION | ITEM DESCRIPTION/ PROJECT LOCATION | DATE LET | UNIT/ QUANTITY | ENGR. EST. | AVERAGE BID | AWARDED BID |
|----------------|----------------------------------|---------------------------------------|----------|-------------------|------------|-------------|-------------|
| ===== | 601-40002 | Masonry Veneer (Brick) | | Sq Foot | ===== | ===== | ===== |
| C0703-498 | | EISENHOWER JOHNSON MEMORIAL T | 02/16/23 | 950.00 | 50.00 | 95.15 | 100.00 |
| | WEIGHTED | AVERAGE FOR THE FIRST QUARTER | | 950.00 | 50.00 | 95.15 | 100.00 |
| | | WEIGHTED AVERAGE FOR THE YEAR | | 950.00 | 50.00 | 95.15 | 100.00 |
| ===== | 601-40300 | Struct Conc Coating | | Sq Yard | ===== | ===== | ===== |
| C0703-498 | | EISENHOWER JOHNSON MEMORIAL T | 02/16/23 | 792.00 | 20.00 | 35.98 | 42.00 |
| NHPP R100-376 | | VARIOUS LOCATIONS IN REGION 1 | 03/30/23 | 648.00 | 20.49 | 18.13 | 3.00 |
| | WEIGHTED | AVERAGE FOR THE FIRST QUARTER | | 1,440.00 | 20.22 | 29.68 | 24.45 |
| | | WEIGHTED AVERAGE FOR THE YEAR | | 1,440.00 | 20.22 | 29.68 | 24.45 |
| ===== | 601-40301 | Struct Conc Coating | | Sq Foot | ===== | ===== | ===== |
| C133A-052 | | SH 133 ROCKFALL N OF MCCLURE | 02/16/23 | 8,110.00 | 1.00 | 6.22 | 15.00 |
| | WEIGHTED | AVERAGE FOR THE FIRST QUARTER | | 8,110.00 | 1.00 | 6.22 | 15.00 |
| | | WEIGHTED AVERAGE FOR THE YEAR | | 8,110.00 | 1.00 | 6.22 | 15.00 |
| ===== | 601-40400 | Struct Conc Stain | | Sq Yard | ===== | ===== | ===== |
| NHPP0253-296 | | I-25 @ LCR 16 (MP 253.8-254.5) | 02/07/23 | 104.00 | 18.10 | 19.37 | 19.37 |
| | WEIGHTED | AVERAGE FOR THE FIRST QUARTER | | 104.00 | 18.10 | 19.37 | 19.37 |
| | | WEIGHTED AVERAGE FOR THE YEAR | | 104.00 | 18.10 | 19.37 | 19.37 |
| ===== | 601-51005 | Galvanic Anodes | | Each | ===== | ===== | ===== |
| STA257A-008 | | SH 257 WINDSOR RESURFACING | 03/30/23 | 78.00 | 35.00 | 67.25 | 52.50 |
| ER0703-524 | | STRUCTURE F-13-P, EB I-70 EXI | 03/31/23 | 825.00 | 35.00 | 37.77 | 35.00 |
| | WEIGHTED | AVERAGE FOR THE FIRST QUARTER | | 903.00 | 35.00 | 39.52 | 36.51 |
| | | WEIGHTED AVERAGE FOR THE YEAR | | 903.00 | 35.00 | 39.52 | 36.51 |

| PROJECT NUMBER | ITEM NUMBER/ PROJECT LOCATION | ITEM DESCRIPTION/ PROJECT LOCATION | DATE LET | UNIT/ QUANTITY | ENGR. EST. | AVERAGE BID | AWARDED BID |
|----------------|----------------------------------|--|----------|-------------------|------------|-------------|-------------|
| ===== | 602-00000 | Reinf Steel | | Pound | ===== | | |
| NHPP0253-296 | | I-25 @ LCR 16 (MP 253.8-254.5 | 02/07/23 | 280.00 | 2.56 | 2.74 | 2.74 |
| C0703-498 | | EISENHOWER JOHNSON MEMORIAL T | 02/16/23 | 2,667.00 | 3.00 | 4.82 | 6.00 |
| STA1381-011 | | SH 138 STERLING NORTH PART 2 | 02/16/23 | 2,090.00 | 2.00 | 8.00 | 8.00 |
| STA257A-008 | | SH 257 WINDSOR RESURFACING | 03/30/23 | 138.00 | 4.00 | 12.25 | 9.50 |
| ER0703-524 | | STRUCTURE F-13-P, EB I-70 EXI | 03/31/23 | 963.00 | 4.00 | 8.20 | 4.00 |
| | | WEIGHTED AVERAGE FOR THE FIRST QUARTER | | 6,138.00 | 2.82 | 6.14 | 6.30 |
| | | WEIGHTED AVERAGE FOR THE YEAR | | 6,138.00 | 2.82 | 6.14 | 6.30 |
| ===== | 602-00020 | Reinf Steel (Epoxy) | | Pound | ===== | | |
| STA172A-022 | | SH 172 IGNACIO TO ELMORE'S CO | 01/12/23 | 3,297.00 | 4.00 | 1.58 | 1.60 |
| NHPPR100-383 | | I70 OVER WASHINGTON ST | 01/26/23 | 6,135.00 | 3.00 | 3.21 | 4.00 |
| NHPP0253-296 | | I-25 @ LCR 16 (MP 253.8-254.5 | 02/07/23 | 2,890.00 | 1.83 | 1.96 | 1.96 |
| C0703-498 | | EISENHOWER JOHNSON MEMORIAL T | 02/16/23 | 6,940.00 | 2.00 | 5.91 | 8.00 |
| C1601-084 | | US 160 SECTION3 PRIORITY CULV | 02/16/23 | 2,588.00 | 5.00 | 4.67 | 2.50 |
| NHPP0253-290 | | I25 @ 58TH AND 62ND | 03/02/23 | 8,273.00 | 1.50 | 4.03 | 5.00 |
| NHPP R100-376 | | VARIOUS LOCATIONS IN REGION 1 | 03/30/23 | 1,590.00 | 2.50 | 2.89 | 3.00 |
| | | WEIGHTED AVERAGE FOR THE FIRST QUARTER | | 31,713.00 | 2.53 | 4.05 | 4.53 |
| | | WEIGHTED AVERAGE FOR THE YEAR | | 31,713.00 | 2.53 | 4.05 | 4.53 |
| ===== | 602-00060 | Reinf Steel Splice | | Each | ===== | | |
| C0703-498 | | EISENHOWER JOHNSON MEMORIAL T | 02/16/23 | 201.00 | 180.00 | 105.93 | 96.00 |
| | | WEIGHTED AVERAGE FOR THE FIRST QUARTER | | 201.00 | 180.00 | 105.93 | 96.00 |
| | | WEIGHTED AVERAGE FOR THE YEAR | | 201.00 | 180.00 | 105.93 | 96.00 |
| ===== | 602-00210 | Welded Wire Fabric | | Sq Yard | ===== | | |
| STA172A-022 | | SH 172 IGNACIO TO ELMORE'S CO | 01/12/23 | 246.00 | 20.00 | 27.47 | 27.93 |
| C1601-084 | | US 160 SECTION3 PRIORITY CULV | 02/16/23 | 340.00 | 50.00 | 34.24 | 52.25 |
| | | WEIGHTED AVERAGE FOR THE FIRST QUARTER | | 586.00 | 37.41 | 31.40 | 42.04 |
| | | WEIGHTED AVERAGE FOR THE YEAR | | 586.00 | 37.41 | 31.40 | 42.04 |

COLORADO DEPARTMENT OF TRANSPORTATION
ITEM UNIT COSTS BY PROJECTS -- 2023 COST DATA

12:26 Wednesday, May 17, 2023 63

| PROJECT NUMBER | ITEM NUMBER/ PROJECT LOCATION | ITEM DESCRIPTION/ PROJECT LOCATION | DATE LET | UNIT/ QUANTITY | ENGR. EST. | AVERAGE BID | AWARDED BID |
|--|--|---------------------------------------|----------|-------------------|------------|-------------|-------------|
| ===== 603-00010 Culvert Lining Sq Foot ===== | | | | | | | |
| C1601-084 | | US 160 SECTION3 PRIORITY CULV | 02/16/23 | 4,293.00 | 47.46 | 35.43 | 25.72 |
| | WEIGHTED AVERAGE FOR THE FIRST QUARTER | | | 4,293.00 | 47.46 | 35.43 | 25.72 |
| | WEIGHTED AVERAGE FOR THE YEAR | | | 4,293.00 | 47.46 | 35.43 | 25.72 |
| ===== 603-01185 18 In RCP (CIP) Lin Foot ===== | | | | | | | |
| NHPPR100-383 | | I70 OVER WASHINGTON ST | 01/26/23 | 120.00 | 150.00 | 363.19 | 265.00 |
| C0703-498 | | EISENHOWER JOHNSON MEMORIAL T | 02/16/23 | 56.00 | 160.00 | 232.53 | 320.00 |
| NHPP0701-256 | | I-70E/31.5 RD MESA COUNTY | 02/16/23 | 8.00 | 250.00 | 312.50 | 400.00 |
| STR194A-002 | | SH194A SUR. TREAT.& DRAI IMP | 03/09/23 | 53.00 | 130.00 | 296.50 | 263.00 |
| | WEIGHTED AVERAGE FOR THE FIRST QUARTER | | | 237.00 | 151.27 | 317.30 | 282.11 |
| | WEIGHTED AVERAGE FOR THE YEAR | | | 237.00 | 151.27 | 317.30 | 282.11 |
| ===== 603-01245 24 In RCP (CIP) Lin Foot ===== | | | | | | | |
| FSA0853-123 | | US 85 AND WCR 66 LEFT TURN AC | 01/26/23 | 73.00 | 175.00 | 246.00 | 210.00 |
| | WEIGHTED AVERAGE FOR THE FIRST QUARTER | | | 73.00 | 175.00 | 246.00 | 210.00 |
| | WEIGHTED AVERAGE FOR THE YEAR | | | 73.00 | 175.00 | 246.00 | 210.00 |
| ===== 603-01305 30 In RCP (CIP) Lin Foot ===== | | | | | | | |
| STR194A-002 | | SH194A SUR. TREAT.& DRAI IMP | 03/09/23 | 72.00 | 200.00 | 369.50 | 339.00 |
| | WEIGHTED AVERAGE FOR THE FIRST QUARTER | | | 72.00 | 200.00 | 369.50 | 339.00 |
| | WEIGHTED AVERAGE FOR THE YEAR | | | 72.00 | 200.00 | 369.50 | 339.00 |
| ===== 603-01365 36 In RCP (CIP) Lin Foot ===== | | | | | | | |
| STR194A-002 | | SH194A SUR. TREAT.& DRAI IMP | 03/09/23 | 201.00 | 240.00 | 411.00 | 372.00 |
| | WEIGHTED AVERAGE FOR THE FIRST QUARTER | | | 201.00 | 240.00 | 411.00 | 372.00 |
| | WEIGHTED AVERAGE FOR THE YEAR | | | 201.00 | 240.00 | 411.00 | 372.00 |

COLORADO DEPARTMENT OF TRANSPORTATION
ITEM UNIT COSTS BY PROJECTS -- 2023 COST DATA

12:26 Wednesday, May 17, 2023 64

| PROJECT NUMBER | ITEM NUMBER/ PROJECT LOCATION | ITEM DESCRIPTION/ PROJECT LOCATION | DATE LET | UNIT/ QUANTITY | ENGR. EST. | AVERAGE BID | AWARDED BID |
|----------------|--|---------------------------------------|----------|-------------------|------------|-------------|-------------|
| ===== | 603-01420 | 42 In RCP | | Lin Foot | ===== | | |
| STA1381-011 | | SH 138 STERLING NORTH PART 2 | 02/16/23 | 133.00 | 400.00 | 400.00 | 400.00 |
| | WEIGHTED AVERAGE FOR THE FIRST QUARTER | | | 133.00 | 400.00 | 400.00 | 400.00 |
| | WEIGHTED AVERAGE FOR THE YEAR | | | 133.00 | 400.00 | 400.00 | 400.00 |
| ===== | 603-01480 | 48 In RCP | | Lin Foot | ===== | | |
| STA1381-011 | | SH 138 STERLING NORTH PART 2 | 02/16/23 | 130.00 | 450.00 | 450.00 | 450.00 |
| C1601-084 | | US 160 SECTION3 PRIORITY CULV | 02/16/23 | 292.00 | 600.00 | 970.43 | 910.00 |
| | WEIGHTED AVERAGE FOR THE FIRST QUARTER | | | 422.00 | 553.79 | 875.67 | 768.29 |
| | WEIGHTED AVERAGE FOR THE YEAR | | | 422.00 | 553.79 | 875.67 | 768.29 |
| ===== | 603-02245 | 30x19 In RCP (CIP) | | Lin Foot | ===== | | |
| FSA0853-123 | | US 85 AND WCR 66 LEFT TURN AC | 01/26/23 | 130.00 | 200.00 | 295.67 | 240.00 |
| | WEIGHTED AVERAGE FOR THE FIRST QUARTER | | | 130.00 | 200.00 | 295.67 | 240.00 |
| | WEIGHTED AVERAGE FOR THE YEAR | | | 130.00 | 200.00 | 295.67 | 240.00 |
| ===== | 603-05018 | 18 In RCES | | Each | ===== | | |
| STR194A-002 | | SH194A SUR. TREAT.& DRAI IMP | 03/09/23 | 2.00 | 1800.00 | 3369.00 | 2738.00 |
| | WEIGHTED AVERAGE FOR THE FIRST QUARTER | | | 2.00 | 1800.00 | 3369.00 | 2738.00 |
| | WEIGHTED AVERAGE FOR THE YEAR | | | 2.00 | 1800.00 | 3369.00 | 2738.00 |
| ===== | 603-05024 | 24 In RCES | | Each | ===== | | |
| FSA0853-123 | | US 85 AND WCR 66 LEFT TURN AC | 01/26/23 | 1.00 | 1900.00 | 1767.67 | 1275.00 |
| | WEIGHTED AVERAGE FOR THE FIRST QUARTER | | | 1.00 | 1900.00 | 1767.67 | 1275.00 |
| | WEIGHTED AVERAGE FOR THE YEAR | | | 1.00 | 1900.00 | 1767.67 | 1275.00 |

COLORADO DEPARTMENT OF TRANSPORTATION
ITEM UNIT COSTS BY PROJECTS -- 2023 COST DATA

12:26 Wednesday, May 17, 2023 65

| PROJECT NUMBER | ITEM NUMBER/ PROJECT LOCATION | ITEM DESCRIPTION/ PROJECT LOCATION | DATE LET | UNIT/ QUANTITY | ENGR. EST. | AVERAGE BID | AWARDED BID |
|----------------|----------------------------------|---------------------------------------|----------|-------------------|------------|-------------|-------------|
| ===== | 603-05030 | 30 In RCES | | Each | ===== | ===== | ===== |
| STR194A-002 | | SH194A SUR. TREAT.& DRAI IMP | 03/09/23 | 4.00 | 2000.00 | 3802.00 | 3504.00 |
| | WEIGHTED | AVERAGE FOR THE FIRST QUARTER | | 4.00 | 2000.00 | 3802.00 | 3504.00 |
| | | WEIGHTED AVERAGE FOR THE YEAR | | 4.00 | 2000.00 | 3802.00 | 3504.00 |
| ===== | 603-05036 | 36 In RCES | | Each | ===== | ===== | ===== |
| STR194A-002 | | SH194A SUR. TREAT.& DRAI IMP | 03/09/23 | 8.00 | 2500.00 | 4221.00 | 3942.00 |
| | WEIGHTED | AVERAGE FOR THE FIRST QUARTER | | 8.00 | 2500.00 | 4221.00 | 3942.00 |
| | | WEIGHTED AVERAGE FOR THE YEAR | | 8.00 | 2500.00 | 4221.00 | 3942.00 |
| ===== | 603-05042 | 42 In RCES | | Each | ===== | ===== | ===== |
| STA1381-011 | | SH 138 STERLING NORTH PART 2 | 02/16/23 | 4.00 | 3500.00 | 4500.00 | 4500.00 |
| | WEIGHTED | AVERAGE FOR THE FIRST QUARTER | | 4.00 | 3500.00 | 4500.00 | 4500.00 |
| | | WEIGHTED AVERAGE FOR THE YEAR | | 4.00 | 3500.00 | 4500.00 | 4500.00 |
| ===== | 603-05048 | 48 In RCES | | Each | ===== | ===== | ===== |
| STA1381-011 | | SH 138 STERLING NORTH PART 2 | 02/16/23 | 4.00 | 4000.00 | 4800.00 | 4800.00 |
| | WEIGHTED | AVERAGE FOR THE FIRST QUARTER | | 4.00 | 4000.00 | 4800.00 | 4800.00 |
| | | WEIGHTED AVERAGE FOR THE YEAR | | 4.00 | 4000.00 | 4800.00 | 4800.00 |
| ===== | 603-05124 | 30x19 In RCES | | Each | ===== | ===== | ===== |
| FSA0853-123 | | US 85 AND WCR 66 LEFT TURN AC | 01/26/23 | 2.00 | 3200.00 | 2280.17 | 1350.00 |
| | WEIGHTED | AVERAGE FOR THE FIRST QUARTER | | 2.00 | 3200.00 | 2280.17 | 1350.00 |
| | | WEIGHTED AVERAGE FOR THE YEAR | | 2.00 | 3200.00 | 2280.17 | 1350.00 |
| ===== | 603-15021 | 21 In Equiv CSPA | | Lin Foot | ===== | ===== | ===== |
| STA172A-022 | | SH 172 IGNACIO TO ELMORE'S CO | 01/12/23 | 7.00 | 150.00 | 458.08 | 377.16 |
| | WEIGHTED | AVERAGE FOR THE FIRST QUARTER | | 7.00 | 150.00 | 458.08 | 377.16 |
| | | WEIGHTED AVERAGE FOR THE YEAR | | 7.00 | 150.00 | 458.08 | 377.16 |

COLORADO DEPARTMENT OF TRANSPORTATION
ITEM UNIT COSTS BY PROJECTS -- 2023 COST DATA

12:26 Wednesday, May 17, 2023 66

| PROJECT NUMBER | ITEM NUMBER/ PROJECT LOCATION | ITEM DESCRIPTION/ PROJECT LOCATION | DATE LET | UNIT/ QUANTITY | ENGR. EST. | AVERAGE BID | AWARDED BID |
|----------------|--|---------------------------------------|----------|-------------------|------------|-------------|-------------|
| ===== | 603-15030 | 30 In Equiv CSPA | | Lin Foot | ===== | | |
| STA172A-022 | | SH 172 IGNACIO TO ELMORE'S CO | 01/12/23 | 180.00 | 100.00 | 545.57 | 465.14 |
| | WEIGHTED AVERAGE FOR THE FIRST QUARTER | | | 180.00 | 100.00 | 545.57 | 465.14 |
| | WEIGHTED AVERAGE FOR THE YEAR | | | 180.00 | 100.00 | 545.57 | 465.14 |
| ===== | 603-15060 | 60 In Equiv CSPA | | Lin Foot | ===== | | |
| STA172A-022 | | SH 172 IGNACIO TO ELMORE'S CO | 01/12/23 | 104.00 | 300.00 | 958.42 | 796.84 |
| C1601-084 | | US 160 SECTION3 PRIORITY CULV | 02/16/23 | 100.00 | 500.00 | 971.00 | 790.00 |
| | WEIGHTED AVERAGE FOR THE FIRST QUARTER | | | 204.00 | 398.04 | 964.58 | 793.49 |
| | WEIGHTED AVERAGE FOR THE YEAR | | | 204.00 | 398.04 | 964.58 | 793.49 |
| ===== | 603-30024 | 24 In SES | | Each | ===== | | |
| C133A-052 | | SH 133 ROCKFALL N OF MCCLURE | 02/16/23 | 1.00 | 3500.00 | 1750.00 | 2000.00 |
| | WEIGHTED AVERAGE FOR THE FIRST QUARTER | | | 1.00 | 3500.00 | 1750.00 | 2000.00 |
| | WEIGHTED AVERAGE FOR THE YEAR | | | 1.00 | 3500.00 | 1750.00 | 2000.00 |
| ===== | 603-31330 | 30 In Equiv Arch SES | | Each | ===== | | |
| STA172A-022 | | SH 172 IGNACIO TO ELMORE'S CO | 01/12/23 | 1.00 | 1000.00 | 2837.25 | 2624.49 |
| | WEIGHTED AVERAGE FOR THE FIRST QUARTER | | | 1.00 | 1000.00 | 2837.25 | 2624.49 |
| | WEIGHTED AVERAGE FOR THE YEAR | | | 1.00 | 1000.00 | 2837.25 | 2624.49 |
| ===== | 603-33042 | 42 In Pipe Safety End Treat | | Each | ===== | | |
| STA1381-011 | | SH 138 STERLING NORTH PART 2 | 02/16/23 | 4.00 | 1500.00 | 1600.00 | 1600.00 |
| | WEIGHTED AVERAGE FOR THE FIRST QUARTER | | | 4.00 | 1500.00 | 1600.00 | 1600.00 |
| | WEIGHTED AVERAGE FOR THE YEAR | | | 4.00 | 1500.00 | 1600.00 | 1600.00 |

COLORADO DEPARTMENT OF TRANSPORTATION
ITEM UNIT COSTS BY PROJECTS -- 2023 COST DATA

12:26 Wednesday, May 17, 2023 67

| PROJECT NUMBER | ITEM NUMBER/ PROJECT LOCATION | ITEM DESCRIPTION/ PROJECT LOCATION | DATE LET | UNIT/ QUANTITY | ENGR. EST. | AVERAGE BID | AWARDED BID |
|----------------|----------------------------------|---------------------------------------|----------|-------------------|------------|-------------|-------------|
| ===== | 603-33048 | 48 In Pipe Safety End Treat | | Each | ===== | ===== | ===== |
| STA1381-011 | | SH 138 STERLING NORTH PART 2 | 02/16/23 | 4.00 | 1700.00 | 1700.00 | 1700.00 |
| | WEIGHTED | AVERAGE FOR THE FIRST QUARTER | | 4.00 | 1700.00 | 1700.00 | 1700.00 |
| | | WEIGHTED AVERAGE FOR THE YEAR | | 4.00 | 1700.00 | 1700.00 | 1700.00 |
| ===== | 603-50015 | 15 In Plastic Pipe | | Lin Foot | ===== | ===== | ===== |
| NHPP R100-376 | | VARIOUS LOCATIONS IN REGION 1 | 03/30/23 | 30.00 | 239.60 | 185.91 | 17.00 |
| | WEIGHTED | AVERAGE FOR THE FIRST QUARTER | | 30.00 | 239.60 | 185.91 | 17.00 |
| | | WEIGHTED AVERAGE FOR THE YEAR | | 30.00 | 239.60 | 185.91 | 17.00 |
| ===== | 603-70804 | 8x4 Ft CBC (Precast) | | Lin Foot | ===== | ===== | ===== |
| STA172A-022 | | SH 172 IGNACIO TO ELMORE'S CO | 01/12/23 | 108.00 | 1100.00 | 2691.06 | 2882.12 |
| | WEIGHTED | AVERAGE FOR THE FIRST QUARTER | | 108.00 | 1100.00 | 2691.06 | 2882.12 |
| | | WEIGHTED AVERAGE FOR THE YEAR | | 108.00 | 1100.00 | 2691.06 | 2882.12 |
| ===== | 604-00305 | Inlet Ty C (5 Ft) | | Each | ===== | ===== | ===== |
| NHPP0253-296 | | I-25 @ LCR 16 (MP 253.8-254.5) | 02/07/23 | 1.00 | 6307.29 | 6748.81 | 6748.81 |
| | WEIGHTED | AVERAGE FOR THE FIRST QUARTER | | 1.00 | 6307.29 | 6748.81 | 6748.81 |
| | | WEIGHTED AVERAGE FOR THE YEAR | | 1.00 | 6307.29 | 6748.81 | 6748.81 |
| ===== | 604-00310 | Inlet Ty C (10 Ft) | | Each | ===== | ===== | ===== |
| NHPP0253-296 | | I-25 @ LCR 16 (MP 253.8-254.5) | 02/07/23 | 2.00 | 6897.07 | 7379.88 | 7379.88 |
| C0703-498 | | EISENHOWER JOHNSON MEMORIAL T | 02/16/23 | 1.00 | 6000.00 | 10202.24 | 13000.00 |
| NHPP0701-256 | | I-70B/31.5 RD MESA COUNTY | 02/16/23 | 1.00 | 5600.00 | 9050.00 | 8000.00 |
| | WEIGHTED | AVERAGE FOR THE FIRST QUARTER | | 4.00 | 6348.54 | 9066.64 | 8939.94 |
| | | WEIGHTED AVERAGE FOR THE YEAR | | 4.00 | 6348.54 | 9066.64 | 8939.94 |

COLORADO DEPARTMENT OF TRANSPORTATION
ITEM UNIT COSTS BY PROJECTS -- 2023 COST DATA

12:26 Wednesday, May 17, 2023 68

| PROJECT NUMBER | ITEM NUMBER/ PROJECT LOCATION | ITEM DESCRIPTION/ PROJECT LOCATION | DATE LET | UNIT/ QUANTITY | ENGR. EST. | AVERAGE BID | AWARDED BID |
|-----------------|--|---------------------------------------|----------|-------------------|------------|-------------|-------------|
| ===== 604-00505 | | Inlet Ty D (5 Ft) | | Each | | | |
| STA172A-022 | | SH 172 IGNACIO TO ELMORE'S CO | 01/12/23 | 2.00 | 15000.00 | 12042.54 | 8955.07 |
| FSA0853-123 | | US 85 AND WCR 66 LEFT TURN AC | 01/26/23 | 1.00 | 6000.00 | 8796.17 | 8000.00 |
| NHPP0253-296 | | I-25 @ LCR 16 (MP 253.8-254.5 | 02/07/23 | 1.00 | 7554.25 | 8083.07 | 8083.07 |
| C133A-052 | | SH 133 ROCKFALL N OF MCCLURE | 02/16/23 | 1.00 | 9000.00 | 7712.50 | 12000.00 |
| | WEIGHTED AVERAGE FOR THE FIRST QUARTER | | | 5.00 | 10510.85 | 9325.35 | 9198.64 |
| | WEIGHTED AVERAGE FOR THE YEAR | | | 5.00 | 10510.85 | 9325.35 | 9198.64 |
| ===== 604-13005 | | Inlet Ty 13 (5 Ft) | | Each | | | |
| STA172A-022 | | SH 172 IGNACIO TO ELMORE'S CO | 01/12/23 | 1.00 | 15000.00 | 8860.11 | 8370.22 |
| | WEIGHTED AVERAGE FOR THE FIRST QUARTER | | | 1.00 | 15000.00 | 8860.11 | 8370.22 |
| | WEIGHTED AVERAGE FOR THE YEAR | | | 1.00 | 15000.00 | 8860.11 | 8370.22 |
| ===== 604-16050 | | Inlet Ty 16 (S) (Spec) | | Each | | | |
| NHPP0253-296 | | I-25 @ LCR 16 (MP 253.8-254.5 | 02/07/23 | 2.00 | 11634.85 | 12449.31 | 12449.31 |
| | WEIGHTED AVERAGE FOR THE FIRST QUARTER | | | 2.00 | 11634.85 | 12449.31 | 12449.31 |
| | WEIGHTED AVERAGE FOR THE YEAR | | | 2.00 | 11634.85 | 12449.31 | 12449.31 |
| ===== 604-19105 | | Inlet Ty R L5 (5 Ft) | | Each | | | |
| NHPP0253-296 | | I-25 @ LCR 16 (MP 253.8-254.5 | 02/07/23 | 2.00 | 8195.83 | 8769.55 | 8769.55 |
| | WEIGHTED AVERAGE FOR THE FIRST QUARTER | | | 2.00 | 8195.83 | 8769.55 | 8769.55 |
| | WEIGHTED AVERAGE FOR THE YEAR | | | 2.00 | 8195.83 | 8769.55 | 8769.55 |
| ===== 604-19110 | | Inlet Ty R L5 (10 Ft) | | Each | | | |
| NHPP0253-296 | | I-25 @ LCR 16 (MP 253.8-254.5 | 02/07/23 | 1.00 | 15240.30 | 16307.14 | 16307.14 |
| | WEIGHTED AVERAGE FOR THE FIRST QUARTER | | | 1.00 | 15240.30 | 16307.14 | 16307.14 |
| | WEIGHTED AVERAGE FOR THE YEAR | | | 1.00 | 15240.30 | 16307.14 | 16307.14 |

COLORADO DEPARTMENT OF TRANSPORTATION
ITEM UNIT COSTS BY PROJECTS -- 2023 COST DATA

12:26 Wednesday, May 17, 2023 69

| PROJECT NUMBER | ITEM NUMBER/ PROJECT LOCATION | ITEM DESCRIPTION/ PROJECT LOCATION | DATE LET | UNIT/ QUANTITY | ENGR. EST. | AVERAGE BID | AWARDED BID |
|----------------|----------------------------------|---------------------------------------|----------|-------------------|------------|-------------|-------------|
| ===== | 604-26005 | Vane Grate Inlet (D) (5 Ft) | | Each | ===== | ===== | ===== |
| NHPPR100-383 | | I70 OVER WASHINGTON ST | 01/26/23 | 1.00 | 8000.00 | 14254.43 | 21000.00 |
| | WEIGHTED | AVERAGE FOR THE FIRST QUARTER | | 1.00 | 8000.00 | 14254.43 | 21000.00 |
| | | WEIGHTED AVERAGE FOR THE YEAR | | 1.00 | 8000.00 | 14254.43 | 21000.00 |
| ===== | 604-30005 | MH Slab Base (5 Ft) | | Each | ===== | ===== | ===== |
| NHPP0253-296 | | I-25 @ LCR 16 (MP 253.8-254.5 | 02/07/23 | 1.00 | 6878.87 | 7360.40 | 7360.40 |
| | WEIGHTED | AVERAGE FOR THE FIRST QUARTER | | 1.00 | 6878.87 | 7360.40 | 7360.40 |
| | | WEIGHTED AVERAGE FOR THE YEAR | | 1.00 | 6878.87 | 7360.40 | 7360.40 |
| ===== | 604-30010 | MH Slab Base (10 Ft) | | Each | ===== | ===== | ===== |
| NHPP0253-296 | | I-25 @ LCR 16 (MP 253.8-254.5 | 02/07/23 | 2.00 | 10530.75 | 11267.92 | 11267.92 |
| | WEIGHTED | AVERAGE FOR THE FIRST QUARTER | | 2.00 | 10530.75 | 11267.92 | 11267.92 |
| | | WEIGHTED AVERAGE FOR THE YEAR | | 2.00 | 10530.75 | 11267.92 | 11267.92 |
| ===== | 604-30015 | MH Slab Base (15 Ft) | | Each | ===== | ===== | ===== |
| NHPP0253-296 | | I-25 @ LCR 16 (MP 253.8-254.5 | 02/07/23 | 2.00 | 16017.80 | 17139.08 | 17139.08 |
| | WEIGHTED | AVERAGE FOR THE FIRST QUARTER | | 2.00 | 16017.80 | 17139.08 | 17139.08 |
| | | WEIGHTED AVERAGE FOR THE YEAR | | 2.00 | 16017.80 | 17139.08 | 17139.08 |
| ===== | 604-30020 | MH Slab Base (20 Ft) | | Each | ===== | ===== | ===== |
| NHPP0253-296 | | I-25 @ LCR 16 (MP 253.8-254.5 | 02/07/23 | 1.00 | 17835.98 | 19084.53 | 19084.53 |
| | WEIGHTED | AVERAGE FOR THE FIRST QUARTER | | 1.00 | 17835.98 | 19084.53 | 19084.53 |
| | | WEIGHTED AVERAGE FOR THE YEAR | | 1.00 | 17835.98 | 19084.53 | 19084.53 |
| ===== | 604-50200 | MH R and C | | Each | ===== | ===== | ===== |
| STA066A-008 | | SH 66 @ WCR 7 | 01/26/23 | 1.00 | 750.00 | 3587.44 | 415.24 |
| | WEIGHTED | AVERAGE FOR THE FIRST QUARTER | | 1.00 | 750.00 | 3587.44 | 415.24 |
| | | WEIGHTED AVERAGE FOR THE YEAR | | 1.00 | 750.00 | 3587.44 | 415.24 |

| PROJECT NUMBER | ITEM NUMBER/ PROJECT LOCATION | ITEM DESCRIPTION/ PROJECT LOCATION | DATE LET | UNIT/ QUANTITY | ENGR. EST. | AVERAGE BID | AWARDED BID |
|----------------|--|---------------------------------------|----------|-------------------|------------|-------------|-------------|
| ===== | 604-83108 | 8 In PPS (PVC) | | Lin Foot | ===== | | |
| C 1601-086 | | MAPLE & CHESTNUT SIGNALS AT I | 02/16/23 | 50.00 | 50.00 | 100.00 | 100.00 |
| | WEIGHTED AVERAGE FOR THE FIRST QUARTER | | | 50.00 | 50.00 | 100.00 | 100.00 |
| | WEIGHTED AVERAGE FOR THE YEAR | | | 50.00 | 50.00 | 100.00 | 100.00 |
| ===== | 605-00061 | 6 In PP Underdrain (Special) | | Lin Foot | ===== | | |
| STA172A-022 | | SH 172 IGNACIO TO ELMORE'S CO | 01/12/23 | 420.00 | 30.00 | 97.71 | 50.42 |
| | WEIGHTED AVERAGE FOR THE FIRST QUARTER | | | 420.00 | 30.00 | 97.71 | 50.42 |
| | WEIGHTED AVERAGE FOR THE YEAR | | | 420.00 | 30.00 | 97.71 | 50.42 |
| ===== | 606-00302 | Gdrail Ty 3 (31 In MGS) | | Lin Foot | ===== | | |
| STA172A-022 | | SH 172 IGNACIO TO ELMORE'S CO | 01/12/23 | 5,275.00 | 55.00 | 38.06 | 38.71 |
| NHPP0701-250 | | I-70B: DDI TO 24 RD, MAIN ST | 01/12/23 | 1,677.00 | 50.00 | 56.30 | 49.60 |
| SFTYR200-277 | | REGION 2 WIDE, VARIOUS HWY & | 01/19/23 | 545.00 | 80.00 | 70.00 | 85.00 |
| C0342-066 | | US 034A (MP 113-150) | 02/02/23 | 150.00 | 50.00 | 59.33 | 68.00 |
| C0703-498 | | EISENHOWER JOHNSON MEMORIAL T | 02/16/23 | 4,599.00 | 50.00 | 52.84 | 54.00 |
| STA1381-011 | | SH 138 STERLING NORTH PART 2 | 02/16/23 | 1,438.00 | 36.00 | 35.00 | 35.00 |
| SHE067A-044 | | SH 67F M.P. 56.5-57.6 AND SH | 03/02/23 | 875.00 | 40.00 | 50.67 | 50.67 |
| STR194A-002 | | SH194A SUR. TREAT.& DRAI IMP | 03/09/23 | 1,138.00 | 40.00 | 57.00 | 59.00 |
| STA257A-008 | | SH 257 WINDSOR RESURFACING | 03/30/23 | 787.50 | 35.00 | 39.50 | 37.00 |
| NHPP R100-376 | | VARIOUS LOCATIONS IN REGION 1 | 03/30/23 | 4,414.00 | 40.70 | 49.79 | 59.00 |
| | WEIGHTED AVERAGE FOR THE FIRST QUARTER | | | 20,898.50 | 47.59 | 48.57 | 49.94 |
| | WEIGHTED AVERAGE FOR THE YEAR | | | 20,898.50 | 47.59 | 48.57 | 49.94 |
| ===== | 606-00305 | Gdrail Ty 3 (Spec) | | Lin Foot | ===== | | |
| C0703-498 | | EISENHOWER JOHNSON MEMORIAL T | 02/16/23 | 84.00 | 80.60 | 183.66 | 190.00 |
| | WEIGHTED AVERAGE FOR THE FIRST QUARTER | | | 84.00 | 80.60 | 183.66 | 190.00 |
| | WEIGHTED AVERAGE FOR THE YEAR | | | 84.00 | 80.60 | 183.66 | 190.00 |
| ===== | 606-00710 | Gdrail Ty 7 (Sty CA) | | Lin Foot | ===== | | |
| NHPP0701-250 | | I-70B: DDI TO 24 RD, MAIN ST | 01/12/23 | 40.00 | 400.00 | 403.50 | 387.00 |

COLORADO DEPARTMENT OF TRANSPORTATION
ITEM UNIT COSTS BY PROJECTS -- 2023 COST DATA

12:26 Wednesday, May 17, 2023 71

| PROJECT NUMBER | ITEM NUMBER/ PROJECT LOCATION | ITEM DESCRIPTION/ PROJECT LOCATION | DATE LET | UNIT/ QUANTITY | ENGR. EST. | AVERAGE BID | AWARDED BID |
|----------------|--|---------------------------------------|----------|-------------------|------------|-------------|-------------|
| ===== | 606-00710 | Gdrail Ty 7 (Sty CA) | | Lin Foot | ===== | ===== | ===== |
| C133A-052 | | SH 133 ROCKFALL N OF MCCLURE | 02/16/23 | 2,160.00 | 220.00 | 196.10 | 190.00 |
| | WEIGHTED AVERAGE FOR THE FIRST QUARTER | | | 2,200.00 | 223.27 | 198.01 | 193.58 |
| | WEIGHTED AVERAGE FOR THE YEAR | | | 2,200.00 | 223.27 | 198.01 | 193.58 |
| ===== | 606-00910 | Guardrail Type 9 (Style CA) | | Lin Foot | ===== | ===== | ===== |
| NHPP0253-296 | | I-25 @ LCR 16 (MP 253.8-254.5 | 02/07/23 | 276.00 | 307.54 | 329.08 | 329.08 |
| C0703-498 | | EISENHOWER JOHNSON MEMORIAL T | 02/16/23 | 2,223.00 | 170.00 | 228.40 | 240.00 |
| STR194A-002 | | SH194A SUR. TREAT.& DRAI IMP | 03/09/23 | 220.00 | 200.00 | 370.50 | 361.00 |
| | WEIGHTED AVERAGE FOR THE FIRST QUARTER | | | 2,719.00 | 186.39 | 240.63 | 258.83 |
| | WEIGHTED AVERAGE FOR THE YEAR | | | 2,719.00 | 186.39 | 240.63 | 258.83 |
| ===== | 606-00915 | Guardrail Type 9 (Style CG) | | Lin Foot | ===== | ===== | ===== |
| NHPP0253-296 | | I-25 @ LCR 16 (MP 253.8-254.5 | 02/07/23 | 328.00 | 331.95 | 355.19 | 355.19 |
| | WEIGHTED AVERAGE FOR THE FIRST QUARTER | | | 328.00 | 331.95 | 355.19 | 355.19 |
| | WEIGHTED AVERAGE FOR THE YEAR | | | 328.00 | 331.95 | 355.19 | 355.19 |
| ===== | 606-01340 | End Anchor Ty 3D | | Each | ===== | ===== | ===== |
| C0703-498 | | EISENHOWER JOHNSON MEMORIAL T | 02/16/23 | 9.00 | 2000.00 | 1552.18 | 1600.00 |
| STR194A-002 | | SH194A SUR. TREAT.& DRAI IMP | 03/09/23 | 1.00 | 1600.00 | 2577.00 | 3154.00 |
| NHPP R100-376 | | VARIOUS LOCATIONS IN REGION 1 | 03/30/23 | 2.00 | 1543.96 | 3151.56 | 3100.00 |
| | WEIGHTED AVERAGE FOR THE FIRST QUARTER | | | 12.00 | 1890.66 | 1808.16 | 1979.50 |
| | WEIGHTED AVERAGE FOR THE YEAR | | | 12.00 | 1890.66 | 1808.16 | 1979.50 |
| ===== | 606-01370 | Transition Ty 3G | | Each | ===== | ===== | ===== |
| STA172A-022 | | SH 172 IGNACIO TO ELMORE'S CO | 01/12/23 | 4.00 | 3500.00 | 4161.10 | 4232.20 |
| NHPP0701-250 | | I-70B: DDI TO 24 RD, MAIN ST | 01/12/23 | 1.00 | 7000.00 | 5795.00 | 5290.00 |
| C0703-498 | | EISENHOWER JOHNSON MEMORIAL T | 02/16/23 | 9.00 | 5000.00 | 5192.97 | 5300.00 |
| STA1381-011 | | SH 138 STERLING NORTH PART 2 | 02/16/23 | 6.00 | 3600.00 | 3900.00 | 3900.00 |

COLORADO DEPARTMENT OF TRANSPORTATION
ITEM UNIT COSTS BY PROJECTS -- 2023 COST DATA

12:26 Wednesday, May 17, 2023 72

| PROJECT NUMBER | ITEM NUMBER/ PROJECT LOCATION | ITEM DESCRIPTION/ PROJECT LOCATION | DATE LET | UNIT/ QUANTITY | ENGR. EST. | AVERAGE BID | AWARDED BID |
|----------------|--|---------------------------------------|----------|-------------------|------------|-------------|-------------|
| ===== | 606-01370 | Transition Ty 3G | | Each ===== | | | |
| STR194A-002 | | SH194A SUR. TREAT.& DRAI IMP | 03/09/23 | 4.00 | 3500.00 | 4651.00 | 4802.00 |
| STA257A-008 | | SH 257 WINDSOR RESURFACING | 03/30/23 | 4.00 | 1500.00 | 4450.00 | 3800.00 |
| | WEIGHTED AVERAGE FOR THE FIRST QUARTER | | | 28.00 | 3842.86 | 4767.75 | 4561.67 |
| | WEIGHTED AVERAGE FOR THE YEAR | | | 28.00 | 3842.86 | 4767.75 | 4561.67 |
| ===== | 606-01371 | Transition Ty 3G (Spec) | | Each ===== | | | |
| NHPP0701-250 | | I-70B: DDI TO 24 RD, MAIN ST | 01/12/23 | 7.00 | 5000.00 | 6690.00 | 6080.00 |
| | WEIGHTED AVERAGE FOR THE FIRST QUARTER | | | 7.00 | 5000.00 | 6690.00 | 6080.00 |
| | WEIGHTED AVERAGE FOR THE YEAR | | | 7.00 | 5000.00 | 6690.00 | 6080.00 |
| ===== | 606-01372 | Transition Type GR9-GR3 | | Each ===== | | | |
| STR194A-002 | | SH194A SUR. TREAT.& DRAI IMP | 03/09/23 | 4.00 | 5000.00 | 8325.50 | 8651.00 |
| | WEIGHTED AVERAGE FOR THE FIRST QUARTER | | | 4.00 | 5000.00 | 8325.50 | 8651.00 |
| | WEIGHTED AVERAGE FOR THE YEAR | | | 4.00 | 5000.00 | 8325.50 | 8651.00 |
| ===== | 606-01380 | Transition Ty 3H | | Each ===== | | | |
| C0703-498 | | EISENHOWER JOHNSON MEMORIAL T | 02/16/23 | 6.00 | 2000.00 | 2244.50 | 2300.00 |
| | WEIGHTED AVERAGE FOR THE FIRST QUARTER | | | 6.00 | 2000.00 | 2244.50 | 2300.00 |
| | WEIGHTED AVERAGE FOR THE YEAR | | | 6.00 | 2000.00 | 2244.50 | 2300.00 |
| ===== | 606-01385 | Transition Ty 3J | | Each ===== | | | |
| STA172A-022 | | SH 172 IGNACIO TO ELMORE'S CO | 01/12/23 | 4.00 | 2500.00 | 1616.45 | 1642.90 |
| C0703-498 | | EISENHOWER JOHNSON MEMORIAL T | 02/16/23 | 3.00 | 2000.00 | 2290.55 | 2300.00 |
| STA257A-008 | | SH 257 WINDSOR RESURFACING | 03/30/23 | 1.00 | 1800.00 | 3750.00 | 3500.00 |
| | WEIGHTED AVERAGE FOR THE FIRST QUARTER | | | 8.00 | 2225.00 | 2160.35 | 2121.45 |
| | WEIGHTED AVERAGE FOR THE YEAR | | | 8.00 | 2225.00 | 2160.35 | 2121.45 |

COLORADO DEPARTMENT OF TRANSPORTATION
ITEM UNIT COSTS BY PROJECTS -- 2023 COST DATA

12:26 Wednesday, May 17, 2023 73

| PROJECT NUMBER | ITEM NUMBER/ PROJECT LOCATION | ITEM DESCRIPTION/ PROJECT LOCATION | DATE LET | UNIT/ QUANTITY | ENGR. EST. | AVERAGE BID | AWARDED BID |
|----------------|----------------------------------|--|----------|-------------------|------------|-------------|-------------|
| ===== | 606-01390 | End Anchor Ty 3K | | Each | ===== | ===== | ===== |
| STA172A-022 | | SH 172 IGNACIO TO ELMORE'S CO | 01/12/23 | 4.00 | 2500.00 | 2472.43 | 2514.86 |
| C0703-498 | | EISENHOWER JOHNSON MEMORIAL T | 02/16/23 | 6.00 | 2000.00 | 3308.57 | 3400.00 |
| STA257A-008 | | SH 257 WINDSOR RESURFACING | 03/30/23 | 1.00 | 2000.00 | 2775.00 | 2250.00 |
| | | WEIGHTED AVERAGE FOR THE FIRST QUARTER | | 11.00 | 2181.82 | 3031.56 | 2973.59 |
| | | WEIGHTED AVERAGE FOR THE YEAR | | 11.00 | 2181.82 | 3031.56 | 2973.59 |
| ===== | 606-01400 | Transition Type BR10M-GR3 | | Each | ===== | ===== | ===== |
| STA1381-011 | | SH 138 STERLING NORTH PART 2 | 02/16/23 | 4.00 | 5000.00 | 10000.00 | 10000.00 |
| STA257A-008 | | SH 257 WINDSOR RESURFACING | 03/30/23 | 4.00 | 4000.00 | 8200.00 | 9000.00 |
| | | WEIGHTED AVERAGE FOR THE FIRST QUARTER | | 8.00 | 4500.00 | 8800.00 | 9500.00 |
| | | WEIGHTED AVERAGE FOR THE YEAR | | 8.00 | 4500.00 | 8800.00 | 9500.00 |
| ===== | 606-01460 | Median Terminal | | Each | ===== | ===== | ===== |
| C0703-498 | | EISENHOWER JOHNSON MEMORIAL T | 02/16/23 | 14.00 | 12000.00 | 13949.92 | 14000.00 |
| | | WEIGHTED AVERAGE FOR THE FIRST QUARTER | | 14.00 | 12000.00 | 13949.92 | 14000.00 |
| | | WEIGHTED AVERAGE FOR THE YEAR | | 14.00 | 12000.00 | 13949.92 | 14000.00 |
| ===== | 606-02003 | End Anchor (Nonflared) | | Each | ===== | ===== | ===== |
| STA172A-022 | | SH 172 IGNACIO TO ELMORE'S CO | 01/12/23 | 26.00 | 4500.00 | 3598.99 | 3657.98 |
| NHPP0701-250 | | I-70B: DDI TO 24 RD, MAIN ST | 01/12/23 | 11.00 | 5000.00 | 6800.00 | 4500.00 |
| SFTYR200-277 | | REGION 2 WIDE, VARIOUS HWY & | 01/19/23 | 71.00 | 5000.00 | 5500.00 | 5500.00 |
| C0342-066 | | US 034A (MP 113-150) | 02/02/23 | 2.00 | 5000.00 | 4707.33 | 5522.00 |
| STA1381-011 | | SH 138 STERLING NORTH PART 2 | 02/16/23 | 10.00 | 3800.00 | 3650.00 | 3650.00 |
| SHE067A-044 | | SH 67F M.P. 56.5-57.6 AND SH | 03/02/23 | 2.00 | 5000.00 | 4747.25 | 4747.25 |
| STR194A-002 | | SH194A SUR. TREAT.& DRAI IMP | 03/09/23 | 13.00 | 3700.00 | 6905.00 | 5210.00 |
| STA257A-008 | | SH 257 WINDSOR RESURFACING | 03/30/23 | 3.00 | 3800.00 | 4350.00 | 4200.00 |
| NHPP R100-376 | | VARIOUS LOCATIONS IN REGION 1 | 03/30/23 | 2.00 | 4905.00 | 4722.93 | 5300.00 |
| | | WEIGHTED AVERAGE FOR THE FIRST QUARTER | | 140.00 | 4673.64 | 5246.32 | 4879.11 |
| | | WEIGHTED AVERAGE FOR THE YEAR | | 140.00 | 4673.64 | 5246.32 | 4879.11 |

COLORADO DEPARTMENT OF TRANSPORTATION
ITEM UNIT COSTS BY PROJECTS -- 2023 COST DATA

12:26 Wednesday, May 17, 2023 74

| PROJECT NUMBER | ITEM NUMBER/ PROJECT LOCATION | ITEM DESCRIPTION/ PROJECT LOCATION | DATE LET | UNIT/ QUANTITY | ENGR. EST. | AVERAGE BID | AWARDED BID |
|----------------|----------------------------------|---------------------------------------|----------|-------------------|------------|-------------|-------------|
| ===== | 606-02005 | End Anchor (Flared) | | Each | ===== | ===== | ===== |
| SFTYR200-277 | | REGION 2 WIDE, VARIOUS HWY & | 01/19/23 | 23.00 | 6500.00 | 6225.00 | 7250.00 |
| C0703-498 | | EISENHOWER JOHNSON MEMORIAL T | 02/16/23 | 3.00 | 6000.00 | 7526.70 | 7700.00 |
| | WEIGHTED | AVERAGE FOR THE FIRST QUARTER | | 26.00 | 6442.31 | 6438.01 | 7301.92 |
| | | WEIGHTED AVERAGE FOR THE YEAR | | 26.00 | 6442.31 | 6438.01 | 7301.92 |
| ===== | 606-10305 | Brdg Rail Ty 3 (Spec) | | Lin Foot | ===== | ===== | ===== |
| NHPP0701-250 | | I-70B: DDI TO 24 RD, MAIN ST | 01/12/23 | 50.00 | 50.00 | 210.50 | 171.00 |
| | WEIGHTED | AVERAGE FOR THE FIRST QUARTER | | 50.00 | 50.00 | 210.50 | 171.00 |
| | | WEIGHTED AVERAGE FOR THE YEAR | | 50.00 | 50.00 | 210.50 | 171.00 |
| ===== | 606-10700 | Brdg Rail Ty 7 | | Lin Foot | ===== | ===== | ===== |
| NHPPR100-383 | | I70 OVER WASHINGTON ST | 01/26/23 | 72.00 | 200.00 | 977.63 | 786.00 |
| | WEIGHTED | AVERAGE FOR THE FIRST QUARTER | | 72.00 | 200.00 | 977.63 | 786.00 |
| | | WEIGHTED AVERAGE FOR THE YEAR | | 72.00 | 200.00 | 977.63 | 786.00 |
| ===== | 606-11037 | Brdg Rail Ty 10R MASH | | Lin Foot | ===== | ===== | ===== |
| STA1381-011 | | SH 138 STERLING NORTH PART 2 | 02/16/23 | 78.00 | 225.00 | 230.00 | 230.00 |
| STA257A-008 | | SH 257 WINDSOR RESURFACING | 03/30/23 | 140.00 | 300.00 | 340.00 | 270.00 |
| | WEIGHTED | AVERAGE FOR THE FIRST QUARTER | | 218.00 | 273.17 | 316.03 | 255.69 |
| | | WEIGHTED AVERAGE FOR THE YEAR | | 218.00 | 273.17 | 316.03 | 255.69 |
| ===== | 607-00005 | End Post | | Each | ===== | ===== | ===== |
| STA172A-022 | | SH 172 IGNACIO TO ELMORE'S CO | 01/12/23 | 21.00 | 750.00 | 596.06 | 606.12 |
| | WEIGHTED | AVERAGE FOR THE FIRST QUARTER | | 21.00 | 750.00 | 596.06 | 606.12 |
| | | WEIGHTED AVERAGE FOR THE YEAR | | 21.00 | 750.00 | 596.06 | 606.12 |

COLORADO DEPARTMENT OF TRANSPORTATION
ITEM UNIT COSTS BY PROJECTS -- 2023 COST DATA

12:26 Wednesday, May 17, 2023 75

| PROJECT NUMBER | ITEM NUMBER/ PROJECT LOCATION | ITEM DESCRIPTION/ PROJECT LOCATION | DATE LET | UNIT/ QUANTITY | ENGR. EST. | AVERAGE BID | AWARDED BID |
|----------------|----------------------------------|---------------------------------------|----------|-------------------|------------|-------------|-------------|
| ===== | 607-00010 | Corner and Line Br Post | | Each | ===== | ===== | ===== |
| STA172A-022 | | SH 172 IGNACIO TO ELMORE'S CO | 01/12/23 | 16.00 | 10.00 | 855.92 | 869.83 |
| | WEIGHTED | AVERAGE FOR THE FIRST QUARTER | | 16.00 | 10.00 | 855.92 | 869.83 |
| | | WEIGHTED AVERAGE FOR THE YEAR | | 16.00 | 10.00 | 855.92 | 869.83 |
| ===== | 607-01000 | Fence BW MP | | Lin Foot | ===== | ===== | ===== |
| STA172A-022 | | SH 172 IGNACIO TO ELMORE'S CO | 01/12/23 | 400.00 | 10.00 | 4.72 | 4.79 |
| C1601-084 | | US 160 SECTION3 PRIORITY CULV | 02/16/23 | 185.00 | 20.00 | 29.13 | 25.00 |
| | WEIGHTED | AVERAGE FOR THE FIRST QUARTER | | 585.00 | 13.16 | 12.44 | 11.18 |
| | | WEIGHTED AVERAGE FOR THE YEAR | | 585.00 | 13.16 | 12.44 | 11.18 |
| ===== | 607-11525 | Fence (Plastic) | | Lin Foot | ===== | ===== | ===== |
| STA172A-022 | | SH 172 IGNACIO TO ELMORE'S CO | 01/12/23 | 495.00 | 5.00 | 3.71 | 3.77 |
| STA066A-008 | | SH 66 @ WCR 7 | 01/26/23 | 100.00 | 5.00 | 8.78 | 17.80 |
| C0703-498 | | EISENHOWER JOHNSON MEMORIAL T | 02/16/23 | 148.00 | 14.00 | 6.24 | 7.00 |
| C133A-052 | | SH 133 ROCKFALL N OF MCCLURE | 02/16/23 | 400.00 | 7.00 | 5.53 | 7.00 |
| C1601-084 | | US 160 SECTION3 PRIORITY CULV | 02/16/23 | 330.00 | 10.00 | 4.89 | 4.30 |
| STM C440-013 | | R3 EAGLE RESIDENCY ADA RAMP I | 02/16/23 | 300.00 | 7.00 | 0.50 | 0.50 |
| C0881-036 | | R1 CURB RAMPS-SH88B & US285D | 02/16/23 | 500.00 | 5.00 | 6.51 | 0.05 |
| STA257A-008 | | SH 257 WINDSOR RESURFACING | 03/30/23 | 530.00 | 6.00 | 3.63 | 4.25 |
| | WEIGHTED | AVERAGE FOR THE FIRST QUARTER | | 2,803.00 | 6.75 | 5.28 | 4.04 |
| | | WEIGHTED AVERAGE FOR THE YEAR | | 2,803.00 | 6.75 | 5.28 | 4.04 |
| ===== | 607-11560 | Debris Barrier | | Sq Foot | ===== | ===== | ===== |
| C133A-052 | | SH 133 ROCKFALL N OF MCCLURE | 02/16/23 | 368.00 | 170.00 | 459.21 | 790.00 |
| | WEIGHTED | AVERAGE FOR THE FIRST QUARTER | | 368.00 | 170.00 | 459.21 | 790.00 |
| | | WEIGHTED AVERAGE FOR THE YEAR | | 368.00 | 170.00 | 459.21 | 790.00 |
| ===== | 607-21300 | Fence Barrier MP | | Lin Foot | ===== | ===== | ===== |
| NHPP0701-250 | | I-70B: DDI TO 24 RD, MAIN ST | 01/12/23 | 800.00 | 30.00 | 13.75 | 20.50 |
| | WEIGHTED | AVERAGE FOR THE FIRST QUARTER | | 800.00 | 30.00 | 13.75 | 20.50 |
| | | WEIGHTED AVERAGE FOR THE YEAR | | 800.00 | 30.00 | 13.75 | 20.50 |

| PROJECT NUMBER | ITEM NUMBER/ PROJECT LOCATION | ITEM DESCRIPTION/ PROJECT LOCATION | DATE LET | UNIT/ QUANTITY | ENGR. EST. | AVERAGE BID | AWARDED BID |
|----------------|----------------------------------|---------------------------------------|----------|-------------------|------------|-------------|-------------|
| ===== | 607-53143 | Fence CL (Spec) (42 In) | | Lin Foot | ===== | | |
| NHPP R100-376 | | VARIOUS LOCATIONS IN REGION 1 | 03/30/23 | 204.00 | 80.00 | 139.17 | 135.00 |
| | WEIGHTED | AVERAGE FOR THE FIRST QUARTER | | 204.00 | 80.00 | 139.17 | 135.00 |
| | | WEIGHTED AVERAGE FOR THE YEAR | | 204.00 | 80.00 | 139.17 | 135.00 |
| ===== | 607-55040 | Mesh Anchor | | Each | ===== | | |
| C133A-052 | | SH 133 ROCKFALL N OF MCCLURE | 02/16/23 | 26.00 | 1300.00 | 2006.14 | 2000.00 |
| | WEIGHTED | AVERAGE FOR THE FIRST QUARTER | | 26.00 | 1300.00 | 2006.14 | 2000.00 |
| | | WEIGHTED AVERAGE FOR THE YEAR | | 26.00 | 1300.00 | 2006.14 | 2000.00 |
| ===== | 607-55050 | Mesh Anchor (Spec) | | Each | ===== | | |
| C133A-052 | | SH 133 ROCKFALL N OF MCCLURE | 02/16/23 | 13.00 | 2200.00 | 4483.36 | 5000.00 |
| | WEIGHTED | AVERAGE FOR THE FIRST QUARTER | | 13.00 | 2200.00 | 4483.36 | 5000.00 |
| | | WEIGHTED AVERAGE FOR THE YEAR | | 13.00 | 2200.00 | 4483.36 | 5000.00 |
| ===== | 607-55100 | Wire Mesh (Draped) | | Sq Foot | ===== | | |
| C133A-052 | | SH 133 ROCKFALL N OF MCCLURE | 02/16/23 | 15,100.00 | 4.00 | 7.11 | 9.40 |
| | WEIGHTED | AVERAGE FOR THE FIRST QUARTER | | 15,100.00 | 4.00 | 7.11 | 9.40 |
| | | WEIGHTED AVERAGE FOR THE YEAR | | 15,100.00 | 4.00 | 7.11 | 9.40 |
| ===== | 607-55104 | Wire Mesh (Special) | | Sq Foot | ===== | | |
| C133A-052 | | SH 133 ROCKFALL N OF MCCLURE | 02/16/23 | 21,700.00 | 10.00 | 9.42 | 11.60 |
| | WEIGHTED | AVERAGE FOR THE FIRST QUARTER | | 21,700.00 | 10.00 | 9.42 | 11.60 |
| | | WEIGHTED AVERAGE FOR THE YEAR | | 21,700.00 | 10.00 | 9.42 | 11.60 |
| ===== | 607-55110 | Safety Rail (Cable) | | Lin Foot | ===== | | |
| C0703-498 | | EISENHOWER JOHNSON MEMORIAL T | 02/16/23 | 87.00 | 100.00 | 136.80 | 140.00 |
| | WEIGHTED | AVERAGE FOR THE FIRST QUARTER | | 87.00 | 100.00 | 136.80 | 140.00 |
| | | WEIGHTED AVERAGE FOR THE YEAR | | 87.00 | 100.00 | 136.80 | 140.00 |

COLORADO DEPARTMENT OF TRANSPORTATION
ITEM UNIT COSTS BY PROJECTS -- 2023 COST DATA

12:26 Wednesday, May 17, 2023 77

| PROJECT NUMBER | ITEM NUMBER/ PROJECT LOCATION | ITEM DESCRIPTION/ PROJECT LOCATION | DATE LET | UNIT/ QUANTITY | ENGR. EST. | AVERAGE BID | AWARDED BID |
|----------------|----------------------------------|---------------------------------------|----------|-------------------|------------|-------------|-------------|
| ===== | 607-60120 | 20 Ft Gate | | Each | ===== | ===== | ===== |
| STA172A-022 | | SH 172 IGNACIO TO ELMORE'S CO | 01/12/23 | 3.00 | 900.00 | 1156.98 | 1173.96 |
| | WEIGHTED | AVERAGE FOR THE FIRST QUARTER | | 3.00 | 900.00 | 1156.98 | 1173.96 |
| | | WEIGHTED AVERAGE FOR THE YEAR | | 3.00 | 900.00 | 1156.98 | 1173.96 |
| ===== | 607-60620 | Road Closure Gate | | Each | ===== | ===== | ===== |
| STA1381-011 | | SH 138 STERLING NORTH PART 2 | 02/16/23 | 1.00 | 30000.00 | 45000.00 | 45000.00 |
| | WEIGHTED | AVERAGE FOR THE FIRST QUARTER | | 1.00 | 30000.00 | 45000.00 | 45000.00 |
| | | WEIGHTED AVERAGE FOR THE YEAR | | 1.00 | 30000.00 | 45000.00 | 45000.00 |
| ===== | 608-00000 | Conc Sidewalk | | Sq Yard | ===== | ===== | ===== |
| STA172A-022 | | SH 172 IGNACIO TO ELMORE'S CO | 01/12/23 | 1,572.00 | 48.00 | 108.52 | 117.14 |
| STM C440-013 | | R3 EAGLE RESIDENCY ADA RAMP I | 02/16/23 | 86.00 | 150.00 | 128.00 | 128.00 |
| C0881-036 | | R1 CURB RAMPS-SH88B & US285D | 02/16/23 | 1,269.00 | 125.00 | 92.00 | 82.00 |
| | WEIGHTED | AVERAGE FOR THE FIRST QUARTER | | 2,927.00 | 84.38 | 98.63 | 102.22 |
| | | WEIGHTED AVERAGE FOR THE YEAR | | 2,927.00 | 84.38 | 98.63 | 102.22 |
| ===== | 608-00006 | Conc Sidewalk (6 In) | | Sq Yard | ===== | ===== | ===== |
| NHPP0701-256 | | I-70B/31.5 RD MESA COUNTY | 02/16/23 | 33.00 | 150.00 | 118.50 | 125.00 |
| STA257A-008 | | SH 257 WINDSOR RESURFACING | 03/30/23 | 240.00 | 80.00 | 82.75 | 77.00 |
| | WEIGHTED | AVERAGE FOR THE FIRST QUARTER | | 273.00 | 88.46 | 87.07 | 82.80 |
| | | WEIGHTED AVERAGE FOR THE YEAR | | 273.00 | 88.46 | 87.07 | 82.80 |
| ===== | 608-00010 | Conc Curb Ramp | | Sq Yard | ===== | ===== | ===== |
| STA172A-022 | | SH 172 IGNACIO TO ELMORE'S CO | 01/12/23 | 970.00 | 50.00 | 103.33 | 110.56 |
| C 1601-086 | | MAPLE & CHESTNUT SIGNALS AT I | 02/16/23 | 45.00 | 500.00 | 630.00 | 630.00 |
| STM C440-013 | | R3 EAGLE RESIDENCY ADA RAMP I | 02/16/23 | 330.00 | 300.00 | 315.00 | 315.00 |

COLORADO DEPARTMENT OF TRANSPORTATION
ITEM UNIT COSTS BY PROJECTS -- 2023 COST DATA

12:26 Wednesday, May 17, 2023 78

| PROJECT NUMBER | ITEM NUMBER/ PROJECT LOCATION | ITEM DESCRIPTION/ PROJECT LOCATION | DATE LET | UNIT/ QUANTITY | ENGR. EST. | AVERAGE BID | AWARDED BID |
|----------------|----------------------------------|--|----------|-------------------|------------|-------------|-------------|
| ===== | 608-00010 | Conc Curb Ramp | | Sq Yard | ===== | ===== | ===== |
| C0881-036 | | R1 CURB RAMPS-SH88B & US285D | 02/16/23 | 3,034.00 | 300.00 | 183.75 | 182.00 |
| STA257A-008 | | SH 257 WINDSOR RESURFACING | 03/30/23 | 10.00 | 200.00 | 175.00 | 190.00 |
| | | WEIGHTED AVERAGE FOR THE FIRST QUARTER | | 4,389.00 | 246.57 | 177.34 | 180.82 |
| | | WEIGHTED AVERAGE FOR THE YEAR | | 4,389.00 | 246.57 | 177.34 | 180.82 |
| ===== | 608-00015 | Detectable Warnings | | Sq Foot | ===== | ===== | ===== |
| STM C440-013 | | R3 EAGLE RESIDENCY ADA RAMP I | 02/16/23 | 146.00 | 75.00 | 135.00 | 135.00 |
| C0881-036 | | R1 CURB RAMPS-SH88B & US285D | 02/16/23 | 16.00 | 95.00 | 155.50 | 94.00 |
| STA257A-008 | | SH 257 WINDSOR RESURFACING | 03/30/23 | 30.00 | 50.00 | 70.70 | 71.00 |
| | | WEIGHTED AVERAGE FOR THE FIRST QUARTER | | 192.00 | 72.76 | 125.57 | 121.58 |
| | | WEIGHTED AVERAGE FOR THE YEAR | | 192.00 | 72.76 | 125.57 | 121.58 |
| ===== | 608-00050 | Brick Pavers | | Sq Foot | ===== | ===== | ===== |
| STM C440-013 | | R3 EAGLE RESIDENCY ADA RAMP I | 02/16/23 | 64.00 | 75.00 | 85.00 | 85.00 |
| | | WEIGHTED AVERAGE FOR THE FIRST QUARTER | | 64.00 | 75.00 | 85.00 | 85.00 |
| | | WEIGHTED AVERAGE FOR THE YEAR | | 64.00 | 75.00 | 85.00 | 85.00 |
| ===== | 609-20000 | Curb Ty 2 B (Spec) | | Lin Foot | ===== | ===== | ===== |
| STA172A-022 | | SH 172 IGNACIO TO ELMORE'S CO | 01/12/23 | 120.00 | 80.00 | 53.69 | 69.48 |
| | | WEIGHTED AVERAGE FOR THE FIRST QUARTER | | 120.00 | 80.00 | 53.69 | 69.48 |
| | | WEIGHTED AVERAGE FOR THE YEAR | | 120.00 | 80.00 | 53.69 | 69.48 |
| ===== | 609-20010 | Curb Ty 2 B | | Lin Foot | ===== | ===== | ===== |
| STA172A-022 | | SH 172 IGNACIO TO ELMORE'S CO | 01/12/23 | 139.00 | 60.00 | 51.53 | 65.25 |
| STM C440-013 | | R3 EAGLE RESIDENCY ADA RAMP I | 02/16/23 | 41.00 | 45.00 | 51.00 | 51.00 |
| C0881-036 | | R1 CURB RAMPS-SH88B & US285D | 02/16/23 | 199.00 | 55.00 | 63.88 | 35.00 |
| | | WEIGHTED AVERAGE FOR THE FIRST QUARTER | | 379.00 | 55.75 | 60.32 | 47.83 |
| | | WEIGHTED AVERAGE FOR THE YEAR | | 379.00 | 55.75 | 60.32 | 47.83 |

COLORADO DEPARTMENT OF TRANSPORTATION
ITEM UNIT COSTS BY PROJECTS -- 2023 COST DATA

12:26 Wednesday, May 17, 2023 79

| PROJECT NUMBER | ITEM NUMBER/ PROJECT LOCATION | ITEM DESCRIPTION/ PROJECT LOCATION | DATE LET | UNIT/ QUANTITY | ENGR. EST. | AVERAGE BID | AWARDED BID |
|----------------|----------------------------------|---------------------------------------|----------|-------------------|------------|-------------|-------------|
| ===== | 609-20011 | Curb Ty 2 M | | Lin Foot | ===== | | |
| NHPP0253-296 | | I-25 @ LCR 16 (MP 253.8-254.5 | 02/07/23 | 414.00 | 39.70 | 42.48 | 42.48 |
| | WEIGHTED | AVERAGE FOR THE FIRST | QUARTER | 414.00 | 39.70 | 42.48 | 42.48 |
| | | WEIGHTED AVERAGE FOR THE YEAR | | 414.00 | 39.70 | 42.48 | 42.48 |
| ===== | 609-21010 | C and G Ty 2 I-B | | Lin Foot | ===== | | |
| STA172A-022 | | SH 172 IGNACIO TO ELMORE'S CO | 01/12/23 | 70.00 | 50.00 | 69.83 | 96.56 |
| C0881-036 | | R1 CURB RAMPS-SH88B & US285D | 02/16/23 | 244.00 | 50.00 | 58.75 | 41.00 |
| | WEIGHTED | AVERAGE FOR THE FIRST | QUARTER | 314.00 | 50.00 | 60.14 | 53.39 |
| | | WEIGHTED AVERAGE FOR THE YEAR | | 314.00 | 50.00 | 60.14 | 53.39 |
| ===== | 609-21011 | C and G Ty 2 I-M | | Lin Foot | ===== | | |
| STA172A-022 | | SH 172 IGNACIO TO ELMORE'S CO | 01/12/23 | 234.00 | 40.00 | 51.62 | 60.13 |
| NHPP0253-296 | | I-25 @ LCR 16 (MP 253.8-254.5 | 02/07/23 | 587.00 | 34.49 | 36.90 | 36.90 |
| | WEIGHTED | AVERAGE FOR THE FIRST | QUARTER | 821.00 | 36.06 | 43.43 | 43.52 |
| | | WEIGHTED AVERAGE FOR THE YEAR | | 821.00 | 36.06 | 43.43 | 43.52 |
| ===== | 609-21020 | C and G Ty 2 II-B | | Lin Foot | ===== | | |
| STA172A-022 | | SH 172 IGNACIO TO ELMORE'S CO | 01/12/23 | 2,811.00 | 40.00 | 47.08 | 51.06 |
| C0703-498 | | EISENHOWER JOHNSON MEMORIAL T | 02/16/23 | 335.00 | 50.00 | 59.84 | 77.00 |
| STM C440-013 | | R3 EAGLE RESIDENCY ADA RAMP I | 02/16/23 | 80.00 | 45.00 | 55.00 | 55.00 |
| C0881-036 | | R1 CURB RAMPS-SH88B & US285D | 02/16/23 | 1,419.00 | 50.00 | 57.00 | 45.00 |
| STA257A-008 | | SH 257 WINDSOR RESURFACING | 03/30/23 | 430.00 | 45.00 | 38.90 | 37.50 |
| | WEIGHTED | AVERAGE FOR THE FIRST | QUARTER | 5,075.00 | 43.96 | 51.82 | 49.99 |
| | | WEIGHTED AVERAGE FOR THE YEAR | | 5,075.00 | 43.96 | 51.82 | 49.99 |
| ===== | 609-21021 | C and G Ty 2 II-M | | Lin Foot | ===== | | |
| NHPP0253-296 | | I-25 @ LCR 16 (MP 253.8-254.5 | 02/07/23 | 1,173.00 | 41.63 | 44.54 | 44.54 |

COLORADO DEPARTMENT OF TRANSPORTATION
 ITEM UNIT COSTS BY PROJECTS -- 2023 COST DATA

12:26 Wednesday, May 17, 2023 80

| PROJECT NUMBER | ITEM NUMBER/ PROJECT LOCATION | ITEM DESCRIPTION/ PROJECT LOCATION | DATE LET | UNIT/ QUANTITY | ENGR. EST. | AVERAGE BID | AWARDED BID |
|---------------------------------|--|---------------------------------------|----------|--------------------|------------|-------------|-------------|
| ===== 609-21021 C0881-036 | C and G Ty 2 II-M R1 CURB RAMPS-SH88B & US285D | | 02/16/23 | Lin Foot 20.00 | 50.00 | 108.50 | 45.00 |
| | WEIGHTED AVERAGE FOR THE FIRST QUARTER | | | 1,193.00 | 41.77 | 48.62 | 44.55 |
| | WEIGHTED AVERAGE FOR THE YEAR | | | 1,193.00 | 41.77 | 48.62 | 44.55 |
| ===== 609-21900 NHPP0253-296 | C and G Ty 2 (Spec) I-25 @ LCR 16 (MP 253.8-254.5 | | 02/07/23 | Lin Foot 711.00 | 40.03 | 42.83 | 42.83 |
| | WEIGHTED AVERAGE FOR THE FIRST QUARTER | | | 711.00 | 40.03 | 42.83 | 42.83 |
| | WEIGHTED AVERAGE FOR THE YEAR | | | 711.00 | 40.03 | 42.83 | 42.83 |
| ===== 609-23000 C0703-498 | Gutter (Special) EISENHOWER JOHNSON MEMORIAL T | | 02/16/23 | Lin Foot 105.00 | 60.00 | 89.41 | 120.00 |
| | WEIGHTED AVERAGE FOR THE FIRST QUARTER | | | 105.00 | 60.00 | 89.41 | 120.00 |
| | WEIGHTED AVERAGE FOR THE YEAR | | | 105.00 | 60.00 | 89.41 | 120.00 |
| ===== 609-24000 C0703-498 | Gutter Ty 2 (Spec) EISENHOWER JOHNSON MEMORIAL T | | 02/16/23 | Lin Foot 128.00 | 65.00 | 74.62 | 100.00 |
| | WEIGHTED AVERAGE FOR THE FIRST QUARTER | | | 128.00 | 65.00 | 74.62 | 100.00 |
| | WEIGHTED AVERAGE FOR THE YEAR | | | 128.00 | 65.00 | 74.62 | 100.00 |
| ===== 609-24002 C0703-498 | Gutter Ty 2 (2 Ft) EISENHOWER JOHNSON MEMORIAL T | | 02/16/23 | Lin Foot 83.00 | 40.00 | 92.74 | 120.00 |
| | WEIGHTED AVERAGE FOR THE FIRST QUARTER | | | 83.00 | 40.00 | 92.74 | 120.00 |
| | WEIGHTED AVERAGE FOR THE YEAR | | | 83.00 | 40.00 | 92.74 | 120.00 |
| ===== 609-24004 STA172A-022 | Gutter Ty 2 (4 Ft) SH 172 IGNACIO TO ELMORE'S CO | | 01/12/23 | Lin Foot 50.00 | 45.00 | 125.97 | 163.83 |

COLORADO DEPARTMENT OF TRANSPORTATION
 ITEM UNIT COSTS BY PROJECTS -- 2023 COST DATA

12:26 Wednesday, May 17, 2023 81

| PROJECT NUMBER | ITEM NUMBER/ PROJECT LOCATION | ITEM DESCRIPTION/ PROJECT LOCATION | DATE LET | UNIT/ QUANTITY | ENGR. EST. | AVERAGE BID | AWARDED BID |
|--|--|--|----------------------|-----------------------------|----------------|-----------------|-----------------|
| ===== 609-24004 STA257A-008 | | Gutter Ty 2 (4 Ft) SH 257 WINDSOR RESURFACING | 03/30/23 | Lin Foot 145.00 | 50.00 | 48.13 | 51.25 |
| | WEIGHTED AVERAGE FOR THE FIRST QUARTER | | | 195.00 | 48.72 | 68.08 | 80.12 |
| | WEIGHTED AVERAGE FOR THE YEAR | | | 195.00 | 48.72 | 68.08 | 80.12 |
| ===== 609-24008 C0881-036 | | Gutter Ty 2 (8 Ft) R1 CURB RAMPS-SH88B & US285D | 02/16/23 | Lin Foot 7.00 | 120.00 | 269.50 | 305.00 |
| | WEIGHTED AVERAGE FOR THE FIRST QUARTER | | | 7.00 | 120.00 | 269.50 | 305.00 |
| | WEIGHTED AVERAGE FOR THE YEAR | | | 7.00 | 120.00 | 269.50 | 305.00 |
| ===== 609-60011 NHPP R100-376 | | Curb Ty 6 M VARIOUS LOCATIONS IN REGION 1 | 03/30/23 | Lin Foot 4,414.00 | 14.00 | 39.81 | 30.00 |
| | WEIGHTED AVERAGE FOR THE FIRST QUARTER | | | 4,414.00 | 14.00 | 39.81 | 30.00 |
| | WEIGHTED AVERAGE FOR THE YEAR | | | 4,414.00 | 14.00 | 39.81 | 30.00 |
| ===== 610-00020 NHPP0253-296 | | Median Cover (Pattern Conc) I-25 @ LCR 16 (MP 253.8-254.5) | 02/07/23 | Sq Foot 1,827.00 | 20.72 | 22.17 | 22.17 |
| | WEIGHTED AVERAGE FOR THE FIRST QUARTER | | | 1,827.00 | 20.72 | 22.17 | 22.17 |
| | WEIGHTED AVERAGE FOR THE YEAR | | | 1,827.00 | 20.72 | 22.17 | 22.17 |
| ===== 610-00026 STA172A-022 C 1601-086 | | Median Cover (6 In Pattern Conc) SH 172 IGNACIO TO ELMORE'S CO MAPLE & CHESTNUT SIGNALS AT I | 01/12/23 02/16/23 | Sq Foot 241.00 130.00 | 20.00 60.00 | 37.10 150.00 | 38.89 150.00 |
| | WEIGHTED AVERAGE FOR THE FIRST QUARTER | | | 371.00 | 34.02 | 61.08 | 77.82 |
| | WEIGHTED AVERAGE FOR THE YEAR | | | 371.00 | 34.02 | 61.08 | 77.82 |
| ===== 610-00030 STM C440-013 | | Median Cover Matl (Conc) R3 EAGLE RESIDENCY ADA RAMP I | 02/16/23 | Sq Foot 17.00 | 25.00 | 145.00 | 145.00 |
| | WEIGHTED AVERAGE FOR THE FIRST QUARTER | | | 17.00 | 25.00 | 145.00 | 145.00 |
| | WEIGHTED AVERAGE FOR THE YEAR | | | 17.00 | 25.00 | 145.00 | 145.00 |

COLORADO DEPARTMENT OF TRANSPORTATION
 ITEM UNIT COSTS BY PROJECTS -- 2023 COST DATA

12:26 Wednesday, May 17, 2023 82

| PROJECT NUMBER | ITEM NUMBER/ PROJECT LOCATION | ITEM DESCRIPTION/ PROJECT LOCATION | DATE LET | UNIT/ QUANTITY | ENGR. EST. | AVERAGE BID | AWARDED BID |
|----------------|----------------------------------|---------------------------------------|----------|-------------------|------------|-------------|-------------|
| ===== | 610-00035 | Median Cover Matl (Conc) (Spec) | | Sq Foot | ===== | ===== | ===== |
| STA172A-022 | | SH 172 IGNACIO TO ELMORE'S CO | 01/12/23 | 246.00 | 30.00 | 30.76 | 38.52 |
| | WEIGHTED | AVERAGE FOR THE FIRST QUARTER | | 246.00 | 30.00 | 30.76 | 38.52 |
| | | WEIGHTED AVERAGE FOR THE YEAR | | 246.00 | 30.00 | 30.76 | 38.52 |
| ===== | 610-00055 | Median Cover Matl (Stone) | | Sq Foot | ===== | ===== | ===== |
| NHPP0253-296 | | I-25 @ LCR 16 (MP 253.8-254.5 | 02/07/23 | 2,463.00 | 6.03 | 6.45 | 6.45 |
| | WEIGHTED | AVERAGE FOR THE FIRST QUARTER | | 2,463.00 | 6.03 | 6.45 | 6.45 |
| | | WEIGHTED AVERAGE FOR THE YEAR | | 2,463.00 | 6.03 | 6.45 | 6.45 |
| ===== | 612-00001 | Delin (Ty I) | | Each | ===== | ===== | ===== |
| SFTYR200-277 | | REGION 2 WIDE, VARIOUS HWY & | 01/19/23 | 23.00 | 50.00 | 50.00 | 25.00 |
| C133A-052 | | SH 133 ROCKFALL N OF MCCLURE | 02/16/23 | 20.00 | 55.00 | 76.00 | 120.00 |
| NHPP0701-256 | | I-70B/31.5 RD MESA COUNTY | 02/16/23 | 1.00 | 25.00 | 41.25 | 32.50 |
| C0881-036 | | R1 CURB RAMPS-SH88B & US285D | 02/16/23 | 20.00 | 25.00 | 114.75 | 50.00 |
| STA257A-008 | | SH 257 WINDSOR RESURFACING | 03/30/23 | 121.00 | 25.00 | 56.25 | 77.00 |
| NHPP R100-376 | | VARIOUS LOCATIONS IN REGION 1 | 03/30/23 | 11.00 | 36.63 | 65.35 | 48.00 |
| | WEIGHTED | AVERAGE FOR THE FIRST QUARTER | | 196.00 | 31.65 | 69.26 | 70.68 |
| | | WEIGHTED AVERAGE FOR THE YEAR | | 196.00 | 31.65 | 69.26 | 70.68 |
| ===== | 612-00002 | Delin (Ty II) | | Each | ===== | ===== | ===== |
| C133A-052 | | SH 133 ROCKFALL N OF MCCLURE | 02/16/23 | 15.00 | 60.00 | 85.75 | 135.00 |
| NHPP0701-256 | | I-70B/31.5 RD MESA COUNTY | 02/16/23 | 2.00 | 30.00 | 42.50 | 35.00 |
| C0881-036 | | R1 CURB RAMPS-SH88B & US285D | 02/16/23 | 5.00 | 25.00 | 124.25 | 50.00 |
| STA257A-008 | | SH 257 WINDSOR RESURFACING | 03/30/23 | 16.00 | 30.00 | 62.00 | 82.00 |
| NHPP R100-376 | | VARIOUS LOCATIONS IN REGION 1 | 03/30/23 | 1.00 | 40.84 | 76.65 | 32.00 |
| | WEIGHTED | AVERAGE FOR THE FIRST QUARTER | | 39.00 | 41.18 | 84.21 | 94.59 |
| | | WEIGHTED AVERAGE FOR THE YEAR | | 39.00 | 41.18 | 84.21 | 94.59 |
| ===== | 612-00003 | Delin (Ty III) | | Each | ===== | ===== | ===== |
| SFTYR200-277 | | REGION 2 WIDE, VARIOUS HWY & | 01/19/23 | 15.00 | 35.00 | 58.00 | 26.00 |

| PROJECT NUMBER | ITEM NUMBER/ PROJECT LOCATION | ITEM DESCRIPTION/ PROJECT LOCATION | DATE LET | UNIT/ QUANTITY | ENGR. EST. | AVERAGE BID | AWARDED BID |
|----------------|----------------------------------|--|----------|-------------------|------------|-------------|-------------|
| ===== | 612-00003 | Delin (Ty III) | | Each ===== | | | |
| C133A-052 | | SH 133 ROCKFALL N OF MCCLURE | 02/16/23 | 10.00 | 70.00 | 97.75 | 155.00 |
| C1601-084 | | US 160 SECTION3 PRIORITY CULV | 02/16/23 | 18.00 | 50.00 | 87.61 | 48.00 |
| NHPP0701-256 | | I-70B/31.5 RD MESA COUNTY | 02/16/23 | 2.00 | 35.00 | 42.50 | 35.00 |
| C0881-036 | | R1 CURB RAMPS-SH88B & US285D | 02/16/23 | 5.00 | 35.00 | 142.50 | 50.00 |
| STA257A-008 | | SH 257 WINDSOR RESURFACING | 03/30/23 | 17.00 | 30.00 | 65.00 | 87.00 |
| NHPP R100-376 | | VARIOUS LOCATIONS IN REGION 1 | 03/30/23 | 1.00 | 45.08 | 116.69 | 79.00 |
| | | WEIGHTED AVERAGE FOR THE FIRST QUARTER | | 68.00 | 43.02 | 85.95 | 68.85 |
| | | WEIGHTED AVERAGE FOR THE YEAR | | 68.00 | 43.02 | 85.95 | 68.85 |
| ===== | 612-00041 | Delin (Flex) (Ty I) | | Each ===== | | | |
| SHE067A-044 | | SH 67F M.P. 56.5-57.6 AND SH | 03/02/23 | 70.00 | 100.00 | 80.78 | 80.78 |
| | | WEIGHTED AVERAGE FOR THE FIRST QUARTER | | 70.00 | 100.00 | 80.78 | 80.78 |
| | | WEIGHTED AVERAGE FOR THE YEAR | | 70.00 | 100.00 | 80.78 | 80.78 |
| ===== | 612-00043 | Delin (Flex) (Ty III) | | Each ===== | | | |
| SHE067A-044 | | SH 67F M.P. 56.5-57.6 AND SH | 03/02/23 | 10.00 | 100.00 | 87.91 | 87.91 |
| | | WEIGHTED AVERAGE FOR THE FIRST QUARTER | | 10.00 | 100.00 | 87.91 | 87.91 |
| | | WEIGHTED AVERAGE FOR THE YEAR | | 10.00 | 100.00 | 87.91 | 87.91 |
| ===== | 612-00081 | Delin (PM) (Ty I) | | Each ===== | | | |
| SFTYR200-277 | | REGION 2 WIDE, VARIOUS HWY & | 01/19/23 | 68.00 | 50.00 | 82.50 | 65.00 |
| STA1381-011 | | SH 138 STERLING NORTH PART 2 | 02/16/23 | 36.00 | 65.00 | 29.00 | 29.00 |
| | | WEIGHTED AVERAGE FOR THE FIRST QUARTER | | 104.00 | 55.19 | 71.30 | 52.54 |
| | | WEIGHTED AVERAGE FOR THE YEAR | | 104.00 | 55.19 | 71.30 | 52.54 |
| ===== | 612-00083 | Delin (PM) (Ty III) | | Each ===== | | | |
| SFTYR200-277 | | REGION 2 WIDE, VARIOUS HWY & | 01/19/23 | 76.00 | 65.00 | 95.00 | 70.00 |
| | | WEIGHTED AVERAGE FOR THE FIRST QUARTER | | 76.00 | 65.00 | 95.00 | 70.00 |
| | | WEIGHTED AVERAGE FOR THE YEAR | | 76.00 | 65.00 | 95.00 | 70.00 |

COLORADO DEPARTMENT OF TRANSPORTATION
 ITEM UNIT COSTS BY PROJECTS -- 2023 COST DATA

12:26 Wednesday, May 17, 2023 84

| PROJECT NUMBER | ITEM NUMBER/ PROJECT LOCATION | ITEM DESCRIPTION/ PROJECT LOCATION | DATE LET | UNIT/ QUANTITY | ENGR. EST. | AVERAGE BID | AWARDED BID |
|----------------|--|---------------------------------------|----------|-------------------|------------|-------------|-------------|
| ===== | 612-00101 | Delin (Drv Conc Inst) (Ty I) | | Each | ===== | ===== | ===== |
| STA066A-008 | SH 66 @ WCR 7 | | 01/26/23 | 21.00 | 30.00 | 91.77 | 87.79 |
| | WEIGHTED AVERAGE FOR THE FIRST QUARTER | | | 21.00 | 30.00 | 91.77 | 87.79 |
| | WEIGHTED AVERAGE FOR THE YEAR | | | 21.00 | 30.00 | 91.77 | 87.79 |
| ===== | 612-00102 | Delin (Drv Conc Inst) (Ty II) | | Each | ===== | ===== | ===== |
| FSA0853-123 | US 85 AND WCR 66 LEFT TURN AC | | 01/26/23 | 31.00 | 200.00 | 111.50 | 94.00 |
| STA066A-008 | SH 66 @ WCR 7 | | 01/26/23 | 37.00 | 30.00 | 114.36 | 116.27 |
| | WEIGHTED AVERAGE FOR THE FIRST QUARTER | | | 68.00 | 107.50 | 112.92 | 106.12 |
| | WEIGHTED AVERAGE FOR THE YEAR | | | 68.00 | 107.50 | 112.92 | 106.12 |
| ===== | 612-00103 | Delin (Drv Conc Inst) (Ty III) | | Each | ===== | ===== | ===== |
| FSA0853-123 | US 85 AND WCR 66 LEFT TURN AC | | 01/26/23 | 4.00 | 250.00 | 117.50 | 104.00 |
| STA066A-008 | SH 66 @ WCR 7 | | 01/26/23 | 5.00 | 30.00 | 126.00 | 130.50 |
| | WEIGHTED AVERAGE FOR THE FIRST QUARTER | | | 9.00 | 127.78 | 121.83 | 118.72 |
| | WEIGHTED AVERAGE FOR THE YEAR | | | 9.00 | 127.78 | 121.83 | 118.72 |
| ===== | 612-00111 | Delin (Drv) (Ty I) | | Each | ===== | ===== | ===== |
| NHPP0253-296 | I-25 @ LCR 16 (MP 253.8-254.5 | | 02/07/23 | 42.00 | 31.85 | 34.08 | 34.08 |
| STA1381-011 | SH 138 STERLING NORTH PART 2 | | 02/16/23 | 256.00 | 75.00 | 87.00 | 87.00 |
| | WEIGHTED AVERAGE FOR THE FIRST QUARTER | | | 298.00 | 68.92 | 79.54 | 79.54 |
| | WEIGHTED AVERAGE FOR THE YEAR | | | 298.00 | 68.92 | 79.54 | 79.54 |
| ===== | 612-00112 | Delin (Drv) (Ty II) | | Each | ===== | ===== | ===== |
| NHPP0253-296 | I-25 @ LCR 16 (MP 253.8-254.5 | | 02/07/23 | 24.00 | 35.20 | 37.66 | 37.66 |
| | WEIGHTED AVERAGE FOR THE FIRST QUARTER | | | 24.00 | 35.20 | 37.66 | 37.66 |
| | WEIGHTED AVERAGE FOR THE YEAR | | | 24.00 | 35.20 | 37.66 | 37.66 |

COLORADO DEPARTMENT OF TRANSPORTATION
ITEM UNIT COSTS BY PROJECTS -- 2023 COST DATA

12:26 Wednesday, May 17, 2023 85

| PROJECT NUMBER | ITEM NUMBER/ PROJECT LOCATION | ITEM DESCRIPTION/ PROJECT LOCATION | DATE LET | UNIT/ QUANTITY | ENGR. EST. | AVERAGE BID | AWARDED BID |
|----------------|--|---------------------------------------|----------|-------------------|------------|-------------|-------------|
| ===== | 612-00113 | Delin (Drv) (Ty III) | | Each | ===== | ===== | ===== |
| NHPP0253-296 | | I-25 @ LCR 16 (MP 253.8-254.5 | 02/07/23 | 4.00 | 38.55 | 41.25 | 41.25 |
| STA1381-011 | | SH 138 STERLING NORTH PART 2 | 02/16/23 | 7.00 | 75.00 | 92.00 | 92.00 |
| | WEIGHTED AVERAGE FOR THE FIRST QUARTER | | | 11.00 | 61.75 | 73.55 | 73.55 |
| | WEIGHTED AVERAGE FOR THE YEAR | | | 11.00 | 61.75 | 73.55 | 73.55 |
| ===== | 612-00270 | Loc Mark (Util) (Flat Slat) | | Each | ===== | ===== | ===== |
| C0342-066 | | US 034A (MP 113-150) | 02/02/23 | 4.00 | 200.00 | 169.67 | 149.00 |
| | WEIGHTED AVERAGE FOR THE FIRST QUARTER | | | 4.00 | 200.00 | 169.67 | 149.00 |
| | WEIGHTED AVERAGE FOR THE YEAR | | | 4.00 | 200.00 | 169.67 | 149.00 |
| ===== | 613-00050 | 1/2 In Elec Cond | | Lin Foot | ===== | ===== | ===== |
| C0342-066 | | US 034A (MP 113-150) | 02/02/23 | 30.00 | 25.00 | 32.67 | 18.00 |
| | WEIGHTED AVERAGE FOR THE FIRST QUARTER | | | 30.00 | 25.00 | 32.67 | 18.00 |
| | WEIGHTED AVERAGE FOR THE YEAR | | | 30.00 | 25.00 | 32.67 | 18.00 |
| ===== | 613-00100 | 1 In Elec Cond | | Lin Foot | ===== | ===== | ===== |
| C 1601-086 | | MAPLE & CHESTNUT SIGNALS AT I | 02/16/23 | 150.00 | 20.00 | 18.00 | 18.00 |
| | WEIGHTED AVERAGE FOR THE FIRST QUARTER | | | 150.00 | 20.00 | 18.00 | 18.00 |
| | WEIGHTED AVERAGE FOR THE YEAR | | | 150.00 | 20.00 | 18.00 | 18.00 |
| ===== | 613-00200 | 2 In Elec Cond | | Lin Foot | ===== | ===== | ===== |
| C 1601-086 | | MAPLE & CHESTNUT SIGNALS AT I | 02/16/23 | 135.00 | 30.00 | 29.00 | 29.00 |
| NHPP0701-256 | | I-70B/31.5 RD MESA COUNTY | 02/16/23 | 50.00 | 40.00 | 250.00 | 300.00 |
| | WEIGHTED AVERAGE FOR THE FIRST QUARTER | | | 185.00 | 32.70 | 123.04 | 102.24 |
| | WEIGHTED AVERAGE FOR THE YEAR | | | 185.00 | 32.70 | 123.04 | 102.24 |

COLORADO DEPARTMENT OF TRANSPORTATION
ITEM UNIT COSTS BY PROJECTS -- 2023 COST DATA

12:26 Wednesday, May 17, 2023 86

| PROJECT NUMBER | ITEM NUMBER/ PROJECT LOCATION | ITEM DESCRIPTION/ PROJECT LOCATION | DATE LET | UNIT/ QUANTITY | ENGR. EST. | AVERAGE BID | AWARDED BID |
|----------------|----------------------------------|--|----------|-------------------|------------|-------------|-------------|
| ===== | 613-00206 | 2 In Elec Cond (Bored) | | Lin Foot | ===== | | |
| STA066A-008 | | SH 66 @ WCR 7 | 01/26/23 | 1,244.00 | 25.00 | 25.08 | 25.32 |
| STA1381-011 | | SH 138 STERLING NORTH PART 2 | 02/16/23 | 50.00 | 30.00 | 175.00 | 175.00 |
| C 1601-086 | | MAPLE & CHESTNUT SIGNALS AT I | 02/16/23 | 615.00 | 30.00 | 40.00 | 40.00 |
| | | WEIGHTED AVERAGE FOR THE FIRST QUARTER | | 1,909.00 | 26.74 | 27.50 | 33.97 |
| | | WEIGHTED AVERAGE FOR THE YEAR | | 1,909.00 | 26.74 | 27.50 | 33.97 |
| ===== | 613-00300 | 3 In Elec Cond | | Lin Foot | ===== | | |
| C 1601-086 | | MAPLE & CHESTNUT SIGNALS AT I | 02/16/23 | 220.00 | 32.00 | 38.00 | 38.00 |
| | | WEIGHTED AVERAGE FOR THE FIRST QUARTER | | 220.00 | 32.00 | 38.00 | 38.00 |
| | | WEIGHTED AVERAGE FOR THE YEAR | | 220.00 | 32.00 | 38.00 | 38.00 |
| ===== | 613-00306 | 3 In Elec Cond (Bored) | | Lin Foot | ===== | | |
| STA066A-008 | | SH 66 @ WCR 7 | 01/26/23 | 1,520.00 | 30.00 | 25.94 | 26.52 |
| NHPP0253-296 | | I-25 @ LCR 16 (MP 253.8-254.5) | 02/07/23 | 550.00 | 48.73 | 52.14 | 52.14 |
| C 1601-086 | | MAPLE & CHESTNUT SIGNALS AT I | 02/16/23 | 965.00 | 35.00 | 47.00 | 47.00 |
| | | WEIGHTED AVERAGE FOR THE FIRST QUARTER | | 3,035.00 | 34.98 | 29.75 | 37.67 |
| | | WEIGHTED AVERAGE FOR THE YEAR | | 3,035.00 | 34.98 | 29.75 | 37.67 |
| ===== | 613-01200 | 2 In Elec Cond (P) | | Lin Foot | ===== | | |
| STA066A-008 | | SH 66 @ WCR 7 | 01/26/23 | 423.00 | 30.00 | 33.79 | 36.17 |
| C0342-066 | | US 034A (MP 113-150) | 02/02/23 | 1,040.00 | 30.00 | 28.00 | 25.00 |
| NHPP0253-296 | | I-25 @ LCR 16 (MP 253.8-254.5) | 02/07/23 | 3,425.00 | 34.21 | 36.60 | 36.60 |
| STA1381-011 | | SH 138 STERLING NORTH PART 2 | 02/16/23 | 90.00 | 35.00 | 68.00 | 68.00 |
| | | WEIGHTED AVERAGE FOR THE FIRST QUARTER | | 4,978.00 | 32.99 | 33.18 | 34.71 |
| | | WEIGHTED AVERAGE FOR THE YEAR | | 4,978.00 | 32.99 | 33.18 | 34.71 |
| ===== | 613-01300 | 3 In Elec Cond (P) | | Lin Foot | ===== | | |
| STA066A-008 | | SH 66 @ WCR 7 | 01/26/23 | 483.00 | 40.00 | 39.36 | 43.40 |
| | | WEIGHTED AVERAGE FOR THE FIRST QUARTER | | 483.00 | 40.00 | 39.36 | 43.40 |
| | | WEIGHTED AVERAGE FOR THE YEAR | | 483.00 | 40.00 | 39.36 | 43.40 |

COLORADO DEPARTMENT OF TRANSPORTATION
ITEM UNIT COSTS BY PROJECTS -- 2023 COST DATA

12:26 Wednesday, May 17, 2023 87

| PROJECT NUMBER | ITEM NUMBER/ PROJECT LOCATION | ITEM DESCRIPTION/ PROJECT LOCATION | DATE LET | UNIT/ QUANTITY | ENGR. EST. | AVERAGE BID | AWARDED BID |
|----------------|----------------------------------|--|----------|-------------------|------------|-------------|-------------|
| ===== | 613-02200 | Furn 2 In Elec Cond | | Lin Foot | ===== | | |
| C0342-066 | | US 034A (MP 113-150) | 02/02/23 | 60.00 | 30.00 | 20.67 | 17.00 |
| | | WEIGHTED AVERAGE FOR THE FIRST QUARTER | | 60.00 | 30.00 | 20.67 | 17.00 |
| | | WEIGHTED AVERAGE FOR THE YEAR | | 60.00 | 30.00 | 20.67 | 17.00 |
| ===== | 613-04100 | Elect System Mods | | LUMP SUM | ===== | | |
| C0342-066 | | US 034A (MP 113-150) | 02/02/23 | 1.00 | 5000.00 | 8824.00 | 2131.00 |
| | | WEIGHTED AVERAGE FOR THE FIRST QUARTER | | 1.00 | 5000.00 | 8824.00 | 2131.00 |
| | | WEIGHTED AVERAGE FOR THE YEAR | | 1.00 | 5000.00 | 8824.00 | 2131.00 |
| ===== | 613-07001 | Type One Pull Box | | Each | ===== | | |
| C0881-036 | | R1 CURB RAMPS-SH88B & US285D | 02/16/23 | 14.00 | 1000.00 | 1513.00 | 852.00 |
| | | WEIGHTED AVERAGE FOR THE FIRST QUARTER | | 14.00 | 1000.00 | 1513.00 | 852.00 |
| | | WEIGHTED AVERAGE FOR THE YEAR | | 14.00 | 1000.00 | 1513.00 | 852.00 |
| ===== | 613-07002 | Type Two Pull Box | | Each | ===== | | |
| C0342-066 | | US 034A (MP 113-150) | 02/02/23 | 4.00 | 1500.00 | 2136.00 | 1758.00 |
| STA1381-011 | | SH 138 STERLING NORTH PART 2 | 02/16/23 | 3.00 | 2200.00 | 3900.00 | 3900.00 |
| STM C440-013 | | R3 EAGLE RESIDENCY ADA RAMP I | 02/16/23 | 2.00 | 1700.00 | 3500.00 | 3500.00 |
| C0881-036 | | R1 CURB RAMPS-SH88B & US285D | 02/16/23 | 9.00 | 1250.00 | 1847.50 | 990.00 |
| | | WEIGHTED AVERAGE FOR THE FIRST QUARTER | | 18.00 | 1513.89 | 2091.36 | 1924.56 |
| | | WEIGHTED AVERAGE FOR THE YEAR | | 18.00 | 1513.89 | 2091.36 | 1924.56 |
| ===== | 613-07003 | Type Three Pull Box | | Each | ===== | | |
| STA066A-008 | | SH 66 @ WCR 7 | 01/26/23 | 7.00 | 2500.00 | 2140.45 | 2307.66 |
| C0881-036 | | R1 CURB RAMPS-SH88B & US285D | 02/16/23 | 10.00 | 1500.00 | 2161.75 | 1297.00 |
| | | WEIGHTED AVERAGE FOR THE FIRST QUARTER | | 17.00 | 1911.76 | 2151.81 | 1713.15 |
| | | WEIGHTED AVERAGE FOR THE YEAR | | 17.00 | 1911.76 | 2151.81 | 1713.15 |

COLORADO DEPARTMENT OF TRANSPORTATION
ITEM UNIT COSTS BY PROJECTS -- 2023 COST DATA

12:26 Wednesday, May 17, 2023 88

| PROJECT NUMBER | ITEM NUMBER/ PROJECT LOCATION | ITEM DESCRIPTION/ PROJECT LOCATION | DATE LET | UNIT/ QUANTITY | ENGR. EST. | AVERAGE BID | AWARDED BID |
|-----------------|--|---------------------------------------|----------|-------------------|------------|-------------|-------------|
| ===== 613-07004 | | Type Four Pull Box | | Each | ===== | | |
| STA066A-008 | SH 66 @ WCR 7 | | 01/26/23 | 2.00 | 2800.00 | 3078.51 | 3344.55 |
| C0342-066 | US 034A (MP 113-150) | | 02/02/23 | 3.00 | 2000.00 | 3509.33 | 3628.00 |
| C0881-036 | R1 CURB RAMPS-SH88B & US285D | | 02/16/23 | 15.00 | 1800.00 | 3081.25 | 2325.00 |
| | WEIGHTED AVERAGE FOR THE FIRST QUARTER | | | 20.00 | 1930.00 | 3129.67 | 2622.41 |
| | WEIGHTED AVERAGE FOR THE YEAR | | | 20.00 | 1930.00 | 3129.67 | 2622.41 |
| ===== 613-07005 | | Type Five Pull Box | | Each | ===== | | |
| STA066A-008 | SH 66 @ WCR 7 | | 01/26/23 | 2.00 | 3500.00 | 3908.97 | 4381.43 |
| C0881-036 | R1 CURB RAMPS-SH88B & US285D | | 02/16/23 | 3.00 | 2800.00 | 4898.50 | 3214.00 |
| | WEIGHTED AVERAGE FOR THE FIRST QUARTER | | | 5.00 | 3080.00 | 4448.72 | 3680.97 |
| | WEIGHTED AVERAGE FOR THE YEAR | | | 5.00 | 3080.00 | 4448.72 | 3680.97 |
| ===== 613-07023 | | Pull Box (24"x36"x24") | | Each | ===== | | |
| C 1601-086 | MAPLE & CHESTNUT SIGNALS AT I | | 02/16/23 | 1.00 | 2000.00 | 3770.00 | 3770.00 |
| | WEIGHTED AVERAGE FOR THE FIRST QUARTER | | | 1.00 | 2000.00 | 3770.00 | 3770.00 |
| | WEIGHTED AVERAGE FOR THE YEAR | | | 1.00 | 2000.00 | 3770.00 | 3770.00 |
| ===== 613-07060 | | Pull Box (18"x30"x18") Deep | | Each | ===== | | |
| STA172A-022 | SH 172 IGNACIO TO ELMORE'S CO | | 01/12/23 | 1.00 | 1300.00 | 2058.29 | 3293.57 |
| C 1601-086 | MAPLE & CHESTNUT SIGNALS AT I | | 02/16/23 | 8.00 | 2000.00 | 2730.00 | 2730.00 |
| | WEIGHTED AVERAGE FOR THE FIRST QUARTER | | | 9.00 | 1922.22 | 2595.66 | 2792.62 |
| | WEIGHTED AVERAGE FOR THE YEAR | | | 9.00 | 1922.22 | 2595.66 | 2792.62 |
| ===== 613-10000 | | Wiring | | LUMP SUM | ===== | | |
| STA066A-008 | SH 66 @ WCR 7 | | 01/26/23 | 1.00 | 40000.00 | 69763.85 | 48000.00 |
| C0342-066 | US 034A (MP 113-150) | | 02/02/23 | 1.00 | 30000.00 | 27773.00 | 20819.00 |

COLORADO DEPARTMENT OF TRANSPORTATION
ITEM UNIT COSTS BY PROJECTS -- 2023 COST DATA

12:26 Wednesday, May 17, 2023 89

| PROJECT NUMBER | ITEM NUMBER/ PROJECT LOCATION | ITEM DESCRIPTION/ PROJECT LOCATION | DATE LET | UNIT/ QUANTITY | ENGR. EST. | AVERAGE BID | AWARDED BID |
|--|--|---------------------------------------|----------|-------------------|------------|-------------|-------------|
| ===== 613-10000 Wiring LUMP SUM ===== | | | | | | | |
| NHPP0253-296 | | I-25 @ LCR 16 (MP 253.8-254.5 | 02/07/23 | 1.00 | 65351.54 | 69926.27 | 69926.27 |
| STA1381-011 | | SH 138 STERLING NORTH PART 2 | 02/16/23 | 1.00 | 15000.00 | 11000.00 | 11000.00 |
| C 1601-086 | | MAPLE & CHESTNUT SIGNALS AT I | 02/16/23 | 1.00 | 20000.00 | 57000.00 | 57000.00 |
| NHPP0701-256 | | I-70B/31.5 RD MESA COUNTY | 02/16/23 | 1.00 | 10000.00 | 10400.00 | 15000.00 |
| | WEIGHTED AVERAGE FOR THE FIRST QUARTER | | | 6.00 | 28621.65 | 46276.04 | 39820.75 |
| | WEIGHTED AVERAGE FOR THE YEAR | | | 6.00 | 28621.65 | 46276.04 | 39820.75 |
| ===== 613-13006 Lumin (LED) (6,000 Lumens) Each ===== | | | | | | | |
| STA1381-011 | | SH 138 STERLING NORTH PART 2 | 02/16/23 | 1.00 | 1000.00 | 3000.00 | 3000.00 |
| | WEIGHTED AVERAGE FOR THE FIRST QUARTER | | | 1.00 | 1000.00 | 3000.00 | 3000.00 |
| | WEIGHTED AVERAGE FOR THE YEAR | | | 1.00 | 1000.00 | 3000.00 | 3000.00 |
| ===== 613-13008 Lumin (LED) (8,000 Lumens) Each ===== | | | | | | | |
| NHPP0253-296 | | I-25 @ LCR 16 (MP 253.8-254.5 | 02/07/23 | 1.00 | 1362.25 | 1457.61 | 1457.61 |
| C 1601-086 | | MAPLE & CHESTNUT SIGNALS AT I | 02/16/23 | 4.00 | 1000.00 | 1160.00 | 1160.00 |
| | WEIGHTED AVERAGE FOR THE FIRST QUARTER | | | 5.00 | 1072.45 | 1219.52 | 1219.52 |
| | WEIGHTED AVERAGE FOR THE YEAR | | | 5.00 | 1072.45 | 1219.52 | 1219.52 |
| ===== 613-13010 Lumin(LED) (10,000 Lumens) Each ===== | | | | | | | |
| STA066A-008 | | SH 66 @ WCR 7 | 01/26/23 | 8.00 | 1200.00 | 1693.25 | 1675.89 |
| | WEIGHTED AVERAGE FOR THE FIRST QUARTER | | | 8.00 | 1200.00 | 1693.25 | 1675.89 |
| | WEIGHTED AVERAGE FOR THE YEAR | | | 8.00 | 1200.00 | 1693.25 | 1675.89 |
| ===== 613-13014 Lumin (LED) (14,000 Lumens) Each ===== | | | | | | | |
| NHPP0253-296 | | I-25 @ LCR 16 (MP 253.8-254.5 | 02/07/23 | 6.00 | 4098.14 | 4385.02 | 4385.02 |
| | WEIGHTED AVERAGE FOR THE FIRST QUARTER | | | 6.00 | 4098.14 | 4385.02 | 4385.02 |
| | WEIGHTED AVERAGE FOR THE YEAR | | | 6.00 | 4098.14 | 4385.02 | 4385.02 |

COLORADO DEPARTMENT OF TRANSPORTATION
 ITEM UNIT COSTS BY PROJECTS -- 2023 COST DATA

12:26 Wednesday, May 17, 2023 90

| PROJECT NUMBER | ITEM NUMBER/ PROJECT LOCATION | ITEM DESCRIPTION/ PROJECT LOCATION | DATE LET | UNIT/ QUANTITY | ENGR. EST. | AVERAGE BID | AWARDED BID |
|----------------|----------------------------------|---------------------------------------|----------|-------------------|------------|-------------|-------------|
| ===== | 613-20000 | Inst Light Std + Lumin | | Each | ===== | ===== | ===== |
| NHPP0253-296 | | I-25 @ LCR 16 (MP 253.8-254.5 | 02/07/23 | 6.00 | 761.99 | 815.33 | 815.33 |
| | WEIGHTED | AVERAGE FOR THE FIRST | QUARTER | 6.00 | 761.99 | 815.33 | 815.33 |
| | | WEIGHTED AVERAGE FOR THE YEAR | | 6.00 | 761.99 | 815.33 | 815.33 |
| ===== | 613-32300 | Light Std Steel (30 Ft) | | Each | ===== | ===== | ===== |
| NHPP0253-296 | | I-25 @ LCR 16 (MP 253.8-254.5 | 02/07/23 | 6.00 | 2898.66 | 3101.58 | 3101.58 |
| | WEIGHTED | AVERAGE FOR THE FIRST | QUARTER | 6.00 | 2898.66 | 3101.58 | 3101.58 |
| | | WEIGHTED AVERAGE FOR THE YEAR | | 6.00 | 2898.66 | 3101.58 | 3101.58 |
| ===== | 613-34400 | Light Std Metal (40 Ft) | | Each | ===== | ===== | ===== |
| NHPP0253-296 | | I-25 @ LCR 16 (MP 253.8-254.5 | 02/07/23 | 1.00 | 5131.75 | 5490.98 | 5490.98 |
| | WEIGHTED | AVERAGE FOR THE FIRST | QUARTER | 1.00 | 5131.75 | 5490.98 | 5490.98 |
| | | WEIGHTED AVERAGE FOR THE YEAR | | 1.00 | 5131.75 | 5490.98 | 5490.98 |
| ===== | 613-40010 | Light Std Foundation | | Each | ===== | ===== | ===== |
| NHPP0253-296 | | I-25 @ LCR 16 (MP 253.8-254.5 | 02/07/23 | 13.00 | 4109.55 | 4397.22 | 4397.22 |
| | WEIGHTED | AVERAGE FOR THE FIRST | QUARTER | 13.00 | 4109.55 | 4397.22 | 4397.22 |
| | | WEIGHTED AVERAGE FOR THE YEAR | | 13.00 | 4109.55 | 4397.22 | 4397.22 |
| ===== | 613-40020 | Transformer Base Alum | | Each | ===== | ===== | ===== |
| STA1381-011 | | SH 138 STERLING NORTH PART 2 | 02/16/23 | 1.00 | 1200.00 | 1300.00 | 1300.00 |
| | WEIGHTED | AVERAGE FOR THE FIRST | QUARTER | 1.00 | 1200.00 | 1300.00 | 1300.00 |
| | | WEIGHTED AVERAGE FOR THE YEAR | | 1.00 | 1200.00 | 1300.00 | 1300.00 |
| ===== | 613-50100 | Lighting Ctrl Center | | Each | ===== | ===== | ===== |
| NHPP0253-296 | | I-25 @ LCR 16 (MP 253.8-254.5 | 02/07/23 | 1.00 | 10803.63 | 11559.91 | 11559.91 |
| | WEIGHTED | AVERAGE FOR THE FIRST | QUARTER | 1.00 | 10803.63 | 11559.91 | 11559.91 |
| | | WEIGHTED AVERAGE FOR THE YEAR | | 1.00 | 10803.63 | 11559.91 | 11559.91 |

| PROJECT NUMBER | ITEM NUMBER/ PROJECT LOCATION | ITEM DESCRIPTION/ PROJECT LOCATION | DATE LET | UNIT/ QUANTITY | ENGR. EST. | AVERAGE BID | AWARDED BID |
|----------------|--|---------------------------------------|----------|-------------------|------------|-------------|-------------|
| ===== | 613-80130 | Service Meter Cabinet | | Each | ===== | ===== | ===== |
| C0342-066 | US 034A (MP 113-150) | | 02/02/23 | 2.00 | 7000.00 | 9122.00 | 8757.00 |
| | WEIGHTED AVERAGE FOR THE FIRST QUARTER | | | 2.00 | 7000.00 | 9122.00 | 8757.00 |
| | WEIGHTED AVERAGE FOR THE YEAR | | | 2.00 | 7000.00 | 9122.00 | 8757.00 |
| ===== | 613-80274 | Struct Mount Disc Switch | | Each | ===== | ===== | ===== |
| C0342-066 | US 034A (MP 113-150) | | 02/02/23 | 3.00 | 2500.00 | 1736.67 | 550.00 |
| | WEIGHTED AVERAGE FOR THE FIRST QUARTER | | | 3.00 | 2500.00 | 1736.67 | 550.00 |
| | WEIGHTED AVERAGE FOR THE YEAR | | | 3.00 | 2500.00 | 1736.67 | 550.00 |
| ===== | 614-00011 | Sign Panel (CL I) | | Sq Foot | ===== | ===== | ===== |
| STA172A-022 | SH 172 IGNACIO TO ELMORE'S CO | | 01/12/23 | 18.00 | 25.00 | 24.08 | 24.46 |
| NHPP0701-250 | I-70B: DDI TO 24 RD, MAIN ST | | 01/12/23 | 52.00 | 25.00 | 34.50 | 29.00 |
| NHPP0253-296 | I-25 @ LCR 16 (MP 253.8-254.5 | | 02/07/23 | 193.00 | 38.68 | 41.39 | 41.39 |
| STA1381-011 | SH 138 STERLING NORTH PART 2 | | 02/16/23 | 183.00 | 30.00 | 43.00 | 43.00 |
| NHPP0701-256 | I-70B/31.5 RD MESA COUNTY | | 02/16/23 | 4.00 | 30.00 | 35.50 | 41.00 |
| STR194A-002 | SH194A SUR. TREAT.& DRAI IMP | | 03/09/23 | 162.13 | 23.00 | 39.50 | 44.00 |
| STA257A-008 | SH 257 WINDSOR RESURFACING | | 03/30/23 | 296.00 | 25.00 | 29.50 | 26.00 |
| NHPP R100-376 | VARIOUS LOCATIONS IN REGION 1 | | 03/30/23 | 35.00 | 50.00 | 62.57 | 70.00 |
| | WEIGHTED AVERAGE FOR THE FIRST QUARTER | | | 943.13 | 29.37 | 36.58 | 37.37 |
| | WEIGHTED AVERAGE FOR THE YEAR | | | 943.13 | 29.37 | 36.58 | 37.37 |
| ===== | 614-00012 | Sign Panel (CL II) | | Sq Foot | ===== | ===== | ===== |
| STA172A-022 | SH 172 IGNACIO TO ELMORE'S CO | | 01/12/23 | 36.00 | 25.00 | 43.93 | 44.66 |
| NHPP0253-296 | I-25 @ LCR 16 (MP 253.8-254.5 | | 02/07/23 | 176.00 | 44.48 | 47.59 | 47.59 |
| STA1381-011 | SH 138 STERLING NORTH PART 2 | | 02/16/23 | 1,001.00 | 35.00 | 45.00 | 45.00 |
| C 1601-086 | MAPLE & CHESTNUT SIGNALS AT I | | 02/16/23 | 227.00 | 40.00 | 54.00 | 54.00 |
| NHPP0701-256 | I-70B/31.5 RD MESA COUNTY | | 02/16/23 | 9.00 | 35.00 | 48.00 | 46.00 |
| SHE067A-044 | SH 67F M.P. 56.5-57.6 AND SH | | 03/02/23 | 240.00 | 40.00 | 27.32 | 27.32 |
| STR194A-002 | SH194A SUR. TREAT.& DRAI IMP | | 03/09/23 | 415.00 | 28.00 | 43.63 | 49.25 |
| STA257A-008 | SH 257 WINDSOR RESURFACING | | 03/30/23 | 416.00 | 28.00 | 42.50 | 47.00 |
| NHPP R100-376 | VARIOUS LOCATIONS IN REGION 1 | | 03/30/23 | 53.00 | 35.59 | 63.84 | 56.00 |
| | WEIGHTED AVERAGE FOR THE FIRST QUARTER | | | 2,573.00 | 34.17 | 44.15 | 45.56 |
| | WEIGHTED AVERAGE FOR THE YEAR | | | 2,573.00 | 34.17 | 44.15 | 45.56 |

| PROJECT NUMBER | ITEM NUMBER/ PROJECT LOCATION | ITEM DESCRIPTION/ PROJECT LOCATION | DATE LET | UNIT/ QUANTITY | ENGR. EST. | AVERAGE BID | AWARDED BID |
|-----------------|--|---------------------------------------|----------|-------------------|------------|-------------|-------------|
| ===== 614-00013 | | Sign Panel (CL III) | | Sq Foot | ===== | | |
| NHPP0253-296 | | I-25 @ LCR 16 (MP 253.8-254.5 | 02/07/23 | 190.00 | 51.15 | 54.73 | 54.73 |
| NHPP R100-376 | | VARIOUS LOCATIONS IN REGION 1 | 03/30/23 | 89.00 | 43.96 | 83.61 | 79.00 |
| | WEIGHTED AVERAGE FOR THE FIRST QUARTER | | | 279.00 | 48.86 | 68.70 | 62.47 |
| | WEIGHTED AVERAGE FOR THE YEAR | | | 279.00 | 48.86 | 68.70 | 62.47 |
| ===== 614-00025 | | Inst Sign Panel (CL I) | | Sq Foot | ===== | | |
| STA066A-008 | | SH 66 @ WCR 7 | 01/26/23 | 200.00 | 35.00 | 29.18 | 71.18 |
| | WEIGHTED AVERAGE FOR THE FIRST QUARTER | | | 200.00 | 35.00 | 29.18 | 71.18 |
| | WEIGHTED AVERAGE FOR THE YEAR | | | 200.00 | 35.00 | 29.18 | 71.18 |
| ===== 614-00027 | | Inst Sign Panel (CL II) | | Sq Foot | ===== | | |
| STA066A-008 | | SH 66 @ WCR 7 | 01/26/23 | 129.00 | 45.00 | 32.61 | 71.18 |
| | WEIGHTED AVERAGE FOR THE FIRST QUARTER | | | 129.00 | 45.00 | 32.61 | 71.18 |
| | WEIGHTED AVERAGE FOR THE YEAR | | | 129.00 | 45.00 | 32.61 | 71.18 |
| ===== 614-00216 | | Steel Signpost (2x2 In T) | | Lin Foot | ===== | | |
| STA066A-008 | | SH 66 @ WCR 7 | 01/26/23 | 21.00 | 25.00 | 35.68 | 28.47 |
| | WEIGHTED AVERAGE FOR THE FIRST QUARTER | | | 21.00 | 25.00 | 35.68 | 28.47 |
| | WEIGHTED AVERAGE FOR THE YEAR | | | 21.00 | 25.00 | 35.68 | 28.47 |
| ===== 614-00615 | | Steel Signpost (W 6x15) | | Lin Foot | ===== | | |
| NHPP0253-296 | | I-25 @ LCR 16 (MP 253.8-254.5 | 02/07/23 | 30.00 | 97.98 | 104.84 | 104.84 |
| | WEIGHTED AVERAGE FOR THE FIRST QUARTER | | | 30.00 | 97.98 | 104.84 | 104.84 |
| | WEIGHTED AVERAGE FOR THE YEAR | | | 30.00 | 97.98 | 104.84 | 104.84 |

| PROJECT NUMBER | ITEM NUMBER/ PROJECT LOCATION | ITEM DESCRIPTION/ PROJECT LOCATION | DATE LET | UNIT/ QUANTITY | ENGR. EST. | AVERAGE BID | AWARDED BID |
|----------------|----------------------------------|---------------------------------------|----------|-------------------|------------|-------------|-------------|
| ===== | 614-00818 | Steel Signpost (W 8x18) | | Lin Foot | ===== | | |
| NHPP0253-296 | | I-25 @ LCR 16 (MP 253.8-254.5 | 02/07/23 | 43.00 | 118.61 | 126.91 | 126.91 |
| | WEIGHTED | AVERAGE FOR THE FIRST QUARTER | | 43.00 | 118.61 | 126.91 | 126.91 |
| | | WEIGHTED AVERAGE FOR THE YEAR | | 43.00 | 118.61 | 126.91 | 126.91 |
| ===== | 614-01502 | Steel Sign Supp (2-In Rd) (Po&Sock) | | Lin Foot | ===== | | |
| STA1381-011 | | SH 138 STERLING NORTH PART 2 | 02/16/23 | 425.00 | 15.00 | 10.00 | 10.00 |
| | WEIGHTED | AVERAGE FOR THE FIRST QUARTER | | 425.00 | 15.00 | 10.00 | 10.00 |
| | | WEIGHTED AVERAGE FOR THE YEAR | | 425.00 | 15.00 | 10.00 | 10.00 |
| ===== | 614-01503 | Steel Sign Supp (2-In Rd) (Po&Sock) | | Each | ===== | | |
| NHPP0701-250 | | I-70B: DDI TO 24 RD, MAIN ST | 01/12/23 | 4.00 | 300.00 | 494.00 | 388.00 |
| STR194A-002 | | SH194A SUR. TREAT.& DRAI IMP | 03/09/23 | 14.00 | 29.00 | 678.50 | 657.00 |
| STA257A-008 | | SH 257 WINDSOR RESURFACING | 03/30/23 | 34.00 | 250.00 | 108.00 | 31.00 |
| | WEIGHTED | AVERAGE FOR THE FIRST QUARTER | | 52.00 | 194.35 | 291.29 | 227.00 |
| | | WEIGHTED AVERAGE FOR THE YEAR | | 52.00 | 194.35 | 291.29 | 227.00 |
| ===== | 614-01512 | Steel Sign Support (2-In Rd) (Post) | | Lin Foot | ===== | | |
| STA066A-008 | | SH 66 @ WCR 7 | 01/26/23 | 12.00 | 30.00 | 38.47 | 32.03 |
| NHPP0253-296 | | I-25 @ LCR 16 (MP 253.8-254.5 | 02/07/23 | 41.00 | 15.99 | 17.11 | 17.11 |
| | WEIGHTED | AVERAGE FOR THE FIRST QUARTER | | 53.00 | 19.16 | 29.80 | 20.49 |
| | | WEIGHTED AVERAGE FOR THE YEAR | | 53.00 | 19.16 | 29.80 | 20.49 |
| ===== | 614-01522 | Steel Sign Supp (2-In Rd) (Sock) | | Each | ===== | | |
| STA066A-008 | | SH 66 @ WCR 7 | 01/26/23 | 2.00 | 250.00 | 186.09 | 189.82 |
| NHPP0253-296 | | I-25 @ LCR 16 (MP 253.8-254.5 | 02/07/23 | 4.00 | 484.02 | 517.90 | 517.90 |
| | WEIGHTED | AVERAGE FOR THE FIRST QUARTER | | 6.00 | 406.01 | 280.89 | 408.54 |
| | | WEIGHTED AVERAGE FOR THE YEAR | | 6.00 | 406.01 | 280.89 | 408.54 |

COLORADO DEPARTMENT OF TRANSPORTATION
 ITEM UNIT COSTS BY PROJECTS -- 2023 COST DATA

12:26 Wednesday, May 17, 2023 94

| PROJECT NUMBER | ITEM NUMBER/ PROJECT LOCATION | ITEM DESCRIPTION/ PROJECT LOCATION | DATE LET | UNIT/ QUANTITY | ENGR. EST. | AVERAGE BID | AWARDED BID |
|-----------------|----------------------------------|---|----------|-------------------|------------|-------------|-------------|
| ===== 614-01572 | | Steel Sign Supp (2-1/2 Rd NP40) (Po&Slip) | | Lin Foot | ===== | | |
| STA1381-011 | | SH 138 STERLING NORTH PART 2 | 02/16/23 | 770.00 | 40.00 | 11.00 | 11.00 |
| | WEIGHTED | AVERAGE FOR THE FIRST QUARTER | | 770.00 | 40.00 | 11.00 | 11.00 |
| | | WEIGHTED AVERAGE FOR THE YEAR | | 770.00 | 40.00 | 11.00 | 11.00 |
| ===== 614-01573 | | Steel Sign Supp (2-1/2 Rd NP40) (Po&Slip) | | Each | ===== | | |
| SHE067A-044 | | SH 67F M.P. 56.5-57.6 AND SH | 03/02/23 | 17.00 | 1000.00 | 470.45 | 470.45 |
| STR194A-002 | | SH194A SUR. TREAT.& DRAI IMP | 03/09/23 | 28.00 | 450.00 | 835.50 | 821.00 |
| STA257A-008 | | SH 257 WINDSOR RESURFACING | 03/30/23 | 38.00 | 60.00 | 387.50 | 305.00 |
| | WEIGHTED | AVERAGE FOR THE FIRST QUARTER | | 83.00 | 384.10 | 565.34 | 512.96 |
| | | WEIGHTED AVERAGE FOR THE YEAR | | 83.00 | 384.10 | 565.34 | 512.96 |
| ===== 614-01575 | | Steel Sign Supp (2-1/2 In Rd NP40) (Po) | | Lin Foot | ===== | | |
| STA172A-022 | | SH 172 IGNACIO TO ELMORE'S CO | 01/12/23 | 84.00 | 20.00 | 15.68 | 15.95 |
| STA066A-008 | | SH 66 @ WCR 7 | 01/26/23 | 124.00 | 35.00 | 27.64 | 23.73 |
| NHPP0253-296 | | I-25 @ LCR 16 (MP 253.8-254.5 | 02/07/23 | 226.00 | 52.60 | 56.28 | 56.28 |
| NHPP0701-256 | | I-70B/31.5 RD MESA COUNTY | 02/16/23 | 10.00 | 30.00 | 45.50 | 41.00 |
| | WEIGHTED | AVERAGE FOR THE FIRST QUARTER | | 444.00 | 41.01 | 32.30 | 39.22 |
| | | WEIGHTED AVERAGE FOR THE YEAR | | 444.00 | 41.01 | 32.30 | 39.22 |
| ===== 614-01578 | | Steel Sign Supp (2-1/2 In Rd NP40) (Slip) | | Each | ===== | | |
| STA172A-022 | | SH 172 IGNACIO TO ELMORE'S CO | 01/12/23 | 7.00 | 20.00 | 392.38 | 398.76 |
| FSA0853-123 | | US 85 AND WCR 66 LEFT TURN AC | 01/26/23 | 9.00 | 200.00 | 427.67 | 315.00 |
| STA066A-008 | | SH 66 @ WCR 7 | 01/26/23 | 10.00 | 450.00 | 299.21 | 282.36 |
| NHPP0253-296 | | I-25 @ LCR 16 (MP 253.8-254.5 | 02/07/23 | 21.00 | 594.09 | 635.68 | 635.68 |
| C1601-084 | | US 160 SECTION3 PRIORITY CULV | 02/16/23 | 2.00 | 300.00 | 776.64 | 420.00 |
| NHPP0701-256 | | I-70B/31.5 RD MESA COUNTY | 02/16/23 | 1.00 | 500.00 | 611.00 | 522.00 |
| | WEIGHTED | AVERAGE FOR THE FIRST QUARTER | | 50.00 | 400.32 | 422.24 | 463.22 |
| | | WEIGHTED AVERAGE FOR THE YEAR | | 50.00 | 400.32 | 422.24 | 463.22 |
| ===== 614-01583 | | Stl Sign Supp (2-1/2 In Rd 80) (Po&Slip) | | Each | ===== | | |
| NHPP R100-376 | | VARIOUS LOCATIONS IN REGION 1 | 03/30/23 | 16.00 | 615.00 | 946.31 | 790.00 |
| | WEIGHTED | AVERAGE FOR THE FIRST QUARTER | | 16.00 | 615.00 | 946.31 | 790.00 |
| | | WEIGHTED AVERAGE FOR THE YEAR | | 16.00 | 615.00 | 946.31 | 790.00 |

COLORADO DEPARTMENT OF TRANSPORTATION
ITEM UNIT COSTS BY PROJECTS -- 2023 COST DATA

12:26 Wednesday, May 17, 2023 95

| PROJECT NUMBER | ITEM NUMBER/ PROJECT LOCATION | ITEM DESCRIPTION/ PROJECT LOCATION | DATE LET | UNIT/ QUANTITY | ENGR. EST. | AVERAGE BID | AWARDED BID |
|----------------|----------------------------------|---|----------|-------------------|------------|-------------|-------------|
| ===== | 614-01585 | Steel Sign Supp (2-1/2 In Rd 80) (Post) | | Lin Foot | ===== | | |
| NHPP0253-296 | | I-25 @ LCR 16 (MP 253.8-254.5 | 02/07/23 | 22.00 | 63.12 | 67.54 | 67.54 |
| | WEIGHTED | AVERAGE FOR THE FIRST | QUARTER | 22.00 | 63.12 | 67.54 | 67.54 |
| | | WEIGHTED AVERAGE FOR THE YEAR | | 22.00 | 63.12 | 67.54 | 67.54 |
| ===== | 614-01588 | Steel Sign Supp (2-1/2 In Rd 80) (Slip) | | Each | ===== | | |
| NHPP0253-296 | | I-25 @ LCR 16 (MP 253.8-254.5 | 02/07/23 | 2.00 | 783.86 | 838.74 | 838.74 |
| | WEIGHTED | AVERAGE FOR THE FIRST | QUARTER | 2.00 | 783.86 | 838.74 | 838.74 |
| | | WEIGHTED AVERAGE FOR THE YEAR | | 2.00 | 783.86 | 838.74 | 838.74 |
| ===== | 614-03001 | Conc Footing (Ty 1) | | Each | ===== | | |
| NHPP0253-296 | | I-25 @ LCR 16 (MP 253.8-254.5 | 02/07/23 | 2.00 | 1438.17 | 1538.84 | 1538.84 |
| | WEIGHTED | AVERAGE FOR THE FIRST | QUARTER | 2.00 | 1438.17 | 1538.84 | 1538.84 |
| | | WEIGHTED AVERAGE FOR THE YEAR | | 2.00 | 1438.17 | 1538.84 | 1538.84 |
| ===== | 614-03003 | Conc Footing (Ty 3) | | Each | ===== | | |
| NHPP0253-296 | | I-25 @ LCR 16 (MP 253.8-254.5 | 02/07/23 | 2.00 | 1645.74 | 1760.94 | 1760.94 |
| | WEIGHTED | AVERAGE FOR THE FIRST | QUARTER | 2.00 | 1645.74 | 1760.94 | 1760.94 |
| | | WEIGHTED AVERAGE FOR THE YEAR | | 2.00 | 1645.74 | 1760.94 | 1760.94 |
| ===== | 614-10160 | Sig Head B-Plates | | Each | ===== | | |
| C 1601-086 | | MAPLE & CHESTNUT SIGNALS AT I | 02/16/23 | 19.00 | 300.00 | 178.00 | 178.00 |
| | WEIGHTED | AVERAGE FOR THE FIRST | QUARTER | 19.00 | 300.00 | 178.00 | 178.00 |
| | | WEIGHTED AVERAGE FOR THE YEAR | | 19.00 | 300.00 | 178.00 | 178.00 |
| ===== | 614-70150 | Ped Sig Face (16) (Countdown) | | Each | ===== | | |
| C 1601-086 | | MAPLE & CHESTNUT SIGNALS AT I | 02/16/23 | 10.00 | 900.00 | 720.00 | 720.00 |

COLORADO DEPARTMENT OF TRANSPORTATION
ITEM UNIT COSTS BY PROJECTS -- 2023 COST DATA

12:26 Wednesday, May 17, 2023 96

| PROJECT NUMBER | ITEM NUMBER/ PROJECT LOCATION | ITEM DESCRIPTION/ PROJECT LOCATION | DATE LET | UNIT/ QUANTITY | ENGR. EST. | AVERAGE BID | AWARDED BID |
|-----------------|--|---------------------------------------|----------|-------------------|------------|-------------|-------------|
| ===== 614-70150 | | Ped Sig Face (16) (Countdown) | | Each ===== | | | |
| NHPP0701-256 | | I-70B/31.5 RD MESA COUNTY | 02/16/23 | 1.00 | 875.00 | 918.00 | 986.00 |
| | WEIGHTED AVERAGE FOR THE FIRST QUARTER | | | 11.00 | 897.73 | 753.00 | 744.18 |
| | WEIGHTED AVERAGE FOR THE YEAR | | | 11.00 | 897.73 | 753.00 | 744.18 |
| ===== 614-70200 | | Access Ped Sig | | Each ===== | | | |
| C0881-036 | | R1 CURB RAMPS-SH88B & US285D | 02/16/23 | 34.00 | 2200.00 | 2603.75 | 1590.00 |
| | WEIGHTED AVERAGE FOR THE FIRST QUARTER | | | 34.00 | 2200.00 | 2603.75 | 1590.00 |
| | WEIGHTED AVERAGE FOR THE YEAR | | | 34.00 | 2200.00 | 2603.75 | 1590.00 |
| ===== 614-70336 | | Traf Sig Face (12-12-12) | | Each ===== | | | |
| STA066A-008 | | SH 66 @ WCR 7 | 01/26/23 | 35.00 | 850.00 | 1231.36 | 1350.00 |
| C 1601-086 | | MAPLE & CHESTNUT SIGNALS AT I | 02/16/23 | 18.00 | 900.00 | 1000.00 | 1000.00 |
| NHPP0701-256 | | I-70B/31.5 RD MESA COUNTY | 02/16/23 | 1.00 | 1100.00 | 1575.00 | 1700.00 |
| | WEIGHTED AVERAGE FOR THE FIRST QUARTER | | | 54.00 | 871.30 | 1213.52 | 1239.81 |
| | WEIGHTED AVERAGE FOR THE YEAR | | | 54.00 | 871.30 | 1213.52 | 1239.81 |
| ===== 614-70448 | | Traf Sig Face (12-12-12-12) | | Each ===== | | | |
| C 1601-086 | | MAPLE & CHESTNUT SIGNALS AT I | 02/16/23 | 12.00 | 1000.00 | 1160.00 | 1160.00 |
| | WEIGHTED AVERAGE FOR THE FIRST QUARTER | | | 12.00 | 1000.00 | 1160.00 | 1160.00 |
| | WEIGHTED AVERAGE FOR THE YEAR | | | 12.00 | 1000.00 | 1160.00 | 1160.00 |
| ===== 614-72832 | | Comm Cabinet (Type 2) | | Each ===== | | | |
| C0342-066 | | US 034A (MP 113-150) | 02/02/23 | 2.00 | 15000.00 | 21003.33 | 22010.00 |
| | WEIGHTED AVERAGE FOR THE FIRST QUARTER | | | 2.00 | 15000.00 | 21003.33 | 22010.00 |
| | WEIGHTED AVERAGE FOR THE YEAR | | | 2.00 | 15000.00 | 21003.33 | 22010.00 |
| ===== 614-72835 | | Custom Phone Cab Blank Cover | | Each ===== | | | |
| C0703-498 | | EISENHOWER JOHNSON MEMORIAL T | 02/16/23 | 20.00 | 50.00 | 2135.33 | 2400.00 |
| | WEIGHTED AVERAGE FOR THE FIRST QUARTER | | | 20.00 | 50.00 | 2135.33 | 2400.00 |
| | WEIGHTED AVERAGE FOR THE YEAR | | | 20.00 | 50.00 | 2135.33 | 2400.00 |

COLORADO DEPARTMENT OF TRANSPORTATION
ITEM UNIT COSTS BY PROJECTS -- 2023 COST DATA

12:26 Wednesday, May 17, 2023 97

| PROJECT NUMBER | ITEM NUMBER/ PROJECT LOCATION | ITEM DESCRIPTION/ PROJECT LOCATION | DATE LET | UNIT/ QUANTITY | ENGR. EST. | AVERAGE BID | AWARDED BID |
|----------------|----------------------------------|--|----------|-------------------|------------|-------------|-------------|
| ===== | 614-72854 | Traf Ctrl Cabinet | | Each | ===== | ===== | ===== |
| C 1601-086 | | MAPLE & CHESTNUT SIGNALS AT I | 02/16/23 | 2.00 | 10000.00 | 31400.00 | 31400.00 |
| | | WEIGHTED AVERAGE FOR THE FIRST QUARTER | | 2.00 | 10000.00 | 31400.00 | 31400.00 |
| | | WEIGHTED AVERAGE FOR THE YEAR | | 2.00 | 10000.00 | 31400.00 | 31400.00 |
| ===== | 614-72855 | Traf Sig Ctrl Cabinet | | Each | ===== | ===== | ===== |
| STA066A-008 | | SH 66 @ WCR 7 | 01/26/23 | 2.00 | 40000.00 | 49878.06 | 53175.00 |
| | | WEIGHTED AVERAGE FOR THE FIRST QUARTER | | 2.00 | 40000.00 | 49878.06 | 53175.00 |
| | | WEIGHTED AVERAGE FOR THE YEAR | | 2.00 | 40000.00 | 49878.06 | 53175.00 |
| ===== | 614-72860 | Ped Push Button | | Each | ===== | ===== | ===== |
| NHPP0701-256 | | I-70B/31.5 RD MESA COUNTY | 02/16/23 | 1.00 | 650.00 | 540.00 | 580.00 |
| | | WEIGHTED AVERAGE FOR THE FIRST QUARTER | | 1.00 | 650.00 | 540.00 | 580.00 |
| | | WEIGHTED AVERAGE FOR THE YEAR | | 1.00 | 650.00 | 540.00 | 580.00 |
| ===== | 614-72863 | Ped Push Button Post Assem | | Each | ===== | ===== | ===== |
| C 1601-086 | | MAPLE & CHESTNUT SIGNALS AT I | 02/16/23 | 2.00 | 1500.00 | 5200.00 | 5200.00 |
| NHPP0701-256 | | I-70B/31.5 RD MESA COUNTY | 02/16/23 | 2.00 | 3000.00 | 3800.00 | 4100.00 |
| C0881-036 | | R1 CURB RAMPS-SH88B & US285D | 02/16/23 | 41.00 | 2200.00 | 3002.50 | 2925.00 |
| | | WEIGHTED AVERAGE FOR THE FIRST QUARTER | | 45.00 | 2204.44 | 3047.12 | 3078.33 |
| | | WEIGHTED AVERAGE FOR THE YEAR | | 45.00 | 2204.44 | 3047.12 | 3078.33 |
| ===== | 614-72864 | Fire Preempt Unit | | Each | ===== | ===== | ===== |
| STA066A-008 | | SH 66 @ WCR 7 | 01/26/23 | 2.00 | 10000.00 | 17523.33 | 19750.00 |
| | | WEIGHTED AVERAGE FOR THE FIRST QUARTER | | 2.00 | 10000.00 | 17523.33 | 19750.00 |
| | | WEIGHTED AVERAGE FOR THE YEAR | | 2.00 | 10000.00 | 17523.33 | 19750.00 |

COLORADO DEPARTMENT OF TRANSPORTATION
 ITEM UNIT COSTS BY PROJECTS -- 2023 COST DATA

12:26 Wednesday, May 17, 2023 98

| PROJECT NUMBER | ITEM NUMBER/ PROJECT LOCATION | ITEM DESCRIPTION/ PROJECT LOCATION | DATE LET | UNIT/ QUANTITY | ENGR. EST. | AVERAGE BID | AWARDED BID |
|----------------|----------------------------------|--|----------|-------------------|------------|-------------|-------------|
| ===== | 614-72885 | Detect (Spec) | | Each | ===== | ===== | ===== |
| C 1601-086 | | MAPLE & CHESTNUT SIGNALS AT I | 02/16/23 | 12.00 | 12000.00 | 11100.00 | 11100.00 |
| | | WEIGHTED AVERAGE FOR THE FIRST QUARTER | | 12.00 | 12000.00 | 11100.00 | 11100.00 |
| | | WEIGHTED AVERAGE FOR THE YEAR | | 12.00 | 12000.00 | 11100.00 | 11100.00 |
| ===== | 614-72886 | Intersection Detect Sys (Camera) | | Each | ===== | ===== | ===== |
| NHPP0701-250 | | I-70B: DDI TO 24 RD, MAIN ST | 01/12/23 | 10.00 | 12000.00 | 15420.00 | 14840.00 |
| STA066A-008 | | SH 66 @ WCR 7 | 01/26/23 | 8.00 | 12000.00 | 16703.11 | 17735.49 |
| NHPP0701-256 | | I-70B/31.5 RD MESA COUNTY | 02/16/23 | 3.00 | 12000.00 | 14750.00 | 16000.00 |
| | | WEIGHTED AVERAGE FOR THE FIRST QUARTER | | 21.00 | 12000.00 | 16136.74 | 16108.76 |
| | | WEIGHTED AVERAGE FOR THE YEAR | | 21.00 | 12000.00 | 16136.74 | 16108.76 |
| ===== | 614-75840 | Inst Traf Sig Ctrlr | | Each | ===== | ===== | ===== |
| C 1601-086 | | MAPLE & CHESTNUT SIGNALS AT I | 02/16/23 | 2.00 | 7000.00 | 160.00 | 160.00 |
| | | WEIGHTED AVERAGE FOR THE FIRST QUARTER | | 2.00 | 7000.00 | 160.00 | 160.00 |
| | | WEIGHTED AVERAGE FOR THE YEAR | | 2.00 | 7000.00 | 160.00 | 160.00 |
| ===== | 614-79336 | Furn Traf Sig Face (12-12-12) | | Each | ===== | ===== | ===== |
| STA257A-008 | | SH 257 WINDSOR RESURFACING | 03/30/23 | 1.00 | 750.00 | 2000.00 | 1800.00 |
| | | WEIGHTED AVERAGE FOR THE FIRST QUARTER | | 1.00 | 750.00 | 2000.00 | 1800.00 |
| | | WEIGHTED AVERAGE FOR THE YEAR | | 1.00 | 750.00 | 2000.00 | 1800.00 |
| ===== | 614-80000 | Flash Beacon | | Each | ===== | ===== | ===== |
| NHPP0253-296 | | I-25 @ LCR 16 (MP 253.8-254.5 | 02/07/23 | 2.00 | 841.58 | 900.49 | 900.49 |
| | | WEIGHTED AVERAGE FOR THE FIRST QUARTER | | 2.00 | 841.58 | 900.49 | 900.49 |
| | | WEIGHTED AVERAGE FOR THE YEAR | | 2.00 | 841.58 | 900.49 | 900.49 |

COLORADO DEPARTMENT OF TRANSPORTATION
ITEM UNIT COSTS BY PROJECTS -- 2023 COST DATA

12:26 Wednesday, May 17, 2023 99

| PROJECT NUMBER | ITEM NUMBER/ PROJECT LOCATION | ITEM DESCRIPTION/ PROJECT LOCATION | DATE LET | UNIT/ QUANTITY | ENGR. EST. | AVERAGE BID | AWARDED BID |
|-----------------|----------------------------------|---|----------|-------------------|------------|-------------|-------------|
| ===== 614-80390 | | Rumble Strip (Grinding) (Asphalt) (Sin) | | Lin Foot | ===== | | |
| SHE067A-044 | | SH 67F M.P. 56.5-57.6 AND SH | 03/02/23 | 3,124.00 | 1.00 | 9.08 | 9.08 |
| | WEIGHTED | AVERAGE FOR THE FIRST QUARTER | | 3,124.00 | 1.00 | 9.08 | 9.08 |
| | | WEIGHTED AVERAGE FOR THE YEAR | | 3,124.00 | 1.00 | 9.08 | 9.08 |
| ===== 614-80391 | | Rumble Strip (Grind) (Asphalt) | | Lin Foot | ===== | | |
| STA1381-011 | | SH 138 STERLING NORTH PART 2 | 02/16/23 | 95,718.00 | 0.20 | 0.15 | 0.15 |
| STA257A-008 | | SH 257 WINDSOR RESURFACING | 03/30/23 | 15,280.00 | 0.60 | 1.05 | 0.30 |
| | WEIGHTED | AVERAGE FOR THE FIRST QUARTER | | 110,998.00 | 0.26 | 0.37 | 0.17 |
| | | WEIGHTED AVERAGE FOR THE YEAR | | 110,998.00 | 0.26 | 0.37 | 0.17 |
| ===== 614-81020 | | Sig-Light Pole Steel (2) | | Each | ===== | | |
| C 1601-086 | | MAPLE & CHESTNUT SIGNALS AT I | 02/16/23 | 2.00 | 52500.00 | 55150.00 | 55150.00 |
| | WEIGHTED | AVERAGE FOR THE FIRST QUARTER | | 2.00 | 52500.00 | 55150.00 | 55150.00 |
| | | WEIGHTED AVERAGE FOR THE YEAR | | 2.00 | 52500.00 | 55150.00 | 55150.00 |
| ===== 614-81135 | | Sig-Light Pole Steel (1-35 Ft) | | Each | ===== | | |
| STA066A-008 | | SH 66 @ WCR 7 | 01/26/23 | 1.00 | 20000.00 | 25724.87 | 27238.63 |
| | WEIGHTED | AVERAGE FOR THE FIRST QUARTER | | 1.00 | 20000.00 | 25724.87 | 27238.63 |
| | | WEIGHTED AVERAGE FOR THE YEAR | | 1.00 | 20000.00 | 25724.87 | 27238.63 |
| ===== 614-81145 | | Sig-Light Pole Steel (1-45 Ft) | | Each | ===== | | |
| STA066A-008 | | SH 66 @ WCR 7 | 01/26/23 | 1.00 | 25000.00 | 29272.82 | 31290.90 |
| | WEIGHTED | AVERAGE FOR THE FIRST QUARTER | | 1.00 | 25000.00 | 29272.82 | 31290.90 |
| | | WEIGHTED AVERAGE FOR THE YEAR | | 1.00 | 25000.00 | 29272.82 | 31290.90 |

COLORADO DEPARTMENT OF TRANSPORTATION
ITEM UNIT COSTS BY PROJECTS -- 2023 COST DATA

12:26 Wednesday, May 17, 2023 100

| PROJECT NUMBER | ITEM NUMBER/ PROJECT LOCATION | ITEM DESCRIPTION/ PROJECT LOCATION | DATE LET | UNIT/ QUANTITY | ENGR. EST. | AVERAGE BID | AWARDED BID |
|-----------------|--|---------------------------------------|----------|-------------------|------------|-------------|-------------|
| ===== 614-81155 | | Sig-Light Pole Steel (1-55 Ft) | | Each | ===== | ===== | ===== |
| STA066A-008 | SH 66 @ WCR 7 | | 01/26/23 | 4.00 | 35000.00 | 32040.56 | 33728.78 |
| | WEIGHTED AVERAGE FOR THE FIRST QUARTER | | | 4.00 | 35000.00 | 32040.56 | 33728.78 |
| | WEIGHTED AVERAGE FOR THE YEAR | | | 4.00 | 35000.00 | 32040.56 | 33728.78 |
| ===== 614-81250 | | Sig-Light Pole Steel (2-50 Ft) | | Each | ===== | ===== | ===== |
| C 1601-086 | MAPLE & CHESTNUT SIGNALS AT I | | 02/16/23 | 1.00 | 50000.00 | 50400.00 | 50400.00 |
| | WEIGHTED AVERAGE FOR THE FIRST QUARTER | | | 1.00 | 50000.00 | 50400.00 | 50400.00 |
| | WEIGHTED AVERAGE FOR THE YEAR | | | 1.00 | 50000.00 | 50400.00 | 50400.00 |
| ===== 614-81260 | | Sig-Light Pole Steel (2-60 Ft) | | Each | ===== | ===== | ===== |
| C 1601-086 | MAPLE & CHESTNUT SIGNALS AT I | | 02/16/23 | 1.00 | 55000.00 | 57000.00 | 57000.00 |
| | WEIGHTED AVERAGE FOR THE FIRST QUARTER | | | 1.00 | 55000.00 | 57000.00 | 57000.00 |
| | WEIGHTED AVERAGE FOR THE YEAR | | | 1.00 | 55000.00 | 57000.00 | 57000.00 |
| ===== 614-81550 | | Sig-Light Pole Steel (2-50&60 Ft) | | Each | ===== | ===== | ===== |
| STA066A-008 | SH 66 @ WCR 7 | | 01/26/23 | 1.00 | 40000.00 | 67587.58 | 72376.71 |
| | WEIGHTED AVERAGE FOR THE FIRST QUARTER | | | 1.00 | 40000.00 | 67587.58 | 72376.71 |
| | WEIGHTED AVERAGE FOR THE YEAR | | | 1.00 | 40000.00 | 67587.58 | 72376.71 |
| ===== 614-84000 | | Traf Sig Ped Pole Steel | | Each | ===== | ===== | ===== |
| STA066A-008 | SH 66 @ WCR 7 | | 01/26/23 | 1.00 | 3000.00 | 4161.83 | 4393.49 |
| NHPP0701-256 | I-70B/31.5 RD MESA COUNTY | | 02/16/23 | 1.00 | 4000.00 | 4825.00 | 5200.00 |
| | WEIGHTED AVERAGE FOR THE FIRST QUARTER | | | 2.00 | 3500.00 | 4351.31 | 4796.75 |
| | WEIGHTED AVERAGE FOR THE YEAR | | | 2.00 | 3500.00 | 4351.31 | 4796.75 |

COLORADO DEPARTMENT OF TRANSPORTATION
ITEM UNIT COSTS BY PROJECTS -- 2023 COST DATA

12:26 Wednesday, May 17, 2023 101

| PROJECT NUMBER | ITEM NUMBER/ PROJECT LOCATION | ITEM DESCRIPTION/ PROJECT LOCATION | DATE LET | UNIT/ QUANTITY | ENGR. EST. | AVERAGE BID | AWARDED BID |
|----------------|----------------------------------|--|----------|-------------------|------------|-------------|-------------|
| ===== | 614-85001 | Impact Atten | | Each | ===== | ===== | ===== |
| C0703-498 | | EISENHOWER JOHNSON MEMORIAL T | 02/16/23 | 1.00 | 41571.43 | 49356.54 | 50000.00 |
| C133A-052 | | SH 133 ROCKFALL N OF MCCLURE | 02/16/23 | 6.00 | 40000.00 | 41250.00 | 6000.00 |
| | | WEIGHTED AVERAGE FOR THE FIRST QUARTER | | 7.00 | 40224.49 | 42150.73 | 12285.71 |
| | | WEIGHTED AVERAGE FOR THE YEAR | | 7.00 | 40224.49 | 42150.73 | 12285.71 |
| ===== | 614-86105 | Telemetry (Field) | | Each | ===== | ===== | ===== |
| C0342-066 | | US 034A (MP 113-150) | 02/02/23 | 3.00 | 5000.00 | 7382.33 | 4268.00 |
| C 1601-086 | | MAPLE & CHESTNUT SIGNALS AT I | 02/16/23 | 2.00 | 3000.00 | 2260.00 | 2260.00 |
| | | WEIGHTED AVERAGE FOR THE FIRST QUARTER | | 5.00 | 4200.00 | 6451.00 | 3464.80 |
| | | WEIGHTED AVERAGE FOR THE YEAR | | 5.00 | 4200.00 | 6451.00 | 3464.80 |
| ===== | 614-86741 | Weather Monitor System | | Each | ===== | ===== | ===== |
| C0342-066 | | US 034A (MP 113-150) | 02/02/23 | 1.00 | 60000.00 | 84424.33 | 84512.00 |
| | | WEIGHTED AVERAGE FOR THE FIRST QUARTER | | 1.00 | 60000.00 | 84424.33 | 84512.00 |
| | | WEIGHTED AVERAGE FOR THE YEAR | | 1.00 | 60000.00 | 84424.33 | 84512.00 |
| ===== | 614-86752 | Fold-Over Tower (ITS) | | Each | ===== | ===== | ===== |
| C0342-066 | | US 034A (MP 113-150) | 02/02/23 | 1.00 | 35000.00 | 46653.00 | 40399.00 |
| | | WEIGHTED AVERAGE FOR THE FIRST QUARTER | | 1.00 | 35000.00 | 46653.00 | 40399.00 |
| | | WEIGHTED AVERAGE FOR THE YEAR | | 1.00 | 35000.00 | 46653.00 | 40399.00 |
| ===== | 614-86757 | Anti-icing Syst | | Each | ===== | ===== | ===== |
| C0703-498 | | EISENHOWER JOHNSON MEMORIAL T | 02/16/23 | 2.00 | 551000.00 | 776912.90 | 671000.00 |
| | | WEIGHTED AVERAGE FOR THE FIRST QUARTER | | 2.00 | 551000.00 | 776912.90 | 671000.00 |
| | | WEIGHTED AVERAGE FOR THE YEAR | | 2.00 | 551000.00 | 776912.90 | 671000.00 |

COLORADO DEPARTMENT OF TRANSPORTATION
ITEM UNIT COSTS BY PROJECTS -- 2023 COST DATA

12:26 Wednesday, May 17, 2023 102

| PROJECT NUMBER | ITEM NUMBER/ PROJECT LOCATION | ITEM DESCRIPTION/ PROJECT LOCATION | DATE LET | UNIT/ QUANTITY | ENGR. EST. | AVERAGE BID | AWARDED BID |
|-----------------|----------------------------------|---------------------------------------|----------|-------------------|------------|-------------|-------------|
| ===== 614-87100 | | Auto Traf Rec Sta | | Each | ===== | ===== | ===== |
| STA257A-008 | | SH 257 WINDSOR RESURFACING | 03/30/23 | 1.00 | 35000.00 | 30600.00 | 28000.00 |
| | WEIGHTED | AVERAGE FOR THE FIRST QUARTER | | 1.00 | 35000.00 | 30600.00 | 28000.00 |
| | | WEIGHTED AVERAGE FOR THE YEAR | | 1.00 | 35000.00 | 30600.00 | 28000.00 |
| ===== 614-87320 | | CCTV | | Each | ===== | ===== | ===== |
| C0342-066 | | US 034A (MP 113-150) | 02/02/23 | 3.00 | 6000.00 | 7460.33 | 9281.00 |
| | WEIGHTED | AVERAGE FOR THE FIRST QUARTER | | 3.00 | 6000.00 | 7460.33 | 9281.00 |
| | | WEIGHTED AVERAGE FOR THE YEAR | | 3.00 | 6000.00 | 7460.33 | 9281.00 |
| ===== 614-87333 | | CCTV Camera (Traf Surveil) | | Each | ===== | ===== | ===== |
| C 1601-086 | | MAPLE & CHESTNUT SIGNALS AT I | 02/16/23 | 2.00 | 9000.00 | 10200.00 | 10200.00 |
| | WEIGHTED | AVERAGE FOR THE FIRST QUARTER | | 2.00 | 9000.00 | 10200.00 | 10200.00 |
| | | WEIGHTED AVERAGE FOR THE YEAR | | 2.00 | 9000.00 | 10200.00 | 10200.00 |
| ===== 614-87364 | | CCTV Pole w Low Dev (50 Ft) | | Each | ===== | ===== | ===== |
| C0342-066 | | US 034A (MP 113-150) | 02/02/23 | 1.00 | 30000.00 | 35586.00 | 17758.00 |
| | WEIGHTED | AVERAGE FOR THE FIRST QUARTER | | 1.00 | 30000.00 | 35586.00 | 17758.00 |
| | | WEIGHTED AVERAGE FOR THE YEAR | | 1.00 | 30000.00 | 35586.00 | 17758.00 |
| ===== 614-87690 | | Ethernet Switch | | Each | ===== | ===== | ===== |
| STA066A-008 | | SH 66 @ WCR 7 | 01/26/23 | 2.00 | 7000.00 | 3803.81 | 4180.08 |
| | WEIGHTED | AVERAGE FOR THE FIRST QUARTER | | 2.00 | 7000.00 | 3803.81 | 4180.08 |
| | | WEIGHTED AVERAGE FOR THE YEAR | | 2.00 | 7000.00 | 3803.81 | 4180.08 |
| ===== 614-87702 | | Ethernet Radio (Pair) | | Each | ===== | ===== | ===== |
| STA066A-008 | | SH 66 @ WCR 7 | 01/26/23 | 2.00 | 2000.00 | 2804.59 | 2941.85 |
| | WEIGHTED | AVERAGE FOR THE FIRST QUARTER | | 2.00 | 2000.00 | 2804.59 | 2941.85 |
| | | WEIGHTED AVERAGE FOR THE YEAR | | 2.00 | 2000.00 | 2804.59 | 2941.85 |

COLORADO DEPARTMENT OF TRANSPORTATION
ITEM UNIT COSTS BY PROJECTS -- 2023 COST DATA

12:26 Wednesday, May 17, 2023 103

| PROJECT NUMBER | ITEM NUMBER/ PROJECT LOCATION | ITEM DESCRIPTION/ PROJECT LOCATION | DATE LET | UNIT/ QUANTITY | ENGR. EST. | AVERAGE BID | AWARDED BID |
|----------------|----------------------------------|---------------------------------------|----------|-------------------|------------|-------------|-------------|
| ===== | 615-00030 | Emb Prot Ty 3 | | Each | ===== | ===== | ===== |
| NHPP R100-376 | | VARIOUS LOCATIONS IN REGION 1 | 03/30/23 | 2.00 | 3600.00 | 11888.24 | 22450.00 |
| | WEIGHTED | AVERAGE FOR THE FIRST QUARTER | | 2.00 | 3600.00 | 11888.24 | 22450.00 |
| | | WEIGHTED AVERAGE FOR THE YEAR | | 2.00 | 3600.00 | 11888.24 | 22450.00 |
| ===== | 615-00050 | Emb Prot Ty 5 | | Each | ===== | ===== | ===== |
| STR194A-002 | | SH194A SUR. TREAT.& DRAI IMP | 03/09/23 | 1.00 | 700.00 | 2650.00 | 2300.00 |
| | WEIGHTED | AVERAGE FOR THE FIRST QUARTER | | 1.00 | 700.00 | 2650.00 | 2300.00 |
| | | WEIGHTED AVERAGE FOR THE YEAR | | 1.00 | 700.00 | 2650.00 | 2300.00 |
| ===== | 615-00150 | Emb Prot (Spec) | | Each | ===== | ===== | ===== |
| STA257A-008 | | SH 257 WINDSOR RESURFACING | 03/30/23 | 1.00 | 2500.00 | 5950.00 | 3700.00 |
| | WEIGHTED | AVERAGE FOR THE FIRST QUARTER | | 1.00 | 2500.00 | 5950.00 | 3700.00 |
| | | WEIGHTED AVERAGE FOR THE YEAR | | 1.00 | 2500.00 | 5950.00 | 3700.00 |
| ===== | 619-30320 | 4 In Galv Pipe | | Lin Foot | ===== | ===== | ===== |
| STA257A-008 | | SH 257 WINDSOR RESURFACING | 03/30/23 | 5.00 | 400.00 | 517.50 | 610.00 |
| | WEIGHTED | AVERAGE FOR THE FIRST QUARTER | | 5.00 | 400.00 | 517.50 | 610.00 |
| | | WEIGHTED AVERAGE FOR THE YEAR | | 5.00 | 400.00 | 517.50 | 610.00 |
| ===== | 620-00001 | Field Office (CL 1) | | Each | ===== | ===== | ===== |
| C 1601-086 | | MAPLE & CHESTNUT SIGNALS AT I | 02/16/23 | 1.00 | 40000.00 | 90000.00 | 90000.00 |
| | WEIGHTED | AVERAGE FOR THE FIRST QUARTER | | 1.00 | 40000.00 | 90000.00 | 90000.00 |
| | | WEIGHTED AVERAGE FOR THE YEAR | | 1.00 | 40000.00 | 90000.00 | 90000.00 |
| ===== | 620-00002 | Field Office (CL 2) | | Each | ===== | ===== | ===== |
| STA172A-022 | | SH 172 IGNACIO TO ELMORE'S CO | 01/12/23 | 1.00 | 55000.00 | 42925.81 | 51041.62 |

| PROJECT NUMBER | ITEM NUMBER/ PROJECT LOCATION | ITEM DESCRIPTION/ PROJECT LOCATION | DATE LET | UNIT/ QUANTITY | ENGR. EST. | AVERAGE BID | AWARDED BID |
|-----------------|--|---------------------------------------|----------|-------------------|------------|-------------|-------------|
| ===== 620-00002 | | Field Office (CL 2) | | Each ===== | | | |
| NHPP0701-250 | | I-70B: DDI TO 24 RD, MAIN ST | 01/12/23 | 1.00 | 40000.00 | 29485.00 | 16970.00 |
| FSA0853-123 | | US 85 AND WCR 66 LEFT TURN AC | 01/26/23 | 1.00 | 35000.00 | 29916.67 | 31500.00 |
| STA066A-008 | | SH 66 @ WCR 7 | 01/26/23 | 1.00 | 30000.00 | 41857.00 | 27500.00 |
| STA1381-011 | | SH 138 STERLING NORTH PART 2 | 02/16/23 | 1.00 | 30000.00 | 65000.00 | 65000.00 |
| STM C440-013 | | R3 EAGLE RESIDENCY ADA RAMP I | 02/16/23 | 1.00 | 45000.00 | 35000.00 | 35000.00 |
| NHPP0253-290 | | I25 @ 58TH AND 62ND | 03/02/23 | 1.00 | 34000.00 | 48200.55 | 54000.00 |
| SHE067A-044 | | SH 67F M.P. 56.5-57.6 AND SH | 03/02/23 | 1.00 | 35000.00 | 47817.00 | 47817.00 |
| STR194A-002 | | SH194A SUR. TREAT.& DRAI IMP | 03/09/23 | 1.00 | 36500.00 | 52000.00 | 46000.00 |
| STA257A-008 | | SH 257 WINDSOR RESURFACING | 03/30/23 | 1.00 | 25000.00 | 26250.00 | 37000.00 |
| | WEIGHTED AVERAGE FOR THE FIRST QUARTER | | | 10.00 | 36550.00 | 39301.01 | 41182.86 |
| | WEIGHTED AVERAGE FOR THE YEAR | | | 10.00 | 36550.00 | 39301.01 | 41182.86 |
| ===== 620-00012 | | Field Lab (CL 2) | | Each ===== | | | |
| STA172A-022 | | SH 172 IGNACIO TO ELMORE'S CO | 01/12/23 | 1.00 | 55000.00 | 32028.83 | 30837.65 |
| NHPP0701-250 | | I-70B: DDI TO 24 RD, MAIN ST | 01/12/23 | 1.00 | 40000.00 | 28335.00 | 15570.00 |
| STR2871-040 | | US 287 MP 0.0 TO MP 122 VARIO | 01/12/23 | 1.00 | 25000.00 | 33871.38 | 25044.40 |
| FSA0853-123 | | US 85 AND WCR 66 LEFT TURN AC | 01/26/23 | 1.00 | 30000.00 | 23583.33 | 16500.00 |
| STA066A-008 | | SH 66 @ WCR 7 | 01/26/23 | 1.00 | 30000.00 | 31878.56 | 23950.00 |
| C0703-498 | | EISENHOWER JOHNSON MEMORIAL T | 02/16/23 | 1.00 | 45000.00 | 29043.79 | 49000.00 |
| STA1381-011 | | SH 138 STERLING NORTH PART 2 | 02/16/23 | 1.00 | 35000.00 | 80000.00 | 80000.00 |
| NHPP0253-290 | | I25 @ 58TH AND 62ND | 03/02/23 | 1.00 | 32000.00 | 41993.80 | 44000.00 |
| SHE067A-044 | | SH 67F M.P. 56.5-57.6 AND SH | 03/02/23 | 1.00 | 30000.00 | 28526.85 | 28526.85 |
| STR194A-002 | | SH194A SUR. TREAT.& DRAI IMP | 03/09/23 | 1.00 | 28200.00 | 49500.00 | 45000.00 |
| STA257A-008 | | SH 257 WINDSOR RESURFACING | 03/30/23 | 1.00 | 20000.00 | 21750.00 | 29400.00 |
| | WEIGHTED AVERAGE FOR THE FIRST QUARTER | | | 11.00 | 33654.55 | 32972.41 | 35257.17 |
| | WEIGHTED AVERAGE FOR THE YEAR | | | 11.00 | 33654.55 | 32972.41 | 35257.17 |
| ===== 620-00020 | | Sanitary Facility | | Each ===== | | | |
| STA172A-022 | | SH 172 IGNACIO TO ELMORE'S CO | 01/12/23 | 2.00 | 5000.00 | 7485.21 | 12760.41 |
| NHPP0701-250 | | I-70B: DDI TO 24 RD, MAIN ST | 01/12/23 | 1.00 | 4000.00 | 4740.00 | 6980.00 |
| STR2871-040 | | US 287 MP 0.0 TO MP 122 VARIO | 01/12/23 | 1.00 | 2000.00 | 3197.73 | 1693.60 |
| SFTYR200-277 | | REGION 2 WIDE, VARIOUS HWY & | 01/19/23 | 1.00 | 10000.00 | 5250.00 | 3500.00 |
| FSA0853-123 | | US 85 AND WCR 66 LEFT TURN AC | 01/26/23 | 1.00 | 3500.00 | 2370.00 | 6500.00 |
| NHPPR100-383 | | I70 OVER WASHINGTON ST | 01/26/23 | 1.00 | 1500.00 | 5759.87 | 3200.00 |
| STA066A-008 | | SH 66 @ WCR 7 | 01/26/23 | 3.00 | 3000.00 | 3401.44 | 3090.00 |
| C0342-066 | | US 034A (MP 113-150) | 02/02/23 | 1.00 | 3500.00 | 1527.67 | 713.00 |
| STA1381-011 | | SH 138 STERLING NORTH PART 2 | 02/16/23 | 1.00 | 10000.00 | 13000.00 | 13000.00 |
| C133A-052 | | SH 133 ROCKFALL N OF MCCLURE | 02/16/23 | 1.00 | 3000.00 | 4750.00 | 11000.00 |

| PROJECT NUMBER | ITEM NUMBER/ PROJECT LOCATION | ITEM DESCRIPTION/ PROJECT LOCATION | DATE LET | UNIT/ QUANTITY | ENGR. EST. | AVERAGE BID | AWARDED BID |
|---|--|---------------------------------------|----------|-------------------|------------|-------------|-------------|
| ===== 620-00020 Sanitary Facility Each ===== | | | | | | | |
| C1601-084 | | US 160 SECTION3 PRIORITY CULV | 02/16/23 | 1.00 | 4000.00 | 7011.63 | 2400.00 |
| C 1601-086 | | MAPLE & CHESTNUT SIGNALS AT I | 02/16/23 | 2.00 | 5000.00 | 1800.00 | 1800.00 |
| STM C440-013 | | R3 EAGLE RESIDENCY ADA RAMP I | 02/16/23 | 1.00 | 5000.00 | 5000.00 | 5000.00 |
| NHPP0701-256 | | I-70B/31.5 RD MESA COUNTY | 02/16/23 | 1.00 | 3000.00 | 2000.00 | 500.00 |
| NHPP0253-290 | | I25 @ 58TH AND 62ND | 03/02/23 | 2.00 | 2500.00 | 3647.68 | 3500.00 |
| SHE067A-044 | | SH 67F M.P. 56.5-57.6 AND SH | 03/02/23 | 2.00 | 3500.00 | 8019.00 | 8019.00 |
| STR194A-002 | | SH194A SUR. TREAT.& DRAI IMP | 03/09/23 | 1.00 | 3200.00 | 7000.00 | 5000.00 |
| FBR 0703-520 | | EISENHOWER-JOHNSON MEMORIAL T | 03/16/23 | 2.00 | 9000.00 | 22500.00 | 10000.00 |
| STA257A-008 | | SH 257 WINDSOR RESURFACING | 03/30/23 | 2.00 | 3000.00 | 4850.00 | 7500.00 |
| NHPP R100-376 | | VARIOUS LOCATIONS IN REGION 1 | 03/30/23 | 2.00 | 5000.00 | 2007.10 | 2250.00 |
| | WEIGHTED AVERAGE FOR THE FIRST QUARTER | | | 29.00 | 4403.45 | 5148.50 | 5531.57 |
| | WEIGHTED AVERAGE FOR THE YEAR | | | 29.00 | 4403.45 | 5148.50 | 5531.57 |
| ===== 621-00425 Detour LUMP SUM ===== | | | | | | | |
| C1601-084 | | US 160 SECTION3 PRIORITY CULV | 02/16/23 | 1.00 | 50000.00 | 55712.27 | 27000.00 |
| SHE067A-044 | | SH 67F M.P. 56.5-57.6 AND SH | 03/02/23 | 1.00 | 150000.00 | 35640.00 | 35640.00 |
| | WEIGHTED AVERAGE FOR THE FIRST QUARTER | | | 2.00 | 100000.00 | 49021.51 | 31320.00 |
| | WEIGHTED AVERAGE FOR THE YEAR | | | 2.00 | 100000.00 | 49021.51 | 31320.00 |
| ===== 621-00450 Detour Pvmt Sq Yard ===== | | | | | | | |
| NHPP0253-290 | | I25 @ 58TH AND 62ND | 03/02/23 | 780.00 | 70.00 | 84.92 | 3.00 |
| STA257A-008 | | SH 257 WINDSOR RESURFACING | 03/30/23 | 1,004.00 | 80.00 | 54.25 | 50.00 |
| | WEIGHTED AVERAGE FOR THE FIRST QUARTER | | | 1,784.00 | 75.63 | 70.75 | 29.45 |
| | WEIGHTED AVERAGE FOR THE YEAR | | | 1,784.00 | 75.63 | 70.75 | 29.45 |
| ===== 624-20025 24 In Drainage Pipe (CL 0) (CIP) Lin Foot ===== | | | | | | | |
| C133A-052 | | SH 133 ROCKFALL N OF MCCLURE | 02/16/23 | 120.00 | 100.00 | 437.19 | 700.00 |
| | WEIGHTED AVERAGE FOR THE FIRST QUARTER | | | 120.00 | 100.00 | 437.19 | 700.00 |
| | WEIGHTED AVERAGE FOR THE YEAR | | | 120.00 | 100.00 | 437.19 | 700.00 |
| ===== 624-29016 15 In Drainage Pipe (CL 9) (CIP) Lin Foot ===== | | | | | | | |
| NHPP0253-296 | | I-25 @ LCR 16 (MP 253.8-254.5 | 02/07/23 | 7.00 | 312.53 | 334.41 | 334.41 |
| | WEIGHTED AVERAGE FOR THE FIRST QUARTER | | | 7.00 | 312.53 | 334.41 | 334.41 |
| | WEIGHTED AVERAGE FOR THE YEAR | | | 7.00 | 312.53 | 334.41 | 334.41 |

| PROJECT NUMBER | ITEM NUMBER/ PROJECT LOCATION | ITEM DESCRIPTION/ PROJECT LOCATION | DATE LET | UNIT/ QUANTITY | ENGR. EST. | AVERAGE BID | AWARDED BID |
|-----------------|--|---------------------------------------|----------|-------------------|------------|-------------|-------------|
| ===== 624-29019 | | 18 In Drainage Pipe (CL 9) (CIP) | | Lin Foot | ===== | | |
| NHPP0253-296 | | I-25 @ LCR 16 (MP 253.8-254.5 | 02/07/23 | 237.00 | 119.14 | 127.48 | 127.48 |
| | WEIGHTED AVERAGE FOR THE FIRST QUARTER | | | 237.00 | 119.14 | 127.48 | 127.48 |
| | WEIGHTED AVERAGE FOR THE YEAR | | | 237.00 | 119.14 | 127.48 | 127.48 |
| ===== 624-29025 | | 24 In Drainage Pipe (CL 9) (CIP) | | Lin Foot | ===== | | |
| NHPP0253-296 | | I-25 @ LCR 16 (MP 253.8-254.5 | 02/07/23 | 166.00 | 139.10 | 148.84 | 148.84 |
| | WEIGHTED AVERAGE FOR THE FIRST QUARTER | | | 166.00 | 139.10 | 148.84 | 148.84 |
| | WEIGHTED AVERAGE FOR THE YEAR | | | 166.00 | 139.10 | 148.84 | 148.84 |
| ===== 624-29061 | | 60 In Drainage Pipe (CL 9) (CIP) | | Lin Foot | ===== | | |
| NHPP0253-296 | | I-25 @ LCR 16 (MP 253.8-254.5 | 02/07/23 | 837.00 | 385.64 | 412.63 | 412.63 |
| | WEIGHTED AVERAGE FOR THE FIRST QUARTER | | | 837.00 | 385.64 | 412.63 | 412.63 |
| | WEIGHTED AVERAGE FOR THE YEAR | | | 837.00 | 385.64 | 412.63 | 412.63 |
| ===== 625-00000 | | Const Surveying | | LUMP SUM | ===== | | |
| STA172A-022 | | SH 172 IGNACIO TO ELMORE'S CO | 01/12/23 | 1.00 | 75000.00 | 156212.72 | 154745.44 |
| FSA0853-123 | | US 85 AND WCR 66 LEFT TURN AC | 01/26/23 | 1.00 | 20000.00 | 31866.67 | 12500.00 |
| STA066A-008 | | SH 66 @ WCR 7 | 01/26/23 | 1.00 | 30000.00 | 31051.00 | 27250.00 |
| C0342-066 | | US 034A (MP 113-150) | 02/02/23 | 1.00 | 20000.00 | 13669.67 | 16009.00 |
| NHPP0253-296 | | I-25 @ LCR 16 (MP 253.8-254.5 | 02/07/23 | 1.00 | 51843.63 | 55472.77 | 55472.77 |
| C0703-498 | | EISENHOWER JOHNSON MEMORIAL T | 02/16/23 | 1.00 | 45000.00 | 66105.07 | 36000.00 |
| STA1381-011 | | SH 138 STERLING NORTH PART 2 | 02/16/23 | 1.00 | 120000.00 | 165000.00 | 165000.00 |
| C1601-084 | | US 160 SECTION3 PRIORITY CULV | 02/16/23 | 1.00 | 60000.00 | 21241.43 | 22000.00 |
| C 1601-086 | | MAPLE & CHESTNUT SIGNALS AT I | 02/16/23 | 1.00 | 30000.00 | 19000.00 | 19000.00 |
| STM C440-013 | | R3 EAGLE RESIDENCY ADA RAMP I | 02/16/23 | 1.00 | 15000.00 | 12520.00 | 12520.00 |
| NHPP0701-256 | | I-70B/31.5 RD MESA COUNTY | 02/16/23 | 1.00 | 15000.00 | 14136.00 | 20000.00 |
| SHE067A-044 | | SH 67F M.P. 56.5-57.6 AND SH | 03/02/23 | 1.00 | 30000.00 | 23522.40 | 23522.40 |
| STR194A-002 | | SH194A SUR. TREAT.& DRAI IMP | 03/09/23 | 1.00 | 100000.00 | 50500.00 | 60000.00 |
| STA257A-008 | | SH 257 WINDSOR RESURFACING | 03/30/23 | 1.00 | 40000.00 | 71900.00 | 77000.00 |
| | WEIGHTED AVERAGE FOR THE FIRST QUARTER | | | 14.00 | 46560.26 | 46539.83 | 50072.83 |
| | WEIGHTED AVERAGE FOR THE YEAR | | | 14.00 | 46560.26 | 46539.83 | 50072.83 |

| PROJECT NUMBER | ITEM NUMBER/ PROJECT LOCATION | ITEM DESCRIPTION/ PROJECT LOCATION | DATE LET | UNIT/ QUANTITY | ENGR. EST. | AVERAGE BID | AWARDED BID |
|----------------|--|---------------------------------------|----------|-------------------|------------|-------------|-------------|
| ===== | 625-00001 | Const Surveying (Hour) | | Hour | ===== | ===== | ===== |
| NHPPR100-383 | I70 OVER WASHINGTON ST | | 01/26/23 | 60.00 | 250.00 | 217.83 | 215.00 |
| C133A-052 | SH 133 ROCKFALL N OF MCCLURE | | 02/16/23 | 92.00 | 250.00 | 242.88 | 300.00 |
| STM C440-013 | R3 EAGLE RESIDENCY ADA RAMP I | | 02/16/23 | 10.00 | 180.00 | 179.00 | 179.00 |
| C0881-036 | R1 CURB RAMPS-SH88B & US285D | | 02/16/23 | 40.00 | 225.00 | 296.25 | 175.00 |
| NHPP R100-376 | VARIOUS LOCATIONS IN REGION 1 | | 03/30/23 | 10.00 | 215.36 | 1791.44 | 275.00 |
| | WEIGHTED AVERAGE FOR THE FIRST QUARTER | | | 212.00 | 240.35 | 289.44 | 245.47 |
| | WEIGHTED AVERAGE FOR THE YEAR | | | 212.00 | 240.35 | 289.44 | 245.47 |
| ===== | 626-00000 | Mobilization | | LUMP SUM | ===== | ===== | ===== |
| MTCER500-221 | REGION 5 | | 01/05/23 | 1.00 | 65000.00 | 132500.00 | 90000.00 |
| STA172A-022 | SH 172 IGNACIO TO ELMORE'S CO | | 01/12/23 | 1.00 | 1500000.00 | 1012819.64 | 750639.27 |
| NHPP0701-250 | I-70B: DDI TO 24 RD, MAIN ST | | 01/12/23 | 1.00 | 1000000.00 | 1062500.00 | 960000.00 |
| STR2871-040 | US 287 MP 0.0 TO MP 122 VARIO | | 01/12/23 | 1.00 | 298110.00 | 405648.20 | 183241.00 |
| SFTYR200-277 | REGION 2 WIDE, VARIOUS HWY & | | 01/19/23 | 1.00 | 368925.00 | 613775.00 | 560000.00 |
| FSA0853-123 | US 85 AND WCR 66 LEFT TURN AC | | 01/26/23 | 1.00 | 86512.00 | 147075.83 | 192500.00 |
| NHPPR100-383 | I70 OVER WASHINGTON ST | | 01/26/23 | 1.00 | 256041.00 | 303400.53 | 242000.00 |
| STA066A-008 | SH 66 @ WCR 7 | | 01/26/23 | 1.00 | 182020.00 | 412362.00 | 218875.00 |
| C0342-066 | US 034A (MP 113-150) | | 02/02/23 | 1.00 | 39590.00 | 89785.33 | 54356.00 |
| C0703-498 | EISENHOWER JOHNSON MEMORIAL T | | 02/16/23 | 1.00 | 500000.00 | 823940.22 | 657000.00 |
| STA1381-011 | SH 138 STERLING NORTH PART 2 | | 02/16/23 | 1.00 | 755937.90 | 890000.00 | 890000.00 |
| C133A-052 | SH 133 ROCKFALL N OF MCCLURE | | 02/16/23 | 1.00 | 220000.00 | 651781.75 | 389258.00 |
| C1601-084 | US 160 SECTION3 PRIORITY CULV | | 02/16/23 | 1.00 | 270000.00 | 388425.95 | 195000.00 |
| C 1601-086 | MAPLE & CHESTNUT SIGNALS AT I | | 02/16/23 | 1.00 | 200000.00 | 163000.00 | 163000.00 |
| STM C440-013 | R3 EAGLE RESIDENCY ADA RAMP I | | 02/16/23 | 1.00 | 80000.00 | 247650.00 | 247650.00 |
| NHPP0701-256 | I-70B/31.5 RD MESA COUNTY | | 02/16/23 | 1.00 | 50000.00 | 124616.00 | 93000.00 |
| C0881-036 | R1 CURB RAMPS-SH88B & US285D | | 02/16/23 | 1.00 | 805965.00 | 232020.50 | 258312.00 |
| NHPP0253-290 | I25 @ 58TH AND 62ND | | 03/02/23 | 1.00 | 506433.50 | 310382.50 | 280000.00 |
| SHE067A-044 | SH 67F M.P. 56.5-57.6 AND SH | | 03/02/23 | 1.00 | 783603.00 | 210344.67 | 210344.67 |
| STRR300-265 | MOUNTAIN RE FY23 CRACK SEALS | | 03/02/23 | 1.00 | 120000.00 | 200000.00 | 200000.00 |
| STR194A-002 | SH194A SUR. TREAT.& DRAI IMP | | 03/09/23 | 1.00 | 846348.08 | 795780.00 | 667560.00 |
| MTCER300-276 | I-70 MM 116-207, US 6F MM 208 | | 03/16/23 | 1.00 | 50000.00 | 42500.00 | 50000.00 |
| STA257A-008 | SH 257 WINDSOR RESURFACING | | 03/30/23 | 1.00 | 562770.50 | 330000.00 | 350000.00 |
| NHPP R100-376 | VARIOUS LOCATIONS IN REGION 1 | | 03/30/23 | 1.00 | 828243.26 | 623350.00 | 246700.00 |
| ER0703-524 | STRUCTURE F-13-P, EB I-70 EXI | | 03/31/23 | 1.00 | 250500.00 | 283511.20 | 250500.00 |
| | WEIGHTED AVERAGE FOR THE FIRST QUARTER | | | 25.00 | 425039.97 | 404754.72 | 335997.44 |
| | WEIGHTED AVERAGE FOR THE YEAR | | | 25.00 | 425039.97 | 404754.72 | 335997.44 |
| ===== | 626-00007 | Mobilization | | Each | ===== | ===== | ===== |
| FBR 0703-520 | EISENHOWER-JOHNSON MEMORIAL T | | 03/16/23 | 1.00 | 3000000.00 | 4887500.00 | 5000000.00 |
| | WEIGHTED AVERAGE FOR THE FIRST QUARTER | | | 1.00 | 3000000.00 | 4887500.00 | 5000000.00 |
| | WEIGHTED AVERAGE FOR THE YEAR | | | 1.00 | 3000000.00 | 4887500.00 | 5000000.00 |

COLORADO DEPARTMENT OF TRANSPORTATION
 ITEM UNIT COSTS BY PROJECTS -- 2023 COST DATA

12:26 Wednesday, May 17, 2023 108

| PROJECT NUMBER | ITEM NUMBER/ PROJECT LOCATION | ITEM DESCRIPTION/ PROJECT LOCATION | DATE LET | UNIT/ QUANTITY | ENGR. EST. | AVERAGE BID | AWARDED BID |
|----------------|----------------------------------|---------------------------------------|----------|-------------------|------------|-------------|-------------|
| ===== | 626-00100 | Mobilization (w/o Autopay) | | LUMP SUM | ===== | | |
| NHPP0253-296 | | I-25 @ LCR 16 (MP 253.8-254.5 | 02/07/23 | 1.00 | 179036.81 | 204795.55 | 204795.55 |
| | WEIGHTED | AVERAGE FOR THE FIRST QUARTER | | 1.00 | 179036.81 | 204795.55 | 204795.55 |
| | | WEIGHTED AVERAGE FOR THE YEAR | | 1.00 | 179036.81 | 204795.55 | 204795.55 |
| ===== | 626-01113 | Public Info Manage (Tier III) | | Day | ===== | | |
| STA172A-022 | | SH 172 IGNACIO TO ELMORE'S CO | 01/12/23 | 280.00 | 80.00 | 54.40 | 55.30 |
| NHPP0701-250 | | I-70B: DDI TO 24 RD, MAIN ST | 01/12/23 | 108.00 | 250.00 | 88.80 | 77.60 |
| STR2871-040 | | US 287 MP 0.0 TO MP 122 VARIO | 01/12/23 | 126.00 | 120.00 | 76.03 | 80.04 |
| NHPPR100-383 | | I70 OVER WASHINGTON ST | 01/26/23 | 200.00 | 100.00 | 109.93 | 95.00 |
| C133A-052 | | SH 133 ROCKFALL N OF MCCLURE | 02/16/23 | 212.00 | 70.00 | 58.88 | 65.00 |
| NHPP0701-256 | | I-70B/31.5 RD MESA COUNTY | 02/16/23 | 72.00 | 100.00 | 92.00 | 65.00 |
| C0881-036 | | R1 CURB RAMPS-SH88B & US285D | 02/16/23 | 196.00 | 90.00 | 302.50 | 90.00 |
| NHPP0253-290 | | I25 @ 58TH AND 62ND | 03/02/23 | 80.00 | 120.00 | 92.02 | 98.00 |
| STR194A-002 | | SH194A SUR. TREAT.& DRAI IMP | 03/09/23 | 133.00 | 87.00 | 75.00 | 80.00 |
| | WEIGHTED | AVERAGE FOR THE FIRST QUARTER | | 1,407.00 | 103.32 | 117.97 | 76.42 |
| | | WEIGHTED AVERAGE FOR THE YEAR | | 1,407.00 | 103.32 | 117.97 | 76.42 |
| ===== | 626-01114 | Public Info Manage (Tier IV) | | Day | ===== | | |
| MTCER500-221 | | REGION 5 | 01/05/23 | 95.00 | 85.00 | 100.00 | 85.00 |
| SFTYR200-277 | | REGION 2 WIDE, VARIOUS HWY & | 01/19/23 | 120.00 | 150.00 | 90.00 | 95.00 |
| STA066A-008 | | SH 66 @ WCR 7 | 01/26/23 | 117.00 | 70.00 | 73.12 | 72.00 |
| C0342-066 | | US 034A (MP 113-150) | 02/02/23 | 52.00 | 85.00 | 108.00 | 121.00 |
| C1601-084 | | US 160 SECTION3 PRIORITY CULV | 02/16/23 | 241.00 | 180.00 | 91.77 | 41.00 |
| C 1601-086 | | MAPLE & CHESTNUT SIGNALS AT I | 02/16/23 | 80.00 | 75.00 | 146.00 | 146.00 |
| STM C440-013 | | R3 EAGLE RESIDENCY ADA RAMP I | 02/16/23 | 55.00 | 80.00 | 99.00 | 99.00 |
| SHE067A-044 | | SH 67F M.P. 56.5-57.6 AND SH | 03/02/23 | 150.00 | 100.00 | 77.22 | 77.22 |
| STRR300-265 | | MOUNTAIN RE FY23 CRACK SEALS | 03/02/23 | 100.00 | 100.00 | 65.00 | 65.00 |
| NHPP R100-376 | | VARIOUS LOCATIONS IN REGION 1 | 03/30/23 | 84.00 | 100.00 | 109.11 | 130.00 |
| | WEIGHTED | AVERAGE FOR THE FIRST QUARTER | | 1,094.00 | 115.05 | 89.75 | 82.45 |
| | | WEIGHTED AVERAGE FOR THE YEAR | | 1,094.00 | 115.05 | 89.75 | 82.45 |
| ===== | 627-00001 | Pvmt Mkg Paint | | Gallon | ===== | | |
| STR2871-040 | | US 287 MP 0.0 TO MP 122 VARIO | 01/12/23 | 10.00 | 150.00 | 248.97 | 290.00 |

COLORADO DEPARTMENT OF TRANSPORTATION
ITEM UNIT COSTS BY PROJECTS -- 2023 COST DATA

12:26 Wednesday, May 17, 2023 109

| PROJECT NUMBER | ITEM NUMBER/ PROJECT LOCATION | ITEM DESCRIPTION/ PROJECT LOCATION | DATE LET | UNIT/ QUANTITY | ENGR. EST. | AVERAGE BID | AWARDED BID |
|----------------|--|---------------------------------------|----------|-------------------|------------|-------------|-------------|
| ===== | 627-00001 | Pvmt Mkg Paint | | Gallon | ===== | ===== | ===== |
| STR194A-002 | | SH194A SUR. TREAT.& DRAI IMP | 03/09/23 | 2,168.00 | 51.00 | 64.00 | 77.00 |
| | WEIGHTED AVERAGE FOR THE FIRST QUARTER | | | 2,178.00 | 51.45 | 66.11 | 77.98 |
| | WEIGHTED AVERAGE FOR THE YEAR | | | 2,178.00 | 51.45 | 66.11 | 77.98 |
| ===== | 627-00008 | Mod Epoxy Pvmt Mkg | | Gallon | ===== | ===== | ===== |
| NHPP0701-250 | | I-70B: DDI TO 24 RD, MAIN ST | 01/12/23 | 914.00 | 160.00 | 146.00 | 140.00 |
| STR2871-040 | | US 287 MP 0.0 TO MP 122 VARIO | 01/12/23 | 10.00 | 300.00 | 518.32 | 667.00 |
| FSA0853-123 | | US 85 AND WCR 66 LEFT TURN AC | 01/26/23 | 30.00 | 250.00 | 432.83 | 410.00 |
| STA066A-008 | | SH 66 @ WCR 7 | 01/26/23 | 171.00 | 160.00 | 192.37 | 175.00 |
| NHPP0253-296 | | I-25 @ LCR 16 (MP 253.8-254.5 | 02/07/23 | 87.00 | 203.18 | 217.40 | 217.40 |
| C0703-498 | | EISENHOWER JOHNSON MEMORIAL T | 02/16/23 | 115.00 | 200.00 | 251.75 | 220.00 |
| STA1381-011 | | SH 138 STERLING NORTH PART 2 | 02/16/23 | 775.00 | 150.00 | 230.00 | 230.00 |
| NHPP0701-256 | | I-70B/31.5 RD MESA COUNTY | 02/16/23 | 8.00 | 350.00 | 262.50 | 300.00 |
| NHPP0253-290 | | I25 @ 58TH AND 62ND | 03/02/23 | 20.00 | 200.00 | 517.67 | 670.00 |
| SHE067A-044 | | SH 67F M.P. 56.5-57.6 AND SH | 03/02/23 | 69.00 | 200.00 | 267.30 | 267.30 |
| MTCER300-276 | | I-70 MM 116-207, US 6F MM 208 | 03/16/23 | 22,553.00 | 100.00 | 89.00 | 90.00 |
| STA257A-008 | | SH 257 WINDSOR RESURFACING | 03/30/23 | 556.00 | 90.00 | 162.50 | 140.00 |
| | WEIGHTED AVERAGE FOR THE FIRST QUARTER | | | 25,308.00 | 105.38 | 100.39 | 100.41 |
| | WEIGHTED AVERAGE FOR THE YEAR | | | 25,308.00 | 105.38 | 100.39 | 100.41 |
| ===== | 627-00009 | Mod Epoxy (Inlaid) | | Gallon | ===== | ===== | ===== |
| SHE067A-044 | | SH 67F M.P. 56.5-57.6 AND SH | 03/02/23 | 48.00 | 300.00 | 552.42 | 552.42 |
| | WEIGHTED AVERAGE FOR THE FIRST QUARTER | | | 48.00 | 300.00 | 552.42 | 552.42 |
| | WEIGHTED AVERAGE FOR THE YEAR | | | 48.00 | 300.00 | 552.42 | 552.42 |
| ===== | 627-00011 | Pvmt Mkg Paint (Waterborne) | | Gallon | ===== | ===== | ===== |
| STA1381-011 | | SH 138 STERLING NORTH PART 2 | 02/16/23 | 1,977.00 | 60.00 | 80.00 | 80.00 |
| | WEIGHTED AVERAGE FOR THE FIRST QUARTER | | | 1,977.00 | 60.00 | 80.00 | 80.00 |
| | WEIGHTED AVERAGE FOR THE YEAR | | | 1,977.00 | 60.00 | 80.00 | 80.00 |
| ===== | 627-00013 | Pvmt Mkg Paint (High Build) | | Gallon | ===== | ===== | ===== |
| MTCER500-221 | | REGION 5 | 01/05/23 | 45,300.00 | 40.00 | 41.53 | 42.30 |

| PROJECT NUMBER | ITEM NUMBER/ PROJECT LOCATION | ITEM DESCRIPTION/ PROJECT LOCATION | DATE LET | UNIT/ QUANTITY | ENGR. EST. | AVERAGE BID | AWARDED BID |
|-----------------|--|---|----------|-------------------|------------|-------------|-------------|
| ===== 627-00013 | | Pvmt Mkg Paint (High Build) | | Gallon | | | |
| STA172A-022 | | SH 172 IGNACIO TO ELMORE'S CO | 01/12/23 | 10,522.00 | 40.00 | 51.04 | 51.89 |
| NHPP0701-250 | | I-70B: DDI TO 24 RD, MAIN ST | 01/12/23 | 1,459.00 | 170.00 | 115.20 | 88.40 |
| FSA0853-123 | | US 85 AND WCR 66 LEFT TURN AC | 01/26/23 | 100.00 | 130.00 | 169.67 | 162.00 |
| NHPPR100-383 | | I70 OVER WASHINGTON ST | 01/26/23 | 4.00 | 250.00 | 2238.33 | 125.00 |
| STA066A-008 | | SH 66 @ WCR 7 | 01/26/23 | 433.00 | 70.00 | 54.13 | 50.42 |
| C133A-052 | | SH 133 ROCKFALL N OF MCCLURE | 02/16/23 | 5.00 | 190.00 | 565.75 | 1200.00 |
| C1601-084 | | US 160 SECTION3 PRIORITY CULV | 02/16/23 | 4.00 | 1000.00 | 507.76 | 260.00 |
| C0881-036 | | R1 CURB RAMPS-SH88B & US285D | 02/16/23 | 10.00 | 70.00 | 892.50 | 475.00 |
| NHPP0253-290 | | I25 @ 58TH AND 62ND | 03/02/23 | 26.00 | 125.00 | 97.08 | 115.00 |
| SHE067A-044 | | SH 67F M.P. 56.5-57.6 AND SH | 03/02/23 | 10.00 | 100.00 | 178.20 | 178.20 |
| STR194A-002 | | SH194A SUR. TREAT.& DRAI IMP | 03/09/23 | 1,008.00 | 52.00 | 51.00 | 49.00 |
| STA257A-008 | | SH 257 WINDSOR RESURFACING | 03/30/23 | 340.00 | 50.00 | 110.00 | 90.00 |
| ER0703-524 | | STRUCTURE F-13-P, EB I-70 EXI | 03/31/23 | 10.00 | 207.00 | 216.14 | 207.00 |
| | WEIGHTED AVERAGE FOR THE FIRST QUARTER | | | 59,231.00 | 44.01 | 47.10 | 46.06 |
| | WEIGHTED AVERAGE FOR THE YEAR | | | 59,231.00 | 44.01 | 47.10 | 46.06 |
| ===== 627-00014 | | Pvmt Mkg Paint (Low Temp) | | Gallon | | | |
| C0703-498 | | EISENHOWER JOHNSON MEMORIAL T | 02/16/23 | 6.00 | 150.00 | 352.05 | 120.00 |
| | WEIGHTED AVERAGE FOR THE FIRST QUARTER | | | 6.00 | 150.00 | 352.05 | 120.00 |
| | WEIGHTED AVERAGE FOR THE YEAR | | | 6.00 | 150.00 | 352.05 | 120.00 |
| ===== 627-01001 | | Preform Plastic Pvmt Mkg (Ty I) | | Sq Foot | | | |
| NHPP0253-290 | | I25 @ 58TH AND 62ND | 03/02/23 | 75.00 | 15.00 | 31.35 | 40.00 |
| | WEIGHTED AVERAGE FOR THE FIRST QUARTER | | | 75.00 | 15.00 | 31.35 | 40.00 |
| | WEIGHTED AVERAGE FOR THE YEAR | | | 75.00 | 15.00 | 31.35 | 40.00 |
| ===== 627-01010 | | Preform Plastic Pvmt Mkg (TY I) (Inlaid) | | Sq Foot | | | |
| NHPP0253-296 | | I-25 @ LCR 16 (MP 253.8-254.5 | 02/07/23 | 45.00 | 33.48 | 35.82 | 35.82 |
| | WEIGHTED AVERAGE FOR THE FIRST QUARTER | | | 45.00 | 33.48 | 35.82 | 35.82 |
| | WEIGHTED AVERAGE FOR THE YEAR | | | 45.00 | 33.48 | 35.82 | 35.82 |
| ===== 627-01011 | | Preform Plastic Pvmt Mkg (Contr) (Inlaid) | | Sq Foot | | | |
| NHPP0253-290 | | I25 @ 58TH AND 62ND | 03/02/23 | 75.00 | 20.00 | 31.35 | 40.00 |
| | WEIGHTED AVERAGE FOR THE FIRST QUARTER | | | 75.00 | 20.00 | 31.35 | 40.00 |
| | WEIGHTED AVERAGE FOR THE YEAR | | | 75.00 | 20.00 | 31.35 | 40.00 |

COLORADO DEPARTMENT OF TRANSPORTATION
ITEM UNIT COSTS BY PROJECTS -- 2023 COST DATA

12:26 Wednesday, May 17, 2023 111

| PROJECT NUMBER | ITEM NUMBER/ PROJECT LOCATION | ITEM DESCRIPTION/ PROJECT LOCATION | DATE LET | UNIT/ QUANTITY | ENGR. EST. | AVERAGE BID | AWARDED BID |
|----------------|----------------------------------|---|----------|-------------------|------------|-------------|-------------|
| ===== | 627-02001 | Preform Plastic Pvmt Mkg (Ty II) | | Sq Foot | ===== | ===== | ===== |
| NHPPR100-383 | | I70 OVER WASHINGTON ST | 01/26/23 | 320.00 | 25.00 | 52.47 | 31.00 |
| | WEIGHTED | AVERAGE FOR THE FIRST QUARTER | | 320.00 | 25.00 | 52.47 | 31.00 |
| | | WEIGHTED AVERAGE FOR THE YEAR | | 320.00 | 25.00 | 52.47 | 31.00 |
| ===== | 627-02010 | Preform Plastic Pvmt Mkg (Ty II) (Inlaid) | | Sq Foot | ===== | ===== | ===== |
| NHPP0253-290 | | I25 @ 58TH AND 62ND | 03/02/23 | 67.00 | 23.00 | 36.23 | 45.00 |
| | WEIGHTED | AVERAGE FOR THE FIRST QUARTER | | 67.00 | 23.00 | 36.23 | 45.00 |
| | | WEIGHTED AVERAGE FOR THE YEAR | | 67.00 | 23.00 | 36.23 | 45.00 |
| ===== | 627-30405 | Preform Thermoplastic Pvmt Mkg (WS) | | Sq Foot | ===== | ===== | ===== |
| STA172A-022 | | SH 172 IGNACIO TO ELMORE'S CO | 01/12/23 | 3,514.00 | 30.00 | 19.90 | 20.20 |
| NHPPR100-383 | | I70 OVER WASHINGTON ST | 01/26/23 | 156.00 | 30.00 | 47.93 | 28.00 |
| STA066A-008 | | SH 66 @ WCR 7 | 01/26/23 | 835.00 | 30.00 | 26.04 | 26.10 |
| NHPP0253-296 | | I-25 @ LCR 16 (MP 253.8-254.5) | 02/07/23 | 63.00 | 26.81 | 28.69 | 28.69 |
| STA1381-011 | | SH 138 STERLING NORTH PART 2 | 02/16/23 | 410.00 | 20.00 | 33.00 | 33.00 |
| STA257A-008 | | SH 257 WINDSOR RESURFACING | 03/30/23 | 1,554.00 | 22.00 | 21.00 | 22.00 |
| | WEIGHTED | AVERAGE FOR THE FIRST QUARTER | | 6,532.00 | 27.44 | 23.05 | 22.45 |
| | | WEIGHTED AVERAGE FOR THE YEAR | | 6,532.00 | 27.44 | 23.05 | 22.45 |
| ===== | 627-30407 | Preform Thermoplastic Pvmt Mkg (WS) (Sp) | | Sq Foot | ===== | ===== | ===== |
| NHPP0701-250 | | I-70B: DDI TO 24 RD, MAIN ST | 01/12/23 | 1,621.00 | 30.00 | 18.15 | 17.30 |
| NHPP0701-256 | | I-70B/31.5 RD MESA COUNTY | 02/16/23 | 30.00 | 25.00 | 19.50 | 21.00 |
| | WEIGHTED | AVERAGE FOR THE FIRST QUARTER | | 1,651.00 | 29.91 | 18.17 | 17.37 |
| | | WEIGHTED AVERAGE FOR THE YEAR | | 1,651.00 | 29.91 | 18.17 | 17.37 |
| ===== | 627-30410 | Preform Thermoplastic Pvmt Mkg (XS) | | Sq Foot | ===== | ===== | ===== |
| STA172A-022 | | SH 172 IGNACIO TO ELMORE'S CO | 01/12/23 | 4,756.00 | 30.00 | 17.79 | 18.08 |

COLORADO DEPARTMENT OF TRANSPORTATION
ITEM UNIT COSTS BY PROJECTS -- 2023 COST DATA

12:26 Wednesday, May 17, 2023 112

| PROJECT NUMBER | ITEM NUMBER/ PROJECT LOCATION | ITEM DESCRIPTION/ PROJECT LOCATION | DATE LET | UNIT/ QUANTITY | ENGR. EST. | AVERAGE BID | AWARDED BID |
|-----------------|--|--|----------|-------------------|------------|-------------|-------------|
| ===== 627-30410 | | Preform Thermoplastic Pvmt Mkg (XS) | | Sq Foot | ===== | ===== | ===== |
| STA066A-008 | SH 66 @ WCR 7 | | 01/26/23 | 304.00 | 20.00 | 19.79 | 18.98 |
| STA1381-011 | SH 138 STERLING NORTH PART 2 | | 02/16/23 | 904.00 | 14.00 | 43.00 | 43.00 |
| C0881-036 | R1 CURB RAMPS-SH88B & US285D | | 02/16/23 | 1,850.00 | 17.00 | 30.13 | 18.50 |
| STA257A-008 | SH 257 WINDSOR RESURFACING | | 03/30/23 | 2,354.00 | 20.00 | 15.00 | 15.00 |
| | WEIGHTED AVERAGE FOR THE FIRST QUARTER | | | 10,168.00 | 23.60 | 22.11 | 19.69 |
| | WEIGHTED AVERAGE FOR THE YEAR | | | 10,168.00 | 23.60 | 22.11 | 19.69 |
| ===== 627-30411 | | Preform Thermoplastic Pvmt Mkg (XS) (Sp) | | Sq Foot | ===== | ===== | ===== |
| NHPP0701-250 | I-70B: DDI TO 24 RD, MAIN ST | | 01/12/23 | 11,003.00 | 20.00 | 14.10 | 13.20 |
| STM C440-013 | R3 EAGLE RESIDENCY ADA RAMP I | | 02/16/23 | 173.00 | 20.00 | 16.00 | 16.00 |
| | WEIGHTED AVERAGE FOR THE FIRST QUARTER | | | 11,176.00 | 20.00 | 14.11 | 13.24 |
| | WEIGHTED AVERAGE FOR THE YEAR | | | 11,176.00 | 20.00 | 14.11 | 13.24 |
| ===== 629-01002 | | Survey Monument (Ty 2) | | Each | ===== | ===== | ===== |
| STR194A-002 | SH194A SUR. TREAT.& DRAI IMP | | 03/09/23 | 1.00 | 670.00 | 750.00 | 500.00 |
| | WEIGHTED AVERAGE FOR THE FIRST QUARTER | | | 1.00 | 670.00 | 750.00 | 500.00 |
| | WEIGHTED AVERAGE FOR THE YEAR | | | 1.00 | 670.00 | 750.00 | 500.00 |
| ===== 629-01005 | | Survey Monument (Ty 5) | | Each | ===== | ===== | ===== |
| STA172A-022 | SH 172 IGNACIO TO ELMORE'S CO | | 01/12/23 | 1.00 | 700.00 | 1961.89 | 3721.78 |
| | WEIGHTED AVERAGE FOR THE FIRST QUARTER | | | 1.00 | 700.00 | 1961.89 | 3721.78 |
| | WEIGHTED AVERAGE FOR THE YEAR | | | 1.00 | 700.00 | 1961.89 | 3721.78 |
| ===== 629-01006 | | Survey Monument (Ty 6) | | Each | ===== | ===== | ===== |
| STA172A-022 | SH 172 IGNACIO TO ELMORE'S CO | | 01/12/23 | 3.00 | 700.00 | 717.38 | 1254.77 |
| | WEIGHTED AVERAGE FOR THE FIRST QUARTER | | | 3.00 | 700.00 | 717.38 | 1254.77 |
| | WEIGHTED AVERAGE FOR THE YEAR | | | 3.00 | 700.00 | 717.38 | 1254.77 |

COLORADO DEPARTMENT OF TRANSPORTATION
ITEM UNIT COSTS BY PROJECTS -- 2023 COST DATA

12:26 Wednesday, May 17, 2023 113

| PROJECT NUMBER | ITEM NUMBER/ PROJECT LOCATION | ITEM DESCRIPTION/ PROJECT LOCATION | DATE LET | UNIT/ QUANTITY | ENGR. EST. | AVERAGE BID | AWARDED BID |
|-----------------|--|---------------------------------------|----------|-------------------|------------|-------------|-------------|
| ===== 629-01031 | | Survey Monument (Ty 3A) | | Each | | | |
| STA172A-022 | | SH 172 IGNACIO TO ELMORE'S CO | 01/12/23 | 11.00 | 1400.00 | 267.64 | 340.28 |
| STA066A-008 | | SH 66 @ WCR 7 | 01/26/23 | 1.00 | 1000.00 | 1983.01 | 1200.00 |
| | WEIGHTED AVERAGE FOR THE FIRST QUARTER | | | 12.00 | 1366.67 | 585.30 | 411.92 |
| | WEIGHTED AVERAGE FOR THE YEAR | | | 12.00 | 1366.67 | 585.30 | 411.92 |
| ===== 629-01050 | | Monument Box | | Each | | | |
| STR194A-002 | | SH194A SUR. TREAT.& DRAI IMP | 03/09/23 | 1.00 | 1400.00 | 750.00 | 500.00 |
| | WEIGHTED AVERAGE FOR THE FIRST QUARTER | | | 1.00 | 1400.00 | 750.00 | 500.00 |
| | WEIGHTED AVERAGE FOR THE YEAR | | | 1.00 | 1400.00 | 750.00 | 500.00 |
| ===== 629-01065 | | Survey Monument (Ty 5S) | | Each | | | |
| STM C440-013 | | R3 EAGLE RESIDENCY ADA RAMP I | 02/16/23 | 5.00 | 1000.00 | 100.00 | 100.00 |
| | WEIGHTED AVERAGE FOR THE FIRST QUARTER | | | 5.00 | 1000.00 | 100.00 | 100.00 |
| | WEIGHTED AVERAGE FOR THE YEAR | | | 5.00 | 1000.00 | 100.00 | 100.00 |
| ===== 629-01110 | | Locate Monuments | | Hour | | | |
| C0881-036 | | R1 CURB RAMPS-SH88B & US285D | 02/16/23 | 80.00 | 190.00 | 265.00 | 175.00 |
| STR194A-002 | | SH194A SUR. TREAT.& DRAI IMP | 03/09/23 | 1.00 | 170.00 | 345.00 | 500.00 |
| | WEIGHTED AVERAGE FOR THE FIRST QUARTER | | | 81.00 | 189.75 | 265.50 | 179.01 |
| | WEIGHTED AVERAGE FOR THE YEAR | | | 81.00 | 189.75 | 265.50 | 179.01 |
| ===== 630-00000 | | Flagging | | Hour | | | |
| STA172A-022 | | SH 172 IGNACIO TO ELMORE'S CO | 01/12/23 | 6,000.00 | 35.00 | 40.79 | 41.47 |
| NHPP0701-250 | | I-70B: DDI TO 24 RD, MAIN ST | 01/12/23 | 8,100.00 | 45.00 | 35.60 | 36.20 |
| STR2871-040 | | US 287 MP 0.0 TO MP 122 VARIO | 01/12/23 | 250.00 | 50.00 | 53.74 | 48.55 |
| SFTYR200-277 | | REGION 2 WIDE, VARIOUS HWY & | 01/19/23 | 700.00 | 30.00 | 42.50 | 35.00 |

COLORADO DEPARTMENT OF TRANSPORTATION
 ITEM UNIT COSTS BY PROJECTS -- 2023 COST DATA

12:26 Wednesday, May 17, 2023 114

| PROJECT NUMBER | ITEM NUMBER/ PROJECT LOCATION | ITEM DESCRIPTION/ PROJECT LOCATION | DATE LET | UNIT/ QUANTITY | ENGR. EST. | AVERAGE BID | AWARDED BID |
|----------------|----------------------------------|--|----------|-------------------|------------|-------------|-------------|
| ===== | 630-00000 | Flagging | | Hour | ===== | ===== | ===== |
| FSA0853-123 | | US 85 AND WCR 66 LEFT TURN AC | 01/26/23 | 2,000.00 | 40.00 | 48.00 | 46.00 |
| NHPPR100-383 | | I70 OVER WASHINGTON ST | 01/26/23 | 252.00 | 50.00 | 43.47 | 48.00 |
| STA066A-008 | | SH 66 @ WCR 7 | 01/26/23 | 1,500.00 | 45.00 | 50.23 | 50.00 |
| C0342-066 | | US 034A (MP 113-150) | 02/02/23 | 8.00 | 75.00 | 46.33 | 48.00 |
| NHPP0253-296 | | I-25 @ LCR 16 (MP 253.8-254.5 | 02/07/23 | 600.00 | 42.24 | 45.20 | 45.20 |
| C0703-498 | | EISENHOWER JOHNSON MEMORIAL T | 02/16/23 | 700.00 | 45.00 | 45.14 | 47.00 |
| STA1381-011 | | SH 138 STERLING NORTH PART 2 | 02/16/23 | 5,000.00 | 45.00 | 49.00 | 49.00 |
| C133A-052 | | SH 133 ROCKFALL N OF MCCLURE | 02/16/23 | 2,500.00 | 45.00 | 50.30 | 59.00 |
| C1601-084 | | US 160 SECTION3 PRIORITY CULV | 02/16/23 | 1,200.00 | 45.00 | 37.56 | 37.25 |
| C 1601-086 | | MAPLE & CHESTNUT SIGNALS AT I | 02/16/23 | 1,600.00 | 40.00 | 46.00 | 46.00 |
| STM C440-013 | | R3 EAGLE RESIDENCY ADA RAMP I | 02/16/23 | 1,800.00 | 45.00 | 2.00 | 2.00 |
| NHPP0701-256 | | I-70B/31.5 RD MESA COUNTY | 02/16/23 | 200.00 | 45.00 | 36.50 | 41.00 |
| C0881-036 | | R1 CURB RAMPS-SH88B & US285D | 02/16/23 | 3,000.00 | 33.00 | 41.75 | 2.00 |
| SHE067A-044 | | SH 67F M.P. 56.5-57.6 AND SH | 03/02/23 | 1,500.00 | 35.00 | 59.40 | 59.40 |
| STRR300-265 | | MOUNTAIN RE FY23 CRACK SEALS | 03/02/23 | 2,800.00 | 45.00 | 45.00 | 45.00 |
| STR194A-002 | | SH194A SUR. TREAT. & DRAI IMP | 03/09/23 | 3,000.00 | 30.00 | 38.50 | 41.00 |
| FBR 0703-520 | | EISENHOWER-JOHNSON MEMORIAL T | 03/16/23 | 1,200.00 | 45.00 | 45.25 | 50.00 |
| STA257A-008 | | SH 257 WINDSOR RESURFACING | 03/30/23 | 4,000.00 | 40.00 | 43.75 | 41.00 |
| NHPP R100-376 | | VARIOUS LOCATIONS IN REGION 1 | 03/30/23 | 875.00 | 35.90 | 59.07 | 63.00 |
| | | WEIGHTED AVERAGE FOR THE FIRST QUARTER | | 48,785.00 | 40.67 | 43.30 | 40.26 |
| | | WEIGHTED AVERAGE FOR THE YEAR | | 48,785.00 | 40.67 | 43.30 | 40.26 |
| ===== | 630-00001 | Pilot Car Operation | | Hour | ===== | ===== | ===== |
| STA1381-011 | | SH 138 STERLING NORTH PART 2 | 02/16/23 | 1,500.00 | 110.00 | 135.00 | 135.00 |
| | | WEIGHTED AVERAGE FOR THE FIRST QUARTER | | 1,500.00 | 110.00 | 135.00 | 135.00 |
| | | WEIGHTED AVERAGE FOR THE YEAR | | 1,500.00 | 110.00 | 135.00 | 135.00 |
| ===== | 630-00003 | Uniformed Traf Ctrl | | Hour | ===== | ===== | ===== |
| NHPPR100-383 | | I70 OVER WASHINGTON ST | 01/26/23 | 580.00 | 130.00 | 190.67 | 150.00 |
| SHE067A-044 | | SH 67F M.P. 56.5-57.6 AND SH | 03/02/23 | 100.00 | 100.00 | 237.60 | 237.60 |
| STA257A-008 | | SH 257 WINDSOR RESURFACING | 03/30/23 | 16.00 | 150.00 | 162.50 | 155.00 |
| NHPP R100-376 | | VARIOUS LOCATIONS IN REGION 1 | 03/30/23 | 100.00 | 138.00 | 195.71 | 215.00 |
| | | WEIGHTED AVERAGE FOR THE FIRST QUARTER | | 796.00 | 127.64 | 192.98 | 169.27 |
| | | WEIGHTED AVERAGE FOR THE YEAR | | 796.00 | 127.64 | 192.98 | 169.27 |
| ===== | 630-00006 | Uniformed Traf Ctrl (Vehicle) | | Hour | ===== | ===== | ===== |
| NHPPR100-383 | | I70 OVER WASHINGTON ST | 01/26/23 | 580.00 | 160.00 | 129.00 | 75.00 |

| PROJECT NUMBER | ITEM NUMBER/ PROJECT LOCATION | ITEM DESCRIPTION/ PROJECT LOCATION | DATE LET | UNIT/ QUANTITY | ENGR. EST. | AVERAGE BID | AWARDED BID |
|-----------------|--|---------------------------------------|----------|-------------------|------------|-------------|-------------|
| ===== 630-00006 | | Uniformed Traf Ctrl (Vehicle) | | Hour ===== | | | |
| SHE067A-044 | | SH 67F M.P. 56.5-57.6 AND SH | 03/02/23 | 100.00 | 100.00 | 237.60 | 237.60 |
| | WEIGHTED AVERAGE FOR THE FIRST QUARTER | | | 680.00 | 151.18 | 134.90 | 98.91 |
| | WEIGHTED AVERAGE FOR THE YEAR | | | 680.00 | 151.18 | 134.90 | 98.91 |
| ===== 630-00007 | | Traf Ctrl Inspection | | Day ===== | | | |
| STA172A-022 | | SH 172 IGNACIO TO ELMORE'S CO | 01/12/23 | 90.00 | 130.00 | 261.42 | 265.84 |
| NHPP0701-250 | | I-70B: DDI TO 24 RD, MAIN ST | 01/12/23 | 22.00 | 500.00 | 607.00 | 414.00 |
| STR2871-040 | | US 287 MP 0.0 TO MP 122 VARIO | 01/12/23 | 32.00 | 250.00 | 710.40 | 580.00 |
| SFTYR200-277 | | REGION 2 WIDE, VARIOUS HWY & | 01/19/23 | 44.00 | 450.00 | 325.00 | 200.00 |
| FSA0853-123 | | US 85 AND WCR 66 LEFT TURN AC | 01/26/23 | 26.00 | 250.00 | 174.33 | 153.00 |
| NHPPR100-383 | | I70 OVER WASHINGTON ST | 01/26/23 | 50.00 | 250.00 | 685.20 | 438.00 |
| STA066A-008 | | SH 66 @ WCR 7 | 01/26/23 | 42.00 | 350.00 | 226.00 | 200.00 |
| C0342-066 | | US 034A (MP 113-150) | 02/02/23 | 12.00 | 350.00 | 349.67 | 452.00 |
| NHPP0253-296 | | I-25 @ LCR 16 (MP 253.8-254.5 | 02/07/23 | 90.00 | 100.56 | 107.60 | 107.60 |
| C0703-498 | | EISENHOWER JOHNSON MEMORIAL T | 02/16/23 | 30.00 | 400.00 | 537.22 | 560.00 |
| STA1381-011 | | SH 138 STERLING NORTH PART 2 | 02/16/23 | 60.00 | 400.00 | 775.00 | 775.00 |
| C133A-052 | | SH 133 ROCKFALL N OF MCCLURE | 02/16/23 | 70.00 | 400.00 | 541.88 | 650.00 |
| C1601-084 | | US 160 SECTION3 PRIORITY CULV | 02/16/23 | 78.00 | 400.00 | 408.41 | 410.00 |
| C 1601-086 | | MAPLE & CHESTNUT SIGNALS AT I | 02/16/23 | 12.00 | 500.00 | 496.00 | 496.00 |
| STM C440-013 | | R3 EAGLE RESIDENCY ADA RAMP I | 02/16/23 | 13.00 | 400.00 | 800.00 | 800.00 |
| NHPP0701-256 | | I-70B/31.5 RD MESA COUNTY | 02/16/23 | 15.00 | 400.00 | 400.00 | 300.00 |
| C0881-036 | | R1 CURB RAMPS-SH88B & US285D | 02/16/23 | 56.00 | 300.00 | 667.50 | 750.00 |
| NHPP0253-290 | | I25 @ 58TH AND 62ND | 03/02/23 | 28.00 | 250.00 | 357.10 | 470.00 |
| SHE067A-044 | | SH 67F M.P. 56.5-57.6 AND SH | 03/02/23 | 50.00 | 500.00 | 950.40 | 950.40 |
| STRR300-265 | | MOUNTAIN RE FY23 CRACK SEALS | 03/02/23 | 38.00 | 400.00 | 400.00 | 400.00 |
| STR194A-002 | | SH194A SUR. TREAT.& DRAI IMP | 03/09/23 | 34.00 | 250.00 | 570.00 | 550.00 |
| FBR 0703-520 | | EISENHOWER-JOHNSON MEMORIAL T | 03/16/23 | 5.00 | 600.00 | 731.00 | 900.00 |
| STA257A-008 | | SH 257 WINDSOR RESURFACING | 03/30/23 | 40.00 | 300.00 | 167.50 | 160.00 |
| NHPP R100-376 | | VARIOUS LOCATIONS IN REGION 1 | 03/30/23 | 60.00 | 88.00 | 448.09 | 400.00 |
| ER0703-524 | | STRUCTURE F-13-P, EB I-70 EXI | 03/31/23 | 8.00 | 592.00 | 706.60 | 592.00 |
| | WEIGHTED AVERAGE FOR THE FIRST QUARTER | | | 1,005.00 | 305.84 | 459.36 | 445.40 |
| | WEIGHTED AVERAGE FOR THE YEAR | | | 1,005.00 | 305.84 | 459.36 | 445.40 |
| ===== 630-00012 | | Traf Ctrl Mgmt | | Day ===== | | | |
| STA172A-022 | | SH 172 IGNACIO TO ELMORE'S CO | 01/12/23 | 185.00 | 1000.00 | 1974.21 | 2658.42 |
| NHPP0701-250 | | I-70B: DDI TO 24 RD, MAIN ST | 01/12/23 | 72.00 | 1500.00 | 1967.50 | 1500.00 |
| STR2871-040 | | US 287 MP 0.0 TO MP 122 VARIO | 01/12/23 | 80.00 | 1500.00 | 1545.80 | 1392.00 |
| SFTYR200-277 | | REGION 2 WIDE, VARIOUS HWY & | 01/19/23 | 105.00 | 2000.00 | 2025.00 | 1550.00 |

| PROJECT NUMBER | ITEM NUMBER/ PROJECT LOCATION | ITEM DESCRIPTION/ PROJECT LOCATION | DATE LET | UNIT/ QUANTITY | ENGR. EST. | AVERAGE BID | AWARDED BID |
|----------------|----------------------------------|--|----------|-------------------|------------|-------------|-------------|
| ===== | 630-00012 | Traf Ctrl Mgmt | | Day | ===== | ===== | ===== |
| FSA0853-123 | | US 85 AND WCR 66 LEFT TURN AC | 01/26/23 | 53.00 | 1300.00 | 1002.57 | 1220.00 |
| NHPPR100-383 | | I70 OVER WASHINGTON ST | 01/26/23 | 120.00 | 1300.00 | 2060.36 | 1625.00 |
| STA066A-008 | | SH 66 @ WCR 7 | 01/26/23 | 97.00 | 1300.00 | 1345.95 | 1260.00 |
| C0342-066 | | US 034A (MP 113-150) | 02/02/23 | 30.00 | 1300.00 | 1671.33 | 1959.00 |
| C0703-498 | | EISENHOWER JOHNSON MEMORIAL T | 02/16/23 | 70.00 | 1500.00 | 1657.16 | 1700.00 |
| STA1381-011 | | SH 138 STERLING NORTH PART 2 | 02/16/23 | 130.00 | 1500.00 | 1930.00 | 1930.00 |
| C133A-052 | | SH 133 ROCKFALL N OF MCCLURE | 02/16/23 | 136.00 | 1200.00 | 2002.50 | 1950.00 |
| C1601-084 | | US 160 SECTION3 PRIORITY CULV | 02/16/23 | 155.00 | 1600.00 | 1311.50 | 1300.00 |
| C 1601-086 | | MAPLE & CHESTNUT SIGNALS AT I | 02/16/23 | 50.00 | 1200.00 | 1770.00 | 1770.00 |
| STM C440-013 | | R3 EAGLE RESIDENCY ADA RAMP I | 02/16/23 | 27.00 | 1800.00 | 2000.00 | 2000.00 |
| NHPP0701-256 | | I-70B/31.5 RD MESA COUNTY | 02/16/23 | 38.00 | 1200.00 | 1300.00 | 1100.00 |
| C0881-036 | | R1 CURB RAMPS-SH88B & US285D | 02/16/23 | 140.00 | 1400.00 | 1550.00 | 3000.00 |
| NHPP0253-290 | | I25 @ 58TH AND 62ND | 03/02/23 | 98.00 | 750.00 | 1704.11 | 1600.00 |
| STRR300-265 | | MOUNTAIN RE FY23 CRACK SEALS | 03/02/23 | 76.00 | 1200.00 | 1400.00 | 1400.00 |
| STR194A-002 | | SH194A SUR. TREAT.& DRAI IMP | 03/09/23 | 85.00 | 990.00 | 1400.00 | 1300.00 |
| FBR 0703-520 | | EISENHOWER-JOHNSON MEMORIAL T | 03/16/23 | 10.00 | 2500.00 | 1215.00 | 800.00 |
| STA257A-008 | | SH 257 WINDSOR RESURFACING | 03/30/23 | 98.00 | 1600.00 | 1612.50 | 1525.00 |
| | | WEIGHTED AVERAGE FOR THE FIRST QUARTER | | 1,855.00 | 1350.43 | 1649.00 | 1771.76 |
| | | WEIGHTED AVERAGE FOR THE YEAR | | 1,855.00 | 1350.43 | 1649.00 | 1771.76 |
| ===== | 630-00015 | Uniformed Traf Ctrl Coordination | | Hour | ===== | ===== | ===== |
| NHPPR100-383 | | I70 OVER WASHINGTON ST | 01/26/23 | 10.00 | 25.00 | 55.81 | 38.00 |
| C0703-498 | | EISENHOWER JOHNSON MEMORIAL T | 02/16/23 | 520.00 | 30.00 | 47.87 | 50.00 |
| NHPP0253-290 | | I25 @ 58TH AND 62ND | 03/02/23 | 100.00 | 70.00 | 65.83 | 43.00 |
| STA257A-008 | | SH 257 WINDSOR RESURFACING | 03/30/23 | 8.00 | 100.00 | 35.75 | 21.50 |
| | | WEIGHTED AVERAGE FOR THE FIRST QUARTER | | 638.00 | 37.07 | 50.72 | 48.36 |
| | | WEIGHTED AVERAGE FOR THE YEAR | | 638.00 | 37.07 | 50.72 | 48.36 |
| ===== | 630-00017 | Traffic Control Management (Special) | | Day | ===== | ===== | ===== |
| NHPP0253-296 | | I-25 @ LCR 16 (MP 253.8-254.5 | 02/07/23 | 30.00 | 402.25 | 430.41 | 430.41 |
| SHE067A-044 | | SH 67F M.P. 56.5-57.6 AND SH | 03/02/23 | 110.00 | 1300.00 | 1057.32 | 1057.32 |
| NHPP R100-376 | | VARIOUS LOCATIONS IN REGION 1 | 03/30/23 | 150.00 | 1161.00 | 2493.02 | 2450.00 |
| ER0703-524 | | STRUCTURE F-13-P, EB I-70 EXI | 03/31/23 | 30.00 | 7427.00 | 6250.93 | 7427.00 |
| | | WEIGHTED AVERAGE FOR THE FIRST QUARTER | | 320.00 | 1725.09 | 2716.43 | 2248.52 |
| | | WEIGHTED AVERAGE FOR THE YEAR | | 320.00 | 1725.09 | 2716.43 | 2248.52 |
| ===== | 630-80001 | Flash Beacon (Port) | | Each | ===== | ===== | ===== |
| NHPPR100-383 | | I70 OVER WASHINGTON ST | 01/26/23 | 14.00 | 1200.00 | 1468.01 | 1825.00 |

COLORADO DEPARTMENT OF TRANSPORTATION
ITEM UNIT COSTS BY PROJECTS -- 2023 COST DATA

12:26 Wednesday, May 17, 2023 117

| PROJECT NUMBER | ITEM NUMBER/ PROJECT LOCATION | ITEM DESCRIPTION/ PROJECT LOCATION | DATE LET | UNIT/ QUANTITY | ENGR. EST. | AVERAGE BID | AWARDED BID |
|---|--|---------------------------------------|----------|-------------------|------------|-------------|-------------|
| ===== 630-80001 Flash Beacon (Port) Each ===== | | | | | | | |
| C0703-498 | | EISENHOWER JOHNSON MEMORIAL T | 02/16/23 | 20.00 | 1000.00 | 1729.89 | 1800.00 |
| NHPP0253-290 | | I25 @ 58TH AND 62ND | 03/02/23 | 20.00 | 900.00 | 1351.33 | 2200.00 |
| SHE067A-044 | | SH 67F M.P. 56.5-57.6 AND SH | 03/02/23 | 8.00 | 1000.00 | 53.46 | 53.46 |
| FBR 0703-520 | | EISENHOWER-JOHNSON MEMORIAL T | 03/16/23 | 4.00 | 1500.00 | 630.00 | 10.00 |
| | WEIGHTED AVERAGE FOR THE FIRST QUARTER | | | 66.00 | 1042.42 | 1415.72 | 1606.33 |
| | WEIGHTED AVERAGE FOR THE YEAR | | | 66.00 | 1042.42 | 1415.72 | 1606.33 |
| ===== 630-80002 Flash Beacon (Solar) Each ===== | | | | | | | |
| FSA0853-123 | | US 85 AND WCR 66 LEFT TURN AC | 01/26/23 | 4.00 | 900.00 | 741.67 | 1550.00 |
| STA1381-011 | | SH 138 STERLING NORTH PART 2 | 02/16/23 | 2.00 | 1800.00 | 1625.00 | 1625.00 |
| STR194A-002 | | SH194A SUR. TREAT.& DRAI IMP | 03/09/23 | 3.00 | 900.00 | 1500.00 | 1000.00 |
| NHPP R100-376 | | VARIOUS LOCATIONS IN REGION 1 | 03/30/23 | 2.00 | 1025.83 | 1805.13 | 3500.00 |
| | WEIGHTED AVERAGE FOR THE FIRST QUARTER | | | 11.00 | 1086.51 | 1035.29 | 1768.18 |
| | WEIGHTED AVERAGE FOR THE YEAR | | | 11.00 | 1086.51 | 1035.29 | 1768.18 |
| ===== 630-80335 Barricade (3 M-A) (Temp) Each ===== | | | | | | | |
| FSA0853-123 | | US 85 AND WCR 66 LEFT TURN AC | 01/26/23 | 8.00 | 160.00 | 108.00 | 210.00 |
| NHPPR100-383 | | I70 OVER WASHINGTON ST | 01/26/23 | 3.00 | 400.00 | 384.13 | 378.00 |
| STM C440-013 | | R3 EAGLE RESIDENCY ADA RAMP I | 02/16/23 | 8.00 | 200.00 | 5.00 | 5.00 |
| C0881-036 | | R1 CURB RAMPS-SH88B & US285D | 02/16/23 | 8.00 | 225.00 | 215.00 | 10.00 |
| NHPP0253-290 | | I25 @ 58TH AND 62ND | 03/02/23 | 13.00 | 200.00 | 222.00 | 460.00 |
| STR194A-002 | | SH194A SUR. TREAT.& DRAI IMP | 03/09/23 | 4.00 | 160.00 | 475.00 | 450.00 |
| FBR 0703-520 | | EISENHOWER-JOHNSON MEMORIAL T | 03/16/23 | 3.00 | 400.00 | 30.00 | 10.00 |
| STA257A-008 | | SH 257 WINDSOR RESURFACING | 03/30/23 | 8.00 | 200.00 | 140.00 | 135.00 |
| NHPP R100-376 | | VARIOUS LOCATIONS IN REGION 1 | 03/30/23 | 4.00 | 104.00 | 377.83 | 480.00 |
| | WEIGHTED AVERAGE FOR THE FIRST QUARTER | | | 59.00 | 209.08 | 192.31 | 232.95 |
| | WEIGHTED AVERAGE FOR THE YEAR | | | 59.00 | 209.08 | 192.31 | 232.95 |
| ===== 630-80336 Barricade (3 M-B) (Temp) Each ===== | | | | | | | |
| STR2871-040 | | US 287 MP 0.0 TO MP 122 VARIO | 01/12/23 | 4.00 | 400.00 | 397.13 | 598.56 |
| NHPP0701-256 | | I-70B/31.5 RD MESA COUNTY | 02/16/23 | 2.00 | 600.00 | 185.00 | 350.00 |
| SHE067A-044 | | SH 67F M.P. 56.5-57.6 AND SH | 03/02/23 | 2.00 | 500.00 | 59.40 | 59.40 |
| | WEIGHTED AVERAGE FOR THE FIRST QUARTER | | | 8.00 | 475.00 | 338.52 | 401.63 |
| | WEIGHTED AVERAGE FOR THE YEAR | | | 8.00 | 475.00 | 338.52 | 401.63 |

| PROJECT NUMBER | ITEM NUMBER/ PROJECT LOCATION | ITEM DESCRIPTION/ PROJECT LOCATION | DATE LET | UNIT/ QUANTITY | ENGR. EST. | AVERAGE BID | AWARDED BID |
|-----------------|--|---------------------------------------|----------|-------------------|------------|-------------|-------------|
| ===== 630-80337 | | Barricade (3 M-C) (Temp) | | Each ===== | | | |
| C0703-498 | | EISENHOWER JOHNSON MEMORIAL T | 02/16/23 | 3.00 | 500.00 | 537.72 | 540.00 |
| | WEIGHTED AVERAGE FOR THE FIRST QUARTER | | | 3.00 | 500.00 | 537.72 | 540.00 |
| | WEIGHTED AVERAGE FOR THE YEAR | | | 3.00 | 500.00 | 537.72 | 540.00 |
| ===== 630-80340 | | Pedestrian Barricade (ADA) | | Lin Foot ===== | | | |
| STA172A-022 | | SH 172 IGNACIO TO ELMORE'S CO | 01/12/23 | 250.00 | 150.00 | 10.47 | 10.63 |
| C 1601-086 | | MAPLE & CHESTNUT SIGNALS AT I | 02/16/23 | 200.00 | 40.00 | 63.00 | 63.00 |
| STM C440-013 | | R3 EAGLE RESIDENCY ADA RAMP I | 02/16/23 | 600.00 | 40.00 | 60.00 | 60.00 |
| C0881-036 | | R1 CURB RAMPS-SH88B & US285D | 02/16/23 | 600.00 | 37.00 | 50.00 | 70.00 |
| STA257A-008 | | SH 257 WINDSOR RESURFACING | 03/30/23 | 12.00 | 50.00 | 73.50 | 70.00 |
| | WEIGHTED AVERAGE FOR THE FIRST QUARTER | | | 1,662.00 | 55.54 | 47.15 | 56.62 |
| | WEIGHTED AVERAGE FOR THE YEAR | | | 1,662.00 | 55.54 | 47.15 | 56.62 |
| ===== 630-80341 | | Const Traf Sign (A) | | Each ===== | | | |
| STA172A-022 | | SH 172 IGNACIO TO ELMORE'S CO | 01/12/23 | 22.00 | 40.00 | 33.47 | 34.03 |
| NHPP0701-250 | | I-70B: DDI TO 24 RD, MAIN ST | 01/12/23 | 57.00 | 80.00 | 91.45 | 87.90 |
| STR2871-040 | | US 287 MP 0.0 TO MP 122 VARIO | 01/12/23 | 20.00 | 60.00 | 90.98 | 62.55 |
| SFTYR200-277 | | REGION 2 WIDE, VARIOUS HWY & | 01/19/23 | 23.00 | 60.00 | 110.00 | 70.00 |
| FSA0853-123 | | US 85 AND WCR 66 LEFT TURN AC | 01/26/23 | 38.00 | 55.00 | 105.83 | 102.00 |
| NHPPR100-383 | | I70 OVER WASHINGTON ST | 01/26/23 | 38.00 | 75.00 | 112.47 | 102.00 |
| STA066A-008 | | SH 66 @ WCR 7 | 01/26/23 | 4.00 | 80.00 | 162.29 | 193.38 |
| C0342-066 | | US 034A (MP 113-150) | 02/02/23 | 10.00 | 70.00 | 54.33 | 75.00 |
| C0703-498 | | EISENHOWER JOHNSON MEMORIAL T | 02/16/23 | 18.00 | 70.00 | 97.99 | 100.00 |
| STA1381-011 | | SH 138 STERLING NORTH PART 2 | 02/16/23 | 32.00 | 120.00 | 76.00 | 76.00 |
| C133A-052 | | SH 133 ROCKFALL N OF MCCLURE | 02/16/23 | 32.00 | 50.00 | 81.21 | 120.00 |
| C1601-084 | | US 160 SECTION3 PRIORITY CULV | 02/16/23 | 36.00 | 80.00 | 45.42 | 45.50 |
| C 1601-086 | | MAPLE & CHESTNUT SIGNALS AT I | 02/16/23 | 102.00 | 15.00 | 38.00 | 38.00 |
| STM C440-013 | | R3 EAGLE RESIDENCY ADA RAMP I | 02/16/23 | 84.00 | 60.00 | 5.00 | 5.00 |
| NHPP0701-256 | | I-70B/31.5 RD MESA COUNTY | 02/16/23 | 22.00 | 75.00 | 30.00 | 40.00 |
| C0881-036 | | R1 CURB RAMPS-SH88B & US285D | 02/16/23 | 98.00 | 75.00 | 45.00 | 2.00 |
| NHPP0253-290 | | I25 @ 58TH AND 62ND | 03/02/23 | 48.00 | 75.00 | 105.33 | 110.00 |
| SHE067A-044 | | SH 67F M.P. 56.5-57.6 AND SH | 03/02/23 | 2.00 | 60.00 | 44.55 | 44.55 |
| STRR300-265 | | MOUNTAIN RE FY23 CRACK SEALS | 03/02/23 | 112.00 | 80.00 | 90.00 | 90.00 |
| STR194A-002 | | SH194A SUR. TREAT.& DRAI IMP | 03/09/23 | 24.00 | 54.00 | 56.50 | 56.00 |
| FBR 0703-520 | | EISENHOWER-JOHNSON MEMORIAL T | 03/16/23 | 6.00 | 100.00 | 27.50 | 10.00 |
| STA257A-008 | | SH 257 WINDSOR RESURFACING | 03/30/23 | 151.00 | 60.00 | 56.00 | 53.00 |

| PROJECT NUMBER | ITEM NUMBER/ PROJECT LOCATION | ITEM DESCRIPTION/ PROJECT LOCATION | DATE LET | UNIT/ QUANTITY | ENGR. EST. | AVERAGE BID | AWARDED BID |
|-----------------|--|---------------------------------------|----------|-------------------|------------|-------------|-------------|
| ===== 630-80341 | | Const Traf Sign (A) | | Each ===== | | | |
| NHPP R100-376 | | VARIOUS LOCATIONS IN REGION 1 | 03/30/23 | 48.00 | 60.00 | 216.46 | 120.00 |
| | WEIGHTED AVERAGE FOR THE FIRST QUARTER | | | 1,027.00 | 63.92 | 76.98 | 61.92 |
| | WEIGHTED AVERAGE FOR THE YEAR | | | 1,027.00 | 63.92 | 76.98 | 61.92 |
| ===== 630-80342 | | Const Traf Sign (B) | | Each ===== | | | |
| STA172A-022 | | SH 172 IGNACIO TO ELMORE'S CO | 01/12/23 | 80.00 | 42.00 | 36.61 | 37.22 |
| NHPP0701-250 | | I-70B: DDI TO 24 RD, MAIN ST | 01/12/23 | 147.00 | 90.00 | 102.60 | 98.20 |
| STR2871-040 | | US 287 MP 0.0 TO MP 122 VARIO | 01/12/23 | 90.00 | 75.00 | 97.03 | 78.57 |
| SFTYR200-277 | | REGION 2 WIDE, VARIOUS HWY & | 01/19/23 | 39.00 | 70.00 | 122.50 | 80.00 |
| FSA0853-123 | | US 85 AND WCR 66 LEFT TURN AC | 01/26/23 | 44.00 | 80.00 | 237.67 | 155.00 |
| NHPPR100-383 | | I70 OVER WASHINGTON ST | 01/26/23 | 56.00 | 100.00 | 135.73 | 120.00 |
| STA066A-008 | | SH 66 @ WCR 7 | 01/26/23 | 42.00 | 130.00 | 329.12 | 447.27 |
| C0342-066 | | US 034A (MP 113-150) | 02/02/23 | 20.00 | 80.00 | 71.67 | 90.00 |
| C0703-498 | | EISENHOWER JOHNSON MEMORIAL T | 02/16/23 | 49.00 | 130.00 | 114.60 | 120.00 |
| STA1381-011 | | SH 138 STERLING NORTH PART 2 | 02/16/23 | 130.00 | 125.00 | 85.00 | 85.00 |
| C133A-052 | | SH 133 ROCKFALL N OF MCCLURE | 02/16/23 | 96.00 | 60.00 | 90.12 | 140.00 |
| C1601-084 | | US 160 SECTION3 PRIORITY CULV | 02/16/23 | 50.00 | 80.00 | 69.16 | 69.25 |
| C 1601-086 | | MAPLE & CHESTNUT SIGNALS AT I | 02/16/23 | 40.00 | 20.00 | 51.00 | 51.00 |
| STM C440-013 | | R3 EAGLE RESIDENCY ADA RAMP I | 02/16/23 | 24.00 | 70.00 | 5.00 | 5.00 |
| NHPP0701-256 | | I-70B/31.5 RD MESA COUNTY | 02/16/23 | 10.00 | 80.00 | 35.00 | 50.00 |
| C0881-036 | | R1 CURB RAMPS-SH88B & US285D | 02/16/23 | 33.00 | 100.00 | 74.75 | 2.00 |
| NHPP0253-290 | | I25 @ 58TH AND 62ND | 03/02/23 | 75.00 | 100.00 | 113.67 | 135.00 |
| SHE067A-044 | | SH 67F M.P. 56.5-57.6 AND SH | 03/02/23 | 14.00 | 90.00 | 59.40 | 59.40 |
| STRR300-265 | | MOUNTAIN RE FY23 CRACK SEALS | 03/02/23 | 16.00 | 90.00 | 95.00 | 95.00 |
| STR194A-002 | | SH194A SUR. TREAT.& DRAI IMP | 03/09/23 | 36.00 | 78.00 | 77.00 | 75.00 |
| FBR 0703-520 | | EISENHOWER-JOHNSON MEMORIAL T | 03/16/23 | 36.00 | 150.00 | 42.50 | 10.00 |
| STA257A-008 | | SH 257 WINDSOR RESURFACING | 03/30/23 | 6.00 | 75.00 | 56.50 | 54.00 |
| NHPP R100-376 | | VARIOUS LOCATIONS IN REGION 1 | 03/30/23 | 34.00 | 105.83 | 355.14 | 400.00 |
| | WEIGHTED AVERAGE FOR THE FIRST QUARTER | | | 1,167.00 | 88.83 | 124.75 | 109.47 |
| | WEIGHTED AVERAGE FOR THE YEAR | | | 1,167.00 | 88.83 | 124.75 | 109.47 |
| ===== 630-80343 | | Const Traf Sign (C) | | Each ===== | | | |
| STA172A-022 | | SH 172 IGNACIO TO ELMORE'S CO | 01/12/23 | 1.00 | 40.00 | 41.87 | 42.53 |
| SFTYR200-277 | | REGION 2 WIDE, VARIOUS HWY & | 01/19/23 | 8.00 | 80.00 | 132.50 | 90.00 |
| FSA0853-123 | | US 85 AND WCR 66 LEFT TURN AC | 01/26/23 | 8.00 | 110.00 | 241.17 | 155.00 |
| NHPPR100-383 | | I70 OVER WASHINGTON ST | 01/26/23 | 14.00 | 200.00 | 172.27 | 136.00 |
| C0703-498 | | EISENHOWER JOHNSON MEMORIAL T | 02/16/23 | 44.00 | 140.00 | 132.21 | 140.00 |
| NHPP0253-290 | | I25 @ 58TH AND 62ND | 03/02/23 | 16.00 | 200.00 | 117.00 | 145.00 |

COLORADO DEPARTMENT OF TRANSPORTATION
ITEM UNIT COSTS BY PROJECTS -- 2023 COST DATA

12:26 Wednesday, May 17, 2023 120

| PROJECT NUMBER | ITEM NUMBER/ PROJECT LOCATION | ITEM DESCRIPTION/ PROJECT LOCATION | DATE LET | UNIT/ QUANTITY | ENGR. EST. | AVERAGE BID | AWARDED BID |
|----------------|--|---------------------------------------|----------|-------------------|------------|-------------|-------------|
| ===== | 630-80343 | Const Traf Sign (C) | | Each ===== | | | |
| SHE067A-044 | | SH 67F M.P. 56.5-57.6 AND SH | 03/02/23 | 4.00 | 120.00 | 178.20 | 178.20 |
| FBR 0703-520 | | EISENHOWER-JOHNSON MEMORIAL T | 03/16/23 | 15.00 | 200.00 | 62.50 | 35.00 |
| NHPP R100-376 | | VARIOUS LOCATIONS IN REGION 1 | 03/30/23 | 28.00 | 110.62 | 401.91 | 480.00 |
| | WEIGHTED AVERAGE FOR THE FIRST QUARTER | | | 138.00 | 147.08 | 183.01 | 196.12 |
| | WEIGHTED AVERAGE FOR THE YEAR | | | 138.00 | 147.08 | 183.01 | 196.12 |
| ===== | 630-80344 | Const Traf Sign (Spec) | | Sq Foot ===== | | | |
| NHPP0701-250 | | I-70B: DDI TO 24 RD, MAIN ST | 01/12/23 | 48.00 | 25.00 | 38.10 | 36.20 |
| SFTYR200-277 | | REGION 2 WIDE, VARIOUS HWY & | 01/19/23 | 64.00 | 30.00 | 32.50 | 30.00 |
| FSA0853-123 | | US 85 AND WCR 66 LEFT TURN AC | 01/26/23 | 85.00 | 60.00 | 12.71 | 16.25 |
| STRR300-265 | | MOUNTAIN RE FY23 CRACK SEALS | 03/02/23 | 128.00 | 35.00 | 40.00 | 40.00 |
| STR194A-002 | | SH194A SUR. TREAT.& DRAI IMP | 03/09/23 | 64.00 | 26.00 | 57.50 | 60.00 |
| NHPP R100-376 | | VARIOUS LOCATIONS IN REGION 1 | 03/30/23 | 36.00 | 28.16 | 75.13 | 40.00 |
| | WEIGHTED AVERAGE FOR THE FIRST QUARTER | | | 425.00 | 36.18 | 30.31 | 36.33 |
| | WEIGHTED AVERAGE FOR THE YEAR | | | 425.00 | 36.18 | 30.31 | 36.33 |
| ===== | 630-80348 | Const Info Sign | | Each ===== | | | |
| SHE067A-044 | | SH 67F M.P. 56.5-57.6 AND SH | 03/02/23 | 4.00 | 250.00 | 172.26 | 172.26 |
| | WEIGHTED AVERAGE FOR THE FIRST QUARTER | | | 4.00 | 250.00 | 172.26 | 172.26 |
| | WEIGHTED AVERAGE FOR THE YEAR | | | 4.00 | 250.00 | 172.26 | 172.26 |
| ===== | 630-80350 | Vert Panel | | Each ===== | | | |
| STA066A-008 | | SH 66 @ WCR 7 | 01/26/23 | 25.00 | 75.00 | 32.62 | 33.22 |
| STA1381-011 | | SH 138 STERLING NORTH PART 2 | 02/16/23 | 50.00 | 50.00 | 62.00 | 62.00 |
| NHPP0701-256 | | I-70B/31.5 RD MESA COUNTY | 02/16/23 | 40.00 | 25.00 | 40.00 | 20.00 |
| NHPP0253-290 | | I25 @ 58TH AND 62ND | 03/02/23 | 20.00 | 40.00 | 54.67 | 61.00 |
| STRR300-265 | | MOUNTAIN RE FY23 CRACK SEALS | 03/02/23 | 50.00 | 20.00 | 30.00 | 30.00 |
| STA257A-008 | | SH 257 WINDSOR RESURFACING | 03/30/23 | 60.00 | 40.00 | 17.00 | 16.00 |
| | WEIGHTED AVERAGE FOR THE FIRST QUARTER | | | 245.00 | 39.08 | 35.46 | 34.33 |
| | WEIGHTED AVERAGE FOR THE YEAR | | | 245.00 | 39.08 | 35.46 | 34.33 |
| ===== | 630-80355 | Port Mesg Panel | | Each ===== | | | |
| STA172A-022 | | SH 172 IGNACIO TO ELMORE'S CO | 01/12/23 | 5.00 | 3500.00 | 12550.21 | 12760.41 |

| PROJECT NUMBER | ITEM NUMBER/ PROJECT LOCATION | ITEM DESCRIPTION/ PROJECT LOCATION | DATE LET | UNIT/ QUANTITY | ENGR. EST. | AVERAGE BID | AWARDED BID |
|-----------------|--|---------------------------------------|----------|-------------------|------------|-------------|-------------|
| ===== 630-80355 | | Port Mesg Panel | | Each ===== | | | |
| NHPP0701-250 | I-70B: DDI TO 24 RD, MAIN ST | 01/12/23 | 2.00 | 12000.00 | 15040.00 | 10080.00 | |
| STR2871-040 | US 287 MP 0.0 TO MP 122 VARIO | 01/12/23 | 4.00 | 3500.00 | 7443.55 | 6960.00 | |
| FSA0853-123 | US 85 AND WCR 66 LEFT TURN AC | 01/26/23 | 4.00 | 6000.00 | 3648.83 | 4700.00 | |
| NHPPR100-383 | I70 OVER WASHINGTON ST | 01/26/23 | 2.00 | 7500.00 | 14551.67 | 10375.00 | |
| STA066A-008 | SH 66 @ WCR 7 | 01/26/23 | 4.00 | 10000.00 | 7138.76 | 5800.00 | |
| C0703-498 | EISENHOWER JOHNSON MEMORIAL T | 02/16/23 | 2.00 | 10000.00 | 8377.82 | 8700.00 | |
| STA1381-011 | SH 138 STERLING NORTH PART 2 | 02/16/23 | 2.00 | 15000.00 | 11500.00 | 11500.00 | |
| C133A-052 | SH 133 ROCKFALL N OF MCCLURE | 02/16/23 | 2.00 | 10000.00 | 10288.76 | 11000.00 | |
| C1601-084 | US 160 SECTION3 PRIORITY CULV | 02/16/23 | 2.00 | 10000.00 | 8168.14 | 8200.00 | |
| C 1601-086 | MAPLE & CHESTNUT SIGNALS AT I | 02/16/23 | 4.00 | 5000.00 | 4649.00 | 4649.00 | |
| STM C440-013 | R3 EAGLE RESIDENCY ADA RAMP I | 02/16/23 | 3.00 | 8000.00 | 7000.00 | 7000.00 | |
| NHPP0701-256 | I-70B/31.5 RD MESA COUNTY | 02/16/23 | 3.00 | 5000.00 | 6500.00 | 4500.00 | |
| C0881-036 | R1 CURB RAMPS-SH88B & US285D | 02/16/23 | 4.00 | 8000.00 | 11250.00 | 10000.00 | |
| NHPP0253-290 | I25 @ 58TH AND 62ND | 03/02/23 | 5.00 | 3500.00 | 8325.00 | 14675.00 | |
| SHE067A-044 | SH 67F M.P. 56.5-57.6 AND SH | 03/02/23 | 4.00 | 7500.00 | 8910.00 | 8910.00 | |
| STRR300-265 | MOUNTAIN RE FY23 CRACK SEALS | 03/02/23 | 4.00 | 8000.00 | 7500.00 | 7500.00 | |
| STR194A-002 | SH194A SUR. TREAT.& DRAI IMP | 03/09/23 | 4.00 | 6000.00 | 8575.00 | 5150.00 | |
| FBR 0703-520 | EISENHOWER-JOHNSON MEMORIAL T | 03/16/23 | 2.00 | 15000.00 | 1137.50 | 1500.00 | |
| STA257A-008 | SH 257 WINDSOR RESURFACING | 03/30/23 | 8.00 | 6000.00 | 8275.00 | 8000.00 | |
| NHPP R100-376 | VARIOUS LOCATIONS IN REGION 1 | 03/30/23 | 4.00 | 6507.70 | 15263.12 | 19500.00 | |
| | WEIGHTED AVERAGE FOR THE FIRST QUARTER | | 74.00 | 7067.98 | 8422.95 | 8798.15 | |
| | WEIGHTED AVERAGE FOR THE YEAR | | 74.00 | 7067.98 | 8422.95 | 8798.15 | |
| ===== 630-80357 | | Flash Arrow Panel (B Ty) | | Each ===== | | | |
| STA172A-022 | SH 172 IGNACIO TO ELMORE'S CO | 01/12/23 | 4.00 | 1800.00 | 5754.26 | 5848.52 | |
| SFTYR200-277 | REGION 2 WIDE, VARIOUS HWY & | 01/19/23 | 4.00 | 2000.00 | 3500.00 | 2000.00 | |
| C 1601-086 | MAPLE & CHESTNUT SIGNALS AT I | 02/16/23 | 4.00 | 250.00 | 320.00 | 320.00 | |
| STM C440-013 | R3 EAGLE RESIDENCY ADA RAMP I | 02/16/23 | 3.00 | 1300.00 | 200.00 | 200.00 | |
| NHPP0701-256 | I-70B/31.5 RD MESA COUNTY | 02/16/23 | 4.00 | 1500.00 | 325.00 | 400.00 | |
| C0881-036 | R1 CURB RAMPS-SH88B & US285D | 02/16/23 | 6.00 | 1600.00 | 3900.00 | 200.00 | |
| | WEIGHTED AVERAGE FOR THE FIRST QUARTER | | 25.00 | 1428.00 | 3129.35 | 1442.96 | |
| | WEIGHTED AVERAGE FOR THE YEAR | | 25.00 | 1428.00 | 3129.35 | 1442.96 | |
| ===== 630-80358 | | Flash Arrow Panel (C Ty) | | Each ===== | | | |
| NHPP0701-250 | I-70B: DDI TO 24 RD, MAIN ST | 01/12/23 | 1.00 | 5000.00 | 6420.00 | 2840.00 | |
| FSA0853-123 | US 85 AND WCR 66 LEFT TURN AC | 01/26/23 | 4.00 | 1700.00 | 949.00 | 1550.00 | |
| NHPPR100-383 | I70 OVER WASHINGTON ST | 01/26/23 | 3.00 | 2500.00 | 4494.67 | 3280.00 | |
| C0342-066 | US 034A (MP 113-150) | 02/02/23 | 1.00 | 3000.00 | 535.67 | 904.00 | |

| PROJECT NUMBER | ITEM NUMBER/ PROJECT LOCATION | ITEM DESCRIPTION/ PROJECT LOCATION | DATE LET | UNIT/ QUANTITY | ENGR. EST. | AVERAGE BID | AWARDED BID |
|-----------------|--|---------------------------------------|----------|-------------------|------------|-------------|-------------|
| ===== 630-80358 | | | | | | | |
| | | Flash Arrow Panel (C Ty) | | Each | | | |
| C0703-498 | | EISENHOWER JOHNSON MEMORIAL T | 02/16/23 | 3.00 | 3000.00 | 2769.69 | 2900.00 |
| C 1601-086 | | MAPLE & CHESTNUT SIGNALS AT I | 02/16/23 | 4.00 | 250.00 | 320.00 | 320.00 |
| NHPP0253-290 | | I25 @ 58TH AND 62ND | 03/02/23 | 5.00 | 2000.00 | 1808.33 | 3365.00 |
| STR194A-002 | | SH194A SUR. TREAT.& DRAI IMP | 03/09/23 | 2.00 | 1700.00 | 2225.00 | 2350.00 |
| FBR 0703-520 | | EISENHOWER-JOHNSON MEMORIAL T | 03/16/23 | 1.00 | 3500.00 | 350.00 | 450.00 |
| NHPP R100-376 | | VARIOUS LOCATIONS IN REGION 1 | 03/30/23 | 3.00 | 1354.00 | 2702.80 | 3550.00 |
| | WEIGHTED AVERAGE FOR THE FIRST QUARTER | | | 27.00 | 1972.67 | 2010.56 | 2310.70 |
| | WEIGHTED AVERAGE FOR THE YEAR | | | 27.00 | 1972.67 | 2010.56 | 2310.70 |
| ===== 630-80360 | | | | | | | |
| | | Drum Channel Dev | | Each | | | |
| STA172A-022 | | SH 172 IGNACIO TO ELMORE'S CO | 01/12/23 | 200.00 | 30.00 | 33.47 | 34.03 |
| NHPP0701-250 | | I-70B: DDI TO 24 RD, MAIN ST | 01/12/23 | 100.00 | 50.00 | 32.50 | 31.00 |
| STR2871-040 | | US 287 MP 0.0 TO MP 122 VARIO | 01/12/23 | 200.00 | 50.00 | 70.75 | 66.41 |
| SFTYR200-277 | | REGION 2 WIDE, VARIOUS HWY & | 01/19/23 | 100.00 | 40.00 | 55.00 | 20.00 |
| FSA0853-123 | | US 85 AND WCR 66 LEFT TURN AC | 01/26/23 | 200.00 | 36.00 | 21.83 | 26.00 |
| NHPPR100-383 | | I70 OVER WASHINGTON ST | 01/26/23 | 110.00 | 38.00 | 84.20 | 79.00 |
| STA066A-008 | | SH 66 @ WCR 7 | 01/26/23 | 60.00 | 70.00 | 42.86 | 36.78 |
| C0703-498 | | EISENHOWER JOHNSON MEMORIAL T | 02/16/23 | 204.00 | 50.00 | 75.16 | 78.00 |
| STA1381-011 | | SH 138 STERLING NORTH PART 2 | 02/16/23 | 300.00 | 40.00 | 50.00 | 50.00 |
| C133A-052 | | SH 133 ROCKFALL N OF MCCLURE | 02/16/23 | 50.00 | 30.00 | 68.62 | 90.00 |
| C1601-084 | | US 160 SECTION3 PRIORITY CULV | 02/16/23 | 25.00 | 50.00 | 34.26 | 34.00 |
| C 1601-086 | | MAPLE & CHESTNUT SIGNALS AT I | 02/16/23 | 193.00 | 50.00 | 38.00 | 38.00 |
| NHPP0701-256 | | I-70B/31.5 RD MESA COUNTY | 02/16/23 | 40.00 | 50.00 | 40.00 | 20.00 |
| C0881-036 | | R1 CURB RAMPS-SH88B & US285D | 02/16/23 | 200.00 | 45.00 | 38.00 | 20.00 |
| NHPP0253-290 | | I25 @ 58TH AND 62ND | 03/02/23 | 220.00 | 40.00 | 53.23 | 67.00 |
| SHE067A-044 | | SH 67F M.P. 56.5-57.6 AND SH | 03/02/23 | 30.00 | 30.00 | 29.70 | 29.70 |
| STR194A-002 | | SH194A SUR. TREAT.& DRAI IMP | 03/09/23 | 150.00 | 36.00 | 42.00 | 42.00 |
| FBR 0703-520 | | EISENHOWER-JOHNSON MEMORIAL T | 03/16/23 | 100.00 | 50.00 | 15.00 | 5.00 |
| STA257A-008 | | SH 257 WINDSOR RESURFACING | 03/30/23 | 150.00 | 40.00 | 28.13 | 27.00 |
| NHPP R100-376 | | VARIOUS LOCATIONS IN REGION 1 | 03/30/23 | 100.00 | 72.00 | 100.35 | 118.00 |
| | WEIGHTED AVERAGE FOR THE FIRST QUARTER | | | 2,732.00 | 43.73 | 48.44 | 46.84 |
| | WEIGHTED AVERAGE FOR THE YEAR | | | 2,732.00 | 43.73 | 48.44 | 46.84 |
| ===== 630-80363 | | | | | | | |
| | | Drum Channel Dev (Light) (F) | | Each | | | |
| STA172A-022 | | SH 172 IGNACIO TO ELMORE'S CO | 01/12/23 | 40.00 | 50.00 | 43.93 | 44.66 |
| NHPP0701-250 | | I-70B: DDI TO 24 RD, MAIN ST | 01/12/23 | 40.00 | 70.00 | 38.10 | 36.20 |
| SFTYR200-277 | | REGION 2 WIDE, VARIOUS HWY & | 01/19/23 | 20.00 | 45.00 | 72.50 | 25.00 |
| NHPPR100-383 | | I70 OVER WASHINGTON ST | 01/26/23 | 8.00 | 35.00 | 125.49 | 112.00 |

| PROJECT NUMBER | ITEM NUMBER/ PROJECT LOCATION | ITEM DESCRIPTION/ PROJECT LOCATION | DATE LET | UNIT/ QUANTITY | ENGR. EST. | AVERAGE BID | AWARDED BID |
|-----------------|--|---|----------|-------------------|------------|-------------|-------------|
| ===== 630-80363 | | Drum Channel Dev (Light) (F) | | Each ===== | | | |
| C0703-498 | | EISENHOWER JOHNSON MEMORIAL T | 02/16/23 | 4.00 | 55.00 | 106.61 | 110.00 |
| C133A-052 | | SH 133 ROCKFALL N OF MCCLURE | 02/16/23 | 20.00 | 35.00 | 86.04 | 130.00 |
| C1601-084 | | US 160 SECTION3 PRIORITY CULV | 02/16/23 | 25.00 | 60.00 | 62.24 | 62.00 |
| C0881-036 | | R1 CURB RAMPS-SH88B & US285D | 02/16/23 | 40.00 | 38.00 | 61.75 | 5.00 |
| NHPP0253-290 | | I25 @ 58TH AND 62ND | 03/02/23 | 25.00 | 40.00 | 99.93 | 135.00 |
| | WEIGHTED AVERAGE FOR THE FIRST QUARTER | | | 222.00 | 49.19 | 68.43 | 57.64 |
| | WEIGHTED AVERAGE FOR THE YEAR | | | 222.00 | 49.19 | 68.43 | 57.64 |
| ===== 630-80364 | | Drum Channel Dev (Light) (SB) | | Each ===== | | | |
| NHPP0701-250 | | I-70B: DDI TO 24 RD, MAIN ST | 01/12/23 | 25.00 | 70.00 | 38.10 | 36.20 |
| C0703-498 | | EISENHOWER JOHNSON MEMORIAL T | 02/16/23 | 32.00 | 50.00 | 106.94 | 110.00 |
| C133A-052 | | SH 133 ROCKFALL N OF MCCLURE | 02/16/23 | 20.00 | 35.00 | 86.04 | 130.00 |
| C1601-084 | | US 160 SECTION3 PRIORITY CULV | 02/16/23 | 25.00 | 70.00 | 62.24 | 62.00 |
| STR194A-002 | | SH194A SUR. TREAT.& DRAI IMP | 03/09/23 | 150.00 | 40.00 | 60.50 | 59.00 |
| | WEIGHTED AVERAGE FOR THE FIRST QUARTER | | | 252.00 | 46.83 | 69.99 | 69.15 |
| | WEIGHTED AVERAGE FOR THE YEAR | | | 252.00 | 46.83 | 69.99 | 69.15 |
| ===== 630-80370 | | Barrier (Temp) | | Lin Foot ===== | | | |
| STA172A-022 | | SH 172 IGNACIO TO ELMORE'S CO | 01/12/23 | 500.00 | 100.00 | 124.57 | 98.14 |
| FSA0853-123 | | US 85 AND WCR 66 LEFT TURN AC | 01/26/23 | 120.00 | 50.00 | 69.33 | 55.00 |
| C0703-498 | | EISENHOWER JOHNSON MEMORIAL T | 02/16/23 | 220.00 | 40.00 | 109.35 | 150.00 |
| C133A-052 | | SH 133 ROCKFALL N OF MCCLURE | 02/16/23 | 280.00 | 75.00 | 201.50 | 290.00 |
| C1601-084 | | US 160 SECTION3 PRIORITY CULV | 02/16/23 | 100.00 | 150.00 | 391.60 | 370.00 |
| NHPP0701-256 | | I-70B/31.5 RD MESA COUNTY | 02/16/23 | 600.00 | 40.00 | 60.00 | 35.00 |
| NHPP R100-376 | | VARIOUS LOCATIONS IN REGION 1 | 03/30/23 | 350.00 | 47.86 | 48.97 | 16.00 |
| | WEIGHTED AVERAGE FOR THE FIRST QUARTER | | | 2,170.00 | 65.23 | 117.31 | 107.59 |
| | WEIGHTED AVERAGE FOR THE YEAR | | | 2,170.00 | 65.23 | 117.31 | 107.59 |
| ===== 630-80372 | | Conc Barrier (Temp) (Furnish & Install) | | Lin Foot ===== | | | |
| NHPPR100-383 | | I70 OVER WASHINGTON ST | 01/26/23 | 175.00 | 45.00 | 162.40 | 152.00 |
| STA257A-008 | | SH 257 WINDSOR RESURFACING | 03/30/23 | 40.00 | 40.00 | 68.38 | 90.00 |
| | WEIGHTED AVERAGE FOR THE FIRST QUARTER | | | 215.00 | 44.07 | 149.97 | 140.47 |
| | WEIGHTED AVERAGE FOR THE YEAR | | | 215.00 | 44.07 | 149.97 | 140.47 |

| PROJECT NUMBER | ITEM NUMBER/ PROJECT LOCATION | ITEM DESCRIPTION/ PROJECT LOCATION | DATE LET | UNIT/ QUANTITY | ENGR. EST. | AVERAGE BID | AWARDED BID |
|-----------------|--|---------------------------------------|----------|-------------------|------------|-------------|-------------|
| ===== 630-80380 | | Traffic Cone | | Each ===== | | | |
| STA172A-022 | | SH 172 IGNACIO TO ELMORE'S CO | 01/12/23 | 700.00 | 10.00 | 12.53 | 12.76 |
| NHPP0701-250 | | I-70B: DDI TO 24 RD, MAIN ST | 01/12/23 | 610.00 | 10.00 | 15.25 | 15.50 |
| STR2871-040 | | US 287 MP 0.0 TO MP 122 VARIO | 01/12/23 | 100.00 | 15.00 | 5.01 | 1.43 |
| SFTYR200-277 | | REGION 2 WIDE, VARIOUS HWY & | 01/19/23 | 100.00 | 25.00 | 25.00 | 15.00 |
| FSA0853-123 | | US 85 AND WCR 66 LEFT TURN AC | 01/26/23 | 50.00 | 10.00 | 11.08 | 10.50 |
| STA066A-008 | | SH 66 @ WCR 7 | 01/26/23 | 50.00 | 20.00 | 18.34 | 18.98 |
| C0342-066 | | US 034A (MP 113-150) | 02/02/23 | 50.00 | 25.00 | 13.00 | 15.00 |
| C0703-498 | | EISENHOWER JOHNSON MEMORIAL T | 02/16/23 | 200.00 | 12.00 | 28.72 | 30.00 |
| STA1381-011 | | SH 138 STERLING NORTH PART 2 | 02/16/23 | 400.00 | 15.00 | 11.00 | 11.00 |
| C133A-052 | | SH 133 ROCKFALL N OF MCCLURE | 02/16/23 | 150.00 | 10.00 | 29.53 | 35.00 |
| C1601-084 | | US 160 SECTION3 PRIORITY CULV | 02/16/23 | 100.00 | 10.00 | 1.16 | 1.15 |
| C 1601-086 | | MAPLE & CHESTNUT SIGNALS AT I | 02/16/23 | 300.00 | 10.00 | 1.00 | 1.00 |
| STM C440-013 | | R3 EAGLE RESIDENCY ADA RAMP I | 02/16/23 | 150.00 | 10.00 | 2.00 | 2.00 |
| NHPP0701-256 | | I-70B/31.5 RD MESA COUNTY | 02/16/23 | 40.00 | 10.00 | 15.00 | 10.00 |
| C0881-036 | | R1 CURB RAMPS-SH88B & US285D | 02/16/23 | 400.00 | 11.00 | 19.88 | 2.00 |
| NHPP0253-290 | | I25 @ 58TH AND 62ND | 03/02/23 | 50.00 | 20.00 | 12.87 | 18.00 |
| STRR300-265 | | MOUNTAIN RE FY23 CRACK SEALS | 03/02/23 | 400.00 | 10.00 | 12.00 | 12.00 |
| STR194A-002 | | SH194A SUR. TREAT.& DRAI IMP | 03/09/23 | 350.00 | 10.00 | 1.50 | 1.00 |
| FBR 0703-520 | | EISENHOWER-JOHNSON MEMORIAL T | 03/16/23 | 150.00 | 10.00 | 5.50 | 4.00 |
| STA257A-008 | | SH 257 WINDSOR RESURFACING | 03/30/23 | 100.00 | 15.00 | 14.25 | 13.50 |
| NHPP R100-376 | | VARIOUS LOCATIONS IN REGION 1 | 03/30/23 | 200.00 | 20.96 | 28.27 | 40.00 |
| | WEIGHTED AVERAGE FOR THE FIRST QUARTER | | | 4,650.00 | 11.99 | 14.88 | 12.00 |
| | WEIGHTED AVERAGE FOR THE YEAR | | | 4,650.00 | 11.99 | 14.88 | 12.00 |
| ===== 630-80393 | | Stackable Vertical Panels | | Each ===== | | | |
| STA172A-022 | | SH 172 IGNACIO TO ELMORE'S CO | 01/12/23 | 100.00 | 35.00 | 25.11 | 25.52 |
| FSA0853-123 | | US 85 AND WCR 66 LEFT TURN AC | 01/26/23 | 24.00 | 40.00 | 20.00 | 26.00 |
| C0342-066 | | US 034A (MP 113-150) | 02/02/23 | 20.00 | 30.00 | 46.67 | 68.00 |
| STM C440-013 | | R3 EAGLE RESIDENCY ADA RAMP I | 02/16/23 | 120.00 | 30.00 | 20.00 | 20.00 |
| C0881-036 | | R1 CURB RAMPS-SH88B & US285D | 02/16/23 | 40.00 | 27.00 | 85.00 | 60.00 |
| NHPP0253-290 | | I25 @ 58TH AND 62ND | 03/02/23 | 80.00 | 50.00 | 52.67 | 55.00 |
| NHPP R100-376 | | VARIOUS LOCATIONS IN REGION 1 | 03/30/23 | 50.00 | 35.92 | 76.85 | 71.00 |
| | WEIGHTED AVERAGE FOR THE FIRST QUARTER | | | 434.00 | 35.80 | 45.92 | 39.83 |
| | WEIGHTED AVERAGE FOR THE YEAR | | | 434.00 | 35.80 | 45.92 | 39.83 |
| ===== 630-80430 | | Rumble Strip (Port) | | Each ===== | | | |
| SFTYR200-277 | | REGION 2 WIDE, VARIOUS HWY & | 01/19/23 | 12.00 | 500.00 | 1425.00 | 1200.00 |

COLORADO DEPARTMENT OF TRANSPORTATION
 ITEM UNIT COSTS BY PROJECTS -- 2023 COST DATA

12:26 Wednesday, May 17, 2023 125

| PROJECT NUMBER | ITEM NUMBER/ PROJECT LOCATION | ITEM DESCRIPTION/ PROJECT LOCATION | DATE LET | UNIT/ QUANTITY | ENGR. EST. | AVERAGE BID | AWARDED BID |
|----------------|----------------------------------|--|----------|-------------------|------------|-------------|-------------|
| ===== | 630-80430 | Rumble Strip (Port) | | Each ===== | | | |
| C1601-084 | | US 160 SECTION3 PRIORITY CULV | 02/16/23 | 4.00 | 1500.00 | 3198.20 | 3200.00 |
| | | WEIGHTED AVERAGE FOR THE FIRST QUARTER | | 16.00 | 750.00 | 1868.30 | 1700.00 |
| | | WEIGHTED AVERAGE FOR THE YEAR | | 16.00 | 750.00 | 1868.30 | 1700.00 |
| ===== | 630-80440 | Port Rumble Strips (Temp) | | Each ===== | | | |
| NHPP0701-250 | | I-70B: DDI TO 24 RD, MAIN ST | 01/12/23 | 12.00 | 1500.00 | 1425.00 | 1450.00 |
| STR2871-040 | | US 287 MP 0.0 TO MP 122 VARIO | 01/12/23 | 36.00 | 1200.00 | 2316.00 | 3244.72 |
| SHE067A-044 | | SH 67F M.P. 56.5-57.6 AND SH | 03/02/23 | 12.00 | 100.00 | 999.00 | 999.00 |
| | | WEIGHTED AVERAGE FOR THE FIRST QUARTER | | 60.00 | 1040.00 | 2143.84 | 2436.63 |
| | | WEIGHTED AVERAGE FOR THE YEAR | | 60.00 | 1040.00 | 2143.84 | 2436.63 |
| ===== | 630-80511 | Mobile Pvmt Marking Zone | | LUMP SUM ===== | | | |
| MTCER500-221 | | REGION 5 | 01/05/23 | 1.00 | 60000.00 | 112500.00 | 75000.00 |
| NHPP0701-250 | | I-70B: DDI TO 24 RD, MAIN ST | 01/12/23 | 1.00 | 15000.00 | 15170.00 | 10340.00 |
| | | WEIGHTED AVERAGE FOR THE FIRST QUARTER | | 2.00 | 37500.00 | 63835.00 | 42670.00 |
| | | WEIGHTED AVERAGE FOR THE YEAR | | 2.00 | 37500.00 | 63835.00 | 42670.00 |
| ===== | 630-80520 | Mobile Pvmt Mkg Zone | | Day ===== | | | |
| STR2871-040 | | US 287 MP 0.0 TO MP 122 VARIO | 01/12/23 | 4.00 | 3000.00 | 3396.83 | 2900.00 |
| FSA0853-123 | | US 85 AND WCR 66 LEFT TURN AC | 01/26/23 | 4.00 | 1600.00 | 2616.67 | 2000.00 |
| STA1381-011 | | SH 138 STERLING NORTH PART 2 | 02/16/23 | 3.00 | 3000.00 | 4350.00 | 4350.00 |
| SHE067A-044 | | SH 67F M.P. 56.5-57.6 AND SH | 03/02/23 | 2.00 | 1000.00 | 2970.00 | 2970.00 |
| | | WEIGHTED AVERAGE FOR THE FIRST QUARTER | | 13.00 | 2261.54 | 3055.64 | 2968.46 |
| | | WEIGHTED AVERAGE FOR THE YEAR | | 13.00 | 2261.54 | 3055.64 | 2968.46 |
| ===== | 630-85010 | Impact Atten (Temp) | | Each ===== | | | |
| STA172A-022 | | SH 172 IGNACIO TO ELMORE'S CO | 01/12/23 | 2.00 | 8500.00 | 366.09 | 372.18 |
| FSA0853-123 | | US 85 AND WCR 66 LEFT TURN AC | 01/26/23 | 4.00 | 6000.00 | 4128.33 | 4500.00 |

COLORADO DEPARTMENT OF TRANSPORTATION
ITEM UNIT COSTS BY PROJECTS -- 2023 COST DATA

12:26 Wednesday, May 17, 2023 126

| PROJECT NUMBER | ITEM NUMBER/ PROJECT LOCATION | ITEM DESCRIPTION/ PROJECT LOCATION | DATE LET | UNIT/ QUANTITY | ENGR. EST. | AVERAGE BID | AWARDED BID |
|----------------|----------------------------------|--|----------|-------------------|------------|-------------|-------------|
| ===== | 630-85010 | Impact Atten (Temp) | | Each | ===== | ===== | ===== |
| C0703-498 | | EISENHOWER JOHNSON MEMORIAL T | 02/16/23 | 2.00 | 9000.00 | 12070.54 | 14000.00 |
| C133A-052 | | SH 133 ROCKFALL N OF MCCLURE | 02/16/23 | 2.00 | 2500.00 | 7608.41 | 14000.00 |
| C1601-084 | | US 160 SECTION3 PRIORITY CULV | 02/16/23 | 2.00 | 10000.00 | 1406.12 | 1400.00 |
| C 1601-086 | | MAPLE & CHESTNUT SIGNALS AT I | 02/16/23 | 2.00 | 4000.00 | 13200.00 | 13200.00 |
| NHPP0701-256 | | I-70B/31.5 RD MESA COUNTY | 02/16/23 | 1.00 | 10000.00 | 5250.00 | 5500.00 |
| STA257A-008 | | SH 257 WINDSOR RESURFACING | 03/30/23 | 2.00 | 7000.00 | 4925.00 | 4000.00 |
| NHPP R100-376 | | VARIOUS LOCATIONS IN REGION 1 | 03/30/23 | 1.00 | 4258.95 | 12519.68 | 8500.00 |
| | | WEIGHTED AVERAGE FOR THE FIRST QUARTER | | 18.00 | 6681.05 | 5733.91 | 6996.91 |
| | | WEIGHTED AVERAGE FOR THE YEAR | | 18.00 | 6681.05 | 5733.91 | 6996.91 |
| ===== | 630-85011 | Imp Atten (Temp) | | Day | ===== | ===== | ===== |
| SFTYR200-277 | | REGION 2 WIDE, VARIOUS HWY & | 01/19/23 | 140.00 | 300.00 | 125.00 | 50.00 |
| | | WEIGHTED AVERAGE FOR THE FIRST QUARTER | | 140.00 | 300.00 | 125.00 | 50.00 |
| | | WEIGHTED AVERAGE FOR THE YEAR | | 140.00 | 300.00 | 125.00 | 50.00 |
| ===== | 630-85020 | Mobile Attenuator | | Each | ===== | ===== | ===== |
| SFTYR200-277 | | REGION 2 WIDE, VARIOUS HWY & | 01/19/23 | 2.00 | 30000.00 | 45000.00 | 45000.00 |
| FSA0853-123 | | US 85 AND WCR 66 LEFT TURN AC | 01/26/23 | 1.00 | 30000.00 | 47781.67 | 36500.00 |
| NHPPR100-383 | | I70 OVER WASHINGTON ST | 01/26/23 | 1.00 | 25000.00 | 89372.00 | 109000.00 |
| C0342-066 | | US 034A (MP 113-150) | 02/02/23 | 1.00 | 20000.00 | 35252.67 | 36158.00 |
| STR194A-002 | | SH194A SUR. TREAT.& DRAI IMP | 03/09/23 | 2.00 | 25700.00 | 27500.00 | 27000.00 |
| | | WEIGHTED AVERAGE FOR THE FIRST QUARTER | | 7.00 | 26628.57 | 47528.20 | 46522.57 |
| | | WEIGHTED AVERAGE FOR THE YEAR | | 7.00 | 26628.57 | 47528.20 | 46522.57 |
| ===== | 630-85040 | Impact Atten (T-M-A) (Temp) | | Each | ===== | ===== | ===== |
| NHPPR100-383 | | I70 OVER WASHINGTON ST | 01/26/23 | 2.00 | 13000.00 | 44719.59 | 10600.00 |
| | | WEIGHTED AVERAGE FOR THE FIRST QUARTER | | 2.00 | 13000.00 | 44719.59 | 10600.00 |
| | | WEIGHTED AVERAGE FOR THE YEAR | | 2.00 | 13000.00 | 44719.59 | 10600.00 |
| ===== | 630-85041 | Mobile Attenuator | | Day | ===== | ===== | ===== |
| STA066A-008 | | SH 66 @ WCR 7 | 01/26/23 | 15.00 | 600.00 | 1171.19 | 880.00 |

| PROJECT NUMBER | ITEM NUMBER/ PROJECT LOCATION | ITEM DESCRIPTION/ PROJECT LOCATION | DATE LET | UNIT/ QUANTITY | ENGR. EST. | AVERAGE BID | AWARDED BID |
|----------------|----------------------------------|--|----------|-------------------|------------|-------------|-------------|
| ===== | 630-85041 | Mobile Attenuator | | Day | ===== | ===== | ===== |
| C0703-498 | | EISENHOWER JOHNSON MEMORIAL T | 02/16/23 | 65.00 | 900.00 | 1120.59 | 1200.00 |
| NHPP0701-256 | | I-70B/31.5 RD MESA COUNTY | 02/16/23 | 10.00 | 1000.00 | 725.00 | 850.00 |
| C0881-036 | | R1 CURB RAMPS-SH88B & US285D | 02/16/23 | 50.00 | 600.00 | 1337.50 | 800.00 |
| NHPP0253-290 | | I25 @ 58TH AND 62ND | 03/02/23 | 80.00 | 250.00 | 867.33 | 1160.00 |
| SHE067A-044 | | SH 67F M.P. 56.5-57.6 AND SH | 03/02/23 | 40.00 | 1000.00 | 1092.96 | 1092.96 |
| FBR 0703-520 | | EISENHOWER-JOHNSON MEMORIAL T | 03/16/23 | 10.00 | 1500.00 | 1050.00 | 1000.00 |
| NHPP R100-376 | | VARIOUS LOCATIONS IN REGION 1 | 03/30/23 | 150.00 | 598.72 | 825.66 | 1100.00 |
| | | WEIGHTED AVERAGE FOR THE FIRST QUARTER | | 420.00 | 648.35 | 1017.37 | 1074.33 |
| | | WEIGHTED AVERAGE FOR THE YEAR | | 420.00 | 648.35 | 1017.37 | 1074.33 |
| ===== | 630-86810 | Traffic Signal (Temp) | | Each | ===== | ===== | ===== |
| STA172A-022 | | SH 172 IGNACIO TO ELMORE'S CO | 01/12/23 | 2.00 | 10000.00 | 33473.88 | 34027.75 |
| STR2871-040 | | US 287 MP 0.0 TO MP 122 VARIO | 01/12/23 | 2.00 | 25000.00 | 30576.07 | 43500.00 |
| C1601-084 | | US 160 SECTION3 PRIORITY CULV | 02/16/23 | 1.00 | 40000.00 | 19292.99 | 3600.00 |
| | | WEIGHTED AVERAGE FOR THE FIRST QUARTER | | 5.00 | 22000.00 | 29890.14 | 31731.10 |
| | | WEIGHTED AVERAGE FOR THE YEAR | | 5.00 | 22000.00 | 29890.14 | 31731.10 |
| ===== | 630-88001 | Work Zone Intrusion Alarm System | | Day | ===== | ===== | ===== |
| NHPP0701-250 | | I-70B: DDI TO 24 RD, MAIN ST | 01/12/23 | 72.00 | 120.00 | 102.50 | 155.00 |
| | | WEIGHTED AVERAGE FOR THE FIRST QUARTER | | 72.00 | 120.00 | 102.50 | 155.00 |
| | | WEIGHTED AVERAGE FOR THE YEAR | | 72.00 | 120.00 | 102.50 | 155.00 |
| ===== | 632-00000 | Night Work Lighting | | LUMP SUM | ===== | ===== | ===== |
| NHPP0701-250 | | I-70B: DDI TO 24 RD, MAIN ST | 01/12/23 | 1.00 | 100000.00 | 78755.00 | 57510.00 |
| SFTYR200-277 | | REGION 2 WIDE, VARIOUS HWY & | 01/19/23 | 1.00 | 30000.00 | 65000.00 | 10000.00 |
| NHPPR100-383 | | I70 OVER WASHINGTON ST | 01/26/23 | 1.00 | 20000.00 | 150013.58 | 36000.00 |
| C 1601-086 | | MAPLE & CHESTNUT SIGNALS AT I | 02/16/23 | 1.00 | 30000.00 | 3870.00 | 3870.00 |
| NHPP0253-290 | | I25 @ 58TH AND 62ND | 03/02/23 | 1.00 | 20000.00 | 126839.15 | 38000.00 |
| NHPP R100-376 | | VARIOUS LOCATIONS IN REGION 1 | 03/30/23 | 1.00 | 16670.93 | 31565.23 | 30600.00 |
| | | WEIGHTED AVERAGE FOR THE FIRST QUARTER | | 6.00 | 36111.82 | 91159.13 | 29330.00 |
| | | WEIGHTED AVERAGE FOR THE YEAR | | 6.00 | 36111.82 | 91159.13 | 29330.00 |

COLORADO DEPARTMENT OF TRANSPORTATION
ITEM UNIT COSTS BY PROJECTS -- 2023 COST DATA

12:26 Wednesday, May 17, 2023 128

| PROJECT NUMBER | ITEM NUMBER/ PROJECT LOCATION | ITEM DESCRIPTION/ PROJECT LOCATION | DATE LET | UNIT/ QUANTITY | ENGR. EST. | AVERAGE BID | AWARDED BID |
|----------------|--|---------------------------------------|----------|-------------------|------------|-------------|-------------|
| ===== | 641-10010 | Initial Shotcrete Facing | | Sq Foot | ===== | | |
| NHPP R100-376 | | VARIOUS LOCATIONS IN REGION 1 | 03/30/23 | 6,546.00 | 30.00 | 28.96 | 32.00 |
| | WEIGHTED AVERAGE FOR THE FIRST QUARTER | | | 6,546.00 | 30.00 | 28.96 | 32.00 |
| | WEIGHTED AVERAGE FOR THE YEAR | | | 6,546.00 | 30.00 | 28.96 | 32.00 |
| ===== | 641-10070 | Shotcrete Sculpting | | Sq Yard | ===== | | |
| NHPP R100-376 | | VARIOUS LOCATIONS IN REGION 1 | 03/30/23 | 491.00 | 340.12 | 113.10 | 165.00 |
| | WEIGHTED AVERAGE FOR THE FIRST QUARTER | | | 491.00 | 340.12 | 113.10 | 165.00 |
| | WEIGHTED AVERAGE FOR THE YEAR | | | 491.00 | 340.12 | 113.10 | 165.00 |
| ===== | 641-11003 | Shotcrete (CL D) | | Cubic Yard | ===== | | |
| NHPP R100-376 | | VARIOUS LOCATIONS IN REGION 1 | 03/30/23 | 131.00 | 590.08 | 1116.84 | 980.00 |
| | WEIGHTED AVERAGE FOR THE FIRST QUARTER | | | 131.00 | 590.08 | 1116.84 | 980.00 |
| | WEIGHTED AVERAGE FOR THE YEAR | | | 131.00 | 590.08 | 1116.84 | 980.00 |