



**END OF SLAB
RECTANGULAR PANEL OPTION AND
SKEWS LESS THEN 70°**

**CONTINUOUS SLAB
OVER PIER**

**END OF SLAB
SKEWED PANEL OPTION FOR
SKEWS 70° TO 90°**

Rectangular panel option shall be used for skews less than 70°.



NOTES:

Composite total slab designed for HS 25-44 and Alternate Military Loading.

All concrete shall be Class PS with release strength $f_{ci} = 4500$ psi and minimum 28 day strength $f'_c = 6000$ psi. Entrained air is not required for precast panel deck form concrete. The strength shall be at least 5000 psi at time of deck pour.

Use 3/8" low relaxation strands meeting the requirements of ASTM A-416 grade 270. Jacking force per strand (F_j) shall be at least 17.2 kips. Final force per strand (F_r) is estimated to be 14.2 kips.

Installation of U Bar (#3) is mandatory. All four U Bar (#3) loops shall be used simultaneously for lifting the panels. Alternate methods may be used for lifting, provided they are shown on the shop plans and approved by the Engineer.

Care must be taken to ensure the proper cleaning of construction debris and construction of concrete mortar under the edges of the panels. It is also important that adequate space (Δ min. 1" x 2") is provided for the concrete to fill the space under the panel as the slab concrete is placed. Panel lengths and width shall be determined by the Contractor and shown on the shop plans.

The Contractor is responsible for the stability of the panels on the girders. Erected panels shall be uniformly supported along the length of the panel. The Contractor is responsible for meeting the total slab thickness shown on the Superstructure Details.

All planes of reinforcing steel shown in the superstructure details are required for areas not formed with precast panels.

Precast panels and their accessories, including support details, shall be attached to the steel girders or other structural steel elements, or reinforcing steel by welding. No part of the girder, diaphragm, or studs shall be used as ground or field welding.

◆ Required when longitudinal stud spacing is less than 1'-0" and shall be epoxy coated.

Revision Dates (Preliminary Stage Only)			
DATE	BY	REASON	DATE
12/91			10/13
2/93			3/07
3/94			4/02
3/99			11/99

Design		Detail		Quantities	
INITIAL	DATE	INITIAL	DATE	INITIAL	DATE
XXX	MM/YY	XXX	MM/YY	XXX	MM/YY
Checked By					

Print Date: \$DATE\$
File Name: Sheet_B-601-5S.dgn
Horiz. Scale: NTS Vert. Scale: As Noted
Staff Bridge Branch - Unit 022X Unit Leader Initials

Sheet Revisions		
Date:	Comments	Init.

Colorado Department of Transportation
 4201 East Arkansas Avenue
 Room 107
 Denver, CO 80222
 Phone: 303-757-9309 FAX: 303-757-9197

Staff Bridge Branch Initials

As Constructed
No Revisions:
Revised:
Void:

PRECAST PANEL DECK FORM			
Designer:	XXXXXXXX	Structure	X-XX-XX
Detailer:	XXXXXXXX	Numbers	X-XX-XX
Sheet Subset:	BRIDGE	Subset Sheets:	BXX of XXX

Project No./Code
Project Number
Code
Sheet Number

0000