



LEGEND

-  VEHICLE WITH TRUCK-MOUNTED ATTENUATORS (TMA), TWO 360-DEGREE YELLOW FLASHING BEACONS, AND YELLOW FLASHING VEHICLE LIGHTS OR STROBES.
-  ADVANCE WARNING FLASHING OR SEQUENCING ARROW PANEL.
-  VARIABLE MESSAGE SIGN (VMS).
-  WHEN VMS IS USED, THE "SHOULDER CLOSED" SIGN BECOMES OPTIONAL.
-  THE "PICK-UP VEHICLES" OR "WARNING VEHICLE" MAY ENCR OACH INTO THE TRAFFIC LANE WHEN THE SHOULDER IS TOO NARROW TO DRIVE ON.
-  IF TRACKING OF THE WET PAINT IS ANTICIPATED, THE USE OF CONES OR STATIONARY "WET PAINT" SIGNS SHALL BE POSTED.
-  THE VARIABLE SEPARATION DISTANCE BETWEEN THE "CONE PLACEMENT VEHICLE" AND "CONE PICKUP VEHICLE" SHALL BE DETERMINED BY THE TRACK DRYING TIME OF THE PAVEMENT MARKING MATERIAL.

FOLLOWING DISTANCE CHART FOR WARNING AND SIGNING VEHICLES

POSTED WZ SPEED LIMIT (MPH)	FOLLOWING DISTANCE (FEET)
0 - 30	250 - 550
35 - 40	325 - 700
45 - 50	600 - 900
55	750 - 1200
60 - 65	1000 - 1400
70 - 75	1200 - 1600



<p>Computer File Information</p> <p>Creation Date: 06/24/09 Initials: KEN</p> <p>Last Modification Date: 02/24/11 Initials: KEN</p> <p>Full Path: www.dot.state.co.us/DesignSupport/</p> <p>Drawing File Name: Sheet_S-630-1_16of19.dgn</p> <p>CAD Ver.: MicroStation V8 Scale: Not to Scale Units: English</p>	<p>Sheet Revisions</p> <table border="1" style="width: 100%; border-collapse: collapse;"> <tr> <th>Date:</th> <th>Comments</th> </tr> <tr> <td>2/24/11</td> <td>CORRECTING TEXT ERRORS</td> </tr> <tr> <td> </td> <td> </td> </tr> <tr> <td> </td> <td> </td> </tr> </table>	Date:	Comments	2/24/11	CORRECTING TEXT ERRORS					<p>Colorado Department of Transportation</p> <p> 4201 East Arkansas Avenue Denver, Colorado 80222 Phone: (303) 757-9543 Fax: (303) 757-9219</p> <p>Safety & Traffic Engineering Branch KCM/KEN</p>	<p>TRAFFIC CONTROLS FOR HIGHWAY CONSTRUCTION</p> <p>Issued By: Safety & Traffic Engineering Branch July 4, 2006</p>	<p>STANDARD PLAN NO.</p> <p>S-630-1</p> <p>Sheet No. 16 of 19</p>
Date:	Comments											
2/24/11	CORRECTING TEXT ERRORS											