



SECTION VIEW

NOTES:

1. Temporary shoring is required.
2. The Contractor may provide alternate shoring pattern.
3. The Contractor will provide stamped and sealed shop drawing for shoring.
4. Shoring needs to be in place prior to any excavation.
5. Drainage behind shoring shall be designed and provided by the contractor.
6. Pre-drilling may be required for sheet/soldier piles.
7. Shoring, except soil nail as shoring wall shall be removed when backfill reach membrane elevation as approved by the Engineer.
8. Pay limits of Structural Backfill (Class 1) shall be bound by top of DH (design height), Shoring line & face of wall.

Revision Dates		Quantities	
DATE	INITIAL	DATE	INITIAL
09-16			

Print Date: 9/6/2016	0000
File Name: Sheet_B-504-S1.dgn	
Horiz. Scale: 1:4 Vert. Scale: As Noted	
Staff Bridge Branch-Unit OXXX Unit Leader Initials	

Sheet Revisions		
Date:	Comments	Init.

Colorado Department of Transportation
 4201 East Arkansas Avenue
 Room 107
 Denver, CO 80222
 Phone: 303-757-9309 FAX: 303-757-9197

Staff Bridge Branch **Initials**

As Constructed
No Revisions:
Revised:
Void:

MSE/GRS WALL WITH SHORING FOR CONSTRUCTION			
Designer:	XXXXXXX	Structure Numbers	Wall-X-XX-XX
Detailer:	XXXXXXX	Structure Numbers	Wall-X-XX-XX
Sheet Subset:	Wall	Subset Sheets:	WXX of XXX

Project No./Code
Project Number
Code
Sheet Number