


B-504-T1

This sheet must be accompanied by B-504-L1 and D1 B-504-M1 and D2 B-504-N1 and D3 or D4


Revision Dates
09-16 10-24

INITIALS	DESIGN	DATE	DETAIL	DATE	QUANTITY	DATE
By						
Checked By						



SECTION VIEW

Engineer of Record (EOR), This sheet is for staged build MSE/GRS walls or abutment in segments along wall alignment.



WIRE BASKET DETAIL

NOTES:

- Geotextile reinforcement shall be biaxial woven geotextile fabric with minimum average roll value of 4800 Lb/Ft based on ASTM D4595.
- Reinforcement length (RL) is equal to a minimum of 0.7 design height (DH).
- To avoid a weakened plane the 18" minimum lap, where applicable, is for splicing with adjacent reinforcing.
- For the extended use of temporary wall more than 18 months, wire basket may be treated epoxy and faced with a minimum of 3" shotcrete as approved by the engineer.
- Temporary wall may be paid as Item 206 shoring (Lump Sum) for staged build wall or as Alteration of Embankment.
- To avoid roadway pavement tension cracks, the topmost two layers of soil reinforcement shall be extended an additional 0.5DH in length.
- Bearing capacity shall be checked and addressed in the Geotechnical Report.
- The top 18" of existing ground or on-site material shall be compacted to a density of at least 95% of maximum according to AASHTO T-180.
- The Contractor may propose an alternate equivalent basket facing with heavier WWF and 2'-0" maximum height, however the spacing of wrap around geotextile remains 1'-0" (Typ).
- Refer to B-504-L1, M1, N1, and O1, O2, O3 or O4 for bearing capacity versus BP (factored load) requirement.
- The topmost wrap around shall be a full piece of "U" fabric in the main (principal) direction with a minimum of 10'-0" roll width.
- A minimum of 1'-0" overlap (as a non-principal direction splice) is required between fabric rolls.

All seals for this set of drawings are applied to the cover page(s)	Print Date: \$DATE\$	Sheet Revisions		Colorado Department of Transportation			As Constructed	GEOFABRIC WRAP AROUND WIRE BASKET FACING PHASE WALL		Project No./Code						
	File Name: Sheet_B-504-T1.dgn	Date:	Comments:	Init.	2829 West Howard Place, 3rd Floor Denver, CO 80204 Phone: 303-512-4079 FAX: 303-757-9197			No Revisions:	<table border="1" style="width:100%; border-collapse: collapse;"> <tr> <td style="width: 50%;">Designer: XXXXXXXX</td> <td style="width: 50%;">Structure: XXXXXXXXXXXXX</td> </tr> <tr> <td>Detailer: XXXXXXXX</td> <td>Numbers: XXXXXXXXXXXXX</td> </tr> <tr> <td>Sheet Subset: WALL</td> <td>Subset Sheets: WXX of XXX</td> </tr> </table>		Designer: XXXXXXXX	Structure: XXXXXXXXXXXXX	Detailer: XXXXXXXX	Numbers: XXXXXXXXXXXXX	Sheet Subset: WALL	Subset Sheets: WXX of XXX
	Designer: XXXXXXXX	Structure: XXXXXXXXXXXXX														
	Detailer: XXXXXXXX	Numbers: XXXXXXXXXXXXX														
Sheet Subset: WALL	Subset Sheets: WXX of XXX															
Horiz. Scale: Vert. Scale: As Noted				Revised:												
Unit Information Unit Leader Initials				Void:	Staff Bridge Branch		Initials		Sheet Number							