

DESIGN COMPUTATIONS

**PROJECT # BR R600-297
SUBACCOUNT # 16212
STRUCTURE # F-16-XB
MSE PANEL WALLS-F-16-EC, EE AND EF
Volume 1**

Designer: Andy Pott

TABLE OF CONTENTS

DECK DESIGN

P 1-122

Section Properties	P 1-3
Prestress Losses	P 4-11
Strength	P 12-14
Overhang Design	P 15-20
Deck Loads	P 21-35
Strength Checks	P 36-76
Closure Pours	P 77-87
Deck Joints	P 88-93
Post Tensioning Anchors	P 94-103
Deflections	P 104-114
Deck at Northwest Abutment	P 115-122

PRESTRESSED GIRDER DESIGN

P 123-364

Deck Post Tensioning Losses	P 123-136
SAP 2000 Loads	P 137
Strength Calculations	P 138-149
Girder Shear	P 150-165
Inflection Points	P 166-181
Horizontal Shear	P 182-189
Haunch Depth	P 190-193
Deflections, Camber & Stresses	P 194-338
Access Hatch	P 339-351
Temp. Girder Kicker support	P 352-356
Miscellaneous/Trolley Supports	P 357-364

BEARINGS

P 365-416


Pier Bearings	P 365-413
Leveling Pads	P 413-416

COLORADO DEPARTMENT OF TRANSPORTATION
DESIGN COMPUTATIONS (Grid)

DECK DESIGN

By: _____	Date _____	Project no. _____	Project code (SA#): _____
Chk'd: _____	Date _____	Structure no. _____	Sheet _____ of _____

SECTION PROPERTIES



of blockouts = 4
 blockout width = 10"

For No Blockouts (midspan)

$$\bar{y} = 3.95428''$$

$$I_x = 3886.92 \text{ in}^4$$

} from station

$$A = 723.575 \text{ in}^2$$

$$S_{TOP} = \frac{3886.92}{8 - 3.95428} = 960.75 \text{ in}^3$$

$$S_{BOTTOM} = \frac{3886.92}{3.95428} = 982.96 \text{ in}^3$$

With Blockouts

$$\bar{y} = 3.91801''$$

$$I_x = 2179.06''$$

} from station

$$A = 403.375 \text{ in}^2$$

$$S_{TOP} = \frac{2179.06}{8 - 3.91801} = 533.82 \text{ in}^3$$

$$S_{BOTTOM} = \frac{2179.06}{3.91801} = 556.16 \text{ in}^3$$

8' x 8" PANEL

$$\bar{y} = 4''$$

A =


$$I_x = \frac{Bt^3}{12} = \frac{(96)(8)^3}{12} = 4096 \text{ in}^4 \text{ (no blockouts)}$$

$$I_{x \text{ blockouts}} = \frac{Bt^3}{12} - \frac{n \cdot B_{block} t^3}{12} = 4096 - \frac{4(10)8^3}{12} = 2389.33 \text{ in}^4$$

$$S_{TOP} = S_{BOTTOM} = \frac{2389.33}{4} = 597.33 \text{ in}^3 \text{ (w/ blockouts)}$$

$$S_{TOP} = S_{BOTTOM} = \frac{4096}{4} = 1024 \text{ in}^2 \text{ (w/o blockouts)}$$

By: Date	Project no.	Project code (SA#):
Chk'd: Date	Structure no.	Sheet of



No Blockouts

Mass Properties

File Display

Mass Per Area: 1.000000

Perimeter:	200.919	Centroid	X: -2.04545e-009	Center Of Mass	X: -2.04545e-009
Surface Area:	723.375		Y: 3.95428		Y: 3.95428
Mass:	723.375		Z: 0		Z: 0

Coordinate System: Center Of Mass

Moments Of Inertia		Products Of Inertia	
X:	3886.92	XY:	4.66081e-006
Y:	493682	XZ:	0
Z:	497569	YZ:	0

Principal Moments		Principal Directions	
X:	3886.92	1.000000	0.000000
Y:	493682	-0.000000	1.000000
Z:	497569	0.000000	1.000000

Radii Of Gyration

X: 2.31804

Y: 26.1241

Z: 26.2268

NO BLOCKOUTS

with blockouts

Mass Properties [min] [max] [close]

File Display

Mass Per Area: 1.000000

	Centroid	Center Of Mass
Perimeter: 264.919	X: -6.85774e-009	X: -6.85774e-009
Surface Area: 403.375	Y: 3.91801	Y: 3.91801
Mass: 403.375	Z: 0	Z: 0

Coordinate System: Center Of Mass

Moments Of Inertia	Products Of Inertia
X: 2179.06	XY: 3.31267e-006
Y: 279415	XZ: 0
Z: 281594	YZ: 0

Principal Moments	Principal Directions		
X: 2179.06	1.000000	0.000000	0.000000
Y: 279415	-0.000000	1.000000	0.000000
Z: 281594	0.000000	0.000000	1.000000

Radii Of Gyration

X: 2.32423
Y: 26.3191
Z: 26.4215

COLORADO DEPARTMENT OF TRANSPORTATION
DESIGN COMPUTATIONS (Grid)

PRESTRESS LOSSES

$$\Delta f_{PT} = \Delta f_{PEs} + \Delta f_{PLT} \quad (5.9.5.1-1)$$

Time Dependent Losses - Table 5.9.5.3-1

$$A_{vg} = 26 + 4.0 \text{ PPR}$$

PPR - partial prestress ratio

assume PPR = 1.0

$$A_{vg} = 26 + 4(1.0) = 30 \text{ ksi} - 6 \text{ ksi} = 24 \text{ ksi} \quad (5.9.5.3)$$

ELASTIC SHORTENING

(5.9.5.2.3a)

$$\Delta f_{PEs} = \frac{E_p}{E_{ci}} f_{cp} \quad (5.9.5.2.3a-1)$$

or

$$\Delta f_{PEs} = \frac{A_{ps} f_{pbe} (I_g + e_m^2 A_g) - e_m M_g A_g}{A_{ps} (I_g + e_m^2 A_g) + \frac{A_g I_g E_{ci}}{E_p}} \quad (5.9.5.2.3a-1)$$

$$A_g \approx 723.375 \text{ in}^2$$

$$E_p = 28500 \text{ ksi}$$

$$E_{ci} = 1820 \sqrt{f'_{ci}} = 1820 \sqrt{6} = 4458.07 \text{ ksi}$$


$$I_g = 3886.92 \text{ in}^4$$

$$e_m \approx 4" - 3.95428" = .04572"$$

$$M_g \approx \frac{w l^2}{8} = \frac{(5.023 \text{ klf})(15 \text{ klf}) 43^2}{8} \approx 174.16 \text{ ft k} = 2089.9 \text{ in k}$$

$$f_{pbe} \approx .75(270 \text{ ksi}) = 202.5 \text{ ksi} \quad (\text{Table } 5.9.3-1)$$

$$A_{ps} = (4 \text{ strands})(.217) \approx 9.548 \text{ in}^2$$



$$\Delta f_{PEs} = \frac{(9.548)(202.5)(3886.92 + .04572^2(723.375)) - .04572(2089.9)723.375}{9.548(3886.92 + .04572^2(723.375)) + \frac{723.375(3886.92)}{28500} 4458.07}$$

$$\Delta f_{PEs} \approx 15.61 \text{ ksi}$$

477170.9807

By: _____	Date _____	Project no. _____	Project code (SA#): _____
Chk'd: _____	Date _____	Structure no. _____	Sheet 4 of _____

TOTAL LONG TERM LOSSES

STANDARD

$$\Delta f_{PLT} = 10.0 \frac{f_{pi} A_{ps}}{A_g} \gamma_h \gamma_{st} + 12.0 \gamma_h \gamma_{st} + \Delta f_{pr} \quad (5.9.5.3-1)$$

$$\gamma_h = 1.7 - .01H = 1.7 - .01(55) = 1.15$$

$$\gamma_{st} = \frac{5}{1+f_{ci}} = \frac{5}{1+.5} = .833$$

$$f_{pi} = .75(270) = 202.5$$

$$\Delta f_{pr} = 2.4 \text{ ksi}$$

$$\Delta f_{PLT} = \frac{10.0 (202.5) (9.548)}{768} (1.15)(.833) + 12 (1.15)(.833) + 2.4$$

$$\Delta f_{PLT} \approx 24.12 + 11.50 + 2.4 = 38.0 \text{ ksi}$$

APPROXIMATION

Table 5.9.5.3-1

PPR = partial prestress ratio

$$A_{ug} = 26 + 4.0 \text{ PPR}$$

$$\text{Upper Bnd} = 29 + 4.0 \text{ PPR}$$

reduce by 6 ksi for solid slabs

$$\text{PPR} = \frac{A_{ps} f_{py}}{A_{ps} f_{py} + A_s f_y} = 1$$

(5.5.4.2.1-4)

$$\text{Upper Stress} = 29 + 4.0(1) - 6 = 27 \text{ ksi}$$

COLORADO DEPARTMENT OF TRANSPORTATION
DESIGN COMPUTATIONS (Grid)

PRESTRESS LOSSES - REFINED ESTIMATE (5.9.5.4)

(TIME OF TRANSFER TO DECK PLACEMENT)

SHRINKAGE

(5.9.5.4.2a) & (5.4.2.3)

$$\Delta f_{pSR} = \epsilon_{bid} E_p k_{ed} \quad (5.9.5.4.2a-1)$$

$$\epsilon_{bid} = K_s K_{hs} K_f K_{td} \quad 0.48 \times 10^{-3} \quad (5.4.2.3.3-1)$$

$$K_{hs} = 2.00 - 0.014 H \quad (5.4.2.3.3-2)$$

$$K_{hs} = 2.0 - 0.014(55) = \underline{1.23}$$

H = 55% (Fig 5.4.2.3.3-1)

$$K_s = 1.45 - .13(V/S) \geq 1.0 \quad (5.4.2.3.2-2)$$

$$V/S = \frac{723.375 \text{ m}^2}{200.919 \text{ m}} = 3.6$$

$$\frac{723.375 \text{ m}^2}{94 \text{ m}} = 7.7$$

$$K_s = 1.45 - .13(3.6) = \underline{1.0}$$

$$K_f = \frac{5}{1 + f'_{ci}} = \frac{5}{1 + 6} = .714 \quad (5.4.2.3.2-4)$$

$$K_{td} = \frac{t}{61 - 4f'_{ci} + t} \quad (5.4.2.3.2-5)$$

@ 30 days $K_{td} = .45$

@ 3650 days $K_{td} = .99$ (10 years)

@ 50 years $K_{td} = 1.00$ (50 years)

$$\epsilon_{bid} = (1.0)(1.23)(.714)(.45) (0.48 \times 10^{-3})$$

$$\epsilon_{bid} = .000190 \quad @ \text{ 30 days}$$

$$\epsilon_{bid} = .000486 \quad @ \text{ 10 years}$$

$$.000491 \quad @ \text{ 50 years}$$

$$E_p = 28500 \text{ Ksi}$$

By: Date	Project no.	Project code (SA#):
Chk'd: Date	Structure no.	Sheet <u>6</u> of <u> </u>

PRESTRESS LOSSES

SHRINKAGE (Cont.)

$$\psi(t, t_i) = 1.9 K_s K_{hc} K_f K_{td} \epsilon_i^{-.118} \quad (5.4.2.3.2-1)$$

$$K_s = 1.0$$

$$K_{hc} = 1.56 - 0.008 H \quad (5.4.2.3.2-3)$$

$$= 1.56 - 0.008 (35) = 1.12$$

$$K_f = .714 \quad (5.4.2.3.2-4)$$

$$K_{td} = .448 \quad @ 30 \text{ days} \quad (5.4.2.3.2-5)$$

$$\psi(t, 30 \text{ days}) = (1.9)(1.0)(1.12)(.714)(.448) 30^{-.118}$$

$$= .456$$

$$\psi(10 \text{ yrs}) = .572$$

$$\psi(50 \text{ yrs}) = .477$$

$$K_{id} = \frac{1}{1 + \frac{E_p}{E_{ci}} \frac{A_{ps}}{A_g} \left(1 + \frac{A_g e_{pg}^2}{I_g} \right) [1 + .7 \psi(t)]} \quad (5.9.5.4.2a-2)$$

$$K_{id} = \frac{1}{1 + \frac{28500}{4458} \frac{(9.548)}{723.375} \left(1 + \frac{723.375 (.04572)^2}{3886.92} \right) (1 + .7 (.456))}$$

$$K_{id} = .900$$

30 days

PRESTRESS LOSSES

SHRINKAGE (cont.)

$$\begin{aligned} \Delta f_{pSR} &= \epsilon_{bid} E_p k_{id} && (5.9.5.4.2a-1) \\ &= (.000190)(28500)(.900) \\ &= \underline{4.86 \text{ ksi}} @ 30 \text{ days} \end{aligned}$$

CREEP (FROM TIME OF TRANSFER TO DECK PLACEMENT)

$$\Delta f_{PCR} = \frac{E_p}{E_{ci}} f_{cgp} \psi_s(t_d, t_c) k_{id} \quad (5.9.5.4.2b-1)$$

$\psi_s = .502$ (30 days)

$k_{id} = .889$ (30 days)

$$\begin{aligned} f_{cgp} &= \frac{P_e}{A} + \frac{P_e e}{I} \nu + \frac{M_g x}{I} \\ &= \frac{(9.548 \text{ in}^2)(.9(.75)(270))}{723.375} + \frac{(9.548 \text{ in}^2)(.04572)(.04572)}{3886.92} + \frac{(2089.9)(.04572)}{3886.92} \end{aligned}$$

$f_{cgp} \approx 2.41 \text{ ksi} + .00005 + .0246$

$f_{cgp} \approx 2.43 \text{ ksi}$

use $f_{cgp} \approx 2.47 \text{ ksi}$

$\Delta f_{pES} \approx 17.02 \text{ ksi}$ (5.9.5.2.3a-1)

$\frac{17.02}{202.5} \times 100 \approx 8.4\%$

$\approx 10\% \rightarrow \text{okay}$

$f_{cgp} \approx 2.47$ with 8.4%

iteration method

$\rightarrow 8.55\%$ loss

okay

$$\Delta f_{PCR} = \frac{28500}{4458} (2.47) (.456) (.9)$$

$\Delta f_{PCR} \approx \underline{6.48 \text{ ksi}}$ ←

PRESTRESS LOSSES

RELAXATION (TIME OF TRANSFER TO DELTA PLACEMENT) (5.9.5.4.2 c)

$$\Delta f_{PRI} = \frac{f_{PE}}{K_L} \left(\frac{f_{PE}}{F_{PY}} - .55 \right) \quad (5.9.5.4.2c-1)$$

$$\Delta f_{PRI} = \frac{[.75(270) - 16.98]}{30} \left(\frac{.75(270) - 16.98}{9(270)} - .55 \right)$$

$$\Delta f_{PRI} \approx 1.32 \text{ ksi}$$

per 5.9.5.4.2 c

$$\Delta f_{PRI} = 1.2 \text{ ksi for low-relax strand}$$

PRESTRESS LOSSES - (TIME OF DECK PLACEMENT TO FINAL TIME)

SHRINKAGE OF GIRDER

(5.9.5.4.3 a)

$$\Delta F_{psD} = \epsilon_{sh} E_p K_{df} \quad (5.9.5.4.3 a-1)$$

$$K_{df} = \frac{1}{1 + \frac{E_p}{E_{ci}} \frac{A_{ps}}{A_c} \left(1 + \frac{A_c e_{pc}^2}{I_c}\right) (1 + .7 \psi_b (t_f, t_c))} \quad (5.9.5.4.3 a-2)$$

$$K_{df} = \frac{1}{1 + \left(\frac{28500}{4069.64}\right) \left(\frac{9.548}{768}\right) \left(1 + \frac{768 (0)}{4096}\right) (1 + .7 (1.194))}$$

$$K_{df} = .863 \quad (50 \text{ years})$$

$$\begin{aligned} \Delta F_{psD} &= (.00491) (28500) (.863) \\ &= \underline{12.08 \text{ Ksi}} \end{aligned}$$

CREEP

$$\begin{aligned} \Delta F_{pcD} &= \frac{E_p}{E_{ci}} f_{cgp} [\psi(50 \text{ yrs}) - \psi(30 \text{ days})] K_{df} \quad (5.9.5.4.3 b-1) \\ &+ \frac{E_p}{E_c} \Delta f_{cd} \psi(50 \text{ yrs}) K_{df} \end{aligned}$$

Δf_{cd} = stress due to composite loads
 strand group is concentric with panel cross section
 so $\Delta f_{cd} = 0$

$$\Delta f_{pcD} = \frac{28500}{4458} (2.47) (.393 - .456) .863$$

$$\underline{\Delta f_{pcD} = 10.18 \text{ Ksi} \quad \ominus}$$

PRESTRESS LOSSES - (LONG TERM)

RELAXATION

$$\Delta F_{PR2} = \Delta F_{PR1}$$

(5.9.5.4.3c-1)

$$\Delta F_{PR2} = \underline{1.2 \text{ ksi}} \quad \leftarrow$$

SHRINKAGE OF DECK

$$A_d = \emptyset$$

$$\Delta F_{cd} = 0$$

(5.9.5.4.3d-2)

$$\Delta f_{pss} = \emptyset$$

TOTAL LONG TERM LOSSES

$$\begin{aligned} \Delta f_{PLT} &= \Delta f_{pse} + \Delta f_{pce} + \Delta f_{PR1} + \Delta f_{psd} + \Delta f_{pcd} + \Delta f_{PR2} \\ &= 5.27 \text{ ksi} + 7.72 \text{ ksi} + 1.2 \text{ ksi} + 12.08 \text{ ksi} + 10.18 \text{ ksi} + 1.2 \text{ ksi} \\ &= \underline{37.65 \text{ ksi}} \quad \leftarrow \end{aligned}$$

$$\begin{aligned} f_{pe} &= f_{jack} - \Delta f_{pes} - \Delta f_{PLT} \\ &= .75(270) - 16.98 - 37.65 \end{aligned}$$

$$f_{pe} = \underline{147.87 \text{ ksi}} \quad \leftarrow$$

By: _____	Date _____	Project no. _____	Project code (SA#): _____
Chk'd: _____	Date _____	Structure no. _____	Sheet <u>11</u> of _____

STRENGTH

$$C = \frac{A_{ps} f_{pu} + A_s f_s - A'_s f'_s}{.85 f'_c \beta b + K A_{ps} \frac{f_{pu}}{d_p}} \quad (5.7.3.1.1-4)$$

$K = .28$ from table C5.7.3.1.1-1

Concrete strength = 7 ksi

$$\beta = .85 - 3(.05) = .7 \quad (5.7.2.2)$$

$A'_s = \phi$ compression steel
 $A_s = \phi$ mild steel

$$A_{ps} = (22 \text{ strands}) (.217 \text{ in}^2) \approx 4.774 \text{ in}^2 \quad 4.557 \text{ 21 strands}$$

$$f_{pu} = 270 \text{ ksi}$$

$$b = 7'-5" = 89" \text{ no voids} \quad 89" - 4(10") = 49"$$

$$d_p = 8" - 2" \text{ CLR} - .6/2 = 5.7"$$

$$C = \frac{(4.774)(270 \text{ ksi}) + 0 - 0}{.85(7 \text{ ksi})(.7)(89") + .28(4.774) \frac{270}{5.7}}$$

$C \approx 2.97$ inches in positive moment region \Rightarrow no voids

2.78 for .96" wide

2.85 21 strands

$C = 4.82"$ for areas with voids

$$f_{ps} = f_{pu} \left(1 - K \frac{C}{d_p}\right) \quad (5.7.3.1.1-1)$$

$$= 270 \left(1 - .28 \frac{2.97"}{5.7"}\right)$$

$$f_{ps} \approx 230.6 \text{ ksi} \quad 232.2 \text{ ksi} \quad 21 \text{ strands}$$

$f_{ps} = 206.1 \text{ ksi}$ if voids included

COLORADO DEPARTMENT OF TRANSPORTATION
DESIGN COMPUTATIONS (Grid)

(5.7.3.2.2-1)



$$M_n = A_{ps} f_{ps} \left(d_p - \frac{a}{2} \right) + A_s f_s \left(d_s - \frac{a}{2} \right) - A'_s f'_s \left(d'_s - \frac{a}{2} \right) + .85 f'_c (b - b_w) h_f \left(\frac{a}{2} - \frac{h_f}{2} \right)$$

$$M_n = (4.774 \text{ in}^2)(230.6) \left(5.7'' - (2.97'')(0.7) \right) + 0 + 0 + .85(7) (89'' - 89'') h_f \left(\frac{9/2 - h_f}{2} \right)$$

$$M_n = 3986.3 \text{ in kip} = 332.2 \text{ ft kip}$$

326.7 for 21 strands

- $\phi = .75$ for compression controlled sections
- $\phi = .9$ for tension controlled reinforced concrete
- $\phi = 1.0$ for tension controlled prestressed concrete



$$c = 2.97''$$

$$\frac{.003}{c} = \frac{\epsilon_T}{d_t - c}$$

$$\frac{.003}{2.97} = \frac{\epsilon_T}{5.7 - 2.97}$$

$$\epsilon_T \approx .00276$$

section is compression controlled ←

$$\phi = .75 \quad \leftarrow$$

$$M_R = \phi M_n = .75 (332.2) = 249.15 \text{ ft kip}$$

$$M_R = 249.15 \text{ ft kip}$$

245 for 21 strands

By: Date	Project no.	Project code (SA#):
Chk'd: Date	Structure no.	Sheet 13 of

DEVELOPMENT LENGTH & TRANSFER LENGTH

$$l_d \geq K \left(f_{ps} - \frac{2}{3} f_{pe} \right) d_b \quad (5.11.4.2-1)$$

$$d_b = .6''$$

f_{ps} = average stress

f_{pe} = stress after losses

$$K = 1.0$$

$$\text{Transfer length} = 60 d_b = 36'' \quad (5.11.4.1)$$





Fig. C5.11.4.2-1

$$f_{pe} \approx 147.87 \text{ Ksi}$$

$$f_{ps} \approx 230.6 \text{ Ksi}$$

$$l_d \geq 1.0 \left(230.6 - \frac{2}{3} (147.87) \right) .6''$$

$$l_d \geq 79.2'' = 6.6'$$

at the front face of barrier, ($\sim 13''$ from end of precast)


$$F_{px} \approx \frac{f_{pe} l_{px}}{60 d_b} = \frac{(147.87) (13'')}{60 (.6'')} \quad (5.11.4.2-2)$$

$$f_{strand} \approx 53.4 \text{ Ksi}$$

By: Date	Project no.	Project code (SA#):
Chk'd: Date	Structure no.	Sheet 14 of

STRENGTH AT OVERHANG

(FACE OF BARRIER)



$$A_p f_p = .85 f'_c b a$$

$$(4.774)(53.4) = (.85)(7)(96")a$$

$$a \approx .446"$$

$$A_{ps} = 22(.217) = 4.774 \text{ in}^2$$

$$c = a/\beta = \frac{.446}{.7} = .6376"$$

$$\frac{T_1}{d_p - c} = \frac{T_2}{d_p - c}$$

$$\frac{53.4}{5.7 - .6376} = \frac{T_2}{2.3 - .6376}$$

$$T_2 \approx 17.54 \text{ k}_s$$

$$M_n = A_{ps} f_{ps} (d_p - a/2)$$

$$M_n = 4.774 (53.4) \left(5.7 - \frac{.446}{2}\right) + 4.774 (17.54) \left(2.3 - \frac{.446}{2}\right)$$

$$M_n = 1396.26 + 173.92 = 1570.2 \text{ in}_k, = 130.85 \text{ ft}_k$$

assume compression control $\Rightarrow \phi = .75$

$$M_n = .75 (130.85) = 98.1 \text{ ft}_k \quad (\text{FACE OF BARRIER})$$

ADD # 5 @ 8" mild steel = (9.39 ftk) $\phi = 75.1 \text{ ft}_k$

AT TRANSFER LENGTH

$$f_{pe} \approx 147.87 \text{ k}_s$$

$$(4.774)(147.87) = .85 (7) (96) a$$

$$a \approx 1.236"$$

$$\frac{147.87}{5.7 - 1.766} = \frac{T_2}{2.3 - 1.766}$$

$$c \approx \frac{1.236}{.7} = 1.766"$$

$$T_2 \approx 20.07 \text{ k}_s$$

$$M_n = 4.774 (147.87) \left(5.7 - \frac{1.236}{2}\right) + 4.774 (20.07) \left(2.3 - \frac{1.236}{2}\right)$$

$$M_n = 3587.5 + 161.2 = 3748.7 \text{ in}_k = 312.4 \text{ ft}_k$$

$$M_r = (.75)(312.4) \approx 234.3 \text{ ft}_k$$

By: _____	Date: _____	Project no. _____	Project code (SA#): _____
Chk'd: _____	Date: _____	Structure no. _____	Sheet 15 of _____

COLORADO DEPARTMENT OF TRANSPORTATION
DESIGN COMPUTATIONS (Grid)

Assume stress on rebar = stress of prestressing (53.4 ksi)

$$A_{ps} f_{ps} + A_s f_{ps} = .85 f'_c b a$$

$$4.774(53.4) + 2.4(53.4) = .85(7)(96)a$$

$$a = .671''$$

$$c \approx \frac{.671}{.7} = .958''$$

$$\frac{53.4}{5.7 - .958} = \frac{T_2}{2.3 - .958}$$

$$T_2 = 15.11 \text{ ksi}$$

$$M_n = A_{ps} f_{ps} (d_p - a/2)$$

$$M_n = 4.774(53.4) \left(5.7 - \frac{.671}{2} \right) + 4.774(15.11 \text{ ksi}) \left(2.3 - \frac{.671}{2} \right) + 2.4(53.4) \left(5.75 - \frac{.671}{2} \right)$$

$$M_n \approx 1367.58 + 141.71 + 693.92 = 2203.2 \text{ in} \cdot \text{k}$$

$$M_n = 183.6 \text{ ft} \cdot \text{k}$$

$$M_R = \phi M_n = .75(183.6) = 137.7 \text{ ft} \cdot \text{k}$$

$$M_U = 142.52 \text{ ft} \cdot \text{k} - \text{NO GOOD}$$

$$4.774(53.4) + 3.72(53.4) = .85(7)(96)a$$

$$a = .794''$$

$$c = \frac{.794}{.7} \approx 1.134''$$

$$\frac{53.4}{5.7 - 1.134} = \frac{T_2}{2.3 - .958}$$

$$T_2 \approx 15.69 \text{ ksi}$$

$$M_n = 4.774(53.4) \left(5.7 - \frac{.794}{2} \right) + 4.774(15.69 \text{ ksi}) \left(2.3 - \frac{.794}{2} \right) + 3.72(53.4) \left(5.675 - \frac{.794}{2} \right)$$

$$M_n \approx 1351.9 + 142.5 + 1050.8 = 2545.3 \text{ in} \cdot \text{k}$$

$$M_n = 212.1 \text{ ft} \cdot \text{k}$$

$$M_R = .75(212.1) = 159.1 \text{ ft} \cdot \text{k}$$

$$\phi M_R = .973(159.1) = 154.8 \text{ ft} \cdot \text{k}$$

$$M_U < M_R \quad \text{okay} \quad \checkmark$$

$$A_s = \#4 @ 8''$$

$$= \frac{(20)}{(8/16)} = .3 \text{ in}^2/\text{ft}$$

$$= 2.4 \text{ in}^2 \text{ for } 8'$$

$$A_s = \#5 @ 8''$$

$$= \frac{.31}{8/16} = .465 \text{ in}^2/\text{ft}$$

$$= 3.72 \text{ in}^2 \text{ for } 8' \text{ slab}$$

By: Date	Project no.	Project code (SA#):
Chk'd: Date	Structure no.	Sheet 16 of

REINFORCING DESIGN

GIVEN:

$f_y = 60.00$ ksi
 $f_c = 4.50$ ksi
 COVER = 2.00 inches
 $\Phi_{flexure} = 0.75$
 Beam Thickness (t_s) = 8.00 inches
 $b = 12.00$ inches
 bar diameter = 0.875 inches

LOAD TYPE	M _{hTOT} ft-K
M _h (UNFACTORED)	5.88
STRENGTH I	5.88
SERVICE I	5.88

A _{Sreq'd} in ²
0.29
0.29
0.29

Impact Steel

Can use #5s
@ blockouts

$d_s = 5.56$ inches
 per 5.10.8.2 A_{Stemp} = 0.14 sq inches

Use #5 at top face min. spacing = 12.74 inches
 use spacing = 8.00 inches
 $A_s = 0.465$ sq. inches

compressive steel:

Use #5 at bottom face
 $A_s' = 0.00$ sq. inches

$M_n = 12.52$ ft-K
 $M_r = 9.39$ ft-K

Reinforcing is okay

Maximum Reinforcement per 5.7.3.3.1-1 (Ductility Check)

$c = 0.74$ inches
 $d_e = d_s = 5.56$ inches (for no prestressing)
 $c/d_e = 0.13$

okay - member is not overreinforced

Minimum Reinforcement per 5.7.3.3.2

$1.2 \cdot M_{cracking} = 6.52$ ft-K <--- Test 1
 $1.33 M_{hTOT} (max.) = 7.82$ ft-K <--- Test 2

Minimum Reinforcing is provided

Transverse Reinforcement per 9.7.3.2

Percentage of main reinforcement, $220 / \sqrt{S} \leq 67\%$

Girder Spacing = 15.25 ft
 Flange Width = 21 inches
 Flange Overhang = 18 inches
 Effective Length S = 15.00 ft
 $220 / \sqrt{S} = 56.80$ % Use **56.804** % of required main reinforcement
 Required $A_s = 0.26$ sq inches
 Use #6 transverse reinforcement
 min. spacing = 19.98 inches

development length 5.11.2.1.1


$$l_{dh} = \frac{(.31)(1.25)60}{\sqrt{f_c}} = 8.79''$$

or $.4(5/8)60 = 15''$

$$l_d = l_{dh} * 1.2 = 15 * (1.2)$$

$$l_d = 18''$$

For hook 5.11.2.4.1-1



$$l_{hb} = \frac{38(5/8)}{\sqrt{f_c}} = 8.98''$$

$$l_d = 1.2 l_{hb} = 10.77''$$

use 11''

11.2'' for 4.5
K₁

COLORADO DEPARTMENT OF TRANSPORTATION
DESIGN COMPUTATIONS (Grid)

STRENGTH AT OVERHANG

@ 6" from Face of Barrier

$$f_{ps} \approx \frac{20''}{36''} (147.87) = 82.15 \text{ ksi}$$

$$(4.774)(82.15) = .85(7)(96) a$$

$$a \approx .687''$$

$$\frac{82.15}{5.7 - .981} = \frac{T_2}{2.3 - .981}$$

$$c = \frac{.687}{7} \approx .0981$$

$$T_2 = 22.96 \text{ ksi}$$

$$M_n = 4.774 (82.15) \left(5.7 - \frac{.687}{2}\right) + 4.774 (22.96) \left(2.3 - \frac{.687}{2}\right)$$

$$M_n \approx 2100.73 + 214.45 = 2315 \text{ in-k} = 192.9 \text{ ft-k}$$

$$M_R = .75 (192.9) = 144.7 \text{ ft-k}$$

@ 7" from Face of Barrier

$$f_{ps} = \frac{21''}{36''} (147.87) = 86.26 \text{ ksi}$$

$$4.774 (86.26) = .85(7)(96) a$$

$$a = .721''$$

$$\frac{86.26}{5.7 - 1.03} = \frac{T_2}{2.3 - 1.03}$$

$$c = \frac{.721}{7} \approx 1.03''$$

$$T_2 = 23.46 \text{ ksi}$$

$$M_n = 4.774 (86.26) \left(5.7 - \frac{.721}{2}\right) + 4.774 (23.46) \left(2.3 - \frac{.721}{2}\right)$$

$$M_n \approx 2198.8 \text{ in-k} + 217.2 \text{ in-k} \approx 2416 \text{ in-k} \approx 201.3 \text{ ft-k}$$

$$M_R = .75 (201.3) = 151.0 \text{ ft-k}$$

By: _____	Date _____	Project no. _____	Project code (SA#): _____
Chk'd: _____	Date _____	Structure no. _____	Sheet 18 of _____

STRENGTH AT OVERHANG

@ 12" from face of barrier (beginning of live load)

$$f_{ps} = \frac{26''}{36''} (147.87) = 106.795 \text{ ksi}$$

$$\frac{106.795}{5.7 - 1.275} = \frac{T_2}{2.3 - 1.275}$$

$$T_2 = 24.74 \text{ ksi}$$

$$(4.774)(106.795) = .85(7)(96)a$$

$$a \approx .893''$$

$$c = \frac{.893}{.7} = 1.275''$$

$$M_n = 4.774(106.795)\left(5.7 - \frac{.893}{2}\right) + 4.774(24.74)\left(2.3 - \frac{.893}{2}\right)$$

$$M_n \approx 2679.4 + 218.9 = 2897.4 \text{ in k} = 241.4 \text{ ft k}$$

$$M_R = .75 M_n = 181.1 \text{ ft k}$$

@ 9.33" from girder support

L = 6.69' from barrier

L ≈ 6.21' from precast end
75.3"

$$f_{px} = f_{pe} + \frac{l_{px} - 60d_b}{l_d - 60d_b} (f_{ps} - f_{pe})$$

$$5.114.2 - 3$$

$$f_{px} = 147.87 + \frac{75.3 - 36}{79.2 - 36} (230.6 - 147.87)$$

$$f_{px} \approx 223.13 \text{ ksi}$$

209.73 @ 7" to left
198.24 @ 13" to left

$$M_n = (4.774)(2)(223.13)\left(5.7 - 2.97\right) (.7)$$

$$M_n \approx 3857.2 \text{ in k} = 321.4 \text{ ft k}$$

$$M_R = .75 (321.4) \approx 241.1 \text{ ft k}$$


$$\approx 30.14 \text{ ft k/ft}$$

226.6 @ 7" to left
214.2 @ 13" to left
no good ↑
216.2 @ 12" to left
okay

Can only move
start of precast
segment by 12"

By: Date	Project no.	Project code (SA#):
Chk'd: Date	Structure no.	Sheet 19 of

STRENGTH BY STRAIN COMPATIBILITY



Assume: depth of rectangular stress block (a) is less than $2''$

all strand in tension

strand at bottom - $f_{py} = .9f_{pu} = 243 \text{ ksi}$

strand at top - $f_{pe} \approx 147.87 \text{ ksi}$

$$T = C$$

$$T = A_{ps} \times f_{ps}$$

$$C = .85 f'_c b a$$

$$b = \text{width of panel} = 8' = 96''$$

$$A_{ps} f_{ps} = .85 f'_c b a$$

$$22(.217) 147.87 + 22(.217)(243) = .85 (7) (96) (a)$$

$$a \approx 3.27''$$

248"

$$\beta = .85 - .05(f'_c - 4) = .85 - .05(7 - 4) = .7$$

$$c = a/\beta = 3.27/.7 \approx 4.67''$$

depth of stress block $> 2''$

not all of strands are in tension

assume top strands in compression

@ yield $22(.217)(243) = .85 (7) (96) a$

$$a \approx 2.03''$$

$$c = \frac{2.03}{.7} = 2.9$$

top strands are above neutral axis (compression)

@ ultimate $22(.217) 270 = .85 (7) 96 a$

$$a \approx 2.26''$$


$$c = 3.22''$$

top strands are above neutral axis (compression)

Assume strength based on single eccentric layer

By: _____	Date _____	Project no. _____	Project code (SA#): _____
Chk'd: _____	Date _____	Structure no. _____	Sheet 20 of _____

DECK LOADS



$w_t \approx 35 \text{ K/ft}$

flange width $\approx 28''$

$l_{max} = 17'-11''$

$\frac{1}{3}$ flange width $\approx 9.33''$

INTERIOR SPANS

from SAP2000 analysis, max. pos. moment from uniform dead load $\approx \frac{w l_{max}^2}{16}$
 max. neg. moment from uniform dead load $\approx \frac{w l^2}{14}$ use for both

moments are at support points

per 4.6.2.1.6, we could use moments at $\frac{1}{3}$ flange width away from support

use higher dead load moment for design \leftarrow

DC concrete

8" precast deck - weight = $(.15 \times \frac{8''}{12''})(1') = .1 \text{ K/ft/ft width}$


$$M_{\text{positive/negative}} = \frac{(.1)(17.917')^2}{14} \approx 2.293 \text{ ft-K/ft}$$

DW

3" asphalt weight $\approx .147 \left(\frac{3''}{12''}\right) 1' \approx .037 \text{ K/ft/ft width}$

$$M_{\text{positive/negative}} = \frac{(.037)(17.917')^2}{14} \approx 0.848 \text{ ft-K/ft}$$

By: Date	Project no.	Project code (SA#):
Chk'd: Date	Structure no.	Sheet 21 of



Dead load moments for 1'x1' beam

$$M = \frac{wL^2}{n}$$

(77.4 ft K @ 9.33")

$$LL = 96.8476 \text{ ftK}$$

$$LL = 83.293 \text{ ftK}$$

$$LL = 77.81$$

$$LL = 83.6045$$

$$n = 15.6$$

$$4.485$$

$$4.287$$

$$n = 14.12$$

$$4.96$$

$$1.433$$

$$4.32$$


$$n = 16.2$$

$$L_{max} = 21.6'$$

$$w = .15 \text{ K/ft}$$

$$n = \frac{wL^2}{M} = \frac{70.06}{M}$$

use $n_{min} \approx 14$




dead load moments for 'A' beam

$$M = \frac{wL^2}{n}$$


$$L = 17.9167'$$

$$w = .15 \text{ k/ft}$$

$$n = \frac{wL^2}{M} \approx \frac{48.15}{M}$$




USE $n_{min} \approx 14$



SAP2000 v8.3.8 - File:deck_phase1 - Moment 3-3 Diagram (DEAD) - Kip, in, F Units

COLORADO DEPARTMENT OF TRANSPORTATION
DESIGN COMPUTATIONS (Grid)

per 2.6.1.3.3, use only axle loads for deck design



Impact Factor (IM) = 33% for HL-93
 per C3.6.2.1 this is 4/3 of axle load alone. For Deck Design use 25%
 1.25

per 4.6.2.1.3 & Table 4.6.2.1.3-1

Strip width $+M = 26.0 + 6.6 S$ $S+ = 17.9167'$
 $-M = 48.0 + 3.0 S$ $S- = 7.083'$


$S_{min} = 7'-1"$

$+M \text{ width} = 26.0 + 6.6 (7.08) = 72.73"$
 $-M \text{ width} = 48.0 + 3.0 (7.08) = 69.24"$

for decks that span primarily in transverse direction,
 width limits do not apply

apply live load to 8' wide panel

assume beam fixed @ both ends



can use moments @ 9.33" in for design

$l = 17.9167$

$M+ = \frac{2 (25) (5.958)^2 (11.958)^2}{17.9167^3} + \frac{25 (5.958)^2 (3(11.958) + 5.958) 5.958}{17.9167^3} - \frac{25 (11.958)(5.958)^2}{17.9167^2}$

$M+ = 44.13 + 38.46 - 33.06$

$M+ \approx 49.53 \text{ ft-kip}$

$M- = \frac{25 (5.958)(11.958)^2}{17.9167^2} + \frac{25 (11.958)(5.958)^2}{17.9167^2} + \frac{25 (11.958)(5.958)^2}{17.9167^2}$

$M- = -99.4 \text{ ft-k}$

By: Date	Project no.	Project code (SA#):
Chk'd: Date	Structure no.	Sheet 25 of

COLORADO DEPARTMENT OF TRANSPORTATION
DESIGN COMPUTATIONS (Grid)

Moment: @ 9.33" = .778 ft

$$M_x = \frac{25 (11.958)^2}{17.9167^3} (3 (5.958) + 11.958) .778 - \frac{25 (5.958) (11.958)^2}{(17.9167)^2}$$

$$+ \frac{25 (5.958)^2}{17.9167^3} (3 (11.958) + 5.958) .778 - \frac{25 (11.958) (5.958)^2}{17.9167^2}$$

$$M_x = 14.426 - 66.35 + 5.022 - 33.059$$

$$M_x = -79.96 \text{ ft k} @ 9.33''$$

from SAP2000

for one tandem load

$$M + \approx 70.28 \text{ ft k}$$

$$M - \approx -78.68 \text{ ft k @ support}$$

$$-59.238 \text{ ft k @ 9.33''}$$


Teddy's Egn.

$$M_{LL+} = \frac{(\text{Clear Span} + 2')}{32} (IAP) (.8) (IM) / \text{ft panel}$$

$$M_{LL+} = \frac{(4.33 + 2)(1)(50)}{32} (.8)(1.25) * 8' \text{ panel} = 81.65 \text{ ft k}$$

By: Date	Project no.	Project code (SA#):
Chk'd: Date	Structure no.	Sheet 26 of

COLORADO DEPARTMENT OF TRANSPORTATION
DESIGN COMPUTATIONS (Grid)



DC concrete

8" precast deck $wt = (.15 \text{ k/ft}^3) \left(\frac{8''}{12''} \right) (1') = .1 \text{ k/ft} / \text{ft width}$
 @ support:

$$M_{\text{negative}} = \frac{(.1)(7.47)^2}{2} = 2.79 \text{ ft-k/ft width}$$

@ 9.33" from support

$$M_{\text{negative}} = \frac{(.1)(6.69)^2}{2} \approx 2.24 \text{ ft-k/ft width}$$


DW

3" asphalt $weight = .147 \text{ k/ft}^3 \left(\frac{3''}{12''} \right) (1') = .037 \text{ k/ft} / \text{ft width}$

@ support: $M_{\text{negative}} = \frac{(.037)(5.97)^2}{2} = 0.66 \text{ ft-k/ft width}$

@ 9.33" from support $M_{\text{neg}} = \frac{(.037)(5.19)^2}{2} = 0.50 \text{ ft-k/ft width}$

DC BARRIER



$wt \approx .485 \text{ k/ft}$



@ support $M_{\text{negative}} = (.485 \text{ k/ft})(7.47 - 1.28) \approx 3.00 \text{ ft-k/ft width}$

@ 9.33" from support $M_{\text{negative}} = .485 \text{ k/ft} (7.47 - 1.28 - .73) \approx 2.62 \text{ ft-k/ft width}$

By: Date	Project no.	Project code (SA#):
Chk'd: Date	Structure no.	Sheet 27 of

COLORADO DEPARTMENT OF TRANSPORTATION
DESIGN COMPUTATIONS (Grid)

LL Live load



effective width
 $\approx 4 + .93 + 2(4.19) \approx 13.21'$

@ support $M_{neg} = 25(7.47 - 2.5) \approx 124.25 \text{ ft k}$

@ 9.33' from support $M_{neg} = 25(7.47 - 2.5 - .77) \approx 104.83 \text{ ft k}$

$104.83 \text{ ft k} / 13.21 \approx 7.94 \text{ ft k/ft}$

Per 3.6.1.34 $U = 1 \text{ k/ft}$ @ 1' from barrier

$M_{neg} = (1 \text{ k/ft})(4.97') = 4.97 \text{ ft k/ft}$

IMPACT LOADS

Assume TL-4 loads
 Table A13.2-1

$F_t = 54.0 \text{ kips}$


$F_L = 18.0 \text{ kips}$

$F_v = 18.0 \text{ kips}$

$L_T = L_L = 3.5 \text{ ft}$

$L_v = 18.0 \text{ ft}$

$H_e = 32 \text{ inches}$



By: Date	Project no.	Project code (SA#):
Chk'd: Date	Structure no.	Sheet <u>28</u> of

COLORADO DEPARTMENT OF TRANSPORTATION
DESIGN COMPUTATIONS (Grid)

$$L_c = \frac{L_t}{2} + \sqrt{\left(\frac{L_t}{2}\right)^2 + \frac{8H(M_b + M_w)}{M_c}} \quad (A 13.3.1-2)$$


$$L_c = \frac{3.5}{2} + \sqrt{\left(\frac{3.5}{2}\right)^2 + \frac{8(2.67)(\phi + 17.7)}{17.7}}$$

$$L_c \approx 6.69 \text{ ft}$$

$$R_w = \left(\frac{2}{2L_c - L_t}\right) \left(8M_b + 8M_w + \frac{M_c L_c^2}{H}\right) \quad (A 13.3.1-1)$$

$$R_w = \left(\frac{2}{2(6.69) - 3.5}\right) \left(\phi + 8(17.7) + \frac{17.7(6.69)^2}{2.67}\right)$$

$$R_w = 88.72 \text{ kips}$$



$$W_{avg} = \frac{18 + 0.5}{2} = 14.25" \quad (CA 13.3.1)$$

$$M_b = \phi$$

$$M_c = 5\text{-}\#4s \text{ in } 35" \approx \#4 @ 8" \quad M_c = 17.7 \text{ ft-k/ft}$$

$$M_w = \#4 @ 8"$$

$$M_w \approx 17.7 \text{ ft-k/ft}$$


$$H = 2.67' (32")$$

$$T = \frac{R_w}{L_c + 2H} \quad (A 13.4.2-1)$$

$$T = \frac{88.72}{6.69 + 2(2.67)} \approx 7.38 \text{ k/ft} \quad (\text{tensile force in deck})$$

DESIGN CASE I

Extreme Event II - transverse & longitudinal force
 assume longitudinal force does not increase deck moment or transverse stress



$$M_{neg \text{ impact}} = (54 \text{ kips}) \left(\frac{32 + 3 + 8}{12}\right) = 193.5 \text{ ft-kip}$$

$$M_{c \text{ base}} \approx 23.33 \text{ ft-k/ft}$$

$$M_{c \text{ avg}} = 17.7 \text{ ft-k/ft}$$

per A13.4.2, design for $M_s > M_{c \text{ avg}} + T$

By: Date	Project no.	Project code (SA#):
Chk'd: Date	Structure no.	Sheet 29 of

REINFORCING DESIGN

GIVEN:

$f_y = 60.00$ ksi
 $f_c = 4.50$ ksi
 COVER = 2.00 inches
 $\Phi_{flexure} = 0.90$
 Beam Thickness (t_s) = 14.25 inches
 $b = 12.00$ inches
 bar diameter = 0.500 inches

Average Barrier
Strength

TOP STEEL

LOAD TYPE	M_{hTOT} ft-K
M_h (UNFACTORED)	1.00
STRENGTH I	1.00
SERVICE I	1.00

$A_{Sreq'd}$ in ²
0.02
0.02
0.02

$d_s = 12.00$ inches
 per 5.10.8.2 $A_{Stemp} = 0.26$ sq inches

Use # 4 at top face min. spacing = 129.46 inches
 use spacing = 8.00 inches
 $A_s = 0.300$ sq. inches

compressive steel:

Use # 5 at bottom face
 $A_{s'} = 0.00$ sq. inches

$M_h = 17.71$ ft-K
 $M_r = 15.94$ ft-K

Reinforcing is okay

Maximum Reinforcement per 5.7.3.3.1-1 (Ductility Check)

$c = 0.48$ inches
 $d_e = d_s = 12.00$ inches (for no prestressing)
 $c/d_e = 0.04$

okay - member is not overreinforced

Minimum Reinforcement per 5.7.3.3.2

$1.2 * M_{cracking} = 20.68$ ft-K <--- Test 1
 $1.33 M_{hTOT} (max.) = 1.33$ ft-K <--- Test 2

Minimum Reinforcing is provided

Transverse Reinforcement per 9.7.3.2

Percentage of main reinforcement, $220 / \sqrt{S} \leq 67\%$

Girder Spacing = 10.94 ft
 Flange Width = 43 inches
 Flange Overhang = 18 inches
 Effective Length $S = 8.86$ ft
 $220 / \sqrt{S} = 73.92\%$ Use **67%** of required main reinforcement
 Required $A_s = 0.20$ sq inches
 Use # 4 transverse reinforcement
 min. spacing = 11.94 inches

REINFORCING DESIGN

GIVEN:

fy= 60.00 ksi
 fc= 4.50 ksi
 COVER= 2.00 inches
 $\Phi_{flexure}$ = 0.90
 Beam Thickness (ts)= 18.00 inches
 b= 12.00 inches
 bar diameter= 0.500 inches

*Barrier strength
 @ Base*

TOP STEEL

LOAD TYPE	MhTOT ft-K
Mh (UNFACTORED)	1.00
STRENGTH I	1.00
SERVICE I	1.00

ASreq'd in^2
0.01
0.01
0.01

ds= 15.75 inches
 per 5.10.8.2 AStemp= 0.32 sq inches

Use # 4 at top face min. spacing = 170.00 inches
 use spacing= 8.00 inches
 As= 0.300 sq. inches

compressive steel:

Use # 5 at bottom face
 As'= 0.00 sq. inches

Mn= 23.33 ft-K
 Mr= 21.00 ft-K

Reinforcing is okay

Maximum Reinforcement per 5.7.3.3.1-1 (Ductility Check)

c= 0.48 inches
 de=ds= 15.75 inches (for no prestressing)
 c/de= 0.03

okay - member is not overreinforced

Minimum Reinforcement per 5.7.3.3.2

1.2*Mcracking= 32.99 ft-K <--- Test 1
 1.33MhTOT (max.)= 1.33 ft-K <--- Test 2

Minimum Reinforcing is provided

Transverse Reinforcement per 9.7.3.2

Percentage of main reinforcement, 220 / sqrt(S) <= 67%

Girder Spacing = 10.94 ft
 Flange Width = 43 inches
 Flange Overhang = 18 inches
 Effective Length S = 8.86 ft
 220 / sqrt(S) = 73.92 % Use 67 % of required main reinforcement
 Required As = 0.20 sq inches
 Use # 4 transverse reinforcement
 min. spacing = 11.94 inches

Design Computations

REINFORCING DESIGN

GIVEN:

$f_y = 60.00$ ksi
 $f'_c = 4.50$ ksi
 COVER = 2.00 inches
 $\Phi_{flexure} = 0.90$
 Beam Thickness (t_s) = 10.50 inches
 $b = 12.00$ inches
 bar diameter = 0.500 inches

Barrier Strength @ TOP

TOP STEEL

LOAD TYPE	M_{hTOT} ft-K
M_h (UNFACTORED)	1.00
STRENGTH I	1.00
SERVICE I	1.00

$A_{Sreq'd}$ in ²
0.03
0.03
0.03

$d_s = 8.25$ inches
 per 5.10.8.2 $A_{Stemp} = 0.19$ sq inches

Use # 4 at top face min. spacing = 88.90 inches
 use spacing = 8.00 inches
 $A_s = 0.300$ sq. inches

compressive steel:

Use # 5 at bottom face
 $A_{s'} = 0.00$ sq. inches

$M_n = 12.08$ ft-K
 $M_r = 10.87$ ft-K

Reinforcing is okay

Maximum Reinforcement per 5.7.3.3.1-1 (Ductility Check)

$c = 0.48$ inches
 $d_e = d_s = 8.25$ inches (for no prestressing)
 $c/d_e = 0.06$

okay - member is not overreinforced

Minimum Reinforcement per 5.7.3.3.2

$1.2 * M_{cracking} = 11.23$ ft-K <--- Test 1
 $1.33 M_{hTOT} (max.) = 1.33$ ft-K <--- Test 2

Minimum Reinforcing is provided

Transverse Reinforcement per 9.7.3.2

Percentage of main reinforcement, $220 / \sqrt{S} \leq 67\%$

Girder Spacing = 10.94 ft
 Flange Width = 43 inches
 Flange Overhang = 18 inches
 Effective Length $S = 8.86$ ft
 $220 / \sqrt{S} = 73.92\%$ Use 67 % of required main reinforcement
 Required $A_s = 0.20$ sq inches
 Use # 4 transverse reinforcement
 min. spacing = 11.94 inches

By: Date
 Chk'd: Date

Project no.
 Structure no.

Project code (SA#)
 Sheet 2 of

COLORADO DEPARTMENT OF TRANSPORTATION
DESIGN COMPUTATIONS (Grid)

INTERACTION FORMULA

$$\frac{P_u}{\phi P_n} + \frac{M_u}{\phi M_n} \leq 1.0$$

$$M_u \leq \phi M_n \left(1.0 - \frac{P_u}{\phi P_n} \right)$$

$$P_u = T$$

$$\phi P_n = \phi A_{st} f_y$$

$$A_{st} = (52 \text{ strands}) (217 \text{ in}^2) \approx 11.284 \text{ in}^2 \text{ in } 8' \text{ slab}$$

$$F_u = 270 \text{ ksi}$$

$$F_y \approx 243 \text{ ksi}$$

$$\phi P_n = (1.0)(11.284 \text{ in}^2)(243 \text{ ksi}) = 2742 \text{ K over } 8'$$

$$\approx 342.75 \text{ K/ft}$$

$$T = 7.38 \text{ K/ft}$$

$$M_u \leq \phi M_n \left(1.0 - \frac{7.38 \text{ K/ft}}{342.75 \text{ K/ft}} \right) \approx \phi M_n (.978)$$

$$\text{for } A_{st} = (42 \text{ strands}) (217) \approx 9.114 \text{ in}^2$$

$$\phi P_n = (1.0)(9.114)(243 \text{ ksi}) = 2214.7 \text{ K} = 276.84 \text{ K/ft}$$


$$M_u = \phi M_n \left(1.0 - \frac{7.38}{276.84} \right) = .973 \phi M_n$$

By: Date	Project no.	Project code (SA#):
Chk'd: Date	Structure no.	Sheet 33 of

DESIGN CASE 2

Extreme Event II - vertical force

$F_v = 18 \text{ Kips over } 18 \text{ ft} \Rightarrow 1 \text{ k/ft}$



assume F_v acts at middle of top face

moment arm = $7'-5 \frac{5}{8} - \frac{10 \frac{1}{2}}{2} \approx 7.03'$

$M_{\text{Impact}} = (7.03') (1 \text{ k/ft}) = 7.03 \text{ ft k/ft wall}$

HANDLING LOADS

ASSUME LIFTING LUGS @ 1/4 points of slab

$$L_{slab} \approx 43.5'$$

$$\text{cantilever moment} \approx \frac{wl^2}{2}$$

$$w = (.67)(1)(.15)k/cf \approx .1 \text{ k/ft / ft width}$$

$$M = \frac{(.1) \left(\frac{43.5}{4}\right)^2}{2} \approx 5.91 \text{ ft k.p/ft}$$

mid support moment

$$M = \frac{wlx}{2l} (l^2 - a^2 - xl) - \frac{wa^2x}{2l}$$

$$x = a = l/2$$

$$M = \frac{w(l/2)}{2l} \left(l^2 - \frac{l^2}{4} - \frac{l^2}{2} \right) - \frac{w(l/2)^2}{2l} \cdot \frac{l}{4}$$

$$M = \frac{wl^2}{16} - \frac{wl^2}{16}$$

$$M = \phi$$

if @ 1/5 points

$$\text{cantilever moment} \approx \frac{(.1) \left(\frac{43.5}{5}\right)^2}{2} \approx 3.78 \text{ ft k.p/ft}$$

mid support moment

$$a = l/3 \quad x = l/2$$

$$l = \frac{3}{5} L = 26.1' \pm$$

$$M = \frac{w(l/3)}{2l} \left(l^2 - \frac{l^2}{9} - \frac{l^2}{2} \right) - \frac{w(l/3)^2}{2l} \cdot \frac{l}{2}$$

$$M = \frac{w}{6} \left(\frac{7}{18} l^2 \right) - \frac{wl^2}{36}$$

$$M = \frac{.1}{6} \left(\frac{7}{18} (26.1) \right) - \frac{.1 (26.1)^2}{36} = 1.72 \text{ ft k.p/ft}$$

By: Date	Project no.	Project code (SA#):
Chk'd: Date	Structure no.	Sheet 35 of

STRENGTH CHECKS

$M_R \approx 249 \text{ ft K}$

INTERIOR

STRENGTH I

(8' sks)

$M_u \text{ positive} = 1.25 DC + 1.5 DW + 1.75 (LL + IM)$

$M_u \text{ positive} = 1.25 (2.293)(8) + 1.5 (.848)(8) + 1.75 (70.28) 1.25$

$M_u \text{ positive} = 186.84 \text{ ft K} < M_R \text{ okay } \checkmark$

$M_u \text{ negative} = 1.25 (2.293)(8) + 1.5 (.848)(8) + 1.75 (59.238) 1.25$

$M_u \text{ negative} = 162.69 \text{ ft K} < M_R \text{ okay } \checkmark$

SERVICE I

$M_u \text{ positive} = DC + DW + LL + IM$

$= (2.293)(8) + .848(8) + 70.28(1.25)$

$M_u \text{ positive} = 87.85 \text{ ft K}$

$M_u \text{ negative} = 2.293(8) + .848(8) + (59.238) 1.25$

$M_u \text{ negative} = 99.18 \text{ ft K}$

By: _____	Date _____	Project no. _____	Project code (SA#): _____
Chk'd: _____	Date _____	Structure no. _____	Sheet <u>26</u> of _____

STRENGTH CHECKS

$M_R \approx 249 \text{ ft K}$

EXTERIOR

STRENGTH I (8' SLAB)

$$M_u \text{ negative} = 1.25 DC + 1.5 DW + 1.75 (LL + IM)$$

$$= 1.25 (2.24 + 2.62) 8 + 1.5 (0.5) 8 + 1.75 (4.97) (8) 1.25$$

$$M_u \text{ negative} = 141.58 \text{ ft K} < M_R \text{ okay } \checkmark$$

203.3 ft K if 3.6.1.3.4 not used

@ Transfer Length $M_u = 1.25 \left[\frac{.1 (3.42)^2}{2} + .485 (2.417 - 1.28) \right] + 1.5 \left[\frac{.027 (2.42)^2}{2} \right]$
 $+ 1.75 \left[\frac{1}{4} (1.9167) \right]$
 $M_u = 3.96 \text{ K ft/ft} \times 8 \text{ ft} \approx 31.6 \text{ ft K} < M_R \text{ okay } \checkmark$

$M_u < M_R$
 okay if 3.6.1.3.4 not used

SERVICE I

$$M_{all \text{ negative}} = (2.24 + 2.57) 8 + (0.5)(8) + 4.97(8) 1.25$$

$$M_{all \text{ negative}} \approx 92.18 \text{ ft K}$$

129.7 ft K if 3.6.1.3.4 not used

EXTREME EVENT II - Design Case 1, A13.4.1

$$M_u = 1.0 DC + 1.0 DW + .5(LL + IM) + M_c + T \leftarrow \text{incorporate into } M_R$$

$$M_u = 1.0 (2.24 + 2.62) 8 + 1.0 (0.5) 8 + .5 (4.97(8)) 1.25 + 17.7 \text{ ft K}(8)$$

$$M_u = 219.8 \text{ ft K}$$

235.98 ft K if 3.6.1.3.4 not used

from interaction formula $M_{R \text{ tension}} = .973 \phi M_n = .973 M_R$

$$M_{R \text{ tension}} = .973 (241.1) = 234.6$$

reduced for development length

$$M_R > M_u \text{ okay } \checkmark$$

By: Date	Project no.	Project code (SA#):
Chk'd: Date	Structure no.	Sheet 37 of

STRENGTH CHECKS

EXTREME EVENT II - Design Case 1

PRESTRESSING NOT FULLY DEVELOPED

@ Face of Barrier

$$M_u \approx 1.0 \left[\frac{.1(1.5)^2}{2} + \frac{.485(1.5-1.28)^2}{2} \right] + 17.7 \text{ ft-k/ft}$$

$$M_u \approx .124 + 17.7 \approx 17.82 \text{ ft-k/ft}$$

$$M_u \approx 142.59 \text{ ft-k for 8' slab}$$

$$M_R \text{ prestressed} \approx 98.1 \text{ ft-k}$$

$$M_R \text{ mild steel} \approx 9.39 \text{ ft-k/ft} * 8 \approx 75.1 \text{ ft-k}$$

$$M_R \text{ total} = (173.2 \text{ ft-k}) * .973 \approx 168.5 \text{ ft-k}$$

$$M_u < M_R \quad \checkmark \text{ okay}$$

@ Transfer length (36") 3'-5" from edge of deck (1'-11" from barrier)

$$M_u \approx 1.0 \left[\frac{.1(3.42)^2}{2} + .485(3.417-1.28)^2 \right] + 1.0 \left[\frac{.037(3.42)^2}{2} \right] + .5 \left[\frac{125 \text{ (ft-k/ft)} (9.167)}{1} \right]$$

$$+ 17.7 \text{ ft-k/ft}$$

$$M_u \approx 20.11 \text{ ft-k/ft}$$

$$M_u \approx 160.88 \text{ ft-k for 8' slab}$$

$$M_R \text{ prestressed} = (234.3 \text{ ft-k}) * .973 \approx 228.0 \text{ ft-k}$$

$$M_u < M_R \quad \checkmark \text{ okay}$$

@ 13" from barrier (live load)

$$M_u \approx 1.0 \left[\frac{.1(2.58)^2}{2} + .485(2.58-1.28)^2 \right] + 1.0 \left[\frac{.037(1.1)^2}{2} \right] + .5(1 \text{ ft-k/ft})(.08) + 17.7 \text{ ft-k}$$

$$M_u \approx 18.74 \text{ ft-k/ft} \approx 149.9 \text{ ft-k for 8' slab}$$

$$M_R > 18.11 \text{ ft-k}$$

$$M_u < M_R \quad \text{okay} \quad \checkmark$$

By: Date	Project no.	Project code (SA#):
Chk'd: Date	Structure no.	Sheet <u>38</u> of <u> </u>

COLORADO DEPARTMENT OF TRANSPORTATION
DESIGN COMPUTATIONS (Grid)

AT 7" FROM BARRIER

$$M_U = 1.0 \left[\frac{.1(2.08)^2}{2} + .485(2.08 - 1.28) \right] + 1.0 \left[\frac{.037(.583)^2}{2} \right] + 17.7$$

$$M_U = 18.31 \text{ ft-k}$$

$$M_U = 146.48 \text{ ft-k for 8' slab}$$

$$M_R = .973(151) \approx 146.9 \text{ ft-k}$$

$M_U < M_R$ ✓ okay mild steel not reqd

AT 6" $M_U = 1.0 \left[\frac{.1(2)^2}{2} + .485(2 - 1.28) \right] + 1.0 \left[\frac{.037(.5)^2}{2} \right] + 17.7$

$$M_U = 18.25 \text{ ft-k/ft}$$

$$M_U = (18.25)(8) = 146.0 \text{ ft-k for 8' slab}$$

$$M_R = .973(144.7) = 140.8 \text{ ft-k}$$

$M_U > M_R$ add mild steel #5 @ 8" = 8(9.39) * .973 = 73.1
 $M_R \text{ w/ steel} = 213.9 > M_U$ okay ✓

$$\frac{A_s \text{ reqd}}{A_s \text{ provided}} = \frac{146.0}{213.9} = .68$$

12.5" post point

EXTREME EVENT II - Design Case 2 A13.4.1

$$M_U = 1.0 DC + 1.0 DW + .5(LL + IM) + M_v$$

$$M_U = 1.0(2.24 + 2.62)(8) + 1.0(.5)(8) + .5(4.97)(8)1.25 + 7.05(8)$$

$$M_U = 123.97 \text{ ft-k}$$

$$M_R = 249 \text{ ft-k}$$

$M_U < M_R$ okay ✓

By: Date	Project no.	Project code (SA#):
Chk'd: Date	Structure no.	Sheet 39 of

STRESS CHECKS @ RELEASE

COMPRESSIVE Stress @ Release

$\Delta P_{ES} = 16.98 \text{ ksi}$

strands are concentric, so no eccentricity checks

$f_c = \frac{P}{A}$

$P = (.75(270) - 16.98)(44 \text{ strands}) .217$

1678.6

30 strands max

$P = 1771.3 \text{ k}$

185.52

$f_c = \frac{1771.3}{403.375 \text{ in}^2} = 4.39 \text{ ksi @ blockouts}$


4.14

$f_c = \frac{1771.3}{723.315} = 2.45 \text{ ksi with no blockouts}$

Compressive limit = $.6f'_{ci} = .6(5) = 3 \text{ ksi}$

36 strands

38 strands
153



for 6 ksi release 2.67

+ 1/2" $A = 427.875$
 + 1" $A = 452.375$

31 strands

NO GOOD for 44 strands

- 38 strands for 6 ksi 1529.8

- 40 strands for 6 ksi

use 30 strands max 356 ksi

TENSION

tension $< .24 \sqrt{f'_{ci}}$

strands are concentric, so no eccentricity

\therefore tension $\approx \phi$

By: Date	Project no.	Project code (SA#):
Chk'd: Date	Structure no.	Sheet 40 of

COLORADO DEPARTMENT OF TRANSPORTATION
DESIGN COMPUTATIONS (Grid)

STRESS CHECKS @ SERVICE 5.9.4

Total Losses @ Transfer = $\Delta_{PEs} = 16.98 \text{ ksi}$

Total Losses @ Service Loads

$$\Delta f_{PT} = \Delta f_{PEs} + \Delta f_{FR} + \Delta f_{CR} + \Delta f_{PR}$$

$$= 16.98 + 5.27 + 7.72 + 1.2 + 12.08 + 10.18 + 1.2$$

$$\Delta f_{PT} = 54.63 \text{ ksi}$$

Stress in tendons

$$\Delta f_{pe} = f_{pi} - \Delta f_{PT} = 202.5 - 54.63 = 147.87 \text{ ksi}$$

$$f_{pe} \leq .8 f_{py} \quad (\text{Table 5.9.3-1})$$

$$\leq .8 [270] = 194.4 \text{ ksi} \quad \checkmark \quad \text{OK}$$

$$\text{final prestress losses} = \frac{54.63}{202.5} \times 100 \approx 26.98 \%$$

Concrete Stress in Positive Moment Area (Table 5.9.4.2.1-1)

$$P_{pe} = (147.87 \text{ ksi}) (44 \text{ strands}) (217 \text{ in}^2) \approx 1411.86 \text{ K}$$

$$f_c = \frac{P_e}{A} + \left(\frac{M_{slab} + M_{barrier} + M_{DW} + M_{LL}}{S_T} \right)$$

$$f_c = \frac{1411.86}{723.375} + \frac{(2.293)(8)(12)}{960.75 \text{ in}^3} + 20 + \frac{(848)(8)(12)}{1024} + \frac{(70.28 \text{ ft-k})(12)}{1024} \cdot 1.33$$

$$f_c = 1.95 + .23 + 0 + .08 + 1.09$$

$$f_c \approx 3.35 \text{ ksi}$$

$$\text{Compressive limit} = .6 f'_c = .6(7) = 4.2 \text{ ksi} \quad \checkmark \quad \text{OKay}$$

$$\text{for permanent loads} \approx f_c \approx 2.26 \text{ ksi}$$

$$\text{limit} = .45 f'_c = .45(7) = 3.15 \text{ ksi} \quad \checkmark \quad \text{OKay}$$

$$LL + \frac{1}{2}(DL + PS) < .4 f'_c \quad \checkmark \quad \text{OKay}$$

By: Date	Project no.	Project code (SA#):
Chk'd: Date	Structure no.	Sheet <u>41</u> of <u> </u>

COLORADO DEPARTMENT OF TRANSPORTATION
DESIGN COMPUTATIONS (Grid)

STRESS CHECK @ SERVICE

TENSION

$$\text{limits} = .19 \sqrt{f'_c} = .19 \sqrt{7} = 502.7 \text{ psi}$$

Service III

$$DC + DW + PS + .8(LL + IH)$$

$$f_t = \frac{P_e}{A} - \frac{M_{s66}}{S_{s66}} + \frac{M_{bar}}{S_{s66}} - \frac{M_{DW}}{S_{s66}} - \frac{M_{LL}}{S_{s66}}$$

$$f_t = \frac{1411.86}{723.375} - \frac{(2.293)(8)(12)}{982.96} - \frac{(.473)(8)(12)}{1024} - \frac{(.848)(8)(12)}{1024} - \frac{(70.29)(12) 1.33 (.8)}{1024}$$

$$f_t = 1.95 - .224 - .044 - .080 - 0.880$$

$$f_c = .722 \text{ ksi (compression)} \quad \checkmark \quad \text{okay}$$

CONCRETE STRESS AT NEGATIVE MOMENT AREA (INTERIOR)

COMPRESSION - SERVICE I

$$f_c = \frac{1411.86}{723.375} + \frac{(2.293)(8)(12)}{982.96} + 0 + \frac{(.848)(8)(12)}{1024} + \frac{(59.238)(12) 1.33}{1024}$$

$$f_c = 1.95 + .224 + 0 + .080 + .923$$

$$f_c = 3.18 \text{ ksi} < 4.2 \text{ ksi} \quad \checkmark \quad \text{okay}$$

Tension - Service III

$$f_t = \frac{1411.86}{723.375} - \frac{(2.293)(8)(12)}{960.75} - \frac{(.473)(8)(12)}{1024} - \frac{(.848)(8)(12)}{1024} - \frac{(59.238)(12) 1.33 (.8)}{1024}$$

$$f_t = 1.95 - .229 - .044 - .08 - .739$$

$$f_t \approx .858 \text{ (compression)} \quad \checkmark \quad \text{okay}$$

By: _____	Date _____	Project no. _____	Project code (SA#): _____
Chk'd: _____	Date _____	Structure no. _____	Sheet 42 of _____

SECTION PROPERTIES (Interior Girder: Precast panel)

GEOMETRY

Structure Number? **Precast panel**
 # of spans = 3.000
 Center to Center Panel Spacing = 8.000 feet
 overhang = 9.010 feet
 Panel Length = 51.87 feet
 deflection point = 0.40 *L
 a = 0.4*L = 20.75 feet
 Exterior Girder ? (Y or N) **N**
 Weight of Formwork = 5.00 psf

NONCOMPOSITE PROPERTIES

Girder Type ? **FULLDEPTHPRECASTPANEL**
 Girder Depth = 8.0 inches

Area =	723.38 in ²	Top Width =	89.00 inches
y _b (CG) =	3.95 inches	Bottom Width =	94 inches
y _t =	4.05 inches	Depth to Slope =	5 inches
I _g =	3886.92 in ⁴	Slope Depth =	1.25 inches
S _{bottom} =	982.97 in ³	Chamfer Dimension =	0.5 inches
S _{top} =	960.75 in ³	Slope Depth from Bottom =	1.75 inches

of strands = 28
 Strand diameter = 0.600 inches
 Individual Strand Area = 0.217 in²
 Strand Center of Gravity at Midspan = 4.00 inches
 Strand Center of Gravity at End = 4.00 inches
 Estrand = 28500 ksi
 f_u = 270 ksi

Depth of Haunch for Strength = 0.00 inches

Thickness of Deck =	0.00 inches	W _{concrete-deck} =	0.150 kcf
Effective Width of Deck =	0.00 inches	W _{concrete-girder} =	0.150 kcf
Ec-deck =	4069.64 ksi *	f _{c-deck} =	5.00 ksi
Ec-girder initial =	4069.64 ksi *	f _{c-girderinitial} =	5.00 ksi
Ec-girder 28day =	4883.57 ksi *	f _{c-girder28day} =	7.20 ksi

* Ec based on Eqn. C5.4.2.4-1

TRANSFORMED NONCOMPOSITE PROPERTIES (Prestressing Steel Transformed)

n = 5.84 (using Ec-girder final = long term modular ratio)
 A_{steeltransformed} = 29.38 in²
 y_{bottomnoncomposite} = 3.96 inches
 I_{noncomposite} = 3886.98 in⁴

n = 7.00 (using Ec-girder initial = initial modular ratio)
 A_{steeltransformed} = 36.47 in²
 y_{bottomnoncomposite} = 3.96 inches
 I_{noncomposite-initial} = 3887.00 in⁴

TRANSFORMED COMPOSITE PROPERTIES (Prestressing Steel Transformed)

n = 0.8333 (using Ec-girder final = long term modular ratio)
 y_{bottomcompositetransformed} = 3.96 inches
 I_{compositetransformed} = 3886.98 in⁴

GROSS COMPOSITE PROPERTIES

Assume closure pour concrete ~ equals precast concrete properties

By: _____ Date _____
 Chk'd: _____ Date _____

Project no. _____
 Structure no. _____

Project code (SA#) _____
 Sheet 43 of _____

Ybottomcomposite =	4.00 inches	
Icomposite =	4096.00 in ⁴	
Acomposite =	768 in ²	only good for precast panels
Sbottom=	1024.00 in ³	only good for precast panels
Stop=	1024.00 in ³	only good for precast panels

By: Date
Chk'd: Date

Project no. .
Structure no. .

Project code (SA#) .
Sheet 4A of .

PRESTRESS LOSSES (28 Strands)

Note: Prestress Losses are based on Non-Transformed Section Properties

ELASTIC SHORTENING (per 5.9.5.2.3a)

(for usual design cases)

$$\Delta f_{pES} = (E_p/E_{ci}) f_{cgp}$$

$$E_p = 28500.00 \text{ ksi}$$

$$E_{ci} = 4069.64 \text{ ksi}$$

$$\text{cover to prestressing} = 2 \text{ inches}$$

$$f_{cgp} = P/A + (P \cdot e/I) \cdot y + M_g \cdot y/I$$

$$P_t = .7 \cdot f_u \cdot A_{strand} = 1148.36 \text{ k (low relax strand)}$$

$$M_g = W_{self} \cdot (L^2) / 8 = 253.39 \text{ ft-k}$$

$$e = 0.05 \text{ inches}$$

$$y = 1.65 \text{ inches}$$

$$\text{per RLO: } 0.75$$

$$f_{ji} = 0.75 \cdot f_u = 202.50 \text{ ksi}$$

$$\text{initial relaxation} = 3.50\%$$

$$f_{jo} = 184.79 \text{ ksi}$$

$$\Delta f_{pES} = 10.62 \text{ ksi (RLO)}$$

$$f_{cgp} = 1.62 \text{ ksi}$$

$$\Delta f_{pES} = 11.37 \text{ ksi (gross method)}$$

$$\text{USE } \Delta f_{pES} = 11.02 \text{ ksi}$$

$$11.34 \text{ ksi (per Transformed Section Analysis)}$$

$$11.02 \text{ ksi (per C5.9.5.2.3a-1)}$$

LOSSES: Time of Transfer to Time of Deck Placement (5.9.5.4.2)

$$\text{time to transfer (t)}_t = 0.75 \text{ days}$$

$$\text{time to deck placement (t)}_d = 30 \text{ days}$$

$$\text{final age (t)}_r = 18250 \text{ days}$$

$$= 50.0 \text{ years}$$

SHRINKAGE OF GIRDER CONCRETE (per 5.9.5.4.2a)

$$\text{average annual humidity (H)} = 55.00\%$$

$$\Delta f_{pSR} = \epsilon_{bid} \cdot E_p \cdot K_{id}$$

$$\epsilon_{bid} = K_s \cdot K_{hs} \cdot K_f \cdot K_{td} \cdot 0.48 \cdot 10^{-3} \quad (5.4.2.3.3-1)$$

$$K_s = 1.45 - .13(V/S) \geq 1.0 \quad (5.4.2.3.2-2)$$

$$V/S = 3.60$$

$$K_s = 1.000$$

$$K_{hs} = 2.0 - .014 H \quad (5.4.2.3.3-2)$$

$$K_{hs} = 1.230$$

$$K_f = 5 / (1 + f_{ci}) \quad (5.4.2.3.2-4)$$

$$K_f = 0.833$$

$$K_{td} = t_d / (61 - 4f_{ci} + t_d) \quad (5.4.2.3.2-5)$$

$$K_{td} = 0.423$$

$$\epsilon_{bid} = 2.08E-04$$

$$K_{id} = 1 / (1 + E_p/E_{ci} \cdot A_{ps}/A_g \cdot (1 + A_g \cdot e_{pg}^2/I_g) \cdot [1 + .7 \psi(t_r, t)]) \quad (5.9.5.4.2a-2)$$

$$\psi(t_r, t) = 1.9 \cdot K_s \cdot K_{hc} \cdot K_f \cdot K_{td} \cdot t_r^{-1.18} \quad (5.4.2.3.2-1)$$

$$K_{hc} = 1.56 - .008 H \quad (5.4.2.3.3-3)$$

$$K_{hc} = 1.120$$

$$K_{td} = t_r / (61 - 4f_{ci} + t_r) \quad (5.4.2.3.2-5)$$

$$K_{td} = 0.998$$

$$\psi(t_r, t) = 0.556$$

$$K_{id} = 0.924$$

$$\Delta f_{pSR} = 5.48 \text{ ksi}$$

By: _____ Date _____
 Chk'd: _____ Date _____

Project no. _____
 Structure no. _____

Project code (SA#) _____
 Sheet 45 of _____

LOSSES: Time of Transfer to Time of Deck Placement (5.9.5.4.2) (continued)

CREEP OF GIRDER CONCRETE (per 5.9.5.4.2b)

$$\Delta f_{pCR} = E_p/E_{ci} * f_{cgp} * \psi(t_a, t_i) * K_{id} \quad (5.9.5.4.2b-1)$$

$$\psi(t_a, t_i) = 1.9 * K_s * K_{hc} * K_f * K_{td} * t_i^{-1.18} \quad (5.4.2.3.2-1)$$

$$K_s = 1.000$$

$$K_{hc} = 1.120$$

$$K_f = 0.833$$

$$K_{td} = t_i / (61 - 4f_{ci} + t_i) \quad (5.4.2.3.2-5)$$

$$K_{td} = 0.423$$

$$\psi(t_a, t_i) = 0.502$$

$$\Delta f_{pCR} = 5.27 \text{ ksi}$$

RELAXATION OF PRESTRESSING STRANDS (per 5.9.5.4.2c)

$$\Delta f_{pR1} = f_{pt} / K_I * (f_{pt} / f_{py} - .55) \quad (5.9.5.4.2c-1)$$

Type of Strand = **Low-Relaxation** $K_I = 30$

$$f_{pj} = .75 f_{pu} = 202.50 \text{ ksi} \quad (\text{Table 5.9.3-1})$$

$$f_{py} = .9 f_{pu} = 243.00 \text{ ksi}$$

$$\Delta f_{pR1} = 1.52 \text{ Per } 5.9.5.4.2c, \Delta f_{pR1} \text{ may be assumed equal to } 1.2 \text{ ksi}$$

$$\Delta f_{pR1} = 1.20 \text{ ksi}$$

LOSSES: Time of Deck Placement to Final Time (5.9.5.4.3)

time to transfer (t_i) = 0.75 days
 time to deck placement (t_d) = 30.0 days
 final age (t_f) = 18250.0 days
 = 50.0 years

SHRINKAGE OF GIRDER CONCRETE (per 5.9.5.4.3a)

$$\Delta f_{pSD} = \epsilon_{bdf} * E_p * K_{df} \quad (5.9.5.4.3a-1)$$

$$\epsilon_{bdf} = K_s * K_{hs} * K_f * K_{td} * 0.48 * 10^{-3} \quad (5.4.2.3.3-1)$$

$$K_s = 1.000$$

$$K_{hs} = 1.230$$

$$K_f = 0.833$$

$$K_{td} = t_i / (61 - 4f_{ci} + t_i) \quad (5.4.2.3.2-5)$$

$$K_{td} = 0.998$$

$$\epsilon_{bdf} = 4.91E-04$$

$$K_{df} = 1 / (1 + E_p/E_{ci} * A_{ps}/A_c * (1 + A_c * e_{pc}^2 / I_c) * [1 + .7 \psi(t_r, t_i)])$$

$$\psi(t_r, t_i) = 1.9 * K_s * K_{hc} * K_f * K_{td} * t_i^{-1.18}$$

$$K_{hc} = 1.120$$

$$\psi(t_r, t_i) = 0.556$$

$$K_{df} = 0.929$$

$$\Delta f_{pSD} = 12.99 \text{ ksi}$$

By: _____ Date _____
 Chk'd: _____ Date _____

Project no. _____
 Structure no. _____

Project code (SA#) _____
 Sheet 46 of _____

CREEP OF GIRDER CONCRETE (per 5.9.5.4.3b)

$$\Delta f_{pCD} = E_p/E_{ci} * f_{cgp} * [\psi(t_r, t_i) - \psi(t_a, t_i)] * K_{df} + E_p/E_c * \Delta f_{cd} * \psi(t_r, t_a) * K_{df} \quad (5.9.5.4.2.6-1)$$

$f_{cgp} = 1.62 \text{ ksi}$
 $K_{df} = 0.929$
 $\psi(t_r, t_i) = 0.556$
 $\psi(t_a, t_i) = 0.502$

$$\psi(t_r, t_a) = 1.9 * K_s * K_{hc} * K_f * K_{td} * t_a^{-1.18} \quad (5.4.2.3.2-1)$$

$K_s = 1.000$
 $K_{hc} = 1.120$
 $K_f = 0.833$

$$K_{td} = t_i / (61 - 4f'_{ci} + t_i) \quad (5.4.2.3.2-5)$$

$K_{td} = 0.998$
 $\psi(t_r, t_a) = 1.184$

Total losses: $\Delta f_{pid} = \Delta f_{psR} + \Delta f_{pCR} + \Delta f_{pR2}$ NCHRP 496 Example 4
 $\Delta f_{pid} = 11.95 \text{ ksi}$
 $\Delta P = \Delta f_{pid} * A_{ps} = 72.61 \text{ kip}$

$$\Delta f_{cd} = \Delta P / A_c + (\Delta P * e / I_c) * y + M_g * y / I_g + M_c * y / I_c$$

Input following moments from Conspan or other calculations:

$M_{noncomposite} (M_g) = 26.69 \text{ ft-k}$ $M_{simple} = 0.00 \text{ ft-k}$ (see deflection sheet)
 $M_{composite} (M_c) = 9.88 \text{ ft-k}$ $M_{simple} = 0.00 \text{ ft-k}$ (see deflection sheet)
 $e = 0.05 \text{ inches}$
 $y = 1.65 \text{ inches}$ (for moments)

$$\Delta f_{cd} = 0.279 \text{ ksi}$$

$$\Delta f_{pCD} = E_p/E_{ci} * f_{cgp} * [\psi(t_r, t_i) - \psi(t_a, t_i)] * K_{df} + E_p/E_c * \Delta f_{cd} * \psi(t_r, t_a) * K_{df} \quad (5.9.5.4.2.6-1)$$

$$\Delta f_{pCD} = 2.36 \text{ ksi}$$

RELAXATION OF PRESTRESSING STRAND (per 5.9.5.4.3c)

$$\Delta f_{pR2} = \Delta f_{pR1}$$

$$\Delta f_{pR2} = 1.20 \text{ ksi}$$

SHRINKAGE OF DECK CONCRETE (per 5.9.5.4.3d)

$$\Delta f_{pSS} = E_p/E_c * \Delta f_{cdf} * K_{df} * [1 + 0.7\psi(t_r, t_a)]$$

$K_{df} = 0.929$
 $\psi(t_r, t_a) = 1.184$
 $\Delta f_{cdf} = \epsilon_{ddf} * A_d * E_{cd} / [1 + 0.7\psi(t_r, t_a)] * (1/A_c - e_{pc} * e_d / I_c)$

$$\epsilon_{ddf} = K_s * K_{hs} * K_f * K_{td} * 0.48 * 10^{-3} \quad (5.4.2.3.3-1)$$

$K_s = 1.000$
 $K_{hs} = 1.230$
 $K_f = 5 / (1 + f'_{ci})$ (5.4.2.3.2-4)
 $K_f = 0.833$

$$K_{td} = t_i / (61 - 4f'_{ci} + t_i) \quad (5.4.2.3.2-5)$$

$K_{td} = 0.423$

$$\epsilon_{ddf} = 2.08E-04$$

$$\Delta f_{cdf} = 0.00 \text{ ksi}$$

$$\Delta f_{pSS} = 0.00 \text{ ksi}$$

TOTAL LOSSES

$$\Delta f_{pLT} = \Delta f_{pSR} + \Delta f_{pCR} + \Delta f_{pR1} + \Delta f_{pSD} + \Delta f_{pCD} + \Delta f_{pR2} - \Delta f_{pSS}$$

$$\Delta f_{pLT} = \quad 28.50 \text{ ksi}$$

$$\Delta f_{pT} = \Delta f_{pES} + \Delta f_{pSR} + \Delta f_{pCR} + \Delta f_{pR1} + \Delta f_{pSD} + \Delta f_{pCD} + \Delta f_{pR2} - \Delta f_{pSS}$$

$$\Delta f_{pT} = \quad 39.52 \text{ ksi}$$

$$\text{LRFD Ed3 Losses} = \quad 42.21 \text{ ksi}$$

$$\Delta f_{pT} = \quad 42.21 \text{ ksi}$$

(JACKING) INITIAL FORCE =	1230.4 k	% LOSS =	20.85%
FINAL FORCE =	973.9 k		

By: Date
Chk'd: Date

Project no. .
Structure no. .

Project code (SA#)
Sheet 48 of

LRFD Ed. 3 PRESTRESS LOSSES (28 Strands)

Note: Prestress Losses are based on Non-Transformed Section Properties

ELASTIC SHORTENING (per 5.9.5.2.3a) (for usual design cases)

$$\Delta f_{pES} = (E_p/E_{ci}) f_{cgp}$$

$$E_p = 28500.00 \text{ ksi}$$

$$E_{ci} = 4069.64 \text{ ksi}$$

$$f_{cgp} = P/A + (P \cdot e/l) \cdot y + M_g \cdot y/l$$

$$P_t = 7 \cdot f_u \cdot A_{strand} = 1148.36 \text{ k (low relax strand)}$$

$$M_g = W_{self} \cdot (L^2) / 8 = 253.39 \text{ ft-k}$$

$$e = y = 0.05 \text{ inches}$$

$$f_{cgp} = 1.62 \text{ ksi}$$

$$\Delta f_{pES} = 11.37 \text{ ksi (gross method)}$$

$$\text{USE } \Delta f_{pES} = 11.02 \text{ ksi}$$

$$\text{per RLO: } 0.75$$

$$f_{ji} = 0.75 \cdot f_u = 202.50 \text{ ksi}$$

$$\text{initial relaxation} = 3.50\%$$

$$f_{jo} = 184.79 \text{ ksi}$$

$$\Delta f_{pES} = 10.62 \text{ ksi (RLO method)}$$

$$11.34 \text{ ksi (per Transformed Section Analysis)}$$

$$11.02 \text{ ksi (per C5.9.5.2.3a-1)}$$

SHRINKAGE (per 5.9.5.4.2)

$$\text{average annual humidity (H)} = 55.00\%$$

$$\Delta f_{pSR} = 17 \cdot H$$

$$\Delta f_{pSR} = 8.75 \text{ ksi}$$

CREEP (per 5.9.5.4.3)

$$\Delta f_{pCR} = 12.0 \cdot f_{cgp} - 7.0 \cdot \Delta f_{cdp}$$

$$\Delta f_{cdp} = M_{noncomposite} \cdot y / I + M_{composite} \cdot y / I_{comp}$$

Input following moments from Conspan, Approximation below or other calculations

$$M_{noncomposite} = 26.69 \text{ ft-k}$$

$$M_{simple} = 0.00 \text{ ft-k (see deflection sheet)}$$

$$M_{composite} = 9.88 \text{ ft-k}$$

$$M_{simple} = 456.26 \text{ ft-k (see deflection sheet)}$$

$$\Delta f_{cdp} = 0.00 \text{ ksi}$$

$$\Delta f_{pCR} = 19.46 \text{ ksi}$$

RELAXATION AT TRANSFER (per 5.9.5.4.4b)

$$\Delta f_{pR1} = \log(24.0 \cdot t) / K_r [f_{pj} / f_{py} - .55] \cdot f_{pj}$$

$$K_r = 40.00 \text{ (per LRFD, but PCI recommends 45)}$$

$$t = 0.75 \text{ days}$$

$$f_{pj} = .75 \cdot f_{pu} \text{ (per PCI)} = 202.50 \text{ ksi}$$

LRFD suggests .8 fpu (C5.9.5.4.4b)

$$f_{py} = .9 \cdot f_{pu} = 243.00 \text{ ksi}$$

$$\Delta f_{pR1} = 1.80 \text{ ksi}$$

RELAXATION AFTER TRANSFER (per 5.9.5.4.4c)

$$\Delta f_{pR2} = 30\% [20 \cdot \Delta f_{pES} - 2(\Delta f_{psr} + \Delta f_{pCR})]$$

$$\Delta f_{pR2} = 2.99 \text{ ksi}$$

TOTAL LOSSES

$$\Delta f_{pT} = \Delta f_{pES} + \Delta f_{psr} + \Delta f_{pCR} + \Delta f_{pR2}$$

$$\Delta f_{pT} = 42.21 \text{ ksi}$$

$$\text{(JACKING) INITIAL FORCE} = 1230.4 \text{ k}$$

$$\text{FINAL FORCE} = 973.9 \text{ k}$$

$$\% \text{ LOSS} = 20.85\%$$

By: _____ Date: _____
 Chk'd: _____ Date: _____

Project no. _____
 Structure no. _____

Project code (SA#) _____
 Sheet 49 of _____

STRENGTH CALCULATIONS - FULL DEPTH PANEL

Strength by Strain Compatibility

Assume depth of rectangular stress block (a) is less than cover
 => all strands in tension

	T=C		
	T=Aps*fps	prestress cover =	2 inches
	C=.85fc*b*a	fps=	270 ksi
Aps=	3.038 in ² (half of total)	fpy=.9*fps=	243 ksi
b=	96 inches	fc=	7.20 ksi
		β=	0.69 (5.7.2.2)

a=Aps*fps/.85fcb

@ Yield (fpy):

	a=	1.26 inches	
	c=a/β =	1.82 inches	Top strands are below neutral axis (tension)

@ Ultimate (fps):

	a=	1.40 inches	
	c=a/β =	2.02 inches	Top strands are below neutral axis (tension)

$$c = (Aps \cdot fps + As \cdot fs - A' \cdot s' \cdot fs) / (.85 \cdot fc \cdot \beta \cdot b + K \cdot Aps \cdot fps / dp) \quad (5.7.3.1.1-4)$$

K= 0.28 (Table C5.7.3.1.1-1)

assume As=A's=0

c= 1.84 inches

$$fps = fps(1 - K \cdot c / dp) \quad (5.7.3.1.1-1)$$

fps= 245.59 ksi

for As=A's=0 and b=bw,

$$Mn = Aps \cdot fps \cdot (dp - a/2) \quad (5.7.3.2.2-1)$$

Mn= 314.92 ft kip

εt= 0.00629 Tension Controlled (C5.7.2.1)

φ = 0.9

Mr = φ * Mn = 283.43 ft kip

Development Length & Transfer Length (5.11.4)
 $l_d \geq \kappa * (f_{ps} - 2/3 f_{pe}) * d_b$ (5.11.4.2-1)
 $f_{pe} = f_{jack} - \Delta f_{pT}$
 $f_{pe} = 160.29$ ksi
 $\kappa = 1.0$
 $l_d = 83.24$ inches
 $l_{transfer} = 60 * d_b = 36$ inches
 $f_{px} = f_{pe} * l_{px} / 60 * d_b$ (5.11.4.2-2)
 $f_{px} = f_{pe} + (l_{px} - 60 d_b) / (l_d - 60 d_b) * (f_{ps} - f_{pe})$ (5.11.4.2-3)
 $l_{px} = 46$ inches
 $f_{px} = 178.34$ ksi

for prestress only:

$A_{ps} * f_{ps} = .85 * f'_c * b * a$
 $a = 0.9222$ inches
 $T_{topstrand} = 39.38$ ksi
 $M_n = A_{ps} * f_{ps} * (d_p - a/2)$
 $M_n = 254.87$ ft kip
 assume compression control $\Rightarrow \phi = .75$
 $M_r = 191.16$ ft kip

for prestress + mild reinforcing:

$A_s * f_s + A_{ps} * f_{ps} = .85 * f'_c * b * a$
 Mild bar size = #6
 bar spacing = 8 inches
 $A_s = 5.28$ in²
 $a = 2.5250$ inches
 $T_{topstrand} = 0.00$ ksi
 $M_n = A_{ps} * f_{ps} * (d_p - a/2) + A_s * f_s * (d_p - a/2)$
 $M_n = 315.53$ ft kip
 $\epsilon_t = 0.00351$ Compression Controlled (C5.7.2.1)
 $\phi = 0.75$

Interaction Formula

$P_u / \phi P_n + M_u / \phi M_n \leq 1.0$
 $M_u \leq \phi M_n (1.0 - P_u / \phi P_n)$
 $\phi_{interaction} = (1.0 - P_u / \phi P_n)$
 $P_u = T = 7.38$ k/ft (Impact Tension)
 $\phi P_n = 168.12$ k/ft
 $\phi_{interaction} = 0.956$
 $M_r = \phi * \phi_{interaction} * M_n$
 $M_r = 226.26$ ft kip

Stress Checks @ Release

Compressive Stress

Compressive Limit = $.6 \cdot f_{ci}$ = 3 ksi

Blockouts

of blockouts = 4
blockout width = 10 inches
Ag = 723.375 in²
Anet = 403.375 in²

$f = P/A$

fconc-g = 1.61 ksi
fconcret = 2.88 ksi

Okay

Tension Stress

Tension Limit = $.24 \cdot \sqrt{f_{ci}}$ = -0.537 ksi

$f_{top} = P_t/A + (P_t \cdot e/I) \cdot y + M_g \cdot y/I$

$P_t = .7 \cdot f_u \cdot A_{strand} = 1148.36 \text{ k}$
 $M_g = W_{self} \cdot (L^2) / 8 = 253.39 \text{ ft-k}$
e = -0.05 inches
y = 4.05 inches

$f_{top} = 4.70 \text{ ksi}$

Okay

Stress Checks @ Service

Stress in Strand

Total Losses = 42.21 ksi

f_{pe} = 160.29 ksi
.8f_{py} = 194.4 ksi
f_{pe} <= .8f_{py}? Okay

(Table 5.9.3-1)

By: Date
Chk'd: Date

Project no.
Structure no.

Project code (SA#)
Sheet 52 of

Stress Checks @ Service (cont.)

Concrete Stress in Positive Moment Area (Interior Spans)

Mslab (+) = Mslab (-) = 3.336 ft kip/ft
 Mdc2 = 0 ft kip/ft
 Mdw (+) = Mdw (-) = 1.234 ft kip/ft
 MLL+ = 83.60 ft kip for 8 foot panel
 MLL- = 77.40 ft kip for 8 foot panel

Compression Stress

$$f_{top} = Pe/A + Mslab/Stop + (Mdc + Mdw + MLL)/Stopc$$

$f_{max} = .6 f_c = 4.32$ ksi transient loads (Table 5.9.4.2.1-1)

$f_{top} = 3.10$ ksi

$f_{top} \leq f_{max}$? **Okay**

$f_{max} = .45 f_c = 3.24$ ksi permanent loads (Table 5.9.4.2.1-1)

$f_{top} = 1.80$ ksi

$f_{top} \leq f_{max}$? **Okay**

$f_{max} = .40 f_c = 2.88$ ksi LL + 1/2DL (Table 5.9.4.2.1-1)

$f_{top} = 2.20$ ksi

$f_{top} \leq f_{max}$? **Okay**

Tension Stress

$$f_{bottom} = Pe/A + Mslab/Sbott + (Mdc + Mdw + MLL)/Sbott$$

$f_{bottom} = -0.138$ ksi

Tension Limit = $.19 \sqrt{f_c} = -0.510$ ksi (Table 5.9.4.2.2-1)

$f_{bottom} \leq f_{max}$? **Okay**

Concrete Stress in Negative Moment Area (Interior Spans)

Compression Stress

$$f_{bottom} = Pe/A + Mslab/Sbot + (Mdc + Mdw + MLL)/Sbotc$$

$f_{max} = .6 f_c = 4.32$ ksi transient loads (Table 5.9.4.2.1-1)

$f_{bottom} = 2.99$ ksi

$f_{bottom} \leq f_{max}$? **Okay**

$f_{max} = .45 f_c = 3.24$ ksi permanent loads (Table 5.9.4.2.1-1)

$f_{bottom} = 1.79$ ksi

$f_{top} \leq f_{max}$? **Okay**

$f_{max} = .40 f_c = 2.88$ ksi LL + 1/2DL (Table 5.9.4.2.1-1)

$f_{bottom} = 2.74$ ksi

$f_{bottom} \leq f_{max}$? **Okay**

Tension Stress

$$f_{top} = Pe/A + Mslab/Stop + (Mdc + Mdw + MLL)/Stop$$

$f_{top} = -0.068$ ksi

Tension Limit = $.19 \sqrt{f_c} = -0.510$ ksi (Table 5.9.4.2.2-1)

$f_{top} \leq f_{max}$? **Okay**

By: Date
 Chk'd: Date

Project no.
 Structure no.

Project code (SA#)
 Sheet 53 of

Concrete Stress in Negative Moment Area (Overhang)

Overhang Length =	9.01 ft	
Distance to Start of Precast Slab =	6.00	Inches
Support Girder Flange Width =	28.00	Inches
Distance to Barrier Center of Mass =	1.54	ft
width of barrier =	1.81	ft
Wt of Barrier =	0.485	k/ft
Asphalt Thickness =	3.00	inches
Asphalt Weight =	12.22	lb/sf/inch asphalt
Live Load =	1.00	k/lf (Input live load)
Mslab (-) =	3.39 ft kip/ft	moment at 9.33 inches from support
Mdc2 (barrier) (-) =	3.24 ft kip/ft	moment at 9.33 inches from support
Mdw (-) =	0.76 ft kip/ft	moment at 9.33 inches from support
MLL- =	5.42 ft kip/ft	moment at 9.33 inches from support

Compression Stress

$$f_{bottom} = Pe/A + Mslab/S_{bot} + (Mdc + Mdw + MLL)/S_{botc}$$

f _{max} = .6 f _c =	4.32 ksi	transient loads (DL+LL)	(Table 5.9.4.2.1-1)
f _{bottom} =	2.73 ksi		
f _{bottom} ≤ f _{max} ?	Okay		

f _{max} = .45 f _c =	3.24 ksi	permanent loads (DL)	(Table 5.9.4.2.1-1)
f _{bottom} =	2.05 ksi		
f _{top} ≤ f _{max} ?	Okay		
f _{max} = .40 f _c =	2.88 ksi	LL + 1/2DL	(Table 5.9.4.2.1-1)
f _{bottom} =	1.70 ksi		
f _{bottom} ≤ f _{max} ?	Okay		

Tension Stress

$$f_{top} = Pe/A + Mslab/S_{top} + (Mdc + Mdw + MLL)/S_{top}$$

f _{top} =	0.396 ksi	
Tension Limit = .19*sqrt(f _c) =	-0.510 ksi	(Table 5.9.4.2.2-1)
f _{top} ≤ f _{max} ?	Okay	

By: Date
 Chk'd: Date

Project no. .
 Structure no. .

Project code (SA#)
 Sheet 54 of

Design Computations

Strength Checks

Interior Spans

STRENGTH I

$$\begin{aligned} M_u &= 1.25DC + 1.5DW + 1.75(LL + IM) \\ M_{u\text{positive}} &= 231.05 \text{ ft kip} \\ M_{u\text{negative}} &= 217.48 \text{ ft kip} \\ M_r = \phi * M_n &= 283.43 \text{ ft kip} \end{aligned}$$

Okay

SERVICE I

$$\begin{aligned} M_u &= DC + DW + (LL + IM) \\ M_{u\text{positive}} &= 141.07 \text{ ft kip} \\ M_{u\text{negative}} &= 133.31 \text{ ft kip} \end{aligned}$$

Overhang

STRENGTH I

$$\begin{aligned} M_u &= 1.25DC + 1.5DW + 1.75(LL + IM) \\ M_{u\text{negative}} &= 170.30 \text{ ft kip} \end{aligned}$$

Development Length & Transfer Length (5.11.4)

$$\begin{aligned} l_d &= 83.24 \text{ inches} \\ l_{\text{transfer}} = 60 * d_b &= 36 \text{ inches} \\ \text{distance from face of barrier} &= 6.42 \text{ ft (distance is } > \text{ development length } \rightarrow \text{ Full Strength)} \\ l_{px} &= 92.79 \text{ inches This is greater than } l_d, \text{ use a smaller value} \\ f_{px} &= 245.59 \text{ ksi} \end{aligned}$$

for prestress only:

$$\begin{aligned} A_{ps} * f_{ps} &= .85 * f_c * b * a \\ a &= 1.2699 \text{ inches} \\ T_{\text{topstrand}} &= 29.24 \text{ ksi} \\ M_n &= A_{ps} * f_{ps} * (d_p - a/2) \\ M_n &= 314.92 \text{ ft kip} \\ \epsilon_t &= 0.01321 \text{ Tension Controlled} \\ \phi &= 0.9 \\ M_r &= 283.43 \text{ ft kip} \end{aligned} \quad (C5.7.2.1)$$

Okay

for prestress + mild reinforcing:

$$\begin{aligned} A_s * f_s + A_{ps} * f_{ps} &= .85 * f_c * b * a \\ \text{Mild bar size} &= \# 6 \quad f_y = 60 \text{ ksi} \\ \text{bar spacing} &= 8 \text{ inches} \\ A_s &= 5.28 \text{ in}^2 \\ a &= 3.4770 \text{ inches} \\ T_{\text{topstrand}} &= 0.00 \text{ ksi} \\ M_n &= A_{ps} * f_{ps} * (d_p - a/2) + A_s * f_s * (d_p - a/2) \\ M_n &= 348.91 \text{ ft kip} \\ \epsilon_t &= 0.00083 \text{ Compression Controlled} \\ \phi &= 0.75 \\ M_r = \phi * M_n &= 261.68 \text{ ft kip} \end{aligned} \quad (C5.7.2.1)$$

Okay

By: Date
 Chk'd: Date

Project no.
 Structure no.

Project code (SA#)
 Sheet 55 of

Design ComputationsSERVICE I

$$M_u = DC + DW + (LL + IM)$$

$$M_{unegative} = 113.34 \text{ ft kip}$$

EXTREME EVENT II (Case 1) Transverse & Longitudinal Force

$$T = 7.38 \text{ kip (see interaction calc. above)}$$

$$M_{cbase} = 23.3 \text{ ft kip/ft}$$

$$\text{distance from face of barrier} = 6.42 \text{ ft (distance is } > \text{ development length } \rightarrow \text{ Full Strength)}$$

$$M_{slab} (-) = 3.39 \text{ ft kip/ft}$$

$$M_{dc2} (\text{barrier}) (-) = 3.24 \text{ ft kip/ft}$$

$$M_{dw} (-) = 0.76 \text{ ft kip/ft}$$

$$M_{LL-} = 5.42 \text{ ft kip/ft}$$

$$M_u = 1.0DC + 1.0DW + 0.5(LL + IM) + M_{cbase}(\text{min})$$

$$M_{unegative} = 272.62 \text{ ft kip}$$

Development Length & Transfer Length

(5.11.4)

$$l_d = 83.24 \text{ inches}$$

$$l_{transfer} = 60 * d_b = 36 \text{ inches}$$

$$l_{px} = 92.79 \text{ inches} \quad \text{This is greater than } l_d, \text{ use a smaller value}$$

$$f_{px} = 245.59 \text{ ksi}$$

for prestress only:

$$A_{ps} * f_{ps} = .85 * f_c * b * a$$

$$a \sim = 1.2699 \text{ inches}$$

$$T_{topstrand} = 29.24 \text{ ksi}$$

$$M_n = A_{ps} * f_{ps} * (d_p - a/2)$$

$$M_n = 314.92 \text{ ft kip}$$

$$\epsilon_t = 0.01321 \text{ Tension Controlled}$$

(C5.7.2.1)

$$\phi = 0.9$$

$$\phi_{interaction} = 0.963$$

$$M_r = \phi * \phi_{interaction} * M_n$$

$$M_r = 273.06 \text{ ft kip}$$

Okay

for prestress + mild reinforcing:

$$A_s * f_s + A_{ps} * f_{ps} = .85 * f_c * b * a$$

$$\text{Mild bar size} = \# 6$$

$$f_y = 60 \text{ ksi}$$

$$\text{bar spacing} = 8 \text{ inches}$$

$$A_s = 5.28 \text{ in}^2$$

$$a \sim = 3.4770 \text{ inches}$$

$$T_{topstrand} = 0.00 \text{ ksi}$$

$$M_n = A_{ps} * f_{ps} * (d_p - a/2) + A_s * f_s * (d_p - a/2)$$

$$M_n = 348.91 \text{ ft kip}$$

$$\epsilon_t = 0.00083 \text{ Compression Controlled}$$

(C5.7.2.1)

$$\phi = 0.75$$

$$\phi_{interaction} = 0.956$$

$$M_r = \phi * \phi_{interaction} * M_n$$

$$M_r = 250.20 \text{ ft kip}$$

By: _____
 Chk'd: _____
 Date: _____

Project no. _____
 Structure no. _____

Project code (SA#) _____
 Sheet 56 of _____

EXTREME EVENT II (Case 1) Transverse & Longitudinal Force

distance from face of barrier = 0.00 ft (distance is < development length -> Partial Strength)

Mslab (-) = 0.16 ft kip/ft
Mdc2 (barrier) (-) = 0.13 ft kip/ft
Mdw (-) = 0.00 ft kip/ft
MLL- = 0.00 ft kip/ft

Mu=1.0DC+1.0DW+0.5(LL+IM)+Mcbase(min)
Munegative = 188.74 ft kip

Development Length & Transfer Length (5.11.4)

ld = 83.24 inches
ltransfer = 60*db = 36 inches
lpx = 15.71 inches
fpx = 69.94 ksi

for prestress only:

Aps*fps=.85*fc*b*a
a~ = 0.3616 inches
Ttopstrand = 24.00 ksi

Mn=Aps*fps*(dp-a/2)
Mn = 110.60 ft kip

εt = 0.06223 Tension Controlled (C5.7.2.1)
φ = 0.9

φinteraction = 0.963
Mr = φ*φinteraction*Mn
Mr = 95.90 ft kip

for prestress + mild reinforcing:

As*fs + Aps*fps=.85*fc*b*a
Mild bar size = # 6 fy = 60 ksi
bar spacing = 8 inches
As = 5.28 in^2
a~ = 0.9902 inches
Ttopstrand = 14.18 ksi

Mn=Aps*fps*(dp-a/2)+As*fs*(dp-a/2)
Mn = 234.07 ft kip

εt = 0.01873 Tension Controlled (C5.7.2.1)
φ = 0.9

φinteraction = 0.963
Mr = φ*φinteraction*Mn
Mr = 202.96 ft kip

Okay

Design Computations

EXTREME EVENT II (Case 1) Transverse & Longitudinal Force

distance from face of barrier = 1.67 ft (distance is < development length -> Partial Strength)

Mslab (-) = 0.61 ft kip/ft
 Mdc2 (barrier) (-) = 0.94 ft kip/ft
 Mdw (-) = 0.05 ft kip/ft
 MLL- = 0.67 ft kip/ft

Mu=1.0DC+1.0DW+0.5(LL+IM)+Mcbase(min)
 Munegative = 202.51 ft kip

Development Length & Transfer Length (5.11.4)

ld = 83.24 inches
 ltransfer = 60*db = 36 inches
 lpx = 35.75 inches
 fpx = 159.16 ksi

for prestress only:

Aps*fps=.85*fc*b*a
 a~ = 0.8230 inches
 Ttopstrand = 39.10 ksi
 Mn=Aps*fps*(dp-a/2)
 Mn = 231.79 ft kip
 εt = 0.02381 Tension Controlled (C5.7.2.1)
 φ = 0.9
 φinteraction = 0.963
 Mr = φ*φinteraction*Mn
 Mr = 200.98 ft kip

for prestress + mild reinforcing:

As*fs + Aps*fps=.85*fc*b*a
 Mild bar size = # 6 fy = 60 ksi
 bar spacing = 8 inches
 As = 5.28 in^2
 a~ = 2.2534 inches
 Ttopstrand = 0.00 ksi
 Mn=Aps*fps*(dp-a/2)+As*fs*(dp-a/2)
 Mn = 303.04 ft kip 118.75474
 εt = 0.00470 Compression Controlled (C5.7.2.1)
 φ = 0.75
 φinteraction = 0.956
 Mr = φ*φinteraction*Mn
 Mr = 217.30 ft kip

Areqd/Aprov ~ Mreqd/Mprov = 0.93

Design ComputationsEXTREME EVENT II (Case 1) Transverse & Longitudinal Force

distance from face of barrier = 1.75 ft (distance is < development length -> Partial Strength)

$$\begin{aligned} \text{Mslab (-)} &= 0.63 \text{ ft kip/ft} \\ \text{Mdc2 (barrier) (-)} &= 0.98 \text{ ft kip/ft} \\ \text{Mdw (-)} &= 0.06 \text{ ft kip/ft} \\ \text{MLL-} &= 0.75 \text{ ft kip/ft} \end{aligned}$$

$$\begin{aligned} \text{MU} &= 1.0\text{DC} + 1.0\text{DW} + 0.5(\text{LL} + \text{IM}) + \text{Mcbase}(\text{min}) \\ \text{MUnegative} &= 203.48 \text{ ft kip} \end{aligned}$$

Development Length & Transfer Length

(5.11.4)

$$\begin{aligned} l_d &= 83.24 \text{ inches} \\ l_{\text{transfer}} = 60 \cdot d_b &= 36 \text{ inches} \\ l_{px} &= 36.71 \text{ inches} \\ f_{px} &= 161.57 \text{ ksi} \end{aligned}$$

for prestress only:

$$A_{ps} \cdot f_{ps} = .85 \cdot f_c \cdot b \cdot a$$

$$\begin{aligned} a &= 0.8354 \text{ inches} \\ T_{\text{topstrand}} &= 39.20 \text{ ksi} \end{aligned}$$

$$M_n = A_{ps} \cdot f_{ps} \cdot (d_p - a/2)$$

$$M_n = 234.74 \text{ ft kip}$$

$$\epsilon_t = 0.02336 \text{ Tension Controlled}$$

(C5.7.2.1)

$$\phi = 0.9$$

$$\phi_{\text{interaction}} = 0.963$$

$$M_r = \phi \cdot \phi_{\text{interaction}} \cdot M_n$$

$$M_r = 203.54 \text{ ft kip}$$

Okay

for prestress + mild reinforcing:

$$A_s \cdot f_s + A_{ps} \cdot f_{ps} = .85 \cdot f_c \cdot b \cdot a$$

$$\text{Mild bar size} = \# 6$$

$$f_y = 60 \text{ ksi}$$

$$\text{bar spacing} = 8 \text{ inches}$$

$$A_s = 5.28 \text{ in}^2$$

$$a = 2.2874 \text{ inches}$$

$$T_{\text{topstrand}} = 0.00 \text{ ksi}$$

$$M_n = A_{ps} \cdot f_{ps} \cdot (d_p - a/2) + A_s \cdot f_s \cdot (d_p - a/2)$$

$$M_n = 304.67 \text{ ft kip}$$

$$\epsilon_t = 0.00453 \text{ Compression Controlled}$$

(C5.7.2.1)

$$\phi = 0.75$$

$$\phi_{\text{interaction}} = 0.956$$

$$M_r = \phi \cdot \phi_{\text{interaction}} \cdot M_n$$

$$M_r = 218.47 \text{ ft kip}$$

Okay

By: _____
Date: _____

Project no. _____
Structure no. _____

Project code (SA#) _____
Sheet 59 of _____

Design Computations

EXTREME EVENT II (Case 2) Vertical Force

M_{impactvertical} = 7.03 ft kip/ft

distance from face of barrier = 6.42 ft (distance is > development length -> Full Strength)

M_{slab (-)} = 3.39 ft kip/ft
 M_{dc2 (barrier) (-)} = 3.24 ft kip/ft
 M_{dw (-)} = 0.76 ft kip/ft
 M_{LL-} = 5.42 ft kip/ft

M_U = 1.0DC + 1.0DW + 0.5(LL + IM) + M_{impactvertical}
 M_{unegative} = 142.46 ft kip

Development Length & Transfer Length (5.11.4)

l_d = 83.24 inches
 l_{transfer} = 60 * d_b = 36 inches
 l_{px} = 92.79 inches This is greater than l_d, use a smaller value
 f_{px} = 245.59 ksi

for prestress only:

A_{ps} * f_{ps} = .85 * f_c * b * a
 a~ = 1.2699 inches
 T_{topstrand} = 29.24 ksi
 M_n = A_{ps} * f_{ps} * (d_p - a/2)
 M_n = 314.92 ft kip
 ε_t = 0.01321 Tension Controlled (C5.7.2.1)
 φ = 0.9
 φ_{interaction} = 0.963
 M_r = φ * φ_{interaction} * M_n
 M_r = 273.06 ft kip

Okay

for prestress + mild reinforcing:

A_s * f_s + A_{ps} * f_{ps} = .85 * f_c * b * a
 Mild bar size = # 6 fy = 60 ksi
 bar spacing = 8 inches
 A_s = 5.28 in²
 a~ = 3.4770 inches
 T_{topstrand} = 0.00 ksi
 M_n = A_{ps} * f_{ps} * (d_p - a/2) + A_s * f_s * (d_p - a/2)
 M_n = 348.91 ft kip
 ε_t = 0.00083 Compression Controlled (C5.7.2.1)
 φ = 0.75
 φ_{interaction} = 0.956
 M_r = φ * φ_{interaction} * M_n
 M_r = 250.20 ft kip

Okay

By: _____ Date _____
 Chk'd: _____ Date _____

Project no. _____
 Structure no. _____

Project code (SA#) _____
 Sheet 60 of _____

Design Computations

Concrete Stress in Negative Moment Area (Interior Overhang)

Overhang Length = 4.77 ft
 Distance to Start of Precast Slab = 0.00 Inches
 Support Girder Flange Width = 28.00 Inches
 Distance to Barrier Center of Mass = 0.00 ft
 width of barrier = 0.00 ft
 Wt of Barrier = 0.000 k/ft
 Asphalt Thickness = 3.00 inches
 Asphalt Weight = 12.22 lb/sf/inch asphalt
 Live Load = 4.16 k/lf (Input live load)

Handwritten:
 $3.91 = \frac{50k \times 1.33}{2/8}$
 $\frac{50k \times 1.33}{2} / 8'$

Mslab (-) = 0.80 ft kip/ft moment at 9.33 inches from support
 Mdc2 (barrier) (-) = 0.00 ft kip/ft moment at 9.33 inches from support
 Mdw (-) = 0.29 ft kip/ft moment at 9.33 inches from support
 MLL- = 12.46 ft kip/ft moment at 9.33 inches from support

Compression Stress

$f_{bottom} = Pe/A + Mslab/S_{bot} + (Mdc + Mdw + MLL)/S_{botc}$

$f_{max} = .6 f_c = 4.32$ ksi transient loads (DL+LL) (Table 5.9.4.2.1-1)
 $f_{bottom} = 3.00$ ksi
 $f_{bottom} \leq f_{max}$? **Okay**

$f_{max} = .45 f_c = 3.24$ ksi permanent loads (DL) (Table 5.9.4.2.1-1)
 $f_{bottom} = 1.45$ ksi
 $f_{top} \leq f_{max}$? **Okay**

$f_{max} = .40 f_c = 2.88$ ksi LL + 1/2DL (Table 5.9.4.2.1-1)
 $f_{bottom} = 2.28$ ksi
 $f_{bottom} \leq f_{max}$? **Okay**

Tension Stress

$f_{top} = Pe/A + Mslab/S_{top} + (Mdc + Mdw + MLL)/S_{top}$

$f_{top} = -0.003$ ksi
 Tension Limit = $.19 \times \sqrt{f_c} = -0.510$ ksi (Table 5.9.4.2.2-1)
 $f_{top} \leq f_{max}$? **Okay**

Design Computations

Strength Checks

Interior Overhang

STRENGTH I

$$M_u = 1.25DC + 1.5DW + 1.75(LL + IM)$$

$$M_{unegative} = 229.47 \text{ ft kip}$$

Development Length & Transfer Length (5.11.4)

$$l_d = 83.24 \text{ inches}$$

$$l_{transfer} = 60 * d_b = 36 \text{ inches}$$

distance from edge of slab = 4.00 ft (distance is < development length -> Partial Strength)

$$l_{px} = 47.96 \text{ inches}$$

$$f_{px} = 181.89 \text{ ksi}$$

for prestress only:

$$A_{ps} * f_{ps} = .85 * f_c * b * a$$

$$a \sim = 0.9405 \text{ inches}$$

$$T_{topstrand} = 39.29 \text{ ksi}$$

$$M_n = A_{ps} * f_{ps} * (d_p - a/2)$$

$$M_n = 259.02 \text{ ft kip}$$

$$\epsilon_t = 0.02005 \text{ Tension Controlled} \quad (C5.7.2.1)$$

$$\phi = 0.9$$

$$M_r = 233.12 \text{ ft kip}$$

Okay

for prestress + mild reinforcing:

$$A_s * f_s + A_{ps} * f_{ps} = .85 * f_c * b * a$$

Mild bar size = # 4

$$\text{bar spacing} = 24 \text{ inches} \quad f_y = 60 \text{ ksi}$$

$$A_s = 0.8 \text{ in}^2$$

$$a \sim = 1.1882 \text{ inches}$$

$$T_{topstrand} = 26.43 \text{ ksi}$$

$$M_n = A_{ps} * f_{ps} * (d_p - a/2) + A_s * f_s * (d_p - a/2)$$

$$M_n = 267.15 \text{ ft kip}$$

$$\epsilon_t = 0.01456 \text{ Tension Controlled} \quad (C5.7.2.1)$$

$$\phi = 0.9$$

$$M_r = \phi * M_n = 240.44 \text{ ft kip}$$

Okay

SERVICE I

$$M_u = DC + DW + (LL + IM)$$

$$M_{unegative} = 133.29 \text{ ft kip}$$

By: _____ Date _____
 Chk'd: _____ Date _____

Project no. _____
 Structure no. _____

Project code (SA#) _____
 Sheet 62 of _____

Strength per Power Stress-Strain Formula Method

$f_{pe} = 160.29$ ksi strand depth = 2.3 inches

$A_{ps1} * f_{ps1} + A_{ps2} * f_{ps2} = .85 * f_c * b * a$

Assume: Note: Iterate Until Stresses Match
(bottom) $f_{ps1} = 229.1$ ksi Stress Match Okay
(top) $f_{ps2} = 144.7$ ksi Stress Match Okay

$a = 1.93288$
 $c = a/\beta = 2.80127$

$f_{ps} = \epsilon_p * [887 + 27613 / \{1 + (112.4 * \epsilon_p)^{7.36}\}^{1/7.36}]$ (Devalapura & Tadros)

Bottom Layer:

$\epsilon_p = .003 * (d_p - c) / c + (f_{pe} / E_{ps})$

$\epsilon_p = 0.00873$
 $f_{ps} = 229.13$ ksi

Top Layer:

$\epsilon_p = .003 * (d_p - c) / c + (f_{pe} / E_{ps})$

$\epsilon_p = 0.00509$
 $f_{ps} = 144.678$ ksi

$M_n = A_{ps} * f_{ps} * (d_p - a/2)$
 $M_n = 274.58$ ft kip

$\epsilon_t = 0.00873$ Tension Controlled
 $\phi = 0.9$

$M_r = \phi * M_n = 247.13$ ft kip

By: Date
Chk'd: Date

Project no. .
Structure no. .

Project code (SA#)
Sheet 63 of

COLORADO DEPARTMENT OF TRANSPORTATION
DESIGN COMPUTATIONS (Grid)

@ 1' from edge

$$M_u \approx (25k)(1.33)(1') \cdot 1.75 \approx 58.2 \text{ ft k}$$

$$M_r = 64.31 \text{ ft kip}$$

$$M_u < M_r \quad \Rightarrow \text{Key}$$

By: _____	Date _____	Project no. _____	Project code (SA#): _____
Chk'd: _____	Date _____	Structure no. _____	Sheet <u>64</u> of _____

Development Length & Transfer Length

(5.11.4)

$$l_d \geq \kappa * (f_{ps} - 2/3 f_{pe}) * d_b$$

(5.11.4.2-1)

$$f_{pe} = f_{jack} - \Delta f_{pT}$$

$$f_{pe} = 160.34 \text{ ksi}$$

$$\kappa = 1.0$$

$$l_d = 83.22 \text{ inches}$$

$$l_{transfer} = 60 * d_b = 36 \text{ inches}$$

$$f_{px} = f_{pe} * l_{px} / 60 * d_b$$

(5.11.4.2-2)

$$f_{px} = f_{pe} + (l_{px} - 60 d_b) / (l_d - 60 d_b) * (f_{ps} - f_{pe})$$

(5.11.4.2-3)

$$l_{px} = 12 \text{ inches}$$

$$f_{px} = 53.45 \text{ ksi}$$

for prestress only:

$$A_{ps} * f_{ps} = .85 * f'_c * b * a$$

$$a \sim = 0.2764 \text{ inches}$$

$$T_{topstrand} = 19.16 \text{ ksi}$$

$$M_n = A_{ps} * f_{ps} * (d_p - a/2)$$

$$M_n = 85.74 \text{ ft kip}$$

assume compression control => $\phi = .75$

$$M_r = 64.31 \text{ ft kip}$$

for prestress + mild reinforcing:

$$A_s * f_s + A_{ps} * f_{ps} = .85 * f'_c * b * a$$

$$\text{Mild bar size} = \# 5$$

$$f_y = 60 \text{ ksi}$$

$$\text{bar spacing} = 24 \text{ inches}$$

$$A_s = 1.24 \text{ in}^2$$

$$a \sim = 0.3892 \text{ inches}$$

$$T_{topstrand} = 18.07 \text{ ksi}$$

$$M_n = A_{ps} * f_{ps} * (d_p - a/2) + A_s * f_s * (d_p - a/2)$$

$$M_n = 114.46 \text{ ft kip}$$

$$\epsilon_t = 0.05738 \text{ Tension Controlled}$$

(C5.7.2.1)

$$\phi = 0.9$$

Interaction Formula

$$P_u / \phi P_n + M_u / \phi M_n \leq 1.0$$

$$M_u \leq \phi M_n (1.0 - P_u / \phi P_n)$$

$$\phi_{interaction} = (1.0 - P_u / \phi P_n)$$

$$P_u = T = 7.38 \text{ k/ft} \quad (\text{Impact Tension})$$

$$\phi P_n = 173.56 \text{ k/ft}$$

$$\phi_{interaction} = 0.957$$

$$M_r = \phi * \phi_{interaction} * M_n$$

$$M_r = 98.63 \text{ ft kip}$$

By: _____ Date _____
 Chk'd: _____ Date _____

Project no. _____
 Structure no. _____

Project code (SA#) _____
 Sheet 65 of _____

Strength per Power Stress-Strain Formula Method

fpe = 160.29 ksi strand depth = 2.3 inches

$$A_{ps1} * f_{ps1} + A_{ps2} * f_{ps2} = .85 * f_c * b * a$$

Assume:

(bottom) $f_{ps1} = 229.1$ ksi

Note: Iterate Until Stresses Match
Stress Match Okay

(top) $f_{ps2} = 144.7$ ksi

Stress Match Okay

$$a = 1.93288$$

$$c = a/\beta = 2.80127$$

$$f_{ps} = \epsilon_p * [887 + 27613 / \{1 + (112.4 * \epsilon_p)^{7.36}\}^{1/7.36}]$$

(Devalapura & Tadros)

Bottom Layer:

$$\epsilon_p = .003 * (dp - c) / c + (f_{pe} / E_{ps})$$

$$\epsilon_p = 0.00873$$

$$f_{ps} = 229.13 \text{ ksi}$$

Top Layer:

$$\epsilon_p = .003 * (dp - c) / c + (f_{pe} / E_{ps})$$

$$\epsilon_p = 0.00509$$

$$f_{ps} = 144.678 \text{ ksi}$$

$$M_n = A_{ps} * f_{ps} (dp - a/2)$$

$$M_n = 274.58 \text{ ft kip}$$

$$\epsilon_t = 0.00873 \text{ Tension Controlled}$$

$$\phi = 0.9$$

$$M_r = \phi * M_n = 247.13 \text{ ft kip}$$

By: Date
Chk'd: Date

Project no.
Structure no.

Project code (SA#)
Sheet 66 of

SHEAR STRENGTH

$$v_u = \frac{|V_u - \phi V_p|}{\phi b_v d_v} \quad (5.8.2.9-1)$$

$$\phi = .9 \text{ for normal weight concrete} \quad (5.5.4.2.1)$$

$$b_v \approx 96'' \text{ (no transverse ducts)}$$

$$d_v \geq .9 d_c$$

$$d_c = \frac{A_{ps} f_{ps} d_p + A_s f_y d_s}{A_{ps} f_{ps} + A_s f_y} \quad (5.8.2.9-2)$$

$$d_c = \frac{(3.038)(245.59)(8'-2''-.3) + (5.28 \text{ in}^2)(60)(8'-2''-.75 \frac{1}{2})}{3.038(245.59) + 5.28(60)}$$

$$d_c = 5.68$$

$$d_v \geq .9 d_c = .9(5.68) = 5.11'' \leftarrow$$


$$d_v \geq .72 h = .72(8) = 5.76'' \leftarrow \text{controls}$$

$$d_v = \frac{M_n}{A_s f_y + A_{ps} f_{ps}} \quad (5.8.2.9-1)$$


$$d_v = \frac{314.92(12)}{(5.28)(60) + 3.038(245.59)}$$

$$d_v = 3.56'' \leftarrow$$

$$V_p = 0 \text{ (zero)}$$



SHEAR STRENGTH



$$\text{Span} = \frac{17.927'}{\sin(\text{skew})} = \frac{17.927'}{\sin 56} = 21.62'$$

$$V_u = 25k + \frac{(25)(21.62 - 6')}{21.62} + \frac{25(21.62 - 12')}{21.62} + \frac{25(21.62 - 18')}{21.62}$$

$$V \approx 58.37 k$$

$$V_u = 1.75(58.37)(1.25) \approx 127.69$$

$$v_u = \frac{(127.69 k - 0)}{.9(96)(5.76'')} \quad (5.8.2.9-1)$$

$$v_u \approx .257 \text{ ksi}$$

$$.125 f'_c = .125(7.2) \approx .9 \text{ ksi}$$

$$v_u \leq .125 f'_c$$

$$S_{\max} = .8 d_v = 24.0 \text{ in} \quad (5.8.2.7-1)$$

$$S_{\max} = .8(5.76) = 4.608 \text{ in}$$

$$A_v \geq .0316 \sqrt{f'_c} \frac{b_u S}{f_y} \quad (5.8.2.5-1)$$

$$A_v \geq .0316 \sqrt{7.2} \frac{(96)(4'')}{60}$$

$$A_v \geq .5427 \text{ in}^2$$

$$\#5 \Rightarrow .31 \text{ in}^2 \quad + \quad +$$

$$A = (2)(.31) = .62 \text{ in}^2$$

Shear Strength

$$V_n = V_c + V_s + V_p \quad (5.8.3.3-1)$$

$$V_n = .25 f'_c b_v d_v + V_p \quad (5.8.3.3-2)$$

$$V_c = .0316 \beta \sqrt{f'_c} b_v d_v \quad (5.8.3.3-3)$$

$$\beta = \frac{4.8}{(1 + 750 E_s)} \quad (5.8.3.4.2-1)$$

$$E_s = \frac{\left(\left| \frac{M_u}{d_v} \right| + .5 N_u + |V_u - V_p| - A_{ps} f_{po} \right)}{E_s A_s + E_p A_{ps}} \quad (5.8.3.4.2-4)$$

$M_u \approx 169.31 \text{ ft-k}$ (neg moment @ girder support)

$N_u = 0$

$V_u \approx 127.69$

$V_p = 0$

$f_{po} \approx .7 f_{pu} = .7(270) = 189 \text{ ksi}$

$A_s = 5.28 \text{ in}^2$

$A_{ps} = 3.038 \text{ in}^2$

$$E_s = \frac{\frac{(169.31)(12)}{5.76} + 0 + 127.69\text{k} - 3.038(189\text{ksi})}{28500(3.038)}$$

$E_s \approx -.001$

$$\beta = \frac{4.8}{1 + 750(-.001)} = 25.56$$

SHEAR STRENGTH

$$V_c = .0316 (25.56) \sqrt{7.2} (96) (5.76) \quad (5.8.3.3-3)$$

$$V_c = \underline{1198.3 \text{ Kip}} \quad \leftarrow$$

$$V_u > .5 \phi (V_c + V_p) \quad (5.8.2.4-1)$$

$$.5 (.9) (1198.3 + 0)$$

$$= 539.2 \text{ K}$$

$$V_u = 127.69 \text{ K}$$

$$V_u \leq .5 \phi (V_c + V_p)$$

Requirement doesn't
apply to slabs

Transverse Reinforcement NOT REQUIRED \leftarrow

$$V_u < V_c$$

✓

OKay

DESIGN COMPUTATIONS (Grid) SHEAR STRENGTH

with less than Minimum Transverse Reinforcement

$$s_{xe} = s_x \left(\frac{1.38}{d_y + .63} \right) \quad (B5.2-4)$$

$$d_y \approx 5''$$

$$s_x = 8'' - 2'' - .3 - 2'' - .3 \approx 3.4''$$

$$s_{xe} = 3.4 \left(\frac{1.38}{.5 + .63} \right) \approx 4.15'' \leq 5''$$

$$\beta \approx 26^\circ$$

(Table B5.2-2)

$$E_x = \frac{169.31(12) + 0 + .5(27.69) \cot(26) - 3.038(189)}{5.76}$$

$$2(28500(3.038) + 96(4'')4883.57)$$

$$E_x \approx -.000023 \quad .023 \times \frac{1}{1000}$$

$$\beta_{min} \approx 5.15 \quad \text{avg} \approx 5.35$$

$$\beta_{max} = 5.56$$

$$V_c \approx .0316(5.35) \sqrt{7.2}(96) 5.76$$

$$V_c = 250.84 \text{ K}$$

(5.8.2.4-1)

$$V_u \geq .5 \phi (V_c + V_p) = (.5)(.9)(250.84) \approx 112.88 \text{ K}$$

$$V_u \approx 127.69 \text{ K}$$


$$V_u \leq .5 \phi (V_c + V_p) \quad \text{requirement doesn't apply to slabs}$$

$$V_u < V_c \quad \checkmark \quad \text{okay}$$

By: Date	Project no.	Project code (SA#):
Chk'd: Date	Structure no.	Sheet 71 of

SHEAR STRENGTH

PUNCHING SHEAR



$$V_n = \left(.063 + \frac{.126}{B_c} \right) \sqrt{f'_c} b_o d_v \leq .126 \sqrt{f'_c} b_o d_v \quad (5.13.3.6.3-1)$$

$$B_c = \frac{20''}{10''} = 2$$

$$V_n = .126 \sqrt{7.2} (60'') 5.76''$$

$$V_n \approx 116.8 \text{ Kip}$$

$$V_r = .9 V_n = 105.2 \text{ K}$$

$$V_u = (25 \text{ K})(1.75) = 43.75 \text{ K} < V_r \quad \checkmark \text{ okay}$$

distribution steel - deck panels

tension in concrete \approx 68 psi (negative moment region)
 138 psi (positive moment region)

$$S = \frac{700 Y_e}{\beta_s f_{ss}} - 2 d_c \quad (5.7.3.4-1)$$

$$\beta_s = 1 + \frac{d_c}{.7(h-d_c)} = 1 + \frac{2}{.7(8-2)} \approx 1.476$$

$$d_c = 2''$$

$$h = 8''$$

assume $Y_e = .75$ (Class 2 exposure \Rightarrow concern for corrosion)

$$f_{ss} \approx n f_c = \frac{28500}{4.88357} \quad (138 \text{ ksi}) \approx .81 \text{ ksi}$$

$$S = \frac{700(.75)}{(1.476)(.81)} - 2(2)$$

$$S = 435''$$

prestressing & posttensioning
 reduces need for distribution steel

for 60 ksi steel @ yield

$$S = \frac{700(.75)}{1.476(.60)} - 2(2) = 1.93''$$

COLORADO DEPARTMENT OF TRANSPORTATION
DESIGN COMPUTATIONS (Grid)

Mild steel Spacing

$$S \leq \frac{700 Y_e}{\beta_s f_{ss}} - 2 d_c \quad (5.7.3.4-1)$$

$$\beta_s = 1 + \frac{d_c}{.7(h-d_c)} = 1 + \frac{2}{.7(8-1.6875)} = 1.453$$

$$Y_e = .75$$

$$d_c = 1.375'' + .65 \frac{1}{2} = 1.6875''$$

$$f_{ss} \approx .130 \text{ ksi} \quad (\text{deck stress @ negative moment region})$$

$$h = 8''$$

$$S = \frac{700 (.75)}{(1.453)(.130 \text{ ksi})} - 2(2) = 2.775 \text{ in}$$

By: _____	Date _____	Project no. _____	Project code (SA#): _____
Chk'd: _____	Date _____	Structure no. _____	Sheet <u>74</u> of _____

COLORADO DEPARTMENT OF TRANSPORTATION
DESIGN COMPUTATIONS (Grid)

#6 development length (extra steel for impact loads)

$$f'_c = 7.2 \text{ ksi}$$

$$l_{db} = .4 d_b f_y = 18''$$

epoxy

$$l_n = (1.2)(18'') = 21.6''$$

$$M_u = 202.5$$

$$M_r \text{ prestress} \approx .75(184.3) \approx 138.2 \text{ ft k}$$

$$M_r \text{ req'd steel} = 202.5 - 138.2 \approx 64.3 \text{ ft k}$$

$$M_r \text{ provided} = .75(118.7) \approx 89$$

$$\frac{A_{reqd}}{A_{provided}} \approx \frac{M_{reqd}}{M_{provided}} = \frac{64.3}{89} \approx .72$$

$$l_d = 15.6'' \text{ min}$$

By: _____	Date _____	Project no. _____	Project code (SA#): _____
Chk'd: _____	Date _____	Structure no. _____	Sheet 75 of _____

PRETENSIONED ANCHORAGE ZONES

$$P_r = f_s A_s$$

(5.10.10.1-1)

$$f_{s, max} = 20 \text{ ksi}$$

> #3 @ 6" per 5.10.10.2

$$h = 96''$$

$$h/4 = 24 \text{ in}$$

$$P_r > .04 (.75) P_u A_{ps}$$

per 5.10.10.1

Use 1 side

$$P_r > .04 (.75) (270) 14 \text{ strand} \left(\frac{.217 \text{ in}^2}{\text{strand}} \right)$$

5.10.10.1

$$P_r > 24.61 \text{ k}$$

$$A_{s, min} = \frac{7.23 \text{ k}}{20 \text{ ksi}} = 1.23 \text{ in}^2 \text{ in } h/4 (24'')$$

$$\text{Spacing} \leq 6''$$

$$\#5 = .31 \text{ in}^2$$

use 4-#5 @ 6"

$$A_s = 1.24 \text{ in}^2$$



spiral not needed but wouldn't hurt

DECK DESIGN - CLOSURE POUR

FROM SAP 2000


$$M_{\text{Live}} = \begin{matrix} 20.76 \text{ ft-k (min.)} & \dots & 70.28 \text{ ft-k (max.)} \\ 32.1 \text{ ft-k (min.)} & & 51.42 \text{ ft-k (max.)} \end{matrix}$$

can neglect this for CIP

continuous slab

$$M_{\text{DEAD}} \approx \begin{matrix} 3.98 \text{ ft-k for } 8' \text{ slab} \approx .5 \text{ ft-k/ft} \\ 10.62 \text{ ft-k for } 8' \text{ slab} \approx 1.33 \text{ ft-k/ft} \end{matrix}$$

$$M_{\text{DW}} \approx .2 \text{ ft-k/ft (min.)} \quad .51 \text{ ft-k/ft (max)}$$



Per Table 4.6.2.1.3-1

$$\text{Strip Width} \approx \begin{matrix} 26 + 6.6S & +M \\ 48 + 3.0S & -M \end{matrix}$$

$$S = 17.93'$$

$$\begin{aligned} \text{strip width} &= 26 + 6.6(17.93') \\ &= 144.34'' \approx 12.028' \end{aligned}$$

By: _____	Date _____	Project no. _____	Project code (SA#): _____
Chk'd: _____	Date _____	Structure no. _____	Sheet <u>77</u> of _____

COLORADO DEPARTMENT OF TRANSPORTATION
DESIGN COMPUTATIONS (Grid)

Maximum @ closure pour

$$M_u = 1.25 \text{ Dead} + 1.75 \text{ Live} + 1.5 \text{ DW}$$
$$= \cancel{0} + 1.75 \left(\frac{70.28}{12.028} \right) + 1.5 (.51)$$

$$M_u \approx 10.99 \text{ ft k/ft} \quad (\text{max})$$

Minimum @ closure pour

$$M_u = \cancel{1.25} (.5) + 1.75 \left(\frac{20.76}{12.028} \right) + 1.5 (.2)$$

$$M_u \approx 3.32 \text{ ft k/ft} \quad (\text{min})$$

$$\text{Average} \approx 7.16 \text{ ft k/ft}$$

space for 12 bars in 8' slab

$$\text{average spacing} \approx 8''$$

By: Date	Project no.	Project code (SA#):
Chk'd: Date	Structure no.	Sheet <u>78</u> of <u> </u>

Design Computations

REINFORCING DESIGN

GIVEN:

$f_y = 60.00$ ksi
 $f_c = 4.50$ ksi
 COVER = 2.00 inches
 $\Phi_{flexure} = 0.90$
 Beam Thickness (t_s) = 8.00 inches
 $b = 12.00$ inches
 bar diameter = 0.625 inches

CLOSURE POUR

LOAD TYPE	M _{hTOT}
	ft-K
M _h (UNFACTORED)	6.35
STRENGTH I	10.99
SERVICE I	6.35

A _{Sreq'd}
in ²
0.26
0.45
0.26

#5

$d_s = 5.69$ inches
 per 5.10.8.2 A_{Stemp} = 0.14 sq inches

Use # 5 at top face min. spacing = 8.21 inches
 use spacing = 8.00 inches
 $A_s = 0.465$ sq. inches

compressive steel:

Use # 5 at bottom face
 $A_s' = 0.00$ sq. inches

$M_n = 12.52$ ft-K
 $M_r = 11.27$ ft-K

Reinforcing is okay

Maximum Reinforcement per 5.7.3.3.1-1 (Ductility Check)

$c = 0.74$ inches
 $d_e = d_s = 5.69$ inches (for no prestressing)
 $c/d_e = 0.13$

okay - member is not overreinforced

Minimum Reinforcement per 5.7.3.3.2

$1.2 * M_{cracking} = 6.52$ ft-K <--- Test 1
 $1.33 M_{hTOT} (max.) = 14.62$ ft-K <--- Test 2

Minimum Reinforcing is provided

Transverse Reinforcement per 9.7.3.2

Percentage of main reinforcement, $220 / \sqrt{S} \leq 67\%$

Girder Spacing = 10.94 ft
 Flange Width = 43 inches
 Flange Overhang = 18 inches
 Effective Length S = 8.86 ft
 $220 / \sqrt{S} = 73.92\%$ Use 67 % of required main reinforcement
 Required $A_s = 0.31$ sq inches
 Use # 4 transverse reinforcement
 min. spacing = 7.70 inches

By: Date
 Chk'd: Date

Project no.
 Structure no.

Project code (SA#)
 Sheet of 79

Design Computations

REINFORCING DESIGN

GIVEN:

$f_y = 60.00$ ksi
 $f'_c = 4.50$ ksi
 COVER = 2.00 inches
 $\Phi_{flexure} = 0.90$
 Beam Thickness (t_s) = 8.00 inches
 $b = 12.00$ inches
 bar diameter = 0.750 inches

CLOSURE POUR

LOAD TYPE	M _{hTOT} ft-K
M _h (UNFACTORED)	6.35
STRENGTH I	10.99
SERVICE I	6.35

AS _{req'd} in ²
0.26
0.46
0.26

#6

$d_s = 5.63$ inches
 per 5.10.8.2 A_{Temp} = 0.14 sq inches

Use # 6 at top face min. spacing = 11.51 inches
 use spacing = 8.00 inches
 $A_s = 0.660$ sq. inches

compressive steel:

Use # 5 at bottom face
 $A_s' = 0.00$ sq. inches

$M_n = 17.14$ ft-K
 $M_r = 15.43$ ft-K

Reinforcing is okay

Maximum Reinforcement per 5.7.3.3.1-1 (Ductility Check)

$c = 1.05$ inches
 $d_e = d_s = 5.63$ inches (for no prestressing)
 $c/d_e = 0.19$

okay - member is not overreinforced

Minimum Reinforcement per 5.7.3.3.2

$1.2 * M_{cracking} = 6.52$ ft-K <--- Test 1
 $1.33 M_{hTOT} (max.) = 14.62$ ft-K <--- Test 2

Minimum Reinforcing is provided

Transverse Reinforcement per 9.7.3.2

Percentage of main reinforcement, $220 / \sqrt{S} \leq 67\%$

Girder Spacing = 10.94 ft
 Flange Width = 43 inches
 Flange Overhang = 18 inches
 Effective Length S = 8.86 ft
 $220 / \sqrt{S} = 73.92\%$ Use 67 % of required main reinforcement
 Required $A_s = 0.44$ sq inches
 Use # 4 transverse reinforcement
 min. spacing = 5.42 inches

Design Computations

REINFORCING DESIGN

GIVEN:

$f_y = 60.00$ ksi
 $f'_c = 4.50$ ksi
 COVER = 2.00 inches
 $\Phi_{flexure} = 0.90$
 Beam Thickness (t_s) = 8.00 inches
 $b = 12.00$ inches
 bar diameter = 0.875 inches

CLOSURE POUR

LOAD TYPE	M_{hTOT} ft-K
M_h (UNFACTORED)	6.35
STRENGTH I	10.99
SERVICE I	6.35

$A_{Sreq'd}$ in ²
0.26
0.46
0.26

#7

$d_s = 5.56$ inches
 per 5.10.8.2 $A_{Stemp} = 0.14$ sq inches

Use #7 at top face min. spacing = 15.50 inches
 use spacing = 8.00 inches
 $A_s = 0.900$ sq. inches

compressive steel:

Use #5 at bottom face
 $A_{s'} = 0.00$ sq. inches

$M_n = 22.38$ ft-K
 $M_r = 20.15$ ft-K

Reinforcing is okay

Maximum Reinforcement per 5.7.3.3.1-1 (Ductility Check)

$c = 1.43$ inches
 $d_e = d_s = 5.56$ inches (for no prestressing)
 $c/d_e = 0.26$

okay - member is not overreinforced

Minimum Reinforcement per 5.7.3.3.2

$1.2 \cdot M_{cracking} = 6.52$ ft-K <--- Test 1
 $1.33 M_{hTOT} (max.) = 14.62$ ft-K <--- Test 2

Minimum Reinforcing is provided

Transverse Reinforcement per 9.7.3.2

Percentage of main reinforcement, $220 / \sqrt{S} \leq 67\%$

Girder Spacing = 10.94 ft
 Flange Width = 43 inches
 Flange Overhang = 18 inches
 Effective Length $S = 8.86$ ft
 $220 / \sqrt{S} = 73.92\%$ Use **67%** of required main reinforcement
 Required $A_s = 0.60$ sq inches
 Use #4 transverse reinforcement
 min. spacing = 3.98 inches

REINFORCING DESIGN

GIVEN:

$f_y = 60.00$ ksi
 $f'_c = 4.50$ ksi
 COVER = 2.00 inches
 $\Phi_{flexure} = 0.90$
 Beam Thickness (t_s) = 8.00 inches
 $b = 12.00$ inches
 bar diameter = 1.000 inches

CLOSURE POUR

LOAD TYPE	M_{hTOT} ft-K
M_h (UNFACTORED)	6.35
STRENGTH I	10.99
SERVICE I	6.35

$A_{Sreq'd}$ in ²
0.26
0.47
0.26

8

$d_s = 5.50$ inches
 per 5.10.8.2 $A_{Stemp} = 0.14$ sq inches

Use # 8 at top face min. spacing = 20.15 inches
 use spacing = 8.00 inches
 $A_s = 1.185$ sq. inches

compressive steel:

Use # 5 at bottom face
 $A_s' = 0.00$ sq. inches

$M_n = 28.00$ ft-K
 $M_r = 25.20$ ft-K

Reinforcing is okay

Maximum Reinforcement per 5.7.3.3.1-1 (Ductility Check)

$c = 1.88$ inches
 $d_e = d_s = 5.50$ inches (for no prestressing)
 $c/d_e = 0.34$

okay - member is not overreinforced

Minimum Reinforcement per 5.7.3.3.2

$1.2 * M_{cracking} = 6.52$ ft-K <--- Test 1
 $1.33 M_{hTOT} (max.) = 14.62$ ft-K <--- Test 2

Minimum Reinforcing is provided

Transverse Reinforcement per 9.7.3.2

Percentage of main reinforcement, $220 / \sqrt{S} \leq 67\%$

Girder Spacing = 10.94 ft
 Flange Width = 43 inches
 Flange Overhang = 18 inches
 Effective Length $S = 8.86$ ft
 $220 / \sqrt{S} = 73.92\%$ Use 67 % of required main reinforcement
 Required $A_s = 0.79$ sq inches
 Use # 4 transverse reinforcement
 min. spacing = 3.02 inches

5 development

$$\frac{1.25 A_b f_y}{f'_c} = \frac{1.25 (.31) 60}{4.5} = 5.17''$$

$$.4 d_b F_y = .4 (.625) 60 = 15''$$

modification factors

epoxy bar = 1.2

$$\frac{A_{s, reqd}}{A_{s, provided}} = \frac{10.99}{11.27} \approx .975$$

$$l_d \text{ (development length)} = 15'' \times 1.2 \times .975 = 17.55''$$

class C splice = 1.7 l_d

increase splice length by 20% for phasing vibration

$$\begin{aligned} \text{lap splice} &= 1.7 (17.55) (1.2) \\ &= 35.8'' \end{aligned}$$

use 36'' for #5 lap splice

use 32'' for #6 lap splice

use 28 1/4'' for #7 lap splice

use 20'' for #8 lap splice

Minimum

By: Date	Project no.	Project code (SA#):
Chk'd: Date	Structure no.	Sheet 83 of

COLORADO DEPARTMENT OF TRANSPORTATION
DESIGN COMPUTATIONS (Grid)

#6 development

$$\frac{1.25 A_b F_y}{f'_c} = \frac{1.25 (.44)(60)}{4.5} = 7.33''$$

$$.4 d_b F_y = .4 (.75) 60 = 18''$$

modification factors
 epoxy bar 1.2

$$\frac{A_{s \text{ reqd}}}{A_{s \text{ provided}}} \approx \frac{10.99}{15.43} = .71$$

$$l_d \text{ development length} = 18'' * 1.2 * .71 = \underline{15.38''} \leftarrow$$

#6 hook

$$l_{hb} = \frac{38.0 d_b}{\sqrt{f'_c}} \approx \frac{38 (.75)}{\sqrt{4.5}} = 13.435''$$

modification factors

Cover > 2.5'' .7

$$\frac{A_{s \text{ reqd}}}{A_{s \text{ provided}}} \approx .71$$

epoxy coated = 1.2

$$l_d \approx (13.435)(.7)(.71) 1.2 \approx \underline{8.02''} \leftarrow$$

$l_d \approx 11.5''$ if cover < 2.5''

By: _____	Date _____	Project no. _____	Project code (SA#): _____
Chk'd: _____	Date _____	Structure no. _____	Sheet <u>84</u> of _____


COLORADO DEPARTMENT OF TRANSPORTATION
DESIGN COMPUTATIONS (Grid)

$$\text{Class C splice} = 1.7 l_d$$

Increase splice length by 20% for phasing vibration

$$\text{lap splice} \approx 1.7 (15.38") (1.2)$$

$$\text{lap splice} = 31.4"$$

use 32" for lap splice 

By: _____	Date _____	Project no. _____	Project code (SA#): _____
Chk'd: _____	Date _____	Structure no. _____	Sheet <u>85</u> of _____

COLORADO DEPARTMENT OF TRANSPORTATION
 DESIGN COMPUTATIONS (Grid)

#7 development

$$\frac{1.25 A_s f_y}{f_c} = \frac{1.25 (.60) 60}{4.5} =$$

$$.4 d_b F_y = .4 (.875) 60 = 21''$$

modification factors

$$\text{epoxy} = 1.2$$

$$\frac{A_{s \text{ reqd}}}{A_{s \text{ provided}}} \approx \frac{10.99}{20.15} = .545$$

$$l_d = 21'' * 1.2 * .545 = 13.73''$$

class C splice = 1.7 l_d

increase 20% for phasing vibration

$$\text{lap splice} = 1.7 (13.73) 1.2 \approx 28.04''$$

use 28 1/4'' min for #7 lap splice

#8

$$l_d = 24''$$

$$\frac{A_{s \text{ reqd}}}{A_{s \text{ provided}}} \approx \frac{10.99}{25.2} = .436$$


$$l_d = 24'' * 1.2 * .436 \approx 12.56''$$

Class B splice = 1.3 l_d

$$\text{lap splice} = 1.3 (12.56) 1.2 \approx 19.6''$$


use 20'' for #8 lap splice

By: _____	Date _____	Project no. _____	Project code (SA#): _____
Chk'd: _____	Date _____	Structure no. _____	Sheet <u>86</u> of _____



COLORADO DEPARTMENT OF TRANSPORTATION
 DESIGN COMPUTATIONS (Grid)

DECK JOINTS



$a \approx 8'$
 $b \approx 18'$
 $a/b \approx .44$ use $3/8$ in table

$LL = .64 \text{ K/LF}$
 $= .064 \text{ K/SF}$
 (assuming 10' lane)

$M_y =$
 $1/6 = .5$

Coefficient $M_y \approx .0166$ midspan $.0516$ near girder

Moment = (Coefficient) ρa^2
 $= .0166 (.064) 8^2$

$M \approx .068 \text{ Kft}$ (.211 Kft near girder)

worst case spacing of #5 = 18"

capacity > 4 ft K joint is okay for moments about joint

Shear Capacity

$V_s \approx \frac{A_v f_y d_v}{s} (\cot \theta + \cot \alpha) \sin \alpha = \frac{2(.31)(60)}{18} 6'' \cot 45^\circ$ (5.8.3.3.4)
 $V_s = 12.4 \text{ K}$

$V_c \approx .0316 B \sqrt{f'_c} b r d_v = (.0316)(2) \sqrt{7.2} (18'')(6'') \approx 289.8 \text{ K}$ (5.8.3.3.3)

By: Date	Project no.	Project code (SA#):
Chk'd: Date	Structure no.	Sheet <u>88</u> of <u> </u>

COLORADO DEPARTMENT OF TRANSPORTATION
DESIGN COMPUTATIONS (Grid)

Joint is good for shear

Post Tensioning is not required. for lane load



M_{provided} by post tensioning $\approx 9.83 \text{ kft} / \text{strand}$

Conduit spacing $\approx 2'-6''$

$\Rightarrow 3.932 \text{ kft/ft} / \text{strand}$

For 16k wheel load, $M_{\text{strength}} \approx 6.73 \text{ kft/ft}$ (from SAA 14)

$M_{\text{service}} = 4.54 \text{ kft/ft}$

need minimum 2 strands per conduit for deck loading

need 4 strands per conduit for negative moment

By: _____	Date _____	Project no. _____	Project code (SA#): _____
Chk'd: _____	Date _____	Structure no. _____	Sheet <u>29</u> of _____

REINFORCING DESIGN

GIVEN:

$f_y = 60.00$ ksi
 $f_c = 7.00$ ksi
 COVER = 2.50 inches
 $\Phi_{flexure} = 0.90$
 Beam Thickness (t_s) = 8.00 inches
 $b = 18.00$ inches
 bar diameter = 0.625 inches

LOAD TYPE	M_{hTOT} ft-K
Mh (UNFACTORED)	4.54
STRENGTH I	6.73
SERVICE I	4.54

$AS_{req'd}$ in ²
0.20
0.29
0.20

*deck joint
mild steel*

$d_s = 5.19$ inches
 per 5.10.8.2 $AS_{temp} = 0.22$ sq inches

Use # 5 at top face min. spacing = 19.04 inches
 use spacing = 18.00 inches
 $A_s = 0.310$ sq. inches

compressive steel:

Use # 5 at bottom face
 $A_s' = 0.00$ sq. inches

$M_n = 7.91$ ft-K
 $M_r = 7.12$ ft-K

Reinforcing is okay

Maximum Reinforcement per 5.7.3.3.1-1 (Ductility Check)

$c = 0.25$ inches
 $d_e = d_s = 5.19$ inches (for no prestressing)
 $c/d_e = 0.05$

okay - member is not overreinforced

~ 50% of development length

$M_{r actual} \approx 3.5$ ft-k

$\Rightarrow 2.3$ ft-k/ft

Minimum Reinforcement per 5.7.3.3.2

$1.2 * M_{cracking} = 12.19$ ft-K <--- Test 1
 $1.33 M_{hTOT} (max.) = 8.95$ ft-K <--- Test 2

Needs more reinforcing

Transverse Reinforcement per 9.7.3.2

Percentage of main reinforcement, $220 / \sqrt{S} \leq 67\%$

Girder Spacing = 15.25 ft
 Flange Width = 21 inches
 Flange Overhang = 18 inches
 Effective Length S = 15.00 ft

$220 / \sqrt{S} = 56.80\%$ Use **56.804** % of required main reinforcement

Required $A_s = 0.18$ sq inches
 Use # 6 transverse reinforcement
 min. spacing = 44.97 inches

Design Computations

REINFORCING DESIGN

GIVEN:

$f_y = 183.33$ ksi after losses
 $f_c = 7.20$ ksi
 COVER = 3.69 inches
 $\Phi_{flexure} = 0.75$
 Beam Thickness (t_s) = 8.00 inches
 $b = 30.00$ inches
 bar diameter = 0.875 inches

POST TENSIONING

Impact Steel

LOAD TYPE	M_{hTOT} ft-K	$A_{Sreq'd}$ in ²
M_h (UNFACTORED)	4.00	0.09
STRENGTH I	4.00	0.09
SERVICE I	4.00	0.09

$d_s = 3.88$ inches
 per 5.10.8.2 $A_{Stemp} = 0.14$ sq inches

Use # 4 at top face min. spacing = 65.81 inches
 use spacing = 18.00 inches

compressive steel:

$A_s = 0.217$ sq. inches
 Use # 5 at bottom face
 $A_{s'} = 0.00$ sq. inches

1 strand

$M_h = 13.11$ ft-K
 $M_r = 9.83$ ft-K $\rightarrow 3.93$ ft K/ft

Reinforcing is okay

Maximum Reinforcement per 5.7.3.3.1-1 (Ductility Check)

$c = 0.31$ inches
 $d_e = d_s = 3.88$ inches (for no prestressing)
 $c/d_e = 0.08$

okay - member is not overreinforced

Minimum Reinforcement per 5.7.3.3.2

$1.2 * M_{cracking} = 20.61$ ft-K <--- Test 1
 $1.33 M_{hTOT} (max.) = 5.32$ ft-K <--- Test 2

Minimum Reinforcing is provided


Transverse Reinforcement per 9.7.3.2

Percentage of main reinforcement, $220 / \sqrt{S} \leq 67\%$


Girder Spacing = 15.25 ft
 Flange Width = 21 inches
 Flange Overhang = 18 inches
 Effective Length $S = 15.00$ ft
 $220 / \sqrt{S} = 56.80$ % Use **56.804** % of required main reinforcement
 Required $A_s = 0.12$ sq inches
 Use # 6 transverse reinforcement
 min. spacing = 107.08 inches

MOMENTS AND REACTIONS FOR RECTANGULAR PLATES

y/b \ x/a	M _x								M _y							
	0	0.05	0.1	0.2	0.3	0.4	0.5	0	0.05	0.1	0.2	0.3	0.4	0.5		
a/b = 3/8	0.5	+0.5055	+0.0830	+0.0590	+0.0376	+0.0024	-0.0226	-0.0375	-0.0424	+0.0156	+0.0118	+0.0074	+0.0002	-0.0050	-0.0082	-0.0093
	0.4	+0.5068	+0.0825	+0.0585	+0.0371	+0.0022	-0.0225	-0.0372	-0.0420	+0.0165	+0.0117	+0.0073	-0.0001	-0.0055	-0.0088	-0.0099
	0.3	+0.5060	+0.0796	+0.0558	+0.0348	+0.0013	-0.0219	-0.0355	-0.0400	+0.0159	+0.0110	+0.0065	-0.0013	-0.0071	-0.0108	-0.0120
	0.2	+0.4778	+0.0690	+0.0470	+0.0282	-0.0004	-0.0192	-0.0299	-0.0334	+0.0138	+0.0091	+0.0046	-0.0034	-0.0095	-0.0132	-0.0145
	0.1	+0.3316	+0.0400	+0.0254	+0.0139	-0.0017	-0.0108	-0.0155	-0.0170	+0.0080	+0.0047	+0.0017	-0.0033	-0.0066	-0.0084	-0.0090
	0.05	+0.1331	+0.0170	+0.0108	+0.0060	+0.0001	-0.0026	-0.0037	-0.0039	+0.0034	+0.0026	+0.0026	+0.0044	+0.0071	+0.0094	+0.0102
	0	-0.0513	0	+0.0005	+0.0016	+0.0047	+0.0076	+0.0096	+0.0103	0	+0.0024	+0.0078	+0.0234	+0.0381	+0.0481	+0.0516
R _x \ R _y	-0.0513	-0.0797	+0.0291	+0.2203	+0.3559	+0.4352	+0.4612									
a/b = 1/2	0.5	+0.5142	+0.0815	+0.0573	+0.0359	+0.0015	-0.0224	-0.0365	-0.0411	+0.0163	+0.0113	+0.0068	-0.0012	-0.0071	-0.0108	-0.0121
	0.4	+0.5111	+0.0797	+0.0557	+0.0346	+0.0011	-0.0220	-0.0355	-0.0399	+0.0159	+0.0110	+0.0064	-0.0017	-0.0078	-0.0116	-0.0129
	0.3	+0.4928	+0.0728	+0.0499	+0.0303	-0.0000	-0.0203	-0.0319	-0.0356	+0.0146	+0.0097	+0.0051	-0.0031	-0.0093	-0.0132	-0.0145
	0.2	+0.4260	+0.0568	+0.0375	+0.0217	-0.0014	-0.0159	-0.0238	-0.0263	+0.0114	+0.0071	+0.0030	-0.0042	-0.0096	-0.0128	-0.0139
	0.1	+0.2350	+0.0270	+0.0168	+0.0090	-0.0011	-0.0066	-0.0092	-0.0100	+0.0054	+0.0032	+0.0014	-0.0006	-0.0013	-0.0013	-0.0012
	0.05	+0.0591	+0.0099	+0.0066	+0.0039	+0.0011	+0.0003	+0.0003	+0.0003	+0.0020	+0.0022	+0.0034	+0.0082	+0.0135	+0.0174	+0.0188
	0	-0.0496	0	+0.0005	+0.0016	+0.0049	+0.0080	+0.0100	+0.0108	0	+0.0025	+0.0082	+0.0247	+0.0399	+0.0502	+0.0538
R _x \ R _y	-0.0496	-0.0631	+0.0371	+0.2253	+0.3598	+0.4382	+0.4638									
a/b = 5/8	0.5	+0.5143	+0.0765	+0.0526	+0.0319	-0.0001	-0.0214	-0.0336	-0.0376	+0.0153	+0.0102	+0.0054	-0.0033	-0.0101	-0.0144	-0.0159
	0.4	+0.5045	+0.0736	+0.0502	+0.0302	-0.0004	-0.0207	-0.0321	-0.0358	+0.0147	+0.0097	+0.0050	-0.0037	-0.0104	-0.0147	-0.0161
	0.3	+0.4660	+0.0642	+0.0429	+0.0251	-0.0012	-0.0181	-0.0274	-0.0304	+0.0128	+0.0082	+0.0037	-0.0045	-0.0107	-0.0146	-0.0159
	0.2	+0.3697	+0.0462	+0.0297	+0.0166	-0.0017	-0.0127	-0.0186	-0.0204	+0.0092	+0.0055	+0.0020	-0.0039	-0.0082	-0.0106	-0.0114
	0.1	+0.1635	+0.0191	+0.0119	+0.0065	-0.0004	-0.0037	-0.0052	-0.0056	+0.0038	+0.0025	+0.0018	+0.0022	+0.0036	+0.0050	+0.0056
	0.05	+0.0150	+0.0063	+0.0046	+0.0030	+0.0018	+0.0020	+0.0025	+0.0028	+0.0013	+0.0021	+0.0042	+0.0110	+0.0180	+0.0231	+0.0249
	0	-0.0454	0	+0.0005	+0.0017	+0.0050	+0.0082	+0.0102	+0.0109	0	+0.0025	+0.0083	+0.0252	+0.0408	+0.0511	+0.0547
R _x \ R _y	-0.0454	-0.0527	+0.0410	+0.2277	+0.3616	+0.4394	+0.4648									
a/b = 3/4	0.5	+0.4999	+0.0686	+0.0457	+0.0265	-0.0017	-0.0196	-0.0293	-0.0324	+0.0137	+0.0087	+0.0037	-0.0055	-0.0128	-0.0175	-0.0191
	0.4	+0.4845	+0.0653	+0.0432	+0.0248	-0.0019	-0.0186	-0.0277	-0.0306	+0.0131	+0.0082	+0.0034	-0.0056	-0.0126	-0.0171	-0.0186
	0.3	+0.4311	+0.0550	+0.0357	+0.0200	-0.0022	-0.0156	-0.0227	-0.0249	+0.0110	+0.0066	+0.0024	-0.0054	-0.0113	-0.0150	-0.0162
	0.2	+0.3179	+0.0374	+0.0235	+0.0126	-0.0019	-0.0101	-0.0142	-0.0155	+0.0075	+0.0043	+0.0014	-0.0033	-0.0064	-0.0081	-0.0086
	0.1	+0.1133	+0.0140	+0.0089	+0.0049	+0.0001	-0.0018	-0.0025	-0.0026	+0.0028	+0.0021	+0.0023	+0.0045	+0.0074	+0.0098	+0.0107
	0.05	-0.0109	+0.0043	+0.0034	+0.0024	+0.0022	+0.0031	+0.0039	+0.0043	+0.0009	+0.0021	+0.0048	+0.0129	+0.0210	+0.0268	+0.0288
	0	-0.0412	0	+0.0005	+0.0017	+0.0051	+0.0082	+0.0102	+0.0109	0	+0.0024	+0.0083	+0.0254	+0.0409	+0.0511	+0.0546
R _x \ R _y	-0.0412	-0.0457	+0.0445	+0.2305	+0.3626	+0.4384	+0.4629									
a/b = 7/8	0.5	+0.4730	+0.0592	+0.0380	+0.0208	-0.0031	-0.0172	-0.0245	-0.0267	+0.0118	+0.0070	+0.0021	-0.0072	-0.0146	-0.0193	-0.0209
	0.4	+0.4542	+0.0560	+0.0356	+0.0193	-0.0031	-0.0162	-0.0229	-0.0250	+0.0112	+0.0065	+0.0018	-0.0070	-0.0139	-0.0183	-0.0198
	0.3	+0.3928	+0.0462	+0.0288	+0.0153	-0.0029	-0.0131	-0.0183	-0.0198	+0.0092	+0.0052	+0.0012	-0.0059	-0.0113	-0.0146	-0.0157
	0.2	+0.2736	+0.0302	+0.0184	+0.0094	-0.0020	-0.0079	-0.0107	-0.0114	+0.0060	+0.0033	+0.0010	-0.0026	-0.0047	-0.0057	-0.0061
	0.1	+0.0798	+0.0106	+0.0068	+0.0037	+0.0005	-0.0005	-0.0006	-0.0006	+0.0021	+0.0019	+0.0027	+0.0060	+0.0099	+0.0129	+0.0139
	0.05	-0.0250	+0.0031	+0.0026	+0.0021	+0.0025	+0.0037	+0.0047	+0.0051	+0.0006	+0.0021	+0.0051	+0.0140	+0.0226	+0.0285	+0.0306
	0	-0.0377	0	+0.0005	+0.0017	+0.0050	+0.0080	+0.0099	+0.0106	0	+0.0024	+0.0083	+0.0251	+0.0400	+0.0497	+0.0530
R _x \ R _y	-0.0377	-0.0391	+0.0503	+0.2341	+0.3608	+0.4319	+0.4546									
a/b = 1	0.5	+0.4389	+0.0500	+0.0306	+0.0156	-0.0040	-0.0147	-0.0198	-0.0213	+0.0100	+0.0054	+0.0007	-0.0082	-0.0153	-0.0197	-0.0213
	0.4	+0.4189	+0.0470	+0.0286	+0.0144	-0.0039	-0.0137	-0.0184	-0.0197	+0.0094	+0.0050	+0.0006	-0.0078	-0.0143	-0.0184	-0.0198
	0.3	+0.3551	+0.0382	+0.0229	+0.0112	-0.0033	-0.0109	-0.0143	-0.0153	+0.0076	+0.0040	+0.0003	-0.0061	-0.0109	-0.0137	-0.0147
	0.2	+0.2373	+0.0244	+0.0143	+0.0068	-0.0020	-0.0061	-0.0078	-0.0082	+0.0049	+0.0026	+0.0007	-0.0020	-0.0033	-0.0039	-0.0040
	0.1	+0.0585	+0.0082	+0.0052	+0.0028	+0.0007	+0.0003	+0.0006	+0.0007	+0.0016	+0.0018	+0.0028	+0.0068	+0.0112	+0.0144	+0.0156
	0.05	-0.0316	+0.0024	+0.0021	+0.0018	+0.0026	+0.0040	+0.0050	+0.0054	+0.0005	+0.0021	+0.0052	+0.0143	+0.0229	+0.0286	+0.0306
	0	-0.0351	0	+0.0005	+0.0016	+0.0049	+0.0076	+0.0094	+0.0100	0	+0.0024	+0.0082	+0.0244	+0.0382	+0.0470	+0.0500
R _x \ R _y	-0.0351	-0.0316	+0.0585	+0.2373	+0.3551	+0.4189	+0.4389									




Moment = (Coefficient)(pa²)
Reaction = (Coefficient)(pa)



POSITIVE SIGN CONVENTION

FIGURE 34.—Plate fixed along four edges, moment and reaction coefficients, Load I, uniform load.

Side conduit



COMPRESSIVE STRESSES

$$f_{ca} = \frac{.6 P_u K}{A_b \left(1 + \rho_c \left(\frac{1}{b_{eff}} - \frac{1}{t}\right)\right)} \quad (5.10.9.6.2 - 1)$$

$K = 1.0$

$t = 8''$

$b_{eff} = 6''$ (assumed)

$a_{eff} = 12''$ (assumed)

$\rho_c = 1.15 \left(\max(b_{eff}, a_{eff})\right) = 1.15(12) = 13.8$

$P_u = .75 (270 \text{ ksi}) (4) (.217 \text{ m}^2) = 175.77 \text{ K}$

$A_{duct} = 1.843 \text{ in}^2$

$A_b = 6'' \times 12'' - 1.843 = 70.1568 \text{ in}^2$

$f_{ca} \approx 1.523 \text{ ksi}$

$f_{all} = .7 \phi f'_{ci} = .7 (.9) (5.0 \text{ ksi})$

$f_{all} \approx 3.15 \text{ ksi}$

$f_{ca} < f_{all}$ can use smaller plate

max spiral $\phi = 8'' - 1'' - 1'' = 6''$

max $A_{conf} = \frac{\pi \phi^2}{4} \approx 19.63 \text{ in}^2$

$A_{plate \text{ max}} = \frac{4}{\pi} A_{conf} = 25 \text{ in}^2$

$f_{ca} \approx \frac{.6 (175.77)}{19.63 \left(1 + 13.8 \left(\frac{1}{6} - \frac{1}{8}\right)\right)} = 3.41 > f_{allow}$

can't use spiral reinforcement
 not enough room

By: Date	Project no.	Project code (SA#):
Chk'd: Date	Structure no.	Sheet 94 of

COLORADO DEPARTMENT OF TRANSPORTATION
DESIGN COMPUTATIONS (Grid)

Compressive stresses (cont.)

for hat bars

$$A_{conf} = 4" \times 9" \approx 36 \text{ in}^2$$

$$A_{plate \text{ max}} = \frac{4}{\pi} A_{conf} \approx 45.84 \text{ in}^2$$

$$A_{plate} = 5" \times 8" = 40 \text{ in}^2 \rightarrow \text{controls}$$

$$A_b = 40 \text{ in}^2 - 1.8343 = 38.166 \text{ in}^2$$

duct area

$$l_c = 1.15 (8") = 9.2"$$

$$f_{ca} = \frac{.6 (175.77) (1.0)}{38.166 \left(1 + 9.2 \left(\frac{1}{5} - \frac{1}{8} \right) \right)}$$

$$f_{ca} \approx 1.65 \text{ ksi}$$

$$F_{allow} = 3.15 \text{ ksi} \quad \checkmark \text{ okay}$$

k= 1
beff= 6
aeff= ~~8~~ 8
t= 8
lc= 10.35
Pu= 175.77
Ab= 52.1568

fca= 2.022018 ksi

fallow= 3.15 ksi

By: Date
Chk'd: Date

Project no. .
Structure no. .

Project code (SA#)
Sheet 96 of .

BURSTING FORCES

$$T_{burst} = .25 \sum P_u \left(1 - \frac{a}{h}\right) + .5 \left[\sum P_u \sin \alpha \right] \quad (5.10.9.6.3-1)$$

$$\alpha = 0$$

$$P_u = .75 (270 \text{ ksi}) (4) (.217 \text{ in}^2) = 175.77 \text{ K}$$

$$a \approx 6''$$

$$h = 8''$$

$$T_{burst} = .25 (175.77) \left(1 - \frac{6}{8}\right) + .5 (0)$$

$$T_{burst} = 16.48 \text{ Kip}$$

$$d_{burst} = .5 (h - 2e) + 5e \sin \alpha$$

$$(5.10.9.6.3-2)$$

$$e = 0$$

$$d_{burst} \approx .5 (8) = 4''$$

distance for reinforce

$$2.5 d_{burst} = 2.5 (4) = 10''$$

$$1.5 h = 1.5 (8) = 12''$$

$$f_c = 9.2''$$


$$\#4 \text{ bar} = .20 \text{ in}^2$$

$$\#3 \text{ bars} = .11 \text{ in}^2$$

$$\sigma = \frac{10.99}{.20} = 54.95 \text{ ksi for 1 bar}$$

assume shared by 4 bars

$$\sigma \approx 13.74 \text{ ksi}$$



149.82 ksi for 1 #3

assume 6 bars

$$\sigma \approx 25 \text{ ksi}$$

4.5''

By: Date	Project no.	Project code (SA#):
Chk'd: Date	Structure no.	Sheet 97 of


POST-TENSION FORCE ON TRANSVERSE JOINTS

(Phase 3 & 4)

(other phases similar)

Phase 2 - $L_{wi} = 48' - 3"$

17 ducts
width = 40'




~13 ducts, 4 strands each

Post Tension Force = $13 \times 4 \times .217 \text{ in}^2/\text{strand} \times .75 \times 270 \text{ ksi}$

$F_{pt} = 2285.01 \text{ K}$



Normal force = $\cos 34^\circ (2285.01) \approx 1894.4 \text{ K}$
 transverse force = $\sin 34^\circ (2285.01) \approx 1277.8 \text{ K} = V_{ui}$



$A_{vf} = 31' / .31 \text{ in}^2/\text{ft} = 9.61 \text{ in}^2$



$A_{vf} \geq \frac{.05 A_{cw}}{f_y}$ (5.8.4.4-1)

$b_w \approx 6.25"$

$L_w = 37' - 4"$

$A_{cw} = b_w L_w = 6.25 \times 37.33 \times \frac{12}{1} = 2800 \text{ in}^2$ (4256 in² for 9.5") (5.8.4.1-6)

$A_{vf} \geq \frac{.05 \times 2800}{60} = 2.33 \text{ in}^2$

$\Rightarrow .06 \text{ in}^2/\text{ft}$ (minimum)

$\#5 @ 12" = .31 \text{ in}^2/\text{ft}$ ✓ okay

By: Date	Project no.	Project code (SA#):
Chk'd: Date	Structure no.	Sheet 98 of

COLORADO DEPARTMENT OF TRANSPORTATION
DESIGN COMPUTATIONS (Grid)

$$V_{ni} = c A_{cv} + \mu (A_{cv} f_y + P_c) \quad (5.8.4.1-3)$$

$$c = .075 \text{ Ksi}$$

$$\mu = .6$$

$$K_1 = .2$$

$$K_2 = .8 \text{ Ksi}$$

Concrete placed against
 a clean concrete surface
 not intentionally roughened

$$(5.8.4.3)$$

$$V_{ni} = (.075 \text{ Ksi}) (4256 \text{ in}^2) + .6 \left(\frac{24}{15} (9.61 \text{ in}^2) \# 60 \text{ Ksi} + 0 \right)$$

$$V_{ni} = 319.2 \text{ K} + 1153.2$$

$$V_{ni} = 1472.4 \text{ K}$$

$$V_{ni} \leq K_1 f'_c A_{cv} \quad (5.8.4.1-4)$$

$$\leq .2 (7.2) 2400 = 3456 \text{ K}$$

$$V_{ni} \leq K_2 A_{cv} \quad (5.8.4.1-5)$$

$$\leq .8 (2400) = 1920 \text{ K}$$

$$V_{ri} = \phi V_{ni} \quad (5.8.4.1-1)$$

$$V_{ri} = (.9) (1472.4) = \underline{1325.2 \text{ K}} \quad \leftarrow$$

$$V_{ri} > V_{ui}$$

$$1325.2 > 1277.8$$

✓ okay

By: Date	Project no.	Project code (SA#):
Chk'd: Date	Structure no.	Sheet 29 of

COLORADO DEPARTMENT OF TRANSPORTATION
DESIGN COMPUTATIONS (Grid)

$$\left. \begin{aligned}
 C &= .24 \text{ ksi} \\
 \mu &= 1.0 \\
 K_1 &= .25 \\
 K_2 &= 1.5 \text{ ksi}
 \end{aligned} \right\} \begin{array}{l} \text{roughened surface} \\ .25" \text{ amplitude} \end{array} \quad (5.8.4.3)$$

$$V_{ni} = C A_{cv} + \mu (A_{vf} F_y + P_c) \quad (5.8.4.1-3)$$

$$V_{ni} = .24 (2800) + 1.0 (2 \text{ legs} * 9.61 \text{ in}^2 * 60 \text{ ksi} + 0)$$

4256

$$V_{ni} = 672 \text{ K} + 1153.2 \text{ K}$$

$$V_{ni} \approx 1825.2 \text{ K}$$

$$V_{ri} = \phi V_{ni} = .9 (1825.2 \text{ K}) \quad (5.8.4.1-1)$$

$$\underline{V_{ri} = 1642.7 \text{ K}} \quad \leftarrow$$

$$\begin{aligned}
 V_{ni} &\leq K_1 A_{cv} = .25 (7.2) (2800) && (5.8.4.1-4) \\
 &= 5040 \text{ K}
 \end{aligned}$$

$$\begin{aligned}
 V_{ni} &\leq K_2 A_{cv} = (1.5) (2800) && (5.8.4.1-5) \\
 &\approx 4200 \text{ K}
 \end{aligned}$$

$$V_{ri} = 1642.7 \text{ K} > V_{ui} \quad \checkmark \quad \text{okay}$$

for 5" roughend



$$\begin{aligned}
 V_{ni} &= .24 (2240) + 1153.2 \\
 &= 537.6 + 1153.2 \\
 &= 1690.8
 \end{aligned}$$

$$V_{ri} = \phi V_{ni} = .9 (1690.8) = 1521.7 \text{ K}$$

By: _____	Date _____	Project no. _____	Project code (SA#): _____
Chk'd: _____	Date _____	Structure no. _____	Sheet 100 of _____

COLORADO DEPARTMENT OF TRANSPORTATION
DESIGN COMPUTATIONS (Grid)

ELASTIC SHORTENING

$$\delta = \frac{PL}{AE}$$

Phase I

18 conduit * 4 strands = 72 strands

$$A_g \approx 8'' \times 43' \approx 4128 \text{ in}^2$$


$$E_c \approx 4917 \text{ ksi} \quad f'_c = 7.3 \text{ ksi} \quad (\text{28 day strength})$$

$$L \approx 368' = 4416 \text{ in} \quad (\text{E Abut to E Abut})$$

$$P \approx .75 (270 \text{ ksi}) (72 \text{ strands}) (.27 \text{ in}^2/\text{strand})$$

$$P \approx 3163.9 \text{ K}$$


$$\delta = \frac{(3163.9 \text{ K})(4416)}{(4128)(4917)} \approx .69''$$



make bottom portion of level screw
smooth to allow sliding

By: Date	Project no.	Project code (SA#):
Chk'd: Date	Structure no.	Sheet 10 of

POST-TENSIONING FORCES (ON ADJUSTING SCREW)



deck width $\approx 25'$

~ 9 ducts, 3 strands each

Post Tension Force $\approx 9 * 3 * .217 \text{ in}^2/\text{strand} * .75 * 270 \text{ ksi}$

$F_{PT} \approx 1186.4 \text{ K}$

From SAP 2000

WORST REACTION $\approx 8 \text{ Kip}$ @ center R_3

assume supports evenly spaced

$8 \text{ k}/74' \approx .11 \text{ K/ft}$

$6.9 \text{ k} / ((86/2) + 74/2) \approx .09 \text{ K/ft}$

for 8' panel $\Rightarrow (8)(.11) \approx .88 \text{ K} / \text{panel}$

assume 4 supports per panel

$\approx .88 \text{ k}/4 \approx .22 \text{ K} / \text{support}$

Use Safety Factor ≈ 1.5

Load $\approx (.22 \text{ k})(1.5) \approx .33 \text{ Kips} \approx .44 \text{ k} / \text{for 4 strands}$

6 kips

Dead load $\approx (31')(8')(8\frac{1}{2} \text{ in}^2/\text{ft}^2)(.15 \text{ k/ft}^3) \approx 24.8 \text{ K}$

$24.8 \text{ k} / 4 \text{ supports} \approx 6.2 \text{ K}$

$\% \approx .33 / 6.2 \approx .053 \Rightarrow 5.3\%$

Use 450 lb/adjusting screw \leftarrow

By: Date	Project no.	Project code (SA#):
Chk'd: Date	Structure no.	Sheet 102 of

Deck Panel Supports - conceptual design

phase 3 & 4 - deck panel width $\approx 35'$

$$wt = (35') \left(\frac{8''}{12''} \right) (8') .15k \approx 28k$$

assume 4 supports (2/web)

$$wt \approx 28k/4 \approx 7k$$

allowable stress = $.3f'_c$

$$f'_c = 9 \text{ ksi}$$

$$(.3)(9 \text{ ksi}) \approx 2.7 \text{ ksi}$$

$$A_{reqd} \approx \frac{7k}{2.7} \approx 2.6 \text{ in}^2$$

$1\frac{3}{4}''$ SQR R

or $12''$ Round R

allowable stress $\approx .55 F_y$

A325 $F_y \approx 90$

Grade 36 & 55

assume 36 ksi

$$T_{allow} = .55(36) = 19.8 \text{ ksi}$$


$$A_{reqd} = \frac{7}{19.8 \text{ ksi}} = .35 \text{ in}^2$$

$\frac{3}{4}''$ bolt = .44 in²

use $1''$ bolt with $2''$ round R
 or approved equal

COLORADO DEPARTMENT OF TRANSPORTATION
DESIGN COMPUTATIONS (Grid)

OVER HANG DEFLECTION (DEAD LOAD)



$$\Delta_x = \frac{Pb^2}{6EI} (3L - 3x - b)$$

$$\Delta_{\text{barrier}} = \frac{(8') (.485) [6.187(12)]^2}{6 (4883.57) 4096} \left[3 (7.467(12)) - 6.187(12) \right]$$

$$\Delta_{\text{barrier}} \approx .035''$$

$$\Delta_{\text{deck}} \approx \frac{w d^4}{8EI} = \frac{8' \left(\frac{3''}{12''} \right) \left(\frac{15k}{ft} \right) \left[\frac{7.467(12)}{12} \right]^4}{8 (4883.57) (4096)}$$

$$\Delta_{\text{deck}} \approx .027''$$

$$\Delta_{\text{asphalt}} \approx \frac{8' \left(\frac{3''}{12''} \right) (1.1467 \frac{k}{ft}) [5.967(12)]^4}{8 (4883.57) 4096}$$


$$\Delta_{\text{asphalt}} \approx .048''$$

$$\text{total } \Delta \approx .11''$$

By: _____	Date _____	Project no. _____	Project code (SA#): _____
Chk'd: _____	Date _____	Structure no. _____	Sheet <u>104</u> of _____

COLORADO DEPARTMENT OF TRANSPORTATION
DESIGN COMPUTATIONS (Grid)

PHASE 3 & 4 OVERHANG DEFLECTION (DEADLOAD)



$$\Delta_{deck} = \frac{w l^4}{8EI}$$

$$\Delta_{deck} = \frac{(8') \left(\frac{2''}{12''} \right) (.15) [12(12)]^4}{8 (4883.57) 4096}$$

$\frac{K}{EI} = \frac{1'}{12'' \cdot 14.6}$

$$\Delta_{deck} \approx 2.18''$$

Prestress Camber $\approx \frac{M l^2}{8EI}$


$$M = P e$$



$$e = 1.7''$$

$$P = 14 (.217) (.75) (270 \text{ ksi}) \approx 615.2 \text{ k}$$

$$P = 1045.83 \text{ in k.p}$$



$$\delta = \frac{(1045.83) \left(32' \times \frac{12''}{ft} \right)^2}{8 (4883.57) 4096} \approx .96''$$

For debonded strand

$$b_1 = 12' / 32 = .375$$

$$b_2 = 13' / 32 = .406$$

$$l = 32'$$

$$\delta = \frac{M l^2}{8EI} (1 - 2b_1^2 - 2b_2^2)$$















$$\delta = \frac{(1045.83) (384)^2}{8 (4883.57) (4096)} [1 - 2(.375)^2 - 2(.406)^2] \approx .375''$$

By: Date	Project no.	Project code (SA#):
Chk'd: Date	Structure no.	Sheet 105 of

DESIGN THEORY AND PROCEDURE

8.7 Camber and Deflection

Table 8.7-1
Camber (deflection) and rotation coefficients for prestress force and loads*

Prestress Pattern	Equivalent Moment or Load	Equivalent Loading	Camber	End rotation
(1) 	$M = Pe$		$\frac{M\ell^2}{16EI} + \frac{M\ell}{3EI}$	$\frac{M\ell}{6EI}$
(2) 	$M = Pe$		$\frac{M\ell^2}{16EI} + \frac{M\ell}{6EI}$	$\frac{M\ell}{3EI}$
(3) 	$M = Pe$		$\frac{M\ell^2}{8EI} + \frac{M\ell}{2EI}$	$\frac{M\ell}{2EI}$
(4) 	$N = \frac{4Pe'}{\ell}$		$\frac{N\ell^3}{48EI} + \frac{N\ell^2}{16EI}$	$\frac{N\ell^2}{16EI}$
(5) 	$N = \frac{Pe'}{b\ell}$		$\frac{b(3-4b^2)N\ell^3}{24EI} + \frac{b(1-b)N\ell^2}{2EI}$	$\frac{b(1-b)N\ell^2}{2EI}$
(6) 	$w = \frac{8Pe'}{\ell^2}$		$\frac{5w\ell^4}{384EI} + \frac{w\ell^3}{24EI}$	$\frac{w\ell^3}{24EI}$
(7) 	$M = Pe'$		$\frac{M\ell^2}{8EI}(1-2b_1^2-2b_2^2) + \frac{M\ell}{2EI}[(1-2b_1)^2-b_2^2]$	$\frac{M\ell}{2EI}[(1-2b_1)^2-b_2^2]$

* The tabulated values apply to the effects of prestressing. By adjusting the directional rotation, they may also be used for the effects of loads. For patterns 4 to 7, superimpose on 1, 2 or 3 for other C.G. locations

COLORADO DEPARTMENT OF TRANSPORTATION
DESIGN COMPUTATIONS (Grid)

LIVE LOAD DEFLECTION

$$\Delta < \text{Span}/800$$

(2.5.2.6.2)

$$\Delta < \text{Cantilever}/300$$

Design Manual 9.1-C1

for skewed bridges, a right cross section may be used
 for simply supported beam:

$$\Delta = \frac{Px}{48EI} (3L^2 - 4x^2)$$

$$V = \frac{M}{S} = \frac{83.6(12)}{1024} = 1.65$$

$$P = 50 \text{ K} \times 1.33 = 66.5 \text{ K}$$

$$x = L/2 \approx 107.6''$$

$$L = 17.927' \approx 215.2''$$

$$E = 4883.57 \text{ ksi}$$

$$I \approx 4096 \text{ in}^4$$

$$\Delta = \frac{25 (107.6)}{48 (4883.57) 4096} (3 (215.2)^2 - 4 (107.6)^2)$$

$$\Delta \approx .26''$$

$$\Delta_{\max} = L/800 = \frac{215.2''}{800} \approx .269''$$

$$\Delta < \Delta_{\max}$$

✓

okay

$$\text{Clear span} = 14' - 11''$$

$$\text{skew dist} \approx \frac{14.92}{\sin 56} = 18' \approx 216''$$

$$x = 108''$$

$$\Delta = \frac{25 (108)}{48 (4883.57) 4096} (3 (216)^2 - 4 (108)^2)$$

$$\Delta \approx .263''$$

$$\Delta_{\max} = \frac{216}{800} \approx .27'' \quad \checkmark \quad \text{okay}$$

By: Date	Project no.	Project code (SA#):
Chk'd: Date	Structure no.	Sheet 107 of

COLORADO DEPARTMENT OF TRANSPORTATION
DESIGN COMPUTATIONS (Grid)

LIVE LOAD DEFLECTION

$$\Delta < \text{cantilever}/300$$

$$l = 6' - 7\frac{1}{2}" \text{ to live load} = 79.5"$$

$$\text{live load} = 1 \text{ k/ft}$$

$$\Delta = \frac{P}{6EI} (2l^3)$$

$$E = 4883.57 \text{ ksi}$$

$$I = 4096 \text{ in}^4 \text{ for } 8' \text{ slab}$$

$$\Delta = \frac{(1 \text{ k/ft})(8)(1.33)}{6(4883.57)(4096)} 2(79.5)^3$$


$$\Delta = .089"$$

$$\Delta_{\text{max}} = \frac{79.5}{300} = .265"$$

$$\Delta < \Delta_{\text{max}} \quad \checkmark \quad \text{OKay}$$

By: _____	Date _____	Project no. _____	Project code (SA#): _____
Chk'd: _____	Date _____	Structure no. _____	Sheet <u>108</u> of _____


**COLORADO DEPARTMENT OF TRANSPORTATION
DESIGN COMPUTATIONS (Grid)**



SPAN 1/SPAN 5 deflection $\approx .009317 \frac{P L^3}{EI}$

SPAN 3 deflection $\approx \frac{P L^3}{192 EI}$

$f_c = 9 \text{ ksi}$
 $E \approx 5460 \text{ ksi}$
 $I \approx 2,947,200 \text{ in}^4$
 $I_{\text{worst}} \approx 2,921,130$
 (exterior with no barrier)



Span 5 deflection $\approx \frac{.009317 (72) [(122.5)(12)]^3}{5460 \cdot 2,947,200} \approx .132'' \times 1.33 = .176''$
input

Span 3 deflection $\approx \frac{72 [(125)(12)]^3}{(192) 5460 (2,947,200)} \approx .079'' \times 1.33 = .11''$
input


from SAP2000 RUNS
 all deflections $< \Delta/800$ ✓ okay
 max deflection $\approx 1.69'' < 1.875''$ ✓ okay

By: _____	Date _____	Project no. _____	Project code (SA#): _____
Chk'd: _____	Date _____	Structure no. _____	Sheet 109 of _____

COLORADO DEPARTMENT OF TRANSPORTATION
DESIGN COMPUTATIONS (Grid)

Phase 3 LA

Assume 50 psf construction loads



$$M = \frac{w l^2}{2}$$

width of slab $\approx 8'$

$$M \approx \frac{(8') (50 \text{ psf}) (12.083')^2}{2}$$

$$M \approx 29.2 \text{ ft-k}$$

$$25.6 \text{ ft-k @ } 9.33'' \\ = 3.2 \text{ ft-k/ft}$$

$$= 3.65 \text{ ft-k/ft for } 8' \text{ slab}$$

strength & stress okay for 50 psf load \checkmark ok

Deflections

$$\Delta_{\text{deck}} = \frac{w l^4}{8 E I}$$

$$E \approx 4883.57$$

$$I \approx 4096$$

DEAD WT

$$\Delta_{\text{DEAD}} \approx \frac{\left(\frac{1}{12}\right) 8' \left(\frac{8}{12}\right) (15 \text{ k/ft}) \left[(12.083') \left(\frac{12}{12}\right) \right]^4}{8 (4883.57) (4096)} = .184''$$

$$\Delta_{\text{const. loads}} \approx \frac{\frac{1}{12} 8' \left(\frac{250 \text{ k}}{8 \text{ ft}}\right) \left[(12.083') \left(\frac{12}{12}\right) \right]^4}{8 (4883.57) (4096)} \approx .092''$$

$$\text{TOTAL} \approx .276''$$

By: _____	Date _____	Project no. _____	Project code (SA#): _____
Chk'd: _____	Date _____	Structure no. _____	Sheet <u>110</u> of _____

Concrete Stress in Negative Moment Area (Overhang)

Overhang Length = 14.58 ft skewed length
 Distance to Start of Precast Slab = 0.00 Inches
 Support Girder Flange Width = 28.00 Inches
 Distance to Barrier Center of Mass = 0.00 ft
 width of barrier = 0.00 ft
 Wt of Barrier = 0.000 k/ft
 Asphalt Thickness = 0.00 inches
 Asphalt Weight = 12.22 lb/sf/inch asphalt
 Live Load = 4.16 k/lf (Input live load) 4.16
 ired Shear Support @ CLOSURE POUR = 0.00 k/lf "=6.4"

Mslab (-) = 9.53 ft kip/ft moment at 9.33 inches from support
 Mdc2 (barrier) (-) = 0.00 ft kip/ft moment at 9.33 inches from support
 Mdw (-) = 0.00 ft kip/ft moment at 9.33 inches from support
 M const LL- = 3.65 ft kip/ft moment at 9.33 inches from support
 50 psf

Compression Stress

$$f_{bottom} = Pe/A + Mslab/Sbot + (Mdc + Mdw + MLL)/Sbotc$$

$f_{max} = .6 f_c = 4.32$ ksi transient loads (DL+LL) (Table 5.9.4.2.1-1)
 $f_{bottom} = 2.74$ ksi
 $f_{bottom} \leq f_{max}$? **Okay**

$f_{max} = .45 f_c = 3.24$ ksi permanent loads (DL) (Table 5.9.4.2.1-1)
 $f_{bottom} = 2.28$ ksi
 $f_{top} \leq f_{max}$? **Okay**

$f_{max} = .40 f_c = 2.88$ ksi LL + 1/2DL (Table 5.9.4.2.1-1)
 $f_{bottom} = 1.60$ ksi
 $f_{bottom} \leq f_{max}$? **Okay**

Tension Stress

$$f_{top} = Pe/A + Mslab/Stop + (Mdc + Mdw + MLL)/Stop$$

$f_{top} = 0.028$ ksi
 Tension Limit = $.19 * \sqrt{f_c} = -0.510$ ksi (Table 5.9.4.2.2-1)
 $f_{top} \leq f_{max}$? **Okay**

Strength Checks

Interior Spans

STRENGTH I

$M_u = 1.25DC + 1.5DW + 1.75(LL+IM)$
 $M_{positive} = 259.96$ ft kip
 $M_{negative} = 221.92$ ft kip
 $M_r = \phi * M_n = 283.43$ ft kip
Okay

SERVICE I

$$M_u = DC + DW + (LL + IM)$$

By: _____ Date _____
 Chk'd: _____ Date _____

Project no. _____
 Structure no. _____

Project code (SA#) _____
 Sheet { } of { }

Design Computations

$$\begin{aligned} M_{\text{positive}} &= 157.59 \text{ ft kip} \\ M_{\text{negative}} &= 135.85 \text{ ft kip} \end{aligned}$$

Strength ChecksOverhangSTRENGTH I

$$\begin{aligned} M_u &= 1.25DC + 1.5DW + 1.75(LL + IM) \\ M_{\text{negative}} &= 159.13 \text{ ft kip} \end{aligned}$$

Development Length & Transfer Length (5.11.4)

$$\begin{aligned} l_d &= 83.41 \text{ inches} \\ l_{\text{transfer}} = 60 * d_b &= 36 \text{ inches} \\ \text{distance from edge of slab} &= 13.80 \text{ ft (distance is } > \text{ development length } \rightarrow \text{ Full Strength)} \\ l_{px} &= 165.63 \text{ inches This is greater than } l_d, \text{ use a smaller value} \\ f_{px} &= 245.59 \text{ ksi} \end{aligned}$$

for prestress only:

$$\begin{aligned} A_{ps} * f_{ps} &= .85 * f_c * b * a \\ a_{\sim} &= 1.2699 \text{ inches} \\ T_{\text{topstrand}} &= 29.24 \text{ ksi} \\ M_n &= A_{ps} * f_{ps} * (d_p - a/2) \\ M_n &= 314.92 \text{ ft kip} \\ \epsilon_t &= 0.01321 \text{ Tension Controlled} & (C5.7.2.1) \\ \phi &= 0.9 \\ M_r &= 283.43 \text{ ft kip} \end{aligned}$$

Okay

for prestress + mild reinforcing:

$$\begin{aligned} A_s * f_s + A_{ps} * f_{ps} &= .85 * f_c * b * a \\ \text{Mild bar size} &= \# 0 \\ \text{bar spacing} &= 24 \text{ inches} & f_y = 60 \text{ ksi} \\ A_s &= 0 \text{ in}^2 \\ a_{\sim} &= 1.2699 \text{ inches} \\ T_{\text{topstrand}} &= 29.24 \text{ ksi} \\ M_n &= A_{ps} * f_{ps} * (d_p - a/2) + A_s * f_s * (d_p - a/2) \\ M_n &= 314.92 \text{ ft kip} \\ \epsilon_t &= 0.01321 \text{ Tension Controlled} & (C5.7.2.1) \\ \phi &= 0.9 \\ M_r = \phi * M_n &= 283.43 \text{ ft kip} \end{aligned}$$

Okay

SERVICE I

$$\begin{aligned} M_u &= DC + DW + (LL + IM) \\ M_{\text{negative}} &= 112.70 \text{ ft kip} \end{aligned}$$


Okay for SERVICE

By: _____ Date _____
 Chk'd: _____ Date _____

Project no. _____
 Structure no. _____

Project code (SA#) _____
 Sheet 112 of _____

COLORADO DEPARTMENT OF TRANSPORTATION
DESIGN COMPUTATIONS (Grid)



for 8' slab

$$P \approx \frac{\text{Dead Load} + \text{Construction load}}{2}$$



$$P \approx \frac{(12.08 + 2) \left(\frac{8''}{12''}\right) (8') (.15 \text{ kcf}) + .05 \text{ ksf} (12.08') (8')}{2}$$

$$P \approx \frac{11.264 + 4.832}{2} = 8.05 \text{ K}$$

use 2 - 7/8" F-42 Loop Females

load = 5300 lbs each

total = 10.6 K




By: _____	Date _____	Project no. _____	Project code (SA#): _____
Chk'd: _____	Date _____	Structure no. _____	Sheet 113 of _____

COLORADO DEPARTMENT OF TRANSPORTATION
DESIGN COMPUTATIONS (Grid)

FALSEWORK

OPTION 1




$$M \approx (3)(4.1) \approx 12.3 \text{ ft k}$$

Use W6x12 $I=22.1$
 W8x10 or equal $I=30$

C8x11.5 $E=32.6$ $b_f=2.26''$
 MC10x22 $I=103$ $b_f=3.315''$

use MC 10 x 22

OPTION 2



$$M_{max} = \frac{Pl}{4}$$

$$M_{max} = \frac{Pab}{l}$$

$$M \approx 35.6 \text{ ft k}$$

$$M_{max} = \frac{(9.05)(19')}{4} \approx 38.3 \text{ ft k}$$

Use W10x33 or equal $I=170 \text{ in}^4$


W14x34 every other slab

could use as platforming over river

By: _____	Date _____	Project no. _____	Project code (SA#): _____
Chk'd: _____	Date _____	Structure no. _____	Sheet 114 of _____

COLORADO DEPARTMENT OF TRANSPORTATION
DESIGN COMPUTATIONS (Grid)

DECK @ Northwest Abutment



$$M_{max} = \frac{3 P l}{16}$$

2'-8"

$$M = \frac{3(16k)(3.25)}{16} \approx 9.75 \text{ ft k}$$

8.125

$$M_{ULT} = (1.75)(9.75) \approx 17.1 \text{ ft k}$$

for 10"

$$V_c \approx 10.72$$

for full cantilever

$$l \approx 2'-8"$$

$$M = (16k)(2'-8") \approx 42.72 \text{ k}$$

#8 @ 6"

$$M_{ULT} = (1.75)(42.72) \approx 74.8 \text{ k}$$

18" depth


@ 1'-4"

$$M = 21.33 \text{ k}$$

$$M_{ULT} = 37.33 \text{ k}$$

#8 @ 6"

13" depth



By: _____	Date _____	Project no. _____	Project code (SA#): _____
Chk'd: _____	Date _____	Structure no. _____	Sheet <u>115</u> of _____

REINFORCING DESIGN

GIVEN:

$f_y = 60.00$ ksi
 $f_c = 4.50$ ksi
 COVER = 2.00 inches
 $\Phi_{flexure} = 0.75$
 Beam Thickness (t_s) = 13.00 inches
 $b = 12.00$ inches
 bar diameter = 0.875 inches

Impact Steel

LOAD TYPE	M _h TOT ft-K	AS _{req'd} in ²
M _h (UNFACTORED)	21.33	0.56
STRENGTH I	37.33	1.01
SERVICE I	21.33	0.56

$d_s = 10.56$ inches
 per 5.10.8.2 A_{Stemp} = 0.23 sq inches

Use # 8 at top face min. spacing = 9.43 inches
 use spacing = 6.00 inches
 $A_s = 1.580$ sq. inches

compressive steel:

Use # 5 at bottom face
 $A_{s'} = 0.00$ sq. inches

$M_n = 74.79$ ft-K
 $M_r = 56.09$ ft-K

Reinforcing is okay

Maximum Reinforcement per 5.7.3.3.1-1 (Ductility Check)

$c = 2.50$ inches
 $d_e = d_s = 10.56$ inches (for no prestressing)
 $c/d_e = 0.24$

okay - member is not overreinforced

Minimum Reinforcement per 5.7.3.3.2

$1.2 * M_{cracking} = 17.21$ ft-K <--- Test 1
 $1.33 M_{hTOT} (max.) = 49.65$ ft-K <--- Test 2

Minimum Reinforcing is provided

Transverse Reinforcement per 9.7.3.2

Percentage of main reinforcement, $220 / \sqrt{S} \leq 67\%$

Girder Spacing = 15.25 ft
 Flange Width = 21 inches
 Flange Overhang = 18 inches
 Effective Length S = 15.00 ft
 $220 / \sqrt{S} = 56.80$ % Use **56.804** % of required main reinforcement
 Required $A_s = 0.90$ sq inches
 Use # 6 transverse reinforcement
 min. spacing = 5.88 inches

Design Computations

Crack Control per 5.7.3.4

$$f_y = 60.00 \text{ ksi}$$

$$f_{sa} = Z / (d_c \cdot A)^{1/3} \leq 0.6 \cdot f_y$$

$$d_c = \text{clear} + \text{dia.} / 2 = 2.5 \text{ in}$$

$$A = 30 \text{ in}^2$$

$$Z = 170 \text{ kip/in} \quad (\text{moderate exposure conditions})$$

$$\text{Maximum allowable } f_{sa} = 36.00 \text{ ksi}$$

Stress under service loads:

$$E_c = 33,000 \cdot (0.15)^{1.5} \cdot \text{sqrt}(f_c)$$

$$E_c = 4066.84 \text{ ksi}$$

$$E_s = 29000 \text{ ksi}$$

$$n = E_s / E_c = 7$$

$$(b/2)X^2 + (A_s n)X - (A_s n \cdot (t_s - d_c)) = 0$$

$$X = 3.573 \text{ in} \quad \text{compression depth of concrete at Service I Level}$$

$$c = 6.99 \text{ in}$$

Service load = DC + DW + (LL + IM)

$$M_u = 21.33 \text{ ft-K}$$

$$I_{\text{transform}} = 722.77 \text{ in}^4$$

$$f_s = n \cdot M(+)\cdot c / I_{\text{transformed}} = 17.33 < 36 \text{ ksi, Okay}$$

By: _____ Date _____
 Chk'd: _____ Date _____

Project no. _____
 Structure no. _____

Project code (SA#) _____
 Sheet 11 of 17

Design Computations

REINFORCING DESIGN

GIVEN:

$f_y = 60.00$ ksi
 $f_c = 4.50$ ksi
 COVER = 2.00 inches
 $\Phi_{flexure} = 0.75$
 Beam Thickness (t_s) = 18.00 inches
 $b = 12.00$ inches
 bar diameter = 0.875 inches

Impact Steel

LOAD TYPE	M_{hTOT} ft-K	$A_{Sreq'd}$ in ²
M_h (UNFACTORED)	42.72	0.76
STRENGTH I	74.80	1.36
SERVICE I	42.72	0.76

$d_s = 15.56$ inches
 per 5.10.8.2 $A_{Stemp} = 0.32$ sq inches

Use # 8 at top face min. spacing = 6.97 inches
 use spacing = 6.00 inches
 $A_s = 1.580$ sq. inches

compressive steel:

Use # 5 at bottom face
 $A_{s'} = 0.00$ sq. inches

$M_n = 114.29$ ft-K
 $M_r = 85.72$ ft-K

Reinforcing is okay

Maximum Reinforcement per 5.7.3.3.1-1 (Ductility Check)

$c = 2.50$ inches
 $d_e = d_s = 15.56$ inches (for no prestressing)
 $c/d_e = 0.16$

okay - member is not overreinforced

Minimum Reinforcement per 5.7.3.3.2

$1.2 * M_{cracking} = 32.99$ ft-K <--- Test 1
 $1.33 M_{hTOT} (max.) = 99.48$ ft-K <--- Test 2

Minimum Reinforcing is provided

Transverse Reinforcement per 9.7.3.2

Percentage of main reinforcement, $220 / \sqrt{S} \leq 67\%$

Girder Spacing = 15.25 ft
 Flange Width = 21 inches
 Flange Overhang = 18 inches
 Effective Length $S = 15.00$ ft
 $220 / \sqrt{S} = 56.80$ % Use **56.804** % of required main reinforcement
 Required $A_s = 0.90$ sq inches
 Use # 6 transverse reinforcement
 min. spacing = 5.88 inches

Design Computations

Crack Control per 5.7.3.4

$$f_y = 60.00 \text{ ksi}$$

$$f_{sa} = Z / (d_c * A)^{1/3} \leq 0.6 * f_y$$

$$d_c = \text{clear} + \text{dia.} / 2 = 2.5 \text{ in}$$

$$A = 30 \text{ in}^2$$

$$Z = 170 \text{ kip/in} \quad (\text{moderate exposure conditions})$$

$$\text{Maximum allowable } f_{sa} = 36.00 \text{ ksi}$$

Stress under service loads:

$$E_c = 33,000 * (0.15)^{1.5} * \text{sqrt}(f_c)$$

$$E_c = 4066.84 \text{ ksi}$$

$$E_s = 29000 \text{ ksi}$$

$$n = E_s / E_c = 7$$

$$(b/2)X^2 + (A_s n)X - (A_s n * (t_s - d_c)) = 0$$

$$X = 4.502 \text{ in}$$

compression depth of concrete at Service I Level

$$c = 11.06 \text{ in}$$

Service load = DC + DW + (LL + IM)

$$M_u = 42.72 \text{ ft-K}$$

$$I_{\text{transform}} = 1718.01 \text{ in}^4$$

$$f_s = n * M(+)*c / I_{\text{transformed}} = 23.10 < 36 \text{ ksi, Okay}$$

By: Date
 Chk'd: Date

Project no. .
 Structure no. .

Project code (SA#)
 Sheet of .

119

Design Computations

REINFORCING DESIGN

GIVEN:

$f_y = 60.00$ ksi
 $f_c = 4.50$ ksi
 COVER = 2.00 inches
 $\Phi_{flexure} = 0.75$
 Beam Thickness (t_s) = 13.00 inches
 $b = 12.00$ inches
 bar diameter = 0.875 inches

@ 2' from bottom

Impact Steel

LOAD TYPE	M _{hTOT} ft-K	A _{Sreq'd} in ²
M _h (UNFACTORED)	30.67	0.82
STRENGTH I	53.67	1.49
SERVICE I	30.67	0.82

$d_s = 10.56$ inches
 per 5.10.8.2 A_{Stemp} = 0.23 sq inches

Use # 8 at top face min. spacing = 6.35 inches
 use spacing = 6.00 inches
 A_s = 1.580 sq. inches

compressive steel:

Use # 5 at bottom face
 A_{s'} = 0.00 sq. inches

$M_n = 74.79$ ft-K
 $M_r = 56.09$ ft-K

Reinforcing is okay

Maximum Reinforcement per 5.7.3.3.1-1 (Ductility Check)

$c = 2.50$ inches
 $d_e = d_s = 10.56$ inches (for no prestressing)
 $c/d_e = 0.24$

okay - member is not overreinforced

Minimum Reinforcement per 5.7.3.3.2

$1.2 * M_{cracking} = 17.21$ ft-K <--- Test 1
 $1.33 M_{hTOT} (max.) = 71.38$ ft-K <--- Test 2

Minimum Reinforcing is provided

Transverse Reinforcement per 9.7.3.2

Percentage of main reinforcement, $220 / \sqrt{S} \leq 67\%$

Girder Spacing = 15.25 ft
 Flange Width = 21 inches
 Flange Overhang = 18 inches
 Effective Length S = 15.00 ft
 $220 / \sqrt{S} = 56.80 \%$ Use **56.804 %** of required main reinforcement
 Required A_s = 0.90 sq inches
 Use # 6 transverse reinforcement
 min. spacing = 5.88 inches

By: Date
 Chk'd: Date

Project no. .
 Structure no. .

Project code (SA#)
 Sheet of

REINFORCING DESIGN

GIVEN:

fy= 60.00 ksi
 fc= 4.50 ksi
 COVER= 2.00 inches
 $\Phi_{flexure}$ = 0.75
 Beam Thickness (ts)= 10.00 inches
 b= 12.00 inches
 bar diameter= 0.875 inches

@ 3' from barrier

Impact Steel

LOAD TYPE	M _{hTOT} ft-K
M _h (UNFACTORED)	20.00
STRENGTH I	35.00
SERVICE I	20.00

AS _{req'd} in ²
0.75
1.40
0.75

ds= 7.56 inches
 per 5.10.8.2 A_{Temp}= 0.18 sq inches

Use # 8 at top face min. spacing = 6.74 inches
 use spacing= 6.00 inches
 As= 1.580 sq. inches

compressive steel:

Use # 5 at bottom face
 As'= 0.00 sq. inches

M_n= 51.09 ft-K
 M_r= 38.32 ft-K

Reinforcing is okay

Maximum Reinforcement per 5.7.3.3.1-1 (Ductility Check)

c= 2.50 inches
 de=ds= 7.56 inches (for no prestressing)
 c/de= 0.33

okay - member is not overreinforced

Minimum Reinforcement per 5.7.3.3.2

1.2*M_{cracking}= 10.18 ft-K <--- Test 1
 1.33M_{hTOT} (max.)= 46.55 ft-K <--- Test 2

Minimum Reinforcing is provided

Transverse Reinforcement per 9.7.3.2

Percentage of main reinforcement, 220 / sqrt(S) <= 67%

Girder Spacing = 15.25 ft
 Flange Width = 21 inches
 Flange Overhang = 18 inches
 Effective Length S = 15.00 ft
 220 / sqrt(S) = 56.80 % Use **56.804** % of required main reinforcement
 Required As = 0.90 sq inches
 Use # 6 transverse reinforcement
 min. spacing = 5.88 inches

REINFORCING DESIGN

GIVEN:

$f_y = 60.00$ ksi
 $f_c = 4.50$ ksi
COVER = 2.00 inches
 $\Phi_{flexure} = 0.75$
Beam Thickness (t_s) = 8.00 inches
 $b = 12.00$ inches
bar diameter = 0.875 inches

@ 4' from barrier

Impact Steel

LOAD TYPE	M _{hTOT} ft-K	AS _{req'd} in ²
M _h (UNFACTORED)	9.33	0.47
STRENGTH I	16.33	0.87
SERVICE I	9.33	0.47

$d_s = 5.56$ inches
per 5.10.8.2 A_{Stemp} = 0.14 sq inches

Use # 8 at top face min. spacing = 10.86 inches
use spacing = 6.00 inches
A_s = 1.580 sq. inches

compressive steel:

Use # 5 at bottom face
A_{s'} = 0.00 sq. inches

M_n = 35.29 ft-K
M_r = 26.47 ft-K

Reinforcing is okay

Maximum Reinforcement per 5.7.3.3.1-1 (Ductility Check)

$c = 2.50$ inches
 $d_e = d_s = 5.56$ inches (for no prestressing)
 $c/d_e = 0.45$

not good - member is overreinforced

Minimum Reinforcement per 5.7.3.3.2

$1.2 \cdot M_{cracking} = 6.52$ ft-K <--- Test 1
 $1.33 M_{hTOT} (max.) = 21.72$ ft-K <--- Test 2

Minimum Reinforcing is provided

Transverse Reinforcement per 9.7.3.2

Percentage of main reinforcement, $220 / \sqrt{S} \leq 67\%$

Girder Spacing = 15.25 ft
Flange Width = 21 inches
Flange Overhang = 18 inches
Effective Length S = 15.00 ft
 $220 / \sqrt{S} = 56.80\%$ Use **56.804** % of required main reinforcement
Required A_s = 0.90 sq inches
Use # 6 transverse reinforcement
min. spacing = 5.88 inches

COLORADO DEPARTMENT OF TRANSPORTATION
DESIGN COMPUTATIONS (Grid)

GIRDER DESIGN

By: Date	Project no.	Project code (SA#):
Chk'd: Date	Structure no.	Sheet of

DECK POST-TENSIONING LOSSES

5.9.5.2.1 Anchorage Set

per C5.9.5.1 Anchorage loss $\approx 3\%$

anchor set loss = $\frac{3}{8}'' = \Delta L$

$$\Delta f = \frac{E \Delta L}{6x}$$

$L \approx 366.25'$ from anchor to anchor tension from both sides

$$x = \sqrt{\frac{E (\Delta L) L}{12 d}}$$

$L_{max} \approx 184'$


$$d = .75 (270) \left(1 - e^{[-(0.0002) 184' + .25 (.00873)]} \right)$$

$d \approx 6.89 \text{ ksi}$ ($\approx 3.4\%$) 6.85

$$x = \sqrt{\frac{(28500 \text{ ksi}) (.375'') 184'}{(12) (6.89 \text{ ksi})}}$$

$x = 154.2''$ 154.67

$$\Delta f = \frac{(28500)(.375)}{(6) 154.2} \approx 11.55 \text{ ksi}$$




$$\frac{(154.2 - 139')}{154.2} = \frac{\Delta f_{pier}}{11.55}$$

$\Delta f_{pierA} \approx 1.14 \text{ ksi}$ ← loss @ pier

5.6.2 Derivation of Formulas for Calculating the Effects of Anchor Set

The effects of anchor set on tendon stresses may be calculated with sufficient accuracy for most conventional applications in accordance with the diagram and formulas presented below.



- Δf = Change in stress due to anchor set, ksi
- d = Friction loss in length, L, ksi
- x = Length influenced by anchor set, ft
- L = Length to point where loss is known, ft
- ΔL = Anchor set, in.
- E = Modulus of elasticity, ksi

$$E = \frac{\text{Unit Stress}}{\text{Unit Strain}} = \frac{f_{avg}}{\Delta L/x} = \frac{f_{avg} x}{\Delta L}$$

$$f_{avg} = \frac{E \Delta L}{x}$$

$$\frac{\Delta f}{2} = \frac{E \Delta L}{12x} \quad \text{Units Correct}$$

$$\Delta L = \frac{P_{avg} x}{A E} = \frac{f_{avg} x}{E}$$

$$f_{avg} = \frac{E \Delta L}{x}$$

$$\frac{\Delta f}{2} = \frac{E \Delta L}{12x} \quad \text{Units Correct}$$

$$\Delta f = \frac{E \Delta L}{6x} \quad \Delta L \ \& \ x \ \text{Known}$$

by similar triangles

$$\frac{x}{\Delta f/2} = \frac{L}{d}$$

$$\Delta f = \frac{2 x d}{L} \quad x \ \text{Known}$$

$$x = \frac{\Delta f L}{2d}$$

$$x = \frac{E \Delta L L}{6x \ 2d}$$

$$x^2 = \frac{E (\Delta L) L}{12 \ d}$$

$$x = \sqrt{\frac{E(\Delta L)L}{12 \ d}} \quad \Delta L \ \text{Known}$$

Also from $\Delta f = \frac{E \Delta L}{6x}$ & $\Delta f = \frac{2 x d}{L}$

$$x = \frac{E \Delta L}{6 \Delta f} = x = \frac{L \Delta f}{2d}$$

$$\Delta f^2 = \frac{E \Delta L d}{3L}$$

$$\Delta f = \sqrt{\frac{E \Delta L d}{3L}} \quad \Delta L \ \text{Known}$$

When measuring anchor set, the tendon elongation within the jack must be considered:

- Jacking to .75f's = .75(270) = 202.5 ksi
- 5/8" required anchor set
- 4' jack used (ΔL)
- E = 27 x 10³ ksi

$$\Delta L = \frac{f L}{E} = \frac{202.5 \ 4 \times 12}{27 \times 10^3} = .36''$$

Total elongation lost during anchor set

$$\begin{aligned} &= \Delta L + 5/8'' \\ &= .36'' + .625'' \\ &= 1'' \pm \end{aligned}$$

For simplicity use ΔL

$$= 1/12'' \ \text{per foot of jack.}$$

DECK POST-TENSIONING LOSSES (cont.)

5.9.5.2.2 Friction


$$\Delta f_{pF} = f_{pj} (1 - e^{(-kx + \mu \alpha)}) \quad (5.9.5.2.2 b-1)$$

$$k = .0002$$

Table 5.9.5.2.2 b-1

$$\mu = .23$$

$$X_{total} = 86' + 148' + 134' = 368'$$



assume post tensioning from both ends

$$X_{max} = 368/2 \approx 184'$$

$$X_{max \text{ to pier}} \approx 139' \pm$$

assume $\alpha \approx 0.50^\circ = .00873$ radians

$$\Delta f_{pF} = (.75)(270) (1 - e^{[-(.0002)(139') + .25(.00873)])}$$

$$\Delta f_{pF} \approx \frac{5.12 \text{ Ksi}}{5.12} \leftarrow (-2\frac{1}{2} \%) \quad \text{loss @ pier}$$

5.12

By: _____	Date _____	Project no. _____	Project code (SA#): _____
Chk'd: _____	Date _____	Structure no. _____	Sheet <u>125</u> of _____

**COLORADO DEPARTMENT OF TRANSPORTATION
DESIGN COMPUTATIONS (Grid)**

		<u>Anchorage Loss</u>	<u>Friction Loss</u>	<u>KL/πE</u>
Pier 2	point 1.0	11.55 ksi	0	0
	point 2.0 ≈ 73.6'	6.04 ksi	2.52 ksi	.017
	point 3.0 ≈ 96.6'	4.31 ksi	3.44 ksi	.021
Pier 3	point 4.0 ≈ 144.6'	.72 ksi	5.34 ksi	.031
	point 5.0 ≈ 121.6'	2.44 ksi	4.43 ksi	.026
	point 6.0	11.55 ksi	0	0
Initial Stress Ratio =		$\frac{.75(270) - 6.04 - 2.52 - 2.63}{.75(270)} = .945$		
		<u>ISR (without ES)</u>		
	pt 2	.958		
	pt 3	.962		
	pt 4	.970		
	pt 5	.966		
	pt 1	.943		
	pt 6	.943		
		↑		
		USE		
Elastic Shortening is recovered during jacking process 2.63 ksi)				

By: _____	Date _____	Project no. _____	Project code (SA#): _____
Chk'd: _____	Date _____	Structure no. _____	Sheet <u>126</u> of _____

COLORADO DEPARTMENT OF TRANSPORTATION
DESIGN COMPUTATIONS (Grid)

Elongation

$$\Delta = \frac{f_s L}{E_s} = \frac{.75(270) * 366.25' * 12''/ft}{29500}$$

$$\Delta = 31.23''$$

friction loss + anchorage loss @ 5.0 = 2.44 + 4.43 = 6.87 Ksi @ Controls

$$\Delta = \frac{6.87 (366.25)(12'')}{29500} = 1.06''$$

friction loss + anch. loss @ 4.0 = 5.34 + .72 = 6.06 K

$$\Delta = \frac{6.06 (366.25)(12'')}{29500} = .934''$$

friction loss & anchor loss @ 2.0 = 6.04 + 2.52 = 8.56 Ksi @ Controls

friction loss & anchor loss @ 3.0 = 4.31 + 3.44 = 7.75 Ksi

$$\Delta = \frac{(8.56) (366.25)(12'')}{29500} \approx 1.32''$$

$$\text{max} \approx 31.23 + 1.32 \approx 32.55''$$

By: Date	Project no.	Project code (SA#):
Chk'd: Date	Structure no.	Sheet 127 of


5.9.5.2.3 b

ELASTIC SHORTENING

$$\Delta f_{p ES} = \frac{N-1}{2N} \frac{E_p}{E_c} f_{cgp} \quad (5.9.5.2.3b-1)$$

or

$$\Delta f_{p ES} = \frac{N-1}{2N} \frac{A_{ps} f_{pb} (I_g + e_m^2 A_g) - e_m M_g A_g}{A_{ps} (I_g + e_m^2 A_g) + \frac{A_g I_g E_c}{E_p}} \quad (5.9.5.2.3b-1)$$



assume 10 conduit with 4 strand each
 $N = 40$

$$A_{ps} = (10)(4)(.217) = \underline{8.68 \text{ in}^2}$$

$$f_{pb} \approx .9 f_{py} \quad \text{or} \quad .74 f_{pu}$$

$$f_{py} = .9 f_{pu} \approx .9 (270) = 243 \text{ ksi}$$

$$f_{pb} \approx \begin{matrix} .9 f_{py} \\ 218.7 \end{matrix} \quad \text{or} \quad \begin{matrix} .74 f_{pu} \\ 199.8 \end{matrix} \text{ ksi}$$

use $f_{pb} = \underline{218.7 \text{ ksi}}$ (conservative)

$$M_{g \text{ dead}} \approx 483 \text{ ft-k}$$

$$M_{\text{self wt}} = 3875.3 \text{ ft-k}$$

neg. moment = .1 $w l^2$

$$l = 148'$$

$$w = (25') \left(\frac{8''}{12''} \right) .15 \text{ k/ft} \approx 2.5 \text{ k/ft}$$

$$M_g \approx (.1)(2.5)(148)^2 \approx 5476 \text{ ft-k} = \underline{65712 \text{ in-kip}}$$



$$E_c = \underline{4069.64 \text{ ksi}}$$

$$E_p = \underline{28500 \text{ ksi}}$$

$$e_m \approx 0$$

$$A_g = (25') \left(\frac{12''}{12} \right) 8'' = 2400 \text{ in}^2$$

$$I_g = \frac{b h^3}{12} = \frac{(25)(12)(8)^3}{12} \approx 12800$$

By: Date	Project no.	Project code (SA#):
Chk'd: Date	Structure no.	Sheet 28 of

COLORADO DEPARTMENT OF TRANSPORTATION
DESIGN COMPUTATIONS (Grid)

$$\Delta f_{pes} = \frac{40 - 1}{2(40)} \frac{(8.68) 218.7 (12800 + 0) - 0}{8.68 (12800 + 0) + 2400 (12800)} = \frac{4069.64}{28500}$$

$$\Delta f_{pes} = \underline{2.63 \text{ Ksi}} \quad \leftarrow$$

2.18 Ksi
for 33 strands

TIME DEPENDENT LOSSES

$$\Delta f_{psR} \approx \phi$$

$$\Delta f_{psCR} \approx \phi$$

$$\Delta f_{psR1} \approx \phi$$

$$\Delta f_{psR2} = 7.2 \text{ Ksi} \quad (= \Delta f_{psR1})$$

$$\Delta f_{psD} = \text{TBD}$$


$$\Delta f_{psC} = \text{TBD}$$

SHRINKAGE LOSS

$$\Delta f_{psD} = \epsilon_{shf} E_p k_{df}$$

$$k_{df} = \frac{1}{1 + \frac{E_p}{E_{ci}} \frac{A_{ps}}{A_c} \left(1 + \frac{A_c e_{pc}^2}{I_c} \right) \left[1 + .7 \psi_b (t_f, t_i) \right]}$$

COLORADO DEPARTMENT OF TRANSPORTATION
DESIGN COMPUTATIONS (Grid)



$$A_g \approx 5450.77 \text{ in}^2$$

$$I_{gg} \approx 3751787 \text{ in}^4$$

$$y_{cg} \approx 47.761 \text{ in}$$

$$f'_c = 4.5 \text{ ksi}$$

$$E_c \approx 3860.80$$

$$A_{deck} = 8" \times 25' \approx 2400 \text{ in}^2$$

$$I_{gdeck} = 12800 \text{ in}^4$$

$$f'_c = 7.2 \text{ ksi}$$

$$E_c \approx 4883.57$$

$$n = .79$$

$$A_c = 2400 \text{ in}^2 + \frac{3860.8}{4883.57} (5450.77) = \underline{6709.21 \text{ in}^2}$$

$$y_c = \frac{(.79)(5450.77)(47.761) + 2400 \text{ in}^2(88")}{(.79)(5450.77) + 2400 \text{ in}^2}$$

$$y_c \approx 62.16"$$

$$I_c = 3751787 + .79(5450.77) (62.16 - 47.761)^2$$

$$+ 12800 + 2400 (62.16 - 88")^2$$

$$I_c \approx \underline{6,259,871 \text{ in}^4}$$

$$e_{pc} \approx 62.16" - 88" \approx \underline{25.84"}$$

$$\psi(t_f, t_c) = 1.9 K_s K_{hc} K_F K_{td} t_c^{-.118} \quad (5.4.2.3.2-1)$$

$$K_s = 1.45 - .13(1/5) \geq 1.0 \quad (5.4.2.3.2-2)$$

$$1/5 = \frac{45.358 - 7.5}{16.42467} \approx 2.3$$

By: Date	Project no.	Project code (SA#):
Chk'd: Date	Structure no.	Sheet <u>130</u> of

COLORADO DEPARTMENT OF TRANSPORTATION
DESIGN COMPUTATIONS (Grid)

$$K_s = 1.45 - .13(2.3) \approx \underline{1.15}$$

$$K_{hc} = 1.56 - .008 H$$

(5.4.2.3.2-3)

$$H = 55\%$$

$$K_{hc} = \frac{1.56 - .008(55)}{\underline{1.12}}$$

$$K_f = \frac{5}{1 + f'_{ci}}$$

(5.4.2.3.2-4)

$$f'_{ci} = .8 f'_c = .8(4.5) \approx 3.6 \text{ ksi}$$

of concrete class D

$$K_f = \frac{5}{1 + 3.6} \approx .833$$

$$f'_{ci} = 5 \text{ ksi for deck slabs}$$

$$= 7.2 \text{ ksi for post-tensioning}$$

$$K_{td} = \left(\frac{t}{61 - 4f'_{ci} + t} \right)$$

(5.4.2.3.2-5)

$$t = 18250$$

$$K_{td} = \frac{18250}{61 - 4(5) + 18250} \approx .998$$

$$t_i \approx 30 \text{ days}$$

$$\psi(t_f, t_i) = 1.9 (1.15) (1.12) (.833) (.998) 30^{-.118}$$

$$\psi(t_f, t_i) \approx 1.362$$

By: Date	Project no.	Project code (SA#):
Chk'd: Date	Structure no.	Sheet 131 of

COLORADO DEPARTMENT OF TRANSPORTATION
DESIGN COMPUTATIONS (Grid)

(5.9.5.4.3a-2)

$$K_{df} = \frac{1}{1 + \frac{E_p}{E_c} \frac{\Delta f_s}{A_c} \left(1 + \frac{A_c e_{pc}^2}{I_c}\right) \left[1 + .7 \psi_0 (t_f, t_i)\right]}$$

$$K_{df} = \frac{1}{1 + \frac{28500}{3860.8} \left(\frac{8.68}{5806.73}\right) \left(1 + \frac{5806.73 (25.84)^2}{6259871}\right) + \left[1 + .7 (1.382)\right]}$$

$$K_{df} \approx \underline{.338}$$

$$\Delta f_{psD} = \epsilon_{bdf} E_p K_{df}$$

$$\epsilon_{bdf} = K_s k_{hs} K_f K_{ed} (0.48 \times 10^{-3}) \quad 5.4.2.3.3-1$$

$$K_s = 1.15$$

$$K_{hs} = 2 - .014 H = 2 - .014 (55) = \underline{1.992}$$

$$K_f = 1.833$$

$$K_{ed} = .998$$

$$\epsilon_{bdf} \approx (1.15)(1.992)(1.833)(.998)(0.48 \times 10^{-3}) = .000914$$

$$\Delta f_{psD} = (.000914)(28500)(.338)$$

$$\Delta f_{psD} = 8.81 \text{ Ksi}$$

COLORADO DEPARTMENT OF TRANSPORTATION
DESIGN COMPUTATIONS (Grid)

CREEP LOSS

$$\Delta F_{PCD} = \frac{E_p}{E_{ci}} f_{cgp} [\psi_b(t_f, t_i) - \psi(t_d, t_i)] K_{df}$$

$$+ \frac{E_p}{E_c} \Delta f_{CO} \psi(t_f, t_d) K_{df} \quad (5.9.5.4.36-1)$$

$K_{df} = .338$

$E_p = 29500 \text{ ksi}$

$E_{ci} = 4883.57 \quad [3860.8 \text{ ksi Pier Concrete}]$

$$f_{cgp} = \frac{P_t}{A} + \frac{P_t e}{I} y + \frac{M_g y}{I}$$

$P_t = (5)(4)(.217) (.74)(270) = 188.17 \text{ kips}$

$A = 6709.21 \text{ in}^2$

$e \approx 25.84''$

$I_c = 6259871 \text{ in}^4$

$M_g = \phi @ \text{ pier (selfweight)}$

$$f_{cgp} = \frac{188.17}{6709.21} + \frac{188.17(25.84)(25.84)}{6259871} + 0$$

$f_{cgp} \approx .048 \text{ ksi}$

$$\psi(t_s, t_i) = 1.9 K_s K_{hc} K_f K_{td} t_c^{-.118}$$

$K_s = 1.15$

$K_{hc} = 1.12$

$t_i = \text{age of concrete at time of load application} \approx 30 \text{ days}$
 $t_f = 18250 \text{ days (50 yrs)}$
 $t_d = \text{age at deck placement}$

By: _____	Date: _____	Project no. _____	Project code (SA#): _____
Chk'd: _____	Date: _____	Structure no. _____	Sheet 133 of _____

COLORADO DEPARTMENT OF TRANSPORTATION
DESIGN COMPUTATIONS (Grid)

$f'_{ci} = 5 \text{ ksi}$ for slabs

$$K_f = \frac{5}{1 + f'_{ci}}$$

$$K_f = \frac{5}{1 + 5} = \underline{.8333}$$

$$\underline{K_{td} = .998}$$

$$\psi(t_f, t_i) = 1.9 (1.15)(1.12)(.833)(.998) 30^{-.118}$$

$$\underline{\psi(t_f, t_i) = 1.362}$$

$$\underline{K_{df} = .338}$$

$$t_i = t_d \approx 30 \text{ days}$$

$$\psi(t_f, t_d) = \underline{1.362}$$

$$\psi(t_d, t_i) = 1.9 K_s K_{hc} K_f K_{td} t_i^{-.118}$$

$$K_s = 1.15$$

$$K_{hc} = 1.12$$

$$K_f = .833$$

$$K_{td} = \frac{t}{61 - 4f'_{ci} + t} = \frac{30}{61 - 4(5) + 30} = .423$$

$$\psi(t_d, t_i) = 1.9 (1.15)(1.12)(.833)(.423) 30^{-.118}$$

$$\psi(t_d, t_i) = \underline{.577}$$

By: Date	Project no.	Project code (SA#):
Chk'd: Date	Structure no.	Sheet <u>134</u> of <u> </u>

COLORADO DEPARTMENT OF TRANSPORTATION
DESIGN COMPUTATIONS (Grid)

long term losses between transfer
 & deck placement ≈ 0

deck weight $\approx \phi$

Super imposed loads = DW

$$\Delta f_{cd} = \frac{\Delta P}{A_c} + \frac{\Delta P e_y}{I_c} + \frac{M_g y}{I_g} + \frac{M_{cd} y}{I_c}$$

$$M_{cd} \approx 574 \text{ ft k}$$

$$\Delta f_{cd} = \frac{(574)(12)(25.84)}{6259871} \approx \underline{.0284}$$

$$\Delta f_{PLD} \approx \frac{28500}{4883.57} (.048) [1.362 - .577] .338$$

$$+ \frac{28500}{4883.57} (.0284) (1.362) .338$$

$$\Delta f_{PLD} = .15 \text{ ksi}$$

By: Date	Project no.	Project code (SA#):
Chk'd: Date	Structure no.	Sheet 135 of

TOTAL POST-TENSIONING LOSSES

$\Delta f_{perA} = 1.12 \text{ ksi}$ anchorage set

$\Delta f_{pf} = 5.16 \text{ ksi}$ friction loss

$\Delta f_{pes} \approx 2.73 \text{ ksi}$ Elastic Shortening


$\Delta f_{prz} = 1.2 \text{ ksi}$ Relaxation

$\Delta f_{psd} \approx 8.81 \text{ ksi}$ Shrinkage

$\Delta f_{pcd} \approx 0.15 \text{ ksi}$ Creep

Total \approx 19.17 ksi \leftarrow
Loss


lead pencil - HL93
 blue pencil - DW
 purple pencil - Bridge Rail
 green pencil - deck load
 orange pencil - deck load Phase 3 & 4
 brown pencil - Haunch



	PH 3 & 4	OTHER
Span 3 - $M_o = 21393$		19738
Span 2 - $M_o = 22021$		19021
Span 1 - $M_o = 9484$		8869

90'
75'

lead pencil - HL93
 blue pencil - DW
 purple pencil - Bridge Rail
 green pencil - deckland
 orange pencil - deckbad Phase 3 & 4
 brown pencil - Haunch




	PH 3 & 4	OTHER
Span 3 - $M_u =$	21393	19738
Span 2 - $M_u =$	22021	19021
Span 1 - $M_u =$	9484	8869

80'

75'

STRENGTH

5 @ 12" nominal
 ≈ .31 m² @ 25'
 ≈ 7.75 m² @ each level
 use 15 m² @ center



$$C = \frac{A_{ps} f_{ps} + A_s f_s}{.85 f'_c \beta b}$$

5.7.3.1.2-4

FOR MILD STEEL ONLY

$$C = \frac{(15)(60)}{.85(4.5)(.825)(54")}$$

$$C \approx 5.282"$$

$$a = \beta C$$

$$M_n = A_s f_s (d_s - a/2)$$

(5.7.3.2.2-1)

$$M_n = 15(60) \left(72 + 5.25 + 4 - \frac{.825(5.282)}{2} \right)$$

$$M_n \approx 71164 \text{ in kip} \approx 5930.3 \text{ ft kip}$$

FOR POST TENSIONING ONLY

9 1/2 conduits (min)
 11 conduits (max)

min. 9 1/2 + 4 strands ≈ 38 strands for ultimate
 loss ≈ 19.17 ksi

$$C = \frac{38(.217) [.75(270) - 19.17]}{.85(4.5)(.825)(54")}$$

$$C \approx 8.872"$$

$$M_n = A_{ps} f_{ps} (d_p - a/2) + A_s f_s (d_s - a/2) \quad (5.7.3.2.2-1)$$

$$M_n = 38(.217) [.75(270) - 19.17] \left[72 + 5.25 + 4 - \frac{.825(8.872)}{2} \right]$$

$$M_n \approx 117296 \text{ in kip} \approx 9774.7 \text{ ft kip}$$

$$M_R = \phi M_n = .9(9774.7) \approx 8797.2 \text{ ft kip}$$

By: Date	Project no.	Project code (SA#):
Chk'd: Date	Structure no.	Sheet 138 of

COLORADO DEPARTMENT OF TRANSPORTATION
DESIGN COMPUTATIONS (Grid)

$$M_u \approx 4394(1.75) + 1536(1.5) + 308(1.25) \quad (\text{from SAP 2000})$$

$$M_u \approx 10378.5 \text{ ft k}$$

$$M_R(\text{min}) = 1.33 M_u = 13803.4 \text{ ft k @ bearing} \quad (5.7.3.3.2)$$

FOR MILD STEEL + POST TENSIONING

3% drop to end of girder

$$C = \frac{38(.277)[.75(270) - 19.17] + 15(60)}{.85(4.5)(.825)(54")}$$

$$M_R(\text{min}) = 13390 \text{ ft k}$$

$$C \approx 14.153"$$

$$a \approx b_c = .825(14.15) = 11.68$$

$$M_n = 38(.277)[.75(270) - 19.17] \left[72" + 5.25" + 4" - \frac{.825(14.153)}{2} \right] + 15(60) \left[72" + 5.25" + 4" - \frac{.825(14.153)}{2} \right]$$

$$M_n = 114003.1 + 67870.7 = 181873.8 \text{ in kip}$$

$$M_n \approx 15156.1 \text{ ft k}$$

$$M_R = \phi M_n = .9(15156.1) = 13640.5 \text{ ft k}$$

$M_R > M_u$ ✓ okay

$$M \text{ Mild Steel Required} = 10378.5 - .9 \left(\frac{114003.1}{12} \right) = 1828.3 \text{ ft k}$$

$$M \text{ Mild Steel Provided} = \frac{67870.7}{12} = 5655.9 \text{ ft k}$$

$$\frac{A_{s \text{ reqd}}}{A_{s \text{ provided}}} = \frac{M_{\text{reqd}}}{M_{\text{provided}}} = \frac{1828.3}{5655.9} \approx .323 \quad \text{need } 32.3\% \text{ of steel strength}$$

$$l_{hb} = \frac{38.0 d_b}{\sqrt{f_c}} = \frac{38(5/8)}{\sqrt{7.4}} = 8.73" \quad (5.11.2.4.1-1)$$



$$l_{dh} = (1.2) (1.7) (1.323) (8.73") \approx 2.37" > 6"$$

epoxy side cover > 2.5" As reqd Approved

distance past joint = 3.5" $3.5/6 = 58.3\%$ strength provided

$$M_n = [14003.1 + .583(67870.7)]^{1/2} = 12797.6 \text{ ft k}$$

$$M_R = .9(12797.6) = 11517.9 \text{ ft k} > M_u \quad \checkmark \text{ okay}$$

By: _____	Date: _____	Project no. _____	Project code (SA#): _____
Chk'd: _____	Date: _____	Structure no. _____	Sheet 139 of _____

COLORADO DEPARTMENT OF TRANSPORTATION
DESIGN COMPUTATIONS (Grid)

STRENGTH @ GIRDER BEARING

girder = 9 ksi $\beta = .6$

$$C = \frac{38(.217) [.75(270) - 19.17] + 15 (60)}{.85 (9.0) .6 (54")}$$

$$C = 9.73"$$

$$M_n = A_{ps} f_{ps} (d_p - a/2) + A_s f_s (d_s - a/2)$$

$$M_n = 38 (.217) [.75(270) - 19.17] \left[72" + 5.25" + 4" - \frac{.6(9.73)}{2} \right] + 15(60) \left[72" + 5.25" + 4" - \frac{.6(9.73)}{2} \right]$$

$$M_n \approx (118416.0 + 70497.9) \frac{1}{2}$$

$$M_n = 15742.8 \text{ ft-k}$$

$$M_R = (.9) (15742.8) \approx 14168.5 \text{ ft-k}$$


$$M_R > M_u \quad \text{okay} \quad M_u \approx 10378.5 \text{ ft-k}$$

By: Date	Project no.	Project code (SA#):
Chk'd: Date	Structure no.	Sheet 140 of

COLORADO DEPARTMENT OF TRANSPORTATION
DESIGN COMPUTATIONS (Grid)

$$f_{top} = \frac{P_e}{A} + \frac{M_c}{I}$$

Assumed Pier Section



$$I = 2256570 \text{ in}^4$$

$$Y_{cg} = 41.25''$$

$$A = 4150.57 \text{ in}^2$$

Girder Info

$$I = 1154251.7 \text{ in}^4$$

$$Y_{cg} = 35.84''$$

$$A = 1765.15 \text{ in}^2$$

$$M_{service \text{ @ bearing}} \approx 4394 + 1536 + 308 = 6238 \text{ ft K}$$

Max

By: _____	Date _____	Project no. _____	Project code (SA#): _____
Chk'd: _____	Date _____	Structure no. _____	Sheet <u>141</u> of _____

COLORADO DEPARTMENT OF TRANSPORTATION
DESIGN COMPUTATIONS (Grid)

PIER PROPERTIES

8" Deck, 25' wide

assume 4" of haunch
 $f'_c = 4.5$ $E = 3860.80$
 $f'_{c \text{ deck}} = 7.2 \text{ Ks.}$ $E = 4883.57$
 $f'_{c \text{ girder}} = 9 \text{ Ks.}$ $E = 5460.0$

$$\bar{Y}_g = \frac{41.25 (4150.57) + \frac{4883.57}{3860.80} (25' \times 12') (8") \times (72 + 4 + 4)}{4150.57 + \frac{4883.57}{3860.80} (25' \times 12') (8")}$$

$\bar{Y}_g = 57.61$

$$I_{comp} \approx 2256570 + (4150.57) (57.61 - 41.25)^2 + \frac{1}{12} (25)(12) \left(\frac{4883.57}{3860.80} \right) 8^3 + \frac{4883.57}{3860.80} (25)(12)(8") (57.61 - 80")^2$$

$I_{comp} \approx 4905536.2$

$$S_{comp \text{ top}} \approx \frac{I}{c} = \frac{4905536}{(84 - 57.61)} \approx 185886.2 \text{ in}^3$$

for 28 strands

$$f_{top} = \frac{P}{A} + \frac{M_c}{I} = \frac{P}{A} + \frac{M}{S}$$

$$f_{top} = \frac{(.74(270) - 19.17) 28(.217)}{(25)'(12'/ft)(8")} + \frac{-(6238)(12)}{-185886.2}$$

$f_{top} = .457 - .403 \approx .054 = 54 \text{ psi (Compression)}$
 6201 psi ✓ okay

for 33 strands

$$f_{top} = \frac{(.74(270) - 19.17) 33(.217)}{25(12)(8)} - .403$$

$f_{top} = 539 - 403 \approx 136 \text{ psi (Compression)} \quad \checkmark \text{ okay}$

By: _____	Date _____	Project no. _____	Project code (SA#): _____
Chk'd: _____	Date _____	Structure no. _____	Sheet 142 of _____

COLORADO DEPARTMENT OF TRANSPORTATION
DESIGN COMPUTATIONS (Grid)

@ 4 Bearing

$$y_{cg} = \frac{(.35.84) (1765.15) + \frac{4883.57}{54607} (25' + 12''/ft) 8'' * (72 + 4 + 4)}{1765.15 + \frac{4883.57}{5460} (25' + 12'') (8'')}$$

$$y_{cg} = 60.07 \text{ in}$$

$$I_{comp} \approx 1154251.7 + 1765.15 (60.07 - 35.84)^2 + \frac{1}{12} (25)(12) \left(\frac{4883.57}{5460}\right) (8'')^3 + \frac{4883.57}{5460} (25')(12''/ft) 8'' (60.07 - 80)^2$$

$$I_{comp} \approx 3053098.3 \text{ in}^4$$

$$S_{comp \text{ top}} \approx \frac{I}{c} = \frac{3053098.3}{(84 - 60.07)} \approx 127584.55 \text{ in}^3$$

for 28 strands

$$f_{top} \approx \frac{(.74)(270) - (9.17) 28(217)}{25' (12''/ft) (8'')} - \frac{6238 (12)}{127584.5}$$

$$f_{top} = .457 - .597 \approx -.130 \text{ ksi} = -130 \text{ psi (tension)}$$

< 500 ✓ okay

for 33 strands

$$f_{top} = 539 - 587 \approx -48 \text{ psi (tension)}$$

< 500 ✓ okay
 < 284 ✓ okay
 per 9.1 C16

By: _____	Date _____	Project no. _____	Project code (SA#): _____
Chk'd: _____	Date _____	Structure no. _____	Sheet <u>43</u> of _____

COLORADO DEPARTMENT OF TRANSPORTATION
DESIGN COMPUTATIONS (Grid)

Stress @ top of Girder


$$S = \frac{3053098.3}{72 - 60.07} \approx 255917.7$$

$$\sigma = \frac{6238 (12)}{255917.7} \approx -293 \text{ psi (due to moment)}$$

Stress Due to Pretensioning

strand ht @ bearing $\approx 12.5 - \left(\frac{12.5 - 4.02}{50}\right) \cdot 5 \approx 12.42''$

strand ht @ transfer (36") $\approx 12.5 - \left(\frac{12.5 - 4.02}{50}\right) \cdot 3 \approx 11.99''$



P_e after losses $= 2335.2 \text{ K}$

$M_x = .5 W X (L - x)$

$M_y \approx (.5) (1.84 \text{ K/ft}) (15') (125 - .5)$

$M_y \approx 57.27 \text{ ft K}$

$$f_t \approx \left(\frac{.5}{3}\right) \frac{2335.2}{1765.15} - \left(\frac{.5}{3}\right) \frac{2335.2 (35.84 - 12.42)}{(1154251.7) / 36.16''} + \frac{57.27 \text{ ft K} (12)}{(1154251.7) / 36.16''}$$

$$f_t \approx \left(\frac{.5}{3}\right) 1.32 - \left(\frac{.5}{3}\right) 1.71 + .022$$

$f_t = .22 - .285 + .022 \approx -.043 \text{ ksi} \Rightarrow -43 \text{ psi}$

total stress $\approx -293 - 43 \approx -336 \text{ psi} < 570$

okay ✓

By: _____	Date _____	Project no. _____	Project code (SA#): _____
Chk'd: _____	Date _____	Structure no. _____	Sheet 144 of _____

U72 shape with 18" walls

Mass Properties
_ □ ×

File Display

Mass Per Area:

	Centroid	Center Of Mass
Perimeter: 517.534	X: 0	X: 0
Surface Area: 4150.57	Y: 41.2526	Y: 41.2526
Mass: 4150.57	Z: 0	Z: 0

Coordinate System
Center Of Mass

Moments Of Inertia	Products Of Inertia
X: 2.25657e+006	XY: -2.48886e-005
Y: 2.97114e+006	XZ: 0
Z: 5.22771e+006	YZ: 8.09504e-005

Principal Moments	Principal Directions		
X: 2.25657e+006	1.000000	-0.000000	0.000000
Y: 2.97114e+006	0.000000	1.000000	0.000000
Z: 5.22771e+006	0.000000	-0.000000	1.000000

Mass Properties

File Display

Mass Per Area:

	Centroid	Center Of Mass	
Perimeter: 522.056	X: 0	X: 0	
Surface Area: 4069.17	Y: 39.3463	Y: 39.3463	
Mass: 4069.17	Z: 178957	Z: 178957	

Coordinate System:

Moments Of Inertia		Products Of Inertia	
X: 2.24429e+006	Y: 2.94308e+006	XY: -8.58187e-006	XZ: 0
Z: 5.18737e+006		YZ: 0	


Principal Moments	Principal Directions		
X: 2.24429e+006	1.000000	-0.000000	0.000000
Y: 2.94308e+006	0.000000	1.000000	0.000000
Z: 5.18737e+006	0.000000	0.000000	1.000000

Radii Of Gyration

X: 23.4848

Y: 26.8935

Z: 35.7043



Mass Properties

File Display

Mass Per Area: 1.000000


	Centroid	Center Of Mass
Perimeter: 477.05	X: -0.0342651	X: -0.0342651
Surface Area: 1765.14	Y: 35.8415	Y: 35.8415
Mass: 1765.14	Z: 178957	Z: 178957

Coordinate System: Center Of Mass

Moments Of Inertia	Products Of Inertia
X: 1.15425e+006	XY: -1996.51
Y: 2.05432e+006	XZ: 0
Z: 3.20857e+006	YZ: 0

Principal Moments	Principal Directions		
X: 1.15424e+006	0.999998	-0.002218	0.000000
Y: 2.05432e+006	0.002218	0.999998	0.000000
Z: 3.20857e+006	0.000000	0.000000	1.000000

Radii Of Gyration
X: 25.5717
Y: 34.1149
Z: 42.635



COLORADO DEPARTMENT OF TRANSPORTATION
DESIGN COMPUTATIONS (Grid)

DELTA COMPRESSION AT MIDSPAN

ASSUME HAUNCH $\approx 1''$

$$y_{cg} = \frac{(35.84) 1765.15 + \frac{4883.57}{5460} (25' \times 12'') 8'' + (72 + 1 + 4)}{1765.15 + \frac{4883.57}{5460} (25' \times 12'') (8'')}$$

$y_{cg} = 58.43 \text{ in}$

$$I_{comp} = 1154251.7 + 1765.15 (58.43 - 35.84)^2 + \frac{1}{2} (25)(12) \frac{4883.57}{5460} 8^3 + \frac{4883.57}{5460} (25')(12'') (8'') (58.43 - 77)^2$$

$I_{comp} = 2806723.1 \text{ in}^4$

$$S_{comp} \approx \frac{I}{c} = \frac{2806723.1}{(81 - 58.43)} \approx 124356.36 \text{ in}^3$$

$M_{service @ \text{ midspan}} \approx 4565 + 1044 + 210 \approx 5819 \text{ ft k}$

$$F_{top} = \frac{P}{A} + \frac{M}{S}$$

$$= \frac{(.74(270) - 19.17) 33(127)}{25(12'') (8'')} + \frac{5819(12)}{124356.36}$$

$F_{top} = .539 + .562$

$f_{top} \approx 1.10 \text{ ksi} < .6(7.2) = 4.32 \text{ ksi}$
1.29 w/ 4 strands

stress from prestressing = 3.11 ksi ✓ okay

total $\approx 3.11 + 1.10 \approx 4.21 \text{ ksi} > 4.32 \text{ ksi}$

7.4 ksi (minimum) Use 7.3 ksi compression in slabs

By: _____	Date: _____	Project no. _____	Project code (SA#): _____
Chk'd: _____	Date: _____	Structure no. _____	Sheet <u>48</u> of _____

STAFF BRIDGE DESIGN MEMO:

February 2, 1978


1. LONGITUDINAL GIRDER NEGATIVE DESIGN
MOMENT FROM CALIFORNIA FRAME PROGRAM

Use the numerically larger (-)M from the reported (output) (-)M left and (-)M right of any pier. Use this (-)M for reinforcement requirements at C. L. pier and also at the face of support.


2. TRANSVERSE CAP NEGATIVE DESIGN
MOMENT AT COLUMN OR WALL SUPPORT

(a) Use the value of M_D shown in the sketch. Reinforce for M_D at the face of support, and continue this reinforcement amount to the C. L. support when $W = 6$ ft. or less.

When $W > 6$ ft., reinforce for M_D at face of support, continue reinforcement for development requirements, and then reinforcement may be reduced to 40% of maximum reinforcement at centerline of support.



(b) When fillets making an angle θ of 45° or more with the axis of a continuous or restrained member and built monolithic with the member and support, the face of support shall be considered at a section where the combined depth of the member and fillet is at least $1\frac{1}{2}$ times the thickness of the member (T). No portion of a fillet shall be considered as adding to the effective depth. See sketch below.





Paul Chuvorsky
Paul Chuvorsky, Staff Bridge Engineer

Jim Siebels
James E. Siebels, Assistant Staff Bridge
Engineer

H. Henrie Henson
H. Henrie Henson, Assistant Bridge Engineer
(Operations)

**COLORADO DEPARTMENT OF TRANSPORTATION
DESIGN COMPUTATIONS (Grid)**

WEB SHEAR DESIGN



USE STANDARD SPACING
OKAY PER CONSPAN

By: _____	Date _____	Project no. _____	Project code (SA#): _____
Chk'd: _____	Date _____	Structure no. _____	Sheet 150 of _____

COLORADO DEPARTMENT OF TRANSPORTATION
DESIGN COMPUTATIONS (Grid)

GIRDER SHEAR @ bearing

$M_u \approx 18210.6 \text{ ft-k}$

$V_u \approx 1015 \text{ k}$

$d_e \approx d_s = \underset{\text{girder}}{72"} + \underset{\text{haunch}}{5"} + \underset{\text{deck}}{8"} - 4" \approx 81"$

$d_v = .9 d_e = .9(81) \approx 72.9" \rightarrow \text{controls}$

$d_u = .72 H = .72(85") \approx 61.2"$

$$\epsilon_s = \frac{\frac{M_u}{d_v} + .5 N_u + (U_u - V_u) - A_{ps} f_{ps}}{E_s A_s + E_p A_p} \quad (5.8.3.4.2-4)$$

$A_{ps} \approx (9\#)(4)(.27) \approx 9.72 \text{ in}^2$

$A_s \approx \#5 @ 12" \approx 2(.31)(25) \approx 15.5 \text{ in}^2$

$f_{ps} = .7 P_u \approx .7(270) \approx 189 \text{ ksi}$

$$\epsilon_s \approx \frac{\frac{(18210.6)}{72.9} + .5(30 \text{ k}) + 1015 - (9.72)(189 \text{ ksi})}{(29000)(15.5 \text{ in}^2) + 28500(9.72)}$$

$$\epsilon_s \approx \frac{-278.69}{684511} \approx -.000407$$

Use $\epsilon_s = 0$

$\beta = \frac{4.8}{1 + 750 \epsilon_s} = \frac{4.8}{1 + 750(0)} \approx 4.8 \quad (5.8.3.4.2-1)$

$\theta = 29 + 3500 \epsilon_s \approx 29 + 3500(0) = 29^\circ \quad (5.8.3.4.2-3)$

$V_c = .0316(4.8) \sqrt{9 \text{ ksi}} (54") (72.9") \quad (5.8.3.3-3)$

$V_c \approx 1791.3 \text{ k}$

for 2-7/8" webs
 $V_c \approx 497.6 \text{ k}$

$S \approx 3.33" \quad \#4 + \#3 \quad A_s \approx .62 \text{ in}^2$

$V_s = \frac{(.62)(60)(72.9) (\cot 29^\circ + \cot 90^\circ) \sin 90^\circ}{3"} \quad (5.8.3.3-4)$

$V_s \approx 1630 \text{ k}$

$V_n = 1791.3 + 1630 = 3422.1 \text{ k}$

$V_r = \phi V_n = .9(3422.1) = 3079.9 \text{ k} \quad \checkmark \text{ okay}$


By: _____	Date _____	Project no. _____	Project code (SA#): _____
Chk'd: _____	Date _____	Structure no. _____	Sheet 151 of _____

Rebar Pattern: Span 3, Beam 2

Stirrups | Neg. Moment Continuity Steel

- Insert...
- Copy...
- Delete...
- Copy To...
- Graphs...
- Make Symmetrical

Number of Legs	Stirrup Size	Stirrup Area (in ²)	Stirrup Spacing (in)	Start (ft)	End (ft)
3	US#4[M13]	0.600	3.33	0.0000	16.6500
3	US#4[M13]	0.600	5.00	16.6500	37.4800
3	US#4[M13]	0.600	10.00	37.4800	87.4800
3	US#4[M13]	0.600	5.00	87.4800	108.3100
3	US#4[M13]	0.600	3.33	108.3100	126.0000



Auto Design

Stirrup Increment: in.

Size:

Legs:

Auto-Design...

Stirrup Pattern

Delete

Save

Load

Save As

OK Cancel



Program: LEAP®
CONSPAN®
Version: 08.01.00.10
File Name: 76-21-125-21-124_U72C.csl

Copyright © Bentley Systems, Inc. 1984 - 2008.
www.bentley.com
1-800-778-4277

By: A. Pott
Date: Jan/22/2009
CKD:
Date:

VERTICAL/HORIZONTAL SHEAR

VERTICAL SHEAR (Art. 5.8) - Span : 3, Beam : 2, STRENGTH I

Using General Beta Theta Tables procedure - Art.5.8.3.4.2

Location(ft)	Vu (kips)	bv (in)	de (in)	Aps (in ²)	Vp (kips)	eps_x	Theta	Vs-reqd (kips)	Av/s (in ² /ft)	Av-prvd (in ² /ft)	Al_reqd (in ²)
	Mcor (kft)	a (in)	dv (in)	fpo (ksi)	vu/fc	Vc-com (kips)	Beta	Max.spc. (in)	min.Av/s (in ² /ft)	pVn/Vu	Aps* (in ²)
Bearing :		0.50									
	837.8	15.0	79.0	1.432	4.6	0.95e-3	36.0	682.2	1.290	2.16	21.54
	-5021.7	4.1	77.0	31.5	0.089	244.1	2.23	24.00	0.284	1.495	0.459
Transfer :		3.00									
	809.8	15.0	79.0	1.302	27.4	0.91e-3	35.6	624.5	1.160	2.16	6.72
	-3526.7	4.1	77.0	189.0	0.084	247.8	2.26	24.00	0.284	1.600	2.754
Critical :		6.91									
	766.1	15.0	79.0	1.302	27.4	1.00e-3	36.5	580.5	1.114	2.16	7.68
	-1322.4	4.1	77.0	189.0	0.079	243.2	2.22	24.00	0.284	1.641	1.061
0.1L :		12.60									
	702.5	15.0	78.0	14.322	27.4	-0.12e-3	20.8	197.4	0.284	2.16	0.00
	1837.0	2.2	76.9	189.0	0.073	555.6	5.08	24.00	0.284	3.358	13.572
0.2L :		25.20									
	558.1	15.0	76.4	17.577	27.4	-0.13e-3	21.0	28.1	0.284	1.44	0.00
	8146.6	2.4	75.2	189.0	0.058	564.5	5.28	24.00	0.284	3.224	16.542
0.3L :		37.80									
	412.9	15.0	77.7	17.577	27.4	-0.08e-3	20.6	0.0	0.284	0.72	0.00
	12902.0	2.5	76.5	189.0	0.042	490.7	4.51	24.00	0.284	2.724	17.504
0.4L :		50.40									
	271.3	15.0	79.1	17.577	0.0	-0.06e-3	20.9	0.0	0.284	0.72	0.00
	15505.9	2.6	77.8	189.0	0.029	466.7	4.22	24.00	0.284	3.982	17.577
0.5L :		63.00									
	142.0	15.0	79.1	17.577	0.0	-0.06e-3	20.9	0.0	0.284	0.72	0.00
	16458.5	2.6	77.8	189.0	0.015	464.4	4.20	24.00	0.284	7.588	17.577
0.6L :		75.60									
	282.3	15.0	79.1	17.577	0.0	-0.06e-3	20.9	0.0	0.284	0.72	0.00
	15640.3	2.6	77.8	189.0	0.030	462.6	4.18	24.00	0.284	3.810	17.577
0.7L :		88.20									
	428.2	15.0	77.7	17.577	27.4	-0.08e-3	20.6	0.0	0.284	1.44	0.00
	12974.9	2.5	76.5	189.0	0.043	487.3	4.48	24.00	0.284	4.153	17.504
0.8L :		100.80									
	573.6	15.0	76.4	17.577	27.4	-0.13e-3	20.9	54.6	0.284	1.44	0.00
	8431.9	2.4	75.2	189.0	0.060	555.3	5.19	24.00	0.284	3.134	16.542



Program: LEAP®
CONSPAN®
Version: 08.01.00.10

Copyright © Bentley Systems, Inc. 1984 - 2008.
www.bentley.com
1-800-778-4277

By: A. Pott
Date: Jan/22/2009
CKD:
Date:

File Name: 76-21-125-21-124 U72C.csl

Location(ft)	Vu (kips)	bv (in)	de (in)	Aps (in2)	Vp (kips)	eps_x	Theta	Vs-reqd (kips)	Av/s (in2/ft)	Av-prvd (in2/ft)	Al_reqd (in2)
Mcor (kft)	a (in)	dv (in)	fpo (ksi)	vu/fc	Vc-com (kips)	Beta	Max.spc. (in)	min.Av/s (in2/ft)	pVn/Vu	Aps* (in2)	
0.9L :	113.40										
	715.6	15.0	78.0	14.322	27.4	-0.12e-3	20.8	216.1	0.284	2.16	0.00
	2190.0	2.2	76.9	189.0	0.074	551.5	5.05	24.00	0.284	3.297	13.572
Critical :	119.09										
	775.8	15.0	79.0	1.302	27.4	1.00e-3	36.5	591.6	1.136	2.16	7.21
	-1094.5	4.1	77.0	189.0	0.080	243.0	2.22	24.00	0.284	1.620	1.061
Transfer :	123.00										
	817.3	15.0	79.0	1.302	27.4	0.98e-3	36.3	637.2	1.216	2.16	6.23
	-3399.2	4.1	77.0	189.0	0.085	243.4	2.22	24.00	0.284	1.546	2.754
Bearing :	125.50										
	843.7	15.0	79.0	1.432	4.6	1.00e-3	36.6	692.0	1.334	2.16	21.36
	-5000.0	4.1	77.0	31.5	0.090	240.9	2.20	24.00	0.284	1.458	0.459

ANCHORAGE ZONE REINFORCEMENT (Art. 5.10.10)

Span : 3, Beam : 2

Fpi (kips)	fs (ksi)	h/4 (in)	Abrst_rqrd (in2)
2988.09	20.00	18.00	5.98

HORIZONTAL SHEAR (Art. 5.8.4) - Span : 3, Beam : 2

(Beam and Slab effects are INCLUDED in Vu).

Location (ft)	Vu (kips)	Vnh-req (kips)	de (in)	a (in)	dv (in)	s_max (in)	Avh-min (in2/ft)	Avh-sm (in2/ft)	Avh-rg (in2/ft)
Bearing :	0.00								
	837.8	12.09	79.00	4.07	76.96	24.00	0.640	2.423	0.000
Transfer :	2.50								
	809.8	11.69	79.00	4.07	76.96	24.00	0.640	2.288	0.000
Critical :	6.41								
	766.1	11.06	79.00	4.07	76.96	24.00	0.640	2.078	0.000
0.1L :	12.10								
	702.5	10.16	77.97	2.23	76.85	24.00	0.640	1.776	0.000



Program: LEAP®
CONSPAN®
Version: 08.01.00.10

Copyright © Bentley Systems, Inc. 1984 - 2008.
www.bentley.com
1-800-778-4277

By: A. Pott
Date: Jan/22/2009
CKD:
Date:

File Name: 76-21-125-21-124_U72C.csl

Location (ft)	Vu (kips)	Vnh-req (kips)	de (in)	a (in)	dv (in)	s_max (in)	Avh-min (in2/ft)	Avh-sm (in2/ft)	Avh-rg (in2/ft)
0.2L :	558.1	24.70	76.40	2.43	75.18	24.00	0.640	1.140	0.000
0.3L :	412.9	37.30	77.73	2.55	76.45	24.00	0.640	0.391	0.000
0.4L :	271.3	49.90	79.06	2.55	77.78	24.00	0.640	0.000	0.000
0.5L :	142.0	62.50	79.06	2.55	77.78	24.00	0.640	0.000	0.000
0.6L :	282.3	75.10	79.06	2.55	77.78	24.00	0.640	0.000	0.000
0.7L :	428.2	87.70	77.73	2.55	76.45	24.00	0.640	0.465	0.000
0.8L :	573.6	100.30	76.40	2.43	75.18	24.00	0.640	1.217	0.000
0.9L :	715.6	112.90	77.97	2.23	76.85	24.00	0.640	1.840	0.000
Critical :	775.8	118.59	79.00	4.07	76.96	24.00	0.640	2.124	0.000
Transfer :	817.3	122.50	79.00	4.07	76.96	24.00	0.640	2.324	0.000
Bearing :	843.7	125.00	79.00	4.07	76.96	24.00	0.640	2.451	0.000

REBAR SPACING AT FLARE

$V_u \approx 1015 \text{ k}$

max shear @
 abuts $\approx 680 \text{ k}$

for one $\frac{1}{2}$ of girder $V_u \approx \frac{1015}{2} \approx 507.5 \text{ k}$

$V_c \approx 248.8 \text{ k}$

for $1\frac{1}{2}^\circ$ rotation

#3 spaced @ $6.92" \pm \Rightarrow V_s \approx 125.4$

#4 spaced @ $6.68" \pm \Rightarrow V_s \approx 236.3$

$V_r \approx 248.8 + 125.4 + 236.3 \approx 610.5$

$V_n = .9(610.5) \approx 549.4 \text{ k} > V_u$

✓ okay

need $34^\circ/15^\circ \approx 23$ rotated sets

distance = $23(3.33") \approx 76.6" \approx 6'-7"$

if #5s are used in lieu of #4s

for $2\frac{1}{2}^\circ$ rotation $\Rightarrow 14$ rotated sets $\Rightarrow 4'$

#3 spaced @ $9.3" \pm \Rightarrow V_s = 93.3 \text{ k}$


#5 spaced @ $8.9" \pm \Rightarrow V_s \approx 274.9 \text{ k}$

$V_r \approx 248.8 + 93.3 + 274.9 \approx 617.0 \text{ k}$

$V_n = .9(617.0) \approx 555.3 \text{ k} > V_u$



✓ okay

USE:



By: _____	Date _____	Project no. _____	Project code (SA#): _____
Chk'd: _____	Date _____	Structure no. _____	Sheet <u>156</u> of _____

COLORADO DEPARTMENT OF TRANSPORTATION
 DESIGN COMPUTATIONS (Grid)



By: _____	Date _____	Project no. _____	Project code (SA#): _____
Chk'd: _____	Date _____	Structure no. _____	Sheet 157 of _____

GIRDER CONNECTION AT PIER

$$M_u \approx 10378.5 \text{ ft-k}$$

$$V_u \approx 1015 \text{ k}$$

For normal weight concrete placed against clean concrete surface
 with surface intentionally roughened to an amplitude of .25 in.
 Use shear keys in girder to provide roughening

$$C = .24 \text{ ksi}$$

$$\mu = 1.0$$

$$K_1 = .25$$

$$K_2 = 1.5 \text{ ksi}$$

$$A_{cv} \approx 12.25 \text{ SF for U72C with no diaphragm}$$

$$A_{cv} = 28.82 \text{ SF for U72C with diaphragm (1'-6" thick)}$$

$$V_{nc} \leq K_1 f'_c A_{cv} = .25 (4.5) (12.25) (144) \quad (5.8.4.1-4)$$

$$V_{nc} \leq 1984.5 \text{ k}$$

$$V_{nc} \leq K_2 A_{cv} = (1.5 \text{ ksi}) (12.25 \text{ SF}) (144) \quad (5.8.4.1-5)$$

$$V_{nc} \leq 2646 \text{ kips}$$

$$A_{uf min} \geq \frac{.05 A_{cv}}{f_y} = \frac{.05 (12.25) (144)}{60} \approx 1.47 \text{ in}^2 \quad (5.8.4.4-1)$$

$$P_c = 0$$

COLORADO DEPARTMENT OF TRANSPORTATION
DESIGN COMPUTATIONS (Grid)

$$V_{ni} = c A_{cr} + \mu (A_{vf} f_y + P_2) \quad (5.8.4.1-3)$$

$$1015 = \underbrace{(.24)(12.25)(144)}_{\text{girder}} + \underbrace{.24(8'')(25' \frac{12''}{16})}_{\text{deck}} + 1.0(A_{vf} 60 \text{ksi} + 0)$$

$$1015 = 423.36 \text{ K} + 576 \text{ K} + 60 A_{vf}$$

$$A_{vf} \approx .26 \text{ in}^2$$

$$\text{one strand} = .257 \text{ in}^2$$

extend 2 strand minimum
 ✓ OKAY

without deck:

$$1015 = 423.36 \text{ K} + 60 A_{vf}$$

$$A_{vf} \approx 9.86 \text{ in}^2$$

for Dead Loads:

$$V_{max} = \left[(25')(1.67') \left(\frac{23'}{2} \right) (.15) + (12.25' \text{ SF} \left(\frac{23'}{2} \right) (.15) \right] 1.25$$

$$V_{max} \approx 62.6 \text{ K}$$

$$c A_{cr} > V_{max}$$

✓ OKAY

$$A_{\text{provisions}} \approx .217 \text{ in}^2$$

extend all draped strands \approx 12 strands

extend 16 bottom strands

$$28(.217) \approx 6.076 \text{ in}^2$$

$$A_{\text{need}} = 9.86 - 6.076 \approx 3.784 \text{ in}^2$$

$$A_{s \text{ deck}} = 7.75 \text{ in}^2 + \frac{5237.6 - 3046.1}{5237.6} \approx 3.24 \text{ in}^2 \text{ of deck steel could be used for steel}$$

(not needed for moment)

$$A_{\text{need}} = 3.784 - 3.24 \approx .54 \text{ in}^2$$

$$2 \# 5_s = .62 \text{ in}^2$$

By: _____	Date _____	Project no. _____	Project code (SA#): _____
Chk'd: _____	Date _____	Structure no. _____	Sheet 159 of _____

COLORADO DEPARTMENT OF TRANSPORTATION
DESIGN COMPUTATIONS (Grid)

Closure Pour Shear

$\beta \approx 4.8$

$\theta = 29$

diaphragm = 18" webs

$V_c = .0316 (4.8) \sqrt{4.5 \text{ ksi}} (72.9") (36")$

$V_c \approx 844.43 \text{ K}$

Assume 2-#5 $\Rightarrow .31 * 2 = .62 \text{ in}^2 @ 6"$

$V_s = \frac{.62 (60) (72.9) (\cot 29^\circ + \cot 90^\circ)}{6"} \sin 90$

$V_s \approx 815.4 \text{ K}$

$V_n = 844 + 815 \approx 1659 \text{ K}$

$V_r = \phi V_n = .9 (1659) \approx 1493 \text{ K} > V_u \checkmark \text{ okay}$

Shear Keys

$V_c = .0316 \beta \sqrt{f'_c} b_v d_v \quad (5.8.3.3-3)$

$b_v \approx 14" \text{ each web}$

$d_v \approx 3\frac{1}{2}"$

$V_c = .0316 (2) \sqrt{4.5} (14") (3\frac{1}{2}) (2 \text{ webs}) = 13.1 \text{ K each key pair}$

$V = 62.6$

6 Keys \Rightarrow pairs $13.1 (6) = 78.6 \text{ K} (.9) = 70.7 \text{ K}$




14"
 13.1 K

6 PA

By: _____	Date _____	Project no. _____	Project code (SA#): _____
Chk'd: _____	Date _____	Structure no. _____	Sheet <u>160</u> of _____

COLORADO DEPARTMENT OF TRANSPORTATION
DESIGN COMPUTATIONS (Grid)




Place Closure Pair after Deck Placement

Shear Keys



use 6/ web min.



can make out of 2x4

By: Date	Project no.	Project code (SA#):
Chk'd: Date	Structure no.	Sheet 161 of

PIER GIRDER

Composite section

$$I_{comp} = 2806723.1 \text{ in}^4$$

$$Y_{cg} = 58.43$$

$$S_{comp \text{ top}} = I/c = \frac{2806723.1}{(81 - 58.43)} = 124356.36 \text{ in}^3$$

$$S_{comp \text{ top girder}} = I/c = \frac{2806723.1}{(81 - 8 - 1 - 58.43)} = 206832.9$$

$$S_{comp \text{ bottom top girder flange}} \approx 388742.8$$

$$f_{top} = M/S$$

$$M_{service} = 4395 + 1555 + 312 \approx 6262 \text{ ft kip (Pier 3)}$$

$$M_{service \text{ dead}} = 1867 \text{ ft kip}$$

$$5471 \text{ ft kip (Pier 2)}$$

$$f_{top \text{ girder}} \approx \frac{-6262 (12)}{206832.9} = -.363 \text{ Ksi tension}$$

$$-.317 \text{ Ksi (Pier 2)}$$

$$f_{top \text{ deck}} \approx \frac{-6262 (12)}{124356.36} = -.604 \text{ Ksi tension}$$

$$-.528 \text{ Ksi (Pier 3)}$$

$f_{deck} \approx .457$ compression from post-tensioning

$$-.604 + .457 \approx -.147 \text{ Ksi} < 201 \text{ psi } \checkmark \text{ okay}$$

deck okay

→ tension in top of girder need
 well distributed tension steel
 or put girder into tension (prestressing)

By: Date	Project no.	Project code (SA#):
Chk'd: Date	Structure no.	Sheet 162 of

COLORADO DEPARTMENT OF TRANSPORTATION
DESIGN COMPUTATIONS (Grid)

$$P_R = 489.4 \text{ K}$$

$$E_{EE} = E_{MS} = 33,880 \text{ psi}$$

$$I = 115,4251.67$$

$$A = 12.26 \text{ SF} = 1765 \text{ in}^2$$


$$Y_{CG} = 35.84$$

$$S_T = \frac{1154251.67}{72 - 35.84} = 31920.68$$

$$f_{top} = \frac{P}{A} + \frac{P \cdot e}{S_T} = \frac{489.4}{1765} + \frac{(1765 \text{ in}^2)(33,880 - 35.84)}{31920.68}$$

$$= .277 + -.108$$

$$= .169 \text{ Ksi} \quad \text{compression}$$




$$f_{flange} = \frac{6262(12)}{398742.8} = .193 \text{ Ksi}$$

$$f_r = .23 \sqrt{f'_c}$$

$$= .23 \sqrt{9 \text{ Ksi}}$$

$$f_r = .69 \text{ Ksi}$$

$f_r > f_{top}$ ✓ okay strength



$$\approx 72.93 \text{ K} / 60 \text{ Ksi} = 1.215 \text{ in}^2$$

$$7 - \#4 = 1.4 \text{ in}^2$$


$$4 - \#5 = 1.24 \text{ in}^2$$

$$3 - \#6 = 1.32 \text{ in}^2$$

← use

By: _____	Date _____	Project no. _____	Project code (SA#): _____
Chk'd: _____	Date _____	Structure no. _____	Sheet <u>163</u> of _____

COLORADO DEPARTMENT OF TRANSPORTATION
 DESIGN COMPUTATIONS (Grid)



$$M_{max} = \frac{w l^2}{2}$$

$$M_{max} = \frac{(1.839 \text{ k/ft}) 21^2}{2}$$

$$M_{max} \approx 405.5 \text{ ft kip}$$

Use 8 - #5



$$M_R \approx 775.03 \text{ ft kip} \quad \checkmark \text{ okay}$$

REINFORCING DESIGN

GIVEN:

$f_y = 60.00$ ksi
 $f_c = 6.75$ ksi
 COVER = 2.00 inches
 $\Phi_{flexure} = 0.90$
 Beam Thickness (t_s) = 72.00 inches
 $b = 54.00$ inches
 bar diameter = 0.625 inches

LOAD TYPE	M_{hTOT} ft-K
Mh (UNFACTORED)	405.50
STRENGTH I	506.87
SERVICE I	405.50

$A_{Sreq'd}$ in ²
1.30
1.62
1.30

$d_s = 69.69$ inches
 per 5.10.8.2 $A_{Stemp} = 5.83$ sq inches

Use # 5 at top face min. spacing = 10.33 inches
 use spacing = 6.75 inches
 $A_s = 2.480$ sq. inches

compressive steel:

Use # 5 at bottom face
 $A_{s'} = 0.00$ sq. inches

$M_n = 861.15$ ft-K
 $M_r = 775.03$ ft-K

Reinforcing is okay

Maximum Reinforcement per 5.7.3.3.1-1 (Ductility Check)

$c = 0.67$ inches
 $d_e = d_s = 69.69$ inches (for no prestressing)
 $c/d_e = 0.01$

okay - member is not overreinforced

Minimum Reinforcement per 5.7.3.3.2

$1.2 * M_{cracking} = 2909.18$ ft-K <--- Test 1
 $1.33 M_{hTOT} (max.) = 674.14$ ft-K <--- Test 2

Minimum Reinforcing is provided

Transverse Reinforcement per 9.7.3.2

Percentage of main reinforcement, $220 / \sqrt{S} \leq 67\%$


Girder Spacing = 15.25 ft
 Flange Width = 21 inches
 Flange Overhang = 18 inches
 Effective Length S = 15.00 ft
 $220 / \sqrt{S} = 56.80\%$ Use **56.804** % of required main reinforcement
 Required $A_s = 1.41$ sq inches
 Use # 6 transverse reinforcement
 min. spacing = 16.86 inches

ADDITIONAL

Points of Inflection

FOR NEGATIVE MOMENT
 POST-TENSIONING

From SAP 2000:



span 3 = 125'

$.0625 \times 125 = 7.81'$ min. embed post inflection 5.11.1.2.3

$1/20 \times 125 \approx 6.25'$ min embed post strength requirement 5.11.1.2.1

negative moment strength for 2 strands/conduit

min. $9\frac{1}{2} \times 2$ strand ≈ 19 strands for ultimate
 loss ≈ 19.17

$$C = \frac{19(217) [.75(270) - 19.17]}{(1.85)(9.0) .6(54')}$$

$C \approx 3.05''$

assume haunch less than max.

$M_n = A_p s f_{ps} (d_p - a/2)$

$= (19)(217) [.75(270) - 19.17] [72'' + 5'' + 4'' - \frac{.6(3.05)}{2}]$

$M_n \approx 60533.8 \text{ wk} = 5044.5 \text{ ft k}$

$M_R = \phi M_n = .9 (5044.5) = \underline{4540 \text{ ft k}}$

max live load $< \frac{4540}{1.75/1.33} < 1950 \text{ ft k}$

By: Date	Project no.	Project code (SA#):
Chk'd: Date	Structure no.	Sheet 166 of

NEGATIVE MOMENTS
FROM CONSPAN

Interior {
Span 1 @ ~1.5' $M_u < -4540$
from bearing
Span 3 @ ~8' $M_u < -4540$
@ ~8' $M_u < -4540$
Span 5 @ ~11.5' $M_u < -4540$

exterior {
Span 1 @ ~2.5' $M_u < -4540$
Span 2 @ ~9' $M_u < -4540$
@ ~9' $M_u < -4540$
Span 3 @ ~12.5' $M_u < -4540$

Use $12.5 + 6.25' \approx 18.75'$ past bearing
_{min embed}
for negative moment steel

By: Date	Project no.	Project code (SA#):
Chk'd: Date	Structure no.	Sheet 167 of

COLORADO DEPARTMENT OF TRANSPORTATION
DESIGN COMPUTATIONS (Grid)

from SAP 2000

min distance to $M_0 = 4540$

$x \approx 14.7$ to span 5

$x \approx 16.4$ to span 3

min length $\approx 16.4 + \underset{\text{min embed}}{6.25'} \approx 22.65'$

Use $\approx 23'$ for negative moment ~~⊕~~

By: _____	Date _____	Project no. _____	Project code (SA#): _____
Chk'd: _____	Date _____	Structure no. _____	Sheet <u>68</u> of _____



Colorado DOT

Sheet #	DS-1
Job #	BR R600-297
By	A. Pott
Date	Jan/4/2010
Checked	
Date	

Program: LEAP® CONSPAN® V8i (SELECTseries 1)

Version: Version: 09.00.01.06

Copyright © Bentley Systems, Inc. 1984 - 2009

www.bentley.com Phone: 1-800-778-4277

File Name: 76-21-125-21-124_U72C_NewVersion.csl

REINFORCED DESIGN

REINFORCED DESIGN - Span : 1, Beam : 2, STRENGTH I (fy = 60.00 ksi)

(a) NEGATIVE MOMENTS ALONG SPAN (Non-composite Moment effects are INCLUDED in Mu)

f_c	b	bw
(ksi)	(in)	(in)
9.00	54.00	15.00

Sec	Dist (ft)	Mu-reqd (k.ft)	hf (in)	d (in)	d' (in)	Phi	Phi*Mn-r (k.ft)	c/dt	Asb (in ²)	Ast-r (in ²)	Ast-p (in ²)	Phi*Mn-p (k.ft)
1	0.00	0.0	8.10	80.53	2.00	0.9	-0.0	0.0000	0.000	0.000	0.000	-0.0
2	8.10	0.0	8.10	80.53	2.00	0.9	-0.0	0.0000	0.000	0.000	0.000	-0.0
3	15.70	0.0	8.10	80.53	2.00	0.9	-0.0	0.0000	0.000	0.000	0.000	-0.0
4	23.30	0.0	8.10	80.53	2.00	0.9	-0.0	0.0000	0.000	0.000	0.000	-0.0
5	30.90	0.0	8.10	80.53	2.00	0.9	-0.0	0.0000	0.000	0.000	0.000	-0.0
6	38.50	0.0	8.10	80.53	2.00	0.9	-0.0	0.0000	0.000	0.000	0.000	-0.0
7	46.10	0.0	8.10	80.53	2.00	0.9	-0.0	0.0000	0.000	0.000	0.000	-0.0
8	53.70	0.0	8.10	80.53	2.00	0.9	-0.0	0.0000	0.000	0.000	0.000	-0.0
9	61.30	0.0	8.10	80.53	2.00	0.9	-0.0	0.0000	0.000	4.835	0.000*	-0.0
10	68.90	-1428.2	8.10	80.53	2.00	0.9	-1428.2	0.0110	0.000	4.835	0.000*	-0.0
11	76.50	-5187.8	8.10	80.53	2.00	0.9	-5187.8	0.0403	0.000	14.506	0.000*	-0.0

(b) POSITIVE MOMENTS AT PIERS

NONE

169



Colorado DOT

Sheet #	DS-1
Job #	BR R600-297
By	A. Pott
Date	Jan/4/2010
Checked	
Date	

Program: LEAP® CONSPAN® V8i (SELECTseries 1)

Version: Version: 09.00.01.06

Copyright © Bentley Systems, Inc. 1984 - 2009

www.bentley.com Phone: 1-800-778-4277

File Name: 76-21-125-21-124_U72C_NewVersion.csl

REINFORCED DESIGN

REINFORCED DESIGN - Span : 2, Beam : 2, STRENGTH I (fy = 60.00 ksi)

(a) NEGATIVE MOMENTS ALONG SPAN (Non-composite Moment effects are INCLUDED in Mu)

f_c	b	bw
(ksi)	(in)	(in)
9.00	54.00	15.00

Sec	Dist (ft)	Mu-reqd (k.ft)	hf (in)	d (in)	d' (in)	Phi	Phi*Mn-r (k.ft)	c/dt	Asb (in ²)	Ast-r (in ²)	Ast-p (in ²)	Phi*Mn-p (k.ft)
1	0.00	0.0	8.10	80.53	2.00	0.9	-0.0	0.0000	0.000	0.000	0.000	-0.0
2	3.00	-4560.6	8.10	80.53	2.00	0.9	-4560.6	0.0353	0.000	12.732	0.000*	-0.0
3	5.00	-4150.7	8.10	80.53	2.00	0.9	-4150.7	0.0321	0.000	11.575	0.000*	-0.0
4	7.00	-4443.1	8.10	80.53	2.00	0.9	-4443.1	0.0344	0.000	12.400	0.000*	-0.0
5	9.00	-4759.2	8.10	80.53	2.00	0.9	-4759.2	0.0369	0.000	13.293	0.000*	-0.0
6	11.00	-5099.2	8.10	80.53	2.00	0.9	-5099.2	0.0396	0.000	14.255	0.000*	-0.0
7	13.00	-5467.4	8.10	80.53	2.00	0.9	-5467.4	0.0425	0.000	15.299	0.000*	-0.0
8	15.00	-6615.9	8.10	80.53	2.00	0.9	-6615.9	0.0515	0.000	18.569	0.000*	-0.0
9	17.00	-7470.0	8.10	80.53	2.00	0.9	-7470.0	0.0583	0.000	21.013	0.000*	-0.0
10	19.00	-8347.2	8.10	80.53	2.00	0.9	-8347.2	0.0653	0.000	23.535	0.000*	-0.0
11	21.00	-6258.4	8.10	80.53	2.00	0.9	-6258.4	0.0487	0.000	17.549	0.000*	-0.0

(b) POSITIVE MOMENTS AT PIERS

NONE

MP



Colorado DOT

Sheet #	DS-1
Job #	BR R600-297
By	A. Pott
Date	Jan/4/2010
Checked	
Date	

Program: LEAP® CONSPAN® V8i (SELECTseries 1)

Version: Version: 09.00.01.06

Copyright © Bentley Systems, Inc. 1984 - 2009

www.bentley.com

Phone: 1-800-778-4277

File Name: 76-21-125-21-124_U72C_NewVersion.csl

REINFORCED DESIGN

REINFORCED DESIGN - Span : 3, Beam : 2, STRENGTH I (fy = 60.00 ksi)

(a) NEGATIVE MOMENTS ALONG SPAN (Non-composite Moment effects are INCLUDED in Mu)

f_c	b	bw
(ksi)	(in)	(in)
9.00	54.00	15.00

Sec	Dist (ft)	Mu-reqd (k.ft)	hf (in)	d (in)	d' (in)	Phi	Phi*Mn-r (k.ft)	c/dt	Asb (in ²)	Ast-r (in ²)	Ast-p (in ²)	Phi*Mn-p (k.ft)
1	0.00	-9593.2	8.10	80.53	2.00	0.9	-9593.3	0.0753	0.000	27.138	0.000*	-0.0
2	12.70	-1442.2	8.10	80.53	2.00	0.9	-1442.2	0.0111	0.000	9.046	0.000*	-0.0
3	25.40	0.0	8.10	80.53	2.00	0.9	-0.0	0.0000	0.000	9.046	0.000*	-0.0
4	38.10	0.0	8.10	80.53	2.00	0.9	-0.0	0.0000	0.000	0.000	0.000	-0.0
5	50.80	0.0	8.10	80.53	2.00	0.9	-0.0	0.0000	0.000	0.000	0.000	-0.0
6	63.50	0.0	8.10	80.53	2.00	0.9	-0.0	0.0000	0.000	0.000	0.000	-0.0
7	76.20	0.0	8.10	80.53	2.00	0.9	-0.0	0.0000	0.000	0.000	0.000	-0.0
8	88.90	0.0	8.10	80.53	2.00	0.9	-0.0	0.0000	0.000	0.000	0.000	-0.0
9	101.60	0.0	8.10	80.53	2.00	0.9	-0.0	0.0000	0.000	8.738	0.000*	-0.0
10	114.30	-1196.9	8.10	80.53	2.00	0.9	-1196.9	0.0092	0.000	8.738	0.000*	-0.0
11	127.00	-9274.5	8.10	80.53	2.00	0.9	-9274.5	0.0727	0.000	26.214	0.000*	-0.0

(b) POSITIVE MOMENTS AT PIERS

NONE

171



Colorado DOT

Sheet #	DS-1
Job #	BR R600-297
By	A. Pott
Date	Jan/4/2010
Checked	
Date	

Program: LEAP® CONSPAN® V8i (SELECTseries 1)

Version: Version: 09.00.01.06

Copyright © Bentley Systems, Inc. 1984 - 2009

www.bentley.com

Phone: 1-800-778-4277

File Name: 76-21-125-21-124_U72C_NewVersion.csl

REINFORCED DESIGN

REINFORCED DESIGN - Span : 4, Beam : 2, STRENGTH I (fy = 60.00 ksi)

(a) NEGATIVE MOMENTS ALONG SPAN (Non-composite Moment effects are INCLUDED in Mu)

f'c	b	bw
(ksi)	(in)	(in)
9.00	54.00	15.00

Sec	Dist (ft)	Mu-reqd (k.ft)	hf (in)	d (in)	d' (in)	Phi	Phi*Mn-r (k.ft)	c/dt	Asb (in ²)	Ast-r (in ²)	Ast-p (in ²)	Phi*Mn-p (k.ft)
1	0.00	0.0	8.10	80.53	2.00	0.9	-0.0	0.0000	0.000	0.000	0.000	-0.0
2	3.00	-8080.1	8.10	80.53	2.00	0.9	-8080.1	0.0632	0.000	22.766	0.000*	-0.0
3	5.00	-7620.0	8.10	80.53	2.00	0.9	-7620.0	0.0595	0.000	21.443	0.000*	-0.0
4	7.00	-7171.5	8.10	80.53	2.00	0.9	-7171.5	0.0559	0.000	20.157	0.000*	-0.0
5	9.00	-7387.2	8.10	80.53	2.00	0.9	-7387.2	0.0577	0.000	20.776	0.000*	-0.0
6	11.00	-7626.2	8.10	80.53	2.00	0.9	-7626.2	0.0596	0.000	21.461	0.000*	-0.0
7	13.00	-7888.6	8.10	80.53	2.00	0.9	-7888.6	0.0616	0.000	22.215	0.000*	-0.0
8	15.00	-9082.0	8.10	80.53	2.00	0.9	-9081.9	0.0712	0.000	25.657	0.000*	-0.0
9	17.00	-9988.9	8.10	80.53	2.00	0.9	-9988.9	0.0785	0.000	28.288	0.000*	-0.0
10	19.00	-10919.1	8.10	80.53	2.00	0.9	-10919.1	0.0860	0.000	31.000	0.000*	-0.0
11	21.00	-7903.3	8.10	80.53	2.00	0.9	-7903.3	0.0618	0.000	22.257	0.000*	-0.0

(b) POSITIVE MOMENTS AT PIERS

NONE



Colorado DOT

Sheet #	DS-1
Job #	BR R600-297
By	A. Pott
Date	Jan/4/2010
Checked	
Date	

Program: LEAP® CONSPAN® V8i (SELECTseries 1)

Version: Version: 09.00.01.06

Copyright © Bentley Systems, Inc. 1984 - 2009

www.bentley.com

Phone: 1-800-778-4277

File Name: 76-21-125-21-124_U72C_NewVersion.csl

REINFORCED DESIGN

REINFORCED DESIGN - Span : 5, Beam : 2, STRENGTH I (fy = 60.00 ksi)


(a) NEGATIVE MOMENTS ALONG SPAN (Non-composite Moment effects are INCLUDED in Mu)

f_c	b	bw
(ksi)	(in)	(in)
9.00	54.00	15.00

Sec	Dist (ft)	Mu-reqd (k.ft)	hf (in)	d (in)	d' (in)	Phi	Phi*Mn-r (k.ft)	c/dt	Asb (in ²)	Ast-r (in ²)	Ast-p (in ²)	Phi*Mn-p (k.ft)
1	0.00	-12341.9	8.10	80.53	2.00	0.9	-12341.9	0.0976	0.000	35.175	0.000*	-0.0
2	12.90	-3368.4	8.10	80.53	2.00	0.9	-3368.4	0.0260	0.000	11.725	0.000*	-0.0
3	25.30	0.0	8.10	80.53	2.00	0.9	-0.0	0.0000	0.000	11.725	0.000*	-0.0
4	37.70	0.0	8.10	80.53	2.00	0.9	-0.0	0.0000	0.000	0.000	0.000	-0.0
5	50.10	0.0	8.10	80.53	2.00	0.9	-0.0	0.0000	0.000	0.000	0.000	-0.0
6	62.50	0.0	8.10	80.53	2.00	0.9	-0.0	0.0000	0.000	0.000	0.000	-0.0
7	74.90	0.0	8.10	80.53	2.00	0.9	-0.0	0.0000	0.000	0.000	0.000	-0.0
8	87.30	0.0	8.10	80.53	2.00	0.9	-0.0	0.0000	0.000	0.000	0.000	-0.0
9	99.70	0.0	8.10	80.53	2.00	0.9	-0.0	0.0000	0.000	0.000	0.000	-0.0
10	112.10	0.0	8.10	80.53	2.00	0.9	-0.0	0.0000	0.000	0.000	0.000	-0.0
11	124.50	0.0	8.10	80.53	2.00	0.9	-0.0	0.0000	0.000	0.000	0.000	-0.0

(b) POSITIVE MOMENTS AT PIERS

NONE

		Colorado DOT		Sheet #	DS-1
				Job #	BR R600-297
Program:	LEAP® CONSPAN® V8i (SELECTseries 1)			By	A. Pott
Version:	Version: 09.00.01.06	Copyright © Bentley Systems, Inc. 1984 - 2009		Date	Jan/4/2010
		www.bentley.com	Phone: 1-800-778-4277	Checked	
File Name:	76-21-125-21-124_U72C_NewVersion.csl			Date	

REINFORCED DESIGN

REINFORCED DESIGN - Span : 1, Beam : 1, STRENGTH I (fy = 60.00 ksi)

(a) NEGATIVE MOMENTS ALONG SPAN (Non-composite Moment effects are INCLUDED in Mu)

f_c	b	bw
(ksi)	(in)	(in)
9.00	54.00	15.00

Sec	Dist (ft)	Mu-reqd (k.ft)	hf (in)	d (in)	d' (in)	Phi	Phi*Mn-r (k.ft)	c/dt	Asb (in ²)	Ast-r (in ²)	Ast-p (in ²)	Phi*Mn-p (k.ft)
1	0.00	0.0	8.10	80.53	2.00	0.9	-0.0	0.0000	0.000	0.000	0.000	-0.0
2	8.10	0.0	8.10	80.53	2.00	0.9	-0.0	0.0000	0.000	0.000	0.000	-0.0
3	15.70	0.0	8.10	80.53	2.00	0.9	-0.0	0.0000	0.000	0.000	0.000	-0.0
4	23.30	0.0	8.10	80.53	2.00	0.9	-0.0	0.0000	0.000	0.000	0.000	-0.0
5	30.90	0.0	8.10	80.53	2.00	0.9	-0.0	0.0000	0.000	0.000	0.000	-0.0
6	38.50	0.0	8.10	80.53	2.00	0.9	-0.0	0.0000	0.000	0.000	0.000	-0.0
7	46.10	0.0	8.10	80.53	2.00	0.9	-0.0	0.0000	0.000	0.000	0.000	-0.0
8	53.70	0.0	8.10	80.53	2.00	0.9	-0.0	0.0000	0.000	0.000	0.000	-0.0
9	61.30	0.0	8.10	80.53	2.00	0.9	-0.0	0.0000	0.000	5.228	0.000*	-0.0
10	68.90	-1677.9	8.10	80.53	2.00	0.9	-1677.9	0.0129	0.000	5.228	0.000*	-0.0
11	76.50	-5603.1	8.10	80.53	2.00	0.9	-5603.1	0.0435	0.000	15.685	0.000*	-0.0

(b) POSITIVE MOMENTS AT PIERS

NONE



Colorado DOT

Sheet #	DS-1
Job #	BR R600-297
By	A. Pott
Date	Jan/4/2010
Checked	
Date	

Program:	LEAP® CONSPAN® V8i (SELECTseries 1)
Version:	Version: 09.00.01.06
File Name:	76-21-125-21-124_U72C_NewVersion.csl

Copyright © Bentley Systems, Inc. 1984 - 2009
 www.bentley.com Phone: 1-800-778-4277

REINFORCED DESIGN

REINFORCED DESIGN - Span : 3, Beam : 1, STRENGTH I (fy = 60.00 ksi)

(a) NEGATIVE MOMENTS ALONG SPAN (Non-composite Moment effects are INCLUDED in Mu)

f_c	b	bw
(ksi)	(in)	(in)
9.00	54.00	15.00

Sec	Dist (ft)	Mu-reqd (k.ft)	hf (in)	d (in)	d' (in)	Phi	Phi*Mn-r (k.ft)	c/dt	Asb (in ²)	Ast-r (in ²)	Ast-p (in ²)	Phi*Mn-p (k.ft)
1	0.00	-10251.6	8.10	80.53	2.00	0.9	-10251.6	0.0806	0.000	29.052	0.000*	-0.0
2	12.70	-1856.1	8.10	80.53	2.00	0.9	-1856.1	0.0143	0.000	9.684	0.000*	-0.0
3	25.40	0.0	8.10	80.53	2.00	0.9	-0.0	0.0000	0.000	9.684	0.000*	-0.0
4	38.10	0.0	8.10	80.53	2.00	0.9	-0.0	0.0000	0.000	0.000	0.000	-0.0
5	50.80	0.0	8.10	80.53	2.00	0.9	-0.0	0.0000	0.000	0.000	0.000	-0.0
6	63.50	0.0	8.10	80.53	2.00	0.9	-0.0	0.0000	0.000	0.000	0.000	-0.0
7	76.20	0.0	8.10	80.53	2.00	0.9	-0.0	0.0000	0.000	0.000	0.000	-0.0
8	88.90	0.0	8.10	80.53	2.00	0.9	-0.0	0.0000	0.000	0.000	0.000	-0.0
9	101.60	0.0	8.10	80.53	2.00	0.9	-0.0	0.0000	0.000	9.378	0.000*	-0.0
10	114.30	-1614.0	8.10	80.53	2.00	0.9	-1614.0	0.0124	0.000	9.378	0.000*	-0.0
11	127.00	-9935.6	8.10	80.53	2.00	0.9	-9935.6	0.0781	0.000	28.133	0.000*	-0.0

(b) POSITIVE MOMENTS AT PIERS

NONE

175



Colorado DOT

Sheet #	DS-1
Job #	BR R600-297
By	A. Pott
Date	Jan/4/2010
Checked	
Date	

Program: LEAP® CONSPAN® V8i (SELECTseries 1)

Version: Version: 09.00.01.06

Copyright © Bentley Systems, Inc. 1984 - 2009

www.bentley.com Phone: 1-800-778-4277

File Name: 76-21-125-21-124_U72C_NewVersion.csl

REINFORCED DESIGN

REINFORCED DESIGN - Span : 5, Beam : 1, STRENGTH I (fy = 60.00 ksi)

(a) NEGATIVE MOMENTS ALONG SPAN (Non-composite Moment effects are INCLUDED in Mu)

f_c	b	bw
(ksi)	(in)	(in)
9.00	54.00	15.00

Sec	Dist (ft)	Mu-reqd (k.ft)	hf (in)	d (in)	d' (in)	Phi	Phi*Mn-r (k.ft)	c/dt	Asb (in ²)	Ast-r (in ²)	Ast-p (in ²)	Phi*Mn-p (k.ft)
1	0.00	-13191.9	8.10	80.53	2.00	0.9	-13191.9	0.1046	0.000	37.686	0.000*	-0.0
2	12.90	-3922.7	8.10	80.53	2.00	0.9	-3922.7	0.0303	0.000	12.562	0.000*	-0.0
3	25.30	0.0	8.10	80.53	2.00	0.9	-0.0	0.0000	0.000	12.562	0.000*	-0.0
4	37.70	0.0	8.10	80.53	2.00	0.9	-0.0	0.0000	0.000	0.000	0.000	-0.0
5	50.10	0.0	8.10	80.53	2.00	0.9	-0.0	0.0000	0.000	0.000	0.000	-0.0
6	62.50	0.0	8.10	80.53	2.00	0.9	-0.0	0.0000	0.000	0.000	0.000	-0.0
7	74.90	0.0	8.10	80.53	2.00	0.9	-0.0	0.0000	0.000	0.000	0.000	-0.0
8	87.30	0.0	8.10	80.53	2.00	0.9	-0.0	0.0000	0.000	0.000	0.000	-0.0
9	99.70	0.0	8.10	80.53	2.00	0.9	-0.0	0.0000	0.000	0.000	0.000	-0.0
10	112.10	0.0	8.10	80.53	2.00	0.9	-0.0	0.0000	0.000	0.000	0.000	-0.0
11	124.50	0.0	8.10	80.53	2.00	0.9	-0.0	0.0000	0.000	0.000	0.000	-0.0

(b) POSITIVE MOMENTS AT PIERS

NONE

176

Negative moment (Pier)
post tensioning losses

5.9.5.2.1 Anchorage Set

anchorage set loss = $3/8'' = \Delta L$

min $L \approx 69'$

based on deck slabs $L \approx 77'$

$$d = .75(270) \left(1 - e^{[-(.0002)77 + .25(.00873)]} \right)$$

$d \approx 2.659$ ksi


$$X = \sqrt{\frac{E(\Delta L)L}{12d}} = \sqrt{\frac{(28500)(.375)77'}{(12)2.659}}$$

$X \approx 160.6'$

$$\Delta f = \frac{E\Delta L}{6X} = \frac{(28500)(.375)}{6(160.6)}$$

$\Delta f = 11.09$ ksi

dist. to pier $\approx 25'$



$$\frac{160.6' - 25'}{160.6'} = \frac{\Delta f_{\text{pier}}}{11.09}$$

$\Delta f_{\text{pier}} \approx 9.36$ ksi ← loss @ pier

5.9.5.2.2 Friction

$$\Delta f_{PF} = F_{ej} (1 - e^{(-kx + \mu\alpha)}) \quad (5.9.5.2.2b-1)$$

$$k = .0002$$

Table 5.9.5.2.2b-1

$$\mu = .23$$

$$X_{total} \approx 77'$$

$$X_{max} = 77/2 = 38.5'$$

assume post tensioning
from both ends

$$X_{max \text{ to pier}} \approx 25'$$

assume $\alpha \approx 0^\circ = 0$ radians

$$\Delta f_{PF} = .75(270) (1 - e^{(-.0002(25') + .2(0))})$$

$$\Delta f_{PF} \approx \underline{1.01 \text{ Ksi}} \quad \odot$$

By: Date	Project no.	Project code (SA#):
Chk'd: Date	Structure no.	Sheet 178 of

5.9.5.2.3b ELASTIC SHORTENING

$$\Delta f_{ps} = \frac{N-1}{2N} \frac{E_p}{E_{ci}} f_{cp} \quad (5.9.5.2.3b-1)$$

$$\Delta f_{ps} = \underline{2.63 \text{ ksi}} \quad \leftarrow$$

TIME DEPENDENT LOSSES

$$\Delta f_{pr2} = \underline{1.2 \text{ ksi}} = \Delta f_{pr1} \quad \leftarrow$$

SHRINKAGE LOSS

$$\Delta f_{psD} = \epsilon_{shD} E_p K_{df}$$

$$K_{df} = \frac{1}{1 + \frac{E_p}{E_{ci}} \frac{A_{ps}}{A_c} \left(1 + \frac{A_{ce} e^2}{I_c}\right)} \left[1 + .7 \psi_0 (t_f, t_i)\right]$$

$$\Delta f_{psD} = \underline{8.81 \text{ ksi}} \quad \leftarrow$$

CREEP

$$\Delta f_{pL0} \approx \underline{.15 \text{ ksi}}$$

TOTAL POST-TENSIONING LOSSES (NEGATIVE MOMENT)

$\Delta f_{pier} = 9.36 \text{ ksi}$ anchorage

$\Delta f_{pf} = 1.01 \text{ ksi}$ friction

$\Delta f_{pes} \approx 2.73 \text{ ksi}$ Elastic shortening

$\Delta f_{pr2} \approx 1.2 \text{ ksi}$ Relaxation

$\Delta f_{pco} \approx 8.81 \text{ ksi}$ Shrinkage

$\Delta f_{pc0} \approx .15 \text{ ksi}$ Creep

Total Loss $\approx \underline{23.26 \text{ ksi}}$ \leftarrow

$$c \approx \frac{19(.217)[.75(270) - 19.17] + 19(.217)[.75(270) - 23.26] + 15(60)}{.85(4.5)(.825) 54''}$$

$c \approx 14.054''$

$$M_n = 19(.217)[.75(270) - 19.17] \left[72'' + 5.25'' + 4'' - \frac{.825(14.054)}{2} \right]$$

$$+ 19(.217)[.75(270) - 23.26] \left[72'' + 5.25'' + 4'' - \frac{.825(14.054)}{2} \right]$$

$$+ 15(60) \left[72'' + 5.25'' + 4'' - \frac{.825(14.054)}{2} \right]$$

$M_n \approx 57032.4 + 55760.0 + 67907.4 \approx 180699.8$

$M_n \approx 15058.3 \text{ ft-k}$

$M_R = \phi M_n \approx .9(15058.3) \approx \underline{13552.5 \text{ ft-k}}$ \leftarrow

OKay

By: _____	Date _____	Project no. _____	Project code (SA#): _____
Chk'd: _____	Date _____	Structure no. _____	Sheet <u>180</u> of _____

COLORADO DEPARTMENT OF TRANSPORTATION
DESIGN COMPUTATIONS (Grid)

EXTRA NEGATIVE MOMENT ONLY POST-TENSIONING

amount of post tensioning saved

$$\sim 48' + \sim 67' + 96'$$

span 1 span 3 span 5

$$\text{total} \approx 211'$$

$$\# \text{ of ducts} = 50$$

Saves 2 strands/duct

$$(50)(2) * .75(270)(.27) * \frac{211'}{1000} \approx 927.2 \text{ MKFT}$$

ITEM 618-00002 Prestressing Steel Wire or Strand

assume \$100/unit from EEMA cost data


$$\text{Savings} \approx (927.2) 100 \approx \underline{\$92720}$$

FOR CONSTRUCTABILITY, LONG TERM
MAINTENANCE, SAFETY, ETC.

USE 4 strands entire length of deck
rather than just at negative moment
region.

By: Date	Project no.	Project code (SA#):
Chk'd: Date	Structure no.	Sheet 131 of

HORIZONTAL SHEAR



$$\phi = .9 \quad (5.5.4.2.1)$$

$$V_{U \max} \approx 850 \text{ k}$$

$$V_{ui} = V_u \div b_{vi} d_v \quad (5.8.4.2-1)$$

$$= \frac{850}{76.96(.9)(64)} = .192 \text{ Ksi} < .210$$

$$V_h = \frac{V_{U \max}}{d_e} \approx \frac{850 \text{ k}}{76.96 (.9)} \approx 12.27 \text{ Kips/in}$$

$$A_{vf \text{ min}} \geq \frac{.05 A_{cv}}{f_y} \quad (5.8.4.4-1)$$

$$A_{vf} \geq \frac{.05 [(2)(32)(12)]}{60 \text{ Ksi}} = .64 \text{ in}^2/\text{ft} \quad (2 \text{ studs per blockout})$$

for concrete placed against clean concrete surface
 not intentionally roughened (bottom of precast slabs)

$$c = .075 \text{ Ksi}$$

$$\mu = .6$$

$$K_1 = .2$$

$$K_2 = .8 \text{ Ksi}$$

$$(5.8.4.3)$$

$$V_{ni} \leq K_1 f'_c A_{cv} = (.2)(4.5)(64)(12) \approx 691.2 \text{ k/ft} \quad (5.8.4.1-4)$$

$$V_{ni} \leq K_2 A_{cv} = (.8)(64)(12) = 614.4 \text{ k/ft} \quad (5.8.4.1-5)$$

$$V_{ni} = c A_{cv} + \mu (A_{vf} f_y + P_c) \quad (5.8.4.1-3)$$

By: _____	Date _____	Project no. _____	Project code (SA#): _____
Chk'd: _____	Date _____	Structure no. _____	Sheet 182 of _____

COLORADO DEPARTMENT OF TRANSPORTATION
DESIGN COMPUTATIONS (Grid)

$$V_{ni} = c A_{cu} + u (A_{vf} f_y + P_c) \quad \text{wt of slab}$$

$$(12.27)(12) = .075(64)(12) + .6 \left[A_{vf}(60 \text{ ksi}) + 2.5 \text{ K} \right]$$

$$147.24 \text{ K} = 57.6 \text{ K} + 36 A_{vf} + 1.5 \text{ K}$$

$$A_{vf} \approx 2.45 \text{ in}^2/\text{ft}$$

blockouts spaced @ 2'-9" max (at closure pour)
 @ 2'-4" nom

for maximum spacing

$$A_{vf} = (2.45)(2.75) = 6.73 \text{ in}^2/\text{blockout pair}$$

$$A_{vf} = 3.37 \text{ in}^2/\text{blockout}$$

for 1" studs $A = .79$

$$\# \text{ of studs} = \frac{3.37}{.79} \approx 4.27 \Rightarrow 5 \text{ studs per hole (worst case)}$$

@ .1L

6 - 7/8" studs

$$A_{vf} = 1.84 \text{ in}^2/\text{ft}$$

$$\Rightarrow 2.53 \text{ in}^2/\text{blockout}$$

$$\Rightarrow 4 - 1" \text{ studs per blockout} \quad 5 - 7/8" \text{ studs}$$

@ .2L

$$A_{vf} \approx 1.22 \text{ in}^2/\text{ft}$$

$$\Rightarrow 1.68 \text{ in}^2/\text{blockout}$$

$$\Rightarrow 3 - 1" \text{ studs per blockout} \quad 3 - 7/8" \text{ studs}$$

@ .3L

$$A_{vf} \approx .465 \text{ in}^2/\text{ft} < .64 \text{ in}^2/\text{ft}$$

$$\Rightarrow .88 \text{ in}^2/\text{blockout}$$

$$\Rightarrow 2 - 1" \text{ studs} \quad 2 - 7/8" \text{ studs}$$

By: Date	Project no.	Project code (SA#):
Chk'd: Date	Structure no.	Sheet 183 of

COLORADO DEPARTMENT OF TRANSPORTATION
DESIGN COMPUTATIONS (Grid)

if bottom surface of precast slabs is intentionally roughened to .25" amplitude

$$C = .24 \text{ ksi}$$

$$\mu = 1.0$$

$$(12.27) (12) = .24(64)(12) + 1.0 [A_v f_{60 \text{ ksi}} + 2.5 k]$$

$$147.24 \text{ K} = 184.32 \text{ K} + A_v f_{60 + 2.5}$$


additional shear steel not required (friction sufficient)

minimum steel = .64 in²/ft $A_v f \geq \frac{.05 A_w}{f_y} \quad (5.8.4.4-1)$

$\Rightarrow .88 \text{ in}^2/\text{blockout}$ (worst case) = $\frac{2.75(.64)}{2} =$

2 - 7/8" stud or 3/4" stud

need #6 rebar min.



double amount of steel in pocket to reduce development length

use hooked steel



or rebar with terminator

By: _____	Date _____	Project no. _____	Project code (SA#): _____
Chk'd: _____	Date _____	Structure no. _____	Sheet <u>184</u> of _____

COLORADO DEPARTMENT OF TRANSPORTATION
DESIGN COMPUTATIONS (Grid)

Breakout Strength Per PCI Design Handbook

for 1 $\frac{7}{8}$ " ϕ stud (for yielding)

$$\begin{aligned} \phi V_s &= \phi n A_s e f_{ut} && \text{Eq 6.5.2.1} \\ &= .65 (1) (.60) (51 \text{ ksi}) \\ &= 19.89 \text{ kips} && \text{steel strength} \end{aligned}$$

$$N_{cb} = C_{bs} A_n C_{crb} \psi_{ed,N} \quad \text{Eq 6.5.4.1}$$

$$C_{bs} = 3.33 \lambda \sqrt{\frac{f'_c}{h_{ef}}} \quad \text{Eq 6.5.4.2}$$

assume $f'_c = 7.2 \text{ ksi}$

$h_{ef} =$

$\lambda = 1$

$$C_{bs} = 3.33 \sqrt{\frac{7200}{5}} = 126.36$$

$$A_n = 9 h_{ef}^2 = 9 \cdot 5^2 = 225$$

$C_{crb} = 1.0$ uncracked concrete

$$\psi_{ed,N} = .7 + .3 \left(\frac{d_{min}}{1.5 h_{ef}} \right) \leq 1.0 \quad \text{Eq 6.5.4.3}$$

$d_{min} \approx 9"$

$$\psi_{ed,N} = .7 + .3 \left(\frac{9}{(1.5)(5)} \right) = 1.0$$

$$N_{cb} = \frac{(126.36)(225)(1.0)(1.0)}{1000} = 28.43 \text{ kips}$$

$\phi = .7$ for unconfined

$$\phi N_{cb} = .7 (28.43) = 19.9 \text{ kips}$$

By: _____	Date _____	Project no. _____	Project code (SA#): _____
Chk'd: _____	Date _____	Structure no. _____	Sheet <u>185</u> of _____

Pullout strength

$$N_{PN} = 11.2 A_{brg} f_L C_{brg}$$

Eg 6.5.4.5

$$N_{PN} = 11.2 (.88)(7200)(1.0) / 1000$$


$$N_{PN} = 70.96 \text{ K}$$

GROUP STRENGTH (BREAKOUT)

$$\phi N_{cb} = \phi C_{bs} (x + 3h_{ef})(y + 3h_{ef}) C_{ub}$$

$$\phi N_{cb} = .7 (126.36)(0 + 3(5))(9 + 3(5)) (1.0) / 1000$$


$$\phi N_{cb} = 31.84 \text{ K}$$



required steel strength for shear (2 - 7/8" ϕ)

$$\phi V_s = .65 (2) (.60) 51 \text{ ksi}$$

$$= 39.78 \text{ K}$$




$$\phi N_{cb} = .7 (126.36)(3 + 3(5))(3 + 3(5))(1.0) / 1000$$

$$\phi N_{cb} = 28.66 \text{ K}$$

By: _____	Date _____	Project no. _____	Project code (SA#): _____
Chk'd: _____	Date _____	Structure no. _____	Sheet <u>136</u> of _____

COLORADO DEPARTMENT OF TRANSPORTATION
DESIGN COMPUTATIONS (Grid)

for 60 ksi rebar & lenth terminator




Required steel = .88 in² = 2 - 3/4" ϕ

$\phi V_s = .65(2)(.44)(60 \text{ ksi}) = 34.32 \text{ K}$

Group strength (Breakout)

$\phi N_{cb} = \phi C_{bs} (X + 3 \text{ hef}) (Y + 3 \text{ hef}) C_{c,b}$




= .7 (147.49) [3.1 + 3(4.67)] + [6 + 3(4.67)] 1.0/1000

$\phi N_{cb} = 35.3 \text{ K}$

for group spacings of 3.75'

min steel = 1.2 in² = 2 - 7/8" ϕ





$\phi V_s = .65(2)(.60)(60 \text{ ksi}) = 46.8 \text{ K}$

$\phi N_{cb} = .7(147.49)[5.4 + 3(4.67)][12" + 3(4.67)] 1.0/1000$
 = 52.1 K

By: _____	Date _____	Project no. _____	Project code (SA#): _____
Chk'd: _____	Date _____	Structure no. _____	Sheet 87 of _____

COLORADO DEPARTMENT OF TRANSPORTATION
DESIGN COMPUTATIONS (Grid)



$$\phi T_n = 4 \phi \sqrt{f'_c} A$$

$$D_p = 2 l_e + D_B$$

$$l_e \approx 5 \frac{5}{8} \text{''}$$

$$D_B = 1 \frac{3}{8} \text{''}$$

$$D_p = 12.625 \text{''}$$

$$A_p = \pi \left(\frac{D_p^2}{4} - \frac{D_B^2}{4} \right)$$

$$A_p = \pi \left(\frac{12.625^2}{4} - \frac{1.375^2}{4} \right) = 123.7 \text{ in}^2$$

$$\phi T_n = 4 (.65) \sqrt{7200} (123.7) / 1000 = 27.29 \text{ K}$$

22.1 K for 5" embed

$$T_n = A_b F_y$$

$$= \left(\frac{\pi (1.875^2)}{4} \right) 36 \text{ ksi}$$

$$= 21.65 \text{ kip}$$



3, 4, 5, 6, 7, 8

Provide min 5" embed for headed studs

By: _____	Date _____	Project no. _____	Project code (SA#): _____
Chk'd: _____	Date _____	Structure no. _____	Sheet <u>188</u> of _____

COLORADO DEPARTMENT OF TRANSPORTATION
DESIGN COMPUTATIONS (Grid)

for Leaton Terminator



$F_y = 60 \text{ ksi.}$

$T = (60 \text{ ksi}) \frac{\pi (7/8)^2}{4} = 36.1 \text{ Kips}$

$(1000) 36.1 = 4 (.65) \sqrt{7200} A$

$A = 163.54 \text{ in}^2$

$163.54 \text{ in}^2 = \frac{\pi D_p^2}{4} - \frac{\pi 2^2}{4}$

$D_p = 14.57''$

$14.57 = 2 l_e + 2''$

$l_e = 6.28''$

By: _____	Date _____	Project no. _____	Project code (SA#): _____
Chk'd: _____	Date _____	Structure no. _____	Sheet <u>189</u> of _____

COLORADO DEPARTMENT OF TRANSPORTATION
DESIGN COMPUTATIONS (Grid)

Use $5\frac{1}{2}$ " Haunch
everywhere except Abut 1.

Use $4\frac{1}{4}$ " Haunch @ Abut 1

By: _____	Date _____	Project no. _____	Project code (SA#): _____
Chk'd: _____	Date _____	Structure no. _____	Sheet <u>190</u> of _____

Design Computations

HAUNCH CALCULATION (GEOMETRY) (Interior Girder)


bottom of deck elevation at centerline 1 (A):	5219.540 ft	crossslope m =	2.00%
bottom of deck elevation at midpoint (B):	5219.080 ft	total girder width =	131.0 inches
bottom of deck elevation at centerline 2 (C):	5218.410 ft	x =	0.5 (midspan)

camber-	2.51	
deadloads (Δ) =	2.86 inches at midspan	2.98 hand calc values
28 Day Camber Estimate =	4.64 inches	5.15 hand calc values
RLO Tolerance =	20.0% = 0.93 inches	
Use Std. Tolerance-(Y/N)?	Y	
precast panel requirement =	1.00 inches	
depth tolerance =	0.50 inches	
slope tolerance =	1.31 inches	
Camber tolerance =	1.00 inches (AASHTO Standard)	
minimum clear at midspan =	2.81 inches	

Calculate H & y where H1=H2=H

k1=	-0.460
k2=	-0.327
y =	3.81 inches
Minimum Haunch (H) =	5.41 inches

USE H =	5.500 inches	MAX SAG Avg. haunch =	5.00 inches
average haunch =	4.17 inches	MAX SAG Avg. weight =	0.68 kip/ft
average weight =	0.57 kip/ft	thickness for strength =	4.00 inches (3.9 in. max.)
thickness for strength =	0.00 inches	nonstrength weight =	0.14 kip/ft
nonstrength weight =	0.57 kip/ft		



Design Computations

HAUNCH CALCULATION (GEOMETRY) (Interior Girder)

girder 3


bottom of deck elevation at centerline 1 (A):	5219.740 ft	crossslope m =	2.00%
bottom of deck elevation at midpoint (B):	5219.810 ft	total girder width =	131.0 inches
bottom of deck elevation at centerline 2 (C):	5219.650 ft	x =	0.5 (midspan)

camber-deadloads (Δ) =	2.94 inches at midspan	3.00 hand calc values
28 Day Camber Estimate =	4.81 inches	5.35 hand calc values
RLO Tolerance =	20.0% = 0.96 inches	
Use Std. Tolerance (Y/N)?	Y	
precast panel requirement =	1.00 inches	
depth tolerance =	0.50 inches	
slope tolerance =	1.31 inches	
Camber tolerance =	1.00 inches (AASHTO Standard)	
minimum clear at midspan =	2.81 inches	

Calculate H & y where H1=H2=H

k1=	0.070
k2=	0.200
y =	3.81 inches
Minimum Haunch (H) =	5.37 inches

USE H =	5.500 inches	MAX SAG Avg. haunch =	5.03 inches
average haunch =	4.20 inches	MAX SAG Avg. weight =	0.69 kip/ft
average weight =	0.57 kip/ft	thickness for strength =	4.00 inches (3.94 in. max.)
thickness for strength =	0.00 inches	nonstrength weight =	0.14 kip/ft
nonstrength weight =	0.57 kip/ft		



By: _____ Date _____
 Chk'd: _____ Date _____

Project no. _____
 Structure no. _____

Project code (SA#) _____
 Sheet 192 of _____

HAUNCH CALCULATION (GEOMETRY) (Interior Girder)


bottom of deck elevation at centerline 1 (A):	18.961 ft	crossslope m =	2.00%
bottom of deck elevation at midpoint (B):	19.245 ft	total girder width =	131.0 inches
bottom of deck elevation at centerline 2 (C):	19.449 ft	x =	0.5 (midspan)

camber-deadloads (Δ) =	0.69 inches at midspan	0.86 hand calc values
28 Day Camber Estimate =	1.13 inches	1.16 hand calc values
RLO Tolerance =	20.0% = 0.23 inches	
Use Std. Tolerance (Y/N)?	Y	
precast panel requirement =	1.00 inches	
depth tolerance =	0.50 inches	
slope tolerance =	1.31 inches	
Camber tolerance =	1.00 inches (AASHTO Standard)	
minimum clear at midspan =	2.81 inches	

Calculate H & y where $H_1=H_2=H$

k1=	0.284
k2=	0.302
y =	3.81 inches
Minimum Haunch (H) =	4.02 inches

USE H =	4.250 inches	MAX SAG Avg. haunch =	4.91 inches
average haunch =	4.08 inches	MAX SAG Avg. weight =	0.67 kip/ft
average weight =	0.56 kip/ft	thickness for strength =	4.00 inches (4.04 in. max.)
thickness for strength =	0.00 inches	nonstrength weight =	0.12 kip/ft
nonstrength weight =	0.56 kip/ft		





DESIGN STATUS

Span:4, Beam:3

RELEASE STRESSES (ksi)

Limiting Stresses		
Compression	Tens with Reinf	Tens without Reinf
4.050	-0.624	-0.200

Computed Stresses						
	Trans	0.10L/0.90L	0.20L/0.80L	0.30L/0.70L	0.40L/0.60L	Midspan
Location, ft	3.000	2.000	4.000	6.000	8.000	10.000
Precast-top	0.282	0.189	0.287	0.293	0.298	0.299
Bottom	0.311	0.207	0.307	0.300	0.296	0.294
As top, in2	0.000	0.000	0.000	0.000	0.000	0.000

FINAL STRESSES (ksi)

Limiting Stresses			
		Precast	Topping-Top
Final 1 (P/S+DL+LL)	Compression	5.400	4.320
Final 1	Tension	-0.570	-0.510
Final 2 (P/S+DL)	Compression	4.050	3.240
Final 3 (0.5(P/S+DL)+LL)	Compression	3.600	2.880

Computed Stresses									
POSITIVE MOMENT ENVELOPE : SERVICE I (Final 1)									
	Bearing	Trans	H/2	0.10L/0.90L	0.20L/0.80L	0.30L/0.70L	0.40L/0.60L	Midspan	
Location, ft	0.000	2.500	3.517	1.500	3.500	5.500	7.500	9.500	
Topping-top	-0.118	-0.082	-0.000	-0.083	-0.077	-0.074	-0.074	-0.078	
Precast-top	-0.020	0.245	0.247	0.148	0.261	0.282	0.293	0.295	
Bottom	0.399	0.507	0.307	0.423	0.479	0.450	0.440	0.447	

POSITIVE MOMENT ENVELOPE : SERVICE III (Final 1)									
	Bearing	Trans	H/2	0.10L/0.90L	0.20L/0.80L	0.30L/0.70L	0.40L/0.60L	Midspan	
Topping-top	-0.081	-0.085	-0.000	-0.086	-0.081	-0.080	-0.081	-0.084	
Precast-top	-0.001	0.243	0.247	0.146	0.258	0.279	0.290	0.292	
Bottom	0.289	0.517	0.307	0.431	0.493	0.468	0.459	0.467	

NEGATIVE MOMENT ENVELOPE : SERVICE I (Final 1)									
	Bearing	Trans	H/2	0.10L/0.90L	0.20L/0.80L	0.30L/0.70L	0.40L/0.60L	Midspan	
Topping-top	-0.557	-0.500	-0.000	-0.521	-0.481	-0.441	-0.387	-0.375	
Precast-top	-0.249	0.026	0.247	-0.082	0.049	0.090	0.130	0.140	
Bottom	1.686	1.731	0.307	1.708	1.662	1.525	1.355	1.316	

**NEGATIVE MOMENT ENVELOPE : SERVICE III (Final 1)**

	Bearing	Trans	H/2	0.10L/0.90L	0.20L/0.80L	0.30L/0.70L	0.40L/0.60L	Midspan
Topping-top	-0.472	-0.426	-0.000	-0.443	-0.410	-0.377	-0.333	-0.322
Precast-top	-0.205	0.065	0.247	-0.041	0.086	0.123	0.158	0.168
Bottom	1.438	1.513	0.307	1.478	1.454	1.337	1.196	1.161

POSITIVE MOMENT ENVELOPE : SERVICE I (Final 2)

	Bearing	Trans	H/2	0.10L/0.90L	0.20L/0.80L	0.30L/0.70L	0.40L/0.60L	Midspan
Topping-top	-0.134	-0.099	-0.000	-0.097	-0.100	-0.103	-0.107	-0.111
Precast-top	-0.029	0.236	0.247	0.140	0.248	0.266	0.272	0.278
Bottom	0.445	0.556	0.307	0.465	0.548	0.538	0.537	0.544

NEGATIVE MOMENT ENVELOPE : SERVICE I (Final 2)

	Bearing	Trans	H/2	0.10L/0.90L	0.20L/0.80L	0.30L/0.70L	0.40L/0.60L	Midspan
Topping-top	-0.134	-0.127	-0.000	-0.130	-0.125	-0.120	-0.115	-0.111
Precast-top	-0.029	0.221	0.247	0.123	0.235	0.258	0.272	0.278
Bottom	0.445	0.640	0.307	0.561	0.620	0.586	0.560	0.544

POSITIVE MOMENT ENVELOPE : SERVICE I (Final 3)

	Bearing	Trans	H/2	0.10L/0.90L	0.20L/0.80L	0.30L/0.70L	0.40L/0.60L	Midspan
Topping-top	-0.051	-0.032	-0.000	-0.034	-0.027	-0.022	-0.021	-0.022
Precast-top	-0.006	0.127	0.124	0.078	0.136	0.149	0.155	0.156
Bottom	0.176	0.229	0.154	0.191	0.205	0.182	0.172	0.175

NEGATIVE MOMENT ENVELOPE : SERVICE I (Final 3)

	Bearing	Trans	H/2	0.10L/0.90L	0.20L/0.80L	0.30L/0.70L	0.40L/0.60L	Midspan
Topping-top	-0.490	-0.437	-0.000	-0.456	-0.419	-0.381	-0.329	-0.319
Precast-top	-0.235	-0.085	0.124	-0.143	-0.069	-0.039	-0.006	0.001
Bottom	1.464	1.411	0.154	1.427	1.352	1.232	1.075	1.043

ULTIMATE MOMENT (k.ft)**STRENGTH I**

	Trans	H/2	0.10L/0.90L	0.20L/0.80L	0.30L/0.70L	0.40L/0.60L	Midspan
Location, ft	2.500	3.517	1.500	3.500	5.500	7.500	9.500
Mu-req'd	-353.8	0.0	-447.1	-177.0	-2.2	74.2	55.4
Mu-prv'd	2073.6	2178.3	1384.6	2176.5	2382.3	2587.8	2793.2

CAMBER / DEFLECTION (in) at Midspan (0.5 x L = 9.50 ft)**SERVICE I**

	Release	Mult	Erection	Mult	Final
Prestress	0.001	1.80	0.002	2.20	0.003
Self Wt.	-0.001	1.85	-0.002	2.40	-0.003
Deck + Haunch			-0.001	2.30	-0.003
DL-Prec. (DC)			-0.000	3.00	-0.001



Bentley

Colorado DOT
4201 E. Arkansas Ave. Denver CO 80222

Sheet: DS-3
Job No: BR R600-
297

Program: LEAP®
CONSPAN®
Version: 08.01.00.10

Copyright © Bentley Systems, Inc. 1984 - 2008.
www.bentley.com
1-800-778-4277

By: A. Pott
Date: Jun/12/2009
CKD:
Date:

File Name: 76-21-125-21-124_U72C.csl

	Release	Mult	Erection	Mult	Final
Diaphragm			0.000	3.00	0.000
DL-Prec. (DW)			0.000	3.00	0.000
DL-Comp. (DC)			0.001	3.00	0.004
DL-Comp. (DW)			0.006	3.00	0.017
Total	0.000		0.005		0.017

Positive values indicate upward deflection.

Strand Pattern: Span 4, Beam 2

ENDS MID-SPAN

Type	End Template	End Height	Middle Height	# of Strands
Straight	25	2.25		6
Straight	2	63.50		2
Straight	2	65.50		2
Straight	2	67.50		2

Initial Pull/CG Method

Kern Points (in) Total Strands Ycg (in)

Lower: 17.76	Total Strands: 12	End: 33.88
Upper: 54.08		Mid: 33.88

Draping:

Design:

Strand Pattern Library
 Save/Load Strand Patterns

Project:

Non-live Load Deflections

Stage 9: PS

POI	Location (ft)	Horiz (in)	Vertical (in)	Rotation (deg)
L.000	0.00	0.526	-0.137	1.3071
L.100	0.50	0.526	-0.000	1.3062
Sp1.000	0.50	0.526	-0.000	1.3062
Sp1.010	12.80	0.441	3.154	1.1131
Sp1.020	25.10	0.331	5.684	0.8481
Sp1.030	37.40	0.220	7.518	0.5728
Sp1.040	49.70	0.110	8.631	0.2886
Sp1.050	62.00	-0.000	9.003	0.0000
Sp1.060	74.30	-0.110	8.631	-0.2886
Sp1.070	86.60	-0.220	7.518	-0.5728
Sp1.080	98.90	-0.331	5.684	-0.8481
Sp1.090	111.20	-0.441	3.154	-1.1131
Sp1.100	123.50	-0.526	0.000	-1.3062
R.000	123.50	-0.526	0.000	-1.3062
R.100	124.00	-0.526	-0.137	-1.3071

Project:

Non-live Load Deflections

Stage 9: ComponentWeight

POI	Location (ft)	Horiz (in)	Vertical (in)	Rotation (deg)
L.000	0.00	0.019	0.085	-0.8108
L.100	0.50	0.019	-0.000	-0.8108
Sp1.000	0.50	0.019	-0.000	-0.8108
Sp1.010	12.80	0.018	-2.063	-0.7657
Sp1.020	25.10	0.015	-3.901	-0.6418
Sp1.030	37.40	0.011	-5.337	-0.4593
Sp1.040	49.70	0.006	-6.247	-0.2389
Sp1.050	62.00	0.000	-6.558	-0.0000
Sp1.060	74.30	-0.006	-6.247	0.2389
Sp1.070	86.60	-0.011	-5.337	0.4593
Sp1.080	98.90	-0.015	-3.901	0.6418
Sp1.090	111.20	-0.018	-2.063	0.7657
Sp1.100	123.50	-0.019	-0.000	0.8108
R.000	123.50	-0.019	-0.000	0.8108
R.100	124.00	-0.019	0.085	0.8108

Project:

Non-live Load Deflections

Stage 9: Shrinkage

POI	Location (ft)	Horiz (in)	Vertical (in)	Rotation (deg)
L.000	0.00	0.295	0.014	-0.1344
L.100	0.50	0.292	0.000	-0.1334
Sp1.000	0.50	0.292	0.000	-0.1334
Sp1.010	12.80	0.234	-0.310	-0.1072
Sp1.020	25.10	0.175	-0.552	-0.0807
Sp1.030	37.40	0.117	-0.726	-0.0540
Sp1.040	49.70	0.058	-0.830	-0.0270
Sp1.050	62.00	-0.000	-0.865	-0.0000
Sp1.060	74.30	-0.058	-0.830	0.0270
Sp1.070	86.60	-0.117	-0.726	0.0540
Sp1.080	98.90	-0.175	-0.552	0.0807
Sp1.090	111.20	-0.234	-0.310	0.1072
Sp1.100	123.50	-0.292	0.000	0.1334
R.000	123.50	-0.292	0.000	0.1334
R.100	124.00	-0.295	0.014	0.1344

Project:

Non-live Load Deflections

Stage 9: haunch

POI	Location (ft)	Horiz (in)	Vertical (in)	Rotation (deg)
L.000	0.00	0.001	0.003	-0.0283
L.100	0.50	0.001	-0.000	-0.0283
Sp1.000	0.50	0.001	-0.000	-0.0283
Sp1.010	12.80	0.001	-0.072	-0.0267
Sp1.020	25.10	0.001	-0.136	-0.0224
Sp1.030	37.40	0.000	-0.186	-0.0160
Sp1.040	49.70	0.000	-0.218	-0.0083
Sp1.050	62.00	0.000	-0.229	0.0000
Sp1.060	74.30	-0.000	-0.218	0.0083
Sp1.070	86.60	-0.000	-0.186	0.0160
Sp1.080	98.90	-0.001	-0.136	0.0224
Sp1.090	111.20	-0.001	-0.072	0.0267
Sp1.100	123.50	-0.001	-0.000	0.0283
R.000	123.50	-0.001	-0.000	0.0283
R.100	124.00	-0.001	0.003	0.0283

Project:

Non-live Load Deflections

Stage 9: extradeck

POI	Location (ft)	Horiz (in)	Vertical (in)	Rotation (deg)
L.000	0.00	0.002	0.010	-0.0989
L.100	0.50	0.002	-0.000	-0.0989
Sp1.000	0.50	0.002	-0.000	-0.0989
Sp1.010	12.80	0.002	-0.252	-0.0934
Sp1.020	25.10	0.002	-0.476	-0.0783
Sp1.030	37.40	0.001	-0.651	-0.0560
Sp1.040	49.70	0.001	-0.762	-0.0292
Sp1.050	62.00	0.000	-0.800	0.0000
Sp1.060	74.30	-0.001	-0.762	0.0292
Sp1.070	86.60	-0.001	-0.651	0.0560
Sp1.080	98.90	-0.002	-0.476	0.0783
Sp1.090	111.20	-0.002	-0.252	0.0934
Sp1.100	123.50	-0.002	-0.000	0.0989
R.000	123.50	-0.002	-0.000	0.0989
R.100	124.00	-0.002	0.010	0.0989

Colorado DOT
4201 E. Arkansas Ave.

PHONE: (303) 757-9589 | SHEET 2 OF 2
Denver, CO 80222 | JOB NO. 16212

PROGRAM: Conspllice PT - V 1.2.2 by LEAP Software, Inc. | BY AJP 02/16/2009
PHONE : TOLL-FREE 1-800-451-5327 TAMPA AREA: 813-985-9170 | CKD.

Project:

Sp4.080	241.50	0.000	0.003	-0.0023
Sp4.090	243.50	0.000	0.001	-0.0031
Sp4.100	245.50	0.000	-0.000	-0.0040
Sp5.000	245.50	0.000	-0.000	-0.0040
EndCmp	247.00	0.000	-0.002	-0.0053
BegCmp	247.00	0.000	-0.002	-0.0053
Sp5.010	258.00	0.000	-0.017	-0.0075
Sp5.020	270.50	0.000	-0.038	-0.0081
Sp5.030	283.00	0.000	-0.059	-0.0070
Sp5.040	295.50	0.000	-0.074	-0.0047
Sp5.050	308.00	-0.000	-0.083	-0.0016
Sp5.060	320.50	-0.000	-0.083	0.0019
Sp5.070	333.00	-0.000	-0.073	0.0054
Sp5.080	345.50	-0.000	-0.054	0.0084
Sp5.090	358.00	-0.000	-0.029	0.0105
Sp5.100	370.50	-0.001	-0.000	0.0113
R.000	370.50	-0.001	-0.000	0.0113
R.100	371.00	-0.001	0.001	0.0113

Project:

Non-live Load Deflections

Stage 9: bridgerail

POI	Location (ft)	Horiz (in)	Vertical (in)	Rotation (deg)
L.000	0.00	0.000	0.000	-0.0031
L.100	0.50	0.000	-0.000	-0.0031
Sp1.000	0.50	0.000	-0.000	-0.0031
Sp1.010	8.20	0.000	-0.005	-0.0029
Sp1.020	15.90	0.000	-0.009	-0.0023
Sp1.030	23.60	0.000	-0.012	-0.0016
Sp1.040	31.30	0.000	-0.014	-0.0007
Sp1.050	39.00	0.000	-0.015	0.0003
Sp1.060	46.70	0.000	-0.013	0.0011
Sp1.070	54.40	0.000	-0.011	0.0018
Sp1.080	62.10	0.000	-0.008	0.0023
Sp1.090	69.80	0.000	-0.004	0.0023
EndCmp	76.00	0.000	-0.001	0.0021
BegCmp	76.00	0.000	-0.001	0.0021
Sp1.100	77.50	0.000	-0.000	0.0019
Sp2.000	77.50	0.000	-0.000	0.0019
Sp2.010	79.50	0.000	0.001	0.0016
Sp2.020	81.50	0.000	0.001	0.0014
Sp2.030	83.50	0.000	0.002	0.0011
Sp2.040	85.50	0.000	0.002	0.0007
Sp2.050	87.50	0.000	0.003	0.0003
Sp2.060	89.50	0.000	0.003	-0.0003
Sp2.070	91.50	0.000	0.002	-0.0009
Sp2.080	93.50	0.000	0.002	-0.0017
Sp2.090	95.50	0.000	0.001	-0.0025
EndCmp	96.50	0.000	0.001	-0.0031
BegCmp	96.50	0.000	0.001	-0.0031
Sp2.100	97.50	0.000	-0.000	-0.0036
Sp3.000	97.50	0.000	-0.000	-0.0036
EndCmp	98.00	0.000	-0.000	-0.0038
BegCmp	98.00	0.000	-0.000	-0.0038
Sp3.010	110.30	0.000	-0.013	-0.0057
Sp3.020	123.10	0.000	-0.030	-0.0059
Sp3.030	135.90	0.000	-0.044	-0.0047
Sp3.040	148.70	0.000	-0.055	-0.0026
Sp3.050	161.50	0.000	-0.058	-0.0000
Sp3.060	174.30	-0.000	-0.055	0.0025
Sp3.070	187.10	-0.000	-0.045	0.0047
Sp3.080	199.90	-0.000	-0.030	0.0059
Sp3.090	212.70	-0.000	-0.014	0.0058
EndCmp	225.00	-0.000	-0.000	0.0040
BegCmp	225.00	-0.000	-0.000	0.0040
Sp3.100	225.50	-0.000	-0.000	0.0037
Sp4.000	225.50	-0.000	-0.000	0.0037
EndCmp	226.50	-0.000	0.001	0.0032
BegCmp	226.50	-0.000	0.001	0.0032
Sp4.010	227.50	-0.000	0.001	0.0029
Sp4.020	229.50	-0.000	0.002	0.0022
Sp4.030	231.50	-0.000	0.003	0.0015
Sp4.040	233.50	-0.000	0.004	0.0008
Sp4.050	235.50	-0.000	0.004	0.0000
Sp4.060	237.50	-0.000	0.004	-0.0007
Sp4.070	239.50	0.000	0.003	-0.0015

Colorado DOT
4201 E. Arkansas Ave.

PHONE: (303) 757-9589 | SHEET 2 OF 2
Denver, CO 80222 | JOB NO. 16212

PROGRAM: Conspllice PT - V 1.2.2 by LEAP Software, Inc. | BY AJP 02/16/2009
PHONE : TOLL-FREE 1-800-451-5327 TAMPA AREA: 813-985-9170 | CKD.

Project:

Sp4.080	241.50	0.000	0.013	-0.0115
Sp4.090	243.50	0.000	0.007	-0.0156
Sp4.100	245.50	0.000	-0.000	-0.0199
Sp5.000	245.50	0.000	-0.000	-0.0199
EndCmp	247.00	0.000	-0.008	-0.0263
BegCmp	247.00	0.000	-0.008	-0.0263
Sp5.010	258.00	0.001	-0.085	-0.0375
Sp5.020	270.50	0.001	-0.191	-0.0404
Sp5.030	283.00	0.001	-0.292	-0.0350
Sp5.040	295.50	0.000	-0.371	-0.0234
Sp5.050	308.00	-0.000	-0.413	-0.0079
Sp5.060	320.50	-0.001	-0.411	0.0096
Sp5.070	333.00	-0.002	-0.363	0.0269
Sp5.080	345.50	-0.002	-0.272	0.0419
Sp5.090	358.00	-0.002	-0.146	0.0525
Sp5.100	370.50	-0.003	-0.000	0.0564
R.000	370.50	-0.003	-0.000	0.0564
R.100	371.00	-0.003	0.006	0.0564

Project:

Non-live Load Deflections

Stage 9: asphalt

POI	Location (ft)	Horiz (in)	Vertical (in)	Rotation (deg)
L.000	0.00	0.001	0.002	-0.0153
L.100	0.50	0.001	-0.000	-0.0153
Sp1.000	0.50	0.001	-0.000	-0.0153
Sp1.010	8.20	0.001	-0.025	-0.0143
Sp1.020	15.90	0.001	-0.046	-0.0116
Sp1.030	23.60	0.001	-0.062	-0.0078
Sp1.040	31.30	0.001	-0.071	-0.0033
Sp1.050	39.00	0.001	-0.073	0.0013
Sp1.060	46.70	0.001	-0.067	0.0056
Sp1.070	54.40	0.000	-0.055	0.0091
Sp1.080	62.10	0.000	-0.038	0.0113
Sp1.090	69.80	0.000	-0.018	0.0116
EndCmp	76.00	0.000	-0.003	0.0103
BegCmp	76.00	0.000	-0.003	0.0103
Sp1.100	77.50	0.000	-0.000	0.0092
Sp2.000	77.50	0.000	-0.000	0.0092
Sp2.010	79.50	0.000	0.004	0.0081
Sp2.020	81.50	0.000	0.007	0.0069
Sp2.030	83.50	0.001	0.010	0.0053
Sp2.040	85.50	0.001	0.012	0.0035
Sp2.050	87.50	0.001	0.013	0.0012
Sp2.060	89.50	0.001	0.013	-0.0014
Sp2.070	91.50	0.001	0.012	-0.0045
Sp2.080	93.50	0.001	0.010	-0.0082
Sp2.090	95.50	0.001	0.006	-0.0126
EndCmp	96.50	0.001	0.003	-0.0152
BegCmp	96.50	0.001	0.003	-0.0152
Sp2.100	97.50	0.001	-0.000	-0.0179
Sp3.000	97.50	0.001	-0.000	-0.0179
EndCmp	98.00	0.001	-0.002	-0.0190
BegCmp	98.00	0.001	-0.002	-0.0190
Sp3.010	110.30	0.001	-0.067	-0.0285
Sp3.020	123.10	0.001	-0.148	-0.0295
Sp3.030	135.90	0.001	-0.222	-0.0235
Sp3.040	148.70	0.001	-0.272	-0.0130
Sp3.050	161.50	0.000	-0.290	-0.0002
Sp3.060	174.30	-0.000	-0.273	0.0127
Sp3.070	187.10	-0.001	-0.223	0.0234
Sp3.080	199.90	-0.001	-0.150	0.0295
Sp3.090	212.70	-0.001	-0.069	0.0289
EndCmp	225.00	-0.001	-0.002	0.0197
BegCmp	225.00	-0.001	-0.002	0.0197
Sp3.100	225.50	-0.000	-0.000	0.0187
Sp4.000	225.50	-0.000	-0.000	0.0187
EndCmp	226.50	-0.000	0.004	0.0160
BegCmp	226.50	-0.000	0.004	0.0160
Sp4.010	227.50	-0.000	0.007	0.0143
Sp4.020	229.50	-0.000	0.012	0.0109
Sp4.030	231.50	-0.000	0.016	0.0074
Sp4.040	233.50	-0.000	0.019	0.0038
Sp4.050	235.50	-0.000	0.019	0.0002
Sp4.060	237.50	-0.000	0.019	-0.0036
Sp4.070	239.50	0.000	0.017	-0.0075

Project:

Non-live Load Deflections

Stage 9: PS

POI	Location (ft)	Horiz (in)	Vertical (in)	Rotation (deg)
L.000	0.00	0.540	-0.134	1.2819
L.100	0.50	0.540	0.000	1.2813
Sp1.000	0.50	0.540	0.000	1.2813
Sp1.010	13.10	0.462	3.217	1.1290
Sp1.020	25.70	0.353	5.890	0.8878
Sp1.030	38.30	0.235	7.870	0.6067
Sp1.040	50.90	0.118	9.082	0.3068
Sp1.050	63.50	-0.000	9.487	0.0001
Sp1.060	76.10	-0.118	9.082	-0.3066
Sp1.070	88.70	-0.235	7.871	-0.6066
Sp1.080	101.30	-0.353	5.891	-0.8876
Sp1.090	113.90	-0.462	3.218	-1.1293
Sp1.100	126.50	-0.540	0.000	-1.2816
R.000	126.50	-0.540	0.000	-1.2816
R.100	127.00	-0.540	-0.134	-1.2823

Alternate Strands

Project:

Non-live Load Deflections

Stage 9: ComponentWeight

POI	Location (ft)	Horiz (in)	Vertical (in)	Rotation (deg)
L.000	0.00	0.021	0.091	-0.8715
L.100	0.50	0.021	-0.000	-0.8715
Sp1.000	0.50	0.021	-0.000	-0.8715
Sp1.010	13.10	0.020	-2.270	-0.8220
Sp1.020	25.70	0.017	-4.288	-0.6876
Sp1.030	38.30	0.012	-5.863	-0.4914
Sp1.040	50.90	0.006	-6.860	-0.2553
Sp1.050	63.50	-0.000	-7.200	0.0000
Sp1.060	76.10	-0.006	-6.860	0.2553
Sp1.070	88.70	-0.012	-5.863	0.4914
Sp1.080	101.30	-0.017	-4.288	0.6876
Sp1.090	113.90	-0.020	-2.270	0.8220
Sp1.100	126.50	-0.021	-0.000	0.8715
R.000	126.50	-0.021	-0.000	0.8715
R.100	127.00	-0.021	0.091	0.8715

Project:

Non-live Load Deflections

Stage 9: Shrinkage

POI	Location (ft)	Horiz (in)	Vertical (in)	Rotation (deg)
L.000	0.00	0.302	0.014	-0.1359
L.100	0.50	0.299	0.000	-0.1349
Sp1.000	0.50	0.299	0.000	-0.1349
Sp1.010	13.10	0.239	-0.323	-0.1100
Sp1.020	25.70	0.179	-0.579	-0.0835
Sp1.030	38.30	0.119	-0.763	-0.0560
Sp1.040	50.90	0.060	-0.874	-0.0280
Sp1.050	63.50	-0.000	-0.911	-0.0000
Sp1.060	76.10	-0.060	-0.874	0.0280
Sp1.070	88.70	-0.119	-0.763	0.0560
Sp1.080	101.30	-0.179	-0.579	0.0835
Sp1.090	113.90	-0.239	-0.323	0.1100
Sp1.100	126.50	-0.299	0.000	0.1349
R.000	126.50	-0.299	0.000	0.1349
R.100	127.00	-0.302	0.014	0.1359

Project:

Non-live Load Deflections

Stage 9: haunch

POI	Location (ft)	Horiz (in)	Vertical (in)	Rotation (deg)
L.000	0.00	0.001	0.003	-0.0304
L.100	0.50	0.001	-0.000	-0.0304
Sp1.000	0.50	0.001	-0.000	-0.0304
Sp1.010	13.10	0.001	-0.079	-0.0286
Sp1.020	25.70	0.001	-0.150	-0.0240
Sp1.030	38.30	0.000	-0.204	-0.0171
Sp1.040	50.90	0.000	-0.239	-0.0089
Sp1.050	63.50	-0.000	-0.251	0.0000
Sp1.060	76.10	-0.000	-0.239	0.0089
Sp1.070	88.70	-0.000	-0.204	0.0171
Sp1.080	101.30	-0.001	-0.150	0.0240
Sp1.090	113.90	-0.001	-0.079	0.0286
Sp1.100	126.50	-0.001	-0.000	0.0304
R.000	126.50	-0.001	-0.000	0.0304
R.100	127.00	-0.001	0.003	0.0304

Project:

Non-live Load Deflections

Stage 9: extradeck

POI	Location (ft)	Horiz (in)	Vertical (in)	Rotation (deg)
L.000	0.00	0.002	0.011	-0.1063
L.100	0.50	0.002	-0.000	-0.1063
Sp1.000	0.50	0.002	-0.000	-0.1063
Sp1.010	13.10	0.002	-0.277	-0.1003
Sp1.020	25.70	0.002	-0.523	-0.0839
Sp1.030	38.30	0.001	-0.716	-0.0600
Sp1.040	50.90	0.001	-0.837	-0.0312
Sp1.050	63.50	-0.000	-0.879	0.0000
Sp1.060	76.10	-0.001	-0.837	0.0312
Sp1.070	88.70	-0.001	-0.716	0.0600
Sp1.080	101.30	-0.002	-0.523	0.0839
Sp1.090	113.90	-0.002	-0.277	0.1003
Sp1.100	126.50	-0.002	-0.000	0.1063
R.000	126.50	-0.002	-0.000	0.1063
R.100	127.00	-0.002	0.011	0.1063

Project:

Non-live Load Deflections

Stage 9: bridgerail

POI	Location (ft)	Horiz (in)	Vertical (in)	Rotation (deg)
L.000	0.00	0.000	0.000	-0.0031
L.100	0.50	0.000	-0.000	-0.0031
Sp1.000	0.50	0.000	-0.000	-0.0031
Sp1.010	8.20	0.000	-0.005	-0.0029
Sp1.020	15.90	0.000	-0.009	-0.0023
Sp1.030	23.60	0.000	-0.012	-0.0016
Sp1.040	31.30	0.000	-0.014	-0.0007
Sp1.050	39.00	0.000	-0.015	0.0003
Sp1.060	46.70	0.000	-0.013	0.0011
Sp1.070	54.40	0.000	-0.011	0.0018
Sp1.080	62.10	0.000	-0.008	0.0023
Sp1.090	69.80	0.000	-0.004	0.0023
EndCmp	76.00	0.000	-0.001	0.0021
BegCmp	76.00	0.000	-0.001	0.0021
Sp1.100	77.50	0.000	-0.000	0.0018
Sp2.000	77.50	0.000	-0.000	0.0018
Sp2.010	79.50	0.000	0.001	0.0016
Sp2.020	81.50	0.000	0.001	0.0014
Sp2.030	83.50	0.000	0.002	0.0011
Sp2.040	85.50	0.000	0.002	0.0007
Sp2.050	87.50	0.000	0.003	0.0002
Sp2.060	89.50	0.000	0.003	-0.0003
Sp2.070	91.50	0.000	0.002	-0.0009
Sp2.080	93.50	0.000	0.002	-0.0016
Sp2.090	95.50	0.000	0.001	-0.0025
EndCmp	96.50	0.000	0.001	-0.0030
BegCmp	96.50	0.000	0.001	-0.0030
Sp2.100	97.50	0.000	-0.000	-0.0036
Sp3.000	97.50	0.000	-0.000	-0.0036
EndCmp	98.00	0.000	-0.000	-0.0038
BegCmp	98.00	0.000	-0.000	-0.0038
Sp3.010	110.30	0.000	-0.013	-0.0058
Sp3.020	123.10	0.000	-0.030	-0.0059
Sp3.030	135.90	0.000	-0.045	-0.0047
Sp3.040	148.70	0.000	-0.055	-0.0026
Sp3.050	161.50	0.000	-0.058	-0.0000
Sp3.060	174.30	-0.000	-0.055	0.0025
Sp3.070	187.10	-0.000	-0.045	0.0047
Sp3.080	199.90	-0.000	-0.030	0.0059
Sp3.090	212.70	-0.000	-0.014	0.0058
EndCmp	225.00	-0.000	-0.000	0.0039
BegCmp	225.00	-0.000	-0.000	0.0039
Sp3.100	225.50	-0.000	-0.000	0.0037
Sp4.000	225.50	-0.000	-0.000	0.0037
EndCmp	226.50	-0.000	0.001	0.0032
BegCmp	226.50	-0.000	0.001	0.0032
Sp4.010	227.50	-0.000	0.001	0.0029
Sp4.020	229.50	-0.000	0.002	0.0022
Sp4.030	231.50	-0.000	0.003	0.0015
Sp4.040	233.50	-0.000	0.004	0.0008
Sp4.050	235.50	-0.000	0.004	0.0000
Sp4.060	237.50	-0.000	0.004	-0.0007
Sp4.070	239.50	0.000	0.003	-0.0015

Colorado DOT
4201 E. Arkansas Ave.

PHONE: (303) 757-9589 | SHEET 2 OF 2
Denver, CO 80222 | JOB NO. 16212

PROGRAM: Conspllice PT - V 1.2.2 by LEAP Software, Inc. | BY AJP 02/16/2009
PHONE : TOLL-FREE 1-800-451-5327 TAMPA AREA: 813-985-9170 | CKD.

Project:

Sp4.080	241.50	0.000	0.003	-0.0023
Sp4.090	243.50	0.000	0.001	-0.0031
Sp4.100	245.50	0.000	-0.000	-0.0040
Sp5.000	245.50	0.000	-0.000	-0.0040
EndCmp	247.00	0.000	-0.002	-0.0053
BegCmp	247.00	0.000	-0.002	-0.0053
Sp5.010	258.00	0.000	-0.017	-0.0075
Sp5.020	270.50	0.000	-0.038	-0.0081
Sp5.030	283.00	0.000	-0.059	-0.0070
Sp5.040	295.50	0.000	-0.074	-0.0047
Sp5.050	308.00	-0.000	-0.083	-0.0016
Sp5.060	320.50	-0.000	-0.082	0.0019
Sp5.070	333.00	-0.000	-0.073	0.0054
Sp5.080	345.50	-0.000	-0.054	0.0084
Sp5.090	358.00	-0.001	-0.029	0.0105
Sp5.100	370.50	-0.001	-0.000	0.0113
R.000	370.50	-0.001	-0.000	0.0113
R.100	371.00	-0.001	0.001	0.0113

Project:

Non-live Load Deflections

Stage 9: asphalt

POI	Location (ft)	Horiz (in)	Vertical (in)	Rotation (deg)
L.000	0.00	0.001	0.002	-0.0153
L.100	0.50	0.001	-0.000	-0.0153
Sp1.000	0.50	0.001	-0.000	-0.0153
Sp1.010	8.20	0.001	-0.025	-0.0143
Sp1.020	15.90	0.001	-0.046	-0.0116
Sp1.030	23.60	0.001	-0.062	-0.0078
Sp1.040	31.30	0.001	-0.071	-0.0033
Sp1.050	39.00	0.001	-0.073	0.0013
Sp1.060	46.70	0.001	-0.067	0.0056
Sp1.070	54.40	0.001	-0.055	0.0091
Sp1.080	62.10	0.000	-0.038	0.0113
Sp1.090	69.80	0.000	-0.018	0.0116
EndCmp	76.00	0.000	-0.003	0.0103
BegCmp	76.00	0.000	-0.003	0.0103
Sp1.100	77.50	0.000	-0.000	0.0092
Sp2.000	77.50	0.000	-0.000	0.0092
Sp2.010	79.50	0.001	0.004	0.0081
Sp2.020	81.50	0.001	0.007	0.0068
Sp2.030	83.50	0.001	0.010	0.0053
Sp2.040	85.50	0.001	0.012	0.0034
Sp2.050	87.50	0.001	0.013	0.0012
Sp2.060	89.50	0.001	0.013	-0.0014
Sp2.070	91.50	0.001	0.012	-0.0045
Sp2.080	93.50	0.001	0.010	-0.0082
Sp2.090	95.50	0.001	0.006	-0.0126
EndCmp	96.50	0.001	0.003	-0.0151
BegCmp	96.50	0.001	0.003	-0.0151
Sp2.100	97.50	0.001	-0.000	-0.0178
Sp3.000	97.50	0.001	-0.000	-0.0178
EndCmp	98.00	0.001	-0.002	-0.0189
BegCmp	98.00	0.001	-0.002	-0.0189
Sp3.010	110.30	0.001	-0.067	-0.0287
Sp3.020	123.10	0.001	-0.149	-0.0296
Sp3.030	135.90	0.001	-0.222	-0.0235
Sp3.040	148.70	0.001	-0.272	-0.0130
Sp3.050	161.50	0.000	-0.291	-0.0002
Sp3.060	174.30	-0.000	-0.273	0.0126
Sp3.070	187.10	-0.001	-0.224	0.0233
Sp3.080	199.90	-0.001	-0.151	0.0296
Sp3.090	212.70	-0.001	-0.069	0.0290
EndCmp	225.00	-0.001	-0.002	0.0196
BegCmp	225.00	-0.001	-0.002	0.0196
Sp3.100	225.50	-0.001	-0.000	0.0186
Sp4.000	225.50	-0.001	-0.000	0.0186
EndCmp	226.50	-0.001	0.004	0.0159
BegCmp	226.50	-0.001	0.004	0.0159
Sp4.010	227.50	-0.001	0.007	0.0142
Sp4.020	229.50	-0.000	0.012	0.0108
Sp4.030	231.50	-0.000	0.016	0.0074
Sp4.040	233.50	-0.000	0.018	0.0038
Sp4.050	235.50	-0.000	0.019	0.0002
Sp4.060	237.50	-0.000	0.019	-0.0036
Sp4.070	239.50	0.000	0.017	-0.0075

Colorado DOT
4201 E. Arkansas Ave.

PHONE: (303) 757-9589 | SHEET 2 OF 2
Denver, CO 80222 | JOB NO. 16212

PROGRAM: Conspllice PT - V 1.2.2 by LEAP Software, Inc. | BY AJP 02/16/2009
PHONE : TOLL-FREE 1-800-451-5327 TAMPA AREA: 813-985-9170 | CKD.

Project:

Sp4.080	241.50	0.000	0.013	-0.0115
Sp4.090	243.50	0.000	0.007	-0.0156
Sp4.100	245.50	0.000	-0.000	-0.0199
Sp5.000	245.50	0.000	-0.000	-0.0199
EndCmp	247.00	0.000	-0.008	-0.0263
BegCmp	247.00	0.000	-0.008	-0.0263
Sp5.010	258.00	0.001	-0.085	-0.0375
Sp5.020	270.50	0.001	-0.191	-0.0404
Sp5.030	283.00	0.001	-0.292	-0.0350
Sp5.040	295.50	0.000	-0.371	-0.0234
Sp5.050	308.00	-0.000	-0.413	-0.0079
Sp5.060	320.50	-0.001	-0.411	0.0096
Sp5.070	333.00	-0.002	-0.363	0.0269
Sp5.080	345.50	-0.002	-0.272	0.0419
Sp5.090	358.00	-0.003	-0.146	0.0525
Sp5.100	370.50	-0.003	-0.000	0.0564
R.000	370.50	-0.003	-0.000	0.0564
R.100	371.00	-0.003	0.006	0.0564

Project:

Non-live Load Deflections

Stage 9: PS

POI	Location (ft)	Horiz (in)	Vertical (in)	Rotation (deg)
L.000	0.00	0.539	-0.140	1.3411
L.100	0.50	0.539	-0.000	1.3402
Sp1.000	0.50	0.539	-0.000	1.3402
Sp1.010	13.10	0.452	3.315	1.1420
Sp1.020	25.70	0.339	5.973	0.8700
Sp1.030	38.30	0.226	7.900	0.5875
Sp1.040	50.90	0.113	9.069	0.2957
Sp1.050	63.50	0.000	9.459	-0.0000
Sp1.060	76.10	-0.113	9.069	-0.2957
Sp1.070	88.70	-0.226	7.900	-0.5875
Sp1.080	101.30	-0.339	5.973	-0.8700
Sp1.090	113.90	-0.452	3.315	-1.1420
Sp1.100	126.50	-0.539	-0.000	-1.3402
R.000	126.50	-0.539	-0.000	-1.3402
R.100	127.00	-0.539	-0.140	-1.3411

9.335

Project:

Non-live Load Deflections

Stage 9: ComponentWeight

POI	Location (ft)	Horiz (in)	Vertical (in)	Rotation (deg)
L.000	0.00	0.021	0.091	-0.8714
L.100	0.50	0.021	-0.000	-0.8714
Sp1.000	0.50	0.021	-0.000	-0.8714
Sp1.010	13.10	0.019	-2.270	-0.8229
Sp1.020	25.70	0.016	-4.293	-0.6897
Sp1.030	38.30	0.012	-5.874	-0.4936
Sp1.040	50.90	0.006	-6.875	-0.2568
Sp1.050	63.50	0.000	-7.218	-0.0000
Sp1.060	76.10	-0.006	-6.875	0.2568
Sp1.070	88.70	-0.012	-5.874	0.4936
Sp1.080	101.30	-0.016	-4.293	0.6897
Sp1.090	113.90	-0.019	-2.270	0.8229
Sp1.100	126.50	-0.021	-0.000	0.8714
R.000	126.50	-0.021	-0.000	0.8714
R.100	127.00	-0.021	0.091	0.8714

Project:

Non-live Load Deflections

Stage 9: Shrinkage

POI	Location (ft)	Horiz (in)	Vertical (in)	Rotation (deg)
L.000	0.00	0.302	0.014	-0.1377
L.100	0.50	0.299	-0.000	-0.1367
Sp1.000	0.50	0.299	-0.000	-0.1367
Sp1.010	13.10	0.240	-0.325	-0.1099
Sp1.020	25.70	0.180	-0.579	-0.0827
Sp1.030	38.30	0.120	-0.762	-0.0553
Sp1.040	50.90	0.060	-0.871	-0.0277
Sp1.050	63.50	0.000	-0.908	-0.0000
Sp1.060	76.10	-0.060	-0.871	0.0277
Sp1.070	88.70	-0.120	-0.762	0.0553
Sp1.080	101.30	-0.180	-0.579	0.0827
Sp1.090	113.90	-0.240	-0.325	0.1099
Sp1.100	126.50	-0.299	0.000	0.1367
R.000	126.50	-0.299	0.000	0.1367
R.100	127.00	-0.302	0.014	0.1377

Project:

Non-live Load Deflections

Stage 9: haunch

POI	Location (ft)	Horiz (in)	Vertical (in)	Rotation (deg)
L.000	0.00	0.001	0.003	-0.0304
L.100	0.50	0.001	-0.000	-0.0304
Sp1.000	0.50	0.001	-0.000	-0.0304
Sp1.010	13.10	0.001	-0.079	-0.0287
Sp1.020	25.70	0.001	-0.150	-0.0240
Sp1.030	38.30	0.000	-0.205	-0.0172
Sp1.040	50.90	0.000	-0.240	-0.0090
Sp1.050	63.50	-0.000	-0.252	-0.0000
Sp1.060	76.10	-0.000	-0.240	0.0090
Sp1.070	88.70	-0.000	-0.205	0.0172
Sp1.080	101.30	-0.001	-0.150	0.0240
Sp1.090	113.90	-0.001	-0.079	0.0287
Sp1.100	126.50	-0.001	-0.000	0.0304
R.000	126.50	-0.001	-0.000	0.0304
R.100	127.00	-0.001	0.003	0.0304

Project:

Non-live Load Deflections

Stage 9: extradeck

POI	Location (ft)	Horiz (in)	Vertical (in)	Rotation (deg)
L.000	0.00	0.002	0.011	-0.1063
L.100	0.50	0.002	-0.000	-0.1063
Sp1.000	0.50	0.002	-0.000	-0.1063
Sp1.010	13.10	0.002	-0.277	-0.1004
Sp1.020	25.70	0.002	-0.524	-0.0841
Sp1.030	38.30	0.001	-0.717	-0.0602
Sp1.040	50.90	0.001	-0.839	-0.0313
Sp1.050	63.50	-0.000	-0.881	-0.0000
Sp1.060	76.10	-0.001	-0.839	0.0313
Sp1.070	88.70	-0.001	-0.717	0.0602
Sp1.080	101.30	-0.002	-0.524	0.0841
Sp1.090	113.90	-0.002	-0.277	0.1004
Sp1.100	126.50	-0.002	-0.000	0.1063
R.000	126.50	-0.002	-0.000	0.1063
R.100	127.00	-0.002	0.011	0.1063

Project:

Non-live Load Deflections

Stage 9: bridgerail

POI	Location (ft)	Horiz (in)	Vertical (in)	Rotation (deg)
L.000	0.00	0.000	0.000	-0.0031
L.100	0.50	0.000	-0.000	-0.0031
Sp1.000	0.50	0.000	-0.000	-0.0031
Sp1.010	8.20	0.000	-0.005	-0.0029
Sp1.020	15.90	0.000	-0.009	-0.0023
Sp1.030	23.60	0.000	-0.012	-0.0016
Sp1.040	31.30	0.000	-0.014	-0.0007
Sp1.050	39.00	0.000	-0.015	0.0003
Sp1.060	46.70	0.000	-0.013	0.0011
Sp1.070	54.40	0.000	-0.011	0.0018
Sp1.080	62.10	0.000	-0.008	0.0023
Sp1.090	69.80	0.000	-0.004	0.0023
EndCmp	76.00	0.000	-0.001	0.0021
BegCmp	76.00	0.000	-0.001	0.0021
Sp1.100	77.50	0.000	-0.000	0.0019
Sp2.000	77.50	0.000	-0.000	0.0019
Sp2.010	79.50	0.000	0.001	0.0016
Sp2.020	81.50	0.000	0.001	0.0014
Sp2.030	83.50	0.000	0.002	0.0011
Sp2.040	85.50	0.000	0.002	0.0007
Sp2.050	87.50	0.000	0.003	0.0003
Sp2.060	89.50	0.000	0.003	-0.0003
Sp2.070	91.50	0.000	0.002	-0.0009
Sp2.080	93.50	0.000	0.002	-0.0017
Sp2.090	95.50	0.000	0.001	-0.0025
EndCmp	96.50	0.000	0.001	-0.0031
BegCmp	96.50	0.000	0.001	-0.0031
Sp2.100	97.50	0.000	-0.000	-0.0036
Sp3.000	97.50	0.000	-0.000	-0.0036
EndCmp	98.00	0.000	-0.000	-0.0038
BegCmp	98.00	0.000	-0.000	-0.0038
Sp3.010	110.30	0.000	-0.013	-0.0057
Sp3.020	123.10	0.000	-0.030	-0.0059
Sp3.030	135.90	0.000	-0.044	-0.0047
Sp3.040	148.70	0.000	-0.055	-0.0026
Sp3.050	161.50	0.000	-0.058	-0.0000
Sp3.060	174.30	-0.000	-0.055	0.0025
Sp3.070	187.10	-0.000	-0.045	0.0047
Sp3.080	199.90	-0.000	-0.030	0.0059
Sp3.090	212.70	-0.000	-0.014	0.0058
EndCmp	225.00	-0.000	-0.000	0.0040
BegCmp	225.00	-0.000	-0.000	0.0040
Sp3.100	225.50	-0.000	-0.000	0.0037
Sp4.000	225.50	-0.000	-0.000	0.0037
EndCmp	226.50	-0.000	0.001	0.0032
BegCmp	226.50	-0.000	0.001	0.0032
Sp4.010	227.50	-0.000	0.001	0.0029
Sp4.020	229.50	-0.000	0.002	0.0022
Sp4.030	231.50	-0.000	0.003	0.0015
Sp4.040	233.50	-0.000	0.004	0.0008
Sp4.050	235.50	-0.000	0.004	0.0000
Sp4.060	237.50	-0.000	0.004	-0.0007
Sp4.070	239.50	0.000	0.003	-0.0015

Colorado DOT
4201 E. Arkansas Ave.

PHONE: (303) 757-9589 | SHEET 2 OF 2
Denver, CO 80222 | JOB NO. 16212

PROGRAM: Consplince PT - V 1.2.2 by LEAP Software, Inc. | BY AJP 02/16/2009
PHONE : TOLL-FREE 1-800-451-5327 TAMPA AREA: 813-985-9170 | CKD.

Project:

Sp4.080	241.50	0.000	0.003	-0.0023
Sp4.090	243.50	0.000	0.001	-0.0031
Sp4.100	245.50	0.000	-0.000	-0.0040
Sp5.000	245.50	0.000	-0.000	-0.0040
EndCmp	247.00	0.000	-0.002	-0.0053
BegCmp	247.00	0.000	-0.002	-0.0053
Sp5.010	258.00	0.000	-0.017	-0.0075
Sp5.020	270.50	0.000	-0.038	-0.0081
Sp5.030	283.00	0.000	-0.059	-0.0070
Sp5.040	295.50	0.000	-0.074	-0.0047
Sp5.050	308.00	-0.000	-0.083	-0.0016
Sp5.060	320.50	-0.000	-0.083	0.0019
Sp5.070	333.00	-0.000	-0.073	0.0054
Sp5.080	345.50	-0.000	-0.054	0.0084
Sp5.090	358.00	-0.000	-0.029	0.0105
Sp5.100	370.50	-0.001	-0.000	0.0113
R.000	370.50	-0.001	-0.000	0.0113
R.100	371.00	-0.001	0.001	0.0113

Project:

Non-live Load Deflections

Stage 9: asphalt

POI	Location (ft)	Horiz (in)	Vertical (in)	Rotation (deg)
L.000	0.00	0.001	0.002	-0.0153
L.100	0.50	0.001	-0.000	-0.0153
Sp1.000	0.50	0.001	-0.000	-0.0153
Sp1.010	8.20	0.001	-0.025	-0.0143
Sp1.020	15.90	0.001	-0.046	-0.0116
Sp1.030	23.60	0.001	-0.062	-0.0078
Sp1.040	31.30	0.001	-0.071	-0.0033
Sp1.050	39.00	0.001	-0.073	0.0013
Sp1.060	46.70	0.001	-0.067	0.0056
Sp1.070	54.40	0.000	-0.055	0.0091
Sp1.080	62.10	0.000	-0.038	0.0113
Sp1.090	69.80	0.000	-0.018	0.0116
EndCmp	76.00	0.000	-0.003	0.0103
BegCmp	76.00	0.000	-0.003	0.0103
Sp1.100	77.50	0.000	-0.000	0.0092
Sp2.000	77.50	0.000	-0.000	0.0092
Sp2.010	79.50	0.000	0.004	0.0081
Sp2.020	81.50	0.000	0.007	0.0069
Sp2.030	83.50	0.001	0.010	0.0053
Sp2.040	85.50	0.001	0.012	0.0035
Sp2.050	87.50	0.001	0.013	0.0012
Sp2.060	89.50	0.001	0.013	-0.0014
Sp2.070	91.50	0.001	0.012	-0.0045
Sp2.080	93.50	0.001	0.010	-0.0082
Sp2.090	95.50	0.001	0.006	-0.0126
EndCmp	96.50	0.001	0.003	-0.0152
BegCmp	96.50	0.001	0.003	-0.0152
Sp2.100	97.50	0.001	-0.000	-0.0179
Sp3.000	97.50	0.001	-0.000	-0.0179
EndCmp	98.00	0.001	-0.002	-0.0190
BegCmp	98.00	0.001	-0.002	-0.0190
Sp3.010	110.30	0.001	-0.067	-0.0285
Sp3.020	123.10	0.001	-0.148	-0.0295
Sp3.030	135.90	0.001	-0.222	-0.0235
Sp3.040	148.70	0.001	-0.272	-0.0130
Sp3.050	161.50	0.000	-0.290	-0.0002
Sp3.060	174.30	-0.000	-0.273	0.0127
Sp3.070	187.10	-0.001	-0.223	0.0234
Sp3.080	199.90	-0.001	-0.150	0.0295
Sp3.090	212.70	-0.001	-0.069	0.0289
EndCmp	225.00	-0.001	-0.002	0.0197
BegCmp	225.00	-0.001	-0.002	0.0197
Sp3.100	225.50	-0.000	-0.000	0.0187
Sp4.000	225.50	-0.000	-0.000	0.0187
EndCmp	226.50	-0.000	0.004	0.0160
BegCmp	226.50	-0.000	0.004	0.0160
Sp4.010	227.50	-0.000	0.007	0.0143
Sp4.020	229.50	-0.000	0.012	0.0109
Sp4.030	231.50	-0.000	0.016	0.0074
Sp4.040	233.50	-0.000	0.019	0.0038
Sp4.050	235.50	-0.000	0.019	0.0002
Sp4.060	237.50	-0.000	0.019	-0.0036
Sp4.070	239.50	0.000	0.017	-0.0075

Colorado DOT
4201 E. Arkansas Ave.


PHONE: (303) 757-9589 | SHEET 2 OF 2
Denver, CO 80222 | JOB NO. 16212

PROGRAM: Conspllice PT - V 1.2.2 by LEAP Software, Inc. | BY AJP 02/16/2009
PHONE : TOLL-FREE 1-800-451-5327 TAMPA AREA: 813-985-9170 | CKD.


Project:

Sp4.080	241.50	0.000	0.013	-0.0115
Sp4.090	243.50	0.000	0.007	-0.0156
Sp4.100	245.50	0.000	-0.000	-0.0199
Sp5.000	245.50	0.000	-0.000	-0.0199
EndCmp	247.00	0.000	-0.008	-0.0263
BegCmp	247.00	0.000	-0.008	-0.0263
Sp5.010	258.00	0.001	-0.085	-0.0375
Sp5.020	270.50	0.001	-0.191	-0.0404
Sp5.030	283.00	0.001	-0.292	-0.0350
Sp5.040	295.50	0.000	-0.371	-0.0234
Sp5.050	308.00	-0.000	-0.413	-0.0079
Sp5.060	320.50	-0.001	-0.411	0.0096
Sp5.070	333.00	-0.002	-0.363	0.0269
Sp5.080	345.50	-0.002	-0.272	0.0419
Sp5.090	358.00	-0.002	-0.146	0.0525
Sp5.100	370.50	-0.003	-0.000	0.0564
R.000	370.50	-0.003	-0.000	0.0564
R.100	371.00	-0.003	0.006	0.0564


Phase 1 & 2



Phase 4




Phase 3 & 5



COLORADO DEPARTMENT OF TRANSPORTATION
DESIGN COMPUTATIONS (Grid)

1.2 K

FOR FINAL




8" deck \Rightarrow .1 K/ft of deck / ft longitudinal
transverse


$$Wt = (25') (1') = 2.5 \text{ K/ft for final}$$

@ erection

Phase 1 & 2




Exterior girder




.5 K/ft lighter

Phase 4



~~.1 K/ft heavier~~
 Same as interior
 girder phase 1 & 2

Phase 3 & 5



.6 K/ft heavier

By: _____	Date _____	Project no. _____	Project code (SA#): _____
Chk'd: _____	Date _____	Structure no. _____	Sheet <u>220</u> of _____

COLORADO DEPARTMENT OF TRANSPORTATION
DESIGN COMPUTATIONS (Grid)

SPAN 1

GIRDER 3

extra load $\approx .6$ k/ft

camber @ erection $\approx 0.46''$

30 strands

GIRDER 2

less load $\approx .5$ k/ft

camber @ erection = $.521$

increased camber (deck) $\approx .05''$

$\approx .526''$

30 strands

GIRDER 1

camber @ erection $\approx .538''$

30 strands

GIRDER 4

~~extra load = $.1$ k/ft~~

~~camber @ erection = $.511''$~~

~~30 strands~~

Same as girder 2

By: _____	Date _____	Project no. _____	Project code (SA#): _____
Chk'd: _____	Date _____	Structure no. _____	Sheet <u>221</u> of _____



Program: LEAP®
CONSPAN®
Version: 08.01.00.10

Copyright © Bentley Systems, Inc. 1984 - 2008.
www.bentley.com
1-800-778-4277

By: A. Pott
Date: Jan/4/2010
CKD:
Date:

File Name: 76-21-125-21-124 U72C.csl

DESIGN STATUS

Span:1, Beam:1

RELEASE STRESSES (ksi)

Limiting Stresses

Compression	Tens with Reinf	Tens without Reinf
4.050	-0.624	-0.200

Computed Stresses

	Trans	0.10L/0.90L	0.20L/0.80L	0.30L/0.70L	0.40L/0.60L	Midspan	Depress.
Location, ft	3.000	7.600	15.200	22.800	30.400	38.000	26.600
Precast-top	-0.296	-0.193	-0.186	-0.151	-0.091	-0.072	-0.116
Bottom	1.257	1.157	1.470	1.584	1.527	1.508	1.551
As_top, in2	3.372	0.000	0.000	0.000	0.000	0.000	0.000

FINAL STRESSES (ksi)

Limiting Stresses

		Precast	Topping-Top
Final 1 (P/S+DL+LL)	Compression	5.400	4.320
Final 1	Tension	-0.570	-0.510
Final 2 (P/S+DL)	Compression	4.050	3.240
Final 3 (0.5(P/S+DL)+LL)	Compression	3.600	2.880

Computed Stresses

POSITIVE MOMENT ENVELOPE : SERVICE I (Final 1)

	Bearing	Trans	H/2	0.10L/0.90L	0.20L/0.80L	0.30L/0.70L	0.40L/0.60L	Midspan
Location, ft	0.000	2.250	3.517	6.850	14.450	22.050	29.650	37.250
Topping-top	0.017	0.051	0.069	0.111	0.180	0.217	0.229	0.217
Precast-top	-0.078	-0.178	-0.095	0.106	0.360	0.562	0.712	0.754
Bottom	0.264	0.949	0.829	0.538	0.434	0.295	0.125	0.111

POSITIVE MOMENT ENVELOPE : SERVICE III (Final 1)

	Bearing	Trans	H/2	0.10L/0.90L	0.20L/0.80L	0.30L/0.70L	0.40L/0.60L	Midspan
Topping-top	0.014	0.043	0.057	0.092	0.150	0.182	0.192	0.182
Precast-top	-0.079	-0.182	-0.101	0.096	0.344	0.543	0.692	0.735
Bottom	0.272	0.973	0.861	0.589	0.517	0.394	0.228	0.208

NEGATIVE MOMENT ENVELOPE : SERVICE I (Final 1)

	Bearing	Trans	H/2	0.10L/0.90L	0.20L/0.80L	0.30L/0.70L	0.40L/0.60L	Midspan
Topping-top	-0.251	-0.206	-0.183	-0.126	-0.021	0.019	0.031	0.038
Precast-top	-0.222	-0.317	-0.232	-0.022	0.250	0.453	0.604	0.656
Bottom	1.021	1.667	1.531	1.199	0.994	0.846	0.675	0.609



Program: LEAP®
CONSPAN®
Version: 08.01.00.10

Copyright © Bentley Systems, Inc. 1984 - 2008.
www.bentley.com
1-800-778-4277

By: A. Pott
Date: Jan/4/2010
CKD:
Date:

File Name: 76-21-125-21-124_U72C.csl

NEGATIVE MOMENT ENVELOPE : SERVICE III (Final 1)

	Bearing	Trans	H/2	0.10L/0.90L	0.20L/0.80L	0.30L/0.70L	0.40L/0.60L	Midspan
Topping-top	-0.208	-0.170	-0.151	-0.103	-0.015	0.020	0.032	0.038
Precast-top	-0.199	-0.298	-0.214	-0.010	0.253	0.454	0.605	0.657
Bottom	0.900	1.567	1.442	1.136	0.977	0.843	0.672	0.607

POSITIVE MOMENT ENVELOPE : SERVICE I (Final 2)

	Bearing	Trans	H/2	0.10L/0.90L	0.20L/0.80L	0.30L/0.70L	0.40L/0.60L	Midspan
Topping-top	0.003	0.009	0.012	0.019	0.032	0.040	0.043	0.042
Precast-top	-0.085	-0.200	-0.126	0.057	0.279	0.465	0.611	0.658
Bottom	0.303	1.067	0.988	0.794	0.846	0.788	0.640	0.598

NEGATIVE MOMENT ENVELOPE : SERVICE I (Final 2)

	Bearing	Trans	H/2	0.10L/0.90L	0.20L/0.80L	0.30L/0.70L	0.40L/0.60L	Midspan
Topping-top	-0.035	-0.027	-0.023	-0.012	0.009	0.024	0.035	0.042
Precast-top	-0.106	-0.220	-0.145	0.040	0.266	0.457	0.607	0.658
Bottom	0.412	1.167	1.085	0.882	0.911	0.831	0.661	0.598

POSITIVE MOMENT ENVELOPE : SERVICE I (Final 3)

	Bearing	Trans	H/2	0.10L/0.90L	0.20L/0.80L	0.30L/0.70L	0.40L/0.60L	Midspan
Topping-top	0.016	0.047	0.063	0.101	0.164	0.198	0.207	0.196
Precast-top	-0.035	-0.077	-0.032	0.078	0.220	0.329	0.407	0.425
Bottom	0.113	0.416	0.335	0.141	0.011	-0.099	-0.195	-0.188

NEGATIVE MOMENT ENVELOPE : SERVICE I (Final 3)

	Bearing	Trans	H/2	0.10L/0.90L	0.20L/0.80L	0.30L/0.70L	0.40L/0.60L	Midspan
Topping-top	-0.233	-0.192	-0.171	-0.120	-0.025	0.007	0.013	0.017
Precast-top	-0.169	-0.207	-0.159	-0.042	0.117	0.225	0.301	0.327
Bottom	0.816	1.083	0.989	0.758	0.538	0.431	0.344	0.310

ULTIMATE MOMENT (k.ft)

STRENGTH I

Location, ft	Trans	H/2	0.10L/0.90L	0.20L/0.80L	0.30L/0.70L	0.40L/0.60L	Midspan	Depress
Mu-req'd	1508.7	2119.2	3583.2	6147.4	7731.1	8447.7	8366.4	8089.4
Mu-prv'd	5423.5	5776.5	6704.2	9731.4	11283.5	11721.3	11722.3	11502.4

CAMBER / DEFLECTION (in) at Midspan (0.5 x L = 37.25 ft)

SERVICE I

	Release	Mult	Erection	Mult	Final
Prestress	0.701	1.80	1.263	2.20	1.543
Self Wt.	-0.234	1.85	-0.432	2.40	-0.561
Deck + Haunch			-0.269	2.30	-0.618
DL-Prec. (DC)			0.000	3.00	0.000



Colorado DOT
4201 E. Arkansas Ave. Denver CO 80222

Sheet: DS-3
Job No: BR R600-
297

Program: LEAP®
CONSPAN®
Version: 08.01.00.10

Copyright © Bentley Systems, Inc. 1984 - 2008.
www.bentley.com
1-800-778-4277

By: A. Pott
Date: Jan/4/2010
CKD:
Date:

File Name: 76-21-125-21-124 U72C.csl

	Release	Mult	Erection	Mult	Final
Diaphragm			0.000	3.00	0.000
DL-Prec. (DW)			0.000	3.00	0.000
DL-Comp. (DC)			-0.004	3.00	-0.012
DL-Comp. (DW)			-0.020	3.00	-0.059
Total	0.468		0.538		0.293

Positive values indicate upward deflection.

224



Program: LEAP®
CONSPAN®
Version: 08.01.00.10

Copyright © Bentley Systems, Inc. 1984 - 2008.
www.bentley.com
1-800-778-4277

By: A. Pott
Date: Jan/4/2010
CKD:
Date:

File Name: 76-21-125-21-124_U72C.csl

PROPERTIES

Span: 1, Beam: 1

PRECAST DATA:

Section Id	U72C					
Type	Open Box Beam					
Fing width	Top	131.000	in	Bot	54.000	in
thick	Top	6.350	in	Bot	8.100	in
Stems	No	2				
	Top	7.500	in			
	Bot	7.500	in			
Shear width		15.000	in			

GENERAL BRIDGE DATA:

Bridge Width	197.00	ft
Curb-to-curb	194.00	ft
Beam Spac. Lt./Rt	11.00/ 25.00	ft
Lane width	12.00	ft
Number of lanes	16	
Interior/Exterior	Exterior	
Start Skew Angle	-34.00	degrees
End Skew Angle	-34.00	degrees

TOPPING DATA:

Deck	Thickness	8.000	in
Haunch:	Thickness	4.400	in
	Width	64.000	in
Effective	width	282.000	in (Art. 4.6.2.6.1)

GENERAL LOAD DATA:

Dead loads on composite: See Project info for composite loads

GENERAL SPAN DATA:

Overall length	76.000	ft
----------------	--------	----



Program: LEAP®
CONSPAN®
Version: 08.01.00.10

Copyright © Bentley Systems, Inc. 1984 - 2008.
www.bentley.com
1-800-778-4277

By: A. Pott
Date: Jan/4/2010
CKD:
Date:

File Name: 76-21-125-21-124 U72C.csl

Release length	76.000	ft
Design length	74.500	ft

KERN POINTS:

Upper	54.09	in
Lower	17.76	in

DISTRIBUTION FACTORS (Art. 4.6.2.2):

Live Negative Moment	Left Side	(2+ lanes loaded)	1.657	(Calculated)	(#)
Live Negative Moment	Right Side	(2+ lanes loaded)	1.657	(Calculated)	(#)
Live Negative Moment	Left Side	(1 lane loaded)	1.248	(Calculated)	(#)
Live Negative Moment	Right Side	(1 lane loaded)	1.248	(Calculated)	(#)
Live Positive Moment		(2+ lanes loaded)	1.657	(Calculated)	(#)
Live Positive Moment		(1 lane loaded)	1.248	(Calculated)	(#)
Live Shear		(2+ lanes loaded)	1.880	(Calculated)	(#)
Live Shear		(1 lane loaded)	1.416	(Calculated)	(#)

(#) Lever rule (C4.6.2.2.1)

Dead Loads and Pedestrian Load distributed based on Tributary Fraction

Pedestrian	0.119	(Calculated)
Comp. DC	0.119	(Calculated)
Comp. DW	0.119	(Calculated)

RESISTANCE FACTORS (Art. 5.5.4.2):

Flexure Reinforced	
Compression controlled sections	0.75
Tension controlled sections	0.90
Flexure Prestressed	
Compression controlled sections	0.75
Tension controlled sections	1.00
Shear	0.90



Program: LEAP®
CONSPAN®
Version: 08.01.00.10

Copyright © Bentley Systems, Inc. 1984 - 2008.
www.bentley.com
1-800-778-4277

By: A. Pott
Date: Jan/4/2010
CKD:
Date:

File Name: 76-21-125-21-124_U72C.csl

Span: 1, Beam: 1

SECTION PROPERTIES:

	PRECAST		COMPOSITE		
Area	1765.1	in2	4034.8	in2	#
Total Height	72.00	in	84.40	in	
Mom. of Inertia (Ixx)	1154250	in4	3085155	in4	#
Ht. of c.g.	35.84	in	60.52	in	#
Density	150.00	pcf	150.00	pcf	
Self-weight	1838.6	plf	4482.0	plf	
Mom. of Inertia (Iyy)	2057200.1	in4			
Poisson's Ratio	0.2				

(#) Of Total Section using $E_c/E_c = 0.8944$

Use transformed strand and rebar: Strand Only

Location,	ft	Bearing 0.00	Trans 2.25	H/2 3.52	0.10L 6.85	0.20L 14.45	0.30L 22.05	0.40L 29.65	Midspan 37.25
Precast:(At Release, using	Ec =	4980.8ksi)							
Area,	in2	1770.2	1785.6	1785.6	1785.6	1792.6	1795.8	1795.8	1795.8
Yb,	in	35.75	35.47	35.47	35.47	35.35	35.29	35.29	35.29
MI(Ixx),	in4	1159467	1174940	1174940	1174940	1182351	1185930	1185930	1185930
Composite:(At Final, using	Ec =	5751.4ksi)							
Area,	in2	4039.1	4052.0	4052.0	4052.0	4057.8	4060.5	4060.5	4060.5
Yb,	in	60.46	60.28	60.28	60.28	60.20	60.16	60.16	60.16
MI(Ixx),	in4	3098906	3139987	3139987	3139987	3159249	3168460	3168460	3168460

Span: 1, Beam: 1

STRESS LIMITS (Art. 5.9.4):

STRESS LIMITS AT RELEASE BEFORE LOSSES:

	PRECAST	
Strength	6.75	ksi
Elasticity	4980.8	ksi
Max comp	4.05	ksi
Max tens	-0.20	ksi
Max tens, w/reinf	-0.62	ksi



Program: LEAP®
CONSPAN®
Version: 08.01.00.10

Copyright © Bentley Systems, Inc. 1984 - 2008.
www.bentley.com
1-800-778-4277

By: A. Pott
Date: Jan/4/2010
CKD:
Date:

File Name: 76-21-125-21-124 U72C.csl

STRESS LIMITS AT FINAL AFTER LOSSES:

	PRECAST	DECK
Strength	9.00 ksi	7.20 ksi
Elasticity	5751.38 ksi	5144.19 ksi

STRESS LIMITS AT FINAL 1 (P/S + DL + LL):

	PRECAST	DECK
Max comp	5.40 ksi	4.32 ksi

STRESS LIMITS AT FINAL 2 (P/S + DL):

	PRECAST	DECK
Max comp	4.05 ksi	3.24 ksi

STRESS LIMITS AT FINAL 3 (50% P/S + 50% DL + LL):

	PRECAST	DECK
Max comp	3.60 ksi	2.88 ksi

SERVICE III (Tension):

	PRECAST	DECK
Max tens	-0.57 ksi	-0.51 ksi

Span: 1, Beam: 1

PRESTRESSED STEEL:

30 strands, 6/10-270K-LL, Low relaxation strands
Depressed at 0.35L (26.60 ft from member end)

END PATTERN (Ycg = 3.46 in):



Program: LEAP®
CONSPAN®

Copyright © Bentley Systems, Inc. 1984 - 2008.
www.bentley.com
1-800-778-4277

By: A. Pott
Date: Jan/4/2010
CKD:
Date:

Version: 08.01.00.10
File Name: 76-21-125-21-124_U72C.csl

16 @ 2.250 in | 8 @ 4.060 in | 6 @ 5.880 in

SHIELDING AND REDUCED INITIAL PULLS:

Group	Strands	End	Heights	Mid	End	Shielding	Mid	Initial Frac	Pull Pull/Str
1	2	2.250	in	2.250	in	10.00	ft	0.00	ft 75.0 % 43.9
5	2	4.060	in	4.060	in	10.00	ft	0.00	ft 75.0 % 43.9
9	2	2.250	in	2.250	in	12.00	ft	0.00	ft 75.0 % 43.9
10	2	2.250	in	2.250	in	14.00	ft	0.00	ft 75.0 % 43.9
11	2	2.250	in	2.250	in	16.00	ft	0.00	ft 75.0 % 43.9

Check for Art. 5.11.4.3 (debond termination distances): OK

Strand Diameter	0.600	in
Strand Area	0.217	in ²
Total Strand Area	6.510	in ²
Trans. Len, bonded	3.000	ft
Trans. Len, debonded	3.000	ft
Dev. Len, bonded	11.556	ft
Dev. Len, debonded	14.445	ft
Holddown Force	0.000	kips
Tensile Strength(fpu)	270.0	ksi
Initial Prestress = 0.75fpu	202.5	ksi
Initial Pull	1318.3	kips
Beam Shrtng (PL/AE)	0.135	in

REINFORCING STEEL:

Tension steel:		
fy	60.0	ksi
Es	29000	ksi
fs	24.0	ksi

Stirrups:

# legs	Size	fy (ksi)	Area (in ²)	Spacing (in)	Start (ft)	End (ft)
4	US#3[M10]	60.0	0.44	3.33	0.2500	16.9167
4	US#3[M10]	60.0	0.44	5.00	16.9167	59.0833
4	US#3[M10]	60.0	0.44	3.33	59.0833	75.7500

LOSSES

Note: Values are calculated at Midspan

229



Program: LEAP®
CONSPAN®
Version: 08.01.00.10

Copyright © Bentley Systems, Inc. 1984 - 2008.
www.bentley.com
1-800-778-4277

By: A. Pott
Date: Jan/4/2010
CKD:
Date:

File Name: 76-21-125-21-124_U72C.csl

Str. area	6.5100	in2
Ycg	3.46	in
P_init	1318.3	kips
Ecc	32.38	in
Days to release	0.75	
Rel. Humid.(RH)	60.0	%
Es	28500.0	ksi
Eci	4981	ksi

AASHTO LOSSES

Elastic Shortening ** 8.29 ksi (Eq 5.9.5.2.3a-1), (fcgp= 1.449 ksi)

Elastic Gains		Gains	Adjustment
due to Precast Loads		-2.93 ksi	0.00 ksi
due to Composite Loads		-0.54 ksi	0.00 ksi
due to Live Loads		-1.82 ksi	0.00 ksi

Time Dependent Losses (Approximate Method (Art.5.9.5.3))

	Initial	Final	
Steel relaxation	0.00 ksi	2.40 ksi	(Eq 5.9.5.3-1)
Concrete shrinkage	0.00 ksi	8.52 ksi	(Eq 5.9.5.3-1)
Concrete creep	0.00 ksi	5.30 ksi	(Eq 5.9.5.3-1)
Sub-total	8.29 ksi	10.93 ksi	(5.40 %)
Total Prestress Losses		19.22 ksi	(9.49 %)

Prestressing Stress Limit Check (Table 5.9.3.1)
initial fpi = 202.5 ksi < 0.75 fpu, OK
initial fpe = 183.3 ksi < 0.80 fpy, OK

** Since the transformed section properties option has been selected, even though ES losses have been calculated explicitly here, they are not included as a part of stress calculations. Please see theory section for complete explanation.



DESIGN STATUS

Span:1, Beam:2

RELEASE STRESSES (ksi)

Limiting Stresses		
Compression	Tens with Reinf	Tens without Reinf
4.050	-0.624	-0.200

Computed Stresses							
	Trans	0.10L/0.90L	0.20L/0.80L	0.30L/0.70L	0.40L/0.60L	Midspan	Depress.
Location, ft	3.000	7.600	15.200	22.800	30.400	38.000	26.600
Precast-top	-0.296	-0.193	-0.186	-0.151	-0.091	-0.072	-0.116
Bottom	1.257	1.157	1.470	1.584	1.527	1.508	1.551
As_top, in2	3.372	0.000	0.000	0.000	0.000	0.000	0.000

FINAL STRESSES (ksi)

Limiting Stresses			
		Precast	Topping-Top
Final 1 (P/S+DL+LL)	Compression	5.400	4.320
Final 1	Tension	-0.570	-0.510
Final 2 (P/S+DL)	Compression	4.050	3.240
Final 3 (0.5(P/S+DL)+LL)	Compression	3.600	2.880

Computed Stresses								
POSITIVE MOMENT ENVELOPE : SERVICE I (Final 1)								
	Bearing	Trans	H/2	0.10L/0.90L	0.20L/0.80L	0.30L/0.70L	0.40L/0.60L	Midspan
Location, ft	0.000	2.250	3.517	6.850	14.450	22.050	29.650	37.250
Topping-top	0.015	0.046	0.062	0.099	0.161	0.195	0.205	0.195
Precast-top	-0.079	-0.177	-0.093	0.111	0.371	0.579	0.733	0.778
Bottom	0.268	0.955	0.836	0.548	0.448	0.307	0.134	0.116

POSITIVE MOMENT ENVELOPE : SERVICE III (Final 1)								
	Bearing	Trans	H/2	0.10L/0.90L	0.20L/0.80L	0.30L/0.70L	0.40L/0.60L	Midspan
Topping-top	0.013	0.038	0.052	0.083	0.135	0.164	0.173	0.164
Precast-top	-0.080	-0.181	-0.098	0.103	0.358	0.562	0.716	0.761
Bottom	0.275	0.976	0.865	0.594	0.522	0.396	0.227	0.204

NEGATIVE MOMENT ENVELOPE : SERVICE I (Final 1)								
	Bearing	Trans	H/2	0.10L/0.90L	0.20L/0.80L	0.30L/0.70L	0.40L/0.60L	Midspan
Topping-top	-0.223	-0.183	-0.162	-0.111	-0.017	0.020	0.032	0.039
Precast-top	-0.204	-0.297	-0.211	0.001	0.277	0.486	0.642	0.695
Bottom	0.966	1.616	1.483	1.156	0.961	0.810	0.632	0.564



Program: LEAP®
CONSPAN®
Version: 08.01.00.10

Copyright © Bentley Systems, Inc. 1984 - 2008.
www.bentley.com
1-800-778-4277

By: A. Pott
Date: Jan/4/2010
CKD:
Date:

File Name: 76-21-125-21-124 U72C.csl

NEGATIVE MOMENT ENVELOPE : SERVICE III (Final 1)

	Bearing	Trans	H/2	0.10L/0.90L	0.20L/0.80L	0.30L/0.70L	0.40L/0.60L	Midspan
Topping-top	-0.186	-0.152	-0.134	-0.091	-0.012	0.021	0.033	0.040
Precast-top	-0.184	-0.281	-0.196	0.011	0.280	0.487	0.642	0.695
Bottom	0.856	1.527	1.403	1.099	0.946	0.807	0.630	0.562

POSITIVE MOMENT ENVELOPE : SERVICE I (Final 2)

	Bearing	Trans	H/2	0.10L/0.90L	0.20L/0.80L	0.30L/0.70L	0.40L/0.60L	Midspan
Topping-top	0.003	0.009	0.012	0.019	0.033	0.041	0.044	0.043
Precast-top	-0.085	-0.196	-0.119	0.069	0.303	0.497	0.648	0.697
Bottom	0.303	1.061	0.979	0.779	0.818	0.750	0.597	0.554

NEGATIVE MOMENT ENVELOPE : SERVICE I (Final 2)

	Bearing	Trans	H/2	0.10L/0.90L	0.20L/0.80L	0.30L/0.70L	0.40L/0.60L	Midspan
Topping-top	-0.036	-0.028	-0.023	-0.012	0.009	0.025	0.036	0.043
Precast-top	-0.106	-0.215	-0.138	0.053	0.290	0.489	0.644	0.697
Bottom	0.418	1.167	1.082	0.871	0.886	0.796	0.620	0.554

POSITIVE MOMENT ENVELOPE : SERVICE I (Final 3)

	Bearing	Trans	H/2	0.10L/0.90L	0.20L/0.80L	0.30L/0.70L	0.40L/0.60L	Midspan
Topping-top	0.014	0.041	0.055	0.089	0.145	0.174	0.183	0.173
Precast-top	-0.036	-0.079	-0.033	0.077	0.220	0.330	0.409	0.429
Bottom	0.116	0.425	0.346	0.159	0.039	-0.068	-0.164	-0.161

NEGATIVE MOMENT ENVELOPE : SERVICE I (Final 3)

	Bearing	Trans	H/2	0.10L/0.90L	0.20L/0.80L	0.30L/0.70L	0.40L/0.60L	Midspan
Topping-top	-0.205	-0.169	-0.150	-0.105	-0.021	0.008	0.014	0.018
Precast-top	-0.151	-0.190	-0.142	-0.026	0.132	0.242	0.320	0.347
Bottom	0.757	1.033	0.942	0.721	0.517	0.412	0.322	0.287

ULTIMATE MOMENT (k.ft)

STRENGTH I

Location, ft	Trans	H/2	0.10L/0.90L	0.20L/0.80L	0.30L/0.70L	0.40L/0.60L	Midspan	Depress
Mu-req'd	1448.1	2040.1	3461.5	5963.0	7522.4	8242.5	8185.6	7882.5
Mu-prv'd	5423.6	5776.8	6705.1	9736.4	11290.0	11729.1	11730.2	11509.6

CAMBER / DEFLECTION (in) at Midspan (0.5 x L = 37.25 ft)

SERVICE I

	Release	Mult	Erection	Mult	Final
Prestress	0.701	1.80	1.263	2.20	1.543
Self Wt.	-0.234	1.85	-0.432	2.40	-0.561
Deck + Haunch			-0.284	2.30	-0.653
DL-Prec. (DC)			0.000	3.00	0.000



Program: LEAP®
CONSPAN®
Version: 08.01.00.10

Copyright © Bentley Systems, Inc. 1984 - 2008.
www.bentley.com
1-800-778-4277

By: A. Pott
Date: Jan/4/2010
CKD:
Date:

File Name: 76-21-125-21-124 U72C.csl

	Release	Mult	Erection	Mult	Final
Diaphragm			0.000	3.00	0.000
DL-Prec. (DW)			0.000	3.00	0.000
DL-Comp. (DC)			-0.004	3.00	-0.013
DL-Comp. (DW)			-0.021	3.00	-0.062
Total	0.468		0.521		0.254

Positive values indicate upward deflection.



DESIGN STATUS

Span:1, Beam:7

RELEASE STRESSES (ksi)

Limiting Stresses		
Compression	Tens with Reinf	Tens without Reinf
4.050	-0.624	-0.200

Computed Stresses							
	Trans	0.10L/0.90L	0.20L/0.80L	0.30L/0.70L	0.40L/0.60L	Midspan	Depress.
Location, ft	3.000	7.600	15.200	22.800	30.400	38.000	26.600
Precast-top	0.296	-0.193	-0.186	-0.151	-0.091	-0.072	-0.116
Bottom	1.257	1.157	1.470	1.584	1.527	1.508	1.551
As_top, in2	3.372	0.000	0.000	0.000	0.000	0.000	0.000

FINAL STRESSES (ksi)

Limiting Stresses			
		Precast	Topping-Top
Final 1 (P/S+DL+LL)	Compression	5.400	4.320
Final 1	Tension	-0.570	-0.510
Final 2 (P/S+DL)	Compression	4.050	3.240
Final 3 (0.5(P/S+DL)+LL)	Compression	3.600	2.880

Computed Stresses									
POSITIVE MOMENT ENVELOPE : SERVICE I (Final 1)									
	Bearing	Trans	H/2	0.10L/0.90L	0.20L/0.80L	0.30L/0.70L	0.40L/0.60L	Midspan	
Location, ft	0.000	2.250	3.517	6.850	14.450	22.050	29.650	37.250	
Topping-top	0.015	0.046	0.062	0.099	0.161	0.195	0.205	0.195	
Precast-top	-0.079	-0.162	-0.070	0.155	0.452	0.686	0.857	0.906	
Bottom	0.268	0.940	0.814	0.506	0.370	0.204	0.016	-0.008	

POSITIVE MOMENT ENVELOPE : SERVICE III (Final 1)									
	Bearing	Trans	H/2	0.10L/0.90L	0.20L/0.80L	0.30L/0.70L	0.40L/0.60L	Midspan	
Topping-top	0.013	0.038	0.052	0.083	0.135	0.164	0.173	0.164	
Precast-top	-0.080	-0.165	-0.075	0.146	0.438	0.670	0.840	0.890	
Bottom	0.275	0.962	0.842	0.552	0.444	0.293	0.108	0.080	

NEGATIVE MOMENT ENVELOPE : SERVICE I (Final 1)									
	Bearing	Trans	H/2	0.10L/0.90L	0.20L/0.80L	0.30L/0.70L	0.40L/0.60L	Midspan	
Topping-top	-0.223	-0.183	-0.162	-0.111	-0.017	0.020	0.032	0.039	
Precast-top	-0.204	-0.282	-0.188	0.044	0.358	0.593	0.765	0.824	
Bottom	0.966	1.602	1.460	1.115	0.883	0.707	0.513	0.440	



Program: LEAP®
CONSPAN®
Version: 08.01.00.10
File Name: 76-21-125-21-124_U72C.csl

Copyright © Bentley Systems, Inc. 1984 - 2008.
www.bentley.com
1-800-778-4277

By: A. Pott
Date: Jan/4/2010
CKD:
Date:

NEGATIVE MOMENT ENVELOPE : SERVICE III (Final 1)

	Bearing	Trans	H/2	0.10L/0.90L	0.20L/0.80L	0.30L/0.70L	0.40L/0.60L	Midspan
Topping-top	-0.186	-0.152	-0.134	-0.091	-0.012	0.021	0.033	0.040
Precast-top	-0.184	-0.266	-0.173	0.054	0.360	0.594	0.765	0.824
Bottom	0.856	1.512	1.380	1.057	0.868	0.704	0.511	0.438

POSITIVE MOMENT ENVELOPE : SERVICE I (Final 2)

	Bearing	Trans	H/2	0.10L/0.90L	0.20L/0.80L	0.30L/0.70L	0.40L/0.60L	Midspan
Topping-top	0.003	0.009	0.012	0.019	0.033	0.041	0.044	0.043
Precast-top	-0.085	-0.181	-0.096	0.113	0.384	0.604	0.771	0.826
Bottom	0.303	1.046	0.957	0.737	0.740	0.647	0.479	0.430

NEGATIVE MOMENT ENVELOPE : SERVICE I (Final 2)

	Bearing	Trans	H/2	0.10L/0.90L	0.20L/0.80L	0.30L/0.70L	0.40L/0.60L	Midspan
Topping-top	-0.036	-0.028	-0.023	-0.012	0.009	0.025	0.036	0.043
Precast-top	-0.106	-0.200	-0.115	0.096	0.371	0.596	0.767	0.826
Bottom	0.418	1.153	1.059	0.829	0.809	0.693	0.501	0.430

POSITIVE MOMENT ENVELOPE : SERVICE I (Final 3)

	Bearing	Trans	H/2	0.10L/0.90L	0.20L/0.80L	0.30L/0.70L	0.40L/0.60L	Midspan
Topping-top	0.014	0.041	0.055	0.089	0.145	0.174	0.183	0.173
Precast-top	-0.036	-0.071	-0.022	0.098	0.260	0.384	0.471	0.494
Bottom	0.116	0.417	0.335	0.138	-0.000	-0.119	-0.224	-0.223

NEGATIVE MOMENT ENVELOPE : SERVICE I (Final 3)

	Bearing	Trans	H/2	0.10L/0.90L	0.20L/0.80L	0.30L/0.70L	0.40L/0.60L	Midspan
Topping-top	-0.205	-0.169	-0.150	-0.105	-0.021	0.008	0.014	0.018
Precast-top	-0.151	-0.182	-0.130	-0.004	0.172	0.295	0.381	0.411
Bottom	0.757	1.026	0.931	0.700	0.479	0.360	0.263	0.225

ULTIMATE MOMENT (k.ft)

STRENGTH I

Location, ft	Trans	H/2	0.10L/0.90L	0.20L/0.80L	0.30L/0.70L	0.40L/0.60L	Midspan	Depress
	2.250	3.517	6.850	14.450	22.050	29.650	37.250	25.850
Mu-req'd	1498.9	2118.1	3606.4	6234.1	7883.9	8658.1	8619.2	8271.0
Mu-prv'd	5423.6	5776.8	6705.1	9736.4	11290.0	11729.1	11730.2	11509.6

CAMBER / DEFLECTION (in) at Midspan (0.5 x L = 37.25 ft)

SERVICE I

	Release	Mult	Erection	Mult	Final
Prestress	0.701	1.80	1.263	2.20	1.543
Self Wt.	-0.234	1.85	-0.432	2.40	-0.561
Deck + Haunch			-0.284	2.30	-0.653
DL-Prec. (DC)			-0.051	3.00	-0.152



Program: LEAP®
CONSPAN®
Version: 08.01.00.10

Copyright © Bentley Systems, Inc. 1984 - 2008.
www.bentley.com
1-800-778-4277

By: A. Pott
Date: Jan/4/2010
CKD:
Date:

File Name: 76-21-125-21-124 U72C.csl

	Release	Mult	Erection	Mult	Final
Diaphragm			0.000	3.00	0.000
DL-Prec. (DW)			0.000	3.00	0.000
DL-Comp. (DC)			-0.004	3.00	-0.013
DL-Comp. (DW)			-0.021	3.00	-0.062
Total	0.468		0.471		0.102

Positive values indicate upward deflection.



Program: LEAP®
CONSPAN®
Version: 08.01.00.10

Copyright © Bentley Systems, Inc. 1984 - 2008.
www.bentley.com
1-800-778-4277

By: A. Pott
Date: Jan/4/2010
CKD:
Date:

File Name: 76-21-125-21-124 U72C.csl

PROPERTIES

Span: 1, Beam: 2

PRECAST DATA:

Section Id	U72C					
Type	Open Box Beam					
Fing width	Top	131.000	in	Bot	54.000	in
thick	Top	6.350	in	Bot	8.100	in
Stems	No	2				
	Top	7.500	in			
	Bot	7.500	in			
Shear width	15.000		in			

GENERAL BRIDGE DATA:

Bridge Width	197.00	ft
Curb-to-curb	194.00	ft
Beam Spac. Lt./Rt	25.00/ 25.00	ft
Lane width	12.00	ft
Number of lanes	16	
Interior/Exterior	Interior	
Start Skew Angle	-34.00	degrees
End Skew Angle	-34.00	degrees

TOPPING DATA:

Deck	Thickness	8.000	in
Haunch:			
	Thickness	4.400	in
	Width	64.000	in
Effective	width	300.000	in (Art. 4.6.2.6.1)

GENERAL LOAD DATA:

Dead loads on precast:
UNITS: (Point: kips, Location: ft)
(Line: klf)

DC/DW	Type	Mag.	Loc.
DC	Line	-0.500	-
DC	Line	0.500	-



Program: LEAP®
CONSPAN®
Version: 08.01.00.10

Copyright © Bentley Systems, Inc. 1984 - 2008.
www.bentley.com
1-800-778-4277

By: A. Pott
Date: Jan/4/2010
CKD:
Date:

File Name: 76-21-125-21-124_U72C.csl

Dead loads on composite: See Project info for composite loads

GENERAL SPAN DATA:

Overall length	76.000	ft
Release length	76.000	ft
Design length	74.500	ft

KERN POINTS:

Upper	54.09	in
Lower	17.76	in

DISTRIBUTION FACTORS (Art. 4.6.2.2):

Live Negative Moment	Left Side	(2+ lanes loaded)	1.498	(Calculated)	(#)
Live Negative Moment	Right Side	(2+ lanes loaded)	1.498	(Calculated)	(#)
Live Negative Moment	Left Side	(1 lane loaded)	0.931	(Calculated)	(#)
Live Negative Moment	Right Side	(1 lane loaded)	0.931	(Calculated)	(#)
Live Positive Moment		(2+ lanes loaded)	1.498	(Calculated)	(#)
Live Positive Moment		(1 lane loaded)	0.931	(Calculated)	(#)
Live Shear		(2+ lanes loaded)	1.700	(Calculated)	(#)
Live Shear		(1 lane loaded)	1.056	(Calculated)	(#)

(#) Lever rule (C4.6.2.2.1)

Dead Loads and Pedestrian Load distributed based on Tributary Fraction

Pedestrian	0.127	(Calculated)
Comp. DC	0.127	(Calculated)
Comp. DW	0.127	(Calculated)

RESISTANCE FACTORS (Art. 5.5.4.2):

Flexure Reinforced	
Compression controlled sections	0.75
Tension controlled sections	0.90
Flexure Prestressed	
Compression controlled sections	0.75



Program: LEAP®
CONSPAN®
Version: 08.01.00.10

Copyright © Bentley Systems, Inc. 1984 - 2008.
www.bentley.com
1-800-778-4277

By: A. Pott
Date: Jan/4/2010
CKD:
Date:

File Name: 76-21-125-21-124 U72C.csl

Tension controlled sections	1.00
Shear	0.90

Span: 1, Beam: 2

SECTION PROPERTIES:

	PRECAST		COMPOSITE		
Area	1765.1	in2	4163.6	in2	#
Total Height	72.00	in	84.40	in	
Mom. of Inertia (Ixx)	1154250	in4	3135173	in4	#
Ht. of c.g.	35.84	in	61.13	in	#
Density	150.00	pcf	150.00	pcf	
Self-weight	1838.6	plf	4632.0	plf	
Mom. of Inertia (Iyy)	2057200.1	in4			
Poisson's Ratio	0.2				

(#) Of Total Section using $E_c/E_c = 0.8944$

Use transformed strand and rebar: Strand Only

Location,	ft	Bearing 0.00	Trans 2.25	H/2 3.52	0.10L 6.85	0.20L 14.45	0.30L 22.05	0.40L 29.65	Midspan 37.25
Precast:(At Release, using	Ec =	4980.8ksi)							
Area,	in2	1770.2	1785.6	1785.6	1785.6	1792.6	1795.8	1795.8	1795.8
Yb,	in	35.75	35.47	35.47	35.47	35.35	35.29	35.29	35.29
MI(Ixx),	in4	1159467	1174940	1174940	1174940	1182351	1185930	1185930	1185930
Composite:(At Final, using	Ec =	5751.4ksi)							
Area,	in2	4167.9	4180.8	4180.8	4180.8	4186.6	4189.3	4189.3	4189.3
Yb,	in	61.08	60.90	60.90	60.90	60.82	60.78	60.78	60.78
MI(Ixx),	in4	3149225	3191210	3191210	3191210	3210890	3220300	3220300	3220300

Span: 1, Beam: 2

STRESS LIMITS (Art. 5.9.4):

STRESS LIMITS AT RELEASE BEFORE LOSSES:

PRECAST



Program: LEAP®
CONSPAN®
Version: 08.01.00.10

Copyright © Bentley Systems, Inc. 1984 - 2008.
www.bentley.com
1-800-778-4277

By: A. Pott
Date: Jan/4/2010
CKD:
Date:

File Name: 76-21-125-21-124 U72C.csl

PRECAST			
Strength		6.75	ksi
Elasticity		4980.8	ksi
Max comp		4.05	ksi
Max tens		-0.20	ksi
Max tens,	w/reinf	-0.62	ksi

STRESS LIMITS AT FINAL AFTER LOSSES:

	PRECAST		DECK	
Strength	9.00	ksi	7.20	ksi
Elasticity	5751.38	ksi	5144.19	ksi

STRESS LIMITS AT FINAL 1 (P/S + DL + LL):

	PRECAST		DECK	
Max comp	5.40	ksi	4.32	ksi

STRESS LIMITS AT FINAL 2 (P/S + DL):

	PRECAST		DECK	
Max comp	4.05	ksi	3.24	ksi

STRESS LIMITS AT FINAL 3 (50% P/S + 50% DL + LL):

	PRECAST		DECK	
Max comp	3.60	ksi	2.88	ksi

SERVICE III (Tension):

	PRECAST		DECK	
Max tens	-0.57	ksi	-0.51	ksi

Span: 1, Beam: 2

PRESTRESSED STEEL:



Program: LEAP®
CONSPAN®
Version: 08.01.00.10

Copyright © Bentley Systems, Inc. 1984 - 2008.
www.bentley.com
1-800-778-4277

By: A. Pott
Date: Jan/4/2010
CKD:
Date:

File Name: 76-21-125-21-124_U72C.csl

30 strands, 6/10-270K-LL, Low relaxation strands
Depressed at 0.35L (26.60 ft from member end)

END PATTERN (Ycg = 3.46 in):

16 @ 2.250 in | 8 @ 4.060 in | 6 @ 5.880 in

SHIELDING AND REDUCED INITIAL PULLS:

Group	Strands	End	Heights	Mid	End	Shielding	Mid	Initial Frac	Pull Pull/Str
1	2	2.250	in	2.250	in	10.00	ft	0.00	ft 75.0 % 43.9
5	2	4.060	in	4.060	in	10.00	ft	0.00	ft 75.0 % 43.9
9	2	2.250	in	2.250	in	12.00	ft	0.00	ft 75.0 % 43.9
10	2	2.250	in	2.250	in	14.00	ft	0.00	ft 75.0 % 43.9
11	2	2.250	in	2.250	in	16.00	ft	0.00	ft 75.0 % 43.9

Check for Art. 5.11.4.3 (debond termination distances): OK

Strand Diameter	0.600	in
Strand Area	0.217	in ²
Total Strand Area	6.510	in ²
Trans. Len, bonded	3.000	ft
Trans. Len, debonded	3.000	ft
Dev. Len, bonded	11.563	ft
Dev. Len, debonded	14.454	ft
Holddown Force	0.000	kips
Tensile Strength(fpu)	270.0	ksi
Initial Prestress = 0.75fpu	202.5	ksi
Initial Pull	1318.3	kips
Beam Shrtng (PL/AE)	0.135	in

REINFORCING STEEL:

Tension steel:		
fy	60.0	ksi
Es	29000	ksi
fs	24.0	ksi

Stirrups:

# legs	Size	fy (ksi)	Area (in ²)	Spacing (in)	Start (ft)	End (ft)
4	US#3[M10]	60.0	0.44	3.33	0.2500	16.9167
4	US#3[M10]	60.0	0.44	5.00	16.9167	59.0833



Program: LEAP®
CONSPAN®
Version: 08.01.00.10

Copyright © Bentley Systems, Inc. 1984 - 2008.
www.bentley.com
1-800-778-4277

By: A. Pott
Date: Jan/4/2010
CKD:
Date:

File Name: 76-21-125-21-124 U72C.csl

# legs	Size	fy (ksi)	Area (in2)	Spacing (in)	Start (ft)	End (ft)
4	US#3[M10]	60.0	0.44	3.33	59.0833	75.7500

LOSSES

Note: Values are calculated at Midspan

Str. area	6.5100	in2
Ycg	3.46	in
P_init	1318.3	kips
Ecc	32.38	in
Days to release	0.75	
Rel. Humid.(RH)	60.0	%
Es	28500.0	ksi
Eci	4981	ksi

AASHTO LOSSES

Elastic Shortening ** 8.29 ksi (Eq 5.9.5.2.3a-1), (fcgp= 1.449 ksi)

	Elastic Gains	Gains	Adjustment
due to Precast Loads		-3.09 ksi	0.00 ksi
due to Composite Loads		-0.57 ksi	0.00 ksi
due to Live Loads		-1.64 ksi	0.00 ksi

Time Dependent Losses (Approximate Method (Art.5.9.5.3))

	Initial	Final
Steel relaxation	0.00 ksi	2.40 ksi (Eq 5.9.5.3-1)
Concrete shrinkage	0.00 ksi	8.52 ksi (Eq 5.9.5.3-1)
Concrete creep	0.00 ksi	5.30 ksi (Eq 5.9.5.3-1)
Sub-total	8.29 ksi	10.92 ksi (5.39 %)
Total Prestress Losses		19.21 ksi (9.48 %)

Prestressing Stress Limit Check (Table 5.9.3.1)

initial fpi = 202.5 ksi < 0.75 fpu, OK
initial fpe = 183.3 ksi < 0.80 fpy, OK

** Since the transformed section properties option has been selected, even though ES losses have been calculated explicitly here, they are not included as a part of stress calculations. Please see theory section for complete explanation.



Program: LEAP®
CONSPAN®
Version: 08.01.00.10

Copyright © Bentley Systems, Inc. 1984 - 2008.
www.bentley.com
1-800-778-4277

By: A. Pott
Date: Jan/4/2010
CKD:
Date:

File Name: 76-21-125-21-124 U72C.csl

DESIGN STATUS

Span:1, Beam:3

RELEASE STRESSES (ksi)

Limiting Stresses

Compression	Tens with Reinf	Tens without Reinf
4.050	-0.624	-0.200

Computed Stresses

	Trans	0.10L/0.90L	0.20L/0.80L	0.30L/0.70L	0.40L/0.60L	Midspan	Depress.
Location, ft	3.000	7.600	15.200	22.800	30.400	38.000	26.600
Precast-top	-0.296	-0.193	-0.186	-0.151	-0.091	-0.072	-0.116
Bottom	1.257	1.157	1.470	1.584	1.527	1.508	1.551
As_top, in2	3.372	0.000	0.000	0.000	0.000	0.000	0.000

FINAL STRESSES (ksi)

Limiting Stresses

		Precast	Topping-Top
Final 1 (P/S+DL+LL)	Compression	5.400	4.320
Final 1	Tension	-0.570	-0.510
Final 2 (P/S+DL)	Compression	4.050	3.240
Final 3 (0.5(P/S+DL)+LL)	Compression	3.600	2.880

Computed Stresses

POSITIVE MOMENT ENVELOPE : SERVICE I (Final 1)

	Bearing	Trans	H/2	0.10L/0.90L	0.20L/0.80L	0.30L/0.70L	0.40L/0.60L	Midspan
Location, ft	0.000	2.250	3.517	6.850	14.450	22.050	29.650	37.250
Topping-top	0.015	0.046	0.062	0.099	0.161	0.195	0.205	0.195
Precast-top	-0.079	-0.158	-0.065	0.163	0.468	0.708	0.882	0.932
Bottom	0.268	0.937	0.809	0.498	0.354	0.184	-0.008	-0.032

POSITIVE MOMENT ENVELOPE : SERVICE III (Final 1)

	Bearing	Trans	H/2	0.10L/0.90L	0.20L/0.80L	0.30L/0.70L	0.40L/0.60L	Midspan
Topping-top	0.013	0.038	0.052	0.083	0.135	0.164	0.173	0.164
Precast-top	-0.080	-0.162	-0.070	0.155	0.454	0.691	0.865	0.916
Bottom	0.275	0.959	0.838	0.544	0.428	0.272	0.084	0.055

NEGATIVE MOMENT ENVELOPE : SERVICE I (Final 1)

	Bearing	Trans	H/2	0.10L/0.90L	0.20L/0.80L	0.30L/0.70L	0.40L/0.60L	Midspan
Topping-top	-0.223	-0.183	-0.162	-0.111	-0.017	0.020	0.032	0.039
Precast-top	-0.204	-0.279	-0.183	0.052	0.374	0.615	0.790	0.850
Bottom	0.966	1.599	1.456	1.106	0.867	0.686	0.490	0.415



NEGATIVE MOMENT ENVELOPE : SERVICE III (Final 1)

	Bearing	Trans	H/2	0.10L/0.90L	0.20L/0.80L	0.30L/0.70L	0.40L/0.60L	Midspan
Topping-top	-0.186	-0.152	-0.134	-0.091	-0.012	0.021	0.033	0.040
Precast-top	-0.184	-0.263	-0.168	0.063	0.376	0.615	0.790	0.850
Bottom	0.856	1.509	1.376	1.049	0.852	0.683	0.487	0.413

POSITIVE MOMENT ENVELOPE : SERVICE I (Final 2)

	Bearing	Trans	H/2	0.10L/0.90L	0.20L/0.80L	0.30L/0.70L	0.40L/0.60L	Midspan
Topping-top	0.003	0.009	0.012	0.019	0.033	0.041	0.044	0.043
Precast-top	-0.085	-0.178	-0.091	0.121	0.400	0.626	0.796	0.851
Bottom	0.303	1.044	0.952	0.728	0.724	0.626	0.455	0.405

NEGATIVE MOMENT ENVELOPE : SERVICE I (Final 2)

	Bearing	Trans	H/2	0.10L/0.90L	0.20L/0.80L	0.30L/0.70L	0.40L/0.60L	Midspan
Topping-top	-0.036	-0.028	-0.023	-0.012	0.009	0.025	0.036	0.043
Precast-top	-0.106	-0.197	-0.110	0.104	0.387	0.618	0.792	0.851
Bottom	0.418	1.150	1.054	0.821	0.793	0.672	0.478	0.405

POSITIVE MOMENT ENVELOPE : SERVICE I (Final 3)

	Bearing	Trans	H/2	0.10L/0.90L	0.20L/0.80L	0.30L/0.70L	0.40L/0.60L	Midspan
Topping-top	0.014	0.041	0.055	0.089	0.145	0.174	0.183	0.173
Precast-top	-0.036	-0.070	-0.020	0.103	0.268	0.395	0.484	0.507
Bottom	0.116	0.416	0.333	0.134	-0.008	-0.130	-0.236	-0.235

NEGATIVE MOMENT ENVELOPE : SERVICE I (Final 3)

	Bearing	Trans	H/2	0.10L/0.90L	0.20L/0.80L	0.30L/0.70L	0.40L/0.60L	Midspan
Topping-top	-0.205	-0.169	-0.150	-0.105	-0.021	0.008	0.014	0.018
Precast-top	-0.151	-0.180	-0.128	0.000	0.180	0.306	0.394	0.424
Bottom	0.757	1.024	0.929	0.696	0.471	0.350	0.251	0.213

ULTIMATE MOMENT (k.ft)

STRENGTH I

Location, ft	Trans	H/2	0.10L/0.90L	0.20L/0.80L	0.30L/0.70L	0.40L/0.60L	Midspan	Depress
	2.250	3.517	6.850	14.450	22.050	29.650	37.250	25.850
Mu-req'd	1509.1	2133.7	3635.3	6288.4	7956.1	8741.2	8706.0	8348.7
Mu-prv'd	5423.6	5776.8	6705.1	9736.4	11290.0	11729.1	11730.2	11509.6

CAMBER / DEFLECTION (in) at Midspan (0.5 x L = 37.25 ft)

SERVICE I

	Release	Mult	Erection	Mult	Final
Prestress	0.701	1.80	1.263	2.20	1.543
Self Wt.	-0.234	1.85	-0.432	2.40	-0.561
Deck + Haunch			-0.284	2.30	-0.653
DL-Prec. (DC)			-0.061	3.00	-0.183



Program: LEAP®
CONSPAN®
Version: 08.01.00.10

Copyright © Bentley Systems, Inc. 1984 - 2008.
www.bentley.com
1-800-778-4277

By: A. Pott
Date: Jan/4/2010
CKD:
Date:

File Name: 76-21-125-21-124_U72C.csl

	Release	Mult	Erection	Mult	Final
Diaphragm			0.000	3.00	0.000
DL-Prec. (DW)			0.000	3.00	0.000
DL-Comp. (DC)			-0.004	3.00	-0.013
DL-Comp. (DW)			-0.021	3.00	-0.062
Total	0.468		0.460		0.071

Positive values indicate upward deflection.



Program: LEAP®
CONSPAN®
Version: 08.01.00.10

Copyright © Bentley Systems, Inc. 1984 - 2008.
www.bentley.com
1-800-778-4277

By: A. Pott
Date: Jan/4/2010
CKD:
Date:

File Name: 76-21-125-21-124 U72C.csl

PROPERTIES

Span: 1, Beam: 3

PRECAST DATA:

Section Id	U72C					
Type	Open Box Beam					
Fling width	Top	131.000	in	Bot	54.000	in
thick	Top	6.350	in	Bot	8.100	in
Stems	No	2				
	Top	7.500	in			
	Bot	7.500	in			
Shear width		15.000	in			

GENERAL BRIDGE DATA:

Bridge Width	197.00	ft
Curb-to-curb	194.00	ft
Beam Spac. Lt./Rt	25.00/ 25.00	ft
Lane width	12.00	ft
Number of lanes	16	
Interior/Exterior	Interior	
Start Skew Angle	-34.00	degrees
End Skew Angle	-34.00	degrees

TOPPING DATA:

Deck	Thickness	8.000	in
Haunch:			
	Thickness	4.400	in
	Width	64.000	in
Effective	width	300.000	in (Art. 4.6.2.6.1)

GENERAL LOAD DATA:

Dead loads on precast:
UNITS: (Point: kips, Location: ft)
(Line: klf)

DC/DW	Type	Mag.	Loc.
DC	Line	0.600	-



Program: LEAP®
CONSPAN®
Version: 08.01.00.10

Copyright © Bentley Systems, Inc. 1984 - 2008.
www.bentley.com
1-800-778-4277

By: A. Pott
Date: Jan/4/2010
CKD:
Date:

File Name: 76-21-125-21-124_U72C.csl

Dead loads on composite: See Project info for composite loads

GENERAL SPAN DATA:

Overall length	76.000	ft
Release length	76.000	ft
Design length	74.500	ft

KERN POINTS:

Upper	54.09	in
Lower	17.76	in

DISTRIBUTION FACTORS (Art. 4.6.2.2):

Live Negative Moment	Left Side	(2+ lanes loaded)	1.498	(Calculated)	(#)
Live Negative Moment	Right Side	(2+ lanes loaded)	1.498	(Calculated)	(#)
Live Negative Moment	Left Side	(1 lane loaded)	0.931	(Calculated)	(#)
Live Negative Moment	Right Side	(1 lane loaded)	0.931	(Calculated)	(#)
Live Positive Moment		(2+ lanes loaded)	1.498	(Calculated)	(#)
Live Positive Moment		(1 lane loaded)	0.931	(Calculated)	(#)
Live Shear		(2+ lanes loaded)	1.700	(Calculated)	(#)
Live Shear		(1 lane loaded)	1.056	(Calculated)	(#)

(#) Lever rule (C4.6.2.2.1)

Dead Loads and Pedestrian Load distributed based on Tributary Fraction

Pedestrian	0.127	(Calculated)
Comp. DC	0.127	(Calculated)
Comp. DW	0.127	(Calculated)

RESISTANCE FACTORS (Art. 5.5.4.2):

Flexure Reinforced	
Compression controlled sections	0.75
Tension controlled sections	0.90
Flexure Prestressed	
Compression controlled sections	0.75

247



Program: LEAP®
CONSPAN®
Version: 08.01.00.10

Copyright © Bentley Systems, Inc. 1984 - 2008.
www.bentley.com
1-800-778-4277

By: A. Pott
Date: Jan/4/2010
CKD:
Date:

File Name: 76-21-125-21-124 U72C.csl

Tension controlled sections	1.00
Shear	0.90

Span: 1, Beam: 3

SECTION PROPERTIES:

	PRECAST		COMPOSITE		
Area	1765.1	in2	4163.6	in2	#
Total Height	72.00	in	84.40	in	
Mom. of Inertia (Ixx)	1154250	in4	3135173	in4	#
Ht. of c.g.	35.84	in	61.13	in	#
Density	150.00	pcf	150.00	pcf	
Self-weight	1838.6	plf	4632.0	plf	
Mom. of Inertia (Iyy)	2057200.1	in4			
Poisson's Ratio	0.2				

(#) Of Total Section using $E_c/E_c = 0.8944$

Use transformed strand and rebar: Strand Only

Location,	ft	Bearing	Trans	H/2	0.10L	0.20L	0.30L	0.40L	Midspan
		0.00	2.25	3.52	6.85	14.45	22.05	29.65	37.25
Precast:(At Release, using	Ec =	4980.8ksi)							
Area,	in2	1770.2	1785.6	1785.6	1785.6	1792.6	1795.8	1795.8	1795.8
Yb,	in	35.75	35.47	35.47	35.47	35.35	35.29	35.29	35.29
MI(Ixx),	in4	1159467	1174940	1174940	1174940	1182351	1185930	1185930	1185930
Composite:(At Final, using	Ec =	5751.4ksi)							
Area,	in2	4167.9	4180.8	4180.8	4180.8	4186.6	4189.3	4189.3	4189.3
Yb,	in	61.08	60.90	60.90	60.90	60.82	60.78	60.78	60.78
MI(Ixx),	in4	3149225	3191210	3191210	3191210	3210890	3220300	3220300	3220300

Span: 1, Beam: 3

STRESS LIMITS (Art. 5.9.4):

STRESS LIMITS AT RELEASE BEFORE LOSSES:

PRECAST



Program: LEAP®
CONSPAN®
Version: 08.01.00.10

Copyright © Bentley Systems, Inc. 1984 - 2008.
www.bentley.com
1-800-778-4277

By: A. Pott
Date: Jan/4/2010
CKD:
Date:

File Name: 76-21-125-21-124 U72C.csl

PRECAST			
Strength		6.75	ksi
Elasticity		4980.8	ksi
Max comp		4.05	ksi
Max tens		-0.20	ksi
Max tens	w/reinf	-0.62	ksi

STRESS LIMITS AT FINAL AFTER LOSSES:

	PRECAST		DECK	
Strength	9.00	ksi	7.20	ksi
Elasticity	5751.38	ksi	5144.19	ksi

STRESS LIMITS AT FINAL 1 (P/S + DL + LL):

	PRECAST		DECK	
Max comp	5.40	ksi	4.32	ksi

STRESS LIMITS AT FINAL 2 (P/S + DL):

	PRECAST		DECK	
Max comp	4.05	ksi	3.24	ksi

STRESS LIMITS AT FINAL 3 (50% P/S + 50% DL + LL):

	PRECAST		DECK	
Max comp	3.60	ksi	2.88	ksi

SERVICE III (Tension):

	PRECAST		DECK	
Max tens	-0.57	ksi	-0.51	ksi

Span: 1, Beam: 3

PRESTRESSED STEEL:



Program: LEAP®
CONSPAN®
Version: 08.01.00.10

Copyright © Bentley Systems, Inc. 1984 - 2008.
www.bentley.com
1-800-778-4277

By: A. Pott
Date: Jan/4/2010
CKD:
Date:

File Name: 76-21-125-21-124_U72C.csl

30 strands, 6/10-270K-LL, Low relaxation strands
Depressed at 0.35L (26.60 ft from member end)

END PATTERN (Ycg = 3.46 in):

16 @ 2.250 in | 8 @ 4.060 in | 6 @ 5.880 in

SHIELDING AND REDUCED INITIAL PULLS:

Group	Strands	End	Heights	Mid	End	Shielding	Mid	Initial Frac	Pull Pull/Str
1	2	2.250	in	2.250	in	10.00	ft	0.00	ft 75.0 % 43.9
5	2	4.060	in	4.060	in	10.00	ft	0.00	ft 75.0 % 43.9
9	2	2.250	in	2.250	in	12.00	ft	0.00	ft 75.0 % 43.9
10	2	2.250	in	2.250	in	14.00	ft	0.00	ft 75.0 % 43.9
11	2	2.250	in	2.250	in	16.00	ft	0.00	ft 75.0 % 43.9

Check for Art. 5.11.4.3 (debond termination distances): OK

Strand Diameter	0.600	in
Strand Area	0.217	in ²
Total Strand Area	6.510	in ²
Trans. Len, bonded	3.000	ft
Trans. Len, debonded	3.000	ft
Dev. Len, bonded	11.563	ft
Dev. Len, debonded	14.454	ft
Holddown Force	0.000	kips
Tensile Strength(fpu)	270.0	ksi
Initial Prestress = 0.75fpu	202.5	ksi
Initial Pull	1318.3	kips
Beam Shrtng (PL/AE)	0.135	in

REINFORCING STEEL:

Tension	steel:	
fy	60.0	ksi
Es	29000	ksi
fs	24.0	ksi

Stirrups:

# legs	Size	fy (ksi)	Area (in ²)	Spacing (in)	Start (ft)	End (ft)
4	US#3[M10]	60.0	0.44	3.33	0.2500	16.9167
4	US#3[M10]	60.0	0.44	5.00	16.9167	59.0833



Program: LEAP®
CONSPAN®
Version: 08.01.00.10

Copyright © Bentley Systems, Inc. 1984 - 2008.
www.bentley.com
1-800-778-4277

By: A. Pott
Date: Jan/4/2010
CKD:
Date:

File Name: 76-21-125-21-124 U72C.csl

# legs	Size	fy (ksi)	Area (in2)	Spacing (in)	Start (ft)	End (ft)
4	US#3[M10]	60.0	0.44	3.33	59.0833	75.7500

LOSSES

Note: Values are calculated at Midspan

Str. area	6.5100	in2
Ycg	3.46	in
P_init	1318.3	kips
Ecc	32.38	in
Days to release	0.75	
Rel. Humid.(RH)	60.0	%
Es	28500.0	ksi
Eci	4981	ksi

AASHTO LOSSES

Elastic Shortening ** 8.29 ksi (Eq 5.9.5.2.3a-1), (fcgp= 1.449 ksi)

Elastic Gains		Gains	Adjustment
due to Precast Loads		-3.76 ksi	0.00 ksi
due to Composite Loads		-0.57 ksi	0.00 ksi
due to Live Loads		-1.64 ksi	0.00 ksi

Time Dependent Losses (Approximate Method (Art.5.9.5.3))

	Initial	Final
Steel relaxation	0.00 ksi	2.40 ksi (Eq 5.9.5.3-1)
Concrete shrinkage	0.00 ksi	8.52 ksi (Eq 5.9.5.3-1)
Concrete creep	0.00 ksi	5.30 ksi (Eq 5.9.5.3-1)
Sub-total	8.29 ksi	10.25 ksi (5.06 %)
Total Prestress Losses		18.54 ksi (9.16 %)

Prestressing Stress Limit Check (Table 5.9.3.1)

initial fpi = 202.5 ksi < 0.75 fpu, OK
initial fpe = 184.0 ksi < 0.80 fpy, OK

** Since the transformed section properties option has been selected, even though ES losses have been calculated explicitly here, they are not included as a part of stress calculations. Please see theory section for complete explanation.

COLORADO DEPARTMENT OF TRANSPORTATION
DESIGN COMPUTATIONS (Grid)

SPAN 3

GIRDER 3

extra load $\approx .6$ k/ft

camber @ erection $\approx 2.9''$

86 strands w/ debonding

GIRDER 2

less load $\approx .5$ k/ft

camber @ erection $\approx 2.52''$ $2.52''$

increased camber (deck) $\approx .39''$

2.91''

76 strands w/ debonding

GIRDER 1

camber @ erection $\approx 2.64''$

76 strands w/ debonding (same as girder 2)

GIRDER 4

~~extra load $\approx .1$ k/ft~~

~~camber @ erection $\approx 2.91''$~~

~~81 strands w/ debonding~~

Same as girder 2



Program: LEAP®
CONSPAN®
Version: 08.01.00.10

Copyright © Bentley Systems, Inc. 1984 - 2008.
www.bentley.com
1-800-778-4277

By: A. Pott
Date: Jan/4/2010
CKD:
Date:

File Name: 76-21-125-21-124_U72C.csl

DESIGN STATUS

Span:3, Beam:1

RELEASE STRESSES (ksi)

Limiting Stresses

Compression	Tens with Reinf	Tens without Reinf
4.050	-0.624	-0.200

Computed Stresses

	Trans	0.10L/0.90L	0.20L/0.80L	0.30L/0.70L	0.40L/0.60L	Midspan	Depress.
Location, ft	3.000	12.700	25.400	38.100	50.800	63.500	44.450
Precast-top	-0.195	-0.067	0.041	0.041	0.068	0.123	0.002
Bottom	3.617	3.573	3.460	3.449	3.418	3.368	3.477
As_top, in2	0.000	0.000	0.000	0.000	0.000	0.000	0.000

FINAL STRESSES (ksi)

Limiting Stresses

	Compression	Precast	Topping-Top
Final 1 (P/S+DL+LL)	5.400	4.320	
Final 1	Tension	-0.570	-0.510
Final 2 (P/S+DL)	4.050	3.240	
Final 3 (0.5(P/S+DL)+LL)	3.600	2.880	

Computed Stresses

POSITIVE MOMENT ENVELOPE : SERVICE I (Final 1)

	Bearing	Trans	H/2	0.10L/0.90L	0.20L/0.80L	0.30L/0.70L	0.40L/0.60L	Midspan
Location, ft	0.000	2.000	3.517	11.700	24.400	37.100	49.800	62.500
Topping-top	-0.051	-0.043	-0.036	0.006	0.106	0.221	0.298	0.321
Precast-top	-0.113	-0.101	0.025	0.614	1.360	1.840	2.155	2.301
Bottom	1.279	3.210	3.075	2.499	1.580	0.884	0.428	0.244

POSITIVE MOMENT ENVELOPE : SERVICE III (Final 1)

	Bearing	Trans	H/2	0.10L/0.90L	0.20L/0.80L	0.30L/0.70L	0.40L/0.60L	Midspan
Topping-top	-0.058	-0.049	-0.042	-0.001	0.088	0.186	0.251	0.271
Precast-top	-0.117	-0.105	0.021	0.610	1.350	1.821	2.129	2.273
Bottom	1.298	3.227	3.092	2.520	1.630	0.979	0.554	0.380

NEGATIVE MOMENT ENVELOPE : SERVICE I (Final 1)

	Bearing	Trans	H/2	0.10L/0.90L	0.20L/0.80L	0.30L/0.70L	0.40L/0.60L	Midspan
Topping-top	-0.466	-0.416	-0.383	-0.221	-0.031	0.037	0.059	0.067
Precast-top	-0.339	-0.308	-0.167	0.488	1.284	1.738	2.022	2.159
Bottom	2.437	4.225	4.017	3.114	1.951	1.380	1.072	0.927



Program: LEAP®
CONSPAN®
Version: 08.01.00.10

Copyright © Bentley Systems, Inc. 1984 - 2008.
www.bentley.com
1-800-778-4277

By: A. Pott
Date: Jan/4/2010
CKD:
Date:

File Name: 76-21-125-21-124 U72C.csl

NEGATIVE MOMENT ENVELOPE : SERVICE III (Final 1)

	Bearing	Trans	H/2	0.10L/0.90L	0.20L/0.80L	0.30L/0.70L	0.40L/0.60L	Midspan
Topping-top	-0.392	-0.350	-0.322	-0.185	-0.023	0.038	0.059	0.068
Precast-top	-0.299	-0.272	-0.134	0.508	1.288	1.738	2.022	2.159
Bottom	2.232	4.046	3.852	3.016	1.931	1.378	1.071	0.926

POSITIVE MOMENT ENVELOPE : SERVICE I (Final 2)

	Bearing	Trans	H/2	0.10L/0.90L	0.20L/0.80L	0.30L/0.70L	0.40L/0.60L	Midspan
Topping-top	-0.086	-0.074	-0.067	-0.032	0.014	0.045	0.064	0.069
Precast-top	-0.132	-0.119	0.008	0.593	1.308	1.742	2.025	2.160
Bottom	1.375	3.295	3.158	2.602	1.830	1.358	1.058	0.922

NEGATIVE MOMENT ENVELOPE : SERVICE I (Final 2)

	Bearing	Trans	H/2	0.10L/0.90L	0.20L/0.80L	0.30L/0.70L	0.40L/0.60L	Midspan
Topping-top	-0.098	-0.087	-0.079	-0.041	0.007	0.041	0.062	0.069
Precast-top	-0.139	-0.125	0.001	0.588	1.305	1.740	2.023	2.160
Bottom	1.408	3.329	3.191	2.627	1.849	1.371	1.065	0.922

POSITIVE MOMENT ENVELOPE : SERVICE I (Final 3)

	Bearing	Trans	H/2	0.10L/0.90L	0.20L/0.80L	0.30L/0.70L	0.40L/0.60L	Midspan
Topping-top	-0.009	-0.006	-0.003	0.022	0.099	0.199	0.266	0.286
Precast-top	-0.047	-0.042	0.021	0.317	0.706	0.969	1.143	1.221
Bottom	0.592	1.562	1.496	1.199	0.665	0.205	-0.101	-0.217

NEGATIVE MOMENT ENVELOPE : SERVICE I (Final 3)

	Bearing	Trans	H/2	0.10L/0.90L	0.20L/0.80L	0.30L/0.70L	0.40L/0.60L	Midspan
Topping-top	-0.417	-0.373	-0.343	-0.200	-0.034	0.017	0.028	0.033
Precast-top	-0.269	-0.246	-0.168	0.194	0.631	0.868	1.010	1.079
Bottom	1.733	2.561	2.422	1.800	1.027	0.695	0.540	0.466

ULTIMATE MOMENT (k.ft)

STRENGTH I

	Trans	H/2	0.10L/0.90L	0.20L/0.80L	0.30L/0.70L	0.40L/0.60L	Midspan	Depress
Location, ft	2.000	3.517	11.700	24.400	37.100	49.800	62.500	43.450
Mu-req'd	732.7	1283.2	4253.5	9110.1	13745.7	16707.0	17635.8	15226.4
Mu-prv'd	16555.3	18027.6	25812.9	27130.8	28209.1	28748.3	28748.3	28478.7

Note: Check minimum reinforcement criteria (LRFD Art. 5.7.3.3.2) in Ultimate Moment detailed report.

CAMBER / DEFLECTION (in) at Midspan (0.5 x L = 62.50 ft)

SERVICE I

	Release	Mult	Erection	Mult	Final
Prestress	4.466	1.80	8.039	2.20	9.826
Self Wt.	-1.761	1.85	-3.258	2.40	-4.227



Program: LEAP®
CONSPAN®
Version: 08.01.00.10

Copyright © Bentley Systems, Inc. 1984 - 2008.
www.bentley.com
1-800-778-4277

By: A. Pott
Date: Jan/4/2010
CKD:
Date:

File Name: 76-21-125-21-124_U72C.csl

	Release	Mult	Erection	Mult	Final
Deck + Haunch			-2.058	2.30	-4.733
DL-Prec. (DC)			0.000	3.00	0.000
Diaphragm			0.000	3.00	0.000
DL-Prec. (DW)			0.000	3.00	0.000
DL-Comp. (DC)			-0.014	3.00	-0.042
DL-Comp. (DW)			-0.067	3.00	-0.201
Total	2.705		2.642		0.623

Positive values indicate upward deflection.



Program: LEAP®
CONSPAN®
Version: 08.01.00.10

Copyright © Bentley Systems, Inc. 1984 - 2008.
www.bentley.com
1-800-778-4277

By: A. Pott
Date: Jan/4/2010
CKD:
Date:

File Name: 76-21-125-21-124 U72C.csl

PROPERTIES

Span: 3, Beam: 1

PRECAST DATA:

Section Id	U72C					
Type	Open Box Beam					
Fling width	Top	131.000	in	Bot	54.000	in
thick	Top	6.350	in	Bot	8.100	in
Stems	No	2				
	Top	7.500	in			
	Bot	7.500	in			
Shear width		15.000	in			

GENERAL BRIDGE DATA:

Bridge Width	197.00	ft
Curb-to-curb	194.00	ft
Beam Spac. Lt./Rt	11.00/ 25.00	ft
Lane width	12.00	ft
Number of lanes	16	
Interior/Exterior	Exterior	
Start Skew Angle	-34.00	degrees
End Skew Angle	-34.00	degrees

TOPPING DATA:

Deck	Thickness	8.000	in
Haunch:	Thickness	4.400	in
	Width	64.000	in
Effective	width	282.000	in (Art. 4.6.2.6.1)

GENERAL LOAD DATA:

Dead loads on composite: See Project info for composite loads

GENERAL SPAN DATA:

Overall length	127.000	ft
----------------	---------	----



Program: LEAP®
CONSPAN®
Version: 08.01.00.10

Copyright © Bentley Systems, Inc. 1984 - 2008.
www.bentley.com
1-800-778-4277

By: A. Pott
Date: Jan/4/2010
CKD:
Date:

File Name: 76-21-125-21-124_U72C.csl

Release length	127.000	ft
Design length	125.000	ft

KERN POINTS:

Upper	54.09	in
Lower	17.76	in

DISTRIBUTION FACTORS (Art. 4.6.2.2):

Live Negative Moment	Left Side	(2+ lanes loaded)	1.657	(Calculated)	(#)
Live Negative Moment	Right Side	(2+ lanes loaded)	1.657	(Calculated)	(#)
Live Negative Moment	Left Side	(1 lane loaded)	1.248	(Calculated)	(#)
Live Negative Moment	Right Side	(1 lane loaded)	1.248	(Calculated)	(#)
Live Positive Moment		(2+ lanes loaded)	1.657	(Calculated)	(#)
Live Positive Moment		(1 lane loaded)	1.248	(Calculated)	(#)
Live Shear		(2+ lanes loaded)	1.880	(Calculated)	(#)
Live Shear		(1 lane loaded)	1.416	(Calculated)	(#)

(#) Lever rule (C4.6.2.2.1)

Dead Loads and Pedestrian Load distributed based on Tributary Fraction

Pedestrian	0.119	(Calculated)
Comp. DC	0.119	(Calculated)
Comp. DW	0.119	(Calculated)

RESISTANCE FACTORS (Art. 5.5.4.2):

Flexure Reinforced	
Compression controlled sections	0.75
Tension controlled sections	0.90
Flexure Prestressed	
Compression controlled sections	0.75
Tension controlled sections	1.00
Shear	0.90



Program: LEAP®
CONSPAN®
Version: 08.01.00.10

Copyright © Bentley Systems, Inc. 1984 - 2008.
www.bentley.com
1-800-778-4277

By: A. Pott
Date: Jan/4/2010
CKD:
Date:

File Name: 76-21-125-21-124_U72C.csl

Span: 3, Beam: 1

SECTION PROPERTIES:

	PRECAST		COMPOSITE		
Area	1765.1	in2	4034.8	in2	#
Total Height	72.00	in	84.40	in	
Mom. of Inertia (Ixx)	1154250	in4	3085155	in4	#
Ht. of c.g.	35.84	in	60.52	in	#
Density	150.00	pcf	150.00	pcf	
Self-weight	1838.6	plf	4482.0	plf	
Mom. of Inertia (Iyy)	2057200.1	in4			
Poisson's Ratio	0.2				

(#) Of Total Section using Ect/Ec = 0.8944

Use transformed strand and rebar: Strand Only

Location,	ft	Bearing	Trans	H/2	0.10L	0.20L	0.30L	0.40L	Midspan
Precast:(At Release, using	Ec =	4980.8ksi)							
Area,	in2	1790.4	1840.9	1840.9	1843.0	1843.0	1843.0	1843.0	1843.0
Yb,	in	35.54	34.96	34.94	34.83	34.71	34.58	34.52	34.52
MI(Ixx),	in4	1165252	1187803	1188926	1196949	1207958	1220229	1226837	1226837
Composite:(At Final, using	Ec =	5751.4ksi)							
Area,	in2	4056.0	4098.3	4098.3	4100.0	4100.0	4100.0	4100.0	4100.0
Yb,	in	60.28	59.80	59.80	59.75	59.70	59.65	59.63	59.63
MI(Ixx),	in4	3129125	3218404	3220471	3236816	3255506	3275281	3285575	3285575

Span: 3, Beam: 1

STRESS LIMITS (Art. 5.9.4):

STRESS LIMITS AT RELEASE BEFORE LOSSES:

	PRECAST	
Strength	6.75	ksi
Elasticity	4980.8	ksi
Max comp	4.05	ksi
Max tens	-0.20	ksi
Max tens, w/reinf	-0.62	ksi



Program: LEAP®
CONSPAN®
Version: 08.01.00.10

Copyright © Bentley Systems, Inc. 1984 - 2008.
www.bentley.com
1-800-778-4277

By: A. Pott
Date: Jan/4/2010
CKD:
Date:

File Name: 76-21-125-21-124_U72C.csl

STRESS LIMITS AT FINAL AFTER LOSSES:

	PRECAST	DECK
Strength	9.00 ksi	7.20 ksi
Elasticity	5751.38 ksi	5144.19 ksi

STRESS LIMITS AT FINAL 1 (P/S + DL + LL):

	PRECAST	DECK
Max comp	5.40 ksi	4.32 ksi

STRESS LIMITS AT FINAL 2 (P/S + DL):

	PRECAST	DECK
Max comp	4.05 ksi	3.24 ksi

STRESS LIMITS AT FINAL 3 (50% P/S + 50% DL + LL):

	PRECAST	DECK
Max comp	3.60 ksi	2.88 ksi

SERVICE III (Tension):

	PRECAST	DECK
Max tens	-0.57 ksi	-0.51 ksi

Span: 3, Beam: 1

PRESTRESSED STEEL:

76 strands, 6/10-270K-LL, Low relaxation strands
Depressed at 0.35L (44.45 ft from member end)

END PATTERN (Ycg = 14.82 in):

259



Program: LEAP®
CONSPAN®
Version: 08.01.00.10

Copyright © Bentley Systems, Inc. 1984 - 2008.
www.bentley.com
1-800-778-4277

By: A. Pott
Date: Jan/4/2010
CKD:
Date:

File Name: 76-21-125-21-124 U72C.csl

15 @ 5.880 in	23 @ 2.250 in	2 @ 57.500 in	24 @ 4.060 in
2 @ 59.500 in	2 @ 61.500 in	2 @ 63.500 in	2 @ 65.500 in
2 @ 67.500 in	2 @ 69.500 in		

MID PATTERN (Ycg = 4.64 in):
(A) Draped:

2 @ 2.250 in	2 @ 4.250 in	2 @ 6.250 in	2 @ 8.250 in
2 @ 10.250 in	2 @ 12.250 in	2 @ 14.250 in	

(B) Straight:

15 @ 5.880 in	23 @ 2.250 in	24 @ 4.060 in
---------------	---------------	---------------

SHIELDING AND REDUCED INITIAL PULLS:

Group	Strands	End	Heights	Mid	End	Shielding	Mid	Initial Frac	Pull Pull/Str
1	2	5.880	in	5.880	in	8.00	ft	75.0 %	43.9

Check for Art. 5.11.4.3 (debond termination distances): OK

Strand Diameter	0.600	in
Strand Area	0.217	in ²
Total Strand Area	16.492	in ²
Trans. Len, bonded	3.000	ft
Trans. Len, debonded	3.000	ft
Dev. Len, bonded	11.822	ft
Dev. Len, debonded	14.778	ft
Holddown Force	63.383	kips
Tensile Strength(fpu)	270.0	ksi
Initial Prestress = 0.75fpu	202.5	ksi
Initial Pull	3339.6	kips
Beam Shrtng (PL/AE)	0.555	in

REINFORCING STEEL:

Tension steel:		
fy	60.0	ksi
Es	29000	ksi
fs	24.0	ksi

Stirrups:

# legs	Size	fy (ksi)	Area (in ²)	Spacing (in)	Start (ft)	End (ft)
4	US#3[M10]	60.0	0.44	3.33	0.2500	16.9167



Program: LEAP®
CONSPAN®
Version: 08.01.00.10

Copyright © Bentley Systems, Inc. 1984 - 2008.
www.bentley.com
1-800-778-4277

By: A. Pott
Date: Jan/4/2010
CKD:
Date:

File Name: 76-21-125-21-124_U72C.csl

# legs	Size	fy (ksi)	Area (in2)	Spacing (in)	Start (ft)	End (ft)
4	US#3[M10]	60.0	0.44	5.00	16.9167	110.0833
4	US#3[M10]	60.0	0.44	3.33	110.0833	126.7500

LOSSES

Note: Values are calculated at Midspan

Str. area	16.4920	in2
Ycg	4.64	in
P_init	3339.6	kips
Ecc	31.20	in
Days to release	0.75	
Rel. Humid.(RH)	60.0	%
Es	28500.0	ksi
Eci	4981	ksi

AASHTO LOSSES

Elastic Shortening ** 18.26 ksi (Eq 5.9.5.2.3a-1), (fcgp= 3.191 ksi)

	Elastic Gains	Gains	Adjustment
due to Precast Loads		-7.48 ksi	0.00 ksi
due to Composite Loads		-0.85 ksi	0.00 ksi
due to Live Loads		-2.48 ksi	0.00 ksi

Time Dependent Losses (Approximate Method (Art.5.9.5.3))

	Initial	Final	
Steel relaxation	0.00 ksi	2.40 ksi	(Eq 5.9.5.3-1)
Concrete shrinkage	0.00 ksi	8.52 ksi	(Eq 5.9.5.3-1)
Concrete creep	0.00 ksi	13.43 ksi	(Eq 5.9.5.3-1)
Sub-total	18.26 ksi	13.54 ksi	(6.68 %)
Total Prestress Losses		31.80 ksi	(15.70 %)

Prestressing Stress Limit Check (Table 5.9.3.1)

initial fpi = 202.5 ksi < 0.75 fpu, OK

initial fpe = 170.7 ksi < 0.80 fpy, OK

** Since the transformed section properties option has been selected, even though ES losses have been calculated explicitly here, they are not included as a part of stress calculations. Please see theory section for complete explanation.



Program: LEAP®
CONSPAN®
Version: 08.01.00.10
File Name: 76-21-125-21-124 U72C.csl

Copyright © Bentley Systems, Inc. 1984 - 2008.
www.bentley.com
1-800-778-4277

By: A. Pott
Date: Jan/4/2010
CKD:
Date:

DESIGN STATUS

Span:3, Beam:2

RELEASE STRESSES (ksi)

Limiting Stresses

Compression	Tens with Reinf	Tens without Reinf
4.050	-0.624	-0.200

Computed Stresses

	Trans	0.10L/0.90L	0.20L/0.80L	0.30L/0.70L	0.40L/0.60L	Midspan	Depress.
Location, ft	3.000	12.700	25.400	38.100	50.800	63.500	44.450
Precast-top	-0.195	-0.067	0.041	0.041	0.068	0.123	0.002
Bottom	3.617	3.573	3.460	3.449	3.418	3.368	3.477
As top, in2	0.000	0.000	0.000	0.000	0.000	0.000	0.000

FINAL STRESSES (ksi)

Limiting Stresses

		Precast	Topping-Top
Final 1 (P/S+DL+LL)	Compression	5.400	4.320
Final 1	Tension	-0.570	-0.510
Final 2 (P/S+DL)	Compression	4.050	3.240
Final 3 (0.5(P/S+DL)+LL)	Compression	3.600	2.880

Computed Stresses

POSITIVE MOMENT ENVELOPE : SERVICE I (Final 1)

	Bearing	Trans	H/2	0.10L/0.90L	0.20L/0.80L	0.30L/0.70L	0.40L/0.60L	Midspan
Location, ft	0.000	2.000	3.517	11.700	24.400	37.100	49.800	62.500
Topping-top	-0.058	-0.048	-0.041	0.001	0.094	0.199	0.268	0.289
Precast-top	-0.116	-0.097	0.034	0.648	1.420	1.915	2.238	2.386
Bottom	1.302	3.223	3.082	2.480	1.540	0.842	0.387	0.203

POSITIVE MOMENT ENVELOPE : SERVICE III (Final 1)

	Bearing	Trans	H/2	0.10L/0.90L	0.20L/0.80L	0.30L/0.70L	0.40L/0.60L	Midspan
Topping-top	-0.064	-0.054	-0.047	-0.006	0.078	0.168	0.228	0.245
Precast-top	-0.119	-0.100	0.032	0.644	1.411	1.898	2.216	2.362
Bottom	1.320	3.239	3.097	2.498	1.585	0.927	0.500	0.325

NEGATIVE MOMENT ENVELOPE : SERVICE I (Final 1)

	Bearing	Trans	H/2	0.10L/0.90L	0.20L/0.80L	0.30L/0.70L	0.40L/0.60L	Midspan
Topping-top	-0.419	-0.374	-0.344	-0.197	-0.026	0.039	0.061	0.069
Precast-top	-0.307	-0.272	-0.129	0.541	1.355	1.828	2.125	2.266
Bottom	2.349	4.142	3.935	3.036	1.876	1.290	0.967	0.817



Program: LEAP®
CONSPAN®
Version: 08.01.00.10

Copyright © Bentley Systems, Inc. 1984 - 2008.
www.bentley.com
1-800-778-4277

By: A. Pott
Date: Jan/4/2010
CKD:
Date:

File Name: 76-21-125-21-124_U72C.csl

NEGATIVE MOMENT ENVELOPE : SERVICE III (Final 1)

	Bearing	Trans	H/2	0.10L/0.90L	0.20L/0.80L	0.30L/0.70L	0.40L/0.60L	Midspan
Topping-top	-0.355	-0.317	-0.291	-0.166	-0.019	0.039	0.061	0.069
Precast-top	-0.273	-0.242	-0.100	0.557	1.359	1.828	2.125	2.267
Bottom	2.164	3.981	3.786	2.949	1.858	1.288	0.966	0.816

POSITIVE MOMENT ENVELOPE : SERVICE I (Final 2)

	Bearing	Trans	H/2	0.10L/0.90L	0.20L/0.80L	0.30L/0.70L	0.40L/0.60L	Midspan
Topping-top	-0.087	-0.076	-0.068	-0.032	0.014	0.046	0.065	0.071
Precast-top	-0.132	-0.111	0.020	0.630	1.377	1.832	2.127	2.267
Bottom	1.388	3.300	3.157	2.572	1.765	1.268	0.954	0.812

NEGATIVE MOMENT ENVELOPE : SERVICE I (Final 2)

	Bearing	Trans	H/2	0.10L/0.90L	0.20L/0.80L	0.30L/0.70L	0.40L/0.60L	Midspan
Topping-top	-0.100	-0.088	-0.080	-0.042	0.007	0.042	0.063	0.071
Precast-top	-0.138	-0.118	0.013	0.625	1.373	1.830	2.126	2.267
Bottom	1.424	3.336	3.192	2.599	1.784	1.281	0.960	0.812

POSITIVE MOMENT ENVELOPE : SERVICE I (Final 3)

	Bearing	Trans	H/2	0.10L/0.90L	0.20L/0.80L	0.30L/0.70L	0.40L/0.60L	Midspan
Topping-top	-0.014	-0.011	-0.008	0.017	0.087	0.176	0.236	0.254
Precast-top	-0.050	-0.041	0.024	0.333	0.732	0.999	1.174	1.252
Bottom	0.608	1.573	1.504	1.194	0.658	0.208	-0.090	-0.203

NEGATIVE MOMENT ENVELOPE : SERVICE I (Final 3)

	Bearing	Trans	H/2	0.10L/0.90L	0.20L/0.80L	0.30L/0.70L	0.40L/0.60L	Midspan
Topping-top	-0.369	-0.330	-0.304	-0.177	-0.029	0.018	0.029	0.034
Precast-top	-0.238	-0.213	-0.136	0.228	0.669	0.913	1.062	1.133
Bottom	1.637	2.474	2.339	1.737	0.984	0.649	0.487	0.411

ULTIMATE MOMENT (k.ft)

STRENGTH I

Location, ft	Trans	H/2	0.10L/0.90L	0.20L/0.80L	0.30L/0.70L	0.40L/0.60L	Midspan	Depress
	2.000	3.517	11.700	24.400	37.100	49.800	62.500	43.450
Mu-req'd	651.5	1225.2	4283.3	9165.5	13740.4	16646.7	17560.5	15193.5
Mu-prv'd	16564.1	18039.7	25861.5	27180.5	28259.0	28798.2	28798.2	28528.6

CAMBER / DEFLECTION (in) at Midspan (0.5 x L = 62.50 ft)

SERVICE I

	Release	Mult	Erection	Mult	Final
Prestress	4.466	1.80	8.039	2.20	9.826
Self Wt.	-1.761	1.85	-3.258	2.40	-4.227
Deck + Haunch			-2.175	2.30	-5.002
DL-Prec. (DC)			0.000	3.00	0.000



Program: LEAP®
CONSPAN®
Version: 08.01.00.10

Copyright © Bentley Systems, Inc. 1984 - 2008.
www.bentley.com
1-800-778-4277

By: A. Pott
Date: Jan/4/2010
CKD:
Date:

File Name: 76-21-125-21-124 U72C.csl

	Release	Mult	Erection	Mult	Final
Diaphragm			0.000	3.00	0.000
DL-Prec. (DW)			0.000	3.00	0.000
DL-Comp. (DC)			-0.015	3.00	-0.044
DL-Comp. (DW)			-0.070	3.00	-0.210
Total	2.705		2.521		0.342

Positive values indicate upward deflection.



DESIGN STATUS

Span:3, Beam:7

RELEASE STRESSES (ksi)

Limiting Stresses		
Compression	Tens with Reinf	Tens without Reinf
4.050	-0.624	-0.200

Computed Stresses							
	Trans	0.10L/0.90L	0.20L/0.80L	0.30L/0.70L	0.40L/0.60L	Midspan	Depress.
Location, ft	3.000	12.700	25.400	38.100	50.800	63.500	44.450
Precast-top	-0.195	-0.067	0.041	0.041	0.068	0.123	0.002
Bottom	3.617	3.573	3.460	3.449	3.418	3.368	3.477
As_top, in2	0.000	0.000	0.000	0.000	0.000	0.000	0.000

FINAL STRESSES (ksi)

Limiting Stresses			
		Precast	Topping-Top
Final 1 (P/S+DL+LL)	Compression	5.400	4.320
Final 1	Tension	-0.570	-0.510
Final 2 (P/S+DL)	Compression	4.050	3.240
Final 3 (0.5(P/S+DL)+LL)	Compression	3.600	2.880

Computed Stresses								
POSITIVE MOMENT ENVELOPE : SERVICE I (Final 1)								
	Bearing	Trans	H/2	0.10L/0.90L	0.20L/0.80L	0.30L/0.70L	0.40L/0.60L	Midspan
Location, ft	0.000	2.000	3.517	11.700	24.400	37.100	49.800	62.500
Topping-top	-0.058	-0.048	-0.041	0.001	0.094	0.199	0.268	0.289
Precast-top	-0.116	-0.074	0.074	0.771	1.647	2.215	2.581	2.744
Bottom	1.302	3.202	3.045	2.364	1.328	0.565	0.071	-0.127

POSITIVE MOMENT ENVELOPE : SERVICE III (Final 1)								
	Bearing	Trans	H/2	0.10L/0.90L	0.20L/0.80L	0.30L/0.70L	0.40L/0.60L	Midspan
Topping-top	-0.064	-0.054	-0.047	-0.006	0.078	0.168	0.228	0.245
Precast-top	-0.119	-0.077	0.072	0.768	1.639	2.198	2.559	2.720
Bottom	1.320	3.217	3.060	2.383	1.373	0.650	0.184	-0.005

NEGATIVE MOMENT ENVELOPE : SERVICE I (Final 1)								
	Bearing	Trans	H/2	0.10L/0.90L	0.20L/0.80L	0.30L/0.70L	0.40L/0.60L	Midspan
Topping-top	-0.419	-0.374	-0.344	-0.197	-0.026	0.039	0.061	0.069
Precast-top	-0.307	-0.249	-0.089	0.664	1.582	2.128	2.468	2.624
Bottom	2.349	4.120	3.897	2.920	1.665	1.013	0.651	0.487



NEGATIVE MOMENT ENVELOPE : SERVICE III (Final 1)

	Bearing	Trans	H/2	0.10L/0.90L	0.20L/0.80L	0.30L/0.70L	0.40L/0.60L	Midspan
Topping-top	-0.355	-0.317	-0.291	-0.166	-0.019	0.039	0.061	0.069
Precast-top	-0.273	-0.219	-0.060	0.681	1.586	2.128	2.468	2.625
Bottom	2.164	3.959	3.749	2.833	1.646	1.011	0.649	0.486

POSITIVE MOMENT ENVELOPE : SERVICE I (Final 2)

	Bearing	Trans	H/2	0.10L/0.90L	0.20L/0.80L	0.30L/0.70L	0.40L/0.60L	Midspan
Topping-top	-0.087	-0.076	-0.068	-0.032	0.014	0.046	0.065	0.071
Precast-top	-0.132	-0.088	0.060	0.753	1.604	2.132	2.471	2.625
Bottom	1.388	3.279	3.119	2.456	1.553	0.991	0.638	0.482

NEGATIVE MOMENT ENVELOPE : SERVICE I (Final 2)

	Bearing	Trans	H/2	0.10L/0.90L	0.20L/0.80L	0.30L/0.70L	0.40L/0.60L	Midspan
Topping-top	-0.100	-0.088	-0.080	-0.042	0.007	0.042	0.063	0.071
Precast-top	-0.138	-0.095	0.053	0.748	1.600	2.130	2.469	2.625
Bottom	1.424	3.314	3.155	2.483	1.573	1.004	0.644	0.482

POSITIVE MOMENT ENVELOPE : SERVICE I (Final 3)

	Bearing	Trans	H/2	0.10L/0.90L	0.20L/0.80L	0.30L/0.70L	0.40L/0.60L	Midspan
Topping-top	-0.014	-0.011	-0.008	0.017	0.087	0.176	0.236	0.254
Precast-top	-0.050	-0.029	0.044	0.394	0.845	1.149	1.346	1.431
Bottom	0.608	1.562	1.485	1.136	0.552	0.070	-0.248	-0.368

NEGATIVE MOMENT ENVELOPE : SERVICE I (Final 3)

	Bearing	Trans	H/2	0.10L/0.90L	0.20L/0.80L	0.30L/0.70L	0.40L/0.60L	Midspan
Topping-top	-0.369	-0.330	-0.304	-0.177	-0.029	0.018	0.029	0.034
Precast-top	-0.238	-0.202	-0.116	0.290	0.782	1.063	1.233	1.312
Bottom	1.637	2.463	2.320	1.679	0.878	0.511	0.329	0.246

ULTIMATE MOMENT (k.ft)

STRENGTH I

	Trans	H/2	0.10L/0.90L	0.20L/0.80L	0.30L/0.70L	0.40L/0.60L	Midspan	Depress
Location, ft	2.000	3.517	11.700	24.400	37.100	49.800	62.500	43.450
Mu-req'd	728.4	1358.7	4697.5	9932.6	14759.4	17817.0	18781.2	16288.2
Mu-prv'd	16564.1	18039.7	25861.5	27180.5	28259.0	28798.2	28798.2	28528.6

Note: Check minimum reinforcement criteria (LRFD Art. 5.7.3.3.2) in Ultimate Moment detailed report.

CAMBER / DEFLECTION (in) at Midspan (0.5 x L = 62.50 ft)

SERVICE I

	Release	Mult	Erection	Mult	Final
Prestress	4.466	1.80	8.039	2.20	9.826
Self Wt.	-1.761	1.85	-3.258	2.40	-4.227



Program: LEAP®
CONSPAN®
Version: 08.01.00.10

Copyright © Bentley Systems, Inc. 1984 - 2008.
www.bentley.com
1-800-778-4277

By: A. Pott
Date: Jan/4/2010
CKD:
Date:

File Name: 76-21-125-21-124 U72C.csl

	Release	Mult	Erection	Mult	Final
Deck + Haunch			-2.175	2.30	-5.002
DL-Prec. (DC)			-0.389	3.00	-1.168
Diaphragm			0.000	3.00	0.000
DL-Prec. (DW)			0.000	3.00	0.000
DL-Comp. (DC)			-0.015	3.00	-0.044
DL-Comp. (DW)			-0.070	3.00	-0.210
Total	2.705		2.132		-0.825

Positive values indicate upward deflection.



Program: LEAP®
CONSPAN®
Version: 08.01.00.10

Copyright © Bentley Systems, Inc. 1984 - 2008.
www.bentley.com
1-800-778-4277

By: A. Pott
Date: Jan/4/2010
CKD:
Date:

File Name: 76-21-125-21-124_U72C.csl

PROPERTIES

Span: 3, Beam: 2

PRECAST DATA:

Section Id	U72C					
Type	Open Box Beam					
Fling width	Top	131.000	in	Bot	54.000	in
thick	Top	6.350	in	Bot	8.100	in
Stems	No	2				
	Top	7.500	in			
	Bot	7.500	in			
Shear width		15.000	in			

GENERAL BRIDGE DATA:

Bridge Width	197.00	ft
Curb-to-curb	194.00	ft
Beam Spac. Lt./Rt	25.00/ 25.00	ft
Lane width	12.00	ft
Number of lanes	16	
Interior/Exterior	Interior	
Start Skew Angle	-34.00	degrees
End Skew Angle	-34.00	degrees

TOPPING DATA:

Deck	Thickness	8.000	in
Haunch:	Thickness	4.400	in
	Width	64.000	in
Effective	width	300.000	in (Art. 4.6.2.6.1)

GENERAL LOAD DATA:

Dead loads on precast:
UNITS: (Point: kips, Location: ft)
(Line: klf)

DC/DW	Type	Mag.	Loc.
DC	Line	-0.500	-
DC	Line	0.500	-



Program: LEAP®
CONSPAN®
Version: 08.01.00.10

Copyright © Bentley Systems, Inc. 1984 - 2008.
www.bentley.com
1-800-778-4277

By: A. Pott
Date: Jan/4/2010
CKD:
Date:

File Name: 76-21-125-21-124_U72C.csl

Dead loads on composite: See Project info for composite loads

GENERAL SPAN DATA:

Overall length	127.000	ft
Release length	127.000	ft
Design length	125.000	ft

KERN POINTS:

Upper	54.09	in
Lower	17.76	in

DISTRIBUTION FACTORS (Art. 4.6.2.2):

Live Negative Moment	Left Side	(2+ lanes loaded)	1.498	(Calculated)	(#)
Live Negative Moment	Right Side	(2+ lanes loaded)	1.498	(Calculated)	(#)
Live Negative Moment	Left Side	(1 lane loaded)	0.931	(Calculated)	(#)
Live Negative Moment	Right Side	(1 lane loaded)	0.931	(Calculated)	(#)
Live Positive Moment		(2+ lanes loaded)	1.498	(Calculated)	(#)
Live Positive Moment		(1 lane loaded)	0.931	(Calculated)	(#)
Live Shear		(2+ lanes loaded)	1.700	(Calculated)	(#)
Live Shear		(1 lane loaded)	1.056	(Calculated)	(#)

(#) Lever rule (C4.6.2.2.1)

Dead Loads and Pedestrian Load distributed based on Tributary Fraction

Pedestrian	0.127	(Calculated)
Comp. DC	0.127	(Calculated)
Comp. DW	0.127	(Calculated)

RESISTANCE FACTORS (Art. 5.5.4.2):

Flexure Reinforced	
Compression controlled sections	0.75
Tension controlled sections	0.90
Flexure Prestressed	
Compression controlled sections	0.75



Program: LEAP®
CONSPAN®
Version: 08.01.00.10

Copyright © Bentley Systems, Inc. 1984 - 2008.
www.bentley.com
1-800-778-4277

By: A. Pott
Date: Jan/4/2010
CKD:
Date:

File Name: 76-21-125-21-124 U72C.csl

Tension controlled sections	1.00
Shear	0.90

Span: 3, Beam: 2

SECTION PROPERTIES:

	PRECAST		COMPOSITE		
Area	1765.1	in2	4163.6	in2	#
Total Height	72.00	in	84.40	in	
Mom. of Inertia (Ixx)	1154250	in4	3135173	in4	#
Ht. of c.g.	35.84	in	61.13	in	#
Density	150.00	pcf	150.00	pcf	
Self-weight	1838.6	plf	4632.0	plf	
Mom. of Inertia (Iyy)	2057200.1	in4			
Poisson's Ratio	0.2				

(#) Of Total Section using $E_c/E_c = 0.8944$

Use transformed strand and rebar: Strand Only

Location,	ft	Bearing 0.00	Trans 2.00	H/2 3.52	0.10L 11.70	0.20L 24.40	0.30L 37.10	0.40L 49.80	Midspan 62.50
Precast:(At Release, using	Ec =	4980.8ksi)							
Area,	in2	1790.4	1840.9	1840.9	1843.0	1843.0	1843.0	1843.0	1843.0
Yb,	in	35.54	34.96	34.94	34.83	34.71	34.58	34.52	34.52
MI(Ixx),	in4	1165252	1187803	1188926	1196949	1207958	1220229	1226837	1226837
Composite:(At Final, using	Ec =	5751.4ksi)							
Area,	in2	4184.8	4227.1	4227.1	4228.8	4228.8	4228.8	4228.8	4228.8
Yb,	in	60.90	60.43	60.43	60.38	60.33	60.29	60.26	60.26
MI(Ixx),	in4	3180342	3272062	3274157	3290773	3309701	3329716	3340130	3340130

Span: 3, Beam: 2

STRESS LIMITS (Art. 5.9.4):

STRESS LIMITS AT RELEASE BEFORE LOSSES:

PRECAST



Program: LEAP®
CONSPAN®
Version: 08.01.00.10

Copyright © Bentley Systems, Inc. 1984 - 2008.
www.bentley.com
1-800-778-4277

By: A. Pott
Date: Jan/4/2010
CKD:
Date:

File Name: 76-21-125-21-124 U72C.csl

		PRECAST	
Strength		6.75	ksi
Elasticity		4980.8	ksi
Max comp		4.05	ksi
Max tens		-0.20	ksi
Max tens,	w/reinf	-0.62	ksi

STRESS LIMITS AT FINAL AFTER LOSSES:

	PRECAST		DECK	
Strength	9.00	ksi	7.20	ksi
Elasticity	5751.38	ksi	5144.19	ksi

STRESS LIMITS AT FINAL 1 (P/S + DL + LL):

	PRECAST		DECK	
Max comp	5.40	ksi	4.32	ksi

STRESS LIMITS AT FINAL 2 (P/S + DL):

	PRECAST		DECK	
Max comp	4.05	ksi	3.24	ksi

STRESS LIMITS AT FINAL 3 (50% P/S + 50% DL + LL):

	PRECAST		DECK	
Max comp	3.60	ksi	2.88	ksi

SERVICE III (Tension):

	PRECAST		DECK	
Max tens	-0.57	ksi	-0.51	ksi

Span: 3, Beam: 2

PRESTRESSED STEEL:



Program: LEAP®
CONSPAN®
Version: 08.01.00.10

Copyright © Bentley Systems, Inc. 1984 - 2008.
www.bentley.com
1-800-778-4277

By: A. Pott
Date: Jan/4/2010
CKD:
Date:

File Name: 76-21-125-21-124_U72C.csl

76 strands, 6/10-270K-LL, Low relaxation strands
Depressed at 0.35L (44.45 ft from member end)

END PATTERN (Ycg = 14.82 in):

15 @ 5.880 in	23 @ 2.250 in	2 @ 57.500 in	24 @ 4.060 in
2 @ 59.500 in	2 @ 61.500 in	2 @ 63.500 in	2 @ 65.500 in
2 @ 67.500 in	2 @ 69.500 in		

MID PATTERN (Ycg = 4.64 in):

(A) Draped:

2 @ 2.250 in	2 @ 4.250 in	2 @ 6.250 in	2 @ 8.250 in
2 @ 10.250 in	2 @ 12.250 in	2 @ 14.250 in	

(B) Straight:

15 @ 5.880 in	23 @ 2.250 in	24 @ 4.060 in
---------------	---------------	---------------

SHIELDING AND REDUCED INITIAL PULLS:

Group	Strands	End	Heights	Mid	End	Shielding	Mid	Initial Frac	Pull Pull/Str
1	2	5.880	in	5.880	in	8.00	ft	75.0 %	43.9

Check for Art. 5.11.4.3 (debond termination distances): OK

Strand Diameter	0.600	in
Strand Area	0.217	in ²
Total Strand Area	16.492	in ²
Trans. Len, bonded	3.000	ft
Trans. Len, debonded	3.000	ft
Dev. Len, bonded	11.839	ft
Dev. Len, debonded	14.799	ft
Holddown Force	63.383	kips
Tensile Strength(fpu)	270.0	ksi
Initial Prestress = 0.75fpu	202.5	ksi
Initial Pull	3339.6	kips
Beam Shrtng (PL/AE)	0.555	in

REINFORCING STEEL:

Tension	/Shear	steel:
fy	60.0	ksi
Es	29000	ksi
fs	24.0	ksi



Program: LEAP®
CONSPAN®
Version: 08.01.00.10

Copyright © Bentley Systems, Inc. 1984 - 2008.
www.bentley.com
1-800-778-4277

By: A. Pott
Date: Jan/4/2010
CKD:
Date:

File Name: 76-21-125-21-124_U72C.csl

LOSSES

Note: Values are calculated at Midspan

Str. area	16.4920	in ²
Ycg	4.64	in
P_init	3339.6	kips
Ecc	31.20	in
Days to release	0.75	
Rel. Humid.(RH)	60.0	%
Es	28500.0	ksi
Eci	4981	ksi

AASHTO LOSSES

Elastic Shortening ** 18.26 ksi (Eq 5.9.5.2.3a-1), (fcgp= 3.191 ksi)

Elastic Gains		Gains	Adjustment
due to Precast Loads		-7.90 ksi	0.00 ksi
due to Composite Loads		-0.90 ksi	0.00 ksi
due to Live Loads		-2.23 ksi	0.00 ksi

Time Dependent Losses (Approximate Method (Art.5.9.5.3))

	Initial	Final	
Steel relaxation	0.00 ksi	2.40 ksi	(Eq 5.9.5.3-1)
Concrete shrinkage	0.00 ksi	8.52 ksi	(Eq 5.9.5.3-1)
Concrete creep	0.00 ksi	13.43 ksi	(Eq 5.9.5.3-1)
Sub-total	18.26 ksi	13.31 ksi	(6.57 %)
Total Prestress Losses		31.57 ksi	(15.59 %)

Prestressing Stress Limit Check (Table 5.9.3.1)

initial fpi = 202.5 ksi < 0.75 fpu, OK
initial fpe = 170.9 ksi < 0.80 fpy, OK

** Since the transformed section properties option has been selected, even though ES losses have been calculated explicitly here, they are not included as a part of stress calculations. Please see theory section for complete explanation.



DESIGN STATUS

Span:3, Beam:3

RELEASE STRESSES (ksi)

Limiting Stresses		
Compression	Tens with Reinf	Tens without Reinf
4.050	-0.624	-0.200

Computed Stresses							
	Trans	0.10L/0.90L	0.20L/0.80L	0.30L/0.70L	0.40L/0.60L	Midspan	Depress.
Location, ft	3.000	12.700	25.400	38.100	50.800	63.500	44.450
Precast-top	-0.181	-0.082	-0.041	-0.095	-0.065	-0.011	-0.131
Bottom	3.604	3.629	3.785	3.994	3.961	3.911	4.020
As_top, in2	0.000	0.000	0.000	0.000	0.000	0.000	0.000

FINAL STRESSES (ksi)

Limiting Stresses			
		Precast	Topping-Top
Final 1 (P/S+DL+LL)	Compression	5.400	4.320
Final 1	Tension	-0.570	-0.510
Final 2 (P/S+DL)	Compression	4.050	3.240
Final 3 (0.5(P/S+DL)+LL)	Compression	3.600	2.880

Computed Stresses								
POSITIVE MOMENT ENVELOPE : SERVICE I (Final 1)								
	Bearing	Trans	H/2	0.10L/0.90L	0.20L/0.80L	0.30L/0.70L	0.40L/0.60L	Midspan
Location, ft	0.000	2.000	3.517	11.700	24.400	37.100	49.800	62.500
Topping-top	-0.058	-0.048	-0.041	0.001	0.094	0.198	0.267	0.288
Precast-top	-0.111	-0.054	0.098	0.788	1.626	2.161	2.538	2.703
Bottom	1.287	3.154	2.993	2.356	1.543	0.973	0.472	0.274

POSITIVE MOMENT ENVELOPE : SERVICE III (Final 1)								
	Bearing	Trans	H/2	0.10L/0.90L	0.20L/0.80L	0.30L/0.70L	0.40L/0.60L	Midspan
Topping-top	-0.064	-0.054	-0.047	-0.006	0.078	0.168	0.227	0.245
Precast-top	-0.114	-0.057	0.095	0.784	1.617	2.144	2.516	2.680
Bottom	1.304	3.169	3.008	2.374	1.588	1.057	0.585	0.395

NEGATIVE MOMENT ENVELOPE : SERVICE I (Final 1)								
	Bearing	Trans	H/2	0.10L/0.90L	0.20L/0.80L	0.30L/0.70L	0.40L/0.60L	Midspan
Topping-top	-0.419	-0.374	-0.344	-0.197	-0.026	0.038	0.060	0.069
Precast-top	-0.302	-0.230	-0.066	0.681	1.561	2.074	2.425	2.584
Bottom	2.334	4.072	3.846	2.911	1.878	1.416	1.047	0.882

274



Program: LEAP®
CONSPAN®
Version: 08.01.00.10
File Name: 76-21-125-21-124_U72C.csl

Copyright © Bentley Systems, Inc. 1984 - 2008.
www.bentley.com
1-800-778-4277

By: A. Pott
Date: Jan/4/2010
CKD:
Date:

NEGATIVE MOMENT ENVELOPE : SERVICE III (Final 1)

	Bearing	Trans	H/2	0.10L/0.90L	0.20L/0.80L	0.30L/0.70L	0.40L/0.60L	Midspan
Topping-top	-0.355	-0.317	-0.291	-0.166	-0.019	0.039	0.061	0.069
Precast-top	-0.268	-0.199	-0.037	0.698	1.564	2.074	2.425	2.584
Bottom	2.149	3.911	3.698	2.824	1.859	1.414	1.046	0.882

POSITIVE MOMENT ENVELOPE : SERVICE I (Final 2)

	Bearing	Trans	H/2	0.10L/0.90L	0.20L/0.80L	0.30L/0.70L	0.40L/0.60L	Midspan
Topping-top	-0.087	-0.076	-0.068	-0.032	0.014	0.046	0.065	0.071
Precast-top	-0.126	-0.069	0.083	0.770	1.582	2.078	2.427	2.585
Bottom	1.373	3.231	3.068	2.448	1.767	1.394	1.034	0.878

NEGATIVE MOMENT ENVELOPE : SERVICE I (Final 2)

	Bearing	Trans	H/2	0.10L/0.90L	0.20L/0.80L	0.30L/0.70L	0.40L/0.60L	Midspan
Topping-top	-0.100	-0.088	-0.080	-0.042	0.007	0.042	0.063	0.071
Precast-top	-0.133	-0.076	0.077	0.765	1.579	2.075	2.426	2.585
Bottom	1.409	3.266	3.103	2.474	1.786	1.408	1.040	0.878

POSITIVE MOMENT ENVELOPE : SERVICE I (Final 3)

	Bearing	Trans	H/2	0.10L/0.90L	0.20L/0.80L	0.30L/0.70L	0.40L/0.60L	Midspan
Topping-top	-0.014	-0.011	-0.008	0.017	0.087	0.175	0.235	0.253
Precast-top	-0.048	-0.020	0.056	0.403	0.835	1.122	1.324	1.411
Bottom	0.600	1.539	1.460	1.132	0.660	0.275	-0.044	-0.165

NEGATIVE MOMENT ENVELOPE : SERVICE I (Final 3)

	Bearing	Trans	H/2	0.10L/0.90L	0.20L/0.80L	0.30L/0.70L	0.40L/0.60L	Midspan
Topping-top	-0.369	-0.330	-0.304	-0.176	-0.029	0.018	0.029	0.034
Precast-top	-0.235	-0.192	-0.104	0.298	0.772	1.036	1.212	1.291
Bottom	1.629	2.439	2.294	1.674	0.984	0.712	0.527	0.444

ULTIMATE MOMENT (k.ft)

STRENGTH I

Location, ft	Trans	H/2	0.10L/0.90L	0.20L/0.80L	0.30L/0.70L	0.40L/0.60L	Midspan	Depress
	2.000	3.517	11.700	24.400	37.100	49.800	62.500	43.450
Mu-req'd	743.7	1385.4	4780.4	10086.0	14963.3	18051.1	19025.4	16507.2
Mu-prv'd	16393.9	17879.9	26052.3	28902.9	31659.3	32410.9	32410.9	32035.1

CAMBER / DEFLECTION (in) at Midspan (0.5 x L = 62.50 ft)

SERVICE I

	Release	Mult	Erection	Mult	Final
Prestress	4.914	1.80	8.846	2.20	10.812
Self Wt.	-1.749	1.85	-3.236	2.40	-4.198
Deck + Haunch			-2.160	2.30	-4.968
DL-Prec. (DC)			-0.464	3.00	-1.392



Program: LEAP®
CONSPAN®
Version: 08.01.00.10

Copyright © Bentley Systems, Inc. 1984 - 2008.
www.bentley.com
1-800-778-4277

By: A. Pott
Date: Jan/4/2010
CKD:
Date:

File Name: 76-21-125-21-124_U72C.csl

	Release	Mult	Erection	Mult	Final
Diaphragm			0.000	3.00	0.000
DL-Prec. (DW)			0.000	3.00	0.000
DL-Comp. (DC)			-0.015	3.00	-0.044
DL-Comp. (DW)			-0.069	3.00	-0.207
Total	3.165		2.903		0.004

Positive values indicate upward deflection.



Program: LEAP®
CONSPAN®
Version: 08.01.00.10

Copyright © Bentley Systems, Inc. 1984 - 2008.
www.bentley.com
1-800-778-4277

By: A. Pott
Date: Jan/4/2010
CKD:
Date:

File Name: 76-21-125-21-124_U72C.csl

PROPERTIES

Span: 3, Beam: 3

PRECAST DATA:

Section Id	U72C					
Type	Open Box Beam					
Fling width	Top	131.000	in	Bot	54.000	in
thick	Top	6.350	in	Bot	8.100	in
Stems	No	2				
	Top	7.500	in			
	Bot	7.500	in			
Shear width		15.000	in			

GENERAL BRIDGE DATA:

Bridge Width	197.00	ft
Curb-to-curb	194.00	ft
Beam Spac. Lt./Rt	25.00/ 25.00	ft
Lane width	12.00	ft
Number of lanes	16	
Interior/Exterior	Interior	
Start Skew Angle	-34.00	degrees
End Skew Angle	-34.00	degrees

TOPPING DATA:

Deck	Thickness	8.000	in
Haunch:			
	Thickness	4.400	in
	Width	64.000	in
Effective	width	300.000	in (Art. 4.6.2.6.1)

GENERAL LOAD DATA:

Dead loads on precast:
UNITS: (Point: kips, Location: ft)
(Line: klf)

DC/DW	Type	Mag.	Loc.
DC	Line	0.600	-



Program: LEAP®
CONSPAN®
Version: 08.01.00.10

Copyright © Bentley Systems, Inc. 1984 - 2008.
www.bentley.com
1-800-778-4277

By: A. Pott
Date: Jan/4/2010
CKD:
Date:

File Name: 76-21-125-21-124 U72C.csl

Dead loads on composite: See Project info for composite loads

GENERAL SPAN DATA:

Overall length	127.000	ft
Release length	127.000	ft
Design length	125.000	ft

KERN POINTS:

Upper	54.09	in
Lower	17.76	in

DISTRIBUTION FACTORS (Art. 4.6.2.2):

Live Negative Moment	Left Side	(2+ lanes loaded)	1.498	(Calculated)	(#)
Live Negative Moment	Right Side	(2+ lanes loaded)	1.498	(Calculated)	(#)
Live Negative Moment	Left Side	(1 lane loaded)	0.931	(Calculated)	(#)
Live Negative Moment	Right Side	(1 lane loaded)	0.931	(Calculated)	(#)
Live Positive Moment		(2+ lanes loaded)	1.498	(Calculated)	(#)
Live Positive Moment		(1 lane loaded)	0.931	(Calculated)	(#)
Live Shear		(2+ lanes loaded)	1.700	(Calculated)	(#)
Live Shear		(1 lane loaded)	1.056	(Calculated)	(#)

(#) Lever rule (C4.6.2.2.1)

Dead Loads and Pedestrian Load distributed based on Tributary Fraction

Pedestrian	0.127	(Calculated)
Comp. DC	0.127	(Calculated)
Comp. DW	0.127	(Calculated)

RESISTANCE FACTORS (Art. 5.5.4.2):

Flexure Reinforced	
Compression controlled sections	0.75
Tension controlled sections	0.90
Flexure Prestressed	
Compression controlled sections	0.75



Program: LEAP®
CONSPAN®
Version: 08.01.00.10

Copyright © Bentley Systems, Inc. 1984 - 2008.
www.bentley.com
1-800-778-4277

By: A. Pott
Date: Jan/4/2010
CKD:
Date:

File Name: 76-21-125-21-124_U72C.csl

Tension controlled sections	1.00
Shear	0.90

Span: 3, Beam: 3

SECTION PROPERTIES:

	PRECAST		COMPOSITE		
Area	1765.1	in2	4163.6	in2	#
Total Height	72.00	in	84.40	in	
Mom. of Inertia (Ixx)	1154250	in4	3135173	in4	#
Ht. of c.g.	35.84	in	61.13	in	#
Density	150.00	pcf	150.00	pcf	
Self-weight	1838.6	plf	4632.0	plf	
Mom. of Inertia (Iyy)	2057200.1	in4			
Poisson's Ratio	0.2				

(#) Of Total Section using $E_c/E_c = 0.8944$

Use transformed strand and rebar: Strand Only

Location,	ft	Bearing	Trans	H/2	0.10L	0.20L	0.30L	0.40L	Midspan
		0.00	2.00	3.52	11.70	24.40	37.10	49.80	62.50
Precast:(At Release, using	Ec =	4980.8ksi)							
Area,	in2	1790.4	1840.9	1840.9	1844.0	1849.0	1853.2	1853.2	1853.2
Yb,	in	35.55	34.96	34.95	34.81	34.61	34.42	34.36	34.36
MI(Ixx),	in4	1165098	1187345	1188460	1197770	1212883	1228624	1235183	1235183
Composite:(At Final, using	Ec =	5751.4ksi)							
Area,	in2	4184.8	4227.1	4227.1	4229.7	4233.9	4237.4	4237.4	4237.4
Yb,	in	60.90	60.43	60.43	60.36	60.27	60.18	60.15	60.15
MI(Ixx),	in4	3180055	3271202	3273291	3293291	3324567	3355069	3365452	3365452

Span: 3, Beam: 3

STRESS LIMITS (Art. 5.9.4):

STRESS LIMITS AT RELEASE BEFORE LOSSES:

PRECAST



Program: LEAP®
CONSPAN®
Version: 08.01.00.10

Copyright © Bentley Systems, Inc. 1984 - 2008.
www.bentley.com
1-800-778-4277

By: A. Pott
Date: Jan/4/2010
CKD:
Date:

File Name: 76-21-125-21-124 U72C.csl

PRECAST		
Strength	6.75	ksi
Elasticity	4980.8	ksi
Max comp	4.05	ksi
Max tens	-0.20	ksi
Max tens, w/reinf	-0.62	ksi

STRESS LIMITS AT FINAL AFTER LOSSES:

	PRECAST		DECK	
Strength	9.00	ksi	7.20	ksi
Elasticity	5751.38	ksi	5144.19	ksi

STRESS LIMITS AT FINAL 1 (P/S + DL + LL):

	PRECAST		DECK	
Max comp	5.40	ksi	4.32	ksi

STRESS LIMITS AT FINAL 2 (P/S + DL):

	PRECAST		DECK	
Max comp	4.05	ksi	3.24	ksi

STRESS LIMITS AT FINAL 3 (50% P/S + 50% DL + LL):

	PRECAST		DECK	
Max comp	3.60	ksi	2.88	ksi

SERVICE III (Tension):

	PRECAST		DECK	
Max tens	-0.57	ksi	-0.51	ksi

Span: 3, Beam: 3

PRESTRESSED STEEL:



Program: LEAP®
CONSPAN®
Version: 08.01.00.10

Copyright © Bentley Systems, Inc. 1984 - 2008.
www.bentley.com
1-800-778-4277

By: A. Pott
Date: Jan/4/2010
CKD:
Date:

File Name: 76-21-125-21-124_U72C.csl

86 strands, 6/10-270K-LL, Low relaxation strands
Depressed at 0.35L (44.45 ft from member end)

END PATTERN (Ycg = 13.78 in):

25 @ 5.880 in	23 @ 2.250 in	2 @ 59.500 in	2 @ 61.500 in
2 @ 63.500 in	2 @ 65.500 in	24 @ 4.060 in	2 @ 67.500 in
2 @ 69.500 in	2 @ 57.500 in		

MID PATTERN (Ycg = 4.79 in):

(A) Draped:

2 @ 4.250 in	2 @ 6.250 in	2 @ 8.250 in	2 @ 10.250 in
2 @ 12.250 in	2 @ 14.250 in	2 @ 2.250 in	

(B) Straight:

25 @ 5.880 in	23 @ 2.250 in	24 @ 4.060 in
---------------	---------------	---------------

SHIELDING AND REDUCED INITIAL PULLS:

Group	Strands	End	Heights	Mid	End	Shielding	Mid	Initial Frac	Pull Pull/Str
1	2	5.880	in	5.880	in	24.00	ft	0.00	ft 75.0 % 43.9
31	2	2.250	in	2.250	in	8.00	ft	0.00	ft 75.0 % 43.9
32	1	2.250	in	2.250	in	8.00	ft	0.00	ft 75.0 % 43.9
41	2	5.880	in	5.880	in	32.00	ft	0.00	ft 75.0 % 43.9
42	2	5.880	in	5.880	in	24.00	ft	0.00	ft 75.0 % 43.9
43	2	5.880	in	5.880	in	16.00	ft	0.00	ft 75.0 % 43.9
44	1	5.880	in	5.880	in	16.00	ft	0.00	ft 75.0 % 43.9

Check for Art. 5.11.4.3 (debond termination distances): OK

Strand Diameter	0.600	in
Strand Area	0.217	in ²
Total Strand Area	18.662	in ²
Trans. Len, bonded	3.000	ft
Trans. Len, debonded	3.000	ft
Dev. Len, bonded	11.899	ft
Dev. Len, debonded	14.874	ft
Holddown Force	63.383	kips
Tensile Strength(fpu)	270.0	ksi
Initial Prestress = 0.75fpu	202.5	ksi
Initial Pull	3779.1	kips
Beam Shrtng (PL/AE)	0.628	in



Program: LEAP@
CONSPAN@
Version: 08.01.00.10

Copyright © Bentley Systems, Inc. 1984 - 2008.
www.bentley.com
1-800-778-4277

By: A. Pott
Date: Jan/4/2010
CKD:
Date:

File Name: 76-21-125-21-124 U72C.csl

REINFORCING STEEL:

Tension	/Shear	steel:
fy	60.0	ksi
Es	29000	ksi
fs	24.0	ksi

LOSSES

Note: Values are calculated at Midspan

Str. area	18.6620	in ²
Ycg	4.79	in
P_init	3779.1	kips
Ecc	31.05	in
Days to release	0.75	
Rel. Humid.(RH)	60.0	%
Es	28500.0	ksi
Eci	4981	ksi

AASHTO LOSSES

Elastic Shortening ** 21.07 ksi (Eq 5.9.5.2.3a-1), (fcgp= 3.682 ksi)

	Elastic Gains	Gains	Adjustment
due to Precast Loads		-9.44 ksi	0.00 ksi
due to Composite Loads		-0.89 ksi	0.00 ksi
due to Live Loads		-2.20 ksi	0.00 ksi

Time Dependent Losses (Approximate Method (Art.5.9.5.3))

	Initial	Final
Steel relaxation	0.00 ksi	2.40 ksi (Eq 5.9.5.3-1)
Concrete shrinkage	0.00 ksi	8.52 ksi (Eq 5.9.5.3-1)
Concrete creep	0.00 ksi	15.19 ksi (Eq 5.9.5.3-1)
Sub-total	21.07 ksi (10.41 %)	13.58 ksi (6.71 %)
Total Prestress Losses		34.65 ksi (17.11 %)

Prestressing Stress Limit Check (Table 5.9.3.1)
initial fpi = 202.5 ksi < 0.75 fpu, OK
initial fpe = 167.9 ksi < 0.80 fpy, OK

** Since the transformed section properties option has been selected, even though ES losses



Bentley

Colorado DOT
4201 E. Arkansas Ave. Denver CO 80222

Sheet: DS-7
Job No: **BR R600-297**

Program: LEAP®
CONSPAN®
Version: 08.01.00.10

Copyright © Bentley Systems, Inc. 1984 - 2008.
www.bentley.com
1-800-778-4277

By: A. Pott
Date: Jan/4/2010
CKD:
Date:

File Name: 76-21-125-21-124 U72C.csl

have been calculated explicitly here, they are not included as a part of stress calculations.
Please see theory section for complete explanation.

COLORADO DEPARTMENT OF TRANSPORTATION
DESIGN COMPUTATIONS (Grid)

SPAN 5

GIRDER 3

extra load $\approx .6$ K/ft

asphalt $\approx .1$ " camber @ erection ≈ 2.88 "

84 strands w/ debonding

GIRDER 2

less load $\approx .5$ K/ft

camber @ erection ≈ 2.57

increased camber (deck) $\approx .36$ "
 increased camber (asphalt) $\approx .02$ "

≈ 2.95 "

76 strands w/ debonding

GIRDER 1

camber @ erection ≈ 2.68 "

76 strands w/ debonding (same as girder 2)

GIRDER 4

~~extra load $\approx .1$ K/ft~~

~~camber @ erection ≈ 2.94 "~~

~~81 strands w/ debonding~~

Same as girder 2

By: Date	Project no.	Project code (SA#):
Chk'd: Date	Structure no.	Sheet <u>284</u> of <u> </u>



DESIGN STATUS

Span:5, Beam:1

RELEASE STRESSES (ksi)

Limiting Stresses		
Compression	Tens with Reinf	Tens without Reinf
4.050	-0.624	-0.200

Computed Stresses							
	Trans	0.10L/0.90L	0.20L/0.80L	0.30L/0.70L	0.40L/0.60L	Midspan	Depress.
Location, ft	3.000	12.400	24.800	37.200	49.600	62.000	43.400
Precast-top	-0.199	-0.090	0.000	-0.013	0.007	0.059	-0.056
Bottom	3.621	3.595	3.498	3.499	3.474	3.427	3.531
As_top, in2	0.000	0.000	0.000	0.000	0.000	0.000	0.000

FINAL STRESSES (ksi)

Limiting Stresses			
		Precast	Topping-Top
Final 1 (P/S+DL+LL)	Compression	5.400	4.320
Final 1	Tension	-0.570	-0.510
Final 2 (P/S+DL)	Compression	4.050	3.240
Final 3 (0.5(P/S+DL)+LL)	Compression	3.600	2.880

Computed Stresses									
POSITIVE MOMENT ENVELOPE : SERVICE I (Final 1)									
	Bearing	Trans	H/2	0.10L/0.90L	0.20L/0.80L	0.30L/0.70L	0.40L/0.60L	Midspan	
Location, ft	0.000	2.250	3.517	11.650	24.050	36.450	48.850	61.250	
Topping-top	0.013	0.056	0.080	0.212	0.353	0.430	0.449	0.420	
Precast-top	-0.056	-0.027	0.085	0.700	1.425	1.854	2.119	2.229	
Bottom	0.820	2.923	2.765	1.968	0.980	0.417	0.134	0.095	

POSITIVE MOMENT ENVELOPE : SERVICE III (Final 1)									
	Bearing	Trans	H/2	0.10L/0.90L	0.20L/0.80L	0.30L/0.70L	0.40L/0.60L	Midspan	
Topping-top	0.011	0.047	0.067	0.179	0.298	0.363	0.379	0.355	
Precast-top	-0.057	-0.032	0.078	0.681	1.394	1.817	2.080	2.192	
Bottom	0.825	2.947	2.799	2.059	1.130	0.598	0.322	0.271	

NEGATIVE MOMENT ENVELOPE : SERVICE I (Final 1)									
	Bearing	Trans	H/2	0.10L/0.90L	0.20L/0.80L	0.30L/0.70L	0.40L/0.60L	Midspan	
Topping-top	-0.598	-0.535	-0.504	-0.317	-0.085	0.040	0.072	0.091	
Precast-top	-0.387	-0.355	-0.239	0.406	1.182	1.636	1.908	2.045	
Bottom	2.533	4.531	4.350	3.401	2.163	1.469	1.149	0.981	



NEGATIVE MOMENT ENVELOPE : SERVICE III (Final 1)

	Bearing	Trans	H/2	0.10L/0.90L	0.20L/0.80L	0.30L/0.70L	0.40L/0.60L	Midspan
Topping-top	-0.504	-0.450	-0.423	-0.265	-0.068	0.040	0.072	0.092
Precast-top	-0.336	-0.308	-0.195	0.435	1.191	1.637	1.908	2.045
Bottom	2.268	4.299	4.132	3.261	2.118	1.467	1.148	0.979

POSITIVE MOMENT ENVELOPE : SERVICE I (Final 2)

	Bearing	Trans	H/2	0.10L/0.90L	0.20L/0.80L	0.30L/0.70L	0.40L/0.60L	Midspan
Topping-top	0.003	0.012	0.017	0.044	0.076	0.094	0.100	0.094
Precast-top	-0.062	-0.052	0.050	0.606	1.271	1.667	1.924	2.047
Bottom	0.847	3.043	2.936	2.423	1.730	1.322	1.073	0.974

NEGATIVE MOMENT ENVELOPE : SERVICE I (Final 2)

	Bearing	Trans	H/2	0.10L/0.90L	0.20L/0.80L	0.30L/0.70L	0.40L/0.60L	Midspan
Topping-top	-0.125	-0.110	-0.103	-0.058	-0.001	0.043	0.075	0.094
Precast-top	-0.131	-0.119	-0.017	0.550	1.228	1.638	1.910	2.047
Bottom	1.205	3.374	3.260	2.700	1.937	1.459	1.141	0.974

POSITIVE MOMENT ENVELOPE : SERVICE I (Final 3)

	Bearing	Trans	H/2	0.10L/0.90L	0.20L/0.80L	0.30L/0.70L	0.40L/0.60L	Midspan
Topping-top	0.011	0.050	0.071	0.190	0.315	0.383	0.399	0.373
Precast-top	-0.026	-0.001	0.060	0.396	0.790	1.021	1.157	1.206
Bottom	0.396	1.401	1.297	0.757	0.115	-0.244	-0.403	-0.391

NEGATIVE MOMENT ENVELOPE : SERVICE I (Final 3)

	Bearing	Trans	H/2	0.10L/0.90L	0.20L/0.80L	0.30L/0.70L	0.40L/0.60L	Midspan
Topping-top	-0.536	-0.480	-0.452	-0.288	-0.084	0.018	0.034	0.044
Precast-top	-0.322	-0.295	-0.231	0.131	0.567	0.817	0.953	1.022
Bottom	1.931	2.843	2.720	2.051	1.195	0.739	0.579	0.494

ULTIMATE MOMENT (k.ft)

STRENGTH I

	Trans	H/2	0.10L/0.90L	0.20L/0.80L	0.30L/0.70L	0.40L/0.60L	Midspan	Depress
Location, ft	2.250	3.517	11.650	24.050	36.450	48.850	61.250	42.650
Mu-req'd	1914.7	2813.5	7998.2	13948.3	17723.2	19424.2	19251.2	18573.7
Mu-prv'd	16559.4	17790.6	25805.8	27130.8	28209.1	28748.3	28748.3	28478.7

CAMBER / DEFLECTION (in) at Midspan (0.5 x L = 61.25 ft)

SERVICE I

	Release	Mult	Erection	Mult	Final
Prestress	4.257	1.80	7.663	2.20	9.366
Self Wt.	-1.601	1.85	-2.961	2.40	-3.841
Deck + Haunch			-1.898	2.30	-4.366
DL-Prec. (DC)			0.000	3.00	0.000



Program: LEAP®
CONSPAN®
Version: 08.01.00.10

Copyright © Bentley Systems, Inc. 1984 - 2008.
www.bentley.com
1-800-778-4277

By: A. Pott
Date: Jan/4/2010
CKD:
Date:

File Name: 76-21-125-21-124_U72C.csl

	Release	Mult	Erection	Mult	Final
Diaphragm			0.000	3.00	0.000
DL-Prec. (DW)			0.000	3.00	0.000
DL-Comp. (DC)			-0.022	3.00	-0.065
DL-Comp. (DW)			-0.103	3.00	-0.308
Total	2.657		2.680		0.786

Positive values indicate upward deflection.



Program: LEAP®
CONSPAN®
Version: 08.01.00.10

Copyright © Bentley Systems, Inc. 1984 - 2008.
www.bentley.com
1-800-778-4277

By: A. Pott
Date: Jan/4/2010
CKD:
Date:

File Name: 76-21-125-21-124 U72C.csl

PROPERTIES

Span: 5, Beam: 1

PRECAST DATA:

Section Id	U72C				
Type	Open Box Beam				
Fling width	Top	131.000	in	Bot	54.000 in
thick	Top	6.350	in	Bot	8.100 in
Stems	No	2			
	Top	7.500	in		
	Bot	7.500	in		
Shear width		15.000	in		

GENERAL BRIDGE DATA:

Bridge Width	197.00	ft
Curb-to-curb	194.00	ft
Beam Spac. Lt./Rt	11.00/ 25.00	ft
Lane width	12.00	ft
Number of lanes	16	
Interior/Exterior	Exterior	
Start Skew Angle	-34.00	degrees
End Skew Angle	-34.00	degrees

TOPPING DATA:

Deck	Thickness	8.000	in
Haunch:	Thickness	4.400	in
	Width	64.000	in
Effective	width	282.000	in (Art. 4.6.2.6.1)

GENERAL LOAD DATA:

Dead loads on composite: See Project info for composite loads

GENERAL SPAN DATA:

Overall length	124.000	ft
----------------	---------	----



Program: LEAP@
CONSPAN@
Version: 08.01.00.10

Copyright © Bentley Systems, Inc. 1984 - 2008.
www.bentley.com
1-800-778-4277

By: A. Pott
Date: Jan/4/2010
CKD:
Date:

File Name: 76-21-125-21-124 U72C.csl

Release length	124.000	ft
Design length	122.500	ft

KERN POINTS:

Upper	54.09	in
Lower	17.76	in

DISTRIBUTION FACTORS (Art. 4.6.2.2):

Live Negative Moment	Left Side	(2+ lanes loaded)	1.657	(Calculated)	(#)
Live Negative Moment	Right Side	(2+ lanes loaded)	1.657	(Calculated)	(#)
Live Negative Moment	Left Side	(1 lane loaded)	1.248	(Calculated)	(#)
Live Negative Moment	Right Side	(1 lane loaded)	1.248	(Calculated)	(#)
Live Positive Moment		(2+ lanes loaded)	1.657	(Calculated)	(#)
Live Positive Moment		(1 lane loaded)	1.248	(Calculated)	(#)
Live Shear		(2+ lanes loaded)	1.880	(Calculated)	(#)
Live Shear		(1 lane loaded)	1.416	(Calculated)	(#)

(#) Lever rule (C4.6.2.2.1)

Dead Loads and Pedestrian Load distributed based on Tributary Fraction

Pedestrian	0.119	(Calculated)
Comp. DC	0.119	(Calculated)
Comp. DW	0.119	(Calculated)

RESISTANCE FACTORS (Art. 5.5.4.2):

Flexure Reinforced	
Compression controlled sections	0.75
Tension controlled sections	0.90
Flexure Prestressed	
Compression controlled sections	0.75
Tension controlled sections	1.00
Shear	0.90



Program: LEAP®
CONSPAN®
Version: 08.01.00.10

Copyright © Bentley Systems, Inc. 1984 - 2008.
www.bentley.com
1-800-778-4277

By: A. Pott
Date: Jan/4/2010
CKD:
Date:

File Name: 76-21-125-21-124 U72C.csl

Span: 5, Beam: 1

SECTION PROPERTIES:

	PRECAST		COMPOSITE	
Area	1765.1	in2	4034.8	in2 #
Total Height	72.00	in	84.40	in
Mom. of Inertia (Ixx)	1154250	in4	3085155	in4 #
Ht. of c.g.	35.84	in	60.52	in #
Density	150.00	pcf	150.00	pcf
Self-weight	1838.6	plf	4482.0	plf
Mom. of Inertia (Iyy)	2057200.1	in4		
Poisson's Ratio	0.2			

(#) Of Total Section using Ect/Ec = 0.8944

Use transformed strand and rebar: Strand Only

Location,	ft	Bearing	Trans	H/2	0.10L	0.20L	0.30L	0.40L	Midspan
		0.00	2.25	3.52	11.65	24.05	36.45	48.85	61.25
Precast:(At Release, using	Ec =	4980.8ksi)							
Area,	in2	1784.1	1840.9	1840.9	1843.0	1843.0	1843.0	1843.0	1843.0
Yb,	in	35.62	34.95	34.94	34.83	34.71	34.58	34.52	34.52
MI(Ixx),	in4	1162488	1187856	1188817	1196949	1207958	1220229	1226837	1226837
Composite:(At Final, using	Ec =	5751.4ksi)							
Area,	in2	4050.7	4098.3	4098.3	4100.0	4100.0	4100.0	4100.0	4100.0
Yb,	in	60.34	59.80	59.80	59.75	59.70	59.65	59.63	59.63
MI(Ixx),	in4	3118097	3218502	3220270	3236816	3255506	3275281	3285575	3285575

Span: 5, Beam: 1

STRESS LIMITS (Art. 5.9.4):

STRESS LIMITS AT RELEASE BEFORE LOSSES:

	PRECAST	
Strength	6.75	ksi
Elasticity	4980.8	ksi
Max comp	4.05	ksi
Max tens	-0.20	ksi
Max tens, w/reinf	-0.62	ksi



Program: LEAP®
CONSPAN®
Version: 08.01.00.10

Copyright © Bentley Systems, Inc. 1984 - 2008.
www.bentley.com
1-800-778-4277

By: A. Pott
Date: Jan/4/2010
CKD:
Date:

File Name: 76-21-125-21-124_U72C.csl

STRESS LIMITS AT FINAL AFTER LOSSES:

	PRECAST	DECK
Strength	9.00 ksi	7.20 ksi
Elasticity	5751.38 ksi	5144.19 ksi

STRESS LIMITS AT FINAL 1 (P/S + DL + LL):

	PRECAST	DECK
Max comp	5.40 ksi	4.32 ksi

STRESS LIMITS AT FINAL 2 (P/S + DL):

	PRECAST	DECK
Max comp	4.05 ksi	3.24 ksi

STRESS LIMITS AT FINAL 3 (50% P/S + 50% DL + LL):

	PRECAST	DECK
Max comp	3.60 ksi	2.88 ksi

SERVICE III (Tension):

	PRECAST	DECK
Max tens	-0.57 ksi	-0.51 ksi

Span: 5, Beam: 1

PRESTRESSED STEEL:

76 strands, 6/10-270K-LL, Low relaxation strands
Depressed at 0.35L (43.40 ft from member end)

END PATTERN (Ycg = 14.82 in):



Program: LEAP®
CONSPAN®
Version: 08.01.00.10

Copyright © Bentley Systems, Inc. 1984 - 2008.
www.bentley.com
1-800-778-4277

By: A. Pott
Date: Jan/4/2010
CKD:
Date:

File Name: 76-21-125-21-124_U72C.csl

15 @ 5.880 in	23 @ 2.250 in	2 @ 57.500 in	24 @ 4.060 in
2 @ 59.500 in	2 @ 61.500 in	2 @ 63.500 in	2 @ 65.500 in
2 @ 67.500 in	2 @ 69.500 in		

**MID PATTERN (Ycg = 4.64 in):
(A) Draped:**

2 @ 2.250 in	2 @ 4.250 in	2 @ 6.250 in	2 @ 8.250 in
2 @ 10.250 in	2 @ 12.250 in	2 @ 14.250 in	

(B) Straight:

15 @ 5.880 in	23 @ 2.250 in	24 @ 4.060 in
---------------	---------------	---------------

SHIELDING AND REDUCED INITIAL PULLS:

Group	Strands	End	Heights	Mid	End	Shielding	Mid	Initial Frac	Pull Pull/Str
1	2	5.880	in	5.880	in	8.00	ft	0.00	ft 75.0 % 43.9

Check for Art. 5.11.4.3 (debond termination distances): OK

Strand Diameter	0.600	in
Strand Area	0.217	in ²
Total Strand Area	16.492	in ²
Trans. Len, bonded	3.000	ft
Trans. Len, debonded	3.000	ft
Dev. Len, bonded	11.822	ft
Dev. Len, debonded	14.778	ft
Holddown Force	64.900	kips
Tensile Strength(fpu)	270.0	ksi
Initial Prestress = 0.75fpu	202.5	ksi
Initial Pull	3339.6	kips
Beam Shrtng (PL/AE)	0.542	in

REINFORCING STEEL:

Tension	/Shear	steel:
fy	60.0	ksi
Es	29000	ksi
fs	24.0	ksi

LOSSES

Note: Values are calculated at Midspan



Program: LEAP®
CONSPAN®
Version: 08.01.00.10

Copyright © Bentley Systems, Inc. 1984 - 2008.
www.bentley.com
1-800-778-4277

By: A. Pott
Date: Jan/4/2010
CKD:
Date:

File Name: 76-21-125-21-124_U72C.csl

Str. area	16.4920	in2
Ycg	4.64	in
P_init	3339.6	kips
Ecc	31.20	in
Days to release	0.75	
Rel. Humid.(RH)	60.0	%
Es	28500.0	ksi
Eci	4981	ksi

AASHTO LOSSES

Elastic Shortening ** 18.50 ksi (Eq 5.9.5.2.3a-1), (fcgp= 3.233 ksi)

	Elastic Gains	Gains	Adjustment
due to Precast Loads		-7.18 ksi	0.00 ksi
due to Composite Loads		-1.15 ksi	0.00 ksi
due to Live Loads		-3.21 ksi	0.00 ksi

Time Dependent Losses (Approximate Method (Art.5.9.5.3))

	Initial	Final	
Steel relaxation	0.00 ksi	2.40 ksi	(Eq 5.9.5.3-1)
Concrete shrinkage	0.00 ksi	8.52 ksi	(Eq 5.9.5.3-1)
Concrete creep	0.00 ksi	13.43 ksi	(Eq 5.9.5.3-1)
Sub-total	18.50 ksi	12.80 ksi	(6.32 %)
Total Prestress Losses		31.30 ksi	(15.46 %)

Prestressing Stress Limit Check (Table 5.9.3.1)
initial fpi = 202.5 ksi < 0.75 fpu, OK
initial fpe = 171.2 ksi < 0.80 fpy, OK

** Since the transformed section properties option has been selected, even though ES losses have been calculated explicitly here, they are not included as a part of stress calculations. Please see theory section for complete explanation.



DESIGN STATUS

Span:5, Beam:2

RELEASE STRESSES (ksi)

Limiting Stresses

Compression	Tens with Reinf	Tens without Reinf
4.050	-0.624	-0.200

Computed Stresses

	Trans	0.10L/0.90L	0.20L/0.80L	0.30L/0.70L	0.40L/0.60L	Midspan	Depress.
Location, ft	3.000	12.400	24.800	37.200	49.600	62.000	43.400
Precast-top	-0.199	-0.090	0.000	-0.013	0.007	0.059	-0.056
Bottom	3.621	3.595	3.498	3.499	3.474	3.427	3.531
As top, in2	0.000	0.000	0.000	0.000	0.000	0.000	0.000

FINAL STRESSES (ksi)

Limiting Stresses

	Compression	Precast	Topping-Top
Final 1 (P/S+DL+LL)	Compression	5.400	4.320
Final 1	Tension	-0.570	-0.510
Final 2 (P/S+DL)	Compression	4.050	3.240
Final 3 (0.5(P/S+DL)+LL)	Compression	3.600	2.880

Computed Stresses

POSITIVE MOMENT ENVELOPE : SERVICE I (Final 1)

	Bearing	Trans	H/2	0.10L/0.90L	0.20L/0.80L	0.30L/0.70L	0.40L/0.60L	Midspan
Location, ft	0.000	2.250	3.517	11.650	24.050	36.450	48.850	61.250
Topping-top	0.011	0.050	0.072	0.191	0.318	0.387	0.404	0.378
Precast-top	-0.057	-0.023	0.091	0.721	1.467	1.911	2.187	2.303
Bottom	0.822	2.926	2.768	1.974	0.983	0.414	0.122	0.075

POSITIVE MOMENT ENVELOPE : SERVICE III (Final 1)

	Bearing	Trans	H/2	0.10L/0.90L	0.20L/0.80L	0.30L/0.70L	0.40L/0.60L	Midspan
Topping-top	0.010	0.043	0.061	0.161	0.270	0.329	0.344	0.322
Precast-top	-0.058	-0.028	0.085	0.705	1.441	1.879	2.154	2.272
Bottom	0.827	2.948	2.799	2.055	1.118	0.577	0.291	0.233

NEGATIVE MOMENT ENVELOPE : SERVICE I (Final 1)

	Bearing	Trans	H/2	0.10L/0.90L	0.20L/0.80L	0.30L/0.70L	0.40L/0.60L	Midspan
Topping-top	-0.538	-0.481	-0.452	-0.283	-0.073	0.041	0.073	0.093
Precast-top	-0.346	-0.310	-0.192	0.465	1.255	1.723	2.007	2.148
Bottom	2.419	4.423	4.245	3.305	2.079	1.381	1.046	0.871



Program: LEAP®
CONSPAN®
Version: 08.01.00.10

Copyright © Bentley Systems, Inc. 1984 - 2008.
www.bentley.com
1-800-778-4277

By: A. Pott
Date: Jan/4/2010
CKD:
Date:

File Name: 76-21-125-21-124 U72C.csl

NEGATIVE MOMENT ENVELOPE : SERVICE III (Final 1)

	Bearing	Trans	H/2	0.10L/0.90L	0.20L/0.80L	0.30L/0.70L	0.40L/0.60L	Midspan
Topping-top	-0.456	-0.407	-0.383	-0.238	-0.059	0.042	0.074	0.094
Precast-top	-0.303	-0.270	-0.155	0.489	1.263	1.723	2.007	2.148
Bottom	2.180	4.216	4.049	3.179	2.038	1.379	1.044	0.869

POSITIVE MOMENT ENVELOPE : SERVICE I (Final 2)

	Bearing	Trans	H/2	0.10L/0.90L	0.20L/0.80L	0.30L/0.70L	0.40L/0.60L	Midspan
Topping-top	0.003	0.012	0.017	0.045	0.077	0.096	0.102	0.095
Precast-top	-0.062	-0.044	0.061	0.642	1.336	1.753	2.022	2.149
Bottom	0.847	3.035	2.923	2.382	1.657	1.228	0.966	0.864

NEGATIVE MOMENT ENVELOPE : SERVICE I (Final 2)

	Bearing	Trans	H/2	0.10L/0.90L	0.20L/0.80L	0.30L/0.70L	0.40L/0.60L	Midspan
Topping-top	-0.127	-0.112	-0.105	-0.059	-0.001	0.044	0.076	0.095
Precast-top	-0.130	-0.111	-0.004	0.586	1.294	1.725	2.008	2.149
Bottom	1.225	3.384	3.265	2.675	1.875	1.372	1.038	0.864

POSITIVE MOMENT ENVELOPE : SERVICE I (Final 3)

	Bearing	Trans	H/2	0.10L/0.90L	0.20L/0.80L	0.30L/0.70L	0.40L/0.60L	Midspan
Topping-top	0.010	0.045	0.063	0.168	0.279	0.339	0.353	0.331
Precast-top	-0.026	-0.001	0.060	0.400	0.799	1.035	1.176	1.228
Bottom	0.399	1.409	1.307	0.783	0.155	-0.200	-0.361	-0.357

NEGATIVE MOMENT ENVELOPE : SERVICE I (Final 3)

	Bearing	Trans	H/2	0.10L/0.90L	0.20L/0.80L	0.30L/0.70L	0.40L/0.60L	Midspan
Topping-top	-0.474	-0.425	-0.400	-0.254	-0.073	0.019	0.035	0.045
Precast-top	-0.281	-0.255	-0.190	0.172	0.608	0.861	1.003	1.073
Bottom	1.806	2.731	2.612	1.968	1.141	0.695	0.527	0.438

ULTIMATE MOMENT (k.ft)

STRENGTH I

Location, ft	Trans	H/2	0.10L/0.90L	0.20L/0.80L	0.30L/0.70L	0.40L/0.60L	Midspan	Depress
	2.250	3.517	11.650	24.050	36.450	48.850	61.250	42.650
Mu-req'd	1862.5	2742.5	7825.7	13685.6	17431.0	19153.9	19034.8	18292.5
Mu-prv'd	16568.2	17802.1	25854.3	27180.5	28259.0	28798.2	28798.2	28528.6

CAMBER / DEFLECTION (in) at Midspan (0.5 x L = 61.25 ft)

SERVICE I

	Release	Mult	Erection	Mult	Final
Prestress	4.257	1.80	7.663	2.20	9.366
Self Wt.	-1.601	1.85	-2.961	2.40	-3.841
Deck + Haunch			-2.006	2.30	-4.613
DL-Prec. (DC)			0.000	3.00	0.000



Program: LEAP®
CONSPAN®
Version: 08.01.00.10

Copyright © Bentley Systems, Inc. 1984 - 2008.
www.bentley.com
1-800-778-4277

By: A. Pott
Date: Jan/4/2010
CKD:
Date:

File Name: 76-21-125-21-124_U72C.csl

	Release	Mult	Erection	Mult	Final
Diaphragm			0.000	3.00	0.000
DL-Prec. (DW)			0.000	3.00	0.000
DL-Comp. (DC)			-0.023	3.00	-0.068
DL-Comp. (DW)			-0.108	3.00	-0.323
Total	2.657		2.566		0.520

Positive values indicate upward deflection.



DESIGN STATUS

Span:5, Beam:7

RELEASE STRESSES (ksi)

Limiting Stresses		
Compression	Tens with Reinf	Tens without Reinf
4.050	-0.624	-0.200

Computed Stresses							
	Trans	0.10L/0.90L	0.20L/0.80L	0.30L/0.70L	0.40L/0.60L	Midspan	Depress.
Location, ft	3.000	12.400	24.800	37.200	49.600	62.000	43.400
Precast-top	-0.199	-0.090	0.000	-0.013	0.007	0.059	-0.056
Bottom	3.621	3.595	3.498	3.499	3.474	3.427	3.531
As top, in2	0.000	0.000	0.000	0.000	0.000	0.000	0.000

FINAL STRESSES (ksi)

Limiting Stresses			
		Precast	Topping-Top
Final 1 (P/S+DL+LL)	Compression	5.400	4.320
Final 1	Tension	-0.570	-0.510
Final 2 (P/S+DL)	Compression	4.050	3.240
Final 3 (0.5(P/S+DL)+LL)	Compression	3.600	2.880

Computed Stresses								
POSITIVE MOMENT ENVELOPE : SERVICE I (Final 1)								
	Bearing	Trans	H/2	0.10L/0.90L	0.20L/0.80L	0.30L/0.70L	0.40L/0.60L	Midspan
Location, ft	0.000	2.250	3.517	11.650	24.050	36.450	48.850	61.250
Topping-top	0.011	0.050	0.072	0.191	0.318	0.387	0.404	0.378
Precast-top	-0.057	0.002	0.130	0.841	1.686	2.199	2.517	2.647
Bottom	0.822	2.902	2.732	1.861	0.779	0.147	-0.182	-0.242

Computed Stresses								
POSITIVE MOMENT ENVELOPE : SERVICE III (Final 1)								
	Bearing	Trans	H/2	0.10L/0.90L	0.20L/0.80L	0.30L/0.70L	0.40L/0.60L	Midspan
Topping-top	0.010	0.043	0.061	0.161	0.270	0.329	0.344	0.322
Precast-top	-0.058	-0.002	0.124	0.826	1.660	2.168	2.484	2.616
Bottom	0.827	2.924	2.762	1.943	0.914	0.310	-0.013	-0.084

Computed Stresses								
NEGATIVE MOMENT ENVELOPE : SERVICE I (Final 1)								
	Bearing	Trans	H/2	0.10L/0.90L	0.20L/0.80L	0.30L/0.70L	0.40L/0.60L	Midspan
Topping-top	-0.538	-0.481	-0.452	-0.283	-0.073	0.041	0.073	0.093
Precast-top	-0.346	-0.285	-0.153	0.585	1.474	2.012	2.337	2.492
Bottom	2.419	4.400	4.208	3.192	1.875	1.115	0.742	0.554



Program: LEAP®
CONSPAN®
Version: 08.01.00.10
File Name: 76-21-125-21-124 U72C.csl

Copyright © Bentley Systems, Inc. 1984 - 2008.
www.bentley.com
1-800-778-4277

By: A. Pott
Date: Jan/4/2010
CKD:
Date:

NEGATIVE MOMENT ENVELOPE : SERVICE III (Final 1)

	Bearing	Trans	H/2	0.10L/0.90L	0.20L/0.80L	0.30L/0.70L	0.40L/0.60L	Midspan
Topping-top	-0.456	-0.407	-0.383	-0.238	-0.059	0.042	0.074	0.094
Precast-top	-0.303	-0.245	-0.115	0.609	1.482	2.012	2.337	2.492
Bottom	2.180	4.192	4.012	3.066	1.834	1.113	0.741	0.553

POSITIVE MOMENT ENVELOPE : SERVICE I (Final 2)

	Bearing	Trans	H/2	0.10L/0.90L	0.20L/0.80L	0.30L/0.70L	0.40L/0.60L	Midspan
Topping-top	0.003	0.012	0.017	0.045	0.077	0.096	0.102	0.095
Precast-top	-0.062	-0.019	0.100	0.763	1.556	2.041	2.352	2.493
Bottom	0.847	3.011	2.886	2.270	1.453	0.961	0.663	0.547

NEGATIVE MOMENT ENVELOPE : SERVICE I (Final 2)

	Bearing	Trans	H/2	0.10L/0.90L	0.20L/0.80L	0.30L/0.70L	0.40L/0.60L	Midspan
Topping-top	-0.127	-0.112	-0.105	-0.059	-0.001	0.044	0.076	0.095
Precast-top	-0.130	-0.086	0.035	0.706	1.513	2.013	2.338	2.493
Bottom	1.225	3.361	3.228	2.562	1.671	1.106	0.735	0.547

POSITIVE MOMENT ENVELOPE : SERVICE I (Final 3)

	Bearing	Trans	H/2	0.10L/0.90L	0.20L/0.80L	0.30L/0.70L	0.40L/0.60L	Midspan
Topping-top	0.010	0.045	0.063	0.168	0.279	0.339	0.353	0.331
Precast-top	-0.026	0.011	0.080	0.460	0.908	1.179	1.340	1.400
Bottom	0.399	1.397	1.289	0.726	0.052	-0.333	-0.513	-0.516

NEGATIVE MOMENT ENVELOPE : SERVICE I (Final 3)

	Bearing	Trans	H/2	0.10L/0.90L	0.20L/0.80L	0.30L/0.70L	0.40L/0.60L	Midspan
Topping-top	-0.474	-0.425	-0.400	-0.254	-0.073	0.019	0.035	0.045
Precast-top	-0.281	-0.242	-0.170	0.232	0.717	1.005	1.168	1.245
Bottom	1.806	2.719	2.594	1.911	1.039	0.562	0.375	0.280

ULTIMATE MOMENT (k.ft)

STRENGTH I

	Trans	H/2	0.10L/0.90L	0.20L/0.80L	0.30L/0.70L	0.40L/0.60L	Midspan	Depress
Location, ft	2.250	3.517	11.650	24.050	36.450	48.850	61.250	42.650
Mu-req'd	1947.0	2873.3	8229.3	14425.5	18411.2	20278.2	20207.2	19344.7
Mu-prv'd	16568.2	17802.1	25854.3	27180.5	28259.0	28798.2	28798.2	28528.6

CAMBER / DEFLECTION (in) at Midspan (0.5 x L = 61.25 ft)

SERVICE I

	Release	Mult	Erection	Mult	Final
Prestress	4.257	1.80	7.663	2.20	9.366
Self Wt.	-1.601	1.85	-2.961	2.40	-3.841
Deck + Haunch			-2.006	2.30	-4.613
DL-Prec. (DC)			-0.359	3.00	-1.077



Program: LEAP®
CONSPAN®
Version: 08.01.00.10

Copyright © Bentley Systems, Inc. 1984 - 2008.
www.bentley.com
1-800-778-4277

By: A. Pott
Date: Jan/4/2010
CKD:
Date:

File Name: 76-21-125-21-124_U72C.csl

	Release	Mult	Erection	Mult	Final
Diaphragm			0.000	3.00	0.000
DL-Prec. (DW)			0.000	3.00	0.000
DL-Comp. (DC)			-0.023	3.00	-0.068
DL-Comp. (DW)			-0.108	3.00	-0.323
Total	2.657		2.207		-0.557

Positive values indicate upward deflection.



Program: LEAP®
CONSPAN®
Version: 08.01.00.10

Copyright © Bentley Systems, Inc. 1984 - 2008.
www.bentley.com
1-800-778-4277

By: A. Pott
Date: Jan/4/2010
CKD:
Date:

File Name: 76-21-125-21-124 U72C.csl

PROPERTIES

Span: 5, Beam: 2

PRECAST DATA:

Section Id	U72C					
Type	Open Box Beam					
Fing width	Top	131.000	in	Bot	54.000	in
thick	Top	6.350	in	Bot	8.100	in
Stems	No	2				
	Top	7.500	in			
	Bot	7.500	in			
Shear width		15.000	in			

GENERAL BRIDGE DATA:

Bridge Width	197.00	ft
Curb-to-curb	194.00	ft
Beam Spac. Lt./Rt	25.00/ 25.00	ft
Lane width	12.00	ft
Number of lanes	16	
Interior/Exterior	Interior	
Start Skew Angle	-34.00	degrees
End Skew Angle	-34.00	degrees

TOPPING DATA:

Deck	Thickness	8.000	in
Haunch:	Thickness	4.400	in
	Width	64.000	in
Effective	width	300.000	in (Art. 4.6.2.6.1)

GENERAL LOAD DATA:

Dead loads on precast:
UNITS: (Point: kips, Location: ft)
(Line: klf)

DC/DW	Type	Mag.	Loc.
DC	Line	0.500	-
DC	Line	-0.500	-



Program: LEAP®
CONSPAN®
Version: 08.01.00.10

Copyright © Bentley Systems, Inc. 1984 - 2008.
www.bentley.com
1-800-778-4277

By: A. Pott
Date: Jan/4/2010
CKD:
Date:

File Name: 76-21-125-21-124_U72C.csl

Dead loads on composite: See Project info for composite loads

GENERAL SPAN DATA:

Overall length	124.000	ft
Release length	124.000	ft
Design length	122.500	ft

KERN POINTS:

Upper	54.09	in
Lower	17.76	in

DISTRIBUTION FACTORS (Art. 4.6.2.2):

Live Negative Moment	Left Side	(2+ lanes loaded)	1.498	(Calculated)	(#)
Live Negative Moment	Right Side	(2+ lanes loaded)	1.498	(Calculated)	(#)
Live Negative Moment	Left Side	(1 lane loaded)	0.931	(Calculated)	(#)
Live Negative Moment	Right Side	(1 lane loaded)	0.931	(Calculated)	(#)
Live Positive Moment		(2+ lanes loaded)	1.498	(Calculated)	(#)
Live Positive Moment		(1 lane loaded)	0.931	(Calculated)	(#)
Live Shear		(2+ lanes loaded)	1.700	(Calculated)	(#)
Live Shear		(1 lane loaded)	1.056	(Calculated)	(#)

(#) Lever rule (C4.6.2.2.1)

Dead Loads and Pedestrian Load distributed based on Tributary Fraction

Pedestrian	0.127	(Calculated)
Comp. DC	0.127	(Calculated)
Comp. DW	0.127	(Calculated)

RESISTANCE FACTORS (Art. 5.5.4.2):

Flexure Reinforced	
Compression controlled sections	0.75
Tension controlled sections	0.90
Flexure Prestressed	
Compression controlled sections	0.75



Program: LEAP®
CONSPAN®
Version: 08.01.00.10

Copyright © Bentley Systems, Inc. 1984 - 2008.
www.bentley.com
1-800-778-4277

By: A. Pott
Date: Jan/4/2010
CKD:
Date:

File Name: 76-21-125-21-124 U72C.csl

Tension controlled sections	1.00
Shear	0.90

Span: 5, Beam: 2

SECTION PROPERTIES:

	PRECAST		COMPOSITE		
Area	1765.1	in2	4163.6	in2	#
Total Height	72.00	in	84.40	in	
Mom. of Inertia (Ixx)	1154250	in4	3135173	in4	#
Ht. of c.g.	35.84	in	61.13	in	#
Density	150.00	pcf	150.00	pcf	
Self-weight	1838.6	plf	4632.0	plf	
Mom. of Inertia (Iyy)	2057200.1	in4			
Poisson's Ratio	0.2				

(#) Of Total Section using $E_c/E_c = 0.8944$

Use transformed strand and rebar: Strand Only

Location,	ft	Bearing 0.00	Trans 2.25	H/2 3.52	0.10L 11.65	0.20L 24.05	0.30L 36.45	0.40L 48.85	Midspan 61.25
Precast:(At Release, using	Ec =	4980.8ksi)							
Area,	in2	1784.1	1840.9	1840.9	1843.0	1843.0	1843.0	1843.0	1843.0
Yb,	in	35.62	34.95	34.94	34.83	34.71	34.58	34.52	34.52
MI(Ixx),	in4	1162488	1187856	1188817	1196949	1207958	1220229	1226837	1226837
Composite:(At Final, using	Ec =	5751.4ksi)							
Area,	in2	4179.5	4227.1	4227.1	4228.8	4228.8	4228.8	4228.8	4228.8
Yb,	in	60.96	60.43	60.43	60.38	60.33	60.29	60.26	60.26
MI(Ixx),	in4	3169013	3272162	3273953	3290773	3309701	3329716	3340130	3340130

Span: 5, Beam: 2

STRESS LIMITS (Art. 5.9.4):

STRESS LIMITS AT RELEASE BEFORE LOSSES:

PRECAST



Program: LEAP®
CONSPAN®
Version: 08.01.00.10

Copyright © Bentley Systems, Inc. 1984 - 2008.
www.bentley.com
1-800-778-4277

By: A. Pott
Date: Jan/4/2010
CKD:
Date:

File Name: 76-21-125-21-124 U72C.csl

PRECAST			
Strength		6.75	ksi
Elasticity		4980.8	ksi
Max comp		4.05	ksi
Max tens		-0.20	ksi
Max tens	w/reinf	-0.62	ksi

STRESS LIMITS AT FINAL AFTER LOSSES:

	PRECAST		DECK	
Strength	9.00	ksi	7.20	ksi
Elasticity	5751.38	ksi	5144.19	ksi

STRESS LIMITS AT FINAL 1 (P/S + DL + LL):

	PRECAST		DECK	
Max comp	5.40	ksi	4.32	ksi

STRESS LIMITS AT FINAL 2 (P/S + DL):

	PRECAST		DECK	
Max comp	4.05	ksi	3.24	ksi

STRESS LIMITS AT FINAL 3 (50% P/S + 50% DL + LL):

	PRECAST		DECK	
Max comp	3.60	ksi	2.88	ksi

SERVICE III (Tension):

	PRECAST		DECK	
Max tens	-0.57	ksi	-0.51	ksi

Span: 5, Beam: 2

PRESTRESSED STEEL:



Program: LEAP®
CONSPAN®
Version: 08.01.00.10

Copyright © Bentley Systems, Inc. 1984 - 2008.
www.bentley.com
1-800-778-4277

By: A. Pott
Date: Jan/4/2010
CKD:
Date:

File Name: 76-21-125-21-124 U72C.csl

76 strands, 6/10-270K-LL, Low relaxation strands
Depressed at 0.35L (43.40 ft from member end)

END PATTERN (Ycg = 14.82 in):

15 @ 5.880 in	23 @ 2.250 in	2 @ 57.500 in	24 @ 4.060 in
2 @ 59.500 in	2 @ 61.500 in	2 @ 63.500 in	2 @ 65.500 in
2 @ 67.500 in	2 @ 69.500 in		

MID PATTERN (Ycg = 4.64 in):

(A) Draped:

2 @ 2.250 in	2 @ 4.250 in	2 @ 6.250 in	2 @ 8.250 in
2 @ 10.250 in	2 @ 12.250 in	2 @ 14.250 in	

(B) Straight:

15 @ 5.880 in	23 @ 2.250 in	24 @ 4.060 in
---------------	---------------	---------------

SHIELDING AND REDUCED INITIAL PULLS:

Group	Strands	End	Heights	Mid	End	Shielding	Mid	Initial Frac	Pull Pull/Str
1	2	5.880	in	5.880	in	8.00	ft	75.0 %	43.9

Check for Art. 5.11.4.3 (debond termination distances): OK

Strand Diameter	0.600	in
Strand Area	0.217	in ²
Total Strand Area	16.492	in ²
Trans. Len, bonded	3.000	ft
Trans. Len, debonded	3.000	ft
Dev. Len, bonded	11.839	ft
Dev. Len, debonded	14.799	ft
Holddown Force	64.900	kips
Tensile Strength(fpu)	270.0	ksi
Initial Prestress = 0.75fpu	202.5	ksi
Initial Pull	3339.6	kips
Beam Shrtng (PL/AE)	0.542	in

REINFORCING STEEL:

Tension	/Shear	steel:
fy	60.0	ksi
Es	29000	ksi
fs	24.0	ksi



Program: LEAP®
CONSPAN®
Version: 08.01.00.10

Copyright © Bentley Systems, Inc. 1984 - 2008.
www.bentley.com
1-800-778-4277

By: A. Pott
Date: Jan/4/2010
CKD:
Date:

File Name: 76-21-125-21-124_U72C.csl

LOSSES

Note: Values are calculated at Midspan

Str. area	16.4920	in2
Ycg	4.64	in
P_init	3339.6	kips
Ecc	31.20	in
Days to release	0.75	
Rel. Humid.(RH)	60.0	%
Es	28500.0	ksi
Eci	4981	ksi

AASHTO LOSSES

Elastic Shortening ** 18.50 ksi (Eq 5.9.5.2.3a-1), (fcgp= 3.233 ksi)

Elastic Gains		Gains	Adjustment
due to Precast Loads		-7.59 ksi	0.00 ksi
due to Composite Loads		-1.22 ksi	0.00 ksi
due to Live Loads		-2.89 ksi	0.00 ksi

Time Dependent Losses (Approximate Method (Art.5.9.5.3))

	Initial	Final	
Steel relaxation	0.00 ksi	2.40 ksi	(Eq 5.9.5.3-1)
Concrete shrinkage	0.00 ksi	8.52 ksi	(Eq 5.9.5.3-1)
Concrete creep	0.00 ksi	13.43 ksi	(Eq 5.9.5.3-1)
Sub-total	18.50 ksi	12.65 ksi	(6.25 %)
Total Prestress Losses		31.15 ksi	(15.38 %)

Prestressing Stress Limit Check (Table 5.9.3.1)

initial fpi = 202.5 ksi < 0.75 fpu, OK

initial fpe = 171.4 ksi < 0.80 fpy, OK

** Since the transformed section properties option has been selected, even though ES losses have been calculated explicitly here, they are not included as a part of stress calculations.

Please see theory section for complete explanation.



Program: LEAP®
CONSPAN®
Version: 08.01.00.10

Copyright © Bentley Systems, Inc. 1984 - 2008.
www.bentley.com
1-800-778-4277

By: A. Pott
Date: Jan/4/2010
CKD:
Date:

File Name: 76-21-125-21-124_U72C.csl

DESIGN STATUS

Span:5, Beam:3

RELEASE STRESSES (ksi)

Limiting Stresses

Compression	Tens with Reinf	Tens without Reinf
4.050	-0.624	-0.200

Computed Stresses

	Trans	0.10L/0.90L	0.20L/0.80L	0.30L/0.70L	0.40L/0.60L	Midspan	Depress.
Location, ft	3.000	12.400	24.800	37.200	49.600	62.000	43.400
Precast-top	-0.202	-0.156	-0.137	-0.157	-0.120	-0.068	-0.183
Bottom	3.361	3.566	3.837	3.966	3.926	3.879	3.983
As_top, in2	0.876	0.000	0.000	0.000	0.000	0.000	0.000

FINAL STRESSES (ksi)

Limiting Stresses

	Compression	Precast	Topping-Top
Final 1 (P/S+DL+LL)	Compression	5.400	4.320
Final 1	Tension	-0.570	-0.510
Final 2 (P/S+DL)	Compression	4.050	3.240
Final 3 (0.5(P/S+DL)+LL)	Compression	3.600	2.880

Computed Stresses

POSITIVE MOMENT ENVELOPE : SERVICE I (Final 1)

	Bearing	Trans	H/2	0.10L/0.90L	0.20L/0.80L	0.30L/0.70L	0.40L/0.60L	Midspan
Location, ft	0.000	2.250	3.517	11.650	24.050	36.450	48.850	61.250
Topping-top	0.011	0.051	0.072	0.190	0.317	0.386	0.403	0.377
Precast-top	-0.058	0.007	0.141	0.811	1.611	2.133	2.474	2.607
Bottom	0.754	2.643	2.467	1.787	1.023	0.500	0.151	0.089

POSITIVE MOMENT ENVELOPE : SERVICE III (Final 1)

	Bearing	Trans	H/2	0.10L/0.90L	0.20L/0.80L	0.30L/0.70L	0.40L/0.60L	Midspan
Topping-top	0.010	0.043	0.061	0.161	0.269	0.328	0.343	0.321
Precast-top	-0.059	0.003	0.135	0.795	1.585	2.102	2.441	2.576
Bottom	0.759	2.665	2.498	1.869	1.157	0.662	0.318	0.245

NEGATIVE MOMENT ENVELOPE : SERVICE I (Final 1)

	Bearing	Trans	H/2	0.10L/0.90L	0.20L/0.80L	0.30L/0.70L	0.40L/0.60L	Midspan
Topping-top	-0.538	-0.481	-0.453	-0.283	-0.073	0.041	0.073	0.093
Precast-top	-0.347	-0.279	-0.142	0.555	1.399	1.945	2.294	2.452
Bottom	2.352	4.146	3.949	3.118	2.112	1.459	1.067	0.878

306



Program: LEAP@
CONSPAN@
Version: 08.01.00.10

Copyright © Bentley Systems, Inc. 1984 - 2008.
www.bentley.com
1-800-778-4277

By: A. Pott
Date: Jan/4/2010
CKD:
Date:

File Name: 76-21-125-21-124 U72C.csl

NEGATIVE MOMENT ENVELOPE : SERVICE III (Final 1)

	Bearing	Trans	H/2	0.10L/0.90L	0.20L/0.80L	0.30L/0.70L	0.40L/0.60L	Midspan
Topping-top	-0.456	-0.407	-0.383	-0.238	-0.059	0.042	0.074	0.093
Precast-top	-0.304	-0.239	-0.104	0.579	1.407	1.945	2.294	2.452
Bottom	2.113	3.938	3.752	2.992	2.072	1.458	1.066	0.877

POSITIVE MOMENT ENVELOPE : SERVICE I (Final 2)

	Bearing	Trans	H/2	0.10L/0.90L	0.20L/0.80L	0.30L/0.70L	0.40L/0.60L	Midspan
Topping-top	0.003	0.012	0.017	0.045	0.077	0.096	0.102	0.095
Precast-top	-0.063	-0.014	0.111	0.732	1.481	1.975	2.310	2.453
Bottom	0.779	2.752	2.622	2.196	1.693	1.307	0.988	0.872

NEGATIVE MOMENT ENVELOPE : SERVICE I (Final 2)

	Bearing	Trans	H/2	0.10L/0.90L	0.20L/0.80L	0.30L/0.70L	0.40L/0.60L	Midspan
Topping-top	-0.127	-0.112	-0.105	-0.059	-0.001	0.044	0.076	0.095
Precast-top	-0.131	-0.081	0.046	0.676	1.438	1.947	2.295	2.453
Bottom	1.157	3.103	2.965	2.488	1.910	1.451	1.060	0.872

POSITIVE MOMENT ENVELOPE : SERVICE I (Final 3)

	Bearing	Trans	H/2	0.10L/0.90L	0.20L/0.80L	0.30L/0.70L	0.40L/0.60L	Midspan
Topping-top	0.010	0.045	0.063	0.168	0.278	0.338	0.352	0.330
Precast-top	-0.027	0.014	0.085	0.445	0.871	1.146	1.319	1.380
Bottom	0.365	1.267	1.156	0.689	0.177	-0.153	-0.343	-0.347

NEGATIVE MOMENT ENVELOPE : SERVICE I (Final 3)

	Bearing	Trans	H/2	0.10L/0.90L	0.20L/0.80L	0.30L/0.70L	0.40L/0.60L	Midspan
Topping-top	-0.474	-0.425	-0.400	-0.254	-0.073	0.019	0.035	0.045
Precast-top	-0.282	-0.239	-0.164	0.217	0.680	0.972	1.146	1.225
Bottom	1.774	2.595	2.466	1.874	1.157	0.734	0.537	0.442

ULTIMATE MOMENT (k.ft)

STRENGTH I

Location, ft	Trans	H/2	0.10L/0.90L	0.20L/0.80L	0.30L/0.70L	0.40L/0.60L	Midspan	Depress
	2.250	3.517	11.650	24.050	36.450	48.850	61.250	42.650
Mu-req'd	1963.9	2899.4	8310.0	14573.5	18607.2	20503.1	20441.6	19555.2
Mu-prv'd	15218.0	16366.2	24900.4	28745.8	31225.7	31772.2	31772.2	31498.9

CAMBER / DEFLECTION (in) at Midspan (0.5 x L = 61.25 ft)

SERVICE I

	Release	Mult	Erection	Mult	Final
Prestress	4.650	1.80	8.369	2.20	10.229
Self Wt.	-1.591	1.85	-2.943	2.40	-3.817
Deck + Haunch			-1.993	2.30	-4.585
DL-Prec. (DC)			-0.428	3.00	-1.284



Program: LEAP®
CONSPAN®
Version: 08.01.00.10

Copyright © Bentley Systems, Inc. 1984 - 2008.
www.bentley.com
1-800-778-4277

By: A. Pott
Date: Jan/4/2010
CKD:
Date:

File Name: 76-21-125-21-124_U72C.csl

	Release	Mult	Erection	Mult	Final
Diaphragm			0.000	3.00	0.000
DL-Prec. (DW)			0.000	3.00	0.000
DL-Comp. (DC)			-0.022	3.00	-0.067
DL-Comp. (DW)			-0.106	3.00	-0.318
Total	3.059		2.877		0.158

Positive values indicate upward deflection.



Program: LEAP®
CONSPAN®
Version: 08.01.00.10

Copyright © Bentley Systems, Inc. 1984 - 2008.
www.bentley.com
1-800-778-4277

By: A. Pott
Date: Jan/4/2010
CKD:
Date:

File Name: 76-21-125-21-124 U72C.csl

PROPERTIES

Span: 5, Beam: 3

PRECAST DATA:

Section Id	U72C					
Type	Open Box Beam					
Fing width	Top	131.000	in	Bot	54.000	in
thick	Top	6.350	in	Bot	8.100	in
Stems	No	2				
	Top	7.500	in			
	Bot	7.500	in			
Shear width		15.000	in			

GENERAL BRIDGE DATA:

Bridge Width	197.00	ft
Curb-to-curb	194.00	ft
Beam Spac. Lt./Rt	25.00/ 25.00	ft
Lane width	12.00	ft
Number of lanes	16	
Interior/Exterior	Interior	
Start Skew Angle	-34.00	degrees
End Skew Angle	-34.00	degrees

TOPPING DATA:

Deck	Thickness	8.000	in
Haunch:	Thickness	4.400	in
	Width	64.000	in
Effective	width	300.000	in (Art. 4.6.2.6.1)

GENERAL LOAD DATA:

Dead loads on precast:
UNITS: (Point: kips, Location: ft)
(Line: klf)

DC/DW	Type	Mag.	Loc.
DC	Line	0.600	-



Program: LEAP®
CONSPAN®
Version: 08.01.00.10

Copyright © Bentley Systems, Inc. 1984 - 2008.
www.bentley.com
1-800-778-4277

By: A. Pott
Date: Jan/4/2010
CKD:
Date:

File Name: 76-21-125-21-124_U72C.csl

Dead loads on composite: See Project info for composite loads

GENERAL SPAN DATA:

Overall length	124.000	ft
Release length	124.000	ft
Design length	122.500	ft

KERN POINTS:

Upper	54.09	in
Lower	17.76	in

DISTRIBUTION FACTORS (Art. 4.6.2.2):

Live Negative Moment	Left Side	(2+ lanes loaded)	1.498	(Calculated)	(#)
Live Negative Moment	Right Side	(2+ lanes loaded)	1.498	(Calculated)	(#)
Live Negative Moment	Left Side	(1 lane loaded)	0.931	(Calculated)	(#)
Live Negative Moment	Right Side	(1 lane loaded)	0.931	(Calculated)	(#)
Live Positive Moment		(2+ lanes loaded)	1.498	(Calculated)	(#)
Live Positive Moment		(1 lane loaded)	0.931	(Calculated)	(#)
Live Shear		(2+ lanes loaded)	1.700	(Calculated)	(#)
Live Shear		(1 lane loaded)	1.056	(Calculated)	(#)

(#) Lever rule (C4.6.2.2.1)

Dead Loads and Pedestrian Load distributed based on Tributary Fraction

Pedestrian	0.127	(Calculated)
Comp. DC	0.127	(Calculated)
Comp. DW	0.127	(Calculated)

RESISTANCE FACTORS (Art. 5.5.4.2):

Flexure Reinforced	
Compression controlled sections	0.75
Tension controlled sections	0.90
Flexure Prestressed	
Compression controlled sections	0.75



Program: LEAP®
CONSPAN®
Version: 08.01.00.10

Copyright © Bentley Systems, Inc. 1984 - 2008.
www.bentley.com
1-800-778-4277

By: A. Pott
Date: Jan/4/2010
CKD:
Date:

File Name: 76-21-125-21-124_U72C.csl

Tension controlled sections	1.00
Shear	0.90

Span: 5, Beam: 3

SECTION PROPERTIES:

	PRECAST		COMPOSITE		
Area	1765.1	in2	4163.6	in2	#
Total Height	72.00	in	84.40	in	
Mom. of Inertia (Ixx)	1154250	in4	3135173	in4	#
Ht. of c.g.	35.84	in	61.13	in	#
Density	150.00	pcf	150.00	pcf	
Self-weight	1838.6	plf	4632.0	plf	
Mom. of Inertia (Iyy)	2057200.1	in4			
Poisson's Ratio	0.2				

(#) Of Total Section using $E_c/E_c = 0.8944$

Use transformed strand and rebar: Strand Only

Location,	ft	Bearing 0.00	Trans 2.25	H/2 3.52	0.10L 11.65	0.20L 24.05	0.30L 36.45	0.40L 48.85	Midspan 61.25
Precast:(At Release, using	Ec =	4980.8ksi)							
Area,	in2	1782.5	1834.8	1834.8	1840.9	1848.2	1851.2	1851.2	1851.2
Yb,	in	35.63	35.01	35.00	34.82	34.60	34.44	34.39	34.39
MI(Ixx),	in4	1162066	1186135	1187003	1198878	1215094	1228654	1234541	1234541
Composite:(At Final, using	Ec =	5751.4ksi)							
Area,	in2	4178.2	4222.0	4222.0	4227.1	4233.2	4235.7	4235.7	4235.7
Yb,	in	60.97	60.48	60.48	60.38	60.26	60.19	60.17	60.17
MI(Ixx),	in4	3166721	3262884	3264488	3292014	3327326	3352719	3361990	3361990

Span: 5, Beam: 3

STRESS LIMITS (Art. 5.9.4):

STRESS LIMITS AT RELEASE BEFORE LOSSES:

PRECAST



Program: LEAP®
CONSPAN®
Version: 08.01.00.10

Copyright © Bentley Systems, Inc. 1984 - 2008.
www.bentley.com
1-800-778-4277

By: A. Pott
Date: Jan/4/2010
CKD:
Date:

File Name: 76-21-125-21-124_U72C.csl

PRECAST			
Strength		6.75	ksi
Elasticity		4980.8	ksi
Max comp		4.05	ksi
Max tens		-0.20	ksi
Max tens	w/reinf	-0.62	ksi

STRESS LIMITS AT FINAL AFTER LOSSES:

	PRECAST		DECK	
Strength	9.00	ksi	7.20	ksi
Elasticity	5751.38	ksi	5144.19	ksi

STRESS LIMITS AT FINAL 1 (P/S + DL + LL):

	PRECAST		DECK	
Max comp	5.40	ksi	4.32	ksi

STRESS LIMITS AT FINAL 2 (P/S + DL):

	PRECAST		DECK	
Max comp	4.05	ksi	3.24	ksi

STRESS LIMITS AT FINAL 3 (50% P/S + 50% DL + LL):

	PRECAST		DECK	
Max comp	3.60	ksi	2.88	ksi

SERVICE III (Tension):

	PRECAST		DECK	
Max tens	-0.57	ksi	-0.51	ksi

Span: 5, Beam: 3

PRESTRESSED STEEL:



Program: LEAP®
CONSPAN®
Version: 08.01.00.10

Copyright © Bentley Systems, Inc. 1984 - 2008.
www.bentley.com
1-800-778-4277

By: A. Pott
Date: Jan/4/2010
CKD:
Date:

File Name: 76-21-125-21-124_U72C.csl

84 strands, 6/10-270K-LL, Low relaxation strands
Depressed at 0.35L (43.40 ft from member end)

END PATTERN (Ycg = 12.74 in):

25 @ 5.880 in	23 @ 2.250 in	2 @ 59.500 in	2 @ 61.500 in
2 @ 63.500 in	2 @ 65.500 in	24 @ 4.060 in	2 @ 67.500 in
2 @ 69.500 in			

MID PATTERN (Ycg = 4.56 in):

(A) Draped:

2 @ 2.250 in	2 @ 4.250 in	2 @ 6.250 in	2 @ 8.250 in
2 @ 10.250 in	2 @ 12.250 in		

(B) Straight:

25 @ 5.880 in	23 @ 2.250 in	24 @ 4.060 in
---------------	---------------	---------------

SHIELDING AND REDUCED INITIAL PULLS:

Group	Strands	End	Heights	Mid	End	Shielding	Mid	Initial Frac	Pull
1	2	5.880 in		5.880 in	16.00 ft		0.00 ft	75.0 %	43.9
28	2	2.250 in		2.250 in	8.00 ft		0.00 ft	75.0 %	43.9
29	2	2.250 in		2.250 in	8.00 ft		0.00 ft	75.0 %	43.9
30	2	2.250 in		2.250 in	8.00 ft		0.00 ft	75.0 %	43.9
31	1	2.250 in		2.250 in	16.00 ft		0.00 ft	75.0 %	43.9
40	2	5.880 in		5.880 in	24.00 ft		0.00 ft	75.0 %	43.9
41	2	5.880 in		5.880 in	24.00 ft		0.00 ft	75.0 %	43.9
42	2	5.880 in		5.880 in	16.00 ft		0.00 ft	75.0 %	43.9
43	1	5.880 in		5.880 in	16.00 ft		0.00 ft	75.0 %	43.9

Check for Art. 5.11.4.3 (debond termination distances): OK

Strand Diameter	0.600 in
Strand Area	0.217 in ²
Total Strand Area	18.228 in ²
Trans. Len, bonded	3.000 ft
Trans. Len, debonded	3.000 ft
Dev. Len, bonded	11.888 ft
Dev. Len, debonded	14.860 ft
Holddown Force	57.619 kips
Tensile Strength(fpu)	270.0 ksi
Initial Prestress = 0.75fpu	202.5 ksi
Initial Pull	3691.2 kips
Beam Shrtng (PL/AE)	0.601 in



Program: LEAP®
CONSPAN®
Version: 08.01.00.10
File Name: 76-21-125-21-124 U72C.csl

Copyright © Bentley Systems, Inc. 1984 - 2008.
www.bentley.com
1-800-778-4277

By: A. Pott
Date: Jan/4/2010
CKD:
Date:

REINFORCING STEEL:

Tension /Shear steel:		
fy	60.0	ksi
Es	29000	ksi
fs	24.0	ksi

LOSSES

Note: Values are calculated at Midspan

Str. area	18.2280	in2
Ycg	4.56	in
P_init	3691.2	kips
Ecc	31.28	in
Days to release	0.75	
Rel. Humid.(RH)	60.0	%
Es	28500.0	ksi
Eci	4981	ksi

AASHTO LOSSES

Elastic Shortening ** 20.90 ksi (Eq 5.9.5.2.3a-1), (fcgp= 3.652 ksi)

	Elastic Gains	Gains	Adjustment
due to Precast Loads		-9.14 ksi	0.00 ksi
due to Composite Loads		-1.21 ksi	0.00 ksi
due to Live Loads		-2.87 ksi	0.00 ksi

Time Dependent Losses (Approximate Method (Art.5.9.5.3))

	Initial	Final	
Steel relaxation	0.00 ksi	2.40 ksi	(Eq 5.9.5.3-1)
Concrete shrinkage	0.00 ksi	8.52 ksi	(Eq 5.9.5.3-1)
Concrete creep	0.00 ksi	14.84 ksi	(Eq 5.9.5.3-1)
Sub-total	20.90 ksi	12.53 ksi	(6.19 %)
Total Prestress Losses		33.43 ksi	(16.51 %)

Prestressing Stress Limit Check (Table 5.9.3.1)

initial fpi = 202.5 ksi < 0.75 fpu, OK
initial fpe = 169.1 ksi < 0.80 fpy, OK



Colorado DOT
4201 E. Arkansas Ave. Denver CO 80222

Sheet: DS-7
Job No: **BR R600-297**

Program: LEAP®
CONSPAN®
Version: 08.01.00.10

Copyright © Bentley Systems, Inc. 1984 - 2008.
www.bentley.com
1-800-778-4277

By: A. Pott
Date: Jan/4/2010
CKD:
Date:

File Name: 76-21-125-21-124_U72C.csl

** Since the transformed section properties option has been selected, even though ES losses have been calculated explicitly here, they are not included as a part of stress calculations. Please see theory section for complete explanation.



DESIGN STATUS

Span:2, Beam: ~~ALL~~
24

RELEASE STRESSES (ksi)

Limiting Stresses		
Compression	Tens with Reinf	Tens without Reinf
4.050	-0.624	-0.200

Computed Stresses							
	Trans	0.10L/0.90L	0.20L/0.80L	0.30L/0.70L	0.40L/0.60L	Midspan	Depress.
Location, ft	3.000	2.000	4.000	6.000	8.000	10.000	7.000
Precast-top	0.282	0.189	0.287	0.293	0.298	0.299	0.296
Bottom	0.311	0.207	0.307	0.300	0.296	0.294	0.297
As_top, in2	0.000	0.000	0.000	0.000	0.000	0.000	0.000

FINAL STRESSES (ksi)

Limiting Stresses			
		Precast	Topping-Top
Final 1 (P/S+DL+LL)	Compression	5.400	4.320
Final 1	Tension	-0.570	-0.510
Final 2 (P/S+DL)	Compression	4.050	3.240
Final 3 (0.5(P/S+DL)+LL)	Compression	3.600	2.880

Computed Stresses									
POSITIVE MOMENT ENVELOPE : SERVICE I (Final 1)									
	Bearing	Trans	H/2	0.10L/0.90L	0.20L/0.80L	0.30L/0.70L	0.40L/0.60L	Midspan	
Location, ft	0.000	2.500	3.517	1.500	3.500	5.500	7.500	9.500	
Topping-top	-0.091	-0.033	-0.000	-0.033	-0.029	-0.028	-0.031	-0.037	
Precast-top	-0.006	0.266	0.247	0.171	0.280	0.297	0.306	0.307	
Bottom	0.319	0.368	0.307	0.279	0.345	0.326	0.324	0.338	

POSITIVE MOMENT ENVELOPE : SERVICE III (Final 1)									
	Bearing	Trans	H/2	0.10L/0.90L	0.20L/0.80L	0.30L/0.70L	0.40L/0.60L	Midspan	
Topping-top	-0.029	-0.036	-0.000	-0.035	-0.033	-0.034	-0.037	-0.043	
Precast-top	0.027	0.264	0.247	0.170	0.277	0.294	0.303	0.303	
Bottom	0.136	0.377	0.307	0.287	0.358	0.343	0.342	0.357	

NEGATIVE MOMENT ENVELOPE : SERVICE I (Final 1)									
	Bearing	Trans	H/2	0.10L/0.90L	0.20L/0.80L	0.30L/0.70L	0.40L/0.60L	Midspan	
Topping-top	-0.431	-0.379	-0.000	-0.399	-0.360	-0.322	-0.270	-0.252	
Precast-top	-0.184	0.085	0.247	-0.021	0.106	0.143	0.181	0.194	
Bottom	1.317	1.381	0.307	1.352	1.315	1.186	1.023	0.968	



NEGATIVE MOMENT ENVELOPE : SERVICE III (Final 1)

	Bearing	Trans	H/2	0.10L/0.90L	0.20L/0.80L	0.30L/0.70L	0.40L/0.60L	Midspan
Topping-top	-0.365	-0.322	-0.000	-0.339	-0.306	-0.274	-0.231	-0.216
Precast-top	-0.149	0.115	0.247	0.011	0.134	0.168	0.201	0.213
Bottom	1.124	1.214	0.307	1.175	1.157	1.046	0.909	0.861

POSITIVE MOMENT ENVELOPE : SERVICE I (Final 2)

	Bearing	Trans	H/2	0.10L/0.90L	0.20L/0.80L	0.30L/0.70L	0.40L/0.60L	Midspan
Topping-top	-0.104	-0.049	-0.000	-0.046	-0.051	-0.057	-0.063	-0.069
Precast-top	-0.013	0.258	0.247	0.164	0.268	0.282	0.290	0.290
Bottom	0.356	0.414	0.307	0.317	0.411	0.410	0.417	0.432

NEGATIVE MOMENT ENVELOPE : SERVICE I (Final 2)

	Bearing	Trans	H/2	0.10L/0.90L	0.20L/0.80L	0.30L/0.70L	0.40L/0.60L	Midspan
Topping-top	-0.104	-0.094	-0.000	-0.098	-0.090	-0.083	-0.076	-0.069
Precast-top	-0.013	0.234	0.247	0.137	0.248	0.269	0.283	0.290
Bottom	0.356	0.546	0.307	0.469	0.524	0.485	0.455	0.432

POSITIVE MOMENT ENVELOPE : SERVICE I (Final 3)

	Bearing	Trans	H/2	0.10L/0.90L	0.20L/0.80L	0.30L/0.70L	0.40L/0.60L	Midspan
Topping-top	-0.039	-0.009	-0.000	-0.010	-0.003	0.000	0.000	-0.002
Precast-top	0.000	0.137	0.124	0.089	0.146	0.156	0.161	0.162
Bottom	0.141	0.161	0.154	0.120	0.140	0.121	0.115	0.122

NEGATIVE MOMENT ENVELOPE : SERVICE I (Final 3)

	Bearing	Trans	H/2	0.10L/0.90L	0.20L/0.80L	0.30L/0.70L	0.40L/0.60L	Midspan
Topping-top	-0.379	-0.332	-0.000	-0.350	-0.315	-0.281	-0.232	-0.218
Precast-top	-0.177	-0.032	0.124	-0.089	-0.018	0.009	0.040	0.049
Bottom	1.139	1.108	0.154	1.117	1.053	0.944	0.796	0.753

ULTIMATE MOMENT (k.ft)

STRENGTH I

	Trans	H/2	0.10L/0.90L	0.20L/0.80L	0.30L/0.70L	0.40L/0.60L	Midspan	Depress
Location, ft	2.500	3.517	1.500	3.500	5.500	7.500	9.500	6.500
Mu-req'd	41.6	0.0	-35.3	201.9	349.1	402.5	363.7	375.8
Mu-prv'd	2073.6	2178.3	1384.6	2176.5	2382.3	2587.8	2793.2	2485.1

CAMBER / DEFLECTION (in) at Midspan (0.5 x L = 9.50 ft)

SERVICE I

	Release	Mult	Erection	Mult	Final
Prestress	0.001	1.80	0.002	2.20	0.003
Self Wt.	-0.001	1.85	-0.002	2.40	-0.003
Deck + Haunch			-0.001	2.30	-0.003
DL-Prec. (DC)			0.000	3.00	0.000



Program: LEAP®
CONSPAN®
Version: 08.01.00.10

Copyright © Bentley Systems, Inc. 1984 - 2008.
www.bentley.com
1-800-778-4277

By: A. Pott
Date: Jan/4/2010
CKD:
Date:

File Name: 76-21-125-21-124 U72C.csl

	Release	Mult	Erection	Mult	Final
Diaphragm			0.000	3.00	0.000
DL-Prec. (DW)			0.000	3.00	0.000
DL-Comp. (DC)			0.001	3.00	0.002
DL-Comp. (DW)			0.003	3.00	0.010
Total	0.000		0.003		0.010

Positive values indicate upward deflection.



Program: LEAP®
CONSPAN®
Version: 08.01.00.10

Copyright © Bentley Systems, Inc. 1984 - 2008.
www.bentley.com
1-800-778-4277

By: A. Pott
Date: Jan/4/2010
CKD:
Date:

File Name: 76-21-125-21-124 U72C.csl

PROPERTIES

Span: 2, Beam: 2

PRECAST DATA:

Section Id	U72C					
Type	Open Box Beam					
Fing width	Top	131.000	in	Bot	54.000	in
thick	Top	6.350	in	Bot	8.100	in
Stems	No	2				
	Top	7.500	in			
	Bot	7.500	in			
Shear width		15.000	in			

GENERAL BRIDGE DATA:

Bridge Width	197.00	ft
Curb-to-curb	194.00	ft
Beam Spac. Lt./Rt	25.00/ 25.00	ft
Lane width	12.00	ft
Number of lanes	16	
Interior/Exterior	Interior	
Start Skew Angle	-34.00	degrees
End Skew Angle	-34.00	degrees

TOPPING DATA:

Deck	Thickness	8.000	in
Haunch:			
	Thickness	4.400	in
	Width	64.000	in
Effective	width	300.000	in (Art. 4.6.2.6.1)

GENERAL LOAD DATA:

Dead loads on precast:
UNITS: (Point: kips, Location: ft)
(Line: klf)

DC/DW	Type	Mag.	Loc.
DC	Line	-0.500	-
DC	Line	0.500	-



Program: LEAP®
CONSPAN®
Version: 08.01.00.10

Copyright © Bentley Systems, Inc. 1984 - 2008.
www.bentley.com
1-800-778-4277

By: A. Pott
Date: Jan/4/2010
CKD:
Date:

File Name: 76-21-125-21-124 U72C.csl

Dead loads on composite: See Project info for composite loads

GENERAL SPAN DATA:

Overall length	20.000	ft
Release length	20.000	ft
Design length	19.000	ft

KERN POINTS:

Upper	54.09	in
Lower	17.76	in

DISTRIBUTION FACTORS (Art. 4.6.2.2):

Live Negative Moment	Left Side	(2+ lanes loaded)	1.498	(Calculated)	(#)
Live Negative Moment	Right Side	(2+ lanes loaded)	1.498	(Calculated)	(#)
Live Negative Moment	Left Side	(1 lane loaded)	0.931	(Calculated)	(#)
Live Negative Moment	Right Side	(1 lane loaded)	0.931	(Calculated)	(#)
Live Positive Moment		(2+ lanes loaded)	1.498	(Calculated)	(#)
Live Positive Moment		(1 lane loaded)	0.931	(Calculated)	(#)
Live Shear		(2+ lanes loaded)	1.700	(Calculated)	(#)
Live Shear		(1 lane loaded)	1.056	(Calculated)	(#)

(#) Lever rule (C4.6.2.2.1)

Dead Loads and Pedestrian Load distributed based on Tributary Fraction

Pedestrian	0.127	(Calculated)
Comp. DC	0.127	(Calculated)
Comp. DW	0.127	(Calculated)

RESISTANCE FACTORS (Art. 5.5.4.2):

Flexure Reinforced	
Compression controlled sections	0.75
Tension controlled sections	0.90
Flexure Prestressed	
Compression controlled sections	0.75



Program: LEAP®
CONSPAN®
Version: 08.01.00.10

Copyright © Bentley Systems, Inc. 1984 - 2008.
www.bentley.com
1-800-778-4277

By: A. Pott
Date: Jan/4/2010
CKD:
Date:

File Name: 76-21-125-21-124 U72C.csl

Tension controlled sections	1.00
Shear	0.90

Span: 2, Beam: 2

SECTION PROPERTIES:

	PRECAST		COMPOSITE		
Area	1765.1	in2	4163.6	in2	#
Total Height	72.00	in	84.40	in	
Mom. of Inertia (Ixx)	1154250	in4	3135173	in4	#
Ht. of c.g.	35.84	in	61.13	in	#
Density	150.00	pcf	150.00	pcf	
Self-weight	1838.6	plf	4632.0	plf	
Mom. of Inertia (Iyy)	2057200.1	in4			
Poisson's Ratio	0.2				

(#) Of Total Section using $E_c/E_c = 0.8944$

Use transformed strand and rebar: Strand Only

Location,	ft	Bearing	Trans	H/2	0.10L	0.20L	0.30L	0.40L	Midspan
		0.00	2.50	3.52	1.50	3.50	5.50	7.50	9.50
Precast:(At Release, using	Ec =	4980.8ksi)							
Area,	in2	1767.1	1777.4	1777.4	1773.3	1777.4	1777.4	1777.4	1777.4
Yb,	in	35.84	35.83	35.83	35.83	35.83	35.83	35.83	35.83
MI(Ixx),	in4	1154258	1154297	1154297	1154281	1154297	1154297	1154297	1154297
Composite:(At Final, using	Ec =	5751.4ksi)							
Area,	in2	4165.3	4173.9	4173.9	4170.5	4173.9	4173.9	4173.9	4173.9
Yb,	in	61.12	61.07	61.07	61.09	61.07	61.07	61.07	61.07
MI(Ixx),	in4	3136448	3142807	3142807	3140267	3142807	3142807	3142807	3142807

Span: 2, Beam: 2

STRESS LIMITS (Art. 5.9.4):

STRESS LIMITS AT RELEASE BEFORE LOSSES:

PRECAST



Program: LEAP®
CONSPAN®
Version: 08.01.00.10

Copyright © Bentley Systems, Inc. 1984 - 2008.
www.bentley.com
1-800-778-4277

By: A. Pott
Date: Jan/4/2010
CKD:
Date:

File Name: 76-21-125-21-124 U72C.csl

PRECAST			
Strength	6.75	ksi	
Elasticity	4980.8	ksi	
Max comp	4.05	ksi	
Max tens	-0.20	ksi	
Max tens, w/reinf	-0.62	ksi	

STRESS LIMITS AT FINAL AFTER LOSSES:

	PRECAST		DECK	
Strength	9.00	ksi	7.20	ksi
Elasticity	5751.38	ksi	5144.19	ksi

STRESS LIMITS AT FINAL 1 (P/S + DL + LL):

	PRECAST		DECK	
Max comp	5.40	ksi	4.32	ksi

STRESS LIMITS AT FINAL 2 (P/S + DL):

	PRECAST		DECK	
Max comp	4.05	ksi	3.24	ksi

STRESS LIMITS AT FINAL 3 (50% P/S + 50% DL + LL):

	PRECAST		DECK	
Max comp	3.60	ksi	2.88	ksi

SERVICE III (Tension):

	PRECAST		DECK	
Max tens	-0.57	ksi	-0.51	ksi

Span: 2, Beam: 2

PRESTRESSED STEEL:



Program: LEAP®
CONSPAN®
Version: 08.01.00.10

Copyright © Bentley Systems, Inc. 1984 - 2008.
www.bentley.com
1-800-778-4277

By: A. Pott
Date: Jan/4/2010
CKD:
Date:

File Name: 76-21-125-21-124 U72C.csl

12 strands, 6/10-270K-LL, Low relaxation strands
Depressed at 0.35L (7.00 ft from member end)

END PATTERN (Ycg = 33.88 in):

6 @ 2.250 in	2 @ 63.500 in	2 @ 65.500 in	2 @ 67.500 in
--------------	---------------	---------------	---------------

Strand Diameter	0.600	in
Strand Area	0.217	in ²
Total Strand Area	2.604	in ²
Trans. Len, bonded	3.000	ft
Trans. Len, debonded	3.000	ft
Dev. Len, bonded	11.432	ft
Dev. Len, debonded	14.290	ft
Holddown Force	0.000	kips
Tensile Strength(fpu)	270.0	ksi
Initial Prestress = 0.75fpu	202.5	ksi
Initial Pull	527.3	kips
Beam Shrtng (PL/AE)	0.014	in

REINFORCING STEEL:

Tension	/Shear	steel:
fy	60.0	ksi
Es	29000	ksi
fs	24.0	ksi

LOSSES

Note: Values are calculated at Midspan

Str. area	2.6040	in ²
Ycg	33.88	in
P_init	527.3	kips
Ecc	1.96	in
Days to release	0.75	
Rel. Humid.(RH)	60.0	%
Es	28500.0	ksi
Eci	4981	ksi

AASHTO LOSSES



Program: LEAP®
CONSPAN®
Version: 08.01.00.10

Copyright © Bentley Systems, Inc. 1984 - 2008.
www.bentley.com
1-800-778-4277

By: A. Pott
Date: Jan/4/2010
CKD:
Date:

File Name: 76-21-125-21-124 U72C.csl

Elastic Shortening ** 1.70 ksi (Eq 5.9.5.2.3a-1), (fcgp= 0.297 ksi)

Elastic Gains		Gains		Adjustment	
due to Precast Loads		-0.01 ksi		0.00 ksi	
due to Composite Loads		-0.00 ksi		0.00 ksi	
due to Live Loads		-0.17 ksi		0.00 ksi	

Time Dependent Losses (Approximate Method (Art.5.9.5.3))

		Initial		Final	
Steel relaxation	0.00	ksi		2.40	ksi (Eq 5.9.5.3-1)
Concrete shrinkage	0.00	ksi		8.52	ksi (Eq 5.9.5.3-1)
Concrete creep	0.00	ksi		2.12	ksi (Eq 5.9.5.3-1)
Sub-total	1.70	ksi	(0.84 %)	12.86	ksi (6.35 %)
Total Prestress Losses				14.56	ksi (7.19 %)

Prestressing Stress Limit Check (Table 5.9.3.1)

initial fpi = 202.5 ksi < 0.75 fpu, OK
initial fpe = 187.9 ksi < 0.80 fpy, OK

** Since the transformed section properties option has been selected, even though ES losses have been calculated explicitly here, they are not included as a part of stress calculations. Please see theory section for complete explanation.



Colorado DOT

Sheet #	DS-1
Job #	BR R600-297
By	A. Pott
Date	Jan/4/2010
Checked	
Date	

Program:	LEAP® CONSPAN® V8i (SELECTseries 1)
Version:	Version: 09.00.01.06
File Name:	76-21-125-21-124_U72C.csl

Copyright © Bentley Systems, Inc. 1984 - 2009
www.bentley.com Phone: 1-800-778-4277

CAMBER/DEFLECTION

CAMBER AND DEFLECTIONS: SERVICE I
(Span : 1, Beam : 2; Units: in)

	Release	Mult	Erection	Mult	Final
At 0.1 x L = 6.85 ft					
Prestress	0.242	1.80	0.435	2.20	0.531
Self Wt.	-0.074	1.85	-0.137	2.40	-0.178
Deck + Haunch			-0.083	2.30	-0.191
DL-Prec. (DC)			0.000	3.00	0.000
Diaphragm			0.000	3.00	0.000
DL-Prec. (DW)			0.000	3.00	0.000
DL-Comp. (DC)			-0.002	3.00	-0.005
DL-Comp. (DW)			-0.008	3.00	-0.025
Live Load	Not Included				
Total	0.168		0.205		0.132

.093"

	Release	Mult	Erection	Mult	Final
At 0.2 x L = 14.45 ft					
Prestress	0.441	1.80	0.794	2.20	0.970
Self Wt.	-0.139	1.85	-0.258	2.40	-0.334
Deck + Haunch			-0.165	2.30	-0.379
DL-Prec. (DC)			0.000	3.00	0.000
Diaphragm			0.000	3.00	0.000
DL-Prec. (DW)			0.000	3.00	0.000
DL-Comp. (DC)			-0.003	3.00	-0.010
DL-Comp. (DW)			-0.015	3.00	-0.046
Live Load	Not Included				
Total	0.302		0.353		0.202

.183"

	Release	Mult	Erection	Mult	Final
At 0.3 x L = 22.05 ft					
Prestress	0.583	1.80	1.050	2.20	1.283
Self Wt.	-0.190	1.85	-0.351	2.40	-0.456
Deck + Haunch			-0.229	2.30	-0.526
DL-Prec. (DC)			0.000	3.00	0.000
Diaphragm			0.000	3.00	0.000
DL-Prec. (DW)			0.000	3.00	0.000
DL-Comp. (DC)			-0.004	3.00	-0.013
DL-Comp. (DW)			-0.020	3.00	-0.060
Live Load	Not Included				
Total	0.393		0.445		0.228

.253"

	Release	Mult	Erection	Mult	Final
--	---------	------	----------	------	-------

325



Colorado DOT

Sheet #	DS-2
Job #	BR R600-297
By	A. Pott
Date	Jan/4/2010
Checked	
Date	

Program:	LEAP® CONSPAN® V8i (SELECTseries 1)
Version:	Version: 09.00.01.06
File Name:	76-21-125-21-124_U72C.csl

Copyright © Bentley Systems, Inc. 1984 - 2009
www.bentley.com Phone: 1-800-778-4277

	Release	Mult	Erection	Mult	Final
At 0.4 x L = 29.65 ft					
Prestress	0.672	1.80	1.209	2.20	1.478
Self Wt.	-0.223	1.85	-0.412	2.40	-0.534
Deck + Haunch			-0.270	2.30	-0.620
DL-Prec. (DC)			0.000	3.00	0.000
Diaphragm			0.000	3.00	0.000
DL-Prec. (DW)			0.000	3.00	0.000
DL-Comp. (DC)			-0.005	3.00	-0.014
DL-Comp. (DW)			-0.023	3.00	-0.068
Live Load	Not Included				
Total	0.449		0.500		0.241

298"

	Release	Mult	Erection	Mult	Final
At 0.5 x L = 37.25 ft					
Prestress	0.701	1.80	1.263	2.20	1.543
Self Wt.	-0.234	1.85	-0.432	2.40	-0.561
Deck + Haunch			-0.284	2.30	-0.653
DL-Prec. (DC)			0.000	3.00	0.000
Diaphragm			0.000	3.00	0.000
DL-Prec. (DW)			0.000	3.00	0.000
DL-Comp. (DC)			-0.005	3.00	-0.015
DL-Comp. (DW)			-0.023	3.00	-0.069
Live Load	Not Included				
Total	0.468		0.518		0.246

312"

	Release	Mult	Erection	Mult	Final
At 0.6 x L = 44.85 ft					
Prestress	0.672	1.80	1.209	2.20	1.478
Self Wt.	-0.223	1.85	-0.412	2.40	-0.534
Deck + Haunch			-0.270	2.30	-0.620
DL-Prec. (DC)			0.000	3.00	0.000
Diaphragm			0.000	3.00	0.000
DL-Prec. (DW)			0.000	3.00	0.000
DL-Comp. (DC)			-0.004	3.00	-0.013
DL-Comp. (DW)			-0.021	3.00	-0.063
Live Load	Not Included				
Total	0.449		0.503		0.248

295"

	Release	Mult	Erection	Mult	Final
At 0.7 x L = 52.45 ft					
Prestress	0.583	1.80	1.050	2.20	1.283
Self Wt.	-0.190	1.85	-0.351	2.40	-0.456
Deck + Haunch			-0.229	2.30	-0.526
DL-Prec. (DC)			0.000	3.00	0.000
Diaphragm			0.000	3.00	0.000

25"



Colorado DOT

Sheet #	DS-3
Job #	BR R600-297
By	A. Pott
Date	Jan/4/2010
Checked	
Date	

Program: LEAP® CONSPAN® V8i (SELECTseries 1)
 Version: Version: 09.00.01.06

Copyright © Bentley Systems, Inc. 1984 - 2009
 www.bentley.com Phone: 1-800-778-4277

File Name: 76-21-125-21-124_U72C.csl

	Release	Mult	Erection	Mult	Final
DL-Prec. (DW)			0.000	3.00	0.000
DL-Comp. (DC)			-0.004	3.00	-0.011
DL-Comp. (DW)			-0.017	3.00	-0.050
Live Load	Not Included				
Total	0.393		0.449		0.240

	Release	Mult	Erection	Mult	Final
At 0.8 x L = 60.05 ft					
Prestress	0.441	1.80	0.794	2.20	0.970
Self Wt.	-0.139	1.85	-0.258	2.40	-0.334
Deck + Haunch			-0.165	2.30	-0.379
DL-Prec. (DC)			0.000	3.00	0.000
Diaphragm			0.000	3.00	0.000
DL-Prec. (DW)			0.000	3.00	0.000
DL-Comp. (DC)			-0.002	3.00	-0.007
DL-Comp. (DW)			-0.011	3.00	-0.034
Live Load	Not Included				
Total	0.302		0.358		0.216

178"

	Release	Mult	Erection	Mult	Final
At 0.9 x L = 67.65 ft					
Prestress	0.242	1.80	0.435	2.20	0.531
Self Wt.	-0.074	1.85	-0.137	2.40	-0.178
Deck + Haunch			-0.083	2.30	-0.191
DL-Prec. (DC)			0.000	3.00	0.000
Diaphragm			0.000	3.00	0.000
DL-Prec. (DW)			0.000	3.00	0.000
DL-Comp. (DC)			-0.001	3.00	-0.003
DL-Comp. (DW)			-0.005	3.00	-0.016
Live Load	Not Included				
Total	0.168		0.208		0.144

089"

326



Colorado DOT

Sheet #	DS-1
Job #	BR R600-297
By	A. Pott
Date	Jan/4/2010
Checked	
Date	

Program: LEAP® CONSPAN® V8i (SELECTseries 1)

Version: Version: 09.00.01.06

Copyright © Bentley Systems, Inc. 1984 - 2009

www.bentley.com

Phone: 1-800-778-4277

File Name: 76-21-125-21-124_U72C.csl

CAMBER/DEFLECTION

CAMBER AND DEFLECTIONS: SERVICE I
(Span : 1, Beam : 3; Units: in)

*Girders 3 & 6
Span 1*

	Release	Mult	Erection	Mult	Final
At 0.1 x L = 6.85 ft					
Prestress	0.242	1.80	0.435	2.20	0.531
Self Wt.	-0.074	1.85	-0.137	2.40	-0.178
Deck + Haunch			-0.083	2.30	-0.191
DL-Prec. (DC)			-0.018	3.00	-0.053
Diaphragm			0.000	3.00	0.000
DL-Prec. (DW)			0.000	3.00	0.000
DL-Comp. (DC)			-0.002	3.00	-0.005
DL-Comp. (DW)			-0.008	3.00	-0.025
Live Load	Not Included				
Total	0.168		0.187		0.079

.111"

	Release	Mult	Erection	Mult	Final
At 0.2 x L = 14.45 ft					
Prestress	0.441	1.80	0.794	2.20	0.970
Self Wt.	-0.139	1.85	-0.258	2.40	-0.334
Deck + Haunch			-0.165	2.30	-0.379
DL-Prec. (DC)			-0.035	3.00	-0.106
Diaphragm			0.000	3.00	0.000
DL-Prec. (DW)			0.000	3.00	0.000
DL-Comp. (DC)			-0.003	3.00	-0.010
DL-Comp. (DW)			-0.015	3.00	-0.046
Live Load	Not Included				
Total	0.302		0.318		0.096

.218"

	Release	Mult	Erection	Mult	Final
At 0.3 x L = 22.05 ft					
Prestress	0.583	1.80	1.050	2.20	1.283
Self Wt.	-0.190	1.85	-0.351	2.40	-0.456
Deck + Haunch			-0.229	2.30	-0.526
DL-Prec. (DC)			-0.049	3.00	-0.147
Diaphragm			0.000	3.00	0.000
DL-Prec. (DW)			0.000	3.00	0.000
DL-Comp. (DC)			-0.004	3.00	-0.013
DL-Comp. (DW)			-0.020	3.00	-0.060
Live Load	Not Included				
Total	0.393		0.396		0.081

.302"

Release	Mult	Erection	Mult	Final
---------	------	----------	------	-------



Colorado DOT

Sheet #	DS-2
Job #	BR R600-297
By	A. Pott
Date	Jan/4/2010
Checked	
Date	

Program: LEAP® CONSPAN® V8i (SELECTseries 1)

Version: 09.00.01.06

Copyright © Bentley Systems, Inc. 1984 - 2009

www.bentley.com

Phone: 1-800-778-4277

File Name: 76-21-125-21-124_U72C.csl

	Release	Mult	Erection	Mult	Final
At 0.4 x L = 29.65 ft					
Prestress	0.672	1.80	1.209	2.20	1.478
Self Wt.	-0.223	1.85	-0.412	2.40	-0.534
Deck + Haunch			-0.270	2.30	-0.620
DL-Prec. (DC)			-0.058	3.00	-0.174
Diaphragm			0.000	3.00	0.000
DL-Prec. (DW)			0.000	3.00	0.000
DL-Comp. (DC)			-0.005	3.00	-0.014
DL-Comp. (DW)			-0.023	3.00	-0.068
Live Load	Not Included				
Total	0.449		0.442		0.067

,356"

	Release	Mult	Erection	Mult	Final
At 0.5 x L = 37.25 ft					
Prestress	0.701	1.80	1.263	2.20	1.543
Self Wt.	-0.234	1.85	-0.432	2.40	-0.561
Deck + Haunch			-0.284	2.30	-0.653
DL-Prec. (DC)			-0.061	3.00	-0.183
Diaphragm			0.000	3.00	0.000
DL-Prec. (DW)			0.000	3.00	0.000
DL-Comp. (DC)			-0.005	3.00	-0.015
DL-Comp. (DW)			-0.023	3.00	-0.069
Live Load	Not Included				
Total	0.468		0.458		0.063

,373"

	Release	Mult	Erection	Mult	Final
At 0.6 x L = 44.85 ft					
Prestress	0.672	1.80	1.209	2.20	1.478
Self Wt.	-0.223	1.85	-0.412	2.40	-0.534
Deck + Haunch			-0.270	2.30	-0.620
DL-Prec. (DC)			-0.058	3.00	-0.174
Diaphragm			0.000	3.00	0.000
DL-Prec. (DW)			0.000	3.00	0.000
DL-Comp. (DC)			-0.004	3.00	-0.013
DL-Comp. (DW)			-0.021	3.00	-0.063
Live Load	Not Included				
Total	0.449		0.445		0.074

,353"

	Release	Mult	Erection	Mult	Final
At 0.7 x L = 52.45 ft					
Prestress	0.583	1.80	1.050	2.20	1.283
Self Wt.	-0.190	1.85	-0.351	2.40	-0.456
Deck + Haunch			-0.229	2.30	-0.526
DL-Prec. (DC)			-0.049	3.00	-0.147
Diaphragm			0.000	3.00	0.000

,299"



Colorado DOT

Sheet #	DS-3
Job #	BR R600-297
By	A. Pott
Date	Jan/4/2010
Checked	
Date	

Program: LEAP® CONSPAN® V8i (SELECTseries 1)

Version: Version: 09.00.01.06

Copyright © Bentley Systems, Inc. 1984 - 2009

www.bentley.com

Phone: 1-800-778-4277

File Name: 76-21-125-21-124_U72C.csl

	Release	Mult	Erection	Mult	Final
DL-Prec. (DW)			0.000	3.00	0.000
DL-Comp. (DC)			-0.004	3.00	-0.011
DL-Comp. (DW)			-0.017	3.00	-0.050
Live Load	Not Included				
Total	0.393		0.400		0.093

	Release	Mult	Erection	Mult	Final
At 0.8 x L = 60.05 ft					
Prestress	0.441	1.80	0.794	2.20	0.970
Self Wt.	-0.139	1.85	-0.258	2.40	-0.334
Deck + Haunch			-0.165	2.30	-0.379
DL-Prec. (DC)			-0.035	3.00	-0.106
Diaphragm			0.000	3.00	0.000
DL-Prec. (DW)			0.000	3.00	0.000
DL-Comp. (DC)			-0.002	3.00	-0.007
DL-Comp. (DW)			-0.011	3.00	-0.034
Live Load	Not Included				
Total	0.302		0.322		0.110

.213"

	Release	Mult	Erection	Mult	Final
At 0.9 x L = 67.65 ft					
Prestress	0.242	1.80	0.435	2.20	0.531
Self Wt.	-0.074	1.85	-0.137	2.40	-0.178
Deck + Haunch			-0.083	2.30	-0.191
DL-Prec. (DC)			-0.018	3.00	-0.053
Diaphragm			0.000	3.00	0.000
DL-Prec. (DW)			0.000	3.00	0.000
DL-Comp. (DC)			-0.001	3.00	-0.003
DL-Comp. (DW)			-0.005	3.00	-0.016
Live Load	Not Included				
Total	0.168		0.191		0.090

.107"

328



Colorado DOT

Sheet #	DS-1
Job #	BR R600-297
By	A. Pott
Date	Jan/4/2010
Checked	
Date	

Program: LEAP® CONSPAN® V8i (SELECTseries 1)

Version: Version: 09.00.01.06

Copyright © Bentley Systems, Inc. 1984 - 2009

www.bentley.com Phone: 1-800-778-4277

File Name: 76-21-125-21-124_U72C.csl

CAMBER/DEFLECTION

CAMBER AND DEFLECTIONS: SERVICE I
(Span : 3, Beam : 2; Units: in)

	Release	Mult	Erection	Mult	Final
At 0.1 x L = 11.70 ft					
Prestress	1.620	1.80	2.915	2.20	3.563
Self Wt.	-0.566	1.85	-1.048	2.40	-1.359
Deck + Haunch			-0.656	2.30	-1.509
DL-Prec. (DC)			0.000	3.00	0.000
Diaphragm			0.000	3.00	0.000
DL-Prec. (DW)			0.000	3.00	0.000
DL-Comp. (DC)			-0.003	3.00	-0.010
DL-Comp. (DW)			-0.016	3.00	-0.049
Live Load	Not Included				
Total	1.053		1.192		0.635

675"

	Release	Mult	Erection	Mult	Final
At 0.2 x L = 24.40 ft					
Prestress	2.900	1.80	5.220	2.20	6.380
Self Wt.	-1.061	1.85	-1.962	2.40	-2.546
Deck + Haunch			-1.283	2.30	-2.951
DL-Prec. (DC)			0.000	3.00	0.000
Diaphragm			0.000	3.00	0.000
DL-Prec. (DW)			0.000	3.00	0.000
DL-Comp. (DC)			-0.008	3.00	-0.025
DL-Comp. (DW)			-0.039	3.00	-0.118
Live Load	Not Included				
Total	1.839		1.927		0.741

1.33"

	Release	Mult	Erection	Mult	Final
At 0.3 x L = 37.10 ft					
Prestress	3.809	1.80	6.857	2.20	8.380
Self Wt.	-1.436	1.85	-2.657	2.40	-3.447
Deck + Haunch			-1.761	2.30	-4.050
DL-Prec. (DC)			0.000	3.00	0.000
Diaphragm			0.000	3.00	0.000
DL-Prec. (DW)			0.000	3.00	0.000
DL-Comp. (DC)			-0.013	3.00	-0.038
DL-Comp. (DW)			-0.061	3.00	-0.182
Live Load	Not Included				
Total	2.373		2.365		0.663

1.835"

Release	Mult	Erection	Mult	Final
---------	------	----------	------	-------

329



Colorado DOT

Sheet #	DS-2
Job #	BR R600-297
By	A. Pott
Date	Jan/4/2010
Checked	
Date	

Program: LEAP® CONSPAN® V8i (SELECTseries 1)

Version: 09.00.01.06

Copyright © Bentley Systems, Inc. 1984 - 2009

www.bentley.com

Phone: 1-800-778-4277

File Name: 76-21-125-21-124_U72C.csl

	Release	Mult	Erection	Mult	Final
At 0.4 x L = 49.80 ft					
Prestress	4.358	1.80	7.845	2.20	9.588
Self Wt.	-1.672	1.85	-3.094	2.40	-4.013
Deck + Haunch			-2.062	2.30	-4.742
DL-Prec. (DC)			0.000	3.00	0.000
Diaphragm			0.000	3.00	0.000
DL-Prec. (DW)			0.000	3.00	0.000
DL-Comp. (DC)			-0.016	3.00	-0.048
DL-Comp. (DW)			-0.076	3.00	-0.229
Live Load	Not Included				
Total	2.686		2.598		0.557

2.154"

	Release	Mult	Erection	Mult	Final
At 0.5 x L = 62.50 ft					
Prestress	4.552	1.80	8.194	2.20	10.015
Self Wt.	-1.756	1.85	-3.249	2.40	-4.214
Deck + Haunch			-2.168	2.30	-4.987
DL-Prec. (DC)			0.000	3.00	0.000
Diaphragm			0.000	3.00	0.000
DL-Prec. (DW)			0.000	3.00	0.000
DL-Comp. (DC)			-0.017	3.00	-0.052
DL-Comp. (DW)			-0.082	3.00	-0.247
Live Load	Not Included				
Total	2.796		2.677		0.515

2.267"

	Release	Mult	Erection	Mult	Final
At 0.6 x L = 75.20 ft					
Prestress	4.358	1.80	7.845	2.20	9.588
Self Wt.	-1.672	1.85	-3.094	2.40	-4.013
Deck + Haunch			-2.062	2.30	-4.742
DL-Prec. (DC)			0.000	3.00	0.000
Diaphragm			0.000	3.00	0.000
DL-Prec. (DW)			0.000	3.00	0.000
DL-Comp. (DC)			-0.016	3.00	-0.049
DL-Comp. (DW)			-0.078	3.00	-0.233
Live Load	Not Included				
Total	2.686		2.596		0.552

2.156"

	Release	Mult	Erection	Mult	Final
At 0.7 x L = 87.90 ft					
Prestress	3.809	1.80	6.857	2.20	8.380
Self Wt.	-1.436	1.85	-2.657	2.40	-3.447
Deck + Haunch			-1.761	2.30	-4.050
DL-Prec. (DC)			0.000	3.00	0.000
Diaphragm			0.000	3.00	0.000

1.837"



Colorado DOT

Sheet #	DS-3
Job #	BR R600-297
By	A. Pott
Date	Jan/4/2010
Checked	
Date	

Program: LEAP® CONSPAN® V8i (SELECTseries 1)

Version: Version: 09.00.01.06

Copyright © Bentley Systems, Inc. 1984 - 2009

www.bentley.com Phone: 1-800-778-4277

File Name: 76-21-125-21-124_U72C.csl

	Release	Mult	Erection	Mult	Final
DL-Prec. (DW)			0.000	3.00	0.000
DL-Comp. (DC)			-0.013	3.00	-0.040
DL-Comp. (DW)			-0.063	3.00	-0.190
Live Load	Not Included				
Total	2.373		2.362		0.654

	Release	Mult	Erection	Mult	Final
At 0.8 x L = 100.60 ft					
Prestress	2.900	1.80	5.220	2.20	6.380
Self Wt.	-1.061	1.85	-1.962	2.40	-2.546
Deck + Haunch			-1.283	2.30	-2.951
DL-Prec. (DC)			0.000	3.00	0.000
Diaphragm			0.000	3.00	0.000
DL-Prec. (DW)			0.000	3.00	0.000
DL-Comp. (DC)			-0.009	3.00	-0.027
DL-Comp. (DW)			-0.042	3.00	-0.126
Live Load	Not Included				
Total	1.839		1.924		0.731

1.334"

	Release	Mult	Erection	Mult	Final
At 0.9 x L = 113.30 ft					
Prestress	1.620	1.80	2.915	2.20	3.563
Self Wt.	-0.566	1.85	-1.048	2.40	-1.359
Deck + Haunch			-0.656	2.30	-1.509
DL-Prec. (DC)			0.000	3.00	0.000
Diaphragm			0.000	3.00	0.000
DL-Prec. (DW)			0.000	3.00	0.000
DL-Comp. (DC)			-0.004	3.00	-0.012
DL-Comp. (DW)			-0.019	3.00	-0.056
Live Load	Not Included				
Total	1.053		1.189		0.627

.679'



Colorado DOT

Sheet #	DS-1
Job #	BR R600-297
By	A. Pott
Date	Jan/4/2010
Checked	
Date	

Program:	LEAP® CONSPAN® V8i (SELECTseries 1)
Version:	Version: 09.00.01.06
File Name:	76-21-125-21-124_U72C.csl

Copyright © Bentley Systems, Inc. 1984 - 2009
www.bentley.com Phone: 1-800-778-4277

CAMBER/DEFLECTION

CAMBER AND DEFLECTIONS: SERVICE I
 (Span : 3, Beam : 3; Units: in)

Girders 3 & 6

	Release	Mult	Erection	Mult	Final
At 0.1 x L = 11.70 ft					
Prestress	1.771	1.80	3.188	2.20	3.896
Self Wt.	-0.566	1.85	-1.047	2.40	-1.358
Deck + Haunch			-0.656	2.30	-1.508
DL-Prec. (DC)			-0.141	3.00	-0.422
Diaphragm			0.000	3.00	0.000
DL-Prec. (DW)			0.000	3.00	0.000
DL-Comp. (DC)			-0.003	3.00	-0.010
DL-Comp. (DW)			-0.016	3.00	-0.049
Live Load	Not Included				
Total	1.205		1.325		0.548

.816"

	Release	Mult	Erection	Mult	Final
At 0.2 x L = 24.40 ft					
Prestress	3.183	1.80	5.730	2.20	7.003
Self Wt.	-1.056	1.85	-1.954	2.40	-2.536
Deck + Haunch			-1.278	2.30	-2.939
DL-Prec. (DC)			-0.274	3.00	-0.823
Diaphragm			0.000	3.00	0.000
DL-Prec. (DW)			0.000	3.00	0.000
DL-Comp. (DC)			-0.008	3.00	-0.025
DL-Comp. (DW)			-0.039	3.00	-0.117
Live Load	Not Included				
Total	2.127		2.176		0.564

1.599"

	Release	Mult	Erection	Mult	Final
At 0.3 x L = 37.10 ft					
Prestress	4.170	1.80	7.506	2.20	9.174
Self Wt.	-1.427	1.85	-2.639	2.40	-3.424
Deck + Haunch			-1.749	2.30	-4.022
DL-Prec. (DC)			-0.376	3.00	-1.127
Diaphragm			0.000	3.00	0.000
DL-Prec. (DW)			0.000	3.00	0.000
DL-Comp. (DC)			-0.013	3.00	-0.038
DL-Comp. (DW)			-0.060	3.00	-0.181
Live Load	Not Included				
Total	2.744		2.670		0.382

2.198"

Release	Mult	Erection	Mult	Final
---------	------	----------	------	-------

331



Colorado DOT

Sheet #	DS-2
Job #	BR R600-297
By	A. Pott
Date	Jan/4/2010
Checked	
Date	

Program: LEAP® CONSPAN® V8i (SELECTseries 1)

Version: Version: 09.00.01.06

Copyright © Bentley Systems, Inc. 1984 - 2009

www.bentley.com Phone: 1-800-778-4277

File Name: 76-21-125-21-124_U72C.csl

	Release	Mult	Erection	Mult	Final
At 0.4 x L = 49.80 ft					
Prestress	4.780	1.80	8.605	2.20	10.517
Self Wt.	-1.661	1.85	-3.073	2.40	-3.987
Deck + Haunch			-2.048	2.30	-4.710
DL-Prec. (DC)			-0.440	3.00	-1.320
Diaphragm			0.000	3.00	0.000
DL-Prec. (DW)			0.000	3.00	0.000
DL-Comp. (DC)			-0.016	3.00	-0.048
DL-Comp. (DW)			-0.076	3.00	-0.227
Live Load	Not Included				
Total	3.119		2.953		0.226

2.58"

	Release	Mult	Erection	Mult	Final
At 0.5 x L = 62.50 ft					
Prestress	4.995	1.80	8.992	2.20	10.990
Self Wt.	-1.744	1.85	-3.227	2.40	-4.186
Deck + Haunch			-2.154	2.30	-4.953
DL-Prec. (DC)			-0.463	3.00	-1.388
Diaphragm			0.000	3.00	0.000
DL-Prec. (DW)			0.000	3.00	0.000
DL-Comp. (DC)			-0.017	3.00	-0.052
DL-Comp. (DW)			-0.082	3.00	-0.245
Live Load	Not Included				
Total	3.251		3.050		0.166

2.716"

	Release	Mult	Erection	Mult	Final
At 0.6 x L = 75.20 ft					
Prestress	4.780	1.80	8.605	2.20	10.517
Self Wt.	-1.661	1.85	-3.073	2.40	-3.987
Deck + Haunch			-2.048	2.30	-4.710
DL-Prec. (DC)			-0.440	3.00	-1.320
Diaphragm			0.000	3.00	0.000
DL-Prec. (DW)			0.000	3.00	0.000
DL-Comp. (DC)			-0.016	3.00	-0.049
DL-Comp. (DW)			-0.077	3.00	-0.231
Live Load	Not Included				
Total	3.119		2.951		0.221

2.581"

	Release	Mult	Erection	Mult	Final
At 0.7 x L = 87.90 ft					
Prestress	4.170	1.80	7.506	2.20	9.174
Self Wt.	-1.427	1.85	-2.639	2.40	-3.424
Deck + Haunch			-1.749	2.30	-4.022
DL-Prec. (DC)			-0.376	3.00	-1.127
Diaphragm			0.000	3.00	0.000

2.201"



Colorado DOT

Sheet #	DS-3
Job #	BR R600-297
By	A. Pott
Date	Jan/4/2010
Checked	
Date	

Program: LEAP® CONSPAN® V8i (SELECTseries 1)
 Version: Version: 09.00.01.06

Copyright © Bentley Systems, Inc. 1984 - 2009
 www.bentley.com Phone: 1-800-778-4277

File Name: 76-21-125-21-124_U72C.csl

	Release	Mult	Erection	Mult	Final
DL-Prec. (DW)			0.000	3.00	0.000
DL-Comp. (DC)			-0.013	3.00	-0.040
DL-Comp. (DW)			-0.063	3.00	-0.189
Live Load	Not Included				
Total	2.744		2.667		0.373

	Release	Mult	Erection	Mult	Final
At 0.8 x L = 100.60 ft					
Prestress	3.183	1.80	5.730	2.20	7.003
Self Wt.	-1.056	1.85	-1.954	2.40	-2.536
Deck + Haunch			-1.278	2.30	-2.939
DL-Prec. (DC)			-0.274	3.00	-0.823
Diaphragm			0.000	3.00	0.000
DL-Prec. (DW)			0.000	3.00	0.000
DL-Comp. (DC)			-0.009	3.00	-0.026
DL-Comp. (DW)			-0.042	3.00	-0.126
Live Load	Not Included				
Total	2.127		2.173		0.554

1.603"

	Release	Mult	Erection	Mult	Final
At 0.9 x L = 113.30 ft					
Prestress	1.771	1.80	3.188	2.20	3.896
Self Wt.	-0.566	1.85	-1.047	2.40	-1.358
Deck + Haunch			-0.656	2.30	-1.508
DL-Prec. (DC)			-0.141	3.00	-0.422
Diaphragm			0.000	3.00	0.000
DL-Prec. (DW)			0.000	3.00	0.000
DL-Comp. (DC)			-0.004	3.00	-0.012
DL-Comp. (DW)			-0.019	3.00	-0.056
Live Load	Not Included				
Total	1.205		1.322		0.540

.82"

332



Colorado DOT

Sheet #	DS-1
Job #	BR R600-297
By	A. Pott
Date	Jan/4/2010
Checked	
Date	

Program:	LEAP® CONSPAN® V8i (SELECTseries 1)
Version:	Version: 09.00.01.06
File Name:	76-21-125-21-124_U72C.csl

Copyright © Bentley Systems, Inc. 1984 - 2009
 www.bentley.com Phone: 1-800-778-4277

CAMBER/DEFLECTION

CAMBER AND DEFLECTIONS: SERVICE I
 (Span : 5, Beam : 2; Units: in)

	Release	Mult	Erection	Mult	Final
At 0.1 x L = 11.65 ft					
Prestress	1.539	1.80	2.771	2.20	3.387
Self Wt.	-0.515	1.85	-0.952	2.40	-1.235
Deck + Haunch			-0.614	2.30	-1.413
DL-Prec. (DC)			0.000	3.00	0.000
Diaphragm			0.000	3.00	0.000
DL-Prec. (DW)			0.000	3.00	0.000
DL-Comp. (DC)			-0.005	3.00	-0.015
DL-Comp. (DW)			-0.024	3.00	-0.071
Live Load	Not Included				
Total	1.025		1.176		0.652

.643"

	Release	Mult	Erection	Mult	Final
At 0.2 x L = 24.05 ft					
Prestress	2.760	1.80	4.968	2.20	6.073
Self Wt.	-0.964	1.85	-1.784	2.40	-2.314
Deck + Haunch			-1.189	2.30	-2.735
DL-Prec. (DC)			0.000	3.00	0.000
Diaphragm			0.000	3.00	0.000
DL-Prec. (DW)			0.000	3.00	0.000
DL-Comp. (DC)			-0.012	3.00	-0.035
DL-Comp. (DW)			-0.055	3.00	-0.166
Live Load	Not Included				
Total	1.796		1.929		0.823

1.256"

	Release	Mult	Erection	Mult	Final
At 0.3 x L = 36.45 ft					
Prestress	3.627	1.80	6.529	2.20	7.979
Self Wt.	-1.305	1.85	-2.415	2.40	-3.133
Deck + Haunch			-1.627	2.30	-3.742
DL-Prec. (DC)			0.000	3.00	0.000
Diaphragm			0.000	3.00	0.000
DL-Prec. (DW)			0.000	3.00	0.000
DL-Comp. (DC)			-0.018	3.00	-0.055
DL-Comp. (DW)			-0.087	3.00	-0.260
Live Load	Not Included				
Total	2.322		2.382		0.790

1.732"

	Release	Mult	Erection	Mult	Final
--	---------	------	----------	------	-------

333



Colorado DOT

Sheet #	DS-2
Job #	BR R600-297
By	A. Pott
Date	Jan/4/2010
Checked	
Date	

Program:	LEAP® CONSPAN® V8i (SELECTseries 1)
Version:	Version: 09.00.01.06
File Name:	76-21-125-21-124_U72C.csl

Copyright © Bentley Systems, Inc. 1984 - 2009
www.bentley.com Phone: 1-800-778-4277

	Release	Mult	Erection	Mult	Final
At 0.4 x L = 48.85 ft					
Prestress	4.150	1.80	7.471	2.20	9.131
Self Wt.	-1.520	1.85	-2.812	2.40	-3.647
Deck + Haunch			-1.902	2.30	-4.375
DL-Prec. (DC)			0.000	3.00	0.000
Diaphragm			0.000	3.00	0.000
DL-Prec. (DW)			0.000	3.00	0.000
DL-Comp. (DC)			-0.024	3.00	-0.071
DL-Comp. (DW)			-0.112	3.00	-0.336
Live Load	Not Included				
Total	2.631		2.622		0.702

2.038"

	Release	Mult	Erection	Mult	Final
At 0.5 x L = 61.25 ft					
Prestress	4.335	1.80	7.803	2.20	9.537
Self Wt.	-1.596	1.85	-2.952	2.40	-3.830
Deck + Haunch			-2.000	2.30	-4.600
DL-Prec. (DC)			0.000	3.00	0.000
Diaphragm			0.000	3.00	0.000
DL-Prec. (DW)			0.000	3.00	0.000
DL-Comp. (DC)			-0.027	3.00	-0.080
DL-Comp. (DW)			-0.126	3.00	-0.379
Live Load	Not Included				
Total	2.739		2.698		0.649

2.153"

	Release	Mult	Erection	Mult	Final
At 0.6 x L = 73.65 ft					
Prestress	4.150	1.80	7.471	2.20	9.131
Self Wt.	-1.520	1.85	-2.812	2.40	-3.647
Deck + Haunch			-1.902	2.30	-4.375
DL-Prec. (DC)			0.000	3.00	0.000
Diaphragm			0.000	3.00	0.000
DL-Prec. (DW)			0.000	3.00	0.000
DL-Comp. (DC)			-0.027	3.00	-0.080
DL-Comp. (DW)			-0.127	3.00	-0.381
Live Load	Not Included				
Total	2.631		2.603		0.648

2.056"

	Release	Mult	Erection	Mult	Final
At 0.7 x L = 86.05 ft					
Prestress	3.627	1.80	6.529	2.20	7.979
Self Wt.	-1.305	1.85	-2.415	2.40	-3.133
Deck + Haunch			-1.627	2.30	-3.742
DL-Prec. (DC)			0.000	3.00	0.000
Diaphragm			0.000	3.00	0.000

1.764"



Colorado DOT

Sheet #	DS-3
Job #	BR R600-297
By	A. Pott
Date	Jan/4/2010
Checked	
Date	

Program: LEAP® CONSPAN® V8i (SELECTseries 1)

Version: Version: 09.00.01.06

Copyright © Bentley Systems, Inc. 1984 - 2009

www.bentley.com Phone: 1-800-778-4277

File Name: 76-21-125-21-124_U72C.csl

	Release	Mult	Erection	Mult	Final
DL-Prec. (DW)			0.000	3.00	0.000
DL-Comp. (DC)			-0.024	3.00	-0.071
DL-Comp. (DW)			-0.113	3.00	-0.339
Live Load	Not Included				
Total	2.322		2.350		0.694

	Release	Mult	Erection	Mult	Final
At 0.8 x L = 98.45 ft					
Prestress	2.760	1.80	4.968	2.20	6.073
Self Wt.	-0.964	1.85	-1.784	2.40	-2.314
Deck + Haunch			-1.189	2.30	-2.735
DL-Prec. (DC)			0.000	3.00	0.000
Diaphragm			0.000	3.00	0.000
DL-Prec. (DW)			0.000	3.00	0.000
DL-Comp. (DC)			-0.018	3.00	-0.054
DL-Comp. (DW)			-0.085	3.00	-0.256
Live Load	Not Included				
Total	1.796		1.892		0.713

1.292"

	Release	Mult	Erection	Mult	Final
At 0.9 x L = 110.85 ft					
Prestress	1.539	1.80	2.771	2.20	3.387
Self Wt.	-0.515	1.85	-0.952	2.40	-1.235
Deck + Haunch			-0.614	2.30	-1.413
DL-Prec. (DC)			0.000	3.00	0.000
Diaphragm			0.000	3.00	0.000
DL-Prec. (DW)			0.000	3.00	0.000
DL-Comp. (DC)			-0.010	3.00	-0.029
DL-Comp. (DW)			-0.046	3.00	-0.139
Live Load	Not Included				
Total	1.025		1.148		0.570

.67"

334



Colorado DOT

Sheet # DS-1

Job # BR R600-297

Program: LEAP® CONSPAN® V8i (SELECTseries 1)

By A. Pott

Version: Version: 09.00.01.06

Copyright © Bentley Systems, Inc. 1984 - 2009

Date Jan/4/2010

www.bentley.com

Phone: 1-800-778-4277

Checked

File Name: 76-21-125-21-124_U72C.csl

Date

CAMBER/DEFLECTION

CAMBER AND DEFLECTIONS: SERVICE I
(Span : 5, Beam : 3; Units: in)

Gunders 386

	Release	Mult	Erection	Mult	Final
At 0.1 x L = 11.65 ft					
Prestress	1.702	1.80	3.064	2.20	3.745
Self Wt.	-0.511	1.85	-0.945	2.40	-1.226
Deck + Haunch			-0.610	2.30	-1.403
DL-Prec. (DC)			-0.131	3.00	-0.393
Diaphragm			0.000	3.00	0.000
DL-Prec. (DW)			0.000	3.00	0.000
DL-Comp. (DC)			-0.005	3.00	-0.015
DL-Comp. (DW)			-0.024	3.00	-0.071
Live Load	Not Included				
Total	1.191		1.349		0.637

0.77"

	Release	Mult	Erection	Mult	Final
At 0.2 x L = 24.05 ft					
Prestress	3.041	1.80	5.474	2.20	6.691
Self Wt.	-0.957	1.85	-1.770	2.40	-2.296
Deck + Haunch			-1.180	2.30	-2.714
DL-Prec. (DC)			-0.254	3.00	-0.761
Diaphragm			0.000	3.00	0.000
DL-Prec. (DW)			0.000	3.00	0.000
DL-Comp. (DC)			-0.012	3.00	-0.035
DL-Comp. (DW)			-0.055	3.00	-0.165
Live Load	Not Included				
Total	2.084		2.204		0.720

1.501"

	Release	Mult	Erection	Mult	Final
At 0.3 x L = 36.45 ft					
Prestress	3.993	1.80	7.188	2.20	8.785
Self Wt.	-1.297	1.85	-2.400	2.40	-3.113
Deck + Haunch			-1.617	2.30	-3.719
DL-Prec. (DC)			-0.347	3.00	-1.042
Diaphragm			0.000	3.00	0.000
DL-Prec. (DW)			0.000	3.00	0.000
DL-Comp. (DC)			-0.018	3.00	-0.054
DL-Comp. (DW)			-0.086	3.00	-0.259
Live Load	Not Included				
Total	2.696		2.719		0.598

2.068"

	Release	Mult	Erection	Mult	Final
--	---------	------	----------	------	-------

335



Colorado DOT

Sheet #	DS-2
Job #	BR R600-297
By	A. Pott
Date	Jan/4/2010
Checked	
Date	

Program: LEAP® CONSPAN® V8i (SELECTseries 1)

Version: Version: 09.00.01.06

Copyright © Bentley Systems, Inc. 1984 - 2009

www.bentley.com

Phone: 1-800-778-4277

File Name: 76-21-125-21-124_U72C.csl

	Release	Mult	Erection	Mult	Final
At 0.4 x L = 48.85 ft					
Prestress	4.567	1.80	8.220	2.20	10.047
Self Wt.	-1.512	1.85	-2.796	2.40	-3.628
Deck + Haunch			-1.892	2.30	-4.351
DL-Prec. (DC)			-0.406	3.00	-1.219
Diaphragm			0.000	3.00	0.000
DL-Prec. (DW)			0.000	3.00	0.000
DL-Comp. (DC)			-0.023	3.00	-0.070
DL-Comp. (DW)			-0.111	3.00	-0.334
Live Load	Not Included				
Total	3.055		2.991		0.445

2.432"

	Release	Mult	Erection	Mult	Final
At 0.5 x L = 61.25 ft					
Prestress	4.768	1.80	8.582	2.20	10.489
Self Wt.	-1.587	1.85	-2.936	2.40	-3.809
Deck + Haunch			-1.989	2.30	-4.575
DL-Prec. (DC)			-0.427	3.00	-1.282
Diaphragm			0.000	3.00	0.000
DL-Prec. (DW)			0.000	3.00	0.000
DL-Comp. (DC)			-0.026	3.00	-0.079
DL-Comp. (DW)			-0.126	3.00	-0.377
Live Load	Not Included				
Total	3.181		3.077		0.367

2.568"

	Release	Mult	Erection	Mult	Final
At 0.6 x L = 73.65 ft					
Prestress	4.567	1.80	8.220	2.20	10.047
Self Wt.	-1.512	1.85	-2.796	2.40	-3.628
Deck + Haunch			-1.892	2.30	-4.351
DL-Prec. (DC)			-0.406	3.00	-1.219
Diaphragm			0.000	3.00	0.000
DL-Prec. (DW)			0.000	3.00	0.000
DL-Comp. (DC)			-0.027	3.00	-0.080
DL-Comp. (DW)			-0.126	3.00	-0.378
Live Load	Not Included				
Total	3.055		2.973		0.391

2.451"

	Release	Mult	Erection	Mult	Final
At 0.7 x L = 86.05 ft					
Prestress	3.993	1.80	7.188	2.20	8.785
Self Wt.	-1.297	1.85	-2.400	2.40	-3.113
Deck + Haunch			-1.617	2.30	-3.719
DL-Prec. (DC)			-0.347	3.00	-1.042
Diaphragm			0.000	3.00	0.000

2.1"



Colorado DOT

Sheet #	DS-3
Job #	BR R600-297
By	A. Pott
Date	Jan/4/2010
Checked	
Date	

Program: LEAP® CONSPAN® V8i (SELECTseries 1)

Version: Version: 09.00.01.06

Copyright © Bentley Systems, Inc. 1984 - 2009

www.bentley.com Phone: 1-800-778-4277

File Name: 76-21-125-21-124_U72C.csl


	Release	Mult	Erection	Mult	Final
DL-Prec. (DW)			0.000	3.00	0.000
DL-Comp. (DC)			-0.024	3.00	-0.071
DL-Comp. (DW)			-0.112	3.00	-0.337
Live Load	Not Included				
Total	2.696		2.688		0.503

	Release	Mult	Erection	Mult	Final
At 0.8 x L = 98.45 ft					
Prestress	3.041	1.80	5.474	2.20	6.691
Self Wt.	-0.957	1.85	-1.770	2.40	-2.296
Deck + Haunch			-1.180	2.30	-2.714
DL-Prec. (DC)			-0.254	3.00	-0.761
Diaphragm			0.000	3.00	0.000
DL-Prec. (DW)			0.000	3.00	0.000
DL-Comp. (DC)			-0.018	3.00	-0.054
DL-Comp. (DW)			-0.085	3.00	-0.255
Live Load	Not Included				
Total	2.084		2.168		0.611


1.537"

	Release	Mult	Erection	Mult	Final
At 0.9 x L = 110.85 ft					
Prestress	1.702	1.80	3.064	2.20	3.745
Self Wt.	-0.511	1.85	-0.945	2.40	-1.226
Deck + Haunch			-0.610	2.30	-1.403
DL-Prec. (DC)			-0.131	3.00	-0.393
Diaphragm			0.000	3.00	0.000
DL-Prec. (DW)			0.000	3.00	0.000
DL-Comp. (DC)			-0.010	3.00	-0.029
DL-Comp. (DW)			-0.046	3.00	-0.138
Live Load	Not Included				
Total	1.191		1.322		0.555

.797"



$\langle -65, 72 \rangle$ 72L



$-60.82, 65.65$ $-43.41, 65.65$

72L $\langle -62.25, 65.65 \rangle$

$\langle -32.77, 54 \rangle$ 72L

72L $\langle -21.18, 10.04 \rangle$

72L $\langle -19.29, 8 \rangle$

$-23.87, 8$

54

4'6"

11' 4"

-33

11"

11"

COLORADO DEPARTMENT OF TRANSPORTATION
DESIGN COMPUTATIONS (Grid)

Stress @ access hatch

34 strands location @ 4.06"
 12 strands debonded

$$f_t = \frac{P_e}{A} + \frac{P_t e}{S_b}$$

for mod. Aed section



$$I_x \approx 812026$$

$$y \approx 41.94$$

$$A \approx 1482.6 \text{ in}^2$$

$$S_b \approx 19361.6$$

$$e = 41.94 - 4.06 \approx 37.88"$$

$$f_t = \frac{(22)(.217)(75)(270)}{1482.6} + \frac{(22)(.217)(75)(270)(37.88")}{19361.6}$$

$$f_t \approx .652 + 1.89$$

$$f_t \approx 2.54 \text{ ksi} < 4.05 \text{ ksi } \checkmark \text{ ok}$$

By: _____	Date _____	Project no. _____	Project code (SA#): _____
Chk'd: _____	Date _____	Structure no. _____	Sheet <u>339</u> of _____



Program: LEAP®
CONSPAN®
Version: 08.01.00.10

Copyright © Bentley Systems, Inc. 1984 - 2008.
www.bentley.com
1-800-778-4277

By: A. Pott
Date: Jan/4/2010
CKD:
Date:

File Name: 76-21-125-21-124_U72C.csl

ULTIMATE MOMENT

ULTIMATE - Span : 1, Beam : 6, STRENGTH I (Mr-prvd computed by AASHTO equations, Art. 5.7.3.2/5.7.3.3)

Location (ft)	dp in	Aps in ²	fps ksi	c in	a in	Mr-prvd k.ft	c/dt	Phi	1.2 Mcr k.ft	min Mr k.ft	Crkg Ratio	Mu-pr Ratio
Transfer	2.25											
1509.1	80.3	2.399	269.5	0.5	0.4	4319.9	0.006T	1.00	-	-	-	-
H/2	3.52											
2133.7	80.3	2.558	269.5	0.5	0.4	4603.5	0.007T	1.00	-	-	-	-
0.1L	6.85											
3635.3	80.3	2.974	269.4	0.6	0.4	5349.4	0.008T	1.00	-	-	-	-
0.2L	14.45											
6288.4	80.3	5.715	268.9	1.2	0.8	10234.2	0.015T	1.00	13947.3	8363.5	0.9	1.63
0.3L	22.05											
7956.1	80.3	6.991	268.6	1.5	1.0	12491.9	0.018T	1.00	14579.7	10581.7	1.0	1.57
0.4L	29.65											
8741.2	80.3	7.378	268.5	1.6	1.1	13175.0	0.019T	1.00	14266.6	11625.8	1.1	1.51
0.5L	37.25											
8706.0	80.3	7.378	268.5	1.6	1.1	13175.0	0.019T	1.00	14162.2	11578.9	1.1	1.51
0.6L	44.85											
7837.4	80.3	7.378	268.5	1.6	1.1	13175.0	0.019T	1.00	14266.6	10423.7	1.1	1.68
0.7L	52.45											
6159.3	80.3	6.991	268.6	1.5	1.0	12491.9	0.018T	1.00	14579.7	8191.9	1.0	2.03
0.8L	60.05											
4042.1	80.3	5.715	268.9	1.2	0.8	10234.2	0.015T	1.00	13947.3	5376.0	0.9	2.53
0.9L	67.65											
2015.6	80.3	2.974	269.4	0.6	0.4	5349.4	0.008T	1.00	-	-	-	-
H/2	70.98											
1194.0	80.3	2.558	269.5	0.5	0.4	4603.5	0.007T	1.00	-	-	-	-
Transfer	72.25											
881.3	80.3	2.399	269.5	0.5	0.4	4319.9	0.006T	1.00	-	-	-	-

Legend: C = Compression-Controlled (c/dt > 0.600)

I = In-Transition (0.60 >= c/dt > 0.375)

T = Tension-Controlled (c/dt <= 0.375)

Note : fr used for calculating Mcr is computed using AASHTO method (Art.5.4.2.6.)



Program: LEAP®
CONSPAN®
Version: 08.01.00.10
File Name: 76-21-125-21-124 U72C.csl

Copyright © Bentley Systems, Inc. 1984 - 2008.
www.bentley.com
1-800-778-4277

By: A. Pott
Date: Jan/4/2010
CKD:
Date:

VERTICAL/HORIZONTAL SHEAR

VERTICAL SHEAR (Art. 5.8) - Span : 1, Beam : 6, STRENGTH I

Using General Beta Theta Tables procedure - Art.5.8.3.4.2

Location(ft)	Vu (kips)	bv (in)	de (in)	Aps (in ²)	Vp (kips)	eps_x	Theta	Vs-reqd (kips)	Av/s (in ² /ft)	Av-prvd (in ² /ft)	Al_reqd (in ²)
	Mcor (kft)	a (in)	dv (in)	fpo (ksi)	vu/fc	Vc-com (kips)	Beta	Max.spc. (in)	min.Av/s (in ² /ft)	pVn/Vu	Aps* (in ²)
Bearing :		0.75									
	571.5	15.0	80.3	1.245	0.0	1.00e-3	36.4	381.8	0.705	1.59	4.48
	375.0	1.1	79.8	47.2	0.059	253.1	2.23	24.00	0.284	1.750	0.600
Transfer :		3.00									
	540.4	15.0	80.3	3.472	0.0	1.00e-3	36.4	347.3	0.642	1.59	0.00
	1531.6	1.1	79.8	189.0	0.056	253.1	2.23	24.00	0.284	1.851	2.399
Critical :		7.43									
	479.2	15.0	80.3	3.472	0.0	1.00e-3	36.4	278.3	0.512	1.59	0.00
	3517.9	0.4	80.1	189.0	0.049	254.1	2.23	24.00	0.284	2.095	2.952
0.1L :		7.60									
	476.8	15.0	80.3	3.472	0.0	1.00e-3	36.4	275.6	0.507	1.59	1.60
	3593.5	0.4	80.1	189.0	0.049	254.1	2.23	24.00	0.284	2.106	2.974
0.2L :		15.20									
	367.4	15.0	80.3	7.378	0.0	-0.01e-3	21.6	0.0	0.284	1.59	4.75
	6108.9	0.8	79.9	189.0	0.038	434.6	3.82	24.00	0.284	4.978	4.265
0.3L :		22.80									
	262.2	15.0	80.3	7.378	0.0	0.02e-3	22.3	0.0	0.284	1.06	0.00
	7601.4	1.0	79.8	189.0	0.027	414.3	3.65	24.00	0.284	4.950	6.125
0.4L :		30.40									
	177.7	15.0	80.3	7.378	0.0	0.01e-3	22.0	0.0	0.284	1.06	0.00
	8124.1	1.1	79.8	189.0	0.018	420.2	3.70	24.00	0.284	7.401	7.378
0.5L :		38.00									
	176.9	15.0	80.3	7.378	0.0	0.01e-3	22.1	0.0	0.284	1.06	0.00
	8137.9	1.1	79.8	189.0	0.018	418.8	3.69	24.00	0.284	7.412	7.378
0.6L :		45.60									
	281.7	15.0	80.3	7.378	0.0	0.01e-3	21.9	0.0	0.284	1.06	0.00
	7413.9	1.1	79.8	189.0	0.029	423.2	3.73	24.00	0.284	4.700	7.378
0.7L :		53.20									
	384.7	15.0	80.3	7.378	0.0	-0.01e-3	21.6	0.0	0.284	1.06	0.00
	5827.2	1.0	79.8	189.0	0.040	435.9	3.84	24.00	0.284	3.510	6.125
0.8L :		60.80									
	485.0	15.0	80.3	7.378	0.0	-0.04e-3	21.2	83.3	0.284	1.59	1.13
	3463.2	0.8	79.9	189.0	0.050	455.6	4.01	24.00	0.284	3.875	4.265



Program: LEAP@
CONSPAN@
Version: 08.01.00.10

Copyright © Bentley Systems, Inc. 1984 - 2008.
www.bentley.com
1-800-778-4277

By: A. Pott
Date: Jan/4/2010
CKD:
Date:

File Name: 76-21-125-21-124 U72C.csl

Location(ft)											
Vu (kips)	bv (in)	de (in)	Aps (in ²)	Vp (kips)	eps_x	Theta	Vs-reqd (kips)	Av/s (in ² /ft)	Av-prvd (in ² /ft)	Al_reqd (in ²)	
Mcor (kft)	a (in)	dv (in)	fpo (ksi)	vu/fc	Vc-com (kips)	Beta	Max.spc. (in)	min.Av/s (in ² /ft)	pVn/Vu	Aps* (in ²)	
0.9L :											
581.6	15.0	80.3	3.472	0.0	1.00e-3	36.4	392.1	0.722	1.59	0.00	
433.6	0.4	80.1	189.0	0.060	254.1	2.23	24.00	0.284	1.726	2.974	
Critical :											
583.9	15.0	80.3	3.472	0.0	1.00e-3	36.4	394.7	0.726	1.59	0.00	
348.2	0.4	80.1	189.0	0.060	254.1	2.23	24.00	0.284	1.720	2.949	
Transfer :											
635.4	15.0	80.4	0.000	0.0	1.00e-3	36.4	452.7	0.836	1.59	0.00	
-1563.6	1.1	79.9	189.0	0.065	253.3	2.23	24.00	0.284	1.575	2.699	
Bearing :											
661.8	15.0	80.4	0.000	0.0	1.00e-3	36.4	482.0	0.890	1.59	11.82	
-2612.2	1.1	79.9	47.2	0.068	253.3	2.23	24.00	0.284	1.513	0.675	

ANCHORAGE ZONE REINFORCEMENT (Art. 5.10.10)

Span : 1, Beam : 6

Fpi (kips)	fs (ksi)	h/4 (in)	Abrst_rqrd (in ²)
703.08	20.00	18.00	1.41

HORIZONTAL SHEAR (Art. 5.8.4) - Span : 1, Beam : 6

(Beam and Slab effects are INCLUDED in Vu).

Location (ft)									
Vu (kips)	Vnh-req (kips)	de (in)	a (in)	dv (in)	s_max (in)	Avh-min (in ² /ft)	Avh-sm (in ² /ft)	Avh-rg (in ² /ft)	
Bearing :									
571.5	7.96	80.34	1.06	79.81	24.00	0.640	1.043	0.000	
Transfer :									
540.4	7.52	80.34	1.06	79.81	24.00	0.640	0.899	0.000	
Critical :									
479.2	6.65	80.34	0.43	80.12	24.00	0.640	0.606	0.000	
0.1L :									
476.8	6.61	80.34	0.44	80.12	24.00	0.640	0.595	0.000	



Program: LEAP®
CONSPAN®
Version: 08.01.00.10

Copyright © Bentley Systems, Inc. 1984 - 2008.
www.bentley.com
1-800-778-4277

By: A. Pott
Date: Jan/4/2010
CKD:
Date:

File Name: 76-21-125-21-124_U72C.csl

Location (ft)	Vu (kips)	Vnh-req (kips)	de (in)	a (in)	dv (in)	s_max (in)	Avh-min (in2/ft)	Avh-sm (in2/ft)	Avh-rg (in2/ft)	
0.2L :	367.4	14.45	5.11	80.34	0.84	79.92	24.00	0.640	0.094	0.000
0.3L :	262.2	22.05	3.65	80.34	1.02	79.83	24.00	0.640	0.000	0.000
0.4L :	177.7	29.65	2.47	80.34	1.08	79.80	24.00	0.640	0.000	0.000
0.5L :	176.9	37.25	2.46	80.34	1.08	79.80	24.00	0.640	0.000	0.000
0.6L :	281.7	44.85	3.92	80.34	1.08	79.80	24.00	0.640	0.000	0.000
0.7L :	384.7	52.45	5.35	80.34	1.02	79.83	24.00	0.640	0.176	0.000
0.8L :	485.0	60.05	6.74	80.34	0.84	79.92	24.00	0.640	0.639	0.000
0.9L :	581.6	67.65	8.07	80.34	0.44	80.12	24.00	0.640	1.080	0.000
Critical :	583.6	67.82	8.09	80.34	0.43	80.12	24.00	0.640	1.089	0.000
Transfer :	635.4	72.25	8.84	80.40	1.06	79.87	24.00	0.640	1.338	0.000
Bearing :	661.8	74.50	9.21	80.40	1.06	79.87	24.00	0.640	1.460	0.000



Program: LEAP®
CONSPAN®
Version: 08.01.00.10
File Name: 76-21-125-21-124 U72C_rev1.csl

Copyright © Bentley Systems, Inc. 1984 - 2008.
www.bentley.com
1-800-778-4277

By: A. Pott
Date: Jan/22/2009
CKD:
Date:

SHEAR/MOMENT ENVELOPE (&REACTIONS)

SHEAR AND MOMENT ENVELOPE : Span : 1, Beam : 3, SERVICE I
Shears: kips, Moments: kft

Location,	ft	Bearing	Trans	H/2	0.10L	0.20L	0.30L	0.40L	Midspan
Self wt. :	M	0.0	149.4	229.5	426.0	797.7	1063.2	1222.5	1275.6
(Max)	V	68.5	64.4	62.0	55.9	41.9	27.9	14.0	0.0
DL-Prec. :	M	0.0	48.8	74.9	139.0	260.3	347.0	398.9	416.3
DC(Max)	V	22.4	21.0	20.2	18.2	13.7	9.1	4.6	0.0
DL-Prec. :	M	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0
DW(Max)	V	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0
Deck + :	M	0.0	227.0	348.6	647.2	1211.9	1615.3	1857.3	1938.0
Haunch (Max)	V	104.1	97.8	94.2	84.9	63.7	42.5	21.2	0.0
Diaphragm :	M	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0
(Max)	V	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0
DL-Comp :	M	7.4	20.0	26.6	42.7	71.7	89.9	97.3	94.0
DC(Max)	V	5.8	5.4	5.1	4.5	3.1	1.7	0.3	1.2
DL-Comp :	M	35.1	94.9	126.5	203.0	340.7	427.1	462.3	446.4
DW(Max)	V	27.5	25.6	24.4	21.5	14.7	8.0	1.3	5.5
LL + I :	M+	151.0	463.0	625.4	1006.9	1628.8	1955.0	2044.3	1932.4
	V	39.7	71.5	89.4	136.6	38.7	15.7	26.6	81.5
LL + I :	M-	-1.4	-4.0	-5.5	-9.3	-18.1	-26.8	-35.6	-44.4
	V	30.1	20.7	15.3	1.3	1.3	1.3	1.3	1.3
LL + I :	Vmx	159.6	152.2	148.1	137.2	109.9	85.0	71.9	95.6
	M	178.9	475.9	628.9	983.0	1526.2	1752.3	1691.8	1607.7
Total :	M+	193.5	1003.1	1431.5	2464.9	4311.1	5497.5	6082.7	6102.5
	V	267.9	285.6	295.5	321.7	175.8	104.9	67.8	88.1
Total :	M-	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0
	V	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0
Total :	Vmx	387.8	366.3	354.2	322.3	247.0	174.2	113.2	102.2
	M	221.4	1016.0	1435.1	2441.0	4208.5	5294.8	5730.1	5777.9

Location,	ft	0.60L	0.70L	0.80L	0.90L	H/2	Trans	Bearing
Self wt. :	M	1222.5	1063.2	797.7	426.0	229.5	149.4	0.0
(Max)	V	14.0	27.9	41.9	55.9	62.0	64.4	68.5
DL-Prec. :	M	398.9	347.0	260.3	139.0	74.9	48.8	0.0
DC(Max)	V	4.6	9.1	13.7	18.2	20.2	21.0	22.4
DL-Prec. :	M	0.0	0.0	0.0	0.0	0.0	0.0	0.0
DW(Max)	V	0.0	0.0	0.0	0.0	0.0	0.0	0.0
Deck + :	M	1857.3	1615.3	1211.9	647.2	348.6	227.0	0.0
Haunch (Max)	V	21.2	42.5	63.7	84.9	94.2	97.8	104.1
Diaphragm :	M	0.0	0.0	0.0	0.0	0.0	0.0	0.0
(Max)	V	0.0	0.0	0.0	0.0	0.0	0.0	0.0
DL-Comp :	M	79.8	54.9	19.2	-27.2	-48.6	-58.3	-77.5
DC(Max)	V	2.6	4.0	5.4	6.8	7.4	7.7	8.1
DL-Comp :	M	379.2	260.9	91.4	-129.3	-231.1	-276.9	-368.1
DW(Max)	V	12.2	18.9	25.7	32.4	35.4	36.5	38.5
LL + I :	M+	1611.6	1095.7	596.3	347.9	326.7	332.7	362.3
	V	107.5	131.5	60.0	9.5	7.8	7.1	6.0
LL + I :	M-	-53.1	-61.9	-326.7	-1247.1	-1753.1	-1961.7	-2354.6
	V	1.3	1.3	94.6	158.1	175.8	182.5	194.4
LL + I :	Vmx	120.3	144.0	166.1	186.1	192.9	195.6	200.2



Program: LEAP@
CONSPAN@
Version: 08.01.00.10

Copyright © Bentley Systems, Inc. 1984 - 2008.
www.bentley.com
1-800-778-4277

By: A. Pott
Date: Jan/22/2009
CKD:
Date:

File Name: 76-21-125-21-124 U72C rev1.csl

		0.60L	0.70L	0.80L	0.90L	H/2	Trans	Bearing
Total :	M	1369.6	905.9	265.5	-487.8	-801.6	-918.3	-1121.8
	M+	5549.4	4437.0	2976.9	1403.6	700.0	422.7	0.0
	V	162.1	234.0	210.4	207.7	227.1	234.4	0.0
Total :	M-	0.0	0.0	0.0	-191.4	-1379.7	-1871.6	-2800.1
	V	0.0	0.0	0.0	330.8	395.1	409.8	435.9
Total :	Vmx	174.8	246.4	316.4	384.4	412.2	422.8	441.7
	M	5307.4	4247.2	2646.1	567.9	-428.3	-828.2	-1567.4

REACTIONS (kips), SERVICE I

Load Type		Left Support	Right Support
Self Wt.		68.5	68.5
Deck+Haunch		104.1	104.1
Diaphragm		0.0	0.0
DL-Prec.(DC)		22.4	22.4
DL-Prec.(DW)		0.0	0.0
DL-Comp.(DC)		47.5	25.5
DL-Comp.(DW)		225.8	121.3
Live	(Max)	80.8	179.7
Live	(Min)	-0.6	-125.6
Pedestrian	(Max)	-0.0	-0.0
Pedestrian	(Min)	-0.0	-0.0

Upward reactions are positive.

Live Load reactions are per lane with no distribution factor and no impact.

Non-composite load types are per beam.

Composite and Pedestrian load types are per total bridge width.

SHEAR AND MOMENT ENVELOPE : Span : 1, Beam : 3, SERVICE III

Shears: kips, Moments: kft

Location,	ft	Bearing	Trans	H/2	0.10L	0.20L	0.30L	0.40L	Midspan
Self wt. :	M	0.0	149.4	229.5	426.0	797.7	1063.2	1222.5	1275.6
(Max)	V	68.5	64.4	62.0	55.9	41.9	27.9	14.0	0.0
DL-Prec. :	M	0.0	48.8	74.9	139.0	260.3	347.0	398.9	416.3
DC(Max)	V	22.4	21.0	20.2	18.2	13.7	9.1	4.6	0.0
DL-Prec. :	M	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0
DW(Max)	V	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0
Deck + :	M	0.0	227.0	348.6	647.2	1211.9	1615.3	1857.3	1938.0
Haunch (Max)	V	104.1	97.8	94.2	84.9	63.7	42.5	21.2	0.0
Diaphragm :	M	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0
(Max)	V	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0
DL-Comp :	M	7.4	20.0	26.6	42.7	71.7	89.9	97.3	94.0
DC(Max)	V	5.8	5.4	5.1	4.5	3.1	1.7	0.3	1.2
DL-Comp :	M	35.1	94.9	126.5	203.0	340.7	427.1	462.3	446.4
DW(Max)	V	27.5	25.6	24.4	21.5	14.7	8.0	1.3	5.5
LL + I :	M+	120.8	370.4	500.3	805.5	1303.0	1564.0	1635.5	1545.9
	V	31.7	57.2	71.6	109.3	30.9	12.5	11.2	65.2



Program: LEAP®
CONSPAN®
Version: 08.01.00.10

Copyright © Bentley Systems, Inc. 1984 - 2008.
www.bentley.com
1-800-778-4277

By: A. Pott
Date: Jan/22/2009
CKD:
Date:

File Name: 76-21-125-21-124 U72C_rev1.csl

		Bearing	Trans	H/2	0.10L	0.20L	0.30L	0.40L	Midspan
LL + I :	M-	-1.2	-3.2	-4.4	-7.5	-14.5	-21.5	-28.5	-35.5
	V	24.1	16.5	12.3	1.0	1.0	1.0	1.0	1.0
LL + I :	Vmx	127.7	121.8	118.5	109.8	87.9	68.0	57.5	76.5
	M	143.1	380.7	503.1	786.4	1221.0	1401.9	1353.4	1286.2
Total :	M+	163.3	910.5	1306.5	2263.5	3985.3	5106.5	5673.9	5716.1
	V	260.0	271.3	277.6	294.4	168.1	101.7	62.5	71.8
Total :	M-	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0
	V	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0
Total :	Vmx	355.9	335.8	324.5	294.8	225.0	157.2	98.8	83.1
	M	185.6	920.8	1309.3	2244.4	3903.3	4944.3	5391.8	5456.4

		0.60L	0.70L	0.80L	0.90L	H/2	Trans	Bearing
Location,	ft	44.85	52.45	60.05	67.65	70.98	72.25	74.50
Self wt. :	M	1222.5	1063.2	797.7	426.0	229.5	149.4	0.0
(Max)	V	14.0	27.9	41.9	55.9	62.0	64.4	68.5
DL-Prec. :	M	398.9	347.0	260.3	139.0	74.9	48.8	0.0
DC(Max)	V	4.6	9.1	13.7	18.2	20.2	21.0	22.4
DL-Prec. :	M	0.0	0.0	0.0	0.0	0.0	0.0	0.0
DW(Max)	V	0.0	0.0	0.0	0.0	0.0	0.0	0.0
Deck + :	M	1857.3	1615.3	1211.9	647.2	348.6	227.0	0.0
Haunch (Max)	V	21.2	42.5	63.7	84.9	94.2	97.8	104.1
Diaphragm :	M	0.0	0.0	0.0	0.0	0.0	0.0	0.0
(Max)	V	0.0	0.0	0.0	0.0	0.0	0.0	0.0
DL-Comp :	M	79.8	54.9	19.2	-27.2	-48.6	-58.3	-77.5
DC(Max)	V	2.6	4.0	5.4	6.8	7.4	7.7	8.1
DL-Comp :	M	379.2	260.9	91.4	-129.3	-231.1	-276.9	-368.1
DW(Max)	V	12.2	18.9	25.7	32.4	35.4	36.5	38.5
LL + I :	M+	1289.3	876.6	477.0	278.3	261.3	266.1	289.8
	V	86.0	105.2	48.0	7.6	6.2	5.7	4.8
LL + I :	M-	-42.5	-49.5	-261.4	-997.6	-1402.5	-1569.4	-1883.7
	V	1.0	1.0	75.7	126.5	140.6	146.0	155.6
LL + I :	Vmx	96.2	115.2	132.9	148.9	154.4	156.4	160.1
	M	1095.7	724.7	212.4	-390.2	-641.3	-734.6	-897.5
Total :	M+	5227.1	4217.8	2857.6	1334.0	634.7	356.2	0.0
	V	140.5	207.7	198.4	205.8	225.5	233.0	0.0
Total :	M-	0.0	0.0	0.0	0.0	-1029.1	-1479.3	-2329.2
	V	0.0	0.0	0.0	0.0	359.9	373.3	397.0
Total :	Vmx	150.8	217.6	283.2	347.1	373.7	383.7	401.6
	M	5033.5	4066.0	2593.0	665.4	-268.0	-644.5	-1343.0

SHEAR AND MOMENT ENVELOPE : Span : 1, Beam : 3, STRENGTH I
Shears: kips, Moments: kft

		Bearing	Trans	H/2	0.10L	0.20L	0.30L	0.40L	Midspan
Location,	ft	0.00	2.25	3.52	6.85	14.45	22.05	29.65	37.25
Self wt. :	M	0.0	186.8	286.9	532.5	997.1	1329.0	1528.1	1594.5
(Max)	V	85.6	80.4	77.5	69.9	52.4	34.9	17.5	0.0
Self wt. :	M	0.0	134.5	206.5	383.4	717.9	956.9	1100.3	1148.1
(Min)	V	61.6	57.9	55.8	50.3	37.7	25.2	12.6	0.0
DL-Prec. :	M	0.0	61.0	93.6	173.8	325.4	433.7	498.7	520.3
DC(Max)	V	27.9	26.3	25.3	22.8	17.1	11.4	5.7	0.0



Program: LEAP®
CONSPAN®
Version: 08.01.00.10

Copyright © Bentley Systems, Inc. 1984 - 2008.
www.bentley.com
1-800-778-4277

By: A. Pott
Date: Jan/22/2009
CKD:
Date:

File Name: 76-21-125-21-124 U72C_rev1.csl

		Bearing	Trans	H/2	0.10L	0.20L	0.30L	0.40L	Midspan
DL-Prec. :	M	0.0	43.9	67.4	125.1	234.3	312.3	359.0	374.6
DC(Min)	V	20.1	18.9	18.2	16.4	12.3	8.2	4.1	0.0
DL-Prec. :	M	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0
DW(Max)	V	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0
DL-Prec. :	M	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0
DW(Min)	V	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0
Deck + :	M	0.0	283.8	435.8	809.0	1514.9	2019.1	2321.6	2422.5
Haunch (Max)	V	130.1	122.2	117.8	106.1	79.6	53.1	26.5	0.0
Deck + :	M	0.0	204.3	313.8	582.5	1090.7	1453.7	1671.6	1744.2
Haunch (Min)	V	93.6	88.0	84.8	76.4	57.3	38.2	19.1	0.0
Diaphragm :	M	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0
(Max)	V	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0
Diaphragm :	M	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0
(Min)	V	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0
DL-Comp :	M	9.2	25.0	33.3	53.4	89.6	112.4	121.6	117.4
DC(Max)	V	7.2	6.7	6.4	5.7	3.9	2.1	0.3	1.4
DL-Comp :	M	6.7	18.0	24.0	38.5	64.5	80.9	87.6	84.6
DC(Min)	V	5.2	4.8	4.6	4.1	2.8	1.5	0.2	1.0
DL-Comp :	M	52.7	142.3	189.8	304.6	511.0	640.6	693.5	669.6
DW(Max)	V	41.3	38.3	36.6	32.2	22.1	12.0	1.9	8.2
DL-Comp :	M	22.8	61.7	82.2	132.0	221.4	277.6	300.5	290.1
DW(Min)	V	17.9	16.6	15.9	14.0	9.6	5.2	0.8	3.6
LL + I :	M+	264.3	810.3	1094.4	1762.0	2850.3	3421.3	3577.6	3381.6
	V	69.4	125.2	156.5	239.1	67.6	27.4	46.5	142.5
LL + I :	M-	-2.5	-7.1	-9.6	-16.3	-31.7	-47.0	-62.3	-77.6
	V	52.7	36.1	26.8	2.3	2.3	2.3	2.3	2.3
LL + I :	Vmx	279.3	266.4	259.2	240.1	192.3	148.7	125.7	167.2
	M	313.1	832.8	1100.6	1720.2	2670.9	3066.5	2960.6	2813.6
Total :	M+	326.2	1509.1	2133.7	3635.3	6288.4	7956.1	8741.2	8706.0
	V	361.6	399.1	420.2	475.8	242.7	140.9	98.4	152.2
Total :	M-	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0
	V	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0
Total :	Vmx	571.5	540.4	522.9	476.8	367.4	262.2	177.7	176.9
	M	375.0	1531.6	2139.9	3593.5	6108.9	7601.4	8124.1	8137.9

		0.60L	0.70L	0.80L	0.90L	H/2	Trans	Bearing
Location,	ft	44.85	52.45	60.05	67.35	70.98	72.25	74.50
Self wt. :	M	1528.1	1329.0	997.1	532.5	286.9	186.8	0.0
(Max)	V	17.5	34.9	52.4	69.9	77.5	80.4	85.6
Self wt. :	M	1100.3	956.9	717.9	383.4	206.5	134.5	0.0
(Min)	V	12.6	25.2	37.7	50.3	55.8	57.9	61.6
DL-Prec. :	M	498.7	433.7	325.4	173.8	93.6	61.0	0.0
DC(Max)	V	5.7	11.4	17.1	22.8	25.3	26.2	27.9
DL-Prec. :	M	359.0	312.3	234.3	125.1	67.4	43.9	0.0
DC(Min)	V	4.1	8.2	12.3	16.4	18.2	18.9	20.1
DL-Prec. :	M	0.0	0.0	0.0	0.0	0.0	0.0	0.0
DW(Max)	V	0.0	0.0	0.0	0.0	0.0	0.0	0.0
DL-Prec. :	M	0.0	0.0	0.0	0.0	0.0	0.0	0.0
DW(Min)	V	0.0	0.0	0.0	0.0	0.0	0.0	0.0
Deck + :	M	2321.6	2019.1	1514.9	809.0	435.8	283.8	0.0
Haunch (Max)	V	26.5	53.1	79.6	106.1	117.8	122.2	130.1
Deck + :	M	1671.6	1453.7	1090.7	582.5	313.8	204.3	0.0
Haunch (Min)	V	19.1	38.2	57.3	76.4	94.8	88.0	93.6
Diaphragm :	M	0.0	0.0	0.0	0.0	0.0	0.0	0.0
(Max)	V	0.0	0.0	0.0	0.0	0.0	0.0	0.0
Diaphragm :	M	0.0	0.0	0.0	0.0	0.0	0.0	0.0
(Min)	V	0.0	0.0	0.0	0.0	0.0	0.0	0.0



Program: LEAP®
CONSPAN®
Version: 08.01.00.10
File Name: 76-21-125-21-124 U72C_rev1.csl

Copyright © Bentley Systems, Inc. 1984 - 2008.
www.bentley.com
1-800-778-4277

By: A. Pott
Date: Jan/22/2009
CKD:
Date:

		0.60L	0.70L	0.80L	0.90L	H/2	Trans	Bearing
DL-Comp :	M	99.8	68.6	24.0	-34.0	-60.8	-72.9	-96.8
DC(Max)	V	3.2	5.0	6.8	8.5	9.3	9.6	10.1
DL-Comp :	M	71.8	49.4	17.3	-24.5	-43.8	-52.5	-69.7
DC(Min)	V	2.3	3.6	4.9	6.1	6.7	6.9	7.3
DL-Comp :	M	568.9	391.4	137.1	-194.0	-346.6	-415.3	-552.1
DW(Max)	V	18.3	28.4	38.5	48.6	53.0	54.7	57.7
DL-Comp :	M	246.5	169.6	59.4	-84.1	-150.2	-180.0	-239.3
DW(Min)	V	7.9	12.3	16.7	21.1	23.0	23.7	25.0
LL + I :	M+	2820.3	1917.5	1043.5	608.8	571.7	582.1	634.0
	V	188.2	230.1	105.1	16.5	13.6	12.5	10.5
LL + I :	M-	-93.0	-108.3	-571.7	-2182.4	-3067.9	-3433.0	-4120.5
	V	2.3	2.3	165.6	276.6	307.6	319.4	340.3
LL + I :	Vmx	210.5	251.9	290.6	325.6	337.7	342.2	350.3
	M	2396.8	1585.4	464.6	-853.6	-1402.9	-1607.0	-1963.2
Total :	M+	7837.4	6159.3	4042.1	2015.6	1194.0	881.3	325.0
	V	259.4	362.9	299.5	272.5	263.9	272.0	286.4
Total :	M-	0.0	0.0	0.0	-1319.4	-2887.5	-3538.5	-4769.5
	V	0.0	0.0	0.0	430.3	528.8	548.5	583.5
Total :	Vmx	281.7	384.7	485.0	581.6	620.6	635.4	661.8
	M	7413.9	5827.2	3463.2	433.6	-994.0	-1563.6	-2612.2

REACTIONS (kips), STRENGTH I

Load Type		Left Support	Right Support
Self Wt.		85.6	85.6
Deck+Haunch		130.1	130.1
Diaphragm		0.0	0.0
DL-Prec.(DC)		27.9	27.9
DL-Prec.(DW)		0.0	0.0
DL-Comp.(DC)		59.4	31.9
DL-Comp.(DW)		338.7	182.0
Live	(Max)	141.3	314.4
Live	(Min)	-1.1	-219.9
Pedestrian	(Max)	-0.0	-0.0
Pedestrian	(Min)	-0.0	-0.0

Upward reactions are positive.
Live Load reactions are per lane with no distribution factor and no impact.
Non-composite load types are per beam.
Composite and Pedestrian load types are per total bridge width.



Program: LEAP®
CONSPAN®
Version: 08.01.00.10
File Name: 76-21-125-21-124 U72C.csl

Copyright © Bentley Systems, Inc. 1984 - 2008.
www.bentley.com
1-800-778-4277

By: A. Pott
Date: Jan/4/2010
CKD:
Date:

VERTICAL/HORIZONTAL SHEAR

VERTICAL SHEAR (Art. 5.8) - Span : 1, Beam : 2, STRENGTH I

Using General Beta Theta Tables procedure - Art.5.8.3.4.2

Location(ft)	Vu (kips)	bv (in)	de (in)	Aps (in ²)	Vp (kips)	eps_x	Theta	Vs-reqd (kips)	Av/s (in ² /ft)	Av-prvd (in ² /ft)	Al reqd (in ²)
Mcor (kft)	a (in)	dv (in)	fpo (ksi)	vu/fc	Vc-com (kips)	Beta	Max.spc. (in)	min.Av/s (in ² /ft)	pVn/Vu	Aps* (in ²)	
Bearing :	0.75										
543.5	15.0	80.7	1.060	0.0	1.00e-3	36.4	349.5	0.642	1.59	3.79	
375.0	1.1	80.2	47.2	0.056	254.4	2.23	24.00	0.284	1.850	0.676	
Transfer :	3.00										
514.1	15.0	80.7	3.906	0.0	1.00e-3	36.4	316.8	0.582	1.59	0.00	
1470.7	1.1	80.2	189.0	0.053	254.4	2.23	24.00	0.284	1.955	2.703	
Critical :	7.46										
455.9	15.0	80.7	3.906	0.0	0.98e-3	36.2	249.9	0.455	1.59	0.00	
3361.2	0.5	80.5	189.0	0.047	256.6	2.24	24.00	0.284	2.227	3.329	
0.1L :	7.60										
454.0	15.0	80.7	3.906	0.0	1.00e-3	36.4	249.1	0.456	1.59	0.00	
3419.7	0.5	80.5	189.0	0.046	255.3	2.23	24.00	0.284	2.222	3.349	
0.2L :	15.20										
350.3	15.0	80.9	6.510	0.0	-0.00e-3	21.8	0.0	0.284	1.59	2.60	
5783.5	0.8	80.5	189.0	0.036	431.1	3.76	24.00	0.284	5.216	4.435	
0.3L :	22.80										
250.8	15.0	81.0	6.944	0.0	0.02e-3	22.1	0.0	0.284	1.06	0.00	
7167.7	1.0	80.5	189.0	0.026	422.0	3.68	24.00	0.284	5.268	5.821	
0.4L :	30.40										
172.0	15.0	81.0	6.944	0.0	-0.00e-3	21.8	0.0	0.284	1.06	0.00	
7625.5	1.0	80.5	189.0	0.018	429.7	3.75	24.00	0.284	7.812	6.941	
0.5L :	38.00										
176.9	15.0	81.0	6.944	0.0	-0.00e-3	21.8	0.0	0.284	1.06	0.00	
7617.5	1.0	80.5	189.0	0.018	429.5	3.75	24.00	0.284	7.593	6.944	
0.6L :	45.60										
276.0	15.0	81.0	6.944	0.0	-0.00e-3	21.8	0.0	0.284	1.06	0.00	
6915.2	1.0	80.5	189.0	0.028	429.9	3.75	24.00	0.284	4.869	6.941	
0.7L :	53.20										
373.3	15.0	81.0	6.944	0.0	-0.01e-3	21.6	0.0	0.284	1.06	0.00	
5393.5	1.0	80.5	189.0	0.038	439.9	3.84	24.00	0.284	3.650	5.821	
0.8L :	60.80										
467.9	15.0	80.9	6.510	0.0	-0.03e-3	21.4	67.8	0.284	1.59	0.00	
3137.8	0.8	80.5	189.0	0.048	452.1	3.95	24.00	0.284	4.012	4.435	



Program: LEAP®
CONSPAN®
Version: 08.01.00.10

Copyright © Bentley Systems, Inc. 1984 - 2008.
www.bentley.com
1-800-778-4277

By: A. Pott
Date: Jan/4/2010
CKD:
Date:

File Name: 76-21-125-21-124 U72C.csl

Location(ft)										
Vu (kips)	bv (in)	de (in)	Aps (in ²)	Vp (kips)	eps_x	Theta	Vs-reqd (kips)	Av/s (in ² /ft)	Av-prvd (in ² /ft)	Al_reqd (in ²)
Mcor (kft)	a (in)	dv (in)	fpo (ksi)	vu/fc	Vc-com (kips)	Beta	Max.spc. (in)	min.Av/s (in ² /ft)	pVn/Vu	Aps* (in ²)
0.9L :										
558.8	15.0	80.7	3.906	0.0	1.00e-3	36.4	365.6	0.670	1.59	0.00
259.8	0.5	80.5	189.0	0.057	255.3	2.23	24.00	0.284	1.805	3.349
Critical :										
560.6	15.0	80.7	3.906	0.0	1.00e-3	36.4	367.6	0.673	1.59	0.00
192.9	0.5	80.5	189.0	0.057	255.3	2.23	24.00	0.284	1.800	3.325
Transfer :										
609.2	15.0	80.4	0.000	0.0	1.00e-3	36.4	423.5	0.782	1.59	2.28
-1624.5	1.1	79.9	189.0	0.063	253.4	2.23	24.00	0.284	1.643	2.103
Bearing :										
633.8	15.0	80.4	0.000	0.0	1.00e-3	36.4	450.9	0.832	1.59	12.14
-2612.2	1.1	79.9	47.2	0.065	253.4	2.23	24.00	0.284	1.579	0.526

ANCHORAGE ZONE REINFORCEMENT (Art. 5.10.10)

Span : 1, Beam : 2

Fpi (kips)	fs (ksi)	h/4 (in)	Abrst_rqrd (in ²)
790.96	20.00	18.00	1.58

HORIZONTAL SHEAR (Art. 5.8.4) - Span : 1, Beam : 2

(Beam and Slab effects are INCLUDED in Vu).

Location (ft)								
Vu (kips)	Vnh-req (kips)	de (in)	a (in)	dv (in)	s_max (in)	Avh-min (in ² /ft)	Avh-sm (in ² /ft)	Avh-rg (in ² /ft)
Bearing :								
543.5	7.53	80.74	1.05	80.21	24.00	0.640	0.901	0.000
Transfer :								
514.1	7.12	80.74	1.05	80.21	24.00	0.640	0.765	0.000
Critical :								
455.9	6.29	80.74	0.49	80.50	24.00	0.640	0.488	0.000
0.1L :								
454.0	6.27	80.74	0.49	80.49	24.00	0.640	0.480	0.000



Program: LEAP®
CONSPAN®
Version: 08.01.00.10

Copyright © Bentley Systems, Inc. 1984 - 2008.
www.bentley.com
1-800-778-4277

By: A. Pott
Date: Jan/4/2010
CKD:
Date:

File Name: 76-21-125-21-124_U72C.csl

Location (ft)	Vu (kips)	Vnh-req (kips)	de (in)	a (in)	dv (in)	s_max (in)	Avh-min (in2/ft)	Avh-sm (in2/ft)	Avh-rg (in2/ft)
0.2L :	350.3	14.45	80.94	0.79	80.55	24.00	0.640	0.002	0.000
0.3L :	250.8	22.05	81.02	0.97	80.53	24.00	0.640	0.000	0.000
0.4L :	172.0	29.65	81.02	1.02	80.51	24.00	0.640	0.000	0.000
0.5L :	176.9	37.25	81.02	1.02	80.51	24.00	0.640	0.000	0.000
0.6L :	276.0	44.85	81.02	1.02	80.51	24.00	0.640	0.000	0.000
0.7L :	373.3	52.45	81.02	0.97	80.53	24.00	0.640	0.108	0.000
0.8L :	467.9	60.05	80.94	0.79	80.55	24.00	0.640	0.543	0.000
0.9L :	558.8	67.65	80.74	0.49	80.49	24.00	0.640	0.962	0.000
Critical :	560.4	67.79	80.74	0.49	80.50	24.00	0.640	0.969	0.000
Transfer :	609.2	72.25	80.40	1.05	79.87	24.00	0.640	1.216	0.000
Bearing :	633.8	74.50	80.40	1.05	79.87	24.00	0.640	1.330	0.000



Program: LEAP®
CONSPAN®
Version: 08.01.00.10
File Name: 76-21-125-21-124 U72C.csl

Copyright © Bentley Systems, Inc. 1984 - 2008.
www.bentley.com
1-800-778-4277

By: A. Pott
Date: Jan/4/2010
CKD:
Date:

ULTIMATE MOMENT

ULTIMATE - Span : 1, Beam : 2, STRENGTH I
(Mr-prvd computed by AASHTO equations, Art. 5.7.3.2/5.7.3.3)

Location (ft)	dp in	Aps in ²	fps ksi	c in	a in	Mr-prvd k.ft	c/dt	Phi	1.2 Mcr k.ft	min Mr k.ft	Crkg Ratio	Mu-p/r Ratio
Transfer	2.25											
1448.1	80.7	2.703	269.5	0.6	0.4	4889.4	0.007T	1.00	-	-	-	-
H/2	3.52											
2040.1	80.7	2.881	269.4	0.6	0.4	5209.2	0.007T	1.00	-	-	-	-
0.1L	6.85											
3461.5	80.7	3.349	269.3	0.7	0.5	6049.8	0.009T	1.00	-	-	-	-
0.2L	14.45											
5963.0	80.8	5.404	268.9	1.1	0.8	9737.4	0.014T	1.00	13349.0	7930.8	0.9	1.63
0.3L	22.05											
7522.4	80.9	6.598	268.7	1.4	1.0	11885.5	0.017T	1.00	14339.4	10004.8	1.0	1.58
0.4L	29.65											
8242.5	81.0	6.943	268.6	1.5	1.0	12513.8	0.018T	1.00	14062.3	10962.5	1.1	1.52
0.5L	37.25											
8185.6	81.0	6.944	268.6	1.5	1.0	12515.3	0.018T	1.00	13970.0	10886.9	1.1	1.53
0.6L	44.85											
7338.7	81.0	6.943	268.6	1.5	1.0	12513.8	0.018T	1.00	14062.3	9760.5	1.1	1.71
0.7L	52.45											
5725.6	80.9	6.598	268.7	1.4	1.0	11885.5	0.017T	1.00	14339.4	7615.1	1.0	2.08
0.8L	60.05											
3716.7	80.8	5.404	268.9	1.1	0.8	9737.4	0.014T	1.00	13349.0	4943.2	0.9	2.62
0.9L	67.65											
1841.8	80.7	3.349	269.3	0.7	0.5	6049.8	0.009T	1.00	-	-	-	-
H/2	70.98											
1100.4	80.7	2.881	269.4	0.6	0.4	5209.2	0.007T	1.00	-	-	-	-
Transfer	72.25											
820.3	80.7	2.703	269.5	0.6	0.4	4889.4	0.007T	1.00	-	-	-	-

Legend: C = Compression-Controlled (c/dt > 0.600)
I = In-Transition (0.60 >= c/dt > 0.375)
T = Tension-Controlled (c/dt <= 0.375)

Note : fr used for calculating Mcr is computed using AASHTO method (Art.5.4.2.6.)



Program: LEAP®
CONSPAN®
Version: 08.01.00.10
File Name: 76-21-125-21-124_U72C.csl

Copyright © Bentley Systems, Inc. 1984 - 2008.
www.bentley.com
1-800-778-4277

By: A. Pott
Date: Jan/4/2010
CKD:
Date:

SHEAR/MOMENT ENVELOPE (&REACTIONS)

SHEAR AND MOMENT ENVELOPE : Span : 1, Beam : 2, SERVICE I
Shears: kips, Moments: kft

	ft	Bearing	Trans	H/2	0.10L	0.20L	0.30L	0.40L	Midspan
Location,	ft	0.00	2.25	3.52	6.85	14.45	22.05	29.65	37.25
Self wt. :	M	0.0	149.4	229.5	426.0	797.7	1063.2	1222.5	1275.6
(Max)	V	68.5	64.4	62.0	55.9	41.9	27.9	14.0	0.0
DL-Prec. :	M	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0
DC(Max)	V	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0
DL-Prec. :	M	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0
DW(Max)	V	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0
Deck + :	M	0.0	227.0	348.6	647.2	1211.9	1615.3	1857.3	1938.0
Haunch (Max)	V	104.1	97.8	94.2	84.9	63.7	42.5	21.2	0.0
Diaphragm :	M	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0
(Max)	V	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0
DL-Comp :	M	7.4	20.0	26.6	42.7	71.7	89.9	97.3	94.0
DC(Max)	V	5.8	5.4	5.1	4.5	3.1	1.7	0.3	1.2
DL-Comp :	M	35.1	94.9	126.5	203.0	340.7	427.1	462.3	446.4
DW(Max)	V	27.5	25.6	24.4	21.5	14.7	8.0	1.3	5.5
LL + I :	M+	151.0	463.0	625.4	1006.9	1628.8	1955.0	2044.3	1932.4
	V	39.7	71.5	89.4	136.6	38.7	15.7	26.6	81.5
LL + I :	M-	-1.4	-4.0	-5.5	-9.3	-18.1	-26.8	-35.6	-44.4
	V	30.1	20.7	15.3	1.3	1.3	1.3	1.3	1.3
LL + I :	Vmx	159.6	152.2	148.1	137.2	109.9	85.0	71.9	95.6
	M	178.9	475.9	628.9	983.0	1526.2	1752.3	1691.8	1607.7
Total :	M+	193.5	954.3	1356.7	2325.9	4050.8	5150.5	5683.8	5686.3
	V	245.6	264.6	275.3	303.4	162.1	95.8	63.3	88.1
Total :	M-	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0
	V	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0
Total :	Vmx	365.5	345.3	333.9	304.0	233.3	165.0	108.6	102.2
	M	221.4	967.2	1360.2	2302.0	3948.2	4947.8	5331.2	5361.7

	ft	0.60L	0.70L	0.80L	0.90L	H/2	Trans	Bearing
Location,	ft	44.85	52.45	60.05	67.65	70.98	72.25	74.50
Self wt. :	M	1222.5	1063.2	797.7	426.0	229.5	149.4	0.0
(Max)	V	14.0	27.9	41.9	55.9	62.0	64.4	68.5
DL-Prec. :	M	0.0	0.0	0.0	0.0	0.0	0.0	0.0
DC(Max)	V	0.0	0.0	0.0	0.0	0.0	0.0	0.0
DL-Prec. :	M	0.0	0.0	0.0	0.0	0.0	0.0	0.0
DW(Max)	V	0.0	0.0	0.0	0.0	0.0	0.0	0.0
Deck + :	M	1857.3	1615.3	1211.9	647.2	348.6	227.0	0.0
Haunch (Max)	V	21.2	42.5	63.7	84.9	94.2	97.8	104.1
Diaphragm :	M	0.0	0.0	0.0	0.0	0.0	0.0	0.0
(Max)	V	0.0	0.0	0.0	0.0	0.0	0.0	0.0
DL-Comp :	M	79.8	54.9	19.2	-27.2	-48.6	-58.3	-77.5
DC(Max)	V	2.6	4.0	5.4	6.8	7.4	7.7	8.1
DL-Comp :	M	379.2	260.9	91.4	-129.3	-231.1	-276.9	-368.1
DW(Max)	V	12.2	18.9	25.7	32.4	35.4	36.5	38.5
LL + I :	M+	1611.6	1095.7	596.3	347.9	326.7	332.7	362.3
	V	107.5	131.5	60.0	9.5	7.8	7.1	6.0
LL + I :	M-	-53.1	-61.9	-326.7	-1247.1	-1753.1	-1961.7	-2354.6
	V	1.3	1.3	94.6	158.1	175.8	182.5	194.4
LL + I :	Vmx	120.3	144.0	166.1	186.1	192.9	195.6	200.2



Program: LEAP®
CONSPAN®
Version: 08.01.00.10

Copyright © Bentley Systems, Inc. 1984 - 2008.
www.bentley.com
1-800-778-4277

By: A. Pott
Date: Jan/4/2010
CKD:
Date:

File Name: 76-21-125-21-124 U72C.csl

		0.60L	0.70L	0.80L	0.90L	H/2	Trans	Bearing
	M	1369.6	905.9	265.5	-487.8	-801.6	-918.3	-1121.8
Total :	M+	5150.5	4090.0	2716.5	1264.6	625.1	374.0	0.0
	V	157.5	224.8	196.7	189.5	206.8	213.4	0.0
Total :	M-	0.0	0.0	0.0	-330.4	-1454.6	-1920.4	-2800.1
	V	0.0	0.0	0.0	312.5	374.8	388.8	413.6
Total :	Vmx	170.3	237.3	302.8	366.1	392.0	401.8	419.3
	M	4908.5	3900.2	2385.7	428.9	-503.2	-876.9	-1567.4

REACTIONS (kips), SERVICE I

Load Type		Left Support	Right Support
Self Wt.		68.5	68.5
Deck+Haunch		104.1	104.1
Diaphragm		0.0	0.0
DL-Prec.(DC)		0.0	0.0
DL-Prec.(DW)		0.0	0.0
DL-Comp.(DC)		47.5	25.5
DL-Comp.(DW)		225.8	121.3
Live	(Max)	80.8	179.7
Live	(Min)	-0.6	-125.6
Pedestrian	(Max)	-0.0	-0.0
Pedestrian	(Min)	-0.0	-0.0

Upward reactions are positive.
Live Load reactions are per lane with no distribution factor and no impact.
Non-composite load types are per beam.
Composite and Pedestrian load types are per total bridge width.

SHEAR AND MOMENT ENVELOPE : Span : 1, Beam : 2, SERVICE III Shears: kips, Moments: kft

		Bearing	Trans	H/2	0.10L	0.20L	0.30L	0.40L	Midspan
Location,	ft	0.00	2.25	3.52	6.85	14.45	22.05	29.65	37.25
Self wt. :	M	0.0	149.4	229.5	426.0	797.7	1063.2	1222.5	1275.6
(Max)	V	68.5	64.4	62.0	55.9	41.9	27.9	14.0	0.0
DL-Prec. :	M	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0
DC(Max)	V	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0
DL-Prec. :	M	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0
DW(Max)	V	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0
Deck + :	M	0.0	227.0	348.6	647.2	1211.9	1615.3	1857.3	1938.0
Haunch (Max)	V	104.1	97.8	94.2	84.9	63.7	42.5	21.2	0.0
Diaphragm :	M	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0
(Max)	V	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0
DL-Comp. :	M	7.4	20.0	26.6	42.7	71.7	89.9	97.3	94.0
DC(Max)	V	5.8	5.4	5.1	4.5	3.1	1.7	0.3	1.2
DL-Comp. :	M	35.1	94.9	126.5	203.0	340.7	427.1	462.3	446.4
DW(Max)	V	27.5	25.6	24.4	21.5	14.7	8.0	1.3	5.5
LL + I :	M+	120.8	370.4	500.3	805.5	1303.0	1564.0	1635.5	1545.9
	V	31.7	57.2	71.6	109.3	30.9	12.5	21.2	65.2



Program: LEAP®
CONSPAN®
Version: 08.01.00.10

Copyright © Bentley Systems, Inc. 1984 - 2008.
www.bentley.com
1-800-778-4277

By: A. Pott
Date: Jan/4/2010
CKD:
Date:

File Name: 76-21-125-21-124 U72C.csl

		Bearing	Trans	H/2	0.10L	0.20L	0.30L	0.40L	Midspan
LL + I :	M-	-1.2	-3.2	-4.4	-7.5	-14.5	-21.5	-28.5	-35.5
	V	24.1	16.5	12.3	1.0	1.0	1.0	1.0	1.0
LL + I :	Vmx	127.7	121.8	118.5	109.8	87.9	68.0	57.5	76.5
	M	143.1	380.7	503.1	786.4	1221.0	1401.9	1353.4	1286.2
Total :	M+	163.3	861.7	1231.6	2124.5	3725.0	4759.5	5274.9	5299.8
	V	237.6	250.3	257.4	276.1	154.4	92.6	58.0	71.8
Total :	M-	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0
	V	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0
Total :	Vmx	333.6	314.8	304.3	276.6	211.3	148.1	94.2	83.1
	M	185.6	872.0	1234.4	2105.4	3643.0	4597.3	4992.9	5040.1

		0.60L	0.70L	0.80L	0.90L	H/2	Trans	Bearing
Location,	ft	44.85	52.45	60.05	67.65	70.98	72.25	74.50
Self wt. :	M	1222.5	1063.2	797.7	426.0	229.5	149.4	0.0
(Max)	V	14.0	27.9	41.9	55.9	62.0	64.4	68.5
DL-Prec. :	M	0.0	0.0	0.0	0.0	0.0	0.0	0.0
DC(Max)	V	0.0	0.0	0.0	0.0	0.0	0.0	0.0
DL-Prec. :	M	0.0	0.0	0.0	0.0	0.0	0.0	0.0
DW(Max)	V	0.0	0.0	0.0	0.0	0.0	0.0	0.0
Deck + :	M	1857.3	1615.3	1211.9	647.2	348.6	227.0	0.0
Haunch (Max)	V	21.2	42.5	63.7	84.9	94.2	97.8	104.1
Diaphragm :	M	0.0	0.0	0.0	0.0	0.0	0.0	0.0
(Max)	V	0.0	0.0	0.0	0.0	0.0	0.0	0.0
DL-Comp :	M	79.8	54.9	19.2	-27.2	-48.6	-58.3	-77.5
DC(Max)	V	2.6	4.0	5.4	6.8	7.4	7.7	8.1
DL-Comp :	M	379.2	260.9	91.4	-129.3	-231.1	-276.9	-368.1
DW(Max)	V	12.2	18.9	25.7	32.4	35.4	36.5	38.5
LL + I :	M+	1289.3	876.6	477.0	278.3	261.3	266.1	289.8
	V	86.0	105.2	48.0	7.6	6.2	5.7	4.8
LL + I :	M-	-42.5	-49.5	-261.4	-997.6	-1402.5	-1569.4	-1883.7
	V	1.0	1.0	75.7	126.5	140.6	146.0	155.6
LL + I :	Vmx	96.2	115.2	132.9	148.9	154.4	156.4	160.1
	M	1095.7	724.7	212.4	-390.2	-641.3	-734.6	-897.5
Total :	M+	4828.2	3870.9	2597.3	1195.0	559.8	307.4	0.0
	V	136.0	198.5	184.7	187.6	205.3	212.0	0.0
Total :	M-	0.0	0.0	0.0	-81.0	-1104.0	-1528.1	-2329.2
	V	0.0	0.0	0.0	280.9	339.7	352.3	374.7
Total :	Vmx	146.2	208.5	269.5	328.9	353.4	362.7	379.3
	M	4634.6	3719.1	2332.6	526.4	-342.9	-693.3	-1343.0

SHEAR AND MOMENT ENVELOPE : Span : 1, Beam : 2, STRENGTH I
Shears: kips, Moments: kft

		Bearing	Trans	H/2	0.10L	0.20L	0.30L	0.40L	Midspan
Location,	ft	0.00	2.25	3.52	6.85	14.45	22.05	29.65	37.25
Self wt. :	M	0.0	186.8	286.9	532.5	997.1	1329.0	1528.1	1594.5
(Max)	V	85.6	80.4	77.5	69.9	52.4	34.9	17.5	0.0
Self wt. :	M	0.0	134.5	206.5	383.4	717.9	956.9	1100.3	1148.1
(Min)	V	61.6	57.9	55.8	50.3	37.7	25.2	12.6	0.0
DL-Prec. :	M	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0
DC(Max)	V	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0



Program: LEAP®
CONSPAN®
Version: 08.01.00.10

Copyright © Bentley Systems, Inc. 1984 - 2008.
www.bentley.com
1-800-778-4277

By: A. Pott
Date: Jan/4/2010
CKD:
Date:

File Name: 76-21-125-21-124 U72C.csl

		Bearing	Trans	H/2	0.10L	0.20L	0.30L	0.40L	Midspan
DL-Prec. :	M	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0
DC(Min)	V	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0
DL-Prec. :	M	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0
DW(Max)	V	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0
DL-Prec. :	M	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0
DW(Min)	V	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0
Deck + :	M	0.0	283.8	435.8	809.0	1514.9	2019.1	2321.6	2422.5
Haunch (Max)	V	130.1	122.2	117.8	106.1	79.6	53.1	26.5	0.0
Deck + :	M	0.0	204.3	313.8	582.5	1090.7	1453.7	1671.6	1744.2
Haunch (Min)	V	93.6	88.0	84.8	76.4	57.3	38.2	19.1	0.0
Diaphragm :	M	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0
(Max)	V	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0
Diaphragm :	M	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0
(Min)	V	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0
DL-Comp :	M	9.2	25.0	33.3	53.4	89.6	112.4	121.6	117.4
DC(Max)	V	7.2	6.7	6.4	5.7	3.9	2.1	0.3	1.4
DL-Comp :	M	6.7	18.0	24.0	38.5	64.5	80.9	87.6	84.6
DC(Min)	V	5.2	4.8	4.6	4.1	2.8	1.5	0.2	1.0
DL-Comp :	M	52.7	142.3	189.8	304.6	511.0	640.6	693.5	669.6
DW(Max)	V	41.3	38.3	36.6	32.2	22.1	12.0	1.9	8.2
DL-Comp :	M	22.8	61.7	82.2	132.0	221.4	277.6	300.5	290.1
DW(Min)	V	17.9	16.6	15.9	14.0	9.6	5.2	0.8	3.6
LL + I :	M+	264.3	810.3	1094.4	1762.0	2850.3	3421.3	3577.6	3381.6
	V	69.4	125.2	156.5	239.1	67.6	27.4	46.5	142.5
LL + I :	M-	-2.5	-7.1	-9.6	-16.3	-31.7	-47.0	-62.3	-77.6
	V	52.7	36.1	26.8	2.3	2.3	2.3	2.3	2.3
LL + I :	Vmx	279.3	266.4	259.2	240.1	192.3	148.7	125.7	167.2
	M	313.1	832.8	1100.6	1720.2	2670.9	3066.6	2960.6	2813.6
Total :	M+	326.2	1448.1	2040.1	3461.5	5963.0	7522.4	8242.5	8185.6
	V	333.7	372.9	394.9	453.0	225.6	129.5	92.7	152.2
Total :	M-	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0
	V	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0
Total :	Vmx	543.5	514.1	497.6	454.0	350.3	250.8	172.0	176.9
	M	375.0	1470.7	2046.3	3419.7	5783.5	7167.7	7625.5	7617.5

		0.60L	0.70L	0.80L	0.90L	H/2	Trans	Bearing
Location,	ft	44.85	52.45	60.05	67.65	70.98	72.25	74.50
Self wt. :	M	1528.1	1329.0	997.1	532.5	286.9	186.8	0.0
(Max)	V	17.5	34.9	52.4	69.9	77.5	80.4	85.6
Self wt. :	M	1100.3	956.9	717.9	383.4	206.5	134.5	0.0
(Min)	V	12.6	25.2	37.7	50.3	55.8	57.9	61.6
DL-Prec. :	M	0.0	0.0	0.0	0.0	0.0	0.0	0.0
DC(Max)	V	0.0	0.0	0.0	0.0	0.0	0.0	0.0
DL-Prec. :	M	0.0	0.0	0.0	0.0	0.0	0.0	0.0
DC(Min)	V	0.0	0.0	0.0	0.0	0.0	0.0	0.0
DL-Prec. :	M	0.0	0.0	0.0	0.0	0.0	0.0	0.0
DW(Max)	V	0.0	0.0	0.0	0.0	0.0	0.0	0.0
DL-Prec. :	M	0.0	0.0	0.0	0.0	0.0	0.0	0.0
DW(Min)	V	0.0	0.0	0.0	0.0	0.0	0.0	0.0
Deck + :	M	2321.6	2019.1	1514.9	809.0	435.8	283.8	0.0
Haunch (Max)	V	26.5	53.1	79.6	106.1	117.8	122.2	130.1
Deck + :	M	1671.6	1453.7	1090.7	582.5	313.8	204.3	0.0
Haunch (Min)	V	19.1	38.2	57.3	76.4	84.8	88.0	93.6
Diaphragm :	M	0.0	0.0	0.0	0.0	0.0	0.0	0.0
(Max)	V	0.0	0.0	0.0	0.0	0.0	0.0	0.0
Diaphragm :	M	0.0	0.0	0.0	0.0	0.0	0.0	0.0
(Min)	V	0.0	0.0	0.0	0.0	0.0	0.0	0.0



Program: LEAP®
CONSPAN®
Version: 08.01.00.10

Copyright © Bentley Systems, Inc. 1984 - 2008.
www.bentley.com
1-800-778-4277

By: A. Pott
Date: Jan/4/2010
CKD:
Date:

File Name: 76-21-125-21-124 U72C.csl

		0.60L	0.70L	0.80L	0.90L	H/2	Trans	Bearing
DL-Comp :	M	99.8	68.6	24.0	-34.0	-60.8	-72.9	-96.8
DC(Max)	V	3.2	5.0	6.8	8.5	9.3	9.6	10.1
DL-Comp :	M	71.8	49.4	17.3	-24.5	-43.8	-52.5	-69.7
DC(Min)	V	2.3	3.6	4.9	6.1	6.7	6.9	7.3
DL-Comp :	M	568.9	391.4	137.1	-194.0	-346.6	-415.3	-552.1
DW(Max)	V	18.3	28.4	38.5	48.6	53.0	54.7	57.7
DL-Comp :	M	246.5	169.6	59.4	-84.1	-150.2	-180.0	-239.3
DW(Min)	V	7.9	12.3	16.7	21.1	23.0	23.7	25.0
LL + I :	M+	2820.3	1917.5	1043.5	608.8	571.7	582.1	634.0
	V	188.2	230.1	105.1	16.5	13.6	12.5	10.5
LL + I :	M-	-93.0	-108.3	-571.7	-2182.4	-3067.9	-3433.0	-4120.5
	V	2.3	2.3	165.6	276.6	307.6	319.4	340.3
LL + I :	Vmx	210.5	251.9	290.6	325.6	337.7	342.2	350.3
	M	2396.8	1585.4	464.6	-853.6	-1402.9	-1607.0	-1963.2
Total :	M+	7338.7	5725.6	3716.7	1841.8	1100.4	820.3	325.0
	V	253.7	351.5	282.4	249.7	238.6	245.7	258.4
Total :	M-	0.0	0.0	0.0	-1444.5	-2954.9	-3582.4	-4769.5
	V	0.0	0.0	0.0	413.9	510.6	529.6	563.4
Total :	Vmx	276.0	373.3	467.9	558.8	595.3	609.2	633.8
	M	6915.2	5393.5	3137.8	259.8	-1087.6	-1624.5	-2612.2

REACTIONS (kips), STRENGTH I


Load Type		Left Support	Right Support
Self Wt.		85.6	85.6
Deck+Haunch		130.1	130.1
Diaphragm		0.0	0.0
DL-Prec.(DC)		0.0	0.0
DL-Prec.(DW)		0.0	0.0
DL-Comp.(DC)		59.4	31.9
DL-Comp.(DW)		338.7	182.0
Live	(Max)	141.3	314.4
Live	(Min)	-1.1	-219.9
Pedestrian	(Max)	-0.0	-0.0
Pedestrian	(Min)	-0.0	-0.0

Upward reactions are positive.

Live Load reactions are per lane with no distribution factor and no impact.

Non-composite load types are per beam.

Composite and Pedestrian load types are per total bridge width.



$$l_{max} = 125'$$



$$\sum M_0 = 0$$

$$F_1 (1.2083) - F_2 (1.2083) - \frac{(50 \text{ psf}) (15.5') \left(\frac{15.5'}{2} \right) + \left(\frac{125}{2} \right)}{1000} = 0$$

$$F_1 - F_2 = 375.39 \text{ K}$$

$$\sum F_y = 0$$

$$F_1 + F_2 = \frac{125}{2} \left(\frac{(15.5') (50 \text{ psf})}{1000} \right) + 31' * \frac{(8'')}{12'} (.15 \text{ kcf}) + (12.245F) (.15 \text{ kcf})$$

$$F_1 + F_2 = 356.94 \text{ K}$$

by addition $2F_1 = 732.33$


$$F_1 = 366.165 \text{ K}$$

$$F_2 = -9.23 \text{ k up lift}$$

need bracing @ piers & abutments

By: Date	Project no.	Project code (SA#):
Chk'd: Date	Structure no.	Sheet 352 of

COLORADO DEPARTMENT OF TRANSPORTATION
DESIGN COMPUTATIONS (Grid)



bearing = $30'' \times 15.5''$

@ 200 psi

Load $\approx (30)(15.5) \cdot 2 \text{ ksi} = 93 \text{ k}$

Uplift = 9.23 k

Use Safety Factor = 3

$C (5.5') = (9.23 \text{ k}) (1.2083) (3)$

$C \approx 6.08 \text{ k}$

use Pin-Pin Connections

$K = 1.0$

$L \approx 9' \text{ max}$

could use $2 \times 2 \times 3/16''$

use $3 \times 3 \times 1/4''$ for clearance requirements

$7/8'' \phi$ Bolt $A = .60 \text{ in}^2$


$F_{allow} = .4 F_y$

$F_y = 90 \text{ ksi}$

Load $\approx (.4) (90 \text{ ksi}) (.60 \text{ in}^2) = 21.6 \text{ kips} \checkmark \text{ okay}$

By: _____	Date _____	Project no. _____	Project code (SA#): _____
Chk'd: _____	Date _____	Structure no. _____	Sheet <u>353</u> of _____

COLORADO DEPARTMENT OF TRANSPORTATION
DESIGN COMPUTATIONS (Grid)




$$M \approx 6.08k (\sin 60^\circ) * 4$$

$$M \approx 21.06 \text{ ft } k$$

use W6x20 for clearance requirements

Revision for straight pier



still okay w/ bolt locations shown
 if bolts move to main portion of pier
 maximum change \Rightarrow 5'-6" moment arm

$$M_{max} \approx 6.08k (\sin 60^\circ) * 5.5$$

$$M \approx 28.96 \text{ ft } k$$

okay for W6x20

By: _____	Date _____	Project no. _____	Project code (SA#): _____
Chk'd: _____	Date _____	Structure no. _____	Sheet <u>354</u> of _____

TUB TORSION STRENGTH

$$T_n = \frac{2 A_o A_t f_y \cot \theta}{S} \quad (1.10.2) \quad (5.8.3.6.2-1)$$

$$A_o \approx 683.7 \text{ in}^2$$

$$A_t = .11 \text{ in}^2 \quad (\#3 \text{ min.})$$

$$S = 10'' \text{ max}$$

$$f_y = 60 \text{ ksi}$$


$$\text{assume } \theta = 45^\circ$$

$$T_n \approx \frac{2 (683.7 \text{ in}^2) (.11) (60) \cot 45}{10''}$$

$$T_n \approx 902.48 \text{ in.kip} \approx 75 \text{ ft.kip}$$

$$T_R = \phi T_n = .9 T_n \quad (5.8.2.1-1)$$

$$T_R \approx 67.5 \text{ ft.kip}$$



$$T_u = (F) \left(\frac{15.5}{2} \right) (1.75) = 13.56 F_{max}$$


$$13.56 F_{max} = 67.5 \text{ ft.kip}$$

$$F_{max} = 4.98 \text{ kip}$$

$$\text{dist. load} = \frac{4.98}{15.5} = .322 \text{ k/SF} \approx \underline{32.2 \text{ lb/SF}} \quad \leftarrow$$


$$\text{for } \theta = 60^\circ, F_{max} \approx \underline{18.6 \text{ lb/SF}} \quad \leftarrow \quad \text{Allowable Eccentric Load}$$

By: _____	Date _____	Project no. _____	Project code (SA#): _____
Chk'd: _____	Date _____	Structure no. _____	Sheet <u>355</u> of _____



COLORADO DEPARTMENT OF TRANSPORTATION
DESIGN COMPUTATIONS (Grid)


Phase 3 & 4



each slab ~ 8' wide

$$28 \text{ K} / 8' / 2 \text{ sides} \approx 1.75 \text{ K/ft}$$

$$M \approx 1.75 \text{ K/ft} * 1.42'' \approx 2.5 \text{ ft K/ft}$$




$$M_R \approx 4.88 \text{ ft K/ft}$$

2.08 ft K/ft

4 hooks development length $\approx 6.33''$

okay for moment



$$P_{eq} = \frac{2.5 \text{ ft K/ft}}{5'-4''}$$


$$P_{eq} = .46875 \text{ K}$$

64

$$\Delta_{max} = \frac{P L^3}{3EI}$$

$$\Delta_{max} \approx \frac{(.46875) 64^3}{3 (5460) (421.875)}$$

$$\Delta_{max} \approx .0178''$$




$$I = \frac{12'' (7.5'')^2}{12} \approx 421.875$$

$$E \approx 5460$$

from SAP 2000 $\Delta \approx .03''$

By: _____	Date _____	Project no. _____	Project code (SA#): _____
Chk'd: _____	Date _____	Structure no. _____	Sheet <u>357</u> of _____

COLORADO DEPARTMENT OF TRANSPORTATION
DESIGN COMPUTATIONS (Grid)



$Wt \approx 7 \text{ K}$

$f'_c = 9 \text{ ksi}$

allowable stress = $.3 f'_c$

$(.3)(9 \text{ ksi}) = 2.7 \text{ ksi}$

$\frac{7 \text{ K}}{\frac{\pi 2''^2}{4}} \approx 2.23 \text{ ksi} < \text{allowable okay}$

Good for bearing force ✓


$V_c = .0316 B \sqrt{f'_c} b_v d_v = .0316 (2) \sqrt{9} (12)(12)$

(5.8.3.3-3)

$V_c \approx 27.3 \text{ K} \checkmark$

Phase 1 & 2


Max Load = 39 K



$39 \text{ K} / 8 \text{ points of bearing} \approx 4.9 \text{ K}$

Phase 3 & 4 are worst case

By: _____	Date _____	Project no. _____	Project code (SA#): _____
Chk'd: _____	Date _____	Structure no. _____	Sheet <u>38</u> of _____



REINFORCING DESIGN

GIVEN:

$f_y = 60.00$ ksi
 $f'_c = 9.00$ ksi
 COVER = 1.75 inches
 $\Phi_{flexure} = 0.90$
 Beam Thickness (t_s) = 7.50 inches
 $b = 10.00$ inches
 bar diameter = 0.875 inches

Impact Steel

LOAD TYPE	M_{hTOT} ft-K	$A_{Sreq'd}$ in ²
M_h (UNFACTORED)	2.08	0.09
STRENGTH I	3.13	0.13
SERVICE I	2.08	0.09

$d_s = 5.31$ inches
 per 5.10.8.2 $A_{S_{temp}} = 0.11$ sq inches

Use #4 at top face min. spacing = 15.15 inches
 use spacing = 10.00 inches
 $A_s = 0.200$ sq. inches

compressive steel:

Use #5 at bottom face
 $A_{s'} = 0.00$ sq. inches

$M_h = 5.42$ ft-K
 $M_r = 4.88$ ft-K

Reinforcing is okay

Maximum Reinforcement per 5.7.3.3.1-1 (Ductility Check)

$c = 0.26$ inches
 $d_e = d_s = 5.31$ inches (for no prestressing)
 $c/d_e = 0.05$

okay - member is not overreinforced

Minimum Reinforcement per 5.7.3.3.2

$1.2 * M_{cracking} = 6.75$ ft-K <--- Test 1
 $1.33 M_{hTOT} (max.) = 4.16$ ft-K <--- Test 2

Minimum Reinforcing is provided

Transverse Reinforcement per 9.7.3.2

Percentage of main reinforcement, $220 / \sqrt{S} \leq 67\%$

Girder Spacing = 15.25 ft
 Flange Width = 21 inches
 Flange Overhang = 18 inches
 Effective Length $S = 15.00$ ft
 $220 / \sqrt{S} = 56.80\%$ Use **56.804%** of required main reinforcement
 Required $A_s = 0.11$ sq inches
 Use #6 transverse reinforcement
 min. spacing = 38.72 inches

By: _____ Date _____
 Chk'd: _____ Date _____


Project no. _____
 Structure no. _____

Project code (SA#) _____
 Sheet of _____

360

COLORADO DEPARTMENT OF TRANSPORTATION
DESIGN COMPUTATIONS (Grid)


use $1\frac{1}{2}$ " ϕ PVC drains in
low ends of girders



By: _____	Date _____	Project no. _____	Project code (SA#): _____
Chk'd: _____	Date _____	Structure no. _____	Sheet <u>361</u> of _____

Supports for Trolley Insulator

assume oak - 60 lb/ft³



assumed shape, assume 1" thick wood

length between girders \approx 30'


$$Wt = (6 + 1) \left(\frac{1}{12} \text{ft} \right) (30') 60 \text{ lb/ft}^3 \approx$$

$$Wt \approx 1200 \text{ lbs}$$

use P-86 Star Insert

style P36T or approved equal (1/2")


minimum safe working load \approx 2500 lbs



Inserts shall be approximately centered about Trolley Line
 Dimensions shown used to avoid vertical ties.

By: _____	Date _____	Project no. _____	Project code (SA#): _____
Chk'd: _____	Date _____	Structure no. _____	Sheet 362 of _____

363



MAX STRANDS


384

2


126

130

of one layer




PIER BEARINGS



$N_{11} = 339.5 \text{ k}$ 415.8 ft k

Torsion $\approx 533.8 \text{ ft k}$

$LL = 454.8 \text{ k ft k}$



by Method A:

$0.08 < G < 0.175$

$50 < \text{hardness} < 60$

need to specify

$.25 < \text{Creep} < .35$

Shape Factor

$S_x = \frac{LW}{2h_f(L+W)}$

$h_f = 1/2$

$K > 3/4$

$D_s \leq .80 \text{ ksi}$

$D_L \leq 2.0 \text{ ksi}$

643.82

Load $\times \frac{860.6 \text{ k}}{533.8} + \frac{2}{2.5'} \approx 643.8 \text{ k ip}$

257.3 k min

square pad $= \frac{643.8 \text{ kip}}{20 \text{ ksi}} = 804.8 \text{ sq in}$

\rightarrow 28" square

for Live Load $\approx \frac{421.5 \text{ k}}{2} + \frac{454.8}{2.5} \approx 392.7 \text{ k}$

$\frac{392.7}{2 \text{ ksi}} = 196.3 \text{ sq in} \rightarrow 14" \text{ sq r}$

Bearing - Method A - No Testing Required (2009 Interims)

Total Vertical Load =	709.7 Kip		
Total Torsion Load =	552.1 Ft Kip		
Live Vertical Load =	272.9 Kip		
Live Torsion Load =	505.6 Ft Kip		
Dist. Between CL bearings =	2.67 Ft		
Total Load =	561.90 Kip		
Live Load =	326.10 Kip		
L =	15.5 inches (longitudinal)		
W =	30 inches (transverse)		
Hardness =	50 durometer		
G =	0.095 ksi		
h _{ri} =	0.5 inches (thickness of ith layer)		
n =	7 # of layers		
h _{ext} =	0.125 inches (thickness of exterior layer)		
h _s =	0.125 inches (thickness of shims)		
h _{total} =	4.75 inches (total bearing thickness)		
S _i =	L*W/(2*h _i *(L+W))		
S _i =	10.220		
S _i ² /n =	14.92		
Compressive Stress			
σ _s <=	1.25*G*S _i		
σ _s <=	1.21 ksi		
σ _s <=	1.25 ksi		
σ _s =	Total Load/(L*W)		
σ _s =	1.21 ksi		
Compressive Deflection			
Dead Load =	235.80 Kip		
σ _{DL} =	0.51 ksi		
ε _{DL} =	2.00%		
σ _{DL} =	Σ ε _{DL} *h _i		
σ _{DL} =	0.07 inches		
σ _{DL} =	σ _{DL} + a _c *σ _{DL}		
a _c =	0.25		
σ _{LT} =	0.088 inches (long term deflection)		
σ _{LL} =	0.70 ksi		
ε _{LL} =	2.80%		
σ _{LL} =	Σ ε _{LL} *h _i		
σ _{LL} =	0.10 inches		

(14.7.6.3.3 & 14.7.5.3.6)

(Fig C14.7.6.3.3-1)

(14.7.5.3.6-2)

(14.7.5.3.6-3)

(Fig C14.7.6.3.3-1)

(14.7.5.3.6-1)

by Method B:

Temperature Zone : Zone C

50 year low temp = -30°F

Min low temp Expansion Grade = 3

$$H_{bu} = GA \frac{\Delta v}{h_{rt}}$$

(14.6.3.1-2)

$$M_u = 1.60 (.5 E I) \frac{\theta_s}{h_{rt}}$$

(14.6.3.2-3)

Compressive Stress

subject to shear deformation

$$D_s \leq 1.66 G S$$

(14.7.5.3.2-1)

$$D_s \leq 1.6 K S$$

(14.7.5.3.2-2)

$$D_s \leq 0.66 G S$$

(14.7.5.3.2-3)

$$Load = 643.8 \text{ k} \approx$$

$$Sg. \text{ pad} = \frac{643.8}{1.6} \approx 402.4 \text{ in}^2$$

↔ 20" SQR

or 15" x 27" rectangle

COLORADO DEPARTMENT OF TRANSPORTATION
DESIGN COMPUTATIONS (Grid)

$$S_i = \frac{L W}{2 h_{ri} (L+W)} \quad (4.7.5.1-1)$$

$h_{ri} = 1/2''$

for 20" SQR

$$S_i = \frac{(20)(20)}{2(.5)(20+20)} \approx 10$$

$$G_{min} = .08$$

$$\tau_s \leq 1.66 G S = 1.66 (10) (.13) \approx 2.158 \text{ ksi}$$

for 15" x 27" L = 15" W = 27"

$$S_i = \frac{15(27)}{2(.5)(15+27)} \approx 9.643$$

$$\tau_s \leq 1.66 (.13)(9.643) = 2.08 \text{ ksi}$$

$G_{min} = .1$ for 1.66 ksi

$$\tau_{max} \approx \frac{643.8}{(15)(27)} \approx 1.59 \text{ ksi} < 1.60 \text{ ksi} \quad \checkmark \text{ okay}$$

$$\tau_{min} \approx \frac{(339.5/2)}{15(27)} \approx .42 \text{ ksi} > 200 \text{ psi} \quad \checkmark \text{ okay}$$

By: _____	Date: _____	Project no. _____	Project code (SA#): _____
Chk'd: _____	Date: _____	Structure no. _____	Sheet <u>368</u> of _____

COLORADO DEPARTMENT OF TRANSPORTATION
DESIGN COMPUTATIONS (Grid)

$$h_{rt} \geq 2 \Delta s$$

(14.7.5.3.4-1)

length of contribution \approx middle of bridge to bearing $37\frac{1}{2}' - 11.5' - 74.5' = 109.5'$

$$\text{Temp. Movement} = 90^\circ \times .000006 + 109.5' \times \frac{.71''}{12} = .71''$$

to account for shrinkage & creep multiply by 1.6

$$\Delta s = \text{TOTAL MOVEMENT} = 1.6 (.71) = 1.14''$$

$$h_{rt} \geq 2 \Delta s = 2 (1.14'') = 2.28''$$

3.5'

$\Delta s = 1.75''$ max

$$\# \text{ of plgs} = 2.28 / .5 = 4.56 \Rightarrow 5 \text{ min.}$$

Use 8

$\Delta s = 1.75''$ max
 Temp movements 1.09'' max

$$\# \text{ of shims} = \# \text{ of plgs} + 1 = 9$$

$$\text{Thickness of shim} = \frac{1}{8}''$$

$$\text{thickness of pad} = \frac{1}{2}'' + 8 + \frac{1}{8}'' \times 9 + 2 \times \frac{1}{8}''$$

aluminum shims cover

$$= 5 \frac{3}{8}''$$

STABILITY

for 15" x 27" L = 15" W = 27"

$$A = \frac{1.92 h_{rt}}{L} = \frac{1.92 (1.14'')}{15} = .352$$

$$\frac{1.92 h_{rt}}{\sqrt{1 + 2.04/W}} = \frac{1.92 (1.14'')}{\sqrt{1 + 2 \cdot 15/27}} = .352$$

(14.7.5.3.6-2)

$$B = \frac{2.67}{(s+2.0)(1 + \frac{L}{4.0W})} = \frac{2.67}{(9.6+2.0)(1 + \frac{15}{4.0(27)})} = .201$$

(14.7.5.3.6-3)

$$2A \leq B \quad ?$$

(14.7.5.3.6-1)

NO, check stress

By: _____	Date: _____	Project no. _____	Project code (SA#): _____
Chk'd: _____	Date: _____	Structure no. _____	Sheet <u>369</u> of _____

COLORADO DEPARTMENT OF TRANSPORTATION
DESIGN COMPUTATIONS (Grid)

$$\sigma_s \leq \frac{G S}{A-B}$$

(14.7.5.3.6-5)

$$\sigma_s \leq \frac{(.13)(9.643)}{(.352 - .201)} = 8.30 \text{ ksi}$$

$$\sigma_s = \frac{643.8 \text{ k}}{15(27) \text{ in}^2} \approx 1.59 \text{ ksi} \quad \checkmark \text{ ok}$$

bearing is stable

Reinforcement

$$h_s \geq \frac{3 h_{\max} \sigma_s}{F_y}$$

(14.7.5.3.7-1)

$$h_s \geq \frac{3 \left(\frac{1}{2}''\right) (1.55)}{60 \text{ ksi}} = .039'' < \frac{1}{8}'' \quad \checkmark \text{ okay}$$

$$h_s \geq \frac{2 h_{\max} \sigma_L}{\Delta F_{TH}}$$

(14.7.5.3.7-2)

$$\sigma_L = \frac{421.5}{2} + \frac{454.8}{3.5} \approx 909 \text{ ksi}$$

(15)(25)

$$\Delta F_{TH} = 24.0 \text{ ksi}$$

(Table 6.6.1.2.5-3)

$$h_s \geq \frac{2 \left(\frac{1}{2}''\right) (909)}{24} = .038'' < \frac{1}{8}'' \quad \checkmark \text{ okay}$$

COLORADO DEPARTMENT OF TRANSPORTATION
DESIGN COMPUTATIONS (Grid)

COMPRESSIVE DEFLECTION

$$DL \approx \frac{439.1}{2} + \frac{79}{25} \approx 251.2 \text{ k}$$

$$\sigma_{DL} \approx \frac{(251.2)}{(15)(27)} = .62 \text{ ksi}$$

ϵ_{DL} = Compressive strain \approx 3% (50 diameter)
 2 1/2% (60 diameter)
 (Fig C14.7.6.3.3-1)

$$\delta_d = \sum \epsilon_{Li} h_{Li} \quad (14.7.5.3.3-2)$$

$$= (.025)(.5)(8) = .1'' < 1/8''$$

$$a_{cr} = .35 \quad (60 \text{ diameter}) \quad (\text{Table } 14.7.6.2-1)$$

$$\delta_{d,t} = \delta_d + a_{cr} \delta_i \quad (14.7.5.3.3-3)$$

$$\delta_{d,t} = .1 + .35(.1) = .135'' \quad (60 \text{ diameter})$$

$$\delta_{d,t} = .12 + .25(.12) = .15'' \quad (50 \text{ diameter})$$

$$LL \approx 392.7 \text{ k}$$

$$\sigma_{LL} = \frac{(392.7)}{(15)(27)} \approx .97 \text{ ksi}$$

ϵ_{LL} = compressive strain \approx 4% 50 diameter
 3 1/2% 60 diameter

$$\delta_L = \sum \epsilon_{Li} h_{Li} \quad (14.7.5.3.3-1)$$

$$\delta_L = (.04)(.5)(8) \approx .16'' > 1/4'' \text{ for } 50 \text{ diameter}$$

$$\delta_L = .035(.5)(8) \approx .14'' > 1/8'' \text{ for } 60 \text{ diameter}$$

Use 60 diameter, $G_{min} = .13$




Figure C14.7.6.3.3-1 Stress-Strain Curves.

For CDP, the computed compressive strain, ϵ_s , may be taken as:

$$\epsilon_s = \frac{\sigma_s}{E_c} \quad (14.7.6.3.3-1)$$

where:

E_c = uniaxial compressive stiffness of the CDP bearing pad. It may be taken as 30 ksi in lieu of pad-specific test data (ksi)

σ_s = average compressive stress due to total load from applicable service load combinations in Table 3.4.1-1 (ksi)


CDP is typically very stiff in compression. The shape factor may be computed, but it has a different meaning and less significance to the compressive deflection than it does for FGP and PEP (Roeder *et al.*, 2000). As a result, the maximum compressive deflection for CDP can be based upon an average compressive strain, ϵ_s , for the total bearing pad thickness as computed in Eq. 1.

ROTATIONS ON BEARING

$$\frac{2\pi \text{ radians}}{360^\circ}$$

DEAD LOAD ROTATIONS

DEAD LOADS CAUSE $\approx 2.1''$ of camber change
 $\approx 0^\circ 18' 39''$ of rotation



4.6

LIVE LOAD CAUSES $\approx 1.6''$ of camber change
 $\Rightarrow 0^\circ 14'$

4.8

2.2

PRESTRESSING LOSS CAUSES $\approx 2.1''$ of camber change
 $\approx 0^\circ 18' 39''$

$$\theta_s \approx .005 \text{ Radians}$$

allowance for uncertainties $\approx .005$ Radians (14.4.2.1)

$$\theta_{s \text{ TOTAL}} \approx .01 \text{ Radians}$$

By: Date	Project no.	Project code (SA#):
Chk'd: Date	Structure no.	Sheet <u>373</u> of _____

COMBINED COMPRESSION AND ROTATION

$$\sigma_s > 1.0 G_s \left(\frac{\theta_s}{n} \right) \left(\frac{B}{h_{ri}} \right)^2 \quad (14.7.5.3.5-1)$$

$$S = 9.643$$

$$G = .13$$

$$\theta_s \approx .01 \text{ radians} \approx .005 \text{ rad} + .005 \text{ rad uncertainty}$$

$$n = 8$$

$$L = B = 15''$$

$$h_{ri} = .5''$$

$$\sigma_s = \frac{643.8 \text{ ksi}}{(15)(27)} \approx 1.59 \text{ ksi}$$

$$\sigma_s > (1.0) (.13) (9.643) \left(\frac{.01}{8} \right) \left(\frac{15}{.5} \right)^2 = 1.41 \text{ ksi}$$

okay at max load, for min. load, keeper bars & vertical bolt is provided.

$$\sigma_s < 1.875 G_s \left[1 - .2 \left(\frac{\theta_s}{n} \right) \left(\frac{B}{h_{ri}} \right)^2 \right] \quad (14.7.5.3.5-2)$$

$$\sigma_s < 1.875 (.13) (9.643) \left[1 - .2 \left(\frac{.01}{8} \right) \left(\frac{15}{.5} \right)^2 \right]$$

$$\sigma_s < 1.82 \text{ ksi} \quad 1.828$$

BALANCED DESIGN

(TABLE C14.7.5.3.5-1)

$$\frac{\sigma_s}{G_s} = 1.364 \quad 1.268$$

$$\frac{\theta_s}{n} \left(\frac{B}{h_{ri}} \right)^2 = 1.364 \quad 1.125$$

9.22

By: _____	Date _____	Project no. _____	Project code (SA#): _____
Chk'd: _____	Date _____	Structure no. _____	Sheet 374 of _____

BEARING DEFORMATION

$$H_{bu} = GA \frac{\Delta_u}{h_{nt}} \quad (14.6.3.1-2)$$

$$G \approx .13$$

$$A = 27" \times 15" = 405 \text{ in}^2$$

$$\Delta_u \approx 1.14"$$

$$h_{nt} = 4"$$

$$H_{bu} \approx .13 (405) \left(\frac{1.14}{4} \right) \approx \underline{15 \text{ kips}} \quad \leftarrow \text{bearing pad}$$

$$M_u = 1.60 (.5 E_c I) \frac{\theta_s}{h_{nt}} \quad (14.6.3.2-3)$$

$$E_c \approx 6 G S^2$$

$$= 6 (.13) (9.643)^2$$

$$E_c = 72.53$$

$$(14.6.3.2-1)$$

$$I = \frac{b^3}{12} \approx \frac{(27) 15^3}{12} \approx 7593.75$$

$$\theta_s \approx .01 \text{ radians}$$


$$h_{nt} = 4"$$

$$M_u \approx 1.6 \left[(.5) (72.53) (7593.75) \right] \frac{.01}{4}$$

$$M_u \approx 1101.55 \text{ in Kip} = \underline{91.8 \text{ ft K}} \quad \leftarrow$$

TAPERED SOLE PLATE

Maximum deflection due to grade & D.L. deflection
 $= .06T = .06 (8 \times .5) = .24''$



90 grade @ bearing $\approx 0^\circ 30'$ max. = .0053'/ft

D.L. rotations

allowance for uncertainties = .005 radians = .286° (14.4.2.1)
 $\approx 0^\circ 17' 11''$

@ erection, camber $\approx 2\frac{1}{2}''$ (3" max)

end rotation $\approx 0^\circ 30' \approx .0052$ radians

$\frac{122.5}{125}$

total $\approx .01$ radians

$\frac{\pi}{180}$

(tapered plate not required per 14.8.2)
 $\leq .01$ radians

grade deflection $\approx .0053'/ft \times \frac{20''}{12'/ft} \approx .009''$

D.L. rotation $\approx .0053'/ft \times \frac{20''}{12'/ft} \approx .009''$

total $\approx .018''$


$< .24''$

(tapered plate not required)

By: Date	Project no.	Project code (SA#):
Chk'd: Date	Structure no.	Sheet 376 of

COLORADO DEPARTMENT OF TRANSPORTATION
DESIGN COMPUTATIONS (Grid)

Dead Loads



$$\text{deck} \approx \left(\frac{8''}{12''}\right)(25')(15) \approx 2.5 \text{ K/ft}$$

$$\text{girder} \approx 12.265 \text{ SF} (15) \approx 1.84 \text{ K/ft}$$

$$\text{asphalt} \approx \left(\frac{3''}{12''}\right)(25)(.1467) \approx 0.92 \text{ K/ft}$$

$$\text{haunch} \approx \left(\frac{4''}{12''}\right) \left(\frac{64''}{12''}\right) .15 = 0.27 \text{ K/ft}$$

$$L \approx \frac{122.5}{2} + \frac{23'}{2} \approx 72.75'$$

$$Wt \approx 72.75 (2.5 + 1.84 + .92 + .27)$$

$$Wt \approx 402.3 \text{ K}$$

$$\sigma_{\min} \approx \frac{402.3 \text{ K}}{(27)(15)(2)} \approx 496.7 \text{ psi}$$

$$\sigma_{\min} > 200 \text{ psi}$$

Live Load

$$LL \approx 251 \text{ K}$$

for span 1

$$L \approx \frac{74.5}{2} + \frac{23}{2} \approx 48.75'$$

$$Wt \approx 48.75 (2.5 + 1.84 + .92 + .27)$$

$$Wt \approx 269.59 \text{ K}$$

$$\sigma = \frac{269.59}{(27)(15)(2)} \approx 333 \text{ psi}$$

$$\sigma_{\min} > 200 \text{ psi}$$

By: Date	Project no.	Project code (SA#):
Chk'd: Date	Structure no.	Sheet 377 of

COLORADO DEPARTMENT OF TRANSPORTATION
DESIGN COMPUTATIONS (Grid)

From SAP 2000 Analysis

max dead load ≈ 243 k/pad (From SAP 2000)

dead load from hand calc $\approx 402.3/2 \approx 201.6$ k/pad

max live load ≈ 324 k/pad ~ 270 avg max

total load ≈ 567 kip max.

avg ≈ 513 k

By: _____	Date _____	Project no. _____	Project code (SA#): _____
Chk'd: _____	Date _____	Structure no. _____	Sheet 378 of _____

Exterior

-142.8	-489.6	-625.7	-225.4	-374.9	-323.2
-181.4	-748.9	-588.8	-217.1	+284.2 -47.7	-245.3
-202.7	-391.7	-682.6	-245.7	-500.7	-254.7
-286.5	-723.6	-760.2	-274.3	-252.9	-205.9

INTERIOR

<u>Live</u>	<u>Service</u>	<u>Service</u>	<u>Live</u>	<u>Service</u>	<u>Live</u>
-260.9	-902.2	-676.2	-256.1	+346.9	-184.8
-138.5	-427.0	-652.6	-239.6	-406.3	-283.6
-137.1	-419.08	-644.6	-224.4	-403.0	-266.6
-248.5	-837	-656.7	-243.4	+283.4	-166.3
-136	-426	-648.1	-223.9	-387.9	-255.6
-243.4	-871.4	-665.7	-240.5	+305.4	-158.9
-142.4	-423.4	-652.6	-226.1	-392.5	-248.7
-245.9	-856.3	-653.6	-238.1	+293.0	-152.0
-150.4	-445.1	-655.7	-229.1	-374.7	-244.7
-251.3	-859.3	-660.4	-235.7	287.5	-145.4
-163.0	-455.2	-639.3	-235.5	-352.7	-243.0
-257.8	-884.0	-616.3	-238.5	356.8	-148.2

Table: Element Forces - Frames, Part 1 of 2

Frame Text	Station ft	OutputCase Text	CaseType Text	StepType Text	P Kip	V2 Kip	V3 Kip	T Kip-ft
224	0.0000	HL-93	LinMoving	Max	89.679	108.855	4.766	305.7409
224	0.7000	HL-93	LinMoving	Max	89.679	113.504	4.766	310.7934
224	0.7000	HL-93	LinMoving	Max	155.828	135.634	7.392	244.5313
224	1.0000	HL-93	LinMoving	Max	155.828	137.538	7.392	244.5791
224	1.0000	HL-93	LinMoving	Max	7.436	18.431	0.391	247.7088
224	2.0000	HL-93	LinMoving	Max	7.436	20.118	0.391	247.7776
224	0.0000	HL-93	LinMoving	Min	-12.329	-49.911	-2.351	-220.1568
224	0.7000	HL-93	LinMoving	Min	-12.329	-49.775	-2.351	-220.7819
224	0.7000	HL-93	LinMoving	Min	-19.514	-63.642	-6.326	-342.6309
224	1.0000	HL-93	LinMoving	Min	-19.514	-62.968	-6.326	-340.3717
224	1.0000	HL-93	LinMoving	Min	-35.740	-182.545	-3.205	-340.9043
224	2.0000	HL-93	LinMoving	Min	-35.740	-177.553	-3.205	-333.4330
224	0.0000	SERVICEI	Combination	Max	335.900	161.351	9.979	257.5607
224	0.7000	SERVICEI	Combination	Max	335.900	169.161	9.979	262.6132
224	0.7000	SERVICEI	Combination	Max	580.067	272.177	7.300	185.1541
224	1.0000	SERVICEI	Combination	Max	580.067	275.437	7.300	185.2018
224	1.0000	SERVICEI	Combination	Max	-35.322	-305.692	-10.007	193.4846
224	2.0000	SERVICEI	Combination	Max	-35.322	-299.489	-10.007	193.5534
224	0.0000	SERVICEI	Combination	Min	233.892	2.585	2.863	-268.3370
224	0.7000	SERVICEI	Combination	Min	233.892	5.883	2.863	-268.9620
224	0.7000	SERVICEI	Combination	Min	404.724	72.901	-6.417	-402.0081
224	1.0000	SERVICEI	Combination	Min	404.724	74.930	-6.417	-399.7490
224	1.0000	SERVICEI	Combination	Min	-78.499	-506.668	-13.602	-395.1286
224	2.0000	SERVICEI	Combination	Min	-78.499	-497.160	-13.602	-387.6573
323	0.0000	HL-93	LinMoving	Max	56.799	191.297	8.228	55.6207
323	0.2500	HL-93	LinMoving	Max	56.799	191.297	8.228	55.6207
323	0.5000	HL-93	LinMoving	Max	56.799	191.297	8.228	55.6207
323	0.0000	HL-93	LinMoving	Min	-271.311	-25.794	-4.575	-50.3589
323	0.2500	HL-93	LinMoving	Min	-271.311	-25.794	-4.575	-50.3589
323	0.5000	HL-93	LinMoving	Min	-271.311	-25.794	-4.575	-50.3589
323	0.0000	SERVICEI	Combination	Max	-405.222	658.294	18.534	79.2531
323	0.2500	SERVICEI	Combination	Max	-405.372	658.294	18.534	79.2531
323	0.5000	SERVICEI	Combination	Max	-405.522	658.294	18.534	79.2531
323	0.0000	SERVICEI	Combination	Min	-733.332	441.203	5.731	-26.7264
323	0.2500	SERVICEI	Combination	Min	-733.482	441.203	5.731	-26.7264
323	0.5000	SERVICEI	Combination	Min	-733.632	441.203	5.731	-26.7264

Table: Element Forces - Frames, Part 2 of 2

Frame Text	Station ft	OutputCase Text	StepType Text	M2 Kip-ft	M3 Kip-ft
224	0.0000	HL-93	Max	25.5385	357.5220
224	0.7000	HL-93	Max	26.7789	332.3554
224	0.7000	HL-93	Max	30.2037	326.0496
224	1.0000	HL-93	Max	31.9551	315.5563
224	1.0000	HL-93	Max	9.0444	317.4091
224	2.0000	HL-93	Max	8.7589	343.7574
224	0.0000	HL-93	Min	-34.7519	-2980.5208
224	0.7000	HL-93	Min	-37.8809	-2992.0875
224	0.7000	HL-93	Min	-41.6635	-2964.8166
224	1.0000	HL-93	Min	-43.7917	-2977.8671
224	1.0000	HL-93	Min	-27.5105	-3083.9989
224	2.0000	HL-93	Min	-24.5352	-2964.6007
224	0.0000	SERVICEI	Max	-10.7225	-6233.4068
224	0.7000	SERVICEI	Max	-13.1317	-6296.4274
224	0.7000	SERVICEI	Max	-17.1815	-6225.1367
224	1.0000	SERVICEI	Max	-15.4027	-6276.7963
224	1.0000	SERVICEI	Max	-61.9458	-6508.4419
224	2.0000	SERVICEI	Max	-51.8338	-6160.2288
224	0.0000	SERVICEI	Min	-71.0129	-9571.4496
224	0.7000	SERVICEI	Min	-77.7915	-9620.8703
224	0.7000	SERVICEI	Min	-89.0488	-9516.0029
224	1.0000	SERVICEI	Min	-91.1495	-9570.2197
224	1.0000	SERVICEI	Min	-98.5007	-9909.8498
224	2.0000	SERVICEI	Min	-85.1280	-9468.5869
323	0.0000	HL-93	Max	4.0993	95.6476

COLORADO DEPARTMENT OF TRANSPORTATION
DESIGN COMPUTATIONS (Grid)

$$\sigma_s \geq .5 GS \left(\frac{L}{h_{ri}} \right)^2 \frac{\theta_{sx}}{n} \quad (14.7.6.3.5 d-1)$$

$$\sigma_s \geq .5 GS \left(\frac{W}{h_{ri}} \right)^2 \frac{\theta_{sz}}{n} \quad (14.7.6.3.5 d-2)$$

$$S = 9.643$$

$$G \approx .13$$

$$W = 27'$$

$$\theta_{sx} \approx .005$$

$$\theta_{sz} = .002$$

$$n = 8$$

$$L \approx 15$$

$$h_{ri} = .5''$$

$$\sigma_s \geq .5 (.13)(9.643) \left(\frac{15}{.5} \right)^2 \frac{.005}{8} \approx .353 \text{ Ksi}$$

$$\sigma_s \geq .5 (.13)(9.643) \left(\frac{27}{.5} \right)^2 \frac{.002}{8} \approx 0.46 \text{ Ksi}$$

Method A Criteria

By: _____	Date _____	Project no. _____	Project code (SA#): _____
Chk'd: _____	Date _____	Structure no. _____	Sheet <u>381</u> of _____

TRANSVERSE LOAD ON BEARINGS

FROM SEISMIC CALCULATION AND PER 3.10.9.2

Horizontal Connection Force = .25 Vertical Reaction

$$H = .25 \left(\frac{860.6 \text{ k.p.}}{2} \right) \approx 107.6 \text{ k per bearing}$$


per C14.8.3.1 $\mu_{\text{friction}} \approx .2$

assume $DL_{\text{min}} \approx 366.8 \overset{DL}{(.9)} + .65 \overset{DW}{(72.3)}$
 $\approx 377 \text{ k for two bearings}$

$$\text{friction} \approx .2 \left(\frac{377}{2} \right) \approx 37.7 \text{ k}$$

$$\text{req'd} = 107.6 \text{ k} - 37.7 \text{ k} \approx 69.9 \text{ k}$$

GIRDER TO BEARING CONNECTION



$$L_{\text{weld}} \approx 16''$$

$E_{xx} = 70 \text{ ksi}$ for prequalified welds
 Plates are A36 steel
 $F_y = 36 \text{ ksi}$
 $F_u = 58 \text{ ksi}$

$$R_R = .6 \phi_{e2} F_{exx} \quad (6.13.3.2.4 b-1)$$

$$\phi_{e2} = .8 \quad (6.5.4.2)$$



for $3/16''$ weld, throat $\approx .133'' = t \sin 45^\circ$
 (prequalified for $1/4''$) $R_R = .6 (.8) (16'') (.133'') (70 \text{ ksi})$

$$R_R \approx 71.5 \text{ k} > 69.9 \text{ k}$$

need min 16" long, $3/16''$ weld per bearing per direction

By: _____	Date _____	Project no. _____	Project code (SA#): _____
Chk'd: _____	Date _____	Structure no. _____	Sheet <u>382</u> of _____

SHEAR STUDS IN GIRDER

$$Q_n = .5 A_{sc} \sqrt{f'_c E_c} \leq A_x F_u \quad (6.10.10.4.3-1)$$

$$A_{sc} = \frac{\pi (3/4)^2}{4} \approx .44 \text{ in}^2$$

$$E_c \approx 5460$$

$$f'_c \approx 9.0 \text{ ksi}$$

$$F_u = 58 \text{ ksi}$$

$$Q_n \approx .5 (.44) \sqrt{(9 \text{ ksi})(5460)} = 48.77 \text{ k}$$

$$Q_n \approx .44 (58 \text{ ksi}) = 25.5 \text{ k} \leftarrow \text{controls}$$

need $\frac{107.6 \text{ k}}{25.5 \text{ k}} \approx 5$ studs / bearing

use 10 studs min on bearing R

STAFF BRIDGE DESIGN MEMO

COLORADO DEPARTMENT OF HIGHWAYS

NUMBER

509.3-2

SUBJECT

ELASTOMERIC BEARING PADS

DATE

JULY 10, 1982

SUPERSEDES

JULY 6, 1972

The attached sheets give the properties, necessary design criteria, and design procedures for elastomeric bearing pads.

Elastomeric Bearing Pads shall be laminated with metal sheets.

All pads greater than 3/4" in thickness will be laminated in 1/2" layers.

Do not detail these bearing pads on the plans. Show overall size to be used; i.e., 8" x 1 1/2" x 1'-6". Standard Specifications will describe the construction of the pads. See Bridge Standard 32 for details.

In the interest of uniformity, all pads shall be designed with 60 durometer hardness. Figure 1 is the stress strain diagram for Durometer 60 in compression. The specification will call for Durometer 60 ± 5.

PROPERTIES OF ELASTOMER

Durometer Hardness 60 ± 5

Modulus of Elasticity in shear @ 0° F. . 180 = G

DESIGN CRITERIA

1. Plain Bearings: Minimum L or W = 5T
Laminated Bearings: Minimum L = 3T; Minimum W = 2T
T = total effective elastomer thickness = the sum of the layers (Σt)
Thickness of elastomer for an expansion pad shall not be less than twice the total horizontal movement.

Pads used for locked-in girders need only to be as thick as needed to ensure that the bottom of the girder does not touch the edge of cap; and these pads will be called leveling pads on project plans.
2. The minimum thickness of elastomer shall be 1/2". Maximum thickness of unlaminated pad is 3/4". For thicknesses greater than 3/4", increments of 1/2" layers (t) will be used with 8 - 1/2" layers as a maximum (4" effective thickness). Lengths and widths of pads should be in increments of 2" where possible. Pads should not extend outside the girder flanges without the use of sole plates or stiffening plates.
3. Initial compressive strain due to the maximum DL and LL shall not exceed 7% of the uncompressed thickness of the pad.
4. Maximum DL+LL (no impact) pressure on the pad shall not exceed 800 psi. Maximum DL pressure on the pad shall not exceed 500 psi. Minimum DL+LL uplift pressure on the pad without restraint against crawling is 200 psi.
5. The temperature range of the elastomeric pad is assumed to be 140° F for steel structures and 90° F for concrete structures. The mean

temperature is assumed to be 40° F. The coefficient of expansion for steel is .0000065 and for concrete is .000006. For prestress girders, the horizontal movement due to temperature shall be multiplied by 1.6 in order to account for shrinkage and creep of the concrete.

The "1.6" factor will satisfy most situations. However, if the designer feels that it is necessary, he may make a detailed analysis to determine the more exact values of shrinkage and creep of the concrete in his particular situation.


6. Shear Force = $F = \frac{\text{Modulus} \times \text{Area} \times \text{Temp. Movement}}{T}$ (This shear force is applied to the substructure and is included as a temperature force (T) in Group Loading Combinations IV, V, and VI.)
7. Shape Factor = $\frac{\text{length} \times \text{width}}{2 \times (\text{length} + \text{width}) \times (\text{thickness})}$
For laminated pads, since thickness per layer is always 1/2", the formula is reduced to:

$$SF = \frac{\text{length} \times \text{width}}{\text{length} + \text{width}}$$

A minimum Shape Factor of 6 is preferred.

8. Maximum compressive deflection due to geometry of non-parallel load surfaces and/or DL rotation is .06T. (Rotation may be neglected except on long spans and/or sliding teflon bearings).
9. Use tapered sole plates in lieu of tapered elastomeric pads on steel girders or prestressed girders placed on grades which require a taper as per above.


Staff Bridge Engineer


Asst. Staff Bridge Engr.


Staff Bridge Const. Engr.

DESIGN PROCEDURE

Given: Structure Type = Steel Girder
 Length Contributing to Movement = 150 feet
 Profile Grade at Bearing = 2%
 Dead Load Reaction = 65 kips
 Live Load Reaction (w/o Impact) = 45 kips
 Live Load Uplift Reaction = 25 kips
 Bottom Flange Width = 12 inches

a. Width of Pad = Bottom Flange Width = 12"

b. Length of Pad = $\frac{DL + LL}{0.8 (\text{Width of Pad})} = \frac{110}{0.8(12)} = 11.45$ Use 12

c. ^{TOTAL} Temperature Movement = $140^\circ \times 0.0000065 \times 150 \times 12 = 1.64"$ *-x(1.6 FOR COALC)*

d. Min. Elastomer Thickness = 2 x Horizontal Movement
 = 2 x 1.64"
 = 3.28"

No. of Plys = Elastomer Thickness/Ply Thickness
 = $3.28/0.5$
 = 6.6 Use 7

No. of Shims = No. of Plys + 1
 = 7 + 1
 = 8

Thickness of Shim = 1/8"

Thickness of Pad = 1/2" x No. of Plys + 1/8" x No. of Shims
 + 2 x Cover of Top & Bottom Shims
 = $1/2 \times 7 + 1/8 \times 8 + 2 \times 1/8$
 = 4-3/4"

e. Trial Pad: 12" x 4-3/4" x 12"

1. Check minimum compressive stress (with LL uplift)

$$\frac{(65 - 25) \times 1000}{12 \times 12} = 278 \text{ psi} > 200 \text{ psi} \quad \text{OK}$$

2. Maximum Compressive Stress

$$\frac{(65 + 45) \times 1000}{12 \times 12} = 764 \text{ psi} < 800 \text{ psi}$$

3. Shape Factor

$$\frac{(\text{Length} \times \text{Width})}{2 \times (\text{Length} + \text{Width}) \times (\text{Thickness})} = \frac{12 \times 12}{2(12 + 12)(1/2)} = 6$$

4. Compressive Strain

From Fig. 1, for compression stress = 764 psi
and Shape Factor = 6, initial compressive strain is 5.8%
of pad thickness < 7% OK

5. Calculate the maximum horizontal movement permissible before slippage starts.

$$\begin{aligned} \text{Allowable} &= \frac{\text{D.L. Reaction} \times \text{Thickness} \times 1.5^*}{5 \times \text{Modulus} \times \text{Area}} && \text{*Constant for 60 Durometer} \\ &= \frac{65000 \times (7 \times 0.5) \times 1.5}{5 \times 180 \times 144} \\ &= 2.63" > 1.64" \end{aligned}$$

6. Shear force to substructure

$$F = \frac{\text{Modulus} \times \text{Area} \times \text{Movement}}{\text{Thickness}}$$

$$F = \frac{180 \times 144 \times 1.64}{(7 \times 0.5)} \times \frac{1}{1000}$$

$$F = 12.145 \text{ kips}$$

Modulus at 0° F

110 IN ARIZONA

7. Check for tapered sole plate requirement:

Maximum compressive deflection due to grade and
D. L. deflection = $0.06T = 0.06 (7 \times 0.5) = 0.21"$

$$2\% \text{ grade} = 0.02'/' \times 1' = 0.02' = 0.240"$$


$$\text{D.L. Rotation} = 0^\circ-15' = 0.004'/' \times 0.5' = 0.002' = 0.024"$$

$$\frac{0.240" + 0.024"}{0.264"} > 0.21"$$

Tapered Sole Plates are required.

Use 12" x 4-3/4" x 1'-0" Laminated Pad

SOLE PLATE



$$\sigma_s = 1.25 \text{ Ksi}$$

$$M = (1.25)(15.5)(4)\left(\frac{4}{2}\right)$$

$$M = 155.0 \text{ in-kp}$$

$16\frac{3}{4}'' \times 1\frac{3}{4}'' \text{ PL}$

$$I = \frac{bh^3}{12} = \frac{16.75(1.75)^3}{12} = 7.48 \text{ in}^4$$

24.6

$$\sigma = \frac{Mc}{I} = \frac{(155.0)(1.875)}{7.48} = 18.13 \text{ Ksi}$$

$$\sigma_{\text{allow}} = .55 F_y = .55 (36) = 19.8 \text{ Ksi}$$

✓ okay

For 50 Ksi steel, $\sigma_{\text{allow}} = .55 (50) = 27.5 \text{ Ksi}$
 could use $1\frac{1}{2}'' \text{ PL}$

Use $1\frac{1}{2}''$ Sole Plate (50 Ksi) ←


MASONRY PLATE

Size = $73 \times 16\frac{3}{4}$ "

$A = 1222.75 \text{ in}^2$

load from 1 pad $\approx (15\frac{1}{2} \times 30") (1.25 \text{ ksi}) = 581.25 \text{ k}$

$\sigma = \frac{581.25}{(\frac{1}{2})(1222.75)} \approx .95 \text{ ksi}$



$M = (.95 \text{ ksi})(16.75") (5.5)(\frac{5.5}{2})$

$M \approx 240.68 \text{ k}\cdot\text{k}$

$I = \frac{(16.75)(2^3)}{12} = 11.167 \text{ in}^4$

$\sigma = \frac{MC}{I} = \frac{(240.68)(1")}{11.167 \text{ in}^4} = 21.55 \text{ ksi}$

for 50 ksi steel $\sigma_{allow} = .55(50) = 27.5 \text{ ksi}$

use 2" Masonry plate (50 ksi)

Anchor Bolts

~ 70 K per bearing is required

$$R_n = .48 A_B F_{ub} N_s \quad (6.13.2.12-1)$$

$$N_s = 1$$

$$F_{ub} = 58 \text{ ksi (min)} \quad (A307)$$

$$A_b = \frac{\pi (1.5)^2}{4} \approx 1.767 \text{ in}^2 \quad 1.767 \text{ in}^2 - 1\frac{1}{2} \text{ } \phi$$

$$R_n = .48 (1.767) (58) (1) \approx 49.2 \text{ K/bolt}$$

for A325 Bolts

$$F_{ub} = 100 \text{ ksi}$$

$$R_n = .48 (1.767) (100 \text{ ksi}) (1) \approx 84.8 \text{ K/bolt}$$

$R_n > 70 \text{ K}$ okay

use $1\frac{1}{2} \text{ } \phi$ A325 bolt


$$\text{thread length} = 2 \times \phi + 1\frac{1}{2} \text{ } \approx 3\frac{1}{2} \text{ } \text{''}$$

can use A449 Bolts for greater thread length

thread length $\approx 6 \text{ } \text{''}$

42" |

F 1554 Grade 105



← threads/inch

COLORADO DEPARTMENT OF TRANSPORTATION
DESIGN COMPUTATIONS (Grid)

$$\phi T_n = 4 \phi \sqrt{f'_c} A$$

$$f'_c = 4500 \text{ ksi}$$

$$\phi = .65$$

$$A = \pi \left(\frac{D_p^2}{4} - \frac{D_b^2}{4} \right)$$

$$D_p = 2 l_e + D_b$$

$$D_b = 1\frac{1}{2}''$$

$$l_e = 12''$$

$$D_p = 2(12) + 1\frac{1}{2}''$$

$$= 25\frac{1}{2}''$$


$$A = \pi \left(\frac{25.5^2}{4} - \frac{1.5^2}{4} \right) = 508.9$$

$$\phi T_n = (4)(.65) \sqrt{4500} (508.9) / 1000$$

$$\phi T_n = 88.8 \text{ K}$$





46.57 K for 8 $\frac{1}{2}$ '' embedment

use 12'' embedment



COLORADO DEPARTMENT OF TRANSPORTATION
DESIGN COMPUTATIONS (Grid)

PIER BEARING







By: Date	Project no.	Project code (SA#):
Chk'd: Date	Structure no.	Sheet 392 of

COLORADO DEPARTMENT OF TRANSPORTATION
DESIGN COMPUTATIONS (Grid)

Jack Plates

Girder



By: Date	Project no.:	Project code (SA#):
Chk'd: Date	Structure no.	Sheet <u>393</u> of

CDOT Form #1034 3/02

JACKING POINTS

DEAD LOAD ≈ 439.1 K max

for 2 jacks DL = $439.1/2 \approx 219.6$ K ≈ 110 tons

Use 160 ton jack

$\phi \approx 8\frac{1}{2}"$ $A = 56.75$ in²
 lift $\phi \approx 6.3"$ $A \approx 31.17$ in²

Top Pressure $\approx 219.6/31.17 \approx 7.05$ Ksi

Bottom Pressure $\approx 219.6/56.75 \approx 3.87$ Ksi

Allowable Bearing Stress = $.3 f'_c$

for girder $\sigma_{allow} = .3 (9.0) = 2.7$ Ksi

for pier $\sigma_{allow} = .3 (4.5) = 1.35$ Ksi

Girder Plate

Area_{reqd} ≈ 219.6 KIP / 2.7 Ksi ≈ 81.33 in²

$\Rightarrow 9\frac{1}{2}"$ SQR PL

$10\frac{1}{4}"$ ϕ RND PL

Use $3/4"$ PL minimum

18" SQR
for studs

Pier Plate

Area_{reqd} ≈ 219.6 KIP / 1.35 Ksi ≈ 162.67 in²

$\Rightarrow 13"$ SQR PL

$14\frac{1}{2}"$ RND PL

Use $1\frac{1}{4}"$ PL minimum

SHIM PLATES

DEAD LOAD + LIVE LOAD ≈ 860.6 K

$860.6 / 1.35$ Ksi ≈ 637.5 in² $\Rightarrow 26"$ SQR PL for Live Load

$439.1 / 1.35$ Ksi ≈ 325.3 in² $\Rightarrow 19"$ SQR PL for Dead Load ONLY

By: Date	Project no.	Project code (SA#):
Chk'd: Date	Structure no.	Sheet <u>394</u> of _____

COLORADO DEPARTMENT OF TRANSPORTATION
DESIGN COMPUTATIONS (Grid)

JACK FOR LIVE LOAD & DEAD LOAD

$$\text{DEAD + LIVE LOAD} \approx \frac{860.6 \text{ K}}{2} + \frac{533.8}{3.5} \approx 582.8 \text{ K}$$

$$\approx 291.4 \text{ tons}$$

$$\text{LL} \approx 340.7$$

$$\text{DL} \approx 242.1$$

need 400 ton jack - 7" height

GIRDER R

$$A_{\text{reqd}} \approx \frac{582.8}{2.7 \text{ KSI}} = 215.9 \text{ in}^2 \Rightarrow 15" \text{ SQR R}$$

use 1" R minimum (service loads)
 1 1/4" R for strength I


PIER R

$$A_{\text{reqd}} \approx \frac{582.8}{1.35 \text{ KSI}} = 431.7 \text{ in}^2 \Rightarrow 21" \text{ SQR R}$$

22.5" max

use 2" R minimum (service loads)
 2 1/4" R for strength I

FOR PARTIAL LIVE LOAD



$$\text{DF} = 1.5$$

$$\text{LL} \Rightarrow (L)(25) = 501.4 (1)$$

$$L \approx 20.1 \text{ K}$$

160 ton jack can handle additional 50 tons of force \Rightarrow 100 K

size plates, etc for 400 ton jack
 \Rightarrow least disturbance to traffic

By: _____	Date: _____	Project no. _____	Project code (SA#): _____
Chk'd: _____	Date: _____	Structure no. _____	Sheet <u>395</u> of _____

Flange Width	b_f	9.840 in		
Flange Thickness	t_f	0.705 in		
Nominal Wt. per Ft	r_f	102.000 lb/ft		
Moment of Inertia X-X	I_x	3.970 in ⁴		
Section Modulus X-X	S_x	1050.000 in ³		
Radius of Gyration X-X	r_x	150.000 in		
Moment of Inertia Y-Y	I_y	5.920 in ⁴		
Section Modulus Y-Y	S_y	380.000 in ³		
Radius of Gyration Y-Y	r_y	51.400 in		
Torsional Constant	J	3.560 in ⁴		
Plastic Modulus X-X	Z_x	0.000 in ³		
Plastic Modulus Y-Y	Z_y	169.000 in ³		
		78.800 in ³		
Limiting Slenderness Ratio	K^*L/r	0.03 OK	AASHTO LRFD 6.9.3	
	λ	0.000	AASHTO LRFD Eq. 6.9.4.4-3	
Nominal Compressive Resistance	P_n	1080.00 kips	AASHTO LRFD Eq.'s 6.9.4.1-1 & 2	
Resistance Factor	ϕ_c	0.9	AASHTO LRFD 6.5.4.2	
Compressive Resistance	$\phi_c P_n$	972.000 kips	AASHTO LRFD Eq. 6.9.2.1-1	
Total Resistance	P_r	972 kips	Resistance * Number of Prop Columns	
Use Live Load in Calculations?		YES		
Total Factored Prop Load per Column	P_u	583 kips		
Resistance/Load		1.67 OK		
Combined Axial Compression and Flexure				
Minimum Horizontal Load =		4.84 kips	CDOT Standard Spec. 601.11(c)4	
Wind Pressure =		27.50 psf	Table 3-7 Sign Specs	
Shape Factor =	C_d	0.75	Table 3-6 Sign Specs	
Wind Load =		0.00 kips		
Construction Load =		0 kips		
Moment =	M_c	0.01 ft-kips		
Ultimate Moment =	M_u	0.01 ft-kips		
Nominal flexural resistance =	M_n	236.40 ft-kips	AASHTO LRFD Eq. 6.12.2.2.1-1 or 3-1	
Flexural Resistance =	$\phi_c M_n$	212.76 ft-kips		
Combined Stress Ratio		0.60 OK	AASHTO LRFD Eq. 6.9.2.2-1 or 2	
Shim Bolts				Shim Plates Required
Concrete Bearing-Girder				

Girder - Top Plate interaction:
 Plate area 12"x12" : Girder width = 16";
 Girder edge distance = (16-12)/2 = 2";
 A1 area under plate = 144 and A2 = Girder Notional area = WxW = 16x16
 $m = \sqrt{A2/A1} = 1.33$ and less than 1.5 use 1.33

Bottom plate - Footing Area interaction:
 Plate area 12"x12" : Footing area = 4'x4' = 16 sf
 Footing edge distance = (48"-12)/2 = 1.5 ft
 A1 area under plate = 144 and A2 = footing Notional area = WxW = (16 ft
 $m = \sqrt{A2/A1} = 4$ but greater than 1.5 use 1.5

use m = lesser of the above two = 1.33

AASHTO LRFD Eqn. 5.7.5-3
 AASHTO LRFD Eqn. 5.7.5-2
 AASHTO LRFD 5.5.4.1

Resistance * Number of Prop Columns

B	15 in
N	15 in
	1.3 ft
	2.0 in
	6 ft
	1.5 ft
f_c	9 ksi
A_1	225 in ²
A_2	225 in ²
m	1.00
P_n	1721.25 kips
Φ_b	0.7
$\Phi_b P_n$	1205 kips

1205 kips
 583 kips
 2.1 OK

Total Resistance
 Total Factored Prop Load per Column
 Resistance/Load

Concrete Bearing-Pier

B	21 in
N	21 in
	1.3 ft
	2.0 in
	6 ft
	1.5 ft
f_c	4.5 ksi
A_1	441 in ²
A_2	441 in ²
m	1.00
P_n	1686.825 kips
Φ_b	0.7
$\Phi_b P_n$	1181 kips

21 in
 21 in
 1.3 ft
 2.0 in
 6 ft
 1.5 ft
 4.5 ksi
 441 in²
 441 in²
 1.00
 1686.825 kips
 0.7
 1181 kips

AASHTO LRFD Eqn. 5.7.5-3
 AASHTO LRFD Eqn. 5.7.5-2
 AASHTO LRFD 5.5.4.1

Resistance * Number of Prop Columns

Resistance * Number of Prop Columns

1181 kips
 1050 kips
 1.1 OK

Total Resistance
 Total Factored Prop Load per Column
 Resistance/Load

Base Plate-Bottom (Pier)

B	490 lb/ft ³
N	21 in
T	21 in
	1.5 inch
	187.58 lb

Unit Weight
 Base Plate Width
 Base Plate Length
 Base Plate Thickness
 Plate Weight

Corner bending not checked

Number	1.00 each		
Total Weight	187.58 lb		
Yield Strength	36.0 ksi	ASTM A-36	
Moment of Inertia	0.84375 in ⁴	per inch of plate	
Section Modulus	1.125 in ³	per inch of plate	
Nominal Flexural Strength	40.5 kip-in	per inch of plate	
Resistance Factor	1	AASHTO LRFD 6.5.4.2	
Flexural Strength	40.5 kip-in	per inch of plate	
Column Depth	13.78 in		
Column Flang Width	13.78 in		
Design base plate projection perp. to flange	3.955 in	Beam-Column Base Plate Design - LRFD Method	
Design base plate projection perp. to web	4.988 in	Engineering Journal / First Quarter / 1999	
Between flange bending	3.445 in		
Applied Load per Prop Column	583 kip		
Concrete Bearing Stress	2.590 ksi	Based on Factored Load	
Plate Moment II to flange	20.253 kip-in	per inch of plate	
Plate Moment II to web	32.223 kip-in	per inch of plate	
Plate moment between flanges	15.370 kip-in	per inch of plate	
Max Plate Moment	32.223		
Flexural Strength	41 kip-in		
Resistance/Load	1.26 OK		
Unit Weight	490 lb/ft ³	Corner bending not checked	
Base Plate Width	15 in		
Base Plate Length	15 in		
Base Plate Thickness	7 inch		
Plate Weight	63.80 lb		
Number	1.00 each		
Total Weight	63.80 lb	ASTM A-36	
Yield Strength	36.0 ksi	per inch of plate	
Moment of Inertia	0.25 in ⁴	per inch of plate	
Section Modulus	0.5 in ³	per inch of plate	
Nominal Flexural Strength	18 kip-in	per inch of plate	
Resistance Factor	1	AASHTO LRFD 6.5.4.2	
Flexural Strength	18 kip-in	per inch of plate	
Column Depth	9.840 in		

Base Plate-Top (Girder)

Column Flange Width	b_f	9.840 in	Beam-Column Base Plate Design - LRFD Method Engineering Journal / First Quarter / 1999
Design base plate projection perp. to flange	m	2.826 in	
Design base plate projection perp. to web	n	3.564 in	
Between flange bending	n'	2.460 in	
Applied Load per Prop Column Concrete Bearing Stress	P f_p	583 kip 2.590 ksi	Based on Factored Load
Plate Moment II to flange	M_{pl}	10.343 kip-in	per inch of plate
Plate Moment II to web	M_{pw}	16.451 kip-in	per inch of plate
Plate moment between flanges	M_{pl}	7.838 kip-in	per inch of plate
Max Plate Moment	M_{pl}	16.451	
Flexural Strength	ϕM_n	18 kip-in	
Resistance/Load		1.09	OK

SHEAR AT JACKING POINT

$$V_u \approx 860.6 \text{ K}$$

$$V_c = .0316 B \sqrt{f_c'} d_v$$

@ bearing

$$d_e = d_s \approx 27\frac{1}{2}'' - 2'' - \frac{7}{8}'' - 1.27\frac{1}{2}'' \approx 23.99''$$

$$d_v = .9 d_e = .9 (23.99) \approx 21.59'' \quad \leftarrow \text{controls}$$

$$d_v = .72 H = .72 (27\frac{1}{2}) \approx 19.8''$$

$$M_u \approx 0$$

$$V_u \approx 860.6 \text{ K}$$

$$\epsilon_s = \frac{0}{21.59} + 0 + \frac{860.6 - 0}{29000 (13.97)} \approx .0021$$

$$\beta = \frac{4.8}{1 + 750 \epsilon_s} = \frac{4.8}{1 + 750 (.0021)} \approx 1.85$$


$$\theta = 29 + 3500 \epsilon_s = 29 + 3500 (.0021) \approx 36.35^\circ$$

$$V_c = .0316 (1.85) \sqrt{4.5} (54'') (21.59'')$$

$$V_c \approx 144.6 \text{ K}$$

for $s = 6''$

#7 triplex bar = 3.6 in²



$$V_s = \frac{3.6 (60) 21.59 (\cot 36.35 + \cot 90) \sin 90}{6''}$$

$$V_s = 1056.2$$

$$V_n = 144.6 + 1056.2 = 1200.8$$

$$V_r = .9 (1200.8) \approx 1080.6 \text{ K}$$

By: _____	Date _____	Project no. _____	Project code (SA#): _____
Chk'd: _____	Date _____	Structure no. _____	Sheet 401 of _____



Bentley

Colorado DOT
4201 E. Arkansas Ave. Denver CO 80222

Sheet: DS-1
Job No: BR R600-297

Program: LEAP®
CONSPAN®
Version: 08.01.00.10

Copyright © Bentley Systems, Inc. 1984 - 2008.
www.bentley.com
1-800-778-4277

By: A. Pott
Date: Jan/22/2009
CKD:
Date:

File Name: 76-21-125-21-124 U72C.csl

SHEAR/MOMENT ENVELOPE (& REACTIONS)

SHEAR AND MOMENT ENVELOPE : Span : 5, Beam : 2, SERVICE I
Shears: kips, Moments: kft

		Bearing	Trans	H/2	0.10L	0.20L	0.30L	0.40L	Midspan
Location,	ft	0.00	2.25	3.52	11.65	24.05	36.45	48.85	61.25
Self wt. :	M	0.0	248.7	384.7	1187.2	2176.7	2883.5	3307.5	3448.9
(Max)	V	112.6	108.5	106.2	91.2	68.4	45.6	22.8	0.0
DL-Prec. :	M	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0
DC(Max)	V	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0
DL-Prec. :	M	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0
DW(Max)	V	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0
Deck + :	M	0.0	377.9	584.4	1803.7	3306.9	4380.7	5024.9	5239.7
Haunch (Max)	V	171.1	164.8	161.3	138.5	103.9	69.3	34.6	0.0
Diaphragm :	M	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0
(Max)	V	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0
DL-Comp :	M	-278.7	-248.2	-231.5	-131.1	-1.8	98.8	170.8	214.0
DC(Max)	V	13.8	13.3	13.1	11.6	9.3	7.0	4.6	2.3
DL-Comp :	M	-1324.0	-1179.2	-1099.6	-622.7	-8.4	469.6	811.4	1016.8
DW(Max)	V	65.4	63.4	62.2	55.0	44.0	33.1	22.1	11.1
LL + I :	M+	233.8	218.3	216.5	322.9	878.6	1913.6	2956.0	3646.5
	V	2.4	2.5	2.6	3.3	67.8	83.2	54.4	23.3
LL + I :	M-	-5171.8	-4688.1	-4423.8	-2861.5	-930.9	-41.0	-35.2	-29.3
	V	241.1	234.4	230.7	206.7	136.7	0.5	0.5	0.5
LL + I :	Vmx	236.6	232.4	230.1	214.9	190.2	163.5	135.4	107.1
	M	-2377.3	-2182.4	-2068.4	-1263.8	205.6	1438.5	2323.0	2837.3
Total :	M+	0.0	0.0	0.0	2560.0	6352.0	9746.3	12270.6	13565.9
	V	0.0	0.0	0.0	299.6	293.4	238.1	138.6	36.7
Total :	M-	-6774.5	-5488.9	-4785.8	-624.4	0.0	0.0	0.0	0.0
	V	552.3	534.4	524.3	459.6	0.0	0.0	0.0	0.0
Total :	Vmx	599.5	582.4	572.8	511.3	415.9	318.4	219.5	120.5
	M	-3979.9	-2983.2	-2430.5	973.3	5679.1	9271.1	11637.7	12756.8

		0.60L	0.70L	0.80L	0.90L	H/2	Trans	Bearing
Location,	ft	73.65	86.05	98.45	110.85	118.98	120.25	122.50
Self wt. :	M	3307.5	2883.5	2176.7	1187.2	384.7	248.7	0.0
(Max)	V	22.8	45.6	68.4	91.2	106.2	108.5	112.6
DL-Prec. :	M	0.0	0.0	0.0	0.0	0.0	0.0	0.0
DC(Max)	V	0.0	0.0	0.0	0.0	0.0	0.0	0.0
DL-Prec. :	M	0.0	0.0	0.0	0.0	0.0	0.0	0.0
DW(Max)	V	0.0	0.0	0.0	0.0	0.0	0.0	0.0
Deck + :	M	5024.9	4380.7	3306.9	1803.7	584.4	377.9	0.0
Haunch (Max)	V	34.6	69.3	103.9	138.5	161.3	164.8	171.1
Diaphragm :	M	0.0	0.0	0.0	0.0	0.0	0.0	0.0
(Max)	V	0.0	0.0	0.0	0.0	0.0	0.0	0.0
DL-Comp :	M	228.6	214.5	171.7	100.2	37.3	26.4	6.2
DC(Max)	V	0.0	2.3	4.6	6.9	8.4	8.7	9.1
DL-Comp :	M	1086.0	1018.9	815.6	475.9	177.4	125.5	29.7
DW(Max)	V	0.1	10.9	21.9	32.9	40.1	41.2	43.2
LL + I :	M+	3899.2	3745.4	3081.8	1856.0	696.3	490.3	107.5
	V	49.2	82.6	127.5	163.1	90.3	79.0	58.8
LL + I :	M-	-23.5	-17.6	-11.7	-5.9	-2.0	-1.4	-0.4
	V	0.5	0.5	0.5	0.5	35.6	41.0	50.7
LL + I :	Vmx	81.1	101.5	131.2	164.0	185.5	188.8	194.7



		0.60L	0.70L	0.80L	0.90L	H/2	Trans	Bearing
	M	2895.1	3328.4	2868.7	1792.3	697.5	499.3	128.7
Total :	M+	13546.3	12242.9	9552.6	5423.0	1880.0	1268.8	143.5
	V	106.8	210.7	326.3	432.6	406.3	402.1	394.8
Total :	M-	0.0	0.0	0.0	0.0	0.0	0.0	0.0
	V	0.0	0.0	0.0	0.0	0.0	0.0	0.0
Total :	Vmx	138.6	229.6	330.1	433.5	501.4	512.0	530.8
	M	12542.1	11825.9	9339.6	5359.3	1881.2	1277.8	164.7

REACTIONS (kips), SERVICE I

Load Type		Left Support	Right Support
Self Wt.		112.6	112.6
Deck+Haunch		171.1	171.1
Diaphragm		0.0	0.0
DL-Prec.(DC)		0.0	0.0
DL-Prec.(DW)		0.0	0.0
DL-Comp.(DC)		160.1	72.8
DL-Comp.(DW)		760.7	345.7
Live	(Max)	286.5	96.1
Live	(Min)	-117.9	-0.2
Pedestrian	(Max)	-0.0	-0.0
Pedestrian	(Min)	-0.0	-0.0

Upward reactions are positive.

Live Load reactions are per lane with no distribution factor and no impact.

Non-composite load types are per beam.

Composite and Pedestrian load types are per total bridge width.

SHEAR AND MOMENT ENVELOPE : Span : 5, Beam : 2, SERVICE III

Shears: kips, Moments: kft

Location,	ft	Bearing	Trans	H/2	0.10L	0.20L	0.30L	0.40L	Midspan
Self wt. :	M	0.0	2.25	3.52	11.65	24.05	36.45	48.85	61.25
(Max)	V	112.6	108.5	106.2	91.2	68.4	45.6	22.8	0.0
DL-Prec. :	M	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0
DC(Max)	V	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0
DL-Prec. :	M	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0
DW(Max)	V	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0
Deck + :	M	0.0	377.9	584.4	1803.7	3306.9	4380.7	5024.9	5239.7
Haunch (Max)	V	171.1	164.8	161.3	138.5	103.9	69.3	34.6	0.0
Diaphragm :	M	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0
(Max)	V	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0
DL-Comp. :	M	-278.7	-248.2	-231.5	-131.1	-1.8	98.8	170.8	214.0
DC(Max)	V	13.8	13.3	13.1	11.6	9.3	7.0	4.6	2.3
DL-Comp. :	M	-1324.0	-1179.2	-1099.6	-622.7	-8.4	469.6	811.4	1016.8
DW(Max)	V	65.4	63.4	62.2	55.0	44.0	33.1	22.1	11.1
LL + I. :	M+	187.0	174.7	173.2	258.3	702.9	1530.9	2364.8	2917.2
	V	1.9	2.0	2.1	2.6	54.2	66.5	43.5	18.6



Program: LEAP®
CONSPAN®
Version: 08.01.00.10

Copyright © Bentley Systems, Inc. 1984 - 2008.
www.bentley.com
1-800-778-4277

By: A. Pott
Date: Jan/22/2009
CKD:
Date:

File Name: 76-21-125-21-124 U72C.csl

		Bearing	Trans	H/2	0.10L	0.20L	0.30L	0.40L	Midspan
LL + I :	M-	-4137.4	-3750.5	-3539.0	-2289.2	-744.7	32.8	-28.1	-23.5
	V	192.9	187.6	184.6	165.4	109.4	0.4	0.4	0.4
LL + I :	Vmx	189.3	185.9	184.1	172.0	152.2	130.8	108.3	85.7
	M	-1901.8	-1745.9	-1654.8	-1011.1	164.5	1150.8	1858.4	2269.9
Total :	M+	0.0	0.0	0.0	2495.4	6176.3	9363.5	11679.4	12836.6
	V	0.0	0.0	0.0	299.0	279.9	221.4	127.7	32.0
Total :	M-	-5740.1	-4551.3	-3901.0	-52.1	0.0	0.0	0.0	0.0
	V	504.1	487.5	478.2	418.3	0.0	0.0	0.0	0.0
Total :	Vmx	552.1	535.9	526.8	468.3	377.8	285.7	192.5	99.1
	M	-3504.5	-2546.7	-2016.8	1226.0	5637.9	8983.4	11173.0	12189.3

		0.60L	0.70L	0.80L	0.90L	H/2	Trans	Bearing
Location,	ft	73.65	86.05	98.45	110.85	118.98	120.25	122.50
Self wt. :	M	3307.5	2883.5	2176.7	1187.2	384.7	248.7	0.0
(Max)	V	22.8	45.6	68.4	91.2	106.2	108.5	112.6
DL-Prec. :	M	0.0	0.0	0.0	0.0	0.0	0.0	0.0
DC(Max)	V	0.0	0.0	0.0	0.0	0.0	0.0	0.0
DL-Prec. :	M	0.0	0.0	0.0	0.0	0.0	0.0	0.0
DW(Max)	V	0.0	0.0	0.0	0.0	0.0	0.0	0.0
Deck + :	M	5024.9	4380.7	3306.9	1803.7	584.4	377.9	0.0
Haunch (Max)	V	34.6	69.3	103.9	138.5	161.3	164.8	171.1
Diaphragm :	M	0.0	0.0	0.0	0.0	0.0	0.0	0.0
(Max)	V	0.0	0.0	0.0	0.0	0.0	0.0	0.0
DL-Comp :	M	228.6	214.5	171.7	100.2	37.3	26.4	6.2
DC(Max)	V	0.0	2.3	4.6	6.9	8.4	8.7	9.1
DL-Comp :	M	1086.0	1018.9	815.6	475.9	177.4	125.5	29.7
DW(Max)	V	0.1	10.9	21.9	32.9	40.1	41.2	43.2
LL + I :	M+	3119.4	2996.3	2465.4	1484.8	557.0	392.2	86.0
	V	39.4	66.1	102.0	130.5	72.2	63.2	47.1
LL + I :	M-	-18.8	-14.1	-9.4	-4.7	-1.6	-1.1	-0.3
	V	0.4	0.4	0.4	0.4	28.5	32.8	40.6
LL + I :	Vmx	64.9	81.2	105.0	131.2	148.4	151.0	155.8
	M	2316.1	2662.7	2295.0	1433.8	558.0	399.4	103.0
Total :	M+	12766.4	11493.8	8936.3	5051.8	1740.8	1170.7	122.0
	V	96.9	194.2	300.8	400.0	388.2	386.3	383.1
Total :	M-	0.0	0.0	0.0	0.0	0.0	0.0	0.0
	V	0.0	0.0	0.0	0.0	0.0	0.0	0.0
Total :	Vmx	122.4	209.3	303.8	400.7	464.3	474.2	491.8
	M	11963.1	11160.2	8765.8	5000.8	1741.8	1177.9	138.9

SHEAR AND MOMENT ENVELOPE : Span : 5, Beam : 2, STRENGTH I
Shears: kips, Moments: kft

		Bearing	Trans	H/2	0.10L	0.20L	0.30L	0.40L	Midspan
Location,	ft	0.00	2.25	3.52	11.65	24.05	36.45	48.85	61.25
Self wt. :	M	0.0	310.9	480.8	1484.0	2720.9	3604.3	4134.4	4311.1
(Max)	V	140.8	135.6	132.7	114.0	85.5	57.0	28.5	0.0
Self wt. :	M	0.0	223.9	346.2	1068.5	1959.0	2595.1	2976.8	3104.0
(Min)	V	101.4	97.6	95.5	82.1	61.6	41.0	20.5	0.0
DL-Prec. :	M	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0
DC(Max)	V	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0



Bentley

Colorado DOT
4201 E. Arkansas Ave. Denver CO 80222

Sheet: DS-4
Job No: BR R600-
297

Program: LEAP®
CONSPAN®
Version: 08.01.00.10

Copyright © Bentley Systems, Inc. 1984 - 2008.
www.bentley.com
1-800-778-4277

By: A. Pott
Date: Jan/22/2009
CKD:
Date:

File Name: 76-21-125-21-124 U72C.csl

		Bearing	Trans	H/2	0.10L	0.20L	0.30L	0.40L	Midspan
DL-Prec. :	M	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0
DC(Min)	V	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0
DL-Prec. :	M	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0
DW(Max)	V	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0
DL-Prec. :	M	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0
DW(Min)	V	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0
Deck + :	M	0.0	472.4	730.5	2254.6	4133.6	5475.8	6281.2	6549.6
Haunch (Max)	V	213.9	206.0	201.6	173.2	129.9	86.6	43.3	0.0
Deck + :	M	0.0	340.1	526.0	1623.3	2976.2	3942.6	4522.4	4715.7
Haunch (Min)	V	154.0	148.3	145.1	124.7	93.5	62.3	31.2	0.0
Diaphragm :	M	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0
(Max)	V	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0
Diaphragm :	M	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0
(Min)	V	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0
DL-Comp. :	M	-348.3	-310.2	-289.3	-163.8	-2.2	123.6	213.5	267.5
DC(Max)	V	17.2	16.7	16.4	14.5	11.6	8.7	5.8	2.9
DL-Comp. :	M	-250.8	-223.4	-208.3	-118.0	-1.6	89.0	153.7	192.6
DC(Min)	V	12.4	12.0	11.8	10.4	8.3	6.3	4.2	2.1
DL-Comp. :	M	-1986.0	-1768.8	-1649.4	-934.0	-12.6	704.4	1217.0	1525.2
DW(Max)	V	98.0	95.0	93.4	82.6	66.1	49.6	33.1	16.6
DL-Comp. :	M	-860.6	-766.5	-714.8	-404.8	-5.5	305.3	527.4	660.9
DW(Min)	V	42.5	41.2	40.5	35.8	28.6	21.5	14.3	7.2
LL + I. :	M+	409.2	382.0	378.8	565.0	1537.6	3348.9	5172.9	6381.3
	V	4.1	4.5	4.6	5.7	118.6	145.6	95.2	40.8
LL + I. :	M-	-9050.7	-8204.2	-7741.6	-5007.7	-1629.1	-71.8	-61.6	-51.3
	V	421.9	410.3	403.7	361.7	239.3	0.9	0.9	0.9
LL + I. :	Vmx	414.1	406.8	402.6	376.1	332.9	286.1	236.9	187.5
	M	-4160.2	-3819.2	-3619.8	-2211.7	359.8	2517.3	4065.3	4965.3
Total :	M+	0.0	175.5	667.1	3780.9	8385.0	13257.0	17019.0	19034.8
	V	0.0	457.8	448.6	390.0	411.7	347.4	205.9	60.3
Total :	M-	-11385.0	-9719.3	-8808.2	-3413.8	0.0	0.0	0.0	0.0
	V	698.6	676.9	664.7	586.5	0.0	0.0	0.0	0.0
Total :	Vmx	884.0	860.1	846.7	760.4	626.0	488.0	347.6	207.0
	M	-6494.6	-5114.9	-4347.2	429.0	7199.5	12425.5	15911.4	17618.8

		0.60L	0.70L	0.80L	0.90L	H/2	Trans	Bearing
Location,	ft	73.65	86.05	98.45	110.85	118.98	120.25	122.50
Self wt. :	M	4134.4	3604.3	2720.9	1484.0	480.8	310.9	0.0
(Max)	V	28.5	57.0	85.5	114.0	132.7	135.6	140.8
Self wt. :	M	2976.8	2595.1	1959.0	1068.5	346.2	223.9	0.0
(Min)	V	20.5	41.0	61.6	82.1	95.5	97.6	101.4
DL-Prec. :	M	0.0	0.0	0.0	0.0	0.0	0.0	0.0
DC(Max)	V	0.0	0.0	0.0	0.0	0.0	0.0	0.0
DL-Prec. :	M	0.0	0.0	0.0	0.0	0.0	0.0	0.0
DC(Min)	V	0.0	0.0	0.0	0.0	0.0	0.0	0.0
DL-Prec. :	M	0.0	0.0	0.0	0.0	0.0	0.0	0.0
DW(Max)	V	0.0	0.0	0.0	0.0	0.0	0.0	0.0
DL-Prec. :	M	0.0	0.0	0.0	0.0	0.0	0.0	0.0
DW(Min)	V	0.0	0.0	0.0	0.0	0.0	0.0	0.0
Deck + :	M	6281.2	5475.8	4133.7	2254.6	730.5	472.4	0.0
Haunch (Max)	V	43.3	86.6	129.9	173.2	201.6	206.0	213.9
Deck + :	M	4522.4	3942.6	2976.2	1623.3	526.0	340.1	0.0
Haunch (Min)	V	31.2	62.3	93.5	124.7	145.1	148.3	154.0
Diaphragm :	M	0.0	0.0	0.0	0.0	0.0	0.0	0.0
(Max)	V	0.0	0.0	0.0	0.0	0.0	0.0	0.0
Diaphragm :	M	0.0	0.0	0.0	0.0	0.0	0.0	0.0
(Min)	V	0.0	0.0	0.0	0.0	0.0	0.0	0.0



Program: LEAP®
CONSPAN®
Version: 08.01.00.10

Copyright © Bentley Systems, Inc. 1984 - 2008.
www.bentley.com
1-800-778-4277

By: A. Pott
Date: Jan/22/2009
CKD:
Date:

File Name: 76-21-125-21-124 U72C.csl

		0.60L	0.70L	0.80L	0.90L	H/2	Trans	Bearing
DL-Comp :	M	285.7	268.1	214.6	125.2	46.7	33.0	7.8
DC(Max)	V	0.0	2.9	5.8	8.7	10.5	10.8	11.4
DL-Comp :	M	205.7	193.0	154.5	90.2	33.6	23.8	5.6
DC(Min)	V	0.0	2.1	4.1	6.2	7.6	7.8	8.2
DL-Comp :	M	1629.0	1528.4	1223.3	713.9	266.0	188.2	44.5
DW(Max)	V	0.1	16.4	32.8	49.3	60.1	61.8	64.8
DL-Comp :	M	705.9	662.3	530.1	309.3	115.3	81.6	19.3
DW(Min)	V	0.1	7.1	14.2	21.4	26.1	26.8	28.1
LL + I :	M+	6823.6	6554.4	5393.1	3248.0	1218.5	858.0	188.2
	V	86.2	144.6	223.1	285.4	158.0	138.2	103.0
LL + I :	M-	-41.0	-30.8	-20.5	-10.3	-3.5	-2.5	-0.6
	V	0.9	0.9	0.9	0.9	62.2	71.8	88.7
LL + I :	Vmx	141.9	177.7	229.7	287.0	324.5	330.4	340.8
	M	5066.4	5824.6	5020.2	3136.5	1220.6	873.7	225.3
Total :	M+	19153.9	17431.0	13685.6	7825.7	2742.5	1862.5	240.5
	V	158.1	307.4	477.1	630.5	563.0	552.5	533.8
Total :	M-	0.0	0.0	0.0	0.0	0.0	0.0	0.0
	V	0.0	0.0	0.0	0.0	0.0	0.0	0.0
Total :	Vmx	213.9	340.5	483.7	632.1	729.5	744.7	771.6
	M	17396.7	16701.3	13312.7	7714.2	2744.6	1878.2	277.6

REACTIONS (kips), STRENGTH I

Load Type		Left Support	Right Support
Self Wt.		140.8	140.8
Deck+Haunch		213.9	213.9
Diaphragm		0.0	0.0
DL-Prec.(DC)		0.0	0.0
DL-Prec.(DW)		0.0	0.0
DL-Comp.(DC)		200.1	91.0
DL-Comp.(DW)		1141.0	518.6
Live	(Max)	501.4	168.1
Live	(Min)	-206.4	-0.4
Pedestrian	(Max)	-0.0	-0.0
Pedestrian	(Min)	-0.0	-0.0

Upward reactions are positive.

Live Load reactions are per lane with no distribution factor and no impact.

Non-composite load types are per beam.

Composite and Pedestrian load types are per total bridge width.



Program: LEAP®
CONSPAN®
Version: 08.01.00.10

Copyright © Bentley Systems, Inc. 1984 - 2008.
www.bentley.com
1-800-778-4277

By: A. Pott
Date: Jan/22/2009
CKD:
Date:

File Name: 76-21-125-21-124 U72C.csl

SHEAR/MOMENT ENVELOPE (& REACTIONS)

SHEAR AND MOMENT ENVELOPE : Span : 5, Beam : 1, SERVICE I
Shears: kips, Moments: kft

		Bearing	Trans	H/2	0.10L	0.20L	0.30L	0.40L	Midspan
Location,	ft	0.00	2.25	3.52	11.65	24.05	36.45	48.85	61.25
Self wt. :	M	0.0	248.7	384.7	1187.2	2176.7	2883.5	3307.5	3448.9
(Max)	V	112.6	108.5	106.2	91.2	68.4	45.6	22.8	0.0
DL-Prec. :	M	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0
DC(Max)	V	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0
DL-Prec. :	M	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0
DW(Max)	V	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0
Deck + :	M	0.0	357.6	553.0	1706.8	3129.3	4145.4	4755.1	4958.3
Haunch (Max)	V	161.9	156.0	152.6	131.1	98.3	65.6	32.8	0.0
Diaphragm :	M	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0
(Max)	V	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0
DL-Comp :	M	-262.0	-233.3	-217.6	-123.2	-1.7	92.9	160.5	201.2
DC(Max)	V	12.9	12.5	12.3	10.9	8.7	6.5	4.4	2.2
DL-Comp :	M	-1244.6	-1108.4	-1033.7	-585.3	-7.9	441.4	762.7	955.8
DW(Max)	V	61.4	59.6	58.5	51.7	41.4	31.1	20.7	10.4
LL + I :	M+	258.6	241.4	239.4	357.1	971.6	2116.3	3268.9	4032.6
	V	2.6	2.8	2.9	3.6	75.0	92.0	60.2	25.8
LL + I :	M-	-5719.4	-5184.5	-4892.1	-3164.5	-1029.5	-45.4	-38.9	-32.4
	V	266.6	259.3	255.1	228.6	151.2	0.6	0.6	0.6
LL + I :	Vmx	261.7	257.0	254.4	237.7	210.4	180.8	149.7	118.5
	M	-2629.0	-2413.5	-2287.5	-1397.7	227.4	1590.8	2569.0	3137.8
Total :	M+	0.0	0.0	0.0	2542.5	6268.1	9679.5	12254.8	13596.8
	V	0.0	0.0	0.0	288.6	291.8	240.8	140.9	38.4
Total :	M-	-7225.9	-5919.9	-5205.7	-979.1	0.0	0.0	0.0	0.0
	V	567.0	548.8	538.5	472.7	0.0	0.0	0.0	0.0
Total :	Vmx	610.6	593.6	584.0	522.6	427.2	329.6	230.4	131.1
	M	-4135.5	-3148.9	-2601.0	787.8	5523.9	9154.0	11554.9	12702.0

		0.60L	0.70L	0.80L	0.90L	H/2	Trans	Bearing
Location,	ft	73.65	86.05	98.45	110.85	118.98	120.25	122.50
Self wt. :	M	3307.5	2883.5	2176.7	1187.2	384.7	248.7	0.0
(Max)	V	22.8	45.6	68.4	91.2	106.2	108.5	112.6
DL-Prec. :	M	0.0	0.0	0.0	0.0	0.0	0.0	0.0
DC(Max)	V	0.0	0.0	0.0	0.0	0.0	0.0	0.0
DL-Prec. :	M	0.0	0.0	0.0	0.0	0.0	0.0	0.0
DW(Max)	V	0.0	0.0	0.0	0.0	0.0	0.0	0.0
Deck + :	M	4755.1	4145.4	3129.3	1706.8	553.0	357.6	0.0
Haunch (Max)	V	32.8	65.6	98.3	131.1	152.6	156.0	161.9
Diaphragm :	M	0.0	0.0	0.0	0.0	0.0	0.0	0.0
(Max)	V	0.0	0.0	0.0	0.0	0.0	0.0	0.0
DL-Comp :	M	214.9	201.6	161.4	94.2	35.1	24.8	5.9
DC(Max)	V	0.0	2.2	4.3	6.5	7.9	8.2	8.5
DL-Comp :	M	1020.9	957.8	766.6	447.4	166.7	117.9	27.9
DW(Max)	V	0.1	10.3	20.6	30.9	37.7	38.7	40.6
LL + I :	M+	4312.0	4141.9	3408.1	2052.5	770.0	542.2	118.9
	V	54.4	91.4	141.0	180.3	99.9	87.3	65.1
LL + I :	M-	-25.9	-19.5	-13.0	-6.5	-2.2	-1.6	-0.4
	V	0.6	0.6	0.6	0.6	39.3	45.4	56.1
LL + I :	Vmx	89.7	112.3	145.1	181.4	205.1	208.8	215.4



		0.60L	0.70L	0.80L	0.90L	H/2	Trans	Bearing
	M	3201.6	3680.8	3172.5	1982.0	771.3	552.1	142.4
Total :	M+	13610.4	12330.2	9642.1	5488.1	1909.5	1291.3	152.7
	V	110.1	215.0	332.6	440.1	404.2	398.7	388.7
Total :	M-	0.0	0.0	0.0	0.0	0.0	0.0	0.0
	V	0.0	0.0	0.0	0.0	0.0	0.0	0.0
Total :	Vmx	145.4	235.8	336.8	441.1	509.5	520.1	539.0
	M	12500.0	11869.1	9406.5	5417.6	1910.8	1301.2	176.2

REACTIONS (kips), SERVICE I

Load Type		Left Support	Right Support
Self Wt.		112.6	112.6
Deck+Haunch		161.9	161.9
Diaphragm		0.0	0.0
DL-Prec.(DC)		0.0	0.0
DL-Prec.(DW)		0.0	0.0
DL-Comp.(DC)		160.1	72.8
DL-Comp.(DW)		760.7	345.7
Live	(Max)	286.5	96.1
Live	(Min)	-117.9	-0.2
Pedestrian	(Max)	-0.0	-0.0
Pedestrian	(Min)	-0.0	-0.0

Upward reactions are positive.
Live Load reactions are per lane with no distribution factor and no impact.
Non-composite load types are per beam.
Composite and Pedestrian load types are per total bridge width.

SHEAR AND MOMENT ENVELOPE : Span : 5, Beam : 1, SERVICE III
Shears: kips, Moments: kft

Location,	ft	Bearing	Trans	H/2	0.10L	0.20L	0.30L	0.40L	Midspan
Self wt. :	M	0.0	2.25	3.52	11.65	24.05	36.45	48.85	61.25
(Max)	V	112.6	108.5	106.2	91.2	68.4	45.6	22.8	0.0
DL-Prec. :	M	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0
DC(Max)	V	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0
DL-Prec. :	M	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0
DW(Max)	V	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0
Deck + :	M	0.0	357.6	553.0	1706.8	3129.3	4145.4	4755.1	4958.3
Haunch (Max)	V	161.9	156.0	152.6	131.1	98.3	65.6	32.8	0.0
Diaphragm :	M	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0
(Max)	V	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0
DL-Comp. :	M	-262.0	-233.3	-217.6	-123.2	-1.7	92.9	160.5	201.2
DC(Max)	V	12.9	12.5	12.3	10.9	8.7	6.5	4.4	2.2
DL-Comp. :	M	-1244.6	-1108.4	-1033.7	-585.3	-7.9	441.4	762.7	955.8
DW(Max)	V	61.4	59.6	58.5	51.7	41.4	31.1	20.7	10.4
LL + I :	M+	206.8	193.1	191.5	285.6	777.3	1693.0	2615.2	3226.1
	V	2.1	2.3	2.3	2.9	60.0	73.6	48.1	20.6



Program: LEAP®
CONSPAN®
Version: 08.01.00.10

Copyright © Bentley Systems, Inc. 1984 - 2008.
www.bentley.com
1-800-778-4277

By: A. Pott
Date: Jan/22/2009
CKD:
Date:

File Name: 76-21-125-21-124 U72C.csl

		Bearing	Trans	H/2	0.10L	0.20L	0.30L	0.40L	Midspan
LL + I :	M-	-4575.5	-4147.6	-3913.7	-2531.6	-823.6	-36.3	-31.1	-25.9
	V	213.3	207.4	204.1	182.9	121.0	0.5	0.5	0.5
LL + I :	Vmx	209.3	205.6	203.6	190.2	168.3	144.6	119.8	94.8
	M	-2103.2	-1930.8	-1830.0	-1118.1	181.9	1272.6	2055.2	2510.2
Total :	M+	0.0	0.0	0.0	2471.1	6073.8	9256.3	11601.0	12790.3
	V	0.0	0.0	0.0	287.8	276.8	222.4	128.8	33.2
Total :	M-	-6082.0	-4883.0	-4227.3	-346.2	0.0	0.0	0.0	0.0
	V	513.7	496.9	487.5	427.0	0.0	0.0	0.0	0.0
Total :	Vmx	558.2	542.2	533.1	475.1	385.1	293.4	200.5	107.4
	M	-3609.7	-2666.2	-2143.5	1067.4	5478.4	8835.9	11041.1	12074.4

Location,	ft	0.60L	0.70L	0.80L	0.90L	H/2	Trans	Bearing
Self wt. :	M	3307.5	2883.5	2176.7	1187.2	384.7	248.7	0.0
(Max)	V	22.8	45.6	68.4	91.2	106.2	108.5	112.6
DL-Prec. :	M	0.0	0.0	0.0	0.0	0.0	0.0	0.0
DC(Max)	V	0.0	0.0	0.0	0.0	0.0	0.0	0.0
DL-Prec. :	M	0.0	0.0	0.0	0.0	0.0	0.0	0.0
DW(Max)	V	0.0	0.0	0.0	0.0	0.0	0.0	0.0
Deck + :	M	4755.1	4145.4	3129.3	1706.8	553.0	357.6	0.0
Haunch (Max)	V	32.8	65.6	98.3	131.1	152.6	156.0	161.9
Diaphragm :	M	0.0	0.0	0.0	0.0	0.0	0.0	0.0
(Max)	V	0.0	0.0	0.0	0.0	0.0	0.0	0.0
DL-Comp. :	M	214.9	201.6	161.4	94.2	35.1	24.8	5.9
DC(Max)	V	0.0	2.2	4.3	6.5	7.9	8.2	8.5
DL-Comp. :	M	1020.9	957.8	766.6	447.4	166.7	117.9	27.9
DW(Max)	V	0.1	10.3	20.6	30.9	37.7	38.7	40.6
LL + I :	M+	3449.6	3313.5	2726.5	1642.0	616.0	433.8	95.1
	V	43.6	73.1	112.8	144.3	79.9	69.9	52.0
LL + I :	M-	-20.8	-15.6	-10.4	-5.2	-1.8	-1.3	-0.3
	V	0.5	0.5	0.5	0.5	31.5	36.3	44.9
LL + I :	Vmx	71.8	89.8	116.1	145.1	164.1	167.0	172.3
	M	2561.3	2944.6	2538.0	1585.6	617.1	441.7	113.9
Total :	M+	12748.0	11501.8	8960.5	5077.6	1755.5	1182.8	128.9
	V	99.2	196.7	304.4	404.0	384.3	381.2	375.7
Total :	M-	0.0	0.0	0.0	0.0	0.0	0.0	0.0
	V	0.0	0.0	0.0	0.0	0.0	0.0	0.0
Total :	Vmx	127.4	213.4	307.8	404.8	468.5	478.4	496.0
	M	11859.6	11132.9	8772.0	5021.2	1756.6	1190.8	147.7

SHEAR AND MOMENT ENVELOPE : Span : 5, Beam : 1, STRENGTH I
Shears: kips, Moments: kft

Location,	ft	Bearing	Trans	H/2	0.10L	0.20L	0.30L	0.40L	Midspan
Self wt. :	M	0.0	310.9	480.8	1484.0	2720.9	3604.3	4134.4	4311.1
(Max)	V	140.8	135.6	132.7	114.0	85.5	57.0	28.5	0.0
Self wt. :	M	0.0	223.9	346.2	1068.5	1959.0	2595.1	2976.8	3104.0
(Min)	V	101.4	97.6	95.5	82.1	61.6	41.0	20.5	0.0
DL-Prec. :	M	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0
DC(Max)	V	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0

406



Program: LEAP®
CONSPAN®
Version: 08.01.00.10

Copyright © Bentley Systems, Inc. 1984 - 2008.
www.bentley.com
1-800-778-4277

By: A. Pott
Date: Jan/22/2009
CKD:
Date:

File Name: 76-21-125-21-124 U72C.csl

		Bearing	Trans	H/2	0.10L	0.20L	0.30L	0.40L	Midspan
DL-Prec. :	M	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0
DC(Min)	V	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0
DL-Prec. :	M	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0
DW(Max)	V	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0
DL-Prec. :	M	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0
DW(Min)	V	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0
Deck + :	M	0.0	447.0	691.3	2133.5	3911.7	5181.8	5943.9	6197.9
Haunch (Max)	V	202.4	194.9	190.8	163.9	122.9	81.9	41.0	0.0
Deck + :	M	0.0	321.8	497.7	1536.1	2816.4	3730.9	4279.6	4462.5
Haunch (Min)	V	145.7	140.4	137.3	118.0	88.5	59.0	29.5	0.0
Diaphragm :	M	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0
(Max)	V	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0
Diaphragm :	M	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0
(Min)	V	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0
DL-Comp :	M	-327.4	-291.6	-272.0	-154.0	-2.1	116.1	200.7	251.5
DC(Max)	V	16.2	15.7	15.4	13.6	10.9	8.2	5.5	2.7
DL-Comp :	M	-235.8	-210.0	-195.8	-110.9	-1.5	83.6	144.5	181.1
DC(Min)	V	11.6	11.3	11.1	9.8	7.8	5.9	3.9	2.0
DL-Comp :	M	-1866.8	-1662.6	-1550.5	-878.0	-11.8	662.2	1144.0	1433.7
DW(Max)	V	92.2	89.3	87.8	77.6	62.1	46.6	31.1	15.6
DL-Comp :	M	-809.0	-720.5	-671.9	-380.5	-5.1	286.9	495.7	621.3
DW(Min)	V	39.9	38.7	38.0	33.6	26.9	20.2	13.5	6.8
LL + I :	M+	452.5	422.5	419.0	624.8	1700.4	3703.5	5720.7	7057.0
	V	4.6	4.9	5.1	6.4	131.2	161.0	105.3	45.1
LL + I :	M-	-10009.0	-9072.9	-8561.3	-5537.9	-1801.6	-79.4	-68.1	-56.7
	V	466.6	453.7	446.5	400.0	264.6	1.0	1.0	1.0
LL + I :	Vmx	457.9	449.8	445.3	416.0	368.2	316.4	262.0	207.3
	M	-4600.7	-4223.6	-4003.0	-2445.9	397.9	2783.8	4495.8	5491.1
Total :	M+	0.0	250.0	723.4	3751.0	8326.3	13267.9	17143.6	19251.2
	V	0.0	440.5	431.7	375.4	412.6	354.7	211.4	63.5
Total :	M-	-12203.2	-10481.5	-9539.8	-3965.3	0.0	0.0	0.0	0.0
	V	733.7	711.1	698.5	617.0	0.0	0.0	0.0	0.0
Total :	Vmx	909.4	885.4	871.9	785.1	649.6	510.1	368.1	225.7
	M	-6795.0	-5419.9	-4653.4	139.6	7016.6	12348.3	15918.7	17685.3

		0.60L	0.70L	0.80L	0.90L	H/2	Trans	Bearing
Location,	ft	73.65	86.05	98.45	110.85	118.98	120.25	122.50
Self wt. :	M	4134.4	3604.3	2720.9	1484.0	480.8	310.9	0.0
(Max)	V	28.5	57.0	85.5	114.0	132.7	135.6	140.8
Self wt. :	M	2976.8	2595.1	1959.0	1068.5	346.2	223.9	0.0
(Min)	V	20.5	41.0	61.6	82.1	95.5	97.6	101.4
DL-Prec. :	M	0.0	0.0	0.0	0.0	0.0	0.0	0.0
DC(Max)	V	0.0	0.0	0.0	0.0	0.0	0.0	0.0
DL-Prec. :	M	0.0	0.0	0.0	0.0	0.0	0.0	0.0
DC(Min)	V	0.0	0.0	0.0	0.0	0.0	0.0	0.0
DL-Prec. :	M	0.0	0.0	0.0	0.0	0.0	0.0	0.0
DW(Max)	V	0.0	0.0	0.0	0.0	0.0	0.0	0.0
DL-Prec. :	M	0.0	0.0	0.0	0.0	0.0	0.0	0.0
DW(Min)	V	0.0	0.0	0.0	0.0	0.0	0.0	0.0
Deck + :	M	5943.9	5181.8	3911.7	2133.5	691.3	447.0	0.0
Haunch (Max)	V	41.0	81.9	122.9	163.9	190.8	194.9	202.4
Deck + :	M	4279.6	3730.9	2816.4	1536.1	497.7	321.8	0.0
Haunch (Min)	V	29.5	59.0	88.5	118.0	137.3	140.4	145.7
Diaphragm :	M	0.0	0.0	0.0	0.0	0.0	0.0	0.0
(Max)	V	0.0	0.0	0.0	0.0	0.0	0.0	0.0
Diaphragm :	M	0.0	0.0	0.0	0.0	0.0	0.0	0.0
(Min)	V	0.0	0.0	0.0	0.0	0.0	0.0	0.0



Program: LEAP®
CONSPAN®
Version: 08.01.00.10

Copyright © Bentley Systems, Inc. 1984 - 2008.
www.bentley.com
1-800-778-4277

By: A. Pott
Date: Jan/22/2009
CKD:
Date:

File Name: 76-21-125-21-124 U72C.csl

		0.60L	0.70L	0.80L	0.90L	H/2	Trans	Bearing
DL-Comp :	M	268.6	252.0	201.7	117.7	43.9	31.0	7.3
DC(Max)	V	0.0	2.7	5.4	8.1	9.9	10.2	10.7
DL-Comp :	M	193.4	181.4	145.2	84.7	31.6	22.3	5.3
DC(Min)	V	0.0	1.9	3.9	5.9	7.1	7.3	7.7
DL-Comp :	M	1531.3	1436.7	1149.9	671.0	250.1	176.9	41.9
DW(Max)	V	0.1	15.4	30.9	46.4	56.5	58.1	60.9
DL-Comp :	M	663.6	622.6	498.3	290.8	108.4	76.7	18.1
DW(Min)	V	0.1	6.7	13.4	20.1	24.5	25.2	26.4
LL + I :	M+	7546.1	7248.4	5964.1	3591.9	1347.5	948.8	208.1
	V	95.3	159.9	246.7	315.6	174.8	152.8	113.9
LL + I :	M-	-45.4	-34.0	-22.7	-11.3	-3.9	-2.7	-0.7
	V	1.0	1.0	1.0	1.0	68.8	79.4	98.1
LL + I :	Vmx	157.0	196.5	254.0	317.4	358.9	365.4	376.9
	M	5602.8	6441.4	5551.8	3468.6	1349.8	966.2	249.2
Total :	M+	19424.2	17723.2	13948.3	7998.2	2813.5	1914.7	257.3
	V	164.9	317.0	491.4	648.0	564.7	551.7	528.6
Total :	M-	0.0	0.0	0.0	0.0	0.0	0.0	0.0
	V	0.0	0.0	0.0	0.0	0.0	0.0	0.0
Total :	Vmx	226.6	353.5	498.7	649.8	748.8	764.2	791.6
	M	17481.0	16916.2	13536.0	7874.9	2815.9	1932.1	298.4

REACTIONS (kips), STRENGTH I

Load Type		Left Support	Right Support
Self Wt.		140.8	140.8
Deck+Haunch		202.4	202.4
Diaphragm		0.0	0.0
DL-Prec.(DC)		0.0	0.0
DL-Prec.(DW)		0.0	0.0
DL-Comp.(DC)		200.1	91.0
DL-Comp.(DW)		1141.0	518.6
Live	(Max)	501.4	168.1
Live	(Min)	-206.4	-0.4
Pedestrian	(Max)	-0.0	-0.0
Pedestrian	(Min)	-0.0	-0.0

Upward reactions are positive.

Live Load reactions are per lane with no distribution factor and no impact.

Non-composite load types are per beam.

Composite and Pedestrian load types are per total bridge width.



Program: LEAP®
CONSPAN®
Version: 08.01.00.10
File Name: 76-21-125-21-124_U72C.csl

Copyright © Bentley Systems, Inc. 1984 - 2008.
www.bentley.com
1-800-778-4277

By: A. Pott
Date: Jan/22/2009
CKD:
Date:

SHEAR/MOMENT ENVELOPE (& REACTIONS)

SHEAR AND MOMENT ENVELOPE : Span : 3, Beam : 2, SERVICE I
Shears: kips, Moments: kft

Location,	ft	Bearing	Trans	H/2	0.10L	0.20L	0.30L	0.40L	Midspan
Self wt. :	M	0.0	226.2	392.7	1218.7	2256.6	2998.0	3442.8	3591.1
(Max)	V	114.9	111.2	108.4	93.4	70.1	46.7	23.4	0.0
DL-Prec. :	M	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0
DC(Max)	V	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0
DL-Prec. :	M	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0
DW(Max)	V	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0
Deck + :	M	0.0	343.6	596.7	1851.4	3428.3	4554.7	5230.5	5455.7
Haunch (Max)	V	174.6	169.0	164.8	141.9	106.4	71.0	35.5	0.0
Diaphragm :	M	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0
(Max)	V	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0
DL-Comp :	M	-218.0	-193.9	-176.3	-92.5	15.4	93.3	141.0	158.7
DC(Max)	V	11.9	11.5	11.2	9.7	7.3	4.9	2.6	0.2
DL-Comp :	M	-1035.9	-921.0	-837.4	-439.6	73.2	443.0	670.0	753.9
DW(Max)	V	56.4	54.6	53.3	46.0	34.8	23.5	12.2	1.0
LL + I :	M+	183.1	181.1	187.4	337.1	956.4	1902.2	2587.8	2813.0
	V	7.3	17.0	24.4	64.2	135.8	125.2	92.3	56.5
LL + I :	M-	-4025.0	-3636.2	-3352.4	-1986.7	-419.3	-40.0	-30.9	-22.7
	V	218.8	210.1	203.5	168.0	72.4	2.7	0.8	0.8
LL + I :	Vmx	223.8	220.2	217.4	202.4	173.4	142.4	111.1	81.3
	M	-1855.7	-1645.3	-1486.2	-633.7	669.2	1653.4	2216.2	2335.3
Total :	M+	0.0	0.0	163.1	2875.0	6729.9	9991.1	12072.1	12772.5
	V	0.0	0.0	362.1	355.1	354.3	271.3	165.9	57.6
Total :	M-	-5279.0	-4181.3	-3376.7	0.0	0.0	0.0	0.0	0.0
	V	576.6	556.5	541.2	0.0	0.0	0.0	0.0	0.0
Total :	Vmx	581.6	566.5	555.1	493.4	392.0	288.5	184.8	82.5
	M	-3109.6	-2190.4	-1510.4	1904.3	6442.7	9742.3	11700.4	12294.8

Location,	ft	0.60L	0.70L	0.80L	0.90L	H/2	Trans	Bearing
Self wt. :	M	3442.8	2998.0	2256.6	1218.7	392.8	226.2	0.0
(Max)	V	23.4	46.7	70.1	93.4	108.4	111.2	114.9
DL-Prec. :	M	0.0	0.0	0.0	0.0	0.0	0.0	0.0
DC(Max)	V	0.0	0.0	0.0	0.0	0.0	0.0	0.0
DL-Prec. :	M	0.0	0.0	0.0	0.0	0.0	0.0	0.0
DW(Max)	V	0.0	0.0	0.0	0.0	0.0	0.0	0.0
Deck + :	M	5230.5	4554.7	3428.3	1851.4	596.7	343.6	0.0
Haunch (Max)	V	35.5	71.0	106.4	141.9	164.8	169.0	174.6
Diaphragm :	M	0.0	0.0	0.0	0.0	0.0	0.0	0.0
(Max)	V	0.0	0.0	0.0	0.0	0.0	0.0	0.0
DL-Comp :	M	146.3	103.8	31.2	-71.5	-150.0	-167.4	-191.6
DC(Max)	V	2.2	4.5	6.9	9.3	10.8	11.1	11.5
DL-Comp :	M	694.9	493.0	148.1	-339.7	-712.8	-795.2	-910.3
DW(Max)	V	10.3	21.5	32.8	44.0	51.3	52.6	54.4
LL + I :	M+	2617.1	1960.2	1027.6	417.6	335.3	346.8	374.7
	V	89.7	123.8	134.5	62.9	25.7	18.8	9.7
LL + I :	M-	-31.8	-41.0	-400.4	-1947.2	-3301.7	-3583.5	-3969.9
	V	0.8	1.5	71.0	166.6	202.1	208.7	217.4
LL + I :	Vmx	109.8	141.0	172.0	201.0	216.1	218.9	222.5



		0.60L	0.70L	0.80L	0.90L	H/2	Trans	Bearing
	M	2205.6	1658.9	690.2	-598.5	-1442.8	-1600.5	-1809.0
Total :	M+	12131.6	10109.6	6891.8	3076.5	461.9	0.0	0.0
	V	160.9	267.5	350.6	351.6	361.0	0.0	0.0
Total :	M-	0.0	0.0	0.0	0.0	-3175.1	-3976.4	-5071.8
	V	0.0	0.0	0.0	0.0	537.4	552.6	572.7
Total :	Vmx	181.0	284.7	388.2	489.7	551.4	562.8	577.9
	M	11720.1	9808.4	6554.4	2060.4	-1316.2	-1993.4	-2910.8

REACTIONS (kips), SERVICE I

Load Type		Left Support	Right Support
Self Wt.		114.9	114.9
Deck+Haunch		174.6	174.6
Diaphragm		0.0	0.0
DL-Prec.(DC)		0.0	0.0
DL-Prec.(DW)		0.0	0.0
DL-Comp.(DC)		165.2	72.7
DL-Comp.(DW)		785.0	345.5
Live	(Max)	243.7	237.5
Live	(Min)	-70.7	-158.2
Pedestrian	(Max)	-0.0	-0.0
Pedestrian	(Min)	-0.0	-0.0

Upward reactions are positive.
Live Load reactions are per lane with no distribution factor and no impact.
Non-composite load types are per beam.
Composite and Pedestrian load types are per total bridge width.

SHEAR AND MOMENT ENVELOPE : Span : 3, Beam : 2, SERVICE III
Shears: kips, Moments: kft

Location,	ft	Bearing	Trans	H/2	0.10L	0.20L	0.30L	0.40L	Midspan
Self wt. :	M	0.0	226.2	392.7	1218.7	2256.6	2998.0	3442.8	3591.1
(Max)	V	114.9	111.2	108.4	93.4	70.1	46.7	23.4	0.0
DL-Prec. :	M	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0
DC(Max)	V	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0
DL-Prec. :	M	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0
DW(Max)	V	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0
Deck + :	M	0.0	343.6	596.7	1851.4	3428.3	4554.7	5230.5	5455.7
Haunch (Max)	V	174.6	169.0	164.8	141.9	106.4	71.0	35.5	0.0
Diaphragm :	M	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0
(Max)	V	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0
DL-Comp. :	M	-218.0	-193.9	-176.3	-92.5	15.4	93.3	141.0	158.7
DC(Max)	V	11.9	11.5	11.2	9.7	7.3	4.9	2.6	0.2
DL-Comp. :	M	-1035.9	-921.0	-837.4	-439.6	73.2	443.0	670.0	753.9
DW(Max)	V	56.4	54.6	53.3	46.0	34.8	23.5	12.2	1.0
LL + I :	M+	146.4	144.9	149.9	269.7	765.1	1521.8	2070.3	2250.4
	V	5.9	13.6	19.5	51.3	108.6	100.2	73.8	45.2



Program: LEAP®
CONSPAN®
Version: 08.01.00.10

Copyright © Bentley Systems, Inc. 1984 - 2008.
www.bentley.com
1-800-778-4277

By: A. Pott
Date: Jan/22/2009
CKD:
Date:

File Name: 76-21-125-21-124 U72C.csl

		Bearing	Trans	H/2	0.10L	0.20L	0.30L	0.40L	Midspan
LL + I :	M-	-3220.0	-2909.0	-2682.0	-1589.4	-335.5	-32.0	-24.7	-18.2
	V	175.1	168.1	162.8	134.4	57.9	2.1	0.6	0.7
LL + I :	Vmx	179.1	176.1	173.9	161.9	138.7	113.9	88.9	65.0
	M	-1484.5	-1316.2	-1188.9	-506.9	535.3	1322.7	1772.9	1868.3
Total :	M+	0.0	0.0	125.6	2807.6	6538.6	9610.7	11554.5	12209.8
	V	0.0	0.0	357.2	342.3	327.2	246.3	147.5	46.4
Total :	M-	-4474.0	-3454.1	-2706.2	0.0	0.0	0.0	0.0	0.0
	V	532.8	514.4	500.5	0.0	0.0	0.0	0.0	0.0
Total :	Vmx	536.8	522.5	511.6	452.9	357.3	260.0	162.6	66.2
	M	-2738.5	-1861.4	-1213.2	2031.0	6308.8	9411.7	11257.2	11827.7

		0.60L	0.70L	0.80L	0.90L	H/2	Trans	Bearing
Location,	ft	75.20	87.90	100.60	113.30	121.48	123.00	125.00
Self wt. :	M	3442.8	2998.0	2256.6	1218.7	392.8	226.2	0.0
(Max)	V	23.4	46.7	70.1	93.4	108.4	111.2	114.9
DL-Prec. :	M	0.0	0.0	0.0	0.0	0.0	0.0	0.0
DC(Max)	V	0.0	0.0	0.0	0.0	0.0	0.0	0.0
DL-Prec. :	M	0.0	0.0	0.0	0.0	0.0	0.0	0.0
DW(Max)	V	0.0	0.0	0.0	0.0	0.0	0.0	0.0
Deck + :	M	5230.5	4554.7	3428.3	1851.4	596.7	343.6	0.0
Haunch (Max)	V	35.5	71.0	106.4	141.9	164.8	169.0	174.6
Diaphragm :	M	0.0	0.0	0.0	0.0	0.0	0.0	0.0
(Max)	V	0.0	0.0	0.0	0.0	0.0	0.0	0.0
DL-Comp :	M	146.3	103.8	31.2	-71.5	-150.0	-167.4	-191.6
DC(Max)	V	2.2	4.5	6.9	9.3	10.8	11.1	11.5
DL-Comp :	M	694.9	493.0	148.1	-339.7	-712.8	-795.2	-910.3
DW(Max)	V	10.3	21.5	32.8	44.0	51.3	52.6	54.4
LL + I :	M+	2093.6	1568.1	822.0	334.1	268.2	277.4	299.8
	V	71.7	99.1	107.6	50.4	20.5	15.0	7.7
LL + I :	M-	-25.5	-32.8	-320.3	-1557.8	-2641.3	-2866.8	-3175.9
	V	0.7	1.2	56.8	133.2	161.7	166.9	173.9
LL + I :	Vmx	87.8	112.8	137.6	160.8	172.9	175.1	178.0
	M	1764.5	1327.1	552.2	-478.8	-1154.2	-1280.4	-1447.2
Total :	M+	11608.2	9717.6	6686.3	2993.0	394.8	0.0	0.0
	V	143.0	242.8	323.7	339.0	355.8	0.0	0.0
Total :	M-	0.0	0.0	0.0	0.0	-2514.8	-3259.7	-4277.8
	V	0.0	0.0	0.0	0.0	497.0	510.9	529.2
Total :	Vmx	159.1	256.5	353.8	449.5	508.2	519.0	533.4
	M	11279.0	9476.6	6416.4	2180.1	-1027.6	-1673.3	-2549.1

SHEAR AND MOMENT ENVELOPE : Span : 3, Beam : 2, STRENGTH I
Shears: kips, Moments: kft

		Bearing	Trans	H/2	0.10L	0.20L	0.30L	0.40L	Midspan
Location,	ft	0.00	2.00	3.52	11.70	24.40	37.10	49.80	62.50
Self wt. :	M	0.0	282.7	490.9	1523.3	2820.8	3747.5	4303.5	4488.9
(Max)	V	143.6	139.0	135.6	116.8	87.6	58.4	29.2	0.0
Self wt. :	M	0.0	203.5	353.5	1096.8	2030.9	2698.2	3098.5	3232.0
(Min)	V	103.4	100.1	97.6	84.1	63.0	42.0	21.0	0.0
DL-Prec. :	M	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0
DC(Max)	V	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0



Program: LEAP@
CONSPAN@
Version: 08.01.00.10

Copyright © Bentley Systems, Inc. 1984 - 2008.
www.bentley.com
1-800-778-4277

By: A. Pott
Date: Jan/22/2009
CKD:
Date:

File Name: 76-21-125-21-124 U72C.csl

		Bearing	Trans	H/2	0.10L	0.20L	0.30L	0.40L	Midspan
DL-Prec. :	M	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0
DC(Min)	V	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0
DL-Prec. :	M	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0
DW(Max)	V	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0
DL-Prec. :	M	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0
DW(Min)	V	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0
Deck + :	M	0.0	429.5	745.8	2314.3	4285.4	5693.3	6538.1	6819.7
Haunch (Max)	V	218.2	211.2	206.0	177.4	133.0	88.7	44.3	0.0
Deck + :	M	0.0	309.2	537.0	1666.3	3085.5	4099.2	4707.4	4910.2
Haunch (Min)	V	157.1	152.1	148.3	127.7	95.8	63.9	31.9	0.0
Diaphragm :	M	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0
(Max)	V	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0
Diaphragm :	M	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0
(Min)	V	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0
DL-Comp. :	M	-272.6	-242.3	-220.3	-115.7	19.3	116.6	176.3	198.4
DC(Max)	V	14.8	14.4	14.0	12.1	9.1	6.2	3.2	0.3
DL-Comp. :	M	-196.2	-174.5	-158.6	-83.3	13.9	83.9	126.9	142.8
DC(Min)	V	10.7	10.3	10.1	8.7	6.6	4.5	2.3	0.2
DL-Comp. :	M	-1553.9	-1381.5	-1256.1	-659.5	109.8	664.6	1004.9	1130.9
DW(Max)	V	84.6	81.9	79.9	69.0	52.1	35.2	18.4	1.5
DL-Comp. :	M	-673.4	-598.6	-544.3	-285.8	47.6	288.0	435.5	490.1
DW(Min)	V	36.6	35.5	34.6	29.9	22.6	15.3	8.0	0.6
LL + I :	M+	320.4	316.9	327.9	589.9	1673.6	3328.8	4528.7	4922.8
	V	12.8	29.8	42.7	112.3	237.6	219.1	161.5	98.8
LL + I :	M-	-7043.7	-6363.3	-5866.8	-3476.8	-733.8	-70.0	-54.1	-39.8
	V	382.9	367.7	356.2	294.0	126.7	4.7	1.4	1.4
LL + I :	Vmx	391.7	385.3	380.4	354.2	303.5	249.2	194.5	142.3
	M	-3247.4	-2879.3	-2600.8	-1108.9	1171.0	2893.4	3878.3	4086.8
Total :	M+	0.0	255.9	861.7	4058.5	8908.8	13550.8	16551.5	17560.5
	V	0.0	426.0	428.9	487.5	519.5	407.6	256.6	100.5
Total :	M-	-8870.2	-7474.4	-6452.8	-1488.8	0.0	0.0	0.0	0.0
	V	742.9	716.2	696.0	520.8	0.0	0.0	0.0	0.0
Total :	Vmx	853.0	831.9	815.8	729.4	585.3	437.7	289.6	144.0
	M	-5073.9	-3790.9	-2840.5	1953.6	8406.2	13115.4	15901.1	16724.6

		0.60L	0.70L	0.80L	0.90L	H/2	Trans	Bearing
Location,	ft	75.20	87.90	100.60	113.30	121.48	123.00	125.00
Self wt. :	M	4303.5	3747.5	2820.8	1523.3	490.9	282.7	0.0
(Max)	V	29.2	58.4	87.6	116.8	135.6	139.0	143.6
Self wt. :	M	3098.5	2698.2	2030.9	1096.8	353.5	203.5	0.0
(Min)	V	21.0	42.0	63.0	84.1	97.6	100.1	103.4
DL-Prec. :	M	0.0	0.0	0.0	0.0	0.0	0.0	0.0
DC(Max)	V	0.0	0.0	0.0	0.0	0.0	0.0	0.0
DL-Prec. :	M	0.0	0.0	0.0	0.0	0.0	0.0	0.0
DC(Min)	V	0.0	0.0	0.0	0.0	0.0	0.0	0.0
DL-Prec. :	M	0.0	0.0	0.0	0.0	0.0	0.0	0.0
DW(Max)	V	0.0	0.0	0.0	0.0	0.0	0.0	0.0
DL-Prec. :	M	0.0	0.0	0.0	0.0	0.0	0.0	0.0
DW(Min)	V	0.0	0.0	0.0	0.0	0.0	0.0	0.0
Deck + :	M	6538.1	5693.3	4285.4	2314.3	745.9	429.5	0.0
Haunch (Max)	V	44.3	88.7	133.0	177.4	206.0	211.2	218.2
Deck + :	M	4707.4	4099.2	3085.5	1666.3	537.0	309.2	0.0
Haunch (Min)	V	31.9	63.9	95.8	127.7	148.3	152.1	157.1
Diaphragm :	M	0.0	0.0	0.0	0.0	0.0	0.0	0.0
(Max)	V	0.0	0.0	0.0	0.0	0.0	0.0	0.0
Diaphragm :	M	0.0	0.0	0.0	0.0	0.0	0.0	0.0
(Min)	V	0.0	0.0	0.0	0.0	0.0	0.0	0.0



Program: LEAP®
CONSPAN®
Version: 08.01.00.10

Copyright © Bentley Systems, Inc. 1984 - 2008.
www.bentley.com
1-800-778-4277

By: A. Pott
Date: Jan/22/2009
CKD:
Date:

File Name: 76-21-125-21-124 U72C.csl

		0.60L	0.70L	0.80L	0.90L	H/2	Trans	Bearing
DL-Comp :	M	182.8	129.7	39.0	-89.4	-187.5	-209.2	-239.5
DC(Max)	V	2.7	5.7	8.6	11.6	13.5	13.8	14.3
DL-Comp :	M	131.6	93.4	28.1	-64.4	-135.0	-150.6	-172.4
DC(Min)	V	1.9	4.1	6.2	8.3	9.7	10.0	10.3
DL-Comp :	M	1042.4	739.5	222.2	-509.6	-1069.2	-1192.9	-1365.4
DW(Max)	V	15.4	32.3	49.2	66.1	76.9	79.0	81.6
DL-Comp :	M	451.7	320.5	96.3	-220.8	-463.3	-516.9	-591.7
DW(Min)	V	6.7	14.0	21.3	28.6	33.3	34.2	35.4
LL + I :	M+	4579.9	3430.3	1798.2	730.8	586.8	606.9	655.7
	V	156.9	216.7	235.3	110.2	44.9	32.8	16.9
LL + I :	M-	-55.7	-71.8	-700.7	-3407.6	-5777.9	-6271.1	-6947.3
	V	1.4	2.7	124.3	291.5	353.7	365.2	380.4
LL + I :	Vmx	192.1	246.8	301.1	351.8	378.1	383.0	389.4
	M	3859.8	2903.1	1207.9	-1047.3	-2524.9	-2800.8	-3165.7
Total :	M+	16646.7	13740.4	9165.5	4283.3	1225.2	651.5	0.0
	V	248.6	401.7	513.7	481.9	429.5	427.3	0.0
Total :	M-	0.0	0.0	0.0	-1243.5	-6144.2	-7160.5	-8552.2
	V	0.0	0.0	0.0	517.6	690.0	710.2	736.9
Total :	Vmx	283.7	431.8	579.5	723.6	810.1	826.1	847.2
	M	15926.7	13213.2	8575.2	2191.4	-2544.9	-3490.7	-4770.6

REACTIONS (kips), STRENGTH I

Load Type		Left Support	Right Support
Self Wt.		143.6	143.6
Deck+Haunch		218.2	218.2
Diaphragm		0.0	0.0
DL-Prec.(DC)		0.0	0.0
DL-Prec.(DW)		0.0	0.0
DL-Comp.(DC)		206.5	90.9
DL-Comp.(DW)		1177.5	518.3
Live	(Max)	426.6	415.7
Live	(Min)	-123.8	-276.8
Pedestrian	(Max)	-0.0	-0.0
Pedestrian	(Min)	-0.0	-0.0

Upward reactions are positive.
Live Load reactions are per lane with no distribution factor and no impact.
Non-composite load types are per beam.
Composite and Pedestrian load types are per total bridge width.



SHEAR/MOMENT ENVELOPE (& REACTIONS)

SHEAR AND MOMENT ENVELOPE : Span : 3, Beam : 1, SERVICE I
Shears: kips, Moments: kft

		Bearing	Trans	H/2	0.10L	0.20L	0.30L	0.40L	Midspan
Location,	ft	0.00	2.00	3.52	11.70	24.40	37.10	49.80	62.50
Self wt. :	M	0.0	226.2	392.7	1218.7	2256.6	2998.0	3442.8	3591.1
(Max)	V	114.9	111.2	108.4	93.4	70.1	46.7	23.4	0.0
DL-Prec. :	M	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0
DC(Max)	V	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0
DL-Prec. :	M	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0
DW(Max)	V	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0
Deck + :	M	0.0	325.1	564.6	1752.0	3244.2	4310.1	4949.6	5162.8
Haunch (Max)	V	165.2	159.9	155.9	134.3	100.7	67.1	33.6	0.0
Diaphragm :	M	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0
(Max)	V	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0
DL-Comp. :	M	-205.0	-182.2	-165.7	-87.0	14.5	87.7	132.6	149.2
DC(Max)	V	11.2	10.8	10.5	9.1	6.9	4.6	2.4	0.2
DL-Comp. :	M	-973.8	-865.7	-787.2	-413.3	68.8	416.5	629.8	708.7
DW(Max)	V	53.0	51.3	50.1	43.2	32.7	22.1	11.5	0.9
LL + I :	M+	202.4	200.3	207.2	372.8	1057.6	2103.6	2861.8	3110.8
	V	8.1	18.8	27.0	70.9	150.2	138.5	102.0	62.4
LL + I :	M-	-4451.2	-4021.2	-3707.4	-2197.1	-463.7	-44.3	-34.2	-25.1
	V	242.0	232.4	225.1	185.8	80.1	3.0	0.9	0.9
LL + I :	Vmx	247.5	243.5	240.4	223.8	191.8	157.5	122.9	89.9
	M	-2052.2	-1819.5	-1643.5	-700.8	740.0	1828.4	2450.8	2582.6
Total :	M+	0.0	0.0	211.7	2843.2	6641.7	9915.8	12016.6	12722.6
	V	0.0	0.0	352.0	351.0	360.5	279.1	172.9	63.6
Total :	M-	-5629.9	-4517.9	-3702.9	0.0	0.0	0.0	0.0	0.0
	V	586.3	565.7	550.1	0.0	0.0	0.0	0.0	0.0
Total :	Vmx	591.8	576.8	565.4	503.9	402.1	298.0	193.8	91.0
	M	-3230.9	-2316.2	-1639.0	1769.7	6324.1	9640.6	11605.5	12194.3

		0.60L	0.70L	0.80L	0.90L	H/2	Trans	Bearing
Location,	ft	75.20	87.90	100.60	113.30	121.48	123.00	125.00
Self wt. :	M	3442.8	2998.0	2256.6	1218.7	392.8	226.2	0.0
(Max)	V	23.4	46.7	70.1	93.4	108.4	111.2	114.9
DL-Prec. :	M	0.0	0.0	0.0	0.0	0.0	0.0	0.0
DC(Max)	V	0.0	0.0	0.0	0.0	0.0	0.0	0.0
DL-Prec. :	M	0.0	0.0	0.0	0.0	0.0	0.0	0.0
DW(Max)	V	0.0	0.0	0.0	0.0	0.0	0.0	0.0
Deck + :	M	4949.6	4310.1	3244.2	1752.0	564.6	325.1	0.0
Haunch (Max)	V	33.6	67.1	100.7	134.3	155.9	159.9	165.2
Diaphragm :	M	0.0	0.0	0.0	0.0	0.0	0.0	0.0
(Max)	V	0.0	0.0	0.0	0.0	0.0	0.0	0.0
DL-Comp. :	M	137.5	97.5	29.3	-67.2	-141.0	-157.3	-180.1
DC(Max)	V	2.0	4.3	6.5	8.7	10.1	10.4	10.8
DL-Comp. :	M	653.2	463.4	139.2	-319.3	-670.0	-747.5	-855.7
DW(Max)	V	9.7	20.2	30.8	41.4	48.2	49.5	51.1
LL + I :	M+	2894.2	2167.7	1136.4	461.8	370.8	383.5	414.4
	V	99.2	136.9	148.7	69.6	28.4	20.8	10.7
LL + I :	M-	-35.2	-45.4	-442.8	-2153.4	-3651.3	-3962.9	-4390.2
	V	0.9	1.7	78.6	184.2	223.5	230.8	240.4
LL + I :	Vmx	121.4	155.9	190.3	222.3	238.9	242.0	246.1



		0.60L	0.70L	0.80L	0.90L	H/2	Trans	Bearing
Total :	M	2439.1	1834.6	763.3	-661.8	-1595.6	-1769.9	-2000.5
	M+	12077.3	10036.8	6805.7	3046.0	517.1	29.9	0.0
	V	167.8	275.3	356.8	347.4	351.1	351.8	0.0
Total :	M-	0.0	0.0	0.0	0.0	-3505.0	-4316.5	-5426.0
	V	0.0	0.0	0.0	0.0	546.2	561.8	582.4
Total :	Vmx	190.0	294.3	398.3	500.1	561.7	573.1	588.1
	M	11622.3	9703.6	6432.7	1922.3	-1449.2	-2123.5	-3036.3

REACTIONS (kips), SERVICE I

Load Type		Left Support	Right Support
Self Wt.		114.9	114.9
Deck+Haunch		165.2	165.2
Diaphragm		0.0	0.0
DL-Prec.(DC)		0.0	0.0
DL-Prec.(DW)		0.0	0.0
DL-Comp.(DC)		165.2	72.7
DL-Comp.(DW)		785.0	345.5
Live (Max)		243.7	237.5
Live (Min)		-70.7	-158.2
Pedestrian (Max)		-0.0	-0.0
Pedestrian (Min)		-0.0	-0.0

Upward reactions are positive.
Live Load reactions are per lane with no distribution factor and no impact.
Non-composite load types are per beam.
Composite and Pedestrian load types are per total bridge width.

SHEAR AND MOMENT ENVELOPE : Span : 3, Beam : 1, SERVICE III

Shears: kips, Moments: kft

Location,	ft	Bearing	Trans	H/2	0.10L	0.20L	0.30L	0.40L	Midspan
Self wt. :	M	0.0	226.2	392.7	1218.7	2256.6	2998.0	3442.8	3591.1
(Max)	V	114.9	111.2	108.4	93.4	70.1	46.7	23.4	0.0
DL-Prec. :	M	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0
DC(Max)	V	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0
DL-Prec. :	M	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0
DW(Max)	V	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0
Deck + :	M	0.0	325.1	564.6	1752.0	3244.2	4310.1	4949.6	5162.8
Haunch (Max)	V	165.2	159.9	155.9	134.3	100.7	67.1	33.6	0.0
Diaphragm :	M	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0
(Max)	V	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0
DL-Comp. :	M	-205.0	-182.2	-165.7	-87.0	14.5	87.7	132.6	149.2
DC(Max)	V	11.2	10.8	10.5	9.1	6.9	4.6	2.4	0.2
DL-Comp. :	M	-973.8	-865.7	-787.2	-413.3	68.8	416.5	629.8	708.7
DW(Max)	V	53.0	51.3	50.1	43.2	32.7	22.1	11.5	0.9
LL + I :	M+	162.0	160.2	165.8	298.2	846.1	1682.9	2289.5	2488.7
	V	6.5	15.1	21.6	56.8	120.1	110.8	81.6	49.9



Program: LEAP®
CONSPAN®
Version: 08.01.00.10

Copyright © Bentley Systems, Inc. 1984 - 2008.
www.bentley.com
1-800-778-4277

By: A. Pott
Date: Jan/22/2009
CKD:
Date:

File Name: 76-21-125-21-124_U72C.csl

		Bearing	Trans	H/2	0.10L	0.20L	0.30L	0.40L	Midspan
LL + I :	M-	-3560.9	-3217.0	-2965.9	-1757.7	-371.0	-35.4	-27.4	-20.1
	V	193.6	185.9	180.1	148.6	64.1	2.4	0.7	0.7
LL + I :	Vmx	198.0	194.8	192.3	179.1	153.4	126.0	98.3	71.9
	M	-1641.7	-1455.6	-1314.8	-560.6	592.0	1462.8	1960.7	2066.1
Total :	M+	0.0	0.0	170.3	2768.7	6430.2	9495.1	11444.2	12100.4
	V	0.0	0.0	346.6	336.8	330.4	251.4	152.5	51.1
Total :	M-	-4739.7	-3713.6	-2961.4	0.0	0.0	0.0	0.0	0.0
	V	537.9	519.2	505.0	0.0	0.0	0.0	0.0	0.0
Total :	Vmx	542.3	528.1	517.3	459.1	363.7	266.6	169.2	73.1
	M	-2820.5	-1952.3	-1310.3	1909.8	6176.1	9274.9	11115.4	11677.8

		0.60L	0.70L	0.80L	0.90L	H/2	Trans	Bearing
Location,	ft	75.20	87.90	100.60	113.30	121.48	123.00	125.00
Self wt. :	M	3442.8	2998.0	2256.6	1218.7	392.8	226.2	0.0
(Max)	V	23.4	46.7	70.1	93.4	108.4	111.2	114.9
DL-Prec. :	M	0.0	0.0	0.0	0.0	0.0	0.0	0.0
DC(Max)	V	0.0	0.0	0.0	0.0	0.0	0.0	0.0
DL-Prec. :	M	0.0	0.0	0.0	0.0	0.0	0.0	0.0
DW(Max)	V	0.0	0.0	0.0	0.0	0.0	0.0	0.0
Deck + :	M	4949.6	4310.1	3244.2	1752.0	564.6	325.1	0.0
Haunch (Max)	V	33.6	67.1	100.7	134.3	155.9	159.9	165.2
Diaphragm :	M	0.0	0.0	0.0	0.0	0.0	0.0	0.0
(Max)	V	0.0	0.0	0.0	0.0	0.0	0.0	0.0
DL-Comp :	M	137.5	97.5	29.3	-67.2	-141.0	-157.3	-180.1
DC(Max)	V	2.0	4.3	6.5	8.7	10.1	10.4	10.8
DL-Comp :	M	653.2	463.4	139.2	-319.3	-670.0	-747.5	-855.7
DW(Max)	V	9.7	20.2	30.8	41.4	48.2	49.5	51.1
LL + I :	M+	2315.3	1734.2	909.1	369.5	296.6	306.8	331.5
	V	79.3	109.6	119.0	55.7	22.7	16.6	8.5
LL + I :	M-	-28.2	-36.3	-354.2	-1722.7	-2921.0	-3170.4	-3512.2
	V	0.7	1.4	62.9	147.4	178.8	184.6	192.3
LL + I :	Vmx	97.1	124.8	152.2	177.9	191.2	193.6	196.9
	M	1951.3	1467.7	610.6	-529.5	-1276.4	-1415.9	-1600.4
Total :	M+	11498.5	9603.2	6578.5	2953.6	442.9	0.0	0.0
	V	148.0	247.9	327.0	333.5	345.4	0.0	0.0
Total :	M-	0.0	0.0	0.0	0.0	-2774.7	-3523.9	-4547.9
	V	0.0	0.0	0.0	0.0	501.5	515.7	534.3
Total :	Vmx	165.7	263.1	360.3	455.7	513.9	524.7	538.9
	M	11134.5	9336.7	6280.0	2054.7	-1130.1	-1769.5	-2636.2

SHEAR AND MOMENT ENVELOPE : Span : 3, Beam : 1, STRENGTH I
Shears: kips, Moments: kft

		Bearing	Trans	H/2	0.10L	0.20L	0.30L	0.40L	Midspan
Location,	ft	0.00	2.00	3.52	11.70	24.40	37.10	49.80	62.50
Self wt. :	M	0.0	282.7	490.9	1523.3	2820.8	3747.5	4303.5	4488.9
(Max)	V	143.6	139.0	135.6	116.8	87.6	58.4	29.2	0.0
Self wt. :	M	0.0	203.5	353.5	1096.8	2030.9	2698.2	3098.5	3232.0
(Min)	V	103.4	100.1	97.6	84.1	63.0	42.0	21.0	0.0
DL-Prec. :	M	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0
DC(Max)	V	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0



Bentley

Colorado DOT
4201 E. Arkansas Ave. Denver CO 80222

Sheet: DS-4
Job No: BR R600-
297

Program: LEAP®
CONSPAN®
Version: 08.01.00.10

Copyright © Bentley Systems, Inc. 1984 - 2008.
www.bentley.com
1-800-778-4277

By: A. Pott
Date: Jan/22/2009
CKD:
Date:

File Name: 76-21-125-21-124 U72C.csl

		Bearing	Trans	H/2	0.10L	0.20L	0.30L	0.40L	Midspan
DL-Prec. :	M	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0
DC(Min)	V	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0
DL-Prec. :	M	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0
DW(Max)	V	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0
DL-Prec. :	M	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0
DW(Min)	V	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0
Deck + :	M	0.0	406.4	705.8	2190.0	4055.3	5387.6	6187.0	6453.5
Haunch (Max)	V	206.5	199.9	194.9	167.9	125.9	83.9	42.0	0.0
Deck + :	M	0.0	292.6	508.2	1576.8	2919.8	3879.1	4454.6	4646.5
Haunch (Min)	V	148.7	143.9	140.3	120.9	90.6	60.4	30.2	0.0
Diaphragm :	M	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0
(Max)	V	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0
Diaphragm :	M	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0
(Min)	V	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0
DL-Comp. :	M	-256.2	-227.8	-207.1	-108.7	18.1	109.6	165.7	186.5
DC(Max)	V	13.9	13.5	13.2	11.4	8.6	5.8	3.0	0.2
DL-Comp. :	M	-184.5	-164.0	-149.1	-78.3	13.0	78.9	119.3	134.2
DC(Min)	V	10.0	9.7	9.5	8.2	6.2	4.2	2.2	0.2
DL-Comp. :	M	-1460.7	-1298.6	-1180.8	-619.9	103.2	624.7	944.6	1063.0
DW(Max)	V	79.5	77.0	75.1	64.9	49.0	33.1	17.3	1.4
DL-Comp. :	M	-633.0	-562.7	-511.7	-268.6	44.7	270.7	409.3	460.6
DW(Min)	V	34.4	33.4	32.5	28.1	21.2	14.4	7.5	0.6
LL + I :	M+	354.3	350.5	362.6	652.4	1850.9	3681.3	5008.2	5444.0
	V	14.2	33.0	47.2	124.2	262.8	242.4	178.6	109.3
LL + I :	M-	-7789.5	-7037.1	-6488.0	-3844.9	-811.5	-77.5	-59.8	-44.0
	V	423.5	406.7	393.9	325.2	140.1	5.2	1.5	1.6
LL + I :	Vmx	433.2	426.1	420.7	391.7	335.6	275.6	215.1	157.4
	M	-3591.3	-3184.1	-2876.2	-1226.3	1295.0	3199.8	4288.9	4519.6
Total :	M+	0.0	312.8	898.6	4018.8	8848.2	13550.7	16609.1	17635.8
	V	0.0	415.0	419.7	485.0	533.8	423.6	270.0	110.9
Total :	M-	-9506.4	-8067.3	-7014.2	-1899.9	0.0	0.0	0.0	0.0
	V	769.0	741.2	720.1	544.2	0.0	0.0	0.0	0.0
Total :	Vmx	876.8	855.5	839.4	752.5	606.7	456.8	306.5	159.0
	M	-5308.1	-4021.4	-3067.3	1758.4	8292.4	13069.1	15889.8	16711.4

		0.60L	0.70L	0.80L	0.90L	H/2	Trans	Bearing
Location,	ft	75.20	87.90	100.60	113.30	121.48	123.00	125.00
Self wt. :	M	4303.5	3747.5	2820.8	1523.3	490.9	282.7	0.0
(Max)	V	29.2	58.4	87.6	116.8	135.6	139.0	143.6
Self wt. :	M	3098.5	2698.2	2030.9	1096.8	353.5	203.5	0.0
(Min)	V	21.0	42.0	63.0	84.1	97.6	100.1	103.4
DL-Prec. :	M	0.0	0.0	0.0	0.0	0.0	0.0	0.0
DC(Max)	V	0.0	0.0	0.0	0.0	0.0	0.0	0.0
DL-Prec. :	M	0.0	0.0	0.0	0.0	0.0	0.0	0.0
DC(Min)	V	0.0	0.0	0.0	0.0	0.0	0.0	0.0
DL-Prec. :	M	0.0	0.0	0.0	0.0	0.0	0.0	0.0
DW(Max)	V	0.0	0.0	0.0	0.0	0.0	0.0	0.0
DL-Prec. :	M	0.0	0.0	0.0	0.0	0.0	0.0	0.0
DW(Min)	V	0.0	0.0	0.0	0.0	0.0	0.0	0.0
Deck + :	M	6187.0	5387.6	4055.3	2190.0	705.8	406.4	0.0
Haunch (Max)	V	42.0	83.9	125.9	167.9	194.9	199.9	206.5
Deck + :	M	4454.6	3879.1	2919.8	1576.8	508.2	292.6	0.0
Haunch (Min)	V	30.2	60.4	90.6	120.9	140.3	143.9	148.7
Diaphragm :	M	0.0	0.0	0.0	0.0	0.0	0.0	0.0
(Max)	V	0.0	0.0	0.0	0.0	0.0	0.0	0.0
Diaphragm :	M	0.0	0.0	0.0	0.0	0.0	0.0	0.0
(Min)	V	0.0	0.0	0.0	0.0	0.0	0.0	0.0



Program: LEAP®
CONSPAN®
Version: 08.01.00.10
File Name: 76-21-125-21-124 U72C.csl

Copyright © Bentley Systems, Inc. 1984 - 2008.
www.bentley.com
1-800-778-4277

By: A. Pott
Date: Jan/22/2009
CKD:
Date:

		0.60L	0.70L	0.80L	0.90L	H/2	Trans	Bearing
DL-Comp :	M	171.9	121.9	36.6	-84.0	-176.3	-196.7	-225.1
DC(Max)	V	2.5	5.3	8.1	10.9	12.7	13.0	13.5
DL-Comp :	M	123.7	87.8	26.4	-60.5	-126.9	-141.6	-162.1
DC(Min)	V	1.8	3.8	5.8	7.8	9.1	9.4	9.7
DL-Comp :	M	979.9	695.1	208.8	-479.0	-1005.1	-1121.3	-1283.5
DW(Max)	V	14.5	30.4	46.2	62.1	72.3	74.2	76.7
DL-Comp :	M	424.6	301.2	90.5	-207.6	-435.5	-485.9	-556.2
DW(Min)	V	6.3	13.2	20.0	26.9	31.3	32.2	33.2
LL + I :	M+	5064.8	3793.5	1988.6	808.2	648.9	671.1	725.2
	V	173.6	239.6	260.2	121.8	49.7	36.3	18.7
LL + I :	M-	-61.6	-79.4	-774.9	-3768.4	-6389.7	-6935.1	-7682.9
	V	1.6	3.0	137.5	322.3	391.1	403.8	420.7
LL + I :	Vmx	212.4	272.9	333.0	389.1	418.2	423.5	430.7
	M	4268.5	3210.5	1335.8	-1158.2	-2792.2	-3097.4	-3500.9
Total :	M+	16707.0	13745.7	9110.1	4253.5	1283.2	732.7	6.9
	V	261.7	417.6	528.0	479.4	420.6	416.8	411.8
Total :	M-	0.0	0.0	0.0	-1657.8	-6709.4	-7757.0	-9191.5
	V	0.0	0.0	0.0	540.8	714.0	735.1	762.9
Total :	Vmx	300.6	450.9	600.7	746.7	833.6	849.7	871.0
	M	15910.8	13162.7	8457.3	1992.1	-2776.8	-3726.2	-5009.5

REACTIONS (kips), STRENGTH I

Load Type		Left Support	Right Support
Self Wt.		143.6	143.6
Deck+Haunch		206.5	206.5
Diaphragm		0.0	0.0
DL-Prec.(DC)		0.0	0.0
DL-Prec.(DW)		0.0	0.0
DL-Comp.(DC)		206.5	90.9
DL-Comp.(DW)		1177.5	518.3
Live	(Max)	426.6	415.7
Live	(Min)	-123.8	-276.8
Pedestrian	(Max)	-0.0	-0.0
Pedestrian	(Min)	-0.0	-0.0

Upward reactions are positive.

Live Load reactions are per lane with no distribution factor and no impact.

Non-composite load types are per beam.

Composite and Pedestrian load types are per total bridge width.

LEVELING PAD

PER BRIDGE DESIGN MANUAL (14.2), LEVELING PADS FOR LOCKED IN GIRDERS SHALL BE DESIGNED FOR DEAD LOAD ONLY (NO LONGITUDINAL, TRANSVERSE OR ROTATIONAL MOMENTS).

DEFLECTION CRITERIA OF AASHTO CHAPTER 14 DO NOT NEED TO BE MET EITHER (PER RLO) (DESIGN MANUAL WILL BE CHANGED TO REFLECT THIS)

USE PLAIN ELASTOMERIC PAD (PEP)

$$\sigma_s \leq 0.80 \text{ ksi} \quad (14.7.6.3.2-1)$$

span length $\approx 122'-6"$ U72C-A 12.26 SF

$$DL \approx .15 \frac{W}{L} \left(\frac{122.5}{2} + .5 \right) \left[12.26 \text{ SF} + 8 \frac{1}{2} \frac{1}{\text{ft}} \left(33' \right) \right] + \left(3 \frac{1}{2} \right) \left(\frac{.1467 \text{ K}}{\text{CF}} \right) \left(33' \right) \left(\frac{122.5}{2} + .5 \right)$$

$$DL \approx 317.3 + 74.7 \text{ K}$$


$$DL \approx 392.0 \text{ K}$$

$$\text{min. Area} \approx \frac{392.0}{.8} \approx 490.0 \text{ in}^2$$

$$\text{width} = 54" \text{ max}$$

$$\text{length} = \frac{490.0}{54} \approx 9.07"$$

use 9 1/2" wide x 56" ←



$$\sigma = \frac{392.0}{(56)(9.5)} = .74 \text{ ksi}$$

DEFLECTION

$$S = \frac{LW}{2 h_n (L+W)} = \frac{(9.5)(56)}{2 (.5)(9.5+56)} = 8.12 \quad (14.7.5.1-1)$$

$$E = 3.4 \times 10^6$$

(Fig. C14.7.6.3.3-1)

$$\delta = 3 E h_n^3 = 3 (.034)^3 \approx .077" \approx 1/16"$$

$$\delta > .07 h_n$$

(C14.7.6.3.3)
(14.7.6.3.3)

By: _____	Date _____	Project no. _____	Project code (SA#): _____
Chk'd: _____	Date _____	Structure no. _____	Sheet 414 of _____




Figure C14.7.6.3.3-1 Stress-Strain Curves.

For CDP, the computed compressive strain, ϵ_s , may be taken as:

$$\epsilon_s = \frac{\sigma_s}{E_c} \quad (14.7.6.3.3-1)$$


where:

E_c = uniaxial compressive stiffness of the CDP bearing pad. It may be taken as 30 ksi in lieu of pad-specific test data (ksi)


σ_s = average compressive stress due to total load from applicable service load combinations in Table 3.4.1-1 (ksi)

CDP is typically very stiff in compression. The shape factor may be computed, but it has a different meaning and less significance to the compressive deflection than it does for FGP and PEP (Roeder *et al.*, 2000). As a result, the maximum compressive deflection for CDP can be based upon an average compressive strain, ϵ_s , for the total bearing pad thickness as computed in Eq. 1.

COLORADO DEPARTMENT OF TRANSPORTATION
DESIGN COMPUTATIONS (Grid)



or run continuous under girder



By: _____	Date _____	Project no. _____	Project code (SA#): _____
Chk'd: _____	Date _____	Structure no. _____	Sheet <u>4/6</u> of _____