



**COLORADO**  
Department of  
Transportation

# CENTRAL 70 PROJECT

Public Disclosure Administrative and Technical Proposal:  
5280 CONNECTORS

VOLUME 2 | Electronic Copy | Binder 6 of 8

**5280** Connectors  
Linking Communities



TRANSPARENCY | RELIABILITY | ACCOUNTABILITY | INCLUSIVITY





## Volume 2 Technical Submissions Table of Contents

### 2.1 Technical Proposal

2.1.1	Executive Summary.....	Binder 1
2.1.2	Part 1: Project Management.....	Binder 1
2.1.3	Part 2: Quality Management.....	Binder 1
2.1.4	Part 3: Maintenance of Traffic.....	Binder 1
2.1.5	Part 4: Environmental Management, Strategic Communications, Community Development Programs, Small and Disadvantaged Business Participation and Workforce Development.....	Binder 1
2.1.6	Part 5: Operations and Maintenance.....	Binder 1
2.1.7	Part 6: Technical Approach and Solutions.....	Binder 1
2.1.8	Appendix A: Draft Design Drawings	
	Draft Roadway Design Drawings (TS-01 TO RD-68).....	Binder 2
	Draft Roadway Design Drawings (RD-69 TO XS-13).....	Binder 3
	Draft Drainage Design Drawings (DN-01 TO DP-11).....	Binder 3
	Draft Drainage Design Drawings (DP-12 TO GWE-01).....	Binder 4
	Draft Bridge Design Drawings.....	Binder 4
	Draft Cover and Swansea Elementary School Landscape and Aesthetic Design Drawings.....	Binder 4
	Draft Dewatering Design.....	Binder 4
	ATC Map.....	Binder 4
2.1.9	Appendix B: Draft Project Management Plan.....	Binder 5
2.1.10	<b>Appendix C: Proposal Schedule</b>	
	Narrative.....	Binder 5
	<b>P6 Schedule.....</b>	<b>Binder 6</b>
2.1.11	Appendix D: Draft Stage 1 Quality Management Plan.....	Binder 5
2.1.12	Appendix E: Draft Stage 2 Quality Management Plan.....	Binder 5
2.1.13	Appendix F: Draft Transportation Management Plan.....	Binder 7
2.1.14	Appendix G: Draft Cover Design Baseline Report.....	Binder 7
2.1.15	Appendix H: Draft Operations Management Plan.....	Binder 7
2.1.16	Appendix I: Draft Maintenance Management Plan.....	Binder 7
2.1.17	Appendix J: Draft Strategic Communications Plan.....	Binder 7
2.1.18	Appendix K: Draft Small and Disadvantaged Business Participation Plan.....	Binder 7
2.1.19	Appendix L: Draft Workforce Development Plan.....	Binder 7
2.1.20	Appendix M: Draft Environmental Compliance Work Plan.....	Binder 7
	Envision Rating System Self-Assessment Checklist.....	Binder 7

### 2.2 Alternative Technical Concepts (ATCs)

2.2.1	ATC 2.3 Colorado Interchange DDI.....	Binder 8
2.2.2	ATC 4.2 Storm Sewer Diversion.....	Binder 8
2.2.3	ATC 7.2 Sanitary Sewer Gravity Line.....	Binder 8
2.2.4	ATC 10.2 Elimination of PCC Joint Sealing.....	Binder 8
2.2.5	ATC 20.0 Lower Design Speed for Quebec WB Off Ramp from 45MPH to 35MPH.....	Binder 8
2.2.6	ATC 25.2 York Street Storm Drain Connection.....	Binder 8
2.2.7	ATC 27.1 Eliminating Intermediate Diaphragms for PC Girders.....	Binder 8
2.2.8	ATC 28.0 Tunnel Lighting Electrical Drivers.....	Binder 8
2.2.9	ATC 29.1 Vasquez EB DMS.....	Binder 8
2.2.10	ATC 30.1 DMS Median Access.....	Binder 8
2.2.11	ATC 31.2 Cover Buildings Configuration.....	Binder 8
2.2.12	ATC 32.0 Precast Concrete FIB Girders (Florida I-Beams).....	Binder 8
2.2.13	ATC 36.0 Drainage CCD Storm Interceptor Pipes at Forest and Grape St.....	Binder 8
2.2.14	ATC 37.2 North Steele Vasquez Interchange.....	Binder 8
2.2.15	ATC 40.1 Harmonic Action of Structure for Loading.....	Binder 8
2.2.16	ATC 41.1 Reduced Portal Architectural Requirements.....	Binder 8
2.2.17	ATC 42.0 T-Wall Backfill.....	Binder 8
2.2.18	ATC 44.0 Tunnel Fiber Glass Conduit.....	Binder 8

## **2.1.10 APPENDIX C: PROPOSAL SCHEDULE**

### **PROPOSAL SCHEDULE**













































































































































Activity ID	Activity Name	Original Duration	Start	Finish	Total Float	2017			2018				2019				2020				2021				2022				2023				
						Q2	Q3	Q4	Q1	Q2	Q3	Q4	Q1	Q2	Q3	Q4	Q1	Q2	Q3	Q4	Q1	Q2	Q3	Q4	Q1	Q2	Q3	Q4	Q1	Q2	Q3	Q4	Q1
E-A345-459	Plans and Specifications '60% (OTS) Pavement Plans and Specs WA03,04,05	60	09-Feb-18	03-May-18	337																												
E-A345-458	WA03,04,05 - 30% Pavement Specs - Summary LOE	133	09-Feb-18	21-Jun-18	536																												
E-A345-460	QA audit submittal '60% (OTS) Pavement Plans and Specs WA03,04,05	0	04-May-18		337																												
E-A345-461	Comment resolution/Certification '60% (OTS) Pavement Plans and Specs WA03,04,05	10	04-May-18	17-May-18	337																												
E-A345-462	Submittal Date '60% (OTS) Pavement Plans and Specs WA03,04,05	0	18-May-18		337																												
E-A345-463	CDOT/CCD review '60% (OTS) Pavement Plans and Specs WA03,04,05	15	18-May-18	07-Jun-18	382																												
E-A345-464	CDOT/CCD comment resolution '60% (OTS) Pavement Plans and Specs WA03,04,05	10	08-Jun-18	21-Jun-18	382																												
<b>100% Pavement Plans and Specs</b>		<b>102</b>	<b>18-May-18</b>	<b>12-Oct-18</b>	<b>322</b>																												
E-A345-466	Plans and Specifications '100% Pavement Plans and Specs WA03,04,05	70	18-May-18	23-Aug-18	337																												
E-A345-465	WA03,04,05 - 100% Pavement Specs - Summary LOE	148	18-May-18	12-Oct-18	473																												
E-A345-467	QA audit submittal '100% Pavement Plans and Specs WA03,04,05	0	24-Aug-18		337																												
E-A345-468	Comment resolution/Certification '100% Pavement Plans and Specs WA03,04,05	10	24-Aug-18	06-Sep-18	337																												
E-A345-469	Submittal Date '100% Pavement Plans and Specs WA03,04,05	0	07-Sep-18		337																												
E-A345-470	CDOT/CCD review '100% Pavement Plans and Specs WA03,04,05	15	07-Sep-18	27-Sep-18	337																												
E-A345-471	CDOT/CCD comment resolution '100% Pavement Plans and Specs WA03,04,05	10	28-Sep-18	11-Oct-18	337																												
E-A345-472	RFC Pavement Plans and Specs '100% Pavement Plans and Specs WA03,04,05	1	12-Oct-18	12-Oct-18	337																												
<b>30% Permanent Groundwater</b>		<b>61</b>	<b>15-Dec-17</b>	<b>15-Mar-18</b>	<b>178</b>																												
E-A345-474	Plans and Specifications '30% Permanent Groundwater03,04,05	30	15-Dec-17	25-Jan-18	149																												
E-A345-473	WA03,04,05 - 30% Permanent Groundwater Plans & Specifications - Summary LOE	91	15-Dec-17	15-Mar-18	258																												
E-A345-475	QA audit submittal '30% Permanent Groundwater03,04,05	0	26-Jan-18		149																												
E-A345-476	Comment resolution/Certification '30% Permanent Groundwater03,04,05	10	26-Jan-18	08-Feb-18	149																												
E-A345-477	Submittal Date '30% Permanent Groundwater03,04,05	0	09-Feb-18		149																												
E-A345-478	CDOT/CCD review '30% Permanent Groundwater03,04,05	15	09-Feb-18	01-Mar-18	184																												
E-A345-479	CDOT/CCD comment resolution '30% Permanent Groundwater03,04,05	10	02-Mar-18	15-Mar-18	184																												
<b>60% Permanent Groundwater</b>		<b>93</b>	<b>09-Feb-18</b>	<b>21-Jun-18</b>	<b>185</b>																												
E-A345-481	Plans and Specifications '60% Permanent Groundwater03,04,05	60	09-Feb-18	03-May-18	149																												
E-A345-480	WA03,04,05 - 60% Permanent Groundwater Plans & Specifications - Summary LOE	133	09-Feb-18	21-Jun-18	272																												
E-A345-482	QA audit submittal '60% Permanent Groundwater03,04,05	0	04-May-18		149																												
E-A345-483	Comment resolution/Certification '60% Permanent Groundwater03,04,05	10	04-May-18	17-May-18	149																												
E-A345-484	Submittal Date '60% Permanent Groundwater03,04,05	0	18-May-18		149																												
E-A345-485	CDOT/CCD review '60% Permanent Groundwater03,04,05	15	18-May-18	07-Jun-18	194																												
E-A345-486	CDOT/CCD comment resolution '60% Permanent Groundwater03,04,05	10	08-Jun-18	21-Jun-18	194																												
<b>100% Permanent Groundwater</b>		<b>101</b>	<b>18-May-18</b>	<b>11-Oct-18</b>	<b>143</b>																												
E-A345-488	Plans and Specifications '100% Permanent Groundwater03,04,05	70	18-May-18	23-Aug-18	149																												
E-A345-487	WA03,04,05 - 100% Permanent Groundwater Plans & Specifications - Summary LOE	147	18-May-18	11-Oct-18	209																												
E-A345-489	QA audit submittal '100% Permanent Groundwater 03, 04, 05	0	24-Aug-18		149																												
E-A345-490	Comment resolution/Certification '100% Permanent Groundwater03,04,05	10	24-Aug-18	06-Sep-18	149																												
E-A345-491	Submittal Date '100% Permanent Groundwater03,04,05	0	07-Sep-18		149																												
E-A345-492	CDOT/CCD review '100% Permanent Groundwater03,04,05	15	07-Sep-18	27-Sep-18	149																												
E-A345-493	CDOT/CCD comment resolution '100% Permanent Groundwater03,04,05	10	28-Sep-18	11-Oct-18	149																												
<b>RFC Permanent Groundwater</b>		<b>49</b>	<b>12-Oct-18</b>	<b>21-Dec-18</b>	<b>143</b>																												
E-A345-495	Plans and Specifications 'RFC Permanent Groundwater03,04,05	15	12-Oct-18	01-Nov-18	149																												
E-A345-494	WA03,04,05 - RFC Permanent Groundwater Plans & Specifications - Summary LOE	71	12-Oct-18	21-Dec-18	209																												
E-A345-496	QA audit submittal 'RFC Permanent Groundwater 03, 04, 05	0	02-Nov-18		149																												
E-A345-497	Comment resolution/Certification 'RFC Permanent Groundwater03,04,05	10	02-Nov-18	15-Nov-18	149																												

Project ID: CENTRAL 70 - PBS-08  
 BaselineID:  
 Data Date: 18-May-17

Print Date: 24-May-17

**Central 70 - 5280 Connectors - Proposal Baseline(PBS-01)**

**Central 70 Proposal Schedule**

- Critical Remaining Work
- Actual Level of Effort
- Milestone
- Actual Work
- Remaining Level of Effort
- Remaining Work





















Activity ID	Activity Name	Original Duration	Start	Finish	Total Float	2017			2018				2019				2020				2021				2022				2023				
						Q2	Q3	Q4	Q1	Q2	Q3	Q4	Q1	Q2	Q3	Q4	Q1	Q2	Q3	Q4	Q1	Q2	Q3	Q4	Q1	Q2	Q3	Q4	Q1	Q2	Q3	Q4	Q1
PWA03-Proc-1620	Prepare / Submit / Review / Approve - Piling Shop Drawings - Bridge (BNSF Market Lead Structure)	20	22-Jun-18	20-Jul-18	925																												
PWA03-Proc-1910	Prepare / Submit / Review / Approve - Overhang Shop Drawings - Bridge (NB Monroe St. over I-70)	20	29-Jun-18	27-Jul-18	506																												
PWA03-Proc-1850	Prepare / Submit / Review / Approve - MSE Wall Shop Drawings - Bridge (NB Monroe St. over I-70)	20	29-Jun-18	27-Jul-18	396																												
PWA03-Proc-1870	Prepare / Submit / Review / Approve - Beam Shop Drawings - Bridge (NB Monroe St. over I-70)	20	09-Jul-18	03-Aug-18	396																												
PWA03-Proc-2080	Prepare / Submit / Review / Approve - Overhang Shop Drawings - Bridge (Cook St. over I-70)	20	09-Jul-18	03-Aug-18	617																												
PWA03-Proc-2020	Prepare / Submit / Review / Approve - MSE Wall Shop Drawings - Bridge (Cook St. over I-70)	20	09-Jul-18	03-Aug-18	600																												
PWA03-Proc-1930	Prepare / Submit / Review / Approve - Pre-cast Deck Panels Shop Drawings - Bridge (NB Monroe St. over I-70)	20	09-Jul-18	03-Aug-18	506																												
PWA03-Proc-2890	Prepare / Submit / Review / Approve - Beam Shop Drawings - Bridge (UPRR Service Bridge over I-70)	20	23-Jul-18	17-Aug-18	834																												
PWA03-Proc-2930	Prepare / Submit / Review / Approve - Overhang Shop Drawings - Bridge (UPRR Service Bridge over I-70)	20	23-Jul-18	17-Aug-18	849																												
PWA03-Proc-2380	Prepare / Submit / Review / Approve - Beam Shop Drawings - Bridge (Fillmore St. over I-70)	20	23-Jul-18	17-Aug-18	515																												
PWA03-Proc-1680	Prepare / Submit / Review / Approve - MSE Wall Shop Drawings - Bridge (BNSF Market Lead Structure)	20	23-Jul-18	17-Aug-18	912																												
PWA03-Proc-2040	Prepare / Submit / Review / Approve - Beam Shop Drawings - Bridge (Cook St. over I-70)	20	23-Jul-18	17-Aug-18	605																												
PWA03-Proc-2100	Prepare / Submit / Review / Approve - Pre-cast Deck Panels Shop Drawings - Bridge (Cook St. over I-70)	20	23-Jul-18	17-Aug-18	617																												
PWA03-Proc-2250	Prepare / Submit / Review / Approve - Overhang Shop Drawings - Bridge (NB Steele St./Vasquez Blvd. over I-70)	20	23-Jul-18	17-Aug-18	883																												
PWA03-Proc-2190	Prepare / Submit / Review / Approve - MSE Wall Shop Drawings - Bridge (NB Steele St./Vasquez Blvd. over I-70)	20	23-Jul-18	17-Aug-18	839																												
PWA03-Proc-2420	Prepare / Submit / Review / Approve - Overhang Shop Drawings - Bridge (Fillmore St. over I-70)	20	23-Jul-18	17-Aug-18	845																												
PWA03-Proc-2550	Prepare / Submit / Review / Approve - Beam Shop Drawings - Bridge (Josephine St. over I-70)	20	23-Jul-18	17-Aug-18	591																												
PWA03-Proc-2590	Prepare / Submit / Review / Approve - Overhang Shop Drawings - Bridge (Josephine St. over I-70)	20	23-Jul-18	17-Aug-18	586																												
PWA03-Proc-2720	Prepare / Submit / Review / Approve - Beam Shop Drawings - Bridge (York St. over I-70)	20	23-Jul-18	17-Aug-18	703																												
PWA03-Proc-1740	Prepare / Submit / Review / Approve - Overhang Shop Drawings - Bridge (BNSF Market Lead Structure)	20	23-Jul-18	17-Aug-18	943																												
PWA03-Proc-1760	Prepare / Submit / Review / Approve - Pre-cast Deck Panels Shop Drawings - Bridge (BNSF Market Lead Structure)	20	20-Aug-18	17-Sep-18	943																												
PWA03-Proc-2210	Prepare / Submit / Review / Approve - Beam Shop Drawings - Bridge (NB Steele St./Vasquez Blvd. over I-70)	20	20-Aug-18	17-Sep-18	872																												
PWA03-Proc-2270	Prepare / Submit / Review / Approve - Pre-cast Deck Panels Shop Drawings - Bridge (NB Steele St./Vasquez Blvd. over I-70)	20	20-Aug-18	17-Sep-18	883																												
PWA03-Proc-2440	Prepare / Submit / Review / Approve - Pre-cast Deck Panels Shop Drawings - Bridge (Fillmore St. over I-70)	20	20-Aug-18	17-Sep-18	845																												
PWA03-Proc-2610	Prepare / Submit / Review / Approve - Pre-cast Deck Panels Shop Drawings - Bridge (Josephine St. over I-70)	20	20-Aug-18	17-Sep-18	586																												
PWA03-Proc-1700	Prepare / Submit / Review / Approve - Beam Shop Drawings - Bridge (BNSF Market Lead Structure)	20	20-Aug-18	17-Sep-18	927																												
PWA03-Proc-3010	Prepare / Submit / Review / Approve - SOE Shop Drawings - Bridge (UPRR Bridge over I-70)	20	05-Oct-18	02-Nov-18	238																												
PWA03-Proc-1530	Prepare / Submit / Review / Approve - Beam Shop Drawings - Bridge (NB Colorado Blvd. over I-70)	20	03-Dec-18	31-Dec-18	232																												
PWA03-Proc-1050	Prepare / Submit / Review / Approve - Soil Nail Wall Shop Drawings - Soil Nail Walls - Work Area 03	20	24-Dec-18	23-Jan-19	416																												
PWA03-Proc-1290	Prepare / Submit / Review / Approve - Cast-in-Place Concrete Wall Shop Drawings - Work Area 03	20	24-Dec-18	23-Jan-19	290																												
PWA03-Proc-1270	Prepare / Submit / Review / Approve - Differential Barrier Wall Shop Drawings - Work Area 03	20	24-Dec-18	23-Jan-19	357																												
PWA03-Proc-1280	Prepare / Submit / Review / Approve - Soldier Pile Tie Back Abutment Wall Shop Drawings - Work Area 03	20	24-Dec-18	23-Jan-19	839																												
PWA03-Proc-3050	Prepare / Submit / Review / Approve - Beam Shop Drawings - Bridge (UPRR Bridge over I-70)	20	28-Jan-19	25-Feb-19	124																												
PWA03-Proc-3090	Prepare / Submit / Review / Approve - Overhang Shop Drawings - Bridge (UPRR Bridge over I-70)	20	28-Jan-19	25-Feb-19	189																												
PWA03-Proc-3110	Prepare / Submit / Review / Approve - Pre-cast Deck Panels Shop Drawings - Bridge (UPRR Bridge over I-70)	20	28-Jan-19	25-Feb-19	189																												
PWA03-Proc-3210	Prepare / Submit / Review / Approve - Beam Shop Drawings - Bridge (I-70 over Brighton Blvd.)	45	06-Mar-19	07-May-19	405																												
PWA03-Proc-3260	Prepare / Submit / Review / Approve - Overhang Shop Drawings - Bridge (I-70 over Brighton Blvd.)	20	06-Mar-19	02-Apr-19	445																												
PWA03-Proc-3280	Prepare / Submit / Review / Approve - Pre-cast Deck Panels Shop Drawings - Bridge (I-70 over Brighton Blvd.)	20	06-Mar-19	02-Apr-19	446																												
PWA03-Proc-3200	Prepare / Submit / Review / Approve - MSE Wall Shop Drawings - Bridge (I-70 over Brighton Blvd.)	20	06-Mar-19	02-Apr-19	423																												

Project ID: CENTRAL 70 - PBS-08  
 BaselineID:  
 Data Date: 18-May-17

Print Date: 24-May-17

**Central 70 - 5280 Connectors - Proposal Baseline(PBS-01)**

**Central 70 Proposal Schedule**

-  Critical Remaining Work
-  Actual Level of Effort
-  Milestone
-  Actual Work
-  Remaining Level of Effort
-  Remaining Work

































Activity ID	Activity Name	Original Duration	Start	Finish	Total Float	2017				2018				2019				2020				2021				2022				2023
						Q2	Q3	Q4	Q1	Q2	Q3	Q4	Q1	Q2	Q3	Q4	Q1	Q2	Q3	Q4	Q1	Q2	Q3	Q4	Q1	Q2	Q3	Q4	Q1	
CWA03-CW5ST02-3130	WA03 - 02 - Survey Soil Nail Wall - ML2015L	1	06-Mar-20	09-Mar-20	183																									
CWA03-CW5ST02-3140	WA03 - 02 - Excavate FG Slope Soil Nail Wall - ML20815L	2	09-Mar-20	11-Mar-20	182																									
CWA03-CW5ST02-3150	WA03 - 02 - Install Soil Nails (40 Ea @ 5' O.C. - 8 per Day) - ML2015L	5	12-Mar-20	20-Mar-20	183																									
CWA03-CW5ST02-3160	WA03 - 02 - Install Mesh and Whalers for Soil Nail Wall - ML2015L	2	20-Mar-20	24-Mar-20	183																									
CWA03-CW5ST02-3170	WA03 - 02 - Place Initial Shotcrete - ML2015L	1	23-Mar-20	24-Mar-20	183																									
CWA03-CW5ST02-3180	WA03 - 02 - Place Final Shotcrete - ML2015L	1	24-Mar-20	25-Mar-20	183																									
CWA03-CW5ST02-3190	WA03 - 03 - Survey Soil Nail Wall - ML2015L	1	25-Mar-20	26-Mar-20	183																									
CWA03-CW5ST02-3200	WA03 - 03 - Excavate FG Slope Soil Nail Wall - ML2046L	2	26-Mar-20	30-Mar-20	181																									
CWA03-CW5ST02-3210	WA03 - 03 - Install Soil Nails (40 Ea @ 5' O.C. - 8 per Day) - ML2046L	5	31-Mar-20	08-Apr-20	183																									
CWA03-CW5ST02-3220	WA03 - 03 - Install Mesh and Whalers for Soil Nail Wall - ML2046L	2	08-Apr-20	10-Apr-20	183																									
CWA03-CW5ST02-3230	WA03 - 03 - Place Initial Shotcrete - ML2046L	1	09-Apr-20	10-Apr-20	183																									
CWA03-CW5ST02-3240	WA03 - 03 - Place Final Shotcrete - ML2046L	1	10-Apr-20	13-Apr-20	183																									
CWA03-CW5ST02-3250	WA03 - 04 - Survey Soil Nail Wall - ML2046L	1	13-Apr-20	14-Apr-20	183																									
CWA03-CW5ST02-3260	WA03 - 04 - Excavate FG Slope Soil Nail Wall - ML2046L	2	14-Apr-20	17-Apr-20	180																									
CWA03-CW5ST02-3270	WA03 - 04 - Install Soil Nails (40 Ea @ 5' O.C. - 8 per Day) - ML2046L	5	20-Apr-20	27-Apr-20	183																									
CWA03-CW5ST02-3280	WA03 - 04 - Install Mesh and Whalers for Soil Nail Wall - ML2046L	2	27-Apr-20	29-Apr-20	183																									
CWA03-CW5ST02-3290	WA03 - 04 - Place Initial Shotcrete - ML2046L	1	28-Apr-20	29-Apr-20	183																									
CWA03-CW5ST02-3300	WA03 - 04 - Place Final Shotcrete - ML2046L	1	29-Apr-20	30-Apr-20	183																									
CWA03-CW5ST02-3310	WA03 - 05 - Survey Soil Nail Wall - ML2046L	1	30-Apr-20	01-May-20	183																									
CWA03-CW5ST02-3320	WA03 - 05 - Excavate FG Slope Soil Nail Wall - ML2046L	2	01-May-20	05-May-20	180																									
CWA03-CW5ST02-3330	WA03 - 05 - Install Soil Nails (40 Ea @ 5' O.C. - 8 per Day) - ML2046L	5	06-May-20	13-May-20	184																									
CWA03-CW5ST02-3340	WA03 - 05 - Install Mesh and Whalers for Soil Nail Wall - ML2046L	2	13-May-20	15-May-20	184																									
CWA03-CW5ST02-3350	WA03 - 05 - Place Initial Shotcrete - ML2046L	1	14-May-20	15-May-20	184																									
CWA03-CW5ST02-3360	WA03 - 05 - Place Final Shotcrete - ML2046L	1	15-May-20	18-May-20	184																									
CWA03-CW5ST02-3370	WA03 - 06 - Survey Soil Nail Wall - ML2046L	1	18-May-20	19-May-20	184																									
CWA03-CW5ST02-3380	WA03 - 06 - Excavate FG Slope Soil Nail Wall - ML2046L	2	19-May-20	21-May-20	180																									
CWA03-CW5ST02-3390	WA03 - 06 - Install Soil Nails (40 Ea @ 5' O.C. - 8 per Day) - ML2046L	5	22-May-20	01-Jun-20	184																									
CWA03-CW5ST02-3400	WA03 - 06 - Install Mesh and Whalers for Soil Nail Wall - ML2046L	2	01-Jun-20	03-Jun-20	184																									
CWA03-CW5ST02-3410	WA03 - 06 - Place Initial Shotcrete - ML2046L	1	02-Jun-20	03-Jun-20	184																									
CWA03-CW5ST02-3420	WA03 - 06 - Place Final Shotcrete - ML2046L	1	03-Jun-20	04-Jun-20	184																									
CWA03-CW5ST02-3430	Work Area 03 - Phase 1 - Stage 02 - Soil Nail/Shotcrete Walls - Completion Milestone	0		04-Jun-20	184																									
<b>WA03 - Phase I - Stage 03 - Structures</b>		<b>507</b>	<b>08-Aug-19</b>	<b>16-Aug-21</b>	<b>263</b>																									
<b>WA03 - Phase I - Stage 03 - Structures - Bridges</b>		<b>257</b>	<b>27-Aug-19</b>	<b>02-Sep-20</b>	<b>501</b>																									
<b>Cook Street 11 - Bridge Phase/Stage 01</b>		<b>130</b>	<b>27-Aug-19</b>	<b>05-Mar-20</b>	<b>293</b>																									
CWA03-BR11-3010	Detour Crossroad Traffic - Cook St. over I-70	2	27-Aug-19	28-Aug-19	90																									
CWA03-BR11-3000	Work Area 03 - Cook Street Bridge - Summary LOE	192	27-Aug-19	05-Mar-20	425																									
CWA03-BR11-3020	Cut Wall - Abutment 1 - Cook St. over I-70	9	29-Aug-19	11-Sep-19	303																									
CWA03-BR11-3030	Cut Wall - Abutment 3 - Cook St. over I-70	9	12-Sep-19	25-Sep-19	303																									
CWA03-BR11-3040	Excavate to Btm of Caps (Abut to Abut) - Cook St. over I-70	5	26-Sep-19	02-Oct-19	298																									
CWA03-BR11-3060	F/P/S Lower Abutment/Wings - Abutment 1 - Cook St. over I-70	9	03-Oct-19	16-Oct-19	316																									
CWA03-BR11-3070	F/P/S Lower Abutment/Wings - Abutment 3 - Cook St. over I-70	9	03-Oct-19	16-Oct-19	316																									
CWA03-BR11-3050	Caissons - Pier 2 - Cook St. over I-70	5	03-Oct-19	09-Oct-19	302																									
CWA03-BR11-3080	F/R/P Column - Pier 2 - Cook St. over I-70	9	10-Oct-19	23-Oct-19	302																									
CWA03-BR11-3090	F/P/S Pier Cap - Pier 2 - Cook St. over I-70	9	24-Oct-19	06-Nov-19	302																									
CWA03-BR11-3100	Erect Precast Girders - Cook St. over I-70	3	15-Nov-19	19-Nov-19	305																									
CWA03-BR11-3110	F&I Precast Deck Panels - Cook St. over I-70	2	19-Nov-19	20-Nov-19	305																									
CWA03-BR11-3190	Prep & Place Top Wearing Surface - Cook St. over I-70	3	19-Nov-19	03-Mar-20	215																									
CWA03-BR11-3120	F/R/P Deck Slab - Cook St. over I-70	8	21-Nov-19	05-Dec-19	284																									
CWA03-BR11-3130	Backfill Abutments - Cook St. over I-70	6	02-Dec-19	13-Dec-19	263																									
CWA03-BR11-3140	Concrete Cure Period for Deck Slab - Cook St. over I-70	20	06-Dec-19	25-Dec-19	490																									
CWA03-BR11-3150	Approach Slabs - Cook St. over I-70	4	16-Dec-19	20-Dec-19	284																									
CWA03-BR11-3170	Concrete Cure Period for Approach Slabs - Cook St. over I-70	20	21-Dec-19	09-Jan-20	478																									
CWA03-BR11-3160	F/R/P/S Bridge Rail - Cook St. over I-70	8	23-Dec-19	08-Jan-20	304																									
CWA03-BR11-3180	Strip Superstructure - Cook St. over I-70	2	09-Jan-20	10-Jan-20	306																									

Project ID: CENTRAL 70 - PBS-08


Baseline ID:

Data Date: 18-May-17

Print Date: 24-May-17

### Central 70 - 5280 Connectors - Proposal Baseline(PBS-01)

#### Central 70 Proposal Schedule























































Activity ID	Activity Name	Original Duration	Start	Finish	Total Float	2017				2018				2019				2020				2021				2022				2023				
						Q2	Q3	Q4		Q1	Q2	Q3	Q4	Q1	Q2	Q3	Q4	Q1	Q2	Q3	Q4	Q1	Q2	Q3	Q4	Q1	Q2	Q3	Q4	Q1	Q2	Q3	Q4	Q1
CWA02-DRIR01-2150	Denver Rock Island Rail Road Completion Milestone - WA 02	0		04-Feb-21	293																													
<b>Work Area 03 - Brighton-Dahlia WB Station 2005+00 to 2104+00</b>		<b>739</b>	<b>01-Dec-17</b>	<b>09-Nov-20</b>	<b>575</b>																													
<b>Construction</b>		<b>739</b>	<b>01-Dec-17</b>	<b>09-Nov-20</b>	<b>575</b>																													
<b>WA03 - Phase I - Rail Road</b>		<b>739</b>	<b>01-Dec-17</b>	<b>09-Nov-20</b>	<b>575</b>																													
<b>WA03- Phase I - Stage 00 - Rail Road</b>		<b>334</b>	<b>01-Dec-17</b>	<b>02-Apr-19</b>	<b>73</b>																													
CWA03-UPRRS00-3120	Enter UPRR Agreement - WA03 - Phase I - UPRR	20	01-Dec-17	29-Dec-17	195																													
CWA03-UPRRS00-3210	Design/Bid/Construct UPRR 36th Yard Expansion - (By UPRR)	185	02-Jan-18*	10-Oct-18	68																													
CWA03-UPRRS00-3125	Procurement of UPRR Track/Switches - (By UPRR)	60	02-Jan-18	28-Mar-18	199																													
CWA03-UPRRS00-3150	Perform Engineering Analysis - WA03 - Phase I - UPRR	20	02-Jan-18	30-Jan-18	195																													
CWA03-UPRRS00-3160	Prepare Detailed Work Plans - WA03 - Phase I - UPRR	20	17-Jan-18	13-Feb-18	195																													
CWA03-UPRRS00-3170	Schedule Roadway Closure - WA03 - Phase I - UPRR	20	31-Jan-18	28-Feb-18	195																													
CWA03-UPRRS00-3180	Provide Pre-Demo Notice - WA03 - Phase I - UPRR	20	20-Feb-18	19-Mar-18	195																													
CWA03-UPRRS00-3190	Conduct Pre-Operation Coordination - WA03 - Phase I - UPRR - West	20	20-Mar-18	16-Apr-18	195																													
CWA03-UPRRS00-3000	Perform Track Work North & South of Viaduct - WA03 - Phase I - UPRR - West (by UPRR)	40	10-Oct-18	11-Dec-18	137																													
CWA03-UPRRS00-3030	Work Area 03 - Phase I - Stage 00 - UPRR Rail Road Work - Summary LOE	174	10-Oct-18	02-Apr-19	105																													
CWA03-UPRRS00-3010	Install Temporary Access Crossing - WA03 - Phase I - UPRR - West (by UPRR)	5	04-Dec-18	11-Dec-18	137																													
CWA03-UPRRS00-3020	Temporary Relocate Up Signal Lines - WA03 - Phase I - UPRR - West (by UPRR)	10	11-Dec-18	27-Dec-18	137																													
CWA03-UPRRS00-3040	Set-up 46th Ave Detour Route - WA03 - Phase I - UPRR - West (by UPRR)	5	27-Dec-18	04-Jan-19	137																													
CWA03-UPRRS00-3050	Close 46th Ave to Traffic - WA03 - Phase I - UPRR - West (by UPRR)	5	04-Jan-19	14-Jan-19	137																													
CWA03-UPRRS00-3060	Build New UPRR Maintenance Road Detour - WA03 - Phase I - UPRR - West (by UPRR)	10	14-Jan-19	30-Jan-19	68																													
CWA03-UPRRS00-3070	Remove Paving & Underdrain System - WA03 - Phase I - UPRR - West	10	14-Jan-19	30-Jan-19	68																													
CWA03-UPRRS00-3080	Install Temporary Drainage System - WA03 - Phase I - UPRR - West	20	30-Jan-19	04-Mar-19	68																													
CWA03-UPRRS00-3090	Temporary Relocate FO Lines - WA03 - Phase I - UPRR	20	04-Mar-19	02-Apr-19	68																													
<b>WA03- Phase I - Stage 01 - Rail Road</b>		<b>100</b>	<b>04-Apr-19</b>	<b>26-Aug-19</b>	<b>267</b>																													
CWA03-BNSFS01-3010	Prepare Subgrade for RR - North Side - BNSF Market Lead Rail Road	4	04-Apr-19	10-Apr-19	144																													
CWA03-BNSFS01-3000	Work Area 03 - Phase I - Stage 02 - BNSF Rail Road - Summary LOE	42	04-Apr-19	16-May-19	490																													
CWA03-BNSFS01-3020	F&I Subballast for RR - Northside - BNSF Market Lead Rail Road	3	10-Apr-19	15-Apr-19	149																													
CWA03-BNSFS01-3030	F&I Ballast - Northside (Including Bridge) - BNSF Market Lead Rail Road	5	15-Apr-19	23-Apr-19	319																													
CWA03-BNSFS01-3040	Final Phase Tracks - North Side (by BNSF) - BNSF Market Lead Rail Road	15	23-Apr-19	16-May-19	319																													
CWA03-UPRRS01-3040	Excavate Demo East Retaining Walls - WA03 - Phase I - UPRR	5	25-Apr-19	01-May-19	90																													
CWA03-UPRRS01-3050	Install SOE for Bridge - East Side - WA03 - Phase I - UPRR	4	01-May-19	06-May-19	90																													
CWA03-UPRRS01-3060	Place Fill East Side Shootily - WA03 - Phase I - UPRR	4	01-May-19	06-May-19	90																													
CWA03-UPRRS01-3010	Excavate Demo Existing West Retaining Walls - WA03 - Phase I - UPRR - West	5	02-May-19	09-May-19	80																													
CWA03-UPRRS01-3000	Work Area 03 - Phase I - Stage 02 - UPRR West - Summary LOE	117	02-May-19	26-Aug-19	109																													
CWA03-UPRRS01-3090	UPRR Track Work East - WA03 - (By UPRR)	30	06-May-19	19-Jun-19	78																													
CWA03-UPRRS01-3020	Install SOE for Bridge - West Side - WA03 - Phase I - UPRR - West	4	09-May-19	14-May-19	80																													
CWA03-UPRRS01-3030	Place Fill West Side Shootily - WA03 - Phase I - UPRR - West	4	14-May-19	18-May-19	80																													
CWA03-BNSFS01-3050	Work Area 03 - Phase I - Stage 02 - BNSF Rail Road - Completion Milestone	0		16-May-19	319																													
CWA03-UPRRS01-3070	UPRR Track Work West - WA03 - (By UPRR)	30	20-May-19	01-Jul-19	69																													
CWA03-UPRRS01-3080	Install Shoo Fly Track - West - WA03 - Phase I - UPRR - West	5	26-Jun-19	01-Jul-19	81																													
CWA03-UPRRS01-3100	Install Shoo Fly Track - East - WA03 - Phase I - UPRR	5	02-Jul-19	10-Jul-19	81																													
CWA03-UPRRS01-3110	Install Shoo Fly Switches North & South - WA03 - Phase I - UPRR - West	5	11-Jul-19	16-Jul-19	81																													
CWA03-UPRRS01-3120	Shift Rail Traffic to Shoo Flies - WA03 - Phase I - UPRR - West	5	17-Jul-19	22-Jul-19	81																													
CWA03-UPRRS01-3130	Remove Track & OTM on Existing Bridge - WA03 - Phase II - UPRR - West	5	23-Jul-19	29-Jul-19	81																													
CWA03-UPRRS01-3140	Install Ballast Retainer - Phase Line - WA03 - Phase II - UPRR - West	5	30-Jul-19	03-Aug-19	81																													
CWA03-UPRRS01-3150	Remove Ballast from West Side - WA03 - Phase II - UPRR - West	3	30-Jul-19	01-Aug-19	81																													
CWA03-UPRRS01-3160	Remove WI Deck Plates - WA03 - Phase II - UPRR - West	5	30-Jul-19	03-Aug-19	81																													

Project ID: CENTRAL 70 - PBS-08  
 BaselineID:  
 Data Date: 18-May-17

Print Date: 24-May-17

**Central 70 - 5280 Connectors - Proposal Baseline(PBS-01)**

**Central 70 Proposal Schedule**

■ Critical Remaining Work     ■ Actual Level of Effort  
◆ Milestone     ■ Actual Work  
■ Remaining Level of Effort     ■ Remaining Work









































Activity ID	Activity Name	Original Duration	Start	Finish	Total Float	2017				2018				2019				2020				2021				2022	2023										
						Q2	Q3	Q4	Q1	Q2	Q3	Q4	Q1	Q2	Q3	Q4	Q1	Q2	Q3	Q4	Q1	Q2	Q3	Q4	Q1	Q2	Q3	Q4	Q1								
RWA03-RRDRP006-3010	Property 006 Right-of-Way Rail Road/Drainage Easements - WA03 (NTP 02)	0		23-May-18	627																																
<b>Property PE-035 - Rail Road/Drainage Easements - ROW Acquisitions - Work Area 03</b>						400	23-May-18	30-Dec-19	227																												
RWA03-RRDRP035-2010	Property 035 ROW Acquisitions - 18 Months after NTP 02	400	23-May-18	30-Dec-19	227																																
RWA03-RRDRP035-3010	Property 035 Right-of-Way Rail Road/Drainage Easements - WA03 (18 Mo after NTP 02)	0		30-Dec-19	227																																
<b>Property PE-036 - Rail Road/Drainage Easements - ROW Acquisitions - Work Area 03</b>						400	23-May-18	30-Dec-19	227																												
RWA03-RRDRP036-2010	Property 036 ROW Acquisitions - 18 Months after NTP 02	400	23-May-18	30-Dec-19	227																																
RWA03-RRDRP036-3010	Property 036 Right-of-Way Rail Road/Drainage Easements - WA03 (18 Mo after NTP 02)	0		30-Dec-19	227																																
<b>Property PE-037 - Rail Road/Drainage Easements - ROW Acquisitions - Work Area 03</b>						400	23-May-18	30-Dec-19	227																												
RWA03-RRDRP037-2010	Property 037 ROW Acquisitions - 18 Months after NTP 02	400	23-May-18	30-Dec-19	227																																
RWA03-RRDRP037-3010	Property 037 Right-of-Way Rail Road/Drainage Easements - WA03 (18 Mo after NTP 02)	0		30-Dec-19	227																																
<b>Property PE-038 - Rail Road/Drainage Easements - ROW Acquisitions - Work Area 03</b>						400	23-May-18	30-Dec-19	227																												
RWA03-RRDRP038-2010	Property 038 ROW Acquisitions - 18 Months after NTP 02	400	23-May-18	30-Dec-19	227																																
RWA03-RRDRP038-3010	Property 038 Right-of-Way Rail Road/Drainage Easements - WA03 (18 Mo after NTP 02)	0		30-Dec-19	227																																
<b>Property PE-039 - Rail Road/Drainage Easements - ROW Acquisitions - Work Area 03</b>						400	23-May-18	30-Dec-19	227																												
RWA03-RRDRP039-2010	Property 039 ROW Acquisitions - 18 Months after NTP 02	400	23-May-18	30-Dec-19	227																																
RWA03-RRDRP039-3010	Property 039 Right-of-Way Rail Road/Drainage Easements - WA03 (18 Mo after NTP 02)	0		30-Dec-19	227																																
<b>Property PE-040 - Rail Road/Drainage Easements - ROW Acquisitions - Work Area 03</b>						400	23-May-18	30-Dec-19	227																												
RWA03-RRDRP040-2010	Property 040 ROW Acquisitions - 18 Months after NTP 02	400	23-May-18	30-Dec-19	227																																
RWA03-RRDRP040-3010	Property 040 Right-of-Way Rail Road/Drainage Easements - WA03 (NTP 02)	0		30-Dec-19	227																																
<b>Partial Acquisitions - ROW Acquisitions - Work Area 03</b>						390	13-Aug-18	06-Mar-20	314																												
<b>Property RW-104 - Partial Acquisitions - ROW Acquisitions - Work Area 03</b>						390	13-Aug-18	06-Mar-20	314																												
RWA03-PARP104-1010	Written notification by Developer to commence partial acquisitions w/ CAD design file & ROW Appraisals - WA03 PARP-104	5	13-Aug-18	17-Aug-18	314																																
RWA03-PARP104-1020	Develop Parcel acquisition files - WA03 PARP-104	5	20-Aug-18	24-Aug-18	314																																
RWA03-PARP104-1030	Property Survey - WA03 PARP-104	10	27-Aug-18	10-Sep-18	314																																
RWA03-PARP104-1040	Delivery of Eng. design - requiring ROW completed to a sufficient level will not change as design is advanced - PARP-104	10	27-Aug-18	10-Sep-18	314																																
RWA03-PARP104-1050	Appraisal and Appraisal review - WA03 PARP-104	15	11-Sep-18	01-Oct-18	314																																
RWA03-PARP104-1060	Acquisition negotiation - WA03 PARP-104	60	02-Oct-18	31-Dec-18	314																																
RWA03-PARP104-1070	Value Findings - WA03 PARP-104	10	02-Jan-19	15-Jan-19	314																																
RWA03-PARP104-1080	Relocation Plan - WA03 PARP-104	10	02-Jan-19	15-Jan-19	314																																
RWA03-PARP104-1090	Administrative settlement - WA03 PARP-104	20	16-Jan-19	13-Feb-19	314																																
RWA03-PARP104-1100	Condemnation - WA03 PARP-104	65	14-Feb-19	16-May-19	314																																
RWA03-PARP104-1110	Certification that acquisition was completed in compliance with state and federal requirements - WA03 PARP-104	15	17-May-19	07-Jun-19	314																																
RWA03-PARP104-1120	Acquisition by 5280 Connectors - milestone - WA03 PARP-104	0	10-Jun-19		314																																
RWA03-PARP104-1140	Certification of review of CDOT Right of Way Manual - PARP-104	10	10-Jun-19	21-Jun-19	314																																
RWA03-PARP104-1130	Develop Condemnation Memorandum and checklist - WA03 PARP-104	10	10-Jun-19	21-Jun-19	314																																
RWA03-PARP104-1150	Permission to Enter Property Form - WA03 PARP-104	20	24-Jun-19	22-Jul-19	314																																
RWA03-PARP104-1180	Property Management Plan - WA03 PARP-104	10	23-Jul-19	05-Aug-19	314																																
RWA03-PARP104-1190	Prepare SWMP - WA03 PARP-104	10	23-Jul-19	05-Aug-19	314																																
RWA03-PARP104-1160	Structure Survey Assessment Report ("SSAR") (per parcel structure) - WA03 PARP-104	10	23-Jul-19	05-Aug-19	314																																
RWA03-PARP104-1170	Demolition Plan - WA03 PARP-104	10	23-Jul-19	05-Aug-19	314																																
RWA03-PARP104-1200	Relocation by 5280 Connectors - WA03 PARP-104	85	06-Aug-19	09-Dec-19	314																																
RWA03-PARP104-1220	Installation of Security Fencing - WA03 PARP-104	5	10-Dec-19	16-Dec-19	314																																
RWA03-PARP104-1210	Regular maintenance and inspection - WA03 PARP-104	60	10-Dec-19	06-Mar-20	314																																
RWA03-PARP104-1230	Hazardous Substance Testing - WA03 PARP-104	15	17-Dec-19	08-Jan-20	314																																
RWA03-PARP104-1240	Disconnect Utilities - WA03 PARP-104	5	17-Dec-19	23-Dec-19	324																																
RWA03-PARP104-1250	Board up property - WA03 PARP-104	5	17-Dec-19	23-Dec-19	354																																
RWA03-PARP104-1260	Surface removal / remediation of hazardous materials - WA03 PARP-104	20	09-Jan-20	06-Feb-20	314																																
RWA03-PARP104-1270	Subsurface removal / remediation of hazardous materials - WA03 PARP-104	20	09-Jan-20	06-Feb-20	314																																
RWA03-PARP104-1280	Installation of SWPM BMPs - WA03 PARP-104	10	07-Feb-20	21-Feb-20	314																																
RWA03-PARP104-1290	Building Demolition - WA03 - PARP-104	10	24-Feb-20	06-Mar-20	314																																
RWA03-PARP104-2000	Property 104 Right-of-Way Partial Acquisitions - WA03 Acquisition Completion Milestone	0		06-Mar-20	314																																
<b>Property RW-087 - Partial Acquisitions - ROW Acquisitions - Work Area 03</b>						390	13-Aug-18	06-Mar-20	314																												
RWA03-PARP087-1010	Written notification by Developer to commence partial acquisitions w/ CAD design file & ROW Appraisals - WA03 PARP-087	5	13-Aug-18	17-Aug-18	314																																
RWA03-PARP087-1020	Develop Parcel acquisition files - WA03 PARP-087	5	20-Aug-18	24-Aug-18	314																																
RWA03-PARP087-1030	Property Survey - WA03 PARP-087	10	27-Aug-18	10-Sep-18	314																																
RWA03-PARP087-1040	Delivery of Eng. design - requiring ROW completed to a sufficient level will not change as design is advanced - PARP-087	10	27-Aug-18	10-Sep-18	314																																

Project ID: CENTRAL 70 - PBS-08  
 BaselineID:  
 Data Date: 18-May-17

Print Date: 24-May-17

### Central 70 - 5280 Connectors - Proposal Baseline(PBS-01)

#### Central 70 Proposal Schedule

- Critical Remaining Work
- Actual Level of Effort
- Remaining Level of Effort
- Actual Work
- Remaining Work
- ◆ Milestone













































































































































































Activity ID	Activity Name	Original Duration	Start	Finish	Total Float	2017				2018				2019				2020				2021				2022				2023
						Q2	Q3	Q4	Q1	Q2	Q3	Q4	Q1	Q2	Q3	Q4	Q1	Q2	Q3	Q4	Q1	Q2	Q3	Q4	Q1	Q2	Q3	Q4	Q1	
CWA05-ELTS01-5240	Install WB cabinets in WA05 - Brighton Blvd. to I-25 Station 2005 to 1942 WB	5	11-Feb-22	22-Feb-22	96																									
CWA05-ELTS01-5410	Install EB foundations Poured in place in - Brighton Blvd. to I-25 Station 2005 to 1942 EB	5	14-Feb-22	23-Feb-22	101																									
CWA05-ELTS01-5350	Install EB conduit Pull Boxes MVDS in WA05 - Segment 1 - Brighton Blvd. to I-25 Station 2005 to 1942 EB	5	14-Feb-22	23-Feb-22	95																									
CWA05-ELTS01-5360	Install EB conduit & pullboxes DMS in WA05 - Segment 1 - Brighton Blvd. to I-25 Station 2005 to 1942 EB	5	14-Feb-22	23-Feb-22	96																									
CWA05-ELTS01-5370	Install EB cabinets in WA05 - Brighton Blvd. to I-25 Station 2005 to 1942 EB	5	14-Feb-22	23-Feb-22	96																									
CWA05-ELTS01-5290	Install WB foundations Precast in - Brighton Blvd. to I-25 Station 2005 to 1942 WB	5	22-Feb-22	01-Mar-22	102																									
CWA05-ELTS01-5250	Install WB power cabinet in - Brighton Blvd. to I-25 Station 2005 to 1942 WB	5	22-Feb-22	01-Mar-22	99																									
CWA05-ELTS01-5260	Place WB fiber cable in - Brighton Blvd. to I-25 Station 2005 to 1942 WB	8	22-Feb-22	07-Mar-22	96																									
CWA05-ELTS01-5420	Install EB foundations Precast in - Brighton Blvd. to I-25 Station 2005 to 1942 EB	5	23-Feb-22	03-Mar-22	101																									
CWA05-ELTS01-5380	Install EB power cabinet in - Brighton Blvd. to I-25 Station 2005 to 1942 EB	5	23-Feb-22	03-Mar-22	99																									
CWA05-ELTS01-5390	Place EB fiber cable in - Brighton Blvd. to I-25 Station 2005 to 1942 EB	8	23-Feb-22	08-Mar-22	96																									
CWA05-ELTS01-5300	Install WB equipment in - Brighton Blvd. to I-25 Station 2005 to 1942 WB	5	01-Mar-22	09-Mar-22	102																									
CWA05-ELTS01-5430	Install EB equipment in - Brighton Blvd. to I-25 Station 2005 to 1942 EB	5	03-Mar-22	10-Mar-22	102																									
CWA05-ELTS01-5270	Splice and test WB fiber cable ( Zayo) in - Brighton Blvd. to I-25 Station 2005 to 1942 WB	8	07-Mar-22	18-Mar-22	96																									
CWA05-ELTS01-5400	Splice and test EB fiber cable ( Zayo) in - Brighton Blvd. to I-25 Station 2005 to 1942 EB	8	08-Mar-22	21-Mar-22	96																									
CWA05-ELTS01-5310	Test & Commision WB CCTV in - Brighton Blvd. to I-25 Station 2005 to 1942 WB	10	09-Mar-22	24-Mar-22	102																									
CWA05-ELTS01-5320	Test & Commision WB EILTS in - Brighton Blvd. to I-25 Station 2005 to 1942 WB	10	18-Mar-22	04-Apr-22	96																									
CWA05-ELTS01-5440	Test & Commision EB CCTV in - Brighton Blvd. to I-25 Station 2005 to 1942 EB	10	21-Mar-22	05-Apr-22	96																									
CWA05-ELTS01-5450	Test & Commision EB EILTS in - Brighton Blvd. to I-25 Station 2005 to 1942 EB	10	21-Mar-22	05-Apr-22	96																									
CWA05-ELTS01-5330	EILTS - Brighton Blvd. to I-25 Station 2005 to 1942 WB - Completion Milestone	0		04-Apr-22	96																									
CWA05-ELTS01-5470	EILTS - Brighton Blvd. to I-25 Station 2005 to 1942 WB & EB - Completion Milestone	0		05-Apr-22	96																									
CWA05-ELTS01-5460	EILTS - Brighton Blvd. to I-25 Station 2005 to 1942 EB - Completion Milestone	0		05-Apr-22	96																									
<b>EILTS - Lighting</b>		<b>24</b>	<b>11-Feb-22</b>	<b>18-Mar-22</b>	<b>111</b>																									
CWA05-ELTS01-5805	Mid Mast Lighting WB - Brighton Blvd. to I-25 Station 2005 to 1942 WB	10	11-Feb-22	01-Mar-22	107																									
CWA05-ELTS01-5800	WA05 - EILTS WB/EB Lighting - Summary LOE	35	11-Feb-22	18-Mar-22	159																									
CWA05-ELTS01-5820	Mid Mast Lighting EB - Brighton Blvd. to I-25 Station 2005 to 1942 EB	10	14-Feb-22	03-Mar-22	107																									
CWA05-ELTS01-5810	Street lighting WB - Brighton Blvd. to I-25 Station 2005 to 1942 WB	10	01-Mar-22	17-Mar-22	107																									
CWA05-ELTS01-5830	Street lighting EB - Brighton Blvd. to I-25 Station 2005 to 1942 EB	10	03-Mar-22	18-Mar-22	107																									

Project ID: CENTRAL 70 - PBS-08  
 BaselineID:  
 Data Date: 18-May-17

Print Date: 24-May-17

**Central 70 - 5280 Connectors - Proposal Baseline(PBS-01)**  
**Central 70 Proposal Schedule**

	Critical Remaining Work		Actual Level of Effort
	Milestone		Actual Work
	Remaining Level of Effort		Remaining Work



1700 Lincoln Street, Suite 300  
Denver, CO 80203

[www.5280Connectors.com](http://www.5280Connectors.com)

