**Report No. CDOT-2009-2 Final Report** 



# **COLORADO DEPARTMENT OF TRANSPORTATION'S CURRENT PROCEDURE FOR LIFE CYCLE COST ANALYSIS AND DISCOUNT RATE CALCULATIONS**

Scott Harris, CDOT Pavement Design Program

January 2009

COLORADO DEPARTMENT OF TRANSPORTATION DTD APPLIED RESEARCH AND INNOVATION BRANCH The contents of this report reflect the views of the author(s), who is(are) responsible for the facts and accuracy of the data presented herein. The contents do not necessarily reflect the official views of the Colorado Department of Transportation or the Federal Highway Administration. This report does not constitute a standard, specification, or regulation.

**Technical Report Documentation Page** 

1. Report No. CDOT-2009-2			3. Recipient's Catalog No.				
4. Title and Subtitle COLORADO DEPARTMENT OF TR PROCEDURE FOR LIFE CYCLE CO		T Janua	5. Report Date January 2009				
RATE CALCULATIONS		6. Per	6. Performing Organization Code				
7. Author(s)			8. Performing Organization Report No.				
Scott Harris		CDO.	CDOT-2009-2				
9. Performing Organization Name and Addr Materials and Geotechnical Branch	955	10. Wo	ork Unit No. (TRAIS)				
4670 Holly St. Unit A Denver, Colorado 80216		11. Co	11. Contract or Grant No.				
12. Sponsoring Agency Name and Address		13. Tvi	be of Report and Pe	riod Covered			
Colorado Department of Transportatio	n - Research	Final					
4201 E. Arkansas Ave. Denver, CO 80222							
		14. Sp	14. Sponsoring Agency Code				
15. Supplementary Notes Prepared in cooperation with the US D	epartment of Transportation, Fe	deral Highway A	Administration				
16. Abstract This report provides information on lif CDOT uses to select a discount rate. I discount rates.							
Implementation:							
The discount rate will be calculated an Engineers in each Region for use in the		ement Design U	nit and distributed	to the Pavement Design			
17. Keywords LCCA, discount rate, probabilistic triangular distribution, normal distrib inflation, rehabilitation cycles		No restrictions through the Na	Distribution Statement restrictions. This document is available to the public ough the National Technical Information Service, ringfield, VA 22161				
19. Security Classif. (of this report) Unclassified			21. No. of Pages 13	22. Price			

## COLORADO DEPARTMENT OF TRANSPORTATION'S CURRENT PROCEDURE FOR LIFE CYCLE COST ANALYSIS AND DISCOUNT RATE CALCULATIONS

by

Scott Harris Report No. CDOT-2009-2

Prepared by Colorado Department of Transportation Materials and Geotechnical Branch

Sponsored by the

Colorado Department of Transportation In Cooperation with the U.S. Department of Transportation Federal Highway Administration

January 2009

Colorado Department of Transportation DTD Applied Research and Innovation Branch 4291 E Arkansas Ave. Denver, CO 80222 (303) 757-9506

### ACKNOWLEDGEMENTS

The author wishes to give special thanks to Jay Goldbaum and Bob Locander of the CDOT Materials and Geotechnical Branch for their efforts developing the LCCA procedures and time spent reviewing this document. Without them this report would not have been possible.

#### Introduction

The Colorado Department of Transportation (CDOT) has previously published life cycle cost analysis (LCCA) procedural reports in 2002 and 2006. This is an update to the earlier reports defining the currently approved LCCA practices for CDOT pavement designs statewide.

CDOT has a written LCCA process for pavements dating back to 1972. The original process remains fundamentally unchanged, although the CDOT LCCA procedure has been updated in 1981, 1994, 2000, 2002 and 2008. The changes made in 2008 addressed the minimum dollar amount requiring LCCA for pavement construction and the method for determining the State's discount rate.

#### Life Cycle Cost Analysis

The Federal Highway Administration (FHWA) defines LCCA as an analysis technique that builds on the well-founded principles of economic analysis to evaluate the over-all-long-term economic efficiency between competing alternative investment options. It does not address equity issues. It incorporates initial and discounted future agency, user, and other relevant costs over the life of alternative investments. It attempts to identify the best value (the lowest long-term cost that satisfies the performance objective being sought) for investment expenditures<sup>(1)</sup>.

Before a LCCA can be carried out a benefit-cost analysis (BCA) is performed to determine if a project's desired benefit can be obtain through a reasonable cost. Once a BCA deems a project necessary, the LCCA approach is used to objectively compare alternatives over a predetermined amount of time. The primary use of LCCA by CDOT is to compare alternatives for asphalt and concrete pavements. Once the pavement designs for both alternatives have been completed, the initial construction, annual maintenance, required rehabilitations, and user costs are calculated for both. Then these costs are run through a 40-year life cycle cost analysis to identify the alternative with the lowest overall cost and best value for the traveling public. In 2002, CDOT increased the analysis period to 40 years. The 40-year analysis period was chosen by CDOT, because

FHWA's LCCA Policy Statement recommends an analysis period of at least 35 years for all pavement projects <sup>(2)</sup>. CDOT planned to follow FHWA's recommendation, as well as account for pavement rehabilitation cycles to prevent having to use a salvage value. Unmodified HMA has a 10-year rehab life, which easily led to a 40-year analysis period.

After the preliminary designs are completed for each pavement type's typical section, pavement quantities, costs, and construction time can be estimated. The estimated initial pavement costs, along with annual maintenance, rehabilitation, and user costs are the foundation for a reliable LCCA decision. The LCCA calculations for CDOT are done using FHWA's RealCost software. The RealCost software performs both deterministic and probabilistic calculations. Deterministic LCCA provides a discrete output based on specific inputs. Probabilistic LCCA takes into account the uncertainty of the input and carries that uncertainty through the calculation to create a distribution curve with costs associated to varying probabilities.

CDOT uses three types of distribution curves in the probabilistic LCCA process; triangular, normal, and lognormal. A triangular distribution, see Figure 1, is a subjective description of a population for which there is only limited sample data. It is based on the knowledge of the minimum and maximum and requires an educated guess as to what the most likely value might be. The triangular distribution is used when evaluating initial construction costs for probabilistic LCCA, because historical data combined with quantity of scale provide a reasonable minimum, maximum, and average.






Figure 1. Triangular Distribution Curve

Unlike the triangular distribution, which may or may not be symmetrical, a normal distribution, see Figure 2, is a symmetrical bell-shaped density curve with two specific values one being the mean and the other being the standard deviation. The normal distribution is used for incorporating the discount rate into the probabilistic analysis, because a mean and standard deviation for the discount rate can be easily calculated from the 10-year moving average of real interest rates.



**Figure 2. Normal Distribution Curve** 

Lognormal distributions, see Figure 3, are defined with reference to a normal distribution and the fact they must always be positive. A random variable is lognormally distributed if the logarithm of that random variable is normally distributed. The lognormal distribution was chosen to be used for the activity service life of initial construction and rehabilitation projects, because although there is some variability, the number of years required for service life must be positive.



**Figure 3. Lognormal Distribution Curve** 

Once all values are entered into the RealCost software and calculations are complete, a comparison of the alternatives is based on the probabilistic LCCA output for 75% confidence level. In 2008, CDOT recommended that the probabilistic approach to LCCA be used in conjunction with deterministic to allow designers some time to adjust. In January of 2009 CDOT required the probabilistic approach be the primary means of LCCA.

CDOT requires the LCCA process for all new or reconstruction projects with a pavement material cost of more than \$2,000,000<sup>(3)</sup>. Pavement cost includes anything associated with the pavement structure i.e. asphalt, base coarse and subbase. The 2 million dollar amount is also the requirement for surface treatment projects when both concrete and asphalt are considered feasible alternatives. If one of the alternatives is determined to not be practical the decision should be documented in the Pavement Justification Report (PJR).

Examples of projects where LCCA may not be necessary are <sup>(3)</sup>:

- A concrete pavement, which is structurally sound and requires only resealing and/or minor rehabilitation work
- A concrete or asphalt pavement, which is structurally sound but may need skid properties restored or ride improved
- Minor safety improvements such as channelization, shoulder work
- Bridge replacement projects with minimal pavement work
- Locations where curb and gutter or barrier prohibits the use of alternative thicker treatments

#### **Discount Rate**

The discounting process allows people to compare projects with different funding requirements to identify the most beneficial by taking future costs and giving them an equivalent present dollar value.

A discount rate is the factor used to identify a present value of goods or services when dealing with a future cost expressed in constant dollars. Typically a discount rate is the difference between the interest rate and the inflation rate, which gives a value to money if saved rather then spent. Public agencies cannot invest or save the taxpayers' money, so they are responsible for finding the best use for these funds through public projects that provide a cost savings or expanded output. Even though the government cannot chose to save money versus spend it, the discount rate is still required, because by taxing the public the taxpayer is not given the chance to invest their money, which is known as the opportunity cost of capital.

CDOT has used a couple different methods to determine its discount rate, but after several meetings with FHWA, CDOT's Materials Advisory Committee (MAC) recommended in July of 2007 to use the Office of Management and Budget's (OMB) real interest rate data to calculate the discount rate for CDOT. The following link to the OMB website has a list of the real interest rates from 1979 to 2008. http://www.whitehouse.gov/omb/circulars/a094/dischist.pdf

Due to the pavements initial design period and the 40-year analysis period for LCCA, the MAC determined that the longest maturity and most conservative investment strategy for interest rates should be used. The longest maturity for interest rates from the OMB is 30 years, which on the attached link to the OMB website is the far right column on the second page. The discount rate will then be calculated using the 10-year moving average to better account for the year-to-year movement in the real rates. The standard deviation calculation is then based on the previous 10-year moving averages.

Every year, the OMB publishes a new 30-year Real Treasury interest rate and CDOT will be using this annual value in order to update the discount rate. Table 1, shows how the data can be arranged to calculate the average and standard deviation. For example, for the 2008 data the 10-year moving average (1999 to 2008) provides a new discount rate of 3.3% and the previous 10 years of the moving average (1998 to 2007) are used to determine a standard deviation of 0.22%.

#### Table 1

	7-Year	10-Year	10-Year	10-Year	30-Year	10-Year
Year	Note	Moving	Note	Moving	Note	Moving
1979	4.1		4.6		5.4	
1980	2.9		3.3		3.7	
1981	4.3		4.4		4.8	
1982	7.5		7.8		7.9	
1983	5		5.3		5.6	
1984	5.7		6.1		6.4	
1985	6.8		7.1		7.4	
1986	5.6		5.9		6.7	
1987	3.5		3.8		4.4	
1988	4.7	5	5.1	5.3	5.6	5.8
1989	5.3	5.1	5.8	5.5	6.1	5.9
1990	3.9	5.2	4.2	5.6	4.6	6
1991	3.7	5.2	3.9	5.5	4.2	5.9
1992	3.3	4.8	3.6	5.1	3.8	5.5
1993	3.9	4.6	4.3	5	4.5	5.4
1994	2.5	4.3	2.7	4.6	2.8	5
1995	4.6	4.1	4.8	4.4	4.9	4.8
1996	2.8	3.8	2.8	4.1	3	4.4
1997	3.4	3.8	3.5	4.1	3.6	4.3
1998	3.5	3.7	3.6	3.9	3.8	4.1
1999	2.7	3.4	2.7	3.6	2.9	3.8
2000	4	3.4	4	3.6	4.2	3.8
2001	3.2	3.4	3.2	3.5	3.2	3.7
2002	3	3.4	3.1	3.5	3.9	3.7
2003	2.2	3.2	2.5	3.3	3.2	3.6
2004	2.4	3.2	2.8	3.3	3.5	3.6
2005	2.3	3	2.5	3.1	3.1	3.4
2006	2.7	2.9	2.8	3.1	3	3.4
2007	2.7	2.9	2.8	3	3	3.4
2008	2.4	2.8	2.6	2.9	2.8	3.3

**Real Treasury Interest Rates and 10 Year Moving Average** 

Standard Deviation = 0.22

The newly calculated discount rate will be compared to the original, and if it changes by more than two standard deviations from the original, in this case 0.44%, a new LCCA should be performed on all projects not yet through Field Inspection Review (FIR) to verify the proper pavement was selected. Standard deviations will be calculated annually as well to ensure an appropriate year-to-year comparison can be made.

The Colorado Asphalt Paving Association (CAPA) performed a preliminary survey of several other states to find out their discount rates and the rehabilitation time periods used in their LCCA for asphalt. Table 2 shows all the states that participated in the survey. Most states use a set value of 4.0% for their discount rate. While Ohio appears to be the only state that references the OMB's real interest rate directly. The average for the states that participated is 3.8%. Discount rate selection is a critical process in LCCA, because it directly impacts which alternative will be chosen. A high discount rate favors projects with low initial construction costs and higher maintenance costs dispersed throughout the remaining life of the project. The higher maintenance costs are discounted at a greater value making it more beneficial to defer those costs. A low discount rate favors the projects with high initial costs and low maintenance costs, because any remaining cost are factored in closer to face value. An example of this would be the traditional view of hot mix asphalt (HMA) versus portland cement concrete pavement (PCCP). Until the recent fluctuation in oil prices, HMA was believed to have a lower initial construction cost, higher annual maintenance cost and more expensive rehabilitation costs than PCCP. In a situation such as this, HMA would benefit from a high discount rate in the LCCA calculation because it is deferring a greater amount of its overall cost until the future. HMA on the other hand would suffer from low discount rates, because the deferred costs are added in closer to their actual value.

		Yr@1st	Yr@2nd	Yr@3rd	Yr@4th	Total	Discount
State		OL	OL	OL	OL	Years	Rate
1	Alabama	12.0	20.0			28.0	4.0
2	Alaska						
3	Arizona	15.0	20.0	30.0		35.0	4.0
4	Arkansas	12.0	20.0			30.0	3.8
5	California	20.0	25.0	30.0	35.0		4.0
6	Colorado	10.0	20.0	30.0		40.0	3.3
7	Connecticut						
8	Delaware	12.0	20.0			30.0	3.0
9	Florida	14.0	28.0			40.0	4.0
10	Georgia	10.0	20.0			40.0	3.0
11	Hawaii	17.0	35.0			40.0	4.0
12	Idaho						
13	Illinois	20.0	40.0			40.0	3.0

Table 2

State Discount Rate and Asphalt Overlay Timetable for LCCA

14	Indiana	20.0	35.0				4.0
15	Iowa	20.0	40.0			40.0	
16	Kansas	12.0	22.0	32.0		40.0	3.0
17	Kentucky	10.0	20.0	30.0		40.0	4.0
18	Louisiana	15.0	30.0			30.0	4.0
19	Maine	16.5	25.5				4.0
20	Maryland	14.8	26.6			40.0	4.0
21	Massachusetts						
22	Michigan						
23	Minn < 7M ESALS	20.0	35.0			50.0	3.5
	Minn > 7M ESALs	15.0	27.0	40.0		50.0	3.5
24	Mississippi	12.0	22.0	30.0		40.0	4.0
25	Missouri	20.0	33.0			45.0	2.3
26	Montana						
27	Nevada	20.0				35.0	4.0
28	New Hampshire	20.0	31.0				4.0
29	New Jersey						
30	New Mexico						
31	New York						
32	Nebraska						
33	North Carolina	10.0	20.0			30.0	4.0
34	North Dakota						
35	Ohio	12.0	22.0	34.0		35.0	2.8
36	Oklahoma						
37	Oregon	20.0	40.0				4.0
38	Pennsylvania	10.0	20.0			35.0	6.0
39	Rhode Island	20.0	31.0			20.0	4.0
40	South Carolina	12.0	22.0			30.0	
41	South Dakota						
42	Tennessee	10.0	20.0	30.0		40.0	4.0
43	Texas						
44	Utah	17.5	21.0				1.0
45	Vermont	17.5	31.0	22.0		<b>7</b> 0 0	4.0
46	Virginia	12.0	22.0	32.0	44.0	50.0	4.0
47	Washington						
48	West Virginia	10.0	10.0	10.0	10.0	<b>5</b> 4.0	
49	Wisconsin	18.0	12.0	12.0	12.0	54.0	5.0
50	Wyoming			20.0		20.0	
	Average	15.1	26.1	30.0	30.3	38.0	3.8

For comparison, Table 3 includes PCCP rehabilitation schedules used in LCCA. This data was collected from a survey posted on www.transportion.org as well as information available on State DOT websites.

#### Table 3

#### State PCCP Rehabilitation Timetable for LCCA

<u>State</u>	Year	<b>Rehabilitation</b>				
Alabama <sup>(5)</sup>	20	Performs Concrete Pavement Repair				
Arkansas <sup>(5)</sup>	15	Major Patching, Diamond Grind and Joint Seal				
	25	Patch, Joint Seal, and HMA Overlay				
	30	Seal Reflective Cracks				
Colorado <sup>(5)</sup>	22	0.5% Slab Replacement, Diamond Grind, and Joint Seal				
	20-25	3% Slab Replacement of outside lane, Diamond Grind and Joint Seal				
Florida <sup>(5)</sup>	30-35	5% Slab Replacement, or Crack Seal, or Rubbilize and Overlay				
	7	0.5 % Full-Depth PCC patch				
	10	1% Full-Depth PCC patch, and Joint Seal				
	15	1.5% Full-Depth PCC patch				
Illinois <sup>(5)</sup>	20	Underseal, 4% Full-Depth PCC patch, Diamond Grind, Joint Seal				
	25	1.5% Full-Depth PCC patch				
	30	2.5% Full-Depth PCC patch				
	35	3.5% Full-Depth PCC patch				
	9	15% Crack Seal				
	17	15% Crack Seal				
	25	15% Crack Seal				
Indiana <sup>(5)</sup>	30	PCCP patch with 4" HMA Overlay				
	33	5% Crack Seal				
	36	5% Crack Seal				
	39	5% Crack Seal				
Kansas <sup>(5)</sup>	20	3% Patch with 3" Overlay				
Kansas	30	5% Patch with 4" Overlay				
Missouri <sup>(5)</sup>	25	1.5% Slab Replacement, and Diamond Grind				
Montana <sup>(5)</sup>	20	2% Slab Replacement, Diamond Grind, Joint Seal				
	10	Crack Seal				
. (5)	20	Crack Seal				
New Jersey <sup>(5)</sup>	30	5% Slab Replacement, Diamond Grind, and Crack Seal				
	40	30% Slab Replacement, 4" HMA Overlay				
	8	Joint Seal				
N N (6)	15	Full-Depth Slab Replacement, Spall Repair, Joint Seal				
New York <sup>(6)</sup>	23	Joint Seal				
	30	3" HMA Overlay				
<b>a</b> (5)	22	4% Full-Depth Repair of driving lanes, Diamond Grind				
Ohio <sup>(5)</sup>	32	2% Full-Depth Repar of driving lanes, and 3.25" HMA Overlay				
South Carolina <sup>(5)</sup>	20	Full-Depth Patching, Diamond Grinding, Joint Seal				
	10	3% Full-Depth Repair, Joint Seal				
Virginia <sup>(7)</sup>	20	10% Patching, Diamond Grind, Joint Seal				
<del>-</del>	30	10% Patching, HMA Overlay				
Washington <sup>(5)</sup>	20-30					
Wyoming <sup>(5)</sup>	20	4% Slab Replacement, Diamond Grind travel lane, Joint Seal				

#### References

- 1. Life Cycle Cost Analysis in Pavement Design, U.S. Department of Transportation Office of Asset Management, September 1998.
- 2. The 2009 Colorado Department of Transportation Pavement Design Manual, Chapter 10, Pavement Selection.
- 3. Life Cycle Cost Analysis Primer, U.S. Department of Transportation Office of Asset Management, August 2002.
- 4. Life Cycle Cost Analysis and Discount Rate on Pavements for the Colorado Department of Transportation, October 2006.
- 5. <<u>http://www.transportation.org/sites/research/docs/LCCA%20Replies.xls</u>> (14 January 2009).
- 6. New York Department of Transportation, "Comprehensive Pavement Design Manual Part 3: Life Cycle Cost Analysis". June 2001. <<u>https://www.nysdot.gov/divisions/engineering/design/dqab/cpdm/repository</u>/ <u>/chapter5app5a2.pdf</u>>. (14 January 2009).
- 7. Virginia Department of Transportation, Materials Division. "Life Cycle Cost Analysis". May 2002. <<u>http://www.virginiadot.org/business/resources/bu-</u><u>mat-pde-LCCADocMay02.pdf</u>>. (14 January 2009).