

Report No. CDOT-DTD-R-2001-6

Results and Recommendations of Forensic Investigation of Three Full-Scale GRS Abutment and Piers in Denver, Colorado

Naser Abu-Hejleh

Jorge G. Zornberg

William (Skip) Outcalt

Mike McMullen



June 2001

**COLORADO DEPARTMENT OF TRANSPORTATION
RESEARCH BRANCH**

The contents of this report reflect the views of the authors, who are responsible for the facts and accuracy of the data presented herein. The contents do not necessarily reflect the official views of the Colorado Department of Transportation or the Federal Highway Administration. This report does not constitute a standard, specification, or regulation.

Technical Report Documentation Page

1. Report No. CDOT-DTD-R-2001-6	2. Government Accession No.	3. Recipient's Catalog No.	
4. Title and Subtitle Results and Recommendations of Forensic Investigation of Three Full-Scale GRS Abutment and Piers in Denver, Colorado		5. Report Date June, 2001	
7. Author(s) Naser Abu-Hejleh, Jorge G. Zornberg, William (Skip) Outcalt, and Mike McMullen		6. Performing Organization Code 1. Performing Organization Report No. CDOT-DTD-R-2001-6	
9. Performing Organization Name and Address Colorado Department of Transportation 4201 E. Arkansas Ave Denver, Colorado 80222		10. Work Unit No. (TRAVIS)	
1. Sponsoring Agency Name and Address Colorado Department of Transportation 4201 E. Arkansas Ave Denver, Colorado 80222		11. Contract or Grant No.	
15. Supplementary Note		13. Type of Report and Period Covered	
16. Abstract In 1996, a full-scale geotextile-reinforced soil bridge abutment and two bridge piers with block facing were constructed in the Havana Maintenance Yard in Denver, Colorado. The abutment and outer GRS pier were load tested to demonstrate that GRS abutments and piers with block facing are viable alternatives to conventional bridge piers and abutments. Four to six months after the surcharge load was placed, excessive movements of the top several layers of the outer pier structure and severe cracking of the block facing were noticed. The toppling failure of the upper four block layers of the outer pier was deemed imminent and, consequently, the structures were dismantled. This report summarizes the measured in-situ conditions and characteristics of the structures materials (backfill, blocks, and geotextile fabric) after almost three years of being in place and identifies potentially relevant causes for the excessive deformation and cracking of the outer pier structure. Results of 27 out of 28 soil density tests indicate the backfill compaction level for The Havana GRS structures was below standard specifications (the average measured relative compaction was 88.3%). Also, relative compaction was variable (ranging 74% to 97%) and particularly low (88. 3%), especially close to the facing (average of 86.6%). Results of 128 wide-width tensile tests, conducted on geotextile sheets, indicated only a small loss of geotextile tensile strength (5.3%), which was attributed primarily to construction damage. Construction damage contributes to geosynthetic material deterioration and should be minimized. The block facing of the outer pier showed heavy external and internal damage in the middle zone. The facing experienced its largest movements in the upper four block layers, which decreased with the depth to become negligible in the bottom layers. The excessive deformations in the upper zone of the pier were evidence of a bearing capacity problem. Both the results of forensic investigation and simplified facing connection stability analysis indicate that layers 25 to 38 of the outer pier failed in meeting the serviceability block-to-block connection requirements. Potential reasons for the observed excessive deformation and cracking of the Havana outer pier are: high surcharge load applied to a limited surface area of a slender pier, low and variable backfill compaction level, low facing connection strength and reinforcement pullout resistance in the upper zone of the pier, weak blocks, and seasonal changes of temperature and moisture.		14. Sponsoring Agency Code	
Implementation GRS abutments and piers, constructed using closely spaced and high-strength geosynthetic reinforcements, well-compacted quality granular backfill, and strong blocks are viable alternatives to conventional bridge piers and abutments. Durability and creep of reinforcements were not identified as a problem for this system. Although design and construction of GRS abutment in highway projects have been successfully implemented by CDOT, research is still needed to develop rational design and construction guidelines for GRS piers. Design limitations and construction details for GRS piers are identified based on the findings from this study and recent published literature.		18. Distribution Statement	
17. Key Words abutments, geotextiles, geosynthetics, walls, compaction, forensic, durability, connection, blocks	19. Security Classif. (of this report)		
20. Security Classif. (of this page)	21. No. of Pages 84	22. Price	

CONVERSION TABLE
U. S. Customary System to SI to U. S. Customary System
(multipliers are approximate)

Multiply (symbol)	by	To Get Multiply (symbol)	by	To Get
----------------------	----	-----------------------------	----	--------

LENGTH

Inches (in)	25.4	millimeters (mm)	mm	0.039 in
Feet (ft)	0.305	meters (m)	m	3.28 ft
yards (yd)	10.914	meters (m)	m	1.09 yd
miles (mi)	1.61	kilometers (km)	m	0.621 mi

AREA

square inches (in ²)	645.2	square millimeters (mm ²)	mm ²	0.0016 in ²
square feet (ft ²)	0.093	square meters (m ²)	m ²	10.764 ft ²
square yards (yd ²)	0.836	square meters (m ²)	m ²	1.195 yd ²
acres (ac)	0.405	hectares (ha)	ha	2.47 ac
square miles (mi ²)	2.59	square kilometers (km ²)	km ²	0.386 mi ²

VOLUME

fluid ounces (fl oz)	29.57	milliliters (ml)	ml	0.034 fl oz
gallons (gal)	3.785	liters (l)	l	0.264 gal
cubic feet (ft ³)	0.028	cubic meters (m ³)	m ³	35.71 ft ³
cubic yards (yd ³)	0.765	cubic meters (m ³)	m ³	1.307 yd ³

MASS

ounces (oz)	28.35	grams (g)	g	0.035 oz
pounds (lb)	0.454	kilograms (kg)	kg	2.202 lb
short tons (T)	0.907	megagrams (Mg)	Mg	1.103 T

TEMPERATURE (EXACT)

Fahrenheit (°F)	5(F-32)/9	Celsius (° C)	° C	1.8C+32	° F
	(F-32)/1.8				

ILLUMINATION

foot candles (fc)	10.76	lux (lx)	lx	0.0929 fc
foot-Lamberts (fl)	3.426	candela/m (cd/m)	cd/m	0.2919 fl

FORCE AND PRESSURE OR STRESS

poundforce (lbf)	4.45	newtons (N)	N	.225 lbf
poundforce (psi)	6.89	kilopascals (kPa)	kPa	.0145 psi

RESULTS AND RECOMMENDATIONS OF FORENSIC INVESTIGATION OF
THREE FULL-SCALE GRS ABUTMENT AND PIERS
IN DENVER, COLORADO

by

Naser Abu-Hejleh
Jorge G. Zornberg
William (Skip) Outcalt
Mike McMullen

Report No. CDOT-DTD-R-2001-5

Prepared by
Colorado Department of Transportation
Research Branch

Sponsored by the
Colorado Department of Transportation
in Cooperation with the
U.S. Department of Transportation
Federal Highway Administration

June 2001

Colorado Department of Transportation
Research Branch
4201 E. Arkansas Ave.
Denver, CO 80222
(303) 757-9506

ACKNOWLEDGEMENTS

The authors wish to acknowledge valuable input and comments provided by the study panel members, Rich Griffin, Dr. Trevor Wang, and Dr. Hsing Cheng Liu. Thanks are also extended to Advanced Terra Testing, Inc. for performing the wide-width tensile tests on the geotextile specimens, and to CDOT Maintenance crews for their significant role during dismantling of the Havana Yard Structures.

EXECUTIVE SUMMARY

In 1996, a full-scale geotextile reinforced soil (GRS) bridge abutment and two bridge piers (center and outer) with block facing were constructed at the Havana Maintenance Yard in Denver, Colorado (Photos 1 through 5 of Appendix A and Figure 1). A surcharge load of 2340 kN was applied to the abutment and outer pier (not to the center pier). The objective, as with the Turner-Fairbank full-scale GRS pier, was to demonstrate that GRS abutments and piers with block facing were viable alternatives to conventional bridge piers and abutments. The performance of the GRS abutment and piers was good during load testing (November 1996 to October 1997). However, sometime between March and May of 1997 (4 to 5 months after the surcharge load was placed), excessive movements of the top several layers of the outer pier structure and severe cracking of the block facing were noticed, as depicted in Photos 5 to 7 of Appendix A. Toppling failure of the upper four block layers of the outer pier was deemed imminent. Therefore, it was decided to remove the applied surcharge load, tear down the structures, and perform a forensic investigation and facing connection stability analysis. This report summarizes the in-situ conditions and characteristics of the materials (backfill soil, facing blocks, and geotextile reinforcement) after almost three years of being in place and identifies potentially relevant causes for the excessive deformation and cracking experienced by the outer pier structure.

Results of 27 out of 28 soil density tests indicate the backfill compaction level for the Havana Yard GRS Structures was below standard specifications (the average measured relative compaction was 88.3%). Also, relative compaction was variable (ranging from 74% to 97%) and particularly low (88.3% in average), especially close to the facing (86.6%), not meeting CDOT requirements of 95% of the maximum dry unit weight measured in accordance with AASHTO T-180 method. Results of 128 wide-width tensile tests, conducted on 1 pristine and 15 exhumed geotextile sheets, indicated only a small loss of geotextile tensile strength (5.3%). This was attributed primarily to construction damage. Negligible loss in tensile strength was attributed to geotextile degradation and in-situ stresses. Creep of geosynthetic reinforcements was not identified as a problem. The block facing of the outer pier experienced significant external and internal damage in the middle zone, and experienced its largest movements in the upper four block layers. Movements decreased with the depth to become negligible in the bottom layers.

The excessive deformations in the upper zone of the pier were evidence of a bearing capacity problem. Both the results of forensic investigation and facing connection stability analysis indicate that layers 25 to 38 of the outer pier failed in meeting the serviceability block-to-block connection requirements (i.e., relative displacement between block layers was larger than 4 mm). Potential reasons for the excessive deformation and cracking of the Havana outer pier are: high surcharge load applied to a limited surface area of a slender pier, low and variable backfill compaction level, low facing connection strength and reinforcement pullout resistance in the upper zone of the pier, weak blocks, and seasonal changes of temperature and moisture. The comparatively low backfill compaction level led to increased lateral earth pressure loads and to decreased strength and stiffness of the reinforced soil mass. The construction of the pier during the cold season may have delayed the excessive movement and cracking of the pier facing. The delay in the development of structure movements, which appeared several months after loading during the 1997 spring season, was attributed to softening of the backfill that may have resulted from low backfill compaction and soil wetting due to rain and ice melting.

Implementation Statement

GRS abutment and piers are viable alternatives to conventional methods used in bridge support. Details for construction of GRS abutments and piers are available in several references (Elias and Christopher, 1997; FHWA, 2000; and Abu-Hejleh et al., 2000 and 2001). Design and construction of GRS abutments in highway projects have been successfully implemented and monitoring results have shown excellent field performance. However, research is still needed to develop rational design and construction guidelines for GRS piers and appropriate limitations (e.g., base to height ratio). Consequently, future field implementation of GRS piers should still be considered experimental and such structures should be carefully monitored. Limitations and additional details for construction of GRS piers (and, if appropriate, other GRS structures) learned from this study and from recently published literature (FHWA, 2000; Adams, 1997) are furnished in this report. They are:

- The use of GRS piers is well-suited for remote locations, where specialized equipment or concrete is unavailable or cannot be reached. The materials used to construct the pier are commonly available. In emergency situations, a GRS pier can be constructed using small

construction equipment and put into service within a few days. The use of GRS piers may be beneficial for temporary bridge structures, and bike or pedestrian bridges. Also, GRS piers should be considered for aesthetic purposes when a massive look is needed. Although there are many benefits from this modern approach to bridge pier design, it should not be used in a scour environment, when it would not prove economical, or when loads are excessive. CDOT engineers believe that the use of GRS piers may not be economical for many typical highway practices when compared to the use of concrete piers.

- ❑ Closely spaced (0.2 m to 0.3 m), high-strength geosynthetic reinforcements and well-compacted quality granular backfill form a strong composite reinforced soil mass. Based on the limited results of full-scale GRS piers and recommendations provided in the literature, design surcharge pressures ranging from 100 to 150 kPa are recommended for comparatively large and slender GRS piers (e.g., having base width/height ratio of 0.7 – the Turner-Fairbank structure to 0.33 – the Havana Yard Structure). Under these surcharge pressures, creep and durability of geosynthetic materials have not been a problem in monitored full-scale structures. Construction damage of the geosynthetic is not considered a problem in GRS piers because fill material can be spread by manual labor (an approximately 5% reduction in tensile strength from damage was measured in this study). For construction of GRS structures using heavy equipment, construction damage may contribute to reduction in geosynthetic tensile strength and should be minimized.

- ❑ Requirements for compaction of coarse-grained backfill should be enforced and well controlled in the field. To achieve proper backfill compaction at the optimal moisture content within the limited area of the pier, numerous compaction passes with light equipment should be performed. For GRS piers, a backfill soil with a friction angle of at least 40 degrees is highly recommended. If feasible, a maximum size crushed stone of 19 mm should be used for a minimum distance of 0.3 m behind the facing blocks in order to facilitate fill compaction behind blocks, provide internal drainage, and prevent migration of fines to the wall facing. Alternatively, wrapping of geotextile behind the face could be implemented for erosion control purposes.

- ❑ In the top 1.6 m of piers loaded with a high surcharge load, it is recommended to: 1) place reinforcements with a wrapped-around procedure behind the facing, and 2) employ mechanical connection between blocks and between blocks and reinforcements. Results of this research and other studies suggest that the friction-based facing connection strength in the lower zone of the pier is adequate.
- ❑ Consider measures and details to achieve a uniform distribution of surcharge load over the entire pier surface area (e.g., use of flow fill in the top zone), or a trapezoidal distribution where the highest pressure would occur at the center of the structure (e.g., plastic hinge joint at the center of the concrete pad).
- ❑ Include measures to enhance the pullout resistance of reinforcements in the top layers near to the sides of the pier (e.g., wrap reinforcements around heavy items, drive bars through reinforcement into the backfill).
- ❑ Construction of the GRS structures during drier and warmer seasons is preferred. At least, backfill temperature during construction should be maintained above freezing.
- ❑ Implement measures to prevent surface water run-off and ground water intrusion into the reinforced soil mass.
- ❑ Use high quality, strong blocks meeting CDOT specifications.

TABLE OF CONTENTS

1.0	INTRODUCTION	1
1.1	Background	1
1.2	Problem Statement and Study Objectives.....	2
1.3	Content of the Report.....	3
2.0	IN –SITU CONDITIONS AND CHARACTERISTICS OF THE BACKFILL MATERIALS	5
2.1	Backfill Material Characterization.....	5
2.2	General Observations	5
2.3	In-situ Backfill Compaction Level.....	6
3.0	IN-SITU CONDITIONS AND DURABILITY OF BURIED GEOTEXTILES	9
3.1	Overview.....	9
3.2	Specimen Retrieval and Preparation.....	9
3.3	Testing Procedure (Wide-Width Tensile Test, ASTM D 4595).....	10
3.4	Testing Results.....	11
3.5	Discussion of the Results	13
4.0	IN-SITU CONDITIONS AND CHARACTERISTICS OF THE BLOCK FACING	15
4.1	East Abutment Structure	15
4.2	Center Pier Structure.....	15
4.3	Outer Pier Structure	16
4.3.1	External Conditions of the East Face of the Outer Pier Structure	16
4.3.2	Internal Conditions of the Facing of the Outer Pier Structure	17
4.3.3	Summary of the Movement and Damage Results for the Outer Pier	17
5.0	STABILITY INVESTIGATION OF THE OUTER PIER STRUCTURE.....	31
5.1	Influence of Backfill Compaction Level.....	31
5.2	Serviceability Block-to-Block Connection Stability Analyses.....	31
5.2.1	Background	31
5.2.2	Analysis Results and Discussion.....	32
5.3	High Surcharge Load.....	33
5.4	Influence of Seasonal Changes of Temperature and Moisture	34
5.5	Comparison between the Turner-Fairbank and the Havana Yard Piers	34

6.0	SUMMARY.....	39
6.1	Overview.....	39
6.2	Fulfilling 1 st Study Objective.....	39
6.2.1	Backfill.....	39
6.2.2	Geotextiles.....	40
6.2.3	Block Facing.....	40
6.3	Fulfilling 2 nd Study Objective.....	41
7.0	RECOMMENDATIONS.....	45
	REFERENCES.....	48
	APPENDIX A.....	51
	Photographs taken before and during dismantling of structures and during testing of geotextile sheets.	

LIST OF FIGURES

Figure 1 Side and Top Views of the Havana Yard Large Scale GRS Structures (from Ketchart and Wu, 1997)	4
Figure 2 Schematic Diagram of Specimen Sampling Plan for the Center Pier Geotextile Sheets	10
Figure 3 Typical Block from East Abutment Structure (133 to 182 N or 30 to 41 lb. in weight)	19
Figure 4 Block from Center Pier Structure (324 N or 73 lb. in weight)	20
Figure 5 Block from Outer Pier Structure (258 N or 58 lb. in weight)	21
Figure 6 Density of Cracking along the East Face of the Outer Pier	22
Figure 7 Density of Opened Joints along the East Face of the Outer Pier Indicating Movement Parallel to the Facing	23
Figure 8 Targeted and Current Vertical Profiles of the East Facing of the Outer Pier	24
Figure 9 Outward Displacement of the East Face of the Outer Pier Induced During and After Construction.....	25
Figure 10 Measured and Maximum Recommended Relative Outward Displacements between Block Layers	26
Figure 11 Mapping Results for the Blocks' Breaks in the Upper Zone of the Outer Pier (Note: Marks indicate the broken sides, not location of the breaks)	27
Figure 12 Mapping Results for the Blocks Breaks in the Middle Zone of the Outer Pier	28
Figure 13 Mapping Results for the Blocks Breaks in the Middle Zone of the Outer Pier	29
Figure 14 Effect of Relative Soil Density on the Soil Friction Angle, $\tan f$, for Coarse-Grained Soils (USBR, 1998)	36

LIST OF TABLES

Table 1 Measured Material Characteristics of the Havana Yard Structures Backfill.....	5
Table 2 Moisture, Density, and Compaction Level of the Havana Yard Structures' Backfill Results Measured during Dismantling Operations	7
Table 3 Wide Width Tensile Test Results on Sheet W28	12
Table 4 Results of Wide Width Tensile Strength Tests on Pristine and Exhumed Geotextile Sheets	12

Table 5 Results of Serviceability Block-to-Block Connection Stability Analyses37

1.0 INTRODUCTION

1.1 Background

The technology of geosynthetic-reinforced soil (GRS) systems has been used extensively in transportation systems to support the self-weight of the backfill soil, roadway structures, and traffic loads. A comparatively new use of this technology is the use of GRS systems as an integral structural component of bridge abutments and piers. Use of a reinforced soil system to directly support both the bridge (e.g., using a shallow foundation) and the approaching roadway structure has the potential of significantly reducing construction costs, decreasing construction time and space, and smoothing the ride for vehicular traffic. From 1996 to 1999, two full-scale GRS structures and two production GRS abutments were constructed to demonstrate that GRS abutments and piers with block facings were viable alternatives to conventional bridge piers and abutments and metallic reinforced piers and abutments.

A full-scale instrumented fabric-reinforced pier was constructed and load tested at the Turner-Fairbank Highway Research Center in 1996. The pier was 5.4 m high and its base was 3.6 m x 4.8 m. The method of construction utilizes closely spaced high-strength geosynthetic reinforcement and quality compacted road base. The pier sustained a vertical surcharge that was equivalent to a pressure of 900 kPa. The Turner-Fairbank GRS pier showed excellent performance at 200 kPa and a superficial problem of cracks in the facing system became notable at pressures greater than 275 kPa. The results indicated this GRS pier was suitable for bridge support and should be considered for use on an experimental field project (Adams, 1997; FHWA, 2000).

To continue the Turner-Fairbank experiment, a geosynthetic-reinforced soil (GRS) abutment and two GRS bridge piers (called center and outer piers) were constructed inside a 3.5-m deep pit in the Havana Maintenance Yard in Denver, Colorado (see Photos 1 through 5 in Appendix A and Figure 1). A complete description of the structures and measured performance were summarized by Ketchart and Wu (1997). Side and top views showing the configuration of these structures are shown in Figure 1. The structures were constructed with a roadbase backfill reinforced with layers of a woven polypropylene geotextile. Dry-stacked hollow-core concrete blocks were used

as facing. The outer pier and the abutment structure, both 7.6 m in height, were load tested (the center pier was not tested, see Photo 1 of Appendix A). The load was applied using concrete barrier stacked in seven layers over three steel bridge girders (Figure 1). The load was transmitted from the girders to the backfill through concrete pads placed on top of the structures (Figure 1). A total load of 2340 kN (1170 kN on the pier and 1170 kN on the abutment) was applied. The pier and abutment structures were instrumented to monitor the lateral and vertical movements of the facing and deformation of the reinforcements. The performance of the loaded large-scale abutment structure over a year was excellent. The measured immediate maximum vertical displacement and lateral displacement (defined as elongation of the perimeter of the abutment) were, respectively, 27.1 mm and 14.3 mm. The maximum vertical and lateral creep displacements under a sustained load during 70 days were 18.3 mm and 14.3 mm, respectively. Almost 70% of the creep displacement occurred in the first 15 days. The maximum strains in the reinforcements were less than 1.0%, which was smaller than the reinforcement rupture strain of 18 %.

The excellent performance of the full-scale GRS abutment in the Havana Yard and the Turner-Fairbank GRS pier cleared the way for Colorado engineers to select GRS walls to support the bridge abutment shallow footings of the Founders/Meadows Structure (Abu-Hejleh et al. 2000, and 2001) and Black Hawk Structure (FHWA, 2000).

1.2 Problem Statement and Study Objectives

Application of the surcharge load on the Havana Yard abutment and outer pier (Photo 1 of Appendix A) was completed on 11/1/1996. Some time between March and May of 1997, excessive movements of the top several layers of the outer pier structure and severe cracking of the facing were noticed as depicted in Photos 5 to 7 of Appendix A. Toppling failure of the upper four rows of the outer pier was felt to be imminent. Therefore, on October 30, 1997, the barriers and girders were removed to preclude the collapse of the entire structure assembly. From November 1997 to October 1999, all three unloaded structures (abutment, center and outer piers) were not monitored but there were no signs of additional movements. In October of 1999, it was decided to tear down the three structures and conduct forensic and stability investigations to achieve two objectives:

1. Determine the in-situ conditions and characteristics of the materials (backfill, blocks, and geotextile), after almost three years in place (from October 1996 to October 1999).
2. Determine potential causes of the excessive deformation and cracking of the outer pier structure.

Dismantling of the three structures was conducted in stages, by hand, to enable careful examination of the undisturbed in-situ condition and testing of backfill, geotextiles, and block materials at different depths inside the three structures.

1.3 Content of the Report

The study recommendations and implementation statement were presented previously in the executive summary. Chapter 2 presents and discusses the in-situ conditions and characteristics of the backfill material including measured compaction levels at different locations (center and edge) and depths inside the three structures. Results on the exhumed strength of geotextile sheets from the center and outer GRS pier structures after being buried for three years are presented and discussed in Chapter 3. Results of in-situ conditions and characteristics of block facing are discussed in Chapter 4. The emphasis in Chapter 4 is on mapping the movement, external cracking, and internal breaking of the east face of the outer pier. Probable causes for the excessive movement of the outer pier structure, including results of simplified facing connection stability analysis, are compiled in Chapter 5. A comprehensive summary of the study findings is given in Chapter 6. Appendix A lists photos taken before and after dismantling the large-scale structures and during testing of the geotextile sheets.




Fig. 1 Side view of the structures




Fig. 2 Top view of the structures

Figure 1 Side and Top Views of the Havana Yard Large Scale GRS Structures (from Ketchart and Wu, 1997)

2.0 IN –SITU CONDITIONS AND CHARACTERISTICS OF THE BACKFILL MATERIALS

2.1 Backfill Material Characterization

The measured backfill gradation, liquid limit, and plasticity index for a backfill sample collected from the outer pier structure are shown in Table 1. As shown in this table, the backfill soil used in this project was a mixture of gravel (39.7%), sand (46.7%) and fine-grained soil (13.6%). The backfill material was classified as A-1-A(0) according to AASHTO. The backfill meets the material specifications of CDOT Class-1 backfill material (Table 1).

Table 1 Measured Material Characteristics of the Havana Yard Structures Backfill

	Requirements for CDOT Class-1 Backfill	Measured Values
Gradation		
50 mm, (% Passing)	100	100
Sieve # 4 ((% Passing)	30-100	60.3
Sieve # 50 (% Passing)	10-60	25.1
Sieve # 200 (% Passing)	5-20	13.6
2. Liquid Limit (%)	<35	22.2
3. Plasticity Index (%)	<6	6

2.2 General Observations

During dismantling operations, the fill in some of the layers was easily cut with a shovel, while in other lifts a pick was needed to break the material up before it could be removed. The softer layers could be identified visually. The softer layers were too dry during construction. Considerable amounts of larger aggregates were visible on top of the layer. The well-compacted layers had been constructed with more moisture – there were more fines on the top of the fill layer. The blocks and the voids between and behind the m were filled with uniform sized gravel (approximately ¼” in size). Some of the gravel was obtained from the salt treated road-sand pile at the maintenance yard. Some salt, which built up on the fabric at the back of the blocks, was noticed. Deterioration of blocks may have increased with the presence of this salt.

After removal of the concrete pad from the top of the outer pier and during stage removal of the upper three rows, it was noticed that the soil below the concrete pad settled more than the rest of the pier area. The low and variable compaction over the pier area caused the uneven settlement and most likely caused the non-uniform distribution of vertical surcharge load over the entire surface area of the pier.

2.3 In-situ Backfill Compaction Level

For the backfill material employed in the Havana Yard Structures, the maximum backfill dry unit weight and optimum moisture content were 21.1 kN/m³ and 6.4%, respectively as measured in accordance with AASHTO T-180 Method A using 40% gravel. To have a satisfactory performance for reinforced earth structures, CDOT construction specifications for Class-1 backfill material requires a compaction level exceeding 95% of the maximum dry unit weight measured in accordance with AASHTO T-180 method. Twenty-eight field tests were conducted during dismantling operations to measure the backfill moisture content, density and compaction level at the center and edges for different depths inside the three structures (Table 2). Note that the edge measurement was taken 1 foot from the facing.

It is clear from Table 2 that the backfill compaction requirements for all structures at all levels and locations (except the center of row 35) were not met. Note also that the initial backfill density before application of the surcharge load could even be less than the measured value after the surcharge load had been applied. According to the CDOT crew who constructed the Havana Yard Structures, the low compaction level was due to the lack of control of moisture and density during construction. If the fill material was dry the construction crew added water randomly during the compaction, but no moisture content tests or compaction density tests were done. The lack of quality control also explains the variation of compaction level throughout the structure depth (Table 2). The crew who constructed the structures indicated the fill was compacted using small, walk behind, vibrating compactors. Also, compaction was likely to be less than desirable due to the small surface area of the pier and the “fear-of-height factor” at the top layers. It is also clear from Table 2 that the backfill close to the facing received less compactive effort than the backfill at the center of the structure. Note that the backfill adjacent to the facing was even looser

than what was measured 1 foot from the facing. To keep from deforming the block facing, the construction crew did not use the vibrating compactors less than about 1 foot from the back of the blocks. The fill in that area was compacted by foot pressure.

Table 2 Moisture, Density, and Compaction Level of the Havana Yard Structures' Backfill Results Measured during Dismantling Operations

Row #	Center of Structure			Edge of the Structure		
	Moisture (%)	Dry Unit Wt. (kN/m ³)	Relative Compaction (%)	Moisture (%)	Dry Unit Wt. (kN/m ³)	Relative Compaction (%)
Outer Pier Structure						
38	3.0	19.6	92.2	3.4	18.7	88.1
35	5.4	20.9	97.9	5.3	19.6	92.0
32	4.3	20.2	94.8	4.3	19.7	92.8
22	5.7	19.7	92.4	7.3	18.4	86.5
13	1.9	19.6	92.2	2.3	19.1	89.7
2	4.4	18.9	89.1	4.2	19.3	90.1
Center Pier Structure						
39	5.1	19.5	91.9	5.3	18.6	87.7
30	2.2	18.7	88.4	3.3	18.8	88.7
20	3.3	16.4	77.1	3.0	15.7	74.1
2	3.5	19.9	93.4	3.2	18.9	88.9
East Abutment Structure						
38	4.7	18.7	87.9	5.2	18.3	85.9
28	3.5	19.0	89.5	3.5	18.7	87.8
18	1.8	19.8	92.6	1.7	18.3	86.3
3	3.4	16.9	79.5	2.6	15.7	73.8

3.0 IN-SITU CONDITIONS AND DURABILITY OF BURIED GEOTEXTILES

3.1 Overview

The reinforcement buried in the Havana Yard Structures for approximately three years was a woven polypropylene geotextile designated as Amoco 2044 (Photos 11 and 13 of Appendix A). The reinforcements were placed with the same orientation in all three structures. The geotextile cross-machine (or fill) direction was along the short length of the structure (where geotextile was subjected to relatively higher stresses), and machine direction (roll or warp direction) was along the longer length of the structure (see Photo 2 and 1.1). The survivability and durability of the exhumed geotextiles were evaluated by comparing the wide-width tensile strength of the exhumed samples with the strength of a pristine geotextile sample. The loss of geotextile strength of exhumed samples was attributed to stresses due to backfill weight and surcharge load, aging over three years, and construction damage. One hundred twenty-eight wide-width tensile tests were performed.

3.2 Specimen Retrieval and Preparation

Geotextile sheets were retrieved from the center pier (9 sheets) and outer pier (6 sheets) structures during dismantling operations. On the layers where exhumed geotextile layers were collected, the fill material was removed with extra caution to prevent damage to the geotextile. The conditions of all retrieved geotextile sheets were excellent showing no signs of geotextile distress (e.g., tears or cuts). To identify the location of the exhumed sheets, each exhumed layer was marked with a letter (C= center pier, and W= outer pier), and a number indicating the row number at which the geotextile sheet was placed. Note that row #1 refers to the bottom row. A pristine geotextile sheet from the same lot of sheets used in the Havana Yard Structures was not available. Therefore, a pristine (undamaged) geotextile sheet designated as Amoco 2044 was obtained from the lab at the University of Colorado at Denver in November of 1999.

Each geotextile sheet was laid out as shown in the schematic diagram given in Figure 2. The dimensions of each sheet changed with its location in the structure since the structures were tapered from bottom to top (see Figure 1 for dimensions at top and bottom). Seven cross machine

direction (CMD) specimens and one machine direction (MD) specimen (# 8 in Figure 2) were sampled from each sheet (see Figure 2). Approximate location of these specimens is shown in Figure 2. Three center CMD specimens (1, 2, 3), and two CMD specimens (4, 5, 6, 7) on each side were collected, spaced along each line approximately 1.5 to 2 meters apart (Figure 2). One MD specimen was collected (#8) close to the corner edges (Figure 2). To ensure structural integrity, specimens were taken by cutting each specimen 216 mm wide, and removing an equal number of yarns from each side to obtain an 203 x 203 mm test specimens (Photo 14 in Appendix A). Specimens were then placed in the standard atmosphere (50% relative humidity, 70° F laboratory temperature) for a period of 24 hours to insure temperature and moisture equilibrium. One hundred twenty-eight specimens, (8 from each sheet), were prepared for the wide-width tensile tests.




Figure 2 Schematic Diagram of Specimen Sampling Plan for the Center Pier Geotextile Sheets

3.3 Testing Procedure (Wide-Width Tensile Test, ASTM D 4595)

The distance of clamp separation was adjusted to approximately 203 mm (Photo 15). The top jaw was supported by a free swivel, which allowed the jaw to rotate in the plane of the geotextile. The 203 mm wide by 203 mm long specimens were then mounted centrally and positioned adjacent to the inside edges of the upper and lower jaws. The specimens were placed in the grips

to test the middle 102 mm without regard to specimen damage. A small seating load was applied to each specimen to remove any slack in the jaws and geotextile (Photo 15). The recorder was then zeroed with the pre-load applied, and the tensile testing machine was then started at a constant rate of 10.2 mm (10% strain rate) per minute. Tests were continued until rupture, at which point the tensile machine was stopped and reset to the initial gage position (Photo 16).

3.4 Testing Results

Typical observed responses during testing of sheets W17 and C20 (8 specimens of each sheet) are shown in Photo 17. It was noted that at a point of rupture, the majority of the specimens tended to break violently on one side or the other, resulting in a single peak graph (see Photo 17). In a few instances, rupture initiated near the center of the specimen and radiated outward, resulting in a dual peak graph, and somewhat lower ultimate loads. Typical results in terms of the ultimate strength and strain at break on the 8 specimens of sheet W28 are shown in Table 4. It is clear from Photo 17 and Table 3 that the test results for the 7 CMD specimens were very close with minor variations. The low standard deviation and coefficient of variation of the results of 7 CMD specimens (Table 3) was noticed for specimens of all tested geotextile sheets. Therefore, the results of 7 CMD specimens for each sheet are presented in terms of the average ultimate strength and strain at break as listed in Table 42. Note that the strength results for each structure in Table 42 are listed in order starting from the sheets located in the top. The average geotextile strength and strain at break for each structure (center and outer pier structures) obtained from all sheets and specimens are also listed in Table 42.

Table 3 Wide Width Tensile Test Results on Sheet W28

Specimen #	Ultimate Tensile Strength (kN/m)	Strain at Break (%)
Machine Direction (MD) Specimen		
8	71.4	17.9
Cross Machine Direction (CMD) specimens		
1	86.1	16.8
2	86.9	15.8
3	87.6	15.6
4	85.9	15.6
5	90.1	15.9
6	86.5	15.4
7	85.4	15.8
<i>Average</i>	86.9	15.8
Std. Dev.	1.6	0.45
Coefficient of Variation	1.8 %	2.84

Table 4 Results of Wide Width Tensile Strength Tests on Pristine and Exhumed Geotextile Sheets

Sheet Identification	Ultimate Tensile Strength (kN/m) and Strain at Break (%)			
	7 CMD specimens for each sheet		1 MD specimen for each sheet	
	Average Strength	Average Strain	Strength	Strain
Pristine Fresh Geotextile Sheet				
	88.2	17.8	75.9	19.7
Center Structure				
C36	80.4	14.5	78.8	21.6
C35	86.4	15.9	79.2	19.4
C30	71.9	13.5	83.3	20.1
C25	76.9	15.1	78.7	19.4
C20	74	14.2	81.2	21.2
C15	86.7	16.4	72.3	18.3
C13	86.6	15.9	75.9	19.6
C10	83.6	16.1	71.3	18.3
C5	89.1	16.5	70.2	17.5
<i>Average</i>	81.7	15.3	76.8	19.5
Outer Pier Structure				
W28	86.9	15.8	71.4	17.9
W23	89.2	16.9	72.7	21.9
W17	85.4	16	84.1	24.1
W13	87.5	16.6	70.3	18.3
W8	86.5	16.5	75.6	18.8
W5	81.3	14.5	76.4	18.2
<i>Average</i>	86.1	16.1	75.1	19.8

3.5 Discussion of the Results

The strengths in the cross machine direction (CMD) and machine direction (MD) of the pristine (undamaged) geotextile sheet were determined as 88.2 kN/m and 75.9 kN/m, respectively (see Table 3). The results on all pristine and exhumed sheets suggest that geotextile strength in the machine direction was a little weaker than the cross-machine direction. The loss of geotextile strength of exhumed samples was attributed to stresses due to backfill weight and surcharge load, degradation over three years, and construction damage. To address the first factor, geotextile sheets were selected from different depths of two structures: the outer pier where heavy surcharge load was applied, and the center pier with no surcharge load. Seven CMD specimens at several locations of each sheet were tested (Tables 3.1 and 3.2). A careful examination of Table 42 indicates no correlation between the position (depth) of the exhumed geotextile sheet and its measured strength. Contrary to expectations, the average strength of the geotextiles sheets buried in the outer pier structure, where heavy surcharge load was applied (86.1 kN/m), was higher than in the geotextile sheets buried in the center structure (80.1 kN/m). In addition, the strength results for 7 CMD specimens of each sheet were very close, indicating that strength of the exhumed sheets was not related to the specimen location (i.e., center or close to the edges of the structure). Therefore, based on these findings, it was concluded that subjecting geotextiles to different stress levels from overlying materials and surcharge loading did not contribute to the geosynthetic deterioration and loss of strength.

The results on all geotextile sheets exhumed from the center and outer pier structures (Table 42) showed that exhumed strengths were lower by 0 to 18 percent than the pristine strength. The results suggest no strength loss in the machine direction (Table 42). The average CMD strength of 105 specimens was 83.5 kN/m. The average mean geotextile strength loss in the CMD was 5.3%. This loss in geotextile strength can be attributed to construction damage and degradation over three years. Many research studies concluded that durability and creep of closely spaced geosynthetic-reinforcements embedded in well-compacted granular backfill and subjected to a design pressure less than 200 kPa were not a problem (FHWA, 2000; Adams, 1997; Ketchart and Wu, 1997; Bell and Barrett, 1995; Powell and Mohny, 1994; Abu-Hejleh et al., 2001). Therefore, the small loss of geotextile strength (5.3%) for the Havana Yard Structures can be attributed primarily to construction damage. Bell and Barrett (1995) indicated an average mean

strength loss of 27 % for geotextiles buried in Glenwood Canyon GRS walls for up to 11 years. They attributed most of the loss to construction damage. Bell and Barrett (1994) reported large cuts and abraded areas in the exhumed geotextiles, which were not noticed in the geotextiles retrieved from the Havana Yard Structures. When compared to the construction method employed in Glenwood Canyon, the construction method employed in The Havana Yard Structures was relatively gentle because the fill was spread by manual labor (due to the small working size) and smaller compaction equipment was utilized. This all indicates that construction methods and techniques have a great impact on the level of geosynthetic degradation.

4.0 IN-SITU CONDITIONS AND CHARACTERISTICS OF THE BLOCK FACING

4.1 East Abutment Structure

The blocks for the abutment structure (Figure 3, Photo 2 Appendix A) were supplied by several manufacturers (Amoco Fabrics & Fibers, Best Block, Clalite, Retaining Wall Systems, and Valley Block). The blocks were standard blocks (0.2m x 0.2m x 0.4m), made of lightweight concrete in the basic two-cell shape (Figure 3). Their weights varied from 133 to 182 newtons (30 to 41 pounds). There were few cracks visible in the external face before the dismantling began (Photo 8). During dismantling, a fairly large percentage – as high as 50% – of the blocks in some layers was internally broken. Most of the blocks on west face of the abutment (the side where surcharge load on the abutment was applied, see Figure 1) were broken. Most of the blocks on the north, east, and south faces of the abutment were unbroken. Many of the blocks that were broken did not have visible cracks before dismantling of the structure. A block that had a crack that ran completely from the top to the bottom and half way through the center web is shown in Photo 12 (Appendix A). There did not seem to be any correlation between the layer location (depth) and the percentage of broken blocks.

4.2 Center Pier Structure

The concrete blocks from the center pier (Figure 4, Photo 4) were the heaviest of the three structures at 324 Newtons (72.7 pounds), supplied by one manufacturer and most likely made of normal weight concrete. The blocks' dimensions are shown in Figure 4. They had a raised lip along the outside face. The blocks were laid with the lip up, forcing a small setback in the next row. This setback resulted in a uniform positive batter at the face (Figure 1). The blocks of this structure were the only ones that had any type of connection from one layer to the next other than friction with the fabric. It was noticed that the top several rows of the center pier experienced outward bowing (Photo 4 of Appendix A), possibly due to negligence in controlling the facing alignment during construction. There were no visible cracks in the external face and no internal broken blocks were found during dismantling of the center pier.

4.3 Outer Pier Structure

The outer pier was constructed of “D” shaped blocks – 203 mm high by 445 mm long and 305 mm wide (Figure 5). The outside faces of the blocks were 70 mm thick, the sides were 43 mm thick, and the backs were 60 mm thick. The same manufacturer supplied the blocks and there was no significant variation in the weight. The blocks used in the outer pier weighed 258 newtons (58 pounds). These blocks seemed to be denser than those used in the east abutment, and were most likely made of normal weight concrete. Because of the tapered sides the blocks can be placed in a curve easily. The ends of the outer pier were curved that way (Photo 10).

Since the blocks of the outer pier structure were severely cracked and the upper four rows showed significant movements (see Photos 5, 6 and 7), the external and internal conditions of blocks were thoroughly examined. The results of this examination are presented in the following subsections.

4.3.1 *External Conditions of the East Face of the Outer Pier Structure*

The outer pier had 38 rows, numbered from 1 at the bottom to 38 at the top. Scaffolding was placed next to the east face of the outer pier structure enabling complete examination of the 3 m wide face. The numbers of fine cracks up to 1 mm in width and coarse cracks up to 5 mm in width in each row are shown in Figure 6. Cracks were typically aligned with joints in the layers above and below the cracked block (Photos 5, 6, and 7). When a block cracked, the crack would often follow the joints between blocks and cause other blocks to crack. The middle zone, between layer 11 and 34, was heavily cracked, the lower zone was cracked to a lesser degree, and no cracking was noticed in the upper 4 layers. The vertical joints opened up as the blocks moved in the direction perpendicular to the facing. The number of opened joints in each row is shown in Figure 7. The construction of the pier facing targeted a uniform positive batter of 5% from the vertical line (see Figures 1 and 8). It was assumed that each constructed row was placed with a setback of 10 mm (corresponding to a 5% positive batter) from the row below. The current facing out-of-vertical alignment shown in Figure 8 was determined from measurements of distances between the bottom edge of each row and the top edge of the row below. The targeted batter and current out-of-vertical alignments were employed to estimate the outward displacement of each block layer assuming that the leveling pad did not experience any outward

displacement (Figure 9). It is important to realize that the estimated facing outward displacements given in Figure 9 include displacements incurred during construction of the pier, application of the surcharge load, and the post-construction displacements. From the results in Figure 9, the displacements of each block layer relative to the layer below (referred to as relative displacement) were obtained (Figure 10). Figures 7, 9 and 10 indicate that most of the pier movements occurred in the upper two thirds of the pier, mostly in the upper four layers, and that the movement decreased with the depth from top of the pier.

4.3.2 Internal Conditions of the Facing of the Outer Pier Structure

No damage was noticed for the internal sides of the upper four block layers (rows 35 to 38), but all other layers had broken blocks. In rows 33 and 34, the blocks were broken into several pieces. As the dismantling progressed, it became apparent that many of the blocks that appeared from the outside to be whole were also broken. Typical mapping results for the blocks' breaks at different levels in the pier structure are shown in Figures 11, 12, and 13. Note that the marks indicate the broken sides, not exact location of the breaks. From layer 32 down to 30 all of the blocks were broken (~ 27 blocks per layer). In rows 29 through 27 there were only five unbroken blocks. On row 27, all blocks were broken, on row 26 there were two unbroken blocks, on row 25 there were 7 unbroken blocks, and on row 24 there were 5 unbroken blocks. For the entire pier, more blocks on the straight sides of a given layer were broken than in the curves at the ends of the layer (Figure 11 to 13). Most of the unbroken blocks were either on the curves or at the end of the straight sides of the pier (see Figures 11 to 13). From rows 32 to 24, there were almost no unbroken blocks in the straight part of the pier. It is also clear from the mapping results that the lower layers had more unbroken blocks. The breaks in all of the blocks were nearly vertical from the top to the bottom of the block; no intersection of one break with another was observed. Most broken blocks had at least two breaks. Most blocks had only one break per side and most breaks were near a corner, although multiple breaks in a side and breaks near the centers of the faces were found. While many of the blocks were broken in several places, none was shattered.

4.3.3 Summary of the Movement and Damage Results for the Outer Pier

Distinct responses were noticed for three zones of the outer pier (see Figures 6 to 13):

- Upper zone of block layers 35 to 38: No cracking to the external facing, or internal damage to the blocks was noticed in this zone. The upper four layers experienced excessive relative outward displacement between block layers and significant opening of vertical joints.
- Middle zone of block layers 11 to 34: This zone moved to a lesser degree than the upper zone but was the most heavily damaged and cracked. The relative displacements of block layers 25 through 34 were approximately 10 mm. On the average, smaller relative displacements were noticed for layers 11 to 25 (movement decreased with depth).
- Lower zone of block layers 1 to 10: In this zone, the intensity of block damage (cracking and breaks) diminished and the facing experienced negligible movement.




Figure 3 Typical Block from East Abutment Structure (133 to 182 N or 30 to 41 lb. in weight)




Figure 4 Block from Center Pier Structure (324 N or 73 lb. in weight)




Figure 5 Block from Outer Pier Structure (258 N or 58 lb. in weight)




Figure 6 Density of Cracking along the East Face of the Outer Pier




Figure 7 Density of Opened Joints along the East Face of the Outer Pier Indicating Movement Parallel to the Facing




Figure 8 Targeted and Current Vertical Profiles of the East Facing of the Outer Pier




Figure 9 Outward Displacement of the East Face of the Outer Pier Induced During and After Construction




Figure 10 Measured and Maximum Recommended Relative Outward Displacements between Block Layers




Figure 11 Mapping Results for the Blocks' Breaks in the Upper Zone of the Outer Pier
 (Note: Marks indicate the broken sides, not location of the breaks)




Figure 12 Mapping Results for the Blocks Breaks in the Middle Zone of the Outer Pier




Figure 13 Mapping Results for the Blocks Breaks in the Middle Zone of the Outer Pier

5.0 STABILITY INVESTIGATION OF THE OUTER PIER STRUCTURE

Causes for the excessive movements of the outer pier could be attributed to the combination of several factors that will be discussed in this chapter.

5.1 Influence of Backfill Compaction Level

It was concluded in the FHWA study (FHWA 2000) that good backfill compaction is essential to satisfactory performance of GRS structures. Figure 14 shows the relation between relative density and the angle of internal friction (also expressed as $\tan \phi$) for compacted coarse-grained soils (USBR, 1998). A soil with a friction angle of 40 degrees has almost four times the bearing capacity of a soil with a friction angle of 32 degrees.

Chapter 2 concluded that the backfill compaction level for the Havana Yard GRS structures was variable and low, especially close to the facing, not meeting CDOT requirements of 95% of AASHTO T-180 method (see Table 2). The non-smooth pier deformation response from row 11 to row 14 (Figures 8 and 9) could be attributed to the variable and low applied backfill compaction level. According to CDOT design specifications, a compaction level of 95% is required to achieve a minimum backfill friction angle of 34 degrees. Hence, the friction angle for the outer pier backfill is expected to be lower than 34 degrees, especially close to the facing. The comparatively low backfill compaction level led to a low strength (i.e., bearing capacity) and stiffness of the reinforced soil mass (Figure 14), lower reinforcement pull-out resistance, higher lateral earth pressures and facing connection loads, and non-uniform distribution of surcharge loads over the pier area, especially in the top zone. Therefore, the lower backfill compaction level resulted in relatively more deformation to the pier.

5.2 Serviceability Block-to-Block Connection Stability Analyses

5.2.1 Background

There is no procedure developed for stability analysis of GRS pier structures. The stability analysis of the facing connections employed here follow the analysis described for reinforced soil walls supporting high surcharge loads (Elias and Christopher, 1997). Serviceability facing connection criteria are employed in the design of segmental retaining walls to ensure that design

facing connection capacity is not developed at the expense of unacceptable wall movement. A relative displacement between block layers below 2% of the height of the block (4 mm in our case) is recommended by NCMA guidelines to insure that serviceability block-to-block connection (or interface shear) capacity criterion is met (Bathurst and Simac, 1997). Results of Figure 10 indicate this criterion was not met for the upper 14 block layers (rows 25 to 38). In the Havana Yard outer pier structure, a fabric layer was placed between block layers and the hollow concrete blocks were filled with uniform size gravel. This facing system developed its block-to-block connection capacity by interface friction between blocks and reinforcements and between gravel and reinforcements. That is, no interlock with shear key or other form of mechanical or positive connection was used.

5.2.2 Analysis Results and Discussion

A surcharge load of 1170 kN was applied on the concrete pad placed on the top of the pier (3.05 m x 0.91 m, see Figure 1). The average vertical stress, σ_v , within the reinforced soil mass of the outer pier structure was induced by gravity forces due to the backfill self weight and surcharge concentrated loads. For a uniformly loaded rectangular area, an approximate estimate of the increase in vertical stresses at different depths can be obtained by assuming the applied surcharge loading to be distributed within a truncated pyramid with sides sloping at 2 vertical to 1 horizontal. The area of the truncated pyramid at any given depth (Area of Influence) should not exceed the cross-sectional pier area at that depth. Note that the cross-sectional area of the pier was not constant with depth and it was tapered from 8.4 m² at the bottom to 5 m² at the top (see Figure 1). The connection load per 1 unit width (kN/m) at any depth z can be calculated as

$$\sigma_v = \gamma z + 1170 / (\text{Area of Influence}) \quad (1)$$

$$\text{Connection Load} = K_a \sigma_v S \quad (2)$$

Where γ is the backfill unit weight (measured as 20.5 kN/m³), K_a is the active earth pressure coefficient, and S is the vertical spacing (0.2m). Table 5 summarizes the results for the average vertical stress, area of influence, and connection loads at different row levels. Employed in the analysis was a backfill with an internal friction angle of 32 degrees, which is a conservative estimated value, based on the discussion in the previous section.

The serviceability block to block connection capacity (T_s) was estimated using the equation suggested by Bathurst and Simac (1997) as:

$$T_s = a + N \cdot \tan \lambda \quad (3)$$

Where a is the minimum available block-to-block connection capacity (kN/m), λ is the equivalent friction angle between blocks, and N is the normal load transmitted across the blocks. Bathurst and Simac (1997) recommended $a = 0.8$ kN/m and $\lambda = 37$ degrees for a facing system that seems similar to the one employed in the Havana Yard pier structure. N is taken as the self-weight of overlying infilled blocks, thus neglecting the drag vertical forces transferred to the blocks from the fabric and the soil. Results for the connection capacity and factor of safety (connection load/connection capacity) at different rows are given in Table 5. Results of Table 5 indicate that the factor of safety was less than 1 between rows 25 and 38, suggesting the serviceability block-to-block connection capacity was exceeded in that zone.

Both the results of forensic investigation (Figure 10) and facing connection stability analysis (Table 5) indicated that layers 25 to 38 of the outer pier failed to meet the serviceability block-to-block connection requirements (i.e., relative displacement between block layers larger than 4 mm). If higher soil friction angles of 36 and 40 degrees were employed in the analysis, the connection capacity would still be exceeded for block layers above 27 and 29, respectively. This indicates that serviceability connection capacity would have been exceeded in the upper zone of the outer pier structure even if the backfill had been well compacted. Therefore, some form of positive block-to-block mechanical connection was needed for a geosynthetic-reinforced soil structure supporting a high surcharge load.

5.3 High Surcharge Load

A very large average contact bearing pressure (422 kPa) was induced directly below the concrete pad (at the top of row 38, see Table 5). A sharp drop of vertical soil stresses occurred around the concrete pad. Around the concrete pad, the vertical forces acting on the reinforced soil were small; also, the area of that zone was very small, leading to small pullout resistance of the

geotextile layers. The vertical stresses on the blocks around the concrete pad were also very small, making the friction-based block-to-block connection strength very small (see Table 5). For all of the reasons described above, the generated high lateral earth load under the concrete pad exceeded the in-service block-to-block connection capacity (maximum factor of safety less than 0.36 in Table 5), and possibly caused a soil bearing capacity problem, leading to excessive displacement of blocks in the upper zone of the pier.

5.4 Influence of Seasonal Changes of Temperature and Moisture

Abu-Hejleh et al. (2001) and Buttry et al. (1996) discussed the influence of temperature and seasonal changes on the performance of GRS walls. Abu-Hejleh et al. (2001) reported that during construction of Phase II of the Founders/Meadows Structure during the cold season, the front GRS wall responded with comparatively small deformations to the increasing level of applied vertical soil stresses. During the following spring season, the front GRS wall responded with comparatively large displacements to the increasing level of applied vertical soil stresses. This behavior was attributed to softening of the backfill due to soil wetting caused by ice melting and rain during the spring season in Colorado.

Field records for the Havana Yard Structures indicate that construction of most of the outer pier structure and application of the surcharge load were performed during the cold season, at times in freezing conditions (construction completed 11/1/96). The sudden excessive movement of the pier structure was noticed some time between March and June of 1997 (during the thawing and heavy rain season in Colorado). Thus, it may be speculated that construction of the outer pier structure during the cold season and softening of the backfill during the 1997 spring may have contributed to the excessive movement of the pier noticed in the spring season. The softening occurred due to a lower backfill compaction level and soil wetting due to heavy rain and ice melting.

5.5 Comparison between the Turner-Fairbank and the Havana Yard Piers

The Havana Yard pier was a relatively slender structure (1.82 m wide and 4.57 m long at the top, and 2.45 m wide and 5.18 m long at the bottom, and 7.6 m high) with base width to height ratio of 0.32. The Turner-Fairbank pier was 5.4 m in height with a base 3.6 m x 4.8 m for a width to

height ratio of 0.67. In the Turner-Fairbank pier, the load was applied uniformly over the entire surface area but the load was applied to a limited surface area in the Havana Yard pier. For the Turner-Fairbank pier, the backfill compaction was monitored very carefully to ensure a proper moisture and uniform backfill compaction level exceeding construction requirements. The measured average backfill unit weight was a very high value (22.8 kN/m^3 or 145 lb/ft^3). This was not the case with the Havana Yard pier backfill (see Chapter 2). The Havana Yard pier backfill was poorly monitored and not uniformly compacted (19.5 kN/m^3). It did not achieve the required 95% compaction level. The average compaction was 91.5 %, and close to the edge of the pier was only 89.9%. For all these reasons, the performance of the Turner-Fairbank pier was much better in terms of load carrying capacity (loaded up to a pressure of 900 kPa), settlement of the top of the pier, and long-term creep which was negligible for the Turner-Fairbank pier but quite significant for the Havana Yard outer pier (FHWA, 2000). Furthermore, the Havana Yard pier experienced excessive deformations and cracking. For the Turner-Fairbank pier, Adams (1997) reported excellent pier performance at 200 kPa and a superficial problem of cracks in the facing at pressures greater than 275 kPa.

Elias and Christopher (1997) recommended a design pressure of 200 kPa for reinforced soil abutments directly supporting bridge loads. The GRS abutments for the Founders/Meadows Structure (Abu-Hejleh et al., 2000) and Black Hawk Structure (FHWA, 2000) were constructed and performed satisfactorily with a design pressure of 150 kPa. For the Turner-Fairbank large-size pier, it was concluded that the performance of the pier at 200 kPa was very good with no cracks occurring in the facing blocks. Therefore, based on the previous discussion, for future construction of a massive pier like the Turner-Fairbank pier, a design pressure of 150 kPa can be used. For future construction of slender piers like the Havana Yard outer pier, when properly constructed as outlined in the Executive Summary, a design pressure of 100 kPa is recommended.

CHAPTER 1—PROPERTIES OF SOILS




Figure 1-17 Effect of relative density on the coefficient of friction, tan ϕ

Figure 14 Effect of Relative Soil Density on the Soil Friction Angle, tan ϕ , for Coarse-Grained Soils (USBR, 1998)

Table 5 Results of Serviceability Block-to-Block Connection Stability Analyses

Top of Row #	Depth (z) m	Influence Area (m2)	Average Vertical Stress (kPa)	Horizontal Active Stress (kPa)	Connection Load (kN/m)	Serviceability Block to Block Connection Stability Analyses	
						Capacity kN/m	Factor of Safety
38	0	2.78	421.5	129.4			
37	0.2	3.61	328.4	100.8	23.0	1.8	0.08
36	0.4	4.52	267.1	82.0	18.3	2.8	0.15
35	0.6	5.30	233.2	71.6	15.4	3.8	0.25
34	0.8	5.39	233.6	71.7	14.3	4.8	0.34
33	1	5.48	234.2	71.9	14.4	5.9	0.41
32	1.2	5.56	234.9	72.1	14.4	6.9	0.48
31	1.4	5.65	235.7	72.4	14.4	7.9	0.55
30	1.6	5.74	236.6	72.6	14.5	8.9	0.61
29	1.8	5.83	237.6	72.9	14.6	9.9	0.68
28	2	5.92	238.6	73.3	14.6	10.9	0.75
27	2.2	6.01	239.8	73.6	14.7	11.9	0.81
26	2.4	6.10	241.1	74.0	14.8	12.9	0.88
25	2.6	6.19	242.4	74.4	14.8	13.9	0.94
24	2.8	6.28	243.8	74.9	14.9	15.0	1.00
23	3	6.37	245.3	75.3	15.0	16.0	1.06
22	3.2	6.45	246.9	75.8	15.1	17.0	1.12
21	3.4	6.54	248.5	76.3	15.2	18.0	1.18
20	3.6	6.63	250.2	76.8	15.3	19.0	1.24
19	3.8	6.72	252.0	77.4	15.4	20.0	1.30
18	4	6.81	253.8	77.9	15.5	21.0	1.35
17	4.2	6.90	255.7	78.5	15.6	22.0	1.41
16	4.4	6.99	257.6	79.1	15.8	23.0	1.46
15	4.6	7.08	259.6	79.7	15.9	24.1	1.51
14	4.8	7.17	261.7	80.3	16.0	25.1	1.57
13	5	7.26	263.8	81.0	16.1	26.1	1.62
12	5.2	7.34	265.9	81.6	16.3	27.1	1.67
11	5.4	7.43	268.1	82.3	16.4	28.1	1.71
10	5.6	7.52	270.3	83.0	16.5	29.1	1.76
9	5.8	7.61	272.6	83.7	16.7	30.1	1.81
8	6	7.70	274.9	84.4	16.8	31.1	1.85
7	6.2	7.79	277.3	85.1	17.0	32.1	1.90
6	6.4	7.88	279.7	85.9	17.1	33.2	1.94
5	6.6	7.97	282.2	86.6	17.2	34.2	1.98
4	6.8	8.06	284.6	87.4	17.4	35.2	2.02
3	7	8.15	287.1	88.2	17.6	36.2	2.06
2	7.2	8.23	289.7	88.9	17.7	37.2	2.10
1	7.4	8.32	292.3	89.7	17.9	38.2	2.14
0	7.6	8.41	294.9	90.5	18.0	39.2	2.18

6.0 SUMMARY

6.1 Overview

From 1996 to 1999, two full-scale GRS structures (Turner-Fairbank pier and Havana Yard piers and abutment) and two production GRS abutments (Founders/Meadows and Black Hawk) were constructed. The objective was to demonstrate that GRS abutments and piers with block facings were viable alternatives to conventional bridge piers and abutments. A full-scale fabric geotextile-reinforced soil bridge abutment and two GRS bridge piers (center and outer) with block facing were constructed in the Havana Maintenance Yard (Photos 1 through 5 of Appendix A and Figure 1). A surcharge load was applied to the abutment and outer pier (not the center pier). The performance of the Havana Maintenance Yard abutment was good. Some time between March and May of 1997 (4 to 5 months after the surcharge load was placed), excessive and sudden movements of the top several layers of the outer pier structure and severe cracking of the facing were noticed as depicted in Photo 5 to 7 of Appendix A. The toppling failure of the upper four rows of the outer pier was deemed to be imminent. Therefore, it was decided to remove the applied surcharge load, tear down the structures, and conduct forensic and stability investigations. The objectives and findings of these investigations are given below.

6.2 Fulfilling 1st Study Objective

“Determine the in-situ conditions and characteristics of the structures materials after almost three years in place.”

6.2.1 Backfill

The backfill material was a mixture of gravel (39.7%), sand (46.7%) and fine-grained soil (13.6%) that meets material requirements for CDOT Class-1 backfill (Table 1). Twenty-eight field tests were conducted to measure the backfill moisture content and density at the center and edges at different depths inside the three structures (Table 2). The results of 27 tests suggest that requirements for backfill compaction level (95%) were not met. The measured backfill compaction level ranged from 74 % to 97.9 % with an average of 88.3 %. The backfill placed at the edges (1 foot from the facing) received less compactive efforts (average of 86.6 %) than the backfill at the center of the structure (89.9 %). In the upper three layers of the outer pier, the soil

below the concrete pad settled more than the rest of the pier area, possibly due to variable applied compaction efforts and concentrated surcharge loads.

6.2.2 *Geotextiles*

The reinforcement buried in the Havana Yard Structures for three years was a woven polypropylene geotextile designated as Amoco 2044 (Photo 11, 13 and 14 of Appendix A). All collected geotextile sheets were in excellent condition, showing no obvious signs of geotextile distress (e.g., tears or cuts). The survivability and durability of the exhumed geotextiles were evaluated by comparing the measured wide-width tensile strength of the exhumed samples with the strength of the fresh new geotextile samples. The findings were:

- ❑ The results of 128 wide-width tensile tests shown in Table 42 suggest that geotextile exhumed strength were lower by 0 to 18%.
- ❑ Subjecting geotextiles to different stress levels from overlying materials and surcharge loading did not contribute to the geosynthetic deterioration and loss of strength
- ❑ The low loss of geotextile strength measured in this study (up to 53 %) and results reported in the literature indicated that the durability and creep of geotextile reinforcements were not a problem.
- ❑ The small loss of geotextile strength was attributed primarily to construction damage.
- ❑ Construction method and technique has a great impact on the level of geosynthetic deterioration and damage.

6.2.3 *Block Facing*

Different types of blocks were used in the construction of the three Havana Yard Structures (Figures 3 to 5). There were few cracks visible in the external face of the abutment before the dismantling began, but during dismantling, a fairly large percentage – as high as 50% – of the blocks in some layers was broken. On most of the levels, most of the broken blocks were on the side where the surcharge load was applied (Figure 1). There were no visible cracks in the external face of the center pier (the pier that was not surcharge loaded) and no internally broken blocks were found during the dismantling operations. The facing of the outer pier (see Photo 5 and 6) was severely damaged, as was observed in the cracking of the external face (Figure 6) and

broken internal sides of the blocks (Figures 11 to 13). The facing of the outer pier experienced excessive movements, especially the upper four layers. This movement decreased with the depth from the top of the pier (Figures 7 to 10). Additional descriptions of the movement and damage of the pier and possible causes for this response are provided in the next section.

6.3 Fulfilling 2nd Study Objective

“Determine potential causes for the excessive deformations and cracking of the Havana Yard outer pier structure.”

A geotextile layer was placed between block layers and the hollow concrete blocks were infilled with uniform size gravel. This facing system derived its block-to-block connection capacity through interface friction between blocks and reinforcements and between gravel and reinforcements (there was no interlock with shear key or other form of mechanical connection). Both the results of forensic investigation (Figure 10) and facing connections stability analyses (Table 5) indicated that layers 25 to 38 of the outer pier failed to meet the serviceability block-to-block connection requirements (i.e., relative displacement between block layers was larger than 4 mm). The pier response and causes for this response are summarized below for three zones of the pier (See Figures 6 to 13 and Table 5).

- Upper zone of block layers (35 to 38): In this zone, no damage was noticed to the external and internal sides of the blocks. Large relative displacement between block layers of 27 mm, and significant vertical joint openings were noticed. Very large average contact bearing pressure (422 kPa) was induced directly below the concrete pad (at top of row 38, see Table 5). A sharp drop of vertical soil stresses occurred around the concrete pad. The area around the concrete pad was small so the vertical forces acting on the reinforced soil were small resulting in low reinforcement pullout resistance. Also, around the concrete pad the vertical stresses on the blocks were very small, making the friction-based block-to-block connection strength very small (see Table 5). For reasons described above, the generated high lateral earth load under the concrete pad exceeded in-service block/block connection capacity (maximum factor of safety less than 0.36 in Table 5), and caused a soil bearing capacity problem, leading to excessive displacement

of blocks in this zone. The almost free (unrestrained) excessive relative displacement between block layers (due to low connection strength) resulted in no damage to the blocks.

- Middle zone of block layers 11 to 34: This zone moved to a lesser degree than the upper zone but was heavily damaged (cracked and broken blocks). The relative displacement of layers 25 through 34 was approximately 10 mm. On the average, smaller relative displacements occurred for layers 11 to 25 (i.e., block outward displacements decreased with depth, Figure 9). Typically, cracks on the external face were aligned with the joints in the layers above and below the cracked blocks (Photo 5 to 7 of Appendix A). Many of the blocks that appeared from the outside to be whole were broken on the interior sides. In this zone, the friction-based connection strength between blocks was high because of the higher normal loads from overlying blocks, and possibly from vertical loads transferred to the blocks by drag forces from the reinforced soil mass. The higher connection strength and placement of blocks in a running bond configuration restricted the free expansion of the pier in this zone, causing severe damage to blocks. The restraining caused the development of axial transverse tension forces in the blocks, leading to vertical cracks in the blocks around the vertical joints. It seems that the facing connection strength in this zone was stronger than the tensile strength of blocks. The vertical loads transferred to the blocks by drag forces from the reinforced soil mass could have contributed to the significant breaking of the interior sides of the blocks.

- Lower zone of block layers 1 to 10: In this zone, the intensity of block damage diminished and the relative displacements between block layers were negligible (almost zero). It was possible that the friction resistance between the bottom leveling pad and the lower zone of the pier reduced the earth pressures supported by the facing in the lower zone of the pier. The lower earth pressure on the facing and very high connection strength between blocks (due to high vertical stresses acting on blocks) minimized block movements and damage in this zone.

The comparatively low backfill compaction level led to a low strength (i.e., bearing capacity) and stiffness of the reinforced soil mass (Figure 14), low reinforcement pullout resistance, higher lateral earth pressures and facing connection loads, and non-uniform distribution of surcharge loads over the pier area especially in the top zone. Therefore, the lower backfill compaction level resulted in relatively more deformation to the pier.

The construction of the outer pier structure during the cold season and softening of the backfill during the 1997 spring season could possibly have contributed to the movement of the pier in the spring season. The softening occurred due to lower backfill compaction level and soil wetting due to heavy rain and ice melting.

In summary, the reasons for the excessive deformation and cracking of the Havana Yard outer pier are: high surcharge load applied uniformly to a limited surface area of a slender pier, low backfill compaction level, weak facing connection strength and pullout resistance in the upper zone of the pier, weak blocks, and seasonal changes.

7.0 RECOMMENDATIONS

GRS abutment and piers are viable alternatives to conventional methods used in bridge support. Details for construction of GRS abutments and piers are available in several references (Elias and Christopher, 1997; FHWA, 2000; and Abu-Hejleh et al., 2000 and 2001). Design and construction of GRS abutments in highway projects have been successfully implemented and monitoring results have shown excellent field performance. However, research is still needed to develop rational design and construction guidelines for GRS piers and appropriate limitations (e.g., base to height ratio). Consequently, future field implementation of GRS piers should still be considered experimental and such structures should be carefully monitored. Limitations and additional details for construction of GRS piers (and, if appropriate, other GRS structures) learned from this study and from recently published literature (FHWA, 2000; Adams, 1997) are furnished in this report. They are:

- ❑ The use of GRS piers is well-suited for remote locations, where specialized equipment or concrete is unavailable or cannot be reached. The materials used to construct the pier are commonly available. In emergency situations, a GRS pier can be constructed using small construction equipment and put into service within a few days. The use of GRS piers may be beneficial for temporary bridge structures, and bike or pedestrian bridges. Also, GRS piers should be considered for aesthetic purposes when a massive look is needed. Although there are many benefits from this modern approach to bridge pier design, it should not be used in a scour environment, when it would not prove economical, or when loads are excessive. CDOT engineers believe that the use of GRS piers may not be economical for many typical highway practices when compared to the use of concrete piers.

- ❑ Closely spaced (0.2 m to 0.3 m), high-strength geosynthetic reinforcements and well-compacted quality granular backfill form a strong composite reinforced soil mass. Based on the limited results of full-scale GRS piers and recommendations provided in the literature, design surcharge pressures ranging from 100 to 150 kPa are recommended for comparatively large and slender GRS piers (e.g., having base width/height ratio of 0.7 – the Turner-Fairbank structure to 0.33 – the Havana Yard Structure). Under these surcharge pressures, creep and durability of geosynthetic materials have not been a problem in monitored full-

scale structures. Construction damage of the geosynthetic is not considered a problem in GRS piers because fill material can be spread by manual labor (an approximately 5% reduction in tensile strength from damage was measured in this study). For construction of GRS structures using heavy equipment, construction damage may contribute to reduction in geosynthetic tensile strength and should be minimized.

- ❑ Requirements for compaction of coarse-grained backfill should be enforced and well controlled in the field. To achieve proper backfill compaction at the optimal moisture content within the limited area of the pier, numerous compaction passes with light equipment should be performed. For GRS piers, a backfill soil with a friction angle of at least 40 degrees is highly recommended. If feasible, a maximum size crushed stone of 19 mm should be used for a minimum distance of 0.3 m behind the facing blocks in order to facilitate fill compaction behind blocks, provide internal drainage, and prevent migration of fines to the wall facing. Alternatively, wrapping of geotextile behind the face could be implemented for erosion control purposes.
- ❑ In the top 1.6 m of piers loaded with a high surcharge load, it is recommended to: 1) place reinforcements with a wrapped-around procedure behind the facing, and 2) employ mechanical connection between blocks and between blocks and reinforcements. Results of this research and other studies suggest that the friction-based facing connection strength in the lower zone of the pier is adequate.
- ❑ Consider measures and details to achieve a uniform distribution of surcharge load over the entire pier surface area (e.g., use of flow fill in the top zone), or a trapezoidal distribution where the highest pressure would occur at the center of the structure (e.g., plastic hinge joint at the center of the concrete pad).
- ❑ Include measures to enhance the pullout resistance of reinforcements in the top layers near to the sides of the pier (e.g., wrap reinforcements around heavy items, drive bars through reinforcement into the backfill).

- ❑ Construction of the GRS structures during drier and warmer seasons is preferred. At least, backfill temperature during construction should be maintained above freezing.

- ❑ Implement measures to prevent surface water run-off and ground water intrusion into the reinforced soil mass.

- ❑ Use high quality, strong blocks meeting CDOT specifications.

REFERENCES

1. Abu-Hejleh, N., Outcalt, S., Wang, T., and Zornberg, J.G. (2000).“Performance of Geosynthetic-Reinforced Structures supporting the Founders/Meadows Bridge and Approaching Roadway Structure. Report 1: Design, Materials, Construction, Instrumentation, and Preliminary Results.” Report No. CDOT-DTD-R-00-5, Colorado Department of Transportation, Denver, Colorado.
2. Abu-Hejleh, N., Wang, T., and Zornberg, J.G. (2000).“Performance of Geosynthetic-Reinforced Walls Supporting Bridge and Approaching Roadway Structures.” ASCE/Geotechnical Special Publication No. 103, Advances in Transportation and Geoenvironmental Systems Using Geosynthetics, Zornberg, J.G. and Christopher, B.R. (Eds.), pp. 218-243.
3. Abu-Hejleh, N., Zornberg, J.G., and Wang, T. (2001). “Monitored Displacements of a Unique Geosynthetic-Reinforced Walls Supporting Bridge and Approaching Roadway Structures.” Presented at the 2001 TRB annual meeting.
4. Adams, M. (1997). “Performance of a prestained geosynthetic reinforced soil bridge pier.” Int. Symp. On Mechanically Stabilized Backfill, T.H. Wu, editor, A. A. Balkema, Denver, USA, 35-53.
5. Bathurst, R.J., and Simac, M.R. (1997). “Design and Performance of the Facing Column for Geosynthetic Reinforced Segmental Retaining Walls.” Int. Symp. On Mechanically Stabilized Backfill, T. H. Wu, editor, A. A. Balkema, Denver, USA, 193-208.
6. Bell, J.R., and Barrett, R. (1995). “Survivability and Durability of Geotextiles Buried in Glenwood Canyon Wall.” Transportation Research Record 1474, TRB, National Research Council, Washington, D.C., pp. 55-63.

7. Buttry, K., McCullough, E., and Wetzell, R. (1996). "Temperature and Related Behavior in Segmental Retaining Wall System." *Transportation Research Record # 1524*, pp. 19-23.
8. Elias, V. and Christopher, B.R. (1997). "Mechanically Stabilized Earth Walls and Reinforced Soil Slopes, Design and Construction Guidelines." FHWA Demo Project 82-1, Washington DC, 367 p.
9. FHWA (2000). "GRS Bridge Piers and Abutments." FHWA-RD-00-038. Sponsored by Turner-Fairbank Highway Research Center.
10. U.S. Department of the Interior, Bureau of Reclamation (1998). "Earth Manual, Part I." Third Edition, Earth Sciences and Research Laboratory, Geotechnical Research, Technical Service Center, Denver, Colorado.
11. Ketchart, K. and Wu, J.T.H. (1997). "Loading Tests of GRS Bridge Pier and Abutment in Denver, Colorado." Report No. CDOT-DTD-97-10, Colorado Department of Transportation, Denver, Colorado.
12. Powell, B., and Mohny, J. (1994). "Durability of Geotextiles Used in Reinforcement of Walls and Road Subgrade." In *Transportation Research Record 1439*, TRB, National Research Council, Washington, D.C., pp. 20-24.

APPENDIX A

APPENDIX A

Photographs taken before and during dismantling of structures and during testing of geotextile sheets.




Photo 1. Demonstration Fabric Reinforced Structures at the Havana Maintenance Yard.



Photo 2. Upper Portion of the Abutment Structure.



Photo 3. Lower Portion of the Abutment Structure. Note the negative batter. This was done only on the east side of the abutment and only below the ground level.



Photo 4. The Center Pier Structure. Note the outward bow of the top several rows of blocks.



Photo 5. The Outer Pier Structure.



Photo 6. Excessive Movements of the Top Rows of Blocks on the Outer Pier.



Photo 7. Excessive Cracking of the Facing of the Outer Pier Note that all cracks are vertical and they are aligned with joints in layers below or above the cracked blocks.



Photo 8. Cracks in the Lower Part of the Abutment.



Photo 9. Dismantling Operation of the Havana Maintenance Structures.



Photo 10. Dismantling in Progress: The Outer Pier at Row 10 from bottom.



Photo 11. Geotextile Sheet During Dismantling of the Inner Pier. No damage to any of the fabric sheets was observed in any of the structures even at locations where the fill had settled considerably.



Photo 12. A Vertical Crack in a Block from the Abutment Structure.



Photo 13. Retrieved Geotextile Sheets and Whole Blocks from the Structures.



Photo 14. Fabric Specimens Ready for the Wide-Width Tensile Test (ASTM D 4595).




Photo 15. Mounting Fabric Specimen in The Wide-Width Tensile Test to Remove any Slack.






Photo 16. A Fabric Specimen at the Failure Condition.



**Photo 17. Wide-Width Tensile Test Results on Geotextile Sheets W17 and C20
 (8 specimens of each sheet).**