# 9.0 SURVEY

# 9.1 Administrative Requirements

# 9.1.1 Standards

The Contractor shall meet all applicable federal, state, and local requirements related to surveys, records, and monuments.

# 9.1.2 Project Survey Coordinator

Should the Contractor choose to collect additional field survey information, the Contractor shall designate a Colorado Registered Professional Land Surveyor as the Project survey coordinator. The Project survey coordinator shall be in responsible charge of all Contractor survey Activities on the Project. The Project survey coordinator shall direct and review all survey Work and shall be the point of contact for all survey related Activities. Contractor survey staff shall perform Work under the direct supervision of the Project survey coordinator.

PROJECT: STA C800-001/16501

**DATE: JANUARY 29, 2009** 

# 9.1.3 CDOT Supplied Survey Data

The full extent of survey and mapping information to be supplied by CDOT is provided in Book 4. Topography ground survey information within the project construction limits was collected using RTK methods with supplemental collection using conventional survey methods. Surveys were performed according to the guidelines for Preliminary Surveys published in the CDOT Survey Manual. The Contractor shall verify and confirm the accuracy of all survey and mapping information provided to the Contractor, regardless of the source of the information. The Contractor shall document all forms of data verification. Any discrepancies in information provided that is reported to the CDOT Project Director within 60 Days of NTP1 will be resurveyed or corrected by CDOT at no cost to the Contractor.

Available aerial mapping-based planimetric and contour information outside of the ground survey limits and field survey of underground utility information is provided in the Reference Documents and is for information only.

# 9.1.4 Contractor Supplied Survey Data

Except as provided by CDOT above, the Contractor shall provide all other surveys required for completion of the Work.

# 9.1.5 Preservation of Survey Monuments

The preservation of survey markers and monuments is mandatory and affects all governmental agencies. The Contractor shall notify the agency affected as soon as it becomes known that a marker is in a position that will interfere with new construction or with Contractor operations. The marker position shall be accurately preserved prior to disturbing any such marker.

PROJECT: STA C800-001/16501 **DATE: JANUARY 29, 2009** 

#### **CDOT Monuments** 9.1.6

If any survey monuments are at risk of being destroyed at any time within the Right-of-Way (ROW), the Contractor shall immediately notify the CDOT Project Director. The Contractor may assume that the agency affected will send a new marker disk, which has been properly stamped together with instructions for establishment of the new marker, or CDOT will provide a marker disk. The Contractor shall have the new marker set in accordance with the provided instructions and the requirements of the Contract. The new marker shall be set under the direct supervision, and responsible charge of the Project survey coordinator or other Colorado Registered Professional Land Surveyor, and where required by Colorado statute shall bear the registration number of the responsible Professional Land Surveyor.

### 9.1.7 **Other Agency Monuments**

The Contractor shall coordinate with all other agencies with monuments on the Project to protect and restore their monuments as required to complete the Work.

### 9.1.8 **Survey Records**

The Contractor shall prepare and maintain supporting documentation, including but not limited to field notes, drawings, and calculations for all survey Work on the Project. All survey records shall conform to the formats shown in the CDOT Survey Manual. Such records shall be neat, legible, accurate, and maintained by the Contractor in a neat and orderly manner.

The Contractor's Project survey coordinator shall be required to sign and seal all survey documentation in accordance with state law. All such documentation shall be transmitted to the CDOT Project Director at the completion of the Work.

# 9.2 **Design Requirements**

### 9.2.1 **Design Control Surveys**

The Contractor shall plan, schedule, and perform all surveys and monumentation necessary to maintain and supplement the Project control network for the design of the Project.

The Contractor shall submit to the CDOT Project Director a revised Project control diagram showing all modifications to the Project control network.

### 9.2.2 **Design Surveys**

The Contractor shall arrange for all supplemental survey information and utility locations necessary to complete the design. Design surveys shall provide sufficient detail to verify actual field locations of existing drainage improvements as well as for the final design of drainage and utility improvements. Surveying shall be performed in accordance with the CDOT Survey Manual. Traffic control and permits necessary to complete the survey shall be the responsibility of the Contractor. The Contractor shall deliver the data (in InRoads TMOSS survey format) and field notes to the CDOT Project Director for review upon completion of the survey. Errors and omissions found by the CDOT Project Director shall be corrected by the Contractor and resubmitted.

# **Construction Requirements** 9.3

### 9.3.1 **Construction Control Surveys**

The Contractor shall plan, schedule, and perform all surveys and monumentation necessary to maintain and supplement the Project control network for the construction layout of the Work.

PROJECT: STA C800-001/16501

**DATE: JANUARY 29, 2009** 

### 9.3.2 **Construction Layout Surveys**

The Contractor shall plan, schedule and perform all staking and construction layout required for the Work.

## 9.3.3 **As-Built Surveys**

**SECTION 9 - SURVEY** 

The Contractor shall plan, schedule and perform all surveys required to document the location of as-built features on the Project.

#### 9.3.4 **ROW Monumentation**

The Contractor shall replace all ROW monumentation lost or destroyed during the progression of the Work.

The Contractor shall submit to the CDOT Project Director for acceptance a revised ROW monumentation sheet listing all ROW monumentation reset by the Contractor.

#### 9.4 **Deliverables**

At a minimum, the Contractor shall submit the following to CDOT for review, Approval and/or Acceptance:

Acceptance or Approval	Schedule
Acceptance	Submit with as-built documents
	or Approval