## REVISION OF SECTION 401 COMPACTION PAVEMENT TEST SECTION (CTS)

Section 401 of the Standard Specifications is hereby revised for this project as follows:

In subsection 401.17, delete the fourteenth paragraph and replace with the following:

Two sets of random cores shall be taken within the last 200 tons of the CTS. Each set shall consist of a minimum of seven random corings. The Engineer will determine the coring locations using a stratified random sampling process. The locations of these cores will be such that one set can serve as a duplicate of the other. One set of these cores shall be immediately submitted to the Engineer. This set will be used for determining acceptance of the CTS and determining density correction factors for nuclear density equipment. Densities of the random samples will be determined by cores according to CP 44. Density correction factors for nuclear density equipment will be determined according to CP 81. Coring shall be performed under CDOT observation. Coring will not be measured and paid for separately but shall be included in the work.