1 **REVISION OF SECTION 412** PORTLAND CEMENT CONCRETE PAVEMENT CONSOLIDATING AND FINISHING

Section 412 of the Standard Specifications is hereby revised for this project as follows:

In subsection 412.07(b) delete the second paragraph and replace with the following:

The full width and depth of concrete requiring a finishing machine shall be consolidated by a single pass of an approved internal vibrator. Internal vibrators shall be operated within a frequency range of 4,000 to 8,000 vibrations per minute (VPM). Vibrators shall not be operated in a manner to cause a separation of the mix ingredients, either a downward displacement of large aggregate particles or an accumulation or laitance on the surface of the concrete. Avoidance of separation of the mix may require reduction in the vibrator frequency when forward motion of the paver is reduced. Paving machine operations shall stop if any vibrator fails to operate within specifications. Vibration shall be stopped whenever forward motion of the paver is stopped.

The use of surface vibrators shall be approved by the Engineer prior to use. Surface vibrators shall be operated within a frequency range of 3,500 to 6,000 VPM.

Delete subsection 412.12 and replace with the following:

412.12 Finishing. The sequence of operations shall be strike-off and consolidation, floating, and final surface finish.

Water shall not be added to the surface of the concrete to assist in finishing operations. The surface shall be finished to a uniform texture, true to grade and cross section, and free from porous areas. When the finishing machine, either form or slip form, or hand finishing method, leaves a surface that is not acceptable, the operation shall stop and corrective action shall be taken. Inability of the finish machine to provide an acceptable surface finish, after corrective action, will be cause for requiring replacement of the finish machine.

Wastewater generated from concrete finishing operations shall be contained and disposed of in accordance with subsection 107.25.

- (a) Hand Finishing. Unless otherwise specified, hand finishing methods will be permitted only when performed under the direct supervision of a Craftsman holding the following certificate: ACI Concrete Flatwork Finisher and Technician (ACICFFT) or other Flatwork Finisher certification program approved by the Department. A minimum of one certified Craftsman is required at each finishing operation. A minimum of one certified Craftsman is required for each three or fewer finishers (non-certified ACICFFTs) at each operation.
 - Hand finished concrete shall be struck off and screeded with a portable screed that is at least 2 feet longer than the maximum width of the slab to be struck off. It shall be sufficiently rigid to retain its shape. Concrete shall be thoroughly consolidated by hand vibrators. Hand finishing shall not be allowed after concrete has been in-place for more than 30 minutes or when initial set has begun unless otherwise approved by the Engineer.
- (b) Floating. Hand floating will be permitted only as specified in paragraph (a) above. The Contractor shall not use floats made of aluminum.
- (c) Final Finish. For the final finish a strip of plastic turf shall be dragged longitudinally over the full width of pavement after a strip of burlap or other approved fabric has been dragged longitudinally over the full width of pavement to produce a uniform surface of gritty texture.
 - The plastic turf drag shall be made of material at least 3 feet wide and be maintained in such a condition that the resultant surface finish is of uniform appearance and reasonably free from grooves over ¹/₁₆ inches in depth. Where more than one layer of burlap drag is used, the bottom layer shall be approximately 6 inches wider than the layer above. Drags shall be maintained clean and free from encrusted mortar. Drags that cannot be cleaned shall be discarded and new drags installed.

REVISION OF SECTION 412 PORTLAND CEMENT CONCRETE PAVEMENT CONSOLIDATING AND FINISHING

(d) *Tining and Stationing*. Where posted speeds are 40 mph or higher, the surface shall be given a longitudinal metal tine finish immediately following turf drag. Tining is not required where posted speeds are less than 40 mph. Tining shall produce grooves of ¹/₈ inch by ¹/₈ inch spaced ³/₄ inch apart and parallel to the longitudinal joint. Longitudinal tining shall stop at the edge of travel lanes. Tining devices shall be maintained clean and free from encrusted mortar and debris to ensure uniform groove dimensions. The tining finish shall not be performed too early whereby the grooves may close up.

Before paving the Contractor shall provide in writing a tining plan showing tining locations and describing methods that will be used for hand tining. Paving shall not commence until the Engineer has approved the tining plan in writing.

The tining grooves shall be neat in appearance, parallel with the longitudinal joint, uniform in depth and in accordance with what is shown in the plans and these specifications. Any time that the tining grooves do not meet these requirements, the concrete paving operation shall be immediately stopped and will not resume until the problem has been resolved.

Stationing shall be stamped into the outside edge of the pavement, as shown on the plans.