## REVISION OF SECTION 630 CONSTRUCTION ZONE TRAFFIC CONTROL

Section 630 of the Standard Specifications is hereby revised for this project as follows:

Subsection 630.10 shall include the following after the first paragraph:

The Contractor's Superintendent and all others serving in a similar supervisory capacity shall have completed a CDOT-approved two-day Traffic Control Supervisor training as offered by the CCA. The one-day ATSSA Traffic Control Technician (TCT) training along with the two-day ATSSA Traffic Control Supervisor training will serve as an alternate. If the alternate is chosen, the Contractor shall provide written evidence that at least an 80 percent score was achieved in both of the two training classes. The certifications of completion or certifications of achievement for all appropriate staff shall be submitted to the Engineer at the preconstruction conference.

In subsection 630.11, delete the fourth paragraph and replace with the following:

All covering materials shall be plywood, hard-board, sheet metal, aluminum, corrugated polypropylene or rigid plastic, and shall be durable enough to resist deterioration due to weathering and atmospheric conditions for the duration of the project. Examples are aluminum at least 0.040 inch thick, corrugated polypropylene board, and plywood at least 3/8 inch thick. Adhesives, glues, tapes, or mechanical fasteners that mar the face of the panel to be masked shall not be used.

In subsection 630.15 delete the fifth paragraph and replace with the following:

The Contractor shall agree to quantities for the following items on a weekly basis when signing the Form 7:

Traffic Control Management	Day
Traffic Control Inspection	Day
Flagging	Hour
Pilot Car Operation	Hour