

Addendum #2

June 25, 2015

BID SCHEDULE FOR I25 MANAGED LANES - INITIAL WORKS - PAVEMENTS

ITEM NO.	DESCRIPTION	ESTIMATED QUANTITY	UNIT	CONTRACTORS UNIT PRICE	TOTAL PRICE
202-00210	REMOVAL OF CONCRETE PAVEMENT	3,995	SY	\$ -	\$ -
202-00240	REMOVAL OF ASPHALT MAT (PLANING)	24,390	SY	\$ -	\$ -
202-00250	REMOVAL OF PAVEMENT MARKING	48,973	SF	\$ -	\$ -
208-00045	CONCRETE WASHOUT STRUCTURE	3	EACH	\$ -	\$ -
208-00050	STORM DRAIN INLET PROTECTION	186	EACH	\$ -	\$ -
208-00106	SWEEPING (SEDIMENT REMOVAL)	40	HOUR	\$ -	\$ -
208-00107	REMOVAL OF TRASH	40	HOUR	\$ -	\$ -
208-00206	EROSION CONTROL SUPERVISOR	80	DAY	\$ -	\$ -
210-04000	ADJUST STRUCTURE	24	EACH	\$ -	\$ -
210-04010	ADJUST MANHOLE	14	EACH	\$ -	\$ -
304-06000	AGGREGATE BASE COURSE (CLASS 6)	15	TON	\$ -	\$ -
403-09221	STONE MATRIX ASPHALT (FIBERS)(ASPHALT)	2,839	TON	\$ -	\$ -
403-33841	HOT MIX ASPHALT (GRADING S) (100) (PG 64-22)	68	TON	\$ -	\$ -
412-00190	CONCRETE PAVEMENT (PATCHING)	341	SY	\$ -	\$ -
412-01000	CONCRETE PAVEMENT (10 INCH)	3,722	SY	\$ -	\$ -
412-14000	SAWING AND SEALING CONCRETE PAVEMENT JOINTS	293,542	LF	\$ -	\$ -
412-15000	ROUTING AND SEALING CONCRETE PAVEMENT CRACKS	3,820	LF	\$ -	\$ -
626-00000	MOBILIZATION	1	L S	\$ -	\$ -
627-00005	EPOXY PAVEMENT MARKING	570	GAL	\$ -	\$ -
627-30405	PREFORMED THERMOPLASTIC PAVEMENT MARKING (WORD-SYMBOL)	765	SF	\$ -	\$ -
630-00000	FLAGGING	330	HOUR	\$ -	\$ -
630-00007	TRAFFIC CONTROL INSPECTION	55	DAY	\$ -	\$ -
630-00012	TRAFFIC CONTROL MANAGEMENT	120	DAY	\$ -	\$ -
630-80001	FLASHING BEACON (PORTABLE)	8	EACH	\$ -	\$ -
630-80335	BARRICADE (TYPE 3 M-A) (TEMPORARY)	3	EACH	\$ -	\$ -
630-80341	CONSTRUCTION TRAFFIC SIGN (PANEL SIZE A)	14	EACH	\$ -	\$ -
630-80342	CONSTRUCTION TRAFFIC SIGN (PANEL SIZE B)	30	EACH	\$ -	\$ -
630-80343	CONSTRUCTION TRAFFIC SIGN (PANEL SIZE C)	18	EACH	\$ -	\$ -
630-80355	PORTABLE MESSAGE SIGN PANEL	1	EACH	\$ -	\$ -
630-80358	ADVANCE WARNING FLASHING OR SEQUENCING ARROW PANEL (C TYPE)	2	EACH	\$ -	\$ -
630-80360	DRUM CHANNELIZING DEVICE	120	EACH	\$ -	\$ -
630-80363	DRUM CHANNELIZING DEVICE (WITH LIGHT) (FLASHING)	4	EACH	\$ -	\$ -
630-80380	TRAFFIC CONE	400	EACH	\$ -	\$ -

CONSTRUCTION SUBTOTAL				\$ -
WEEKEND RENTAL SUBTOTAL		PER WEEKEND DAY	\$ (6,000.00)	\$ -
I25 MANAGED LANES - INITIAL WORKS - PAVEMENTS TOTAL PROJECT COST				\$ -

AD ALTERNATE #1					
202-00210	Removal of Concrete Pavement	12,515	SY	\$ -	\$ -
202-00895	Removal of Impact Attenuator	1	EACH	\$ -	\$ -
630-85006	Impact Attenuator (Sand Filled Plastic Barrel)(Temporary)	1	EACH	\$ -	\$ -
403-00721	Hot Mix Asphalt (Patching) (Asphalt)	327	SY	\$ -	\$ -

CONSTRUCTION SUBTOTAL				\$ -
AD ALTERNATE #1 TOTAL PROJECT COST				\$ -

I25 MANAGED LANES - INITIAL WORKS - PAVEMENTS TOTAL				\$ -
AD ALTERNATE #1 TOTAL				\$ -

TOTAL COMBINED BID AMOUNT				\$ -
---------------------------	--	--	--	------