

# A tutorial on how collector-distributor lanes will help traffic flow between I-25 and US 6


#### What are collector-distributor lanes?

A collector-distributor lane (sometimes referred to as a C-D lane) is a lane specifically designed to handle entering and exiting traffic along a highway. As its name implies, this lane "collects" traffic exiting from a highway and "distributes" it back onto a highway. These lanes are barrier separated from the main highway and provide direct access to local arterial roads and longer acceleration distances to merge onto a highway.

### Where will they be incorporated on US 6?

When the US 6 Bridges Design-Build Project is complete in late October, there will be westbound C-D lanes on the north side of US 6 and eastbound C-D lanes on the south side of US 6 to help facilitate traffic flow to and from I-25.

The westbound C-D lanes on the north side of US 6 will run from the I-25 interchange to the Lowell/Perry exit and will collect traffic coming from northbound and southbound I-25 and distribute it to either Federal Boulevard or westbound US 6 about ¼ mile west of Federal.



The eastbound C-D lanes on the south side of US 6 will begin just west of Federal Boulevard and continue to the I-25 interchange to collect eastbound US 6 drivers and distribute them to either direction of I-25. Another C-D lane will connect Federal Boulevard to Bryant Street on the south side of US 6 to provide local access.

### How will they help traffic flow?

These C-D lanes will help traffic flow by separating eastbound and westbound US 6 through traffic from drivers who are destined for I-25 or any of the local arterial streets. C-D lanes separate different traffic flows into distinct paths and they keep drivers in these alignments for a greater distance, eliminating weaving traffic movements that can cause drivers to tap on their brakes and slow down.

## How will my commute change?

As with any new traffic pattern, when these collector-distributor lanes open this fall, drivers will need to pay extra attention to signage and lane assignments, particularly when traveling between I-25 and US 6. Here are a few of the major changes drivers will notice:

**Eastbound US 6 to I-25:** The barrier-separated lanes that will take eastbound US 6 drivers to I-25 will begin just west of the Federal Boulevard bridge, so drivers will need to be prepared to exit much sooner.

**Eastbound US 6 to Bryant Street**: Eastbound US 6 drivers wanting to access Bryant Street will need to exit at Federal Boulevard and continue east through that intersection to access Bryant Street.

**I-25 to westbound US 6**: Drivers making the movement from I-25 to westbound US 6 will follow the collector-distributor lanes on the north side of US 6 and pass beneath Federal Boulevard before merging into westbound US 6 near the Lowell/Perry exit.

**I-25 to Federal Boulevard**: There will be three collector-distributor lanes on the north side of US 6 – two coming from southbound I-25 and one from northbound I-25. Drivers coming from I-25 will need to be in the left C-D lane to access Federal Boulevard.

**Bryant Street to westbound US 6**: Drivers will need to follow the westbound C-D lanes on the north side of US 6 to about ¼ mile west of Federal Boulevard to access the highway.

**Federal Boulevard to eastbound US 6**: Drivers wanting to access eastbound US 6 from Federal Boulevard will use the braided ramp bridge to travel over the eastbound C-D lanes and enter eastbound US 6.

**Federal Boulevard to I-25**: Drivers will no longer merge directly onto eastbound US 6 to reach I-25. Instead, drivers will make this movement by taking the C-D lane between Federal and Bryant Street and veering to the left to merge in with the eastbound C-D lane traffic heading to I-25.

**Federal Boulevard to westbound US 6**: When the project is complete and the westbound C-D lanes are open on the north side of US 6, Federal Boulevard traffic will merge onto westbound US 6 from the right side.

## Are there other examples of collector-distributor lanes in the area?

It will be the end of October before the US 6 Bridges Design-Build Project is substantially complete and the C-D lanes are open, so anyone wanting to get an idea now of how these lanes operate can see a similar alignment along southbound I-25 between Broadway and Washington Street. This C-D lane provides access to local streets along with a longer acceleration distance for drivers entering southbound I-25 from Broadway.



Southbound I-25 collector-distributor lanes between Broadway and Washington St.