
# SANTA FE INTERCHANGE

# ALTERNATIVES - DISPOSITION

# SPLIT DIAMOND




#### DESCRIPTION

- Splits Access To Two Crossroads
- Connects Blakeland Extension & Santa Fe With Parallel Roadways
- Increases T he Number Of Signalized Intersections For Some Movements
- An Extension Of Blakeland Is Required

## DISPOSITION

This Alternative Is Being Eliminated Because Of Indirect T raffic Movements, Increased S ignalization, And An Increase In Conflicting T raffic Movements.

# 3-LEVELDIAMOND(A)



# 3-level diamond (b)

## DESCRIPTION


- Through Traffic Along Santa Fe May Bypass Interchange Intersections
- Reduces Congestion Within Interchange Compared T o Diamond Configuration
- Geometry At Blakeland Intersection Will Require An Additional Traffic Signal Phase
- Potential Impacts T o S tate Park Land

## DISPOSITION

T his Alternative Is Being Eliminated Due To Increased Traffic Signal Phases and Unfamiliar Traffic Movements At The Blakeland Intersection.

# DESCRIPTION

- Through Traffic Along Santa Fe May Bypass Interchange Intersections
- Reduces Congestion Within Interchange Compared To Diamond Configuration



ACOMPANY PBS

Potential Impacts T o S tate Park Land

This Alternative Is Being Carried Forward For Further Analysis Because It Provides Immediate Operational Improvement Along With Potential For Future Capacity Implementation.