

# I-225 Reconfiguration Project

**DID WE  
MAKE  
I-225  
BETTER?**

TRAVEL TIME  
Parker Rd to I-25



am

pm

26%

3 minutes

25%

2 minutes

Source: INRIX

## BENEFIT ANALYSIS

January 2018 - April 2018 Net Total

TIME SAVED

1,476  
hours

Overall total  
time saved

AIR QUALITY

262,581  
lbs

Overall total  
CO<sub>2</sub> decrease

Source: INRIX, Ramp Meter Devices, Traffic Detection Cameras

**HOW IS  
I-25  
IMPACTED?**

TRAVEL TIME  
Hampden Ave to  
Orchard Rd



NB am

19%  
1 min.

SB am

7%  
16 sec.

NB pm

2%  
8 sec.

SB pm

6%  
13 sec.

Source: INRIX

Before Construction Period  
Nov 15, 2016 - Apr 27, 2017

After Construction Period  
Nov 14 2017 - Apr 26, 2018

Tuesday to Thursday  
Excluding Holidays

AM Peak Period: 6am-9am

PM Peak Period: 3pm-7pm

## HOW ARE THE ARTERIALS IMPACTED? (Changes under 5% not shown)

TRAVEL TIME

Hampden Ave WB  
Dartmouth Ave to I-25

am

5%  
26 sec.

Bellevue Ave  
Yosemite to I-25

WB pm

16%  
35 sec.

EB am

12%  
13 sec.



Dam Road SB  
Vaughn Way to  
Union/Dayton St

am

13%  
48 sec.

Orchard Road WB  
DTC Blvd to I-25

am

6%  
5 sec.

Yosemite St NB  
Bellevue Ave to  
Hampden Ave

am

7%  
19 sec.

Source: INRIX

DAILY VOLUMES

Dam Road WB

6%  
366 veh/day

Bellevue Ave WB

6%  
994  
veh/day

Orchard Rd WB

10%  
889 veh/day

Orchard Rd onto I-25 SB

6%  
845 veh/day

Hampden Ave WB  
No Data

Yosemite St  
No Data

Before Construction Period  
Sept 4 - Nov 6, 2017

After Construction Period  
April 2018

Source: Traffic Detection Devices



COLORADO  
Department of  
Transportation

NAVJOY  
Trusted Navigators in Innovation & Technology