


**GENERAL NOTES**

1. ROUNDABOUT APPROACH SPEED REDUCTION SIGNING SHOULD BE IMPLEMENTED WHEN THE POSTED SPEED OF THE HIGHWAY IS 50 MPH OR GREATER.
2. THE SPEED WARNING PLAQUE (W13-1P) AT ENTRY CAN BE SIGNED AT THE ENGINEER'S DISCRETION AS FOLLOWS:
  - SINGLE-LANE ROUNDABOUT: 20-25 MPH
  - MULTI-LANE ROUNDABOUT: 25-30 MPH
  - MINI-ROUNDABOUT: 15-20 MPH
3. SPEED STEP-DOWN SIGNING SHOULD NOT EXCEED 15 MPH. START WITH THE ADVISORY SPEED WARNING PLAQUE AND STEP DOWN IN SPEED AT A MAXIMUM OF 15 MPH AT A TIME UNTIL YOU REACH THE POSTED SPEED OF THE HIGHWAY OUTSIDE OF THE ROUNDABOUT APPROACH.
4. ADJUST SPEED SIGNING PLACEMENT AS NECESSARY TO AVOID CONFLICTS WITH OTHER ROUNDABOUT SIGNING.
5. ALL DISTANCE MEASUREMENTS FOR SIGN PLACEMENT ARE MEASURED FROM ROUNDABOUT ENTRANCE YIELD LINE. SPLITTER ISLAND LENGTH WILL VARY BY DESIGN.
6. A FLASHING BEACON IS NOT REQUIRED IF AN LED FRAME IS PROVIDED WITH THE W2-6 SIGN.

**LEGEND**

- ▲ THESE SIGNS ARE OPTIONAL AND THEIR NEED SHALL BE DETERMINED BY THE ENGINEER.
- ☀ FLASHING BEACON (SEE GENERAL NOTE 6).



<b>Computer File Information</b> Creation Date: 10/09/23 Created By: Stolfus Last Modification Date: Last Modified By: CAD Ver.: ORDesigner CE 2021 - Version 10.10	<table border="1" style="width: 100%; border-collapse: collapse;"> <thead> <tr> <th colspan="3">Sheet Revisions</th> </tr> <tr> <th style="width: 15%;">Date:</th> <th style="width: 55%;">Comments</th> <th style="width: 30%;">Init.</th> </tr> </thead> <tbody> <tr><td> </td><td> </td><td> </td></tr> <tr><td> </td><td> </td><td> </td></tr> <tr><td> </td><td> </td><td> </td></tr> </tbody> </table>	Sheet Revisions			Date:	Comments	Init.										<b>Colorado Department of Transportation</b>  2829 W. Howard Pl. Denver, CO 80204 Phone: 303-757-9654 FAX: 303-757-9219 <b>Traffic Safety &amp; Engineering</b>	<h2 style="margin: 0;">RURAL ROUNDABOUT APPROACH SIGNING</h2>	<b>STANDARD PLAN NO.</b> DS-614-16 <b>Standard Sheet No. 1 of 1</b> Issued by: Traffic & Safety Engineering Branch October 9, 2023
Sheet Revisions																			
Date:	Comments	Init.																	