

# -PEDESTAL POLE CONFIGURATIONS-

# **INDEX**

10" Ø BOLT

1.55" R.

(TYP.)

Ø

Ø

- PEDESTAL POLE INSTALLATION
- PEDESTAL POLE FOUNDATION DETAILS

### **GENERAL NOTES**

- ALL PEDESTAL POLE STEEL SHALL BE ASTM A53 GRB AND SHALL BE HOT DIP GALVANIZED INSIDE AND OUTSIDE ACCORDING TO ASTM A123.
- 2. MOUNTING HARDWARE FOR EACH TRAFFIC SIGNAL WILL BE FURNISHED BY THE MANUFACTURER, INCLUDING POLE PLATES FOR SIDE POLE MOUNTING.
- 3. PEDESTAL POLES SHALL HAVE A FRANGIBLE BASE: AKRON FOUNDRY TB2-17 OR APPROVED EQUAL.
- 4. ALL POLES, PEDESTALS AND CABINETS SHALL BE PLACED A MINIMUM OF 2 FEET OFF THE ROADWAY MEASURED FROM THE EDGE OF SHOULDER OR FACE OF CURB.
- 5. 12-12-12 TRAFFIC SIGNAL FACES FOR RAMP METERING LOCATIONS SHALL BE ALUMINUM TYPE.
- 6. TWO-SECTION 12" RED AND GREEN SIGNAL HEADS SHALL BE "ANGLED IN" AND SHALL BE EQUIPPED WITH VISORS THAT MAY BE POSITIONED TO EITHER SIDE OF THE LENS, ALLOWING ONLY THE FIRST MOTORIST BEHIND THE STOP BAR TO SEE THE SIGNAL INDICATION.
- 7. REGULATORY SIGNING SHALL BE AS SHOWN ON THE PLANS. 24R10-60 FOR LEFT SIDE POLE INSTALLATIONS SHALL CONTAIN A RIGHT-POINTING ARROW 24R10-60 FOR RIGHT SIDE POLE INSTALLATIONS SHALL CONTAIN A LEFT-POINTING ARROW. TYPICAL SPECIAL SIGN MESSAGES ARE "1 VEHICLE PER GREEN" FOR SINGLE-LANE METERED RAMPS, AND "1 VEHICLE PER GREEN EACH LANE" FOR TWO-LANE METERED RAMPS.
- 8. ALL SIGNAL HEADS SHALL BE APPROVED LED TYPE.
- 9. IF THE PLACEMENT OF A PEDESTRIAN PUSH BUTTON ASSEMBLY ON A TRAFFIC SIGNAL MAST POLE WILL NOT BE WITHIN EASY REACH BY PEDESTRIANS (10" OR LESS AND UNOBSTRUCTED IN ACCORDANCE WITH THE AMERICANS WITH DISABILITIES ACT), THEN A SEPARATE PEDESTRIAN PUSH BUTTON POST ASSEMBLY (PPBPA) SHALL BE INSTALLED WITHIN EASY REACH. THE PPBPA SHALL MEET THE PROVISIONS FOUND IN COOT STANDARD PLAN S-614-9 AND "SECTION 4E.08 THROUGH 4E.13 - PEDESTRIAN DETECTORS" IN THE 2009 MUTCD WITH REVISIONS 1 AND 2.

## POLE AND CAISSON INFORMATION

MEMBER	ATTRIBUTES AND LOADS	TRAFFIC SIGNAL POLE	RAMP METERING POLE
	SIZE	6" ¢ SCH 40	4" ¢ SCH 40
POLE	SERVICE MOMENT	14.72 k.ft.	4.23 k.ft.
_	SERVICE SHEAR	0.97 kip	0.45 kip
Z	SIZE	18" Ø	18" Ø
CAISSON	ULT. MOMENT	20.55 k.ft.	5.90 k.ft.
	ULT. SHEAR	1.36 kip	0.63 kip

Computer File Information		
Creation Date: 07-04-12 Initials: LAW		
Last Modification Date: 08-08-13 Initials: DWS	Π,	
Full Path: www.codot.gov/library/traffic/traffic-standards/2012-s-standard-plans		
Drawing File Name: S-614-44 (1 of 2).dgn		
CAD Ver.: MicroStation V8 Scale: Not to Scale Units: English	ו	

	Sheet Revisions		
	Date:	Comments	
$\overline{\mathbf{x}}$			
$\overline{\mathbf{x}}$			
$\odot$			
$\overline{\Sigma}$			
		_	

Colorado Department of Transportation



2829 W Howard Place Denver, Colorado 80204 Phone: 303-757-9543 FAX: 303-757-9219 KCM/RLO Safety & Traffic Engineering

PEDESTAL POLE SIGNALS

STANDARD PLAN NO

S-614-44

Issued By: Safety & Traffic Engineering Branch July 4, 2012

Sheet No. 1 of 2

### FOUNDATION NOTES

- 1. CAISSON CONCRETE SHALL BE AIR ENTRAINED CLASS BZ IN ACCORDANCE WITH SECTION 503 OF THE STANDARD SPECIFICATIONS.
- 2. REINFORCING STEEL SHALL BE GRADE 60 IN ACCORDANCE WITH SECTION 602 OF THE STANDARD SPECIFICATIONS.
- 3. ALL REINFORCING STEEL SHALL BE NON COATED.
- 4. CAISSON CONCRETE MUST HAVE A MINIMUM COMPRESSIVE STRENGTH OF 2,700 PSI BEFORE INSTALLING THE PEDESTAL POLE; VERIFY CONCRETE STRENGTH WITH MATURITY METER.
- 5. CAISSONS SHALL BE PLACED AGAINST UNDISTURBED EARTH.

## **DESIGN DATA**

CAISSON CONCRETE: CLASS BZ CONCRETE: f'c = 4,000 psi REINFORCING STEEL: fy = 60,000 psi

DESIGN WIND SPEED = 90 mph

THE DESIGNS HEREIN ASSUME THAT THE PEDESTAL POLES ARE INSTALLED WITHIN THE ROADWAY PRISM WITH THE FOLLOWING PARAMETERS:

MEDIUM DENSE COHESIONLESS SOIL: SOIL DENSITY, 9 = 110 pcf SDIL V ANGLE = 30° SF = 1.25 FOR FLEXURAL RESISTANCE


MEDIUM STIFF COHESIVE SOIL: SOIL DENSITY, 9 = 110 pcf SOIL COHESION = 750 psf SF = 1.25 FOR FLEXURAL RESISTANCE

CONTACT THE ENGINEER IF ANY OF THE FOLLOWING SOIL CONDITIONS ARE ENCOUNTERED DURING DRILLING:

- (A) SIGNALS WILL NOT BE INSTALLED WITHIN THE ROADWAY PRISM.
- (B) THE SOIL HAS A HIGH ORGANIC CONTENT OR CONSISTS OF SATURATED SILT AND CLAY.
- (C) THE SITE WON'T SUPPORT THE WEIGHT OF THE DRILLING RIG.
- (D) THE FOUNDATION SOILS ARE NOT HOMOGENOUS.
- (E) FIRM BEDROCK IS ENCOUNTERED.

UNFACTORED GROUP LOAD II COMBINATION LOADS FOR THE DESIGN OF POLES WERE GENERATED WITH THE STANDARD SPECIFICATIONS FOR STRUCTURAL SUPPORTS FOR HIGHWAY SIGNS, LUMINAIRES, AND TRAFFIC SIGNALS, 5TH EDITION INCLUDING THE 2010 & 2011 INTERIMS.

LOAD FACTORS FOR GENERATING ULTIMATE CAISSON LOADS ARE FOR THE STRENGTH III LOAD COMBINATION AS SPECIFIED IN THE 6TH EDITION OF THE AASHTO LRFD BRIDGE DESIGN SPECIFICATIONS.



	TRAFFIC SIGNAL PEDESTAL POLE CAISSON	RAMP METERING PEDESTAL POLE CAISSON		
"["	4'-8"	3'-2"		
PAY LENGTH	5'-0''	3'-6"		

CAISSON DATA TABLE

Computer File Information			
	nitials: LAW		
Last Modification Date: 08-08-13	nitials: DWS		
Full Path: www.codot.gov/library/traffic/traffic-standards/2012-s-standard-plans			
Drawing File Name: S-614-44 (2 of 2).dgn			
CAD Ver.: MicroStation V8 Scale: Not to Scale	Units: English		

	Sheet Revisions		
	Date:	Comments	
$\mathbb{R}$ -1	06/17/16	REVISE NOTES 3 AND 4	
(R-X)			
$\overline{\mathbb{R}-X}$			
(R-X)			

Colorado Department of Transportation

KCM/RLO



PEDESTAL POLE SIGNALS

STANDARD PLAN NO S-614-44

Issued By: Safety & Traffic Engineering Branch July 4, 2012

Sheet No. 2 of 2